

START

Title: OFFICIAL GAZETTE OF THE UNITED STATES PATENT AND TRADEMARK
OFFICE. PATENTS.

Volume: 1193

Issues: 4 - 5
PATENT: 5,586,339-5,590,419

Date: , DECEMBER 24 - DECEMBER 31, 1996

UMI Number: 10426.00

Note:

REEL: 17

UMI
300 North Zeeb Road
Ann Arbor, MI 48103

U·M·I

THE PAPER AND INK USED IN THE ORIGINAL
MATERIAL AFFECT THE QUALITY OF THE
MICRO-EDITION. THIS REPRODUCTION IS
MADE FROM THE BEST COPY AVAILABLE.

VOL
11 93

ISS
4

DE
24

1996

UMI

OFFICIAL GAZETTE

THE GOVERNMENT OF SINGAPORE

WEEKLY

NUMBER 24 1996



PUBLISHED WEEKLY BY AUTHORITY OF GOVERNMENT

VOL
11 93

ISS
4

DE
24

1996

UMI

OFFICIAL GAZETTE of the
UNITED STATES PATENT AND TRADEMARK OFFICE
December 24, 1996 Volume 1193 Number 4

CONTENTS

		Page
Patent and Trademark Office Notices		
Patent Cooperation Treaty (PCT) Information	1193	OG 71
Notice of Maintenance Fees Payable	1193	OG 71
Notice of Expiration of Patents Due to Failure to Pay Maintenance Fee	1193	OG 72
Patents Reinstated Due To The Acceptance of a Late Maintenance Fee From 10/18/96	1193	OG 79
Patents Reinstated Due To The Acceptance of a Late Maintenance Fee From 10/25/96	1193	OG 79
Reissue Applications Filed	1193	OG 80
Requests for Reexaminations Filed	1193	OG 81
Notice of Expiration of Trademark Registrations Due to Failure to Renew	1193	OG 81
Service by Publication	1193	OG 83
Certificate of Correction	1193	OG 83
Summary of Final Decisions Issued by the Trademark Trial and Appeal Board	1193	OG 84
Special Boxes for Mail	1193	OG 85
Reference Collections of U.S. Patents Available for Public Use in		
Patent Depository Libraries	1193	OG 87
Patent Examining Corps	1193	OG 89
Condition of Trademark Applications	1193	OG 90
Reexaminations		2479
Reissue Patents Granted (35,408)		2481
Plant Patents Granted (9,757)		2483
Patents Granted		
General and Mechanical (5,586,339)		2485
Chemical (5,586,992)		2717
Electrical (5,587,518)		2867
Design Patents Granted (376,679)		3083
Index of Patentees		PI 1
Indices of Reissue, Reexaminations, Design and Plant Patents		PI 82
Classification of		
Patents (Including Reissues and Reexaminations)		PI 89
Designs and Plants Applications		PI 93
Geographical Index of Residence of Inventors		
Patents (Including Reissues and Reexaminations)		PI 95
Designs and Plants Applications		PI 97
Change of Address Form		PI 99
Subscription Order Form		PI 101

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C. 20402, to whom all subscriptions should be made payable and all communications addressed. VISA or MasterCard may be used for telephone orders, (202)-512-1800.
THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly. Stock No. 703-033-00000-8
THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly. Stock No. 703-034-00000-4
PATENT AND TRADEMARK OFFICE NOTICES, issued weekly. Stock No. 703-035-00000-1
GENERAL INFORMATION concerning PATENTS. Stock No. 003-004-00661-7

COPIES OF PATENTS are furnished by the Patent and Trademark Office at \$3.00 each; PLANT PATENTS in color, \$12.00 each; copies of TRADEMARKS at \$3.00 each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C. 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S.P.T.O.

For sale by the U.S. Government Printing Office
Superintendent of Documents, Mail Stop: SSOP, Washington, DC 20402-9328

VOL
11 93

ISS
4

DE
24
1996

UMI

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty (PCT) Information

For information concerning PCT member countries, see the notice appearing in the *Official Gazette* at 1190 O.G. 3, on September 3, 1996.

For use of the European Patent Office as an International Searching Authority for international applications filed in the United States Receiving Office, see the notice appearing in the *Official Gazette* at 1022 O.G. 52, on September 28, 1982.

For use of the European Patent Office as an International Preliminary Examining Authority for international applications filed in the United States Receiving Office, see the notices appearing in the *Official Gazette* at 1080 O.G. 2, on July 7, 1987, and at 1091 O.G. 2, on June 7, 1988. There is no longer a limit on the number of such international applications accepted for international preliminary examination by the European Patent Office; see the notice appearing at 1116 O.G. 32, on July 17, 1990.

The search fee of the European Patent Office was changed, effective July 1, 1996, due to a change in the exchange rate of the U.S. dollar with regard to the German mark, and was announced in the *Official Gazette* at 1187 O.G. 73, on June 25, 1996.

International fees were changed, effective on January 1, 1996, due to a change in the exchange rate of the U.S. dollar with regard to the Swiss franc, and were announced in the *Official Gazette* at 1181 O.G. 49, on December 19, 1995.

Certain domestic PCT fees and charges for International Search and Preliminary Examination were changed, effective October 1, 1996, and were announced in the *Official Gazette* at 1189 O.G. 62, on August 20, 1996.

The schedule of PCT fees (in U.S. dollars), effective October 1, 1996, is as follows:

International Application (PCT Chapter I) fees:

Transmittal fee.....	230.00
Search Fee	
U.S. Patent and Trademark Office (USPTO) as International Searching Authority (ISA)	
— No corresponding prior U.S. national application filed.....	680.00
— Corresponding prior U.S. national application filed.....	440.00
— Supplemental search fee, per additional invention (payable only upon invitation)	200.00
European Patent Office as ISA.....	1585.00
International fees	
Basic fee	677.00
Basic supplemental fee (for each page over 30).....	13.00
Designation fee per country or region	
— For the first 11 national or regional offices designated.....	164.00
— For each designation in excess of 11 offices	No Charge
Precautionary designation fee and confirmation fee for each precautionary designation confirmed (PCT Rule 15.5)	
— Designation fee.....	164.00
— Confirmation fee	82.00

International Application (PCT Chapter II) fees associated with filing a Demand for Preliminary Examination:

Handling fee	207.00
Preliminary examination fee	
USPTO as International Preliminary Examining Authority (IPEA)	
— USPTO was ISA in PCT Chapter I	480.00

— Additional examination fee, per additional invention (payable only upon invitation).....	140.00
— USPTO was not ISA in PCT Chapter I	730.00
— Additional examination fee, per additional invention (payable only upon invitation)	260.00

U.S. National Stage Fees	Small Entity	Regular
Basic National fee		
USPTO was IPEA		
— All claims presented satisfied provisions of PCT Article 33(2) to (4)	48.00	96.00
— All claims presented did not satisfy provisions of PCT Article 33(2) to (4)	350.00	700.00
USPTO was ISA but not IPEA.....	385.00	770.00
USPTO was neither ISA nor IPEA		
— Search report has not been prepared by the European Patent Office or the Japanese Patent Office	520.00	1040.00
— Search report has been prepared by the European Patent Office or the Japanese Patent Office	455.00	910.00

Other National fees:

— For each independent claim in excess of 3.....	40.00	80.00
— For each claim in excess of 20.....	11.00	22.00
— For each application containing a multiple dependent claim.....	130.00	260.00
— Surcharge for filing oath or declaration after the time limit applicable under PCT Article 22 or 39(1)	65.00	130.00
— Processing fee for filing English translation after the time limit applicable under PCT Article 22 or 39(1).....	130.00	130.00

Sept. 10, 1996

BRUCE A. LEHMAN
Assistant Secretary of Commerce and
Commissioner of Patents and Trademarks

Notice of Maintenance Fees Payable

Title 37 Code of Federal Regulations (CFR), Section 1.362(d) provides that maintenance fees may be paid without surcharge for the six-month period beginning 3, 7, and 11 years after the date of issue of patents based on applications filed on or after Dec. 12, 1980. An additional six-month grace period is provided by 35 U.S.C. 41(b) and 37 CFR 1.362(e) for payment of the maintenance fee with the surcharge set forth in 37 CFR 1.20(h), as amended effective Dec. 16, 1991. If the maintenance fee is not paid in the patent requiring such payment the patent will expire on the 4th, 8th, or 12th anniversary of the grant.

Attention is drawn to the patents which were issued on December 21, 1993 for which maintenance fees due at 3 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 5,271,099 through 5,272,769
Reissue Patents based on the above identified patents.

Attention is drawn to the patents which were issued on December 19, 1989 for which maintenance fees due at 7 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 4,887,315 through 4,888,824
Reissue Patents based on the above identified patents.

Attention is drawn to the patents which were issued on December 17, 1985 for which maintenance fees due at 11 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 4,558,466 through 4,559,645
Reissue Patents based on the above identified patents.

No maintenance fees are required for design or plant patents.

Payments of maintenance fees in patents should be directed to "Commissioner of Patents and Trademarks, Box M. Fee, Washington, D.C. 20231."

For patents based on applications filed on or after Dec. 12, 1980, but before Aug. 27, 1982, patent owners must establish small entity status according to 37 CFR 1.27 if they have not done so and if they wish to pay the small entity amount.

The current amounts of the maintenance fees due at 3 years and six months, 7 years and six months, and 11 years and six months are set forth in 37 CFR 1.20(e)-(g), as amended Oct. 1, 1996, which are reproduced below:

37 CFR § 1.20 Post-issuance fees

(e) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980, in force beyond 4 years; the fee is due by three years and six months after the original grant:

By a small entity (§ 1.9(f))\$510.00
By other than a small entity\$1,020.00

(f) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980 in force beyond 8 years; the fee is due by seven years and six months after the original grant:

By a small entity (§ 1.9(f))\$1,025.00
By other than a small entity\$2,050.00

(g) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980 in force beyond 12 years; the fee is due by eleven years and six months after the original grant:

By a small entity (§ 1.9(f))\$1,540.00
By other than a small entity\$3,080.00

The amount of the surcharge for paying the maintenance fee during the grace period or after expiration of the patent are set forth in 37 CFR 1.20(h), and (i) which are reproduced below:

(h) Surcharge for paying a maintenance fee during the 6 month grace period following the expiration of three years and six months, seven years and six months, and eleven years and six months after the date of the original grant of a patent based on an application filed on or after Dec. 12, 1980:

By a small entity (§ 1.9(f))\$65.00
By other than a small entity\$130.00

(i) Surcharge for accepting a maintenance fee after expiration of a patent for non-timely payment of a maintenance fee where the delay is shown to the satisfaction of the Commissioner to have been:

(1) unavoidable\$680.00
(2) unintentional\$1,600.00

Notice of Expiration of Patents
Due to Failure to Pay Maintenance Fee

35 U.S.C. 41 and 37 CFR 1.362(g) provide that if the required maintenance fee and any applicable surcharge are not paid in a patent requiring such payment, the patent will expire at the end of the 4th, 8th or 12th anniversary of the grant of the patent depending on the first maintenance fee which was not paid.

According to the records of the Office, the patents listed below have expired due to failure to pay the required maintenance fee and any applicable surcharge.

PATENTS WHICH EXPIRED October 16, 1996
DUE TO FAILURE TO PAY MAINTENANCE FEES

Patent Number	Serial Number	Issue Date
Re. 32,608 (4,477,035)	06/913,719 (06/462,558)	02/23/88 (10/16/84)
Re. 32,630 (4,477,687)	06/727,001 (06/501,282)	03/29/88 (10/16/84)
Re. 33,039 (4,476,591)	06/839,695 (06/528,337)	08/29/89 (10/16/84)
Re. 33,044 (4,476,799)	06/919,233 (06/428,304)	09/05/89 (10/16/84)
4,476,593	06/406,353	10/16/84
4,476,595	06/409,284	10/16/84
4,476,599	06/395,410	10/16/84
4,476,606	06/508,022	10/16/84
4,476,607	06/428,650	10/16/84
4,476,621	06/462,739	10/16/84
4,476,622	06/573,222	10/16/84
4,476,627	06/391,472	10/16/84
4,476,632	06/402,944	10/16/84
4,476,636	06/378,478	10/16/84
4,476,643	06/473,387	10/16/84
4,476,652	06/402,331	10/16/84
4,476,662	06/315,849	10/16/84
4,476,665	06/326,912	10/16/84
4,476,667	06/482,426	10/16/84
4,476,669	06/432,855	10/16/84
4,476,674	06/387,296	10/16/84
4,476,675	06/355,662	10/16/84
4,476,679	06/234,177	10/16/84
4,476,684	06/476,825	10/16/84
4,476,688	06/454,424	10/16/84
4,476,701	06/380,679	10/16/84
4,476,706	06/340,074	10/16/84
4,476,709	06/408,896	10/16/84
4,476,717	06/266,563	10/16/84
4,476,719	06/377,425	10/16/84
4,476,720	06/387,950	10/16/84
4,476,729	06/384,367	10/16/84
4,476,734	06/472,900	10/16/84
4,476,741	06/383,495	10/16/84
4,476,748	06/331,392	10/16/84
4,476,749	06/579,288	10/16/84
4,476,764	06/409,737	10/16/84
4,476,765	06/498,086	10/16/84
4,476,772	06/439,065	10/16/84
4,476,781	06/430,761	10/16/84
4,476,782	06/385,773	10/16/84
4,476,789	06/413,516	10/16/84
4,476,791	06/498,006	10/16/84
4,476,793	06/325,620	10/16/84
4,476,805	06/260,829	10/16/84
4,476,814	06/474,564	10/16/84
4,476,815	06/431,264	10/16/84
4,476,816	06/436,246	10/16/84
4,476,818	06/543,542	10/16/84
4,476,824	06/318,801	10/16/84
4,476,827	06/459,965	10/16/84
4,476,836	06/455,827	10/16/84
4,476,837	06/447,535	10/16/84
4,476,841	06/499,459	10/16/84
4,476,844	06/419,305	10/16/84

Patent Number	Serial Number	Issue Date	4,477,215	06/321,574	10/16/84
4,476,845	06/428,834	10/16/84	4,477,221	06/338,055	10/16/84
4,476,853	06/424,868	10/16/84	4,477,224	06/417,338	10/16/84
4,476,857	06/458,035	10/16/84	4,477,225	06/344,105	10/16/84
4,476,873	06/415,042	10/16/84	4,477,232	06/456,597	10/16/84
4,476,888	06/400,669	10/16/84	4,477,234	06/416,996	10/16/84
4,476,902	06/408,010	10/16/84	4,477,249	06/489,793	10/16/84
4,476,905	06/526,509	10/16/84	4,477,254	06/450,755	10/16/84
4,476,916	06/287,091	10/16/84	4,477,264	06/480,448	10/16/84
4,476,917	06/279,070	10/16/84	4,477,276	06/421,331	10/16/84
4,476,918	06/392,441	10/16/84	4,477,280	06/452,292	10/16/84
4,476,921	06/363,142	10/16/84	4,477,281	06/434,489	10/16/84
4,476,923	06/359,477	10/16/84	4,477,294	06/489,632	10/16/84
4,476,926	06/363,765	10/16/84	4,477,295	06/408,420	10/16/84
4,476,945	06/465,407	10/16/84	4,477,301	06/493,691	10/16/84
4,476,947	06/277,521	10/16/84	4,477,302	06/505,430	10/16/84
4,476,948	06/392,068	10/16/84	4,477,303	06/345,357	10/16/84
4,476,959	06/388,691	10/16/84	4,477,304	06/510,046	10/16/84
4,476,960	06/406,617	10/16/84	4,477,306	06/402,466	10/16/84
4,476,963	06/325,643	10/16/84	4,477,309	06/430,177	10/16/84
4,476,969	06/367,509	10/16/84	4,477,311	06/561,967	10/16/84
4,476,974	06/313,005	10/16/84	4,477,312	06/498,668	10/16/84
4,476,978	06/381,490	10/16/84	4,477,316	06/351,302	10/16/84
4,476,981	06/372,660	10/16/84	4,477,317	06/547,194	10/16/84
4,476,982	06/433,245	10/16/84	4,477,322	06/499,135	10/16/84
4,476,983	06/358,868	10/16/84	4,477,328	06/354,830	10/16/84
4,476,992	06/425,556	10/16/84	4,477,340	06/416,286	10/16/84
4,476,996	06/348,350	10/16/84	4,477,352	06/475,148	10/16/84
4,476,998	06/357,592	10/16/84	4,477,357	06/529,483	10/16/84
4,477,002	06/404,768	10/16/84	4,477,373	06/385,155	10/16/84
4,477,003	06/345,288	10/16/84	4,477,374	06/394,530	10/16/84
4,477,011	06/416,502	10/16/84	4,477,378	06/416,513	10/16/84
4,477,012	06/449,149	10/16/84	4,477,382	06/451,826	10/16/84
4,477,013	06/529,925	10/16/84	4,477,385	06/463,164	10/16/84
4,477,020	06/296,349	10/16/84	4,477,393	06/384,847	10/16/84
4,477,022	06/351,560	10/16/84	4,477,394	06/489,367	10/16/84
4,477,027	06/378,453	10/16/84	4,477,395	06/368,388	10/16/84
4,477,028	06/382,483	10/16/84	4,477,396	06/328,890	10/16/84
4,477,032	06/395,037	10/16/84	4,477,399	06/389,032	10/16/84
4,477,038	06/427,034	10/16/84	4,477,400	06/577,335	10/16/84
4,477,041	06/409,684	10/16/84	4,477,404	06/376,978	10/16/84
4,477,053	06/577,637	10/16/84	4,477,407	06/467,823	10/16/84
4,477,054	06/431,312	10/16/84	4,477,409	06/229,767	10/16/84
4,477,062	06/342,607	10/16/84	4,477,418	06/525,716	10/16/84
4,477,063	06/285,541	10/16/84	4,477,425	06/561,788	10/16/84
4,477,075	06/267,418	10/16/84	4,477,430	06/404,822	10/16/84
4,477,076	06/254,957	10/16/84	4,477,431	06/225,005	10/16/84
4,477,079	06/408,300	10/16/84	4,477,433	06/348,134	10/16/84
4,477,089	06/401,926	10/16/84	4,477,436	06/484,963	10/16/84
4,477,099	06/450,050	10/16/84	4,477,437	06/347,871	10/16/84
4,477,100	06/326,341	10/16/84	4,477,445	06/469,042	10/16/84
4,477,103	06/375,170	10/16/84	4,477,450	06/471,837	10/16/84
4,477,106	06/431,872	10/16/84	4,477,451	06/482,004	10/16/84
4,477,108	06/378,840	10/16/84	4,477,453	06/423,104	10/16/84
4,477,109	06/288,129	10/16/84	4,477,456	06/370,137	10/16/84
4,477,111	06/320,200	10/16/84	4,477,461	06/426,893	10/16/84
4,477,124	06/332,735	10/16/84	4,477,463	06/376,650	10/16/84
4,477,125	06/419,685	10/16/84	4,477,468	06/447,037	10/16/84
4,477,132	06/433,064	10/16/84	4,477,473	06/457,326	10/16/84
4,477,134	06/576,788	10/16/84	4,477,476	06/453,826	10/16/84
4,477,136	06/437,688	10/16/84	4,477,483	06/478,469	10/16/84
4,477,140	06/464,238	10/16/84	4,477,484	06/448,574	10/16/84
4,477,143	06/446,806	10/16/84	4,477,486	06/579,300	10/16/84
4,477,146	06/244,527	10/16/84	4,477,490	06/470,156	10/16/84
4,477,157	06/393,726	10/16/84	4,477,491	06/422,475	10/16/84
4,477,158	06/311,663	10/16/84	4,477,506	06/391,874	10/16/84
4,477,174	06/396,104	10/16/84	4,477,511	06/418,206	10/16/84
4,477,175	06/450,868	10/16/84	4,477,518	06/307,182	10/16/84
4,477,177	06/466,401	10/16/84	4,477,523	06/536,825	10/16/84
4,477,183	06/445,079	10/16/84	4,477,532	06/493,798	10/16/84
4,477,187	06/342,539	10/16/84	4,477,544	06/539,644	10/16/84
4,477,192	06/392,401	10/16/84	4,477,547	06/455,998	10/16/84
4,477,193	06/447,527	10/16/84	4,477,548	06/562,043	10/16/84
4,477,197	06/574,524	10/16/84	4,477,553	06/566,778	10/16/84
4,477,199	06/345,301	10/16/84	4,477,554	06/545,434	10/16/84
4,477,202	06/541,452	10/16/84	4,477,566	06/381,777	10/16/84
4,477,210	06/425,082	10/16/84	4,477,568	06/419,800	10/16/84
4,477,213	06/530,614	10/16/84	4,477,569	06/349,905	10/16/84
			4,477,572	06/383,361	10/16/84

Patent Number	Serial Number	Issue Date	4,477,891	06/357,595	10/16/84
4,477,586	06/464,095	10/16/84	4,477,893	06/411,382	10/16/84
4,477,594	06/450,341	10/16/84	4,477,894	06/406,883	10/16/84
4,477,595	06/489,562	10/16/84	4,477,902	06/389,820	10/16/84
4,477,596	06/371,311	10/16/84	4,477,907	06/374,472	10/16/84
4,477,597	06/307,829	10/16/84	4,477,908	06/357,501	10/16/84
4,477,599	06/439,981	10/16/84	4,477,915	06/447,085	10/16/84
4,477,602	06/517,087	10/16/84	4,477,916	06/357,245	10/16/84
4,477,605	06/477,194	10/16/84	4,477,921	06/325,286	10/16/84
4,477,606	06/542,859	10/16/84	4,477,925	06/329,776	10/16/84
4,477,616	06/471,913	10/16/84	4,477,042	07/085,639	10/11/88
4,477,620	06/585,439	10/16/84	4,477,047	06/731,533	10/11/88
4,477,625	06/481,528	10/16/84	4,477,048	07/118,181	10/11/88
4,477,630	06/473,459	10/16/84	4,477,049	07/039,109	10/11/88
4,477,633	06/561,523	10/16/84	4,477,053	07/150,834	10/11/88
4,477,634	06/355,656	10/16/84	4,477,057	07/057,369	10/11/88
4,477,635	06/336,637	10/16/84	4,477,061	07/029,817	10/11/88
4,477,640	06/422,775	10/16/84	4,477,066	07/053,825	10/11/88
4,477,643	06/602,256	10/16/84	4,477,072	06/939,832	10/11/88
4,477,646	06/525,866	10/16/84	4,477,074	07/070,928	10/11/88
4,477,649	06/479,066	10/16/84	4,477,076	06/779,361	10/11/88
4,477,650	06/479,057	10/16/84	4,477,083	07/028,442	10/11/88
4,477,651	06/501,477	10/16/84	4,477,090	07/107,444	10/11/88
4,477,656	06/572,271	10/16/84	4,477,096	06/947,758	10/11/88
4,477,664	06/351,256	10/16/84	4,477,101	07/120,756	10/11/88
4,477,666	06/348,272	10/16/84	4,477,108	07/077,502	10/11/88
4,477,667	06/332,251	10/16/84	4,477,116	07/090,219	10/11/88
4,477,670	06/451,139	10/16/84	4,477,117	06/823,046	10/11/88
4,477,677	06/469,676	10/16/84	4,477,119	06/900,149	10/11/88
4,477,680	06/439,495	10/16/84	4,477,122	07/072,636	10/11/88
4,477,682	06/451,788	10/16/84	4,477,123	07/106,594	10/11/88
4,477,685	06/409,819	10/16/84	4,477,126	07/083,366	10/11/88
4,477,691	06/466,909	10/16/84	4,477,128	07/116,632	10/11/88
4,477,699	06/356,702	10/16/84	4,477,131	07/142,251	10/11/88
4,477,702	06/362,467	10/16/84	4,477,133	07/106,636	10/11/88
4,477,703	06/409,963	10/16/84	4,477,136	07/065,202	10/11/88
4,477,705	06/383,695	10/16/84	4,477,137	07/062,288	10/11/88
4,477,707	06/444,273	10/16/84	4,477,139	07/019,330	10/11/88
4,477,708	06/398,812	10/16/84	4,477,140	06/893,682	10/11/88
4,477,712	06/371,708	10/16/84	4,477,142	06/820,857	10/11/88
4,477,714	06/459,107	10/16/84	4,477,143	07/061,878	10/11/88
4,477,715	06/399,337	10/16/84	4,477,144	07/033,741	10/11/88
4,477,719	06/454,532	10/16/84	4,477,167	06/920,456	10/11/88
4,477,720	06/333,083	10/16/84	4,477,168	07/052,426	10/11/88
4,477,721	06/341,955	10/16/84	4,477,169	07/151,824	10/11/88
4,477,723	06/318,094	10/16/84	4,477,171	06/931,464	10/11/88
4,477,730	06/438,127	10/16/84	4,477,174	07/155,488	10/11/88
4,477,731	06/505,007	10/16/84	4,477,182	07/021,600	10/11/88
4,477,732	06/363,858	10/16/84	4,477,200	06/937,850	10/11/88
4,477,740	06/390,721	10/16/84	4,477,206	07/084,264	10/11/88
4,477,742	06/527,300	10/16/84	4,477,208	07/041,801	10/11/88
4,477,744	06/423,780	10/16/84	4,477,213	07/027,479	10/11/88
4,477,747	06/468,231	10/16/84	4,477,216	07/018,384	10/11/88
4,477,749	06/350,486	10/16/84	4,477,217	07/145,128	10/11/88
4,477,768	06/404,113	10/16/84	4,477,220	07/014,278	10/11/88
4,477,773	06/389,064	10/16/84	4,477,221	06/946,413	10/11/88
4,477,777	06/357,865	10/16/84	4,477,222	07/031,901	10/11/88
4,477,783	06/409,429	10/16/84	4,477,237	07/078,432	10/11/88
4,477,803	06/317,090	10/16/84	4,477,238	07/030,769	10/11/88
4,477,804	06/353,751	10/16/84	4,477,242	07/045,657	10/11/88
4,477,817	06/396,280	10/16/84	4,477,243	06/801,718	10/11/88
4,477,828	06/433,792	10/16/84	4,477,245	07/057,753	10/11/88
4,477,830	06/434,082	10/16/84	4,477,254	07/144,196	10/11/88
4,477,833	06/489,151	10/16/84	4,477,256	07/004,162	10/11/88
4,477,840	06/366,083	10/16/84	4,477,267	07/030,660	10/11/88
4,477,844	06/346,144	10/16/84	4,477,272	07/069,294	10/11/88
4,477,848	06/414,533	10/16/84	4,477,274	07/047,416	10/11/88
4,477,851	06/386,048	10/16/84	4,477,275	07/092,057	10/11/88
4,477,855	06/396,376	10/16/84	4,477,277	07/072,427	10/11/88
4,477,857	06/453,645	10/16/84	4,477,278	07/025,044	10/11/88
4,477,858	06/472,109	10/16/84	4,477,279	07/097,698	10/11/88
4,477,860	06/533,182	10/16/84	4,477,280	07/180,094	10/11/88
4,477,873	06/373,254	10/16/84	4,477,282	07/024,057	10/11/88
4,477,877	06/272,290	10/16/84	4,477,285	07/144,506	10/11/88
4,477,878	06/299,258	10/16/84	4,477,289	07/063,536	10/11/88
4,477,880	06/311,083	10/16/84	4,477,298	07/042,774	10/11/88
4,477,887	06/300,430	10/16/84	4,477,299	06/863,331	10/11/88
			4,477,300	07/050,416	10/11/88
			4,477,301	07/025,047	10/11/88

Patent Number	Serial Number	Issue Date	4,776,604	07/135,493	10/11/88
4,776,311	07/070,670	10/11/88	4,776,610	06/936,223	10/11/88
4,776,315	07/114,875	10/11/88	4,776,618	07/085,911	10/11/88
4,776,319	07/015,140	10/11/88	4,776,629	07/106,226	10/11/88
4,776,322	06/898,050	10/11/88	4,776,634	07/052,785	10/11/88
4,776,324	07/040,365	10/11/88	4,776,635	07/067,175	10/11/88
4,776,327	06/893,288	10/11/88	4,776,638	07/072,679	10/11/88
4,776,329	06/778,232	10/11/88	4,776,640	07/045,819	10/11/88
4,776,332	07/074,368	10/11/88	4,776,643	06/750,551	10/11/88
4,776,342	06/916,063	10/11/88	4,776,648	07/039,716	10/11/88
4,776,346	06/863,596	10/11/88	4,776,653	07/109,470	10/11/88
4,776,349	06/914,867	10/11/88	4,776,654	07/035,573	10/11/88
4,776,355	06/877,803	10/11/88	4,776,658	07/079,767	10/11/88
4,776,359	06/806,447	10/11/88	4,776,662	06/903,691	10/11/88
4,776,365	07/028,875	10/11/88	4,776,667	06/387,896	10/11/88
4,776,372	07/042,289	10/11/88	4,776,670	07/130,364	10/11/88
4,776,374	07/089,822	10/11/88	4,776,684	06/891,643	10/11/88
4,776,380	07/074,615	10/11/88	4,776,685	07/058,848	10/11/88
4,776,381	06/878,672	10/11/88	4,776,686	06/782,487	10/11/88
4,776,382	06/499,278	10/11/88	4,776,689	06/873,185	10/11/88
4,776,387	06/533,468	10/11/88	4,776,692	06/779,572	10/11/88
4,776,393	07/011,950	10/11/88	4,776,696	07/028,564	10/11/88
4,776,397	06/915,380	10/11/88	4,776,698	06/893,431	10/11/88
4,776,398	07/031,736	10/11/88	4,776,700	07/102,704	10/11/88
4,776,405	07/054,393	10/11/88	4,776,707	06/942,544	10/11/88
4,776,406	06/906,914	10/11/88	4,776,711	06/878,825	10/11/88
4,776,412	07/150,283	10/11/88	4,776,712	06/789,619	10/11/88
4,776,420	07/025,953	10/11/88	4,776,713	06/820,564	10/11/88
4,776,432	07/155,296	10/11/88	4,776,716	07/025,012	10/11/88
4,776,436	07/051,091	10/11/88	4,776,722	07/016,569	10/11/88
4,776,443	06/890,367	10/11/88	4,776,724	07/088,730	10/11/88
4,776,444	07/003,457	10/11/88	4,776,726	07/142,514	10/11/88
4,776,448	07/103,080	10/11/88	4,776,727	07/058,970	10/11/88
4,776,449	07/047,691	10/11/88	4,776,728	07/024,532	10/11/88
4,776,450	06/878,975	10/11/88	4,776,730	07/036,297	10/11/88
4,776,452	07/048,383	10/11/88	4,776,732	06/423,501	10/11/88
4,776,454	07/089,049	10/11/88	4,776,735	07/105,487	10/11/88
4,776,455	07/022,703	10/11/88	4,776,741	06/898,577	10/11/88
4,776,457	07/076,795	10/11/88	4,776,742	06/758,371	10/11/88
4,776,459	06/948,363	10/11/88	4,776,750	07/041,881	10/11/88
4,776,470	07/139,988	10/11/88	4,776,752	07/021,273	10/11/88
4,776,473	07/070,048	10/11/88	4,776,763	07/127,701	10/11/88
4,776,476	07/105,377	10/11/88	4,776,764	07/033,230	10/11/88
4,776,481	07/054,647	10/11/88	4,776,767	07/048,612	10/11/88
4,776,482	07/008,032	10/11/88	4,776,769	07/076,157	10/11/88
4,776,499	07/009,632	10/11/88	4,776,771	07/089,225	10/11/88
4,776,500	06/501,892	10/11/88	4,776,772	07/081,411	10/11/88
4,776,503	07/023,516	10/11/88	4,776,774	06/884,370	10/11/88
4,776,512	07/069,106	10/11/88	4,776,775	07/148,772	10/11/88
4,776,513	07/051,241	10/11/88	4,776,782	06/481,421	10/11/88
4,776,516	07/106,402	10/11/88	4,776,784	07/023,013	10/11/88
4,776,519	07/043,952	10/11/88	4,776,788	07/064,553	10/11/88
4,776,520	07/048,316	10/11/88	4,776,790	07/093,061	10/11/88
4,776,522	06/912,546	10/11/88	4,776,791	07/142,988	10/11/88
4,776,523	07/091,790	10/11/88	4,776,792	07/015,836	10/11/88
4,776,525	07/017,107	10/11/88	4,776,793	07/097,756	10/11/88
4,776,526	07/089,006	10/11/88	4,776,795	07/021,175	10/11/88
4,776,528	07/092,970	10/11/88	4,776,797	07/044,465	10/11/88
4,776,532	07/010,679	10/11/88	4,776,798	06/805,626	10/11/88
4,776,538	07/004,450	10/11/88	4,776,801	07/124,900	10/11/88
4,776,541	07/021,569	10/11/88	4,776,803	06/935,238	10/11/88
4,776,543	06/920,065	10/11/88	4,776,804	07/012,703	10/11/88
4,776,545	07/081,761	10/11/88	4,776,811	07/037,924	10/11/88
4,776,548	07/075,329	10/11/88	4,776,816	06/455,456	10/11/88
4,776,551	07/082,342	10/11/88	4,776,818	06/946,536	10/11/88
4,776,556	06/926,862	10/11/88	4,776,826	07/167,537	10/11/88
4,776,558	07/073,313	10/11/88	4,776,836	07/056,695	10/11/88
4,776,565	07/132,325	10/11/88	4,776,841	06/906,138	10/11/88
4,776,567	07/129,600	10/11/88	4,776,845	06/879,332	10/11/88
4,776,578	07/091,872	10/11/88	4,776,852	06/934,485	10/11/88
4,776,580	07/032,481	10/11/88	4,776,854	06/844,785	10/11/88
4,776,581	06/889,827	10/11/88	4,776,857	06/933,649	10/11/88
4,776,584	07/083,175	10/11/88	4,776,858	07/026,385	10/11/88
4,776,585	07/030,664	10/11/88	4,776,864	07/074,917	10/11/88
4,776,587	07/041,395	10/11/88	4,776,866	07/042,114	10/11/88
4,776,589	07/007,653	10/11/88	4,776,867	07/044,673	10/11/88
4,776,590	06/855,139	10/11/88	4,776,869	07/053,617	10/11/88
4,776,598	06/887,267	10/11/88	4,776,870	06/762,744	10/11/88
			4,776,872	06/781,964	10/11/88

Patent Number	Serial Number	Issue Date	4,777,208	06/822,991	10/11/88
4,776,873	07/009,001	10/11/88	4,777,209	06/708,754	10/11/88
4,776,875	06/844,472	10/11/88	4,777,212	06/933,249	10/11/88
4,776,880	07/150,592	10/11/88	4,777,215	07/107,109	10/11/88
4,776,881	06/881,320	10/11/88	4,777,221	07/015,639	10/11/88
4,776,884	07/052,020	10/11/88	4,777,225	07/117,824	10/11/88
4,776,885	07/047,020	10/11/88	4,777,234	06/899,680	10/11/88
4,776,892	06/899,993	10/11/88	4,777,236	07/095,078	10/11/88
4,776,901	07/032,186	10/11/88	4,777,239	06/884,184	10/11/88
4,776,902	06/856,823	10/11/88	4,777,241	06/885,737	10/11/88
4,776,904	06/756,676	10/11/88	4,777,248	06/813,777	10/11/88
4,776,910	07/061,897	10/11/88	4,777,250	06/876,278	10/11/88
4,776,915	07/045,758	10/11/88	4,777,252	07/085,050	10/11/88
4,776,920	07/167,524	10/11/88	4,777,256	06/816,380	10/11/88
4,776,926	06/774,203	10/11/88	4,777,257	06/901,694	10/11/88
4,776,930	07/070,419	10/11/88	4,777,267	06/939,711	10/11/88
4,776,931	07/078,270	10/11/88	4,777,269	07/044,260	10/11/88
4,776,934	07/123,943	10/11/88	4,777,280	06/880,851	10/11/88
4,776,937	06/765,638	10/11/88	4,777,281	06/835,599	10/11/88
4,776,940	07/156,370	10/11/88	4,777,282	06/877,658	10/11/88
4,776,941	06/875,630	10/11/88	4,777,283	06/948,215	10/11/88
4,776,944	07/092,159	10/11/88	4,777,286	06/746,147	10/11/88
4,776,946	07/044,956	10/11/88	4,777,293	06/753,682	10/11/88
4,776,951	06/943,996	10/11/88	4,777,298	07/142,118	10/11/88
4,776,954	06/927,878	10/11/88	4,777,299	07/142,112	10/11/88
4,776,962	07/080,773	10/11/88	4,777,303	06/848,998	10/11/88
4,776,965	07/088,475	10/11/88	4,777,314	07/119,511	10/11/88
4,776,971	06/867,514	10/11/88	4,777,315	07/055,843	10/11/88
4,776,973	06/832,120	10/11/88	4,777,316	07/118,926	10/11/88
4,776,979	07/029,242	10/11/88	4,777,321	07/043,716	10/11/88
4,776,987	06/839,725	10/11/88	4,777,322	06/759,234	10/11/88
4,776,989	07/007,149	10/11/88	4,777,323	06/756,908	10/11/88
4,776,990	07/095,734	10/11/88	4,777,328	07/049,268	10/11/88
4,776,991	06/901,710	10/11/88	4,777,329	07/090,088	10/11/88
4,777,004	06/785,774	10/11/88	4,777,333	07/075,525	10/11/88
4,777,005	06/825,337	10/11/88	4,777,339	06/901,880	10/11/88
4,777,008	06/797,810	10/11/88	4,777,340	07/102,218	10/11/88
4,777,012	06/292,603	10/11/88	4,777,341	07/086,861	10/11/88
4,777,013	06/889,123	10/11/88	4,777,346	06/911,119	10/11/88
4,777,015	07/143,878	10/11/88	4,777,352	06/752,463	10/11/88
4,777,020	07/033,073	10/11/88	4,777,356	06/905,586	10/11/88
4,777,025	07/037,985	10/11/88	4,777,358	07/032,473	10/11/88
4,777,026	07/012,374	10/11/88	4,777,364	07/061,626	10/11/88
4,777,030	06/758,595	10/11/88	4,777,367	06/836,426	10/11/88
4,777,038	06/864,051	10/11/88	4,777,375	07/079,660	10/11/88
4,777,047	06/903,339	10/11/88	4,777,375	07/109,862	10/11/88
4,777,050	07/029,032	10/11/88	4,777,384	07/075,005	10/11/88
4,777,063	06/935,088	10/11/88	4,777,393	07/070,952	10/11/88
4,777,065	06/643,858	10/11/88	4,777,394	06/846,019	10/11/88
4,777,066	06/890,198	10/11/88	4,777,395	07/111,804	10/11/88
4,777,067	07/033,649	10/11/88	4,777,396	07/047,675	10/11/88
4,777,075	06/788,269	10/11/88	4,777,398	06/909,439	10/11/88
4,777,076	06/919,773	10/11/88	4,777,406	07/065,274	10/11/88
4,777,085	06/687,202	10/11/88	4,777,410	07/098,827	10/11/88
4,777,092	07/044,738	10/11/88	4,777,413	07/100,974	10/11/88
4,777,094	06/842,184	10/11/88	4,777,416	06/864,028	10/11/88
4,777,095	06/906,046	10/11/88	4,777,417	07/071,326	10/11/88
4,777,120	07/050,811	10/11/88	4,777,420	06/936,928	10/11/88
4,777,126	06/771,252	10/11/88	4,777,421	07/060,922	10/11/88
4,777,129	06/662,858	10/11/88	4,777,429	07/105,576	10/11/88
4,777,133	06/801,965	10/11/88	4,777,434	07/023,892	10/11/88
4,777,135	06/697,778	10/11/88	4,777,444	06/909,564	10/11/88
4,777,139	07/066,265	10/11/88	4,777,446	06/842,179	10/11/88
4,777,140	07/054,048	10/11/88	4,777,449	07/053,003	10/11/88
4,777,142	06/879,297	10/11/88	4,777,454	07/070,755	10/11/88
4,777,151	06/848,482	10/11/88	4,777,458	06/846,773	10/11/88
4,777,154	06/889,927	10/11/88	4,777,462	07/094,959	10/11/88
4,777,156	06/524,065	10/11/88	4,777,466	07/009,328	10/11/88
4,777,166	06/846,174	10/11/88	4,777,470	07/101,760	10/11/88
4,777,172	06/829,366	10/11/88	4,777,473	06/899,548	10/11/88
4,777,180	07/106,143	10/11/88	4,777,474	07/036,926	10/11/88
4,777,188	06/948,219	10/11/88	4,777,475	06/829,315	10/11/88
4,777,189	07/067,970	10/11/88	4,777,476	07/046,735	10/11/88
4,777,190	06/765,925	10/11/88	4,777,479	07/033,711	10/11/88
4,777,194	06/744,204	10/11/88	4,777,486	06/861,695	10/11/88
4,777,196	06/822,990	10/11/88	4,777,489	06/812,314	10/11/88
4,777,205	07/076,453	10/11/88	4,777,490	06/859,032	10/11/88
4,777,206	07/037,034	10/11/88	4,777,495	07/042,210	10/11/88
			4,777,500	07/107,789	10/11/88

Patent Number	Serial Number	Issue Date	5,154,114	07/648,919	10/13/92
4,777,501	07/040,991	10/11/88	5,154,115	07/780,028	10/13/92
4,777,502	07/128,849	10/11/88	5,154,116	07/848,641	10/13/92
4,777,514	07/044,981	10/11/88	5,154,119	07/592,037	10/13/92
4,777,533	07/001,251	10/11/88	5,154,122	07/602,151	10/13/92
4,777,539	06/903,190	10/11/88	5,154,125	07/700,545	10/13/92
4,777,540	06/840,692	10/11/88	5,154,129	07/628,907	10/13/92
4,777,541	06/897,889	10/11/88	5,154,134	07/754,547	10/13/92
4,777,550	06/759,966	10/11/88	5,154,139	07/522,757	10/13/92
4,777,552	07/091,201	10/11/88	5,154,146	07/753,130	10/13/92
4,777,558	07/111,066	10/11/88	5,154,150	07/654,537	10/13/92
4,777,562	07/070,756	10/11/88	5,154,158	07/723,446	10/13/92
4,777,569	07/065,000	10/11/88	5,154,159	07/720,407	10/13/92
4,777,571	07/050,684	10/11/88	5,154,162	07/772,449	10/13/92
4,777,572	06/934,742	10/11/88	5,154,163	07/752,590	10/13/92
4,777,573	07/153,056	10/11/88	5,154,185	07/613,214	10/13/92
4,777,596	06/880,851	10/11/88	5,154,186	07/508,384	10/13/92
4,777,598	06/827,240	10/11/88	5,154,187	07/790,422	10/13/92
4,777,601	06/835,248	10/11/88	5,154,190	07/738,475	10/13/92
4,777,603	06/709,542	10/11/88	5,154,193	07/549,020	10/13/92
4,777,607	06/845,266	10/11/88	5,154,198	07/240,906	10/13/92
4,777,612	06/657,910	10/11/88	5,154,206	07/280,064	10/13/92
4,777,618	06/756,944	10/11/88	5,154,207	07/739,998	10/13/92
4,777,624	06/884,808	10/11/88	5,154,208	07/703,677	10/13/92
4,777,632	07/079,600	10/11/88	5,154,210	07/730,044	10/13/92
4,777,636	07/018,272	10/11/88	5,154,211	07/632,547	10/13/92
4,777,638	06/795,656	10/11/88	5,154,212	07/705,603	10/13/92
4,777,647	06/912,984	10/11/88	5,154,213	07/693,881	10/13/92
4,777,656	06/655,606	10/11/88	5,154,218	07/702,618	10/13/92
5,153,943	07/754,836	10/13/92	5,154,219	07/636,451	10/13/92
5,153,945	07/741,334	10/13/92	5,154,221	07/730,879	10/13/92
5,153,950	07/740,716	10/13/92	5,154,222	07/625,854	10/13/92
5,153,951	07/775,779	10/13/92	5,154,233	07/621,837	10/13/92
5,153,953	07/722,116	10/13/92	5,154,234	07/769,793	10/13/92
5,153,955	07/745,220	10/13/92	5,154,235	07/790,755	10/13/92
5,153,956	07/629,831	10/13/92	5,154,236	07/771,115	10/13/92
5,153,957	07/631,895	10/13/92	5,154,249	07/822,381	10/13/92
5,153,958	07/795,558	10/13/92	5,154,251	07/614,847	10/13/92
5,153,959	07/852,465	10/13/92	5,154,257	07/756,515	10/13/92
5,153,962	07/611,042	10/13/92	5,154,261	07/557,802	10/13/92
5,153,968	07/611,034	10/13/92	5,154,267	07/765,593	10/13/92
5,153,974	07/826,637	10/13/92	5,154,268	07/633,216	10/13/92
5,153,975	07/622,496	10/13/92	5,154,273	07/798,536	10/13/92
5,153,979	07/720,667	10/13/92	5,154,276	07/768,631	10/13/92
5,153,988	07/499,117	10/13/92	5,154,277	07/824,171	10/13/92
5,153,991	07/593,877	10/13/92	5,154,278	07/682,736	10/13/92
5,153,993	07/762,564	10/13/92	5,154,281	07/733,648	10/13/92
5,153,998	07/692,737	10/13/92	5,154,291	07/701,745	10/13/92
5,154,003	07/762,242	10/13/92	5,154,293	07/690,050	10/13/92
5,154,004	07/795,836	10/13/92	5,154,295	07/612,186	10/13/92
5,154,005	07/720,653	10/13/92	5,154,297	07/754,068	10/13/92
5,154,006	07/804,041	10/13/92	5,154,321	07/641,290	10/13/92
5,154,009	07/494,847	10/13/92	5,154,322	07/751,614	10/13/92
5,154,010	07/602,472	10/13/92	5,154,323	07/643,215	10/13/92
5,154,014	07/577,764	10/13/92	5,154,329	07/790,511	10/13/92
5,154,015	07/710,700	10/13/92	5,154,330	07/545,865	10/13

Patent Number	Serial Number	Issue Date	5,154,702	07/526,172	10/13/92
5,154,420	07/806,371	10/13/92	5,154,704	07/607,299	10/13/92
5,154,426	07/719,496	10/13/92	5,154,710	07/755,816	10/13/92
5,154,427	07/722,180	10/13/92	5,154,711	07/460,876	10/13/92
5,154,428	07/732,613	10/13/92	5,154,721	07/572,577	10/13/92
5,154,430	07/786,541	10/13/92	5,154,722	07/583,187	10/13/92
5,154,441	07/826,795	10/13/92	5,154,726	07/657,941	10/13/92
5,154,445	07/764,343	10/13/92	5,154,734	07/729,065	10/13/92
5,154,446	07/560,852	10/13/92	5,154,736	07/677,050	10/13/92
5,154,449	07/661,134	10/13/92	5,154,743	07/687,156	10/13/92
5,154,454	07/830,582	10/13/92	5,154,745	07/777,180	10/13/92
5,154,463	07/540,182	10/13/92	5,154,748	07/484,881	10/13/92
5,154,464	07/760,379	10/13/92	5,154,749	07/314,526	10/13/92
5,154,465	07/726,194	10/13/92	5,154,751	07/530,711	10/13/92
5,154,466	07/644,646	10/13/92	5,154,752	07/334,317	10/13/92
5,154,470	07/826,052	10/13/92	5,154,754	07/517,451	10/13/92
5,154,472	07/714,655	10/13/92	5,154,758	07/698,948	10/13/92
5,154,474	07/749,535	10/13/92	5,154,766	07/792,580	10/13/92
5,154,478	07/664,209	10/13/92	5,154,770	07/587,158	10/13/92
5,154,480	07/574,819	10/13/92	5,154,776	07/711,184	10/13/92
5,154,484	07/689,964	10/13/92	5,154,782	07/745,501	10/13/92
5,154,495	07/445,599	10/13/92	5,154,798	07/707,286	10/13/92
5,154,498	07/742,328	10/13/92	5,154,800	07/830,292	10/13/92
5,154,506	07/716,239	10/13/92	5,154,805	07/706,185	10/13/92
5,154,507	07/642,815	10/13/92	5,154,813	07/712,511	10/13/92
5,154,509	07/821,194	10/13/92	5,154,818	07/749,483	10/13/92
5,154,515	07/395,511	10/13/92	5,154,821	07/793,558	10/13/92
5,154,516	07/696,141	10/13/92	5,154,822	07/839,291	10/13/92
5,154,520	07/669,617	10/13/92	5,154,825	07/690,952	10/13/92
5,154,522	07/594,553	10/13/92	5,154,831	07/591,116	10/13/92
5,154,523	07/477,796	10/13/92	5,154,836	07/538,158	10/13/92
5,154,524	07/785,423	10/13/92	5,154,837	07/620,576	10/13/92
5,154,525	07/717,313	10/13/92	5,154,838	07/697,416	10/13/92
5,154,526	07/812,911	10/13/92	5,154,845	07/752,285	10/13/92
5,154,533	07/687,181	10/13/92	5,154,856	07/558,721	10/13/92
5,154,535	07/646,282	10/13/92	5,154,864	07/744,399	10/13/92
5,154,537	07/706,505	10/13/92	5,154,871	07/658,278	10/13/92
5,154,541	07/791,111	10/13/92	5,154,894	07/747,065	10/13/92
5,154,542	07/829,908	10/13/92	5,154,896	07/577,538	10/13/92
5,154,544	07/751,501	10/13/92	5,154,921	07/552,746	10/13/92
5,154,548	07/766,397	10/13/92	5,154,922	07/675,936	10/13/92
5,154,553	07/460,682	10/13/92	5,154,925	07/630,748	10/13/92
5,154,554	07/796,011	10/13/92	5,154,931	07/228,923	10/13/92
5,154,556	07/575,078	10/13/92	5,154,932	07/577,825	10/13/92
5,154,557	07/849,614	10/13/92	5,154,942	07/683,902	10/13/92
5,154,560	07/733,443	10/13/92	5,154,947	07/679,467	10/13/92
5,154,563	07/551,407	10/13/92	5,154,954	07/501,292	10/13/92
5,154,568	07/642,461	10/13/92	5,154,956	07/463,385	10/13/92
5,154,569	07/525,193	10/13/92	5,154,959	07/539,739	10/13/92
5,154,574	07/729,304	10/13/92	5,154,965	07/541,805	10/13/92
5,154,579	07/556,688	10/13/92	5,154,968	07/643,534	10/13/92
5,154,580	07/748,273	10/13/92	5,154,983	07/623,284	10/13/92
5,154,582	07/749,715	10/13/92	5,154,984	07/598,515	10/13/92
5,154,583	07/600,008	10/13/92	5,155,022	07/802,719	10/13/92
5,154,588	07/783,526	10/13/92	5,155,040	07/652,681	10/13/92
5,154,600	07/632,067	10/13/92	5,155,096	07/493,122	10/13/92
5,154,606	07/699,115	10/13/92	5,155,106	07/615,621	10/13/92
5,154,607	07/709,587	10/13/92	5,155,108	07/548,882	10/13/92
5,154,608	07/594,281	10/13/92	5,155,109	07/648,136	10/13/92
5,154,611	07/729,270	10/13/92	5,155,111	07/730,491	10/13/92
5,154,615	07/759,388	10/13/92	5,155,116	07/518,271	10/13/92
5,154,624	07/771,588	10/13/92	5,155,119	07/711,297	10/13/92
5,154,625	07/794,923	10/13/92	5,155,123	07/846,110	10/13/92
5,154,627	07/683,445	10/13/92	5,155,132	07/607,153	10/13/92
5,154,640	07/693,700	10/13/92	5,155,133	07/170,490	10/13/92
5,154,641	07/833,625	10/13/92	5,155,135	07/643,161	10/13/92
5,154,643	07/821,845	10/13/92	5,155,139	07/446,606	10/13/92
5,154,652	07/697,798	10/13/92	5,155,142	07/861,679	10/13/92
5,154,656	07/748,852	10/13/92	5,155,161	07/413,322	10/13/92
5,154,658	07/798,356	10/13/92	5,155,162	07/578,228	10/13/92
5,154,666	07/597,790	10/13/92	5,155,169	07/684,811	10/13/92
5,154,672	07/699,957	10/13/92	5,155,176	07/567,921	10/13/92
5,154,676	07/794,076	10/13/92	5,155,182	07/856,273	10/13/92
5,154,683	07/655,407	10/13/92	5,155,185	07/561,791	10/13/92
5,154,684	07/499,396	10/13/92	5,155,186	07/562,493	10/13/92
5,154,686	07/681,811	10/13/92	5,155,191	07/134,738	10/13/92
5,154,696	07/551,142	10/13/92	5,155,194	07/835,115	10/13/92
5,154,699			5,155,195	07/704,653	10/13/92
				07/701,557	10/13/92

Patent Number	Serial Number	Issue Date	5,155,430	07/444,730	10/13/92
5,155,196	07/532,297	10/13/92	5,155,438	07/673,915	10/13/92
5,155,197	07/493,177	10/13/92	5,155,440	07/707,986	10/13/92
5,155,198	07/714,980	10/13/92	5,155,448	07/690,929	10/13/92
5,155,205	07/641,235	10/13/92	5,155,450	07/812,385	10/13/92
5,155,207	07/485,396	10/13/92	5,155,458	07/787,060	10/13/92
5,155,209	07/747,893	10/13/92	5,155,460	07/663,114	10/13/92
5,155,210	07/580,835	10/13/92	5,155,470	07/685,884	10/13/92
5,155,222	07/731,518	10/13/92	5,155,480	07/634,758	10/13/92
5,155,228	07/702,441	10/13/92	5,155,483	07/681,425	10/13/92
5,155,235	07/726,185	10/13/92	5,155,488	07/439,941	10/13/92
5,155,236	07/334,749	10/13/92	5,155,489	07/304,506	10/13/92
5,155,246	07/102,195	10/13/92	5,155,493	07/578,034	10/13/92
5,155,254	07/729,240	10/13/92	5,155,500	07/596,137	10/13/92
5,155,257	07/774,511	10/13/92	5,155,509	07/603,464	10/13/92
5,155,271	07/543,245	10/13/92	5,155,527	07/661,326	10/13/92
5,155,275	07/718,693	10/13/92	5,155,540	07/699,469	10/13/92
5,155,276	07/756,698	10/13/92	5,155,552	07/455,001	10/13/92
5,155,288	07/761,197	10/13/92	5,155,556	07/737,472	10/13/92
5,155,290	07/783,664	10/13/92	5,155,559	07/735,534	10/13/92
5,155,292	07/550,810	10/13/92	5,155,565	07/517,447	10/13/92
5,155,293	07/626,809	10/13/92	5,155,580	07/638,301	10/13/92
5,155,294	07/680,362	10/13/92	5,155,589	07/687,678	10/13/92
5,155,297	06/788,542	10/13/92	5,155,600	07/401,131	10/13/92
5,155,298	07/769,933	10/13/92	5,155,624	07/543,152	10/13/92
5,155,316	07/633,113	10/13/92	5,155,640	07/518,599	10/13/92
5,155,318	07/808,991	10/13/92	5,155,654	07/707,652	10/13/92
5,155,319	07/633,111	10/13/92	5,155,661	07/700,784	10/13/92
5,155,321	07/611,309	10/13/92	5,155,662	07/641,946	10/13/92
5,155,322	07/779,425	10/13/92	5,155,667	07/751,973	10/13/92
5,155,327	07/486,954	10/13/92	5,155,674	07/667,583	10/13/92
5,155,330	07/739,900	10/13/92	5,155,694	07/606,082	10/13/92
5,155,333	07/733,819	10/13/92	5,155,702	07/617,628	10/13/92
5,155,334	07/668,194	10/13/92	5,155,709	07/727,760	10/13/92
5,155,338	07/656,998	10/13/92	5,155,710	07/588,768	10/13/92
5,155,344	07/812,867	10/13/92	5,155,714	07/425,161	10/13/92
5,155,345	07/507,046	10/13/92	5,155,757	07/718,300	10/13/92
5,155,357	07/556,751	10/13/92	5,155,762	07/439,399	10/13/92
5,155,358	07/729,252	10/13/92	5,155,765	07/737,356	10/13/92
5,155,366	07/753,368	10/13/92	5,155,771	07/879,711	10/13/92
5,155,371	07/628,141	10/13/92	5,155,775	07/260,423	10/13/92
5,155,374	07/500,506	10/13/92	5,155,784	07/784,969	10/13/92
5,155,381	07/474,488	10/13/92	5,155,790	07/532,932	10/13/92
5,155,383	07/829,197	10/13/92	5,155,793	07/645,469	10/13/92
5,155,406	07/681,474	10/13/92	5,155,798	07/312,949	10/13/92
5,155,408	07/576,588	10/13/92	5,155,808	07/379,017	10/13/92
5,155,409	07/728,395	10/13/92	5,155,811	07/304,662	10/13/92
5,155,419	07/598,238	10/13/92	5,155,820	07/313,704	10/13/92
5,155,424	07/474,121	10/13/92	5,155,827	07/325,289	10/13/92
5,155,425	07/640,426	10/13/92	5,155,841	07/586,944	10/13/92
5,155,426	07/790,402	10/13/92	5,155,847	07/227,799	10/13/92
			5,155,861	07/612,858	10/13/92

Patents Reinstated Due to the Acceptance of a Late Maintenance Fee From 10/18/96

Patent Number	Serial Number	Filing Date	Issue Date	Granted Date
4,350,527	06/310,475	10/13/81	09/21/82	10/24/96
4,629,607	06/686,993	12/27/84	12/16/86	10/23/96
4,727,626	06/809,610	12/16/85	03/01/88	10/23/96
4,747,315	06/500,809	06/03/83	05/31/88	10/21/96
4,757,865	06/932,706	11/19/86	07/19/88	10/23/96
4,976,732	06/649,909	09/12/84	12/11/90	10/24/96
5,007,557	07/495,806	03/19/90	04/16/91	10/23/96
5,123,258	07/734,628	07/23/91	06/23/92	

Patent Number	Serial Number	Filing Date	Issue Date	Granted Date
Re. 34,186	07/774,578	10/10/91	03/02/93	10/31/96
4,418,740	06/247,292	03/26/81	12/06/83	10/31/96
4,442,326	06/398,403	10/10/91	04/10/84	10/31/96
4,563,808	06/632,667	07/20/84	01/14/86	10/31/96
4,576,301	06/537,680	09/30/83	03/18/86	10/31/96
4,603,333	06/521,722	08/09/83	07/29/86	10/31/96
4,655,390	06/904,455	09/08/86	04/07/87	10/31/96
4,677,798	06/852,021	04/14/86	07/07/87	10/31/96
4,703,465	06/804,803	12/04/85	10/27/87	10/31/96
4,717,402	06/656,708	10/01/84	01/05/88	10/31/96
4,740,375	06/705,023	02/25/85	04/26/88	10/31/96
4,818,905	06/808,629	12/13/85	04/04/89	10/31/96
4,943,063	07/330,055	03/29/89	07/24/90	10/31/96
4,954,300	07/366,757	06/14/89	09/04/90	10/31/96
4,955,566	07/420,911	10/13/89	09/11/90	10/31/96
4,960,271	07/229,488	08/08/88	10/02/90	10/31/96
5,037,836	07/555,887	07/23/90	08/06/91	10/31/96
5,053,046	07/579,105	09/06/90	10/01/91	10/30/96
5,056,704	07/158,797	02/22/88	10/15/91	10/31/96
5,057,423	07/134,717	12/18/87	10/15/91	10/30/96
5,063,896	07/568,870	08/17/90	11/12/91	10/31/96
5,071,819	07/236,763	08/26/88	12/10/91	10/31/96
5,116,110	07/318,671	03/03/89	05/26/92	10/31/96
5,117,366	07/372,730	06/28/89	05/26/92	10/31/96
5,126,153	07/625,017	12/10/90	06/30/92	10/31/96
5,127,720	07/605,128	10/24/90	07/07/92	10/31/96
5,129,737	07/646,193	01/28/91	07/14/92	10/30/96

Reissue Applications Filed

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.12(b)).

4,718,008, Re. S.N. 08/726565, Oct. 4, 1996, Cl. 395, METHOD TO CONTROL PAGING SUBSYSTEM IN VIRTUAL MEMORY DATA PROCESSING SYSTEM DURING EXECUTION OF CRITICAL CODE SECT., Albert Chang et. al., Owner of Record: *International Business Machines Corp., Armonk, N.Y.*, Attorney or Agent: Kenneth C. Hill, Ex. Gp.: 2364

4,770,803, Re. S.N. 08/726874, Oct. 4, 1996, Cl. 252, AQUEOUS COMPOSITION CONTAINING NITROGEN-CONTAINING SALTS, John W. Forsberg, Owner of Record: *Inventor*, Attorney or Agent: Neil A. Du Chez, Ex. Gp.: 1105

4,926,547, Re. S.N. 08/558979, Nov. 13, 1995, Cl. 29/841, METHOD FOR MANUFACTURING A MODULAR SEMI-CONDUCTOR POWER DEVICE, Antonio P. Spatrisano et. al., Owner of Record: *SGS-Thomson Microelectronics SPA, Catania, Italy*, Attorney or Agent: Richard K. Robinson, Ex. Gp.: 3206

5,301,159, Re. S.N. 08/628496, April 5, 1996, Cl. 365/225.7, ANTI-FUSE CIRCUIT AND METHOD WHEREIN THE READ OPERATION AND PROGRAMMING OPERATION ARE REVERSED, Ruojia Lee, Owner of Record: *Micron Technology Inc., Boise, Idaho*, Attorney or Agent: James R. Duzan, Ex. Gp.: 2511

5,347,568, Re. S.N. 08/723980, Sept. 13, 1996, Cl. 379/45, EMERGENCY CALL STATION IDENTIFICATION SYSTEM, Martin Moody et. al., Owner of Record: *Telident Inc., Minneapolis, Minn.*, Attorney or Agent: Lawrence M. Nawrocki, Ex. Gp.: 2608

5,355,167, Re. S.N. 08/728995, Oct. 10, 1996, Cl. 348/405, ORTHOGONAL TRANSFORM CODING APPARATUS, Tatsuro Juri, Owner of Record: *Matsushita Electric Industrial*

Co., Ltd., Osaka, Japan, Attorney or Agent: Adam C. Volentine, Ex. Gp.: 2615

5,360,093, Re. S.N. 08/740750, Nov. 1, 1996, Cl. 194/206, METHOD AND APPARATUS FOR THE CONTROL OF A MULTIPLE OF DOOR ACCESSIBLE NEWSPAPER VENDING CABINETS WITH A SINGLE VEND CONTROL MECHANISM OPERATING REMOTE DOOR, LATCHES, Scott Baer, Owner of Record: *Kasper Wire Works Inc., Shiner, Tex.*, Attorney or Agent: Pamela B. Huff, Ex. Gp.: 3107

5,361,151, Re. S.N. 08/729929, Oct. 15, 1996, Cl. 359/65, REFLECTION-TYPE LIQUID CRYSTAL DEVICE WITH POLARIZATION OF OUTPUT LIGHT PERPENDICULAR TO THAT OF INPUT LIGHT, Tomio Sonehara et. al., Owner of Record: *Seiko Epson Corp., Tokyo-To, Japan*, Attorney or Agent: Mark P. Watson, Ex. Gp.: 2515

5,368,619, Re. S.N. 08/716655, Sept. 6, 1996, Cl. 51/308, REDUCED VISCOSITY SLURRIES, ABRASIVE, Scott R. Culter, Owner of Record: *Minnesota Mining And Manufacturing Co., St. Paul, Minn.*, Attorney or Agent: Doreen S. L. Gwin, Ex. Gp.: 1108

5,418,585, Re. S.N. 08/713308, Sept. 13, 1996, Cl. 396/429, METHOD AND APPARATUS FOR PREVENTING UNAUTHORIZED RECYCLING OF SINGLE-USE CAMERA AND PERMITTING AUTHORIZED REUSE OF THE CAMERA, Dwight J. Petruchik et. al., Owner of Record: *Eastman Kodak Co., Rochester, N.Y.*, Attorney or Agent: Roger A. Fields, Ex. Gp.: 3101

5,426,997, Re. S.N. 08/556042, Nov. 13, 1995, Cl. 74/594.1, BICYCLE CHAIN DRIVE ASSEMBLY, Donald G. Brion, Owner of Record: *Inventor*, Attorney or Agent: B. Craig Kilough, Ex. Gp.: 3502

5,503,401, Re. S.N. 08/733520, Oct. 18, 1996, Cl. 273/306, METHOD OF PLAYING A CARD GAME, Son H. Nguyen, Owner of Record: *Inventor*, Attorney or Agent: Kenton R. Mullins, Ex. Gp.: 3304

Requests for Reexaminations Filed

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.19(a)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.248(a)(5) and 1.525(b)).

5,427,720, Reexam. No. 90/004,441, Nov. 4, 1996, Cl. 264/40.6, METHOD FOR MOLD TEMPERATURE CONTROL, Werner Kotzab, Owner of Record: *Inventor*, Attorney or Agent: Robert F. Conte, Chicago, Ill., Ex. Gp.: 1307, Requester: Albert O. Cota, Encino, Calif.

5,452,906, Reexam. No. 90/004,440, Nov. 1, 1996, Cl. 279/062, NON-IMPACT KEYLESS CHUCK, Robert O. Huff, et. al., Owner of Record: *Power Tool Holders Inc., Wilmington, Del.*, Attorney or Agent: Mark C. Dukes, Dority & Manning, Greenville, S.C., Ex. Gp.: 3209, Requester: Clarence J. Fleming, Jones Day Reavis & Pogue, Chicago, Ill.

Notice of Expiration of Trademark Registrations Due To Failure to Renew

15 U.S.C. 1059 provides that each trademark registration may be renewed for periods of ten years from the end of the expiring period upon payment of the prescribed fee and the filing of an acceptable application for renewal. This may be done at any time within six months before the expiration of the period for which the registration was issued or renewed, or it may be done within three months after such expiration on payment of an additional fee.

According to the records of the Office, the trademark registrations listed below are expired due to failure to renew in accordance with 15 U.S.C. 1059.

TRADEMARK REGISTRATIONS WHICH EXPIRED AUGUST 26, 1996 DUE TO FAILURE TO RENEW

Reg. Number	Serial Number	Reg. Date		
107,316	71/088,007	11/23/1915	616,377	71/675,471
107,321	71/088,036	11/23/1915	616,379	71/678,165
107,323	71/088,039	11/23/1915	616,384	71/679,513
107,350	71/080,587	11/23/1915	616,392	71/647,929
107,368	71/087,278	11/23/1915	616,400	71/676,140
329,908	71/365,985	11/19/1935	616,401	71/677,907
329,911	71/366,061	11/19/1935	616,406	71/679,995
329,932	71/366,276	11/19/1935	616,409	71/667,670
329,947	71/366,848	11/19/1935	616,413	71/682,669
329,981	71/367,376	11/19/1935	616,414	71/682,838
329,989	71/362,715	11/19/1935	616,418	71/652,613
329,992	71/360,048	11/19/1935	616,419	71/663,304
329,995	71/352,473	11/19/1935	616,421	71/666,895
329,997	71/351,143	11/19/1935	616,426	71/669,705
329,998	71/367,197	11/19/1935	616,428	71/673,146
330,006	71/364,199	11/19/1935	616,432	71/678,443
330,018	71/367,430	11/19/1935	616,433	71/681,114
330,048	71/366,929	11/19/1935	616,435	71/681,572
330,059	71/365,134	11/19/1935	616,436	71/681,835
330,063	71/367,242	11/19/1935	616,437	71/667,358
330,084	71/366,406	11/19/1935	616,438	71/670,827
330,089	71/366,265	11/19/1935	616,445	71/682,823
330,094	71/366,894	11/19/1935	616,449	71/683,699
330,131	71/347,618	11/19/1935	616,451	71/674,489
330,148	71/367,137	11/19/1935	616,452	71/680,026
330,149	71/365,097	11/19/1935	616,454	71/664,581
330,151	71/365,096	11/19/1935	616,460	71/681,483
330,160	71/366,621	11/19/1935	616,463	71/686,864
330,161	71/366,618	11/19/1935	616,464	71/686,875
330,162	71/366,616	11/19/1935	616,467	71/643,120
589,109	71/648,175	04/27/1954	616,472	71/668,335
596,716	71/643,605	10/12/1954	616,480	71/681,138
			616,498	71/634,486
			616,509	71/670,343
			616,512	71/672,400
			616,517	71/674,301
			616,532	71/680,780
			616,544	71/679,748
			616,546	71/679,968
			616,556	71/677,968
			616,573	71/672,944
			616,577	71/678,342
			616,578	71/678,857
			616,579	71/678,977
			616,593	71/672,914
			616,601	71/679,747
			616,619	71/667,892
			616,620	71/631,771
			616,623	71/667,979
			616,624	71/668,029
			616,626	71/671,642
			616,627	71/674,507
			616,628	71/674,894
			616,631	71/680,358
			616,640	71/659,995
			616,643	71/675,190
			616,645	71/677,555
			616,648	71/657,060
			616,652	71/678,544
			616,657	71/669,505
			616,680	71/607,406
			616,683	71/689,709
			990,560	73/000,472
			1,025,033	73/009,372
			1,025,034	73/025,455
			1,025,037	73/040,369
			1,025,038	73/043,208
			1,025,040	73/044,719
			1,025,041	73/044,720
			1,025,045	73/047,816
			1,025,049	73/030,656
			1,025,050	73/031,819
			1,025,051	73/032,007
			1,025,055	73/042,247
			1,025,058	73/045,573
			1,025,060	73/045,886
			1,025,061	73/048,477
			1,025,064	73/009,910
			1,025,065	73/016,744

Re. 35,321	5,391,744	5,470,526	5,515,194
D. 366,829	5,391,796	5,472,191	5,516,055
D. 371,091	5,395,174	5,473,704	5,517,608
D. 371,975	5,397,746	5,476,861	5,517,653
D: 372,474	5,398,075	5,477,949	5,517,665
D. 374,009	5,403,304	5,479,362	5,518,567
D. 374,124	5,408,376	5,481,003	5,518,620
4,624,673	5,409,662	5,485,381	5,518,692
4,665,082	5,410,532	5,486,830	5,519,066
4,961,938	5,420,518	5,487,383	5,521,693
5,066,968	5,423,929	5,488,778	5,521,964
5,082,668	5,424,605	5,489,637	5,522,205
5,106,609	5,425,458	5,491,469	5,522,611
5,133,021	5,428,057	5,492,188	5,522,946
5,142,590	5,428,204	5,493,568	5,523,209
5,145,783	5,430,564	5,494,314	5,523,800
5,164,899	5,430,793	5,494,733	5,524,161
5,175,096	5,434,173	5,494,911	5,524,886
5,211,896	5,435,816	5,495,925	5,524,640
5,228,943	5,444,022	5,498,615	5,525,011
5,240,471	5,445,278	5,499,971	5,525,206
5,268,608	5,446,834	5,500,403	5,525,426
5,272,754	5,451,527	5,500,477	5,526,003
5,275,014	5,453,288	5,500,859	5,526,261
5,288,059	5,456,910	5,504,109	5,528,382
5,301,281	5,457,038	5,504,326	5,528,475
5,318,089	5,457,074	5,504,619	5,528,621
5,322,488	5,457,811	5,505,670	5,528,976
5,345,543	5,458,371	5,505,673	5,529,787
5,348,010	5,458,933	5,506,075	5,529,883
5,352,690	5,459,150	5,506,311	5,530,130
5,357,594	5,459,266	5,506,351	5,530,408
5,364,038	5,462,960	5,507,482	5,530,616
5,366,692	5,463,039	5,507,923	5,530,813
5,369,912	5,463,484	5,508,318	5,530,995
5,374,208	5,464,057	5,510,471	5,531,715
5,377,020	5,465,134	5,510,838	5,531,839
5,379,396	5,468,033	5,512,065	5,531,964
5,382,245	5,469,544	5,514,143	5,532,518
5,383,090	5,470,280	5,514,998	5,532,915

Summary of Final Decisions

Issued by the

Trademark Trial and Appeal Board

October 28 - November 1, 1996

Date Issued	Type of Case ⁽¹⁾	Proceeding or App'n No.	Party/Parties	Issue	TTAB Decision	Opposer's Mark and Goods/Services	Applicant's Mark and Goods/Services	Mark Cited by Examining Attorney	Recommended for Publication
10-29	OPP OPP	87,081 87,082	Sharkskins Surf Gear, Inc. v. San Jose Sharks	2(d); counterclaim for cancellation on grounds of (1) no bona fide use in commerce and (2) fraud	Oppositions Dismissed, Counterclaim for Cancellation Granted	"SHARKSKINS" (and a design incorporating a shark's head) [surf clothing, namely, t-shirts, jackets, pants, warm-up suits, wetsuits, shoes and shorts]	design incorporating a fanciful representation of a shark [clothing—namely, shirts, jerseys, sweaters, sweatshirts, t-shirts, jackets, pants, warm-up suits, wetsuits, hats, socks, nightshirts, scarves, mittens and cloth hats, services—namely, entertainment services—namely, providing professional ice hockey exhibitions]	No	No
10-30	EX EX EX EX	74/107,141 74/30,369 74/390,769 74/391,199	Orange Communications, Inc.	de jure functionality (of color)	Refusal Affirmed (in all four cases)		the color orange and the color yellow applied across the surface of applicant's goods [pay telephones and pay telephone booths]	Yes	Yes
10-30	EX	74/509,007	Dynacraft Industries Inc.	2(d)	Refusal Affirmed		"POWER CLIMBER" [bicycles]	No	No
11-1	EX	74/405,927	Crawford Fitting Co.	2(e)(1)	Refusal Affirmed		"TOOBENDER" [tube bending machines]	No	No

(1) EX = EX PARTE APPEAL; OPP = OPPOSITION; CANCELLATION; CU = CONCURRENT USE; (S) = SUMMARY JUDGMENT; (R) = REQ FOR RECONSIDERATION

SPECIAL BOXES FOR PATENT MAIL

Special box designations should be used to allow forwarding of particular types of mail to the appropriate areas as quickly as possible. Such mail is forwarded to the appropriate area without being opened. Only the specified type of document should be placed in an envelope addressed to one of these special boxes. If any documents other than the specified type identified for each special box are addressed to that box, they will be significantly delayed in reaching the appropriate area for which they are intended.

Please address mail as follows:

Box _____
Assistant Commissioner for Patents
Washington, D.C. 20231

Box Designations	Explanation
Box 7 Box 12 Box 313b	Reissue applications for patents involved in litigation and subsequently filed related papers. Contributions to the Examiner Education Program. Petitions under 37 CFR 1.313(b) to withdraw a patent application from issue after payment of the issue fee and any papers associated with the petition, including papers necessary for filing a continuing application.
Box AF Box Comments Patents Box DAC	Expedited procedure for processing amendments and other responses after final rejection. Public comments regarding patent related regulations and procedures. Petitions decided by the Office of Petitions including petitions to revive and petitions to accept late payment of issue fees or maintenance fees.
Box DD Box FWC Box Issue Fee	Disclosure Documents or materials related to the Disclosure Document Program. Requests for File Wrapper Continuation Applications (under 37 CFR 1.62). All communications following the receipt of a PTOL-85, "Notice of Allowance and Issue Fee Due," and prior to the issuance of a patent should be addressed to Box Issue Fee, unless advised to the contrary. Assignments are the exception. Assignments should be submitted in a separate envelope and not be sent to Box Issue Fee.
Box Missing Parts Box MPEP Box Non-Fee Amendment Box PATENT APPLICATION Box Patent Ext. Box PCT Box Provisional Patent Application Box Reconstruction Box Reexam Box Sequence Box SN	Response to the Notice to File Missing Parts of Application and associated papers and fees. Submissions concerning the Manual of Patent Examining Procedures. Non-fee amendments to patent applications. (Use Box AF for responses after final rejection). New patent applications and associated papers and fees. Applications for patent term extension and any communications relating thereto. Mail related to applications filed under the Patent Cooperation Treaty. The filing of all provisional patent applications and any communications relating thereto. Correspondence pertaining to the reconstruction of lost patent files. Requests for Reexamination for <i>original</i> request papers <i>only</i> . Submission of diskette for biotechnical application. For fee and petitions under 37 CFR 1.182 to obtain date received and/or serial number for patent applications <i>prior</i> to the Office's standard notification (return post card or the official "Filing Receipt," "Notice to File Missing Parts," or "Notice of Incomplete Application").

SPECIAL BOXES FOR TRADEMARK MAIL

Special box designations should be used to allow forwarding of particular types of trademark mail to the appropriate areas as quickly as possible. In addition to these box designations, filers are encouraged to indicate whether the contents of the envelope contain a fee. Envelopes containing a fee should be marked "FEE;" envelopes not containing a fee should be marked "NO FEE." Box designations and "FEE/NO FEE" indicators should appear on the envelope as well as on the cover sheet or first page of any document.

Please address mail as follows:

Box _____
FEE (or NO FEE)
Assistant Commissioner for Trademarks
2900 Crystal Drive
Arlington, Virginia 22202-3513

Box Designations	Explanation
Box NEW APP FEE Box ITU FEE Box TTAB FEE Box TTAB NO FEE Box STATUS NO FEE Box POST REG FEE Box RESPONSES NO FEE	New trademark applications and fees. Statements of Use (SOU) and extension requests. Oppositions, cancellation petitions, and ex parte appeals. Interferences, motions, and extension requests. Written status inquiries. Affidavits, renewals, corrections and amendments. Responses to Examining Attorneys' Office actions and Post Registration actions.

SPECIAL BOXES APPLICABLE TO BOTH PATENT AND TRADEMARK MAIL

The following special box designations are applicable to both patent and trademark related mail, and the recommendations for "Special Boxes for Patent Mail" (above) should be followed for the types of mail listed below.

Please address mail as follows:

Box _____
Commissioner of Patents and Trademarks
Washington, D.C. 20231

Box Designations	Explanation
Box 3	Mail for the Office of Personnel from NFC.
Box 4	Mail for the Deputy Assistant Secretary of Commerce and Deputy Commissioner of Patents and Trademarks; Office of Legislative and International Affairs.
Box 6	Mail for the Office of Procurement.
Box 8	All papers for the Office of the Solicitor <i>except</i> communications relating to <i>pending litigation and disciplinary proceedings</i> ; papers relating to pending litigation in court cases shall be mailed only to Office of the Solicitor, P.O. Box 15667, Arlington, Virginia 22215 and papers relating to pending disciplinary proceedings before the Administrative Law Judge or the Commissioner shall be mailed only to the Office of the Solicitor, P.O. Box 16116, Arlington, Virginia 22215.
Box 9	Coupon orders for U.S. patent and trademark copies.
Box 10	Orders for certified copies of PTO documents.
Box 11	Electronic Ordering Service (EOS).
Box 13	Mail for the Employee and Labor Relations Division.
Box 14	Mail directed to the APS Contracts Office.
Box 16	Deposit Account Replenishment Checks.
Box 17	Invoices directed to the Office of Finance.
Box 171	Vacancy Announcement Applications.
Box Assignment	All assignment documents except those filed with new applications.
Box EEO	Mail for the Office of Civil Rights.
Box Interference	Communications relating to interferences and applications and patents involved in interference.
Box M Fee	Correspondence regarding patent maintenance fees and related matter.
Box OED	Mail for the Office of Enrollment and Discipline.

Reference Collections of U.S. Patents and Trademarks
Available for Public Use in Patent and Trademark Depository Libraries

The following libraries, designated as Patent and Trademark Depository Libraries (PTDLs), receive patent and trademark information in various formats from the U.S. Patent and Trademark Office. Many PTDLs have on file all full-text patents issued since 1790, trademarks published since 1872, and select collections of foreign patents. All PTDLs have both the patent and trademark sections of the *Official Gazette of the U.S. Patent and Trademark Office*. The full-text utility and design patents are distributed numerically on 16 mm microfilm, and plant patents on color microfiche. Patent and trademark search systems on CD-ROM (Compact Disc-Read Only) format are available at all PTDLs to increase utilization of and enhance access to the information found in patents and trademarks. It is through the CD-ROM systems that preliminary patent and trademark searches can be conducted through the numerically arranged collections.

All information is available for use by the public free of charge.

In addition, each PTDL offers reference publications which outline and provide access to the patent and trademark classification systems, as well as other documents and publications which supplement the basic search tools. PTDLs provide technical staff assistance in using all materials. Facilities for making paper copies of patent and trademark information are generally provided for a fee.

Since there are variations in the scope of patent and trademark collections among the PTDLs, and their hours of service to the public vary, anyone contemplating use of these collections at a particular library is urged to contact that library in advance about its collections, services, and hours in order to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Auburn University Libraries	(205) 844-1747
	Birmingham Public Library	(205) 226-3620
Alaska	Anchorage: Z.J. Loussac Public Library	(907) 562-7323
Arizona	Tempe: Noble Library, Arizona State University	(602) 965-7010
Arkansas	Little Rock: Arkansas State Library	(501) 682-2053
California	Los Angeles Public Library	(213) 228-7220
	Sacramento: California State Library	(916) 654-0069
	San Diego Public Library	(619) 236-5813
	San Francisco Public Library	(415) 557-4500
	Sunnyvale Center for Innovation, Invention and Ideas	(408) 730-7290
Colorado	Denver Public Library	(303) 640-6249
Connecticut	New Haven: Science Park Library	(203) 786-5447
Delaware	Newark: University of Delaware Library	(302) 831-2965
Dist. of Columbia	Washington: Howard University Libraries	(202) 806-7252
Florida	Fort Lauderdale: Broward County Main Library	(305) 357-7444
	Miami-Dade Public Library	(305) 375-2665
	Orlando: University of Central Florida Libraries	(407) 823-2562
	Tampa Campus Library, University of South Florida	(813) 974-2726
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4508
Hawaii	Honolulu: Hawaii State Public Library System	(808) 586-3477
Idaho	Moscow: University of Idaho Library	(208) 885-6235
Illinois	Chicago Public Library	(312) 747-4450
	Springfield: Illinois State Library	(217) 782-5659
Indiana	Indianapolis-Marion County Public Library	(317) 269-1741
	West Lafayette Siegesmund Engineering Library, Purdue University	(317) 494-2872
Iowa	Des Moines: State Library of Iowa	(515) 281-4118
Kansas	Wichita: Ablah Library, Wichita State University	(316) 689-3155
Kentucky	Louisville Free Public Library	(502) 574-1611
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Maine	Orono: Raymond H. Fogler Library, University of Maine	(207) 581-1678
Maryland	College Park: Engineering and Physical Sciences Library, University of Maryland	(301) 405-9157
Massachusetts	Amherst: Physical Sciences Library, University of Massachusetts	(413) 545-1370
	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Ann Arbor: Media Union Library, University of Michigan	(313) 647-5735
	Big Rapids: Abigail S. Timme Library, Ferris State University	(616) 592-3602
	Detroit: Great Lakes Patent and Trademark Center	(313) 833-3379
Minnesota	Minneapolis Public Library and Information Center	(612) 372-6570
Mississippi	Jackson: Mississippi Library Commission	(601) 359-1036
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 390
Montana	Butte: Montana College of Mineral Science and Technology Library	(406) 496-4281
Nebraska	Lincoln: Engineering Library, University of Nebraska-Lincoln	(402) 472-3411
Nevada	Reno: University of Nevada, Reno Library	(702) 784-6500 Ext. 257
New Hampshire	Concord: New Hampshire State Library	(603) 271-2239
New Jersey	Newark Public Library	(201) 733-7782
	Piscataway: Library of Science and Medicine, Rutgers University	(908) 445-2895
New Mexico	Albuquerque: University of New Mexico General Library	(505) 277-4412
New York	Albany: New York State Library	(518) 474-5355
	Buffalo and Erie County Public Library	(716) 858-7101

Reference Collections of U.S. Patents and Trademarks Available for Public Use in Patent and Trademark Depository Libraries—(continued)

State	Name of Library	Telephone Contact
North Carolina North Dakota Ohio	New York Public Library (The Research Libraries)	(212) 592-7000
	Raleigh: D.H. Hill Library, North Carolina State University	(919) 515-3280
	Grand Forks: Chester Fritz Library, University of North Dakota	(701) 777-4888
	Akron - Summit County Public Library	(303) 643-9075
	Cincinnati and Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 292-6175
Oklahoma	Toledo/Lucas County Public Library	(419) 259-5212
	Stillwater: Oklahoma State University Center for International Trade Development	(405) 744-7086
	Portland: Paul L. Boley Law Library, Lewis & Clark College	(503) 768-6786
Oregon	Philadelphia: The Free Library of	(215) 686-5331
Pennsylvania	Pittsburgh: Carnegie Library of	(412) 622-3138
	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
Puerto Rico	Mayaguez General Library, University of Puerto Rico	(787) 832-4040 Ext. 3459
Rhode Island	Providence Public Library	(401) 455-8027
South Carolina	Clemson University Libraries	(803) 656-3024
	Rapid City: Devereaux Library, South Dakota	(605) 394-6822
Tennessee	School of Mines and Technology	(615) 322-2775
	Memphis & Shelby County Public Library and Information Center	(901) 725-8877
Texas	Nashville: Stevenson Science Library, Vanderbilt University	(615) 322-2775
	Austin: McKinney Engineering Library, University of Texas at Austin	(512) 495-4500
	College Station: Sterling C. Evans Library, Texas A & M University	(409) 845-3826
	Dallas Public Library	(214) 670-1468
Utah	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
	Lubbock: Texas Tech University	Not Yet Operational
	Salt Lake City: Marriott Library, University of Utah	(801) 581-8394
Virginia	Richmond: James Branch Cabell Library, Virginia Commonwealth University	(804) 828-1104
	Seattle: Engineering Library, University of Washington	(206) 543-0740
Washington	Morgantown: Evansdale Library, West Virginia University	(304) 293-2510
West Virginia	Madison: Kurt F. Wendt Library, University of Wisconsin	(608) 262-6845
Wisconsin	Madison	(414) 286-3051
	Milwaukee Public Library	(307) 237-4935
Wyoming	Casper: Natrona County Public Library	(307) 237-4935

PATENT EXAMINING CORPS

BRUCE A. LEHMAN, Commissioner
LAWRENCE J. GOFFNEY Jr., Assistant Commissioner for Patents
EDWARD R. KAZENSKE, Deputy Assistant Commissioner for Patents
STEPHEN G. KUNIN, Deputy Assistant Commissioner for Patent Policy

PATENT EXAMINING GROUPS	Phone number Area Code 703	New Case Date*
CHEMICAL EXAMINING GROUPS		
GENERAL METALLURGICAL, INORGANIC, PETROLEUM AND ELECTRICAL CHEMISTRY, ENGINEERING AND DESIGNS, GROUP 1100— JOHN E. KITTLE, Director	308-0661	05/19/95
ORGANIC CHEMISTRY, DRUG, BIO-AFFECTING AND BODY TREATING COMPOSITION, GROUP 1200—RICHARD V. FISHER, Director	308-1235	07/26/95
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 1300—JOHN F. TERAPANE, Director	308-0651	08/03/95
HIGH POLYMER CHEMISTRY, PLASTICS, COATING, PHOTOGRAPHY STOCK MATERIALS AND COMPOSITIONS, GROUP 1500—THEODORE MORRIS, Director	308-2351	09/01/95
BIOTECHNOLOGY, GROUP 1800—JOHN J. DOLL, Director	308-0196	01/15/95
ELECTRICAL EXAMINING GROUPS		
INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 2100—STEWART LEVY, Director	308-1782	01/15/95
SPECIAL LAWS AND ADMINISTRATION, GROUP 2200—ROBERT E. GARRETT, Director	308-0511	05/25/95
COMPUTER SYSTEMS AND COMPUTER APPLICATION, GROUP 2300— JOSEPH J. ROLLA, Director	305-9600	02/15/95
SPECIAL COMPUTER APPLICATIONS: COMPUTER GRAPHICS, BUSINESS PRACTICES, & DIAGNOSTIC TESTING, GROUP 2400—GERALD GOLDBERG, Director	305-3800	02/25/95
ELECTRONIC AND OPTICAL SYSTEMS AND DEVICES, GROUP 2500— JANICE A. HOWELL, Director	308-0956	04/30/95
TELECOMMUNICATIONS, GROUP 2600—NICHOLAS P. GODICI, Director	305-4700	03/03/95
DESIGN, GROUP 2900—JOHN E. KITTLE, Director	308-0661	04/10/95
MECHANICAL EXAMINING GROUPS		
HANDLING AND TRANSPORTATION MEDIA, GROUP 3100—MARGARET FOCARINO, Acting Director	308-1113	07/02/95
MATERIAL SHAPING, ARTICLE MANUFACTURING AND TOOLS, GROUP 3200—ETHEL CROSS, Director	308-1148	06/15/95
MEDICAL INSTRUMENTS, DIAGNOSTIC EQUIPMENT AND TREATMENT DEVICES; SURGERY AND SURGICAL SUPPLIES; AMUSEMENT AND EXERCISING DEVICES; ANIMAL HUSBANDRY; SPORTING GOODS; TOBACCO PRODUCTS AND MANUFACTURING EQUIPMENT; AND PRINTING, GROUP 3300—J.J. LOVE, Director	308-0858	08/14/95
SOLAR, HEAT, POWER, AND FLUID ENGINEERING DEVICES, GROUP 3400—DONALD G. KELLY, Director	308-0861	07/14/95
GENERAL CONSTRUCTION, PETROLEUM AND MINING ENGINEERING, GROUP 3500—A.L. SMITH, Director	308-1021	09/03/95

*A communication from the examiner should have been received in most applications filed prior to this date.

Patents will Expire as Follows:

- (1) The term of any utility or plant patent that is in force on or results from an application filed before June 8, 1995 is the greater of the 20 year term provided in 35 U.S.C. 154(a)(2) or 17 years from grant subject to any terminal disclaimers. 35 U.S.C. 154(c)(1).
- (2) All utility and plant patents granted on applications having an actual United States filing date on or after June 8, 1995 are granted for a term which begins on the date on which the patent is granted and ends 20 years from the date on which the application was filed in the United States. If the application contains a specific reference to an earlier application under 35 U.S.C. 120, 121 or 365(c), the patent term ends twenty years from that date on which the earliest application was filed. 35 U.S.C. 154(a)(2).
- (3) All design patents are granted for a term of 14 years from the date of the grant. However, the term of any patent may have been curtailed by disclaimer under the provisions of 35 U.S.C. 153, have lapsed due to failure to pay maintenance fees, or have been extended under the provisions of 35 U.S.C. 154, 155, or 156. Thus, if more reliable information is needed with respect to a particular patent, then the specific patent file should be reviewed to determine the actual date of patent expiration.

TRADEMARK OPERATION

Bruce A. Lehman, Commissioner
 Philip G. Hampton, II, Assistant Commissioner
 Robert M. Anderson, Deputy Assistant Commissioner
 David E. Bucher, Director, Trademark Examining Office
 Condition of Trademark Applications as of November 1, 1996

	Oldest Date	
	New*	Amendment Filed
Law Office		
Law Office 101—Ron Williams, Managing Attorney, (703) 308-9101—4th Floor Foods, Beverages, Wines & Spirits—Int. Classes 29, 30, 31, 32, 33 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	04/29/96	08/12/96
Law Office 102—Myra Kurzbar, Managing Attorney, (703) 308-9102—5th Floor Scientific Equipment & Furniture—Int. Classes 9, 20 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	04/18/96	05/02/96
Law Office 103—Kathryn Erskine, Managing Attorney, (703) 308-9103—5th Floor Scientific Equipment & Furniture—Int. Classes 9, 20 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/02/96	10/18/96
Law Office 104—Sidney Moskowitz, Managing Attorney, (703) 308-9104—6th Floor Unwrought metals, Industrial Equipment, Tools, Installation, Vehicles, Firearms, Musical Instruments, Building Materials & Floor Coverings—Int. Classes 6, 7, 8, 11, 12, 13, 15, 19, 27 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/13/96	08/15/96
Law Office 105—Thomas Howell, Managing Attorney, (703) 308-9105—6th Floor Chemicals, Paints, Lubricants, Pharmaceuticals, Medical Apparatus & Tobacco—Int. Classes 1, 2, 4, 5, 10, 34 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/07/96	06/07/96
Law Office 106—Mary Sparrow, Managing Attorney, (703) 308-9106—7th Floor Cosmetics, Cleaning Preparations, Paper Products & Toys—Int. Classes 3, 16, 28 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/10/96	08/16/96
Law Office 107—Thomas Lamone, Managing Attorney, (703) 308-9107—7th Floor Cosmetics, Cleaning Preparations, Paper Products & Toys—Int. Classes 3, 16, 28 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/31/96	07/29/96
Law Office 108—David Shallant, Managing Attorney, (703) 308-9108—8th Floor Precious metals, Fibers, Leather goods, Housewares, Cordage, Yarns, Fabrics, Clothing & Notions—Int. Classes 14, 17, 18, 21, 22, 23, 24, 25, 26 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	07/10/96	06/14/96
Law Office 109—Deborah Cohn, Managing Attorney, (703) 308-9109—8th Floor Precious metals, Fibers, Leather goods, Housewares, Cordage, Yarns, Fabrics, Clothing & Notions—Int. Classes 14, 17, 18, 21, 22, 23, 24, 25, 26 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/18/96	07/30/96
**Collective Marks—Class 200 **Certification Marks—Classes A & B		
Office of Trademark Services—Terror Simms, Director, (703) 308-9100 Trademark Assistance Center—(703) 308-9000 Pre-Examination—Alan Lambert, Supervisor, (703) 308-9401 ext. 188 Intent-To-Use—(ITU)—(703) 308-9500 Post Registration Section—Mary Bowman, Supervisor, (703) 308-9500 ext. 126 Affidavits Under Sections 8 & 15 (All Classes)..... Renewals (All Classes)..... Section 12(c) Publications (All Classes).....	09/03/96 09/19/96 04/05/96	— — —

1. ** Assigned to all Law Office

2. Applicants with inquiries concerning the status of their applications and a touch telephone should call (703) 305-8747 from 6:30 a.m. to Midnight EST, Monday through Friday. This automated voice system will provide the current status of your application. Applicants are urged not to file unnecessary inquiries concerning the status of their applications. See SECTION 411 of the TRADEMARK MANUAL OF EXAMINING PROCEDURE.

3. * These dates identify the oldest unassigned new case in each Law Office. All cases with earlier dates have either been examined and made the subject of an action or are currently being worked on by the assigned examining attorney.

REEXAMINATIONS


DECEMBER 24, 1996

Matter enclosed in heavy brackets [] appears in the patent but forms no part of this reexamination specification; matter printed in italics indicates additions made by reexamination.

B2 4,981,472 (3081st)
CANNULA ASSEMBLY FOR SYRINGE
 James F. Ennis, III, Preston, Conn., and Mark Anderson, R.R. 2, Elmwood, Wis. 54740, assignors to Mark Anderson, Elmwood, Wis.

Reexamination Request No. 90/003,123, Jul. 9, 1993.
 Reexamination Certificate for Patent 4,981,472, issued Jan. 1, 1991, Ser. No. 439,180, Nov. 20, 1989.
 Int. Cl.⁶ A61M 5/00

U.S. Cl. 604—117



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 7-10 is confirmed.

Claims 1-6 and 11-16 are cancelled.

7. A cannula assembly for a syringe adapted for discharging medicinal fluid into a teat of an animal being treated comprising: a first cannula having an elongated first body of predetermined axial length terminating in a first free open end for discharging said fluid therefrom;

a first tubular jacket enclosing said cannula in axial alignment therewith;

first means on said cannula and said jacket for detachably engaging together with cannula and said jacket;

a second cannula integral with said jacket and extending axially forward of said open end of said first cannula in axial alignment therewith for receiving said fluid from said first cannula, said second cannula having an elongated body shorter in axial length than that of said first cannula and having a second free open end for discharging said fluid therefrom;

a second tubular jacket enclosing said second cannula in axial alignment therewith;

second means on said second cannula and said second jacket for detachably engaging together said second cannula and second jacket;

a third cannula integral with said second jacket and extending axially forward of said open end of said second cannula in axial alignment therewith for receiving said fluid from said second cannula, said third cannula having an elongated third body shorter in axial length than that of said second cannula and having a third free open end for discharging said fluid therefrom;

a tubular cap having opposite closed and open ends, said cap enclosing said third cannula when said third cannula is axially inserted into said cap through said open end of said cap; and

third means on said third cannula and said cap for detachably engaging together with third cannula and said cap;

whereby a user can select said third cannula for discharging said fluid by detaching said cap from said third cannula, whereby said user can select said second cannula for discharging said fluid by detaching said second jacket from said second cannula, and whereby said user can select said first cannula for discharging said fluid by detaching said first jacket for said first cannula.

B1 5,138,028 (3082nd)
POLYIMIDES END-CAPPED WITH DIARYL SUBSTITUTED ACETYLENE

Charles W. Paul, Madison; Rose A. Schultz, Princeton, and Steven P. Fenelli, Hillsborough, all of N.J., assignors to National Starch and Chemical Investment Holding Corporation, Wilmington, Del.

Reexamination Request No. 90/004,069, Nov. 3, 1995.
 Reexamination Certificate for Patent 5,138,028, issued Aug. 11, 1992, Ser. No. 823,508, Jan. 21, 1992.


Int. Cl.⁶ C08G 69/26; 8/02; 7/500; C08F 22/40

U.S. Cl. 528—353

AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1-32 is confirmed.

1. A polymerizable oligomer selected from the group consisting of polyamic acids, corresponding amic esters, corresponding isoimides, corresponding imides, and mixtures thereof, and wherein said polymerizable oligomer is end-capped with a diaryl substituted acetylene (DASA) having the general formula:



wherein m=0 to 5, L=0 to 4, R and R¹ are independently selected from the group consisting of halogen, C₁-C₄ alkyl, alkoxy, aryloxy, haloaryl, haloalkyl, haloacyl, aryl, and acyl, and X is a linking group to the oligomer backbone selected from the group consisting of NH₂, CHO, isocyanate, anhydride, carboxylic acid, ester, and acyl halide; provided that m or L≠0 when the oligomer backbone is composed of 2,2-bis(3,4-dicarboxyphenyl) hexafluoropropane dianhydride and 1,3-bis(3-amino-phenoxy) benzene and X=NH₂; and said polymerizable oligomer must have a glass transition temperature (T_g) greater than 135° C. after imidization, but prior to the onset of cure of the DASA end-caps.

B1 5,217,937 (3083rd)
SIO₂-CONTAINING COPPER OXIDE-CHROMIUM OXIDE CATALYST FOR THE HYDROGENATION OF FATTY ACIDS AND FATTY ESTERS

Michael Schneider, Ottobrunn-Riemerling; Gerd Maletz, Brückmühl, and Karl Kochloeff, Brückmühl/Heufeld, all of Germany, assignors to Sud-Chemie Aktiengesellschaft, Munich, Germany

Reexamination Request No. 90/003,937, Aug. 29, 1995.
 Reexamination Certificate for Patent 5,217,937, issued Jun. 8, 1993, Ser. No. 795,493, Nov. 21, 1991.

Claims priority, application Germany, Nov. 27, 1990, 4037729

Int. Cl.⁶ B01J 21/06; 21/08; 23/10; 23/26; 23/72

U.S. Cl. 502—242

AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1-8 is confirmed.

1. An acid-resistant catalyst for the hydrogenation of fatty acids or fatty acid esters or mixtures thereof which consists essentially of (in analytical terms) about 20 to about 70 weights percent CuO, about 20 to about 70 weight percent Cr₂O₃, about 1 to about 25 weight percent SiO₂ having a porosity (determined by the nitrogen adsorption method) of <0.1 cm³/g. and 0 to about 15 weight

percent of additional metal oxide selection from zirconium, cerium, or lanthanum oxide or mixture thereof, wherein said catalyst, after thermal treatment of the metal oxides or precursor compounds convertible into the oxides, has a specific surface area of about 8 m²/g to about 60 m²/g wherein the intensity ratio between the x-ray diffraction lines (XRD reflexes) of the copper oxide with d=0.232 nm and of the CuCr₂O₄ spinel with d=0.240 nm determined as a ratio of the reflex amplitudes is about 0.7 to about 40:1 and wherein the acid resistance as measured by the solubility of the copper in the catalyst in acid is a maximum of 200 mg as determined by stirring 10 grams of the catalyst in 10 weight percent acetic acid at 20° C. for 2 minutes.

REISSUES

DECEMBER 24, 1996

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

Re. 35,408

NASAL DEVICES

Bjorn Petruson, Goteborg, Sweden, assignor to Patent Development & Investment S.A., Luxembourg, Luxembourg

Original No. 5,479,944, dated Jan. 2, 1996, Ser. No. 701,621, May 14, 1991. Continuation of Ser. No. 391,010, May 17, 1989, abandoned. Application for reissue Mar. 28, 1996, Ser. No. 623,608

Claims priority, application United Kingdom, May 17, 1989, 8627600

Int. Cl.⁶ A61F 11/00

U.S. Cl. 128—858



1. A one-piece device for positioning in the nose comprising:
- (i) a pair of tabs for positioning in respective nostrils; and
 - (ii) an elongate connecting member resiliently interconnecting the tabs;
- wherein:
- (a) each tab is resilient and has a surface for engaging the outer side wall of the respective nostril, is relatively thin [se] so to project a relatively small distance from the outer side wall into the passage of the respective nostril and is formed from a resilient, relatively soft material whereby said surface may conform to the contours of said respective side wall;
 - (b) the connecting member is of a length sufficient to follow a path from one tab to the other over the septum of the nose;
 - (c) said connecting member is resiliently bendable from an inoperative configuration into an operative configuration in which the tabs are positioned within the nostrils, the connecting member follows said path over the septum, and there is a restoring force tending to return said connecting member to the inoperative configuration; and
 - (d) the restoring force is sufficient to maintain the device in the nose of a user by means of engagement of the tabs with their respective nostril by means of the tabs urging the respective side walls outwardly.

Re. 35,409


ELECTRICALLY ADDRESSABLE OPTO-ELECTRONIC INDICATOR FOR MAKING DYNAMIC EVALUATIONS OF MICROSCOPIC OR LARGER SUBJECTS

Sidney D. Moore, 760 Mansfield Dr., Claremont, Calif. 91711

Original No. 4,720,804, dated Jan. 19, 1988, Ser. No. 915,145, Oct. 3, 1986. Continuation-in-part of Ser. No. 638,896, Aug. 8, 1984, abandoned, which is a continuation-in-part of Ser. No. 422,823, Sep. 24, 1982, Pat. No. 4,531,052. Application for reissue Dec. 6, 1993, Ser. No. 165,015

Int. Cl.⁶ G02B 21/00; G06F 17/00

U.S. Cl. 364—525



1. An optical instrument for examining and evaluating a specimen wherein the instrument has an optical axis, comprising:
- means mounted on said optical axis of the instrument for producing an image of the specimen on a plane of focus disposed on said optical axis;
- opto-electronic indicator means mounted within the instrument on said optical axis for generating a multiplicity of electrically-addressable indicia which are visible on said plane of focus on the optical axis of the instrument for simultaneous viewing with the image of the specimen; and
- processor means for selectively addressing each of said indicia to cause said indicia to become visible on said plane of focus for viewing thereon With the specimen and for processing the addresses of the selected indicia to define a relationship between the selected indicia and the specimen.

VOL
11 93

ISS
4

DE
24

1996

UMI

PLANT PATENTS

GRANTED DECEMBER 24, 1996

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

9,757

STRAWBERRY PLANT NAMED 'AIRES'

Jose M. A. Lopez, Navarra, Spain, assignor to Plantas de Navarra, S.A., Navarra, Spain

Filed Aug. 9, 1995, Ser. No. 512,886

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—49

1 Claim

1. A new and distinct variety of strawberry plant, substantially as shown and described.

9,762

GERANIUM PLANT NAMED 'FISBRARIS'

Angelika Utecht, Montabaur, Germany, assignor to Florfis AG, Binningen, Switzerland

Filed Aug. 29, 1995, Ser. No. 518,893

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new and distinct cultivar of geranium plant named Fisbraris, as illustrated and described.

9,758

CARNATION PLANT NAMED 'VELVET'

Flavio Sapia, San Remo, Italy, assignor to Messick Company, Saratoga, Calif.

Filed Aug. 21, 1995, Ser. No. 517,106

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—70.7

1 Claim

1. A new and distinct cultivar of Carnation plant named Velvet, as illustrated and described.

9,763

GERANIUM PLANT NAMED 'FISVIDEO'

Angelika Utecht, Montabaur, Germany, assignor to Florfis AG, Binningen, Switzerland

Filed Aug. 29, 1995, Ser. No. 518,895

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new distinct cultivar of geranium plant named Fisvideo, as illustrated and described.

9,759

CARNATION PLANT NAMED 'PACO'

Flavio Sapia, San Remo, Italy, assignor to Messick Company, Saratoga, Calif.

Filed Aug. 21, 1995, Ser. No. 517,110

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—70.7

1 Claim

1. A new and distinct cultivar of Carnation plant named Paco, as illustrated and described.

9,764

GERANIUM PLANT NAMED 'FISBLU'

Angelika Utecht, Montabaur, Germany, assignor to Florfis AG, Binningen, Switzerland

Filed Aug. 29, 1995, Ser. No. 518,896

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new distinct cultivar of geranium plant named Fisblu, as illustrated and described.

9,760

CHRYSANTHEMUM PLANT NAMED 'PEACH CINDERELLA'

Cornelis P. Vandenberg, Salinas, Calif., assignor to Yoder Brothers, Inc., Barberton, Ohio

Filed Sep. 7, 1995, Ser. No. 525,312

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—78

1 Claim

1. A new and distinct Chrysanthemum plant named Peach Cinderella, as described and illustrated.

9,765

GERANIUM PLANT NAMED 'FISBRAVO'

Angelika Utecht, Montabaur, Germany, assignor to Florfis AG, Binningen, Switzerland

Filed Aug. 29, 1995, Ser. No. 518,897

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new and distinct cultivar of geranium plant named Fisbravo, as illustrated and described.

9,761

GERANIUM PLANT NAMED 'FISALB'

Angelika Utecht, Montabaur, Germany, assignor to Florfis AG, Binningen, Switzerland

Filed Aug. 29, 1995, Ser. No. 518,892

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new and distinct cultivar of geranium plant named Fisalb, as illustrated and described.

9,766

GERANIUM PLANT NAMED 'HWD CORELLI'

Gabriele Harring, Kerpen, Germany, assignor to Dummen Jungpflanzenkulturen, Rheinberg-Eversael, Germany

Filed Aug. 30, 1995, Ser. No. 520,860

Claims priority, application Germany, May 16, 1988, PEL 308

Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new and distinct cultivar of Geranium plant named HWD Corelli, as illustrated and described.

9,767

GERANIUM PLANT NAMED 'HWD RAVELINA'

Günter Dünmen, Rheinberg-Eversael, Germany, assignor to
Dünmen Jungpflanzenkulturen, Rheinberg-Eversael, Ger-
many

Filed Aug. 30, 1995, Ser. No. 521,401

Int. Cl.⁶ A01H 5/00

U.S. Cl. Plt.—87.12

1 Claim

1 A new and distinct cultivar of Geranium plant named HWD
Ravelina, as illustrated and described.

9,768

GUZMANIA 'PUNA GOLD'

David R. Shiigi, 35 Pau O Palae St., Hilo, Hi. 96720

Filed Jul. 20, 1995, Ser. No. 510,136

Int. Cl.⁶ A01H 5/00

U.S. Cl. Plt.—88.8

1 Claim

1. A new and distinct hybrid cultivar named Guzmania "Puna
Gold" obtained by crossing *Guzmania memoria* (*G. lingulata* vari-
ety minor crossed with *G. lingulata* variety major) and *Guzmania*
insignis (*G. lingulata* variety splendens with *G. zahnii*) substan-
tially as illustrated and described herein.

PATENTS

GRANTED December 24, 1996

ERRATA

For CLASS	See PATENT NO.
056-367	5,586,421
140-123	5,586,584
141-021	5,586,629
206-315	5,586,674
236-093	5,586,722
473-207	5,586,761
294-001	5,586,801
296-026	5,586,802
445-024	5,586,879
510-298	5,587,104
323-312	5,587,655
396-319	5,587,751
396-315	5,587,752
396-397	5,587,753
396-144	5,587,754
396-380	5,587,755
396-515	5,587,756
396-536	5,587,757
396-613	5,587,758
396-630	5,587,759
396-630	5,587,760
396-095	5,587,761
396-095	5,587,762
396-114	5,587,763
396-055	5,587,764
396-234	5,587,765
396-257	5,587,766
386-068	5,587,789
386-026	5,587,802
386-033	5,587,803

ERRATA-CONTINUED

For CLASS	See PATENT NO.
386-002	5,587,804
386-068	5,587,805
386-068	5,587,806
386-046	5,587,807
349-062	5,587,816
349-187	5,587,817
349-106	5,587,818
349-106	5,587,819
349-116	5,587,820
349-118	5,587,821
349-124	5,587,822
395-752	5,587,902
395-759	5,587,903
370-337	5,588,020
382-167	5,588,050

PATENTS

GRANTED DECEMBER 24, 1996

GENERAL AND MECHANICAL


5,586,339
OUTER PROTECTIVE GARMENT APPARATUS
 Betty S. Lathan, P.O. Box 184 Keuer Rd., Mount Alry, Ga. 30563
 Continuation of Ser. No. 55,276, May 3, 1993, abandoned.
 This application Feb. 28, 1995, Ser. No. 396,252
 Int. Cl.⁶ A41D 1/00; 13/00; 27/00
 U.S. Cl. 2-46 5 Claims



1. A new and improved outer protective garment apparatus, comprising:
 torso covering assembly means for protecting a torso of a wearer, said torso covering assembly means including an elastic, snugly-fitting, neck-encompassing assembly means for snugly fitting around the wearer's neck and for protecting the wearer's torso from contamination by entry of a contaminant via the wearer's neck,
 two arm covering assembly means, connected to said torso covering assembly means, for protecting a wearer's arms, each of said arm covering assembly means including an elastic, snugly-fitting, wrist-encompassing assembly means for snugly fitting around a wrist of the wearer and for protecting the wearer's arms from contamination by entry of a contaminant via the wearer's wrists, and
 pants assembly means, connected to said torso covering assembly means, said pants assembly means including an abdomen covering assembly means and two leg covering assembly means, each of said leg covering assembly means including an elastic, snugly-fitting, ankle-encompassing assembly means for snugly fitting around an ankle of the wearer and for protecting the wearer's legs and abdomen from contamination by entry of a contaminant via the wearer's ankles,
 wherein each of said elastic, snugly-fitting, neck-encompassing assembly means, said elastic, snugly-fitting, wrist-encompassing assembly means, and said elastic, snugly-fitting, ankle-encompassing assembly means includes an elastic element and includes thermoplastic material which retains said elastic element by a seam joined by heat welds which form a single melted region,
 wherein said torso covering assembly means and said arm covering assembly means are formed into a unified integrated structure,
 wherein said torso covering assembly means includes a first side assembly and a second side assembly, wherein said first side assembly includes a strip of contact adhesive material covered by a barrier sheet, such that said torso covering assembly means can be put on by the wearer, said barrier sheet can be removed, and said first side assembly can be adhered to said second side assembly,
 wherein said torso covering assembly means further includes an interior surface and an exterior surface,

a rip cord is attached to said interior surface of said torso covering assembly means, such that when said rip cord is pulled in a direction outward from said interior surface, said torso covering assembly means is torn apart by said rip cord, permitting removal of the outer protective garment apparatus, wherein the said pants assembly includes an interior surface and an exterior surface and said rip cord is also attached to said interior surface of said pants assembly means, such that when said rip cord is pulled in a direction outward from said interior surface, said pants assembly means is torn apart by said rip cord, permitting removal of the outer protective garment apparatus.

5,586,340
MULTIFUNCTION SWIMSUIT AND CASUAL WEAR UNDERGARMENT
 Peter J. Russo, 150 Rockland Rd., Guilford, Conn. 06437
 Filed Oct. 5, 1994, Ser. No. 318,083
 Int. Cl.⁶ A41D 7/00
 U.S. Cl. 2-67 1 Claim



1. A dual purpose molded swimsuit and undergarment for being worn by a person, comprising:
 a resilient waterproof, elastomeric material being contoured for tightly encasing at least a portion of the person's torso, including a portion of the abdomen, hips, crotch, bosoms and buttocks area, and having portions defining a pair of legholes;
 a prosthetic bra means being secured within the swimsuit at the front bosom regions and valve means for enabling selective pneumatic pressurization of each of said prosthetic bra bosom regions to a size and pressure for wearer customizing and selective enlargement of each of the bosom bulge regions of said swimsuit for selectively enhancing at least one bosom bulge swimsuit contour to a wearer selected size and for providing increased buoyance to the wearer of said swimsuit to facilitate floating and swimming activities, said swimsuit material being molded to form a relatively fade and stain resistant design pattern without stitched seams;
 the prosthetic bra means being integrally formed with the swimsuit and undergarment to have a sealed pocket section and a valve means to enable air to be put into said pocket to a pneumatic pressure in excess of the ambient air pressure; and
 a relatively intricate and colorful design member being integrally molded into the elastic material;
 and a pair of prosthetic pneumatically inflatable buttock enlarging members integrally molded into said swimsuit and undergarment;
 at least one cut out section of selected design for revealing predetermined torso sections of the wearer.

5,586,341

STOCKINGS AND METHODS THEREFORE


Bruce U. Hill, Jr., 735 Field Club Rd., Pittsburgh, Pa. 15238

Filed Sep. 29, 1995, Ser. No. 537,088

Int. Cl.⁶ A41B 11/00

U.S. Cl. 2—239

7 Claims



1. A stocking comprising:

a foot section;

a sleeve section extending upwardly from said foot section to at least midcalf in length, said sleeve section having a lower surface attached to said foot section and an upper section adjacent an opening adaption to receive the user's foot and leg; and

an orientation marker positioned only on said upper section of said sleeve section on a front side of said sleeve section, said orientation marker lying in a vertically extended plane which substantially symmetrically bisects said stocking, wherein said foot section and said lower surface of said sleeve section are free of said orientation marker.

5,586,342

ROTARY SIPHON FLUSHER


Randy C. Young, 201 Bridgecreek Dr., Myrtle Beach, S.C. 29575

Filed Jun. 6, 1995, Ser. No. 471,857

Int. Cl.⁶ E03D 1/06

U.S. Cl. 4—368

11 Claims



1. A rotary siphon flushing device for discharging a liquid from a liquid tank through a tank drainage port into a connected bowl, said rotary siphon flushing device comprising, in combination:

a. a siphon exhaust pipe having an open-air end and a tank insertion end connected to said tank drainage port;

b. a rotary pipe axially and movably secured to an axis point centrally located to said rotary siphon flushing device, said rotary pipe further comprising a tube insert member and a tube ballast member, said tube ballast member being adjacent to said siphon exhaust pipe when said liquid tank is filled and having a fill end, said tube insert member having a discharge end; and

c. a lever means for rotating said rotary pipe around said axis point such that said tube insert member inserts inside said open-air end of said siphon exhaust pipe when said liquid tank

is full inducing a siphoning action by initiating a continuous flow of said liquid from said fill end of said tube ballast member through said discharge end of said tube insert member.

5,586,343

WHEEL CHAIR WITH A REMOVABLE TOILET BOWL AND SEAT


Dawn M. Mayle, 827 W. River Rd. N., Elyria, Ohio 44035

Filed Aug. 21, 1995, Ser. No. 517,731

Int. Cl.⁶ A47K 11/06; A61G 7/02

U.S. Cl. 4—480

5 Claims



1. A wheel chair with a removable toilet bowl and seat, comprising:

a frame having two forward vertical rails and two rearward vertical rails with horizontal rails coupled therebetween to form a wheel chair with a push handle at the upper extent of the rearward vertical rails and wheels rotatably secured to the lower extent of the frame;

a pair of upper slide rails in a horizontal orientation and spaced parallel with respect to each other and coupled at their forward ends to the forward vertical rail and coupled at their rearward ends to the rearward vertical rail;

a pair of lower slide rails in a horizontal orientation and spaced parallel with respect to each other and coupled at their forward ends to the forward vertical rail and coupled at their rearward ends to the rearward vertical rail;

a pair of upper channels formed in the upper slide rails facing each other and laterally spaced by a first predetermined distance;

a pair of lower channels formed in the lower slide rails facing each other and laterally spaced by a first predetermined distance;

an upper tray formed in a planar configuration with enlarged horizontal lateral edges received in the upper channels and formed with a central planar surface to constitute a seat for a user; and

a lower tray with enlarged horizontal lateral edges received in the lower channels, the central extent of the lower tray being formed with a recess to function as a toilet.

5,586,344

PORTABLE TOILET

Tui-Chang Liang, No. 126, Sec. 1, Kuang Fu Road, San Chung City, Taiwan

Filed Jun. 13, 1995, Ser. No. 489,813


Int. Cl.⁶ A47K 11/02

U.S. Cl. 4—484

4 Claims

1. A portable toilet, comprising:

a base including two tubular side members connected transversely by two horizontal tubes, and an insert tube pivotably connected by a bending part to each of the two tubular side members so that each insert tube is capable of approximately a 90 degree displacement relative to a tubular side member;



1. A mobile portable playyard system which is easily transportable, comprising:

a playyard structure which collapses into a generally rectangular shape including a plurality of corner legs, at least one corner leg having a foot attached thereto and at least one corner leg having a wheel attached thereto; and

a carrying case having a top portion, a side portion, and a bottom portion, the bottom portion defining a wheel opening formed through the bottom portion such that the wheel can extend therethrough, and defining a foot opening formed through the bottom portion such that the foot can extend therethrough.

5,586,346

METHOD AND APPARATUS FOR SUPPORTING AND FOR SUPPLYING THERAPY TO A PATIENT

Richard B. Stacy; Craig D. Ellis, both of Charleston; Barry D. Hand; James M. C. Thomas, both of Mt. Pleasant; Kenith W. Chambers; Stephen E. Glover, both of Charleston; Richard I. Barnett; Paul B. King, both of Mount Pleasant, all of S.C.; Ryszard S. Ozarowski, Marietta, Ga., and William T. Sutton, Charleston, S.C., assignors to Support Systems, International, S.C.

Filed Feb. 15, 1994, Ser. No. 196,847

Int. Cl.⁶ A61G 7/04

U.S. Cl. 5—710

38 Claims

a bowl having a seat and a container which is integral with the seat, the seat having a bottom with a front, rear, left side and right side, a recessed member disposed at the front and rear of the seat bottom to receive and mate with the two horizontal tubes, a hook disposed at each of the right and left sides of the seat bottom, said hooks adapted to have a waste bag suspended therefrom

an upper frame including two generally n-shaped tubes which are pivotably connected to each other at ends thereof by bending parts and are thereby capable of being pivotably disposed by approximately 180 degrees to each other, and one of the generally n-shaped tubes has two spaced-apart bent members extending therefrom and an inert tube extending from each of the two bent members;

two suspension tubes whose diameter is larger than the diameters of the insert tubes of the base and the upper frame, each suspension tube having opposite ends, with one end of each suspension tube mating with an insert tube of the base and an opposite end of each suspension tube mating with an insert tube of the upper frame, thereby connecting the upper frame to the base,

a cloth cover extending downward from the upper frame to cover all of said portable toilet; and

a trunk for storing the portable toilet in a disassembled condition.

5,586,345

MOBILE PORTABLE PLAYYARD SYSTEM


Robert A. Nielsen, Morgantown, Pa., and Vladimiro Pizzi, Scanzorosciate, Italy, assignors to Graco Children's Products, Elverson, Pa.

Filed Nov. 9, 1995, Ser. No. 556,057

Int. Cl.⁶ A47D 7/00; B65D 65/02

U.S. Cl. 5—99.1

17 Claims



1. A patient support surface, comprising:

a support assembly;

a first longitudinal cushion set coupled to said support assembly, said first longitudinal cushion set including a plurality of generally parallel cells, and extending a portion of the longitudinal length of said support assembly;

a second longitudinal cushion set coupled to said support assembly, said second longitudinal cushion set including a plurality of generally parallel cells and also extending a second, longitudinally offset portion of the longitudinal length of said support assembly; and

an inflatable support layer disposed generally above said first and second longitudinal cushion sets.

5,586,347

MATTRESS WITH AN INTEGRATED AIR SYSTEM
 Willi Frischknecht, Schönengrund, Switzerland, assignor to Airlux AG, Regensdorf, Switzerland
 PCT No. PCT/CH93/00110, § 371 Date Sep. 15, 1994, § 102(c) Date Sep. 15, 1994, PCT Pub. No. WO93/21803, PCT Pub. Date Nov. 11, 1993


PCT Filed Apr. 30, 1993, Ser. No. 295,751

Claims priority, application Switzerland, May 6, 1992, 1449/92

Int. Cl.⁶ A47C 27/08

U.S. Cl. 5—713

11 Claims



1. A mattress for beds or seating furniture, the mattress comprising:

a cushion, an air cell, and an in-the-mattress pump system wherein the pump system comprises: a pump body, an air reservoir and a pressure regulating valve, wherein the air cell is connected to the pump system so that said pump system replenishes air lost from said air cell with air from the air reservoir and regulates pressure in the air cell by the pressure regulating valve.

5,586,348

AIR MATTRESS AND METHOD FOR ADJUSTING IT
 Ilkka Toivio, Terttu Toivio, both of Lahti, and Kari Olkkonen, Kaustua, all of Finland, assignors to Ahlstrom Consumer Products Ltd., Finland


Continuation-in-part of Ser. No. 625,940, Dec. 11, 1990, abandoned, which is a continuation-in-part of Ser. No. 209,978, Jun. 22, 1988, Pat. No. 4,999,867. This application Jan. 27, 1993, Ser. No. 9,648

Claims priority, application Finland, Jun. 24, 1987, 872813

Int. Cl.⁶ A47C 27/10

U.S. Cl. 5—710

26 Claims



1. A mattress, comprising:
 a bottom part;

a plurality of elongate, bag-like first mattress elements, each said first mattress element enclosing a first fluid chamber for a flowing medium, said first elements being essentially parallel to each other and transverse to the longitudinal axis of said mattress, and said first elements being fixed to said bottom part at least at one fixing joint essentially parallel to the longitudinal direction of the mattress element, two mattress elements at the most constitute an arched structure, which is directed upward from the bottom part and is transverse to the longitudinal direction of the mattress, the fluid chambers of

the mattress elements being inflatable with a flowing medium up to a suitable pressure while using the mattress; and wherein the first mattress elements are divided, in the direction of the longitudinal axis of the mattress, into at least three groups, the elements of each of these groups being connectable, via conduits, to a fluid supply, so that the fluid pressure in the elements of each group can be adjusted to be suitable when the mattress is being used.

5,586,349

TROLLEYS


Keith Hannant, Rustington, England, assignor to Smiths Industries Public Limited Company, London, England
 Filed Feb. 17, 1995, Ser. No. 390,518

Claims priority, application United Kingdom, Mar. 4, 1994, 9404181

Int. Cl.⁶ A47B 9/10; A47C 19/04

U.S. Cl. 5—614

5 Claims



1. A trolley comprising: a base; a support column; a first mechanism for altering the height of the support column; a top surface supported by said column above said base; a second mechanism for altering the angle of said top surface relative to said support column, said first and second mechanisms being so interconnected that the height of said support column cannot be increased without automatically causing said top surface to move to a horizontal position; said first mechanism including an hydraulic actuator and a pump, said first mechanism being operative to initially supply hydraulic fluid to an actuator in said second mechanism for altering the angle of said top surface and to subsequently supply hydraulic fluid to said actuator in said first mechanism for altering the height of said support column; said trolley including an overpressure valve, an hydraulic line connecting said valve between said pump and said actuator in said first mechanism, an hydraulic line connected between said pump and said actuator in said second mechanism, said overpressure valve being closed at low pressure such that fluid from said pump flows to said actuator in said second mechanism until said top surface is horizontal, and wherein fluid pressure increases after said top surface is horizontal thereby causing said valve to open and to allow fluid to flow to said actuator in said first mechanism.

5,586,350

LOW FLAMMABILITY PILLOW

Franz Thönnessen, Bobingen, and Hans H. Mühlhaus, Kriftel, both of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Filed Jun. 28, 1994, Ser. No. 267,426


Claims priority, application Germany, Jun. 30, 1993, 9309699 U

Int. Cl.⁶ A47G 9/02


U.S. Cl. 5—636

18 Claims

1. A low flammability pillow comprising a cushioning core and a cover separable therefrom, wherein the cushioning core com-



prises a binder-consolidated nonwoven block from 5 to 15 cm in thickness and from 500 to 3000 g/m² in basis weight comprising fibers or filaments having a linear density from 3 to 50 dtex and the cover is a pocket-shaped, closable casing comprising a textile sheet material comprising woven or knitted fabric, the fibers and filaments of the cushioning core and of the casing comprising flame resistant polyester, and wherein the flame resistant polyester contains cocondensed structural units of the formula I



(I)

where R is alkylene or polymethylene of 2 to 6 carbon atoms or phenyl and R¹ is alkyl of 1 to 6 carbon atoms, aryl or aralkyl.

5,586,351

INFANT SUPPORT PAD WITH ADJUSTABLE PILLOW


Ronald A. Ives, 12848 W. Ellsworth Pl., Lakewood, Colo. 80228

Filed Mar. 7, 1995, Ser. No. 399,911

Int. Cl.⁶ A47D 15/00; A47G 9/00

U.S. Cl. 5—655

21 Claims



1. A support article adapted to engage an infant's head, neck and shoulders in order to provide lateral stability to the infant's head and neck, comprising:

(a) a pad adapted to be placed against a support, said pad having a first surface upon which said infant can be placed in a reposed position and a second surface opposite said first surface; and
 (b) an upstanding support pillow secured to said pad and including a central portion extending in an arcuate configuration around a region that is sized and adapted to receive the infant's head when said infant is in the reposed position and a pair of end portions disposed on opposed ends of said central portion and projecting in laterally outward directions from one another thereby to define shoulder supports that are positionable against the infant's shoulders when the infant's head is received within said region, said end portions adapted to be supported by the infant's shoulders and said end portions and said central portion operative to provide stability to

the head and neck of said infant by resisting lateral movement of said infant when said infant is in the reposed position.

15. A support article adapted to engage an infant's head, neck and shoulders in order to provide lateral stability to the infant's head and neck, comprising:

(a) an elongated pad having a longitudinal axis and adapted to be positioned against a support and having a first surface upon which said infant can be placed in a reposed position, said pad including a lower portion having a pair of lateral side edges and an upper portion having an upper peripheral edge extending arcuately around a majority of a circle and terminating at peripheral edge ends located laterally inwardly of said lateral side edges, said side edges respectively connected to the peripheral edge ends of said upper peripheral edge by respective inwardly extending medial edges each formed at an obtuse angle with respect to an associated one of said side edges such that said upper peripheral edge and said medial edges form a pair of opposed V-shaped cut-outs which define a medial portion of said pad between said upper portion and said lower portion with said medial portion being of reduced transverse dimension with respect thereto; and

(b) a raised support pillow disposed on said pad alongside the upper peripheral edge to terminate proximate to said medial portion, said support pillow including a central portion extending in an arcuate configuration around a region that is sized and adapted to receive the infant's head when said infant is in the reposed position and a pair of end portions disposed on opposed ends of said central portion and projecting in laterally outward directions from one another thereby to define shoulder supports that are positionable against the infant's shoulders when the infant's head is received within said region, said end portions adapted to be supported by the infant's shoulders and said end portions and said central portion operative to provide stability to the head and neck of said infant by resisting lateral movement of said infant when said infant is in the reposed position.

5,586,352

SUPPORT POLE WITH A PIVOTING AND LOCKING

HANDRAIL FOR ELDERLY AND DISABLED PERSONS


John L. O'Brien, 1682 Station Boulevard, Ottawa, Ontario, Canada; Edward M. Thomas, 522 Gascon St. P.O. Box 131, Russell, Ontario, Canada, and Donald A. N. Ed, 662 Windermere Ave., Ottawa, Ontario, Canada

Filed May 2, 1994, Ser. No. 236,113

Int. Cl.⁶ A61G 12/00; 7/053

U.S. Cl. 5—662

12 Claims



1. A support pole for assisting elderly and disabled persons with a pivoting and locking handrail unit comprising a pole member having means at its upper end and at its lower end to support said pole member in a vertical operating position wherein said hand rail unit comprises a cylindrical member having a tubular handrail member radially mounted thereon said handrail member being

positioned below the upper end of the pole member and above the lower end of the pole member.

5,586,353 PLASTIC FASTENER FOR SHOE-LASTING APPLICATIONS

F. Gerard Merzer, Round Pond, Me., assignor to Avery Dennison Corp., Pasadena, Calif.
Continuation of Ser. No. 968,397, Oct. 29, 1992, Pat. No. 5,438,724. This application Apr. 19, 1995, Ser. No. 424,910
Int. Cl.⁶ A43D 9/00; 5/00; B65D 77/10
U.S. Cl. 12—142 LC 9 Claims




1. A fastener comprising:
 - (a) an elongated flexible filament having a first end and a second end;
 - (b) a cross-bar disposed at said first end of said elongated flexible filament, said cross-bar having a pair of ends; and
 - (c) a paddle disposed at said second end of said elongated flexible filament, said paddle being provided with three alternative openings through any one of which both ends of said cross-bar may be completely inserted to form a rounded loop, wherein said three alternative openings are arranged generally parallel to the longitudinal axis of said elongated flexible filament so that three different sized loops may be formed.

5,586,354 METHOD FOR FORMING PATTERNS ON SHOE SOLE

Kuan-Jen Chi, Da Li, Taiwan, assignor to Kuan M. Chi, Da Li, Taiwan
Filed May 11, 1995, Ser. No. 439,175
Int. Cl.⁶ A43D 8/24 1 Claim


1. A method for forming a pattern on a shoe sole comprising: preparing a material for forming said shoe sole, preparing a film, providing a pattern on said film, attaching said film onto said material so as to engage said pattern with said material, disengaging said film from said material so as to allow transferring of said pattern onto said material, and molding said material so as to allow infiltrating of said pattern in said material and so as to form a shoe sole body, wherein said shoe sole body includes an outer peripheral surface having said pattern provided therein and includes a bottom portion having a cavity formed therein, said shoe sole includes an insert for engaging in said cavity.



5,586,355 SAFETY DEVICE FOR A VERTICALLY STORED DOCK LEVELER

Donald Metz, Kirkville, N.Y., and James C. Alexander, London, Canada, assignors to United Dominion Industries, Inc., Charlotte, N.C.
Filed Mar. 21, 1995, Ser. No. 408,038
Int. Cl.⁶ E01D 15/127 11 Claims

U.S. Cl. 14—69.5




7. A vertically storing dock leveler comprising, a movable deck, a power source to move the deck up into a vertical stored position and to lower said deck into a generally horizontal operative position, and a sensor positioned under the deck and movable therewith to stop downward deck movement when said sensor is tripped.

5,586,356 AUTOMATIC RETURN TO DOCK MECHANISM FOR MECHANICAL DOCK LEVELER

James C. Alexander, London, Canada, assignor to United Dominion Industries, Inc., Charlotte, N.C.
Filed Nov. 27, 1995, Ser. No. 563,061
Int. Cl.⁶ E01D 1/00 6 Claims

U.S. Cl. 14—71.1


1. A dockboard comprising: a frame, a deck pivotally mounted to said frame, a lip pivotally mounted to an outboard end of said deck; said lip having an arm mounted to a lower surface, a crank mechanism comprising a pivoting arm member mounted to said frame, a pushrod extending under said deck having one end thereof coupled to said pivoting arm member and a slot member attached to the other end of said push rod, said slot member having a slot engaging a portion of said arm mounted to said lip,



5,586,358 HAND CARRIABLE VACUUM CLEANER WITH ACCESSORY ATTACHMENT

Jack Wolfe, Discovery Bay, and Roy C. C. Ping, North Point, both of Hong Kong, assignors to Bissell, and TTI
Filed Aug. 15, 1994, Ser. No. 290,429
Int. Cl.⁶ A47L 5/32 11 Claims

U.S. Cl. 15—334




- a spring to bias said slot member to urge engagement between said slot and said arm mounted to said lip, and
- a hold down mechanism to permit said deck to raise and lower, said hold down mechanism including a linkage to said pivoting arm member, whereby as said lip moves from an extended position to a pendant position, said pushrod is moved in one direction by action of said arm engaged in said slot causing said pivoting arm member to disengage said hold down mechanism allowing said deck to raise and, as said lip continues to fall said arm moves in said slot allowing said push rod to move in a second direction thereby allowing said hold down mechanism to re-engage said deck and return to dock level.

5,586,357 HAND-HELD SCRATCH TICKET SCRAPER

Steven J. Kosakowski, 125 R Baldwinville Rd., Winchendon, Mass. 01475, and Brian A. Chipman, 151 Hosley Rd., Gardner, Mass. 01440
Filed Jul. 10, 1995, Ser. No. 501,419
Int. Cl.⁶ A47L 13/022 20 Claims

U.S. Cl. 15—111




1. A lottery game scratch ticket scraper for use with a lottery game scratch ticket of the type having a planar surface with rows of indicia hidden by a removable covering, said scraper comprising:

- a planar main body, said main body having a planar upper side defining a thumb lying area and a lower side defining a forefinger lying area, said main body further having a front end and a rear end;
- at least one appendage protruding from said main body, said at least one appendage comprising an arcuate strip of material which lies outside the plane defined by said planar main body, said arcuate strip of material having a crescent-shaped cross-sectional shape for preventing breakage, wherein said at least one appendage has an attached end and a scraping end, said attached end being attached to said front end of said main body and said scraping end for scraping the covering off a lottery game scratch ticket and said scraper further comprising a brush means attached to said rear end of said main body for brushing off game ticket covering scrapings wherein said brush means comprises bristles extending substantially in the same plane as said planar main body.

5,586,359 LEAF VACUUM WITH ROTARY CUTTING BLADE

Gleichi Iida, Tokyo, Japan, assignor to Kioritz Corporation, Tokyo, Japan
Filed Jun. 29, 1995, Ser. No. 496,415
Claims priority, application Japan, Jul. 4, 1994, 6-174794
Int. Cl.⁶ A47L 7/02 17 Claims

U.S. Cl. 15—339



11. An outdoor vacuum cleaner for picking up and shredding leaves and other debris, the vacuum cleaner comprising: a housing having an inlet and an outlet; a suction tube detachably mounted to the housing at the inlet; a fan located within the housing for creating suction in the suction tube; a motor for driving the fan; a rotary blade located in the suction tube;


a stationary blade mounted in the suction tube between the fan and the rotary blade at a location proximate the rotary blade; a transmission shaft rotatably secured to the fan and extending from the fan past the stationary blade to the rotary blade, whereby the rotary blade is rotatably secured to the transmission shaft and the transmission shaft is supported on the stationary blade; wherein fan pieces are provided on the rotary blade such that rotation of the rotary blade creates suction.

5,586,360

ATTACHMENT FOR PNEUMATIC CLEANING DEVICE
Everett G. Diederiks, Jr., Lake Ridge, Va., and Edwin E. Puett, Jr., Stuart, Fla., assignors to Anser Tool & Machinery Technologies, Inc., Stuart, Fla.

Filed Jul. 5, 1995, Ser. No. 498,053
Int. Cl.⁶ A47L 9/02; 9/32

U.S. Cl. 15—410



1. An attachment for a pneumatic cleaning device comprising: an elongated, rigid tubular member having a first end portion and a second end portion, the first end portion of said rigid tubular member being adapted to be attached to a pneumatic cleaning device;

a flexible tubular member having an associated length and including a first end and a second end, the first end of said flexible tubular member being attached to the second end portion of said rigid tubular member;

a rigid, tubular end piece being attached to the second end of said flexible tubular member, said end piece terminating at a portion remote from said flexible tubular member in a nozzle portion; and

a tubular, rigid cover member having an associated length that is longer than the associated length of said flexible tubular member, said cover member defining an associated inner diameter that is greater than an associated outer diameter of each of said rigid tubular member and said flexible tubular member, said cover member being movably mounted between a first position wherein said cover member extends between the second end portion of said rigid tubular member and said end piece and about said flexible tubular member in order to maintain said flexible tubular member in a straight posture and a second position wherein said cover member extends about said rigid tubular member in order to enable said flexible tubular member to assume a curved posture.


5,586,361
DOOR STOP, IN PARTICULAR FOR MOTOR VEHICLE DOORS

Karl-Heinz Tölle, Wuppertal, and Hermann Grothe, Remscheid, both of Germany, assignors to Ed. Scharwachter GmbH & Co. KG., Remscheid, Germany
Filed Sep. 21, 1995, Ser. No. 531,681

Claims priority, application Germany, Sep. 21, 1994, 44 33 648.9

Int. Cl.⁶ E05F 3/04
U.S. Cl. 16—51

10 Claims



19 Claims

1. A door stop for enabling an unhindered movement of a door in a first door opening angular region and for stepless stopping and retaining the door in an arbitrary selected opening position in a second opening angular region, the door stop comprising:

a hydraulic cylinder connectable to one of a door assembly part, a door and a door frame;

a stop piston longitudinally displaceable in said hydraulic cylinder, said piston separating two pressure chambers formed in a cavity of said hydraulic cylinder;

a piston rod fixedly secured to said stop piston for connecting said stop piston with another part of the door assembly;

two separate conduits formed in said stop piston for communicating said two pressure chambers with each other;

two closing pistons respectively located in said two separate conduits and displaceable therein in opposite directions between an open position, in which they permit flow of a pressure medium through said two separate conduits, respectively, from one of the pressure chambers to another of the pressure chambers, and a closing position, in which they block the fluid flow through said two separate conduits, each of said closing pistons being formed of at least two parts and has at least one axial pressure relief bore extending between respective two parts;

spring means for biasing said two closing pistons to the closing positions thereof; and

a by-pass conduit formed in said hydraulic cylinder and by-passing said stop piston for directly communicating said two pressure chambers with each other.

5,586,362

ANTI-RUBBING BLOCK

Neil M. Baker, Barnwood, United Kingdom, assignor to Securistyle Limited, Cheltenham, United Kingdom
Filed Dec. 15, 1994, Ser. No. 357,857

Claims priority, application United Kingdom, Apr. 14, 1994, 9407370

Int. Cl.⁶ E05D 13/00


31 Claims

U.S. Cl. 16—193

1. An anti-rubbing block for a friction stay, said stay including a track having sidewalls with edges, a slider mounted in the track, and a link connected to the slider and adapted to be connected to a vent arm, said anti-rubbing block comprising:

a body for positioning within the track, said body extending above the track to prevent rubbing of the link on the track; said body having extending lips for overlying the edges of the side walls of the track; and

said body having a flange extending from the body substantially parallel to the track, during use, for attachment to the slider such that the anti-rubbing block moves with the slider along the track during opening and closing of the stay.



5,586,363

INDEXING HINGE


John M. Fanuzzi, Hwy. 89 Seven Point Ranch, Emigrant, Mont. 59027

Filed Apr. 6, 1995, Ser. No. 417,941

Int. Cl.⁶ E05C 17/64; E05D 11/08

U.S. Cl. 16—342

13 Claims



1. An indexing hinge, comprising:

a first sleeve having an interior surface;

a second sleeve, with an interior surface;

a plurality of longitudinal channels formed circumferentially in said interior surface of said second sleeve and extending substantially the length thereof;

a hollow shaft with a first end and a second end with at least one first opening on said first end and a second plurality of openings formed circumferentially along said second end of said shaft;

a lip on said second end of said shaft;

said first end of said shaft inserted thru said second sleeve until said lip engages said second sleeve and second plurality of openings on said shaft are aligned with said channels of said second sleeve;

said first sleeve inserted onto said first end of said shaft so to cover said first opening on said shaft and said shaft is non-rotatably affixed to said first sleeve;

a plunger with a first end and a second end;

a first circumferential channel formed on the outside of said first end of said plunger with at least one sloped side and a second circumferential channel formed on the outside of said second end of said plunger;

said plunger inserted into said shaft so that said first circumferential channel of said plunger is aligned with said second plurality of openings on said shaft and said second circumferential channel of said plunger is aligned with said first opening on said shaft;

a first detent inserted into said second circumferential channel of said plunger and thru said first opening on said shaft; and a second detent inserted into each of said second plurality of openings on said shaft.

5,586,364


FASTENING ELEMENT FOR HARDWARE PARTS AND HINGE EMBODYING SUCH ELEMENTS

Franco Ferrari, Frazione Deviscio 2, 22053 Lecco, and Carlo Migli, Lecco, both of Italy, assignors to Franco Ferrari, Italy
Filed Apr. 24, 1995, Ser. No. 427,066

Claims priority, application Italy, May 13, 1994, M1940353 U
Int. Cl.⁶ E05D 5/00

U.S. Cl. 16—383

15 Claims



1. A fastening element for fastening hardware elements to parts of furniture units, comprising a plug which has therethrough an opening defining an axial housing between opposed side walls of the plug which are expandable, said housing having therein a pin, said pin having opposed side portions thereof extended in a direction crosswise to the axis of said housing and being rotatable between a first position in which the side walls of the plug are not expanded to enable one end thereof to be inserted into a hole in the furniture unit, and a second position in which the plug side walls are expanded by said extended side portions of said pin to enable said plug to be anchored in the hole, and characterized by the fact that the confronting surfaces of the axial housing and of the extended side portions of the pin have reciprocal contacting surfaces in the expanded position which are divergent in the direction of said one end of the plug.

5,586,365

FIBER TUFT FEEDER FOR A FIBER PROCESSING TEXTILE MACHINE

Ferdinand Leifeld, Kempen, and Armin Leder, Mönchengladbach, both of Germany, assignors to Trützschler GmbH & Co. KG, Mönchengladbach, Germany

Filed Sep. 22, 1995, Ser. No. 532,855

Claims priority, application Germany, Sep. 24, 1994, 44 34 251.9

Int. Cl.⁶ D01G 15/40; 23/02; 15/74

20 Claims

U.S. Cl. 19—105

1. A fiber tuft feeder comprising


(a) a first chute having an upper, inlet end and a lower, outlet end;

(b) charging means for introducing fiber tufts into said first chute through said inlet end;

(c) a feed roller supported at said outlet end of said first chute; said feed roller having a rotary axis;

(d) an opening roller adjoining said feed roller and being supported below said feed roller; said opening roller having a rotary axis; said opening roller receiving fiber tufts from said feed roller; an imaginary plane containing said rotary axes dividing said feed roller and said opening roller into first and second sides; said opening roller throwing fiber tufts to said first side;

(e) drive means for rotating said feed roller and said opening roller;



- (f) a second chute extending downwardly from said opening roller at said first side of said feed roller and said opening roller; said second chute having an upper, initial portion extending generally tangentially to said opening roller;
- (g) densifying air stream generating means for introducing an air stream into said second chute to densify the fiber tufts therein; and
- (h) guide means for directing said densifying air stream to flow consecutively along said feed roller and said opening roller on said first side; said guide means including means for directing said densifying air stream circumferentially about a significant part of a surface of said feed roller.

5,586,366


APPARATUS FOR CLEANING AND OPENING FIBER TUFTS

Ferdinand Leifeld, Kempen, and Konrad Temburg, Mönchengladbach, both of Germany, assignors to Trützschler GmbH & Co. KG, Mönchengladbach, Germany
Filed Oct. 4, 1995, Ser. No. 539,056

Claims priority, application Germany, Nov. 5, 1994, 44 39 564.7

Int. Cl.⁶ D01G 9/16; 9/14; 9/12; 9/06
U.S. Cl. 19—105

19 Claims



1. A fiber tuft feeding device for a fiber processing machine, comprising
- (a) a fiber advancing member having a first fiber-contacting surface;
- (b) an extruded, light-metal feed tray having a second fiber-contacting surface defining, with said first fiber-contacting surface, a nip between which the fiber tufts pass in a feed direction; said feed tray having a length extending transversely to the feed direction; said feed tray having an elongated cavity extending parallel to said length;

- (c) an elongated element received in said cavity and extending parallel to said length; said elongated element being resistant to bending; and
- (d) support means for positioning said feed tray adjacent said fiber advancing member.

5,586,367


HOOK CLOSURE FOR BOOT

Louis Benoit, La Balme de Sillingy, France, assignor to Salomon S.A., Metz-Tessy, France
Filed Oct. 30, 1995, Ser. No. 550,301

Claims priority, application France, Nov. 2, 1994, 94 13343
Int. Cl.⁶ A43C 11/00

U.S. Cl. 24—68 SK

11 Claims



1. Hook closure for a boot having a shell comprising on one side, a control assembly provided with an elastic means for returning to the position pressed against the shell of the boot, which assembly is constituted by a plurality of elements of which a lever-puller, a hooking buckle, and a base, connected between them by journals, and on the other side a hooking element adapted to cooperate with the buckle, at least one of the elements being obtained from a metallic wire in the form of an open buckle whose ends of the arms are curved to assure the linkage by journaling with the other elements on which it is mounted, wherein the elastic return means is integrated with one of the elements made in the form of an open buckle, which, obtained in a flexible metallic wire, has two arms of which at least one of the curved ends is offset by a value "X" and is fixed in a corresponding hole offset by the same value "X" and obtained on the other element, thus assuring the linkage by journaling between the two elements and the elastic return function thereof.

5,586,368

LOCKING ATTACHMENT

Richard L. Nelson, R.R. #3, Box 50 H, Pelican Rapids, Minn. 56572


Filed May 8, 1995, Ser. No. 436,527

Int. Cl.⁶ A44B 19/00

U.S. Cl. 24—390

1 Claim

1. A zipper lock attachment for a pair of jeans wherein the jeans have a pair of front panels with a zipper mounted across the inner edges of the front panels for opening and closing the front panels, and wherein a button is mounted to one of the panels above the zipper with the other of the front panels having a button opening for buttoning said other of said panels to said one panel, comprising a one piece ring like resilient rod formed into a ring like shape and having its remote ends overlapping one another in parallel relation for a portion of the length of the rod with the ends spring urged together along an upper portion of its ring like shape, said ring like rod having a downwardly bent loop portion along the bottom of its ring like shape bent downward into a relatively small loop with relatively small inner radius in



relation to the ring like rod's inner radius and with the small loop formed about an axis perpendicular to the axis of the ring like rod,

wherein said ring like rod have its upper overlapping ends manually urged apart sufficiently to insert their ends into an eyelet of a zipper handle of the zipper, and when said zipper has been zipped upward to close the zipper opening, the upper overlapping ends of the ring like rod be slipped over the button of the jeans to secure the zipper in its upper closed position on the panels of the jeans with the zipper handle resting in the small loop of the rod.

5,586,369

DOUBLE-LAYER SLIDE FASTENER TAPE


Yoshio Matsuda; Shunji Akashi, and Hiroshi Yoshida, all of Toyama-ken, Japan, assignors to YKK Corporation, Tokyo, Japan

Filed Aug. 30, 1995, Ser. No. 520,857

Claims priority, application Japan, Aug. 31, 1994, 6-206208
Int. Cl.⁶ A44B 19/00

U.S. Cl. 24—392

4 Claims



1. A slide fastener tape woven or knitted so as to form a coupling element attaching edge portion, a tape body portion and a tape sewing portion arranged in order transversely of said tape,

wherein said tape has a double-layer structure portion composed of a front cloth and a back cloth joined together by a connecting yarn with a predetermined gap therebetween extending transversely over a predetermined region of said tape, said connecting yarn being a synthetic resin monofilament or multifilament, said back cloth of the double-layer structure portion being a section formed of at least a mesh woven or knitted fabric.

5,586,370

SEPARABLE BOTTOM STOP ASSEMBLY FOR SLIDE FASTENER


Tsutomu Fudaki, Toyama-ken, Japan, assignor to YKK Corporation, Tokyo, Japan

Filed Jul. 21, 1995, Ser. No. 505,758

Claims priority, application Japan, Jul. 29, 1994, 6-178747
Int. Cl.⁶ A44B 19/38

U.S. Cl. 24—433

8 Claims



1. A separable bottom stop assembly for a slide fastener, comprising:

- (a) a box having on one side thereof a stopper-insertion hole communicating with a box-pin-insertion hole;
- (b) a box pin adapted to be mounted to a lower end of one fastener stringer of a pair of fastener stringers of the slide fastener and inserted in said box-pin-insertion hole;
- (c) a separable pin adapted to be mounted on a lower end of a second fastener stringer of the pair of fastener stringers of the slide fastener; and
- (d) a stopper from said box and said box pin inserted in said stopper-insertion hole to press said box pin against a partition of said box in such a manner that said box, said box pin and said stopper are fixedly joined together.

5,586,371

METHOD FOR MANUFACTURING REFASTENABLE FASTENING SYSTEMS INCLUDING A FEMALE LOOP FASTENING COMPONENT AND THE PRODUCT PRODUCED THEREFROM


Dennis A. Thomas, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

Filed Nov. 8, 1994, Ser. No. 336,277

Int. Cl.⁶ A44B 18/00

U.S. Cl. 24—452

9 Claims



1. A fastening system, comprising:
a male component including a plurality of extending hooks;
a female component including a substrate comprising a sheet of flexible material and a multiplicity of female formed loop

members deposited onto and joined to said substrate, each of said loop members including:

(a) a base comprising the plane of attachment of said member to said substrate such that said member is joined at said base to said substrate;

(b) a shank having a proximal end and a distal end, said proximal end being contiguous with said base, said shank projecting longitudinally outwardly from said base and said substrate, said distal end fusing with another loop member thereby providing an opening through which at least one of said hooks may project upon fastenably contacting the male and female components.


5,586,372

FASTENING DEVICE

Tomoo Eguchi, Utsunomiya, and Goro Asami, Machida, both of Japan, assignors to Nifco Inc., Yokohama, Japan
Filed Mar. 4, 1996, Ser. No. 610,337
Claims priority, application Japan, Apr. 5, 1995, 7-103190
Int. Cl.⁶ A44B 1/00

U.S. Cl. 24-452

8 Claims



1. A fastening device comprising:
two fastening members, each having a flat base portion and a plurality of engaging projections fixed on the base portion, said engaging projections extending from one side of the base portion and being arranged laterally and vertically, each engaging projection having at least one leg fixed to the base portion at one side and an engaging head portion fixed to the other side of the leg, said engaging head portion having a lateral size greater than that of the leg, and
non-engaging projections integrally formed on at least one of the fastening members, each non-engaging projection having a height less than the engaging projection so that in case the two fastening members are engaged, when one engaging projection projecting toward one non-engaging projection is pushed laterally by another engaging projection situated adjacent to said one non-engaging projection, an engaging head portion of said one engaging projection is pushed toward said one non-engaging projection and then is returned to an original position by said one non-engaging projection to thereby engage engaging head portions of said one and another engaging projections.

5,586,373
CLAMP


Devon Eby, Nappanee; Dale Love, Goshen, and James L. Reed, Nappanee, all of Ind., assignors to Grrreat Creations, Inc., Nappanee, Ind.

Filed Sep. 6, 1995, Ser. No. 524,263
Int. Cl.⁶ A44B 21/00; F16B 7/00

U.S. Cl. 24-525

7 Claims

1. A clamp comprising a pair of relatively movable clamping members made of a material other than metal, a pair of clamping



pods, each of said members including a pair of arms, one arm of each member carrying one of the clamping pods such that the clamping pod of one member opposes the clamping pod of the other member, the other arm of said one member being stepped to define a larger cross-section portion and a smaller cross-section portion with a shoulder therebetween, said smaller portion extending from said larger cross-section portion, the other arm of said other member slidably engaging the smaller portion of the other arm of said one member, said one arm of said one member extending from said larger portion, a bore extending through said larger portion substantially parallel to said smaller portion, and adjustable fastening means extending through said bore and then parallel to said smaller portion thereby interconnecting said other arm of said other member and said other arm of said one member for moving the members relative to one another whereby adjustment of the fastening means moves the clamping pods toward and away from one another.

5,586,374

CLASP MECHANISM


Shoichi Nishida, No. 3-2, Nishi-Ichlnoe, 4-Chome, Edogawa-Ku, Tokyo, Japan

Filed Dec. 14, 1994, Ser. No. 356,919

Int. Cl.⁶ A45F 5/02; F16B 45/02; A44B 13/02

U.S. Cl. 24-599.8

10 Claims



10. A clasp, comprising:
a) a main body;
b) a hook;
c) said main body having opposed sides defining a cavity therebetween, said body including a web disposed between said opposed sides, said web including a pair of eyelets for receiving a ring;
d) said hook including an arc-shaped portion for securing to an article, said arc-shaped portion including a free end;
e) said hook including a base portion adapted to be disposed within said cavity and pivotably secured to said opposed sides for movement between closed and open positions, said base portion including opposed side walls;
f) a mating end secured to said main body and extending therefrom, said mating end being adapted to engage said free end of said arc-shaped portion when in the closed position; and
g) a spring operably disposed within said main body cavity and between said base portion opposed side walls for biasing said arc-shaped portion in the closed position.

5,586,375

TWO-PIECE SHOWER CURTAIN HOOK


Barbara Cooperman, New York, N.Y., and Robert M. Huff, Clark, N.J., assignors to Springs Industries, Inc., Fort Mill, S.C.

Filed Sep. 30, 1994, Ser. No. 316,189

Int. Cl.⁶ A44B 17/00

U.S. Cl. 24-716

7 Claims



1. A shower curtain hook, including:
a hook including a body for permitting the shower curtain hook to hang from a shower curtain rod, a tail for supporting a shower curtain thereon, and a positioning plate supported on said tail, said tail being constructed to support a shower curtain positionable intermediate said positioning plate and said hook; and a decorative cover having a mounting means, said mounting means being adapted to receive said positioning plate so that said decorative cover may be releasably secured to said positioning plate.

5,586,376

DECORATIVE CASKET CARRYING AND PRESENTATION TRAY


John R. Enneking, and John Schultz, both of Batesville, Ind., assignors to Batesville Casket Company, Batesville, Ind.

Filed Oct. 24, 1994, Ser. No. 327,579

Int. Cl.⁶ A61G 17/00

U.S. Cl. 27-27

22 Claims



1. A decorative casket carrying and presentation tray comprising:
a generally rectangular casket support adapted to bear and display a casket thereon; and
pallbearer handles mounted on either side of said support movable laterally into and out of said support to and between an

exposed, operable position wherein said handles are graspable by a pallbearer and a concealed, inoperable position wherein the laterally outboard ends of said handles are flush with said support and said handles are hidden from view.

5,586,377

SYSTEM FOR COVERING A CUSHION MEMBER WITH A TRIM COVER ASSEMBLY


Kazuo Katsuta, and Tadafumi Abe, both Akishima, Japan, assignors to Tachi-S Co., Ltd, Tokyo, Japan

Filed Nov. 30, 1994, Ser. No. 351,103

Int. Cl.⁶ B68G 7/00

U.S. Cl. 29-91.5

12 Claims



1. A system for covering a cushion member with a trim cover assembly, in which the trim cover assembly is formed in a sack-like configuration having a top section, a first side section, a second side section facing said first side section, an interior surface, an exterior surface and a pair of lateral sections, said trim cover assembly further having an anchor device on an inside surface of said second side section, the cushion member being formed from a foam material having an upper wall, lower wall and four side walls and further including an anchoring point, to which said anchor device is to be secured, said system comprising:

a first movable securing and support means for temporarily securing and supporting thereon said upper wall of said cushion member and said top section of said trim cover assembly at a predetermined position, wherein said interior surface of said trim cover assembly is turned outwardly thereby rendering said interior surface outwardly facing when secured on said first movable securing and support means;
a second movable securing and support means for temporarily securing and supporting thereon said lower wall of said cushion member;
a first drive means for causing said first movable securing and support means and said second movable securing and support means to be moved in a first direction;
a covering guide means for supporting and guiding said trim cover assembly and turning said outwardly facing interior surface inwardly onto said four side walls of said cushion member, said covering guide means being arranged so as to surround said first movable securing and support means;
said covering guide means comprising:
a first guide element for pressing and guiding said first side section of said trim cover assembly alongside of said first movable securing and support means;
a second guide element for pressing and guiding said second side section of said trim cover assembly alongside of said first movable securing and support means; and

a pair of third guide elements, each pressing and guiding a respective lateral section of said pair of lateral sections of said trim cover assembly;

a pressing means for applying a pressure to a part of said cushion member corresponding to said anchoring point, thereby rendering said part of said cushion member thin, to make said anchoring point accessible;

a second drive means for moving said covering guide means in a second direction opposite to said first direction; and

a switch means operable to start and stop said first drive means and said second drive means and to activate said pressing means;

wherein said covering guide means and said first movable securing and support means and said second movable securing and support means may be moved toward each other through said first drive means and said second drive means by operation of said switch means so as to cause said first side section, said second side section and said paired lateral sections of said outwardly facing interior surface to be turned inwardly by said first guide element, said second guide element and said pair of third guide elements onto said four side walls of said cushion member, and said pressing means may be activated by operation of said switch means to make said anchoring point of said cushion member and permitting said anchor means of said trim cover assembly to be manually secured to said anchoring point, wherein said cushion member is precisely and neatly covered with the trim cover assembly with said anchor means being secured to said anchoring point.

5,586,378

BALL JOINT EXTRACTOR


Steven D. Smith, 1115 Ward St., Centalla, Wash. 98531-5047

Filed Jul. 18, 1994, Ser. No. 276,838

Int. Cl.⁶ B23P 19/04

U.S. Cl. 29—257

1 Claim



1. A ball joint clamp comprising:

a C-shaped clamp having an elongated vertical component at its central extent and having two horizontal parallel legs comprised of an upper leg and a lower leg extending from opposing ends thereof;

a fixed jaw in a U-shaped configuration having parallel legs in a horizontal orientation and a curved coupling section therebetween, the coupling section secured at its interior end to the outboard end of the upper leg, the U-shaped jaw having a horizontal lower surface and an upper surface angling downward from its curved coupling section with the interior surface of the U-shaped jaw being chamfered whereby the upper surface of the U-shaped jaw has a smaller surface area on its upper surface than its lower surface with the coupling section being a curve having an axis parallel with the axis of the long leg of the U-shaped member;

a cylindrical member with a threaded central aperture and an exterior surface secured at one edge to the exterior surface of the lower leg of the C-shaped clamp with the axis of the cylindrical member being co-extensive with the axis of the U-shaped member and parallel with the axis of the long leg of the C-shaped member; and

a bolt having a thread exterior surface rotatably coupled to the threads of the cylindrical member, the upper end of the threaded bolt being formed with an enlarged disk having a spherical recess facing the U-shaped member and having a head at its lower end rotatable at the discretion of the user, the disk being shaped to contact the free end of a ball joint pin and push it through its supporting aperture;

a handle component having a lower end and an upper end and a leg component with an outboard end and a threaded exterior end adapted to be threadably coupled to the central portion of the elongated vertical component on the side thereof remote from its legs but parallel therewith, the outboard end of the leg component being formed with an aperture positionable to be co-axial with an aperture at the upper end of the handle component, a toothed interface between the upper end of the handle component and the outboard end of the leg component and a bolt with a wing nut adapted to be positioned through the apertures of the handle and leg component for effecting a secure coupling therebetween at a predetermined angle.

5,586,379

STABILIZING OF CAM IN AUTOMATED BEVERAGE FILLING MACHINERY


Terry E. Nish, Salt Lake City, Utah, assignor to Servi-Tech, Inc., Salt Lake City, Utah

Division of Ser. No. 168,692, Dec. 16, 1993, abandoned. This application Apr. 14, 1995, Ser. No. 422,376

Int. Cl.⁶ B23P 6/00; 11/00

U.S. Cl. 29—401.1

9 Claims



1. A method for modifying an automatic beverage filling machine to insure accurate filling of successive containers comprising the steps of:

- providing a cam comprising a cantilevered end forming part of a cam assembly for a fill valve of the automatic beverage filling machine;
- fabricating one bearing segment at the cantilevered end of the cam;
- fabricating a second matching bearing segment as a separate piece;
- placing the two bearing segments into mating contiguous rotatable relation within a cam housing of the cam assembly;
- non-rotatably securing the second bearing segment to the cam housing so as to retain the mating contiguous rotatable relationship between the two bearing segments.

5,586,380

METHOD FOR MAKING MATED MOLDED PARTS ASSEMBLY


Dennis S. Shimmell, Hudsonville, Mich., assignor to Nelson Metal Products Corporation, Grandville, Mich.

Division of Ser. No. 994,272, Dec. 21, 1992, Pat. No. 5,387,472, which is a continuation-in-part of Ser. No. 886,694, May 20, 1992, Pat. No. 5,313,703. This application Oct. 18, 1994, Ser. No. 324,797

Int. Cl.⁶ B23P 15/00

U.S. Cl. 29—413

5 Claims



1. A method for making an assembly of mated parts comprising the steps of:

- forming a first part with a mating surface and at least one protrusion extending from the mating surface, said protrusion formed with a head joined to said mating surface by a narrowed neck portion;
- subsequent to the forming of said first part, forming a second part in place with said first part such that the material of said second part envelops said protrusion, captures said head, and mates precisely with the mating surface of said first part; and forcibly separating said first and second parts until said narrowed neck portion of said protrusion breaks.

5,586,381

METHOD FOR THE PRODUCTION OF A DEVICE FOR THE TRANSMISSION OF A SIGNAL BETWEEN TWO END POINTS

Friedrich Schauer, Heroldsberg, and Andreas Neuner, Nürnberg, both of Germany, assignors to Kabelmetal elektro GmbH, Hanover, Germany

Continuation of Ser. No. 223,779, Apr. 6, 1994, abandoned.


This application Nov. 24, 1995, Ser. No. 562,551

Claims priority, application Germany, May 4, 1993, 43 14 648.1

Int. Cl.⁶ B23P 11/00

U.S. Cl. 29—434

7 Claims



1. A method for making a device comprising a substantially circular cassette for transmitting a signal between two end points at least one of which is movable relative to the other, wherein the device is adapted to hold a wound cable which forms a coil between the two end points, wherein extending lines are connected to the cable at the two end points, and wherein the cassette comprises two parts, a first of said parts being a stator, and a second of said parts being a rotor which rotates around an axis and around the stator, the method comprising the steps of:

injection molding said first cassette part using a first mold, said first cassette part comprising a first annular disk with a first cylindrical tube extending concentrically from said first disk; providing a second mold comprising said first cassette part, and a further mold part extending into said first tube of said first cassette part;

injection molding said second cassette part using said second mold, said second cassette part comprising a second annular disk with a second cylindrical tube extending concentrically from said second disk, said second tube, while in said second mold, being disposed between said further mold part and said first tube; and

cooling said second tube to obtain a shrinking of said second tube away from said first tube to produce a gap between said first and said second tubes, said gap allowing said cassette parts to rotate relative to each other around a common axis of said two cassette parts.

5,586,382

RIGHT ANGLE TURNING ATTACHMENT FOR MILLING MACHINE


Charles F. Ganem, 1 Key Way P.O. Box 154, Cape Neddick, Me. 03902

Filed Apr. 5, 1995, Ser. No. 417,517

Int. Cl.⁶ B23Q 37/00; B23C 9/00

U.S. Cl. 29—560

6 Claims



1. A right angle drive, for converting a milling machine to a lathe, comprising:

- a housing having a bore therein and a clamping means for releasably attaching said right angle drive to a milling machine;
- a drive shaft having at least one bearing mounted in the housing, the drive shaft being connectable to a milling machine spindle;
- a through hole spindle having at least one bearing mounted in the housing, the through hole spindle extending at a right angle to the drive shaft;
- a drive mechanism connecting the drive shaft to the through hole spindle for driving the through hole spindle; and
- a device for holding material in the through hole spindle and for clamping and unclamping material as desired.

5,586,383

STATOR WINDING METHOD


Patrick A. Dolgas, Clermont County; Ballard E. Walton, Bethel Township, Miami County, and Larry E. Staton, Clark County, all of Ohio, assignors to Globe Products Inc., Huber Heights, Ohio

Division of Ser. No. 17,111, Feb. 12, 1993, Pat. No. 5,394,046, which is a continuation-in-part of Ser. No. 950,262, Sep. 23, 1992, abandoned, which is a continuation-in-part of Ser. No. 948,399, Sep. 21, 1992, abandoned. This application Feb. 27, 1995, Ser. No. 394,718

Int. Cl.⁶ H02K 15/08

U.S. Cl. 29—596

13 Claims



1. A method for winding a stator core for a permanent magnet motor, said stator core having a circular first end face and a circular second end face, said end faces having outer margins spaced by and adjoined to a cylindrical outer wall having a center axis,

a first set of axially-outwardly projecting coil-retaining members in mutually-spaced relation on the outer margin of said first end face,

a second set of axially-outwardly projecting coil-retaining members on the outer margin of said second end face, individual ones of said coil-retaining members of said second set being aligned with individual ones of said coil-retaining members of said first set, said coil-retaining members of said first set each having outer extremities projecting beyond said first end face, said coil-retaining members of said second set each having outer extremities projecting beyond said second end face, said method comprising the steps of:

winding coils of wire around individual pairs of said first set of said coil-retaining members and individual pairs of said second set of coil-retaining members aligned with said individual pairs of said first set of coil-retaining members, said coils having sides extending along said outer wall, a first end extending over said first end face, a second end extending over said second end face, and corners joining the aligned pairs of said first and second coil-retaining members; and

while winding said coils, guiding the wires forming said ends so that the respective ends of said coils do not project beyond said end faces as far as the outer extremities of said coil-retaining members.

5,586,384

STATOR MANUFACTURING METHOD AND APPARATUS

Lawrence E. Newman, Tipp City, Ohio, assignor to Globe Products Inc., Huber Heights, Ohio


Filed Apr. 28, 1995, Ser. No. 430,738

Int. Cl.⁶ H02K 15/085

U.S. Cl. 29—596

8 Claims

1. Stator manufacturing apparatus for winding stator coils on a stator core at a winding station, temporarily clamping the coil lead wires leading to and from the coils by temporary wire clamps, and for removing the stator coil lead wires from the temporary wire clamps at a coil lead terminating station, said apparatus comprising:



a stator support track that supports a stator being wound at the winding station, that extends from the winding station to the coil lead terminating station, and that supports a stator at the coil lead terminating station while lead wire terminations are being made;

a stator transfer assembly comprising a main carriage that shuttles between the stator winding station and the coil lead terminating station, a stator bore-engaging pin mounted on said carriage that moves a wound stator supported by said support track from said stator winding station and said coil lead terminating station, and temporary wire clamps mounted on said carriage; and

a stator clamp assembly at said coil lead terminating station that clamps a wound stator against said support track when a wound stator is located at said coil lead terminating station, thereby permitting said transfer assembly to be shuttled back to the winding station before all of the lead wires are terminated at the coil lead terminating station.

5,586,385

METHOD OF MANUFACTURING A THIN FILM MAGNETIC HEAD

Hiromi Nishino, Kitakatsuragi-gun, and Akiyoshi Fujii, Ikoma-gun, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 213,917, Mar. 15, 1994, abandoned.


This application Feb. 13, 1996, Ser. No. 599,858

Claims priority, application Japan, Mar. 16, 1993, 5-055970; Dec. 27, 1993, 5-332864

Int. Cl.⁶ G11B 5/127; B29C 45/14

U.S. Cl. 29—603.16

10 Claims



1. A method of manufacturing a thin film magnetic head, said head including, on a resin substrate thereof, an element portion for reading a magnetic signal, and a wiring connection portion connected to a terminal wiring for taking out an electric signal from the element portion, said method comprising the steps of:

forming said element portion on the resin substrate;

connecting said terminal wiring to said wiring connection portion;

inserting said resin substrate and said terminal wiring into a mold;

injecting resin material into said mold to form a resin cover of said magnetic head and to form a tape guide of said magnetic head, said resin cover and said tape guide being formed of the same resin material and integrally with each other; and

shaping an end of said resin substrate in the vicinity of said element portion to form a magnetic recording medium sliding surface.

5,586,386

SENSOR FOR USE WITH AIR BAG INFLATOR AND METHOD FOR MAKING

Daniel Morin, North Providence, R.I., assignor to Texas Instruments Incorporated, Dallas, Tex.


Division of Ser. No. 323,955, Oct. 17, 1994, Pat. No. 5,504,288.

This application Nov. 16, 1995, Ser. No. 559,217

Int. Cl.⁶ H01H 35/34

U.S. Cl. 29—622

4 Claims



1. A method for making a monitoring system for a vehicular inflator air bag system in which a first gas mixture for use in inflating an air bag is stored in a container at a prescribed pressure at a selected temperature, the first gas mixture selected from any two amounts of the group of gases consisting of argon, nitrogen and helium and having a pressure vs temperature curve with a given slope comprising the steps of forming a reference gas chamber, taking a snap acting disc having opposed first and second face surfaces, mounting the snap acting disc so that the first face surface is exposed to the first gas mixture and the second face surface is exposed to gas in the reference gas chamber, filling the reference gas chamber with a second gas mixture at a selected pressure lower than the pressure of the first gas mixture at the selected temperature, said second gas mixture selected from the group of gases for the first gas mixture and including at least one additional gas and having a pressure vs temperature curve with a slope steeper than the slope of the pressure vs temperature curve of the first gas mixture and choosing a sufficient quantity of the additional gas so that the slope of the pressure vs temperature curve of the first and second gas mixtures are essentially the same.

5,586,387

AUTOMATED PART ASSEMBLY MACHINE

Takuya Nakatani, Hirakata; Mitsutaka Abe, Yahata; Shigeru Dono, Osaka, and Youji Urano, Shijonawate, all of Japan, assignors to Matsushita Electric Works, Ltd., Osaka, Japan


Filed Dec. 21, 1994, Ser. No. 360,568

Claims priority, application Japan, Dec. 22, 1993, 5-325460; Sep. 27, 1994, 6-231867

Int. Cl.⁶ B23P 21/00

U.S. Cl. 29—703

23 Claims



1. An automated parts assembling machine comprising: a work table supported to a base and movable relative thereto; at least two separate robots each having an end effector movable around within an individual work region, said at least two separate robots positioned in such a relation as to give a common work region in which individual work regions of said at least two separate robots overlap;

parts supply means arranged adjacent to said work table for storing parts to be picked-up by said at least two separate robots;

a plurality of operator hands selectively and removably attached to at least one of said end effector of said at least two separate robots for handling parts;

jig means disposed within said common region in order to position said parts for assembly by said at least two separate robots;

control means for controlling operations of said at least two separate robots and moving said work table;

wherein said at least two separate robots are mounted on said movable work table together with said operator hands and said jig means, said at least two separate robots spaced in a moving direction of said work table, and wherein said parts supply means extends in the moving direction of said work table.

5,586,388

METHOD FOR PRODUCING MULTI-BOARD ELECTRONIC DEVICE

Yasunohu Hiran, Toyokawa; Yuji Motoyama, Okazaki; Takashi Nagasaka, Anjo, and Hidekazu Katsuyama, Nukata-gun, all of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan

Continuation-in-part of Ser. No. 118,785, Sep. 10, 1993, Pat. No. 5,408,383, which is a continuation of Ser. No. 889,701, May 29, 1992, abandoned. This application Mar. 6, 1995, Ser. No. 400,243

Claims priority, application Japan, May 31, 1991, 3-157672


Int. Cl.⁶ H05K 3/36

U.S. Cl. 29—830

13 Claims

1. A method for producing an electronic device having circuit boards which mount electronic circuits thereon and which are arranged in a multi-board structure within a casing, said method comprising the steps of:

preparing a frame forming said casing;



engaging a first plate on which a first circuit is mounted with said frame to form a plate of said frame;
arranging a second plate on which a second circuit is mounted inside said frame at an intermediate position of said frame and with an interposing space between said first plate and said second plate;
injecting a coating agent into said interposing space between said first and second plates through an injection aperture provided on a side surface of said frame and at a position between said first plate and said second plate, so as to completely cover said first circuit with said coating agent;
injecting said coating agent over a surface of said second plate through an aperture provided in said frame, so as to completely cover said second circuit with said coating agent; and simultaneously curing said coating agent covering both said first and second circuits, when said coating agent has completely covered said first and second circuits.

5,586,389


METHOD FOR PRODUCING MULTI-BOARD ELECTRONIC DEVICE

Yasunobu Hirao, Toyokawa; Makoto Koyama, Kariya, and Yuji Motoyama, Okazaki, all of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan

Division of Ser. No. 118,785, Sep. 10, 1993, Pat. No. 5,408,383, which is a continuation of Ser. No. 889,701, May 29, 1992, abandoned. This application Mar. 6, 1995, Ser. No. 400,242 Claims priority, application Japan, May 31, 1991, 3-157674 Int. Cl.⁶ H05K 3/30; H01R 43/24; H05K 3/36

U.S. Cl. 29—841

11 Claims



1. A method for producing an electronic device casing, said casing including a resin frame for arranging at least two circuit boards in a mutually parallel relationship to each other and at least one connecting metallic lead disposed inside a side wall of said frame, said connecting metallic lead including an intermediate portion, a first contacting portion for electrically connecting with a first circuit board, and a second contacting portion for electrically connecting with a second circuit board, said method comprising the steps of:

arranging said connecting metallic lead as an insert in a cavity of a mold for molding said frame;
pressing said intermediate portion of said connecting metallic lead with an extended portion of a supporting plate which extends through a groove in said mold toward said cavity so as to press said first and second contacting portions of said connecting metallic lead against a surface of said cavity and to fix said connecting metallic lead in said cavity; and
molding said frame while pressing said connecting metallic lead against said mold cavity surface with said extended portion of said supporting plate so as to fix said connecting metallic lead in said cavity.

5,586,390

METHOD OF MAKING JEWELRY ARTICLES


Josef J. Barr, 777 W. Flagler Dr., West Palm Beach, Fla. 33402

Filed Jul. 3, 1995, Ser. No. 498,033

Int. Cl.⁶ A44C 25/00; 5/00; B21F 43/00

U.S. Cl. 29—896.411

2 Claims



1. The method of forming a generally planar article of jewelry which comprises the steps of:

- a) providing a planar sheet of precious metal of thickness ranging from 0.008 to 0.020 inch;
- b) using a corresponding male and female die set, stamping a portion of said sheet to form an article of overall rectangular configuration including a design in relief, and, including additional peripheral material along the longitudinal and end edges thereof;
- c) bending said additional peripheral material through substantially 180 degrees to form a peripheral re-enforcing liner to increase the effective thickness of said article at the periphery thereof.

5,586,391

METHOD OF MAKING AIRPLANE FUSELAGE

Antonio C. Micale, Seattle, Wash., assignor to The Boeing Company, Seattle, Wash.


Division of Ser. No. 964,533, Oct. 13, 1992, Pat. No. 5,560,102.

This application Jun. 6, 1995, Ser. No. 468,217

Int. Cl.⁶ B23Q 17/00

U.S. Cl. 29—897.2

3 Claims



1. A method of making an airplane fuselage section from a plurality of individual subassemblies including panels, frame members and a floor grid, comprising:

- drilling coordination holes in the marginal regions of said panels said panels each including longitudinal stiffening stringers, stringer clips, and shear ties fastened thereto;
- aligning said coordination holes in adjacent edges of a plurality of panels;
- fastening said panels together temporarily with temporary fasteners through said aligned coordination holes;
- clamping said panels together along said adjacent edges;
- drilling holes in said adjacent edges of said panels with a single drill plunge for each hole during said clamping of said panels;
- riveting said panels together along said adjacent edges through the drilled holes during said clamping of said panels to produce a superpanel;
- drilling a coordination hole in each of said stringer clips of said superpanel and corresponding coordination holes in said frame members;
- orienting said frame members on station planes adjacent corresponding stringer clips;
- aligning said coordination holes in said stringer clips with said corresponding coordination holes in said frame members;
- fastening said frame members to said stringer clips temporarily with temporary fasteners through their aligned coordination holes;
- clamping said frame members to said stringer clips and to said shear ties fastened to said superpanel and extending between said stiffening stringers along said station planes;
- drilling holes in said frame members and their corresponding stringer clips with a single drill plunge for each hole during said clamping of said frame members;
- riveting said frame members and their corresponding stringer clips together through the drilled holes during said clamping of said frame members;
- drilling holes in said frame members and corresponding shear ties with a single drill plunge for each hole during said clamping of said frame members;
- riveting said frame members and their corresponding shear ties together through the drilled holes during said clamping of said frame members;
- drilling a coordination hole adjacent each end of a plurality of cross members of said floor grid, and corresponding coordination holes in said frame members at each location therealong at which it is desired to connect said floor grid to said frame members;
- orienting said floor grid adjacent said frame members and aligning said coordination holes in said cross members of said floor grid with said corresponding coordination holes in said frame members;
- fastening said cross members to said frame members temporarily with temporary fasteners through their aligned coordination holes;
- clamping said floor grid cross members to said frame members;
- drilling holes in said cross members and said frame members with a single drill plunge for each hole during said clamping of said cross members;
- fastening said cross members and said frame members together through the drilled holes during said clamping of said cross members to form a fuselage lower lobe;
- drilling coordination holes along two longitudinally extending edges of said fuselage lower lobe, and along two corresponding longitudinally extending edges on a fuselage upper lobe;
- orienting said fuselage upper lobe over said fuselage lower lobe and aligning said coordination holes along said longitudinally extending edges of said fuselage upper lobe with said corresponding coordination holes along said longitudinally extending edges of said fuselage lower lobe;
- sealing and temporarily fastening said upper lobe and said lower lobe with temporary fasteners along said longitudinally extending edges through their aligned coordination holes;
- clamping said fuselage upper and lower lobes together along said longitudinally extending edges;

drilling holes in said fuselage upper and lower lobes with a single drill plunge for each hole along said longitudinally extending edges during said clamping of said fuselage upper and lower lobes; and

fastening said fuselage upper and lower lobes together through the drilled holes along said longitudinally extending edges to form a fuselage section;

wherein said drilling of said coordination holes in said panels, in said stringer clips, in said shear ties, in said frame members, in said cross members of said floor grid, and in said fuselage lower and upper lobe is done using an end effector carried by a precision computer controlled robot that is directed to the drilling locations using a digital data set taken directly from digital engineering part definition records, said drilling locations being determined with respect to reference points on each drilled component, so the spatial relationships between key features of said subassemblies as defined by said coordination holes make said subassemblies self-locating and intrinsically determinate of the final contour and configuration of said fuselage section, independent of tooling.

5,586,392

SWING STROKE GARDENING TOOL


Michael J. Pasquale, 45 Spring St., Middletown, Conn. 06457

Filed May 18, 1995, Ser. No. 444,091

Int. Cl.⁶ B26B 27/00

U.S. Cl. 30—318

13 Claims



1. A gardening tool comprising a handle and a cutting head fixedly secured to the handle, said cutting head comprising a pair of elongated blade members and an adjustable interconnection therebetween for connecting the blade members end to end, said interconnection permitting selective angular positioning of said first and second blade members relative to each other and secured fastening thereof in said selected position, said interconnection comprises a bolt having a locking shank portion and a threaded portion, and a nut threadably mountable on said threaded portion, said locking shank portion being immobilized against rotation relative to one of said blade members, the other of said blade members having an aperture for receiving and cooperating with the shank portion for positioning said other blade member relative to said shank to fix the selected angular positions of said blade members.

5,586,393

HEADLAMP LEVEL INDICATOR

Douglas E. Pherigo, Loves Park, and Leo B. Jansen, Rockford, both of Ill., assignors to Textron Inc., Providence, R.I.


Filed Dec. 20, 1994, Ser. No. 359,399

Int. Cl.⁶ G01C 9/10; B60Q 1/00

U.S. Cl. 33—288

5 Claims

1. A headlamp alignment indicator assembly for indicating and calibrating a vehicle headlamp orientation comprising:
an adjustable, beam-directing structure for a headlamp;
a roller element arranged for rolling movement along a guide structure arranged to guide said rolling movement, said guide




structure being disposed with exclusion of dampening liquid therefrom in order to eliminate handling and disposal hazards of said liquid;
said guide means being coupling said beam-directing structure for movement therewith; and
indicator means for indicating displacement of said roller element resulting from said rolling movement relative to said guide means and further comprising at least one cushioning structure positioned to form an end of said guide track in order to absorb impact of said roller member thereagainst.

5,586,394
SELF-CONTAINED PLUMB BOB AND INK LINE MARKER WITH LINE CAPABLE OF AUTOMATIC BRAKING AND RETRACTION

Mick Courtney, 311 W. Main St., Enterprise, Oreg. 97828
Filed Jun. 2, 1995, Ser. No. 460,535
Int. Cl.⁶ G01C 15/10; B44D 3/38
U.S. Cl. 33—394

4 Claims




1. An assembly for a self contained, combination plumb bob and ink line marker capable of braking and retraction comprising:
a hollow housing, comprising a threadedly and separably engaged cylindrical neck portion, a substantially flat and round disc shaped portion with a tapered point on the circumferential edge, and a connector sleeve joining one open end of the cylindrical neck portion with the circumferential edge of the disc portion opposite the tapered point on the disc shaped portion of the housing giving the assembled invention a pendulum shape;
a line reel mounted inside the disc portion of the housing;

a strong flexible member attached at one end and wound about the line reel, extending through the cylindrical neck portion of the invention housing, to which the disc portion of the housing is attached, and out the open end of the cylindrical neck portion of the housing opposite the disc shaped portion of the housing;
an ink reservoir formed by two apertured partitions in the cylindrical neck portion of the invention housing;
absorbent member inside the ink reservoir for storing and applying ink to the flexible member as it passes over the absorbent member;
an access door in the external surface of the cylindrical portion of the invention housing allowing access to the ink reservoir and absorbent member for replenishing the ink and means for securing the door in a closed position;
a reel stop and means for halting rotation of the line reel and extension or retraction of the attached flexible member;
a hub extending from one side surface of the line reel through an aperture in the disc shaped portion of the apparatus housing for effecting manual rotation of the line reel;
a series of gears or teeth on the side surface of the line reel opposite the external reel hub;
a spring spool associated with the line reel by gears or teeth on one side surface of the spring spool which interlock with the gears or teeth on the side surface of the line reel allowing the line reel and spring spool to rotate together simultaneously and means for turning the spring spool independently of the line reel;
a coiled band spring attached at one end to the spring spool and at the other end to the internal surface of the disc portion of the apparatus and means for adjusting the tension of the spring.

5,586,395
LEVEL ANGLE GAUGE

Jerry P. Malczewski, Evergreen, Colo., assignor to Malczewski Holdings, Inc., Evergreen, Colo.
Filed Sep. 30, 1994, Ser. No. 316,557
Int. Cl.⁶ B43L 7/10

22 Claims



1. A level angle gauge adapted for use to capture an angular measurement of a structural surface relative to an imaginary plane so that the captured angular measurement can be transferred onto a workpiece when said level angle gauge is positioned thereon, said level angle gauge comprising:

(a) an elongated body structure having a pair of oppositely disposed sides extending in a longitudinal direction and a reference surface extending therebetween, said reference surface having a reference surface width that is oriented transversely to said longitudinal direction;
(b) a leveling element connected to said body structure and operative to indicate that said reference surface of said body structure is oriented parallel to the imaginary plane when the angular measurement is being made;
(c) an arm structure having an arm surface and being pivotally connected to said body structure, said arm structure movable

between a first position wherein said arm surface is oriented in a common plane with said reference surface of said body structure and a second position wherein said arm surface is oriented at an angle relative to said reference surface, said arm surface having an arm surface width that is less than said reference surface width; and

(d) an arm lock mechanism operative in an unlocked state to permit said arm structure to pivot between the first position and the second position and in a locked state to releasably retain said arm structure in one of the first position and the second position whereby when in the second position with said reference surface being oriented parallel to the imaginary plane and with said arm surface being disposed in registration with the structural surface, said arm structure and said body structure can be locked together to capture the angular measurement so that the captured angular measurement can be transferred onto the workpiece when said level angle gauge is positioned thereon, said arm lock mechanism being dimensioned to have a length in a direction transverse to said body structure which length is less than the reference surface width.


5,586,396
DRYING APPARATUS HAVING ROTATING VANE ASSEMBLIES AND DRYING METHOD USING THE SAME

Masao Kanai, 18-10 Nagatassannoudai, Minami-ku, Yokohama-shi, Japan

Filed Aug. 8, 1995, Ser. No. 512,375
Claims priority, application Japan, Aug. 10, 1994, 6-209246;
Sep. 1, 1994, 6-232096; Oct. 13, 1994, 6-013805 U
Int. Cl.⁶ F26B 17/30

U.S. Cl. 34—59

9 Claims



1. A drying apparatus comprising:

a cylindrical drying vessel for receiving material to be dried, an inner wall surface of said cylindrical drying vessel defining a heat-transmitting surface,

heat-generating means encircling the cylindrical drying vessel to transmit heat to the heat-transmitting surface of the cylindrical drying vessel, and

at least one rotating vane assembly rotatably fixed in the cylindrical drying vessel,

the rotating vane assembly having a plurality of vane sections, which extend from a common central portion and leave between circumferential edges thereof and the heat-transmitting surface of the cylindrical drying vessel, annular spaces wide enough to allow the material to cross and contact the heat-transmitting surface without falling therein.

each vane section extending obliquely upward in a direction which is opposite to a rotating direction thereof, and the


circumferential edge of each vane section extending less than 360 degrees as viewed from above,

whereby all vane sections when rotating bear material on upper surfaces thereof to raise the material upward and push the material against the heat-transmitting surface under the influence of centrifugal force thus causing the material to continuously climb along the heat-transmitting surface, thereby drying the material.

5,586,397
DRYER SECTIONS OF A PAPER MACHINE
Reima Kerttula, and Jouko Yli-Kauppi, both of Muurame, Finland, assignors to Valmet Corporation, Helsinki, Finland
Filed Apr. 18, 1994, Ser. No. 229,471
Claims priority, application Finland, Nov. 30, 1993, 935340
Int. Cl.⁶ F26B 3/00

U.S. Cl. 34—114

35 Claims



8. Dryer section in a paper machine, comprising a plurality of only normal dryer groups having a single-wire draw, each of said dryer groups comprising contact-drying cylinders arranged in a first row, reversing suction cylinders arranged in a second row spaced from said first row of contact-drying cylinders and a drying wire for supporting a paper web, the paper web being passed in a closed draw between adjacent ones of said dryer groups and running over an outer circumference of said reversing suction cylinders while being subjected to negative pressure, the web running over a sector of at least one of said contact-drying cylinders in one of said dryer groups and having an exposed first face and a second, opposed face of the web in direct contact with an outer surface of said at least one of said contact-drying cylinders in said sector, and

drying means for applying a drying impulse to the exposed first face of the web as the web runs over said sector of said at least one contact-drying cylinder such that the drying profile of the web in the direction of thickness of the web is equalized and the drying capacity of the dryer section is increased.

5,586,398
ARTICLE OF FOOTWEAR FOR MORE EFFICIENT RUNNING
J. Martin Carlson, 6005 Kellogg Ave., Edina, Minn. 55424-1830
Continuation of Ser. No. 183,360, Jan. 19, 1994, abandoned.
This application Oct. 13, 1995, Ser. No. 542,682
Int. Cl.⁶ A43B 5/00


U.S. Cl. 36—114

10 Claims

1. An article of footwear having an anterior end portion and a postero-lateral portion comprising:


a sole structure having a postero-lateral initial contact portion and an medial/forefoot portion;

the initial contact portion having a substantially planar lower surface joining the medial/forefoot portion along a junction line, and the initial contact portion having a thickness tapering from the junction line to a postero-lateral edge of the sole



structure to provide a minimum thickness of material interposed between a foot of the wearer and the ground engaging surface; and
an insole having an insole initial contact portion and an insole medial/forefoot portion, the insole initial contact portion overlying the initial contact portion of the sole structure and being formed of material having a surface of a selected coefficient of friction for controlling slippage, and the insole medial/forefoot portion having a higher coefficient of friction which is higher than the selected coefficient of friction in the initial contact portion of the insole, to permit initial sliding between the foot and the insole in the insole initial contact portion on impact of the foot with the support surface, and the insole medial/forefoot portion reducing sliding of the forefoot relative to the insole.

5,586,399
VERTICAL TRENCHER APPARATUS EMPLOYING CUTTER HAVING HELICAL CHANNEL OF VARYING RISE ANGLE
Simeon Staroselsky, Tel Aviv, Israel, assignor to V.T.S. Trencher Systems Ltd., Yavne, Israel
Filed Aug. 22, 1995, Ser. No. 517,697
Int. Cl.⁶ E02F 3/06
U.S. Cl. 37—351



1. A vertical trencher apparatus attachable to a moving platform carrying a power source for excavating rock and soil to form a trench, the apparatus comprising:

- a cutter body having:
 - a substantially cylindrical surface having a lower end, an upper end and defined as having a longitudinal central axis;
 - a ridge attached to, and extending outwardly from, said surface in a helical configuration extending continuously along said surface to said lower end, said ridge having an upper surface and an outer edge, said ridge being formed such that a rise angle at a point of said ridge proximal to said lower end of said surface is less than a rise angle at a point of said ridge proximal to said upper end of said surface, wherein said rise angle is defined at each point of said ridge as the angle between a virtual plane parallel to said upper surface at that point and a virtual plane perpendicular to said longitudinal axis; and
 - a plurality of cutting elements deployed in fixed relation to said outer edge such that said cutting elements lie substantially on a virtual cylinder;


- a housing operatively engaged with said cutter body at said upper end so as to maintain said cutter body with said longitudinal central axis substantially vertical and to allow rotation of said cutter body about said longitudinal central axis, said housing having a lateral aperture;
- a power transmission associated with said cutter body at said upper end for employing power from the power source to generate rotation of said cutter body about said longitudinal central axis; and
- a back cover mounted in fixed relation to said housing so as to present an inner surface extending substantially along and partially circumscribing said cutter body.

5,586,400
FABRIC HOLDER WITH COMPLIMENTARY CLAMPING SURFACES AND METHOD
E. Frank Moore, III, 4447 Old Randleman Rd., Greensboro, N.C. 27406
Continuation of Ser. No. 254,071, Jun. 3, 1994, abandoned.
This application Jul. 7, 1995, Ser. No. 499,231
Int. Cl.⁶ D06C 3/08; D05B 39/00
U.S. Cl. 38—102.2



1. A means for securing a flexible planar member in a taut manner for subsequent sewing operations on a sewing machine comprising: a base and a clamp, said base comprising a vertical male mating projection, said vertical projection having a single convex section and a single concave section on opposite sides of said vertical projection, said clamp having an outer surface, said clamp outer surface defining a complementary female mating receptacle, said complementary female mating receptacle for rotatably tightening around said convex section and said concave section wherein said complementary female mating receptacle fully encloses said male mating projection to sandwich said flexible planar member therebetween.


5,586,401
ART WORK DISPLAY APPARATUS
Gary T. Sheehan, 7 Frazer Ave., Malvern, Pa. 19355, and Paul G. Landry, 9 N. Cedar Hollow Rd., Paoli, Pa. 19301
Filed Oct. 31, 1994, Ser. No. 331,806
Int. Cl.⁶ G09F 1/12
U.S. Cl. 40—737



1. Apparatus for displaying an article, said apparatus comprising:
a front cover plate of transparent material;

a rear cover plate of at least the same size as the front cover plate; upper fastening means for fastening said front cover plate to said rear cover plate, said upper fastening means comprising at least two fasteners spaced apart on a horizontal line, said fasteners having inner surfaces facing the central portion of said cover plates along said horizontal line;
lower fastening means for fastening said front cover plate to said rear cover plate, said lower fastening means comprising at least two fasteners, said lower fasteners having an upper surface facing the top edges of said cover plates, and spaced apart on a horizontal line a distance less than the horizontal distance between said upper fasteners and being positioned to provide vertical support for the article between the front and rear cover plates, the length of said upper and lower fastening means being adjustable according to the thickness of the article; and
support means attached to the rear surface of the rear cover plate by said upper fasteners.

5,586,402
FISHING ROD BITE INDICATOR
S. Shannon Brent, and Craig W. Forbes, both of 1050 Sunnyview Rd. NE., Salem, Oreg. 97303
Filed Feb. 27, 1995, Ser. No. 395,490
Int. Cl.⁶ A01K 97/12
U.S. Cl. 43—17




1. A fish bite indicator for use on a fishing rod comprising the combination of:

- a clamping member comprised of two rigid, parallel arms containing generally hook-shaped openings at the opposite end of an integral perpendicular member having a generally centered threaded hole with a set screw thereby providing the means of attachment of the visual indicator assembly to the fishing rod;
- a rigid, channel-shaped member having aligning flanges on the upper and lower edges of the parallel arms which loosely fits inside the parallel arms of the clamping member;
- a rigid, tubular member positioned snugly inside the parallel arms of the channel-shaped member;
- a rigid, elongated tubular member of approximately twice the length and possessing an exterior dimension slightly less than the interior dimension of the tubular member into which it is inserted; having at its lowermost end a spiral line guide providing the means to encompass fishing line and at its uppermost end a perpendicular projection forming a cap of a size wherein its outermost dimension is slightly larger than the interior dimension of the tubular member providing the means to limit the travel of the elongated tubular assembly within the tubular member and forming, as an assembly, a line-tension-responsive indicating means being operable to produce a visual indication when the action of a fish produces enough line tension to raise the elongated member assembly

inside the tubular member when said member is attached in a perpendicular, vertical position on the fishing rod.

5,586,403
ILLUMINATED FISHING ROD
Maurice Ward, RR #6, Orillia, Ontario, Canada
Filed Nov. 3, 1995, Ser. No. 552,717
Int. Cl.⁶ A01K 75/02
U.S. Cl. 43—17.5

3 Claims




2. An illuminated fishing rod comprising:
an elongated fishing rod having a plurality of eyelets arranged in a linear relationship along a length thereof, the open lower end of the elongated fishing rod having a pair of copper contacts therein, the fishing rod having copper wire extending from the copper contacts at the open lower end thereof to the upper end portion for electrical coupling with the light portion, the copper wire being wrapped around the fishing pole;
a flashlight portion received within an open lower end of the elongated fishing rod, the flashlight portion comprises of a lower housing having an upper and portion and an open lower end, the upper end portion having a pair of copper contacts therein, the upper end portion dimensioned to be received within the open lower end of the elongated fishing rod with copper contacts thereof in cooperation with contacts within the fishing rod, the lower housing having a pair of batteries therein, the open lower end having a lamp portion removably coupled thereto to facilitate the removal of batteries, the lamp portion contacting a lowermost of the pair of batteries for activation thereof, the lower housing having an on/off switch electrically coupled with the pair of batteries for activation or deactivation of the lamp portion, the on/off switch having copper wiring extending therefrom to couple with the pair of copper contacts of the upper end portion; and
a light portion electrically coupled to an upper end portion of the elongated fishing rod.

5,586,404
FISHPOLE STORAGE SYSTEM
Michael J. Freitas, 1921 Bowers Ave., Santa Clara, Calif. 95051
Filed Mar. 20, 1995, Ser. No. 406,678
Int. Cl.⁶ A01K 97/06; 97/10
U.S. Cl. 43—21.2

7 Claims

1. A device for storing and carrying a fish pole wherein said fish pole has two sections that are detachably joinable end to end, said device comprising:




an elongated central member having a substantially rectangular cross section;
a pair of elongated tongues, one of said tongues on one side of said central member opposite another side of said central member having the other of said tongues;
a pair of pole catches, each pole catch being elongated with an elongated groove on one side dimensioned to mate with one of said tongues and an elongated groove on another side adapted to detachably engage a fish pole section; and
means for detachably attaching said central member to a wall.

5,586,405 FISHING LURE

Jody R. Flke, 831 Jackson Ave., Monaca, Pa. 15061
Continuation-in-part of Ser. No. 221,800, Apr. 1, 1994, abandoned. This application Dec. 21, 1994, Ser. No. 360,617
Int. Cl.⁶ A01K 85/00

U.S. Cl. 43—42.31

3 Claims



1. A fishing lure for use in top water surface fishing, comprising:
a head having means for securing a swivel device thereto;
a tail end;


a rigid buoyant body extending along an axis joining said head and said tail end, said body having a cross section including a concave recess, said body twisting around said axis such that said concave recess forms a longitudinal spiral for allowing said lure to rotate when pulled along the water surface, said body tapering from said head to said tail end, said body including two perpendicular rattle chambers, each rattle chamber having a loose object therein; and
securing means disposed along said body for attaching hooks to said body.

5,586,406 LIVE BAIT CONTAINER

Yong F. Lin, No. 827, Twu Chen Rd., and Yong C. Lin, No. 853, Twu Chen Rd., both of Tali City, Taichung Hsien, Taiwan
Filed Nov. 28, 1995, Ser. No. 563,339
Int. Cl.⁶ A01K 97/04

U.S. Cl. 43—55

5 Claims



1. A live bait container comprising:
a container body for keeping live baits, the container body comprising an outer thread around the periphery at one end, a downward bottom flange around the periphery at an opposite end, and an inner thread around said downward bottom flange;
a cover covered on said container body to close said bait chamber, said cover comprising an inner thread threaded onto the outer thread of said container body, a bait outlet and a bait inlet spaced on the periphery, a bait passage way connected between said bait outlet and said bait inlet at an outer side, a plurality of raised portions raised from the inside opposite to said bait passage way, and a spiral track spirally extending downwards from said bait outlet for guiding live baits from said bait chamber to said bait passage way;
a locating board mounted on said cover, said locating board comprising a peripheral flange covered over said bait passage way, and a plurality of holes through said peripheral flange; and
a rotary cap covered on said locating board, having an inside recess forced into engagement with one raised portion of said cover, and a through hole through the periphery, said rotary cap being turned relative to said locating board between the operative position in which the through hole of said rotary cap is disposed in alignment with one through hole on said locating board for permitting a fishhook to be inserted into said bait passage way to pick up live baits from said bait passage way, and the non-operative position in which the through hole of said rotary cap is closed by the periphery of said locating board to prevent escape of live baits.


5,586,407 SWATTER AND METHOD OF USING THE SAME

Anthony E. Raymond, 5342 W. Bar S St., Tucson, Ariz. 85713
Filed May 8, 1995, Ser. No. 436,734
Int. Cl.⁶ A01M 3/02

U.S. Cl. 43—137

8 Claims

1. A swatter, comprising a support having a cross section, a pair of opposed substantially flat major surfaces, and perforations arranged in plurality of rows and columns; a first set of impaling elements on said support for impaling insects, said impaling elements of said first set being substantially uniformly distributed throughout said cross section, and neighboring impaling elements of said first set being spaced from one another by distances sufficiently large to prevent substantial squashing of an insect were




the insect to be impaled by more than one impaling element of said first set; a second set of impaling elements on said support for impaling insects, said impaling elements of said second set being shorter than said impaling elements of said first set and being substantially uniformly distributed throughout said cross section, and neighboring impaling elements of said second set being spaced from one another by distances sufficiently large to prevent substantial squashing of an insect were the insect to be impaled by more than one impaling element of said second set; and a handle extending from said support.

5,586,408 SURFACE FOR SPORTS AND OTHER USES

Jerry G. Bergevin, Lynnwood, Wash., assignor to Turf Systems International, Inc., Lynnwood, Wash.
Continuation of Ser. No. 78,624, Jun. 17, 1993, abandoned, which is a continuation-in-part of Ser. No. 902,147, Jun. 22, 1992, abandoned. This application Nov. 4, 1994, Ser. No. 334,414
Int. Cl.⁶ A01G 1/00; A01H 5/00

U.S. Cl. 47—1.01

18 Claims



1. A grass playing surface comprising:

(a) a foundation;
(b) an artificial grass turf located on top of the foundation, the artificial grass turf having generally vertically upright fibers mounted in a porous backing material;
(c) a layer of growth medium disposed in the artificial grass turf to a depth sufficient to substantially fill the artificial grass turf to the top of the fibers, the top of the fibers terminating at approximately the top of the layer of growth medium; and
(d) natural grass plants having grass blades, crowns and roots, the grass plants disposed in the growth medium, the roots extending downwardly through the growth medium, the artificial grass turf, and into the foundation, the crowns being located slightly below the top of the artificial fibers and the


grass blades extending upwardly above the top of the fibers forming a playing surface of substantially natural grass.
17. A method for forming a durable, natural grass playing surface, comprising the steps of:
(a) providing a panel of artificial turf having generally vertically upright fibers attached to a porous backing material;
(b) placing a layer of growth medium throughout the fibers to a depth sufficient to fill the artificial turf to approximately a top of the fibers;
(c) stabilizing the layer of growth medium with a binding material;
(d) strewing a layer of grass seed over the top of the layer of growth medium;
(e) dispersing a shallow layer of growth medium over the top of the layer of grass seed to fill the artificial turf to at least the top of the fibers;
(f) stabilizing the shallow layer of growth medium with a binding agent; and
(g) placing a plurality of panels formed in accordance with steps (a)–(f) adjacent one another on a foundation and watering the panels to produce a natural grass playing surface.

5,586,409 SAFETY VASES FOR UMBRELLA TABLES

Bruce W. Jamieson, 1361 Divine La., Tracy, Calif. 95376
Filed Nov. 14, 1994, Ser. No. 339,020
Int. Cl.⁶ A01G 5/00; A47G 7/00

U.S. Cl. 47—41.01

5 Claims



1. A safety vase for use in combination with an umbrella table the top of which is provided with an aperture for receiving an umbrella pole, comprising:

a water-tight receptacle portion having an outer wall which is symmetrical about a longitudinal axis, has an open end and a closed end, the maximum dimension of said receptacle portion transverse to said axis being less than the diameter of said aperture in said table top; and
a flange means extending outwardly from said outer wall of said receptacle portion, the diameter of the smallest cylinder coaxial with said longitudinal axis which is capable of containing the entirety of said flange means being greater than the diameter of said aperture in said table top, whereby a part of said receptacle portion adjacent said flange means is maintained in said aperture in said table top when at least a part of the lower face of said flange means bears against the upper face of said table top.

5,586,410


FRESH FLOWER HOLDER

Joseph S. Gallo, 58 Peach St., Walpole, Mass. 02081

Filed Jan. 4, 1996, Ser. No. 583,216

Int. Cl.⁶ A01G 5/00

U.S. Cl. 47—55



1. A holder for at least one element of living corsage material from which substantially the entire stem has been severed, the holder comprising:
 - a covered wire;
 - a plug of absorbent material surrounding an intermediate portion of the covered wire to form a moisture reservoir, the plug having upper and lower surfaces through which the covered wire passes and sides extending from the upper to the lower surfaces; and
 - a water-repellent covering surrounding the sides and lower surface of the plug and extending down the wire, and leaving the upper surface of the plug uncovered;
- the plug of absorbent material comprising random fibers of synthetic material organized generally uniformly in density throughout the plug and extending predominantly parallel to the covered wire, the fibers being capable of spreading generally radially outwardly to permit insertion of the severed end of the living material into the plug and being capable of providing a radially-inward restoring tendency to keep the material from breaking its moisture-supplying contact with the plug;
- the wire having a laterally-extending formation at the intermediate portion, the formation extending laterally from the wire into the fibers of the plug to secure the plug to the wire.

5,586,411

METHOD OF PREPARING A SEED TREATMENT COMPOSITION

Sanford C. Gleddie; Mary E. Leggett, both of Saskatoon; Wendell A. Rice, and Perry E. Olsen, both of Beaverlodge, all of Canada, assignors to Her Majesty the Queen in Right of Canada, and Philom Bios Inc., both of Saskatchewan, Canada

Division of Ser. No. 174,335, Dec. 29, 1993, Pat. No. 5,484,464. This application May 30, 1995, Ser. No. 453,257

Int. Cl.⁶ A01C 1/06; C12R 1/80; 1/41

U.S. Cl. 47—57.6

4 Claims

1. A method of preparing a composition for co-inoculating legume seeds, comprising packaging a carrier substrate in a container, sterilizing the substrate, adding a suspension of spores of *P. bilaii*, adding a suspension of *Rhizobium* sp. cells, and mixing said suspensions with said carrier to form a composition.

5,586,412

METHOD FOR RECOVERY OF COTTON SEED FROM LINT


James B. Wadlington, Greenville, Miss., assignor to Delta and Pine Land Company, Scott, Miss.

Continuation of Ser. No. 309,487, Sep. 22, 1994. This application Jun. 6, 1995, Ser. No. 470,134

Int. Cl.⁶ A01C 1/00

U.S. Cl. 47—58

8 Claims



1. A batch method for removing lint from fuzzy cotton seed which is to be used for planting purposes comprising:
 - selecting a batch quantity of fuzzy cotton seed which is to be delinted;
 - forming a first feed stream of a dilute acid solution;
 - forming a second feed stream of fuzzy cotton seed from said batch quantity from which lint is to be removed;
 - merging the flows of said first and second feed streams at an inlet end of an extended flow path to form a composite stream at said inlet end containing said dilute acid first feed stream and said fuzzy cotton seed second feed stream;
 - gently mixing said composite stream from said inlet end along said extended flow path to gradually blend said first and second flow streams together and thereby gradually saturate the lint on said fuzzy cotton seed with said dilute acid solution along the length of said extended flow path from said inlet end thereof to an exit end thereof;
 - discharging the mixed composite stream of dilute acid solution saturated fuzzy cotton seed at said exit end of said extended flow path in said selected batch quantity into a reaction chamber having a rotatable drum mounted therein;
 - circulating heated air through said rotatable drum from an inlet opening through a discharge opening while continuously rotating said drum with said batch quantity of cotton seed therein;
 - controlling the temperature of said heated air such that the temperature of the heated air at said discharge opening is below the level at which heat damage to the suitability of the seed for planting could occur;
 - evaporating the water in the dilute acid solution absorbed in the lint on said fuzzy seed by circulating said heated air in said reaction chamber to concentrate the acid and thereby cause hydrolyzation of the lint on said fuzzy seed;
 - entraining the hydrolyzed lint in the circulating heated air to remove said hydrolyzed lint from said reaction chamber through said discharge opening; and
 - separately removing the batch quantity of delinted seed from said reaction chamber after said batch quantity has been delinted.

5,586,413

SELF ON CENTER LEVELING POT HANGER

Arie N. Sharon, 1322 N. Park Dr., Richardson, Tex. 75081

Filed Oct. 2, 1992, Ser. No. 955,414

Int. Cl.⁶ A01G 9/02; A47G 7/02

U.S. Cl. 47—67

3 Claims



1. A plant pot mount comprising: a one piece wire metal member including, a circular portion sized to mount a predetermined range of plant pot sizes and to clear plants in said pots; a lateral extension outwardly from said circular portion; a vertically extended section substantially at right angles to the plane of said circular portion and extending from the outermost portion of said lateral extension so as to be laterally displaced from said circular portion sufficiently to clear a pot mounted in said circular portion and generally to clear plant foliage extending upward from said pot; an inwardly and upwardly directed slanted section connected to the top of said vertically extended section and extended inwardly to a top vertically extended mount section generally parallel and adjacent to a center line projected of the center of said circular portion; and a bent over suspension hook extended from the top of said mount section spanning the center line projection of the center of said circular portion.

5,586,414

SYSTEM FOR RESURFACING A ROOF WITH A CANTILEVER EDGE


Charles Tawzer, Portland, Oreg., assignor to A-1 All Weather Roofing, Inc., Hillsboro, Oreg.

Division of Ser. No. 985,024, Dec. 3, 1992, abandoned. This application Feb. 3, 1994, Ser. No. 191,445

Int. Cl.⁶ E04D 13/15

U.S. Cl. 52—57

1 Claim



1. A method of resurfacing a roof having existing roof material overlying a roof base without first removing the existing roof material from the roof base, comprising:

- (a) providing an edge strip having a cover portion, with an outer surface that is heat sealable to polymeric film, which overlies a portion of the existing roof material, an escutcheon portion that depends from the cover portion and a terminal portion that depends from the escutcheon portion and overlies the end of the roof base;
- (b) placing said edge strip along an edge of a roof that is covered with existing asphalt singles having a cantilever portion that extends outwardly past the edge of the roof base, with said escutcheon portion wrapping around the cantilever portion so that the cantilever portion does not have to be removed before installing said edge piece;
- (c) fastening said edge piece to the roof base along the cover portion and the terminal portion;
- (d) thereafter installing polymeric sheet roofing material over the existing shingles with a bottom edge of said material overlying the cover portion of the edge strip; and
- (e) heat sealing the bottom edge of the polymeric material to the cover portion.

5,586,415

FLASHING DEVICE FOR USE WITH EXTERIOR SIDING


Fred M. Fisher, 2450 Bass Bay Dr., and Jack R. Powis, 8085 Briarcreek St., both of Tallahassee, Fla. 32312

Filed Jun. 3, 1994, Ser. No. 253,916

Int. Cl.⁶ E04D 1/36

U.S. Cl. 52—58

7 Claims



1. A preformed, ready made corner flashing means for creating a moisture-impervious water-directing barrier at either a right or a left corner of a frame of a door or a window located on an exterior wall of a building in cooperation with an exterior wall siding material consisting of a plurality of individual longitudinal panels having a horizontal orientation, wherein a top of each panel includes locking means configured to engage a correspondingly configured engagement means on a bottom of an adjacent overlapping panel for securing the siding panels together, said flashing means comprises a substantially rectangular flat planar structure formed of a flexible, waterproof sheet material selected from the group consisting of foam, vinyl, plastic and coated paper, said flashing means having one corner removed to form a right angle notch configured to fit securely and tightly against any corner of the frame with and under the siding panels so that a minor portion of a wall engaging bottom surface of the flashing means directly contacts and is adhesively secured to the wall adjacent to the frame and a major portion of the wall engaging surface of the flashing means is held away from contact with the wall and in contact with the locking means of one siding panel in an orientation that causes water to be directed along a top water diverting surface of the flashing means and through drain holes in the engagement means of an adjacent siding panel.

5,586,416

CONCRETE FORM WITH INTEGRAL DRAIN


John Hess, III, 1813 S. 11th, and Harold Hess, 17 Lakewood Dr., both of Belleville, Ill. 62223

Filed Mar. 22, 1995, Ser. No. 408,535

Int. Cl.⁶ E02D 19/00

U.S. Cl. 52—169.5

25 Claims



1. In a concrete form for retaining concrete poured about one side of the form and having at least one tube and a support that supports the tube in spaced-apart relation to an excavation bottom, an improvement comprising gravel between at least a portion of said tube and the excavation bottom such that the tube and the gravel are positioned to engage liquid concrete poured about one side of the form.

5,586,417

TENSIONLESS PIER FOUNDATION


Allan P. Henderson, 5919 Mohawk Dr., Bakersfield, Calif. 93308, and Miller B. Patrick, 5808 Baywood, Bakersfield, Calif. 93309

Filed Nov. 23, 1994, Ser. No. 346,935

Int. Cl.⁶ E02D 5/38; 27/32

U.S. Cl. 52—295

13 Claims



1. A pier foundation subject to high upset forces which comprises a hollow, upright cylindrical structure of heavy post-compressed cementitious material under high compressive loading from the upper end thereof downwardly to a level adjacent the lower end thereof and having open top and bottom ends, a plurality of metal rods and shield means surrounding said rods spaced about said cylindrical structure and extending generally vertically in said cementitious material from said level to said upper end, and tension adjusting structure operatively connected between said rods and said cylindrical structure for tensioning of said rods, said shield means shielding said rods from said cementitious material and permitting said rods to elongate relative to said cementitious material during tensioning, said rods each being heavily tensioned between said level and said upper end to post-compress said cementitious material, and said shield means continuously shield-

ing said rods from said cementitious material to permit said rods to be retentioned as necessary.

5,586,418

COMPOSITE CONSTRUCTION OF REINFORCED CONCRETE

Casper Ålander, and Tarmo Mononen, both of Espoo, Finland, assignors to Rautaruukki Oy, Hämeenlinna, Finland

PCT No. PCT/FI93/00276, § 371 Date Jan. 30, 1995, § 102(e)

Date Jan. 30, 1995, PCT Pub. No. WO94/01636, PCT Pub.

Date Jan. 20, 1994


PCT Filed Jun. 30, 1993, Ser. No. 362,423

Claims priority, application Finland, Jul. 1, 1992, 923052

Int. Cl.⁶ E04F 13/12

U.S. Cl. 52—450

11 Claims



1. A composite construction which has a beam part (1) and a slab part (2) bearing thereon, the construction comprising a combination of at least the following components:

- a) a metal mantle (3) of the beam part, the mantle being at the same time the casting form and being made up of an upwardly open profile which has longitudinal surfaces (5) formed by its bended edges and a portion between them;
- b) additional reinforcement components (7) which, together with the metal mantle, make up the reinforcement of the composite construction; and
- c) a cast component (8), such as concrete, which, when set and together with the metal mantle and with the additional reinforcement components left inside the casting, makes up the composite construction, characterized in that
- d) the metal mantle (3) of the beam part (1) is a shaped profile, wherein one surface (10) of the mantle wall is embossed, and the thickness of this mantle wall (9) is such that said embossing will not substantially affect the surface structure of the opposite surface (11) of the wall sheet.
- e) the cross-sectional shape of the beam part wall form (3) in the portion between its longitudinal surfaces (5) is defined by sheet portions (12) interconnected by outwardly or inwardly oriented edges (13), corrugations (22) or welded joints (23), or by curved sheet portions (24, 25); and that
- f) the edges of said longitudinal surfaces (5) are oriented towards each other in order to prevent these portions (12, 24, 25) from buckling and becoming detached from the concrete.

5,586,419

Patent Not Issued For This Number

5,586,420

METHOD AND APPARATUS FOR FILLING STRUCTURAL HOLES


Olan D. Harris, 7404 Zoar, Lubbock, Tex. 79424

Filed Dec. 7, 1993, Ser. No. 128,479

Int. Cl.⁶ F04G 23/02

U.S. Cl. 52—514.5

12 Claims



1. A structural hole filling apparatus comprising:
 - a structural hole filler having a filler receiving means for receiving and holding a structural filler material;
 - a template having a template bore engagable with said filler receiving means;
 - said bore for passing structural filler material from within said receiving means into a structural hole located exterior to said receiving means;
 - said template bore having a lip surface that defines a rim that protrudes below a lower surface of said filler receiving means;
 - said filler receiving means comprising a filler receiving tray having at least one bore therethrough and a plurality of edges designed to hold the structural filler material therein;
 - said receiving tray having an upper surface and a lower surface;
 - said receiving tray upper surface designed to removably engage said template lower surface; and
 - said rim of said template being adapted to be insertable through said bore of said filler receiving tray;
 - said receiving tray lower surface being designed to mate with structural surfaces to be filled.

5,586,421

HAYMAKING MACHINE

Jerome Aron, Dossenheim Sur Zinsel, France, assignor to Kuhn S.A., Saverne Cedex, France

Filed Jul. 13, 1995, Ser. No. 501,808


Claims priority, application France, Jul. 13, 1994, 94 08882

Int. Cl.⁶ A01D 78/12

U.S. Cl. 56—367

16 Claims

1. A haymaking machine comprising:
 - a wheeled supporting structure which can be attached to a tractor;
 - a swathing rotor supported by said supporting structure and comprising:
 - a) a ring supported by roller wheels for rotation about an approximately vertical geometric axis,
 - b) a plurality of arms mounted to said ring for rotation about longitudinal axes of said arms,
 - c) a plurality of working forks mounted to said arms, and
 - d) a plurality of actuating devices located in proximity to said ring connected to said arms so as to rotate said arms; and
 - a driven control member supported by said supporting structure and located at least in part near said ring, said control member cooperating with said actuating devices for rotating said arms.



5,586,422

LOG ILLUSION VINYL LOG SIDING


Terrell W. Hoffner, 3128 Indian Rd., Davenport, Iowa 52802

Filed Jun. 16, 1995, Ser. No. 491,391

Int. Cl.⁶ E04B 1/10

U.S. Cl. 52—529


6 Claims



1. Siding apparatus in combination with a building having a planer outer surface thereon, said siding comprising:
 - a first elongated siding member having an upper edge and a lower edge, first end and a second end;
 - means for attaching said first siding member to said surface;
 - a second elongated siding member having an upper edge, a lower edge, a first end and a second end;
 - means for attaching the upper edge of the first elongated siding member to the lower edge of the second siding member and to said building surface whereby said first and second elongated siding members will cover a portion of said surface;
 - wherein said first and second siding member are C-shaped in cross-section to resemble logs; and
 - wherein said means for attaching the upper edge of said first elongated siding member to the lower edge of said second siding member included a strap attached to said surface, said strap having an opening therein through which extends a fastener, said fastener having a first end adjacent to the surface, said first end being larger than the opening; a second end of said fastener being larger than holes in said siding members, said second fastener end being deformable to extend through said holes in the siding and resilient enough to

spring back to its original larger shape once through the holes in said siding to thereby hold the siding to said surface.

5,586,423
BUILDING HANDRAIL BRACKET
George P. Mullen, 2956 Rogue River Hwy., Grants Pass, Oreg. 97527
Filed Aug. 2, 1995, Ser. No. 510,163
Int. Cl.⁶ E04H 12/10
U.S. Cl. 52—653.2
6 Claims




1. In combination with a building construction including a threaded socket member opening horizontally outwardly therefrom, an L-shaped bracket incorporating (1) a tubular lower horizontal leg defining first and second end portions and a longitudinal passage extending therethrough opening outwardly through said end portions and (2) an upstanding leg rigidly supported from and projecting upwardly from said second end portion, said upstanding leg defining a support structure operative to releasably support the lower end of an upstanding railing post therefrom in predetermined height adjusted position relative to said bracket, and threaded fastener structure extending through said passage and removably threaded into said threaded socket member, said second end portion including an end face opposing and tightly seated against said socket member, said socket member being fixedly anchored in said building construction independent of said threaded fastener.

5,586,424
APPARATUS FOR MOVEMENT OF U-SHAPED CLIPS ALONG A RAIL
Kuo-Raid G. Chen, Cary; Raymond H. Misner, Raleigh; Elbert P. Windham, Fuquay-Varina, and Bernard D. Richardson, Apex, all of N.C., assignors to Delaware Capital Formation, Inc., Wilmington, Del.
Continuation of Ser. No. 188,020, Jan. 28, 1994, abandoned, which is a continuation of Ser. No. 883,648, May 15, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 480,524
Int. Cl.⁶ B65B 51/04
U.S. Cl. 53—138.2
2 Claims

1. In apparatus for attaching a U-shaped metal clip of the type having a pair of spaced parallel legs connected at respective ends by a crown about gathered material, said apparatus including a housing having at least one clip channel for receipt of at least one U-shaped clip, at least one punch for driving a clip present in the channel about gathered material, a window for feeding at least one clip into said one channel into the pathway of said punch, at least one guide rail for supporting a plurality of aligned clips for feeding one at a time through said window into said channel in the pathway of said punch, said guide rail having an inside surface opposite side surfaces and an outside surface, the improvement comprising:

clip feed means for advancing the clips on said guide rail and into said window, said clip feed means comprising, in combination:



- a U-shaped arm which is supported in opposed relation to and over a series of stacked clips on the guide rail, said clips each having the clip legs extending on the opposite side surfaces of the rail and said clips further each having the crown connecting said clip legs on the inside surface, said clips aligned side by side and stacked and connected to one another along the crowns, said arm including parallel first and second runs extending on the opposite sides of the rail in opposed relation to said first and second clip legs respectively, said arm further including an arm connection section connecting said first and second runs, said arm section being positioned on the outside of the guide rail;
 - first and second jaw members pivotally mounted on said first and second runs of the arm respectively, each one of the jaw members extending over a clip leg and positioned for pivotal movement about a pivot axis to and from positions in which an end of each jaw member is pressed against the side of and thereby engaged against a leg of the stacked, connected clips on each side of the rail respectively;
 - biasing means for biasing each jaw member about its pivot axis into said position of engagement with a clip leg;
 - a support rod connected to the arm at the arm connection section for driving the legs generally parallel in the direction of the guide rail;
 - means for driving the rod in a first direction with each of the jaw members engaged with a clip leg of the same clip to thereby advance the clips on the guide rail into the window, said means for driving operable in the opposite direction for positioning of the arm and jaw members by sliding the jaw members over clip legs to thereby position the jaw members for driving of additional clips, each of said jaw members including at least one clip engaging tooth shaped for maintaining both of the jaw members in driving contact with the same clip legs in the first direction and for release of driving contact of the clips legs when moved in the opposite direction, said tooth including a first surface generally at a right angle to the rail and a second surface at an acute angle with respect to the rail to form a tooth pointed in the direction of clip travel; and
 - a clip retention rail spaced from and generally parallel to the guide rail along the length of the inside surface, said clip retention rail positioned with the crowns of the clips between the guide rail and retention rail whereby the crowns are positioned slidably between the guide rail and retention rail;
- said clip feed means defining means for feeding of stacked, connected clips by pressure against and engagement of the clip engaging teeth against the sides of the clip legs of one of the stacked, connected clips located adjacent the clip feed means with the clips retained on the guide rail by the retention rail;


rail as the jaws drive the clips when the arm moves in the first direction, but not the opposite direction.

5,586,425
ARTICLE PACKAGING SYSTEM AND METHOD
Frank Craig, Valley Park, Mo.; Joseph G. Straeter, and Donald E. Weder, both of Highland, Ill., assignors to Southpac Trust International, Inc., Oklahoma City, Okla.
Continuation of Ser. No. 954,635, Sep. 30, 1992, abandoned. This application Apr. 5, 1995, Ser. No. 417,477
Int. Cl.⁶ B65B 5/04
U.S. Cl. 53—449
61 Claims



- A method of packaging a potted plant comprising the steps of: providing a sleeving station having automatic sleeving means for automatically applying a preformed sleeve; automatically opening the preformed sleeve and automatically disposing a decorative cover into the opened preformed sleeve; providing a plurality of potted plants, each having an exterior surface; sequentially conveying each potted plant to the sleeving station via conveying means having a distal end near the sleeving station; sequentially delivering each potted plant to guiding means arranged at the distal end of the conveying means through which guiding means each potted plant is automatically passed downwardly and thereby automatically oriented and maintained in an upright orientation for placement into an opened sleeve and placing each such uprightly oriented potted plant into the opened sleeve and into the cover therein forming a sleeved covered potted plant; and automatically removing each sleeved covered potted plant from the sleeving station.

5,586,426
SEMI-AUTOMATED HARVESTER
James P. Warkentine, 832 Atlanta Hwy., Cumming, Ga. 30130
Continuation-in-part of Ser. No. 325,895, Oct. 18, 1994, abandoned. This application Mar. 10, 1995, Ser. No. 402,009
Int. Cl.⁶ A01D 51/00; 46/00
U.S. Cl. 56—327.1
9 Claims




- A method for harvesting fruits and vegetables comprising the following steps:

(a) mounting the base end of a boom to a collection vehicle;

- deploying the free end of the boom directly toward, away from, or around the collection vehicle in a field of fruits or vegetables to be harvested;
- providing a conveying device connected to the boom;
- collecting at least one fruit or vegetable with the conveying device;
- propelling the conveying device along the boom to a collection point on the collection vehicle where the fruit or vegetable is released; and
- returning the conveying device to the free end of the boom for collecting another fruit or vegetable.

5,586,427
DEVICE FOR ADJUSTING THE CONTACT PRESSURE OF A PRESSURE ROLLER AGAINST THE DRAW-OFF SHAFT OF A ROTOR SPINNING MACHINE
Romeo Pohn, and Edmund Schuller, both of Ingolstadt, Germany, assignors to Rieter Ingolstadt Spinnereimaschinenbau AG, Ingolstadt, Germany
Filed May 25, 1995, Ser. No. 450,387
Claims priority, application Germany, Sep. 3, 1994, 44 31 537.6
Int. Cl.⁶ D01H 7/46; 7/92
U.S. Cl. 57—264
12 Claims




- A yarn draw off device for use with a spinning machine, said device comprising: a pressure roller; a rotatably driven draw-off shaft, said pressure roller in contact with said draw-off shaft and rotatably driven thereby whereby a yarn continuously produced in the spinning machine is draw off between said pressure roller and said draw-off shaft in a continuous yarn producing configuration of said spinning machine; and an adjustable mounting device for said pressure roller, said pressure roller rotatably mounted on said mounting device, said mounting device selectively movable relative to said draw-off shaft in said continuous yarn producing configuration, thereby providing selectable varied contact pressures between said pressure roller and said draw-off shaft in said continuous yarn producing configuration.

5,586,428 ROVING BOBBIN CHANGING METHOD AND APPARATUS FOR SPINNING MACHINE

Isao Asai, and Toshinori Hasegawa, both of Kariya, Japan, assignors to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho, Kariya, Japan
 Filed Jul. 20, 1994, Ser. No. 277,899
 Claims priority, application Japan, Jul. 26, 1993, 5-184152
 Int. Cl. D01H 9/00; 9/10

U.S. Cl. 57-269

11 Claims



2. A roving bobbin changing apparatus including roving end finding/pick-up means for finding and picking up roving ends from at least two full roving bobbins disposed on an auxiliary rail extending alongside a creel of a spinning machine, roving tying means for tying to rovings of roving-depleted bobbins said roving ends that have been found and picked up from said full roving bobbins, and roving bobbin exchanging means for transferring said roving-depleted bobbins to said auxiliary rail while transferring to bobbin hangers of said creel said full roving bobbins from which previously tied rovings are being delivered for spinning, said apparatus being characterized in that:

said roving bobbin changing apparatus comprises a roving end finding/pick-up section and a roving tying/bobbin exchange section; and


said roving end finding/pick-up means is disposed in said roving end finding/pick-up section and said roving bobbin exchanging means is disposed in said roving tying/bobbin exchange section, said roving end finding/pick-up section being coupled to said bobbin changing apparatus at a position ahead of said roving tying/bobbin exchange section when viewed in the direction of movement of said bobbin changing apparatus relative to said spinning machine for substantially concurrent and cyclical operation with said roving tying means and said roving bobbin exchanging means, said roving bobbin exchanging means being reciprocally movable between said roving end finding/pick-up section and said roving tying/bobbin exchange section; and driving means for moving said roving bobbin exchanging means to a position for grasping new rovings in said roving end finding/pick-up section, and to a roving tying position corresponding to that of full roving bobbins transfer means in said roving tying/bobbin exchange section;

such that said roving end finding/pick-up means finds and picks up roving ends from at least two full roving bobbins while said roving tying means ties roving ends found and picked up in an immediately preceding cycle by said roving end finding/pick-up means to rovings of roving depleted bobbins and said roving bobbin exchanging means transfers said roving depleted bobbins to said auxiliary rail while transferring to said bobbin hangers said full roving bobbins which have had roving ends tied in the current cycle and from which rovings are concurrently being delivered.

5,586,429 BRAYTON CYCLE INDUSTRIAL AIR COMPRESSOR James B. Kessell, Mont Vernon, N.H., and Stephen P. Baldwin, Charlotte, N.C., assignors to Northern Research & Engineering Corporation, Woburn, Mass. Filed Dec. 19, 1994, Ser. No. 359,259 Int. Cl. F02C 7/00

U.S. Cl. 60-39.07

10 Claims




1. An apparatus comprising:
 - a combustion chamber;
 - a supply of fuel being provided to the combustion chamber;
 - a first turbine which is driven by exhaust gases leaving the combustion chamber;
 - a second turbine which is driven by exhaust gases leaving the first turbine;
 - a first compressor driven by the second turbine for compressing inlet air;
 - a second compressor driven by the first turbine for compressing the compressed air from the first compressor, the compressed air from the second compressor being divided into two portions, the first portion being provided to the combustion chamber, this first portion defining a combustion air portion, the second portion being extracted to form a supply of compressed air, this second portion defining a supply air portion; and
 - a means for cooling the supply air portion;
 - a dryer system for removing moisture from the supply air portion, the dryer system including a moisture absorption substance capable of being regenerated by the application of air having a temperature higher than the temperature of the cooled supply air portion, a further portion of the combustion air portion being applied to the moisture absorption substance for regenerating the moisture absorption substance, this portion of the combustion air portion defining a regeneration air portion.

5,586,430 BALANCED DUAL FLOW REGENERATOR HEAT EXCHANGER SYSTEM AND CORE DRIVING SYSTEM John M. Stopa, 6659 W. Torch Lake Dr., Kewadin, Mich. 49648 Division of Ser. No. 301,003, Sep. 6, 1994, Pat. No. 5,538,073. This application May 15, 1995, Ser. No. 440,771 Int. Cl. F02C 7/105

U.S. Cl. 60-39.511

32 Claims

1. A gas turbine engine for producing power from a fluid medium, said turbine engine comprising:
 - a gas generator having a compressor member for compressing the fluid medium, a first turbine member for driving said compressor member and a combustion member interposed said compressor member and said first turbine member for increasing the temperature of the fluid medium prior to said first turbine member;
 - a second turbine member adjacent to said gas generator for extracting power from the fluid medium as the fluid medium passes through said second turbine member; and




a rotary heat scavenging member adjacent to said gas generator, said rotary heat scavenging member passing the fluid medium from said compressor member at least two times through said rotary scavenging member and passing the fluid medium from said second turbine once through said rotary scavenging member.

5,586,431 AIRCRAFT NACELLE VENTILATION AND ENGINE EXHAUST NOZZLE COOLING Douglas A. Thonebe, Jupiter, and Russell L. Coons, Palm Beach Gardens, both of Fla., assignors to United Technologies Corporation, Hartford, Conn. Filed Dec. 6, 1994, Ser. No. 349,843 Int. Cl. F02K 1/12; 3/04

U.S. Cl. 60-226.1

15 Claims




1. A combined purging and cooling system for the nacelle of an aircraft and the edge pieces of the flap of a two-dimensional exhaust nozzle of a gas turbine engine comprising a double clam shell convergent flap and divergent flap, means defining in said convergent flap a pair of side by side passageways, one of said passageways for conducting fan air and the other of said passageways for conducting nacelle air, pumping means including a tubular manifold member and a plurality of supersonic nozzles in said tubular manifold member in fluid communication with said passageway conducting fan air, a cavity adjacent to said other of said passageways in fluid pumping relationship with said supersonic nozzles for pumping said nacelle air, a rectangular mixing plenum in communication with said cavity for mixing the fan air and the nacelle air, transfer means in fluid communication with said rectangular mixing plenum for conducting mixed fan air and nacelle air to the exterior surface of the edge pieces of said exhaust nozzle and a source of fan air and nacelle air.

5,586,432 DEVICE FOR REGULATION OF A MOTOR VEHICLE ENGINE AT IDLE SPEED Gerhart Huemer, Neukeferloh, and Heinz Lemberger, Unterfoehring, both of Germany, assignors to Bayerische Motoren Werke AG, Munich, Germany Filed Oct. 11, 1994, Ser. No. 320,317 Claims priority, application Germany, Oct. 11, 1993, 43 34 557.3

U.S. Cl. 60-274

Int. Cl. F01N 3/20

16 Claims



1. A device for operating a motor vehicle engine at idle, said engine having two rows of cylinders, and a catalytic converter and an oxygen sensor operatively associated with each of said two rows, the device comprising:


means for alternately shutting-off injectors of one of said two rows of cylinders during idle operation of the engine when a temperature (T) of the associated catalytic converter is above a predetermined temperature limit (T_C); and
 means for switching an injection valve shut-off from one row of cylinders to the other row of cylinders when the temperature (T) of said catalytic converter associated with said row of cylinders having just been shut-off falls below the predetermined temperature limit (T_C).

5,586,433 PROCESS AND APPARATUS FOR SELECTIVE CATALYZED NO-REDUCTION IN OXYGEN- CONTAINING EXHAUST GASES Walter Boegner, Remseck; Michael Kraemer, Notzingen; Bernd Kruttsch, Denkendorf; Guenter Wenninger, Stuttgart; Friedrich Wirbeleit, Esslingen, and Werner Weisweiler, Remchingen, all of Germany, assignors to Daimler-Benz AG, Germany Filed Feb. 14, 1995, Ser. No. 388,037 Claims priority, application Germany, Feb. 14, 1994, 44 04 617.0

U.S. Cl. 60-274

Int. Cl. F01N 3/36

10 Claims



1. An arrangement for selective catalyzed NO_x-reduction in oxygen-containing exhaust gases of a diesel internal-combustion engine, comprising an exhaust pipe operatively connected with the engine, an exhaust gas purifier arranged in the exhaust pipe, a fuel tank operatively connected with an engine intake of the engine, a cracked catalyst in fluid communication with the exhaust pipe

upstream of the exhaust gas purifier and thermally isolated from a flow of exhaust gas from the engine, an air pipe operatively associated with the cracked catalyst, a metering pipe operatively arranged between the fuel tank and cracked catalyst, a motoring pump arranged in the metering pipe to meter diesel fuel stored in the fuel tank to the cracked catalyst, wherein a defined fuel quantity from the stored fuel is catalytically cracked to produce a substantial portion of short-chained unsaturated hydrocarbons, and the defined fuel quantity is oxidizable by air simultaneously supplied thereto from the air pipe, and a supply pipe provides the fluid communication between the exhaust pipe and the cracked catalyst for supplying in metered amounts the short-chained unsaturated hydrocarbons to the exhaust gas upstream of the exhaust gas purifier for purifying the exhaust gas.


5,586,434 ONE WAY CLUTCH MECHANISM FOR A TORQUE CONVERTER

Mamoru Okubo, Neyagawa, and Koji Yoneyama, Shijonawate, both of Japan, assignors to Exedy Corporation, Osaka, Japan

Filed Aug. 30, 1995, Ser. No. 520,795
Claims priority, application Japan, Sep. 13, 1994, 6-219233
Int. Cl. F16D 41/06

U.S. Cl. 60-345

3 Claims



1. A stator assembly for a torque converter assembly, comprising:
an inner race;

- a metal outer race having a plurality of friction surfaces formed on an inner circumferential portion, a distance between a first point of each of said friction surfaces and an outer surface of said inner race being smaller than the distance between a second point of each of said friction surfaces and said outer surface of said inner race;
- a ring-shaped resin stator carrier molded about at least an outer circumference of said outer race to be integral therewith, said ring-shaped resin stator carrier formed with a plurality of supporting elements, said supporting elements extending axially between said inner race and said outer race;
- a one-way clutch mechanism including a plurality of rolling elements disposed between said inner race and said outer race, one of said rolling elements disposed between each pair of adjacent ones of said supporting elements, a plurality elastic elements, one elastic element disposed adjacent to each of said supporting elements for urging said rolling elements in a first circular direction.


3. A method of manufacturing a stator carrier having a one way clutch mechanism for a torque converter, comprising:
providing an outer race member with a plurality of circumferentially inclined surfaces and a plurality of concave portions, one concave portion formed between each pair of adjacent inclined surfaces;
positioning a mold concentrically within the outer race, the mold formed with a plurality of inclined surfaces corresponding to the inclined surfaces on the outer race;
rotating the mold relative to the outer race bringing the inclined surfaces on the mold into engagement with the inclined surfaces on the outer race; and

injecting resin into spaces defined between the mold and the outer race forming protruding members therebetween and further forming a stator carrier around the outer periphery of the outer race.

5,586,435
HYDRAULIC CLOSED LOOP CONTROL SYSTEM
George P. Kokalis, Ann Arbor, Mich., assignor to Servo Kinetics, Ann Arbor, Mich.
Continuation of Ser. No. 389,071, Jan. 3, 1995, abandoned, which is a continuation of Ser. No. 94,508, Jul. 20, 1993, abandoned. This application Oct. 13, 1995, Ser. No. 543,207
Int. Cl. F16D 31/02

U.S. Cl. 60-416

1 Claim



1. A hydraulic control system for a die casting machine of the type having a shot cylinder with first and second ports and applying a force on a shot plunger for forcing molten metal into a casting die, said control system comprising:


- a source of hydraulic fluid acting on said shot cylinder first port for applying a force on said shot plunger urging said shot plunger to force said molten metal into said die;
- a servo valve having a single translatable servo spool for metering a servo control pressure source and a return line providing first and second servo control pressure signals, said servo spool being urged to translate by direct mechanical connection to a voice coil actuator having a permanent magnet affixed to a housing of said servo valve and a relatively moveable coil which is directly affixed to said servo spool such that they move linearly together, said servo valve further having a first position transducer providing a first output signal related to positioning of said servo spool;
- a proportional spool valve having a metering spool translatable in response to first and second shift control pistons acting on opposite ends of said metering spool, said metering spool providing a variable restriction for flow of said hydraulic fluid from said shot cylinder second port thereby controlling pressure differentials acting on said shot plunger and thus controlling forcing of molten metal into said casting die, said proportional valve further having a second position transducer providing a second output signal related to positioning of said metering spool;
- conduit means for communicating said first and second servo control pressure signals with said first and second shift control pistons thereby enabling said servo valve to control said proportional spool valve to provide control of said variable restriction; and
- a third position transducer coupled to said shot plunger and providing a position signal related to the position of said shot plunger, said position signal and said second output signal resulting in a control signal, said control signal being utilized in conjunction with said first output signal for causing movement of said movable coil in response thereto;
- a first hydraulic accumulator in said servo valve control pressure source;
- a second hydraulic accumulator in said servo valve control pressure return;
- an intermediate holding mounted directly to said proportioned spool valve and having a fluid capacity greater than the capacity of said shot cylinder; and

controller means for receiving said position signal and said second output signal and producing said control signal as a result thereof, said controller means also receiving said first output signal, said first output signal and said control signal being utilized by said control means to generate a signal to be applied to said voice coil thereby enabling control over said shot cylinder.

5,586,436
MASTER CYLINDER RESERVOIR
Shozo Sakaguchi, Mitsuhiro Ikeda, and Syusaku Chiba, all of c/o Matsuyama Plant, Jidosha Kiki Co., Ltd. 11-6, Shinmeicho, 2-chome, Higashimatsuyama-shi, Saitama-ken, Japan
Filed Jun. 23, 1995, Ser. No. 494,679
Claims priority, application Japan, Jun. 30, 1994, 6-148908
Int. Cl. B60T 11/26

U.S. Cl. 60-585

2 Claims



1. A master cylinder reservoir comprising a diaphragm interposed between a cap and a body to define an upper chamber communicating with the outside and a lower chamber communicating with a reservoir chamber, said diaphragm having upper and lower surfaces and a peripheral edge, and a slit or an air valve is formed in said diaphragm so that said slit or said valve is opened by the deformation of said diaphragm caused by the pressure difference acting on the upper and lower surfaces of said diaphragm, by which communication is permitted between said upper and lower chambers, wherein a plate is disposed below said diaphragm in such a manner as to substantially cover said diaphragm, said plate including upper and lower surfaces, and a vent hole communicating between the upper and lower surfaces of said plate is provided, wherein the peripheral edge of said diaphragm is extended downwardly, and said plate is fixed to said extended portion, wherein a step portion is formed at the middle position on the inner peripheral surface of said extended portion, said plate comprises an upper disk portion, a lower disk portion, and a column portion for connecting the two disk portions with each other at the center thereof, and said plate is fixed to said diaphragm by engaging said upper disk portion with said step portion and engaging said lower disk portion with the lower end of said extended portion.


5,586,437
MRI CRYOSTAT COOLED BY OPEN AND CLOSED CYCLE REFRIGERATION SYSTEMS
Leo Blecher, Schenectady, N.Y.; Ralph C. Longworth, Allentown, Pa.; F. Scott Murray, Schenectady; Philip A. Jonas, Albany, both of N.Y., and Michael Bolarski, Moscow, Russian Federation, assignors to Intermagnetics General Corporation, Latham, N.Y.

Filed Sep. 6, 1995, Ser. No. 524,400
Int. Cl. F17C 5/02

U.S. Cl. 62-47.1

22 Claims

1. A cryostat system for maintaining a load at a predetermined cryogenic temperature, comprising:
a chamber for containing in an interior volume a liquid cryogenic refrigerant, said chamber having a vent tube connected between said interior volume and an ambient environment of said cryostat;
an evacuated housing surrounding said chamber, said vent tube extending through an evacuated space within said housing to said ambient environment;




a first thermal intercept positioned within said evacuated space between said chamber and said ambient environment, a first heat transfer relationship existing between said first thermal intercept and said vent tube, heat from said first thermal intercept being transferred to gaseous refrigerant which, in use, boils off from said liquid in said chamber and flows through said vent tube to said ambient environment;
a second thermal intercept positioned within said evacuated space between said first thermal intercept and said ambient environment;
a refrigerant evaporator within said evacuated space, a second heat transfer relationship existing between said second thermal intercept and said evaporator, heat from said second thermal intercept being transferred, in use, to refrigerant in said evaporator, said evaporator, in use, being part of a closed cycle vapor compression refrigeration unit;
a temperature for said load being determined by a boiling temperature of said liquid refrigerant in said vented chamber, said first thermal intercept being generally warmer than said load temperature, said second thermal intercept being generally warmer than said first thermal intercept and colder than a temperature of said ambient environment.

5,586,438
PORTABLE DEVICE FOR PRESERVING ORGANS BY STATIC STORAGE OR PERFUSION
Gregory M. Fahy, Gaithersburg, Md., assignor to Organ, Inc., and LRT, Inc., both of Chicago, Ill.
Filed Mar. 27, 1995, Ser. No. 411,274
Int. Cl. F24F 3/16; F25D 3/08

U.S. Cl. 62-78

21 Claims



1. A device for holding an organ, comprising:
an organ container;
a lower organ receiving portion located within the organ container; and
an upper organ receiving portion located within the organ container and spaced from said lower organ receiving portion.

wherein the upper and lower organ receiving portions are configured to contact and immobilize an organ.

5,586,439


ICE MAKING MACHINE

Charles E. Schlosser, Manitowoc; Lee G. Mueller, Kewaunee, and Gregory McDougal, Manitowoc, all of Wis., assignors to The Manitowoc Company, Inc., Manitowoc, Wis.
Continuation of Ser. No. 201,758, Feb. 25, 1994, Pat. No. 5,408,834, which is a continuation of Ser. No. 989,791, Dec. 11, 1992, Pat. No. 5,289,691. This application Apr. 24, 1995, Ser. No. 429,286

Int. Cl.⁶ F25C 1/14

U.S. Cl. 62—78

27 Claims




21. A method of automatically cleaning the surfaces of an ice making machine comprising

- i) a coolant/refrigerant system having a compressor, a condenser, an evaporator, an expansion device and a hot gas valve for directing hot gases from the compressor to the evaporator;
- ii) a water/ice system comprising a fresh water inlet, a water reservoir, a water circulation mechanism, and an ice forming evaporator plate; and
- iii) an electronic controlling/monitoring system comprising a microprocessor which controls the compressor, the water circulation mechanism and the hot gas valve; the method comprising the steps of:
 - a) stopping the compressor;
 - b) performing a wash cycle by
 - i) starting the water circulation mechanism;
 - ii) adding a cleaning/sterilizing solution to water in the water/ice system; and
 - iii) circulating the water containing the cleaning/sterilizing solution through the water reservoir and over the ice forming evaporator plate for a period of time after step b) i), said period of time being controlled by the microprocessor;
 - c) automatically stopping the circulation of water containing the cleaning/sterilizing solution over the ice forming evaporator plate after said period of time; and
 - d) performing a rinse cycle in which the microprocessor controls the water/ice system to automatically operate through a series of multiple rinse operations in each of which fresh water is introduced through the fresh water inlet and water from the water reservoir is removed from the water/ice system, thereby ensuring a complete rinsing of the cleaning/sterilizing solution from the water/ice system.

5,586,440
PNEUMATIC REFRIGERATION SYSTEM AND METHOD
David M. Vincent, c/o Chester, Wilcox & Sarbe 17 S. High St., Suite 900, Columbus, Ohio 43215-3413
Filed Dec. 6, 1994, Ser. No. 349,918
Int. Cl.⁶ F25B 9/00

U.S. Cl. 62—87

9 Claims



1. A pneumatic refrigeration system comprising:
 - a compressor for generating a pressure increase in an air flow;
 - a system expander downstream of the compressor for reducing a temperature of the air flow;
 - a pre-cooler downstream of the compressor and upstream of the system expander for cooling the air flow prior to expansion, wherein the pre-cooler includes a pre-cooling expander for expanding a portion of the air flow and a pre-cooling heat exchanger for exchanging heat from a remainder of the air flow to that portion of the air flow; and
 - a recycling conduit downstream of the system expander for conducting at least a part of the air flow toward the compressor.

5,586,441
HEAT PIPE DEFROST OF EVAPORATOR DRAIN
Wilbert J. Wilson, Fullerton, Calif., and Robert G. O'Neal, Yuma, Ariz., assignors to Russell A Division Of Arco, Inc., Brea, Calif.
Filed May 9, 1995, Ser. No. 438,169
Int. Cl.⁶ F25D 17/02

U.S. Cl. 62—99

17 Claims




13. A method of passively defrosting a drain from a drain pan located beneath an evaporator in a refrigeration circuit, comprising the steps of:

- a) placing a condenser end of a sealed heat pipe in heat transfer relation with an inlet to said drain; and
- b) exposing an evaporator end of said heat pipe to a heat source such that a heat transfer fluid within said heat pipe is heated to a vapor phase.

5,586,442
THERMAL ABSORPTION COMPRESSION CYCLE
Carl D. Nicodemus, Satellite Beach, Fla., assignor to Helios Research Corp., Mumfords, N.Y.
Filed Oct. 17, 1994, Ser. No. 324,779
Int. Cl.⁶ F25B 15/00

U.S. Cl. 62—107

48 Claims




1. In an absorption cycle system using an absorbent liquid and an absorbable working fluid, the improvement comprising:
 - a. a system stream of working fluid vapor directed to merge with a system stream of absorbent liquid so that the kinetic energy of the vapor accelerates the liquid stream while an absorbable portion of the vapor is absorbed in the liquid stream and an unabsorbable additional portion of the vapor is entrained in the liquid stream; and
 - b. a nozzle and a diffuser receiving the combined liquid and vapor streams and converting fluid velocity to pressure applied to a liquid mixture containing substantially more of the working fluid than can be absorbed in the absorbent liquid stream.

5,586,443
REFRIGERANT CONSERVATION SYSTEM AND METHOD
Gordon A. C. Lewis, Ronkonkoma, N.Y., assignor to Conair Corporation, Garden City Park, N.Y.
Filed Sep. 20, 1995, Ser. No. 530,961
Int. Cl.⁶ F25B 1/00

U.S. Cl. 62—115

20 Claims

12. A method for preventing the release of refrigerant to the atmosphere from a mechanical refrigeration system having a plurality of compressors, comprising:
 - providing a refrigerant overpressure receiver tank for receiving refrigerant from a high pressure side of the mechanical refrigeration system,
 - preventing a first overpressure flow of refrigerant to the receiver tank unless the pressure on said high pressure side of the refrigerant loop exceeds a first predetermined value which is higher than the safe operating pressure of said high pressure side of the refrigerant loop,
 - collecting refrigerant from said high pressure side in the overpressure receiver tank when the pressure on said high pressure side exceeds said first predetermined value,




preventing further operation of at least one but not all of said plurality of compressors in the mechanical refrigeration system when the pressure in said overpressure receiver tank exceeds a second predetermined value which is substantially lower than said safe operating pressure, and continuing the operation of at least one of said plurality of compressors in the mechanical refrigeration system while said further operation of at least one compressor is prevented.

5,586,444
CONTROL FOR COMMERCIAL REFRIGERATION SYSTEM
Kwok K. Fung, South Bend, Ind., assignor to Tyler Refrigeration, Niles, Mich.
Filed Apr. 25, 1995, Ser. No. 428,580
Int. Cl.⁶ F25B 7/00; F04B 41/06

U.S. Cl. 62—117

31 Claims



1. Capacity control system for a commercial refrigeration system having at least one refrigerator case, said refrigeration system including a compressor system for compressing refrigerant, said compressor system including a variable speed compressor and fixed speed compressors whereby the capacity of said system can be controlled by varying the speed of the variable speed compressor and by turning said fixed speed compressors on or off, said control system including load sensing means for detecting a variable indicative of the refrigeration load on the system, means for comparing said variable with a target value and generating a difference signal varying in accordance with the difference between the variable and the target value, and calculating means for calculating a compressor control signal for controlling the capacity of said system as a function of the second derivative with respect to time of said difference signal.

pressors through the respective oil return means whereby bypassed excess oil is returned to each of said plurality of compressors responsive to the respective oil level in each compressor.

5,586,451

PROCESS AND INSTALLATION FOR THE PRODUCTION OF OXYGEN BY DISTILLATION OF AIR


Yves Koeberle, Le Perreux sur Marne, and Philippe Frayssé, Fontenay aux Roses, both of France, assignors to L'Air Liquide, Société Anonyme Pour l'Étude et l'Exploitation des Procédés Georges Claude, Paris, France

Filed Apr. 10, 1995, Ser. No. 419,441

Claims priority, application France, Apr. 12, 1994, 94 04298
Int. Cl.⁶ F25J 3/02

U.S. Cl. 62-646

10 Claims



1. A process for the production of gaseous oxygen under pressure by cryogenic distillation of air in a double column comprising a medium pressure column and a low pressure column, comprising dividing rich liquid from the medium pressure column into first and second liquid fractions, sending all of said first and second liquid fractions in liquid phase to different levels in the low pressure column, and withdrawing impure nitrogen from the low pressure column, both of said different levels being below a level of said withdrawal of impure nitrogen from the low pressure column.

5,586,452

JEWELRY WITH AN INTEGRAL HINGE

Peter Schmid, Leeds, United Kingdom, assignor to Abbeycrest Plc., Leeds, England

Continuation of Ser. No. 970,377, Nov. 2, 1992, abandoned.

This application Feb. 4, 1994, Ser. No. 192,303


Claims priority, application United Kingdom, Nov. 6, 1991, 9123539

Int. Cl.⁶ A44C 15/00

U.S. Cl. 63-19

10 Claims

1. An item of jewelry comprising:
(a) first and second blanks in the form of endless rims, and defining thereby respective first and second endless rims;
(b) means on said first endless rim defining over a length of said first endless rim, an integral hinge pin; and
(c) an integral tongue on said second endless rim which wraps around the said length of said first endless rim, said means on said first endless rim being a part of the rim itself whereby said endless rims are connected hingedly together without the need for a separate pintle pin or an additional hinge wire.



5,586,453

METHOD AND APPARATUS FOR TREATING STITCHES OF KNIT ARTICLES


Alberto Frullini, and Paolo Frullini, both of Via di Brozzi 151/A, 50145 Firenze, Italy

Filed Aug. 24, 1995, Ser. No. 519,115

Claims priority, application Italy, Sep. 7, 1994, F194A170
Int. Cl.⁶ D04B 9/40

U.S. Cl. 66-148

26 Claims



1. A method for removing stitches from needles, the method comprising the steps of:
providing a compound type needle with a latch and a stitch latched in a hook of said needle;
providing a sinker in a closed position with respect to said needle;
lifting said needle with respect to said sinker to move the stitch out and away from said hook and said latch while the stitch is on said needle and in an unlatched condition;
providing a punch means for receiving the stitch from said needle;
moving an end of said punch means into contact with said hook;
lowering said needle with respect to said sinker to move the stitch towards said hook and to close said latch with the stitch being outside said latch and said hook, said latch in a closed position covering said hook and a portion of said punch means, said lowering also moving the stitch off of said needle and onto said punch means;
moving said punch means with the stitch away from said needle.

5,586,454

WARP-KNIT TAPE FOR SLIDE FASTENER

Yoshio Matsuda, and Hidenobu Kato, both of Toyama-ken, Japan, assignors to YKK Corporation, Tokyo, Japan


Filed Aug. 25, 1995, Ser. No. 519,403

Claims priority, application Japan, Aug. 26, 1994, 6-202259


Int. Cl.⁶ A44B 19/34; D04B 21/00

U.S. Cl. 66-193

5 Claims



1. A warp-knit tape, for a slide fastener, comprising:
(a) a web portion having a ground knit structure; and
(b) an element-mounting edge portion connected to and extending along said web portion;
(c) said element-mounting edge portion being composed of a reinforcing core, double chain stitches knitted of two knitting yarns respectively extending on opposite sides of said reinforcing core, a weft inlaid structure of a plurality of weft inlaid yarns laid in and extending symmetrically in opposite directions between said double chain stitches on front and back sides, and part of said ground knit structure of said web portion, said double chain stitches forming two wales with said reinforcing core laid therebetween;
(d) said double chain stitches being knitted alternately with the front side and back side of said element-mounting edge portion, said symmetrical weft inlaid yarns being knitted with the front side and back side of said element-mounting edge portion respectively;
(e) said web portion being knitted by knitting needles only on either of the front side or back side.



communicating with the rotatable tub to be filled with water when the water is supplied to the rotatable tub in a wash step; and

a clutch float disposed in the first float chamber so as to be vertically movable along the inner shaft, the clutch float being movable relative to the rotatable tub, the clutch float being engaged with both of the outer and inner shafts to thereby couple the inner shaft to the outer shaft for transmission of rotation when assuming a first position where the clutch float is escaped from buoyancy, the clutch float being moved from the first position to a second position when subjected to buoyancy, thereby decoupling the inner shaft from the outer shaft.

5,586,456

APPARATUS FOR WASHING AND DRYING CLOTHES

Hiroyuki Takagawa, Yasuhiro Tsubaki, Yoshio Miyairi, Toshio Hattori, and Haruo Hagiwara, all of Nagoya, Japan, assignors to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo, Japan Division of Ser. No. 257,295, Jun. 9, 1994, Pat. No. 5,498,266.


This application Sep. 19, 1995, Ser. No. 530,447

Claims priority, application Japan, Jun. 11, 1993, 5-164985; Oct. 28, 1993, 5-270312; Apr. 14, 1994, 6-075557

Int. Cl.⁶ D06F 43/08

U.S. Cl. 68-18 R

7 Claims



1. A dry-cleaning apparatus for washing and drying clothes with a high boiling point combustible solvent comprising:
a first solvent reserve tank for containing a high boiling point combustible solvent;
a second solvent reserve tank for containing a liquid perfluoro-carbon;
a processing tank for washing clothes, selectively connected with solvents reserved in said first and second solvent reserve tanks;
liquid separator means for separating and recovering each solvent used for washing after completion of washing of clothes in said processing tank; and

a means for drying clothes in said processing tank.


5,586,457

VEHICLE ANTI-THEFT DEVICE

Manuel L. Keener, P.O. Box 6625, Dothan, Ala. 36302
Filed Dec. 9, 1994, Ser. No. 355,253
Int. Cl.⁶ F16H 57/00; G05G 5/00

U.S. Cl. 70—201

13 Claims



1. A partial vehicle disablement system for limiting engine operation to idle speed, by selectively locking the vehicle accelerator pedal against depression, comprising:

an obstructing member movable between obstructing and enabling positions, selectively contacting and completely clearing the accelerator pedal, respectively;

means defining an opening through a vehicle firewall in the vicinity of the vehicle accelerator pedal for enabling said obstructing member to be slidably mounted therethrough, toward and beneath the vehicle accelerator pedal; and
a means for moving said obstructing member selectively to said obstructing and enabling positions, said means for moving said obstructing member being located outside of the vehicle firewall and including:

a motor;

a pinion attached to said motor; and

a rack formed on said obstructing member, said pinion engaging said rack;

whereby,

actuation of said motor moves said obstructing member between said enablement position and said obstructing position.

5,586,458

HANDLE OPERABLE ROTARY LATCH AND LOCK


Lee S. Weismann, Medina, and Scott A. Arthurs, Brunswick, both of Ohio, assignors to The Eastern Company, Cleveland, Ohio

Continuation-in-part of Ser. No. 510,470, Aug. 2, 1995, Pat. No. 5,564,295, which is a continuation of Ser. No. 145,691, Oct. 29, 1993, Pat. No. 5,439,240. This application Dec. 22, 1995, Ser. No. 577,717

Int. Cl.⁶ E05C 3/26

U.S. Cl. 70—208

27 Claims



1. A flush-mountable, handle-operable rotary lock for being mounted as a unit on a closure for releasably retaining the closure in a closed position by latchingly engaging a suitably configured strike formation that is located within relatively close proximity to the rotary lock when the closure is in its closed position, comprising:

a) a flush-mountable handle and housing assembly including:

i) a one-piece, flush-mountable, pan-shaped housing for mounting on a closure adjacent a mounting opening formed in the closure, with the housing having back and side wall portions that cooperate to define a forwardly facing recess, with the housing also having a substantially flat front mounting flange that extends in an uninterrupted manner about a front perimeter of the recess, with a major back wall portion being substantially flat and extending in a back wall plane that generally parallels a front plane in which the mounting flange extends, and with a back wall opening formed through the major back wall portion;

ii) an operating handle configured to be nestable within the recess at a location on the front side of the major back wall portion;

iii) pivot means connecting the operating handle to the pan-shaped housing for pivotal movement between a normal, non-operated position nested with the recess at a location on the front side of the major back wall portion, and an operated position wherein a normally nested portion of the handle projects forwardly from the recess;

b) a rotary latch assembly rigidly connected to the pan-shaped housing, including a rotary latch housing that has:

i) a one-piece, elongate, generally rectangular first housing side plate having opposed end regions near opposite ends of the length thereof, having a first side surface that extends lengthwise between the opposed end regions, and defining a first U-shaped notch that opens through the first side surface at a location near one of the opposed end regions of the first housing side plate;

ii) a one piece, elongate, generally rectangular second housing side plate having opposed end regions near opposite ends of the length thereof, having a second side surface that extends lengthwise between the opposed end regions, and defining a second U-shaped notch that opens through the second side surface at a location near one of the opposed end regions of the second housing side plate, with the first and second side surfaces extending in spaced, substantially parallel relationship, and with the second U-shaped notch being substantially aligned with the first U-shaped notch;

iii) spacer means for extending transversely between, for rigidly connecting with, and for maintaining a substantially parallel relationship between the first and second housing side plates, with the spacer means including a first spacer that extends along a first transverse axis that intersects each of the first and second housing side plates at a location that is relatively near to the other end regions thereof, and with the spacer means also including a second spacer that extends along a second transverse axis that intersects each of the first and second housing side plates at a location that is substantially mid-way between the opposite ends thereof;

c) plural connection means rigidly connecting the rotary latch housing to the pan-shaped housing, including a plurality of tab-like projections formed integrally with a chosen one of the first and second housing side plates, with at least one of the tab-like projections extending along and being rigidly connected to a chosen side wall portion of the pan-shaped housing, and at least another one of the tab-like projections extending along and being rigidly connected to the major back wall portion at a location near where said at least one of the tab-like projections extends along and is rigidly connected to said chosen side wall portion;

d) with the rotary latch assembly additionally including a rotary jaw and a rotary pawl that extend substantially within a common plane located between the first and second housing side plates, with the rotary jaw being connected to the second spacer and being rotatable through a limited range of angular movement about the second transverse axis between latched and unlatched positions but being spring-biased toward its

unlatched position, with the rotary pawl being connected to the first spacer and being movable relative to the rotary latch housing about the first transverse axis between jaw-retaining and jaw-releasing positions to selectively release and retain the rotary jaw in its latched position but being spring-biased to move the rotary pawl toward its jaw-retaining position as the rotary jaw moves to its latched position, with the rotary jaw defining a third U-shaped notch that is configured to cooperate with the first and second U-shaped notches to concurrently receive and to latchingly retain within the confines of the first, second and third U-shaped notches a suitably configured strike formation when the rotary latch assembly latchingly engages the strike formation, and with a selected one of the first and second housing side plates being strengthened and enhanced in rigidity adjacent its associated U-shaped notch by the close proximity presence thereto of a transversely extending flange that is formed integrally with said selected housing side plate;

e) an operating arm connected to the major back wall portion for pivotal movement along the rear of the major back wall portion between primary and secondary positions about a pivot axis that extends substantially perpendicular to the major back wall portion, with the operating arm defining three spaced formations, with a first of the three formations being movable adjacent the back wall opening when the operating arm moves between its primary and secondary positions, with a second of the three formations being located generally one side of said pivot axis and being movable adjacent the rotary pawl of the rotary latch assembly to move the rotary pawl to release the rotary jaw from its latched position in response to movement of the operating arm from its primary position to its secondary position, and with a third of the three formations being located generally on an opposite side of said pivot axis and being spaced from the first and second of the three formations and being movable along a path of travel between a first position and a second position in response to movement of the operating arm between its primary and secondary positions;

d) locking means for being connected to the pan-shaped housing and for providing a locking member that is movable into and out of said path of travel to selectively block and permit movement of the operating arm between its primary and secondary positions;

e) projection means for extending through said back wall opening, for being rigidly connected to a selected one of the operating handle and the first of the three formations of the operating arm, and for being engaged by the other of the operating handle and the first of the three formations for establishing a driving connection between the operating handle and the operating arm that will cause the operating arm to move from its primary position toward its secondary position in response to movement of the operating handle from its non-operated position to its operated position, and for blocking movement of the operating handle from its non-operated position to its operated position when the locking member is moved into said path of travel to block movement of the operating arm from its first position to its second position; and,

f) first guide means for defining a first passage of limited length paralleling said back plane within which at least a part of the first of the three formations is movable during movement of the operating arm relative to the pan-shaped housing between the primary and secondary positions of the operating arm, and second guide means for defining a second elongate passage of limited length paralleling said back plane within which at least a part of the third of the three formations is movable during movement of the operating arm between the primary and secondary positions of the operating arm, with said first and second passages being configured to assist in confining said relative movement of the operating arm so as to limit such movement to pivotal movement about said axis to help ensure that other movement of the operating arm that might defeat the action of the lock is resisted.

5,586,459

LOCKING HANDLE


Charles E. Bullock, Waukegan, Ill., and Douglas L. Juga, Kenosha, Wis., assignors to A. L. Hansen Mfg. Co., Waukegan, Ill.

Filed May 16, 1995, Ser. No. 441,820

Int. Cl.⁶ G05G 5/00

U.S. Cl. 70—224

9 Claims



1. In a locking handle of the type comprising a base mountable to a mounting surface and a handle rotatably mounted to the base, the improvement comprising:

a well formed in the handle, said well communicating with a key opening in a front portion of the handle and a loading opening in a rear portion of the handle;

a shaft mounted in the well via the loading opening to rotate with the handle, said shaft comprising a first part which extends out of the base and a second part which forms a recess adjacent the key opening, said first and second parts of the shaft formed to rotate at all times as a unit;

a lock comprising a key receiving slot and a locking element; said lock positioned in the recess to rotate in unison with the handle with the key slot aligned with the key opening, said lock dimensioned to pass through the loading opening but not the key opening for assembly, said locking element passing outside of the shaft to releasably engage the base and thereby selectively lock the handle against rotation with respect to the base.

5,586,460

DEVICE WITH PEAK CURRENT LOOP AND PROCESS FOR THE MAGNETIC SHAPING OF METAL PARTS

Erich Steingroever, Bonn, Germany, assignor to Magnet-Physik Dr. Steingroever GmbH, Germany

Filed Apr. 6, 1995, Ser. No. 417,897

Claims priority, application Germany, Oct. 13, 1994, 44 36 615.9

Int. Cl.⁶ B21D 26/02

U.S. Cl. 72—56


17 Claims

1. A pulse transformer with a high-current loop for magnetic shaping metal parts with high-energy magnetic pulses, characterized in that said high-current loop is a magnetic field shaper, comprising:

an opening to receive metal parts which are to be shaped;

a slit extending through the material of said high-current loop radially with respect to said opening;

said high-current loop characterized in that it is divided into segments forming said opening and separable along a plane through said opening; intermediate layers between said segments of said high-current loop that form said opening, said intermediate layers consisting of a material that prevent parts from becoming welded together; and means for pressing together said segments of said high-current loop that form said opening.



5,586,461

METHODS AND APPARATUS FOR MANUFACTURING HELICAL PRODUCTS


Maurice W. Murphy, Lawrenceville, Ga., assignor to The Morgan Crucible Company plc, Windsor, England

Filed Nov. 4, 1994, Ser. No. 334,136

Int. Cl.⁶ B21F 35/02; 3/02

U.S. Cl. 72-137

6 Claims



1. A method of producing a helical device having legs and a bight, comprising the steps of:

- providing along a first axis an elongated flat strip of material having integrally-formed first, second, third, and fourth sections, the first and third sections defining the legs of the device and the second section defining the bight;
- be knurling the material;
- passing the first section through adjustable forming rollers to form the first section in the shape of a helix, which forming rollers are separated by a predetermined distance and at least one of which forming rollers defines a longitudinal axis along which the first section travels while being formed in the shape of a helix, the distance between the forming rollers determining the diameter of the helix and the angle between the first axis and the longitudinal axis determining the pitch length of the helix;
- bending the second section along the longitudinal axis;
- passing the third section through adjustable forming rollers to form the third section in the shape of a helix;
- cutting the material between the third and fourth sections; and
- thereafter bending the second section.

5,586,462
DEVICE AND METHOD FOR FORMING BENT PIPE OF NON-ANNULAR CROSS-SECTION

Kiyoshi Takeuchi, Toyota; Shin Takeda, Nagoya, and Masao Nakamura, 2-1, Aza Higashiura, Kitayama-cho, Toyohashi city, Aichi-pref., all of Japan, assignors to Aisin Seiki Kabushiki Kaisha, and Masao Nakamura, both of Aichi, Japan


Filed Jan. 31, 1995, Ser. No. 380,947

Claims priority, application Japan, Jan. 31, 1994, 6-009186

Int. Cl.⁶ B21D 9/05; B21C 1/24; B21B 17/02

U.S. Cl. 72-150

10 Claims



1. A device for converting a straight pipe having an annular cross-section defined between an inner diameter and an outer diameter into a bent pipe having a non-annular cross-section, comprising:

- a round, bar-shaped guide member having a first end portion and a second end portion spaced from the first end portion in the axial direction, said guide member being adapted for mounting slidably with the straight pipe;
- a floating member including an expanding portion with a first end thereof being connected to the second end of said guide member in a ball-and-socket joint, said first end having a cross-section in the form of a circle with a diameter less than the inner diameter of said straight pipe, said expanding portion further having a second end with a cross-section formed as a polygon and a maximum diameter larger than the inner diameter of the straight pipe, wherein
- a cross-sectional area of said expanding portion along a longitudinal axis of said floating member increases from said first end to said second end having said maximum diameter, an outer surface area of said expanding portion comprising a plurality of adjacent trapezoids positioned to form sides of said polygon in cross-section with adjacent pairs of said polygon sides each defined to form an arcuate corner therebetween with a predetermined radius, the predetermined radius of adjacent polygon sides being defined to progressively decrease from said first end to said second end of said expanding portion;
- feeding means for sliding said straight pipe on said guide member toward said floating member such that said straight pipe is brought into engagement with said floating member thereby forming said non-annular cross-section of said straight pipe; and
- bending means for bending the resultant pipe by applying a force thereto.

5,586,463

PIPE BENDING DEVICE

Reen-Yuan Sheen, P.O. Box 1-394, Chungho, Taipei Hsien, Taiwan

Filed Aug. 17, 1995, Ser. No. 515,643


Int. Cl.⁶ B21D 5/14; B21B 39/02

U.S. Cl. 72-166

4 Claims

1. A pipe bending device comprising:

- a drive toothed wheel;



5,586,465

PRESS BRAKE CONTROLLER POSITIONING SYSTEM
Raymond R. Alcini, 195 Mast St., Morgan Hill, Calif. 95037, and Dan E. Ritola, 406 Imboden Rd., Castle Rock, Wash. 98611

Filed Nov. 22, 1994, Ser. No. 344,351

Int. Cl.⁶ B21J 13/00

U.S. Cl. 72-441

23 Claims

a plurality of guide toothed wheels arranged at a same level and oppositely to said drive toothed wheel;

- a first guide mold located under said drive toothed wheel and having teeth engaged with said drive toothed wheel;
- a second guide mold disposed on said guide toothed wheels and having teeth engaged with said guide toothed wheels;
- a mandrel adapted to be inserted into a pipe to be bent and having a link at an end thereof, said pipe having an end which will be fastened on an end of said first guide mold in operation.

5,586,464

MODULAR DIE TRANSFER SYSTEM


Boice F. Horde, Westland, and Denver Akers, Lincoln Park, both of Mich., assignors to Livernols Die and Automation, Dearborn, Mich.

Filed Oct. 20, 1995, Ser. No. 546,537

Int. Cl.⁶ B21D 43/05


U.S. Cl. 72-405.16

13 Claims



1. In a die transfer system for transferring workpieces between successive die stations in a stamping press, and including elongated bar means having spaced means for engaging workpieces at successive die stations, first means for reciprocating said bar means longitudinally for transferring workpieces between successive die stations, and second means for reciprocating said bar means horizontally into and out of engagement with workpieces at the die stations and vertically upwardly and downwardly with respect to the die stations, said second means comprising:

- at least one drive module coupled to said bar means, drive shaft means coupled to said drive module, and means coupled to said drive shaft means for operating said drive shaft means and said drive module in synchronism with operation of the stamping press, said drive module comprising:
- crank arm means, means operatively coupling said crank arm means to said drive shaft means for rotating said crank arm means about an axis parallel to said bar means, cam plate means coupled to said bar means and mounted for movement laterally of said axis both horizontally and vertically with respect to said axis, cam slot means extending along said cam plate means, and cam follower means disposed in said slot means and coupled to said crank arm means,
- the improvement wherein said slot means includes first and second slot portions lateral to said axis and orthogonal to each



1. A controller positioning system for use with a piece of equipment having a user-operated controller having an interface for manually inputting parameters to control the piece of equipment, said piece of equipment having a length, said controller positioning system comprising:

- a guide means for guiding said user-operated controller along at least a portion of the length of said piece of equipment,
- a powered means for moving said user-operated controller along said guide means,
- and a control means for controlling the movement of said user-operated controller along said guide means.

5,586,466

NON-SLIP SLEEVE FOR FLOAT LEVEL SENSOR SHAFT
George A. Steiner, 4425 Harvard Ave., Montreal, Quebec, Canada

Filed Dec. 16, 1993, Ser. No. 168,547

Int. Cl.⁶ G01F 23/30

U.S. Cl. 73-319

4 Claims

1. In a float level sensor wherein at least one float has a vertical linear movement on a shaft with a circular external cross-section, the movement caused by variation in liquid level, the improvement comprising:


- a non-stick thin walled sleeve formed of a polytetrafluoroethylene polymer fitting over the shaft, extending for at least the vertical linear movement of the float, the float freely slidable over the sleeve, and
- gripping means for retaining the sleeve in a desired position on the shaft.



5,586,467
IMPACT PROTECTED CAM DRIVE FREE OF BACKLASH

Uwe Weber, Aalen, Germany, assignor to Carl Zeiss Stiftung, Heidenheim-Brenz, Germany
Filed Mar. 29, 1995, Ser. No. 412,587
Claims priority, application Germany, Apr. 2, 1994, 44 11 516.4

U.S. Cl. 74—57 Int. Cl.⁶ F16H 25/12 8 Claims




1. A backlash-free cam drive which can be subjected to an impact load, the cam drive comprising:
a cam member having a guide path thereon;
said guide path defining two mutually adjacent cam tracks;
a cam follower unit including first and second contact rollers mounted thereon so as to be resiliently biased relative to each other and against corresponding ones of said cam tracks; and,
an ancillary component mounted thereon so as to be in spaced relationship to said cam tracks in the absence of said impact load and contact engaging one of said cam tracks in response to said impact load on said cam drive;
said cam member including a first material for defining said cam tracks and said ancillary component including a contact part for contact engaging said one cam track; and,
said contact part being made of a second material elastically softer than said first material.

5,586,468
TABLE DRIVING DEVICE
Katsura Tomotaki, Narashino, Japan, assignor to Seiko Seiki Kabushiki Kaisha, Japan
Filed Jul. 28, 1994, Ser. No. 282,077
Claims priority, application Japan, Jul. 30, 1993, 5-190576
Int. Cl.⁶ F16H 25/24

U.S. Cl. 74—89.15 2 Claims

1. A table driving device comprising:




- a guide portion with which a part of a table is movably engaged for guiding the table;
- a feed screw disposed in parallel with a moving direction of the table;
- driving means for rotating the feed screw;
- a nut threadedly engaged with the feed screw;
- a nut holder having a nut connecting portion connected to the nut and an engaging portion movably engaged with the guide portion, and moving along the feed screw and the guide portion together with the nut in accordance with the rotation of the feed screw; and
- a coupling portion for coupling the engaging portion of the nut holder to the part of the table that is engaged with the guide portion through a ball that can roll in a plane perpendicular to the moving direction of the table.

5,586,469
OUT-OF-CIRCUIT BALL PREVENTING STRUCTURE FOR BALL SCREW NUT
Hidenaga Mitani, and Hiroshi Morimoto, both of Gunma, Japan, assignors to NSK Ltd., Tokyo, Japan
Filed Mar. 15, 1995, Ser. No. 404,443
Claims priority, application Japan, Mar. 15, 1994, 6-044306
Int. Cl.⁶ F16H 25/22

1. A ball screw nut adapted to having balls loaded therein, comprising:


- a plurality of ball circulation circuits including a first in-circuit groove and a second in-circuit groove for circulating the balls, and an out-of-circuit groove disposed between a first ball circulation circuit and a second ball circulation circuit of said plurality of balls for circulating no balls in an inner circumferential surface of the ball screw nut, wherein the out-of-circuit groove has an oblique diameter that is smaller than that of the first and second in-circuit grooves.



5,586,470
GEAR-CHANGING DEVICE FOR A GEAR BOX, IN PARTICULAR A MOTOR VEHICLE GEAR BOX
Gerhard Bailly; Detlef Baasch, and Unal Gazyakan, all of Friedrichshafen, Germany, assignors to ZF Friedrichshafen AG, Friedrichshafen, Germany
PCT No. PCT/EP93/02920, § 371 Date Mar. 31, 1995, § 102(e)
Date Mar. 31, 1995, PCT Pub. No. WO94/10484, PCT Pub. Date May 11, 1994

PCT Filed Oct. 22, 1993, Ser. No. 411,702
Claims priority, application Germany, Oct. 28, 1992, 42 36 336.5

U.S. Cl. 74—477 Int. Cl.⁶ F16H 63/36 6 Claims




1. A gear-changing device for a transmission comprising:
a slider-crank mechanism (4) comprising a plurality of oscillating cranks (5) each being operably connected to a slide rod (1);
one end of each of said plurality of oscillating cranks (5) supporting a coupling mechanism (6) while an opposite end of each of said plurality of oscillating cranks (5) communicating with a switching element (12);
said slide rod (1) having a plurality of driving apertures (10) formed therein for accommodating said coupling mechanisms (6) when in a driving position;
a housing having a plurality of rest apertures (8) formed therein for accommodating said coupling mechanisms (6) when in a rest position; and
each of said plurality of switching elements (12) being movable, via the slider-crank mechanism (4), from a stationary position to a switching position in such a manner that the stationary position is urged by said coupling mechanism (6) and a driving position is achieved via the slide rod (1);

wherein a spacing distance (B) between the rest apertures (8) formed in the housing (11) is different from a spacing distance (A) between driving apertures (10) formed in the slide rod (1).

5,586,471
ENERGY STORAGE FLYWHEEL DEVICE
Vincent C. Nardone, South Windsor; Mark S. Thompson, Vernon, and Thomas G. Meyer, Lebanon, all of Conn., assignors to United Technologies Corporation, Hartford, Conn.
Division of Ser. No. 128,319, Sep. 29, 1993, Pat. No. 5,452,625.
This application Jun. 7, 1995, Ser. No. 487,878
Int. Cl.⁶ F16F 15/30


U.S. Cl. 74—572 15 Claims



1. An energy storage flywheel device, comprising:
(a) at least one annular shaped composite section, and,
(b) at least one annular shaped insert having a specific radial strength substantially greater than the composite section's specific radial strength, wherein the insert and composite section are shaped to form interlocking features that provide a mechanical bond between the insert and composite section, wherein the insert comprises a monolithic metal selected from the group consisting of Al, Al alloys, Ti, Ti alloys, Ni, Ni alloys, and steel,
wherein the composite section, and the insert are alternately stacked along a common axis such that they have a common axis of rotation and are bonded to each other such that radial load transfers between the composite section and insert.

5,586,472
DETACHABLE BICYCLE PEDAL MOUNTING STRUCTURE
Wen-Hwa Lin, No. 5, Ming Shen Rd., Ta Chia Chen, Taichung Hsien, Taiwan
Filed Aug. 31, 1995, Ser. No. 522,078
Int. Cl.⁶ B62M 3/08


U.S. Cl. 74—594.1 1 Claim



1. A detachable bicycle pedal mounting structure comprising a crank having a screw hole at one end, a pedal having a spindle of hexagonal cross section, and a connector having a cylindrical

shape with an axis, first and second ends arranged along said axis, a stepped hole radially extending from said axis, and a lock means mounted in said stepped hole for locking said spindle within said connector and preventing rotation of said spindle relative to said connector and said crank.

said first end of said connector is a screw rod threaded into said screw hole of said crank and said second end of said connector is a hexagonal coupling hole receiving said spindle of said pedal; said stepped hole has a cylindrical upper hole, a cylindrical lower hole below said upper hole, and a step between said upper hole and said lower hole; a diameter of said lower hole is smaller than a diameter of said upper hole, said lock means including a locating bolt mounted in said stepped hole of said connector and tightly received in a locating hole of said spindle when locking said spindle in place; a head with a top and a side, a shank having an annular groove and extending from said head, a clamp secured in said annular groove of said locating bolt, a packing ring mounted around said shank of said locating bolt underneath said head, a spring mounted around the shank of said locating bolt and arranged between said packing ring and said clamp for providing a downward bias to said clamp and forcing said shank of said locating bolt into the locating hole of said spindle of said pedal, and a finger rod rotatably mounted in said head; said finger rod arranged at said side of said head when said spindle is locked in place and rotating to above said top of said head for pulling said locating bolt out of said stepped hole of said connector by hand.



- a continuous loop direct drive means comprising a plurality of alternating spacers and links which are connected by a continuous cable which extends through each of said links and spacers;
 - a first drive gear and a second drive gear, each comprising an orifice about a circumference thereof which is of sufficient width to allow protrusion there through of the spacers of said direct drive means and in which are defined a plurality of voids of sufficient size to allow protrusion there through of the links of said direct drive means, said voids located around said circumference in such manner that each link of said direct drive means enters one void as said direct drive means passes through each of said drive gears; and
 - a housing in which said first drive gear and said second drive gear are present;
- wherein said direct drive means provides communication between said first drive gear and said second drive gear, and wherein a drive means causes rotation of said first drive gear and said direct drive means causes, in turn, rotation of said second drive gear.

5,586,473

INTEGRATED NEEDLE FOR PERMANENT PIGMENT APPLICATOR

Kuei C. Chou, Taipei, Taiwan, assignor to Mei-Chi-Na Beauty International, Inc., Irvine, Calif.

Filed Jul. 20, 1994, Ser. No. 277,677

The portion of the term of this patent subsequent to Jul. 26, 2013, has been disclaimed.

Int. Cl.⁶ B43K 5/00

U.S. Cl. 81—9.22

22 Claims



1. An integrated needle for use with a permanent pigment applicator device having a needle coupler that is coupled to a needle drive mechanism, the integrated needle comprising: a needle having an elongated shaft portion and a head at a top end; and an attachment piece that receives the needle and is detachably and coaxially coupled to the needle coupler for detachment after each use, wherein the attachment piece includes a head recess that holds the needle head, thereby preventing longitudinal movement of the needle head in the needle chamber; wherein the head of the needle is hooked and the head recess is adapted to receive the hooked head of the needle and hold the needle head against longitudinal movement.

5,586,474

TORQUE TRANSFER TOOL

David R. Lund, Charleston, S.C., assignor to Victory in Jesus Ministries, Inc., Summerville, S.C.

Continuation-in-part of Ser. No. 75,787, Jun. 14, 1993, abandoned. This application Aug. 1, 1994, Ser. No. 284,080

Int. Cl.⁶ B25B 17/00

U.S. Cl. 81—57.3

30 Claims

1. A torque transfer device, comprising:

RATCHETING TYPE TOOL HAVING FREE WHEELING SLEEVE TO FACILITATE USE


Jeffrey W. Wenner, 520 Singley Ave., Runnemede, N.J. 08078

Filed Feb. 7, 1995, Ser. No. 385,108

Int. Cl.⁶ B25B 13/46; 23/16

U.S. Cl. 81—60

6 Claims



1. Hand tool comprising: an annular-shaped hollow main body; an elongated torquing handle integral with said main body having a hollow interior portion and extending substantially at right angles to a longitudinal axis of said hollow main body; adjustable ratcheting means arranged within a cavity in said main body adjacent to said torquing handle; an operating rod extending along the hollow interior of said main body and having an upper end joined to said ratcheting means; means in said main body for permitting substantially free rotation of said operating rod relative to said main body while maintaining a longitudinal axis of said operating rod substantially coaxial with a longitudinal axis of said main body; said main body having an open end remote from said torquing handle; coupler means for releasably coupling tool tips to a lower end of said operating rod, said tool tips extending through said open end;

an elongated, cylindrical-shaped guide sleeve being rotatably mounted about an outer periphery of said main body; and said main body including means for rotatably mounting said sleeve to said main body while preventing movement of said sleeve in a direction of said longitudinal axis, enabling said hand tool to be rotated by said torquing handle while said guide sleeve is gripped by an operator's hand to maintain the hand tool in alignment with a member to be rotatably driven by the hand tool;

said main body is divided into a first body portion having a first axial length and a second body portion having a second axial length greater than said first axial length releasably detachable to said first body portion;

said operating rod being divided into a first operating rod portion having a first axial length and a second operating rod portion of a second axial length greater than the axial length of said first operating rod portion;

said first operating rod portion being coupled to said ratcheting means; and

second coupler means for releasably coupling said first operating rod portion to said elongated operating rod portion.

5,586,477

BAR STOCK FEEDER METHOD AND APPARATUS HAVING SEPARABLE GUIDE TUBE SECTIONS

Kirt M. Babuder, Euclid; Douglas A. Joseph, Concord Township; Donald Pistor, Willoughby Hills, and L. Joseph Stupica, Euclid, all of Ohio, assignors to Devlieg-Bullard, Inc., Westport, Conn.


Continuation of Ser. No. 107,946, Aug. 17, 1993, abandoned.

This application Nov. 13, 1995, Ser. No. 557,379

Int. Cl.⁶ B23B 15/00

U.S. Cl. 82—126

19 Claims



1. Apparatus for aligning and feeding bar stock to a head stock of a multiple spindle lathe, said apparatus comprising:

a plurality of parallel guide tubes for supporting pieces of bar stock for movement toward the head stock, each of the parallel guide tubes comprising a first elongated tube section and a second elongated tube section separable from the first elongated tube section along a plane transverse to a longitudinal axis of the guide tube to allow insertion of the bar stock into one of the guide tubes and a seal for sealing each tube at an interface between the first and second elongated tube sections;

a plurality of piston assemblies, each fitted to slide inside a respective one of said guide tubes for engaging one end of a corresponding piece of said bar stock and pushing said piece toward said head stock;

fluid supply means for delivering fluid under pressure to the inside of said guide tubes for moving said piston assemblies; a first support member and a second support member separable from the first support member, the first section of each of the guide tubes supported in the first support member and the second section of each of the guide tubes supported in the second support member, one of said first and second support members being moved with respect to the other support member to separate the first and second sections of all of said guide tubes as a group to permit reloading of bar stock into any one of the first sections of said tubes with said piston assemblies being in a retracted position within the second sections of their respective guide tubes.

5,586,478

CENTERING DEVICE HAVING WORK REST CONTROL RESPONSIVE TO CARRIAGE MOVEMENT

Teruo Hoshino, Gifu-ken, Japan, assignor to Dainichi Kinzoku Kogyo Co., Ltd., Osaka, Japan

Division of Ser. No. 237,149, May 3, 1994, Pat. No. 5,517,886.

This application Mar. 20, 1996, Ser. No. 618,565

Int. Cl.⁶ B23B 31/00; B23Q 7/00; 3/16

U.S. Cl. 82—133

8 Claims

1. A centering device for use with a lathe having a bed, a head stock and a tail stock for holding a work therebetween, a carriage reciprocally movable in a longitudinal direction of the bed, and a tool box having a cutting tool mounted thereon, comprising:

a plurality of work rests disposed along the longitudinal direction of the bed, each of said work rests being movable

5,586,476

PROCESS AND DEVICE FOR MACHINING BARS, TUBES OR TUBE BLANKS

Karl-Joseph Esser, Mönchengladbach, Germany, assignor to Mannesmann Aktiengesellschaft, Düsseldorf, Germany


Filed May 10, 1995, Ser. No. 438,348

Claims priority, application Germany, May 10, 1994, 44 16 771.7


Int. Cl.⁶ B23B 5/08; 5/12

U.S. Cl. 82—1.11

11 Claims



1. A process for machining an elongate work piece, comprising the steps of: holding the work piece in a non-rotatable manner, cutting the work piece on its periphery and along its length with a metal cutting device including at least one die having cutters; and simultaneously continually moving the die and the work piece relative to one another in a longitudinal direction of the work piece, the cutting step including rotating two directly adjacent dies concentrically around the work piece on two different planes that are inclined toward a common longitudinal axis of the work piece in directions offset to one another by 90 and simultaneously machining two areas of the work piece surface that are located opposite to one another with the cutters.



between a first position for supporting the work and a second position spaced from the work; and control means associated with said work rests for controlling movement of each of said work rests between said first position and said second position in response to the movement of said carriage; each of said work rests including piston-cylinder means having a piston operable by a pressurized fluid controlled by said control means to be vertically moved between said first position and said second position; said control means being operable to control the pressurized fluid of said piston in such a manner that an amount of the pressurized fluid is reduced to lower the moving speed of said piston when said piston is moved from said second position to a position adjacent said first position.

5,586,479

CUTTING APPARATUS FOR CUTTING AN IMAGE FROM A RECEIVING SHEET


Carl W. Roy, Spencerport, and Paul E. Tschiderer, Geneseo, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Mar. 10, 1993, Ser. No. 29,257

Int. Cl.⁶ B23Q 15/26; B26D 5/20; 5/38; G01D 15/00

U.S. Cl. 83—74

4 Claims



1. Cutting apparatus capable of cutting a rectangular image, skewed relative to a receiver sheet on which the image is located, from the receiver sheet such that edges of the image are essentially parallel with respective edges of the receiver sheet, comprising:

a first cutter;
a sensor device for detecting an edge of an image located on a receiving sheet;
means, responsive to said sensor device, for aligning said first cutter and said edge of said image such that said first cutter can cut said receiver sheet essentially parallel to said edge of said image;
means for edge registering an edge of the receiving sheet cut by said first cutter; and
a second cutter positioned to cut said receiving sheet perpendicular with said edge cut by said first cutter.

5,586,480

PNEUMATIC MOTOR


Richard K. Gardner, Montpelier, Ohio, assignor to Ingersoll-Rand Company, Woodcliff Lake, N.J.

Filed Feb. 20, 1996, Ser. No. 604,147

Int. Cl.⁶ F01B 7/20; F15B 11/08

U.S. Cl. 91—169

12 Claims



1. A pneumatic motor, comprising:

- a motor body having a piston chamber with opposed chamber ends, at least two valve chambers, inlet means for flowing a pressurized fluid into the piston chamber and each of the at least two valve chambers, outlet means provided in the housing for exhausting the pressurized fluid from the piston chamber and each of the at least two valve chambers;
- a three-way valve member adapted to be located in each of the at least two valve chambers, said valve members having at least one open end and at least one port formed along the valve member body;
- at least one spool member located in one of said valve chambers, each spool member having a first end adapted to be located in the open end of the valve member, said spool members adapted to be movable in a first direction relative to the valve member to permit pressurized fluid to be supplied to the piston chamber and also in a second direction relative to the valve member to permit the pressurized fluid in the piston chamber to be exhausted from the chamber; and
- a piston movable in a reciprocating manner in the main chamber in response to movement by the spools relative to the three-way valve members.

5,586,481

APPARATUS FOR PREVENTING DISENGAGEMENT OF SEAL MEMBER IN A BOOSTER

Makoto Watanabe, Saltama-ken, Japan, assignor to Jidosha Kiki Co., Ltd., Tokyo, Japan


Filed Dec. 20, 1994, Ser. No. 359,575

Claims priority, application Japan, Jan. 28, 1994, 6-026085

Int. Cl.⁶ F15B 9/10

U.S. Cl. 91—376 R

9 Claims



1. A booster comprising:

- a shell including a stepped tubular portion which extends axially rearward from a rear end face of the shell and has a step formed therein, the stepped tubular portion having a greater diameter forwardly of the step;
- a reciprocable valve body disposed within the shell and including a tubular terminal end which projects axially rearward through the stepped tubular portion;
- a bearing disposed within the portion of the stepped tubular portion which has the greater diameter for slidably supporting the tubular terminal end of the valve body;
- an annular seal member disposed within the portion of the stepped tubular portion having the greater diameter so as to be held sandwiched between the step and the bearing in sealing engagement with the tubular terminal end to provide a seal between the stepped tubular portion and the tubular terminal end of the valve body, the seal member having an end face, and the bearing having an end face facing toward the end face of the seal member in a mutually opposing relation, each of the mutually opposing end faces being defined by a radially outer region and a radially inner region; and
- means for preventing disengagement of the seal member comprising a projection portion disposed on one of the mutually opposing end faces of the seal member and the bearing in the radially outer region of said one of the mutually opposing end faces for engagement with the other of the mutually opposing end faces, the radially inner regions of the mutually opposing end faces being circumferentially continuously spaced apart and out of contact with one another by a circumferentially continuous space radially extending inwardly from the radially inner side of said projection portion to the radially inner edge of at least one of said opposing end faces.

5,586,482

TWO-STAGE FLUIDIC ACTUATOR

W. Burt Leonard, Rt. 1, Box 254, Waller, Tex. 77484

Filed Aug. 25, 1995, Ser. No. 519,540


Int. Cl.⁶ F15B 11/036

U.S. Cl. 91—519

5 Claims

5. A two-stage fluidic actuator, comprising:

- a dual-chamber cylinder body, said cylinder body including a power chamber having a first length that opens into a superjacent coaxial extender chamber having a second length that is greater than said first length, the internal diameter of said extender chamber being a pre-selected fraction of the internal diameter of said power chamber;
- a power piston mounted for reciprocating motion in said power chamber, a reduced-diameter portion of the power piston reaching into a portion of said extender chamber, the power



piston defining posterior, intermediate and anterior faces and having a longitudinal bore therethrough;
an extender piston mounted in said extender chamber, said extender piston including a piston rod and adapted for executing reciprocating strokes of desired incremental lengths independently of said power piston, said extender piston having posterior and anterior faces, the posterior face of the extender piston being exposed to the anterior face of the power piston;
a spring-loaded throttling plunger slidably mounted in said longitudinal bore for metering the volumetric flow rate of pressurized fluid therethrough against the posterior face of said extender piston as a function of the incremental stroke length thereof;
a first port in said cylinder body for providing fluid communication with the posterior face of the power piston;
a breather port in said cylinder body in fluid communication with the intermediate face of the power piston; and
a second port in said cylinder body for providing fluid communication with the anterior face of the extender piston.

5,586,483

PISTON AND ROD ASSEMBLY


Andrew L. Sine, Lawrenceville, Pa., assignor to Dresser-Rand Company, Corning, N.Y.

Filed Aug. 23, 1995, Ser. No. 518,630

Int. Cl.⁶ F16J 1/00

U.S. Cl. 92—255

6 Claims



1. A piston and rod assembly, comprising:

a hollow piston, having (a) an axis, and (b) an opening formed in one axial end thereof, with (c) an annular ledge rimming said opening; wherein
 said ledge has a given plurality of tapped bores formed therein; and
 an annular hub, also having the same, given plurality of bolt holes formed therein;
 said hub having a circumferential surface which pilotingly receives said piston opening thereabout; and
 fasteners set in said holes and fastened in said bores securing said hub to said ledge;
 a piston rod, having a prominent shoulder formed thereon, and being threaded at one end thereof; wherein
 said hub has (a) a throughgoing bore which pilotingly receives said piston rod therein, and (b) a rim for seating thereof against said shoulder; and
 a nut threadably torqued onto said one end of said rod and fastening said rim of said hub against said shoulder; wherein said hub has a plurality of radially disposed, rigidizing ribs.


5,586,484

EXPRESSO COFFEE MAKER

Pietro Piazza, 11 Catherine Dr., Prospect, Conn. 06712
 Filed Oct. 25, 1994, Ser. No. 344,847

Int. Cl.⁶ A47J 31/24

U.S. Cl. 99—287



1. An improved espresso coffee maker comprising an interlocking assembly of four components, the first of said components being an upper brewed coffee holder, the second of said components being a lower water heating container, the third of said components being a coffee grounds holder located between said upper brewed coffee holder and said lower water heating container, the fourth component being a piston, said piston being located within said coffee grounds holder to form a coffee brewing assembly, the external dimensions of said piston closely complying with the internal dimensions of said coffee grounds holder, said coffee brewing assembly having a hollow stem which extends from its base; said improved espresso coffee maker being formed by threadably assembling said upper brewed coffee holder, said coffee brewing assembly and said lower water heating container to effect an hermetic seal between said components.

5,586,485

COFFEE MACHINE


Heinrich Baumann, Solingen, Germany, assignor to Robert Krups GmbH & Co. KG, Solingen, Germany
 PCT No. PCT/EP94/02685, § 371 Date Apr. 10, 1995, § 102(e)
 Date Apr. 10, 1995, PCT Pub. No. WO95/05109, PCT Pub. Date Feb. 23, 1995

PCT Filed Aug. 11, 1994, Ser. No. 416,694
 Claims priority, application Germany, Aug. 12, 1993, 9312009 U

Int. Cl.⁶ A47J 31/10

U.S. Cl. 99—295

5 Claims



1. In a coffee machine with a water reservoir located in a main housing, a heating device having electric regulating devices, a beverage collecting vessel which can be placed on a housing base, a coffee brewing housing which is arranged above the beverage collecting vessel, mounting means for connecting said coffee brewing housing to said main housing to enable a swiveling of said coffee brewing housing out of the main housing and manually actuated hold-back means for securing said coffee brewing housing in a working position at said main housing, a spring being provided for biasing said hold-back means towards a locking position, the improvement comprising:

a push bar;
 said hold-back means being coupled with said push bar which acts on the coffee brewing housing in the swiveling out direction; and
 means at the main housing for guiding said push bar.

5,586,486

AUTOMATED DEEP FRYER

John S. Nitschke, Perrysburg, and Daniel B. Kuhary, Whitehouse, both of Ohio, assignors to Vend-It Corporation, Perrysburg, Ohio


Continuation-in-part of Ser. No. 190,866, Feb. 1, 1994, Pat. No. 5,367,949. This application Nov. 23, 1994, Ser. No. 344,151

Int. Cl.⁶ A47J 37/00; 37/12

U.S. Cl. 99—330

56 Claims

1. An automated deep fryer comprising:
 a refrigerated food storage compartment connected with a portion controller and food dispenser;
 a cooking chamber isolated from the storage compartment, the cooking chamber including a food basket mounted for movement to a variety of preselected positions;
 a control for programmed dispensing, preparation and serving of a preselected portion of food in response to an operator's input; and
 an air purifier connected with the cooking chamber, said air purifier including
 a fan for extracting gases from the cooking chamber, and
 a cold plate having a generally smooth surface over which the fumes from the cooking chamber travel, the cold plate being interposed between the fan and the cooking chamber.



5,586,487

PASTA PERCOLATOR


Francis E. Marino, 9 Hazeltine Rd., Upton, Mass. 01568

Filed May 22, 1995, Ser. No. 446,249

Int. Cl.⁶ A47J 27/04; 27/06; 27/18; 27/21

U.S. Cl. 99—330

17 Claims



1. An electrical pasta cooking device comprising:
 an electrical heater,
 a first compartment for containing water in thermal communication with said electrical heater, and having a lower water level and a first upper water level,
 a second compartment for containing pasta, having a cooking level and having a bottom surface disposed below said cooking level and above said first upper water level, said bottom surface including one or more drainage holes therethrough, said one or more drainage holes adapted to allow a down-flow of water therethrough,
 a conduit for providing fluid communication from said first compartment at said lower water level to said second compartment above said cooking level,
 a third compartment for containing water and having a second upper water level disposed below said bottom surface, and adapted for receiving water from said drainage holes,
 a control to establish a cooking period, and to energize said heater during said cooking period and to reduce energization of said heater after said cooking period, and wherein
 water within said first compartment is heated by said energized heater during said cooking period,
 said heated water up-flows by percolation from said first compartment, through said conduit and into said second compartment above said cooking level, cooks pasta within said second compartment, and down flows through said drainage holes to said third compartment after said cooking period to drain said pasta.

5,586,488

PORTABLE PIZZA OVEN


Simon Y. Liu, West Bend, Wis., assignor to Americorp Inc., West Bend, Wis.

Filed Oct. 3, 1995, Ser. No. 538,751

Int. Cl.⁶ A47J 37/00; 37/08

U.S. Cl. 99—331

21 Claims



1. A portable pizza oven comprising
 a fixed upper casing,
 a fixed lower casing, the upper and lower casings defining therebetween an opening,
 an upper heater assembly located within and fixed to the upper casing,
 a lower heater assembly located within and fixed to the lower casing, so as to define a cooking chamber which is located between the heater assemblies and which is accessible via the opening, and
 a pan assembly insertable into and removable from the cooking chamber, the pan assembly including a tray and a handle fixed to the tray, such that, when the pan assembly is inserted into the cooking chamber, the handle closes the opening, thereby closing the cooking chamber,
 wherein said upper casing includes a circular dome-like portion, a rectangular portion, and vertical side walls extending downwardly from the circular and rectangular portions, and wherein said lower casing includes a circular dome-like portion, a rectangular portion, and vertical side walls extending upwardly from the circular and rectangular portions of the lower casing, the side walls of the upper and lower casings defining therebetween the opening.

5,586,489

METHOD AND APPARATUS FOR THE PREPARATION OF FOWL


Robert L. Fraga, 886 Cardozo, Tulare, Calif. 93274

Filed Oct. 4, 1995, Ser. No. 539,309

Int. Cl.⁶ A47J 37/04; A22C 7/00


U.S. Cl. 99—419

13 Claims



1. Heat transfer member for the preparation of fowl which has been dressed out in such a manner as to leave an interior cavity defined by an interior wall, comprising:
 a heat transfer member; said heat transfer member having a longitudinal axis; said heat transfer member including a bulbous element formed about said longitudinal axis in asymmetrical fashion such that the bulbous element is formed with an exterior surface defining a shape which substantially conforms to the shape of the interior cavity of the fowl, said exterior surface of said heat transfer member adapted to make

heat transfer contact with substantially all of the interior wall of the cavity of the fowl, a heated environment; means within said heated environment for the controlled application of heat to said heat transfer member so as to cause the heat to be uniformly transmitted to the interior wall of the fowl to thereby initially sear in juices and thereafter continue to apply heat thereto to cook the fowl from the interior, as well as the exterior, thereof.



5,586,490
COOKING DEVICE


Shukri T. Saman, 4712 David Dr., Kenner, La. 70065

Filed Jun. 30, 1995, Ser. No. 497,389

Int. Cl.⁶ A47J 37/04

U.S. Cl. 99—421 R

12 Claims



1. A cooking device comprising:
an insulated housing defining a cooking cavity therein having a front opening;
a radiant heat source disposed within the cooking cavity and positioned adjacent a rear wall of said housing;
a rotating vertical support having a first end, centered in said housing;
a plurality of rigid elongated skewers aligned along the length of said vertical support and disposed horizontally therethrough for holding various items of food to be cooked, the food items traveling in a circular path about the longitudinal axis of said rotating vertical support said skewers having a first and second end conically tapered to a point; and
mechanized means detachably connected to said first end of said vertical support for rotating said vertical support about its longitudinal axis.

5,586,491
DISPOSABLE BARBECUE GRILL SHIELD

Robert J. Diller, and Barbara J. Diller, both of 800 Lagunita Dr., Soquel, Calif. 95073

Filed Apr. 28, 1995, Ser. No. 431,311

Int. Cl.⁶ A47J 27/00

U.S. Cl. 99—450

4 Claims

1. A disposable shield for covering an existing barbecue grill comprising a flexible metal foil in the form of a roll having edges with a repeating pattern of rectangular vents, and a score line spaced inwardly from the edges of the roll to allow for manual upturning of the edges against a side of the grill after a desired length of foil is removed from the roll.

5,586,492
APPARATUS FOR THE WETTING OF CEREALS WITH A LIQUID


Dieter O. Graef, Neumuehle, D-35633 Lahnu-Dorlar, Germany

Division of Ser. No. 193,010, Feb. 17, 1994, Pat. No. 5,512,310. This application Sep. 29, 1995, Ser. No. 536,186
Claims priority, application Germany, Aug. 17, 1991, 41 27 290.0

U.S. Cl. 99—516

Int. Cl.⁶ B02B 3/00

27 Claims



1. An apparatus for the wetting of a mixture of cereals with liquid, comprising a shaking apparatus which comprises at least one pipe having substantially smooth walls, the at least one pipe is arranged with a horizontal or approximately vertical axis and is connected to at least one motor setting the pipe in shaking movement, wherein said at least one motor and said at least one pipe are arranged for shaking said at least one pipe with sufficient force to impart acceleration forces to at least a portion of said cereal/liquid mixture, which acceleration forces provide a substantially uniform wetting of said cereals and a substantially uniform penetration of the liquid from the husk into the inside of the cereal.

5,586,493
PAPER RECYCLING RACK

Marjorie N. McEntee, 3350 Airport Rd. #42, Allentown, Pa. 18103


Filed Jan. 3, 1996, Ser. No. 580,977

Int. Cl.⁶ B65B 27/08

U.S. Cl. 100—34

14 Claims

1. A paper recycling rack providing for the bundling of loose papers and storage of bundled papers therein, said rack comprising:
a lower paper storage area comprising a generally rectangular floor panel having first through fourth upper platform supports extending upwardly therefrom and defining four corners for said floor panel and said rack;



a pair of elongate strips of resilient material oppositely disposed beneath said floor panel;
separate first through fourth upper platforms each extending inwardly from a respective one of said upper platform supports, with said upper platforms disposed in a rectangular array and defining first and second orthogonally disposed binding slots therebetween;
said upper platforms each having an opening therebelow, with each said opening communicating with a respective one of said binding slots and providing for the passage of binding material therethrough, and;
first through fourth discontinuous peripheral upper paper retaining walls each extending upwardly from said upper platforms, with each of said walls including a gap therein corresponding to and communicating with a respective one of said binding slots and providing for the passage of binding material therethrough and about any papers resting upon said upper platforms, whereby:
papers are placed in a generally rectangular stack upon said upper platforms and binding material is secured orthogonally about the stack by means of access provided by said openings below said upper platforms, said binding slots, and each said gap in said upper paper retaining walls, with bound stacks being placed within said lower paper storage area for transfer to a recycling facility.

5,586,494
SWIVELLING PISTON PRESS

Jürgen Simons, Wolfenbüttel, Germany, assignor to Welger GmbH, Wolfenbüttel, Germany


Filed May 26, 1995, Ser. No. 451,578

Claims priority, application Germany, May 26, 1994, 9408619 U

Int. Cl.⁶ B30B 9/30; 1/32

U.S. Cl. 100—189

5 Claims



1. A swivelling piston press for forming bales of material, said swivelling piston press comprising:

a housing;
compression channel means formed in said housing for receiving the material to be baled;
a compression piston supported in said compression channel means for pivotal movement about an axis into an extended position of the compression piston during a return stroke thereof for enabling feeding of the material to be baled into said compression channel means, and into a retracted position thereof during a compression stroke thereof for compressing the material received in said compression channel means to form a bale;
a piston-cylinder unit for pivoting said compression piston between the extended and retracted positions thereof and including a cylinder pivotally supported on said compression channel means and a piston rod connected to said compression piston;
wherein said piston rod is tension-stressed during the compression stroke of said compression piston and, in the retracted position of said compression piston, forms an acute angle with a connection line connecting the pivotal axis of said compression piston with a connection point of said compression piston with said piston rod.

5,586,495
TRANSFER PRESS

Kazuo Ogawa, and Naoki Ikeoka, both of Komatsu, Japan, assignors to Kabushiki Kaisha Komatsu Seisakusho, Tokyo, Japan


Filed Dec. 28, 1992, Ser. No. 997,196

Claims priority, application Japan, Dec. 27, 1991, 3-358319; Jul. 15, 1992, 4-187759

Int. Cl.⁶ B30B 15/30; 15/04

U.S. Cl. 100—207

21 Claims




1. In a transfer press having a plurality of workstations through which workpieces are sequentially fed in a first workpiece feed direction from workstation to workstation for accomplishing a plurality of pressing operations, the improvement comprising the combination of:

a body having components comprising: a bed, uprights provided vertically upon said bed, a pair of supporting beams provided upon said uprights and disposed in spaced relationship with each other in a horizontal direction perpendicular to the direction in which a workpiece is fed, and a plurality of pressing units each of which is independently provided for a respective one of said plurality of pressing operations, said components being readily dividable from each other;


a plurality of crowns;
a plurality of slides;
each of said plurality of pressing units including a respective one of said plurality of crowns, which is removably mounted upon said supporting beams, and a respective one of said plurality of slides, which is positioned for movement with respect to the associated crown.

5,586,496
DOT LINE PRINTER WITH ADJUSTED DOT POSITIONS FOR CANCELING SHEET FEED ERROR
 Makoto Shinohara, Yoshikane Matsumoto, and Shigenori Suetatsu, all of Hitachinaka, Japan, assignors to Hitachi Koki Co., Ltd., Tokyo, Japan
 Filed Nov. 28, 1994, Ser. No. 348,887
 Claims priority, application Japan, Nov. 26, 1993, 5-297007
 Int. Cl.⁶ B41J 2/255
 U.S. Cl. 101—93.04 9 Claims



1. A dot line printer comprising:
 a hammer bank accommodating a plurality of print hammer which have pins for making impressions of dots on a sheet of paper, said pins of said plurality of print hammers having respective home positions displaced at an equi-distant pitch in a first direction perpendicular to a second direction in which said hammer bank reciprocates so that N dot lines are printable with each of forward and backward movements of said hammer bank where N is an integer equal to or greater than two, wherein at least one of said pins for printing N dot lines is shifted from its home position to compensate for an error causing impressions of dots to be made at an unequal pitch in the first direction as a result of consecutive forward and backward movement of said hammer bank.

5,586,497
STENCIL PRINTING MACHINE WITH STENCIL TENSIONING MEMBER
 Shingo Shimada, Tokyo, Japan, assignor to Riso Kagaku Corporation, Tokyo, Japan
 Filed Jun. 23, 1995, Ser. No. 494,025
 Claims priority, application Japan, Jul. 4, 1994, 6-152353
 Int. Cl.⁶ B41L 13/04
 U.S. Cl. 101—128.4 7 Claims




1. A stencil printing machine, comprising:
 a cylindrical printing cylinder around an outer peripheral surface of which a perforated stencil sheet can be wrapped;
 a stencil sheet storing section for holding a blank stencil;
 a stencil sheet perforating means for perforating a stencil sheet fed from said stencil sheet storing section;

a stencil sheet cutting means disposed between said stencil sheet perforating means and said printing cylinder, for cutting a perforated stencil sheet;
 a stencil sheet stocking section disposed between said stencil sheet perforating means and said stencil sheet cutting means, for stocking a perforated stencil sheet;
 a single long member disposed, inside said stencil sheet stocking section, in parallel with a direction of width of said stencil sheet beneath said stencil sheet stocked inside said stencil sheet stocking section, and movable between an upper limit position and a lower limit position;
 a driving mechanism for moving said long member up and down; and
 a stencil sheet feed means for feeding said perforated stencil sheet from said stencil sheet stocking section to said stencil sheet cutting means.

5,586,498
DUPLICATE COPIES FROM A PRINTER OR COPIER
 Dan Kikinis, Saratoga, Calif., assignor to Elonex I.P. Holdings, Ltd., London, England
 Division of Ser. No. 291,987, Aug. 17, 1994, This application Oct. 26, 1995, Ser. No. 548,848
 Int. Cl.⁶ B41M 1/12 3 Claims

U.S. Cl. 101—127




1. A method of priming two copies of a document in a single pass through a printer, comprising the steps of:
 (a) making a form comprising two layers of flat printing stock, one layer having a pattern of openings exposing area on the other layer;
 (b) passing the form through a printer;
 (c) printing a copy of the document by applying printing ink to the side of the form having the pattern of openings, wherein some of the ink remains on said side of the form to form one copy and the remainder of the ink passes through the openings to mark the other layer; and
 (d) separating the two layers, providing two copies of the document printed.

5,586,499
METHOD FOR ELIMINATING GEAR TRAIN BACKLASH IN A DRIVE FOR A MULTI-COLOR SHEET-FED PRINTING MACHINE HAVING FACE PRINTING AND PERFECTING MODES
 Hendrikus Beaumont, Eupen, Belgium; Hanns-Otto Haas, Heusenstamm, Germany; Holger Wiese, Obertshausen, Germany, and Bernd Lindner, Heusenstamm, Germany, assignors to MAN Roland Druckmaschinen AG, Germany
 Filed Sep. 29, 1995, Ser. No. 536,938
 Claims priority, application Germany, Sep. 30, 1994, 44 35 011.2 17 Claims


U.S. Cl. 101—211

1. A method for eliminating gear train backlash in the drive of a sheet-fed printing machine when changing the printing mode of the machine between face printing and perfecting or vice versa, the



printing machine having a gear train, a longitudinal drive shaft, and at least two input drives for connecting the longitudinal drive shaft to the gear train, the method comprising the steps of:
 operating the printing machine to assume a predefined drive position for changing the printing mode;
 releasing a clutch in the longitudinal shaft disposed between the at least two input drives to separate the drive shaft into two segments;
 fixing the position of the gear train;
 separating the gear train into a first section and a second section by releasing a separation device disposed between the two sections of the gear train;
 rotating the second section of the gear train to a new position associated with the new printing mode while maintaining the first section of the gear train in the fixed position;
 reconnecting the first and second sections of the gear train by engaging the separation device;
 releasing the first section of the gear train for rotation;
 rotating a first segment of the longitudinal shaft relative to a second segment of the longitudinal shaft; and
 engaging the clutch in the longitudinal shaft to reconnect the two segments of the drive shaft with the first segment rotated relative to the second segment to apply a torque to compensate for backlash conditions in the gear train.


5,586,500
STENCIL STAMP
 Hiroshi Takami, Yoshihiro Yasui, and Takashi Okumura, all of Nagoya, Japan, assignors to Brother Kogyo Kabushiki Kaisha, Nagoya, Japan
 Filed Mar. 10, 1995, Ser. No. 401,688
 Claims priority, application Japan, May 19, 1994, 6-105222
 Int. Cl.⁶ B41F 31/00 20 Claims



1. A stencil stamp, comprising:
 a handgrip;
 a stencil stamp block holding member connectable to said handgrip; and
 a plurality of stencil stamp blocks, said stencil stamp block holding member having means to simultaneously detachably

mount a plurality of stencil stamp blocks on said stencil stamp block holding member, each stencil stamp block comprising:
 a base member,
 an ink-bearing member mounted on said base member, and
 a thermal stencil sheet having a stamping central portion, each said stamping central portion covering said ink-bearing member, the remainder of said thermal stencil sheet which surrounds said stamping central portion covering said base member, said stamping central portion having a plurality of apertures formed therein, ink from said ink-bearing member being passable through said plurality of apertures during a stamping operation to form an ink image on a recording sheet.

5,586,501
DISAPPEARING INK MARKING SYSTEM
 Bartolome Burguera, 1103 8th Ave. South West, Rochester, Minn. 55902, and Richard K. Stanzak, P.O. Box 195, Bath, N.C. 27808
 Filed Oct. 25, 1995, Ser. No. 547,947
 Int. Cl.⁶ B41M 1/40 18 Claims



1. A disappearing ink marking system adaptable to a sole of a user, comprising:
 a) an upper layer having an upper layer outer surface and an upper layer inner surface;
 b) an intermediate layer having an intermediate layer upper surface affixed to said upper layer inner surface and an intermediate layer lower surface, said intermediate layer containing an intermediate layer longitudinally disposed aperture;
 c) a lower layer having a lower layer outer surface, a lower layer inner surface affixed to said intermediate layer lower surface, said lower layer containing at least one lower layer aperture;
 d) a reservoir tube partially disposed within said intermediate layer longitudinally disposed aperture and containing a plurality of reservoir tube apertures which are in fluid communication with said intermediate layer;
 e) a disappearing ink flowable through said reservoir tube; and
 f) at least one image block having an image block upper surface removably affixed to said lower layer lower surface, said at least one image block being in fluid communication with said at least one lower layer aperture so that said disappearing ink flowing through said reservoir tube escapes through said plurality of reservoir tube apertures and enters said intermediate layer and is absorbed therein where upon when pressure is applied to said intermediate layer and said at least one image block said disappearing ink is forced from said intermediate layer through said at least one lower layer aperture and into said at least one image block which in turn causes said at least one image block to disperse said disappearing ink and leave a temporary image.

5,586,502

APPARATUS FOR INSTALLING AND REMOVING RAIL CLIPS


Robert M. Weber, Ingleside, Ill., assignor to Nordco Inc., Milwaukee, Wis.

Filed Mar. 14, 1995, Ser. No. 403,635

Int. Cl.⁶ E01B 29/24

U.S. Cl. 104—17.2

13 Claims



1. A rail clip installer configured for connection to a vehicle for installing transverse mount rail clips onto a rail, the rail having a gage side and a field side, said rail clip installer comprising:
 - at least one clip applicator;
 - at least one actuator having a substantially vertical reciprocating output shaft operably connected to said applicator for reciprocating said applicator relative to the rail; and
 - at least one guide rod operably connected to said actuator and being disposed between said actuator and the rail for guiding said reciprocation of said shaft, said rod being pivotally connected to said applicator for translating the substantially vertical motion of said output shaft into substantially horizontal reciprocating motion of said applicator transverse to the rail.

5,586,503

PASSENGER RESTRAINT SYSTEM

Don W. Rehorn, 140 Calle San Simon, Santa Fe, N.M. 87505


Filed Jun. 7, 1995, Ser. No. 472,324

Int. Cl.⁶ B61B 11/00

U.S. Cl. 104—241

21 Claims

1. A passenger restraint system for restraining passengers in an elevated, open-air vehicle, comprising:
 - a safety bar mounted to the vehicle and pivotable between vertical and angled positions;
 - restraining means fixed to the safety bar and operable to move between restraining and non-restraining positions;
 - movable means movable along the safety bar and operable to move the restraining means between restraining and non-restraining positions;
 - means for securing the restraining means to the safety bar while in its restraining position; and
 - transmission means connected to the safety bar for moving the movable means.



5,586,504

DUAL-KEEL ELECTRODYNAMIC MAGLEV SYSTEM


Jianliang He, Naperville; Zhan Wang, Downers Grove; Donald M. Rote, Lagrange; Howard T. Coffey, Darien; John R. Hull, Westmont; Thomas M. Mulcahy, Western Springs, and Yigang Cai, Woodridge, all of Ill., assignors to The United States of America as represented by The United States Department of Energy, Washington, D.C.

Filed May 11, 1995, Ser. No. 438,829

Int. Cl.⁶ B60L 13/04

U.S. Cl. 104—282

7 Claims



1. A magnetic levitation, guidance and propulsion system for a vehicle having a base and adapted to travel over a roadbed comprising:
 - a pair of vertical keels axially aligned along the base of said vehicle;
 - a row of superconducting magnets integrally connected to and arranged lengthwise along each of said keels and oriented so that said magnets' poles are approximately perpendicular to a vertical plane formed by said keel;
 - a guideway affixed along said roadbed, said guideway having a pair of vertical slots longitudinally aligned to receive said vertical keels;
 - electromagnetic means affixed to opposing vertical sides of said vertical slots for interacting with said row of superconducting magnets to levitate, guide and propel said vehicle where both poles or double-sides of said superconducting magnets electromagnetically interact with said electromagnetic means when said means is activated to form two double-sided linear synchronous motors for propulsion.

5,586,505

LEVITATION SYSTEM USING PERMANENT MAGNETS FOR USE WITH TRAINS AND THE LIKE TYPE OF RIGHT-OF-WAY VEHICLES

Elberto Berdud, Orquidea No. 98, Santa Maria, Guaynabo, Puerto Rico


Continuation-in-part of Ser. No. 184,440, Jan. 21, 1994, Pat. No. 5,452,663, which is a continuation-in-part of Ser. No. 45,863, Apr. 14, 1993, Pat. No. 5,431,109. This application

Feb. 22, 1995, Ser. No. 392,247

Int. Cl.⁶ B60L 13/10

U.S. Cl. 104—283

13 Claims



1. A magnetic unit, comprising:
 - a first group of at least a first pair of permanent magnets comprising either ceramic magnets or ferrous magnets having like poles of said permanent magnets positioned adjacent each other;
 - a second group of at least a second pair of permanent magnets comprising either ceramic magnets or ferrous magnets having like poles of said permanent magnets positioned adjacent each other, said first and said second groups of said permanent magnets defining a channel therebetween;
 - at least a third pair of magnetically permeable members comprising malleable steel members, malleable iron members, or molded iron members, one of said third pair being respectively located between said adjacent surfaces of said pair of permanent magnets and located adjacent each outer surface of said pair of permanent magnets; and
 - means for securing said pair of magnetically permeable members and said pair of permanent magnets, thus to provide a said magnetic unit which concentrates its magnetic flux through said malleable steel members at opposed locations in said channel;
 - at least a third permanent magnet located in said channel, each pole of said third magnet being positioned adjacent an opposite magnetic pole of said first pair of permanent magnets at a surface of one of said magnetically permeable members, thus to maintain a stable positional relationship by the magnetic effect of the relationship among said first, second, and third permanent magnets.

5,586,506

BALL-AND-SOCKET COUPLING, PARTICULARLY FOR RAILWAY CARS

Harald Heubusch, Büchenbach, and Jörg Rösler, Feucht, both of Germany, assignors to AEG Schienenfahrzeuge GmbH, Hennigsdorf, Germany

Filed Dec. 12, 1995, Ser. No. 571,117


Claims priority, application Germany, Dec. 21, 1994, 9428230 U

Int. Cl.⁶ B61G 5/00

U.S. Cl. 105—3

7 Claims

6. The combination of a first railway car, a second railway car and two vertically spaced, axially aligned, upper and lower ball-and-socket couplings connecting the first and second railway cars with one another; each said ball-and-socket coupling comprising



- a U-shaped welded support frame having a base and first and second legs extending from said base; said first and second legs being spaced from one another and defining an open side of said frame opposite said base; said first leg forming a ball-holding pin and said second leg being attached to said first railway car;
- a ball traversed and carried by said ball-holding pin;
- a support bracket attached to said second railway car;
- a socket affixed to and carried by said support bracket; said ball nesting in said socket;
- a lid closing said open side of said frame; and
- securing means for releasably attaching said lid to said frame.

5,586,507

RAIL GUIDE WHEEL APPARATUS WITH DOUBLE OVERCENTER LINKAGE



Harry Madison, Memphis, Tenn., and Jeffrey L. Tilley, Glenwood, Iowa, assignors to Harco Corporation, Wormleysburg, Pa.

Filed Jul. 24, 1995, Ser. No. 585,946

Int. Cl.⁶ B61F 1/00

U.S. Cl. 105—215.2

17 Claims



1. A rail guide wheel apparatus comprising:
 - a first rail wheel;
 - a first rail arm having a wheel end on which the first rail wheel is rotatably mounted and a mount end;
 - a second rail wheel;
 - a second rail arm having a wheel end on which the first rail wheel is rotatably mounted and a mount end; and

a position adjustor operably connected to move each of the first and second rail wheels between rail positions whereat they may engage rails and road positions whereat they are removed from any road surface; and

wherein each of the first and second rail wheels is automatically secured against changing in either way between rail and road positions; and wherein the position adjustor includes a linkage structure movable between an overcenter rail state and an overcenter road state, each of the overcenter rail and road states securing the first and second rail wheels against changing between their rail and road positions; and further comprising: first and second wheel arms having the respective first and second rail wheels mounted on wheel ends thereof, each of the first and second wheel arms are pivotable about corresponding first and second wheel arm axes; at least one torque member operable to apply torque for moving at least one of the first and second wheel arms about the corresponding one of the first and second wheel arm axes; and wherein the linkage structure includes at least one linkage and one crank member pivotably connected thereto, the crank member rotating about a crank axis and the linkage directly connected to the torque member.

5,586,508

ADJUSTING DEVICE FOR A MATCHING TABLE

Klaus Bähr, Offenbach am Main, Germany, assignor to Heidelberger Druckmaschinen, Heidelberg, Germany


Filed Jan. 20, 1995, Ser. No. 375,967

Claims priority, application Germany, Jan. 20, 1994, 44 01 532.1

Int. Cl.⁶ A47F 5/12

U.S. Cl. 108—2

2 Claims



1. In combination with a matching table having a frame and a support for at least one copy to be matched, an adjusting device for reciprocatingly facilitating moving the support towards and away from an observer in an adjusting movement, comprising a guide for the adjusting movement provided in common for the support and the frame of the matching table, frictional retaining means defined at the support for releasably holding the support fast with respect to the frame, said frictional retaining means including a spring-loaded lock acting on said frame, and a tension band engaging said lock and tightenable for releasing said lock.


5,586,509
CARD TABLE FOOD, BEVERAGE, BIDDING BOX AND CONVENTION CARD HOLDING APPARATUS
Howard L. Mangold, 458 Sharon Dr., San Antonio, Tex. 78216, and Anita L. Mangold, 4026 Georgetown Rd., Blue Ash, Ohio 45236

Filed May 23, 1995, Ser. No. 447,396

Int. Cl.⁶ A47B 41/04

U.S. Cl. 108—28

12 Claims



1. An improved portable combination apparatus for mounting to the leg at the corner of a card table comprising:
 - a) platform means for receiving card game accouterments and refreshments, comprising a generally planar upper surface, a perimeter flange extending downwardly relative to said upper surface, at least one notch means formed in said platform to receive the corner of a card table and a horizontal stabilizing ledge extending from the perimeter flange at the notch in said platform;
 - b) at least one support brace means for supporting said platform in position proximate the card table;
 - c) at least one retaining clip means for releasably securing said support brace to said card table leg; and
 - d) a raised stabilizing ridge on said ledge, for in combination with said ledge and said perimeter flange at said notch, nesting the upper surface of said ledge and ridge combination with the lower surface of a card table proximate the support leg of said card table.

5,586,510

METHOD AND SYSTEM FOR CONTROLLING POLLUTANT EMISSIONS IN COMBUSTION OPERATIONS


R. Leon Leonard, Sacramento; Earl F. Bouse, Walnut Creek, and Anne T. McQueen, Huntington Beach, all of Calif., assignors to Cement Industry Environment Consortium, Riverside, Calif.

Filed Mar. 16, 1994, Ser. No. 213,718

Int. Cl.⁶ F23J 11/00

U.S. Cl. 110—345

20 Claims



1. A process for reducing pollutant emissions from a combustion operation comprising introducing particles of aqueous sludge at a point in a flue gas outlet of a combustion operation wherein a

temperature is approximately 1500° F. to approximately 1800° F., and wherein the sludge introduced in the combustion operation contains an amount of ammonia effective to reduce NO_x emissions, whereby pollutant emissions in outlet flue gases produced by the combustion operation are reduced.

5,586,511

METHOD AND APPARATUS FOR ASSEMBLY OF PILLOW-TOP MATTRESS COVERS



Michael R. Porter, Topsfield; Charles E. Mulcahey, Beverly, and John J. Kirby, Hamilton, all of Mass., assignors to Porter Sewing Machines, Inc., Beverly, Mass.

Division of Ser. No. 422,151, Apr. 14, 1995, Pat. No. 5,501,164, which is a continuation of Ser. No. 101,941, Aug. 4, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 478,033

Int. Cl.⁶ D05B 1/00

U.S. Cl. 112—2.1

8 Claims



7. Apparatus for assembly of a pillow-top mattress cover having at least a top panel, a side panel, a gusset for connecting the top panel to the side panel, and flange material for attachment of the gusset to an inner spring, the gusset having two flaps, said apparatus comprising:

- a gusset-forming machine for folding gusset material longitudinally to form a folded edge and the two flaps which are joined at the folded edge, and for stitching together the two flaps;
- a binding machine for securing a free edge of one flap of the gusset to an outer edge of the top panel;
- a sewing machine for providing a mitered corner to the gusset, said sewing machine being disposed sufficiently closed to said binding machine to allow the gusset to be mitered while the gusset is partially attached to the top panel and without removing the top panel from said binding machine; and
- a stitching machine for stitching the one flap of the gusset to an undersurface of the top panel.

5,586,512

SHIP'S HULL VIBRATION DAMPER

Finn Orbeck, Sunderland, United Kingdom, assignor to Orian Technology Limited, Sunderland, United Kingdom
PCT No. PCT/GB92/02053, § 371 Date May 3, 1994, § 102(e) Date May 3, 1994, PCT Pub. No. WO93/09025, PCT Pub. Date May 13, 1993

PCT Filed Nov. 6, 1992, Ser. No. 232,182


Claims priority, application United Kingdom, Nov. 7, 1991, 9123644

Int. Cl.⁶ B63B 43/00

U.S. Cl. 114—65 R

26 Claims

1. An apparatus for inclusion in a ship comprising a mass at least in part comprised of a chain locker and that portion of the chain



stored therein and having a hull vibrating at fundamental and harmonic frequencies of a transverse two node mode of wave induced vibration, means for vibrationally coupling the mass to the ship's hull and means for damping the movement of the mass, the mass being so sized and located as to, when in use, reduce the fundamental and/or harmonic frequencies of the transverse two node mode of wave-induced vibration in the ship's hull.

5,586,513

WATERTIGHT AND THERMALLY INSULATING TANK BUILT INTO A BEARING STRUCTURE


Pierre Jean, Dampierre, and Jean-Michel Chauvin, Plaisir, both of France, assignors to Gaztransport & Technigaz, Trappes, France

Filed Sep. 18, 1995, Ser. No. 529,401

Claims priority, application France, Sep. 20, 1994, 94 11165 Int. Cl.⁶ B63B 25/16

U.S. Cl. 114—74 A

22 Claims



1. A watertight and thermally insulating tank built into a bearing structure, comprising:

- a primary watertight barrier in contact with a material contained within said tank and comprising metal strakes including edges turned upwardly towards an interior of said tank, said strakes being made of thin sheet metal with a low coefficient of expansion;
 - a secondary watertight barrier positioned between said primary watertight barrier and the bearing structure;
 - a primary thermal insulating barrier;
 - a secondary thermal insulating barrier, said primary thermal insulating barrier and said secondary thermal insulating barrier being alternately arranged with said primary watertight barrier and said secondary watertight barrier; and
 - a weld support mechanically held on said primary thermal insulating barrier and constituting an expansion joint, said strakes being butt-welded via said turned-up edges to two faces of said weld support;
- said secondary watertight barrier, said secondary thermal insulating barrier and said primary thermal insulating barrier each comprising a set of prefabricated panels fixed to the bearing

structure, wherein a zone at a junction between two adjacent panels is filled in so as at least to ensure continuity of said secondary watertight barrier, each prefabricated panel being formed of:


- a first rigid plate including a layer of thermal insulant, said panels and said layer of thermal insulant together forming said secondary thermal insulating barrier;
- a flexible sheet bonded substantially to the entire surface of said layer of thermal insulant, said flexible sheet including at least one continuous fine metal foil forming said secondary watertight barrier;
- a second layer of thermal insulant that at least partially covers said flexible sheet and that is bonded thereto; and
- a second rigid plate covering said second layer of thermal insulant, said second rigid plate and said second layer of thermal insulant forming said primary thermal insulation barrier.

5,586,514 MOORING DEVICE

Thomas M. Yuscavage, 149 Bear Creek Rd., Dupont, Pa. 18641
Filed Mar. 29, 1995, Ser. No. 413,876
Int. Cl.⁶ B63B 21/00

U.S. Cl. 114—230

6 Claims



1. A mooring device comprising an elongated tubular handle having forward and rearward open ends; flexible tubular means formed into a loop having opposite ends connected to the forward end of said handle;
- a continuous line having leading and trailing ends, said leading end extending into said rearward end, through said handle, through said flexible tubular means to form said first loop therewith, through said handle and out of said rearward end, said leading and trailing ends of said line being tied at said rearward end of said handle to form a second loop.


5,586,515 FISHING ROD STORAGE APPARATUS AND METHOD

James A. Nickles, 1400 Kerr Station Rd., Cabot, Ark. 72023
Filed Sep. 11, 1995, Ser. No. 526,598
Int. Cl.⁶ B63B 35/14

U.S. Cl. 114—255

2 Claims

1. A fishing rod storage device comprising:
 - a base having an upper, substantially planar portion disposed substantially vertically and a lower, substantially planar portion disposed substantially perpendicular thereto, said upper portion of said base having a first plurality of holes passing therethrough and said lower portion of said base having a second plurality of holes passing therethrough to facilitate securing said device within a rod box;
 - a plurality of tubes secured to said upper portion of said base and aligned with said first plurality of holes so that said base retains and aligns said tubes substantially horizontally, each of said first plurality of holes and each of said plurality of tubes being sized to permit a tip end of a fishing rod to pass therethrough; and
 - each of said plurality of tubes being of sufficient length to store a fishing rod in close proximity to other fishing rods while preventing entanglement of rod tip ends, fishing lines and lures; and
 - wherein each of said plurality of tubes has a rear end portion and wherein each of said plurality of tubes is secured to said base



at said rear end portion of said tube whereby substantially the entire length of each of said plurality of tubes extends forward of said base.

5,586,516 RELATING TO BOARDING RAMP

Urs A. Hagen, Eggenran; Martin Schmid, Bahnhofstrasse, both of Switzerland, and Gwyn P. Owen, Clwyd, Great Britain, assignors to Services Algoa International Anstalt, Switzerland


Filed Sep. 5, 1995, Ser. No. 523,409

Claims priority, application United Kingdom, Sep. 6, 1994, 9417949

Int. Cl.⁶ B63B 17/00

U.S. Cl. 114—362

11 Claims




1. A boarding ramp which, in use, is pivotally secured to a waterborne craft, said boarding ramp comprising an elongated passageway, one end region of which is adapted to be pivotally attached to the waterborne craft, a hydraulic ram being connected to the passageway and connectable to the craft to, in use, control pivotal movement of the passageway, a controllable bypass connected across the hydraulic ram, a solenoid valve disposed and operative for controlling said controllable bypass, and an electromagnet being arranged on the other end region of the passageway for use in securing said other end region of the passageway to an unloading location.

5,586,517 FLAG SUPPORT AND ANGULATION SYSTEM

Tucker Willis, 4717 Wildwood Rd., Dallas, Tex. 75209, and James Cinquemani, Jr., 2412 Hardwick, Dallas, Tex. 75208
Continuation-in-part of Ser. No. 42,155, Apr. 2, 1993, Pat. No. 5,335,621. This application Jul. 15, 1994, Ser. No. 276,068
Int. Cl.⁶ G09F 17/00; A01K 97/10
U.S. Cl. 116—173

20 Claims



1. An improved flag staff assembly of the type wherein an elongate flag staff, having at least a hollow region formed in one end thereof, is disposed at an angle relative to a generally vertical surface having means for supporting a flag therefrom above a ground region wherein the improvement comprises:


a base member adapted for securement to said vertical surface in support of said flag staff therefrom, said base member being formed with an aperture therein adapted for receipt of said flag staff in a first angulated position therein; and means for re-angulating said flag staff to another angulated position, said means for re-angulating including an angulated shaft having first and second ends and adapted for receipt of said first end into said aperture, said second end including a neck portion for receiving said hollow region, formed in one end of said flag staff, over said neck portion, wherein said first end of said angulated shaft includes a slotted portion therein, said slotted portion being adapted for receiving an elongate member extending through said base member for preventing rotation of said angulated shaft in said base member.

5,586,518 MILKING CLUSTER AIR FORK

James A. Carrano, Stoughton, Wis., assignor to DEC International, Inc., Madison, Wis.
Filed Mar. 27, 1995, Ser. No. 411,417
Int. Cl.⁶ A01J 5/04

U.S. Cl. 119—14.51

18 Claims



1. A milking cluster for a dairy animal having an udder and a plurality of teats, and a backbone defining an axially extending longitudinal direction, comprising:

a claw having a plurality of inlets, and an outlet, said claw lying along a central longitudinal axis extending between the animal's legs and generally parallel to said backbone;

a plurality of teat cups, each connected to a respective teat;

a plurality of milk tubes, each connecting a respective claw inlet to a respective teat cup;

an air fork having a plurality of outlets, and one or more inlets;

a plurality of air tubes, each connecting a respective air fork outlet to a respective teat cup;

a milk hose connected to said claw outlet;

one or more vacuum pulsation air lines connected to said one or more air fork inlets;


wherein said air fork outlets direct said air tubes laterally inwardly of said milk tubes, rather than outwardly of said milk tubes, such that if the animal lifts her rear leg and steps forward, the dew claw on the inside of her leg will not hook an air tube and pull the respective teat cup off the teat, and wherein said air fork outlets extend generally axially longitudinally such that said air tubes extend generally axially longitudinally therefrom.

5,586,519 BALE FEEDER

Everett Wilkinson, 8124 Snowdell, Bonne Terre, Mo. 63628
Filed Nov. 9, 1994, Ser. No. 336,877
Int. Cl.⁶ A01K 1/10

U.S. Cl. 119—60

16 Claims



1. A bale hay feeder, comprising:
 - a first and second side frame each frame having a top rail and bottom rail both rails having a front end and rearward end, a front side rail with a top end and bottom end connecting said front end of said top rail to said front end of said bottom rail and a rearward side rail with a top end and bottom end connecting said rearward end of said top rail to said rearward end of said bottom rail;
 - a bottom frame having a front cross rail and rearward cross rail and at least one support rail connecting said front cross rail to said rearward cross rail, said rearward cross rail connecting said bottom end of said rearward side rails of said first and second side frames, said front cross rails connecting said front side rails of said first and second side frames, said bottom rails of said first and second side frames are closer together than said top rail of said first and second side frames and said top rails are far enough apart to accommodate a round bale of hay;
 - a plurality of said vertical chains, spaced such that an animal may reach hay through said spacing, affixed to said top rail of each of said first side frame and said second side frame, extending and affixed to said support rail;
 - a top cross rail connecting said top end of said rearward side rail of said first side frame to said top end of said rearward side rail of said second side frame; and
 - a gate including at least one chain affixed and extending from said front side rail of said first side frame to said front side rail of said second side frame wherein at least one end of said chain is removably affixed to allow hay to be inserted into said hay feeder.

5,586,520

METHOD OF MAINTAINING THE APPEARANCE OF EQUESTRIAN JUMPS

Timothy J. Cleary, 250 Round Swamp Rd., Melville, N.Y. 11747


Filed Oct. 26, 1994, Ser. No. 329,325
Int. Cl.⁶ A01K 15/02

U.S. Cl. 119—705

3 Claims

1. A method of maintaining a set appearance of at least one element of an equestrian jump that is subject to soiling, comprising the steps of:

- encasing the jump element in a cover substantially coextensive with a length thereof;
- removing the cover when it is soiled;
- cleaning the cover; and
- reapplying the cover to the jump element.



a replaceable combustion chamber dome including a spark plug housing and a dome-forming portion;

an engine cylinder head housing having means for receiving and supporting the replaceable dome therein, the replaceable dome receiving and supporting means including an aperture for receiving the spark plug housing;

means associated with the replaceable dome and the dome receiving and supporting means, for preventing rotational movement of the replaceable dome relative to the engine cylinder head housing, the rotational movement preventing means comprising a planar inner surface which defines a portion of the dome receiving and supporting means, and a corresponding planar outer surface which defines a portion of the replaceable dome and is situated adjacent to the planar inner surface;

means for directing a fluid coolant into the cylinder head to cool the replaceable dome and then exhausting the fluid coolant to a cylinder block; and

means for directing the fluid coolant from the cylinder block through the cylinder head to an outlet.


5,586,521

PORTABLE PET WASTE CONTAINER

Richard D. Kelley, 3114 N. 25th, Tacoma, Wash. 98406
Continuation-in-part of Ser. No. 69,445, Jun. 1, 1993, abandoned. This application Nov. 8, 1994, Ser. No. 336,307
Int. Cl.⁶ A01K 23/00

U.S. Cl. 119—858

4 Claims



1. A portable combination scoop-container apparatus detachably secured vertically to an animal's shoulder harness for toting animal waste and for collecting the waste from ground in the normal manner of a scoop when detached from the harness, comprising

- a container with a low front side and a high back side and having an open end and a closed end with the open end angled from the high back side to the lower front side as a scoop, means to detachably mount the container to the animal's shoulder harness,
- a flat lid covering the container open end and pivotally mounted on the high back side of the container so the lid tends to remain closed over the open end by gravity and rotatable against and disposed opposite the container back side when the container is detached from the shoulder harness, such that the flat lid is then directed generally toward the container closed end and away from the open end with the flat lid between the high back side and the ground, unobstructive to the open end to fully expose the open end as a scoop, when the container back side is held close to the ground approximately parallel thereto in the normal mode of a scoop.

5,586,522

CYLINDER HEAD FOR INTERNAL COMBUSTION ENGINES

Lawrence R. Phillis, Box 220514, Newhall, Calif. 91322, and Eugene W. VanDenBerg, II, 28169 Florence La., Canyon Country, Calif. 91351

Filed Sep. 12, 1995, Ser. No. 527,157
Int. Cl.⁶ F02B 75/08


U.S. Cl. 123—41.82 R

23 Claims

10. A cylinder head for an internal combustion engine, comprising:

1. A crankcase compression type single-cylinder two-cycle engine comprising:

- a single crankcase;



5,586,525

AIR/FUEL MIXTURE SUPPLY DEVICE FOR A TWO-STROKE INTERNAL-COMBUSTION ENGINE

Jean M. Masse, 60, rue Saint-Léger F-78100, Saint-Germain-en-Laye, France


PCT No. PCT/FR94/00972, § 371 Date Jan. 17, 1996, § 102(e) Date Jan. 17, 1996, PCT Pub. No. WO95/04212, PCT Pub. Date Feb. 9, 1995

PCT Filed Aug. 2, 1994, Ser. No. 583,043

Claims priority, application France, Aug. 3, 1993, 93 09556
Int. Cl.⁶ F02B 25/20

U.S. Cl. 123—73 B

9 Claims



a single cylinder communicating with said single crankcase;

a piston slidably mounted in said cylinder for movement between a top dead center position and a bottom dead center position, said piston partitioning said cylinder into a combustion chamber and a crank chamber, said combustion chamber having a first end adjacent said crank chamber and a second end remote from said crank chamber;

an air inlet opening into said crank chamber via a check valve;

an exhaust port provided in said first end of said combustion chamber;

a scavenging intake port provided in said first end of said combustion chamber adjacent said exhaust port and being in communication with said crank chamber;

an intake port opening into said second end of said combustion chamber, said intake port confronting an end of said piston;

a poppet type scavenging valve movably mounted in said intake port and confronting said end of said piston so as to be movable towards and away from said end of said piston;

a scavenging valve operating mechanism operably connected to said scavenging valve for opening said scavenging valve when said piston is located adjacent said bottom dead center position;

a scavenging passage communicating said intake port with said crank chamber; and

a fuel supply device communicating with said scavenging passage upstream of said intake port.

5,586,524

FUEL INJECTION CONTROL SYSTEM FOR INTERNAL COMBUSTION ENGINE

Kimihiro Nonaka, and Hiroaki Ohtani, both of Hamamatsu, Japan, assignors to Sanshin Kogyo Kabushiki Kaisha, Hamamatsu, Japan


Filed Sep. 1, 1994, Ser. No. 299,519

Claims priority, application Japan, Sep. 1, 1993, 5-217771; Sep. 1, 1993, 5-217772; Sep. 1, 1993, 5-217773

Int. Cl.⁶ F02D 41/04; F02B 33/04

U.S. Cl. 123—73 A

11 Claims



1. A fuel injection control system for a two-cycle internal combustion engine, comprising a pressure sensor installed in a cylinder of said engine for detecting crankcase pressure at the time of scavenge opening and scavenge closing to obtain a tentative intake air amount, a fuel injector for injecting fuel to said engine on the basis of said crankcase pressure detected by said pressure sensor, means for compensating the amount of fuel injected from said fuel injector in response to the condition of intake air in said crankcase to obtain a compensation factor to be multiplied by said tentative air amount to determine a true amount of fuel to be injected.

5,586,526

LARGE TWO-STROKE INTERNAL COMBUSTION ENGINE

Henning Lindquist, Nivå, Denmark, assignor to MAN B&W Diesel A/S, Copenhagen SV, Denmark

PCT No. PCT/DK93/00364, § 371 Date Dec. 4, 1995, § 102(e) Date Dec. 4, 1995, PCT Pub. No. WO94/29577, PCT Pub. Date Dec. 22, 1994


PCT Filed Nov. 9, 1993, Ser. No. 557,193

Claims priority, application Denmark, Jun. 4, 1993, 0647/93
Int. Cl.⁶ F01L 9/02

U.S. Cl. 123—90.12

10 Claims

1. A large two-stroke internal combustion engine (1), in particular a main engine of a ship, having a hydraulically driven cylinder member, such as a fuel pump (18) or an exhaust valve (13), in which the hydraulic drive of the member comprises a driving piston (70) journaled in a hydraulic cylinder (69) which, through a flow passage 67, communicates with a spool valve, the spool of which (74) may occupy a position where the flow passage (67) communicates with a high-pressure source (65) for hydraulic oil, and another position where the flow passage communicates with a low-pressure port (66), and where, during normal engine operation, the spool is positionable by means of an electrically activated positioning means (64) receiving control signals from an engine controlling computer (16), and where, in case of failure of the normal engine control, the spool is alternatively positionable by



means of a camshaft (23) rotating synchronously with the crankshaft (11) of the engine, characterized in that the spool (74) is associated with a first piston (41) on which the pressure in a hydraulic conduit (48) acts, said conduit extending to a second piston (44) which may follow a cam (26) on the rotating camshaft, and that the hydraulically driven cylinder members (14, 13, 18) associated with each of the engine cylinders are mounted at the pertaining cylinder, whereas the camshaft (23) independently of the positioning of the cylinder members is disposed at an appropriate shaft drive, such as the crankshaft (11).

5,586,527

DEVICE FOR THE VARIABLE CONTROL OF THE VALVES OF INTERNAL COMBUSTION ENGINES, MORE PARTICULARLY FOR THE THROTTLE-FREE LOAD CONTROL OF 4-STROKE ENGINES

Peter Kreuter, Aachen, Germany, assignor to Meta Motoren- und Energie-Technik GmbH, Herzogenrath, Germany
PCT No. PCT/DE93/01248, § 371 Date Jun. 9, 1995, § 102(e) Date Jun. 9, 1995, PCT Pub. No. WO94/16203, PCT Pub. Date Jul. 21, 1994


PCT Filed Dec. 22, 1993, Ser. No. 481,245

Claims priority, application Germany, Dec. 30, 1992, 42 44 551.5; Dec. 30, 1992, 42 44 550.7

Int. Cl.⁶ F01L 13/00; 1/34

U.S. Cl. 123—90.15

12 Claims



1. Apparatus for variable control of valves in an internal combustion engine having a crankshaft, said apparatus comprising

first and second camshafts having fixed axes and acting on a rocker lever when in turn acts on a spring loaded valve, gear means for phase-shifting said second camshaft relative to said first camshaft, said gear means comprising a driving wheel driving said first camshaft and driven by said crankshaft, a first intermediate wheel driven by said driving wheel, a second intermediate wheel driven by said first intermediate wheel, and a driven wheel driving said second camshaft and driven by said second intermediate wheel, said first and second intermediate wheels having moveable axes, whereby moving said axes of said intermediate wheels phase-shifts said second camshaft relative to said first camshaft, and drag means comprising a pair of engaged wheels having different operative diameters mounted on respective first and second camshafts, and friction means effective between one of said pair of wheels and one of said camshafts, thereby generating a drag force which is superposed on the force transmitted to the second camshaft by the driven wheel.

5,586,528

TAPPET FOR THE VALVE DRIVE OF AN INTERNAL COMBUSTION ENGINE

Walter Spell, Ingolstadt, Germany, assignor to Ina Walzinger Schaeffler KG, Germany


Continuation-in-part of Ser. No. 447,720, May 23, 1995, abandoned, which is a division of Ser. No. 340,024, Nov. 14, 1994, Pat. No. 5,450,826. This application Jan. 16, 1996, Ser. No. 586,376

Claims priority, application Germany, Dec. 22, 1993, 43 43 876.8

Int. Cl.⁶ F01L 1/25

U.S. Cl. 123—90.51

1 Claim



1. A tappet (1) for a valve drive of an internal combustion engine, comprising a hollow cylindrical housing (2) arranged with a thin-walled jacket (3) for axial displacement in a receiving bore (4) of a cylinder head (5), said housing (2) being closed at one front end (6) by a thin-walled bottom (7), the tappet (1) further comprising a hydraulic clearance compensation element (9) which extends concentric with the jacket (3) from an underside (8) of the bottom (7) and whose guide sleeve (10) facing an underside (8) of the bottom (7) is surrounded by an axially displaceable pressure piston (11) whose bottom (12) faces an end of a valve shaft (13), said tappet (1) also comprising a thin-walled cylindrical element (15) fixed in an oil-tight manner to an inner surface (14) of the jacket (3), said cylindrical element (15) extending in a region of the jacket (3) up to the housing bottom (7) and forming an annular oil reservoir (18) by merging into a radially inwards extending portion (16) which continues into an axially oriented concentric guide portion (17) for the pressure piston (11), a canal (19) for hydraulic medium starting from a supply bore (20) in the jacket (3) and extending in a region of the jacket (3) toward the housing bottom (7) and being formed in the cylindrical element (15), there

being further provided in the housing bottom (7), a recess (25) to allow oil transfer between the annular oil reservoir (18) and a central oil reservoir (26), characterized in that an upper edge (22) of the cylindrical element (15) extends directly along the underside (8) of the housing bottom (7) except in a region of a trough-like formation (24) provided in the cylindrical element (15) in a region of the underside (8) of the housing bottom (7) for oil transfer from the canal (19) into the annular oil reservoir (18), the ratio of the width of the recess (24) at an upper edge thereof facing the bottom of the width of the canal (19) is ≥ 1.75 .

5,586,530

VALVE SEAT INSERT

Shuhei Adachi, and Junichi Inami, both of Iwata, Japan, assignors to Yamaha Hatsudoki Kabushiki Kaisha, Iwata, Japan


Division of Ser. No. 278,026, Jul. 20, 1994. This application Jun. 7, 1995, Ser. No. 483,538

Claims priority, application Japan, Jul. 20, 1993, 5-200325; Jul. 20, 1993, 5-250559

Int. Cl.⁶ F01L 3/04

U.S. Cl. 123—188.8

10 Claims



1. A metallic valve seat insert for a metallic cylinder head, said valve seat insert having an opening adapted to form a flow opening registering with a cylinder head passage surrounded by a recess and an outer surface positioned to face the part of the cylinder head defining the recess, and a layer of metallic material interposed between said outer surface of said valve seat insert and the recess and physically adhered to said outer surface and capable of forming an alloy with the metal of one of said cylinder head and said valve seat insert when heated.

5,586,529

PNEUMATIC ENGINE VALVE SPRING ASSEMBLY


Serge Vallve, 33320 Hereford Way, Lake Elsinore, Calif. 92530

Filed Sep. 13, 1995, Ser. No. 527,441

Int. Cl.⁶ F01L 3/10; F16F 1/00

U.S. Cl. 123—90.65

8 Claims



1. A pneumatic valve spring member (10) for an internal combustion engine, comprising:

- a valve guide (16), said valve guide defining a valve stem passage (24) through which a valve stem (12) may reciprocally travel in a manner guided by said valve guide;
- a valve retainer (30), said valve retainer coupled to a distal end of said valve stem, said valve retainer reciprocally traveling with said valve stem;
- a bellows seal (42), said bellows seal sealingly attached at a first end to said valve guide and at a second end to said valve retainer, said bellows seal preventing the further travel of blow-by gasses from said valve stem passage and allowing resiliently flexible articulation between said valve guide and said valve retainer;
- a lower isolator (50), said lower isolator extending laterally about said valve guide;
- an upper isolator (52), said upper isolator extending laterally about said valve retainer; and
- a pressurized air cushion (60) having a hollow interior (59) and a resiliently flexible exterior (58), said pressurized air cushion held between said lower isolator and said upper isolator, said pressurized air cushion resiliently biasing said valve retainer (30) away from said valve guide (16); whereby an engine valve (14) coupled to said valve retainer (30) is biased closed by the pneumatic valve spring member (10).

5,586,531

ENGINE RETARDER CYCLE

David A. Vittorio, Columbus, Ind., assignor to Cummins Engine Company, Inc., Columbus, Ind.


Filed Nov. 28, 1995, Ser. No. 563,615

Int. Cl.⁶ F02D 39/02

U.S. Cl. 123—320

20 Claims

Exhaust Mass Flow Rate



1. An engine retarder cycle for operation of an engine brake, comprising the steps of:

- (a) beginning to open a retarder valve in an engine cylinder during a second half of a compression stroke of a piston in the engine cylinder;
- (b) opening the retarder valve to a maximum displacement prior to a top dead center position of the piston; and
- (c) closing the retarder valve during a first half of all expansion stroke of the piston.

- (d) return means for returning the operation of said mixture controller to said checking means after either said first changing means or said second changing means has changed said output value; and
- (e) inhibit means for inhibiting a return of the operation of the mixture controller from said first changing means or said second changing means to said checking means until an inhibit time has elapsed.

5,586,544


FUEL INJECTION AMOUNT CONTROL SYSTEM FOR INTERNAL COMBUSTION ENGINES AND INTAKE PASSAGE WALL TEMPERATURE-ESTIMATING DEVICE USED THEREIN

Toru Kitamura; Akira Katoh; Katsuhiko Kumagai; Sachito Fujimoto; Hiroshi Kitagawa; Shunichi Tsuzuki; Jun Takahashi; and Masami Watanabe, all of Wako, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan
Filed Nov. 30, 1994, Ser. No. 351,210

Claims priority, application Japan, Nov. 30, 1993, 5-325831; Dec. 16, 1993, 5-343761; Dec. 16, 1993, 5-343762
Int. Cl.⁶ F02D 41/06; 41/14; 41/32

U.S. Cl. 123—684

32 Claims



1. In a fuel injection amount control system for an internal combustion engine having an intake passage, said intake passage having a wall surface, at least one fuel injection valve, and at least one combustion chamber, including first fuel amount-calculating means for calculating a first amount of fuel directly drawn into said at least one combustion chamber out of an amount of fuel injected into said intake passage via said at least one fuel injection valve, second fuel amount calculating means for calculating a second amount of fuel carried off fuel adhering to said wall surface of said intake passage into said at least one combustion chamber, fuel injection amount-calculating means for calculating an amount of fuel to be injected into said intake passage, based on said first amount of fuel and said second amount of fuel, air-fuel ratio detecting means for detecting an air-fuel ratio of exhaust gases from said engine, air-fuel ratio correction amount-calculating means for calculating an air-fuel ratio correction amount, based on an output from said air-fuel ratio detecting means, and air-fuel ratio correcting means for correcting said amount of fuel to be injected into said intake passage by said air-fuel ratio correction amount.

the improvement comprising carried-off fuel amount-correcting means for correcting said second fuel amount, based on said air-fuel ratio correction amount; and driving means for driving said at least one fuel injection valve in order to supply said corrected amount of fuel to be injected to said intake passage, wherein said carried-off fuel amount-correcting means includes carried-off fuel amount correction coefficient-setting means for setting a carried-off fuel amount correction coefficient such that said carried-off fuel amount correction coefficient assumes a smaller value as said air-fuel ratio correction amount is larger, said carried-off fuel amount-correcting means correcting said second amount of fuel by said carried-off fuel amount correction coefficient.

3. A fuel injection amount control system for an internal combustion engine having an intake passage, said intake passage having a wall surface, at least one fuel injection valve, at least one combustion chamber, and an exhaust passage, comprising:

first fuel amount-calculating means for calculating a first amount of fuel directly drawn into said at least one combustion chamber and burned therein out of an amount of fuel injected into said intake passage via said at least one fuel injection valve;

second fuel amount-calculating means for calculating a second amount of fuel directly drawn into said at least one combustion chamber and exhausted therefrom without being burned therein out of said amount of fuel injected into said intake passage via said at least one fuel injection valve;

third fuel amount-calculating means for calculating a third amount of fuel carried off fuel adhering to said wall surface of said intake passage into said at least one combustion chamber;

fuel injection amount-calculating means for calculating an amount of fuel to be injected into said intake passage, based on said first amount of fuel, said second amount of fuel and said third amount of fuel; and

driving means for driving said at least one fuel injection valve in order to supply said calculated amount of fuel to be injected to said intake passage.

11. An intake passage wall surface temperature-estimating device for an internal combustion engine having an intake passage, said intake passage having a wall surface, comprising:

coolant temperature-detecting means for detecting a temperature of coolant circulating through said engine;

intake air temperature-detecting means for detecting a temperature of intake air in said intake passage of said engine; and

intake passage wall surface temperature-estimating means for estimating a temperature of said wall surface of said intake passage, based on said coolant temperature detected by coolant temperature-detecting means and said temperature of said intake air in said intake passage detected by said intake air temperature-detecting means, at an intermediate temperature between said coolant temperature and said temperature of said intake air.

5,586,545


COMPRESSED GAS GUN

John A. McCaslin, 4104 Steeplewood Ct., Arlington, Tex. 76016
Filed Oct. 2, 1995, Ser. No. 537,528

Int. Cl.⁶ F41B 11/00

U.S. Cl. 124—73

14 Claims



1. A compressed gas gun operable to be coupled to a compressed gas tank and for propelling a projectile under force of compressed gas expelled through an outlet fitting on the compressed gas tank, said air gun comprising:

a frame having a muzzle end and a breech end;

a first barrel guide, having a housing, attached to said frame at a point closer to said muzzle end than said breech end, and

5,586,547

INSTANTANEOUS GAS WATER HEATER


Austin D. Nixon, 1500 Airway Cir., New Smyrna Beach, Fla. 32168

Filed Jan. 13, 1995, Ser. No. 372,500

Int. Cl.⁶ F24H 1/00

U.S. Cl. 126—351

17 Claims



1. An instantaneous gas water heater comprising:

a control panel comprising gas solenoid valve electrically connected to an electronic controller, and a blower operation providing means electrically connected to said electronic controller;

a blower section comprising a blower electrically connected to said electronic controller, said blower communicating with a gas/air mixing chamber and with said blower operation providing means, said gas/air mixing chamber communicating with said gas solenoid valve; and

a heat transfer section comprising an inner jacket, the space within said inner jacket defining a combustion chamber, a baffle disposed within said combustion chamber, a gas/air combustion means communicating with said gas/air mixing chamber disposed within said combustion chamber, an ignition means disposed within said combustion chamber, and an outer jacket enclosing said inner jacket, space between said inner jacket and said outer jacket defining a water sleeve, said gas/air combustion means comprising a powered burner comprising a venturi tube communicating with said gas/air mixing chamber, venturi tube holes in said venturi tube, and a mantle enclosing said venturi tube, the mantle's shape matching the inner jacket's shape.

5,586,546

FOLD-AWAY GAS APPLIANCE


Walter M. Ashcraft, Rockford, and Matthew A. Wales, South Beloit, both of Ill., assignors to Atwood Industries, Inc., Rockford, Ill.

Filed Jul. 24, 1995, Ser. No. 506,366

Int. Cl.⁶ F24C 3/12

U.S. Cl. 126—42

12 Claims



1. A fold-away gas appliance for a recreational vehicle having a sidewall with an opening therein, the appliance comprising a storage compartment located in the opening, a cooking unit supported by the compartment for pivotal movement to swing downwardly and upwardly between an upright storage position located in the compartment and a generally horizontal exposed position extending outwardly from the sidewall, the cooking unit having a gas burner and having a cut-off valve disposed for operating movement between open and closed positions to establish and cut off the flow of gas to the burner, an actuator operably linking the pivotal movement of the cooking unit with the operating movement of the cut-off valve for moving the valve between the open and closed positions, and bracket means connecting the storage compartment to the cooking unit and linked to the cut-off valve for shifting the actuator in a first direction relative to the cooking unit to move the valve toward the closed position as the cooking unit is swung upwardly toward the storage position and in a second direction relative to the cooking unit to move the valve toward the open position as the cooking unit is swung downwardly toward the exposed position.

5,586,548

FLOATING SOLAR HEATER FOR POOL WATER

Chih-Yu Hsia, 301 Warren Wy., Arcadia, Calif. 91006

Filed Feb. 28, 1995, Ser. No. 395,715

Int. Cl.⁶ F24J 2/42

U.S. Cl. 126—565

4 Claims

1. A solar heater in combination with a water pool, comprising:

a) a float having an upper side and a lower side,


b) a solar heat collecting first plate spaced above said upper side of the float,

c) heat radiating means spaced below the lower side of the float, to contact pool water, and

d) heat transfer means extending through the float and between said heat collecting plate and said heat radiating means, for transferring heat by conduction from the plate to said means, to enable collected solar heat transfer to the pool water,

e) said heat transfer means comprising a plurality of metallic elements, which are spaced apart, said float having plastic float material and a plurality of separate and individual openings through the plastic float material below said plate and passing said metallic elements,

f) and wherein said metallic elements hang from said plate and extend downwardly through and spaced from a sidewall of



said openings and substantially below the float lower side to be suspended by the float for contact with pool water at a depth therein below the float.
g) said float suspended by water in the pool, whereby said metallic elements are floatingly suspended in and by said water pool.

5,586,549


COMBINED SOLAR AND GAS HEATER

John R. Hartenstine, Landisville, and Peter M. Dussinger, Lititz, both of Pa., assignors to Thermacore, Inc., Lancaster, Pa.

Filed Jan. 3, 1996, Ser. No. 582,386
Int. Cl.⁶ F24J 2/32

U.S. Cl. 126—635

8 Claims



1. In a solar collector assembly of the type which includes a solar heat pipe formed as a sealed enclosure, with one wall of the solar heat pipe being a solar collector which has a solar evaporator wick on the surface of the solar collector wall within the solar heat pipe; a heat utilization device acting as the condenser of the solar heat pipe; capillary means delivering condensed liquid from the condenser to the solar evaporator wick; a fuel burning heater to furnish auxiliary heat to the solar heat pipe; a combustion chamber enclosing the fuel burning heater; a fuel delivery means supplying fuel and air to the heater; and an exhaust means open to the interior of the combustion chamber to exhaust combustion products from the burner; the improvement comprising:
the combustion chamber including at least one surface which is heated by the fuel burning heater, with the heated surface including a first side within the combustion chamber and a second side outside the combustion chamber;
a burner evaporator wick attached to the second side of the heated surface; and

a heat pipe enclosing the burner evaporator wick on the second side of the surface, with the heat pipe removing heat from the combustion chamber and with the heat pipe including a condenser section to condense evaporated vapor and a delivery means to supply liquid condensed within the condenser section to the burner evaporator wick further including:
at least one cavity formed in a wall of the solar heat pipe enclosure other than the solar collector wall, with the cavity forming the combustion chamber and having at least one surface exposed within the solar heat pipe; and
the burner evaporator wick being located within the solar heat pipe and covering a surface of the cavity which is exposed within the solar heat pipe, so that the solar heat pipe is the heat pipe enclosing the burner evaporator wick.

5,586,550


APPARATUS AND METHODS FOR THE DELIVERY OF THERAPEUTIC LIQUIDS TO THE RESPIRATORY SYSTEM

Yehuda Ivri, Irvine, and Cheng H. Wu, Sunnyvale, both of Calif., assignors to Fluid Propulsion Technologies, Inc., Santa Clara, Calif.

Filed Aug. 31, 1995, Ser. No. 521,641
Int. Cl.⁶ A61M 11/00

U.S. Cl. 128—200.16

47 Claims



1. An apparatus for nebulizing a liquid, the apparatus comprising:
a non-planar member comprising a front surface, a rear surface, and a plurality of apertures extending therebetween, said apertures being tapered to narrow from the rear surface to the front surface;
a liquid supplier which delivers liquid to the rear surface such that substantially all of the delivered liquid adheres to the non-planar member by surface tension; and
a vibrator which vibrates the non-planar member to eject liquid droplets from the front surface of the member.

5,586,551

OXYGEN MASK WITH NEBULIZER


Kenneth R. Hilliard, 2840 Gibbs-Williams Rd., Dallas, Tex. 75233

Filed Jul. 17, 1995, Ser. No. 503,327
Int. Cl.⁶ A61M 11/00

U.S. Cl. 128—203.29

6 Claims

1. A respiratory therapy mask comprising:
a mask portion defining a cavity having an opening, said cavity and said opening being dimensioned and configured for said opening to sealingly contact a patient's face and for said cavity to form an enclosed space about the patient's nose and mouth, said mask portion further having a first one-way inlet valve and a second one-way inlet valve;
a first main breathable gas supply assembly communicating with said first inlet valve for supplying a first breathable gas to a patient; and
a nebulizer assembly removably attached to said second inlet valve and supplies an inhalable medication entrained in a second breathable gas to said mask portion, said nebulizer assembly includes:



a nebulizer bottle in the form of a container containing a jet with a centered nozzle, said nozzle receiving said second breathable gas from a secondary gas source, whereby the breathable gas from said secondary gas source issues as a jet stream;
a jet housing fitting over said jet and creating an annular gap between said jet housing and said jet, the inhalable medication in liquid form filling said annular gap and reaching the nozzle of said jet, the inhalable medication becomes being entrained in the breathable gas from said secondary gas source issuing from said nozzle; and
a nebulizer connector removably attached to said nebulizer bottle, said nebulizer connector containing a baffle centered said nebulizer connector, said baffle which disperses the second breathable gas from said secondary gas source issuing from said nozzle and having inhalable medication entrained therein into the gas jet stream, and said nebulizer connector having an outlet in communication with said second inlet valve;
whereby a patient can receive a prescribed dosage of medication simultaneously with the first breathable gas to prevent hypoxia and shortness of breath.

5,586,552


PHYSICAL-INFORMATION DETECTING SYSTEM

Hiroshi Sakai, Komaki, Japan, assignor to Colin Corporation, Komaki, Japan

Filed Nov. 16, 1994, Ser. No. 341,989
Claims priority, application Japan, Nov. 29, 1993, 5-298385
Int. Cl.⁶ A61B 5/00

U.S. Cl. 128—633

19 Claims



1. A physical-information detecting system comprising:

a first detector which detects a first physical information of a living subject and generates a first physical-information signal representing the detected first physical information;
a second detector which detects a second physical information of said living subject and generates a second physical-information signal representing the detected second physical information;
a first transmitter which transmits said first physical-information signal, and a first identification signal identifying said first detector;
a second transmitter which transmits said second physical-information signal, and a second identification signal identifying said second detector;
a physical-information output device which receives said first and second physical-information signals and said first and second identification signals, from said first and second transmitters, and outputs said detected first physical information represented by said first physical-information signal and said detected second physical information represented by said second physical-information signal;
determining means for determining a characteristic of change of each of said first and second physical-information signals; and
judging means for judging whether said first and second detectors are located on the same living subject based on the respective determined characteristics of said first and second physical-information signals, said judging means providing a positive judgment when said respective determined characteristics are substantially identical with each other.

5,586,553


TRANSCUTANEOUS SENSOR INSERTION SET

Edgardo C. Halili, Reseda, and John J. Mastrototaro, Los Angeles, both of Calif., assignors to MiniMed Inc., Sylmar, Calif.

Filed Feb. 16, 1995, Ser. No. 393,148
Int. Cl.⁶ A61B 5/05

U.S. Cl. 128—635


21 Claims



1. A transcutaneous sensor insertion set, comprising:
a mounting base adapted for mounting onto a patient's skin;
a flexible sensor having a proximal segment carried by said mounting base, and a distal segment protruding from said mounting base and having at least one sensor electrode thereon;
a cannula protruding from said mounting base and having said sensor distal segment therein, said cannula defining at least one window disposed generally in alignment with said at least one sensor electrode on said sensor distal segment; and
a hollow insertion needle carried by said mounting base to protrude therefrom and having at least a portion of said cannula nested therein, said insertion needle defining a longitudinally extending slot along one side thereof to permit sliding withdrawal of said needle from said mounting base and said nested portion of said cannula.

5,586,554
OPTICAL SYSTEM FOR MEASURING METABOLISM IN A BODY
 Atsushi Maki, Hachioji; Fumio Kawaguchi, Tokyo; Yulchi Yamashita, Hachioji, and Yoshitoshi Ito, Ome, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
 Filed Feb. 16, 1994, Ser. No. 197,749
 Claims priority, application Japan, Feb. 23, 1993, 5-033018
 Int. Cl.⁶ A61B 5/05
 U.S. Cl. 128—653.1

34 Claims




1. An optical system for measuring metabolism in a test subject by irradiating rays of light from a light source to the inside of the test subject and detecting rays of light passing from inside of the test subject so as to obtain information about the inside of the test subject, said optical system comprising:
 irradiating means for receiving from the light source light having a plurality of wavelengths and irradiating plural rays of the light onto plural irradiation spots on the test subject, with each of the irradiation spots receiving a light ray of a different wavelength;
 means for detecting rays of light passing from the inside of the test subject at plural detecting spots on the test subject; and
 first separating means for separating the detected rays of light by wavelength.

5,586,555
BLOOD PRESSURE MONITORING PAD ASSEMBLY AND METHOD
 Donald E. Bobo, Jr., Orange, and Thomas H. Doupe, Huntington Beach, both of Calif., assignors to Innerspace, Inc., Santa Ana, Calif.
 Filed Sep. 30, 1994, Ser. No. 316,555
 Int. Cl.⁶ A61B 5/00

U.S. Cl. 128—672

36 Claims



1. A pad assembly for use in a system for obtaining certain information about the blood pressure of a given person by a particular blood pressure technique in which a pressurizable pressure transducing bladder is supported on the skin of the person


adjacent to and in cooperation with a particular target artery in combination with means for pressurizing the bladder in a controlled way, said pad assembly comprising:

- a) said pressure transducing bladder; and
- b) support means including adhesive tape for fixably supporting said bladder in place against the skin adjacent the target artery so that the bladder is in direct contact with the skin and said adhesive tape is directly attached to a portion of the skin adjacent the bladder, said support means further including movement means configured to move at least to a limited extent within a release zone in response to the pressurization of said bladder in a way which prevents said adhesive tape from detaching from the skin as the bladder is pressurized.

5,586,556
PACEMAKER AND HEART MONITORING AND DATA TRANSMITTING DEVICE AND METHOD
 Thomas R. Spivey, West Linn, and Byron G. Zahler, Portland, both of Oreg., assignors to T Z Medical, Inc., Lake Oswego, Oreg.
 Filed May 11, 1995, Ser. No. 438,688
 Int. Cl.⁶ A61B 5/04

U.S. Cl. 128—697

13 Claims




1. A pacemaker monitor transmitter device for coupling to a patient having a pacemaker and interacting with a remote station including a remote operator, the device comprising:
 a telephonic communication channel delivering a pacemaker monitor transmitter device generated signal and a patient voice signal into a telephone connection and receiving from said telephone connection a remote signal including a command signal and a remote operator voice signal;
 an electrode pair attachable to said patient and providing a patient signal; and
 a patient signal processing element receiving said patient signal in analog form, converting said patient signal to digital form, and providing said patient signal to said telephonic channel in frequency modulated form as said device generated signal.

5,586,557
FUNCTIONAL AMBULATION PERFORMANCE SCORING DEVICE
 Arthur J. Nelson, New York, and Clifford M. Gross, Roslyn, both of N.Y., assignors to BCAM International, Inc., Melville, N.Y.
 Filed May 31, 1994, Ser. No. 251,596
 Int. Cl.⁶ A61B 5/103

U.S. Cl. 128—779

18 Claims

1. For use with a walking surface and left and right feet, a device for measuring human ambulation comprising:
 (a) a left foot sensor capable of sensing when the left foot is in contact with the walking surface, the left foot sensor being activated when such contact occurs;




- (b) a right foot sensor capable of sensing when the right foot is in contact with the walking surface, the right foot sensor being activated when such contact occurs;
- (c) a processor having an algorithm to create an ambulation index reflective of a quantitative analysis of human ambulation;
- (d) left transmission means for indicating to the processor when the left foot sensor is activated;
- (e) right transmission means for indicating to the processor when the right foot sensor is activated; and
- (f) output means to output the ambulation index from the processor.

5,586,558
OPTIMIZER MEASURING UNIT
 David R. Riley, Russellville, Ark., assignor to Stanley E. Gately, and Catherine G. Gately, both of Russellville, Ark.
 Filed Sep. 2, 1994, Ser. No. 300,485
 Int. Cl.⁶ A61B 5/10

U.S. Cl. 128—781

9 Claims



1. In a measuring device used for determining bone lengths and degree angles of the skeletal system of a human body for purposes of determining natural ranges of motion of any specific individual as used in ergonomics, fitness and job safety; a base plate from which a stand extends upwardly, said stand comprising a vertical column attached to said base plate and that has a square tube in said column that extends and adjusts the height of said stand, said square tube having a right support arm that extends right from said square tube, and at the end of said right support arm is a fixed plexiglass disc with black graduations etched on the surface for obtaining degree angles and length measurements of the upper extremities of the human body, further wherein said disc is affixed to said right support arm at a center point which is a point of origin


from which all measurements originate and which is the top of the sternoclavicular joint of the human body, and further pivotally affixed to said center point is a plexiglass radial dial arm used in obtaining degree angles of the elbow radius and length measurements of the human body, further attached to said radial dial arm is an aluminum slide that slides along said radial dial arm to indicate the measurements of the human body.

5,586,559
ARTHROMETER WITH GRAVITY SWITCHES AND ADJUSTABLE LIMIT SIGNALING
 Kevin R. Stone, 1 Throckmorton La., Mill Valley, Calif. 94941; Perry A. Klebahn, 2633 Steiner St., San Francisco, Calif. 94115, and William R. Knapp, 116 Gilbert St., Menlo Park, Calif. 94025

Continuation of Ser. No. 992,059, Dec. 17, 1992, Pat. No. 5,394,888. This application Mar. 6, 1995, Ser. No. 398,527
 Int. Cl.⁶ A61B 5/103

U.S. Cl. 128—782

20 Claims



19. An arthrometer for monitoring an angle of flexure of an elongated body limb with respect to the portion of the body to which the limb is attached, comprising:

- A. an elongated housing extending along a principal axis,
- B. means for detachably coupling said housing to the limb whereby said principal axis is at a fixed orientation with respect to a central axis of the limb,
- C. first limit sensor affixed to said housing including:
 - i. a first gravity-actuated switch coupled to said housing and responsive to orientation relative to a vertical axis, so that said first switch is in a first state when said first switch is oriented within a first range of orientations, and said first switch is in a second state when said first switch is oriented within a second range of orientations,
 - ii. first switch positioning assembly including first vernier means for adjustably orienting said first switch with respect to said principal axis with a sensitivity reduction greater than 1:1, whereby said first switch is in its first state when said principal axis is oriented within a first predetermined range of orientations measured with respect to the vertical axis and in its second state otherwise, and
- D. second limit sensor affixed to said housing including:
 - i. a second gravity-actuated switch coupled to said housing and responsive to orientation relative to the vertical axis, so that said second switch is in a first state when said second switch is oriented within a third range of orientations, and said second switch is in a second state when said second switch is oriented within a fourth range of orientations, and
 - ii. second switch positioning assembly including second vernier means for adjustably orienting said second switch with respect to said principal axis with a sensitivity reduction greater than 1:1, whereby said second switch is in its first

state when said principal axis is oriented within a second predetermined range of orientations measured with respect to the vertical axis and in its second state otherwise.

interconnecting means for directly attaching each of the plurality of curved plates one to another for maintaining the continuous tunnel between at least two adjacent ones of the plurality of curved plates.

5,586,560


COLLAPSIBLE SEATING APPARATUS

David Boutos, 4420 Dunlap Crossing St., Las Vegas, Nev. 89129
Filed Jan. 5, 1995, Ser. No. 368,907

Int. Cl.⁶ A61G 15/00; A47C 3/00

U.S. Cl. 128—845

9 Claims



1. A seating apparatus, said apparatus comprising:
a base;
a plurality of support members rising up from said base, said support members supporting two transverse horizontal members which form a seating surface for one person;
supports for resting one's legs rotatably mounted at the front of said transverse horizontal members; and
a seat back attached to the rear of said transverse horizontal members.

5,586,561


BACK GUARD WITH TUNNEL FOR SPINAL COLUMN

Shreve M. Archer, III, Carmel Valley, Calif., assignor to Entropy Racing, Inc., Monterey, Calif.
Continuation-in-part of Ser. No. 163,906, Dec. 6, 1993, Pat. No. 5,400,801. This application Sep. 7, 1994, Ser. No. 301,891

Int. Cl.⁶ A61F 5/37

U.S. Cl. 128—846

8 Claims



1. A back guard comprising:
a plurality of curved plates having inner contours, the plurality of curved plates aligned with one another for forming a continuous tunnel, the continuous tunnel, defined by the inner contours, for corresponding to at least a portion of a human spine, the continuous tunnel having a height along at least a portion thereof of at least 3 cm; and

5,586,562


DEVICE FOR SENSING AND TREATING BRUXISM

Warren W. Matz, 882 U.S. Highway 1, Juno Beach, Fla. 33408
Filed Jul. 14, 1995, Ser. No. 502,681

Int. Cl.⁶ A61F 5/56

U.S. Cl. 128—848

17 Claims



1. An anti-bruxism device comprising: an L-shaped support means defined by a substantially vertical mounting section and a substantially horizontal biting section, said support means having a width and a length with an inner surface and an outer surface defining a thickness therebetween; and a mounting means bonded to at least one tooth for releasably securing said support means to a tooth side surface positioning said inner and outer surfaces of said biting section between the biting surfaces of teeth and said inner surface of said vertical section positioned along an outer surface of a tooth.

5,586,563


METHOD FOR MAKING A SURGICAL DRAPE

Charles L. Newman, Stillwater, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.
Filed Oct. 23, 1995, Ser. No. 546,587

Int. Cl.⁶ A61B 19/00

U.S. Cl. 128—849

23 Claims



1. A method for making a series of surgical drapes comprising the steps of:
advancing a first continuous web forming a body portion of a surgical drape along a first longitudinal axis to a cutting and bonding location, the first continuous web having a first width

perpendicular to the first longitudinal axis and first and second long edges generally parallel to the first longitudinal axis;
locating a second web having first and second long edges generally parallel to a second longitudinal axis so that the first long edge of the second web is adjacent to the cutting and bonding location and the second longitudinal axis is generally perpendicular to the first longitudinal axis;
forming a curvilinear seam between the first and second webs along a path extending into the second web, the path generally originating and terminating proximate the intersections of the first long edge of the second web and the first and second long edges of the first continuous web, respectively; and
cutting the first continuous web and second web generally along the path so that a first portion of the second web forms a fitted portion on the body portion of a first surgical drape and a second portion of the second web forms a screen portion attached to the body portion of a second surgical drape in the series of surgical drapes.

5,586,565

METHOD FOR VARYING TOBACCO ROD DENSITY AND TOBACCO RODS WITH VARYING DENSITY PRODUCED THEREBY

Jacques Babey, Pully; Brian Salmon, St-Legier; Eric De Borst, Belmont, and Bernard Tallier, Cortaillod, all of Switzerland, assignors to Philip Morris Incorporated, New York, N.Y.


Division of Ser. No. 259,718, Jun. 14, 1994, Pat. No. 5,501,233. This application Dec. 19, 1995, Ser. No. 575,108

Claims priority, application European Pat. Off., Jun. 16, 1993, 93810432

Int. Cl.⁶ A24C 5/14

U.S. Cl. 131—84.2

50 Claims



1. A method of varying the density of a rod of tobacco material comprising the steps of:
providing a rod of tobacco material;
compressing a first end region of a segment of the rod to increase the density;
compressing a first intermediate region of the rod segment spaced apart from the first end region; and
compressing a second end region of the rod segment, spaced apart from the first intermediate region, the intermediate region located between the first and second end regions, the first and second end regions defining a segment length for a subsequently formed cigarette rod cutting the rod at the first end region and second end region to form the cigarette rod.

5,586,564

INSTRUMENTATION AND SURGICAL PROCEDURE FOR DECOMPRESSION FOR MORTON'S NEUROMA


Stephen L. Barrett, and Michael G. Brown, both of The Woodlands, Tex., assignors to Instratek, Inc., Houston, Tex.

Filed Feb. 4, 1994, Ser. No. 192,167

Int. Cl.⁶ A61B 19/00; 17/32

U.S. Cl. 128—898

28 Claims



28. A surgical method for decompression for Morton's neuroma, comprising the steps of:
preparing the patient for surgery;
making a first incision in the patient's foot;
making a second incision in the foot;
dissecting between the metatarsal heads;
palpating the intermetatarsal ligament;
palpating the plantar aspect of the patient's arch;
inserting a cannula and trocar into the foot through the second incision;
making a third incision in the foot;
projecting the cannula and trocar through the third incision;
removing any adipose tissue which is in the cannula;
inserting an endoscope into the cannula;
inserting a cutting instrument into the cannula; and
manipulating the cutting instrument to sever the intermetatarsal ligament.

5,586,566

ZIG-ZAG METHOD OF BRAIDING HAIR


Ryeu K. Kim, 21100 Nashville St., Chatsworth, Calif. 91311, and Im S. Lee, #371-4 Geolpo-Ri, Kimpo-Up, Kimpo-Gon, Kyunggi-Do, Rep. of Korea

Filed Jul. 28, 1995, Ser. No. 508,706

Int. Cl.⁶ A45D 24/00

U.S. Cl. 132—200

1 Claim



1. A zig-zag method of braiding hair comprising a long braided lock of hair, folding said long braided lock of hair a plurality of times, wherein a resulting plurality of folds are equidistantly arranged forming a plurality of segments of said long braided lock of hair between each consecutive pair of said folds, said plurality of segments of said long braided lock of hair being parallel to one another, equidistantly arranged, and equal in length to one another, affixing a base transversely across said plurality of folds in which said folds are firmly attached to said base, and transversely cutting said plurality of segments through middle of said plurality of segments, thus resulting in two identical hair pieces.


5,586,567 DISHWASHER WITH TURBIDITY SENSING MECHANISM

John M. Smith; David A. Schneider, both of Louisville, Ky.; Mark E. Dausch, Latham, and Walter Whipple, III, Amsterdam, both of N.Y., assignors to General Electric Company, Louisville, Ky.

Filed Jan. 10, 1995, Ser. No. 370,795
Int. Cl.⁶ A47L 15/46

U.S. Cl. 134—57 D

10 Claims



1. A dishwasher comprising: a wash chamber for receiving fluid and articles to be washed in the fluid; a spray mechanism for spraying fluid into said chamber to remove soil from articles therein; a pump connected to said chamber, a conduit connecting said pump to said spray mechanism; said pump being selectively operable to withdraw fluid from said chamber and to supply the fluid to said spray mechanism through said conduit; a turbidity sensing mechanism including a transparent tube in fluid flow relationship with said conduit between said pump and said spray mechanism; a source of electromagnetic radiation directed into the fluid in said tube; a sensor detecting electromagnetic radiation propagated through the fluid in said tube and providing a frequency signal representative of the turbidity of the fluid in said tube; said turbidity sensing mechanism includes an elongated housing connected in said conduit, said transparent tube being mounted within said housing in fluid flow relationship with said conduit; said housing defining a cavity therein around said tube; said source of electromagnetic radiation being mounted in said cavity adjacent said tube and said sensor being mounted in said cavity adjacent said tube substantially opposite said source.

5,586,568 COVER ASSEMBLY AND METHOD FOR COVERING UNDERSINK PIPING


John A. Helmsderfer, 1033 Windsor Ct., Cincinnati, Ohio 45206

Continuation-in-part of Ser. No. 146,999, Oct. 29, 1993, Pat. No. 5,341,830. This application Jul. 7, 1994, Ser. No. 271,439
Int. Cl.⁶ F16L 7/00; 9/22

U.S. Cl. 137—15

14 Claims

1. An insulative cover for insulating a P-trap drain piping assembly located under a sink including multiple pipe sections joined at junctures, the pipe sections joined by fastening structures which have a larger outer diameter than an outer diameter of the respective pipe sections, the cover comprising: a first piece to be placed over a pipe section and having a diameter dimension and an end; and



- a second piece to be placed over a pipe section and having a diameter dimension and an end; when placed over the respective pipe sections of said P-trap assembly, the end of the first piece being adjacent the end of the second piece at a pipe juncture; a generally flexible collar structure configured to be slid along a portion of a pipe section and slid with respect to a portion of at least one of the first and second pieces, the collar structure being operably expandable for expanding its inner diameter and further being operable to be slid with respect to said piece away from the juncture so that the pipe sections may be joined together by the larger outer diameter fastening structure at said juncture, the expandable collar structure operable for expanding its inner diameter when the collar structure is subsequently slid over a portion of the juncture to cover said larger outer diameter fastening structure and form a generally continuous insulative cover over the joined pipe sections of the P-trap assembly.


5,586,569 PNEUMATIC PRESSURE REGULATOR

John R. Hanning, Wake Forest, and Daniel C. Olmsted, Youngsville, both of N.C., assignors to Parker-Hannifin Corporation, Cleveland, Ohio

Filed Jul. 27, 1995, Ser. No. 508,306
Int. Cl.⁶ G05D 16/02

U.S. Cl. 137—116.5

21 Claims



1. A fluid pressure regulator comprising a housing including a main body having formed therein an inlet port, an outlet port and an intersecting chamber between the inlet and outlet ports, the intersecting chamber having a longitudinal axis, a valve seat insert disposed in the intersecting chamber and having an insert body separating an upstream portion of the

intersecting chamber from a downstream portion respectively in fluid communication with the inlet and outlet ports, the insert body having a valve seat surrounding a valve seat opening.

a valve element including a valve head movable into and out of engagement with the valve seat for opening and closing the valve seat opening to control flow from the inlet port to the outlet port,

the insert body having a peripheral edge in supportive engagement with a sealing surface on the main body, the peripheral edge and sealing surface being inclined to the longitudinal axis of the intersecting chamber and having a seal therebetween to provide fluid tight engagement of the insert body with the housing, and the insert body including a passage for directing the flow of fluid from the valve seat to the outlet port.

5,586,570 DIRECTIONAL CONTROL VALVE

Yoshihiro Fukano, and Yoshitada Dol, both of Ibaraki-ken, Japan, assignors to SMC Kabushiki Kaisha, Tokyo, Japan

PCT No. PCT/JP94/00640, § 371 Date Dec. 18, 1995, § 102(e)

Date Dec. 18, 1995, PCT Pub. No. WO95/28591, PCT Pub.


Date Oct. 26, 1995

PCT Filed Apr. 18, 1994, Ser. No. 553,553

Int. Cl.⁶ F15B 13/02; F16K 27/00

U.S. Cl. 137—271

10 Claims



1. A directional control valve comprising a supply port, an output port, a discharge port, a valve body having a valve hole communicating with the supply, output, and discharge ports, and a valve body displaceable in the valve body for controlling the direction of flow of a fluid under pressure, characterized in that:

said valve body has a supply passage and discharge passages extending therethrough in a direction in which directional control valves are arrayed, and first and second output ports communicating with said valve hole;

said supply port, said first output port, and said discharge port being defined in a first side surface of the valve body at positions for communication with corresponding openings in a manifold base for installing the directional control valve thereon, said supply port and said discharge ports being defined for communication with said supply passage and said discharge passage, respectively;

said second output port being defined in a second side surface of the valve body in opposite confronting relation to said first side surface thereof;

further comprising:

attachment means in said first side surface of the valve body for attaching a closure member for closing said supply port, said first output port, and said discharge port.

5,586,571 APPARATUS AND METHOD FOR REPLACING THE DIVERTER VALVE ASSEMBLY IN A FAUCET


Pedro M. Guillermo, 501 Mayo Rd., Glen Burnie, Md. 21061

Filed Sep. 15, 1994, Ser. No. 306,380

Int. Cl.⁶ F16K 43/00

U.S. Cl. 137—315

4 Claims



1. A kit containing a plurality of tools for removing different components of a diverter valve from a faucet comprising a container including a tang and flat shoulder tool capable of fitting in registry with the annular top and opposing slots of the diverter valve for removal of a portion thereof, a tapped end tool capable of receiving and holding a threaded tube upper end of the diverter valve, an expanding split sleeve tool for removing the top half portion of the diverter valve, an elongated wedge tool capable of removing a separated bottom end of the detached threaded tube of the diverter valve and an elastomeric wedge tool for use in removing the plastic broken bottom end portion of the diverter valve.

5,586,572 HYDROTHERMAL STABILIZER


William J. Lund, Stockton, Calif., assignor to ACT Distribution, Inc., Newport Beach, Calif.

Filed Mar. 30, 1994, Ser. No. 219,973

Int. Cl.⁶ F16K 49/00


U.S. Cl. 137—337

10 Claims



1. Plumbing apparatus for reducing energy consumption of a hot water heater, said plumbing apparatus comprising: a tank means for containing water, said tank means having a top with a water inlet therein and a bottom with a water outlet therein; a buoyant piston, having an air volume therein, and said buoyant piston being movably disposed within said tank means and having a perimeter slidably engaging an inside wall of said tank means; and means for enabling water entering the water inlet to pass by the buoyant piston when the buoyant piston is displaced to a selected lower position in said tank means by the entering


5,586,579
COMBINATION BALL VALVE AND PRESSURE RELIEF
VALVE ASSEMBLY
Matthew D. Diehl, St. Albans, Vt., assignor to Martin Marietta
Corporation, Bethesda, Md.
Filed Nov. 15, 1995, Ser. No. 559,752
Int. Cl.⁷ F16K 15/18
U.S. Cl. 137—614.17
11 Claims



1. A valve assembly comprising, in combination:
first and second valve ports for connections into a fluid circuit;
a valve element movable between a closed valve position sealing at least one of the first and second valve ports and an open valve position accommodating fluid flow between the first and second valve ports; and
a relief valve incorporated in the valve element to permit pressure-relieving fluid flow between the first and second valve ports in response to excessive valve fluid pressure when the valve element is in the closed valve position.

5,586,580
**APPARATUS AND METHOD FOR INTERNALLY
SEALING PIPES**
Allan T. Fisk, Needham, and David I. Freed, Waltham, both of
Mass., assignors to Gas Research Institute, Chicago, Ill.
Filed Apr. 3, 1995, Ser. No. 415,267
Int. Cl.⁶ F16L 55/162

U.S. Cl. 138—98 **21 Claims**



1. An apparatus for applying sealant to leaks and joints along an inside surface of a pipe, the pipe having an axis extending along the length thereof,
the apparatus comprising:
a push snake for insertion into a pipe and removal from the pipe through a single point of entry, the push snake including a distal end, a proximate end and a mid-section,
the distal end of the push snake including a head, the head including an applicator tip and a motor for rotating the applicator tip about the axis of the pipe,
the proximate end of the push snake being connected to a pressurized supply of sealant, the pressurized supply of sealant being disposed outside of the pipe, the push snake providing communication between the pressurized supply of sealant and the applicator tip.

the applicator tip includes at least one delivery tube in communication with the pressurized supply of sealant, the applicator tip also including a flat disk which is rotated by a motor, the motor does not impart rotation to the delivery tube, sealant is applied to the inside surface of the pipe when pressurized sealant is ejected from the delivery tube onto a front side of the disk during rotation of the disk, the applicator tip further including a pair of flaps pivotally attached to the applicator tip and biased into a position parallel to the axis of the pipe and the snake when the applicator tip is not spinning, the flaps being forced radially outward into a position perpendicular to the axis of the pipe when the applicator tip is spinning.

5,586,581

**CLOTH ROLL DRIVING APPARATUS FOR DRIVING
THE CLOTH ROLL AT TWO DIFFERENT SPEEDS**

Mitsuru Suwa, Kanazawa, Japan, assignor to Tsudakoma
Kogyo Kabushiki Kaisha, Ishikawa, Japan


Filed Dec. 8, 1995, Ser. No. 569,519

Claims priority, application Japan, Dec. 22, 1994, 6-336247

Int. Cl.⁶ D03D 49/20

U.S. Cl. 139—304

7 Claims



1. A cloth roll driving apparatus for taking up a cloth around a cloth roll, which comprises:
 - a drive source adapted to be driven in synchronism with a main shaft of a weaving machine;
 - a slave shaft coupled to a cloth roll;
 - a drive shaft coupled to the drive source;
 - a first power transmission mechanism provided with a one-way clutch and adapted to transmit, through the one-way clutch, rotation of the drive shaft to the slave shaft as a torque in a direction in which the cloth is taken up and at a velocity corresponding to the weaving velocity of the cloth; and
 - a second power transmission mechanism provided with a clutch mechanism which is coupled to the slave shaft during the time of winding of the cloth around the cloth roll when the cloth roll is empty and adapted to transmit, through the clutch mechanism of the second power transmission mechanism, the rotation of the drive shaft as a torque in the same direction as the torque transmitted to the slave shaft by the first power transmission mechanism and at a velocity higher than said velocity corresponding to the weaving velocity of the cloth.

5,586,582

**SUPPORT ASSEMBLY FOR A PLANETARY-TYPE
SELVAGE UNIT ON A LOOM**

Yasuo Nakada, Ishikawa-ken, Japan, assignor to Tsudakoma
Kogyo Kabushiki Kaisha, Japan


Filed Jun. 6, 1995, Ser. No. 469,661

Claims priority, application Japan, Sep. 27, 1994, 6-257443

Int. Cl.⁶ D03D 47/40

U.S. Cl. 139—430

4 Claims



1. A support assembly for a planetary gear train type selvage unit on a loom comprising

- a slide base adapted to be mounted atop a back top stay of said loom in an arrangement slidable in the width direction of said loom and adapted to rotatably carry a drive shaft for a drive gear of said planetary-type selvage unit,
- a support bracket having a proximal end adapted to be swingably mounted to said drive shaft and having a distal end adapted to support said planetary-type selvage unit, and
- a locker unit including a first element mounted to said slide base, a second element mounted to said support bracket and a third element for detachably engaging said first element with said second element,

whereby said support bracket is adapted to be swingable on said drive shaft between an operative position suited for a weaving operation and a stand-by position suited for a looming operation.

5,586,583

FLUID EXCHANGER WITH FLUID RECONCILIATION
Robert W. Edwards, Ooltewah; Terry M. Fulmer, Chattanooga, and Patrick J. Schultz, Hixson, all of Tenn., assignors to Tokheim Corporation, Fort Wayne, Ind.

Continuation of Ser. No. 114,377, Aug. 30, 1993, abandoned, which is a continuation of Ser. No. 823,850, Jan. 22, 1992, Pat. No. 5,273,085. This application Sep. 19, 1994, Ser. No. 308,395

Int. Cl.⁶ B65B 1/30; 3/26


U.S. Cl. 141—83 **8 Claims**

1. A computerized fluid exchange and reconciliation apparatus for engines, said apparatus comprising:

input means for displaying an operator query and providing an input signal based on an operator response;

computer means for receiving and processing said input signal, said computer means generating an output signal based on said input signal and a predetermined program; and

operating means responsive to said output signal to convey a measured volume of liquid from and to an engine.



5,586,584


FENCING TOOL AND METHOD OF OPERATION

Pol N. Haldemann, P.O. Box 879, Chinook, Mont. 59523

Continuation-in-part of Ser. No. 122, Jan. 2, 1987, Pat. No. 5,303,748. This application Mar. 11, 1994, Ser. No. 212,341

Int. Cl.⁶ B21F 9/02

U.S. Cl. 140—123.5 3 Claims



1. A method of securing fencing wire to a post, said method comprising the steps of:
 - a) providing a fencing tool having a first elongate portion with a working end and a handle end and a second elongate portion with a working end and a handle end joined at a pivot to said first elongate portion between the working end and the handle end of both the first and the second elongate portions wherein said second elongate portion is provided with a fulcrum bar located between said working end and said pivot and wherein said handle end of said first elongate portion and said handle end of said second elongate portion are both provided with wire-gripping surfaces to grip the fencing wire between said surfaces;
 - b) forming a loop in a free end of the fencing wire;
 - c) providing a bight in the fencing wire;
 - d) running the free end of the fencing wire containing the formed loop about the post and back upon a portion of the fencing wire so as to be in a substantially parallel spaced relationship with the bight;
 - e) inserting said loop in the free end of the fencing wire over said fulcrum bar;
 - f) engaging the bight of the fencing wire with said wire-gripping surfaces to form a pivot point between the loop and the bight;
 - g) applying force directed towards the post to said first and said second handle ends to stretch the fencing wire;
 - h) twisting the free end of the fencing wire around said portion by rotating said fencing tool about the bight so as to secure the stretched fencing wire to the post; and
 - i) removing the loop from over the fulcrum bar.

5,586,585


DIRECT LOADLOCK INTERFACE

Anthony C. Bonora, Menlo Park, and Joshua T. Oen, Newark, both of Calif., assignors to Asyst Technologies, Inc., Fremont, Calif.

Filed Feb. 27, 1995, Ser. No. 394,698
Int. Cl.⁶ B65G 65/00

U.S. Cl. 141—93

41 Claims



1. A loadlock chamber for transferring at least one semiconductor wafer supported within a support structure from a pod into a wafer fabrication process chamber without exposing the at least one semiconductor wafer or support structure to an atmosphere exterior to the pod and loadlock chamber, the pod including a pod door and a pod cover mating with the pod door, the loadlock chamber comprising:

- means for receiving the pod;
- means for separating the support structure from the pod door and pod cover prior to loading the support structure into an interior of the loadlock chamber without exposing the support structure or at least one semiconductor wafer to the atmosphere exterior to the pod and loadlock chamber; and
- means for loading the support structure into said interior of the loadlock chamber without exposing the support structure or at least one semiconductor wafer to the atmosphere exterior to the pod and loadlock chamber, said interior including means for allowing transfer of the at least one semiconductor wafer from said interior to the wafer fabrication process chamber.

5,586,586


UNITIZED FUEL STORAGE SYSTEM

Manfred M. Flech, c/o Euro Tank, P.O. Box 478, Silver Springs, Fla. 33489-0478

Continuation-in-part of Ser. No. 988,836, Dec. 10, 1992, Pat. No. 5,390,713. This application Feb. 2, 1995, Ser. No. 383,505
Int. Cl.⁶ B67D 5/60

U.S. Cl. 141—98

15 Claims



1. A unitized tank structure comprising:
a vessel having at least first and second compartments;

fill lines coupled to the vessel providing access to fill said first and second compartments of said vessel with fuel;
at least one sump riser portion coupled to the vessel and extending therefrom;
at least first and second dispensing lines for dispensing fuel from the vessel, said dispensing lines being disposed within the sump riser portion and penetrating the vessel, each dispensing line extending within said vessel and within an associated one of said first and second compartments, said sump riser portion being constructed and arranged to contain fuel which may leak from said dispensing lines; and
cross-over venting structure disposed within said vessel constructed and arranged to balance pressure in said first and second compartments when dispensing fuel from a compartment.

5,586,587


HIGH RATE PRESSURE VESSEL FILLING PROCESS

Daniel R. Leininger, Layton, and Walter A. Moore, Ogden, both of Utah, assignors to Morton International, Inc., Chicago, Ill.

Filed Jun. 14, 1995, Ser. No. 490,186
Int. Cl.⁶ B65B 31/00

U.S. Cl. 141—196

14 Claims



1. A method of filling a pressure vessel with a required gas mass comprising:

- (a) flowing gas from a source thereof into a chamber having a set volume V;
- (b) measuring the temperature of the gas in the chamber;
- (c) controlling the temperature of the gas in the chamber;
- (d) measuring the pressure of the gas in the chamber;
- (e) utilizing the relationship

$$P = \frac{mRT}{MWV}$$

where P is the pressure of the gas in the chamber, m is the target gas mass, MW is the molecular weight of the gas, V is the volume of the chamber, R is the universal gas constant, and T is the temperature of the gas in the chamber, correlating the measured pressure P through a feedback system to controlling the temperature of the gas in the chamber, the temperature measurement T, and the set volume V of the chamber to establish a gas mass in the chamber by the flow of gas therinto; and

- (f) once the required gas mass is accurately established in the chamber, rapidly discharging the gas mass from the chamber into the pressure vessel and immediately sealing the pressure vessel.

5,586,588

APPARATUS AND METHOD FOR PRESSURIZING AND DRAFTING LIQUID CONTAINED WITHIN FOOD-GRADE CONTAINERS


Lee B. Knox, 310 Adams Ave., Endicott, N.Y. 13760

Filed Dec. 21, 1994, Ser. No. 361,204

Int. Cl.⁶ B65B 1/04; 3/04; B67C 3/00

U.S. Cl. 141—285

21 Claims



1. An apparatus for use in pressurizing a liquid contained within an interior portion of a container and drafting the liquid from the container which includes a neck portion having external threads, said apparatus comprising:

- a cap having a generally cylindrical body section and internal threads formed on said body section which are adapted to threadingly engage the external threads of the neck portion of the container and an annular flange attached to and protruding radially from said body section toward a central opening;
- a fluid fitting assembly extending through said central opening in said cap and adapted to be secured to the neck portion by said cap, said fluid fitting assembly including a body section and a nipple assembly having an annular flange attached to and circumventing said body section of said nipple assembly, said annular flange of said nipple assembly being disposed inward of and in radially overlapping relationship with said annular flange of said cap, said nipple assembly including a first nipple for accepting a fluid from an external source for injection into the container and a second nipple for dispensing fluid from the container;
- a draw tube having a first end attached to said second nipple, a second end immersed in the liquid, and an interior flow passage extending longitudinally between said first and second ends;

wherein said first nipple and said second nipple each include an outer portion attached to and protruding from an outer surface of said body section and adapted to be disposed externally of the container, an inner portion attached to and protruding from an inner surface of said body section within the interior portion of the container and an interior flow passage extending longitudinally through said inner and outer portions of the corresponding one of said first nipple and said second nipple, said interior flow passage of said first nipple is in fluid communication with the external source of the fluid and with the interior portion of the container and said interior flow passage of said second nipple is in fluid flow communication with said interior flow passage of said draw tube such that said draw tube and said second nipple combine to permit at least a portion of the liquid to be dispensed from the container through said exterior portion of said second nipple, said inner portion of said first nipple is disposed above the liquid within the container;

an annular seal surrounding said body section of said nipple assembly and disposed inward of said annular flange of said nipple assembly, said annular flange of said cap urges said annular seal into sealing engagement with said annular flange of said nipple assembly and the neck portion of the container when said cap is screwed onto the neck portion;

a check valve having first and second spaced apart holes extending therethrough disposed within the neck portion of the container and attached to said nipple assembly, said check valve having a generally circular shape and being fabricated from a resilient material which is substantially impermeable to the flow of fluid therethrough, said check valve flexes way from said inner portion of said first nipple so as to permit fluid to flow through said interior flow passage of said first nipple into the interior portion of the container when the pressure within said interior flow passage of said first nipple exceeds the pressure within the container by a predetermined differential pressure and said check valve is urged against said inner portion of said first nipple so as to close said interior flow passage of said first nipple thereby preventing fluid to flow outward through said first nipple when the pressure within the container exceeds the pressure within said interior flow passage of said first nipple;

a center post protruding from an inner surface of said body section of said nipple assembly and extending through one of said first and second holes and said inner portion of said second nipple extends through the other of said first and second holes; and
means for retaining said check valve.

5,586,589

REFILLABLE CLOSED CONTAINER SYSTEM


Scott C. Voelker, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

Filed May 19, 1995, Ser. No. 445,362

Int. Cl.⁶ B65B 1/04; 3/00

U.S. Cl. 141—349

31 Claims



1. A refillable closed container system comprising
a closed container having an upper wall and an opening in the upper wall through which the container can be filled and emptied,
a valve body in the container opening having a flow passage therethrough for permitting flow into and out of the container,
a magnetically attractable valve member in the valve body movable between a closed position for blocking flow through the passage and an open position for permitting flow through the passage, said valve member being gravity biased toward its closed position when the container is upright to inhibit unauthorized filling of the container through said passage and being movable toward an open position to permit emptying of the container through said passage,
a magnet carrier securable with respect to the container in a position adjacent the valve body,
a magnet carried by said magnet carrier for magnetically moving the valve member toward an open position when the magnet carrier is secured with respect to the container and the con-

tainer is upright thereby to permit refilling of the container when the container is upright.


5,586,590

COUPLER FOR FLUID DELIVERY SYSTEM

Ronald J. Venooker, Franklin; John A. Scavitto, Mendon; Peter N. Karkantis, Acton; David T. Healey, No. Reading, and Richard L. Travers, Seltuate, all of Mass., assignors to Ciba Corning Diagnostics Corp., Medfield, Mass.
Division of Ser. No. 165,137, Dec. 9, 1993, abandoned. This application Aug. 11, 1995, Ser. No. 513,697
Int. Cl.⁶ B65D 47/00

U.S. Cl. 141—386

6 Claims



1. A coupler for an aspirating fluid delivery system for conveying liquid from a source of liquid to be aspirated to a manifold fitting on an analytical instrument, said coupler comprising:

- (a) a main body portion which has a central longitudinal axis, an elongated outer surface which is substantially parallel to said longitudinal axis, and an elongated liquid passageway which is substantially parallel to said longitudinal axis;
- (b) a first end portion at one end of said main body portion which has a first end opening to said liquid passageway for operatively connecting said liquid passageway to said source of liquid; and
- (c) a second end portion at the opposite end of said main body portion from said one end, said second end portion having a connector fitting which is complementary with said manifold fitting, said connector fitting having a first tab which extends transversely away from said longitudinal axis and a second tab which extends transversely away from said longitudinal axis, one of said tabs having a stop flange at a first widthwise side of said one tab which extends toward said first end portion, said one tab having a bevelled cam surface at a second widthwise side of said one tab, said bevelled cam surface facing away from said stop flange and said first end portion.

5,586,591


ROUTER ACCESSORY FOR PRODUCING CUTS HAVING A CONTOURED DEPTH

George G. Gaydos, 509 Peebles Apt #3, Pittsburgh, Pa. 15221
Filed Nov. 15, 1994, Ser. No. 339,798
Int. Cl.⁶ B27C 5/10; B27M 3/00

U.S. Cl. 144—145.2

9 Claims

1. A router accessory comprising:
- a housing having a router attaching portion;
 - a plate for fixedly holding a work piece, said plate having a plurality of arms extending therefrom; and
 - a plurality of track mechanisms attached to said housing, said arms slidably attached to the track mechanism so that the plate can be guided in a desired path relative to the router.




5,586,592

ROLLING SHUTTER AND SHUTTER DRIVE

Thomas McGregor, 1621 S. Ivanhoe St., Anaheim, Calif. 92804
Filed Apr. 25, 1995, Ser. No. 428,900
Int. Cl.⁶ E06B 9/08

U.S. Cl. 160—133

19 Claims



1. A rolling shutter covering an area comprising:
- a shutter element array having a plurality of elongated shutter elements and a plurality of elongated links intercoupling said shutter elements;
 - a take-up roll coupled to said shutter element array for rolling said shutter element array;
 - a shutter drive operatively coupled to said shutter element array for moving said shutter element array to and from said take-up roller; and
 - shutter guide means for guiding said shutter element array into a position overlying said area.
- said elongated links including at least one set formed of an apex link coupled to a pair of said shutter elements and a pair of angle links coupled to each of said shutter elements in said pair such that said pair of shutter elements form an included angle therebetween less than one hundred eighty degrees when said shutter element array is compressively loaded.

5,586,593

PARTITIONING SYSTEM

David L. Schwartz, Florence, Ala., assignor to Hunt Holdings, Inc., Wilmington, Del.


Filed Jun. 30, 1995, Ser. No. 497,558

Int. Cl.⁶ A47G 5/00

U.S. Cl. 160—135

12 Claims

1. A partition construction comprising a core having a rectangular frame with panels of relatively rigid sheet material overlying each side of said frame and extending beyond the top and side edges of the frame to form U-shaped channels along said top and



5,586,595

CURTAIN ATTACHMENT CONNECTOR

Toshiaki Takizawa, and Kazuo Iwai, both of Toyama-ken, Japan, assignors to YKK Corporation, Tokyo, Japan

Filed Sep. 27, 1995, Ser. No. 534,827


Claims priority, application Japan, Sep. 30, 1994, 6-236370

Int. Cl.⁶ A47H 1/00

U.S. Cl. 160—330

11 Claims

side edges, a top tube centrally disposed within said top edge U-shaped channel and attached to said frame, side tubes centrally disposed within said side edge U-shaped channels and attached to said frame, said top tube extending over the upper ends of said side tubes, side edge members for covering the side edge U-shaped channels, a top edge member for covering the top edge U-shaped channel except for an end portion thereof, a demountable top cap for covering the top U-shaped channel end portion not covered by said top edge member, a receiver mounted over said end portion to be covered and secured on an end of said top tube for demountably receiving said top cap, said receiver including a plurality of ribbed side edge slots which are elongated in direction parallel to said top edge, said top cap including a plurality of prongs aligned with said receiver slots, said prongs being shorter than the depth of the slots, said ribbed slot side edges holding said top cap prongs in a desired position, permitting both vertical and horizontal adjustment.



5,586,594


INFLATABLE WALL

Stanley N. Shapoff, 816 Coronado Ct., San Diego, Calif. 92109
Filed Nov. 17, 1995, Ser. No. 559,986

Int. Cl.⁶ A47G 5/00

U.S. Cl. 160—135

15 Claims



1. An inflatable wall comprising:

- a wall panel including:
- a pliable skin defining an inflatable enclosure; said skin including:
- a first sheet generally defining a first side of said enclosure; said first sheet having an inner side and an outer side; and

1. A curtain attachment connector movable along a guide member, being disposed between said guide member and a curtain having a number of male or female engaging faces at predetermined intervals on and along the upper edge, and having engaging faces which engage with said engaging faces of said curtain, said curtain attachment connector comprising a plate-like fastener member having said engaging faces, and an attachment extending from one end of said fastener member and adapted to be mounted to said guide member,

wherein said engaging faces of said fastener member including first and second engaging faces composed of a multiplicity of hooks rising from front and back sides of said fastener member, and

wherein said first and second engaging faces having different engaging strengths from each other.

5,586,596

DIE CAST VENT BLOCK

Lewis G. Freeman, 1509 Pontiac Dr., Kokomo, Ind. 46902


Filed Sep. 26, 1994, Ser. No. 312,308

Int. Cl.⁶ B22D 17/14; 17/20

U.S. Cl. 164—253

18 Claims


1. A vacuum valve device in combination with a die pair comprising:
- a first and a second die having a cavity and defining a parting line;
 - an ejector die block adapted to be coupled with said first die and including a slot adapted for enabling flow of a molten material from said cavity;



a shut-off piston disposed within said ejector die block;
a cover die block adapted to be coupled with said second die;
a complementary surface for said shut-off piston disposed within said cover die block;
vent block means for preventing flow of said molten material, said vent block means including a first vent block having a plurality of lands and an alternating plurality of grooves, adjacent lands and grooves forming an overall oval shape when viewed in plan;
a second vent block having a plurality of lands and an alternating plurality of grooves, adjacent lands and grooves forming an overall oval shape when viewed in plan, a parting line defined by said first and second vent blocks, wherein said first and second blocks mate with one another to define a serpentine path, in cross-section, which path enables overflow of molten material to flow in and out of the parting line as well as to cool, solidify and stop; and
control means for controlling said shut-off piston.


5,586,597 METHOD TO PREVENT/MITIGATE STEAM EXPLOSIONS IN CASTING PITS

Rusi P. Taleyarkhan, Knoxville, Tenn., assignor to Lockheed Martin Energy Systems, Inc., Oak Ridge, Tenn.
Filed Dec. 18, 1995, Ser. No. 573,813
Int. Cl.⁶ B22D 11/24; 11/22
U.S. Cl. 164—487 17 Claims



1. A method of preventing and mitigating a steam explosion in a casting pit, comprising the steps of:
(a) providing a casting pit having a bottom and a cooling water reservoir;
(b) providing a floor system, having perforations, positioned in said cooling water reservoir in said casting pit; and
(c) introducing a compressed gas upward through said floor system into said cooling water reservoir during a casting operation.


5,586,598
HEAT EXCHANGER
Hiroshi Tanaka, Iseaki, and Kazuki Hosoya, Sawa-gun, both of Japan, assignors to Sanden Corporation, Gunma, Japan
Filed Dec. 21, 1994, Ser. No. 361,301
Claims priority, application Japan, Dec. 21, 1993, 5-346144
Int. Cl.⁶ F28F 1/40
U.S. Cl. 165—133 6 Claims



1. A heat exchanger comprising:
a pipe means for directing a first fluid to flow therethrough, said pipe means including at least one flat tube member across an exterior of which a second fluid flows laterally; and
dispersing means for dispersing the flow of the first fluid, as the first fluid flows through said pipe means, including a plurality of projected stripes fixedly disposed on an inner surface of said at least one flat tube member;
wherein each of said projected stripes has a first and a second side wall and an inner edge therebetween and said plurality of projected stripes are arranged to diagonally extend along said at least one flat tube member and said projected stripes include first portions which project from a lower inner surface of said at least one flat tube member and second portions which project from an upper inner surface of said at least one flat tube, such that said first and second portions of the projected stripes intersect with one another, and said first and second portions of said projected stripes are fixed with one another at said intersections therebetween;
wherein said flat tube member includes a clad construction, said clad construction comprising a base metal member and an inner brazing metal member fixedly connected to an inner peripheral surface of said base metal member only along said inner edge of said projected stripes.


5,586,599
HEAT EXCHANGER
Anders Sjöström, Lund, Sweden, assignor to Tetra Laval Holdings & Finance SA, Pully, Switzerland
Filed Oct. 17, 1994, Ser. No. 323,687
Claims priority, application Sweden, Oct. 21, 1993, 9303466; Jun. 10, 1994, 9402029
Int. Cl.⁶ F28F 9/26
U.S. Cl. 165—143 16 Claims

1. A heat exchanger comprising:
a plurality of heat exchanger elements having at least one heat transfer tube for conveying a first fluid and a tubular jacket surrounding said at least one heat transfer tube for conveying a second fluid;
a plurality of modular units connected to the tubular jackets for supporting the heat exchanger elements;
at least one jacket connection element having two tubular elements connected by a connecting element, said connecting element conveying said second fluid from one of said two tubular elements to the other, said at least one jacket connection element being connected at a first end to two neighboring tubular jackets by two of said modular units;



at least one elbow pipe connecting the heat transfer tubes in two neighboring heat exchanger elements for conveying said first fluid; and
a coupling adapted to engage four mutually adjacent modular units.


5,586,600
HEAT EXCHANGER
John C. Cribari, Oakland, Mich., assignor to Valeo Engine Cooling, Inc., Jamestown, N.Y.
Filed Oct. 26, 1994, Ser. No. 329,547
Int. Cl.⁶ F28F 9/02
U.S. Cl. 165—173 10 Claims



1. A tank part for connection to a header part to form a heat exchanger manifold, which tank part comprises an elongate generally channel-shaped member and at least one partition member fitted in the channel to extend transversely thereacross, wherein the tank part is provided with inwardly deformed regions on opposite sides of the at least one partition member in the longitudinal direction of the tank part to retain the at least one partition in position, wherein the inwardly deformed regions have inwardly protruding dimples formed in the wall of the tank part, and wherein two pairs of dimples are provided for the at least one partition.
9. A method of assembly of a tank part for a heat exchanger manifold of the type having separate tank and header parts joined to form a tubular manifold comprising the steps of:
a) providing a generally channel-shaped tank part and at least one partition member;
b) fitting the at least one partition member into the channel to extend transversely across the channel;
c) inwardly deforming the tank part on opposite sides of the at least one partition member to retain this in position; and

wherein in step c) a punch tool directed at the outside of the tank part is employed to form inwardly protruding dimples.


5,586,601
MECHANISM FOR ANCHORING WELL TOOL
Ronald E. Pringle, Houston, Tex., assignor to Camco International Inc., Houston, Tex.
Filed Apr. 28, 1995, Ser. No. 431,876
Int. Cl.⁶ E21B 33/128; 33/129
U.S. Cl. 166—212 14 Claims



11. A mechanism for anchoring a well tool to a casing, comprising: a plurality of slip members carried on a well tool; a plurality of pistons each operatively connected to one of the slip members so that upon introduction of hydraulic fluid thereto each of the slip members is individually moved into engagement with an interior surface of the casing; and means to individually retract the slip members whereby axial rotational movement of a housing carried in the well tool causes each of the slip members pistons to retract.

5,586,602
METHOD AND APPARATUS FOR SHOCK WAVE
STIMULATION OF AN OIL-BEARING FORMATION
Vladimir P. Vagin, Moscow, Russian Federation, assignor to Nefteotdacha, Ltd., Moscow, Russian Federation
Filed Nov. 9, 1995, Ser. No. 555,421
Claims priority, application Russian Federation, Apr. 11, 1995, 95104938
Int. Cl.⁶ E21B 43/25
U.S. Cl. 166—249 14 Claims

11. A method for imparting periodic elastic wave stimulation to the accumulation zone of an oil field having a plurality of producing wells, comprising the steps of selecting at least one well for wave generation; sealing the wave generation well so it is capable of functioning as a closed system; filling the well with a fluid; compressing an upper portion of the fluid in the well; suddenly releasing the compressed fluid into the remaining fluid, thereby creating a compression shock wave that travels to the well bottom; and repeating the steps of compressing and releasing the fluid.




5,586,603

SPIKES FOR FIELD AERATOR

Henry J. Mattis, 601 Shoshone #15, Cheyenne, Wyo. 82009
Continuation-in-part of Ser. No. 217,972, Mar. 25, 1994, Pat.
No. 5,460,229. This application Sep. 6, 1995, Ser. No. 524,245
Int. Cl.⁶ A01B 45/02

U.S. Cl. 172—21

6 Claims



1. In field aerator apparatus of the type having a rotatable drum member and a plurality of band members carried on the periphery of the drum; wherein the band members are adjustably movable axially along the drum; wherein the improvement comprises a plurality of elongated spike members each having a base end and a tapered free end, wherein the base end includes a plurality of attachment apertures therethrough and the base end is attached to said band members by means of said plurality of attachment apertures; wherein said tapered end defines an angle in the range of about 15° to 30°; wherein said spike member has a thickness in the range of about 0.3 to 1 inch; and wherein said spike member has a length of about 10 to 15 inches.

5,586,604


AERATOR

Leonard F. Postema, 830 Ranchwood Trail, Woodstock, Ga.
30188

Continuation-in-part of Ser. No. 508,322, Jul. 27, 1995, which
is a continuation-in-part of Ser. No. 252,244, Jun. 2, 1994.
This application Jan. 11, 1996, Ser. No. 584,980
Int. Cl.⁶ A01B 45/02

U.S. Cl. 172—21

22 Claims



1. An aerator assembly for attachment to a deck of a lawn mower to aerate the soil of a lawn as the mower moves across the ground, said aerator assembly comprising:

a frame adapted to be mounted to the deck of the mower with said frame extending a predetermined distance rearwardly of the mower deck;

an elongated caster pin mounted to said frame for rotation about its longitudinal axis, said caster pin being oriented substantially vertically to extend from an upper end portion of said caster pin downwardly to a lower end portion of said caster pin;

a first pivot plate axle secured at one end to said lower end portion of said caster pin, said pivot plate axle extending substantially horizontally from said lower end of said caster pin to a free end of said pivot plate axle;

a pivot plate having a proximal end portion and a distal end portion, said pivot plate being substantially planar and being pivotally mounted at its proximal end portion to said free end of said first pivot plate axle for substantially vertical pivotal motion of said pivot plate between a lowered position relative to said first pivot plate axle and a raised position relative thereto;

a substantially circular weighted wheel having a predetermined weight and being mounted to said pivot plate adjacent its distal end for rotation of said weighted wheel about a substantially horizontal axis, said weighted wheel rolling on the ground when said aerator assembly is attached to the mower and said pivot plate is in said lowered position, said caster pin, pivot plate, and weighted wheel forming a caster assembly adapted to follow the mower as it moves across a lawn;

a spiked aerator wheel having a plurality of substantially radially projecting curved tines extending outwardly from a central hub, said aerator wheel rotatably mounted to said pivot plate at a location intermediate said proximal end portion of said pivot plate and the mounting location of said weighted wheel, said spiked aerator wheel being mounted for rotation about a substantially horizontal axis and being positioned on said pivot plate so that the weight of said weighted wheel causes said tines of said aerator wheel to be driven into the ground to aerate the soil as the mower to which said aerator assembly is attached moves across the lawn.

5,586,605


MULTI-WALL TIE APPARATUS

Robert I. Paterson, London, and Brian A. Breeze, Wallsend,
both of England, assignors to Helifix Ltd., Bickinghamshire,
United Kingdom

Continuation-in-part of Ser. No. 204,465, Feb. 28, 1994, abandoned. This application Jun. 30, 1995, Ser. No. 491,358
Int. Cl.⁶ B25C 5/13

U.S. Cl. 173—4

7 Claims



4. An adapter for use with a hammer drill for reciprocatingly driving a helical tie between walled members, comprising, in combination:

a hollow hand grip of tubular cross-section, said grip having two ends and a hollow;

a drive pin positioned interiorly of the hand grip;

said drive pin having a shaft;

said drive pin being slidable within the hollow of the hand grip; an SDS engaging means;

said shaft having two ends, one end being rigidly secured to the SDS engaging means, and the other end terminating in a helical tie engaging means for receiving a portion of the helical tie therein;

a spring coaxially mounted along the shaft of the drive pin; and a tubular guide shaped to fit within one end of the hand grip, said tubular guide being shaped to receive the helical tie, whereby the helical tie can be inserted into the tubular guide and seated within the helical tie engaging means of the shaft and, thereafter, reciprocatingly driven into the walled members.

5,586,606

SYSTEM FOR LUBRICATING AND RECIPROCATING A PISTON IN A FLUID-ACTIVATED, PERCUSSIVE PAVING BREAKER

Robert R. Kimberlin; Steven W. Bodell, both of Troutville; Ted C. Chang; Robert M. Diesel, both of Roanoke, and Scott Barker, Daleville, all of Va., assignors to Ingersoll-Rand Company, Woodcliff Lake, N.J.

Division of Ser. No. 282,356, Jul. 29, 1994, Pat. No. 5,524,714.
This application Oct. 17, 1995, Ser. No. 545,443
Int. Cl.⁶ B25D 17/04

U.S. Cl. 173—62

1 Claim

1. A system for simultaneously lubricating and reciprocating a piston within a bore of a housing of a fluid-activated paving breaker comprising:

(a) said housing having a rear housing portion, with said bore extending axially therethrough forming a rear housing bore;

(b) handles mounted on said rear housing portion adjacent said rear housing bore;


(c) an inlet port for transmitting high pressure fluid into said rear housing bore;

(d) valve assembly means removably mounted in said rear housing bore, for communicating high pressure fluid with a drive chamber and low pressure fluid with a return chamber in said housing bore, whereby said piston is reciprocated, said valve assembly means positioned axially within said rear housing bore with respect to said inlet port so that high pressure fluid contacts a top surface of said valve assembly means when said inlet port is opened;

(e) means for retaining said valve assembly means within said rear housing bore;

(f) means for injecting a lubrication fluid into said rear housing bore through said rear housing portion;

(g) means for opening and closing said inlet port; and



(h) said means for retaining said valve assembly means within said rear housing bore further comprising:

(a) a valve housing plug, substantially the same cross-sectional shape and size as said rear housing bore, removably inserted into said rear housing bore;

(b) means for axially spacing said housing plug from said top surface of said valve assembly means;

(c) a bottom surface of said housing plug, said top surface of said valve assembly means and said housing plug forming a high pressure fluid chamber between said valve assembly means and said housing plug;

(d) a top housing plate removably connected to said housing, said housing plate contacting a top surface of said housing plug to retain said housing plug in said rear housing bore; and

(e) means for fluid tight sealing of said housing plug in said rear housing bore.

5,586,607

MANUALLY OPERATED CHIPPING TOOL

Anton Neumaier, Fürstentum, and Hans-Christian Donner, Karlsfeld, both of Germany, assignors to Hilti Aktiengesellschaft, Fürstentum, Liechtenstein


Filed Apr. 25, 1995, Ser. No. 428,756

Claims priority, application Germany, Apr. 25, 1994, 44 14 342.7

Int. Cl.⁶ B25D 17/00; B23D 79/00


U.S. Cl. 173—117

9 Claims




1. Manually operated tool for chipping material from a surface comprises a housing 1 extending axially between a leading end and a trailing end, a plurality of axially elongated needle-type chisels (8) each having a leading end and a trailing end with the leading ends projecting from the leading end of said housing, a needle cage (12) having a leading end and a trailing end located within said housing, and an anvil (17) having a leading end and a trailing end located within said housing adjacent the trailing end of said cage, said anvil being axially displaceable within said housing against

the counteracting force of a compression spring (16) having a leading end and a trailing end and abutting said housing at the leading end thereof, a hammer (29) located within said housing and arranged to strike the trailing end of said anvil (17) and advance said anvil in the axial direction, said hammer (29) being displaceable within said housing in the axial direction of said needle-type chisels (8), said needle cage (12) having a plurality of bores extending therethrough in the axial direction of said chisels, said needle cage being enclosed and guided within an axially extending guide sleeve (14) disposed between said anvil and said compression spring, said compression spring (15) forcing said guide sleeve against the leading end of said anvil, and said needle cage being freely axially displaceable within said guide sleeve between the leading end of said anvil and a stop shoulder (15b) formed at a leading end of said guide sleeve.



5,586,608
METHOD OF MAKING AN ANTI-BIT BALLING WELL FLUID USING A POLYOL HAVING A CLOUD POINT, AND METHOD OF DRILLING
David E. Clark, Humble, and William M. Dye, Houston, both of Tex., assignors to Baker Hughes Incorporated, Houston, Tex.

Filed Jun. 7, 1995, Ser. No. 473,614
Int. Cl.⁶ C09K 7/02; E21B 47/06; 21/08
U.S. Cl. 175—40 20 Claims



11. A method of lubricating drilling equipment during the drilling, completion or workover of a subterranean well, comprising the steps of:

- determining uphole region and downhole region operating temperatures in the well; and
- contacting the drilling equipment with a treating fluid by circulating the treating fluid between the uphole region and downhole region, with the treating fluid comprising an oil phase, a water phase, and a cloud point additive, wherein the cloud point additive has a cloud point temperature greater than the uphole operating temperature and equal to or less than the downhole operating temperature.


5,586,609
METHOD AND APPARATUS FOR DRILLING WITH HIGH-PRESSURE, REDUCED SOLID CONTENT LIQUID
Frank J. Schuh, Plano, Tex., assignor to Teletex Technologies, Inc., Dallas, Tex.

Filed Dec. 15, 1994, Ser. No. 356,656
Int. Cl.⁶ E21B 17/18; 21/12
U.S. Cl. 175—65 37 Claims

1. A method of drilling a borehole comprising the steps of: running a drillstring terminating in a drill bit into a borehole; pumping a reduced solid content drilling fluid through the drillstring and out the bit, wherein the drilling fluid impinges upon and disintegrates formation material in cooperation with the bit;

continuously pumping an annulus fluid having a density greater than that of the drilling fluid into an annulus between the borehole and drillstring while drilling formation material, wherein the annulus fluid extends substantially from the earth's surface to the bit; returning the drilling fluid and cuttings resulting from disintegration of formation material to the earth's surface through a substantially unobstructed tubular return passage in the drillstring; and maintaining the annulus fluid under a selected pressure in the annulus, wherein an interface is formed at the drill bit at which annulus fluid mixes with the drilling fluid and is returned along with the drilling fluid and cuttings, but drilling fluid is substantially prevented from entering the annulus.


5,586,610
KELLY BAR HAVING HARDENED FLUTES
James N. Sajatovic, Nazareth, Pa., assignor to Ingersoll-Rand Company, Woodcliff Lake, N.J.
Filed Jun. 5, 1995, Ser. No. 463,466
Int. Cl.⁶ E21B 3/04 8 Claims



1. A Kelly bar comprising:


- a hollow, tubular, elongated body having an outer surface, said body terminating in a first end and a second end;
- an electric arc gouged flute in said outer surface, extending axially lengthwise along said body substantially the distance between said first and second end, said flute extending radially inwardly into said body and terminating at a curved bottom surface; and
- said body having a first microstructure at said flute bottom surface and a second microstructure away from said flute bottom surface, said first microstructure comprising a heat-affected zone having a hardness greater than a hardness of said second microstructure.

5,586,611
DRILL BIT HAVING DUAL SPLIT BUSHINGS FOR CUTTER SUPPORT AND RETENTION
Daniel E. D. Dorosz, Joplin, Mo., assignor to Cypress Services, Inc., Spring, Tex.
Filed Oct. 13, 1995, Ser. No. 542,678
Int. Cl.⁶ E21B 10/22
U.S. Cl. 175—369 13 Claims



1. A rotary cutter cone type drill bit, comprising:
 - (a) a body structure having a plurality of depending cutter support lugs;
 - (b) spindle means being integral with each of said cutter support lugs and defining a cylindrical bushing support surface;
 - (c) a cutter cone being positioned for rotation about each of said spindle means;
 - (d) an inner split bushing being received in immovable relation about said cylindrical bushing support surface; and
 - (e) an outer split bushing being received in rotatable bearing relation about at least a portion of said inner split bushing and retaining said inner split bushing about said cylindrical bushing support surface, said outer split bushing being disposed in immovable relation with said cutter cone.

5,586,612
ROLLER CONE BIT WITH POSITIVE AND NEGATIVE OFFSET AND SMOOTH RUNNING CONFIGURATION
Matthew R. Isbell, and Rudolf C. O. Pessier, both of Houston, Tex., assignors to Baker Hughes Incorporated, Houston, Tex.
Filed Jan. 26, 1995, Ser. No. 378,345
Int. Cl.⁶ E21B 10/08
U.S. Cl. 175—353 9 Claims



5,586,614

SNOW VEHICLE

Takao Kouchi, and Hideaki Suzuki, both of Saitama, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan



Filed Nov. 29, 1994, Ser. No. 350,006

Claims priority, application Japan, Nov. 29, 1993, 5-298407; Sep. 22, 1994, 6-254241

Int. Cl.⁶ B62D 55/06

U.S. Cl. 180—190

14 Claims



1. A snow vehicle comprising:

- a slide rail structure;
 - a plurality of pairs of guide wheels supported on the slide rail structure; and
 - a crawler belt supported and guided on a lower surface thereof by said guide wheels;
- wherein the slide rail structure includes
- a main slide rail supporting a longitudinal center portion of said crawler belt, and
 - a pair of side slide rails being disposed respectively along opposed longitudinal side portions of said crawler belt, wherein said guide wheels are laterally disposed between said side slide rails,
 - wherein a clearance is provided between said crawler belt and each side slide rail, and
 - wherein said crawler belt selectively engages at least one of said side slide rails when the corresponding clearance is closed between said crawler belt and the at least one side slide rail by deflection of said crawler belt.

5,586,615

VACUUM PACKAGED ESCAPE SLIDE

David R. Hammer, Glendale; Kenneth W. Sego, Jr., Peoria, and Lance C. Labun, Tempe, all of Ariz., assignors to Simula Inc., Phoenix, Ariz.


Filed Jun. 7, 1995, Ser. No. 477,402

Int. Cl.⁶ A62B 1/20

U.S. Cl. 182—48

39 Claims

1. An inflatable escape slide system comprising:
- (a) a vacuum packaged envelope containing an inflatable escape slide, an aspirator and at least one slide light;
 - (b) means for fluidly connecting a carbon dioxide cylinder to the inflatable escape slide system;
 - (c) fluid connection means for connecting the means for connecting a carbon dioxide cylinder to the inflatable escape slide system to the aspirator through a vacuum envelope interface, said fluid connection means comprising a rupture disk at the



- vacuum envelope interface, said aspirator being fluidly connected to the inflatable escape slide;
- (e) means for electrically connecting a battery pack through an electrical feedthrough in the vacuum envelope to the at least one slide light;
- (f) a girt bar;
- (g) at least one tear initiator cord, with each tear initiator cord being attached at one end to the vacuum envelope proximate to a tear initiator attachment point, and attached at the other end to the girt bar; and
- (h) an outer girt attached at one end to the girt bar.

5,586,616

ROTATABLE SCAFFOLD


Nick Ksenych, 1900 14th Ave., NW., P.O. Box 1564, Watertown, S. Dak. 57201

Filed Nov. 8, 1994, Ser. No. 336,855

Int. Cl.⁶ E04G 1/00

U.S. Cl. 182—222

11 Claims



1. A scaffold adapted for use with a forklift truck, said truck including a pair of lines for lifting a load, said scaffold comprising:
- (a) a work platform; and
 - (b) a vertical mast to which said work platform is mounted, said vertical mast including:
 - (i) means for mounting said mast to said lines of said forklift truck;
 - (ii) means for allowing a worker on said platform to rotate said platform about said mast to any desired position; and
 - (iii) foothold means mounted to said mast and adapted to rotate with said platform so as to allow said worker to ascend and descend from said platform.

5,586,617

AUTOMATIC EMERGENCY ESCAPE FOR TALL STRUCTURES


Robert L. England, 1443 Tamara Ct., Benicia, Calif. 94510, and Donn E. Albert, Florissant, Mo., assignors to Robert L. England, Benicia, Calif.

Filed Sep. 30, 1994, Ser. No. 315,793

Int. Cl.⁶ A62B 1/02

U.S. Cl. 182—238

1 Claim



1. Apparatus for lowering persons during an emergency along an upright exterior of a structure to the ground surrounding the structure at a safe, predetermined speed, the apparatus comprising: a drum adapted to be attached to the structure and a cable wound about the drum and of sufficient length so that a free end of the cable can reach the ground, the drum being rotatable in a first direction for paying out the cable and lowering the free end thereof to the ground; a hydraulic circuit including a gear pump operatively coupled to the drum so that rotation of the drum causes the gear pump to operate and generate a flow of hydraulic fluid through the circuit; a flow control valve interposed in the hydraulic circuit limiting the rate of flow through the hydraulic circuit to therewith control and limit a rate of rotation of the drum so that the cable is lowered at said predetermined speed when a load is applied to its free end irrespective of a fluid pressure generated by the gear pump; a hand crank operatively coupled with the drum for manually rotating the drum in a second direction opposite the first direction to thereby rewind the cable about the drum and raise the free end of the cable from the ground; and means independent of the flow control valve for preventing the flow control valve from affecting the rate of rotation of the drum in the second direction; a housing enclosing the drum including an elongated slot parallel to an axis of the drum and extending over a length of the drum about which the cable is wound when the cable is fully retracted for guiding the cable as it is paid out and rewound; and a container for holding a quantity of the hydraulic fluid, fluidly coupled with the hydraulic circuit, and disposed outside the housing, the container being sized and shaped so that it holds a quantity of fluid and prevents the fluid in the container from rising above a temperature of about 250° F. even when a plurality of persons in succession use the apparatus for lowering themselves to the ground; whereby a person suspended from the free end of the cable descends along the exterior of the structure at the predetermined speed irrespective of the person's weight and without requiring independent control or external power.

5,586,618

SYSTEM FOR LUBRICATING THREADED MEMBERS

Dale Francis, 379 Fairfield Ave., Gretna, La. 70056


Filed Nov. 14, 1995, Ser. No. 557,501

Int. Cl.⁶ F16N 19/00; 7/19

U.S. Cl. 184—14

17 Claims

14. An apparatus for lubricating threads of threaded members, comprising:



- a) a chamber for housing lubricant;
- b) a first roller for receiving lubricant from the chamber onto an outer surface of the roller;
- c) a first brush member, making sufficient contact with the outer surface of the first roller to receive lubricant onto bristles of the brush member;
- d) a second roller for receiving lubricant from the chamber onto an outer surface of the second roller;
- e) a second brush member, making sufficient contact with the outer surface of the second roller to receive lubricant onto bristles of the second brush member;
- f) power-driven drive chains engaging and rotating the first and second rollers and the first and second brush members so that the lubricant can be transmitted from the outer surface of the first and second rollers to the bristles of the first and second brush members as the rollers and brushes are rotated;
- g) a circular opening in the wall of the apparatus for allowing a threaded member to be positioned sufficiently adjacent the bristles of the first and second brush members for receiving lubricant from said bristles onto a portion of the outer threaded portion of the threaded member as the threaded member is manually rotated, and the rollers and brush members are rotated by the drive chains.

5,586,619

LIFTING APPARATUS


Roland O. Young, R.R. #1, Box 138, Grand Forks, N. Dak. 58201

Filed Nov. 25, 1994, Ser. No. 344,886

Int. Cl.⁶ B66F 9/06; 9/08

U.S. Cl. 187—226

11 Claims



1. A lifting apparatus comprising a housing, at least three elongated telescoping members extending upward in said housing and slidably mounted in telescoping relation to one another, three elongated chains, power actuated upward extending drive means,

three roller means with one of said roller means mounted to the top of said power actuated upward extendable drive means, a second of said roller means mounted to the top of a first one of said three telescoping members, a third one of said roller means mounted to the top of a second one of said three telescoping members, each of said chains having opposite ends below their respective roller means, said first of said chains having its one end attached to said housing and its other end attached to the lower end of a first one of said telescoping members, a second of said chains having one of its ends attached adjacent the top of said first telescoping member and its other end attached to the lower end of a second of said three telescoping members, a third of said chains having its one end attached adjacent the top of said second telescoping member and its other end attached to the lower end of said third telescoping member, whereby actuation of said upward extendable drive means causes said one roller on top thereof to engage and raise said first chain intermediate its ends with one of its ends held from rising causing the other of its ends and the first telescoping member by its lower end to raise upward in reaction thereto with the raising of the first telescoping member causing the second roller on top thereof to engage and raise the second chain intermediate its ends thereby raising the other end of the second chain and sliding upward the second telescoping member by its lower end with respect to the first telescoping member, with the raising of the second telescoping member causing the third roller on top thereof to engage the third chain intermediate its ends thereby raising the other end of the third chain and the third telescoping member by its lower end relative to the first and second telescoping member, said apparatus including a detachable platform having a detachable connection with said housing, said platform having a reservoir for holding fluid, a fluid pump, an electric motor with a battery for powering said motor, said power actuated upward extending drive means comprising a fluid actuated piston and cylinder on said housing, a fluid connection between said reservoir and said pump and a hose connection between said pump on said platform and said fluid cylinder said housing, said hose connection having a detachable connection between said pump and cylinder.


5,586,620
REMOTE VIEWING APPARATUS FOR FORK LIFT TRUCKS

Ned E. Dammeyer, New Bremen; Todd M. Fullenkamp, Coldwater, and Harold A. Stammen, New Bremen, all of Ohio, assignors to Crown Equipment Corporation, New Bremen, Ohio

Filed May 12, 1995, Ser. No. 439,985
Int. Cl.⁶ B66F 9/08; 17/00

U.S. Cl. 187—227

25 Claims



1. A fork lift truck including a mast assembly.

a carriage assembly mounted for vertical movement in said mast assembly;
a pair of forks extending from said carriage assembly for supporting a load;
means for raising and lowering said carriage assembly;
a camera mounted near the plane of said forks, said camera viewing the scene immediately in front of the forks;
means for positioning said camera at a first predetermined location below said forks when the forks are in a raised position and for raising the camera to a protected position when said forks are in their lowermost position, and
a display terminal for presenting to an operator the image of the scene viewed by the camera.

5,586,621
SAFETY CHOCKS FOR BOAT TRAILERS AND THE LIKE


Tracy L. Moon, 1524 Wolfsnare Rd., Virginia Beach, Va. 23451, and Lewis C. Schlener, 1718 Sunset Pl., Ft. Myers, Fla. 33901

Filed Oct. 16, 1995, Ser. No. 544,259

Int. Cl.⁶ B60T 3/00

U.S. Cl. 188—4 R

3 Claims




1. A method of removing wheel blocks from behind the rear wheels of a vehicle hitched to a trailer, comprising passing a flexible member connected to the blocks over the trailer hitch in such a way that when the vehicle moves forward, a portion of the flexible member moves with it, dragging the blocks out of the way of the trailer.

5,586,622
BRAKE OF A BABY'S WALKER
Stephen Hu, No. 2, Ta Ton Road, Hsinchu Industrial Area, Hu Kou, Hsinchu, Taiwan
Filed Mar. 1, 1995, Ser. No. 396,955
Int. Cl.⁶ B62B 9/08

U.S. Cl. 188—20

7 Claims


1. A brake for a baby's walker, comprising:
an inlay board;
a connected tube having an opening and an inner periphery, said connected tube fixed on said inlay board;
a support cylinder having a base, said base being connectable to said inlay board;
a revolving casing having a helical guide, said revolving casing rotatably positioned between said connected tube and said support cylinder;
a slide having a horizontal piece, said slide movably engaging said inner periphery of said connected tube and said horizontal piece movably engaging said helical guide through said opening in said connected tube;



a spring disposed within said connected tube biasing said horizontal piece of said slide against said helical guide;
a brake pad; and
a support pole having a first end and a second end, said first end rotatably engaging said brake pad and said second end fixedly engaging said slide, wherein
rotation of said revolving casing causes said horizontal piece to move vertically within said opening in accordance with said helical guide, thereby vertically displacing said support pole and said brake pad.

5,586,623
REDUCED-BULK BRAKE MOTOR
Jean-Claude Mery, Pavillons-Sous-Bois, France, assignor to AlliedSignal Europe Services Techniques, Drancy, France
PCT No. PCT/FR93/00918, § 371 Date Oct. 12, 1993, § 102(e)
Date Oct. 12, 1993, PCT Pub. No. WO94/09285, PCT Pub. Date Apr. 28, 1994
PCT Filed Sep. 22, 1993, Ser. No. 133,074
Claims priority, application France, Oct. 22, 1992, 92 12638
Int. Cl.⁶ F16D 65/56; 65/16
U.S. Cl. 188—72.6

2 Claims




1. A brake motor comprising: an essentially cylindrical body filled with a hydraulic fluid subjected to a variable pressure; a mechanical actuator comprising a control member which can be accessed from outside the body; a brake piston closing off the body in leaktight fashion and capable of sliding therein under the effect of the actuator in order to actuate at least one friction member; and an automatic adjustment device arranged inside the body between the mechanical actuator and the piston to take up the play resulting from wear of the friction member, the device comprising: a rotationally fixed elongate nut, a first end of which receives a selectively rotary screw engaged therein by a first screw end, a second end of the nut capable of receiving a thrust from the mechanical actuator, and a second end of the screw passing through the piston in leaktight fashion in order to be subjected to atmospheric pressure and having a tapered shoulder capable of being selectively

rotationally blocked by an internal tapered, rotationally fixed surface of the piston against which the shoulder is pressed with a force which increases with the pressure of the hydraulic fluid, characterized in that the mechanical actuator comprises two plates capable of relative rotation, the first plate fastened securely to the second end of the elongate nut, and the second plate connected to a spindle passing through the body in leaktight fashion.

5,586,624
FLY WHEEL BRAKE DEVICE FOR AN EXERCISE BICYCLE
Wen-Chung Ko, Kent Ko, and Chin-Jen Fu, all of No. 342, Ta tung Rd., Kwei San Hsian, Tau Yuan Shien, Taiwan
Filed Sep. 1, 1995, Ser. No. 522,927
Int. Cl.⁶ A63B 22/06; B60L 7/00
U.S. Cl. 188—164

6 Claims



1. A flywheel brake device for an exercise bicycle comprising:
a fixed axle;
a rotary disc having a hollow flange at a center thereof for rotatively coupling said rotary disc to said fixed axle, said rotary disc having a plurality of cambered slots formed there-through, said cambered slots being angularly displaced one from the other about said center by a predetermined angle, each of said cambered slots including a far and a near end thereof, said far end being positioned at a first predetermined radial distance from said hollow flange and said near end being positioned at a second predetermined radial distance from said hollow flange, said first predetermined radial distance being greater than said second predetermined radial distance;
a rotary handle fixedly coupled to said hollow flange of said rotary disk for rotatively displacing said rotary disk relative to said fixed axle;
a fixing rail disc having a hollow sleeve spindle extending from a central portion, said hollow sleeve spindle being fixedly coupled to said fixed axle for securing said fixing rail disc in spaced relationship with said rotary disc, said fixing rail disc having substantially planar opposing first and second sides, said first side having a plurality of V-shaped rails formed thereon;
a plurality of substantially identical sector shaped sliding blocks disposed on said V-shaped rails of said fixing rail disc, said plurality of sliding blocks being arranged adjacent each other about said fixed axle, each of said sliding blocks having substantially planar first and second opposing surfaces, said first surface being positioned adjacent said rotary disc and having formed thereon a plurality of convex columns extending from said first surface for respective insertion into said plurality of cambered slots of said rotary disc, each of said cambered slots defining a cambered path along which a respectively inserted convex column travels responsive to a bi-directional rotative displacement of said rotary disc, each of said sliding blocks correspondingly sliding radially inward


and radially outward as its convex column traverses a respective one of said cambered paths responsive to said rotative displacement of said rotary disc, each of said sliding blocks including an arcuate outer edge from which extends a cambered surface for supporting a plurality of permanent magnets thereon;

- a flywheel formed of a magnetic material and rotatively coupled to said fixed axle, said flywheel having a driving element fixedly coupled to a central portion thereof for rotatably driving said flywheel about said fixed axle, said flywheel having a substantially annular cavity formed in one side thereof for positioning therein said rotary disc, said plurality of sliding blocks and said fixing rail disc, said annular cavity including a bevelled magnetic surface positioned adjacent said second side of said fixing rail disc, said bevelled magnetic surface having adhered thereto a layer of a non-magnetic metal, said bevelled magnetic surface and said plurality of permanent magnets of said plurality of sliding blocks having defined therebetween a magnetic gap of adjustable width; and,
- a flywheel brake operating cable coupled to said rotary handle for effecting said bi-directional rotative displacement of said rotary disc relative to said plurality of sliding blocks, said magnetic gap respectively narrowing and widening as said sliding blocks slide radially inward and outward in response to said bi-directional rotative displacement of said rotary disc to vary the magnetic coupling between said magnetic flywheel and said integral and permanent magnets of said plurality of sliding blocks.

5,586,625

METHOD FOR FINAL BALANCING A BRAKE DRUM
Jay K. Julow, Louisville, Ky.; Robert A. DeRegnaucourt, Centerville, and John C. Hall, Kettering, both of Ohio, assignors to Dayton Walther Corporation, Dayton, Ohio
Division of Ser. No. 76,986, Jun. 14, 1993, Pat. No. 5,483,855.
This application Dec. 13, 1995, Ser. No. 572,227
Int. Cl.⁶ B23C 3/34; F16D 65/10
U.S. Cl. 188—218 R

4 Claims



1. A final balanced brake drum comprising a generally cylindrical body provided with an integral raised squaler band, said squaler band having an outwardly facing surface initially machined to a predetermined diameter around its entire circumference, said brake drum having the initially machined squaler band incorporating an unacceptable imbalance, said squaler band being further machined to produce a cut at a predetermined location along said squaler band, said cut having a circumferentially extending substantially constant depth which extends along a predetermined length of said squaler band, with said predetermined

location, depth, and length being selected to produce a brake drum which corrects the imbalance.


5,586,626
BRAKES

Keith D. Dolbear, Buxton; Trevor W. Beamond, Matlock, and Kerry G. Schofield, Breadsall, all of England, assignors to Ferodo Limited and British Railways Board, England
Continuation of Ser. No. 204,239, Mar. 9, 1994, abandoned.
This application May 31, 1995, Ser. No. 455,249
Claims priority, application United Kingdom, Nov. 15, 1991, 9124381

Int. Cl.⁶ F16D 65/02, 69/04

U.S. Cl. 188—250 B

5 Claims



1. A brake element for engaging a surface of a moving component of a brake system, comprising a lining secured to a backing plate, wherein the lining includes a layer of elastomeric material and a layer of friction material, the layer of elastomeric material having a Rockwell value of a depth of penetration of greater than 0.30 millimeter penetration and at least twice that of the layer of friction material, and wherein the layer of elastomeric material is interposed between the layer of friction material and the backing plate, thereby permitting the lining to more closely conform to the moving component and to thereby also reduce hot spotting of the surface of the moving component.

5,586,627

HYDRAULIC SHOCK ABSORBER OF DAMPING FORCE ADJUSTABLE TYPE

Takashi Nezo, Tokyo, and Akira Kashiwagi, Kanagawa-ken, both of Japan, assignors to Tokico, Ltd., Kanagawa-ken, Japan

Filed May 19, 1994, Ser. No. 246,299


Claims priority, application Japan, May 20, 1993, 5-141437; Oct. 20, 1993, 5-286111; Mar. 18, 1994, 6-074471; Mar. 31, 1994, 6-085591

Int. Cl.⁶ F16F 9/46; B62K 25/10

U.S. Cl. 188—299

8 Claims

1. A hydraulic shock absorber comprising:
a hollow cylinder for containing a hydraulic fluid;
a piston, provided in said cylinder, and dividing the interior of said cylinder into an extension-side chamber and a contraction-side chamber;
a piston rod having a first end connected to said piston and a second end extending out of said cylinder;
an extension-side passage connecting said two cylinder chambers with each other so that hydraulic fluid can flow in the extension-side passage during an extension stroke of said piston;
an extension-side damping force generating valve provided in said extension-side passage for generating a damping force during an extension stroke of said piston;



- an extension-side back pressure chamber operatively associated with said extension-side damping force generating valve;
an extension-side back pressure passage for transmitting hydraulic fluid pressure in said extension-side passage, at a point upstream of said extension-side damping force generating valve, to said extension-side back pressure chamber through a pressure-reducing orifice, wherein hydraulic fluid pressure established in said back pressure chamber urges said damping force generating valve toward a closed position;
an extension-side back pressure adjusting valve in fluid communication with said extension-side back pressure chamber through said extension-side back pressure passage, wherein said extension-side back pressure adjusting valve controls discharge of hydraulic fluid from said back pressure chamber to a low pressure area;
a contraction-side passage connecting said two cylinder chambers with each other so that hydraulic fluid can flow in the contraction-side passage during a contraction stroke of said piston;
a contraction-side damping force generating valve provided in said contraction-side passage for generating a damping force during a contraction stroke of said piston;
a contraction-side back pressure chamber operatively associated with said contraction-side damping force generating valve;
a contraction-side back pressure passage for transmitting hydraulic fluid pressure in said contraction-side passage, at a point upstream of said contraction-side damping force generating valve, to said contraction-side back pressure chamber through a pressure-reducing orifice, wherein hydraulic fluid pressure established in said back pressure chamber urges said damping force generating valve toward a valve-closing position; and
a contraction-side back pressure adjusting valve in fluid communication with said contraction-side back pressure chamber through said contraction-side back pressure passage, wherein said contraction-side back pressure adjusting valve controls discharge of hydraulic fluid from said back pressure chamber to a low pressure area.

5,586,628

STRUCTURE OF A TELESCOPIC HANDLE FOR WHEELED LUGGAGE

Yuan L. Wang, P.O. Box 82-144, Taipei, Taiwan


Continuation-in-part of Ser. No. 363,946, Dec. 27, 1994. This application Jun. 5, 1995, Ser. No. 463,769

Int. Cl.⁶ A45C 13/26; 5/14

U.S. Cl. 190—115

3 Claims

1. A telescopic handle for a wheeled luggage piece comprising: a pair of sleeves each including a tubular portion having an axial hole, a flange at an upper end, an external annular groove



- under said flange, and a pair of external protuberances under said groove, said sleeves being mounted on an upper panel of a wheeled luggage piece with said flange located on said upper panel and fixedly kept in place by a retainer engaged with said external groove below said upper panel;
a pair of outer tubes each formed with a pair of holes aligned with said external protuberances and adapted to receive said protuberances when extended over one of said sleeves, said outer tubes further having a circular projection on an inner surface under said holes;
a pair of inner tubes each formed with a pair of first holes, a circular projection on an inner surface under said first holes, and a pair of second holes under said circular projection;
a pair of tubular members each having a flange at an upper end and a pair of external protuberances under said flange of said tubular member aligned with said first holes of said inner tube, each of said tubular members being inserted into one of said inner tubes with said flange of said tubular member on an upper end of said inner tube and said external protuberances of said tubular member engaged with said first holes of said inner tube;
an inverted U-shaped member having two downwardly depending legs each formed at a lower end with a threaded axial hole, each of said legs being inserted into one of said inner tubes through said tubular members;
a pair of first plugs each including a cylindrical portion having a cavity at an upper end dimensioned to receive a lower end of said leg of said inverted U-shaped member, a center hole, and a plurality of slits at a lower portion;
a pair of first screws each extending upwardly through the center hole of each of said first plugs to engage with the threaded axial hole of one of said legs of said inverted U-shaped member;
a pair of second plugs each including a cylindrical portion having a divergent center hole with internal threads, a pair of external protuberances aligned with said second holes and adapted to engage with said second holes of one of said inner tubes, and a plurality of axial slits at a lower portion; and
a pair of second screws each extending upwardly to engage with said divergent center hole of each of said second plugs.

5,586,629

PRESURE CONTROLLED SYSTEM FOR FILLING AN IMPLANTABLE DRUG INFUSION PUMP

Bret R. Shoberg, Corcoran, and Kenneth T. Heruth, Maple Grove, both of Minn., assignors to Medtronic, Inc., Minneapolis, Minn.


Filed Apr. 13, 1995, Ser. No. 422,362

Int. Cl.⁶ B65B 1/04; 3/04

U.S. Cl. 141—21

13 Claims

13. A method of filling a drug infusion pump with a fluid while preventing over-pressurization of said pump, comprising the steps of:



coupling a filling syringe containing a preselected amount of said fluid to the inlet of a pressure regulating valve; coupling the outlet of said pressure regulating valve to a hypodermic needle; inserting said hypodermic needle into said pump; and actuating said filling syringe to pass fluid through said pressure regulating valve and into said pump until the pressure of said fluid passing through said pressure regulating valve achieves a preselected maximum at which time said pressure regulating valve closes to prevent further flow of fluid into said pump.

5,586,630

SPRING APPLIED/FLUID RELEASED PARKING BRAKE


Gregory J. Orzal, Hartford, Wis., assignor to Wacker Corporation, Menomonee Falls, Wis.

Filed May 15, 1995, Ser. No. 440,908

Int. Cl.⁶ B60K 41/26

U.S. Cl. 192—4 R

18 Claims




1. A braking system comprising:
 - (A) a drive train having a toothed rotatable component; and
 - (B) a parking brake assembly for preventing undesired rotation of said rotatable component, said parking brake assembly comprising a stationary member and a piston which 1) presents a toothed member meshing with the teeth of said rotatable component and which 2) is movable axially from a first position in which said piston is locked to said stationary member such that said and said rotatable component are mechanically locked from rotation with respect to said stationary member to a second position in which said piston is unlocked from said stationary member such that said piston and said rotatable component are freely rotatable with respect to said stationary member.

5,586,631
WINDOW SHADE
 Siegfried Benthin, Bremerhaven, Germany, assignor to Benthin Aktiengesellschaft, Bremerhaven, Germany
 Filed Dec. 22, 1994, Ser. No. 363,513
 Claims priority, application Germany, Dec. 24, 1993, 43 44 627.2

Int. Cl.⁶ E06B 9/84

U.S. Cl. 192—8 R

12 Claims



1. Window shade, comprising:
 - a winding shaft;
 - a shaft sleeve projection rigidly mounted on the winding shaft;
 - said shaft sleeve projection having an inner surface;
 - stationary pivots for rotatably mounting the winding shaft, one of said pivots being provided at each end of the winding shaft;
 - a first pivot of said pivots having a pivot sleeve projection, a recess being defined between an inner jacket surface of said pivot sleeve projection and an outer jacket surface of said shaft sleeve projection, said recess being wedge-shaped in a circumferential direction;
 - opening element means arranged in said recess, said opening element means including an opening element;
 - a drive member coupled to said first pivot and engaged with said opening element for moving said opening element; locking member means for interlocking the winding shaft loaded in the roll-off direction of the window shade with said first pivot, to maintain the winding shaft stationary, said locking member means including at least one rolling body clamped in said recess, in a clamped position, said rolling member being released from the clamped position by movement of said opening element, by said drive member in the direction of rotation.

5,586,632

PULSE ACTUATED INTERLOCK MECHANISM

Jon Bigley, 43120 Barchester, Canton, Mich. 48187, and Evan Baker, 2017 SW. 6th Ave., Camas, Wash. 98607


Continuation-in-part of Ser. No. 143,086, Oct. 26, 1993, Pat. No. 5,535,869. This application Jun. 7, 1995, Ser. No. 485,784

Int. Cl.⁶ F16D 11/14; 25/04; B25B 7/12; B60B 5/00

U.S. Cl. 192—69.41

11 Claims

1. In a device including a drive member and a driven member a pulse actuated interlocking mechanism for releasably interlocking the drive member and driven member comprising:
 - a clutch member between the drive and driven members and slidable between first and second positions, said clutch member in the first position engaged with one of the drive and driven members and the clutch member in the second position engaged with both of the drive and driven members;
 - a first biasing member continuously urging the clutch member to one of the first and second positions;
 - a piston assembly selectively urging the clutch member to the other of the first and second positions, said piston assembly including first and second pistons, a second biasing member urging and second pistons apart to an expanded condition and



a latch mechanism for latching the first and second pistons together in a contracted condition and thereby constraining the second biasing member, said latch mechanism responsive to first and second compressive forces compressing said pistons together for latching and unlatching said latch member mechanism; and

said piston assembly arranged relative to said clutch member whereby the expanded condition of the piston assembly urges the clutch member to the other of the first and second positions and whereby the contracted condition allows the first biasing member to urge the clutch member to said one of the first and second positions.

5,586,633

CLUTCH COVER ASSEMBLY

Hiroshi Mizukami; Norihisa Uenohara, and Hiroshi Takeuchi, all of Neyagawa, Japan, assignors to Kabushiki Kaisha Daikin Seisakusho, Osaka, Japan

Division of Ser. No. 117,425, Sep. 7, 1993, Pat. No. 5,431,268.


This application Apr. 6, 1995, Ser. No. 417,993

Claims priority, application Japan, Sep. 7, 1992, 4-62612 U; Dec. 25, 1992, 4-346511

Int. Cl.⁶ F16D 13/75

U.S. Cl. 192—70.25

16 Claims



1. A clutch cover assembly, comprising:
 - a friction member connected to an output member, said friction member engaging with an input rotation member when pressed toward said output member;
 - a clutch cover fixed to said input rotation member;
 - a pressure plate located within said clutch cover for pressing said friction member;
 - an urging member for urging said pressure plate toward said friction member, said urging member being a diaphragm spring, radially outward end of which urges said pressure plate;
 - a support mechanism movable toward said friction member and for supporting said urging member, wherein said support

mechanism includes a first support mechanism movable toward said friction member from said pressure plate side, and a second support mechanism movable toward said friction member from the opposite side of said pressure plate, said first support mechanism and said second support mechanism supporting radially middle portion of said diaphragm spring; and

a movement regulation mechanism for moving said support mechanism toward said friction member according to wear displacement of said friction member, wherein said movement regulation mechanism includes a restriction member for permitting said first support mechanism to move toward said friction member according to wear displacement of said friction member, and an urging mechanism for urging said second support mechanism toward said friction member in order to move said second support mechanism according to movement of said first support mechanism, said movement regulation mechanism permits said support mechanism to move toward said friction member when said diaphragm spring releases its urging force against said pressure plate.

5,586,634

CLUTCH MECHANISM, ESPECIALLY FOR A MOTOR VEHICLE

Jacques Thirion de Briel, Colombes, France, assignor to Valeo, Paris, France

PCT No. PCT/FR93/01266, § 371 Date Sep. 8, 1994, § 102(e) Date Sep. 8, 1994, PCT Pub. No. WO94/13970, PCT Pub. Date Jun. 23, 1994


PCT Filed Dec. 17, 1993, Ser. No. 284,487

Claims priority, application France, Dec. 17, 1992, 92 15246

Int. Cl.⁶ F16D 13/50

U.S. Cl. 192—70.27

2 Claims



1. A clutch mechanism comprising a hollow cover plate having at its outer periphery an annular skirt, oriented generally axially, at least one pressure plate, which is coupled in rotation to the cover plate through attachment means which enables said pressure plate to be displaced axially with respect to said cover plate, and, between the cover plate and the pressure plate, a diaphragm the outer periphery of which defines a Belleville ring, which, firstly, bears at its outer periphery on a deflection abutment carried by the cover plate, and, secondly, bears at its inner periphery on a protecting element of the pressure plate so as to urge said plate in a direction in which it is displaced away from the cover plate, characterised in that the deflection abutment is of elastic material and carries an integral centring extension, oriented generally axially and interposed radially between the inner periphery of the skirt of the cover plate and the outer periphery of the diaphragm, characterised in that the extension is provided at its free end with a transverse flange directed towards the axis of the assembly, in such a way that the deflection abutment caps the Belleville ring of the diaphragm.

5,586,635


ROTATIONAL CONTROL APPARATUS

Chris Nelson, Roseville; David R. Hennessy, Minneapolis, and James P. LeClaire, St. Paul, all of Minn., assignors to Horton, Inc., Minneapolis, Minn.

Filed Mar. 31, 1995, Ser. No. 414,279
Int. Cl.⁶ F16D 25/06

U.S. Cl. 192—85 A

28 Claims



1. Rotational control apparatus comprising, in combination: an input having an annular interface disc; an output having an annular interface disc, with the input being rotatable relative to the output about an axis, with the interface discs being concentric to the axis and having a first condition where the interface discs are rotatably related to each other and a second condition where the interface discs are rotatably independent from each other; first means for moving the interface discs from the first condition to the second condition; second means for moving the interface discs from the second condition to the first condition; and third means for moving the interface discs from the second condition to the first condition and which is controllable both independently and in combination with the second means.

5,586,636

FRICTION CLUTCH, PARTICULARLY FOR A FAN WHEEL OF A MOTOR VEHICLE ENGINE FAN

Karl-Heinz Linnig, Schillerstrasse 10, 88677 Markdorf, Germany


Filed Jul. 14, 1994, Ser. No. 274,688

Claims priority, application Germany, Jul. 15, 1993, 43 23 651.0

Int. Cl.⁶ F16D 29/00

U.S. Cl. 192—48.2

12 Claims



12. A clutch assembly for a fan wheel of an internal combustion engine, comprising:
a friction disc clutch and an eddy-current clutch, each being arranged in parallel to each other, and each being locatable

between the engine and fan wheel and connectable thereto for transmitting a force from the engine to the fan wheel;
said eddy-current clutch having a first portion connectable to a drive shaft to rotate therewith, and a second portion adjacent to the first portion of said eddy-current clutch and connectable to the fan wheel, said first and second portions being axially spaced from one another by a preselected distance, said distance remaining constant regardless of whether said friction disc clutch is engaged or disengaged;
means for engaging said friction disc clutch using a fluid pressurized medium so that the fan wheel is directly connected to the engine and is rotated at an engine rotational speed; and
means for disengaging said friction disc clutch using the fluid pressurized medium so that said eddy-current clutch entrains the fan wheel and rotates the fan wheel at a speed less than the engine rotational speed.

5,586,637


VARIABLE ANGLE CONVEYOR ASSEMBLY WITH STEPPED CLEAT

Samuel S. Aldlin, 5079 Village Garden Dr., Sarasota, Fla. 34234; Stephen H. Aldlin, 1521 Eastbrook Dr., Sarasota, Fla. 34231; Larry Kincaid, 2635 Hyde Park St., Sarasota, Fla. 34239; Kenneth Cordonnier, 1970 Seton Dr., Clearwater, Fla. 34623; Robert Ledwith, 6210 99th St., E. Bradenton, Fla. 34202, and Robert J. Hencke, 302 73rd St., NW, Bradenton, Fla. 34209

Continuation-in-part of Ser. No. 199,737, Feb. 22, 1994, Pat. No. 5,394,972. This application Jan. 30, 1995, Ser. No. 380,638
Int. Cl.⁶ B65G 47/24

U.S. Cl. 198—397

17 Claims



2. A conveying system for lifting and orienting multi-diameter push-pull caps comprising:

a conveyor belt formed of articulated sections and with guide rollers to support the belt with an upper section having an essentially vertical path of travel and a lower section with an angled path of travel;

sprockets on the guide rollers to effect movement of the belt in a path of travel through the lower section and then the upper section;

a plurality of cleats secured to the exterior surface of the conveyor belt, the cleats having supporting treads extending at right angles from the exterior surface of the conveyor belt for retaining push-pull caps thereon in a proper orientation when a nose of the push-pull cap is in contact with the conveyor belt and a plurality of cylindrical edges of the push-pull cap is supported on the supporting treads of the cleats but to effect the dropping thereof when the push-pull caps are not in the proper orientation;

a supplemental sprocket in contact with the interior face of the conveyor belt in the lower extent of the upper section to form

an outwardly directed bow in the belt and effect the removal, by gravity, of push-pull caps not in the proper orientation; and adjustment means to vary the extent of the bow as a function of the particular bottle cap being conveyed.

5,586,638


DISCHARGE APPARATUS FOR ARTICLE HANDLING SYSTEM

Andrew E. Mojden, Hinsdale, and Richard P. Hoinacki, Oak Lawn, both of Ill., assignors to Fleetwood Systems, Inc., Romeoville, Ill.

Continuation of Ser. No. 10,747, Jan. 29, 1993, Pat. No. 5,449,060. This application Mar. 28, 1995, Ser. No. 390,080
Int. Cl.⁶ B65B 35/40

U.S. Cl. 198—419.1

9 Claims



8. A discharge apparatus for an article handling system, said discharge apparatus receiving a group of facewise stacked articles having a leading end and a trailing end and delivering said group of articles to an outfeed apparatus wherein the articles are assimilated into a generally continuous flow, said discharge apparatus comprising: a first stage station for receiving a group of article; a discharge station having an incoming end associated with said first stage station and an outgoing end adjacent said outfeed apparatus; an article carrying lane extending through said first stage station and said discharge station; a reciprocating shuttle having a leading end support and a trailing end support for holding end leading end and said trailing end of said group of stacked articles and transporting a group of articles from said first stage station to said discharge station; a reciprocating discharge carriage having an article engager extending therefrom for engaging said trailing end of said group of stacked articles for advancing articles received from said shuttle through said discharge station to said outfeed apparatus; and an operating device associated with said shuttle and with said discharge carriage for operating said shuttle to position a leading end of a group of articles into abutment with a trailing end of articles at said discharge station and for operating said discharge carriage to advance said articles toward said outgoing end of said discharge station; whereby reciprocation of said shuttle and said discharge carriage maintain the trailing end of said generally continuous flow to said outfeed apparatus and the leading and trailing ends of a group of articles and facilitate assimilation of said group of articles into said generally continuous flow.

5,586,639

POWERED ROLLER CONVEYER FOR LIGHT LOADS

Shuji Yoshino, Shizuoka, Japan, assignor to Yazaki Industrial Chemical Co., Japan

Filed Dec. 12, 1994, Ser. No. 355,267


Int. Cl.⁶ F16H 55/08; B65G 13/04

U.S. Cl. 198—690.2

3 Claims

1. A powered roller conveyor for light loads comprising rollers made of steel pipes with a synthetic resin coating fixed to the steel pipes;

bearings rotatably supporting each end of each roller;



conveyor frames to support said bearings such that said rollers are arranged transversely to said conveyor frames and are regularly spaced over a length of said conveyor frames; and driving means for driving said rollers in a common direction at an equal peripheral velocity;

wherein said coating resin of said rollers is a soft polyurethane rubber of a hardness of 65 to 80 degrees and in that each of said rollers has a transverse section having on the outer periphery slender trapezoidal ridges that are arranged at a pitch of about 3 mm, having a height of about 2 mm and extend axially to be parallel with each other to form an undulating surface.

5,586,640

CONVEYOR CHAIN

Ingolf Kraut, Balingen, Germany, assignor to Bizerba-Werke Wilhelm Kraut GmbH & Co. KG, Balingen, Germany

PCT No. PCT/EP93/03181, § 371 Date Jul. 6, 1995, § 102(e)

Date Jul. 6, 1995, PCT Pub. No. WO94/11279, PCT Pub.

Date May 26, 1994


PCT Filed Nov. 12, 1993, Ser. No. 428,089

Claims priority, application Germany, Nov. 13, 1992, 9215323 U

Int. Cl.⁶ B65G 15/42

U.S. Cl. 198—692

17 Claims



1. A chain for conveying slices of a food product including in combination a plurality of interlocking links formed of wire, each link having a U shape and comprising a crossbar and two legs, each leg being bent from the crossbar by more than 90° whereby the legs are inclined toward one another, the legs terminating in loops having endpieces which are bent through at least 180° and at least partially surround the crossbar of an adjacent link, a predetermined number of links having at least one loop the endpiece of which is bent through at least 270° and comprises an elongated tip extending appreciably from and at substantially right angles to the plane of the chain.

5,586,641


APPARATUS FOR FEEDING SLIVERS TO A DRAWING FRAME

Ferdinand Leifeld, Kempen, Germany, assignor to Trützschler GmbH & Co. KG, Mönchengladbach, Germany
Continuation-in-part of Ser. No. 278,147, Jul. 21, 1994, abandoned. This application Feb. 21, 1995, Ser. No. 391,276
Claims priority, application Germany, Jul. 22, 1993, 43 24 540.4

Int. Cl.⁶ B65G 19/00

U.S. Cl. 198—720

22 Claims



1. An apparatus for advancing sliver-filled coiler cans into a position at a sliver-intake side of a drawing frame and for removing empty coiler cans from said position; the apparatus comprising
 - (a) an endless track including
 - (1) a first track portion including said position and structured to accommodate a first plurality of coiler cans;
 - (2) a second track portion structured to accommodate a second plurality of coiler cans; said first and second track portions extending generally side by side;
 - (3) two arcuate deflecting track portions interconnecting said first and second track portions at opposite ends thereof;
 - (b) an endless circulating transporting chain extending along said endless track;
 - (c) a plurality of spaced pusher arms mounted on the chain and extending therefrom to individually engage a coiler can and advancing each can on said endless track as the chain circulates, whereby said pusher arms advance the coiler cans on said first track portion in a first direction and on said second track portion in a second direction; said first and second directions being opposite to one another; said spaced pusher arms defining at all times a plurality of can positions for said first plurality of coiler cans on said first track portion and a plurality of can positions for said second plurality of coiler cans on said second track portion;
 - (d) can retaining means for preventing the cans from leaving the deflecting track portions during travel thereon;
 - (e) a motor connected to the transporting chain for circulating said transporting chain; and
 - (f) motor actuating means for intermittently initiating consecutive operating cycles of said transporting chain such that during each operating cycle the first plurality of coiler cans positioned on said first track portion is moved as a single batch to said second track portion and the second plurality of coiler cans positioned on said second track portion is moved as a single batch to said first track portion.

5,586,642

CONVEYOR SYSTEMS


Christopher J. Hawkins, Burnham, United Kingdom, assignor to BWI KartidgPak Co., Davenport, Iowa
Filed Nov. 13, 1995, Ser. No. 557,996
Claims priority, application United Kingdom, Nov. 26, 1994, 9423936

Int. Cl.⁶ B65G 17/34

U.S. Cl. 198—803.11

8 Claims

1. A conveyor system for conveying upright cylindrical objects along a predetermined vertical path, defined by a predetermined vertical loop, said system comprising



- first and second vertically oriented elongate endless members, first and second vertically oriented rotary assemblies positioned at opposite ends of the loop to constrain the elongate members to be driven in synchronism around said predetermined loop, a plurality of longitudinally and vertically spaced, horizontally and outwardly-directed, vertically thin fingers independently mounted on each member and arranged to independently engage said cylindrical objects at vertically spaced locations on opposite sides and displace said cylindrical objects along said predetermined path, adjustment means for effecting relative longitudinal displacement between such endless members to vary the spacing between each finger on one said member relative to a corresponding finger on the other said member in a sense to equal the diameter of the cylindrical object whereby to close the fingers up on said object when inserted between the fingers.

5,586,643

MODULAR BELTING HAVING ANTIMICROBIAL CHARACTERISTICS AND METHOD OF MANUFACTURE


Florian S. Zabron, Orchard Park; Mary E. Mariette, Snyder; Miles S. Rothman, Williamsville, all of N.Y., and William D. Hanrahan, Charlotte, N.C., assignors to Globe International Inc., Buffalo, N.Y.

Filed May 19, 1995, Ser. No. 444,738

Int. Cl.⁶ B65G 17/06

U.S. Cl. 198—853

13 Claims



1. A modular conveyor belting having antimicrobial characteristics that inhibit bacterial growth and promote asepsis on the belting, which comprises:
 - a) a plurality of like modules, each module comprised of a polymeric material and including a first plurality of link ends, a second plurality of link ends and an intermediate section integrally formed with and joining the first and second plurality of link ends, wherein the link ends of each of the modules are releasably engaged between link ends of an adjacent module except for individual link ends disposed at the extreme sides of the module;
 - b) a pivot rod for pivotally connecting the modules at engaged link ends, wherein the link ends of each of the modules are of a width somewhat less than the spacing between confronting

- link ends along the pivotal axis thereof to provide for the pivotal connection of the modules; and
- c) an antimicrobial agent associated with the modules, wherein the antimicrobial agent is provided as a topical applicator applied to an exposed surface of the module or is incorporated into the polymeric material thereof, wherein the antimicrobial agent is selected from the group consisting of a chlorinated phenoxy and polyhexamethylene biguanide hydrochloride, and wherein when the antimicrobial agent is incorporated into the polymeric material comprising the modules, the antimicrobial agent exhibits controlled migration through the polymeric material to the exposed surface thereof when an imbalance of vapor pressure of the antimicrobial agent demands equalization to thereby continuously inhibit bacterial growth and promote asepsis on the belting.

5,586,644

CHAIN CONVEYOR HAVING IMPROVED RUNNING FEATURES

Daniele Coen, Villasanta, and Carlo Garbagnati, Castello Brianza, both of Italy, assignors to Regina Sud S.p.A., Latina, Italy


Filed Oct. 19, 1995, Ser. No. 545,097

Claims priority, application Italy, Nov. 8, 1994, M1940731 U

Int. Cl.⁶ B65G 17/06

U.S. Cl. 198—853

4 Claims



1. A link for a chain conveyor running along a guide comprising at least one sliding surface for moving on a said guide, with at least part of said sliding surface being a sliding element carried by said link; said link having a transverse housing for receiving a pivot pin to enable articulation with a similar link; said sliding element comprising a plug for fitting into a seating which transversely intersects said pivot pin housing; said sliding element having teeth for locking into the seating, said teeth snap interfitting with an abutment edge formed by an intersection between the seating and its associated pivot pin housing.

5,586,645

EXPANDING HELICAL RATCHET SWITCH

Stephen Bartok, 5687 Mistridge Dr., Rancho Palos Verdes, Calif. 90274

Continuation of Ser. No. 258,944, Jun. 13, 1994, abandoned.

This application Nov. 20, 1995, Ser. No. 561,082

Int. Cl.⁶ H01H 19/02

U.S. Cl. 200—527

23 Claims

1. A switch for completing an electrical circuit comprising:
 - a housing having an aperture;
 - a plunger mounted within the housing projecting outward through the aperture;
 - at least two terminals mounted within the housing connectable with the electrical circuit;
 - contact means mounted within the housing for interruptably bridging the terminals;



- a ratchet comprised of one moving element mounted within the housing and having a plurality of rotationally overlapping helical camming surfaces;
- actuating means mounted within the housing and interfacing with the plunger for indexing the ratchet in response to movement of a portion of the plunger into and out of the housing; and
- biasing means mounted within the housing for urging the plunger outward from the housing.

5,586,646

VEHICLE LOCKING SYSTEMS

Mark Bridgeman, 106 Kelsey Lane, Balsall Common, Coventry, United Kingdom, and Pierre Periou, Fordhouse Lane, Sturcheley, Birmingham, West Midlands B30 3BW, United Kingdom

Continuation of Ser. No. 75,635, Jun. 11, 1993, abandoned.


This application Jun. 6, 1995, Ser. No. 468,631

Claims priority, application United Kingdom, Jun. 16, 1992, 9212768

Int. Cl.⁶ H01H 15/06

U.S. Cl. 200—541

7 Claims



1. An actuator assembly for an electrically operated vehicle door lock comprising:
 - means forming a guide for an actuator plunger;
 - a push-pull action actuator plunger slideably received between and located by opposing side walls of said guide for inward and outward movement between first and second positions relative to said guide;
 - a first electrical contact element carried by said plunger for movement therewith; and
 - at least one separate, second electrical contact element mounted on a said side wall of said plunger guide and so positioned relative to said first contact element as to engage said first contact element when said plunger is moved to a predetermined one of said first and second positions.

said first contact element comprising a generally U-shaped resilient metal strip having spaced apart, parallel limbs extending along opposite side faces of the plunger and a connecting portion passing through the plunger whereby the first contact element is coupled to said plunger, an intermediate portion of each said limb being supported in spaced relation to said plunger and being deformable toward the respective plunger side face upon engagement with said second contact element.

5,586,647

DRINKING GLASS

Patrick J. Barta, and Ann L. Porterfield, both of 7336 Earl Ave. NW., Seattle, Wash. 98117


Continuation of Ser. No. 215,029, Mar. 21, 1994, abandoned.

This application Oct. 13, 1995, Ser. No. 543,147

Int. Cl.⁶ B65D 77/00; 25/24; B67B 7/44

U.S. Cl. 206—217

7 Claims



1. A drinking glass comprising:
 - a cup having an upper portion and a lower portion;
 - a stem having a top portion and a bottom portion, the top portion of the stem attached to the lower portion of the cup;
 - a base having a first and second ends;
 - means for inverting and detaching the base from the stem, associated with the base, for removably attaching the first end of the base to the bottom portion of the stem in a first position and for removably attaching the second end of the base to the bottom portion of the stem in a second inverted position;
 - means for securely inserting the base into a penetrable medium attached to the second end of the base wherein the means for securely inserting the base into a penetrable medium includes a spike and wherein the stem includes an upright wall surrounding a hollow interior, the spike fitting into the hollow interior of the stem when the base is in the first position.

5,586,648

HINGE-LID CIGARETTE PACK MADE FROM A ONE-PIECE BLANK

Heinz Focke, Verden, and Henry Buse, Visselhövede, both of Germany, assignors to Focke & Co. (GmbH & Co.), Verden, Germany

Filed Jun. 21, 1995, Ser. No. 493,279


Claims priority, application Germany, Jun. 22, 1994, 44 21 445.6

Int. Cl.⁶ B65D 5/66

U.S. Cl. 206—264

5 Claims

1. In a hinge-lid pack for cigarettes (10) that is made from a one-piece overall blank of material from which are formed a pack part (12), a lid (13) connected pivotally to said pack part (12), and a collar (38) which is anchored in the pack part (12) and which has a portion that projects outwardly from the pack part (12), the improvement wherein:



- a) the lid has an inner tab and the lid (13) is connected to the collar (38) via material webs (43, 44) in a region of the lid inner tab (36) until the hinge-lid pack is opened for the first time;
- b) the lid inner tab (36) is connected by the material webs (43, 44) to an upper free edge of a collar front wall (39), the edge being formed by a punch line (45);
- c) the punch line (45) forms transversely directed edge legs (62, 63) at lateral edge regions of the collar front wall (39), said edge legs (62, 63) defining lateral webs (49, 50) of the collar front wall (39);
- d) the material webs (43, 44) are located in the edge legs (62, 63) and immediately adjacent to upright folding lines (42) between the collar front wall (39) and collar side tabs (40, 41); and
- e) the collar side tabs (40, 41) are each provided with a recess (60, 61) which faces the lateral webs (49, 50), and which is defined by the punch line (45), first as an extension of the edge legs (62, 63) in a region adjacent to the collar side tabs (40, 41), and second as an upper edge (57), which extends parallel to the edge legs, in a region of the collar side tabs (40, 41) which is spaced apart from the lateral webs (49, 50).

5,586,649

WHEEL RETAINING DEVICE


Louis Hsiao, Palo Alto, Calif., assignor to Concept Designs, Inc., Mountain View, Calif.

Filed May 18, 1995, Ser. No. 444,308

Int. Cl.⁶ B65D 85/12

U.S. Cl. 206—303

20 Claims



1. A package comprising a wheel retaining device and a plurality of wheels each having an aperture formed therein, said wheel retaining device comprising:
 - an elongate body extending through said apertures in said wheels, said elongate body having first and second ends;
 - a first retainer positioned proximate one of said ends of said elongate body for supporting said wheels on said elongate body;

a second retainers paced from said first retainer, said second retainer substantially resisting removal of said wheels from said elongate body over said second retainer to securely retain said wheels on said elongate body (during handling of said wheel retaining device).

12. In combination, a wheel retaining device and a plurality of wheels each having an aperture formed therein, said wheel retaining device comprising:

- an elongate body extending through said apertures in said wheels, said elongate body having opposed ends;
- a retainer positioned at one of said opposed ends of said elongate body, said retainer substantially resisting removal of said wheels from said elongate body for retaining said wheels on said elongate body, said retainer being integral with said elongate body and configured to permit said wheels to slip over said retainer when said wheels are moved onto said elongate body; and
- a base portion positioned at the other of said ends, said base portion being configured for selectively supporting said elongate body on each of a plurality of different display systems.

19. A wheel retaining device for storing a plurality of replacement wheels each having an aperture formed therein, said wheel retaining device comprising:

- an elongate body insertable through said apertures in said wheels, said elongate body having opposed ends;
- a retainer positioned at one of said opposed ends of said elongate body for retaining said wheels on said elongate body, said retainer being integral with said elongate body and configured to permit said wheels to slip over said retainer when said wheels are moved onto said elongate body; and
- a base portion positioned at the other of said ends, said base portion being configured for selectively supporting said elongate body on each of a plurality of different display systems; and
- a loop positioned at one of said opposed ends, said loop being mountable to at least one of said display systems, said loop being spaced from said base portion, and
- said base portion including a lower edge positionable on a support surface and a connector spaced upwardly from said lower edge, said connector being shaped to engage said loop of a second wheel retaining device to couple said second wheel retaining device to the first-mentioned wheel retaining device.

20. A wheel retaining device for storing a plurality of replacement wheels each having an aperture formed therein, said wheel retaining device comprising:

- an elongate body insertable through said apertures in said wheels, said elongate body having opposed ends;
- a retainer positioned at one of said opposed ends of said elongate body for retaining said wheels on said elongate body, said retainer being integral with said elongate body and configured to permit said wheels to slip over said retainer when said wheels are moved onto said elongate body; and
- a base portion positioned at the other of said ends, said base portion being configured for selectively supporting said elongate body on each of a plurality of different display systems, said base portion including at least one leg portion configured for supporting said elongate body on a horizontally extending support surface, said leg portion being further configured for mounting said elongate body to a first display system, said base portion further including a connector spaced upwardly from said leg portion, said connector being configured to mount said elongate body to a second display system different from said first display system.

5,586,650

CD BANK

Sheng-Fu Yeh, P.O. Box 82-144, Taipei, Taiwan


Continuation-in-part of Ser. No. 632,585, Apr. 15, 1996. This application May 29, 1996, Ser. No. 654,587

Int. Cl.⁶ B65D 85/57

U.S. Cl. 206—308.1

1 Claim

1. A CD bank comprising a case, a transparent cover hinged to said case, and a plurality of individual CD holder plates mounted inside said case to hold individual compact disks respectively, wherein said case comprises two longitudinal rails bilaterally disposed on the inside, and longitudinally spaced pairs of transverse



grooves respectively made on said longitudinal rails; said individual CD holder plates are respectively pivotably mounted in said longitudinally spaced pairs of transverse grooves between said longitudinal rails, each individual CD holder plate comprising a top side, a bottom side, a half-round recess defined between said top side and said bottom side for holding an individual compact disk, an arched opening at the periphery of said half-round recess for the insertion of the thumb, an extension board extending from said top side at one side of said arched opening, an index groove at said extension board for mounting an index sticker, a plurality of retaining lugs suspending above said half-round recess and spaced around the border thereof for holding down an individual compact disk within said half-round recess, and two springy rods respectively raised from said bottom side at two opposite ends and pivoted to one pair of said longitudinally spaced pairs of transverse grooves, each transverse groove of said longitudinally spaced pairs of transverse grooves having an inner end terminating in a blind hole adapted to hold one springy rod of one individual CD holder plate, and a bottom side smoothly curved inwards, each of the springy rod of each of said individual CD holder plates including a suspension rod section downwardly suspended from the respective individual CD holder plate, and a pivot rod section outwardly extending from said suspension rod section and turned in the blind hole of the respective transverse groove, said half-round recess has a first beveled edge and said retaining lugs being each formed with a second beveled edge opposite to said first beveled edge thereby enabling a compact disk can be therebetween and therefore preventing said compact disk from being scratched and damaged by said CD holder plates.

5,586,651

DISK HOLDER IN A CD BOX

Josef Krummenacher, Muri, Switzerland, assignor to Apparate-Und Werkzeugbau AG, Muri/AG, Switzerland

Filed Jul. 13, 1995, Ser. No. 502,217

Claims priority, application Switzerland, Jul. 14, 1994, 02257/94

Int. Cl.⁶ B65D 85/57

U.S. Cl. 206—310

4 Claims



1. A disk holder in a CD box, comprising a ring of retaining tongues having each a radial arm followed at its inner end by a substantially axial arm which engages in the inserted disk in an elastic manner, wherein it is provided with a support outside the radial arms, respectively wherein the latter are shaped in such a manner that an inserted disk is supported at a distance above the

radial arms, and wherein the external supporting surfaces of the axial arms are still overhanging when the disk is inserted, said radial arms having a curved portion radially extending underneath said inserted disk.


5,586,652

BICYCLE TORQUE COUPLING

Steve-Frank Smilanick, 318 Zola Ave., Roseville, Calif. 95678
Continuation-in-part of Ser. No. 89,108, Jul. 12, 1993, Pat.
No. 5,431,507. This application Sep. 16, 1993, Ser. No. 122,368
Int. Cl. B65D 85/00

U.S. Cl. 206—335

4 Claims



1. A case comprising, in combination:
an exterior surface formed of flexible material, said exterior surface forming a periphery of the case including peripheral side surfaces,
an interior volume dimensioned to receive a disassembled bicycle when the bicycle has handlebars, seat and two 25½ (twenty-five and one-half) inch wheels all of which are removed from its frame, and its frame is in at least two pieces, and wherein its frame is formed from a series of connected tubes having a diameter and lengths and having means to separate the tubes to form the two pieces,
wherein at least one said wheel touches an interior of each said side surface substantially at a mid point of said surfaces when the wheel is within said case,
means for distributing forces passing through said exterior surface, coupled to said exterior surface,
said exterior surface including two similarly sized square surfaces oriented in a parallel, spaced relationship with each other, each said square surface having a height and width just greater than or equal to a 25½ (twenty-five and one-half) inch diameter of the wheels of the disassembled bicycle,
wherein each said square surface of said exterior surface includes two or more pockets therein, said pockets oriented adjacent each other with a seam therebetween, said seam passing over a geometric center of said square surface, whereby a user can place items within said pockets and diminish the presentation of compressive loads at said geometric center of the square surfaces, thereby preventing axles of wheels placed within said case from receiving damaging compressive loads,
wherein said square surfaces' height or width is not greater than 26 inches,
wherein an aggregate of said height, width and a thickness between said square surfaces are dimensioned to be less than 62 (sixty-two) inches,
wherein said force distributing means is a planar layer of semi-rigid sheet material oriented adjacent an interior of said exterior surface,
wherein said case includes a plurality of detachable sleeves of flexible material, each said sleeve having a substantially rectangular shape when lying flat with a width greater than the diameter of said tubes of the bicycle, a length similar to the length of said tubes of the bicycle, and a hook and loop fastener oriented along long edges of said sleeve;
whereby said sleeves are wrapped around said tubes of the bicycle and connect thereto within said case to further prevent the disassembled bicycle within said case from damage,

2. A case comprising, in combination:
an exterior surface formed of flexible material, said exterior surface forming a periphery of the case,
an interior volume dimensioned to receive a disassembled bicycle when the bicycle has handlebars, seat and two 25½ (twenty-five and one-half) inch wheels all of which are removed from its frame, and its frame is in at least two pieces, and wherein its frame is formed from a series of connected tubes having a diameter and lengths and having means to separate the tubes to form the two pieces,
means for distributing forces passing through said exterior surface, coupled to said exterior surface, and
said exterior surface including two similarly sized square surfaces oriented in a parallel, spaced relationship with each other, each said square surface having a height and width greater than a 25½ (twenty-five and one-half) inch diameter of the wheels of the disassembled bicycle,
wherein each said square surface of said exterior surface includes two or more pockets therein, said pockets oriented adjacent each other with a seam therebetween, said seam passing over a geometric center of said square surface, whereby a user can place items within said pockets and diminish the presentation of compressive loads at said geometric center of the square surfaces, thereby preventing axles of wheels placed within said case from receiving damaging compressive loads,
wherein said square surfaces' height or width is not greater than 26 inches,
wherein the total of said height and width and a thickness is not greater than 62 inches,
wherein said force distributing means is a planar layer of semi-rigid sheet material oriented adjacent an interior of said exterior surface,
wherein said case includes a plurality of detachable sleeves of flexible material, each said sleeve having a substantially rectangular shape when lying flat with a width greater than the diameter of said tubes of the bicycle, a length similar to the length of said tubes of the bicycle, and a hook and loop fastener oriented along long edges of said sleeve;
whereby said sleeves are wrapped around said tubes of the bicycle and connect thereto within said case to further prevent the disassembled bicycle within said case from damage,


5,586,653

COSMETIC PACKAGE

Alan L. Taveroff, Dollard-des-Ormeaux, Canada, assignor to Canadian Plastics Inc., Lasalle, Canada
Continuation-in-part of Ser. No. 949,022, Sep. 21, 1992, abandoned. This application Sep. 21, 1993, Ser. No. 124,026
Int. Cl. B65D 85/20; A45D 40/20

U.S. Cl. 206—362

20 Claims



- wherein a plurality of straps including tethered portions and free ends are included, said tethered portions being attached to portions of said exterior surface and said free ends including connectors at ends thereof, said free ends extending a distance from said tethered portions sufficient to completely surround said case with said connectors at said free ends coupling together,
said case including four side surfaces which space said square surfaces away from each other, two of said side surfaces oriented vertically and two of said side surfaces oriented horizontally,
said straps are oriented to surround the case while either surrounding said square surfaces and said vertical side surfaces or said square surfaces and said horizontal side surfaces,
wherein said side surfaces of said exterior surface include four corners therebetween, and
wherein a zipper passes over each of said four corners and completely bisects three of said four side surfaces, whereby said case is openable and closeable for loading and unloading, and
wherein said zipper includes a beginning end and an ending end, and wherein a removable patch of material covers said ends of said zipper over two said corners of said case closest to said ends of said zipper, whereby said zipper is protected from damage.
4. A case comprising, in combination:
an exterior surface formed of flexible material, said exterior surface forming a periphery of the case,
an interior volume dimensioned to receive a disassembled bicycle when the bicycle has handlebars, seat and two 25½ (twenty-five and one-half) inch wheels all of which are removed from its frame, and its frame is in at least two pieces, and wherein its frame is formed from a series of connected tubes having a diameter and lengths and having means to separate the tubes to form the two pieces,
means for distributing forces passing through said exterior surface, coupled to said exterior surface, and
said exterior surface including two similarly sized square surfaces oriented in a parallel, spaced relationship with each other, each said square surface having a height and width greater than a 25½ (twenty-five and one-half) inch diameter of the wheels of the disassembled bicycle,
said case including four side surfaces which space said square surfaces away from each other, two of said side surfaces oriented vertically and two of said side surfaces oriented horizontally,
wherein said side surfaces of said exterior surface include four corners therebetween, and
wherein a zipper passes over each of said four corners and completely bisects three of said four side surfaces, whereby said case is openable and closeable for loading and unloading, and
wherein said zipper includes a beginning end and an ending end, and wherein a removable patch of material covers said ends of said zipper over two said corners of said case closest to said ends of said zipper, whereby said zipper is protected from damage,
wherein at least one of said square surfaces includes rings attached thereto, said rings pivotable away from said square surfaces to allow access through a center of said rings, whereby the case may be tethered to another object such as additional straps for placement and support upon a wearer, and
including thin sheets of puncture resistant material on said square surfaces,
including reinforcing straps attached to an outer surface of said case, and
including a handle coupled to said straps which are attached to said case, said handle including a wrap overlying an inner cylinder.

1. A package comprising a plurality of elongated sticks, a casing comprising peripheral walls defining an open top, a closure and a tray each pivotally mounted to said casing, said tray having attachment means detachably carrying the elongated sticks on said tray and said tray being adapted for retracting, in a closed position thereof, within said casing with said closure being adapted, in a closed position thereof, for covering said open top of said casing, said tray and the elongated sticks being substantially enclosed within said casing and said closure in said closed positions, the elongated sticks being carried on an underside of said tray when said tray is in said closed position thereof such that said tray extends intermediate said elongated sticks and said closure with said elongated sticks extending in a plane substantially parallel to said underside of said tray.

5,586,654

CASSETTE ACCOMMODATING CASE



Shingo Katagiri, and Teruo Ashikawa, both of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed Dec. 28, 1994, Ser. No. 365,551

Claims priority, application Japan, Dec. 28, 1993, 5-74515 U;
Dec. 28, 1993, 5-74516 U; Sep. 29, 1994, 6-235405
Int. Cl. B65D 85/672

U.S. Cl. 206—387.1

16 Claims



16. A cassette accommodating case including a cover section, the cover section comprising a cover-side opposing wall arranged

to extend along one surface of a conventional magnetic tape cassette, and a pocket capable of accommodating one end of the cassette, and a casing section which has a pair of rotation-preventing projections provided on casing-side opposing wall facing the cover-side opposing wall to retain a pair of hubs of the cassette by engaging hub pawls which protrude from an inner periphery of the hubs, the casing section being pivotally attached to the cover section so that the case can open and close, wherein each of said rotation-preventing projections comprises:

two plates which extend in parallel with each other and define an interval therebetween, the interval between said plates defining a hub-pawl retaining groove into which the hub-pawl fits, one of said two plates being longer than the other of said two plates, a width of said one of said plates along a transverse direction to a line extending between said rotation-preventing projections being less than or equal to a minimum width of a common area of opening of the hub when the cassette is loaded in both forward and backward orientations thereof at a distal position of the plate that is remote from the casing side opposing wall, the distal position being disposed in the common area, and a guiding inclined surface provided on a side edge of said one of said plates adjacent to said distal position.

5,586,655

LINE STORAGE DEVICE

John C. McBride, Athens, Ala., assignor to Bag-It Products Corp., Nashville, Tenn.

Continuation of Ser. No. 174,045, Dec. 28, 1993, Pat. No.


5,439,109. This application Jun. 6, 1995, Ser. No. 469,487

The portion of the term of this patent subsequent to Dec. 28, 2013, has been disclaimed.

Int. Cl.⁶ B65D 85/00

U.S. Cl. 206—388

16 Claims



1. A line storage device comprising:

a base portion;

a body portion extending from said base portion and terminating at a first aperture, said body portion having an interior surface and an exterior surface, said base portion and said body portion operatively defining an interior of said device;

at least one hand receptacle, said hand receptacle being located on said exterior surface of said body portion;


wiping means comprising an absorbent material, said wiping means being located on said interior surface of said body portion adjacent to said hand receptacle; and

a second aperture in said base portion, said second aperture including a first opening and a second opening, said first opening being at least partially separated from said second opening, said first opening being larger than said second opening.

5,586,656
NESTABLE AND STACKABLE STORAGE UNIT
Rolin L. Abrams, 4243 White Sands Dr., Las Vegas, Nev. 89121
Filed Jan. 13, 1995, Ser. No. 372,098
Int. Cl.⁶ B65D 21/036

U.S. Cl. 206—501

6 Claims



1. A nestable and stackable storage unit comprising:

a container comprising a base with an upwardly extending wall having a rim extending upwardly therefrom and located inwardly thereof and a lip extending downwardly from said base and located inwardly of said wall;

a substantially planar lid, having a top surface and a bottom surface, said lid having a member extending downwardly from such lid below said bottom surface, said member including inward and outward flanges defining a first groove therebetween for engagement with said rim on said container, said member oriented on said lid such that when said first groove engages said rim, said outward flange is not located outwardly of said upwardly extending wall, a tab extending downwardly from said lid below said bottom surface, said member and tab defining a second groove therebetween for engagement with said lip on said base, said lip on said base located inwardly of said upwardly extending wall a sufficient distance such that when said second groove engages said lip, said member on said lip does not extend outwardly of said upwardly extending wall.

5,586,657

SECURITY BLISTER PACKAGE


Thomas F. Ward, Madison, and Grant W. Smith, Middleton, both of Wis., assignors to Rayovac Corporation, Madison, Wis.

Filed Dec. 22, 1995, Ser. No. 577,504

Int. Cl.⁶ B65D 85/88

U.S. Cl. 206—705

13 Claims



1. A package comprising:

a) a means for holding articles, the article holding means being thermoformed of clear plastic and having a substantially planar flange and a cavity extending frontwardly from said flange;

b) a means for holding a sensor for detecting shoplifting, said sensor holding means having a first surface facing the cavity in the blister which is positioned to engage articles contained in the article holding means, and the sensor holding means further having a second surface spaced rearwardly from the

first surface and a third surface intermediate between said first surface and said second surface;

c) a sensor for detecting shoplifting mounted to the third surface and thereby spaced from the articles within the package; and
d) a means for supporting the means for holding articles, said means for supporting having a card which is bonded to the flange, wherein the card engages said second surface of said sensor support.

5. A blister package comprising:

a) thermoformed plastic blister, the blister having a peripheral flange and a centrally located cavity extending frontwardly from said flange;

b) a sensor support tray, said tray having a first surface for engaging a product spaced within said blister cavity, a second surface lying substantially in the plane of the blister flange, and a third surface spaced between said first surface and said second surface;

c) an anti-shoplifting sensor connected to said third surface; and

c) a backing card which engages the blister peripheral flange and is adhesively bonded thereto, wherein the card further engages the second surface of the tray.

9. A packaged battery assembly with theft-detection features comprising:

a) a clear thermoformed plastic blister, the blister having a peripheral flange and a centrally located cavity extending frontwardly from said flange;

b) a plurality of batteries positioned in the blister cavity;

c) a card which engages with and is bonded to the blister peripheral flange;

d) a thermoformed plastic sensor support tray, said tray having a first surface which engages the batteries and positions the batteries within the blister cavity, and a second surface defined by a peripheral flange and a raised rib, the second surface lying substantially in the plane of the flange of the blister and engaging the card, and a third surface which extends from the rib and is spaced from the first surface by the rib, wherein the third surface is spaced between the second surface and the first surface, the third surface facing toward the card; and

e) an electronic article surveillance sensor adhesively bonded to the third surface to be thereby spaced from the batteries.

12. A method of manufacturing a blister package containing a sensor for detecting shoplifting, the method comprising the steps of:

a) positioning a thermoformed blister, having a cavity and a peripheral flange surrounding the cavity, for receiving at least one article for packaging within the cavity;

b) loading the at least one article wholly within the cavity formed in the blister so as to leave a gap of about one tenth inch between the article and a plane defined by the peripheral flange;

c) picking-and-placing a tray containing a sensor for detecting shoplifting in the blister cavity so the tray does not extend above the plane defined by the peripheral flange; and

d) positioning a backing card over the flange, and bonding the card to the flange to seal the package.

5,586,658

WAFER CUSHIONS FOR WAFER SHIPPER

David L. Nyseth, Plymouth, Minn., assignor to Fluoroware, Inc., Chaska, Minn.

Filed Jun. 6, 1995, Ser. No. 471,641


Int. Cl.⁶ B65D 85/30

U.S. Cl. 206—711

20 Claims

1. A device for storing and shipping semiconductor wafers and disks comprising:

(a) a container having side, end and bottom walls, an open top and an elongate removable cover to provide access into the interior chamber wherein such wafers are received and stored, the container having wafer separating means maintaining the wafers in a spaced and confronting relationship to each other and transversely oriented of the side walls, the cover having a



5,586,659

COMBINATION GIFT BOX AND GREETING CARD


Timothy F. Trumbo, Box 657, Sun Valley, Id. 83353

Filed Jun. 5, 1995, Ser. No. 475,456

Int. Cl.⁶ B65D 5/42

U.S. Cl. 206—768

8 Claims



1. A combined greeting card and gift box formed by preselectively stamping and cutting a single sheet blank to form a plurality of interconnected panels having tabs and tab inserts, the interconnected panels being arranged so that each panel is hingedly con-

ected to at least one other panel along a fold line wherein the combined greeting card and gift box may be arranged in one of a first gift box configuration and a second greeting card configuration by folding the interconnected panels along the fold lines interconnecting the panels and inserting the tabs into corresponding tab inserts, wherein the first gift box configuration comprises:

- a lower back panel;
 - a center base panel perpendicular to the lower back panel;
 - a first side panel perpendicular to the lower back panel;
 - a second side panel perpendicular to the lower back panel and parallel with the first side panel;
 - an upper back panel perpendicular to the lower back panel and parallel with the center base panel;
 - a first base panel perpendicular to the center base panel;
 - a second base panel perpendicular to the center base panel and parallel with the first base panel; and
 - a top panel perpendicular to the upper back panel and parallel with the lower back panel; and
- wherein the second greeting card configuration comprises:
- the center base panel perpendicular to the lower back panel;
 - the upper back panel extending from the lower back panel and coplanar with the lower back panel;
 - the first base panel extending from the center base panel and coplanar with the center base panel;
 - the second base panel extending from the center base panel and coplanar with the center base panel;
 - the first side panel perpendicular to and engaging via a tab and tab insert, the first base panel, for supporting the lower back panel in a vertical plane;
 - the second side panel perpendicular to and engaging via a tab and tab insert, the second base panel, for supporting the lower back panel in a vertical plane; and
 - the top panel folded backwards so that the top panel lies flat against the back of the upper back panel.

5,586,660

PROCESS AND APPARATUS FOR SCREENING A STREAM OF BULK MATERIAL


Adolf Buchlink, Rosengarten, Germany, assignor to Claudius Peters Aktiengesellschaft, Buxtehude, Germany
PCT No. PCT/EP94/01504, § 371 Date Jan. 6, 1995, § 102(e)
Date Jan. 6, 1995, PCT Pub. No. WO94/26428, PCT Pub. Date Nov. 24, 1994

PCT Filed May 10, 1994, Ser. No. 360,794

Claims priority, application Germany, May 10, 1993, 9307072 U

Int. Cl.⁶ B03B 1/00

U.S. Cl. 209—3



1. An apparatus for screening a stream of bulk material comprising a screening zone defining at least a portion of a conveying path for said stream of material, said screening zone comprising at least one fluidized-bed segment and an adjacent screening segment arranged successively within the conveying path, said fluidized-bed segment being effective to impart to the bulk material free-flowing, fluid-like behavior characteristics of a fluidized bed for conveyance in fluidized form along said path toward said adjacent screening segment.

5,586,661

DAM MEMBER FOR A SCREEN DECK


Roger M. Maki, Hibbing, Minn., assignor to Illinois Tool Works Inc., Glenview, Ill.

Filed Dec. 15, 1994, Ser. No. 357,911

Int. Cl.⁶ B07B 1/49

U.S. Cl. 209—397

9 Claims



1. A one-piece dam member for a screen deck having at least two adjacent panels, each panel having a top surface, a bottom surface and an adjoining side surface, said top surface being coplanar the dam member comprising:
 - a wall member formed from a material having a substantially high resistance to abrasion mountable on the top surface of at least one of the adjacent panels; and
 - a bracket member having an L-shape cross-sectional configuration defined by a first leg and a second leg, the first leg having an upper portion opposite the second leg, and a lower portion, the upper portion of the first leg secured to the wall member to form a one-piece dam member,
- wherein the lower portion of the first leg of the bracket member is retained in releasable engagement between the adjoining side surfaces of the adjacent panels, and the second leg of the bracket member extends along the bottom most surface of one of the panels, and
- wherein the dam member is readily placed in desired positions about the screen deck.

5,586,662

BASKET FOR A PAPER-MAKING SCREEN AND METHOD FOR PRODUCING SAME



Yoshihiko Aikawa, Shizuoka, Japan, assignor to Aikawa Iron Works Co., Ltd., Shizuoka, Japan

Filed Apr. 28, 1995, Ser. No. 431,317

Int. Cl.⁶ B07B 1/49

U.S. Cl. 209—411

4 Claims



1. A basket for a paper-making screen consisting essentially of: a plurality of rod-shape members, each having a circular cross section;
- a first annular supporting member having a plurality of first receiving portions arranged annularly in predetermined constant intervals, each first receiving portion being formed of a circular hole slightly larger than a diameter of the rod-shape member and located in a center of the first annular supporting member in a direction of the width; and
- a second annular supporting member having a plurality of second receiving portions arranged annularly in constant intervals as in the first receiving portions, each second receiving portion being formed of a circular hole having a size as in the first receiving portion and located in a center of the second annular supporting member in a direction of the width, longitudinal end portions of said rod-shape members being located in the circular holes of the first and second annular supporting members and fixed thereto so that a space between the rod-shape members includes wide entrance and exit portions, and a narrow middle portion to thereby select paper materials through the spaces, said first and second annular supporting members having same widths and being connected only to the rod-shape members.

5,586,663

PROCESSING FOR THE OPTICAL SORTING OF BULK MATERIAL

Wolfgang Graudejus, Haselau, Eberhard Briem, Pinneberg; Wilhelm Haettich, Karlsruhe, and Heribert Geisselmann, Stutensee, all of Germany, assignors to H.F. & Ph.F. Reemtsma GmbH & Co., Hamburg, Germany


Filed Dec. 28, 1994, Ser. No. 365,489

Claims priority, application Germany, Dec. 28, 1993, 43 45 106.3

Int. Cl.⁶ B07C 5/342; G01J 3/46

U.S. Cl. 209—582

10 Claims



1. A process for the optical sorting of an examination material comprising a bulk material, comprising:
 - conveying the examination material over a transport belt and moving it past an observation head with a light source and a product signal receiver arranged in the vicinity of the light source;
 - measuring light reflected back from the examination material by means of detection elements lying next to one another along a line on the receiver, the detection elements measuring an image wherein each image point is broken down into one of several color components by color filters;
 - sorting the bulk material from reject parts on the basis of color values given by the intensities measured in the color components for each image point by
 - analyzing color values of the examination material in several selected sub-regions of a color space established by the color components;

ascertaining by a classifier, for each sub-region, connected areas of image points with color values falling into the respective sub-region; and

carrying out a sorting classification according to preset criteria applied to the geometry and the size of these ascertained connected areas in the image of the examination material; wherein through comparison of color signals of adjacent image points, large gradients are determined and generally disrupted color values resulting from such gradients are not taken into account during the color value measurements.

5,586,664

DISPLAY ARRANGEMENT


Stephen D. Taylor, P.O. Box 669, Neutral Bay Junction 2089, Australia

Filed Jun. 2, 1994, Ser. No. 253,007

Int. Cl.⁶ A47F 5/05

U.S. Cl. 211—58

11 Claims



1. A display arrangement including an elongate and substantially vertical shaft, extending upwardly from a base; at least two article receiving and holding modules being provided and so formed and adapted as to be mounted to said shaft, so that three article receiving and holding arms extend substantially radially outwardly from said shaft, each of said article receiving and holding arms having at least three substantially vertical walls adapted for containing articles in substantially vertical orientation, an inner end wall, an outer end wall and a back wall, wherein the inner end walls of the three article receiving and holding arms about one another in a triangular relationship about the vertical shaft; each of said modules being independently rotatable about and relative to said shaft.

5,586,665

GRAVITY FED BOTTLE DISPENSING AND DISPLAY RACK

Claude Brousseau, Iles Perreault, Canada, assignor to Etalex Inc., Montreal, Canada


Filed Mar. 1, 1995, Ser. No. 396,712

Int. Cl.⁶ A47F 1/04; 7/28

U.S. Cl. 211—59.2

9 Claims

1. A gravity fed bottle dispensing and display rack comprising a support frame having front and rear transverse horizontal rigid members, a straight bottle support channel interconnected between said transverse horizontal rigid members and oriented downwardly from a rear end thereof to a front open end, said support channel having a longitudinal slot defined longitudinally thereof in a lower




said fingers on said left front and said left rear base members being interengaged with one another, said fingers on said right front and said right rear base members being interengaged with one another, and said left rear and said right rear base members being hinged together, said hinging being on a hinge axis, whereby said base members can hingedly fold over one another.

5,586,667
MOBILE CRANE WITH MAIN AND AUXILIARY COUNTERWEIGHT ASSEMBLIES
Camile J. Landry, 12636 Bristol Ave., Baton Rouge, La. 70815
Filed Dec. 14, 1995, Ser. No. 572,086
Int. Cl.⁶ B66C 23/76

U.S. Cl. 212—196

21 Claims




1. A crane comprising:
 - (A) a ground-supported base;
 - (B) a platform supported on said base;
 - (C) an elongated boom having a lower end pivotally mounted on said platform and having an upper end, said boom being confined to swing relative to said platform substantially in a vertical plane; and
 - (D) an elongated spar which is substantially shorter than said boom, said spar including
 - (1) a lower spar body having i) a lower, from end which is mounted on said platform and which is spaced rearwardly from said lower end of said boom, and ii) an upper, rear end and
 - (2) an upper rigid spar tip formed from a plurality of members immovably attached to one another, said spar tip having a lower end connected to said upper end of said spar body by a) a pivot pin pivotably coupling said spar tip directly to said spar body and b) a lost motion connection, said lost motion connection being pivotably coupled to said spar body and also being pivotably coupled to said spar tip at a location above and behind said pivot pin, said lost motion connection being axially compressible, said pivot pin and said lost motion connection operating to render said spar tip capable of limited pivotal motion with respect to said spar body through a range having upper and lower limits;
 - (E) a main counterweight assembly suspended from said spar body;
 - (F) an auxiliary counterweight assembly connected to said spar tip so as to be supported on the ground when said spar tip is in its lower limit of pivotal motion but otherwise to be suspended from said spar tip; and
 - (G) a link connecting said spar tip to said upper end of said boom, wherein said spar tip, said lost motion connection, said pivot pin, said link, and said boom interact with one another such that, when said boom deflects forwardly and downwardly upon imposition of a load thereon, said boom deflection is resisted by said auxiliary counterweight assembly but

end and extends between opposed support flanges, said support channel having a dispensing front section adjacent said front open end, said dispensing front section of said support channel extending in a substantially horizontal plane, with the remaining section being inclined upwardly towards, said rear end, attachment means for securing said support channel to said front and rear transverse horizontal rigid members, said attachment means being clampingly and displaceably connected to said front and rear transverse horizontal rigid members to position said support channel at a desired lateral spacing in said support frame to accommodate bottles of different diameters, said attachment means comprises a rear clamp secured to a rear end of said bottle support channel and said rear transverse horizontal rigid member for maintaining said rear end of said support channel elevated from said dispensing front section, and a front clamp to said front section of said bottle support channel and secured said front transverse horizontal rigid member, arresting means adapted to abuttingly engage a forwardmost bottle suspended by a neck thereof by said support channel at said dispensing front section to arrest said forwardmost bottle at said front open end of said support channel, and abutment means secured inwardly of said support channel in said dispensing front section at a predetermined location to releasably engage an upper end of said forwardmost bottle.

5,586,666
FOLDABLE AND EXPANDABLE PROMOTIONAL PALLET
Anthony C. Squitieri, Monroe, Conn., assignor to Mechtronics Corporation, Stamford, Conn.
Filed Jun. 12, 1995, Ser. No. 489,441
Int. Cl.⁶ A47F 5/00

U.S. Cl. 211—175

20 Claims




1. A pallet which is adjustable in both length and width, said pallet including
 - left front, right front, left rear, and right rear base members, each said base member having an end piece with parallel fingers extending therefrom,

not by said main counterweight assembly until said spar tip reaches an upper limit of pivotal motion, after which further boom deflection is resisted by both said auxiliary counterweight assembly and said main counterweight assembly.

5,586,668
IMBEDDED ELECTRICAL CONNECTOR
Craig A. Miller, Pittsburgh, Pa., assignor to Westinghouse Air Brake Company, Wilmerding, Pa.
Filed Dec. 14, 1994, Ser. No. 355,839
Int. Cl.⁶ B61G 5/00

U.S. Cl. 213—1.3

25 Claims




1. A connector for joining a fluid pressure communication conduit and at least one electrical conduction line on a first railway vehicle to a like connector on a second railway vehicle coupled to such first railway vehicle, said connector comprising:
 - (a) a connector body including:
 - (I) a surface for mating two like connectors, said surface having a fluid pressure port, said fluid pressure port having a center, and compressible sealing means surrounding said fluid pressure port;
 - (II) a nipple for attachment of a fluid pressure hose, said connector body having formed therein a fluid pressure communication passage joining said nipple to said fluid pressure port;
 - (III) means for mechanically joining two connectors disposed with their said mating surfaces in contact wherein force is applied across their said mating surfaces so said sealing means are compressed and a fluid seal is provided;
 - (b) at least one electrical contact on said mating surface, said at least one electrical contact including a button with resilient mounting means and a plate having an arcuate contact surface electrically connected to said button so that when a first connector is joined to a second connector, said button with resilient mounting means on said first connector makes an electrical interconnection with said arcuate contact surface on said second connector, and said button with resilient mounting means on said second connector makes an electrical interconnection with said arcuate contact surface on said first connector, through which redundant electrical interconnection is provided between said at least one electrical contact on said first connector and said at least one electrical contact on said second connector; and
 - (c) means for connecting at least one electrical conduction line to said at least one electrical contact.

5,586,669
CUSHIONING UNIT FAULT DETECTOR
O. Elwyn Seay, Fort Worth; Stephen K. Nickles, and John E. Haley, both of Burleson, all of Tex., assignors to FM Industries, Inc., Fort Worth, Tex.
Filed May 3, 1995, Ser. No. 433,725
Int. Cl.⁶ B61G 7/00

U.S. Cl. 213—43

20 Claims




11. In a railcar cushioning device for absorbing shock between railway cars, the cushioning device having a hydraulic cylinder containing hydraulic fluid and a piston which locates within the cylinder, the piston and cylinder being movable relative to the other between an extended position and a contracted position in response to draft and buff forces, the improvement comprising:
 - a draft sensor and a buff sensor mounted to the cushioning device, each sensor producing a first initiation signal in response to movement of the piston and cylinder substantially from the extended position to the contracted position, and each sensor producing a second initiation signal in response to movement of the piston and cylinder substantially from the contracted position to the extended position; and
 - detection means which measures a first selected time period initiated in response to the first initiation signal from the draft sensor, the detection means detecting a first error each time the first initiation signal from the buff sensor is generated within the first selected time period, the detection means measuring a second selected time period initiated in response to the second initiation signal from the buff sensor, the detection means detecting a second error when the second initiation signal from the draft sensor is generated within the second selected time period.

5,586,670
BOTTLE SECURITY SYSTEM
Kenneth Greenwald, 135 Ocean Pkwy., Brooklyn, N.Y. 11218
Division of Ser. No. 290,164, Aug. 15, 1994, Pat. No. 5,464,109. This application Nov. 6, 1995, Ser. No. 554,582
Int. Cl.⁶ B65D 55/14

U.S. Cl. 215—207

5 Claims

1. A device to prevent the unauthorized removal of a closure from the mouth of a bottle having an annular ring about its neck, said annular ring having a first face adjacent the mouth of the bottle and a second face spaced apart from said first face comprising:
 - a) a cap member having an interior cavity extending from an open first end to a closed second end;
 - b) said cap member having a cylindrical exterior wall and a generally cylindrical interior wall, said interior wall having an inwardly tapered portion adjacent said open first end;



- c) bottle grip means arranged to fit within said interior cavity of said cap member and move with respect to said cap member;
- d) said bottle grip means having a circular base member and a plurality of resilient fingers extending from the periphery of said base member and perpendicular thereto, the free ends of said fingers describing a circle;
- e) each of said fingers having an inwardly tapered portion, said inwardly tapered portion having an exterior and an interior surface;
- f) said exterior surface of said fingers engaging the inwardly tapered portion adjacent said open first end of said cap member whereby the diameter of the circle described by said interior surface is dependent upon the relative position of said exterior surface of said fingers with respect to said inwardly tapered portion adjacent said open first end of said cap member so that said diameter can be adjusted to engage to disengage the ring of the bottle.

5,586,671


CHILD RESISTANT PACKAGE

Hewin N. Thomas; Jack E. Haney, both of Norcross, Ga., and Peter W. Hamilton, Cincinnati, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio
Continuation of Ser. No. 382,736, Feb. 2, 1995, abandoned, which is a continuation-in-part of Ser. No. 103,476, Aug. 6, 1993, abandoned. This application Feb. 23, 1996, Ser. No. 602,877

Int. Cl.⁶ B65D 50/08

U.S. Cl. 215—209

19 Claims



1. A child-resistant package for storing and dispensing material, comprising:

- (a) a bottle including a base and a finish portion, said finish portion having an innermost surface and an outermost surface, said finish portion including a first means for rotatably and releasably securing a closure to said finish portion on at least one of its surfaces, a platform extending radially outward from said finish portion, said platform having an outermost surface being generally concentrically aligned with said finish portion, and at least one resiliently deformable pushtab having a first end and a second end, at least one of said ends being secured to said platform, each of said at least one pushtab having an uppermost surface, a lowermost surface, an innermost surface, and an outermost surface, said outermost surface of said pushtab being generally concentrically aligned with said finish portion and generally conforming to the contour of said exterior surface of the adjacent portions of said platform to minimize the chance of inadvertent depression thereof when said platform is grasped, said at least one pushtab having a vertical extension projecting above said uppermost surface of said at least one pushtab, said at least one pushtab being inwardly moveable relative to the rest of said platform when a force is applied to said outermost surface of said at least one pushtab;
- (b) a closure having a skin, said skirt having an innermost surface and an outermost surface, said skirt including on at least one of its surfaces second means complementary to said first means for rotatably and releasably securing said closure to said finish portion, said skirt having at least one interlocking pawl on its innermost surface wherein each of said at least one interlocking pawl corresponds to only one of said vertical extension, said at least one interlocking pawl being shaped and positioned to deflect said corresponding vertical extension on said at least one resiliently deformable pushtab when said closure is rotatably secured onto said finish portion in a latched position and releasing said closure from said finish portion by rotating said closure in a reverse direction when said at least one resiliently deformable pushtab is first depressed to disengage said at least one pushtab's vertical extension from said interlocking pawl; and
- (c) a seal on said innermost surface of said closure for providing sealing engagement between said closure and said finish portion of said bottle at least when said at least one interlocking pawl engages said corresponding vertical extension in said latched position, said seal being configured so as to be biased against said finish portion so that after said cap is rotatably secured onto said finish portion, said cap can be rotated in a reverse direction, to a point at which said at least one interlocking pawl and said at least one pushtab come into contact, without breaking said sealing engagement between said seal and said finish portion.

5,586,672

TUBE MADE OF PLASTICS MATERIAL HAVING A TEARABLE CAP, SAID TUBE WITH A COVER


Bernard Schneider, and René Hoslet, both of Sainte Menehould, France, assignors to Cebal, S.A., Clichy, France
Continuation of Ser. No. 79,675, Jun. 18, 1993, abandoned.
This application Aug. 17, 1995, Ser. No. 516,249

Claims priority, application France, Jun. 19, 1992, 92 07839
Int. Cl.⁶ B65D 47/10

U.S. Cl. 215—250

23 Claims

1. A tube (1) made of plastics material having a longitudinal axis (16),
- a head (2) which has a cylindrical axial internal surface (12), the head being sealed by an integral cap (5) which is connected to the head and adapted to be torn therefrom by twisting to leave an orifice in the head, the cap (5) having
- a base (7) where the cap (5) is connected to the head (2),
- an exterior lateral surface (6) of convex planar polygonal contour extending down to the base (7).



- an internal surface (11) adjoining the cylindrical axial internal surface (12), and being a surface of revolution about the axis and in the form of an arch which extends up into the cap, and
- a tear zone (10) contained between and defined by the cap convex planar polygonal exterior lateral surface (6), the cap internal surface (11) and the head internal surface (12), the external lateral surface (6) and the internal surface (11) at the connection between the base of the cap and the head providing the tear zone with successive gradually thinning and thickening thin and thick portions (e.g. 14, 14' and 9, 9') extending about the axis (16).

5,586,673


CAP ASSEMBLY FOR FLUID DELIVERY SYSTEM

Ronald J. Venooker, Franklin; John A. Scavitto, Mendon; Peter N. Karkantis, Acton; David T. Healey, No. Reading, and Richard L. Travers, Scituate, all of Mass., assignors to Ciba Corning Diagnostics Corp., Medfield, Mass.
Division of Ser. No. 165,137, Dec. 9, 1993, abandoned. This application Aug. 11, 1995, Ser. No. 513,699

Int. Cl.⁶ B65D 51/00

U.S. Cl. 215—310

4 Claims



1. A cap assembly for receiving a stopper and for application to a bottle having a cylindrical neck portion which has a central longitudinal axis, external threads and a circular end edge which defines an opening to the bottle, said cap assembly comprising:

- (a) a cap which has an axis of rotation, an end wall and a circular side wall, said end wall having a first central circular aperture which is concentric with said axis of rotation, said circular side wall having internal threads which are complementary with the external threads of the neck portion of a bottle for screwing the cap onto said neck portion about said axis of rotation, said end wall having an outer surface and an inner surface; and
- (b) a removable thrust washer which is adapted to lie within the circular side wall of said cap, said thrust washer comprising:
- (1) a base wall which is adapted to lie against the inner surface of said end wall, said base wall having a second

- central circular aperture which is concentric with the central circular aperture of said cap and said axis of rotation;
- (2) an annular side wall which extends transversely from said base wall, said annular side wall being concentric with said axis of rotation and having an outer end which extends through said first central circular aperture to the outer surface of said end wall when said base wall lies against said end wall within the annular side wall of said cap, said annular side wall being resiliently yieldable toward said axis of rotation; and
- (3) a ridge at the outer end of said annular side wall, said ridge extending away from said axis of rotation for engaging the outer surface of said end wall when said base wall engages the inner surface of said end wall to secure said thrust washer against movement away from said cap while allowing said thrust washer to rotate freely within said cap about said axis of rotation, said flange moving out of contact with the outer surface of said end wall upon bending of said annular side wall toward said axis of rotation in response to pressure against said end wall toward said axis of rotation for releasing said thrust washer from said cap.

5,586,674


GOLF CLUB COVER HOLDING DEVICE FOR ATTACHMENT TO A GOLF BAG

Armand E. Nachbauer, 811 Bolivar St., Lady Lake, Fla. 32159
Filed Dec. 13, 1995, Ser. No. 571,473

Int. Cl.⁶ A63B 55/00

U.S. Cl. 206—315.4

14 Claims



1. A golf club cover device for semi-permanent attachment to a golf bag for holding a club head cover in a prominent manner, said golf club cover device comprising:

- (a) a receiving member for hooking engagement with the golf bag, said receiving member having a main body and a hooking leg extending therefrom, wherein the main body has a front wall, a back wall, a substantially vertical first sidewall and a generally vertical second sidewall with a passageway extending therethrough such that an entry opening of the passageway is in the substantially vertical first sidewall adjacent said hooking leg and an exit opening of the passageway is in the generally vertical second sidewall, further wherein the hooking leg extends substantially parallel to the substantially vertical first sidewall so as to create an open channel therebetween sufficiently wide to allow said receiving member to fit onto an open-top edge of the golf bag; and
- (b) an L-shaped meshing member positioned in the receiving member, said L-shaped meshing member having a substantially vertical leg and a substantially horizontal leg whereby the substantially vertical leg has a generally rounded knob to receive the club head cover and the substantially horizontal

leg has an enlarged terminus with a protuberance dimensioned to be received within the passageway of the receiving member but not pass completely therethrough with the protuberance extending past the entry opening of said passageway such that the enlarged terminus is seated in the passageway in a manner which allows the L-shaped member meshing to be rocked from a non-locking position to a locking position by contact of the protuberance with the golf bag so as to hold the golf club cover device to the golf bag.

5,586,675

REINFORCED MATERIAL HANDLING CONTAINER


Antonius H. Borsboom; Anthony A. Gennari, both of Pittsfield; Kenneth G. Rudolph, Dalton, and Peter J. Zuber, Pittsfield, all of Mass., assignors to General Electric Company, Pittsfield, Mass.

Filed Nov. 29, 1993, Ser. No. 159,095

Int. Cl.⁶ B65D 88/52

U.S. Cl. 220—6

5 Claims



1. A material handling container (10) of the type for packing, shipping and inventorying goods and of the type for stacking one upon the other when not in use, said container (10) comprising: a molded thermoplastic container (10) defining at least one planer expanse (84) and having a plurality of plastic reinforcement members (86) integrally molded with the container (10) at predetermined positions on said plastic planer expanse (84) of said container (10); said plurality of reinforcement members (86) defining a plurality of hollow channels (88) disposed adjacent to said planer expanse (84) and including at least one rib (90) extending outwardly from said channel (88) defined by said member (86) for adding strength to said planer expanse (84) of said container (10).

5,586,676

BEVERAGE CONTAINER CAP WITH STIRRER

L. Grant Lynd, Canal Winchester, Ohio, assignor to National Packaging Corporation, Columbus, Ohio


Filed Oct. 20, 1995, Ser. No. 546,337

Int. Cl.⁶ B65D 41/56

U.S. Cl. 220—212

16 Claims

1. A drink container cap, said cap comprising an exterior surface, and an interior surface, said interior surface having a stirrer depending downwardly therefrom, said stirrer having a shank end, said cap having formed therein a stirrer receptacle having an inner surface, said stirrer being mechanically retained within



said stirrer receptacle by cooperation between said shank end and said inner surface, said stirrer receptacle having a bottom edge, said stirrer receptacle having at least one notch formed in said bottom edge, said stirrer having at least one projection extending outwardly therefrom, said projection configured to fit within said notch.

5,586,677

THERMOFORMED FOLDOVER PACKAGE WITH EASY OPEN FEATURE


Douglas E. Foos, Barrington Hills, Ill., assignor to Plastofilm Industries, Inc., Wheaton, Ill.

Filed Sep. 30, 1994, Ser. No. 316,240

Int. Cl.⁶ B65D 43/26

U.S. Cl. 220—260

5 Claims



1. A container comprising: a base having an upper rim defining a top opening and a sidewall forming at least a portion of said rim, said base including a first flange extending outward from said sidewall along one length of the sidewall and a second flange extending outward from said sidewall along a second length of the sidewall; a cover hingeably connected to said base, said cover including a peripheral portion and a skirt connected to said peripheral portion, said cover being shaped and dimensioned to cover

and close said top opening of said base with said skirt extending generally along the exterior of said sidewall, said cover including a third flange extending outward from said skirt along a first length of said skirt and a fourth flange extending outward from said skirt along a second length of said skirt; a hinge integrally and pivotally connecting said second flange to said fourth flange; and means for releasably holding said cover in position upon said base when said cover is closed over said top opening, said skirt and said sidewall being sized so that said first flange is vertically spaced from said third flange and said second flange extends abuttingly adjacent said fourth flange when said cover is closed so each of said first and said third flanges may be individually grasped to open said container.

5,586,678

BULK HOPPER TANK LID OPENER ASSEMBLY


Hans J. Rosch, Aurora, and Steven R. Beck, Central City, both of Nebr., assignors to TIC United Corp., Dallas, Tex.

Filed Nov. 4, 1994, Ser. No. 334,529

Int. Cl.⁶ B65D 43/26

U.S. Cl. 220—263

15 Claims



1. A bulk hopper tank assembly comprising: a bulk hopper tank having a top end and a bottom end, the bulk hopper tank containing an opening at the top end thereof, the bulk hopper tank having an exterior side; a lid assembly, the lid assembly including: a lid, a generally vertical arm extending along the exterior side of the bulk hopper tank, the vertical arm having opposite top and bottom ends, a generally horizontal arm having opposite ends wherein one end thereof being attached to the lid and the other end thereof being connected to the top end of the vertical arm, a lifter attached to the bottom end of the vertical arm, the lifter moveable between a down position and an up position, a handle being connected to the vertical arm near the bottom end thereof, when the lifter is in the up position the handle being moveable to a plurality of positions between a first position in which the lid is over the opening and a second position in which the lid is away from the opening so as to not cover any of the opening.

5,586,679

DISPOSABLE BODY CONTAINER


Betty M. Thomas, Joliet, Ill., assignor to Group-J, Inc., Evergreen Park, Ill.

Filed Aug. 16, 1993, Ser. No. 106,648

Int. Cl.⁶ B65D 5/36; 5/60; A61G 17/00

U.S. Cl. 220—410

20 Claims



1. A collapsible, disposable body container, comprising: a container base moveable along a plurality of fold lines between an open position defining a container, and a collapsed position defining a generally planar configuration; and a container lid sized to cover said container base; said container base including a double center fold line for folding said container base in half longitudinally in said collapsed position.

5,586,680

BOX CONSTITUTING VACUUM INSULATED WALLS OF A REFRIGERATOR OR FREEZER CABINET


Fredrik Dellby, Enskede, and Per Åke Fonser, Stockholm, both of Sweden, assignors to Aktiebolaget Electrolux, Stockholm, Sweden

Continuation of Ser. No. 346,751, Nov. 30, 1994, abandoned. This application Nov. 9, 1995, Ser. No. 556,126

Claims priority, application Sweden, Dec. 22, 1993, 9304248 Int. Cl.⁶ B65D 25/00

U.S. Cl. 220—467

8 Claims



1. A box forming heat insulating walls of a refrigerator or freezer cabinet, said walls comprising an inner metal shell, an outer metal

shell, and an evacuated heat insulation between the shells, said shells having edges which surround a rectangular access opening to the box and which are gas imperviously connected to each other by a thin metal strip having poor heat conductivity, wherein the edges are folded toward each other so that said edges form planar surfaces located in substantially one and the same plane as said access opening, said planar surfaces surrounding said rectangular access opening in said substantially one and the same plane, and wherein the strip is generally flat and soldered to the planar surfaces.

5,586,681

CONTAINER FOR DISPENSING LIQUIDS


Nini E. Polcappelli, 361 N. Robertson Blvd., Los Angeles, Calif. 90048

Continuation-in-part of Ser. No. 29,791, Mar. 11, 1993, abandoned. This application Jan. 26, 1995, Ser. No. 378,461

Int. Cl.⁶ B65D 25/28

U.S. Cl. 220—674

10 Claims



1. A container for a fluid, comprising:
 - an elongated generally cylindrical body portion having first and second ends;
 - a bottom portion sealing the first end;
 - a substantially planar top portion sealing the second end and having an aperture;
 - a cover member releasably secured to the top portion for sealing the aperture, wherein the cover member provides a closed cavity suitable for containing a fluid without fluid communication therethrough;
 - the body portion having disposed thereon and embossed therein a pattern of protrusions of a preselected shape, height, configuration and arrangement, the protrusions enhancing the exterior periphery of the body portion by providing traction thereto whereby the container can be more securely held when the container becomes wet or cold, the protrusions extending outwardly to increase the volume of container relative to the same container without embossing and to substantially decrease the area of contact with the hand of a user holding the container such that there is less temperature conduction between the hand and the fluid in the container and,
 - the body including an outside surface, and including a printed layer of an ornamental representation on the outside surface, the ornamental representation acting to enhance the ornamental effect of the surface, and the ornamental representation including in at least some part printed lettering, and at least some part of the ornamental representation extending over the protrusions.

5,586,682

HANDLE GRIP PIECE FOR USE IN GRIPPING A DRINKING MUG


Frank Yeh, 1019 N. Mayflower St., Anaheim, Calif. 92801

Filed Oct. 23, 1995, Ser. No. 547,108

Int. Cl.⁶ B65D 25/28

U.S. Cl. 220—755

11 Claims



1. A combination comprising:
 - a) a mug having a wall and a handle, the handle having a top portion connected to the wall, a bottom portion connected to the wall, and a central portion connected to the top and bottom portions, the top, central and bottom portions of the handle together with the wall defining a space between the handle and the wall; and
 - b) a handle grip piece comprising:
 - (i) a first side piece comprising an inner edge and an outer surface facing the wall of the mug, the first side piece comprising an upper recess and a lower recess spaced-apart from each other along the inner edge;
 - (ii) a second side piece comprising an inner edge and an outer surface facing the wall of the mug, the second side piece comprising an upper recess and a lower recess spaced-apart from each other along the inner edge; and
 - (iii) means positioned along the inner edges of the first and second side pieces for connecting the first side piece to the second side piece;
 - c) wherein the first and second side pieces are positioned substantially inside the space between the handle and the mug, the upper and lower recesses of the first and second side pieces retain and connect portions of the handle, and the handle is exposed and is not encapsulated by the first and second side pieces except by the upper and lower recesses of the first and second side pieces, when the first and second side pieces are positioned inside the space between the handle and the mug.

5,586,683

STORAGE DEVICE FOR UMBRELLA SACKS

Toshiyuki Murakami, Kanagawa, Japan, assignor to Kabushiki Kaisha Muraharu Seisakusho, Sagami-hara; Ninkura Scales Co., Ltd., and Kabushiki Kaisha Yakult Honsha, both of Tokyo, all of Japan

PCT No. PCT/JP93/01852, § 371 Date Apr. 14, 1995, § 102(e) Date Apr. 14, 1995, PCT Pub. No. WO95/01281, PCT Pub. Date Jan. 12, 1995

PCT Filed Dec. 22, 1993, Ser. No. 256,423


Claims priority, application Japan, Jun. 30, 1993, 5-041131 U; Nov. 26, 1993, 5-321070; Nov. 26, 1993, 5-321071

Int. Cl.⁶ B65H 1/00

U.S. Cl. 221—33

5 Claims

1. A storage device for umbrella sacks comprising: a device body having a plurality of storage sacks for umbrellas stored



therein; a movable support member in said device body vertically movable therein; a foot pedal for moving said movable support member lower in said device body; open control levers for opening said storage sacks in connection with the descending motion of said movable support member.

5,586,684

VENDING APPARATUS AND METHOD HAVING IMPROVED RELIABILITY


James H. Halsey, El Dorado, Ark.; Scott Judd, Everett, Wash., and James W. Erwin, El Dorado, Ark., assignors to IDX, Inc., El Dorado, Ark.

Filed May 2, 1994, Ser. No. 235,893

Int. Cl.⁶ G07F 11/06

U.S. Cl. 221—90

7 Claims



1. A vending apparatus comprising:
 - a plurality of shelves, each shelf being positionable in a nondispensing position and in a dispensed position;

a plurality of solenoids, each solenoid being positioned and arranged to support one of the plurality of shelves in the nondispensing position;

control circuit means operably coupled to the plurality of solenoids for selectively enabling any one of the plurality of solenoids thereby causing an associated shelf to move from the nondispensing position to the dispensed position; and

test circuit means operably coupled to the plurality of solenoids and to the plurality of shelves for determining when any one particular solenoid and the shelf that is associated with that particular solenoid are in electrical contact with one another, thereby indicating that the shelf that is associated with the particular solenoid is in the nondispensing position.

5,586,685

APPARATUS FOR DISPENSING ARTICLES


Wolfgang C. Dörner; Michael A. Hosch, both of Oconomowoc; Darin L. Danelski, Dousman, and David A. Remsing, Sussex, all of Wis., assignors to Dörner Mfg. Corp., Hartland, Wis.

Filed Sep. 27, 1994, Ser. No. 313,016

Int. Cl.⁶ B65H 1/00

U.S. Cl. 221—197

16 Claims



9. In combination, a conveyor including a conveyor frame and a conveyor member mounted for travel on the frame in a given direction, a dispenser disposed above the conveyor member for individually dispensing articles onto the conveyor member, said dispenser including an elongated supporting structure for supporting a stack of superimposed articles, said supporting structure having a longitudinal axis disposed at an acute angle with respect to the vertical, said supporting structure including a generally L-shaped base to support a lowermost article in the stack, said L-shaped base having a pair of legs disposed at an angle to each other, a peripheral portion of the lowermost article being supported on said legs, pusher means including a pusher mounted for sliding movement relative to the base and disposed to engage the lowermost article and push the lowermost article from the stack and deposit said article on the conveyor member, and stripper means mounted on the supporting structure and disposed to be engaged by a second lowermost article in the stack to prevent movement of the second lowermost article from the stack as the lowermost article is pushed from the stack.

5,586,686


TEMPERATURE MAINTAINED FOOD DISPENSING SYSTEM AND METHOD

Rafael T. Bustos, Alpharetta, Ga., and George LaPolice, Somerville, N.J., assignors to L&P Property Management Company, Chicago, Ill.

Continuation-in-part of Ser. No. 404,243, Mar. 15, 1995, abandoned. This application May 25, 1995, Ser. No. 449,935
Int. Cl.⁶ B23Q 7/04

U.S. Cl. 221—211

26 Claims



1. A system for vending individually packaged food products in their individual non-reusable packaging containers to customers at a customer location in an ambient temperature environment, for immediate consumption at a food service temperature that differs from the temperature of the ambient temperature environment, comprising:

- a customer terminal at the customer location in an ambient temperature in the ambient temperature environment having an order entry device operable to generate an order command in response to order input from a customer and a packaged product dispensing unit operable to present a food product in its own individual non-reusable packaging container to the customer;
- a food product supply terminal at a loading location that is physically separated from the customer location by an intervening building structure or partition or an otherwise useful space that is part of neither the customer terminal nor the supply terminal, the loading station including a food product supply enclosure having an environment therein maintained the food service temperature;
- a pneumatic conveyor extending between the food product supply terminal and the product dispensing unit operable, when activated, to move an individually packaged food product in its packaging container from the supply terminal, across the intervening structure or space, between the two locations, to the dispensing unit; and
- a controller operable to activate the conveyor, in response to an order command from the order entry device, the controller being logically linked to a payment device that accepts payment for the product or charges payment therefor to the customer.

5,586,687

GRAVITY FEED BOTTLE DISPENSING DEVICE HAVING A TRACK-BLOCKING GATE MECHANISM

William S. Spamer, Roswell; J. Marshall Suttles, Elberton; Dennis E. Parham, and James D. Whiten, both of Kennesaw, all of Ga., assignors to The Mead Corporation, Dayton, Ohio
Filed Feb. 16, 1995, Ser. No. 389,379
Int. Cl.⁶ B65G 60/00

U.S. Cl. 221—298

23 Claims

1. A merchandising device for bottles each having an integrally formed annular neck flange, comprising:
track means having a front end and a rear end and defining a pathway therealong to support a row of said bottles such that said bottles are suspended by said neck flanges thereof for



movement along said pathway and are removable from said pathway through said front end;
support means for supporting said track means such that said track means is inclined downwardly toward said front end whereby said bottles when supported by said track means are allowed to gravity feed toward said front end as a leading bottle in said row is removed from said pathway;
stopper means provided at said front end for engagement with said leading bottle so as to prevent said leading bottle from being accidentally removed through said front end whereby said leading bottle when arriving at said front end is stopped and presented for removal from said pathway; and
gate means for blocking said pathway at a position between said front and rear ends when said leading bottle is engaged by said stopper means such that forward movement of the other bottles in said row is blocked by said gate means whereby said leading bottle is maintained free of pressure of said other bottles and disposed substantially vertical when stopped at and suspended from said front end.

5,586,688


ELECTRIC PUMP TOY WATER GUN

Lonnie G. Johnson, Smyrna, and John Applewhite, Atlanta, both of Ga., assignors to Johnson Research & Development Company, Inc., Smyrna, Ga.

Filed Nov. 25, 1994, Ser. No. 344,875
Int. Cl.⁶ A63H 3/18

U.S. Cl. 222—61

13 Claims



1. A portable water gun comprising a housing defining a barrel, a handle and a trigger; a storage reservoir adapted to hold liquid; a pressure tank adapted to hold liquid; a pump for drawing liquid from said storage reservoir and depositing the drawn liquid into said pressure tank; an electric motor coupled with said pump, an electric power supply electrically coupled with said electric motor; conduit means for conveying liquid from said pressure tank to ambience adjacent an end of said barrel; and control means

coupled to said trigger for controlling the flow of liquid through said conduit means upon actuation of said trigger.

5,586,689

SQUEEZABLE RECEPTACLE HAVING A CUT-OUT PORTION IN AN END SECTION THEREOF

Antonio D'Amato, Arzano, Italy, assignor to Seda S.p.A., Napoli, Italy


Filed Apr. 7, 1995, Ser. No. 418,427

Claims priority, application European Pat. Off., Apr. 12, 1994, 94105630

Int. Cl.⁶ B65D 35/00

U.S. Cl. 222—92

15 Claims



1. A squeezable receptacle, comprising:

- a body, the body having a receptacle opening and a wall, the body tapering downward from the receptacle opening, the wall being defined by a circumferential surface held together in an overlapping area extending along a left-hand side edge and a right-hand side edge, said circumferential surface having at a lower end thereof a flattened end section, a cut-out portion being provided in the end section, the cut-out portion extending in from at least one of the left-hand side edge and the right-hand side edge, said cut-out portion being open towards a respective other edge and being arranged, at least partially, in the overlapping area.

5,586,690

BULK CONTAINER WITH REMOVABLE LINER, DISCHARGE FITMENT FOR THE LINER, AND ADAPTER FOR CONNECTION TO DISCHARGE PORT OF THE CONTAINER


Steven P. Ettore; Joseph J. Lane, both of Marietta, and Douglas S. Vandergriff, Woodstock, all of Ga., assignors to 21st Century Containers, Ltd., Atlanta, Ga.

Filed Sep. 19, 1994, Ser. No. 305,939

Int. Cl.⁶ B65D 35/56

U.S. Cl. 222—105

11 Claims



1. A lined container comprising:

- a rigid-walled vessel having a wall and a port formed in said wall;
- a flexible liner having a discharge fitment integrally provided therewith, said fitment having female threads;
- an adapter comprising a tubular member having a proximal end, a distal end, and a coaxial bore, for connecting said fitment of said flexible liner to said port of said vessel, and a flange member, secured to said tubular member, for abutting against an interior surface of the wall of said vessel, wherein the distal end of said adapter extends through the port of said rigid-walled vessel.

5,586,691

COMBINATION DISPENSE TAP AND CUSTOMER INFORMATION DISPLAY

Henry E. Gotch, Sunbury-on-Thames, and Roger J. Hyde, Little Harrowden, both of England, assignors to Alumasc Limited, Kettering, England

PCT No. PCT/GB93/01701, § 371 Date Apr. 17, 1995, § 102(e) Date Apr. 17, 1995, PCT Pub. No. WO94/04456, PCT Pub. Date Mar. 3, 1994


PCT Filed Aug. 11, 1993, Ser. No. 381,953

Claims priority, application United Kingdom, Aug. 14, 1992, 9217293; Oct. 15, 1992, 9221677

Int. Cl.⁶ B65D 5/66

U.S. Cl. 222—113

12 Claims



1. In combination customer information display apparatus and a dispense tap, for beverages and other fluids, and having a tap body, for attachment to a counter fitting, and an operating lever assembly with an illuminated tap handle, connected to a tap opening and closing mechanism in the tap body, wherein:

- the operating lever assembly includes
 - a tap handle formed at least in part of light transparent and/or light reflective material and
 - a tap handle holder connected to the tap opening and closing mechanism; and
 - the display apparatus includes
 - a light generator mounted externally to the tap handle, and means to direct light from the light generator into or onto the tap handle;
- whereby, in use, the tap handle can be illuminated to display customer information.

5,586,692

WATER BOTTLE ASSIST DEVICE

Rodney C. Livengood, P.O. Box 744, Kittanning, Pa. 16201


Filed Mar. 13, 1995, Ser. No. 402,642

Int. Cl.⁶ B67D 5/64

U.S. Cl. 222—166

4 Claims

1. For a drinking water dispenser of the type utilizing an inverted water bottle removably mounted on the upper end of the



dispenser, an assist device for inverting the water bottle from an upright position to an inverted, dispensing position on the dispenser, comprising:

- a base member having a recess into which a water bottle is temporarily set in an upright position;
- an elongated support member for positioning the base member in a horizontal disposition against the dispenser;
- retention means for maintaining the assist device and the water bottle in close proximity to the dispenser as the assist device inverts the water bottle from the upright position to the inverted, dispensing position;
- an extension member attached to the support member and capable of selective linear adjustment relative to the support member in order to maintain the horizontal disposition of the support member relative to a floor surface;
- the extension member further comprising a sliding surface contiguous with the support member and which slidably contacts the support member during selective linear adjustment of the extension member; a flat elongated facing surface opposite the sliding surface;
- the flat elongated facing surface further including an elongated groove;
- an attachment means for securing the retention means to the dispenser; and
- the attachment means including a pair of attachment strips for securement to the dispenser in a spaced-apart relationship to that the retention means can be secured to each respective attachment strip.

5,586,693

LIQUID DISPENSER COMPRISING A DISPENSING VALVE AND A PUSH BUTTON

Vincent De Laforcade, Rambouillet, France, assignor to L'Oreal, Paris, France


Filed Jun. 8, 1995, Ser. No. 488,738

Claims priority, application France, Jun. 8, 1994, 94 07018

Int. Cl.⁶ B67D 5/06

U.S. Cl. 222—182

16 Claims



1. A dispenser for dispensing of a product in the form of a liquid, a spray or a foam, the dispenser comprising:

- a reservoir for the product, the reservoir having a first axis of symmetry and being provided with a dispensing valve, the dispensing valve comprising an actuator stem;
- a push button having a pin which is capable of acting on the stem, a duct passing through the pin and connecting one end of the stem to a nozzle provided with a second axis, and arranged in the push button; and
- a retaining ring capable of being fixed on the reservoir for keeping the push button in position;

wherein:

the push button and the retaining ring are made in one piece and articulated to each other by a swivel joint connecting the push button to the ring in a zone situated in a plane defined by the first axis of the reservoir and the second axis of the nozzle, the swivel joint being capable of pivoting round a third axis perpendicular to the first axis, and the push button and the ring being connected to each other by at least one tab movable in translation along the first axis.

5,586,694

PERFUME APPLICATOR WITH REPLACEABLE CARTRIDGES

Diane Breidenbach, and Laurence Mille, both of Smithtown, N.Y., assignors to Fragrance Systems International, Inc., Smithtown, N.Y.

Continuation-in-part of Ser. No. 356,918, Dec. 14, 1994, Pat.

No. 5,526,960. This application Feb. 24, 1995, Ser. No.

394,031

Int. Cl.⁶ B67D 5/06

U.S. Cl. 222—183

10 Claims



1. A liquid perfume product dispenser assembly comprising, in combination:

- a cylindrical container having an open base end and an open outlet end,
- a removable and replaceable liquid reservoir cartridge within said cylindrical container;
- said reservoir cartridge having an open discharge end extending beyond the outlet end of said cylindrical container and a closed end extending beyond the open base end of said cylindrical container;
- dispensing means removably mounted in the open discharge end of said reservoir cartridge for dispensing the contents of said cartridge and to permit the replacement of said cartridge and transfer of said dispensing means to a replacement cartridge; and
- cover means for enclosing the open discharge end of said cartridge and said dispensing means to form a continuous cylindrical configuration with said cylindrical container.

5,586,695

SPRAYED LIQUID DISPENSING APPARATUS


Rainer H. Labus, 811 E. Grinnell Dr., Burbank, Calif. 91501, and Stephen L. Tucker, 227 Poinsettia, Corona Del Mar, Calif. 92625

Continuation-in-part of Ser. No. 13,959, Oct. 7, 1993, Pat. No. Des. 357,177. This application Mar. 6, 1995, Ser. No. 398,971

Int. Cl.⁶ B65D 83/14

U.S. Cl. 222—396

9 Claims



1. Sprayed liquid dispensing apparatus comprising:

- a) a container consisting of high-strength synthetic resin, the container having a bottom wall, an upright side wall, and an upper neck,
- b) said side wall including upper and lower wall portions having threaded interconnection, whereby the upper wall portion is rotatably removable from the lower wall portion to allow liquid to be filled into the lower portion, after which the upper portion is rotatably connectible to the lower portion to provide a sealed interconnection therewith,
- c) a pressurized gas inlet fitting carried by said upper wall portion proximate said neck, the fitting including a check valve, whereby pressurized gas can be filled into the container, for pressurizing the liquid therein,
- d) and a manually manipulable discharge valve carried proximate the top of the container, above said neck and via which sprayed liquid is dispensed,
- e) said side wall and bottom wall having sufficient thickness as to be rigid and to contain fluid pressure up to at least about 200 psi.

5,586,696

HAIR GROWING MANNEQUIN HEAD

Evelyn R. Martinez, 1053 S. White Rd., San Jose, Calif. 95127

Filed Jan. 17, 1995, Ser. No. 375,372

Int. Cl.⁶ D06C 15/00; A63H 3/44; G09B 19/10; A41G 3/00

U.S. Cl. 223—66

6 Claims

1. A hair growing mannequin head comprising:

- a mannequin head portion; and
- a hair supply means removably mounted to an upper portion of the mannequin head portion for selectively dispensing hair proximal to the upper portion of the mannequin head portion, wherein the hair supply means is in the form of a replaceable cartridge assembly which can be selectively separated from the mannequin head portion for replacement,
- wherein the hair supply means comprises a perforated helmet assembly which can be positioned into fitting engagement with the mannequin head portion to form a representation of a human head structure; a supply reel rotatably mounted within



the helmet assembly; a plurality of strands of hair stored on the reel for dispensing through perforations in the helmet assembly.

5,586,697

GARMENT HANGER


Gert A. Johansson, Hammarbacke 36, S-443 38 Lerum, Sweden

Filed Jun. 8, 1995, Ser. No. 488,745

Int. Cl.⁶ A47G 25/14; G09F 19/00

U.S. Cl. 223—85

16 Claims



9. A one-piece garment hanger assembly comprising:

- a hanger body;
- a hook member formed integrally with said hanger body;
- an elongate member partially delimiting an opening which is defined between a portion of said hook member and said elongate member; and
- a substantially cylindrical information marker attached to and rotatable about said elongate member within said opening, said marker comprising a cylindrical ring wall and a slot through said ring wall which said elongate member passes to attach said marker to said elongate member.

5,586,698

AUTOMOTIVE TOOL STORAGE DEVICE

Hideto Satoh, Hamamatsu, Japan, assignor to Suzuki Motor Corporation, Japan

Filed May 19, 1995, Ser. No. 444,442


Claims priority, application Japan, May 30, 1994, 6-116131

Int. Cl.⁶ B62D 43/00

U.S. Cl. 224—42.24

3 Claims

1. An automotive tool storage device for use with a spare tire having a wheel hub fixable to an automobile rear floor, said storage device comprising:



a spare tire holder having a threaded portion in connection therewith and adapted to project downwardly through the wheel hub and toward the automobile rear floor and a spare tire bracket adapted to be connected with the automobile rear floor for connection with the threaded portion for fixing the spare tire to the rear floor;

a tool; and
a tool holder disposed below the spare tire holder and adapted to be disposed above the wheel hub, said tool holder having a hole formed therein permitting said threaded portion of said spare tire holder to be inserted therethrough, said tool holder further comprising a concave portion formed therewith and opening downwardly toward the wheel hub, wherein, in use, said threaded portion of said spare tire holder is inserted through said hole of said tool holder, said tool is situated in said concave portion of said tool holder and said threaded portion is fixed to said spare tire bracket such that said tool is adapted to bear against the wheel hub and said tool is clamped inside said concave portion between said tool holder and the wheel hub.

5,586,699

BACKPACK SUPPORT

Kurt W. Helsler, McDonough, and Richard S. Haddock, Endwell, both of N.Y., assignors to Johnson Worldwide Associates, Inc., Sturtevant, Wis.

Continuation of Ser. No. 195,707, Feb. 14, 1994, abandoned.

This application Feb. 6, 1996, Ser. No. 597,347

Int. Cl.⁶ A45F 3/04; 3/08

U.S. Cl. 224-628

9 Claims



1. In a rectangular frame for supporting a backpack having a pair of shoulder straps and a rigid frame having cylindrical upper and lower cross members, the improvement comprising a pair of rigid vertical fittings for securing the shoulder straps to the frame, each of said fittings including a main section having a series of parallel

slots, means at each end of said main section for securing said fittings in a perpendicular spaced relation to said upper and lower cylindrical cross members, said securing means comprising a curved member on one end of each of said fittings having a curvature slightly greater than half the curvature of the upper cross member, the curved member being sufficiently flexible to form a snap fit with said upper cross member, and a flat slotted ring mounted on each shoulder strap, said ring being of a size to pass through said slots and being rotatable with respect to the shoulder straps to lock each strap in one of the slots in said fittings.

5,586,700

MAIL CARRIER


John E. Fitzner, 1006 Floral Ave., Schenectady, N.Y. 12306, and Thomas J. McCoy, 4 St. Marie St., Schenectady, N.Y. 12303

Filed Nov. 8, 1994, Ser. No. 336,258

Int. Cl.⁶ A45C 13/26

U.S. Cl. 224-219

14 Claims



1. A mail carrier for assisting a mailperson with carrying mail, comprising:

a flat back portion having a top edge and two side edges, wherein said flat back portion is vertically stiff;
a pair of stiff side flaps, each stiff side flap being moveable along a vertical axis and connected to a respective one of said two side edges;

an open pouch connected to said flat back portion at a lower half thereof, wherein an upper half of said flat back portion extends above said open pouch; and

a pair of handles, each handle being connected to a respective one of said pair of stiff side flaps, wherein said pair of handles allow said mail carrier to be suspended along the length of said mailperson's forearm.

5,586,701

HANDGUN HOLSTER

Kwon K. Kim, Seoul, Rep. of Korea, assignor to Samduck Sanggong Co., Ltd., Seoul, Rep. of Korea

Filed Sep. 29, 1995, Ser. No. 536,208

Claims priority, application Rep. of Korea, May 4, 1995, 9576

Int. Cl.⁶ F41C 33/02

U.S. Cl. 224-243

5 Claims

1. A handgun holster having a flap that may be arranged in a plurality of fastening positions, said handgun holster comprising:

a holster body (1), said holster body (1) having an inside surface and an outside surface, said outside surface of said holster body having a loop fastening part (3b) formed thereon, said outside surface of said holster body having a subordinate fastening piece (4) secured thereto, said subordinate fastening piece (4) having a hook fastening part (a) and a loop fastening part (b) formed on opposite sides thereof; and

a holster flap (2), said holster flap (2) having a beginning portion and an ending portion, said beginning portion of said holster

5,586,703

DUAL FIELD PACK


Elizabeth Radar, and James R. Radar, both of 1215 Red Gum, Suite H, Anaheim, Calif. 92806

Filed May 26, 1995, Ser. No. 451,858

Int. Cl.⁶ A45F 3/04

U.S. Cl. 224-601

17 Claims



flap being secured to said holster body (1), said holster flap (2) having an inside surface and an outside surface corresponding to said inside surface and said outside surface of said holster body (1), said inside surface of said ending portion of said holster flap having a hook fastening part (3a) formed thereon, said outside surface of said ending portion of said holster flap having a loop fastening part (3b) formed thereon, said inside surface of said beginning portion of said holster flap having a loop fastening part (3b') formed thereon.

5,586,702

VEHICLE CARGO CARRIER


William R. Sadler, 1520 Edgewood Dr., Altoona, Wis. 54720

Filed Apr. 12, 1995, Ser. No. 421,049

Int. Cl.⁶ B60R 7/00; 7/10; 9/00; 11/00

U.S. Cl. 224-521

17 Claims



1. A cargo carrier for attachment to the rear portion of a vehicle via a receiver-type trailer hitch of the type having a substantially square tubular configuration with an open central channel, comprising:

(a) a connection member for attachment to the vehicle trailer hitch, said connection member having a predetermined configuration, said connection member having a bar structure which is horizontally pivotal, said bar structure being of a predetermined length and having predetermined outside dimensions which are substantially equivalent to inside dimensions of the trailer hitch central channel, said connection member further having a proximal end for insertion into vehicle trailer hitch central channel and an opposing distal end;

(b) a frame member slidably attached to said connection member; and

(c) a box member attached to said frame member.

5,586,704

SHOULDER HOLSTER AND METHOD OF CARRYING A PORTABLE TELEPHONE NEAR THE BODY OF A USER

Tommy Alexander, 419 Durham Rd., Stanley, N.C. 28164, and Shawn B. Jenkins, Charlotte, N.C., assignors to Tommy Alexander, Stanley, N.C.


Filed Mar. 7, 1995, Ser. No. 399,893

Int. Cl.⁶ A45F 5/00

U.S. Cl. 224-605

4 Claims

1. In combination with portable telephone means comprising a telephone and a protective jacket for holding the telephone therein, and said jacket including a front, substantially planar wall having respective transmitter and receiver openings residing adjacent to a transmitter and receiver portion of the telephone and a center window spaced from each of the receiver and transmitter openings for exposing a plurality of push buttons of said telephone, the jacket further including an attached flap for removably covering said transmitter and receiver openings and said center window, a shoulder holster for carrying the telephone means near the body of a user for storage of and ready access to the telephone means by the user, said holster comprising:



two shoulder carrier straps connected at one end thereof to the rucksack;
a harness yoke to which the other ends of the shoulder straps are joined, and
yoke engagement means on the rear wall of the rucksack to receive the harness yoke in height-adjustable engagement;
wherein the yoke engagement means comprises a plurality of overlapping transverse slats attached to the rear wall of the rucksack which define a plurality of overlapping open-ended sleeves into a selected one of which sleeves the harness yoke may be inserted.

5,586,706 WAIST BAG



Mary E. Ritzheim, 354 Western Ave., Fond du Lac, Wis. 54935

Filed Jan. 20, 1995, Ser. No. 375,797
Int. Cl.⁶ A45C 13/18

U.S. Cl. 224—671

3 Claims

- a supporting shoulder strap having opposing ends and extending generally over the shoulder and under the arm of the user during wear;
- a telephone mounting panel attached to respective ends of the shoulder strap, and residing near the chest of the user during wear; and
- complementary attachment means located on said mounting panel and on a back wall of said protective jacket for removably attaching the telephone means to said mounting panel.



5,586,705

RUCKSACK HARNESS


James Leonard, Dublin, Ireland, assignor to Lowe Alpine Systems International Limited, County Offaly, Ireland
PCT No. PCT/IE94/00027, § 371 Date Nov. 13, 1995, § 102(e)
Date Nov. 13, 1995, PCT Pub. No. WO94/26143, PCT Pub. Date Nov. 24, 1994

PCT Filed May 11, 1994, Ser. No. 545,866

Claims priority, application Ireland, May 14, 1993, S930368
Int. Cl.⁶ A45F 3/04

U.S. Cl. 224—631

13 Claims



1. A rucksack having a carrying harness, the carrying harness comprising:

- A waist bag comprising:
 - a belt having opposed ends with buckles thereon of predetermined size;
 - a pouch having front, back, top, and bottom sides and opposed ends, wherein:
 - the pouch back side has a lower portion fabricated from a first piece of flexible material and having an upper edge;
 - the pouch back side has an upper portion fabricated from a second piece of flexible material and having a lower edge;
 - a zipper connects the lower edge of the second piece of material to the upper edge of the first piece of material;
 - a third piece of material is located inside the pouch and has an upper end sewn to the lower edge of the second piece of material adjacent the zipper and a lower end sewn to the first piece of material proximate the pouch bottom side; and
 - a flexible decorative strip extends outside of the pouch back side between the two ends thereof and is sewn to the second piece of material proximate the zipper and sewn to the first piece of material for short distances from each of the two pouch ends, the decorative strip overlying the zipper; and
 - a pair of loops fastened to the pouch back side and having a size sufficient to enable the belt and buckles to slide without resistance therethrough.

so that a person can wear the waist bag around the person's waist and cutting and pulling the belt from the person does not pull the pouch from the person, and so that the upper edge of the first piece of material, the lower edge of the second piece of material, the zipper, and the third piece of material cooperate to form a hidden pocket in the back side of the pouch and the decorative strip selectively conceals the zipper.

5,586,707

HOLDER FOR SCORECARDS


Christopher F. Haskell, 73 Kenneth Rd., Marblehead, Mass. 01945

Filed May 25, 1995, Ser. No. 450,635

Int. Cl.⁶ A45F 5/00

U.S. Cl. 224—684

16 Claims



1. A holder for a scorecard, the holder comprising:

- a scorecard retaining unit comprised of a first section, a second section, and a third section; each section being generally flat and generally rectangular and having an inside face, an outside face, a first end, and a second end; the first section having its first end free and its second end connected by a first hinge means to a first end of the second section; the second end of the second section connected by a second hinge means to a first end of the third section; and the second end of the third section being free; such that the retaining unit may be folded along the first and second hinge means so that the inside faces of the first and second sections are in a contacting relationship and the third section folds over the first end of the first section such that its inside face is in a contacting relationship with the outside face of the first section;
- a means for slidably securing the scorecard retaining unit to the user's waist so that the user may slide the scorecard retaining unit about substantially the entire waist of the user;
- a means for retaining a scorecard secured to the inside face of one of the sections, the scorecard retaining means is comprised of a narrow elasticized band having a first end and a second end and travelling freely across substantially the entire inside face of the section upon which a scorecard is to be retained; the elasticized band being secured at each of its ends to the section whereby the wearer's access to the scorecard is not materially interfered with and substantially the entire scorecard may be marked without being removed from the scorecard retaining unit; and
- the sections of the retaining unit being formed of a flexible material with that material connecting the sections and thereby acting as the first and second hinge means.

5,586,708

PACKAGING MACHINE FEED MECHANISM


Bernard Lerner, Aurora; Richard W. Hess, Hudson; William M. Cronauer, Tallmadge; Rick S. Wehrmann, Hudson, and James D. Kramer, Medina, all of Ohio, assignors to Automated Packaging Systems, Inc., Streetsboro, Ohio

Division of Ser. No. 298,786, Aug. 31, 1994, Pat. No. 5,499,485, which is a division of Ser. No. 954,378, Sep. 30, 1992, Pat. No. 5,394,676. This application Jun. 8, 1995, Ser. No. 488,791

Int. Cl.⁶ B65H 20/00

U.S. Cl. 226—172

5 Claims



1. A feed mechanism for feeding a plastic web comprising:

- a first pair of grooved rolls;
- a first set of elastic belts reeved about the first pair of rolls to form a first web conveyor, the belts of the first set each having a web feed reach extending between the rolls along a path of travel and opposed return reaches each of the belts of the first set being disposed in associated grooves of each roll of the first pair of rolls;
- a second pair of grooved rolls;
- a second set of elastic belts reeved about the second pair of rolls to form a second web conveyor, the belts of the second set each having a web feed reach extending between the rolls along a path of travel and opposed return reaches each of the belts of the second set being disposed in associated grooves of each roll of the second pair of rolls;
- the feed reaches of the first set being juxtaposed with the feed reaches of the second set whereby to grip opposite faces of a web of plastic film and convey such web along the path;
- first rolls of each pair being abutting nip rolls at the downstream ends of the feed reaches;
- second rolls of each pair being an upstream set with the second roll of the first pair being downstream from the second roll of the second pair;
- the feed reaches of the first conveyor being located in an imaginary plane; and
- the second roll of the second pair including a portion on the same side of such imaginary plane as the return reaches of the first conveyor such that the feed reaches of the second conveyor are deflected over and engage surfaces of the second roll of the first pair.

5,586,709

DEVICE TO COMPENSATE THE ELONGATION OF AT LEAST TWO WIRE RODS OR ROUND BARS, WHICH IS ASSOCIATED WITH A DRAWING ASSEMBLY

Giorgio Del Fabro, Tricesimo, and Marcello Del Fabro, Udine, both of Italy, assignors to M.E.P. Macchine Elettroniche Piegatrici SpA, Reana del Rojale, Italy


Filed Jul. 18, 1995, Ser. No. 503,857

Claims priority, application Italy, Jul. 20, 1994, UD94A0129
Int. Cl.⁶ B65H 20/00; 20/02

U.S. Cl. 226—177

8 Claims

1. Device to compensate the elongation of two or more wire rods or round bars on machines fed with two metallic wire rods or




round bars of iron or alloys thereof of a type for building work, the device comprising a pair of opposed rolls comprising an upper roll and a lower roll, the pair of opposed rolls defining between them respective inner and outer passes, with which the wire rods passing through cooperate, at least one roll of the pair of opposed rolls being able to move substantially parallel to itself on a plane containing the axes of the pair of opposed rolls, the pair of opposed rolls having respective shafts fitted to respective upper and lower supports, wherein the lower roll is able to move in a controlled rocking manner on the plane containing the axes of the pair of opposed rolls, the rocking being controlled by a bottom positioning screw and a return spring.

5,586,710 POWER STAPLER

Roman M. Golcz, Clinton, Conn., assignor to Roll Systems, Inc., Burlington, Mass.
Continuation-in-part of Ser. No. 976,275, Nov. 13, 1992, abandoned. This application Jan. 12, 1994, Ser. No. 180,427
Int. Cl.⁶ B25C 7/00

U.S. Cl. 227—155

9 Claims



7. A clincher assembly for use in a power stapler comprising: a clincher head defining a plane for receiving a face of a stack of sheets positioned above the plane; a pair of clinchers having substantially linear surfaces for engaging ends of a staple that is driven through the stack of sheets in a direction downwardly toward the clinchers;

the clinchers each including a respective pivot so that the clinchers move pivotally relative to the clincher head between a position substantially below the plane and a position substantially within the plane;
a clincher bar that is operatively connected with and that contacts the clinchers and that moves substantially linearly along a direction of linear motion to cause the clinchers to pivot between the position substantially below the plane to the position substantially within the plane to bend the ends of the staple so that the ends engage the stack; and
wherein the clincher bar includes an elongated slot having a direction of elongation aligned substantially along the direction of linear motion and a shaft located through the elongated slot and substantially fixed relative to the plane, the slot having an upper end and a lower end and the shaft being located so that the upper end is in engagement with the shaft when the clincher bar is located at a position that, thereby, pivotally locates the clinchers so that the linear surfaces each define an angle A1 of approximately 25 degrees whereby the ends of the staple are formed into curves as the ends are driven downwardly into engagement with the linear surfaces.



5,586,711 SURGICAL STAPLER WITH MECHANISMS FOR REDUCING THE FIRING FORCE

Alan K. Pyley; Claude A. Vidal; John L. Minck, Jr., all of Santa Barbara, Calif., and Alan J. Solyntjes, Richfield, Minn., assignors to United States Surgical Corporation, Norwalk, Conn.

Division of Ser. No. 236,379, May 2, 1994. This application Jun. 1, 1995, Ser. No. 457,877
Int. Cl.⁶ A61B 17/068

U.S. Cl. 227—176.1

7 Claims




1. A surgical stapler for applying staples to compressed tissue comprising:
a handle portion having surfaces adapted to be manually grasped by a surgeon;
a cartridge retention portion and an anvil retention portion, means for mounting said cartridge retention portion and said anvil retention portion for relative movement between a closed position in which said cartridge retention portion and said anvil retention portion are in closely spaced relationship for clamping tissue to be stapled therebetween and an open position in which said cartridge retention portion and said anvil retention portion are spaced farther from each other than in the closed position;
an anvil having a plurality of specially shaped surfaces,

said cartridge retention portion having a staple housing for enclosing six rows of staples in substantially parallel, linear rows having proximal and distal ends,
said six rows being spaced laterally across the staple housing such that any line drawn laterally across the staple line crosses at least three staples,
staple drivers adjacent staples, and a plurality of pushers each having camming surfaces, said staple housing being elongate to define a longitudinal axis,
said staple housing having a plurality of longitudinally extending pusher slots adapted to receive said pushers to afford movement of said pushers in a firing direction between pre-fired and fired positions, and a plurality of driver channels for receiving said staple drivers to afford movement of said staple drivers in a staple driving direction between pre-eject and ejected positions; and
each of said staple drivers having a cam follower surface for engaging the camming surface of a pusher to move the staple driver from the pre-eject toward the ejected position to substantially sequentially eject the staples in a row from the staple housing and press the ejected staples against the specially shaped surfaces of the anvil to engage, form and close staples in tissue clamped between the staple housing and the anvil.

5,586,712
APPARATUS FOR JOINING FOILS USED IN
SUPERCONDUCTING MAGNETS
Neil G. Fiddes, Columbia; Christopher G. King, Florence; Anthony Mantone, Effingham, and Frank D. Shaffer, Quimby, all of S.C., assignors to General Electric Company, Milwaukee, Wis.
Division of Ser. No. 148,303, Nov. 8, 1993. This application Jan. 9, 1995, Ser. No. 369,957
Int. Cl.⁶ B23K 37/04

U.S. Cl. 228—5.7

20 Claims




1. Apparatus for forming joints for foils used in superconducting magnet tape comprising:
means to provide squared end lengths of foils to be joined;
foil handling and positioning means to overlap the square ends of said foils;
means to guide a welder across the overlap;
said foil handling and positioning means including at least two independently controlled foil retainers with edge guards for said foil;
at least one positionable stop to control the sequential positioning of one of said square ends over the other of said square ends;
each of said foil retainers being energizable for initial placement and retention of said square ends proximate to each other, deenergizable during overlap positioning of one of said square ends against said at least one positionable stop, and reenergized to retain the positioned foil against said stop; and
means to offset said stop position a predetermined distance to control the amount of said overlap.

5,586,713
METHOD FOR WIRE BONDING
Kiyoshi Arita, and Kouichi Takahashi, both of Fukuma-machi, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan
Filed Aug. 30, 1994, Ser. No. 298,148
Claims priority, application Japan, Aug. 31, 1993, 5-215518; Feb. 9, 1994, 6-015179
Int. Cl.⁶ B23K 20/10; 31/02

U.S. Cl. 228—102

5 Claims




1. A wire bonding method which bonds a wire supplied by a capillary tool supported by a bonding arm to a bonding face of one of (a) a substrate and (b) a semiconductor chip using a bonding force derived from a driving means for driving the bonding arm, said wire bonding method comprising the steps of:
(a) lowering the capillary tool supplying the wire using the driving means controlled by a positioning control;
(b) reducing a lowering speed of the capillary tool almost to zero before the wire contacts the bonding face;
(c) changing the positioning control to a torque control;
(d) instructing the driving means to generate a specified bonding force before the wire contacts the bonding face;
(e) pushing the bonding face with the specified force when the wire contacts the bonding face, and
(f) wire bonding the wire to the bonding face.

5,586,714
METHOD OF BONDING METAL TO A NON-METAL
SUBSTRATE
Victor Curicuta; Dennis R. Alexander; Robert J. Deangelis, and Brian W. Robertson, all of Lincoln, Nebr., assignors to Board of Regents of the University of Nebraska, Lincoln, Nebr.

Filed Oct. 6, 1994, Ser. No. 319,014
Int. Cl.⁶ B23K 26/00

U.S. Cl. 228—122.1

13 Claims



1. A method of directly bonding a metal to a non-metallic substrate, comprising the steps of:
a. placing a metal in contact with a non-metallic substrate;

b. in the presence of a reactive gas, directly heating said metal by applying energy thereto by use of a laser, such that said reactive gas and metal form a eutectic which simultaneously wets the metal and non-metallic substrate at at least one point of contact therebetween;

such that said metal and non-metallic substrate are caused to be bonded to one another

5,586,715

METHOD OF MAKING SOLDER BALLS BY CONTAINED PASTE DEPOSITION


Matthew K. Schwiebert, Palo Alto; Donald T. Campbell, Campbell; Matthew Heydinger, Sunnyvale; Robert E. Kraft, Santa Clara, and Hubert A. Vander Plas, Palo Alto, all of Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif.

Continuation of Ser. No. 287,453, Aug. 8, 1994, Pat. No. 5,539,153. This application Mar. 19, 1996, Ser. No. 617,585

Int. Cl.⁶ H01L 21/60; H05K 3/34

U.S. Cl. 228—248.1

9 Claims



1. A method for producing solder balls comprising the steps of: selecting a mask having a plurality of openings; selecting a solder paste; selecting a substrate non-wettable by the solder paste selected; positioning the mask on the substrate thereby forming a substrate-mask assembly; applying solder paste to the mask side of the substrate-mask assembly so that the mask openings load with solder paste; heating the substrate-mask assembly at a temperature sufficient to reflow the solder paste into a solder ball; removing the mask after formation of the solder ball; and removing the solder ball from the substrate.

5,586,716

DESIGNER-COVER BOX

John D. Correll, 8459 Holly Dr., Canton, Mich. 48187

Continuation-in-part of Ser. No. 11,739, Aug. 13, 1993, Pat. No. Des. 356,254, Ser. No. 272,677, Jul. 8, 1994, and Ser. No. 86,318, Jul. 6, 1993. This application Jul. 21, 1994, Ser. No. 278,258


Int. Cl.⁶ B65D 5/42; 5/56

U.S. Cl. 229—110

8 Claims

1. A one-piece blank of foldable material cut and scored to define:

- a bottom panel;
- a rear wall hingedly attached to said bottom panel at a rear wall fold line;
- a front wall opposing said rear wall and hingedly attached to said bottom panel at a front wall fold line;
- first and second diagonal walls hingedly attached to said bottom panel at first and second diagonal wall fold lines, respectively;
- said first and second diagonal wall fold lines each being disposed adjacent to and at an oblique angle to said rear wall fold line;



first and second side walls hingedly attached to said bottom panel at first and second side wall fold lines, respectively; said first and second side wall fold lines each being disposed perpendicularly to said front wall fold line and extending to said first and second diagonal wall fold lines, respectively;

first and second ancillary wall panels hingedly attached to a top edge of said first and second diagonal walls, respectively;

first and second corner flaps hingedly attached to a first end of said first and second side walls, respectively;

a cover hingedly attached to a top edge of said rear wall, said cover comprising a cover panel and first and second cover side flaps;

said cover panel having a rear cover edge, a front cover edge opposing said rear cover edge, and first and second side cover edges;

said first and second cover side flaps being hingedly attached to said first and second side cover edges, respectively;

said cover panel having a first section of recessed cover edge disposed between first and second edge points and a second section of recessed cover edge disposed between third and fourth edge points.

5,586,717

CARTON AND CARTON HINGE CONSTRUCTION

Christopher P. Hallam, Bradford, United Kingdom, assignor to Concept Packaging Limited, Bradford, United Kingdom


Filed Feb. 9, 1995, Ser. No. 385,954

Claims priority, application United Kingdom, Feb. 9, 1994, 9402512

Int. Cl.⁶ B65D 5/56; 5/64

U.S. Cl. 229—116.1

8 Claims



1. A "book pack" type carton comprising:

a rigid rectangular inner component having four side walls and a bottom connected to the four side walls, the inner component defining an open top for receiving at least one article therein, one of the four side walls being a rear wall having a slot formed on an inner side thereof; and

an outer component assembled with the inner component, the outer component being a one-piece member including:

a generally rectangular base panel connected to the bottom of the inner component and extending beyond three of the four side walls of the inner component which do not include the rear wall;

a generally rectangular intermediate panel contiguous with the base panel and separated therefrom by a first fold line, the intermediate panel extending across the rear wall in a direction from the bottom of the inner component toward the open top of the inner component; and

a cover member for covering the open top of the inner component, the cover member extending beyond the three of the four side walls of the inner component when it covers the open top of the inner component and including: a generally rectangular outer cover panel contiguous with the intermediate panel and separated therefrom by a second fold line so as to be hingedly connected to the intermediate panel, the cover member being adapted to pivot about the second fold line for covering the open top of the inner component and having an underside;

a generally rectangular inner cover panel contiguous with the outer cover panel and separated therefrom by a third fold line, the inner cover panel being folded upon the underside of the outer cover panel along the third fold line to be in face-to-face relation with the underside of the outer cover panel such that an outer edge of the inner cover panel registers with the second fold line, the inner cover panel further including, at the outer edge thereof, a locating flap having a tongue slidably received in the slot formed on the inner side of the rear wall for assembling the outer component with the inner component.

engageable on a side of said latch opposite said notch such that said mail box door is in said closed position.

5,586,719

CONTROL SYSTEM FOR A HOT WATER TANK CONSTRUCTION, CONTROL DEVICE THEREFOR AND METHODS OF MAKING THE SAME


Jay R. Katchka, 10455 Hampshire Ct., Cypress, Calif. 90630

Continuation of Ser. No. 145,969, Oct. 29, 1993, abandoned, which is a continuation-in-part of Ser. No. 142,491, Oct. 22, 1995, abandoned. This application Nov. 28, 1994, Ser. No. 345,120

Int. Cl.⁶ F23N 5/02; F22B 37/42

U.S. Cl. 236—21 B

20 Claims



1. In a combination of a hot water tank construction having a combustion chamber means, a source of fuel, burner means for heating water in said tank construction and being disposed in said combustion chamber means of said tank construction, flame detecting means having means for generating an electrical current when sensing a flame at said burner means, and a control device for interconnecting said source of fuel to said burner means, said control device comprising a housing means, an electromagnetic means carried by said housing means, a movable valve means carried by said housing means and normally being disposed in a closed position thereof to prevent said source from reaching said burner means and being adapted to be held in an open position thereof by said electromagnetic means as long as said electromagnetic means remains energized so that said source of fuel can be interconnected to said burner means, said flame detecting means being operatively interconnected to said electromagnetic means to direct said electrical current thereto to energize said electromagnetic means, and a temperature responsive electrical switch means carried by said housing means and being operatively interconnected to said electromagnetic means so that said electromagnetic means is adapted to be energized by said flame detecting means when said switch means is in a first operating condition thereof by sensing a temperature below a certain temperature and is prevented from being energized by said flame detecting means when said switch means is in a second operating condition thereof by sensing a temperature above said certain temperature, the improvement wherein said switch means has a portion thereof disposed remote from said housing means and in a position to sense the temperature of an adverse heat roll out from said chamber means and thereby be in said second operating condition thereof if said sensed temperature of said heat roll out is above said certain temperature, said tank construction having wall means, said portion of said switch means being fastened to said wall means, said wall means having an opening means therethrough and defined by peripheral edge means of said wall means, said portion of said switch means having a part thereof comprising a fastening means and being fastened by said fastening means to a part of said peripheral edge means of said wall means.

5,586,718

SECURITY MAIL BOX LOCK ASSEMBLY


Stephen A. Speece, Youngstown, Ohio, assignor to Steel City Corporation, Youngstown, Ohio

Filed Feb. 13, 1995, Ser. No. 387,316

Int. Cl.⁶ B65D 91/00

U.S. Cl. 232—17

6 Claims



1. A mail box lock assembly securing a door of a rural mail box in a closed position, said rural mail box having cooperating frictional members on said door and said mail box, said lock comprising: a catch assembly and a lock assembly, said lock assembly comprising a cylinder keyed lock having a lock element with an engagement tab portion extending in planar relation therefrom, said lock element movable from a first locked and pre-set position to a second unlocked position, said catch assembly comprising a latch pivotally secured to said mail box, said latch having a tapered portion on its free end and a locking notch inwardly thereof, spring means on said latch and means for mounting said lock assembly to the door and means for pivotally securing said catch assembly to said mail box wherein, in the pre-set position the tab portion is


5,586,720

HOT WATER SUPPLY SYSTEM WITH A RING PIPELINE
Herbert Spiegel, Marktplatz 5, D-97464 Niederwerrn, and Robert Böhm, Schonungen, both of Germany, assignors to Herbert Spiegel, Niederwerrn, Germany
Filed Mar. 21, 1995, Ser. No. 407,914
Claims priority, application Germany, Mar. 23, 1994, 44 09 927.4

Int. Cl.⁶ F24D 3/02

U.S. Cl. 237—8 R

12 Claims



1. A hot water supply system, comprising:
a water heater;
a circulation pipeline;

at least one tap pipeline leading to a tap, said tap pipeline having therein said circulation pipeline of a smaller cross-section than said tap pipeline, with a section of said circulation pipeline extending from an interior portion of said tap pipeline and outwardly from said tap pipeline and terminating opening in proximity to said tap, said circulation pipeline being comprised of a pressure-proof material for that portion extending outwardly from said tap pipeline;

a first pipe branch piece made of continuous pipe, said first pipe branch piece being a component of said tap pipeline and having a branch pipe which receives said circulation pipeline, with a longitudinal axis of said branch pipe forming an acute angle with a longitudinal axis of said tap pipeline, the acute angle formed being open opposite a direction of flow in said tap pipeline with the section of said circulation pipeline extending to said tap being inserted endways into said branch pipe;

a second pipe branch piece; and,

a ring pipeline extending through said water heater in which heated water circulates in said ring pipeline before proceeding therefrom to at least one of said tap pipelines then to said tap, with ends of a remaining section of said circulation pipe joining at said branch pipe and, via said second pipe branch piece, open at said ring pipeline.

5,586,721


DUAL-CIRCUIT VEHICLE HEATER
Michael Humburg, Göppingen, Germany, assignor to J. Eberspächer, Esslingen, Germany
PCT No. PCT/DE94/00735, § 371 Date Aug. 17, 1995, § 102(e) Date Aug. 17, 1995, PCT Pub. No. WO95/03187, PCT Pub. Date Feb. 2, 1995
PCT Filed Jun. 23, 1994, Ser. No. 522,298
Claims priority, application Germany, Jul. 21, 1993, 43 24 371.1

Int. Cl.⁶ B60H 1/02

U.S. Cl. 237—12.3 B

15 Claims

1. A vehicle heating system, comprising:
a heater including means for generating heat by burning fuel for releasing heat to a fluid heat carrier;
a vehicle drive engine;
a heat exchanger for heat exchange with the interior space of the vehicle;



a heat carrier circuit with a flow pipe with an inlet, said flow pipe leading from the vehicle drive engine to said heater and leading from said heater to said heat exchanger, said flow pipe having an inlet and a return, which leads from said heat exchanger to said vehicle drive engine, as well as with a flow connection, which leads from said return to said inlet of said flow pipe, said inlet being located between said vehicle drive engine and said heater, a secondary circuit being formed, which passes through said heater and said heat exchanger bypassing said vehicle drive engine;

automatically switching two-way valve means with a freely movable switching element in combination with a check valve, said automatically switching two-way valve means being arranged in said flow pipe; and


a connection piece, said check valve being connected to said return by said connection piece.

5,586,722

TEMPERATURE AND FLOW CONTROL VALVE
Jerome L. Murray, 12 Aldersgate Cir., Budd Lake, N.J. 07828
Filed May 5, 1995, Ser. No. 435,188
Int. Cl.⁶ G05D 23/08

U.S. Cl. 236—93 B

18 Claims



1. A temperature and flow control valve, comprising:

a valve housing having a given axis;

first means at one axial end of said housing for admitting fluid therethrough and into said housing; and

second means at the opposite axial end of said housing for discharging fluid therethrough and from said housing; wherein said second means has a valve seat formed therewithin;

valving means, within said housing, and movable both toward and away from said seat for (a) closing off said second means to prohibit fluid flow through said second means, and (b) accommodating fluid flow through said second means, respectively;

means within said housing, and interposed between said seat and said valving means, for urging said valving means away from said seat;

barrier means, within said housing, for barring movement of said valving means to said one axial end of said housing;

piston means interposed between said barrier means and said first means for moving said valving means onto said seat for closure of said second means to fluid flow therethrough; and wherein

said barrier means comprises means (a) for restraining said piston means from causing movement of said valving means, and (b) responsive to a given temperature of admitted fluid for


releasing said piston means, to permit said piston means to move said valving means onto said seat, respectively.

5,586,723

LIQUID SPRAY NOZZLE WITH LIQUID INJECTOR/EXTRACTOR
Shikui Chen, Carol Stream, and Ted Butterfield, Naperville, both of Ill., assignors to Spraying Systems Co., Wheaton, Ill.
Filed Oct. 7, 1994, Ser. No. 319,608
Int. Cl.⁶ B05B 3/14

U.S. Cl. 239—102.2

9 Claims



9. A liquid ejector comprising a housing defining a chamber having an open side, a vibratable member having first and second sides and at least one discharge aperture extending between said sides, said first side of said vibratable member closing said chamber, said vibratable member being made of a piezoelectric material which is vibratable when subjected to a high frequency alternating current voltage, said housing defining a liquid flow passage for supplying liquid to said chamber, said vibratable member being operable upon being vibrated for ejecting at least a portion of the liquid supplied to said chamber through said discharge aperture, said housing defining an excess liquid siphon passage communicating with said chamber for drawing excess liquid from said chamber not ejected by said vibratable member as an incident to the supply of liquid through said flow passage.

5,586,724


TAPERED PLUG FOAM SPRAY APPARATUS
Peter B. Allen, Slidell, La., assignor to Lockheed Martin Corporation, Bethesda, Md.

Filed Mar. 9, 1995, Ser. No. 401,606

Int. Cl.⁶ B05B 7/04;15/02

U.S. Cl. 239—112

6 Claims



1. A foam spray device for spraying multicomponent foam in response to a flow, under pressure, of first and second reactant fluids from ratio-controlled sources of said first and second reactant fluids, and for purging in response to a flow, under pressure, of purging gas from a gas source, said device comprising:

a body with a cavity defining a principal axis of said body, and also defining first and second reactant fluid inlet ports adapted to be connected to said sources for receiving said first and second reactant fluids, respectively, said first and second reactant fluid inlet ports intersecting said cavity, and being centered on a second axis which is transverse to, and intersects, said principal axis, said body further defining at least a first purge port adapted to be connected to said gas source, said first purge port intersecting said cavity, and being centered on a third axis which is transverse to, and intersects, both said principal and second axes, said cavity extending through said body from an assembly insertion aperture at a first end thereof to a front aperture at a second end thereof, whereby said second and third axes together define a port plane in which said ports lie, said body cavity defining a first inner surface portion in the form of a right circular cylindrical surface which is centered on said principal axis of said body and traversed by said port plane;

a valve bearing of a moldable material in the general shape of a cylindrical annulus, said valve bearing having a right circular cylindrical outer surface centered about a first packing axis, and a cylindrical inner surface which tapers in a particular manner from a first diameter at a front end thereof to a second diameter, larger than said first diameter, at a second end thereof, said valve bearing also defining first and second apertures extending therethrough, coaxial with a second packing axis which is transverse to, and intersects, said first packing axis, and at least a third aperture extending therethrough, coaxial with a third packing axis which is transverse to, and intersects, both said first and second packing axes, said valve bearing being located within said cavity of said body, with said first packing axis centered on said principal axis of said body, with said second diameter portion remote from said front aperture of said cavity, and with said outer surface of said valve bearing contiguous with said first inner surface portion of said body, and with said first, second, and third apertures in said valve bearing lying in said port plane;

a valve and tip piece, said valve and tip piece being centered on a first valve and tip piece axis, said valve and tip piece including a dispensing end and a rotation drive end mutually displaced along said first valve and tip piece axis, and also including a rotational drive attachment at said rotation drive end, said valve and tip piece also defining a longitudinal mixing cavity extending along said first valve and tip piece axis, said valve and tip piece also including a conical portion with an outer surface in the shape of a portion of a cone, said conical portion being centered on said first valve and tip piece axis, said cone tapering from (a) a first diameter adjacent said dispensing end of said valve and tip piece, which first diameter is substantially equal to said first diameter of said cylindrical inner surface of said valve bearing, to (b) a second diameter adjacent said rotation drive end of said valve and tip piece, which second diameter is substantially equal to said second diameter of said cylindrical inner surface of said valve bearing, said conical portion having said particular taper, said valve and tip piece also defining first and second apertures extending therethrough, coaxial with a second valve and tip piece axis which is transverse to, and intersects, said first valve and tip piece axis, said valve and tip piece also including a second portion lying between said rotation drive end and said conical portion, said second portion being in the form of a right circular cylinder centered on said first valve and tip piece axis, with a diameter less than that of said second diameter of said cone, the transition between said first and second portions of said valve and tip piece being made by a bearing surface, said cavity in said valve and tip piece extending from said dispensing end at least to said second valve and tip piece axis, said valve and tip piece being located within said cavity of said body, with said dispensing end protruding from said front aperture of said body, with said rotation drive end accessible from the exterior of said body, and with said first and second apertures in said conical portion lying in said port plane, whereby, in a first rotational position of said valve


and tip piece, said first and second apertures in said conical portion align with said first and second ports of said body to provide a path between said first and second ports of said body and said mixing cavity in said valve and tip piece, and in a second rotational position of said valve and tip piece, said first and second apertures in said conical portion misalign with said first and second ports of said body, and at least one of said apertures in said conical portion aligns with said purge port, to provide a path between said purge port and said mixing cavity in said valve and tip portion;

a packing washer of a moldable material, said packing washer having an inner diameter substantially equal to said diameter of said second portion of said valve and tip piece, and having an outer diameter no smaller than said second diameter of said conical portion of said valve and tip piece, said packing washer being located within said cavity in said body, and bearing on said bearing surface of said valve and tip piece; and

nonelastic washer compression means including a washer bearing surface and a valve and tip piece clearance aperture, said washer compression means being affixed to said body, with said clearance aperture surrounding said second portion of said valve and tip means, and with said washer bearing surface bearing on said packing washer, for maintaining said packing washer in position by application of pressure thereto, whereby a seal is formed by which the pressure of said sources is prevented from causing flow of said reactant fluids around said packing washer.

5,586,725
DEVICE FOR PRODUCING AN AIR STREAM HAVING A FLATTENED SHAPE IN TRANSVERSE SECTION
Patrick J. Ballu, Reims, France, assignor to Tecnomat, Epernay, France


Filed Nov. 9, 1994, Ser. No. 338,738
Claims priority, application France, Nov. 10, 1993, 93 13437
Int. Cl.⁶ A01G 25/09
U.S. Cl. 239—172 14 Claims



1. A device for producing an air stream having a flattened shape in transverse section, this device comprising:
at least two diffusers, each diffuser being formed of a convergent-divergent pipe which is open at both ends, said diffusers being placed in a plane of the longest dimension of the transverse section of the air stream which it is desired to obtain; and
an injector associated with each diffuser, generally coaxial with the pipe forming the diffuser, and situated in its convergent part, being directed toward the divergent part, said injector being connected by compressed air conveying means to a centrifugal compressor such that the compressed air produced by the compressor and sprayed by the injector sets the air located in the diffuser into motion or accelerates it, by a venturi effect.


said device further comprising a box structure which can be fed with compressed air by the centrifugal compressor and constitutes a main manifold, said diffusers being mounted in said box structure so as to be situated in said plane of the longest dimension of the transverse section of the air jet to be produced, and wherein said injectors are placed inside said diffusers and are connected to the inside of the box structure by feed pipes.

5,586,726
COLLISION TYPE FUEL INJECTION NOZZLE AND METHOD OF MANUFACTURING THE NOZZLE
Yuji Furuya, and Kenichi Iino, both of Higashi-Matsuyama, Japan, assignors to Zexel Corporation, Japan
Filed Jul. 28, 1995, Ser. No. 508,867
Claims priority, application Japan, Jul. 29, 1994, 6-196251
Int. Cl.⁶ F02M 61/18
U.S. Cl. 239—533.12 12 Claims




11. A method of manufacturing a collision type fuel injection nozzle comprising a nozzle body in which are formed a fuel passage, a collision recess, fuel inlets in communication with the fuel passage, and at least one pair of injection nozzle holes that communicate with the fuel inlets and open out into the collision recess in opposition to each other, and a nozzle element that reciprocates in the nozzle body to inject atomized fuel from the collision recess the method comprising the steps of
forming fuel inlets that extend from the fuel passage and avoid the collision recess,
simultaneously forming the at least one pair of injection nozzle holes in a straight line that intersects the fuel inlets and the collision recess, and
affixing a cap over at least a peripheral portion of the injection nozzle holes.

5,586,727
FLOW REDUCER DEVICES AND DRIP IRRIGATION EMITTER INCLUDING SAME
Avraham Shekalim, Neshet, Israel, assignor to Hydromatic Ltd., Migdal Haemek, Israel
Filed Nov. 28, 1994, Ser. No. 348,173
Claims priority, application Israel, Dec. 24, 1993, 108171
Int. Cl.⁶ B05B 1/30
U.S. Cl. 239—542 16 Claims




1. A flow reducer device attachable to a tube of pressurized fluid for reducing flow of a fluid therefrom, comprising: a body member formed with a fluid inlet, a fluid outlet, and a flow regulating region between said inlet and outlet;

said flow regulating region including a cavity extending through opposite faces of the body member closed by a side of a deformable diaphragm at each of said opposite faces;
said body member being further formed with an inlet passageway leading from said fluid inlet into the cavity, and an outlet passageway leading from said cavity to the fluid outlet;
said body member being formed with a plurality of baffles to define a labyrinth in said inlet passageway for reducing the pressure of the fluid flowing therethrough into said cavity;
said device being attachable to the tube of pressurized fluid such that an outer face of each diaphragm side is exposed to fluid pressure at said fluid inlet, and an inner face of each diaphragm side is exposed to fluid pressure within said cavity, whereby the diaphragm sides deform towards or away from each other within said cavity in response to changes in the inlet pressure to regulate the fluid flow via said cavity to said outlet passageway.



5,586,728
PRE-PLANT SOIL TREATMENT METHOD AND APPARATUS
Michael V. McKenry, 2793 S. Wakefield, Reedley, Calif. 93654
Division of Ser. No. 159,684, Nov. 29, 1993, Pat. No. 5,421,514. This application Mar. 6, 1995, Ser. No. 398,909
Int. Cl.⁶ B05B 7/26
U.S. Cl. 239—734 5 Claims



1. A portable apparatus for pre-treating soil before planting comprising:
a. a plurality of low atomizing sprinkler heads that may be removably connected to a first manifold on an existing linear irrigation system, said manifold connected to a water source;
b. a pump means at said water source;
c. a means for mixing biocidal materials with water at said water source for introduction into said apparatus; and
d. a plurality of conduit lines removably deployed behind the motorized assemblies of said irrigation system, each line having a plurality of drip irrigation emitters attached thereto at regularly spaced intervals wherein one end of each line is closed, and each line is attached to a second manifold for connection between the open ends of said deployed conduit lines and said water source.


5,586,729
FUELS BLENDING SYSTEM AND METHOD OF USING
Ricky W. Davenport, 814 Omega Dr., Lafayette, La. 70506
Division of Ser. No. 368,386, Dec. 30, 1994, Pat. No. 5,495,986, which is a continuation of Ser. No. 60,753, May 12, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 480,844
Int. Cl.⁶ B02C 7/04; 7/14; 23/02
U.S. Cl. 241—21 20 Claims

1. A method for grinding and dispersing solid particles in a fluid and agitating said fluid to produce a mixture having uniform properties comprising the steps of:

5,586,730
FLUORESCENT LAMP COLLECTION AND SEPARATION METHOD AND APPARATUS
Jon P. Mortrud, Cottage Grove, Wis., assignor to Budget Lamp Reclaimers, Inc., Madison, Wis.
Filed Mar. 10, 1995, Ser. No. 402,203
Int. Cl.⁶ B02C 19/12
U.S. Cl. 241—24.22 27 Claims

1. Mobile lamp collection and separation apparatus comprising: a wheeled mobile vehicle transportable to a facility site where lamps to be processed are located;

a) introducing coarsely sized solid particles and fluidics material simultaneously into a vessel in which is located a rotary dispersion and agitation means said dispersing means comprising a rotary plate and a stationary plate surrounded by an accumulation ring, said rotary and stationary plate having opposing faces fitted with intermeshing shear blocks, forming an attrition zone therebetween capable of variable displacement and having an inlet and outlet, said attrition zone having a plurality of particle reduction stages;
b) producing a fluidics mixture of said coarsely sized solids and fluidics material via exposure to said rotating dispersion and agitation means, said agitation means further comprising, a plurality of vanes located externally on said rotating dispersion means;
c) agitating and circulating said fluidics mixture in said vessel via said rotating vanes constantly;
d) reducing said coarsely sized solid particles to a consistent size via the striking action of said rotating vanes against said solid particles until such particles are sufficiently sized to allow entry into said inlet of said attrition zone for further size reduction;
e) ingesting sized solid particles and fluidics material into said attrition zone while rejecting all oversized solid particles from said inlet and simultaneously preventing plugging of said inlet with oversized solid particles, due to vane action;
f) processing said ingested mixture of said solid particles and fluidics mixture from said inlet through said plurality of particle reduction stages in said attrition zone;
g) directing said ingested mixture radially through said reduction stages in said attrition zone;
h) shearing said sized solid particles in the ingested mixture to a selectable, particle size as the solid particles travel radially through said attrition zone thus producing a mixture of finely reduced solid particles of a specified size in the fluidics mixture;
i) discharging said reduced solid particle laden fluidics mixture through said outlet in said accumulation ring back into said vessel for reintroduction into the unprocessed fluidics and solid particle mixture; and
j) reprocessing of said fluidics mixture contained within said vessel by said dispersion means until all solid particles introduced into said vessel have been consistently reduced and dispersed into the fluidics component of said mixture.



separation apparatus mounted to the mobile vehicle, the separation apparatus comprising:

(a) a collection bin having an interior and a door mounted to open to allow lamps to be placed in the interior of the collection bin and to be closed to seal the interior of the collection bin, the bin having a discharge end;

(b) crusher means, mounted to receive tubes discharged from the discharge end of the collection bin, for crushing the tubes to particulates of glass and metal and dust mixed therewith;

(c) separator means receiving mixtures of crushed glass, metal particulates and powder and separating the particulates and discharging them to a particulates discharge port and discharging the dust carried by air to a dust exhaust discharge port;

(d) conveyor means for conveying the mixtures of crushed glass, metal and dust from the crusher means to the separator means;


(e) a dust filter for filtering dust from air; and

(f) a conduit for conducting the dust carried by air from the dust exhaust port of the separator means to the dust filter, the dust filter collecting the solid dust and having a discharge port from which the collected dust may be discharged.

5,586,731

COMPOST MIXING AND AERATING APPARATUS
 Bradley S. Glaze, Lyons, and Kenneth R. Warner, Gladstone, both of Oreg., assignors to Frontier Manufacturing Company, Brooks, Oreg.
 Continuation-in-part of Ser. No. 918,528, Jul. 21, 1992, abandoned. This application Jul. 11, 1994, Ser. No. 273,566
 Int. Cl.⁶ A01B 9/00; B02C 21/02
 U.S. Cl. 241—56

43 Claims



1. A drum and paddle assembly for mixing and aerating a windrow of composting material comprising:

a. an elongate drum having a longitudinal axis, first and second end portions, and a center portion, the drum being rotatable about its longitudinal axis at a predetermined rotational speed; and


b. means extending outwardly from the drum for generating a compost entraining air stream when the drum is rotated at the predetermined speed, the compost entraining air stream having a sufficient velocity for entraining substantially all of the composting material therein for mixing and aerating the windrow of composting material when the rotating drum is engaged therewith.

5,586,732

CRUSHING AND DISPERSING BAG
 Hiroshige Yamauchi, Kobe, and Shonosuke Nishi, Kawanishi, both of Japan, assignors to Shimagyu Chemical Co., Ltd., Osaka, Japan
 PCT No. PCT/JP93/00963, § 371 Date Dec. 23, 1994, § 102(e) Date Dec. 23, 1994, PCT Pub. No. WO95/02457, PCT Pub. Date Jan. 26, 1995
 PCT Filed Jul. 12, 1993, Ser. No. 360,746
 Claims priority, application Japan, Jan. 16, 1992, 4-5808
 Int. Cl.⁶ A47J 43/04

U.S. Cl. 241—168

19 Claims



1. A crushing and dispersing bag comprising:

a synthetic resin bag member open at one end thereof and being provided with at least a first plurality of parallel ridges, sized to facilitate comminution of material inserted into the synthetic resin bag member by grinding the material into smaller pieces, on an inner surface of the synthetic resin bag member; and

a sealing member for sealing the open end of the synthetic resin bag member;

wherein said synthetic resin bag member has two opposed inner surfaces and said sealing member comprises a groove provided on one of the inner surfaces and a projection provided on the other of the inner surfaces, which projection is sized to be received in the groove in an interference fit, to thereby seal the bag member.

5,586,733


TAKE-UP REEL FOR METALLIC FILAMENTS
 Yoshihiro Miura, and Masami Goto, both of Tochigi-ken, Japan, assignors to Bridgestone Metalpha Corporation, Tokyo, Japan
 Filed Jul. 19, 1995, Ser. No. 504,007
 Claims priority, application Japan, Jul. 21, 1994, 6-191878
 Int. Cl.⁶ B65H 75/28; 51/015

U.S. Cl. 242—125.2

5 Claims

1. A metallic-filament take-up reel for carrying a filament, comprising:

a winding drum with first and second axial ends;



first and second flanges having inner sides respectively abutting said first and second axial ends to hold said filament therebetween;

at least one flange of said first and second flanges defining an access hole and a concavity on said inner side thereof, the concavity having a base surface and a peripheral wall descending from said inner side to said base surface;

said at least one flange further defining an aperture in a portion of said peripheral wall;

a metallic-filament retainer having a base portion fixed to said base surface of said concavity, a hook portion, and an intermediate portion connecting said hook portion to said base portion;

said intermediate portion extending from said base portion through said aperture and terminating at said hook portion to dispose said hook portion above the access hole for passage therethrough to catch said filament between said inner side and said hook portion; and


said retainer being formed of a material having a modulus of elasticity sufficient for permitting deflection of said hook portion through said access hole and for retaining said filament between said inner side and said hook portion.

5,586,734

SPINNING REEL HAVING AN ANTI-REVERSE MECHANISM

Yuzo Kawabe, Izumi, and Noboru Sakaguchi, Tondabayashi, both of Japan, assignors to Shimano Inc., Osaka, Japan
 Division of Ser. No. 59,672, May 12, 1993, Pat. No. 5,547,140.
 This application Mar. 7, 1995, Ser. No. 400,071
 Claims priority, application Japan, May 13, 1992, 4-31071 U
 Int. Cl.⁶ A01K 89/02; F16D 55/02
 U.S. Cl. 242—247

11 Claims



1. A spinning reel comprising:

a reel body;

a rotor provided on said reel body, said rotor including a sleeve shaft rotatable with said rotor and a cylindrical portion surrounding said sleeve shaft;

an anti-reverse mechanism for preventing said rotor from rotating in a line unwinding direction, said anti-reverse mechanism including:

engaging teeth defined on an inner surface of the cylindrical portion of said rotor along its inner periphery;

an engaging pawl supported on said reel body, said pawl being displaceable between an operative position engageable with said engaging teeth and an inoperative position disengaged from said engaging teeth;

a brake mechanism for applying a braking force to said rotor in a line unwinding direction, said brake mechanism including a one-way clutch mechanism mounted on said sleeve shaft;

a selector mechanism for displacing said engaging pawl and operating said braking mechanism, said selector mechanism including a cam member switchable between a first mode and a second mode;

wherein said cam member places said engaging pawl in said operative position and operates said braking mechanism to apply a braking force in said first mode; and

wherein said cam member places said engaging pawl in said inoperative position and operates said braking mechanism to remove said braking force in said second mode.

5,586,735

TWO-DIMENSIONAL SUPERSONIC AND HYPERSONIC AIR INTAKE, WITH THREE MOVABLE RAMPS, FOR THE COMBUSTION AIR OF AN AIRCRAFT ENGINE


Francois Falempin, Saint Arnould en Yvelines; Olivier Fourt, Jouy en Josas, and Jean-Louis Pastre, Sainte Genevieve des Bois, all of France, assignors to Office National d'Etudes et de Recherches Aerospatiales, Chatillon-sous-Bagneux, France

Filed Sep. 30, 1994, Ser. No. 316,347

Claims priority, application France, Oct. 1, 1993, 93 11726
 Int. Cl.⁶ B64D 31/00; 33/02

U.S. Cl. 244—53 B

7 Claims




1. A two-dimensional variable-geometry supersonic and hypersonic air intake, for the combustion air of an aircraft engine, placed under the wings or the fuselage of the aircraft and comprising two main flaps arranged face to face and each movable about a pivot axis situated in the vicinity of one wall of the air intake which extends the main flap in question rearwards, in which wall is arranged a first boundary layer bleed, the pivot axes of the two main flaps being substantially parallel to the plane of the wings or of the fuselage, so that the abovementioned main flaps move perpendicularly to this plane, wherein a ramp, which is movable about a pivot axis substantially parallel to the pivot axes of the main flaps, and situated in proximity to its leading edge, is arranged upstream of the main flap closest to the wings or to the fuselage, this upstream ramp being adjacent, at its leading edge, to the wings or to the fuselage and delimiting, with said main flap, a boundary layer bleed of variable cross section and wherein the boundary layer bleed of variable cross section may be of zero cross section.

5,586,736

CAB SIGNAL SENSOR WITH NOISE SUPPRESSION
 Samuel R. Mollet, Blue Springs, Mo., assignor to Harmon Industries, Inc., Blue Springs, Mo.
 Filed Jun. 16, 1995, Ser. No. 491,247
 Int. Cl.⁶ B61L 3/00

U.S. Cl. 246—194

14 Claims



1. In a cab signal system having a receiver on board a locomotive and in which control information transmitted through the rails to the locomotive utilizes a carrier having a frequency in a predetermined range, wherein the locomotive employs an alternating current drive motor that emits high level noise by producing a magnetic field in said frequency range, the improvement comprising:

a pair of horizontally spaced pickup coils for sensing a magnetic field around one of the rails produced by said control information;

each of said coils having an upright axis and an axially extending magnetic core component, means interconnecting said core components for establishing a flux path therebetween;

means for mounting said pickup coils on said locomotive in an environment in which said noise is present but in operative positions closely spaced from an underlying rail and with the coils spaced transversely thereof;

means interconnecting said coils in a manner to provide voltage addition in response to the magnetic field produced by said control information, and voltage subtraction in response to said noise; and

input circuit means for said receiver operably connected to said coils, whereby to suppress interfering noise from the drive motor and deliver sensed information to the receiver.

5,586,737

SWITCH MACHINE CAM BAR

Daniel W. van Alstine, Rochester, and Charles M. Eggebrecht, Churchville, both of N.Y., assignors to General Railway Signal Corporation, Rochester, N.Y.
 Continuation of Ser. No. 293,127, Aug. 19, 1994, abandoned.
 This application Mar. 28, 1996, Ser. No. 624,186
 Int. Cl.⁶ E01B 7/00


U.S. Cl. 246—448

17 Claims

12. A switch machine for switching a position of a railroad track, comprising:

a lock bar having a particular locking position in said switch machine; and

a cam bar having a positioning section, a locking section separably attached to said positioning section for locking said lock bar at said particular locking position, and means for interlocking said locking section to said positioning section,



wherein said interlocking means allows said positioning section to separate from said locking section when said locking section is not able to lock said lock bar at said particular locking position,

wherein said positioning section has a first ridge having a linear sloping edge at one end thereof, and said interlocking means has a second ridge having a linear sloping edge that positions over said linear sloping edge said first ridge so that said locking section is capable of interlocking to said positioning section.


5,586,738

TUBING BRACKET ASSEMBLY

James C. Binelli, Grand Blanc, Mich., assignor to Lab Holding Company, W. Muskegon, Mich.
 Filed May 8, 1995, Ser. No. 438,069
 Int. Cl.⁶ F16L 3/00

U.S. Cl. 248—73

15 Claims



1. A clamp for clamping a tube to a support, said clamp comprising:

two opposed generally C-shaped engagement rings for engaging a tube to be clamped, each of said engagement rings having opposed ends generally facing each other;

two bridging members, one of said bridging members extending between one of said ends of each of said opposed engagement rings and the other bridging member extending between the other one of said ends of each said opposed engagement members such that said bridging members extend generally parallel to one another;

said rings being adapted to partially encircle a tube to be clamped with said bridging members extending generally longitudinally along the exterior of said tube; and a bracket for mounting said clamp to a support, said bracket being adapted to be attached to said bridging members.

5,586,739

PIPE CLAMP


Gebhard Gantner, Nenzing, Austria; Franz Dengg, Saarbrücken, Germany; Peter Ofner, Feldkirch, Austria, and Herbert Münzenberger, Wiesbaden, Germany, assignors to Hilti Aktiengesellschaft, Schaan, Liechtenstein
 Filed Mar. 31, 1995, Ser. No. 415,016

Claims priority, application Germany, Mar. 31, 1994, 44 11 220.3

Int. Cl.⁶ F16L 3/08

U.S. Cl. 248—74.1

10 Claims



1. Pipe clamp with an annular wall part (1, 21) having a central axis and a circumferentially extending outside surface, at least one attachment part (2) extending radially outwardly from said outside surface of said wall part (1, 21), wherein the improvement comprising that said attachment part (2) having a radially inner section detachably connected to the outside surface of said wall part (1, 21) and a radially outer section, said wall part (1, 21) comprises at least one bracket (3, 22, 23) projecting radially outwardly from the outside surface thereof, and said attachment part being detachably connected to said bracket, and wherein said bracket forms an opening extending parallel to said central axis and arranged to receive said radially inner section of said attachment part.


5,586,740

CHUCKLESS POWER SEAT ADJUSTER SLIDE

Hans J. Borlinghaus, Mt. Clemens; James P. Nini, and Thomas B. Blake, both of Clinton Township, all of Mich., assignors to General Motors Corporation, Detroit, Mich.
 Filed Dec. 19, 1994, Ser. No. 359,305
 Int. Cl.⁶ F16M 11/00

U.S. Cl. 248—157

7 Claims



1. A four-way powered seat adjuster slide unit comprising:
 a top rail for mounting a vehicle seat;

a bottom rail for supporting the top rail;
 a guide rail pivotally joined to the top rail and to the bottom rail along generally opposite ends to stabilize the top rail;
 a first forward jack screw unit with a powered extendable jack screw, the jack screw unit having fixed pivotal axes in positions fixed with respect to the top and bottom rails; and
 a second rearward jack screw unit with a powered extendable jack screw, the jack screw unit having fixed pivotal axes in positions fixed with respect to the top and bottom rails.


5,586,741

CLIP-ON COMPUTER DISC HOLDER

Gregory S. Cuneo, 49 Balcom St., Mansfield, Mass. 02048
 Filed May 11, 1995, Ser. No. 439,252
 Int. Cl.⁶ A47B 96/06

U.S. Cl. 248—229.26

3 Claims



1. A device for removably retaining on a planar member at least one planar computer disc having side edges, comprising:

a one-piece structure having a substantially planar rear wall, said rear wall having a left side, a right side, a top, a bottom, a front surface and a back surface;

a curved spring clip member having a top bend connected to said top of said rear wall, said spring clip member disposed extending downward, from said top bend's connection to said top of said rear wall, adjacent to said back surface of said rear wall and defining a planar member receipt area therebetween, said spring clip member urging toward said back surface of said rear wall for quick and easy installation and removal of said device from said planar member;

a left side wall and a right side wall, each extending a distance, respectively, from said left side and right side of said rear wall, said left side wall and right side wall being perpendicular to said rear wall;

a base extending forwardly and perpendicular from said bottom of said rear wall;

a left front wall and a right front wall extending, respectively, inwardly a distance and perpendicularly from said left side wall and said right side wall, said left front wall and said right front wall each having, respectively, an inside edge, and an unobstructed central opening defined between said inside edges of said left front wall, right front wall, and said base, said side walls and said front walls defining a storage area therebetween;

disc retention means formed from a portion of each front wall, said disc retention means biased to press against and releasably hold said computer disc placed within said storage area to allow for the quick and easy removal and reinsertion of said computer disc out of and into said storage area; and

wherein said disc retention means comprise an L-shaped left cut having a lower portion thereof defined in said left front wall and an L-shaped right cut having a lower portion thereof defined in said right front wall, said lower portions each directed toward one another, said L-shaped left cut and said L-shaped right cut disposed in proximity to said inside edges, respectively, of said left front wall and said right front wall forming, respectively, a left retention member bounded by said L-shaped left cut and said central opening and a right retention member bounded by said L-shaped right cut and

said central opening, each of said retention members bent toward said rear wall to contact, maintain pressure on and releasably hold said computer disc in said storage area.


5,586,742

LIGHT STANDARD APPARATUS

E. Ray Carter, 2515 N. 7th St., Phoenix, Ariz. 85006
Continuation of Ser. No. 238,001, May 3, 1994. This application Apr. 22, 1996, Ser. No. 595,099
Int. Cl.⁶ F21V 7/00

U.S. Cl. 248—545

12 Claims



1. Light standard apparatus for supporting an electrical fixture to be connected to electrical conductors within the light standard apparatus, including a ground conductor, comprising in combination:

- a nonconductive post for receiving electrical conductors, said nonconductive post including a ground conductor therein;
- a nonconductive cap secured to the post;
- means for securing the electrical fixture to the cap, including a nonconductive bushing; and
- means for grounding the electrical fixture, including a first ground portion in the bushing for providing electrical connection with the fixture, and a second ground portion connected to the first ground portion to be connected to the ground conductor in the post.

5,586,743

AUGER STAND


Eddie A. Sodalak, 144 Chew Rd., Sealy, Tex. 77474
Filed Jan. 6, 1995, Ser. No. 369,705
Int. Cl.⁶ F16M 1/00

U.S. Cl. 248—671

26 Claims

1. An auger stand for an auger assembly, said auger assembly having a hub, an auger extending beneath the hub, a boom extending outwardly from the hub, and a drive shaft, said auger stand comprising:

- (a) a rack comprised of a set of front and rear posts connected by support rods and forming a support frame having an opening for receiving the auger;
- (b) a support plate member mounted on said support rods proximate the top of said rear posts of said rack and extending laterally across said opening and adapted to fit beneath said auger hub;



- (c) said support plate member having an upper surface extending across said opening adapted to receive said auger hub to rest thereon;
- (d) said support plate member having a slot extending downwardly therethrough for said auger to extend downwardly from said auger hub through said support plate member; and
- (e) coupling assembly connected to said rack forward of said front posts and said support plate member, said coupling assembly comprising a transverse support beam extending across said opening in said support frame for receiving said auger boom thereon and supporting said boom during mounting and dismounting of said auger assembly from a vehicle.


5,586,744

BOOST DEVICE BYPASS VALVE

James C. Smith, Washington, Ill., and Dennis R. Walling, Lafayette, Ind., assignors to Caterpillar Inc., Peoria, Ill.
Filed May 11, 1995, Ser. No. 439,049
Int. Cl.⁶ F16K 31/145

U.S. Cl. 251—61.5

7 Claims



1. A bypass valve, comprising:

- a housing;
- a manifold adapted for containing pressurized gas therein;
- a piston movably disposed in said housing, said piston defining first and second chambers in said housing and being actuable between first and second positions;
- a first sealing member connected to said piston, said first sealing member being adapted for sealing against an opening of said manifold;

an annular diaphragm connected between said piston and said housing to seal between said first and second chambers, said annular diaphragm flexing as said piston is actuated between said first and second positions;

said annular diaphragm being pre-formed to define an outer annular portion adapted for connecting to said housing, an inner annular portion adapted for connecting to said piston and a middle portion generally U-shaped in cross-section arranged between said outer annular portion and said inner annular portion;

said annular diaphragm flexing uniformly between a first position in which said middle portion is in compression and a second position in which said middle portion is in tension.

5,586,745

VALVE FOR CONTROLLING FLOW OF CRYOGENIC FLUID


Philip A. Knapp, Moore, Id., assignor to The United States of America as represented by the United States Department of Energy, Washington, D.C.

Filed Jun. 5, 1995, Ser. No. 462,338

Int. Cl.⁶ F16K 47/00

U.S. Cl. 251—121

25 Claims



1. A cryogenic valve comprising:

- a body having an internal valve chamber with an inlet and an outlet communicating through said body into said valve chamber;
- a valve stem, said valve stem disposed at least partially in said body and in communication with said valve chamber;
- a needle valve disposed within said valve chamber and affixed to a distal end of said valve stem;
- a disk valve in communication with said needle valve and disposed within said valve chamber;
- means for sealing and seating said disk valve to said needle valve, and thereby forming a needle valve assembly; and
- rotating means for allowing said valve stem to rotate with respect to said needle valve assembly.

5,586,746

FAUCET WITH MOTION-DETECTOR ON/OFF CONTROL

Jürgen Humpert, Hemer; Bruno Heimann, Fröndenberg, and Christian Frankholz, Schwerte, all of Germany, assignors to Friedrich Grohe Aktiengesellschaft, Hemer, Germany


Filed Jun. 8, 1995, Ser. No. 488,479

Claims priority, application Germany, Jun. 10, 1994, 44 20 330.6

Int. Cl.⁶ F16K 31/06; E03C 1/05

U.S. Cl. 251—129.04

8 Claims



1. A plumbing fixture comprising:
 - a housing provided with a water inlet and formed with a water outlet and with a circuit pocket;
 - means for securing the housing to a support surface;
 - an electrically operated valve in the body between the inlet and outlet and having an electrical feed wire energizable for movement of the valve between a closed position blocking flow between the inlet and outlet and an open position permitting such flow;
 - an insert fittable in the pocket, provided with a window, and formed with a battery compartment;
 - means for fixing the insert in the pocket with the window facing forward out of the pocket;
 - a battery in the compartment; and
 - electrical circuit means in the insert connected to the feed wire and to the battery and including a proximity detector behind the window for opening the valve on detection of a solid object in front of the housing.

5,586,747

ADJUSTABLE SOLENOID VALVE WITH IMPROVED STABILITY

Gilbert Bennardo, Nice, and Aimé Goubely, La Trinité, both of France, assignors to Eaton Corporation, Cleveland, Ohio


Filed Dec. 13, 1994, Ser. No. 355,386

Int. Cl.⁶ F16K 31/06

U.S. Cl. 251—129.18


16 Claims

1. A solenoid valve having preset manual adjustability of a first (5) armature part relative to the valve body and a second armature part (6) driven by the solenoid relative to the valve body, the parts being separated by a gap (7), characterized by a self-cutting or self-tapping thread (8) moving with the first armature part (5) and adapted to engage a valve body portion (1), thereby presetting said gap (7); wherein said first armature part is characterized by a self tapping threaded portion and a portion of reduced transverse dimension that is free from contact with said valve body portion.




5,586,748
DISCONNECT VALVE ASSEMBLY FOR CONNECTING A SOURCE OF FLUID WITH A CONTAINER TO BE FILLED

Arthur S. Kish, Sarasota, Fla., assignor to JEM Industries, Inc., Willoughby, Ohio
 Filed Mar. 29, 1995, Ser. No. 413,097
 Int. Cl.⁶ F16L 37/28
 U.S. Cl. 251—149.8 14 Claims



5,586,749
COMPOSITE POLYETHYLENE AND TRANSITION VALVE

Richard W. Conley, Oakmont; Robert G. Visalli, Murrysville, and James R. Daniels, McDonald, all of Pa., assignors to Kerotest Manufacturing Corp., Pittsburgh, Pa.
 Filed Jun. 17, 1994, Ser. No. 261,719
 Int. Cl.⁶ F16K 5/06
 U.S. Cl. 251—315.05 11 Claims




1. A disconnect valve assembly for connecting a source of fluid with a container to be filled with fluid and comprising:
 a tubular body having a fluid passageway extending there-through from an inlet to an outlet so that fluid may enter said inlet and exit from said outlet;
 a depressor located in said passageway intermediate said inlet and said outlet;
 a ball-valve check assembly located within said passageway between said inlet and said depressor, said assembly including a stem body slidably mounted within said fluid passageway and having a stem passageway extending therethrough between a stem inlet and a stem outlet, said stem passageway having a first passageway portion and a second passageway portion with said second passageway portion being located downstream from said first passageway portion and being of smaller diameter than said first passageway portion, a radially extending valve seat interconnecting said first passageway portion and said second passageway portion, a ball member having a diameter greater than said second passageway portion but less than said first passageway portion located within said first passageway portion, and spring means located in said first passageway portion for normally resiliently biasing said ball member against said valve seat for preventing pas-

sage of fluid through said stem passageway from said first passageway portion to said second passageway portion;
 said depressor being carried by said stem body and mounted thereon for relative movement with respect thereto downstream from said second passageway portion, said depressor having an actuator means extending therefrom toward said ball-valve check assembly and extending into said second passageway portion for engaging said ball member upon relative movement of said depressor and said stem body toward each other for displacing said ball member against the resilient bias of said spring means to thereby open said ball valve assembly permitting fluid to flow from said inlet to said outlet;
 means for imparting slidable movement of said stem body in a first direction and in an opposing second direction; and
 means for limiting movement of said depressor in said first direction whereupon further movement of said stem body in said first direction causes relative movement of said depressor and said stem body toward each other for displacing said ball member toward said ball valve assembly.

1. A valve assembly comprising:
 a metal valve body having a pair of end fittings with at least one of said end fittings being fabricated of polyethylene to form a composite valve structure combining metal and polyethylene, said metal valve body including an annular portion, a pair of conduit portions, and a stem housing,
 means for connecting said conduit portions and said stem housing to said annular portion to form a unitary valve body free of fastening elements,
 said annular portion forming a valve chamber,
 said conduit portions including passageways positioned in spaced relation in said annular portion to provide a flow path between said conduit portions through said valve chamber,
 a valve closure member positioned in said valve chamber and sealingly connected to said conduit portions for rotation between an open position for directing flow between said conduit portions and a closed position sealing said conduit portions against flow,
 a valve stem extending from said closure member through said annular portion and rotatably positioned within said stem housing,
 an actuator connected to said valve stem above said stem housing for turning said valve stem to move said closure member between said open and closed positions,

means for connecting said end fittings to said conduit portions to form a unitary valve assembly having a metal valve body and at least one polyethylene end fitting for direct connection to polyethylene conduit,
 a second end fitting of said pair of end fittings fabricated of metal,
 said polyethylene end fitting extending into gripping engagement with one of said metal conduit portions, and
 said metal end fitting formed integral with the other of said metal conduit portions.


5,586,750
GUIDE TYPE CABLE ENGINE
 Takuji Ezoe, 2-7-14, Tsukushino, Machida-shi, Tokyo, Japan
 Filed Jan. 25, 1995, Ser. No. 378,373
 Claims priority, application Japan, Mar. 30, 1994, 5-082716
 Int. Cl.⁶ B63B 35/03
 U.S. Cl. 254—134.3 SC 4 Claims



1. A guide type cable engine comprising:
 a main pull rope;
 a cable to be paid out;
 an inner guide tightly enclosing said main pull rope, said inner guide made of a resilient sheet fastened in an elongated cylindrical shape; and
 an outer guide enclosing said inner guide, and said cable, said outer guide made of a resilient sheet fastened in an elongated shape,
 wherein said inner guide is located at a predetermined position in said outer guide.


5,586,751
MANUAL CHAIN BLOCK
 Yoshio Ueno; Yasuo Wada, and Munenobu Honda, all of Sayama, Japan, assignors to Elephant Chain Block Company, Ltd., Osaka, Japan
 Filed Sep. 8, 1994, Ser. No. 303,199
 Claims priority, application Japan, Sep. 14, 1993, 5-229281; Sep. 14, 1993, 5-229282
 Int. Cl.⁶ B66D 3/26
 U.S. Cl. 254—352 3 Claims

1. A manual chain block comprising:
 first and second side plates, spaced apart from each other;
 a load sheave rotatably supported between the first and second side plates;
 a drive shaft for driving the load sheave;
 a driven member coupled to the drive shaft and non-rotatable relative to the drive shaft;
 a hand wheel threadedly mounted on the drive shaft;
 a ratchet wheel rotatably interposed between the hand wheel and the driven member, the ratchet wheel comprising a boss and an outer peripheral portion having teeth;
 a brake pawl supported to the first side plate and engageable with the teeth of the ratchet wheel;
 lining plates interposed between the ratchet wheel and the hand wheel and between the ratchet wheel and the driven member, respectively;



a cover portion provided at one of the hand wheel and the ratchet wheel, the cover portion having a peripheral surface and extending toward the other of the hand wheel and the ratchet wheel to cover an outer peripheral portion of the lining plate interposed between the ratchet wheel and the hand wheel;
 an opposite peripheral surface provided at the other of the hand wheel and the ratchet wheel, the opposite peripheral surface being in opposition to and in close vicinity to the peripheral surface of the cover portion; and
 a sealing member interposed between the peripheral surface of the cover portion and the opposite peripheral surface opposed thereto.

5,586,752
LOAD CHAIN RETAINMENT FOR A CHAIN BLOCK
 Yasuo Wada, and Yoshio Ueno, both of Sayama, Japan, assignors to Elephant Chain Block Company Limited, Osaka, Japan
 Filed Jul. 5, 1994, Ser. No. 270,659
 Claims priority, application Japan, Jul. 2, 1993, 5-164894
 Int. Cl.⁶ B66D 1/30
 U.S. Cl. 254—372 6 Claims



1. A load chain fixing structure in a manual chain block comprising:
 a pair of side plates, spaced from each other;
 a load sheave, rotatively interposed between said pair of side plates, for supporting a load chain comprising horizontal links and vertical links;
 a manual driving means for driving said load sheave to wind said load chain up and down; and
 a pair of load chain guides, formed of block-like members and fixed between said side plates at two radial sides of said load sheave, for guiding said load chain when approaching said load sheave and for forcing the chain toward said load sheave, said load chain guides having a chain pushing surface facing said load sheave and a rear surface which opposes said chain pushing surface; wherein a retaining portion is formed on said

rear surface of one load chain guide, at a non-load side of said pair of load chain guides, so as to retain a horizontal link at an end of a non-load side portion of the load chain, said retaining portion comprising a recessed portion to receive said horizontal link and being provided at its lower part with a load receiving portion, comprising a stepped portion protruding from said chain guide having a corresponding shape to that of a lower end portion of said horizontal link, such that a load acting on said horizontal link at the end of the load chain on the non-load side is transferred to said chain guide by said stepped portion in contact with the lower end portion of said horizontal link received in said recessed portion, said retaining portion being also provided with fixing means for fixing said horizontal link which is received in said recessed portion, to said retaining portion.

5,586,753

FENCE VEGETATION BARRIER


William E. Michaels, 204 Harrison Blvd., Valparaiso, Ind. 46383

Filed Oct. 27, 1995, Ser. No. 549,266

Int. Cl.⁶ E04H 17/02

U.S. Cl. 256—32

20 Claims



1. A fence vegetation barrier for use with a fence having a pair of spaced-apart posts and a lower edge extending therebetween, the fence vegetation barrier comprising:

barrier means receivable beneath the lower edge of the fence, the barrier means having a length in a longitudinal direction, a width in a transverse direction to the longitudinal direction, two oppositely-disposed ends in the longitudinal direction, oppositely-disposed edges in the transverse direction and running along the length of the barrier means, and a center disposed along the longitudinal direction and equidistant from the edges;

first attachment means disposed near a first end of the two oppositely-disposed ends of the barrier means, the first attachment means comprising a first aperture in communication with the first end, the first aperture having a first aperture width in the transverse direction; and

second attachment means disposed near a second end of the two oppositely-disposed ends of the barrier means, the second attachment means comprising a second aperture in communication with the second end, the second aperture having a second aperture width in the transverse direction that is less than the first aperture width;

wherein the first and second apertures are each entirely disposed between the edges of the barrier means and substantially at the center of the barrier means at the first and second ends, respectively.

5,586,754

GRID BLOCK WORKPIECE CLAMPING APPARATUS


Willis R. Williams, 767 S. Fielder, Arlington, Tex. 76013

Filed Aug. 11, 1995, Ser. No. 514,358

Int. Cl.⁶ B23Q 3/02

U.S. Cl. 269—99

5 Claims



1. A workpiece clamping apparatus for securing a workpiece relative to a planar support surface provided with a plurality of spaced apertures and a plurality of elongated channels, wherein the workpiece clamping apparatus comprises:

a pair of generally rectangular contoured block members each provided with a plurality of vertically and horizontally aligned slots and apertures; wherein each block member has a contoured base dimensioned to be slidably received in the plurality of elongated channels in the planar support surface; means for selectively engaging the contoured base of each block member with the spaced apertures and the elongated channels of said planar support surface; and,

a plurality of threaded securing elements operatively associated with said plurality of vertically and horizontally aligned slots.

5,586,755

MISFEED DETECTOR FOR A STACK OF DIFFERENT WEIGHT SHEETS


Paul Hansen, Westminster, Calif., assignor to Xerox Corporation, Stamford, Conn.

Filed Feb. 13, 1995, Ser. No. 387,678

Int. Cl.⁶ B65H 7/00

U.S. Cl. 271—9.06

20 Claims



1. In a sheet transport system comprising:

a. a support tray for supporting a stack of sheets,

b. an inlet operably connected to said support tray through which each sheet passes prior to entering into the stack of sheets on said tray,

- c. an outlet operably connected to said support tray through which each sheet passes upon being discharged from the stack of sheets on said tray,
- d. an inlet sensor at said inlet for sensing the thickness of a sheet passing through said inlet,
- e. an outlet sensor at said outlet for sensing the thickness of a sheet passing through said outlet, and
- f. means for comparing the thickness value sensed at the inlet sensor with the thickness value sensed at the outlet sensor of the same sheet and generating a signal indicating a misfeed if the values differ by a predetermined amount.

5,586,756

DUAL MODE PNEUMATIC SIGNATURE FEEDING SPRING AND DISABLING APPARATUS


Bobby Chang, 3100 W. Sierra Dr., Westlake Village, Calif. 91362

Filed Nov. 2, 1994, Ser. No. 333,286

Int. Cl.⁶ B65H 5/08

U.S. Cl. 271—11

12 Claims



1. In a cyclically operable signature feeding apparatus including a driven rotary drum having a plurality of signature grippers disposed about the periphery thereof, said signature grippers being adapted to grip signatures seriatim from a signature supply means, suction means driven by cam means for shifting signatures seriatim from said signature supply means to said rotary drum for gripping by said signature grippers, said suction means including oscillating suction grippers in communication with a source of vacuum, the improvement comprising:

a cam follower assembly operatively associated with said suction means to control movement of said oscillating suction grippers toward and away from said signature supply means; and

pneumatic means having dual modes of operation including a cam follower spring mode of operation for selectively biasing said cam follower assembly toward said cam means to maintain engagement therewith and a cam follower disabling mode of operation for selectively supporting said cam follower assembly in a position out of the full path of movement of said cam means to thereby disable said oscillating suction grippers;

said pneumatic means including a source of pressurized air in communication with a pneumatic cylinder having both a spring chamber and a disabling chamber, valve means intermediate said source of pressurized air and both said spring chamber and said disabling chamber, and control means associated with said valve means for selectively pressurizing one of said chambers and purging the other of said chambers.

5,586,757

PAPER REGULATING MECHANISM AND PAPER CASSETTE

Yasuhiro Nakamatsu; Masao Otsuka; Fumio Hatanaka, and Arihiro Tsunoda, all of Osaka, Japan, assignors to Mita Industrial Co., Ltd., Osaka, Japan


Filed Jan. 12, 1995, Ser. No. 372,048

Claims priority, application Japan, Jan. 14, 1994, 6-002813; Jan. 14, 1994, 6-002814

Int. Cl.⁶ B65H 1/04

U.S. Cl. 271—145

5 Claims



1. A paper cassette comprising: a paper cassette body for accommodating stacked paper sheets; a paper stopper for abutting against the end portions of the paper sheets stacked in said paper cassette body; and a support shaft horizontally extending in a through groove formed in the bottom portion of said paper cassette body, wherein said paper stopper includes a paper abutment portion erected upright, and a sliding sleeve fitted on said support shaft at the lower end of said paper abutment portion, wherein said sliding sleeve has clamping members separated by axial slits from a cylindrical fitting portion thereof, wherein a control lever has said cylindrical fitting portion fitted rotatably on the outer circumferences of said clamping members, and wherein said cylindrical fitting portion is formed with push projections raised radially inward from the inner face of said cylindrical fitting portion.

5,586,758

SHEET DISCHARGE APPARATUS AND IMAGE FORMING APPARATUS HAVING SUCH SHEET DISCHARGE APPARATUS

Shoji Kimura, Kawasaki, and Nobukazu Adachi, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Mar. 1, 1995, Ser. No. 396,643

Claims priority, application Japan, Mar. 3, 1994, 6-060356

Int. Cl.⁶ B65H 39/10


U.S. Cl. 271—303

22 Claims



1. A sheet discharge apparatus comprising: a first sheet discharge path for discharging a sheet; a second sheet discharge path for discharging the sheet;

a sheet stacking tray on which the sheets discharged through said second sheet discharge path are stacked and which is pivotally mounted on a body of the apparatus;
a guide rockably supported by said sheet stacking tray so as to protrude from or to drop below said sheet stacking tray, and forming a part of said first sheet discharge path; and
a holding means for holding said guide in a position where said guide forms a part of said first sheet discharge path in a condition that said sheet stacking tray is closed with respect to a body of the apparatus, and for releasing said guide to drop to a position below a stacking surface of said sheet stacking tray so as not to prevent a sheet from being directed to said sheet stacking tray.



(b) a waist belt having first and second belt ends adjustably connectable to one another for securement around a waist of a user;

(c) a cord formed of a non-elastic material, the cord having a first portion attached to the mesh soccer net in a drawstring type fashion by gathering the mesh soccer net, the cord having a second portion operatively connected to the waist belt leaving the mesh soccer net carrying the soccer ball suspended from the waist belt; and

(d) cord adjustment means connected to the cord for manually adjusting the length of the cord between the mesh soccer net and waist belt.

5,586,759

BASKETBALL GOAL UNIT


James N. Fitzsimmons, Waukesha, and Randy R. Schickert, Kewaskum, both of Wis., assignors to Huff Corporation, Miamisburg, Ohio

Filed Jul. 28, 1994, Ser. No. 282,521

Int. Cl.⁶ A63B 63/08

U.S. Cl. 273—1.5 R

63 Claims



1. A method of assembling a basketball goal unit to a backboard, comprising the following steps:

- inserting a first bolt through a hole in a first mounting plate and retaining said first bolt with an elongated coupling nut;
- attaching said first mounting plate to said backboard;
- pivotally connecting a second mounting plate to said first mounting plate, said second mounting plate supporting a rim therefrom; and
- inserting a second bolt through a hole in said second mounting plate and retaining said second bolt in said elongated coupling nut.

5,586,760

SOCCER TRAINING BELT FOR USE WITH A CORD SUSPENDED SOCCER BALL

Bradley D. Hauter, 433 Harvest Gate, Lake In The Hills, Ill. 60102

Continuation-in-part of Ser. No. 273,761, Jul. 22, 1994, Pat. No. 5,443,576. This application Aug. 2, 1995, Ser. No. 510,357 Int. Cl.⁶ A63B 67/10

U.S. Cl. 273—58 C

12 Claims

1. A soccer training apparatus, comprising:

- a mesh soccer net sized and configured for encapsulating a soccer ball and loosely holding the soccer ball within the mesh soccer net enabling the encapsulated soccer ball to freely rotate within;

5,586,761


GOLF SWING TRAINING DEVICE

James H. Brock, 2055 Federal Rd., Roswell, Ga. 30075, and Robert P. Foster, 1170 Harrowgrove Ct., Marietta, Ga. 30064 Filed Aug. 26, 1994, Ser. No. 296,969

Int. Cl.⁶ A63B 69/36

U.S. Cl. 473—207

6 Claims



1. A golf swing training device, comprising:
an indicator;

means for securing said indicator to a golfer so as to reflect the shoulder rotation of said golfer while making a golf swing, said indicator adapted to extend from said golfer in a direction substantially parallel to an axis passing through said golfer's shoulders and substantially perpendicular to an axis passing through said golfer's spine; and

an adjustable guide adapted to be positioned adjacent said golfer for engagement with said indicator, said guide defining a path that reflects a proper shoulder turn to be made by said golfer such that, when said golfer makes a golf swing, said indicator traverses said guide.

5,586,762
METHOD OF PLAYING A QUADRILATERAL CHESS GAME


Jon P. Wearley, Box 248, Augusta, Mont. 59410

Division of Ser. No. 178,380, Dec. 22, 1993, abandoned. This application Nov. 17, 1994, Ser. No. 345,804

Int. Cl.⁶ A63F 3/02

U.S. Cl. 273—261

5 Claims



1. A method of playing a chess-like board game providing for simultaneous play by from two to four players or plural teams formed thereof, the method comprising the following steps:

providing first, second, third and fourth groups of chess pieces, with each of said groups of chess pieces including means distinguishing said chess pieces of said each of said groups from said chess pieces of other said groups;

further providing a game board having a central matrix of sixty-four playing positions comprising eight ranks and eight files in a substantially square array, and four sides with each of said sides including an extension having two ranks and eight files of sixteen playing positions extending therefrom, thereby providing a total of twelve ranks across said board in each of four directions starting from each said extension, said central matrix including four corners each having means excluding play thereacross extending between each adjacent said extensions of playing positions, said game board further including means thereon designating and distinguishing from all other ranks of playing positions at an eight rank across said game board in each direction starting from each said extension;

alternately moving one of said chess pieces from each of said groups in turn according to the rules of chess;
attempting to advance pawns of each of said groups to reach said rank designation mean at said eighth rank, thereby promoting said pawns to chess pieces of higher value in accordance with the standard rules of chess;
attempting to reach a checkmate position against each of the kings of each of said group of chess pieces; and
continuing in the above manner until a king of only one of said groups of chess piece remains free of checkmate, thereby establishing a winner of said game.

5,586,763

SIAMESE CASE FOR STORING AND PLAYING TWO GAMES

Edward De Bono, L2 Albany Piccadilly, London, W1V 9RR, England, and Maurice S. Kanbar, 2140 Pacific Ave. Apt. #5, San Francisco, Calif. 94115


Filed Sep. 18, 1995, Ser. No. 529,720

Int. Cl.⁶ A63F 3/00

U.S. Cl. 273—285

7 Claims

1. A Siamese case and two games stored in the case, each game having a play board and playing pieces movable on the board, said case comprising:



A. a central section formed by a pair of open boxes in back-to-back relation, each box being adapted to nest the board of a respective game and to accommodate its play pieces; and

B. a complementary pair of wing sections, each formed by a cover hinged to a respective side of the central section whereby when the cover is folded over its related box, the closed box is then in a storage mode, and when the cover is folded out to expose the open box and its contents, the box is then in a playing mode.

5,586,764

CARD GAME SET HAVING BLOCK SHAPED TILES

Daniel B. Katz, 9979 Nob Hill La., Sunrise, Fla. 33351

Filed Mar. 27, 1995, Ser. No. 409,848

Int. Cl.⁶ A63F 1/10; 1/00

U.S. Cl. 273—293

7 Claims



1. A novel game set, said set comprising:

- a plurality of rigid game pieces for playing a combination of games, each of said plurality of rigid game pieces each comprising a plurality of individually laminated wood layers permanently pressed together to form a high grade plywood piece, having a predetermined thickness sufficient for convenient handling by young, unskilled and arthritic persons, each said plywood piece being of sufficient weight to resist the force of wind and sudden drafts for facilitating the playing of games outdoors, each of said plurality of game pieces bearing an individual traditional playing card indicia to facilitate the playing of traditional western and novel card games;
- a waterproof enamel coating completely insulating each of said plurality of rigid game pieces to protect said game pieces from moisture and marring and to protect said game pieces from the defacing of the playing card indicia;
- a gripping means, defined by said waterproof coating, for producing a semi-rough surface for easy handling of each of said plurality of game pieces; and
- each of said plurality of rigid game pieces being rectangular in shape and having flat side edges and ends for balancing said game pieces vertically and planar continuous surfaces for constructing traditional playing card houses and block structures and for enabling uninhibited slidable removal of said game pieces from said structure.

5,586,765


METHOD OF PLAYING A WORD SCRAMBLE GAME
 Glenn D. Lackey, 9014 Carlotta Ct., Houston, Tex. 77074
 Filed Nov. 18, 1994, Ser. No. 342,148
 Int. Cl.⁶ A63F 1/00

U.S. Cl. 273—299

4 Claims

1	TAFFETA	-	AAFEFTT
2	HARMFUL	-	HULMRAF
3	NECKTIE	-	EECNITK
4	LANTERN	-	NENTRAL
5	WORLDLY	-	RWYLDLO
6	FASCIST	-	ACSSIFT

1. A method of playing a word scramble game for two or more players comprising the steps of:
- a) providing a plurality of cards forming a card set wherein each card has printed thereon a plurality of correctly spelled words opposite a scramble version of each such word;
 - b) providing each player with paper and a writing instrument;
 - c) providing a timing means;
 - d) a die;
 - e) starting a round by each player drawing a card from the card set and positioning the card such that the words on the card are not in clear view of the other players;
 - f) providing a means for determining which player should be selected to choose and verbally present the scrambled letters to the other player or players;
 - g) providing a means for presenting the scrambled letters to the other player or players;
 - h) activating the timing means;
 - i) each player as quickly as possible, writing on their own paper attempts to unscramble the given letters and form the correct word within the time period;
 - j) a means for player recognition when the player has formed a word from the given scrambled letters;
 - k) providing point values to the player who provides the correct word from the scramble letters within the time period;
 - l) providing point values to the player who first provides a word formed from the given scrambled letters and such word is not the same word provided from the given card selection;
 - m) providing point values to the player who presented the scramble letters to the other player or players and which no player provided a correct unscramble version of the word;
 - n) repeating steps g through l until a player wins by reaching a predetermined number of total points.



by rules of a particular blackjack game and are countable for purposes of awarding one or more player jackpot bonuses;

a plurality of player keys mounted upon the central module for selectively incrementing the player counters to change player count values for players who have experienced a player jackpot tally event;

means for zeroing the player count values of players who have not experienced a player jackpot tally event;

an electronic dealer counter for registering a dealer count value indicating the number of dealer jackpot tally events experienced by the dealer; said dealer jackpot tally events being an event defined by rules of a particular blackjack game and are countable for purposes of awarding one or more bonuses;

means for selectively incrementing the dealer counter to change the dealer count value if the dealer has experienced a dealer jackpot tally event;

means for zeroing the dealer counter to a zero dealer count value if the dealer has not experienced a dealer jackpot tally event;

a plurality of player status displays which are connected to receive information from the plurality of electronic player counters to display the player count values;

at least one dealer status display which is connected to receive information from the electronic dealer counter to display the dealer count value;

wherein the game system includes a table-top unit having an array of display lights along side edges thereof.

5,586,767

LAWN GAME APPARATUS FOR USE WITH A WATER HOSE


William Bohland, 101 N. 72nd Ave., Pensacola, Fla. 32506
 Filed Mar. 21, 1996, Ser. No. 619,006
 Int. Cl.⁶ A63B 67/00

U.S. Cl. 273—349

13 Claims

1. Game apparatus for use in combination with a water hose and intended to be played by at least two teams, said game apparatus comprising:

- a) a framework having a base portion and a water emitting portion extending vertically upward from said base portion, said base portion adapted to operatively receive said hose, said base and water emitting portions being in fluid communication with one another;
- b) valve means disposed at an intermediate position within said water emitting portion;
- c) an elongated valve actuating member pivotally attached to said water emitting portion, and including a proximal end operatively attached to said valve means and a distal end spaced from said water emitting portion; and



d) projectile receiving means operatively attached to said distal end of said valve actuating member.


5,586,768

COLLAPSIBLE/PORTABLE SOCCER GOAL

Onofrio F. Pavonetti, 78 Dunwoodie St., Scarsdale, N.Y. 10583
 Filed Dec. 12, 1994, Ser. No. 354,477
 Int. Cl.⁶ A63B 63/00

U.S. Cl. 273—411

31 Claims



1. A collapsible soccer goal for an athletic field comprising: a matched pair of vertical side supporting frame sections, and a crossbar beam having a plurality of horizontal sections; each of said vertical and horizontal sections comprising a locking hinge enabling each said section to be folded in half; said plurality of horizontal sections being detachably connected together by clamping means to form said crossbar beam; and said vertical frame sections each having an overhead elongated hinge removably connectable to a horizontal section for supporting said crossbar beam in a hanging manner from said vertical side supporting frame sections.

5,586,769

HEAD GASKET WITH PRE-EMBEDDED METAL SHIM AND METHOD OF USING SAME
 Martin Novil, Bristol, Wis., and Michael O'Brien, Addison, Ill., assignors to Fel-Pro Incorporated, Skokie, Ill.


Filed May 1, 1995, Ser. No. 432,947

Int. Cl.⁶ F16J 15/08

U.S. Cl. 277—1

5 Claims

5. A method of reducing the susceptibility of a head gasket to the effects of excessively high local stress comprising the steps of providing a head gasket comprising a laminate, said gasket defining a plurality of adjacent combustion openings, oil and



water holes and bolt holes, said laminate comprising a metallic core having a pair of main surfaces and fiber-elastomer facing layers on each main surface of said core, disposing a thin metallic shim on at least one of the facing layers, said shim having elongated arcuate elements lying adjacent to each of a pair of adjacent combustion openings, said shim having a thickness less than that of the facing layer and precompressing the thin metallic shim into the facing layer, then disposing U-shaped armors in each combustion opening with legs thereof overlapping the edges of the facing layers as well as portions of said arcuate elements adjacent to the edges of the combustion openings, both of said arcuate elements extending beyond the zone of adjacency of adjacent combustion openings, and extending radially outwardly beyond said armor legs, and prior to installation of the gasket in a service environment, compressing said facing layer under said armor and shim, whereby the facing layer is reduced in thickness under said armor at the locations of said shim, is reduced in thickness by approximately the thickness of the shim where the arcuate elements extend radially outwardly beyond the legs, and is substantially unreduced in thickness radially beyond that.

5,586,770

METAL LAMINATE GASKET WITH ENGAGING DEVICE


Tsunekazu Udagawa, Ichikawa, and Kenji Yamada, Tokyo, both of Japan, assignors to Ishikawa Gasket Co., Ltd., Tokyo, Japan

Filed Jul. 5, 1994, Ser. No. 270,652

Int. Cl.⁶ F16J 15/08

U.S. Cl. 277—11

7 Claims



1. A metal laminate gasket adapted to be engaged with an engaging projection of an engine part for immovably locating the gasket on the engine part, comprising, a first plate including at least one first hole having a size generally corresponding to the engaging projection of the engine part, a plurality of first engaging portions with pointing ends having a size smaller than that of the engaging projec-

tion, and a plurality of first non-engaging portions, each first non-engaging portion being situated between two adjacent first engaging portions, the width of each first engaging portion sandwiched between two adjacent first non-engaging portions decreasing in a direction toward the pointing end, said first engaging portions and first non-engaging portions defining the first hole, and

a second plate situated above and engaging the first plate, said second plate including at least one second hole having a size generally corresponding to the first hole and located above the first hole, a plurality of second engaging portions with pointing ends having a size smaller than that of the engaging projection and a plurality of second non-engaging portions, each second non-engaging portion being situated between two adjacent second engaging portions, the width of each second non-engaging portions decreasing in a direction toward the pointing end thereof, said second engaging portions and second non-engaging portions defining the second hole, said second engaging portions being located above the first non-engaging portions and said second non-engaging portions being located above the first engaging portions so that when the first and second plates are urged against the engine part, the first and second engaging portions deform to allow the engaging projection to enter into the first and second holes and engage the engaging projection to thereby prevent the gasket from easily disengaging from the engaging projection.

5,586,771

SLIDING SEAL WITH HOLE AND GROOVE FOR DISTRIBUTION OF PRESSURIZED FRICTION REDUCING MEDIUM

Pertti Koskinen, Paasikiventie 8 B 9, FIN-33230 Tampere, Finland

PCT No. PCT/FI94/00397, § 371 Date May 4, 1995, § 102(e) Date May 4, 1995, PCT Pub. No. WO95/07423, PCT Pub. Date Mar. 16, 1995


PCT Filed Sep. 12, 1994, Ser. No. 433,349

Claims priority, application Finland, Sep. 10, 1993, U930453

Int. Cl. F16J 15/46

U.S. Cl. 277—34

8 Claims



1. An arrangement for sealing an element which is relatively moveable with respect to an elongate slit, and for reducing friction at a sliding interface between said element and a seal for said slit, said seal comprising at least one pressurized tubular sealing member and said element including a tapering part tapering down towards the ends thereof, one side of said tapering part including a hole for feeding a pressurized medium to the sliding interface between the seal and said part, and at least a portion of said part of said element including an elongate groove in communication with said hole and along which said pressurized medium supplied through said hole is fed.

5,586,772 RETROFIT GASKET ASSEMBLY FOR RAILROAD HOPPER HAVING REINFORCING PORTIONS


Ralph Deaver, Waverly, Tenn., assignor to Central Sales & Service, Inc., Waverly, Tenn.

Filed Oct. 20, 1995, Ser. No. 546,278

Int. Cl. F16J 15/10

U.S. Cl. 277—166

7 Claims



1. A gasket assembly for sealing the flanged opening in the bottom of a railroad car, the assembly comprising:
an elongate flexible seal, the seal having a top sealing portion, the seal further including a bottom channel;
a plurality of elongate rigid support members, the support members attach to the flexible seal at the channel; and
the top sealing portion presenting a bulbous shape over a portion of its length corresponding to one of the support members, and the top sealing portion presenting a planar shape over a portion of its length corresponding to another of the support members.

5,586,773

GAS-PATH LEAKAGE SEAL FOR A GAS TURBINE MADE FROM METALLIC MESH


Bharat S. Bagepalli, Schenectady, and Osman S. Dinc, Troy, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Jun. 19, 1995, Ser. No. 491,758

Int. Cl. F16J 15/12

U.S. Cl. 277—167.5

10 Claims



1. A gas-path leakage seal for generally sealing a gas-path leakage-gap between spaced-apart first and second members of a gas turbine, said seal comprising a cloth-layer assemblage disposed in said gas-path leakage-gap and including a metallic, woven cloth

layer having a first group of generally equal-diameter wires which are warp wires and a second group of generally equal-diameter wires which are weft wires, wherein adjacent wires of one of said first and second groups of wires are spaced apart by a center-to-center distance equal to generally between four and ten times the diameter of the wires of the other of said first and second groups of wires.

5,586,774

SPRING SUPPORTED IN-LINE SKATE


Patsy Dentale, 2314 E. Third St., Brooklyn, N.Y. 11223

Filed Sep. 15, 1995, Ser. No. 528,930

Int. Cl. A63C 17/06

U.S. Cl. 280—11.22

7 Claims



1. A spring supported in-line skate comprising:

a foot engaging means comprising a boot adapted to receive and engage a human foot therewithin and an inverted, U-shaped outer receiver secured directly to a lower portion of the boot
a rolling support means secured to said outer receiver and movable relative to the foot engaging means for rollingly engaging a ground surface therebeneath, said rolling support means comprising an inner wheel rack of elongated configuration; a plurality of wheels rotatably supported in an in-line configuration within the inner wheel rack; the inner wheel rack being pivotally mounted to a forward end of the outer receiver by a pivot pin directed therethrough wherein the pivot pin comprises an axle rotatably supporting a forward-most one of the wheels;

and,

a spring means interposed between the foot engaging means and the rolling support means for resiliently supporting the foot engaging means relative to the rolling support means.

5,586,775

FOLDABLE APPARATUS OF A BAGGAGE CART

Chin-chang Cheng, No. 20, Lane 327, Sec. 2, Chung Shan Rd., Chung Ho City, Taipei Hsien, Taiwan


Filed Jul. 14, 1995, Ser. No. 502,577

Int. Cl. B62B 1/12

U.S. Cl. 280—38

4 Claims

1. A foldable apparatus of a baggage cart comprising
a base plate (10),
two elongate sockets (20) formed on the base plate (10) substantially along two sides thereof;
a first cutout (21), a second cutout (22), and a third cutout (23) being defined in the elongate socket (20) and substantially in alignment with each other;



a first flange (211) being projected from a wall of the first cutout (21);
a channel (25) is defined in the socket (20) and in communication with the first cutout (21), the second cutout (22) and the third cutout (23);
a pivot (31) being pivotally received in the channel (25) and having a first end and a second end of said pivot extended outward from the channel (25), the first end of the pivot (31) being integrally formed as a substantially U-shaped bracket (34) which has an upright branch (34A) integrally formed with a curved portion (34B) connected to an inclined branch (34C) which abuts against a wall (22W) of the second cutout (22) by a resilience of said inclined branch, while a second end of the pivot (31) is formed as an upright rod (32) which has a wheel (33) rotatably connected to said upright rod; a recess (24) being defined in a low portion of the wall (22W) of the second cutout (22), and being sized to be capable of receiving an end portion of the inclined branch (34C) of the U-shaped bracket (34);
whereby the foldable apparatus is operable to be in an extended mode in which the upright branch (34A) and the upright rod (32) are substantially perpendicular to the base plate (10) and are respectively retained in the first cutout (21) and the third cutout (23) by the resilience of the inclined branch (34C) and the first flange (211), or to a retracted mode in which the upright branch (34A) and the upright rod (32) are substantially in contact with the base plate (10) and an end portion of the inclined branch (34C) is received in the recess (24).

5,586,776

LAMINATED METAL GASKET HAVING A VARYING BEAD STRUCTURE, THICKNESS, AND OVERLAP WIDTH

Kenji Kubouchi, Hirakata-shi; Yuji Fukui, and Kunitoshi Inoue, both of Higashi-Osakashi, all of Japan, assignors to Nippon Gasket Co., Ltd., Osaka, Japan

Filed Jul. 31, 1995, Ser. No. 509,457


Claims priority, application Japan, Aug. 19, 1994, 6-195269

Int. Cl. F16J 15/08

U.S. Cl. 277—235 B

4 Claims

1. A metal gasket for a cylinder head comprising:
an elastic metal base plate having a plurality of beads, each of said beads being formed around a respective one of a plurality of juxtaposed holes for combustion chambers;
an elastic metal adjusting plate having a plurality of beads, each of said beads being formed around a respective one of a plurality of juxtaposed holes for combustion chambers; and
a grommet having a plurality of juxtaposed holes for combustion chambers which are smaller in diameter than said holes in said base plates and in said adjusting plates, said grommet being folded about the edges of said holes in said adjusting plate, said adjusting plate lying between said base plate and said grommet in intimate contact therewith to form a plurality



of bores formed by aligning said holes in said base plate, in said adjusting plate and in said grommet; said bead on said base plate being formed as a full bead between every adjoining two of said holes in said base plate and as a half bead around the remaining edges of each of said holes in said base plate, while said bead on said adjusting plate is a full bead around the entire edge of each of said holes in said adjusting plate, so that each said bead on said base plate extends over each said bead on said adjusting plate between every adjoining two of said bores.

5,586,777

IN LINE SKATE WITH DYNAMICALLY ADJUSTABLE WHEELS


David Wolf, 67 Brackett Rd., Newton, Mass. 02158

Filed Jun. 5, 1995, Ser. No. 462,829

Int. Cl. A63C 17/04

U.S. Cl. 280-11.22

9 Claims



1. A first in-line skate having a plurality of aligned wheels and axles therefor, means for selectively shifting and securing the axle of at least one of the plurality of wheels to and from a secured position below the others of said axles of said plurality of wheels, said shifting means including means engageable by a second in-line skate for effecting the shift dynamically as said first skate is in use and moving.

5,586,778

COLLAPSIBLE GOLF CART

Leif Lindh, Danderyd, and Kjell Lindh, Lidings, both of Sweden, assignors to Eurogreen International Inc., Chang-Hua Hsien, Taiwan


Filed Aug. 11, 1995, Ser. No. 514,136

Int. Cl. B62B 1/12

U.S. Cl. 280-40

7 Claims

1. A collapsible golf cart comprising:



elongated upper and lower frame parts, said lower frame part being slidably received within said upper frame part in a longitudinal direction thereof, said upper frame part having an upper end which has a handle connected thereto, and a lower end into which said lower frame part is inserted, said lower frame part having a lower end;

means for supporting a golf bag on said upper and lower frame parts; two legs, each of which has an upper end that is connected pivotally to said lower end of said upper frame part so that said legs can be brought into a collapsed position, wherein said legs are pivoted inwardly and substantially parallel with each other and with said upper and lower frame parts, when said lower frame part is slidably received within said upper frame part and an outwardly extended opened position, wherein said legs and said upper and lower frame parts are moved away from one another when said lower frame part is extended outwardly of said upper frame part, each of said legs further having a lower end which has a wheel suspension means for supporting a removable wheel, and link arms pivotally connected between said lower ends of said legs and said lower end of said lower frame part; and holding means for maintaining distance between said wheels constant and for maintaining a distance between said wheels and said lower end of said lower frame part constant when said legs are in said opened position.

5,586,779

ADJUSTABLE SNOWBOARD BOOT BINDING APPARATUS


Paul J. Dawes, 12422 Skyline Blvd., Woodside, Calif. 94062; Thomas A. Krulvitch, 2833 Kensington Rd., Redwood City, Calif. 94061, and Peter A. Krulvitch, 4319 Railroad Ave. #19, Pleasanton, Calif. 94566

Filed Jun. 6, 1995, Ser. No. 466,989

Int. Cl. A63C 5/00; 9/00

U.S. Cl. 280-14.2

4 Claims



1. A snowboard boot binding device comprising: a binding mount plate for fixedly mounting a snowboard binding thereto, said binding mount plate having a cavity centrally defined therein;

a ring fixedly attached to said binding mount plate, said ring having a bore centrally defined therethrough; a hub for mounting said boot binding device to a snowboard, said hub being centrally disposed in said cavity and extending through said bore, wherein said binding mount plate and said ring rotate about said hub, thereby allowing for adjustment of an angular position of said binding mount plate, said ring dimensioned to hold said binding mount plate to said hub; and said binding mount plate to be adjusted.

5,586,780

HIGH EFFICIENCY BICYCLE SUSPENSION

Gary G. Klein; Darrell W. Voss, both of Chehalis, Wash., and Lonney Pauls, Estacada, Oreg., assignors to Klein Bicycle Corporation, Chehalis, Wash.


Division of Ser. No. 268,883, Jun. 30, 1994, Pat. No.

5,405,159, which is a continuation of Ser. No. 946,060, Sep. 18, 1992, abandoned. This application Sep. 28, 1994, Ser. No. 313,928

Int. Cl. B62K 25/04

U.S. Cl. 280-275

8 Claims



1. A bicycle having a frame and handlebar-steering and seat assemblies attached to said frame, front and rear ground engaging wheel assemblies attached to said frame, a suspension unit comprising a linkage of pivots and lever arms including as a part of said linkage at least one spring element and at least one rotary shock absorber having a fluid filled cavity and a rotary blade element in said fluid-filled cavity for causing fluid in said fluid-filled cavity to be displaced from one side of said rotary blade element to the other side of said rotary blade element in a substantially friction-free manner, means mounting said suspension unit between said frame and at least one of said handlebar-steering, seat, front and rear ground engaging wheel assemblies and wherein said rotary shock absorber has dynamic resistance, walls and a fluid metering gap between said walls and said rotary blade element, the fluid metering gap between the walls of said fluid-filled cavity and the rotating blade of said rotary shock absorber changes cross-sectional area at different angles of rotation of said vane, in order to change said dynamic resistance of said rotary shock absorber.

5,586,781

VARIABLE RIDE HEIGHT VEHICLE SUSPENSION SYSTEM

Colin J. Anderson, Reservoir Cottage, Gargate Hill Aldershot, Hants GU11 3AA, Great Britain

PCT No. PCT/GB93/02216, § 371 Date May 5, 1995, § 102(e) Date May 5, 1995, PCT Pub. No. WO94/11211, PCT Pub. Date May 26, 1994

PCT Filed Oct. 27, 1993, Ser. No. 432,150


Claims priority, application United Kingdom, Nov. 7, 1992, 9223414

Int. Cl. B60G 11/26

U.S. Cl. 280-708

4 Claims

1. A hydropneumatic system comprising:



(I) a telescopic strut including (A) a first chamber including first and second mutually telescopically movable wall parts, said first chamber containing hydraulic fluid; (B) a second chamber containing pneumatic fluid; and (C) a free piston means dividing said first chamber from said second chamber; (II) an auxiliary chamber containing pneumatic fluid; and (III) selectively operable valve means connecting said auxiliary chamber and said second chamber, said valve means comprising first valve means for allowing unidirectional flow of pneumatic fluid from said auxiliary chamber to said second chamber and second valve means for allowing unidirectional flow of pneumatic fluid from said second chamber to said auxiliary chamber.

5,586,782

DUAL PRESSURE SIDE IMPACT AIR BAG


Ronald A. Zimmerman, II, Rochester; John C. Hofer, Novi; Douglas E. Medvedik, Lake Orion; Eric D. Veggian, Troy, and Michael J. Lachat, Macomb Township, all of Mich., assignors to AlliedSignal Inc., Morristown, N.J.

Filed Jun. 26, 1995, Ser. No. 494,657

Int. Cl. B60R 21/22

U.S. Cl. 280-730.2

12 Claims



1. A side impact air bag for protecting the side and head of an occupant during a crash or vehicular impact comprising: a first side joined to a second side, separating means, a portion of which is located proximate a neck portion of the air bag, consisting of a sew pattern (46) joining the first and second sides and dividing the bag into upper and lower chambers and for diverting a predetermined quantity of inflation gas, received from an inflation gas source directly into the upper and lower chambers.

5,586,783

HYBRID GAS GENERATOR FOR FILLING A GAS BAG


Paul Adam, Munich; Heinz Tillmann, deceased, late of Riemerling; Michael Werner, Höhenkirchen-Siegertsbrunn; Peter Renn, Taufkirchen; Joachim Reif, Sauerlach, and Uwe Dölling, Heldenstein, all of Germany, assignors to TEMIC Bayern-Chemie Airbag GmbH, Aschau/Inn, Germany
Filed Feb. 23, 1995, Ser. No. 393,361

Claims priority, application Germany, Feb. 24, 1994, 44 05 997.3

Int. Cl.⁶ B60R 21/26

U.S. Cl. 280—737

16 Claims



1. A hybrid gas generator, comprising:
 - a. a pyrotechnic gas generator which is comprised of:
 - a. an enveloping housing which is provided with a plurality of outlet openings;
 - an igniter which is positioned within the enveloping housing;
 - a mixing chamber which is provided within the enveloping housing and which is in communication with the plurality of outlet openings; and
 - a combustion chamber which is provided within the enveloping housing in communication with the igniter, which has defined therein a blow-out opening in communication with the mixing chamber, and which contains a propellant composition comprised of a propellant which is oxidizable and an amount in excess of a stoichiometric amount of at least one oxidant for oxidizing the propellant in use to generate a propellant gas which is chemically reactive by igniting the propellant composition with the igniter; and
 - b. a high-pressure vessel which is comprised of:
 - a. a housing which contains gas under pressure;
 - an outflow opening which is defined in the high-pressure vessel and at which the high-pressure vessel is joined to the pyrotechnic gas generator; and
 - a sealing disk which is sealingly joined to the housing and positioned between the outflow opening of the high-pressure vessel and the mixing chamber of the pyrotechnic gas generator opposite the blow-out opening of the combustion chamber so that the propellant gas produced in the combustion chamber in use impinges against the sealing disk, and which is comprised of a substance which chemically reacts with the propellant gas so that the propellant gas attacks the sealing disk chemically and thermally, and continuously burns through the sealing disk as in a welding process in use whereby the sealing disk opens with a substantially reduced acoustic pressure and without a bang, the gas from the high-pressure vessel flows into the mixing chamber, mixes with the propellant gas to provide a gas mixture, and the gas mixture flows through the plurality of outlet openings provided in the enveloping housing of the pyrotechnic gas generator into a gas bag.

5,586,784


ROLLOVER PROTECTIVE STRUCTURE AND METHOD

Donald R. Mast, Argenta; Robert L. McNabb, Monticello, and Joseph A. Rapp, Morris, all of Ill., assignors to Caterpillar Inc., Peoria, Ill.
Continuation of Ser. No. 439,048, May 11, 1995, Pat. No. 5,529,342. This application Mar. 11, 1996, Ser. No. 613,300

Int. Cl.⁶ B60R 21/13

U.S. Cl. 280—756

10 Claims



1. A rollover protective structure for use with construction machinery, comprising:
 - a base member;
 - a first post attached to and extending upwardly from said base member, said first post including a first angled post member defining a first interior corner between adjacent first sides thereof;
 - a second post attached to and extending upwardly from said base member, said second post including a second angled post member defining a second interior corner between adjacent second sides thereof;
 - a cross member extending between said first angled post member and said second angled post member above said base member;
 - a first reinforcing member attached between said first sides across said first interior corner and adjacent to said cross member;
 - a second reinforcing member attached between said second sides across said second interior corner and adjacent to said cross member;
 - a third reinforcing member attached between said cross member and said first angled post member adjacent to said first reinforcing member; and
 - a fourth reinforcing member attached between said cross member and said second angled post member adjacent to said second reinforcing member.

5,586,785

VEHICLE WIRE CUTTER

Joseph G. Warner, Sterling Heights, and Christopher J. Benesch, Livonia, both of Mich., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.


Filed Oct. 6, 1995, Ser. No. 540,362

Int. Cl.⁶ B60R 19/00; 21/00

U.S. Cl. 280—762

1 Claim

1. A wire cutter adapted for installation on a vehicle to sever and protect it from a wire disposed transversely to the direction of vehicle travel, comprising a first bracket adapted to be mounted to the front of the vehicle to be protected, the first bracket having a channel formed therein; a first vertically extending cutting bar having a first end adapted to be attached to and mounted within the channel formed in the first bracket the first cutting bar having a



said reinforced ribs enwrapped by soft plastic cloth with woven designs;
wherein foldable outer end edge is turned upward to fasten an outer end edge of said outer movable plate, and wherein said outer movable plate and said positioning plate are inclined.

5,586,787

METHOD AND APPARATUS FOR PREVENTION OF REGISTER RECEIPT FALSIFICATION


Jerry W. Brown, and Stewart Brubaker, both of 4303 Victory Dr., St. 303, Austin, Tex. 78704

Filed Dec. 20, 1994, Ser. No. 360,984

Int. Cl.⁶ B42D 15/00

U.S. Cl. 283—67

12 Claims



plurality of serrations on a front face of the first cutting bar, the first cutting bar has a second mounting bracket located on a second end of the bar opposite the first bracket; a second cutting bar having a first end rotatably mounted to the first vertical cutting bar; a cutting hook mounted on a second end of the second cutting bar, the hook being disposed at an acute angle to the second cutting bar and having a beveled edge adapted to engage and sever the wire; a boss mounted on the vehicle juxtaposed a passenger compartment to be protected; an adjustable length support arm having one end attached to the boss and another end attached to the second cutting bar at a location between the ends of the second cutting bar, the support arm length being chosen so as to hold the second cutting bar at an adjustable acute angle to a longitudinal axis of the vehicle; whereby the second cutting bar will make contact with a wire to be severed at an angle which provides a reduced normal stress on the second cutting bar as the wire traverses a cutting edge of the second cutting bar to weaken the wire, and wire hitting the hook will be subjected to a large normal force severing the wire.

5,586,786


EASEL SHOW FILE DISPLAY BOOKS

Liang-Feng Su, 58, Ma Yuan West St., Taichung, Taiwan
Filed Aug. 21, 1995, Ser. No. 517,057

Int. Cl.⁶ A47B 23/00

U.S. Cl. 281—33

1 Claim



1. A foldable cover is made of recyclable polypropylene, said cover comprising:
 - an outer movable plate;
 - a positioning plate;
 - an inner movable plate;
 - said outer movable plate extending from one side of said positioning plate, and said inner movable plate extending from the other side of said positioning plate;
 - a crease line disposed at an outer edge of said inner movable plate defining a foldable outer end edge;
 - a plurality of transparent envelopes positioned by said positioning plate;
 - two reinforced ribs which are made of steel wire imbedded in two longer side edge portions of said foldable cover;

5,586,788

LABEL FOR OPERATION CONTROL SYSTEM

David F. Laurash, Bellbrook, Ohio, assignor to The Standard Register Company, Dayton, Ohio


Continuation of Ser. No. 276,262, Jul. 18, 1994, Pat. No. 5,486,021, which is a continuation of Ser. No. 961,377, Oct. 15, 1992, Pat. No. 5,383,686. This application Dec. 21, 1995, Ser. No. 575,212

Int. Cl.⁶ B42D 15/00

U.S. Cl. 283—81

5 Claims

1. A label form comprising:
 - a first sheet having a first portion on a first surface thereof with an adhesive associated therewith;
 - a second sheet located adjacent to said first sheet and having a second portion on a second surface thereof which is positioned adjacent to said first portion, said second portion being substantially coextensive with said first portion and having a



first section coated with release material and a second section without release material.

5,586,789


QUICK CONNECTOR FOR JOINING LARGE DIAMETER VACUUM HOSE TO DUCTWORK

John F. Bently, 11153 S. Wilton River Rd., New Richland, Minn. 56072

Filed Jun. 29, 1995, Ser. No. 496,602
Int. Cl.⁶ F16L 35/00

U.S. Cl. 285—38

2 Claims



1. Apparatus for cleaning ductwork comprising:

a hose attachment tube body for receiving a hose at one end and including a flat flange attached at the other end, said flat flange adapted to abut against the surface of the ductwork around a hole in the ductwork;

means for temporarily and removably connecting said hose attachment tube body flange to said surface over the hole therein including;


at least one pivoting rod assembly attached to the interior of said hose attachment tube body, said pivoting rod assembly comprising support ear means, a rod, rod bushings, a compression spring and means extending to the exterior of said hose attachment tube body for manipulating said pivoting rod assembly; said rod being supported by said rod bushings for movement relative thereto, said support ear means connected to one end of said rod and said compression spring arranged to resist axial movement of said rod in a direction toward said other end;

said support ear means engaging the interior of the ductwork adjacent the hole therein when said flat flange is in abutting engagement with said surface over the hole therein and said pivoting rod assembly is manipulated by said means extending to the exterior to move said support ear means through the hole and into engagement with the interior wall adjacent the hole with the wall of the ductwork being thereby clamped between said flat flange and said support ear means by the pressure exerted by said compression spring.

5,586,790
FLUID COUPLING AND FASTENER CAPTURE DEVICE
Kurt K. Bynum, Saline, Mich., assignor to Moeller Manufacturing Co., Inc., Wixom, Mich.
Continuation-in-part of Ser. No. 826,005, Jan. 27, 1992, Pat. No. 5,362,110, and Ser. No. 660,645, Feb. 25, 1991, Pat. No. 5,083,819. This application Nov. 8, 1994, Ser. No. 335,638
Int. Cl.⁶ F16L 55/00

U.S. Cl. 285—89

8 Claims



1. A capture device comprising a plurality of tangs extending substantially in parallel longitudinally and axially and attached together at one end of each tang to form a single integral tang portion, said tang portion adapted to non-rotatably engage a first fitting, and said tangs radially spaced from the axis of the first fitting, and said tangs separated by slots lying in planes containing said axis; a detent portion comprising a plurality of detents separated by peaks in a substantially cylindrical configuration, said detent portion non-rotatable with respect to a second fitting, said first and second fittings rotationally engageable; said plurality of tangs flexing longitudinally in engagement with the detent portion as the first and second fittings are rotationally engaged and as the tangs ratchet over the peaks between the detents.

5,586,791

PUSH-FIT CONNECTOR FOR JOINING A FLUID LINE TO A PIPE

Hary Kirchner, Hanau; Ralf Hohmann, and Ralf Spors, both of Bruchköbel, all of Germany, assignors to Rasmussen GmbH, Maintal, Germany


Filed Aug. 14, 1995, Ser. No. 514,694

Claims priority, application Germany, Aug. 19, 1994, 44 29 498.0

Int. Cl.⁶ F16L 43/02

U.S. Cl. 285—179

6 Claims



1. A connector for joining a fluid line to a pipe, said connector comprising:

a pipe having an outwardly projecting retaining rib, said pipe having a first end;

an angled pipe section having a first end section which is configured to be connected to the fluid line and a second end section which is configured to be connected to the first end of

said pipe, said second end section having at least one outwardly projecting tooth; and
a coupling ring being fixedly connected to said angled pipe section at any one of a predetermined number of relative rotational positions, said coupling ring having at least two inwardly projecting teeth and a pair of outwardly projecting retaining arms, said at least two inwardly projecting teeth engaging with said at least one outwardly projecting tooth to prevent said coupling ring and said angled pipe section from rotating with respect to each other, said retaining arms being engaged with said retaining rib, said first end of said pipe having an anti-rotation means for preventing rotation of said coupling ring with respect to said pipe.

5,586,792

QUICK CONNECTOR WITH INTEGRAL RELEASE MECHANISM


Gopichand Kalahasthy, Clinton Township, and James R. Zinke, II, Sterling Heights, both of Mich., assignors to Bundy Corporation, Warren, Mich.

Filed Feb. 21, 1995, Ser. No. 391,138

Int. Cl.⁶ F16L 37/14

U.S. Cl. 285—319

11 Claims



1. A quick connector coupling for forming a joint in a fluid line system comprising:

a female connector body having a generally cylindrical exterior wall a through bore extending from an end of said connector body, an outer annular rim adjacent said end of said connector body joined to an inner annular rim by spaced support members, the spacing between said support members defining slots, and a raised semi-annular shield formed on said exterior wall adjacent said inner annular rim;

a male member extending through said end of said connector body and into said bore, said male member having a tubular surface and an annular upset, said upset having a greater diameter than said tubular surface;

a retainer demountably coupled to said connector body, said retainer including two spaced beams extending from a cross member spaced from said exterior wall through said slots and being positioned between said male member upset and said connector body end, said beams having a relaxed spacing less than a diameter of said upset such that said male member is secured in said connector body; and

release means associated with said retainer, said release means being cooperable with said exterior wall of said connector body to spread said beams apart a distance greater than said diameter of said upset such that said male member may be withdrawn from said connector body.

5,586,793

LOCK FOR SLIDE BOLT LATCHES

Charles L. Davenport, 34 Sherry Dr., Southington, Conn. 06489


Filed Dec. 22, 1995, Ser. No. 577,497

Int. Cl.⁶ E05C 5/00

U.S. Cl. 292—67

12 Claims

1. A door latch assembly having open and closed positions comprising:



(a) a door latch having
(i) a bracket adapted to be mounted on a door; and
(ii) an elongated bolt having a shank with a handle portion at one end thereof and a locking arm at the other end thereof extending substantially perpendicularly to said shank, said shank adjacent said one end being slidably and rotatably seated in said bracket, said bolt being rotatable at least 90° about its axis to move said arm between a first position to a second position and said bolt being reciprocable axially in said bracket to move said arm portion from a first axial position spaced from said bracket to a second axial position adjacent thereto; and
(b) a locking clip removably mounted upon said shank of said bolt between said locking arm of said bolt and said bracket in said first axial position of said bolt, whereby, when said clip is mounted upon said bolt, said clip restricts the axial movement of said bolt from said first axial position by its abutment against said bracket.

5,586,794


RESEALABLE FASTENING DEVICE Woodrow C. Stillwagon, 7610 Ball Mill Rd., Atlanta, Ga. 30350

Filed Dec. 21, 1994, Ser. No. 361,429

Int. Cl.⁶ E05C 19/00

U.S. Cl. 292—252

5 Claims



1. A latching assembly comprising
a rigid stud member (121, 121') having a free end,
a retention surface (102, 102') adjacent to the other end of the stud member,
a tubular support housing (14, 14') enclosing at least partially a fastening device (10) including a cylindrical shell (12) having an axial passage (22) for receiving said stud member through one end thereof, and a plurality of radial openings (21) provided in said cylindrical shell and arranged in circumferentially spaced relationship.

a plurality of hardened balls (31) disposed in said radial openings of said shell and movable under the influence of said cylindrical shell;
 a spring retention shoulder (24) associated with said cylindrical shell at said one end of said cylindrical shell;
 a compression spring (41) positioned about said cylindrical shell and supported on said retention shoulder (24);
 a pressure ring (51) slidably disposed about said cylindrical shell and having a pressure application surface (54) in contact with said compression spring;
 means for moving said pressure ring from a first to a second position with respect to said cylindrical shell and maintaining said ring in either position;
 said pressure ring having an interior cam surface comprising a portion adjacent said pressure surface which is parallel to said cylindrical shell and a portion which is outwardly tapered, whereby said pressure ring, when in said first position, forces said hardened balls to impinge on said stud member, and, when in said second position, releases said balls so that the stud member may be removed from said cylindrical shell or inserted therein.

5,586,795

EMBEDDED-TYPE HANDLE ASSEMBLY

Shunji Sasaki, Tokyo, Japan, assignor to Takigen Manufacturing Co. Ltd., Tokyo, Japan

Continuation of Ser. No. 191,811, Feb. 3, 1994, abandoned.


This application Aug. 30, 1995, Ser. No. 521,015

Claims priority, application Japan, Mar. 1, 1993, 5-013637 U

Int. Cl.⁶ E05B 3/00

U.S. Cl. 292—336.3

6 Claims



1. An embedded-type handle assembly, comprising:
 a casing (1) having side walls (4) and a bottom wall (6);
 a handle (2) having a base-end portion which is pivoted to the side walls (4) of said casing (1) through a cross pivot (3) so as to be received in said casing (1), said handle (2) being provided with an operating-foot plate (5) in a rear surface of said handle base-end portion, which plate (5) projects from said rear surface to pass through a through-hole (7) of the bottom wall (6) of said casing (1), said bottom wall (6) having a cylindrical bearing portion (8) projected outwardly from a rear surface of the bottom wall (6);
 a shaft (9) rotatably inserted in said cylindrical bearing portion (8) of said casing (1);
 a spring (14) encircling said cylindrical bearing portion (8) and arranged for biasing said handle (2) toward its embedded position within said casing (1);
 a link plate (18) provided with a circular hole (16) through which said link plate (18) is mounted on a front-end portion of said shaft (9) in an insertion manner, said link plate (18) being prevented from dropping off of said shaft (9);
 a first lock bar (20) having its base-end portion connected with one end portion (19) of said link plate (18) through a pivot (27);

a second lock bar (23) having its base-end portion connected with the other end portion (22) of said link plate (18) through a pivot (28); and
 said link plate (18) being provided with a follower surface (25) in a side surface of the other end portion (22), so that said follower surface (25) can be pushed by said operating-foot plate (5) of said handle (2) to rotate said link plate (18) and move said first and second lock bars (20, 23).

5,586,796

REINFORCING DEVICES FOR DOORS AND DOOR FRAMES

Paul E. Fraser, 501, Valcartier, Loretteville, Quebec, Canada

Continuation of Ser. No. 998,461, Dec. 30, 1992, abandoned.


This application Feb. 21, 1995, Ser. No. 393,924

Claims priority, application Canada, Dec. 30, 1991, 2058615

Int. Cl.⁶ E05B 17/00

U.S. Cl. 292—346

20 Claims



1. A reinforcement device for a door, the door comprising interior and exterior parallel surfaces and also comprising at least one door control device of at least one bolt, dead or live, the bolt extending through a side of the door joining the two previous parallel surfaces thereof, said reinforcement device comprising a pair of distinct inner and outer reinforcing plates having inner flat sides adapted to be positioned substantially opposite one to the other respectively on the interior and exterior surfaces of the door and close to the side of the door carrying the bolt, each one of said plates defining at least a first opening intended to receive the control device of the bolt, mounting means being provided for connecting said plates together, said mounting means for extending through the door substantially along the thickness thereof, said reinforcement device thus reinforcing the door at least around the bolt; wherein said mounting means comprise at least one element mounted to said outer plate, said element extending towards said inner plate and adjacent thereto, and attachment means adapted to connect said inner plate to said element with said element and said attachment means for being at least partly received in at least a second opening defined substantially transversely in the door in such a way that said attachment means urge said inner plate towards said element, thermal break means being provided between said inner plate and said outer plate.

5,586,797

AUTOMOTIVE DOOR ASSEMBLY

Shinichi Hirahara, and Hiroki Morimoto, both of Saitama-ken, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 27, 1995, Ser. No. 508,207


Claims priority, application Japan, Jul. 29, 1994, 6-197320

Int. Cl.⁶ B60J 5/04

U.S. Cl. 296—146.6

7 Claims

1. An automotive door assembly, comprising:
 an outer panel;



an inner panel opposing said outer panel, said inner panel presenting a concave surface toward said outer panel as seen in vertical cross section; and

an inner reinforcement means, made of a plate member attached to an internal surface of said inner panel, for presenting a mutually concave surface toward said inner panel as seen in vertical cross section so as to jointly define a closed vertical cross section with said inner panel, said inner panel being more readily deformable than said inner reinforcement means so that upon receiving impact force from said vehicle occupant in a side collision, lateral deceleration or lateral acceleration situation, said inner panel extends in a direction parallel to a longitudinal direction of said inner panel to apply a tensile force to said inner reinforcement means to stretch said inner reinforcement means into a more straightened condition.

5,586,798

CURVED WINDOW GLASS PANEL AND METHOD OF INSTALLING CURVED WINDOW GLASS PANEL ON AUTOMOBILE BODY

Hiroyuki Saegusa, Utsunomiya, Japan, assignor to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 188,413, Jan. 24, 1994, abandoned.


This application Dec. 12, 1995, Ser. No. 571,019

Claims priority, application Japan, Jan. 25, 1993, 5-028681

Int. Cl.⁶ B60J 1/18

U.S. Cl. 296—146.15

4 Claims



1. A curved window glass panel for installation on an attachment frame on an automobile body, said automobile body having a window glass attachment frame fixed to said body and having a guide surface fixed to each of opposite ends of said frame, each guide surface having a slant surface, comprising:
 a glass panel having a curved center portion; and
 a pair of bent end glass portions extending from opposite ends of said center glass panel portion, said attachment frame having a portion extending substantially parallel to each of the bent end portions and one of the slant surfaces extending from each substantially parallel attachment frame portion toward the bent end portion, each of said bent end glass portions having a holder on an inner surface of each of said bent end glass portions for, respectively, engaging said slant guide surface on each said guide surface fixed to a respective opposite end of said attachment frame for guiding each holder on said inner surface of said bent glass portion and said

curved window glass panel inwardly into a predetermined position with respect to said attachment frame when said curved window glass panel is pressed against said attachment frame.

5,586,799

UPPER BODY STRUCTURE OF A VEHICLE

Northiko Kanemitsu; Manabu Tamura, both of Hiroshima; Koh Nakao, Hiroshima-ken; Yukari Kato, Hiroshima; Katsumi Ejima, Hiroshima-ken, and Noboru Yoshii, Higashihiroshima, all of Japan, assignors to Mazda Motor Corporation, Hiroshima-ken, Japan

Continuation of Ser. No. 151,392, Nov. 12, 1993, abandoned.

This application Sep. 8, 1995, Ser. No. 524,958


Claims priority, application Japan, Nov. 11, 1992, 4-083576

U

Int. Cl.⁶ B62D 25/04

U.S. Cl. 296—203

7 Claims



1. An upper body structure for a car body comprising:
 inner and outer front pillar panels forming a hollow front pillar having a vertical lower section and an inclined upper section which is bent rearward from a top of said vertical lower section;
 a reinforcement extending inside of the hollow front pillar from the vertical lower section to the inclined upper section for structurally reinforcing a part of the hollow front pillar, said reinforcement including a front inner surface portion, a side wall inner surface portion and a rear inner surface portion;
 and
 a gusset, disposed entirely inside of a space defined by said front inner surface portion, said side wall inner surface portion, said rear inner surface portion and an outer surface of the inner front pillar panel, having a wall extending in said space approximately vertically so that said wall abuts with said rear inner surface portion in said vertical lower section and said front inner surface portion in said inclined upper section so as to divide the space into front and rear sections.

5,586,800

HIGH CHAIR TRAY

Kelvin N. Triplett, 11304 E. 16th Ave., Spokane, Wash. 99206


Filed Oct. 3, 1995, Ser. No. 535,776

Int. Cl.⁶ A47B 83/02

U.S. Cl. 297—148

9 Claims

1. A high chair tray, comprising:
 a tray assembly having a top surface and a bottom surface, said tray assembly including a forward tray component and a rearward tray component divided by a lateral separation line, said forward tray component and said rearward tray component disposed in coplanar relationship;
 a left and a right track member extending forwardly from said rearward tray component, said left track member and said right track member permanently and slidably secured to said forward tray component, said left track member and said right



track member slidably connecting said forward tray component and said rearward tray component together;
at least one container receptacle included in said tray assembly and divided substantially equally said lateral separation line, said at least one receptacle including a rim protruding from said top surface of said tray assembly around said at least one container receptacle;
a plate underlying said bottom surface of said tray assembly, said plate extending from said rearward tray component forwardly under said at least one container receptacle, said plate and said rim defining a peripheral channel surrounding said at least one container receptacle, whereby;
at least one container including flanges adapted to be positively secured within said at least one container receptacle placed on said plate is securable to said tray assembly by slidably closing said forward and rearward tray components together along said left and right track members to secure the container positively within said tray assembly by said peripheral channel surrounding said at least one container receptacle.


5,586,801

STUD MOUNTED HOIST RING

David R. Sawyer, Smithfield, and Douglas M. Wheeler, Newport News, both of Va., assignors to Newport News Shipbuilding and Dry Dock Company, Newport News, Va.

Filed Oct. 27, 1994, Ser. No. 329,929
Int. Cl.⁶ B66C 1/66; F16G 15/08

U.S. Cl. 294—1.1



1. A hoist ring assembly for attachment to a load lifting point comprising:

a welding stud having a free end, a threaded shank, and a second end for welding to a load lifting point;
a bushing concentric with said welding stud;
a ring assembly in rotating and swivel engagement with said bushing;
a locking nut threadably engaged on said stud for holding said bushing against said lifting point;
a flat washer disposed on said welding stud between said bushing and said locking nut;
said bushing further comprising a bearing flange at one end for bearing engagement with the load lifting point and a sleeve at the other end, said bearing flange having an outer cylindrical surface and a plurality of inner cylindrical surfaces, said inner cylindrical surfaces being in stepped relationship with each other, said steps being formed by the diameter of one of said inner cylindrical surfaces being larger at an end of said flange in bearing engagement with said load lifting point and the diameter of the other of said inner cylindrical surfaces being smaller at an end of said flange adjacent said sleeve end, and at least said smaller diameter inner cylindrical surface having a chamfer.

5,586,802


LINKAGE FOR GUIDING A RETRACTABLE ROOM

James E. Dewald, Jr., Martin P. McManus, and Patrick W. McManus, all of 1023 W. Eighth St., P.O. Box 703, Mishawaka, Ind. 46544

Filed May 11, 1995, Ser. No. 438,765
Int. Cl.⁶ B60R 27/00

U.S. Cl. 296—26

12 Claims



1. Mobile living quarters comprising a main frame including a pair of main frame members, an axle mounted on said main frame members, a pair of wheels mounted on said axle, main living area defining means including a main floor mounted on said main frame members and walls extending from said floor for defining a main living area, a retractable room mounted for movement in a direction substantially parallel to said main floor from a retracted position retracted into said main living quarters to an extended position extended from said main living area to provide an auxiliary living area, said retractable room including a subframe member facing one of said main frame members and extending substantially parallel thereto, a linkage connected between said one main frame member and said subframe member for guiding said retractable room during extension and retraction thereof, said linkage having a pair of arms, each of said arms having opposite ends, first pivot means securing one end of one of said arms to said main frame and one end of the other arm to said retractable room, second pivot means securing one end of said one arm to said retractable room and the other end of said other arm to said main frame, and actuating means for moving said retractable room between said retracted and extended positions.

5,586,803


PORTABLE PICNIC TABLE

Willard T. Overpeck, 171 Bellwood Ave., Wellsboro, Pa. 16901
Filed Oct. 14, 1994, Ser. No. 324,402

Int. Cl.⁶ A47B 83/02

U.S. Cl. 297—158.3

1 Claim



1. A portable picnic table comprising:

- a tabletop having first and second ends and a pair of connecting side;
- a first pair of legs extending downwardly from said first end of said tabletop at an angle, so as to diverge toward the opposite connecting sides of said tabletop;
- a second pair of legs extending downwardly from said second end of said tabletop at the same angle as said first pair of legs;
- each said leg of each said pair of legs having a front face facing one connecting side of said tabletop, a back face facing the opposite connecting side of said tabletop, an outer side face facing the adjacent end of said tabletop, an inner side face opposite said outer side face, said faces defining a rectangular cross sectional configuration, in which said side faces are wider than said front and back faces;
- means comprising a pair of crossbars for maintaining said first and second pair of legs in spaced relationships;
- a pair of bench boards, each extending between the ends of said crossbars below the opposite sides of said tabletop;
- means on said outer side faces near bottom ends of said first pair of legs for rolling said first pair of legs along the ground when the second end of said tabletop is lifted up by the hands of a person and then pushed by the hands of the person, said rolling means including a pair of wheel assemblies and means for securing said wheel assemblies to said outer side faces near the bottom ends of said first pair of legs such that said wheels extend a distance below said first pair of legs whereby the first end of said tabletop is supported directly by said rolling means, each wheel assembly including a wheel bracket, an axle carried in said wheel bracket, and a wheel rotatively mounted on said axle, each wheel bracket including a central portion having a plurality of apertures therethrough and a pair of arm portions integral with and extending at a right angle from said central portion, each said arm portion having a hole therethrough at a distal end to receive said axle, each said securing means including a backing plate on each of the inner faces of said first pair of legs, each said backing plate having a plurality of apertures therethrough which align with said apertures in said central portion of one said wheel bracket and apertures formed in each said first leg, and a plurality of bolts extending through the aligned apertures in said bracket, first leg, and said bracket, with a nut engaging each of said bolts to hold said wheel bracket on said first leg;
- means on the bottom ends of said second pair of legs for raising said second pair of legs off the ground when at rest to compensate for said rolling means on said first pair of legs to maintain said tabletop in a true horizontal level position, said raising means including a pair of foot brackets and means for attaching said foot brackets to the bottom ends of said second pair of legs, each foot bracket comprising a base portion for resting on the ground surface and spaced from a bottom end of each of said second pair of legs and a pair of side portions each integral with and extending at a right angle from said base portion, each fixed and said side portion having a plurality of openings therethrough to accommodate fasteners passing through said openings into said second pair of legs.

5,586,804

BEVERAGE CONTAINER HOLDER FOR A FOLDING CHAIR

Richard H. Burroughs, Green Bay, Wis., assignor to Krueger International, Inc., Green Bay, Wis.

Filed Jun. 19, 1995, Ser. No. 492,236

Int. Cl.⁶ A47C 7/62

U.S. Cl. 297—188.08

18 Claims



16. A folding chair, comprising:

- a seat assembly including a frame member and a seat mounted to the frame member, the seat defining a peripheral edge;
- a back assembly;
- wherein the seat assembly and the back assembly are collapsibly interconnected with each other for providing movement of the seat and the back assemblies between a collapsed, storage position and an open, use position;
- a beverage container holder assembly, comprising a mounting member mounted to the seat assembly, and a container holder member including an outer container holding portion and an inner mounting portion movably secured to the mounting member for providing pivoting movement of the container holder member between a storage position in which a majority of the outer container holding portion is located inwardly of the seat peripheral edge, and an operative position in which the container holding portion is located outwardly of the seat peripheral edge; and
- wherein the frame member and the seat cooperate to define a downwardly facing recess within which the mounting member is located.

5,586,805

PORTABLE COMBINATION SEAT AND CONTAINER


John R. Rinehart, Milton, Wis., assignor to American Institute of Taxidermy, Inc., Janesville, Wis.

Filed Jul. 26, 1994, Ser. No. 280,497

Int. Cl.⁶ A47C 9/00

U.S. Cl. 297—188.09

13 Claims




1. A seat-container capable of use with a generally cylindrical bucket having a circular bucket rim bounding the interior of the bucket surface, comprising:

a receptacle having a bottom, a flat sidewall joined to the bottom, a curved sidewall joined to the bottom and the flat sidewall, a rim having a straight portion at the top of the flat sidewall and a semicircular portion at the top of the curved sidewall, the rim including a receptacle flange extending outwardly from the curved sidewall which is capable of supporting the receptacle on the bucket rim when the receptacle rests within a portion of the interior of the bucket, and further including a ridge which extends downwardly from an outer edge of the receptacle flange, the bottom, sidewalls and rim integrally formed of plastic;

a lid seat having a semicircular shape with a straight edge, and an integral hinge connecting the straight edge of the lid seat to the straight portion of the receptacle rim, the lid seat sized so that when the lid seat is in a closed position on the receptacle it extends over the rim flange of the receptacle to be firmly supported about the periphery of the lid seat by the rim of the receptacle such that the lid seat will support an individual seated on the lid seat wherein the lid seat includes a ridge which extends downwardly from a curved outer edge of the lid seat such when the lid seat is in the closed position, the ridge the lid seat extends downwardly closely adjacent to the ridge on the receptacle flange; and

wherein the receptacle, the hinge, and the lid seat are integrally formed of plastic such that the hinge is defined by a region of plastic which is thinner than the plastic forming the receptacle and lid seat.


5,586,806
UNDERSEAT ARTICLE HOLDER APPARATUS
 Arthur Hergott, Deerfield, Ill., assignor to Greenwich Industries, L.P., Lake Bluff, Ill.
 Filed Nov. 21, 1995, Ser. No. 561,437
 Int. Cl.⁶ A47C 7/62
 U.S. Cl. 297—188.11
 22 Claims



12. A seating apparatus comprising:
a seat having laterally spaced sides;
a guide mounted to the seat;
a carriage supported by the guide for movement in a first path between the laterally spaced sides; and
a receptacle holder supported by the carriage for movement in a second path transverse to the first path;
the seat includes a substantially flat bottom surface and the guide includes a pair of longitudinally spaced rails extending between the laterally spaced sides and spaced from the bottom surface with the carriage mounted between the rails and the bottom surface for movement in the first path;
the carriage comprising a frame having a pair of spaced legs and a base, the receptacle holder comprises a substantially planar elongate member located between the spaced legs of the carriage and the substantially planar elongate member moves along the spaced legs in the second path; and

the substantially planar elongate member comprising a forward end and a rearward end, the forward end adapted to hold an article, the substantially planar elongate member further being movable between a retracted position with the receptacle holder generally beneath the bottom surface of the seat and the rearward end being adjacent to the frame of the carriage, and an extended position with the forward end extending outwardly from beneath the bottom surface of the seat to expose the receptacle holder forward end to hold an article, and the rearward end being spaced from the frame of the carriage.

5,586,807
VEHICLE SEAT TRIM COVER RETAINER
 Russell C. Taggart, White Lake, Mich., assignor to Atoma
 International Of America, Inc., Livonia, Mich.
 Filed Feb. 10, 1995, Ser. No. 386,417
 Int. Cl.⁶ A47C 31/02



1. A trim cover of a vehicle seat in combination with a retainer for securing first and second ends of the trim cover to a portion of a frame of the seat such that said first and second trim cover ends are in generally adjacent relation when the retainer is fixed to the frame portion, the retainer comprising:


- a first elongate body having a base portion and first and second arms extending in spaced relation from said base portion defining a first, open-ended channel therebetween;
- a second elongate body having a base portion and first and second arms extending in spaced relation from said base portion of said second body defining a second, open-ended channel therebetween, said second arm of said second body being coupled to said first body in such a manner that (1) a longitudinal axis of said first body is in parallel relation with a longitudinal axis of said second body and (2) an open end of said first channel is oriented at an angle of at least 180° with respect to an open end of said second channel; and
- a planar portion extending from said first arm of said first body in parallel relation with said second arm of said first body, said first end of said trim cover being attached to said planar portion.

said first channel being constructed and arranged to receive said frame portion so as to be in secured relation therewith, said second channel being constructed and arranged to receive said second end of said trim cover.

5,586,808
**CHAIR WITH LATERAL FRAME PARTS CONNECTED
 BY TRANSVERSE RODS SUPPORTING SEAT AND
 BACKREST**
 Frank Oelke, Eichgrabenstr. 14a, D-82340 Feldafing, Germany
 Filed Apr. 21, 1995, Ser. No. 426,040
 Claims priority, application Germany, Apr. 22, 1994, 44 14
 120.3; Dec. 10, 1994, 44 44 047.2
 Int. Cl.⁶ A47C 5/10

U.S. Cl. 297-287 12 Claims
1. A chair comprising:


1. A chair comprising:



two lateral frame parts, each one of said frame parts comprised of a single, continuous member of an elastically yielding material;

transverse rods connected between said lateral frame parts; a seat connected to at least one of said transverse rods; and a backrest connected to at least one of said transverse rods; and wherein each one of said single members of said lateral frame parts has an upper rearward end, a lower rearward end, and a floor-contacting portion, wherein each one of said single members is curved continuously at a first radius of curvature from said upper rearward end forward and downward, then rearward and downward to said floor-contacting portion, from said floor-contacting portion upward and rearward, and then with an arc of a second radius of curvature, substantially smaller than said first radius of curvature, downward and rearward to said lower rearward end, wherein an end portion of said single member, positioned between said lower rearward end and said arc, extends straight downward and rearward at a slant.

5,586,809
HEIGHT ADJUSTMENT MECHANISM FOR A CHAIR
BACKREST
John A. Szmazdzinski, Muskegon, Mich., assignor to Herman
Miller, Inc., Zeeland, Mich.
Filed Aug. 4, 1995, Ser. No. 511,612
Int. Cl.⁶ B60N 2/02
U.S. Cl. 297—353 25 Claims



8. An adjustment mechanism for releasably retaining a backrest in a plurality of selected positions relative to a seat, the adjustment mechanism comprising:

- a channel member adapted to be rigidly secured to the backrest;
- a support member slidably received by said channel member and adapted to be rigidly secured to the seat;
- a first plurality of vertically aligned rack teeth extending in a generally lateral direction from the support member;

a second plurality of vertically aligned rack teeth extending from the support member in the same direction as the first plurality of rack teeth, said second plurality of rack teeth being spaced apart from and generally parallel to said first plurality of rack teeth;

a catch having spaced apart, horizontally aligned, first and second pawls extending in the opposite direction as the first and second plurality of rack teeth, said catch being slidably mounted to one of the channel member and the support member, wherein actuation of the catch causes movement thereof in a linear, horizontal direction to simultaneously selectively engage the first and second pawls with the respective first and second plurality of rack teeth; and


a spring acting against the catch for biasing the first and second pawls into engagement with the first and second plurality of rack teeth;

whereby the backrest is retained from falling downwardly from a desired vertical position by the engagement of the first and second pawls with the first and second plurality of rack teeth.

5,586,810
ADJUSTABLE HEADREST
 Yang-Ting Liu, P.O. Box 82-144, Taipei, Taiwan
 Filed Feb. 12, 1996, Ser. No. 599,847
 Int. Cl.⁶ H47C 7/36

U.S. Cl. 297—406

2 Claims



1. A headrest comprising:

- 1. A nest comprising:
 - two vertical rods;
 - an upper horizontal rod connected between upper ends of said two vertical rods;
 - a lower horizontal rod connected between lower ends of said two vertical rods;
 - a pair of vertical supporting means arranged between said upper and lower horizontal rods and including a positioning rod and a guiding rod;
 - a first pair of sliders slidably mounted on said upper horizontal rod and having a recess at an intermediate portion and two pins at a bottom thereof adapted to engage with upper ends of said positioning rod and guiding rod;
 - a second pair of sliders slidably mounted on said lower horizontal rod and having a recess at an intermediate portion and two pins at a bottom thereof adapted to engage with lower ends of said positioning rod and guiding rod;
 - a first pair of cylindrical members each fitted in said recess of said first pair of sliders and having a lug and an eccentric hole receiving said upper horizontal rod;
 - a second pair of cylindrical members each fitted in said recess of said second pair of sliders and having a lug and an eccentric hole receiving said lower horizontal rod;

a pair of panels each slidably mounted on said guiding rod and having a cavity and a projection plate; and a pair of cylinders each fitted in said cavity and having an eccentric hole receiving said guiding rod.

5,586,811

ADJUSTMENT DEVICE FOR CHAIR ARMS


Lino E. Tornero, 809 Quailmeadow L.A., Colfax, N.C. 27235

Filed Aug. 15, 1994, Ser. No. 289,578

Int. Cl.⁶ A47C 7/54

U.S. Cl. 297—411.36

8 Claims



1. An adjustment device comprising: a structural member, said structural member defining a slot, a support member, said support member in contact with said structural member, a retaining member, said support member and said retaining member encasing said structural member therebetween, a detente element, said detente element contacting said structural member for selective adjustable movement of said structural member along said support member, bushing means, said bushing means defining a guide post aperture, a guide post, said guide post passing through said guide post aperture, a friction element, said friction element contacting said bushing means and said structural member to slightly retard the movement of said structural element, said bushing means defining a receiving cavity, said receiving cavity for reception of said frictional element.

5,586,812

RAILWAY BRAKING APPARATUS

Wajih Kanjo, Lockport, Ill.; Eric Smith, Burlington, Canada; Thomas J. Demoise, Export, Pa.; Michael Girotti, Thorold; Thomas McCabe, Dorval, both of Canada; Charles B. Fessler, Lancaster, Pa., and Scott Natschke, Kankakee, Ill., assignors to Westinghouse Air Brake Company, Wilmerding, Pa.

Division of Ser. No. 278,937, Jul. 22, 1994. This application


Jun. 7, 1995, Ser. No. 477,470

Int. Cl.⁶ B60T 1/300

U.S. Cl. 303—7

4 Claims

1. A parking brake release system for a railway vehicle having a first conduit for fluid pressure, service brakes actuated by fluid pressure in such first conduit such that an increase in said fluid pressure causes release of such service brakes, and a reduction of said fluid pressure causes application of such service brakes, an auxiliary parking brake apparatus, means for manually actuating



such auxiliary parking brake apparatus to a braking condition, said parking brake release system comprising a parking brake cylinder biased to a braking position by mechanical means when such auxiliary parking brake apparatus has been manually actuated, said parking brake cylinder responsive to such increase in said fluid pressure in such first conduit to configure said parking brake cylinder to a brake release position and wherein said reduction of said fluid pressure causes application of such auxiliary parking brake apparatus.

5,586,813

ELECTRO-PNEUMATIC FREIGHT BRAKE CONTROL SYSTEM


Albert A. McKay, Stoney Creek, and Eric G. Smith, Burlington, both of Canada, assignors to Westinghouse Air Brake Company, Wilmerding, Pa.

Filed Apr. 27, 1995, Ser. No. 429,450

Int. Cl.⁶ B60T 8/18

U.S. Cl. 303—22.4

3 Claims



1. A railroad car brake control system comprising:
a) a source of fluid under pressure;
b) a brake cylinder device;
c) application and release control valve means interposed between said brake cylinder device and respective ones of said source of fluid under pressure and atmosphere;
d) electric communication means for conducting a brake command signal;
e) processor means for establishing and interrupting electrical communication between a source of electric power and said application and release control valve means in accordance with said brake command signal, said application and release control valve means in a deenergized condition establishing communication between said source of fluid under pressure and said brake cylinder device;
f) electric load sensing means for providing a car load signal corresponding to the load weight of said car; and
g) pressure limiting valve means interposed between said application and release control valve means and said brake cylinder device, and subject to said car load weight signal for setting a maximum pressure limit above which the fluid pressure at said brake cylinder device is cut-off from said source of fluid under pressure, and for retaining the setting of

said maximum pressure limit following a loss of said car load weight signal, wherein said limiting valve means includes:

- (i) an inlet connected to said application and release valve means;
- (ii) an outlet;
- (iii) a proportioning valve assembly including:
 - (a) a differential area piston abutment;
 - (b) a supply valve carried on said differential area piston abutment via which fluid under pressure effective at said input is connected to said outlet;
 - (c) a load responsive piston connected to said differential area piston abutment and subject on one side to the fluid under pressure supplied to said inlet; and
 - (d) a non-rotatable spring seat spaced from the other side of said load responsive piston;
 - (e) a proportioning spring in the space between said other side of said load responsive piston and said spring seat;
 - (f) electric motor means subject to said car load weight signal and having a screw-threaded output shaft threadedly engaged with said spring seat for adjusting the degree of compression of said spring in accordance with the degree of rotation of said output shaft, the degree of rotation of said output shaft being dependent on said car load weight signal, the fluid pressure effective at said outlet when said car load weight signal is absent in consequence of a loss of said source of electric power corresponding to said maximum pressure limit.

trollable by which a deliberate brake application occurs; an auxiliary force valve coupled to the amplifier and which switchably causes exposure of the low-pressure chamber to a pressure equal to or greater than atmospheric pressure, this exposure causing a high actuating force sufficient for a full brake application to be deployed; an electronic control unit having an output signal coupled to the auxiliary force control valve to control the triggering of the switching of the auxiliary force control valve, the electronic control unit generating said output signal when the speed or the rate of change of the force with which the driver actuates the brake pedal exceeds a threshold value; an electronically controllable antilock brake system (ABS) coupled to and acting on the individual brake circuits by feedback, and having inlet and outlet valves associated individually with the wheel brakes; electrically drivable feedback pumps individually associated with the brake circuits and having a high output pressure level, wherein said pumps, in a pressure-reduction phase of antilock brake regulation resulting from the antilock brake system, recycle into a main brake line of the respective brake circuit the brake fluid released into a return line of the respective brake circuit;

a separate electrically controllable switching valve for each of the brake circuits, said valve being switchable from a functional position connecting the main brake line of the respective brake circuit with the respective pressure outlet of the braking device, into a functional position shutting off the respective pressure outlet from the respective main brake line; and

electrically controllable precharging control valves associated with the respective brake circuits and operatively arranged between the braking device and the ABS such that an outlet of each precharging control valve is connected solely with a line leading to the low pressure inlet of the respective return pump switchable from a functional position shutting off the respective pressure outlet of the braking device from a low-pressure inlet of a return pump of the respective brake circuit, into a functional position connecting the respective pressure outlet with the low-pressure inlet of the respective return pump whereby the braking device-precharges the return pumps and is employable to provide slip regulation as a function of wheel speed;

wherein the electronic control unit includes sensor inputs configured to receive sensor output signals representing at least one of the actuation of the brake pedal and the dynamic behavior of the motor vehicle, the electronic control unit generating signals required for automatic operation of the brake system at a high braking pressure level, for controlling the switching valves, the precharging control valves, the return pumps and the inlet and outlet valves of the antilock brake system and the auxiliary force control valve.

5,586,814

BRAKING PRESSURE CONTROL DEVICE WITH MAXIMUM VEHICLE DECELERATION DURING AUTOMATIC BRAKING

Maofred Steiner, Winnenden, Germany, assignor to Mercedes-Benz AG, Germany


Filed Aug. 30, 1994, Ser. No. 299,009

Claims priority, application Germany, Aug. 30, 1993, 43 29 140.6

Int. Cl.⁶ B60T 8/60; 8/40; 8/48

U.S. Cl. 303—116.2

7 Claims



1. Braking pressure control device for a motor vehicle with hydraulic multi-circuit brake systems with static brake circuits, comprising a master cylinder constituting a braking device with separate pressure outlets associated with each of said brake circuits; a pneumatic braking force amplifier coupled to said master cylinder and a brake pedal coupled to said pneumatic braking force amplifier, the brake pedal actuating the master cylinder through said amplifier; said amplifier having a drive chamber movably delimited by a piston between a permanent low-pressure chamber maintained at a low pressure, whose charging with a pressure monotonically correlated with pressure on the brake pedal is con-

5,586,815 METHOD AND SYSTEM FOR DETECTING FALSE FOUR-WHEEL DRIVE INDICATION IN ANTILOCK BRAKE SYSTEMS


Dan Negrin, Wiesbaden, Germany, assignor to Kelsey-Hayes Company, Livonia, Mich.

Filed Sep. 9, 1994, Ser. No. 303,389

Int. Cl.⁶ B60J 8/00

U.S. Cl. 303—143

27 Claims



1. A method for detecting an incorrect indication of four-wheel drive operation of a vehicle, the vehicle having a front axle with two front wheels and a rear axle with two rear wheels, the vehicle capable of both four-wheel drive operation where the front and rear axles are locked together and operation where the front and rear

axes are unlocked, the vehicle further having an antilock brake system and means coupled to the antilock brake system for indicating four-wheel drive operation, the method comprising the steps of:

- generating a first speed signal representative of a speed of at least one wheel on the front axle;
- generating a second speed signal representative of a speed of at least one wheel on the rear axle;
- calculating a decision value based upon the first and second speed signals; and
- detecting an incorrect indication that the vehicle is in four-wheel drive operation when the decision value is within a rejection region.


5,586,816

MULTI-PURPOSE, MOBILE STORAGE CABINET WITH HORIZONTALLY AND VERTICALLY ADJUSTABLE SHELF STRUCTURE

Michael J. Geiss, II, 531 Oak St., Syracuse, N.Y. 13203
Continuation-in-part of Ser. No. 119,485, Sep. 13, 1993, abandoned, and Ser. No. 911,090, Jul. 9, 1992, abandoned. This application Jun. 19, 1995, Ser. No. 492,240
Int. Cl.⁶ A47B 83/00

U.S. Cl. 312—301

27 Claims



- A combination cabinet and shelf structure comprising:
 - an outer cabinet having a top, planar surface and at least one support leg extending therefrom adapted to position and support said top surface a predetermined distance above a substantially planar floor surface;
 - a shelf structure comprising:
 - a platen;
 - an inner cabinet of generally rectangular configuration having a top, bottom and opposite side walls extending between said top and bottom walls to define an open front, said bottom wall mounted in covering relation to said platen; and
 - at least one shelf slidably mounted to said inner cabinet within said open front between said side walls, said shelf being slidably movable between a stored position beneath said top wall in said open front, and an extended position spaced forwardly of and adjacent said open front, said shelf lying in a plane spaced and parallel to said top and bottom walls;
 - horizontal adjusting means connected to and between said outer cabinet and said platen, said horizontal adjusting means operable to horizontally move said platen and said inner cabinet between a stored position with said platen and inner cabinet positioned beneath said outer cabinet top surface, and an extended position with said platen and inner cabinet positioned forwardly of and adjacent to said outer cabinet; and
 - vertical adjusting means connected to and between said platen and said inner cabinet, said vertical adjusting means operable to vertically move said inner cabinet and said at least one shelf between a fully lowered position with said inner cabinet

bottom wall lying in covering relation to said platen, and a fully raised position with said inner cabinet bottom wall positioned a predetermined distance above said platen.


5,586,817

DRAWER INTERLOCK APPARATUS

David Hubbard, Stamford, and Walter Wolog, Orange, both of Conn., assignors to Pitney Bowes Inc., Stamford, Conn.
Filed Sep. 5, 1995, Ser. No. 523,728
Int. Cl.⁶ A47B 88/00

U.S. Cl. 312—334.44

5 Claims



- A pair of drawers having a drawer interlock apparatus, each of the drawers including opposite side walls, a rear wall, and a front panel, the interlock apparatus comprising:

- a frame;
- a pair of longitudinal rails, each rail mounted to a side wall of each drawer, each rail including a front end and a rear end, a pair of substantially L-shaped stop means, one of the pair of stop means being situated at the front end of the rail, the other of the pair of stop means being situated at the rear end of the rail, and a locating notch having an angled surface positioned between the stop means; and,
- locking means pivotally mounted to the frame, the locking means further being slideably engaged with the rail of each drawer for preventing the simultaneous extension of the pair of drawers wherein the locking means comprises:
 - a pair of link mechanisms having a first end pivotally mounted to the frame, one of the pair of link mechanisms having a substantially T-shaped opposite end including an elongated slot, the other of the pair of link mechanisms having a pin fixedly mounted at an opposite end for engaging the elongated slot;
 - a spring interposed between the pair of link mechanisms; and
 - roller means rotatably mounted to the opposite end of each link mechanism and fitting into the locating notch, the roller means being engaged with the rail of each drawer so that as the roller means move toward the rear end of one of the pair of drawers, the spring compresses and the pin engages the elongated slot thereby prohibiting movement of the roller means engaged with the other of the pair of drawers.

5,586,818

THREE DIMENSIONAL PROJECTION SYSTEM


Dong-Hee Lee, Seoul, Rep. of Korea, assignor to Daewoo Electronics Co., Ltd., Seoul, Rep. of Korea
Filed Feb. 14, 1996, Ser. No. 601,437
Claims priority, application Rep. of Korea, Feb. 15, 1995, 95-2741

Int. Cl.⁶ G03B 21/00; G02B 7/04

U.S. Cl. 353—101

11 Claims

- A three dimensional projection system comprising:
 - a holder having an upper plate and a lower plate, a plurality of longitudinally inclined guiding holes symmetrically formed at both sides of said upper and lower plates and



- inclined at predetermined angles about central axes of said upper and lower plates, and first and second opening portions, said first and second opening portions being formed in rear central portions of said upper and lower plates, respectively; first and second projecting lens holders having cylindrical shapes and being provided with projecting lenses formed in front sides thereof, said holders being arranged in parallel in said holder housing;
- movable pins protrusively formed on upper and lower portions of said first and second projecting lens holders, said movable pins being respectively inserted into corresponding longitudinally inclined guiding holes;
- a holder supporting plate having a pair of front and rear plates and a spacer for maintaining a distance between said front and rear plates, said front and rear plates being provided with a first and a second leg portions formed at both sides thereof and extended through said first opening portion onto an upper portion of said upper plate, and a third and fourth leg portions extended through said second opening portion onto a lower portion of said lower plate, guiding grooves being formed at said leg portions for said movable pins being inserted thereinto;
- driving means for supplying driving power for transporting said projecting lens holders forward and backward; and
- transporting means for transporting the driving power supplied from said driving means to said projecting lens holders.

5,586,819

FLASHLIGHT

David J. Bamber, Wichita, Kans.; Benson Leung, and Vincent Leung, both of Kowloon, Hong Kong, assignors to The Coleman Company, Inc., Wichita, Kans.

Filed Nov. 8, 1994, Ser. No. 334,429

Int. Cl.⁶ F21L 7/00

U.S. Cl. 362—158

4 Claims

- A flashlight comprising:
 - a battery housing having a generally cylindrical side wall having an open top end, an inner surface, an outer surface, and a bottom wall, the outer surface of the side wall having male threads adjacent the top end of the battery housing;
 - a generally cylindrical switch housing having a generally cylindrical side wall having open top and bottom ends and inner and outer surfaces, the inner surface of the side wall of the switch housing having female threads adjacent the bottom end of the switch housing, the outer surface of the side wall of the switch housing having male threads adjacent the top end of the switch housing, the female threads of the switch housing being engaged with the male threads on the battery housing;
 - a switch mounted in the switch housing;
 - a bulb holder mounted in the switch housing adjacent the open top end of the switch housing;
 - a light bulb mounted in the bulb holder;
 - a head having an outer wall having open top and bottom ends and a generally cylindrical inner wall extending upwardly


5,586,820

MULTIDIRECTIONAL TASK LAMP

Andrew K. Klink, 865 First Ave., New York, N.Y. 10017
Filed Aug. 22, 1995, Ser. No. 518,049
Int. Cl.⁶ F21V 21/18

U.S. Cl. 362—402

7 Claims



- A multidirectional task lamp comprising:
 - a base;

a mounting socket;
a rod;
a tension wheel having an axial opening and a peripheral cleat;
a tubular extension arm including a socket end and a mounting end;
a shaded socket portion;
said mounting socket is disposed on said base;
said rod rotatably extends between said mounting socket and said axial opening;
said cleat includes an opening configured for slidably accepting said tubular extension arm;
said tension wheel is rotatably connected to the rod via a cross bar associated with said rod;
tension means associated with said tension wheel and another cross bar associated with said rod for controlling the rotatability of the tension wheel;
said shaded socket portion is rotatably disposed on said socket end on said tubular extension arm;
an electrical connection is guided through said tubular extension arm to provide an electrical connection to said socket end.

5,586,821

BONE CEMENT PREPARATION KIT


John A. Bonlati; Kirt L. Case, both of Warsaw; Michael E. Hawkins, Columbia City, and Stephen H. Hoag, Warsaw, all of Ind., assignors to Zimmer, Inc., Warsaw, Ind.

Filed Oct. 10, 1995, Ser. No. 541,360

Int. Cl.⁶ B01F 1/306

U.S. Cl. 366—139

16 Claims



1. An apparatus for manufacturing bone cement by mixing a plurality of constituent components comprising:

- a telescoping cartridge including a tubular outer cylinder having an open proximal end and a distal end, and a tubular inner cylinder having an open proximal end and a distal end shiftably received within said outer cylinder distal end, said inner cylinder being axially extensible between an extended position, an intermediate position, and a retracted position,
- a cap connectable to said outer cylinder proximal end, said cap part including means for connecting said cartridge to a vacuum pump to draw a vacuum within said cartridge when said inner cylinder is in its said extended position,
- an end plug, shiftably disposed within said inner cylinder for axial movement within said inner cylinder towards said cap to expel said cement from said cartridge,
- and means for releasing vacuum pressure within said cartridge when said inner cylinder is in its said intermediate position.

5,586,822
STIRRER LID FOR COLOR CANS OF STIRRING MACHINES

Alain Krzywdziak, Orleans, France, assignor to F.A.S., Orleans Cedex, France


Filed Jul. 5, 1995, Ser. No. 498,198

Claims priority, application France, Jul. 5, 1994, 94 08283

Int. Cl.⁶ B01F 7/20

U.S. Cl. 366—247

8 Claims



1. A stirrer lid for a color can which is positionable on paint stirring machines, said stirrer lid comprising a raised pouring lip; a sealing element for said pouring lip including shutter means (13, 13') for selectively opening and closing the pouring lip (7); an operating lever (15, 15') mounted on said lid for placing said sealing element into an open position for pouring the contents of the can; a pair of helical springs (25) for biasing said sealing element of the pouring lip into a closed position, said springs being two identical helical springs (25) for returning the sealing element (13, 13') into the closed position, said springs being arranged symmetrically relative to a vertical mid-plane (P) of the stirrer lid, each said spring having an upper end connected to the front base of the pouring lip (7) laterally relative to the pouring lip and being oriented downwardly toward the outer edge of the stirrer lid, each spring being connected at the ends thereof to a fastening element (27) on the sealing element and to a lower part of the pouring lip, said springs (25) being each connected at their lower ends to a rod (31) which is engaged and retained in a groove (33) in the front base of the pouring lip (7).

5,586,823

MAGNETIC STIRRING SYSTEM

Anthony H. Carr, Bedfordshire, Great Britain, assignor to Unipath Limited, Basingstoke, England

PCT No. PCT/GB93/01479, § 371 Date Mar. 9, 1995, § 102(e)

Date Mar. 9, 1995, PCT Pub. No. WO94/02238, PCT Pub.

Date Feb. 3, 1994

PCT Filed Jul. 14, 1993, Ser. No. 373,254


Claims priority, application United Kingdom, Feb. 17, 1993, 93301171

Int. Cl.⁶ B01F 1/308

U.S. Cl. 366—274

9 Claims

1. A magnetic stirrer comprising a bottle unit constituted by a closed culture bottle containing liquid and a gaseous headspace above the liquid, the bottle having a base and a stirrer bar of relatively low power magnetisation establishing opposite poles at opposite ends of the bar and extending parallel to the bottle base within the bottle, and a permanent magnet means of relatively high power providing spaced opposite poles in a plane parallel to the length of the stirrer bar located beneath the bottle base in close proximity thereto, and driving means for continuously rotating the permanent magnet means about an axis substantially normal to the



bottle base so that its rotating strong magnetic field aligns with that of the stirrer bar and entrains the stirrer bar in continuous rotation in a plane parallel to and above the bottle base within the liquid in the container, thereby to disturb the liquid surface in order to promote gas exchange with the bottle headspace.

5,586,824

METHOD OF MEASURING THE THERMAL CONDUCTIVITY OF MICROSCOPIC GRAPHITE FIBERS


John Barkyoumb, Beltsville; Lawrence T. Kabacoff, Columbia, and David J. Land, Silver Spring, all of Md., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jun. 14, 1994, Ser. No. 260,273

Int. Cl.⁶ G01N 25/18

U.S. Cl. 374—44

18 Claims



1. A method of determining the thermal conductivity of a fiber comprising the steps of:

- A. suspending a cylindrical sample fiber selected from the group consisting of metal fibers and graphite fibers in a working fluid having a high refractive index change with temperature;
- B. heating the sample fiber at a first point by means of a pump laser beam that is modulated at a frequency of less than 200 hertz;
- C. passing a weak continuous intensity probe laser beam through the working fluid close to a second point on the sample fiber so that a deflection of the probe beam occurs that is a measure of the amplitude and phase shift of a synchronous thermal wave passing through the second point as a result of the heating of the sample fiber by the modulated pump laser beam;
- D. converting the probe laser beam deflection into an electrical signal whose amplitude and phase shift correspond to the amplitude and phase shift of the synchronous thermal wave as it passes through the second point on the sample fiber;
- E. recording either the maximum or the RMS amplitude of the electrical signal and the corresponding distance between the first point and the second point on the sample fiber;

F. changing the distance between the first point and the second point on the sample fiber and repeating steps B through E and continuing this procedure until the amplitude of the electrical signal has been measured at a desired number of different distances between the first point and the second point on the sample fiber;

G. determining the straight line slope of a plot of the logarithm of the amplitude of the electrical signal versus the distance between the first point and the second point on the sample fiber;

H. using a mathematical model for the synchronous thermal wave produced in a theoretical uniform cylindrical fiber by a modulated pump laser beam heat source at a first point to calculate the maximum theoretical amplitude of the thermal wave for each of a series of second points along the theoretical uniform cylindrical fiber from inputs which include the modulation frequency of the real pump laser beam used to heat the sample fiber in step B, the actual density, specific heat, and diameter of the sample fiber, the distance of each second point from the first point, on the theoretical fiber, and an initial estimate of the thermal conductivity of the sample fiber which is to be determined;

I. finding the straight line slope of a plot of the logarithm of the maximum theoretical amplitude of the mathematical model thermal wave at each second point on the theoretical fiber versus the distance of the second point from the first point on the theoretical fiber;

J. comparing the straight line slope of the logarithm of the calculated maximum theoretical amplitude of the mathematical model thermal wave versus the distance between the first point and the second point on the theoretical fiber (step I) with the straight line slope of the logarithm of the amplitude of the electrical signal versus the distance between the first point and the second point on the sample fiber (step G) and then adjusting the value of the estimated thermal conductivity to bring the slopes closer together; and

K. repeating steps H through J until the straight line slope of the logarithm of the calculated maximum theoretical amplitude of the mathematical model thermal wave versus the distance between the first point and the second point on the theoretical fiber is the same as the straight line slope of the logarithm of the amplitude of the electrical signal versus the distance between the first point and the second point on the sample fiber, and the value of thermal conductivity last used is the correct one.

5,586,825

Patent Not Issued For This Number

5,586,826

ROLLER BEARING PROVIDED WITH ROLLER SKEW CONTROL AND LONG LIFE CHARACTERISTICS

Magnus Kellström, Partille; Joacim Fogelström, Billdal, both of Sweden, and Henning Wittmeyer, Hilversum, Netherlands, assignors to SKF Sverige AB, Gothenburg, Sweden


Filed Dec. 19, 1994, Ser. No. 358,314

Int. Cl.⁶ F16C 19/28


U.S. Cl. 384—450

8 Claims

1. A roller bearing having an axis and comprising an inner member having at least one inner raceway and an outer member having at least one outer raceway, said at least one inner raceway and said at least one outer raceway being spaced apart to define an annular space in which is located a row of rolling elements, said rolling elements being adapted to engage the at least one inner raceway and the at least one outer raceway at respective contact zones, each rolling element having an axis and being positioned at



5,586,828
PRINTER WITH PRINTING HAMMER
 Takashi Nakata, Aichi-ken, Japan, assignor to Brother Kogyo Kabushiki Kaisha, Nagoya, Japan
 Filed Dec. 27, 1994, Ser. No. 364,317
 Claims priority, application Japan, Dec. 28, 1993, 5-350872
 Int. Cl.⁶ B41J 23/34
 U.S. Cl. 400—185 20 Claims



a skew angle when the rolling element axis and the axis of the roller bearing are other than coplanar, said skew angle being positive when axial components of the friction forces acting on the rolling element and arising between the rolling element and either raceway in the respective contact zone are co-directional to an axial component of a normal force carried by the rolling element, and friction producing means for producing frictional coefficients at two spaced apart and separate first locations across a width of at least one of the outer raceway and the inner raceway which is different from a frictional coefficient at a second location disposed between the two first locations, said means for producing said first frictional coefficients at said two first locations being located at positions in which the friction forces acting on the rolling elements contribute to creation of a positive skew moment.

1. A print mechanism using a type wheel, having a plurality of type elements, the type wheel mounted on a carriage movement mechanism which moves a carriage in a first direction or a second direction opposite to the first direction along a platen, comprising: a pivotal mechanism having a pair of stopping portions, a first stopping portion and a second stopping portion, which are turned to a first position when the carriage is moved in the first direction and turned to a second position when the carriage is moved in the second direction by the carriage movement mechanism;

an operation mechanism comprising a rotating body which is rotated by a driving motor having a first supporting portion and a second supporting portion, a first cylindrical member which is engaged with a first supporting projection in the circumference, a second cylindrical member which is engaged with a second supporting portion with play being provided with a second stopping projection in the circumference, a first clutch mechanism which connects or disconnects the transmission of the rotating force from the rotating body disposed between the first supporting portion and the first cylindrical member, a second clutch mechanism which connects or disconnects the transmission of the rotating force from the rotating body being disposed between the second supporting portion and the second cylindrical member, a hammer cam member which is rotated following the rotation of the first cylindrical member, and a lift cam member which is rotated following the rotation of the second cylindrical member;

a printing hammer driving mechanism which strikes type elements on the type wheel with the printing hammer responsive to the rotation of the above-mentioned hammer cam member; a ribbon lift mechanism which shifts a correction ribbon up or down corresponding to the rotation of the lift cam member; a selecting mechanism comprising a first selecting member in which a first engagement portion is provided which can be selectively engaged with the first stopping portion of the above-mentioned pivotal mechanism and which has a first stopping claw to be engaged with the first stopping projection of the first cylindrical member and selects the printing hammer driving mechanism, and a second selecting member in which a second engagement portion is provided which can be selectively engaged with the second stopping portion of the pivotal mechanism and which has a second stopping claw to be engaged with the second stopping projection of the second cylindrical member and selects the ribbon lift mechanism; and a solenoid mechanism which releases the engagement of the first stopping claw with the first stopping projection of the first cylindrical member in a state where the first stopping portion of the above-mentioned pivotal mechanism is being engaged


5,586,827
BALL BEARING WITH CONTROLLED DYNAMIC IMBALANCE

Tetsuo Unno, Yoshio Shoda, and Tatsunohu Momono, all of Fujisawa, Japan, assignors to NSK Ltd., Tokyo, Japan
 Filed Jan. 5, 1996, Ser. No. 583,398

Claims priority, application Japan, Jan. 6, 1995, 7-000463
 Int. Cl.⁶ F16C 19/00

U.S. Cl. 384—450

1 Claim




1. A ball bearing comprising a first race ring having a first surface formed with a first race surface thereon, a second race ring having a second surface formed with a second race surface thereon, and a plurality of balls provided so as to be freely rotatable between the first race surface and the second race surface, each of the plurality of balls satisfying the numerical limitations that a ratio $\Delta I/I$ of a dynamic imbalance amount to a moment of inertia I , is less than $(3.1 \times 10^{-7}/(d_m \cdot N)^2) + 2.7 \times 10^{-5}$, when the ball bearing is used under conditions wherein a product $d_m \cdot N$ of a pitch circle diameter d_m mm of the plurality of balls, and a rotational speed N rpm of the second race ring relative to the first race ring is greater than 1,000,000 mm-rpm.

with the first engagement portion of the first selecting member and also releases the engagement of the second stopping claw with the second stopping projection of the second cylindrical member in a state where the second stopping portion of the pivotal mechanism is being engaged with the second engagement portion of the second selecting member.

5,586,829
SINGLE FOOTPRINT SAME FACE TRI-POCKET ARRAY
 David C. Schwartz, Southboro, Mass., assignor to Productive Environments, Inc., Framlingham, Mass.
 Filed Feb. 16, 1994, Ser. No. 197,500
 Int. Cl.⁶ B42F 21/02; 7/02

U.S. Cl. 402—79

13 Claims




1. A section of foldable material for forming a tri-pocket array, said section of material comprising at least an interconnected set of panels including a backing panel of predetermined height having perimeter features including adjoining first and second backing panel edges, a first pocket panel, a second pocket panel, and a third pocket panel, said interconnected set of pocket panels being attached off at least one of said first and said second of said adjoining first and second backing panel edges, each of said pocket panels having an entry lip edge of predetermined height, said pocket panels forming a first pocket, a second pocket, and a third pocket of a tri-pocket array, wherein a first pocket panel of said first, second, and third pocket panels is disposed along a first of said first and second adjoining backing panel edges, and a third pocket panel of said first, second, and third pocket panels is disposed along a second of said first and second adjoining backing panel edges, and where a second pocket panel of said first, second, and third pocket panels is disposed between said first pocket panel and said third pocket panel of said first second, and third pocket panels, and where each of said predetermined heights of said first, second, and third pocket panel entry lip edges is less than said predetermined height of said backing panel.

5,586,830
PIVOTING AND VARIABLE HEIGHT TABLE
 Ronald G. Wanek, James C. Dotta, both of Arcadia; Brian Konkelt, Mondovi, and Duane Herold, Arcadia, all of Wis., assignors to Ashley Furniture Industries, Inc., Arcadia, Wis.
 Filed Dec. 5, 1994, Ser. No. 349,533
 Int. Cl.⁶ F16B 7/10; F16D 1/00; B25G 3/18; A47B 9/00

U.S. Cl. 403—59 20 Claims

1. Device for allowing an object to be pivoted about a vertical axis and to be positioned at variable heights comprising, in combination: a vertical pillar having an elongated, vertically extending inner passage, with the inner passage including a plurality of vertically spaced, shoulder portions extending generally perpendicular to the vertical axis and having inner edges, with each of the shoulder portions being annular and centered and extending completely around the vertical axis; at least first and second fingers




located on opposite diametric sides of the vertical axis, with the object being operatively attached to the fingers; and means for moving the fingers between a first position and a second position, with the fingers in the first position being of a size for movement in the inner passage and past the inner edges of the shoulder portions without engagement and in the second position being of a size for abutting with one of the shoulder portions for preventing vertically downward movement of the fingers therebeyond and for allowing the fingers to move on one of the shoulder portions in a circular path centered on the vertical axis.

5,586,831
CONNECTOR FOR CONNECTING TWO PLATE-LIKE MEMBERS
 Kazuaki Tsubota, Hiroshima, and Takeshi Yamamoto, Hiroshima-ken, both of Japan, assignors to Delta Tooling Co., Ltd., and Delta Kogyo Co., Ltd., both of Hiroshima-ken, Japan

Filed Jun. 16, 1995, Ser. No. 491,578
 Claims priority, application Japan, Oct. 25, 1994, 6-260104
 Int. Cl.⁶ F16B 5/06; B65H 19/18; 69/06

U.S. Cl. 403—305

19 Claims



1. A connector for connecting two plate-like members, said connector comprising: a main body having two rectangular grooves defined therein, said two rectangular grooves having respective upper and lower walls and being open on opposite sides of said main body for receiving therein ends of two respective plate-like members, said main body also having a center wall continuous with said upper and lower walls and separating said two rectangular grooves from each other; and retaining means mounted on said main body for retaining the end of at least one of the two plate-like members within a

respective one of said rectangular grooves for subsequent simultaneous feed of the two plate-like members.

5,586,832

TWO PIECE INTERLOCKING SHAFT ATTACHMENT


Karl-Heinz Zylka, 1431 NE. 57th Ct., Fort Lauderdale, Fla. 33334

Filed May 22, 1995, Ser. No. 446,479

Int. Cl.⁶ B25G 3/00; F16H 1/00; F16H 55/12

U.S. Cl. 403—344

14 Claims



I. A two part encircling attachment for affixing to a rod or shaft, the attachment comprising:

- (A) a first part having an edge portion substantially defining a half cylinder having an axis, a particular diameter, and a first pair of interlocking edge elements substantially diametrically opposed to one another;
- (B) a second part having an edge portion substantially defining a half cylinder and a second pair of interlocking edge elements substantially diametrically opposed to one another;
- (C) each of said pair of interlocking edge elements of said first part being arranged to interdigitate and thereby interlock with one of said interlocking edge elements of said second part when said edge elements of said first and second parts are moved together axially to form a completely encircling cylindrical attachment which resists radial dismemberment;
- (D) a threaded passage extending radially through said first part intermediate the edge elements of said first part;
- (E) an elongate threaded fastener arranged to be threadedly received in and through said passage for locking said attachment against said rod or shaft after said parts have been moved together to thereby prevent axial motion of said attachment on said rod or shaft;
- (F) a radially extending aperture at one of said second pair of edge elements and adapted for aligning with said passage in said first part to receive said fastener passing through said passage prior to said fastener engaging said rod or shaft to thereby prevent relative axial movement between said parts.

5,586,833

ARTICULATED FITTING FOR SEATS WITH ADJUSTABLE BACKREST, IN PARTICULAR MOTOR VEHICLE SEATS

Gregor Vossman, Vreden, and Dirk Angermann, Cologne, both of Germany, assignors to Keiper Recaro GmbH & Co., Remscheid, Germany

Filed Nov. 10, 1994, Ser. No. 337,681


Claims priority, application Germany, Nov. 30, 1993, 43 40 696.3

Int. Cl.⁶ B25G 3/28; B60N 2/02; F16H 1/32; F16B 3/00

U.S. Cl. 403—359

10 Claims

I. In an articulated fitting for seats having an adjustable backrest, in particular motor vehicle seats, in which a stationary articulated part associated with the seat part and a swivelable articulated part associated with the backrest are connected with one another via a swivel axle, having an adjusting and fixing device which determines the position of both articulated parts relative to one



another and is constructed as a gear unit, the swivel axle of each articulated fitting having a central recess or receptacle serving to connect with a transmission rod so as to be fixed with respect to rotation relative thereto, which transmission rod couples the two articulated fittings of a seat with one another, the improvement comprising:

that the transmission rod and the recess of the swivel axle, which recess receives the transmission rod so as to be fixed with respect to rotation relative thereto, have a profile cross section in the shape of a toothed circumference, where said teeth are evenly spaced about said circumference and said circumference has a missing tooth which defines a double space between two adjacent teeth at a location on the circumference, this location on the circumference being reduced to a core cross section of said transmission rod so that the transmission rod may be inserted into the recess of the swivel axle after a complete revolution of 360 degrees.

5,586,834

JOINT STRUCTURE FOR COUPLING PRECAST CONCRETE PAVEMENT SLABS

Tomoyuki Tsuji, Otaru, Japan, assignor to Otaru Development and Construction Department of Hokkaido Development Bureau, Japan


Filed Oct. 11, 1994, Ser. No. 320,926

Claims priority, application Japan, Apr. 8, 1994, 6-071092

Int. Cl.⁶ E01C 11/14

9 Claims

U.S. Cl. 404—60



I. A joint structure for coupling adjacent precast concrete pavement slabs comprising:

- a first horizontal hole defined through a first outer end surface of a first precast concrete pavement slab;
- a second horizontal hole defined through a second outer end surface of a second precast concrete pavement slab, said second horizontal hole being opposite to the first horizontal hole and having an inner end surface;
- a reinforcing bar having a distal end, said reinforcing bar accommodated into the first horizontal hole and then inserted into the second horizontal hole, said distal end formed semispherical;
- the second precast concrete slab having an upper surface and a straightened guide passage defined therethrough which guide passage is provided to allow said inner end surface of the second horizontal hole to communicate with said upper surface, and said guide passage having a vinyl hose inserted therethrough;

a flexible hauling member connected to the distal end of the reinforcing bar, said flexible hauling member being insertable into the guide passage; wherein said first and second horizontal holes are provided by securely embedding sheathing members made of steel pipes in the first and second outer end surfaces of the first and second precast concrete pavement slabs respectively, said sheathing members being cylinder-shaped, having the same diameters.

5,586,835

SHORE EROSION CONTROL STRUCTURES


Samuel S. Fair, 599 Linwood Beach Rd., Linwood, Mich. 48634

Filed Feb. 23, 1995, Ser. No. 393,179

Int. Cl.⁶ E02B 3/04

U.S. Cl. 405—30

26 Claims



17. A block member for use in constructing a shore erosion control wall along a shoreline, said block member comprising a top panel and a bottom panel connected by spaced apart uprights to form at least one opening defined by said panels and said uprights; and a plurality of spaced apart baffles removably accommodated in said opening and supported by said bottom panel and forming a plurality of passages extending transversely through said block member and substantially parallel to said uprights.

5,586,836

BOOTSTRAPPING PROCESS OPTIMIZATION FOR TWO PHASE VACUUM EXTRACTION SYSTEMS


Steven R. Morrow, Hatboro, Pa., assignor to BCM Engineers, Inc., Plymouth Meeting, Pa.

Filed May 11, 1994, Ser. No. 241,127

Int. Cl.⁶ E03B 3/12; E21B 43/00

U.S. Cl. 405—128

25 Claims



I. A system for receiving a two phase stream of liquids and gases drawn by a vacuum extraction system comprising:

- a knock out pot for separating the liquids and gases;
 - a vacuum line connecting the knock out pot to a vacuum pump; and
 - a knock out pot pump connected to the knockout pot for removing liquid from the knockout pot,
- whereby a quantity of cooling liquid is supplied by liquid collected in the knockout pot.

5,586,837

RAINGUTTER LEAF GUARD AND CLEANING DEVICE


Steven D. Udelle, 13 Seasons Dr., Punta Gorda, Fla. 33983

Filed Jul. 10, 1995, Ser. No. 499,821

Int. Cl.⁶ E02B 5/08; 9/04; 5/00; E04D 13/076; 13/00

U.S. Cl. 405—119

10 Claims



I. A raingutter leafguard and cleaning device comprising: a movably attached elongated sheet member of predetermined length and width mounted on the topside of a raingutter, and said elongated sheet member having an integral grid means exhibiting a plurality of openings throughout said sheet member capable of passing a liquid therethrough said grid means, while preventing leaves and debris from entering said raingutter through said grid means, and said sheet member having a first longitudinal edge and a second longitudinal edge, said first longitudinal edge comprising a first integral hinge means portion movably attached to a second hinge means portion, said second hinge means portion affixed to a top front surface of said raingutter, and said second longitudinal edge of said sheet member resting on raingutter hangers, and a lever means affixed to said sheet member, for providing an arcuate movement to said sheet member at movable said first hinge means portion, said lever means having an opening guide at its uppermost portion for securing a hook means, and said hook means affixed to a pole means having sufficient length, whereby said hook means is mated through an opening within said opening guide of said lever means, thereby causing lifting and pivoting of movable said sheet member when said pole means is pulled in a downward direction, thus dumping or releasing said leaves and debris adhering to said sheet member to the ground, and said hook means affixed to said pole means for mating to said opening guide being operable by a human at ground level.

5,586,838

SEALED MARINE POST

Thomas M. Walsh, 53 LaFayette Ave., Suffern, N.Y. 10901


Filed May 30, 1995, Ser. No. 453,399

Int. Cl.⁶ E02D 5/60; E04H 12/00; B65H 81/00; B32B 31/00


U.S. Cl. 405—216

3 Claims

I. A sealed marine post comprising:



5,586,839
YIELDABLE CABLE BOLT
Harvey D. Gillespie, 4848 S. 2200 West, Salt Lake City, Utah 84118
Filed Sep. 6, 1994, Ser. No. 301,056
Int. Cl.⁶ E21D 20/02
U.S. Cl. 405—259.1 27 Claims




- an elongated central post member having a longitudinal axis directed therethrough;
- a first mesh layer wrapped about the central post member and including a plurality of orthogonally oriented fibers which extend parallel and orthogonal relative to the longitudinal axis of said central post member;
- a first matrix resin layer impregnated within said first mesh layer and bonded with said central post member;
- a second mesh layer wrapped about said central post member on top of said first matrix resin layer, said second mesh layer including orthogonally oriented fibers which extend at an oblique angle relative to the longitudinal axis of said central post member;
- a second matrix resin layer impregnated within said second mesh layer and bonded with said first matrix resin layer;
- a first upper mesh panel extending substantially orthogonally across an upper end of the central post member in a plane substantially parallel to said upper end, said first upper mesh panel being impregnated with said first matrix resin layer so as to seal said upper end of said central post member;
- a second upper mesh panel extending across the upper end of said central post member on top of said first upper mesh panel and being impregnated with said second matrix resin layer, said first upper mesh panel including orthogonally oriented fibers and said second upper mesh panel including orthogonally oriented fibers positioned at an oblique angle to the fibers of said first upper mesh panel;
- a first lower mesh panel extending substantially orthogonally across a lower end of said central post member and being impregnated with the first matrix resin layer so as to seal the lower end of said central post member;
- a second lower mesh panel extending across the lower end of said central post member on top of the first lower mesh panel, said second lower mesh panel being impregnated with the second matrix resin layer, said lower mesh panels each including orthogonally oriented fibers, said fibers of said second lower mesh panel being positioned at an oblique angle relative to the fibers of said first lower mesh panel;
- and,
- a mounting means secured to a top end of the central post member for coupling the sealed central post to a structure, said mounting means comprising a cylindrical receiver circumferentially positioned about and adhesively secured to the upper end of said central post member over said mesh layers and a mounting plate extending orthogonally across an upper end of said cylindrical receiver;
- said mounting means further comprising a first mounting flange projecting substantially orthogonally from the mounting plate, and a second mounting flange projecting substantially orthogonally from the mounting plate, the mounting flanges being orthogonally oriented relative to one another so as to define a corner coupling which can be positioned at a juncture of two intersecting joists of a structure.

26. A yieldable cable bolt comprising:
- a length of multi-strand cable comprising a center wire and a plurality of peripheral wires spirally wrapped around the center wire;
- means defining an enlarged cable section of the cable;
- an outer sleeve having an inside diameter slightly less than the outside diameter of the enlarged cable section, the cable being inserted through the outer sleeve, and the enlarged cable section being pressed into one end of the outer sleeve; and
- a plurality of anchor sleeves swaged onto the cable.
27. A cable bolt comprising:
- a length of multi-strand cable comprising a center wire and a plurality of peripheral wires spirally wrapped around the center wire;
- an enlarged cable section of the cable comprising a center wire sleeve positioned around the cable center wire and between the cable center wire and peripheral wires; and
- an outer sleeve positioned on the enlarged cable section to resist movement of the cable through the outer sleeve.


5,586,840
APPARATUS FOR DIGGING SOIL FOUNDATION AND METHOD FOR CONSTRUCTING UNDERGROUND WALL BY USING THE APPARATUS
Tadashi Nishio, and Shuichi Fukuda, both of Tokyo, Japan, assignors to Concrete Coring Company, Tokyo, Japan
PCT No. PCT/JP94/02006, § 371 Date Jul. 28, 1995, § 102(e) Date Jul. 28, 1995, PCT Pub. No. WO95/15419, PCT Pub. Date Jun. 8, 1995
PCT Filed Nov. 30, 1994, Ser. No. 501,101
Claims priority, application Japan, Nov. 30, 1993, 5-229242; Dec. 28, 1993, 5-335181
Int. Cl.⁶ E02D 3/12; 5/18
U.S. Cl. 405—267 12 Claims

1. A digging apparatus comprising:
- a cylindrical digging bit;
- a plate digging bit extending radially outward from said cylindrical digging bit;
- a rotary driving means for rotating said cylindrical digging bit;
- a percussion means for applying percussion force to said cylindrical digging bit;
- movement converting means positioned between said cylindrical digging bit and said plate digging bit and for converting rotary movement of said cylindrical digging bit into reciprocating movement of said plate digging bit;



percussion transfer means positioned between said cylindrical digging bit and said plate digging bit and for transferring said percussion force from said cylindrical digging bit to said plate digging bit.

5,586,841
DUAL PURPOSE MODULAR BLOCK FOR CONSTRUCTION OF RETAINING WALLS
Peter L. Anderson, North Reading, Mass.; Michael J. Cowell, Leesburg, and Dan J. Hotek, Chantilly, both of Va., assignors to Societe Civile des Brevets Henri Vidal, France
Continuation-in-part of Ser. No. 137,585, Oct. 15, 1993, Pat. No. 5,474,405, and a continuation-in-part of Ser. No. 108,933, Aug. 18, 1993, Pat. No. 5,487,623, which is a continuation-in-part of Ser. No. 40,904, Mar. 31, 1993, Pat. No. 5,507,599.
This application Feb. 3, 1995, Ser. No. 382,985
Int. Cl.⁶ E02D 29/02
U.S. Cl. 405—286 30 Claims




1. An improved retaining wall construction comprising, in combination:
- a plurality of facing block members arrayed in overlapping courses one upon the other, each block member having a generally planar front face, a back face, opposite side faces connecting the front face to the back face, and generally parallel top and bottom surfaces;
- each block member also including at least two generally parallel rod receiving throughbores extending from the top surface through the bottom surface, each throughbore including a counterbore in one of the parallel top and bottom surfaces, surrounding the throughbore and extending from adjacent the front face through the back face to define a channel with side walls in the block, and a cross throughbore connecting the parallel counterbores;

a stabilizing element comprising a pair of tension arms in the parallel counterbores of selected block members, each pair of said tension arms of each stabilizing element being generally parallel;

the stabilizing elements including soil engaging means extending therefrom projecting away from the back face of each block into compacted soil; and

compacted soil adjacent the back face engaging the stabilizing elements.

5,586,842
FILE GRINDER
Tae H. Bae; Sang Y. Bae, and Sang I. Bae, all of 6898 Old Annapolis Rd., Linthicum, Md. 21090
Filed May 3, 1994, Ser. No. 237,209
Int. Cl.⁶ B23D 71/00; 21/04; 71/08
U.S. Cl. 407—29.14 1 Claim



1. An abrasive tool comprising:
- a plurality of straight elongated blades, each of said elongated blades having a substantially flat upper edge, an opposed lower edge having a plurality of spaced-apart teeth located thereon, a predetermined thickness, and a median line defined by a line extending along said elongated blades at a position halfway between said upper edge and said lower edge;
- a plurality of spacer links interconnecting respective sides of said plurality of elongated blades together in spaced-apart relation, said spacer links being entirely located between said upper edge and said median line, a thickness of said spacer links being approximately equal to said predetermined thickness of said elongated blades, said elongated blades and said spacer links forming a composite structure having a predetermined length and opposed end portions, with outermost elongated blades of said composite structure defining a maximum overall width of said composite structure, said elongated blades being spaced-apart and substantially parallel to one another along substantially their entire length to form a longitudinal passage between each of said elongated blades, each said longitudinal passage having a passage depth extending from said lower edge of said elongated blades to a depth beyond said median line, each said longitudinal passage of said passage depth extending along substantially the entire length of said composite structure, each said longitudinal passage between said elongated blades decreasing in both width and height at each of said opposed end portions to form a tapered end portion of said composite structure, each longitudinal passage including a plurality of longitudinal openings adjacent said upper edges of said plurality of elongated blades for allowing grinding dust to pass therethrough;

an elongated substantially cylindrical handle, said handle including an elongated rod located coaxially therein and extending longitudinally therefrom; and fastening means for fastening said rod to said composite structure, said fastening means including a threaded member extending from said upper edges of said elongated blades and located approximately centrally along the length of said composite structure, an aperture located at a distal end of said rod for loosely receiving said threaded member therein, and a nut threadably attached to said threaded member, said fastening means allowing said composite structure to pivot relative to said handle such that a longitudinal axis of said composite structure may assume any angular orientation within 360° with respect to a longitudinal axis of said handle.

thereof, with cutting edges in operable relationship thereto and in substantially parallel relationship with the leading edge of said tooth.

5,586,844

TOOLHOLDER CLAMPING WEDGE WITH INSERT ENGAGING PROTRUSIONS


Folke Nyman, Sandviken, Sweden, assignor to Sandvik AB, Sandviken, Sweden

Filed Feb. 24, 1995, Ser. No. 393,685

Claims priority, application Sweden, Mar. 4, 1994, 9400742
Int. Cl. B23B 27/16; 29/04


U.S. Cl. 407—105

11 Claims



1. A toolholder for holding a cutting insert having top and bottom faces, a center through-hole, and an edge face, said toolholder comprising:

- a holder body having a top surface, a forward portion of said top surface defining an insert site for receiving an insert, the top surface including a generally upstanding supporting surface spaced rearwardly from said insert site, said supporting surface being inclined downwardly and forwardly;
- a pin disposed in said body and having an upper end projecting upwardly at said insert site for entering a center through-hole of an insert to locate the insert;
- a clamping wedge mounted on said body for up and down movement relative thereto, said clamping wedge including a rear end for engaging said supporting surface, a front end for engaging an insert mounted at said insert site, and a fastener hole extending downwardly through said clamping wedge, said front end including:
 - a pair of forwardly projecting upper protrusions disposed on opposite sides of an imaginary plane containing a center axis of said pin and a center axis of said fastener hole, said upper protrusions arranged to bear downwardly against the top face of the insert;
 - a concave surface interconnecting said upper protrusions, said concave surface arranged coaxially with respect to said pin and having a radius of curvature no shorter than a radius of said pin; and
 - a pair of forwardly projecting lower protrusions disposed on opposite sides of said imaginary plane, said lower protrusions arranged to bear forwardly against the edge face of the insert; and
- a fastener comprising a clamp screw projecting through said fastener hole and threadably secured in said body for bearing downwardly on said clamping wedge to push said upper protrusions downwardly against the top face of the insert while pushing said rear end downwardly against said supporting surface to cause said lower protrusions to be pushed forwardly against the edge face of the insert.



10. A rotary cutting tool comprising a cutting portion having a longitudinal axis and a plurality of helically arranged teeth separated by helical gullets extending the length of said cutting portion, the leading edge of each tooth comprising a plurality of sockets and cutting inserts disposed in said sockets, each cutting insert comprising a six sided block having a longitudinal axis and two major parallel rhomboid-shaped plane surfaces constituting a seating face and a clearance face respectively, two opposed minor side surfaces constituting cutting faces extending parallel to said longitudinal axis and extending between said seating and clearance faces, each said cutting face forming an acute angle with said clearance face and forming a cutting edge along the intersection thereof, and two minor parallel plane faces extending between seating and clearance faces and said two cutting faces, each said cutting face having a concave curvature centrally of its major dimension, and convex curvature at each end of its major dimension to define a serpentine cutting face and cutting edge; said sockets being of complementary shape to said cutting inserts and so disposed along each tooth that said cutting inserts are arranged along the leading edge of each tooth substantially the length

5,586,845


FACE MILLING CUTTING INSERT HAVING CONVEX RAKES WITH OBTUSELY INTERSECTING FLAT SURFACES

Tatsuo Arai, and Takayoshi Salto, both of Ibaragi-ken, Japan, assignors to Mitsubishi Materials Corporation, Tokyo, Japan
Filed Dec. 28, 1994, Ser. No. 365,547

Claims priority, application Japan, Dec. 28, 1993, 5-350015
Int. Cl. B23C 5/06; 5/22

U.S. Cl. 407—113

2 Claims



1. A cutting insert comprising:

- an insert body having a parallelogrammatic plate shape;
- a plurality of cutting edges formed in a peripheral direction along peripheries of upper and lower surfaces of said insert body on a pair of opposite ridge portions of the upper surface of said insert body and a pair of opposite ridge portions of the lower surface of said insert body in a staggered position relative to the pair of upper surface ridge portions; and
- a first and second pair of rakes extending from said cutting edges, said rakes being formed in side surfaces of said insert body connecting to said cutting edges, each of said rakes being inclined with respect to the upper and lower surface; wherein each of said rakes has a convex curved surface portion which is formed along one side of the corresponding side surface connecting to said cutting edge and which is curved along said peripheral direction so as to round out in an outward direction from said insert body, and a flat surface portion which obtusely intersects said convex curved surface portion and which connects to the ridge portion of the side surface opposite said cutting edge.


5,586,846

PORTABLE DOWEL BORING TOOL

Joseph J. Johns, 11384 Jeb Stuart La., Culpeper, Va. 22701
Continuation-in-part of Ser. No. 442,158, May 16, 1995, abandoned. This application Mar. 4, 1996, Ser. No. 610,697
Int. Cl. B23B 45/14

U.S. Cl. 408—72 R

16 Claims



1. A dowel-hole boring device for boring dowel receiving holes at a predetermined angle and depth having:

- a body, said body having a first end and a second end;

- a first interior channel, said first interior channel being open to said first end;
- a second interior channel, said second interior channel being open to said second end and contiguous to said first interior channel;
- a pair of bearings, said pair of bearings having an interior diameter and an exterior diameter, said exterior diameter being dimensioned to fit within said first interior channel;
- a shaft, said shaft being dimensioned to fit within the interior diameter of said pair of bearings to prevent relative rotation between said shaft and inner races of said bearings, having a drill bit receiving means at one end and a receiving groove;
- a spring, said spring separating said pair of bearings a predetermined distance from one another.

5,586,847

POWER TOOL ADAPTER


Charles J. Mattern, Jr., 309 Bank Ave. No. A2, and Lawrence G. Tatum, Taylors La. Farm, both of Riverton, N.J. 08077

Filed Jun. 6, 1995, Ser. No. 466,838

Int. Cl. B23B 51/12; 31/22

U.S. Cl. 408—239 A

19 Claims



1. A power tool adapter for being quickly connected and disconnected to a first power driven rotary drive bit, the first drive bit having an outer periphery, said power tool adapter comprising:

- a. an inner sleeve having a first end and a second end, said first end including an opening for accessing a cavity within said inner sleeve, said sleeve including at least one radially extending opening, said cavity being sized to complementarily receive at least a portion of the first drive bit, said first drive bit including a keyed portion which is rotatably fixed to a complementarily shaped portion of said inner sleeve, said second end of said inner sleeve having a second rotary cutting bit secured thereto;
- b. a locking mechanism operatively engaged with said inner sleeve; and
- c. an outer sleeve having a cavity slidably receiving at least a portion of said inner sleeve therein, said outer sleeve being movable from a first position, wherein said outer sleeve maintains the locking mechanism in engagement with the first drive bit to lock the first drive bit to said inner sleeve, in a first direction to a second position wherein the locking mechanism is disengaged from the first drive bit to permit the first drive bit to be removed from the cavity of the inner sleeve, and from the first position in a second direction to a third position wherein the locking mechanism is removable from the cavity of the inner sleeve to permit the first drive bit to be installed into the cavity of the inner sleeve, said outer sleeve being biased toward said first position.

5,586,848

MACHINE TOOL CHIP REMOVAL SYSTEM

Paul W. Suwijn, Pittsford, N.Y., assignor to The Gleason Works, Rochester, N.Y.


Filed May 2, 1995, Ser. No. 433,277

Int. Cl. B65G 47/46; B23C 1/00; B23F 23/00

U.S. Cl. 409—137

26 Claims

1. An apparatus for performing wet or dry machining processes, said apparatus comprising a machine base having top and bottom surfaces and a plurality of side surfaces, said apparatus further



comprising a tool support located on said base top surface and a workpiece support located on said base top surface, said apparatus including means to move said tool and workpiece supports relative to one another to engage a tool and workpiece in a manner to machine said workpiece, said apparatus comprising means to remove metal chips resulting from said wet or dry machining processes from said apparatus via respective independent wet and dry chip outlets, the chip removal means comprising:

- a first passageway located in said machine base, said first passageway extending between an outlet in two of said plurality of side surfaces;
- a second passageway located in said machine base, said second passageway extending from said top surface to said first passageway and communicating therewith, said second passageway providing a means of passage to said first passageway for metal chips resulting from said machining processes;
- transfer means located in and extending the length of said first passageway, said transfer means being reversible in direction in order to convey metal chips from said machining processes and received via said second passageway to said outlet in either of said two side surfaces, thereby enabling metal chips from wet machining processes to be conveyed to and discharged from an outlet in one side surface and metal chips from dry machining processes to be conveyed to and discharged from an outlet in another side surface.

5,586,849

WHEEL RESTRAINT DEVICE AND QUICK-CONNECT HOOKS FOR USE THEREWITH

James L. Kissel; Earl J. Dalley, and Daniel F. Dolan, all of Rapid City, S. Dak., assignors to Rushmore Vehicle Restraints, L.L.C., Rapid City, S. Dak.


Continuation-in-part of Ser. No. 291,779, Aug. 17, 1994, abandoned, which is a continuation-in-part of Ser. No. 202,342, Feb. 28, 1994, abandoned. This application Jan. 27, 1995, Ser. No. 379,731

Int. Cl.⁶ B60P 3/06

U.S. Cl. 410—10

22 Claims

1. A device for restraining a wheel on a vehicle to a support surface on which the wheel is supported, the device comprising:
 - (a) a restraining member, comprising:
 - (i) an upper restraint supported on an upper outer surface of the wheel;
 - (ii) inner and outer flexible members coupled to and extending from the upper restraint on inner and outer sides of the wheel, respectively; and
 - (iii) a lower restraint including a flexible member coupled to the inner and outer flexible members and abutting a lower outer surface of the wheel; and
 - (b) inner and outer securing means for respectively securing the inner and outer flexible members to the support surface.



5,586,850

TRUCK BED CARGO DIVIDER



James H. Johnson, Rte. 1, Box 276-1, Ore City, Tex. 75683

Filed Sep. 11, 1995, Ser. No. 524,946

Int. Cl.⁶ B60P 7/14

U.S. Cl. 410—138

2 Claims



1. A truck bed cargo divider for a pickup truck comprising:
 - a cargo bed in the pickup truck;
 - a floor in the cargo bed;
 - wheel wells extending into a cargo area defined by the cargo bed;
 - a panel having a size and dimension approximately equal in size to a dimension of a plane transverse to a longitudinal axis of the cargo bed;
 - at least two spaced apart sidewalls in the cargo bed;
 - a first track means for supporting the panel affixed to the side walls of the truck bed;
 - wheel assembly means attached to the panel and adapted to ride on the track means for allowing translational movement to the panel;
 - a recess area in the panel on opposed sides for clearance between the panel and each wheel well;
 - door means attached by hinges to the panel proximate each recess area for closing the recess area;
 - a second track means affixed to the floor of the truck bed and extending the length of the floor parallel with the longitudinal axis;

5,586,852

SPRING-LOADED PRESS PIN

Bernhard Ganter, Furtwangen, Germany, assignor to Otto Ganter & Co. KG, Furtwangen, Germany

Filed Nov. 30, 1994, Ser. No. 352,061

Claims priority, application Germany, Dec. 28, 1993, 9319799 U; Dec. 28, 1993, 9319800 U

Int. Cl.⁶ F16B 21/18

U.S. Cl. 411—353

8 Claims

lock means mounted in the panel, proximate each track means for controlling movement of the panel along the track means within the truck bed cargo area;

the first track means includes a continuous series of slots facing each side edge of the panel;

the second track means includes a continuous series of slots facing a bottom edge of the panel;

the lock means includes a horizontal sliding bolt mounted within the panel on each side for engagement with the slots in the first track means;

the lock means includes a vertical sliding bolt mounted within the panel on each side for engagement with the slots in the second track means;


the horizontal sliding bolt includes an operating handle extending from a top edge of the panel;

the horizontal sliding bolt and the vertical sliding bolt are interconnected;

a connecting rod for connecting the horizontal sliding bolt and the vertical sliding bolt;

the connecting rod biases the horizontal sliding bolt in a locked position; and

a recess in the top edge of the panel, on each side, for securing the sliding bolt handle in an unlocked position, whereby movement of the horizontal sliding bolt from a said track slot of the first track means and rotation of the handle will cause the connecting rod to withdraw the vertical sliding bolt and thereby allow the panel to move freely on the first track means.



5,586,851

PRESTRESS-MONITORING ELEMENT FOR SCREW-TYPE ANCHORS

Manfred Haage, Dornstetten, Germany, assignor to Fischerwerke, Artur Fischer GmbH & Co KG, Waldachtal, Germany


Filed May 19, 1995, Ser. No. 445,998

Claims priority, application Germany, Jun. 23, 1994, 44 21 959.8

Int. Cl.⁶ F16B 31/02; G01L 5/00

U.S. Cl. 411—10

4 Claims



1. A prestress-monitoring element for a screw-type anchor to be arranged on an anchoring rod of the screw-type anchor between an article to be fixed to a wall and the screw element of the screw-type anchor, the prestress-monitoring element comprising a dimensionally stable pressure ring and an expansible expansion ring having contact surfaces therebetween, said contact surfaces between said rings including at least one contact surface which is formed as a conical annular surface, said rings being formed so that under the action of a clamping force generated by the screw-type element toward the prestress-monitoring element, by way of bearing surfaces, a radial force component expands said expansion ring, and in an end position of the screw-type element when a maximum relative axial displacement between said pressure ring and said expansion ring has been achieved, the screw-type element abuts against both rings, said expansion ring having an end face provided with a circumferential groove, said pressure ring having a trapezoidal cross-section and engaging in said circumferential groove so that said expansion ring expands radially outward into said groove as said pressure ring presses in.

5,586,853

FASTENER CAGE FOR A PANEL

Charles A. Poe, Athens, Tenn., assignor to Davidson Textron Inc., Dover, N.H.


Filed Mar. 16, 1995, Ser. No. 405,367

Int. Cl.⁶ F16B 19/00

U.S. Cl. 411—372

9 Claims

1. A molded plastic fastener cage for securing a fastener in an aperture formed in a rigid panel structure having opposed inner and outer side surfaces, said cage comprising:
 - a molded plastic collar having a central opening extending through said collar between opposite axial ends thereof and registerable with the aperture in the panel structure, a first annular shoulder surrounding said opening at one of said axial ends of said collar and engagable with the outer side of the panel structure about the aperture, and a second annular shoulder surrounding said opening at the other of said axial ends of said collar facing away and spaced axially from said first shoulder so as to be exposed on the exterior side of the panel structure for engagement by an assembly end of the fastener to transmit compressive pushing loads applied to the fastener during installation of the panel structure through said



collar to the outer side surface of the panel structure lying beneath said first annular shoulder;

a molded plastic retainer formed separately from said collar having a sleeve portion extending between opposite inner and outer axial ends of said retainer and defining a central axial opening of said retainer extending between said ends thereof, said outer end of said sleeve portion being dimensioned for extension through the aperture of the panel structure and into said opening of said collar, said retainer and said collar including snap together connecting structure mutually engageable with one another upon the extension of said sleeve portion into said collar to secure said retainer attached to said collar, said retainer including an annular formation at said outer axial end of said sleeve portion defining first an second annular shoulders extending radially inwardly of said collar in axially spaced oppositely facing relation to one another for capturing an assembly end of the fastener, said retainer including an annular flange at said inner axial end of said sleeve portion defining a third annular shoulder extending radially outwardly of said sleeve portion disposed in axially spaced facing relation to said first shoulder of said collar for engaging the inner side surface of the panel structure thereby to mount said cage within the aperture of the panel structure, said third annular shoulder cooperating with one of said first and second shoulders of said retainer to transmit extensive pulling loads applied to the fastener during dismounting of the panel structure through said retainer and to the inner surface of the panel structure lying beneath said third shoulder of said retainer; and

a foam-imperious cover member adhered to said axially inner end of said retainer and extending across said opening of said retainer sealing off said retainer opening to prevent the entry of foam material into said retainer opening during formation of a plastic foam layer against the inner side of the panel structure.

5,586,854

CONNECTOR FASTENING NUT AND BOLT-NUT FASTENED CONNECTOR

Hiroshi Sakai, and Kazuo Ohtaka, both of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan
Filed Aug. 17, 1995, Ser. No. 516,407


Claims priority, application Japan, Aug. 19, 1994, 6-195226
Int. Cl.⁶ F16B 37/14:39/34

U.S. Cl. 411—429

6 Claims

1. A connector fastening nut for a bolt-nut fastened connector, comprising:

a nut member fixed to a first connector housing and having a female threaded portion engaged with a male threaded portion of a fastening bolt fitted to a second connector housing; and



an elastic portion integral with said nut member, for urging an end of the fastening bolt in an engagement direction between the female threaded portion of said nut member and the male threaded portion of the fastening bolt, when the male threaded portion has been passed through the female threaded portion after full engagement of the two connector housings by fastening the fastening bolt to the fastening nut, wherein said nut member is a box-shaped nut; and said elastic portion is in a side wall portion of the box-shaped nut integral with the female threaded portion of said nut member.

5,586,855


APPARATUS AND METHOD FOR INFEEEDING BATCHED MATERIALS

Roger D. Eshleman, 506 Clayton Ave., Waynesboro, Pa. 17268
Filed Nov. 23, 1993, Ser. No. 157,359

Int. Cl.⁶ F23G 5/00

U.S. Cl. 414—160

44 Claims



1. An apparatus for infeeding batched material to an inlet opening of a material processing apparatus, said batched material infeeding apparatus comprising:

(a) a lift mechanism disposed alongside a material processing apparatus and being operable to lift a batched material at least to the elevation of an inlet opening of the material processing apparatus;

(b) a delivery conveyor disposed alongside the material processing apparatus and adjacent to said lift mechanism and being operable to deliver the batched material to said lift mechanism; and

(c) a transfer enclosure spaced from said lift mechanism and disposed above the inlet opening of the material processing apparatus, said transfer enclosure having an entrance for receiving batched material from said lift mechanism and an exit for subsequent discharge of the batched material from said transfer enclosure into the material processing apparatus through the inlet opening thereof;

(d) said lift mechanism including

(i) a transfer deck for supporting the batched material, and
(ii) a drive assembly supporting said deck and being operable to have said deck between a lowered loading position and a raised unloading position,


(iii) said transfer deck including movable means operable to undergo movement in a transverse direction relative to the

direction of the movement of said deck between said raised and lower positions for aligning the batched material supported by said deck with said entrance of said transfer enclosure when said deck is at said raised unloading position of said lift mechanism;

(e) said delivery conveyor including

(i) an end portion disposed adjacent to said lowered loading position of said deck of said lift mechanism, and

(ii) a main portion extending away from said lift mechanism to provide space for loading the batched material on said delivery conveyor, said delivery conveyor being operable to deposit the batched material at the location of said movable means on said deck of said lift mechanism each time said deck is disposed at said lowered loading position.



5,586,856

LIFT APPARATUS


William O. Sprigler, 709 37th Ave. North, Fargo, N. Dak. 58102

Filed Apr. 19, 1995, Ser. No. 424,860

Int. Cl.⁶ B60P 9/00

U.S. Cl. 414—462

23 Claims



1. An apparatus for raising and supporting an article above a vehicle, comprising:

a wheel assembly including a set of wheels, mounting to a rear of the vehicle;

a platform for supporting the article including supplementary wheels retractably mounted at the rear of the platform;

a lift frame mounting on the wheel assembly;

arms rotatably mounted to the lift frame proximate the wheel assembly, connecting to and supporting the platform at an extended end thereof, wherein the arms rotate between a lowered position and a raised position; and

a cross member mounted above the wheel assembly engaging the platform upon actuation of the apparatus from the lowered to the raised position and supporting the platform in the raised position, wherein the article is supported above the platform in the lowered and raised positions.

5,586,857

ROTATING STALL PREVENTION SYSTEM FOR COMPRESSOR

Hiroshi Ishii, Chiyoda-machi; Tetsuo Sasada, Hitachi; Masayuki Kasahara, Chiyoda-machi; Yasuhiro Katoh, Hitachi, and Yasuhide Kashiwabara, Katsuta, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Continuation of Ser. No. 145,592, Nov. 4, 1993, abandoned.

This application Jun. 30, 1995, Ser. No. 497,417

Claims priority, application Japan, Nov. 11, 1992, 4-300803
Int. Cl.⁶ F01D 17/00

U.S. Cl. 415—23

9 Claims

1. A rotating stall preventing system of a compressor, which has rows of compressing blades including rotor blades and stator blades in a flow passage of the compressor and means for performing flow control corresponding to the rotating speed of said compressor, said rotating stall prevention system comprising: baffle

vanes separate from said means for performing flow control of said compressor, said baffle vanes being rotatably mounted in said flow passage upstream of said compressing blade rows so that their angles can be varied, actuators coupled to said baffle vanes to rotate said baffle vanes to vary their angles, flow sensors to detect flow condition in said flow passage of the compressor, and control means responsive to signals from said flow sensors for outputting control signals to said actuators for varying the angles of said baffle vanes so as to prevent occurrence of rotating stall phenomena.

5,586,858

REGENERATIVE FUEL PUMP


Charles H. Tuckey, Cass City, Mich., assignor to Walbro Corporation, Cass City, Mich.

Filed Apr. 7, 1995, Ser. No. 418,666

Int. Cl.⁶ F04D 5/00

U.S. Cl. 415—55.1

16 Claims



1. An electric-motor fuel pump that comprises:

a housing including a fuel inlet and a fuel outlet,

an electric motor including a rotor and means for applying electrical power to said motor to rotate said rotor within said housing,

pump means including an impeller coupled to said rotor for corotation therewith and having a periphery with a circumferential array of vanes, and means forming an arcuate pumping channel surrounding said impeller periphery and coupled to said inlet and said outlet, said means forming said pumping channel including channel inlet and outlet ports at opposed ends of said pumping channel,

said vanes comprising circumferential arrays of axially facing pockets on opposed axial side faces of said rotor, a channel extending radially inwardly from each pocket on each axial side face of said rotor, and a passage extending axially through said impeller radially inwardly of said pockets interconnecting said channels, and

vent means in said pump means for sequential registry with said passages in said impeller as said impeller rotates to vent vapor from within said pockets and said pumping channel.

5,586,859

FLOW ALIGNED PLENUM ENDWALL TREATMENT FOR COMPRESSOR BLADES


Nick A. Natcheff, Palm Beach Gardens, Fla., assignor to United Technologies Corporation, Hartford, Conn.

Filed May 31, 1995, Ser. No. 455,580

Int. Cl.⁶ F01D 1/12

U.S. Cl. 415—58.5

4 Claims



1. A tip shroud assembly for use with an axial flow gas turbine engine case, said tip shroud assembly comprising:

an annular shroud secured to said engine case and extending circumferentially about a reference axis, said shroud including a plurality of arcuate segments, each segment having a circumferentially extending length, the sum of said lengths defining the circumference of said annular shroud, each segment comprising

an arcuate member having:

a radially outer surface, and a radially inner surface including a plurality of first holes defining a first row and a plurality of second holes defining a second row, each of said rows extending circumferentially along the length of said segment, said first row in spaced relation to said second row, a circumferentially extending plenum spaced radially outward from said radially inner surface,

a plurality of first passages, each first passage extending from one of said first holes to said plenum, and a plurality of second passages, each second passage extending from one of said second holes to said plenum, each of said passages having a first and a second end, wherein said plenum communicates with said radially inner surface through each of said first and second passages,

a plenum surface radially outward of the radially inner surface said plenum surface including:

a plurality of third holes, each of said third holes defining the second end of one of said first passages, and a plurality of fourth holes, each of said fourth holes defining the second end of one of said second passages, each of said first holes defines the first end of one of said first passages, and the first hole of each first passage is spaced circumferentially along the length of the segment from the third hole thereof,

wherein the first hole of each first passage is spaced axially relative to said axis from the third hole thereof.

5,586,860

TURBO AERO ENGINE PROVIDED WITH A DEVICE FOR HEATING TURBINE DISKS ON REVVING UP

Jean-Louis Bertrand, Livry S/Seine; Gilles A. Charier, La Grande Paroisse; Xavier J.A. Guyonnet, St. Fargeau Ponthierry, and Jean-Louis Picard, Vaux le Penil, all of France, assignors to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation "Sneema", Paris, France


Filed Oct. 31, 1994, Ser. No. 332,101

Claims priority, application France, Nov. 3, 1993, 93 13044

Int. Cl.⁶ F01D 5/08; 1/12

U.S. Cl. 415—115

13 Claims



1. A turbo aero engine including a rotor, a stator, a combustion chamber upstream of a turbine belonging to the rotor and partly constituted by a disk, wherein it includes a channel for sending and blowing hot gas from a drawing off zone of the turbo aero engine to a central zone of the disk, the sending channel being composed of a portion opening into the drawing off zone and integral with the stator, and another portion integral with the rotor, the two portions being joined by an annular assembly including concentric walls for closing the portions, the walls, however, being perforated by orifices, and further including for one of the portions, circular parallel peaks established on the wall of said one portion being adjusted towards the other of the portions where the peaks approximately touch the wall, and delimiting grooves with certain of the grooves having no orifices, the orifices of the other portion being situated so that, according to the differential heat expansions in the turbo aero engine at different operating conditions, they open either in front of the grooves without orifices for certain conditions or in front of the grooves with orifices for other conditions.

5,586,861

AIRFLOW MEASURING CENTRIFUGAL FAN

Thomas A. Berger, Portland, Oreg., assignor to Pace Company, Portland, Oreg.

Continuation-in-part of Ser. No. 63,013, May 17, 1993, abandoned. This application Jun. 1, 1994, Ser. No. 252,192

Int. Cl.⁶ F04D 29/00

U.S. Cl. 415—118

12 Claims


1. An air flow measuring inlet cone for a centrifugal fan within a ventilation system comprising:

an inlet cone defining a major passage for the passage of air, the inlet cone having a flared inlet with a first diameter, a narrow throat with second diameter smaller than the first diameter, and a flared outlet with third diameter smaller than the first diameter and larger than the second diameter, the inlet cone having an empirically determined constant representative of its flow characteristics;

a first static pressure tap for measuring the static pressure at the flared inlet;

a second static pressure tap for measuring the static pressure at the throat;

means for determining the air flow through the inlet cone based on the difference between the static pressure at the flared inlet and the static pressure at the throat and the empirically determined constant.



4. A method for measuring the air flow within a ventilation system having a centrifugal fan and an inlet cone: measuring the static pressure at a first point of the inlet cone; measuring the static pressure at a second point of the inlet cone different from the first point; determining the pressure drop between the first and second points; empirically determining a constant for the inlet cone that is representative of the air flow characteristics of the inlet cone; and calculating the air flow through the inlet cone.

5,586,862

CENTRIFUGAL PUMP HAVING A SLIDABLE GATE


Michael Danner, 21 North Rd., Stony Brook, N.Y. 11790

Filed Jun. 15, 1995, Ser. No. 490,953

Int. Cl.⁶ F04D 29/48

U.S. Cl. 415—146

13 Claims



1. A centrifugal pump, comprising:

a) a pump volute having a substantially axial inlet port and a substantially radial outlet port and being substantially symmetrical about the axis of said outlet port, said outlet port being flanked by a first and second side wall;

b) an impeller rotatably mounted inside said pump volute;

c) a drive motor coupled to said impeller for imparting rotational movement to said impeller; and

d) slidable gate means mounted between said impeller and said outlet port and including a gate slidably movable between a

first position where said gate rests against said first side wall and a second position where said gate rests against said second side wall.

5,586,863

MOLTEN METAL PUMP WITH VANED IMPELLER


Ronald E. Gilbert, Chardon; George S. Mordue, Ravenna, and Chris T. Vild, Cleveland Heights, all of Ohio, assignors to Metallurgical Systems Co., L.P., Solon, Ohio

Continuation of Ser. No. 312,327, Sep. 26, 1994, which is a continuation-in-part of Ser. No. 898,043, Jun. 12, 1992, abandoned. This application Jun. 6, 1995, Ser. No. 468,378

Int. Cl.⁶ F04D 7/06

U.S. Cl. 415—200

12 Claims



1. A molten metal pump comprising:

(a) an elongated shaft having first and second ends;

(b) a means for rotating said shaft about an axis in communication with said first end of said shaft;

(c) an impeller disposed adjacent said second end of said shaft;

(d) a pumping chamber housing said impeller, said pumping chamber having a first generally axially directed inlet opening through which molten metal can be drawn and a second generally radially directed outlet opening through which molten metal can be discharged; and

(e) said impeller comprising an imperforate substantially circular base having a surface facing toward the first end of the shaft, and at least two imperforate vanes connected to and extending substantially perpendicular from said surface and extending radially from said shaft or a hub securing said shaft toward a peripheral portion of said base, said vanes being spaced apart at terminal inlet ends along their entire radial dimension to create an inlet area comprised of the axial opening between adjacent vanes at the terminal ends and an outlet area comprised of the radial opening between adjacent vanes along the axial direction of the vanes, each vane having a leading edge with a distal portion adjacent said peripheral base portion forming an angle of less than about 100° relative to a tangent to said circular base, said tangent being drawn at the center of said vane.

5,586,864

TURBINE NOZZLE DIAPHRAGM AND METHOD OF ASSEMBLY

Victor J. Knorowski, Rexford; George Reluzco; Kenneth J. Robertson, both of Schenectady, and Paul L. Adamkoski, Amsterdam, all of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Continuation-in-part of Ser. No. 280,899, Jul. 27, 1994, abandoned. This application Feb. 27, 1995, Ser. No. 395,357

Int. Cl.⁶ F04D 29/44


U.S. Cl. 415—209.2

10 Claims

1. A nozzle diaphragm for use in a turbine comprising:


an outer ring;

an inner web;



a circumferentially extending locator ring carried by one of said outer ring and said inner web, said locator ring including a plurality of circumferentially spaced holes through and extending between opposite radial sides thereof; a plurality of partitions connected to and extending between said outer ring and said inner web, each of said partitions having an end adjacent said locator ring and an opening therein; and a plurality of pins, each said pin being received in and through a hole of said locator ring and extending therefrom into said opening in the end of a partition for locating said locator ring and said partitions.


5,586,865
FAN WITH TRANSITION CHAMBER FOR PROVIDING ENHANCED CONVECTIVE FLOW
Ji-Zhong Yin, Fremont, Calif., assignor to Micronics Computers Inc., Fremont, Calif.
Filed Mar. 8, 1996, Ser. No. 613,247
Int. Cl.⁶ F04D 29/60
U.S. Cl. 415—213.1 26 Claims



1. Fan for delivering an enhanced cooling air flow, comprising: fan support means; fan blade means rotatably mounted within the fan support means defining a transition path therethrough for the cooling air; stationary screen means positioned adjacent to the blade means traversing the transition path; transition chamber formed between the screen means and the blade means traversing the transition path and defining a transition gap dimension between the screen means and the blade means, the transition chamber having a screen region adjacent the screen means with the cooling air flow through the screen region and the screen means being generally linear, having a blade region adjacent the blade means with the cooling air flow through the blade region and the blade means having a rotational component, and having a middle region between the screen region and the blade region allowing transition between the linear flow and the rotational component flow;

the fan support means positioned outside the transition chamber to avoid interference with the cooling air transition between the linear flow and the rotational component flow; fan driver secured to the fan support means for rotating the blade means to propel the cooling air flow, the rotation of the blade means imparting the rotational component to the cooling air flow through the blade region and the blade means; and spacer means extending between the screen means and the blade means maintaining the transition gap at a dimension sufficient to substantially isolate the linear flow through the screen region from the effects of the rotational component flow through the blade region, for enhancing the cooling air flow.


5,586,866
BAFFLE-COOLED WALL PART
Hans Wettstein, Fislisbach, Switzerland, assignor to ABB Management AG, Baden, Switzerland
Filed Aug. 2, 1995, Ser. No. 510,307
Claims priority, application Germany, Aug. 26, 1994, 44 30 302.5
Int. Cl.⁶ F01D 5/18
U.S. Cl. 416—96 A 15 Claims



1. A baffle cooling arrangement for wall parts, comprising: a wall having a wall part to be cooled; a carrier having an inner and an outer surface, the inner surface of the carrier being arranged at a distance from the wall part; and a plurality of baffle tubes, the baffle tubes each having an inlet end and an outlet end, the inlet ends of the baffle tubes being arranged over an area on the outer surface of the carrier and the outlet ends of the baffle tubes being directed toward the wall part, the tubes extending into a space between the inner surface of the carrier and the wall part.

5,586,867
DIRECT MOUNTED FAN APPARATUS
Michael D. Mehlos, Hwy. E, Watertown, Wis. 53094
Filed Jan. 19, 1994, Ser. No. 183,739
Int. Cl.⁶ F04B 49/06
U.S. Cl. 417—45 5 Claims


1. A fan unit for direct releasable mounting to a wall mounted power receptacle, comprising a support unit having an electrical connection means adapted to be releasably inserted into said receptacle with a physical and electrical interconnection between said support unit and said receptacle to physically support the fan unit and to connect electrical power to said electrical connector means, a fan blade support structure rotatable secured to said support unit, a plurality of fan blades secured to said fan blade support structure, a small high speed motor unit secured to said support unit, a speed



reducing drive coupling between said motor unit and said fan blade support structure for reducing the speed at said support structure and rotating of said fan blades, an enclosure enclosing said motor and said speed reducing drive coupling to physically support the fan unit and to connect electrical power to said electrical connector means, a control unit mounted within said enclosure and connected to control the speed of said motor and thereby the rotation of said fan blades, and control members secured to said support structure and located beneath said enclosure for ready access, wherein said motor is a permanent magnet D.C. motor and said motor control includes an AC power input, a solid state switching circuit having a power supply connection to said AC power input and including a variable impedance for controlling the turn on of said switching circuit in response to the incoming AC power input, a full wave rectifier connected to the output of said switching circuit and having an output connected to said motor control, and a reversing switch unit interconnected in said connection between the output of said rectifier and said motor for controlling the rotation direction of said motor, and separate movable control members secured to said support structure and extending from the lower portion of said enclosure for ready recess thereto.


5,586,868
METHOD OF DELIVERING LIQUID TO A PATIENT VIA A DISPOSABLE PUMPING CASSETTE HAVING A FLOW CONTROL & PRESSURE MONITORING MEMBER
Michael W. Lawless, Poway; Peter A. Soberon, Cardiff; Ashok Kaul; Steven E. Minick, both of San Diego; Gregory G. Hoerner, Poway; Robert A. Hermann, Chula Vista, and Stephen J. Kreinick, San Diego, all of Calif., assignors to Abbott Laboratories, Abbott Park, Ill.
Division of Ser. No. 242,762, May 13, 1994. This application Jun. 25, 1995, Ser. No. 494,986
Int. Cl.⁶ F04B 43/02; 53/10
U.S. Cl. 417—53 12 Claims

1. A method of delivering a fluid to a patient, comprising the steps of:
a. providing a disposable pumping cassette having a pumping chamber, an inlet valve, and an outlet valve;
b. priming said cassette with the fluid to be administered to the patient;
c. coupling the cassette to an associated pump driver;
d. advancing a plunger of the associated pump driver to force the fluid through the cassette, past the outlet valve, and thus, to deliver the fluid to the patient;



e. providing an auxiliary flow control member on the cassette to control free fluid flow through the cassette and to monitor fluid pressure when the cassette is installed in the pump; and
f. monitoring the pressure of the fluid discharged from said outlet valve.

5,586,869
INITIAL PRESSURE GOVERNOR FOR A VARIABLE DISPLACEMENT PUMP
Hartmut Benckert, Sielmingen, and Werner Muenzenmaier, Nuertingen, both of Germany, assignors to Putzmeister-Werk Maschinenfabrik GmbH, Germany
PCT No. PCT/EP92/02880, § 371 Date Jun. 10, 1994, § 102(e) Date Jun. 10, 1994, PCT Pub. No. WO93/12342, PCT Pub. Date Jun. 24, 1993
PCT Filed Dec. 12, 1992, Ser. No. 244,917
Claims priority, application Germany, Dec. 13, 1991, 41 41 108.0
Int. Cl.⁶ F04B 49/02
U.S. Cl. 417—218 18 Claims



1. A pressure governor for regulating the output of a hydraulic displacement pump that generates a pressurized fluid to a hydraulic fluid consuming unit, the pump including an outlet through which the pressurized fluid is discharged and an actuable control plate for regulating the output of the pump, the control plate having a first position allowing maximum pump output and a second position allowing a minimum pump output, said governor comprising:
a differential-pressure actuated regulator connected to the pump control plate for moving the control plate between the first and second positions, said regulator having opposed first and second chambers, wherein when fluid in said first chamber is pressurized relative to fluid in said second chamber, said regulator moves the pump control plate to the first position and when fluid in said second chamber is pressurized relative to fluid in said first chamber, said regulator moves the pump control plate to the second position;

a conduit connecting the outlet of the pump to said first chamber of said regulator;

a pressure regulated valve, said pressure regulated valve being connected to the outlet of the pump and said second chamber of said regulator, said pressure regulated valve having:

a valve unit having a first position for connecting said second chamber of said regulator to a discharge port and a second position for connecting the outlet of the pump to said second chamber of said regulator;

a biasing member connected to said valve unit for holding said valve unit in said first position;

a first control chamber connected to the outlet of the pump and to said valve unit wherein, when said first control chamber is provided with pressurized fluid from the outlet of the pump, said valve unit is displaced to said second position so as to allow fluid flow from the pump into said second chamber of said regulator; and

a second control chamber for receiving a restoring fluid wherein, when the restoring fluid is applied to said second control chamber, the pressure of the restoring fluid and said biasing member urge said valve unit from said second position to said first position; and

a hydraulic retarder connected between the outlet of the pump and said second control chamber of said pressure regulated valve for supplying pressurized fluid from the pump to said second control chamber as the restoring fluid, wherein said hydraulic retarder is configured to supply the pressurized fluid to said second control chamber at a pressure that increases at a rate slower than the rate at which the pressure of the fluid discharged from the pump increases.

5,586,870


BEARING STRUCTURE USED IN A COMPRESSOR
Masahiro Kawaguchi; Masanori Sonobe; Shigeki Kanzaki, and Tomohiko Yokono, all of Kariya, Japan, assignors to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho, Kariya, Japan

Filed Jul. 19, 1994, Ser. No. 277,347

Claims priority, application Japan, Jul. 20, 1993, 5-179394
Int. Cl. F04B 1/29

U.S. Cl. 417—222.2

17 Claims



1. A compressor comprising a rotary drive shaft having a first end and second end, said first and second ends being rotatably supported by opposing walls of a crank chamber defined in a casing, a disk tiltably mounted on said drive shaft and operably coupled to a plurality of pistons, such that rotation of said drive shaft results in reciprocating movement of said pistons for compressing refrigerant gas in a corresponding plurality of cylinder bores;

said first end of said drive shaft extending outside said casing;

a rotary member continuously coupled to said first end of said drive shaft for directly driving said drive shaft from a driving source;

a rigid support member protruding outwardly from said casing and disposed between said rotary member and said first end of said drive shaft;

a first bearing disposed between said rigid support member and said rotary member for receiving a thrust load and a radial load acting on said rotary member when said rotary member is rotatably driven by said driving source; and

a second bearing disposed between said second end of said drive shaft and the adjacent one of said walls of said crank chamber for receiving a radial load acting on said rotary member when said rotary member is rotated; and

said drive shaft being rotatably supported by only said first and second bearings.

5,586,871

ELECTRIC MOTOR DRIVEN FAN WITH WATER Baffle


Steven J. Barnes, Kettering, and Scott R. Spence, New Carlisle, both of Ohio, assignors to ITT Automotive Electrical Systems, Inc., Auburn Hills, Mich.

Filed Jun. 7, 1995, Ser. No. 479,675

Int. Cl. F04B 35/04

U.S. Cl. 417—423.11

5 Claims



1. In an electric motor driven fan for motor vehicle use including an electric fan motor having a motor shaft and a motor housing, a fan hub on said motor shaft spaced from said motor housing and supporting a plurality of fan blades, a motor support bracket by which the fan motor is supported, at least one ventilating aperture formed in said motor housing and opening into the space between the motor housing and said fan hub, the improvement for preventing direct entrance of water into the motor ventilation opening and into the space between said motor housing and said fan hub, comprising:

a plurality of axially extending rings including at least one ring mounted concentrically to said motor shaft on said fan hub and extending axially toward said motor housing, and at least one ring mounted on said motor mounting bracket and extending axially toward the other said ring and in overlapping relation thereto and defining between said rings a passage through which air may flow, said annular rings forming a labyrinth-like barrier preventing straight line intrusion of water radially inwardly into said space and ventilating aperture.

5,586,872

ADJUSTABLE PERISTALTIC PUMP

Valery V. Skobelev, ulitsa Menzhinskogo, 10, kv. 232; Mikhail A. Slivin, prospekt Krasnoyarsky rabochy, 191 A, kv. 36; Evgeny A. Selezov, ulitsa K. Marxa, 88, kv. 37; Viktor G. Kabakov, pereulok Rechnoi, 1, kv. 33, and Gennady S. Puzikov, ulitsa Mechnikova, 12, kv. 61, all of Krasnoyarsk, Russian Federation


PCT No. PCT/RU92/00171, § 371 Date Apr. 29, 1994, § 102(e)
Date Apr. 29, 1994, PCT Pub. No. WO94/05345, PCT Pub. Date Mar. 17, 1994

PCT Filed Sep. 2, 1992, Ser. No. 232,096

Int. Cl. F04B 43/08

U.S. Cl. 417—477.8

5 Claims



1. A pump for biological fluids comprising a housing which includes:

a resilient tube for passing through biological fluid, and an operating head which is rotatable in the direction of fluid transference by pump and which contains at least one roller member for bearing against said tube, wherein:

the at least one roller member comprises at least two rollers placed in series so that a roller of said roller member which is preceding in a direction of the operating head rotation has a greater aperture of said tube for transference in comparison with the roller of the same member which follows, and the pump is provided with a means for adjusting the degree of compression of said tube using the rollers, said means being mounted in the region of the operating head, wherein, said means for adjusting the degree of compression of the tube comprises a turnable and retainable eccentric placed coaxially with the operating head and coupled with at least one said roller member.

5,586,873

TUBE PUMP WITH RETRACTABLE ROLLERS

Pavel Novak, Stettenerstr. 117, CH-8207 Schaffhausen, Germany, and Clemens Rebholz, Alte Uhldingerstr. 25, D-7772 Uhldingen/Mühlheim, Germany


Continuation of Ser. No. 363,590, Dec. 23, 1994, abandoned, which is a continuation of Ser. No. 77,779, Jun. 18, 1993, abandoned. This application May 22, 1995, Ser. No. 445,954
Claims priority, application Germany, Jun. 18, 1992, 42 20 119.5

Int. Cl. F04B 43/08

U.S. Cl. 417—477.8

6 Claims

1. Tube pump for conveying liquid or viscous media, comprising a pump head on which at least two pump rollers are arranged which latter can be brought into engagement in succession with a tube wherein the medium to be conveyed is contained, in such a way that the medium is transported by squeezing the tube tightly,



wherein the pump rollers are displaceable between two end positions, of which one position, pumping position, permits the pumping operation and the other position, park position, permits changing of the tube without manual twisting of the pump head and without displacement of the tube bed; and

a first mechanism which unlocks the pump rollers which are in the pumping position, so that these pump rollers can be converted into the park position.

wherein the first mechanism comprises an eccentric disk for each pump roller, this disk being supported in an eccentric disk mounting to be rotatable about an axis, a shaft of the respective pump roller being mounted on this disk eccentrically to the axis, and a release button displacing a release disk in such a way that locking pins supported therein overcome the locking of the eccentric disks so that tension springs tensioned between the eccentric disks and the eccentric disk mounting pull the eccentric disks with the pump rollers supported therein into the park position.

5,586,874

REED VALVE ARRANGEMENT FOR A RECIPROCATING COMPRESSOR


Kenji Hashimoto, Yamada-gun, and Yoshito Matsumura, Seta-gun, both of Japan, assignors to Sanden Corporation, Japan

Filed Nov. 14, 1995, Ser. No. 555,698

Int. Cl. F04B 53/10

U.S. Cl. 417—569

9 Claims



1. A fluid displacement apparatus comprising:

a housing including a front end plate and a rear end plate;

a valve plate member disposed in said housing and dividing said housing into a first chamber and a second chamber, said second chamber comprising a discharge chamber;

a passage formed in said valve plate member extending between said first chamber and said discharge chamber, said passage having an open end through which discharge fluid flows;

an elastic valve member disposed on said valve plate, said valve member having a spring constant allowing said passage to remain blocked until the pressure in said first chamber exceeds a predetermined value;

a valve retainer member secured by a securing member to said valve plate, said valve retainer member bent away from said

valve plate member, said valve retainer member limiting bending movement of said valve member; and
a valve seat formed on said valve plate around the open end of said passage, said valve seat comprising a recess formed in said valve plate, said recess including a surface inclined with increasing depth in the radial direction of said valve plate, said inclined surface beginning at a point radially outside said securing member, point at which said valve retainer member is bent being radially outside said point where said inclined surface begins.

5,586,875


ASSEMBLY OF ROTARY HYDRAULIC PUMPS
Richard T. Ondrejko, Highland; Paul J. Castiglione, Milford, and Robert J. Miller, Livonia, all of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Jul. 10, 1995, Ser. No. 500,376

Int. Cl.⁶ F01C 1/36

U.S. Cl. 418—3

9 Claims




1. A pump assembly, comprising:
 - a first rotary pump having an inlet port, an outlet port, a first outer rotor formed with external gear teeth and internal lobes, a first inner rotor having external lobes intermeshing with the internal lobes of the first outer rotor;
 - a second rotary pump having an inlet port, an outlet port, a second outer rotor formed with external gear teeth meshing with the gear teeth of the first outer rotor, and internal lobes, a second inner rotor having external lobes intermeshing with the internal lobes of the second outer rotor;
 - a gear pump having an inlet and outlet located adjacent the intermeshing gear teeth;
 - a reservoir connected to the outlet of the first rotary pump and to the inlet of the second rotary pump, and adapted to hold fluid in communication with the external gear teeth of the first and second outer rotors;
 - a housing containing the first and second rotary pumps; and
 - a passage plate defining suction and pressure passages leading to the inlet ports and outlet ports of the first and second rotary pumps and the gear pump.

5,586,876
ROTARY COMPRESSOR HAVING OIL PUMPED THROUGH A VERTICAL DRIVE SHAFT
Donald Yasnascoll, Manlius, N.Y., and Alexander D. Leyderman, Frederick, Md., assignors to Carrier Corporation, Syracuse, N.Y.

Filed Nov. 3, 1995, Ser. No. 552,662
Int. Cl.⁶ F04C 1/8356; 23A00:29/02

U.S. Cl. 418—60

6 Claims



1. A vertical, high side, hermetic rotary compressor means comprising:
 - shell means;
 - pump assembly means located in said shell means;
 - motor means located in said shell means above said pump assembly means;
 - shaft means rotatably driven by said motor means and extending downwardly through said pump assembly means into an oil sump located in the bottom of said shell means;
 - said shaft means coating with said pump assembly means to cause said pump assembly means to compress gas and including oil distribution means extending from said oil sump;
 - said oil distribution means including means for pumping oil from said sump into said oil distribution means;
 - bearing means secured to said pump assembly means and supportingly receiving said shaft means;
 - muffler means secured to said bearing means and coating therewith to define a chamber in fluid communication with said pump assembly means via discharge valve means whereby gas compressed in said pump assembly means is supplied to said chamber;
 - a first fluid path for directing a majority of the compressed gas supplied to said muffler means into said shell means;
 - a second fluid path for directing a minor amount of the compressed gas supplied to said muffler means into said oil distribution means whereby the compressed gas passing into said oil distribution means coats with said oil from said sump to produce a jet pump effect assisting to supply oil from said sump to said oil distribution means.

5,586,877

INFRARED RAY EMITTERS WITH CATALYTIC BURNER

Michel Charmes, Lyons, France, assignor to A.J.C., Sathonay Camp, France


Filed Jul. 20, 1995, Ser. No. 504,946

Int. Cl.⁶ F23D 14/12

U.S. Cl. 431—115

7 Claims

1. An infrared ray emitter having a catalytic burner which is adapted to be installed within a furnace, the infrared ray emitter comprising: a box having a plurality of faces defining an interior chamber and opposite first and second end walls, one of said faces defining an opening from said interior chamber of said box, a



catalytic material structure mounted within said opening, means for injecting a combustible gas mounted within said chamber adjacent said catalytic material structure, a turbine means mounted to said box for introducing a combustion supporting gas under pressure into said chamber so as to distribute said combustion supporting gas over said catalytic material structure, motor means for driving said turbine means, said second end wall of said box including an inlet opening for receiving combustion supporting gas under pressure from said turbine means, electrical preheating means mounted within said chamber and adjacent said catalytic material structure for pre-heating said catalytic material structure, first and second spaced bracket members for supporting said box within the furnace, said second bracket member including an opening aligned with said inlet opening in said second end wall of said box and means for mounting said turbine means to said second bracket, whereby gas within the furnace is introduced into said interior chamber by said turbine means and thereafter exhausted from said interior chamber through said catalytic material structure and into said furnace whereby said gas within the furnace is recycled through said infrared emitter.

5,586,878

PREMIXING BURNER

Klaus Döbeling, Nussbaumen; Johannes Santner, and Christian Steinbach, both of Neuenhof, all of Switzerland, assignors to ABB Research Ltd., Zurich, Switzerland


Filed Nov. 2, 1995, Ser. No. 552,088

Claims priority, application Germany, Nov. 12, 1994, 44 40 558.8

Int. Cl.⁶ F23D 14/46

U.S. Cl. 431—351

8 Claims



1. A premixing burner of the double-cone design for operating an internal combustion engine, a combustion chamber of a gas-turbine group, or a firing plant, the burner comprising:
 - at least two hollow conical sectional bodies positioned to enclose a conical interior space that widens in a direction of flow at a cone half angle which is constant in the direction of flow, longitudinal symmetry axes of the sectional bodies being parallel to a longitudinal axis of the burner and mutu-

ally offset to define opposed tangential flow air-inlet slots on opposite sides of the interior space for a combustion-air flow, a nozzle for atomizing a liquid fuel arranged in a narrowest cross section of the conical interior space, the nozzle being directed for fuel injection at an acute angle to the longitudinal axis of the burner,

wherein the nozzle is a high-pressure atomization nozzle comprising a nozzle body having at least one feed passage for delivering liquid fuel to be atomized at a pressure greater than 100 bar, and at least two nozzle bores to spray fuel droplets into the interior space of the burner, wherein the nozzle bores are aligned with zones of high air velocity in the burner interior space, and the acute angle between the fuel-droplet spray and the longitudinal axis of the burner is at least as large as the cone half angle between the sectional cone bodies and the longitudinal axis of the burner.

5,586,879


FLUORESCENT ELECTROLUMINESCENT LAMP
Archana Szpak, Canton, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Division of Ser. No. 270,331, Jul. 5, 1994, abandoned. This application Dec. 20, 1995, Ser. No. 575,267

Int. Cl.⁶ H05B 33/02

U.S. Cl. 445—24

1 Claim



1. A method of providing an electroluminescent lamp structure comprising the steps of:
 - providing an electroluminescent lamp having a phosphor selected to optimize lamp durability and luminance without regard to the color of light produced by said phosphor;
 - selecting a fluorescent pigment to modify light produced by said phosphor in said optimized electroluminescent lamp to a desired color by absorbing a portion of light emitted by said phosphor and re-emitting light by fluorescence to produce said desired color;
 - mixing said selected fluorescent pigment with a matrix material to form an ink; and
 - applying said ink to said electroluminescent lamp.

5,586,880

HEAT TREATMENT APPARATUS AND HEAT TREATMENT BOAT

Tetsu Ohsawa, Tokyo, Japan, assignor to Tokyo Electron Limited, and Tokyo Electron Tohoku Limited, both of Japan

Continuation of Ser. No. 184,915, Jan. 24, 1994, abandoned.

This application May 30, 1995, Ser. No. 452,505


Claims priority, application Japan, Jan. 27, 1993, 5-031315

Int. Cl.⁶ F23D 3/12

U.S. Cl. 432—241

13 Claims

1. A heat treatment apparatus for heat-treating substrates to be treated, comprising:
 - a heat treatment furnace for housing and heat-treating said substrates; and



boat means for supporting said substrates and transporting said substrates into said heat treatment furnace, and comprising a bottom plate, a top plate and three support rods which are disposed at predetermined intervals from one another along an outer peripheral edge of each of said substrates housed in said boat means, said three support rods including a first support rod having a rectangular cross section supporting each of said substrates at an orientation flat, and a second and a third support rod provided on both sides of said first support rod, each of said second and third support rods being a hollow substantially halved tube having an arcuated cross section defined by curved outer and inner surfaces, each of said first, second and third support rods having notched grooves, and each formed with a lower face on which a corresponding one of said substrates sits.


5,586,881

INDICATOR FOR USE IN FIXING A DEVICE FOR CORRECTING TEETH IRREGULARITIES TO A SURFACE OF EACH TOOTH

Kunio Chikami, 211-1, Minamikuma, Kochi-shi, Kochi-ken, Japan, assignor to Kunio Chikami, Kochi, Japan
Filed Nov. 21, 1994, Ser. No. 345,418
Claims priority, application Japan, Jul. 25, 1994, 6-172190
Int. Cl.⁶ A61C 3/00

U.S. Cl. 433-3

5 Claims



1. An indicator for using in setting a device for teeth irregularities comprising a wire extending along with a dentition, a bracket in which said wire is inserted, said bracket being fixed to a surface of each tooth in a manner that a pillow-shaped base plate is interposed between said bracket and said surface, said indicator comprising:

- a backbone member extending along a longitudinal axis in said tooth;
- a leg member connected with a lower end of said backbone member;
- a first arm member connected with an upper end of said backbone member, said first arm member extending parallel to said leg member;

a means for carrying said bracket in a slidable manner, said means being connected with said backbone member at an intermediate portion of said backbone member; and
at least one second arm member connected with said backbone member at an intermediate portion between a position where said means for carrying said bracket is connected and another position where said leg member is connected, said second arm member extending parallel to said leg member, wherein in a state where the indicator is slidably provided with the bracket that the pillow-shaped base plate is adhered to the bracket, the pillow-shaped base plate is contacted with the tooth and each free end of the first arm member and second arm member contact the tooth.

5,586,882


SELF-LIGATING ORTHODONTIC BRACKETS

G. Herbert Hanson, 57 Augusta Street, Hamilton, Ontario, Canada

Filed Jul. 12, 1994, Ser. No. 274,077
Int. Cl.⁶ A61C 3/00

U.S. Cl. 433-13

30 Claims



1. An orthodontic bracket comprising:
a bracket body having labial, lingual, gingival, occlusal, mesial and distal surface portions, and having a mesial distal extending arch wire slot opening to the labial surface portion; and
a generally U-shaped ligating spring member of thin resilient material having labial and lingual portions in embracing sliding engagement with corresponding labial and lingual surface portions of the body, the ligating spring member being movable on the body between two positions in which the slot labial opening is respectively open and closed;
wherein the ligating spring member is of a superelastic shape recovery metal alloy.

5,586,883


GOLD-PLATED DENTAL MATRIX BAND

Robert G. Nakisber, 1212 N. LaSalle #1301, Chicago, Ill. 60610, and Daniel Uditsky, 1516 E. Flemming Dr. N., Arlington Heights, Ill. 60004

Filed Mar. 6, 1995, Ser. No. 398,540
Int. Cl.⁶ A61C 5/04

U.S. Cl. 433-39

17 Claims



1. A dental matrix band, comprising:
a body portion that is made from a foil-like metal have a central tooth circumscribing portion extending between and merging

with a pair of arms adapted to generally surround a pre-selected tooth; and a layer of gold disposed on said body portion such that said layer of gold extends over said central tooth circumscribing portion.

5,586,884


DENTAL ARTICULATOR

Richard F. Kraus, 3 Oakbrook Club Dr., #D 106, Oakbrook, Ill. 60521

Filed Aug. 26, 1994, Ser. No. 296,736
Int. Cl.⁶ A61C 11/00

U.S. Cl. 433-60

16 Claims



1. A dental articulator for mounting molded casts of teeth having a mounting surface and defining an occlusal plane, said articulator comprising:

- a. a base platform for stabilizing the articulator in a first position on a work surface;
- b. a longitudinal support column securely attached to the base platform;
- c. upper and lower support arms of predetermined length operatively connected with the support column;
- d. at least one quick-release coupling for mounting a cast on a support arm such that the cast is firmly mounted and quickly removable;
- e. wherein said quick-release coupling further comprises a first member mounted directly to the mounting surface of said cast, and a second member connected to said support arm, said connection occurring along a connecting plane parallel to said occlusal plane, said coupling allowing for fully traversable and rotational adjustment movement of the mounted cast in and along said connecting plane.

5,586,885

DENTAL FILE/REAMER INSTRUMENT


Jimmie Kert, Norrevaenget 76, DK-3500 Værløse, Denmark

Filed May 4, 1995, Ser. No. 431,646
Int. Cl.⁶ A61C 5/02

U.S. Cl. 433-102

8 Claims

1. In combination, a dental reamer/file instrument and a rotary drive member, said combination comprising:
said dental reamer/file instrument including
a shank for releasably attaching the instrument to a rotary drive member,
a body having a working part with projections for cutting, abrading and/or shaping a root canal of a tooth undergoing endodontic treatment,
an intermediate part connecting said shank to said body, such as being formed integrally therewith,



wherein said intermediate part comprises a part having a torsional fracture strength substantially less than that of said body, and
a first projection protruding radially outward and situated between said part having a reduced torsional strength and said body;
said rotary drive member including
a second projection protruding radially inward and located towards a proximal end of said body yet distally of said radially outwardly protruding projection on said intermediate part of said dental reamer/file instrument so as to allow relative rotation but not relative movement in an axial direction when said instrument is operatively connected to said drive member.

5,586,886


ROTARY HANDPIECE FOR ENDODONTIC INSTRUMENTS

James B. Roane, 707 SW. 24th St., Suite 201, Norman, Okla. 73069

Filed Aug. 30, 1995, Ser. No. 520,992
Int. Cl.⁶ A61C 5/02; 1/10; 3/00

U.S. Cl. 433-224

20 Claims



1. In a rotary handpiece for cleaning and enlarging a root canal of a tooth having a rotary endodontic file, said handpiece having a rotary drive which rotates a chuck for holding and rotating the endodontic file, the improvement which comprises:
a retractable support rod attached to and extending from said handpiece positioned adjacent and substantially parallel to said endodontic file and adapted to rest on a tooth whereby the retraction of said support rod controls the advance of said endodontic file into said root canal; and
means attached to said handpiece and to said support rod for retracting said support rod and advancing said endodontic file at a controlled rate into said root canal whereby said endo-

dontic file does not become excessively loaded while said root canal is being cleaned and enlarged.

5,586,887

HOWITZER STRAP-ON KIT FOR CREW PERFORMANCE EVALUATION AND TRAINING METHOD


Niall B. McNelis, Baltimore; Richard W. Doyle, Fallston; Dale A. Clark, Parkton; Larry A. Zeafra, Baltimore, and Thomas P. McGrath, Lutherville, all of Md., assignors to AAI Corporation, Hunt Valley, Md.

Filed Nov. 23, 1994, Ser. No. 346,289

Int. Cl.⁶ F41G 3/26

U.S. Cl. 434—20

22 Claims



22. A training method for remotely and substantially instantaneously evaluating the aiming alignment, settings and levels set by a crew training on a howitzer gun, comprising:

- (1) manually removably attaching to a pantel of the gun a video means for receiving a sight picture in the pantel or for displaying a synthetic sight picture in a pantel eyepiece;
- (2) manually removably attaching to a pantel deflection setting means a pantel deflection setting encoder for encoding signals responsive to a pantel deflection setting;
- (3) manually removably attaching to the pantel a pantel level encoder for encoding signals responsive to a pantel level;
- (4) manually removably attaching to a quadrant setting means a quadrant setting encoder for encoding signals responsive to a quadrant setting;
- (5) manually removably attaching to a quadrant a quadrant level encoder for encoding signals responsive to a quadrant level; and
- (6) receiving in a data processing computer said sight picture, or the data processing computer displaying and controlling the synthetic sight picture in a pantel eyepiece, and receiving in the data processing computer said signals for evaluation of the alignment, settings and levels.

5,586,888

METHOD OF ADAPTING A PAIR OF CHILDREN'S SHOES

Marlene K. Webb, 335 Lee Ave. So. Box 495, Cokato, Minn. 55321


Filed Jul. 10, 1995, Ser. No. 500,458

Int. Cl.⁶ G09B 19/00

U.S. Cl. 434—258

1 Claim

1. A method for adapting a child's pair of shoes to indicate to the child which shoe is for the left foot and which is for the right foot consisting of the steps of positioning a pair of a child's shoes to have side-by-side engagement corresponding to the feet upon which they are worn,



overlying adjacent engaging toe and side wall portions portions of said shoes with a design of a figure readily recognizable as a whole design by a child which tells the child the shoes are properly positioned to be put on the corresponding feet, and when said shoes are otherwise positioned, said figure is separated and meaningless telling the child that the shoes have to be otherwise positioned relative to each other to form of a whole design.

5,586,889

HAND HELD TEACH AND TEST DEVICE


Milton Goodman, 160-06 65TH Ave., Flushing, N.Y. 11365

Filed Sep. 22, 1994, Ser. No. 310,889

Int. Cl.⁶ G09B 3/00

U.S. Cl. 434—327

18 Claims



1. A hand-held device for selecting one of a plurality of sets of internally-stored answers and recording individual responses for comparison to the selected set of answers, each set of answers having an identification code, a plurality of separate sets of questions being freely creatable for each set of answers, the device comprising: select one of said plurality of sets of internally-stored answers;

an indicator for serially prompting for individual responses to a separate set of questions corresponding to the selected set of answers;

response means for registering a response for each question; and recording means for comparing the responses to the answers and recording the number of correct and incorrect responses given.

5,586,890

CONTACTING APPARATUS FOR A CHIPCARD

Gerhard Braun, Erlenbach, Germany, assignor to Amphenol-Tuchel Electronics GmbH, Germany
PCT No. PCT/EP93/03618, § 371 Date Nov. 7, 1994, § 102(e)
Date Nov. 7, 1994, PCT Pub. No. WO94/15313, PCT Pub. Date Jul. 7, 1994


PCT Filed Dec. 20, 1993, Ser. No. 284,660

Claims priority, application Germany, Dec. 18, 1992, 42 43 076.3

Int. Cl.⁶ H01R 9/09

U.S. Cl. 439—66

32 Claims



1. An apparatus for establishing electrical connection between a chipcard and a printed circuit board, said apparatus comprising: means, arranged on said circuit board, for contacting said chipcard, said means including a support containing a plurality of contact elements for facilitating electrical contact between said contact elements and said chipcard, said support performing the function of supporting said contact elements in a manner that will increase the available space on said printed circuit board and wherein said support has a width which is narrower than the width of the chip card and said support further comprises a parallelogram-shaped section and a rectangular-shaped section wherein the sides of the support in the parallelogram-shaped section are inclined with respect to the sides of the support in the rectangular section; and guide means, spaced from the support, for guiding the chipcard onto the support.

5,586,891

ELECTRICAL SOCKET FOR HIGH-FREQUENCY APPLICATIONS

Gary P. Pirani, Shrewsbury; Alan M. Gulachenski, West Millbury, and David J. Kelly, Worcester, all of Mass., assignors to Electronic Designs Inc., Westborough, Mass.

Filed May 4, 1994, Ser. No. 237,676


Int. Cl.⁶ H01R 9/09

U.S. Cl. 439—71

16 Claims

1. An electrical socket, suitable for electrically interconnecting an electronic module having external leads with a printed circuit board having contact pads, said electrical socket comprising:

- a base frame, having an upper surface, a lower surface, and an opening therethrough generally conforming to the body shape and size of the electronic module, said opening defining an inner surface extending between said upper surface and said lower surface;
- at least one resilient strip, coextensive with at least a portion of said inner surface, said resilient strip comprising a mounting surface for engaging said base frame inner surface, a mating surface for engaging the electronic module external leads, a contact surface essentially coplanar with said base frame lower surface, and a retaining surface; and
- a plurality of conductive members, each comprising a lead portion and a contact portion, said conductive members strayed upon said resilient strip in generally parallel disposition to one another, each said conductive member configured such that said lead portion physically engages said resilient strip mating surface and said contact portion physically engages said resilient strip contact surface; whereby said conductive member contact portion electrically engages the contact pads when said base frame lower surface is positioned against the printed circuit board, and placement of the electronic module into said base frame opening positions each electronic module external lead proximate said resilient strip mating surface and places each electronic module external lead into adjacent parallel relationship with at least one said conductive member lead portion to establish electrically conductive paths between the electronic module external leads and the printed circuit board via the contact pads.



tion to one another, each said conductive member configured such that said lead portion physically engages said resilient strip mating surface and said contact portion physically engages said resilient strip contact surface; whereby said conductive member contact portion electrically engages the contact pads when said base frame lower surface is positioned against the printed circuit board, and placement of the electronic module into said base frame opening positions each electronic module external lead proximate said resilient strip mating surface and places each electronic module external lead into adjacent parallel relationship with at least one said conductive member lead portion to establish electrically conductive paths between the electronic module external leads and the printed circuit board via the contact pads.

5,586,892

ELECTRICALLY CONNECTING STRUCTURE

Minoru Sato, Hamura, Japan, assignor to Casio Computer Co., Ltd., Tokyo, Japan



Filed Mar. 3, 1995, Ser. No. 397,919

Claims priority, application Japan, Mar. 10, 1994, 6-065417

Int. Cl.⁶ H01R 4/04

U.S. Cl. 439—91

20 Claims



1. An electrically connecting structure, comprising: a first electronic part having a first connecting terminal; a second electronic part having a second connecting terminal which is arranged to face said first connecting terminal of said first electronic part; and an anisotropic conductive adhesive arranged between said first connecting terminal and said second connecting terminal, said anisotropic conductive adhesive including: an insulating adhesive, a plurality of first conductive particles which are covered with an insulating layer, and

a plurality of second conductive particles which are not covered with any material;
 said first conductive particles and said second conductive particles having substantially the same size;
 portions of said insulating layer covering said first conductive particles being brought into contact with said first connecting terminal and said second connecting terminal, and being broken away, under a force which is applied to said first connecting terminal and said second connecting terminal, so that said first conductive particles are brought into contact with said first connecting terminal and said second connecting terminal;
 said second conductive particles being brought into contact with said first connecting terminal and said second connecting terminal under the force which is applied to said first connecting terminal and said second connecting terminal, and
 said first connecting terminal and said second connecting terminal being electrically connected to each other through said first conductive particles and said second conductive particles.


5,586,893

IC CARD CONNECTOR SHIELD GROUNDING
 Rene Mosquera, Laguna Niguel, Calif., assignor to ITT Corporation, New York, N.Y.

Filed Jul. 17, 1995, Ser. No. 503,025
 Int. Cl.⁶ H01R 13/648

U.S. Cl. 439—108

8 Claims



1. A plug connector for mating with a receptacle connector, comprising:

- a dielectric plug connector housing which is elongated in a lateral direction and which has laterally spaced opposite side walls;
- a plurality of plug contacts arranged in at least one laterally extending row and mounted on said housing;
- a circuit board attached to said housing, said circuit board having a board front portion and having at least one laterally-extending row of conductive contact traces on said board front portion, said contacts having tails joined to said contact traces, said circuit board also having at least one ground trace; each of said housing opposite side walls has a recess facing away from said row of contacts, and including a pair of plug ground members each having a forward terminal portion lying in one of said housing recesses with each of said forward terminal portions having a contact part extending in a bend that projects laterally beyond adjacent portions of the corresponding housing side wall, and with each plug ground member having a rear portion joined to one of said circuit board ground traces.

5,586,894

MULTIPLE LEVER CONNECTOR ASSEMBLY


Osamu Taniuchi, and Nakata Hiroyuki, both of Yokkaichi, Japan, assignors to Sumitomo Wiring Systems, Ltd., Mie Pref., Japan

Filed Nov. 17, 1994, Ser. No. 343,898

Claims priority, application Japan, Nov. 18, 1993, 5-066819 U; Nov. 18, 1993, 5-066820 U; Nov. 19, 1993, 5-066836 U
 Int. Cl.⁶ H01R 13/62

U.S. Cl. 439—157

10 Claims



1. A connector assembly comprising:

- a) a plurality of first connector housings forming male terminal accommodating cavities, each said housing having opposite side walls;
- b) a plurality of second connector housings forming female terminal accommodating chambers;
- c) a lever support shaft protruding outwardly from each of said first connector housing side walls;
- d) a plurality of operating levers each straddling one of said first connector housings and each having two bearing holes into which said lever support shafts are fitted for rotatably mounting said operating levers on said first connector housings;
- e) a plurality of cam projections provided on each of said second connector housings and engaging said levers to displace said first and second connector housings by cam action of said operating levers in a coupling direction and in an uncoupling direction; and
- f) a coupling member coupling said first connector housings to one another so that said first connector housings are arranged side by side with a predetermined clearance between adjacent surfaces of said operating levers, said clearance being smaller than a depth of fit between said lever support shafts and said respective operating lever bearing holes.

5,586,895

POWER TRANSFER HINGE

Raymond E. Zehrung, 3029 Cameron Way, Santa Clara, Calif. 95051

Filed Oct. 23, 1995, Ser. No. 546,586


Int. Cl.⁶ H01R 35/04

U.S. Cl. 439—165

14 Claims

1. A power transfer hinge comprising:

- a first hinge leaf having a first rear surface having a first recess and at least two first knuckles having bores axially aligned to a common bore;
- a second hinge leaf having a second rear surface having a second recess and at least two second knuckles, interleaved with said first knuckles, having bores axially aligned to said common bore;
- a pair of pins, disposed in said common bore, for pivotally engaging said first and second hinge leaves;



- a first passageway entering said common bore through a first opening and connecting said common bore to said first recess;
- a second passageway entering said common bore through a second opening and connecting said common bore to said second recess, the second passageway and the first passageway having a common center line for entering said common bore; and
- a cable passing through said first recess, the first passageway, said common bore, the second passageway, and the second recess.

5,586,896

HEATER RING CONNECTOR ASSEMBLY


Daniel T. Casey, Harrisburg, and Brent D. Yohn, Newport, both of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Jan. 11, 1995, Ser. No. 371,243

Int. Cl.⁶ H01R 23/68

U.S. Cl. 439—218

14 Claims



1. A connector assembly comprising a pair of rings including a first ring defined by a first insulative ring housing and having an annular periphery provided with a plurality of circumferentially-spaced plug contacts, and a second ring defined by a second insulative ring housing and having an annular periphery provided with a like plurality of circumferentially-spaced receptacle contacts receiving the plug contacts on the first ring;

- said second ring having a pair of adjacent segments, one of the segments having said like plurality of circumferentially-spaced receptacle contacts, and the other of the segments having a second plurality of circumferentially-spaced receptacle contacts equal in number to said like plurality, said receptacle contacts in one segment being equal in number to all of the plug contacts on said first ring, such that the plug contacts on the first ring may be received in either plurality of receptacle contacts on the second ring upon mating.

5,586,897

WATERPROOF CONNECTOR


Yasuhisa Shinji, and Hiraji Takase, both of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan

Filed Aug. 22, 1995, Ser. No. 518,138

Claims priority, application Japan, Aug. 25, 1994, 6-200734
 Int. Cl.⁶ H01R 13/52

U.S. Cl. 439—271

5 Claims



1. A waterproof connector (1), comprising:

- a connector housing (30) having an opening (5) engaged with a mated connector housing;
- a packing (10) disposed within the opening of said connector housing, for sealing a space between the two mated connector housings, at least one part (10a) of said packing being exposed outside through at least one hole (12) formed in said connector housing; and
- a protective cover (40) selectively attached to said connector housing from the outside at need, for covering at least one exposed part (10a) of said packing according to a required degree of connector waterproof characteristics.

5,586,898

SELF LOCKING MALE AND FEMALE CONNECTORS FOR ELECTRICAL CORDS


Dennis R. Anderson, and Katherine D. Anderson, both of 1952 Rainbow Ridge, Corona, Calif. 91720

Filed Nov. 25, 1994, Ser. No. 344,970

Int. Cl.⁶ H01R 13/28

U.S. Cl. 439—287

2 Claims



1. An electrical connector apparatus for an electrical cord comprising:

- (a) a male connector;
- (b) said male connector comprising:
 - a first housing;
 - a first wiring chamber in the first housing;
 - a first wiring chamber cover removably covering the first wiring chamber and removably connected to the first housing;
 - a plurality of first wiring terminals in the first wiring chamber;

- a plurality of connector prongs electrically connected to the first wiring terminals;
the connector prongs partially extending outside the first housing; and
a first T-shaped longitudinal locking foot attached to a first outer surface of the first housing;
- (c) a female connector removably attached to the male connector; and
(d) said female connector comprising:
a second housing;
a second wiring chamber in the second housing;
a second wiring chamber cover removably covering the second wiring chamber and removably connected to the second housing;
a plurality of second wiring terminals in the second wiring chamber;
a plurality of prong receptors, to removably receive the connector prongs, electrically connected to the second wiring terminals;
the prong receptors in the second housing; and
a first T-shaped longitudinal locking channel attached to a second outer surface of the second housing to slidably and removably receive the first T-shaped longitudinal locking foot;
- (e) a second T-shaped longitudinal locking foot attached to a fourth outer surface of the second housing to slidably and removably receive the first T-shaped longitudinal locking channel; and
(f) a second T-shaped longitudinal locking channel attached to a third outer surface of the first housing to slidably and removably receive the second T-shaped longitudinal locking foot on the second outer surface of the second housing.

5,586,899

ELECTRICAL TERMINAL

Naohisa Okada, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Japan


Filed Feb. 28, 1995, Ser. No. 397,683

Claims priority, application Japan, Mar. 1, 1994, 6-056733

Int. Cl.⁶ H01R 13/28

U.S. Cl. 439—287

15 Claims



1. An electrical terminal having a stud connection region with an aperture therein, a wire connection region for connection to an electrical wire, and a neck region connecting the stud connection region and the wire connection region, the stud connection region having angularly spaced latch members arranged such that said electrical terminal is engageable with an identical, overlying electrical terminal upon relative rotation of said electrical terminals about said aperture to form an integrated terminal assembly, wherein said neck region includes angularly spaced male and female lock members in a generally planar surface, one of which is engageable with the other one of a male and female lock member of the overlying electrical terminal to prevent decoupling of the electrical terminals on engagement of said latch members.

5,586,900

CONNECTOR TERMINAL TEST JIG

Sakai Yagi, Masanori Tsuji, Motohisa Kashiya, and Takayoshi Endo, all of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan


Filed Apr. 27, 1995, Ser. No. 432,426

Claims priority, application Japan, May 9, 1994, 6-095083

Int. Cl.⁶ H01R 13/62

U.S. Cl. 439—310

7 Claims



1. A connector terminal conduction test jig for testing conduction of terminals (35) of a connector (49) having an engaging member (65) engaged with a connector housing (55) thereof, which comprises:
a connector support member (39) for supporting the connector (49) to be tested;
a test body member (69) disposed movably toward and away from said connector support member and formed with a plurality of through holes (77) each for supporting a terminal conduction test pin (89) movably therein;
a contact plate member (73) attached to said test body member and composed of a contact surface (83) and a fitted contact projection (85) formed with a plurality of test pin accommodating holes (87) each communicating with each through hole (77) of said test body member; and
when said test body member (69) is moved toward said connector support member (39), the fitted contact projection (85) being first inserted into the connector housing (55) so that the contact surface (83) of said contact plate member (73) urges the connector housing (55) toward said connector support member (39) to correctly engage the engaging member (65) with the connector housing (55), and after that terminal ends (35a) of the terminals (35) arranged in the connector housing being inserted into the test pin accommodating holes (87) of the fitted contact projection (85) into contact with the terminal conduction test pins (89) in the test body member (69) for terminal conduction test.

5,586,901

CONNECTOR ASSEMBLY WITH COOPERATING TERMINALS AND METHOD FOR CONNECTING SAME

Junji Muta, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Mie, Japan

Filed Nov. 30, 1995, Ser. No. 565,579


Claims priority, application Japan, Dec. 7, 1994, 6-331121

Int. Cl.⁶ H01R 13/64

U.S. Cl. 439—342

25 Claims

1. A connector assembly comprising:
male and female housings;
at least one male terminal and at least one female terminal mounted on the male and female housings, respectively;
the at least one male terminal having a distal end portion narrower than a proximal end portion thereof;



the at least one female terminal comprising:
a connection portion that resiliently fits on an outer periphery of the proximal end portion of the at least one male terminal;
an insertion groove formed in a side of the connection portion, the insertion groove being adapted to temporarily hold the distal end portion of the at least one male terminal and allowing the distal end portion to pass therethrough into the connection portion; and
guide portions that guide the distal end portion of the at least one male terminal into the insertion groove, the guide portions being formed respectively on opposite side edges of the insertion groove;
wherein the at least one female terminal is connected to the at least one male terminal by inserting the at least one female terminal in a direction intersecting a longitudinal axis of the at least one male terminal, with the distal end portion of the at least one male terminal being passed through the insertion groove, and the at least one female terminal being inserted in a direction along the longitudinal axis of the at least one male terminal.

5,586,902

ELECTRIC CONNECTOR

Gustav Hopf, Schnaittach, and Helmut Steinhardt, Nürnberg, both of Germany, assignors to Framatome Connectors International, Paris, France


Filed May 24, 1994, Ser. No. 247,998

Claims priority, application Germany, May 25, 1993, 43 17 344.6

Int. Cl.⁶ H01R 13/73

U.S. Cl. 439—352

7 Claims



1. Electric connector between a generator and an electronic controller for housing socket inflatable motor vehicle airbags, said connector comprising a housing for contact tubes with leads, wherein said housing in a coupling position lifts a jumper, disposed in a receptacle for generator-sided plug pins, from said plug pins, said housing further comprising hook-shaped spring elements attached to said housing, and engaging with recesses in said generator, said connector being provided with a cover member having strip-shaped extensions, constituting a click-stop position blocking said hook-shaped spring elements, wherein the connector housing has an assembly opening closed by a cover member retained on said housing by a pin arranged in front of said cover

member in a push-on direction, and by guide elements, attached to front and rear regions of longitudinal sides of said cover member, said cover member being slidable over said assembly opening of said housing in a direction parallel to an upper surface of said connector, from a preclick-stop position to said click-stop position by means of projections provided on said longitudinal sides.

5,586,903

PLUG CONNECTOR IN WHICH THE CABLES ARE LED OUT AT AN ANGLE AND WITH A RELEASABLE SECONDARY LOCK

Manfred Hoffmann, Reichenschwand, Germany, assignor to Framatome Connectors International, Paris, France


Filed Apr. 18, 1995, Ser. No. 423,102

Claims priority, application Germany, Apr. 25, 1994, 44 14 348.6

Int. Cl.⁶ H01R 13/627; 13/62

U.S. Cl. 439—352

7 Claims



1. A plug connector in which cables are led out at an angle and comprising secondary locking means, said plug connector comprising:

- (a) a plug part on which at least two opposite tongues are disposed parallel to an axis of said plug part, said tongues comprising outwardly directed catches;
- (b) a socket part comprising slots receiving said tongues and shoulders for engagement of said catches;
- (c) said tongues extending towards a back wall of said plug part;
- (d) said tongues having side surfaces oriented towards said axis and being bevelled away from said axis towards said back wall;
- (e) the tongues being adapted to pivot on a housing of said plug part over substantially half a length of said tongues; and
- (f) said back wall being formed with slots in a region of said bevelled side surfaces of said tongues in such a manner that a U-shaped yoke, upon insertion of limbs of said yoke into said slots, forces said tongues away from said axis in this zone so that said opposite ends of tongues are moved with said catches towards said axis.

5,586,904

SAFETY STRUCTURE IMPROVEMENT OF A BULB SOCKET

Ming H. Huang, 2, Lane 65, Cheng Kong Road, Hsinchu, Taiwan

Filed Mar. 17, 1995, Ser. No. 404,494


Int. Cl.⁶ H01R 4/24

U.S. Cl. 439—419

1 Claim

1. A lamp socket assembly for securely and operatively receiving therein a lamp having an electric conduction terminal comprising:

- (a) a socket member extending in an axial direction, said socket member having a sidewall portion and a base portion defining a chamber for coaxially receiving at least a portion of said



lamp, said base portion having formed therein a through opening, said sidewall portion having formed therein an elongate insertion groove;

- (h) a cover member coupled to said base portion of said socket member, said cover member having a supporting seat extending in said axial direction into said opening of said base portion of said socket member, said supporting seat having front and side surfaces extending substantially in said axial direction, said side surface having an elongate slot formed therein, said front surface having a recessed area and a raised block protruding therefrom, said supporting seat having formed thereon a boss portion projecting in said axial direction and a plurality of barb projections, said barb projections engaging said base portion of said socket member to secure said coupling of said cover member therewith;
- (c) a first terminal conductor plate received in said insertion groove of said socket member; and
- (d) a second terminal conductor plate coupled to said supporting seat of said cover member, said second terminal conductor plate having a first end, a second end, and an intermediate plate portion extending therebetween, said first end securely engaging said raised block of said cover member supporting seat, said second end having formed thereon a pointed portion received in said elongate slot of said cover member supporting seat, said intermediate plate portion being adapted for resilient deflection by said electric conduction terminal of said lamp into contact with said boss portion of said cover member supporting seat when said lamp is received in said lamp socket assembly.

5,586,905


INSULATION DISPLACEMENT ELECTRICAL CONNECTOR WITH IMPROVED STRAIN RELIEF
Robert C. Marshall, St. Petersburg, and Frank Pansari, Jr., Clearwater, both of Fla., assignors to Molex Incorporated, Lisle, Ill.

Filed Nov. 1, 1993, Ser. No. 146,384
Int. Cl.⁶ H01R 13/58

U.S. Cl. 439—463

9 Claims

1. In an electrical connector assembly for terminating an insulated electrical wire having an inner conductor surrounded by insulation, the connector assembly including:
- housing means having a wire-receiving opening therein for receiving the insulated electrical wire;
- a terminal mounted in the housing means and having an insulation displacement slot adapted to displace the insulation of the wire and electrically engage the inner conductor to create an electrical connection therebetween;
- wherein the improvement comprises:
- integrally molded strain relief means located adjacent the connection within the wire-receiving opening of the housing means for surrounding and gripping the insulated wire substantially entirely thereabout,



wherein the wire-receiving opening extends entirely through the housing means and said integrally molded strain relief means are positioned on both sides of the terminal within the opening adjacent the electrical connection to provide support to the electrical insulated wire in two locations longitudinally spaced along the wire on opposite sides of the terminal, whereby the strain relief means provide support to the insulated electrical wire and strain relieves the inner conductor.

5,586,906


ELECTRICAL CONNECTOR HAVING AN IMPROVED GRIP MEMBER

Theodore Staros, Margate, and Alan Flum, Boca Raton, both of Fla., assignors to Sony Corporation, Tokyo, Japan, and Sony Electronics Inc., Park Ridge, N.J.

Filed Jul. 28, 1994, Ser. No. 282,188
Int. Cl.⁶ H01R 13/00

U.S. Cl. 439—483

10 Claims



1. An electrical connector comprising:
- a housing comprising:
- a front housing which is detachably coupled to a back housing;
- a manual grip member removably attached between said front housing and said back housing comprising:
- a substantially planar collar member having an opening formed therein for receiving said housing
- a substantially planar pull tab having an area which is greater than the area of said planar collar member
- said pull tab is attached to said collar member so as to form an angle therebetween which is less than 180 degrees but greater than 90 degrees;
- said front housing further comprises
- a plurality of electrical contacts each attached to an electrically conductive terminal
- an insert assembly for holding said electrical contacts in position within said housing;
- said back housing further comprises
- an opening for receiving an electrical conductor
- a clamping means for physically interfacing an electrical conductor received through said opening to said back housing; and wherein axial force applied to said pull tab is translated to said housing without stressing said contacts.

5,586,907

BATTERY CONNECTOR


Robert H. Frantz, Newville; John T. Larkin, Jr., New Cumberland, and Robert S. Correll, Jr., Harrisburg, all of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Aug. 25, 1995, Ser. No. 519,216

Int. Cl.⁶ H01R 3/00

U.S. Cl. 439—500

2 Claims



1. A battery connector for disk-shaped batteries comprising:
- a dielectric housing having opposed sidewalls, opposed endwalls and a bottom wall together defining a battery receiving cavity said bottom wall including two terminal receiving passageways extending therethrough one proximate each sidewall said endwalls of said housing extend outwardly from said housing and beyond said battery receiving cavity to define spring arms at leading ends thereof dimensioned to receive said battery therebetween and retain said battery in said housing cavity.

a surface mountable positive terminal and a surface mountable negative terminal, each having spring arm contact sections electrically engageable with a respective battery electrode, and surface mountable connecting sections, said positive and negative terminals being insertable through respective terminal receiving passageways with said spring arm contact sections opposing each other along said sidewalls of said housing and said surface mountable connecting sections of both said terminals extending outwardly from respective said housing sidewalls at the bottoms thereof;

whereby said positive and said negative terminals are electrically engageable with battery electrodes on opposed surfaces of said battery, and surface mountable connecting sections of said positive and negative terminals are spaced apart at least a sufficient distance from each other to prevent bridging therebetween when said connecting sections are soldered to respective circuit pads on a circuit board.

5,586,908

SAFETY UNIT FOR AN ELECTRIC 3-PHASE CIRCUIT

Henri L. P. Lorrain, Brussels, Belgium, assignor to U.S. Phillips Corporation, New York, N.Y.


Filed Sep. 7, 1994, Ser. No. 302,140

Claims priority, application Belgium, Sep. 8, 1993, 09300942
Int. Cl.⁶ H02H 9/04

U.S. Cl. 439—511

7 Claims

1. A safety unit for an electric 3-phase circuit, said safety unit comprising: three semi-conducting components each provided with a first terminal and a second terminal; a support having three contact pins, each contact pin respectively electrically coupleable to a respective first terminal, said support further including a plurality of receptive apertures formed therein; and an insertive module



having a plurality of connection pins for selectively electrically interconnecting a respective first terminal and a respective contact pin within said respective receptive apertures.

5,586,909

SEALING STRUCTURE FOR A PANEL-MOUNTED ELECTRICAL CONNECTOR

Toshikazu Saba, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Yokkaichi, Japan


Filed Nov. 23, 1994, Ser. No. 347,143

Claims priority, application Japan, Nov. 25, 1993, 5-067943
U: Nov. 26, 1993, 5-068073 U

Int. Cl.⁶ H01R 13/52; 13/74

U.S. Cl. 439—559

11 Claims



1. A sealing structure for a panel-mounted electrical connector comprising:

a panel having a mounting hole therein;

first and second connector housings fitted into said mounting hole formed in said panel from opposite sides of the panel such that said panel is interposed between said first and second connector housings, said second connector housing having a peripheral edge, and said first connector housing having a portion thereof extending through said mounting hole, said portion forming an end face; and

an annular sealing member mounted on said peripheral edge of said second connector housing, said annular sealing member

comprising a plurality of annular abutting faces abutting one side of said panel and an annular inner seal engaging said end face of said portion of said first connector housing.

5,586,910

CLAMP NUT RETAINING FEATURE


James Del Negro, Woodbury; Russell Brown, Oakville, and Roger Avery, Danbury, all of Conn., assignors to Amphenol Corporation, Wallingford, Conn.

Filed Aug. 11, 1995, Ser. No. 514,227

Int. Cl.⁶ H01R 17/04

U.S. Cl. 439—584

6 Claims



1. A retention assembly for two relatively movable members in an electrical connector, comprising:

- a first member having a longitudinal axis, said first member having
 - a first end portion including a first inner peripheral surface with a first diameter,
 - a second end portion including a second inner peripheral surface with a second diameter smaller than said first diameter, a third inner peripheral surface having a third diameter smaller than said second diameter,
 - a first radially extending axially facing interface between said first inner peripheral surface and said second inner peripheral surface, said interface including a protrusion extending axially therefrom, and
 - a second radially extending axially facing interface between said second inner peripheral surface and said third inner peripheral surface; and
- a second member having a longitudinal axis adapted to fit within said first member, said second member including
 - a first end,
 - a second end,
 - a tapered inner peripheral surface and a first outer peripheral surface at said first end with a fourth diameter adapted to cooperate with said first inner peripheral surface;
 - a second outer peripheral surface at said second end with a fifth diameter adapted to cooperate with said second inner peripheral surface,
 - a third outer peripheral surface located between said first and second outer peripheral surfaces with a sixth diameter smaller than said fourth and fifth diameters, said third outer peripheral surface forming the bottom of a slot located in the second member between said first and second outer peripheral surfaces, said slot adapted to receive said protrusion after it is radially deformed by axial pressure, said protrusion and said slot adapted to cooperate such that the second member may move axially within said first member.

5,586,911

SHIELDING DATA CONNECTOR

Mitchell E. Miller, Clemmons; Julian J. Ferry, Kernersville, both of N.C.; Brian E. Kiltbey, Chesham, England; Bruce S. Coolbear, East Barnet, England, and Richard F. Gandy, St. Albans, England, assignors to The Whitaker Corporation, Wilmington, Del.


Continuation of Ser. No. 101,529, Aug. 3, 1993, abandoned, which is a continuation-in-part of Ser. No. 941,526, Sep. 8, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 484,099

Claims priority, application United Kingdom, Nov. 3, 1992, 9222960; Dec. 29, 1992, 9227064; Feb. 22, 1993, 9303502

Int. Cl.⁶ H01R 4/24

U.S. Cl. 439—607

3 Claims



1. An electrical connector for data transfer, comprising:
- an insulative terminal support housing having a terminal support platform, defining a mating face and a wire connecting face and an open upper face;
 - a plurality of terminals positioned laterally along the terminal support platform, with a contact section disposed adjacent the mating face, and a wire connecting section adjacent the wire connecting face;
 - a wire stuffer cap, positionable over the wire connecting sections of the terminals, and having wire positioning grooves for initial retention of the wires to be terminated, the wire stuffer cap enclosing said wire connecting sections along a length thereof, said wire stuffer cap further comprising a slot extending along a length of said cap, and extending between at least two said terminals; and
 - shielding members comprised of a lower shield and an upper shield, said upper shield including an integral cross talk shield which is profiled for receipt within said slot, to provide a cross talk shield between the wire connecting sections of said at least two terminals.

5,586,912

HIGH DENSITY FILTERED CONNECTOR

Robert A. Eslampour, Norwalk; Robert J. Shiley, II, Monroe, and Allan W. Hendry, Norwalk, all of Conn., assignors to Burndy Corporation, Norwalk, Conn.

Continuation of Ser. No. 973,827, Nov. 9, 1992, abandoned.


This application Mar. 28, 1995, Ser. No. 411,397

Int. Cl.⁶ H01R 13/66

U.S. Cl. 439—620

31 Claims

1. A filtered electrical connector comprising:
- an electrically conductive housing;



a plurality of filtered contacts located, at least partially, in the housing, the filtered contacts each including a ceramic tubular capacitor; and

at least one ground plane member having a center section and legs extending outwardly from the center section, the center section having receiving areas with each of the capacitors being located in one of the receiving areas and making electrical contact thereat, all of the receiving areas, at least along one side of the center section, each having a separate one of the legs proximate thereto, each leg having a bend proximate the center section and an end that contacts the housing.

5,586,913

S TO B WATTHOUR METER SOCKET ADAPTER


Darrell Robinson, Highland Township; Karl Loehr, Novi; Allen V. Pruehs, Howell, and Robert O. Learmont, Walled Lake, all of Mich., assignors to Ekstrom Industries, Inc., Farmington Hills, Mich.

Continuation of Ser. No. 334,562, Nov. 4, 1994, which is a continuation-in-part of Ser. No. 215,915, Mar. 22, 1994, abandoned, and Ser. No. 216,261, Mar. 22, 1994, abandoned. This application Jan. 11, 1995, Ser. No. 371,015

Int. Cl.⁶ H01R 25/00

U.S. Cl. 439—638

32 Claims



1. A wathour meter socket adapter for mounting a wathour meter having a plurality of outwardly extending blade terminals in a wathour meter socket including a plurality of terminals connected to electrical power line and load conductors, the wathour meter socket adapter comprising:

- a housing having a base and an annular sidewall extending from the base and terminating in a wathour meter mounting flange;

a plurality of rigid electrical conductors disposed within the housing, each electrical conductor having first and second ends;

an electrical contact mounted on the first end of each electrical conductor for receiving one blade terminal of a wathour meter therein, each electrical contact including:

- first and second spaced contact clips disposed in registry with each electrical conductor;
- biasing means, engageable with each of the first and second contact clips, for biasing an end of each of the first and second contact clips toward each other; and
- means for fixedly joining the first and second contact clips and the biasing means to the electrical conductors;

an aperture formed in the sidewall; and

a portion of each electrical conductor and the second end of each electrical conductor extending through the aperture externally from the housing for electrical connection of the second end of each electrical conductor to one terminal in a wathour meter socket.

5,586,914

ELECTRICAL CONNECTOR AND AN ASSOCIATED METHOD FOR COMPENSATING FOR CROSSTALK BETWEEN A PLURALITY OF CONDUCTORS


George H. Foster, Jr., deceased, late of Winston-Salem, N.C., and Donald L. Metzger, Harrisburg, Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed May 19, 1995, Ser. No. 444,501

Int. Cl.⁶ H01R 23/02; 4/24

U.S. Cl. 439—676

23 Claims



1. An electrical connector comprising:
- a housing defining a cavity which opens through a front surface of said housing, said housing comprising a rear surface, opposite the front surface, defining a plurality of apertures extending therethrough; and
 - a plurality of elongate conductors positioned at least partially within the cavity defined within said housing, each of said conductors having a resilient contact portion at a first end and an insulation displacement contact portion at a second end, opposite the first end, extending through an aperture defined in the rear surface of said housing, each of said conductors having a respective substantially constant width, wherein said plurality of conductors include first and second elongate conductors which extend in a substantially parallel, laterally spaced relationship from their respective first ends to a predetermined crossover location where the first and second conductors laterally cross without establishing electrical contact therebetween, and wherein each conductor of a laterally spaced-apart pair of said conductors has a respective portion which is wider than its said substantially constant width, and said wider portions are positioned in an overlapping, vertically spaced relationship at a predetermined location spaced apart from the crossover location to compensate for crosstalk between said plurality of conductors.

5,586,915


ELECTRICAL CONNECTOR WITH CONTACTS AT DIFFERENT INSERTION DEPTHS

Ronald J. Baker, York; Douglas G. Fisher, Boiling Springs; Martha L. Rupert, Hummelstown, and David M. Swartz, York, all of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Dec. 20, 1994, Ser. No. 359,497
Int. Cl.⁶ H01R 23/70

U.S. Cl. 439—733.1

7 Claims



1. An electrical connector comprising: multiple electrical contacts extending axially along respective contact receiving cavities in an insulating housing upon insertion of said contacts therein from an insertion face toward a mating end of the housing, wherein at least two transverse marker surfaces on the housing are positioned at different depths along an axis of the housing and exposed to said insertion face to be engageable by insertion tooling to limit travel thereof during contact insertion, and wherein each of said electrical contacts is provided with at least one respective tool-engageable transverse marker surface that is, upon contact insertion, in coplanar nonabutting relationship with respect to selected one of the housing marker surfaces depending upon the desired depth of insertion of the contact into the housing.

5,586,916

WATERPROOF COVER FOR CONNECTOR


Yasuhisa Shinji; Kazuhiko Morishita, and Hiraji Takase, all of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan

Filed Apr. 4, 1995, Ser. No. 415,986
Claims priority, application Japan, Apr. 15, 1994, 6-077257
Int. Cl.⁶ H01R 13/514; 13/56; 13/58

U.S. Cl. 439—752

9 Claims

1. A waterproof cover for a connector, which comprises: a rear holder portion attached to a rear portion of a connector housing and holding terminals to be inserted into terminal insertion holes of the connector housing from a rear side of the connector housing; and a waterproof cover portion attached to a rear side of said rear holder portion and covering wires extending rearwardly from the terminals, said waterproof cover portion having: a pair of first and second cover halves, a front end surface of said first cover half being formed integrally with an outer circumference of said rear holder portion so as to form an end surface plate of said first cover half along substantially the entire circumference of said first cover half;



a hinge integrally connected to each of said first and second cover halves and linking said first and second cover halves so as to be opened and closed relative to each other; and a lock mechanism locking a pair of said first and second cover halves when said two cover halves are closed.

5,586,917


CONNECTOR HAVING AN ASCERTAINMENT HOLE FOR VISUALLY CHECKING ENGAGEMENT

Sakai Yagi; Tamio Watanabe, and Toru Nagano, all of Shizuoka, Japan, assignors to Yazaki Corporation, Tokyo, Japan

Filed Mar. 17, 1995, Ser. No. 405,855
Claims priority, application Japan, Mar. 17, 1994, 6-047156
Int. Cl.⁶ H01R 13/514

U.S. Cl. 439—752

4 Claims



1. A double engagement connector, comprising: a connector housing comprising a plurality of longitudinally and laterally arranged terminal accommodation chambers and first engagement means for engaging a plurality of terminals inside the terminal accommodation chambers; and a second insertion engagement means for engaging the terminals when the second insertion engagement means is inserted into the connector housing, wherein

said connector housing comprises at least one engagement pin insertion hole provided on an outer peripheral surface of said connector housing for communicating said plurality of terminal accommodation chambers aligned in a row, said second insertion engagement means comprising at least one engagement pin for engaging the terminals in the terminal accommodation chambers when the at least one engagement pin is inserted in the at least one engagement pin insertion hole, said second insertion engagement means also comprising a connecting section for connecting base end portions of the at least one engagement pin at intervals corresponding to an arrangement of the at least one engagement pin insertion hole, and said connector housing comprising at least one ascertainment hole penetrating through a position where an end of the at least one engagement pin inserted in the at least one engagement pin insertion hole is disposed so that the end of the at least one engagement pin can be visually observed through the at least one ascertainment hole.

5,586,918


CONNECTOR HAVING A GRID FOR SECONDARY LOCKING OF TERMINALS

Gilles Chemin, Toulouse, France, assignor to Framatome Connectors International, Paris, France

Filed Dec. 19, 1995, Ser. No. 574,965
Claims priority, application France, Dec. 19, 1994, 94 15245
Int. Cl.⁶ H01R 13/514

U.S. Cl. 439—752

5 Claims



1. A connector designed to be coupled to a complementary connector by plugging, comprising: an insulating body of rectangular cross-section formed with at least one row of passages extending parallel to a plugging direction, each said passage being formed with a backwardly directed shoulder, at least one side wall of each of said passages being cut out to form a detent whose resilience tends to hold a catch in a position in which it projects into the respective passage; a plurality of contact terminals received in said passages and each sized to be retained by the respective catch against the respective shoulder; and a unitary locking grid dimensioned to be fitted against a front end face of said body, having an end wall designed to contact the front end face and formed with holes in registry with the passages, two side flanks that are spaced apart so as to straddle two walls of the body which are orthogonal to the row, and two side flaps that are connected to the end wall by flexible portions, and that are designed to contact outside walls of the body which are parallel to the row, each said side flap having a plurality of end internal extensions for penetrating through windows in said insulating body to retain the grid and lock the terminals of said row, said flaps being shaped to prevent the catches from moving away from a position in which they project into the passages.


5,586,919

BATTERY CONNECTOR

John D. Ritson, 12 Northwoods Rd., Granby, Conn. 06060
Filed Apr. 3, 1995, Ser. No. 414,419
Int. Cl.⁶ H01R 4/38

U.S. Cl. 439—757

9 Claims



1. A releasable connector for electrically connecting a cable to a generally cylindric battery post comprising: a body portion adapted for substantially surrounding and clamping the connector to a generally cylindric battery post; a cable attachment portion connected to said body portion for conducting electricity between said body portion and a cable; the structure of said body portion being comprised solely of a strip of sheet metal configured to create opposed partially cylindrical section shapes normally inwardly biased in compression towards one another for clamping about a substantially cylindric battery post; and means associated with each of said partially cylindrical section shapes for moving the normally inwardly biased partially cylindrical section shapes apart from one another from an otherwise compressing condition about a battery post.

5,586,920


BLADE RECEPTACLE

Donald C. Brown, Freehold, N.J., assignor to Heyco Stamped Products, Inc., Toms River, N.J.

Filed Feb. 17, 1995, Ser. No. 389,946
Int. Cl.⁶ H01R 11/22

U.S. Cl. 439—857

8 Claims



1. A three sided stamped metal female blade receptacle for a molded plastic plug said receptacle including a longitudinal opening for engaging a variety of male blade variants within its length and providing full line side contact on one side and full surface contact on another side to an engaged blade, said receptacle comprising a crimp end and a blade receiving portion, said crimp end including a pair of crimp arms, said blade receiving portion including a flat side; a curved side; and a back portion, said flat side and curved side extending longitudinally and substantially on a perpendicular plane from said back portion and substantially the length of said blade receiving portion, said curve of said curved

side longitudinal and convex within said blade receiving portion; and resilient and spring biased, said sides each having longitudinal edges, said longitudinal edges straight and substantially parallel to each other and substantially the same height.


5,586,921

WATERCRAFT

Noboru Kobayashi; Tomoyoshi Koyanagi, and Keijiro Ikeda, all of Iwata, Japan, assignors to Yamaha Hatsudoki Kabushiki Kaisha, Iwata, Japan
Division of Ser. No. 997,599, Dec. 28, 1992, Pat. No. 5,449,305. This application May 22, 1995, Ser. No. 446,282
Claims priority, application Japan, Dec. 28, 1991, 3-359432
Int. Cl.⁶ B63H 1/00

U.S. Cl. 440—38

21 Claims



1. A small watercraft comprising a hull having a pair of chines which connect side surfaces of the hull with a hull bottom surface, said hull bottom surface including at least first and second stripes with said first stripe being disposed between one of said chines and a center of said hull and the second stripe being disposed between the other chine and the center of said hull, and a pair of propulsion devices supported within the hull in an area disposed between said first and second stripes, said propulsion devices include intake ports disposed between said first and second stripes, and the distance between said first stripe and the closest of said intake ports is greater than a distance between said first stripe and the closest chine.


5,586,922

WATERCRAFT

Noboru Kobayashi; Tomoyoshi Koyanagi, and Keijiro Ikeda, all of Iwata, Japan, assignors to Yamaha Hatsudoki Kabushiki Kaisha, Iwata, Japan
Division of Ser. No. 997,599, Dec. 28, 1992, Pat. No. 5,449,305. This application Feb. 27, 1995, Ser. No. 394,458
Claims priority, application Japan, Dec. 28, 1991, 3-359432
Int. Cl.⁶ B63H 21/00

U.S. Cl. 440—88

16 Claims



1. A small watercraft having a hull, a pair of engines disposed in side by side relationship in said hull, each of said engines having

an exhaust pipe, a single waterlock disposed device comprised of a unitary outer housing within said hull along the longitudinal center line of said watercraft and positioned at one end of said engines, said waterlock device having a pair of exhaust gas inlets each for receiving the exhaust gases from a respective of said exhaust pipes and at least one discharge for discharging the exhaust gases to the atmosphere, said waterlock device unitary outer housing being provided within an internal trap for precluding the entry of water into said exhaust pipes from said waterlock device.

5,586,923


TOY VEHICLE PLAYSET FOR THERMOCHROMIC VEHICLES

Keith A. Hippely, Manhattan Beach; Larry R. Wood, Redondo Beach; Brian E. Walsh, Mission Hills, and Terence A. Choy, Lawndale, all of Calif., assignors to Mattel, Inc., El Segundo, Calif.

Filed Feb. 9, 1995, Ser. No. 388,224
Int. Cl.⁶ A63H 33/00; 3/00; 3/52; 18/00

U.S. Cl. 446—14

13 Claims



1. For use in combination with a toy vehicle having at least a portion thereof bearing a thermochromic material, a toy vehicle playset comprising:
a trackway for guiding a toy vehicle along a travel path having an entrance gate and an exit gate;
a tank unit having at least two tank portions each having a ramp passing therethrough; and
a base supporting said tank unit between said entrance gate and said exit gate having means for aligning a selected one of said ramps within a selected one of said at least two tank portions within said travel path.
said at least two tank portions each receiving quantities of different temperature liquid such that said toy vehicle traversing said selected one of said ramps is exposed to the liquid within said selected one of said at least two tank portions.

5,586,924

TOY CAR STRUCTURE



Tien F. Huang, Taipei, Taiwan, assignor to Wen Ho Tsai, Taipei, Taiwan

Filed Jan. 25, 1996, Ser. No. 591,811
Int. Cl.⁶ A63H 29/22

U.S. Cl. 446—462

7 Claims

1. A toy car structure comprising:
a fixed casing including a chassis and a fixed outer housing secured thereon, a power wheel assembly being disposed under a bottom side of the chassis and multiple decorative wheels being disposed on lateral sides thereof, a hook portion being disposed at one end of the fixed outer housing;
a movable casing including a movable outer housing and an inner decorative housing secured therein, the end of the outer housing being pivotally connected with the top of the fixed outer housing by a pivot shaft, a movable door held by a



restoring spring being disposed on an outer side of the inner decorative housing and outwardly pivotable for showing the inner decorative housing; and
a driving mechanism including a power source fixed in the fixed casing to output power through two driving wheels and a movable rotary shaft, each driving wheel being disposed with an outer flange and inner flange, the outer flange driving a linkage assembly connected to the end of the inner decorative housing to push the movable casing open the middle portion of the movable rotary shaft being supported on the chassis and one end thereof being intermittently pressed by the inner flange of the driving wheel so as to change the engagement between the movable rotary shaft and the power wheel assembly for intermittent rotation and running.

5,586,925


APPARATUS AND METHOD FOR PROCESSING MARBLE

Anthony DiNoria, Sr.; Anthony DiNoria, Jr., and Donato L. DiNoria, all of 702 7th Ave., Lake Worth, Fla. 33463, assignors to Donato DiNoria; Anthony DiNoria, Jr., and Anthony DiNoria, Sr., all of Lake Worth, Fla.

Filed Apr. 8, 1994, Ser. No. 225,379
Int. Cl.⁶ B24B 1/00

U.S. Cl. 451—35

11 Claims



1. A method for surface treating marble to produce a weathered appearance comprising the steps of:

- selecting a group of marble materials having similar hardness;
- depositing said marble materials in a drum having an interior stone lined surface;
- placing silica sand into said drum;
- adding water into said drum;
- adding clay to said drum;
- rotating said drum for a predetermined period of time dependent upon the hardness of said marble materials;
- removing said marble materials from said drum; and
- slicing said marble materials along a longitudinal length thereof to provide two separate marble pieces with weathered veneer surfaces and flat mounting surfaces.

5,586,926

METHOD FOR TEXTURING A METALLIC THIN FILM


Eric D. Wedell, White Bear Lake, and Darlene N. Strecker, Oakdale, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.
Filed Sep. 6, 1994, Ser. No. 301,254

The portion of the term of this patent subsequent to Aug. 31, 2012, has been disclaimed.

Int. Cl.⁶ B24B 29/00

U.S. Cl. 451—59

19 Claims



1. A method for texturing a surface of a metallic thin film of a magnetic disk substrate comprising the steps of:

- frictionally contacting said surface of said metallic thin film with an abrasive article, wherein the abrasive article comprises an abrasive coating including a water-soluble binder material and abrasive particles, wherein said abrasive coating is adhesively attached to a flexible foraminous fibrous backing; and
- abrading said surface of said metallic thin film by moving said metallic thin film and said abrasive article relative to one another with said abrasive coating being in contact with an aqueous liquid solution to form scratches in said surface of said metallic thin film, wherein said liquid solution is free of abrasive particles before said contact with said abrasive coating.

5,586,927

CONSTANT CONCENTRATION RINSEABLE SLURRY DEVICE


William G. Herbert, Williamson, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Nov. 30, 1994, Ser. No. 351,100
Int. Cl.⁶ B24C 9/00

U.S. Cl. 451—88

9 Claims

- A honing system for a substrate comprising:
a slurry containment tank for retaining a slurry of a liquid and a solid, including an opening and a bottom, containing an amount of the slurry;
an independent source of the liquid;
means for mounting and moving the substrate;



means for forcibly conducting the slurry against the substrate, the slurry conducting means connected to the slurry containment tank to receive the slurry;

means for forcibly conducting the liquid against the substrate, the liquid conducting means connected to the independent source of the liquid to receive the liquid;

a containment booth, connected to the opening of the slurry containment tank, enclosing the slurry conducting means, the liquid conducting means, and the substrate;

means for mixing the slurry in the slurry containment tank;

a drain;

means for separating the liquid from the slurry contained in the slurry containment tank wherein the separation means has an upper end and a lower end, the lower end is submerged in the slurry contained in the slurry containment tank, the upper end is secured at a predetermined vertical level relative to the vertical level of the bottom of the slurry containment tank, and the upper end is connected to the drain,

wherein the separation means is submerged in the slurry contained in the slurry containment tank up to the level of the upper end; and

wherein the mixing of the slurry by the mixing means causes the separation means to vibrate.

5,586,928

GRINDING APPARATUS WITH TOUCH-TOP WORK SURFACE


Richard K. Wland, Birmingham, and Dennis R. Buschmohle, St. Clair Shores, both of Mich., assignors to Inland Craft Products Co., Madison Heights, Mich.

Continuation-in-part of Ser. No. 271,135, Jul. 6, 1994, Pat. No. 5,549,509. This application Dec. 4, 1994, Ser. No. 353,086

Int. Cl.⁶ B24B 7/00

U.S. Cl. 451—177

16 Claims



16. A grinding wheel assembly to be secured to a drive shaft of an electric motor associated with a grinding apparatus, said grinding wheel rotating upon rotation of the drive shaft, said grinding wheel assembly comprising:

a core element including a first cylindrical portion of one diameter and a second cylindrical portion of another diameter, said one diameter of the first cylindrical portion being greater than the another diameter of the second portion so as to define a shoulder therebetween, said first cylindrical portion including an internal bore for accepting the drive shaft in a friction type engagement, said first cylindrical portion further including a set screw positioned within an opening in the first cylindrical portion that allows the core element to be secured to the drive shaft, said second cylindrical portion including an external threaded portion; and

a cylindrical grinding element including an internal bore having an internal threaded portion, said grinding element further including an outer layer of an abrasive grit, wherein the grinding element is threadably engageable with the second cylindrical portion of the core element to be in contact with the shoulder.

5,586,929

PRECISION CUT OFF MACHINE


Hayden L. Butcher, and Karen N. Butcher, both of 21699 Swan Creek Rd., Merrill, Mich. 48637

Filed Nov. 23, 1994, Ser. No. 344,508

Int. Cl.⁶ B24B 3/00

U.S. Cl. 451—213

20 Claims



1. A precision cut-off machine for cutting workpieces made from hard materials comprising a frame, a spindle rotatably journaled on the frame for rotation about a spindle axis of rotation, a motor supported by the frame and spaced from the spindle, a torque transmission drive connecting the motor to the spindle that is operable to rotate the spindle, a flexible abrasive cutting disk secured to the spindle and rotatable with the spindle, a fixed workpiece support pivotally attached to the frame adjacent to the flexible cutting disk for pivotal movement about an axis parallel to the spindle axis that is operable to support a workpiece while the workpiece is manually held and advanced to the flexible cutting disk, a slot in the fixed workpiece support perpendicular to the spindle that receives a portion of the flexible cutting disk, and a coolant wand adjustable supported on the frame adjacent to the flexible cutting disk, and a coolant pump connected to the coolant wand and operable to supply coolant to the workpiece while the workpiece is supported by the fixed workpiece support and manually advanced toward and cut by the flexible cutting disk.

5,586,930

GRINDING CHIP FITTING TYPE GRINDING PLATE

Teruoki Hayashi, and Yoshio Shibai, both of Kyoto, Japan, assignors to Sanwa Kenma Kogyo Co., Ltd., Kyoto, Japan


Filed Dec. 8, 1995, Ser. No. 569,985

Claims priority, application Japan, Mar. 15, 1995, 7-056277

Int. Cl.⁶ B23F 21/03

U.S. Cl. 451—548

11 Claims



1. A grinding chip fitting type grinding plate comprising a plurality of grinding chips each having a cylindrical mounting portion, a grinding chip mounting plate to which the grinding chips are attached, and a holding plate, wherein

each of said grinding chips is provided with an O-ring attached to the cylindrical mounting portion having a front end to which a diamond chip is bonded, and a projection portion is integrally formed at a rear end of the mounting portion;

said grinding chip mounting plate has a plurality of grinding chip receiving holes which are radially provided, and each of the receiving holes is a stepped hole composed of a mounting portion receiving hole and a projection receiving hole which is radially offset with respect to the mounting portion receiving hole by a predetermined eccentric amount; and

said holding plate has a plurality of holes through each of which the diamond chip passes,

wherein the mounting portion of each of said grinding chips is inserted into the mounting portion receiving hole of said grinding chip mounting plate against the resistance of the O-ring, the projection is rotated so that said grinding chip is fixed to said grinding chip mounting plate, and said holding plate is coupled with said grinding chip mounting plate by attaching said holding plate from the side where the diamond chip exists.

5,586,931

HAND OPERATED CRAB LEG OPENER WITH MULTIANGLED BLADE

Richard M. Williams, Jr., 1719 E. Marks St., Orlando, Fla. 32803

Continuation-in-part of Ser. No. 287,299, Aug. 8, 1994, abandoned. This application Aug. 25, 1995, Ser. No. 519,660


Int. Cl.⁶ A22C 29/02

U.S. Cl. 452—6

25 Claims

1. A hand held utensil adapted to open elongate sections of crab shells and similar objects, said utensil comprising:

- a manually engagable handle,
- a planar blade secured to said handle and extending outwardly therefrom to form a somewhat rounded tip, with the forward portion of said blade adjacent said tip being substantially straight,
- a blade-protecting member secured in a spaced relationship adjacent said substantially straight forward portion of said



blade, with said blade-protecting member extending from said handle for a distance exceeding the length of said blade,

d) an open-ended slot defined between said substantially straight forward portion of said blade and said blade-protecting member,

e) said slot being adapted to receive the shell of a crustacean, such that said blade can cut through the shell as user grasping said handle moves said blade longitudinally along the shell,

f) said blade being multiangled, with a rear portion of said blade extending upwardly from said substantially straight forward blade portion in the direction of the adjacent undersurface of said blade-protecting member, said undersurface having a recess therein into part of which said upwardly extending rear portion of said blade extends, thus to provide assured shell-cutting capability when said blade and recess are brought into contact with the shell of a crustacean.

5,586,932

ENVIRONMENTAL CONTROL AIRHOUSE WITH VARIABLE OUTPUT


Thomas E. Kiser, Fremont, Ohio, assignor to Professional Supply, Inc., Fremont, Ohio

Continuation-in-part of Ser. No. 148,833, Nov. 5, 1993, Pat. No. 5,376,045. This application Dec. 22, 1994, Ser. No. 362,128

Int. Cl.⁶ F24F 7/08

U.S. Cl. 454—229

20 Claims



1. An airhouse for supplying conditioned air in controlled amounts to the interior of a building, comprising:

an enclosure defining a central chamber,

outside air inlet means for allowing air from outside said interior to enter said enclosure central chamber,

a direct fire burner for combusting a hydrocarbon fuel receiving air from said outside air inlet means and supplying said air from said outside air inlet means to said central chamber,

outside air inlet damper means for adjustably controlling the inlet flow area through said outside air inlet means into said central chamber,

return air inlet means for allowing air within said building interior to enter said enclosure central chamber,

return air inlet damper means for adjustably controlling the inlet flow area through said return air inlet means into said central chamber,

blower means mounted to said enclosure having an inlet communicating with said enclosure central chamber and an outlet for discharging air into said building interior, blower speed control means for adjustably controlling the volumetric output rate of said blower means, and damper control means for controlling said outside air inlet damper means and said return air inlet damper means whereby the total airflow area defined by said outside air inlet damper means and said return air inlet damper means provides airflow velocity through said direct fire burner within a range determined to produce proper combustion through a range of settings of said volumetric output rates of said blower means.

5,586,933

HEATING, VENTILATING AND AIR CONDITIONING SYSTEMS


Colin Sawyer, Barming; John Wallis, Warrington, and Peter Bartingale, Margate, all of England, assignors to Hunter Technical Developments Limited, Jersey, Channel Islands
Filed Nov. 2, 1994, Ser. No. 333,557

Claims priority, application United Kingdom, Nov. 2, 1993, 9322559

Int. Cl.⁶ F24F 13/075

U.S. Cl. 454—299

14 Claims



1. A grille for use adjacent an outlet of a heating, ventilating or air conditioning system, the grille comprising a frame and a plurality of blades extending between opposed frame parts, each blade having a spindle which is rotatably supported within opposed slots formed in the opposed parts of the frame, the slots having an open end to permit the insertion of a blade spindle therein and a closed end, the spindle being supported at the closed ends of the slots, the grille further comprising means for retaining the blade spindle in the slots, the retaining means comprising a separate retaining element configured as a substantially planar component mountable on the frame of the grille, the frame defining a channel between two substantially parallel walls and the retaining element being configured to be slidably inserted into the channel upon the frame such that part of the retaining element is located between the two substantially parallel walls and engages the blade spindle when mounted upon the frame and prevents the spindle from moving out of the open ends of the slots.

5,586,934

WALL SAFE


Larry A. Dombrowski, 4281 Cherry Hill Dr., Orchard, Mich. 48323; Daniel S. Goldsmith, 1883 Chipping Way, Bloomfield Hills, Mich. 48302; Judith Goldsmith, 1883 Chipping Way, Bloomfield Hills, Mich. 48302, and Walter J. Goldsmith, 1867 Golf Ridge, Bloomfield Hills, Mich. 48302

Continuation-in-part of Ser. No. 375,299, Jan. 20, 1995. This application Aug. 15, 1995, Ser. No. 515,141

Int. Cl.⁶ F24F 13/06

U.S. Cl. 454—309

8 Claims



1. For use in conjunction with a wall having an air duct and an opening in the wall which connects a room with the air duct, a safe comprising:
a housing having a bottom wall and a pair of spaced side walls which together define an interior, said housing dimensioned to fit within the air duct so that said housing is recessed in said wall and in alignment with the wall opening and so that said bottom wall extends transversely across and covers the air duct;
a grille dimensioned to overlie and cover the wall opening, means for pivotally mounting said grille to said housing so that said grille is movable between a closed position in which said grille overlies and covers the wall opening and an open position in which said housing interior is accessible from the room, and
air passage means formed through one of said walls of said housing for enabling air flow through one of said walls of said housing, said grille and the air duct, wherein said bottom wall of said housing forms a support shelf for items placed in said housing interior.

5,586,935

AIR-DIRECTION ADJUSTING APPARATUS FOR AIR-CONDITIONING EQUIPMENT

Satoru Kotoh, Hyogo; Kiyoshi Sakuma, Shizuoka; Takayuki Yoshida, Shizuoka; Hiromi Sano, Shizuoka; Katuyuki Anki, Shizuoka; Shin'ichi Suzuki, Shizuoka; Hideaki Koizumi, Shizuoka; Kaoru Yamamoto, Shizuoka; Kunio Matsushita, Shizuoka; Kenichi Unno, Shizuoka, and Tomoko Oguma, Shizuoka, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 202,258, Feb. 25, 1994. This application Jun. 7, 1995, Ser. No. 478,879


Claims priority, application Japan, Mar. 5, 1993, 5-045142; Aug. 24, 1993, 5-209419

Int. Cl.⁶ B60H 1/34

U.S. Cl. 454—320

3 Claims

3. A mechanism for controlling the flow of air from an air-conditioning unit, comprising:
two series of guide vanes respectively located adjacent to one another in the center portion of an air outlet of said air-conditioning unit, said two series of guide vanes having a narrow space therebetween, each of said series of guide vanes engaging in rotational movement in opposite directions to thereby adjust a direction of said flow of air, each of said



guide vanes having a series of cavities formed on a surface thereof for receiving dew.

5,586,936

AUTOMATED GAMING TABLE TRACKING SYSTEM AND METHOD THEREFOR


Michael J. Bennett, Las Vegas; John E. Nino, and Brian D. Todoroff, both of Henderson, all of Nev., assignors to Mikohn Gaming Corporation, Las Vegas, Nev.

Filed Sep. 22, 1994, Ser. No. 310,718

Int. Cl.⁶ A63F 1/18

U.S. Cl. 463—25

19 Claims



1. An automated gaming table tracking system for a gaming table on which is played a plurality of games for a predetermined type of game, said gaming table including a playing surface, a plurality of player positions, and an operator position, said playing surface having playing areas for the operator and for each of the plurality of player positions, said automated gaming table tracking system comprising:

- a sensor located in the playing area of the operator position for sensing when a game is played;
- a plurality of player identity cards, each of said player identity cards containing identity information on the player assigned to said player identity card;
- a plurality of player station controls, one of said plurality of player station controls located at each of said plurality of player positions, each of said player station controls including:
 - (a) means for identifying the player position corresponding to the player station control,
 - (b) means for reading said player identity information from said player identity card when the said player identity card is inserted in said reading means,
 - (c) means for displaying a plurality of predetermined messages,
 - (d) means for signaling an indication when said player identity card is inserted in said reading means,
 - (e) means connected to the identifying means, the reading means, the displaying means, and the signaling means for

processing the player position, the player identity information, the plurality of predetermined messages, and the indication, and

(f) means connected to the processing means for providing external communication to and from said player station control,

a central distribution control connected to the external communication providing means of each of said plurality of player station controls, said central distribution control including:

- (a) means for identifying the gaming table,
- (b) first means connected to the sensor for receiving a game-being-played signal,
- (c) second means connected to the external communication providing means for receiving from each of said plurality of player station controls for at least receiving the player position and the player information for each player control station reading an inserted player identity card, and
- (d) means connected to the gaming table identifying means and the first and second receiving means for determining the start and end of each of the games and the beginning and termination of play by each player at each player position;

a host computer connected to said central distribution control for storing the player identity information and the player position for each player station control, the start and end of each of the games, and the beginning and termination of play at each player position;

means connected to said host computer for printing a player tracking card for each player having a player identity card inserted into a player station control, including:

- (a) the player identity information,
- (b) blanks for in-session gaming information; and

means connected to said host computer for reading each said player tracking card when each said player tracking card has the blank in-session gaming information filled in, said host computer storing said read in-session gaming information corresponding to the player identity information.

5,586,937

INTERACTIVE, COMPUTERISED GAMING SYSTEM WITH REMOTE TERMINALS

Julian Menashe, 54 Copley Park, London SW16 3DB, United Kingdom


Filed May 19, 1994, Ser. No. 252,538

Claims priority, application South Africa, May 19, 1993, 93/3483

Int. Cl.⁶ A63F 9/22

U.S. Cl. 463—41

17 Claims




1. A gaming system including a host computer, a plurality of terminal computers forming player stations remote from the host computer, communicating means for connecting each of the terminal computers to the host computer, and program means for operating the terminal computers, the host computer and the communicating means wherein:

- a. each terminal computer has a processor, a video display unit connected to the processor, a data entry means connected to the processor and a terminal communicating means connected to the processor, the communicating means being operable to connect the terminal computer to the host computer via a public telecommunication link;
- b. each terminal computer has terminal program means for:
- establishing communication with the host computer and advising the host computer of a personal password of a player using that terminal computer;
 - generating simulations to reproduce at least one selected game including a player status during playing of the selected game in response to host data packets received from the host computer; and
 - generating terminal data packets, each terminal data packet being representative of a response generated by activating the data entry means at the terminal computer, and sending such packets to the host computer at least each time the data entry means is actuated to generate a valid response; and
- c. the host computer has host program means for:
- generating at least one random number for the selected game being played on a terminal computer that is in communication with the host computer within preset criteria for that selected game in response to at least one valid terminal data packet received from that terminal computer;
 - determining a status for the selected game at least when a predetermined number of random numbers have been generated for the selected game, including when the selected game has been completed and an outcome for that selected game;
 - storing an account for each password and updating the account associated with the password of the player playing on a terminal computer when the selected game is started and when the selected game is completed, the account being updated in accordance with the amount wagered and the outcome determined by the host computer;
 - verifying the password of the player attempting to establish communication with said host computer via the terminal computer; and
 - generating said host data packets for controlling the simulations to be reproduced by the terminal computer.

5,586,938
TOOTHED TORQUE TRANSMITTING DEVICE HAVING REINFORCEMENT RIBS
 Josef Schürhörster, Rhelne, Germany, assignor to KTR Kupplungstechnik GmbH, Rhelne, Germany
 Filed Feb. 17, 1994, Ser. No. 197,585
 Claims priority, application Germany, Nov. 26, 1993, 9318139 U

Int. Cl. F16D 3/56

20 Claims



1. A device for transmitting torque between a rotary driving component and a rotary driven component, comprising a hub having an axis of rotation and including internal teeth arranged to


transmit torque between said hub and one of said components; a flange surrounding said hub and including a plurality of sets of elongated reinforcing elements, said sets being spaced apart from each other in a circumferential direction of said hub and each of said sets including first and second elements which converge toward each other at an oblique angle radially outwardly of said hub, said first and second elements being at least substantially mirror images of each other with reference to a plane disposed between the first and second elements and including said axis; and means for transmitting torque between said flange and the other of said components.

5,586,939
CONSTANT VELOCITY JOINT WITH SPHERICAL BALL AND TONGUE AND GROOVE INTERCONNECTION
 Louis E. Swinney, 6333 Long, Suite 200, Shawnee, Kans. 66216
 Filed May 25, 1994, Ser. No. 249,301

Int. Cl. F16D 3/16

6 Claims

U.S. Cl. 464-106




1. A constant velocity joint assembly comprising:
 a hollow housing closed at one end to define a cup shaped cavity, the other end of the housing being open to define a housing open end and to provide access into the cavity;
 an output shaft connected to the housing for rotation therewith;
 a rotatably input shaft having an end extending into the cavity through said housing open end and having a longitudinal axis;
 means in the cavity interconnecting the input shaft with the housing for rotating the housing at the velocity of rotation of the input shaft uniformly throughout each revolution despite variations in the angle of alignment of the respective input and output shafts, wherein said interconnecting means includes an insert adapted to be received in said cavity, there being an elongated, arcuate groove in the insert, said groove having an open side facing the input shaft;
 a link having an elongated, rigid, arcuate rib complementally received in said groove for sliding movement of the rib with respect to the groove, the groove and rib being configured for mutual interlocked relationship to prevent relative separating movement of the groove and rib;
 said link having an elongated, rigid, arcuate projection extending transversely to said rib and projecting toward the input shaft;
 an elongated arcuate channel extending across the proximal end of the input shaft with said link projection complementally received therein, the channel and the projection being configured for mutual interlocked relationship to prevent relative separating movement of the channel and the projection;
 whereby the housing and output shaft are operably coupled to the input shaft for rotation thereby through the insert and said link such that the relative sliding of the link rib and projection in the groove and channel respectively allow relative movement of the joint components to provide said uniform velocity irrespective of the angularity between said shafts; and
 seal means interposed across said housing open end and around the input shaft for sealing the cavity against ingress of deleterious materials and egress of lubricant.

5,586,940
GOLF PRACTICE APPARATUS
 Thomas J. Dosch, 83 Briarhill Rd., Orchard Park, N.Y. 14127,
 and Joseph Dosch, 325 Owasco St., Auburn, N.Y. 13021
 Filed Nov. 14, 1994, Ser. No. 339,597
 Int. Cl. A63B 69/36

U.S. Cl. 473-140

15 Claims




1. Golf practice apparatus comprising means for tethering a golf ball, means for dissipating kinetic energy of the golf ball when it is struck, means attached to said energy dissipation means for deriving an initial velocity vector of the golf ball in each of x, y, and z directions in a cartesian coordinate system over the period of time during which the kinetic energy is dissipated including means for measuring and time integrating force components measured in the x, y, and z directions during the period of time whereby the untethered trajectory of the golf ball may be computed.

5,586,941
GOLF PUTTING PRACTICE DEVICE
 Melvin Klearman, 739 Bergerac Dr., Creve Coeur, Mo. 63141
 Filed Jan. 11, 1996, Ser. No. 587,845
 Int. Cl. A63B 69/36

U.S. Cl. 473-160

23 Claims



1. A golf putting practice device which will enable a golfer to practice putts of varying distances and conditions which affect the speed and path of a golf ball on a putting green; the device including:
 a base including a first end and a second end;
 a height indicator arm hingedly connected to the base near said second end;
 a pivotal sub-base which is hingedly connected to said base, said sub-base including a fixed end and a free end, said fixed end being connected to said base intermediate said first end and

said second end of said base, a portion of said base between said base first end and said fixed end of said pivotal sub-base defining a putting section of said device; said pivotal sub-base defining a ball travel surface and having a hole near said free end, said hole being sized to allow a golf ball to fall there-through;


a track including a putting end and a hole end, said track being connected to said base putting section and lying over said pivotal sub-base;

said pivotal sub-base being selectively securable to said height indicator arm at a desired point along said height indicator arm.

5,586,942
TEE DIVIDER FOR GOLF DRIVING RANGE
 Robert Wittek, Sr., Chicago; Aron Cantrell, River Grove, and Terry Sopko, Wood Dale, all of Ill., assignors to Wittek Golf Supply Co., Inc., Chicago, Ill.
 Filed Jan. 23, 1996, Ser. No. 590,166
 Int. Cl. A63B 5/00

U.S. Cl. 473-168

11 Claims




1. A tee divider for a golf ball driving range comprising, a vertically arranged imperforate wall having a canted upper surface, said wall having laterally extending flange means at the base thereof for anchoring the tee divider at the tee sites, a console-like formation connected to an end of said wall and extending forwardly from and aligned with said wall, said formation having a planar surface at the upper end thereof and upwardly opening storage means in said planar surface for holding articles therein, and liquid drainage means connected with said storage means.

5,586,943
GOLF TRAINING DEVICE
 Hailie S. Clay, P.O. Box 326, La Honda, Calif. 94020
 Continuation of Ser. No. 340,250, Nov. 16, 1994, abandoned, which is a continuation-in-part of Ser. No. 134,419, Oct. 8, 1993, abandoned. This application Jan. 24, 1996, Ser. No. 590,616
 Int. Cl. A63B 69/36

U.S. Cl. 473-214



18 Claims

1. A training device mountable to an arm of an athlete for developing a proper arm swing, said arm including first and second arm portions, a first joint between said arm portions and a second joint spaced from said first joint, said training device comprising:
 a support body mountable to said arm of said athlete, sensing means carried by said support body, said sensing means including a first sensor configured for detecting rotation of



said arm relative to said second joint independent of the position of said first arm portion relative to said second arm portion and a second sensor configured for detecting movement of one of said arm portions relative to the other of said arm portions about said first joint, and
signaling means coupled to said sensing means for producing a detectable signal when movement is detected by at least one of said first sensor and said second sensor.


5,586,945
GOLF PUTTING TRAINER
James D. Vonderhaar, 324 Woodside Dr., Bloomington, Ill. 60108
Filed Jan. 22, 1996, Ser. No. 589,299
Int. Cl.⁶ A63B 69/36
U.S. Cl. 473—258
11 Claims



1. A training device for training a golfer to use a putter correctly, the putter having a head and a shaft extending from the head, the training device comprising means for delineating a sight line and means for guiding the shaft as the putter is swung through a limited range, the limited range including an intermediate position, in which the head is positioned in a lowermost position, the limited range including a subrange of back-swing positions, in which the head is raised from the lowermost position, the limited range including a subrange of follow-through positions, in which the head is raised from the lowermost position, the guiding means including a rail defining the limited range and having a guiding surface, along which the shaft is guided with head below the sight line, the rail being curved into a given configuration such that the shaft when guided along the guiding surface is positioned in a position farthest from the sight line when the putter is positioned in the intermediate position with the head positioned in the lowermost position and such that the shaft is positioned in positions closer to the sight line when the putter is swung through the subrange of back-swing positions with the head raised from the lowermost position.

3 Claims


5,586,944
GOLF CLUB HEAD
Itsushi Nagamoto; Noburo Sumikawa; Tatsuya Hirakawa, and Tatsuo Nakanishi, all of Shizuoka-ken, Japan, assignors to Yamaha Corporation, Japan
Continuation of Ser. No. 895,210, Jun. 8, 1992, abandoned, which is a continuation of Ser. No. 648,598, Jan. 31, 1991, abandoned. This application Oct. 30, 1995, Ser. No. 550,276
Claims priority, application Japan, Feb. 1, 1990, 2-23240; Mar. 31, 1990, 2-86461
Int. Cl.⁶ A63B 53/02
U.S. Cl. 473—248



1. A golf club, comprising: a shaft
a shell type main body made of fiber reinforced plastic material unsuited for plastic deformation and having a toe side, a heel side and a sole;
a sole piece separably coupled to said sole of said main body; and
a hosel having an upper tubular section for receiving the shaft as an angle with respect to said main body and a lower, easily deformable flattened tongue section adapted to contact said heel side of said main body externally of said main body and being separably coupled to said main body and to said sole piece, said shaft being received in said hosel such that said shaft does not extend into said tongue section and said hosel being made of a metal suited for plastic deformation such that said tongue section of said hosel may be easily deformed with said shaft in said upper tubular section of said hosel to change the angle between said shaft and said main body.


5,586,946
GOLF CLUB HAVING A SEGMENTED, VARIABLE POSITION GRIP ASSEMBLY
Terry M. Haber, El Toro; William H. Smedley, Lake Elsinore, and Clark B. Foster, Laguna Niguel, all of Calif., assignors to Habley Medical Technology Corporation, Lake Forrest, Calif.
Filed Sep. 29, 1995, Ser. No. 537,129
Int. Cl.⁶ A63B 69/36; 53/14
U.S. Cl. 473—295
20 Claims

1. A golf club comprising a cylindrical shaft including a longitudinally extending axis and first and second ends, a club head located at the first end of said shaft, and a grip surrounding the second end of said shaft, said grip having an upper grip member and a lower grip member, each of said upper and lower grip members adapted to be rotated relative to one another around said shaft, and means by which to releasably lock said upper and lower



grip members at the respective positions to which they have been rotated around said shaft.


5,586,947
GOLF CLUBHEAD AND GOLF CLUB FITTED WITH SUCH A HEAD
Patrice Hutin, Annecy le Vieux, France, assignor to Skis Rossignol SA, France
Filed Mar. 21, 1995, Ser. No. 408,162
Claims priority, application France, Mar. 22, 1994, 94 03620; Mar. 22, 1994, 94 03621
Int. Cl.⁶ A63B 53/04
U.S. Cl. 473—324
33 Claims



1. A golf clubhead comprising:
a front strike faces
a sole extending rearwardly from a bottom region of said front strike face; and
vibration damping means provided on at least one surface of the clubhead and comprising constraining means connected to said at least one surface by at least one layer of visco-elastic material, wherein at least one of said constraining means and said at least one layer of visco-elastic material has at least one opening therethrough.


5,586,948
METAL WOOD GOLF CLUB HEAD
Phillip J. Mick, 7831 Alabama, #16, Canoga Park, Calif. 91304
Filed Apr. 24, 1995, Ser. No. 428,779
Int. Cl.⁶ A63B 53/04
U.S. Cl. 473—332
9 Claims

1. A golf club head adapted to be secured to a golf club shaft for use in hitting a golf ball, said club head comprising:



a generally hollow metal shell defining a club head body having vertically spaced top and bottom surface portions interconnected by laterally separated toe and heel side portions and longitudinally spaced back and front end portions, said front end portion being substantially open;
a generally flat sided face plate secured to said shell closing said open front end portion, said face plate having an inner face and an outer face for impacting against a golf ball; and
a shock absorbing and reflecting compression insert made of a hard thermosetting polyurethane material disposed within said generally hollow metal shell and extending between said face plate and said back end portion of said club head body, said polyurethane insert having a generally conical shape with an enlarged diameter base end attached to said inner face of said face plate and a small diameter apex end attached to said back end portion of said club head body whereby upon impact of said face plate against a golf ball, compression shock waves produced in said club head body are absorbed and reflected by said insert.

5,586,949
HOLLOW CLUB HEAD WITH SOLE PLATE SUPPORT STRUCTURE
Yuichi Aizawa, Tokyo, Japan, assignor to Daiwa Seiko, Inc., Tokyo, Japan
Filed Aug. 1, 1995, Ser. No. 510,099
Claims priority, application Japan, Aug. 5, 1994, 6-184399
Int. Cl.⁶ A63B 53/04
U.S. Cl. 473—345
13 Claims



1. A golf club head comprising:
a hollow metal head body having a single internal chamber, said head body having a top surface;
a recess portion formed in a sole portion of said head body, said recess portion having a support portion; and
a sole plate made of material greater in specific gravity than said head body, said sole plate being mounted in said recess portion and contacting with said support portion substantially along an inner surface; wherein


said support portion extends into said single internal chamber no further than a midpoint between said top surface of said head body and said sole portion, and wherein said support portion comprises a plurality of stays extending across said recess in at least two directions and intersecting with each other to form a grid.

5,586,950 GOLF BALL

Seichiro Endo, Akashi, Japan, assignor to Sumitomo Rubber Industries, Ltd., Hyogo-ken, Japan
Filed Dec. 29, 1994, Ser. No. 365,949
Claims priority, application Japan, Dec. 29, 1993, 5-351591
Int. Cl.⁶ A63B 37/12

U.S. Cl. 473—356

6 Claims




1. A golf ball comprising a core and a cover for covering said core, said cover comprising an inner layer cover and an outer layer cover, a stiffness modulus of the inner layer cover being 3,000 to 5,500 kg/cm², a stiffness modulus of the outer layer cover being 1,000 to 2,500 kg/cm², a thickness of the inner layer cover being 0.5 to 2.5 mm, a thickness of the outer layer being 0.5 to 2.5 mm, a total thickness of the inner layer cover and the outer layer cover being 1.0 to 4.5 mm, a base resin of the inner layer cover containing 5 to 100% by weight of an ionomer neutralized with a zinc ion, and a base resin of the outer layer cover containing 5 to 100% by weight of an ionomer.

5,586,951 GOLF BALL

Michihiko Sugiura, Hiratsuka, Japan, assignor to The Yokohama Rubber Co., Ltd., Tokyo, Japan
Filed Jul. 19, 1995, Ser. No. 503,923
Claims priority, application Japan, Jul. 21, 1994, 6-169704
Int. Cl.⁶ A63B 37/14

U.S. Cl. 473—379

13 Claims



13. A golf ball, comprising:
a substantially spherical surface having a plurality of dimples of differing diameter arranged thereon;


twelve spherical regular pentagons and twenty spherical regular triangles arranged on the spherical surface in a manner corresponding to a dodecaicosahedron (12-20 hedron), each pentagon sharing a same asymmetrical dimple pattern thereon, such that an arrangement of dimples extending across the pentagon from each of five sides of each pentagon differs from the arrangement of dimples extending from each of the four other sides thereof, all of the pentagons sharing the same five differing side arrangements; and
six great circle paths arranged about the spherical surface, each great circle path being bounded on one side thereof by a series of five pentagons each of the five pentagons oriented so that each great circle path is bounded on one side thereof by each of the five differing side arrangements, and wherein a sequence of side arrangements along each great circle path is consistent among all six great circle paths.

5,586,952 HYDRAULIC AUTOTENSIONER

Tomoyoshi Izutsu, and Kazuki Kawashima, both of Iwata, Japan, assignors to NTN Corporation, Osaka, Japan
Filed Jul. 25, 1995, Ser. No. 506,564
Claims priority, application Japan, Jul. 26, 1994, 6-174325
Int. Cl.⁶ F16H 7/08

U.S. Cl. 474—110

10 Claims



1. A hydraulic autotensioner comprising a body containing hydraulic oil and having a closed bottom, a plunger having a top and a bottom and being slidably mounted in said body with a gap formed therebetween through which hydraulic oil can leak, said plunger being formed with a rod-receiving hole extending through said top of said plunger, and a return passage extending through said plunger from said rod-receiving hole to said bottom of said plunger, a rod having a bottom end inserted in said rod-receiving hole, a rod spring for biasing said rod in such a direction as to protrude out of said body, a plunger spring for urging said plunger against said bottom end of said rod, and a valve seat provided on a surface of said rod-receiving hole so as to be brought into close contact with said bottom end of said rod, whereby said return passage is opened and closed by axial displacement of said rod relative to said valve seat.


5,586,953 SYSTEM FOR CONTROLLING A CONTINUOUSLY VARIABLE TRANSMISSION IN RESPONSE TO A SENSED WHEEL DECELERATION

Keiju Abo, Yokohama, Japan, assignor to Nissan Motor Co., Ltd., Yokohama, Japan
Filed Jan. 27, 1995, Ser. No. 379,058
Claims priority, application Japan, Jan. 31, 1994, 6-010104; Apr. 11, 1994, 6-072070
Int. Cl.⁶ B60K 41/12

U.S. Cl. 477—47

20 Claims

1. A shift control system, comprising:
continuously variable transmission; and
shift controller which controls a transmission ratio of said continuously variable transmission between a maximum ratio and a minimum ratio when a normal drive range is selected, and




which, when an engine brake range is selected, prevents the transmission ratio from decreasing beyond a shift limit of the engine brake range which is greater than said minimum ratio; wherein said shift control system further comprises a wheel condition sensing means for sensing a revolving condition of a wheel of a vehicle to determine a wheel deceleration, and said shift controller decreases said shift limit of said engine brake range when the wheel deceleration is equal to or greater than a predetermined deceleration value; wherein said shift controller comprises a limit changing means for normally holding said shift limit of said engine brake range equal to a normal limit ratio and changing said shift limit to a modified limit ratio which is smaller than said normal limit ratio when the wheel deceleration is equal to or greater than the predetermined deceleration value, and said wheel deceleration is a rate of decrease of a drive wheel speed of the vehicle with respect to time; and wherein said shift controller comprises a limit restoring means for restoring said shift limit of said engine brake range from said modified limit ratio to said normal limit ratio when said engine brake range is not selected.

5,586,954 CONTROL SYSTEM FOR AUTOMATIC TRANSMISSION

Akihito Iwata, Hekinan; Kazumasa Tsukamoto, Toyota; Kazuhiro Miki, Kariya; Masahiro Hayabuchi, Anjo, and Yoshihisa Yamamoto, Nishio, all of Japan, assignors to Aisin AW Co., Ltd., Japan
Filed Oct. 31, 1995, Ser. No. 551,227
Claims priority, application Japan, Oct. 31, 1994, 6-290570
Int. Cl.⁶ F16H 61/20

U.S. Cl. 477—93

16 Claims



1. A control system for an automatic transmission, the automatic transmission including a speed change unit with an output shaft

and a fluid transmission unit for transmitting the rotation of an engine to the speed change unit, said control system comprising:
a clutch which is applied responsive to selection of a forward running range;
a one-way clutch which becomes locked when said clutch is applied, to establish a forward first speed;
a brake for locking said one-way clutch to prevent reverse rotation of the output shaft of the speed change unit;
a first hydraulic servo including a first piston for applying said clutch by a piston stroke responsive to receipt of an oil pressure;
a second hydraulic servo including a second piston for applying said brake by a piston stroke responsive to receipt of an oil pressure; and
a control unit for controlling the oil pressures fed to said first hydraulic servo, said control unit comprising:
oil pressure feed means for feeding oil pressure to said second hydraulic servo responsive to selection of a forward running range, provided the vehicle is substantially stopped, the engine is idling and the foot brake is engaged; and
pressure reducing means for starting reduction of the oil pressure in said first hydraulic servo upon expiration of a set time period to start transition of the clutch from the applied state to the slipping state, at or after completion of the piston stroke of said second hydraulic servo.


5,586,955 NEUTRAL START MECHANISM FOR A HYDROSTATIC TRANSMISSION

Lee J. Wanie, Horicon, Wis., assignor to Deere & Company, Moline, Ill.

Filed Aug. 11, 1995, Ser. No. 514,279
Int. Cl.⁶ F16H 63/36

U.S. Cl. 477—99

3 Claims



1. A neutral start linkage mechanism for a vehicle having a hydrostatic transmission having a pivotable input control shaft which controls the hydrostatic transmission, said mechanism being operatively coupled with the input control shaft, said mechanism comprising:
an operator engaged control,
a first arm member operatively fixed with the input control shaft of the hydrostatic transmission,
a first engagement member coupled with the first arm member
a second arm member which extends generally at an angle to the first arm member, said second arm member having
a first slot within which the first engagement member is received,
a second slot within which is received a second engagement member which is rigidly fixed with the vehicle during vehicle operation,
said linkage mechanism having forward, neutral and reverse modes; in the neutral mode the input control shaft is in a position whereat the transmission is placed in a neutral non-driving mode and the first and second engagement members are positioned within the end portions of the respective first and second slots; in the forward mode the input shaft has pivoted in a first direction for shifting the transmission to a forward running range;

forward driving mode and the first arm means pivots therewith which forces the first engagement member toward the end portion of the first slot and forces the second arm member to shift relative to the second engagement member such that the second engagement member shifts out of the end portion of the second slot; in the reverse mode the input control shaft is pivoted in a second direction for shifting the transmission to a reverse driving mode and the first arm member pivots therewith such that the first engagement member shifts out of the end portion of the first slot and the second engagement member remains positioned within the end portion of the second slot for generally blocking the second arm member from shifting.

a biasing means extending between the first and second arm members for biasing the linkage to its neutral mode when the operator releases the operator engaged control, and first and second switch means for detecting the presence of the respective first and second engagement members within the end portions of the first and second slots when the linkage mechanism is in the neutral mode, and said switches are operatively connected with the vehicle power source for preventing the power source from being started by the operator when either of the first or second engagement members are not positioned within the end portion of the respective first or second slot.

5,586,956

Patent Not Issued For This Number

5,586,957

ADJUSTABLE LENGTH, ADJUSTABLE WEIGHT, ADJUSTABLE SHOCK ABSORPTION, MULTI PURPOSE EXERCISE POLES WITH ELECTRONICS PACKAGE
William T. Wilkinson, P.O. Box 572, Crownsville, Md. 21032-0572, assignor to William T. Wilkinson, Salem, N.J.
Continuation-in-part of Ser. No. 846,053, Mar. 5, 1992, abandoned. This application Sep. 4, 1992, Ser. No. 941,304

Int. Cl.⁶ A63B 71/00

U.S. Cl. 482-74

22 Claims



1. A pole device for the aiding of forward movement comprising:

- (a) at least one shaft forming a pole, said pole has a top end and a bottom end.

- (b) handle attached to said shaft at the top end of the pole.
(c) means for exercising a user's arms during the course of forward movement of the user's legs, during relative movement of the user's arms with respect to the user's body while said handle is gripped by the user's hand during the course of forward movement of the user's legs.
(d) at least one weight being attached to the outside of said shaft below the handle, or with said weight being dropped in the top of said shaft or said weight being attached as said handle.
(e) said handle is attached to a top end of said device and said handle is capable of being gripped by user's hand, said device having a bottom end, said device being of sufficient length for the user to grip said handle during the course of forward movement while said bottom end of said device touches a ground surface.
(f) the touching of said bottom end with the surface comprising a push off means to assist the user in moving forward and
(g) an electronics package which comprises at least one component selected from the group consisting of a clock, pedometer, stopwatch, pulse meter, hour chime, alarm, am/fm radio, am/fm cassette, cassette, compact disc player and a day and/or date display wherein said electronics package is attached to the top of the shaft.

5,586,958

LOWER LEG EXERCISE DEVICE

Oscar L. Little, Sr., P.O. Box 2621, Danbury, Conn. 06813


Division of Ser. No. 344,944, Nov. 25, 1994, Pat. No.

5,487,711. This application Oct. 16, 1995, Ser. No. 543,557

Int. Cl.⁶ A63B 23/04

U.S. Cl. 482-79

4 Claims



1. A lower leg exercise device, comprising:

- (a) a base member;
(b) two, elongate, parallel plates attached to rotating means mounted on said base member;
(c) support means disposed at distal ends of said plates to accommodate thereon selected weights, said support means comprising posts extending upwardly from upper surfaces of said plates;
(d) a proximal end of each of said posts is rotatably fixedly attached to a horizontal shaft which is journaled in a support fitting attached to a said plate; and
(e) a cylindrical collar is movable between a first, lowered position in which said collar engages both a lower end of said post and said support fitting, thus locking said post in a position orthogonal to said plate when said device is in use, and a second, raised position, permitting said post to be folded

down on said plate for storage or transport when said device is not in use; such that a person standing on said plates, with a foot disposed over each of said rotating means, moves said weights between a first, lowered position and a second, elevated position by alternately flexing and relaxing muscles in the person's lower leg.

5,586,961

AQUATIC EXERCISE EQUIPMENT

Jeffrey T. Qulnt, 6641 Smith Rd., Cincinnati, Ohio 45140

Continuation-in-part of Ser. No. 189,072, Jan. 28, 1994, Pat.


No. 5,378,213. This application Dec. 28, 1994, Ser. No.

365,209

Int. Cl.⁶ A63B 21/008

U.S. Cl. 482-111

50 Claims



5,586,959

EXERCISE MACHINE

Joseph E. Adkins, P.O. Box 7758, Huntington, W. Va. 25776,


and Jeffrey A. Adkins, 174 Iroquois Trail, Ona, W. Va. 25545

Filed Dec. 20, 1995, Ser. No. 575,548

Int. Cl.⁶ A63B 21/00

U.S. Cl. 482-96

8 Claims



6. An exercise machine comprising:

- a support frame including a longitudinal rail;
a handlebar and footrest assembly pivotally attached to said support frame;
a seat assembly including an elongated seat support member and a seat, said seat support member having a proximate end and a distal end, said proximate end pivotally attached to said support frame, said seat attached to said distal end of said seat support member;
a seat riser arm having a first end and a second end, said first end pivotally attached to said seat support member;
a glide assembly attached to said second end of said seat riser arm, said glide assembly riding on said longitudinal rail of said support frame;
adjustable friction means for controlling resistance to motion of said glide assembly along said longitudinal rail; and
a linkage bar having a front end and a rear end, said front end pivotally attached to said handlebar and footrest assembly and said rear end pivotally attached to said seat riser arm.

5,586,960

Patent Not Issued For This Number

5,586,962

MULTIPLE SPORT TRAINING AND EXERCISE APPARATUS

Timothy M. Hallmark, 2799 Kuykendall, Bellville, Tex. 77418

Filed Jan. 26, 1995, Ser. No. 378,399


Int. Cl.⁶ A63B 21/02

U.S. Cl. 482-129

16 Claims

1. A multiple sport training, exercise, and rehabilitation apparatus comprising:

- a frame having two upright members with a plurality of cross bar members between the upright members;
a base stabilizing the frame in a vertical position;
one or more elastic ropes as the means for producing a resistive force, each of said elastic ropes having at least one end attached to the apparatus and the other end of the rope attachable to an exerciser; and
at least one clamp per each elastic rope provided on the frame for releasably engaging the elastic ropes whereby the length of the elastic rope is adjustable thereby producing resistance



by the elastic ropes which may be varied according to the length of elastic rope clamped.

5,586,963

SINGLE-PLY PAPERBOARD TUBE AND METHOD OF FORMING SAME


George E. Lennon, Newport, Tenn.; James R. Martin, and Charles D. Anderson, both of Hartsville, S.C., assignors to Sonoco Products Company, Hartsville, S.C.

Filed Jun. 27, 1994, Ser. No. 265,999

Int. Cl.⁶ B31C 3/00; 3/04

U.S. Cl. 493-299

19 Claims



1. A method of producing a paperboard tube comprising the steps of:

conditioning a continuous paperboard ply defined in transverse cross-section by a pair of thin longitudinal edge portions and a thicker central portion disposed therebetween, each of said thin portions having a predetermined uniform width and a substantially constant thickness, said thicker central portion having a predetermined uniform width substantially greater than the width of said edge portions and a substantially constant thickness that is greater than the thickness of said edge portions, said conditioning raising the moisture content of the paperboard ply by an amount of at least about 1.0 percent, based on the dry weight of the ply;

applying a layer of permanent adhesive layer to a first edge portion on a first side of said conditioned paperboard ply; and spirally winding said paperboard ply onto a mandrel in edge overlapping relation so that the second edge portion of the paperboard ply overlaps the adhesive coated face of the first edge portion, thereby forming a permanently bonded, continuous paperboard tube.

5,586,964

SYSTEM FOR DELIVERING FOLDED PAPER


Walter W. Chase, Glendale, Ariz., assignor to B. Bunch Company, Inc., Phoenix, Ariz.

Filed Nov. 2, 1994, Ser. No. 333,215

Int. Cl.⁶ B31B 3/02; B65H 20/00

U.S. Cl. 493-413

3 Claims



3. Apparatus for producing continuous form stationery by folding a strip of paper along transverse lines of weakening formed therein, said apparatus including

(a) a frame;

(b) guide means mounted on said frame for alternately distributing said successive lines of weakening in said paper in substantially opposite directions;

(c) folding means carried on said frame and operatively associated with said guide means for urging said paper distributed by said guide means into a zig-zag folded condition;

(d) a generally horizontally oriented conveyor assembly for receiving folded paper from said folding means, forming a stack of the folded paper, and carrying said stack of folded paper away from said folding means in a first direction of travel, said stack including

(i) first and second groups of folded edges, said first group of folded edges contacting said conveyor assembly, said second group of folded edges being generally spaced apart from and extending above said first group of folded edges and said conveyor assembly; and

(ii) a plurality of upstanding sheets each bounded by a parallel pair of said folded edges and canted in said first direction of travel, alternating ones of said sheets each being connected to and overlaying the one of said first group of said folded edges connected to the immediately preceding one of said sheets, and laying on and contacting a portion of said immediately preceding one of said sheets extending from said one of said first group of said folded edges such that said portion of said immediately preceding one of said sheets is pressed against said conveyor assembly;

(e) inverting means for turning over said stack of folded paper, said inverting means comprising

(i) means for receiving said stack of folded paper from said conveyor assembly and incrementally displacing said sheets downwardly around to move said stack in a second direction of travel rearwardly from said first direction of travel onto a support surface such that after said stack of folded paper is inverted onto said support surface, said first group of folded edges are spaced above said second group of folded edges, and said sheets in said stack of folded paper are in a substantially upright orientation facilitating feeding said sheets into another paper processing machine; and

(ii) means for contacting, moving, and guiding said second group of folded edges downwardly in said second direction of travel and to facilitate the displacement of said sheets downwardly in said second direction of travel rearwardly from said first direction of travel onto said support surface in said substantially upright orientation.

5,586,965

CENTRIFUGAL SEPARATOR WITH CONICAL BOWL SECTION AND AXIALLY SPACED RECESSES


Benjamin V. Knelson, 20321-86th Ave., Langley, British Columbia, Canada

Filed May 11, 1995, Ser. No. 439,273

Int. Cl.⁶ B04B 11/00; B01D 43/00

U.S. Cl. 494-29

16 Claims



1. An apparatus for separating intermixed materials of different specific gravity comprising:

a centrifuge bowl having a base and a peripheral wall surrounding an axis passing through the base and generally upstanding from the base to an open mouth;

means mounting the bowl for rotation about the axis;

feed means for feeding the intermixed materials into the bowl so that during rotation of the bowl the intermixed materials flow over the peripheral wall for discharge from the open mouth; first guide means for collecting the materials discharged from the open mouth;

at least one annular recess on the peripheral wall over which the materials pass so that heavier material collects in the recess and lighter material passes over the recess to the open mouth for discharge from the open mouth;

said at least one recess being defined by a lower side wall and an upper side wall which extend generally outwardly of the axis to an outer base of said at least one recess;

fluidizing means for fluidizing said heavier material in said at least one annular recess comprising a plurality of openings through the peripheral wall at said at least one recess and fluid injection means outside the peripheral wall for injecting fluid through the openings;

and second guide means for collecting the heavier materials from said at least one recess;

wherein said feed means comprises a feed duct extending into the bowl to a discharge mouth positioned adjacent said base of the bowl such that the feed materials are fed from the discharge mouth to move to the peripheral wall for said flowing movement over the peripheral wall;

and wherein said peripheral wall of the bowl includes a frusto-conical portion which extends axially of the peripheral wall from a lower end on the peripheral wall arranged for receiving said feed materials from the discharge mouth to an upper end of the frusto-conical portion which is axially spaced from the discharge mouth;

said frusto-conical portion being substantially smooth and substantially impermeate and increasing in diameter from said lower end to said upper end;

said at least one recess being arranged such that the lower side wall thereof connects with the upper end of the frusto-conical portion and extends outwardly relative to the axis from the upper end of the frusto-conical portion;

said at least one recess thus being axially spaced from the discharge mouth by at least a part of an axial length of the frusto-conical portion such that the feed materials pass over

said at least a part of the axial length of the frusto-conical portion before reaching said at least one recess.

5,586,966

APPARATUS AND METHOD FOR SEPARATING SOLID/FLUID MIXTURES

Warwick N. Wood, Cheltenham, Australia, assignor to Warman International Limited, Artarmon, Australia

Continuation of Ser. No. 307,777, Oct. 7, 1994, abandoned.


This application Mar. 18, 1996, Ser. No. 616,934

Claims priority, application Australia, Apr. 10, 1992, PL1857

Int. Cl.⁶ B04B 1/20

U.S. Cl. 494-37

12 Claims



1. Apparatus for separating materials into a heavier component and a lighter component comprising:

a main body;

a rotor disposed within said main body, said rotor and said main body being rotatable about axes of rotation; said rotor comprising:

first and second end walls spaced apart from one another with a rotor chamber therebetween, and a plurality of generally radially extending blades extending between said first and second end walls and separating said rotor chamber into a plurality of sub-chambers;

a feed inlet chamber between said main body and said first end wall;

said first and second end walls having a circumferential clearance for permitting the flow of material into and the discharge of the heavier component out of the rotor chamber; and

a generally centrally disposed discharge in communication with the rotor chamber for discharging the lighter component from a radially inner portion of the rotor chamber, said sub-chambers being open in a radially inward direction with respect to the rotor's axis of rotation and being arranged with respect to said centrally disposed discharge so that said lighter component flows in said radially inward direction through said sub-chambers and directly into said centrally disposed discharge.

5,586,967

METHOD AND RECORDING FOR PRODUCING SOUNDS AND MESSAGES TO ACHIEVE ALPHA AND THETA BRAINWAVE STATES AND POSITIVE EMOTIONAL STATES IN HUMANS


Mark E. Davis, 21711 Wesley, Apartment D, Laguna Beach, Calif. 92677

Continuation-in-part of Ser. No. 939,088, Sep. 2, 1992, Pat. No. 5,352,181. This application Jun. 27, 1994, Ser. No. 267,149

Int. Cl.⁶ A61M 21/00

U.S. Cl. 600—28

5 Claims



1. A method for producing an audio tape for use in achieving alpha and theta brainwave states and effecting positive emotional states in humans to enhance learning and self-improvement, said method comprising:

- recording on an audio tape, a musical composition having an initial tempo;
- during recording of the musical composition, reducing the initial tempo over a length of the musical composition until a final tempo is reached at an end of the musical composition; and
- recording on an audio tape, in synchrony with the reducing initial tempo of the musical composition, a plurality of verbal phrases, said verbal phrases being recorded with between one and approximately eight words per phrase, and with pauses between verbal phrases having a duration of between approximately four and approximately eight seconds.

5,586,968

METHOD AND APPARATUS FOR MOVING AN ENDOSCOPE ALONG A CANAL-SHAPED CAVITY

Andreas Gründl, Haseneystrasse 20, D-81377 München; Alexander Bob, Rahfeldstrasse 9A, D-68163 Mannheim, and Konstantin Bob, Weberstrasse 17, D-69469 Weinheim, all of Germany

PCT No. PCT/EP93/03570, § 371 Date Jan. 3, 1995, § 102(e) Date Jan. 3, 1995, PCT Pub. No. WO94/13188, PCT Pub. Date Jun. 23, 1994

PCT Filed Dec. 15, 1993, Ser. No. 284,568
Claims priority, application Germany, Dec. 15, 1992, 42 42 291.4


Int. Cl.⁶ A61B 1/00

U.S. Cl. 600—114

13 Claims

5. An assemblage for examining the interior of a canal-shaped cavity, said assemblage comprising:

- a) an endoscope having a movable distal end for positioning within the cavity, and having an opposite stationary operating end for positioning outside of the cavity;
- b) a turnout tube embracing a portion of the endoscope, said turnout tube having a movable turnout area for positioning within the cavity, and having an opposite fixed end for positioning outside of the cavity;
- c) drive means disposed between said movable distal end and said stationary operating end of said endoscope, said drive means being operable to advance and retract said endoscope in said cavity; and



d) means for providing slack in said endoscope between said movable distal end and said stationary operating end of said endoscope so as to allow said movable distal end of said endoscope to be moved away from said stationary operating end of said endoscope without moving said operating end of said endoscope.

5,586,969

REVERSIBLE SUPPORT BELT


Edward H. Yewer, Jr., 6259 N. Highway 83, Hartland, Wis. 53029

Filed Jun. 16, 1995, Ser. No. 490,928

Int. Cl.⁶ A61F 5/00

U.S. Cl. 602—19

16 Claims



1. In a support belt for wearing around the waist of a human body of the type having a body with an inner surface, an outer surface and longitudinal side edges connecting said inner and outer surfaces, and a cinching strap narrower than said body and having an inner surface, an outer surface and longitudinal side edges connecting said inner and outer surfaces for encircling said body when said belt is worn around the waist of a human body, the improvement wherein:

- said longitudinal side edges of said body are arcuate over the length of said body and curve in the same direction;
- said strap can be detachably removed from said body; and
- said strap includes at least two inextensible and straight strips joined end to end by an intermediate bridging section which is flexible so as to allow said strips to form an angle relative to one another as said strips lay against said body.

5,586,970

ARTICULATING ADJUSTABLE CONDYLAR PAD FOR KNEE BRACE

John Morris, Castro Valley, and Gary Stafford, Hayward, both of Calif., assignors to Orthopedic Technology, Inc., Tracy, Calif.


Filed Jan. 23, 1995, Ser. No. 379,313

Int. Cl.⁶ A61F 5/00

U.S. Cl. 602—26

5 Claims

- 1. An improved knee brace comprising:
- a) a thigh brace portion mountable to the user's upper leg, the thigh brace portion including medial and lateral struts, said struts extending rigidly from said thigh brace portion downward to and through a hinge axis;
- b) a lower leg portion, said lower leg portion including medial and lateral struts extending upwardly from said lower leg portion to and towards a hinge axis on either side of said leg;



a simple hinge mounted between said upper and lower struts on both sides of said knee brace, said simple hinge enabling pivot of said thigh brace portion relative to said lower leg portion along a first substantially horizontal hinge axis between positions of extension and flexion when mounted to the knee of a wearer;

medial and lateral condylar pads pivotally secured to the thigh brace portion of pivotal movement generally along a second substantially horizontal medial and lateral pivot pad axis, parallel to but offset from said first substantially horizontal hinge axis of said simple hinge, said second substantially horizontal medial and lateral pivot pad axis spaced apart from the above first substantially horizontal axis of said hinge of said brace by a distance approximating articulation of said simple hinge axis from said thigh brace portion to follow the changing center of pivot of said knee during extension and flexion of said knee;

each said medial and lateral condylar pads including a first cam slot at said pivot for enabling said pad to move on said pivot towards and away from said pivot; and

each said medial and lateral condylar pads further including a second cam slot between said thigh brace portion and said pad for constraining said medial and lateral condylar pads to move on said pivot towards and away from said pivot to further approximate articulation of said simple hinge axis from said thigh brace portion to follow the changing center of pivot of said knee during extension and flexion of said knee.

5,586,971

INVISIBLE BANDAGE ASSEMBLY


Nancy M. Newman, 819 Spring Dr., Mill Valley, Calif. 94941

Continuation of Ser. No. 964,339, Oct. 21, 1992, Pat. No. 5,368,553, which is a continuation-in-part of Ser. No. 729,463, Jul. 12, 1991, abandoned. This application Nov. 29, 1994, Ser. No. 346,084

Int. Cl.⁶ A61F 13/00; 15/00

U.S. Cl. 602—58

1 Claim



1. A bandage assembly comprising tape, wherein said tape is a three layer laminate consisting of

- (a) an upper paper backing layer,
- (b) an underlying pressure-sensitive adhesive layer which is coterminous in size with said upper paper backing layer, and
- (c) a central wound release layer which does not adhere to wounds or blemishes; is not coterminous in size with said

upper paper backing layer and the underlying pressure-sensitive adhesive layer and thereby providing a peripheral ring of exposed adhesive and further wherein said assembly has a scalloped edge and a removable tab.

5,586,972

CREPE EFFECT BANDAGE

John C. Evans, Newhey, United Kingdom, assignor to Smith & Nephew plc, London, United Kingdom

PCT No. PCT/GB93/00958, § 371 Date Nov. 7, 1994, § 102(e) Date Nov. 7, 1994, PCT Pub. No. WO93/22994, PCT Pub. Date Nov. 25, 1993


PCT Filed May 10, 1993, Ser. No. 331,631

Claims priority, application United Kingdom, May 9, 1992, 9210036

Int. Cl.⁶ A61L 15/00

U.S. Cl. 602—76

21 Claims



1. A woven bandage which exhibits a crepe effect characterised in that the bandage contains textured filament warp yarns and composite warp yarns comprising a staple fibre yarn and a textured filament yarn twisted together.

5,586,973

METHOD AND DEVICE FOR CONTROLLED IRRIGATION AND SUCTIONING OF A LIQUID CLARIFICANT DURING ENDOSCOPIC SURGERY

Ivan Lemaire, St Didier au Mont d'Or, and Bertrand Gonon, Lyon, both of France, assignors to C & D Biomedical S.A., Ecullly, France


Continuation-in-part of Ser. No. 962,210, Dec. 18, 1992, abandoned. This application Dec. 12, 1994, Ser. No. 353,879

Claims priority, application France, Apr. 22, 1991, 91 04969; WIPO, Apr. 22, 1992, PCT/FR92/00362

Int. Cl.⁶ A61M 1/00

U.S. Cl. 604—19

15 Claims



1. Apparatus for the controlled irrigation and suctioning of a liquid clarificant in a cavity or a natural passageway in the human body during a surgical procedure with an endoscopic surgical instrument having an injection conduit for injecting liquid clarificant into the cavity or natural passageway and a suction conduit for suctioning liquid clarificant from the cavity or natural passageway, the apparatus comprising:

- an irrigation branch for connection to the injection conduit of the instrument and a suction branch for connection to the suction

conduit of the instrument, each of said branches having at least one pressure sensor and a pump; the irrigation branch comprises, in sequence commencing from an end of the irrigation branch remote from the instrument: (a) a reservoir (RESE) for storing the liquid clarificant, the reservoir being supported by a first weighing means (DISPE1) for weighing the liquid clarificant contained in the reservoir (RESE); (b) a peristaltic irrigation pump (PIR) with a flow regulator; and (c) a pressure differential sensor block (BCDP) formed by a pair of irrigation pressure sensors (CP1 and CP2), interconnected by a calibrated Venturi conduit (CAB), for measuring a respective pair of irrigation pressure values (P1 and P2);

the suction branch comprises, in sequence, commencing adjacent the outlet of the instrument: (a) a pressure sensor (CPA) to measure downstream pressure (P3); (b) a peristaltic suction pump (PPAS) with a flow regulator; (c) a recovery pump (POR) connected to a recovery branch (BRE), which is in turn connected to a collection device on the operating table; (d) a conductimetric cell (CECO) which measures hemodilution; and (e) a receptacle (RECI) for recovering liquid clarificant, the receptacle (RECI) being supported by a second weighing means (DISPE2) for weighing the liquid clarificant recovered by the receptacle;

the entire system being connected to a central processing and control unit (UCCG) having a flowmeter measurement device (UMDI) for determining an irrigation flow rate (PIR) in the irrigation branch from the difference between the pair of irrigation pressure values (P1 and P2) measured by the pair of irrigation pressure sensors (CP1 and CP2), and a control circuit (CIRP) for controlling the irrigation pump in response to the determined irrigation flow rate (PIR) and thereby controlling an interior cavity pressure (P1) inside the cavity or natural passageway; and

the first and second weighing devices (DISPE1 and DISPE2) are each connected to means for comparing the measurement results of each device with each other, and a reference pressure sensor (CPRE) for measuring a reference pressure is connected to the processing and control unit (UCCG) in order to compare the measured reference pressure with the pressures measured by the other pressure sensors and thereby determine corresponding relative pressures with regard to the reference pressure.

5,586,974

CONTINUOUSLY ADJUSTABLE HIGH FLOW INSUFFLATOR VALVE


Marcus J. Martinez, and Anthony S. Tafuya, both of Albuquerque, N.M., assignors to Olympus America, Inc., Lake Success, N.Y.

Filed Apr. 25, 1995, Ser. No. 428,381

Int. Cl. A61M 37/00

U.S. Cl. 604-26

17 Claims



1. A valve comprising:

- an inlet for receiving fluid flow from a fluid source;
- a chamber fluidly coupled with the inlet;
- a chamber outlet fluidly coupled to the chamber;
- a perforated disk having at least one perforation;
- an outlet;

- a dynamic seal, the dynamic seal having a dynamic seal inlet fluidly coupled with the chamber outlet, and a dynamic seal outlet fluidly coupled with the outlet, and arranged about the perforated disk such that, when the at least one perforation of the perforated disk is aligned with the dynamic seal inlet and the dynamic seal outlet, the dynamic seal inlet is fluidly coupled to the dynamic seal outlet;
- a controllable device for rotating the perforated disk; and
- a pressure sensor for sensing the pressure in the chamber.

5,586,975

AIR AND LIQUID TIGHT CONTAINER WITH A SLIDABLE GASKET

Nobuo Tanaka, Mishima-gun; Seiji Otani, Toyono-gun; Hiroyuki Kawakita, Suita, and Teruo Matsuda, Chiyoda-ku, all of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, and Arte Corporation, Tokyo, both of Japan


Filed Dec. 29, 1994, Ser. No. 365,947

Claims priority, application Japan, Feb. 18, 1994, 6-021485

Int. Cl. A61M 37/00

U.S. Cl. 604-89

10 Claims



1. An apparatus comprising:

- a tubular body having an inside wall, an inside space, a front open end, a rear open end and an inside diameter r ;
- a front gasket slidable in said tubular body, said front gasket separating said inside space into a front compartment and a rear compartment, and each of said compartments having a substance therein;
- a rear gasket that is capable of being connected to a push rod so as to function as a plunger, said front gasket being slidable in said tubular body in response to sliding of said rear gasket in said tubular body;
- a bypass located between said front gasket and said front open end, said bypass having an axial length along said tubular body, and said bypass permitting the substance in said rear compartment to be introduced into said front compartment;
- wherein said front gasket comprises a first front gasket arranged on the rear side of said bypass and a second front gasket arranged behind said first front gasket, said first and second front gaskets being axially slidable independently of each other upon sliding of said rear gasket in said tubular body by the push rod;
- wherein said first and second front gaskets have a combined axial thickness less than said axial length of said bypass such that, when said first and second front gaskets are slid to said bypass, the substance in said rear compartment can be introduced into said front compartment through said bypass;
- wherein each of said front and rear gaskets has at least two annular ribs sealingly engaging said inside wall of tubular body;
- wherein each said annular rib has an uncompressed outside diameter R ; and
- wherein said front and rear gaskets are disposed in said tubular body such that a compressibility C (%) of said ribs, defined as $C = (R-r)/R \times 100$, is in a range of 2% to 10%, inclusive, and the product of the compressibility and the contact area (mm^2) of said ribs with said inside wall of said tubular body is within a range of 150 to 400.

5,586,976

MEDICAL SYRINGE NEEDLE SHEATH HOLDING DEVICE


Vincent M. Coutoumanos, 8512 Steeple Ridge, North Richland Hills, Tex. 76180

Filed Oct. 11, 1995, Ser. No. 540,962

Int. Cl. A61M 5/00

U.S. Cl. 604-192

9 Claims



1. A portable, hand-held pocket safety device for removing and replacing a needle sheath for the needle of a syringe with the risk of contact with the needle minimized, comprising:

- a holder body having a sheath receiving passage formed there-through;
- a plunger means received within said holder body and movable through said holder body, said plunger means including an aperture formed therealong and adapted to be alignable with said sheath receiving passage of said holder body as said plunger means is moved along said holder body; and
- means for automatically biasing said plunger means along said holder body so as to move said aperture of said plunger means away from alignment with said sheath receiving passage upon release of said plunger means, such that said plunger means engages and holds a needle sheath received through said sheath receiving passage.

5,586,977

QUICK DISCONNECT FITTING FOR COUPLING INTERCHANGEABLE PROBE TIP TO LAPAROSCOPIC INSTRUMENT


James H. Dorsey, III, Delray Beach, Fla., assignor to C.R. Bard, Inc., Murray Hill, N.J.

Continuation of Ser. No. 989,109, Dec. 11, 1992, abandoned, which is a continuation-in-part of Ser. No. 470,771, Jan. 26, 1990, Pat. No. 5,188,591. This application Aug. 8, 1994, Ser. No. 286,949

Int. Cl. A61M 5/00

U.S. Cl. 604-264

5 Claims



1. A combination surgical valve and surgical probe, said combination comprising:

- a surgical probe including a probe shaft, said surgical probe further including an attachment member, said attachment member secured to said probe shaft;
- a surgical valve having an inlet and an outlet;

said surgical valve further including a first probe mount member operatively associated with said outlet of said surgical valve; said probe mount member and said attachment member operatively associated with one another, respectively, providing for rapid engagement or disengagement of said surgical probe to said surgical valve;

engaging means including a groove defined by an inner surface portion of said attachment member and a corresponding collar disposed on an outer surface portion of said probe mount member, said groove and said collar operatively associated with each other to provide a frictional engagement between said attachment member and said probe mount member; and an o-ring assembly including a notch defined by an outer surface portion of said probe mount member and a second groove defined by an inner surface portion of said attachment member, said notch and second groove housing an o-ring, when said attachment member is removably secured to said probe mount member said o-ring assembly providing a sealed and aligned relationship between said attachment member and said probe mount member.

5,586,978

INCONTINENCE DEVICE


Donald E. Bayne, 1465 Holton Rd., Muskegon, Mich. 49445

Filed Nov. 7, 1994, Ser. No. 335,106

Int. Cl. A61M 1/00

U.S. Cl. 604-327

19 Claims



1. An incontinence device comprising:

- a tray having a body with an opening that extends through said body;
- an annular ring surrounding said opening and extending away from said body to a terminal edge, said annular ring having an annular groove, said annular groove opening radially outward from said annular ring;
- a flange extending outward from said annular ring to said terminal edge and defining at least a portion of said annular groove, said flange and annular ring formed as a single piece from a moldable material;
- at least one drain operatively connected with said body to drain material from within said tray; and
- a liquid barrier having an aperture extending through said liquid barrier, said liquid barrier being connected with said tray to define a passage through each of said opening and said aperture said liquid barrier at least partially enveloping said tray.


5,586,979

DISPOSABLE ABSORBENT ARTICLE CORE INTEGRITY SUPPORT

Dennis A. Thomas, Cincinnati, Ohio, assignor to The Procter and Gamble Company, Cincinnati, Ohio
Continuation of Ser. No. 149,410, Dec. 16, 1993, Pat. No. 5,397,317. This application Nov. 21, 1994, Ser. No. 342,538
Int. Cl.⁶ A61F 13/15; 13/20

U.S. Cl. 604—382

10 Claims



1. A disposable absorbent article comprising:
a backing sheet of a flexible sheet material;
a plurality of individual columnar projections disposed on said backing sheet, said projections disposed to project generally normal to said backing sheet;
a mass of absorbent material overlying a portion of said backing sheet and penetrated by at least some of said individual columnar projections.

5,586,980


MICROKERATOME

Frederic B. Kremer, 887 Roscommon Rd., Bryn Mawr, Pa. 19010, and Harold E. Clupper, Little Shiloh Rd., West Chester, Pa. 19380

Filed Oct. 14, 1994, Ser. No. 323,177
Int. Cl.⁶ A61F 9/00; A61N 5/06

U.S. Cl. 606—4

44 Claims



39. A micro-keratome device comprising:
a vacuum ring, a cutting blade carrier containing a cutting blade, a guard, and an applanation shoe, wherein said cutting blade carrier, said cutting blade and said applanation shoe are mounted on said vacuum ring; said cutting blade is movable independently of said cutting blade carrier so that after making an incision in a cornea of a patient, said cutting blade can be retracted into said cutting blade carrier; said guard maintains incised portions of said cornea during an ophthalmic

surgical procedure to be performed on said patient and returns said incised portion to said cornea after said surgical procedure; and said micro-keratome provides an unobstructed pathway to layers of said cornea exposed by displacement of said incised portions without removing said cutting blade carrier from said micro-keratome prior to or during said surgical procedure;

wherein said applanation shoe is pivotally connected to said vacuum ring allowing pivoting motion of said applanation shoe in a plane substantially parallel to a plane projected by said applanation shoe as mounted on said vacuum ring;
wherein said cutting blade carrier is pivotally attached to said applanation shoe, allowing said cutting blade carrier to be pivoted out of said unobstructed pathway during said surgical procedure, after said incision is made;
wherein said micro-keratome further comprises a stop to limit the movement of said cutting blade carrier;
wherein said pivotal attachment of said applanation shoe and said pivotal connection of said cutting blade carrier pivot about the same axis, and said cutting blade carrier and said applanation shoe further comprise means for interlocking said cutting blade carrier and said applanation shoe, one with the other, to allow simultaneous movement of said interlocked cutting blade carrier and applanation shoe in a plane substantially parallel to a plane projected by said vacuum ring as said cutting blade makes said incision, said movement traversing from a first position prior to making said incision wherein said cutting blade carrier and said applanation shoe are interlocked, to a second position, after making said incision, at which point said stop limits movement of said applanation shoe and said cutting blade carrier and said applanation shoe remain interlocked; and
said micro-keratome further comprises means for releasing said interlocking means after said incision is made, when said cutting blade carrier and said applanation shoe are at said second position, said releasing means returning said cutting blade carrier to said first position while said applanation shoe remains in said second position.


5,586,981

TREATMENT OF CUTANEOUS VASCULAR AND PIGMENTED LESIONS

Xin-Hua Hu, 109 Squire Dr., Winterville, N.C. 28590, assignor to Xin-Hua Hu, Winterville, N.C.

Filed Aug. 25, 1994, Ser. No. 295,987
Int. Cl.⁶ A61N 5/06

17 Claims



1. A method for treatment of cutaneous vascular and pigmented lesions, comprising the steps of:

generating a pulsed beam of laser radiation;
directing the beam to a target region of the skin;
controlling the peak irradiance, the pulse duration and the focal spot size of the beam such that a microplasma is created in the targeted lesion for disruption; and
scanning the beam within a treatment area of the skin.


5,586,982

CELL TRANSFECTION APPARATUS AND METHOD

George S. Abela, 80 Longfellow Rd., Wellesley, Mass. 02181
Continuation-in-part of Ser. No. 53,206, Apr. 28, 1993, Pat. No. 5,330,467, which is a continuation of Ser. No. 866,473, Apr. 10, 1992, Pat. No. 5,246,437. This application Jul. 18, 1994, Ser. No. 276,324
Int. Cl.⁶ A61B 17/36

U.S. Cl. 606—28

34 Claims



1. An apparatus for cell transfection comprising:
an instrument with a housing having a wall with at least one hole therein, wherein said instrument has a distal portion adjacent said hole and a proximal portion remote from said hole;
a heater operatively connected to said distal portion so as to apply a sufficient amount of heat to cells of a patient in vivo to enhance the cells susceptibility to transfection; and
a source of treatment agent including a DNA plasmid operatively connected to the instrument so as to apply treatment agent to the heated cells by way of a treatment channel inside said instrument and extending to said hole; and
wherein the treatment agent is operable to transfect the heated cells.

5,586,983

BONE CLAMP OF SHAPE MEMORY MATERIAL

Albert E. Sanders, 7107 Brookside La., San Antonio, and James O. Sanders, 530 Grandview Pl., Terrell Hills, both of Tex. 78209


Division of Ser. No. 956,673, Oct. 5, 1992, Pat. No. 5,290,289, which is a continuation-in-part of Ser. No. 526,601, May 22, 1990, abandoned. This application Jan. 31, 1994, Ser. No. 189,192

Int. Cl.⁶ A61B 17/70

U.S. Cl. 606—61

7 Claims

1. A clamp for securing a rod adjacent to a bone, comprising:
means for holding said rod, said means for holding constructed of shape memory material;
means for affixing said means for holding adjacent to the bone, said means for affixing connected to said means for holding and constructed of shape memory material; and



means for securing said rod within said means for holding, wherein said means for securing is constructed of shape memory material and allows slidable motion of said rod within said means for holding.

5,586,984

POLYAXIAL LOCKING SCREW AND COUPLING ELEMENT ASSEMBLY FOR USE WITH ROD FIXATION APPARATUS


Joseph P. Errico, Hempstead, N.Y.; Thomas J. Errico, Summit, and James D. Ralph, Oakland, both of N.J., assignors to Fastenetix, L.L.C., Summit, N.J.

Continuation-in-part of Ser. No. 502,285, Jul. 13, 1995. This application Jul. 14, 1995, Ser. No. 502,803

Int. Cl.⁶ A61B 17/70

U.S. Cl. 606—61

28 Claims



1. A polyaxial screw and coupling element assembly for use with orthopedic rod implantation apparatus, comprising:
a screw having a curvate head;
a coupling element including
an expandable and contractable interior chamber for receiving therein said curvate head,
a rod receiving locus for receiving therein a rod, and
a surface threading disposed on an upper exterior portion thereof;
a locking ring mounted around said coupling element, the downward translation of said ring providing a force which causes said interior chamber to contract, therein locking the screw to the coupling element; and
a top locking nut, mateable with said surface threading.

5,586,985


METHOD AND APPARATUS FOR FIXATION OF DISTAL RADIUS FRACTURES

Matthew D. Putnam, Minneapolis, and David Gesensway, Mendota Heights, both of Minn., assignors to Regents of the University of Minnesota, Minneapolis, Minn.

Filed Oct. 26, 1994, Ser. No. 329,444
Int. Cl.⁶ A61B 17/56

U.S. Cl. 606—69

22 Claims



1. A plate for stable fixation of distal radius fractures comprising:

- a) an elongated plate adapted for attachment to the dorsal surface of the radius, the plate having a proximal end and a distal end, wherein the distal end comprises first and second substantially planar surfaces, the first and second surfaces forming an included angle adapted to substantially match the curvature of the dorsal surface of the distal end of the radius, and further wherein the proximal end of the plate is curved such that the proximal end is adapted to substantially match the profile of the near distal portion of the radius;
- b) a plurality of lines extending from the distal end of the plate, wherein each line is completely integral and unitary with the plate, and further wherein each line is oriented substantially normal to the first surface such that when the plate is located on a radius, each of the plurality of lines is adapted to extend into the radius; and
- c) a plurality of openings extending through the plate adapted to receive fasteners to fasten the plate to the radius.

5,586,986

INSTRUMENT FOR CLOSING TROCAR PUNCTURE WOUNDS

Peter W. J. Hinchliffe, New Haven, Conn., assignor to United States Surgical Corporation, Norwalk, Conn.

Continuation of Ser. No. 91,793, Jul. 14, 1993. This application Feb. 23, 1995, Ser. No. 393,541

Int. Cl.⁶ A61B 17/00

U.S. Cl. 606—147

18 Claims

1. A surgical instrument for applying sutures, which comprises:
- a) a shaft;
 - b) a needle carrier connected to a distal end portion of said shaft;
 - c) a needle having a tapered end portion and a base portion, said base portion disposed in said needle carrier such that at least said needle base portion is spaced a fixed predetermined distance from a central longitudinal axis of said instrument; and



- d) an elongated housing member surrounding said shaft and being longitudinally slidable thereon to a distally extended position, wherein said needle is at least partially enclosed within said elongated housing member by said elongated housing member moving from said tapered end portion toward said base portion such that said tapered end portion is shielded from body tissue by said elongated housing member, and to a proximally extended position, wherein said needle tapered end portion is exposed to such body tissue.

5,586,987

ANASTOMOSIS CUFF


Gregory M. Fahy, Galtersburg, Md., assignor to Organ, Inc., and Life Resuscitation Technologies, Inc., both of Chicago, Ill.

Filed Mar. 24, 1995, Ser. No. 409,705

Int. Cl.⁶ A61B 17/00

U.S. Cl. 606—155

20 Claims



1. A cuff suitable for use in an anastomosis procedure, comprising:

- a) a hollow portion having a length extending in a longitudinal axial direction of the cuff and a continuous inner surface; and
- b) a non-annular outwardly extending ridge directly connected to an exterior wall of the hollow portion, the non-annular outwardly extending ridge having a planar portion that extends along the exterior wall of the hollow portion in a direction parallel to the longitudinal axial direction such that the ridge is graspable to immobilize and position the cuff.

5,586,988

Patent Not Issued For This Number

5,586,989

MICROSURGICAL CURETTE


Robert Bray, Jr., 17724 Camino de Yatasto, Pacific Palisades, Calif. 90272

Filed Jan. 27, 1995, Ser. No. 379,738

Int. Cl.⁶ A61B 17/22

U.S. Cl. 606—160

9 Claims



1. A curette comprising:

- a) a cylindrical handle having a longitudinal axis;
- b) a shaft, having a longitudinal axis;
- c) means for attaching a first end of the shaft to the cylindrical handle, such that the longitudinal axis of the shaft is parallel to, but not collinear with, the longitudinal axis of the cylindrical handle; and
- d) a tip included in a second end of the shaft.

5,586,990

ENDOSURGICAL INSTRUMENT WITH A RADIALLY MOVABLE END EFFECTOR


Kevin F. Hahnen, Miami; Laszlo Farkas, Hialeah, both of Fla., and David P. Gordon, Stamford, Conn., assignors to Symbolis Corporation, Miami, Fla.

Filed May 8, 1995, Ser. No. 436,121

Int. Cl.⁶ A61B 17/32

U.S. Cl. 606—170

20 Claims



1. An endosurgical instrument, comprising:

- a) a hollow tube having a proximal end, and a distal end, and a wall defining a radial opening near said distal end;
- b) a push rod having a proximal end and a distal end, said push rod extending at least partially through said hollow tube;
- c) a deflecting surface inside said hollow tube and near said distal end of said hollow tube;
- d) a non-rotatable end effector coupled to said push rod with said end effector extending at least partially outside said tube

and coupled to said push rod through said radial opening when said end effector is in a deployed position; and

- e) actuation means coupled to said proximal end of said hollow tube and said proximal end of said push rod for effecting a relative axial movement of said tube and push rod, wherein relative axial movement of said tube and push rod causes said distal end of said push rod and said deflecting surface to engage such that said end effector is moved radially and distally relative to said tube.

5,586,991

SAFETY PENETRATING INSTRUMENT


InBae Yoon, 2101 Highland Ridge Dr., Phoenix, Md. 21131
Division of Ser. No. 745,071, Aug. 14, 1991, abandoned, which is a continuation-in-part of Ser. No. 628,899, Dec. 18, 1990, Pat. No. 5,226,426. This application Jan. 6, 1994, Ser. No. 178,151

The portion of the term of this patent subsequent to Mar. 8, 2011, has been disclaimed.

Int. Cl.⁶ A61B 5/20

U.S. Cl. 606—185

14 Claims



1. A safety penetrating instrument comprising

- a) an elongate penetrating member having a proximal end and a distal end having a sharp tip for penetrating tissue;
- b) a safety probe including a protective body disposed adjacent said distal end of said penetrating member and having an extended position with at least a portion of said protective body protruding distally of said sharp tip and a retracted position with said body disposed to expose said sharp tip, said protective body being made of a flexible, pliable material allowing contact with tissue within the body without injury to the tissue, said protective body being resilient to permit said protective body to be moved to said retracted position in response to forces from contact of said protective body with tissue and to permit said protective body to resiliently return to said extended position upon removal of the forces from tissue contact, said protective body having a portion configured to be compressed in said retracted position and to be expanded in said extended position, said protective body portion having an accordion-like, folded configuration;
- c) a hub receiving said proximal end of said penetrating member;
- d) a housing abutting said hub; and
- e) an elongate, tubular portal sleeve surrounding said penetrating member and having a distal end disposed adjacent said penetrating member distal end and a proximal end secured to said housing.

CHEMICAL

5,586,992

DYEING CELLULOSE-CONTAINING TEXTILE MATERIAL WITH HYDROGENATED INDIGO

Georg Schnitzer, Weisenheim; Franz Suetsch, Roedersheim-Gronau; Michael Schmitt, Worms; Erich Kromm, Weisenheim; Harald Schlueter, Weisenheim; Rudolf Krueger, Weisenheim, and Andreas Weiper-Idelmann, Mannheim, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

PCT No. PCT/EP94/00873, § 371 Date Sep. 29, 1995, § 102(e) Date Sep. 29, 1995, PCT Pub. No. WO94/23114, PCT Pub. Date Oct. 13, 1994

PCT Filed Mar. 21, 1994, Ser. No. 525,655

Claims priority, application Germany, Mar. 30, 1993, 43 10 122.4; May 12, 1993, 43 15 873.0

Int. Cl.⁶ D06P 1/22; 5/20

U.S. Cl. 8—653

7 Claims

1. A process for dyeing cellulose-containing textile material with indigo which comprises

- introducing into a dye bath an aqueous solution of leuco indigo prepared by catalytic hydrogenation;
- contacting the textile material with the dye bath; and, after the leuco indigo has gone onto the textile material,
- converting said leuco indigo back into the pigment form in a conventional manner by air oxidation.

5,586,993

SEALED STORAGE BATTERY AND MANUFACTURING METHOD THEREOF

Ken Saito; Naoyoshi Hinotsu; Hikaru Sakamoto, and Koichi Hoshino, all of Iwaki, Japan, assignors to Furukawa Denchi Kabushiki Kaisha, Kanagawa, Japan


Filed Jun. 1, 1995, Ser. No. 456,564

Claims priority, application Japan, Jun. 3, 1994, 6-121641

Int. Cl.⁶ H01M 6/00

U.S. Cl. 29—623.2

4 Claims



1. A method for manufacturing a sealed storage battery in which a sealing assembly of said battery is assembled, the improvement wherein said assembling of said sealing assembly includes the steps of:

- fitting an annular plate cover to a hollow shaft of a hollow rivet via an insulating gasket;
- inserting a conical tip end portion of a punch into a bore of said hollow shaft from a side of said bore away from a head of said hollow rivet, said inserting step including a sub-step of inserting a positioning center shaft provided at a tip end of the conical tip end portion of said punch into the bore of said hollow shaft; and
- pressurizing said punch toward the head of said hollow rivet, to cause an end portion of said hollow rivet on a side away from the head of said hollow rivet to be diametrically enlarged and caulked by the conical tip end portion of said punch, whereby said hollow rivet is fixed to said cover plate via said insulating gasket.

5,586,994

METHOD FOR MANUFACTURE OF A LEAD ACID STORAGE BATTERY

Toshirou Hasegawa, Toyohashi; Kazuhiko Shimoda, Kosai; Kunio Makino, Kosai, and Mitsuo Tomioka, Kosai, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Division of Ser. No. 441,129, May 15, 1995. This application Nov. 22, 1995, Ser. No. 561,068

Claims priority, application Japan, May 24, 1994, 6-109628; May 24, 1994, 6-109665; Aug. 2, 1994, 6-181257; Apr. 14, 1995, 7-089290

Int. Cl.⁶ H01M 10/14

U.S. Cl. 29—623.5

10 Claims



1. A method for making a lead acid storage battery which comprises the steps of:

- forming a plurality of plate groups, with each plate group being formed by alternately arranging a plurality of positive plates and a plurality of negative plates, each plate having lower and upper ends and a lug disposed on the upper end, enveloping each of the positive plates or each of the negative plates in an envelope separator having an upper portion extending to a position higher than the upper end of the plate, and integrally connecting all of the positive plates together with a first connecting strap and integrally connecting all of the negative plates together with a second connecting strap;
- placing the plate groups in a plurality of cell chambers formed in a case by a plurality of inner partition walls, the case being made of a synthetic thermoplastic resin;
- inserting two shape regulating plates having a width the same as or narrower than an interval between opposing inner partition walls into an area above the plate group in one of the cell chambers, the shape regulating plates being disposed in the area above the plate group at a right angle to the direction of the thickness of the plate group and forming a space between the shape regulating plates;
- pouring a heat molten insulating resin into the space between the shape regulating plates to form a beam of resin with first and second ends and crossing the plate group in the direction of the thickness of the plate group, with the first end of the beam contacting an inner wall of the case or one of the inner partition walls, and the second end of the beam contacting one of the inner partition walls; and
- curing the molten resin by cooling to form a beam-shaped plate fixing member.

5,586,995

FILTER FOR SEPARATING POLLUTANTS FROM FLUE GASES


Frohmut Vollhardt, Oberhausen, and Jürgen R. Heering, Knrschenbroich, both of Germany, assignors to Man Gutehoffnungshütte Aktiengesellschaft, Oberhausen, Germany
Filed Mar. 7, 1995, Ser. No. 399,751

Claims priority, application Germany, Mar. 30, 1994, 44 11 078.2

Int. Cl.⁶ B01D 47/14

U.S. Cl. 55—227

12 Claims



1. A flue gas filter for separating pollutants from the flue gases, comprising: a filter housing; a plurality of filter boxes, each filter box being arranged at a spaced location from another filter box and being disposed one of horizontally one on top of another or vertically one next to another, said filter boxes being positioned within said filter housing, said filter boxes including cage-wall means for defining walls which are permeable to gas and water; filter medium selected from the group consisting of activated carbon, open-hearth furnace coke and carbonaceous material, said cage wall means retaining said filter medium within said filter boxes; water distribution means for providing a metered charging of water into said housing, said water distribution means including nozzles for spraying said filter medium in said filter boxes, said nozzles being arranged one of above each filter box, for horizontally arranged filter boxes, and to a side of each filter box, for vertically arranged filter boxes; a water collection tank, positioned below said filter boxes, for collecting water; pump means connected to said collection tank for pumping collected water and feeding water to said nozzles of said distribution means; a flue gas feed pipe connection arranged at the bottom of said filter housing; vertical gas flow pipes extending through said water collection tank for passage of flue gases from said flue gas feed pipe, past said water collection tank; and a flue gas exhaust pipe arranged at a top of said filter housing.

5,586,996

VAPOR SEPARATING DEVICE


Arman K. Manookian, Jr., 2875 Terrell Ave., Oceanside, N.Y. 11572-1151

Filed May 12, 1994, Ser. No. 241,600
Int. Cl.⁶ B01D 19/00

U.S. Cl. 55—321

9 Claims

1. Apparatus for separating oil from the blow-by exhaust vapors of a combustion engine comprising a canister having an inlet port for the intake of said vapors from the engine, a gas outlet port for connection to a source of suction for causing the vapors to be sucked through said canister from said inlet port, a discharge port for removal of condensed oil from said canister, and a hollow, cylindrical filter stack located in said canister and operatively



arranged so that the vapors pass in contact and radially through the filter stack being sucked from the inlet to the gas outlet port, said filter stack comprising a filter body formed of material permeable to gas and impermeable to oil, a sleeve partially surrounding said filter body on which said vapors from said inlet port impinge and on which the oil in said vapors condense and a longitudinal opening diametrically opposite to the inlet port, and including a pair of seal caps secured against opposite ends of said canister, and an end closure compressed against said seal cap to provide an airtight seal at both ends of said canister comprising a pair of annular disks having a diameter greater than the diameter of said filter body, each of said disks being interposed between said filter body and a respective one of filter stack material ends such that said core extends through said disks, and retaining means securing said sleeve about said annular disks and in spaced enveloping relation to said filter body, said filter stack being mounted within said canister and spaced from the interior wall surface thereof to define an annular flow passage between said sleeve and the interior wall surface of said canister in which said oil in said vapors may collect prior to passage through said filter body.

5,586,997

BAG FILTER

David B. Pall, Roslyn Estates, and James T. Connors, Jr., Groton, both of N.Y., assignors to Pall Corporation, East Hills, N.Y.

Continuation-in-part of Ser. No. 281,772, Jul. 28, 1994. This application Feb. 16, 1995, Ser. No. 389,264

Int. Cl.⁶ B01D 46/02

U.S. Cl. 55—361

29 Claims



1. A bag filter comprising a melt-blown fibrous nonwoven web formed into a bag configuration with a closed end, an open end, an inside surface, and an outside surface, wherein said fibrous nonwoven web comprises fibers such that 90% of the fibers have a

diameter ranging from a minimum fiber diameter to a maximum fiber diameter which is no more than about three times the minimum fiber diameter.

5,586,998

CO-CURRENT CYCLONE SEPARATION EXTRACTOR

Thierry Gauthier, Saint Genis Laval, France, assignor to Institut Français Du Pétrole, Rueil Malmaison, France

Continuation of Ser. No. 985,712, Dec. 4, 1992, abandoned.


This application Jan. 17, 1995, Ser. No. 373,535

Claims priority, application France, Dec. 5, 1991, 91 15063

Int. Cl.⁶ B01D 53/24

U.S. Cl. 55—391

23 Claims



1. Cocurrent cyclone separator extractor for both the separation of a gas/solid mixture MA, having at least one dense phase DA and a light phase LA, into at least one dense phase and into at least one light phase, and for the extraction of gases sorbed by the solid, said separator extractor comprising:

a first external enclosure (1), which is elongated along an axis (X), which has a substantially circular cross-section, of internal diameter D₁ and length L₁, having at a first end, external inlet means (4) for the introduction of the mixture MA, said means making it possible to give at least to the light phase LA a helical movement in the flow direction of the mixture MA in said enclosure,

an internal enclosure (2), which is elongated along the axis (X), which has a substantially circular cross-section of diameter D₂, which is less than D₁, and of length L₂, which is less than L₁, whose end close to inlet means (4) is located at a distance L₃, which is less than L₁, from the extreme level of inlet means (4), and constitutes the internal inlet (5) by which penetrates at least part of the light phase LA, said internal enclosure being extended by at least one pipe (6) permitting the discharge of the light phase LA separated outside the first external enclosure,

a second external enclosure (3) having a substantially vertical axis of symmetry, connected to said first enclosure by an opening of diameter D₁, said second enclosure collecting the separated dense phase DA and having means (10) for the injection of a light extraction phase LB, injection taking place in countercurrent manner with respect to the flow of the separated dense phase and, at least in part in said dense phase which is at least partly fluidized, the above-mentioned components arranged so that injection of light extraction phase LB limits flow of light phase LA in the direction of said second enclosure, and said second enclosure has at least one outlet (12) for the recovery of the at least partly desorbed dense phase DA, said inlet (5) also functioning as a removal means for said light extraction phase LB.

5,586,999

METHOD FOR PRODUCING GLASS WITH LOWER ALKALI CONTENT


Hisashi Kobayashi, Putnam Valley, N.Y., assignor to Praxair Technology, Inc., Danbury, Conn.

Continuation-in-part of Ser. No. 894,588, Jun. 5, 1992, abandoned. This application May 16, 1994, Ser. No. 242,827

Int. Cl.⁶ C03B 5/18; 5/225

U.S. Cl. 65—134.3

7 Claims



1. A method for producing glass comprising:

(A) providing glass forming materials into a glassmelting zone;
(B) combusting fuel and oxidant, having an oxygen concentration exceeding that of air and at least 35 volume percent, to provide heat to the glassmelting zone and to generate sufficient combustion reaction products including carbon dioxide and water vapor to establish an atmosphere in the glassmelting zone comprising at least 30 volume percent water vapor;
(C) melting glass forming materials in the glassmelting zone by application of said heat provided to the glassmelting zone to produce molten glass;
(D) dissolving water into the molten glass to act as flux while maintaining the water vapor concentration in the glassmelting zone atmosphere at 30 volume percent or more;
(E) passing molten glass from the glassmelting zone into a refining zone and maintaining an atmosphere in the refining zone having a water vapor concentration of at least 30 volume percent;
(F) passing molten glass from the refining zone into a forehearth zone and maintaining an atmosphere in the forehearth zone having a water vapor concentration of at least 30 volume percent; and
(G) passing dry gas having less than 6 volume percent water over the molten glass and thereafter passing the molten glass to a forming machine.

5,587,000

TAKEOUT MECHANISM IN GLASSWARE FORMING MACHINE

Philip A. Mann, Pontefract, and Ian Green, Dore, both of United Kingdom, assignors to Emhart Glass Machinery Investments Inc., Wilmington, Del.

Filed Dec. 12, 1994, Ser. No. 353,843


Claims priority, application United Kingdom, Dec. 16, 1993, 9325748

Int. Cl.⁶ C03B 9/44

U.S. Cl. 65—260

2 Claims

1. A method of setting up a take out mechanism in a glassware forming machine comprising a machine frame, a set of blow mould members having an upper surface and having a known invert height mounted in said machine frame, support means extending above said machine frame, and a take out mechanism comprising: a vertically extending housing which is secured in said machine frame and which includes an upward extension secured to said support means, a piston and cylinder device in said housing having upper and lower ends, the piston displaceable between upper and lower positions.



a stop at the lower end of said piston and cylinder which determines the lower position of the piston in said device, a rack in said housing connected to said piston and cylinder device, a take out arm pivoted on said housing and linked to said rack by gear means, a take out head pivoted on said take out arm at a pivot point, take out tongs depending from said take out head, the pivotal displacement of the take out arm displacing the take out tongs from a lower position for picking up formed containers to an upper position and wherein a reference boss is provided on said housing, the method comprising:

- positioning a first jig member between said reference boss and said pivot point to ensure said take out arm is at a predetermined angle to the housing;
- adjusting said stop at the lower end of said piston and cylinder device to ensure that when said take out arm is at the predetermined angle said piston cannot move further downwards;
- removing said first jig member from the pivot point of the arm and from the reference boss and replacing it with a second jig member selected for the lower position of said take out tongs, said second jig member placed on the pivot point of the arm and freely depending from said pivot point of said arm;
- adjusting the position of said housing in the machine frame so that said second jig member contacts the upper surface of the set of blow mould members in the machine and fixing said housing in such position; and
- adjusting a scale on said upward extension so that the scale reads a value equivalent to the invert height of the mould members.

5,587,001

PROCESS FOR TREATING IRON-CONTAINING SULFIDIC ROCKS AND ORES

Nadine H. C. De Vries, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.
Filed Apr. 28, 1995, Ser. No. 431,215
Int. Cl. C22B 3/06; 3/12

U.S. Cl. 75—743

8 Claims

1. A process for pretreating sulfidic iron-containing ores of metals prior to lixiviating said ores comprising the steps of:

- contacting said ores with an aqueous solution containing manganate ions or a precursor of manganate ions wherein the concentration of manganate ions, present or formed, is between approximately 0.0005 mole % and saturation, and the pH of the solution is between about 6 and 13;
- allowing a reaction between said precursor moiety and the sulfides in said ore to proceed when the solution of step A contains a manganate precursor so as to form manganate ions; and

C. maintaining the pH of the reaction medium at between about 6 and 13 so as to cause the formation of a layer of manganese oxide on the surface of said sulfides.

5,587,002

PROCESS FOR THE PREPARATION OF A COOLING AGENT CONTAINING IRON FOR A STEEL-MAKING CONVERTER

Serge Audebert, Bellegarde, and Francis Audibert, Saint Martin de Crau, both of France, assignors to Sollac, Puteaux, France

Filed Nov. 25, 1992, Ser. No. 981,425

Claims priority, application France, Nov. 26, 1991, 91 14590
Int. Cl. C22B 1/24; 1/244

U.S. Cl. 75—770

8 Claims

1. A process for the preparation of a cooling agent containing iron, comprising the steps of:

- adding quicklime, iron ore, slag and metal fibrils to extracted fatty rolling mill slurries present in a container in order to obtain mixture A which comprises more than 5% water, hydrocarbons and contains the following components in percent by weight:
fatty slurries: 55 to 93%
lime: 5 to 25%
metal fibrils: 5 to 15%
iron ore: 1 to 15%
slag: 1 to 15%

covering said container containing mixture A and allowing mixture A to stand for a time sufficient for slaking of said lime, reduction of the water content to 4–5% and reduction of the hydrocarbon content, homogenizing mixture A,

adding 4 to 10% of binder to said mixture A to produce mixture B,

compacting said mixture B in order to form ovoids.

5,587,003

REMOVAL OF CARBON DIOXIDE FROM GAS STREAMS

Martin Bülow, Basking Ridge; Loc Dao, Bound Brook, and Frank R. Fitch, Bedminster, all of N.J., assignors to The BOC Group, Inc., New Providence, N.J.

Filed Mar. 21, 1995, Ser. No. 407,817

Int. Cl. B01D 53/047

U.S. Cl. 95—123

13 Claims

1. A method of removing carbon dioxide from a gas stream selected from oxygen, nitrogen, argon and mixtures of these which contains carbon dioxide at a partial pressure not greater than about 10 mbar as an impurity, comprising subjecting said gas stream to adsorption using clinoptilolite as the adsorbent at a temperature in the range of about 20° to about 80° C., thereby adsorbing substantially all of the carbon dioxide from the gas stream.

5,587,004

DEFOAMING DEVICE AND METHOD FOR AERATION

Fumio Mogi, Kanagawa, Japan, assignor to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Division of Ser. No. 716,466, Jun. 17, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 487,514

Claims priority, application Japan, Jun. 22, 1990, 2-165367


Int. Cl. B01D 19/02

U.S. Cl. 95—157

20 Claims

1. A defoaming device for aeration, for use in a processor equipped with an aeration apparatus for sending air into a processing solution, comprising:

- a pipe for guiding foam produced in said aeration apparatus to outside said aeration apparatus;



a throttle portion disposed midway in said pipe and formed by reducing the cross-sectional area of said pipe so as to accelerate the flow rate of the foam in said pipe, portions of said pipe at an upstream side of said throttle portion being isolated from ambient;

air-stream guiding means co-acting with said throttle portion for guiding an air stream into a portion of said pipe in a downstream direction corresponding to the direction of the flow of the foam so as to accelerate the flow rate of the foam in said pipe up to a predetermined rate, said air-stream guiding means being disposed at the downstream side of said throttle portion, said pipe having no throttle portions downstream of said air-stream guiding means.

11. A defoaming method for use in a processor equipped with an aeration apparatus for sending air into a processing solution, said method comprising:

- guiding foam produced in said aeration apparatus through a pipe to an outside apparatus;
- increasing a flow rate of the foam in said pipe by providing a throttle portion midway in said pipe and by providing means for guiding an air stream into a portion of said pipe downstream of said throttle portion of said pipe in a direction corresponding to a direction of flow for the foam, said pipe having no throttle portions downstream of said air stream guiding means and portions of said pipe at an upstream side of said throttle portion being isolated from ambient.

5,587,005

AIR PURIFIER APPARATUS WITH AN ELECTROSTATIC FILTER


Doreano De Marco, Belluno, Italy, assignor to Procond Eletttronica S.p.A., Belluno, Italy

Filed Mar. 7, 1995, Ser. No. 399,553

Claims priority, application Italy, Mar. 16, 1994, PN94A0015
Int. Cl. B03C 3/72

U.S. Cl. 96—26

4 Claims



1. An air purifier apparatus comprising:

- a power supply;
- a first electrode connected to a first terminal of said power supply;

an electrical contact connected to a second terminal of said power supply;

an electrostatic filter detachably and operatively connected to said electrical contact;

an alarm device having at least first and second indicator states, said alarm device having said first indicator state when said electrostatic filter is electrically connected to said power supply through said electrical contact, and said alarm device having said second indicator state when said electrostatic filter is not electrically connected to said power supply through said electrical contact; and

a second electrical contact which is connected to said alarm device, wherein said electrostatic filter is detachably and operatively connectable to said second electrical contact, and wherein said electrical contact and said second electrical contact are electrically connected through said electrostatic filter when said electrostatic filter is operatively connected to said electrical contact and said second electrical contact;

wherein said alarm device includes means for changing from said second indicator state to said first indicator state when energized by said power supply through said electrostatic filter and said second electrical contact;

wherein said alarm device includes a display indicator and an electrostatically controlled shutter, said electrostatically controlled shutter concealing said display indicator in the absence of energy from said power supply and revealing said display indicator when energized by said power supply.

5,587,006

COMPOSITION AND PROCESS FOR MECHANICAL PLATING OF NICKEL-CONTAINING COATINGS ON METAL SUBSTRATES

Marjorie H. Shepherd, Madison, Ind., and Kim B. Gasaway, Troy, Ohio, assignors to Madison Chemical Co., Inc., Madison, Ind.

Division of Ser. No. 336,668, Nov. 7, 1994, Pat. No. 5,460,848, which is a continuation-in-part of Ser. No. 224,520, Apr. 7, 1994, abandoned. This application Aug. 1, 1995, Ser. No. 510,127

Int. Cl. B22F 7/00

U.S. Cl. 106—1.05

9 Claims

1. A co-plating promoter composition for mechanically plating a tin- and nickel-containing coating on metal articles, said composition comprising from 1 to 30 wt-% insoluble nickel oxide, from 5 to 50 wt-% platable tin compound, from 10 to 45 wt-% acidity regulating agent and from 10 to 60 wt-% dispersant.

5,587,007

MODIFIED DICYCLOPENTADIENE RESINS

Daniel R. Curvin, Franklin, Va., assignor to Arizona Chemical Company, Panama City, Fla.

Filed Aug. 14, 1995, Ser. No. 514,764

Int. Cl. C09D 11/00; C08G 63/00

U.S. Cl. 106—23

25 Claims

1. A method for preparing a modified dicyclopentadiene resin consisting essentially of

- reacting (a) dicyclopentadiene, (b) a phenol selected from the group consisting of an alkyl phenol having the formula $\text{CH}_3(\text{CH}_2)_n\text{C}_6\text{H}_4\text{OH}$, where n is from 1 to 9, and a bisphenol having the formula $\text{HOC}_6\text{H}_4(\text{CR}_2)_x\text{C}_6\text{H}_4\text{OH}$, where R is independently hydrogen or a $\text{C}_1\text{--C}_6$ alkyl group and x is from 1 to 4, or mixtures thereof; (c) a fatty acid or a derivative thereof selected from the group consisting of tall oil, a tall oil derivative, dimer fatty acid, linseed oil and mixtures thereof; and (d) an unsaturated organic diacid or an anhydride thereof, at a temperature and pressure sufficient to produce a phenol-modified cyclopentadiene resin.

5,587,008

SAND MOLDING MEDIA FOR IRON CASTINGS

Victor S. LaFay, Cincinnati, Ohio, and Stephen L. Neltner, Alexandria, Ky., assignors to Hill & Griffith Co., Cincinnati, Ohio

Filed Nov. 7, 1995, Ser. No. 556,740

Int. Cl.⁶ B22C 1/02

U.S. Cl. 106—38.51

10 Claims

1. A sand molding medium comprising, on a weight basis:

silica sand	85%—95%
pre-mix	5%—15%

wherein the pre-mix comprises:

a clay component	70%—80%
a carbon component	15%—30%

characterized in that the carbon component includes wettable untaite.



alumina powder consisting of fine flaky alumina particles having a particle size of 1.0 μm or less and a thickness of 0.1 μm or less with an organic water holding material and water.

5,587,011


OPTICALLY WHITENED CLAY PIGMENTS

Carl J. Marshall, Jr., and Gary M. Freeman, both of Macon, Ga., assignors to J. M. Huber Corporation, Edison, N.J.
Continuation-in-part of Ser. No. 382,938, Feb. 1, 1995, abandoned, which is a continuation of Ser. No. 102,312, Aug. 5, 1993, abandoned, which is a continuation of Ser. No. 844,318, Mar. 30, 1992, abandoned, which is a continuation of Ser. No. 665,824, Mar. 7, 1991, abandoned, which is a division of Ser. No. 427,341, Oct. 27, 1989, abandoned. This application Apr. 6, 1995, Ser. No. 419,069

Int. Cl.⁶ C04B 14/00

U.S. Cl. 106—416

33 Claims



5,587,010

PROCESS FOR PRODUCING FINE FLAKY ALUMINA PARTICLES AND ALUMINA-BASED PLASTIC MATERIAL

Yasun Shibusaki, Nagoya; Kiichi Oda, Nagoya, and Takeshi Fukuda, Kurobe, all of Japan, assignors to Agency Of Industrial Science And Technology, Ministry Of International Trade And Industry, and YKK Corporation, both of Tokyo, Japan

Division of Ser. No. 301,734, Sep. 7, 1994, which is a continuation of Ser. No. 907,933, Jul. 1, 1992, abandoned. This application Jun. 16, 1995, Ser. No. 491,114

Claims priority, application Japan, Jul. 9, 1991, 3-193668; Oct. 3, 1991, 3-282015

Int. Cl.⁶ C04B 35/10

U.S. Cl. 106—287.17

4 Claims

1. An alumina-based plastic material produced by kneading an

1. A method of optically whitening an inorganic pigment selected from a mineral clay pigment and a sodium aluminosilicate pigment, each pigment having a yellow tint, without sacrificing the pigment's brightness, comprising adding to an aqueous slurry of the pigment, an aqueous solution in combination comprising (1) a blue cationic organic dye that is either bright blue or reddish-blue in hue with (2) a red cationic organic dye that is bluish-red in hue, the ratio of the (1) blue to the (2) red dye being from 99/1 to 60/40 at an effective combined concentration of 0.00002 to 0.008% by weight as based on active dyestuffs on dry pigment, and vigorously mixing the resulting slurry to bond the dyes directly to the pigment, whereby the pigment exhibits increased whiteness.

5,587,012

COMPOSITION FOR AND METHOD OF PUMPING CONCRETE

Daniel P. Montgomery, Mesquite, Tex., assignor to Fritz Industries, Inc., Mesquite, Tex.

Division of Ser. No. 282,879, Jul. 29, 1994, Pat. No. 5,443,636.

This application Jun. 22, 1995, Ser. No. 493,411

Int. Cl.⁶ C04B 24/10

U.S. Cl. 106—823

10 Claims

1. An additive for a concrete slurry said additive being comprised of a water soluble, inorganic, alkaline material and a solvatable, organic polymeric material,

wherein the concentration of said alkaline material in said additive is an amount in the range of from about 40 to about 99 parts per 100 parts by weight of said additive and the concentration of said polymeric material in said additive is an amount in the range of from about 1 to about 60 parts per 100 parts by weight of said additive, and further

wherein said organic polymeric material consists essentially of a mixture of at least one synthetic hydrophilic polymer and a material selected from the group consisting of natural polymers modified by reaction with hydrophilic constituents and mixtures thereof, and still further

wherein the weight ratio of said synthetic hydrophilic polymer to said modified natural polymer is an amount in the range of from about 1 to 1 to about 2 to 1 and the molecular weight of said modified natural polymer is less than about 100,000.

5,587,013

METHODS OF SYNTHESIZING AND POLISHING A FLAT DIAMOND FILM AND FREE-STANDING DIAMOND FILM

Akihiko Ikegaya; Keiichi Tanabe, and Naoki Fujimori, all of Hyogo, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan


Filed Jan. 27, 1995, Ser. No. 379,692

Claims priority, application Japan, Jan. 27, 1994, 6-26353

Int. Cl.⁶ C30B 29/04

U.S. Cl. 117—89

32 Claims



1. A method of synthesizing a free-standing diamond film comprising the steps off:

growing at least one potential-convex diamond layer on a substrate by a CVD method using hydrogen gas and hydrocarbon gas under a condition (a) such that the at least one potential-convex diamond layer has a potential to deform into a convex shape by elimination of the substrate;

growing at least one potential-concave diamond layer on the potential-convex diamond layer by a CVD method under a condition (b) such that the at least one potential-concave diamond layer has a potential to deform into a concave shape by elimination of the substrate;

alternating said growing steps such that the potential-convex and potential-concave diamond layers alternate;

eliminating the substrate; and obtaining the free-standing diamond film having at least one potential-convex layer and at least one potential-concave layer, the potential-convex and potential concave layers being deposited alternately.

5,587,014

METHOD FOR MANUFACTURING GROUP III-V COMPOUND SEMICONDUCTOR CRYSTALS

Yasushi Iyechika, and Tomoyuki Takada, both of Ibaraki, Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan


Filed Dec. 21, 1994, Ser. No. 360,427

Claims priority, application Japan, Dec. 22, 1993, 5-325333

Int. Cl.⁶ G30B 25/14

U.S. Cl. 117—90

10 Claims



1. A method for manufacturing group III-V compound semiconductor crystals including at least Ga as the group III element and at least N as the group V element by using metal-organic compounds of a group III metal having at least Ga in the molecule thereof and compounds having N in the molecule thereof as the raw materials, to grow a group III-V compound semiconductor crystal in a reaction tube and grow the crystal on a substrate made of a material different from the group III-V compound semiconductor crystal to be grown;

wherein at least one kind of gas, selected from a group consisting of compounds including halogen elements and group V elements, and hydrogen halide, is introduced before the growth of the compound semiconductor crystal begins thereby to carry out gas phase etching of the inner wall surface of the reaction tube.

5,587,015

APPARATUS FOR PRODUCTION OF SINGLE CRYSTAL OXIDE FILMS BY LIQUID-PHASE EPITAXY

Masaru Fujino, and Hiroshi Takagi, both of Ohtsu, Japan, assignors to Murata Manufacturing Co., Ltd., Japan


Filed Apr. 6, 1995, Ser. No. 418,012

Claims priority, application Japan, Apr. 7, 1994, 6-069402

Int. Cl.⁶ C30B 35/00

U.S. Cl. 117—200

15 Claims



1. An apparatus for production of single crystal oxide films by liquid-phase epitaxy comprising an insulating core tube, an electroconductive cylindrical member having openings at both ends and being arranged in the core tube, a high frequency induction heater disposed outside said core tube for heating said electroconductive cylindrical member and a crucible made of an electroconductive material and coaxially arranged in the cylindrical member.

5,587,016


CONTROLLED FEEDING CZOCHRALSKI APPARATUS
Burkhard Altekruiger; Joachim Aufreiter, both of Alzenau;
Dieter Brüss, Bruchköbel, and Klaus Kalkowski, Kelkheim,
all of Germany, assignors to Leybold Aktiengesellschaft,
Hanau, Germany

Division of Ser. No. 293,428, Aug. 19, 1994, Pat. No.
5,492,078. This application Nov. 13, 1995, Ser. No. 556,048
Claims priority, application Germany, Aug. 28, 1993, 43 28
982.7

Int. Cl.⁶ C30B 35/00

U.S. Cl. 117—214

8 Claims



1. A control system for the controlled feeding of a melting crucible (13) with particles (2, 2a) during the drawing of a crystal (16) by the Czochralski method, said system comprising a source (1) for a supply of particles (2, 2a) and with a melting crucible (13) to receive the particles, where the source (1) is equipped with a conveying device (4) for discharging particles at an adjustable rate per unit time, and where a device (17) for the continuous drawing-out of a crystal (16) with a given diameter and a given dopant concentration is attached to the melting crucible (13), means (7, 11) for putting the doped particles into single file as the particles (2, 2a) are traveling to the melting crucible (13), at least one sensor (21, 22) for counting the particles traveling in single file, wherein the output of each sensor (21, 22) is connected to a first input (24) of a counter (25), which has a second input (24) for a reference value element (27) and which can find the difference between the count pulses of the sensor (21, 22) and the reference input pulses supplied by the reference input element; and wherein the counter output (29) is connected to a control device (switching element (36) and amplifier (35)) for the drive (8) of the conveying device (4) of the source (1).

5,587,017

PROCESS AND APPARATUS FOR PRODUCING MOLTEN METAL COATED STEEL SHEETS

Shizuo Yamanaka, Chiba-ken, and Takao Hashimoto, Ibaragi-ken, both of Japan, assignors to Sumitomo Metal Industries, Ltd., Osaka, Japan


Filed Sep. 29, 1994, Ser. No. 314,630

Claims priority, application Japan, Sep. 30, 1993, 5-244749
Int. Cl.⁶ B05C 3/00

U.S. Cl. 118—424

16 Claims

1. An apparatus for producing a molten metal plated steel sheet comprising:
a molten metal plating tank containing a melt, said plating tank having a bottom and side walls with one side wall being located at a delivery end at which a steel sheet fed through the plating tank emerges,



a submerged sink roll disposed in the plating tank for conveying the steel sheet; and
a buffer member provided within the tank between the sink roll and the one side wall for decelerating melt flows coming from below the sink roll.


5,587,018

360 DEGREES FAST SPOT GLUING MACHINE FOR SCREWS

Fa-Chih Chung, Miao-Li Hsien, Taiwan, assignor to Jih Yih Hardware Co., Ltd., Miao-Li Hsien, Taiwan
Filed Jan. 20, 1995, Ser. No. 375,676
Int. Cl.⁶ B05C 11/00; 1/00; 5/00

U.S. Cl. 118—679

4 Claims



1. A gluing machine for applying glue around the periphery of a shank portion of a headed fastener comprising:
a) supply means for supplying a plurality of fasteners;
b) a conveyor for conveying a plurality of fasteners from the supply means, the conveyor comprising a pair of spaced apart endless belts having first runs moving at substantially the same speed so as to convey the fastener with the shank portions extending below the first runs between the spaced apart endless belts; and,
c) a glue applying device for applying glue around the entire circumference of the shank of the fastener, the glue applying device comprising:
i) a pair of spaced apart upright boards forming a channel therebetween, the boards located immediately beneath the first runs of the spaced apart endless belts such that shanks of fasteners conveyed by the endless belts pass through the channel between the upright boards;
ii) a gluing plate attached to a first of the pair of upright boards so as to extend into the channel;
iii) glue supply means connected to the gluing plate to supply glue to the gluing plate;
iv) an arcuate notch in a second of the pair of upright boards; and,
v) a rotatable wheel having a resilient peripheral surface, a portion of the wheel extending into the channel between the

upright boards through the arcuate notch to contact the shanks of fasteners conveyed by the conveyer such that rotation of the wheel causes rotation of a fastener shank coming into contact with the wheel against the gluing pad so as to apply the glue around the entire periphery of shanks.

5,587,019

APPARATUS FOR USE IN EPITAXIAL CRYSTAL GROWTH

Koji Fujie, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan


Filed Feb. 23, 1993, Ser. No. 47,552

Claims priority, application Japan, Feb. 26, 1992, 4-075200

Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—725

5 Claims



1. An apparatus for epitaxially growing a semiconductor crystal, comprising:
a reactor having an inner container made of quartz, a transparent quartz window at the upper end of said reactor, a gas supply pipe for supplying a reactive gas into said reactor and an exhaust pipe for exhausting the gas remaining in the reactor, with both tubes mounted through opposite side walls of the reactor, respectively, said reactor being completely sealed except for said gas supply and exhaust pipes;
a semiconductor support member fixedly mounted in said container of said reactor for supporting a semiconductor substrate; and
a hermetically sealed infrared lamp housing rotatably mounted over said quartz window and in parallel with said quartz window, wherein said reactor and said lamp housing are completely separate from each other.

5,587,020

Patent Not Issued For This Number

5,587,021

METHOD AND APPARATUS FOR THE CLEANING AND/OR CARE OF FLOORS AND/OR FLOOR COVERINGS OF ALL TYPES

Guido Hoersch, Kapfenberger Strasse 28, D-50226 Frechen, Germany, and Reinhard Hoersch, Frechen, Germany, assignors to Guido Hoersch, Frechen, Germany

PCT No. PCT/EP93/02747, § 371 Date Apr. 6, 1995, § 102(e) Date Apr. 6, 1995, PCT Pub. No. WO94/08504, PCT Pub. Date Apr. 28, 1994

PCT Filed Oct. 7, 1993, Ser. No. 411,606


Claims priority, application Germany, Oct. 10, 1992, 42 33 888.3

Int. Cl.⁶ B08B 3/12; 5/00; A47L 5/10; 5/26

U.S. Cl. 134—1

37 Claims

1. A method for the treatment of a surface, the surface being bare floor, a tiled floor or a floor with a covering including a carpet, upon an application of an auxiliary medium and an application of



heat with a machine, wherein the machine has means for heating an air stream, at least one rotary disk and at least one drive dish with an opening through said dish for the passage of said hot air stream and at least one opening for said auxiliary medium, comprising the steps:

heating said air stream to provide a heated air stream;
pre-heating said auxiliary medium in said heated air stream to provide a pre-heated auxiliary medium;
directing said heated air stream through said drive dish;
directing said pre-heated auxiliary medium through said drive dish;
heating said pre-heated auxiliary medium with said heated air stream as said pre-heated auxiliary medium and said heated air stream pass through said drive dish.

5,587,022

METHOD OF RINSING SHOWERS

Robert H. Black, 4858 Mariner Point, Jacksonville, Fla. 32225

Division of Ser. No. 374,918, Jan. 19, 1995, abandoned, which is a continuation-in-part of Ser. No. 162,751, Dec. 7, 1993, abandoned. This application May 11, 1995, Ser. No. 439,382

Int. Cl.⁶ B08B 3/04; 3/08

U.S. Cl. 134—26

20 Claims

1. A method of rinsing showers clean, consisting essentially of repeated cycles of the steps of:

wetting surfaces of a shower;
spraying the wet shower surfaces after showering with an aqueous rinsing solution comprising:
0.5% to 3% by volume of a non-ionic surfactant having an HLB of 13 or less;

1 to 8% by volume of an alcohol selected from the group consisting of isopropyl alcohol, ethyl alcohol, n-propyl alcohol, n-butyl alcohol, isobutyl alcohol, and glycerol; and
0.1 to 3% by volume of a chelating agent, wherein said aqueous rinsing solution has a pH in a range of 4 to 8, whereby deposits resulting from showering are removed, without scrubbing or wiping by allowing said aqueous rinsing solution to transport said deposits down the shower surfaces to a drain, said shower surfaces air-drying spot-free and without streaking.

5,587,023


METHOD OF REMOVING A WHIRLPOOL JET APPARATUS FROM A WHIRLPOOL BATHTUB FOR INSPECTION, CLEANING OR REPAIR

John W. Booth, Irving, Tex., assignor to Sanijet Corporation, Dallas, Tex.

Continuation of Ser. No. 147,201, Nov. 3, 1993, Pat. No. 5,414,878. This application May 16, 1995, Ser. No. 442,548
Int. Cl.⁶ B08B 7/00

U.S. Cl. 134—32

14 Claims



1. A method of removing a jet assembly for inspection, cleaning and repair from a whirlpool jet apparatus, the apparatus comprising a jet casing mounted in a tub aperture in a water tight manner providing an open end facing into tub interior, and a jet assembly for receiving and pumping water being insertable and removable through said open end, the method comprising the steps of:
disengaging the jet assembly from the jet casing without breaking a water tight seal; and
removing the jet assembly from the casing as a one piece unit.

5,587,024

SOLID RESIN-COATED MAGNET POWDER AND A METHOD FOR PRODUCING AN ANISOTROPIC BONDED MAGNET THEREFROM


Ryoji Nakayama; Takuo Takeshita, and Muneaki Watanabe, all of Saitama-ken, Japan, assignors to Mitsubishi Materials Corporation, Tokyn, Japan

Division of Ser. No. 71,565, Jun. 1, 1993, abandoned. This application Apr. 17, 1995, Ser. No. 423,272

Claims priority, application Japan, Jun. 1, 1992, 4-165349
Int. Cl.⁶ H01F 1/03

U.S. Cl. 148—101

4 Claims



1. A method for making a solid resin-coated magnet powder comprising:
forming an alloy ingot;
heating said alloy ingot in a hydrogen atmosphere;
continuing said heating to promote phase transformation of said alloy ingot;
maintaining said alloy ingot in a vacuum at an elevated temperature to further promote phase transformation;
grinding said ingot to produce an anisotropic powder;
dissolving a plastic resin in a solvent to produce a solution;
mixing said anisotropic powder with said solution;
kneading said anisotropic powder in said solution in a vacuum until said solvent is substantially completely volatilized;

granulating the product of said kneading step to produce a composite powder; and
ball milling said composite powder to produce a resulting product containing a substantial fraction consisting of individual magnet powder particles coated with said plastic resin.

5,587,025

NUCLEAR STEAM GENERATOR CHEMICAL CLEANING PASSIVATION SOLUTION

John M. Jevic, Uniontown, Ohio, and Randall P. Dow, Lynchburg, Va., assignors to Framatome Technologies, Inc., Lynchburg, Va., and The Babcock & Wilcox Company, New Orleans, La.

Filed Mar. 22, 1995, Ser. No. 408,670
Int. Cl.⁶ C23C 22/60

U.S. Cl. 148—274

4 Claims

1. A method for chemically passivating nuclear steam generator surfaces, comprising the steps of:
during a copper removal step after a copper removal phase when copper concentration stops increasing;
providing a free EDTA solution in an amount of less than or equal to 15 grams per liter of solution but not less than a minimum of about 1 gram per liter of solution;
raising the solution temperature to about 37° C. to 49° C.;
spiking a hydrogen peroxide concentration back to about 2±0.5% (w/v) as a passivation solution; and
exposing the nuclear steam generator surfaces to the passivation solution for a period of at least two hours.

5,587,026

FERROMAGNETIC FILM

Hitoshi Iwasaki; Yuichi Ohsawa, and Reiko Kondoh, all of Yokohama, Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Continuation of Ser. No. 188,747, Jan. 31, 1994, Pat. No. 5,484,491, which is a continuation of Ser. No. 954,042, Sep. 30, 1992, abandoned. This application Jul. 5, 1995, Ser. No. 498,231

Claims priority, application Japan, Sep. 30, 1991, 3-250674;
Sep. 30, 1991, 3-252448

U.S. Cl. 148—313

Int. Cl.⁶ C22C 19/07

9 Claims



1. A magnetic head comprising a ferromagnetic film having a coercive force of 200 A/m or less and consisting of an alloy represented by the formula:



wherein T is an element selected from the group consisting of

Ta, Ti, Zr, Hf, Mo and W, and x, y, and z represent atomic % and satisfy:
 $73 < x < 94$,
 $5 < y \leq 15$,
 $1 < z < 12$, and
 $x + y + z = 100$,
and wherein said film shows hcp-phase (001) orientation.

5,587,027

METHOD OF MANUFACTURING CANNING STEEL SHEET WITH NON-AGING PROPERTY AND SUPERIOR WORKABILITY


Akio Tosaka; Chikako Fujinaga; Toshiyuki Kato; Kaku Sato, and Hideo Kuguminato, all of Chiba, Japan, assignors to Kawasaki Steel Corporation, Kyogo, Japan

Filed Feb. 15, 1995, Ser. No. 389,045

Claims priority, application Japan, Feb. 17, 1994, 6-020346
Int. Cl.⁶ C22C 38/06; C21D 8/00

U.S. Cl. 148—320

21 Claims



1. A method for manufacturing a canning steel sheet with non-aging property and superior workability, comprising the steps of:

- using, as a starting material, an ultra-low-carbon steel slab consisting essentially of:
C: from 0.0015% to 0.0100% by weight,
Si: up to 0.20% by weight,
Mn: from 0.10% to 1.20% by weight,
Al: from 0.02% to 0.10% by weight,
P: from 0.005% to 0.040% by weight,
S: up to 0.015% by weight,
N: up to 0.005% by weight, and balance iron and unavoidable impurities;
- hot rolling said steel;
- pickling said steel;
- cold rolling said steel at a reduction ratio of at least 70% after said pickling step; and
- recrystallization annealing said steel in a continuous annealing furnace in an atmosphere having a hydrogen content of from 3% to less than 10% and a dew point not lower than -20° C. at a temperature not lower than 730° C. such that the content of remained C in said steel is kept less than 0.0015% by weight.

5,587,028

AMORPHOUS ALLOYS RESISTANT TO HOT CORROSION

Koji Hashimoto, 2-25-5, Shogen, Izumi-ku, Sendai-shi, Miyagi; Hiroki Habazaki, Sendai, both of Japan; Stanislaw Mrowec, and Marek Danielewski, both of Krakow, Poland, assignors to Koji Hashimoto, Miyagi, and YKK Corporation, Tokyo, both of Japan

Continuation of Ser. No. 44,534, Apr. 7, 1993, abandoned.

This application Feb. 9, 1995, Ser. No. 386,121

Claims priority, application Japan, Apr. 7, 1992, 4-085529;
Apr. 7, 1992, 4-085530; Nov. 11, 1992, 4-326075
Int. Cl.⁶ C22C 45/08

U.S. Cl. 148—403

5 Claims

5. A single phase amorphous alloy which is produced by sputtering and resistant to hot corrosion in both sulfidizing and oxidiz-

ing atmospheres at high temperatures, which consists of, at most, 20 atomic percent of at least one element selected from the group of Fe, Co, Ni and Cu, at most, 50 atomic percent of Si and less than 50 atomic percent of the sum of Cr and at least 7 atomic percent of at least one element selected from the group of Mo and W, with the sum of Si and the substantial balance of at least 10 atomic percent of Al being at least 30 atomic percent, said alloy having a parabolic rate constant of oxidation at 950° C. of 5×10^{-12} g² cm⁻⁴ s⁻¹ or smaller and a parabolic rate constant of sulfidation at 950° C., under a sulfur partial pressure of 10^{-2} atm., of 9×10^{-9} g² cm⁻⁴ s⁻¹ or smaller.

5,587,029

MACHINEABLE ALUMINUM ALLOYS CONTAINING IN AND SN AND PROCESS FOR PRODUCING THE SAME

Subhasish Sircar, Richmond, Va., assignor to Reynolds Metals Company, Richmond, Va.

Filed Oct. 27, 1994, Ser. No. 330,514

Int. Cl.⁶ C22C 21/12

U.S. Cl. 148—438

16 Claims

1. A lead-free free-machining aluminum alloy comprising an aluminum alloy including an effective amount of tin and an effective amount of indium, the effective amounts of tin and indium being those amounts of tin and indium that when combined with each other and with other elements in the alloy form low melting point constituents that melt during a machining operation to facilitate formation of proper size machine chips for effective machining, the amount of tin in the alloy ranging from 0.04 to 1.5 wt. %, the amount of indium being greater than 0.10 wt. %, and the alloy having copper as a major alloying element.

5,587,030

TIRE HAVING CARCASS REINFORCEMENT FORMED OF STRIPS


Yves Herbelleau, Riom, France, assignor to Sedepro, Paris, France

Filed Jun. 2, 1995, Ser. No. 458,737

Claims priority, application France, Jun. 28, 1994, 94 08304
Int. Cl.⁶ B60C 9/00; 9/02; 9/08

U.S. Cl. 152—555

7 Claims



1. A tire reinforced by at least one so-called carcass reinforcement present at least in the sidewalls of said tire in which the carcass reinforcement has a circumferential arrangement of lengths of cord arranged side by side, said lengths being of a length less than the height of the sidewall of the tire in question, said lengths extending transversely with respect to the circumferential direction, said lengths being embedded in a matrix of elastomeric material, said circumferential arrangement being arranged in such a manner that, when the carcass reinforcement is observed in radial section, said lengths of cord show at least a certain overlap.

5,587,031


EDGE-FOLDED TINSEL GARLAND AND METHOD OF PRODUCTION

Kevin Young, Bensalem, Pa., assignor to F. C. Young & Co., Inc., Yardley, Pa.

Division of Ser. No. 298,267, Aug. 31, 1994, Pat. No. 5,500,258. This application Jul. 20, 1995, Ser. No. 504,476
Int. Cl.⁶ A41G 1/04

U.S. Cl. 156—148

5 Claims



1. The method of making a tinsel garland, comprising the steps of: providing an elongate strip of web material; folding at least one edge of said web material along a longitudinal foldline defining a boundary of a side portion parallel to said edge so that said side portion is folded over face-to-face; creasing said web material along said foldline by applying pressure to the opposite sides of the folded web; cutting said folded web material transversally along a plurality of parallel cut lines to form a plurality of needles with free ends at said edge and an uncut portion at the center of said web material, said needles having bent tabs formed by the folded portions of the web material between said foldline and said edge; and twisting said uncut portion of said folded and cut web about a pair of wires along a central axis forming a substantially cylindrical garland having radially-projecting needles with bent tabs at the free ends of said needles.

5,587,032


METHOD AND APPARATUS FOR REGISTRATION OF A SEAL ON A PLASTIC BAG

Stephen A. Saindon, Appleton; Peter J. Gietman, Jr., Combined Locks, and Nicholas J. Nagel, Oregon, all of Wis., assignors to CMD Corporation, Appleton, Wis.

Continuation-in-part of Ser. No. 228,566, Apr. 15, 1994, Pat. No. 5,518,559, which is a continuation-in-part of Ser. No. 105,434, Aug. 12, 1993, abandoned. This application Aug. 12, 1994, Ser. No. 289,426
Int. Cl.⁶ B32B 31/00

U.S. Cl. 156—64

19 Claims



7. A method for making plastic bags from plastic film having a plurality of registration marks using a bag making machine having

a cylindrical drum with a variable diameter, a circumference, an axis and at least one seal bar substantially parallel to the axis and defining the circumference, comprising:

detecting the rotation of the drum;
detecting the registration marks on the film;
determining the nominal length of the bags from the detection of the registration marks and the rotation of the drum;
determining a phase of the registration mark relative to a seal on the plastic bag;
adjusting the diameter of the drum in a first direction in response to the nominal bag length and the phase of the registration mark relative to the seal on the plastic bag such that a circumferential distance between subsequent seal bars is changed in a first direction to be substantially equal to the nominal bag length; and
continued adjusting of the diameter of the drum in the first direction such that the circumferential distance between subsequent seal bars is not substantially equal to the nominal bag length.

5,587,033

PROCESS FOR THE PREPARATION OF RADIATION IMAGE STORAGE PANELS

Hideki Suzuki, and Katsuhiko Kohda, both of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Division of Ser. No. 196,460, Feb. 15, 1994, which is a division of Ser. No. 692,649, Apr. 29, 1991, Pat. No. 5,306,367. This application Jun. 6, 1995, Ser. No. 468,326

Claims priority, application Japan, Apr. 27, 1990, 2-112505; May 11, 1990, 2-122380; Jun. 20, 1990, 2-161518

Int. Cl.⁶ B29C 55/06; B32B 31/20; 31/26; G03C 1/00

U.S. Cl. 156—164

6 Claims



1. A process for the preparation of a radiation image storage panel comprising the steps of: forming a phosphor sheet comprising a binder and a stimutable phosphor; and compressing the phosphor sheet on a support under heating up to a temperature of not lower than softening point or melting point of the binder by means of a heated calender roll, keeping the phosphor sheet under tension in the range of 10–700 g/cm.

5,587,034

PROCESS FOR PULTRUDING FIBER REINFORCED FURAN COMPOSITES

Chen-Chi M. Ma, Hsinchu, Taiwan, assignor to National Science Council, Taipei, Taiwan

Filed Oct. 23, 1992, Ser. No. 965,864

Int. Cl.⁶ B29C 70/52

U.S. Cl. 156—166

6 Claims

1. A process for pultruding a fiber reinforced furan resin composite which comprises drawing a plurality of continuous filaments through an impregnating bath of liquid furan resin to saturate the filaments with said resin and a squeeze orifice to remove excess resin and air, and

continuously pulling the resin-impregnated filaments through a pultrusion die to heat and cure said resin,

wherein the liquid furan resin comprises a furfuryl alcohol prepolymer which is prepared by polymerizing 100 parts by weight of furfuryl alcohol monomer with an addition of 0.05–2.5 parts by weight of an acid catalyst at a temperature of 35–70° C. until the resulting polymerization mixture has a viscosity of 300–400 cps,

and wherein the liquid furan resin is maintained at a temperature of 15–35° C. and has a viscosity ranging from 500–3000 cps during the impregnating step,

and wherein the pultrusion die has three heating zones through which the resin is pultruded, the first zone having a temperature range of 150–180° C., the second zone having a temperature range of 180–225° C., and the third zone having a temperature range of 170–220° C., and wherein the temperature in the second zone is higher than the temperatures in the first and third zones.

5,587,036

PROCESS FOR THE PRODUCTION OF BLANKS FOR MOTOR VEHICLE LICENSE PLATES

Joachim Utsch, Alte Dreisbachstr. 19, 5900 Siegen; Gerhard Utsch, and Manfred Utsch, both of Siegen, all of Germany, assignors to Joachim Utsch, Siegen, Germany


Filed Dec. 17, 1991, Ser. No. 808,768

Claims priority, application Germany, Dec. 17, 1990, 40 40 386.6

Int. Cl.⁶ B32B 31/16; B60R 13/10

U.S. Cl. 156—219

1 Claim



1. A process for the production of automotive vehicle license plates, comprising unreeling from a coil a continuous length of metal strip, applying to said length of metal strip a colored film that imparts to said strip a series of colored rims, severing said length of strip into individual license plate blanks bordered by said rims and embossing only said rims thereby to produce raised rims about the periphery of each severed blank, subsequently embossing on said blank individual characters identifying a particular automotive vehicle, and applying to said characters a paint of a color contrasting with the background of said characters by applying to said characters a strip bearing said paint and having a width substantially less than the distance between upper and lower said rims of said blank.

5,587,035

COMPOSITE FILLED HOLLOW STRUCTURE


Robert H. Greene, 131 Stable Dr., Lancaster, Pa. 17603

Division of Ser. No. 915,315, Jul. 20, 1992. This application Dec. 8, 1994, Ser. No. 352,350

Int. Cl.⁶ E04G 21/00

U.S. Cl. 156—187

3 Claims



1. A method of constructing a filled structure characterized by the combination of high compressive strength and tensile strength to allow a high bending load comprising:

providing a fiber reinforced resinous hollow structure having a tensile strength of at least 30,000 psi and an inside surface forming a boundary which encloses a space,

providing a mixture of particulate cementitious material and liquid which may be hardened into a hard core, said mixture being selected so that the hard core formed therefrom has a density of at least 35 pounds per cubic foot and a compressive strength of at least 1500 psi and the mixture expands its volume as it hardens,

placing the mixture within the space, and permitting said mixture to expand and harden into the hard core within the hollow structure in such a manner that expansion of the mixture is restrained by the hollow structure and the hard core exerts a force against the inside surface of the hollow structure such that the hard core is force-fit against the inside surface to provide said filled structure.

5,587,037

MULTI-LAYER SHEET MATERIAL HAVING A REFRACTIVE SURFACE AND METHOD FOR MAKING SAME


Alan E. Fellner, Macedonia, Ohio, assignor to Custom Graphics, Solon, Ohio

Filed Nov. 23, 1994, Ser. No. 344,566

Int. Cl.⁶ B44C 1/165

U.S. Cl. 156—231

8 Claims



1. A process for making a multi-layer metallic-foil printed sheet material comprising the steps of:

positioning a sheet media and a foil sheet having a carrier and metal foil thereon, in a stamping press;
moving a heat transfer plate die into engagement with the carrier of the foil sheet and pressing the sheet media against the foil sheet with the die, said die having reliefs etched therein;
releasing from the foil sheet a metal foil design shape by supplying heat to the die, said metal foil design shape corresponding to the reliefs etched in the die;
bonding the metal foil design shape to the sheet media by means of heat supplied by the die;
applying a first laminate coating over the surface of the sheet media having the metal foil design shape thereon;


applying printing ink to the first laminate coating using an offset printing press;
applying a second laminate coating over the printing ink; and
applying a high gloss coating over the second laminate coating.

5,587,038

APPARATUS AND PROCESS FOR PRODUCING HIGH DENSITY AXIALLY EXTENDING PLASMAS
Joseph L. Cecchi, and James E. Stevens, both of Albuquerque, N.M., assignors to Princeton University, Princeton, N.J.
Filed Jun. 16, 1994, Ser. No. 261,853
Int. Cl.⁶ C23F 1/02

U.S. Cl. 156—345

18 Claims



1. An apparatus for producing a plasma comprising:
a processing chamber;
gas supplying means for supplying gas to said processing chamber;
a radio frequency power source;
an electrically conductive planar antenna located outside of said processing chamber and electrically coupled to said radio frequency power source to generate a helicon wave in said processing chamber and thereby produce a plasma of a gas in said processing chamber; and
magnetic field generating means located outside of said processing chamber for generating a magnetic field within said processing chamber, said magnetic field generating means generating a magnetic field within said chamber substantially perpendicular to the plane of said planar antenna, the magnetic field causing elongation of said plasma in said processing chamber.

5,587,039

PLASMA ETCH EQUIPMENT
Siamak Salimian, Sunnyvale; Michelangelo Delfino, Los Altos, and Bu-Chin Chung, Saratoga, all of Calif., assignors to Varian Associates, Inc., Palo Alto, Calif.
Division of Ser. No. 818,662, Jan. 9, 1992, Pat. No. 5,376,233.
This application Sep. 12, 1994, Ser. No. 304,719
Int. Cl.⁶ H01L 21/302

U.S. Cl. 156—345

6 Claims



1. In an ECR plasma processing apparatus having a microwave generator coupled to a plasma generating chamber, said plasma generating chamber being disposed in a magnetic field, the maximum intensity of said magnetic field being aligned with the axis of said plasma generating chamber, an interior region of said plasma generating chamber being isolated from said microwave generator by a dielectric microwave window having a first face and a second


face, said first face forming an interior wall of said interior region and said second face being parallel to said first face, the improvement comprising:
said first face of said dielectric microwave window coated with a layer of alumina to preclude plasma etching of and release of oxygen from said first face; and
said second face of said dielectric microwave window formed of a quartz dielectric material.

5,587,040

APPARATUS FOR MANUFACTURING RECAPPED TIRE
Mikio Fujimoto, Higashimurayama, Japan, assignor to Bridgestone Corporation, Tokyo, Japan
Filed Nov. 28, 1995, Ser. No. 563,484
Claims priority, application Japan, Dec. 5, 1994, 6-300843
Int. Cl.⁶ B29D 30/54

U.S. Cl. 156—394.1

20 Claims



1. An apparatus for manufacturing a recapped tire, comprising:
a vulcanizer in which is filled a fluid for vulcanization for adhering by vulcanization a base tire and a tread;
a rim to which the base tire is mounted;
an envelope which is annular and covers an outer periphery of the base tire;
suction means for sucking air from between the base tire and said envelope;
a tube which is annular and expandable and contractible, said tube being provided at a portion of said rim corresponding to an outer side of the base tire along a tire axial direction, and pushing said envelope against a bead portion of the base tire;
a stopper provided at a portion of said rim corresponding to an inner side of the base tire along the tire axial direction, and preventing movement of the bead portion toward the inner side of the base tire along the tire axial direction; and
internal pressure providing means for providing internal pressure to said tube so as to inflate said tube.


5,587,041

COMPOSITE PREPREG APPLICATION DEVICE
Donald A. Sandusky, Williamsburg, and Joseph M. Marchello, Hampton, both of Va., assignors to The United States of America as represented by the Administrator of the National Aeronautics and Space Administration, Washington, D.C.
Division of Ser. No. 411,231, Mar. 21, 1995, abandoned. This application Jun. 1, 1995, Ser. No. 457,608
Int. Cl.⁶ B65H 81/00

U.S. Cl. 156—441

2 Claims

1. A device for applying composite prepreg comprising:
an attachment base having means for attaching to a conventional robotic lay-up machine and having an electrical supply and cooling fluid supply;



a heated shoe assembly attached to said attachment base and enclosing a means for heating said shoe assembly; and
a pressure roller rotatably attached to said attachment base, said roller having a means for cooling which comprises an external cooling shoe.


5,587,042

ADHESIVE CURING SYSTEM AND METHOD FOR A HEMMING MACHINE

Lucien St. Denis, Windsor, Canada, assignor to E. R. St. Denis & Sons Ltd., Oldcastle, Canada
Continuation-in-part of Ser. No. 307,470, Sep. 19, 1994, abandoned. This application May 17, 1995, Ser. No. 443,334
Int. Cl.⁶ B32B 31/20; C09J 5/06

U.S. Cl. 156—477.1

14 Claims



1. A machine for hemming a flange on a first rigid panel with an edge portion of a second rigid panel to form a hem, one of said panels having adhesive located in the hem, said machine comprising:
(a) a panel support nest having a top surface for supporting the first panel and the second panel in a superimposed relation such that the flange of the first panel is pressed against the flange of the second panel;
(b) a support surface heater for heating a portion of the support surface of the support nest;
(c) a plurality of first flange bending members having bevelled engaging surfaces, the first flange bending members being located at a pre-hem position;
(d) a plurality of second flange bending members located at a final hem position;
(e) a second flange bending member heater for heating a section of each of the plurality of second flange bending members;
(f) means for moving the support nest to the pre-hem position such that the flange of the first panel is pressed against the bevelled engaging surfaces of the first flange bending members wherein the flange of the first panel is bent to approximately 45° with respect to the plane of the first panel to form a pre-hemmed flange; and
(g) means for moving the support nest to the final hem position such that the pre-hemmed flange is pressed against the second flange bending members, wherein said pre-hemmed flange of the first panel is bent to fully clinch said edge portion of the

second panel to form the hem and whereby upon forming the hem the adhesive is heated and at least partially cured.


5,587,043

THIN LABEL APPLICATOR

Clement F. Hying, Menomonee Falls; Jack E. Perko, Cedarburg, and Larry E. Wenzler, Oak Creek, all of Wis., assignors to Brady USA, Inc., Milwaukee, Wis.
Filed Jun. 5, 1995, Ser. No. 462,298
Int. Cl.⁶ B65C 9/00

U.S. Cl. 156—566

8 Claims



1. A device for applying adhesive coated, thin labels carried on a web roll in which each label has a leading edge, a trailing edge, an adhesive face and a nonadhesive face, said device comprising:
a. a label drum for holding the web roll;
b. a peel plate around which the label bearing web is guided, wherein an abrupt change in direction of the web around the peel plate initiates separation of the leading edge of a label from the web;
c. a vacuum transfer drum for picking up the separated labels at a pick-up station adjacent said peel plate and moving the labels to a transfer station, said vacuum transfer drum comprising:
i. a drum;
ii. at least one vacuum pad mounted on the periphery of said drum, said vacuum pad having a plurality of apertures;
iii. vacuum means in the interior of said drum for applying a negative pressure at the surface of said vacuum pad by way of said apertures, wherein said vacuum means applies said negative pressure only as the drum rotates between the pick-up station and the transfer station;
d. a take-up drum for receiving the web after the labels have been removed;
e. means for driving the web between said label drum and said take-up drum;
f. a shuttle for holding and moving articles to and from the transfer station, such that articles are placed in contact with labels as the labels arrive at the transfer station;
g. a first sensor for detecting the position of the shuttle;
h. a second sensor for detecting the position of the drum;
i. a third sensor for detecting when web mounted labels are in position for being picked up; and
j. a fourth sensor for detecting either the leading edge or trailing edge of a label as it is held on said vacuum pad to verify the position of the label on the pad for proper alignment with the article carried by said shuttle.

5,587,044


LABEL CASSETTE RETAINING DEVICE FOR LABELER
Fumio Goto, Iwate-ken, Japan, assignor to Kahushiki Kaisha Sato, Japan

Continuation-in-part of Ser. No. 133,624, Oct. 8, 1993, Pat. No. 5,403,431. This application Apr. 8, 1994, Ser. No. 225,052. Claims priority, application Japan, Oct. 18, 1992, 4-75906; Mar. 10, 1994, 6-003376

Int. Cl.⁶ B32B 31/00

U.S. Cl. 156—577

6 Claims



1. A labeler comprising:

- a main body;
- a label cassette for holding a roll of labels, the roll of labels comprising a label strip of separate labels and a continuous backing strip to which the labels are separably adhered;
- label strip advancing means for advancing the label strip off the roll;
- label removing means for engaging the label strip after it has left the roll and for removing the labels from the backing strip;
- an outlet from the main body for labels removed from the backing strip; and
- a retainer on the label cassette for restricting lateral movement of and for guiding the label strip moving off the label roll and being adjustable for different width label strips, the retainer comprising:
 - a first side plate for engaging one side edge of the label strip;
 - a second side plate for engaging the other side edge of the label strip; the second side plate being movable toward or away from the first side plate for adjusting the space between the plates for guiding different width label strips; and
 - a grip for moving the second side plate and for engaging a slot on the main body.

5,587,045

GETTERING OF PARTICLES FROM AN ELECTRO-NEGATIVE PLASMA WITH INSULATING CHUCK

John H. Keller, Newburgh, and Gregory Costriani, Hopewell Junction, both of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 27, 1995, Ser. No. 430,040


Int. Cl.⁶ H01L 21/306

U.S. Cl. 156—627.1

5 Claims

1. In a plasma processing system used in the manufacture of semiconductor circuits wherein a semiconductor wafer is mounted on a negative electrode and exposed to a plasma discharge, said wafer being separated from said negative electrode by an insulator, an apparatus for preventing negatively charged particulates from going to the wafer when the plasma discharge is turned off, said apparatus comprising:

- a sensing device connected to said negative electrode through a diode and a choke;
- a source of voltage between said sensing device and circuit ground; and
- bias control means connected across said capacitor for controlling said source of voltage to maintain a small negative bias on said wafer when plasma density decays to zero.



5,587,046

PROCESS FOR TREATING SEMICONDUCTOR MATERIAL WITH AN ACID-CONTAINING FLUID

Maximilian Stadler, Haiming; Günter Schwab, Emmerting; Peter Romeder, Burghausen, and Gabriele Trifellner, Wnhoring, all of Germany, assignors to Wacker Siltronic Gesellschaft Für Halbleitermaterialien Aktiengesellschaft, Burghausen, Germany

Filed Apr. 10, 1995, Ser. No. 419,362

Claims priority, application Germany, Apr. 28, 1994, 44 14 925.5

Int. Cl.⁶ H01L 21/00

U.S. Cl. 156—662.1

10 Claims

3. A process for treating semiconductor material with an acid-containing fluid, water being formed as the product of a chemical reaction, which comprises adding phosphorus pentoxide to the acid-containing fluid during the treatment of the semiconductor material.

5,587,047

METHOD FOR SEPARATING BORIC ACID

Aimé Bruggeman, Retie, and Johan Braet, Nazareth, both of Belgium, assignors to Studiecentrum voor Kernenergie, Belgium


Continuation of Ser. No. 260,786, Jun. 16, 1994, Pat. No. 5,468,347. This application Sep. 8, 1995, Ser. No. 525,216

Claims priority, application Belgium, Jun. 16, 1993, 09300608

Int. Cl.⁶ B01D 1/00; 3/38; G21F 9/08

U.S. Cl. 159—47.300

17 Claims



1. A method for removing boric acid from water having boric acid dissolved therein which comprises introducing said water having boric acid dissolved therein into an evaporator wherein the temperature in the evaporator is more than 100° C. and the pressure in the evaporator is above atmospheric pressure; said water having a substantially neutral or acidic pH; heating said water to form steam whereby boric acid is removed from said water by transfer from said water to said steam so as to produce steam

enriched with boric acid; removing said boric acid enriched steam from said evaporator and removing, from the evaporator, the water from which boric acid has been removed.

10. A method for removing boric acid from a liquid containing boric acid which comprises introducing a liquid containing boric acid into an evaporator wherein the temperature in the evaporator is more than 100° C. and the pressure in the evaporator is above atmospheric pressure; and liquid having a substantially neutral or acidic pH; introducing steam into said evaporator whereby boric acid is removed from said liquid by transfer from said liquid to said steam so as to produce steam enriched with boric acid; removing said boric acid enriched steam from said evaporator and removing, from the evaporator, the liquid from which boric acid has been removed.

5,587,048

PULP AND PAPER PRODUCTS PRODUCED FROM RECYCLED, HIGH LIGNIN CONTENT, WASTE PAPER

Robert C. Streisel, Mt. Pleasant, S.C.; Mark A. Hank; Leo T. Mulcahy, both of Covington, Va., and Ralph S. Peterson, Clifton Forge, Va., assignors to Westvaco Corporation, New York, N.Y.

Continuation of Ser. No. 216,448, Mar. 23, 1994, abandoned, which is a division of Ser. No. 21,662, Mar. 9, 1993, abandoned, which is a continuation-in-part of Ser. No. 862,996, Apr. 6, 1992, abandoned. This application Mar. 15, 1996, Ser. No. 616,762

Int. Cl.⁶ D21C 5/02

U.S. Cl. 162—7

5 Claims

1. A fiber pulp for a generally streak and scratch-free blade-coated paper from a furnish having at least 10% by weight of said fiber pulp produced from recycled paper substantially comprised of recycled corrugated containers, said fiber pulp containing less than about 20 ppm per unit area of solid, non-fibrous contaminants of a size greater than 0.05 mm², said fiber pulp being produced from said recycled paper by a method comprising the steps of:

- a) combining a quantity of paper substantially comprised of corrugated containers to be recycled, containing lignin, cellulose fibers and solid non-fibrous contaminants, with an aqueous liquid to form a slurry containing about 9–15% by weight solids and agitating said slurry in a low shear mixer at a temperature of less than 65.6° C. for a time sufficient to separate said lignin and cellulose fibers from said solid contaminants without significantly degrading said solid contaminants, and then sequentially;
- b) removing from said slurry gross contaminants of a size in a range greater than about 5 mm² by passing said slurry through holes of a predetermined diameter;
- c) removing from said slurry contaminants having a specific gravity in a range greater than 1;
- d) removing from said slurry intermediate contaminants having a size in a range greater than about 2 to 3 mm² by passing said slurry through holes of a predetermined size;
- e) removing sand from said slurry;
- f) removing from said slurry fine contaminants of a size in a range at least about 0.15 mm², by passing said slurry through elongated slots of a predetermined width;
- g) removing from said slurry by centrifugal means contaminants having a specific gravity less than 1;
- h) dewatering said slurry to form a wet, friable pulp having a moisture content of about 30–60%;
- i) digesting said pulp in a cooking liquor for a time and at a temperature sufficient to hydrolyze a substantial portion of said lignin remaining in intimate association with said cellulose fibers wherein said digesting takes place at a target temperature in a range of 121°–150° C.; and
- j) separating said digested pulp from spent cooking liquor.

5,587,049

PROCESS FOR DELIGNIFYING RAW CELLULOSIC MATERIAL IMPREGNATED WITH MONOPERSULPHURIC ACID

Fausto Marzolini; Giulio Calmanti, both of Milan, and Gianpiero Sacchi, Trivolzio, all of Italy, assignors to Ausimont S.p.A., Italy

Continuation of Ser. No. 9,719, Jan. 27, 1993, abandoned.

This application Apr. 8, 1994, Ser. No. 225,353

Claims priority, application Italy, Jan. 31, 1992, MI92A0192

Int. Cl.⁶ D21C 3/04; 3/26

U.S. Cl. 162—40

6 Claims

1. A process for delignifying raw lignocellulosic material comprising:

- (1) a first step comprising:
 - (a) impregnating raw lignocellulosic material with an acid solution containing monopersulphuric acid or salts thereof in an amount ranging from 0.3 to 14% by weight of dry cellulose and sulphuric acid in an amount ranging from 0.4 to 18% by weight of dry cellulose, at a temperature lower than 20° C. and for a time ranging from 5 to 90 minutes to form impregnated lignocellulosic material;
 - (b) thickening the impregnated lignocellulosic material of step (1)(a) to obtain a concentrated pulp of impregnated lignocellulosic material containing from 5 to 30% of dry matter by separating the acid solution from the impregnated lignocellulosic material without any washing of the impregnated lignocellulosic material with water;
 - (c) recycling at least a portion of the solution obtained from the thickening of step (1)(b) to the acid solution of step (1)(a), and
- (2) conducting a second step prior to any washing of the impregnated lignocellulosic material of step (1) with water comprising:
 - treating the thickened, impregnated lignocellulosic material of step (1) with an alkaline medium at a pH higher than 9 to 12.5, at a temperature lower than 40° C., and for a time sufficient to obtain a substantial reduction in the amount of lignin contained in the thickened, impregnated lignocellulosic material.

5,587,050

Patent Not Issued For This Number

5,587,051

SIMPLIFIED LASER APPARATUS AND METHOD FOR MEASURING STOCK THICKNESS ON PAPERMAKING MACHINES

Volker Ostermayer, 209 Gilderbrook Rd., Greenville, S.C. 29615, and Thomas B. Fleischer, 108 Meadowood Ct., Pelzer, S.C. 29669

Continuation-in-part of Ser. No. 282,924, Jul. 29, 1994. This application Nov. 14, 1994, Ser. No. 337,770


Int. Cl.⁶ D21F 7/00; G01N 21/90

U.S. Cl. 162—198

31 Claims

1. An apparatus for monitoring the de-watering performance of a forming section of a papermaking machine, said forming section including an associated structure having a side frame and an endless paper forming fabric which travels about a plurality of rolls; said paper forming fabric having an upper horizontal run, a head box for depositing paper stock consisting of a water/fiber mixture on top of said upper horizontal run of said forming fabric; a plurality of de-watering mechanisms disposed sequentially underneath said fabric along said upper horizontal run of said fabric for removing water from said stock; wherein said apparatus comprises:

- a carrier stand having a pair of spaced apart legs including a top leg and a bottom leg for being positioned above and below said horizontal run of said fabric, respectively;



a laser instrument carried by said top leg portion of said carrier stand and having a laser beam;
 a baseline contact device carried by said bottom leg portion of said carrier stand for contacting a bottom surface of said horizontal run of said fabric to establish a baseline reference a first distance directly below said laser instrument;
 said carrier stand positioning said laser instrument above said upper horizontal run of said forming fabric so that said laser beam is reflected from a top horizontal surface of said paper stock and said carrier stand supporting said baseline device which contacts said bottom surface of said upper horizontal run of said forming fabric which is devoid of said paper stock;
 said laser instrument including a laser displacement meter having a receiver for receiving said reflected laser beam of said laser meter and generating a signal corresponding to said reflected laser beam and distance to said upper run of said fabric; and
 a controller for receiving said signal and for computing and generating an output representative of a thickness of said paper stock, and hence the relative water content of said stock, based on said signal and said baseline reference.


5,587,052

APPARATUS AND METHOD FOR TENSIONING A FABRIC IN A PAPER MACHINE

Jukka Autio, Karstula, and Timo Kujala, Jyväskylä, both of Finland, assignors to Valmet Corporation, Helsinki, Finland
 Filed Jan. 27, 1994, Ser. No. 189,115
 Claims priority, application Finland, Jan. 29, 1993, 930398
 Int. Cl.⁶ D21F 3/00

U.S. Cl. 162—273

19 Claims



1. Apparatus for tensioning a fabric in a paper machine, comprising
 a frame defining a driving side of the apparatus on a first side thereof and an operating side of the apparatus at a second side thereof opposite to said first side;
 a tensioning roll mounted on said frame and arranged in a loop of the fabric;
 bearing supports for supporting ends of said tensioning roll, sledges to which said bearing supports are fixed at the driving side and at the operating side of the apparatus.

a drive motor for moving said sledges synchronously in relation to one another to thereby regulate the tension in the fabric that runs over said tensioning roll,
 linear guide means for guiding movement of said sledges in a substantially linear direction, said linear guide means comprising linear guide rails coupled to said frame and linear ball-bearing units coupled to said sledges, said linear ball-bearing units engaging with said linear guide rails,
 shafts journaled on said sledges and operated by said motor to displace said sledges guided along said linear guide rails of said linear guide means, and
 synchronization means for synchronizing said shafts journaled on said sledges and thus the movement of said sledges.


5,587,053

BOILER/CONDENSER ASSEMBLY FOR HIGH EFFICIENCY PURIFICATION SYSTEM

Robert C. Keith, Redondo Beach, Calif., assignor to Grano Environmental Corporation, Carson, Calif.
 Filed Oct. 11, 1994, Ser. No. 320,233
 Int. Cl.⁶ B01D 3/00

U.S. Cl. 202—172

3 Claims



1. A boiler and condenser device comprising: a plate-in-frame heat exchanger including a plurality of vertically extending common plate members, a plurality of alternating boiling and condensing chambers on opposite sides of said common plate members, means for conveying feed material into said boiling chambers, means for conveying vapors from said boiling chambers into said condensing chambers, a face of each common plate member in a condensing chamber having a corrugated herringbone surface configuration, a plurality of diagonal vapor flow paths for directing vapors from the boiling chambers diagonally across the condensing chamber, the corrugated surfaces of oppositely facing adjacent common plate members having portions in abutting relationship to form contact points between adjacent common plate members, said contact points providing accumulation points for liquid forming on condensing surfaces of said common plate members, a plurality of diagonal liquid flow paths adjacent the diagonal vapor flow paths for directing the liquid to flow down the condensing surface into run-off streams, and a run-off area on the condensing surfaces communicating with the lower ends of the diagonal liquid flow paths for carrying a large volume of liquid off the plate members while occupying a small portion of the total surface area of the plate.

5,587,054


VAPOR COMPRESSION DISTILLATION SYSTEM

Robert C. Keith, Redondo Beach, Calif., assignor to Grano Environmental Corporation, Carson, Calif.
 Filed Oct. 11, 1994, Ser. No. 320,235
 Int. Cl.⁶ B01D 3/10

U.S. Cl. 202—182

4 Claims

1. A vapor compression distillation system comprising, a plate-in-frame heat exchanger including a plurality of vertically extend-



ing plate members, a plurality of alternating boiling and condensing chambers on opposite sides of said plate members, means for conveying incoming feed material into said boiling chambers, a vacuum pump for providing the system with a vacuum for matching the temperature of the boiling chambers with the temperature of the incoming feed material, the inlet of said vacuum pump communicating with non-condensable gases from the incoming feed material and non-condensable gases from a condensate, a vapor outlet port communicating with said boiling chambers, a compressor having an inlet communicating with said boiling chambers, said compressor having an outlet communicating with a vapor inlet port for said condensing chambers, means for flowing an evaporated portion of the feed material in the boiling chambers through the vapor outlet port into the compressor to form superheated steam, means for feeding said superheated steam from the outlet of said compressor to an inlet of said condensing chambers, a condensate outlet port communicating with said condensing chamber, a quench nozzle positioned in proximity to and being in communication with the vapor inlet port of the condensing chambers, and means for directing a portion of condensate through the quench nozzle into the vapor inlet port for desuperheating the superheated system to reduce the steam temperature to saturated steam temperature as it enters the condensing chambers, such that the condensing chambers are maintained at a higher temperature than the boiling chambers, heat released by the steam as it condenses in the condensing chambers on one side of the plate members being transmitted through the plate members to the opposite side thereof into the boiling chambers to evaporate the incoming feed material, thereby providing a high heat transfer coefficient between the steam and plate members.

5,587,055


WATER DISTILLING APPARATUS AND METHOD

Michael O. Hartman, 7553 Brazil Rd., Benton, Ark. 72015; Dale J. Kinder, Benton, Ark.; Randy E. Rainey, Conway, Ark.; Arthur R. Helmich, and Daniel E. Willis, both of Benton, Ark., assignors to Michael O. Hartman, Benton, Ark.
 Continuation-in-part of Ser. No. 143,437, Oct. 26, 1993, Pat. No. 5,484,510. This application Oct. 21, 1994, Ser. No. 327,038
 Int. Cl.⁶ B01D 3/42; C02F 1/04

U.S. Cl. 203—1

22 Claims

21. A method of operating a water distillation unit, comprising: providing an evaporation unit and a heating member within a heating pan to purify incoming water containing contaminants;
 inputting water to the heating pan;
 activating the heating member within the heating pan to generate steam;
 cooling the steam within a condenser unit to form water condensate;



positioning a total dissolved solids probe within the heating pan for measuring total dissolved solids values; and
 partially flushing water from the heating pan in response to the measured total dissolved solids value to lower the total dissolved solids content of the water in the heating pan.

5,587,056

SEPARATION OF ALIPHATIC DIACIDS FROM ADIPIC ACID ADMIXTURES THEREOF

Philippe Denis, Decines; Carl Patols, Lyon, and Robert Perron, Charly, all of France, assignors to Rhone-Poulenc Chimie, Courbevoie Cedex, France
 Filed Jun. 14, 1995, Ser. No. 490,231
 Claims priority, application France, Jun. 14, 1994, 94 07505
 Int. Cl.⁶ B01D 3/34

U.S. Cl. 203—29

22 Claims

1. A process for the separation of at least a fraction of at least one branched, saturated aliphatic diacid having 6 carbon atoms from an admixture thereof with at least adipic acid, comprising at least partially converting said at least one aliphatic diacid in said admixture in the presence of a homogeneous acid catalyst soluble in said admixture and having a pKa less than or equal to 5, or in the presence of a heterogeneous acid catalyst into a corresponding anhydride thereof, and removing said corresponding anhydride or said adipic acid from said admixture.


5,587,057

HIGHLY CONDUCTIVE LIQUID MEDIA ELECTROCOAGULATION

David M. A. Metzler, 1001 Winchester, Kansas City, Mo. 64126, and Albert L. Mauk, Kansas City, Kans., assignors to David M. A. Metzler, Kansas City, Mo.
 Continuation-in-part of Ser. No. 854,360, Mar. 19, 1992, Pat. No. 5,271,814. This application Dec. 7, 1993, Ser. No. 163,683
 Int. Cl.⁶ C25D 17/00

U.S. Cl. 204—228

9 Claims



1. An electrolytic treater apparatus for liquids and comprising:
 (a) an elongated tubular housing formed of conductive material and closed at opposite ends to form an elongated treater chamber;

- (b) means forming a first fluid connection and a second fluid connection positioned respectively adjacent said opposite ends and defining a flow path through said treater chamber;
- (c) power supply means having a first power supply terminal and a second power supply terminal of opposite polarities and having an output voltage;
- (d) an elongated electrode structure extending through said chamber, said electrode structure having multiple conductive sections insulated from one another;
- (e) said power supply means being connected to said housing and said electrode structure in such a manner that, with a conductive liquid present in said chamber, said output voltage is divided across said electrode structure sections; and
- (f) flow reversing valve means fluidically connected to said first and second fluid connections and being reversibly operable to flow a fluid through said flow path in a first direction from the first connection to the second connection or in the reverse direction from the second connection to the first connection.

5,587,058

ELECTRODE AND METHOD OF PREPARATION THEREOF

Victor V. Gorodetsky; Vladimir A. Neburchilov, and Y. M. Kolotyrkin, all of Moscow, Russian Federation, assignors to Karpov Institute of Physical Chemistry, Moscow, Russian Federation

Filed Sep. 21, 1995, Ser. No. 531,405

Int. Cl.⁶ C25B 11/08; 11/10

U.S. Cl. 204—290 F

6 Claims

1. An electrode for electrolysis of solutions of electrolytes comprising a support of film forming metal or alloy thereof, having a composite coating consisting essentially of oxides of metals selected from the group consisting of iridium, ruthenium, titanium and tantalum having molar ratios $(\text{IrO}_2 + \text{RuO}_2) : (\text{TiO}_2 + \text{Ta}_2\text{O}_5)$ of $(1-19) : (3-1)$ wherein $\text{IrO}_2 : \text{RuO}_2$ is $(24-4) : 1$, and $\text{TiO}_2 : \text{Ta}_2\text{O}_5$ is $1 : (0-0.05)$.

5,587,059

ANTICORROSIVE CATHODIC ELECTRODEPOSITION PAINT

Shuhei Yamoto, Hirakata; Koji Ito, Ibaraki, and Mitsuo Yamada, Suita, all of Japan, assignors to Nippon Paint Co., Ltd., Japan

Filed Aug. 10, 1995, Ser. No. 513,232

Claims priority, application Japan, Aug. 11, 1994, 6-212094; Aug. 11, 1994, 6-212095

Int. Cl.⁶ C25D 9/02

U.S. Cl. 204—505

21 Claims

1. In a cathodic electrodeposition paint composition comprising a cationic film-forming epoxy resin and a crosslinker, said crosslinker is a blocked polyisocyanate, both dispersed in an aqueous medium containing a neutralizing agent, the improvement wherein said paint composition further comprises an anticorrosively effective amount of a combination of a water-soluble cerium compound and either a polyvalent metal phosphomolybdate or a copper compound.

5,587,060
METHOD OF REMOVING METAL CONTAINED IN SOLUTION

Naoki Abe, Okazaki; Koji Mizuno, Toyota; Masayuki Sumiyoshi, Okazaki; Katsuya Murakami, Toyota; Kojiro Murayama, Toyota; Koichi Suglura, Toyota; Fumio Kawahara, Toyota; Mitsuru Tomono, Toyota, and Heiji Ojima, 7, Shimoshibehara-cho 4-chome, Kariya-shi, Aichi-ken, all of Japan, assignors to Toyota Jidosha Kabushiki Kaisha; MEC International Corporation, both of Toyota, and Heiji Ojima, Kariya, all of Japan


Filed Sep. 12, 1995, Ser. No. 527,206

Claims priority, application Japan, Sep. 13, 1994, 6-219103; Aug. 11, 1995, 7-205765; Aug. 28, 1995, 7-218820

Int. Cl.⁶ B01D 17/06; C02F 1/48

U.S. Cl. 204—554

4 Claims



1. A method of separating metal from a metal-containing solution, comprising the steps of: adding a surface active agent containing a hydrophilic group, a hydrophobic group and a chelating group to a metal-containing solution; applying an electric field to the mixture solution containing the surface active agent obtained in the preceding step; and separating an aggregate from the solution in which the surface active agent having chelated metal has been aggregated in the preceding two steps.

5,587,061

DEVICE AND METHOD FOR BIOMOLECULE PURIFICATION


Stephen L. Chen, 1300 SW, 185th Ave., Aloha, Oreg. 97007

Filed Nov. 28, 1995, Ser. No. 563,445

Int. Cl.⁶ G01N 27/26; 27/447

U.S. Cl. 204—613

6 Claims



1. A device of modified preparative gel electrophoresis for biomolecule purification, comprising: a lower chamber containing a first buffer and electrode for conducting an electric field of electrophoresis, a balance channel, with a substantially reduced volume capacity, uprising from said lower chamber, said balance channel being sealable by a sealing means for trapping air bubbles generated within said lower chamber; an upper chamber containing a second buffer and an electrode for conducting said electric field of electrophoresis, an inlet on top side of said upper chamber, said inlet being sealable by said sealing means for trapping air bubbles generated within said upper chamber.

an air chamber containing said second buffer and three electrodes immersed in said second buffer, a silicon diode in electric circuit having direct connection with one of said three electrodes in said air chamber for controlling electric current of said one of said three electrodes, a vent connected to said air chamber, said vent being sealable by said sealing means for trapping air bubbles generated within said air chamber, a column channel vertically connecting said upper chamber to said lower chamber via a buffer channel, said buffer channel, with a substantially reduced diameter, located between said column channel and said lower chamber and join to said lower chamber at a site immersed in said first buffer, said column channel located beneath said inlet with said upper chamber and immersed by said second buffer from said upper chamber, a gel column fitted in said column channel loosely for easy placement, gap between said gel column and said column channel being permeable for said second buffer from said upper chamber to said buffer channel, and a fraction storage tubing receiving an outflow of said first buffer from said lower chamber, an outflow of said second buffer from said upper chamber, and an outflow of said air bubbles from said air chamber via a channel means, said channel means linked to said buffer channel at the middle and joined to said air chamber on its top.

a base table for placing a gel thereon; an extractor disposed above said base table for extracting by electrophoresis a migration band at a specified part of said gel; a moving mechanism for moving said extractor three-dimensionally for causing said extractor to extract said migration band at said specified part of said gel; a detector for optically detecting migration patterns in said gel placed on said base table; and a control device for controlling said moving mechanism according to detection by said detector so as to cause said extractor to extract said migration band at said specified part of said gel.

5,587,063

METHOD FOR ELECTROLYTIC COLORING OF ALUMINUM SURFACES USING ALTERNATING CURRENT

Peter Kuhn, Hilden; Christine Schroeder, Duesseldorf; Volker Sander, Hilden; Juergen Lindener, and Loert De Riese-Meyer, both of Duesseldorf, all of Germany, assignors to Henkel Kommanditgesellschaft auf Aktien, Duesseldorf, Germany

PCT No. PCT/EP93/03574, § 371 Date Jul. 28, 1995, § 102(e) Date Jul. 28, 1995, PCT Pub. No. WO94/15002, PCT Pub. Date Jul. 7, 1994

PCT Filed Dec. 16, 1993, Ser. No. 464,702


Claims priority, application Germany, Dec. 24, 1993, 42 44 021.1

Int. Cl.⁶ C25D 11/22

U.S. Cl. 205—173

20 Claims

1. A process for the electrolytic alternating-current coloring of anodized aluminum surfaces, said process comprising steps of: (A) providing an acidic coloring bath A that is substantially free from tin(II) ions and silver ions but contains copper(II) ions and an electrolyte additive A' selected from the group consisting of (A'.a) benzene sulfonates corresponding to general formula (I):




(I)

in which

R stands for one or more position-isomeric moieties, each of which is hydrogen, hydroxyl, carboxyl or aldehyde, with the proviso that not more than one is a carboxylic group (COOH), and

X represents hydrogen or sodium or potassium cation, and (A'.b) naphthalene disulfonates corresponding to general formula (II):



(II)

5,587,062

SAMPLE COLLECTING APPARATUS BY GEL ELECTROPHORESIS


Yoshiyuki Togawa, Osaka, and Makoto Miura, Kyoto, both of Japan, assignors to Shimadzu Corporation, Japan

Filed Jan. 24, 1996, Ser. No. 592,872

Int. Cl.⁶ G01N 27/26; 27/447

U.S. Cl. 204—613

13 Claims



1. A sample collecting apparatus comprising:

a base table for placing a gel thereon;

a cutting tool disposed above said base table for cutting out a specified part of said gel;

a moving mechanism for moving said cutting tool three-dimensionally for causing said cutting tool to cut out said specified part of said gel;

a detector for optically detecting migration patterns in said gel placed on said base table; and

a control device for controlling said moving mechanism according to detection by said detector so as to cause said cutting tool to cut out said specified part of said gel.

7. A sample collecting apparatus comprising:






in which

R' stands for one or more position-isomeric moieties, each of which is hydrogen, hydroxyl, carboxyl or aldehyde, with the proviso that no hydroxy group is present in the 1-position of the naphthalene ring, and

X is as defined above;

(B) providing an acidic coloring bath B that is substantially free from copper(II) ions but contains (B.1) tin(II) ions, silver ions, or both tin(II) and silver ions; and, if bath B contains tin(II) ions, also contains (B.2) an electrolyte additive B' containing:

(B'.1) at least one stabilizer for tin(II) ions, said at least one stabilizer corresponding to one of the general formulas (III) to (VII):



in which



R¹ and R² represent hydrogen, alkyl, aryl, alkylaryl, alkylaryl sulfonic acid, alkyl sulfonic acid and alkali metal salts thereof containing 1 to 22 carbon atoms,

R³ represents one or more hydrogen and/or alkyl, aryl, alkylaryl moieties containing 1 to 22 carbon atoms,

R⁴ represents one or more sulfonic acid groups (SO₃X),

R⁵ represents one or more hydrogen and/or alkyl, aryl and alkylaryl moieties containing 1 to 22 carbon atoms and

X is as defined above, at least one of the substituents R¹, R² and R³ not being hydrogen; and (B'.2) at least one throw improver corresponding to one of the general formulae (VIII) and (IX):



in which

R⁶ stands for one or more position-isomeric moieties, each of which is hydrogen, hydroxyl, carboxyl, aldehyde or C₁-₆ alkyl,

R⁷ represents one or more carboxyl groups (COO) or sulfonic acid groups (SO₃X) and

X is hydrogen or an alkali metal cation selected from sodium and potassium; and

(C) either (C.1) coloring the aluminum surfaces by alternating current electrolysis in first bath (A) and subsequently in bath (B) or (C.2) coloring the aluminum surfaces by alternating current electrolysis first in bath (B) and subsequently in bath (A).

5,587,064 WASTE WATER PURIFICATION PROCESS AND APPARATUS

Günther Hambitzer, Pfinztal; Winfried Böke, Karlsruhe, and Armin Oertel, Pfinztal, all of Germany, assignors to Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V., Munich, Germany


Filed Aug. 10, 1995, Ser. No. 513,235

Claims priority, application Germany, Aug. 13, 1994, 44 28 787.9

Int. Cl.⁶ C02F 1/461

U.S. Cl. 205-742

14 Claims



1. A method for cleaning wastewater containing heavy metals, which are deposited cathodically, with at least one cathode and at least one anode, a cutting device for mechanically removing the heavy metal deposits on the cathode, the removed deposits being separated from the wastewater, with the at least one cathode and the cutting device being moved relative to one another, with a variable pressure force between the at least one cathode and the cutting device and with a lead dioxide layer on the at least one anode being formed in a self-renewing manner by deposition of lead dioxide from the wastewater on an anode base material, and with the lead dioxide layer on the at least one anode is maintained at a specified thickness.

5,587,065 MOBILE SYSTEM FOR THE COLLECTION, SEPARATION AND DISPOSAL OF WET SOLID, OILY AND/OR WATERY WASTE

Thomas J. Burns, Aurora, Ohio, assignor to H2Oil, Inc., Aurora, Ohio

Filed Mar. 23, 1993, Ser. No. 35,626


Int. Cl.⁶ B01D 21/24; 21/34

U.S. Cl. 210-104

19 Claims

5. A separating and disposal system for handling watery, oily waste, which comprises

- first and second fluid chambers disposed generally in a side-by-side arrangement,
- means forming a fluid flow connection between lower portions of said fluid chambers,
- means forming an air flow connection between upper portions of said fluid chambers.



- a fluid inlet means for flowing fluid into the upper portions of said first fluid chamber,
- a fluid outlet communicating with said second fluid chamber and being located at a predetermined height therein to establish a predetermined normal liquid level for said first and second chambers,
- means in said first fluid chamber for sensing the level of an interface between a layer of oily liquid separated from and supported by water,
- a discharge conduit for oily liquid communicating with said first fluid chamber below said normal liquid level for effecting removal of oily liquid from said first fluid chamber,
- means for effecting a flow of liquid into said fluid inlet means and out of said fluid outlet, and
- control means responsive to said means for sensing for periodically and selectively removing oily liquid from said first fluid chamber.

6. A separating and disposal system according to claim 5, further characterized by

- said means for sensing the level of said layer of oily liquid comprising a sensor in said first fluid chamber operative to detect an oil-water interface.

7. A separating and disposal system according to claim 6, further characterized by

- a normally closed oil-receiving vessel, connected to said discharge conduit, for receiving oily liquid from said first fluid chamber,
- said oil-receiving vessel including sensor means for determining a full condition.

5,587,066 BARREL SHAPED SPRING CENTER TUBE FOR A FLUID FILTER

Edward A. Covington, Gastonia, N.C., assignor to Dana Corporation, Toledo, Ohio

Division of Ser. No. 938,430, Aug. 31, 1992, Pat. No.

5,284,579. This application Feb. 8, 1994, Ser. No. 193,225

Int. Cl.⁶ B01D 27/10

U.S. Cl. 210-130


20 Claims

20. A filter unit comprising:
a hollow container having a closed end and an opened end;
a hollow cylindrical filter element disposed within said container;

an end plate supported on said container adjacent said opened end, said end plate having a plurality of fluid inlet ports and a fluid outlet port formed therethrough;

a valve disposed within said container, said valve including an annular housing having a first end, a second end, and an annular flange between said first end and said second end which extends radially outwardly between said filter element and said end plate, said first end of said housing being disposed within said filter element; and

a spring disposed within said container having a first end portion, a central portion, and a second end portion, said spring extending through said filter element and reacting between said closed end of said container and said valve annular housing to urge said valve into engagement with said end



plate, said first end portion of said spring defining an outer diameter which is smaller than an outer diameter defined by said central portion of said spring.

5,587,067 WASTEWATER TREATMENT APPARATUS


Leonard S. Love, Mississauga, Canada, assignor to Sydle Inc., Mississauga, Canada

Filed Jun. 21, 1995, Ser. No. 493,074

Int. Cl.⁶ C02F 9/00

U.S. Cl. 210-155

14 Claims



1. A unitary wastewater treatment apparatus having an inlet for raw wastewater and a treated effluent outlet, the apparatus comprising:

a screen filter for receiving raw wastewater from said raw wastewater inlet and removing coarse particles from the wastewater, said screen filter having an outlet;

a flume having an inlet coupled to said outlet, and a discharge; de-ragging means in said flume;

scum and grit removal means comprising a tank for receiving wastewater from said flume and for containing a body of water to a defined level, said tank having an effluent outlet communicating with said treated effluent outlet of the apparatus, a skimmer for removing scum from the surface of said body of water, pre-aeration means for aerating water in the tank, and grit removal means; and

chemical mixing means between said flume discharge and said treated effluent outlet of the apparatus.

5,587,068


MULTI-ATTITUDE DEAERATOR FOR OIL TANK

Wilho V. Aho, Jr., West Palm Beach; Stephen R. Jones, Tequesta; Gregory E. Chetta, Palm Beach Gardens, and Terry H. Strout, Palm City, all of Fla., assignors to United Technologies Corporation, Hartford, Conn.

Filed Nov. 15, 1994, Ser. No. 340,498
Int. Cl.⁶ B01D 19/00; 21/26

U.S. Cl. 210—188

9 Claims



1. A deaerator apparatus for removing air entrained in oil having wall means for defining an enclosed chamber and vortex generating means in said chamber, the air entrained in oil being an air/oil mixture being centrifuged by said vortex generating means to separate the oil and air from the air/oil mixture, an inlet formed in said wall means for admitting the air/oil mixture into said enclosed chamber wherein the oil is directed toward the wall means of said enclosed chamber, an air removal tube extending through said wall means into said enclosed chamber for removing the air, wake separator means disposed in said inlet for creating a wake and removing a portion of the air from said air/oil mixture prior to said air/oil mixture entering said enclosed chamber, and connecting means interconnecting said wake separator means and said air removal tube.

5,587,069


WATER DECONTAMINATION APPARATUS USING PEROXIDE PHOTOLYSIS IONIZER

Wayne F. Downey, Jr., 437 Franklin Ct., Collegeville, Pa. 19426
Continuation-in-part of Ser. No. 111,988, Aug. 25, 1993, Pat. No. 5,439,595. This application Jun. 7, 1995, Ser. No. 480,852

Int. Cl.⁶ C02F 1/32

U.S. Cl. 210—192

18 Claims



1. For use in the treatment of water, apparatus comprising a first chamber, a water inlet port in fluid communication with said first chamber, a second chamber in fluid communication with said first

chamber and having an outlet port, first orifice means in fluid communication with said second chamber for introducing oxidizing reagent into said second chamber, an ultraviolet radiation source operatively coupled to said first and second chambers, said ultraviolet radiation source being disposed to simultaneously irradiate water in said first chamber and water and reagent in said second chamber, and second orifice means for conducting and directing water from said first to said second chamber, said second orifice means directing the water toward a mixing zone, wherein the water and the reagent are mixed in said second chamber and irradiated by ultraviolet radiation from said radiation source.

5,587,070

SYSTEM FOR PROCESSING BIOLOGICAL FLUID


David B. Pall, Roslyn Estates; Thomas C. Gsell; Vlado I. Matkovich, both of Glen Cove, and Thomas Bormann, Seaford, all of N.Y., assignors to Pall Corporation, East Hills, N.Y.

Continuation of Ser. No. 788,787, Nov. 6, 1991, abandoned, which is a continuation-in-part of Ser. No. 609,654, Nov. 6, 1990, Pat. No. 5,100,564. This application Jun. 4, 1993, Ser. No. 71,495

Int. Cl.⁶ B01D 36/00; 36/02

U.S. Cl. 210—202

32 Claims



26. A biological fluid processing system comprising:
a first container;
a first porous medium communicating with the first container, said first porous medium comprising a leukocyte depletion medium; and
a separation device downstream of, and communicating with, the first porous medium, said device comprising a housing and including a separation medium;

said housing having an inlet, a first outlet, and a second outlet; said separation medium having a first surface and a second surface, and comprising at least one porous membrane, said separation medium being suitable for passing a biological fluid including plasma and at least one other component of the biological fluid along the first surface of the separation medium and for passing plasma through the separation medium;

said separation medium positioned inside the housing to provide a first fluid flow path for the biological fluid from the inlet along the first surface of the separation medium to the first outlet, wherein said first fluid flow path includes at least one fluid flow channel which comprises a serpentine flow channel; and a second fluid flow path for passing plasma through the first and second surfaces of the separation medium to the second outlet.

5,587,071

REPLACEABLE ELEMENT FLUID FILTER

Donald E. Belden, Sand Springs, Okla., assignor to Facet International, Inc., Tulsa, Okla.


Division of Ser. No. 58,768, Apr. 13, 1993, Pat. No. 5,423,984. This application Jun. 9, 1995, Ser. No. 488,877

Int. Cl.⁶ B01D 29/21; 27/06; 27/06; 35/30

U.S. Cl. 210—232

4 Claims

1. A replaceable element fluid filter comprising:



an elongated rigid apertured center tube comprised of a plurality of tubular sections joined concentrically end-to-end with the joined sections allowing flow communication between adjacent joined tube sections, the center tube having a top and a bottom end;

an elongated rod extending coaxially through said center tube, a bottom end of the rod being secured to a filter attachment means, said filter attachment means having a fluid passageway therethrough, the rod having a top end portion;

a top flange member having a central opening therethrough and a periphery in engagement with and closing said center tube top end, the top flange member central opening receiving said rod therethrough;

a means received on said rod top end portion to secure said top flange member against said center tube and to thereby hold said center tube in communication with said filter attachment means;

a tubular filter element having top and bottom end portions replaceably receivable on said center tube; means to sealably close said filter element top and bottom end portions and for providing closed communication between said tubular filter element and said filter attachment means fluid passageway;

a yoke member received on the top end portion of said rod and having an outer peripheral area sealably engaging said means to sealably close said filter element top end portion; and means received on said rod adjacent to said top end thereof to retain said yoke whereby said yoke member may be removed to replace said filter element without disturbing said center tube, whereby by varying the number of said plurality of apertured center tube tubular sections and the length of said rod, said tubular filter elements of different length may be employed.

5,587,072

STORM SEWER OUTLET FILTER

Francis A. Regan, 211 Ardmore Ave., Ardmore, Pa. 19003


Filed Oct. 10, 1995, Ser. No. 541,619

Int. Cl.⁶ B01D 35/02

U.S. Cl. 210—232

11 Claims

1. A filter device to be connected to the outlet of a storm sewer to receive the flow of water and debris carried by the water which exits from the outlet, the filter functioning for allowing the water to pass therethru while retaining debris carried by the water, the filter device comprising:



first filter means including an elongated, hollow member made of netting and having a water/debris entrance end and also having a water/debris exit end, the netting being open to pass water therethrough;

first connector means mounted on said netting and extending around said entrance end;

mechanism mounted on said first connector means for use in connecting the entrance end to a storm sewer outlet;

second connector means mounted on said netting and extending around said exit end;

mechanism mounted on said second connector means for use in connecting the exit end to an adjacent filter means;

second filter means including an elongated, hollow member made of netting and having a water/debris entrance end, the netting being open to pass water therethrough and also having an opposite closed end;

third connector means mounted on said netting of said second filter means and extending around the entrance end of said second filter means;

mechanism mounted on said third connector means for use in connecting last said entrance end to the exit end of said first filter means; and

a plurality of releasable, reusable fastener means respectively engaging said mechanism or said exit end of said first filter means; and said mechanism on said entrance end of said second filter means and releasably securing the first and second filter means together with the ends of said second and third connector means adjacent to and facing one another and constituting a joint.

5,587,073

END SUPPORTED DOUBLE DRUM WASTE WATER SCREEN


David R. Zittel, 155 Oak Grove Dr., Columbus, Wis. 53925

Continuation of Ser. No. 121,730, Sep. 15, 1993, Pat. No. 5,433,849. This application Jun. 7, 1995, Ser. No. 477,085

Int. Cl.⁶ B01D 33/067; 33/11; 33/42; 33/72

U.S. Cl. 210—372

11 Claims



1. An apparatus for filtering particulate matter from water, the apparatus comprising:

a) a frame;

b) an outer drum rotatably mounted to the frame, the outer drum having portions defining a drum head and a generally cylindrical perforated screen extending from the drum head which


- allows the passage of water therethrough but which retains particulate matter above a first size;
- c) an inner drum mounted in cantilever supported engagement to the drum head inside of the outer drum and thus mounted to co-rotate with the outer drum, the inner drum having portions defining a generally cylindrical perforated screen which allows the passage of water therethrough but which retains particulate matter above a second size, wherein the second size is greater than the first size;
- d) means mounted on the interior of the outer drum for advancing particulate matter retained by the outer drum screen to a discharge opening of the outer drum;
- e) means mounted on the interior of the inner drum for advancing particulate matter retained by the inner drum screen to an inner drum discharge opening; and
- f) a conduit which discharges waste water containing particulate matter into the interior of the inner drum, whereby the water passes through the perforated screen of the inner drum and through the perforated screen of the outer drum, to yield a treated water flow which has reduced levels of particulate matter.

5,587,074

FLUID FILTER WITH ENHANCED BACKFLUSH FLOW
Gerard J. Lynch, Bridgewater, and Joseph Quinn, Kearny, both of N.J., assignors to H-Tech, Inc., Del.
Filed Feb. 17, 1995, Ser. No. 390,134
Int. Cl.⁶ B01D 29/68

U.S. Cl. 210—411

7 Claims



1. A backflush conduit for an automatic backflushing filter, comprising:

- a) a flared inlet portion converging inwardly from an inlet aperture in the direction of backflushing flow;
- b) an outlet portion having a generally cylindrical shape and oriented at an angle with respect to said inlet portion; and
- c) a transition portion connecting said inlet portion and said outlet portion, said transition portion turning through said angle while converging to said outlet portion, said inlet portion having an interior with upper and lower walls, said upper and lower walls being symmetrical and convex relative to each other and converging in the direction of backflushing flow through said conduit toward said transition portion, said conduit having a streamlined interior contour to enhance fluid flow therethrough and supporting a substantially even rate of fluid flow across said inlet aperture.

5,587,075
PRESSURE FILTER


Uwe Maurer, Schwelm, Germany, assignor to Mike Maurer, Schwelm, Germany
PCT No. PCT/DE94/00795, § 371 Date Apr. 13, 1995, § 102(e)
Date Apr. 13, 1995, PCT Pub. No. WO95/00229, PCT Pub. Date Jan. 5, 1995

PCT Filed Jun. 21, 1994, Ser. No. 392,770
Claims priority, application Germany, Jun. 24, 1993, 43 20 951.3

Int. Cl.⁶ B01D 29/68

U.S. Cl. 210—411

7 Claims



1. A pressure filter comprising a fluid compartment with a fluid inlet, at least one filter surface in the fluid compartment having a plurality of apertures, one side of the filter surface being restricted by the fluid compartment and the other side thereof being restricted by a filtrate compartment having a filtrate outlet, and a backwashing means with a backwashing head sweeping over the filter surface and sealing a part of the filter surface with respect to the fluid compartment, the backwashing head restricting a backwashing compartment having at least one suction chamber open in a slot-like manner to the filter surface and having connected thereto a reject drain, wherein the slot-like aperture of the suction chamber is formed as a semi-arc of a helix of about 190° and in such a manner that each aperture of the filter surface, independent of its radial position, is swept over by the slot-like aperture in approximately the same space of time.

5,587,076

FILTER NOZZLE FOR INJECTION MOLDING MACHINES PROCESSING THERMOPLASTICS
Kurt Herzog, Wattwil, Switzerland, assignor to Herzog AG, Wolfertswil, Switzerland
Filed May 19, 1995, Ser. No. 446,011


Claims priority, application Switzerland, May 25, 1994, 1613/94

Int. Cl.⁶ B01D 35/02

U.S. Cl. 210—461

13 Claims

1. A filter nozzle for thermoplastic injection molding machines, the nozzle comprising:
- a) a nozzle body defining an inlet opening, an outlet opening and a passage between said inlet opening and said outlet opening, said nozzle body also defining a flushing opening communicating with said passage;
- b) a filter positioned in said passage in an area adjacent said flushing opening, said filter including partition means for blocking contaminants from flowing through said filter, said filter and said nozzle body providing a path from an upstream side of said partition means to said flushing opening, said path not passing through said partition means;



means for opening and closing said flushing opening to remove contaminants from upstream of said filter.

5,587,077

SCREEN CYLINDER OR PLATE HAVING A GROOVED FIRST FACE AND A STEPLESS SECOND FACE

Frank Aaltonen, Lisse, Netherlands, and Timo Alajaa, Kotka, Finland, assignors to CAE Investments B.V., Eygelshoven, Netherlands
PCT No. PCT/FI92/00263, § 371 Date Jul. 18, 1994, § 102(e)
Date Jul. 18, 1994, PCT Pub. No. WO93/07384, PCT Pub. Date Apr. 15, 1993


PCT Filed Sep. 30, 1992, Ser. No. 211,403

Claims priority, application Finland, Oct. 4, 1991, 914703

Int. Cl.⁶ B01D 39/10

U.S. Cl. 210—498

30 Claims



1. A method of producing a screen cylinder or plate from a piece of material having first and second opposed substantially parallel faces, comprising the steps of:

- (a) forming a plurality of grooves associated with the first face, each groove having a lowermost portion closest to the second face; and
- (b) from the second face, in a single working phase, forming stepless, continuous surface through-extending apertures in the material, the apertures cooperating with the grooves.

5,587,078


CENTRIFUGAL CLEANER
Peter LeBlanc, Queensbury, N.Y., assignor to Ahlstrom Machinery Corporation, Noormarkku, Finland
Filed Apr. 1, 1994, Ser. No. 221,004

PCT Filed Apr. 1, 1994, Ser. No. 221,004

Int. Cl.⁶ B01D 21/26

U.S. Cl. 210—512.1

26 Claims



1. A centrifugal cleaner for fiber suspensions having fiber flocs therein, comprising:

- a generally hollow main body having a top and a bottom and a side wall having at least a portion thereof with a generally decreasing conical taper from the top toward the bottom thereof, and having a tangential inlet in said side wall near said body top for introducing fiber suspension to be cleaned;
- a vortex finder located in said body top;
- a bottom outlet nozzle located at said bottom of said main body, substantially concentric with said vortex finder; and
- a turbulence generator disposed in said tangential inlet for generating sufficient turbulence so as to break up fiber flocs in introduced suspension and prevent reformation of the flocs before the suspension enters said hollow main body, so as to enhance cleaning efficiency of the cleaner, increase the consistency of fiber suspension which the cleaner can effectively handle, and/or minimize the sensitivity of the cleaner cleaning efficiency to consistency changes in the fiber suspension compared to the same cleaner but not including said turbulence generator.

5,587,079

PROCESS FOR TREATING SOLUTIONS CONTAINING SULFATE AND METAL IONS


Michael V. Rowley; Douglas D. Warkentin, both of 930 West 49th Avenue, Vancouver, B.C., V5Z 2S9, Canada, and Beverly M. Piroshko, 3913 West 24th Avenue, Vancouver, B.C., V6S 1M1, Canada

Filed Apr. 21, 1995, Ser. No. 426,802

Int. Cl.⁶ C02F 3/30

U.S. Cl. 210—603

29 Claims



1. A process for treating a solution containing sulfate ions and metal ions, comprising the steps of:

- (a) adding hydrogen sulfide to the solution;
- (b) precipitating a sulfide of the metal ions from the solution;
- (c) feeding a portion of the solution to an anaerobic microbiological culture that utilizes the sulfate ions and produces hydrogen sulfide;
- (d) feeding the anaerobic microbiological culture gaseous nutrients comprising hydrogen and a carbon oxide, the gaseous nutrients being produced by a partial oxidation burner;
- (e) stripping hydrogen sulfide produced by the microbiological culture from the solution; and
- (f) recirculating a portion of the hydrogen sulfide stripped from the solution in step (e) to be used in step (a).

5,587,080


FERMENTATION PROCESS
Robert Landine; Claude De Garie, and Albert Cocci, all of Fredericton, Canada, assignors to ADI, Limited, Canada
Division of Ser. No. 94,118, Sep. 22, 1993, Pat. No. 5,505,848.
This application Dec. 11, 1995, Ser. No. 570,690

Int. Cl.⁶ C02F 3/28

U.S. Cl. 210—603

8 Claims

1. A method of treating a liquid effluent by fermentation, comprising: positioning a gas collection conduit around at least part of the periphery of an effluent container; positioning a gas-impermeable cover of said effluent container; pumping effluent into said container for fermentation therein; collecting gas emanating



from said effluent into said gas collection conduit; extracting said gas from said conduit; and removing clarified liquor from said container.

5,587,081

THERMOPHILIC AEROBIC WASTE TREATMENT PROCESS


Kenneth L. Norcross, and Yanlong J. I., both of Edwardsville, Kans., assignors to Jet-Tech, Inc., Edwardsville, Kans.

Filed Apr. 26, 1994, Ser. No. 233,276

Int. Cl.⁶ C02F 11/06

U.S. Cl. 210—604

13 Claims



1. A method of destroying pathogenic organisms in a material by exposing the organisms to an aerobic and thermophilic environment, comprising the steps of:

- placing the material in a reactor;
- flowing oxygen-containing gas upward through the material; and
- providing a blower mechanism for recycling at least a portion of the gas that has previously flowed through the material back through the material as recycle.

5,587,082

HIGH OSMOTIC PRESSURE CHROMATOGRAPHY

Iwao Terakawa, 73 Balavia Pl., Harrison, N.Y. 10528, and Min Luo, 229 W. 62nd St., New York, N.Y. 10023

Filed Jun. 7, 1995, Ser. No. 480,238


Int. Cl.⁶ B01D 15/08

U.S. Cl. 210—635

21 Claims

1. A method for fractionating polymers based on molecular size comprising the steps of:

- providing a solution of polymer dissolved in a first solvent, said polymer having an initial polydispersity index greater than 1.000 and including higher and lower molecular weight polymer components, said polymer being dissolved in said first solvent at a concentration about equal to or greater than an overlap concentration, c^* , of said polymer but less than a concentration at which said solution is no longer fluid;
- passing said solution as a mobile phase through a chromatographic matrix to generate an eluent, said matrix including a



porous material imbibed with a second solvent, said second solvent imbibed in said porous material acting as a stationary phase in communication with said mobile phase, said porous material having pore openings of a dimension on the order of a molecular size of said polymer that allows said lower and higher molecular weight polymer components to migrate selectively between said mobile phase and said stationary phase to effect size-based partitioning of said polymer, whereby said migration is enhanced by a relatively high osmotic pressure generated because said concentration is about equal to or greater than said overlap concentration, c^* , and

(C) eluting said polymer from said porous material.

5,587,083

NANOFILTRATION OF CONCENTRATED AQUEOUS SALT SOLUTIONS


Zhigiew Twardowski, Burnaby, Canada, assignor to Chemetec International Company Ltd., Vancouver, Canada

Filed Apr. 17, 1995, Ser. No. 422,935

Int. Cl.⁶ B01D 61/00

U.S. Cl. 210—652

12 Claims



1. In a nanofiltration process for filtering an aqueous liquor comprising feeding a feed liquor to a nanofiltration membrane module under a positive applied pressure to provide a pass liquor and a permeate liquor and selectively decreasing the concentration of a first compound relative to the concentration of a second compound in said aqueous liquor wherein said first compound has a first feed concentration and said second compound has a second feed concentration, said process comprising feeding said aqueous liquor to said nanofiltration membrane module, collecting said pass liquor wherein said first compound is at a first pass concentration lower than said first feed concentration, and said second compound is at a second pass concentration higher than said second feed concentration, and collecting said permeate liquor wherein said first compound has a first permeate concentration and said second compound is at a second permeate concentration, the improvement wherein said first feed compound has a first feed concentration greater than 50 g/l, wherein said first feed compound contains monovalent ions, and said second feed compound contains poly-valent ions.

5,587,084

METHOD OF REMOVING ORGANIC CONTAMINANTS FROM AIR AND WATER WITH ORGANOPHILIC, QUATERNARY PHOSPHONIUM ION-EXCHANGED SMECTITE CLAYS


Stephen A. Boyd, and Ravi Kukkadapu, both of East Lansing, Mich., assignors to Board of Trustees operating Michigan State University, East Lansing, Mich.

Filed Feb. 7, 1995, Ser. No. 384,967


Int. Cl.⁶ C02F 1/28; 1/42

U.S. Cl. 210—691

9 Claims



1. A method of adsorbing an organic compound from air or water comprising contacting the organic compound in the air or water with a quaternary phosphonium ion-exchanged colloidal clay including a quaternary phosphonium ion-exchanged cation of the formula:



wherein X^- is selected from the group consisting of Cl^- , Br^- and I^- ; wherein R_1 , R_2 , R_3 and R_4 are organic moieties selected from the group consisting of short chain alkyl moieties (C_1-C_4); long chain alkyl moieties (C_4-C_{20}); substituted alkyl moieties having 1 to about 20 carbon atoms; substituted or unsubstituted cyclo-alkyl moieties; substituted or unsubstituted aryl moieties; substituted or unsubstituted alkaryl moieties; alkenes; alkynes; aldehydes; ketones; alcohols; carboxylic acids; esters; ethers; cyclic ethers; and combinations thereof.

5,587,085

METHOD FOR DEWATERING PARTICLES


Roe-Hoan Yoon, and Gerald H. Luttrell, both of Blacksburg, Va., assignors to Virginia Tech Intellectual Property Inc., Blacksburg, Va.

Continuation-in-part of Ser. No. 229,012, Apr. 18, 1994, Pat. No. 5,458,786. This application Jun. 7, 1995, Ser. No. 476,513

Int. Cl.⁶ C02F 1/54

U.S. Cl. 210—711

5 Claims



1. A method for dewatering hydrophobic particles, comprising the steps of:

adding to a mixture comprised of water and hydrophobic particles, a quantity of at least one hydrophobic compound which is in a gaseous state under atmospheric pressure and in liquid state at higher pressures, said hydrophobic compound being under pressure and in said liquid state during said adding step, said quantity of said hydrophobic compound being sufficient to displace water from surfaces of said hydrophobic particles; spontaneously displacing water from said surfaces of said hydrophobic particles while said hydrophobic compound is in its liquid state;

separating said hydrophobic compound and said hydrophobic particles from said water by the substeps of: floating said hydrophobic compound and said hydrophobic particles on top of said water, and recovering a binary composition of said hydrophobic compound and said hydrophobic particles from said mixture; reducing said pressure of said binary composition to cause said hydrophobic compound to change to said gaseous state and separate from said hydrophobic particles; collecting dried hydrophobic particles after said step of reducing pressure; and recycling said hydrophobic compound for use in said adding a step.

5,587,086

PURIFICATION OF AQUEOUS MEDIA USING ALUMINUM POLYCHLORIDE/IRON COMPOUND/SALT-BASED COAGULANT COMPOSITIONS

Sylvain Danda, Marly la Ville; Magnus Kvant, Niederroedern, and Yvette Pescher, Bagneux, all of France, assignors to Kemrhone France, Courbevoie Cedex, France

Division of Ser. No. 248,178, May 24, 1994. This application Jun. 2, 1995, Ser. No. 458,698

Claims priority, application France, May 24, 1999, 93 06159 Int. Cl.⁶ C02F 1/52; 1/56

U.S. Cl. 210—723

11 Claims

1. In a process of the treatment/purification of an impure aqueous medium by contacting same with a coagulating agent and thence permitting particulate impurities therein to settle, the improvement which comprises using, as the coagulant therefor, a coagulant composition, comprising (i) at least one basic aluminum polychloride or polychlorosulfate, (ii) at least one iron (II) and/or iron (III) compound, and (iii) at least one alkali metal and/or alkaline earth metal halide wherein said at least one basic aluminum polychloride or polychlorosulfate has the general formula:



in which n , m and k are positive numbers; $3n-m-k$ is positive; z is a positive integer at least equal to 1; and k is a number ranging from 0 to $0.4n$, and wherein said basic aluminum polychloride or polychlorosulfate has a $(m/3n) \times 100$ ratio of from 10% to 80%.

5,587,087

METHOD AND APPARATUS FOR TREATING LIQUIDS

Alban Timmons, 7 Cartwright La. Beverly, North Humber-side, Great Britain

PCT No. PCT/GB94/01771, § 371 Date May 30, 1995, § 102(e) Date May 30, 1995, PCT Pub. No. WO95/05345, PCT Pub. Date Feb. 23, 1995

PCT Filed Aug. 12, 1994, Ser. No. 416,852


Claims priority, application United Kingdom, Aug. 16, 1993, 9317026

Int. Cl.⁶ C02F 1/66

U.S. Cl. 210—724

31 Claims

1. A method for treating a contaminated liquid in a first vessel comprising a light contaminants outlet through which light contaminants can be extracted in upper regions of the vessel and a heavy contaminants outlet through which heavy contaminants can be extracted in lower regions of the vessel and a mid-height outlet



in a mid-height region of the vessel, said mid-height outlet comprising a vertical duct open at both ends and having its axis concentric with the axis of the vessel comprising the steps of adding to the contaminated liquid a first treatment material selected from the group consisting of soluble magnesium salts, ferrous salts, manganous compounds, cuprous compounds, and nickel II, intimately mixing the first treatment material into the contaminated liquid and then raising the pH of the contaminated liquid to a value in excess of 8, and separating clarified liquid from the contaminant.

5,587,088

PRECIPITATION AND SEPARATION OF INORGANIC SPECIES FROM AQUEOUS SOLUTIONS


Mansour S. Bader, P.O. Box 1901, Stillwater, Okla. 74074

Filed Aug. 1, 1995, Ser. No. 509,781

Int. Cl.⁶ C02F 1/58; 1/62

U.S. Cl. 210—729

18 Claims



Precipitation of Calcium Chloride by Isopropylamine

1. A method of removing salt from an aqueous solution comprising said salt and water, said method comprising the step of adding an effective amount of isopropylamine to said solution to cause at least a portion of said salt to form a solid precipitate, wherein said salt is selected from the group consisting of: chlorides of calcium, barium, strontium, and radium; bicarbonates of sodium, potassium, magnesium, calcium, barium, strontium, and radium; silicates of sodium, potassium, magnesium, and radium; selenites, selenates and selenides of sodium, potassium, magnesium, calcium, barium, strontium, and radium; phosphorous selenide salts selected from phosphorous sub-selenide, phosphorous penta-selenide, phosphorous tri-selenide, and phosphorous mono-selenide; selenium halide salts selected from selenium mono-chloride, selenium tetra-chloride, selenium mono-bromide, and selenium tetra-bromide; bromides, nitrates, nitrites, and phosphates of sodium, potassium, magnesium, calcium, barium, strontium, and radium; and combinations thereof.

5,587,089

WATER PURIFICATION AND DISPENSING SYSTEM


Gerald A. Vogel, Willmar, and Joseph H. Tholen, Waconia, both of Minn., assignors to J. Vogel Premium Water, St. Cloud, Minn.

Filed Jul. 8, 1994, Ser. No. 272,784

Int. Cl.⁶ B01D 17/12

U.S. Cl. 210—164

23 Claims



8. A process for purifying and dispensing water comprising the steps of:
 - a) obtaining unpurified water from a supply source and purifying the unpurified water in an apparatus including a water purification system;
 - b) placing a container in the apparatus in an upright position in a container rotating means;
 - c) rotating the container to an inverted position;
 - d) directing the purified water from the water purification system into the container when the container is in the inverted position;
 - e) rotating the container to an upright position; and
 - f) directing the purified water from the water purification system into the container for filling the container in the upright position.
11. The process of claim 8 additionally comprising, ozonating the purified water in the apparatus.

5,587,090

MULTIPLE LEVEL MASK FOR PATTERNING OF CERAMIC MATERIALS


James F. Belcher, Plano; Steven N. Frank, McKinney; John P. Long, Garland, and Jeanette Jones, Plano, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Apr. 4, 1994, Ser. No. 222,146

Int. Cl.⁶ B44C 1/22; C03C 15/00

U.S. Cl. 216—17

12 Claims



1. A method of forming a microelectronic structure, said method comprising steps:
 - (a) providing a ceramic substrate;
 - (b) chemical vapor depositing a parylene mask layer on said ceramic substrate;
 - (c) forming a dry-etch-selective mask layer on said parylene mask layer, said dry-etch-selective mask layer comprising a different material than said parylene mask layer;
 - (d) forming a top photosensitive layer on said dry-etch-selective mask layer, said top photosensitive layer comprising a different material than said dry-etch-selective mask layer;
 - (e) forming a pattern in said top photosensitive layer using photolithography;
 - (f) forming said pattern in said dry-etch-selective mask layer using said top photosensitive layer as a first etch mask;

- (g) forming said pattern in said parylene mask layer using said dry-etch-selective mask layer as a second etch mask, said parylene mask layer having vertical walls; and
- (h) ion milling said pattern in said ceramic substrate using said parylene mask layer as a third etch mask, whereby the vertical walls of the parylene mask layer allow vertical walls and/or deep trenches to be formed in the ceramic substrate.

5,587,091

METHOD AND APPARATUS FOR CONTROLLING RESISTANCE WELDING

Tadashi Kawagoe, Hekinan, and Keizo Zyouko, Okazaki, both of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan


Filed Apr. 20, 1995, Ser. No. 426,979

Claims priority, application Japan, Apr. 20, 1994, 6-081651

Int. Cl.⁶ B23K 11/24

U.S. Cl. 219—110

6 Claims



1. A control apparatus for resistance welding, comprising:
 - time measuring means for measuring an energization time of a welding current, the energization time being required by a given electrode displacement during welding between an electrical conductive weld member and a member to be welded which are arranged between two electrodes;
 - time difference calculating means for calculating a time difference between the energization time measured by the time measuring means and a preset target energization time; and
 - feedback control means for correctively increasing and decreasing a welding current, which occurs at a next weld timing, on the basis of the time difference calculated by the time difference calculating means.

5,587,092

METHOD OF WELDING VANES INTO A SHELL FOR A TORQUE CONVERTER

Chris Sullivan, Warren; Jim Wells, Sterling Heights, and Michael Prevost, Ypsilanti, all of Mich., assignors to Borg-Warner Automotive, Inc., Sterling Heights, Mich.


Filed May 2, 1995, Ser. No. 433,947

Int. Cl.⁶ B23K 11/26

U.S. Cl. 219—113

10 Claims

1. A method for assembly of a vane into a turbine or impeller for a torque converter, substantially without vane deformation due to heat, comprising:
 - providing a shell, for an impeller or a turbine, and a vane for insertion into said shell in a predetermined orientation; and
 - using a high energy pulse from a capacitance discharge welding apparatus for welding of the vane into said shell, without heat deformation of the vane.



5,587,093

SAFE POTENTIAL ARC CHANNEL ENHANCED ARC HEAD


Graeme Aston, Monument, Colo., assignor to Electric Propulsion Laboratory, Inc., Monument, Colo.

Filed Jun. 2, 1995, Ser. No. 459,332

Int. Cl.⁶ B23K 10/00

U.S. Cl. 219—121.48

23 Claims



1. A safe potential arc channel enhanced arc head comprising:
 - means for introducing a gas flow ionizable to produce a plasma, the gas flowing from a location generally at an upstream end of the arc head into an electrically conducting gas inlet and input current tube coaxially assembled to a generally tubular, electrically conducting insert heater orifice plate;
 - means for aligning the gas inlet and input current tube and the insert heater orifice plate to share a common axis aligned with the direction of gas flow, the insert heater orifice plate having an orifice therein through which the gas flow exits the arc head;
 - means for forming a joint at a downstream end of the insert heater orifice plate and a downstream end of an electrically conducting body and return current tube;
 - a tube coupler electrical insulator generally tubular in shape and means for attaching an upstream end of the body and return current tube to the downstream end of the tube coupler electrical insulator and for attaching an upstream end of the tube coupler electrical insulator to an upstream end of the gas inlet and input current tube;
 - means for aligning the tube coupler electrical insulator and the body and return current tube to share a common axis, the common axis being coaxial with the common axis of the gas inlet and input current tube and the insert heater orifice plate which are contained wholly within, and electrically isolated from, an inside diameter of the tube coupler electrical insulator and the body and return current tube except at the joint between the insert heater orifice plate and the body and return current tube;
 - means for establishing a potential difference between an upstream end of the gas inlet and input current tube and an upstream end of the body and return current tube to produce a heater current flow in a path from the upstream end of the gas

inlet and input current tube, through the insert heater orifice plate, and through the body and return current tube to the upstream end of the body and return current tube;
resistance means for making an Ohmic resistance integral to the insert heater orifice plate at least three times higher than an Ohmic resistance of the current path through the gas inlet and input current tube and the body and return current tube; said resistance means comprising one or more helices, each with a multiplicity of turns, generally located between an interface between the gas inlet and input current tube and an upstream end of the insert heater orifice plate, the insert heater orifice plate comprising porous tungsten, having a density within the range 70%-90%, and the one or more helices being impregnated with a low electronic work function emissive mix material;

first power supply means for providing variable control of a heater current to enable heating the one or more helices to a temperature of at least 1100 degrees C. for normal arc head operation and to a higher temperature for rapid arc head start-up and self-cleaning;

thermal insulation positioned outside of the body and return current tube from a location at a downstream end of the insert heater orifice plate to a location generally at the upstream end of the insert heater orifice plate.

5,587,094

LASER MARKING APPARATUS


Koji Yoshida, Hiratsuka, Japan; Taku Yamazaki, Pittsburgh, Pa., and Akira Mori, Chigasaki, Japan, assignors to Kabushiki Kaisha Komatsu Seisakusho, Tokyo, Japan
PCT No. PCT/JP93/01717, § 371 Date May 23, 1995, § 102(e) Date May 23, 1995, PCT Pub. No. WO94/12309, PCT Pub. Date Jun. 9, 1994

PCT Filed Nov. 24, 1993, Ser. No. 433,416

Claims priority, application Japan, Nov. 25, 1992, 4-086578

U.S. Cl. 219—121.68 Int. Cl. B23K 26/06

25 Claims



1. In a laser marking apparatus for passing a laser beam along a beam path from a laser beam source through a raster-scanning system onto a marking surface, said raster-scanning system comprising:

an X-direction polarizing mirror,
a Y-direction polarizing mirror,
a field lens, and
a mask,

wherein said X-direction polarizing mirror, said Y-direction polarizing mirror, said field lens, and said mask are arranged along said beam path so that said laser beam is reflected by each of said X-direction polarizing mirror and said Y-direction polarizing mirror and passes through each of said field lens and said mask,

wherein one of said X-direction polarizing mirror and said Y-direction polarizing mirror is upstream of the other one of said X-direction polarizing mirror and said Y-direction polarizing mirror, with respect to passage of said laser beam along said beam path;

the improvement comprising:

a double polarizing element for branching said laser beam from said laser beam source into two branch beams, said double polarizing element comprising two polarizing prisms arranged in series, with respect to passage of said laser beam along said beam path, at a position in said beam path between said laser beam source and the upstream one of said X-direction polarizing mirror and said Y-direction polarizing mirror, said two polarizing prisms being spaced apart from each other so that there is a distance between the two polarizing prisms along said beam path; and

an adjusting means for varying said distance between the two polarizing prisms.

5,587,095

PROCESS AND APPARATUS FOR CONTAMINATION-FREE PROCESSING OF SEMICONDUCTOR PARTS


Nunzio DiPaolo, Poughkeepsie, and Daniel J. Ferguson, Marlboro, both of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Continuation of Ser. No. 227,937, Apr. 15, 1994, Pat. No. 5,471,033. This application Aug. 22, 1995, Ser. No. 518,054

Int. Cl. F27B 9/06

U.S. Cl. 219—388

12 Claims



1. A process for treating a part in a second environment wherein said part is protected from said second environment, comprising the steps of:

- placing said part on a part carrier in a first environment,
- placing a cover over said part carrier such that said cover entraps material from said first environment while enveloping said part to form a covered boat,
- removing said boat from said first environment, and
- placing said boat in said second environment for treating said part wherein said second environment has more contamination than said first environment.

5,587,096

DE-LABELLING FOR REMOVING APPARATUS LABELS ADHERED TO A DISKETTE UTILIZING OPPOSED HEATERS

Gary S. Huvard, 7819 Tochester Dr., Chesterfield, Va. 23832, and Alfred D. Lobo, 2655 Euclid Heights Blvd., Cleveland Heights, Ohio 44106

Division of Ser. No. 39,895, Mar. 30, 1993, Pat. No. 5,378,300. This application Dec. 21, 1994, Ser. No. 361,060


Int. Cl. B32B 35/00; H05B 1/00

U.S. Cl. 219—521

10 Claims

1. A device for heating a label of laminar imprintable material, prior to removal thereof from a surface of a standard diskette to which said label is non-removably adhered with a thin layer of adhesive, said diskette having front and rear generally laminar sidewalls which define a casing, in which is non-removably captured a storage disk protected by opposed planar foam pads within said casing; a front label portion extending over at least about 60% of said front sidewall; a rear label portion extending over about 15% of said rear sidewall; said label being adhesively secured to at least said front label portion, said device comprising:

- support means to receive and support a diskette in a desired position;



(b) opposed first and second heating means mounted in desired spaced-apart relationship with each other and a diskette therebetween supported in a vertical plane delimited by a pair of opposed biasing means adapted to maintain surfaces of the diskette which are not heated, open to the atmosphere, at least said first heating means providing direct heat energy in a heating zone over said front label portion, said first and second heating means are adapted to direct heat energy over substantially only an area coextensive with the front and rear label portions, respectively, together providing sufficient heat energy to heat said adhesive to a temperature within a range in which said adhesive undergoes thermal viscous deformation; and

(c) control means including (i) a timer element to provide a predetermined duration of current of requisite amperage and continuous voltage to at least said first heating means, (ii) a starting switch means, and (iii) a signal means recognizable by human senses, said control means being connected to at least said first heating means.

5,587,097

FIXING HEATER AND METHOD OF MANUFACTURING FIXING HEATER

Shigehiro Sato, Yokohama; Yoshiyuki Matsunaga, Yokosuka; Tsuyoshi Ono, Tokyo, and Takaaki Karube, Yokohama, all of Japan, assignors to Toshiba Lighting & Technology Corporation, Tokyo, Japan

Continuation of Ser. No. 987,600, Dec. 9, 1992, abandoned.


This application Jul. 13, 1994, Ser. No. 274,367

Claims priority, application Japan, Dec. 9, 1991, 3-324791; Feb. 27, 1992, 4-041327; Mar. 31, 1992, 4-108733

Int. Cl. H05B 3/16

U.S. Cl. 219—543

8 Claims



1. A fixing heater comprising:

a substrate having an electrically insulative property; an electrical resistance member including a heat generating portion formed on the substrate and extending in a longitudinal direction thereof, said heat generating portion having a pair of edge portions one of which is trimmed along the longitudinal direction;

electrode forming portions formed at both longitudinal end portions of the electrical resistance member; and

at least two glass layers formed on a surface of the heat generating portion of the electrical resistance member, said at least two glass layers including a lowermost glass layer and an

uppermost glass layer, said lowermost glass layer contacting the surface of the heat generating portion and having an electrical insulation effect higher than that of the uppermost glass layer, said lowermost glass layer also having a surface smoothness lower than that of the uppermost glass layer.

5,587,098

JOINING LARGE STRUCTURES USING LOCALIZED INDUCTION HEATING


Marc R. Matsen, Seattle; Richard J. Poel, Kent; Wesley B. Crow, and David S. Nansen, both of Bellevue, all of Wash., assignors to The Boeing Company, Seattle, Wash.

Continuation-in-part of Ser. No. 169,655, Dec. 16, 1993, Ser. No. 92,050, Jul. 15, 1993, Pat. No. 5,410,133, and Ser. No. 151,433, Nov. 12, 1993, Pat. No. 5,420,400, said Ser. No. 169,655 is a continuation-in-part of Ser. No. 777,739, Oct. 15, 1991, Pat. No. 5,410,132, said Ser. No. 92,050 is a division of Ser. No. 681,004, Apr. 5, 1991, Pat. No. 5,229,562. This application Jun. 7, 1995, Ser. No. 481,094

Int. Cl. B23K 13/01

U.S. Cl. 219—615

20 Claims



1. A method for joining large metal aerospace structure made by joining two workpieces using localized induction heating provided by an induction coil to heat the structure along a bondline to a joining temperature to reduce processing time and energy consumption, comprising the steps of:

- assembling at least two workpieces to define an assembly having a joint interface at the bondline to form the structure;
- placing the assembly in an induction heating press with the bondline adjacent a surrounding ribbon coil susceptor susceptible for induction heating and incorporated into a wall of a die adjacent the joint interface;
- energizing the induction coil to heat the susceptor and thereby to heat the workpieces locally at the joint interface;
- applying pressure by pushing the workpieces together laterally when the bondline reaches the joining temperature to produce a jointed part having a geometry;
- monitoring the geometry of the jointed part; and
- de-energizing the coil.

5,587,099

SAFETY CONTAINER FOR MICROWAVE OVEN BAKING UTENSIL

James O. Kuhn, Box 444 203 Litchfield Rd., Norfolk, Conn. 06058, and Lee J. Goldman, 23 Buckingham Ave., Harvey Cedars, N.J. 06008

Continuation-in-part of Ser. No. 166,517, Dec. 13, 1993, Pat. No. 5,396,051, and Ser. No. 173,784, Dec. 27, 1993. This application Oct. 31, 1994, Ser. No. 332,137


The portion of the term of this patent subsequent to Mar. 7, 2012, has been disclaimed.

Int. Cl. H05B 6/80

U.S. Cl. 219—728

7 Claims

1. A safety container for a baking utensil useable in a microwave oven to cook food held in the utensil, the utensil being provided



with a heating element having ferrite particles which absorb microwave energy to produce thermal heat to heat the food, said container comprising:

- separable upper and lower sections formed of a material insensitive to microwave energy for housing the utensil; and
- temperature-sensitive latching means that latch the sections together when the heating element of the utensil housed in the container raises the temperature of the utensil to a high level well above room temperature and automatically unlatch the sections when the temperature of the utensil is relatively cool and one can then safely remove the utensil from the container.

5,587,100


PROCESS AND THE CONTRIVANCE EMPLOYED FOR PRODUCING HEAT ENERGY WITHOUT COMBUSTION

James P. S. Huang, No. 22-4, Lane 64, Sec. II, Chung Shen Road, Chung Ho city, Taipei, Taiwan
Continuation of Ser. No. 237,281, May 3, 1994, abandoned.
This application Mar. 13, 1996, Ser. No. 614,912

Int. Cl.⁶ H05B 6/46

U.S. Cl. 219—772

4 Claims



1. A process for producing heat energy without combustion comprising:


- using a vacuum pump to evacuate air from a cylindrical shaped reactor including an electrostatic wave generator and a heat releasing reactor which interconnect to said cylindrical shaped reactor through a gas circulating device;
- flushing said cylindrical shape reactor and heat releasing reactor with nitrogen gas;
- filling said cylindrical shaped reactor and heat releasing reactor with a predetermined amount of gaseous matter selected from the group consisting of nitrogen, helium and hydrogen;
- turning on said electrostatic wave generator to produce static electricity at an energy level sufficient to energize the gaseous matter with kinetic energy of static electricity;
- introducing the gaseous matter energized by said kinetic energy of static electricity into said heat releasing reactor through said gas circulating device for converting said kinetic energy to heat energy;
- releasing said heat energy from said heat releasing reactor while restoring the energized gaseous matter to an unenergized state; and
- returning the restored gaseous matter to said cylindrical shape reactor to start another cycle.

5,587,101 GAS INJECTION NOZZLE FOR POURING LIQUID METAL

Hirokatsu Hattanda; Mitsukazu Ogiso; Yasuta Koike, and Kazuhiro Takagi, all of Tokyo, Japan, assignors to Tokyo Yogyo Kabushiki Kaisha, Tokyo, Japan
Filed Sep. 29, 1995, Ser. No. 536,438
Int. Cl.⁶ B22D 41/58

U.S. Cl. 222—603

3 Claims



- A gas injection nozzle for pouring liquid metal, wherein:
 - said nozzle having a circumference consisting of a porous refractory;
 - said circumference of said nozzle is surrounded by an iron shell having a gas injection pipe nozzle through which gas is injected to form a gas pool; said gas pool extending perpendicularly along said circumference of said nozzle between said porous refractory and said iron shell; and
 - said gas pool having a wavy space along at least one portion of said circumference of said nozzle.

5,587,102

MAGNETIC PAINT COMPOSITION AND METHOD

Donald J. Stern, Bellingham, Wash., and Dan Treleaven, Delta, Canada, assignors to DJS&T Limited Partnership, Bellingham, Wash.

Filed Aug. 25, 1994, Ser. No. 296,351

Int. Cl.⁶ C09D 5/23

U.S. Cl. 252—62.54

9 Claims

- A paint composition comprising:
 - water;
 - a binder;
 - a particulate magnetically permeable material, comprising iron particles, distributed in the composition;
 - a thickening agent having thixotropic and viscosity characteristic such that the composition has higher viscosity when subjected to substantially no shear movement and lower viscosity when the composition is subjected to movement having high shear rate;
 - a rust inhibitor that is characterized in that with the paint in its stored condition before application, the rust inhibitor prevents rust caused by water in the composition, and is further characterized in that after application and drying of the paint composition, the rust inhibitor remains distributed throughout the dried paint composition in a manner that at such time as a second coat of waterbase paint is applied, with water from the second coat migrating into the dried paint, the rust inhibitor in the dried paint is positioned to prevent rust occurring by the water in the second coat having migrated into the previously applied paint composition;

whereby when the composition is being stored, its high-viscosity maintains the particulate material suspended in the composition and the rust inhibitor prevents rust in the particulate material, when the paint composition is applied to a wall surface, it is subjected to high shear rates to lower the viscosity and cause its easy application, and when the paint composition is dried and a second coat of waterbase paint is applied over the dried paint composition, with water from the second coat migrating into the dried paint composition the dried paint composition remains intact and rust is prevented.

5,587,103 COMPOSITION, AND METHOD FOR USING SAME, FOR ETCHING METALLIC ALLOYS FROM A SUBSTRATE

Timothy A. Dennis, Bloomdale, Ohio, assignor to Harris Corporation, Melbourne, Fla.

Filed Jan. 17, 1996, Ser. No. 587,692

Int. Cl.⁶ C09K 13/08


U.S. Cl. 252—79.3

12 Claims

1. A method for removing Aluminum Alloy from a substrate comprising applying a composition to said Aluminum Alloy, said composition being five (5) to ten (10) parts by volume Nitric Acid, four (4) to ten (10) parts by volume Buffered Oxide Etch, thirty (30) to sixty-five (65) parts by volume Phosphoric Acid, and twenty-one (21) to thirty (30) parts by volume Water.

wherein

D=a hydrocarbon radical including an unsaturated functionality selected from the group consisting of:



R₁=lower alkyl, aryl, substituted alkyl, substituted aryl, lower alkoxy, aryloxy, halogen, or mixtures thereof;

G=—CH₂—, —O—, —S—, —SO₂—, —SO—, —CO—, —CH(R)—, or —C(R)₂—;

j=0, 1, or 2;

T=allyl or methallyl;

Me=methyl; and

R=hydrogen, lower alkyl, or phenyl,

with a diamine of the formula H₂N—R₂—NH₂, and a compound of the formula OCN—R₃—NCO, wherein R₃ is a hydrocarbon radical and R₂ is a hydrocarbon radical.

2. The method of claim 1 further comprising the step of blending the condensation product with an effective amount of a diluent.

5,587,104 READILY SOLUBLE DRY CONCENTRATES CONTAINING INGREDIENTS OF DETERGENTS

Christiane Zeise, Korschenbroich; Wilfried Raehse, Duesseldorf; Jochen Jacobs, Wuppertal, and Juergen Hoffmeister, Duesseldorf, all of Germany, assignors to Henkel Kommanditgesellschaft auf Aktien, Duesseldorf, Germany
PCT No. PCT/EP91/02366, § 371 Date Sep. 8, 1993, § 102(e) Date Sep. 8, 1993, PCT Pub. No. WO92/12229, PCT Pub. Date Jul. 23, 1992

PCT Filed Dec. 10, 1991, Ser. No. 87,684

Claims priority, application Germany, Jan. 8, 1991, 41 00 306.3

Int. Cl.⁶ C11D 17/00

U.S. Cl. 510—298

21 Claims

1. Free-flowing and storable granular compacts comprising ingredients of detergent or cleaning compositions in concentrated form, said compacts having been prepared by the process of

- preparing an adhesively bound dry premix containing
 - fine-particle detergent ingredients substantially free of binding or adhesive properties, and
 - fine-particle detergent ingredients having binding or adhesive properties to form a substantially homogeneous premix, and
- press-molding said premix at a temperature of from about 40° C. to 80° C. in the substantial absence of shear forces whereby air is microdispersed in the resultant compacts.

5,587,105

METHODS FOR MAKING LIQUID MOLDING COMPOUNDS USING DIAMINES AND DICYANATES

Clyde H. Sheppard, Boeing Aerospace Company, P.O. Box 399, M/S 73-09, Seattle, Wash. 98124-2499, and Hyman R. Lubowitz, 26 Coral Tree Ln., Rolling Hills Estates, Calif. 90274

Division of Ser. No. 168,289, Mar. 15, 1988. This application


Jun. 5, 1995, Ser. No. 493,434

Int. Cl.⁶ C07D 209/02; C09K 3/00


U.S. Cl. 252—183.11

10 Claims

1. A method for making a liquid molding compound of the formula



comprising the step of simultaneously condensing an unsaturated anhydride selected from the group consisting of:



5,587,106 LIQUID CRYSTAL DISPLAY DEVICES AND LIQUID CRYSTAL SUBSTANCES THEREFOR

Masamichi Mizukami, Tsukuba; Tomoyuki Yui, Nagareyama; Yoshihisa Arai, and Yoshihiro Gocho, both of Tsukuba, all of Japan, assignors to Mitsubishi Gas Chemical Company, Inc., Tokyo, Japan

Continuation of Ser. No. 52,604, Apr. 27, 1993, abandoned.


This application Jun. 6, 1995, Ser. No. 467,898

Claims priority, application Japan, Apr. 27, 1992, 4-107529


Int. Cl.⁶ C09K 19/34; C07D 239/02; G02F 1/13

U.S. Cl. 252—299.61

9 Claims



1. Liquid crystal substances which are represented by the formula (1):



wherein

R is a straight chain alkyl group having 6 to 10 carbon atoms,

X is hydrogen or fluorine atom,

Z is [-CF₂-, -CF₂-, [or -C₂H₅], and

C** stands for an asymmetric carbon atom, and

l is an integer of 5 to 7, m is 1 and n is 2.

5,587,107

SIO₂ AEROGELS CONTAINING CARBON PARTICLES AND THEIR PREPARATION
 Fritz Schwertfeger; Ulrich Schubert; Elisabeth Seyfried; Joachim Kuhn; Jochen Fricke, all of Wuerzburg, and Manfred Mielke, Heidelberg, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany
 Filed Jan. 11, 1994, Ser. No. 179,698
 Claims priority, application Germany, Jan. 13, 1993, 43 00 598.5

Int. Cl.⁶ B01J 13/00; E04B 1/76

U.S. Cl. 252—315.6 6 Claims
 1. An SiO₂ aerogel having a density of up to 395 kg/m³ and containing carbon particles, which aerogel is obtained by heating a) organically modified SiO₂ aerogels having a density of up to 395 kg/m³ in the presence of at least one pyrolyzable hydrocarbon gas or at least one inert gas or b) organically unmodified SiO₂ aerogels having a density of up to 395 kg/m³ in the presence of at least one pyrolyzable hydrocarbon gas and in the presence or absence of inert gases to 600°–1300° C.

5,587,108

STYRENE MONOMER BASED NAIL TIP BLENDER AND BRUSH CLEANER
 Michael R. Schick, Nashotah, Wis., assignor to European Touch Co., Inc., Milwaukee, Wis.
 Filed Oct. 6, 1994, Ser. No. 319,278
 Int. Cl.⁶ C08K 501/507; 5/15; A61K 7/04

U.S. Cl. 252—364 10 Claims
 1. A solvent for partially dissolving an edge of a synthetic nail, said solvent comprising:
 A) about 20% to about 50% by weight of styrene monomer;
 B) about 20% to about 60% by weight of acetone;
 C) about 15% to about 30% by weight of gamma butyrolactone; and
 D) about 1% to about 10% by weight of a mixture comprising safflower oil and fragrance.


5,587,109

METHOD FOR INHIBITION OF OXYGEN CORROSION IN AQUEOUS SYSTEMS BY THE USE OF A TANNIN ACTIVATED OXYGEN SCAVENGER
 Brian Greaves, Runcorn; Stephen C. Poole, Newton-Le-Willows, both of England; Chih M. Hwa, Palatine, and Joseph C. Fan, Lake Zurich, both of Ill., assignors to W. R. Grace & Co.-Conn., New York, N.Y.
 Division of Ser. No. 107,550, Aug. 17, 1993, abandoned. This application Apr. 19, 1995, Ser. No. 426,162
 Claims priority, application United Kingdom, Aug. 17, 1992, 9217448


Int. Cl.⁶ C23F 11/12; 11/16

U.S. Cl. 252—392

14 Claims



1. A method for the treatment of an aqueous system which comprises incorporating into the system (i) at least one member of the group consisting of (a) hydroxylamine or its derivatives, (b) water soluble salts and (c) precursors thereof the formula:



wherein R₁, R₂ and R₃, which may be the same or different, is a member of the group consisting of hydrogen, alkyl of 1 to 8 carbon atoms, and aryl, and (ii) tannin wherein (i) and (ii) are in a weight ratio of at least 2:1.

5,587,110

COMPOSITION BEING CAPABLE OF IMPARTING CONDUCTIVITY AND NON-TACKIFYING PROPERTY. PAINT USING THE COMPOSITION, AND ROLLER
 Masayuki Yamana, and Tomohiro Isogai, both of Settsu, Japan, assignors to Dainippon Ink & Chemicals, Ltd., Osaka, Japan
 PCT No. PCT/JP94/01655, § 371 Date Jun. 30, 1995, § 102(e) Date Jun. 30, 1995, PCT Pub. No. WO95/09887, PCT Pub. Date Apr. 13, 1995


PCT Filed Oct. 3, 1994, Ser. No. 481,366

Claims priority, application Japan, Oct. 5, 1993, 5-249593; Apr. 28, 1994, 6-091993

Int. Cl.⁶ H01B 1/00; 1/24

U.S. Cl. 252—511

20 Claims



1. A composition consisting essentially of (A) carbon fluoride particles having a ratio F/C of fluorine atom to carbon atom of more than 0.5 and less than 1.0, and (B) at least one resin material selected from the group consisting of a thermoplastic resin, a thermosetting resin and a rubber; wherein the weight ratio of (A) to (B) is from 1/99 to 30/70, and said composition imparts electrical conductivity and non-tackifying property.

5,587,111

METAL PASTE, PROCESS FOR PRODUCING SAME AND METHOD OF MAKING A METALLIC THIN FILM USING THE METAL PASTE

Kazuhiro Watanabe, Tsuchiura; Michihiro Oshima, Hachinohe; Kazuhiro Setoguchi, Chiba, and Masaaki Oda, Chiba-ken, all of Japan, assignors to Vacuum Metallurgical Co., Ltd., Chiba-ken, Japan

Continuation-in-part of Ser. No. 622,569, Dec. 5, 1990, abandoned. This application Mar. 29, 1991, Ser. No. 677,190

Claims priority, application Japan, Mar. 29, 1990, 2-81635

Int. Cl.⁶ H01B 1/02

U.S. Cl. 252—514

8 Claims


1. A metal paste comprising at least 14 wt. % of ultrafine particles of gold individually uniformly dispersed in a solvent

5,587,113

DEVICE FOR THE TREATMENT OF POLLUTED WATER
 Antonio Caballero Pichardo, Calle de la Amargura No. 15 Lomas de la Herradura C.P. 52785 Huixquilucan, Mexico
 Division of Ser. No. 320,567, Oct. 11, 1994, which is a continuation of Ser. No. 10,144, Jan. 28, 1993, abandoned. This application Apr. 12, 1995, Ser. No. 420,760
 Int. Cl.⁶ C02F 1/74

U.S. Cl. 261—116

2 Claims



consisting essentially of at least one organic compound, said particles having a particle size of 100 angstroms or less and each particle having its entire surface covered with the solvent.

5,587,112

BENZAZOLE COMPOUNDS WITH ESIPT FLUORESCENCE


Joel M. Kauffman, Wayne, and Peter T. Litak, Lansdowne, both of Pa., assignors to Philadelphia College of Pharmacy and Science, Philadelphia, Pa.

Filed Sep. 2, 1994, Ser. No. 300,401


Int. Cl.⁶ F21V 9/04; C09K 11/06; C07D 277/62

U.S. Cl. 252—589

21 Claims



1. An organic, fluorescent material comprising a 2-benzazoyl compound having the structure:



wherein X is a —N(R₁)— group, —O—, or —S—; Y is a proton donating group; Z is a —N(R₁)— group, —O—, or —S—; R₁ is a H or a C₁ to C₁₀ alkyl group; R₂ is a H or an added 2-benzazoyl group; R₃ is a H when R₂ is a H and R₃ is H or a Y when R₂ is an added 2-benzazoyl group; and the 2-benzazoyl, the added 2-benzazoyl, or both the 2-benzazoyl and the added 2-benzazoyl is unsubstituted or substituted with one to four R₄ group(s), wherein each R₄ individually is a C₁ to C₁₀ alkyl group, aryl group, halo group, or alkyl sulfonyl; or wherein two or more R₄ groups are fused into an aromatic group.

1. An aeration device, comprising:
 a tubular section defining a primary chamber, said tubular section having an opening in a side thereof forming an orifice adjacent said primary chamber for the admission of ambient air from the surrounding atmosphere into said primary chamber, said tubular section having an upper peripheral edge and a lower peripheral edge;
 a screen for preventing the entrance of foreign particles positioned over the orifice in said tubular section;
 means defining a distribution chamber for receiving a liquid to be aerated; said distribution chamber positioned above and sealingly connected to the upper peripheral edge of said tubular section;
 a plurality of high speed nozzles positioned at a top end of said primary chamber and fluidly connected to said distribution chamber for delivering accelerated sprays of liquid from said distribution chamber to said primary chamber;
 a tapering section having an upper peripheral edge and a lower peripheral edge, wherein the upper peripheral edge of said tapering section is positioned below and sealingly connected to the lower peripheral edge of said tubular section, and wherein a diameter of the upper peripheral edge of said tapering section is larger than a diameter of the lower peripheral edge of said tapering section;
 a venturi section including an upper peripheral edge and a lower peripheral edge, wherein the upper peripheral edge of said venturi section is positioned below and sealingly connected to the lower peripheral edge of the tapering section for accelerating the air and liquid therefrom with the entrapped air and for creating a suction at the orifice for drawing air into said primary chamber;
 a single drain pipe having an upper peripheral edge that is sealingly connected to the lower peripheral edge of said venturi section, said drain pipe having a lower open end, wherein said drain pipe constitutes the sole outlet of said device such that all of the liquid and air entering said device exits said device through said drain pipe wherein said tapering section, said venturi section, and said drain pipe each have respective maximum cross sectional areas that are substantially smaller than a maximum cross sectional flow area of said primary chamber.

5,587,114


AERATION SYSTEM EMPLOYING RETRIEVBLE
AERATION MODULESCharles E. Tharp, Columbia, Mo., assignor to Environmental
Dynamics, Inc., Columbia, Mo.

Filed Jun. 6, 1995, Ser. No. 471,768

Int. Cl.⁶ B01F 3/04

U.S. Cl. 261-124

14 Claims




1. Apparatus for aerating liquid in a basin, comprising:
an air supply pipe in the basin adapted to receive air under pressure, said air supply pipe comprising a floating pipe on the surface of the liquid;
a submerged conduit in the basin;
a plurality of aerators mounted to said submerged conduit in a manner to receive air therefrom, said aerators being adapted to discharge air into the liquid;
flexible hose means for directing air from said air supply pipe to said submerged conduit;
means for normally holding said submerged conduit down in the basin at a submerged location; and
means for disabling said holding means to allow the buoyancy of said conduit to raise the conduit and aerators to a location accessible from the surface of the liquid for maintenance.

5,587,115

METHOD OF MANUFACTURING A CONDUIT
ASSEMBLY WITH A FLOATING DIVIDERJerry L. Allen, Westfield Ctr., Ohio, assignor to Vikimatic
Sales, Inc., Wadsworth, OhioDivision of Ser. No. 215,595, Mar. 22, 1994, abandoned. This
application May 19, 1995, Ser. No. 446,563Int. Cl.⁶ B29C 47/02

U.S. Cl. 264-1.24

8 Claims




1. A method of manufacturing a conduit assembly comprising the steps of extruding a longitudinally extending tubular casing through a die, and at the same time feeding a longitudinally extending web member into the casing without contacting the casing as it is being extruded.

5,587,116

PROCESS FOR INJECTION MOLDING OPTICAL
FERRULESMelvin H. Johnson, Chadds Ford, Pa., and Frank M. Willis,
Wenonah, N.J., assignors to E. I. Du Pont de Nemours and
Company, Wilmington, Del.Division of Ser. No. 238,238, May 4, 1994, Pat. No. 5,482,451,
which is a continuation of Ser. No. 984,796, Dec. 3, 1992,
abandoned. This application Jun. 2, 1995, Ser. No. 459,157Int. Cl.⁶ B29D 11/00; B29C 45/14; 45/36

U.S. Cl. 264-1.25

9 Claims



1. A process for the preparation of an optical ferrule containing a cylindrical member therein comprising:

- introducing a cylindrical member into guide means having first and second ends and a center line and an aperture formed along the center line, wherein the cylindrical member is received along the aperture;
- positioning a sleeve for receiving a piston therethrough aligned relative to said guide means of (a), said piston having first and second ends and a center line and an aperture formed along the center line, said first end of the piston located sufficiently close to said second end of said guide means in a first position, so that said first end of said piston receives the cylindrical member along the aperture of said piston;
- locating a pin to extend into said sleeve and having a first end in contact with said second end of said piston and having a hole formed therethrough for receiving the cylindrical member and positioning means attached to a second end of said pin;
- exerting a force sufficient to position said piston in the first position via biasing means which engages said positioning means and a pusher attached to said biasing means;
- dispensing polymer through one or more fill gates positioned equidistant from one another at a uniform pressure into a cavity defined by said second end of said guide means, said sleeve and said first end of said piston, and containing said guide means, piston and pin in position relative to each other, the polymer dispensed sufficiently to move said piston to a second position to form the optical ferrule within said cavity;
- cooling the formed optical ferrule under pressure; and
- withdrawing the optical ferrule with a cylindrical member contained therein from said cavity.

5,587,117

PROCESS FOR INSULATING PIPES USING
POLYURETHANE RIGID FOAMS BY THE ROTATIONAL
CASTING PROCESSNorbert Eisen, Köln; Lutz-Peter Godthardt, Leverkusen, and
Peter Haas, Haan, all of Germany, assignors to Bayer
Aktiengesellschaft, Leverkusen, Germany

Filed Feb. 3, 1995, Ser. No. 382,813


Claims priority, application Germany, Feb. 17, 1994, 44 05
061.5Int. Cl.⁶ B29C 44/06; 44/12

U.S. Cl. 264-45.7

11 Claims


1. In a process for insulating pipes by applying a rigid polyurethane foam-forming reaction mixture as an insulating layer and optionally applying an external top coating, with both the insulating layer and the top coating being applied by a rotational casting process, the improvement wherein said foam-forming reaction mixture comprises:

- an aromatic polyisocyanate with
- an organic compound having a molecular weight of from 92 to 1,000, containing on average at least 3 hydroxyl groups and
- an aliphatic, cycloaliphatic or aromatic polyamine and/or polyimine having a molecular weight of from 32 to 1,000 as a cross-linking agent in the presence
- of a blowing agent, and optionally in the presence of
- known auxiliary substances and additives wherein said reaction mixture also contains
- one or more compounds having a molecular weight of from about 166 to about 1,000 and being of the general formula



wherein

n represents an integer between 2 and 9,

R¹ signifies hydrogen, a C₁-C₉ alkyl radical or aR² signifies hydrogen, andR³ and R⁴ signify hydrogen or methyl.

5,587,118

PROCESS FOR MAKING FIBER FOR A CARPET FACE
YARN

William C. Mallonee, P.O. Box 2318, Dalton, Ga. 30722

Filed Mar. 14, 1995, Ser. No. 407,507

Int. Cl.⁶ D01F 8/06; 8/12

U.S. Cl. 264-78

12 Claims


1. A method for making conjugate filaments for a carpet face yarn having improved stain resistance and resiliency comprising blending from about 5 to about 40 wt. % polyamide pellets with from about 60 to about 95 wt. % polyolefin pellets; feeding the blend to a hot melt extruder to melt the mixture; and forcing the molten mixture at a shear rate within the range of from about 1000 to about 5000 reciprocal seconds through a spinneret containing a plurality of trilobal or delta capillary openings thereby forming conjugate filaments containing polyamide fibrils formed in-situ in a trilobal or delta cross-section polyolefin matrix, said filaments having a denier ranging from about 1350 to about 1550 per 84 filaments.

5,587,119

METHOD FOR MANUFACTURING A COAXIAL
INTERCONNECTDavid M. White, Sulphur Springs, Tex., assignor to E-Systems,
Inc., Dallas, Tex.Division of Ser. No. 305,290, Sep. 14, 1994, abandoned. This
application May 26, 1995, Ser. No. 452,104Int. Cl.⁶ C04B 35/00

U.S. Cl. 264-104

4 Claims



1. A method for manufacturing a coaxial interconnect, comprising the steps of:
forming an outer aperture through a substrate layer;
coating an inner surface of the outer aperture in the substrate layer with an electrically conductive material to form an outer conductor of the coaxial interconnect;
filling the coated outer aperture with a dielectric material;
forming an inner aperture through the dielectric material; and
filling the inner aperture in the dielectric material with an electrically conductive material to form a center conductor of the coaxial interconnect.

5,587,120

METHOD FOR SHAPING A POLYMER MIXTURE INTO
A BLOCK WITH A STABLE SHAPE AND SIZEJean-Paul B. Vieslet, Rue Boubette 92/31, B 4420 Montegnée,
Belgium; Bernard P. Vieslet, Apar. 12A, Collinas de Bello
Monte, Edie. Rio Aranca, Caracas, Venezuela, and Pierre G.
Poswick, Servitude de la Dreve 3, B-7050 Erbisoful, BelgiumPCT No. PCT/BE94/00022, § 371 Date Nov. 6, 1995, § 102(e)
Date Nov. 6, 1995, PCT Pub. No. WO94/21435, PCT Pub.
Date Sep. 29, 1994


PCT Filed Mar. 15, 1994, Ser. No. 525,579

Claims priority, application Belgium, Mar. 16, 1993, 9300249

Int. Cl.⁶ B29C 35/02

U.S. Cl. 264-118

8 Claims



1. Method for shaping an elementary block of stable shape and size from fragments of a polymer mixture which is compressed and constrained under a load into a defined volume of a hydraulic press (1), comprising at least one dead volume delimited by a first moving platen (3) moved into end of travel by a piston (4) and a fixed platen (2) constituting the end wall of the press, so as to form a bale of compacted fragments of a polymer mixture which is transpierced by spikes (8) heated to a temperature above the softening point of at least one of the polymers of the aforementioned mixture, wherein spikes (8), carried by a second moving platen (9) arranged with respect to the first moving platen (3), on the other side of the fixed platen (2) forming the end wall of the press (1), are made to penetrate, via orifices provided through the fixed platen (2) forming the end wall of the press, into the bale of

polymers previously compacted in the dead volume of the press, during or after compression.

a third heated zone being maintained at a temperature in the range of from about 100° C. to about 180° C., to form an annealed polypropylene suture.

5,587,121

METHOD AND APPARATUS FOR THE PRODUCTION OF A GAS-PERVIOUS PART IN A GAS-PERVIOUS MOULD AND A PRODUCT MADE BY THIS METHOD

Juha Vesa, Palokärjenskatu 14 D, Turku, Finland
PCT No. PCT/FI94/00013, § 371 Date Jul. 13, 1995, § 102(e)
Date Jul. 13, 1995, PCT Pub. No. WO94/15768, PCT Pub. Date Jul. 21, 1994


PCT Filed Jan. 12, 1994, Ser. No. 491,857

Claims priority, application Finland, Jan. 13, 1993, 930125

Int. Cl.⁶ B29C 35/02; B68G 11/03

U.S. Cl. 264—126

12 Claims



1. A method for moulding a part from a gas-pervious raw material compound in a gas-pervious mould which at least at one stage of the production is positioned in the gas flow of a flow chamber in such a way that the gas flows through the mould and the raw material, comprising the steps of:

positioning a gas-pervious layer of filling material immediately in front of and/or behind the gas-pervious mould in the gas flow; and

forming said layer of gas-pervious filling material so that the pressure drop across the mould, the raw material compound and the filling material layer is substantially constant over the whole cross-section of the gas flow through the mould, raw material compound and the filling material layer.

5,587,122

IN-LINE ANNEALING OF SUTURES


David J. Lennard, Flemington, N.J., assignor to Ethicon, Inc., Somerville, N.J.

Filed Feb. 10, 1995, Ser. No. 386,617

Int. Cl.⁶ D01D 5/08; 10/02

U.S. Cl. 264—178 F

9 Claims



1. An in-line process for producing a polypropylene suture comprising performing the steps of (a) extruding melted polypropylene resin through an orifice and rapidly quenching the melted polypropylene resin to produce a filament; (b) drawing the filament in the range of from about 4x to about 7.5x in a first drawing zone to produce a drawn filament; (c) drawing the singly drawn filament in a second drawing zone in the range of from about 1.0x to about 2.5x while in a second heated zone being maintained at a temperature in the range of from about 30° C. to about 160° C., to form a doubly drawn filament; (d) relaxing and annealing the doubly drawn filament in the range of from about 0.75x to about 0.9x, in

5,587,123

Patent Not Issued For This Number

5,587,124

METHOD OF MAKING SYNTHETIC DIAMOND FILM WITH REDUCED BOWING


John Meroth, 333 Howard St., Northboro, Mass. 01532

Filed Jul. 5, 1994, Ser. No. 270,656

Int. Cl.⁶ B29C 11/00; B28B 35/00

U.S. Cl. 264—430

12 Claims



1. A method for synthesizing generally flat free-standing diamond, comprising the steps of:

- providing a deposition chamber;
- providing a deposition surface in said deposition chamber, said deposition surface having a concave contour;
- directing a plasma toward said concave deposition surface, the plasma including hydrogen and a hydrocarbon, such that synthetic diamond is formed on said concave deposition surface; and
- releasing said synthetic diamond from said concave deposition surface to obtain free standing diamond, wherein said released synthetic diamond generally flattens.

5,587,125

NON-COEXTRUSION METHOD OF MAKING MULTI-LAYER ANGIOPLASTY BALLOONS

Suranjan Roychowdhury, Minnetonka, Minn., assignor to Schneider (USA) Inc., Minneapolis, Minn.

Filed Aug. 15, 1994, Ser. No. 290,075


Int. Cl.⁶ B29C 49/22

U.S. Cl. 264—515

18 Claims

1. A method of manufacturing a multi-layer expander member for an angioplasty catheter comprising the steps of:

- preforming a first tubular parison of a polymeric material having first physical properties;
- preforming a second tubular parison of a polymeric material having second physical properties;
- later disposing one of said first and second preformed tubular parisons over the other of said first and second preformed tubular parisons to form a composite parison;
- heating said composite parison to a predetermined temperature; and
- blow-molding said composite parison in a mold having a cavity of a predetermined length and radial dimension to bond



the polymeric material comprising the first tubular parison to the polymeric material comprising the second tubular parison in forming said multi-layer expander member.

5,587,126

METHOD OF MANUFACTURING A PIPE LINER FOR INSTALLATION IN AN EXISTING CONDUIT


Campbell H. Steketee, Jr., Salem, Oreg., assignor to NuPipe, Inc., Memphis, Tenn.

Continuation of Ser. No. 34,918, Mar. 19, 1993, which is a continuation of Ser. No. 612,163, Nov. 9, 1990, abandoned, which is a division of Ser. No. 180,904, Apr. 13, 1988, abandoned, which is a continuation-in-part of Ser. No. 76,973, Jul. 28, 1987, Pat. No. 4,867,921, which is a continuation-in-part of Ser. No. 846,322, Mar. 31, 1986, abandoned. This application Jun. 7, 1995, Ser. No. 485,014

Int. Cl.⁶ B29C 47/90; 63/34

U.S. Cl. 264—568

18 Claims



1. A method of manufacturing a thermoplastic liner for installation into an existing conduit in a desired non-circular collapsed and folded form, comprising:

- extruding thermoplastic material through a die to form a substantially tubular shape of a desired size;
- shaping the extruded tubular material exiting the die at a temperature above the temperature which the material is pliable to the desired non-circular collapsed and folded form; and
- cooling the extruded material in the non-circular collapsed and folded form after shaping so that the liner has a memory for the desired non-circular collapsed and folded form such that when reheated to render it pliable, it retains the desired non-circular collapsed and folded form.

5,587,127

METHOD AND APPARATUS FOR CARTON STERILIZATION

Leonard A. Carlson, Bloomington, Minn., assignor to Tetra Laval Holdings & Finance SA, Pully, Switzerland


Division of Ser. No. 974,694, Nov. 12, 1992, Pat. No. 5,368,828. This application Aug. 24, 1994, Ser. No. 293,948

Int. Cl.⁶ A61L 2/18

U.S. Cl. 422—28

8 Claims

1. A method for sterilizing food cartons of the type having a preformed bottom and upright side walls, the method comprising:



applying a solution of hydrogen peroxide to the bottom and side walls of a carton;

inserting a mandrel into the carton, said mandrel having an interior and a plurality of nozzles communicating with the interior;

directing a stream of heated air through the interior of the mandrel and through said nozzles while the mandrel is in the carton, and out of the carton through a space between sides of the mandrel and the side walls of the carton; and

withdrawing the mandrel from the carton.

5,587,128

MESOSCALE POLYNUCLEOTIDE AMPLIFICATION DEVICES


Peter Wilding, Paoli, and Larry J. Kricka, Berwyn, both of Pa., assignors to The Trustees of the University of Pennsylvania, Philadelphia, Pa.

Continuation-in-part of Ser. No. 308,199, Sep. 19, 1994, Pat. No. 5,498,392, which is a continuation of Ser. No. 877,662, May 1, 1992, abandoned. This application Nov. 14, 1994, Ser. No. 338,728

Int. Cl.⁶ C12Q 1/68; G01N 33/50; 21/01

U.S. Cl. 422—50

36 Claims



1. A device for amplifying a polynucleotide in a sample by conducting a polynucleotide amplification reaction, the device comprising:

- a solid substrate fabricated to include at least one polynucleotide amplification reaction chamber, said chamber being permanently sealed with a cover and having one mesoscale cross-sectional dimension of width or depth between about 0.1 and 1,000 μm, said reaction chamber comprising at least one wall having associated therewith a composition which diminishes inhibition by said wall of a polynucleotide amplification reaction in said chamber; and

at least one port in fluid communication with said reaction chamber, for introducing said sample into said reaction chamber, said reaction chamber and at least one said port being of dissimilar cross-section.

5,587,129

APPARATUS FOR AUTOMATICALLY ANALYZING SPECIMEN


Tsuyoshi Kurosaki; Atsuo Tomioka, and Takashi Yamato, all of Hyogo, Japan, assignors to Toa Medical Electronics Co., Ltd., Hyogo, Japan

Filed Sep. 20, 1995, Ser. No. 530,901

Claims priority, application Japan, Sep. 21, 1994, 6-266015
Int. Cl.⁶ G01N 35/02

U.S. Cl. 422-64

13 Claims



1. An apparatus for automatically analyzing a specimen, comprising:
sample vial retaining means for retaining a sample vial containing a specimen;
a stock vial into which part of the specimen in the sample vial is to be dispensed;
stock vial retaining means for retaining a stock vial;
first dispensing means for dispensing the specimen in the sample vial into the stock vial;
an assay vial into which part of the specimen in the stock vial is to be dispensed;
assay vial retaining means for retaining a plurality of assay vials;
second dispensing means for dispensing the specimen in the stock vial into the assay vial;
a reagent container for containing a reagent;
third dispensing means for dispensing the reagent into the assay vial;
assay means for assaying the specimen in the assay vial;
assay vial transporting means for transporting the assay vial from the assay vial retaining means to the assay means;
vial discharging means for discharging the assay vial after the assay; and
a controller for controlling the sample vial retaining means, the stock vial retaining means, the first dispensing means, the assay vial retaining means, the second dispensing means, the third dispensing means, the assay means, the assay vial transporting means, and the vial discharging means,
whereby the specimen, once dispensed from the sample vial into the stock vial, is dispensed from the stock vial into the assay vial for the assay throughout the automatic analysis.

5,587,130

SELECTED AREA ADHESION AND SURFACE PASSIVATION OF METAL FILMS


Qingcheng Bao, Tempe; Ian Sorensen, Phoenix, and William Glaunsinger, Chandler, all of Ariz., assignors to Arizona Board of Regents, Tempe, Ariz.

Continuation-in-part of Ser. No. 31,610, Mar. 15, 1993, Pat. No. 5,466,605. This application Dec. 9, 1994, Ser. No. 353,448
Int. Cl.⁶ G01N 27/12

U.S. Cl. 422-88

28 Claims

1. A method of affixing metal film to a substrate with controlled passivation of said metal film, comprising:



applying a thin layer of a metallic adhesive to a portion of a surface of the substrate to form an adhesive pattern;
applying the metal film to the surface of the substrate over the metallic adhesive so that said metal film is in contact with at least some portion of said metallic adhesive and at least some portion of the surface of the substrate;
exposing an assembly including the substrate, the metallic adhesive, and the metal film to an atmosphere containing a constituent having sufficient bond energy to form a compound having a lower energy state than the pure metallic adhesive, to cause the metallic adhesive to migrate to an exposed surface of said metal film and form a stable compound, thereby passivating a portion of the exposed surface of said metal film corresponding to said adhesive pattern.

5,587,131

SYSTEM FOR AN EFFICIENT MANUFACTURE OF OZONE

Boris Malkin; Gena Perlov, and Shmuel Yannal, all of Haifa, Israel, assignors to Ozontech Ltd., Israel

Continuation-in-part of Ser. No. 209,563, Mar. 10, 1994,


abandoned. This application Mar. 17, 1995, Ser. No. 405,848

Claims priority, application Israel, Mar. 25, 1993, 105166

Int. Cl.⁶ B01J 19/12

U.S. Cl. 422-186.11

14 Claims



1. A system for producing ozone at a high efficiency from oxygen or air, having at least two parallel electrodes made of metallic surfaces and separated by dielectric insulating material, wherein air or oxygen is passed through the gaps between the electrodes with an effective electric field of at least 4 kV/mm, comprising:

- a ratio of electrode surface area to gas volume of at least 2 cm².min/l.
- the electric field in said gap formed by the difference in potentials between the electrodes and the dielectric insulating material and having a breakdown voltage at least 12 kV/mm; and
- Peltier heat pumps connected to the outer surface of the electrodes and capable of removing heat produced to the outer surface of the electrodes.

5,587,132

METHOD FOR PRODUCING HIGH PURITY VANADIUM ELECTROLYTIC SOLUTION

Masato Nakajima; Toshiaki Akahoshi; Masatoshi Sawahata; Yutaka Nomura, and Kanji Sato, all of Kashima-gun, Japan, assignors to Kashima-Kita Electric Power Corporation, Ibaraki-ken, Japan

Filed Nov. 6, 1995, Ser. No. 554,570

Claims priority, application Japan, Nov. 17, 1994, 6-283694
Int. Cl.⁶ C01G 31/00; H01B 1/00

U.S. Cl. 423-62

12 Claims

1. A method for producing an electrolytic solution containing vanadium as positive and negative electrode active materials, said method comprising:

- (1) purifying a vanadium compound selected from the group consisting of vanadium pentoxide and ammonium metavanadate by:
dissolving a crude mixture containing said vanadium compound and impurities in a solvent under an alkaline or neutral condition,
precipitating said polyvanadate compound by thermal polymerization of vanadium ions under an acidic condition, and isolating said polyvanadate compound from the solution containing impurities;
- (2) baking part of said pure polyvanadate compound at a temperature range of 400° to 690° C. in an inert or oxidizing gas atmosphere so as to remove ammonium ions;
- (3) treating another part of said polyvanadate compound under a reductive atmosphere to form a trivalent vanadium compound is formed;
- (4) dissolving said trivalent vanadium compound in an acid solution to form a V³⁺ electrolytic solution; and
- (5) mixing said vanadium pentoxide and said V³⁺ electrolytic solution to form a V⁴⁺/V³⁺ mixed electrolytic solution.

5,587,133

DELITHIATED COBALT OXIDE AND NICKEL OXIDE PHASES AND METHOD OF PREPARING SAME

Glenn G. Amatucci, Raritan, and Jean-Marie Tarascon, Martinsville, both of N.J., assignors to Bell Communications Research, Inc., Morristown, N.J.

Filed Feb. 3, 1995, Ser. No. 383,401

Int. Cl.⁶ C01D 1/02; C01G 49/02; 51/04

U.S. Cl. 423-138

10 Claims

1. A method of preparing a stable cobalt dioxide phase comprising:

- preparing an electrolytic cell having an anode, an electrolyte inert to oxidation, and a cathode comprising a lithium cobalt oxide intercalation complex; and
- applying a voltage in excess of about 5.0 V to deintercalate substantially all lithium from said lithium cobalt oxide intercalation complex.

2. A stable dioxide phase prepared according to the method of claim 1.

5,587,134

PROCESS FOR DECOMPOSING AMMONIA IN AN OFF-GAS

Flemming Dannevang, Copenhagen, Denmark, assignor to Haldor Topsøe A/S, Denmark

Filed Oct. 12, 1995, Ser. No. 542,145

Claims priority, application Denmark, Oct. 14, 1994, 1184/94
Int. Cl.⁶ B01D 53/22

U.S. Cl. 423-237

9 Claims

1. In a process for the catalytic low temperature oxidation of ammonia with oxygen to nitrogen in an ammonia containing off-gas that also contains oxygen at a temperature of between 200° C. and 500° C., said oxygen consisting essentially of O₂, the improvement comprising the steps of:

sulfating a catalyst comprising on an inert carrier a metal selected from the group consisting of copper, cobalt, iron, chromium, nickel, manganese and mixtures thereof in the form of their oxides and/or sulfates and a further component selected from the group of platinum metals;
contacting the ammonia containing off-gas with the catalyst, and withdrawing a decomposed gas being rich in nitrogen.

5,587,135

PROCESS FOR THE CATALYTIC DECOMPOSITION OF DINITROGEN MONOXIDE IN A GAS STREAM

Thomas Fetzner, Speyer; Wolfgang Buechele, Ludwigshafen; Hermann Wistuba, Mannheim; Bernhard Otto, Limburgerhof; Gert Buerger, Mannheim, and Paul Pijl, Frankenthal, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

PCT No. PCT/EP94/00081, § 371 Date Mar. 24, 1995, § 102(e)
Date Mar. 24, 1995, PCT Pub. No. WO94/16798, PCT Pub. Date Aug. 4, 1994

PCT Filed Jan. 13, 1994, Ser. No. 403,835

Claims priority, application Germany, Jan. 21, 1993, 43 01 470.4

Int. Cl.⁶ B01J 8/00

U.S. Cl. 423-239.1

12 Claims

1. A process for the catalytic decomposition of dinitrogen monoxide in a gas stream which comprises contacting the gas stream at temperatures of 200°-900° C. and pressures of 0.1 to 20 bar with a catalyst free of noble metals, said catalyst being prepared by combining a spinel CuAl₂O₄ in an Al₂O₃ matrix with an additional spinel-forming metal component selected from the group consisting of tin, lead, zinc, magnesium, calcium, strontium and barium or mixtures thereof in elemental form or as an oxide or salt, and calcining at temperatures of 300°-1300° C. and under pressures of 0.1-200 bar for partial or complete liberation of the copper from said spinel in the form of its oxide by replacement with said additional metal component.

5,587,136

DRY PROCESS DESULFURIZATION AND DENITRIFICATION PROCESS

Nobuhide Ikegami, and Yutaka Iwanaga, both of Fukuoka-ken, Japan, assignors to Mitsui Mining Co., Ltd., Tokyo, Japan

Filed May 2, 1995, Ser. No. 433,927

Claims priority, application Japan, May 10, 1994, 6-119655
Int. Cl.⁶ C10B 21/00

U.S. Cl. 423-239.1

8 Claims

1. A process for the desulfurization and denitrification by dry process comprising treating a waste gas containing SO_x and NO_x and catalyst-poisoning materials in an apparatus for mainly effecting desulfurization and then in an apparatus for mainly effecting denitrification, characterized by passing the waste gas through a desulfurization apparatus of a moving bed, in which a carbonaceous adsorbent is moved downward at a temperature of 100° to 200° C., adding ammonia to the waste gas at a temperature of 100° to 200° C., leaving the desulfurization apparatus, and then passing the waste gas through the low temperature denitrification apparatus, in which a catalyst of TiO₂-V₂O₅ comprising vanadium oxide supported on titanium oxide of anatase, having a specific surface area of 100 to 250 m²/g and micropores of 1.5 to 2.5 nm in pore diameter and 7.5 to 8.5 nm in pore diameter respectively in an amount of at least 0.05 cc/g, is filled, at a temperature of 100° to 200° C., thus effecting the denitrification.

5,587,137


EXHAUST GAS CONVERSION METHOD USING THERMALLY STABLE ZEOLITES

Srinivas H. Swaroop, and Raja R. Wusirika, both of Painted Post, N.Y., assignors to Corning Incorporated, Corning, N.Y. Division of Ser. No. 183,472, Jan. 18, 1994, Pat. No. 5,447,694. This application Jun. 5, 1995, Ser. No. 464,109

Int. Cl.⁶ B01J 8/02

U.S. Cl. 423-239.2

9 Claims



1. A method for removing at least one of the pollutants NO_x, CO, and hydrocarbons from an exhaust gas, said method comprising contacting said exhaust gas in undiverted flow first with a zeolite suitable for adsorption of hydrocarbons, and thereafter with a main catalyst suitable for conversion of NO_x, CO, and hydrocarbons to innocuous products, at a temperature ranging from cold-start temperatures to light-off temperatures, wherein when the temperature is in the cold-start range and the exhaust gas contains hydrocarbons, the zeolite adsorbs the hydrocarbons, and when the temperature is in the light-off range, and the exhaust gas contains NO_x, CO, and hydrocarbons, the main catalyst converts the NO_x, CO, and the hydrocarbons to innocuous products, said zeolite being selected from the group consisting of Y zeolite, Beta, ZSM-5, mordenite, and combinations thereof, and having a SiO₂/Al₂O₃ mole ratio of no greater than about 200, said zeolite being ion exchanged with chromium.

5,587,138

PROCESS FOR PREVENTING THE FORMATION OF HARMFUL ORGANIC SUBSTANCES AND STEAM GENERATOR FOR CARRYING OUT THE PROCESS

Michael Bobik; Ralf L. Lindbauer, both of Graz, and Alfred Glasner, Passail, all of Austria, assignors to Austrian Energy & Environment, SGP/Wagner-Biro GmbH, Vienna, Austria. Continuation-in-part of Ser. No. 87,722, Jul. 7, 1993, abandoned. This application Apr. 13, 1995, Ser. No. 422,549

Claims priority, application Austria, Dec. 18, 1991, 2504/91 Int. Cl.⁶ C01B 17/00

U.S. Cl. 423-242.1

17 Claims

1. A process for minimizing the formation of dioxins and furan from organic building blocks during combustion of composite combustible materials in a combustion chamber during which combustion gas containing SO₂ is formed and, wherein the combustion gas is passed in a flow from the combustion chamber to a dedusting device, cooled and purified, comprising increasing the SO₂ content in the combustion gas flow to a value in the range of between about 75 mg/m³ to about 500 mg/m³ during the period that the combustion gas flow is from about 300° to about 800° C. until at least surface regions of particles of metal dusts contained in the combustion gas are converted to sulfates to thereby minimize formation of dioxins and furan.

5,587,139

HIGH DENSITY NICKEL HYDROXIDE CONTAINING BORON AND A METHOD FOR PREPARING IT

Dong-Yup Shin, Kyunki-Do, Rep. of Korea, assignor to Hyundai Motor Company, Seoul, Rep. of Korea Division of Ser. No. 390,958, Feb. 21, 1995. This application Jun. 7, 1995, Ser. No. 487,440

Claims priority, application Rep. of Korea, May 20, 1994, 94-11024

Int. Cl.⁶ C01B 35/00; C01G 53/00

U.S. Cl. 423-275

21 Claims

1. A method for preparing a boron containing nickel hydroxide powder, said method comprising the steps of: mixing a nickel sulfate solution containing a boron compound in a concentration in a range of from 0.05 to 0.5 mol/L with ammonium hydroxide in a premixing vessel to form a nickel ammonium complex; supplying said nickel ammonium complex to a reactor; supplying a solution of sodium hydroxide to said reactor to form a mixture; and holding said mixture in said reactor for a time sufficient to form said boron containing nickel hydroxide.

5,587,140

PROCESS FOR PRODUCING POWDERS OF TRANSITION METAL BORIDE

Shinji Fujiwara; Hiroshi Tabuchi, and Akihiko Takahashi, all of Ibaraki, Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed May 16, 1995, Ser. No. 442,503

Claims priority, application Japan, May 18, 1994, 6-103734 Int. Cl.⁶ C01B 35/04

U.S. Cl. 423-297

6 Claims

1. A process of producing a powder of a transition-metal boride, which comprises: contacting a molten phase salt with a molten phase aluminum containing a transition-metal element selected from the group consisting of Groups IV and V of the Periodic Table, said molten phase salt comprising a fluoride and at least one boron compound selected from the group consisting of boron oxide, boric acid and borax, and said contact being carried out at an atomic ratio of boron compound expressed as elemental boron to the transition-metal element of from 0.5 to 4.0 at a temperature which is not lower than 660° C. and which is less than 1000° C. to produce transition-metal boride particles in the molten phase aluminum; and recovering the transition-metal boride particles from the molten phase aluminum.

5,587,141

METHOD AND DEVICE FOR THE PRODUCTION OF FULLERENES

Satoshi Ohshima, Abiko; Motoo Yumura, Tsukuba; Yasunori Kuriki, Tsukuba; Kunio Uchida, Tsukuba, and Fumikazu Ikazaki, Tsukuba, all of Japan, assignors to Director-General of Industrial Science and Technology, Japan

Filed Feb. 13, 1995, Ser. No. 387,253

Claims priority, application Japan, Feb. 25, 1994, 6-053290 Int. Cl.⁶ C01B 31/02; B01J 19/08

U.S. Cl. 423-445 B

13 Claims

1. A method of producing fullerenes, comprising the steps of: (a) disposing an axially extending carbonaceous anode having a tip end surface and a cathode having a cathode surface in an airtight chamber such that said tip end surface faces on said cathode surface; (b) introducing a first supply of inert gas into said airtight chamber to establish an atmosphere of a first inert gas therein; (c) impressing a direct current voltage between said anode and said cathode while maintaining said chamber in the atmo-

5,587,144

DIAZINE CHELATING AGENTS FOR DIAGNOSTIC IMAGING

Torsten Almén, Malmö, Sweden; Arne Berg, Blommenholm, Norway; Harald Dugstad, Norway; Jo Klaveness, both of Oslo, Norway; Klaus D. Krautwurst, Stabekk, Norway, and Pål Rongved, Hellvik, Norway, assignors to Nycomed Imaging AS, Oslo, Norway

Division of Ser. No. 235,882, May 2, 1994, Pat. No. 5,439,668, which is a division of Ser. No. 690,975, Jul. 24, 1991, Pat. No. 5,348,954. This application Jun. 6, 1995, Ser. No. 467,287


Claims priority, application United Kingdom, Jan. 13, 1989, 8900719

Int. Cl.⁶ A61B 5/055

U.S. Cl. 424-9.361

20 Claims

1. A chelate complex of a compound of formula I




wherein X represents a group of formula NR³;

each R¹ which may be the same or different represents a hydrogen atom, a group of formula OR³ or NR³R³ or a C₁₋₈alkyl or (C₁₋₈alkoxy)-C₁₋₈alkyl group optionally substituted by a hydroxyl group or by a group of formula NR³R³ or CONR³R³;

each R² which may be the same or different represents a hydrogen atom or a C₁₋₈alkyl or C₁₋₈alkoxy group optionally mono- or poly-substituted by hydroxyl or C₁₋₈alkoxy groups; each R³ which may be the same or different represents a hydrogen atom, an optionally mono- or poly-hydroxylated C₁₋₈alkyl group or a group of formula CH₂Y;

Y represents a group of formula COZ, CON(OH)R⁴, POZ, or SO₂Z;

Z represents a group of formula OR⁴, NR⁴R⁴, or



where each R¹¹ which may be the same or different is a hydrogen atom, a hydroxyl group or an optionally hydroxylated C₁₋₈alkyl group,

s is 0, 1 or 2, and

W is a group CHR¹¹ or a group NR¹¹; and

each R⁴ which may be the same or different represents a hydrogen atom or an optionally mono- or poly-hydroxylated C₁₋₈alkyl, (C₁₋₈alkoxy)-C₁₋₈alkyl or poly-(C₁₋₈alkoxy)-C₁₋₈alkyl group;

with the proviso that where s is 0 then in the resultant 5 membered heterocyclic ring W is a CHR¹¹ group.

5,587,145

AQUEOUS AEROSOL LACQUER FOR SETTING HAIR Bertrand Lion, Livry-Gargan; Jean Mondet, Drancy, and Christine Dupuis, Paris, all of France, assignors to L'Oréal, Paris, France


Filed Feb. 14, 1994, Ser. No. 195,145

Claims priority, application France, Feb. 16, 1993, 93 01724 Int. Cl.⁶ A61K 7/11; 9/12

U.S. Cl. 424-45

15 Claims

1. A water based aerosol hair lacquer containing in an aerosol container a homogeneous solution consisting essentially of:



sphere of the first inert gas to cause an arc discharge to occur therebetween, so that soot containing fullerenes is accumulated in said chamber;

(d) then, after termination of step (c), blowing a second supply of inert gas on said accumulated soot to fluidize same;

(e) discharging said fluidized soot from said chamber; and

(f) introducing said discharged soot into a liquid containing a solvent capable of dissolving fullerenes, to thereby recover the fullerenes.

5,587,142

METHOD OF DISSOLVING METAL OXIDES WITH DI-OR POLYPHOSPHONIC ACID AND A REDUNDANT

Earl P. Horwitz, and Renato Chiarizia, both of Argonne, Ill., assignors to Arch Development Corporation, Chicago, Ill.

Continuation of Ser. No. 111,782, Aug. 25, 1993, abandoned, which is a continuation of Ser. No. 766,841, Sep. 27, 1991, abandoned, which is a division of Ser. No. 516,436, Apr. 30, 1990, Pat. No. 5,078,894. This application Jun. 6, 1995, Ser.

No. 480,049

Int. Cl.⁶ B01F 1/00; C01G 56/00; 37/00; C01F 17/00

U.S. Cl. 423-658.5

22 Claims

1. A method of dissolving a metal oxide comprising contacting the metal oxide with a composition comprising a di- or polyphosphonic acid and sodium formaldehyde sulfoxylate, each being present in sufficient amount to provide a synergistic effect with respect to the dissolution of the metal oxide, the composition optionally containing corrosion inhibitors and pH adjusting agents.

5,587,143

BUTYLENE OXIDE-ETHYLENE OXIDE BLOCK COPOLYMER SURFACTANTS AS STABILIZER COATINGS FOR NANOPARTICLE COMPOSITIONS Sul-Ming Wong, Collegeville, Pa., assignor to NanoSystems L.L.C., Collegeville, Pa.


Filed Jun. 28, 1994, Ser. No. 267,082

Int. Cl.⁶ A61K 49/00; 49/04

U.S. Cl. 424-9.1

8 Claims

1. A composition comprised of nanoparticles containing a therapeutic or diagnostic agent having a nonionic polymeric surfactant as a surface modifier adsorbed on the surface thereof, wherein said surfactant is a triblock copolymer having the structure



wherein


R is H,

x and y are 15-200, and

z is 5-200; and


said polymer has a molecular weight of 3,000-5,000 and comprises at least 60% by weight of ethylene oxide units.

- (a) 63 to 88% by weight of a carrier consisting of water,
 (b) 10 to 35% by weight of a propellant consisting of dimethyl ether, and
 (c) 2 to 25% by weight relative to the total weight of the lacquer of a water-soluble film-forming copolymer, said copolymer comprising repeating units resulting from the polymerization of:
 (i) 30 to 90% by weight of an unsaturated sulphonic acid having the formula:



in which:

- R_1 represents a hydrogen atom or $-\text{CH}_3$,
 X represents $-\text{O}-$ or $-\text{NH}-$, and
 Y represents a linear or branched alkylene chain having from 1 to 6 carbon atoms, and
 (ii) 10 to 70% by weight of N-monoalkylacrylamide or methacrylamide having the formula:



in which:

- R_2 represents a hydrogen atom or $-\text{CH}_3$ and
 R_3 represents a linear or branched radical having from 3 to 10 carbon atoms, the sulphonic acid functions of said copolymer being neutralized in a proportion from 40 to 70% with triethanolamine.

5,587,146

METHOD OF PREVENTING DEPOSITION OF TARTAR ON TEETH

Louis L. Wood, Rockville, and Gary J. Calton, Elkridge, Md., assignors to Bayer AG, Leverkusen, Germany
 Division of Ser. No. 994,922, Dec. 22, 1992, Pat. No. 5,408,028. This application Apr. 13, 1995, Ser. No. 421,482
 Int. Cl.⁶ A61K 7/16; 7/22

U.S. Cl. 424—49

5 Claims

1. A method of preventing deposition of tartar on teeth comprising treating said teeth with an effective amount of a copolymer of polyaspartic acid with a polycarboxylic acid.

5,587,147

AQUEOUS ZINC-POLYAMIDE COMPLEX SOLUTION

Todd W. Domke, Newtown, Pa., and Wolfgang R. Bergmann, Princeton, N.J., assignors to Church & Dwight Co., Inc., Princeton, N.J.

Filed Jun. 30, 1994, Ser. No. 269,155


The portion of the term of this patent subsequent to Jun. 30, 2014, has been disclaimed.

Int. Cl.⁶ A61K 7/16; 7/22

U.S. Cl. 424—54

6 Claims

1. A single-phase aqueous solution comprising (1) about 0.1–12 weight percent of water-insoluble zinc compound ingredient selected from the group consisting of zinc oxide, zinc silicate, zinc carbonate, zinc stannate, zinc tetrafluoroborate, zinc citrate, zinc benzoate and zinc hexafluorosilicate; and (2) about 0.1–10 weight percent of water-soluble zinc-complexing polyalkylenamine polyamine ingredient; wherein the aqueous solution has a pH in the range between about 6–10.



5,587,148

VISIBLY TRANSPARENT UV SUNBLOCK AGENTS AND METHODS OF MAKING SAME

Kim Mitchell, Granada Hills, Calif., and Mark Mitchnick, Wainscott, N.Y., assignors to SunSmart, Inc., Wainscott, N.Y.
 Continuation of Ser. No. 704,250, May 22, 1991, abandoned, which is a continuation-in-part of Ser. No. 651,696, Feb. 5, 1991, Pat. No. 5,223,250. This application Aug. 4, 1993, Ser. No. 101,661

Int. Cl.⁶ A61K 7/42

9 Claims

1. A topical sunblock formulation for shielding skin from ultra violet radiation, said formulation comprising:
 a substantially colorless dermatologically acceptable liquid carrier;
 micronized particles of zinc oxide, said particles having an average particle diameter of less than about 0.2 microns and containing

lead	<20 ppm;
arsenic	<3 ppm;
cadmium	<15 ppm, and
mercury	<1 ppm

said particles being substantially uniformly dispersed in said substantially colorless dermatologically acceptable liquid carrier to form a substantially visibly transparent topical sunblock formulation, said particles being dispersed in said carrier in an amount effective to shield skin over which said substantially visibly transparent topical sunblock formulation is applied from hazardous effects of UV-A and UV-B radiation.

5,587,149

TOPICAL APPLICATION EMULSIONS

Louis Punto, Clearwater; Chim Potini, Largo; Pilar Duque, and Eva Gould, both of Tampa, all of Fla., assignors to R.P. Scherer Corporation, Troy, Mich.

Filed Feb. 6, 1995, Ser. No. 383,782

Int. Cl.⁶ A61K 7/42

8 Claims

- U.S. Cl. 424—59
 1. A soft gelatin capsule comprising a shell and an emulsion for carrying vitamin C comprising:
 first and second emulsion phases, and a dispersing agent;
 said first emulsion phase including, as a solvent, polyethylene glycol, and vitamin C dissolved into said polyethylene glycol solvent; and
 said second emulsion phase comprising a silicone-derivative silicone oil fluid.

5,587,150

PHOTOSTABLE COSMETIC SCREENING COMPOSITION CONTAINING A UV-A SCREENING AGENT AND AN ALKYL β , β -DIPHENYLACRYLATE OR α -CYANO- β , β -DIPHENYLACRYLATE

André Deffandre, Orry-la-Ville; Michel Dubois, Coulommiers; Serge Forestier, Claye-Souilly, and Hervé Richard, Paris, all of France, assignors to L'Oréal, Paris, France

Continuation of Ser. No. 937,886, Oct. 14, 1992, abandoned.


This application Jun. 5, 1995, Ser. No. 461,842

Claims priority, application France, Feb. 14, 1990, 90 01761
 Int. Cl.⁶ A61K 7/42; 7/40

U.S. Cl. 424—59

33 Claims

1. A photostable cosmetic screening composition for protection of the human epidermis against ultraviolet rays of wavelengths between 280 and 380 nm, which comprises, in a cosmetically acceptable vehicle containing at least one fatty phase, 1 to 5% by weight of a dibenzoylmethane derivative and at least 1% by weight of an alkyl β , β -diphenylacrylate or a α -cyano- β , β -diphenylacrylate of formula:



in which

- R_1 and R'_1 , which may be identical or different, represent a hydrogen atom, a straight- or branched-chain C_1 – C_4 alkoxy radical or a straight- or branched-chain C_1 – C_4 alkyl radical, R_1 and R'_1 being in the para or meta position; R_2 represents a straight- or branched-chain C_1 – C_{12} alkyl radical; and R_3 represents hydrogen atom or a $-\text{CN}$ radical, the mole ratio of the compound of formula (1) to the dibenzoylmethane derivative being not less than 0.8.

5,587,151

PHOTOPROTECTIVE/COSMETIC COMPOSITIONS COMPRISING OXANILIDO-SUBSTITUTED POLYORGANOSILOXANES/POLYORGANOSILANES

Hervé Richard, Villepinte; Madeleine Leduc, Paris, and Alain LaGrange, Couvray, all of France, assignors to L'Oréal, Paris, France

Filed Nov. 17, 1995, Ser. No. 560,489



Claims priority, application France, Nov. 17, 1994, 94 13770

Int. Cl.⁶ A61K 7/42; C08G 77/26

U.S. Cl. 424—59


26 Claims

1. An oxanilido-substituted polyorganosiloxane/polyorganosilane compound having one of the formulae (1) to (3):




- in which the radicals R , which may be identical or different, are each a C_1 – C_{10} alkyl, phenyl or 3,3,3-trifluoropropyl radical, at least 80% by number of the radicals R being methyl radicals; the radicals B , which may be identical or different, are each a radical R or a radical A as defined below; the radicals R' , which may be

identical or different, are each a C_1 – C_8 alkyl radical or a phenyl radical; r is an integer ranging from 0 to 50, inclusive, and s is an integer equal to 0 or 1, with the proviso that, if s is zero, then at least one of the two radicals B is a radical A ; t is an integer ranging from 2 to 10, inclusive; and the radical A is a monovalent radical bonded directly to a silicon atom and which has the following formula (4):



wherein X is a divalent radical $-\text{Y}-$ having the following formula (5):



- (1) in which R^2 is a hydrogen atom or a C_1 – C_4 alkyl radical; p is an integer ranging from 0 to 10, inclusive; m is 0 or 1; the $-\text{CH}_2-$ endgroup is directly bonded to a silicon atom; Z is a hydrogen atom or a divalent radical $-\text{Y}-$; q is an integer ranging from 0 to 3 inclusive; and the radicals R' , which may be identical or different, are each a C_1 – C_8 alkyl radical or C_1 – C_8 alkoxy radical, with the proviso that, when the radicals R' are alkoxy radicals, two adjacent radicals R' ($q \geq 2$) may together form an alkylidenedioxy group in which the alkylidene moiety contains 1 or 2 carbon atoms.

5,587,152

CLEAR SOLID TOPICAL DEODORANT COMPOSITIONS COMPRISING A WATER-INSOLUBLE ESTER OF A WATER-SOLUBLE ACID

Leonard Mackles, 311 E. 23rd St., New York, N.Y. 10010, and Leonard Chavkin, R.R. 1, Box 90, Bloomsbury, N.J. 08804
 Continuation-in-part of Ser. No. 357,107, Dec. 15, 1994, abandoned. This application May 19, 1995, Ser. No. 444,443

Int. Cl.⁶ A61K 7/32

U.S. Cl. 424—65

10 Claims

1. A clear solid topical deodorant composition comprising:
 50 to 98% by weight of at least one water-insoluble ester of a water-soluble acid having solubility in water of greater than 50% w/w at 20° C.,
 2 to 6% by weight of dibenzylidene sorbitol, and
 0 to 44% by weight of one or more optional ingredients, said composition being substantially free of water and of water-miscible solvents which are liquid at ambient temperature.

5,587,153

CLEAR, GELLED ALUMINUM AND ZIRCONIUM SALT CONTAINING ANTIPERSPIRANT FORMULATION

Philip P. Angelone, Jr., Wilmington; Nancy M. Karassik, Concord, and William R. Grace, Reading, all of Mass., assignors to The Gillette Company, Boston, Mass.

Continuation of Ser. No. 592,570, Oct. 4, 1990, abandoned.

This application Mar. 2, 1994, Ser. No. 204,898

Int. Cl.⁶ A61K 7/34; 7/38

U.S. Cl. 424—66

33 Claims

1. An optically clear deodorant or antiperspirant product, comprising: a water-in-oil emulsion, said emulsion being a gel having a viscosity between about 50,000 cps and about 200,000 cps at 21° C. and a refractive index (n_D) in the range of 1.3975–1.4025, said emulsion having a water phase that makes up between seventy-five to ninety percent of said emulsion, with a deodorant or antiperspirant effective salt of aluminum and zirconium dissolved in said water phase and an oil phase.


5,587,154

SHAMPOO COMPOSITIONS AND SUSPENDING AGENT THEREFOR

Teresa J. Dowell, Downers Grove; Gerald P. Newell, Hoffman Estates, and Eugene Zeffren, Lincolnshire, all of Ill., assignors to Helene Curtis, Inc., Chicago, Ill.
Division of Ser. No. 969,382, Oct. 30, 1992, Pat. No. 5,393,519, which is a continuation of Ser. No. 859,128, Mar. 27, 1992, abandoned. This application Sep. 6, 1994, Ser. No. 301,192
Int. Cl.⁶ A61K 7/06; C11D 3/48; 9/50

U.S. Cl. 424—70.11 20 Claims

1. An antidandruff shampoo composition comprising:
(a) about 3% to about 40% by weight of an anionic cleansing surfactant;
(b) about 0.1% to about 10% by weight of a water-insoluble antidandruff agent;
(c) a suspending agent comprising:
(i) from about 1% to about 10% by weight of the composition of an amine having the general structural formula



wherein R_1 is an alkyl group including at least 16 carbon atoms; R_2 is selected from the group consisting of hydrogen, an alkyl group having one to about 22 carbon atoms, benzyl and phenyl; and R_3 is selected from the group consisting of hydrogen, methyl, benzyl, and phenyl, wherein said amine has a water solubility of 0 to 0.5 grams per 100 milliliters of water, and wherein said amine is a solid compound at room temperature; and

- (ii) a sufficient amount of an acid such that essentially no solid particles of the amine are present in the composition, said acid selected from the group consisting of an inorganic mineral acid, an aliphatic carboxylic acid including up to about 22 carbon atoms; an aromatic carboxylic acid, and combinations thereof; and
(d) an aqueous carrier.

5,587,155

HAIR COSMETIC COMPOSITION

Ryuji Ochiai, Ichikawa; Kouzi Morita, Mitaka, and Kazuyuki Yahagi, Tokyo, all of Japan, assignors to Kao Corporation, Tokyo, Japan
PCT No. PCT/JP93/00980, § 371 Date Jan. 18, 1995, § 102(e) Date Jan. 18, 1995, PCT Pub. No. WO94/02111, PCT Pub. Date Feb. 3, 1994


PCT Filed Jul. 14, 1993, Ser. No. 367,228

Claims priority, application Japan, Jul. 21, 1992, 4-194122; Feb. 9, 1993, 5-021456

Int. Cl.⁶ A61K 7/06; 7/00

U.S. Cl. 424—70.28 5 Claims

1. A hair cosmetic composition comprising:
(a) at least one compound selected from the group consisting of fatty acids containing a linear or branched alkyl or alkenyl group having 18–25 carbon atoms, salts of fatty acids containing a linear or branched alkyl or alkenyl group having 18–25 carbons and fatty acid esters formed from fatty acids containing a linear or branched alkyl or alkenyl group having 18–25 carbon atoms and a polyhydric alcohol;
(b) at least one aromatic alcohol of formula (I):



wherein

R^1 is a hydrogen atom, a methyl group or methoxy group;
 Y is a single bond or a linear or branched alkylene or alkenylene group having 1–3 carbon atoms;
 Z is a hydrogen atom or a hydroxyl group; and

p and q stand individually for a number of 0–5; and
(c) at least one quaternary ammonium salt cationic surfactant, wherein the components (a), (b) and (c) are contained in proportions of 0.5–10 wt. %, 1–30 wt. % and 0.2–10 wt. %, respectively, based on the weight of the hair cosmetic composition.

5,587,156

SHAVING COMPOSITIONS CONTAINING PARTICULATE ADDITIVES

Mark S. Wdowik, Ft. Collins, Colo., assignor to Critical Dimension, Incorporated, Ft. Collins, Colo.

Filed Apr. 18, 1996, Ser. No. 634,602

Int. Cl.⁶ A61K 7/09; A01N 37/00

U.S. Cl. 424—73 21 Claims

1. Shaving compositions for use in the personal shaving process with a razor blade assembly, which shaving compositions provide physical, microscopic support for the blade of such a razor blade assembly during the personal shaving process including:

- a mixture of at least one wetting agent, at least one cleansing agent, at least one lather producing composition, and at least one emollient; and further including
at least one solid, insoluble particulate additive in a well dispersed suspension throughout said shaving composition, said solid additives present in an effective amount to produce physical support for the blade of a razor blade assembly during the personal shaving process.

5,587,157

STABILIZATION OF BIOWASTES

James P. Cox, and Robert W. Duffy Cox, both of 246 E. Bartlett Rd., Lynden, Wash. 98264

Continuation-in-part of Ser. No. 287,183, Aug. 8, 1994, abandoned, which is a continuation of Ser. No. 886,417, May 19, 1992, Pat. No. 5,352,444. This application Jun. 7, 1995, Ser. No. 474,329

Int. Cl.⁶ A61L 11/00

U.S. Cl. 424—76.5 54 Claims

1. A biowaste treatment agent consisting essentially of a metal component and an aldehyde, said treatment agent lacking a surfactant;

- said metal component comprising from about 0.5% to about 85.0% by weight of the treatment agent; and
said aldehyde comprising about 0.1% to about 80.0% by weight of the treatment agent.

5,587,158

BIOLOGICAL CONTROL FOR WEED TREES

Ronald Wall; Raghbir Prasad, both of Victoria, and Elaine Sela, Shawnigan Lake, all of Canada, assignors to Minister of Natural Resources, Canadian Forest Service, Hull, Canada

Filed Mar. 27, 1995, Ser. No. 411,334

Int. Cl.⁶ A01N 25/00; 63/00; C12N 1/00; 1/14

U.S. Cl. 424—93.5 3 Claims

1. A refrigeration storable preparation of *Chondrostereum purpureum* fungus for the control of weed trees selected from the group consisting of aspens, beech, birches, maples, pin cherry and poplars comprising:

- (a) a dry culture medium consisting of 90–95% by weight finely powdered inert material, approximately 3–5% by weight digestible carbohydrates, approximately 0.1–1.0% by weight of an organic nitrogen source capable of providing approximately 0.01–0.10% by weight available nitrogen; and 0.5–1% by weight vitamin;
(b) water in an amount to maintain a moisture level of 15–25% by weight based on the dry weight of the culture medium for

maintaining living mycelium of the fungus without promoting excessive growth or free moisture; and
(c) viable mycelium of *Chondrostereum purpureum* in an amount of 1–5% by weight based on the dry weight of the culture medium.

5,587,159

HUMAN TISSUE PLASMINOGEN ACTIVATOR

David V. Goeddel, Hillsborough; William J. Kohr, San Mateo; Diane Pennica, Foster City, and Gordon A. Vehar, San Carlos, all of Calif., assignors to Genentech, Inc., South San Francisco, Calif.

Continuation of Ser. No. 109,698, Aug. 20, 1993, abandoned, which is a continuation of Ser. No. 911,021, Jul. 9, 1992, abandoned, which is a continuation of Ser. No. 489,855, Mar. 2, 1990, Pat. No. 5,185,259, which is a continuation of Ser. No. 12,694, Feb. 9, 1987, abandoned, which is a division of Ser. No. 483,052, Apr. 7, 1983, Pat. No. 4,766,075, which is a continuation-in-part of Ser. No. 398,003, Jul. 14, 1982, abandoned, and Ser. No. 374,860, May 5, 1982, abandoned. This application Jun. 21, 1994, Ser. No. 264,134
Int. Cl.⁶ A61K 38/49; C12N 9/64; 15/15; 15/70

U.S. Cl. 424—94.64 4 Claims

1. Human tissue plasminogen activator as produced by recombinant expression of DNA encoding said tissue plasminogen activator in transformed *E. coli*.

5,587,160

Patent Not Issued For This Number

5,587,161

PRODRUGS FOR ANTIBODY DIRECTED ENZYME PRODRUG THERAPY

Philip J. Burke, Charlton; Robert I. Dowell, Congleton, both of United Kingdom; Anthony B. Mauger, Kensington, Md., and Caroline J. Springer, London, United Kingdom, assignors to Zeneca Limited, and Cancer Research Campaign Technology Limited, both of London, England

Division of Ser. No. 94,952, Jul. 22, 1993, Pat. No. 5,405,990.

This application Dec. 21, 1994, Ser. No. 361,424


Claims priority, application United Kingdom, Jul. 23, 1992, 9215636; May 26, 1993, 9310884

Int. Cl.⁶ A61K 39/395; C07K 16/00; C07C 261/00; C07F 9/02
U.S. Cl. 424—178.1 21 Claims

1. A two component system, each component for use in association with the other, which comprises:

- (i) a first component that is an antibody or fragment thereof capable of binding a given antigen, the antibody or fragment thereof being conjugated to a carboxypeptidase G enzyme capable of converting a compound of Formula I or physiologically acceptable salt thereof into a cytotoxic drug; and
(ii) a second component that is a compound of Formula I or a physiologically acceptable salt thereof convertible under the influence of the carboxypeptidase G enzyme to the cytotoxic drug.

said compound of Formula I having the structure:



wherein

R^1 and R^2 each independently represents chlorine, bromine, iodine, OSO_2Me , or $\text{OSO}_2\text{phenyl}$ (wherein phenyl is option-

ally substituted with 1, 2, 3, 4 or 5 substituents independently selected from $\text{C}_{1-4}\text{alkyl}$, halogen, $-\text{CN}$ and $-\text{NO}_2$);

R^{1a} and R^{1b} each independently represents hydrogen, $\text{C}_{1-4}\text{alkyl}$ or $\text{C}_{1-4}\text{haloalkyl}$;

R^3 and R^4 each independently represents hydrogen, $\text{C}_{1-4}\text{alkyl}$ or $\text{C}_{1-4}\text{haloalkyl}$;

R^{5a} , R^{5b} , R^{5c} and R^{5d} each independently represents hydrogen, $\text{C}_{1-4}\text{alkyl}$ optionally containing one double bond or one triple bond, $\text{C}_{1-4}\text{alkoxy}$, halogen, cyano, $-\text{NH}_2$, $-\text{CONR}^7\text{R}^8$ (wherein R^7 and R^8 are as defined below), $-\text{NH}(\text{C}_{1-4}\text{alkyl})$, $-\text{N}(\text{C}_{1-4}\text{alkyl})_2$ and $\text{C}_{2-3}\text{alkanoyl}$; or R^{5a} and R^{5b} together represent

a) C4 alkylene optionally having one double bond;

b) C3 alkylene; or

c) $-\text{CH}=\text{CH}-\text{CH}=\text{CH}-$, $-\text{CH}=\text{CH}-\text{CH}_2-$ or $-\text{CH}_2-\text{CH}=\text{CH}-$ each optionally substituted with 1, 2, 3 or 4 substituents said substituents each independently selected from the group consisting of $\text{C}_{1-4}\text{alkyl}$, $\text{C}_{1-4}\text{alkoxy}$, halogen, cyano, nitro, $\text{C}_{2-3}\text{alkanoyl}$ and $-\text{CONR}^7\text{R}^8$ (wherein R^7 and R^8 are as defined below);

X represents O or NH;

Y represents O;

Z represents $-\text{V}-\text{W}$ where V is $-\text{CH}_2-\text{T}-$ in which T is $-\text{CH}_2-$, $-\text{O}-$, $-\text{S}-$, $-(\text{SO})-$, or $-(\text{SO}_2)-$ (provided that when V has sulphur or oxygen as its second atom, W is other than $-\text{COOH}$) and said group V optionally further carrying one or two substituents Q^1 and/or Q^2 on carbon; wherein Q^1 and Q^2 each independently represents $\text{C}_{1-4}\text{alkyl}$ or halogen, or, when Q^1 and Q^2 are bonded to adjacent carbon atoms, Q^1 and Q^2 together may additionally represent a C_3-C_4 alkylene radical optionally substituted with 1, 2, 3 or 4 substituents independently selected from the group consisting of $\text{C}_{1-4}\text{alkyl}$ and halogen; and

W represents

(1) COOH ,

(2) $-(\text{C}=\text{O})-\text{O}-\text{R}^6$ wherein R^6 represents $\text{C}_{1-4}\text{alkyl}$, $\text{C}_{3-6}\text{cycloalkyl}$ or aryl (as defined in 3 below) group;

(3) $-(\text{C}=\text{O})-\text{NR}^7\text{R}^8$ wherein R^7 and R^8 each independently represent hydrogen or a $\text{C}_{1-4}\text{alkyl}$, $\text{C}_{3-6}\text{cycloalkyl}$, aryl, heteroaryl linked to N via carbon or $\text{C}_{7-9}\text{paralkyl}$ group wherein aryl is phenyl; heteroaryl is a 5 or 6 membered ring containing 1 to 3 heteroatoms selected from the group consisting of nitrogen and sulphur; the aryl moiety per se, the heteroaryl moiety and the aryl moiety of the aralkyl group may be substituted on carbon with 1–4 substituents selected from the group consisting of $-\text{COOH}$, $-\text{OH}$, $-\text{NH}_2$, $-\text{CH}_2-\text{NH}_2$, $-(\text{CH}_2)_3-\text{COOH}$, tetrazol-5-yl and $-\text{SO}_3\text{H}$ and the alkyl moiety may optionally carry a methyl group;

(4) $-\text{SO}_2\text{NHR}^9$ wherein R^9 is as defined for R^7 but may additionally represent $-\text{CF}_3$, $-\text{CH}_2\text{CF}_3$ or aryl as defined above;

(5) SO_3R^{10} in which R^{10} represents H, $\text{C}_{1-4}\text{alkyl}$ or $\text{C}_{3-6}\text{cycloalkyl}$;

(6) $\text{PO}_3\text{R}^{10}\text{R}^{11}$ (wherein the R^{10} radicals, which may be the same or different, are as herein defined)

(7) a tetrazol-5-yl group

(8) $-\text{CONH}-\text{SO}_2\text{R}^{11}$ in which R^{11} represents


(a) $\text{C}_{3-7}\text{cycloalkyl}$;

(b) $\text{C}_{1-6}\text{alkyl}$ optionally substituted with substituents selected from the group consisting of aryl as defined below, $\text{C}_{1-4}\text{alkyl}$, CF_3 or halogen; and

(c) perfluoro- $\text{C}_{1-4}\text{alkyl}$; wherein aryl is phenyl or phenyl having 1–5 substituents wherein the substituents are selected from the group consisting of halogen, $-\text{NO}_2$, $-\text{CF}_3$, $\text{C}_{1-4}\text{alkyl}$, $\text{C}_{1-4}\text{alkoxy}$, $-\text{NH}_2$, $-\text{NHCOCH}_3$, $-\text{CONH}_2$, $-\text{OCH}_2\text{COOH}$, $-\text{NH}(\text{C}_{1-4}\text{alkyl})$, $-\text{N}(\text{C}_{1-4}\text{alkyl})_2$, $-\text{NHCOOC}_{1-4}\text{alkyl}$, $-\text{OH}$, $-\text{COOH}$, $-\text{CN}$ and $-\text{COOC}_{1-4}\text{alkyl}$; and

(9) $-\text{M}-\text{Het}$ wherein M represents S, SO or SO_2 and Het represents a 5 or 6 membered heterocyclic aromatic ring linked to M via a carbon atom of the aromatic ring, said aromatic ring containing 1, 2, 3 or 4 heteroatoms selected from the group consisting of O, N and S said aromatic ring optionally being substituted on carbon atoms of the ring

with the proviso that at least two of the radicals A' to G' and J' represent OH or that the E' radical represents OX', and
(b) a flavonoid having the formula:



in which:

A', C' and D', independently of one another, represent H, OH or OCH₃;

E' represents H, OH or OR', where R' represents the residue of rutinose,

B', F', G' and J', independently of one another, represents H, OH, OCH₃ or —OCH₂—CH₂—OH,

with the proviso that at least two of the radicals A' to G' or J' represent OH, and

(v) mixtures thereof.

5,587,172

PROCESS FOR FORMING QUICKLY DISPERSING COMESTIBLE UNIT AND PRODUCT THEREFROM


Subraman R. Cherukuri, Towner, N.J.; Garry L. Myers; Gerald E. Battist, both of Reston, Va., and Richard C. Fuisz, Great Falls, Va., assignors to Fuisz Technologies Ltd., Chantilly, Va.

Division of Ser. No. 259,258, Jun. 14, 1994, which is a continuation-in-part of Ser. No. 133,669, Oct. 7, 1993, and Ser. No. 119,974, Sep. 10, 1993, Pat. No. 5,518,551. This application May 26, 1995, Ser. No. 452,666

Int. Cl.⁶ A61K 9/20

U.S. Cl. 424—401

23 Claims



1. A comestible unit which disperses quickly in the mouth prepared from the process comprising:

- subjecting to flash-flow processing a feedstock comprising a carbohydrate capable of undergoing flash-flow processing without use of a solution to provide a shearform matrix;
- initiating crystallization of said shearform matrix;
- forming flowable compactible micro-particulates by combining an additive with said shearform matrix; and
- compacting said micro-particulates resulting from step "c," which comprises at least partially crystallized shearform matrix, to form said unit.

(V)

5,587,173


UTILIZATION OF DERIVATIVES OF 2,5 DIHYDROXYPHENYL-CARBOXYLIC ACID AMIDES AND THEIR SALTS IN PREPARATION OF A COSMETIC OR DERMATOLOGICAL COMPOSITION WITH A DEPIGMENTING ACTION

Alex Junino, Livry Gargan; Alain LaGrange, Chatou; Quang L. N'Guyen, Antony, and Marie-Alix Bourboulon, Paris, all of France, assignors to L'Oreal, Paris, France
Division of Ser. No. 913,950, Jul. 17, 1992, Pat. No. 5,449,518.
This application Jun. 5, 1995, Ser. No. 445,105

Claims priority, application France, Jul. 17, 1991, 91 09029
Int. Cl.⁶ A61K 7/42

7 Claims


U.S. Cl. 424—401
1. A method of cosmetic or dermatological treatment of skin comprising applying to skin to be depigmented a composition comprising in a suitable vehicle for topical application to the skin 2,5-dihydroxyphenylcarboxylic acid derivatives having the following formula:



(I)

wherein:

R₁ represents



r' and r'', identical or different, represent a hydrogen atom, a C₁—C₂₀ alkyl radical, a C₂—C₆ hydroxyalkyl radical, or C₃—C₆ polyhydroxyalkyl radical, or r' and r'' taken together, with the nitrogen atom, form a heterocycle selected from the group consisting of morpholino, pyrrolidino, piperidino, piperazino and piperazino substituted by C₁—C₄ alkyl or C₂—C₆ hydroxy-alkyl;

the number of carbon atoms in the —(CH₂)_n—COR₁ chain is less than or equal to 21;

R₂ and R₃, identical or different, represent a hydrogen atom, a linear or branched C₁—C₄ alkyl radical, or a C₁—C₄ alkoxy;

R₄ represents a hydrogen atom or a linear or branched C₁—C₄ alkyl radical; and

n is an integer from 0 to 20, provided that, when R₂ and R₃ represent a hydrogen atom, n is greater than or equal to 2, and salts thereof.

5,587,174

COSMETIC COMPOSITION FOR TREATING SKIN AND HAIR CONTAINING APPLE WAX AND METHODS OF MAKING THEM

Günther Lang, Reinheim; Dieter Hoch, Pfungstadt-Eich; Eugen Konrad, Darmstadt; Wolfram Geibel, Hünfeld; Harald Wendel, Ober-Ramstadt, and Thomas Kripp, Fränkisch-Crumbach, all of Germany, assignors to Wella Aktiengesellschaft, Darmstadt, Germany
Continuation of Ser. No. 122,609, Sep. 30, 1993, abandoned.

This application Feb. 12, 1996, Ser. No. 598,632

Claims priority, application Germany, Feb. 28, 1992, 42 06 154.7

Int. Cl.⁶ A61K 7/00; 7/021; 7/06

3 Claims

U.S. Cl. 424—401

1. Composition for treating skin and hair, said composition consisting of 0.5 to 2 percent by weight of apple wax, 0.1 to 30 percent by weight of at least one surfactant, a solvent selected from

the group consisting of water, ethanol, propanol, isopropanol, glycols and mixtures thereof and at least one additive selected from the group consisting of perfume oils; opacifiers; pearlescing agents; bacterial and fungicidal ingredients; coconut fatty acid diethanolamide; buffer substances; coloring materials; solubilizers; light stabilizers; antioxidants; complexing agents and antidandruff active ingredients.

5,587,175

MEDICAL USES OF IN SITU FORMED GELS

Tacey X. Viegas, Canton; Lorraine E. Reeve, Dexter, and Raymond L. Henry, Grosse Pointe Woods, all of Mich., assignors to MDV Technologies, Inc., Dearborn, Mich.

Division of Ser. No. 785,305, Oct. 30, 1991, Pat. No. 5,318,780.


This application Dec. 28, 1993, Ser. No. 174,101

Int. Cl.⁶ A61K 31/77; 31/725; 31/73; 2/14

U.S. Cl. 424—427

11 Claims

1. A process for forming a protective corneal shield or an ablatable corneal shield or mask in situ comprising administering to the eye of a mammal an aqueous composition capable of being gelled in situ to produce an hyperosmotic, hypoosmotic, or isoosmotic aqueous gel having a controlled pH, said aqueous composition, including at least one film forming polymer; and gelling said film forming polymer in situ to form said protective corneal shield or ablatable corneal shield or mask.



formed by a small container comprising a cup-shaped bottom with a top portion, a cup-shaped cover having a shape matching the shape of said cup-shaped bottom, and a flexible strip for connecting said top portion to said cover, said capsule further comprising a catch for maintaining said cover on said cup-shaped bottom, said catch being comprised of a step at said cup-shaped bottom and a matching step at said cup-shaped cover catching said step of said cup-shaped bottom, wherein by pressing on said cup-shaped bottom said catch is released for opening said capsule, wherein said capsule once open cannot be closed again.

5,587,176

METHODS OF USING HESPERETIN FOR SEBUM CONTROL AND TREATMENT OF ACNE

Raphael Warren, Amberly Village, and Adebola T. Akadiri, Cincinnati, both of Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Continuation of Ser. No. 49,923, Apr. 20, 1993, abandoned.


This application Dec. 21, 1994, Ser. No. 361,906

Int. Cl.⁶ A61K 9/70

U.S. Cl. 424—443

16 Claims

1. A method of treating acne in mammalian skin comprising administering to a mammal susceptible to or having acne a composition consisting of a safe and effective amount of hesperetin having the structure:



or a pharmaceutically-acceptable salt thereof.

5,587,177

MEDICAMENT HAVING A PEDIATRIC PRESENTATION FOR FACILITATING THE INGESTION THEREOF BY A CHILD

Georges S. Grimberg, 123 rue de l'Université, 75007 Paris, France

Filed Jan. 23, 1995, Ser. No. 376,837

Claims priority, application France, Jan. 21, 1994, 94 00639
Int. Cl.⁶ A61K 9/48

U.S. Cl. 424—454

4 Claims

1. The combination of a medicament with a capsule, said combination having a pediatric presentation facilitating ingestion of the medicament by a child, the medicament being an anhydrous powder mixable with food so as to be easily ingested by a child, wherein said capsule contains a unit dose of the medicament and is

5,587,178

PROCESS FOR THE TREATMENT OF ASPARTAME

Hubertus J. M. Slangen, Stein, Netherlands, assignor to Holland Sweetener Company V.o.F., Maastricht, Netherlands

Continuation-in-part of Ser. No. 74,446, Jun. 10, 1993, Pat. No. 5,411,747. This application Dec. 7, 1994, Ser. No. 351,579

Claims priority, application Netherlands, Jun. 11, 1992, 9201029

Int. Cl.⁶ A61K 9/20

U.S. Cl. 424—464

15 Claims

1. A tablet comprising aspartame, obtained by direct compression tableting aspartame particles, wherein at least 94 wt. % of said aspartame particles are in a particle size distribution range of 20 μm to 250 μm.

5,587,179

PHARMACEUTICAL FORMULATION IN THE FORM OF AN EFFERVESCENT AND/OR DISINTEGRATING TABLET OR OF INSTANT GRANULATE, AND PROCESS FOR THEIR PREPARATION

Gerhard Gergely; Thomas Gergely, and Irmgard Gergely, all of Vienna, Austria, assignors to Gerhard Gergely, Austria

PCT No. PCT/EP93/00055, § 371 Date Jul. 13, 1994, § 102(e) Date Jul. 13, 1994, PCT Pub. No. WO93/13760, PCT Pub. Date Jul. 22, 1993

PCT Filed Jan. 12, 1993, Ser. No. 256,503

Claims priority, application European Pat. Off., Jan. 13, 1992, 92100441

Int. Cl.⁶ A61K 9/46

U.S. Cl. 424—466

17 Claims

1. Pharmaceutical formulation in the form of an effervescent or disintegrating tablet or of instant granules, containing at least one active ingredient having an irritating taste and at least one matrix which delays the release of the active ingredient and which contains at least one fatty ester or one wax, characterised in that the matrix is present as an intimate mixture with the active ingredient particles and covers said particles and is applied to a carrier, the formulation releasing at most 65% of the active ingredient in aqueous solution at room temperature within about 2 min but more than 70% of the active ingredient within max. 20 min in 0.1N HCl at 38° C.

5,587,180

PROCESS FOR MAKING A PARTICULATE SUPPORT MATRIX FOR MAKING A RAPIDLY DISSOLVING TABLET

Lloyd V. Allen, Jr., Edmond, and Bingnan Wang, Oklahoma City, both of Okla., assignors to The Board of Regents of the University of Oklahoma, Norman, Okla.
Division of Ser. No. 187,670, Jan. 27, 1994. This application Dec. 8, 1994, Ser. No. 352,336
Int. Cl.⁶ A61K 9/14; 9/10; 47/42

U.S. Cl. 424—499 19 Claims

1. A process for producing a pharmaceutical particulate support matrix, comprising:

providing an aqueous composition comprising:

an aqueous medium;

a support agent comprising a first gelatin component capable of maintaining a net charge, a second gelatin component capable of maintaining a net charge of the same sign as the first gelatin component, and a bulking agent, and wherein the first gelatin component and the second gelatin component together comprise about 2% to 20% by weight of the particulate support matrix and wherein the bulking agent comprises about 60% to 96% by weight of the particulate support matrix, and wherein the second gelatin component has a solubility in aqueous solution greater than that of the first gelatin component and wherein the mass:mass ratio of the first gelatin component to the second gelatin component is from about 1:1/2 to about 1:14; and

a volatilizing agent comprising an alcohol for enhancing the rate of vaporization of the aqueous medium; and introducing the aqueous composition as droplets into a drying chamber heated to a predetermined temperature causing evaporation of the aqueous medium and volatilizing agent from the droplets leaving the support agent in a dried and expanded particulate form comprising the particulate support matrix.

5,587,181


MAGNETIC SUPPORT SYSTEM FOR CABLE INSERTION TUBE

Steve C. Owens, Coweta County; Richard V. Lovvorn, Carroll County, and Albert B. Elder, Haralson County, all of Ga., assignors to Southwire Company, Carrollton, Ga.
Continuation-in-part of Ser. No. 232,883, Apr. 25, 1994, Pat. No. 5,439,363. This application Dec. 30, 1994, Ser. No. 366,703

Int. Cl.⁶ B29C 47/90

U.S. Cl. 425—3

14 Claims



9. Apparatus for positioning a cable in a bore of an extruded polymeric conduit, comprising:

means for extruding the conduit;

a ferromagnetic cable insertion tube cantilevered from said extruding means and adapted to extend upstream of said extruding means and downstream of said extruding means through said bore of the extruded conduit, said cable insertion tube having a first free end at the downstream end thereof and a second free end at the upstream end thereof;

an electrical winding having an upstream end and a downstream end surrounding a portion of said cable insertion tube downstream of said extruding means;

a d.c. power source connected to said winding for generating a magnetic flux in said cable insertion tube downstream of said extruding means to form a first magnetic pole having a first polarity at said downstream free end and a second magnetic pole having a second polarity opposite to the first polarity upstream of said downstream free end; and

a first magnet means having a first magnetic pole with a polarity the same as the first polarity and supported in confronting relationship with said downstream free end of said cable insertion tube, and a second magnet means having a second magnetic pole with a polarity the same as the second polarity and supported in confronting relationship with said cable insertion tube intermediate of said downstream free end and said extruding means in such position for magnetically levitating said tube and preventing the free end thereof from sagging into contact with the polymeric conduit.

5,587,182

APPARATUS FOR THE PRODUCTION OF ENDLESS POLYURETHANE MOLDINGS


Hans-Michael Sulzbach, Königswinter, and Lothar Röhrig, Neunkirchen-Seelscheid, both of Germany, assignors to Maschinenfabrik Hennecke GmbH, Leverkusen, Germany
Filed Feb. 15, 1995, Ser. No. 388,790

Claims priority, application Germany, Feb. 21, 1994, 44 05 427.0

Int. Cl.⁶ B29C 44/20; B01F 15/00

U.S. Cl. 425—4 C

1 Claim



1. An apparatus for the production of endless polyurethane moldings from at least two reaction components comprising:

A) storage containers for each reaction component,

B) a continuously moving mold,

C) at least two alternately operated mixheads, each of said mixheads comprising:

1) an inlet opening,

2) a mixing chamber in which said reaction components are mixed,

3) a first outlet through which a mixture of said reaction components passes from said mixing chamber,

4) a second outlet through which a reaction component passes,

5) a changeover valve which allows reaction component to either

i) enter said inlet opening, enter said mixing chamber and pass through said first outlet, or

ii) enter said inlet opening and pass through said second outlet,

E) a first feed line leading from a storage container to a metering pump,

F) a second feed line leading from a storage container to a conditioning pump,

G) feed lines leading from said metering pump to each of the inlet openings of each of said mixheads,

H) feed lines leading from said conditioning pump to each of the inlet openings of each of said mixheads,

I) feed lines leading from each of said second outlets to a storage container.

5,587,183


MOLD HAVING VENT PASSAGEWAYS TO OBLIVATE TRIMMING OF FLASH

Leslie E. Clark, Maple; Craig A. Hunter, Milton; Robert B. Magee, Caledon East; Gerry Vande Wetering, Georgetown, and Wilfred W. T. Cheng, Oakville, all of Canada, assignors to Woodbridge Foam Corporation, Mississauga, Canada
Division of Ser. No. 220,927, Mar. 31, 1994, Pat. No. 5,482,721, which is a division of Ser. No. 939,704, Sep. 2, 1992, Pat. No. 5,356,580. This application Jun. 7, 1995, Ser. No. 475,048

Int. Cl.⁶ B29C 33/10; 33/40; 44/58

U.S. Cl. 425—4 R

23 Claims



1. A mold for producing foamed articles having a plurality of ribbon-shaped appendages, the mold comprising:

an upper mold and a lower mold which define a substantially rectangular-shaped mold cavity; and

a first plurality of vents in communication with the mold cavity, and disposed on one side of said substantially rectangular-shaped mold cavity, and a second plurality of vents in communication with the mold cavity and disposed on a second side of said mold cavity which is adjacent said one side, said first and second pluralities of vents being disposed on a part line between said upper mold and said lower mold, each vent having a vent passageway with an entrance and an exit, each said vent passageway being elongated with a width parallel to the part line substantially greater than a thickness orthogonal to the part line to cause liquid foam polymeric composition expanding inside the mold cavity to enter into each said vent passageway entrance but to not exit from each said vent passageway exit to cause at least partial curing of the liquid foam polymeric composition within each said vent passageway, each vent passageway being of a size and elongated shape so that the at least partially cured liquid foam polymeric composition in said vent passageway does not separate from the molded foam article when the upper and lower mold are separated to produce the plurality of ribbon-shaped appendages on the foamed article.

5,587,184

COATING DIE WITH SLOT THICKNESS CONTROL

William K. Leonard, River Falls, Wis.; Stephen W. Mohn, St. Paul, Minn.; Timothy J. Edman, Stillwater, Minn., and Philip D. Schiller, Oakdale, Minn., assignors to Minnesota Mining and Manufacturing, St. Paul, Minn.

Division of Ser. No. 177,152, Jan. 4, 1994, Pat. No. 5,464,577.

This application Jun. 2, 1995, Ser. No. 459,311


Int. Cl.⁶ B29C 47/04; 47/16

U.S. Cl. 425—133.5

7 Claims

1. A die comprising:

a first plate having a lip;



a second plate having a lip and contacting the first plate at first and second locations, wherein the second location is further from the lips than the first location, to form a first slot through the die which terminates and is bounded at its exit by the first and second lips;

means for holding the first and second plates together; and

first means for deforming at least one of the first and second plates at or between the first and second locations thereby to change the gap at the exit of the first slot, wherein one plate has a first cutout formed at one of the first and second locations and wherein the first deforming means is located in the first cutout.

5,587,185

AUTOMATED SYSTEM FOR HANDLING AND CLEANING CONCRETE PIPE-MAKING COMPONENTS


Hartzell H. Schmidgall, and Jon A. Schmidgall, both of Mediapolis, Iowa, assignors to Hawkeye Concrete Products Co., Mediapolis, Iowa

Filed Apr. 18, 1994, Ser. No. 229,191

Int. Cl.⁶ A46B 13/02

U.S. Cl. 425—229

6 Claims



1. A system for cleaning concrete deposits from the surfaces of annular shaped headers and pallet rings used in the manufacture of concrete pipe, said system comprising: a cleaning table having a receiving area into which the ring to be cleaned is moved; a cleaning station extending over a portion of the cleaning table; a pair of spaced-apart drive rollers at one side of the table within the cleaning station; a first slot in the cleaning table extending from the receiving area through the cleaning station; a first ring moving member moveable along the first slot and controllably extendable up through the first slot and above the table and retractable beneath the table; first means causing the ring moving member to extend up

through the table at the ring receiving area so as to extend inside a ring resting on the table at the receiving area; second means to move the ring moving member along the first slot and advance a ring from the receiving area into the cleaning station adjacent to the drive rollers within the station; third means to retract the ring moving member when the ring is adjacent the drive rollers; fourth means to move the ring and hold it against the drive rollers to allow the drive rollers to rotate the ring; cleaning means moveable into and out of a position to engage the surfaces of the ring to be cleaned while the ring is rotating; a second slot in the cleaning table extending from the cleaning station to an area outside the cleaning station; and a second ring moving member moveable along the second slot and controllably extendable up through the slot and retractable beneath the table to selectively engage a cleaned ring and move it outside the cleaning station.

5,587,186

APPARATUS FOR PELLETIZING PLASTICS


Jürgen Voigt, Wathlingen, Germany, assignor to Herman Berstorff Maschinenbau GmbH, Hanover, Germany
Filed Sep. 8, 1994, Ser. No. 302,512

Claims priority, application Germany, Sep. 11, 1993, 43 30 834.1

Int. Cl.⁶ B29B 9/06

U.S. Cl. 425—310

6 Claims



1. Apparatus for pelletizing plastic material discharged through a die plate, comprising:
 - a stationary housing defining a melt channel;
 - a die plate secured to said housing and formed with die openings through which melt strands are discharged, said die plate having a bottom surface;
 - a knife head mounted for rotation in said housing;
 - a plurality of cutting knives having cutting edges extending radially substantially along and passing closely adjacent to the said bottom surface of said die plate for cutting said strands into pellets; and
 - a coupler mechanism mounted on said knife head and extending radially therefrom, said coupler mechanism comprising a pair of cranks which are coaxially arranged one above the other and which support therebetween said cutting knives, said coupler mechanism being constructed and arranged to maintain the cutting knives parallel to said bottom surface of said die plate over the entire length of contact of said cutting knives with said bottom surface regardless of the pressure exerted by said knives on said bottom surface.

5,587,187
BRICK PRESS

Marthinus J. Benade, Plot 4, Glen Dayson, Roodepoort, South Africa

Filed Feb. 1, 1995, Ser. No. 384,267


Claims priority, application South Africa, Feb. 2, 1994, 94/0706

Int. Cl.⁶ B28B 3/04; B30B 1/04; 1/26

U.S. Cl. 425—409

9 Claims

1. A brick press comprising:



a brick pressing chamber which can be charged with loose material that is to be pressed to form a brick and which is defined by side walls, a bottom wall and a top wall, the bottom wall being provided by a platen which is movable towards and away from the top wall, and the top wall being provided by a lid which is movable between a closed position in which said lid closes the chamber and an open position in which it opens the chamber; and

a lever mechanism operable, with the lid in said closed position, firstly with a cam action to move the platen towards the lid so as to apply initial compression to loose material in the pressing chamber and secondly with a levering action to move the platen further towards the lid to apply final compression to the initially compressed material in the pressing chamber,

wherein the lever mechanism includes a lever attached pivotally relative to the platen, a cam follower on the lever and a cam surface on the lid, the lever being pivotable relative to the platen in a first direction to cause movement of the cam follower over the cam surface with the result that the platen is moved towards the lid to apply initial compression to the material in the pressing chamber.

5,587,188

MULTITIP HOT RUNNER SYSTEM


Douglas C. Hepler, Rochester, N.Y., assignor to Polysht Corporation, Henrietta, N.Y.

Continuation-in-part of Ser. No. 249,089, May 25, 1994, Pat. No. 5,464,343, which is a continuation of Ser. No. 982,473, Nov. 27, 1992, abandoned. This application Sep. 9, 1994, Ser. No. 303,495

Int. Cl.⁶ B29C 45/22

U.S. Cl. 425—549

9 Claims



1. A multitip hot runner apparatus for transporting molten plastic from an injection machine to a plurality of mold cavities while controlling the temperature of the molten plastic, said apparatus comprising:

a generally rectangular, parallelepiped shaped distribution body fabricated of a single piece of metal, having a predetermined depth, and being bilaterally symmetric about a centerline, said distribution body having top, bottom, and side surfaces, a distribution well formed in said top surface for receiving molten plastic, a plurality of unrestricted and substantially

identically configured through flow channels formed between said distribution well and said bottom surface of said distribution body to transport molten plastic in a general direction of flow from said distribution well along said flow channels and toward said bottom surface, each of said through flow channels having lower sections adapted to releasably receive tips for transporting molten plastic beyond said bottom surface to gates of respective mold cavities and being aligned aside of one another generally in a line with a predetermined spacing between them, a plurality of heater holes equally spaced within said distribution body with respect to said flow channels so that each flow channel is surrounded in said distribution body by a substantially identical thermal mass to assure uniform heating of said flow channels when heaters present in said distribution body are energized, said heater holes extending parallel to said top and bottom surfaces of said distribution body, transverse to said general direction of flow, and a single non-through thermocouple hole, extending from one side of said distribution body, horizontally and parallel to said heater holes to a predetermined length short of said distribution body centerline; said thermocouple hole being arranged to facilitate monitoring of the temperature at a location in one of said distribution body's bilaterally symmetric halves;

each of said plurality of heaters being disposed in a corresponding one of said plurality of heater holes;

a thermocouple disposed in said thermocouple hole for monitoring the temperature of said distribution body and supplying temperature feedback information for controlling the temperature of all of said flow channels; and

a plurality of tips, each of said tips being releasably engaged within a respective one of said lower sections of said flow channels to form an air space to prevent heat loss, said tips being fabricated of a material with high heat conducting properties relative to those of said distribution body to conduct heat from said distribution body outside of said bottom surface thereof to prevent plastic freeze at cavity gates; and an interface body attached to said distribution body for receiving molten plastic and transporting it to said distribution well of said distribution body.

assembled within the outer frame assembly to be pivotally moved and a link member pivotally engaged with each rear shoulder of the adjustment blades for interconnection of the adjustment blades, the outer frame assembly being comprised of a pair of outer frame members each having a frame body integral with a pair of opposed side wall portions and being integrally coupled with each other at their side wall portions to form the outer frame assembly,

wherein the molding device comprises a pair of opposed first slide cores each formed with a molding surface forming each frame body of the outer frame members, a pair of opposed second slide cores arranged perpendicularly to said first slide cores, said second slide cores each being formed with a molding surface forming each side wall portion of the outer frame members, a third slide core positioned adjacent one of said first slide cores, said third slide core being formed with a molding surface forming the link member, and a core block arranged to be disposed between said first and second slide cores, said core block being formed with a molding surface forming the adjustment blades, and wherein said molding device further comprises first actuator means for moving said first slide cores toward and away from said core block so that in a condition where said first slide cores have been moved toward said core block, the outer frame members are coupled with each other at their side wall portions and engaged with the adjustment blades carried by said core block; guide means for moving said second slide cores outwardly when said core block has been retracted; and second actuator means for moving said third slide core toward said core block so that the link member is engaged with the adjustment blades carried by said core block.

5,587,190

DIETARY DRINK INTENDED TO ENABLE SUSTAINED ACTIVITY

Yannick Guezennec, Fontainebleau; Joseph Koziel, Villiers Sur Marne, and Michel Thiry, Vigneux Sur Seine, all of France, assignors to Pernod Ricard, Paris, France

Continuation of Ser. No. 78,957, Jun. 16, 1993, abandoned, which is a continuation of Ser. No. 776,634, Oct. 15, 1991, abandoned. This application Mar. 21, 1995, Ser. No. 408,110

Int. Cl.⁶ A23L 2/00

U.S. Cl. 426—2

3 Claims

1. A method of enabling sustained activity comprising supplying to a mammal a composition comprising carbohydrates and lipids, said lipids constituting 10 to 55% of the calorie content of the composition and consisting of medium chain triglycerides and long chain triglycerides, said carbohydrates constituting 30% to 90% of the calorie content of the composition and the concentration ratio of carbohydrates to lipids is greater than or equal to 1 and wherein at least a portion of said carbohydrates comprise fructose, said composition being supplied in liquid form before, during or after said sustained activity.

5,587,191

PROCESS FOR MAKING HIGHLY OXYGENATED DRINKING WATER AND DRINKING WATER MADE BY THE PROCESS

Kurt W. Donsbach, 880 Canarios Ct., #210, and Ricardo Caza- res, 870 Canarios Ct., #3, both of Chula Vista, Calif. 91910, assignors to Chang S. Kim, Honolulu, Hi.; Kurt W. Donsbach, and Ricardo Caza- res, both of Chula Vista, Calif.

Filed Jul. 26, 1995, Ser. No. 507,584


Int. Cl.⁶ A23L 2/00

U.S. Cl. 426—66

17 Claims

16. A method of making highly oxygenated drinking water, comprising:

initially preparing a stabilized hydrogen peroxide solution composed of about 0.075% by weight of hydrogen peroxide added as a 30% by weight aqueous solution, about 15% by weight of a water soluble polyvinylpyrrolidone having a K value of about K15, about 50% by weight of a water soluble polyvi-



1. A molding device for a register of synthetic resin adapted for use in adjustment of air flow, the register being comprised of an outer frame assembly, a plurality of spaced adjustment blades


nylpyrrolidone having a K value of about K30, and about 5% by weight of a water soluble polyvinylpyrrolidone having a K value of about K90; and adding a quantity of said stabilized hydrogen peroxide solution to a quantity of drinking water to highly oxygenate the drinking water for consumption purposes.

5,587,192 VENTABLE CONTAINER

Michel Beizermann, Volron, France, assignor to Societe de Constructions de Material Metallique, Renage, France
Filed Sep. 29, 1994, Ser. No. 314,858
Int. Cl.⁶ B65D 81/34

U.S. Cl. 426—118

5 Claims




1. A container comprising a lower body including a tray having a recessed portion terminating at an upper lip that surrounds the tray, said recessed portion containing a product to be heat processed in the container, the lip having a flat configuration including an upper surface and an inner edge separating the tray from the upper surface of the lip, an upper film secured to the lower body by a first bond comprising a weld extending along a welding line on the upper surface of the lip so that the upper film hermetically seals the product in said lower body, a hole formed in the lip between the welding line and the inner edge of the lip, the hole being defined and surrounded by a portion of the upper surface of the lip and being closed by the film extending across the hole in sealing relationship, the film being flexible away from the tray in response to increased gas pressure within the container during heating of the product and a layer of hot melt adhesive having a melting point between 65° C. and 150° C. placed in spaced relation from said welding line and in interposition between the upper film and the portion of the upper surface of the lip that surrounds the hole, said layer releasably bonding said upper surface of the lip to the film to form a second bond between said upper surface of said lip and said film such that said film seals the hole and prevents gaseous communication between the hole and the recessed portion of the tray under temperature conditions less than said melting point and such that when said container and product are heat processed and said film flexes away from said tray, said hot melt adhesive layer softens and releases said second bond between said upper surface of the lip and said film to expose said hole to gaseous communication between the hole and the recessed portion of the tray, thus enabling venting of the container, and such that said second bond between said upper surface of the lip and said film reforms upon the container cooling such that the hole is again sealed, preventing gaseous communication between the hole and the recessed portion of the container.

5,587,193 PROCESS FOR MANUFACTURING FAT-ENRICHED FOODS

Massoud Kazemzadeh, Bloomington, Minn., assignor to MJM Technologies, Stacy, Minn.
Filed Sep. 12, 1995, Ser. No. 527,005
Int. Cl.⁶ A23K 1/00

U.S. Cl. 426—448

7 Claims




1. A method of manufacturing a fat-enriched low bulk density animal food extrudate comprising the steps of: adding a gas into an oil medium to form a gas saturated oil medium wherein the gas in the oil medium is in the form of microbubbles; injecting the gas saturated oil medium into an extruder; mixing the gas saturated oil medium with an animal food extrudate within the extruder; exiting of the resulting mixed extrudate through a die, and expanding said mixed extrudate through release of pressure.

5,587,194 APPARATUS AND METHOD FOR STERILIZING FOOD

Masayuki Nakatani, Nagoya; Koji Sengoku, Chiba-ken, and Akifumi Fujita, Ichihara, all of Japan, assignors to House Foods Corporation, Osaka, Japan
Filed Jun. 15, 1995, Ser. No. 490,708
Claims priority, application Japan, Jun. 16, 1994, 6-134655
Int. Cl.⁶ A23L 3/00

U.S. Cl. 426—521

6 Claims



2. A food sterilizing method comprising the steps of: feeding food into a sterilizing apparatus, said sterilizing apparatus including a heating and sterilizing chamber for heating and sterilizing food and a cooling chamber connected to the heating and sterilizing chamber via a sealing gate, the heating and sterilizing chamber and the cooling chamber each having an inner pressure; maintaining the inner pressure of the cooling chamber at a level higher than the inner pressure of the heating and sterilizing chamber by 0.05–0.3 Kg/cm²; and passing food through the sterilizing apparatus to sterilize and cool the food.

5,587,195 PLASTIC FAT SPREAD COMPRISING A HARDSTOCK

Cornelis L. Sassen, Schiedam, Netherlands, assignor to Van den Bergh Foods Co., Division of Conopco, Inc., Lisle, Ill.
Filed May 8, 1995, Ser. No. 437,191
Claims priority, application European Pat. Off., May 10, 1994, 94201322

U.S. Cl. 426—607

6 Claims

1. A spread comprising: 5 to 90% fat phase and 95–10% of an aqueous phase, the fat phase comprising 4–20% of a fully hardened but otherwise not chemically treated fat material used as a hardstock having the following fatty acid composition:

C ₁₂	9–45 wt %
C ₁₄	1–5%
C ₁₆	3–7%
C ₁₈	>40%

others up to 10%, these fatty acids being arranged in the following triglyceride combinations:

H3	0–35 wt %
HHM	20–80%
MHM	10–60%
M ₃	0–10%

H representing saturated acids having more than 15 carbon atoms and M saturated acids having 12 or 14 carbon atoms, the sequence of the symbols H and M representing the position of the fatty acids in the triglyceride molecule, and a liquid oil as the remaining portion of the fat phase.

5,587,196 METHODS AND COMPOSITIONS TO ADD FLAVOR TO FOOD PRODUCTS CONTAINING LIPID

David W. Mehnert, Antioch; Kevin Forneck, Morton Grove; Steven Prince, and Michael D. Major, both of Evanston, Ill., assignors to Kraft Foods, Inc., Northfield, Ill.
Filed Feb. 15, 1995, Ser. No. 388,013
Int. Cl.⁶ A23D 9/007

U.S. Cl. 426—611

39 Claims

1. A flavored fat substitute comprising a fat substitute and a flavor; the flavored fat subs which is prepared by volatile transfer of the flavor into the fat substitute; wherein the fat substitute is a non-digestible fat and the flavored fat substitute is essentially free of diestibe fat.

5,587,197 PROCESS FOR PRODUCTION OF WATER-SOLUBLE VEGETABLE FIBER

Hirokazu Maeda; Hitoshi Furuta, both of Kitasoma-gun; Chiemi Takel, Inashiki-gun; Toshiaki Salto, Sennan-gun; Hiroyuki Mori, Abiko, and Kazunobu Tsumura, Kitasoma-gun, all of Japan, assignors to Fuji Oil Company, Ltd., Osaka, Japan
Continuation-in-part of Ser. No. 76,946, Jun. 16, 1993, abandoned, which is a continuation of Ser. No. 768,412, Oct. 7, 1991, abandoned. This application May 10, 1995, Ser. No. 437,983

Claims priority, application Japan, Feb. 7, 1990, 2-27882; Feb. 9, 1990, 2-30677

U.S. Cl. 426—658

3 Claims

1. A process for the production of water-soluble vegetable fibers which comprises degrading okara, said okara being a water-insoluble residue containing insoluble protein and insoluble fiber and obtained by adding water to defatted soybeans to form a slurry and removing the water soluble fraction from the slurry, said degrading being carried out at a pH 3 to 6 and at a temperature of 80° to 130° C. to obtain water-soluble hemicellulose having an

average molecular weight of 50,000 to 1,000,000 and a protein content of less than 10% by weight based on the dry solids and recovering the water soluble hemicellulose.

5,587,198 POSITIVE HYDRATION METHOD OF PREPARING CONFECTIONERY AND PRODUCT THEREFROM

Subraman R. Cherukuri, Towaco, N.J.; Robert K. Yang, Flushing, N.Y.; Cecil A. Bowles, Sioux City, Iowa; Jose F. Zamudio-Tena, Vienna, and Santi R. Bhowmik, Chesapeake, both of Va., assignors to Fuisz Technologies Ltd., Chantilly, Va.

Filed May 31, 1995, Ser. No. 455,936

Int. Cl.⁶ A23G 3/00


39 Claims

1. A method of making a confectionery mass comprising: forming a confectionery mass by combining a saccharide-based shearform matrix and a hydrated hydrobinding agent selected from the group consisting of food grade gums, gelatin and mixtures thereof said hydrated hydrobinding agent present in an amount sufficient to hydrate said shearform matrix so as to provide internal cohesiveness and lubricity to said confectionery mass without causing syneresis.

5,587,199 PROCESS OF PREPARING PARTICLES FOR NMR IMAGING

Hervé Tournier, Vallety; Roland Hyacinthe, Douvaine, both of France, and Michel Schneider, Troinex, Switzerland, assignors to Bracco International B.V., Switzerland
Division of Ser. No. 96,414, Jul. 26, 1993, Pat. No. 5,464,696.
This application Apr. 13, 1995, Ser. No. 421,329
Claims priority, application European Pat. Off., Aug. 13, 1992, 92810618; May 25, 1993, 93810380
Int. Cl.⁶ B05D 7/00; 3/12; B32B 9/00; B06B 1/00
U.S. Cl. 427—2.12

8 Claims



1. A method of making a particle for use in the NMR blood-pool imaging of human or animal patients, said particle comprising a magnetite iron oxide core and a layer of at least one amphipatic compound having a negatively charged phosphorus containing head moiety bonded to a hydrophobic tail moiety and one or more surfactants, said method comprising the steps of:

- (a) selecting said amphipatic compound from an alkyl, alkenyl or cycloalkyl mono ester of phosphoric acid or a phospholipid in a micellar form;
- (b) selecting at least one of said surfactants from physiologically acceptable non-ionic surfactants;
- (c) suspending in an aqueous phase: (i) magnetite iron oxide particles, (ii) at least one of the selected amphipatic compounds and (iii) at least one of the selected non-ionic surfactants to form a mixture; and
- (d) energizing the mixture by sonicating, microfluidizing or heating to organize the molecules of the amphipatic compound relative to the iron oxide core so that the phosphorus containing head moiety of the amphipatic compound is pointing towards the iron oxide core and the hydrophobic tail

moiety protrudes therefrom, the negatively charged head moiety having the negative charges of two oxygen atoms available for interaction with the core and the hydrophobic tail moiety having at least eight carbon atoms, thereby producing three dimensional structures around said iron oxide particles.

5,587,200

METHOD FOR MANUFACTURING A MEDICAL ELECTRODE

Hans P. Lorenz, Schwarzenbrück, Bernd Strachler, Berlin, both of Germany, and Ulf Lindgren, Enskede, Sweden, assignors to Pacesetter AB, Solna, Sweden

Filed Nov. 7, 1995, Ser. No. 554,770

Claims priority, application Germany, Nov. 11, 1994, 44 40 386.0

Int. Cl.⁶ B05D 1/32; C23C 8/04; 8/24; 16/34

U.S. Cl. 427-2.24 14 Claims

1. A method for manufacturing a medical electrode comprising the steps of:

- disposing a bare substrate of electrically conductive material in an atmosphere containing titanium, nitrogen and hydrogen; directly covering said bare substrate with an optical mask having a pattern therein having openings corresponding to a structure to be produced on said substrate; and
- irradiating said substrate with said optical mask thereon in said atmosphere with an excimer laser and thereby depositing a structure of porous titanium nitride corresponding to said pattern directly on said substrate exclusively in said openings.

5,587,201

FILMING COMPOSITION FOR CATHODE RAY TUBE AND METHOD OF MANUFACTURING SCREEN USING THE SAME

Hwan-chul Rho; Hong-gyu Choi, and Jae-myung Kim, all of Hwaseong-gun, Rep. of Korea, assignors to Samsung Display Devices Co., Ltd., Kyungki-do, Rep. of Korea

Filed Mar. 30, 1995, Ser. No. 413,888

Claims priority, application Rep. of Korea, Dec. 7, 1994, 94-33112

Int. Cl.⁶ B05D 5/06

U.S. Cl. 427-64 5 Claims

1. A method for manufacturing a screen having high luminance comprising the steps of:

- forming a phosphor layer on a black matrix adhered to a panel;
- forming a filming layer by coating and drying a filming composition containing a decomposable organic polymer and a reducing agent on said phosphor layer;
- forming a metal layer on said filming layer; and
- heating said phosphor layer, filming layer and metal layer to a temperature sufficient to decompose said filming layer.

5,587,202

REPULPABLE HOT MELT POLYMER/FATTY ACID COMPOSITIONS FOR FIBROUS PRODUCTS

Paul E. Sandvick, and Calvin J. Verbrugge, both of Racine, Wis., assignors to S. C. Johnson & Son, Inc., Racine, Wis.

Division of Ser. No. 96,523, Jul. 22, 1993, Pat. No. 5,419,190.

This application Dec. 14, 1995, Ser. No. 572,404

Int. Cl.⁶ D21H 19/00

U.S. Cl. 427-155 18 Claims

1. A method of rendering a paper article water-resistant that comprises the steps of

- heating a hot melt polymer/fatty acid composition that is dispersible in a nearly neutral to alkaline aqueous pH medium heated to above about 50 degrees C. consisting essentially of
- A. from about 5% to 50% by weight based upon the total weight of the composition of at least one addition polymer selected from the group consisting of

(i) a polymer of from about 5 to 95 mole percent of at least one ethylenically unsaturated monocarboxylic acid monomer containing a free carboxyl group and from about 5 to 95 mole percent of at least one additional ethylenically unsaturated monomer.

(ii) a polymer of from about 50 to 95 mole percent of at least one ethylenically unsaturated dicarboxylic acid monomer selected from the group consisting of an ethylene-1,2-dicarboxylic acid containing two free carboxyl groups and an ethylene-1,2-dicarboxylic acid anhydride having two carboxyl groups in the form of an anhydride group, and from about 5 to 50 mole percent of at least one additional ethylenically unsaturated monomer, and

(iii) a polymer of a total of from about 5 to 95 mole percent of (a) at least one of the ethylenically unsaturated monocarboxylic acid monomers and (b) at least one of the ethylenically unsaturated dicarboxylic monomers and from about 5 to 95 mole percent of at least one additional ethylenically unsaturated monomer, wherein the additional ethylenically unsaturated monomer is selected from the group consisting of 1-alkenes having from about 4 to 60 carbon atoms; alkyl vinyl ethers having an ether alkyl group of from about 8 to 60 carbon atoms, and alkyl acrylates or alkyl methacrylates having an alkyl group of from about 8 to 60 carbon atoms, and

B. from about 50% to 95% by weight based upon the total weight of the composition of at least one fatty acid selected from the group consisting of natural or synthetic fatty acids containing from about 12 to 48 carbon atoms, wherein the fatty acid is compatible with the polymer and wherein the composition is a solid at 20° C., but starts to become fluid between about 50° C. and 95° C., until it becomes fluid.

applying to a paper article an amount of the fluid heated composition that is effective to render it water-resistant, and allowing the composition to cool to room temperature to form a coated paper article having a solid coating that is removable upon exposure of the coated paper article to a nearly neutral to alkaline pH medium heated to above about 50 degrees C.

5,587,203

METHOD FOR PREPARING A CARBON/CARBON COMPOSITE MATERIAL

Yoshio Soda; Takefumi Kohno; Masaaki Shinagawa, and Noriyuki Kiuchi, all of Yokohama, Japan, assignors to Nippon Oil Co., Tokyo, Japan

Continuation-in-part of Ser. No. 342,858, Nov. 21, 1994, abandoned. This application Aug. 29, 1995, Ser. No. 520,654

Claims priority, application Japan, Nov. 29, 1993, 5-320817

Int. Cl.⁶ B05D 3/02

U.S. Cl. 427-228 8 Claims

1. A method of preparing a carbon/carbon composite material which consists of the steps of

- 1) impregnating a carbon preform with a carbonaceous pitch, said carbonaceous pitch having a carbon/hydrogen atomic ratio of less than 1.60 and exhibiting a densification parameter of 0.1 or more, said densification parameter being calculated by heating said carbonaceous pitch in an open-type crucible from room temperature up to 1000° C. at a rate of 2° C./min. and then keeping at 1000° C. for two hours whereby said carbonaceous pitch is sintered, said densification parameter being calculated by the formula

$$\text{densification parameter} = K \times L$$

wherein

$$K = \frac{(C-A)}{B-A}$$

and

$$L = \frac{(C-A)}{V \times T}$$

wherein

C= weight of the crucible and the sintered product

A= weight of the crucible

B= weight of the crucible and pitch before sintering

V= volume of the sintered product

T= true density of the sintered product

and then

- 2) heating said impregnated preform at a temperature of 250°-3000° C. and subjecting to an isotactic compression at a pressure higher than atmospheric pressure up to 10 Kg/cm² whereby said impregnated preform is carbonized and a carbon/carbon composite is obtained.

5,587,204

RECYCLABLE PAPERBOARD COMPOSITES

Joe L. Kinsey, Jr., Irvington, and Robert L. Lanham, Jr., Mobile, both of Ala., assignors to International Paper Company, Purchase, N.Y.

Filed Mar. 22, 1995, Ser. No. 408,479

Int. Cl.⁶ B05D 1/38

U.S. Cl. 427-411

8 Claims

1. A method for making recyclable coated paperboard composites comprising providing a cellulosic paperboard substrate having two surfaces, applying adjacent at least one surface of the substrate a highly alcoholized polyvinyl alcohol binder layer and applying a polyethylene coating layer to the polyvinyl alcohol binder layer, wherein the polyvinyl alcohol coating layer is applied in an amount of ranging from about 2 to about 12 pounds per 3000 square feet of substrate.

5,587,205

PLASMA PROCESSING METHOD AND AN APPARATUS FOR CARRYING OUT THE SAME

Hiroshi Saito, Fujisawa; Yasumichi Suzuki, Yokohama, and Naoyuki Tamura, Kudamatsu, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Dec. 23, 1993, Ser. No. 172,285


Claims priority, application Japan, Dec. 28, 1992, 4-347682; Dec. 28, 1992, 4-347683; Dec. 10, 1993, 5-310100

Int. Cl.⁶ B05D 3/06; C23C 16/00; H01L 21/00

U.S. Cl. 427-553

26 Claims






5,587,209
FLUOROCARBON-BASED POLYMER LAMINATION
COATING FILM AND METHOD OF MANUFACTURING
THE SAME

Mamoru Soga, Osaka; Norihisa Mino, Settsu; Kazufumi Ogawa, Hirakata; Yusuke Mochizuki, Neyagawa, and Tsuneo Shibata, Kawanishi, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan
 Continuation of Ser. No. 278,126, Jul. 21, 1994, abandoned, which is a continuation of Ser. No. 61,284, May 14, 1993, abandoned, which is a division of Ser. No. 786,824, Nov. 1, 1991, Pat. No. 5,238,746. This application May 10, 1995, Ser. No. 438,875

Claims priority, application Japan, Nov. 6, 1990, 2-302021
 Int. Cl.⁶ B05D 3/06

U.S. Cl. 427—503

8 Claims



wherein a plurality of axially aligned arcs or a plurality of transversely distributed parallel arcs or both are generated with a main arc burning between one of the one or more cathodes and one of the one or more anodes.


5,587,208
RADIATION INDUCED GRAFTING OF
POLYORGANOSILOXANES TO FLUOROELASTOMERS
 Santokh S. Badesha, Pittsford; David H. Pao, Rochester; William M. Prest, Jr., Webster; Arnold W. Henry, Pittsford; George J. Heeks, Rochester, and Louis D. Fratangelo, Fairport, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Nov. 22, 1993, Ser. No. 155,350
 Int. Cl.⁶ C08J 7/04

U.S. Cl. 427—503

15 Claims

1. The method of making a low surface energy material comprising providing a shaped fluoroelastomer, preparing a solvent solution of a polyorganosiloxane having reactive functionality and the formula:



where R is an alkyl, alkenyl or aryl group having less than 19 carbon atoms or an aryl group substituted with an alkyl or alkenyl group having less than 19 carbon atoms, the functional group A is epoxy, vinyl, acrylic, allylic or methacrylic and n is 2 to 350, contacting said fluoroelastomer with said solution to form at least a thin coating of the polyorganosiloxane on said fluoroelastomer, and generating free radicals in the fluoroelastomer and in the polyorganosiloxane by exposing said coated fluoroelastomer to a level of activating radiation wherein the fluoroelastomer and the polyorganosiloxane couple together to form a thin surface layer of the polyorganosiloxane grafted to said fluoroelastomer, wherein said shaped fluoroelastomer is placed in said solvent solution of said polyorganosiloxane to swell said fluoroelastomer and enable said polyorganosiloxane to penetrate below the surface of said fluoroelastomer so that upon subsequent exposure to said radiation a deep graft of said polyorganosiloxane to said fluoroelastomer below the surface of said fluoroelastomer is formed.

1. A method of manufacturing a fluorocarbon-based polymer lamination coating film which comprises an inner layer comprising an adsorbed film, and an outer layer comprising a cross-linked fluorine-based polymer film wherein the inner layer is bonded onto a substrate surface with siloxane bonds, and said inner layer is bonded to said outer layer, comprising
 contacting a silane-based surface active material, capable of reaction with an active hydrogen, with the substrate surface to form the adsorbed film, and
 bonding the fluorine-based polymer by a cross-linking reaction process on the adsorbed film.

5,587,210
GROWING AND RELEASING DIAMONDS
 Michael J. Marchywka, Lanham, Md., and Pehr E. Pehrsson, Alexandria, Va., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jun. 28, 1994, Ser. No. 266,758
 Int. Cl.⁶ C23C 14/02; 16/26

U.S. Cl. 427—523

15 Claims

1. A process for making diamond which comprises the steps of
 (a) ion implanting a diamond substrate having a top surface to form a damaged layer of non-diamond carbon below the top surface of the substrate wherein a diamond cap layer is disposed above the damaged layer;
 (b) growing diamond on at least a portion of the top surface of the substrate by chemical vapor deposition to form an assembly which includes a bottom layer of the substrate, the layer of non-diamond carbon interfacing with an upper surface of the bottom layer, a diamond cap layer on a surface of the non-diamond carbon layer opposite the interface of the damaged non-diamond carbon and the bottom layer, a grown diamond interfacing with a surface of the diamond cap layer opposite the interface of the diamond cap and the damaged non-diamond carbon layer; and
 (c) electrochemically etching the assembly in order to remove the damaged layer.

5,587,211
LIQUID CRYSTAL DEVICE AND LIQUID CRYSTAL
APPARATUS INCLUDING SAME


Takeshi Togano, Yokohama; Hideaki Takao, Machida; Masanobu Asaoka, Yokohama, and Makoto Kojima, Atsugi, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Apr. 18, 1995, Ser. No. 423,101

Claims priority, application Japan, Apr. 18, 1994, 6-101717
 Int. Cl.⁶ G02F 1/1337

U.S. Cl. 428—1

10 Claims



1. A liquid crystal device, comprising: a pair of substrates disposed in parallel with each other and each having an electrode thereon, and a liquid crystal assuming chiral smectic phase disposed between the substrates; at least one of the substrates having thereon an organic alignment film comprising (i) at least one species of polymer having an average molecular weight of at most 30,000 and (ii) at least one species of polymer having an average molecular weight exceeding 30,000.

5,587,212


Patent Not Issued For This Number

5,587,213
STRETCH ADORNMENTS
 Roberta M. Ruschmann, 260 Minebrook Rd., Bernardsville, N.J.

Filed Nov. 16, 1994, Ser. No. 340,635
 Int. Cl.⁶ B32B 1/00

U.S. Cl. 428—12

11 Claims



1. An adornment for affixing the same to a surface, said adornment comprising a plurality of ornaments and thread means comprising elastic main thread operatively engaging a plurality of such ornaments for affixing the same to a surface, said thread means allows said ornaments to be stretchably attached to a surface, and bobbin thread, said thread means being the sole means of maintaining said ornaments at a predetermined spaced relationship with respect to each other prior to affixing to a surface.


5,587,214
LAMINATED THERMAL TRANSFER PRINTABLE
LABELS

Chauncey T. Mitchell, Jr., Lakeland, Tenn., assignor to Media Solutions, Inc., Lakeland, Tenn.

Filed May 13, 1994, Ser. No. 242,313
 Int. Cl.⁶ B32B 7/00

U.S. Cl. 428—40.1

38 Claims




1. A roll of thermal transfer label stock comprising:
 a first substrate having front and back faces and a length;
 said front face of the first substrate adapted for receiving thermal transfer ink;
 a linerless adhesive layer on said back face of the first substrate;
 a second substrate having front and back faces and a length;
 an unimaged layer of thermal transfer ink on said front face of the second substrate;
 a release layer on said back face of the second substrate; and
 said first and second substrates being aligned along their respective lengths, laminated together, and wound into coils such that said adhesive layer of the first substrate contacts said release layer of the second substrate.

5,587,215
CALENDAR WRITING PAGE
 Laurie A. G. Bell, P.O. Box 22122, Tucson, Ariz. 85734-2122
 Filed Sep. 14, 1994, Ser. No. 305,582
 Int. Cl.⁶ B32B 3/04

U.S. Cl. 428—40.1

1 Claim



1. A set of "writing pages" for attachment to the monthly rectangular illustration sheets of a previously existing calendar, comprising:

- a plurality of rectangular pages of writing paper each of a size and shape corresponding to that of said illustration sheets;
- a corresponding plurality of clear adhesive strips each narrower than said writing paper pages and each having
 - a first portion aligned with and attached to the front surface of the left edge of one of said writing paper pages, said first portion having a longitudinal side edge that is aligned with and completely covering said left edge of said page and
 - a second portion connected along its longitudinal side edge to said first portion side edge and extending beyond such left edge and having adhesive material on its bottom surface with a peel away backing attached thereto, said second portion being folded back along and behind said left edge to permit attachment to the front surface of one of said

illustration sheets along its right edge with the back surface of said writing paper page exactly overlying the back surface of said illustration sheet; said second portion overlaps said first portion and said adhesive faces said first portion and.

(c) markings along the right edge of each said writing paper page to identify hole punch areas for use in binding said writing paper pages and their associated illustration sheets along the edges thereof opposite to the edges attached to each other by said adhesive strips.

5,587,216

OPTICAL RECORDING MEDIUM

Kazumi Yoshio, Yawata, Takeo Ohta, Nara; Shigeaki Furukawa, Nara-ken, and Katsumi Kawahara, Kadoma, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka-fu, Japan


Continuation of Ser. No. 962,112, Oct. 16, 1992, abandoned.

This application Oct. 26, 1994, Ser. No. 329,682

Int. Cl.⁶ B32B 3/02; G11B 5/66

U.S. Cl. 428—64.4

2 Claims



1. An optical recording medium which records on the basis of phase transformation, sequentially formed on one face of a transparent basic plate, comprising:

- a first protection layer consisting of a mixture of ZnS and SiO₂ formed on said face of the transparent basic plate;
- a recording thin film layer formed on the first protection layer which records on the basis of a phase transformation;
- a second protection layer consisting of a mixture of ZnS and SiO₂ formed on the recording thin film layer;
- a third protection layer of SiO₂ formed on the second protection layer;
- a reflection layer formed on the third protection layer; and
- wherein the third protection layer is harder than the second protection layer and has a smaller linear expansion coefficient than the first and second protection layers, the sum of the thickness of the second protection layer and the third protection layer is less than 30 nm, and is less than the thickness of the first protection layer, and wherein the second protection layer has a thickness of less than 10 nm, and is less than the thickness of the third protection layer.

5,587,217

LUBRICANT COMPOSITION AND METHOD

James L. Chao, Milpitas; Yu-Cheun Lee, Newark, and Chao Gao, Fremont, all of Calif., assignors to HMT Technology Corporation, Fremont, Calif.

Continuation-in-part of Ser. No. 270,240, Jul. 1, 1994, abandoned. This application Jun. 30, 1995, Ser. No. 497,431


Int. Cl.⁶ G11B 5/71

U.S. Cl. 428—65.4

9 Claims

1. A thin-film magnetic recording disc for use with a read/write head in a disc drive, comprising

- a substrate,
- a magnetic recording film formed on the substrate,
- a protective overcoat formed on the recording film, and



an outer lubricant layer comprising a hexaphenoxycyclotriphosphazene lubricant and a perfluoropolyether oil, wherein each phenoxy group in the lubricant, taken separately, is substituted with one or more short chain substituents selected from the group consisting of F, CF₃, OCF₃, CF₂CF₃, CH₂CF₃, OCF₂CF₃, and OCH₂CF₃.

and wherein said hexaphenoxycyclotriphosphazene lubricant and perfluoropolyether oil are present in relative proportions effective to provide a significant reduction in frictional drag relative to the reduction in drag provided by the hexaphenoxycyclotriphosphazene lubricant or perfluoropolyether oil alone.

5,587,218

SURFACE COVERING


Richard T. Betz, 701 - 122nd Ave. NE., Bellevue, Wash. 98005

Filed May 18, 1994, Ser. No. 245,445

Int. Cl.⁶ B44C 1/26

U.S. Cl. 428—67

18 Claims



1. A surface covering comprising:

- a base constructed from a substantially planar and rigid material, said base having first, second, third, and fourth edges and first and second opposing sides, said first and second edges being positioned in opposing relationship and said third and fourth edges being positioned in opposing relationship, said first side of said base including a plurality of working grooves extending from said first edge to said second edge of said base, said plurality of working grooves being spaced apart from one another along said first side, said second side of said base including a plurality of receiving grooves extending from said first edge to said second edge of said base, said plurality of receiving grooves being spaced apart from one another along said second side of said base from said third edge to said fourth edge, each of said plurality of receiving grooves being a substantially linear groove having first and second opposing walls extending from said first edge to said second edge, each said first and second wall having a gripping projection projecting into said corresponding receiving groove and extending from said first edge to said second edge, said first side of said base including a plurality of receiving slots;
- a plurality of fasteners each having a head portion and a stem portion, said plurality of fasteners being positioned in said plurality of receiving slots so that said head portion is movably secured within said slot and so that said stem portion extends outward from said slot; and
- a plurality of filler strips each being a substantially compliant material positioned in respective ones of said plurality of receiving grooves and being gripped by said gripping projections of said first and second walls of said receiving grooves, each of said plurality of filler strips extending outward from said receiving grooves to provide a textured surface for said surface covering.

5,587,219

NECK CUSHIONING TOWEL

Lois E. Schofield, 27 Wildwood Ln., So. Hadley, Mass. 01075


Continuation of Ser. No. 382,082, Feb. 1, 1995, abandoned.

This application May 1, 1996, Ser. No. 646,732

Int. Cl.⁶ B32B 3/08; 3/06

U.S. Cl. 428—68

7 Claims



1. A neck cushioning towel for providing comfort for the cervical vertebral area of the neck and for helping to maintain the head in a neutral position to help reduce the risk of vertebral arterial injury, whereby a user's hair can be washed, rinsed or treated at a commercial sink designed with an uncushioned indentation where the cervical vertebral area of the neck rests, said neck cushioning towel comprising:

- (a) a substantially rectangular towel defining upper and lower edges connected by two side edges wherein the upper and lower edges have a length greater than the two side edges;
- (b) a pouch located approximately in the center of the length of said towel and positioned adjacent an upper edge;
- (c) a gel-filled, removable sac for insertion into the pouch;
- (d) fastening means for securing said sac in said pouch;
- (e) an adjustable means attached to the towel for an adjustable fastener fit of the towel around a human being.

5,587,220

FORMED PLASTIC AND METHOD OF MANUFACTURING THE SAME

Kazufumi Ogawa, Hirakata, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Division of Ser. No. 913,727, Jul. 16, 1992, Pat. No. 5,461,083.


This application Jun. 7, 1995, Ser. No. 485,501

Claims priority, application Japan, Jul. 26, 1991, 3-187696

Int. Cl.⁶ B32B 3/14

U.S. Cl. 428—71

4 Claims



2. A foamed plastic comprising a foamed resin comprising foamed cells covered with an airtight film, wherein the pressure at room temperature in the foamed cells and the pressure at room temperature in a gap region between the airtight film and foamed resin are less than atmospheric pressure, and containing a polymerized volatile foaming agent in the foamed cells, wherein said foaming agent is a monomer having a boiling point from about 30° C. to about 81° C. and having at least one unsaturated carbon bond.

5,587,221

INSECTICIDAL CARPET AND PRETREATMENT PROCESS FOR PRODUCING INSECTICIDAL CARPET

T. H. McCamy, P.O. Box 962, Dalton, Ga. 30722, and William H. H. Clark, P.O. Box 8, Ringgold, Ga. 30736

Filed Dec. 20, 1994, Ser. No. 359,401

Int. Cl.⁶ B23B 3/02; A01N 25/34; 59/14; 33/22; A61K 33/22

U.S. Cl. 428—96

20 Claims

1. A carpet possessing insecticidal, bactericidal and fungicidal properties, said carpet comprising a carpet backing and carpet fibers, wherein the carpet has been treated with a solution comprising:

- (a) a mixture consisting of boric acid and disodium tetraborate decahydrate; and
- (b) an aqueous medium.

5,587,222

LABEL ASSEMBLY WITH MULTI-PLY INSERT


Donald J. Hoffmann, Elmhurst, Ill., assignor to Wallace Computer Services, Inc., Hillside, Ill.

Filed Nov. 14, 1994, Ser. No. 340,364

Int. Cl.⁶ B32B 23/02

U.S. Cl. 428—192

35 Claims




1. A label assembly for attaching to a product, comprising:

- a base ply having an informational side and an adhesive side with an adhesive thereon for attaching to the product;
- a multi-ply insert overlying a portion of said informational side of said base ply, said insert being smaller than said base ply such that an area of said informational side of said base ply is exposed for viewing indicia received thereon, said insert having a top ply with a peripheral edge; and
- a pair of separately spaced fastening strips with an adhesive on one side, said adhesive of said fastening strips engaging said peripheral edge of said top ply and said informational side of said base ply for permanently securing said fastening strips to said informational side of said base ply and to said top ply along its peripheral edge, each of said fastening strips having a line of weakness extending substantially adjacent said peripheral edge of said top ply.

5,587,223

HIGH DENSITY MAGNETIC INFORMATION STORAGE MEDIUM

Robert L. White, Stanford, Calif., assignor to Board of Trustees Leland Stanford, Jr. University, Stanford, Calif.
Continuation of Ser. No. 963,562, Oct. 19, 1992, abandoned.
This application Jun. 30, 1994, Ser. No. 270,201
Int. Cl.⁶ G11B 5/66; B32B 3/00
U.S. Cl. 428—195 14 Claims



1. A magnetic information storage medium comprising:
a substrate; and
a plurality of discrete, generally disk-shaped, spaced apart bodies of magnetic material disposed on said substrate with a density in excess of 10^9 bodies/in², each said body being magnetizable independent of its neighboring bodies and each said body having a maximum diameter of between 200 Å and 500 Å, said bodies being formed by
(a) providing a layer of magnetic material on said substrate, said layer being at least 100 Å thick and no greater than 500 Å thick, said magnetic material having uniaxial anisotropy;
(b) providing a layer of photoresist over the layer of magnetic material;
(c) providing a primary mask over said layer of photoresist, said primary mask being formed by an ordered array of discrete generally spherical polymeric particles having a diameter no greater than 750 Å;
(d) exposing said photoresist through said primary mask by flooding it with electrons, said polymeric particles causing generally disk-shaped regions of said layer of photoresist to remain unexposed;
(e) removing said primary mask;
(f) developing said photoresist to leave a plurality of discrete photoresist disks on said layer of magnetic material which form a secondary mask;
(g) subjecting the secondarily masked magnetic film to an etchant to remove magnetic material not covered by said disks; and
(h) stripping away the photoresist disks to leave said plurality of disk-shaped bodies of magnetic material disposed on said substrate.

5,587,224

DEVELOPING APPARATUS INCLUDING A COATED DEVELOPER ROLLER


Bing R. Hsieh; Joseph Mort; Mary A. Machonkin, all of Webster, and Joan R. Ewing, Fairport, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.
Filed Mar. 27, 1995, Ser. No. 411,359
Int. Cl.⁶ G03G 15/08
U.S. Cl. 428—195 32 Claims

1. A coated donor roll comprised of a core with a coating thereover comprised of a photolysis reaction product of a charge transporting polymer and a photo acid compound.

5,587,225

KNIT-LIKE NONWOVEN COMPOSITE FABRIC

Henry L. Griesbach, Atlanta; Christopher C. Creagan, Marietta, and Sharon W. Gwaltney, Woodstock, all of Ga., assignors to Kimberly-Clark Corporation, Neenah, Wis.
Filed Apr. 27, 1995, Ser. No. 430,206
Int. Cl.⁶ B32B 27/14
U.S. Cl. 428—198 17 Claims




1. A launderable composite comprising:
a) a first filamentous layer, said first layer comprising crimped continuous filaments;
b) a second filamentous layer, said second layer comprising crimped continuous filaments; and
c) a cellulosic layer, said cellulosic layer comprising cellulosic fibers and having been disposed between said first and second filamentous layers,
wherein said composite is a hydroentangled pattern bonded composite that is adhesively or thermally patterned bonded forming bonded regions within said composite, and said composite loses less than about 2% of its opacity, based on the initial opacity of said composite, when subjected to one laundering cycle in accordance with the ASTM 2724-87 washing and drying procedure and wherein said first and second filamentous layers are unbonded except by means of said adhesively or thermally patterned bonds.

5,587,226

PORCELAIN-COATED ANTENNA FOR RADIO-FREQUENCY DRIVEN PLASMA SOURCE

Ka-Ngo Leung, Hercules; Russell P. Wells, Kensington, and Glen E. Craven, Fremont, all of Calif., assignors to Regents, University of California, Oakland, Calif.
Filed Jan. 28, 1993, Ser. No. 10,108
Int. Cl.⁶ B32B 9/00
U.S. Cl. 428—210 24 Claims




1. An antenna comprising:
a) a metal conductor;
b) a porcelain coating fused to said conductor;
c) electrical contacts for connecting said antenna to an impedance-matched power supply; and
d) an alternating-current impedance-matched power supply.

5,587,227

COATING OF CHROMIUM AND NITROGEN HAVING GOOD WEAR RESISTANCE PROPERTIES

Masaki Ooya, Kashiwazaki, Japan, assignor to Kabushiki Kaisha Riken, Tokyo, Japan
Filed Oct. 27, 1994, Ser. No. 327,896
Int. Cl.⁶ C23C 8/26
U.S. Cl. 428—217 4 Claims




1. A wear-resistant coating provided on a surface of a substrate of a slidable component and comprising a composition of chromium and nitrogen which is chromium nitride at the portion of the coating in contact with the surface of said substrate and which continuously increases in chromium content from the substrate surface to said coating surface.

5,587,228

MICROPARTICLE ENHANCED FIBROUS CERAMICS

Anna L. Baker, and Darryl F. Garrigus, both of Seattle, Wash., assignors to The Boeing Company, Seattle, Wash.
Division of Ser. No. 124,419, Jul. 28, 1993, Pat. No. 5,441,682, which is a continuation of Ser. No. 527,600, May 23, 1990, which is a continuation-in-part of Ser. No. 381,498, Jul. 18, 1989, abandoned, which is a continuation-in-part of Ser. No. 698,496, Feb. 5, 1985, Pat. No. 5,041,321, which is a continuation-in-part of Ser. No. 667,496, Oct. 18, 1984, Pat. No. 4,634,918. This application Mar. 13, 1995, Ser. No. 404,015
Int. Cl.⁶ B32B 1/04; 1/08; 1/10; 5/24
U.S. Cl. 428—34.5 16 Claims



1. A ceramic composite which is the product of the process of:
(a) forming a slurry of ceramic components in a liquid, the components including microparticles in the size range between about 5–200 micrometers and selected from the group consisting of hollow microballoons, diatoms, solid microparticles and mixtures thereof;
(b) felting a wet mat of the ceramic components from the slurry;
(c) drying the wet mat;
(d) infusing a ceramic sol-gel binder into the dry mat;
(e) gelling and curing the binder at a temperature of no more than about 600° F. to form a glass to hold the felted ceramic components in a rigid, porous, low-density, ceramic form;
(f) optionally, infusing additional binder into the mat to increase the density and strength; and

- (g) optionally, gelling and curing the subsequent infusions of binder.

5,587,229

RESILIENT, HIGH SHRINKAGE PROPYLENE POLYMER YARN AND ARTICLES MADE THEREFROM

Luciano Clementini, Terni, Italy; Adam F. Galambos, New Castle County, Del.; Giuseppe Lesca, Milan, Italy; Kumar Ogale, New Castle County, Del.; Leonardo Spagnoli, Terni, Italy, and Michael E. Starsinic, Cecil County, Md., assignors to Montell North America Inc., Wilmington, Del.
Division of Ser. No. 371,056, Jan. 10, 1995, Pat. No. 5,486,419, which is a continuation-in-part of Ser. No. 824,661, Jan. 23, 1992, abandoned. This application Sep. 21, 1995, Ser. No. 531,985
Claims priority, application Italy, May 29, 1992, M192A1336
Int. Cl.⁶ D02G 3/00; C08L 23/00; C08F 10/04
U.S. Cl. 428—224 2 Claims


1. A fabric prepared from a propylene polymer yarn of increased resiliency and shrinkage, compared to crystalline propylene homopolymer yarn, comprising a continuous strand of multiple monofilament fibers, said fibers consisting essentially of a member of the group consisting of, amounts being expressed as weight %:
I. a blend of crystalline propylene homopolymer at a concentration of about 10–70% of the blend, and (a) a random crystalline terpolymer consisting essentially of about 96.0–85.0% of propylene, about 1.5–15.0% of ethylene, and about 2.5–10% of a C₄–C₈ alpha-olefin or (b) a random, crystalline, propylene polymer consisting essentially of propylene and about 1.5–20.0% of ethylene or C₄–C₈ alpha-olefins; and
II. propylene polymer material, optionally in a blend with crystalline, propylene homopolymer, said homopolymer being at a concentration up to about 70% of the blend, said propylene polymer material being selected from the group consisting of:
(a) a composition of random, crystalline, propylene polymers consisting essentially of:
(1) about 30–65% of a copolymer of about 80–98% propylene, and a C₄–C₈ alpha-olefin, and
(2) about 35–70% of a copolymer of propylene and ethylene and optionally about 2–10% of a C₄–C₈ alpha-olefin, said copolymer containing about 2–10% ethylene when said C₄–C₈ alpha-olefin is not present, and about 0.5–5% ethylene when said C₄–C₈ alpha-olefin is present;
(b) a composition of random, crystalline, propylene polymers and a predominantly ethylene copolymer, which composition consists essentially of:
(1) about 15–35% of a terpolymer of about 90–93% propylene, about 2–3.5% ethylene, and about 5–6% C₄–C₈ alpha-olefin,
(2) about 30–75% of a copolymer of about 80–90% propylene, and a C₄–C₈ alpha-olefin, and
(3) about 20–60% of a copolymer of about 91–95% ethylene, and a C₄–C₈ alpha-olefin;
(c) a heterophasic, polyolefin composition consisting essentially of:
(1) 90–55% of polymeric material selected from the group consisting of a propylene homopolymer having an isotactic index greater than 90, and a crystalline copolymer of propylene and an alpha-olefin of the formula CH₂=CHR, where R is H or C₂–C₈ alkyl, said olefinic material being less than 10% of the copolymer, and
(2) 10–45% of an elastomeric polymer of propylene and olefinic material selected from the group consisting of alpha-olefins of the formula CH₂=CHR, where R is H or C₂–C₈ alkyl, said olefinic material being 50–70% of said elastomeric copolymer being insoluble in xylene at ambient temperature.

5,587,230 HIGH STRENGTH COMPOSITE

Leroy C. Lin, Richmond; Laura G. Wilson; Ashok Bhatnagar, both of Chester, all of Va., and Hsin L. Li, Parsippany, N.J., assignors to AlliedSignal Inc., Morristown, N.J.
Division of Ser. No. 148,732, Oct. 29, 1993. This application Jun. 2, 1995, Ser. No. 459,133
Int. Cl.⁶ B32B 7/00

U.S. Cl. 428—245

15 Claims




1. A method for producing a ballistic resistant article that includes at least one network of high strength fibers in a matrix composition, wherein the high strength fibers have a tenacity of at least about 7 g/d, a tensile modulus of at least about 150 g/d and an energy-to-break of at least about 8 J/g, the method comprising applying a mixture consisting essentially of at least one thermoset vinyl ester, an optional catalyst for curing the thermoset vinyl ester, diallyl phthalate and at least one carbon-carbon saturated solvent having a boiling point lower than about 115° C. to a high strength fiber network followed by consolidating the coated high strength fiber network at a temperature higher than the boiling point of the solvent and lower than about 120° C. to substantially remove the carbon-carbon saturated solvent.

5,587,231 SYNTACTIC FOAM CORE MATERIAL AND METHOD OF MANUFACTURE

Charles L. Mereer, and Thomas E. Phillips, both of Granville, Ohio, assignors to Isored, Inc., Granville, Ohio
Filed Jul. 29, 1994, Ser. No. 282,371
Int. Cl.⁶ B32B 3/26; 5/18

U.S. Cl. 428—283

11 Claims



1. A syntactic foam core material adaptable to providing a low density rigid foam core layer for composite layered sandwich structures comprising a layer of hollow ceramic microspheres, dry resin powder particles finer in dimension than the diameter of said microspheres thoroughly intermixed with said layer of microspheres to provide a uniform mixture of said powder particles and microspheres, said microspheres being present in said mixture in a percentage by volume amount of at least 60%, said mixture of microspheres and resin powder having been processed through a cycle of heat melting and setting of said resin particles in interbonded relationship with said microspheres, said resin particles being present in quantity to interbond said mixture into an integrated rigid syntactic foam layer while leaving void spaces within said layer upon setting of said melted resin, said rigid foam layer having a density less than 25 pounds per cubic foot, said layer having opposite major surfaces for combination with layers of material on opposite sides thereof in layered sandwich structures.

5,587,232 NON-MAGNETIC PARTICLES FOR NON-MAGNETIC UNDERCOATING LAYER OF MAGNETIC RECORDING MEDIUM, NON-MAGNETIC UNDERCOATING LAYER CONTAINING THE SAME, AND MAGNETIC RECORDING MEDIUM HAVING THE UNDERCOATING LAYER

Kazuyuki Hayashi; Keisuke Iwasaki; Yasuyuki Tanaka; Minoru Ohsugi; Toshiharu Harada; Masaru Isoal, and Kazushi Takama, all of Hiroshima, Japan, assignors to Toda Kogyo Corporation, Japan
Filed Aug. 4, 1993, Ser. No. 101,063
Claims priority, application Japan, Aug. 7, 1992, 4-232959
Int. Cl.⁶ G11B 5/66; B32B 5/16

U.S. Cl. 428—323

14 Claims

1. A non-magnetic undercoating layer for a magnetic recording medium formed on a non-magnetic substrate, comprising non-magnetic particles composed of acicular or spindle-shaped α -Fe₂O₃ particles coated with at least one member selected from the group consisting of an Al compound, a silane coupling agent, a titanate coupling agent, an aluminate coupling agent and a zirconate coupling agent,

the amount of said at least one member selected from the group consisting of an Al compound, calculated as Al, a silane coupling agent, a titanate coupling agent, an aluminate coupling agent and a zirconate coupling agent being 0.01 to 50 parts by weight based on 100 parts by weight of said α -Fe₂O₃ particles; wherein said particles have an average major axis diameter of 0.05 to 0.25 μ m, an average minor axis diameter of 0.010 to 0.035 μ m, an aspect ratio of 2 to 20, and a particle size distribution in geometrical standard deviation of not more than 1.40, and the thickness of the non-magnetic undercoating layer is 1 to 10 μ m.


5,587,233 COMPOSITE BODY AND ITS USE

Udo König, Essen, Germany; Hendrikus Van Den Berg, Venlo-Blerick, Netherlands, and Ralf Tabersky, Bottrop, Germany, assignors to Widla GmbH, Essen, Germany
PCT No. PCT/DE93/00047, $\S$ 371 Date Aug. 30, 1994, $\S$ 102(e) Date Aug. 30, 1994, PCT Pub. No. WO93/20257, PCT Pub. Date Oct. 14, 1993
PCT Filed Jan. 21, 1993, Ser. No. 295,902
Claims priority, application Germany, Mar. 27, 1992, 42 09 975.7

Int. Cl.⁶ B32B 1/00

U.S. Cl. 428—325

14 Claims



1. A composite body which comprises (a) a ceramic, sintered ceramic or cermet substrate body or a substrate body made of diamond or a nickel-based or cobalt-based alloy; and (b) at least one surface layer composed of at least one aluminum oxide with a grain size of at most 50 nm selected from the group which consists of fine crystalline γ -aluminum oxide and α -aluminum oxide, and γ -aluminum oxide modified with a fraction of amorphous alumina and α -aluminum oxide modified with a fraction of amorphous alumina deposited by

plasma CVD at a substrate temperature of 400° to 750° C., with the substrate body connected as cathode and with a plasma activation produced by a pulsed direct voltage.

structure as that of said first ferromagnetic alloy thin film layer and a region having an oxygen concentration higher than that of said first ferromagnetic alloy thin film layer.

5,587,234 ELASTOMERIC POLYSULFIDE COMPOSITES AND METHOD


Weldon C. Kiser, Abilene, Tex., assignor to Environmental L.L.C., Abilene, Tex.
Division of Ser. No. 187,082, Jan. 26, 1994, Pat. No. 5,453,313.

This application May 9, 1995, Ser. No. 437,592

Int. Cl.⁶ B32B 5/16

U.S. Cl. 428—327

12 Claims




1. An elastomeric polysulfide composite comprising an elastomeric polysulfide having rubber particles distributed substantially uniformly therethrough.

5,587,235 MAGNETIC RECORDING MEDIUM AND MAGNETIC RECORDING APPARATUS

Hiroyuki Suzuki, Odawara; Naoki Kodama, Kamakura; Takao Yonekawa, Odawara; Tokuho Takagaki, Hiratsuka; Naoto Endo, Odawara; Katsuo Abe, Hiratsuka, and Tsuneo Suganuma, Tokorozawa, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Feb. 8, 1994, Ser. No. 193,376
Claims priority, application Japan, Feb. 19, 1993, 5-030632; Feb. 19, 1993, 5-030633
Int. Cl.⁶ G11B 5/66; B32B 5/16

U.S. Cl. 428—332

17 Claims



1. A magnetic recording medium comprising:

a substrate;

a non-magnetic underlying layer formed on the substrate;

a plurality of stacked ferromagnetic alloy thin film layers each containing Co and at least one additional element selected from the group consisting of Cr and Ni, wherein a first one of the ferromagnetic alloy thin film layers is disposed on said non-magnetic underlying layer and another one of said plurality of ferromagnetic alloy thin film layers is disposed over said first ferromagnetic alloy thin film layer; and an intermediate region laminated on said first one of the ferromagnetic alloy thin film layers, which intermediate region reduces magnetic interaction occurring in the stacked ferromagnetic alloy thin film layers.


said intermediate region being one selected from the group consisting of a paramagnetic region having the same crystal

5,587,236 INTERIOR REAR VIEW MIRROR MOUNTING SYSTEM UTILIZING ONE-PACKAGE STRUCTURAL ADHESIVE

Raj K. Agrawal; Niall R. Lynam, both of Holland, and James K. Galer, Grandville, all of Mich., assignors to Donnelly Corporation, Holland, Mich.
Division of Ser. No. 773,236, Oct. 9, 1991, abandoned. This application May 10, 1995, Ser. No. 438,612
Int. Cl.⁶ A47G 1/17; B32B 15/08; 17/10; 27/38

U.S. Cl. 428—334

42 Claims



1. A mirror mounting button, windshield arrangement, comprising:

a windshield, said windshield including an interior surface; a cured non-elastomeric, thermosetting, one-package, structural adhesive in contact with and adhered to said interior windshield surface, said adhesive having a modulus of elasticity at 85° C. of at least about 10,000 psi, said structural adhesive being a latent curing adhesive system capable of substantial cure at a temperature below about 325° F. and requiring exposure to a temperature in excess of about 125° F. before substantial curing is achieved; and a mirror mounting button attached to said adhesive, whereby said cured adhesive forms a bond between said windshield and said mirror mounting button, wherein said adhesive bond can support a weight greater than or equal to about 100 grams.

5,587,237 PRESSURE SENSITIVE ADHESIVE

Ralf Korpman; Vera Korpman, both of Bridgewater, N.J.; Michael Korpman, Longwood, Fla., and Dennis Korpman, Beaumont, Tex., assignors to Ralf Korpman Associates, Inc., Bridgewater, N.J.
Continuation of Ser. No. 134,924, Oct. 7, 1993, abandoned, which is a division of Ser. No. 977,580, Nov. 17, 1992, Pat. No. 5,274,036. This application Feb. 14, 1995, Ser. No. 389,061
Int. Cl.⁶ C09J 7/02

U.S. Cl. 428—355

3 Claims

1. A health care pressure-sensitive adhesive product having improved skin tack and skin adhesion characteristics comprising a flexible backing having coated on at least one side thereof said pressure-sensitive composition, said pressure sensitive composition comprising a solid rubber and a liquid rubber wherein the weight ratio of said solid rubber to said liquid rubber being from about 1:0.5 to about 1:7, said liquid rubber being selected from the group consisting of liquid isoprene-styrene, liquid butadiene-styrene, liquid carboxyl terminated isoprene, liquid hydroxyl terminated isoprene and liquid hydrogenated isoprene, wherein said composition is substantially tackifying resin free.

5,587,238

COMPOSITION HAVING A BASE OF CELLULOSE FORMATE CAPABLE OF PRODUCING FIBERS OR FILMS

Jean-Paul Meraldi; Vlastimil Cizek, and Rima Huston, all of Zurich, Switzerland, assignors to Michelin Recherche Et Techni UE S.A., Granges - Pacot, Switzerland
Division of Ser. No. 302,753, Sep. 13, 1994. This application Jun. 6, 1995, Ser. No. 466,573

Claims priority, application France, Jan. 27, 1993, 93 01121
Int. Cl.⁶ D02G 3/00

U.S. Cl. 428—357

6 Claims

1. A regenerated cellulose fiber, characterized by the following points:

- the degree of substitution of the cellulose by formate groups is less than 3%;
- the fiber is formed of filaments each of which has, in cross section, a morphology which is practically continuous from the periphery up to the core;
- the mechanical properties of the conditioned fiber are as follows: $T \geq 10$ cN/tex; $M_i \geq 500$ cN/tex; $A_R > 5\%$; T being the tenacity, M_i being the initial modulus, and A_R being the elongation upon rupture.

5,587,239

BALL-LIKE STRUCTURES AND CONTACTING MATERIALS FOR WASTEWATER-TREATMENT

Hisaaki Ueba; Yosio Sunaga, and Tosio Nagasima, all of Tochigi-ken, Japan, assignors to Kureha Kagaku Kogyo Kabushiki, and Kureha Gosen Kabushiki Kaisha, both of Japan


Filed Jun. 27, 1994, Ser. No. 265,963

Claims priority, application Japan, Jun. 29, 1993, 5-185611

Int. Cl.⁶ D02G 3/00; B32B 5/16; B01D 39/08

U.S. Cl. 428—362

4 Claims



1. Ball structures formed from huddled, crimped fibers rounded around a central portion thereof as a core, the core being formed from molten-fused fibers and having the following characteristics:

- a ratio of the specific gravity of the molten-fused fibers forming the ball structures divided by the specific gravity of the material that forms the fibers, expressed as a percentage, of at least 75%;
- a length of the molten-fused fibers of 5 to 50% based on diameter of the ball structures;
- a withdrawing strength of a crimped fiber strand connected to the molten-fused fibers of not less than 50% based on a linear strength of the crimped fiber strand itself used for the ball structures;
- a core volume of 1 to 30% based on the volume of the ball structures; and
- a crimping rate of the crimped fibers of from 10 to 75%.

5,587,240
CARBON FIBERS AND PROCESS FOR PREPARING SAME

Masanobu Kobayashi, Ehime; Motoi Itoh, Iyo; Yoji Matsuhisa, Ehime, and Kazuharu Shimizu, Otsu, all of Japan, assignors to Toray Industries, Inc., Japan


Division of Ser. No. 293,817, Aug. 22, 1994, Pat. No. 5,462,799. This application Jun. 5, 1995, Ser. No. 462,753
Claims priority, application Japan, Aug. 25, 1993, 5-210282; Jan. 14, 1994, 6-002582; Feb. 16, 1994, 6-019219

Int. Cl.⁶ D02G 3/00


U.S. Cl. 428—367

4 Claims

1. A carbon fiber having a surface oxygen concentration (O/C ratio) of 0.20–0.02 and a surface nitrogen concentration (N/C ratio) of 0.02–0.30, as measured by x-ray photoelectron spectroscopy, and comprising a sizing agent having an aromatic compound which has multiple epoxy groups, wherein the number of atoms between the epoxy groups and an aromatic ring is 6 or greater, wherein the aromatic compound with multiple epoxy groups in which the number of atoms between the epoxy groups and an aromatic ring is 6 or greater is a compound represented by the following formula,



wherein R_1 represents the following group,



R_2 represents an alkylene group of 2–30 carbon atoms, R_1 represents $-H$ or $-CH_3$, and m and n are each an integer of 2–48, $m+n$ being 4–50.

5,587,241

MINERAL FIBERS AND WHISKERS EXHIBITING REDUCED MAMMALIAN CELL TOXICITY, AND METHOD FOR THEIR PREPARATION


Gerald L. Vaughan, 2417 W. Gallaher Ferry Rd., Knoxville, Tenn. 37932, and Samuel C. Weaver, 5440 Glen Cove Dr., Knoxville, Tenn. 37919

Filed Jun. 1, 1995, Ser. No. 457,851

Int. Cl.⁶ D02G 3/00

U.S. Cl. 428—375

4 Claims



1. Improved mineral fibers and whiskers exhibiting abatement of cytotoxicity toward mammalian cells which consist of mineral

fibers and whiskers each completely coated with an agent that confers hydrophobicity to said fibers and whiskers, said agent selected from the group consisting of organic halogenated silanes and silicones.

5,587,242

COLORED POLYMERIC DIELECTRIC PARTICLES AND METHOD OF MANUFACTURE

Wei-Hsin Hou; Thomas B. Lloyd, both of Bethlehem, Pa., and Frederic E. Schubert, Shoreham, N.Y., assignors to Cypotele, Inc., Huntington Station, N.Y.

Division of Ser. No. 241,349, May 11, 1994, Pat. No. 5,498,674, which is a division of Ser. No. 65,572, May 21, 1993, Pat. No. 5,360,689. This application Nov. 21, 1995, Ser. No. 561,249


Int. Cl.⁶ C08F 236/20

U.S. Cl. 428—402

7 Claims

1. A plurality of dielectric particles for use in an electrophoretic fluid, said particles being formed by a process comprising the steps of:

polymerizing a monomer selected from the group consisting of vinyl halide monomers and vinyl monomers having the formula



where X is selected from the group consisting of a halide, carboxyl, ether trialkylammonio, acetate, diazoniodialkylsulfonio, cyano, and oxyl imino using dispersion polymerization to form irregularly-shaped crystalline polymer particles, and where n is selected as H or X; wherein said step of polymerization includes:

- admixing said monomer and a crosslinker in a dispersion medium to form a first mixture;
 - preparing a second mixture of an initiator and a dispersion stabilizer for retarding the coagulation of said particles during said polymerization;
 - adding said first mixture to said second mixture to form a third mixture and allowing said monomer to polymerize to form said irregularly shaped crystalline polymer particles; and
 - sonifying said third mixture after polymerization to make said irregularly-shaped crystalline polymer particles uniform in size.
6. The dielectric particles of claim 1, wherein said size of said particles in step (d) is in the range from 0.5 to 5.0 micrometers.

5,587,243

EPOXY RESIN MIXTURES CONTAINING PHOSPHONIC/PHOSPHINIC ACID ANHYDRIDE ADDUCTS

Wolfgang von Gentzow, Kleinsendelbach; Jürgen Huber, Erlangen; Heinrich Kapitz, Fürth; Wolfgang Rogler, Möhrenhof; Hans-Jerg Kleiner, Kronberg, and Dieter Wilhelm, Forchheim, all of Germany, assignors to Siemens Aktiengesellschaft, München, and Hoechst Aktiengesellschaft, Frankfurt, both of Germany

PCT No. PCT/EP94/00747, § 371 Date Sep. 14, 1995, § 102(e) Date Sep. 14, 1995, PCT Pub. No. WO94/21703, PCT Pub. Date Sep. 29, 1994

PCT Filed Mar. 10, 1994, Ser. No. 522,332

Claims priority, application Germany, Mar. 15, 1993, 43 08 187.8

Int. Cl.⁶ C08G 59/14; 59/40; 59/50; H05K 1/03


U.S. Cl. 428—413

17 Claims

1. An epoxy resin mixture for producing prepregs and composites, comprising:

a phosphorus-modified epoxy resin with an epoxy value of 0.02 to 1 mol/100 g, and an average molecular weight M_n of up to 10,000, which is a reaction product of

- a polyepoxy compound with at least two epoxy groups per molecule and
- a phosphinic acid anhydride or a phosphonic acid anhydride, or a mixture thereof, and an aromatic polyamine hardener with the following structure:



where one of the R^1 and R^2 groups on each of the three aromatic rings denotes a hydrogen and the other is an alkyl.

5,587,244

LOW PRESSURE MEDICAL SILICONE GASKET


David E. Flinchbaugh, 4855 Big Oaks La., Orlando, Fla. 32806
Continuation of Ser. No. 625,379, Dec. 11, 1990, abandoned.

This application Jul. 30, 1992, Ser. No. 923,021

Int. Cl.⁶ B32B 25/20; B65D 53/06; F16J 15/00

U.S. Cl. 428—447

1 Claim



1. A seal or gasket comprising a core body having a shore (00) durometer hardness value of from about 2 to about 20 formed of thermally addition curable silicone elastomer and thereafter post cured by heating of the previously heat cured core body with a silicone release agent applied to an exterior surface of the core body at sufficient temperature and time to incorporate the silicone release agent with the core body to form a deformable non-stick skin on the core body, wherein the skin has a reduced adherence character as compared to said exterior surface of the core body prior to application and post curing with said silicone release agent.

5,587,245

FUSING MEMBER HAVING ZINC OXIDE-FILLED, ADDITION CURED LAYER

Susan A. Visser; Charles E. Hewitt; Tonya D. Binga, all of Rochester; Wayne T. Ferrar, Fairport; Michael W. Fichtner, Rochester, and John J. Fitzgerald, Clifton Park, all of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.


Filed Dec. 23, 1994, Ser. No. 363,149

Int. Cl.⁶ B32B 25/20

U.S. Cl. 428—447

23 Claims

1. A fuser member comprising a core and a layer overlying said core, said layer comprising: an addition crosslinked polyorganosiloxane elastomer, said layer having zinc oxide particles dispersed therein in a concentration of from 20 to 40 volume percent of the total volume of said layer, said elastomer comprises the product of addition crosslinking vinyl substituted multifunctional siloxane



polymers having a weight average molecular weight between vinyl groups of from 7,000 to 100,000.


5,587,246

WATER-RESISTANT SURFACE COATING FORMULATIONS AND PAPER COATED THEREWITH
Haruki Tsutsumi, Yoshiaki Ikemoto, both of Kanagawa-ken; Mitsubiro Machama, Yamaguchi-ken; Toshiki Oyanagi, and Tsugin Matsubara, both of Kanagawa-ken, all of Japan, assignors to Mitsui Toatsu Chemicals, Inc., Tokyo, Japan
Division of Ser. No. 248,183, May 24, 1994, Pat. No. 5,470,918. This application May 26, 1995, Ser. No. 450,149
Claims priority, application Japan, May 28, 1993, 5-126829
Int. Cl.⁶ B32B 23/08; 27/10


U.S. Cl. 428—511

8 Claims

5. Paper coated with a water-resistant surface coating formulation comprising a reaction product obtained by reacting an acrylamide polymer of at least one acrylamide monomer represented by the following formula (1):



wherein X represents H or CH₃ and Y represents H or CH₂OH, and, optionally, at least one comonomer selected from the group consisting of acrylic acid, methacrylic acid, acrylonitrile and itaconic acid, with 0.1 to 20 parts by mole, per 100 parts by mole of amido groups in the acrylamide polymer, of a glyoxalmonoureine represented by the following formula (2):



wherein Q and R independently represent H, CH₃ or CH₂OH; wherein the acrylamide polymer is produced from 100 to 60 parts by mole of the at least one acrylamide represented by the formula (1) and 0 to 40 parts by parts by mole of at least one comonomer selected from the group consisting of acrylic acid, methacrylic acid, acrylonitrile and itaconic acid.

5,587,247

RESIN COMPOSITION FOR EXTRUSION MOLDING
Kohji Kubo, Shoichi Nezu, Fumio Ishibashi, Hiroyuki Harada, and Yuji Shigematsu, all of Chiba, Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan
Filed Nov. 29, 1994, Ser. No. 350,074
Claims priority, application Japan, Nov. 29, 1993, 5-298276; May 23, 1994, 6-108183
Int. Cl.⁶ C08L 23/08; 23/04; B32B 27/32; C08K 5/00
U.S. Cl. 428—523

6 Claims

1. A resin composition for extrusion molding which has a melt flow rate (MFR) of from 0.5 to 30 g/10 min., comprising:
(A) 1 to 80 parts by weight of at least one polymer selected from the group consisting of low density polyethylene and copolymers of ethylene and at least one comonomer selected from the group consisting of unsaturated carboxylic acids, esters of unsaturated carboxylic acids containing 4 to 8 carbon atoms and vinyl esters, which gives an endothermic peak in a temperature range of from 80° to 120° C. in a temperature rise thermogram as measured by a differential scanning calorimeter, has a melt flow rate (MFR) of from 0.5 to 50 g/min., and is prepared by high-pressure radical polymerization.

(B) 5 to 80 parts by weight of a copolymer of ethylene and an α -olefin containing 6 to 8 carbon atoms which gives at least one endothermic peak in a temperature range of from 118° to 130° C. in a temperature rise thermogram as measured by a differential scanning calorimeter, has a melt flow rate (MFR) of from 0.5 to 30 g/10 min., a density of from 0.900 to 0.935 g/cm³, and

(C) 5 to 70 parts by weight of a copolymer of ethylene and an α -olefin containing 3 to 8 carbon atoms which has a melt flow rate (MFR) of from 0.5 to 30 g/10 min. and a density of from 0.902 to 0.920 g/cm³ in an unannealed state, gives no endothermic peak at temperatures above 110° C. in a temperature rise thermogram as measured by a differential scanning calorimeter, has a cooled-xylene portion which is not more than 30% by weight, and which has a ratio of a main component given by the formula:

$C_w(\%) = (\text{parts by weight of components which are dissolved in a solvent at solvent temperatures between } T_L \text{ and } T_H) \times 100 / (\text{parts by weight of components which are dissolved in a solvent at solvent temperatures at } 120^\circ \text{ C.})$ wherein $T_L (^\circ \text{C.}) = T_A - \{-4.61 \times \sigma^2 \times \log (0.0125 \times \sigma)\}^{1/2} - 6.15 \times (\log (\text{MFR}) + 1)$, and $T_H (^\circ \text{C.}) = T_A - \{-4.61 \times \sigma^2 \times \log (0.0125 \times \sigma)\}^{1/2}$, wherein $T_A = -5028 \times d^2 + 10481 \times d - 5303$, and $\sigma = 525.9 \times d^2 - 1096.3 \times d + 565.6$, in which d is a density as measured in an unannealed state (g/cm³), and o-dichlorobenzene (ODCB) is used as a solvent, is not less than 80%, and the total quantity of (A), (B) and (C) being 100 parts by weight.

5,587,248


CORROSION RESISTANT NICKEL PLATING STEEL SHEET OR STRIP AND MANUFACTURING METHOD THEREOF

Hitoshi Ohmura, Yamaguchi-ken; Yasuhiro Koyakumaru, and Satoshi Iketaka, both of Kudamatsu, all of Japan, assignors to Toyo Kohan Co., Ltd., Tokyo, Japan
Continuation of Ser. No. 78,920, Jun. 21, 1993, abandoned.
This application Mar. 3, 1995, Ser. No. 400,387
Claims priority, application Japan, Jun. 22, 1992, 4-188628
Int. Cl.⁶ C25D 5/26; B32B 15/01

U.S. Cl. 428—610

3 Claims

1. A corrosion-resistant steel sheet or strip comprising a base sheet made of a cold rolled steel sheet and a diffusion layer consisting essentially of iron and nickel and having a thickness in the range of 0.3 to 10.9 μm on at least one surface of said base sheet as a top exposed layer, wherein said diffusion layer being formed by recrystallizing a nickel layer which has been electroplated on at least one surface of said base sheet.



said nickel layer having a thickness in the range of about 1 to 5 μm prior to forming said diffusion layer; a ratio of said thickness of said diffusion layer to said thickness of said nickel layer prior to forming said diffusion layer being in the range of 10 to 333%; an iron exposure rate at the top surface of the top exposed layer is in the range of 4% to 30%.

5,587,249


Patent Not Issued For This Number

5,587,250

HYBRID ENERGY STORAGE SYSTEM
George Thomas, Lawrenceville, and Georgina Moré, Duluth, both of Ga., assignors to Motorola, Inc., Schaumburg, Ill.
Filed Sep. 27, 1995, Ser. No. 534,517
Int. Cl.⁶ H01M 16/00

U.S. Cl. 429—3

15 Claims



1. A hybrid energy storage system comprising:
a first energy storage device consisting of a secondary battery selected from the group consisting of lead-acid batteries, nickel cadmium batteries, nickel metal hydride batteries, lithium ion batteries, lithium polymer batteries, and combinations thereof for providing a constant current output of less than 1 ampere;
a second energy storage device consisting of an electrochemical capacitor device for providing intermittent bursts of current greater than 1 ampere; and
output electronics electrically coupled to said first and second energy storage devices for conditioning the output thereof, and for electrically coupling said energy storage devices to a load.

5,587,251

CERAMIC GAS SUPPLY COMPONENTS FOR FUEL CELLS COMPRISING ZIRCONIUM OXIDE SOLID ELECTROLYTE


Richard Spaeh, Ueberlingen; Wolfgang Schaefer, Friedrichshafen; Detlef Stollen, Uhlidingen, and Marco Fandel, Immenstaad, all of Germany, assignors to Dornier GmbH, Immenstaad, Germany
Filed Dec. 17, 1993, Ser. No. 168,251

Claims priority, application Germany, Dec. 17, 1992, 42 42728.2

Int. Cl.⁶ H01M 8/10; 2/00

U.S. Cl. 429—33

17 Claims



1. A gas manifold for a solid electrolyte fuel cell comprising an electrically insulating gas-tight ceramic formed from a mixture of a first ceramic component having a coefficient of thermal expansion less than that of said solid electrolyte and a second ceramic component having a coefficient of thermal expansion greater than that of said solid electrolyte, said first and second ceramic components being present in said mixture in such proportions that the ceramic formed from the mixture has a coefficient of thermal expansion substantially corresponding to that of said solid electrolyte.

5,587,252


PROCESS FOR DISPOSING OF SPENT NAS CELLS
Tomonori Tsuchimoto, Hashima-Gun; Katsuchi Iwata, Ichinomiya, and Yoshihiko Kurashima, Nagoya, all of Japan, assignors to NGK Insulators, Ltd., Japan
Filed Jun. 7, 1995, Ser. No. 483,160

Claims priority, application Japan, Jul. 20, 1994, 6-167739; Jun. 1, 1995, 7-135265

Int. Cl.⁶ H01M 10/54

U.S. Cl. 429—49

9 Claims



1. A process for disposing of a spent NaS cell, comprising the steps of:
cutting the NaS cell to form at least one opening to expose an inner tube and sodium in the NaS cell;
flowing oil into the NaS cell through the at least one opening while the NaS cell is positioned upright, to cover the sodium with the oil;
inverting the NaS cell such that the at least one opening faces a downward direction, the NaS cell being supported by a workpiece setting vessel that provides access to permit removal of the inner tube through the at least one opening;
immersing the NaS cell supported by the workpiece setting vessel in heated oil provided in a heating oil vessel while the NaS cell is inverted, whereby the sodium in the NaS cell is melted and flows out of the NaS cell; and
removing the inner tube from the NaS cell through the at least one opening.


5,587,253

LOW RESISTANCE RECHARGEABLE LITHIUM-ION BATTERY

Antoni S. Gozdz, Tinton Falls; Caroline N. Schmutz, Eatontown, and Paul C. Warren, Far Hills, all of N.J., assignors to Bell Communications Research, Inc., Morristown, N.J.
Continuation-in-part of Ser. No. 160,018, Nov. 30, 1993, Pat. No. 5,460,904, which is a continuation-in-part of Ser. No. 110,262, Aug. 25, 1993, Pat. No. 5,418,091, which is a continuation-in-part of Ser. No. 26,904, Mar. 5, 1993, Pat. No. 5,296,318. This application Aug. 3, 1995, Ser. No. 510,835
Int. Cl.⁶ H01M 4/64; 10/36

U.S. Cl. 429—192

12 Claims



1. A rechargeable lithium-ion battery structure comprising positive and negative electrode layer elements having a separator element disposed therebetween and current collectors associated therewith, each of said elements comprising a flexible, polymeric matrix film composition and being bonded to contiguous elements at its respective interfaces to form a unitary flexible structure characterized in that

- a) said positive electrode layer element comprises a composition of a lithium ion intercalating compound selected from the group consisting of LiMn_2O_4 , LiCoO_2 , and LiNiO_2 ; and
b) at least one of said current collectors is embedded within its associated electrode layer.

5,587,254

ALKALINE BATTERY HAVING A GELLED NEGATIVE ELECTRODE

Yuri Kojima, Katano; Yuji Mototani, Yawata, and Junichi Asaka, Ikoma, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Apr. 7, 1995, Ser. No. 419,054

Claims priority, application Japan, Apr. 21, 1994, 6-083089
Int. Cl.⁶ H01M 4/24; 4/62

U.S. Cl. 429—206

6 Claims



1. An alkaline battery provided with a gelled negative electrode comprising a zinc alloy powder, a gelling agent and an alkaline electrolyte;

- said gelling agent comprising a combination of:
a) a crosslinked polyacrylate water-absorbing polymer having a dispersion viscosity at 25° C. of at least 15,000 cps as a 0.5 wt % aqueous solution and having a particle size of 100–900 microns; a crosslinked and branched polyacrylic acid or a salt thereof having a dispersion viscosity at 25° C. of at least 15,000 cps as a 0.5 wt % aqueous solution and having a particle size of 100–900 microns;

thereof having a dispersion viscosity at 25° C. of at least 15,000 cps as a 0.5 wt % aqueous solution and having a particle size of 100 microns or smaller; and a granular crosslinked and branched polyacrylic acid or a salt thereof having a dispersion viscosity at 25° C. of at least 15,000 cps as a 0.5 wt % aqueous solution and having a particle size of 100–900 microns;

the concentration of said crosslinked polyacrylate water-absorbing polymer being in the range of from 0.25 wt % to 3.0 wt %, the concentration of said crosslinked and branched polyacrylic acid or salt thereof being in the range of from 0.1 wt % to 1.0 wt %, the concentration of said granular crosslinked and branched polyacrylic acid or salt thereof being in the range of from 0.1 wt % to 2.0 wt %, and the total concentration of said gelling agent being in the range of more than 1.50 wt % but at most 4.0 wt %, and the total concentration of said gelling agent being in the range of more than 1.50 wt % but at most 4.0 wt %, all the concentrations being based on the weight of the alkaline electrolyte.

5,587,255

CARBONACEOUS ELECTRODE MATERIAL FOR SECONDARY BATTERY

Naohiro Sonobe, Koji Maruyama, and Takao Iwasaki, all of Iwaki, Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 22, 1994, Ser. No. 199,810

Claims priority, application Japan, Feb. 25, 1993, 5-059427;
Nov. 26, 1993, 5-319288

Int. Cl.⁶ H01M 4/02

U.S. Cl. 429—218

9 Claims



1. A carbonaceous electrode material for a non-aqueous solvent-type secondary battery, comprising a pitch carbonaceous material having an average (002)-plane spacing of at least 0.365 nm according to an X-ray diffraction test, wherein said carbonaceous material is characterized by providing a residual carbonaceous substance showing an average (002) planar-spacing of at most 0.350 nm according to an X-ray diffraction test after said carbonaceous material is tested by treatment with an $\text{H}_2\text{O}-\text{N}_2$ equi-molar gas-mixture at 900° C. up to a weight reduction of 60%.

5,587,256

CARBONACEOUS INSERTION COMPOUNDS AND USE AS ANODES IN RECHARGEABLE BATTERIES

Alfred M. Wilson, Burnaby, and Jeffery R. Dahn, Surrey, both of Canada, assignors to Moli Energy (1990) Limited, Canada
Filed Apr. 25, 1995, Ser. No. 428,042

Claims priority, application Canada, Jul. 8, 1994, 2127621


Int. Cl.⁶ H01M 4/02

U.S. Cl. 429—218

46 Claims

1. A carbonaceous insertion compound comprising:

- (a) a pre-graphitic carbonaceous host C;
(b) atoms of an alkali metal A inserted into the host C, the amount of metal A being in a range from greater than or equal to zero; and



(c) atoms of an element B selected from the group consisting of Al, Bi, Cd, Pb, Sb, and Sn incorporated into the host C, the amount of element B being greater than zero, wherein element B alloys with metal A and the atoms of element B are incorporated predominantly as monodispersed atoms in the host C;

wherein said carbonaceous insertion compound has a reversible specific capacity for said alkali metal greater than graphite.

5,587,257

METHOD OF MAKING LITHIUM-ION CELL HAVING DEACTIVATED CARBON ANODES

Gary G. Tibbetts, Birmingham; Gholam-Abbas Nazri, Bloomfield Hills, and Blake J. Howie, Almont, all of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Aug. 14, 1995, Ser. No. 514,896

Int. Cl.⁶ H01M 4/58

U.S. Cl. 429—218

15 Claims

1. In the method of making a secondary, lithium-ion cell including the principle step of positioning an anode and a cathode opposite each other with a non-aqueous, lithium-ion conducting electrolyte therebetween wherein said anode comprises a reversible-lithium-intercalateable carbon and said cathode comprises a reversible-lithium-intercalateable material, the improvement comprising, prior to said positioning, heating said carbon in the presence of oxygen for a time and at a temperature sufficient to selectively oxidize, gasify and remove from said carbon at least those highly reactive carbon atoms therein that would otherwise decompose said electrolyte and/or entrap lithium in said cell.

5,587,258

GALVANIC CELL HAVING IMPROVED CATHODE

Gerd Fehrmann, Pirna; Rainer Frömmel, Dresden, and Rüdiger Wolf, Rabenau, all of Germany, assignors to Litronik Batterietechnologie GmbH & Co., Pirna, Germany

Filed Jan. 5, 1996, Ser. No. 583,611

Int. Cl.⁶ H01M 4/56; 4/50

U.S. Cl. 429—228

12 Claims



1. A galvanic cell which has a high energy density, a high power density, a low self discharge, and an open circuit voltage which is related to state of discharge, and which is useful for supplying electrical power to a device which has a large current consumption and which is implantable in a living being including a defibrillator and a nerve stimulator, the galvanic cell comprising:
a casing;

a cathode unit having at least one electrode and, when a plurality of electrodes are provided, the electrodes of the plurality are separated and are electrically connected to one another, which at least one electrode of the cathode unit is comprised of a mixture of at least one metal oxide and at least one lead compound, which mixture is selected from the group consisting of:

- (a) a mixture of CrO_x in which x ranges between 2.5 and 2.7 and at least one lead compound which is selected from the group consisting of PbCrO_4 , PbMoO_4 , and PbO ;

- (b) a mixture of CrO_x in which x ranges between 2.5 and 2.7, MnO_2 , and at least one lead compound which is selected from the group consisting of PbCrO_4 , PbMoO_4 , and PbO ;

- (c) a mixture of MnO_2 and a lead compound which is PbO ;

an anode unit having at least one electrode comprised of an alkali metal and, when a plurality of electrodes are provided, the electrodes of the plurality are separated and are electrically connected to one another, which at least one electrode of the anode unit is placed one of near the at least one electrode of the cathode unit or between respective electrodes of the cathode unit; and

an organic electrolyte comprised of a mixture of (a) at least one carbonate selected from the group consisting of ethylene carbonate and propylene carbonate, (b), 2-dimethoxyethane, and (c) a conducting salt.

5,587,259

METAL-AIR CATHODE AND CELL HAVING A HARDENED CURRENT COLLECTING SUBSTRATE


Robert B. Dopp, Madison; John E. Oltman, Mount Horeb, and Joseph L. Passaniti, Madison, all of Wis., assignors to Rayovac Corporation, Madison, Wis.

Filed Mar. 9, 1994, Ser. No. 208,450

Int. Cl.⁶ H01H 2/20

U.S. Cl. 429—233

31 Claims



1. A current collecting substrate in an air cathode of an electrochemical metal-air cell having a metal anode and an alkaline electrolyte, the substrate comprising:

- (a) a metal structure having a mean hardness exceeding about 110 micro-Vickers and capable of being connected to electrical circuitry, the metal of the structure being suitable for operation in the alkaline electrolyte.

5,587,260

METHOD OF FORMING A FUNCTIONAL FILM

Susumu Miyazaki, Kitasouma-gun; Tsuyoshi Nakano, Funabashi; Nobuya Niizaki, Yokohama; Junichi Yasukawa, Chigasaki, and Miki Matsumura, Tokyo, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Sep. 13, 1994, Ser. No. 304,950


Claims priority, application Japan, Sep. 13, 1993, 5-227488

Int. Cl.⁶ G03F 9/00

U.S. Cl. 430—7

7 Claims

1. A method of forming a functional film micropatterned on a substrate comprising:



- (a) a step of forming a positive or negative-type photoresist film on the entire surface of a substance having a conductive layer thereon;
- (b) an exposure step of irradiating light to the surface of the already formed positive or negative-type photoresist film through overlapped photo-masks having patterns that allow the film to cover the substrate except for a predetermined portion for forming a functional film in the next developing step;
- (c) a developing step of removing the photoresist film from the predetermined portion for forming a functional film;
- (d) a step of forming a functional film on the substrate in the portion where said photoresist film is removed, by electrodeposition with said conductive layer as one electrode; and
- (e) a step of removing the positive or negative-type photoresist film remaining after the step (c);
- wherein a step of heat-treating the films remaining after the developing step (c) at 80°-280° C. for 5-60 minutes is included before the step (d).

5,587,261

UV/EB CURABLE BUTYL COPOLYMERS FOR LITHOGRAPHIC AND CORROSION-RESISTANT COATING

Jay D. Audett, Brown Deer, Wis., and Kenneth O. McElrath, Waterloo, Belgium, assignors to Exxon Chemical Patents Inc., Wilmington, Del.

Division of Ser. No. 298,450, Oct. 27, 1994, which is a division of Ser. No. 982,104, Nov. 24, 1992, Pat. No. 5,376,503, which is a continuation of Ser. No. 631,610, Dec. 20, 1990. This application Jun. 7, 1995, Ser. No. 473,858

Int. Cl.⁶ G03C 3/00; G03F 7/00; B41N 1/00; 6/00

U.S. Cl. 430-18

1 Claim

1. An article having printing elements made by:
- (a) coating at least a portion of a surface of an article with a composition comprising a random copolymer of an isoocten of 4 to 7 carbon atoms and para-alkylstyrene comonomer, said isoocten comprising 10 to 99.5 weight % of said copolymer and said para-alkylstyrene comprises 0.5 to 90 weight % of said copolymer, wherein about 0.5 to 55 weight % of said copolymer comprises para-alkylstyrene monomers having a photoinitiator substituted on the pendent alkyl group, said copolymer having a substantially homogenous compositional distribution;
- (b) selectively exposing said surface to gamma, UV, electron beam, visible, or microwave radiation to crosslink the copolymer in the area exposed to said radiation; and
- (c) removing the uncrosslinked copolymer to develop a pattern of the crosslinked copolymer.

5,587,262
PHOTOCONDUCTIVE IMAGING MEMBERS
Heldi Pinkney, Hamilton; Ah-Mee Hor, and Zoran D. Popovic, both of Mississauga, all of Canada, assignors to Xerox Corporation, Stamford, Conn.

Filed Oct. 2, 1995, Ser. No. 537,015

Int. Cl.⁶ G03G 5/047

U.S. Cl. 430-54

27 Claims

1. A photoconductive imaging member comprised of a supporting substrate, a hydroxygallium phthalocyanine photogenerator layer, a charge transport layer, a photogenerator layer comprised of a mixture of bisbenzimidazo(2,1-a:1',2'-b)anthra(2,1,9-def:6,5,10-d'e'f')diisoquinoline-6,11-dione and bisbenzimidazo(2,1-a:2',1'-a)anthra(2,1,9-def:6,5,10-d'e'f')diisoquinoline-10, 21-dione, and as a top layer a charge transport layer.

5,587,263

ELECTROPHOTOGRAPHIC PHOTORECEPTOR USING TRIARYLAMINE COMPOUNDS

Katsumi Nukada; Akira Imai, and Ryosaku Igarashi, all of Minami Ashigara, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan

Division of Ser. No. 215,582, Mar. 22, 1994, Pat. No.


5,495,049. This application May 18, 1995, Ser. No. 444,274
Claims priority, application Japan, Mar. 22, 1993, 5-85153;
May 17, 1993, 5-136927; Jul. 7, 1993, 5-191821

Int. Cl.⁶ C07C 211/54; 211/60; 211/61

U.S. Cl. 430-56

21 Claims

1. An electrophotographic photoreceptor comprising a photosensitive layer containing as a charge transport material at least one triarylamine compound represented by formula (I)



wherein Ar₁ and Ar₂ each represents a phenyl group, a phenyl group substituted with an alkyl group having 1-5 carbon atoms or an alkoxy group having 1-5 carbon atoms or a condensed ring group that is a naphthyl group, an anthracenyl group, a pyrenyl group, a fluorenyl group or any of a naphthyl group, an anthracenyl group, a pyrenyl group, or a fluorenyl group substituted with an alkyl group having 1-5 carbon atoms.

5,587,264

ELECTROSTATIC INFORMATION RECORDING MEDIUM AND ELECTROSTATIC INFORMATION RECORDING AND REPRODUCING METHOD

Masayuki Iijima; Kyoji Dantani; Hiroyuki Obata; Makoto Matsuo; Minoru Utsumi, and Seiji Take, all of Tokyo, Japan, assignors to Dai Nippon Printing Co. Ltd., Tokyo, Japan
Continuation of Ser. No. 981,141, Nov. 24, 1992, abandoned, which is a division of Ser. No. 613,689, Nov. 15, 1990, abandoned. This application Jun. 5, 1995, Ser. No. 462,563


Claims priority, application Japan, Mar. 16, 1989, 1-064264;
Mar. 18, 1989, 1-066793; Mar. 18, 1989, 1-066796; Mar. 18, 1989, 1-067242; Mar. 18, 1989, 1-067248

Int. Cl.⁶ G03G 15/02

U.S. Cl. 430-57

14 Claims

1. An electrostatic information recording and reproducing method, characterized in that a photosensitive member having photoconductive layer with electrode on its front is placed face-to-face to an electrostatic information recording medium made of liquid crystal polymer layer and furnished with an electrode on backside, that exposure is performed without heating or by heating the electrostatic information recording medium up to the liquid crystal phase range with voltage applied between two electrodes, that the electrostatic information recording medium is separated



wherein each of the drums satisfying the following inequalities at the same time is used:

$$30^\circ \leq \theta \leq 80^\circ, \text{ and } l \leq 0.3 \text{ mm}$$

where θ represents an angle between an extension line of the chamfered face formed at an edge of the drum and an extension line of a circular end of the drum, and l represents a distance between an intersecting point of the circular end and the chamfered face of the drum, and an extension line of a circumferential surface of the drum.

5,587,267

METHOD OF FORMING PHOTORESIST FILM EXHIBITING UNIFORM REFLECTIVITY THROUGH ELECTROSTATIC DEPOSITION

Mario Garza, Sunnyvale, Calif., assignor to LSI Logic Corporation, Milpitas, Calif.

Division of Ser. No. 189,574, Jan. 31, 1994, which is a division of Ser. No. 907,757, Jun. 29, 1992, Pat. No. 5,330,883. This application Jun. 5, 1995, Ser. No. 461,118

Int. Cl.⁶ G03C 1/52

5 Claims

5. A method of forming a photoresist film of uniform thickness over an underlying semiconductor substrate to thereby form a photoresist film of uniform reflectivity on said semiconductor substrate which comprises the steps of:

- forming a powder of a photoresist material;
 - electrostatically charging said powder of photoresist material at one potential;
 - electrostatically charging a semiconductor substrate at an opposite potential; and
 - spraying a uniform thickness of said powder of photoresist material onto said semiconductor substrate;
- to thereby form a photoresist film of uniform thickness on said semiconductor substrate which will therefore exhibit uniform reflectivity.

5,587,268

THERMAL TRANSFER IMAGING PROCESS

Geert Defieuw, Kessel-Lo; Wilhelmus Janssens, Aarschot, and Luc Vanmaele, Lochrist, all of Belgium, assignors to Agfa-Gevaert N.V., Mortsel, Belgium

Filed Mar. 8, 1995, Ser. No. 400,343

Claims priority, application European Pat. Off., Mar. 25, 1994, 94200796

Int. Cl.⁶ G03C 8/00

U.S. Cl. 430-200

4 Claims

1. A thermal imaging process for producing a high gradation image comprising the steps of:

- bringing a donor layer of a donor element into face to face relationship with a receiving layer of a receiving element to form an assemblage,
 - image-wise heating the assemblage, thereby causing image-wise transfer of an amount of a thermotransferable reducing agent and a thermotransferable dye to said receiving element, the amount of said thermotransferred reducing agent being proportional to the amount of heat supplied,
 - separating said donor element from said receiving element, and
 - overall heating said receiving element, wherein
- (i) said donor element comprises on a support, (a) a donor layer comprising a binder and a thermotransferable reducing agent which is capable of reducing a silver source to metallic silver upon heating and a thermotransferable dye, and (b) a heat resistant layer provided on the side of the support opposite to the side having said donor layer, and

5,587,266

MANUFACTURING METHOD FOR AN ELECTROPHOTOGRAPHIC PHOTORECEPTOR

Junji Ujihara, and Akira Ohira, both of Hachioji, Japan, assignors to Konica Corporation, Tokyo, Japan
Filed Aug. 31, 1995, Ser. No. 521,975

Claims priority, application Japan, Sep. 6, 1994, 6-212675

Int. Cl.⁶ G03G 5/04

U.S. Cl. 430-133

4 Claims

1. A method of manufacturing an electrophotographic photoreceptor drum, the method comprising the steps of:

- aligning cylinder shafts of a plurality of cylindrical drums with each other, each drum having a chamfered face formed at an end thereof;
- contacting circular ends of the drums with each other and stacking the drums on each other; and
- continuously coating photoreceptor material on circumferential surfaces of the drums while inserting the drums into a ring-shaped coater and moving the ring-shaped coater vertically from an upper portion to a lower portion of the stacked drums,

(ii) said receiving element comprises said receiving layer on a support, said receiving layer comprising a silver source which is capable of being reduced by heat in the presence of a reducing agent.

5,587,269

THERMAL TRANSFER IMAGING PROCESS AND DONOR ELEMENT FOR USE THEREIN

Geert Defieuw, Kessel-Lo, Belgium, assignor to Agfa-Gevaert N.V., Mortsel, Belgium

Filed Mar. 8, 1995, Ser. No. 400,346

Claims priority, application European Pat. Off., Mar. 25, 1994, 94200788

Int. Cl.⁶ G03C 8/40; 8/44

U.S. Cl. 430—203

8 Claims

1. A thermal imaging process comprising, in order, the steps of:
 - a) bringing a donor layer of a donor element into face to face relationship with a receiving layer of a receiving element to obtain an assemblage;
 - b) image-wise heating the assemblage, thereby causing image-wise transfer of an amount of a thermotransferable reducing agent to said receiving element in accordance with the amount of heat supplied by said thermal head;
 - c) separating said donor element from said receiving element; and
 - d) overall heating said receiving element, wherein
 - (i) said donor element comprises said donor layer on a support, wherein said donor layer comprises a binder, and thermotransferable reducing agent which is capable of reducing a silver source to metallic silver upon heating, and particles protruding from the surface of said donor layer, wherein
 - (ii) said receiving element comprises said receiving layer on a support, and said receiving layer comprises a silver source which is capable of being reduced by means of heat in the presence of a reducing agent.

which is capable of being reduced by means of heat in the presence of a reducing agent.

5,587,271

DAMPENING SOLUTION FOR PRINTING WITH A LITHOGRAPHIC PRINTING PLATE AND A METHOD FOR PRINTING THEREWITH

Franciscus Heugebaert, Mortsel, and Johan Van Hunsel, Berchem, both of Belgium, assignors to Agfa-Gevaert, N.V., Mortsel, Belgium

Filed Oct. 2, 1995, Ser. No. 538,029

Claims priority, application European Pat. Off., Oct. 18, 1994, 94203008

Int. Cl.⁶ G03C 8/06; G03F 7/07

U.S. Cl. 430—204

5 Claims

1. A method for lithographic printing comprising the following steps:
 - preparing a lithographic printing plate according to the silver salt diffusion transfer process by (1) image-wise exposing an imaging element comprising on a support a photosensitive layer comprising a silver halide emulsion and an image receiving layer containing physical development nuclei in water permeable relationship with said emulsion layer, (2) developing said imaging element in the presence of developing agent(s) and silver halide solvent(s) using an alkaline processing liquid and (3), if said emulsion layer is overlying said image receiving layer, removing the layers overlying said image receiving layer;
 - mounting said lithographic printing plate to a lithographic printing press; and
 - printing while supplying to said lithographic printing plate a dampening solution as used on the printing plate contains less than 1.0 g/l of a transparent pigment of a non-water swellable inorganic fine particle with an average grain diameter of less than 0.1 μm and at least 0.35 g/l of a clay incorporating an inorganic polyphosphate peptiser.

5,587,270

THERMAL IMAGING PROCESS AND AN ASSEMBLAGE OF A DONOR AND RECEIVING ELEMENT FOR USE THEREIN

Wilhelmus Janssens, Aarschot; Jan Van den Bogaert, Schilde; Luc Vanmaele, Lochristi, and Geert Defieuw, Kessel-Lo, all of Belgium, assignors to Agfa-Gevaert N.V., Mortsel, Belgium

Filed Mar. 8, 1995, Ser. No. 400,349

Claims priority, application European Pat. Off., Mar. 10, 1994, 94200613.1

Int. Cl.⁶ G03C 8/40; 8/18

U.S. Cl. 430—203

6 Claims

1. A thermal imaging process comprising, in order, the steps of:
 - a) bringing a donor layer of a donor element into face to face relationship with a receiving layer of a receiving element to obtain an assemblage;
 - b) image-wise heating the assemblage, thereby causing image-wise transfer of an amount of said thermally transferrable reducing agent from said donor layer to said receiving layer in accordance with an amount of heat supplied during the image-wise heating;
 - c) separating said donor element from said receiving element; and
 - d) overall heating said receiving element, wherein
 - (i) said donor element comprises said donor layer on a support, wherein said donor layer comprises a binder and said thermally transferrable reducing agent which is capable of reducing a silver source to metallic silver upon heating, and wherein an oxidized form of said reducing agent is colored or capable of forming a color; and
 - (ii) said receiving element comprises said receiving layer on a support, said receiving layer comprising a silver source

PROCESS FOR PREPARING MULTIPLE COLOR PROOFS

Mario Grossa; Udo D. Bode, both of Dreieich; Manfred Sondergeld, Muhlheim/Main; Karl-Helz Wiedenmann, Rodermark, all of Germany; Ronald J. Coners; Steven M. Kalo, both of Towanda, Pa., and Ashok K. Kudva, Hendersonville, N.C., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Dec. 7, 1995, Ser. No. 569,043

Claims priority, application Germany, Dec. 27, 1994, 44 46 869.5

Int. Cl.⁶ G03C 11/12; G03F 7/28; 7/42

U.S. Cl. 430—257

10 Claims

1. A process for preparing images on multiple receptors comprising:
 - a) image-wise exposing a photopolymerizable layer to produce an exposed layer having tacky and nontacky areas thereon;
 - b) bringing the exposed layer into contact with a pigmented transfer layer on a support, wherein the exposed layer is adjacent the pigmented transfer layer;
 - c) peeling off the support, whereby the pigmented transfer layer is transferred onto the tacky areas of the exposed layer and is removed from the nontacky areas of the exposed layer to form a toned layer;
 - d) bringing the toned layer into contact with a temporary support;
 - e) removing the temporary support, whereupon the pigmented transfer layer adhering to the tacky areas of the photopolymerizable layer is transferred onto the temporary support;
 - f) bringing the temporary support, having thereon the pigmented transfer layer, into contact with an image receptor;

- g) removing the temporary support, whereupon the pigmented transfer layer adhering to the temporary support is transferred onto the image receptor; and
- h) repeating steps b) through g) at least once, whereby, in each instance, a new pigmented transfer layer, a new temporary support, and a new image receptor are used to form an image on the image receptors.

10 and 1 to 75% by weight of another α,β-ethylenically unsaturated compound other than the above two mentioned monomers; and

- (b) a photoactivator which generates an acid in response to a light irradiation.

5,587,275

PHOTOSENSITIVE RESIN COMPOSITION AND A PROCESS FOR FORMING A PATTERNED POLYIMIDE FILM USING THE SAME

Hidetoshi Kato, Matsuida, Japan, assignor to Shin-Etsu Chemical Co., Ltd., Tokyo, Japan


Filed Jul. 5, 1995, Ser. No. 498,225

Int. Cl.⁶ G03F 7/038


U.S. Cl. 430—283.1

11 Claims

1. A photosensitive resin composition comprising:
 - (A) a polyimide precursor comprised of a structural unit represented by the following general formula (1):



wherein X is a tetravalent organic group having an aromatic ring, Y is a divalent organic group having an aromatic ring or a divalent organic group having a siloxane bond, and the two Z are each a hydrogen atom or a monovalent organic group having an acyloxy group or a methacryloxy group represented by the following general formula (2):



wherein R is a hydrogen atom or a methyl group, provided that the content of the monovalent organic group represented by said general formula (2) is at least 30 mole % of the total Z contained in the polyimide precursor; and
(B) a member selected from the group consisting of a sensitizer, a photopolymerization initiator and a combination thereof.

5,587,274

RESIST COMPOSITION

Takahito Kishida, Yao; Akira Matsumura, Hirakata, and Atsushi Kawakami, Suita, all of Japan, assignors to Nippon Paint Co., Ltd., Osaka-fu, Japan

Continuation-in-part of Ser. No. 77,377, Jun. 17, 1993, abandoned. This application Dec. 7, 1994, Ser. No. 350,733

Claims priority, application Japan, Jun. 19, 1992, 4-160840

Int. Cl.⁶ G03C 1/73


U.S. Cl. 430—270.1

5 Claims

1. A positive type resist composition which comprises:
 - (a) a polymer having an acid value of 2 to 200, prepared from 20 to 94% by weight of a t-butyl ester of an α,β-ethylenically unsaturated carboxylic acid, 5 to 79% by weight of a (meth)acrylate of the formula:



wherein R₁ is hydrogen or a methyl group, R₂ represents



wherein R₄ represents hydrogen or an alkyl group, R₅ represents hydrogen or an alkyl group, R₆ represents a branched or straight chain alkylene group, provided that a total carbon number of R₄, R₅ and R₆ is 1 to 5, R₃ is an alkyl group having 1 to 6 carbon atoms, an aryl group or an aralkyl group and n is an integer of 1 to

5,587,276

IMAGE FORMATION METHOD

Kazunobu Katoh, Kanagawa, Japan, assignor to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed Jan. 23, 1996, Ser. No. 590,195

Claims priority, application Japan, Jan. 23, 1995, 7-008094

Int. Cl.⁶ G03C 5/29

U.S. Cl. 430—440

3 Claims

1. A method for forming a silver halide photographic image comprising developing a silver halide photographic material with a developing solution containing an ascorbic acid developing agent, substantially free from hydroquinone and having a pH of 8.5 to 11.0, said silver halide photographic material comprising a support which comprises a syndiotactic styrenic polymer and a silver halide emulsion layer provided on at least one surface of the support, said silver halide emulsion layer or another hydrophilic colloidal layer containing a hydrazine derivative, and the total amount of gelatin on the surface on which said silver halide emulsion layer is provided being 2.5 g/m² or less.

5,587,277

SOLID PROCESSING COMPOSITION FOR SILVER HALIDE LIGHT-SENSITIVE PHOTOGRAPHIC MATERIAL AND METHOD OF PROCESSING BY THE USE THEREOF

Hiroshi Yamashita, and Yutaka Ueda, both of Hino, Japan, assignors to Konica Corporation, Tokyo, Japan
Continuation of Ser. No. 294,580, Aug. 23, 1994. This application Jul. 11, 1995, Ser. No. 500,644

Claims priority, application Japan, Aug. 25, 1993, 5-210651
Int. Cl.⁶ G03C 5/29

U.S. Cl. 430—458

7 Claims



1. A solid photographic processing composition in tablet form for a silver halide photographic light sensitive material comprising a developing agent, bleaching agent, fixing agent or imaging stabilizing agent, wherein said solid composition has a bulk density of 1.0 to 2.5 g/cm³, and substantially the whole of the surface of said solid processing composition is covered with a layer containing a compound in an amount of 0.5 to 5% by weight based on the total weight of the composition, said compound being

a polyalkylene glycol having an average molecular weight of 2000 to 20000, and wherein said solid processing composition in tablet form has a weight of 0.5 to 50 g per a tablet.

5,587,278

POLYESTER PHOTOGRAPHIC SUPPORT

Fumio Kawamoto, Kanagawa, Japan, assignor to Fuji Photo Film Co., Ltd., Kanagawa, Japan
Filed Dec. 10, 1993, Ser. No. 164,962

Claims priority, application Japan, Dec. 11, 1992, 4-331928
Int. Cl.⁶ G03C 1/795

U.S. Cl. 430—533

11 Claims

1. A polyester support prepared by the step of
(1) subjecting a polyester film to bulk rolling and heating the bulk rolled polyester film to a temperature of from 50° C. to the glass transition point of the polyester film for 0.1 to 1500 hours, or

(2) subjecting a polyester film to bulk rolling at a temperature from 50° C. to the glass transition point of the polyester film for 0.1 to 1500 hours,

resulting in the polyester support,

wherein the polyester film comprises a polyester obtained by condensation polymerization of a diol and at least naphthalene dicarboxylic acid or an ester derivative thereof,

wherein the glass transition point of the polyester film is 90° to 200° C., and

wherein the step of bulk rolling has a start tension of 3 to 75 kg/m per unit width of the polyester film and an end tension of 3 to 75 kg/m per unit width of the polyester film.

5,587,279

SILVER HALIDE EMULSION AND METHOD OF PREPARING THE SAME

Hiroyuki Mifune, Junichi Yamanouchi, and Shoji Ishiguro, all of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Nov. 14, 1991, Ser. No. 791,402

Claims priority, application Japan, Nov. 14, 1990, 2-308062; Nov. 29, 1990, 2-331419

Int. Cl.⁶ G03C 1/035

U.S. Cl. 430—567

7 Claims



1. A silver halide photographic emulsion consisting essentially of silver halide grains which have a silver chloride content of at least 60 mol % and an octahedral crystal form constructed of 48 triangular faces, every one of which contacts convexly with each of two of its adjoining faces to form a line and concavely with the one remaining adjoining face to form a line.

5,587,280

LIGHT-SENSITIVE SILVER HALIDE EMULSION AND PHOTOGRAPHIC LIGHT-SENSITIVE MATERIAL USING THE SAME

Hideo Ikeda, Sadanobu Shuto, and Takefumi Hara, all of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Continuation of Ser. No. 195,438, Feb. 14, 1994, abandoned.

This application May 19, 1995, Ser. No. 444,677

Claims priority, application Japan, Feb. 12, 1993, 5-046162
Int. Cl.⁶ G03C 1/035

U.S. Cl. 430—567

9 Claims

1. A light-sensitive silver iodobromide emulsion comprising tabular silver iodobromide grains having twin planes, where the number of said twin planes is two, said grains having an equivalent-circle diameter/thickness ratio of 8 to 100, wherein a variation coefficient of a grain size distribution of said tabular silver iodobromide grains is 1% to 20%, and not less than 50% by number of all of said tabular silver iodobromide grains are grains whose ratio, b/a, of a distance, a, between said two twin planes of said tabular silver iodobromide grain to a grain thickness, b, is $1.5 \leq b/a < 5$.

5,587,281

METHOD FOR PRODUCING SILVER HALIDE GRAIN AND SILVER HALIDE EMULSION USING THE GRAIN

Mitsuo Saitou, Junichi Yamanouchi, and Yoichi Hosoya, all of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Jul. 13, 1995, Ser. No. 501,959

Claims priority, application Japan, Jul. 14, 1994, 6-184128
Int. Cl.⁶ G03C 1/047; 1/043; 1/035

U.S. Cl. 430—567

9 Claims

1. A method for producing silver halide grains containing tabular grains having a thickness of from 0.02 to 0.3 μ m and an aspect ratio (diameter/thickness) of from 2 to 50 at a proportion of from 75 to 100% of the total projected area of silver halide grains, which



comprises at least nucleation, ripening and growing steps in a dispersion medium solution consisting of water and a dispersion medium, wherein gelatin having the following characteristics (a) occupies from 30 to 100 wt % of said dispersion medium used in said growing step:

characteristics (a)

the relation between the number percentage of a chemically modified —NH₂ group selected from a secondary amino group, a tertiary amino group, and a deaminated product in said gelatin and the methionine content of said gelatin is in the region a₁ depicted in FIG. 1.

5,587,282

SILVER HALIDE PHOTOGRAPHIC MATERIAL

Haruyasu Nakatsugawa, Masakazu Yoneyama, and Shigeharu Urabe, all of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Jul. 19, 1995, Ser. No. 504,348

Claims priority, application Japan, Jul. 28, 1994, 6-177183

Int. Cl.⁶ G03C 1/043

U.S. Cl. 430—637

3 Claims

1. A silver halide photographic material comprising a support having thereof at least one light-sensitive silver halide emulsion layer, wherein the silver halide emulsion is produced in the presence of a polyalkylene oxide group-containing organopolysiloxane, wherein the polyalkylene oxide group has at least four repeating units.

5,587,283

COMBUSTION PROCESS

Pierre Karinthi, Jouy en Josas; Marc Buffenoir, Voisins le Bretonneux, both of France, and Dominique Belot, Tokyo, Japan, assignors to L'Air Liquide, Societe Anonyme pour l'Etude et l'Exploitation des Procédés Georges Claude, Paris Cedex, France


Filed Sep. 9, 1994, Ser. No. 303,505

Claims priority, application France, Sep. 9, 1993, 93 10703

Int. Cl.⁶ F23C 7/00

U.S. Cl. 431—10

8 Claims



1. In a combustion process comprising the steps of injecting, via a burner (1), at least one combustible gas flow and at least one flow of oxygenated combustion supporting gas; the improvement

wherein the combustion supporting gas is oxygen which is injected in liquid and gaseous phases.

5,587,284

PERIODONTAL PROBE TIP AND METHOD FOR USING

Steven J. Brattesani, 3051 Laguna St., San Francisco, Calif. 94123


Division of Ser. No. 148,159, Nov. 4, 1993, Pat. No. 5,423,677.

This application May 11, 1995, Ser. No. 438,685

Int. Cl.⁶ A61C 19/04; 1/00; 3/00; 5/00

U.S. Cl. 433—72

15 Claims



1. A dental probe tip for diagnosing periodontal disease, comprising:

- (a) attachment means for coupling to a source of light;
- (b) probing means, joined to said attachment means, for being illuminated by said source of light and for determining the depth of a periodontal pocket;
- (c) said probing means including color indicator means for being illuminated by said source of light and for providing a relative indication of degree of periodontal disease;
- (d) said probing means including an illuminating probing ball; and
- (e) said color indicator means including a plurality of colored bands separated by translucent graduations into measured increments of predetermined length.

5,587,285

GENERATION SEROLOGICAL ASSAY FOR MONITORING HIV EXPOSURE

Miles W. Cloyd, Galveston, Tex., and Keith M. Ramsey, Mobile, Ala., assignors to University of Texas System, Austin, Tex.

Division of Ser. No. 829,352, Jan. 31, 1992, abandoned. This application Oct. 26, 1993, Ser. No. 143,168

Int. Cl.⁶ C12Q 1/70; G01N 33/574; 33/567; 33/564

U.S. Cl. 435—5

13 Claims

1. An immunological method for detecting early human anti-HIV antibodies in a biological sample comprising the steps of: preparing a target antigen with preserved configurational integrity of HIV envelope antigen that binds early anti-HIV antibody;

contacting a quantity of the target antigen with a biological sample to form a mixture;

incubating the mixture to facilitate binding between the target antigen and any early anti-HIV antibodies present in said biological sample specific for the target antigen to form a reaction mixture; and

adding a labeled anti-HIV secondary antibody to label early antibody bound to the target antigen in the reaction mixture to produce labeled antibody target antigen complexes; wherein the presence of labeled antibody-target antigen complexes provide an early indication of HIV exposure, and which biological sample is negative for early anti-HIV antibody to denatured HIV antigen by Western Blot or ELISA.

5,587,286

METHODS AND KITS FOR DETECTION OF CELLS IN FOOD MATERIALS

Edward E. Pahuski, Marshall; Randall L. Dimond, Madison, both of Wis.; John H. Priest, Everett, Wash.; Lisa Zandt, Madison, Wis.; Kathleen K. Stebnitz, Shorewood, Wis., and Leopoldo G. Mendoza, Madison, Wis., assignors to Promega Corporation, Madison, Wis.

Continuation-in-part of Ser. No. 547,981, Jul. 2, 1990, abandoned. This application Jan. 11, 1993, Ser. No. 3,242

Int. Cl.⁶ C12Q 1/02; 1/24; 1/68; C12N 1/02

U.S. Cl. 435—6

24 Claims

1. A method for detecting the presence of cells having nucleic acid that comprises a preselected target segment, in a culture or extract of a food material, said method comprising obtaining a pellet of cells from the culture or extract by combining an aliquot of the culture or extract with an aqueous suspension of a micro-particulate carrier to form a clearing solution and centrifuging the clearing solution to form a cell pellet, provided that, if said culture or extract of a food material is a culture and is a liquid milk sample, said clearing solution further comprises a chelating agent; suspending cells from the pellet so obtained in a first solution and treating the first solution to provide a second solution of nucleic acid from the cells for amplification without substantial isolation of nucleic acids of the cells from other constituents of the cells; subjecting the nucleic acid of the second solution to a nucleic acid amplification process to produce a pre-determined, amplified nucleic acid segment only if the pre-selected target segment is present in said cells suspended from said pellet; and assaying nucleic acid after the amplification process for the presence of said pre-determined, amplified segment.

5,587,287

THERMOSTABLE POLYMERASE SPECIFIC ANTIBODY-CONTAINING DNA AMPLIFICATION COMPOSITION AND KIT

Edward R. Scalice; David J. Sharkey, both of Rochester; Kenneth G. Christy, Jr., North Chili; Theodore W. Esders, Webster, and John L. Daiss, Rochester, all of N.Y., assignors to Johnson & Johnson Clinical Diagnostics, Inc., Rochester, N.Y.

Division of Ser. No. 958,144, Oct. 7, 1992, Pat. No. 5,338,671. This application Apr. 7, 1994, Ser. No. 224,218

Int. Cl.⁶ C12Q 1/68; 1/70; C12P 19/34; C07K 16/40

U.S. Cl. 435—6

18 Claims

1. A composition comprising a thermostable DNA polymerase, and a temperature sensitive inhibitor for said DNA polymerase, said inhibitor being an antibody which is specific to said thermostable DNA polymerase and which inhibits said thermostable DNA polymerase at a temperature T_1 which is less than about 85° C. such that enzymatic activity of said thermostable DNA polymerase is inhibited, and said inhibitor being irreversibly inactivated at a temperature T_2 which is greater than T_1 and is also greater than about 40° C., so that said thermostable DNA polymerase regains its enzymatic activity, wherein said thermostable DNA polymerase is stable at T_2 .

5,587,288

REGULATION OF EXOPROTEIN IN STAPHYLOCOCCUS AUREUS

Ambrose Cheung, New York, and Vincent A. Fischetti, West Hempstead, both of N.Y., assignors to The Rockefeller University, New York, N.Y.

Filed May 24, 1994, Ser. No. 248,505

Int. Cl.⁶ C12Q 1/68; C07K 13/00; C07H 21/02; 21/04

U.S. Cl. 435—6

3 Claims

1. An isolated, purified *S. aureus* staphylococcal accessory regulatory (sar) protein, consisting of the amino acid sequence shown in SEQ ID NO. 1.

5,587,289

ISOLATED NUCLEIC ACID MOLECULES WHICH ARE MEMBERS OF THE MAGE-XP FAMILY AND USES THEREOF

Christophe Lurquin, and Thierry Boon-Falleur, both of Brussels, Belgium, assignors to Ludwig Institute for Cancer Research, New York, N.Y.

Filed Mar. 14, 1995, Ser. No. 403,388

Int. Cl.⁶ C12Q 1/68; C07H 21/02; 21/04; C12N 15/70

U.S. Cl. 435—6

12 Claims

1. Isolated nucleic acid molecule which encodes a MAGE-Xp tumor rejection antigen precursor or is complementary to an isolated nucleic acid molecule which encodes a MAGE-Xp tumor rejection antigen precursor, wherein said isolated nucleic acid molecule (i) is not SEQ ID NO: 1, and (ii) hybridizes to at least one isolated nucleic acid molecule consisting of SEQ ID NO: 2, SEQ ID NO: 3, and SEQ ID NO: 4, under stringent conditions.

9. Method for identifying human X chromosome in a sample comprising contacting said sample with the isolated nucleic acid molecule of claim 1 under condition favoring hybridization of said isolated nucleic acid molecule to said X chromosome, and determining hybridization as a determination of said human X chromosome.

5,587,290

STRESS TOLERANT YEAST MUTANTS

Daniel Klionsky, Davis, Calif.; Helmut Holzer, and Monika Destruelle, both of Freiburg, Germany, assignors to The Regents of the University of California, Oakland, Calif.

Filed Jun. 26, 1995, Ser. No. 494,714

Int. Cl.⁶ C12Q 1/68; C12N 1/19; 15/31

U.S. Cl. 435—6

9 Claims

1. An isolated yeast mutant deficient in the expression of functional Ath1p gene product.

5,587,291

METHOD FOR THE DETERMINATION OF PLASMIN α_2 -ANTIPLASMIN COMPLEXES AND THE USE OF THIS METHOD AS A MEAN OF DETERMINING CHANGES IN THE FIBRINOLYTIC SYSTEM

Bernd Binder, Vienna, Austria, assignor to Berbi Gesellschaft m.b.H., Vienna, Austria

PCT No. PCT/AT93/00065, § 371 Date Dec. 10, 1993, § 102(e) Date Dec. 10, 1993, PCT Pub. No. WO93/21532, PCT Pub. Date Oct. 28, 1993

PCT Filed Apr. 14, 1993, Ser. No. 157,210

Claims priority, application Austria, Apr. 14, 1992, 772/92


Int. Cl.⁶ G01N 33/86; 33/577; 33/543

U.S. Cl. 435—7.4

5 Claims

3. A process for the quantitative determination of a plasmin- α_2 -antiplasmin (PAP) complex in a sample of serum or plasma using a sandwich ELISA system, which comprises the steps of: (a) obtaining the sample of serum or plasma containing the PAP complex;

- (b) providing monoclonal antibody MPW7AP produced by a hybrid continuous cell line having ECACC deposit no. 94072834 as a capture antibody, said capture antibody being immobilized on a solid phase and binding to a neoantigen on the PAP complex, said monoclonal antibody MPW7AP characterized by a specific reaction exclusively with the PAP complex but not with the respective separate components in a Western blot analysis;
- (c) capturing the PAP complex by contacting the sample of serum or plasma with said solid phase immobilized capture antibody;
- (d) contacting the captured PAP complex with a predetermined amount of an enzyme-labelled detecting antibody which specifically binds to the kringle 1-3 region of the plasminogen part of the PAP complex;
- (e) measuring the amount of enzyme label contained in the enzyme-labelled detecting antibody bound to the kringle 1-3 region of the plasminogen part of the captured PAP complex; and
- (f) comparing the amount of bound label in step (e) with the amount of bound label from a standard with a known amount of said PAP complex, also measured according to steps (b) through (e) in order to quantitatively determine the amount of PAP complex in the sample of serum or plasma.



- (c) calculating the predicted reactivity of the target receptor for said candidate compound by applying said formula of step (a) to the reactivity profile of the candidate compound determined in step (b) to predict the reactivity of the candidate compound with the target receptor.

5,587,292

DIAGNOSIS OF FUNGAL INFECTIONS WITH A CHITINASE

Roger A. Laine, and Wai C. J. Lo, both of Baton Rouge, La., assignors to Board of Supervisors of Louisiana State University and Agricultural and Mechanical College, Baton Rouge, La.

Continuation of Ser. No. 288,969, Aug. 10, 1994, abandoned, which is a continuation of Ser. No. 171,184, Dec. 21, 1993, abandoned, which is a continuation of Ser. No. 827,722, Jan. 29, 1992, abandoned, which is a continuation-in-part of Ser. No. 620,909, Dec. 3, 1990, abandoned, which is a continuation of Ser. No. 53,029, May 22, 1987, abandoned. This application Mar. 9, 1995, Ser. No. 402,772

Int. Cl.⁶ G01N 33/53; 33/532; 33/536; 33/569

U.S. Cl. 435—7.9

36 Claims

1. A method for detecting chitin in a sample comprising a human or animal tissue, or comprising a human or animal body fluid, said method comprising the steps of: (a) contacting the sample with a substance comprising Chitinase VPI; and (b) analyzing the sample for the presence of Chitinase VPI bound to chitin.

5,587,293

METHOD TO IDENTIFY BINDING PARTNERS

Lawrence M. Kauvar, San Francisco, and Hugo O. Villar, Newark, both of Calif., assignors to Terrapin Technologies, Inc., South San Francisco, Calif.

Filed Jan. 6, 1994, Ser. No. 177,673

Int. Cl.⁶ G01N 33/53

U.S. Cl. 435—7.21

9 Claims

1. A method to determine a predicted reactivity of a candidate compound with a target receptor, which method comprises the steps of: (a) providing a formula that represents a combination of the reactivity profiles of at least two members of a panel of reference receptors with respect to a first set of training compounds, which formula calculates a predicted profile that best matches the reactivity profile of the target receptor with respect to said first set of training compounds; (b) determining the reactivity of said at least two members of the panel of reference receptors with a candidate compound to obtain a reactivity profile for said candidate compound with respect to said members of said panel; and

5,587,294

METHOD AND KIT FOR MEASURING ENDOGENOUS CYTOKINES

Lawrence Tamarkin, Rockville, and Giulio F. Paciotti, Baltimore, both of Md., assignors to Assay Research, Inc., College Park, Md.

Continuation of Ser. No. 855,109, Mar. 20, 1992, abandoned, which is a continuation-in-part of Ser. No. 732,867, Jul. 19, 1991, abandoned. This application Oct. 28, 1994, Ser. No.

331,333

Int. Cl.⁶ G01N 33/543

12 Claims

1. A method of monitoring cytokine therapy in a human or animal, wherein the cytokine is able to bind a carrier molecule but is not IL-1, comprising the steps of: (1) obtaining a sample of body fluid from the human or animal without dissociation of the cytokine from bound carrier molecule, wherein the cytokine has been administered to the human or animal; (2) combining the sample of body fluid with, (a) an antibody capable of binding specifically to substantially all of the cytokine, whether free or bound to a carrier molecule, wherein the antibody is immobilized on a solid phase support, and (b) a labeled binding epitope of the cytokine, wherein the labeled binding epitope competes with the cytokine for antibody binding, to form an assay mixture; (3) incubating the assay mixture to allow the immobilized antibody to bind specifically to either the cytokine or the labeled binding epitope; (4) washing away unbound labeled binding epitope from the solid phase support; (5) detecting bound label on the solid phase support; (6) determining the amount of substantially all of the cytokine in the sample; and (7) comparing the amount of substantially all of the cytokine in the sample with a determination of substantially all of the cytokine in a previous sample of body fluid.

5,587,295

METHOD FOR PRODUCING AFFINO-ENZYMATIC COMPOUNDS AND VISUALIZING AGENT AND APPLICATION THEREOF

Jury M. Lopukhin; Viktor V. Zvesky; Alexander B. Rabovsky, all of Moscow, and Irina P. Andrianova, deceased, late of Moscow, all of Russian Federation, assignors to 2860601 Canada Inc., Toronto, Canada

Division of Ser. No. 146,974, Dec. 9, 1993, Pat. No. 5,489,510, which is a continuation-in-part of Ser. No. 54,954, Apr. 28, 1993, abandoned, which is a continuation of Ser. No. 296,448, Jan. 11, 1989, abandoned. This application Jul. 19, 1994, Ser. No. 276,914

Claims priority, application U.S.S.R., Jan. 19, 1988, 4357046 Int. Cl.⁶ C12Q 1/60; G01N 31/00

U.S. Cl. 435—11 8 Claims
1. An affino-enzymatic agent which comprises a binding agent A which binds with cholesterol in the surface of the skin and a visualizing agent B which is bound to the binding agent A to permit color detection of the affino-enzymatic agent.

5,587,296


REAGENT FOR ASSAYING GLUCOSE

Hiroaki Tsubota, and Reiko Shimada, both of Tokyo, Japan, assignors to Iatron Laboratories, Inc., Tokyo, Japan
PCT No. PCT/JP94/01395, § 371 Date Apr. 21, 1995, § 102(e) Date Apr. 21, 1995, PCT Pub. No. WO95/06136, PCT Pub. Date Mar. 2, 1995

PCT Filed Aug. 24, 1994, Ser. No. 424,284

Claims priority, application Japan, Aug. 25, 1993, 5-232371 Int. Cl.⁶ C12Q 1/54; 1/50; 1/32; G01N 33/48

U.S. Cl. 435—14 8 Claims



1. A reagent for assaying glucose in a sample consisting essentially of:

- a first reagent containing (i) at least one of glucokinase or hexokinase, (ii) glucose 6-phosphate dehydrogenase and (iii) adenosine 5'-triphosphate, and
 - a second reagent containing an oxidized form of nicotinamide adenine dinucleotide phosphate,
- wherein said first reagent has a pH of 7.5 to 9.5, said second reagent has a pH of 3 to 5, and both the first reagent and the second reagent are liquids.

5,587,297

METHOD FOR IDENTIFICATION OF DISEASE-SPECIFIC SURFACE COMPONENTS OF VASCULAR ENDOTHELIAL CELLS

Bruce S. Jacobson, Amherst, and Jan E. Schnitzer, Boston, both of Mass., assignors to The Regents of the University of California, Oakland, Calif.

Continuation-in-part of Ser. No. 928,912, Aug. 11, 1992, Pat. No. 5,281,700. This application Jan. 24, 1994, Ser. No. 185,433 Int. Cl.⁶ C12Q 1/02; G01N 33/48; C07K 1/18; 1/30

U.S. Cl. 435—29 16 Claims
1. A method for the identification of molecular components that are specific to tumor-associated vascular endothelium and are not

also present in rapidly proliferating non-tumor-associated vascular endothelium, the method comprising the following steps:

- isolating plasma membrane fractions from (i) tumor-associated vascular endothelium, (ii) non-proliferating, non-tumor-associated vascular endothelium, and (iii) rapidly proliferating, non-tumor-associated vascular endothelium, which fractions are substantially enriched in endothelial cell membrane constituents containing said components and substantially depleted of non-membrane endothelial cell constituents;
- purifying said components from said membrane fractions;
- resolving individual components on the basis of differences in at least one of molecular mass, charge, and hydrophobicity to generate a components profile;
- comparing the profiles of plasma membrane fractions derived from (i)–(iii);
- identifying resolved molecular components present in (i) and absent from both (ii) and (iii).


5,587,298
BIOREACTOR

Akira Horigane; Ushio Matsukura, both of Tsukuba, and Masayoshi Kamio, Tsuchiura, all of Japan, assignors to Director General of National Agriculture Research Center, Ministry of Agriculture, Forestry and Fisheries, Ibaraki, Japan

Filed Mar. 24, 1995, Ser. No. 409,446

Claims priority, application Japan, Mar. 2, 1995, 7-043316 Int. Cl.⁶ C12P 1/00; C12M 1/02

U.S. Cl. 435—41 9 Claims



1. A bioreactor for performing biological and biochemical reactions involving a substrate, a microorganism or a chemical substance, said bioreactor comprising:

- a reaction vessel for carrying out a reaction therein;
- a plurality of screws contained in said reaction vessel, said screws being provided in parallel relationship with a vertical axis of said reaction vessel and adjacent to an inner wall surface of the reaction vessel so that a vertical flow path for a reaction product is formed between the inner wall surface and the screws, each of said screws having a screw thread provided therearound with a threading sense opposite to that of an adjacent screw;
- means for rotating adjacent screws in a direction opposite to each other so that a reaction mixture provided in said reaction vessel is pumped in a vertical direction and causes a mixing of the reaction mixture and a milling of particles contained in the reaction mixture by attrition between the particles and forms a sieving action by passing small particles into the vertical flow path through opposing surfaces of adjacent screws;

5,587,301

DNA ENCODING A HYALURONAN RECEPTOR EXPRESSED IN HUMAN UMBILICAL VEIN ENDOTHELIAL CELLS

Phillip R. Hawkins, Mountain View; Craig G. Wilde, Sunnyvale, and Jeffrey J. Seilhamer, Los Altos Hills, all of Calif., assignors to Incyte Pharmaceuticals, Inc., Palo Alto, Calif.

Filed Mar. 10, 1995, Ser. No. 402,217

Int. Cl.⁶ C12N 5/10; 15/12

U.S. Cl. 435—69.1 5 Claims
1. An isolated DNA molecule comprising a nucleotide sequence encoding a human hyaluronan receptor (HR) having the amino acid sequence of SEQ ID NO: 2.

5,587,302

T CELL GROWTH FACTOR

Jacques Van Snick, Brussels; Catherine Uyttenhove, Chaumont-Gistoux, both of Belgium, and Richard J. Simpson, Melbourne, Australia, assignors to Ludwig Institute For Cancer Research, New York, N.Y.

Continuation-in-part of Ser. No. 408,155, Sep. 15, 1989, Pat. No. 5,157,112, which is a continuation-in-part of Ser. No. 246,482, Sep. 19, 1988, Pat. No. 5,208,218. This application

Jan. 8, 1990, Ser. No. 462,158

Int. Cl.⁶ C12N 15/12; 15/63

U.S. Cl. 435—69.5 20 Claims
1. An isolated nucleic acid molecule which encodes murine T cell growth factor P40 which supports interleukin-2 and interleukin-4 independent growth of T cells.

5,587,303

PRODUCTION PROCESS OF L-AMINO ACIDS WITH BACTERIA

Akiko Wakamoto; Osamu Takahashi; Keizo Furuhashi, and Akira Miura, all of Toda, Japan, assignors to Nippon Mining Company, Ltd., Tokyo, Japan

Continuation of Ser. No. 632,022, Dec. 21, 1990, abandoned, which is a continuation-in-part of Ser. No. 318,111, Mar. 2, 1989, abandoned. This application Jul. 20, 1994, Ser. No. 277,775

Claims priority, application Japan, Mar. 8, 1988, 63-052694; Mar. 8, 1988, 63-052695; Mar. 9, 1988, 63-055781; Jun. 14, 1990, 2-155661; Jul. 19, 1990, 2-191676; Jul. 19, 1990, 2-191677 Int. Cl.⁶ C12P 13/08; 13/06

U.S. Cl. 435—116 14 Claims
1. A process for producing an optically active α -amino acid in L-configuration represented by formula (I):



from the α -aminonitrile compound represented by formula (II):



wherein R is an isopropyl, butyl, or isobutyl group, which process comprises the steps of:

- contacting a microorganism having stereospecific nitrilase activity and selected from the group consisting of: Nocardopsis sp. B96-47, FERM BP-2423; Nocardopsis sp. A10-12, FERM BP-2422; Bacillus sp. B9-40, FERM BP-3992; and

a temperature controlling device for maintaining the reaction vessel at a predetermined temperature;

means for supplying the reaction vessel with at least one substrate; and

means for removing the reaction product from the vertical flow path.

5. A method for performing biological and biochemical reactions involving a substrate, a microorganism or a chemical substance, said method comprising the steps of:

- introducing at least one substrate into a reaction vessel of a bioreactor containing at least one member selected from the group consisting of one or more microorganisms and one or more chemical substances, said reaction vessel having a plurality of screws provided therein in a parallel relationship with a vertical axis of said reaction vessel and adjacent to an inner wall surface of the reaction vessel so that a vertical flow path for a reaction product is formed between the inner wall surface and the screws, each of said screws having a screw thread provided therearound with a threading sense opposite to that of an adjacent screw;

conducting at least one reaction in the bioreactor such that adjacent screws rotate in a direction opposite to each other so that a reaction mixture provided in said reaction vessel is pumped in a vertical direction and causes a mixing of the reaction mixture and a milling of particles contained in the reaction mixture by attrition between the particles and forms a sieving action by passing small particles into the vertical flow path through opposing surfaces of adjacent screws; and removing the reaction product from the vertical flow path.

5,587,299

ISOLATED NUCLEIC ACID MOLECULE CODING FOR FIBROBLAST ACTIVATION PROTEIN ALPHA AND USES THEREOF

Wolfgang J. Rettig, Biberach, Germany; Matthew J. Scanlan, New York, N.Y.; Pilar Garin-Chesa, Biberach, Germany, and Lloyd J. Old, New York, N.Y., assignors to Memorial Sloan-Kettering Cancer Center, New York, N.Y.

Filed Apr. 20, 1994, Ser. No. 230,491

Int. Cl.⁶ C12N 15/12; 15/19

U.S. Cl. 435—69.1 15 Claims
1. Isolated nucleic acid molecule which codes for mammalian FAP α having the amino acid sequence of SEQ ID NO: 2.

5,587,300

METHOD TO INCREASE REGULATORY MOLECULE PRODUCTION

James S. Malter, Madison, Wis., assignor to Wisconsin Alumni Research Foundation, Madison, Wis.

Filed Apr. 26, 1994, Ser. No. 233,130

Int. Cl.⁶ C12P 21/00; 21/02; C12N 15/00; 15/06

U.S. Cl. 435—69.1 25 Claims
1. A method to increase the production of a regulatory molecule in a population of transfected cells comprising:

- mutating a wild type cDNA sequence that encodes a first mRNA sequence for the regulatory molecule, wherein the mRNA includes a 3' untranslated region having a destabilizing element comprising an AUUUA sequence, to form a cDNA sequence that encodes a second mRNA sequence more stable than the first mRNA sequence, wherein the AUUUA sequence is replaced by AUGUA, AUAUA, GUGUG, AGGGA, GAGAG, or a combination thereof; and
- transfecting a cell population with the mutant cDNA sequence so that the production of the regulatory molecule by the cells is greater than the production of the regulatory molecule by a cell population with the wild type cDNA sequence.

Bacillus sp. A9-1, FERM BP-3991 and the α -ammonitrile in a reaction medium of an ammoniacal buffer solution at a pH in the range of 8-12 to obtain the optically active α -amino acid in L-configuration; and
(b) recovering the optically active α -amino acid in L-configuration thus obtained from the reaction medium.

5,587,304

CLONING AND EXPRESSION OF THE GENE OF THE MALOLACTIC ENZYME OF *LACTOCOCCUS LACTIS*

Pierre Barre, Saint Gely du Fesc; Sylvie Dequin, and Virginie Ansanay, both of Montpellier, all of France, assignors to Institut National de la Recherche Agronomique - I.N.R.A., Paris Cedex, France

PCT No. PCT/FR94/00589, § 371 Date Jan. 17, 1995, § 102(e) Date Jan. 17, 1995, PCT Pub. No. WO94/26879, PCT Pub. Date Nov. 24, 1994

PCT Filed May 18, 1994, Ser. No. 367,227

Claims priority, application France, May 18, 1993, 93 06003 Int. Cl.⁶ C12P 7/50; C12N 15/53; 15/70; 15/81

U.S. Cl. 435—139 15 Claims
1. An isolated nucleic acid fragment, which comprises a sequence of 1620 bp encoding the malolactic enzyme of *Lactococcus lactis*.

5,587,305

PASTEURELLA HAEMOLYTICA TRANSFORMANTS

Robert E. Briggs, Boone, and Fred M. Tatum, Ames, both of Iowa, assignors to The United States of America as represented by the Department of Agriculture, Washington, D.C., and Biotechnology Research and Development Corporation, Peoria, Ill.

Filed Dec. 6, 1993, Ser. No. 162,392

Int. Cl.⁶ C12N 15/09; 15/63

U.S. Cl. 435—172.1 16 Claims
1. A method for producing a mutation in a particular region of DNA of a *P. haemolytica* genome comprising the steps of: isolating said region of the genome from *P. haemolytica*; introducing a mutation into said region to form a mutated DNA region; methylating said mutated DNA region with a methylating enzyme which inhibits endonuclease cleavage at a recognition sequence selected from the group consisting of 5'-GATGC-3' and 5'-GCATC-3', to form methylated DNA; introducing said methylated DNA into a *P. haemolytica* cell to form transformants; and screening said transformants for those which have said mutation in said region on chromosomal DNA of said *P. haemolytica* cell.

5,587,306

PHOSPHOLIPASE C HOMOLOG

Phillip R. Hawkins, Mountain View, and Jeffrey J. Seilhamer, Los Altos Hills, both of Calif., assignors to Incyte Pharmaceuticals, Inc., Palo Alto, Calif.

Filed Apr. 10, 1995, Ser. No. 419,078

Int. Cl.⁶ C12N 9/20; 15/54; 15/70

U.S. Cl. 435—198 5 Claims
1. An isolated DNA molecule comprising a human phospholipase C homolog (plch) whose nucleotide sequence is shown in SEQUENCE ID NO. 1.

5,587,307

FEMA GENE OF *STAPHYLOCOCCUS EPIDERMIDIS*, FEMA PROTEIN, AND VECTORS AND MICROORGANISMS COMPRISING THE FEMA GENE

William E. Alborn, Jr., Carmel; JoAnn Hoskins, Indianapolis; Paul L. Skatrud, Greenwood, all of Ind., and Serhat Únal, Ankara, Turkey, assignors to Eli Lilly and Company, Indianapolis, Ind.

Continuation of Ser. No. 208,925, Mar. 9, 1994, abandoned, which is a continuation of Ser. No. 57,163, Apr. 30, 1993, abandoned. This application Oct. 27, 1994, Ser. No. 330,154

Int. Cl.⁶ C12N 15/31; 15/70; C07K 14/31

U.S. Cl. 435—240.1 5 Claims
1. A DNA compound that comprises an isolated DNA sequence which is SEQ ID NO:1.

5,587,308

MODIFIED ADENO-ASSOCIATED VIRUS VECTOR CAPABLE OF EXPRESSION FROM A NOVEL PROMOTER

Barrie J. Carter, Kensington; Terence Flotte, Baltimore; Sandra Afione, Bethesda, and Rikki Solow, Gaithersburg, all of Md., assignors to The United States of America as represented by the Department of Health & Human Services, Washington, D.C.

Filed Jun. 2, 1992, Ser. No. 891,962

Int. Cl.⁶ C12N 5/10; 15/86; C07H 21/04

U.S. Cl. 435—240.2 10 Claims
1. An adeno-associated viral vector in an adeno-associated virus particle comprising the inverted terminal repeat sequences of adeno-associated virus and a nucleic acid of a size within the adeno-associated virus packaging limit, wherein the inverted terminal repeat sequences promote expression of the nucleic acid, in the absence of another promoter functionally linked to the nucleic acid.

5,587,309

METHOD OF STIMULATING PROLIFERATION AND DIFFERENTIATION OF HUMAN FETAL PANCREATIC CELLS EX VIVO

Jeffrey Rubin, Rockville, Md.; Alberto Hayek, La Jolla, Calif.; Gillian M. Beattie, Poway, Calif., and Timo P. J. Otonkoski, La Jolla, Calif., assignors to The United States of America as represented by the Department of Health and Human Services, Washington, D.C., and Whittier Institute for Diabetes and Endocrinology, La Jolla, Calif.

Filed Apr. 29, 1994, Ser. No. 235,394

Int. Cl.⁶ C12N 5/00; 5/02

U.S. Cl. 435—240.2 6 Claims
1. A method for inducing the ex vivo proliferation and differentiation of human fetal pancreatic β -islet cells, comprising the steps of:
(a) preparing a primary culture of human fetal pancreatic cells; and
(b) contacting said primary culture with an effective concentration of Hepatocyte Growth Factor/Scatter Factor, wherein said effective concentration is an amount sufficient to induce said primary culture to proliferate, to form insulin-producing islet-like cell clusters that upon grafting into a host animal develop into functional islet tissue, and to increase the proportion of β -epithelial cells in said clusters.

5,587,310

CHIMERIC BLOOD COAGULATION PROTEINS

William H. Kane, and Thomas L. Ortel, both of Durham, N.C., assignors to Duke University, Durham, N.C.

Continuation of Ser. No. 975,839, Nov. 13, 1992, abandoned.

This application Jul. 11, 1994, Ser. No. 273,362

Int. Cl.⁶ C07K 14/745; 14/755; C12N 5/10; 15/12

U.S. Cl. 435—240.2 15 Claims
1. A chimeric blood coagulation protein selected from the group consisting of:
coagulation factor V comprising a light chain in which from one to five A3 domain exons are replaced with the homologous exons of coagulation factor VIII; and
coagulation factor VIII comprising a light chain in which from one to five A3 domain exons are replaced with the homologous exons of coagulation factor V.

5,587,311

DNA ENCODING A CELL MEMBRANE GLYCOPROTEIN OF A TICK GUT

Gary S. Cobon, New South Wales, Australia; Joanna T. Moore, Umea, Sweden; Law A. Y. Johnston, Capalaba, Australia; Peter Willadsen, Chapel Hill, Australia; David H. Kemp, Upper Brookfield, Australia; Alagacoe Sriskantha, Florey, Australia, and George A. Riding, Indooroopilly, Australia, assignors to Biotechnology Australia Pty. Ltd., Roseville, and Commonwealth Scientific and Industrial Research Organization, Campbell, both of Australia

Continuation of Ser. No. 62,109, May 17, 1993, abandoned, which is a continuation-in-part of Ser. No. 926,368, Aug. 7, 1992, abandoned, which is a continuation-in-part of Ser. No. 242,196, Jul. 6, 1988, abandoned. This application Oct. 19, 1994, Ser. No. 325,071

Claims priority, application Australia, Nov. 27, 1986, PH9196; Jun. 19, 1987, PH2570; Oct. 16, 1987, PH4912

Int. Cl.⁶ C12N 1/00; 1/15; 1/21; 5/10; 15/12; 15/63

U.S. Cl. 435—240.2 16 Claims
1. An isolated and purified DNA molecule, free of homologous chromosomal DNA, comprising SEQ ID NO:55.

5,587,312

SOMATIC EMBRYOGENESIS METHOD

Gerrit J. van Holst, Enkhuizen; Marc Kreuger, Bovenkarspel; Wiert van der Meer, Enkhuizen; Erik Postma, Hoorn, and Rob Abbestee, Enkhuizen, all of Netherlands, assignors to Sandoz Ltd., Basel, Switzerland

Continuation of Ser. No. 180,253, Jan. 12, 1994, abandoned.

This application Mar. 20, 1995, Ser. No. 406,822

Claims priority, application United Kingdom, Jan. 15, 1993, 9300705; Jan. 15, 1993, 9300706; Jan. 15, 1993, 9300707; Jan. 15, 1993, 9300729

Int. Cl.⁶ C12N 5/00; 5/02

U.S. Cl. 435—240.46 14 Claims
1. A method of obtaining somatic embryos from non-callus material in suspension culture which comprises:
(i) culturing non-Daucus non-callus explant material in a liquid medium comprising an effective amount of auxin or mixture of auxins sufficient to promote the induction of pro-embryogenic mass (PEM) formation;
(ii) increasing the number of induced PEMs by cultivation of said PEMs in an auxin-containing liquid medium;
(iii) collecting PEMs obtained in step (ii) and placing them in an auxin-free liquid medium to induce somatic embryo formation;
(iv) inducing somatic embryo formation; and
(v) collecting somatic embryos resulting from the induced embryos of step (iv)
wherein the somatic embryos collected in step (v) have the same ploidy level as the non-callus starting material in suspension culture and said ploidy level is either diploid or tetraploid.

5,587,313

METHOD FOR FERMENTATION OF MARINE BACTERIA

Ronald M. Weiner, Adelphi, and David M. Manyak, Annapolis, both of Md., assignors to University of Maryland, College Park, Md.

Filed Mar. 10, 1995, Ser. No. 402,480

Int. Cl.⁶ C12N 1/00; 1/12; 1/20

U.S. Cl. 435—252.1 9 Claims
1. A medium suitable for the culture of marine bacteria comprising liver digest, salts, and a liquid solvent in amounts sufficient for the growth and maintenance of marine bacteria.

5,587,314

INTESTINE COLONIZING *LACTOBACILLI*

Stig Bengmark, Lund; Siv Ahrné, Bjärred; Göran Molin, and Bengt Jeppson, both of Lund, all of Sweden, assignors to Probi AB, Lund, Sweden

Continuation of Ser. No. 989,030, Apr. 16, 1993, Pat. No. 5,474,932. This application Apr. 6, 1995, Ser. No. 417,770

Claims priority, application Sweden, Jul. 25, 1991, 9102238 Int. Cl.⁶ C12N 1/20

U.S. Cl. 435—252.9 7 Claims
1. A biologically pure culture of a *Lactobacillus* strain having the ability to colonize human intestinal mucosa in vivo, and having all the identifying characteristics of *Lactobacillus plantarum* 299v.

5,587,315

Patent Not Issued For This Number

5,587,316

Patent Not Issued For This Number

5,587,317

CHEMICAL-BIOLOGICAL PROCESS FOR DEHALOGENATION OF HALOGENATED ORGANIC COMPOUNDS

James M. Odom, Avondale, Pa., assignor to E. I. Du Pont de Nemours & Company, Wilmington, Del.

Continuation of Ser. No. 383,535, Feb. 2, 1995, abandoned, which is a continuation of Ser. No. 64,607, May 19, 1993, abandoned. This application Nov. 27, 1995, Ser. No. 562,944

Int. Cl.⁶ C12P 5/02

U.S. Cl. 435—262.5 16 Claims
1. A method for the dehalogenation of organohalogen from a sample containing organohalogen treated with a culture of sulfate reducing bacteria, a suitable reductant and a tetrapyrrole catalyst wherein the rate of dehalogenation in the treated sample is enhanced as compared with the untreated sample comprising the steps of:
(i) growing a culture of sulfate reducing bacterial cells in the presence of a suitable reductant useful for donating electrons to a tetrapyrrole catalyst, wherein said reductant is present in a molar excess as compared to said organohalogen;
(ii) contacting said cells with a media containing organohalogen compounds and a tetrapyrrole catalyst useful for catalyzing the dehalogenation of organohalogen, to form a reaction mixture; and
(iii) incubating said reaction mixture under suitable anaerobic conditions and for a time sufficient to dehalogenate said organohalogen.

5,587,318

PROCESS FOR PREPARING(S)- α -METHYLARYLACETIC ACIDS

Charles I. Sih, Madison, Wis., assignor to Wisconsin Alumni Research Foundation, Madison, Wis.

Division of Ser. No. 879,538, May 4, 1992, Pat. No. 5,322,791, which is a continuation of Ser. No. 518,285, May 4, 1990, abandoned, which is a continuation of Ser. No. 942,149, Dec. 16, 1986, abandoned, which is a continuation-in-part of Ser. No. 840,280, Mar. 17, 1986, abandoned, which is a

continuation-in-part of Ser. No. 811,260, Dec. 20, 1985, abandoned. This application Mar. 21, 1994, Ser. No. 215,285

Int. Cl.⁶ C12P 7/40; 7/54; C12N 1/14

U.S. Cl. 435—280

12 Claims

1. A process for preparing (S)-6-methoxy- α -methyl-2-naphthaleneacetic acid which comprises subjecting a substrate comprising a mixture of (R)- and (S)-6-methoxy- α -methyl-2-naphthaleneacetic acid esters, said esters selected from the group consisting of 2,2,2-trichloroethyl, cyanomethyl, 2-nitropropyl, 2-chloroethyl, methyl and 2-bromoethyl esters, to the hydrolytic enzymatic action of an extracellular microbial lipase isolated from *Candida cylindracea*, separating the unreacted (R)-6-methoxy- α -methyl-2-naphthaleneacetic acid ester, and recovering the (S)-6-methoxy- α -methyl-2-naphthaleneacetic acid.

5,587,319

PROCESS FOR THE PREPARATION OF L-PHOSPHINOTHRICIN USING TRANSAMINASES OF DIFFERENT SPECIFICITIES IN A LINKED PROCESS

Johann Then, Frankfurt am Main; Werner Aretz, Königstein, and Klaus Sauber, Bad Soden am Taunus, all of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Germany

Continuation of Ser. No. 136,605, Oct. 15, 1993, abandoned, which is a continuation of Ser. No. 879,111, May 4, 1992, abandoned, which is a continuation of Ser. No. 448,814, Dec. 12, 1989, abandoned. This application Jul. 8, 1994, Ser. No. 272,286

Claims priority, application Germany, Dec. 14, 1988, 38 42 025.2

Int. Cl.⁶ C12P 41/00; 19/02

U.S. Cl. 435—280

11 Claims

1. A two step process for the preparation of L-2-amino-4-methylphosphinobutyric acid, which comprises:

- reacting D,L-2-amino-4-methylphosphinobutyric acid with an α -keto acid, catalyzed by a D-aminoacid transaminase to produce 3-carboxy-3-oxo-propylmethylphosphinate, wherein said α -keto acid, is phenylglyoxylate, 4-hydroxyphenylglyoxylate or thiophenylglyoxylate, and
 - reacting the 3-carboxy-3-oxo-propylmethylphosphinate with an amino-group donor wherein said amino-group donor is L-asparagine, L-aspartic acid, L-glutamic acid or glycine, catalyzed by an L-amino transaminase, wherein said D-aminoacid transaminase does not substantially react with the amino-group donor employed in step (b), and said L-aminoacid transaminase does not substantially react with the α -keto acid employed in step (a) to obtain a product;
- (c) separating L-2-amino-4-methylphosphinobutyric acid from the product obtained in step (b).

5,587,320

SOLID ORGANIC WASTE PROCESSING APPARATUS


Yasuhiro Shindo, Tochigi-ken; Usaburo Yamaguti, Tochigi; Kazuo Ioka, Oyama; Tosio Suzuki, Tatebayashi; Akihiko Minagawa, and Syoichi Kitabatake, both of Tochigi-ken, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Aug. 19, 1994, Ser. No. 292,204

Claims priority, application Japan, Nov. 1, 1993, 5-273395 Int. Cl.⁶ C12M 3/00

U.S. Cl. 435—290.1

30 Claims



1. An apparatus for processing solid organic waste by crushing and/or agitating and fermenting the waste, characterized by comprising:

- a solid organic matter processing device including a processing vessel provided with a crushing unit for receiving and crushing the solid organic waste and a processing unit for agitating and fermenting the crushed waste;
- a heat exchanger disposed outside said solid organic matter processing device which heat exchanger condenses vapor in a gas supplied from the processing vessel of said solid organic matter processing device to thereby change the vapor to liquid and to discharge the liquid; and
- gas circulation means for providing a gas circulation path through which the inside of the processing vessel of said solid organic matter processing device is operably connected to said heat exchanger and through which a gas in the processing vessel of said solid organic matter processing device is supplied into said heat exchanger, almost all of the gas processed in said heat exchanger being returned to said solid organic matter processing device while a portion of the gas processed in said heat exchanger or a portion of the gas supplied from the processing vessel of said solid organic matter processing device is discharged to the outside of the apparatus.

5,587,321

MOATED TISSUE CULTURE PLATE


Donald D. Smith, Blue Springs; Christopher B. Cohick, Kansas City, both of Mo., and Herbert B. Lindsley, Shawnee Mission, Kans., assignors to University of Kansas, Lawrence, Kans.

Filed Jul. 31, 1995, Ser. No. 509,174

Int. Cl.⁶ C12M 3/00

U.S. Cl. 435—305.3

24 Claims



1. A culture plate apparatus comprising:
- structure defining a plurality of culture wells presenting respective top openings;
 - a frame supporting said wells; and
 - a cover configured for enclosing said top openings with a head space therebetween.

said frame including means defining a liquid-receiving chamber in spanning relationship with at least two of said wells, said frame having a chamber opening in communication with said head space, said frame being permanently secured to said structure defining said plurality of culture wells.

5,587,322

REPLICA PLATING DEVICE


Gary L. Chrebet, Princeton, N.J., assignor to ReplicaTech, Inc., Princeton, N.J.

Filed Nov. 23, 1994, Ser. No. 344,217

Int. Cl.⁶ C12M 1/26; 1/32

U.S. Cl. 435—309.4

11 Claims



1. A device for replica plating having a sheet material capable of transferring cellular colonies from one medium to another medium, comprising:

- a rigid support member having a first end and first region terminating at said first end coupled to a peripheral ridge, said rigid support member having a first rim disposed at a point of transition from said first region to said peripheral ridge, said first region having a substantially rectangular cross-sectional geometry with each side of said substantially rectangular cross-sectional geometry having a predetermined length defining the shape of said first end;

said rigid support member having a second end and second region terminating at said second end coupled to said peripheral ridge, said rigid support member having a second rim disposed at a point of transition from said second region to said peripheral ridge, said second region having a substantially circular cross-sectional geometry with a predetermined diameter defining the shape of said second end, said peripheral ridge having a geometric cross section which overlaps said first region creating said first rim and overlaps said second region creating said second rim; and,

a locking element defining an aperture through which said sheet of material and said rigid support member pass, wherein said sheet of material is disposed between said locking element and said first rim and said sheet material is secured over said first end.

5,587,323

MECONIUM ASSAY PROCEDURE

Douglas E. Lewis, Oak Brook, and Christine M. Moore, Forest Park, both of Ill., assignors to United States Drug Testing Laboratories, Inc., Chicago, Ill.

Filed May 2, 1995, Ser. No. 433,232

Int. Cl.⁶ G01N 1/18

U.S. Cl. 436—178

1 Claim

1. A method for preparing a concentrated neonatal meconium extract containing substantially all of at least one target analyte present, if any, in a sample of infant meconium suspected of containing said at least one target analyte, said at least one target analyte being selected from the group consisting of amphetamine, opiate, cocaine metabolite, cannabinoids, PCP and mixtures of any of the foregoing, said concentrated meconium extract being specifically intended for use in subsequent qualitative and quantitative determinations of maternal use or exposure to said at least one target analyte during pregnancy and fetal exposure to said at least one target analyte, said method comprising:

- providing a test sample of newborn meconium suspected of containing said at least one target analyte;
- adding a substantially non-aqueous volatile mixture of acetonitrile and a volatile organic acid to said sample to form a first mixture;
- agitating the first mixture for a time sufficient to extract substantially all of said at least one target analyte from the meconium sample, without diluting the sample with water, until a substantially uniform liquid homogenate is obtained;
- centrifuging the liquid homogenate to form a two-phase mixture including an organic phase and a second phase;
- separating the organic phase from the second phase and diluting the organic phase with water to provide an aqueous organic solution suitable for solid-phase column separation;
- providing a mixed-mode, solid-phase extraction column having a strong cation exchange and hydrophobic functionality;
- separating said at least one target analyte present in the organic solution by adding the organic solution to the solid-phase extraction column in a manner permitting any said at least one target analyte present in the organic solution to become bound to the column;
- drying the column;
- collecting any bound neutral and acid analytes by eluting the column with a first solvent reagent including a mixture of a hydrocarbon and a carboxylic acid ester into a first container to provide an acid-neutral fraction;
- evaporating the acid-neutral fraction to dryness;
- collecting any bound basic analytes from the same column by eluting the column with a second solvent reagent including a polar organic solvent, an alcohol and a volatile base into a second container to provide a base fraction;
- combining the base fraction with the dried acid-neutral fraction to provide a combined fraction and evaporating the combined fraction to dryness;
- acidifying the dried combined fraction with 1% sulfuric acid to prevent amphetamine loss and evaporating to dryness; and
- thereafter, forming a concentrated neonatal meconium extract by reconstituting the acidified combined fraction with a protein-modified phosphate buffer at a pH of between about 5.0-8.5, suitable for use in subsequent qualitative and quantitative analytical procedures.

5,587,324

PROCESS FOR COAL TAR REMEDIATION

Timothy A. Roy, Princeton; Carl R. Mackerer, Pennington, both of N.J., and Lawrence Goldstein, Oakland, Calif., assignors to Mobil Oil Corporation, Fairfax, Va., and Electric Power Research Institute, Inc., Palo Alto, Calif.

Filed Sep. 15, 1994, Ser. No. 306,762

Int. Cl.⁶ A62D 3/00

U.S. Cl. 436—183

2 Claims

1. A method for determining the extent of remediation necessary to reduce the bioavailability of polynuclear aromatic compounds contained within a coal tar composition, comprising:

- obtaining a sample of a coal tar composition comprising coal tar;

- (b) experimentally determining a plurality of dermal flux rates for a corresponding plurality of ratios of petroleum coke to coal tar, wherein the weight ratios of petroleum coke to coal tar is from 1:1 to 10:1;
- (c) calculating a dermally absorbed dose corresponding to each dermal flux rate by means of the equation:

$$DAD=DA \times EF \times ED \times ABW \times AT$$

where:

DAD=dermally absorbed dose (mg PNA/kg body wt./day)

DA=dose absorbed per exposure (mg PNA/cm² body/day)

EF=exposure frequency (days/yr)

ED=exposure duration (yr)

A=exposure surface area (cm² body)

BW=body weight (kg)

AT=average time (days);

- (d) subsequently calculating various corresponding cancer risks associated with the calculated dermally absorbed doses by using equation:

$$\text{Cancer risk} = 1 - e^{-DAD \times Q}$$

where

Cancer risk=probability of fatality due to exposure

Q=cancer slope factor; and

- (e) using the calculated cancer risk to determine the weight ratio of petroleum coke to coal tar to adequately remediate the coal tar composition.

5,587,325

METHOD OF PREPARING ANTIMONY DOPED SEMICONDUCTOR WITH INTRINSIC GETTERING

Alain Comeau, Bromont, Canada, assignor to Mitel Corporation, Kanata, Canada

PCT No. PCT/CA93/00123, § 371 Date Sep. 30, 1994, § 102(e)

Date Sep. 30, 1994, PCT Pub. No. WO93/20582, PCT Pub. Date Oct. 14, 1993


PCT Filed Mar. 26, 1993, Ser. No. 313,091

Claims priority, application Canada, Mar. 31, 1992, 206-4486

Int. Cl.⁶ H01L 21/322

U.S. Cl. 437—10

5 Claims



1. A method of preparing an antimony-doped semiconductor wafer with intrinsic gettering capability, comprising consecutively carrying out the steps of:

- exposing the antimony doped wafer to a wet oxidizing atmosphere at a steady temperature above about 1000° C. for between about 20 to 60 minutes to form an oxidation layer thereon;
- immediately after step (a) heating said wafer at a steady temperature of between about 600°-700° C. in an inert atmosphere for about 1 to 4 hours to initiate formation of crystal nuclei in the wafer;
- carrying out a single ramp cycle in said inert atmosphere during which the temperature is ramped up to a temperature of at least about 850° C. at a rate of about 1°-10° C./min. to initiate nucleation growth from said formed crystal nuclei; and
- directly, without an intervening annealing step, carrying out a well diffusion step on the wafer at a temperature of at least about 1000° C. during which oxygen precipitation occurs.

5,587,326

METHOD OF FORMING BIPOLAR JUNCTION TRANSISTOR OF EPITAXIAL PLANAR TYPE

Hisashi Takemura, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan


Filed Oct. 23, 1992, Ser. No. 965,027

Claims priority, application Japan, Oct. 24, 1991, 3-277623

Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—31

9 Claims



3. A fabrication method of a bipolar junction transistor of an epitaxial planar type, which comprises a collector region of a first conductivity type, a base region of a second conductivity type different from said first conductivity type, and an emitter region of the first conductivity type which is formed through a conductive film deposited on said emitter region and a poly-silicon layer deposited on said conductive film, said fabrication method comprising the steps of:

- adding an additive in said conductive film which prevents occurrence of grain growth in the poly-silicon layer, said additive is selected from a group consisting of C, O and P;
- depositing the conductive film including said additive, to a predetermined thickness not thicker than 100 Å; and
- depositing the poly-silicon layer onto said conductive film.

5,587,327

PROCESS FOR PREPARING A HETEROJUNCTION BIPOLAR TRANSISTOR

Ulf König; Andreas Grühle, both of Ulm; Andreas Schüppen, Brackenheim; Horst Kibbel, Erbach; Harry Dietrich, Kirchhardt, and Heinz-Achim Hefner, Brackenheim, all of Germany, assignors to Daimler Benz AG, Stuttgart, and Temic-electron Microelectronic GmbH, Heilbronn, both of Germany


Filed May 23, 1995, Ser. No. 447,947

Claims priority, application Germany, May 24, 1994, 44 17 916.2

Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—31

13 Claims



1. A process for preparing a bipolar transistor, the process comprising the steps of:

- providing a monocrystalline lead layer;
- preparing a structured first layer with a collector zone and with insulation areas surrounding the collector zone, the structured first layer being prepared on the monocrystalline lead layer;
- growing a series of monocrystalline transistor layers on the structured first layer over the collector zone by differential epitaxy and substantially at the same time, growing a series of polycrystalline layers over the insulation areas; and providing the polycrystalline layers as a base lead, said monocrystalline

layers being grown as a series of layers of a heterobipolar-transistor with a slightly doped emitter layer, one of said polycrystalline layers corresponding to said slightly doped emitter layer being employed as part of said base lead, one of said monocrystalline transistor layers forming a base layer; transposing said one of said polycrystalline layers corresponding to said slightly doped emitter layer into a conductivity type of said base layer, boundaries defined between said polycrystalline layers and said monocrystalline layers being included in said transposing;

partially converting said one of said polycrystalline layers corresponding to said base layer into a silicide, said boundaries defined between said polycrystalline layers and said monocrystalline layers being also included in said silicide conversion;

etching free a portion of said series of polycrystalline layers around said series of monocrystalline layers to form an active emitter zone;

forming a ring of a material around said active emitter zone, shielding said active emitter zone from said silicide conversion, said material of said ring also shielding said active emitter zone from said silicide conversion.

5,587,328

METHOD FOR MANUFACTURING SEMICONDUCTOR DEVICE

Kazuhiko Yoshida, Shiga-ken, Japan, assignor to Murata Manufacturing Co., Ltd., Japan


Filed Dec. 18, 1995, Ser. No. 572,876

Claims priority, application Japan, Dec. 20, 1994, 6-317019

Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—40

15 Claims



1. A method for manufacturing a semiconductor device comprising the steps of:

- depositing a first mask layer on a semiconductor substrate;
- forming an opening in the first mask layer;
- causing the first mask layer to flow by heat-treating the semiconductor substrate;
- depositing a second mask layer on the first mask layer;
- forming in the second mask layer an opening larger than the opening in the first mask layer and exposing the opening in the first mask layer; and
- depositing metal in the opening in the second mask layer, to form a first electrode on said semiconductor substrate.

5,587,329

METHOD FOR FABRICATING A SWITCHING TRANSISTOR HAVING A CAPACITIVE NETWORK PROXIMATE A DRIFT REGION


Fu-Lung Hseuh, Middlesex; Alfred C. Ipri, Princeton, both of N.J.; Gary M. Dolny, Newtown, Pa., and Roger G. Stewart, Hillsborough Township, Somerset County, N.J., assignors to David Sarnoff Research Center, Inc., Princeton, N.J.

Filed Aug. 24, 1994, Ser. No. 295,374

Int. Cl.⁶ H01L 21/786

U.S. Cl. 437—40

4 Claims



4. A method of fabricating a pixel within an electroluminescent display comprising the steps of:

- forming, upon a substrate, a drift region for a transistor;
- forming a drain region and a source region for said transistor, where said drift region is located between said drain region and said source region;
- forming a first insulating layer over said drift region;
- depositing a gate electrode on said first insulating layer, said gate electrode partially overlapping said drift region;
- depositing a first plurality of capacitive elements on said insulating layer, said elements overlapping a portion of said drift region not overlapped by said gate electrode;
- forming a second insulating layer over said capacitive elements and said gate electrode;
- depositing a second plurality of capacitive elements on said second insulating layer, said second plurality of elements partially overlaps said first plurality of capacitive elements;
- forming, upon said second insulating layer and overlapping said gate electrode, an electric field shield;
- forming a third insulating layer over said second plurality of capacitive elements;
- depositing a high voltage electrode of an electroluminescent cell on said third insulating layer such that, when a high voltage is applied to said high voltage electrode, a charge accumulates on said first and second plurality of capacitive elements and an electric field is uniformly distributed in said drift region; and
- forming said electroluminescent cell upon said high voltage electrode.

5,587,330

METHOD FOR MANUFACTURING SEMICONDUCTOR DEVICE

Shunpei Yamazaki, Tokyo, Japan, assignor to Semiconductor Energy Laboratory Co., Ltd., Kanagawa-ken, Japan

Filed Oct. 18, 1995, Ser. No. 544,636

Claims priority, application Japan, Oct. 20, 1994, 6-281406


Int. Cl.⁶ H01L 21/8234

U.S. Cl. 437—41

30 Claims

1. A method for producing a semiconductor device comprising the steps of:

- forming a top gate type thin film transistor, wherein at least a portion of a channel forming region adjacent to a gate insulating film is a semiconductor; and



irradiating the top gate type thin film transistor with ultraviolet light having a wavelength of 350 nm or less in an atmosphere including a nitrogen oxide while heating treatment is performed at 300° C. or higher.

5,587,331

METHOD OF FORMING A CONTACT HOLE FOR A METAL LINE IN A SEMICONDUCTOR DEVICE

Young-Kwon Jun, 3-803 Garak-plaza, Apt. #199, Garak-dong, Songpa-gu, Seoul, Rep. of Korea


Filed Dec. 17, 1993, Ser. No. 168,247

Claims priority, application Rep. of Korea, Dec. 19, 1992, 1992-24804

Int. Cl.⁶ H01L 21/44

U.S. Cl. 437—41

9 Claims



1. A method for forming a contact hole to connect a metal line to a contact area on semiconductor substrate through said contact hole, the method comprising the steps of:

- forming a first insulative layer on a surface of said semiconductor substrate;
- forming a first contact hole in said first insulative layer to expose said contact area;
- forming an insulative sidewall spacer on a sidewall surface of said contact hole;
- depositing a barrier metal layer on said first insulative layer including said insulative sidewall spacer;
- forming a barrier metal protective layer on said barrier metal layer, the barrier metal protective layer covering the contact area;
- etching the barrier metal layer using the barrier metal protective layer as a mask;
- forming a second insulative layer on said barrier metal protective layer and said first insulative layer; and
- forming a second contact hole by removing at least portions of said second insulative layer and said barrier metal protective layer in correspondence with said first contact hole, thereby exposing said barrier metal layer in said contact area.

5,587,332 METHOD OF MAKING FLASH MEMORY CELL


Kuang-Yeh Chang, Los Gatos; Subhash R. Nariani, and William J. Boardman, both of San Jose, all of Calif., assignors to VLSI Technology, Inc., San Jose, Calif.

Filed Sep. 1, 1992, Ser. No. 938,727

Int. Cl.⁶ H01L 21/8247

U.S. Cl. 437—43

43 Claims



1. A method of manufacturing a multilayer polysilicon device including peripheral transistors, said method comprising the steps of:

- forming a memory cell having at least two patterned polysilicon layers on a substrate, with one of said at least two patterned polysilicon layers being patterned subsequent to formation of remaining polysilicon layers used to form said memory cell and being patterned for preventing electron leakage of a gate of said memory cell during erasure; and
- forming at least one peripheral transistor on said substrate, said at least one peripheral transistor having a gate, said step of forming at least one peripheral transistor further including forming said gate of said peripheral transistor with said one of said at least two patterned polysilicon layers for preventing electron leakage of said gate of said memory cell during erasure.

5,587,333

CAPACITOR IN AN INTEGRATED FUNCTION BLOCK OR AN INTEGRATED CIRCUIT HAVING HIGH CAPACITANCE, A METHOD FOR MANUFACTURING SAID CAPACITOR AND UTILIZING OF SAID CAPACITOR AS AN INTEGRATED DECOUPLING CAPACITOR

Ted Johansson, Hägersten, and Jose-Maria Gobbi, Stockholm, both of Sweden, assignors to Telefonaktiebolaget LM Ericsson, Stockholm, Sweden


Division of Ser. No. 84,459, Jul. 1, 1993, abandoned. This application Jun. 6, 1995, Ser. No. 470,145

Claims priority, application Sweden, Jul. 6, 1992, 9202093

Int. Cl.⁶ H01L 21/70; 27/00

U.S. Cl. 437—60

20 Claims



1. A method for construction of an integrated capacitor having a capacitance in an integrated function block or an integrated circuit, which utilizes unoccupied silicon surface underlying supply lines, ground connections or a bonding pad, and comprising the steps of:

- applying a conductive layer on a thin layer of gate oxide on a p⁺ substrate, said conductive layer at the same time constituting a protective layer for the thin gate layer of said oxide and said conductive layer extending in a first direction, which extends beyond the underlying thin layer of said gate oxide, whereby at least one surface of the thin layer of said gate oxide is formed and delimited in a second direction opposite

to said first direction by said conductive layer and by a thick layer of field oxide, and at least the one surface of the thin layer of said gate oxide is not protected by said conductive layer.

creating p⁺ doped islands in said p⁺ substrate by implanting in the surface of the thin layer of said gate oxide, which is not protected by said conductive layer.

forming an insulating layer over exposed surfaces of the thin layer of said gate oxide, said conductive layer and the thick layer of said field oxide.

forming a first plurality of interconnection openings for interconnection to said p⁺ doped islands and a second plurality of interconnection openings for interconnection to said conductive layer at ends of said conductive layer in said first direction, said second plurality of interconnection openings being placed in an area which does not have the thin layer of said gate oxide underneath, and

forming a plurality of metallization areas at a first metallization level, said metallization areas including a first metallization area, which is connected to said p⁺ doped islands through the first plurality of interconnection openings, and at least one second metallization area, which is connected to said conductive layer through said second plurality of interconnection openings, whereby a capacitor structure of a capacitance is created, said capacitor structure decouples to a positive voltage source by additional connection to said first and second metallization areas at said first metallization level, wherein said first and second metallization areas each correspond to a respective capacitor connection, said capacitor structure being connected to portions of the function block or the integrated circuit by a second metallization level formed over said first metallization level.

5,587,334

SEMICONDUCTOR LASER DEVICE FABRICATION METHOD

Hiroki Naito, Suita; Masahiro Kume, Ohtsu; Hideyuki Sugura, Takatsuki; Toru Takayama, Nara; Kunio Itoh, Uji; Issei Ohta, Fujiidera, and Hirokazu Shlmizu, Suita, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Division of Ser. No. 40,655, Mar. 31, 1993, Pat. No. 5,386,429. This application Aug. 3, 1994, Ser. No. 285,357

Claims priority, application Japan, Mar. 31, 1992, 4-076710; Jun. 16, 1992, 4-156559; Sep. 24, 1992, 4-254537; Sep. 29, 1992, 4-259303; Oct. 19, 1992, 4-279907; Oct. 27, 1992, 4-288553; Dec. 11, 1992, 4-331498

Int. Cl.⁶ H01L 21/20

U.S. Cl. 437—129

4 Claims



1. A method of fabricating a semiconductor laser device comprising the steps of:

- forming successively by an epitaxial growth method in at least one side of the principal plane of an active layer a certain conductive type Ga_{1-x}Al_xAs first light guide layer on said active layer, a Ga_{1-x}Al_xAs second light guide layer of said certain conduction type on said first light guide layer surface

and an opposite conduction type Ga_{1-x}Al_xAs layer on said second light guide layer surface;

etching selectively said Ga_{1-x}Al_xAs layer to form a stripe-like configuration by using a mixed solution of hydrogen fluoride acid and an acid that will not by itself etch GaAlAs;

and

epitaxially growing a Ga_{1-x}Al_xAs layer of the same conduction type as said light guide layers on said stripe-like etched part,

where relations of Z>Y3>Y2 and Y1>Y2 are established among Y1, Y2, Y3 and Z that define the AlAs mole-fraction.

5,587,335

METHOD OF MAKING SURFACE EMISSION TYPE SEMICONDUCTOR LASER

Katsumi Mori; Tatsuya Asaka; Hideaki Iwano, and Takayuki Kondo, all of Suwa, Japan, assignors to Seiko Epson Corporation, Tokyo, Japan


Division of Ser. No. 319,650, Oct. 7, 1994, Pat. No. 5,537,666, which is a continuation-in-part of Ser. No. 999,137, Dec. 31, 1992, Pat. No. 5,356,832, which is a continuation-in-part of Ser. No. 756,981, Sep. 9, 1991, Pat. No. 5,182,757, and a continuation-in-part of Ser. No. 205,363, Mar. 3, 1994, Pat. No. 5,436,922, which is a continuation-in-part of Ser. No. 13,024, Feb. 2, 1993, Pat. No. 5,295,148, which is a continuation-in-part of Ser. No. 997,177, Dec. 28, 1992, Pat. No. 5,317,584, which is a continuation-in-part of Ser. No. 756,979, Sep. 9, 1991, Pat. No. 5,181,219, which is a continuation-in-part of Ser. No. 756,980, Sep. 9, 1991, Pat. No. 5,181,221, which is a continuation-in-part of Ser. No. 756,981, Sep. 9, 1991, Pat. No. 5,182,757. This application Jul. 12, 1995, Ser. No. 501,660

Claims priority, application Japan, Sep. 12, 1990, 2-242000

Int. Cl.⁶ H01L 21/20

U.S. Cl. 437—129


26 Claims



1. A method of making a surface emission type semiconductor laser which comprises a substrate and an optical resonator on said substrate, said optical resonator including a pair of reflection mirrors respectively located on the substrate and light exit sides thereof and a plurality of semiconductor layers formed between said reflection mirror pair, the light being emitted in a direction perpendicular to said substrate, said method comprising the steps of:


- forming said reflection mirror located on the substrate side and said semiconductor layers in said optical resonator on said substrate through the organic metal vapor growth method or molecular-beam epitaxy growth method;
- forming a photoresist mask on said semiconductor layers;
- etching at least a cladding layer in said semiconductor layers by the use of said photoresist mask to form at least one column-like portion having sidewalls extending substantially perpendicular to said substrate and being operative to guide the light in a direction perpendicular to said substrate;
- forming a buried layer around said column-like portion, said buried layer including a single layer at its region covering the sidewalls of said column-like portion; and
- depositing a multilayered dielectric mirror in said column-like portion on the light exit side thereof to form said reflection mirror on the light exit side.

5,587,336
BUMP FORMATION ON YIELED SEMICONDUCTOR
DIES
Tsing-Chow Wang, San Jose; Serena M. Luo; Marlita F. Mac-
araeg, both of Milpitas; Francisca Tung, Los Gatos, and
Thomas J. Massingill, Scotts Valley, all of Calif., assignors to
VLSI Technology, San Jose, Calif.
Filed Dec. 9, 1994, Ser. No. 353,022
Int. Cl.⁶ H01L 21/283



1. A method of forming an adhesion pad and ball bump structure on a surface of a semiconductor wafer, said method comprising:
- (a) depositing a barrier material onto the surface of the wafer;
 - (b) depositing a bonding material onto the surface of the barrier material;
 - (c) coating the wafer with a photoresist material;
 - (d) processing the photoresist material to define an adhesion pad, including a barrier material and a bonding material, above a bond pad, and removing the photoresist material which does not define the adhesion pad;
 - (e) etching the material not protected by the photoresist;
 - (f) removing the photoresist material present after step (c) to expose the adhesion pad;
 - (g) testing the wafer to determine good dies; and
 - (h) forming a ball bump on the adhesion pad of good dies.

5,587,337
SEMICONDUCTOR PROCESS FOR FORMING BUMP
ELECTRODES WITH TAPERED SIDEWALLS
Toshiaki Idaka, Yokohama, and Hirokazu Ezawa, Tokyo, both
of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki,
Japan
Division of Ser. No. 246,744, May 20, 1994, Pat. No.
5,473,197. This application May 19, 1995, Ser. No. 444,513
Claims priority, application Japan, May 28, 1993, 5-126582
Int. Cl.⁶ H01L 21/441
U.S. Cl. 437—183 4 Claims



1. A method for manufacturing semiconductor devices comprising the steps of:
- forming a plurality of pad areas on a semiconductor substrate;
 - forming a passivation film on said pad areas, and forming first openings in said passivation film in positions corresponding to said pad areas;
 - covering the entire surface of the resulting passivation film with an organic film;
 - forming second openings in said organic film in positions corresponding to said first openings and in communication with said respective first openings and forming groove portions in the surface of said organic film at least in positions between said second openings;


effecting a heat treatment to contract said organic film and enlarge the upper end portion of said second opening in a direction towards a portion in which said groove portion is not formed;

forming bump electrodes of metal connected to said pad areas in said first and second openings; and

removing said organic film.

5,587,338
POLYSILICON CONTACT STUD PROCESS
Horng-Huei Tseng, Hsin Chu, Taiwan, assignor to Vanguard
International Semiconductor Corporation, Hsin-Chu, Tai-
wan

Filed Apr. 27, 1995, Ser. No. 428,493
Int. Cl.⁶ H01L 21/44



1. A method for fabricating a MOSFET device on a semiconductor substrate, using a conductive stud to provide electrical contact between active device elements in the substrate, and an overlying interconnect metallization, comprising the steps of:
- providing the active device elements in the said semiconductor substrate;
 - depositing a first dielectric layer on said semiconductor substrate, that includes said active device elements;
 - depositing a second dielectric layer on said first dielectric layer, to form composite dielectric layer;
 - photolithographic processing to open a region in a photoresist layer, exposing an area of said composite dielectric layer, directly overlying said active device element;
 - anisotropic removal of said composite dielectric layer, in said exposed region of said photoresist layer, to create contact hole opening to said active device element;
 - cleaning the surface of said active device element, in said contact hole opening;
 - depositing an insitu doped polysilicon layer on the surface of said active device element, in said contact hole opening, and on the surface of said second dielectric layer;
 - depositing a layer of titanium on said insitu doped polysilicon layer;
 - annealing to completely convert a portion of said insitu doped polysilicon layer to a titanium silicide layer, on the surface of said second dielectric layer, while converting only a top portion of said insitu doped polysilicon layer, in said contact hole opening, to titanium silicide;
 - removal of said titanium silicide from the surface of said second dielectric layer, and from the surface of said unconverted insitu doped polysilicon, in said contact hole; and
 - removal of said second dielectric layer from the surface of said first dielectric layer.

5,587,339


**METHOD OF FORMING CONTACTS IN VIAS FORMED
OVER INTERCONNECT LAYERS**

Graeme M. Wyborn, Walton-on-Thames, and Howard C. Nicholls, Penylan, both of United Kingdom, assignors to SGS-Thomson Microelectronics Ltd., United Kingdom

Continuation of Ser. No. 119,421, Sep. 10, 1993, abandoned.

This application Jun. 7, 1995, Ser. No. 480,954

Claims priority, application United Kingdom, Sep. 11, 1992, 9219267




18. A method of fabricating a semiconductor device incorporating a via and a conductive interconnect layer, the method comprising the steps of:
- (a) providing a silicon wafer structure;
 - (b) forming a conductive interconnect layer on the structure;
 - (c) forming a capping layer over the interconnect layer, the capping layer being selected from the group consisting of tungsten, titanium and titanium nitride;
 - (d) forming a dielectric layer on the capping layer; and
 - (e) selectively depositing a tungsten contact on the capping layer in a contact hole of the dielectric layer thereby to form a via, wherein the contact is deposited in a two stage deposition process in which in the first stage a tungsten containing species is introduced, in the absence of a reducing agent for such species, over the wafer structure, wherein the tungsten containing species reacts with the capping layer in the contact hole to deposit a tungsten seed layer on the capping layer, and in the second stage a reducing agent for that species is additionally introduced over the silicon wafer structure so as to reduce the tungsten containing species and deposit tungsten over the seed layer in the contact hole.

5,587,340
METHOD OF FORMING A SEMICONDUCTOR DEVICE
IN A SUBSTRATE DEPRESSION
Shunpei Yamazaki, Tokyo, Japan, assignor to Semiconductor
Energy Laboratory Co., Ltd., Kanagawa-ken, Japan
Division of Ser. No. 168,360, Dec. 17, 1993, Pat. No.
5,464,780, which is a continuation of Ser. No. 735,057, Jul. 24,
1991, abandoned. This application Apr. 19, 1995, Ser. No.
424,194

Claims priority, application Japan, Jul. 25, 1990, 2-196869;
Jul. 25, 1990, 2-196870
Int. Cl.^b H01L 21/44; 21/48
U.S. Cl. 437—203 7 Claims

1. The method of forming a semiconductor device having at least an insulated gate field effect transistors comprising the steps of:
- forming a depression in an upper surface of a semiconductor substrate, said depression having a bottom surface and at least one side surface;
 - forming a pair of impurity regions in an upper portions of the semiconductor substrate and the bottom surface of the depression;
 - forming a gate insulating layer on said side surface;
 - forming a conductive layer on said depression after forming said gate insulating layer; and



- simultaneously forming a gate electrode adjacent to said side surface and a source or drain electrode contacting the impurity region formed within the bottom portion of said depression by selectively etching the formed conductive layer.

5,587,341

**PROCESS FOR MANUFACTURING A STACKED
INTEGRATED CIRCUIT PACKAGE**

Watanabe Masayuki, Yokohama; Sugano Toshio, Kokubunji;
Tsukui Seichiro, Komoro; Ono Takashi, Akita, and
Wakashima Yoshiaki, Kawasaki, all of Japan, assignors to
Hitachi, Ltd., Tokyo; Hitachi Tobu Semiconductor, Ltd.,
Inuma-gun, and Akita Electronics Co., Ltd., Minamiakita-
gun, all of Japan


Continuation of Ser. No. 890,423, May 29, 1992, abandoned,
which is a division of Ser. No. 796,873, Nov. 25, 1991, Pat.
No. 5,138,438, which is a continuation of Ser. No. 607,411,
Oct. 3, 1990, abandoned, which is a continuation of Ser. No.
209,739, Jun. 22, 1988, Pat. No. 4,982,265. This application
Oct. 18, 1994, Ser. No. 323,709

Claims priority, application Japan, Jun. 24, 1987, 62-155478;
Sep. 11, 1987, 62-226307

Int. Cl. ⁸ H01L 21/58; 21/60; 21/70


U.S. Cl. 437—206

17 Claims



6. A method of fabricating a semiconductor memory module comprising the steps of:
 providing a base plate having a first and a second face;
 providing at least four semiconductor memory chips, each chip having at least one chip-select terminal and a plurality of corresponding non-chip-select terminals;
 connecting a chip-select lead to said at least one chip-select terminal and corresponding leads to said plurality of corresponding terminals;

stacking a first chip on top of a second chip, said first and second chips oriented such that corresponding terminals on said first chips are aligned with corresponding terminals on said second chip;
stacking a third chip on top of a fourth chip, said third and fourth chips oriented such that corresponding terminals on said third chips are aligned with corresponding terminals on said fourth chip;
superimposing and connecting only said corresponding leads on said first chip with corresponding leads on said second chip;
superimposing and connecting only said corresponding leads on said third chip with corresponding leads on said fourth chip;
mounting said stacked first and second chips onto the face of said base plate; and
mounting said stacked third and fourth chips onto the second face of said base plate.



therebetween, wherein said beam structure film formation step includes a step of interrupting said film deposition at least one time; and
etching said sacrificial layer after said beam structure forming step so that said beam structure film assumes a movable state with respect to said semiconductor substrate.

5,587,344


METHOD FOR FABRICATING AN OXYNITRIDE FILM FOR USE IN A SEMICONDUCTOR DEVICE
Hiraku Ishikawa, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Apr. 26, 1995, Ser. No. 429,144

Claims priority, application Japan, Jun. 3, 1994, 6-121639
Int. Cl.⁶ H01L 21/316; 21/318

U.S. Cl. 437—238

2 Claims



1. A method for fabricating a semiconductor device, said method comprising the steps of depositing a silicon oxynitride layer by means of plasma-enhanced chemical vapor deposition with a radio-frequency field being applied to a semiconductor substrate, said plasma-enhanced chemical vapor deposition using a silane gas, an argon gas, an oxygen gas and a nitrogen gas as process gases on condition that a flow rate ratio of said argon gas to said silane and nitrogen gases is in the range of 1.1 to 2.0 inclusive, and that a flow rate ratio of said nitrogen gas to said oxygen and nitrogen gases is in the range of 0.25 to 0.6 inclusive.

5,587,345

HIGH FLEXURAL STRENGTH CARBON FIBER REINFORCED SILICON CARBOXYDE COMPOSITE
Roger Y. Leong, Schaumburg, Ill., assignor to AlliedSignal Inc., Morris Township, Morris County, N.J.

Division of Ser. No. 629,923, Dec. 19, 1990, Pat. No. 5,486,251, which is a continuation-in-part of Ser. No. 464,470, Jan. 12, 1990, Pat. No. 5,512,359, and a continuation-in-part of Ser. No. 523,620, May 15, 1990, Pat. No. 5,468,318. This application Jun. 5, 1995, Ser. No. 462,374
Int. Cl.⁶ C03C 14/00

U.S. Cl. 501—32

10 Claims

1. A carbon fiber-black glass composite consisting essentially of (a) carbon reinforcing fibers having a high degree of graphitization resulting from treatment in an inert atmosphere above 1700° C.; and
(b) a black glass matrix having the empirical formula SiC_xO_y where x ranges from about 0.5 to about 2.0 and y ranges from about 0.5 to about 3.0.

5,587,342

METHOD OF FORMING AN ELECTRICAL INTERCONNECT


Jong-Kai Lin; William H. Lytle, both of Chandler, and Ravichandran Subrahmanyam, Mesa, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Apr. 3, 1995, Ser. No. 415,972

Int. Cl.⁶ H01L 21/60

U.S. Cl. 437—209

16 Claims



1. A method of forming an electrical interconnect, comprising the steps of:
providing a substrate;
forming a conductive layer on a portion of the substrate;
forming a wet photoresist layer on the substrate and the conductive layer;
patterning the wet photoresist layer to form openings to the conductive layer;
disposing a conductive paste in at least the openings to the conductive layer;
heating the conductive paste a first time at a temperature above room temperature;
removing the wet photoresist layer; and
heating the conductive paste at a temperature above room temperature a second time after the step of removing the wet photoresist layer.

5,587,343

SEMICONDUCTOR SENSOR METHOD

Kazuhiko Kano, Ohu; Yukihiko Takeuchi, Seto; Takamoto Watanabe, Nagoya; Kenichi Ao, Tokai; Masakazu Kantosue, Nagoya, and Hirofumi Uenoyama, Anjo, all of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan

Filed Mar. 8, 1995, Ser. No. 401,044

Claims priority, application Japan, Mar. 9, 1994, 6-038836; Feb. 20, 1995, 7-031163

Int. Cl.⁶ H01L 21/00; B44C 1/22

U.S. Cl. 437—228

29 Claims

1. A method for fabricating a semiconductor sensor, comprising the steps of:
forming a sacrificial layer on a semiconductor substrate;
forming a beam structure film on said semiconductor substrate by film deposition so as to sandwich said sacrificial layer

5,587,346

TRANSLUCENT POLYCRYSTALLINE ALUMINA
Kariene J. Zuk, Hathorne, Mass., assignor to Osram Sylvania, Inc., Danvers, Mass.

Filed Jun. 16, 1995, Ser. No. 491,064

Int. Cl.⁶ C04B 35/115

U.S. Cl. 501—152

5 Claims

2. A sintered, translucent ceramic article comprising: a substantial amount of alpha alumina and an amount up to 0.050 wt. percent magnesia and between 0.001 to 0.100 wt. percent lutetium oxide.

5,587,347

RAW MATERIALS FOR PRODUCING COLOR CERAMIC PRODUCTS

Jibi Hong; Jianhua Chu, and Hongxiang Wu, all of Panzhihua, China, assignors to Panzhihua Iron and Steel (Group) Co., Panzhihua, China

Filed Mar. 27, 1995, Ser. No. 411,153

Claims priority, application China, Mar. 27, 1994, 94111695.6

Int. Cl.⁶ C04B 35/453; 33/14

U.S. Cl. 501—155

14 Claims

1. A raw material for producing a colored ceramic product, comprising:

- (1) a base material comprising 20–85% by weight of a V-bearing titanomagnetite tail obtained after ore dressing, wherein the total content of iron, titanium, cobalt and nickel of said tail is in the range of 3–45% by weight, based upon the weight of said base material, said iron, titanium, cobalt and nickel are present as titanomagnetite, ilmenite, titanite, plagioclase and/or sulfides; and trace amounts of vanadium in the form of insoluble spinel;
- (2) 15–80% by weight, based upon the weight of said raw material, of at least two additives selected from the group consisting of red clay, white mud, and black mud; and
- (3) 0–10% by weight, based upon the weight of said raw material, of a coloring agent.

5,587,348

ALKYNE HYDROGENATION CATALYST AND PROCESS
Scott H. Brown; Stan A. Zisman, and James B. Kimble, all of Bartlesville, Okla., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Apr. 19, 1995, Ser. No. 424,733

Int. Cl.⁶ B01J 27/06; 27/13; 27/128; 23/44

U.S. Cl. 502—230

32 Claims

1. A catalyst composition which comprises about 0.01–1 weight-% palladium, about 0.05–5 weight-% of at least one alkali metal, about 0.03–10 weight-% fluorine, and an inorganic support material selected from the group consisting of alumina, titania, zirconia and mixtures thereof, wherein the atomic ratio of fluorine to said at least one alkali metal is in the range of about 1.3:1 to about 4:1.

5,587,349

PROCESS FOR PREPARING SILICA-TITANIA CATALYST

Mariko Abe; Shuji Ebata; Takafumi Abe, and Hirofumi Higuchi, all of Niigata, Japan, assignors to Mitsubishi Gas Chemical Company, Inc., Tokyo, Japan

Filed Dec. 30, 1994, Ser. No. 366,812

Claims priority, application Japan, Feb. 15, 1994, 6-018341

Int. Cl.⁶ B01J 21/08

U.S. Cl. 502—236

16 Claims

1. A process for preparing a silica-titania catalyst comprising adding an acidic solution containing a silicon compound and a

titanium compound dissolved therein to a solution of a basic compound to bring about co-precipitation, in which the acidic solution is a nitric acid-acidic solution or a sulfuric acid-acidic solution; a ratio of the amount (gram equivalent) of nitric acid or sulfuric acid to the amount (mol) of the silicon compound in the acidic solution is 0.5 to 50; and the amount of the titanium compound in the acidic solution is such that a ratio of titania (TiO_2) in the prepared silica-titania catalyst is 1 to 50% by weight.

5,587,350

DIRECT THERMAL IMAGING MATERIAL

Bartholomeus C. Horsten, Rumst; Carlo A. Uyttendaele, Mortsel; Guy D. A. Jansen, Borsbeek, and Ronald Schuerwegen, Schelle, all of Belgium, assignors to Agfa-Gevaert N.V., Mortsel, Belgium

PCT No. PCT/EP93/03122, § 371 Date Mar. 28, 1995, § 102(e) Date Mar. 28, 1995, PCT Pub. No. WO94/11199, PCT Pub. Date May 26, 1994

PCT Filed Nov. 6, 1993, Ser. No. 407,014

Claims priority, application European Pat. Off., Nov. 16, 1992, 92203495; Dec. 18, 1992, 92204009; Mar. 8, 1993, 93200652; Mar. 8, 1993, 93200653; Sep. 8, 1993, 93202599

Int. Cl.⁶ B41M 5/40

U.S. Cl. 503—201

10 Claims

1. A recording material comprising on a support (i) a heat sensitive layer comprising a substantially light insensitive organic silver salt, (ii) a protective layer containing a thermomeltable particle dispersed in a binder and (iii) a reducing agent being present in the heat sensitive layer and/or any other layer of the recording material on the same side of the support carrying the heat sensitive layer.

5,587,351

THERMAL TRANSFER SYSTEMS HAVING VANADIUM OXIDE ANTISTATIC LAYERS

Eric D. Morrison, West St. Paul; Jeffrey C. Chang, North Oaks, and Linda K. Williams, St. Paul, all of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.


Continuation of Ser. No. 15,419, Feb. 9, 1993, abandoned.

This application Aug. 22, 1994, Ser. No. 294,190

Int. Cl.⁶ B41M 5/035; 5/38

U.S. Cl. 503—227

16 Claims



4. A process for providing an image by a thermal transfer process comprising the steps of:

- (a) providing a thermal transfer donor sheet and a thermal transfer receptor sheet in a facing relationship; and
 - (b) applying heat in an imagewise distributed manner to the donor sheet to cause material on the donor sheet to transfer to the receptor sheet;
- wherein the receptor sheet comprises a flexible substrate having a front side and a back side, an image-receiving layer coated on the front side of the substrate, and a vanadium oxide antistatic layer coated on the flexible substrate, and wherein the antistatic layer is coated on the front

side of the flexible substrate and is positioned between the flexible substrate and the image-receiving layer.


5,587,352

THERMAL TRANSFER IMAGE-RECEIVING SHEET AND PROCESS FOR PRODUCING THE SAME

Yoshihiko Tamura, and Mitsuru Tsuchiya, both of Tokyo, Japan, assignors to Dai Nippon Printing Co., Ltd., Japan Division of Ser. No. 159,118, Nov. 30, 1993, Pat. No. 5,430,002. This application Apr. 10, 1995, Ser. No. 419,468 Claims priority, application Japan, Nov. 30, 1992, 4-341074; Nov. 30, 1992, 4-341075; Dec. 28, 1992, 4-358504

Int. Cl. B41M 5/035; 5/38

U.S. Cl. 503—227



1. A process for producing a thermal transfer image-receiving sheet, comprising the step of coating a coating solution containing a dye-receiving resin on at least one surface of a substrate sheet to form a dye-receiving layer, wherein said coating solution contains a release agent mixture comprising an addition-polymerizable silicone and a hydrogen-modified silicone.

5,587,353

AGRICULTURAL CHEMICAL COMPOSITION KIT COMPRISING QUATERNARY DI(POLYOXYALKYLENE) AMMONIUM ALKYL SULFATES

Yulchi Hioki; Kazuhiko Kurita; Keiko Kawabata, and Toshikazu Azuma, all of Wakayama, Japan, assignors to KAO Corporation, Tokyo, Japan Division of Ser. No. 305,731, Sep. 14, 1994, Pat. No. 5,462,912, which is a continuation of Ser. No. 957,819, Oct. 8, 1992. This application Jun. 5, 1995, Ser. No. 462,881


Claims priority, application Japan, Oct. 9, 1991, 3-262014

Int. Cl. A01N 25/30; B65D 85/82

U.S. Cl. 504—116

23 Claims

1. A kit (1) comprising package (A) comprising a mixture of compounds represented by the following general formula (I) and having (n1+n2+n3) and (n4+n5+n6) each being a number of 0 to 100 on the average and package (B) comprising an agricultural chemical, wherein the weight ratio of the mixture to the agricultural chemical ranges from 0.1 to 50:



wherein R₁ and R₂ each represent a straight-chain or branched alkyl, alkenyl or hydroxyalkyl group having from 1 to 30 carbon atoms; R₃ represents a straight-chain or branched alkyl group having from 1 to 4 carbon atoms;

(EO)_{n1} and (EO)_{n4} each represent a polyoxyethylene chain; (PO)_{n2} and (PO)_{n5} each represent a polyoxypropylene chain; (BO)_{n3} and (BO)_{n6} each represent a polyoxybutylene chain;

n1, n2, n3, n4, n5 and n6 each are 0 or a positive integer; and (n1+n2+n3) and (n4+n5+n6) each are 0 or a positive integer provided that at least one of (n1+n2+n3) and (n4+n5+n6) is 1 or more.

5,587,354

DRILLING FLUID AND DRILLING FLUID ADDITIVE

William M. Duncan, Jr., Nueces County, Tex., assignor to Integrity Industries, Inc., Kingville, Tex. Continuation of Ser. No. 142,953, Oct. 29, 1993, abandoned, which is a continuation of Ser. No. 950,491, Sep. 25, 1992, abandoned. This application Apr. 26, 1994, Ser. No. 233,501

Int. Cl. C09K 7/02

7 Claims

U.S. Cl. 507—137

10 Claims

1. A water based drilling fluid comprising water, a weight material, a viscosifier and 1–8% of (a) 30–95 parts by volume of a cyclic terpene and (b) 70–5 parts by volume of an oil selected from the group consisting of vegetable oil, mineral oil and mixtures thereof.

5,587,355

HIGH LOAD-CARRYING TURBO OILS CONTAINING AMINE PHOSPHATE AND THIOPHENE CARBOXYLIC ACID DERIVATIVES


Morton Beltzer, Westfield; Paul J. Berlowitz, East Windsor, and Jeonok T. Kim, Holmdel, all of N.J., assignors to Exxon Research and Engineering Company, Florham Park, N.J. Filed Dec. 22, 1995, Ser. No. 577,659

Int. Cl. C10M 141/10; 141/08; 135/32; 137/08

U.S. Cl. 508—302

9 Claims

1. A turbo oil comprising a major amount of a base stock suitable for use as a turbo oil base stock comprising synthetic polyol ester and a minor amount of additives comprising a mixture of thiophene carboxylic acid (TCA) derivative represented by the structural formula



where R₅ is COOH or linear C₁–C₁₂ alkanic acid and one or more amine phosphate(s) wherein the amine phosphate is mono- or di-alkyl amine salts of mixed mono- and di-acid phosphates, wherein the amine phosphate and TCA derivative are used in a weight ratio of 1:1 to 1:10, and wherein the TCA derivative is present in an amount by weight in the range 100 to 1,000 ppm and the amine phosphate is present in an amount in the range 50 to 300 ppm all based on base stock.

5,587,356

THICKENED, HIGHLY AQUEOUS, COST EFFECTIVE LIQUID DETERGENT COMPOSITIONS

Shelley L. Dauderman, Rising Sun, Ind.; Linda C. McWilliams, Cincinnati, Ohio; Hari A. Nair, Cincinnati, Ohio, and Gary G. Staud, Cincinnati, Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Filed Apr. 3, 1995, Ser. No. 415,952

Int. Cl. C11D 3/386; 3/330; 1/12

U.S. Cl. 510—320

10 Claims

1. A heavy duty liquid detergent composition which provides cost effective stain and soil removal performance when used in fabric laundering operations, which composition comprises:

(A) from about 10% to 12% by weight of the composition of an anionic surfactant component which is free of alkyl benzene sulfonate anionic surfactant materials and which comprises (i) sodium C₁₂–C₁₄ alkyl sulfates; and

5,587,358

POTENTIATORS OF ANTIMICROBIAL ACTIVITY

Masayuki Sukigara, Suzuka, Japan, and Isao Kubo, Moraga, Calif., assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan

Filed May 9, 1994, Ser. No. 239,671

Int. Cl. A61K 38/12; 31/11; 31/405

U.S. Cl. 514—11

11 Claims

2. A method for preventing the growth of a microorganism selected from the group consisting of gram-negative bacteria, gram-positive bacteria and yeast comprising contacting said microorganism with a polymyxin and a potentiator of antimicrobial activity, wherein said potentiator is indole, 3-methylindole, or t-2-hexenal.

5,587,359

HUMAN DERIVED GLYCOPROTEIN, BIOLOGICALLY ACTIVE FACTOR WHICH INCLUDES GLYCOPROTEIN AND PHARMACEUTICAL PRODUCT

Kanji Higashio; Shinjiro Mitsuda; Nobuyuki Shima, all of Saitama; Yasuharu Itagaki, and Masayuki Nagao, both of Tochigi, all of Japan, assignors to Snow Brand Milk Products Co., Ltd., Hokkaido, Japan

Continuation of Ser. No. 752,558, Sep. 6, 1991, abandoned.


This application Sep. 12, 1994, Ser. No. 304,419

Claims priority, application Japan, Mar. 10, 1989, 1-58631; Jan. 16, 1990, 2-6692

Int. Cl. C07H 17/00; A01N 37/00; C07K 14/475

U.S. Cl. 514—12

5 Claims



5,587,357

LIQUID CLEANING COMPOSITIONS

Robert Rhinesmith, Somerset, N.J., assignor to Colgate-Palmolive Co., Piscataway, N.J.

Continuation-in-part of Ser. No. 303,243, Sep. 9, 1994, Pat. No. 5,462,690. This application Aug. 9, 1995, Ser. No. 512,853

The portion of the term of this patent subsequent to Oct. 31, 2012, has been disclaimed.

Int. Cl. C11D 1/20; 1/72; 1/722; 3/18

U.S. Cl. 510—417

6 Claims

1. A stable gelled microemulsion cleaning composition which comprises approximately by weight:

- 6% to 18% of a C₁₀ to C₂₀ unsaturated fatty acid;
- 0.4% to 7% of an alkali metal hydroxide;
- 0.1% to 5% of a hydrotrope;
- 1% to 7% of a nonionic surfactant selected from the group consisting of primary aliphatic alcohol ethoxylates, secondary aliphatic alcohol ethoxylates, alkyl phenol ethoxylates and ethylene oxide propylene oxide condensates on primary alkanols;
- 1% to 50% of a cosurfactant selected from the group consisting of C₃₋₄ alkanols, polypropylene glycol of the formula HO(CH₂CHCH₂O)_nH, wherein n is a number from 2 to 18, monoalkyl ethers and esters having the formulas R(X)_mOH and R₁(X)_mOH where R is a C₁–C₆ alkyl group, R₁ is a C₂–C₄ acyl group, X is (OCH₂CH₂) or (OCH₂(CH₂)CH) and m is a number from 1 to 4;
- 0.1% to 25% of a water insoluble hydrocarbon selected from the group consisting of perfume, d-limonene and paraffins or isoparaffins having about 6 to about 18 carbon atoms; and
- the balance being water, wherein the composition does not contain any organic or inorganic builder salt.



1. An isolated DNA molecule having a DNA sequence encoding a glycoprotein which is obtained from the culture broth of human derived fibroblasts and which is characterized by the following physicochemical properties:

- Molecular weight: On the determinations of molecular weight of SDS gel electrophoresis, 78,000±2,000 or 74,000±2,000 under the nonreduced conditions and a common band A with 52,000±2,000 and band B with 30,000±2,000 or band C with 26,000±2,000 under the reduced conditions;
- Isoelectric point: 7.4 to 8.6;
- Heat stability: Stable in heating at 60° C. for 10 min.;
- pH stability: Stable in the range of pH 6 to 9;
- Carbohydrate chain: Adsorbed to a Concanavalin A (Con A)-Sephacrose column;
- Biological activity: Inhibits the growth of KB cells, Hela cells and L-929 cells but not IMR-90 cells;
- Reactivity to antibodies: The cytotoxic activity is not neutralized by anti-TNF antibody, anti-lymphotoxin antibody and anti-interferon-β antibody;
- N-terminal amino acid sequence: Above mentioned band B and band C are subchains of band A, respectively;

N-terminus of band A is blocked; Band B and band C have a common N-terminal amino acid sequence as follow:



or



wherein X is an unidentified amino acid.

5,587,360

PLATELET ADHESION INHIBITOR

Roy T. Sawyer, Dyfed, United Kingdom, assignor to Merck Patent GmbH, Darmstadt, Germany
PCT No. PCT/GB91/01763, § 371 Date Apr. 9, 1993, § 102(e) Date Apr. 9, 1993, PCT Pub. No. WO92/07005, PCT Pub. Date Apr. 30, 1992

PCT Filed Oct. 10, 1991, Ser. No. 39,276

Claims priority, application United Kingdom, Oct. 10, 1990, 9022040

Int. Cl.⁶ A61K 38/58

U.S. Cl. 514—21

13 Claims

1. A purified protein isolated from the leech species *Hirudo medicinalis*, said purified protein being substantially free of leech-derived collagenase, capable of binding to native collagen in such a way that substantially no cleavage breakdown products of collagen molecules occur on SDS-PAGE, capable of inhibiting collagen-induced platelet aggregation or adhesion, having a molecular weight in the range of 60–70 kilodaltons in a reduced form and exhibiting optimum activity in inhibiting collagen-induced platelet aggregation at a pH of about 8.0 in the presence of co-factors Ca^{+2} and Mg^{+2} , said protein being obtained from secretions or extract of the tissue of said leech species by performing chromatographic purification steps using buffers containing about 12% ethanol to prevent protein loss by adsorption and removing said ethanol to obtain said purified protein.

5,587,361

OLIGONUCLEOTIDES HAVING PHOSPHOROTHIOATE LINKAGES OF HIGH CHIRAL PURITY

Phillip D. Cook, San Marcos, Calif., and Glenn Hoke, Mt. Airy, Md., assignors to Isis Pharmaceuticals, Inc., Carlsbad, Calif.
Continuation-in-part of Ser. No. 297,703, Aug. 29, 1994, Pat. No. 5,506,212, and Ser. No. 58,023, May 5, 1993, Pat. No. 5,521,302, which is a division of Ser. No. 777,670, Oct. 15, 1991, Pat. No. 5,212,295, which is a continuation-in-part of Ser. No. 777,007, Oct. 16, 1991, abandoned, said Ser. No. 297,703 is a continuation of Ser. No. 777,007. This application Jun. 6, 1995, Ser. No. 469,851

Int. Cl.⁶ C07H 21/00

U.S. Cl. 514—44

18 Claims

1. A phosphorothioate oligonucleotide complementary to a sequence of targeted RNA or DNA wherein at least 75% of the nucleoside units of said oligonucleotide are joined together by Sp phosphorothioate 3' to 5' intersugar linkages.

5,587,362

L-NUCLEOSIDES

Chung K. Chu, Athens, Ga.; Yung-Chi Cheng, Woodbridge, Conn.; Balakrishna S. Pal, New Haven, Conn., and Gang-Qing Yao, Guilford, Conn., assignors to Univ. of GA Research Foundation, Athens, Ga., and Yale University, New Haven, Conn.


Filed Jan. 28, 1994, Ser. No. 189,070

Int. Cl.⁶ A61K 31/70

U.S. Cl. 514—46

38 Claims

1. A compound of the formula:



wherein R is selected from the group consisting of 5-methyluracil, adenine and cytosine, and R' is selected from the group of hydrogen, acyl, or alkyl or a monophosphate, diphosphate or triphosphate ester.

5,587,363

AMINOSUGAR AND GLYCOSAMINOGLYCAN COMPOSITION FOR THE TREATMENT AND REPAIR OF CONNECTIVE TISSUE

Robert W. Henderson, Baldwin, Md., assignor to Nutramax Laboratories, Inc., Baltimore, Md.
Continuation-in-part of Ser. No. 40,936, Mar. 31, 1993, Pat. No. 5,364,845. This application Mar. 14, 1994, Ser. No. 207,581

Int. Cl.⁶ A61K 31/715; 31/69

U.S. Cl. 514—54

22 Claims

1. A therapeutic composition for treatment and repair of connective tissue in humans and animals comprising: therapeutic synergistic quantities of an aminosugar selected from the group consisting of glucosamine, glucosamine salts and mixtures thereof in combination with a glycosaminoglycan selected from the group consisting of chondroitin, chondroitin salts, and mixtures thereof.

5,587,364

USES OF ALOE PRODUCTS IN THE TREATMENT OF INFLAMMATORY DISEASES

Bill H. McAnalley, Grand Prairie; Robert H. Carpenter, Bastrop, and Harley R. McDaniel, Dallas, all of Tex., assignors to Carrington Laboratories, Inc., Irving, Tex.
Division of Ser. No. 159,830, Dec. 1, 1993, Pat. No. 5,441,943, which is a division of Ser. No. 864,583, Apr. 7, 1992, Pat. No. 5,308,838, which is a division of Ser. No. 558,905, Jul. 27, 1990, Pat. No. 5,118,673, which is a continuation-in-part of Ser. No. 229,164, Aug. 5, 1988, Pat. No. 5,106,616, which is a continuation-in-part of Ser. No. 144,872, Jan. 14, 1988, Pat. No. 4,851,224, which is a continuation-in-part of Ser. No. 869,261, Jun. 5, 1986, Pat. No. 4,735,935, which is a continuation-in-part of Ser. No. 810,025, Dec. 17, 1985, abandoned, which is a continuation-in-part of Ser. No. 754,859, Jul. 12, 1985, abandoned, which is a continuation-in-part of Ser. No. 750,321, Jun. 28, 1985, abandoned, which is a continuation-in-part of Ser. No. 649,967, Sep. 12, 1984, abandoned, which is a continuation of Ser. No. 375,720, May 7, 1982, abandoned. This application Jun. 5, 1995, Ser. No. 462,972

Int. Cl.⁶ A61K 31/715

U.S. Cl. 514—54

9 Claims

1. A method for treating an animal suffering from an inflammatory bowel disease, comprising:

administering to said animal an amount of acetylated mannan derivative of aloe origin sufficient to reduce the symptoms associated with said inflammatory bowel disease.

5,587,365

FUNGICIDAL MIXTURES

Horst Wingert; Hubert Sauter, both of Mannheim; Eberhard Ammermann, Heppenheim; Gisela Lorenz, Neustadt; Reinhold Saur, Böhl-Iggelheim; Klaus Schelberger, Gönheim, and Manfred Hampel, Neustadt, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany
Division of Ser. No. 515,051, Aug. 14, 1995, Pat. No. 5,532,260, which is a division of Ser. No. 311,183, Sep. 23, 1994, Pat. No. 5,476,868. This application Feb. 13, 1996, Ser. No. 600,822

Claims priority, application Germany, Sep. 24, 1993, 43 32 600.5


Int. Cl.⁶ A01N 37/18; 43/50; 43/64; 55/00

U.S. Cl. 514—63

12 Claims

1. A fungicidal mixture containing synergistic fungicidally effective amounts of

a) the oxime ether carboxamide of the formula



and

b) an azole compound selected from the group consisting of:

4-(4-chlorophenyl)-2-phenyl-2-(1H-1,2,4-triazol-1-yl)methylbutyronitrile (fenbuconazole);
3-(2,4-dichlorophenyl)-6-fluoro-2-(1H-1,2,4-triazol-1-yl)quinazolin-4(3H)-one (fluquinconazole);
bis(4-fluorophenyl) (methyl) (1H-1,2,4-triazol-1-yl)methylsilane (flusilazole);
N-propyl-N-[2-(2,4,6-trichlorophenoxy)ethyl]-imidazole-1-carboxamide (prochloraz); and
(±)-2-(2,4-dichlorophenyl)-3-(1H-1,2,4-triazol-1-yl)propyl 1,1,2,2-tetrafluoroethyl ether (tetraconazole);
wherein a) and b) are in a synergistic weight ratio of 10:1 to 0.1:1.

5,587,366

COMPOSITIONS USEFUL IN PROPHYLAXIS AND THERAPY OF ENDOTOXIN RELATED CONDITIONS

Thomas S. Parker, Brooklyn; Daniel M. Levine, New York, both of N.Y.; Albert L. Rubin, Englewood, N.J.; Bruce R. Gordon, and Stuart D. Saal, both of New York, N.Y., assignors to The Rogosin Institute, New York, N.Y.
Continuation-in-part of Ser. No. 288,568, Aug. 10, 1994, Pat. No. 5,506,218, which is a continuation-in-part of Ser. No. 928,930, Aug. 12, 1992, Pat. No. 5,344,822. This application Jun. 7, 1995, Ser. No. 487,461

Int. Cl.⁶ A61K 31/685; 31/56; 31/22; 31/23; 31/13

U.S. Cl. 514—78

5 Claims

1. Protein and peptide free composition useful in treating endotoxemia, comprising:

(a) neutral lipids in an amount ranging from about 3% to about 50% by weight total lipid in said composition, wherein at least a portion of said neutral lipids are triglycerides, and
(b) at least one phospholipid.

5,587,367

PHARMACEUTICAL OR COSMETIC COMPOSITION CONTAINING A COMBINATION OF A RETINOID AND A STEROL

Uwe Reichert, Le Bar S/Loup; Rainer Schmidt, Mougins, and Braham Shroot, Antibes, all of France, assignors to Centre International de Recherches Dermatologiques Galderma (CIRD Galderma), Valbonne, France
Division of Ser. No. 962,596, Mar. 2, 1993. This application May 23, 1995, Ser. No. 447,776

Claims priority, application France, Jul. 2, 1990, 90 08344 Int. Cl.⁶ A61K 31/44; 31/575; 31/38; 31/415

U.S. Cl. 514—171

23 Claims

1. A pharmaceutical or cosmetic composition comprising in combination

at least one retinoid capable of inhibiting the expression of membranal transglutaminase, said retinoid having a heterocycle moiety, and

at least one sterol which functions as an inhibitor of the biosynthesis of cholesterol.

5,587,368


ADMINISTRATION OF A 27-HYDROXYCHOLESTEROL OR RELATED COMPOUND OR STEROL-27-HYDROXYLASE STIMULANT TO PREVENT RESTENOSIS FOLLOWING VASCULAR ENDOTHELIAL INJURY

Norman B. Javitt, New York, N.Y., assignor to New York University, New York, N.Y.
Continuation-in-part of Ser. No. 159,226, Nov. 30, 1993, Pat. No. 5,376,652. This application Oct. 6, 1994, Ser. No. 319,225 Int. Cl.⁶ A61K 31/56

U.S. Cl. 514—177

22 Claims

1. In a process wherein in a mammal, a therapeutic procedure is carried out to reduce or remove a stenosis present within a lumen of a blood vessel, the improvement to prevent restenosis which comprises administering to the mammal a restenosis preventing amount of a compound of formula (I):



wherein R₁ is hydroxyl or keto; R₂ is hydrogen, hydroxyl or keto; R₃ is hydroxyl, carboxyl, hydrogen or amino; R₄ and R₅ are hydrogen or amino; with the provisos that when R₃ is hydroxyl both R₄ and R₅ are hydrogen and when R₃ is not hydroxyl, at least one of R₃, R₄ and R₅ is amino (—NH₂) and the other(s) of them are hydrogen or amino, and pharmaceutically acceptable derivatives and salts thereof.

5,587,369

METHODS FOR PREVENTING PROGRESSIVE TISSUE NECROSIS, REPERFUSION INJURY, BACTERIAL TRANSLOCATION AND ADULT RESPIRATORY DISTRESS SYNDROME


Raymond A. Daynes, Park City, and Barbara A. Araneo, Salt Lake City, both of Utah, assignors to University of Utah Research Foundation, Salt Lake City, Utah
Continuation-in-part of Ser. No. 446,569, May 19, 1995, Pat. No. 5,489,581, which is a division of Ser. No. 284,688, Aug. 9, 1994, Pat. No. 5,532,230, which is a continuation-in-part of Ser. No. 29,422, Mar. 9, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 480,744

Int. Cl.⁶ A61K 31/56

U.S. Cl. 514—178

13 Claims

1. A method for preventing or reducing adult respiratory distress syndrome (ARDS) in a patient at high risk of ARDS, which comprises administering a therapeutically effective amount of a compound of the formula




wherein

X is H or halogen;

R¹, R² and R³ are independently =O, —OH, —SH, H, halogen, pharmaceutically acceptable ester, pharmaceutically acceptable thioester, pharmaceutically acceptable ether, pharmaceutically acceptable thioether, pharmaceutically acceptable monosaccharide, disaccharide or oligosaccharide, spirooxirane, spirothirane, —OSO₂R¹ or —OPOR¹R²;

R⁴ and R⁶ are independently —OH, pharmaceutically acceptable esters or pharmaceutically acceptable ethers; and pharmaceutically acceptable salts.

with the proviso that said compound is not of the formula



wherein

R⁷ is =O or OH;

R⁸ is H or halogen when R⁷ is =O and R⁸ is H when R⁷ is OH;

R⁹ is H, fatty acid, C₁₋₁₀ alkyl, C₁₋₁₀ alkenyl, C₁₋₁₀ acetylenic, (Y)_n-phenyl-C₁₋₅-alkyl, (Y)_n-phenyl-C₁₋₅-alkenyl or —CO—R¹¹;

R¹⁰ is H or OH;

R¹¹ is H, fatty acid, C₁₋₁₀ alkyl, C₁₋₁₀ alkenyl, C₁₋₁₀ acetylenic, (Y)_n-phenyl-C₁₋₅-alkyl or (Y)_n-phenyl-C₁₋₅-alkenyl;

Y is the same or different, and is halogen, C₁₋₄ alkyl, C₁₋₄ alkenyl, C₁₋₄ alkoxy, carboxy, nitro, sulfate, sulfonyl, C₁₋₄ carboxylesters or C₁₋₆ sulfate esters; and

n is 0, 1, 2 or 3.

5,587,370

ACARICIDALLY ACTIVE TETRAZINE DERIVATIVES


Janis Hajimichael; Sandor Botar; Edit Bleicher, all of Budapest; Laszlo Pap, Erd; Istvan Szekely, Dunakeszi; Katalin Marmarosi née Kellner, Batorbagy, and Janos Ori, Budapest, all of Hungary, assignors to Chinoi Gyogyszer es Vegyeszeti Termek Gyar RT., Budapest, Hungary
Continuation-in-part of Ser. No. 277,800, Jul. 20, 1994, Pat. No. 5,455,237. This application Aug. 30, 1995, Ser. No. 521,253

Claims priority, application Hungary, Jul. 21, 1993, 2098/93
Int. Cl.⁶ A01N 43/713; C07D 257/08

U.S. Cl. 514—183

7 Claims

1. A compound of the Formula (IV)



wherein

X is fluoro, chloro or bromo; and

Y is fluoro or hydrogen;

4. An acaricidal, larvicidal, and ovicidal active composition which comprises 0.5 to 99% by weight of a compound of the Formula (IV) as defined in claim 1, together with a carrier, diluting, filling or surface active agent.

5,587,371

TEXAPHYRIN-OLIGONUCLEOTIDE CONJUGATES


Jonathan L. Sessler, Austin, Tex.; Tarak D. Mody; Gregory W. Hemmi, both of Sunnyvale, Calif.; Vladimir A. Král, Austin, Tex., and Darren Magda, Cupertino, Calif., assignors to Pharmacyclis, Inc., Sunnyvale, Calif., and Board of Trustees, Univ. of TX Sys., Austin, Tex.
Continuation of Ser. No. 437,968, May 10, 1995, which is a continuation-in-part of Ser. No. 135,118, Oct. 12, 1993, Pat. No. 5,457,183, which is a continuation-in-part of Ser. No. 75,123, Jun. 19, 1993, abandoned, and Ser. No. 822,964, Jan. 21, 1992, Pat. No. 5,252,720. This application Jun. 2, 1995, Ser. No. 458,909

Int. Cl.⁶ A61K 31/715; C07D 487/22

U.S. Cl. 514—185

42 Claims


1. A texaphyrin having the structure:




wherein,

M is H, a divalent metal cation or a trivalent metal cation;

each of R₁, R₂, R₃, R₄, R₇, and R₈ is independently hydrogen, hydroxyl, alkyl, hydroxyalkyl, oxyalkyl, oxyhydroxyalkyl, saccharide, oxyaminoalkyl, carboxy, carboxyalkyl, carboxyamidealkyl, an oligonucleotide or a couple to an oligonucleotide, where at least one of R₁, R₂, R₃, R₄, R₇ and R₈ is an oligonucleotide or a couple to an oligonucleotide; and N is zero, 1 or 2.



and Ry are individually hydrogen or alkyl of 1 to 4 carbon atoms, R₄ is —OH or alkoxy of 1 to 8 carbon atoms, A and A' are individually selected from the group consisting of hydrogen, an equivalent of an alkali metal or alkaline earth metal, magnesium ammonium and an organic amine, or one or two of —COOA or —COOA' are —CO₂, the wavy line means —CH₂R₆ can be in the E or Z position, R₆ in the quaternary ammonium form is selected from the group consisting of



5,587,372 CEPHALOSPORINS

Jozsef Aszodi, Pontault Combault; Jean-Francois Chantot, Gressy En France; Patrick Fauveau, Livry Gargan; Solange G. D'Ambrieres, Paris; Daniel Hunbert, Foenay Sous Bois, and Christophe Dini, Le Plessis Pate, all of France, assignors to Roussel Uclaf, France

Continuation-in-part of Ser. No. 989,235, Dec. 11, 1992, Pat. No. 5,455,238. This application Dec. 13, 1993, Ser. No. 167,192


Claims priority, application France, Dec. 12, 1991, 91 15416; Sep. 28, 1992, 92 11520

Int. Cl.⁶ C07D 501/24; A61K 31/545



U.S. Cl. 514—202

19 Claims


1. A syn isomer in (R) or (S) form or a mixture thereof of a compound of the formula



syn isomer, in the (R) or (S) form or in the form of an (R,S) mixture, in the form of an internal salt or their salts with organic or mineral acids wherein R₇ is selected from the group consisting of



and



R₁ is selected from the group consisting of alkyl of 1 to 4 carbon atoms, —CN, carboxy and alkoxy carbonyl of 1 to 4 alkoxy carbon atoms, R₁, R₂, R₃ and R₄ are individually selected from the group consisting of hydrogen, halogen, hydroxy, alkyl of 1 to 4 carbon atoms optionally substituted with at least one member of the group consisting of halogen, alkoxy and alkylthio of 1 to 4 carbon atoms, —NO₂, —CN, —NH₂, mono- and dialkylamino of 1 to 4 carbon

5,587,373 2-ACYLOXYCEPHEM DERIVATIVES

M Marco Alpegiani, Milan; Pierluigi Bissolino, San Giorgio di Lomellina, and Ettore Perrone, Boffalora Ticino, all of Italy, assignors to Farmitalia Carlo Erba S.r.l., Milan, Italy
PCT No. PCT/EP94/00529, § 371 Date Nov. 4, 1994, § 102(e) Date Nov. 4, 1994, PCT Pub. No. WO94/20504, PCT Pub. Date Sep. 15, 1994

PCT Filed Feb. 24, 1994, Ser. No. 331,483


Claims priority, application United Kingdom, Mar. 4, 1993, 9304440

Int. Cl.⁶ C07D 501/04; 501/14; 501/60; A61K 31/545

U.S. Cl. 514—202

12 Claims

1. A compound of the formula (I), or a pharmaceutically or veterinarily acceptable salt thereof:



wherein n is one or two;

A and B are each, independently, hydrogen or an organic radical selected from optionally substituted C_1 - C_{12} straight or branched alkyl, C_2 - C_{12} alkenyl, C_2 - C_{12} alkynyl, C_6 - C_{14} aryl, C_3 - C_8 cycloalkyl, C_5 - C_8 cycloalkenyl, or C_7 - C_{18} aralkyl, C_8 - C_{18} aralkenyl, C_8 - C_{18} aralkynyl, $(C_3$ -cycloalkyl) alkyl, $(C_3$ -cycloalkyl) alkenyl, heterocyclyl, (heterocyclyl) alkyl and (heterocyclyl)alkenyl groups, wherein a heterocyclyl group is a 3- to 6-membered, saturated or unsaturated heterocyclyl ring containing at least one hetero atom selected from the group consisting of O, S and N, which is optionally fused to a second 5- or 6-membered, saturated or unsaturated heterocyclyl group, to a cycloalkyl group or to an aryl group;

R^1 represents

- (1) a chlorine, fluorine, bromine or iodine atom;
- (2) A as defined above;
- (3) an ether OA wherein A is as defined above;
- (4) a thioether, sulfoxide or sulfone $-S(O)_m A$ wherein m is either zero, one or two and A is as defined above;
- (5) acyloxy $-OC(O)A$ wherein A is as defined above;
- (6) sulfonyloxy $-OS(O)_2 A$ wherein A is as defined above;
- (7) an acylamino group $-NHC(O)A$ wherein A is as defined above or acylamino $-NH-Z$ wherein Z is a mono, di- or tripeptide composed of D or L α -amino acids selected from the group consisting of Ala, Gly, Val, Leu, Ile and Phe and with the terminal amino group either free or acylated by a group $-C(O)A$ or $-C(O)OA$ wherein A is as defined above;

R^2 represents





- (1) A as defined above;
- (2) a chlorine or fluorine atom;
- (3) a sulphenyl, sulfinyl or sulfonyl group $-S(O)_m A$ wherein A is as defined above;
- (4) an oxy group $-O-A$ wherein A is as defined above;
- (5) an acyl group $-C(O)A$ or acyloxy group $-C(O)OA$ wherein A is as defined above;
- (6) an oxymethyl group $-CH_2-OA$ wherein A is as defined above;
- (7) a thiomethyl group or a derivative thereof of formula $-CH_2S(O)_m A$ wherein m and A are as defined above;
- (8) an acyloxymethyl group $-CH_2OC(O)A$ or $-CH_2O-Z$ wherein A and Z are as defined above;
- (9) an acylthiomethyl group $-CH_2SC(O)A$ wherein A is as defined above;
- (10) an aminomethyl group $-CH_2-N(A)A'$ wherein A is as defined above and A', being the same or different, is as defined above for A; or A and A' taken together with the nitrogen atom to which they are attached represent a heterocyclic ring;
- (11) ammoniumethyl $-CH_2N^+(A)(A')A''$ wherein A and A' are as defined above and A'', being the same or different, is as defined for A; or A is alkyl and A' and A'' together with the nitrogen atom to which they are attached represent a heterocyclic ring, or A and A' and A'' together with the nitrogen atom to which they are attached represent a heterocyclic ring, wherein a heterocyclic ring is of the same cyclic structure defined above for a heterocyclyl group;
- (12) an acylaminomethyl group $-CH_2NH-C(O)A$ or $-CH_2NH-Z$ wherein A and Z are as defined above.

5,587,374
10(1-HYDROXYETHYL)-11-OXO-1-AZATRICYCLO/
7.2.0.0.^{3,8}UNDEC-2-ENE-2-CARBOXYLIC ACID ESTERS
AND A PROCESS FOR PREPARING THEREOF
 Alcide Perboni, San Giorgio de Mantova; Tino Rossi, Verona; Giovanni Gaviraghi, Verona; Giorgio Tarzia, Verona, and Antonella Ursini, Verona, all of Italy, assignors to Glaxo SpA, Verona, Italy
 Division of Ser. No. 264,239, Jun. 22, 1994, which is a continuation of Ser. No. 848,005, May 20, 1992, abandoned. This application Feb. 14, 1995, Ser. No. 388,515
 Claims priority, application United Kingdom, Aug. 21, 1990, 9018330; Mar. 7, 1991, 9104770


Int. Cl.⁶ C07D 487/00; A61K 31/395
 U.S. Cl. 514-210 3 Claims
 1. 1-Cyclohexyloxycarbonyloxyethyl (4S,8S,9R,10S, 12R)-4-methoxy-10-(1-hydroxyethyl)-11-oxo-1-azatricyclo[7.2.0.0.^{3,8}]undec-2-ene-2-carboxylate.

5,587,375
AZEPINONE COMPOUNDS USEFUL IN THE
INHIBITION OF ACE AND NEP
 Jeffrey A. Robl, Newtown, Pa., assignor to Bristol-Myers Squibb Company, Princeton, N.J.
 Filed Feb. 17, 1995, Ser. No. 390,717
 Int. Cl.⁶ C07D 223/32; A61K 31/55

U.S. Cl. 514-213 8 Claims
 1. A compound of the following formula II, or a pharmaceutically acceptable salt thereof:



R and R^6 are each independently hydrogen, alkyl, substituted alkyl, aryl- $(CH_2)_p$ -, substituted aryl- $(CH_2)_p$ -, heteroaryl- $(CH_2)_p$ -, $-CH(R^8)-O-C(O)-R^9$, or



R^1 and R^2 are each independently hydrogen, alkyl, substituted alkyl, cycloalkyl- $(CH_2)_p$ -, aryl- $(CH_2)_p$ -, substituted aryl- $(CH_2)_p$ -, heteroaryl- $(CH_2)_p$ -, or R^1 and R^2 may form, together with the carbon to which they are bonded, a 3 to 7

membered carbocyclic ring, where said ring is optionally substituted by alkyl, or by aryl which is fused or bonded by a single bond to said ring;

R^3 and R^4 are each independently hydrogen, alkyl, aryl, halo, or $-C(O)-OR$, where R is as defined above;

R^5 , R^{5a} , and R^{5b} are each independently hydrogen, alkyl, alkenyl, cycloalkyl, substituted alkyl, substituted alkenyl, aryl, substituted aryl, heteroaryl, cycloalkyl-alkylene-, aryl-alkylene-, substituted aryl-alkylene-, and heteroaryl-alkylene-, or R^{5a} and R^{5b} may form, together with the carbon to which they are bonded, a 3 to 7 membered carbocyclic ring, where said ring is optionally substituted by alkyl, or by aryl which is fused or bonded by a single bond to said ring;

R^7 is hydrogen, $R^8-C(O)-$, or $R^{12}-S-$;


R^8 is hydrogen, alkyl, substituted alkyl, cycloalkyl- $(CH_2)_p$ -, aryl- $(CH_2)_p$ -, substituted aryl- $(CH_2)_p$ -, or heteroaryl- $(CH_2)_p$;

R^9 is hydrogen, alkyl, alkoxy, or aryl;

R^{10} is alkyl or aryl- $(CH_2)_p$;

R^{11} is alkyl, substituted alkyl, cycloalkyl- $(CH_2)_p$ -, aryl- $(CH_2)_p$ -, substituted aryl- $(CH_2)_p$ -, or heteroaryl- $(CH_2)_p$;

R^{12} is hydrogen, alkyl, substituted alkyl, cycloalkyl- $(CH_2)_p$ -, aryl- $(CH_2)_p$ -, substituted aryl- $(CH_2)_p$ -, or heteroaryl- $(CH_2)_p$, or $-S-R^{12}$ completes a symmetrical disulfide wherein R^{12} is



p is zero or an integer from 1 to 6;
 q is zero or an integer from 1 to 3; and
 r is zero or one.


5,587,376
METHODS FOR USING (2-IMIDAZOLIN-2-YLAMINO)
QUINOXALINE DERIVATIVES

James A. Burke, Tustin; Michael E. Garst, Newport Beach, and Larry A. Wheeler, Irvine, all of Calif., assignors to Allergan, Waco, Tex.

Division of Ser. No. 390,265, Feb. 15, 1995, which is a continuation of Ser. No. 135,716, Oct. 13, 1993, abandoned. This application Jun. 2, 1995, Ser. No. 458,949

Int. Cl.⁶ A61K 31/495
 U.S. Cl. 514-249 18 Claims

1. A method of treating a mammal comprising administering to a mammal an effective amount to provide a desired therapeutic effect in said mammal of a compound selected from the group consisting of those having the formula




and pharmaceutically acceptable acid addition salts thereof and

mixtures thereof, wherein R_1 and R_2 each is selected from the group consisting of H, alkyl radicals containing 1 to 4 carbon atoms and alkoxy radicals containing 1 to 4 carbon atoms provided that R_1 and R_2 are not both H, the 2-imidazolin-2-ylamino group may be in any of the 5-, 6-, 7- or 8- positions of the quinoxaline nucleus, and R_3 , R_4 and R_5 each is located in one of the remaining 5-, 6-7 or 8-positions of the quinoxaline nucleus and is independently selected from the group consisting of CL, Br, H and alkyl radicals containing 1 to 3 carbon atoms, said desired therapeutic effect being selected from the group consisting of constriction of one or more blood vessels and decongestion of one or more nasal passages.

5,587,377
TERAZOSIN CRYSTALLINE POLYMORPH AND
PHARMACEUTICAL COMPOSITIONS THEREOF
 Mahendra R. Patel, East Brunswick; Kasireddy C. Reddy, New Brunswick, and Pankaj J. Dave, Kendall Park, all of N.J., assignors to Invamed, Inc., Dayton, N.J.

Filed Oct. 24, 1995, Ser. No. 547,209
 Int. Cl.⁶ C07D 239/84; A61K 31/505
 U.S. Cl. 514-254 3 Claims



1. A novel crystalline polymorph 1-(4-amino-6, 7-dimethoxy-2-quinazolinyl-4-(tetrahydrofuroyl) piperazine monohydrochloride monohydrate Form-IV, characterized by peaks in the powder X-ray diffraction pattern at values of two theta of 5.24±0.2, 9.66±0.2, 11.55±0.2, 15.84±0.2, 16.58 ±0.2, 17.39±0.2, 19.41±0.2, 20.42±0.2, 21.67±0.2, 22.55±0.2, 23.90 ±0.2, 24.81±0.2, 26.70±0.2, 27.17±0.2, 28.86±0.2, 29.46±0.2, 31.66 ±0.2, 31.99±0.2.

5,587,378
THERAPEUTIC AGENT FOR PARKINSON'S DISEASE
 Fumio Suzuki, Mishima; Junichi Shimada, Shizuoka-ken; Nobuaki Koike, Shizuoka-ken; Joji Nakamura, Shizuoka-ken; Shizuo Shiozaki, Fuji; Shunji Ichikawa, Shizuoka-ken; Akio Ishii, Shizuoka-ken, and Hiromi Nonaka, Shizuoka-ken, all of Japan, assignors to Kyowa Hakko Kogyo Co., Ltd., Tokyo, Japan


Division of Ser. No. 133,510, Oct. 17, 1993, Pat. No. 5,484,920, which is a continuation-in-part of Ser. No. 42,535, Apr. 5, 1993, abandoned. This application May 23, 1995, Ser. No. 447,885

Claims priority, application Japan, Apr. 8, 1992, 4-87715; Sep. 28, 1992, 4-257834


Int. Cl.⁶ A61K 31/52
 U.S. Cl. 514-264 14 Claims

1. A method of treating Parkinson's disease which comprises


administering to a patient suffering from Parkinson's disease an agriculturally acceptable carrier, an insecticidally effective amount of a compound of the following formula (I):



in which R^1 , R^2 , and R^3 are independently hydrogen, lower alkyl, or allyl; and R^4 is cycloalkyl, $-(CH_2)_n-R^5$, in which R^5 is unsubstituted or substituted phenyl or naphthyl, having 1 to 3 independently-selected substituents selected from the group consisting of lower alkyl, hydroxy, lower alkoxy, halogen, nitro and amino, or a substituted or unsubstituted heterocyclic group, wherein the heterocyclic group is selected from the group consisting of furyl, thienyl, pyrrolyl, pyranlyl, thiopyranlyl, pyridyl, thiazolyl, imidazolyl, pyrimidyl, triazinyl, indolyl, quinolyl, purinyl, and benzothiazolyl; and n is an integer of 0 to 4, or



wherein Y^1 and Y^2 is independently hydrogen or methyl; and Z is unsubstituted or substituted phenyl or naphthyl having 1 to 3 independently-selected substituents selected from the group consisting of lower alkyl, hydroxy, lower alkoxy, halogen, nitro and amino,



wherein R^6 is hydrogen, hydroxy, lower alkyl, lower alkoxy, halogen, nitro, or amino; and m represents an integer of 1 to 4, or a substituted or unsubstituted heterocyclic group wherein the heterocyclic group is furyl, thienyl, pyrrolyl, pyranlyl, thiopyranlyl, pyridyl, thiazolyl, imidazolyl, pyrimidyl, triazinyl, indolyl, quinolyl, purinyl, or benzothiazolyl; and X^1 and X^2 are independently O or S, or a pharmaceutical acceptable salt thereof.

5,587,379

INSECTICIDAL 5-SUBSTITUTED-2,4-DIAMINOPYRIMIDINE DERIVATIVES

Robert N. Henrie, II, East Windsor; Clinton J. Peake, Trenton; Thomas G. Cullen, Milltown; Albert C. Lew, Princeton Junction; Munirathnam K. Chaguturu, Lawrenceville, all of N.J.; Partha S. Ray, Memphis, Tenn., and Walter H. Yeager, Yardley, Pa., assignors to FMC Corporation, Philadelphia, Pa.


Division of Ser. No. 237,481, May 3, 1994, Pat. No. 5,521,192, which is a continuation-in-part of Ser. No. 985,084, Dec. 2, 1992, abandoned. This application May 22, 1995, Ser. No. 446,354

Int. Cl.⁶ A01N 43/54


U.S. Cl. 514—275

6 Claims

1. An insecticidal composition comprising, in admixture with an



wherein
R is



wherein

V^1 is halogen, lower alkyl, lower haloalkyl, cyano, or aminocarbonyl;

and wherein

R^1 is hydrogen, lower alkyl, amino, phenyl, or phenyl lower alkyl;

R^2 , R^3 , R^7 and R^8 are independently selected from hydrogen, lower alkyl, lower alkylcarbonyl, and lower alkoxy carbonyl;

m is 0 or 1;

n is 2 to 11; and

p is 0 or 1,

and agriculturally acceptable salts thereof, with the proviso that when m , n , and p are 0, R is other than hydrogen; and with the further proviso that when m and p are 1, n must be at least 1.

5,587,380

CERTAIN 2,4-DIAMINO-5-(2,3,5-TRI-CHLOROPHENYL)-6-SUBSTITUTED-PYRIMIDINES WHICH ARE PHARMACOLOGICALLY ACTIVE CNS COMPOUNDS

Alistair A. Miller; Malcolm S. Nohbs; Richard M. Hyde, and Michael J. Leach, all of Beckenham, England, assignors to Glaxo Wellcome Inc., Research Triangle Park, N.C.

Division of Ser. No. 444,963, Dec. 4, 1989, abandoned. This application Jun. 6, 1995, Ser. No. 469,518


Claims priority, application United Kingdom, Dec. 7, 1988, 8828620; Apr. 14, 1989, 8908561; Aug. 18, 1989, 8918893

Int. Cl.⁶ A61K 31/405; C07D 239/48

U.S. Cl. 514—275

20 Claims

1. A pyrimidine of formula (II):



wherein:

R_1 is selected from the group consisting of NH_2 , $N-(C_1-C_6 \text{ alkyl})amino$ and $N,N\text{-di}(C_1-C_6 \text{ alkyl})amino$;

R_2 is NH_2 ;

R_3 is selected from the group consisting of hydrogen, C_1-C_6 alkyl, trifluoromethyl, C_1-C_6 alkoxy, C_1-C_6 alkylthio, $(C_1-C_6 \text{ alkyl})thio$, $(C_1-C_6 \text{ alkyl})oxy$, $(C_1-C_6 \text{ alkyl})oxy$, $(C_1-C_6 \text{ alkyl})oxy$, and CH_2X wherein X is selected from the group consisting of hydroxy, C_1-C_6 alkoxy, phenoxy and benzyloxy;

R_6 is selected from the group consisting of NH_2 , hydrogen, halo and nitro; and

R_7 is hydrogen or halo;

and pharmaceutically acceptable acid addition salts thereof.

5,587,381

METHOD FOR TERMINATING METHADONE MAINTENANCE THROUGH EXTINCTION OF THE OPIATE-TAKING RESPONSES

John D. Sinclair, Nokkalaanniemi 7, SF-02230 Espoo, Finland
Filed Mar. 27, 1995, Ser. No. 410,529

Int. Cl.⁶ A61K 31/485; 31/44; 31/135

U.S. Cl. 514—282

9 Claims

1. A method for terminating methadone maintenance therapy and addition to other legally-available opiates by selective extinction of the opiate-taking response, comprising the steps of:

withholding all opiates from a subject suffering from addiction to a legally-available opiate for a sufficient time to prevent an opiate antagonist when administered to the subject from causing precipitous withdrawal; and

thereafter administering to the subject an opiate antagonist selected from the group consisting of nalmefene, naltrexone, naloxone, cyclazocine, etazocine, levallorphan, metazocine, nalorphine, and salts thereof in a daily dosage sufficient to block the effects of opiate agonists;

while the amount of the antagonist in the subject's body is sufficient to block opiate effects, having the subject self-administer the legally-available opiate agonist to which he or she is addicted;

withholding the opiate antagonist from the subject;

when the amount of antagonist is no longer sufficient to block opiate effects, not allowing the subject to self-administer opiates; and

continuing the above steps of administration of the opiate antagonist and the subject's taking of the opiate and the withholding of the antagonist for a period when the subject cannot take opiates until the opiate-taking behavior is extinguished.

5,587,382

6,9-BIS[(2-AMINOETHYL) AMINO]BENZO [G]ISOQUINOLINE-5,10-DIONE DIMALEATE; AN AZA-ANTHRACENEDIONE WITH REDUCED CARDIOTOXICITY

A. Paul Krapcho, Shelburne; Miles P. Hacker, Williston, both of Vt.; Ennio Cavalletti, Monza, and Ferdinando C. Giuliani, Cassina de Pecchi, both of Italy, assignors to Boehringer Mannheim Italia, SpA, Monza, Italy

Continuation-in-part of Ser. No. 218,946, Mar. 28, 1994, abandoned. This application Jun. 6, 1995, Ser. No. 467,874

Int. Cl.⁶ A61K 31/44

U.S. Cl. 514—290

4 Claims

1. A method of treatment of tumors susceptible to azaanthracene-dione therapy in a mammal requiring such treatment, which method causes minimal cardiotoxicity, comprising administering to the mammal an effective anti-tumor amount of the compound 6,9-bis[(2-aminoethyl)-amino]-benzo[g]isoquinoline-5,10-dione or a physiologically acceptable salt thereof wherein the mammal has been previously treated with mitoxantrone, doxorubicin, or any other anthracycline used in human therapy and has shown cardiotoxicity with said prior treatment.

5,587,383

IMIDAZOPYRIDINE DERIVATIVES AND THEIR USE

Muneo Takatani, Kyoto; Yoshio Kozai, Toyonaka; Kiminori Tomimatsu, Minoo, and Yumiko Shibouta, Suita, all of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

Division of Ser. No. 74,292, Jun. 9, 1993, Pat. No. 5,395,839, which is a division of Ser. No. 736,957, Jul. 30, 1991, Pat. No. 5,244,908. This application Feb. 10, 1995, Ser. No. 387,010


Claims priority, application Japan, Jul. 30, 1990, 2-202963; Jul. 30, 1990, 2-202964; May 27, 1991, 3-121277; Jun. 12, 1991, 3-140186

Int. Cl.⁶ A61K 31/435; C07D 471/02

U.S. Cl. 514—300


6 Claims

1. A compound of the formula (I''):



wherein X is S, $S(O)$, $S(O)_2$, O or NR^3 (wherein R^3 is a hydrogen or an optionally substituted hydrocarbon group);

A is a hydrocarbon group selected from the group consisting of (1) a group represented by the formula



wherein l , m and n are integers of 0 to 5;


R^4 , R^5 , R^6 , R^7 , R^8 and R^9 are hydrogen, an optionally substituted lower alkyl, aralkyl or aryl group; and wherein R^4 and R^5 , R^6 and R^7 or R^8 and R^9 may bind together to form a ring, or R^4 or R^6 may bind together with R^5 or R^7 to form a ring;

(2) a group represented by the formula



and

(3) a group represented by the formula



wherein o and p are integers of 0 to 5;

R^1 and R^2 are the same or different and are a hydrogen, an optionally substituted hydrocarbon group, a halogen, a nitro group, a nitroso group, an optionally protected amino group, a lower alkoxy carbonyl group or a lower alkyl carbamoyl group; and

B^1 is a hydroxyl group acylated by an acyl group derived from a carboxylic acid or a N-hydrocarbon substituted carbamic acid, or its salt or solvate.

5,587,384

INHIBITORS OF POLY(ADP-RIBOSE) SYNTHETASE AND USE THEREOF TO TREAT NMDA NEUROTOXICITY

Jie Zhang; Valina L. Dawson; Ted M. Dawson, and Solomon H. Snyder, all of Baltimore, Md., assignors to The Johns Hopkins University, Baltimore, Md., and The United States of America, Washington, D.C.

Filed Feb. 4, 1994, Ser. No. 191,508

Int. Cl.⁶ A61K 31/165; 31/47

U.S. Cl. 514—309

20 Claims

1. A method of treating a disease condition caused by NMDA neurotoxicity in a mammal comprising:

administering to a mammal which demonstrates symptoms of a disease condition caused by NMDA neurotoxicity a therapeutically effective amount of an inhibitor of poly (ADP-ribose) synthetase.

5,587,385

ARYLIDENE-HETEROCYCLIC DERIVATIVES AND PROCESS FOR THEIR PREPARATION

Franco Buzzetti, Monza; Silvia Fustinoni, Milan; Maria G. Brasca, Cusago, and Sergio Penco, Milan, all of Italy, assignors to Farmitalia Carlo Erba S.r.L., Milan, Italy
Division of Ser. No. 400,113, Mar. 6, 1995, which is a continuation of Ser. No. 988,867, Dec. 10, 1992, abandoned. This application May 26, 1995, Ser. No. 452,288


Claims priority, application United Kingdom, Dec. 24, 1991, 9127401; Jan. 29, 1992, 9201906; Mar. 24, 1992, 9206369

Int. Cl.⁶ A61K 31/47; 31/475; C07D 401/06; 401/08

U.S. Cl. 514—309

5 Claims


1. A method of treating a pathological proliferative disorder comprising administering to a patient a therapeutically effective amount of a compound of formula (IA)



wherein

Ar is mono- or bicyclic ring system selected from quinoline or indole;

Het is;



R is hydrogen, halogen, hydroxy, C₁-C₆ alkoxy, C₂-C₆ acyloxy, cyano, nitro, amino or —COOR₃ in which R₃ is hydrogen or C₁-C₆ alkyl;

R₁ is hydrogen, hydroxy, C₁-C₆ alkyl, C₁-C₆ alkoxy, C₂-C₆ acyloxy, cyano, nitro, amino or —COOR₃ in which R₃ is as defined above; and

R₂ is hydrogen, halogen, hydroxy or C₁-C₆ alkyl, or its pharmaceutically acceptable salt.

5,587,386

OPTICALLY ACTIVE PYRIDONECARBOXYLIC ACID DERIVATIVES

Isao Hayakawa, and Youichi Kimura, both of Tokyo, Japan, assignors to Daiichi Pharmaceutical Co., Ltd., Tokyo, Japan
Continuation of Ser. No. 610,916, Nov. 9, 1990, abandoned, which is a continuation-in-part of Ser. No. 343,567, Apr. 27, 1989, abandoned. This application Oct. 28, 1993, Ser. No. 142,105


Claims priority, application Japan, Apr. 27, 1988, 63-104625; Nov. 24, 1988, 63-296984

Int. Cl.⁶ C07D 471/04; 215/56; A61K 31/47; 31/44

U.S. Cl. 514—312


9 Claims

1. A stereoisomerically pure N₁-(1,2-cis-2-halogenocyclopropyl)-substituted pyridonecarboxylic acid derivative represented by the following formula (I):



wherein R¹ represents a hydrogen atom, an amino group, a hydroxyl group or a thiol group;

R² represents a substituent represented by the following formula:



wherein R²³ and R²⁴ together are (CH₂)_j; where j=2 to 5;

A represents C—X³ or a nitrogen atom;

X¹ and X², which may be the same or different, each represents a halogen atom;

and X³ represents a halogen atom, an alkyl group of from 1 to 6 carbon atoms, an alkoxy group from 1 to 6 carbon atoms, a cyano group, a trifluoromethyl group, or a hydrogen atom; or a pharmaceutically acceptable salt thereof.

5,587,387

HETEROCYCLE-SUBSTITUTED BENZENEMETHANAMINE DERIVATIVES

Marcel A. C. Janssen, Vosselaar; Georges H. P. Van Daele, Turnhout; Jean-Paul R. M. A. Bosmans, Edegem; Marc G. C. Verdonck, Glerle, and Paul A. J. Janssen, Vosselaar, all of Belgium, assignors to Janssen Pharmaceutica N.V., Beerse, Belgium


Continuation-in-part of Ser. No. 240,737, May 12, 1994, Pat. No. 5,480,997. This application May 2, 1995, Ser. No. 432,748
Claims priority, application European Pat. Off., Dec. 30, 1991, 91203431

Int. Cl.⁶ A61K 31/47; C07D 215/38; 215/22; 215/20

U.S. Cl. 514—312

6 Claims

1. A compound of the formula:



a pharmaceutically acceptable acid addition salt form or a stereochemically isomeric form thereof, wherein:

R¹ and R² each independently are halo or methyl;

R³ is hydrogen, halo, nitro or trifluoromethyl;

R⁴ is


trifluoromethyl or methyl carbonyl; or

a radical —C(=X)—NR⁵R⁶ wherein X is O or S, and R⁵ and R⁶ each independently are hydrogen or C₁₋₄alkyl; or

a radical —Alk-R⁷, wherein Alk is C₁₋₄alkanedyl; and

R⁷ is hydrogen or hydroxy; and

Het is a heterocyclic radical of the formula:



wherein:

R¹⁴ and R¹⁵ taken together form C₃₋₄alkanedyl, and

R¹³ is hydrogen or hydroxy, wherein in the heterocyclic radical (d), a nitrogen atom can optionally be oxidized,

PROVIDED THAT when the heterocyclic radical (d) is a 5,6,7,8-tetrahydro-4-quinoliny group, R¹³ is hydroxy.

5,587,388

IRREVERSIBLE HIV PROTEASE INHIBITORS, INTERMEDIATES, COMPOSITIONS AND PROCESSES FOR THE PREPARATION THEREOF

Sung C. Kim; Nakyeon Choy; Chang S. Lee; Young C. Son; Ho I. Choi; Jong S. Koh; Heungsik Yoon; Chi H. Park, and Sang S. Kim, all of Daejeon, Rep. of Korea, assignors to Lucky Limited, Seoul, Rep. of Korea

Filed Nov. 30, 1993, Ser. No. 159,382


Claims priority, application Rep. of Korea, Dec. 2, 1992, 92-23088; Dec. 2, 1992, 92-23089; Jun. 14, 1993, 93-10811; Oct. 14, 1993, 93-21298; Oct. 14, 1993, 93-21299; Oct. 14, 1993, 93-21300

Int. Cl.⁶ C07D 215/38; A61K 31/47

U.S. Cl. 514—314

4 Claims


1. Cis-epoxide compounds of formula (I-1) and pharmaceutically acceptable salts, hydrates and solvates thereof:



wherein:

R¹ is a cycloalkyl, or aryl-substituted lower alkyl group;


A is a functionalized acyl group of the formula



(wherein R² is a C₁₋₄ alkyl, or amide-substituted C₁₋₂ alkyl group;

R³ is a quinoline radical; and m is 0 or 1); and

B is a functionalized amino group of the formula



(wherein R⁶ is a C₁₋₄ alkyl, arylalkyl, or amide-substituted C₁₋₂ alkyl group; R⁷ is a C₁₋₃ alkoxy, C₁₋₃ alkylamino, C₁₋₃ alkoxy-amino or amino group substituted with two C₁₋₃ alkyl groups; and n is 1 or 2).

5,587,389

SUBSTITUTED HETEROARYLAKYLTHIOPYRIDINES FOR CONTROLLING HELICOBACTER BACTERIA

Bernhard Kohl; Jörg Senn-Bilfinger, and Gerhard Grundler, all of Konstanz, Germany, assignors to BYK Gulden Lomberg Chemische Fabrik GmbH, Konstanz, Germany
PCT No. PCT/EP94/00393, § 371 Date Aug. 15, 1995, § 102(e)
Date Aug. 15, 1995, PCT Pub. No. WO94/19346, PCT Pub. Date Sep. 1, 1994

PCT Filed Feb. 11, 1994, Ser. No. 505,270


Claims priority, application Switzerland, Feb. 17, 1993, 0050793

Int. Cl.⁶ A61K 31/415; 31/44; C07D 213/70; 233/42

U.S. Cl. 514—338

10 Claims

1. A compound of the formula I



in which

R¹ is hydrogen, 1-4C-alkyl or 1-4C-alkoxy,

R² is hydrogen, 1-4C-alkyl, 1-4C-alkoxy, halogen, trifluoromethyl, fully or predominantly fluorine-substituted 1-4C-alkoxy, chlorodifluoromethoxy, 2-chloro-1,1,2-trifluoroethoxy, or, if desired, together with R³ 1-2C-alkylenedioxy which is fully or partially substituted by fluorine, or chlorotrifluoroethylenedioxy,

R³ is hydrogen, 1-4C-alkoxy which is fully or predominantly substituted by fluorine, or is chlorodifluoromethoxy, 2-chloro-1,1,2-trifluoroethoxy, or, if desired, together with R² 1-2C-alkylenedioxy which is fully or partially substituted by fluorine, or chlorotrifluoroethylenedioxy,

R⁴ is hydrogen or 1-4C-alkyl,

R⁵ is hydrogen, 1-4C-alkyl or 1-4C-alkoxy,

R⁶ is a heterocycle selected from the group consisting of furan, thiophene, pyrrole, oxazole, isoxazole, thiazole, isothiazole, imidazole, pyrazole, 1,2,3-triazole, 1,2,4-triazole, tetrazole, 1,3,4-thiadiazole, 1,2,4-thiadiazole, pyrimidine and pyridine, each of which is substituted by R⁸ and R⁹,

R⁷ is hydrogen, 1-4C-alkyl or 1-4C-alkoxy,

R⁸ is hydrogen, 1-4C-alkyl, 1-4C-alkoxy, halogen, guanidino, 1-4C-alkyl which is substituted by R¹⁰, or —N(R¹¹)R¹²,

R⁹ is hydrogen, 1-4C-alkyl, 1-4C-alkoxy or halogen,

R¹⁰ is hydroxyl, 1-4C-alkoxy or —N(R¹¹)R¹², where

R¹¹ is hydrogen, 1-4C-alkyl or —CO—R¹³ and

R¹² is hydrogen or 1-4C-alkyl, or where

R¹¹ and R¹² together and including the nitrogen atom to which

both are bonded represent a piperidino or morpholino radical,

R¹³ is hydrogen, 1-4C-alkyl or 1-4C-alkoxy.

m is a number from 1 to 7,
n is the number 0 or 1 and
p is the number 0 or 1,
or a salt thereof.

5,587,390

IMIDAZOLE DERIVATIVES HAVING A II ANTAGONIST ACTIVITY

Aldo Salimbeni; Fabio Paleari; Jacques Mizrahi, and Carlo Scolastico, all of Milan, Italy, assignors to Istituto Luso Farmaco D'Italia S.p.A., Milan, Italy

PCT No. PCT/EP93/02024, § 371 Date Mar. 17, 1995, § 102(e) Date Mar. 17, 1995, PCT Pub. No. WO94/03449, PCT Pub. Date Feb. 17, 1994


PCT Filed Jul. 29, 1993, Ser. No. 379,468

Claims priority, application Italy, Aug. 7, 1992, MI92A1951
Int. Cl.⁶ A61K 31/44; 31/415; C07D 233/56; 401/06

U.S. Cl. 514—341


11 Claims

1. Compounds of general formula (I):



wherein:



n is 0, 1 or 2
X is O, S.



wherein Z is C or N, whereas Y is H, when Z is C or oxygen or it is not present, when Z is the same as N;

R₁ is C₁-C₅ straight, branched or cyclic alkyl, or a C₂-C₅ alkenyl group;

R₂ is a —COOR₈ group, —CN, a SO₃H group, or a tetrazole group of general formula (IIa) or (IIb):



R₃, R₄ are independently H, halogen, CN, NO₂, NH₂, COR₇, OR₈, CH₂OR₈, C₁-C₅ straight or branched alkyl;
R₅ is H, C₁-C₅ straight or branched alkyl, benzyl;
R₆ is H, C₁-C₅ alkyl, triphenylmethyl;
R₇ is H, OR₈, NR₉R₁₀;

R₈ is H, C₁-C₅ straight or branched alkyl, benzyl;
R₉, R₁₀ are independently H, C₁-C₅ alkyl;
and the salts thereof with pharmaceutically acceptable acids and bases.

5,587,391

CYCLOPENTANE(ENE) HEPTENOIC OR HEPTANOIC ACIDS AND DERIVATIVES THEREOF USEFUL AS THERAPEUTIC AGENTS

Robert M. Burk, Laguna Beach, Calif., assignor to Allergan, Waco, Tex.

Division of Ser. No. 174,535, Dec. 28, 1993, Pat. No.


5,545,665. This application Jul. 11, 1995, Ser. No. 445,842

Int. Cl.⁶ A61K 31/44; C07D 213/56

U.S. Cl. 514—357

9 Claims

1. A method of treating ocular hypertension which comprises applying to the eye an amount sufficient to treat ocular hypertension of a compound of formula (I)



wherein either the cyclopentane(ene) radical or the α or ω chain may be unsaturated; R is pyridyl; R₁, R₂ and R₃ are selected from the group consisting of hydroxy and hydrocarboxy radicals wherein said hydrocarboxy radical comprises up to 20 carbon atoms; Y an oxo radical and X represents an amino or a mono or dialkyl amino radical; provided, however, at least one of R₁, R₂ and R₃ is a hydrocarboxy radical.

5,587,392

AZOLYL METHYL PHENYL DERIVATIVES HAVING AROMATASE INHIBITORY ACTIVITY

Kimihiro Murakami; Shuhei Ohnishi; Takashi Yano, and Manabu Itoh, all of Tokyo, Japan, assignors to Mochida Pharmaceutical Co., Ltd., Tokyo, Japan

Filed May 26, 1995, Ser. No. 453,054


Claims priority, application Japan, May 27, 1994, 6-115664

Int. Cl.⁶ A61K 31/41; C07D 403/12; 403/10; 247/18


U.S. Cl. 514—359

24 Claims


1. A compound represented by the following formula (I):



wherein A represents methylene group, oxygen atom or sulfur atom; D represents nitrogen atom R¹ represents halogen atom, cyano group, nitro group, C₁ to C₂ alkoxy group which may or may not be substituted with one or two or more fluorine atoms, C₁ to C₂ alkyl group which may or may not be substituted with one or two or more fluorine atoms, C₂ to C₅ alkenyl group linear or branched, C₂ to C₅ alkynyl group linear or branched, C₁ to C₂ alkoxy carbonyl group, carboxyl group, acetyl group, formyl group or hydrogen atom; R² represents an atomic group represented by formula (II):



or formula (III):



wherein E represents nitrogen atom or methine group; and R³ represents hydrogen atom or C₁ to C₄ alkyl group linear or branched, or a salt thereof.

5,587,393

BENZIMIDAZOLES, PHARMACEUTICAL COMPOSITIONS CONTAINING THESE COMPOUNDS AND PROCESSES FOR PREPARING THEM

Berthold Narr; Norbert Haeu, both of Biberach; Jacques Van Meel, Mittelbiberach; Wolfgang Wienen, Apfingen; Michael Entzeroth, Warthausen, and Uwe Ries, Biberach, all of Germany, assignors to Dr. Karl Thomae GmbH, Biberach an der Riss, Germany

Division of Ser. No. 220,472, Mar. 30, 1994, Pat. No.

5,385,925, which is a continuation of Ser. No. 732,868, Jul. 19, 1991, abandoned. This application Sep. 1, 1994, Ser. No. 299,693


Claims priority, application Germany, Jul. 23, 1990, 40 23 369.3; Oct. 4, 1990, 40 31 287.9; Feb. 20, 1991, 41 05 324.0

Int. Cl.⁶ A61K 31/42; C07D 257/04; 235/06

U.S. Cl. 514—381

6 Claims

1. A method for treating hypertension in a patient which comprises administering to the patient a therapeutically effective amount of a benzimidazole of the formula I



wherein

R₁ represents a maleic acid imido group optionally mono- or disubstituted by a C₁₋₃-alkyl or by a phenyl group, in which the substituents may be identical or different;

R₂ represents a hydrogen atom or a straight-chained or branched C₁₋₅-alkyl group in which a methylene group may be replaced by a sulfur atom;

R₃ represents a carboxy, cyano, 1H-tetrazolyl or 1-triphenylmethyl-tetrazolyl group or an alkoxy carbonyl group with a total of 2 to 5 carbon atoms; and
R₄ represents a hydrogen, fluorine, chlorine or bromine atom; or, a pharmaceutically acceptable salt thereof.

5,587,394

PRODUCTION AND USE OF DIELS ALDER ADDUCTS OF VINYL PORPHYRINS, OF METAL COMPLEXES THEREOF, AND OF COMPOSITIONS CONTAINING SUCH ADDUCTS AND COMPLEXES

Alan R. Morgan, Santa Barbara, Calif., and Steven H. Selman, Toledo, Ohio, assignors to The University of Toledo, and Medical College of Ohio, both of Toledo, Ohio

Continuation-in-part of Ser. No. 321,387, Oct. 11, 1994, which is a continuation-in-part of Ser. No. 912,079, Jul. 8, 1992, Pat.


No. 5,354,858, which is a continuation of Ser. No. 677,408, Mar. 28, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 479,364

Int. Cl.⁶ C07D 487/22; A61K 31/66


U.S. Cl. 514—185



6 Claims

1. A method for detecting diseased tissue in a living mammal which comprises administering intravenously, intramuscularly, subcutaneously or topically to a human or animal patient an effective amount of a Diels Alder adduct or of a metal complex of a Diels Alder adduct and, after healthy tissue has rejected the Diels Alder adduct or the metal complex, examining the patient under illumination which causes residual Diels Alder adduct or metal complex to fluoresce, wherein the Diels Alder adduct has the structure of Formula 9 or of Formula 10, and the metal complex of a Diels Alder adduct has the structure of Formula 3 or of Formula 4:



Formula 10





where

M comprises a metal cation that is complexed with two of the nitrogens of the adduct and is Ag, Al, Ce, Co, Cr, Dy, Er, Eu, Ga, Gd, Hf, Ho, In, La, Lu, Mn, Mo, Nd, Pb, Pd, Pr, Pt, Rh, Sb, Se, Sm, Sn, Tb, Te, Tm, Th, Ti, Tl, U, V, Y, Yb, Zn or Zr.

R1, R2, R3 and R4 can be the same or different, and each is methyl, ethyl, an amino acid moiety which is a part of an amide produced by reaction between an amine function of a naturally occurring amino acid and a carbonyl function of the adduct, or a monoclonal antibody moiety which is attached to the adduct moiety through a carbonyl which is a part of an amide produced by reaction between an amine function of a monoclonal antibody and a CO₂R', CH₂CO₂R' or CH₂CH₂CO₂R' group of the adduct, and wherein the moiety is of a monoclonal antibody which selectively binds to malignant tumors.

R5, R6 and R7 can be the same or different, and each is ethyl, an amino acid moiety which is a part of an amide produced by reaction between an amine function of a naturally occurring amino acid and a carbonyl function of the adduct, or a monoclonal antibody moiety which is attached to the adduct moiety through a carbonyl which is a part of an amide produced by reaction between an amine function of a monoclonal antibody and a CO₂R', CH₂CO₂R' or CH₂CH₂CO₂R' group of the adduct, and wherein the moiety is of a monoclonal antibody which selectively binds to malignant tumors.

R8 is an alkyl group other than t-butyl having from one to four carbon atoms.

5,587,395 METALLO-ORGANIC COBALT COMPOUNDS AND USES THEREOF


Zvi Dori, Halfa, and David Gershon, Kiryat Tavor, both of Israel, assignors to Chai-Tech Corporation, Greenvale, N.Y. Division of Ser. No. 146,395, Nov. 1, 1993, Pat. No. 5,409,914, which is a continuation of Ser. No. 895,526, Jun. 2, 1992, Pat. No. 5,258,403, which is a division of Ser. No. 606,070, Oct. 30, 1990, Pat. No. 5,142,076, which is a continuation of Ser. No. 279,417, Dec. 2, 1988, Pat. No. 5,049,557, which is a continuation-in-part of Ser. No. 147,713, Jan. 25, 1988, Pat. No. 4,866,054, and a continuation-in-part of Ser. No. 147,714, Jan. 25, 1988, Pat. No. 4,866,053, each which is a continuation-in-part of Ser. No. 862,804, May 13, 1986, abandoned. This application Apr. 25, 1995, Ser. No. 428,532

Int. Cl.⁶ A61K 31/295; C07F 15/06

U.S. Cl. 514—501

25 Claims

1. A method of treating a subject having a condition associated with the presence of free radicals in quantities sufficient to cause undesirable symptoms which comprises administering to the subject a compound in an amount effective to alleviate the undesirable symptoms, the compound having the structure:



wherein

R₁ and R₁' are the same or different and each is an alkyl group, a phenyl group or a substituted derivative of a phenyl group; R₂ and R₂' are the same or different and each is hydrogen, an unbranched alkyl group a halide or a group having the structure




wherein R is hydrogen, an alkoxide group, an alkyl group or OH;

R₃ and R₃' are the same or different and each is hydrogen or an alkyl group;

X and X' are the same or different and each is a water-soluble group having weak to intermediate ligand field strength; and Q⁻ is a soluble, pharmaceutically acceptable negative ion.

17. A method of treating a wound or a burn which comprises topically administering to the wound or burn a compound having the structure



wherein

R₁ and R₁' are the same or different and each is an alkyl group, a phenyl group or a substituted derivative of a phenyl group; R₂ and R₂' are the same or different and each is hydrogen, an unbranched alkyl group a halide or a group having the structure



wherein R is hydrogen, an alkoxide group, an alkyl group or OH;

R₃ and R₃' are the same or different and each is hydrogen or an alkyl group;

X and X' are the same or different and each is a water-soluble group having weak to intermediate ligand field strength; and Q⁻ is a soluble, pharmaceutically acceptable negative ion.

22. A method of treating a wound or burn which comprises topically administering to the wound or burn a complex comprising a Co(III) complex having an octahedral basal plane defined by four donor atoms A, which may be same or different, and two axial ligand donor atoms B, which may be the same or different, said donor atoms having a low to intermediate ligand field strength, said complex reacting with O₂⁻ to form a Co(III)-O₂ adduct or oxidizing O₂⁻ to produce dioxygen and a Co(II) complex.

5,587,396 METHOD OF AMELIORATING CELLULITE BY DISRUPTING THE BARRIER FUNCTION OF THE STRATUM CORNEUM

Walter P. Smith, New Canaan, Conn., assignor to Mary Kay Inc., Dallas, Tex.

Filed Aug. 26, 1994, Ser. No. 296,513

Int. Cl.⁶ A61K 31/19

U.S. Cl. 514—557

15 Claims

1. A method of ameliorating a cellulite condition comprising application of a topical treatment composition to skin areas overlying cellulite, said treatment composition being effective to chronically disrupt the barrier function of the stratum corneum and to inhibit barrier repair until a desired amelioration of cellulite is achieved.

5,587,397 REDUCTION OF ELEVATED BLOOD LACTATE USING TWICE-DAILY DICHLOROACETATE

Anthony W. Fox, Rancho La Costa, Calif., assignor to Cypros Pharmaceutical Corporation, Carlsbad, Calif.

Filed Jun. 8, 1995, Ser. No. 488,977

Int. Cl.⁶ A61K 31/19

U.S. Cl. 514—557

5 Claims

1. A method of administering dichloroacetate to a human patient suffering from undesirably elevated levels of lactate in hypoxic tissue or circulating blood, comprising the step of injecting a physiologically acceptable salt of dichloroacetate into the patient twice over a 24-hour period, at dosages sufficient to sustain a substantial reduction in lactate concentration in the patient's blood for at least 24 hours.

5,587,398 META SUBSTITUTED ARYLALKYLAMINES AND THERAPEUTIC AND DIAGNOSTIC USES THEREFOR

David R. Elmaleh, 38 Hartman Rd., Newton, Mass. 02159, and Alan J. Fischman, Boston, Mass., assignors to David R. Elmaleh, Newton, Mass.


Continuation-in-part of Ser. No. 265,512, Jun. 24, 1994, abandoned, which is a continuation-in-part of Ser. No. 254,032, Jun. 3, 1994, abandoned. This application Jun. 2, 1995, Ser. No. 461,577

Int. Cl.⁶ A61K 31/135; C07C 15/04

U.S. Cl. 514—654

9 Claims

1. A compound having the structural formula:



wherein,

X=CF₃, CH₃, C₂H₅ or Cl₃;

Y=Cl or Br; ortho, para or meta to X;

n=1,2 or 3;

R₁=H and R₂ and R₃=acyl, alkenyl and alkynyl groups; or

R₁=CH₃ and R₂ and R₃=H, alkyl, acyl, alkenyl and alkynyl groups.

5,587,399 METHOD FOR PREPARING MEDICAL FOODS FOR THE NUTRITIONAL SUPPORT OF INFANTS/TODDLERS WITH METABOLIC DISEASES

Phyllis J. B. Acosta, Westerville; Richard A. Grondalski, Columbus; Jeffrey W. Liebrecht, Columbus, and Patricia A. Reynolds, Columbus, all of Ohio, assignors to Abbott Laboratories, Abbott Park, Ill.

Continuation of Ser. No. 997,278, Dec. 23, 1992, abandoned.

This application Apr. 20, 1994, Ser. No. 230,452

Int. Cl.⁶ A61K 31/195; 33/42; 33/34; 33/32; 33/26; 33/36; 33/06; 38/00, 31/70; 31/715; 31/415; 31/40; 31/34; 31/19; 31/07

U.S. Cl. 514—561

23 Claims

1. A method for preparing a composition of matter having utility for the nutritional support of infants and toddlers having inherited diseases of metabolism, the method comprising:

(a) preparing a premix base which is a composition of matter that is essentially free of protein and amino acids and consists essentially of fats comprising 30 to 40% by dry weight of the premix base, carbohydrates comprising 60 to 70% by dry weight of the premix base, minerals comprising 0.1 to 8% by dry weight of the premix base, vitamins comprising 0.1 to 1.0% of the premix base, trace elements, carnitine, taurine and antioxidants;

(b) preparing a blend of synthetic α-amino acids is specific for a given inherited disease of metabolism which comprises up to 18 different synthetic α-amino acids selected from the group consisting of L-alanine, L-arginine, L-aspartic acid, L-cystine, L-glutamic acid, L-glutamine, glycine, L-histidine, L-isoleucine, L-leucine, L-lysine, L-methionine, L-proline, L-phenylalanine, L-serine, L-threonine, L-tryptophan, L-tyrosine and L-valine; and

(c) mixing the blend of synthetic α-amino acids with the premix base so that the composition is in powdered form with the premix base comprising about 75 to 90% by dry weight of the composition and the blend of synthetic α-amino acids comprising about 9 to 25% by dry weight of the composition, and wherein the composition is free of intact protein.

5,587,400

PHYSIOLOGICAL COMPOSITION FOR THE TREATMENT OF THERMAL OR CHEMICAL BURNS
Joël Blomet, Valmondois; Marie-Claude Blomet épouse Meyer, 243 Rue de Vaugirard, Paris, and Dominique F. Jahan, Maurecourt, all of France, assignors to Marie-Claude Blomet épouse Meyer, Paris, France

Filed Apr. 14, 1994, Ser. No. 227,648

Claims priority, application France, Apr. 19, 1993, 93 04585; Jul. 6, 1993, 93 08278

Int. Cl.⁶ A61K 31/195

U.S. Cl. 514—566 17 Claims
1. A physiological composition for the treatment of thermal or chemical burns comprising an Al(OH)Y complex, wherein Y is the ethylenediaminetetraacetic ligand and the concentration of Al(OH)Y is 0.05 mole/l to 1.0 mole/l.

5,587,401

REPELLENTS FOR ANTS

Robert K. Vander Meer; William A. Banks, and Clifford S. Lofgren, all of Gainesville, Fla., assignors to The United States of America as represented by the Secretary of Agriculture, Washington, D.C.

Division of Ser. No. 286,111, Aug. 4, 1994, which is a continuation of Ser. No. 925,685, Aug. 7, 1992, abandoned. This application Jun. 6, 1995, Ser. No. 471,354

Int. Cl.⁶ A01N 35/02; 35/04

U.S. Cl. 514—675 1 Claim
1. A method for repelling ants from an object or area comprising treating the object or area with an ant repelling composition comprising
(i) an effective amount of 3-octen-2-one; and (ii) a carrier material.

5,587,402

REGRESSION OF MAMMALIAN LEUKEMIA CELL TUMORS

Michael N. Gould, Madison, Wis.; Pamela L. Crowell, Indianapolis, Ind.; Charles E. Elson, and Steven S. Clark, both of Madison, Wis., assignors to Wisconsin Alumni Research Foundation, Madison, Wis.

Continuation-in-part of Ser. No. 865,561, Apr. 9, 1992, Pat. No. 5,414,019. This application May 4, 1995, Ser. No. 434,811

Int. Cl.⁶ A61K 31/045

U.S. Cl. 514—729 3 Claims
1. A method for causing the regression of a leukemia cell malignancy, comprising the step of administering to a leukemia cell malignancy-containing mammal an effective amount of perillyl alcohol.

5,587,403

ORGANIC SOLVENT & WATER RESISTANT HYDROLYTICALLY STABLE ULTRAVIOLET RADIATION CURABLE COATINGS FOR OPTICAL FIBERS

Paul J. Shustack, West Chester, Ohio, assignor to Borden, Inc., Columbus, Ohio

Division of Ser. No. 454,585, May 31, 1995, Pat. No. 5,538,791, which is a division of Ser. No. 341,172, Nov. 16, 1994, Pat. No. 5,527,835, which is a continuation of Ser. No. 169,544, Dec. 20, 1994, abandoned, and a continuation of Ser. No. 873,105, Apr. 24, 1992, abandoned. This application Jan. 17, 1996, Ser. No. 587,984

Int. Cl.⁶ C08J 7/04; G02B 6/02; 6/00

U.S. Cl. 522—42 17 Claims
1. A process for preparing a coated optical fiber comprising (1) applying to an optical glass fiber a primary coating composition layer comprising

(A) from about 10 percent to about 90 percent by weight, based upon total weight of (A), (B), (C) and (D), of an acrylate or methacrylate terminated urethane oligomer, said oligomer having a number average molecular weight of not more than about 4,430 daltons which oligomer consists essentially of only carbon, hydrogen, nitrogen and oxygen atoms and which is the reaction product of (i) a polyether polyol; (ii) an aliphatic polyisocyanate; and (iii) an endcapping monomer capable of providing an acrylate or methacrylate terminus;

(B) from about 5 percent to about 80 percent by weight, based upon total weight of (A), (B), (C) and (D), of one or more monomer diluents which do not adversely affect the composition when cured and which are selected from the group consisting of

(i) alkyl acrylate and methacrylate monomers having 6 to 18 carbon atoms in the alkyl moiety;

(ii) monomers having (1) an aromatic moiety, (2) a moiety containing acrylic or methacrylic unsaturation, and (3) a hydrocarbon moiety, which monomer (ii) is capable of increasing the refractive index of the composition relative to that of a composition containing only (A), (C) and (D); and

(iii) mixtures thereof;

(C) from about 0.1 percent to about 3.0 percent by weight, based upon total weight of (A), (B), (C) and (D), of an organofunctional silane adhesion promoter; and

(D) optionally, from about 1.0 percent to about 10.0 percent by weight, based on total weight of (A), (B), (C), and (D), of a photoinitiator,

wherein the primary coating composition, after radiation cure, remains adherent and exhibits thermal, hydrolytic and oxidative stability at temperatures in excess of 90° C. and at 95% relative humidity and exhibits an increase in length from swelling of no more than about 40 percent when soaked in gasoline at room temperature for four hours and a water absorption value of no more than about 5% by weight;

wherein the primary coating layer composition is devoid of acid-functional materials; and

wherein the primary coating layer composition, after radiation cure, has a tensile modulus of less than 500 psi; and (2) radiation-curing said primary coating composition layer in situ.

5,587,404

GELS WITH THERMOTROPIC PROPERTIES

Hubertus Kröner, Neustadt; Ekkehard Jahns, Hirschberg, and Manfred Mielke, Heidelberg, all of Germany, assignors to Basf Aktiengesellschaft, Ludwigshafen, Germany

Filed Apr. 18, 1995, Ser. No. 423,850

Claims priority, application Germany, Apr. 22, 1994, 44 14 088.6

Int. Cl.⁶ C08K 3/00

U.S. Cl. 522—85 7 Claims
1. A gel for thermotropic layers, obtained by irradiation of a mixture comprising

a) an uncrosslinked polymer selected from the group consisting of poly-N-vinylcaprolactam, copolymers of N-vinylcaprolactam containing at least 20% by weight of N-vinylcaprolactam and polyvinyl ethers, said uncrosslinked polymer having thermotropic properties such that a 10% by weight solution of this polymer in water or an organic solvent or mixtures thereof brings about, in a switching range covering less than 20° C., a change in the transmission of light at a wavelength of 600 nm and at a path length of 10 mm such that less than 50% of the incident light is transmitted at temperatures above the switching range and at least 70% of the incident light is transmitted below the switching range.

b) monomers capable of free-radical polymerization and c) water or an organic solvent or mixtures thereof, with high-energy light.

5,587,405

INK COMPOSITIONS

Ban Tanaka, Toyota; Hiroki Nii; Kosaku Yamada, both of Fukuyama; Hideo Koshida, Yachiyo; Takashi Miya, Kamagaya; Shuichi Koshio, Sakura, and Tadashi Hayakawa, Chiba, all of Japan, assignors to Yoshino Kogyosho Co., Ltd., Tokyo, and Hayakawa Rubber Co., Ltd., Hiroshima, both of Japan

Continuation-in-part of Ser. No. 111,571, Aug. 25, 1993, abandoned. This application Jun. 6, 1995, Ser. No. 471,449

Claims priority, application Japan, Sep. 14, 1992, 4-269146 Int. Cl.⁶ C08F 2/48; 2/46

U.S. Cl. 522—98 27 Claims
1. A radiation-curable ink composition which comprises a vehicle mixture comprising:

(A) at least one ingredient selected from the group consisting of a linear polyester oligomer substantially free of an acid group and free of a polymerizable double bond on the linear polyester chain, wherein 1 to 10 double bonds are pendent from the linear polyester chain; a linear polyester polymer substantially free of an acid group and free of a polymerizable double bond on the linear polyester chain, wherein 1 to 10 double bonds are pendent from the linear polyester chain; and mixtures thereof.

(B) at least one ingredient selected from the group consisting of a one double bond-containing carboxylic acid wherein the acid has at least one acid group, a carboxylic ester of the said acid, a carboxylic amide of the said acid, and mixtures thereof.

(C) a double bond-containing polycarboxylic ester, wherein 2 to 10 acid groups are present and at least 2 double bonds are pendent from the carboxylic ester having 2 to 10 acid groups.

(D) at least one ingredient selected from the group consisting of a double bond-containing fluorinated carboxylic ester, a block copolymer comprising a fluorinated alkyl group-containing polymer segment and a methacrylic or acrylic polymer segment, a block copolymer comprising a siloxane group-containing polymer segment and a methacrylic or acrylic polymer segment, and mixtures thereof.

(E) a double bond-containing carboxylic ester, having at least 2 double bonds and free of an acid group, provided that it is excluded from the above-mentioned ingredient (A) and

(F) at least one ingredient selected from the group consisting of a one double bond-containing carboxylic ester free of an acid group, a one double bond-containing carboxylic amide free of an acid group, a one double bond-containing carboxylic imide free of an acid group, and mixtures thereof,

wherein the acid value of the vehicle mixture is from 5 to 100.

5,587,406

PRIMER COMPOSITION AND CURABLE COMPOSITION

Takashi Yamamoto; Weiping Zeng; Masami Arata; Tsuyoshi Banba, all of Moriyama, and Harumi Tanaka, Hikone, all of Japan, assignors to Sun Medical Co., Ltd., Moriyama, Japan Division of Ser. No. 284,175, Aug. 2, 1994, Pat. No. 5,530,038. This application May 25, 1995, Ser. No. 450,992

Claims priority, application Japan, Aug. 2, 1993, 5-191476; Aug. 2, 1993, 5-191477; Aug. 2, 1993, 5-191478

Int. Cl.⁶ A61K 6/083; C08F 20/30; C08K 5/08

U.S. Cl. 523—116 11 Claims


1. A method of treating a tooth surface, which comprises applying a primer composition comprising (A) (a) a polymerizable monomer having an acidic group in its molecule, and (f) a solvent selected from the group consisting of an organic solvent and an aqueous organic solvent to a tooth surface and then applying a curable composition comprising

(A1) (a) a polymerizable monomer having an acidic group in its molecule.

(b) a polymerizable monomer having a hydroxyl group in its molecule.

(c) a polymerization initiator and

an amine compound of formula (1)



wherein each of R¹ and R² is, independently, a hydrogen atom or an alkyl group which may contain a functional group or a substituent, and R³ is a hydrogen atom or a metal atom, wherein, on the basis of the total amount of components (A1) (a), (b) and (c), the amount of component (A1) (a) is 1 to 50% by weight, the amount of component (b) is 1 to 98.99% by weight, and the amount of the component (c) is 0.01 to 50% by weight, and

wherein the curable composition has a viscosity in the range of from 100 to 30,000 cp when measured at 37.5° C.

5,587,407

BIOCIDAL POLYMERIC COATING FOR HEAT EXCHANGER COILS

Claude E. Terry, LaGrange; Douglas E. Triestman, and Daniel L. Price, both of Kennesaw, all of Ga., assignors to Interface, Inc., LaGrange, Ga.

Division of Ser. No. 864,499, Apr. 7, 1992, Pat. No. 5,453,275, which is a continuation-in-part of Ser. No. 526,394, May 21, 1990, abandoned, which is a continuation-in-part of Ser. No. 242,484, Sep. 9, 1988, Pat. No. 4,957,948. This application Jun. 6, 1995, Ser. No. 467,011

Int. Cl.⁶ C08J 3/00; C08K 3/10

U.S. Cl. 523—122 24 Claims

1. A heat exchanger, comprising an exterior coating comprising: (a) a water resistant organic polymeric material comprising a halogenated polymer, and wherein the material bonds to the surface of the heat exchanger; and (b) an effective amount of 2-N-octyl-4-isothiazolin-3-one sufficient to inhibit growth of microorganisms on the heat exchanger.

5,587,408

SOLID ERASABLE MARKING COMPOSITION

Barbara J. Burns, Auburn, and Ralph J. Shuman, Needham, both of Mass., assignors to Avery Dennison Corporation, Pasadena, Calif.

Filed Sep. 16, 1994, Ser. No. 307,285

Int. Cl.⁶ C09D 11/00

U.S. Cl. 523—160 12 Claims

1. A marking composition that is erasable from both porous and non-porous marking substrates, said marking composition comprising:

(a) an emulsion, said emulsion comprising a discontinuous polymeric phase and a continuous aqueous phase, said emulsion being characterized in that, prior to being contacted with the surface of a porous or non-porous marking substrate, said emulsion exists in a stable first state whereas, upon being contacted with the surface of a porous or non-porous marking substrate, said emulsion is transformed into an unstable second state and said discontinuous polymeric phase rapidly agglomerates to form a deposit on the surface of the porous or non-porous marking substrate contacted therewith with low adhesion thereto, said polymeric phase constituting 25–50%, by weight, of the total composition;

(b) a colorant, said colorant being characterized by its association with said deposit when said emulsion is transformed into said second state, said colorant constituting 1–2%, by weight, of the total composition;

(c) a shape-giving gel-forming agent, said shape-giving gel-forming agent being a salt of an aliphatic carboxylic acid having from 8 to 36 carbon atoms, said shape-giving gel-forming agent constituting 10–15%, by weight, of the total composition;

- (d) a tackifier, said tackifier constituting 0-40%, by weight, of the total composition;
- (e) a humectant, said humectant constituting 0-6%, by weight, of the total composition;
- (f) an antioxidant and/or combination antioxidant and antioxidant, said antioxidant and/or combination antioxidant and antioxidant constituting 0-6%, by weight, of the total composition; and
- (g) a fluorochemical surfactant, said fluorochemical surfactant constituting 0-1.5%, by weight, of the total composition.

5,587,409

CURING AGENTS FOR AQUEOUS EPOXY RESIN DISPERSIONS

Dieter Dreischhoff, Wiesbaden; Joerg-Peter Geisler, Ingelheim; Claus Godau, Kiedrich; Michael Hoemel, and Bernhard Stengel-Rutkowski, both of Wiesbaden, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Division of Ser. No. 192,868, Feb. 7, 1994, Pat. No. 5,539,023.

This application Oct. 25, 1995, Ser. No. 548,204

Claims priority, application Germany, Feb. 8, 1993, 43 03 562.0

Int. Cl.⁶ C08K 3/20; C08L 63/02

U.S. Cl. 523-404

12 Claims

1. An aqueous epoxy resin composition comprising an aqueous epoxy resin dispersion and/or water-dilutable poly-functional epoxide compounds and water, and a curing agent obtained by reaction of an adduct (A) of at least one polyepoxide (A₁) and at least one polyalkylene polyether polyol (A₂), with

I. a reaction product of an amine (B) and an epoxide (C) or

II. an amine (B), and subsequent reaction with an epoxide (C), the amount of amine (B) being chosen that the H atoms on the nitrogen are present in a 2- to 10-fold excess, based on the epoxide groups in (A).

5,587,410

AQUEOUS RESIN COMPOSITION

Kenta Kanai, Takatsuki, and Kiyoshi Kawamura, Kawanishi, both of Japan, assignors to Nippon Shokubai Co., Ltd., Osaka, Japan

Filed Apr. 5, 1995, Ser. No. 417,615

Claims priority, application Japan, Apr. 7, 1994, 6-069383

Int. Cl.⁶ C08L 63/08

U.S. Cl. 523-410

7 Claims

1. An aqueous resin composition comprising: an aqueous medium;

a polymer (A1) at least partially comprising a polyolefin chloride resin and having a carboxyl group, wherein said polyolefin chloride resin is obtained by chloridizing a polyolefin; and

a polymer (B) having an oxazoline group.

5,587,411

RUBBER COMPOSITION AND METHOD OF PRODUCING RUBBER PRODUCTS USING THE SAME COMPOSITION

Toshiaki Sakaki, Kakogawa, and Shinichi Nakade, Itami, both of Japan, assignors to Sumitomo Rubber Industries, Ltd., Kobe, Japan

Filed Nov. 30, 1993, Ser. No. 158,992

Claims priority, application Japan, Dec. 1, 1992, 4-322082

Int. Cl.⁶ C08L 89/00

U.S. Cl. 524-17

2 Claims

1. An unvulcanized rubber composition consisting essentially of 100 parts by weight of rubber latex and 2.5 to 20 parts by weight of unhydrolyzed keratin.

5,587,412

ESTERIFIED STARCH COMPOSITION

Gerd Borchers, Wehr; Ingo Dake, Hamburg; Albrecht Dinkelaker, Rheinfelden, all of Germany; Jean-Pierre Sachetto, Ariesheim, Switzerland; Richard Zdrachala, Montville, N.J.; Stephen Rimsa, Lebanon, N.J.; Gary Loomis, Morris Township, N.J.; Paul Tatarka, Peoria, Ill., and Olivier Mauzac, Seppois-le-Bas, France, assignors to National Starch and Chemical Investment Holding Corporation, Wilmington, Del.

PCT No. PCT/US93/02822, § 371 Date Feb. 6, 1995, § 102(e) Date Feb. 6, 1995, PCT Pub. No. WO93/20110, PCT Pub. Date Oct. 14, 1993

Continuation of Ser. No. 948,750, Sep. 22, 1992, abandoned, and a continuation-in-part of Ser. No. 938,107, Aug. 28, 1992, abandoned, and a continuation-in-part of Ser. No. 936,175, Aug. 26, 1992, abandoned, which is a continuation-in-part of Ser. No. 860,820, Mar. 31, 1992, abandoned, and a continuation-in-part of Ser. No. 860,914, Mar. 31, 1992, abandoned. This PCT application Mar. 26, 1993, Ser. No. 313,072

Int. Cl.⁶ C08B 33/02

U.S. Cl. 524-47

15 Claims

1. A composition obtained from a melt comprising esterified starch having a degree of substitution of from about 1.8 to about 2.9, wherein the ester group of the esterified starch is selected from the group consisting of C₂ to C₈ ester residues and mixtures thereof.

5,587,413

FLUORINE RUBBER COMPOSITION

Takashi Enokida; Akihiro Naraki; Eichi Yamashita, all of Kitabaraki, and Haruyoshi Tatsu, Hitachi, all of Japan, assignors to Nippon Mektron, Limited, Tokyo, Japan

Filed Jan. 5, 1996, Ser. No. 583,642

Claims priority, application Japan, Jan. 13, 1995, 7-021359

Int. Cl.⁶ C08K 5/33; 5/205; C08L 27/12

U.S. Cl. 524-200

3 Claims

1. A fluorine rubber composition, which comprises a fluorine rubber and a polyfluoroalkyl group-containing block isocyanate compound represented by the following general formula:



where Rf is a polyfluoroalkyl group having 4 to 20 carbon atoms; R is a divalent organic group; R¹ is a lower alkyl group or phenyl group; R² is a lower alkyl group; X is NH or O; n is an integer of 1 to 4 and m is 0 or 1.

5,587,414

COMPATIBILISING AGENTS

Jan W. Leenslag, Tremelo, and Hans G. G. Verbeke, Linden, both of Belgium, assignors to Imperial Chemical Industries PLC, London, England

Division of Ser. No. 321,507, Oct. 12, 1994, which is a continuation-in-part of Ser. No. 187,577, Jan. 27, 1994, abandoned. This application Jun. 7, 1995, Ser. No. 481,728


Claims priority, application United Kingdom, Nov. 11, 1993, 9323288

Int. Cl.⁶ C08K 5/09; 5/098

U.S. Cl. 524-394

2 Claims

1. A process for solubilizing metal carboxylates in polyisocyanate or polyol compositions comprising: (1) adding to said polyisocyanate or polyol composition a preformed compatibilizing agent which is the reaction product of an organic mono- or polyfunctional isocyanate and a compound corresponding to the following general formula (1):



(1)

wherein Y₁ and Y₂ may be the same or different and represent O or S, n and m may be the same or different and represent an integer of from 0 to 1, and R and R' may be the same or different and represent an aliphatic hydrocarbon radical containing 1 to 30 carbon atoms, wherein the sum of the total number of carbon atoms of R and R' is between 7 and 40; and (2) adding the metal carboxylate to said polyisocyanate or polyol composition.

5,587,415

PROCESS FOR PREPARATION OF DISPERSION OF WATER-SOLUBLE CATIONIC POLYMER THE DISPERSION PRODUCED THEREBY AND ITS USE

Hisao Takeda, Zama, Japan, assignor to HYMO Corporation, Japan

Continuation-in-part of Ser. No. 263,536, Jun. 22, 1994, abandoned, which is a continuation of Ser. No. 153,750, Nov. 17, 1993, abandoned, which is a continuation-in-part of Ser. No. 921,566, Jul. 29, 1992, abandoned. This application Jul. 14, 1995, Ser. No. 502,613


Claims priority, application Japan, Jul. 30, 1991, 3-211309

Int. Cl.⁶ C08F 2/16

U.S. Cl. 524-458

26 Claims


1. A water-soluble cationic polymer or copolymer dispersion prepared by use of a cationic monomer mixture consisting essentially of 5 to 100% by mole of one or more of cationic monomers represented by the following formula (1):



(1)

wherein A=O or NH; B=CH₂CH₂, CH₂CH₂CH₂ or CH₂CHOHCH₂; R₁=H or CH₃; R₂, R₃=CH₃ or CH₂CH₃; R₄=(CH₂)_nCH₃ (wherein n=3 to 9); X⁻=anionic counterion, and

0 to 50% by mole of one or more of cationic monomers represented by the following formula (2):



(2)

wherein A=O or NH; B=CH₂CH₂, CH₂CH₂CH₂ or CH₂CHOHCH₂; R₁=H or CH₃; R₂, R₃=CH₃ or CH₂CH₃; R₅=H, CH₃ or CH₂CH₃ (wherein the total carbon atoms of R₂, R₃ and R₅ do not exceed 5); X⁻=anionic counterion, and

0 to 95% by mole of (meth)acrylamide, the dispersion being prepared by a process comprising polymerizing or copolymerizing the cationic monomer mixture with stirring in an aqueous salt solution which does not dissolve the resulting polymer or copolymer and in the presence of a dispersant which is a cationic polymer, soluble in the salt solution, said polymer dispersant comprising at least one monomer represented by formula (2) in an amount of more than 20% by mole.

5,587,416

DISPERSIBLE SILICA PARTICULATES AND REINFORCEMENT OF ELASTOMER/RUBBER MATRICES THEREWITH

Yvonick Chevallier, Decines, and Michel Rabeyrin, Dardilly, both of France, assignors to Rhone-Poulenc Chimie, Courbevoie Cedex, France

Division of Ser. No. 341,974, Nov. 16, 1994, and a continuation-in-part of Ser. No. 904,565, Jun. 26, 1992, Pat. No. 5,403,570. This application Jun. 7, 1995, Ser. No. 475,304

Claims priority, application France, Jun. 26, 1991, 91 07859

Int. Cl.⁶ C08K 3/36

U.S. Cl. 524-492

8 Claims

1. An elastomer/rubber matrix having a reinforcing amount of precipitated silica powder homogeneously dispersed therein, the precipitated silica powder having a mean particle size ranging from 5 to 70 microns, a BET specific surface area ranging from 140 to 200 m²/g, a CTAB specific surface area ranging from 140 to 200 m²/g, a DOP oil absorption ranging from 180 to 350 ml/100 g, a total pore volume of at least 2.5 cm³/g and a pore size distribution such that the pore volume provided by pores ranging from 175 to 275 Å in diameter constitutes at least 50% of the pore volume provided by the pore having diameters no greater than 400 Å.

5,587,417

RUBBER COMPOSITION FOR TIRE TREAD

Shinsuke Nakane; Kazuhiko Kanou, and Takatsugu Hashimoto, all of Tokyo, Japan, assignors to Bridgestone Corporation, Tokyo, Japan

PCT No. PCT/JP93/00971, § 371 Date Mar. 14, 1995, § 102(e) Date Mar. 14, 1995, PCT Pub. No. WO93/19578, PCT Pub. Date Oct. 14, 1993

PCT Filed Jul. 14, 1993, Ser. No. 403,720

Int. Cl.⁶ C08K 3/00

U.S. Cl. 524-495

6 Claims

1. A rubber composition for a tire tread which is obtained by blending 100 parts by weight of a natural rubber and/or a diene synthetic rubber with

40 to 100 parts by weight of a carbon black having characteristic values of a cetyltrimmonium bromide adsorption specific surface area (CTAB) being 90 to 220 m²/g and a 24M4DBP absorption value being 90 to 140 ml/100 g, and

0.1 to 20 parts by weight of an organic unsaturated fatty acid having two or more carbon double bonds in its molecule which includes 35% by weight or more of a conjugated diene acid having at least one conjugated carbon-carbon double bonds in its molecule.

5,587,418

THERMOSETTING COATING COMPOSITION AND COATED BODY

Ryo Sasaki, Atsugi, and Toshiro Ina, Osaka, both of Japan, assignors to Nissan Motor Co., Ltd. Kanagawa, and TBL Co., Ltd., Osaka, both of Japan

PCT No. PCT/JP94/01492, § 371 Date Jun. 5, 1995, § 102(e) Date Jun. 5, 1995, PCT Pub. No. WO95/07320, PCT Pub. Date Mar. 16, 1995

PCT Filed Sep. 9, 1994, Ser. No. 432,140

Claims priority, application Japan, Sep. 10, 1993, 5-249961

Int. Cl.⁶ C08L 51/00; 61/28; 33/08; 23/28

U.S. Cl. 524-504

17 Claims

1. A thermosetting coating composition comprising a graft copolymer obtained by copolymerizing acrylic monomers, unsaturated carboxylic acids, acrylic monomers containing hydroxyl group with chlorinated polyolefin containing anhydride in the

presence of an organic solvent phase, and melamine resin, which is available for use as a primerless coloured base coat of a 2-coat, 1-bake coating for a polyolefinic substrate.

5,587,419

METHOD FOR THE MANUFACTURE OF WEATHERABLE, RIGID EXTRUSION PROFILES HAVING IMPROVED SURFACE APPEARANCE

Dennis L. Lawson, Brunswick, and Robert E. Dettmer, Medina, both of Ohio, assignors to The B.F. Goodrich Company, Akron, Ohio

Continuation-in-part of Ser. No. 365,338, Dec. 28, 1994, abandoned, which is a continuation of Ser. No. 23,542, Feb. 26, 1993, abandoned. This application Oct. 10, 1995, Ser. No. 541,745

Int. Cl.⁶ C08L 23/28; 27/24; C08K 3/34; 5/04

U.S. Cl. 524—527

22 Claims

1. An extruded profile having smooth surface appearance made from a chlorinated polyvinyl chloride blend, said blend comprising 100 weight parts of chlorinated polyvinyl chloride containing from 62% to 72% chlorine and 10 to 30 weight parts chlorinated polyethylene, the blend comprising any one of the following:

- chlorinated polyvinyl chloride containing 62% to 64% chlorine, said chlorinated polyethylene having a real average molecular weight of from 90,000 to 130,000 and a polydispersity of from 4 to 8, said blend (a) extruded in a shear range of from 100 S⁻¹ to 600 S⁻¹;
- chlorinated polyvinyl chloride containing 64.1% to 66% chlorine, said chlorinated polyethylene having a real average molecular weight of from 90,000 to 130,000 and a polydispersity of from 4 to 8 said blend (b) extruded in a shear range of from 350 S⁻¹ to 4,000 S⁻¹;
- said chlorinated polyvinyl chloride containing 64.1% to 66% chlorine, said chlorinated polyethylene having a chlorine content of from 38% to 44% chlorine, a real average molecular weight of from 170,000 to 220,000 and a polydispersity of from 4 to 8, said blend (c) extruded in a shear range of from 400 S⁻¹ to 500 S⁻¹;
- said chlorinated polyvinyl chloride containing 66.1% to 69% chlorine, said chlorinated polyethylene having a real average molecular weight of from 90,000 to 130,000 and a polydispersity of from 4–8, said blend (d) extruded in a shear range of from 300 S⁻¹ to 600 S⁻¹;
- said chlorinated polyvinyl chloride containing 66.1% to 69% chlorine, said chlorinated polyethylene having a real average molecular weight of from 150,000 to 200,000 and a polydispersity of from 3–8, said blend (e) extruded in a shear range of from 400 S⁻¹ to 1,300 S⁻¹;
- said chlorinated polyvinyl chloride containing 66.1% to 69% chlorine, said chlorinated polyethylene having a real average molecular weight of from 290,000 to 330,000 and a polydispersity of from 8–14, said blend (f) extruded in a shear range of from 500 S⁻¹ to 650 S⁻¹;
- said chlorinated polyvinyl chloride containing from 69.1% to 72% chlorine, said chlorinated polyethylene having a real average molecular weight of from 90,000 to 130,000 and a polydispersity of from 4–8, said blend (g) extruded in a shear range of from 350 S⁻¹ to 3,500 S⁻¹;
- said chlorinated polyvinyl chloride containing from 69.1 to 72% chlorine, said chlorinated polyethylene having a real average molecular weight of from 150,000 to 200,000 and a polydispersity of from 3–8, said blend (h) extruded in a shear range of from 300 S⁻¹ to 1,000 S⁻¹; or

- said chlorinated polyvinyl chloride containing from 69.1% to 72% chlorine, said chlorinated polyethylene having a real average molecular weight of from 290,000 to 330,000 and a polydispersity of from 8–14, said blend (i) extruded in a shear range of from 350 S⁻¹ to 500 S⁻¹.

5,587,420

DIENE POLYMER OBTAINED BY ADDING A TIN COMPOUND IN THE POLYMERIZATION WITH AN ORGANOLITHIUM INITIATOR

Toshiki Takizawa, Yasuo Horikawa, and Taro Akazawa, all of Tokyo, Japan, assignors to Bridgestone Corporation, Tokyo, Japan

Filed Jun. 3, 1993, Ser. No. 70,793

Claims priority, application Japan, Jun. 4, 1992, 4-144517; Jun. 4, 1992, 4-144518; Jun. 4, 1992, 4-144519; Sep. 29, 1992, 4-260233; Oct. 22, 1992, 4-284430

Int. Cl.⁶ C08L 9/00; C08K 3/04; C08F 4/16; 4/48

U.S. Cl. 524—572

27 Claims

1. A method of producing a polymer, comprising the steps of polymerizing a conjugated diene monomer or a mixture of a conjugated diene monomer and a vinylaromatic hydrocarbon monomer in a hydrocarbon solvent using an initiator comprising an organolithium compound and adding an organotin compound during a period of growth of the polymer chain between a time immediately after the start of the polymerization to a time before the end of the polymerization; wherein the organolithium compound is selected from the group consisting of alkyl lithium, alkenyl lithium, phenyllithium and stilbenedilithium and the organotin compound is represented by the formula SnR_n, wherein R are the same or different molecular structure groups each having a connecting part to tin selected from the group consisting of a molecular structure containing an allyl group, a molecular structure containing a benzyl group and a molecular structure containing a phenyl group.

19. A high molecular weight polymer, comprising 40% or more of a high molecular weight polymer containing a chain having tin-carbon linkages, the high molecular weight polymer being produced by polymerizing a conjugated diene monomer or a mixture of a conjugated diene monomer and a vinylaromatic hydrocarbon monomer in a hydrocarbon solvent using an initiator comprising an organolithium compound, and adding to the polymerization a halogenated tin compound expressed by the formula SnX_n, wherein X is a halogen and n is 2, and the halogenated tin compound is added to the polymerization system during a period of growth of the polymer chain between a time immediately after start of the polymerization to a time of 80% conversion in an amount of less than 0.5 to 0.12 or more mol equivalent based on 1 mol equivalent of the lithium at the active end of the polymer.

5,587,421

MIXTURES CONTAINING WATER-EMULSIFIABLE ISOCYANATES

Peter Weyland, Frankenthal; Reinhard Treiber, Leimen; Alwin Sturm, Ludwigshafen; Horst Seibert, Fussgönheim; Hans Renz, Meckenheim; Jürgen Reichert, Ludwigshafen, and Karl Häberle, Speyer, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

Filed Aug. 18, 1995, Ser. No. 516,923

Claims priority, application Germany, Aug. 19, 1994, 44 29 446.8

Int. Cl.⁶ C08J 3/00; C08K 3/20; C08L 75/00; B32B 27/00

U.S. Cl. 524—591

13 Claims

1. An aqueous polymer emulsion comprising a crosslinkable polymer, and as a crosslinking agent for said polymer, 0.5 to 20% by weight, based on the weight of the polymer, of a mixture

containing a) a water-emulsifiable polyisocyanate containing ionic group or groups convertible into ionic groups or containing hydrophilic nonionic groups, and b) a carbonic ester or lactone as an organic solvent.

least part of said first monomer has been consumed, and then at least one further monomer is added to said reacted first or further mixture and reacted in a subsequent tubular reactor, wherein each tubular reactor is followed by a static mixer or a stirred vessel.

5,587,422

SINGLE PHASE SOLIDS CONTAINING METALLOPOLYMERS

Josh H. Golden, Stamford, Conn.; Francis J. DiSalvo, and Jean M. J. Frechet, both of Ithaca, N.Y., assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Continuation-in-part of Ser. No. 245,574, May 18, 1994, abandoned. This application Jun. 7, 1995, Ser. No. 471,838

Int. Cl.⁶ C08K 3/10; 3/34

U.S. Cl. 524—779

10 Claims

1. A mixed organic-inorganic solution comprising a homogeneous molecular mixture of a polymerizable organic solvent and an inorganic metallopolymer, wherein the metallopolymer is dissolved in said solvent.

5,587,423

PREPARATION OF BLOCK COPOLYMERS BY IONIC POLYMERIZATION

Franz Brandstetter, Neustadt; Hermann Gausepohl, Mutterstadt, and Reiner Thiele, Kaiserslautern, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany


Filed Oct. 13, 1993, Ser. No. 135,406

Claims priority, application Germany, Oct. 14, 1992, 42 34 601.0

Int. Cl.⁶ C08F 297/04

U.S. Cl. 525—52

6 Claims



1. A process for preparing block copolymers of styrene and of butadiene by sequential anionic polymerization in a series of at least two sequential tubular reactors, in which a first monomer and an organometallic compound serving as initiator are combined to form a first reaction mixture and are reacted (polymerized) until at

5,587,424

MIXTURE OF FLUOROCARBON RUBBER AND SILICONE/ACRYLATE CORE/SHELL RUBBER

Gerhard Langstein, Kürten; Ralf Krüger, Köln; Karl-Erwin Piejko, Bergisch Gladbach; Ulrich Eisele, Leverkusen, and Leo Morbitzer, Köln, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Continuation-in-part of Ser. No. 259,949, Jun. 15, 1994, abandoned. This application Jun. 1, 1995, Ser. No. 456,348

Claims priority, application Germany, Jun. 22, 1993, 43 20 633.6

Int. Cl.⁶ C08L 27/12; 27/18; 27/20

U.S. Cl. 525—63

7 Claims

1. A radically vulcanizable blend of a fluorocarbon rubber and a silicone rubber comprising

- 2 to 65 parts by weight of silicone-core, acrylate-shell rubber particles dispersed within
- 98 to 35 parts by weight of a fluorocarbon rubber which is at least partially compatible and radically cross-linkable with the acrylate-shell of said silicone-core, acrylate-shell particles, and

wherein said silicone-core, acrylate-shell particles are themselves comprised of from 50 to 95 parts by weight of a silicone and from 5–50 parts by weight of an acrylate.

5,587,425

BLENDS OF COPOLYMERS OF MONOVINYLARENES AND CONJUGATED DIENES CONTAINING TWO INTERIOR TAPERED BLOCKS

George A. Moczygemba, Bartlesville; Nancy R. Knight, Ochelata; William J. Trepka, and Nathan E. Stacy, both of Bartlesville, all of Okla., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Continuation of Ser. No. 371,256, Jan. 11, 1995, abandoned, which is a division of Ser. No. 162,735, Dec. 2, 1993, Pat. No. 5,399,638. This application Dec. 28, 1995, Ser. No. 580,227

Int. Cl.⁶ C08F 297/04; C08L 25/04; 53/02

U.S. Cl. 525—98

14 Claims

1. Blends of at least one polymer of styrene and a copolymer prepared by a method of preparing copolymers under polymerization conditions in a reaction zone comprising:

- charging a monovinylaromatic monomer and an initiator and in the presence of a randomizer, allowing polymerization to occur until essentially no free monomer is present; thereafter
- charging an initiator and a monovinylaromatic monomer and allowing polymerization to occur until essentially no free monomer is present; thereafter
- charging a mixture of monovinylaromatic monomer and conjugated diene monomer and allowing polymerization to occur until essentially no free monomer is present; thereafter
- charging a mixture of monovinylaromatic monomer and conjugated diene monomer and allowing polymerization to occur until essentially no free monomer is present; thereafter
- charging a conjugated diene monomer and allowing essentially complete polymerization to occur until essentially no free monomer is present; and thereafter
- charging reaction mixture with a coupling agent, wherein only two initiator charges are present and are performed as stated in steps (a) and (b).

R_n 24.9 PPM

- (h) selecting limits for Q₂ for the process within the range 0.90 to 1.35;
- (c) determining the actual value of the parameter, Q₂, for the copolymer obtained from the second reactor; and
- (d) controlling the ethylene feed to maintain Q₂ within the limits selected in (b).

5,587,437

PROCESS OF PRODUCING VINYL CHLORIDE TYPE POLYMER


Fumiki Adachi, Tadashi Amano, Yoshihiro Shirota, and Yoshitaka Okuno, all of Kamisu-machi, Japan, assignors to Shin-Etsu Chemical Co., Ltd., Tokyo, Japan

Filed Sep. 14, 1995, Ser. No. 528,097

Claims priority, application Japan, Sep. 14, 1994, 6-247104
Int. Cl.⁶ C08F 2/18; 14/06

U.S. Cl. 526—68

19 Claims



1. A process of producing a vinyl chloride containing polymer, comprising suspension polymerizing vinyl chloride monomer or a vinyl monomer mixture mainly made up of vinyl chloride monomer in an aqueous medium in the presence of an oil-soluble polymerization initiator in a polymerization apparatus which comprises (a) a cylindrical polymerization vessel constructed of a cylindrical straight barrel, a semispherical top part and a semispherical bottom part, which parts close the top and bottom of the straight barrel respectively, (b) stirring impellers, each having impeller blades, tiered along a rotating shaft arranged on the center line of said polymerization vessel, (c) a reflux condenser arranged at the upper part of said polymerization vessel for condensing monomer vapor generated in said polymerization vessel and flowing back the resulting condensate into said polymerization vessel, and (d) a heating and cooling jacket arranged around said polymerization vessel for heating and cooling liquid contents of said polymerization vessel, while stirring said vinyl chloride monomer or said vinyl monomer mixture by said stirring impellers and evacuating noncondensable gases evaporated from said contents, wherein said polymerization apparatus is such a polymerization apparatus that the inner volume of the polymerization vessel is 100 m³ or more, the ratio L/D of the length L of the straight barrel to the inner diameter D of the polymerization vessel is 1.5 or more, and an uppermost stirring impeller is arranged such that the height of a center line of the vertical width of its impeller blade is in the range of 150 to 300 cm downwardly from the upper end position of the straight barrel of the polymerization vessel, wherein after the contents in the polymerization vessel are heated to an intended polymerization temperature or a temperature near said polymerization temperature, the noncondensable gases coming into the reflux condenser are evacuated under such conditions that a flow rate of the evacuation is 10 to 100 Nm³/hour and the evacuation time is a period equal to 20% or more of the total polymerization time, and

wherein simultaneously with or after the start of the evacuation of the noncondensable gases, cooling by the reflux condenser is started, and

wherein materials to be charged into the polymerization vessel are charged such that both the relations:

$$\frac{10}{9} H_1 \leq H_0 \leq \frac{100}{65} H_1 \text{ and } H_0 < H_2,$$

wherein H₀ denotes the height of the liquid surface of the contents that have not yet been reacted, H₁ denotes the height of an upper edge of the impeller blade of the upper most stirring impeller, and H₂ denotes the height of an upper end of the straight barrel are simultaneously satisfied.

5,587,438

PROCESS FOR PREPARING STYRENE POLYMERS

Frederik L. Binsbergen; Alouisius N. R. Bos, and Augustinus Santen, all of Amsterdam, Netherlands, assignors to Shell Oil Company, Houston, Tex.

Filed May 31, 1995, Ser. No. 455,371

Int. Cl.⁶ C08F 2/02; 12/08

U.S. Cl. 526—88

17 Claims

1. A process for preparing polymers, comprising the step of bulk polymerizing in a spray-tower reactor, in the presence of an anionic initiator, and in the absence of a quenching solvent, a monomer feedstock comprising one or more monomers selected from the group consisting of styrene, vinylarene compounds, vinyl-substituted vinylarene compounds, and aryl-substituted vinylarene compounds.

5,587,439

POLYMER SUPPORTED CATALYST FOR OLEFIN POLYMERIZATION

Anthony-J. DiMalo, Maineville, Ohio, assignor to Quantum Chemical Corporation, Cincinnati, Ohio

Filed May 12, 1995, Ser. No. 439,810

Int. Cl.⁶ C08F 4/62; 4/63; 10/00

U.S. Cl. 526—142

40 Claims

1. A supported metallocene catalyst useful for polymerizing olefins comprising the product which is prepared by the steps of:

- (a) reacting a particulate olefin copolymer support which comprises discrete particles having a median particle size ranging from about 1 up to about 1500 microns, a pore volume of less than 0.1 cc/g and a surface area of less than about 15 m²/g, wherein said olefin copolymer has a melt index of from about 0.1 to about 400 and includes from about 50.1 to about 99.9 weight percent C₂₋₄ α-olefin and from about 0.1 to about 49.9 weight percent of an acrylate, with a metallated compound, wherein said metallated compound is selected from the group consisting of a substituted or unsubstituted cyclopentadienylide, a substituted or unsubstituted indenylide and a substituted or unsubstituted fluorenyl compound and contains a metal of Groups I-III of the Periodic Table of Elements, under conditions sufficient to form a metallated keto-intermediate;

- (b) contacting said metallated keto-intermediate of step (a) with a transition metal compound having the formula



wherein Cp is a substituted or unsubstituted cyclopentadienyl, indenyl or fluorenyl ring; M is a metal of Group IVB, VB and VIB of the Periodic Table of Elements; Rⁿ is a hydride, a hydrocarbyl group having from about 1 to about 20 carbon atoms, an alkoxy group having from about 1 to about 12 carbon atoms, a substituted or unsubstituted aryl group containing from about 6 to about 12 carbon atoms, or NRⁿ, wherein Rⁿ is an alkyl containing from

about 1 to about 12 carbon atoms; X is a halide; a is 0 or 1; b is 0-4; c is 0-4; and the sum of a, b and c is equal to the oxidation state of M; and

- (c) recovering said contact product of step (b).

5,587,440

PROCESS FOR THE PREPARATION OF ULTRAHIGH MOLECULAR WEIGHT POLYETHYLENE HAVING A HIGH BULK DENSITY

Jens Ehlers, Oberhausen, and Jutta Walter, Neukirchen-Vluyn, both of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Continuation of Ser. No. 309,429, Sep. 20, 1994, abandoned.

This application Feb. 26, 1996, Ser. No. 605,466

Claims priority, application Germany, Sep. 27, 1993, 43 32 786.9

Int. Cl.⁶ C08F 4/655; 10/02

U.S. Cl. 526—153

12 Claims

1. A process for the preparation of pulverulent polyethylenes having viscometrically measured molecular weights of at least 10⁶ g/mol and bulk densities of 430 to 460 g/liter by polymerization of ethylene at polymerization temperatures of 30° to 130° C. and pressures of 0.05 to 4 MPa in the presence of a mixed catalyst and a molecular weight regulator,

said mixed catalyst comprising a titanium component and an activator, said titanium component being produced by a reaction having a first stage and a second stage,

in said first stage, a Ti(IV) compound of the formula Ti(OR¹)_{4-n}X_n wherein n is an integer from 1 to 4, the R¹'s are independently hydrocarbon radicals and X is halogen, is reacted with a first organoaluminum compound which is selected from the group consisting of organoaluminum compounds having the formula AlR²₃, wherein the R²'s are independently alkyl radicals having 1 to 12 carbon atoms, and polymeric organoaluminum compounds which are obtained from the reaction of lithium aluminum hydride, trialkylaluminum, or dialkylaluminum hydrides, the alkyl radicals of which each have 1 to 16 carbon atoms, with diolefins having 4 to 20 carbon atoms, at -40° C. to 140° C. in a first molar ratio of titanium to aluminum of 1:0.1 to 1:0.6 to form a titanium (III) compound as a first reaction product and

in a second stage, said first reaction product is aftertreated with isoprenylaluminum as second organoaluminum compound at -10° to 150° C. in a second molar ratio of titanium to aluminum of 1:0.4 to 1:5, thereby forming said titanium component, and forming said titanium component into said mixed catalyst by adding said activator, which is a third aluminum compound selected from the group consisting of triisobutylaluminum, isoprenylaluminum, and mixtures thereof in a third molar ratio of titanium in said Ti (IV) compound to aluminum in said third aluminum compound of 1:1 to 1:15.

5,587,441

HYPERBRANCHED POLYMERS FROM AB MONOMERS

Jean M. J. Frechet, Ithaca, N.Y., and Sadahito Aoshima, Chiba, Japan, assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Filed Nov. 8, 1994, Ser. No. 335,947

Int. Cl.⁶ C08F 4/14; 16/12

U.S. Cl. 526—238

36 Claims

1. A process for the preparation of a hyperbranched polymer comprising initiating polymerization of and thereafter polymerizing in a single polymerization an AB monomer in which A and B are reactive groups that react independently of each other in which group A is a polymerizable group that is polymerized by opening of a double bond or ring and group B is a precursor of a moiety which initiates the polymerization of A as a result of being activated.

5,587,442

POLYGLYCOMERS

Laura L. Kiessling, 2320 Lakeland Ave., Madison, Wis. 53704; David D. Manning, 1906 Pike Dr., Apt. 1, Madison, Wis. 53713, and Kathleen H. Mortell, 202 G Eagle Heights, Madison, Wis. 53705


Filed Dec. 23, 1994, Ser. No. 363,503

Int. Cl.⁶ A01N 43/04; A61K 31/70

U.S. Cl. 526—238.2

16 Claims

1. A polyglycomer of the formula



wherein L is a linker selected from the group of —O—(CH₂)_m—, —NH—(CH₂)_m—, —O—(CH₂)_m—X—, and —NH—(CH₂)_m—X—, wherein X is S or O and m is 2-10,

wherein R¹ and R² are selected from the group consisting of monosaccharides, disaccharides, trisaccharides, and oligosaccharides, and

wherein n is between 1 and 2000.

5,587,443

POLYMERIZABLE EMULSIFIERS AND REACTIVE GROUPS AND POLYMERS OF EMULSIFIERS AND OTHER MONOMERS

Ludger Heiliger, Leverkusen; Adolf Schmidt, Cologne, and Joachim Probst, Leverkusen, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Division of Ser. No. 3,641, Jan. 13, 1993, Pat. No. 5,380,924.

This application Aug. 8, 1994, Ser. No. 287,164


Claims priority, application Germany, Jan. 25, 1992, 42 02 050.6

Int. Cl.⁶ C08F 30/04

U.S. Cl. 526—240

3 Claims

1. A polymer comprising at least one compound corresponding to formula (I):



in which

X is NH—CO—Y or Y,
Y is NH, oxygen or sulfur.

Z is COOM or SO₃M,

M is hydrogen, sodium, ammonium or potassium.

R^1 , R^2 and R^3 independently of one another represent hydrogen or methyl and
 R^4 is C_{1-12} alkylene, C_{3-12} cycloalkylene, phenylene or naphthylene, and the polymer contains at least one additional monomer.

5,587,444

COPOLYMER, A PROCESS FOR PRODUCING THE SAME AND AN ELECTROLUMINESCENT ELEMENT USING THE SAME

Manabu Uchida, Takenori Izumizawa, and Kenji Furukawa, all of Kanagawa-ken, Japan, assignors to Chisso Corporation, Osaka-fu, Japan


Filed Dec. 27, 1994, Ser. No. 364,894

Claims priority, application Japan, Dec. 27, 1993, 5-354192


Int. Cl.⁶ H01J 1/62

U.S. Cl. 526—247

2 Claims



1. A copolymer consisting of repetition units expressed by the formula (1) and repetition units expressed by the formula (2), the content of the repetition units (1) in the total repetition units being 0.01 to 50% by mol, and the weight average molecular weight calculated in terms of polystyrene measured according to gel permeation chromatography being 1,000 to 1,000,000:



in the formula (1), R_1 to R_5 each independently being chosen from the group consisting of hydrogen, fluorine, alkyl group, alkoxy group, dialkylamino group, alkanoyloxy group, alkyloxycarbonyl group, aryl group, cyano group, alkanoyl group or trifluoromethyl group; X representing O or NY (wherein Y represents hydrogen, alkyl group or aryl group); n representing 1 or 2; and R_6 representing hydrogen or methyl group.

5,587,445 HIGHLY OXYGEN-PERMEABLE HEAT-RESISTANT MATERIAL

Shigeo Mochizuki, Masahiro Matsumoto, both of Nagoya; Toshio Yamazaki, and Shoji Ichinohe, both of Gunma-ken, all of Japan, assignors to Menicon Co., Ltd., Nagoya, Japan

Filed Jan. 18, 1996, Ser. No. 588,388


Claims priority, application Japan, Jan. 20, 1995, 7-007536

Int. Cl.⁶ C08F 34/02

U.S. Cl. 526—271

7 Claims

1. A highly oxygen-permeable heat-resistant material consisting essentially of a polymer obtained by polymerizing a polymerizable component containing a silicon-containing stilbene derivative of the formula (I):



wherein each of R^1 and R^2 which are independent of each other, is a hydrogen atom or a group of the formula (II):



wherein p is an integer of from 1 to 8, provided that at least one of R^1 and R^2 is the group of the formula (II).

5,587,446

HYPERBRANCHED POLYMERS FROM AB MONOMERS

Jean M. J. Frechet, Ithaca, N.Y., and Sadahito Aoshima, Kashiwa, Japan, assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Division of Ser. No. 335,947, Nov. 8, 1994. This application

Jun. 1, 1995, Ser. No. 456,540

Int. Cl.⁶ C08F 16/12; 4/14

U.S. Cl. 526—333

8 Claims

1. A hyperbranched polymer produced from an AB monomer in which A and B are reactive groups that react independently of each other in which group A is a polymerizable group and group B is a precursor of a moiety B* which initiates the polymerization of A as a result of being activated, wherein said hyperbranched polymer comprises an AB*, macro-monomer in which x is an integer that increases as polymerization increases, said hyperbranched polymers having a living character in that said polymer has active sites A* and B* which are reactable with A groups, AB monomers and nucleophiles.

(1)

5,587,447

COPOLYAMIDE PRODUCTION METHOD

Masahiro Harada, and Yasuo Inaba, both of Hiratsuka, Japan, assignors to Mitsubishi Gas Chemical Co., Inc., Tokyo, Japan

Filed Apr. 5, 1995, Ser. No. 417,118

Claims priority, application Japan, Apr. 7, 1994, 6-069415

Int. Cl.⁶ C08G 69/28

U.S. Cl. 528—347


6 Claims

1. A method for producing a copolyamide which comprises the steps of:

(1) heating either one dicarboxylic acid selected from the group consisting of adipic acid and a mixture comprising 40 mol % or more of adipic acid and 60 mol % or less of dicarboxylic acid other than adipic acid to a temperature higher than the melting point of adipic acid but lower than a temperature lower by 30° C. than the melting point of the resulting copolyamide.

(2) dropping a diamine comprising 35 to 70 mol % of paraxylylene diamine and 65 to 30 mol % of metaxylylene diamine into the heated dicarboxylic acid stepwise or continuously before a conversion of the dicarboxylic acid reaches 90 mol %.

(3) discontinuing the dropping of the diamine before the conversion of the dicarboxylic acid reaches 90 mol %, and dropping metaxylylene diamine or a diamine mixture of 70 mol % or more of metaxylylene diamine and 30 mol % or less of paraxylylene diamine in place of the diamine continuously or stepwise until a molar ratio of the total of the diamines to the total of the dicarboxylic acids becomes 0.97 to 1.03, and
 (4) heating a reaction system to a temperature higher than a temperature lower by 30° C. than the melting point of the finally formed copolyamide before the conversion of the dicarboxylic acid reaches 95 mol %, and elevating the temperature of the reaction system to a temperature higher than the melting point of the finally formed copolyamide upon termination of dropping the diamine.



5,587,448

REACTION SYSTEM FOR PRODUCING A POLYURETHANE AND METHOD OF USING SAME TO SEAL A SURFACE


Paul T. Engen, Martell Township, Pierce County, Wis., assignor to Minnesota Mining and Manufacturing, St. Paul, Minn.

Filed Dec. 29, 1994, Ser. No. 366,308

Int. Cl.⁶ C08G 18/08; 18/22

U.S. Cl. 528—55

28 Claims



1. A two-part reaction system for producing a polyurethane having an isocyanate index of at least 100 and having a gel time between 5 and 60 minutes after admixture of said two parts, comprising first and second parts located in separate first and second containers, respectively, effective to prevent contact between said first and second parts thereof,

- (a) said first part comprising a polyisocyanate component;
- (b) said second part comprising
 - (i) a polyol component;
 - (ii) a polyurethane catalyst comprising a bismuth/zinc polyurethane catalyst; and
 - (iii) a molar excess of a complexing agent for said polyurethane catalyst, wherein said complexing agent comprises a mercaptan compound.

5,587,449

PROCESS FOR THE PREPARATION OF POLYACETAL COPOLYMERS

Dietrich Fleischer, Darmstadt; Michael Hoffmoeckel, Niederrhausen; Karl-Friedrich Mück, and Günter Sextro, both of Wiesbaden, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Filed Aug. 31, 1995, Ser. No. 521,998

Claims priority, application Germany, Sep. 5, 1994, 44 31 575.9

Int. Cl.⁶ C08G 4/00

18 Claims

1. In a process for the preparation and simultaneous end group stabilization of a polyacetal copolymer in a homogeneous phase, in

which a cyclic formaldehyde oligomer is copolymerized with a cyclic acetal in the presence of an initiator in a polymerization reactor and immediately thereafter the initiator is deactivated by addition of a basic substance, which comprises a procedure in which the unstable chain ends are degraded down to 0.01% to 1% in the presence of residual monomer, the improvement according to which the product spontaneously solidifies due to evaporation of the residual monomer at the reactor outlet by letting down into a pelletizing device and the residual monomer which remains and the impurities dissolved in the product are removed by extraction with a solvent and the product is pelletized, after drying and stabilization.

5,587,450

PROCESS FOR PRODUCING AROMATIC POLYAMIDE FILM

Kazunori Akiyoshi, and Masahiro Niwano, Tsukuba, both of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Jun. 30, 1995, Ser. No. 496,878

Claims priority, application Japan, Jul. 8, 1994, 6-157399


Int. Cl.⁶ C08G 69/08; 73/10

U.S. Cl. 528—310


18 Claims

1. A process for producing an aromatic polyamide film having an excellent transparency, which comprises the steps of:

- (a) forming a thin layer of an optically isotropic dope in which an aromatic polyamide selected from an aromatic polyamide composed of the following recurring structural units (A) and (B):



(A)



(B)

is dissolved in a polar amide,

- (b) immersing the thin layer dope in a polar solvent, other than said polar amide, kept at a temperature not higher than -20° C. to prepare a film, and
- (c) drying the film.

5,587,451


PROCESS FOR PREPARING POLYAZAMACROCYCLES
 Phillip S. Athey, and Garry E. Kiefer, both of Lake Jackson, Tex., assignors to The Dow Chemical Company, Midland, Mich.

Continuation-in-part of Ser. No. 158,654, Nov. 26, 1993, abandoned. This application Oct. 7, 1994, Ser. No. 320,620
 Int. Cl.⁶ C08G 69/26

U.S. Cl. 528—345

30 Claims

1. A process for preparing polyazamacrocycle compounds of the formula



wherein:

- each n is independently 2 or 3;
- m is 0 or an integer from 1 to 3;
- s is 0 or 1;
- y is 0 or 1;
- z is 0 or 1;

with the proviso that at least 2 of s, y, and z must be 1;


Q is —CH₂—, —C(O)— or —CHR—;

R is hydrogen, C₁–C₆ alkyl, —CO₂H, —CO₂(C₁–C₆ alkyl) or phenyl;

R¹ is hydrogen, —CO₂H, —CO₂(C₁–C₆ alkyl), C₁–C₆ alkyl, C₁–C₆ alkyl substituted by NH₂, NO₂, isothiocyanato, semicarbazido, thiosemicarbazido, maleimido, bromoacetamido or OR², phenyl or phenyl substituted by NH₂, NO₂, isothiocyanato, semicarbazido, thiosemicarbazido, maleimido, bromoacetamido or OR²; or

R and R¹ can be taken together to form a phenyl or phenyl substituted by NH₂, NO₂, isothiocyanato, semicarbazido, thiosemicarbazido, maleimido, bromoacetamido or OR²; and R² is hydrogen or C₁–C₄ alkyl;

which comprises reacting an alkenepolyamine with a formyl equivalent, either neat or in a nonaqueous solvent, to form the unsubstituted imidazoline of the formula




wherein

- q is independently 2 or 3;
- p is 0 or 1;
- t is 0, 1 or 2;


followed by reacting (9) with:

(A) 1 equivalent of an ethylene oxide or an ethylene carbonate, in an aprotic solvent, to form an alcohol (16) of the formula



wherein Q, s, R and R¹ are defined as for Formula (1) and the dotted line represents the optional presence of a bond; when the bond is present, then t is 0, q is 2 to 3, and p is 1; when the bond is absent, then when t is 0, q is 4 or more and p is 1, when t is 1 or more, q is 2 or more and p is 1;


(B) followed by intramolecular amination to yield (17) of the formula



wherein the various terms are defined as for (16) and X is an anion, e.g., a halide ion;

and then either basic or acidic hydrolysis to form a compound of Formula (1); or


(B) an electrophilic substrate, in a polar solvent, optionally in the presence of a non-nucleophilic base, to form a salt (17) of the formula



wherein Q, s, R and R¹ are defined as for Formula (1), X is an anion, and the dotted line represents the presence of a bond, t is 0, q is 2 to 3, and p is 1;

and then basic hydrolysis to form a compound of Formula (1); or and then basic hydrolysis to form a compound of Formula (1); or

(C) an electrophilic substrate, in a polar solvent, optionally in the presence of a non-nucleophilic base, to form (17) of the formula



wherein Q, s, R and R¹ are defined as for Formula (1), X is an anion, and the dotted line represents the presence of a bond, t is 0, q is 2 to 3, and p is 1;

followed by prolonged heating in a polar solvent or by treatment with a peroxide solution to form (18) of the formula

5,587,453

PROCESS FOR PURIFYING METHACRYLATE
 Takafumi Abe; Mitsubishi Nishikawa, and Susumu Naitoh, all of Niigata, Japan, assignors to Mitsubishi Gas Chemical Company, Inc., Tokyo, Japan

Filed Feb. 1, 1995, Ser. No. 381,740

Claims priority, application Japan, Feb. 25, 1994, 6-028191; Mar. 25, 1994, 6-055788; Mar. 25, 1994, 6-055789; Apr. 7, 1994, 6-069416

U.S. Cl. 528—488


Int. Cl.⁶ C08F 6/24

20 Claims

1. A process for purifying a methacrylate which comprises contacting the methacrylate with at least one treating agent selected from the group consisting of (a) an oxidizing agent comprising at least one compound selected from the group consisting of hydroxylamine and a mineral acid salt thereof and (b) an aqueous alkali solution, and then separating and collecting the resultant purified methacrylate.

wherein Q, s, R and R¹ are defined as for Formula (1) and the dotted lines represent the presence of a double bond, t is 0, q is 2 to 3, and p is 1;

followed by basic hydrolysis to form the urea (19) of the formula



wherein Q, s, R and R¹ are defined as for Formula (1) and t is 0, q is 2 to 3, and p is 1;

then basic hydrolysis under pressure to form a compound of Formula (1); and separating the desired polyazamacrocycle.

5,587,454

OMEGA CONOPEPTIDE COMPOSITIONS
 Alan Justice, Sunnyvale; Tejinder Singh, Palo Alto; Kishor C. Gohil, Richmond; Karen L. Valentino, San Carlos, and George P. Miljanich, Redwood City, all of Calif., assignors to Neurex Corporation, Menlo Park, Calif.

Continuation-in-part of Ser. No. 814,759, Dec. 30, 1991, abandoned. This application Apr. 15, 1993, Ser. No. 49,794

Int. Cl.⁶ A61K 38/00; C07K 5/00; 7/00; 17/00

U.S. Cl. 530—324

3 Claims

1. An omega conopeptide having the sequence: SEQ ID NO: 30 (SNX-236).

5,587,455

CYTOTOXIC AGENT AGAINST SPECIFIC VIRUS INFECTION


Edward A. Berger, Rockville; Bernard Moss, Bethesda; Thomas R. Fuerst, Gaithersburg; Ira Pastan, Potomac; David Fitzgerald, Rockville, all of Md.; Tamio Mizukami, Machida, Japan, and Vijay K. Chaudhary, New Delhi, Ind., assignors to The United States of America as represented by the Department of Health and Human Services, Washington, D.C.

Continuation of Ser. No. 22,182, Feb. 25, 1993, abandoned, which is a division of Ser. No. 223,270, Jul. 22, 1988, Pat. No. 5,206,353. This application Nov. 8, 1994, Ser. No. 335,669

Int. Cl.⁶ C07K 14/21; 14/73

U.S. Cl. 530—324

8 Claims



5,587,452

POLYAMIDE-IMIDE

Cornelis E. Koning, Schinnen, Netherlands, and Lilian M. J. Teuwen, Maaseik, Belgium, assignors to DSM N.V., Netherlands

Filed Jul. 3, 1995, Ser. No. 498,278


Claims priority, application Belgium, Jul. 11, 1994, 09400643

Int. Cl.⁶ C08G 73/14

U.S. Cl. 528—350

18 Claims

1. A semi-crystalline polyamide-imide containing recurring units represented by the formula



wherein said formula

Y represents an arylene group, and

R and R¹ are alkylene groups.

and wherein at least 50 mole % of at least one of R or R¹ is a linear butylene group.

1. A hybrid protein comprising a virus binding region from a cellular receptor sequence linked to a protein toxin sequence containing a region essential for cell toxicity, wherein said cellular receptor sequence is CD4.

5,587,456

HYDROPHOBIC ATTACHMENT SITE FOR ADHESION PEPTIDES

Michael D. Pierschbacher, San Diego; Cyril J. Honsik, La Jolla, and Lisa B. Dreishach, Cardiff, all of Calif., assignors to La Jolla Cancer Research Foundation, La Jolla, Calif. Continuation of Ser. No. 787,318, Oct. 30, 1991, abandoned, which is a continuation of Ser. No. 326,168, Mar. 20, 1989, Pat. No. 5,120,829. This application Aug. 20, 1992, Ser. No. 932,929

Int. Cl.⁶ A61K 38/00; C07K 5/00; 7/00

U.S. Cl. 530—326

5 Claims

1. A substantially pure active adhesion peptide comprising a cell attachment promoting binding site containing (D-)RGD and a hydrophobic attachment domain having hydrophobicity between that exhibited by the amino acid sequence L₄ and that exhibited by the amino acid sequence L₆, wherein said substantially pure active adhesion peptide, when adsorbed to a solid surface, can cause the attachment of cells to the solid surface.

5,587,457

NEUTROPHIL STIMULATING PEPTIDES

Deborah A. Rathjen, Thornleigh, and Antonio Ferrante, Mount Osmond, both of Australia, assignors to Peptide Technology Limited, Australia

Continuation-in-part of Ser. No. 930,415, Nov. 9, 1992, abandoned. This application Aug. 16, 1993, Ser. No. 107,235

Claims priority, application Australia, Mar. 12, 1990, PJ9065

Int. Cl.⁶ A61K 38/00; 37/02; C07K 7/06; 14/00

U.S. Cl. 530—326

6 Claims

1. A peptide having the formula: Leu-Phe-Lys-Gly-Gln-Gly-Cys-Pro-Ser-Thr-His-Val-Leu-Leu-Thr-His-Thr-Ile-Ser-Arg-Ile (SEQ ID NO.:6).

5,587,458

ANTI-ERBB-2 ANTIBODIES, COMBINATIONS THEREOF, AND THERAPEUTIC AND DIAGNOSTIC USES THEREOF

C. Richter King; Phillip G. Kasprzyk, both of Washington, D.C., and Robert E. Bird, Rockville, Md., assignors to Aronex Pharmaceuticals, Inc., The Woodlands, Tex.

Continuation-in-part of Ser. No. 906,555, Jun. 30, 1992, which is a continuation-in-part of Ser. No. 772,270, Oct. 7, 1991, abandoned. This application May 14, 1993, Ser. No. 61,092

Int. Cl.⁶ C07K 16/00; 16/46; 16/28

U.S. Cl. 530—387.3

12 Claims

1. A single chain antibody which binds to erbB-2 which comprises the variable heavy and light domains of a monoclonal antibody selected from the group consisting of e21 having ATCC Accession No. HB11602 and e23 having ATCC Accession No. HB11601.

5,587,459

IMMUNOCONJUGATES COMPRISING TYROSINE KINASE INHIBITORS

Fatih M. Uckun, White Bear Lake, Minn., assignor to Regents of the University of Minnesota, Minneapolis, Minn.

Filed Aug. 19, 1994, Ser. No. 293,731

Int. Cl.⁶ C07K 16/28

U.S. Cl. 530—391.1

4 Claims

1. An immunoconjugate comprising genistein linked to an anti-CD19 antibody which specifically binds to cell surface CD19 receptor, wherein said immunoconjugate inhibits CD19 associated tyrosine kinase, thereby inducing apoptosis and cell death.

5,587,460

14-BETA-GAL MAMMALIAN LECTINS

Glenn E. Nedwin, Half Moon Bay; Timothy S. Bringman, Burlingame, all of Calif., and Pierre-Olivier Couraud, Leperay, France, assignors to Incyte Pharmaceutical Corporation, Palo Alto, Calif.

Continuation of Ser. No. 313,649, Feb. 21, 1989, abandoned, which is a continuation-in-part of Ser. No. 263,734, Oct. 28, 1988, which is a continuation-in-part of Ser. No. 181,747, Apr. 14, 1988, abandoned. This application Aug. 5, 1994, Ser. No. 286,807

Int. Cl.⁶ C07K 14/435; C08G 69/26; C12N 15/00

U.S. Cl. 530—396

1 Claim

1. A human HL-60 lectin in purified and isolated form, said lectin having an amino acid sequence consisting of positions 2–135 in FIG. 1A; and

having a molecular weight of about 14 kd,

wherein said human HL-60 lectin is homogeneous

using the criterion of producing a single peak when subjected to C4-HPLC, capable of binding to asialofetuin and trypsinized rabbit erythrocytes and wherein agglutination of said lectin is inhibited by thiodigalactoside and beta-lactose.

5,587,461

AROMATIC ACIDS

Jui Y. Chang, Bubendorf, Switzerland, assignor to Ciba-Geigy Corporation, Ardsley, N.Y.

Division of Ser. No. 255,298, Jun. 7, 1994, Pat. No. 5,382,659, which is a continuation of Ser. No. 56,725, May 3, 1993, abandoned, which is a division of Ser. No. 758,249, Sep. 11, 1991, Pat. No. 5,229,503, which is a continuation of Ser. No. 348,315, May 5, 1989, abandoned. This application Sep. 30, 1994, Ser. No. 316,268


Claims priority, application Switzerland, May 10, 1988, 1766/88; Mar. 22, 1989, 1065/89

Int. Cl.⁶ C07K 1/107

U.S. Cl. 530—404

6 Claims

1. A process for the chemical modification of a protein comprising the conversion of an amino group in the ε-position of a lysine building block of the protein to a carbamoyl or a thiocarbamoyl, or the conversion of a mercapto group of a cysteine building block of the protein into a carbonylmethylthio group, wherein the protein is reacted with a compound of formula I



wherein

R₁ is lower alkyl;R₂ is lower alkyl;

lower is 1–7 carbon atoms;

R₃ is hydrogen, carboxy, or sulfo;R₄ is carboxy or sulfo;

G is a 1,4-phenylene group which is unsubstituted or is substituted by 1–4 substituents selected from carboxy and sulfo or G is a 1,4-naphthylene group which is unsubstituted or substituted by 1–6 substituents selected from carboxy and sulfo; and

wherein R₅ and R₆ together are an additional bond; and

L is an oxygen atom or a sulfur atom; or

wherein R₅ is hydrogen;

R₆ is halomethyl; and

L is an oxygen atom,

or a salt thereof.

5,587,462

BRAIN-DERIVED MEMBRANE-ASSOCIATED CRF BINDING PROTEINS

Dominic P. Behan, San Diego; Wylie W. Vale, Jr., La Jolla; Wolfgang H. Fischer, Encinitas, all of Calif., and Philip J. Lowry, Reading, England, assignors to The Salk Institute For Biological Studies, La Jolla, Calif.

Filed Nov. 8, 1993, Ser. No. 149,091

Int. Cl.⁶ C07K 14/705; 14/695

U.S. Cl. 530—350

11 Claims

5. An isolated, substantially pure CRF-binding protein which exhibits affinity to CRF and which has a molecular weight of at least about 33 kD as determined under reducing conditions by SDS page and has the amino acid sequence of a native mammalian protein that includes at least one sequence selected from the group consisting of the following sequences of SEQ NO: 1: residues 1–16, residues 20–37, residues 110–120, residues 206–222 and residues 248–256.

5,587,463

TEXAPHYRIN MACROCYCLES AND METAL COMPLEXES THEREOF

Jonathan L. Sessler; Gregory W. Hemmi, both of Austin, Tex., and Toshiaki Murai, Gifu, Japan, assignors to Board of Regents, The University of Texas System, Austin, Tex.


Division of Ser. No. 871,357, Apr. 20, 1992, Pat. No. 5,292,414, which is a division of Ser. No. 771,393, Sep. 30, 1991, abandoned, which is a continuation-in-part of Ser. No. 539,975, Jun. 18, 1990, Pat. No. 5,162,509, which is a division of Ser. No. 320,293, Mar. 6, 1989, Pat. No. 4,935,498. This application Mar. 8, 1994, Ser. No. 207,845

Int. Cl.⁶ A61K 49/00; C07D 255/02

U.S. Cl. 534—15

23 Claims

2. A compound having the structure



wherein the substituents R₁, R₂ and R₃ are separately and independently selected from the group consisting of H, alkyl, amino, hydroxy, alkoxy, carboxy, carboxyalkyl, carboxamide, ester, amide, polyether, sulfonate, nitro, halide other than iodide, substituted alkyl, substituted ester, substituted ethers, and substituted amide;

R₄ and R₅ are separately and independently selected from the group consisting of H, alkyl, amino, hydroxy, alkoxy, carboxy, carboxyalkyl, carboxamide, ester, amide, polyether, sulfonate, nitro, halide other than iodide, substituted alkyl, substituted ester, substituted ethers and substituted amide or together form an alkenylene bridge of the formula —C(R₆)=C(R₇)—CH=CH—;

where R₆ and R₇ are separately and independently selected from the group consisting of H, alkyl, amino, hydroxy, alkoxy, carboxy, carboxyalkyl, carboxamide, ester, amide, polyether, sulfonate, nitro, halide other than iodide, substituted alkyl, substituted ester, substituted ethers and substituted amide;

M is H, a di- or trivalent metal cation; and

n is between –5 and +5.

5,587,464

PROCESS FOR PRODUCING DIAZOMETHANE DERIVATIVES

Ichiro Kawahara, Tokushima; Isao Wada, Naruto, and Michio Sasaoka, Tokushima, all of Japan, assignors to Otsuka Kagaku Kabushiki Kaisha, Osaka, Japan

PCT No. PCT/JP94/02124, § 371 Date Aug. 14, 1995, § 102(e) Date Aug. 14, 1995, PCT Pub. No. WO95/16666, PCT Pub. Date Jun. 22, 1995

PCT Filed Dec. 16, 1994, Ser. No. 501,090


Claims priority, application Japan, Dec. 17, 1993, 5-318495

Int. Cl.⁶ C07C 245/14


U.S. Cl. 534—558

18 Claims

1. A process for producing a diazomethane derivative represented by the general formula



wherein Ar represents an aryl group which may be substituted, characterized in that a hydrazine derivative represented by the general formula



wherein Ar as defined above is oxidized in a two-phase system comprising

- a mixed aqueous solution containing, based on the total weight of the mixed aqueous solution, 4 to 14 w/w % of a caustic alkali and 3 to 10 w/w % of an alkali metal hypochlorite,
- a hydrophobic organic solvent,
- an inorganic iodine compound, and
- a phase transfer catalyst.

5,587,465

5-CHLORO-4-FLUOROPYRIMIDINYL SUBSTITUTED DIAZOPYRIDONE

Karl-Heinz Schündehütte, Leverkusen, and Karl J. Herd, Odenthal, both of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany


Filed Jan. 4, 1990, Ser. No. 460,702

Claims priority, application Germany, Jan. 10, 1989, 39 00 535.6

Int. Cl.⁶ C09B 62/245; 62/25; D06P 1/382

U.S. Cl. 534—635

1. A dyestuff of the formula:



wherein

R'=H, CH₃, C₂H₅, C₃H₇, or C₄H₉.

5,587,466

CONDUCTIVE POLYMER DOPED BY A SULFONATED CYCLODEXTRIN SALT AND DEVICE FOR OBTAINING AND/OR SUPPLYING AN ACTIVE SUBSTANCE INCORPORATING SAID POLYMER

Eric Viell, Meylan; Gérard Bidan, Grenoble; Andrée Gadelle, Montbonnot, and Maria-Fatima Mendes-Viegas, Lyons, all of France, assignors to Commissariat A L'Energie Atomique, Paris, France

Division of Ser. No. 246,125, May 19, 1994, Pat. No.

5,480,924. This application Oct. 5, 1995, Ser. No. 539,437

Claims priority, application France, Jun. 3, 1993, 93 06655

Int. Cl.⁶ C08L 3/02

U.S. Cl. 536—4.1

12 Claims

1. Apparatus for supplying an active substance comprising a container having therein a solution to which the active substance is to be added, an electrode having an electrically conductive polymer doped by a dopant as an active electrode material and containing said active substance, an auxiliary electrode, said electrodes extending into said solution, and voltage supply means for applying a voltage across said active electrode material and said auxiliary electrode and thereby controlling the supply of said active substance, said dopant being a cyclodextrin having at least one sulfonate group, and said active substance electrochemically salting out from said polymer in response to the application of voltage across said electrodes.

5,587,467

SEPARATING AGENT FOR OPTICAL ISOMERS AND PROCESS FOR PRODUCING THE SAME

Tatsushi Murakami, and Akito Ichida, both of Hyogo, Japan, assignors to Daiichi Chemical Industries, Ltd., Osaka, Japan

PCT No. PCT/JP94/00992, § 371 Date Jan. 11, 1995, § 102(e)

Date Jan. 11, 1995, PCT Pub. No. WO95/00463, PCT Pub. Date Jan. 5, 1995

PCT Filed Jun. 21, 1994, Ser. No. 374,530

Claims priority, application Japan, Jun. 22, 1993, 5-149956; Jun. 16, 1994, 6-134183; Jun. 20, 1994, 6-137214

Int. Cl.⁶ C08B 3/12; 3/30; 15/10; 31/04; B01J 20/10

U.S. Cl. 536—18.5

19 Claims

1. A separating agent for optical isomers comprising a polysaccharide derivative immobilized on a support, the molecules of the

polysaccharide derivative being solely crosslinked with each other through a crosslinking reaction and at least the surface of the support being inactive to said crosslinking reaction.

5,587,468

HIGH AFFINITY NUCLEIC ACID LIGANDS TO HIV INTEGRASE


Patrick Allen, and Larry Gold, both of Boulder, Colo., assignors to University Research Corporation, Boulder, Colo.

Continuation of Ser. No. 361,795, Dec. 21, 1994, which is a continuation-in-part of Ser. No. 714,131, Jun. 10, 1991, Pat. No. 5,475,096, Ser. No. 964,624, Oct. 21, 1992, and Ser. No. 117,991, Sep. 8, 1993, said Ser. No. 714,131 is a continuation-in-part of Ser. No. 536,428, Jun. 11, 1990, abandoned. This application May 16, 1995, Ser. No. 442,572

Int. Cl.⁶ C07H 21/02; 21/04; C12P 19/34; C12Q 1/68

U.S. Cl. 536—22.1

16 Claims



1. A purified and isolated non-naturally occurring nucleic acid ligand to HIV integrase.

5,587,469

OLIGONUCLEOTIDES CONTAINING N-2 SUBSTITUTED PURINES

Phillip D. Cook, San Marcos; Kanda S. Ramasamy, Laguna Hills, and Muthiah Manoharan, Carlsbad, all of Calif., assignors to Isis Pharmaceuticals, Inc., Carlsbad, Calif.

Division of Ser. No. 159,088, Nov. 29, 1993, Pat. No.


5,459,255, and a continuation-in-part of Ser. No. 854,634, Jul. 1, 1992, abandoned, each which is a continuation-in-part of Ser. No. 463,358, Jan. 11, 1990, abandoned, and Ser. No. 566,977, Aug. 13, 1990, abandoned. This application Aug. 30, 1995, Ser. No. 473,450

Int. Cl.⁶ C07H 21/02; 21/04

U.S. Cl. 536—23.1

29 Claims

1. An oligonucleotide having at least one nucleotide of formula:



wherein

G is CH or N;

X is NH₂ or OH;

Y is RQ or NHRQ, wherein said R is a hydrocarbyl group having from 2 to about 20 carbon atoms; and Q is H, NH₂, polyalkylamino, hydrazines, hydroxylamines, imidazoles, imidazole amides, alkylimidazoles, tetrazole, triazole, or alkoxy groups; and

Z is ribose, 2'-O alkyl ribose, or deoxyribose.

5,587,470

3-DEAZAPURINES

P. Dan Cook, Carlsbad; Oscar L. Acevedo, San Diego, and Robert S. Andrews, San Juan Capistrano, all of Calif., assignors to Isis Pharmaceuticals, Inc., Carlsbad, Calif.


Division of Ser. No. 27,011, Mar. 5, 1993, Pat. No. 5,457,191, which is a continuation-in-part of Ser. No. 463,358, Jan. 19, 1990, abandoned, and Ser. No. 566,977, Aug. 13, 1990, abandoned. This application Aug. 14, 1995, Ser. No. 514,762

Int. Cl.⁶ C07H 21/02; 21/04

U.S. Cl. 536—23.1


17 Claims

1. An oligonucleotide analog wherein at least one heterocyclic base of said oligonucleotide analog is a 3-deazapurine base having the formula:



wherein G is C or N; R₁ is NH₂, alkyl having from one to about 12 carbons, substituted alkyl having from one to about 12 carbons, alkenyl having from two to about 12 carbons, substituted alkenyl having from two to about 12 carbons, aralkyl having from about 6 to about 30 carbons, or amino, and R₂ is amino, alkyl having from one to about 12 carbons, substituted alkyl having from one to about 12 carbons, alkenyl having from two to about 12 carbons, substituted alkenyl having from two to about 12 carbons, or aralkyl having from about 6 to about 30 carbons.

10. An oligonucleotide analog wherein at least one heterocyclic base of said oligonucleotide analog is a 3-deazapurine base having the formula:



wherein G is C or N; R₁ is H, NH₂, alkyl having from one to about 12 carbons, substituted alkyl having from one to about 12 carbons, alkenyl having from two to about 12 carbons, substituted alkenyl having from two to about 12 carbons, aralkyl having from about 6 to about 30 carbons, or amino; and R₄ is NH₂, alkyl having from one to about 12 carbons, substituted alkyl having from one to about 12 carbons, alkenyl having from two to about 12 carbons, substituted alkenyl having from two to about 12 carbons, aralkyl having from about 6 to about 30 carbons, or amino; provided that when R₃ is H, R₄ is not NH₂.

5,587,471

METHOD OF MAKING OLIGONUCLEOTIDE LIBRARIES

Phillip D. Cook, Carlsbad; David J. Ecker, Encinitas; Oscar L. Acevedo, San Diego, and Peter Davis, Carlsbad, all of Calif., assignors to Isis Pharmaceuticals, Inc., Carlsbad, Calif.

Filed Jan. 11, 1994, Ser. No. 179,972

Int. Cl.⁶ C07H 21/00

U.S. Cl. 536—25.3

24 Claims

1. A method of preparing a random phosphate linked oligomer library comprising:

- selecting a group of phosphorous bearing monomers;
- testing said group of monomers for chemical suitability with respect to at least one predetermined parameter;
- selecting from said group of phosphorous bearing monomers a sub-group of monomers that are chemically suitable with respect to said predetermined parameter;
- reacting each of the monomers of said sub-group of monomers to a standard reactive site located on a solid support;
- analyzing the relative coupling efficiency of each of said monomers of said sub-group of monomers with said standard reactive site;
- preparing a mixture of said monomers of said sub-group of phosphorous bearing monomers adjusted in accordance with coupling efficiencies determined in step (e);
- reacting via phosphate coupling said adjusted mixture of phosphorous bearing monomers of said sub-group to a solid support or growing oligomer chain; and
- repeating step (g) in order to prepare a random oligomer library comprising oligomers of a desired length.

5,587,472

COUMARIN-LABELED NUCLEOSIDE 5'-TRIPHOSPHATES

Nanibhushan Dattagupta, San Diego, Calif., and Jürgen Köcher, West Haven, Conn., assignors to Bayer Corporation, Tarrytown, N.Y.


Continuation of Ser. No. 799,470, Nov. 26, 1991, abandoned, which is a continuation-in-part of Ser. No. 744,555, Aug. 13, 1991, abandoned. This application Jun. 2, 1995, Ser. No. 460,027

Int. Cl.⁶ C07H 19/10; 19/20; 21/04

U.S. Cl. 536—26.2

5 Claims


1. A fluorescent label compound having the formula:




wherein

A represents a radical selected from the group consisting of dATP-8-yl and dUTP-5-yl;

B¹-B²-B³ collectively represent a spacer moiety selected from the group consisting of:




and



wherein

"a" represents the point of attachment to A; and

C represents a coumarin radical having the formula:



5,587,473

7-ACYL-3-(SUBSTITUTED CARBAMOYLOXY) CEPHEM COMPOUNDS AND PROCESS FOR THEIR PREPARATION

Shigetoe Negi, Ibaraki Prefecture; Motosuke Yamanaka, Chiba Prefecture; Kanemasa Katsu, Ibaraki Prefecture; Isao Sugiyama, Ibaraki Prefecture; Yuuki Komatsu, Ibaraki Prefecture; Atsushi Kamata, Ibaraki Prefecture; Akihiko Tsuruoka, Ibaraki Prefecture, and Yoshimasa Machida, Ibaraki Prefecture, all of Japan, assignors to Eisai Co., Ltd., Tokyo, Japan

Division of Ser. No. 393,074, Feb. 23, 1995, Pat. No. 5,563,265, which is a continuation of Ser. No. 209,484, Mar. 14, 1994, Pat. No. 5,559,225, which is a continuation of Ser. No. 789,669, Nov. 8, 1991, abandoned. This application Jun. 27, 1996, Ser. No. 671,342


Claims priority, application Japan, Nov. 9, 1990, 2-302783; Feb. 14, 1991, 3-40747; Mar. 8, 1991, 3-67709; Apr. 12, 1991, 3-169512

Int. Cl.⁶ C07D 501/22; A61K 31/545


U.S. Cl. 540—222

4 Claims


1. A process for the preparation of the compound represented by the formula (1):




wherein A means a $-\text{CH}=\text{CH}-$ or $-\text{N}=\text{N}-$ group; R^1 denotes a hydroxyl group, a lower alkoxy group, a fluorine-substituted lower alkoxy group or a hydroxyl group protected by a protecting group; R^2 and R^3 are the same or different and individually represent a lower alkyl group, a hydroxyl-substituted lower alkyl group, a carbamoyl-substituted lower alkyl group or a cyano-substituted lower alkyl group; R^4 is a hydrogen atom and R^5 is a lower alkoxy group or a lower alkyl group which may optionally be substituted by one or more halogen atoms, or the group represented by the formula



means a 4-6 membered heterocyclic group, which contains one nitrogen atom, or a morpholino group, said heterocyclic group or morpholino group being optionally substituted by one or more lower alkyl, hydroxyl and/or hydroxyl-substituted lower alkyl groups; and R^4 denotes a carboxyl group or a carboxyl group protected by a protecting group; or a pharmaceutically acceptable salt thereof, which comprises reacting a compound represented by the following formula (2):



wherein R^2 , R^3 and R^4 have the same meanings as defined above or a salt thereof with a compound represented by the following formula (3):



wherein R^6 represents an amino group or an amino group protected by a protecting group, A and R^1 have the same meanings as defined above, or a reactive acid derivative thereof or a salt thereof; and, if

necessary, removing the protecting group of the amino, carboxyl or hydroxyl group or protecting the carboxyl group with a protecting group.

5,587,474

METHOD FOR REMOVING THE PROTECTING GROUP FOR CARBOXYL GROUP

Kazuhiko Kondo, Osaka; Hiroshi Horikawa, Kawanishi, and Tameo Iwasaki, Nishinomiya, all of Japan, assignors to Tanabe Seiyaku Co., Ltd., Osaka, Japan

Filed Jun. 17, 1993, Ser. No. 77,383


Claims priority, application Japan, Jun. 18, 1992, 4-202866; Dec. 4, 1992, 4-325031

Int. Cl.⁶ C07D 403/12

U.S. Cl. 540—350

16 Claims

1. A method for removing the the protecting group of the carboxyl group from a compound of the formula II.



wherein R is the formula: $-\text{CH}_2-\text{CH}=\text{CHR}^0$, R^0 is a hydrogen atom, a lower alkyl group or a phenyl group, R^4 is a hydrogen atom or a protecting group for a hydroxy group, and R^5 is a hydrogen atom or a lower alkyl group comprising: reacting said compound II with an alkyl-scavenger selected from the group consisting of dimedone, 1,3-cyclohexadione, acetylacetone, ethylacetoacetate, an N-lower alkyl aniline and aniline in the presence of a palladium (II) compound and a compound selected from the group consisting of a tri-lower alkyl phosphate and a triphenyl phosphine in an aqueous organic solvent.

5,587,475

DERIVATIZED VIRGINIAMYCIN M₁

Paul Helquist, Granger, Ind., and Carlo Cocito, Brussels, Belgium, assignors to University of Notre Dame, Notre Dame, Ind.


Filed May 18, 1995, Ser. No. 444,236

Int. Cl.⁶ C07D 498/14; A61K 37/00; 37/02


U.S. Cl. 540—456

22 Claims

1. A compound having the formula




in which Y represents one of $(\text{CH}_2)_n$, ($n=1$ to 20), $(\text{CH}_2)_m\text{CH}[(\text{CH}_2)_n\text{CH}_3](\text{CH}_2)_p$, ($m=0$ to 20, $n=0$ to 20, $p=0$ to 20), and




(m = 0 to 10, n = 0 to 10, p = 0 to 10, q = 0 to 10)

or unsaturated derivatives thereof wherein adjacent pairs of saturated carbon atoms are replaced by alkene or alkyne units; and in which Z represents one of $\text{CO}_2\text{CH}_2\text{CCl}_3$, $\text{CO}_2(\text{CH}_2)_n\text{CH}_3$, $\text{CO}_2(\text{CH}_2)_m\text{CH}[(\text{CH}_2)_n\text{CH}_3](\text{CH}_2)_p\text{CH}_3$, $\text{CO}_2(\text{CH}_2)_m(\text{CH}=\text{CH})(\text{CH}_2)_n\text{H}$, CO_2H , CONH_2 , CONHR (R =saturated or unsaturated n-alkyl or branched alkyl as shown for the esters above), CONRR' (R and R' =saturated or unsaturated n-alkyl or branched alkyl as shown for the esters above), and CO_2^-M^+ (M^+ =lithium, sodium, potassium, cesium, magnesium, or calcium cation, with or without other coordinating groups, or ammonium, monoalkylammonium, dialkylammonium, trialkylammonium, or tetraalkylammonium bearing n-alkyl or branched alkyl groups as shown for the esters above, or ammonium salt derivatives of amino acids), including isomeric forms and mixtures thereof.

2. A process for preparing a virginiamycin derivative of the formula



and isomeric forms and mixtures thereof, in which S represents a sulfur atom, Y represents one of $(\text{CH}_2)_n$, ($n=1$ to 20), $(\text{CH}_2)_m\text{CH}[(\text{CH}_2)_n\text{CH}_3](\text{CH}_2)_p$, ($m=0$ to 20, $n=0$ to 20, $p=0$ to 20), and




(m = 0 to 10, n = 0 to 10, p = 0 to 10, q = 0 to 10)

where R^1 is (C_2-C_4) -alkylene or 1,2- or 1,3-cyclo- (C_3-C_7) -alkylene and R^2 and R^3 which are identical or different, are (C_1-C_3) -alkyl or hydrogen or R^2 and R^3 together are (C_2-C_4) -alkylene, with fullerene C_{60} and/or C_{70} , and also its acid-addition salts, with the proviso that addition compounds obtainable by reaction of a diamine of the formula I in which $\text{R}^1=\text{C}_2$ -alkylene and R^2 and R^3 =hydrogen with fullerene C_{60} are excluded.

ammonium, monoalkylammonium, dialkylammonium, trialkylammonium, or tetraalkylammonium bearing n-alkyl or branched alkyl groups as shown for the esters above, or ammonium salt derivatives of amino acids), comprising:

reacting a ω -mercapto ester having the formula SYZ, wherein S, Y and Z are as defined above, with a virginiamycin M_1 sample having the formula:



in an organic solvent in the presence of a base, said reaction occurring under reaction conditions conducive for attachment of the SYZ side chain to said virginiamycin M_1 via a Michael addition.

5,587,476

FULLERENE DERIVATIVES, METHOD OF SYNTHESIZING THEM AND THEIR USE

Klaus-Dieter Kampe, Bad Soden am Taunus; Hans-Ulrich ter Meer, Frankfurt am Main; Norbert K. Egger, Wiesbaden, and Martin A. Vogel, Nackenheim, all of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt, Germany

PCT No. PCT/EP93/02306, § 371 Date Feb. 15, 1995, § 102(e) Date Feb. 15, 1995, PCT Pub. No. WO94/05671, PCT Pub. Date Mar. 17, 1994

PCT Filed Aug. 26, 1993, Ser. No. 381,946


Claims priority, application Germany, Sep. 8, 1992, 42 29 979.9; Apr. 19, 1993, 43 12 632.4

Int. Cl.⁶ C07D 241/38; 243/10; 245/04; 487/06

U.S. Cl. 540—472

20 Claims

1. An addition compound obtainable by reaction of a diamine of the formula 1,



where R^1 is (C_2-C_4) -alkylene or 1,2- or 1,3-cyclo- (C_3-C_7) -alkylene and R^2 and R^3 which are identical or different, are (C_1-C_3) -alkyl or hydrogen or R^2 and R^3 together are (C_2-C_4) -alkylene, with fullerene C_{60} and/or C_{70} , and also its acid-addition salts, with the proviso that addition compounds obtainable by reaction of a diamine of the formula I in which $\text{R}^1=\text{C}_2$ -alkylene and R^2 and R^3 =hydrogen with fullerene C_{60} are excluded.

5,587,482


ZEROMETHINE MERCYANINE DYES USEFUL AS SPECTRAL SENSITIZERS IN PHOTOGRAPHIC ELEMENTS

Dietrich M. Fabricius, Hendersonville, N.C.; Ralf H. Harms, Neu-Isenburg, Germany, and James J. Welter, Flat Rock, N.C., assignors to Sterling Diagnostic Imaging, Inc., Glasgow, Del.

Filed Mar. 7, 1996, Ser. No. 612,354
Int. Cl. C07D 417/04

U.S. Cl. 548—179

1. A dye having the structure:



wherein:

R¹, R², R³, and R⁴ each independently represents H; halogen; alkyl of 1-6 carbons; aryl of 6-24 carbons; alkoxy of 1-6 carbons; carbonyl; or sulfonate; or R¹ and R², R³ and R⁴, or R³ and R⁴ taken together represent the atoms necessary to complete a six-membered carbocyclic ring;
R⁵ represents hydrogen, alkyl of 1-6 carbons or aryl of 6-24 carbons;
R⁶, R⁷, and R⁸ independently represent alkyl 1-6 carbons; aryl of 6-24 carbons; or any pair of R⁶, R⁷ and R⁸ taken together represent a five- or six-member heterocyclic ring;
X represents O, S, CH=CH, Se, Te or N—R⁹;
Y represents O, S, or N—R¹⁰;
Z represents O, S or Se;
R⁹ represents alkyl of 1-6 carbons; or an aryl of 6-24 carbons;
R¹⁰ represents alkyl of 1-6 carbons;
n is an integer of 1-6; and
Q represents a counterion.

5,587,483


PROCESS FOR PREPARING TETRAZOL-5-YL SUBSTITUTED BENZOPYRAN COMPOUNDS

Graham Johnson, Worthing; Neil Smith, Shoreham-by-Sea; Graham R. Geen, Stansted Mountfitchet; Inderjit S. Mann, Welling, all of England, and Vance Novack, Devon, Pa., assignors to SmithKline Beecham PLC, United Kingdom

Filed May 26, 1995, Ser. No. 451,892


U.S. Cl. 548—252

1. A process for preparing a compound of structure (I):



in which,

R¹ is C₁₋₂₀alkyl, C₂₋₂₀alkenyl, C₂₋₂₀alkynyl, or a group of structure:



9 Claims

(I)

(II)

(III)

(IV)

(V)

(VI)

(VII)

(VIII)

(IX)

(X)

(XI)

(XII)

(XIII)

(XIV)

(XV)

(XVI)

(XVII)

(XVIII)

(XIX)

(XX)

(XXI)

(XXII)

(XXIII)

(XXIV)

(XXV)

(XXVI)

(XXVII)

(XXVIII)

(XXIX)

(XXX)

(XXXI)

(XXXII)

(XXXIII)

(XXXIV)

(XXXV)

(XXXVI)

(XXXVII)

(XXXVIII)

(XXXIX)

(XXXX)

(XXXXI)

(XXXXII)

(XXXXIII)

(XXXXIV)

(XXXXV)

(XXXXVI)

(XXXXVII)

(XXXXVIII)

(XXXXIX)

(XXXXX)

(XXXXXI)

(XXXXXII)

(XXXXXIII)

(XXXXXIV)

(XXXXXV)

(XXXXXVI)

(XXXXXVII)

(XXXXXVIII)

(XXXXXIX)

(XXXXXX)

(XXXXXXI)

(XXXXXXII)

(XXXXXXIII)

(XXXXXXIV)

(XXXXXXV)

(XXXXXXVI)

(XXXXXXVII)

(XXXXXXVIII)

(XXXXXXIX)

(XXXXXXX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

(XXXXXXXII)

(XXXXXXXIII)

(XXXXXXXIV)

(XXXXXXXV)

(XXXXXXXVI)

(XXXXXXXVII)

(XXXXXXXVIII)

(XXXXXXXIX)

(XXXXXXXI)

an aralkyl group, an alkoxy group, an alkenyloxy group, an aryloxy group, an aralkyloxy group or an amino group which may have a substituent, R^4 represents an alkyl group, an alkenyl group, an aryl group or an aralkyl group, R^5 represents a hydrogen atom, an alkyl group, an alkenyl group, an aryl group, an aralkyl group, an alkoxy group, an alkenyloxy group, an aryloxy group, an aralkyloxy group or an amino group which may have a substituent, in which R^2 and R^{11} may join together to form a bivalent organic group optionally containing an oxygen atom or a nitrogen atom.

5,587,487

TETRAIODOPYRROLE DERIVATIVES AS CONTRAST MEDIUM AND AS ANTISEPTIC

Christoph De Haen, Peschiera Borromeo; Fulvio Uggeri, Codogno; Ornella Gazzotti, Pianengo, and Marino Brocchetta, Pavia, all of Italy, assignors to Dibra S.p.A., Milan, Italy


PCT No. PCT/EP94/04201, § 371 Date May 25, 1995, § 102(e) Date May 25, 1995, PCT Pub. No. WO95/17380, PCT Pub. Date Jun. 29, 1995

PCT Filed Dec. 16, 1994, Ser. No. 448,510

Claims priority, application Italy, Dec. 23, 1993, MI93A2718 Int. Cl.⁶ C07D 207/305

U.S. Cl. 548—561


1. A compound of general formulae (I) and (II)



wherein:


m and n are independently between 0 and 5,

R is H, —OR₂, —NR₃R₄, wherein R₂ is H, straight or branched (C₁—C₈) alkyl, straight or branched (C₁—C₈) hydroxyalkyl with 1—7 —OH groups, or polyoxalkyl group of formula



wherein G is H, CH₃, CH₂CH₃,

R₁ and R₄ which are the same or different, have the same meanings as R₂, or they are a group of formula —(CH₂)₁₋₅R₅ where R₅ is one of the following groups COOH, SO₃H, PO₃H, or PCl₂H, or they are a group of formula —CH₂CH₂R₆ where R₆ is a quaternary ammonium group of aliphatic or aromatic nature, or a group of formula



wherein m has the above meanings, or R₃ and R₄ are a neutral or ionic organic group containing from one to two triiodinated aromatic nuclei, or R₃ and R₄, considered together, are a (C₃—C₇) group, optionally interrupted by atoms of O, S, N, or optionally substituted by hydrophilic or radiopaque functional groups.

R₁ has the same meanings as R and is different or the same as R, and

in case the compounds of formulae (I) and (II) contain free carboxylic and/or phenol functions, also the salts of said compounds with physiologically acceptable organic bases which are selected from primary, secondary or tertiary amines, or basic amino acids, or with inorganic bases whose cations are sodium, potassium, magnesium, calcium or their mixtures and, in case compounds of formulae (I) and (II) contain cationic functions, also the salts of said compounds with anions of physiologically acceptable organic acids selected from acetate, fumarate, succinate, oxalate, citrate, glutamate, aspartate or with anions of inorganic acids selected from chlorides, bromides, iodides or sulfates.

1 Claim

5,587,488

BIS-SULFONIUM SALTS OF AMINO SUBSTITUTED BIS(HALOMETHYL) BENZENE


John D. Stenger-Smith; William P. Norris, and Andrew P. Chafin, all of Ridgecrest, Calif., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

(II) Division of Ser. No. 252,701, May 31, 1994, abandoned. This application May 10, 1995, Ser. No. 441,178 Int. Cl.⁶ C07D 409/10

U.S. Cl. 549—59

4 Claims

1. The bis-sulfonium salts of amino substituted bis(halomethyl) benzene compounds having the formula:



wherein X is halogen; wherein R₁ and R₂ on the amine and quaternized amine group are each independently hydrogen; alkyl having 1 to about 22 carbon atoms; alkyl sulfonate having 1 to about 22 carbon atoms; or alcohol having 1 to about 22 carbon atoms, wherein R₃, R₄, and R₅ are each independently hydrogen; alkyl having 1 to about 22 carbon atoms; alkoxy having 1 to about 22 carbon atoms; nitro; halogen; amine; sulphonate; silyl; perfluoro alkyl; or cyano esters.

5,587,489

TAXANE AND BACCATIN III ANALOGS BEARING NEW C2 AND C4 FUNCTIONAL GROUPS

Robert A. Holton, and Seokchan Kim, both of Tallahassee, Fla., assignors to Florida State University, Tallahassee, Fla.

Division of Ser. No. 10,798, Jan. 29, 1993, Pat. No. 5,399,726.


This application Jan. 13, 1995, Ser. No. 372,103

Int. Cl.⁶ C07D 317/70;305/14

U.S. Cl. 549—229

34 Claims

1. A compound having the formula



wherein

R₁ is H, —OH, protected hydroxy, or —OCOR₆;


R₂ is a hydroxy protecting group;

R₃ is H or R₈CO—;

R₄ is —OH or protected hydroxy; and

R₅ and R₆ are independently H, C₁—C₆ alkyl, C₂—C₆ alkenyl, C₂—C₆ alkynyl, monocyclic aryl, or monocyclic heteroaryl.


3. A compound having the formula



wherein

R₁ is H, —OH, protected hydroxy, or —OCOR₆;

R₂ is H or a hydroxy protecting group, or



R₄ is R₈CO—;

R₅ is —OH or protected hydroxy;

R₆ and R₈ are independently H, C₁—C₆ alkyl, C₂—C₆ alkenyl, C₂—C₆ alkynyl, monocyclic aryl, or monocyclic heteroaryl;

R₉ is —OR₁₄, —SR₁₅, or —NR₁₆R₁₇;

R₁₀ is hydrogen, alkyl, alkenyl, alkynyl, aryl or heteroaryl;

R₁₁ and R₁₂ are independently hydrogen, alkyl, alkenyl, alkynyl, aryl, acyl or heteroaryl, provided R₁₁ and R₁₂ are not both acyl;

R₁₃ is —COR₁₈, —COOR₁₈, —COSR₁₈, —CONR₁₂R₁₈, or —SO₂R₁₉;

R₁₄ is hydrogen, alkyl, alkenyl, alkynyl, aryl, heteroaryl, or hydroxy protecting group;

R₁₅ is alkyl, alkenyl, alkynyl, aryl, heteroaryl, or sulfhydryl protecting group;

R₁₆ is hydrogen, alkyl, alkenyl, alkynyl, aryl, or heteroaryl;

R₁₇ is an amino protecting group;

R₁₈ is alkyl, alkenyl, alkynyl, aryl, or heteroaryl; and

R₁₉ is alkyl, alkenyl, alkynyl, aryl, heteroaryl, —OR₁₅, or —NR₁₂R₁₆.

5,587,490

METHOD OF INACTIVATION OF VIRAL AND BACTERIAL BLOOD CONTAMINANTS

Raymond P. Goodrich, Jr., Pasadena, Calif.; Matthew S. Platz, Columbus, Ohio; Nagender Yerram, South Pasadena; Roger W. Hackett, Pasadena, both of Calif.; Marjan van Borssum Waalkes, Vernendaal, Netherlands; Christine M. Williams-Hughes, Sierra Madre, Calif., and Victoria A. Wong, Cary, N.C., assignors to Credit Managers Association of California, Burbank, Calif.


Continuation-in-part of Ser. No. 47,749, Apr. 14, 1993, which is a continuation-in-part of Ser. No. 825,691, Jan. 27, 1992, abandoned, which is a continuation-in-part of Ser. No. 685,931, Apr. 16, 1991, abandoned, which is a continuation-in-part of Ser. No. 656,254, Feb. 15, 1991, abandoned, and a continuation-in-part of Ser. No. 632,277, Dec. 20, 1990, abandoned, which is a continuation-in-part of Ser. No. 686,334, Apr. 16, 1991, abandoned, and Ser. No. 510,234, Apr. 16, 1990, abandoned. This application Dec. 10, 1993, Ser. No. 165,305

Int. Cl.⁶ C07D 493/04

U.S. Cl. 549—282

7 Claims

1. A compound of the formula:



wherein X is an anionic counterion; R₁, R₂, R₃, R₄, R₅ and R₆ are independently a halogen; H; linear or branched alkyl of 1—10 carbon atoms; linear or branched alkoxy of 1—10 carbon atoms; —(CH₂)_m—O—(CH₂)_p—Z'.R'.R'' where n, m and p are independently integers from 1 to 10 and R', R'' and R''' are independently H or linear or branched alkyl of 1 to 10 carbon atoms with the proviso that only one of R₁, R₂, R₃, R₄, R₅ or R₆ is

$-(CH_2)_m-O-(CH_2)_p-Z'R'R''$ or $-O-(CH_2)_n-$ and a base, in an organic solvent, to yield a enyne of the formula $Z'R'R''$, and at least one of R_1 , R_2 , R_3 , R_4 , R_5 or R_6 is a halogen; and Z is N or P.


5,587,491
METHOD FOR THE SYNTHESIS OF BIS-TETRAHYDROFURANYL ANNONACEOUS ACETOGENINS

Thomas R. Hoyer, St. Paul, and Lushi Tan, Minneapolis, both of Minn., assignors to Regents of the University of Minnesota, Minneapolis, Minn.


Filed Mar. 15, 1995, Ser. No. 405,131
Int. Cl.⁶ C07D 305/12

U.S. Cl. 549—320


1. A method for preparing an acetogenin of formula (I):




wherein R^1 , R^2 and R^3 alkyl or aryl; comprising the steps of
(a) coupling a vinyl iodide of formula II:



wherein R^4 is a removable hydroxy protecting group, with a compound of formula (III):



in the presence of an effective amount of a palladium catalyst, CuI



6 Claims

(b) hydrogenating the enyne of formula IV and subsequently removing the hydroxy protecting group to yield a compound of formula I.


5,587,492
POLYHYDRIC PHENOL COMPOUND AND POSITIVE RESIST COMPOSITION COMPRISING THE SAME
Jun Tomioka, Hyogo; Yasunori Uetani, Osaka; Hirotohi Nakanishi, Osaka; Ryotaro Hanawa, Osaka, and Ayako Ida, Hyogo, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Division of Ser. No. 853,547, Mar. 18, 1992, Pat. No. 5,436,107. This application Apr. 18, 1995, Ser. No. 423,760
Claims priority, application Japan, Mar. 25, 1991, 3-60024
Int. Cl.⁶ C07D 311/60

U.S. Cl. 549—406

3 Claims

1. A polyhydric phenol compound of the formula:




wherein R_1 to R_5 are independently a hydrogen atom, an alkyl group, an alkenyl group, a cycloalkyl group or an aryl group, provided that at least one of R_1 and R_2 is an alkyl group, an alkenyl group, a cycloalkyl group or an aryl group.

5,587,493
PROCESS FOR PREPARING TAXOIDS
Hervé Bouchard, Ivry Sur Seine; Jean-Dominique Bourzat, Vincennes, and Alain Commerçon, Vitry-Sur-Seine, all of France, assignors to Rhone-Poulenc Rorer S.A., Antony, France
Division of Ser. No. 162,984, Dec. 8, 1993. This application Jun. 7, 1995, Ser. No. 487,232
Claims priority, application France, Dec. 9, 1992, 92 14813
Int. Cl.⁶ C07D 305/14


U.S. Cl. 549—510

32 Claims


1. A process for preparing a taxoid of formula I:




in which R represents a hydrogen atom or an acetyl, alkoxyacetyl, or alkyl radical, R_1 represents a benzoyl radical or a radical $R_2-O-CO-$ in which R_2 represents an alkyl, alkenyl, alkynyl, cycloalkyl, bicycloalkyl, phenyl or heterocyclyl radical, and Ar represents an aryl radical, comprising the steps of esterifying a compound of the formula VI:




in which G_1 represents a hydrogen atom or an acetyl, alkoxyacetyl or alkyl radical or a hydroxy-protecting group, with a free acid of the formula VII:




in which Ar and R_1 are as defined above, and R_3 and R_4 , which are identical or different, represent an alkyl radical containing 1 to 4 carbon atoms or an aralkyl radical whose alkyl portion contains 1 to 4 carbon atoms or an aryl radical, or R_3 represents a trihalomethyl radical or a phenyl radical substituted by a trihalomethyl radical and R_4 represents a hydrogen atom, or R_3 and R_4 form, together with the carbon atom to which they are attached, a 4- or 7-membered ring, to give, after treating in acidic medium, a compound of the formula IV:



in which Ar and G_1 are as defined above, acylating the compound with benzoyl chloride or a reactive derivative of the formula:




in which X represents a halogen atom or a residue $-O-R_2$ or $-O-CO-O-R_2$, and R_2 is as defined above, to give a product of formula I or a compound of formula III




wherein G_1 represents a protecting group that is removed to give a product of formula I.

17. A process for preparing a taxoid of formula I:




in which R represent a hydrogen atom or an acetyl, alkoxyacetyl, or alkyl radical, R_1 represents a radical $R_2-O-CO-$ in which R_2 represents an alkyl radical, and Ar represents an aryl radical, comprising the steps of esterifying a compound of the formula VI:



in which G_1 represents a hydrogen atom or an acetyl, alkoxyacetyl or alkyl radical or a hydroxy-protecting group, with a free acid of the formula VII:




in which Ar and R_1 are as defined above, and R_3 and R_4 , which are identical or different, represent an alkyl radical containing 1 to 4 carbon atoms or an aralkyl radical whose alkyl portion contains 1 to 4 carbon atoms or an aryl radical, or R_3 represents a trihalomethyl radical or a phenyl radical substituted by a trihalomethyl radical and R_4 represents a hydrogen atom, or R_3 and R_4 form, together with the carbon atom to which they are attached, a 4- or 7-membered ring, to give, after treating in acidic medium, a compound of the formula IV:



in which Ar and G₁ are as defined above, acylating the compound of formula IV with a benzoyl chloride or a reactive derivative of the formula:



in which X represents a halogen atom or a residue $-O-R_2$ or $-O-CO-O-R_2$, and R₂ is as defined above, to give a product of formula I or a compound of formula III



wherein G₁ represents a protecting group that is removed to give a product of formula I.

5,587,494

PRACTICAL, COST-EFFICIENT CHIRAL SYNTHESIS OF DIHYDROSPHINGOSINES


Raymond P. Panzica, Narragansett, R.I.; Hussein I. El Subhagh, Al-Hussnleh, Egypt, and Elie Abushanab, Peace Dale, R.I., assignors to The Board of Governors for Higher Education, State of Rhode Island and Providence Plantations, Providence, R.I.

Continuation-in-part of Ser. No. 852,885, Mar. 17, 1992, abandoned. This application Apr. 5, 1993, Ser. No. 42,875


Int. Cl.⁶ C07D 303/00; C07C 211/00; 209/00

U.S. Cl. 549-512



4 Claims




2. A process for the preparation of a compound of the structural formula 2




which comprises: adding an organomagnesium composition to a compound of the structural formula 4 to form a compound of the structural formula 6.




benzylating a compound of structural formula 6 to form a compound of the structural formula 7




hydrolyzing 7 with acid to form a compound of the structural formula 8




dehydrating 8 to form a compound of the structural formula 9



converting the epoxide of 9 to a corresponding alcohol to form a compound of the structural formula 10




inverting 10 to form a compound of the structural formula 12




reducing 12 to form the compound 2

where R₁, R₂ equals CH₃

R₃ equals CH₂C₆H₅ or



R₄ equals OCH₂C₆H₅, OC(CH₃)₃



R₅ equal C_nH_{2n+1} where n=1, 2, or 3.

5,587,495

4-SUBSTITUTED ANTHRACYCLINONES AND ANTHRACYCLINE GLYCOSIDES AND THE PROCESS FOR PREPARING THEM

Walter Cabri, Silvia De Bernardinis, both of Milan; Franco Francalanci, Novara, and Sergio Penco, Milan, all of Italy, assignors to Farmitalia Carlo Erba Srl, Milan, Italy

PCT No. PCT/EP89/01266, § 371 Date Apr. 25, 1991, § 102(e) Date Apr. 25, 1991, PCT Pub. No. WO90/04601, PCT Pub. Date May 3, 1990

PCT Filed Oct. 24, 1989, Ser. No. 678,352


Claims priority, application United Kingdom, Oct. 25, 1988, 8824947

Int. Cl.⁶ C07H 15/24

U.S. Cl. 552-220

16 Claims

1. A 4-substituted anthracyclinone of formula (I):



wherein R represents a straight or branched alkenyl of 2 to 4 carbon atoms.

5,587,496

15,15-DIALKYL-SUBSTITUTED DERIVATIVES OF ESTRADIOL

James R. Bull, Cape Town, South Africa; Karl-Heinrich Fritzmeier, and Christa Hegele-Hartung, both of Berlin, Germany, assignors to Schering Aktiengesellschaft, Berlin, Germany

Filed Aug. 2, 1994, Ser. No. 284,786


Claims priority, application Germany, Aug. 2, 1993, 43 26 240.6

Int. Cl.⁶ C07J 1/00

U.S. Cl. 552-629

13 Claims

1. A compound of formula IIa



wherein

R¹ is a straight-chain alkyl having 1-10 carbon atoms or a branched-chain alkyl group having 3-10 carbon atoms;

R³ and R⁴, independently of one another, are each a straight-chain alkyl having 1-10 carbon atoms or a branched-chain alkyl having 3-10 carbon atoms; and Z is an α-hydrogen atom and a β-hydroxy group or a keto-oxygen atom.

5,587,497

19-NOR-VITAMIN D COMPOUNDS

Hector F. DeLuca, Deerfield; Heinrich K. Schnoes; Kato L. Perlman, both of Madison, all of Wis.; Rafal R. Sicinski, Warsaw, Poland, and Jean M. Prah, Madison, Wis., assignors to Wisconsin Alumni Research Foundation, Madison, Wis.


Division of Ser. No. 281,261, Jul. 27, 1994, abandoned, which is a division of Ser. No. 123,485, Sep. 17, 1993, Pat. No. 5,342,975, which is a division of Ser. No. 960,241, Oct. 13, 1992, Pat. No. 5,246,925, which is a continuation of Ser. No. 879,706, May 5, 1992, abandoned, which is a continuation of Ser. No. 557,400, Jul. 3, 1990, abandoned, which is a division of Ser. No. 481,354, Feb. 16, 1990, Pat. No. 5,237,110, which is a continuation-in-part of Ser. No. 321,030, Mar. 9, 1989, abandoned. This application May 16, 1995, Ser. No. 442,492

Int. Cl.⁶ C07C 401/00


U.S. Cl. 552-653

12 Claims

1. A compound having the formula



where X¹ and X² are each selected from hydrogen, acyl, alkylsilyl and alkoxyalkyl, and where R is selected from alkyl, hydrogen, hydroxyalkyl, said hydroxyalkyl having from 4 to 5 carbon atoms, fluoroalkyl and a side chain of the formula



wherein R¹ represents hydrogen, hydroxy or O-acyl, R² and R³ are each selected from alkyl, hydroxyalkyl and fluoroalkyl, or, when taken together represent the group $-(CH_2)_m-$ where m is an integer having a value of from 2 to 5, R⁴ is selected from hydrogen, hydroxy, fluorine, O-acyl, alkyl, hydroxyalkyl and fluoroalkyl, R⁵ is selected from hydrogen, fluorine, alkyl, hydroxyalkyl and fluoroalkyl, or R⁴ and R⁵ taken together represent double-bonded oxygen, R⁶ and R⁷ are each selected from hydrogen, hydroxy, O-acyl, fluorine and alkyl, or, R⁶ and R⁷ taken together form a carbon-carbon double bond, and wherein n is an integer having a value of from 1 to 5 and wherein any of the groups $-CH(CH_3)-$, $-CH(R^7)-$, or $-CH(R^6)-$ at positions 20, 22 and 23, respectively, may be replaced by an oxygen atom, with the proviso that when n is 2 to 5 each R⁴ is independently selected from hydrogen, hydroxy, fluorine, O-acyl, alkyl, hydroxyalkyl and fluoroalkyl, and each R⁵ is independently selected from hydrogen, fluorine, alkyl, hydroxyalkyl and fluoroalkyl.

5,587,498

METHOD FOR AMIDE PREPARATION

James A. Krogh; Anita R. Mokadam, both of Janesville, and B. Brian Smith, McFarland, all of Wis., assignors to Exxon Chemical Patents, Inc., Baytown, Tex.
Continuation of Ser. No. 63, Jan. 4, 1993, abandoned. This application Sep. 28, 1994, Ser. No. 314,454
Int. Cl.⁶ C07C 237/00

U.S. Cl. 554—69

17 Claims

1. A method for the batch, continuous, or semi-continuous preparation of amides from carboxylic acids, comprising reacting an amine with a neo carboxylic acid having five to nineteen carbon atoms and which has an α -carbon that is at least trisubstituted, at a molar ratio of about 1:1, at a sufficient temperature of about 220°–350° C. in the presence of at least 0.001 weight percent, based on the reactants, of a catalyst containing a transition metal selected from Groups IVb, Vb, and VIb, said transition metal present on and bound to a solid support.

5,587,499


(METH) ACRYLIC COMPOUNDS, PROCESS FOR THEIR PREPARATION AND THEIR APPLICATION TO THE SYNTHESIS OF NEW POLYMERS

Michèle Currel, Metz; Jean-Luc Mieloszynski, Montigny Les Metz, and Daniel Paquer, Vandoeuvre, all of France, assignors to ELF Atochem S.A., France
Division of Ser. No. 18,594, Feb. 17, 1993, Pat. No. 5,457,172. This application May 11, 1995, Ser. No. 439,141
Claims priority, application France, Feb. 17, 1992, 92 01748
Int. Cl.⁶ C07C 53/126; 327/20; 69/02

U.S. Cl. 554—85


16 Claims

1. A process for the production of an acrylic compound of the formula (I):




wherein

Z is H or a linear or branched alkyl radical;
X is O or S;
A and B are each independently an unsubstituted alkylene radical;
R is H, an alkali metal, or a linear or branched alkyl radical;
x has the value of 0 or 1; and
y has the value of 0, 1 or 2, but is 0 when x=0,
with the proviso that the radical A does not exist if x and y are both equal to 0;
said process comprising:
reacting a compound of the formula (II)



wherein X, A and B are as defined above and Alk is a linear or branched alkyl radical,
with a compound of the formula (III)



wherein Z is as defined above, and Hal represents a halogen, in order to obtain a compound (I) wherein x=1, y=0 and R=alkyl (compound Ia);

optionally, further comprising treating said compound (Ia) with H⁺ ions to produce a compound (I) wherein x=1, y=0 and R=H (compound Ib);
optionally, further comprising converting said compound (Ib) into a salt to produce a compound (I) wherein x=1, y=0 and R=alkali metal (compound Ic);
optionally, further comprising reacting said compound (Ia) with an oxidizing agent to produce a compound (I) wherein x=1, y=1 or 2 and R=alkyl (compound Id), the molar ratio of oxidizing agent to compound (Ia) being at least equal to 1 and lower than 2 in order to obtain a sulfoxide, y=1, and at least equal to 2 in order to obtain a sulfone, y=2;
optionally, further comprising treating said compound (Id) with H⁺ ions to produce a compound (I) wherein x=1, y=1 or 2 and R=H (compound Ie); and
optionally, further comprising converting said compound (Ie) into a salt to produce a compound (I) wherein x=1, y=1 or 2 and R=alkali metal (compound If).


5,587,500

SULFONATION OF FATTY ACID ESTERS

Keith D. Hovda, Kent, Wash., assignor to The Chemithon Corporation, Seattle, Wash.
Filed Sep. 17, 1993, Ser. No. 123,448
Int. Cl.⁶ C11D 1/28

U.S. Cl. 554—98

65 Claims



1. In a process for preparing a sulfonated fatty acid ester surfactant including the steps of
(a) sulfonating a fatty acid ester thereby producing a crude sulfonic acid;
(b) reacting the crude sulfonic acid with a bleaching agent and an alcohol; and
(c) neutralizing the product formed in step (b);
the improvement comprising the following expedients:
(i) providing process equipment for performing step (b) comprising at least one of a continuous reactor vessel, a recirculation loop, a plug flow reactor, and a pressurized batch reactor vessel, said process equipment made from materials selected from the group consisting of non-metallic materials and low-iron, corrosion resistant alloys, said process equipment being wetted by the sulfonic acid and the bleaching agent during step (b); and
(ii) performing the neutralizing step (c) with a solid base in the presence of solvent in an amount sufficient to form a neutralization mixture in the form of one of a solution and a slurry, said solvent being predominantly alcohol.

5,587,501

PROCESS FOR THE PREPARATION OF SYNDIOTACTIC POLYOLEFINS HAVING A BROAD MOLECULAR WEIGHT DISTRIBUTION

Andreas Winter, Glashütten; Volker Dolle, Kelkheim am Taunus, and Walter Spaleck, Liederbach, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany
Division of Ser. No. 326,083, Dec. 22, 1994, Pat. No. 5,539,066, which is a continuation of Ser. No. 102,698, Aug. 5, 1993, abandoned, and a continuation of Ser. No. 888,559, May 27, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 473,080
Claims priority, application Germany, May 27, 1991, 41 17 260.4
Int. Cl.⁶ C07F 17/00

U.S. Cl. 556—53

5 Claims

1. A metallocene mixture comprising at least two different metallocenes which are encompassed by one or more of the following groups:
(diarylmethylene)(9-fluorenyl)(cyclopentadienyl)zirconium R¹R² or (dialkylmethylene)(9-fluorenyl)(cyclopentadienyl)zirconium R¹R² and in which R¹ and R² are identical or different and are a hydrogen atom, a halogen atom, a C₁–C₁₀-alkyl group, a C₁–C₁₀-alkoxy group, a C₆–C₁₀-aryl group, a C₆–C₁₀-aryloxy group, a C₂–C₁₀-alkenyl group, a C₇–C₄₀-aryllalkyl group, a C₇–C₄₀-alkylaryl group or C₈–C₄₀-aryllalkenyl group.

5,587,502


HYDROXY FUNCTIONAL ALKOXYSILANE AND ALKOXYSILANE FUNCTIONAL POLYURETHANE MADE THEREFROM

Dean M. Moren, North St. Paul, Minn., and Ian R. Owen, River Falls, Wis., assignors to Minnesota Mining & Manufacturing Company, St. Paul, Minn.
Filed Jun. 2, 1995, Ser. No. 460,349
Int. Cl.⁶ C07F 7/10

U.S. Cl. 556—420

27 Claims

1. A compound having the structure:



wherein

each R¹, R², R³, R⁴, R⁵, R⁶ and R⁹ is independently selected from the group consisting of hydrogen; linear, branched and cyclic alkyl groups having 1 to 18 carbon atoms, optionally comprising 1 to 3 non-terminal oxygen, sulfur, nitrogen or carbonyl groups in the hydrocarbon backbone of the alkyl group and optionally substituted with one or more hydroxyl groups; and aryl groups having 6 carbon atoms, optionally substituted with a halo, nitro or cyano group, or an alkyl, alkoxy, alkylthio, dialkylamino or carboalkoxy group each having 1 to 18 carbon atoms; with the proviso that at least one of R¹, R², R³ and R⁴ is not hydrogen;
R⁷ is selected from the group consisting of hydrogen and linear, branched and cyclic alkyl groups having 1 to 18 carbon atoms, optionally comprising 1 to 3 non-terminal oxygen, sulfur, nitrogen or carbonyl groups in the hydrocarbon backbone of the alkyl group;
R⁸ is selected from the group consisting of linear, branched and cyclic alkylene groups having at least two carbon atoms;
R¹⁰ is selected from the group consisting of linear, branched, and cyclic alkyl groups having at least 2 carbon atoms, optionally comprising 1 to 3 non-terminal oxygen, sulfur, nitrogen or carbonyl groups in the hydrocarbon backbone of the alkyl groups; m is 0, 1 or 2; and n is 1, 2, or 3.

5,587,503


PREPARATION OF SILICON-CONTAINING VINYL ETHERS AND VINYL THIOETHERS

Marc Heider, Neustadt; Jochem Henkelmann, Mannheim, and Michael Karcher, Schwetzingen, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany
Filed Aug. 24, 1995, Ser. No. 518,718
Claims priority, application Germany, Aug. 27, 1994, 44 30 477.3
Int. Cl.⁶ C07F 7/08

U.S. Cl. 556—427


4 Claims

1. A process for preparing silicon-containing vinyl ethers and vinyl thioethers of the general formula I



where the variables have the following meanings:

X is oxygen or sulfur,
R¹ is C₁–C₂₀-alkylene, C₃–C₁₂-cycloalkylene or C₆–C₁₀-arylene,
R², R³ and R⁴ are hydrogen, C₁–C₂₀-alkyl, C₃–C₁₂-cycloalkyl, C₁–C₁₂-alkoxy, phenoxy, heteroaryl or together with R¹ form a C₃–C₁₂-cycle,
by reaction of silicon-containing alcohols or thiols of the general formula II



where the variables have the meaning indicated above, with acetylene, which comprises carrying out the reaction in phenyl methyl sulfoxide, dimethyl sulfoxide, sulfolane or hexamethylphosphoramide in the presence of an alkali metal hydroxide.

5,587,504


SULFONYLOXY-BIPHENYLCARBOXYLIC ESTER DERIVATIVES WHICH ARE INTERMEDIATES

Yoshio Urawa; Ken Furukawa; Toshikazu Shimizu; Yoji Yamagishi, all of Ibaraki; Tomio Tsurugi, Chiba, and Tomio Ichino, Ibaraki, all of Japan, assignors to Eisai Co., Ltd., Tokyo, and Eisai Chemical Co., Ltd., Ibaraki, both of Japan
Division of Ser. No. 466,128, Jun. 6, 1995, which is a division of Ser. No. 256,869, Aug. 5, 1994. This application Oct. 19, 1995, Ser. No. 545,484
Claims priority, application Japan, Dec. 7, 1992, 4-351139; Dec. 16, 1992, 4-353865; Jun. 17, 1993, 5-169805; Jun. 17, 1993, 5-169823; Jun. 17, 1993, 5-169824; Jun. 17, 1993, 5-169825
Int. Cl.⁶ C07C 409/32

U.S. Cl. 558—58

3 Claims

1. A sulfonyloxy-biphenylcarboxylic ester derivative (I) having the following general formula:



wherein R¹ represents a lower alkylsulfonyl group or an arylsulfonyl group; and R² represents a lower alkyl group, an aryl group, an aralkyl group, a cycloether group, an aryloxyalkyl group, an aralkoxyalkyl group, a thioalkoxyalkyl group or a triphenylmethyl group.

5,587,505


TRITERPENE DERIVATIVES AND ENDOTHELIN-RECEPTOR ANTAGONISTS CONTAINING THE SAME
Toshiro Konoike, Suita; Yoshitaka Araki, Higashiosaka; Tetsuyoshi Hayashi, Otsu; Kensuke Sakurai, Kitakatsuragi-gun, and Takehiko Tozjo, Kobe, all of Japan, assignors to Shionogi & Co., Ltd., Osaka, Japan

Division of Ser. No. 258,392, Jun. 10, 1994, Pat. No. 5,463,107. This application Jul. 26, 1995, Ser. No. 507,211
Claims priority, application Japan, Jun. 11, 1993, 5-140416
Int. Cl.⁶ C07C 69/96; 229/34

U.S. Cl. 558—272

2 Claims

1. A compound of the formula (III)



wherein R² is hydrogen or —R¹—R⁴ wherein R¹ is —SO₃—, —CH₂COO—, —COCOO—, or —COR⁵COO— (R⁵ is lower alkylene or lower alkenylene), R⁴ is hydrogen or lower alkyl, and R⁶ is t-butoxycarbonyl or hydrogen, with the proviso that when R² is hydrogen, R⁶ is not hydrogen, or a pharmaceutically acceptable salt thereof.

5,587,506

PREPARATION OF N-PROTECTED N-ALKYLATED AMINO ACIDS

Klaus Knühl, Limburgerhof; Ulrich Karl, Ludwigshafen; Stefan Müller, Speyer, and Bernd de Potzoll, Bad Dürkheim, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

PCT No. PCT/EP94/03480, § 371 Date Sep. 6, 1995, § 102(e) Date Sep. 6, 1995, PCT Pub. No. WO95/12574, PCT Pub. Date May 11, 1995

PCT Filed Oct. 22, 1994, Ser. No. 530,310


Claims priority, application Germany, Nov. 2, 1993, 43 37 331.3

Int. Cl.⁶ C07C 269/06

U.S. Cl. 560—12

4 Claims


1. A process for preparing N-protected N-alkylated amino acids of the formula I



where

R¹ is a conventional protective group for peptide synthesis, R¹ is the side chain of a proteinogenic amino acid or a functional derivative thereof, R² is hydrogen, C₁₋₆-alkyl, C₂₋₆-alkenyl, C₂₋₆-alkynyl or unsubstituted or C₁₋₄-alkyl-substituted phenyl or benzyl, and R³ is methyl or ethyl,

which comprises adding a compound of the formula II:



where R¹, R² and R³ have the abovementioned meanings, to a solution of sodium or potassium tert-butanolate in a non-protic organic solvent and subsequently adding dimethyl or diethyl sulfate.

5,587,507

SYNTHESIS OF TYROSINE DERIVED DIPHENOL MONOMERS

Joachim B. Kohn, Highland Park, and Kimberly A. Hooper, Long Valley, both of N.J., assignors to Rutgers, The State University, Piscataway, N.J.


Filed Mar. 31, 1995, Ser. No. 414,339

Int. Cl.⁶ C07C 229/28; 229/34

U.S. Cl. 560—40


18 Claims

1. A method for preparing diphenol compounds having the formula:




wherein R₁ is —CH=CH— or —(CH₂)_n—, in which n is zero or an integer from one to eight; and R₂ is selected from the group consisting of straight and branched alkyl and alkylaryl groups containing up to 18 carbon atoms; which method comprises the steps of:

coupling a hydroxyphenyl carboxylic acid having the formula:



with a L-tyrosine ester having the formula:



in a water-miscible organic reaction solvent containing a carbodiimide capable of forming a water-soluble urea by-product to form a diphenol reaction product;

combining the reaction mixture with an amount of water effective to precipitate the diphenol as a water-immiscible organic phase, so that a water-immiscible organic phase is formed containing the diphenol reaction product and a water-miscible phase is formed containing predominately reaction side-products and contaminants.

5,587,508

PROCESS FOR PRODUCING 2,6-NAPHTHALENEDICARBOXYLIC ACID AND ESTER THEREOF

Hiroshi Machida, Okayama-ken, Japan, assignor to Mitsubishi Gas Chemical Company, Inc., Tokyo, Japan

Filed Jan. 3, 1996, Ser. No. 580,974

Claims priority, application Japan, Jan. 11, 1995, 7-002708

Int. Cl.⁶ C07C 67/00; 51/215

U.S. Cl. 560—77

4 Claims

1. A process for producing 2,6-naphthalenedicarboxylic acid, which comprises oxidizing a 2,6-dialkyl-naphthalene with a gas containing molecular oxygen in a solvent containing a lower aliphatic carboxylic acid in the presence of a catalyst comprising heavy metal compounds and a bromine compound, wherein an ester mixture containing dimethyl 2,6-naphthalenedicarboxylate is added to the oxidation reaction.

5,587,509

CAGED CARBOXYL COMPOUNDS AND USE THEREOF

George P. Hess, Ithaca; Barry K. Carpenter, Slaterville Springs, both of N.Y.; Doraiswamy Ramesh, San Diego, Calif., and Raymond Wieboldt, Freeville, N.Y., assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Division of Ser. No. 159,190, Nov. 30, 1993, Pat. No. 5,430,175. This application Mar. 8, 1995, Ser. No. 400,750


Int. Cl.⁶ C07C 69/00

U.S. Cl. 560—130


8 Claims

1. A method of releasing a caged carboxylic acid to a receptor having receptor channels comprising:

- preparing a caged carboxylic acid with a cage group comprising 2-alkoxy-5-nitrophenyl wherein the alkoxy group contains about 1–4 carbon atoms;
- photolyzing the protecting group with light to release the caged carboxylic acid; and
- contacting a receptor with the released carboxylic acid.



wherein R¹⁰ and R¹¹ may be the same or different and each represent a hydrogen atom, an amino group, an acetylamino group, or —SO₃M (in which M represents a hydrogen atom or an alkaline metal atom), with ruthenium as a catalyst, in the presence of a tertiary amine represented by the general formula (VI):



(VI)

5,587,510

(S)-2-ARALKYL-3-CHLOROPROPIONIC ACID AND PROCESS FOR THE PREPARATION THEREOF

Masao Konno, and Yoshifumi Yuasa, both of Kanagawa, Japan, assignors to Takasago International Corporation, Tokyo, Japan

Filed May 23, 1995, Ser. No. 448,310


Claims priority, application Japan, May 25, 1994, 6-133924

Int. Cl.⁶ C07C 53/34


U.S. Cl. 562—496

5 Claims


1. A process for the preparation of a (S)-2-aralkyl-3-chloropropionic acid represented by the general formula




wherein R¹ represents a hydrogen atom or a lower alkyl group, which comprises asymmetrically hydrogenating a (Z)-2-aralkylidene-3-chloropropionic acid represented by the general formula (II):



wherein R¹ is as defined above with a complex of a bidentate phosphine represented by the general formula (III):



wherein R², R³, R⁴ and R⁵ may be the same or different and each represent a phenyl group, a cyclohexyl group, a cyclopentyl group, or a substituted phenyl group substituted with a lower alkyl group, a lower alkoxy group or a halogen atom; and A is represented by the general formula (IV) or (V):



(IV)

wherein R⁶ and R⁹ each represent a hydrogen atom; and R⁷ and R⁸ each represent a methyl group; or R⁶ forms a tetramethylene group with R⁷, and R⁸ forms another tetramethylene group with R⁹:

5,587,511

PROCESS FOR OBTAINING ADIPIC ACID

Herbert Salzburg, Leichlingen; Georg Steinhoff, Krefeld; Andreas Gosch, Bochum, and Gerd Hufen, Duisburg, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Filed Nov. 13, 1995, Ser. No. 556,572

Claims priority, application Germany, Nov. 18, 1994, 44 41 175.8

Int. Cl.⁶ C07C 51/00

U.S. Cl. 562—513

4 Claims

1. A process for obtaining adipic acid from the aqueous nitric acid mother liquor that arise during industrial adipic acid production, said mother liquor containing about 2 to about 8 wt. % of succinic acid, about 4 to about 10 wt. % of glutaric acid, and about 2 to about 25 wt. % of adipic acid and an HNO₃ concentration of 40 to 60 wt. % (relative to the aqueous nitric acid without including said succinic, glutaric, and adipic acids), comprising

- removing nitric acid from the aqueous mother liquor by evaporation to a concentrate having a residual content of at most 2.5 wt. % of HNO₃, relative to the weight of the evaporation residue,
- mixing the concentrate obtained according to step (i) with water or aqueous nitric acid having an HNO₃ content of at most 10 wt. % in a quantity corresponding to a weight ratio of solid to liquid of 1:2.1 to 1:1.2,
- allowing the water added in step (ii) or the nitric acid added in step (ii) to act upon the concentrate for a period of at least 10 minutes at 20° to 80° C., optionally with continuous mixing and optionally with at least partial dissolution of the concentrate, and
- separating adipic acid as crystals from the liquid phase of step (iii), said crystals of adipic acid being formed either (1) during step (iii) when temperatures in step (iii) are no more than about 35° C. or (2) after step (iii) when temperatures in step (iii) are greater than about 35° C. by cooling the mixture from step (iii) to 10° to 35° C.

5,587,512

PROCESS FOR OBTAINING [S,S]-ETHYLENEDIAMINE-N,N'-DISUCCINIC ACID FROM A SALT SOLUTION OF SUCH ACID AND L-ASPARTIC ACID

Ronny W. Lin, Baton Rouge; Eldon E. Atkinson, Jr., Greenwell Springs, and Donald E. Balhoff, Baton Rouge, all of La., assignors to Albemarle Corporation, Richmond, Va.

Filed Jul. 11, 1994, Ser. No. 272,457

Int. Cl.⁶ C07C 229/00

U.S. Cl. 562—565

12 Claims

1. A method for obtaining [S,S] ethylenediamine-N,N'-disuccinic acid from an aqueous solution containing [S,S] ethylenediamine-N,N'-disuccinic acid salt and L-aspartic acid salt by co-feeding, to a volume of water, (1) the aqueous solution and (2) an aqueous mineral acid having a dissociation constant within the range of from about 1.0×10^{-3} to about 1.0×10^{-10} , wherein the feed rates of the aqueous solution and the aqueous mineral acid are controlled so that the volume of water has a pH within the range of from about 2 to about 6.5 at least substantially throughout the co-feed period.

5,587,513

POLYETHER-SUBSTITUTED IMIDE COMPOUNDS AND THEIR USE

Klaus Pohmer; Rainer Weber; Cornelia Dörzbach-Lange; Reinhard Halda, and Hans-Heinrich Moretto, all of Bayer AG, D 51368 Leverkusen, Bayerwerk, Germany

Continuation-in-part of Ser. No. 150,722, Nov. 12, 1993, Pat. No. 5,414,120. This application Jan. 20, 1995, Ser. No. 375,647


Claims priority, application Germany, Nov. 27, 1992, 42 40 008.2

Int. Cl.⁶ C07C 311/01

U.S. Cl. 564—84

6 Claims

1. Imide compounds containing at least one of fluoroalkyl and fluoroaryl groups, which compounds are of the general formula (I):




in which


R_F is a linear or branched fluoroalkyl residue with 1 to 18 carbon atoms, a fluoroaryl residue with 6 to 12 carbon atoms, a mixed fluoroalkyl residue with 7 to 18 carbon atoms or a fluorinated mono or polyether with 2 to 18 carbon atoms.

R is (i) a linear or branched alkyl residue with 1 to 24 carbon atoms, an aryl residue with 6 to 12 carbon atoms or a mixed alkylaryl residue with 7 to 24 carbon atoms, wherein the carbon chain may also be interrupted by oxygen, nitrogen or sulphur atoms, or (ii) a further residue R_F as defined above, wherein the two R_F residues may be the same or different.

each of Y_1 and Y_2 represent a



or Y_1 represents a $>C=O$ group and Y_2 represents a



m is an integer from 0 to 6,

n is an integer from 0 to 6 and

PE is a polyether chain consisting of 5 to 50 ethylene oxide units or 5 to 50 propylene oxide units or a mixture of 5 to 50 ethylene oxide and propylene oxide units and

R_H is a hydrogen atom or a linear or branched alkyl residue with 1 to 10 carbon atoms.

5,587,514

DIASTEREOSELECTIVE SYNTHESIS OF HYDROXYETHYLENE DIPEPTIDE ISOSTERES

Dennis C. Liotta, McDonough, and Bharat R. Lagu, Atlanta, both of Ga., assignors to Emory University, Atlanta, Ga.

Filed Nov. 8, 1993, Ser. No. 148,990

Int. Cl.⁶ C07C 231/18

U.S. Cl. 564—134

21 Claims

1. A process for the preparation of a (4S,5S)-hydroxyethylene dipeptide isostere comprising the step of reacting the enolate of α -N,N-di(protected)amino methyl ketone with a compound selected from the group consisting of α -(leaving group)-acetate and α -(leaving group)-acetamide, wherein the amino protecting groups are capable of controlling the facial selectivity of reaction of the enolate.

5,587,515

METHOD OF MANUFACTURING N-MONOSUBSTITUTED (METH)ACRYLAMIDES

Yuulchi Takao, and Hidetoshi Oogami, both of Yatsushiro, Japan, assignors to Kohjin Co., Ltd., Tokyo, Japan

PCT No. PCT/JP93/01511, § 371 Date Jul. 22, 1994, § 102(e) Date Jul. 22, 1994, PCT Pub. No. WO94/08946, PCT Pub. Date Apr. 28, 1994

PCT Filed Oct. 20, 1993, Ser. No. 256,012


Claims priority, application Japan, Oct. 21, 1992, 4-305860

Int. Cl.⁶ C07C 231/02

U.S. Cl. 564—135

7 Claims


1. A method of manufacturing N-monosubstituted (meth)acrylamide represented by formula (I):



in which R is a hydrogen atom or methyl and Q is an alkyl having 1–12 carbons, a dimethylaminoalkyl having 1–5 carbons or a hydroxyalkyl having 1–3 carbons, characterized in that (1) (meth)acrylate represented by formula (II):




in which R is a hydrogen atom or methyl and R' is a lower alkyl, is made to react with dialkylamine represented by formula (III):



in which R^1 and R^2 are lower alkyls;

(2) the resulting beta-dialkylamino(1-methyl)propionate represented by formula (IV):




in which R is a hydrogen atom or methyl; R' is a lower alkyl; and R^1 and R^2 are lower alkyls, is made to react, in the presence of an alkali metal alkoxide, with a primary amine represented by formula (V):



in which Q is an alkyl having 1–12 carbons, a dimethylaminoalkyl having 1–5 carbons or a hydroxyalkyl having 1–3 carbons; and

(3) the resulting N-monosubstituted beta-dialkylamino(1-methyl)propionamide represented by formula (VI):



in which R is a hydrogen atom or methyl; R^1 and R^2 are lower alkyls; and Q is an alkyl having 1–12 carbons, a dimethylaminoalkyl having 1–5 carbons or a hydroxyalkyl having 1–3 carbons, is subjected to thermal decomposition.

5,587,516

ELECTROPHOTOGRAPHIC PHOTOCONDUCTOR COMPRISING PYRENYLAMINE DERIVATIVE, THE PYRENYLAMINE DERIVATIVE, INTERMEDIATE FOR PREPARATION THEREOF, AND METHOD FOR PREPARING THE PYRENYLAMINE DERIVATIVE AND THE INTERMEDIATE

Chiaki Tanaka, Shizuoka-ken; Masaomi Sasaki, Susono; Tamotsu Aruga, Mishima; Tomoyuki Shimada, Shizuoka-ken, and Hiroshi Adachi, Numazu, all of Japan, assignors to Ricoh Company, Ltd., Tokyo, Japan

Division of Ser. No. 427,124, Apr. 24, 1995, which is a division of Ser. No. 260,920, Jun. 15, 1994, Pat. No. 5,459,275, which is a continuation-in-part of Ser. No. 77,444, Jun. 17, 1993, abandoned, which is a continuation-in-part of Ser. No. 996,080, Dec. 23, 1992, Pat. No. 5,344,985. This application Jun. 5, 1995, Ser. No. 463,739


Claims priority, application Japan, Dec. 28, 1991, 3-360363; Apr. 15, 1992, 4-121326; Jun. 8, 1992, 4-173818; Jun. 17, 1992, 4-183142; Jul. 17, 1992, 4-213528; Jul. 17, 1992, 4-213529; Aug. 10, 1992, 4-234323; Dec. 3, 1992, 4-350440; Jun. 15, 1993, 5-168513

Int. Cl.⁶ C07C 209/10

U.S. Cl. 564—405

1 Claim

1. A method of preparing a pyrenylamine derivative of formula (Ia) comprising the step of allowing a secondary amine compound of formula (IV) to react with a pyrene compound of formula (V) in accordance with the following reaction scheme:



5,587,517

PROCESS FOR THE PREPARATION OF CHLOROPHENYLPHOSPHANES

Guido Scholz, Köln, Germany, assignor to Hoechst Aktiengesellschaft, Frankfurt am Main, Germany

Continuation-in-part of Ser. No. 147,331, Nov. 3, 1993, abandoned. This application Nov. 1, 1994, Ser. No. 332,909

Claims priority, application Germany, Nov. 17, 1992, 42 38 711.6

Int. Cl.⁶ C07F 9/52

U.S. Cl. 568—16

5 Claims

1. A process for the preparation of chlorophenylphosphanes of the formula



in which n is 1 or 2, which comprises introducing liquid triphenylphosphane and gaseous phosphorus trichloride in a molar ratio of 1:(3 to 12) at the upper end of a vertically arranged, elongated reaction zone having temperatures of 350° to 650° C. in the reaction zone, transferring the reaction product discharged at the lower end of the reaction zone to a residence zone charged with phosphorus pentachloride, removing excess phosphorus trichloride from the reaction product, via a subsequent fractionation zone, by heating the residence zone with the resultant formation of a PCl_3 -depleted reaction product, and separating the substances contained in the PCl_3 -depleted reaction product by fractionated rectification under reduced pressure.

VOL
11 93

ISS
4


DE
24

1996

UMI

ELECTRICAL


5,587,518
ACCELEROMETER WITH A COMBINED SELF-TEST
AND GROUND ELECTRODE
Paul E. Stevenson, Colorado Springs, Colo.; Craig H. Stephan,
Ann Arbor; Amer M. Samman, Dearborn, both of Mich.,
and Leland J. Spangler, Manitou Springs, Colo., assignors to
Ford Motor Company, Dearborn, Mich.
Filed Dec. 23, 1994, Ser. No. 363,767
Int. Cl.⁶ G01P 21/00; 15/125
U.S. Cl. 73—1 D 9 Claims



1. A micro-machined accelerometer, operable in a first mode to detect an acceleration force, and in a second mode to test the operability of the accelerometer, comprising:
a substrate;
a moveable plate held at a fixed electrical potential and substantially parallel to and above said substrate, comprising:
an aperture,
a pedestal positioned within said aperture, and connected to said substrate; and
means for connecting said pedestal to at least one edge of said aperture, to allow said moveable plate to rotate, relative to said substrate, about a flexure axis, in the presence of a force normal to said substrate;
a first electrode formed upon said substrate which receives an AC voltage during said first mode and said second mode;
a second electrode formed upon said substrate at a position opposite of said flexure axis from said first electrode, said second electrode receiving a voltage substantially similar to said AC voltage during said first and said second modes; and
a third electrode formed upon said substrate to surround said aperture and extend on at least two opposing sides around said second electrode, said third electrode having an electrical potential substantially equal to said fixed electrical potential of said substrate during said first mode, and at a different electrical potential during said second mode to perform a self-test of the accelerometer.


5,587,519
PROCESS AND DEVICE FOR SUPPLYING GAS TO AN
ANALYZER OF TRACES OF IMPURITIES IN A GAS
Catherine Ronge, Paris; Alain Mail, Draveil, and Yves Marot,
Buc, all of France, assignors to L'Air Liquide, Societe
Anonyme pour l'Etude et l'Exploitation des Procédés
Georges Claude, Paris, France
Filed Jan. 9, 1995, Ser. No. 370,294
Claims priority, application France, Jan. 7, 1994, 94 00120
Int. Cl.⁶ G01N 33/00 7 Claims

1. A process for supplying a gas to an analyzer for measuring traces of impurities in the gas comprising supplying said analyzer with
(i) a gas to be analyzed;
(ii) a pure gas; and
(iii) a standardizing gas obtained by dilution of one or more impurities in said pure gas as follows:
(A) dividing a flow of pure gas into a set of at least first and second bypass lines, arranged in parallel, each of said bypass lines having an entry including a calibrated restric-



- tion, the flow rate of pure gas fed into said set of bypass lines being regulated by a flow regulator placed upstream of the set,
(B) charging the pure gas of the first bypass line with a predetermined quantity of at least one impurity to obtain, after dilution with the pure gas of the second bypass line, a flow of the standardizing gas, which is directed from an exit of said set of bypass lines towards the analyzer along a feed line, wherein the gas to be analyzed, the pure gas, and the standardizing gas flow continuously.

5,587,520
THERMAL CONDUCTIVITY DETECTOR
Robert P. Rhodes, Lincoln University, Pa., assignor to Hewlett-Packard Company, Palo Alto, Calif.
Filed Sep. 29, 1995, Ser. No. 537,182
Int. Cl.⁶ G01N 25/18 7 Claims



1. A thermal conductivity detector for detecting the thermal conductivity of a sample fluid, comprising:
a cavity wall defining a cavity for receiving a quantity of the sample fluid, said cavity wall having a cavity wall temperature;
a sensor located in said cavity and connected as a first element in a bridge circuit configuration, said sensor having a sensor resistance which is dependent on a temperature of said sensor;
a selectable resistor having a selectable resistance in response to a resistor control signal, the selectable resistor being connected in said bridge circuit configuration as a second element wherein the resistance of said selectable resistor controls the temperature of said sensor;
signal providing means, connected to said sensor, for providing an output signal which is related to a change in the power delivered to said sensor and thereby representative of the thermal conductivity of the sample fluid;
heating means for providing a temperature sense signal representative of the cavity wall temperature and for controlling the cavity wall temperature in response to a heating control signal; and
a controller connected to said selectable resistor and said heating means for:
a. receiving said temperature sense signal,
b. determining a desired cavity wall temperature, a desired sensor temperature, and a respective temperature differential therebetween;

c. and in response, providing said heating control signal to effect said desired cavity wall temperature and providing the resistor control signal to effect the selected resistance of the selectable resistor so as to establish the desired temperature of the sensor;
whereby the desired temperature differential may be established between the temperature of the sensor and the temperature of the cavity wall.

5,587,521

PIPE TESTING SYSTEM

Douglas Lanasa, P.O. Box 753, Channelview, Tex. 77530
Continuation of Ser. No. 188,023, Jan. 28, 1994, Pat. No. 5,481,902. This application Sep. 5, 1995, Ser. No. 523,450
Int. Cl.⁶ G01M 3/28

U.S. Cl. 73—49.1

9 Claims



1. A pipe testing system, comprising:
a mobile platform adapted to be transported to a remote location;
a container means for retaining a discrete quantity of a test fluid, said container means being supported by the platform;
a pair of test plugs for engaging interior surfaces of the respective opposite ends of a pipe being tested, said plugs being fluidly connected to the container means;
a means being carried by the platform for moving the pipe, said means comprising a first conveyor means for delivering the pipe to a pre-test station, a lifting arm means for transporting the pipe to a testing cradle and to a holding station, and a second conveyor means for removing the pipe from a holding station;
a means for inserting at least a portion of the test plugs into a fitted engagement within the interior surfaces of the pipe ends;
a means for delivering the test fluid into the pipe;
a means mounted on the platform for applying pressure to the interior of the pipe; and
an independent power source.

5,587,522


MULTIPLE-PART AND/OR SUPPORTED GAS-CONTAINING VESSEL TO ESTABLISH DESIRED HEAT FLUX

Theodore W. Selby, 4402 Arbor Dr., Midland, Mich. 48640
Filed Dec. 26, 1995, Ser. No. 577,969
Int. Cl.⁶ F25D 23/06; 1/00; B65D 81/38

U.S. Cl. 73—54.28

22 Claims

1. A heat-insulating vessel comprising a sealable, outer housing and a sample compartment generally enclosed therein such that a hollow portion between walls of at least a part of the housing and sample compartment is present which can contain a predetermined quantity of a gas selected to have a known, predetermined value for a heat flux and which is supported within the housing by at least one peak in the vessel and/or by an added, thermally-insulative insert, said vessel being useful in heat transmission regulation therethrough between a sample, which can be provided within the sample compartment, and an external bath environment at a temperature T, said hollow portion with its predeterminable quantity of a gas therein able to provide for a desired heat flux therethrough towards or away from the sample depending upon factors including those associated with the predeterminable quantity of a gas therein, the temperature T of the external bath



environment, and temperature of the sample within the sample compartment.


5,587,523

ATOMIC FORCE MICROSCOPE EMPLOYING BEAM TRACKING

Pan S. Jung, Gilbert, and Daphna R. Yaniv, Scottsdale, both of Ariz., assignors to Molecular Imaging Corporation
Continuation of Ser. No. 190,948, Feb. 3, 1994, Pat. No. 5,440,920. This application Feb. 15, 1995, Ser. No. 427,353
Int. Cl.⁶ G01B 5/28

U.S. Cl. 73—105

37 Claims



1. A scanning force microscope for examining surface properties of a sample surface, said microscope comprising:
a frame;
a sample stage;
a scanner element having a scanner end capable of motion relative to said frame in response to signals applied to said scanner element;
a cantilever having a reflective back surface, a first cantilever end and a second cantilever end, said first cantilever end having a sharp probe tip extending therefrom toward said sample stage, said second cantilever end coupled to said scanner;
at least one beam tracking element held in a fixed relationship to a portion of said scanner element;
a source of a collimated light beam, said source arranged to project said collimated light beam to said at least one beam tracking element and from said at least one beam tracking element to said reflective back surface of said cantilever forming a reflected light beam emanating from said reflective back surface; and
a position sensitive detector positioned to intercept said reflected light beam and produce a signal responsive to angular movement of said reflected light beam.


5,587,524

MISFIRE DETECTION ASSEMBLY

Richard J. Hampo, Livonia; Kenneth A. Marko, Ann Arbor, and Bruce D. Bryant, Royal Oak, all of Mich., assignors to Ford Motor Company, Dearborn, Mich.
Filed May 3, 1995, Ser. No. 433,186
Int. Cl.⁶ G01M 15/00; G06F 15/20

U.S. Cl. 73—116

7 Claims



1. A method for creating an optimal filter to separate data collected from an internal combustion engine from a plurality of usable filters, the method comprising the steps of:
collecting data from the internal combustion engine;
operating each of the plurality of usable filters with the data collected to separate the data into a proper firing category and a misfire category;
separating the data into a false positive category and a false negative category;
modifying a portion of the plurality of usable filters to create a new population of usable filters;
testing each of the new population of usable filters to identify the optimal filter to be used on-board a motor vehicle to accurately detect misfire events created by the internal combustion engine;
weighting the data in the false positive category greater than the data in the false negative category; and
measuring the accuracy of each of the new population of usable filters based on the weighted false positive category and the weighted false negative category.

5,587,525


FORMATION FLUID FLOW RATE DETERMINATION METHOD AND APPARATUS FOR ELECTRIC WIRELINE FORMATION TESTING TOOLS

Than Shwe, and John M. Michaels, both of Houston, Tex., assignors to Western Atlas International, Inc., Houston, Tex.
Continuation-in-part of Ser. No. 48,814, Jun. 16, 1993, Pat. No. 5,473,939, which is a continuation-in-part of Ser. No. 903,088, Jun. 19, 1992, abandoned. This application Apr. 27, 1995, Ser. No. 429,722
Int. Cl.⁶ E21B 47/06

U.S. Cl. 73—15.52

7 Claims

1. An apparatus for withdrawing a fluid sample from an earth formation penetrated by a wellbore, comprising:
an elongated housing adapted to traverse said wellbore;
a probe disposed within said housing and adapted to be selectively placed in contact with said earth formation;
a pumping chamber disposed within said housing and selectively placed in hydraulic communication with said probe, said pumping chamber having a selectively controllable volume;
a pressure transducer disposed within said housing and in hydraulic communication with said probe;
means for selectively increasing and selectively decreasing said volume of said pumping chamber;
means for measuring said volume of said pumping chamber; and
means for recording measurements of said volume of said pumping chamber and pressure measurements made by said



transducer with respect to time so that a measurement of a volume of fluid withdrawn through said probe into said pumping chamber can be determined exclusive of an expansion volume of fluid from said wellbore disposed within said probe prior to initiation of withdrawal of said fluid sample.


5,587,526

PROOF MASS SUPPORT AND SENSING SYSTEM

John M. Lumley, Cambridge, United Kingdom, and Ho J. Paik, College Park, Md., assignors to Oxford Instruments (UK) Limited, Oxon, England
Filed Mar. 24, 1995, Ser. No. 409,300
Claims priority, application United Kingdom, Mar. 30, 1994, 9406347; Sep. 28, 1994, 9419649
Int. Cl.⁶ G01V 7/02

U.S. Cl. 73—382 G

25 Claims



1. A proof mass support system comprising a pair of alignment coils for controlling the rest position of an elongate proof mass, wherein said alignment coils are constructed to provide a levitation force when they carry electric currents which varies along the length of said proof mass; and means for tuning the relative strength of said electric currents in said alignment coils to cause said proof mass to take up a predetermined orientation with respect to one or more degrees of freedom defined by said alignment coils.

5,587,527

HANDHELD DENSITY METER

Neal T. Radford, 2119A Lakepark Dr., Smyrna, Ga. 30080, and Roy J. Waddle, 2262K Northwest Pkwy., Marietta, Ga. 30067

Continuation of Ser. No. 59,104, May 10, 1993, abandoned.
This application Jun. 6, 1995, Ser. No. 468,230
Int. Cl.⁶ G01N 9/28

U.S. Cl. 73—439

14 Claims

1. In a density meter comprising a gas pump; a tube assembly including an elongated first bubble tube defining a first tube interior into which the gas pump discharges and an elongated second bubble tube defining a second tube interior into which the gas pump also discharges, wherein the first bubble tube includes a first outlet and the second bubble tube includes a second outlet, and



cable toward and away from said wheel; a position detecting means connected to the sensing means for detecting the position thereof; a storage means connected to the position detecting means for storing position data determining actual balancing positions on the wheel; an electronic evaluation means connected to a measuring arrangement for measuring unbalance means connected to a measuring arrangement for measuring unbalance and to said storage means, for determining the balancing position and the magnitude of a balancing weight to be fixed to the wheel; a comparison means connected to said storage means and said position detecting means; a member operatively connected to said sensing means and which is movable therewith when said sensing means is displaced; and a clamping device adapted to at least partially hold said member in response to receipt of a clamping signal from said comparison means in a retrieval mode upon the attainment of a position of the sensing means which is determined by a stored balancing position.

5,587,529

ANGULAR RATE DETECTOR

Yutaka Iguchi, Chita-gun; Kazuo Sato, Toyota; Toshihiro Kobayashi, and Masayuki Sato, both of Nagoya, all of Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya, Japan


Filed Jun. 5, 1995, Ser. No. 461,743

Claims priority, application Japan, Jun. 3, 1994, 6-122229; Jun. 14, 1994, 6-132048; Sep. 28, 1994, 6-232674

Int. Cl.⁶ G01P 9/04

U.S. Cl. 73-504.13

7 Claims



1. An angular rate detector comprising: an oscillator including a first terminal to which a drive voltage is applied, a second terminal where a signal occurs having a given phase displacement with respect to a signal appearing at the first terminal during a resonance of the oscillator, and a third terminal where a signal occurs having a phase which changes in accordance with an angular rate; means for applying an alternating signal which corresponds to the drive voltage applied to the first terminal in accordance with the signal at the second terminal; frequency multiplier means responsive to a signal which corresponds to the oscillation frequency of the oscillator to produce a clock pulse having a frequency higher than the oscillation frequency; means for producing a phase difference pulse signal having a duty cycle which changes in accordance with a phase difference between the signal occurring at the third terminal of the oscillator and either the signal applied to the first terminal or the signal occurring at the second terminal;


5,587,528
APPARATUS AND METHOD FOR CORRECTING UNBALANCE ON A MOTOR VEHICLE WHEEL
Karl Rothamel, Seeheim-Jugenheim; Lorenz Lenhardt, Griesheim, and Gottfried Kühn, Weiterstadt, all of Germany, assignors to Hofmann Werkstatt-Technik GmbH, Pfungstadt, Germany

Filed May 26, 1995, Ser. No. 450,500
Claims priority, application Germany, Jul. 26, 1994, 44 26 482.8

Int. Cl.⁶ G01M 1/32

U.S. Cl. 73-462

21 Claims



1. Apparatus for correcting unbalance of a motor vehicle wheel by at least one balancing weight, comprising: a sensing means for sensing a predetermined position on the wheel by being displa-

and counter means for counting the clock pulse during a time interval when the phase difference pulse signal assumes a high or a low level.

5,587,530

LOW STRESS MAGNET INTERFACE FOR A FORCE REBALANCE ACCELEROMETER


Steven A. Foote, Issaquah, and Damon R. Stoddard, Seattle, both of Wash., assignors to AlliedSignal Inc., Morristown, N.J.

Division of Ser. No. 184,527, Jan. 21, 1994, Pat. No. 5,532,665. This application Apr. 12, 1995, Ser. No. 420,916

Int. Cl.⁶ G01P 15/13; 15/08

U.S. Cl. 73-514.23

3 Claims



1. A force rebalance accelerometer, comprising: a proof mass; a mounting ring; a pair of flexures for flexibility connecting the proof mass to the mounting ring; means for returning the proof mass to a null position, said returning means including a permanent magnet having a first and a second opposing bonding surfaces and at least one excitation ring said first bonding surface of said magnet spaced adjacent to said excitation ring; and means for bonding said first bonding surface of said magnet to said excitation ring, said bonding means only bonding a predetermined portion of said first bonding surface of said magnet thereby forming a pedestal and wherein a gap exists between a remaining portion of said first bonding surface and said excitation ring.

5,587,531

SEMICONDUCTOR STRAIN GAUGE ACCELERATION SENSOR


Takahiro Kawakami; Akira Ogawa, and Etsuo Ichimura, all of Omiya, Japan, assignors to Kansei Corporation, Omiya, Japan

Filed Jul. 11, 1995, Ser. No. 501,174

Int. Cl.⁶ G01P 15/12

U.S. Cl. 73-514.12

9 Claims



1. In an acceleration sensor comprising an acceleration detecting semiconductor element for detecting acceleration in a sealed case and a liquid, with which said case is filled, for giving damping to said acceleration detecting semiconductor element, said acceleration sensor further comprising: a sealed enclosure filled with gas and mounted in said case, said sealed enclosure having deformable diaphragm portions, said diaphragm portions extending in waves outwardly from their

5,587,532

METHOD OF MEASURING CRACK PROPAGATION IN OPAQUE MATERIALS


Douglas N. Rose, Macomb County, Mich., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Jan. 12, 1995, Ser. No. 371,719

Int. Cl.⁶ G01N 29/04

U.S. Cl. 73-579

1 Claim



1. A method of testing the susceptibility of an opaque ceramic material to failure by spalling comprising the steps of: making a series of impressions using a pointed indenter at different loads in the surface of the opaque ceramic to be studied to form a sample; mounting the impressed sample on a base with the surface containing the impressions exposed; enclosing the sample within a housing and sealing the housing to the base to form a chamber, the housing having a transparent window through which radiation passes; exposing the surface of the sample with the indentations to a modulated beam of radiation in a predefined pattern about the impressions using different degrees of beam modulation to alternately heat and cool a small defined portion of the exposed surface; measuring the magnitude of the pressure waves generated by the alternate heating and cooling; analyzing the difference in the pressure wave magnitude produced by the alternate heating and cooling as a function of the modulation of the radiation beam to determine the depth and size of the subsurface radial cracks formed by the indenter within the opaque ceramic; whereby the subsurface radial crack formation is disclosed which correlates to the spalling susceptibility of the opaque ceramic.

5,587,533

SURFACE FEATURE MAPPING USING HIGH RESOLUTION C-SCAN ULTRASONOGRAPHY

John K. Schneider, Snyder, N.Y., and William E. Glenn, Ft. Lauderdale, Fla., assignors to Ultra-Scan Corporation, Amherst, N.Y.

Continuation of Ser. No. 33,800, Jan. 13, 1993, abandoned, which is a division of Ser. No. 610,429, Nov. 7, 1990, Pat. No. 5,224,174. This application Jan. 27, 1995, Ser. No. 379,004

Int. Cl.⁶ G01N 29/06; A61B 8/00

U.S. Cl. 73-614

7 Claims

1. A method for ultrasonic imaging of human or animal tissue having a surface comprising the steps of: a. rigidly supporting said surface of human or animal tissue for imaging the same over the area of an image plane; b. focusing and directing an ultrasonic beam onto said surface and in a direction always substantially perpendicular to said




image plane so as to provide a predetermined spot size at the focal point of said beam to provide high lateral resolution imaging in a plane substantially perpendicular to the direction of said beam;

- c. performing a C-mode ultrasonic scan over a fixed area of said surface utilizing said ultrasonic beam; and
- d. applying range gating to said area at a selected location from the surface to a given depth beneath said surface.

5,587,534

WALL THICKNESS AND FLOW DETECTION APPARATUS AND METHOD FOR GAS PIPELINES


Joseph D. McColskey, Broomfield; William P. Dube, Denver; Christopher M. Fortunko, Boulder; Raymond E. Schramm, Thornton; Martin C. Renken, Boulder, all of Colo.; Cecil M. Teller, II, and Glenn M. Light, both of San Antonio, Tex., assignors to The United States of America as represented by the Secretary of Commerce, Washington, D.C.

Filed Oct. 28, 1994, Ser. No. 330,592

Int. Cl.⁶ G01N 29/10

U.S. Cl. 73—623

11 Claims



1. A method for determining a pressure vessel wall thickness and detecting a flaw in the pressure vessel wall comprising the steps of: generating a high power electrical pulse with a pulser; transmitting the high power electrical pulse through a diplexer and then simultaneously to an ultrasonic transducer which is located inside the pressure vessel, and to an amplifier; transmitting an ultrasonic pulse from the ultrasonic transducer through a pressurized gas couplant and then into an inside surface of the pressure vessel; receiving through the ultrasonic transducer, the diplexer, and the amplifier a return signal from the inside surface of the pressure vessel and calculating the distance d1 from the transducer to the inside surface; receiving through the ultrasonic transducer, the diplexer, and the amplifier a return signal from an outside surface of the pressure vessel; calculating a thickness of the pressure vessel wall; detecting a flaw in the pressure vessel wall; choosing said pressure vessel from a group of gas pipelines having a gas pipeline wall and a composition of metal, plastic, and ceramic; said combination of the amplifier and the diplexer forming a circuit having a large dynamic range, a fast response, and a fast recovery; and

selecting the diplexer to comprise a means for producing a saturation threshold matched to the input voltage limits of the amplifier.

5,587,535

PRESSURE SENSOR INCLUDING A PAIR OF SLIDABLE CONTACTS BETWEEN A STRAIN GAGE AND A PRINT CIRCUIT BOARD

Keiji Sasaki, Zama, and Masayuki Koguchi, Yamato, both of Japan, assignors to Fujikoki Mfg. Co., Ltd., Tokyo, Japan


Filed Apr. 17, 1995, Ser. No. 423,147

Claims priority, application Japan, Jul. 8, 1994, 6-157160

Int. Cl.⁶ G01L 9/04; 1/22

U.S. Cl. 73—726

8 Claims



1. A pressure sensor, comprising: a pressure-sensitive coupler body having, at one end thereof, a diaphragm deflective in a first direction in response to a pressure introduced from a pressure inlet and a strain gage overlying said diaphragm for detecting deflection of said diaphragm; an intermediate body having at least one support member, said intermediate body being coupled onto said pressure-sensitive coupler body to encircle said strain gage; a signal-detective coupler body coupled onto said intermediate body in an opposed relation with said pressure-sensitive coupler body to define a closed chamber in said intermediate body, and having at least one external-connective terminal for electrical connection to the exterior of the pressure sensor; a printed board supported by said at least one support member in said closed chamber of said intermediate body and carrying electronic parts thereon; a first connector electrically connecting said printed board to said terminal of said signal-detective coupler body; and a second connector electrically connecting said strain gage and said printed board by slidable contact between at least one pair of slidable contact members which are brought into slidable contact solely from a second direction approximately orthogonal to said first direction; wherein one of said pair of slidable contact members operatively engages said strain gage.

5,587,536

DIFFERENTIAL PRESSURE SENSING DEVICE FOR PNEUMATIC CYLINDERS

John Rasmussen, 8433 South Ave., Youngstown, Ohio 44514


Filed Aug. 17, 1995, Ser. No. 516,375

Int. Cl.⁶ G01L 7/16; F01B 31/12

U.S. Cl. 73—744

4 Claims

1. A pneumatic cylinder control positioning determination system comprising, a pneumatic cylinder having a piston movable therein from a retracted position to an extended position, pressure inlet and outlet ports within said cylinder, pressure lines extend from said ports, a control valve interconnected with said pressure



ports via said pressure lines, a pressure differential sensor switch in communication with said pressure ports between said cylinder and said control valve said pressure differential sensor switch comprising pressure differential sensor, calculating a control output value from the pressure differential between said inlet ports and said outlet ports within said cylinder.

5,587,537

METHOD AND APPARATUS FOR WELD TESTING

Frederick H. G. Simmons, Fergus, Canada, assignor to Alcatel

Canada Wire Inc., North York, Canada


Filed Feb. 24, 1995, Ser. No. 393,694

Claims priority, application Canada, Mar. 15, 1994, 2119061

Int. Cl.⁶ G01L 5/04

U.S. Cl. 73—862.392

20 Claims



1. A method for producing an end-to-end weld and determining if the end-to-end weld has a desired level of quality, comprising the steps of: providing elongated objects having ends to be welded, wherein each elongated object is a conductor for an electrical cable; pressing said ends to be welded against one another and maintaining them in such pressed condition; welding said ends to produce the end-to-end weld; thereafter, applying a predetermined tension to the end-to-end weld; measuring elongation produced by the predetermined tension; and comparing said elongation to a preset value, thereby determining whether the end-to-end weld has the desired level of quality.

5,587,538

DOWNHOLE VOLATILE ORGANIC COMPOUNDS TRAP FOR IMPROVED SAMPLING OF VOLATILE ORGANIC COMPOUNDS USING CONE PENETROMETER TESTING TECHNIQUES

Wes Bratton, South Royaltown, VT, assignor to Applied Research Associates, Inc., Albuquerque, N.M.


Filed Oct. 11, 1995, Ser. No. 540,802

Int. Cl.⁶ G01N 1/16

U.S. Cl. 73—863.33

20 Claims

1. A probe for obtaining a plurality of samples of volatile organic compounds at different depths up to 300 feet, said probe comprising:



5,587,539

GRAB SAMPLER


John K. Carpenter, 12148 Dunsinane, Bridgeton, Mo. 63044

Filed Jun. 14, 1994, Ser. No. 259,391

Int. Cl.⁶ G01N 1/20

U.S. Cl. 73—863.52

20 Claims



1. A grab sampler, comprising: A substantially elongated tubular member having a first open end and a second open end; A container defining a cavity for storing a predetermined quantity of liquid, said container having an open end through which said liquid is received, and a closed end, said open end of said container is coupled to said first open end of said elongated tubular member; A pivot member attached to said elongated tubular member which causes said elongated tubular member to be motionless until said predetermined quantity of liquid is received into said container and which causes said substantially elongated tubular member to pivot in a vertical direction when said container has received a predetermined quantity of said liquid; and A cap attached to said second open end which permits said liquid to flow into said second open end and which closes said

second open end once said container has received said predetermined amount of said liquid.

5,587,540

SOIL SAMPLING DEVICE WITH LATCH ASSEMBLY HAVING A VARIABLE CIRCUMFERENTIAL SHAPE

Robert D. Meyer, 13501 Wilcher NE., Albuquerque, N.M. 87112


Continuation of Ser. No. 189,957, Feb. 1, 1994, abandoned.

This application Jun. 16, 1995, Ser. No. 491,281

Int. Cl.⁶ G01N 1/08

U.S. Cl. 73-864.44

13 Claims



1. A soil sampler, comprising:
a housing;

a rod movably mounted with respect to said housing between a first position extending beyond said housing to assist in penetrating the housing into the soil, and a second position where said rod is retracted within said housing to allow a sample to enter said housing upon advancement of said housing into the soil;

an annular groove on said rod; and
latch means having a longitudinal segment disposed generally parallel to said rod, the longitudinal segment having a transverse segment extending from the longitudinal segment, said latch means in said housing adjacent to said rod, said latch means movable between a first latch position with respect to said rod wherein said rod can be moved with respect to said housing from said rod's first position to said rod's second position, and a second latch position of said latch means with respect to said rod, wherein said transverse segment of said latch means being biased radially inward by a biasing means for extending said transverse segment of said latch means into said annular groove for holding said rod stationary with respect to said housing, whereupon a force applied to said rod, when latched in said rod's second position, is transmitted to said housing to advance said housing into the soil to collect the sample;

wherein said transverse segment of said latch means includes a first curved surface facing and surrounding said rod and conforming circumferentially to the shape of said annular groove.

5,587,541

MUSICAL INSTRUMENT STRINGS

Bruce M. McIntosh, Harrogate; Francis S. Smith, Cheltenham, and Noel A. Briscoe, Dursley, all of England, assignors to Zyex Limited, Gloucestershire, United Kingdom

Filed Oct. 10, 1995, Ser. No. 541,597


Claims priority, application Great Britain, Jul. 18, 1995, 9514688

Int. Cl.⁶ G10D 3/00

U.S. Cl. 84-297 S

11 Claims

1. A string for a musical instrument, said string comprising a thermoplastic aromatic polyetherketone and having a value of E/ρ^2 which is not greater than 5×10^3 , where E is Young's modulus of



the string material measured in N/m^2 and ρ is the density of the string material measured in kg/m^3 .

5,587,542

TUNABLE PLECTRUM


Philip Everly, 10414 Camarillo St., North Hollywood, Calif. 91602

Filed Apr. 29, 1996, Ser. No. 638,801

Int. Cl.⁶ G10D 3/16

U.S. Cl. 84-322

4 Claims



1. A tunable plectrum comprising a planar material having opposed surfaces, said opposed surfaces having an opening extending therethrough, said opening having a center, the periphery of said opening including a plurality of angularly spaced inwardly projecting finger engaging material points extending into said opening toward said center, the periphery of said opening between said material points forming pointed outwardly extending tuning openings pointing radially away from said center, and means for varying the size, shape, and number of said inwardly projecting material points and the size, shape and number of said outwardly pointing tuning openings both to increase the size of said opening to enable the musician to hold the plectrum with stability and to tune the plectrum.

5,587,543

MUSICAL INSTRUMENT

Carlos A. Da Silva Marques, Rua Vitor Brecheret, 520, Apt. 08-B, Osasco, Sao Paulo, Brazil


Filed Aug. 31, 1995, Ser. No. 521,825

Int. Cl.⁶ G10D 13/02

U.S. Cl. 84-411 M

13 Claims

1. A musical instrument, comprising a body; at least one element movable relative to said body and producing sound; and an inflatable cushion arranged so as to be in contact with said element during playing the instrument, said element being formed as a membrane and said body together with said element forming a drum, said inflatable cushion being ring-shaped and arranged in said body so that it extends along a peripheral portion of said membrane, said inflatable cushion having an axial surface abutting



against said membrane, said inflatable cushion having a radially outer ring-shaped projection clamped between said body and said membrane.

5,587,544

DRUM

Junji Fujii, and Yukimasa Okumura, both of Hamamatsu, Japan, assignors to Yamaha Corporation, Shizuoka, Japan


Filed May 17, 1995, Ser. No. 443,581

Claims priority, application Japan, Jun. 22, 1994, 6-139999; Aug. 12, 1994, 6-190427

Int. Cl.⁶ G10D 13/02

U.S. Cl. 84-411 R

7 Claims



1. A drum comprising:

a shell having open ends at both ends;

reinforcement rings provided on edges of said open ends of said shell;

batter heads stretched over outer edges of said reinforcement rings so as to enclose said open ends of said main body; and
a plurality of head supporting and stretching assemblies provided on an outer surface of said shell so as to hold said stretched batter heads at both ends of said shell, any part of each one of said supporting and stretching assemblies being between imaginary planes defined by said outer edges of said reinforcement rings.

5,587,545

MUSICAL TOY WITH SOUND PRODUCING BODY

Takashi Nakada; Keiichi Kazami, both of Saitama, and Kenji Kaneko, Chiba, all of Japan, assignors to Kabushiki Kaisha B-AI, Japan

Filed Feb. 16, 1995, Ser. No. 389,351


Claims priority, application Japan, Mar. 10, 1994, 6-067681; Sep. 20, 1994, 6-251366; Nov. 14, 1994, 6-304403

Int. Cl.⁶ A63H 3/28; 33/26; G10D 13/08; G10H 1/40

U.S. Cl. 84-600

8 Claims

1. A musical toy wherein:



(a) there are provided a toy body, a sound producing body and a control device;

(b) the toy body comprises a first permanent magnet and a swinging body swingably mounted in the vicinity of the first permanent magnet;

(c) the swinging body comprises a tapper for striking the sound producing body and an acting part for magnetically interacting with the first permanent magnet and generating a swinging force;

(d) the acting part comprises a second permanent magnet for swinging the tapper up;

(e) the acting part comprises a coil for swinging down the upswung tapper against the resistance of the second permanent magnet;

(f) the control device comprises rhythm signal generating means for generating a rhythm signal and by supplying this rhythm signal to the coil causes the swinging body to swing according to the rhythm signal; and

(g) the sound producing body is disposed in such a position that it is struck by the tapper of the swinging body when the swinging body swings according to the rhythm signal.

5,587,546

KARAOKE APPARATUS HAVING EXTENDIBLE AND FIXED LIBRARIES OF SONG DATA FILES

Hirokazu Kato, Hamamatsu, and Hiroshi Mino, Tokyo, both of Japan, assignors to Yamaha Corporation, Hamamatsu, Japan


Filed Nov. 15, 1994, Ser. No. 339,824

Claims priority, application Japan, Nov. 16, 1993, 5-309768

Int. Cl.⁶ G10H 1/26; 7/00

U.S. Cl. 84-609

4 Claims



2. A karaoke apparatus for playing a karaoke song designated by a request, comprising:

first storage means for rewriteably storing a plurality of song data files corresponding to a plurality of karaoke songs to form an extendible library which can be updated;

second storage means for permanently storing another plurality of song data files corresponding to another plurality of karaoke songs to form a fixed library which cannot be updated;

director means having a directory table which records a classification of each song data file to classify each song data file to one of the extendible library and the fixed library; retrieval means responsive to a request for addressing the directory table to check a classification of a requested song data file, and for retrieving the same selectively from one of the extendible library and the fixed library according to the classification; and tone generator means for processing the retrieved song data file to sound a desired karaoke song designated by the request.


5,587,547

MUSICAL SOUND PRODUCING DEVICE WITH PITCH CHANGE CIRCUIT FOR CHANGING ONLY PITCH VARIABLE DATA OF PITCH VARIABLE/INVARIABLE DATA

Toshiki Nakai; Mitsuyoshi Amano; Kazuhiro Miyamoto; Yoshiyuki Akiha, and Masuhiro Sato, all of Tokyo-to, Japan, assignors to Pioneer Electronic Corporation, Tokyo, Japan
Filed Jul. 11, 1994, Ser. No. 273,490
Claims priority, application Japan, Jul. 14, 1993, 5-173856
Int. Cl.⁶ G09B 15/02; G10H 7/00

U.S. Cl. 84-645

7 Claims



1. A musical sound producing device for producing musical sound from MIDI data, comprising:

- a MIDI sound source for producing musical sound from prepared MIDI data including play data for producing musical sound of plurality of tones, pitch data for designating pitch of the tones and pitch variable/invariable data indicating pitch variable tones and pitch invariable tones, said MIDI sound source producing musical sound of tones designated by the play data with pitch designated by the pitch data;
- an instruction unit for receiving a pitch change information from a user; and
- a pitch change circuit for changing the pitch data of only pitch variable tones specified by the pitch variable/invariable data in accordance with the pitch change information.

5,587,548

MUSICAL TONE SYNTHESIS SYSTEM HAVING SHORTENED EXCITATION TABLE


Julius O. Smith, III, Palo Alto, Calif., assignor to The Board of Trustees of the Leland Stanford Junior University, Palo Alto, Calif.

Continuation-in-part of Ser. No. 90,783, Jul. 13, 1993, Pat. No. 5,500,486. This application Sep. 1, 1994, Ser. No. 300,497
Int. Cl.⁶ G10H 5/02

U.S. Cl. 84-659

46 Claims

1. A tone synthesis system for synthesizing a tone produced by a vibrating element in conjunction with a resonant member to which the vibrating element is acoustically coupled, comprising:
- a closed loop including an input for receiving an excitation signal, a delay for delaying a signal circulating in the loop,



and a filter for filtering a signal circulating in the loop and an output from the closed loop for providing a synthesized tone, wherein the amount of delay in the loop corresponds to the pitch of a tone to be synthesized; excitation means for providing an excitation signal to the input, said excitation signal including components corresponding to a first partial response of said resonant member to an excitation of said vibrating element; and resonant filter means for imparting resonance to said output signal in accordance with a second partial response of said resonant member to the excitation of said vibrating element, wherein said first and second partial responses represent a total response of said resonant member to the excitation of said vibrating element.

5,587,549

ANGULAR PORTING SYSTEM AND SHOTGUN BARREL EQUIPPED THEREWITH

John D. Clouse, Batesville, Ark., assignor to Jana, Inc., Batesville, Ark.

Filed Jul. 3, 1995, Ser. No. 497,771
Int. Cl.⁶ F41A 21/36

U.S. Cl. 89-14.3

2 Claims



1. A ported shotgun barrel comprising: an elongated tubular barrel having a top and a bottom with a longitudinal axis extending substantially from a breech to a muzzle end; two rows of regularly spaced apart oblong porting orifices defined in said barrel and extending toward said breech from adjacent said muzzle end, said rows radially spaced apart from one another along said top, and wherein each of said oblong porting orifices has an axis forming an acute angle of approximately forty-five degrees with respect to said longitudinal axis, so that forces generated by escaping gases are translated into a downwardly aimed component resisting muzzle jump and a forwardly aimed component resisting recoil; wherein said axis of each oblong porting orifice in the first of said two rows angularly intersects said axis of the corresponding oblong porting orifice in the second of said two rows to form a hypothetical arrow that points towards said muzzle end; and, wherein the combined area of each of the porting orifices is approximately seventy percent of the interior cross-sectional area of the shotgun barrel.

5,587,550

INTERNALLY TIMED, MULTI-OUTPUT IMPULSE CARTRIDGE


Kenneth E. Willis, Redwood City; William D. Fahey, Cupertino, and David S. Whang, San Jose, all of Calif., assignors to Quantic Industries, Inc., San Carlos, Calif.

Filed Mar. 23, 1995, Ser. No. 409,258
Int. Cl.⁶ F23Q 7/00

U.S. Cl. 102-217

14 Claims

1. A method for generating sequentially timed, multiple explosive output charges, comprising:



- (a) applying a single input pulse of electrical current to an input terminal;
- (b) using current from the single input pulse to actuate a first output initiator device and fire a first explosive device;
- (c) after the first output initiator device has actuated, using current from the single input pulse to charge a capacitor to a predetermined voltage level;
- (d) measuring a delay after the firing of the first output initiator device using a timing circuit responsive to the voltage level; and
- (e) after the end of the delay, discharging the capacitor through a second output initiator device to actuate the second output initiator device and fire a second explosive device.

5,587,551

DEVELOPING APPARATUS


Akihito Ikegawa, Sakai; Kouichi Aritomo, Itami; Kazuki Tsukamoto, Katano, and Michiya Yamashita, Itami, all of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 233,525, Apr. 26, 1994, abandoned, which is a division of Ser. No. 16,671, Feb. 11, 1993, Pat. No. 5,338,895, which is a continuation of Ser. No. 552,069, Jul. 13, 1990, abandoned. This application Oct. 12, 1995, Ser. No. 542,299

Claims priority, application Japan, Jul. 17, 1989, 1-185266
Int. Cl.⁶ G03G 15/00

U.S. Cl. 118-661

24 Claims



1. A developing apparatus for developing an electrostatic latent image on an electrostatic latent image carrier comprising:
- a developing member having an outer surface for retaining an electrostatically charged toner thereon and being provided rotatably in a predetermined direction; and
 - a regulating blade formed by a plate which has a fixedly disposed one end and an opposing free end, said plate being bent in the vicinity of the free end in a direction away from the developing member so as to form a bent portion, said bent portion having a first flat portion extending in a substantially tangential direction with respect to the surface of the developing member, a bent corner extending in a direction away from the developing member, and a second flat portion connected to said first flat portion through said bent corner, said bent corner having a round curvature shape and a curvature radius no greater than 0.5 mm, a length measured from the bent corner to the free end being 0.5 to 5 mm, said bent portion being located upstream of said fixedly disposed one end with reference to the direction of rotation of said developing member.


5,587,552

INFRARED ILLUMINATING COMPOSITION

David R. Dillebay, and David W. Turner, both of Marshall, Tex., assignors to Thiokol Corporation, Ogden, Utah
Filed Nov. 9, 1993, Ser. No. 150,427
Int. Cl.⁶ C06B 45/10

U.S. Cl. 149-19.5

27 Claims



1. A composition which emits infrared light upon burning comprising: an infrared emitting material selected from the group consisting of cesium nitrate, rubidium nitrate, and mixtures thereof, said infrared emitting material being present from about 10% to about 20% by weight; ammonium nitrate present from about 45% to about 65% by weight; and a fuel.

5,587,553

HIGH PERFORMANCE PRESSABLE EXPLOSIVE COMPOSITIONS

Paul C. Braithwaite, Brigham City, Utah; Gary K. Lund, Malad, Id., and Robert B. Wardle, Logan, Utah, assignors to Thiokol Corporation, Ogden, Utah
Filed Nov. 7, 1994, Ser. No. 335,097
Int. Cl.⁶ C06B 45/10

U.S. Cl. 149-19.6

20 Claims

9. A high solids pressable explosive composition comprising: a chain-extended PGN (polyglycidyl nitrate) having a weight average molecular weight greater than 10,000 determined using a polystyrene standard; and a high explosive having a concentration in the pressable explosive composition in the range from about 92 weight percent to about 96 weight percent.

5,587,554

CABLE DIRECTING DEVICE


Ralph C. Kendrick, Jr., 553 Warren Ave., Chesapeake, Va. 23320

Filed Feb. 22, 1993, Ser. No. 20,568
Int. Cl.⁶ H02G 9/00

U.S. Cl. 174-37

11 Claims

1. A cable directing device for enclosing and directing underground electrical cable between an underground shielding conduit



for the cables and an above-ground electrical apparatus of the type disposed on a preformed supporting pad having formed therein an access opening substantially enlarged in relation to the underground conduit for passage of the cables through access opening, said directing device comprising a hollow housing defining first and second cable passage openings and a cable directing passageway extending interiorly through the housing between said first and second cable passage openings, said first cable passage opening being directed upwardly and being substantially larger than said second cable passage opening, said first cable passage opening being configured to substantially conform to and be matable with the access opening in the supporting pad and said second cable passage opening being directed generally horizontally and configured to substantially conform to and be matable with the underground shielding conduit, including a mating member projecting outwardly from said housing and configured to mate with an underground shielding conduit, said first and second cable passage openings being oriented substantially perpendicularly to one another and said cable directing passageway being curved substantially ninety degrees (90°) between said first and second cable passage openings and being tapered narrowly from said first cable passage opening toward said second cable passage opening, said cable directing device including means for mounting said device to the supporting pad whereby said cable directing device may be positioned to project downwardly from the access opening in the supporting pad for directing a plurality of underground cables between the access opening in the supporting pad and the underground conduit.

5,587,555

CONDUCTOR HOLDING DEVICE

Eric R. Rinderer, Highland, Ill., assignor to B-Line Systems, Inc., Highland, Ill.


Filed Jun. 3, 1994, Ser. No. 253,507

Int. Cl.⁶ H02G 3/10

U.S. Cl. 174—49

21 Claims

1. A device adapted to be mounted on a support member for holding a conductor in a substantially fixed position extending generally parallel to the support member, said device comprising a bracket having an arm with at least one opening therein, said bracket being adapted to be mounted on said support member so that the arm extends laterally from the member at one side of the member, a clamp having a head and at least one leg projecting from the head adapted for reception in said opening in the arm, the leg of the clamp being movable in the opening in a first axial direction with respect to the leg so that the head of the clamp can be pushed closer to the arm to move the clamp to a clamping position in which the head of the clamp is in clamping engagement with the conductor disposed between the head and the arm and extending generally parallel to the support member, and retainer means for retaining the clamp in said clamping position, said retainer means comprising a structure on the arm adjacent the opening in the arm for biting into the leg of the clamp



when the clamp is pushed to its said clamping position thereby to lock the clamp in its said clamping position by inhibiting any movement of the head of the clamp away from the arm after the clamp has been moved to said clamping position, said leg being formed so that said structure can bite into the leg at any location along at least a major portion of the length of the leg, thereby enabling the clamp to tightly clamp any conductor having any thickness within a wide range of thicknesses.

5,587,556

PROTECTIVE CASING FOR END CONNECTING PART OF WIRE

Takatatsu Yamamoto; Shigehiko Kobayashi, and Tomohiro Ikeda, all of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan


Filed Dec. 16, 1994, Ser. No. 357,312

Claims priority, application Japan, Dec. 20, 1993, 5-320347

Int. Cl.⁶ H01R 4/22

U.S. Cl. 174—74 R

15 Claims



1. A protective casing for accommodating an end connecting part of a bundle of wires, comprising: a casing body forming a storage chamber therein to accommodate the end connecting part, said casing body having an opened upper portion and an opened side portion on at least one side thereof in the longitudinal direction; and a lid pivotally connected to said casing body to close said upper portion, said lid having a presser piece formed on an inner surface of said lid to press against the end connecting part when said lid is closed against said casing body; wherein said casing body has a stop member which projects inwardly from a bottom wall of said casing body and which separates the wires when the wires are accommodated in the protective casing.

5,587,557

PRINTED CIRCUIT BOARD AND LIQUID CRYSTAL DISPLAY

Mikio Kurihara, Yokohama; Satoru Nishi, Zama; Takahiro Onodera, Sagami-hara, and Kazunari Kushima, Shiga-ken, all of Japan, assignors to International Business Machines Corporation, Armonk, N.Y.


Filed Sep. 29, 1994, Ser. No. 314,992

Claims priority, application Japan, Sep. 29, 1993, 5-242879

Int. Cl.⁶ H05K 1/02

U.S. Cl. 174—266

2 Claims



1. An improved Tape Automated Bonding (TAB) structure for contacting a printed circuit board, said TAB structure comprising: a film base in which an opening is provided; wiring which is printed on said film base and extending near said opening; and long, narrow electrodes which are connected with said wiring and formed so as to traverse said opening in said film base, wherein said opening in said film base on either sides of said long, narrow electrodes is wider than at said long, narrow electrodes.

5,587,558

COORDINATE DETECTING APPARATUS HAVING ACCELERATION DETECTORS

Kenichi Matsushima, Tokyo, Japan, assignor to Seiko Instruments Inc., Japan


Filed Jan. 21, 1993, Ser. No. 7,072

Claims priority, application Japan, Jan. 24, 1992, 4-010627; May 26, 1992, 4-133921; Aug. 26, 1992, 4-227643

Int. Cl.⁶ G08C 21/00; G09G 3/02

U.S. Cl. 178—18

28 Claims



1. A coordinate input device for obtaining the spatial coordinates at the tip of a pen-type coordinate indicator, comprising: acceleration detecting means for detecting the acceleration of a body of the pen-type coordinate indicator; attitude detecting means for detecting the attitude of the body of the pen-type coordinate indicator; and coordinate operation means for determining the spatial coordinates at the tip of the coordinate indicator in accordance with outputs of the acceleration detecting means and the attitude detecting means.

5,587,559

CONTROL METHOD OF A PLURALITY OF LOCATORS AND CONTROL DEVICE OF SAME

David C. Fleck, Vancouver, Wash., and Yoichi Tsuchida, Saitama, Japan, assignors to Wacom Co., Ltd., Saitama, Japan


Filed Dec. 1, 1994, Ser. No. 352,133

Claims priority, application Japan, Nov. 18, 1994, 6-309757

Int. Cl.⁶ G08C 21/00

U.S. Cl. 178—18

10 Claims



10. A tablet interfacing device for converting coordinate information and switching information from plural tablets each of which has at least one of pointing device into any suitable forms adapted for an operating system, and supplying the converted information to this operating system, the device comprising: a conversion-table forming means for forming a conversion-table which is converted whenever the switch information from each of the whole switches assembled on the plural tablets is associated with a mouse event or keyboard input; a decision means for deciding whether the switch information on each one of the whole switches of the plural tablets is ON or OFF; and a transmit means for transmitting sequentially the coordinate data from each one of the plural tablets to the operating system in a time sharing manner when all of the switch information are OFF, or the converted information through the conversion-table as the information from the mouse event or the keyboard input to the operating system when any one of the switch information is ON.

5,587,560

PORTABLE HANDWRITTEN DATA CAPTURE DEVICE AND METHOD OF USING


John F. Crooks, Duluth, and Robert L. Protheroe, Lawrenceville, both of Ga., assignors to AT&T Global Information Solutions Company, Dayton, Ohio

Filed Apr. 10, 1995, Ser. No. 419,657

Int. Cl.⁶ G08C 21/00; G09G 3/02; G06F 17/60; G06K 5/00

U.S. Cl. 178—18

8 Claims



1. A method for operating a portable signature capture device having a digitizer, said portable handwritten capture device operating in association with a computer and a docking station, comprising the following steps: (a) determining whether the computer is transmitting a command to the portable signature capture device; (b) if step (a) is true, determining whether the command is a command to transmit data;

- (c) if step (b) is true, transmitting data to the computer;
 (d) if step (a) is not true, determining whether a coordinate is available from the digitizer to obtain data from the digitizer;
 (e) if step (d) is true, determining whether a pen is in contact with the digitizer;
 (f) if step (e) is true, determining whether a paper slip is located over the digitizer; and
 (g) if step (f) is true, storing the coordinate and repeating the process for obtaining another coordinate.

5,587,561

STETHOSCOPE SHIELD


Mahdi Budayr, 611 W. Park St., Urbana, Ill. 61801, and Jack Koff, 1086 Franklin St., Johnstown, Pa. 15905

Filed Jul. 28, 1995, Ser. No. 508,575

Int. Cl.⁶ A61B 7/02

U.S. Cl. 181—131

14 Claims



1. A shield for preventing contact between a diaphragm of a head of a stethoscope and skin of a patient, the shield comprising: a generally planar piece of material having a surface area larger than the diaphragm of the stethoscope; an annular flange disposed so as to extend generally upwardly from the planar piece of material, towards the head of the stethoscope so as to shield the head of the stethoscope from body fluids disposed on a patient's skin; and adhesive attachment means applied to the surface of the planar piece of material for removable attachment to the stethoscope at the diaphragm so as to cover the diaphragm of the stethoscope and prevent contact with the skin of a patient.

5,587,562

DIAPHRAGM FOR ELECTRO-DYNAMIC TYPE LOUSPEAKERS

Masatoshi Sato, Tendo, Japan, assignor to Tohoku Pioneer Electronic Corporation, Yamagata-ken, and Pioneer Electronic Corporation, Tokyo, both of Japan

Filed Jul. 18, 1995, Ser. No. 503,632


Claims priority, application Japan, Jul. 26, 1994, 6-174512

Int. Cl.⁶ H04R 7/00

U.S. Cl. 181—167

1 Claim

1. A diaphragm used for a loudspeaker comprising polybutylene-terephthalate-polyester-elastomer represented by a formula below:



wherein R¹ is selected from the group consisting of C₁₇H₃₄, C₁₇H₃₂, C₁₇H₃₁OCOCH₃, and Cl₂C₁₇H₂₉, R² is selected from the group consisting of C₄H₉, CH₂OCH₃, and CH₃, and n and m individually are integers.

5,587,563
AIR HANDLING STRUCTURE FOR PAN INLET AND OUTLET


Muammer Yazici, and Werner Richarz, both of Ontario, Canada, assignors to Dipti Kr. Datta, Mississauga, Canada
 Division of Ser. No. 72,590, Jun. 4, 1993, Pat. No. 5,426,268.

This application Jun. 16, 1994, Ser. No. 260,753

Int. Cl.⁶ E04F 17/04

U.S. Cl. 181—224

19 Claims



1. A sound attenuating duct unit suitable for placement at an outlet of an air supply fan unit for a building or other large structure, said duct unit comprising a housing having side walls surrounding a main airflow passageway, a circular air inlet for said passageway at one end of said housing for arrangement next to an outlet of said fan unit, at least one resonator chamber located at said air inlet adjacent said main airflow passageway, and a rectangular air outlet for said passageway at an end of the housing opposite said one end, said housing including internal walls providing a gradual transition in the transverse cross-section of said main airflow passageway from circular to rectangular, wherein said side walls contain sound absorbing material which surrounds said airflow passageway and said at least one resonator chamber is enclosed by chamber walls rigidly mounted in said housing.

5,587,564

NOISE DAMPER

Reinhard Stief, Weinheim, and Gerhard Müller-Broll, Rim-bach, both of Germany, assignors to Firma Carl Freudenberg, Weinheim, Germany


Filed Apr. 10, 1995, Ser. No. 419,687

Claims priority, application Germany, Apr. 27, 1994, 44 14 566.7

Int. Cl.⁶ E04B 1/82

U.S. Cl. 181—295

17 Claims



1. A noise damper comprising a molded part of polymer material having at least two chambers and an orifice plate covering the molded part on a side of the molded part facing a sound source, wherein the chambers are designed as resonators with at least two of the chambers having resonant frequencies that differ from one another; wherein the molded part is comprised of a closed-cell material; wherein the chambers are formed as essentially cup-shaped protrusions that open toward the sound source; wherein the orifice plate comprises at least two openings leading into each chamber;

wherein said molded part and said orifice plate are detachably joined together; and
 wherein the number and/or shape of the openings in the orifice plate leading into the chambers differs for at least two of the chambers.

5,587,565

METHOD FOR CONTROLLING ELEVATOR DOORS


Helmut Schröder-Bramloop, and Rüdiger Löt, both of Berlin, Germany, assignors to Otis Elevator Company, Farmington, Conn.

Filed Apr. 14, 1994, Ser. No. 227,435

Int. Cl.⁶ B66B 13/14

U.S. Cl. 187—316

3 Claims



1. A method of controlling an elevator door, said method comprising the steps of:
 moving an elevator door from one extreme position to the other extreme position;
 storing the phase/direction information resulting from said moving step in a memory associated with a microprocessor;
 moving said elevator door from one extreme position to the other extreme position at a constant preselected speed while counting pulses generated by an incremental encoder and simultaneously measuring the elapsed time between said extreme positions such that a reference speed is determined; and
 normalizing said number of pulses counted to represent 100% of the distance travelled by said elevator door between said extreme positions.

5,587,566

METHOD FOR ADJUSTING AN ELEVATOR DOOR

Michael Barten, and Mustapha Toutaoui, both of Berlin, Germany, assignors to Otis Elevator Company, Farmington, Conn.


Filed Apr. 29, 1994, Ser. No. 236,595

Int. Cl.⁶ B66B 13/00; 3/00

U.S. Cl. 187—316

16 Claims

1. A method for adjusting an elevator door, comprising the steps of:
 providing a service task prompt having a service task list of elevator door adjustment service tasks performed by an elevator door adjustment service program in an elevator door controller;
 selecting an elevator door adjustment service task from the service task list;
 inputting an elevator door adjustment parameter corresponding to said elevator door adjustment service task;



storing said elevator door adjustment parameter in a memory of said elevator door controller; and
 controlling said elevator door in accordance with said elevator door adjustment parameter by adapting the phase, voltage, and torque of an elevator door motor with said elevator door controller.

5,587,567

PUSH BUTTON PANEL FOR AN ELEVATOR

Ari Winter, Hyvinkää, and Johannes de Jong, Järvenpää, both of Finland, assignors to Kone Oy, Helsinki, Finland


Filed Jul. 12, 1994, Ser. No. 273,901

Claims priority, application Finland, Jul. 26, 1993, 933340

Int. Cl.⁶ B66B 1/34; H01H 1/00

U.S. Cl. 187—395

13 Claims



1. A push button panel comprising:
 a substantially rigid front plate having a front surface and a rear surface, said front surface including at least one push button area located thereon;
 a back plate located proximate to said rear surface of said front plate, said back plate including a first aperture;
 a pressure sensitive film located between said front plate and said back plate and abutting said front plate and said back plate, said pressure sensitive film including a second aperture; at least one signal conductor associated with said pressure sensitive film for conducting a signal produced by said pressure sensitive film; and
 indicator means aligned with said first aperture and said second aperture for indicating when mechanical work has been applied to the push button area, said indicator means being visible through said first aperture, said second aperture, and a portion of said front plate;
 whereby mechanical work applied to the push button area is transferred to the pressure sensitive film to produce said signal in said signal conductor.

5,587,568


INTERLOCK SWITCH

Thomas J. Lothamer; Carl A. Pontecorvo; Thomas L. Schatke, and Richard A. Osterhout, all of Fort Wayne, Ind., assignors to ITT Corporation, New York, N.Y.

Filed May 19, 1995, Ser. No. 445,085
Int. Cl.⁶ H01H 1/38; 1/306; H01R 33/06

U.S. Cl. 200—16 R

21 Claims



1. An interlock switch for use on a circuit card assembly having oppositely facing surfaces, each of said surfaces having a contact pattern defining circuit and switch functions, comprising:

contact means for engaging said contact patterns to electrically couple said circuits on said oppositely facing surfaces of said circuit card assembly;

switch body means for housing said contact means, said switch body means including slot means for solder-free coupling said switch to an edge of the circuit card assembly, said slot means enabling said switch to selectively reciprocate among a first switch position, a second switch position, and a third switch position, on the edge of the circuit card assembly to electrically couple and uncouple said circuits on said oppositely facing surfaces of said circuit card assembly in any one of said switch positions by connecting said contact patterns on said oppositely facing surfaces of said circuit card assembly with said contact means;

spring means housed within said switch body means for biasing said switch from said third switch position; and
locking projection means for preventing said switch from being easily removed from the edge of the circuit card assembly.

5,587,569

SAFETY SWITCH ASSEMBLIES

Mehdi Mohtasham, Wigan, United Kingdom, assignor to E. J. A. Engineering PLC, Wigan, United Kingdom

PCT No. PCT/GB93/01135, § 371 Date Jun. 24, 1994, § 102(e)
Date Jun. 24, 1994, PCT Pub. No. WO93/24947, PCT Pub. Date Dec. 9, 1993


PCT Filed May 28, 1993, Ser. No. 256,262

Claims priority, application United Kingdom, Jun. 2, 1992, 9211603; Nov. 12, 1992, 9223751

Int. Cl.⁶ H01H 3/16

U.S. Cl. 200—17 R

16 Claims



1. A safety switch, comprising:

a housing containing electrical contacts movable between a power supply off position and a power supply on position by rotation of an actuating cam also contained within the housing and rotatable about a predetermined axis by an actuator of a predetermined shape insertable into the housing.

at least one locking member mounted for movement in a direction substantially perpendicular to the axis of rotation of the actuating cam, the at least one locking member being resiliently urged towards a position in which the at least one locking member locks the actuating cam against rotation and consequent movement of the electrical contacts to the power supply on position.

the housing defining first and second apertures through which the actuator is insertable, the actuator when inserted into each of the apertures engages the at least one locking member and displaces the at least one locking member away from a path of movement of the actuator into a position in which the actuating cam is free to rotate relative to the housing, and engages and rotates the cam to cause movement of the electrical contacts to the power supply on position.

the at least one locking member comprising first and second slidably interengaged components, the first and second components defining interengaging surfaces configured such that displacement of the first component in a first direction causes the second component to be displaced in a second direction and displacement of the second component in the second direction causes the first component to be displaced in the first direction.

the actuator being configured such that when inserted through the first aperture the actuator pushes the first component in the first direction and when inserted through the second aperture the actuator pushes the second component in the second direction.

5,587,570

CIRCUIT BREAKER INTERLOCK UNIT TO PREVENT SINGLE PHASING


Joseph B. Kelaita, Jr., Bristol, and Edwin J. Collin, Southington, both of Conn., assignors to General Electric Company, New York, N.Y.

Filed Jul. 11, 1994, Ser. No. 272,480

Int. Cl.⁶ H01H 9/20

U.S. Cl. 200—50.01

2 Claims



1. A molded case circuit breaker handle interlock arrangement comprising:

a molded plastic case 10 and cover 12;
operating means 9 within said case for moving a pair of contacts to an open condition to interrupt circuit current upon the occurrence of an overcurrent condition within a protected electric circuit;

an indicator 18 extending through said cover and moving to an extended position providing indication of said overcurrent occurrence;

an operating handle 13 extending through said cover providing manual access for controlling said operating means and returning said contacts to a closed condition; and

interlock means 22 interacting between said operating handle and said indicator for preventing said contacts from moving to said closed condition until said indicator is returned from said extended position.

5,587,571

COMBINED-ACTION PUFFER CIRCUIT-BREAKER


Michel Perret, Bourgoin-Jallieu, France, assignor to GEC Alstom T & D SA, Paris, France

Filed Jan. 20, 1995, Ser. No. 375,983

Claims priority, application France, Jan. 25, 1994, 94 00764
Int. Cl.⁶ H01H 33/82

U.S. Cl. 218—60

4 Claims



1. A circuit-breaker comprising,

a casing filled with a dielectric gas;

a first arcing contact disposed within said casing connected to a first terminal;

a second arcing contact disposed within said casing having the same longitudinal axis as the first contact, said second arcing contact being a moving arcing contact, said moving arcing contact being connected to a second terminal and being mounted to moving axially in a fixed cylinder, said moving arcing contact cooperating with one and only one piston, said one and only one piston being a moving piston to form a compression chamber;

drive means for driving the moving piston in a first direction opposite to a second direction in which the moving arcing contact is displaced, wherein the drive means acts during a first portion of a displacement of the moving arcing contact from a closed position to an open position; and
means for constraining the moving piston to move with the moving arcing contact during a second portion of the displacement of the moving contact.

5,587,572

BATCH COUNTER

John Kirby, South Devon, England, assignor to Kirby Devon Limited, England

Continuation-in-part of Ser. No. 220,639, Mar. 31, 1994, abandoned. This application Jan. 30, 1995, Ser. No. 380,833


Claims priority, application United Kingdom, Apr. 23, 1993, 9308506; Oct. 6, 1994, 9420173

Int. Cl.⁶ B61L 1/16

U.S. Cl. 235—98 R

20 Claims

1. A batch counter for tablets and tablet-like items comprising a hopper with a wide bottom opening for passage of a supply of the items to be counted, a counter device for counting the passage of the items from the hopper, and channel means for channeling the items from the hopper to the counter device so as to pass in single file and spaced apart at the counter device, the channel means comprising a lightweight, vibratory, V-section guide channel resiliently suspended, downwardly inclined towards the counter device, beneath the bottom opening of the hopper and adjusted at critical



inclination for flow of the items, and a damming plate swingably suspended above the guide channel.


5,587,573

WIRELESS POWERING AND COMMUNICATION SYSTEM FOR COMMUNICATING DATA BETWEEN A HOST SYSTEM AND A STAND-ALONE DEVICE

William H. Owen, Los Altos Hills, and James M. Jaffe, Santa Clara, both of Calif., assignors to Xicor, Inc., Milpitas, Calif.
Continuation of Ser. No. 974,131, Nov. 10, 1992, Pat. No. 5,434,396. This application May 2, 1995, Ser. No. 432,628
Int. Cl.⁶ G06K 5/00

U.S. Cl. 235—380

10 Claims



1. A slave station formed on the substrate of an integrated-circuit chip for communicating with a master station which is coupled to said slave station by an electromagnetic coupling medium, the electromagnetic coupling medium being capable of communicating data bi-directionally between the master station and said slave station in the form of electromagnetic energy transitions, said energy transitions being coupled through said medium in the form of energy pulses, said slave station comprising:

an inductor means magnetically coupled to the coupling medium and including a segment of conductive material disposed on said substrate, a first terminal and a second terminal coupled at respective ends of said segment of conductive material, said inductor means for receiving magnetic energy transitions from the medium and for providing at said terminals an electrical signal indicative of said transitions;

means coupled to said inductor means for powering said slave station from the energy pulses coupled to said inductor means by said master station through said electromagnetic coupling medium; and

a communication means for selectively emitting at least one energy transition into said electromagnetic coupling medium in a selected time interval.

image sensing device generating outputs according to intensity distributions of light incident on said first areas and said second areas;
 a displacement detection device, responsive to said image sensing device, which detects amounts of displacement between intensity distributions of light at corresponding first areas and second areas, and which generates a plurality of displacement detection signals; and
 a focus detection device which calculates an average value of amounts corresponding to said plurality of displacement detection signals, and which produces a focus detection signal corresponding to the focus of said photo-taking lens based on the calculated average value.

5,587,580

OPTOELECTRONIC SENSOR FOR MEASURING THE INTENSITY AND THE DIRECTION OF INCIDENCE OF A LIGHT BEAM

Philippe Venier, Grenchen; Patrick Debergh, Cressier, and Xavier Arreguit, Le Mont/Lausanne, all of Switzerland, assignors to CSEM Centre Suisse d'Electronique et de Microtechnique SA, Switzerland


Filed Oct. 25, 1995, Ser. No. 548,192

Claims priority, application France, Oct. 25, 1994, 94 13046

Int. Cl.⁶ H01J 40/14; G01B 11/26

U.S. Cl. 250—206.1

11 Claims



1. An optoelectronic sensor for measuring the intensity and the direction of incidence of a light beam, the sensor being of the type comprising:

- a matrix of pixels each including a photosensitive cell, the pixels being organized substantially in a plane so as to constitute an artificial retina;
 - an optical system designed to form a light spot on the matrix of pixels; and
 - a signal processor device for processing the signals delivered by the pixels under the effect of a light beam and comprising:
 - means for determining the geometrical center of the light spot on the matrix, the position of which is a function of the direction of incidence of the light beam; and
 - means for determining the intensity of the light beam;
- wherein the means for determining the geometrical center of the light spot are constituted by:
- two arrays of connections between the pixels of the matrix, said arrays substantially constituting radii and concentric circles, the coordinates of the light spot on the matrix giving an image of the azimuth angle and of the elevation angle of the incident light beam; and
 - circuits associated with the two arrays of connections between pixels respectively for calculating the azimuth coordinate and the elevation coordinate of the incident light beam.

5,587,581

METHOD AND AN APPARATUS FOR AN AIR SAMPLE ANALYSIS

Peter C. Stroosnyder, Finksburg, Md., assignor to Environmental Technologies Group, Inc., Baltimore, Md.


Filed Jul. 31, 1995, Ser. No. 509,382

Int. Cl.⁶ B01D 59/44; H01J 49/00

U.S. Cl. 250—287

5 Claims

- 3. In an apparatus for an air sample analysis,



wherein the apparatus includes a cell comprising a reactor region, a drift region, a shutter grid separating the reactor region and the drift region, and a charge collector, wherein the sample of air containing molecules of different species is introduced to the reactor region and the molecules are polarized, thereby producing ions of positive and negative polarities to be separated, wherein electric fields applied to the cell determine a background polarity of ions to be analyzed, wherein an electric field applied to the shutter grid allows a pass to the drift region to the ions of said background polarity, wherein, once the electric fields at the cell are switched, ions of opposite to said background polarity are to be analyzed, and the electric field at the shutter grid is switched to allow the ions of said opposite to said background polarity to enter the drift region, thereby switching the background polarity to an opposite background polarity in the drift region, wherein the ions arrive to the charge collector and produce a charge spectrum to be analyzed, and wherein the switching of the electric fields at the cell may influence a charge spectrum corresponding to the ions of said opposite to said background polarity thereby upsetting results of the sample analysis, an improvement for stabilizing equilibrium conditions associated with the switching of the electric fields at the cell, comprising means for modulating a duty cycle of the electric field at the shutter grid, the duty cycle including an open time and a closed time for ions of a certain polarity, and wherein during the switching of the electric fields at the cell, the open time is extended, thereby providing additional ions of said opposite to said background polarity to enter the drift region and thereby more rapidly changing a background polarity in the drift region to the opposite to said background polarity.

5,587,582

SELF-ALIGNING LIQUID JUNCTION


Jack D. Henion, Trumansburg; Robin L. Sheppard, Canandaigua, and Timothy Wachs, Ithaca, all of N.Y., assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Filed May 19, 1995, Ser. No. 444,542

Int. Cl.⁶ B01D 59/44; H01J 49/00

U.S. Cl. 250—288

11 Claims



1. An interface for transferring analyte from a capillary electrophoresis system to a mass spectrometer, comprising:

a T fitting having a top arm and an intersecting leg;
 a support tube having a longitudinal axis, an entrance end and an exit end extending through said top arm of said T fitting to produce a continuous axial bore through said arm;
 a supply tube for supplying analyte to be analyzed located in said entrance end of said support tube;
 an outlet tube for receiving analyte from said supply tube, said outlet tube being located in said exit end of said support tube, said supply tube and said outlet tube meeting in end-to-end relationship at a junction within said support tube bore and being axially aligned by said support tube;
 a window in said support tube at the junction; and
 a make-up tube having a longitudinal axis and extending into said intersecting leg of said T fitting, said axis of said make-up tube intersecting said axis of said support tube at said window for supplying make-up fluid to said junction of said supply tube and said outlet tube.

5,587,583

THERMAL IMAGING DEVICE


Richard Chin, Torrance, and David Le Fevre, Redondo Beach, both of Calif., assignors to Hughes Electronics, Los Angeles, Calif.

Filed Sep. 6, 1995, Ser. No. 524,037

Int. Cl.⁶ H04N 5/33; H01L 27/16; G02B 26/10; G01J 1/42

U.S. Cl. 250—332

12 Claims



1. A thermal imaging device for receiving thermal infrared radiation from a scene and responsively providing a visible-light image replicating the scene, said thermal imaging device including a detector having an arrayed plurality of infrared detector elements responsive to infrared radiation, each of said plurality of detector elements providing one of a corresponding plurality of individual electrical signals each indicative of the thermal infrared radiation incident thereon, a multiplexer circuit receiving said corresponding plurality of individual electrical signals and responsively providing a serial analog image signal, said thermal imaging device comprising:

- an analog signal processor (ASP) integrated circuit (IC) for receiving said serial analog image signal and providing a processed serial analog image signal, said ASP IC including:
 - a global responsivity control circuit receiving said serial analog image signal and applying a constant global responsivity multiplier which is individual to said detector and which has been calibrated by reference to an external standard thermal source to provide a responsivity-corrected serial analog image signal;
 - a gain control circuit receiving said responsivity-corrected serial analog image signal and receiving a gain control signal, and multiplying said responsivity-corrected serial analog image signal with said gain control signal to provide a gain-corrected serial analog image signal.

5,587,584

APPARATUS FOR CHARGING A FILM ON THE INTERNAL SURFACE OF A DRUM


Richard F. Bergen, Ontario, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Mar. 28, 1996, Ser. No. 623,800

Int. Cl.⁶ H01T 19/04

U.S. Cl. 250—325

6 Claims



1. A scorotron charging apparatus adapted to apply an ion charge to a film positioned on the interior circumference of a drum, comprising:

- an insulating core member having an outer surface;
- a metallic strip coronode wrapped around said insulating core, said metallic strip coronode having a series of teeth on one edge thereof that are bent orthogonal to said outer surface of said insulating core member; and
- a conductive ring mounted surrounding said insulating core member, said conducting ring having a slit therein overlying said series of teeth of said coronode and through which ions exit to charge the film.

5,587,585

LIGHT WEIGHT GAMMA-CAMERA HEAD AND GAMMA-CAMERA ASSEMBLIES CONTAINING IT

Yosef Eisen, 24, Tel-Aviv Street, Nes Zlona 70400; Chaim Gilat, 29, Moskovitz St., Rehovot 76468, and Giora Keinan, 10, Hayarden St., Rishon-LeZion 75236, all of Israel


Continuation-in-part of Ser. No. 157,713, Nov. 24, 1993, Pat. No. 5,365,069. This application Jun. 10, 1994, Ser. No. 257,876

Claims priority, application Israel, Jun. 2, 1993, 105881

Int. Cl.⁶ G01T 1/24

U.S. Cl. 250—370.09

29 Claims



1. A gamma-camera head having a detector assembly for the detection of x-rays and gamma-radiation, in which said detector assembly comprises an array of room temperature, solid state spectroscopy grade detectors each associated with a collimator and charge sensitive preamplifier means being a member selected from

the group of preamplifiers, hybrid preamplifier/amplifier devices and application specific integrated circuits, which detectors and associated collimators and preamplification means are arranged in parallel rows extending in a first direction and suitably spaced from each other in a second direction normal to said first direction, each of said parallel rows holding a plurality of said room temperature spectroscopy grade solid state detectors, electric motor means being provided for moving said detector assembly in said second direction in a controlled fashion.

5,587,586

PARTICLE-OPTICAL APPARATUS COMPRISING AN ELECTRON SOURCE WITH A NEEDLE AND A MEMBRANE-LIKE EXTRACTION ELECTRODE
Pieter Kruit, Delft, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Oct. 3, 1995, Ser. No. 538,512

Claims priority, application European Pat. Off., Oct. 3, 1994, 94202853

Int. Cl.⁶ H01J 37/073

U.S. Cl. 250-423 F

17 Claims



1. A particle-optical apparatus, comprising an electron source (1) for producing a beam (23) of free electrons, said electron source being provided with:

- a needle-shaped conductor (20);
- a membrane-like, electrically conductive extraction-electrode (22) which is arranged opposite to and at a small distance from the tip (21) of the needle-shaped conductor (20);
- means (24) for applying an electric voltage between the needle-shaped conductor (20) and the extraction-electrode (22), characterized in that the membrane-like extraction-electrode (22) is completely closed, and
- the thickness of the extraction-electrode (22) is such that a practical fraction of electrons incident on the membrane under the influence of the electric voltage traverses the membrane to its other side with an energy loss which is negligibly small for all practical purposes.

5,587,587

ION IMPLANTING APPARATUS AND ION IMPLANTING METHOD

Hiroyuki Hashimoto, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Aug. 4, 1994, Ser. No. 284,992

Claims priority, application Japan, Aug. 5, 1993, 5-194931; Jul. 19, 1994, 6-167085


Int. Cl.⁶ H01J 37/317; 37/304

U.S. Cl. 250-492.21

47 Claims

1. An ion implanting apparatus for irradiating a material subjected to implantation with a beam of ions from an ion source thereby implanting said ions into said material, comprising:

- a magnet generating a magnetic force, positioned at a side of said material, opposite to a side thereof receiving said ion beam irradiation;
- a charge sensor measuring a charge at a surface of said material on which the ion beam is irradiated, to thereby effect feed-



5,587,588

MULTIPLE MICRO-TIPS FIELD EMISSION DEVICE
Jong-min Kim, Seoul, Rep. of Korea, assignor to Samsung Display Devices Co., Ltd., Suwon-city, Rep. of Korea


Filed Jul. 31, 1995, Ser. No. 509,603

Claims priority, application Rep. of Korea, Mar. 28, 1995, 95-6748

Int. Cl.⁶ H01L 29/06; H01J 1/46; 21/10

U.S. Cl. 257-10

16 Claims



1. A field emission device, comprising:

- a substrate;
- an adhesion layer disposed on the substrate;
- a cathode having a striped pattern disposed on the adhesion layer;
- an insulation layer having a hole therein disposed above the cathode;
- a plurality of micro-tips disposed on the cathode; and
- a gate electrode, having an aperture defined around the micro-tips, and having a stripe pattern perpendicular to the striped pattern of the cathode, disposed on the insulation layer.

5,587,589

TWO DIMENSIONAL ORGANIC LIGHT EMITTING DIODE ARRAY FOR HIGH DENSITY INFORMATION IMAGE MANIFESTATION APPARATUS

Franky So, Tempe; Song Q. Shi, Phoenix, and Thomas B. Harvey, III, Scottsdale, all of Ariz., assignors to Motorola, Schaumburg, Ill.

Filed Mar. 22, 1995, Ser. No. 408,677

Int. Cl.⁶ H01L 35/24; 51/00; 33/00

U.S. Cl. 257-40

19 Claims

1. A two dimensional organic light emitting diode array comprising:

5,587,591


SOLID STATE FLUOROSCOPIC RADIATION IMAGER WITH THIN FILM TRANSISTOR ADDRESSABLE ARRAY
Jack D. Kingsley, Grand Junction, Colo., and George E. Posin, Schenectady, N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Dec. 29, 1993, Ser. No. 174,921

Int. Cl.⁶ H01L 29/04

U.S. Cl. 257-59

23 Claims




an electrically insulative supporting substrate;

a plurality of laterally spaced apart, electrically conductive strips positioned on a surface of the supporting substrate so as to define a plurality of first electrodes;

a layer of dielectric medium positioned on an upper surface of the electrically conductive strips and defining a plurality of cavities through the layer of dielectric medium, one each of the plurality of cavities being positioned in overlying relationship to an associated first electrode of the plurality of first electrodes so as to expose a portion of an upper surface of the associated first electrode, and the layer of dielectric medium defining the plurality of cavities with each cavity defining an upper opening substantially equal in area to the exposed portion of the associated first electrode; and

an electroluminescent medium, including at least a layer of active emitter material and a layer of a low work function metal, positioned in each of the plurality of cavities on the exposed portion of the associated first electrode so as to form a light emitting diode in each of the plurality of cavities in conjunction with the associated first electrode; and

a layer of ambient stable metal sealingly positioned over the cavities so as to electrically contact the low work function metal in each of the cavities and to seal the upper openings in each of the cavities, the layer of ambient stable metal defining a plurality of laterally spaced apart, metallic strips orthogonal to the electrically conductive strips, the laterally spaced apart, metallic strips defining a second electrode for each of the light emitting diodes.



1. A solid state fluoroscopic radiation imager for imaging a subject illuminated by incident radiation having wavelengths in a predetermined range, said radiation imager comprising:

a large area photosensor array comprising a plurality of photosensors arranged in a pattern so as to have a predetermined pitch, said photosensor array further comprising an addressable thin film transistor (TFT) array comprising a plurality of low charge retention TFTs, respective ones of said TFTs being electrically coupled to respective ones of said photosensors so as to selectively address respective photosensors in said photosensor array;

each of said low charge retention TFTs having a TFT switched silicon region selected to provide low charge retention; the numerical value of the area of said switched silicon region as expressed in square microns being not substantially greater than the numerical value of said predetermined pitch as expressed in microns.

5,587,592

Patent Not Issued For This Number

5,587,590

TEST PIECE FOR X-RAY INSPECTION

Yoshihisa Matsubara, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Nov. 3, 1994, Ser. No. 335,390

Claims priority, application Japan, Nov. 15, 1993, 5-306998

Int. Cl.⁶ H01L 23/58

U.S. Cl. 257-48

5 Claims



PARTICLE DIAMETER IS
LARGER THAN WIDTH
(D > W)

1. A sample of metal silicide film for facilitating inspection of a crystal structure of said film by an X-ray diffraction process, said sample comprising one or more stripes of metal silicide, each stripe of metal silicide having a width which is smaller than a diameter of a particle of the metal silicide, wherein said one or more stripes each has a width equal to or smaller than about 1.0 μm.

5,587,593

LIGHT-EMITTING SEMICONDUCTOR DEVICE USING GROUP III NITROGEN COMPOUND

Norikatsu Koide; Shiro Yamazaki; Junichi Umezaki, and Shinya Asami, all of Aichi-ken, Japan, assignors to Toyoda Gosei Co., Ltd., Aichi-ken, and Research Development Corporation of Japan, Saitama-ken, both of Japan


Filed Apr. 19, 1995, Ser. No. 423,938

Claims priority, application Japan, Apr. 20, 1994, 6-106059


Int. Cl.⁶ H01L 33/00

U.S. Cl. 257-94

1 Claim



1. A light-emitting semiconductor device comprising:
a sapphire substrate;



said body silicon layer having a thickness of at most 1 μm ; with respect to said body silicon layer, a collector region doped for a first conductivity type, a base region doped for a second conductivity type opposite said first conductivity type, and an emitter region doped for said first conductivity type arranged vertically above one another; contacts for collector, base and emitter; said contacts respectively electrically connected to said collector region, to said base region and to this emitter region; said collector region being limited by said insulation layer at a side facing away from said base region; and said collector region having a thickness and doping density wherein the product of the square of said thickness and said doping density is less than $8 \times 10^6 \text{ cm}^{-1}$ and such that the collector region is substantially depleted of charge carriers when potentials required for a predetermined employment of the bipolar transistor are applied.

5,587,600


SERIES MOS ROM WITH TAPERED OXIDE SIDE WALLS

Ming T. Yang, Hsin-Chu, Taiwan, assignor to United Microelectronics Corporation, Hsin-Chu, Taiwan
Continuation of Ser. No. 404,117, Mar. 14, 1995, abandoned, which is a continuation of Ser. No. 120,795, Oct. 4, 1993, abandoned, which is a division of Ser. No. 941,807, Sep. 8, 1992, Pat. No. 5,264,386. This application Apr. 23, 1996, Ser. No. 636,684

Int. Cl.⁶ H01L 27/112


U.S. Cl. 257—391

8 Claims



1. An improved read-only-memory device having spaced source and drain regions in a semiconductor substrate, a plurality of very narrow, closely spaced, gate electrodes spanning the distance between the source and drain regions, and an overlying gate oxide layer, the improvement comprised of: electrodes comprising first and second alternating polycrystalline silicon lines on said gate oxide layer, said first lines having sidewalls, and being spaced from each other by approximately the width of each first line; and tapered sidewall spacer elements of insulating material along said sidewalls of each of said first lines, so that said first and second lines are separated by tapered sidewall spacer elements and said first and second lines are more closely spaced near an upper surface of said first lines.

5,587,601
SUPPORT STRUCTURE FOR A SEMICONDUCTOR PRESSURE TRANSDUCER
Anthony D. Kurtz, Teaneck, N.J., assignor to Kulite Semiconductor Products, Inc., Leonia, N.J.
Filed Jun. 5, 1995, Ser. No. 465,120
Int. Cl.⁶ H01L 29/82
U.S. Cl. 257—417
16 Claims



1. A support structure for semiconductor transducer elements in a pressure transducer assembly, comprising: a plurality of semiconductive substrates arranged in a composite structure having a top substrate layer, upon which said transducer elements are disposed, and at least one lower substrate layer, wherein a first groove is disposed in said top substrate layer creating an area of reduced thickness in said top substrate layer below said transducer elements and a second groove is disposed through said at least one lower substrate layer that communicates with said first groove, thereby creating a continuous open region through said composite structure below said area of reduced thickness, said second groove being continuous thereby defining the periphery of a boss region in said at least one lower substrate layer that is coupled to said top substrate layer.

5,587,602

Patent Not Issued For This Number

5,587,603

TWO-TRANSISTOR ZERO-POWER ELECTRICALLY-ALTERABLE NON-VOLATILE LATCH


Vikram Kowshik, Fremont, Calif., assignor to Actel Corporation, Sunnyvale, Calif.

Filed Jan. 6, 1995, Ser. No. 369,760

Int. Cl.⁶ H01L 29/788


U.S. Cl. 257—316

3 Claims



1. A two-transistor, zero-power, electrically-alterable non-volatile latch element comprising: an input node; an output node; an erase node;

a P-Channel MOS transistor having a source connected to a source of a first electrical potential, a drain connected to said output node, a control gate connected to said input node, and a floating gate capacitively coupled to said control gate; an N-Channel MOS transistor having a source connected to a source of a second electrical potential lower than said first electrical potential, a drain connected to said output node, a control gate connected to said input node, and a floating gate capacitively coupled to said control gate and common to said floating gate of said P-Channel MOS transistor; said floating gates of said P-Channel MOS transistor and said N-Channel MOS transistor capacitively coupled to said erase node via a tunnel dielectric.



having at least two ends which exit the interconnect package in at least one plane, wherein one end of at least one of the plurality of leads is for mating with a semiconductor chip.

5,587,604

CONTACTED BODY SILICON-ON-INSULATOR FIELD EFFECT TRANSISTOR


Brian J. Macbesney, Burlington, Vt.; Jack A. Mandelman, Stormville, N.Y., and Edward J. Nowak, Essex, Vt., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 22, 1994, Ser. No. 310,691

Int. Cl.⁶ H01L 27/01;27/12

U.S. Cl. 257—350

18 Claims



1. A semiconductor structure comprising: a semiconductor substrate having a buried dielectric defining lower and upper regions of said substrate, said upper region being monocrystalline; an FET comprising a gate dielectric located on a portion of said upper region of said substrate; a gate located above said gate dielectric, said gate having a first side, a second side, and a third side; and a source diffusion and a drain diffusion within said upper region, said source diffusion along said first side, said drain diffusion along said second side; and an electrical connection between said upper region and said lower region, said connection having an edge substantially co-aligned with said third side of said gate, there being no mask alignment tolerance spacing between said connection and said third side of said gate.

5,587,605

PACKAGE FOR MATING WITH A SEMICONDUCTOR DIE

Kenneth C. Ramsey, Gilbert; William J. Miller, Mesa, and William M. Strom, Chandler, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.
Division of Ser. No. 155,880, Nov. 23, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 473,833

Int. Cl.⁶ H01L 23/495;27/15;31/12

U.S. Cl. 257—666


21 Claims

1. An interconnect package, comprising at least one patterned leadframe having a plurality of leads, each of the plurality of leads

5,587,606

LEAD FRAME HAVING DEFLECTABLE AND THEREBY PRECISELY REMOVED TIE BARS

Takashi Sekiba, Murata-machi, Japan, assignor to Fujitsu Miyagi Electronics Ltd., Shibata, Japan
Division of Ser. No. 165,466, Dec. 13, 1993, Pat. No. 5,422,314. This application Feb. 16, 1995, Ser. No. 389,760
Claims priority, application Japan, Mar. 19, 1993, 5-060639
Int. Cl.⁶ H01L 21/60;23/50
U.S. Cl. 257—670
6 Claims




1. A lead frame comprising: a die pad on which a semiconductor chip is mounted; a plurality of leads each having an end which faces said die pad; and tie bars connecting said leads, wherein each of said tie bars is formed so as to project from a surface of each of said leads by an amount sufficient to break a boundary between a tie bar and a lead when the tie bar is pushed back so that the tie bar and lead are separated.

5,587,607

SEMICONDUCTOR INTEGRATED CIRCUIT DEVICE HAVING IMPROVEMENT ARRANGEMENT OF PADS

Kenichi Yasuda; Kiyohiro Furutani, and Hiroshi Miyamoto, all of Hyogo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
Filed Aug. 18, 1994, Ser. No. 292,301
Claims priority, application Japan, Sep. 9, 1993, 5-224481; Jul. 14, 1994, 6-162087
Int. Cl.⁶ H01L 23/48;23/52
U.S. Cl. 257—690
9 Claims

1. A semiconductor integrated circuit device, comprising: a package; a semiconductor chip housed in said package and selectively carrying out any of a plurality of first predetermined operations; a plurality of leads each disposed from the outside of said package to a periphery of said semiconductor chip, said plurality of leads including a first power supply lead for receiving a power supply potential and a second power supply lead positioned apart from said first power supply lead for receiving a power supply potential;



a first power supply pad disposed on said semiconductor chip and connected to said first power supply lead;
 a second power supply pad disposed on said semiconductor chip and connected to said second power supply lead;
 a first selection pad disposed in the vicinity of said first power supply lead on said semiconductor chip and having one of a connection state to said first power supply lead and a disconnection state therefrom;
 a second selection pad disposed in the vicinity of said second power supply lead on said semiconductor chip and having one of a connection state to said second power supply lead and a disconnection state therefrom; and
 first selecting means responsive to said connection/disconnection states of said first and second selection pads for selecting any of said plurality of first predetermined operations.

5,587,608

STRUCTURE HEAT SINK FOR POWER SEMICONDUCTORS


Ching-Ming Meng, No. 59, Jinn Shiun 2nd St., Yangmei City, Taoyuan, Taiwan

Filed Oct. 27, 1995, Ser. No. 549,231

Int. Cl.⁶ H01L 23/34; 23/28

U.S. Cl. 257-712

2 Claims



1. An improved extruded aluminum heat sink structure for coupling to a power semiconductor device, comprising a longitudinally extended body member having a U-shaped cross-sectional contour defined by a pair of upright lateral walls disposed on opposing longitudinal sides of a bottom wall, each of said lateral walls having opposing inner and outer side surfaces and a plurality of longitudinally extended heat dissipation fins integrally formed and extending from both said inner and said outer side surfaces in spaced parallel relationship, said body member having a pair of fastener plates integrally formed and extending respectively from said inner side surfaces of said pair of lateral walls, each of said fastener plates being inclined toward said bottom wall and spaced therefrom by a first predetermined dimension to form a containment slot for receiving a body portion of the power semiconductor

device therein, said body member having a pair of fastener tabs respectively extending from said inner side surfaces of said pair of lateral walls into said containment slot, each of said fastener tabs being formed by displacement of a portion of a respective lateral side wall subsequent to extrusion of said body member in one piece, each of said fastener tabs being spaced from said bottom wall by a second predetermined dimension to define a second portion of said containment slot, said first predetermined dimension being less than a thickness dimension of the body portion of the power semiconductor device and said second predetermined dimension being less than a thickness dimension of a mounting tab portion of the power semiconductor device for securement of the body portion of the power semiconductor device within said first portion of said containment slot and the mounting tab portion thereof with in said second portion of said containment slot.

5,587,609

II-VI GROUP COMPOUND SEMICONDUCTOR DEVICE METALLIC NITRIDE OHMIC CONTACT FOR P-TYPE

Masanori Murakami, Tsuzuki-gun; Yasuo Koide, Kyoto; Nobuaki Teraguchi, and Yoshitaka Tomomura, both of Nara, all of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Mar. 23, 1995, Ser. No. 409,307

Claims priority, application Japan, Mar. 24, 1994, 6-053588

Int. Cl.⁶ H01L 29/45; 29/43; 23/48

U.S. Cl. 257-744

6 Claims



1. A II-VI group compound semiconductor device having a p-type $\text{Zn}_{1-x}\text{Mg}_x\text{S}_y\text{Se}_{1-y}$, ($0 \leq x \leq 1$, $0 \leq y \leq 1$) semiconductor layer, on which an electrode layer is formed with at least metallic nitride layer lying between the semiconductor layer and the electrode.

5,587,610

SEMICONDUCTOR DEVICE HAVING A CONDUCTIVE LAYER WITH AN APERTURE

Masayuki Watanabe, Kanagawa, Japan, assignor to NEC Corporation, Tokyo, Japan

Continuation of Ser. No. 102,260, Aug. 5, 1993, abandoned.


This application Oct. 26, 1994, Ser. No. 330,093

Claims priority, application Japan, Aug. 6, 1992, 4-209903

Int. Cl.⁶ H01L 23/48; 23/52


U.S. Cl. 257-758

7 Claims



1. A semiconductor device comprising:
 a semiconductor substrate of a first conductivity type;
 a circuit element having a first electrode, a second electrode, and an impurity diffusion region of a second conductivity type

formed in said semiconductor substrate and connected to said second electrode, and said first electrode is formed over said semiconductor substrate;
 an insulating layer formed to cover said circuit element; and
 a conductive layer formed on said insulating layer over said circuit element, an aperture being selectively formed in said conductive layer such that respective parts of said first and second electrodes and said impurity diffusion region are exposed through said aperture such that electrical continuity of said conductive layer is retained.



dummy semiconductor region is adjacent to at least one of said plurality of island semiconductor regions and is lower than said plurality of island semiconductor regions.

5,587,611

COPLANAR X-RAY PHOTODIODE ASSEMBLIES


Alexander T. Botka, Cambridge, Vt.; Ben Tuval, Brookline, and Sorin Marcovici, Lexington, both of Mass., assignors to Analogic Corporation, Peabody, Mass.

Filed May 8, 1995, Ser. No. 436,572

Int. Cl.⁶ H01L 27/146; 31/075; 31/115

U.S. Cl. 257-458

40 Claims



1. A coplanar, non-dielectrically isolated photodiode for X-ray detection comprising semiconductor means having an absorption face and adjoining said face: (a) a single, elongated first doped region having a first polarity and defined by planar walls extending substantially perpendicularly from said absorption face into said semiconductor means to a first depth; (b) a second doped region having a polarity opposite that of said first doped region and defined by planar walls extending substantially perpendicularly from said absorption face into said semiconductor means to a second depth that is substantially equal to or greater than said first depth; (c) a substantially undoped region extending from said absorption face into said semiconductor means so as to separate and completely surround both of said first and second regions and to create a single p-n junction between said first and second doped regions; and (d) first electrical contact means connected to said first region along said absorption face.

5,587,612

SEMICONDUCTOR DEVICE HAVING SEMICONDUCTOR ACTIVE AND DUMMY REGIONS WITH THE DUMMY REGIONS LOWER IN HEIGHT THAN THE ACTIVE REGIONS

Mitsuhiko Sugiyama, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Sep. 11, 1995, Ser. No. 526,177

Claims priority, application Japan, Sep. 9, 1994, 6-215924

Int. Cl.⁶ H01L 29/00; 27/01

U.S. Cl. 257-506

6 Claims

1. A semiconductor device, comprising:
 a substrate;
 an insulating layer formed on said substrate;
 a plurality of island semiconductor regions which are formed on said insulating layer and are isolated from each other by an insulator, each of said plurality of island semiconductor regions forming a semiconductor element therein; and
 a dummy semiconductor region which is formed on said insulating layer and is buried in said insulator, wherein said

5,587,613

LOW-CAPACITANCE, ISOTROPICALLY ETCHED ANTIFUSE AND METHOD OF MANUFACTURE THEREFOR


Ali Iranmanesh, Sunnyvale, Calif., assignor to Crosspoint Solutions, Inc., Santa Clara, Calif.

Filed May 25, 1994, Ser. No. 248,771

Int. Cl.⁶ H01L 29/00

U.S. Cl. 257-530

7 Claims



1. An antifuse structure in an integrated circuit comprising a first metal interconnection line;
 a programming layer over said first interconnection line;
 an etch stop layer over said programming layer, said etch stop layer from 20 to 40 Å thick;
 a buffer layer over said etch stop layer, said buffer from 300 to 800 Å thick;
 an insulating layer over said buffer layer, said buffer layer having etching characteristics different from said insulating layer and said etch stop layer, said insulating layer being relatively thick with respect to said etch stop layer and having an aperture therethrough, said aperture further extending through said buffer layer, said insulating layer from 5000 to 15000 Å thick; and
 a second interconnection line over said insulating layer and in said aperture;
 whereby said antifuse structure has low capacitance and a consistent programming voltage.

5,587,614

MICROPLANARIZATION OF ROUGH ELECTRODES BY THIN AMORPHOUS LAYERS

Chong-Lii Hwang, Wappingers Falls, N.Y., and Clarence W. Teng, Plano, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.


Division of Ser. No. 397,001, Mar. 1, 1995, abandoned. This application Jun. 7, 1995, Ser. No. 473,807

Int. Cl.⁶ H01L 27/02; 27/00

U.S. Cl. 257-532

7 Claims

1. A capacitor structure for an integrated circuit comprising:



- (a) an electrode having a polycrystalline material surface having voids extending to said surface;
- (b) a first thin layer of a dielectric over the polycrystalline material;
- (c) a layer of an amorphous form of said material over said first thin layer, the amorphous layer disposed within said voids;
- (d) a second thin layer of a dielectric over said amorphous layer; and
- (e) a layer of electrical conductor spaced from said material over said second thin layer.

5,587,615

ELECTROMAGNETIC FORCE GENERATOR


Bruce S. Murray, Winchester; Howard C. Noble, Cohasset, and Wilma W. Quinn, Wakefield, all of Mass., assignors to Bolt Beranek and Newman Inc., Cambridge, Mass.

Filed Dec. 22, 1994, Ser. No. 362,133

Int. Cl.⁶ H02K 33/12

U.S. Cl. 310—30

9 Claims



1. An electromagnetic force generator comprising:
 - a first elongate magnetic core having transversely facing pole faces at each end;
 - a second elongate magnetic core essentially paralleling said first core and spaced therefrom in fixed relation and having transversely facing pole faces at each end aligned with corresponding pole faces of said first core;
 - between each pair of aligned pole faces, a relatively moveable magnetic core, each of said moveable cores being moveable in the direction extending between the respective aligned pole faces;
 - a magnet mounted in fixed relation between said first and second cores and being polarized along an axis essentially paralleling the length of said first and second cores and extending at each end to a point adjacent to said relatively moveable cores thereby to establish respective sliding gaps;
 - means for attaching said moveable cores to a structure to which force is to be applied;
 - suspension means providing a compliant mechanical connection between said relatively moveable cores and said first and second cores; and
 - respective windings around said first and second cores whereby a.c. energization of said windings will generate a corresponding vibratory force between said moveable cores and said first and second cores.


5,587,616
ROTOR FOR A DYNAMOELECTRIC MACHINE HAVING A ONE-PIECE ROTATION RECTIFIER
 Tyrone A. Johnsen, Rockford, Ill., assignor to Sundstrand Corporation, Rockford, Ill.

Filed May 4, 1993, Ser. No. 57,718

Int. Cl.⁶ H02K 11/00; 1/32

U.S. Cl. 310—68 D

35 Claims



1. A rectifier assembly configured for rotation about an axis of rotation, the rectifier comprising:
 - (a) two axially-spaced field plates having generally planar major surfaces oriented perpendicularly to the axis of rotation;
 - (b) two layers of diodes sandwiched between the field plates;
 - (c) a layer of phase plates electrically isolated from one another sandwiched between the layers of diodes; and
 - (d) means for integrally joining the diodes to the field plates and to the phase plates to form a unitary, laminated structure rotatable about the axis of rotation.

5,587,617

INTEGRATED PASSIVE MAGNETIC BEARING SYSTEM AND SPINDLE MAGNET FOR USE IN AN AXIAL MAGNET SPINDLE MOTOR


John C. Dunfield, and Kamran Oveysi, both of Aptos, Calif., assignors to Seagate Technology, Inc., San Jose, Calif.

Continuation of Ser. No. 289,949, Aug. 12, 1994. This application Jun. 7, 1995, Ser. No. 478,271

Int. Cl.⁶ H02K 7/09

U.S. Cl. 310—90.5

18 Claims



1. In a reduced height disc drive having a flat spindle motor assembly comprised of a spindle permanent magnet held in opposition to an electromagnet assembly attached to a stator, an apparatus for journaling a rotor having a hub shaft about said stator of said flat spindle motor comprising:
 - said stator comprising a base portion and a stator well, said stator well comprising a raised centrally disposed cylindrical portion disposed on said base portion, said stator well for receiving said hub shaft;
 - a pivot, said pivot for pivotally displacing said rotor about said stator, said pivot for engaging said hub shaft at a base portion of said stator well;
 - a first annular disc, said disc comprising an axially aligned magnetic pole, said disc radially extending from said stator;
 - a spindle permanent magnet having a first and second end and non-magnetized region disposed there between, said first end comprising a plurality of magnetic poles disposed on said rotor in opposition to said spindle motor electromagnet assembly, said second end comprised of a like axially aligned

magnetic pole disposed on said rotor, opposing and offset to the inside of said axially aligned magnetic pole on said first annular disc; and
 an annular base extension, said annular base extension integral to said base portion of said stator beginning at an exterior wall of said stator well and extending toward and at a height equal to said electromagnet assembly and directly beneath said first end of said spindle permanent magnet, whereby said rotor is pre-loaded due to the attractive forces developed between said annular base extension and said first end of said spindle permanent magnet.

5,587,618

DIRECT CURRENT HOMOPOLAR MACHINE

George D. Hathaway, 39 Kendal Avenue, Toronto, Ontario, Canada


Continuation-in-part of Ser. No. 155,628, Nov. 22, 1993, abandoned. This application Apr. 13, 1995, Ser. No. 421,317

Claims priority, application Canada, Apr. 15, 1993, 2094078

Int. Cl.⁶ H02K 49/00; 31/00; 16/00

U.S. Cl. 310—178

21 Claims



1. A direct current electrical machine comprising:
 - an orbiting electrical conductor means comprising a first electrically conductive shaft means extending along an axis and having a first electrical connection means and a second electrical connection means displaced from the first electrical connection means along the axis;
 - a stationary set of electrical conductor means comprising:
 - a second electrically conductive shaft means having a third electrical connection means; and
 - a third electrically conductive shaft means having a fourth electrical connection means;
 - a first conductor means electrically coupling the first electrical connection means with the third electrical connection means;
 - a second conductor means electrically coupling the second electrical connection means with the fourth electrical connection means;
 - a first armature means comprising one of the four electrical connection means;
 - a first magnetic flux path mechanically coupled with the orbiting electrical conductor means and intersecting the first armature means;
 - a first magnetic flux generating means for generating a magnetic flux through said first magnetic flux path;
 - wherein the orbiting electrical conductor means is movable around the stationary set of electrical conductor means;
 - wherein movement of the orbiting electrical conductor means around the stationary set of electrical conductor means causes relative movement between said first magnetic flux path and said first armature means; and
 - wherein when the orbiting electrical conductor means moves around the stationary set of electrical conductor means while the first magnetic flux generating means is generating a magnetic flux through the first magnetic flux path an electrical potential is generated between the second electrically conductive shaft means and the third electrically conductive shaft means.

5,587,619

ROTARY ARMATURE AND METHOD OF FORMING ARMATURE COIL

Shigeru Yumiyama, Katsuta; Ko Onodera, Hitachioota, and Yoshimi Mori, Mito, all of Japan, assignors to Hitachi, Ltd., Japan


Filed Dec. 17, 1993, Ser. No. 168,172

Claims priority, application Japan, Dec. 21, 1992, 4-339954

Int. Cl.⁶ H02K 1/04; 3/04; 17/00

U.S. Cl. 310—201

7 Claims



1. A rotary armature, comprising a shaft supported rotatably at both ends thereof;
 - a magnetic core fixed by said shaft and forming a plurality of slots at an outer periphery thereof; and
 - a flat type coil insulated from said magnetic core by an insulating material, said flat type coil being a multi-coil structure in one slot and coated by an insulated coating film; wherein said flat type coil comprises a first flat type coil and a second flat type coil,
 - said first flat type coil having a first pair of said insulated coating films oppositely arranged to each other in a rotational direction of the armature and being made thinner than a second pair of insulated coating films which are oppositely arranged to each other in a radial direction of the armature,
 - said second flat type coil having a third pair of said insulated coating films being oppositely arranged to each other in the rotational direction, and being made thinner than a fourth pair of insulated coating films oppositely arranged to each other in the radial direction,
 - one of said second pair of said insulated coating films in the radial direction of said first flat type coil being opposed to one of said fourth pair of said insulated coating films in the radial direction of said second flat type coil,
 - one of said second pair of said insulated coating films in the radial direction of said first flat type coil contacting one of said fourth pair of said insulated coating films in the radial direction of said second flat type coil,
 - one of said second pair of said insulated coating films in the radial direction of said first flat type coil contacting an insulating sheet, sandwiched between said magnetic core and said second pair of said insulated coating films in the radial direction of said first flat type coil, and
 - one of said fourth pair of said insulated coating films in the radial direction of said second flat type coil contacting an insulating sheet sandwiched between said magnetic core and said fourth pair of said insulated coating films in the radial direction of said second flat type coil.

5,587,620

TUNABLE THIN FILM ACOUSTIC RESONATORS AND METHOD FOR MAKING THE SAME

Richard C. Ruby, Menlo Park, and Paul P. Merchant, Belmont, both of Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif.


Filed Dec. 21, 1993, Ser. No. 171,227

Int. Cl.⁶ H01L 41/08

U.S. Cl. 310—346

25 Claims

1. A high-Q, acoustical resonator, comprising:



a bottom electrode layer having an ordered structure, a thickness and an acoustical attenuation;
a thin-film PZ layer comprising AlN deposited on said lower electrode layer with an ordered structure imparted thereon by said ordered structure of said lower electrode layer, said PZ layer having a top surface and a thickness; and
a top electrode layer adjacent to said top surface of said PZ layer, the top electrode layer having a thickness and an acoustical attenuation,
wherein:

the top electrode layer, the PZ layer, and the bottom electrode layer collectively constitute an acoustic path having a Q, the top electrode layer and the bottom electrode layer each having a thickness relative to the thickness of the PZ layer such that the top electrode layer and the bottom electrode layer collectively constitute such a proportion of the acoustic path that the top electrode layer and the bottom electrode layer having a high acoustical attenuation causes the acoustic path to have a low Q, and

both of said top electrode layer and said bottom electrode layer consist essentially of at least one metal chosen from the group consisting of Mo and W to minimize the acoustical attenuation of said top electrode layer and said bottom electrode layer, and thereby to maximize the Q of the acoustical resonator.

5,587,621

IMAGE INTENSIFIER TUBE

Johannes K. E. Colditz, Heerlen, Netherlands, assignor to U.S. Phillips Corporation, New York, N.Y.


Filed Feb. 8, 1995, Ser. No. 385,520

Claims priority, application Belgium, Feb. 9, 1994, 9400152

Int. Cl.⁶ H01J 29/45

U.S. Cl. 313—366

8 Claims



1. An image intensifier tube, comprising a conversion screen with a substrate on which there is provided a seed layer which is separated by an intermediate layer from a scintillation layer for converting incident radiation of a first wavelength into radiation of a second wavelength, characterized in that the intermediate layer is reflective for at least a part of radiation of the second wavelength emitted towards the intermediate layer.

5,587,622
LOW PRESSURE GAS DISCHARGE LAMPS WITH LOW PROFILE SEALING COVER PLATE

Ferenc Mohacsi, Kalamazoo, Mich., assignor to Fallon Luminous Products, Spartanburg, S.C.

Filed Jul. 12, 1994, Ser. No. 273,713

Int. Cl.⁶ H01K 3/22; H01J 9/26

U.S. Cl. 313—493

5 Claims



1. A low pressure gas discharge lamp comprising:
at least one flat glass sheet including illumination means, said at least one flat glass sheet having an evacuation port;
a thin cover covering said evacuation port and hermetically secured to said at least one flat glass sheet forming the low pressure gas discharge lamp;
wherein a getter is secured to said thin cover.

5,587,623

FIELD EMITTER STRUCTURE AND METHOD OF MAKING THE SAME

Gary W. Jones, Raleigh, N.C., assignor to FED Corporation, Hopewell Junction, N.Y.


Continuation of Ser. No. 29,880, Mar. 11, 1993, abandoned.

This application Apr. 3, 1996, Ser. No. 627,922

Int. Cl.⁶ H01J 19/24

U.S. Cl. 313—497

40 Claims



1. An emitter tip structure for use in a field emission device, comprising:
a substrate;
an emitter tip on the substrate;
a multi-layer electrode structure peripherally overlying and in alignment with the emitter tip, wherein the multi-layer electrode structure comprises:
electrode conductive layer; and
at least three successive insulative layers comprising different insulative materials in successively adjacent insulative layers, between said electrode conductive layer and the substrate, wherein said different insulative material in successively adjacent insulative layers comprises respectively different dielectric constant materials in said successively adjacent insulative layers, for providing current leakage control in said emitter tip structure.

5,587,624

PLASMA DISPLAY PANEL

Toshihiro Komaki, Yamanashi-ken, Japan, assignor to Pioneer Electronic Corporation, Tokyo, Japan


Filed Feb. 14, 1995, Ser. No. 388,470

Claims priority, application Japan, Feb. 23, 1994, 6-025076; Jun. 23, 1994, 6-141775

Int. Cl.⁶ H01J 17/49

U.S. Cl. 313—584

4 Claims



1. A plasma display panel comprising:
a pair of substrates, a plurality of sustaining electrodes provided between the substrates and arranged in pairs, a plurality of address electrodes disposed in a perpendicular direction to the sustaining electrodes, thereby forming a matrix defining a plurality of pixels, each pixel being defined by a region bordered by a pair of the sustaining electrodes and two of the address electrodes, wherein:
each of the sustaining electrodes has an area in a central pixel area of the panel that is larger than an area of the sustaining electrodes in a peripheral pixel area of the panel.

5,587,625

GAS DISCHARGE TUBE

Tomoyuki Ikeda; Yoshinobu Ito, and Ryotaro Matui, all of Hamamatsu, Japan, assignors to Hamamatsu Photonics K.K., Hamamatsu, Japan


Filed Jul. 13, 1995, Ser. No. 502,010

Claims priority, application Japan, Aug. 31, 1994, 6-207712

Int. Cl.⁶ H01J 17/02

U.S. Cl. 313—613

22 Claims



1. A gas discharge tube comprising:
an envelope for sealing a gas therein;
a discharge shielding member of an insulator being in said envelope, said discharge shielding member having a front surface and a rear surface which is opposite to said front surface and which is communicated with the front surface by a through hole;
a hot cathode for emitting thermoelectrons, being in said envelope and located at the front surface side of said discharge shielding member;

an anode plate for receiving the thermoelectrons emitted from said hot cathode, being in contact with at least two parts of the rear surface of said discharge shielding member and covering an opening of the through hole at the rear surface side of said discharge shielding member;

a focusing electrode being supported by said discharge shielding member and in contact with the front surface of said discharge shielding member, said focusing electrode having a focusing opening which is located at a position of an opening of the through hole at the front surface side of said discharge shielding member, for converging paths of the thermoelectrons; and
a support member of an insulator being in said envelope and located on an opposite side to said discharge shielding member through said anode plate, said support member having at least two projections for respectively pushing said anode plate onto said parts of the rear surface of said discharge shielding member, whereby at least two parts of said anode plate are gripped by said projections of said support member and the rear surface of said discharge shielding member.

5,587,626

PATTERNED OPTICAL INTERFERENCE COATINGS FOR ONLY A PORTION OF A HIGH INTENSITY LAMP ENVELOPE

Thomas G. Parham, Gates Mills; Frederick W. Dynys, Chagrin Falls; Carl V. Gunter, Twinsburg; John M. Davenport, Lyndhurst; Thomas M. Golz, Willoughby Hills; Rolf S. Bergman, Cleveland Heights; Frederic F. Ahlgren, Euclid; Gary R. Allen, Chesterland; Mark E. Duffy, Shaker Heights, and Richard L. Hansler, Pepper Pike, all of Ohio, assignors to General Electric Company, Schenectady, N.Y.


Continuation of Ser. No. 165,447, Dec. 10, 1993, abandoned.

This application Dec. 27, 1995, Ser. No. 579,447

Int. Cl.⁶ H01J 17/16; 61/30; G02B 1/10; F21M 3/14

U.S. Cl. 313—634

24 Claims



1. A light source comprising:
means for generating light;
a vitreous light-transmitting envelope having a sealed chamber that receives the light generating means and an external surface, the envelope and light generating means being dimensioned such that the average power density transmitted through the envelope is at least four (4) watts/cm²; and
a multilayer optical interference coating on only a portion of the external surface of the envelope for reflecting light from the light generating means in a direction that enhances the amount of light transmitted through an uncoated portion of the envelope external surface.

5,587,627

PLANAR DISPLAY APPARATUS HAVING EXPOSED INSULATED SUBSTRATE PORTION

Masato Saito; Ryo Suzuki; Keiji Fukuyama; Takuya Ohira; Keiji Watanabe, all of Kamakura; Minoru Kobayashi; Susumu Hoshinouchi, both of Amagasaki, and Yoshinori Hatanaka, Hamamatsu, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 7,912, Jan. 22, 1993, Pat. No. 5,495,145, which is a continuation of Ser. No. 648,031, Jan. 30, 1991, abandoned. This application Feb. 28, 1995, Ser. No. 395,703

Claims priority, application Japan, Feb. 1, 1990, 2-22768; Feb. 21, 1990, 2-41601

Int. Cl.⁶ H05B 37/02

U.S. Cl. 315—169.1

12 Claims



1. A planar display device comprising: an electron emission source for emitting electrons to a phosphor screen provided on an inside surface of a sealed container; a surface insulated substrate being composed of a conductive substrate and an insulating layer said surface insulated substrate being provided between the electron emission source and the phosphor screen and provided with a plurality of electron-passing holes; a control electrode portion including a plurality of conductive films having a passing electron controlling potential applied thereto; a conductive substrate exposed portion formed on a portion of said surface insulated substrate and composed of a portion of the conductive substrate without the insulating layer; and a voltage applying circuit applying a predetermined voltage to the conductive substrate exposed portion wherein each of the plurality of conductive films cover a part of an inside surface of at least one of the plurality of electron passing holes.

5,587,628

FIELD EMITTER WITH A TAPERED GATE FOR FLAT PANEL DISPLAY


Huel-Pei Kuo, 924 Old Town Ct., Cupertino, Calif. 95014
Filed Apr. 21, 1995, Ser. No. 426,357

Int. Cl.⁶ G09G 3/00

U.S. Cl. 315—169.3

12 Claims

1. A field emission device in an apparatus with a screen, the device comprising: a substrate; an emitter layer, made of resistive material, coupled to the substrate, the layer having a side end that has an edge, a spacer layer on and over only a portion of the emitter layer to expose the edge; and a gate layer, on the spacer layer, the gate layer having a side end that is tapered to form a wedge with an edge, and including: a gate dielectric layer; and a gate conductive layer over the gate dielectric layer to cover at least the side end and the edge of the gate layer; wherein the screen is at a selected positive voltage and is positioned above the gate layer; such that: when a selected potential difference is applied between the edge emitter and the gate layer, an electron-extraction field is established between the edge of the wedge and the edge



of the emitter layer to extract electrons from the edge of the emitter layer, and the electrons are attracted to the screen; the resistive nature of the emitter layer enhances the uniformity of the electrons emitted along the edge of the emitter layer; and the wedge reduces the amount of extracted electrons collected by the gate layer.

5,587,629

TRANSFORMERLESS HIGH-VOLTAGE GENERATOR CIRCUIT


Viktor L. Gornstein, New York, N.Y., assignor to Philips Electronics North America Corporation, New York, N.Y.

Filed Aug. 28, 1995, Ser. No. 519,907

Int. Cl.⁶ H05B 37/00

U.S. Cl. 315—200 R

6 Claims



1. A transformerless high-voltage generator circuit, which comprises: an amplifier having an inverting input terminal, a noninverting input terminal, and an amplifier output terminal, said noninverting input terminal being coupled to a common terminal; and a feedback circuit coupled between said amplifier output terminal and said inverting input terminal for causing said high-voltage generator circuit to oscillate during operation, said feedback circuit comprising: a first resistor coupled between said amplifier output terminal and said inverting input terminal; first and second capacitors coupled in series between said amplifier output terminal and said inverting input terminal, said first resistor being coupled in parallel with said first and second capacitors and a common connection between said first and second capacitors forming a high-voltage output terminal for generating a high-voltage output with respect to said common terminal; and an inductor coupled between said high-voltage output terminal and said common terminal and connected directly to said common terminal.

5,587,630

CONTINUOUS PLASMA IGNITION SYSTEM


Kevin A. Dooley, Georgetown, Canada, assignor to Pratt & Whitney Canada Inc., Longueuil, Canada

Filed Oct. 28, 1993, Ser. No. 144,080

Int. Cl.⁶ H05B 37/02

U.S. Cl. 315—209 T

25 Claims



1. A gas turbine ignition system, comprising: an electrical signal generator to generate an electrical AC signal with a frequency f ; an ignitor circuit excited by signals generated by said generator, said ignitor circuit including an ignitor, said ignitor circuit being a resonant circuit having a resonant frequency f_r , such that said ignitor circuit, when excited by said electrical AC signal generated by said generator, generates a plasma of ionized gas and thereafter maintains said plasma of ionized gas when said ignitor circuit continues to be excited with said electrical AC signal.

5,587,631

RESISTOR-MATCHED DEFLECTION APPARATUS FOR A VIDEO DISPLAY

James A. Wilber, Indianapolis, Ind., and Karl R. Koblitz, Meylan, France, assignors to Thomson Consumer Electronics, Inc., Indianapolis, Ind.


Continuation of Ser. No. 843,074, Mar. 2, 1992, abandoned.

This application Oct. 23, 1992, Ser. No. 965,310

Int. Cl.⁶ H01J 29/70; 29/76

U.S. Cl. 315—403

15 Claims



1. A video display deflection apparatus, comprising: a cathode ray tube; a deflection winding mounted on a neck of said cathode ray tube; a resistor network; a source of a sawtooth signal that is developed at a first input terminal of said resistor network having a D.C. component; a source of a D.C. second signal that is developed at a second input terminal of said resistor network having a level that is different from that of said D.C. component; a deflection amplifier responsive to said sawtooth and second signals and coupled to said deflection winding to form a D.C. coupled deflection circuit for generating a deflection current in said deflection winding, said sawtooth and second signals being coupled to said amplifier via said resistor network such

that a D.C. Thevenin equivalent at a first output terminal of said resistor network of a circuit that includes said source of said sawtooth signal and a first plurality of resistors of said resistor network is identical to a D.C. Thevenin equivalent at a second output terminal of said resistor network of a circuit that includes said source of said second signal and a second plurality of resistors of said resistor network, each resistor of said first and second plurality of resistors having the same value.

5,587,632

INJECTION APPARATUS BOTH FOR POSITIVE AND NEGATIVE IONS

Izumi Sakai, Tsukuba, Japan, assignor to National Laboratory for High Energy Physics, Tsukuba, Japan


Filed Sep. 5, 1995, Ser. No. 523,216

Claims priority, application Japan, Sep. 5, 1994, 6-211261

Int. Cl.⁶ H01J 23/00; 23/34; H05H 7/00; H01F 7/00

U.S. Cl. 315—507

4 Claims



2. An injection apparatus both for positive and negative ions comprising: a first, a third and a fourth bump magnets arranged in order on a circulation orbit, a second bump magnet arranged on said circulation orbit between the first and the third bump magnets so as to maintain a given position relative to the circulation orbit and a carbon film arranged between the second and the third bump magnets, wherein upon the injection of a negative ion beam, the second bump magnet is affording a function as a bump magnet, after an orbit of the negative ion beam injected at a given angle is deflected in parallel with the circulation orbit through a bump magnet field formed in the second bump magnet, electrons contained in the negative ion beam are separated through the carbon film and converted into a positive ion beam, which gets on the circulation orbit through the third and the fourth bump magnets, wherein upon the injection of a positive ion beam, the second bump magnet is affording a function as a septum magnet, after an orbit of the positive ion beam injected at a given angle is deflected in parallel with the circulation orbit by making the circulation orbit shifted through the first bump magnet to temporarily pass through a septum magnetic field formed in the second bump magnet, the positive ion beam gets on the circulation orbit through the third and the fourth bump magnets.

5,587,633

PRESS CONTROL METHOD AND PRESS APPARATUS

Hideji Aoki; Takahiro Tashima; Suekazu Nakashima; Yoshiyuki Osako, and Hidetaka Yamasaki, all of Tokyo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, and Mitsubishi Electric Engineering Co., Ltd., both of Tokyo, Japan

Filed Dec. 27, 1995, Ser. No. 578,970


Claims priority, application Japan, Feb. 23, 1995, 7-035368

Int. Cl.⁶ B21D 5/02

U.S. Cl. 318—164

12 Claims

7. A press apparatus which converts a driving force of a motor into a thrusting force of a mold through driving force—thrusting force converting means directly connected to said motor to press a processed object, comprising: torque value detecting means connected to said motor, for detecting a change of a torque value of said motor caused in press processing of said processed object;



torque value comparing means connected to said torque value detecting means, for making a comparison and determining whether the detected torque value is a previously set predetermined torque value which is smaller than a target rated torque value or not;

drive quantity counting means connected to said motor for counting the quantity of drive of said motor; and

controlling means connected to said torque value comparing means and said drive quantity counting means, for storing deceleration pattern previously set as a function of speed and the quantity of drive and comparing the quantity of drive of said motor outputted from said drive quantity counting means and said deceleration pattern to output speed instructions according to the quantity of drive of said motor so as to decelerate the thrusting speed of said mold, so that after reaching said predetermined torque value, the thrusting speed of said mold attains zero at the time when the quantity of drive of said motor achieves a previously set predetermined quantity of drive.


5,587,634

HUMAN BODY ACTUATED CONTROL APPARATUS AND SYSTEM FOR COMMERCIAL SEWING MACHINES
Dhimat R. Desai, South Barrington; Louis C. Tayse, Hinsdale, and Richard W. Gideon, Schaumburg, all of Ill., assignors to ARA Electronics Corp., Elmhurst, Ill.

Filed Nov. 29, 1994, Ser. No. 346,482
Int. Cl.⁶ D05B 69/06

U.S. Cl. 318—257

56 Claims



1. An above ground level human body actuated control apparatus for use with an industrial machine by an upright standing

operator while both feet are fixed in pressing engagement with a floor surface, comprising:

- an elongated housing;
- an elongated control bar having a vertically disposed outer side which extends horizontally, the elongated control bar being sized and configured for horizontally extending across an upright body portion of the operator;
- means for pivotally mounting the elongated control bar to the elongated housing for generally horizontal movement of the elongated control bar relative to the elongated housing;
- biasing means operatively positioned between the elongated housing and the elongated control bar for urging the elongated control bar in a first direction;
- a force sensor operatively positioned between the elongated housing and the elongated control bar; and
- sensor actuator means operatively positioned relative to the force sensor for co-action with the force sensor when the upright body portion of the operator pressingly engages the elongated control bar in a second direction.

5,587,635

ROBOT CONTROL APPARATUS FOR MONITORING LOAD ON ROBOT

Atsushi Watanabe, Oshino-mura; Ryo Nihei, and Akihiro Terada, both of Fujiyoshida, all of Japan, assignors to Fanuc Ltd., Japan


PCT No. PCT/JP94/01582, § 371 Date May 30, 1995, § 102(e) Date May 30, 1995, PCT Pub. No. WO95/09479, PCT Pub. Date Apr. 6, 1995

PCT Filed Sep. 27, 1994, Ser. No. 446,713

Claims priority, application Japan, Sep. 30, 1993, 5-265526
Int. Cl.⁶ H02K 17/32

U.S. Cl. 318—434

8 Claims



- A robot control apparatus for monitoring a load exerted on a robot comprising:
 - a motor having an output shaft connected to a driving mechanism of said robot;
 - speed detection means for detecting a rotational angular speed of said motor;
 - acceleration calculation means for determining a rotational angular acceleration of said motor based on said rotational angular speed;
 - driving torque calculation means for calculating a driving torque outputted from said motor output shaft by determining a torque spent inside the motor using said rotational angular speed and said rotational angular acceleration, by determining a torque generated by the motor using a driving current of said motor and by subtracting said torque spent inside the motor from said torque generated by said motor; and
 - display means for displaying said calculated driving torque.

5,587,636

OBSERVER-COMPENSATOR FOR AN ELECTRIC MOTOR SYSTEM


Izhak Bar-Kana, Wynnewood, and Predrag Filipovic, Philadelphia, both of Pa., assignors to Kulicke and Soffa Investments, Inc., Wilmington, Del.

Filed Feb. 24, 1995, Ser. No. 394,381

Int. Cl.⁶ G06F 15/46

U.S. Cl. 318—561

20 Claims



- A method of compensation for unmeasurable disturbance forces in a motor system of the type including a positioning motor to be accurately positioned at high speed in response to positioning command signals generated by a computer controller which is coupled to the motor system, comprising the steps of:
 - connecting an observer-compensator in a feed forward loop between the output of said computer controller and the input to said motor system;
 - actuating said motor over a limited range of physical positions in which negligible disturbance forces occur;
 - adjusting an ideal motor simulator in said observer-compensator during movement of said motor where negligible disturbances forces occur to provide an ideal motor simulator equal to the said motor system;
 - actuating said motor over a range of physical positions in which high disturbance forces occur;
 - subtracting the output signal from said ideal motor simulator from a similar output signal from the actual motor system to provide a disturbance force error signal;
 - coupling said disturbance force error signal to a disturbance force reconstruction device in said compensator-observer;
 - coupling the output of said disturbance force reconstruction device as a negative input to said actual motor system; and
 - adjusting said disturbance force reconstruction device until the disturbance force error signal is reduced to a minimum and said disturbance force reconstruction device is made substantially equal to said unmeasurable disturbance forces in said actual motor system.

5,587,637

ROBOT ARM DEVICE CAPABLE OF CONVEYING AN ARTICLE IN CIRCUMFERENTIAL AND RADIAL DIRECTIONS

Keishi Ohyama, Kasaoka, Japan, assignor to Tatsumo Kabushiki Kaisha, Okayama-ken, Japan


Filed Dec. 29, 1994, Ser. No. 365,653

Claims priority, application Japan, Jan. 10, 1994, 6-000864
Int. Cl.⁶ B25J 9/18

U.S. Cl. 318—568.11

7 Claims

- A robot arm device comprising:
 - an expandable arm portion including an arm member, a forearm member, and a hand member;
 - an arm drive wheel fixedly connected at a base end of the arm member;
 - a transmission mechanism including a transmission wheel disposed coaxially with the arm drive wheel and rotatable independently from the arm drive wheel;
 - a forearm drive wheel disposed at a leading end of the arm member and rotatable independently from the arm member and fixedly connected at a base end of the forearm member;



- a stationary wheel disposed coaxially with the forearm drive wheel and fixedly connected with the arm member;
- a hand drive wheel disposed at a leading end of the forearm member, and rotatable independently from the forearm member, and fixedly connected at a base end of the hand member, and having a diameter twice greater than the stationary wheel, and an axis of the hand drive wheel being spaced from an axis of the stationary wheel the same distance as an axis of the forearm drive wheel is spaced from an axis of the arm drive wheel;
- an arm drive motor operable to rotate the arm drive wheel;
- a forearm drive motor operable to rotate the forearm drive wheel via the transmission mechanism;
- a first endless member wound on the transmission wheel and the forearm drive wheel;
- a second endless member wound on the stationary wheel and the hand drive wheel; and
- a controller operable to control the driving of the arm and forearm drive motors to:
 - rotate the arm and forearm drive motors in the same direction to thereby rotate the arm portion in a specified circumferential direction; and
 - rotate the arm drive motor in a specified direction and rotate the forearm drive motor in the opposite direction at such an angular speed as to rotate the forearm drive wheel twice faster than the arm drive wheel via the transmission mechanism and the first endless member in combination with a relative rotation of the forearm drive wheel due to the rotation of the arm member to thereby move the hand member in a straight radial direction.

5,587,638

FLEXIBLE SERVO CONTROL METHOD CAPABLE OF SPECIFYING FLEXIBILITY ON WORKING COORDINATES

Tetsuaki Kato, Hadano; Soichi Arita, and Masaru Nakamura, both of Oshino-mura, all of Japan, assignors to Fanuc Ltd., Minamitsuru-gun, Japan

PCT No. PCT/JP94/01012, § 371 Date Feb. 28, 1995, § 102(e) Date Feb. 28, 1995, PCT Pub. No. WO95/02214, PCT Pub. Date Jan. 19, 1995


PCT Filed Jun. 23, 1994, Ser. No. 392,790

Claims priority, application Japan, Jul. 5, 1993, 5-191962
Int. Cl.⁶ G05B 19/42

U.S. Cl. 318—568.14

4 Claims

- A flexible servomotor method of a servomotor which drives a body, the servomotor being controlled by a control system including a position control loop and a speed control loop, the flexible servomotor method comprising the steps of:
 - specifying the degrees of flexibility on a working coordinate system of the body;
 - converting the degrees of flexibility specified on the working coordinate system into servo gains with respect to individual axes of the servo motor; and



driving the servo motor according to the converted gains so that the body which is normally driven by the servo motor can be moved manually.

5,587,639

Patent Not Issued For This Number

5,587,640


DELAYED SAFETY BRAKING APPARATUS FOR A SERVOMOTOR CONTROL SYSTEM

Anders Ek, Chicago, and Johan Hegardt, Buffalo Grove, both of Ill., assignors to Tetra Laval Holdings & Finance S.A., Pully, Switzerland

Filed Sep. 28, 1994, Ser. No. 315,407
Int. Cl.⁶ G05B 1/06

U.S. Cl. 318-638

15 Claims



4. A servomotor control system comprising:
- a programmable control system;
 - a servo amplifier connected for control by the programmable control system to effect a predetermined motion profile;
 - a servomotor connected for control by the servo amplifier;
 - a safety switch connected for detection by the programmable control system, the programmable control system controlling the servo amplifier to brake the servomotor upon detection of activation of the safety switch; and
 - a delayed braking circuit disposed between the servo amplifier and the servomotor, the delayed braking circuit connected to detect activation of the safety switch, the delayed braking circuit acting to brake the servomotor upon failure of the programmable control system and the servo amplifier to brake the servomotor within a predetermined period of time after actuation of the safety switch.

5,587,641 VSCF START SYSTEM WITH PRECISE VOLTAGE CONTROL

Gregory I. Rozman, Rockford, Ill., assignor to Sundstrand Corporation, Rockford, Ill.


Continuation of Ser. No. 279,863, Dec. 5, 1988, abandoned.

This application Apr. 2, 1990, Ser. No. 504,102

Int. Cl.⁶ H02P 7/00

U.S. Cl. 318-801

2 Claims



1. A control system for a brushless machine having a rotor and a stator having a stator coil which is controllably energized from a source of DC power defining a positive and a negative DC voltage for imparting rotation to the rotor, comprising:

switching means coupled between the source of DC power and said stator coil for alternately applying the positive and negative voltage to said coil, said switching means defining an output voltage;

first means for generating an output voltage command;

second means for generating a commutation angle command;

first sensing means for sensing the speed of rotational movement of the rotor;

second sensing means for sending current through the stator coil;

means coupled to said second generating means and said first and second sensing means for developing an estimate of stator coil voltage responsive to said commutation angle command, said rotor speed and said stator current, said developing means including means for determining said stator coil voltage in accordance with the following equation:

$$V_T = I_A \cdot R_s + \frac{I_A \cdot K_1 \cdot \omega \cdot L_q}{R(\alpha)}$$

where:

I_A —stator coil current;

α —commutation angle command;

R_s —a constant representing stator coil resistance;

$$K_1 = \text{no. of motor Poles} \cdot \frac{\pi}{60} \quad (\text{a constant});$$

ω —motor speed, rpm; and

L_q —a constant representing motor quadrature axis synchronous inductance; and

control means coupled to said first and second generating means and said developing means for controlling said switching means so that said switching means develop an output voltage in accordance with said output voltage command, said commutation angle command and said voltage estimate.

5,587,642

FAN MOTOR BROWN-OUT CONTROL ALGORITHM


Larry J. Manson, Baroda; Chris A. Scriber, Holland, both of Mich., and William L. Davis, Murfreesboro, Tenn., assignors to Whirlpool Corporation, Benton Harbor, Mich.

Filed Apr. 7, 1995, Ser. No. 418,621

Int. Cl.⁶ H02P 7/622

U.S. Cl. 318-812

13 Claims



1. An air conditioner, comprising:
- a power supply connected to an AC line voltage;
 - a fan motor;
 - a multispeed fan driven by the fan motor, the multispeed fan having at least a first speed, a second speed and a third speed of discrete increasing values;
 - means for selecting one of the first, second or third speeds of the fan to obtain a selected speed of the fan;
 - means for sensing a brown-out condition of the AC line voltage and for providing a signal indicative of the brown-out condition, the sensing means being connected to the power supply; and
 - means for increasing the speed of the fan from the selected speed to the next higher speed value in response to the sensed brown-out condition signal provided by the sensing means.

5,587,643

ROTARY INDUCTION MACHINE HAVING CONTROL OF SECONDARY WINDING IMPEDANCE

Samuel Heller, Westchester County, N.Y., assignor to Heller DeJulio Corporation, Danville, Calif.

Continuation of Ser. No. 789,993, Nov. 12, 1991, abandoned,

which is a continuation of Ser. No. 489,894, Mar. 6, 1990,

abandoned, which is a continuation-in-part of Ser. No.


218,575, Jul. 12, 1988, abandoned. This application Mar. 22,

1994, Ser. No. 216,090

Int. Cl.⁶ H02P 13/00

U.S. Cl. 318-821

2 Claims



1. A rotary induction generator comprising a stator having wound thereon stator windings defining a three-phase stator; a rotor mounted for rotation in said stator and having wound thereon three rotor winding defining a three-phase rotor; said three-phase stator windings adapted to be connected to a source of electrical power and serving as primary windings whereby the applied power causes current to flow in said three-phase windings and provide a rotating magnetic field; said other three-phase windings serving as a secondary winding coupled to said magnetic field whereby currents are induced in said secondary windings which in turn induce power in said primary windings in response to rotation of the rotor;

capacitive means connected directly across each of said secondary windings having a value sufficient to increase the efficiency of said machine; and
resistive means connected in series with said secondary windings to control the power output for different rotor speeds.

5,587,644

CHARGING CONTROL DEVICE FOR FLASH DEVICE

Junya Masaki, Kanagawa-ken, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Jun. 12, 1995, Ser. No. 490,000

Claims priority, application Japan, Jun. 15, 1994, 6-133265

Int. Cl.⁶ H02J 7/00; H01M 10/44; G03B 7/08

U.S. Cl. 320-1

5 Claims



1. A charging control device for a flash device, comprising:
- a) temperature detecting means for detecting a temperature condition; and
 - b) charging regulating means for regulating a charging action on a main capacitor of the flash device on the basis of the temperature condition detected by said temperature detecting means, said charging regulating means including memory means for storing charging action data corresponding to diverse temperatures.

5,587,645

BATTERY CHARGER WITH NIGHT LIGHT FOR A CORDLESS TELEPHONE


Eduardo Sciammarella, Hoboken, and Michael Lang, Ridge-wood, both of N.J., assignors to Sony Corporation, Tokyo, Japan, and Sony Electronics Inc., Park Ridge, N.J.

Filed Mar. 9, 1994, Ser. No. 208,540

Int. Cl.⁶ H02T 7/00

U.S. Cl. 320-2

3 Claims



1. A battery charger, wherein said battery charger is energized by a power supply and said power supply is accessible through an electrical outlet having upper and lower receptacle pairs, comprising:

a housing having an aperture for receiving a cordless telephone handset having rechargeable batteries and handset contacts electrically connected to said batteries, wherein said housing includes charger contacts for forming an electrical connection with said handset contacts;

upper and lower prongs extending from said housing, said upper and lower prongs being adapted to be inserted into said upper and lower receptacle pairs, respectively, for removably securing said housing to said electrical outlet when said handset is positioned within said aperture;

said housing including:

charging means for charging said batteries, said charging means being electrically connected to said charger contacts and including an indicator disposed on said housing for indicating that said battery is being charged; a phototransistor for detecting whether a level of light impinging on said housing is below a predetermined level;

a lamp disposed on said housing for providing illumination adjacent said housing;

first circuit means for supplying electrical power from said power supply to energize said charging means, said light sensing means and said lamp;

second circuit means for supplying electrical power from said battery to energize said lamp when said power supply is disconnected from said battery charger and when said light detection means detects a level of light below said predetermined level, and

a switch for turning said lamp on or off.


5,587,646

RECHARGEABLE TABLE LIGHTING SYSTEM WITH PROTECTION FROM SHORT CIRCUITS
Mark S. Thomas, 5058 Dunsmuir Common, Fremont, Calif. 94555

Filed Sep. 23, 1994, Ser. No. 311,269
Int. Cl.⁶ F21L 7/00; H02J 7/00

U.S. Cl. 320—25

5 Claims



1. A battery operated table lighting fixture including:
a housing having an upper and a lower end, said housing containing a rechargeable battery;
a lamp extending from the upper end of the housing;
a 3-element, normally closed phono jack in the lower end of said housing opposite said lamp, said phono jack having an electrically conductive body element, a resilient conductive tip element and a conductive third element normally in contact with said conductive tip element;

first series circuitry including said battery, said lamp, said conductive tip element and said conductive third element for energizing said lamp from said battery; and

second series circuitry including said electrically conductive body of said jack, said battery, and said conductive tip element, said first series circuit being opened upon the insertion of a phono plug from a battery charger into said jack;

the improvement comprising a diode in said second series circuitry between said conductive body of said jack and said battery, the cathode end of said diode being attached to a positive terminal of said battery for preventing rapid dis-

charge of said battery by the insertion into said jack of a phono plug with short circuited body and tip contacts.

5,587,647

DUAL OUTPUT SYNCHRONOUS-INDUCTION STARTING/GENERATING SYSTEM
Madan L. Bansal, and Jayant G. Vaidya, both of Rockford, Ill., assignors to Sundstrand Corporation, Rockford, Ill.
Filed Jun. 30, 1995, Ser. No. 497,036
Int. Cl.⁶ H02P 9/00

U.S. Cl. 322—45

13 Claims



1. An electric power starter generator system, comprising:
a synchronous generator having a first rotor and a first polyphase stator output coupled to an ac bus;
an induction motor/generator having a second rotor and a second polyphase stator output;

a shaft coupled to said first rotor of said synchronous generator and to said second rotor of said induction motor/generator, said shaft being drivably coupled to an external prime mover, said shaft driving said synchronous generator and said induction motor/generator at a same speed thereby; and

a rectifier/inverter having ac terminals coupled to said second polyphase stator output and dc terminals coupled to a dc bus, said rectifier/inverter allowing bi-directional power flow therethrough.

5,587,648


POWER SUPPLY CIRCUIT FOR GENERATING AN INTERNAL POWER SUPPLY POTENTIAL BASED ON AN EXTERNAL POTENTIAL

Shinichi Jinbo, and Shigeru Mori, both of Hyogo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 25, 1995, Ser. No. 378,217
Claims priority, application Japan, Jan. 31, 1994, 6-009136
Int. Cl.⁶ G05F 1/613

U.S. Cl. 323—269

14 Claims



1. An internal power supply circuit generating an internal power supply potential based on an external power supply potential, comprising:

a first output node;

a second output node;

primary internal power supply potential supplying means for supplying said internal power supply potential to said first output node based on said external power supply potential;

first auxiliary internal power supply potential supplying means for selectively supplying said internal power supply potential to said first output node based on said external power supply potential;

second auxiliary internal power supply potential supplying means for supplying, when said first auxiliary internal power supply potential supplying means supplies said internal power supply potential, said internal power supply potential to said second output node based on said external power supply potential; and

switching means connected between said first and second output nodes for being rendered non-conductive when said first and second auxiliary internal power supply potential supplying means supply said internal power supply potential, respectively.


5,587,649

THERMAL PERFORMANCE MATCHED CURRENT LIMITING CIRCUIT, AND BATTERY USING SAME
Scott M. Garrett, Lawrenceville, Ga., assignor to Motorola, Inc., Schaumburg, Ill.

Filed Sep. 30, 1994, Ser. No. 316,678
Int. Cl.⁶ G05F 1/573

U.S. Cl. 323—369

9 Claims



1. A battery pack for powering an electronic device having a maximum current demand, in a volatile atmosphere, said battery pack comprising:

at least one battery cell;

current limiting means establishing a current level limit responsive to temperature such that a change of said current level limit over a temperature range matches the maximum current demand of said device over said temperature range, said current limiting means comprising:

a sense resistance means responsive to temperature and characterized by an effective resistance magnitude which has a negative temperature coefficient, said sense resistance means being electrically connected in series between said at least one cell and at least one of said electrical contacts;

a pass transistor having at least three terminals, the first and second of which are electrically connected in series between said sense resistance means and one of said electrical contacts;

a bias resistor for supplying bias to said pass transistor, said bias resistor being electrically connected between said third terminal of said pass transistor means and a voltage potential; and a bipolar transistor, having a base, emitter, and collector, forming a base-emitter junction, electrically connected such that said collector is electrically connected to said third terminal of said pass transistor means; and

a pair of electrical contacts for electrically coupling said battery pack to said device.


5,587,650

HIGH PRECISION SWITCHING REGULATOR CIRCUIT
Harold L. Massie, West Linn, Ore., assignor to Intel Corporation, Santa Clara, Calif.

Filed Dec. 13, 1994, Ser. No. 355,027
Int. Cl.⁶ G05F 1/575

U.S. Cl. 323—282

14 Claims



1. A switching regulator circuit comprising:

a primary feedback loop comprising a drive circuit, a switching transistor, an output stage, and a pre-drive circuit coupled in series, the pre-drive circuit further being coupled to the drive circuit, the primary feedback loop using negative feedback to output a predetermined output voltage at the output stage; and a feedback circuit coupled between an input and an output of the pre-drive circuit, the feedback using regenerative feedback to provide hysteresis which causes the primary feedback loop to oscillate.

5,587,651


ALTERNATING CURRENT SENSOR BASED ON PARALLEL-PLATE GEOMETRY AND HAVING A CONDUCTOR FOR PROVIDING SEPARATE SELF-POWERING

Ertugrul Berkcan, Schenectady, N.Y., and Raymond K. Seymour, Plainville, Conn., assignors to General Electric Company, Schenectady, N.Y.

Filed Nov. 21, 1994, Ser. No. 342,503
Int. Cl.⁶ G01R 1/04;33/00

U.S. Cl. 324—127

21 Claims



1. An alternating current sensor comprising:

a first conductor plate;

a second conductor plate positioned in spaced relationship relative to said first conductor plate and substantially facing said first conductor plate;

a third conductor plate for electrically interconnecting said first and second conductor plates to form a connected electrically conductive path along said first and second conductor plates; said first and second conductor plates shaped to form respective magnetic field constituents substantially around each of said first and second conductor plates during current flow along the conductive path;

sensing means for sensing changes in magnetic flux resulting from changes in said respective magnetic field constituents; a magnetic core situated about said conductive path; and


conductor means electrically interconnected with said first, second and third conductor plates for carrying substantially all current which flows along the conductive path and for producing a magnetic field through said magnetic core, said sensing means being spaced apart from said magnetic core.

5,587,652
ALTERNATING CURRENT SENSOR BASED ON PARALLEL-PLATE GEOMETRY AND HAVING A SHUNT FOR SELF-POWERING

Ertugrul Berkcan, Schenectady, N.Y.; Raymond K. Seymour, Plainville, Conn., and John C. Grzelecki, Schenectady, N.Y., assignors to General Electric Company, Schenectady, N.Y.
Filed Nov. 21, 1994, Ser. No. 342,505
Int. Cl.⁶ G01R 1/04; 33/00

U.S. Cl. 324—127

22 Claims



1. An alternating current sensor comprising:
 - a first conductor plate;
 - a second conductor plate positioned in spaced relationship relative to said first conductor plate and substantially facing said first conductor plate;
 - a third conductor plate for electrically interconnecting said first and second conductor plates to form a connected conductive path along said first and second conductor plates;
 - conductive means joined to said first conductor plate for providing at least one of a plurality of parallel branches for said conductive path, said at least one of said parallel branches comprising shunt means for diverting a predetermined portion of current which flows along the conductive path to produce a magnetic field about said at least one branch of said conductive path;
 - said first and second conductor plates shaped to form respective magnetic field constituents substantially around each of said first and second conductor plates during current flow along the conductive path;
 - sensing means for sensing changes in magnetic flux resulting from changes in said magnetic field constituents; and
 - a magnetic core situated about said at least one branch of said conductive path, said magnetic core being spaced apart from said sensing means.


5,587,653
SENSOR CHARACTERISTIC ADJUSTMENT CIRCUIT FOR ADJUSTING OUTPUT CHARACTERISTICS OF A SEMICONDUCTOR SENSOR

Tohru Araki, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
Filed Dec. 23, 1993, Ser. No. 172,192
Claims priority, application Japan, Dec. 28, 1992, 4-349167
Int. Cl.⁶ G01R 15/00

U.S. Cl. 324—132

13 Claims

1. A sensor characteristic adjustment circuit for adjusting the output characteristic of a sensor comprising:
 - data conversion means for converting serial data bits corresponding to an adjustment characteristic into parallel data bits, the serial data bits including first bits corresponding to an offset of said sensor characteristic adjustment circuit and



- second bits corresponding to a sensitivity of said sensor characteristic adjustment circuit, said data conversion means converting the first serial data bits into first parallel data bits and the second serial data bits into second parallel data bits;
- non-volatile memory means coupled to said data conversion means and having memory cells for storing parallel data bits output from said data conversion means;
- first adjustment means coupled to said non-volatile memory means and the sensor for setting the offset of said sensor characteristic adjustment circuit in accordance with the first parallel data bits, said first adjustment means comprising a first digital-to-analog converter coupled to said non-volatile memory means for effecting digital-to-analog conversion of the first parallel data bits, and a summing circuit coupled to the sensor and said first digital-to-analog converter for adding an output of said first digital-to-analog converter to an output of the sensor;
- second adjustment means coupled to said non-volatile memory means and the sensor for setting the sensitivity of said sensor characteristic adjustment circuit in accordance with the second parallel data bits, said second adjustment means comprising a second digital-to-analog converter coupled to said non-volatile memory means for effecting digital to analog conversion of the second parallel data bits, and an amplifier circuit coupled to said summing circuit;
- first buffer means connected between said non-volatile memory means and said first and second digital-to-analog converters; and
- second buffer means connected between said data conversion means and said first and second digital-to-analog converters.

5,587,654
METHOD AND APPARATUS FOR NOISE REDUCTION IN MAGNETIC MEDIA RECORDINGS


Ronald S. Indeck, Olivette, and Marcel W. Muller, St. Louis, Mo., both of Mo., assignors to Washington University, St. Louis, Mo.

Filed Apr. 9, 1993, Ser. No. 46,071

Int. Cl.⁶ G01R 33/12; G01N 27/72; G11B 5/02; 27/34

U.S. Cl. 324—225

13 Claims



13. A device for compensating a signal read from a magnetic medium for the remanent noise of said magnetic medium, said device including:
 - means for reading said signal from said magnetic medium with a first recording transducer;

means for saturating said magnetic medium with a second recording transducer, said second recording transducer being aligned with and closely spaced behind said first recording transducer to thereby saturate said magnetic medium after only a short time delay from reading;

means for reading said saturated magnetic medium with a third recording transducer to thereby continuously determine the remanent noise thereof, said third recording transducer being aligned with and closely spaced behind said first recording transducer to thereby determine said remanent noise after only a short time delay from saturating; and

means for continuously compensating said read signal with said remanent noise signal as both said signals are generated to thereby continuously produce a compensated signal in real time.

5,587,655
CONSTANT CURRENT CIRCUIT

Kazunori Oyabe, Kazuhiko Yoshida, and Tatsuhiko Fujihira, all of Nagano, Japan, assignors to Fuji Electric Co., Ltd., Kawasaki, Japan


Filed Aug. 11, 1995, Ser. No. 514,208

Claims priority, application Japan, Aug. 22, 1994, 6-196420

Int. Cl.⁶ G05F 3/04; 3/16

U.S. Cl. 323—312

11 Claims



1. A constant current circuit for supplying a constant current to a load comprising:
 - current source means for providing an input current, said input current having a predetermined value with temperature dependence;
 - reference transistor means having a connection point with the current source means, said reference transistor means receiving said input current and generating a reference voltage at the connection point;
 - voltage divider means connected to the connection point, said voltage divider means dividing said reference voltage to thereby generate a control voltage; and
 - output transistor means connected to the voltage divider means and the load for controlling an output current supplied to the load in response to said control voltage, temperature dependence of said output current being adjusted by setting voltage dividing ratio of said voltage divider means.

5,587,656
MAGNETIC RESONANCE IMAGING METHOD AND APPARATUS

Teunis R. Van Heels-Bergen, and Miha Fuderer, both of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Apr. 10, 1995, Ser. No. 419,491


Claims priority, application European Pat. Off., Apr. 8, 1994, 94200959

Int. Cl.⁶ G01V 3/00

U.S. Cl. 324—307

21 Claims

1. A method of determining a magnetic resonance (MR) distribution in a part of a body using an arrangement of multiple surface



coils, comprising determining separate component distributions from magnetic resonance signals obtained by means of separate ones of said surface coils, combining said component distributions to form a distribution I_{hom} which is optimized with respect to homogeneity and a distribution I_{SNR} which is optimized with respect to signal-to-noise ratio, and combining said distributions I_{hom} and I_{SNR} to form said MR distribution.

5,587,657
MAGNETIC RESONANCE IMAGING APPARATUS

Hitoshi Kanazawa, Tochigi-ken, Japan, assignor to Kabushiki Kaisha Toshiba, Tokyo, Japan


Filed Jan. 26, 1994, Ser. No. 187,603

Claims priority, application Japan, Jan. 26, 1993, 5-010589

Int. Cl.⁶ G01V 3/00

U.S. Cl. 324—309

18 Claims



1. A magnetic resonance imaging apparatus comprising:
 - static magnetic field applying means for applying a static magnetic field to an imaging region;
 - gradient magnetic field applying means for applying to said imaging region gradient magnetic field pulses along a phase encoding direction orthogonal to the direction of said static magnetic field;
 - transmitter/receiver means for transmitting an excitation pulse to a phantom placed within said imaging region and having a non-magnetic material that contains candidate nuclear species for magnetic resonance and has a periodic structure along the phase encoding direction and for receiving echo signals from said non-magnetic material, said echo signals being output as echo data;
 - sequence control means for controlling said gradient magnetic field applying means and said transmitter/receiver means in accordance with a predetermined sequence so as to generate a plurality of echo signals of varying echo times each time at each excitation pulse while varying the strength of said gradient magnetic field pulses so that varying phase encoding

amounts are applied to said echo signals and to acquire echo data required to reconstruct an MR image in split scans on the Fourier space;
display means for displaying the distribution of said echo data output from said transmitter/receiver means on the Fourier space; and
input means for adjusting a reference strength of said gradient magnetic field pulse in said gradient magnetic field pulse applying means so that echo data corresponding to spatial frequencies in said phase encoding direction which are the inverse and an integral multiple of a predetermined period of the periodic structure of said non-magnetic material in said phantom becomes maximum.


5,587,658
SHIMMING METHOD FOR NMR MAGNET USING UNSHIELDED GRADIENT SYSTEMS

Subramaniam Sukumar, Union City, Calif., assignor to Bruker Instruments, Inc., Billerica, Mass.

Filed Aug. 25, 1995, Ser. No. 519,290
Int. Cl.⁶ G01V 3/00

U.S. Cl. 324—309

21 Claims



1. A method of detecting a nuclear magnetic resonance (NMR) signal from each of a plurality of spatial points in a sample along a first direction, the method comprising the steps of:

- locating the sample in a static magnetic field and applying a gradient magnetic field to the sample in the first direction;
- applying a first radio frequency (RF) pulse to the sample;
- detecting, after a predetermined duration of time t_1 following application of the first RF pulse, an NMR signal from the sample;
- changing the magnitude of the gradient magnetic field at a rate which is sufficiently gradual that any eddy current induced in surrounding conductive materials as a result of the changing gradient magnetic field is small enough that any corresponding magnetic field generated by the eddy current is below a desired homogeneity of the static magnetic field;
- applying a second RF pulse to the sample; and
- detecting, after a duration equal to t_1 following application of the second RF pulse, an NMR signal from the sample.

5,587,659
TOWABLE ARRAY FOR MEASURING THE RESISTIVITY OF A TERRAIN UTILIZING A LOW POWER LEVEL

Kurt I. Sørensen, Blegindvej 102, DK-8362 Hørning, Denmark
PCT No. PCT/DK92/00023, § 371 Date Oct. 27, 1993, § 102(c)
Date Oct. 27, 1993, PCT Pub. No. WO92/13286, PCT Pub. Date Aug. 6, 1992


PCT Filed Jan. 23, 1992, Ser. No. 90,137

Claims priority, application Denmark, Jan. 24, 1991, 0122/91
Int. Cl.⁶ G01V 3/06; 3/15; 3/15

U.S. Cl. 324—357

18 Claims

1. In an apparatus for mapping the subsurface geology in an earth formation by means of an electrical profiling operation, wherein the apparatus comprises at least one current circuit for passing current from a current source via current electrodes



through a surface layer to be examined, and at least one voltage circuit with a measuring instrument for measuring via voltage electrodes a voltage signal generated by the current across the voltage electrodes, the improvement comprising:

- a plurality of mobile current electrodes and a plurality of mobile voltage electrodes for dragging across the earth formation, each of said current and voltage electrodes having a generally smooth earth engaging surface;
- means for mounting the current and voltage electrodes on a tow in a set configuration whereby the current and voltage electrodes can be towed in the set configuration from one place to another during the profiling operation; said means for mounting comprising respective wires running generally along the tow for connecting each of said current and voltage electrodes to the measuring instrument, each of said voltage electrodes having a single-ended electrode amplifier therein for simplifying the voltage signal so as to reduce interference between the voltage signal and other signals or current in the respective wires;
- a generator for generating a train of current pulses;
- filter means in the voltage circuit for isolating the voltage signal in phase with the current pulses whereby the measuring instrument can distinguish the voltage signal from noise signals.

5,587,660
PROCESS FOR EVALUATING THE REMAINING CHARGE IN AN ACCUMULATOR BATTERY


Philippe Chabbert, Rueil Malmaison; Alain Chatenay, Marly le Roi, and Dominique Meux, Toulouse, all of France, assignors to Thomson-CSF, Paris, France
PCT No. PCT/FR94/00934, § 371 Date Apr. 6, 1995, § 102(c)
Date Apr. 6, 1995, PCT Pub. No. WO95/04938, PCT Pub. Date Feb. 16, 1995

PCT Filed Jul. 26, 1994, Ser. No. 411,697

Claims priority, application France, Aug. 6, 1993, 93 09713
Int. Cl.⁶ G01N 27/42

U.S. Cl. 324—426

4 Claims



1. Process for evaluating the remaining charge in an accumulator battery, according to which the residual charge at the start of discharge is determined and the quantities of electricity extracted as and when the battery is used are added up, wherein account is taken of the quantities of charge which is not restorable instantaneously under the influence of the discharge rate and of the charge which is restorable by reducing the intensity of the current drawn from the battery.

5,587,661
DEVICE FOR INDICATING ERRORS IN A CONTROL LINE OF AN ELECTRIC CONTROL UNIT


Thomas Schneider, Markgroeningen; Stefan Grieser-Schmitz, Mainz, and Michael Walther, Ludwigsburg, all of Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany
Filed Dec. 14, 1994, Ser. No. 355,747

Claims priority, application Germany, Dec. 14, 1993, 43 42 586.0

Int. Cl.⁶ G01R 31/02; G08B 19/00

U.S. Cl. 324—556

8 Claims



1. An indicating device for an electric control unit having a control line, the indicating device comprising:
at least two resistors connected in series and defining a junction point therebetween, the control line being connected to the junction point; and
means, connected in series with the at least two resistors and coupled between a supply voltage and a ground, for indicating a break in the control line upon the occurrence of the break and for indicating a short-circuit between the control line and the supply voltage upon the occurrence of the short-circuit.

5,587,662
METHOD AND APPARATUS FOR NONDISRUPTIVELY MEASURING LINE IMPEDANCE AT FREQUENCIES WHICH ARE RELATIVELY CLOSE TO THE LINE FREQUENCY


Arthur W. Kelley, and Matthew B. Harris, both of Raleigh, N.C., assignors to North Carolina State University, Raleigh, N.C.

Filed Feb. 10, 1995, Ser. No. 386,702

Int. Cl.⁶ G01R 27/08

U.S. Cl. 324—713

19 Claims



1. Apparatus for nondisruptively measuring impedance of an energized electrical power line which carries electrical current at a predetermined line frequency, comprising:
means for generating a measurement current at a measurement frequency which is less than fifty times the predetermined line frequency;

means for coupling said generating means to the energized electrical power line, said coupling means including isolating means for only blocking the predetermined line frequency and frequencies which differ from the predetermined line frequency by substantially less than the predetermined line frequency;

current sensing means, electrically coupled to the energized electrical power line, for measuring a line current in said energized electrical power line at the measurement frequency;

voltage sensing means, electrically coupled to the energized electrical power line, for measuring a line voltage in the energized electrical power line at the measurement frequency; and

analyzing means, responsive to said current sensing means and said voltage sensing means, for determining a magnitude and a phase angle of impedance of the energized electrical power line at the measurement frequency, from the line current and the line voltage.

5,587,663
METHOD FOR MEASURING THE INDUCTANCE OF EACH RESONATOR OF A COUPLED-DUAL RESONATOR CRYSTAL


Gerald E. Roberts, and Michael E. Roberts, both of Lynchburg, Va., assignors to XTAL Technologies, Ltd., Carle Place, N.Y.

Continuation-in-part of Ser. No. 370,495, Jan. 9, 1995. This application Mar. 20, 1995, Ser. No. 407,078

Int. Cl.⁶ G01R 29/22

U.S. Cl. 324—727

23 Claims




1. A method of determining resonator inductances of a coupled-dual resonator crystal connected to a test fixture, the crystal having a piezoelectric plate, a first electrode on the plate, a common electrode on the plate, a second electrode on the plate, wherein the connection of the first electrode and the common electrode form a first resonator and the connection of the second electrode and the common electrode form a second resonator, the method comprising:

inserting the crystal in the test fixture in a first position;
connecting a frequency synthesizer to the first electrode and to a reference point;
applying a plurality of frequencies to the first electrode;
monitoring a phase response of the crystal with respect to frequency;
monitoring a time response of the crystal with respect to frequency;
determining time delay relative maxima from the time response;
determining a first set of critical frequencies corresponding to the time delay relative maxima;
measuring equivalent static capacitances of the first and second resonator; and
calculating the inductance of the first resonator using the first set of critical frequencies, whereby the resonator inductances are accurately determined for low and high frequency filters at any step in a crystal manufacturing process.

5,587,664
LASER-INDUCED METALLIC PLASMA FOR NON-CONTACT INSPECTION
 David Banitt, Soreq, and Moshe B. Shlomo, Maccabim, both of Israel, assignors to Exsight Ltd., Soreq, Israel
 Filed Jul. 12, 1995, Ser. No. 501,685
 Int. Cl.⁶ G01R 31/302

U.S. Cl. 324—752

18 Claims




1. An apparatus for testing an electrical part having a plurality of conductive paths thereon, comprising:
- (a) means for directing a laser pulse to impinge upon a conductor of the part under test so as to form a metallic plasma;
 - (b) at least one pair of probes which, along with said conductor and said plasma, form a part of an electrical circuit; and
 - (c) detector means responsive to the amount of conduction via said plasma between said conductor and said probes.

5,587,665
TESTING HOT CARRIER INDUCED DEGRADATION TO FALL AND RISE TIME OF CMOS INVERTER CIRCUITS
 Chun Jiang, San Jose, Calif., assignor to VLSI Technology, Inc., San Jose, Calif.
 Filed Jul. 18, 1995, Ser. No. 503,760
 Int. Cl.⁶ H03K 19/00; 19/0948

U.S. Cl. 326—16

10 Claims




6. A method for determining performance degradation of an inverter resulting from hot carrier stress, the method comprising the following steps:
- (a) forming a string of inverters on an integrated circuit, the string of inverters being connected in series, comprising the following substep:
 - (a.1) constructing every other inverter in the string of inverters using cascaded transistors so that performance of these every other inverters will not be degraded by hot carrier stress introduced in step (d);
 - (b) measuring propagation delay through the string of inverters of a transition from a first logic state to a second logic state;
 - (c) after step (b), introducing sufficient hot carrier stress to the string of inverters so that inverters not constructed using cascaded transistors will have degraded performance;

- (d) after step (c), measuring propagation delay through the string of inverters of the transition from the first logic state to the second logic state.

5,587,666
SENSE AMPLIFIER SLEW CIRCUITRY
 Mark E. Burchfield, Austin, Tex., assignor to Cyrix Corporation, Richardson, Tex.
 Filed Apr. 26, 1995, Ser. No. 428,983
 Int. Cl.⁶ H03K 19/017

U.S. Cl. 326—17

13 Claims




1. Slew rate circuitry for a sense amplifier comprising:
- (a) a pre-charge load device coupled between a positive voltage rail and an input on the sense amplifier; and,
 - (b) biasing means, coupled between the positive voltage rail and the input on the sense amplifier, for biasing the pre-charge load device in relation to varying capacitance on the input to the sense amplifier.

5,587,667
OUTPUT BUFFER CIRCUIT FOR HIGH-SPEED LOGIC OPERATION
 Daijiro Inami, Tokyo, and Yulchi Sato, Miyagi, both of Japan, assignors to NEC Corporation, Tokyo, Japan
 Filed Dec. 19, 1995, Ser. No. 575,118
 Claims priority, application Japan, Dec. 20, 1994, 6-316725
 Int. Cl.⁶ H03K 19/017

U.S. Cl. 326—17

20 Claims



1. An output buffer circuit comprising:
- a first FET whose gate is applied with a first input digital signal;
 - a second FET whose gate is applied with a second input digital signal;
 - said first FET and said second FET being serially connected to each other and operating to be opposite in logic state to each other; and
 - a current source for causing a bias current having the same direction as that of a drain current of said first FET to flow through said first FET in the OFF state;
- wherein a digital output signal is taken out from a connection point of said first FET and said second FET; and wherein a turn-on speed of said first FET from the pseudo-OFF state to the ON state is enhanced by said bias current.

5,587,668
SEMICONDUCTOR DEVICES UTILIZING NEURON MOS TRANSISTORS

Tadashi Shibata, 5-2, Nihondaira, Taibaku-ku, Sendai-shi, Miyagi-ken 980, Japan, and Tadahiro Ohmi, 1-17-301, Komega bukuro 2-chome, Aoba-ku, Sendai-shi, Miyagi-ken 980, Japan


PCT No. PCT/JP92/00347, § 371 Date Sep. 20, 1993, § 102(e) Date Sep. 20, 1993, PCT Pub. No. WO92/16971, PCT Pub. Date Oct. 1, 1992

PCT Filed Mar. 21, 1993, Ser. No. 119,157

Claims priority, application Japan, Mar. 21, 1991, 3-083152
 Int. Cl.⁶ H03K 19/017

U.S. Cl. 326—36

36 Claims




1. A semiconductor device, comprising:
- a first neuron MOS transistor having a first semiconductor region of one conductivity type disposed on a substrate, a first source region and a first drain region of a conductivity type opposite to said first semiconductor region provided within said first semiconductor region, a first floating gate electrode having a floating potential and isolated from said first source region and said first drain region, said first floating gate electrode capacitively coupled to said first semiconductor region by means of a first insulation film, a plurality of control gate electrodes capacitively coupled to said first floating gate electrode by means of a second insulation film;
 - a means for inputting a first signal into said first neuron MOS transistor connected to a first control gate electrode; and
 - a first inverter comprising at least one stage and having an input and an output, said input connected to said means for inputting a first signal and said output connected to a second control gate electrode.

5,587,669
PROGRAMMABLE APPLICATION SPECIFIC INTEGRATED CIRCUIT AND LOGIC CELL THEREFOR
 Andrew K. Chan, Palo Alto; John M. Birkner, Woodside, and Hua T. Chua, Los Altos Hills, all of Calif., assignors to QuickLogic Corporation, Calif.
 Continuation of Ser. No. 189,352, Jan. 31, 1994, Pat. No. 5,416,367, which is a continuation-in-part of Ser. No. 847,382, Mar. 6, 1992, abandoned, which is a continuation of Ser. No. 665,103, Mar. 6, 1991, Pat. No. 5,122,685. This application Mar. 3, 1995, Ser. No. 399,117
 Int. Cl.⁶ H03K 17/173

U.S. Cl. 326—38

11 Claims

1. A field programmable gate array, comprising:
- a first logic cell;
 - a second logic cell, said second logic cell having a plurality of input leads and at least one output lead;
 - a plurality of parallel wire segments disposed entirely between said first and second logic cells, each of said plurality of parallel wire segments extending in a first dimension toward said second logic cell, each respective one of said plurality of parallel wire segments being coupled to a respective one of said plurality of input leads or to said at least one output lead;
 - a power wire extending in said second dimension, said second dimension being substantially perpendicular to said first dimension, said power wire crossing each of said plurality of parallel wire segments; and



- a plurality of antifuses, a respective one of said plurality of antifuses being disposed to programmably couple said power wire to a respective one of said plurality of input leads, wherein no antifuse is disposed between said power wire and any one of said plurality of parallel wire segments coupled to said at least one output lead.


5,587,670

Patent Not Issued For This Number

5,587,671
SEMICONDUCTOR DEVICE HAVING AN OUTPUT BUFFER WHICH REDUCES SIGNAL DEGRADATION DUE TO LEAKAGE OF CURRENT
 Paul Zagar, and Troy Manning, both of Boise, Id., assignors to Micron Technology, Inc., Boise, Id.
 Filed May 5, 1994, Ser. No. 238,972
 Int. Cl.⁶ H03K 19/0944

U.S. Cl. 326—83

24 Claims



1. A semiconductor circuit device operating from at least one supply voltage and common, comprising:
- a pre-output circuit generating a control signal;
 - a logic circuit generating an enable signal in response to the control signal;
 - an NMOS output circuit having an input node coupled to the control signal and having an output node providing an output signal corresponding to the control signal, the input node of the NMOS output circuit coupled to common through parasitic resistance;
 - an oscillation circuit for providing an oscillating digital signal; and

a booster circuit, responsive to the oscillating digital signal and to the control signal being in one of two predetermined states, accumulating energy from the oscillating digital signal and providing a boost signal therefrom, also in response to the enable signal, for the input node of the NMOS output circuit to compensate for leakage current.

5,587,672


DYNAMIC LOGIC HAVING POWER-DOWN MODE WITH PERIODIC CLOCK REFRESH FOR A LOW-POWER GRAPHICS CONTROLLER

Ravi Ranganathan, Cupertino, and Deepraj S. Puar, Sunnyvale, both of Calif., assignors to NeoMagic Corp., Santa Clara, Calif.

Filed Sep. 25, 1995, Ser. No. 533,647
Int. Cl.⁶ H03K 19/00; 19/096

U.S. Cl. 326—93

16 Claims



1. A dynamic logic circuit comprising:
 - a plurality of dynamic logic cells, each dynamic logic cell having:
 - an output;
 - an input;
 - isolation means for electrically isolating the input from other dynamic logic cells in response to a clock;
 - logic means for performing a logic function, the logic means including a pull-up transistor for connecting the output to a power supply in response to a voltage on the input, the logic means also including a pull-down transistor for connecting the output to ground in response to a voltage on the input;
 - a clock generator for generating the clock to the isolation means in the plurality of dynamic logic cells, the clock generator comprising:
 - an operating mode clock input for receiving an operating mode clock;
 - a pulse generator for generating a first output, the first output receiving a recharging clock pulse when not in an operating mode, the pulse generator including constant voltage means for outputting to the first output a constant voltage between recharging clock pulses;
 - selector means for selecting as the clock to the plurality of dynamic logic cells the operating mode clock during an operating mode but selecting the first output from the pulse generator when not in the operating mode;
 - a clock synthesizer for generating the operating mode clock, the clock synthesizer generating a continuous stream of periodic clock pulses during the operating mode but not generating any pulses when not in the operating mode, the clock synthesizer being powered-down when not in the operating mode;
- whereby the plurality of dynamic logic cells are driven by the operating mode clock during operating mode but receive the recharging clock pulse and constant voltage when not in the operating mode.

5,587,673


CLOCK FREQUENCY MULTIPLYING AND SQUARING CIRCUIT AND METHOD

James B. MacDonald, Dracut, Mass., assignor to Wang Laboratories, Inc., Billerica, Mass.

Continuation of Ser. No. 135,113, Oct. 12, 1993, Pat. No. 5,475,322. This application Nov. 22, 1995, Ser. No. 562,228
Int. Cl.⁶ H03K 3/017

U.S. Cl. 326—93

9 Claims



1. A circuit for generating an output signal having a frequency that is a multiple of an input clock signal (CLKIN), comprising:
 - delay means having an input node and a plurality of output nodes (A, B, C), said input node for coupling to the input clock signal, said delay means being comprised of a first delay element means having an input for coupling to the input clock signal and an output coupled to a first one of said plurality of output nodes, a second delay element means having an input coupled to said output of said first delay element means and an output coupled to a second one of said plurality of output nodes, and a third delay element means having an input coupled to said output of said second delay element means and an output coupled to a third one of said plurality of output nodes, individual ones of said plurality of output nodes outputting a signal that preserves a waveform shape of the input clock signal and that is delayed with respect to the input clock signal and also with respect to others of said plurality of output nodes; and
 - combinatorial logic means having a first input for coupling to the input clock signal and a plurality of second inputs for coupling to said output nodes of said first, second, and third delay element means, said combinatorial logic means comprising first and second two-input gate means having inputs coupled to said input clock signal and to said plurality of output nodes of said first, second, and third delay element means, said combinatorial logic means further comprising a third, two-input gate means having its inputs coupled to outputs of said first and second gate means, said third gate means further having an output for outputting a signal having a frequency that is a multiple of a frequency of the input clock signal and that is synchronous therewith, said combinatorial logic means operating to logically combine signals emanating from said plurality of output nodes with the input clock signal without storing said input clock signal and without storing any of said signals emanating from said output nodes.

5,587,674

COMPARATOR WITH BUILT-IN HYSTERESIS

Eric J. Danstrom, Farmington Hills, Mich., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Continuation-in-part of Ser. No. 366,492, Dec. 30, 1994, abandoned. This application Apr. 7, 1995, Ser. No. 418,558
Int. Cl.⁶ H03K 5/22

U.S. Cl. 327—47

6 Claims

1. A comparator circuit comprising:
 - a differential input stage having a V⁺ input for receiving a first voltage, a V⁻ input for receiving a second voltage, having a first bias voltage input, having a second bias voltage input, and having an output;

5,587,676

DRIVER CIRCUIT

Vivek Chowdhury, Heston, United Kingdom, assignor to S GS - Microelectronics Limited, Buckingham, England


Filed Sep. 27, 1994, Ser. No. 312,877

Claims priority, application United Kingdom, Oct. 1, 1993, 9320246

Int. Cl.⁶ H03K 17/26

U.S. Cl. 327—108

18 Claims



- an output stage having an input for receiving the output of the differential input stage and having an output, the output stage comprising at least one inverter; and
- a bias circuit having a bias voltage connected to the first bias voltage input of the differential input stage and having a hysteresis circuit wherein the hysteresis circuit comprises:
 - a means for selectively applying the bias voltage to the second bias voltage input of the differential amplifier, wherein the means for selectively applying the bias voltage comprises:
 - a first transistor having a current path between the bias voltage and the second bias voltage input of the differential input stage and having a control element connected to the input of the at least one inverter of the output stage, and
 - a second transistor having a current path connected between the second bias voltage input and ground, and having a control element connected to the output of the at least one inverter of the output stage.

5,587,675

MULTICLOCK CONTROLLER


Kenneth C. Schmitt, Colorado Springs, Colo., assignor to AT&T Global Information Solutions Company, Dayton, Ohio; Hyundai Electronics America, San Jose, Calif., and Symbios Logic Inc., Fort Collins, Colo.

Filed Aug. 12, 1993, Ser. No. 105,990

Int. Cl.⁶ H03K 17/00

U.S. Cl. 327—99

30 Claims



1. A multi-clock controller circuit, comprising:
 - a first input for receiving a first type of input clock signal;
 - a second input for receiving a second type of input clock signal;
 - an output for providing a circuit output clock signal;
 - a circuit device for sensing and selecting which one of the two inputs has an active clock signal applied thereto, and for coupling said active clock signal to said output; and
 - a synchronizer stage for delaying the output signal for a period sufficient to avoid non-standard output pulses during power-down of the multi-clock controller circuit.

5,587,677

COMBINED CMOS AND NPN OUTPUT PULL-UP CIRCUIT

Davoud Samani, Saint Martin Le Vinoux, France, assignor to SGS-Thomson Microelectronic S.A., Saint Genis Pouilly, France


Filed Dec. 20, 1994, Ser. No. 359,700

Claims priority, application European Pat. Off., Dec. 23, 1993, 93420510

Int. Cl.⁶ H03K 5/12

U.S. Cl. 327—108

36 Claims



1. A BiCMOS output stage comprising:
 - a first NPN bipolar transistor connected between an output terminal and a positive supply voltage;
 - a first P-MOS transistor connected in parallel with the first NPN bipolar transistor;
 - a first inverter receiving an input signal and controlling a gate of the first P-MOS transistor;

a second inverter receiving the output of the first inverter for controlling a base of the first NPN transistor;
 a first N-MOS transistor connected between the output terminal and a negative supply voltage;
 a second NPN bipolar transistor connected in parallel with the first N-MOS transistor;
 a control circuit for switching on said second NPN transistor when said input signal is such that said output terminal must be pulled down; and
 a third inverter having an input connected to the output terminal and whose output controls the gate of said first N-MOS transistor and provides an active high signal to said control circuit for switching off said second NPN bipolar transistor.

5,587,678

INTEGRATED CIRCUIT HAVING AN OUTPUT STAGE WITH A MILLER CAPACITOR

Eise C. Dijkmans, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed May 9, 1995, Ser. No. 437,750

Claims priority, application European Pat. Off., May 9, 1994, 94201298

Int. Cl.⁶ H03F 3/26; H03K 19/003

U.S. Cl. 327—108

7 Claims



1. An integrated circuit, comprising an output stage with an input which is coupled to a first and a second control electrode of a first and a second output stage current channel, respectively, and an output which is connected to a first and a second supply terminal via the first and the second current channel, respectively, said output stage switching over, under the control of a signal on the input, from a first state (L) in which the first and the second current channel are conductive and non-conductive, respectively, to a second state (H) in which the first and the second current channel are non-conductive and conductive, respectively, the output being coupled to the first control electrode via a series connection of a Miller capacitor and switching means, said integrated circuit being characterized in that it comprises means for rendering the switching means non-conductive ahead of the switching over from the first state (L) to the second state (H).

5,587,679

PULSE GENERATOR INCLUDING SLEW RATE CONTROLLER WITHOUT COMPLEMENTARY TRANSISTORS

Makoto Imamura, Tokyo, Japan, assignor to Yokogawa Electric Corporation, Tokyo, Japan


Filed May 8, 1995, Ser. No. 436,693

Int. Cl.⁶ H03K 5/12

U.S. Cl. 327—170

12 Claims

1. A pulse generator for generating a pulse, comprising:



buffer means for receiving a differential signal and for producing an output signal, said buffer means comprising a pair of selectively controllable current sources;

a first differential amplifier for receiving said output signal from said buffer means and for producing another differential signal, said first differential amplifier comprising a positive input terminal, a negative input terminal, a positive output terminal, and a negative output terminal;

a first capacitor connected between said positive input terminal and said negative output terminal of said first differential amplifier, and being caused to be charged by said buffer means and selectively controlling said first differential amplifier;

a second capacitor connected between said negative input terminal and said positive output terminal of said first differential amplifier, and being caused to be charged by said buffer means and selectively controlling said first differential amplifier;

wherein said another differential signal is obtained at connections of said first and second capacitors and said positive and negative input terminals of said first differential amplifier; and means for receiving said another differential signal and in response thereto for producing said pulse, whereby a rising slew rate of said pulse is selectively controlled by one of said pair of current sources of said buffer means and a falling slew rate of said pulse is selectively controlled by the other of said pair of current sources of said buffer means without the use of complementary transistors.

5,587,680

PULSE GENERATOR WITH CHARGE PUMP


Stephen W. Smith, Raleigh, N.C., assignor to MTS Systems Corporation, Eden Prairie, Minn.

Filed Jun. 30, 1995, Ser. No. 497,210

Int. Cl.⁶ G06F 1/04

U.S. Cl. 327—291

23 Claims



1. A current pulse generation system for generating current pulses on an electrical pulse conductor, said current pulse generation system comprising:

a variable magnitude pulse former having a magnitude control input, a pulse initiation input, and an output electrically connected to said pulse conductor, said variable magnitude current pulse former being capable of forming a current pulse at said output thereof upon an initiation signal being provided to said initiation input thereof with said current pulse having a magnitude substantially determined by a magnitude control signal provided at said magnitude control input thereof;

a magnitude control signal generator having an input, and having an output electrically connected to said variable magnitude pulse former magnitude control input, said magnitude control signal generator providing a signal at said output thereof having a magnitude determined by a signal applied to said input thereof;

a current pulse magnitude sensor having an input electrically connected to said pulse conductor and having an output, said current pulse magnitude sensor providing an output signal on said output thereof indicative of magnitudes reached by current pulses occurring on said pulse conductor; and

a pulse controller having an input electrically coupled to said current pulse magnitude sensor output, a selection output electrically connected to said magnitude control signal generator input, and an initiation output electrically connected to said variable magnitude pulse former initiation input, said pulse controller being capable of providing initiation signals on selected occasions of selected magnitudes on said initiation output thereof.

5,587,681

DC RESTORATION CIRCUIT

Ian G. Fobbeister, Gloucestershire, United Kingdom, assignor to Plessey Semiconductors Limited, United Kingdom


Filed Oct. 18, 1994, Ser. No. 324,911

Claims priority, application United Kingdom, Oct. 29, 1993, 9322273

Int. Cl.⁶ H03K 5/08

U.S. Cl. 327—307

4 Claims



1. A D.C. restoration circuit for digital data signals appearing differentially between first and second input lines, said data signals being superimposed on a variable D.C. level, comprising: first and second capacitors; means for connecting said first capacitor between said first input line and a first output of said D.C. restoration circuit; means for connecting said second capacitor between said second input line and a second output of said D.C. restoration circuit; first and second switching transistors each having emitter, base and collector electrodes; means for connecting the emitter electrode and the collector electrode of said first switching transistor to said first output and to said second output respectively; means for connecting the emitter electrode and the collector electrode of said second switching transistor to said second output and to said first output, respectively; and means responsive to signal voltages at said first and second outputs to forward bias the base electrodes of said first and second switching transistors with respect to their respective emitter electrodes when the signal voltages at said first and second outputs exceed respective predetermined values.

5,587,682

FOUR-QUADRANT BICMOS ANALOG MULTIPLIER


Gianluca Colli, Sannazzaro De Burgondi; Massimo Franciotta, Pavia, and Rinaldo Castello, Arcore, all of Italy, assignors to SGS-Thomson Microelectronics S.r.l., Brianza, Italy

Filed Mar. 30, 1995, Ser. No. 413,772

Int. Cl.⁶ G06G 7/16; H03K 5/22

U.S. Cl. 327—357

14 Claims



1. An analog multiplier circuit, comprising:

a first transconductance stage, comprising:

first and second differential legs, each comprising a bipolar transistor and a MOS transistor connected in series, wherein the MOS transistor in the first differential leg has a source connected to a first common node and a gate for receiving a first input voltage and wherein the MOS transistor in the second differential leg has a source connected to the first common node and a gate for receiving a second input voltage;

a first reference leg, for biasing the bipolar transistors in the first and second differential legs into an active state, so that the MOS transistors in the first and second differential legs are biased into the triode region;

a second transconductance stage, cross-coupled with the first transconductance stage, and comprising:

third and fourth differential legs, each comprising a bipolar transistor and a MOS transistor connected in series, wherein the MOS transistor of the third differential leg has a source connected to a second common node and a gate for receiving the second input voltage and wherein the MOS transistor of the fourth differential leg has a source connected to the second common node and a gate for receiving the first input voltage; and

a second reference leg, for biasing the bipolar transistors in the third and fourth differential legs into an active state, so that the MOS transistors in the third and fourth differential legs are biased into the triode region;

a first sum current source, connected between the first and second common nodes of the first and second transconductance stages and a reference voltage; and

a third transconductance stage, comprising:

fifth and sixth differential legs, each comprising a bipolar transistor and a MOS transistor connected in series, wherein the MOS transistor in the fifth differential leg has a source connected to a third common node and a gate for receiving a third input voltage and wherein the MOS transistor in the sixth differential leg has a source connected to the third common node and a gate for receiving a fourth input voltage;

a third reference leg for biasing the bipolar transistors of the fifth and sixth differential legs into an active state, so that the MOS transistors in the fifth and sixth differential legs are biased in the triode region; and

a second sum current source, connected between the third common node of the third transconductance stage and the reference voltage;

wherein the bipolar transistor in the fifth differential leg has a collector connected to the reference leg of the first transconductance stage;

and wherein the bipolar transistor in the sixth differential leg of the third transconductance stage has a collector connected to the reference leg of the second transconductance stage.

5,587,683

BOOSTER CIRCUIT DEVICE

Masayuki Kawasaki, Yasunori Kuwasima, Hidehiko Tachibana, all of Ooita; Syuji Katsuki, and Akihiro Sueda, both of Yokohama, all of Japan, assignors to Kabushiki Kaisha Toshiba, Tokyo, Japan


Filed Dec. 6, 1994, Ser. No. 350,353

Claims priority, application Japan, Dec. 9, 1993, 5-309076

Int. Cl. G05F 1/10; 3/02

U.S. Cl. 327—538

7 Claims



1. A booster circuit device comprising:

- a liquid crystal drive circuit for outputting a signal to a liquid crystal display panel;
- a timing circuit for outputting a select signal responsive to changes in the signal outputted by the liquid crystal drive circuit, wherein the timing circuit outputs a high frequency clock select signal in response to a high current demand in the liquid crystal drive circuit when the signal outputted by the liquid crystal drive circuit changes, and outputs a low frequency clock select signal in response to a low current demand in the liquid crystal drive circuit when the signal outputted by the liquid crystal drive circuit does not change;
- a drive signal select circuit for selecting a low frequency clock having a first frequency when said timing circuit outputs the low frequency clock select signal, and for selecting any one of at least two high frequency clocks having frequencies higher than the first frequency when said timing circuit outputs the high frequency clock select signal, the selected clock being outputted as a drive signal;
- a booster circuit for supplying a supply voltage to said liquid crystal drive circuit on the basis of the drive signal outputted by said drive signal select circuit; and
- control means for comparing the supply voltage outputted by said booster circuit with a reference voltage when the said timing circuit outputs the high frequency clock select signal, and for controlling said drive signal select circuit to sequentially select a higher frequency clock than a previously selected high frequency clock from the at least two high frequency clocks until the supply voltage reaches the reference voltage.

5,587,684

POWER DOWN CIRCUIT FOR USE IN INTEGRATED CIRCUITS

Jose A. Salcedo, Livermore, Calif., assignor to Exar Corporation, San Jose, Calif.


Filed May 12, 1995, Ser. No. 440,272

Int. Cl. G05F 1/10; H03K 17/22

U.S. Cl. 327—538

8 Claims

1. A packaged analog integrated circuit having a package pin which receives a reference voltage from an external source for use



as a reference in analog/digital voltage conversions, said circuit comprising a plurality of circuit stages each receiving electrical power from a power source, conductor means for applying said reference voltage from said external source to said integrated circuit, and power control circuitry for selectively controlling electrical power to said circuit stages in response to said reference voltage, said power control circuitry including switch means for connecting and disconnecting said power source to said circuit stages, logic means responsive to said reference voltage for controlling said switch means, said logic means including a comparator for comparing said reference voltage to an internal threshold voltage, and, means for generating said threshold voltage from said power source.

5,587,685

SYSTEM FOR SUPPRESSING POWER TRANSIENTS WHEN CONNECTING A DISK DRIVE IN AN OPERATING RAID SYSTEM

Christopher W. Johansson, Horseshoe Bend, Id., assignor to Hewlett-Packard Company, Palo Alto, Calif.


Continuation of Ser. No. 331,468, Oct. 31, 1994, abandoned.

This application Nov. 22, 1995, Ser. No. 562,263

Int. Cl. G05F 3/02

U.S. Cl. 327—546


8 Claims



1. A system of control for electrically interconnected discrete devices, comprising:

- a. an electrical power supply having at least a first and a second voltage terminal;
- b. a plurality of discrete devices connected to said electrical power supply;
- c. a device controller for electrically controlling said discrete devices in a predetermined functional relationship;
- d. at least a first and second transient suppression circuit (TSC) coupled to at least one of said plurality of discrete devices, for suppressing transient currents, said first TSC comprising a first active circuit element, and said second TSC comprising a second active circuit element, and each said active circuit element having an output terminal connected to said at least one discrete device and having an active circuit element input;

- e. said first transient suppression circuit further comprising a first capacitor and voltage divider circuit for generating a time varying voltage signal input to said first active circuit element to control conduction of said first active circuit element;
- f. said second transient suppression circuit further comprising a second capacitor and voltage divider circuit for generating a time varying voltage signal input to said second active circuit element to control conduction of said second active circuit element; and,
- g. connector means for coupling one of said power supply voltage terminals to said first active circuit element input and to said first and second capacitor and voltage divider circuits, and the other of said power supply voltage terminals to said second active circuit element input, and wherein said connector means include, a plurality of pin connectors each having a substantially similar length.



5,587,686

TIME DOMAIN SIGNAL FILTER


Salil Suri, Fremont, and Sassan Teymour, Saratoga, both of Calif., assignors to Adaptec, Inc., Milpitas, Calif.

Filed Sep. 2, 1994, Ser. No. 300,284

Int. Cl. H03K 5/00; 9/06

U.S. Cl. 327—552

21 Claims



1. A time domain signal filter comprising:

- a signal replacement circuit having:
 - a signal replacement circuit input line,
 - a first signal replacement circuit output terminal and
 - a second signal replacement circuit output terminal,
 wherein in response to a predetermined signal change on said signal replacement circuit input line, said signal replacement circuit generates an active signal on said first signal replacement circuit output terminal for a predetermined time period; and
- a signal switching circuit having:
 - a first signal switching circuit input line connected to said first signal replacement circuit output terminal,
 - a second signal switching circuit input line connected to said first signal replacement circuit output terminal,
 - a third signal switching circuit input line connected to said second signal replacement circuit output terminal, and
 - a signal switching circuit output terminal,
 wherein said signal switching circuit disconnects said first signal switching circuit input line from said signal replacement circuit output terminal and connects said third signal switching circuit output terminal for said predetermined time period in response to said active signal on said second signal switching circuit input line; and
- further wherein said predetermined signal change occurs at least from a first signal level to a second signal level.

5,587,687

MULTIPLIER BASED TRANSCONDUCTANCE AMPLIFIERS AND TRANSCONDUCTANCE CONTROL CIRCUITS

William J. Adams, Irvine, Calif., assignor to Silicon Systems, Inc., Tustin, Calif.

Filed Feb. 2, 1995, Ser. No. 383,310

Int. Cl. H03F 3/45

U.S. Cl. 330—253

32 Claims

1. A transconductance amplifier comprising:

- a FET differential input stage, the input stage having a current output; and,
- a Gilbert multiplier output stage coupled to the output of the input stage to amplify the current output of the FET differential input stage;
- the FET differential input stage having a pair of FET transistors each having a source, a drain and a gate, the drains of the pair of FET transistors being directly coupled to the Gilbert multiplier output stage, the sources of the pair of FET transistors being coupled to a bias voltage and the gates of the pair of FET transistors forming the differential input thereof.

5,587,688

DIFFERENTIAL AUTOMATIC GAIN-CONTROL AMPLIFIER HAVING AN ENHANCED RANGE

Mark M. Mulbrook, Marion, Iowa, assignor to Rockwell International Corp., Seal Beach, Calif.


Continuation of Ser. No. 331,833, Oct. 31, 1994, abandoned.

This application Nov. 1, 1995, Ser. No. 551,358

Int. Cl. H03F 3/45

U.S. Cl. 330—253

2 Claims



1. A differential amplifier circuit comprising:

- a first pair of transistors, each coupled to a first common driving signal at their gate electrode;
- a second pair of transistors, each coupled to a second common driving signal at their gate electrode;
- a plurality of current sources coupled to each pair of transistors via a source electrode of each transistor;
- a pair of input transistors electrically coupled in parallel between the plurality of current sources and a source electrode of a transistor from the first and second pair of transistors; and
- a pair of resistors coupled in series between the first and second input transistors for circuit stability;
- wherein a drain electrode of a first transistor from the first pair of transistors is coupled in common to a drain electrode of a first transistor from the second pair of transistors, and the drain electrodes of the second transistors from the first and second pair of transistors are coupled in common, thereby

establishing an output signal of said circuit obtained across the paired drain electrodes of the first and second pair of transistors; and
wherein the second driving signal is an inverted signal of the first driving signal and thereby extends the differential amplifier circuit range by increasing the attenuation level of the circuit.

5,587,689

VOLTAGE CONTROLLED AMPLIFIER WITH A NEGATIVE RESISTANCE CIRCUIT FOR REDUCING NON-LINEARITY DISTORTION


Derek F. Bowers, Sunnyvale, Calif., assignor to Analog Devices, Inc., Norwood, Mass.

Filed Sep. 28, 1995, Ser. No. 536,497

Int. Cl.⁶ H23G 3/32; H03F 3/45

U.S. Cl. 330-254

8 Claims



1. A voltage controlled amplifier (VCA), comprising:
an input differential stage including a pair of differentially connected primary transistors that respond to an input signal by producing a differential signal current at a pair of control terminals, said transistors having different pn junction voltages that induce non-linearity distortion in the differential signal current which produces a differential error voltage between the control terminals;
a gain control stage that has a gain control input, said gain control stage producing a differential output current and a differential control current that sum together to provide said differential signal current and responding to a gain control signal applied to said gain control input to apportion a fraction G of the differential signal current to the differential output current to set the gain of the VCA; and
a negative resistance circuit connected between said control terminals to compensate for the differential error voltage and thereby alter said differential output current to reduce its non-linearity distortion.

5,587,690

RING RESONATOR OSCILLATOR USABLE IN FREQUENCY SYNTHESIZERS AND COMMUNICATION APPARATUS

Hiroyuki Yabuki, Kawasaki; Morikazu Sagawa, Tokyo, and Mitsuo Makimoto, Yokohama, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Japan

Filed Jul. 31, 1995, Ser. No. 509,663


Claims priority, application Japan, Aug. 11, 1994, 6-189499; Sep. 22, 1994, 6-227923; Jan. 24, 1995, 7-009085

Int. Cl.⁶ H03B 5/18; H30L 7/099

U.S. Cl. 331-2

46 Claims

1. An oscillator comprising:
a ring resonator;



an oscillation circuit having a negative resistance active circuit coupled to a first point on said ring resonator for oscillating at an oscillation frequency and resonating said resonator; and an output terminal, coupled to a second point on said ring resonator where a voltage is substantially zero with respect to said oscillation frequency when said ring resonator resonates, for outputting a second harmonic frequency signal.

5,587,691

DIGITAL TRIMMING FOR FREQUENCY ADJUSTMENT


Hiroshi Yabe, and Tsutomu Ogihara, both of Suwa, Japan, assignors to Seiko Epson Corporation, Tokyo-tu, Japan

Division of Ser. No. 47,279, Apr. 19, 1993. This application Jun. 7, 1995, Ser. No. 478,782

Claims priority, application Japan, Apr. 17, 1992, 4-097888; May 14, 1992, 4-122154; Feb. 22, 1993, 5-031783

Int. Cl.⁶ H03B 19/00

6 Claims



1. A digital trimming apparatus for generating a time reference signal from a basic oscillation frequency supplied by an oscillation circuit, comprising:
digital trimming amount-to-pulse number converting means for generating a start control pulse signal within one digital trimming time period based on the basic oscillation frequency and a correction data, the correction data designating a digital trimming amount to be executed within the one digital trimming time period, a number of pulses in the start control pulse signal corresponding to the correction data; and
digital trimming amount applying means for generating the time reference signal from the basic oscillation frequency by executing a digital trimming operation by the digital trimming amount in response to the start control pulse signal, said digital trimming amount applying means comprising:
complementary signal forming means for forming an in-phase signal and a reverse phase signal based upon said basic oscillation signal; and
signal selecting means for selectively outputting said in-phase signal and said reverse phase signal.

5,587,692

COMMON MODE CURRENT CANCELLATION IN TWISTED PAIRS

Martin H. Graham, Berkeley, and Matthew Taylor, Pleasant Hill, both of Calif., assignors to Tut Systems, Inc., Pleasant Hill, Calif.


Filed Nov. 28, 1994, Ser. No. 345,111

Claims priority, application WIPO, May 18, 1994, PCT/US94/05618

Int. Cl.⁶ H04B 3/30

U.S. Cl. 333-12

3 Claims



2. An improved punch down block for connecting together a first and a second twisted pair lines, each of the lines having a first and a second wire, comprising:
a board;
a first, second, third and fourth forked pins mounted on the board; and
a balun for canceling common mode currents resulting from different impedances in the first and second wires of the first and second twisted pair lines, the balun mounted on the board having four leads, each connected to one of the four pins such that a first electrical path exists through the balun between the first and third pins and a second electrical path exists between the second and fourth pins.

5,587,693

POLARIZED ELECTROMAGNETIC RELAY


Christopher Fear, Brighton, Mich., assignor to Siemens Electromechanical Components, Inc., Princeton, Ind.

Filed Aug. 7, 1995, Ser. No. 512,001

Int. Cl.⁶ H01H 51/22

U.S. Cl. 335-78

20 Claims



1. A polarized electromagnetic relay, comprising:
an insulating base defining a bottom plane;
an electromagnet block on the base having a core, means for exciting a coil including a bobbin and at least one winding about the core, and a pair of pole pieces extending perpendicularly from the ends of said core;

an elongate armature pivotally supported at its central portion to be movable about a center pivot axis for angular movement between two contact operating positions, either end portion of the armature on either side of the pivot axis defining an air gap with one of said pole pieces;

a permanent magnet coupled magnetically between said core and said armature so as to induce the same magnetic poles in both said pole pieces and to provide an opposite pole in closely adjacent relationship to said central portion of the armature;

at least one movable contact spring fixedly connected to the armature at a portion intermediate the ends thereof and being formed with contact arms in the vicinity of either armature end portion, said contact arms carrying movable contacts to be moved according to the armature movement in and out of contact with corresponding fixed contacts mounted on said base;

a pair of torsion pivot arms extending transversely in opposite directions from said at least one contact spring along the pivot axis of said armature, a distal end of either pivot arm being fixedly connected to a support being part of or fixedly connected to said electromagnet block and extending around either side of the armature; and

a conductor connecting said contact arms with a movable contact terminal mounted on said base; wherein said at least one movable contact spring is made from a material having high resilience and said conductor is made of flexible construction from a material having high conductivity.

5,587,694

REACTOR WITH CORE GAP SPACERS


Tetsuya Minato, Neyagawa; Toshimitsu Yonehara, Osaka; Junichi Teranishi, Ikoma; Shohei Toyoda, Kyoto; Toshiaki Bito, Neyagawa, and Kazushige Takashima, Kawanishi, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka-fu, Japan

Filed Dec. 28, 1994, Ser. No. 365,157

Int. Cl.⁶ H01F 15/02; 27/26; 27/30

U.S. Cl. 336-65

13 Claims



1. A reactor comprising:
a pair of coils;
a pair of first iron cores disposed in parallel and respectively extending through said coils, each of said first iron cores being formed of laminated electromagnetic steel plates;
a pair of second iron cores abutted against said first iron cores, via core gap spacers, such that a square-shaped magnetic path is formed, each of said second iron cores being formed of laminated electromagnetic plates;
wherein one of said first and second pairs of iron cores constitutes an outer pair of iron cores and the other of said first and second pairs of iron cores constitutes an inner pair of iron cores, and said inner pair of iron cores is sandwiched between said outer pair of iron cores;
wherein each of said iron cores of said outer pair of iron cores is a trapezoid-shaped iron core having four contiguous straight sides, two of which are parallel to one another;
wherein for each of said trapezoid-shaped iron cores, one of said two parallel sides is a short parallel side and the other of said two parallel sides is a long parallel side which is longer than said short parallel side; and

wherein said long parallel side of each of said trapezoid-shaped iron cores is disposed between said short parallel sides of said trapezoid-shaped iron cores, respectively.

5,587,695


MEASURING TRANSFORMER FOR SOLID-STATE ELECTRICITY METERS

Petrus Warmerdam, Wetzikon, Switzerland, assignor to Zellweger Luwa AG, Switzerland
Continuation of Ser. No. 988,313, Dec. 9, 1992, abandoned.
This application Aug. 8, 1994, Ser. No. 287,004
Claims priority, application Switzerland, Dec. 13, 1991, 03672/91

Int. Cl.⁶ H01F 27/28

U.S. Cl. 336—84 R

23 Claims



1. Apparatus for measuring electricity, comprising:
a primary conductor having a helical body for carrying current to be measured, said helical body being shaped to define an interior and having a helical groove;
a secondary coil which is inserted into the interior of said primary conductor such that said helical body surrounds the secondary coil with at least one turn to magnetically couple said primary conductor and said secondary coil; and
a winding provided between said primary conductor and said secondary coil for reducing capacitive coupling between said primary conductor and said secondary coil.

5,587,696


HIGH RESISTANCE POLYSILICON RESISTOR FOR INTEGRATED CIRCUITS AND METHOD OF FABRICATION THEREOF

Chung-Hui Su; Mong-Song Liang, both of Hsin-chu; Shou-Gwo Wu, Hsinchu County, and Chen-Jong Wang, Hsinchu, all of Taiwan, assignors to Taiwan Semiconductor Manufacturing Company Ltd., Hsin-Chu, Taiwan
Filed Jun. 28, 1995, Ser. No. 496,018

Int. Cl.⁶ H01C 1/012

U.S. Cl. 338—314

15 Claims



1. A multi-layer polysilicon resistor for use within an integrated circuit comprising:


a first polysilicon layer formed over an insulating layer upon a semiconductor substrate, the first polysilicon layer being formed at a first deposition temperature;
a minimum of a second polysilicon layer formed directly upon the first polysilicon layer, the second polysilicon layer being formed at a second deposition temperature, where the first deposition temperature and the second deposition temperature are in the range of from 450 to 620 degrees centigrade and the difference in temperature between the first deposition temperature and the second deposition temperature is greater than 10 degrees centigrade whereby there is formed a multi-layer polysilicon resistor of higher resistance than a single layer polysilicon resistor of equivalent aggregate thickness.

5,587,697

CHIME ALARM APPARATUS

Michael P. Rent, Box 287, Bridgetown, N.S., B0S 1C0, Canada
Filed Nov. 29, 1994, Ser. No. 350,103
Int. Cl.⁶ G08B 3/00; G10K 1/00
U.S. Cl. 340—392.4

6 Claims



1. Chime alarm apparatus comprising:
a housing having an axis;
means for suspending said housing from rigid support means;
elongate support means for supporting a disc-shaped contact member, said support means having upper and lower ends,
means for suspending said elongate support means at its upper end from said housing and substantially coaxially therewith, whereby said elongate support means may swing laterally relative to said housing;
said disc-shaped contact member supported by said elongate support means intermediate the ends thereof, said lower end of said elongate support means including pendant means whereby the elongate support means may be caused to move laterally by an external force contacting said pendant means;
a plurality of chime members each having upper and lower ends and being suspended from said housing peripherally outwardly of, and spaced a selected distance from, said elongate support means and said disc-shaped contact member, each said chime member having an area of electrical contact between its ends, said pendant means being normally below the lower ends of said second members;
said disc-shaped contact member and said chime members being of a material whereby a chime sound is produced when the contact member moves laterally and contacts the area of contact of at least one of said chime members;
an electric circuit including in said circuit, a source of power, said disc-shaped contact member, said area of electrical contact of at least one of said chime members and including an

alarm means separate from said chime members, whereby when said disc-shaped contact member contacts said area of contact of said least one chime member, the electric circuit is closed and said alarm means in the electric circuit is activated.


5,587,698

AUTOMATIC TIRE PRESSURE CONTROL SYSTEM FOR A VEHICLE

Robert A. Genna, 4 Talbot La., Greenwich, Conn. 06830
Continuation-in-part of Ser. No. 831,187, Feb. 5, 1992, abandoned. This application Feb. 28, 1995, Ser. No. 395,969
Int. Cl.⁶ B60C 23/00

U.S. Cl. 340—442

6 Claims



1. An automatic tire pressure control system for a vehicle, comprising:
means for compressing air;
means for delivering said compressed air to a tire of said vehicle;
first sensing means for sensing the air pressure in said tire;
first comparing means for comparing the sensed tire air pressure with at least a first preset value;
second sensing means for sensing the air temperature in said tire;
second comparing means for comparing said sensed tire air temperature with at least a second preset value;
third sensing means for sensing a surface temperature of said tire;
third comparing means for comparing said sensed tire surface temperature with at least a third preset value;
means for activating the delivering means to deliver air to and inflate said tire when said first comparing means determines that said sensed tire air pressure is below said first preset value;
means for deactivating the delivering means to stop the delivery of air to and inflation of said tire when said first comparing means determines that said sensed tire air pressure is at said first preset value;
means for remotely controlled venting of air from said tire;
means for activating said venting means to vent air from and deflate said tire when said first comparing means determines that said sensed tire air pressure is above said first preset value;
means for deactivating said venting means to stop the venting of air from and deflation of said tire when said first comparing means determines that said sensed tire air pressure is at said first preset value;
said means for compressing air comprising an air compressor, a compressed air reservoir connected to said air compressor to receive and store said compressed air, and a regulator to regulate air pressure in said reservoir;
means for calculating said sensed tire air pressure;
means for displaying said sensed tire air pressure in a first numeric display;
means for calculating said sensed tire air temperature;
means for calculating said sensed tire surface temperature;
means for displaying said sensed tire air temperature in a second numeric display;
means for displaying said sensed tire surface temperature in said second numeric display;

means for selecting said first, second and third preset values and displaying said first, second and third preset values in said numeric displays;
said delivering means comprising a distributor having a plurality of valve elements each having an air line leading to each tire of said vehicle, whereby said distributor selectively distribute said compressed air to a selected tire;
means for activating said plurality of valve elements to deliver air to and inflate said selected tire when said first comparing means determines that said sensed tire air pressure is below said first preset value;
means for deactivating said plurality of valve elements to stop the delivery of air to and inflation of said selected tire when said comparing means determines that said sensed tire air pressure is at said first preset value;
means for activating said plurality of valve elements to vent air from and deflate said selected tire when said first comparing means determines that said sensed tire air pressure is above said first preset value;
said air compressor having an outlet air line connected to said distributor;
said compressed air reservoir having an outlet air line connected to said distributor;
an inlet air line connecting said distributor to said compressor;
an inlet air line connecting said distributor to said compressed air reservoir;
each said air line being connected to each said tire by a sealing assembly comprising:
a first inlet air line in connection with said distributor and a metal housing of said sealing assembly;
two spaced annular means for sealing located around an axle whereby an annular air chamber is located about said axle with said inlet air line operably connected therewith;
said annular air chamber being capable of sustaining and containing pressurized air without leakage;
an outlet air line leading to a tire wheel, said wheel having an outer surface which is normally contained by a tire to form an airtight tire chamber;
a safety valve disposed in and in connection with said first inlet air line and being operable to permit passage of air only upon certain established conditions;
a remotely controlled two-way safety valve for air flow to said tire or air flow from said tire, disposed in said outlet air line and interfacing an air lock coupling in said wheel and said air lock coupling in a hub and being operable to permit passage of air only upon said certain established conditions;
said safety valve for preventing air loss from said airtight tire chamber and being disposed in said outlet air line and in connection with said tire wheel and interfacing said airtight tire chamber and being operable to permit passage of air only upon said certain established conditions;
an annular ferrofluid seal located to provide said annular air chamber about said axle, said annular air chamber being in connection with said safety valve of said inlet air line;
an annular sealing means comprising said annular ferrofluid seal having a fixed annular magnet fitted about said axle and flanking annular pole blocks and annular pole tips and a ferrofluid located between said annular pole blocks and the axle, thereby forming said annular air chamber between said pole blocks about the axle, said annular air chamber being in connection with said first inlet air line either through channels extending along the axle or through a passage formed in said fixed annular magnet and said metal housing, and further comprising annular carbon graphite seals operable as mechanical seals for preventing contaminants from entering said annular ferrofluid seal and as electrical conductors flanking said annular pole blocks and ring seals disposed about the outside perimeter of said annular pole blocks for the prevention of air leakage between said magnet and said pole blocks;
said mechanical seals located longitudinally outwardly and inwardly of said ferrofluid seals;
a plurality of air channels extending from said annular chamber longitudinally about the axle;
a hearing support shaft being fitted onto and in connection with a support shaft fitting;


5,587,703

UNIVERSAL MERCHANDISE TAG

Charles Dumont, 8925 Collins Ave., Surfside, Fla. 33154
Continuation-in-part of Ser. No. 328,683, Oct. 25, 1994. This
application Apr. 10, 1995, Ser. No. 419,434
Int. Cl.⁶ G08B 13/14

U.S. Cl. 340—572

10 Claims



4. A purchase item security and information tag apparatus for attachment to a purchase item in a store, comprising:
a tag body,

purchase item information display means for retaining item data in machine readable form,

a tag engagement security means including an elongate item engaging member which sounds an alarm if cut away from the item by a customer,

wherein said tag engagement security means comprises an electrically conductive item engaging member configured as a loop for extending through part of a purchase item and forming part of an electric circuit comprising alarm means and a power source, such that opening said circuit by breaking said engaging member prior to deactivation sounds said alarm means,

and wherein said tag engagement security means comprises deactivation means including a control wire provided within a wire guide means in said tag body, said guide means opening as a port in said tag body, said control wire making contact with said circuit when slid along said wire guide means and away from said port, such that said wire forms a short in said circuit diverting current away from said engaging member, such that said engaging member can be cut without opening said circuit.

5,587,704

CODE BLUE LIGHT AUDIO AND VISUAL ALARM APPARATUS


Samuel T. Foster, 124 Belshaw Ave., Shrewsbury Township, Monmouth County, N.J. 07724

Filed Sep. 1, 1995, Ser. No. 523,078

Int. Cl.⁶ G08B 23/00

U.S. Cl. 340—573

7 Claims



1. Alarm apparatus comprising:
an electrical wall outlet providing a source of electrical energy;
first means for generating an audible alarm-signal;
second means for generating a visual alarm-signal;
third means, including a radio receiver, for coupling said electrical energy to said first and second signal-generating means;

fourth means worn by a user for generating a trigger signal, and including a remote control transmitter and a manually operable switch;

with said radio receiver being normally inoperative to disconnect said source of electrical energy from said first and second alarm-signal generating means and being responsive to the generation of said trigger signal from said fourth means for connecting said source of electrical energy to said first and second alarm-signal generating means for turning on both said audible and visual alarm-signals; and

wherein said second means is set in a prominent window at the user's location and includes means for generating a flashing light when energized;

wherein said fourth means also includes a second manually operable switch for generating a second trigger signal, and wherein said radio receiver is responsive to said second trigger signal to connect said source of electrical energy only to said second alarm-signal generating means to only turn-on said visual alarm-signal.

5,587,705

MULTIPLE ALERT SMOKE DETECTOR


Gary J. Morris, 2026 Glenmark Ave., Morgantown, W. Va. 26505

Filed Aug. 29, 1994, Ser. No. 297,403

Int. Cl.⁶ G08B 17/10

U.S. Cl. 340—628

6 Claims



1. A multiple alert smoke detection system comprising:

(a) a minimum of two multiple alert smoke detectors, each detector comprising sensor means for sensing the presence of smoke, each detector comprising an audible alarm;

(b) each detector comprising means for actuation of said audible alarm for the duration of the sensor means sensing of the smoke;

(c) each detector comprising means for wireless direct communication with other smoke detectors of said system, each detector comprising a transmitter for transmitting user selectable, coded frequency modulated radio signal transmission, each smoke detectors comprising user selectable, coded frequency modulated radio receiver each detector emitting an audible pattern defined by the radio signal received by the detector.

5,587,706

METHOD AND APPARATUS FOR POWER OFF CONTROL OF A SELECTIVE CALL RADIO

Donald L. Branner, Coral Springs; Andrew E. Ray, Delray Beach; Scott M. Peters, Coral Springs, and Richard M. Huber, Boca Raton, all of Fla., assignors to Motorola, Inc., Schaumburg, Ill.


Filed Nov. 3, 1994, Ser. No. 333,687

Int. Cl.⁶ G08B 5/22; H04B 7/00

U.S. Cl. 340—825.44

5 Claims

1. A selective call radio, comprising:



a receiver section for receiving and demodulating a radio signal when power is supplied thereto, wherein the radio signal includes an address;

an address detector, coupled to said receiver section, wherein said address detector is for comparing the address demodulated by the receiver section to at least one selective call address stored in the selective call radio, and for generating an address detect signal when the address matches one of the at least one selective call address within predetermined parameters;

an alerting device, coupled to said address detector, for generating a sensible alert in response to the address detect signal;

a power off command detector, coupled to said address detector and said receiver section, for generating a power off signal when the address detect signal is generated and the radio signal includes a power off command; and

a power control section, coupled to said power off command detector, wherein said power control section is arranged such that it is responsive only to the power off signal for changing a state of the selective call radio to an off state, and wherein when said selective call radio is in the off state, essentially no power is supplied to said receiver section and said alerting device is disabled.

5,587,707

DATA TRANSFER

Neil M. Dickie, and Steven M. Hudson, both of Dorset, United Kingdom, assignors to Flight Refuelling Limited, Dorset, United Kingdom

PCT No. PCT/GB93/01272, § 371 Date Dec. 13, 1994, § 102(e) Date Dec. 13, 1994, PCT Pub. No. WO93/26115, PCT Pub. Date Dec. 23, 1993


PCT Filed Jun. 15, 1993, Ser. No. 351,457

Claims priority, application United Kingdom, Jun. 15, 1992, 9212685

Int. Cl.⁶ G08B 19/00; 21/00

U.S. Cl. 340—870.09

16 Claims



1. A pipeline system comprising a metal pipeline having a coating of insulating material which, in conjunction with sacrificial anodes electrically connected to the pipe provides cathodic protec-

tion, there being signal generating means adapted to be coupled to the pipeline and operable when so coupled to apply data to be transmitted in signal form to the pipeline for conveying along an electrically conducting channel formed by the metal pipeline, wherein the improvement comprises the signal generating means being operable to generate as the signal a pulsed electro-magnetic signal which comprises changes of voltage level in a very low frequency range (VLF and below), and further including means operable to use data transmitted via the channel provided by the pipeline for monitoring the condition of the insulation of the pipeline.

5,587,708

DIVISION TECHNIQUE UNIFIED QUANTIZER-DEQUANTIZER


Chung-Yen Chiu, Taipei, Taiwan, assignor to Industrial Technology Research Institute, Chungung, Taiwan

Filed Jan. 19, 1994, Ser. No. 184,368

Int. Cl.⁶ H03M 2/36

U.S. Cl. 341—76

10 Claims



1. A process for quantizing and dequantizing an input digital signal x to produce a quantized coefficient signal y and a reconstructed (dequantized) signal r , comprising the steps of:

inputting into a quantizer circuit an input signal x and a half quantization step size q ;

outputting from said quantizer circuit a quantized coefficient signal y and a remainder R , where:

$$|y| = \left\lfloor \frac{|x|}{2q} \right\rfloor \text{ and } R = |x| - \frac{|x|}{2q}$$

and


inputting into an adder and conversion circuit a magnitude $|x|$ of the input digital signal, a remainder R , q when $y \neq 0$, and 1 when $y = 0$ and q is even;

outputting from an adder and conversion circuit, a reconstructed signal r where:

$$r = \text{sgn}(x) \cdot \left(|x| - \begin{cases} R & \text{if } y = 0 \\ (R - q) & \text{if } y \neq 0 \text{ } q \text{ is odd} \\ (R - q + 1) & \text{if } y \neq 0 \text{ } q \text{ is even} \end{cases} \right)$$

5,587,709
**HIGH SPEED SERIAL LINK FOR FULLY DUPLEXED
 DATA COMMUNICATION**
 Deog-Kyoon Jeong, Gysu Apt. Ga-201, Bongchun-7-Dong,
 Kwanak-Ku, Seoul, Rep. of Korea, assignor to Deog-Kyoon
 Jeong, Seoul, Rep. of Korea, and Sun Microsystems, Inc.,
 Mountain View, Calif.
 Division of Ser. No. 254,326, Jun. 6, 1994. This application
 Dec. 29, 1995, Ser. No. 580,571
 Int. Cl.⁶ H03M 9/00

U.S. Cl. 341-100 20 Claims



1. A receiver for converting a serial data input stream into a parallel data output stream comprising:


- a plurality of registers for receiving the serial data input stream;
- a clock generator circuit for supplying a plurality of clock signals to the plurality of registers;
- a sampler for detecting the state of the data in the registers in response to the clock signals, and in response, supplying output signals indicative of the data;
- a data aligner connected to receive the output signals from the parallel sampler and in response thereto partition the data into words;
- a voter connected to the data aligner to detect zero crossings from the data samples to find a position with the most edge transitions; and
- a data separator for converting the serial data from the voter into parallel data.

5,587,710

SYNTAX BASED ARITHMETIC CODER AND DECODER

Chang Y. Choo, San Jose; Xiaonong Ran, Cupertino; Christine A. Porter, San Jose, and Mohammad R. Motamedli, Palo Alto, all of Calif., assignors to National Semiconductor Corporation, Santa Clara, Calif.

U.S. Cl. 341-107 16 Claims



1. A coder comprising:
a memory which, in response to receiving a symbol index, asserts a signal that indicates the boundaries of a segment that corresponds to the symbol index and results from applying an arithmetic coding model to a first interval;
a register which indicates the boundaries of a second interval;

a scaling circuit coupled to the memory and the register, wherein the scaling circuit transforms the signal asserted by the memory to first and second digital signals indicating the boundaries of a segment of the second interval; and
a signal generator which generates an output bit when a most significant bit of the first digital signal equals a most significant bit of a second digital signal.

5,587,711
METHOD AND SYSTEM FOR RECONSTRUCTING
QUANTIZED SIGNALS
Lance J. Williams, Los Altos, and Michael Kass, Aptos, both of
Calif., assignors to Apple Computer, Inc., Cupertino, Calif.
Filed Sep. 30, 1994, Ser. No. 315,637
Int. Cl.⁶ H03M 1/66

U.S. Cl. 341-144 17 Claims




17. A method for reconstructing an original signal from a quantized signal comprising the steps of:
sampling said quantized signal at control points wherein said step of sampling further comprises the steps of:
identifying horizontal segments of said quantized signal within which a quantization level does not change;
selecting as control points endpoints of each segment and two interior points of each segment which are evenly spaced from one another and from said endpoints; and
solving for amplitude values at said selected control points a system of equations constraining cubic polynomial segments to the range of their quantization bounds and minimizing the integral of the second derivative of the solution;
interpolating said control points to transform said quantized signal into a dequantized signal; and
reconstructing said original signal from said dequantized signal.

5,587,712

**TRANSPONDER HAVING MICROPROCESSOR
GENERATED FREQUENCY SHIFT SIGNALS**

Steven F. Boone, Wood Dale, and Edward J. Ho, Bloomingdale,
both of Ill., assignors to Mark IV Transportation Products
Corp., Niles, Ill.

U.S. Cl. 342-42 6 Claims



1. In a transponder for transmitting an electromagnetic signal based on previously stored information in said transponder, to a

a microprocessor in said transponder having a predetermined cycle time;

means programming said microprocessor for generating a first number of pulses, each said pulse having a period corresponding to a first multiple of said cycle time, said first multiple defining a first signal frequency;

means programming said microprocessor for generating a second number of pulses, said pulses occurring at a period corresponding to a second multiple of said cycle time, said second multiple defining a second signal frequency;

means generating groups of said first and second pulses, said groups defining a frequency shift keyed signal; and


means modulating said frequency shift keyed signals in accordance with said stored information, thereby generating a transponder response to said interrogating station signal and,

means in said transponder transmitting said frequency shift signals to said interrogating station.

5,587,713
RADAR TRANSMITTER/RECEIVERS
Heinz Pfizenmaier, Leonberg, Germany; Philip Blakelock;
Brian Prime, both of Lincoln, United Kingdom, and David
Dawson, Lincolnshire, United Kingdom, assignors to Plessey
Semiconductors Limited, United Kingdom, and Robert
Bosch GmbH, Germany

Filed May 17, 1995, Ser. No. 443,247
Claims priority, application United Kingdom, Jun. 1, 1994,
9410985

U.S. Cl. 342-70 Int. Cl.⁶ G01S 13/93; 7/28 4 Claims




1. A frequency modulated, continuous wave, radar transmitter/receiver arrangement, comprising:
an electric oscillator; an antenna; mixer means; and dual rat-race coupling means including
first and second ring transmission paths each having first, second, third and fourth ports,
means coupling the second and third ports of the first ring transmission path to said oscillator and to said antenna respectively,
means coupling the first and fourth ports of the first ring transmission path to the first and third ports of the second ring transmission path respectively, and
means coupling at least one of the second and fourth ports of the second ring transmission path to said mixer means.

5,587,714
SPACECRAFT ANTENNA POINTING ERROR
CORRECTION
Peter Y. Chu, Palo Alto, and Alfred H. Tadros, San Jose, both
of Calif., assignors to Space Systems/Loral, Inc., Palo Alto,
Calif.

Filed Mar. 10, 1995, Ser. No. 401,863
Int. Cl.⁶ H04B 7/185

U.S. Cl. 342—354 5 Claims

1. A system for correcting the pointing error of an instrument carried by a spacecraft comprising:



means for orienting a line of sight of the instrument relative to the spacecraft;

means for sensing an orientation of the spacecraft including a perturbation in said orientation, said perturbation being characterized in a spectral domain by a band of frequencies extending from a low-frequency end of said band to a high-frequency end of said band, to a high-frequency end of said band, a transient part of said perturbation being characterized in said spectral domain by a high-frequency portion of said band;

means coupled to said sensing means for extracting a transient part perturbation in said orientation, said extracting means comprising high-pass filter means which passes the high frequency portion of said band, while attenuating low-frequency portion of said band, for extracting said transient part of said perturbation; and


compensating means responsive to said transient part of said perturbation, and operating independently of said low-frequency portion of said band, for commanding said orienting means to alter an orientation of said line of sight relative to said spacecraft by an incremental orientation equal and opposite to said transient part of said perturbation.

5,587,715

**METHOD AND APPARATUS FOR TRACKING A
MOVING OBJECT**

Peter T. Lewis, Washington, D.C., assignor to GPS Mobile,
Inc., Washington, D.C.

U.S. Cl. 342—357 62 Claims



1. A method of determining with a high degree of accuracy the location of an object based upon signals transmitted from a plurality of satellites disposed in known orbits about the earth, the object being capable of moving selectively throughout a geographical area, said method comprising the steps of:

- distributing a plurality of fixed points throughout the geographical area and determining with accuracy the location of each of the fixed points;
- receiving at each of the plurality of fixed points and processing satellite signals from a corresponding subset of the plurality of satellites presently in sight of each fixed point to determine the approximate location of each fixed point;
- comparing the approximate and accurate locations of each of the plurality of fixed points to provide differential data;
- receiving at the object and processing the satellite signals from a given subset of the plurality of satellites presently in sight of the object to determine the approximate location of the object;
- transmitting a signal indicative of the object's approximate location to a fixedly disposed command center;
- determining based upon the received object's approximate location and the determined locations of the fixed points which of the plurality of fixed points is presently in sight of the same subset of satellites as the object;
- establishing a communication path between the command center and with at least one of said in sight fixed points; and
- transmitting over the communication path the differential data of the determined fixed point, whereby the object's approximate location is adjusted based on the differential data of said one in sight fixed point to provide an indication of the object's location with greater accuracy.

5,587,716

GAP COVERAGE FOR GPS SIGNALS


Len Sheynblat, Belmont, Calif., assignor to Trimble Navigation, Ltd., Sunnyvale, Calif.

Filed Sep. 29, 1995, Ser. No. 537,110

Int. Cl.⁶ H04B 7/185; G01S 5/02

U.S. Cl. 342—357

13 Claims



1. A method for compensating for temporary loss of differential GPS correction signals for a satellite during an IODE changeover interval, the method comprising the steps of:

- receiving ephemeris data for a satellite, numbered j , during two consecutive IODE time intervals, given by $t(j,n)_{\text{IODE}} \leq t < t(j,n+1)_{\text{IODE}}$ and $t(j,n+1)_{\text{IODE}} \leq t < t(j,n+2)_{\text{IODE}}$ when the ephemeris data are available for at least one satellite numbered $j=1, \dots, J$ ($J \geq 3$);
- receiving differential GPS correction signals for satellite number j for a time interval $t(j,n)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}} \leq t < t(j,n+1)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}}$ based upon ephemeris data that are applicable for the IODE time interval $t(j,n)_{\text{IODE}} \leq t < t(j,n+1)_{\text{IODE}}$ for satellite j , where Δt_{ch} is a first selected non-negative temporal length, $\Delta t_{\text{rev.ref}}$ is a second selected positive temporal length;

receiving differential GPS correction signals for satellite j for a time interval $t(j,n+1)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}} \leq t < t(j,n+2)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}}$ based upon ephemeris data that are applicable for the time interval $t(j,n+1)_{\text{IODE}} \leq t < t(j,n+2)_{\text{IODE}}$ for satellite j ;

for two selected times $t=t'_2$ and $t=t'_3$ satisfying the constraints $t(j,n)_{\text{IODE}} < t'_2 \leq t(j,n+1)_{\text{IODE}} < t'_3$, determining the time variation of each of l ephemeris parameters $e_i(t;j,n)$ ($i=1, \dots, l$; $l \geq 1$) that determine the ephemeris of satellite j during the time interval given by $t'_2 \leq t < t'_3$;

for two selected times $t=t''_2$ and $t=t''_3$ satisfying the constraints $t(j,n+1)_{\text{IODE}} + \Delta t_{\text{rev.ref}} \leq t''_2 < t''_3$, determining the time variation of each of l ephemeris parameters $e_i(t;j,n+1)$ ($i=1, \dots, l$; $l \geq 1$) that determine the ephemeris of satellite j during the time interval given by $t''_2 \leq t < t''_3$, where $\Delta t_{\text{rev.ref}}$ is a third selected positive temporal length;

determining an approximation $\Delta e_i(t;j,n+1,n)$ for each of the l ephemeris parameter difference values $\Delta e_i(t;j,n+1,n) = e_i(t;j,n+1) - e_i(t;j,n)$ in a time interval that includes at least a portion of the time interval $t(j,n+1)_{\text{IODE}} + \Delta t_{\text{rev.ref}} \leq t < t(j,n+2)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}}$; and

estimating the values of each of the l ephemeris parameters $e_i(t;j,n)$ in at least a portion of the time interval $t(j,n+1)_{\text{IODE}} + \Delta t_{\text{rev.ref}} \leq t < t(j,n+2)_{\text{IODE}} + \Delta t_{\text{ch}} + \Delta t_{\text{rev.ref}}$ by the approximation $e_i(t;j,n)_{\text{est}} = e_i(t;j,n+1) - \Delta e_i(t;j,n+1,n)$.

5,587,717

MANUAL ANTENNA ALIGNMENT APPARATUS AND METHOD FOR VERY SMALL APERTURE TERMINAL

Vong J. Jang, Kyoungki-do, Rep. of Korea, assignor to Hyundai Electronics Industries Co., Ltd., Rep. of Korea


Filed Sep. 12, 1995, Ser. No. 526,890

Claims priority, application Rep. of Korea, Dec. 30, 1994, 94-39847

Int. Cl.⁶ H01Q 3/00

U.S. Cl. 342—359

3 Claims



1. An apparatus for manually aligning an antenna of a very small aperture terminal with a satellite, comprising manual antenna alignment means connected between a demodulator and a data processor in a receiver, for aligning said antenna with said satellite, said manual antenna alignment means including:

- peak value detection means for filtering and differentiating an output signal from said demodulator to detect a peak value therefrom in response to a peak value detection control signal from a control processor, the detected peak value indicating a frequency position of a carrier transmitted from a center communication station;
- a sample/holder for sampling and holding an output signal from said peak value detection means in response to a sample/hold control signal from said control processor;
- an inverter for inverting a multiplexing control signal from said control processor;
- a first analog switch for selectively transferring an output signal from said sample/holder in an antenna alignment mode in response to an output signal from said inverter;
- a second analog switch for selectively transferring an output signal from an automatic gain control circuit in said receiver

in a normal mode in response to the multiplexing control signal from said control processor;

a scaling circuit for scaling the output signal from said sample/holder transferred by said first analog switch or the output signal from said automatic gain control circuit transferred by said second switch at a desired ratio;

signal display means for displaying a level of an output signal from said scaling circuit so that it can be observed by the user with the naked eye; and

an antenna alignment mode switch for selecting the antenna alignment mode.

5,587,718

METHOD FOR DISCOVERING AND DESIGNATING AIR TARGETS

Carlo A. Iardella, Carrara, and Mauro Agrusa, La Spezia, both of Italy, assignors to GF-OTO Melara Breda Bresciana S.r.l., Rome, Italy


Filed Jun. 16, 1994, Ser. No. 260,817

Claims priority, application Italy, Jun. 16, 1993, MI93A1290

Int. Cl.⁶ G01S 5/04; F41G 5/12

U.S. Cl. 342—443

2 Claims



1. A method for automatically discovering and designating targets for an operator of a weapons system, comprising:

- automatically scanning for existence and location of a target and thereby acquiring signals indicative of existence and location of the target;
- transmitting signals indicative of existence and location of a target, to a portable receiver that is collocated with a weapons system operator who is wearing a headset unit which includes stereophonic headphones operatively connected with the receiver, so that the operator receives audio signals, including digitized voice signals, which vary depending on the existence and location of the target as well as on spatial orientation of the headset unit;
- the operator orienting his or her head towards a direction in which the weapons system is to be fired at said target by moving so as to achieve a predetermined modification of said audio signals, including digitized voice signals;
- while conducting steps (a) and (b), acquiring signals indicative of existence and location of a higher priority target and transmitting signals indicative of existence and location of said higher priority target to said receiver; and
- the operator interrupting step (c) by rapid large-scale head rotation in response to audio signals received in step (d), and then conducting step (c) in regard to the audio signals received in step (d), for orienting their head towards the direction in which the weapons system is to be fired at said higher priority target.

5,587,719

AXIALLY ARRAYED HELICAL ANTENNA


David A. Steffy, Herndon, Va., assignor to Orbital Sciences Corporation, Dulles, Va.

Filed Feb. 4, 1994, Ser. No. 191,247

Int. Cl.⁶ H01Q 1/36; 11/08

U.S. Cl. 343—895

10 Claims



- An antenna system comprising: a plurality of antenna structures which include at least one antenna element having at least one conductive element helically wound in a first direction around a common axis, said antenna structures being axially spaced from one another along said common axis; feeding means for feeding a common signal to each of said antenna elements, said feeding means comprising phase shifting means for shifting the phase of said common signal with respect to each of said antenna elements; and wherein said antenna elements are quadrifilar helical antennas having four orthogonal conductive elements helically wound around said common axis.

5,587,720

FIELD EMITTER ARRAY AND CLEANING METHOD OF THE SAME

Shinya Fukuta, and Keiichi Betsui, both of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan

Continuation of Ser. No. 971,618, Nov. 6, 1992, abandoned.


This application Jul. 19, 1994, Ser. No. 277,351

Claims priority, application Japan, Nov. 8, 1991, 3-293343


Int. Cl.⁶ G09G 3/10

U.S. Cl. 345—75

15 Claims



- A method for cleaning a field emitter array that includes an electron-beam source array formed by arranging a plurality of electron-beam source elements, each of said electron-beam source elements including a cathode for emitting electrons and a gate provided in the vicinity of said cathode, a predetermined cathode voltage being applied to said cathode and a predetermined gate voltage being applied to said gate, to emit electrons from said cathode by field emission effect in a first mode of operation of the field emitter array, and an anode arranged facing said electron-beam source elements in proximity to said cathode of each of said electron-beam source elements, applied with a predetermined positive voltage for capturing said electrons emitted from at least one



second ports of said first bank are concurrently used for receiving and outputting information;

a second bank of two-ported video random access memory for furnishing all remaining portions of said first frame of information to the output display through its first port and for concurrently receiving information through its second port to update lines in said second frame of information not being currently furnished to the output display such that said first and second ports of said second bank are concurrently used for receiving and outputting information;

said first and second banks simultaneously storing all information corresponding to said first frame and portions of said second frame;

means for alternatively addressing said first and second banks of memory as each line in said first frame is written to the output display, said first frame having its lines interleaved between said first and second banks of said memory;

means for addressing said first and second banks of memory to write information to update lines in said second frame not being currently furnished to the output display, said second frame having its lines interleaved between said first and second banks of said memory; and

means for controlling the writing of lines in said first frame of information to the output display by selecting alternate lines constituting said first frame from said first bank and said second bank.

5,587,727

INK JET APPARATUS USING PRESSURE WAVE INTERSECTION TO EJECT INK DROPLETS

Hiroto Sugahara, Ama-gun, and Yoshikazu Takahashi, Kasugai, both of Japan, assignors to Brother Kogyo Kabushiki Kaisha, Nagoya, Japan


Filed Apr. 4, 1994, Ser. No. 222,594

Claims priority, application Japan, Apr. 23, 1993, 5-097468; Jun. 1, 1993, 5-130282

Int. Cl.⁶ B41J 29/38

U.S. Cl. 347—12

17 Claims



1. An ink jet apparatus, comprising:
an ink chamber filled with ink;
a plurality of jet nozzles communicating with said ink chamber;

energy generating means for generating pressure waves in the ink contained in said ink chamber to jet the ink from said jet nozzles;

energy control means for controlling said energy generating means to generate the pressure waves so that one of the pressure waves generated by said energy generating means is synthesized with another one of the pressure waves generated by said energy generating means to thereby jet the ink from subject jet nozzle of said plurality of jet nozzles.

5,587,728

OPTICAL FEEDBACK PRINTER


Albert D. Edgar, Austin, Tex., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 29, 1994, Ser. No. 235,847

Int. Cl.⁶ B41J 29/393; 2/21

U.S. Cl. 347—19

23 Claims



1. A method for printing an image on a substrate comprising the steps of:
scanning an image on a substrate, wherein a set of pixels of the scanned image has an intensity less than a desired image intensity for a corresponding set of pixels in a desired image; and
printing a set of correction pixels on the substrate, wherein each correction pixel is printed according to a difference between image intensities of corresponding scanned and desired image pixels.

5,587,729

ROTATABLE SERVICE STATION FOR INK-JET PRINTER

Ghal K. Lee, Singapore, Singapore, and Masao Gomi, Suwa, Japan, assignors to Hewlett-Packard Company, Palo Alto, Calif.

Filed May 11, 1993, Ser. No. 59,402


Int. Cl.⁶ B41J 2/165

U.S. Cl. 347—32

10 Claims

1. An apparatus for servicing a pen that is installed in a printer for movement between a printing position and a service position, the apparatus comprising:

- a service station located at the service position, the service station having a rotatable carrier with a capping member and a wiper mounted thereon; and
- a carrier drive subsystem having a driven gear mounted on a displaceable carrier axle that is connected to the carrier, a drive gear, and a cam surface formed on the drive gear, the carrier axle being engaged with and displaceable by the cam surface, the cam surface having a first cam track portion to position the carrier axle in an engaged proximity where the driven gear mounted on the carrier axle engages the drive gear to rotate the rotatable carrier of the service station to position



the capping member and the wiper adjacent to the pen and a second cam track portion to displace the carrier axle to a disengaged proximity where the driven gear is disengaged from the drive gear and the service station is moved along a linear path to selectively cover and uncover the pen with the capping member.

5,587,730

REDUNDANT FULL WIDTH ARRAY THERMAL INK JET PRINTING FOR IMPROVED RELIABILITY


Robert S. Karz, Webster, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Sep. 30, 1994, Ser. No. 316,142

Int. Cl.⁶ B41J 2/21; 29/38

U.S. Cl. 347—43

18 Claims



1. A thermal ink jet printer operates in a first mode or a second mode comprising:
primary printing means for printing ink drops of a first color; and
secondary printing means for printing ink drops of at least said first color, said secondary printing means selectively printing according to said first mode or said second mode, wherein said secondary printing means in said first mode operates simultaneously with said primary printing means to supplement said primary printing means, and wherein if said primary printing means fails, said secondary printing means in said second mode prints ink drops of said first color in place of said primary printing means.

5,587,731

INK RETAINER

Kuniaki Yasunaga, and Shigeru Ueno, both of Yokohama, Japan, assignors to Bridgestone Corporation, Tokyo, Japan

Filed Feb. 22, 1994, Ser. No. 199,653


Int. Cl.⁶ B41J 2/175

U.S. Cl. 347—86

4 Claims

1. An ink retainer comprising a flexible polyurethane foam which is prepared by reacting a polyether polyol with a polyisocyanate,

wherein said polyether polyol comprises a polymeric polyol, wherein at least one of styrene and acrylonitrile is grafted to said polymeric polyol, wherein said polymeric polyol is present in an amount of at least 20% by weight based on the total weight of said polyether polyol.



wherein said polyurethane foam is a three-dimensional reticulated foam which contains at least 20 cells/inch and which has no cell membranes, and
wherein said polyurethane foam absorbs and retains ink.

5,587,732

COLOR THERMAL PRINTING METHOD AND APPARATUS

Hideyuki Kokubo, Saitama, Japan, assignor to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Nov. 3, 1993, Ser. No. 145,107

Claims priority, application Japan, Nov. 4, 1992, 4-295444

Int. Cl.⁶ B41J 2/355

U.S. Cl. 347—183

18 Claims



1. A color thermal recording method for recording full-color images on thermosensitive color recording material by use of a thermal head, said recording material comprising a support and at least first to third thermosensitive color layers formed thereon in order, said first coloring layer having lower heat sensitivity than said second coloring layer, said second coloring layer having lower heat sensitivity than said third coloring layer, said thermal head having a plurality of heating elements, each of which is driven by a pulse train in combination of a bias pulse for raising temperature substantially up to coloring temperature in order to record one pixel in a selected one of said color layers, and gradation pulses, a number of which represents density of recording on said pixel, said recording method comprising steps of:

dividing said pulse train into N pulse sub-trains, each of which comprises one of N subsidiary bias pulses into which said bias pulse is divided at an equal width, and one of N gradation pulse groups into which said gradation pulses are divided substantially equally, each of said pulse sub-trains resulting in a recording density lower than a desired final density of said pixel;
supplying said thermal head with said N pulse sub-trains said recording material is moved relative to said thermal head by an amount of said one pixel, in order to record said one pixel in said selected one of said coloring layers; and
wherein, in a beginning of each of said pulse sub-trains, a first half of said gradation pulse group, then generating said subsidiary bias pulse, and, finally, generating a second half of said gradation pulse group is generated.

5,587,733


RECORDING APPARATUS WHICH AVOIDS INK SHEET STICKING AND IMAGE STREAKING

Takeshi Ono, Yokohama; Takehiro Yoshida, Tokyo; Makoto Kobayashi, Tama; Satoshi Wada, Kawasaki; Hisao Tera-jima, Yokohama; Minoru Yokoyama, Yokohama; Takashi Arai, Yokohama; Akihito Tomoda, Yokohama, and Yasushi Ishida, Tokyo, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 89,639, Jul. 9, 1993, abandoned, which is a continuation of Ser. No. 431,840, Nov. 6, 1989, abandoned. This application Oct. 26, 1994, Ser. No. 329,621 Claims priority, application Japan, Nov. 9, 1988, 63-281372 Int. Cl.⁶ B41J 2/38

U.S. Cl. 347-185

50 Claims



1. A thermal transfer recording apparatus for transferring ink of an ink sheet onto a recording medium by utilizing thermal energy generated by a thermal head to record an image on the recording medium based on image data, said apparatus comprising:

a recording medium conveying mechanism for conveying the recording medium, said recording medium conveying mechanism having a driving section for generating a driving force for conveying the recording medium;

an ink sheet conveying mechanism for conveying the ink sheet; and

a control section for controlling image recording by the thermal head, conveyance of the recording medium by said recording medium conveying mechanism and conveyance of the ink sheet by said ink sheet conveying mechanism.

wherein after the image recording by the thermal head and between generation of the driving force by said driving section and next generation of the driving force, said control section controls said ink sheet conveying mechanism to convey the ink sheet to record an image of image data identical to that used in the image recording.

5,587,734

USER INTERFACE FOR SELECTING TELEVISION INFORMATION SERVICES THROUGH PSEUDO-CHANNEL ACCESS

Gary M. Lauder, Atherton; W. Leo Hoarty, Santa Clara, and Joshua W. Soske, Sunnyvale, all of Calif., assignors to ICTV, Inc., Los Gatos, Calif.

Continuation-in-part of Ser. No. 56,958, May 3, 1993, Pat. No. 5,526,034, which is a continuation-in-part of Ser. No. 877,325, May 1, 1992, Pat. No. 5,412,720, which is a

continuation-in-part of Ser. No. 754,932, Sep. 10, 1991, Pat. No. 5,220,420, which is a continuation of Ser. No. 589,205, Sep. 27, 1990, Pat. No. 5,093,718. This application Nov. 3, 1994, Ser. No. 333,957


Int. Cl.⁶ H04N 7/13

U.S. Cl. 348-10

6 Claims

1. A television interface controller connected to a cable carrying a plurality of non-interactive channels on a first group of carrier frequencies and a plurality of pseudo-channels, each assigned to an information service from a plurality of information services, on a second group of carrier frequencies, said interface controller comprising:

means for receiving a channel selection;



means for communicating with a cable control node when the channel selection is one of said pseudo-channels; a tuner having an input connected to said cable and an output; and

processor means, in communication with said channel selection receiving means and said communicating means, for controlling said tuner to tune to the carrier frequency of the channel selection if the channel selection is a non-interactive channel and to tune to one of said second group of carrier frequencies in accordance with said communicating means if the channel selection is one of said pseudo-channels.

5,587,735

VIDEO TELEPHONE

Kiyoshi Ishida, and Hiroshi Goto, both of Yokohama, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Continuation of Ser. No. 918,054, Jul. 21, 1992, Pat. No. 5,400,068, and a continuation-in-part of Ser. No. 838,348, Feb. 20, 1992, Pat. No. 5,396,269. This application Dec. 22, 1994, Ser. No. 361,957

Claims priority, application Japan, Jul. 24, 1991, 3-184669 The portion of the term of this patent subsequent to Mar. 21, 2012, has been disclaimed.

Int. Cl.⁶ H04N 7/14; H04M 11/00

U.S. Cl. 348-14

13 Claims



1. A video telephone for exchanging image data, voice data and user data through a digital communication channel in real time, comprising:

(a) a communication controller for controlling communication of image data, voice data and user data, which are multiplexed, through the digital communication channel;

(b) a multiplexor-separator for separating multiplexed image data and voice data received by said communication controller, and for multiplexing image data and voice data into multiplexed data which are to be transmitted.

(c) an image CODEC for decoding image data, which are separated by said multiplexor-separator, into an image signal and for coding an input image signal into image data and transmitting image data to said multiplexor-separator;

(d) a camera for outputting an image signal, which is taken by said camera, to said image CODEC as an image signal to be coded;

(e) a display for displaying an image represented by an image signal which is decoded by said image CODEC;

(f) a voice communication controller for decoding voice data, which are separated by said multiplexor-separator into voice signal and for coding an input voice signal into voice data and transmitting voice data to said multiplexor-separator;

(g) a speaker for outputting a voice represented by a voice signal which is decoded by said voice communication controller;

(h) a microphone for transmitting the voice signal, which is produced by said microphone, to said voice communication controller as the voice signal to be coded;

(i) a power supply unit for receiving a supply of power from an external source and distributing the power to each electrical part of the video telephone;

(j) a key input unit having a plurality of keys;

(k) an image input terminal;

(l) an image output terminal for outputting the image signal decoded by said image CODEC;

(m) a video switch for outputting the image signal from said camera or the input image signal from said image input terminal to said image CODEC as the image signal to be coded;

(n) a voice input terminal;

(o) a voice output terminal;

(p) an audio switch for outputting an input signal from said voice input terminal or the voice signal taken by the microphone to said voice communication controller as the voice signal to be coded, and for outputting the voice signal, which is decoded by said voice communication controller, to said speaker or said voice output terminal;

(q) a data terminal; and

(r) a control unit, responsive to the key input from said key input unit, for controlling said video switch and said audio switch and controlling inputting and outputting of user data between said multiplexor-separator and said data terminal.

5,587,736

STERILIZABLE CCD VIDEO CAMERA


Robert R. Walls, Santa Barbara, Calif., assignor to Envision Medical Corporation, Goleta, Calif.

Filed Feb. 16, 1993, Ser. No. 18,053

Int. Cl.⁶ A61B 1/04

U.S. Cl. 348-65

5 Claims



1. A sterilizable apparatus for protecting at least one CCD and a portion of an endoscope, comprising:

a housing having a forward end and rear end, the housing including inner and outer walls separated by a vacuum, an exterior of the housing capable of withstanding temperatures of about 130 degrees Centigrade, the housing capable of preventing electromagnetic interference and gaseous and liquid contaminants from reaching an interior of the housing;

an end bushing mounted in the interior of the housing in proximity to the forward end and coupled to the endoscope, the end bushing providing rotation of the endoscope relative to the housing, and comprising a material capable of withstanding temperatures of about 130 degrees Centigrade;

a backing for receiving a cable, the backing comprising a low heat-conducting material and mounted to the housing in proximity to the rear end;

a support member for positioning the at least one CCD within the inner walls so that the at least one CCD is not heated above approximately 80 degrees Centigrade, the support member being made of a low heat-conducting material and having a long, thin configuration for reducing thermal conduction to the at least one CCD, the support member being attached to the backing and extending toward the forward end for engagement with the endoscope;

coupling optics mounted on the support member and coupled to the endoscope and the at least one CCD;

a heatsink coupled to the at least one CCD and mounted to the support member; and

electronics mounted on the support member and coupled to the at least one CCD and the cable.

5,587,737

SHAKEPROOF CAMERA WHEREIN SHAKE CORRECTION PARAMETERS MAY BE CHANGED

Masayoshi Sekine, Tokyo; Toshiaki Kondo, Fujisawa, and Yoshiaki Kino, Tokyo, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 6,974, Jan. 21, 1993, abandoned.

This application May 25, 1995, Ser. No. 449,917

Claims priority, application Japan, Jan. 23, 1992, 4-010184 Int. Cl.⁶ H04N 5/228

U.S. Cl. 348-208

22 Claims



1. A shakeproof camera comprising:

(A) image pickup means;

(B) shake detecting means for detecting an image shake from an image pickup signal output from said image pickup means;

(C) shake correcting means for correcting the image shake in accordance with an output from said shake detecting means;

(D) control structure for changing an accumulation time of said image pickup means; and

(E) control means for changing correction parameters of said shake correcting means in accordance with a variation of the accumulation time of said image pickup means controlled by said control structure.

5,587,738

SOLID-STATE IMAGE PICKUP DEVICE HAVING PLURAL SWITCHES FOR SUBTRACTING A STORED SIGNAL FROM A PIXEL OUTPUT

Mahito Shinohara, Tokyo, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Nov. 17, 1994, Ser. No. 342,042


Claims priority, application Japan, Nov. 17, 1993, 5-287854; Nov. 17, 1993, 5-287855

Int. Cl.⁶ H04N 5/335

U.S. Cl. 348-302

3 Claims

1. A solid-state image pickup device, wherein plural photoelectric conversion pixels, each of which accumulates electric charges



created due to energy of received light and produces amplified electric charges, are arranged in a matrix form, comprising:

- a respective capacitor having an input terminal connected to each of said plural photoelectric conversion pixels, each capacitor further having an output terminal;
- a respective transistor having a control electrode connected to said output terminal of each said capacitor;
- a respective first switch for switching each said control electrode to a first predetermined potential or an electrically-floated state;
- a respective second switch for selectively switching said input terminal of each said capacitor to a second predetermined potential or an electrically-floated state;
- a respective third switch for selectively inputting a predetermined stored signal to said input terminal of each said capacitor;
- a respective signal accumulating pixel which accumulates an output signal from each said transistor; and
- a respective fourth switch for connecting an output line for each said photoelectric conversion pixel to an output line for said respective signal accumulation pixel.

5,587,739

VARIABLE MAGNIFICATION IMAGE TAKING DEVICE
Takeshi Suzuki, Ebina, and Atushi Sekine, Kasukabe, both of Japan, assignors to Nikon Corporation, Tokyo, Japan

Continuation of Ser. No. 217,842, Mar. 25, 1994, abandoned.


This application May 17, 1995, Ser. No. 443,897

Claims priority, application Japan, Mar. 26, 1993, 5-090533; May 31, 1993, 5-149728; Dec. 22, 1993, 5-345620

Int. Cl.⁶ H04N 5/232

U.S. Cl. 348—347

9 Claims



1. A variable-magnification image taking device comprising: a phototaking lens in which magnification is varied by zooming; a solid-state image taking device which receives an object image formed by said phototaking lens and stores image information thereof;
- a moving device which moves said solid-state image taking device along an optical axis; and
- a control unit which receives information as to magnification variation of said phototaking lens and which controls said moving device according to the magnification variation of

said phototaking lens, so as to compensate displacement of an image point of the object image which moves with zooming of said phototaking lens.

5,587,740
DIGITAL PHOTO KIOSK


James M. Brennan, 3054 N. Downer Ave., Milwaukee, Wis. 53211

Filed Aug. 17, 1995, Ser. No. 516,273

Int. Cl.⁶ H04N 5/225

U.S. Cl. 348—373

4 Claims



1. A kiosk providing postcards of a scenic attraction comprising: an enclosed housing having a front panel with an aperture; an anchor affixing the housing to the ground with the front panel facing the scenic attraction;
- a payment receiver affixed to the housing to provide a payment signal indicating a payment by a user;
- an electronic camera affixed within the housing to receive an image of the scenic attraction through the aperture to produce electronic image signals;
- an electronic printer receiving electronic image signals and producing a printed postcard depicting the image;
- an electronic computer including computer memory receiving the electronic image signals from the electronic camera and storing them in computer memory and after receiving the payment signal, operating according to a stored program to control the electronic printer to print the postcard depicting the scenic attraction;
- a clear motorized cover positioned over the aperture and connected to the electronic computer wherein the electronic computer operates to open the motorized cover only after the payment signal has been received;

and an acceleration sensitive switch producing a tamper signal and wherein the electronic computer operates according to the stored program to store images taken through the cover if the tamper signal is received.

5,587,741

APPARATUS AND METHOD FOR DETECTING MOTION VECTORS TO HALF-PIXEL ACCURACY

Sang-Ho Kim, Seoul, Rep. of Korea, assignor to Daewoo Electronics Co., Ltd., Seoul, Rep. of Korea

Filed Jul. 21, 1994, Ser. No. 278,663


Claims priority, application Rep. of Korea, Jul. 21, 1993, 3-13836

Int. Cl.⁶ H04N 7/36

U.S. Cl. 348—416

2 Claims

1. A method for determining motion vectors between a current frame and a preceding frame of video signals to a half-pixel accuracy, wherein the current frame is divided into a multiplicity of search blocks of an identical size and the preceding frame is made to include a corresponding number of search regions, each of the search regions having M candidate blocks of said identical size, M being an integer greater than 1, which comprises the steps of:



- (a) calculating M first error functions, each of the M first error functions representing the difference between a search block in the current frame and each full-pixel resolution candidate block, included in the corresponding search region of the preceding frame;
- (b) selecting K full-pixel resolution motion vectors for the search block which yield smallest first error functions among said M first error functions, K being an integer greater than 1 and smaller than M;
- (c) obtaining M half-pixel resolution candidate blocks, in a half-pixel resolution search region corresponding to one of the K full-pixel resolution motion vectors;
- (d) calculating M second error functions, each of the M second error functions representing the difference between the search block in the current frame and each of said M half-pixel resolution candidate blocks;
- (e) repeating steps (c) to (d) for the remaining (K-1) full-pixel resolution motion vectors obtained in step (b), providing K×M second error functions;
- (f) selecting a half-pixel resolution motion vector for the search block, said half-pixel resolution motion vector yielding a second error function which is smallest among the K×M second error functions; and
- (g) repeating steps (a) to (f) until all the search blocks in the current frame are processed.

5,587,742

FLEXIBLE PARALLEL PROCESSING ARCHITECTURE FOR VIDEO RESIZING


Clarence J.-Y. Hau, Mt. Laurel; Kevin J. Stec, Medford, and Kenneth E. Vavreck, Maple Shade, all of N.J., assignors to Panasonic Technologies, Inc., Princeton, N.J.

Filed Aug. 25, 1995, Ser. No. 519,437

Int. Cl.⁶ H04N 7/01

U.S. Cl. 348—441

14 Claims



1. A video format converter for converting a digital input signal having a first vertical sample size per unit length and a first horizontal sample size per unit length to a digital output signal having a second vertical sample size per unit length and a second horizontal sample size per unit length comprising:

5,587,743

SIGNAL PROCESSORS FOR TRANSPARENT AND SIMULTANEOUS TRANSMISSION AND RECEPTION OF A DATA SIGNAL IN A VIDEO SIGNAL


Gerald D. Montgomery, and Jay B. Norrish, both of Mesa, Ariz., assignors to WavePhore, Inc., Tempe, Ariz.

Division of Ser. No. 947,134, Sep. 18, 1992, Pat. No. 5,387,941, which is a continuation-in-part of Ser. No. 715,920, Jun. 14, 1991, Pat. No. 5,327,237. This application Apr. 8, 1994, Ser. No. 224,734

Int. Cl.⁶ H04N 7/08

U.S. Cl. 348—473

45 Claims



1. A method of transmitting information, the method comprising: receiving the information from a source; generating a carrier at an odd quarter, non-integral multiple of the frequency of a raster rate of a rasterized video signal, the rasterized video signal having a bandwidth having spectral energy having chrominance and luminance components; modulating the carrier based upon the received information so that the spectral energy of the modulated carrier is frequency interleaved with the chrominance and luminance components to provide a modulated signal; injecting the modulated signal into the video signal bandwidth; and transmitting the injected signal in a channel containing a signal format of said rasterized video signal.


5,587,744

IMAGE DISPLAY APPARATUS

Yasuyuki Tanaka, Tokyo, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan
Continuation of Ser. No. 176,306, Jan. 3, 1994, abandoned, which is a continuation of Ser. No. 672,837, Mar. 21, 1991, abandoned. This application May 23, 1995, Ser. No. 447,838, abandoned, application Japan, Mar. 26, 1990, 2-77493
Int. Cl.⁶ H04N 5/46

U.S. Cl. 348—556

18 Claims



1. An image display apparatus for displaying an image corresponding to an image signal, comprising:
 - (A) a first image display unit having a display screen of a first aspect ratio, for displaying the image corresponding to the image signal;
 - (B) a second image display unit having a display screen of a second aspect ratio different from said first aspect ratio, for displaying the image corresponding to the image signal;
 - (C) display selection designation means for selectively designating on which of said first image display unit and said second image display unit an image corresponding to a first image signal representative of an image having said first aspect ratio is to be displayed;
 - (D) image converting means for receiving the first image signal, converting said image having the first aspect ratio into an image having the second aspect ratio by changing a time base of the received first image signal so as to provide a horizontal scanning period of a second image signal corresponding to the image having said second aspect ratio, and outputting the image signal corresponding to the converted image having said second aspect ratio to the image display unit designated by said display selection designation means; and
 - (E) scanning control means for controlling a scanning range to the display screen of the image display unit designated by said display selection designation means, according to the aspect ratio of the display screen of the image display unit designated by said display selection designation means.

5,587,745

ADJUSTMENT OF SCAN VELOCITY MODULATION CONCURRENT WITH THE AMOUNT OF TRANSITION RISE TIME, PRE-SHOOT, AND OVERSHOOT OF A VIDEO SIGNAL


Dal F. Griepentrog, and Gene K. Sendelweck, both of Indianapolis, Ind., assignors to Thomson Consumer Electronics, Inc., Indianapolis, Ind.

Filed Jul. 5, 1994, Ser. No. 269,583
Int. Cl.⁶ H04N 5/208

U.S. Cl. 348—626

13 Claims

1. A scan velocity modulation circuit comprising:
 - a picture tube;
 - a source of a video signal;
 - a video processing stage coupled to said source for modulating an intensity of an electron beam in said picture tube responsive to said video signal;
 - edge replacement means for modulating the transition rise time of said video signal;



1. An image signal processor for obtaining an image signal having a given format from digital image data which comprises a given number of horizontal scanning lines defining one scene, each of the horizontal scanning lines being formed by digital data for every pixel, said processor comprising an addition circuit actuated in synchronism with a horizontal scan cycle for adding synchronizing data taking the same range as can be taken by said digital image data to said digital image data; a D/A conversion circuit for converting said digital image data with the synchronizing data added thereto into an analog value to form an offset image signal having an offset value in a horizontal blanking term; and an offset circuit for changing the offset value of the horizontal blanking term of said offset image signal.

5,587,746

IMAGE SIGNAL PROCESSOR FOR OBTAINING DIGITAL IMAGE SIGNALS


Toshio Nakakuki, Gifu-ken, Japan, assignor to Sanyo Electric Co., Ltd., Osaka, Japan

Filed Jun. 22, 1995, Ser. No. 493,448

Claims priority, application Japan, Jun. 24, 1994, 6-143342
Int. Cl.⁶ H04N 5/04; 5/14

U.S. Cl. 348—708

9 Claims



1. An image signal processor for obtaining an image signal having a given format from digital image data which comprises a given number of horizontal scanning lines defining one scene, each of the horizontal scanning lines being formed by digital data for every pixel, said processor comprising an addition circuit actuated in synchronism with a horizontal scan cycle for adding synchronizing data taking the same range as can be taken by said digital image data to said digital image data; a D/A conversion circuit for converting said digital image data with the synchronizing data added thereto into an analog value to form an offset image signal having an offset value in a horizontal blanking term; and an offset circuit for changing the offset value of the horizontal blanking term of said offset image signal.


5,587,747

INTERCHANGEABLE EYEGLASS LENS SYSTEM

Charles A. Bernheiser, Kent, Wash., assignor to Gargoyles, Inc., Kent, Wash.
Continuation-in-part of Ser. No. 216,528, Mar. 22, 1994, Pat. No. 5,515,116. This application Jun. 7, 1995, Ser. No. 482,291
Int. Cl.⁶ G02C 1/04; 5/00

U.S. Cl. 351—105

2 Claims



1. An interchangeable eyeglass lens system comprising:
 - a) at least one interchangeable lens;
 - b) a frame comprising a brow bar and a nosebridge, said brow bar having at least one stud disposed near a hinge end of said brow bar, said nosebridge having mounted therein a spring loaded detent mechanism for releasably interengaging a notch in an upper inner corner of one of said lenses;
 - c) said lens having at an upper outer corner a downwardly sloping nook for pivotally and releasably interengaging said stud.

5,587,748

JOYSTICK OVERRIDE CONTROL FOR AN OPHTHALMIC INSTRUMENT


David A. Luce, Clarence Center, and Donald E. Miller, West Seneca, both of N.Y., assignors to Leica Inc., Depew, N.Y.

Filed Oct. 28, 1994, Ser. No. 331,137

Int. Cl.⁶ A61B 3/14; 3/10

U.S. Cl. 351—208

9 Claims



1. An ophthalmic instrument alignment override comprising: a test axis passing through said instrument, motor drive means for moving said axis vertically; a first switch to activate said drive means in one direction, a second switch to activate said drive means in the other direction, manual means for selectively engaging said first or second switches to provide manual control of said drive means, optical means having a field of view and means for detecting the position of an eye, said optical means including signal means to generate a signal having a value representing a vertical location of the eye relative to said axis when the eye is within said field of view, and comparator means to determine when said signal means generates said signal and shift control of said drive means from said first and second switches to said signal, whereby said optical means is in exclusive control of said drive means if the eye is within said field of view.

5,587,749


APPARATUS AND METHOD FOR READING MOTION PICTURE FILM PHOTOGRAPHIC DYE SOUNDTRACKS

Paul R. Goldberg, Palo Alto, and Martin J. Richards, Redwood City, both of Calif., assignors to Dolby Laboratories Licensing Corporation, San Francisco, Calif.

Continuation-in-part of Ser. No. 322,830, Oct. 13, 1994. This application Nov. 9, 1994, Ser. No. 337,327
Int. Cl.⁶ G03B 31/02

U.S. Cl. 352—27

2 Claims



1. A combination reproducing audio signals, comprising
 - a three dye layer color motion picture film print, wherein the middle layer is a cyan layer, the print having a single-dye variable area analog soundtrack printed only in said cyan layer,
 - a light-emitting diode emitting substantially monochromatic narrow-bandwidth light in a range of wavelengths within the red portion of the spectrum, complementary to that of said cyan dye, said diode disposed to illuminate one side of the film, and
 - a signal-producing photocell or solar cell disposed on the other side of the film, opposite the diode, such that the cell senses light emitted from the diode and modulated by said single-dye soundtrack when the film is transported relative to the diode and the cell produces a signal representing the audio signals in said soundtrack.

5,587,750

FILM TRANSPORT MECHANISM


Michael A. Gibbon; Ian Maxwell, both of Oakville, Canada, and Marian Toporkiewicz, Vorau, Austria, assignors to IMAX Corporation, Toronto, Canada

Filed May 8, 1996, Ser. No. 646,581

Int. Cl.⁶ G03B 1/00

U.S. Cl. 352—184

11 Claims



1. A mechanism for intermittently transporting film past a stationary film support element, the mechanism comprising: a rotor rotatable about an axis and having a defined radius of curvature centered on said axis;

stator means co-operating with the rotor to define a film passage and including said film support element, said element having a film support surface forming part of said film passage; means upstream of said film support element for feeding film into said film passage at an input location; and, means for receiving film from said film passage at an output location downstream of said film support element; the rotor having gaps for receiving loops formed in film fed into said film passage and the rotor being rotatable about said axis to transport film through said film passage from said input location to said output location, so that successive portions of the film are laid onto and momentarily remain stationary on said film support surface of the film support element, wherein the said film support surface has a radius of curvature centered on a defined axis, wherein said radius of curvature of the rotor is significantly smaller than the radius of curvature of the film support surface, and wherein the said rotational axis of the rotor is offset from said defined axis in a direction towards said film input location by an amount sufficient to provide a predetermined minimum gap between the rotor and the film support surface at a point upstream of said defined axis.

5,587,751


INFORMATION RECORDING DEVICE AND METHOD WITH FEEDING SPEED CONTROL

Hideo Hibino; Norikazu Yokonuma, both of Kanagawa-ken; Kazuyuki Kazami, Tokyo-to, and Youichi Yamazaki, Kanagawa-ken, all of Japan, assignors to Nikon Corporation, Tokyo, Japan

Filed Sep. 19, 1995, Ser. No. 529,993
Claims priority, application Japan, Dec. 5, 1994, 6-300970
Int. Cl.⁶ G03B 17/24

U.S. Cl. 396—319

40 Claims



1. An information recording device for use in a camera for recording photographic information on a film having an information recording area, the information recording device comprising: a film feeding assembly that feeds the film within the camera at a film feeding speed during a film feeding operation; an information recording assembly that records information on the information recording area during the film feeding operation; a controller that determines whether information recording by said information recording assembly is complete before a first timing; a film feeding speed controller connected to said film feeding assembly that controls said film feeding assembly to reduce the film feeding speed at the first timing when said controller determines that information recording is complete, said film feeding speed controller further controls said film feeding assembly to reduce the film feeding speed at a second timing after the first timing when said controller determines that information recording is not complete at the first timing, and wherein said film feeding speed controller further controls

said film feeding assembly to stop film feeding at a third timing after the film feeding speed has been reduced; and a recording controller connected to said information recording assembly that controls said information recording assembly.

5,587,752

CAMERA, SYSTEM AND METHOD FOR PRODUCING COMPOSITE PHOTOGRAPHIC IMAGE


Dwight J. Petruchik, Honeoye Falls, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Jun. 5, 1995, Ser. No. 462,330

Int. Cl.⁶ G03B 17/24; 29/10; 27/52

U.S. Cl. 396—315

30 Claims



1. A system for producing a composite image comprising a photographic image and a selected prerecorded image, said selected prerecorded image being from a set containing a plurality of prerecorded images, said system comprising:

- a camera for capturing said photographic image on film, said camera including a select mechanism to select and record an identifier on said film in association with said photographic image, said identifier identifying the selected prerecorded image from the set containing the plurality of prerecorded images; and
- an integrating system including:
 - a scanner to scan said film with said photographic image and said identifier recorded thereon;
 - a retrieval mechanism responsive to said identifier scanned by said scanner to retrieve the selected prerecorded image from the set containing the plurality of prerecorded images; and
 - a computer for composing said composite image from said photographic image scanned by said scanner and the selected prerecorded image retrieved by said retrieval mechanism.

5,587,753

FILM FEEDING CONTROL DEVICE FOR ACCURATE ALIGNMENT OF FILM FRAMES AND CAMERA APERTURE

Kazuyuki Kazami, Tokyo, and Tsutomu Wakabayashi, Yokohama, both of Japan, assignors to Nikon Corporation, Tokyo, Japan


Division of Ser. No. 222,360, Apr. 4, 1994, which is a continuation of Ser. No. 801,905, Dec. 3, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 472,730

Claims priority, application Japan, Dec. 6, 1990, 2-406296; Dec. 10, 1990, 2-409808

Int. Cl.⁶ G03B 1/18

U.S. Cl. 396—397

4 Claims



1. An apparatus, comprising:

a film feeding device which feeds a film in which each frame has only two perforations, said two perforations being spaced in a longitudinal direction of the frame and being positioned adjacent to respective ends of the frame;
a perforation detection device which detects a predetermined perforation of said film;
a reproduction device which reproduces clock data recorded on a magnetic recording medium coated on the film;
a counting device which is electrically connected to said reproduction device to count the clock data reproduced by said reproduction device;
a control circuit which is electrically connected to said perforation detection device to stop film feeding of said film feeding device and start counting the clock data by said counting device at substantially the same time when the film feeding is stopped when said perforation detection device detects said predetermined perforation; and
a conversion device which is electrically connected to said counting device to convert the counted clock data into a film feed overrun amount and output the film feed overrun amount.

5,587,754

CAMERA WITH GUIDING OF RECTILINEAR LENS MOVEMENT

Akira Katayama, Koganei, and Hiroshi Terunuma, Ichikawa, both of Japan, assignors to Nikon Corporation, Tokyo, Japan


Division of Ser. No. 418,899, Apr. 7, 1995, abandoned, which is a continuation of Ser. No. 270,319, Jul. 5, 1994, abandoned, which is a continuation of Ser. No. 138,385, Oct. 20, 1993, abandoned, which is a continuation of Ser. No. 717,346, Jun. 18, 1991, abandoned, which is a continuation-in-part of Ser. No. 607,710, Nov. 1, 1990, abandoned. This application Jun. 7, 1995, Ser. No. 474,667

Claims priority, application Japan, Nov. 6, 1989, 1-287603; Nov. 14, 1989, 1-131661; Nov. 20, 1989, 1-133980; Nov. 20, 1989, 1-299568; Jun. 22, 1990, 2-065494

Int. Cl.⁶ G02B 15/00

U.S. Cl. 396—144

2 Claims



1. A camera having a camera housing and comprising:
a holding member that holds an imaging lens and that has a first helicoid formed around an optical axis of said lens;
a rotary member having a second helicoid which engages said first helicoid and which is rotatable about said optical axis relative to said camera housing;
a first guide member which has two guide surfaces extending parallel to said optical axis; and
a second guide member which has at least one pair of rotary elements disposed at positions spaced circumferentially with respect to said optical axis, said rotary elements of said one pair contacting said guide surfaces, respectively, of said first guide member;
one of said first and second guide members being fixed to said holding member and the other of said first and second guide members being fixed to said camera housing, so that contact of said guide surfaces and said rotary elements prevents rotation of said holding member about said optical axis and

allows said holding member to move rectilinearly along said optical axis in accordance with rotation of said rotary member.

5,587,755

VARIABLE FORMAT VIEWFINDER FOR CAMERA


Matthew Wilson, Rochester, and Frank P. Lauricella, Brockport, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Jan. 11, 1995, Ser. No. 371,340

Int. Cl.⁶ G03B 13/10

U.S. Cl. 396—380

2 Claims



1. A variable format viewfinder for a camera comprising masking blades movable to change the format of the view through said viewfinder to match the format of a picture to be taken, is characterized in that:

said masking blades have respective different aspect ratio indicators which are individually uncovered by one of the masking blades each time the one blade is moved to change the format of the view through said viewfinder, to permit an uncovered indicator to be seen to identify the particular aspect ratio of the picture to be taken.

5,587,756

FILM CARTRIDGE WITH VISUAL INDICATOR FOR VERIFYING FILM LOADING IN CAMERA


Madhav Mehra, and Joseph A. Manico, both of Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Jan. 16, 1996, Ser. No. 586,520

Int. Cl.⁶ G03B 17/26; 23/02

U.S. Cl. 396—515

6 Claims



1. A film cartridge comprising a housing having a film exit slit, and a film roll support rotatable inside said housing to unwind a filmstrip from said film roll support to permit said filmstrip to be moved outwardly through said slit, is characterized by:
an indicator for providing a visible indication that said filmstrip has been moved outwardly through said slit;
a cover strip covering said indicator to prevent the indicator from being seen;
a tether having forward means located at said slit for releasably engaging said filmstrip and rearward means releasably engaging said cover strip;
engageable means located on said filmstrip for engagement with said forward means as the filmstrip is moved outwardly

through said slit, to make said tether move with the filmstrip to draw said cover strip off said indicator; and return spring means for urging said tether to disengage said forward means from said engageable means and said rearward means from said cover strip after the cover strip is drawn off said indicator.


5,587,757

CAMERA ACCESS DOOR INTERLOCK MECHANISM
Tom Seamans, Corfu, and Stanley W. Stephenson, III, Spencerport, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Feb. 15, 1995, Ser. No. 388,785
Int. Cl.⁶ G03B 17/02

U.S. Cl. 396—536

7 Claims



1. A camera comprising a body having a chamber sized for containing a film cartridge, said film cartridge having a rotatable film spool for retaining a filmstrip and indicator means for indicating the exposure status of the retained filmstrip based on the rotational position of said film spool, and an access door for opening and closing said chamber, is characterized by:

- an interlock mechanism connected to said access door and engageable with said spool of a loaded film cartridge for preventing said access door from opening until said spool is in a fixed rotational position to indicate the filmstrip is exposed wherein said interlock mechanism includes:
- a spool engagement element engageable with the drive socket of said spool for sensing spool rotation;
- a cam element cooperable with said spool engagement element, said cam element having a cam with a riser corresponding to the exposed position of said spool in said cartridge;
- a lever engageable by said cam riser; said lever being selectively movable between a plurality of positions dependent on the rotational position of said cam element; and
- a latching assembly defined in part by said lever for selectively securing said access door and releasing said access door in response to the rotational position of said cam element.

5,587,758

PHOTO-DEVELOPING APPARATUS

Kazunobu Shima, and Yuji Yamamoto, both of Wakayama, Japan, assignors to Noritsu Koki Co., Ltd., Wakayama-ken, Japan

Filed Oct. 18, 1995, Ser. No. 544,533


Claims priority, application Japan, Oct. 19, 1994, 6-253659; Jan. 10, 1995, 7-002175; Sep. 6, 1995, 7-229244
Int. Cl.⁶ G03D 3/08; 13/00

U.S. Cl. 396—613

28 Claims

1. A photo-developing apparatus cutting a rolled-paper pulled out from a magazine into a desired length of sheet paper, printing the sheet paper in a printing unit and developing the sheet paper in a developing unit, comprising:

direction switching means in a transfer passage shifting the sheet paper to the developing unit from the printing unit, the direc-



tion switching means being disposed for rotating the sheet paper sent from the printing unit to change its direction within the range from 70 degree to 110 degree or from 250 degree to 290 degree.

5,587,759

AUTOMATIC DEVELOPING APPARATUS FOR SILVER HALIDE PHOTOSENSITIVE MATERIALS


Noriaki Kurata, Hino, Japan, assignor to Konica Corporation, Tokyo, Japan

Filed Apr. 17, 1995, Ser. No. 423,297

Claims priority, application Japan, Apr. 30, 1994, 6-114285
Int. Cl.⁶ G03D 3/02

U.S. Cl. 396—630

16 Claims



1. An apparatus for processing a silver halide photographic material with a processing solution, comprising:
 - a processing tank in which the processing solution is stored;
 - a dissolving section for dissolving a solid processing agent, the dissolving section communicated with the processing tank so that the processing solution is circulated between the processing tank and the dissolving section;
 - an accommodation member in which the solid processing agent is stored;
 - a supply member having an inlet opening with which the accommodation member is detachably connected and an outlet opening so that the supply member receives the solid processing agent through the inlet opening and discharges the solid processing agent through the outlet opening; and
 - a processing agent supply section in which the accommodation member and the supply member are constructed in a single body, the processing agent supply section movable together with the accommodation member and the supply member between a first position and a second position, wherein the supply member is connected with the dissolving section in the first position so that the solid processing agent is supplied from the outlet opening of the supply member into the dissolving section, and the supply member is disconnected from

the dissolving section in the second position so that the outlet opening of the supply member is isolated from the dissolving section.

5,587,760

AUTOMATIC DEVELOPING APPARATUS USED FOR SILVER HALIDE PHOTOSENSITIVE MATERIAL


Noriaki Kurata, and Kenji Kuwae, both of Tokyo, Japan, assignors to Konica Corporation, Tokyo, Japan

Filed May 1, 1995, Ser. No. 432,510

Claims priority, application Japan, May 12, 1994, 6-098848
Int. Cl.⁶ G03D 3/02

U.S. Cl. 396—630

24 Claims



1. An apparatus for processing a silver halide photographic material with a processing solution, comprising:
 - a tank in which the processing solution is stored;
 - replenishing means for replenishing a solid processing agent into the processing solution in the tank in which the solid processing agent is dissolved in the processing solution, the replenishing means positioned above the level of the processing solution so that the solid processing agent is dropped from the replenishing means to the processing solution; and
 - a guide passage constructing member comprising an inner wall surface forming and enclosing a guide passage, said guide passage constructing member being provided between the replenishing means and the processing solution and guiding the dropped solid processing agent along the enclosed guide passage and discharging the dropped solid processing agent through an exit opening of the enclosed guide passage into the processing solution, the guide passage constructing member so arranged that a part of the enclosed guide passage is inclined to a horizontal plane and having a ventilating opening to communicate between an enclosed space in the enclosed guide passage and an outer space of the enclosed guide passage separately from the exit opening.

5,587,761

AUTOMATIC FOCUSING APPARATUS

Yosuke Kusaka; Masaru Muramatsu; Ken Utogawa, all of Yokohama, and Shozo Yamano, Tokyo, all of Japan, assignors to Nikon Corporation, Tokyo, Japan

Continuation of Ser. No. 825,810, Jan. 21, 1992, abandoned, which is a continuation of Ser. No. 727,382, Jul. 5, 1991, abandoned, which is a continuation of Ser. No. 453,203, Dec. 26, 1989, abandoned, which is a continuation of Ser. No. 350,463, May 11, 1989, abandoned. This application May 17, 1995, Ser. No. 443,393


Claims priority, application Japan, May 13, 1988, 63-116171; Jul. 20, 1988, 63-179112; Oct. 3, 1988, 63-250600

Int. Cl.⁶ G03B 13/00

U.S. Cl. 396—95

12 Claims

1. A camera having an autofocus mechanism, comprising:



focus detecting means for repeatedly detecting a focusing state of an objective lens with respect to a photographic object and outputting a focus adjustment signal;

object detecting means for detecting movement of the object to be photographed in accordance with a plurality of said focus adjustment signals and outputting a movement signal;

lens drive amount determining means for determining an amount of lens drive in accordance with said movement signal;

signal generating means for generating a signal indicative of a characteristic value of said objective lens;

compensating means for producing an amount of compensation in accordance with said characteristic value, and compensating the amount of lens drive based on said amount of compensation; and

lens drive means for driving said objective lens based on the amount of lens drive as compensated.

5,587,762

AUTOMATIC FOCUSING DEVICE


Toshimi Watanabe, Kanagawa-ken, Japan, assignor to Nikon Corporation, Tokyo, Japan

Filed Aug. 9, 1995, Ser. No. 512,981

Claims priority, application Japan, Sep. 7, 1994, 6-213400
Int. Cl.⁶ G03B 13/36

U.S. Cl. 396—95

23 Claims



1. An auto-focus adjustment device comprising:
 - a focus detecting section that repeatedly detects a focus state of a photo lens;
 - a moving velocity determining section that determines at least a first velocity and a second velocity related to the movement of an object based on the focus states detected by said focus detecting section;

an acceleration determining section that determines an acceleration of the object based on the first velocity and second velocity determined by said moving velocity determining section;

a velocity ratio determining device that determines a velocity ratio for the object based on the determined velocities from said moving velocity determining section; and

a forecast section that forecasts a position of the object based on the determined velocities, the velocity ratio, and the acceleration.

5,587,763

FOCUS DETECTION DEVICE AND METHOD

Shigeyuki Uchiyama, Tokyo, Japan, assignor to Nikon Corporation, Tokyo, Japan


Filed Jun. 30, 1995, Ser. No. 497,153

Claims priority, application Japan, Sep. 6, 1994, 6-212491

Int. Cl.⁶ G03B 3/00

U.S. Cl. 396—114

20 Claims



1. A focus detection device that determines a focus adjustment amount of a photo-optical system having at least an object lens, the focus detection device comprising:

- a pair of photoelectric line image sensor arrays having a plurality of photoelectric conversion elements, the pair of photoelectric line image sensor arrays being capable of outputting a pair of signal strings corresponding to light intensity distributions from a pair of subject images;
- a focus detection optical system that guides at least a pair of light rays from a subject through the object lens and to the pair of photoelectric line image sensor arrays to form the pair of subject images;
- a controller having a focus detection algorithm section that determines focus adjustment condition of the object lens based on the pair of signal strings;
- a memory that stores an error or offset amount between the pair of signal strings when the system is in a focused condition; and
- a signal extractor that selects a pair of effective signal strings from the pair of signal strings based on a value relating to the error amount stored in the memory, wherein the controller computes a focus adjustment amount based on the pair of effective signal strings selected by the signal extractor.

5,587,764

CAMERA-SHAKE CORRECTING CAMERA

Toshiyuki Nakamura, Tokyo, and Yoshikazu Iida, Chigasaki, both of Japan, assignors to Nikon Corporation, Tokyo, Japan

Continuation of Ser. No. 135,615, Oct. 14, 1993, abandoned.

This application Nov. 21, 1995, Ser. No. 561,157

Claims priority, application Japan, Oct. 30, 1992, 4-292335


Int. Cl.⁶ G03B 3/00; 17/00

U.S. Cl. 396—55

3 Claims

1. A camera-shake correcting camera which corrects a camera shake by moving a camera-shake correcting system forming a part of a phototaking optical system, comprising:

- a first controller to control movement of said camera-shake correcting system;



- a second controller to execute a sequence control of said camera-shake correcting camera;
- a first data transfer device to transfer data serially between said first controller and said second controller; and
- a second data transfer device, separate from said first data transfer device, to transfer a binary signal corresponding to a camera operation state between said first controller and said second controller, said second data transfer device performing the data transfer of the binary signal while said first controller is controlling said camera-shake correcting system.

5,587,765

CAMERA CAPABLE OF PERFORMING DIVISIONAL PHOTOMETRY

Tetsuro Goto, Funabashi, Japan, assignor to Nikon Corporation, Tokyo, Japan

Continuation of Ser. No. 145,503, Nov. 4, 1993, abandoned.


This application May 25, 1995, Ser. No. 450,223

Claims priority, application Japan, Nov. 5, 1992, 4-296028

Int. Cl.⁶ G03B 7/08

U.S. Cl. 396—234

19 Claims



1. A camera capable of performing divisional photometry, comprising:

- a photometric sensor having a plurality of photoelectric conversion sub-elements arranged in close proximity to one another over a predetermined light receiving region in a two dimensional array; and which performs photometry on the photographic field divided into a plurality of regions;
- an image projection optical system that projects an image of a photographic field upon light receiving surfaces of a proper subset of said plurality of photoelectric conversion sub-elements which occupies a region which is smaller than said light receiving region;

a mode setting device that sets either of a photographic mode and a field determination mode according to the actuation of an operating member;

a determination device that, when said field determination mode is set, based upon the photometric outputs from said plurality of photoelectric conversion sub-elements, determines for each of said plurality of photoelectric conversion sub-elements whether it is a valid sub-element which is included in said proper subset of said plurality of photoelectric conversion sub-elements upon which said image of said photographic field falls, or an invalid sub-element which is not included in said proper subset of said plurality of photoelectric conversion sub-elements upon which said image of said photographic field falls;

a storage device that stores the results of said determinations performed by said determination device;

a selection device that, based upon the information stored by said storage device, selects said valid sub-elements from said plurality of photoelectric conversion sub-elements; and

a calculation device that calculates an exposure value based upon the photometric outputs from said valid photoelectric conversion sub-elements selected by said selection device.

5,587,766

CAMERA WHICH SETS AN INTERNAL APERTURE VALUE IN ACCORDANCE WITH A CONVERTED PHOTOGRAPHIC LENS APERTURE VALUE

Koichiro Kawamura, Ichihara, and Ryo Uehara, Yokohama, both of Japan, assignors to Nikon Corporation, Tokyo, Japan


Filed Aug. 17, 1995, Ser. No. 516,140

Claims priority, application Japan, Feb. 13, 1995, 7-024254

Int. Cl.⁶ G03B 7/095; 7/097; 7/20; 17/18

U.S. Cl. 396—257

10 Claims



1. A camera having a photographic lens installable thereon, the photographic lens including a photographic lens aperture having an open aperture value, the camera comprising:

- a reduction optical system which reduces an optical image formed by the photographic lens when the photographic lens is installed on the camera, the optical image being reduced by a reduction ratio;
- an internal aperture having a settable aperture value and which restricts light passing through the photographic lens and the reduction optical system when the photographic lens is installed on the camera; and
- a control unit which receives the open aperture value of the photographic lens aperture when the photographic lens is installed on the camera, converts the open aperture value in accordance with the reduction ratio of the reduction optical

system, and sets an aperture value of the internal aperture in a range having a lower limit of approximately the converted open aperture value.

5,587,767

DIGITAL FILM HEAT PROCESSOR AND METHOD OF DEVELOPING DIGITAL FILM


Abu S. Islam, Mt. Vernon; Robert J. Kleckner, Yorktown Hgts.; Leo Chin, Bronx, all of N.Y.; Hardy Sonnenberg, Puslinch, Canada, and Anthony A. Klein, Swampscott, Mass., assignors to Xerox Corporation, Stamford, Conn.

Filed May 4, 1995, Ser. No. 434,960

Int. Cl.⁶ G03B 27/32; G03D 13/00

U.S. Cl. 355—27

21 Claims



1. A digital film processor, comprising:

- a digital film support surface configured to support digital film thereon; and
 - heating means for developing the digital film supported on the digital film support surface by applying heat directly to the digital film without contacting the digital film;
- said digital film processor defining a heating region that is open to ambient atmosphere and being configured so that the digital film does not physically contact any member capable of distorting physical properties of the digital film.

5,587,768

PHOTOGRAPHIC PROJECTOR-PRINTER ASSEMBLY

Takashi Yamamoto; Yasunobu Sakaguchi, and Makoto Utsugi, all of Kaisei-machi, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Apr. 17, 1992, Ser. No. 870,302

Claims priority, application Japan, Apr. 24, 1991, 3-094033

Int. Cl.⁶ G03B 27/52

U.S. Cl. 355—41

7 Claims



1. A camera having a photographic lens installable thereon, the photographic lens including a photographic lens aperture having an open aperture value, the camera comprising:

- a reduction optical system which reduces an optical image formed by the photographic lens when the photographic lens is installed on the camera, the optical image being reduced by a reduction ratio;
- an internal aperture having a settable aperture value and which restricts light passing through the photographic lens and the reduction optical system when the photographic lens is installed on the camera; and
- a control unit which receives the open aperture value of the photographic lens aperture when the photographic lens is installed on the camera, converts the open aperture value in accordance with the reduction ratio of the reduction optical

1. A photographic projector-printer assembly for projecting a negative film onto a photographic paper through a projecting lens for photographic printing, in which a part of the light from the negative film can be used for photometry and monitoring an image on the negative film, wherein said projecting lens is provided on its object side, as an integral piece, with an optical path-splitting prism for splitting the light for the photometric and monitoring purposes on the optical path, wherein said projecting lens is movably mounted on the assembly body so as to achieve focus

regulation in the optical axis direction and said optical path-splitting prism is adjustable in the optical axis direction and around the optical axis in terms of its position with respect to said projecting lens.

5,587,769

IMAGE FORMING APPARATUS ALLOWING SIMPLE REPLACEMENT OF INTERMEDIATE TRANSFER MEMBER AND EASY MAINTENANCE AND HANDLING OF PAPER JAMS


Kenji Sawada, Toyokawa; Masahiro Sato, Toyohashi; Hitoshi Sekino, and Masashi Sakamoto, both of Toyokawa, all of Japan, assignors to Minolta Co., Ltd., Osaka, Japan

Filed Nov. 7, 1995, Ser. No. 554,547

Claims priority, application Japan, Nov. 11, 1994, 6-277533
Int. Cl.⁶ G03G 15/00

U.S. Cl. 355—200

8 Claims



1. An image forming apparatus comprising:
an apparatus housing having a releasible and movable side frame, and stationary side frame,
a photosensitive unit having a photosensitive member and which is detachably mounted on said movable side frame, and
an intermediate transfer unit having an intermediate transfer member for temporarily receiving a transferred toner image formed on the surface of said photosensitive member in a primary transfer, and transferring said temporarily transfer toner image to a recording sheet in secondary transfer, said intermediate transfer unit being detachably mounted on said movable side frame.

5,587,770

DEVICE FOR DETECTING REMAINING LEVEL OF TONER

Hae-Seog Jo; Chang-Kyung Ko, and Dong-Ho Lee, all of Suwon, Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea

Filed Feb. 17, 1995, Ser. No. 389,942


Claims priority, application Rep. of Korea, Feb. 28, 1994, 3776/1994

Int. Cl.⁶ G03G 15/08

U.S. Cl. 355—208

21 Claims

1. A developing device of an electrophotographic recording system developing an electrostatic latent image formed on a photosensitive drum into a visible image, said device comprising:
toner storing means for storing toner;
developing means for developing said electrostatic latent image formed on said photosensitive drum by said toner stored in said toner storing means;
a toner detecting device for detecting one of an existence and non-existence of said toner, said toner detecting device comprising:
first and second light-emitting means for emitting light from a first side of said toner storing means at first and second



predetermined heights from a bottom portion of said toner storing means, respectively; and
first and second light-receiving elements positioned on an interior of said toner storing means for respectively outputting first and second corresponding signals indicative of a remaining amount of said toner in response to an amount of light received from said first and second light-emitting means, respectively;

an agitator for conveying said toner stored in said toner storing means to said developing means while simultaneously cleaning a light-emitting side of said first and second light-emitting means and a light-receiving side of said first and second light-receiving elements in correspondence with a rotational period of said agitator; and
determining means for comparing a value obtained during a given time period by counting signals resulting from logically adding said first and second corresponding signals with a predetermined value to determine a remaining level of said toner.

5,587,771

IMAGE SAMPLING AND COLOR SHIFT CORRECTION SYSTEM IN MULTIPLE IMAGE FORMING APPARATUS


Hirotsuka Mori, and Ryo Ando, both of Kanagawa, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan

Filed Apr. 17, 1995, Ser. No. 422,808

Claims priority, application Japan, Jun. 17, 1994, 6-135525
Int. Cl.⁶ G03G 15/01

U.S. Cl. 355—208

20 Claims



1. An image sampling and color shift correction system in a multiple image forming apparatus for forming a multiple image by providing a plurality of image output means along a transfer belt, said system comprising:

image control means which applies image data to respective said image output means for controlling image formation;

pattern generator means for repeatedly generating a register shift measurement pattern in a main scanning direction and a sub-scanning direction of said respective image output means, the register shift measurement pattern being formed outside the largest paper area;

sampling means for sampling an image formed by said respective image output means at both sides of a paper area on the transfer belt in the main scanning direction of the transfer belt;

processing means which takes data sampled by said sampling means for processing an amount of register shift; and
control means for controlling the image output means and the image sampling means to execute a correction operation in an area between a same one pair of the plurality of image output means.

5,587,772

IMAGE FORMING APPARATUS HAVING IMAGE SIGNAL DISCRIMINATION DEVICE


Kazuhiko Arai; Yasuhiro Oda; Masahiko Kubo; Masayo Higashimura; Kazuhiro Iwaoka, and Takayuki Yamashita, all of Nakai-machi, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan

Filed Oct. 17, 1995, Ser. No. 543,911

Claims priority, application Japan, Dec. 12, 1994, 6-331437
Int. Cl.⁶ G03G 15/04

U.S. Cl. 355—208

20 Claims



1. An image forming apparatus comprising:

image signal discrimination means for discriminating whether an image density signal belongs to a line image portion or a natural image portion including a halftone image and outputting a discrimination signal;

first image density conversion means having a first conversion property for converting said image density signal to a conversion signal and outputting said conversion signal;

second image density conversion means having a second conversion property which is different from said first conversion property for converting a part of said image density signal corresponding to a low density portion to a conversion signal indicating a value within a range in which an image is not developed and outputting said conversion signal;

selection means for alternately selecting said first or second image density conversion means with a predetermined period;

pulse width modulation means for modulating pulse widths of said conversion signals output from said first and second image density signal conversion means and outputting a pulse width modulation signal;

pulse width modulation signal period changing means for changing a period of said pulse width modulation signal output from said pulse width modulation means and the period of selection by said selection means in accordance with said discrimination signal output from said image density signal discriminating means; and

image formation means for forming an image in accordance with said pulse width modulation signal output from said pulse width modulation means.

5,587,773

ELECTROPHOTOGRAPHIC APPARATUS FOR PERFORMING IMAGE EXPOSURE AND DEVELOPMENT SIMULTANEOUSLY

Hideyuki Yano; Junji Araya, both of Yokohama; Yukihiro Oze, Tokyo; Harumi Kugo, Kawasaki; Katsuhiko Sakaizawa, Tokyo; Tadashi Furuya, and Osamu Iwasaki, both of Yokohama, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 172,053, Dec. 23, 1993, abandoned.

This application Dec. 30, 1994, Ser. No. 366,431

Claims priority, application Japan, Dec. 26, 1992, 4-359310
Int. Cl.⁶ G03G 15/00

U.S. Cl. 355—210

4 Claims



1. An electrophotographic apparatus for forming an image on an endless electrophotographic photosensitive member by exposing one side of the electrophotographic photosensitive member to a light image and supplying a developer to the other side of the photosensitive member, said electrophotographic photosensitive member including a conductive layer disposed on a translucent substrate, a photosensitive layer made of an organic photoconductive material and disposed on the conductive layer, and an electric charge pour-in layer made of an insulative binder in which conductive powder is dispersed, said apparatus comprising:

optical means for exposing an interior side of the translucent substrate of said electrophotographic photosensitive member to a light image; and

developing means disposed at a position corresponding to an exposure position of said electrophotographic photosensitive member by said optical means, for forming a magnetic developer brush having a magnetic conductive carrier and an insulative toner to which a bias is applied, said brush being contactable with a surface of said electrophotographic photosensitive member, spanning an upstream side and a downstream side of the exposure position.

wherein said photosensitive member is charged by supplying electric charge into the electric charge pour-in layer upstream of the exposure position of said electrophotographic photosensitive member in a moving direction thereof by the magnetic brush, and wherein the insulative binder and the conductive powder are colored.

5,587,774

CLEANERLESS ELECTROGRAPHIC IMAGING DEVICE

Akira Nagahara; Sachio Sasaki; Mitsuhiro Furukawa; Tsuneo Watanuki; Norio Sawatari, all of Kawasaki; Mikio Amaya, Atsugi, and Toshiaki Narusawa, Kawasaki, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan

Filed May 4, 1995, Ser. No. 434,991

Claims priority, application Japan, Aug. 11, 1994, 6-189680

Int. Cl.⁶ G03G 15/02; 15/08


U.S. Cl. 355—219

64 Claims

1. An imaging device, for use in an electrophotographic imaging process, which comprises:

an image-carrying element;

image exposure means for forming a charged latent image on a surface of the image-carrying element;



when the first region is in the developing zone before the generation of the electric field is different from that applied when the second region having been discharged by said discharging means is in the developing zone.


5,587,781 OPTIMIZING ELECTROSTATIC BRUSH INTERFERENCES FOR INCREASED DETONING EFFICIENCY

Ronald E. Auty, Rochester, and Dennis G. Gerbasi, Webster, both of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Dec. 1, 1995, Ser. No. 566,098
Int. Cl.⁶ G03G 21/00

U.S. Cl. 355—301

11 Claims



1. An apparatus for removing particles from an imaging surface, comprising:

- means for cleaning particles from the imaging surface, said removing means and the surface having a first interference therebetween; and
- means for removing particles from said cleaning means, said cleaning means and said removing means having a second interference therebetween, the second interference being greater than the first interference.

5,587,782 COPYING MACHINE FOR COPYING DOCUMENTS IN TWO-IN-ONE MODE


Akiyoshi Johdai, Toyokawa; Akira Ohhata, Toyohashi; Hiroki Yamashita, Okazaki; Hirokazu Matsuo, Toyohashi, and Yoshihito Hirano, Toyokawa, all of Japan, assignors to Minolta Co., Ltd., Osaka, Japan

Filed Feb. 27, 1995, Ser. No. 394,837

Claims priority, application Japan, Feb. 28, 1994, 6-055212
Int. Cl.⁶ G03G 15/00

U.S. Cl. 355—309

12 Claims



1. A copying machine having a two-in-one copying mode in which two document sheets are fed on a glass platen in series with respect to a document conveying direction and copied onto one copy sheet by one-time exposure scanning, the copying machine comprising:

- a document feeder means for feeding document sheets toward the glass platen one by one to stop the document sheets at a

first-out position which is situated on an upstream side of the document conveying direction;

- a first conveying means for conveying the document sheets fed by the document feeder means onto the glass platen;
 - a second conveying means for conveying the document sheets conveyed by the first conveying means along the glass platen until the rear end of the document sheets reach a predetermined switch-back position, conveying the document sheets in the opposite direction to retreat a predetermined distance, conveying a first of the document sheets as well as a succeeding second document sheet stopped at the first-out position such that the front end of the first document sheet situated on a downstream side of the document conveying direction may be aligned with an exposure reference, and discharging the first and second document sheets to the downstream side of the document conveying direction after exposure; and
 - a third conveying means for conveying the document sheets discharged by the second conveying means from the glass platen to a discharge section;
- whereby the document conveying length (d3) from the exposure reference to the third conveying means is longer than the sum (d4+Δdp) of the document conveying length (d4) from the first-out position to the switch-back position and the difference length (Δdp) of the document conveying direction between a document sheet having a longest length and a document sheet having a shortest length among document sheets to be handled in the two-in-one mode.

5,587,783 COLOR ELECTROPHOTOGRAPHIC APPARATUS HAVING AN INTERMEDIATE TRANSFER BELT VARIABLE IN SPEED


Masahiko Nakamura, Yao; Hajime Yamamoto, Ibaraki, and Hiroshi Terada, Ikoma, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Sep. 12, 1994, Ser. No. 304,767

Claims priority, application Japan, Sep. 16, 1993, 5-230070; Sep. 22, 1993, 5-236224; Nov. 1, 1993, 5-273434; Nov. 5, 1993, 5-276407; Jan. 28, 1994, 6-008257; Jan. 28, 1994, 6-008258
Int. Cl.⁶ G03G 15/01

U.S. Cl. 355—326 R

13 Claims



1. A color electrophotographic apparatus comprising:

- an image forming unit group containing a plurality of image forming units, each image forming unit comprising a photosensitive member, and developing means having a toner of different color than others and forming a toner image on the photosensitive member;
- a movable transfer member on which the toner image on the photosensitive member is overlaid and transferred at a transfer position, and a color image is formed;
- driving means for driving by selecting as a moving speed of the transfer member, a first running speed used when forming an image or a second running speed slower than the first running speed, said second running speed including a stopping state of the transfer member;
- exposure means for exposing the image at an exposure position, said exposure position being a specific distance from the transfer position, and

moving means for moving the image forming unit group to sequentially position each image forming unit at an image forming position defining said exposure position and transfer position, wherein the transfer member is driven at the second running speed while the image forming unit group is moving.

5,587,784 MULTISPECTRAL-STARING SENSOR


Michael Y. Pines, Los Angeles, and Donald F. King, Playa Del Rey, both of Calif., assignors to Hughes Electronics, Los Angeles, Calif.

Filed Jun. 16, 1995, Ser. No. 491,133

Int. Cl.⁶ G01C 3/08; G01J 5/02

U.S. Cl. 356—4.01

19 Claims



1. A multispectral imaging sensor comprising:

- first means for sensing electromagnetic energy, the first means including a broadband detector capable of sensing energy in multiple bands of an electromagnetic spectrum;
- second means in alignment with the first means for selectively filtering the electromagnetic energy for input to the first means, the second means including:
 - a first filter with a first passband,
 - a second filter with a second passband, and
 - means for selectively positioning either the first filter or the second filter in optical alignment with the first means; and
- third means for directing electromagnetic energy from an input aperture to the second means.

5,587,785 LASER DOPPLER VELOCIMETER

Satoru Kato, Hiroshi Ito, Tadashi Ichikawa, and Manabu Kagami, all of Aichi-ken, Japan, assignors to Kabushiki Kaisha Toyota Chuo Kenkyusho, Aichi-ken, Japan


Filed Mar. 21, 1995, Ser. No. 407,671

Claims priority, application Japan, Mar. 22, 1994, 6-050690; Feb. 28, 1995, 7-040933

Int. Cl.⁶ G01D 3/36

U.S. Cl. 356—28.5

10 Claims



1. A laser Doppler velocimeter comprising:

- a light source for emitting laser light whose frequency changes continuously for at least a fixed time duration;
- a branching device for branching the laser light emitted from said light source into at least two beams;

at least one pair of optical fibers for transmitting each of the laser beams branched by said branching device, said optical fibers having an optical path difference therebetween;

at least one focusing device for focusing the laser beams transmitted by said optical fibers onto a region to be measured;

at least one incident device upon which is projected scattered light from the region to be measured where the laser beams are focused;

a light-receiving device for receiving the scattered light from said incident device; and

a calculating device for calculating at least one Doppler shift frequency in the region to be measured on the basis of a frequency of a signal of the scattered light received by said light-receiving device, said optical path difference, and a rate of change of the frequency of the laser light.

5,587,786

APPARATUS FOR MEASURING A BEAM WIDTH D_{0x} ALONG A TRANSVERSE DIRECTION OF A LASER BEAM AND METHOD THEREOF


Yves Champagne, Sainte-Foy; Claude Paré, Saint-Augustin-de-Desmaures, and Pierre-André Bélanger, Sainte-Foy, all of Canada, assignors to Université Laval, Québec, Canada

Filed Feb. 23, 1995, Ser. No. 393,572

Int. Cl.⁶ G01J 1/00

U.S. Cl. 356—121

19 Claims



1. A method for measuring a beam width D_{0x} along a transverse direction of a laser beam having a full power P₀ and a given optical irradiance distribution, the method comprising the steps of:

- (a) scanning a transverse direction X of a first optical filter with the laser beam to produce a first light signal modified by the filter during the scanning, the filter having a transmittance or reflectance profile M(x) varying along the transverse direction X and characterized by lines of constant transmittance or reflectance along a transverse direction Y which is perpendicular to the direction X, the profile M(x) varying along the direction X according to a one-dimensional inverted parabola with a central maximum M_{max} and two peripheral minima M_{min} separated by a distance W_F where a part of the laser beam falling outside the peripheral minima M_{min} of the inverted parabola is substantially blocked, the profile M(x) being defined by the following equation:

$$M(x) = M_{max} - \frac{4(M_{max} - M_{min})}{W_F^2} (x - x_c)^2$$

where M_{min}, M_{max} and W_F are predetermined constants and x_c is the value of x at a central position along the distance W_F.

- W_F being wide enough so that a part of the laser beam which spills past boundaries determined by minima M_{min} is negligible when the profile $M(x)$ is centered on the optical irradiance distribution of the laser beam;
- (b) detecting the light signal produced in step (a) to determine a maximum power value P_{max} ; and
- (c) calculating the beam width D_{ax} by means of the following equation:

$$D_{ax} = \left\{ \frac{4W_F^2}{(M_{max} - M_{min})} \left(M_{max} - \frac{P_{max}}{P_0} \right) \right\}^{1/2}$$

5,587,787

PROCESS FOR MEASURING RELATIVE ANGLES

Heinz Jäger, Volketswil, Switzerland, assignor to J. Müller AG, Volketswil, Switzerland

PCT No. PCT/CH93/00097, § 371 Date Feb. 22, 1994, § 102(e) Date Feb. 22, 1994, PCT Pub. No. WO94/00778, PCT Pub. Date Jan. 6, 1994


PCT Filed Apr. 15, 1993, Ser. No. 199,167

Claims priority, application Switzerland, Jun. 22, 1992, 01965/92

Int. Cl. G01B 11/26; G01C 3/08; G02B 26/08

U.S. Cl. 356—141.1

7 Claims



1. A measuring apparatus for measuring relative angles between a reference direction of a measuring platform and remote points using light rays which emanate from the measuring platform, said measuring device including:

- a housing which is mounted for rotation about a rotation axis, a first light transmitter mounted in said housing for emitting a first fan ray of light from said housing such that a light ray thereof which defines an axis of said first fan ray of light is perpendicular to said rotation axis, a first lens mounted on said housing to receive light reflected from said first fan ray of light by a remote point, a first fiber optic light guide located in said housing, said first fiber optic light guide extending along said housing axis and defining a first end for receiving light from said first lens and a second end for emitting light therefrom,
- a light-sensitive sensor for receiving light passing out of said second end of said first fiber optic guide, and
- evaluation means including a pulse counter connected to said light-sensitive sensor for counting time pulses from when said first fan ray of light passes through a reference direction at a start of an angular range of rotation to (a) when light reflected from said remote points is guided by said first optic light guide to said sensor and (b) when said first fan ray of light passes through an end of said angular range of rotation, and
- a computer means for comparing said time pulse counts to determine relative angles between said reference direction and said remote points.


5,587,788
SAMPLING APPARATUS FOR INLINE
SPECTROGRAPHIC ANALYSIS OF VISCOUS
MATERIALS

John E. Slaughter, Richardson; George Olson, Plano, both of Tex., and William J. McShane, Arlington Heights, Ill., assignors to Texas Instruments Incorporated, Dallas, Tex. Continuation of Ser. No. 378,903, Jan. 26, 1995, abandoned, which is a continuation of Ser. No. 98,554, Jul. 28, 1993. This application Jan. 22, 1996, Ser. No. 589,812

Int. Cl. G01N 21/01

U.S. Cl. 356—246

8 Claims



1. A probe assembly for sampling a sample of a fluid, comprising:
- and longitudinal member having a first aperture to receive and hold said sample of the fluid at a first position and a second aperture being a transparent window for normalization with a light transmission apparatus at a second position;
 - a sleeve having an aperture to slidably engage said longitudinal member, said sleeve having slots for positioning said light transmission apparatus and wherein said second aperture aligns with said slots for said normalization with said light transmission apparatus; and
 - means for sliding said longitudinal member between said first position where said first aperture receives said sample and said second position where said first aperture aligns with said slots.

5,587,789

APPARATUS AND METHOD FOR CONTROLLING
RECORDING AND REPRODUCTION IN DIGITAL VIDEO
CASSETTE TAPE RECORDER

Je H. Lee; Soo K. Kim; Sang J. Woo, and Tae S. Yang, all of Seoul, Rep. of Korea, assignors to Goldstar Co. Ltd., Seoul, Rep. of Korea

Filed Apr. 13, 1994, Ser. No. 227,281


Claims priority, application Rep. of Korea, Apr. 16, 1993, 6441/1993

Int. Cl. H04N 5/76; 5/92

U.S. Cl. 386—68

22 Claims

11. An apparatus for controlling recording in a video cassette tape recorder comprising:
- frame extracting means for receiving compressed digital data input thereto and extracting specific data for a speed-varied reproduction from said compressed digital data;
 - frame recording position controlling means for generating a multiplexing timing signal and multiplexing said compressed digital data and said extracted specific data from said frame extracting means based on said multiplexing timing signal;



- frame position information recording means for recording index information and position information of specific tracks for recording said specific data for the speed-varied reproduction on a magnetic tape based on said multiplexing timing signal; and
- digital recording means for recording digital signals including said digital data and specific data from said frame recording position controlling means on the magnetic tape.

5,587,790

LIGHT SCATTERING TYPE SMOKE DETECTOR
HAVING AN IMPROVED ZERO-POINT LEVEL

Tetsuya Nagashima, Tokyo, Japan, assignor to Hochiki Corporation, Tokyo, Japan


Filed Sep. 2, 1994, Ser. No. 300,193

Claims priority, application Japan, Sep. 7, 1993, 5-221548; Sep. 7, 1993, 5-221549; Sep. 7, 1993, 5-221550; Sep. 7, 1993, 5-221551

Int. Cl. G01N 21/00; 21/49; G08B 17/10

U.S. Cl. 356—338

28 Claims



1. A light scattering type smoke sensor comprising:
- a plurality of labyrinth members for facilitating an inflow of smoke entering from outside, and for cutting off light entering from the outside;
 - a smoke detecting chamber which is formed in a center portion by said labyrinth members;
 - light emitting means for radiating light toward said smoke detecting chamber; and
 - light receiving means for detecting light scattered by said smoke in said smoke detecting chamber, said light receiving means having an optical axis which intersects in said smoke detecting chamber an optical axis of said light emitting means at a scattering angle in a range of substantially 60° to 80°.
- wherein one of said labyrinth members intersects said optical axis of said light emitting means, which has a reflecting face for reflecting light radiated from said light emitting means, said reflecting face reflecting said light in a direction opposite to said light receiving means.

- wherein any points of an extension face of said labyrinth member which intersects said optical axis of said light emitting means are nearer to a center of said smoke detecting chamber than those of a light receiving window of said light receiving means, and
- wherein said light receiving means includes said light receiving window, a light receiving device, and a holder which defines a position of said light receiving window and secures said light receiving device.

5,587,791

OPTICAL INTERFEROMETRIC CURRENT SENSOR AND
METHOD USING A SINGLE MODE BIREFRINGENT
WAVEGUIDE AND A PSEUDO-DEPOLARIZER FOR
MEASURING ELECTRICAL CURRENT


Claude Belleville, Saint-Jean-Chrysostome; Richard Van Neste; Serge Caron, both of Québec; Alain C. Houle, Lachenaie, and Pierre Thibault, Boucherville, all of Canada, assignors to Citeq, Varennes, Canada

Filed Sep. 27, 1994, Ser. No. 313,690

Int. Cl. G01B 9/02; G02B 6/00

U.S. Cl. 356—345

19 Claims



1. An interferometric current sensor for measuring a first electrical current, said sensor comprising:
- a light source for generating a light beam;
 - a single mode birefringent waveguide having a linear birefringence and a circular birefringence, said circular and linear birefringences having respectively given orders of magnitude, the order of magnitude of said circular birefringence being equal or higher than the order of magnitude of said linear birefringence, said waveguide having a first loop portion for encircling said electrical current;
 - a beamsplitter having a first input port optically coupled to said light source, and second and third input/output ports optically coupled to ends of said waveguide for launching counter-propagating light beams into the respective ends of the waveguide and for receiving said counter-propagating light beams therefrom;
 - pseudo-depolarizer means for reducing sensitivity to at least one of mechanical vibrations and temperature variations, said pseudo-depolarizer means being optically coupled in series with said waveguide for converting each of said counter-propagating light beams into a predetermined ratio of useful counter-propagating light signals and useless counter-propagating light signals; and
 - an optical detector optically coupled to the ends of said waveguide via said beamsplitter for detecting a light intensity, said light intensity resulting from an interference of useful counter-propagating light signals and useless counter-propagating light signals, whereby said light intensity is representative of said current.

5,587,792


APPARATUS AND METHOD FOR MEASURING THICKNESS OF THIN SEMICONDUCTOR MULTI-LAYER FILM

Seiji Nishizawa, 1919-8, Hane, Hamura-shi, Tokyo; Tokuji Takahashi, 1 Ban 5-1206, Toyosato 2-chome, Higashiyodogawa-ku Osaka-shi, Osaka, and Ryo Hattori, c/o Mitsubishi Denki Kabushiki Kaisha, Hikari Micro-ha Device Kenkyusho, 1 Mizuhara 4-chome, Itami-shi, Hyogo 664, all of Japan

Division of Ser. No. 262,840, Jun. 21, 1994. This application Oct. 11, 1995, Ser. No. 541,040

Claims priority, application Japan, Jun. 21, 1993, 5-148839 Int. Cl.⁶ G01B 9/02

U.S. Cl. 355—356



1. An apparatus for measuring thicknesses of layers in a thin semiconductor multi-layer film comprising:

a first memory for storing refractive index distribution and wavenumber dispersion data for respective layers of a multi-layer film;

a spectrometer for continuously measuring spectral distribution of light reflected from an underlying layer of the multi-layer film over a range from visible light to far infrared light;

film interference spectrum operating means for eliminating optical transmission characteristics of the spectrometer from the spectral distribution measured by the spectrometer and producing an interference spectrum including only multi-layer film interference components;

a second memory for storing the interference spectrum including only multi-layer film interference components produced by the film interference spectrum operating means;

Spatialgram calculating means for reverse Fourier transforming a wavenumber range of an interference spectrum excluding the optical transmission characteristics of the spectrometer and calculating a Spatialgram;

a third memory for storing the Spatialgram calculated by the Spatialgram calculating means;

layer thickness approximate value calculating means for reading out side burst peaks of the Spatialgram and the refractive index distribution of respective layers stored in the first memory and calculating approximate respective layer thicknesses;

a fourth memory for storing the approximate respective layer thicknesses calculated by the film thickness approximate value calculating means;

theoretical interference spectrum calculating means for obtaining a theoretical interference spectrum from a characteristic matrix calculation based on the approximate layer thicknesses, the refractive index distribution of respective films, and the wavenumber dispersion data stored in the first memory; and

recalculating means for comparing the measured interference spectrum with the theoretical interference spectrum, changing the layer thicknesses of the respective layers to lessen differences between the measured interference spectrum and the theoretical interference spectrum and recalculating the theoretical interference spectrum to obtain layer thicknesses of high precision.

5,587,793

BIREFRINGENCE DISTRIBUTION MEASURING METHOD

Sadao Nakai, 6-45, Kitakasugaoka 3-chome, Ibaragi-shi, Osaka; Yasukazu Izawa, Sulta; Masanobu Yamanaka, Minoo; Masato Ohmi, Toyonaka; Masanori Akatsuka; Chiyo Yamanaka, both of Osaka, and Yoshiyuki Yonezawa, Kawasaki, all of Japan, assignors to Sadao Nakai; Institute for Laser Technology, both of Osaka, and Fuji Electric Co., Ltd., Kanagawa, all of Japan

Continuation of Ser. No. 149,811, Nov. 10, 1993, abandoned.


This application Jun. 6, 1995, Ser. No. 470,157

Claims priority, application Japan, Nov. 12, 1992, 4-301443 Int. Cl.⁶ G01N 21/23

U.S. Cl. 356—367

6 Claims

3 Claims



1. A birefringence distribution measuring method of two-dimensionally measuring a birefringence distribution induced in a sample, comprising the steps of:

placing said sample between a circular polarizer and an analyzer in an optical path between a monochromatic light source and a two-dimensional optical receiver;

converting a plurality of parallel beams emitted from said monochromatic light source into circularly polarized light by said circular polarizer;

transmitting said circularly polarized light through said sample to said analyzer;

detecting image data by said two-dimensional optical receiver while rotating said analyzer about an axis of the plurality of beams, at a step of a fixed rotation angle;

sampling said detected image data and sending the sampled data to an image processing device; and

processing the sampled image data to obtain a relative phase difference due to birefringence of said sample, a two-dimensional birefringence distribution including the sign of said relative phase difference, and the direction of the principal axis.

5,587,794

SURFACE POSITION DETECTION APPARATUS

Hideo Mizutani; Naoyuki Kobayashi, both of Yokohama, and Nobutaka Magome, Kawasaki, all of Japan, assignors to Nikon Corporation, Tokyo, Japan


Continuation of Ser. No. 802,197, Dec. 4, 1991, abandoned.

This application May 9, 1994, Ser. No. 239,847

Claims priority, application Japan, Dec. 13, 1990, 2-401880 Int. Cl.⁶ G01B 11/00

U.S. Cl. 356—375

36 Claims



1. A surface position detection apparatus comprising:

5,587,796

PHOTOELECTRIC MEASURING HEAD FOR THE CONTACTLESS SCANNING OF MEASURING FIELDS ON A PRINTING SHEET WITH AN AIR PERMEABLE ANNULAR DISK

Peter Rakitsch, Moosburg, and Hans Zehentbauer, Germering, both of Germany, assignors to MAN Roland Druckmaschinen AG, Germany


Filed Dec. 22, 1994, Ser. No. 361,597

Claims priority, application Germany, Dec. 22, 1993, 43 43 810.5

Int. Cl.⁶ G01N 21/55; G01J 3/46

U.S. Cl. 356—445

7 Claims



1. A photoelectric measuring head comprising:

an optical device for scanning measurement fields on a printing sheet, the optical device including a light generating means for directing light to the printing sheet and a photoelectric receiver for capturing light reflected from the printing sheet;

a cover including an orifice in which the optical device is disposed and a measuring diaphragm through which light from the light generating means and light reflected from the printing sheet travels;

at least one annular chamber extending in the cover concentrically relative to a central axis of the photoelectric measuring head such that the annular chamber does not block the measuring diaphragm, and wherein the at least one annular chamber holds and distributes compressed air; and

an air permeable annular disc mounted to the cover below the at least one annular chamber and wherein the at least one annular chamber provides the compressed air therein through the air permeable annular disc providing an evenly distributed air flow at a predetermined flow rate that generates an air cushion between an underside of the cover and the printing sheet, the air permeable annular disc extends from the cover concentrically relative to a central axis of the photoelectric measuring head such that the air permeable annular disc does not block the measuring diaphragm.

5,587,797

PROCESS FOR ENCODING AND TRANSMITTING INFORMATION


Josef Dirr, Neufahrner Str. 5, D81679 Munich, Germany
PCT No. PCT/EP93/03088, § 371 Date Jun. 24, 1994, § 102(e)
Date Jun. 24, 1994, PCT Pub. No. WO94/00973, PCT Pub. Date Jan. 20, 1994

PCT Filed Nov. 5, 1993, Ser. No. 50,402

Claims priority, application Germany, Nov. 6, 1992, 42 37 547.9; Dec. 23, 1992, 42 43 899.3; Aug. 11, 1993, 43 26 997.4 Int. Cl.⁶ H04N 1/419; G08C 19/12

U.S. Cl. 358—261.1

11 Claims



1. Method for coding and transmitting information comprising:

a projection optical system for projecting pattern light of a predetermined pattern onto a detection surface from an oblique direction relative to the detection surface;

an imaging optical system for forming an image of the pattern light reflected by the detection surface;

light-receiving-side light-shielding means arranged at a position substantially conjugate with the detection surface in said imaging optical system, and having an opening with a predetermined shape;

scanning means for scanning the image formed by said imaging optical system relative to said light-receiving-side light-shielding means;

means for designating a plurality of different parts of the pattern, in accordance with structure within an area on the detection surface that is disposed in a projection area of said projection optical system; and

means for dividing the pattern light into a plurality of portions corresponding to the different parts of the pattern, and for selectively detecting the portion or portions of the pattern light corresponding to the designated part or parts of the pattern and passing through said opening from said scanning means.

5,587,795


SELF ALIGNING SUBSTRATE TRANSMITTANCE METER

Robert D. Williams, 5374 S. Datura St., Littleton, Colo. 80120
Filed Jul. 13, 1995, Ser. No. 502,255

Int. Cl.⁶ G01N 21/00

U.S. Cl. 356—432

19 Claims



9. A self-aligning window transmittance meter for measuring a light transmittance of a fixed window, comprising:

a remote transmitter having a first housing for holding a first magnet in a predetermined alignment with a light transmitter; and

a remote receiver having a second housing for holding a second magnet in a predetermined alignment with a light receiver, said remote receiver capable to output a transmittance signal, wherein said remote transmitter is placed against a surface of said fixed window such that said remote receiver is brought proximate to an opposing surface of said fixed window and within a magnetic flux of said first magnet such that said first and second magnets are releasably held against said surface and opposing surface, respectively, so as to cause said remote transmitter and remote receiver to self align for measuring a light transmittance through said fixed window by said light transmitter and received by said light receiver for providing a light transmittance measurement of said fixed window.

generating a multilevel phase coding by providing an alternating current of constant frequency and constant phase and providing pulses of predetermined length as code elements, represented by half-periods or periods of said alternating current of said frequency, which pulses are transmitted in an uninterrupted series, a change of phase of said pulses being obtained by increasing or decreasing the numbers of half-periods or periods in relation to the number of half-periods or periods of the preceding pulse, or providing the difference phase as code element, for which the preceding code element is used as a reference, wherein also a leading or lagging phase in relation to the reference phase or in relation to the preceding impulse phase is used as level criterion and a change of phase level which cannot be distinguished is marked by a change of the amplitude of said alternating current.

5,587,798

ENCODING AND DECODING METHODS FOR USE IN FACSIMILE

Kazuo Kurita, Nagano; Mikio Mizutani, Tokyo; Nobuhiko Noma, Yokohama; Tsukasa Sakai, Tokyo; Osamu Noguchi, Tokyo; Hiroyuki Nemoto, Tokyo, and Keiichi Tomita, Tokyo, all of Japan, assignors to Matsushita Graphic Communication Systems, Inc., Tokyo, Japan

Continuation of Ser. No. 923,772, Aug. 3, 1992, abandoned.


This application Nov. 13, 1995, Ser. No. 556,571

Claims priority, application Japan, Aug. 1, 1991, 3-192010

Int. Cl.⁶ H04N 1/32

U.S. Cl. 358—261.1

6 Claims



1. A computer implemented method of encoding and decoding image data used in facsimile for converting raw data representing an image to Modified Huffman code data representing the image, comprising the steps of:

- (1) performing by the computer a first program sequence from a memory for converting the raw data to cumulative run-length coded data including a plurality of run data representing runs of pixels in the image, and for including in the run data for a run:
 - (a) first data representing whether all pixels in the run are white or black; and
 - (b) second data representing where the run lies in the image; and
- (2) performing by the computer a second program sequence from the memory for converting the cumulative run-length code data into Modified Huffman code data representing the image.

5,587,799
COPYING MACHINE WITH RESERVED COPYING AT A
PREDETERMINED TIME PERIOD

Motomi Kawamura, Aichi-ken; Masamichi Kishi, and Takeshi Morikawa, both of Toyokawa, all of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Jul. 30, 1993, Ser. No. 99,937

Claims priority, application Japan, Aug. 1, 1992, 4-225089

Int. Cl.⁶ H04N 1/00; G03G 21/00

U.S. Cl. 358—296

27 Claims



1. A copying machine for forming an image of an original document on a sheet, comprising:
 - image reading means for reading an image of an original document and for generating image data corresponding to the image of said original document, said image reading means being operable under a normal mode and under a reserve mode;
 - memory means for storing said image data read by said image reading means;
 - image forming means for forming an image on a sheet based on said data stored in said memory means;
 - clocking means for clocking time;
 - judging means for judging whether or not the time being clocked by said clocking means reaches a predetermined time; and
 - controlling means for controlling said image forming means to start the image formation on a sheet based on said image data, which is read by said image reading means under said reserve mode, stored in said memory means when the time clocked by said clocking means reaches the predetermined time.

5,587,800

IMAGE PROCESSING METHOD AND APPARATUS
Yuki Miyazaki, Kawasaki, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation-in-part of Ser. No. 7,103, Jan. 21, 1993, abandoned. This application Mar. 15, 1995, Ser. No. 405,377

Claims priority, application Japan, Jan. 29, 1992, 4-013631; Jan. 13, 1993, 5-003918

Int. Cl.⁶ H04N 1/21

U.S. Cl. 358—296

33 Claims

1. An image processing method of forming a new image by overlaying an image based on inputted data on a standardized form image which has been pre-registered, comprising:
 - an input step of inputting data corresponding to the image overlaid on the form;
 - a first discrimination step of discriminating whether or not pattern data corresponding to the data inputted in said input step is stored in a first area of a storage medium;

5,587,802

EXTENDED DEFINITION VIDEO SIGNAL CONVERTER
FOR USE WITH A VIDEO RECORDER

Franciscus H. M. Bergen; Jan J. Rotte; Stephanus J. J. Nijssen, and Peter H. N. De With, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Division of Ser. No. 869,290, Apr. 15, 1992, Pat. No. 5,293,248.



This application Sep. 13, 1993, Ser. No. 120,987

Claims priority, application European Pat. Off., May 6, 1991, 91201070; Feb. 27, 1992, 92200566

Int. Cl.⁶ H04N 9/79

U.S. Cl. 386—26

20 Claims



- a first mapping step of mapping the input data in the first area using an outline font based on the discrimination result in said first discrimination step;
- a second discrimination step of discriminating whether or not the pattern data included in the form is stored in a second area of the storage medium;
- a second mapping step of mapping the form in the second area using an outline font based on the discrimination result in said second discrimination step;
- a third mapping step of bitmapping the patterns mapped in said first and second mapping steps in a bitmap memory; and
- an output step of outputting the bitmapped pattern.

5,587,801

DIGITAL IMAGE FORMING APPARATUS

Nobuo Kamei, Toyokawa; Yoshikazu Ikenoue, Toyohashi, and Hideo Yamamoto, Hiratsuka, all of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 78,464, Jun. 18, 1993, abandoned.


This application Feb. 6, 1996, Ser. No. 595,940

Claims priority, application Japan, Jun. 19, 1992, 4-160793

Int. Cl.⁶ H04N 1/10

U.S. Cl. 358—296

24 Claims



1. A digital image forming apparatus comprising:
 - a read means for reading an image of a document;
 - a document set means for setting a document at a prescribed reading position;
 - memory means for storing data of the image read by said read means;
 - an image forming means for forming the image on a sheet of paper according to the data stored in said memory means;
 - a detection means for detecting whether or not the document is at the prescribed reading position;
 - determining means for determining if the document is removed from the prescribed reading position; and
 - a clear means for automatically clearing the image data stored in said memory means when the determining means determines that the document has been removed from the prescribed reading position after said detection means detects that the document is at the prescribed reading position.

5,587,803

DIGITAL SIGNAL RECORDING AND REPRODUCING
APPARATUS AND ERROR-CORRECTING APPARATUS

Tohru Inoue; Ken Onishi; Sadayuki Inoue, and Ikko Okuma, all of Nagakakyō, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 37,372, Mar. 26, 1993, abandoned.


This application May 2, 1995, Ser. No. 432,703

Claims priority, application Japan, Apr. 1, 1992, 4-079571; Apr. 28, 1992, 4-109804; Mar. 2, 1993, 5-067550

Int. Cl.⁶ H04N 9/79


U.S. Cl. 386—33

18 Claims



1. An error-correcting apparatus for correcting errors caused on a transmission channel and/or a recording medium, comprising:
 - means for grouping compressed data into macroblocks each consisting of a prescribed number of luminance signal blocks and a prescribed number of color-difference signal blocks and for placing the data in fixed positions in an error-correcting code; and
 - means for storing macroblocks of data in areas which correspond to each luminance and color-difference signal, each area having a prescribed number of bits and being filled completely with data of the corresponding one of the luminance signal and color-difference signals unless the data of the corresponding one of the luminance signal and color-difference signals is less than the prescribed number of bits, and for, when the length of at least one of the luminance signals and color-difference signals is smaller than the pre-

scribed number of bits, forming blocks each consisting of the prescribed number of bits by filling a vacant space of an area, corresponding to the one of the luminance signals and color difference signals the length of which is less than the prescribed number of bits, with overflowing components from other luminance and color difference signals and thereafter performing error-correction coding on the data.



5,587,804

REPRODUCTION ERROR CORRECTION CIRCUIT FOR A VIDEO REPRODUCTION SYSTEM & THE METHOD FOR OPERATING IT


Byung-Joon Moon, Kyungki-do; Sung-Il Cho, Incheon, and Ki-ho Shin, Kyungki-do, all of Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea
Filed Jul. 26, 1994, Ser. No. 280,770

Claims priority, application Rep. of Korea, Jul. 28, 1993, 1993-14473

Int. Cl.⁶ H04N 9/89; 5/95; 5/78; 9/88

U.S. Cl. 386—2

10 Claims



1. A reproduction error correction circuit a video reproduction system comprising:

- storage means for storing image data of one horizontal scanning period by receiving an image digitized in response to a write clock signal;
- write address generating means for sequentially generating write addresses for said storage means in response to said write clock signal;
- read address generating means for sequentially generating read addresses for said storage means in response to a read clock signal;
- a chrominance signal phase controlling means for controlling the phase of a chrominance signal by receiving a drop-out detecting signal, said read address signal and said write address signal;
- a chrominance signal phase inverting means for inverting the phase of the chrominance signal by receiving the output signal of said storage means; and
- selecting means for outputting the output signal of said storage means or outputting the output signal of said chrominance signal phase inverting means in response to the output signal of said chrominance signal phase controlling means.

5,587,805

METHOD FOR RECORDING IMAGES IN A DIGITAL VIDEO CASSETTE RECORDER

Ku-man Park, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-do, Rep. of Korea
Filed Nov. 29, 1993, Ser. No. 158,827

Claims priority, application Rep. of Korea, Nov. 28, 1992, 92-22705; Oct. 15, 1993, 93-21451

Int. Cl.⁶ H04N 5/92; 5/782

U.S. Cl. 386—48

12 Claims

4. A method for recording images in a digital video cassette recorder in which a compressed digital video signal of each sub-image of a picture divided into a predetermined number of sub-images is divided into low-frequency data and high-frequency data, so that low-frequency data is recorded in a low-frequency data recording area having a certain distance on each track of a

length of tape and the high-frequency data of a single corresponding sub-image is sequentially recorded on the remaining area of each track, characterized in that the predetermined number of sub-images is divided into a plurality of clusters in accordance with a predetermined method and then the low-frequency data for all sub-images belonging to a specific cluster are recorded together on the low-frequency data recording area of each sub-image belonging to said specific cluster.

5,587,806

APPARATUS FOR SEPARATELY RECORDING INPUT CODED VIDEO SIGNAL AND IMPORTANT DATA GENERATED THEREFROM

Masazumi Yamada, Moriguti; Shinya Kadono, Kobe, and Shiro Kato, Hirakata, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Mar. 21, 1994, Ser. No. 215,421

Claims priority, application Japan, Mar. 26, 1993, 5-068533; Apr. 7, 1993, 5-080492

Int. Cl.⁶ H04N 5/76; 5/78

U.S. Cl. 386—68

28 Claims



1. A video signal recording apparatus for recording on a recording medium an input coded video signal containing intra-picture coded data and inter-picture coded data, comprising:

- important data generating means for generating important data from a part of the input coded video signal that contains intra-picture coded data, said important data generating means outputting the input coded video signal as is as normal data;
- data arranging means for arranging said important data and said normal data in such an order that said important data is recorded in a specific area of the recording medium and said normal data is recorded in the remaining area of the recording medium; and
- data recording means for recording said important data and said normal data into said specific area and the remaining area, respectively, of the recording medium.

5,587,807

APPARATUS FOR PROCESSING DIGITAL VIDEO DATA WITH ERROR CORRECTION PARITY COMPRISING ERROR CONCEALMENT MEANS

Takeshi Ootsuka, Kadoma, and Masaaki Higashida, Moriguchi, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Oct. 4, 1994, Ser. No. 317,793

Claims priority, application Japan, Oct. 5, 1993, 5-249030

Int. Cl.⁶ H04N 5/76

U.S. Cl. 386—46

15 Claims



1. An apparatus for processing input N-bit digital video data with an error correction parity, said input N-bit digital video data including each one sample of higher-order-N-bit data and a plurality of samples of lower-order-(M-N)-bit data, M being a predetermined natural number, N being a predetermined natural number smaller than the natural number M, said apparatus comprising:

- error correction means for correcting an error of said input N-bit digital video data, outputting error-corrected N-bit digital video data, and generating and outputting an error detection signal representing an error which can not be corrected;
- data combining means for converting said error-corrected N-bit digital video data outputted from said error correction means into M-bit digital video data by combining said each one sample of said higher-order-N-bit data and said plurality of samples of said lower-order-(M-N)-bit data included in said error-corrected N-bit digital video data so as to obtain said M-bit digital video data, and outputting converted M-bit digital video data;
- error classifying means for classifying said error detection signal into a first error detection signal representing an error of said each one sample of said higher-order-N-bit data and a second error detection signal representing an error of said plurality of samples of said lower-order-(M-N)-bit data; and
- error concealment means for performing an error concealment process for said converted M-bit digital video data outputted from said data combining means based on said first error detection signal outputted from said error classifying means.

5,587,808

IMAGE PROCESSING APPARATUS FOR IDENTIFYING CHARACTER, PHOTO AND DOT IMAGES IN IMAGE AREA

Hayato Hagihara, and Takahiro Hongu, both of Tokyo, Japan, assignors to NEC Corporation, Tokyo, Japan

Filed May 31, 1995, Ser. No. 455,623

Claims priority, application Japan, May 31, 1994, 6-117768


Int. Cl.⁶ H04N 1/40; 1/38

U.S. Cl. 358—462

4 Claims

1. An image processing device for separating areas in an image in which character, dot and photo images are mixed comprising: first determination means being supplied with picture signals representing an image, which contains a character, dot and photo, with multivalued data on picture element basis, for detecting the maximum and minimum values of the picture elements in a first matrix with a plurality of picture elements, and for determining whether said first matrix is a photo area or a provisional character area on the picture element basis according to result of comparison between said difference and a threshold;

second determination means for determining by using a second matrix with a plurality of picture elements, which partially overlaps said first matrix, whether or not variation of picture elements in said second matrix exceeds a predetermined amount; and,



means for determining said provisional character area as a character area and dot/photo area by a third matrix which is composed by using result of determination by said second determination means.

5,587,809

SYSTEM AND A PROCESS FOR TRANSMISSION OF SECURE FAXES

Hervé Le Corre, Etterville; Jean-Luc Grimault, Mondeville, and François Boudet, Fontenay le Marmion, all of France, assignors to France Telecom Etablissement Autonome de Droit Public, Paris, and La Poste, Boulogne Beillancourt Cedex, both of France


Continuation of Ser. No. 186,970, Jan. 27, 1994, abandoned.

This application Jan. 3, 1996, Ser. No. 582,224

Claims priority, application France, Jan. 28, 1993, 93 00868
Int. Cl.⁶ H04N 1/44

U.S. Cl. 358—405

1 Claim



1. A process for secure transmission of a document with a "registered fax" notice, using a fax server, comprising the following steps:

- a secure sending step (22) for sending the document to be faxed by a sending fax machine (20) to the server (21) wherein the sending fax machine gives the server a name of a recipient;
- a sending step (24) in which the server sends the recipient a "registered fax" notice which has a reference number;
- a recall step (25) following the sending step in which the recipient (23) recalls the server and is authenticated by the server by verifying the identity of the recipient and a digital signature of the recipient, and asks the server to send the document on a specific fax machine, with the document remaining available to the recipient for a predefined time; and


an authentication step for authenticating the recipient by the server, sending (26) said document to the specific fax machine and sending (27) a receipt that the document was sent to the sending fax machine.

5,587,810 COMMUNICATION APPARATUS FOR DISABLING MESSAGES SPECIFYING NON-STANDARD COMMUNICATION FEATURES

Howard R. Feldman, Kenton, England, assignor to International Mobile Satellite Organization, London, England
Filed Mar. 14, 1994, Ser. No. 212,161
Int. Cl.⁶ H04N 1/41; 1/32; 1/40; 1/00

U.S. Cl. 358—442

26 Claims



1. A device for modifying a signal transmitted by a first apparatus for reception by a second apparatus, said first apparatus supporting both a standard communications protocol and a non-standard communications protocol comprising:
means for receiving said signal from the first apparatus;
means for detecting a portion of said signal which identifies said non-standard communications protocol supported by the first apparatus;
means for replacing said portion with a predetermined signal;
and
means for transmitting a modified signal derived from said received signal and including said predetermined signal in a protocol identifying field to the second apparatus, said modified signal identifying only said standard protocol.


5,587,811 HALFTONE SCREEN USING SPOT FUNCTION TO RANK PIXELS FOLLOWING ONE OR MORE DESIGN RULES

Thomas A. Liguori, San Diego, Calif., assignor to Dataproducts Corporation, Simi Valley, Calif.

Filed Apr. 28, 1995, Ser. No. 430,881
Int. Cl.⁶ H04N 1/405; 1/52

U.S. Cl. 358—456

24 Claims



5. A method for halftoning in an area of pixels, the method comprising:

partitioning the pixels into macro halftone cells, each macro halftone cell having a plurality of sub-halftone cells, each sub-halftone cell defining an area of contiguous pixels;

determining a quantity of pixels within a macro halftone cell to be darkened based on a predetermined level of grayness for the macro halftone cell; and
ranking the pixels within the macro halftone cell from highest to lowest in accordance with a spot function such that:
no two pixels within the same sub-halftone cell are ranked consecutively; and
the number of pixels ranked above any particular pixel within the sub-halftone cell is no more than one greater and no more than one less than the number of pixels ranked above said particular pixel in any other sub-halftone cell within the macro halftone cell.

5,587,812 FACSIMILE APPARATUS WITH COMMON SHEET CONVEYING PATH

Michio Kasuya, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Dec. 6, 1994, Ser. No. 354,023

Claims priority, application Japan, Dec. 13, 1993, 5-312016; Oct. 20, 1994, 6-255245

Int. Cl.⁶ H04N 1/00

U.S. Cl. 358—498

11 Claims



1. A facsimile apparatus which has an original sheet conveying path for conveying an original and a recording sheet conveying path for conveying a recording sheet, comprising:
a common sheet conveying path for conveying either the original or the recording sheet, and which is provided downstream of the original sheet conveying path and the recording sheet conveying path;
feeder selection means, which is provided upstream of said common sheet conveying path, for picking-up either the original or the recording sheet by selection;
reading means, provided on said common sheet conveying path, for reading the original fed to said common sheet conveying path by said feeder selection means;
recording means, provided on said common sheet conveying path, for recording on the recording sheet fed to said common sheet conveying path by said feed selection means; and
ejecting means for ejecting the original and the recording sheet to the outside,
wherein said feeder selection means is always at a position where said means can select the original sheet, and has control means for changing the position upon conveying the recording sheet,
and wherein said control means does not change the position of said feeder selection means until conveyance of the original or recording sheet has been completed.

5,587,813 DATA TRANSFER DEVICE FOR AN IMAGE FORMING APPARATUS

Shuichi Yamazaki, Fujimi; Takashi Mama; Nobuyuki Sato, both of Yokohama; Takeshi Yamakawa, Fujisawa; Shinji Kobayashi; Yoshio Kaneko, both of Tokyo, and Koji Oshikiri, Natori, all of Japan, assignors to Ricoh Company, Ltd., Tokyo, Japan


Filed Jul. 29, 1993, Ser. No. 98,940

Claims priority, application Japan, Jul. 31, 1992, 4-205706
Int. Cl.⁶ H04N 1/00; 1/46; 7/12; G03F 3/08

U.S. Cl. 358—500

16 Claims

1. A data transfer device for an image forming apparatus, comprising:



a sending unit for outputting at different times at least first multilevel data of a first color and second multilevel data of a second color;
a plurality of data lines for communicating the first multilevel data and the second multilevel data output by the sending unit at different times;
a control unit for controlling whether the first multilevel data or whether the second multilevel data is communicated on the plurality of data lines; and
a receiving unit for receiving and separating the first multilevel data and the second multilevel data communicated on the plurality of data lines, wherein the receiving unit records on an image receiving material an image of the first color and an image of the second color and the image of the second color are superposed on each other.

5,587,814 COLOR IMAGE SENSOR INCLUDING PLURAL LIGHT- RECEIVING WINDOWS AND COLOR FILTERS

Akio Mihara, Isehara, and Seiji Hashimoto, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Division of Ser. No. 680,692, Apr. 4, 1991, Pat. No. 5,315,412.



This application Jan. 12, 1994, Ser. No. 180,317

Claims priority, application Japan, Apr. 6, 1990, 2-90447; Apr. 9, 1990, 2-92050; Apr. 9, 1990, 2-92051; Apr. 9, 1990, 2-92052

Int. Cl.⁶ H04N 1/46

U.S. Cl. 358—512

6 Claims



1. A multi-chip color image sensor in which a plurality of semiconductor image sensors each having a plurality of light-receiving windows are arrayed, and a plurality of light-receiving windows in a main scanning direction constitute one color light-receiving element,

wherein a last light-receiving window or at least two light-receiving windows including the last light-receiving window of a first semiconductor image sensor of adjacent semiconductor image sensors, and a first light-receiving window or at least two light-receiving windows including the first light-receiving window of the next semiconductor image sensor constitute one color light-receiving element.

5,587,815 PHASE MODULATION HOLOGRAPHIC DEVICE FOR GENERATING TWO DIFFERENT WAVEFRONTS


Akira Sato, Amagasaki, and Takuji Hatano, Sakai, both of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Filed Sep. 15, 1993, Ser. No. 122,372

Claims priority, application Japan, Sep. 17, 1992, 4-247424
Int. Cl.⁶ G03H 1/12

U.S. Cl. 359—11

13 Claims



1. A phase modulating device, comprising:
a substrate having a binarized surface configuration defined by the following equations:

$$B(r) = \pi(PTH(r) \leq P(r) < 2\pi) \text{ or}$$

$$B(r) = (0 \leq P(r) < PTH(r))$$

$$PTH(r) = 2 \sin^{-1} \eta(r)^{-1/2}$$

wherein $P(r)$ is the phase difference distribution and $B(r)$ is the binarized surface configuration at coordinate r along a diameter of the substrate, $\eta(r)$ is a diffraction efficiency distribution, and $PTH(r)$ is a threshold value for binarization.

5,587,816 LCD DEVICE INCLUDING AN ILLUMINATION DEVICE HAVING A POLARIZED LIGHT SEPARATING SHEET BETWEEN A LIGHT GUIDE AND THE DISPLAY

Tomoki Gunjima; Yoshiharu Ooi; Masao Ozeki, all of Yokohama; Hiroaki Ito, Kawasaki; Hiroshi Hasebe, Tokyo; Tetsuro Matsumoto, and Yutaka Nakagawa, both of Yokohama, all of Japan, assignors to Asahi Glass Company Ltd., Tokyo, Japan

Continuation of Ser. No. 132,864, Oct. 7, 1993, abandoned.


This application Oct. 19, 1995, Ser. No. 530,012

Claims priority, application Japan, Oct. 9, 1992, 4-298021; Feb. 17, 1993, 5-051594; May 28, 1993, 5-151260; Jun. 2, 1993, 5-156142

Int. Cl.⁶ G02F 1/1335

U.S. Cl. 349—62

18 Claims



1. An illumination device for a direct viewing type display element, comprising:
a flat light guide;

- a light source set such that light is incident on a side portion of said flat light guide;
- a polarized light separating sheet set on a light emitting side of the flat light guide for transmitting a p polarized light component and reflecting at least a portion of an s polarized light component with respect to a light ray substantially having a predetermined direction of incidence; and
- a light reflecting sheet disposed on another side opposite to and facing said light emitting side of the flat light guide in parallel with the emitting side, said light reflecting sheet converting said portion of s polarized light component reflected by said polarized light separating sheet into p polarized light and reflecting the converted p polarized light to said polarized light separating sheet for transmission of the converted p polarized light through said polarized light separating sheet in overlapping relationship with the p polarized light component.

5,587,817

LIQUID CRYSTAL PANEL UNIT HAVING LIQUID CRYSTAL PANEL AFFIXED TO PANEL FIXING USING ADHESIVE AND HEIGHT-REGULATING PINS

Takao Miyamoto, Chigasaki, and Hisao Tajima, Yokohama, Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 63,541, May 19, 1993, Pat. No. 5,329,391.


This application Apr. 15, 1994, Ser. No. 228,274

Claims priority, application Japan, May 20, 1992, 4-151256

Int. Cl.⁶ G02F 1/13; 1/1333

U.S. Cl. 349—187

4 Claims



1. A liquid crystal panel unit, comprising:
- a panel-fixing plate;
- a liquid crystal panel fixed onto the panel fixing plate with plural adhesive pieces; and
- observable traces of a plurality of removed height-regulating pins disposed in the neighborhood of the adhesive pieces on a face of the panel-fixing plate opposing the liquid crystal panel.

5,587,818

THREE COLOR LCD WITH A BLACK MATRIX AND RED AND/OR BLUE FILTERS ON ONE SUBSTRATE AND WITH GREEN FILTERS AND RED AND/OR BLUE FILTERS ON THE OPPOSITE SUBSTRATE

Si-Hyun Lee, Suwon, Rep. of Korea, assignor to Samsung Display Devices Co., Ltd., Kyungki-do, Rep. of Korea

Filed Dec. 8, 1995, Ser. No. 569,697


Claims priority, application Rep. of Korea, Dec. 26, 1994, 94-36911

Int. Cl.⁶ G02F 1/1335; 1/1333

U.S. Cl. 349—106

2 Claims

1. A liquid crystal display comprising a black matrix and a plurality of color (red, green and blue) filters formed on a pair of



opposite glass substrates, wherein filters of one or two colors other than green, are formed on one glass substrate with said black matrix, while filters of two or one color, respectively, including said green filter, are formed on the other glass substrate such that the edge of the color filters of the one glass substrate are aligned with the edge of the color filters of the other glass substrate.

5,587,819

DISPLAY DEVICE

Kazuyuki Sunohara; Rei Hasegawa; Hiroyuki Nagata; Shinichi Sanada, and Yasushi Kawata, all of Yokohama, Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Filed Dec. 27, 1994, Ser. No. 364,750


Claims priority, application Japan, Dec. 27, 1993, 5-348499;

Jun. 20, 1994, 6-137390

Int. Cl.⁶ G02F 1/1335; 1/1333

U.S. Cl. 349—106

19 Claims



19. A reflective direct-view type display device which comprises:

- a first substrate having two major surfaces and electrode provided on a first major surface;
- a second substrate having two major surfaces and color filter layers and pixel electrodes provided on a first major surface wherein said color filter layers comprise at least a black filter layer; and
- a light-scattering medium interposed between said first and second substrates positioned with said electrode that opposes said pixel electrodes, and a yellow dye is disposed in that part of said light-scattering medium which opposes any part of the black filter layer.

5,587,820

INTEGRATED ELECTRO-OPTICAL LIQUID CRYSTAL DEVICE AND METHOD OF USING SUCH A DEVICE

Paul May, Cambridge; Craig Tombling, Oxfordshire; Michael G. Robinson, Oxfordshire; Edward P. Raynes, Oxfordshire, and Jonathan Harrold, Oxfordshire, all of United Kingdom, assignors to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Sep. 22, 1994, Ser. No. 310,671

Claims priority, application United Kingdom, Sep. 23, 1993, 9319614; Jun. 7, 1994, 9411330

Int. Cl.⁶ G02F 1/1343; 1/135; 1/137; H01J 40/14

U.S. Cl. 359—72

38 Claims



1. An integrated electro-optical device comprising a liquid crystal optical modulation layer, an opto-electronic detector layer, and means for absorbing polarized light superimposed over the detector layer, the absorbing means forming an integral polarization analyzer and the detector layer being arranged to detect a result of optical processing by the optical modulation layer via the absorbing means.

5,587,821

LIQUID CRYSTAL DISPLAY DEVICE HAVING A PARTICULAR COMPENSATOR

Hiroko Nakanishi, Uji, and Hiroshi Ohnishi, Nara, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Dec. 23, 1994, Ser. No. 363,377

Claims priority, application Japan, Dec. 27, 1993, 5-332681

Int. Cl.⁶ G02F 1/1335; C09K 19/02

U.S. Cl. 349—118

4 Claims



1. A liquid crystal display device comprising:
- a) a pair of polarizing plates;
- b) a liquid crystal display element disposed between the pair of polarizing plates, the element including:
- a pair of substrate members at least one of which is transparent, and a
- a super twisted nematic-type liquid crystal layer of the liquid crystal molecules having a twist angle ϕ of 240° , the liquid crystal layer sandwiched between the substrate members, the pair of substrate member each including both an electrode for applying a voltage to the liquid crystal layer and an orientation film in contact with the liquid crystal layer; and

- c) phase difference plates placed between each of the pair of polarizing plates and the liquid crystal display element, wherein
- the liquid crystal layer interposed between the electrodes is used as picture elements;
- the liquid crystal molecules with different pretilt angles are mixed in a single picture element;
- the phase difference plates are selected so that $n_x \geq n_z > n_y$ is satisfied and the value of N_z represented by $N_z = (n_x - n_z) / (n_x - n_y)$, where the N_z value is 0.2 and where n_x , n_y and n_z are the refractive indices in the three-dimensional directions of each phase difference plate;
- the angle γ contained by an orientation axis of liquid crystal molecules closest to the orientation film possessed by a one of the pair of substrate members and an absorption axis of the polarizing plate on the side of the one substrate member is selected to be in the range of 40° to 50° ;
- the angle δ contained by said orientation axis and the slow axis of the phase difference plate on the side of the one substrate member is selected to be in the range of 70° to 80° ;
- the angle ϵ contained by an orientation axis of liquid crystal molecules closest to the orientation film possessed by an other of the pair of substrate members and the slow axis of the phase difference plate on the side of the other substrate member is selected to be in the range of 100° to 110° ; and
- the angle ζ contained by the orientation axis of liquid crystal molecules closest to the orientation film possessed by the other of the pair of substrate members and an absorption axis of the polarizing plate on the side of the other substrate member is selected to be in the range of 40° to 50° .

5,587,822

LIQUID CRYSTAL ORIENTATION CONTROL LAYER METHOD AND APPARATUS FOR MANUFACTURING THE SAME AND MASK FOR USE IN THE MANUFACTURING

Jae-won Lee, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Filed Jan. 30, 1995, Ser. No. 380,862

Claims priority, application Rep. of Korea, Jan. 28, 1994, 94-1586

Int. Cl.⁶ G02F 1/1337

U.S. Cl. 349—124

4 Claims



1. A method for forming an orientation layer, comprising the steps of:
- coating an orientation material in a predetermined thickness on a transparent substrate; and
- forming a striped orientation layer such that a plurality of striped layers are simultaneously formed in parallel at a predetermined distance by evaporating exposed portions of said orientation layer by focusing striped light from a mask having a hemispherical microlens array onto said orientation layer.

5,587,823

RADIO COMMUNICATION DEVICES


Hiroyuki Yoshino, Higashiyama, and Takashi Kojo, Ome, both of Japan, assignors to Casio Computer Co., Ltd., Tokyo, Japan

Filed Dec. 20, 1993, Ser. No. 170,502

Claims priority, application Japan, Dec. 28, 1992, 4-349579

Int. Cl.⁶ H04B 10/10

U.S. Cl. 359—143



1. A radio communication device for exchanging data with another radio communication device, comprising:
 image pattern data storage means for storing a plurality of image pattern data for each of parts of a face, the plurality of image pattern data corresponding respectively to a plurality of code data;
 image pattern data selecting means for designating code data to select image pattern data from among the image pattern data stored in said image pattern data storage means, and for combining the selected image pattern data to obtain image data of a face;
 image data storing means for storing image data of a face obtained by said image pattern data selecting means;
 conversation sentence data storage means for storing a plurality of conversation sentence data, which correspond respectively to a plurality of code data;
 conversation sentence selecting means for selecting one conversation sentence data from among the plurality of conversation sentence data stored in said conversation sentence data storage means;
 sending means for sending to the another radio communication device by means of radio signals, code data of image pattern data included in the image data obtained by said image pattern data selecting means and code data of the conversation sentence data selected by said conversation sentence selecting means;
 receiving means for receiving a radio signal of code data of image data and a radio signal of conversation sentence data, both sent from the another radio communication device;
 reading means for reading out from said image pattern data storage means image pattern data corresponding to code data of the image data which are included in the radio signal received by said receiving means, and for reading out from said conversation sentence data storage means conversation sentence data corresponding to code data of the conversation sentence data received by said receiving means;
 display means for displaying the image pattern data and the conversation sentence data, both read out by said reading means; and
 display control means for controlling said reading means to read out from said image pattern data storage means image pattern data different from the image pattern data previously read out by said reading means, when the conversation sentence data read out by said reading means is a previously determined conversation sentence data, and for controlling said display means to display the image pattern data last read out by said reading means.

5,587,824

OPEN COLLECTOR COMMUNICATIONS LINK

Robert R. Asprey, Harvest, Ala., assignor to Cybex Computer Products Corporation, Huntsville, Ala.
 Continuation-in-part of Ser. No. 736,568, Jul. 26, 1991, Pat. No. 5,323,420, which is a continuation-in-part of Ser. No. 55,829, Apr. 30, 1993, abandoned. This application Sep. 1, 1995, Ser. No. 524,189

Int. Cl.⁶ H04B 1/52

U.S. Cl. 359—154

5 Claims



1. A binary logic communications link comprising:
 a first bidirectional, binary logic communications port and a remotely located second bidirectional, binary logic communications port;
 a first conductor having a first end and a second end;
 a second conductor having a first end and a second end;
 first comparator means responsive to said first port for providing a first digital transition to said first end of said first conductor responsive to a first digital potential transition from said first port crossing a selected potential;
 second comparator means responsive to said second port for providing a second digital transition to said first end of said second conductor responsive to a digital potential transition from said second port crossing a selected potential;
 first voltage control means for providing a first logic level voltage;
 second voltage control means for providing a first logic level voltage;
 said second voltage control means being coupled to said second end of said first conductor and coupled to said second port and responsive to a said first digital transition from said first conductor and said first comparator means for asserting a said first logic level voltage at said second port, thereby communicating a said first digital transition from said first port to said second port;
 said first voltage control means being coupled to said second end of said second conductor and coupled to said first port and being responsive to a said second digital transition from said second conductor and said second comparator means for asserting a said first logic level voltage at said first port, thereby communicating a second digital transition from said second port to said first port;
 said second voltage control means includes means further responsive to said second end of said first conductor for effecting clamping of an output of said second comparator means to a second logic level state until said digital potential transitions asserted by said first port reverts to a quiescent logic level; and
 said first voltage control means is further responsive to said second end of said second conductor for effecting a clamping of an output of said first comparator means to a second logic level state until said first digital potential transition asserted by said first port reverts to a quiescent logic level.

5,587,825

SCANNING OPTICAL SYSTEM

Takashi Iizuka, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan
 Filed Jun. 25, 1992, Ser. No. 904,320

Claims priority, application Japan, Jun. 26, 1991, 3-252687;


Apr. 21, 1992, 4-101383

Int. Cl.⁶ G02B 26/08; H01J 3/14; 5/16; 40/14

U.S. Cl. 359—204

16 Claims

1. A scanning optical system comprising:
 a writing beam source for generating a writing beam;
 a monitoring beam source for generating a monitoring beam of a different wavelength than said writing beam;



combining means for combining said writing beam and said monitoring beam;
 a deflector for deflecting and scanning the rays of light from each of said sources;
 a scanning lens with which the rays of light deflected by said deflector are focused on an image plane;
 an isolating means provided between said deflector and said image plane to isolate the monitoring beam from the optical path of the writing beam;
 a signal generating means that receives the isolated monitoring beam to generate a monitor signal; and
 a photoreceptor disposed at said image plane, wherein said monitoring beam has a wavelength which said photoreceptor is incapable of sensing.

5,587,826

OPTICAL BEAM SCANNING APPARATUS ADJUSTING FOCAL POINT OVER ENTIRE IMAGE FORMING AREA BY FEEDBACK CONTROL

Takashi Shibaguchi, Yokohama, Japan, assignor to Ricoh Company, Ltd., Tokyo, Japan

Division of Ser. No. 420,507, Apr. 12, 1995, Pat. No. 5,541,761.


This application Feb. 27, 1996, Ser. No. 607,456

Claims priority, application Japan, Apr. 14, 1994, 6-075813; Jun. 28, 1994, 6-146086

Int. Cl.⁶ G02B 26/10

U.S. Cl. 359—216

7 Claims



1. An optical beam scanning apparatus comprising:
 a light source emitting a linearly polarized light beam;
 deflecting means for deflecting the light beam toward a scanning surface on which an image is formed a scanning operation defined by the light beam projected from said deflecting means onto said scanning surface;
 a first image forming optical system provided between said light source and said deflecting means focusing the light beam on said scanning surface, said first image forming optical system including an electrooptic lens having a variable focal distance so that a focal distance of said first image forming optical system is varied in synchronization with said scanning operation;
 light beam splitting means for splitting the light beam after the light beam has passed through said electrooptic lens into a

first split light beam and a second split light beam, said first split light beam being directed toward said deflecting means; focal position detecting means for detecting a deviation of a focal position of said first split light beam relative to said scanning surface by use of said second split light beam, and for outputting a detection signal corresponding to the deviation of the focal position;
 focusing signal supplying means for storing and supplying a focusing signal which corresponds to the detection signal obtained when a focal position of said first split light beam is positioned on said scanning surface;
 direct current reference signal generating means for generating and outputting a direct current reference signal having a predetermined constant level;
 differential signal generating means for generating a differential signal between the direct current reference signal output from said direct current reference signal generating means and the detection signal output from said focal position detecting means;
 driving voltage generating means for generating a driving voltage supplied to said electrooptic lens, the driving voltage being controlled by a driving voltage controlling signal which is a sum of the differential signal output from said differential signal generating means and the focusing signal output from said focusing signal supplying means; and
 synchronization signal generating means, provided adjacent to said scanning surface, for generating a synchronization signal by detecting the light beam projected from said deflecting means onto said scanning surface, the synchronization signal used for controlling starting timing for a scanning operation and an output timing for outputting the detection signal from said focal position detecting means so that the differential signal is output for each scanning period in the absence of an image being formed on said scanning surface.

5,587,827

APPARATUS FOR COMPENSATING CHROMATIC AND POLARIZATION DISPERSION AND FREQUENCY CHIRP IN FIBER OPTICS AND FOR PULSE COMPRESSION IN LASER SYSTEMS


Hosain Hakimi, and Farhad Hakimi, both of 131 Coolidge Ave., #627, Watertown, Mass. 02172

Filed Feb. 1, 1995, Ser. No. 381,741

Int. Cl.⁶ G02F 1/03

U.S. Cl. 359—249

9 Claims



1. Apparatus for compensating a predetermined amount of chromatic dispersion and polarization dispersion and frequency chirp in a lightwave signal, the apparatus comprising:
 first means for transforming each wavelength component of the lightwave to different respective polarization states; and
 second means to convert each different respective polarization state to a different respective time delay and wherein said second means to convert is connected to an output of the first transforming means for compensating chromatic dispersion and frequency chirp of the lightwave by inducing an amount of chromatic dispersion substantially equal in magnitude, and

opposite in sign, to the predetermined amount of chromatic dispersion and polarization dispersion and frequency chirp.

wherein said filter comprises means for repeating said filtered signal.


5,587,828

ADJUSTABLE WINDOW TINTING SYSTEM

Leroy A. Bernard, Jr., 2277 Evalon, Beaumont, Tex. 77703
Division of Ser. No. 87,577, Jul. 9, 1993, Pat. No. 5,390,045.
This application Nov. 18, 1994, Ser. No. 342,167
Int. Cl.⁶ G02F 1/01

U.S. Cl. 359—275

1 Claim



1. A new adjustable window tinting system for a vehicle having a plurality of window glass, said system comprising:

- a tinting means for selectively tinting at least one of said plurality of window glass for limiting a passage of light therethrough; the tinting means comprising an electrochromatic glass, and rheostat, said rheostat being electrically connected to both said electrochromatic glass and a power source, the electrochromatic glass comprising a pair of glass panes positioned in a substantially coplanar relationship so as to define a space therebetween, a pair of conductors having a distance therebetween and disposed within said space, and an electrochromatic conductive polymer disposed within said space, said electrochromatic conductive polymer being in electrical communication with said pair of conductors, said electrochromatic conductive polymer comprising an oxidized conductive polymer selected from the group consisting of polyacetylene, poyerinaphthalene, and polynaphthalene.

5,587,829

METHOD AND APPARATUS FOR SIGNAL FILTERING


Edward M. Alexander, Falls Church, Va., and Anthony E. Spezio, Laurel, Md., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Aug. 29, 1994, Ser. No. 296,883

Int. Cl.⁶ G02F 1/11

U.S. Cl. 359—287

16 Claims



1. A filter comprising:
- means for receiving an input signal;
 - means for spatially dispersing said input signal according to frequency, to form a spatially dispersed optical signal; and
 - means for combining selected frequency components of said spatially dispersed signal into a resultant filtered signal;

5,587,830

HIGH CAPACITY OPTICAL FIBER NETWORK


Andrew R. Chraplyvy, and Robert W. Tkach, both of Monmouth County, N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed May 28, 1993, Ser. No. 69,952

Int. Cl.⁶ H04B 10/12; G02B 6/10; 6/28

U.S. Cl. 359—341

10 Claims



1. Wavelength division multiplexed optical waveguide system including:

- a transmitter for generating, modulating, and multiplexing modulated channel carriers for introduction into a transmission line, the transmitter being characterized by a "system wavelength" of magnitude within the wavelength range of the grouped channel carriers; a receiver for performing functions including de-multiplexing modulated channel carriers; optical amplifiers; and a transmission line of optical fiber including at least one fiber span defined at one end by a transmitter and at the other end by a receiver, in which the span includes at least one optical amplifier

CHARACTERIZED IN THAT

substantially all fiber defining the span has a chromatic dispersion of an absolute value in the range 1.5–4 ps/nm-km at the system wavelength.

5,587,831

SEMICONDUCTOR FOIL BEAM-SPLITTER FOR AN INFRARED SPECTROMETER

Arno Simon, Karlsruhe, and Jürgen Gast, Rheinstetten, both of Germany, assignors to Bruker Analytische Messtechnik GmbH, Rheinstetten, Germany


Filed Nov. 23, 1993, Ser. No. 156,430

Claims priority, application Germany, Dec. 16, 1992, 42 42 440.2

U.S. Cl. 359—350

Int. Cl.⁶ G02B 1/10

6 Claims



1. An infrared spectrometer comprising:
- an incident beam having a wavelength in a far infrared optical region; and
 - a beamsplitter, the beamsplitter consisting essentially of a self-supporting foil material selected from the group consisting of carbon and an undoped semi-conductor, the foil material having a thickness less than the wavelength of the incident beam.

5,587,832

SPATIALLY LIGHT MODULATED CONFOCAL MICROSCOPE AND METHOD


Andrew W. Krause, Sparks, Md., assignor to Biophysica Technologies, Inc., Sparks, Md.

Filed Oct. 20, 1993, Ser. No. 138,067

Int. Cl.⁶ G02B 21/06

U.S. Cl. 359—385

22 Claims



1. A confocal optical imaging system for imaging a specimen comprising:

- a light source for providing light to the specimen;
- first optical means to direct light from said light source along an illumination path to said specimen;
- pattern array means positioned in said illumination path between said light source and said specimen which operates to transform light from said light source into a plurality of simultaneously formed illumination spots arranged in a pattern; said pattern array means including an electronically addressed and gated electrostatic microshutter array operative in response to control signals to provide sequential patterns of illumination spots;
- and a control means connected to said pattern array means, said control means operating to provide control signals to said pattern array means to cause said pattern array means to provide sequential complimentary patterns of illumination spots;
- said first optical means operating to separately image each said pattern of illumination spots simultaneously on said specimen.

5,587,833

COMPUTERIZED MICROSCOPE SPECIMEN ENCODER


Louis A. Kamensky, Boston, Mass., assignor to CompuCyt Corporation, Cambridge, Mass.

Filed Jul. 9, 1993, Ser. No. 89,243

Int. Cl.⁶ G02B 21/26; 21/34; G01J 1/20; H04N 7/18

U.S. Cl. 359—393

4 Claims



1. A method for encoding of a specimen slide during scanning examination thereof with a microscope having viewing means and

a moving slide stage, on which the specimen slide is mounted, and subsequent review of the scanning examination, the method comprising the steps of:

- operatively linking a computer, with correlation movement sensor means, to the movable slide stage of the microscope, to correlatively record movement of the slide stage in an x-y direction plane in which the slide stage is movable, with said stage and viewing means being movable relative to each other in the z direction for focussing of the viewing means;
- generating a computer image of a slide having the predetermined area of the specimen slide to be examined;
- fixedly placing the specimen slide on the movable stage of the microscope;
- moving the stage, with concomitant specimen slide movement, until a microscope viewing area is fixed on a predetermined starting location point on said specimen slide;
- thereafter instructing the computer, operatively linked to said movable stage, to start to record subsequent movement in the x-y direction plane of the stage and specimen slide;
- thereafter moving the stage, with concomitant specimen slide movement, away from the starting location point, with microscope examination of the specimen slide at various locations on the specimen slide; with the linked computer, pursuant to programmed instructions, recording the movement and various locations on the generated image of a slide and into computer storage medium;
- causing the computer, pursuant to programmed instructions and an internal clock of the computer to automatically record, on computer storage medium, predetermined indicia on the computer generated image of a slide, at predetermined time intervals, determined by said internal clock, with said indicia correlating to the microscope viewing area location on the specimen, at the predetermined time intervals; and
- optionally marking indicia of interest with a distinguishing marking for subsequent review recognition; and wherein said review of the scanning examination is effected by the steps of:
 - recalling the computer generated image of a slide with indicia thereon from the computer storage medium onto viewing means; and
 - if indicia of interest have been marked with a distinguishing marking; placing the specimen slide on the movable slide stage of a microscope, operatively linked with a computer, by correlation movement sensor means;
 - moving the stage, with concomitant specimen slide movement, until a microscope viewing area is fixed on a predetermined starting location point on said specimen slide;
 - instructing the computer, operatively linked to said movable stage, to start to correlate microscope viewing area of the specimen slide to corresponding indicia on the computer generated image of a slide;
 - moving the stage, with concomitant specimen slide movement, away from the starting location point, with correlation of each subsequent microscope viewing area with indicia on the computer generated image, by indicator means, whereby correlated indicia having a distinguishing marking thereon is directly viewable with the microscope.

5,587,834

SEMICONDUCTOR DEVICE MANUFACTURING METHOD AND PROJECTION EXPOSURE APPARATUS USING THE SAME

Miyoko Noguchi, Tokyo, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 29, 1993, Ser. No. 10,789



Claims priority, application Japan, Jan. 31, 1992, 4-046265

Int. Cl.⁶ G02B 5/18; 27/00

U.S. Cl. 359—558

4 Claims

3. A projection exposure apparatus comprising:
- means for illuminating obliquely an original with a light beam having a main wavelength λ , the original having a grating-like pattern of opaque and light-transmissive areas, the grating-like pattern having a partially isolated pattern and an auxiliary



pattern, the partially isolated pattern being a pattern having, on at least one side thereof, no adjacent pattern other than an auxiliary pattern within a range of $D \leq (\lambda/NA)$, where λ is a wavelength of illuminating light, NA is a numerical aperture of an optical system and D is a distance from one side of the partially isolated pattern measured on an image plane, and the auxiliary pattern having a line width L which satisfies the relation $L \leq 0.2(\lambda/NA)$ and extending in a direction parallel to at least a portion of the partially isolated pattern, the auxiliary pattern being provided at a distance S from the one side of the partially isolated pattern in a direction substantially perpendicular to the one side, where S is within a range of $0 \leq S \leq 0.1(\lambda/NA)$; and

means for projecting a portion of light diffracted by the grating-like pattern onto a pupil plane of a projection optical system having a numerical aperture NA, to project the grating-like pattern onto a photosensitive plate in the image plane.



5,587,835

ANTIREFLECTION FILM AND DISPLAY APPARATUS

Kazuhiko Shimizu, Fukaya; Takeo Itou, Kumagaya, and Hidemi Matsuda, Fukaya, all of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan
Continuation of Ser. No. 280,801, Jul. 26, 1994, abandoned, which is a continuation of Ser. No. 901,147, Jun. 19, 1992, abandoned. This application Feb. 21, 1995, Ser. No. 391,477
Claims priority, application Japan, Jun. 19, 1991, 3-146438
Int. Cl.⁶ G02B 5/28

U.S. Cl. 359—589

12 Claims



1. An antireflection film coating comprising:
 - a substrate having an incident side surface on which unfiltered light is incident and an exit side surface on the opposite side of the substrate;
 - a first light-transmitting thin film, containing a coloring material therein, having a reflection side and an incident side, said reflection side contacting said incident side surface of said substrate, said reflection side reflecting said unfiltered light; and

a second light-transmitting thin film formed on said incident side of said first light-transmitting thin film, on which said unfiltered light is directly incident; wherein said antireflection film coating has reflectance and transmittance characteristics that satisfy the relationship

$$\lambda_r - 50 \text{ nm} < \lambda_r < \lambda_r + 70 \text{ nm}$$

where λ_r is a wavelength at which a spectral reflectance in a visible region is minimized, and λ_t is a wavelength at which a spectral transmittance in the visible region is minimized.

5,587,836

VISUAL DISPLAY APPARATUS

Koichi Takahashi, Hachioji, and Takayoshi Togino, Koganei, both of Japan, assignors to Olympus Optical Co., Ltd., Tokyo, Japan


Filed May 13, 1994, Ser. No. 242,630

Claims priority, application Japan, May 13, 1993, 5-111561

Int. Cl.⁶ G02B 27/14; 27/12

U.S. Cl. 359—630

12 Claims



1. A visual display apparatus having a device for displaying an image;
 - a relay optical system for projecting the image displayed by said image display device to form a first image; and
 - an ocular optical system for projecting said first image in an observer's eyeball,
 wherein said relay optical system has an optical system which is movable along an optical axis and enables a magnification to be changed between two different levels with an image position fixed by moving said movable optical system, wherein when one of said two different levels of magnification is assumed to be β_1 , the other magnification is approximately $1/\beta_1$; and wherein said relay optical system has an optical member of positive power which satisfies the following condition:

$$1.1 < R < 2.25$$

where R is a ratio of two magnifications which are changeable from one to the other by movement of said relay optical system: $R = \beta_1/\beta_2$, where β_1 is a higher magnification and β_2 is a lower magnification.

5,587,837

BINOCULAR EYEPIECE WITH EXTENDED EYE RELIEF

Reynold S. Kebo, Los Angeles, Calif., assignor to Hughes Electronics, Los Angeles, Calif.


Filed Mar. 9, 1993, Ser. No. 28,516

Int. Cl.⁶ G02B 25/00; 9/60; 9/62

U.S. Cl. 359—643

12 Claims

1. A binocular eyepiece comprising:
 - a pair of optical systems, each system consisting of six lenses, one lens defining an optical axis and the remaining five lenses



centered on said axis, said lenses collimating said energy to an exit pupil positioned a desired distance away from the last lens providing extended eye relief, wherein said six lenses of each system are negative, positive, positive, negative, positive and positive power lenses.

5,587,838

PROJECTION LENS UNIT

Takasi Kasihara, Nara, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 212,905, Mar. 15, 1994, abandoned.


This application Feb. 26, 1996, Ser. No. 606,866

Claims priority, application Japan, Mar. 16, 1993, 5-054541

Int. Cl.⁶ G02B 3/00

U.S. Cl. 359—649

10 Claims



1. An optical coupling arrangement for a display device comprising:
 - a display device for displaying a picture;
 - an optical coupling housing mounted to said display device, said optical coupling housing having an aperture therein covered by a movable diaphragm;
 - an optical coupling lens mounted to said optical coupling housing with elastically deformable material;
 - a liquid-tight optical coupling chamber defined by said display device, said optical coupling housing and said optical coupling lens,
 - said optical coupling chamber filled with optical coupling liquid; and
 - an air tank filled with air mounted in an air-tight manner to said optical coupling housing over said movable diaphragm,
 wherein said movable diaphragm moves according to pressure changes in said liquid-tight optical coupling chamber and said air absorbs said pressure changes.

5,587,839

OBJECTIVE LENS SYSTEM FOR ENDOSCOPE

Hitoshi Miyano, and Chikara Yamamoto, both of Saitama-ken, Japan, assignors to Fuji Photo Optical Co., Ltd., Saitama-ken, Japan

Filed Oct. 17, 1995, Ser. No. 544,003


Claims priority, application Japan, Oct. 18, 1994, 6-251976

Int. Cl.⁶ G02B 21/02; 9/34

U.S. Cl. 359—660

2 Claims

1. An objective lens system for an endoscope comprising first to fifth lens elements L_1 to L_5 arranged in this order from the front to



the rear and an aperture stop disposed between the second and third lens elements L_2 and L_3 , the first lens element L_1 being a negative lens concave to the rear, the second lens element L_2 being a positive lens having a flat surface facing rearward, the third lens element L_3 being a positive lens having a flat surface facing forward, the fourth lens element L_4 being a positive lens having a flat surface facing forward, the fifth lens element L_5 being a negative meniscus lens, the fourth and fifth lens elements L_4 and L_5 being cemented together to form a cemented lens having a positive refracting power wherein the following formulae (1) to (3) are satisfied,

$$0.75 < f_1 \times Bf/f^2 < 1.45 \quad (1)$$

$$D_i < 1R_i \quad (2)$$

$$v_2 < 45 \quad (3)$$

wherein f_1 represents the focal length of the first lens element L_1 , Bf represents the back focal length of the overall objective lens system, f represents the combined focal length of the overall objective lens system, D_i represents the central thickness of an lens element L_i having a convex face, R_i represents the radius of curvature of the convex face of an lens element L_i having a convex face and v_2 represents the Abbe's number of the second lens element L_2 .

5,587,840

ZOOM LENS

Yoshinori Itoh, Kanagawa-ken, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 24, 1995, Ser. No. 505,911


Claims priority, application Japan, Jul. 29, 1994, 6-178503;

Jun. 29, 1995, 7-163671; Jun. 29, 1995, 7-163672

Int. Cl.⁶ G02B 15/14

U.S. Cl. 359—686

32 Claims



1. A zoom lens comprising, from front to rear, a first lens unit having a negative refractive power, a second lens unit having a positive refractive power, a third lens unit having a positive refractive power and a fourth lens unit having a negative refractive power, wherein zooming from a wide-angle end to a telephoto end is performed in such a manner that an air separation between said first lens unit and said second lens unit increases, an air separation between said second lens unit and said third lens unit increases and an air separation between said third lens unit and said fourth lens unit decreases.


5,587,841

ZOOM LENS SYSTEM

Takayuki Ito, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan
 Filed Jul. 27, 1994, Ser. No. 281,093
 Claims priority, application Japan, Jul. 27, 1993, 5-184622
 Int. Cl.⁶ G02B 15/14

U.S. Cl. 359—689

15 Claims



7. A zoom lens system comprising at least three lens groups including:

- a positive first lens group comprising a positive lens;
 - a positive second lens group comprising a negative lens assembly including a negative lens and a positive lens assembly including a positive lens arranged in this order from the object to be photographed; and
 - a negative third lens group;
- said first, second and third lens groups being arranged in this order from said object, distances between each lens group changing during a zooming operation;
- a half angle of view at a wide angle extremity of said whole lens system being approximately 37 degrees; wherein said lens groups satisfy the following relationships:

$$0 < f_w/f_1 < 0.5$$

$$1.7 < N_{1P}$$

$$1.75 < N_{2N}$$

$$1.7 < N_{2P}$$

wherein f_w is a focal length of the whole lens system at the wide angle extremity;
 f_1 is a focal length of said positive first lens group;
 N_{1P} is a refractive index of said positive lens of said positive first lens group;
 N_{2N} is a refractive index of said negative lens of said negative lens assembly of said positive second lens group; and
 N_{2P} is a refractive index of said positive lens of said positive lens assembly of said second positive lens group.

5,587,842

LENS CONTROL SYSTEM

Ryunosuke Iijima, Ebina, and Kitahiro Kaneda, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
 Continuation of Ser. No. 902,922, Jun. 23, 1992, abandoned, which is a continuation of Ser. No. 667,191, Mar. 8, 1991, Pat. No. 5,144,492. This application Nov. 22, 1993, Ser. No. 156,797


Claims priority, application Japan, Mar. 12, 1990, 2-62300; Sep. 17, 1990, 2-248185; Sep. 17, 1990, 2-248187

Int. Cl.⁶ G02B 15/14

U.S. Cl. 359—698

29 Claims

1. A lens control apparatus comprising:
- (A) a first lens;
 - (B) first control means for driving said first lens;
 - (C) a second lens whose movement range is different from a movement range of said first lens;



- (D) second control means for driving said second lens;
- (E) memory means for storing a position of said first lens;
- (F) third control means having a first mode in which said first and second control means are operated simultaneously and a second mode in which only one of said first and second control means is operated, and changing a function of said first or second lens for selectively switching said first or second modes according to a position of said second lens and storing the position of said first lens in said memory means in response to the switching from said first mode to said second mode, then moving said first lens to a reference position and moving said first lens to the position stored in said memory means in response to the switching from said second mode to said first mode.


5,587,843

ZOOM LENS MECHANISM

Jim Chen, Taipei, Taiwan, assignor to Industrial Technology Research Institute, Hsinchu, Taiwan
 Filed Jun. 6, 1995, Ser. No. 470,601
 Int. Cl.⁶ G02B 15/14

U.S. Cl. 359—700

8 Claims



1. An improved zoom lens mechanism, including:
- a focusing ring having a plurality of focusing pins;
 - a first barrel with longitudinal slots, said first barrel is interconnected with a rear portion of said focusing ring, and contains a plurality of transverse slots at a front portion thereof respectively matching said focusing pins, said first barrel also contains a plurality of longitudinal slots, generally diametrically opposing each other;
 - an outer ring which is disposed at the front portion said first barrel, said outer ring is provided with a plurality of straight slots providing passages for said focusing pins;
 - an inner ring which is disposed at a rear portion of said outer ring, said inner ring is attached at a rear end of said first barrel, said inner ring is interconnected with said outer ring, both said inner and outer rings are provided with a plurality of beads; and each of said beads can penetrate through said longitudinal slots of said first barrel;
 - a second barrel with spiral slots which is disposed at an outer portion of said first barrel, said second barrel has a front end portion which is provided with a plurality of first contour holes for receiving respective beads disposed within said

inner ring, said front portion of said second barrel is also provided with a second and third contour holes which are disposed adjacent to said first contour hole;

- a third barrel which is provided with a plurality of beads at a surface thereof, each of said beads can penetrate through said longitudinal slots of said first barrel and be received within said second contour holes of said first barrel; and
 - a fourth barrel which is provided with a plurality of beads at its surface, each of said beads can penetrate through said longitudinal slots of said first barrel and be received within said third contour holes of said first barrel;
- whereby the provisions of said longitudinal straight slots diametrically provided at said first barrel, and said second barrel with said spiral slots and said contour holes allow an outer diameter of said lens mechanism to be reduced.

5,587,844

ALBADA TYPE INVERTED GALILEAN FINDER FOR CAMERA

Kazunori Ohno, Saitama-ken, Japan, assignor to Fuji Photo Optical Co., Ltd., Saitama-ken, Japan


Filed Sep. 13, 1994, Ser. No. 305,433

Claims priority, application Japan, Sep. 21, 1993, 5-257766

Int. Cl.⁶ G02B 13/18; G03B 13/02; 13/08

U.S. Cl. 359—717

5 Claims



1. An Albada type inverted Galilean finder lens system for a camera, comprising:

- an objective lens element of negative power having a concave surface on a pupil side opposite an object side which is provided thereon with a half mirror coating; and
 - an eyepiece element having a convex surface on said pupil side and a surface on said object side which is provided thereon with a framing marking defining an area for framing;
- said finder lens system satisfying the following conditions:

$$(1) 4.0 < f_1/L < 7.0$$

$$(2) 2.0 < R_2/d_2 < 2.7$$

$$(3) 0.5 < R_2/R_4 < 2.7$$

where

- L is the overall length of said finder lens system;
- R_2 is the radius of said concave surface of said objective lens element;
- R_4 is the radius of said convex surface of said eyepiece;
- f_1 is the focal length of said eyepiece element; and
- d_2 is the axial distance between said objective lens element and said eyepiece element.

5,587,845

OBJECT LENS HOLDER

Yoshimasa Goda, Kanagawa, Japan, assignor to Sony Corporation, Tokyo, Japan

Division of Ser. No. 237,472, May 3, 1994, Pat. No. 5,555,623,

which is a division of Ser. No. 871,661, Apr. 21, 1992, Pat. No.

5,381,273. This application Jun. 1, 1995, Ser. No. 457,371


Claims priority, application Japan, Apr. 26, 1991, 3-123030

Int. Cl.⁶ G02B 7/02

U.S. Cl. 359—819

6 Claims

1. A block of object lens holders comprising plural interconnected object lens holders, said block comprising:



first and second parallel strip-shaped portions each being formed with positioning holes and interconnected by plural connecting pieces, and

a plurality of bobbin halves integrally molded with a plurality of base pieces integrally formed with at least one of said first and second strip-shaped portions.

5,587,846

LENS MOVING APPARATUS

Masaaki Miyano, Sakai; Toyotoshi Kawasaki, Kawachinagano; Minoru Kuwana, Osaka; Masayuki Miyazawa, Kawachinagano; Masayuki Ueyama, Takarazuka, and Yoshihiro Tasaka, Toyonaka, all of Japan, assignors to Minolta Co., Ltd., Osaka, Japan


Filed Jul. 14, 1995, Ser. No. 502,833

Claims priority, application Japan, Jul. 15, 1994, 6-185217; Jul. 15, 1994, 6-185219; Sep. 21, 1994, 6-226957; Sep. 21, 1994, 6-226958

Int. Cl.⁶ G02B 7/02

U.S. Cl. 359—824

28 Claims



28. A lens moving apparatus, comprising:

- a piezoelectric element which vibrates and deforms upon application of a voltage,
- one end of said piezoelectric element being fixedly supported and the other end being a free end displaceable upon application of the voltage to the piezoelectric element;
- a lens driving member coupled to said other end of said piezoelectric element and operates in association with vibration and deformation of said piezoelectric element,
- said lens driving member driving a lens holder holding said lens slidably in a direction of an optical axis of the lens;
- a magnetized member having N poles and S poles arranged alternately at a prescribed interval along the direction of the optical axis of said lens;
- a pair of magneto-resistive elements fixed at a position near the magnetized member on said lens holder, a magnetic resistance of said pair of magneto-resistive elements changing as said lens holder slides, said change in magnetic resistance including a phase difference;
- a controller for calculating ratio of change of the magnetic resistance having phase difference, and for forming a new signal based on the ratio;
- a detector for detecting position of the lens based on the signal formed by said controller; and
- displaying means for visually displaying position of the lens detected by the detector.

5,587,847

LASER PROTECTION WINDOW USING HOLOGRAPHIC OPTICAL ELEMENT AND CHANNEL PLATES


Byung J. Chang, Ann Arbor, and James M. Tedesco, Livonia, both of Mich., assignors to Kaiser Optical Systems, Ann Arbor, Mich.

Continuation of Ser. No. 163,555, Mar. 3, 1988, abandoned. This application Aug. 14, 1990, Ser. No. 578,511

Int. Cl.⁶ G02B 5/22; B32B 3/10

U.S. Cl. 359—890

30 Claims



1. A laser protection window for protection of an eye having no fixed position relative to the laser protection window from an expected laser threat comprising:

- a planar holographic optical element having interference fringes embedded therein for forming a reflection hologram at the wavelength of the expected laser threat; and
- a set of channel plates disposed at regular intervals at right angles to said holographic optical element, each of said channel plates opaque to light at said wavelength of the expected laser threat;

whereby said set of channel plates cooperate to block all incoming light arriving at angles for which said holographic optical element does not reflect said wavelength of the expected laser threat from reaching the eye regardless of the position of the eye behind said laser protection window and further cooperate to permit substantially all incoming light passed by said holographic optical element arriving at angles for which said holographic optical element reflects said wavelength of the expected laser threat to reach the eye regardless of the position of the eye behind said laser protection window.

5,587,848

DIGITAL SIGNAL MAGNETIC RECORDING AND REPRODUCING APPARATUS FOR BOTH METAL EVAPORATION TAPES AND METAL POWDER TAPES

Masafumi Shimotashiro, and Akio Kuroe, both of Katano, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Apr. 18, 1995, Ser. No. 423,727

Claims priority, application Japan, Apr. 18, 1994, 6-078342

Int. Cl.⁶ G11B 5/09

U.S. Cl. 360—46

5 Claims



1. A magnetic recording apparatus for digital signals, said apparatus comprising:

- a metal powder tape having a magnetic layer, said magnetic layer having a thickness of 0.2 μm or less and a coercive force of 2,000 Oe or more;
- a magnetic head for recording signals onto said metal powder tape; and
- a recording current setting circuit for supplying a recording current to said magnetic head according to input digital signals, a value of the recording current being 4 dB higher than that necessary to obtain 90% of a maximum output level at a shortest wavelength to be recorded for a reference metal evaporation tape of a predetermined digital video cassette recording consumer use standard.

5,587,849

MECHANISM FOR SECURING RECORDED CONTENTS OF RECORDING MEDIUM CASSETTE

Teruhiko Kori, Hiroshi Yamazaki, both of Kanagawa; Harumi Kawamura, Tokyo; Hisato Shima, Chiba, and Kazuyuki Ogawa, Kanagawa, all of Japan, assignors to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 140,259, Oct. 21, 1993, abandoned.


This application Jul. 14, 1995, Ser. No. 502,467

Claims priority, application Japan, Oct. 22, 1992, 4-284706

Int. Cl.⁶ G11B 15/18; 17/00; 11/02; 27/36

U.S. Cl. 360—69

2 Claims



1. Apparatus for securing data recorded on a recording medium housed in a cassette wherein said cassette is provided with data recording enable/disable means for enabling and disabling recording on said recording medium and may or may not be provided with a memory for storing information about data recorded on said recording medium, said apparatus comprising:

- recording means;
- state detecting means for producing a state detection signal representing the state of said enable/disable means;
- memory detecting means for producing a memory detection signal representing a presence or an absence of a memory in said cassette; and
- microcomputer means for disabling recording by said recording means in response to a memory detection signal indicating the presence of a memory in said cassette;
- disabling of recording by said recording means in response to a memory detection signal indicating the absence of a memory in said cassette and a state detection signal indicating that said enable/disable means is in a disable state; and
- enabling recording by said recording means in response to a memory detection signal indicating the absence of a memory in said cassette and a state detection signal indicating that said enable/disable means is in an enable state.

5,587,850

DATA TRACK PATTERN INCLUDING EMBEDDED SERVO SECTORS FOR MAGNETO-RESISTIVE READ/INDUCTIVE WRITE HEAD STRUCTURE FOR A DISK DRIVE


Luan Tonn-that, San Jose, Calif., assignor to Quantum Corporation, Milpitas, Calif.

Filed Aug. 26, 1994, Ser. No. 296,643

Int. Cl.⁶ G11B 5/596

U.S. Cl. 360—77.08

5 Claims



1. In a disk drive including a magnetic data storage disk rotating relative to a base, a data transducer assembly positioned at concentric data track locations by a rotary actuator referenced to the base and controlled by a closed loop servo circuit, the data transducer assembly including a write element, and a read element offset longitudinally from the write element such that when at least some of the track locations are being accessed by the data transducer assembly, a centerline of a magnetic path on the disk read by the read element is offset from a centerline of a magnetic path written to the disk by the write element by a micro-jog distance, and a plurality of servo wedges embedded within the data tracks wherein each servo wedge includes a servo preamble, a single servo identification field, and a plurality of circumferentially sequential, radially offset servo bursts, an improved method for centering the data transducer assembly relative to a centerline of a track to be followed, the method comprising the steps of:

for each servo wedge and each track, forming a respective servo preamble at a first radial displacement relative to the centerline of the track, forming a respective single servo identification field at a second radial displacement related to the micro-jog distance from the centerline of the track, and forming at least a pair of servo bursts to have oppositely facing burst edges in registration, the oppositely facing burst edges being offset from the centerline of the track by the micro-jog distance.

during disk drive data writing operations, reading with the read element the respective servo preamble, the respective single servo identification field, and the pair of servo bursts to obtain relative burst amplitudes therefrom in order to supply write-mode position error signals to the closed loop servo circuit to align the write element with the centerline, and during disk drive reading operations, displacing the data transducer assembly from the centerline by the micro-jog distance, and reading with the read element the respective servo preamble, the respective single servo identification field, and the pair of servo bursts to obtain relative burst amplitudes therefrom in order to supply read-mode position error signals to the closed loop servo circuit to align the read element with the centerline.

5,587,851

MAGNETIC HEAD DRIVING DEVICE WITH PRERECORDING ENERGIZATION

Mitsuo Ishii, Nabari, Japan, assignor to Sharp Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 275,239, Jul. 15, 1994, abandoned.


This application Dec. 11, 1995, Ser. No. 570,207

Claims priority, application Japan, Dec. 24, 1991, 3-341428

Int. Cl.⁶ G11B 5/09; 15/12; 11/00

U.S. Cl. 360—59

6 Claims



1. A magnetic head driving device, comprising: an inductor for generating a magnetic field, said inductor having a pair of terminals; first storing means for storing electromagnetic energy, said first storing means being connected to one of said terminals of said inductor at a first node; second storing means for storing electromagnetic energy, said second storing means being connected to the other terminal of said inductor at a second node; first switching means connected to said first node; second switching means connected to said second node; and control means for receiving a first signal indicating that it causes the generation of a magnetic field by said inductor, and a second signal reversing the direction of current through said inductor and inverting the magnetic field with each reversal, said control means outputting a third signal during a predetermined period of time to alternately turn on and off said first switching means and said second switching means, the predetermined period of time being before Start of a recording operation, and physical change on magnetic media being precluded during the predetermined period of time.

5,587,852

DISK HEAD DRIVING DEVICE USING LINEAR ACTIVATOR WITH MULTIPOLAR MAGNETS

Tsukasa Yoshiura, Katano, and Kiyoshi Masaki, Amagasaki, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Dec. 6, 1994, Ser. No. 350,337

Claims priority, application Japan, Dec. 7, 1993, 5-305672

Int. Cl.⁶ G11B 5/596

U.S. Cl. 360—78.12

9 Claims



1. A head driving device comprising: a carriage having a head for recording or reproducing data onto a data recording medium, said carriage being capable of moving in a straight line;

a linear motor including a plurality of coils, a pair of multipolar magnets, and a stator yoke, said plurality of coils being fixed on the carriage and shifted from each other in a moving direction of the carriage, polarities of said multipolar magnets being alternated along a passage for said plurality of coils, and said stator yoke being ferromagnetic and fixing said multipolar magnets, wherein said multipolar magnets are disposed symmetrically along both sides of the passage for said plurality of coils, one of the coils is positioned so that its phase is shifted from at least one of the other coils by 90 degrees and the resulting magnetic field wave is accordingly shifted, said multipolar magnets are composed of a plurality of unipolar magnetic elements, and a width W of the unipolar magnetic elements and a distance D between adjacent unipolar magnetic elements are in a relation of $0.4 W \leq D \leq 0.6 W$;

a position detection means for detecting a position of the carriage; and

a driving circuit for supplying driving current to said plurality of coils, said driving circuit including a function generation means and a current calculation means, said function generation means generating function signals for each coil, each of said function signals corresponding to a detected position of the carriage, based on a dispersion of magnetic flux to be generated by said multipolar magnets and said current calculation means calculating current to be supplied to said plurality of coils, based on the function signals, wherein said driving circuit includes an operational signal generation means for generating operational signals, based on a position detected by said position detection means, and said current calculation means calculates an amount of current to be supplied to said plurality of coils by multiplying the operational signal generated by said operational signal generation means and the function signal generated by the function generation means, and said operational signal generation means generates the operational signals based on a positional error between the position detected by the position detection means and a desired position.


5,587,853

MANUALLY OPERATED VIDEO CASSETTE ADAPTER
David Tai, 1st. Fl., No. 17, Lane 180, Ho-Chiang Street, Taipei, Taiwan

Filed Aug. 8, 1995, Ser. No. 512,693
Int. Cl.⁶ G11B 23/04

U.S. Cl. 360—94

11 Claims



1. A video cassette adapter comprising:
a housing having a front section, a rear section, first and second lateral sections, a top wall, a bottom wall and a receptacle for receiving a VHS-C video cassette, the receptacle including a front portion, a rear portion, first and second lateral portions, a top opening and a bottom wall, the front portion of the receptacle being communicated with the front section of the housing;

a first tape conducting member having one end pivotally disposed between the first lateral section of the housing and the first lateral portion of the receptacle, and an other end provided with a tape conducting roller and shiftable from the front portion of the receptacle to the front section of the

housing or from the front section of the housing to the front portion of the receptacle;

a second tape conducting member having one end pivotally disposed between the second lateral section of the housing and the second lateral portion of the receptacle, and an other end provided with a tape conducting roller and shiftable from the front portion of the receptacle to the front section of the housing or from the front section of the housing to the front portion of the receptacle;

a first gear rotatably disposed in the housing and extended through the first lateral portion of the receptacle to engage with a gear of a tape take-up reel of the video cassette;

a tape rolling reel rotatably disposed in the housing between the first lateral section thereof and the first lateral portion of the receptacle, the tape rolling reel being provided with a gear and drivingly engaged with the first gear;

an operation button slidably disposed on the top wall of the housing and extended through the top wall into the housing;

a driving lever slidably disposed in the housing and having a driving pin slidably operatively connected with the first tape conducting member to drive the same reversibly between a non-operation position to an operation position, the driving lever being connected with the operation button;

a transmission mechanism disposed between the second lateral section of the housing and the second lateral portion of the receptacle, one end of the transmission mechanism being slidably connected with the second tape conducting member;

a linkage lever slidable disposed between the rear section of the housing and the rear portion of the receptacle, two ends of the linkage lever being pivotally connected with the first tape conducting member and the transmission mechanism respectively; and

a spring connected between the housing and the driving lever.

5,587,854



CASE UNIT HAVING A DUAL CASE STRUCTURE FORMED BY AN OUTER CASE MEMBER AND AN INNER CASE MEMBER FOR A DISK STORAGE APPARATUS

Toshikuni Sato, Kawasaki, and Masaya Agematsu, Tokyo, both of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Filed May 15, 1994, Ser. No. 288,727
Claims priority, application Japan, Aug. 16, 1993, 5-202283
Int. Cl.⁶ G11B 5/012; H05K 7/12; 7/14

U.S. Cl. 360—97.01

5 Claims



1. A disk storage unit being removable from a computer body, the disk storage unit comprising:

connector means for connecting the computer body to a disk drive of the disk storage unit;

case means having an inner case member for containing the disk drive, an outer case member for containing the inner case member, and a guide mechanism for pushing out the inner case member from an inside of the outer case member to an outside of the outer case member, the inner case member having a case lock mechanism for removably holding the disk drive; and

a disk lock mechanism for removably holding the disk drive to the computer body when the disk drive is connected to the computer body by the connector means, the disk lock mechanism releasing the case lock mechanism and locking the disk drive when the inner case member is pushed out from the inside of the outer case member to the outside of the outer case member.

5,587,855

SUPPORTING DEVICE FOR MINIMIZING VIBRATION, NOISE AND EXTERNAL IMPACT OF A HARD DISK DRIVE

Kwang-Kyu Kim, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-do, Rep. of Korea


Filed Dec. 1, 1994, Ser. No. 352,803

Claims priority, application Rep. of Korea, Dec. 1, 1993, 26119/1993

Int. Cl.⁶ G11B 33/08

U.S. Cl. 360—97.02

17 Claims



1. A disk drive comprising:

a spindle motor;

a disk rotatably mounted upon said spindle motor;

a body providing a base accommodating rotation of said disk while said disk is driven by said spindle motor;

a pivot mounted upon said body;

a head assembly mounted rotatably mounted upon said pivot, said head assembly including an actuator and a magnetic head for writing and reading data recorded on said disk as said head assembly rotates about said pivot;

a cover enclosing said disk within said body;

a plate discrete and spaced apart from the cover, said plate being interposed between the cover and said head assembly, said plate having a thermal coefficient of expansion substantially the same as that of said body, said plate having a center portion attached to a shaft of said spindle motor and a plurality of peripheral portions separately extending from said center portion to said pivot of said head assembly and to a plurality of spaced-apart locations mutually separated from each other by said disk and from said pivot by said disk;

means for individually attaching each of said peripheral portions to said body; and

dampers means disposed between said cover and said head assembly, said dampers means being attached to one of an

upper portion and a lower portion of said plate, for damping generation of said vibration, noise and external impact.

5,587,856

DISC LOADING MECHANISM INCLUDING A DAMPER MOUNTED IN A BASE PLATE RECESS

Takashi Aoyama, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 248,453, May 24, 1994, abandoned.


This application Dec. 8, 1995, Ser. No. 569,564

Claims priority, application Japan, May 28, 1993, 5-126419

Int. Cl.⁶ G11B 17/04

U.S. Cl. 360—99.02

9 Claims



1. A disk drive apparatus for reading data from and/or writing to a disk contained in a disk cartridge loaded thereon, comprising:

a chassis including first and second opposing side plates connected by a base plate such that said first and second side plates are supported perpendicular to said base plate in a spaced apart relationship, at least one of said first and second side plates being formed with an elongate horizontal closed slot including a hook at one end thereof;

disk cartridge positioning means integrally formed on an upper surface of said base plate for positioning said disk cartridge loaded thereon;

a slider movably supported on said chassis and receivable of said disk cartridge for moving said disk cartridge in upward and downward directions to facilitate engagement between a lower side of said disk cartridge and said disk cartridge positioning means according to a loading/unloading operation of said disk drive, wherein said disk cartridge positioning means guides movement of said slider in forward and rearward directions while permitting movement of said slider in upward and downward directions with respect to said base plate for an entire locus of movement of said slider in the forward and rearward directions, said slider including at least one projection at a side thereof engageable with said slot formed in said one side plate of said chassis

for guiding movement of said slider in a horizontal direction and for continuously preventing movement of said slider in the upward and downward directions with respect to said base plate; and

biasing means disposed in said slot and connected between said projection and said hook in said slot, said biasing means biasing said slider in a direction of extracting said disk cartridge.


5,587,857

SILICON CHIP WITH AN INTEGRATED MAGNETORESISTIVE HEAD MOUNTED ON A SLIDER
Steven H. Voldman, Burlington, Vt.; Albert J. Wallash, Morgan Hill, Calif., and Reginald B. Wilcox, Jr., Cambridge, Vt., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Oct. 18, 1994, Ser. No. 324,841
Int. Cl.⁶ G11B 21/21

U.S. Cl. 360—103

14 Claims



1. A combined head and slider comprising:
a non-silicon slider body having a trailing edge;
a silicon chip having a leading edge and a trailing edge;
the leading edge of the silicon chip being fixedly mounted to the trailing edge of the slider;
at least one silicon circuit device mounted in the silicon chip;
the head being mounted on a selected one of the trailing edge of the slider between the slider and the silicon chip or the trailing edge of the silicon chip and being connected to the silicon circuit device.

5,587,858


NEGATIVE PRESSURE SLIDER WITH OPTIMIZED LEADING POCKET FOR PROFILE CONTROL
Lee K. Dorius, and Laurence S. Samuelson, both of San Jose, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Division of Ser. No. 149,861, Nov. 10, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 486,088

Int. Cl.⁶ G11B 5/60; 21/21

U.S. Cl. 360—103

14 Claims



1. A negative pressure air bearing slider for use in a disk drive, said slider including a leading edge, a trailing edge, first and second side edges, and an air bearing surface, said air bearing surface further comprising:

two TE pockets, each defined by a generally U-shaped rail including a cross rail and a pair of side rails extending from said cross rail in the direction of said trailing edge;
a center rail disposed between and spaced apart from said TE pockets extending from said leading edge to said trailing edge; and

two LE pockets, each defined by a generally U-shaped rail including a cross-rail and a pair of side rails extending from said cross rail in the direction of said leading edge, wherein said U-shaped rail of each LE pocket abuts one of said U-shaped rails of said first and second TE pockets.

5,587,859


RECORDING AND/OR REPRODUCING APPARATUS HAVING ROTARY TRANSFORMER
Osamu Nagatsuka, Kanagawa-ken, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Aug. 11, 1994, Ser. No. 289,090

Claims priority, application Japan, Aug. 31, 1993, 5-239176
Int. Cl.⁶ G11B 5/52

U.S. Cl. 360—108

16 Claims



1. A rotary transformer arranged to transmit signals between a rotor and a stator, comprising:
(a) a pair of cores arranged to form said rotor and said stator, each of said pair of cores being in a cylindrical shape; and
(b) a plurality of windings secured to one end face of each of said pair of cores, each of said windings being in a flat plate shape, the center of each of said windings approximately coinciding with the center of each of said pair of cores, said windings differing in coil diameter, and said windings being provided respectively with protruding parts which are aligned in a radial direction of said cores, said protruding parts respective free ends radially spaced from one another within an outer perimeter of said plurality of windings.

5,587,860

MAGNETIC DISC CARTRIDGE INCLUDING A MAGNETIC DISC HAVING A CLEANING SHEET COMPOSED OF A NON-THEROPLASTIC FIBER
Nobuhiro Umebayashi; Kunio Mizushima, both of Tsukuba; Akira Miyake, Osaka, and Teruhisa Miyata, Otokuni-gun, all of Japan, assignors to Hitachi Maxell, Ltd., Osaka, Japan
Continuation of Ser. No. 68,290, May 28, 1993, which is a continuation of Ser. No. 784,071, Oct. 30, 1991, which is a continuation of Ser. No. 378,826, Jul. 12, 1989. This application Dec. 23, 1994, Ser. No. 363,022

Claims priority, application Japan, Jul. 14, 1988, 63-173724; Sep. 1, 1988, 63-219240; Sep. 26, 1988, 63-240511

Int. Cl.⁶ G11B 23/03; B32B 5/16

U.S. Cl. 360—133

12 Claims

1. A magnetic disc cartridge for high density recording of 35 Kfci or more comprising in combination a cartridge case, a magnetic disc housed rotatably in said cartridge case, and a cleaning sheet of non-woven fabric secured on an inner surface of said cartridge case juxtapositioned relative to said magnetic disc, said magnetic disc having a linear recording density of 35 Kfci or more

5,587,862


GROUND FAULT INTERRUPTER BUCKET COMBINATION
William D. Frank, Sr., P.O. Box 81, Long Plains Rd., West Buxton, Me. 04093

Filed Jul. 13, 1995, Ser. No. 501,943

Int. Cl.⁶ H02H 3/00

U.S. Cl. 361—42

30 Claims



including a magnetic layer comprising a soft magnetic powder and a reinforcing powder dispersed in a binder resin, said soft magnetic powder being selected from at least one member of the group consisting of a ferromagnetic metal powder and a barium ferrite powder, said reinforcing powder having a particle size of from 0.1 to 1.0 μm and being present in said magnetic layer of said magnetic disc in an amount of from 5 to 40% by weight, wherein at least a disc side surface layer of said cleaning sheet, which is brought into direct sliding contact with said magnetic layer consists of a non-thermoplastic fiber.

5,587,861

METHOD FOR INTERRUPTING ELECTRICAL POWER BETWEEN TWO CONDUCTORS


Christopher J. Wieloch; Mark A. Kappel, both of Brookfield; Jeffrey R. Annis, Waukesha, all of Wis.; David J. Benard, Newbury Park, Calif.; Ellen Boehmer, Thousand Oaks, Calif., and Gernot Hildebrandt, Simi Valley, Calif., assignors to Allen-Bradley Company, Inc., Milwaukee, Wis.

Filed Sep. 29, 1995, Ser. No. 536,712

Int. Cl.⁶ H01H 73/00

U.S. Cl. 361—14

26 Claims



1. A method for interrupting electrical power between first and second conductors comprising the steps of:

- biasing an electrically conductive spanner into a conducting position wherein electrical power is conducted between the first and second conductors;
- repelling the spanner in response to an excessive current condition to move the spanner to an interrupted position wherein electrical power between the first and second conductors is interrupted; and
- directing expansion of arcs produced in step (b) between the spanner and the first conductor and between the spanner and the second conductor to generate a voltage tending to extinguish the arcs.

5,587,863

DIGITAL INTERFACE UNIT

Jan O. Bergström; Lars Liljegren; Ove Skarhed, and Anders Årenäs, all of Västerås, Sweden, assignors to Asea Brown Boveri AB, Västerås, Sweden

PCT No. PCT/SE92/00178, § 371 Date Jan. 26, 1994, § 102(e) Date Jan. 26, 1994, PCT Pub. No. WO92/17829, PCT Pub. Date Oct. 15, 1992


Continuation of Ser. No. 122,472, Jan. 26, 1994. This PCT application Mar. 23, 1992, Ser. No. 608,950

Claims priority, application Sweden, Apr. 2, 1991, 9100951
Int. Cl.⁶ H02H 3/00

U.S. Cl. 361—93

13 Claims

1. An integral digital signal interface for interfacing between an electronic control unit (ECU) and external electrical process equipment (EEPE), said interface having input terminals for receiving



control signals from said ECU and output terminals for transmitting signals for controlling said EEPE, said digital signal interface comprising:

control means for receiving mode select signals from said ECU for selectively programming the interface to operate in digital output/input modes and for receiving threshold input values from said ECU to perform a plurality of functions for controlling the interface and for providing operating functions with respect to controlling said EEPE;

said control means including: at least one multiplexor for receiving at least one of said mode select signals and at least one of said threshold input values from said ECU; a first current limit regulator responsive to an output of said at least one multiplexor, power MOSFET circuits (PMCs) responsive to an output of said first current limit regulator for selectively switching said interface into respective digital input (DI) and digital output (DO) modes, and the interface is correspondingly set to receive input data/control signals from the ECU or to function to generate respective output signals for controlling the EEPE.

5,587,864

SHORT CIRCUIT AND GROUND FAULT PROTECTION FOR AN ELECTRICAL SYSTEM


Allan R. Gale, Allen Park, and Craig B. Toepfer, Dearborn, Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Apr. 11, 1994, Ser. No. 225,872

Int. Cl.⁶ H02H 3/32

U.S. Cl. 361—44

12 Claims



1. A three-phase electrical system comprising a portion which further comprises:

- a first phase conductor;
 - a second phase conductor;
 - a third phase conductor;
 - first current sensing means for sensing a current only in said first phase conductor; and
 - second current sensing means for sensing a current only in said third phase conductor; wherein
- said first current sensing means comprises a first current transformer disposed about said first phase conductor; and

said second current sensing means comprises a second current transformer disposed about said third phase conductor; and said first and second current transformers have a different product of transformer constant and square of number of coil turns.

5,587,865

ELECTRONIC CONTROL EQUIPMENT FOR MOTOR VEHICLES, PARTICULARLY, ELECTRONIC BRAKE CONTROL EQUIPMENT

Peter M. Bielig; Klaus Brähler, both of München, and Günther Gschöfmann, Mühldorf, all of Germany, assignors to Knorr-Bremse Systeme für Nutzfahrzeuge GmbH, Munich, Germany


Filed May 1, 1995, Ser. No. 432,088

Claims priority, application Germany, May 2, 1994, 44 15 386.4

Int. Cl.⁶ H02H 3/16

U.S. Cl. 361—45

12 Claims



1. An electronic control apparatus that controls an electrical load for use in motor vehicles comprising:

- at least one supply voltage terminal for providing a supply voltage to the control apparatus;
- at least one ground terminal for grounding the control apparatus at a ground potential M1;
- at least one output terminal for driving the load with the supply voltage, said load having a first connection to the output terminal and a second connection grounded to a ground potential M2;
- a test circuit for causing a test current having a predetermined minimum magnitude to flow through the load only when the ground potential M1 exceeds the ground potential M2 by a threshold level;
- a measuring element for detecting the magnitude of the test current; and
- an evaluation circuit responsive to the magnitude of the test current detected by the measuring element for initiating countermeasures to protect said control apparatus from damage resulting from differences in the ground potentials M1 and M2.

5,587,866

POWER-ON RESET CIRCUIT

Randy L. Yach, Phoenix, and Richard L. Hull, Chandler, both of Ariz., assignors to Microchip Technology Incorporated, Chandler, Ariz.


Filed Jul. 27, 1995, Ser. No. 508,332

Int. Cl.⁶ H02H 3/20

U.S. Cl. 361—90

6 Claims

1. A power-on reset circuit coupled to an electronic circuit for placing the electronic circuit in reset when power is turned on and until the supply voltage for the electronic circuit reaches a pre-



terminated threshold level and for taking the electronic circuit out of reset when the supply voltage exceeds said threshold level, the power-on reset circuit comprising:

- a trip point generator coupled to receive the supply voltage and incorporating a worst case component constituting a component of the electronic circuit that requires the highest supply voltage to operate properly such that when said worst case component becomes operative, all components of the electronic are also in proper operation; and
- sensor means coupled to said trip point generator and responsive to said worst case component becoming operative for generating a corresponding signal to take the electronic circuit out of reset, said sensor means including noise filter means for returning the electronic circuit to reset when supply voltage variations cause the supply voltage to drop below the threshold level for at least a predetermined time interval.

5,587,867

SURGE ABSORBER

Koichi Kurasawa; Mikio Harada, and Takaaki Ito, all of Saitama-ken, Japan, assignors to Mitsubishi Materials Corporation, Tokyo, Japan


Filed Jun. 27, 1994, Ser. No. 266,040

Claims priority, application Japan, Jun. 30, 1993, 5-162063

Int. Cl.⁶ H02H 1/00

U.S. Cl. 361—118

8 Claims



1. A surge absorber which comprises:

- a surge absorbing element comprising a silicon two-terminal thyristor element having a PNP or NPN junction structure; and
- a bulk resistance element which comprises a material having a resistivity within a range of from $10^{-4}\Omega\text{-cm}$ to $10^3\Omega\text{-cm}$ and a resistance value within a range of from 0.5Ω to 50Ω ; said thyristor element and said bulk resistance element being connected in series to form an integral body.

5,587,868

HIGH VOLTAGE SPHERE-GAP DISCHARGE SWITCH, HIGH VOLTAGE PULSE GENERATION CIRCUIT AND HIGH VOLTAGE DISCHARGE SWITCHING METHOD

Kensuke Akutsu, Toyonaka, Japan, assignor to Nippon Paint Co., Ltd., Osaka, Japan

Filed Feb. 17, 1995, Ser. No. 390,607

Claims priority, application Japan, Feb. 21, 1994, 6-022265


Int. Cl.⁶ H01T 1/20

U.S. Cl. 361—231

8 Claims

1. A high voltage sphere-gap discharge switch which operates by means of the generation of spark discharge comprising:

- a support structure;



a pair of sphere electrodes mounted to said support structure which oppose each other and are separated by a discharge gap.

projections formed on mutually facing portions of said sphere electrodes and which have a projection length of $1/100$ to $1/5$ times the diameter of said sphere electrodes and an outer diameter of $1/100$ to $1/10$ times of said sphere electrodes, and an air current generator associated with said support structure which selectively supplies an air current through said support structure for expelling products produced on the above mentioned projections, generated by the spark discharge;

wherein a pair of ventilation openings are provided on opposite sides of said support structure to allow an air current in a direction which intersects a line joining the centers of said pair of sphere electrodes, and said support structure includes an insulating case which houses said sphere electrodes.

5,587,869

HIGH-VOLTAGE CAPACITOR MANUFACTURING METHOD AND HIGH-VOLTAGE CAPACITOR

Takeshi Azumi; Osamu Yamaoka, and Kazuyuki Kubota, all of Nagaokakyo, Japan, assignors to Murata Manufacturing Co., Ltd., Kyoto-fu, Japan


Filed Feb. 17, 1995, Ser. No. 390,482

Claims priority, application Japan, Feb. 17, 1994, 6-020538; Nov. 1, 1994, 6-293944

Int. Cl.⁶ H01G 4/002; 4/005; 4/224

U.S. Cl. 361—301.3

16 Claims



1. A high-voltage capacitor manufacturing method comprising the steps of: enclosing in a hermetic casing a capacitor body provided with an electrode connected to an external terminal, the external terminal including a passageway therein for making an inside of the hermetic casing communicate with an outside of the hermetic casing while the external terminal is led out of the hermetic casing from the electrode of the capacitor body; discharging a gas from the inside of the hermetic casing by way of the passageway within the external terminal to reduce the pressure inside the hermetic casing; and filling the inside of the hermetic casing with an insulating material.

5,587,870


NANOCRYSTALLINE LAYER THIN FILM CAPACITORS
Wayne A. Anderson, Hamburg, N.Y.; Quanxi Jia, Los Alamos, N.M.; Junsin Yi, Amherst, and Lin-Huang Chang, Tonawanda, both of N.Y., assignors to Research Foundation of State University of New York, Albany, N.Y.

Continuation-in-part of Ser. No. 945,891, Sep. 17, 1992, Pat. No. 5,390,072. This application Jun. 22, 1994, Ser. No. 263,521


Int. Cl.⁶ H01G 4/10

U.S. Cl. 361—313

43 Claims



31. A high performance capacitor comprising film layers of a dielectric material arranged in opposing juxtaposition, one said layer comprising said dielectric in amorphous configuration, another of said layers comprising said dielectric material in nanocrystalline configuration and a further layer comprising said dielectric material in polycrystalline configuration, said opposing layers being arranged between upper and lower electrodes.



polyethylene oxide, polyvinyl alcohol, polyvinyl acetate, polyacrylamide, poly(vinyl pyrrolidone), poly(2-vinylpyridine), poly(4-vinylpyridine) and poly(ethylene imine) and having dispersed therein a proton conducting electrolyte active species selected from the group of H_3PO_4 and H_2SO_4 .

5,587,873

DISTRIBUTOR

Michio Sakai, Ryouzou Hosoya, Nobuyuki Orito, and Minoru Nakahata, all of Marugame, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Division of Ser. No. 39,319, Jun. 10, 1993, Pat. No. 5,340,012. This application Feb. 7, 1995, Ser. No. 385,811

Claims priority, application Japan, Aug. 23, 1991, 3-211784

Int. Cl.⁶ H02B 5/00

U.S. Cl. 361—603

10 Claims



1. A distributor, comprising:
at least one transformer;
a supply bushing disposed on top of each transformer;
a load bushing disposed on top of each transformer;
closed housings disposed on top of each transformer so as to cover each supply bushing and each load bushing for shielding said supply bushing and said load bushing;
a switch connected to each supply bushing and disposed in each closed housing which covers each supply bushing; and
a distribution board disposed adjacent one side of each transformer.

5,587,874

ELECTRICAL BUSWAY METER SERVICE PANEL COMBINATION

Dale Hoppensteadt, 22 W. 492 Lakeside Dr., Glen Ellyn, Ill. 60137, and Joseph L. Mirocha, 14333 S. Glen Dr. West, Lockport, Ill. 60441


Filed Aug. 16, 1995, Ser. No. 515,649

Int. Cl.⁶ H02B 1/00

U.S. Cl. 361—663

8 Claims

1. An electrical busway meter service panel combination, comprising:
a meter fitting housing for housing a utility meter or at least one current transformer, said meter fitting housing having a housing aperture therein;



an insert busway for holding electrical conductors therein, said busway having a first end and a second end, said first end being positioned and slidable within said housing aperture; said second end being integral to an outside portion of said insert busway which extend outside said meter fitting housing; a conduit having a conduit first end and a conduit second end, said conduit first end being attached to said insert busway second end; and
a service disconnecting means housing, said service disconnecting means housing being connected to said conduit second end.

5,587,875

COLLAPSIBLE NOTEBOOK COMPUTER KEYBOARD STRUCTURE WITH HORIZONTALLY AND DOWNWARDLY SHIFTABLE KEY RETURN DOMES


Charles A. Sellers, Houston, Tex., assignor to Compaq Computer Corporation, Houston, Tex.

Continuation-in-part of Ser. No. 268,818, Jun. 30, 1994, Pat. No. 5,532,904. This application Aug. 16, 1995, Ser. No. 515,987

Int. Cl.⁶ G06F 1/16; H01H 3/12; B41J 11/56; H05K 7/04

U.S. Cl. 361—680

20 Claims



1. A collapsible keyboard structure for a portable computer, comprising:
a first support structure having top and bottom sides;
a series of keys each carried on said top side of said first support structure for vertical movement relative thereto, through a vertical key stroke distance, between extended and retracted positions separated by a vertical distance greater than said key stroke vertical distance;

a second support structure carried beneath said first support structure and having a top side facing said bottom side of said first support structure; and
a spaced series of resilient key return members anchored to said second support structure and having top end portions projecting upwardly beyond said top side of said second support structure, said first and second support structures being horizontally and vertically shiftable relative to one another between a first position in which said key return members underlie and resiliently hold said keys in said extended positions thereof and permit said keys to be resiliently moved downwardly from said extended position through said key stroke distance, and a second position in which said key return members are horizontally and downwardly shifted in a manner permitting said keys to be moved from said extended positions thereof to said retracted positions thereof without vertically compressing said resilient key return members.

5,587,876

MODULAR MONITOR ARCHITECTURE


John O'Brien, and Jonathan Ive, both of San Francisco, Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Filed Mar. 30, 1995, Ser. No. 413,401

Int. Cl.⁶ H05K 7/16

U.S. Cl. 361—682

18 Claims



1. A modular architecture for a computer monitor comprising:
a base;
a tilt/swivel module;
a first attachment means for attaching the base to the tilt/swivel module such that the tilt/swivel module is rotatable and tiltable with respect to the base;
a display module for housing a CRT; and
a second attachment means for attaching the display module to the tilt/swivel module such that the tilt/swivel module and the display module will rotate and tilt together when either is moved, the second attachment means including a plurality of cylindrical protrusions formed on a top of the tilt/swivel module, and a plurality of ring shape protrusions on the bottom of the display module, each sized and shaped to hole one of the plurality of cylindrical protrusions, and each positioned to correspond to a respective cylindrical protrusion.

5,587,877

COMPUTER ORGANIZER ENCLOSURE AND METHOD

Thomas P. Ryan, and Glen A. Stelzer, both of Schiller Park, Ill., assignors to Amco Engineering Co., Schiller Park, Ill.


Filed Oct. 26, 1994, Ser. No. 329,462

Int. Cl.⁶ H05K 7/14

U.S. Cl. 361—683

19 Claims

1. A computer organizer for auxiliary storage device enclosure comprising, in combination,
a U-shaped chassis having parallel sidewalls, a chassis base portion perpendicular to the sidewalls,



a spacer comprising a flat imperforate member with means for spacing the same from the chassis base in parallel relationship to the base and overlying substantially all of the chassis base thereby defining an encapsulating chamber therebetween, an enclosure access frame spanning the forward portion of the chassis and secured to the chassis and having an opening therein to communicate with said auxiliary storage devices, housings for the auxiliary storage devices, means for removably securing said housings to the enclosure access frame and to the spacer, each such removable auxiliary storage device housing having parallel longitudinal support means for removably securing an auxiliary device therein with the insert portion of the device facing the opening in the access frame, means for mounting a circuit assembly behind of the devices and to the spacer, a patch panel, an interface panel proportioned to span the space between the rear side walls of the chassis and secured thereto and to the bottom of the chassis in electronic communication with the patch panel, said interface panel having apertures therein, at least one of which is proportioned to removably engage a power supply, an access panel hingedly secured to the lower forward portion of the base of the chassis and proportioned to overlie the enclosure frame and hinge to said chassis, and a cover for removable securement atop the rectangular area bounded by the sidewalls of the chassis, the forward enclosure frame, and the interface panel.

5,587,878

ANTI-THEFT MECHANISM IN A COMPUTER SYSTEM HAVING REMOVABLE MODULES

Philip Tsai, Taipei; Chun-Yen Hung, Chung-Ho, and Feng-Shiung Wu, Taipei, all of Taiwan, assignors to Acer Incorporated, Taipei, Taiwan


Filed Feb. 15, 1995, Ser. No. 388,691

Int. Cl.⁶ G06F 1/16

U.S. Cl. 361—683

9 Claims

1. A module for sliding insertion along a first axis into a slot on a computer, the module comprising:
a portion formed with a through-hole extending along a second axis perpendicular to the first axis;
an elongate element movable along said second axis in said through-hole between a first position where said element is confined within said module and a second position where said element protrudes outside said module; and



a detent mechanism for maintaining said element in either of said first and second positions.

5,587,879


MOUNTING ARRANGEMENT FOR COMPUTER HARDWARE COMPONENTS AND METHOD

Joseph M. Spano, North Reading; Robert S. Antonuccio, Burlington, and James M. Carney, Pepperel, all of Mass., assignors to Sun Microsystems, Inc., Mountain View, Calif.
Continuation-in-part of Ser. No. 187,991, Jan. 28, 1994, Pat. No. 5,481,431. This application Mar. 28, 1994, Ser. No. 218,500

Int. Cl.⁶ H05K 5/00; 7/00

U.S. Cl. 361—685

9 Claims



1. A mounting arrangement for a computer having a drive unit or the like, comprising:
a chassis having an area for receiving said drive unit, said area including a support member for said drive unit, said support member having an opening having a compressing surface, said drive unit including a mounting and holding member, said mounting member including a yieldable portion being constructed and arranged to be received in said opening and placed in contact with said compressing surface in a manner to compress said yieldable portion of said mounting member an amount to create a holding force sufficient to secure said drive unit to said support member, said support member of said area comprising a platform and spaced walls projecting outwardly from said platform, said opening formed in each of said walls, a said mounting member for each opening, each said mounting member comprising a grommet formed of a copolyester elastomer, said support member comprises two said walls, said walls connected to said platform in a manner to extend generally perpendicularly therefrom and having an opposed spaced apart relationship to each other sufficient to permit said drive unit to be received between said opposed walls for connection thereto, each said walls having two longitudinally spaced apart said openings arranged to form opposed cooperative pairs of openings,

said drive unit having two opposed sides arranged generally parallel to said walls, each said side of said drive unit having mounted thereon two spaced apart said grommets constructed and arranged so that associated portions thereof are received in a different one of said openings of said walls, said walls and openings being constructed and arranged to permit said drive unit to be at least substantially received within the confines of said walls, each said portion of an associated grommet arranged to project outwardly from said sides of said drive unit and adapted to be secured to said sides of said walls, each said opening is formed with a first and second extending portion, each said portion of said opening being arranged so that a said portion of an associated grommet is received first by said first portion of an associated said opening and then by said second portion thereof, each said first portion having an area arranged to allow a said portion of an associated grommet to pass freely through said first portion, each said second portion being arranged generally perpendicularly to an associated first portion and having a front part and a back part, each said front part having a reduced open area forming an associated said compressing surface to compress a said portion of an associated grommet to create said holding force of a said portion of an associated grommet, each said back part being enlarged relative to an associated front part for receiving a said portion of an associated grommet after passing through an associated front part, the enlargement being such that said compressed said portion of an associated grommet after passing through an associated front part will possess said holding force with said chassis, each said grommet being cylindrical in shape in which an associated portion thereof is arranged adjacent to an associated side of said drive unit and a second portion thereof is spaced from an associated said side, each said spaced portion of said grommets having a larger diameter than an associated adjacent portion thereof, and each said grommet being constructed and arranged relative to an associated opening to place an associated adjacent portion in an associated opening.

5,587,880

COMPUTER COOLING SYSTEM OPERABLE UNDER THE FORCE OF GRAVITY IN FIRST ORIENTATION AND AGAINST THE FORCE OF GRAVITY IN SECOND ORIENTATION


Richard J. Phillips, Alachua, Fla., and Ralph I. Larson, Bolton, Mass., assignors to Aavid Laboratories, Inc., South Lancaster, Mass.

Filed Jun. 28, 1995, Ser. No. 495,961

Int. Cl.⁶ H05K 7/20; F28D 15/02

U.S. Cl. 361—687

20 Claims



18. Computer apparatus capable of operating in a first orientation and in a second orientation in an environment with an ambient pressure over a temperature range, the apparatus comprising:
a heat dissipating microprocessor;
a memory unit;
an evaporator unit having a first thermally conductive wall in contact with the microprocessor;

a condenser unit located vertically above the evaporator unit in the first orientation and vertically below the evaporator unit in the second orientation;
a first conduit connecting the evaporator unit and the condenser unit;
a second conduit connecting the condenser unit to the evaporator unit to form a hermetic enclosure with an interior and an internal pressure, the condenser unit having at least one wall which is sufficiently flexible that the internal pressure remains substantially at the ambient pressure over the entire temperature range;
a liquid coolant disposed within the hermetic enclosure interior, the liquid coolant having a sufficiently low boiling point that the liquid coolant is changed to a vapor by the heat dissipated from the microprocessor; and
a heater operative only in the second orientation for heating a portion of the first conduit sufficiently to cause bubbles of coolant vapor to form and rise in the first conduit.

5,587,881

POWER SUPPLY CHASSIS FOR PERSONAL COMPUTERS


Joseph Wang, No. 18-3, Lane 197, Fuehr St., Keelung, Taiwan

Filed Dec. 27, 1995, Ser. No. 579,308

Int. Cl.⁶ H05K 7/20

U.S. Cl. 361—695

7 Claims



1. A power supply chassis for personal computers comprising:
a bottom plate;
a first wall plate defining a rail horizontally extending therealong at a mediate height thereof;
a second wall plate adjacent to the first wall plate;
a top plate supported by the first and the second wall plates; and
a wall frame coupled with the bottom plate, the second wall plate, and the top plate for defining a channel and having a plate defining a fan-frame vent, a guide facing the rail on the first wall plate as to divide the channel into a first compartment and a second compartment each slidably receiving a corresponding power supply cartridge, a fan fixedly secured within the frame in a direction of facing the fan-frame vent for expelling out of the chassis heat generated by the power supply cartridges out of the chassis, a first socket and a second socket on the second wall plate each respectively coupling with a corresponding power supply cartridge, and a power receptacle provided adjacent to an entrance of the channel for receiving a power cable.

5,587,882

THERMAL INTERFACE FOR A HEAT SINK AND A PLURALITY OF INTEGRATED CIRCUITS MOUNTED ON A SUBSTRATE

Chandrakant Patel, Fremont, Calif., assignor to Hewlett-Packard Company, Palo Alto, Calif.


Filed Aug. 30, 1995, Ser. No. 521,480

Int. Cl.⁶ H05K 7/20

U.S. Cl. 361—705

11 Claims

1. A module assembly, comprising:



a planar substrate having a top surface, the top surface having a non-through peripheral trough;
at least one heat generating device mounted on the top surface of the substrate;
a heat sink having a support ring penetrating the trough;
a thermal transfer medium having a predetermined thickness, positioned between the at least one heat generating device and the heat sink, operative to conduct heat from the at least one heat generating device to the heat sink; and
a curable adhesive within the trough, securing the support ring to the substrate wherein the depth of penetration of the support ring into the trough positions the thermal transfer medium in contact with the heat sink and the at least one heat generating device.

5,587,883


LEAD FRAME ASSEMBLY FOR SURFACE MOUNT INTEGRATED CIRCUIT POWER PACKAGE

Timothy L. Olson, Phoenix; Lauriann T. Carney, Gilbert; Gary C. Johnson, Tempe, and William M. Strom, Chandler, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.
Continuation of Ser. No. 376,636, Jan. 23, 1995, abandoned, which is a continuation of Ser. No. 215,000, Mar. 18, 1994, abandoned, which is a continuation of Ser. No. 985,055, Dec. 3, 1992, abandoned. This application Nov. 13, 1995, Ser. No. 557,667

Int. Cl.⁶ H05K 7/20

U.S. Cl. 361-723

9 Claims



7. A lead frame assembly for use in a semiconductor package comprising:

- a lead frame comprising:
 - a first region in a first plane including a plurality of separated lead members;
 - a transition region contiguous with said first region;
 - a second region in a second plane contiguous with said transition region wherein said first and second planes are separated by a predetermined distance, said transition region creating said predetermined distance between said first and second regions of the lead frame, wherein a slot extends through said second region and said transition region into said first region;
- a heat sink having a first surface and a second surface, said first surface providing an area for centrally mounting a semiconductor die wherein said heat sink includes a pair of arm like extensions each having a raised area and a stud formed thereon and wherein said lead frame includes a pair of arm

extensions corresponding to said arm like extensions of said heat sink, said pair of arm extensions each having an opening formed therein receiving said studs, said studs being staked for holding said lead frame to said heat sink.

5,587,884

ELECTRICAL CONNECTOR JACK WITH ENCAPSULATED SIGNAL CONDITIONING COMPONENTS


Venkat A. Raman, Hershey, Pa., assignor to The Whitaker Corporation, Wilmington, Del.

Filed Feb. 6, 1995, Ser. No. 384,086

Int. Cl.⁶ H01R 13/66

U.S. Cl. 361-728

1 Claim



1. A modular jack assembly for use in conditioning signals carried by wires comprising:
 - a housing including a cavity for receiving a modular plug;
 - an insert subassembly further comprising:
 - a plurality of contact terminals, the insert subassembly being insertable into the housing such that the contact terminals extend into the cavity and are positioned for engaging the modular plug;
 - a plurality of leads;
 - at least one signal conditioning component connected to corresponding leads and contact terminals, and
 - an insert molded body matable with the housing, the insert molded body positioning the leads for attachment to external circuits and the insert molded body encapsulating the signal conditioning components wherein the housing includes a open ended channel at the rear thereof in which the insert molded body is partially received, the insert molded body protruding from the channel at the rear of the housing.

5,587,885

MECHANICAL PRINTED CIRCUIT BOARD/LAMINATED MULTI CHIP MODULE INTERCONNECT APPARATUS

N. Deepak Swamy, Austin, Tex., assignor to Dell USA, L.P., Austin, Tex.


Continuation-in-part of Ser. No. 245,410, May 18, 1994, Pat. No. 5,400,220. This application Jul. 15, 1994, Ser. No. 275,854

Int. Cl.⁶ H05K 7/02

U.S. Cl. 361-777

8 Claims

1. Circuit board apparatus comprising:
 - a circuit board substrate structure having first and second opposite sides, said circuit board substrate structure having a spaced series of first vias extending transversely therethrough between said first and second opposite sides, and further having a spaced series of socket areas offset from said spaced series of first vias and extending only partially through said circuit board substrate structure from said first side thereof;
 - a first metallic coating deposited on the interiors of said first vias and said socket areas and around their open ends on said first side of said circuit board substrate structure, portions of said first metallic coating being extended across said first side between associated first via/socket area pairs to electrically



- couple them, said first metallic coating having, in said socket areas, a gold outer layer;
- an electronic component having a substrate portion with first and second opposite sides, said electronic component substrate portion having a spaced series of second vias extending transversely therethrough between its opposite first and second sides, and a second metallic coating deposited on the interiors of said second vias and having exterior portions extending outwardly from open ends of said second vias along said first side of said electronic component substrate portion;
- a spaced series of externally disposed, generally ball-shaped metallic lead portions formed on said exterior portions of said second metallic coating and having gold outer layers, said lead portions being partially received in and releasably engaging said second metallic coating on said socket areas; and
- holding means for exerting a resilient force on said electronic component in a manner releasably holding said lead portions in engagement with said second metallic coating on their associated socket areas.

5,587,886

STRUCTURE FOR CONTACT POINTS OF A SHIFT SWITCH USED IN A COMPUTER


Si-Chi Lan, Taipei, Taiwan, assignor to Kinpo Electronics, Taipei, Taiwan

Filed May 4, 1995, Ser. No. 434,507

Int. Cl.⁶ H01H 1/20; 1/44; 1/10; H05K 7/02

U.S. Cl. 361-781

1 Claim



1. A structure for contact points of a shift switch used in a computer comprising:
 - an elastic contact plate disposed under the shift switch and having a plurality of projecting contact points at a lower end thereof to contact the corresponding conductive contact por-

tions of a circuit board, said contact portions are arranged on said circuit board in a series along a shifting direction of said shift switch, with a slot that is inclined along the direction of travel of said shift switch, said slots being formed between each pair of adjacent contact portions to separate said contact portions from each other.

5,587,887

PRINTED CIRCUIT BOARD HAVING A CONFIGURABLE VOLTAGE SUPPLY


Noah M. Price, Campbell; Duane M. P. Takahashi, San Jose, and David C. Buuck, Santa Clara, all of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Filed May 1, 1995, Ser. No. 432,227

Int. Cl.⁶ H05K 1/11

U.S. Cl. 361-794

16 Claims



1. A printed circuit board for connecting and holding devices in a plurality of circuit designs, comprising:
 - at least one conductive layer of material comprising a plurality of electrically isolated voltage supply plane regions including a set of fixed voltage supply plane regions each being fixedly connectable to an associated power supply voltage and at least one undefined voltage supply plane region which is not directly connectable to a power supply voltage; and
 - a plurality of configurations of at least one insertable electrically conductive connector for coupling said set of fixed voltage supply plane regions to said undefined voltage supply plane region to accommodate said plurality of circuit designs.

5,587,888

EXTRACTING DEVICE FOR PLUG-IN MODULES

Michael Joist, Gaggenu, Germany, assignor to Schroff GmbH, Straubenhardt, Germany


Filed Jan. 11, 1996, Ser. No. 584,358

Claims priority, application Germany, Jan. 23, 1995, 195 01 898.2

Int. Cl.⁶ H05K 7/14

U.S. Cl. 361-802

3 Claims



1. An extracting device for plug-in modules which are intended to be inserted into module racks, the device comprising a holding bracket for detachably securing a front plate as well as a printed circuit board on a profile rail of the module rack; a pivoted lever

which is seated on the holding bracket by at least one swing pin, the latter being slidable in a slot of said holding bracket, said swing pin having a pressing shoulder on the pivoted lever, which shoulder is opposite of a front face of the profile rail when the plug-in module is inserted; said pivoted lever being displaceable with respect to the holding bracket by way of a sliding mechanism which comprises a sliding pin arranged on said holding bracket and a sliding track arranged on said pivoted lever, said sliding track having a concave curvature with respect to said swing pin.

5,587,889


EDGE CONNECTOR FOR SECURING A MOUNTABLE ELECTRONIC COMPONENT TO A DEVICE WITH RECEIVING APERTURES FOR EDGE CONNECTOR

Jim Sacherman, 446 Ruthven, Palo Alto, Calif. 94301
Filed May 17, 1994, Ser. No. 243,967

Int. Cl.⁶ H05K 7/14

U.S. Cl. 361—809

6 Claims



1. An apparatus for rack mounting a peripheral electronic component to an electronic system, said apparatus comprising:
 - a. a primary rail means coupled to said electronic system;
 - b. an independent rail means designed to attach to said primary rail means; and
 - c. a screwless clamping means for coupling said independent rail to said peripheral electronic component comprising of:
 - an elongated arch having a convex surface and a concave surface, said arch further having an engaged state and a disengaged state, said arch being in the engaged state when the convex surface is depressed, said arch being in the disengaged state when the convex surface is not depressed; and
 - two legs for clamping an object placed therebetween, each of said legs being placed at an opposite end of the concave surface and angled inward of said arch, said two legs only clamping when said arch is in the disengaged state.

5,587,890

VEHICLE ELECTRIC POWER DISTRIBUTION SYSTEM

Lawrence R. Happ, Mundelein; Jacek Korczynski, Niles; William R. Bailey, Glen Ellyn, all of Ill., and Alan Lesesky, Charlotte, N.C., assignors to Cooper Industries, Inc., Houston, Tex.


Filed Aug. 8, 1994, Ser. No. 287,623

Int. Cl.⁶ H02B 1/20

U.S. Cl. 361—826

29 Claims

1. A vehicle electric power distribution apparatus comprising:
 - a plurality of vertically stacked conductive circuit layers, each layer including a rectangular array of contact pads, each of the conductive circuit layers is at least partially coated with an electrically insulating plastic material, and at least some of the contact pads are electrically connected to selected other contact pads of the same conductive circuit layer via integrally formed conductive traces; and



a plurality of conductive pins providing electrical contact between selected contact pads of different selected conductive circuit layers.

5,587,891

ELECTRIC POWER CONVERTING APPARATUS

Kiyoshi Nakata, Nishibaraki-Gun; Tokunosuke Tanamachi; Kiyoshi Nakamura, both of Katsuta; Mutsuhiro Terunuma, Mito; Masato Suzuki, Naka-Gun; Yoshio Tsutsui, Katsuta; Eiichi Toyota, Katsuta, and Kouji Yasuda, Katsuta, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of Ser. No. 190,126, Feb. 3, 1994, Pat. No.


5,467,262. This application Jun. 7, 1995, Ser. No. 479,030

Claims priority, application Japan, Jun. 4, 1992, 4-143947

Int. Cl.⁶ H02M 7/5387

U.S. Cl. 363—41

1 Claim



1. An electric power converting apparatus for converting a DC voltage into AC phase voltages having 3-level potentials, for driving an AC motor, said electric power converting apparatus comprising:

first means for receiving the DC voltage and producing therefrom an AC voltage in a unipolar modulation mode, to produce a series of output pulses such that each half period of the fundamental wave of an output AC voltage of said electric power converting apparatus is represented by a series of single polarity pulses;

second means for receiving the DC voltage and producing therefrom an AC voltage in an overmodulation mode, to produce a series of output pulses such that each half period of the fundamental wave of the output AC voltage of said electric power converting apparatus is represented by a series of single polarity pulses filled up in the center by a plurality of pulses of the single polarity;

third means for receiving the DC voltage and producing therefrom an AC voltage in a 1-pulse mode, to produce an output pulse such that a half period of the fundamental wave of the

output AC voltage of said electric power converting apparatus is represented by a single pulse having the same polarity as said half period; and

output means for switching among said first, second, and third, means to change the modulation mode among the unipolar modulation mode, the overmodulation mode, and the 1-pulse mode.

5,587,892

MULTI-PHASE POWER CONVERTER WITH HARMONIC NEUTRALIZATION


Alfred H. Barrett, Carmel, Ind., assignor to Delco Electronics Corp., Kokomo, Ind.

Filed Oct. 4, 1994, Ser. No. 317,457

Int. Cl.⁶ H02M 3/335

U.S. Cl. 363—44

16 Claims



1. A multi-phase AC to DC power converter comprising:
 - a plurality of inputs for respective phases of a multi-phase source of AC power,
 - a plurality of first rectifiers connected respectively to said inputs, each said first rectifier having an output,
 - load output terminals connected to said first rectifiers for delivering DC power to a load,
 - a multi-phase harmonic neutralizing converter comprising a power switching inverter having an input connected to the outputs of each of said first rectifiers, said inverter including LC resonant circuits and outputs associated with respective said first rectifiers,
 - said harmonic converter further comprising a plurality of second rectifiers having respective inputs connected to the respective outputs of said inverter through a plurality of respective transformers, each of said second rectifiers having an output connected in a voltage additive relationship to the output of the respective individual phase first rectifier, each respective added outputs of respective said first and second rectifiers connected to said load terminals.

5,587,893

VIDEO DISPLAY HIGH VOLTAGE GENERATOR

David Teng, Taipei, Taiwan, assignor to Chung-Chin Chen, Alexandria, Va.


Filed Jun. 16, 1995, Ser. No. 491,600

Int. Cl.⁶ H02M 7/19; H01J 29/70; H05G 1/12

U.S. Cl. 363—61

14 Claims

1. A high voltage generator for the anode of the cathode-ray tube of a video display, comprising:
 - a pair of cores;
 - a primary coil isolatedly wound on the center poles of the cores, having one terminal connected with the D.C. power supply of an electric circuit of the video display and the other terminal connected with a square wave generator of the video display via a horizontal switch of the electric circuit, said horizontal switch being periodically switched by a square-wave from the square wave generator;



a high voltage coil wound on the primary coil, having one terminal connected with ground and the other terminal connected with a multiplier;

a multiplier, comprising a plurality of metallized foil high voltage stepup capacitors and high voltage rectifiers, said foil high voltage stepup capacitors of the multiplier being wound on the high voltage coil, said multiplier having one terminal connected with the high voltage coil and the other terminal supplying the generated high voltage to the anode of the cathode-ray tube of the video display, the rectifiers therein being used to connect the foil stepup capacitors of the multiplier for stepping up the high voltage coil output to a required high voltage;

cores run through the center hole of the primary coil, and containing the components therein to form a magnetic path.

5,587,894

POWER SOURCE DEVICE

Masahiro Naruo, Shijonawate, Japan, assignor to Matsushita Electric Works, Ltd., Osaka, Japan


Filed Mar. 28, 1995, Ser. No. 412,540

Claims priority, application Japan, Mar. 28, 1994, 6-057868

Int. Cl.⁶ H02M 5/42; 7/04

U.S. Cl. 363—84

19 Claims



1. A power source device comprising:
 - a power source,
 - a first energy storing means connected through a first switching element in parallel to said power source,
 - a load circuit including a parallel connection of a voltage stabilizing means and a load and connected through a second switching element to said first energy storing means,
 - means connected to said first and second switching elements for controlling their ON/OFF operation, and
 - a voltage control means including a second energy storing means and a plurality of further switching elements and controlling an output voltage to said load circuit with switching operation of said further switching elements.

a frame sync signal located at a particular point in the frame, the optical recording medium comprising:

- a recording track extending in a track direction;
- a recordable region for magneto-optically recording the main information on the recording track along the track direction; and
- wherein for each recorded frame of main information, frame sync signals having the same signal format as that of the frame sync signals for the main information data are previously recorded by offsetting the recording track in a direction perpendicular to the track direction.

5,587,902

TRANSLATING SYSTEM FOR PROCESSING TEXT WITH MARKUP SIGNS

Shuzo Kugimiya, Nara, Japan, assignor to Sharp Kabushiki Kaisha, Osaka-fu, Japan


Filed May 26, 1993, Ser. No. 67,143

Claims priority, application Japan, May 26, 1992, 4-133552; May 7, 1993, 5-106405

Int. Cl.⁶ G06F 15/38

U.S. Cl. 395-752

10 Claims



1. A translating machine for translating an original text in a first language including one or a plurality of predetermined markup signs into a translated text in a second language, comprising:

- means for associating each of said one or a plurality of predetermined markup signs with words within the original text;
- separation means for separating the original text into markup signs and a text body exclusive of the markup signs;
- storage means for storing each markup sign with each word to which each said markup sign is associated;
- means for producing a parsing tree in the second language from said text body; and
- means for producing, in communication with said means for producing a parsing tree and said storage means, the translated text from said parsing tree and attaching a markup sign to each word within the translated text equivalent to each of said one or a plurality of markup signs associated with each word within the original text.

5,587,903

ARTIFICIAL INTELLIGENCE LANGUAGE PROGRAM

Thomas W. Yale, c/o Yale Laboratories, Inc. 9, White Oak Rd., Springfield, Ill. 62707

Filed Jun. 22, 1994, Ser. No. 264,071


Int. Cl.⁶ G06F 17/27; 17/00

U.S. Cl. 395-759

14 Claims

1. A method for translating a sentence entered by a user into machine recognizable thought patterns, said method comprising:

- receiving the sentence entered by the user;
- translating the user's sentence to a universal language;
- parsing the translated sentence;
- deriving propositions from the parsed translated sentence of the user;



sequentially storing the derived propositions into a knowledge database; and

- generating a set of peripheral database linkages for the sets of derived propositions representing the user's sentence, wherein each peripheral database linkage includes a peripheral database representing a function of speech selectively linked to one or more of the other peripheral databases and the knowledge database.

5,587,904

AIR COMBAT MONITORING SYSTEM AND METHODS AND APPARATUS USEFUL THEREFOR

Igal Ben-Yair, Tel Aviv; Haim Berger, Ganei Tikva, and Oleg Perelmuter, Rishon LeZion, all of Israel, assignors to Israel Aircraft Industries, Ltd., Lod, Israel


Filed Jun. 10, 1994, Ser. No. 258,973

Claims priority, application Israel, Jun. 11, 1993, 105991

Int. Cl.⁶ G09B 9/08; 9/16

U.S. Cl. 364-449.7

16 Claims



1. An air combat monitoring system comprising:

- a plurality of GPS receivers, mountable on a corresponding plurality of aircraft;
- an avionics monitor mountable on each of the corresponding plurality of aircraft for monitoring the avionics systems of the aircraft;
- a memory for storing information received from the GPS receivers indicating the location of the plurality of aircraft and information received from the avionics monitor in order to provide a reviewable output indication of the performance of the plurality of aircraft;
- an information disseminator for communicating said information among said plurality of aircraft including
- means employing GPS signals for synchronization of aircraft mounted apparatus on the plurality of aircraft; and

means employing time division multiplexing for communicating said information among the plurality of aircraft.

5,587,905

TRANSMISSION AND ENGINE OVERSPEED CONTROL


Leon P. Yesel, East Peoria, and John P. Kitzerow, Metamora, both of Ill., assignors to Caterpillar Inc., Peoria, Ill.

Filed Jul. 15, 1994, Ser. No. 275,861

Int. Cl.⁶ B60K 41/08

U.S. Cl. 364-424.082

15 Claims



1. A method for controlling overspeed conditions of an electronically controlled transmission and engine, said transmission having an output shaft and being electronically shiftable by an electronic shift control module between forward and reverse gears to rotate said output shaft in forward and reverse directions and a neutral gear without shaft rotation, said transmission having an operator controlled shift lever for requesting a gear from said forward, neutral and reverse gears, said transmission operating in a present gear from among said forward, reverse and neutral gears; said method comprising the steps of:

- determining forced downshift shift points and storing said forced downshift shift points in a memory portion of said electronic shift control module;
- determining overspeed downshift shift points and storing said overspeed downshift shift points in a memory portion of said electronic shift control module;
- determining overspeed upshift shift points and storing said overspeed upshift shift points in a memory portion of said electronic shift control module;
- determining a directional shift inhibit speed and storing said directional shift inhibit speed in a memory portion of said electronic shift control module;
- determining overspeed values for each gear based on engine speed and transmission output shaft speed and storing said overspeed value for each gear in a memory portion of said electronic shift control module;
- monitoring engine speed;
- monitoring speed of said output shaft;
- determining whether said shift lever is operated to request a gear from said forward, reverse and neutral gears;
- downshifting said transmission to lowest possible gear using said forced downshift shift points and sequentially changing gears until the requested gear is reached when said requested gear is a lower gear than said present gear and said requested gear is newly requested, and setting a forced downshift timer for a first preselected time duration and preventing said transmission shaft output speed from exceeding the overspeed value for more than said first preselected time duration;

temporarily upshifting said transmission, using said overspeed upshift shift points, when said transmission shaft output speed exceeds speed for present gear for more than a second preselected time set by an overspeed downshift timer then downshifting to said requested gear using said overspeed downshift shift points;

downshifting said transmission to lowest possible gear in requested direction of travel, using said forced downshift shift points, in response to a change of direction request when said transmission shaft output speed is above the overspeed value for said requested gear but not above the directional shift inhibit speed; and

downshifting transmission to lowest possible gear in present direction of travel, using said forced downshift shift points, in response to a change of direction request when said transmission shaft output speed exceeds direction shift inhibit speed.

5,587,906

METHOD AND APPARATUS FOR SENSING A VEHICLE CRASH CONDITION USING VELOCITY ENHANCED ACCELERATION CRASH METRICS


George W. McIver, Redondo Beach; Mark A. Carlin, Hermosa Beach, both of Calif.; James E. Bormann, LaPorte, Ind.; Ronald A. Muckley, Milford, and Roger A. McCurdy, Troy, both of Mich., assignors to TRW Inc., Lyndhurst, Ohio

Filed Jun. 13, 1994, Ser. No. 258,952

Int. Cl.⁶ B60R 21/32

U.S. Cl. 364-424.045

19 Claims



1. An apparatus for sensing a vehicle crash condition comprising:

- acceleration sensing means for sensing a vehicle crash condition and for providing a crash acceleration signal having a characteristic indicative of the vehicle crash condition;
- crash velocity determining means connected to said acceleration sensing means for determining a crash velocity value from said crash acceleration signal;
- crash metric determining means connected to said acceleration sensing means for determining a crash metric value functionally related to said acceleration signal;
- threshold determining means for determining a velocity based threshold value functionally related to said determined crash velocity value, said velocity based threshold value varying as a function of said determined crash velocity value;
- comparing means for comparing said determined crash metric value against said velocity based threshold value and for providing a signal indicative of the comparison; and
- control signal means for providing a control signal in response to said comparing means when said determined crash metric exceeds said velocity based threshold value.

5,587,907

VEHICLE SUSPENSION APPARATUS CAPABLE OF PREVENTING GENERATION OF TRANSITIONAL VARIATION IN ROLLING MOVEMENT

Mineharu Shibata, Ohtake, and Shin Takehara, Higashihiroshima, both of Japan, assignors to Naldec Corporation, and Mazda Motor Corporation, both of Hiroshima, Japan. Continuation of Ser. No. 90,255, Jul. 13, 1993, abandoned.


This application Jun. 30, 1995, Ser. No. 497,702

Claims priority, application Japan, Jul. 14, 1992, 4-186605

Int. Cl.⁶ B60G 17/015

U.S. Cl. 364-424.046

10 Claims



1. A suspension apparatus for a vehicle capable of changing a characteristic of suspension by controlling a resistance force generated by hydraulic cylinders which are respectively provided between a vehicle body and each wheel of the vehicle, comprising: a plurality of vehicle-height sensors detecting vehicle height signals at a plurality of positions; extraction means for extracting a bouncing component signal and a rolling component signal from the vehicle-height signals detected by the plurality of vehicle-height sensors; low pass filtering means for passing a low frequency component each of the bouncing component signal and the rolling component signal; and control means for controlling a resistance force of each hydraulic cylinder against a relative displacement of the vehicle body with respect to the wheel based on output signals from said low-pass filtering means, wherein a cut-off frequency for the low frequency component of the rolling component signal set in the low-pass filtering means is set higher than a cut-off frequency for the low frequency component of the bouncing component signal.

5,587,908

DISTANCE MEASUREMENT DEVICE AND VEHICLE VELOCITY CONTROL DEVICE FOR MAINTAINING INTER-VEHICULAR DISTANCE

Yasuya Kajiwaru, Himeji, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Nov. 5, 1993, Ser. No. 147,320

Claims priority, application Japan, Dec. 22, 1992, 4-342415

Int. Cl.⁶ B60K 31/04

U.S. Cl. 364-426.041

19 Claims



6. A vehicle velocity control device for maintaining an inter-vehicular distance, comprising:

distance measurement means mounted on a vehicle for measuring a distance to another vehicle and outputting measurement values at a predetermined sampling period; a weighting means operable to adjust each of said measurement values by weighting each of said measurement values and a previously adjusted measurement value to obtain a currently adjusted distance value; selecting means for selecting a weighting constant of said weighting means from a plurality of weighting constants depending upon a current measurement value output from said distance measurement means; wherein said weighting means uses said selected weighting constant to adjust the currently measured value to thereby provide said currently adjusted distance value; deviation detection means, coupled to said distance measurement means, for calculating a deviation of said currently adjusted distance value from a target inter-vehicle distance; calculation means, coupled to said deviation detection means, for calculating a parameter corresponding to said deviation; and vehicle velocity control means, coupled to said calculation means, for controlling a vehicle velocity of said vehicle on the basis of said parameter, such that said distance to said another vehicle is maintained at said target inter-vehicle distance.

5,587,909

MISFIRE DETECTING METHOD

Takuya Matsumoto, Toru Hashimoto, Koichi Namiki, Yasuhisa Yoshida, and Satoshi Kasai, all of Tokyo, Japan, assignors to Mitsubishi Jidosha Kogyo Kabushiki Kaisha, Tokyo, Japan

PCT No. PCT/JP93/00764, § 371 Date Nov. 18, 1993, § 102(e) Date Jan. 18, 1994, PCT Pub. No. WO93/25809, PCT Pub. Date Dec. 23, 1993


PCT Filed Jun. 8, 1993, Ser. No. 150,063

Claims priority, application Japan, Jun. 16, 1992, 4-156976; Feb. 17, 1993, 5-028216

Int. Cl.⁶ G01M 15/00

U.S. Cl. 364-431.08

16 Claims



1. A misfire detecting method in which misfire detection is carried out based on a variation in rotating condition of an output shaft of an internal combustion engine, comprising: (a) determining a variation of rotation of said output shaft by determining whether a rotation of said output shaft has varied toward a higher-speed side immediately after said rotation of said output shaft has varied toward a lower-speed side; (b) provisionally determining that a misfire is occurring when said detected variation of rotation below said predetermined misfire discrimination value; (c) initiating a timer to count a predetermined rough-road judgment after said misfire has been provisionally determined; (d) determining that said vehicle is running on a rough road when said variation in rotation becomes greater than a predetermined rough-road discrimination value before said predetermined rough-road judgment time elapses; and

5,587,911

NAVIGATION SYSTEM WITH SELECTIVE INTERSECTION DISPLAY

Hitoshi Asano, Nagoya; Wataru Ishikawa, and Mitsuhiro Nimura, both of Okazaki, all of Japan, assignors to Aisin AW Co., Ltd., Japan

Continuation of Ser. No. 280,677, Jul. 27, 1994, abandoned.


This application Dec. 1, 1995, Ser. No. 566,451

Claims priority, application Japan, Jul. 27, 1993, 5-204576

Int. Cl.⁶ G06F 16/500

U.S. Cl. 364-444.2

18 Claims



1. A navigation system for guiding a vehicle to a destination in accordance with a searched route composed of a series of interconnecting roads and intersections, comprising: external memory means for storing at least road data and intersection data including (1) text information including names of roads and identifying data for identifying intersections and (2) coordinate data for the intersections; a video display for being viewed by a vehicle operator; present position detecting means for detecting the present position of the vehicle; input means for inputting the destination; route searching means for determining a route from the detected present position to the input destination, by searching the data stored in said external memory means; route storing means for retrieving, from said external memory means, text information for the route determined by said route searching means and for storing said retrieved text information as route text information; control means for retrieving the route text information from said route storing means and for listing items of said route text information, including at least the road names and plural identified intersections, in geographical sequence; first picture means for picturing a route information screen on said video display to display the listed items of said text information; intersection selecting means for selecting any one of the plural, identified intersections listed on the route information screen; and second picture means for retrieving the coordinate data for the selected intersection from said external memory means and for providing a map display screen on said video display to show a map including the position of selected intersection.

5,587,912

COMPUTER AIDED PROCESSING OF THREE-DIMENSIONAL OBJECT AND APPARATUS THEREFOR

Matts Andersson, Lerum, and Anders Törnquist, Gothenburg, both of Sweden, assignors to Nobelpharma AB, Gothenburg, Sweden

Filed Jul. 7, 1994, Ser. No. 271,457

Claims priority, application Sweden, Jul. 12, 1993, 93 02399

Int. Cl.⁶ G05F 19/00

U.S. Cl. 364-468.04

15 Claims

1. A method of generating data for manufacturing a three-dimensional body using a program with computer aided design, comprising:

(e) invalidating said provisionally determined misfire when it is detected in said step (d) that said vehicle is running on said rough road.

5,587,910

VEHICLE NAVIGATION SYSTEM WITH NON-OVERFLOW DIGITAL FILTER


Jeffrey P. Woodard, Irvine, Calif., assignor to Rockwell International Corporation, Seal Beach, Calif.

Filed Feb. 6, 1995, Ser. No. 384,084

Int. Cl.⁶ G06F 17/00

U.S. Cl. 364-443

2 Claims




1. A vehicle navigational system, comprising:

- (a) a vehicle;
- (b) a sensor mounted on the vehicle and producing a navigation signal;
- (c) a one-multiplier Gray-Markel filter having an input connected to receive the navigational signal, and having at least one stage, each stage comprising:
 - (1) a first summer connected to receive, at a plus input, a first input to the stage;
 - (2) a multiplier connected to multiply an output of the first summer by a constant k;
 - (3) a second summer connected to receive:
 - (A) at a plus input, the first input to the stage; and
 - (B) at a variable input, an output of the multiplier, the variable input being:
 - (1) a minus input if k is greater than 0; and
 - (2) a plus input if k is less than 0;

wherein an output of the second summer is a first output of the stage;

- (4) a delay element connected to:
 - (A) receive a second input to the stage; and
 - (B) apply an output to a complement input of the first summer, the complement input being the negative of the variable input; and
- (5) a third summer connected to receive:
 - (A) at a first plus input, the output of the multiplier; and
 - (B) at a second plus input, the output of the delay element; and
- (d) a filtered navigation signal display driven by an output of the one-multiplier Gray-Markel filter.



generating input data for a computer, said data representing a three-dimensional body model;
storing said input data in said computer;
responsive to activation of an input device, generating through said computer program first signals for forming, based on said input data, a plurality of surfaces representing said three-dimensional body model, wherein each surface comprises a contour of a vertical section extending through a central axis of said three-dimensional body model;
responsive to activation of said input device, generating through said computer program second signals for modifying contours of vertical sections in accordance with said desired three-dimensional body; and
responsive to activation of said input device, generating through said computer program third signals for storing output data which denotes modifications of said contours in response to said second signals, said output data being transmittable from said computer for manufacturing said three-dimensional body.

5,587,913 METHOD EMPLOYING SEQUENTIAL TWO-DIMENSIONAL GEOMETRY FOR PRODUCING SHELLS FOR FABRICATION BY A RAPID PROTOTYPING SYSTEM


Steven R. Abrams, New York; James U. Koren, Chappaqua; Vijay Srinivasan, Peekskill, and Konstantinos Tarabanis, Flushing, all of N.Y., assignors to Stratasys, Inc., Eden Prairie, Minn.

Continuation of Ser. No. 4,038, Jan. 15, 1993, abandoned.
This application Oct. 12, 1994, Ser. No. 322,401

Int. Cl.⁶ G06F 19/00; 17/50; 17/10

U.S. Cl. 364-468.26

10 Claims



1. A method for operating a system to fabricate a three dimensional object from a computer-generated specification of a solid S, the computer-generated specification of the solid S being oriented in an xyz-coordinate frame and having a height along the z-axis, comprising the steps of:

- preprocessing the computer-generated specification of S, the step of preprocessing including the steps of, for each face f_i lying on a boundary of the solid S, constructing a bounding z-axis interval $I_i = [z_{imin}, z_{imax}]$; for all i , constructing an enlarged interval $I_i' = [z_{imin} - t, z_{imax} + t]$, where t is a thickness of a shell of S; and

- storing the enlarged intervals I_i' for subsequent access;
- searching the stored enlarged intervals to determine a specification of one slice of the shell of S, including the steps of, initializing a set of primitive slices $\Pi = \text{NULL}$; and for each interval I_i' that contains a query point z_q that overlaps with a query interval I_q , adding $P \cap \{CL(f_i \oplus B_t)\}$ to Π , where P is a slice plane, CL indicates a closure, and B_t is an open ball of radius t ;
- merging the set of primitive slices by performing a union of all of the primitive slices in Π to obtain Σ ; and
- returning $(P \cap \Sigma) \cap S$ as the specification of one slice of the shell of S, including providing the specification of the one slice of the shell of S to a material deposition means for fabricating portion of the object in accordance with the specification of the one slice; and
- thereafter operating the system to deposit material by said material deposition means to fabricate a portion of the object in accordance with the specification of the one slice.

5,587,914 APPARATUS AND METHOD FOR COMPUTER-AIDED DESIGN OF SHEET METAL FABRICATED PARTS


Scott A. Conradson, Palo Alto; Lee A. Barford, Mountain View; William D. Fisher, San Jose; Michael J. Weinstein, Los Altos, and Julie D. Wilker, Mountain View, all of Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif.

Continuation of Ser. No. 883,243, May 7, 1992, abandoned, which is a continuation of Ser. No. 411,344, Sep. 22, 1989, abandoned. This application Mar. 17, 1995, Ser. No. 406,767

Int. Cl.⁶ G06F 15/00

U.S. Cl. 364-468.01

17 Claims



9. An interactive method of designing a mechanical part, the method comprising:
- sequentially receiving a plurality of items of data descriptive of a desired mechanical part;
 - storing a plurality of parameters descriptive of an available manufacturing apparatus, at least one of which describes a tooling constraint;
 - as each item of data is received, automatically testing whether the part as described by the received items of data satisfies each of a plurality of the parameters, including one of the tooling constraints;
 - communicating the results of the test such that if the part fails to satisfy any of the parameters any of the items of data can be modified; and
 - performing the test again after an item of data has been modified.

5,587,915 TOOL DAMAGE PREVENTION SYSTEM

Takashi Nagatomi, Minamitsuru-gun, Japan, assignor to Fanuc Ltd., Japan

PCT No. PCT/JP94/00668, § 371 Date Dec. 29, 1994, § 102(e) Date Dec. 29, 1994, PCT Pub. No. WO94/26465, PCT Pub. Date Nov. 24, 1994


PCT Filed Apr. 21, 1994, Ser. No. 360,780

Claims priority, application Japan, May 11, 1993, 5-109153; Jun. 10, 1993, 5-138293

Int. Cl.⁶ G05B 19/065

U.S. Cl. 364-474.19

4 Claims



1. A tool damage prevention system for preventing damage to a tool used in a numerically controlled machine tool, comprising:
- first disturbance torque estimating means for estimating a disturbance torque acting on a spindle for rotating the tool;
 - second disturbance torque estimating means for estimating a disturbance torque acting on a feed shaft for controlling feed of the tool;
 - comparing means for comparing a composite disturbance torque, obtained by combining the disturbance torques estimated by said first and second disturbance torque estimating means, with a preset reference torque; and
 - deceleration/stop command means for outputting a command signal to decelerate or stop the feed of the tool or to change the tool in accordance with a result of the comparison by said comparing means.

5,587,916 LOW VOLTAGE SENSING CIRCUITS FOR BATTERY POWERED DEVICES HAVING A MICRO-PROCESSOR


Glen D. Martinson, Oakville, Canada, and Stephen T. Makk, Conyers, Ga., assignors to B.E.L.-Tronics Limited, Mississauga, Canada

Filed Aug. 15, 1994, Ser. No. 290,122

Int. Cl.⁶ G05F 1/08

U.S. Cl. 364-483

18 Claims




5,587,924

AUTOMATIC SYSTEM FOR HANDLING BATTERIES

Markku J. Rossi, Houston, Tex., assignor to Compaq Computer Corporation, Houston, Tex.
 Filed Mar. 31, 1995, Ser. No. 414,760
 Int. Cl.⁶ H02J 7/00

U.S. Cl. 364-496

22 Claims



1. A system for determining a battery's energy capacity while the battery is in use in an electronic device, comprising:
 - a battery pack;
 - a first set of capacitors mounted in said battery pack comprising at least one capacitor;
 - a first set of resistors mounting in said battery pack comprising at least one resistor;
 - an op-amp circuit adapted to connect to said first set of capacitors and said first set of resistors so that a notch filter circuit results;
 - a noise generator connected to said notch filter;
 - an analog-to-digital converter connected to said notch filter for receiving a filtered signal and for producing a digital signal that corresponds to said filtered signal;
 - a look-up table; and
 - a processor circuit connected to said look-up table and to said analog to digital converter for determining the energy capacity of said battery.


5,587,925

FILE TESTING TECHNIQUES

Cheng J. Li, Leominster, Mass., assignor to Simonds Industries, Inc., Fitchburg, Mass.
 Filed Nov. 8, 1994, Ser. No. 336,188
 Int. Cl.⁶ G01M 13/00

U.S. Cl. 364-508

8 Claims



5. A method of testing a file comprising:

- (a) mounting a file at an initial position on the surface of a test bar of material at a preset compressive force between the file and the test bar surface;
- (b) moving the file over the test bar surface at a first selected filing force until the file stops;
- (c) determining the position of the file when it stops and calculating the distance travelled from said initial position;
- (d) repeating steps (b) and (c) for a successive number of times at successively increasing filing forces until the distance travelled is equal to a specified distance;
- (e) recording a value of the minimum filing force needed to travel the specified distance;
- (f) increasing the present compressive force by selected successive values and successively repeating steps (b), (c), (d), and (e) a selected number of times to record the minimum filing force needed at each successive value of the compressive force;
- (g) determining a curve of minimum filing force as a function of the selected successive values of compressive force;
- (h) performing steps (a) through (g) for a plurality of different files to be tested; and
- (i) comparing the relative values of the curves of minimum filing force values as a function of the selected successive values of compressive forces for said plurality of files to determine the relative sharpness characteristics of said plurality of files.

5,587,926



REFRIGERATED FLUID SAMPLING APPARATUS AND METHOD WITH VARIABLE VOLUME SAMPLING SYSTEM

Francis Chiu, Amherst; William Goss, Buffalo; David Hayes, North Tonawanda; Gary Randolph; Cheryl Sak, both of Lyndonville; Jeff Valery, Lockport, and James Vineski, Bergen, all of N.Y., assignors to American Sigma, Inc., Medina, N.Y.

Continuation-in-part of Ser. No. 219,097, Mar. 29, 1994, Pat. No. 5,506,791, which is a continuation-in-part of Ser. No. 954,288, Sep. 30, 1992, Pat. No. 5,299,141, which is a continuation-in-part of Ser. No. 612,832, Nov. 13, 1990, Pat. No. 5,172,332, which is a continuation-in-part of Ser. No. 455,981, Dec. 22, 1989, Pat. No. 5,091,863. This application Dec. 1, 1994, Ser. No. 348,050
 Int. Cl.⁶ G01F 11/00

U.S. Cl. 364-510

26 Claims



1. A refrigerated fluid sampling apparatus comprising:
 - a main housing;
 - a sample compartment disposed in a lower portion of said main housing;

fluid sampling means, disposed in said main housing, for withdrawing fluid from a fluid channel and delivering fluid samples to said sample compartment;
 means for supplying power to said apparatus;
 thermal control means for controlling temperatures within said sample compartment, said thermal control means comprising a compressor assembly; and
 said compressor assembly being disposed in an upper portion of said main housing, above said sample compartment.

5,587,927

DETECTING APPARATUS FOR DETECTING A CONTOUR OF A MOVING REGION IN A DYNAMIC IMAGE


Kenji Nagao, Watertown, Mass.; Masaki Sohma, Kawasaki, Japan; Shigeru Ando, Chiba, Japan, and Michihiro Kobayakawa, Chigasaki, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Jan. 6, 1994, Ser. No. 178,163

Claims priority, application Japan, Mar. 26, 1993, 5-067825
 Int. Cl.⁶ G06K 9/46

U.S. Cl. 364-514 A

17 Claims



1. A detecting method of a contour of a moving region of a dynamic image for distinguishing a moving object positioned in the moving region, comprising the steps of:
 - inputting a series of frames of dynamic image which consists of variable densities $F(x,y,t)$ of pixels;
 - calculating a variable density gradient $f_x = \partial F(x,y,t) / \partial x$ defined as an x directional gradient of the variable densities $F(x,y,t)$ for each of the pixels;
 - calculating a variable density gradient $f_y = \partial F(x,y,t) / \partial y$ defined as a y directional gradient of the variable densities $F(x,y,t)$ for each of the pixels;
 - calculating a variable density gradient $f_t = \partial F(x,y,t) / \partial t$ defined as a time-based variation of the variable densities $F(x,y,t)$ for each of the pixels;
 - calculating covariances S_{xx} , S_{xy} , S_{xt} , S_{yx} , S_{yt} , S_{tx} , S_{ty} and S_{tt} according to an equation

$$S_{ij} = \frac{1}{N} \sum_{t=1}^T \sum_{x=1}^X \sum_{y=1}^Y (f_i(x,y,t) - \bar{f}_i) (f_j(x,y,t) - \bar{f}_j)$$

- for each of the pixels by utilizing the variable density gradients f_x , f_y and f_t , integration ranges being limited in a space-time region of an observed pixel selected from the pixels and another space-time region of neighboring pixels positioned near to the observed pixel;
- extracting first, second, third and fourth inherent characteristics of the dynamic image by utilizing the covariances S_{xx} , S_{xy} , S_{xt} , S_{yx} , S_{yt} , S_{tx} , S_{ty} and S_{tt} , the first inherent charac-

teristic being utilized to judge whether or not an observed pixel selected from the pixels is positioned in a texture drawn in the dynamic image, the second inherent characteristic being utilized to judge whether the texture in which the observed pixel is positioned is a one-dimensional texture changing in a direction only or a two-dimensional texture changing in an x-y plane, the third inherent characteristic being utilized to judge whether luminous intensity of the observed pixel positioned in the one-dimensional texture changes in a motion change or a non-motion change, and the fourth inherent characteristic being utilized to judge whether luminous intensity of the observed pixel positioned in the two-dimensional texture changes in the motion change or the non-motion change;

classifying one or more pixels into first or second classification type by utilizing the first to fourth inherent characteristics, the first classification type (S1-ACR) denoting that an observed pixel selected from the pixels is positioned in the one-dimensional texture and the luminous intensity of the observed pixel changes with time in a non-motion change, and the second classification type (S2-ACR) denoting that the observed pixel is positioned in the two-dimensional texture and the luminous intensity of the observed pixel changes with time in the non-motion change;

recognizing first pixels classified into the first classification type and second pixels classified into the second classification type as boundary pixels positioned in a boundary region between the moving region and a static region of the dynamic image and setting a region occupied by the boundary pixels as a candidate region for a contour of the moving region;

detecting a contour of the moving region by adopting a line passing through a middle portion of the candidate region as the contour of the moving region;

distinguishing a moving object positioned in the moving region of which the contour is detected; and

processing the dynamic image in which the moving object distinguished exists to display the dynamic image in a displaying unit or transfer the dynamic image to an external unit.

5,587,928

COMPUTER TELECONFERENCING METHOD AND APPARATUS


Oliver Jones, Andover; Mary Deshon, Winthrop; Staffan Ericsson, Brookline, all of Mass., and James Flach, Cave Creek, Ariz., assignors to Vivo Software, Inc., Waltham, Mass.

Filed May 13, 1994, Ser. No. 242,271

Int. Cl.⁶ H04N 7/10

U.S. Cl. 364-514 A

12 Claims



1. A system for video conferencing, comprising:
 - a computer including a graphics subsystem in which a computer display image is represented by a digital computer display signal having a first format different from a digital television signal having a second format, the graphics subsystem receiving as an input the digital computer display signal;
 - means in the computer connected to the graphics subsystem, for obtaining from the graphics subsystem a portion of the digital computer display signal, the portion forming a sequence of frames representative of at least a portion of the computer display image;
 - means in the computer connected to receive the sequence of frames from the means for obtaining, for converting the sequence of frames of the digital computer display signal of

the first format into a sequence of frames forming a digital television signal of the second format; and means in the computer connected to receive the digital television signal, for compressing the digital television signal for transmission to a system for receiving compressed digital television signals.

5,587,929

SYSTEM AND METHOD FOR TRACKING OBJECTS USING A DETECTION SYSTEM


Richard B. League, and Norman K. Lay, both of Peoria, Ill., assignors to Caterpillar Inc., Peoria, Ill.

Filed Sep. 2, 1994, Ser. No. 299,093

Int. Cl.⁶ G01S 13/00

U.S. Cl. 364—516

8 Claims



1. A method of tracking objects using a detection system having a sensor that senses objects within a field of view, comprising the steps of:

- (A) sensing objects in the field of view of the detector;
- (B) generating a current frame of datapoints, wherein said datapoints represent an object sensed in step (A);
- (C) converting said datapoints into datapoints represented in global coordinates; and
- (D) mapping said converted datapoints into a next frame of datapoints to create a new frame of datapoints, wherein said new frame of datapoints represents objects detected in said next frame as well as objects detected in one or more previous frames.
- (E) doing blob coloring on said new frame of datapoints to define objects;
- (F) making a list of said objects in step (E); wherein said step (E) comprises the steps of:
 - i. scanning said new frame to locate a bin having datapoint having a non-zero power value.

5,587,930

FAULT DIAGNOSIS DEVICE

Satoshi Hori, Teruyo Omori, both of Amagasaki, and Makoto Sakagami, Nagoya, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 24, 1991, Ser. No. 739,591


Claims priority, application Japan, Jul. 24, 1990, 2-198273

Int. Cl.⁶ G01B 7/00

U.S. Cl. 364—551.01

3 Claims

1. A fault diagnosis device for determining a cause of fault of a device under test, comprising: detector means for detecting parameters of a device under test; memory means; and a fault tree stored in said memory means and having nodes corresponding to respective sub-units of said device under test, whereby said fault tree has a tree structure corresponding to a hardware organization of said device under test;



test tables stored in said memory and associated with respective nodes of said fault tree, each test table including: a description of at least one parameter to be detected by said detector means; at least one test condition with respect to the parameter detected by said detector means; and a fault probability table representing fault probabilities and names of child nodes corresponding to respective results of said test condition; and search/inference means for searching for and determining a cause of fault of said device under test in accordance with said fault tree and said test tables;

wherein at least one of said nodes has at least three child nodes and the test table associated with the node having at least three child nodes includes: a description of at least two parameters to be detected by said detector means; at least two test conditions with respect to the two parameters detected by said detector means; and a fault probability table representing fault probabilities and names of child nodes corresponding to respective patterns of results of said test conditions.

5,587,931

TOOL CONDITION MONITORING SYSTEM


Joel W. Jones, and Ya Wu, both of Windsor, Canada, assignors to Tri-Way Machine Ltd., Windsor, Canada

Filed Oct. 20, 1995, Ser. No. 546,361

Int. Cl.⁶ G05B 23/02; G08B 21/00

U.S. Cl. 364—551.02

18 Claims



1. A method for monitoring the condition of an electrically powered tool of a selected tool type performing a cyclical task comprising the steps of:

- a. using a tool to perform a cyclical task and measuring a power consumption signal of said tool as said tool performs said cyclical task;

- decomposing said power consumption signal of said tool into components by converting said power consumption signal into time segments, each time segment having a digital value equivalent to the analog value of said signal at said time, and decomposing said time segments of said power consumption signal into different frequency components using a mathematical algorithm;
- selecting feature components of said power consumption signal;
- using said selected components of said power consumption signal to set a power threshold in a learning cycle;
- using a tool to perform a cyclic task and monitoring its power consumption signal; and
- identifying a worn condition of the tool of step e. based upon a comparison of said power consumption signal with said predetermined power threshold of step d.

5,587,932

ON-BOARD MEASUREMENT SYSTEM


Joseph V. Ferrante, Redmond; Mark E. Lockman, Everett; Donald P. Matson, Mukilteo; John A. Gibbs, Lynnwood, and Warren H. Wong, Seattle, all of Wash., assignors to Fluke Corporation, Everett, Wash.

Filed Aug. 4, 1994, Ser. No. 285,952

Int. Cl.⁶ G06F 15/00; 17/40

U.S. Cl. 364—556

33 Claims



1. Apparatus for logging parameters to which a movable unit in a process environment is subjected, said apparatus comprising: a plurality of separable modules including at least one measurement module provided with sensor means for measuring an environmental parameter, and at least one control module for operating said measurement module;

said control module including microprocessor means for programming a measurement sequence, detachable interface means for connection to an external command center, and memory means for storing instructions and measured data; attachment means for removably attaching said measurement and control modules physically to said unit for movement with said unit;

first linking means positioned in communicating relation between said measurement and control modules when said modules are physically attached to said unit for transmitting instructions from said control module to said measurement module in order to direct measurement of said parameters and for returning data from said measurement module to said control module for storage in said memory means; and said measurement module including second linking means adaptable for communication between said measurement module and another measurement module for transmitting instructions from said control module to said other measurement module, and said first and second linking means being operable separately from said detachable interface means so as to facilitate simultaneous data transmittal by said measurement module and connection of said control module to an external command center.

5,587,933

SUPPORT ENHANCING DEVICE AND ASSOCIATED METHOD


Clifford M. Gross, Roslyn, N.Y., assignor to BCAM International, Inc., Melville, N.Y.

Continuation-in-part of Ser. No. 277,230, Jul. 19, 1994. This application Nov. 16, 1994, Ser. No. 340,541

Int. Cl.⁶ A61H 7/00; 1/00; G06F 15/00

U.S. Cl. 364—558

32 Claims



1. A method for supporting an animate object, comprising the steps of:

- (a) providing a structure defining a configurable contoured support surface;
- (b) placing a part of the object in contact with said support surface;
- (c) automatically measuring an input parameter to determine a pressure distribution on the part of the animate object in contact with the support structure;
- (d) automatically determining an optimal pressure distribution wherein comfort of the object's part is maximized according to an empirical regression equation or table;
- (e) automatically subjecting said support surface, in response to the selected optimal comfort pressure, to forces tending to modify a contour of said support surface; and
- (f) periodically and automatically altering said forces exerted on said support surface so as to provide a cyclic massage to the object's part.

5,587,934

AUTOMATIC VNA CALIBRATION APPARATUS


William W. Oldfield, Redwood City, Calif.; Thomas R. Brinkoetter, Portland, Oreg., and Todd D. Antes, San Jose, Calif., assignors to Wiltron Company, Morgan Hill, Calif.

Continuation-in-part of Ser. No. 140,781, Oct. 21, 1993, abandoned. This application Apr. 10, 1996, Ser. No. 630,195

Int. Cl.⁶ G01R 27/00

U.S. Cl. 364—571.01

10 Claims



6. A calibration apparatus for use in calibrating a Vector Network Analyzer (VNA), the VNA having a first and a second terminal, the calibration apparatus comprising:

- a first terminal for connecting to the first terminal of the VNA;
- a second terminal for connecting to the second terminal of the VNA;
- a first set of reflection components;
- a second set of reflection components;

setting a source line corresponding to a selected memory cell to said third predetermined voltage; and reading the state of said selected memory cell which is connected to said selected bit line and said selected word line.

5,587,947


LOW VOLTAGE ONE TRANSISTOR FLASH EEPROM CELL USING FOWLER-NORDHEIM PROGRAMMING AND ERASE

Shang-De Chang, Fremont; Jia-Hwang Chang, Cupertino, and Edwin Chow, Saratoga, all of Calif., assignors to Rohm Corporation, San Jose, Calif.

Division of Ser. No. 205,327, Mar. 3, 1994. This application Sep. 27, 1995, Ser. No. 534,691
Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—185.3

3 Claims



1. A method of identifying and repairing over-erased cells in an electrically erasable and programmable device of the type having a plurality of cells each comprising a single transistor having a source, a drain, a control gate, and a floating gate positioned between the control gate and the source and drain and wherein Fowler-Nordheim tunneling is used for tunneling electrons from the source to the floating gate and for tunneling electrons from the floating gate to the drain and further of the type having a plurality of row address lines each coupled to the control gates of the cells in an associated row, a plurality of column address lines each coupled to the drains of the cells in an associated column, and a plurality of source lines coupled to the sources of the cells, the method comprising the steps of:

- separately testing each column for the presence of over-erased cells;
- individually testing the cells in columns found to have over-erased cells to determine which cells are over-erased; and
- repairing the cells found to be over-erased by
 - applying a first voltage to the row address lines associated with the control gates of the over-erased cells;
 - grounding the source lines associated with the sources of the over-erased cells; and
 - floating the column address lines associated with the drains of the over-erased cells.

5,587,948

NONVOLATILE SEMICONDUCTOR MEMORY WITH NAND STRUCTURE MEMORY ARRAYS

Hirotaki Nakai, Yokohama, Japan, assignor to Kabushiki Kaisha Toshiba, Kyoto, Japan


Filed Jun. 14, 1995, Ser. No. 490,167

Claims priority, application Japan, Jun. 17, 1994, 6-135814
Int. Cl.⁶ G11C 11/34

U.S. Cl. 365—185.17

6 Claims

1. A nonvolatile semiconductor memory comprising:
a first bit line;



a second bit line;
a plurality of select gate lines;
a source line;

a memory cell array comprising a plurality of first NAND strings in a first memory cell area and a plurality of second NAND strings in a second memory cell area, each of the first NAND strings comprising a select gate transistor and i non-volatile memory cells, which are connected in series between said first bit line and said source line, each of the second NAND strings comprising a select gate transistor and j non-volatile memory cells, which are connected in series between said second bit line and said source line, said i non-volatile memory cells being greater in number than said j non-volatile memory cells; and

decoding means for selecting those of said first NAND strings and those of said second NAND strings, which are connected to a selected one of said select gate lines.

5,587,949

METHOD FOR PROGRAMMING AN ETOX EPROM OR FLASH MEMORY WHEN CELLS OF THE ARRAY ARE FORMED TO STORE MULTIPLE BITS OF DATA


Albert Bergemont, and Min-hwa Chi, both of Palo Alto, Calif., assignors to National Semiconductor Corporation, Santa Clara, Calif.

Filed Apr. 27, 1995, Ser. No. 429,644

Int. Cl.⁶ G11C 13/00

U.S. Cl. 365—185.24

20 Claims



1. A method for programming a memory array, the array having a plurality of memory cells formed in columns and rows, a plurality of common source bit lines arranged so that two rows of memory cells are formed between each pair of adjacent common source bit lines, a plurality of drain regions formed in columns and rows so that one row of drain regions is formed between each pair of adjacent common source bit lines, and so that, in each column of memory cells,

one drain region is formed between each pair of memory cells that are formed between adjacent rows of common source bit lines, a plurality of word lines formed so that one word line is formed over each of the memory cells in a row of memory cells, and a plurality of metal drain lines formed so that one metal drain line contacts each of the drain regions in a column of drain regions, each memory cell being formed to produce a punchthrough current during programming, the array being formed in a well, the method comprising the steps of:

identifying a memory cell in a column of memory cells that is to be programmed from an erased threshold voltage to a first threshold voltage, and a memory cell in the column of memory cells that is to be programmed from the erased threshold voltage to a second threshold voltage;

applying a first voltage to the metal drain line that corresponds to the column of memory cells;

applying a second voltage to the common source bit lines, the second voltage being less than the first voltage;

applying the second voltage to the well; and

applying a programming voltage that corresponds to the first threshold voltage to the word line that corresponds to the memory cell in the column of memory cells that is to be programmed to the first threshold voltage, and a programming voltage that corresponds to the second threshold voltage to the word line that corresponds to the memory cell in the column of memory cells that is to be programmed to the second threshold voltage.

5,587,950

TEST CIRCUIT IN CLOCK SYNCHRONOUS SEMICONDUCTOR MEMORY DEVICE

Seiji Sawada, and Yasuhiro Konishi, both of Hyogo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 246,582, May 19, 1994, abandoned. This


application Jun. 5, 1995, Ser. No. 461,907

Claims priority, application Japan, May 25, 1993, 5-122439

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—201

3 Claims



2. A synchronous semiconductor memory device incorporating external signals in synchronization with a clock signal formed of a series of pulses, said synchronous semiconductor memory device comprising:

a plurality of data input terminal;
selection means for simultaneously selecting a group of a predetermined number of memory cells for each of said plurality of data input terminals for writing data applied sequentially to each of said plurality of data input terminals in synchronization with the clock signal; and
write means for simultaneously writing test data being supplied to each of said plurality of data input terminals in one clock cycle in corresponding groups of said predetermined number

of memory cells selected by said selection means in response to a test mode designating signal.

5,587,951

HIGH SPEED, LOW VOLTAGE NON-VOLATILE MEMORY


Mehdi Jazayeri; Edward S. Hui, both of Cupertino, and George J. Korsh, Redwood City, all of Calif., assignors to Atmel Corporation, San Jose, Calif.

Filed Aug. 4, 1995, Ser. No. 511,311

Int. Cl.⁶ G11C 13/00

U.S. Cl. 365—203

34 Claims



1. A low voltage non-volatile memory comprising:
a memory array of rows and columns of nonvolatile memory cells with each row identified by a word line and each column identified by a bit line and each cell addressable through a word line and a bit line, said bit lines coupled through sense amplifiers to output driving circuitry, and
an input means associated with said array for initiating a read operation, said input means being coupled to an oscillator responsive to a read operation and coupled to a voltage pump circuit responsive to a read operation, said oscillator being coupled to a frequency control input of said voltage pump circuit, and said voltage pump circuit being coupled to a word line.

5,587,952

DYNAMIC RANDOM ACCESS MEMORY INCLUDING READ PREAMPLIFIERS ACTIVATED BEFORE REWRITE AMPLIFIERS

Goro Kitsukawa, Hinodemachi; Takao Watanabe, Kokubunji; Ryoichi Hori, Hinodemachi; Noriyuki Honma, Kokubunji; Kunihiko Yamaguchi, Sayama, and Kiyoo Itoh, Higashiku-


ruma, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Continuation of Ser. No. 35,272, Mar. 22, 1993, abandoned, which is a division of Ser. No. 921,385, Jul. 30, 1992, abandoned, which is a continuation of Ser. No. 308,680, Feb. 3, 1989, abandoned, which is a continuation-in-part of Ser. No. 803,673, Dec. 2, 1985, abandoned, and Ser. No. 170,623, Mar. 17, 1988, Pat. No. 4,813,020, which is a continuation of Ser. No. 825,939, Feb. 4, 1986, abandoned. This application Feb. 21, 1995, Ser. No. 391,537

Claims priority, application Japan, Dec. 17, 1984, 59-264466
Int. Cl.⁶ G11C 11/409:7/06

U.S. Cl. 365—207

26 Claims

1. A dynamic random access memory comprising:
a memory cell;
a word line for accessing said memory cell;
a first data line crossing said word line for transferring a signal voltage from said memory cell;
a second data line crossing said word line;
a rewrite amplifier simultaneously coupled to said first and second data lines when amplifying a voltage difference between the signal voltage from said memory cell on said first data line and a voltage on said second data line, for rewriting



the amplified voltage difference to said memory cell, wherein the memory cell is directly connected to said rewrite amplifier through said first data line;

a read sense circuit for sensing the voltage difference between the signal voltage from said memory cell on said first data line and the voltage on said second data line; and

a common data line pair coupled to output terminals of said read sense circuit,

wherein said read sense circuit has two insulated gate field-effect transistors, gates of which are respectively coupled to said first and second data lines to receive voltages thereon, and source/drain paths of which are coupled to said common data line pair, and

wherein said read sense circuit is activated to sense the voltage difference between the signal voltage from said memory cell on said first data line and the voltage on said second data line and to provide an output to the common data line pair before said rewrite amplifier is activated to amplify the voltage difference between the signal voltage from said memory cell on said first data line and the voltage on said second data line.

5,587,953

FIRST-IN-FIRST-OUT BUFFER MEMORY


Chan H. Chung, Bubaleub, Rep. of Korea, assignor to Hyundai Electronics Industries Co., Inc., Rep. of Korea
Filed Jul. 6, 1995, Ser. No. 499,087
Claims priority, application Rep. of Korea, Jul. 6, 1994, 1994-16143

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—220

3 Claims

1. A first-in first-out buffer memory comprising:
 - a core memory having a dual port, for substantially storing data; first and second address decoders responsive to read and write clock signals, for producing addresses indicative of directing a location in the core memory, when data is written in the core memory, or when the data is read from the core memory; and
 - a status detector for generating memory status signals indicating whether the data can be written in the core memory or whether the data can be read from the core memory;
 - said status detector comprising,
 - first and second flip-flops for providing input signals thereof to output terminals thereof in accordance with the write and read clock signals, respectively, each having a clear terminal and a clock terminal;
 - a multiplexer for receiving the output signals of the flip-flops and selecting one of them in response to a selection control signal;
 - a phase detector for generating the selection control signal in response to the write and read clock signals to control selecting operation of the multiplexer;



5,587,954


RANDOM ACCESS MEMORY ARRANGED FOR OPERATING SYNCHRONOUSLY WITH A MICROPROCESSOR AND A SYSTEM INCLUDING A DATA PROCESSOR, A SYNCHRONOUS DRAM, A PERIPHERAL DEVICE, AND A SYSTEM CLOCK

Wilbur C. Vogley, Missouri City; Anthony M. Balistreri, Houston; Karl M. Guttig, Missouri City; Steven D. Krueger, Houston; Duy-Loan T. Le; Joseph H. Neal, both of Sugarland; Kenneth A. Poteet, Houston; Joseph P. Hartigan, Stafford; and Roger D. Norwood, Houston, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.
Division of Ser. No. 184,749, Jan. 21, 1994, Pat. No. 5,390,149, which is a continuation of Ser. No. 690,207, Apr. 23, 1991.
This application Oct. 21, 1994, Ser. No. 327,540

Int. Cl.⁶ G11C 13/00

U.S. Cl. 365—221

53 Claims



1. A data processing system comprising
 - a digital processor;
 - a system clock circuit for producing a system clock signal having timing edges for controlling operation of the digital processor;

a synchronous random access memory, directly responsive to the edges of the system clock signal, for accessing addressable storage cells within the synchronous memory to write data into the storage cells and to read out data from the storage cells; and

the synchronous random access memory including input and output data latches arranged for latching data directly in response to the system clock signal.

5,587,955


ELECTRONIC TOKEN

Robert D. Lee, Denton; Stephen M. Curry, Dallas; Michael L. Bolan, Dallas; Hal Kurkowski, Dallas; Donald R. Diaz, Carrollton; Francis A. Scherpenberg, Dallas, all of Tex., and Kevin E. Deierling, Los Altos Hills, Calif., assignors to Dallas Semiconductor Corporation, Dallas, Tex.
Division of Ser. No. 19,932, Feb. 19, 1993, Pat. No. 5,398,321, which is a division of Ser. No. 352,581, May 15, 1989, Pat. No. 5,210,846. This application Dec. 13, 1994, Ser. No. 355,362

Int. Cl.⁶ G06K 19/04; 19/06; H01L 25/04; G11C 7/00

U.S. Cl. 365—221

81 Claims



1. An electronic token, comprising:
 - (a) a casing having a first conductive surface and a second conductive surface, said first conductive surface and said second conductive surface accessible from an exterior of said casing, said first conductive surface and said second conductive surface combine a substantial portion of said casing, said first conductive surface and said second conductive surface combine to form a cavity;
 - (b) an energy source positioned in said cavity;
 - (c) a semiconductor memory positioned in said cavity, said semiconductor memory electrically coupled to said energy source;
 - (d) input logic operatively electrically coupled to said first conductive surface and to said second conductive surface of said casing and configured to detect whether said first conductive surface is at a first voltage or at a second voltage and selectively to store data in said semiconductor memory accordingly, said input logic electrically coupled to said energy source; and
 - (e) output logic comprising an active device electrically coupled to selectively pull said first conductive surface of said casing toward said second voltage, said output logic electrically coupled to said semiconductor memory and said energy source.

5,587,956


SEMICONDUCTOR MEMORY DEVICE HAVING FUNCTION OF GENERATING BOOSTED POTENTIAL

Susumu Tanida, Hyogo, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
Filed Aug. 17, 1995, Ser. No. 516,077
Claims priority, application Japan, Nov. 10, 1994, 6-276476
Int. Cl.⁶ G11C 13/00; 8/00

U.S. Cl. 365—226

6 Claims

1. A semiconductor memory device comprising:
 - a boosted potential node provided for outputting a boosted potential;



determination cycle control means for outputting a control pulse signal having a controllable cycle for defining a cycle used for determining a level of the potential of said boosted potential node;

level determining means for comparing the potential of said boosted potential node with a predetermined reference potential to determine a relative level of the potential of said boosted potential node with respect to the reference potential in accordance with a determination cycle defined by said control pulse signal output from said determination cycle control means;

drive pulse oscillating means for oscillating a drive pulse signal when said level determining means determines that the potential of said boosted potential node is lower than said reference potential; and

charge pump means for being driven to supply an electric charge for raising the potential of said boosted potential node to said boosted potential node in response to the drive pulse signal output from said drive pulse oscillating means, wherein said determination cycle control means outputs a control pulse signal of a first cycle in response to the determination by said level determining means that the potential of said boosted potential node is equal to or higher than said reference potential, and outputs the control pulse signal of a second cycle shorter than said first cycle in response to the determination by said level determining means that the potential of said boosted potential node is lower than said reference potential.


5,587,957

CIRCUIT FOR SHARING A MEMORY OF A MICROCONTROLLER WITH AN EXTERNAL DEVICE

Robert M. Kowalczyk; Robert H. Brown, III, both of Chandler, and Jack W. Heller, Mesa, all of Ariz., assignors to Intel Corporation, Santa Clara, Calif.
Filed Sep. 29, 1995, Ser. No. 537,109
Int. Cl.⁶ G11C 8/00; G06F 9/00

U.S. Cl. 365—230.03

5 Claims



1. A device for sharing a memory of a microcontroller with an external device said microcontroller having a CPU, said device, comprising:
 - a communication unit for exchanging information between said external device and said memory;
 - bus control circuitry for exchanging information, between said CPU of said microcontroller and said memory, and for generating CPU status signals;
 - memory arbitration circuitry, coupled to said communication unit and to said bus control circuitry, for receiving said CPU status signals and responsive thereto operatively coupling said communication unit to said memory when said CPU status

signals indicate that said CPU will not access said memory for a predetermined time.

5,587,958

SEMICONDUCTOR MEMORY DEVICE INCLUDING A BOOST POTENTIAL GENERATION CIRCUIT

Tetsuya Kaneko, Kawasaki, and Takashi Ohsawa, Yokohama, both of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Dec. 27, 1994, Ser. No. 363,825

Claims priority, application Japan, Dec. 28, 1993, 5-349524

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—230.06

33 Claims



1. A semiconductor memory device comprising:
 - boosted potential generating means for steadily generating a boosted potential which is higher than an external voltage supplied thereto;
 - word line driving means, receiving the boosted potential of said boosted potential generating means as a power supply, for driving word lines; and
 - control means for receiving a designation signal for designating one of a plurality of refresh cycles and for supplying, to said boosted potential generating means, a control signal, which is generated based on the designation signal, for setting a current supply capability of said boosted potential generating means in accordance with the number of word lines driven by said word line driving means in the designated refresh cycle,
- wherein the control signal generated by said control means increases the current supply capability of said boosted potential generating means when the number of word lines driven in the refresh cycle designated by the designation signal is increased, and decreases the current supply capability of said boosted potential generating means when the number of word lines driven in the refresh cycle designated by the designation signal is decreased.

5,587,959

SEMICONDUCTOR MEMORY DEVICE

Masaki Tsukude, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Sep. 19, 1995, Ser. No. 530,583


Claims priority, application Japan, Jan. 10, 1995, 7-001920

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—230.06

16 Claims

15. A semiconductor memory device, comprising:
 - a plurality of memory elements provided in a plurality of rows and a plurality of columns for dynamically storing information by storing charge;
 - a main word line supplied with one of a first voltage not to make a selection of a set of rows in which said plurality of memory elements are provided and a second voltage higher than said first voltage to make the selection;
 - a first signal line for transmitting a binary first subdecode signal including said first voltage and a third voltage lower than said second voltage;



control signal is asserted, a different one of said data being output at each of said clock cycles after said output begins until said plurality of data is output.

5,587,964

PAGE MODE AND NIBBLE MODE DRAM


Mitchell N. Rosich, Groton, Mass., and William L. Lippitt, Combland, R.I., assignors to Digital Equipment Corporation, Maynard, Mass.

Continuation of Ser. No. 417,712, Apr. 6, 1995, abandoned, which is a continuation of Ser. No. 317,413, Oct. 3, 1994, abandoned, which is a continuation of Ser. No. 176,294, Jan. 3, 1994, abandoned, which is a continuation of Ser. No. 722,697, Jun. 28, 1991, abandoned. This application Apr. 1, 1996, Ser. No. 625,990

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—238.5

10 Claims



1. A page mode/nibble mode dynamic random access memory (DRAM) for providing both a page mode and a nibble mode comprising:

- a storage cell for storing information in an array defined by a predetermined number of rows and columns;
- a row address decoder, coupled to said storage cell, the row address decoder receiving a first predetermined portion of a memory address and a first signal, said row address decoder inputting the first predetermined portion of the memory address into said storage cell in response to receiving the first signal;
- a column address decoder, coupled to said storage cell, for receiving a second predetermined portion of the memory address and a second signal;
- a column address buffer counter, coupled to the column address decoder and said storage cell, the column address buffer counter for receiving a third predetermined portion of the memory address and the second signal;
- said column address decoder and said column address buffer counter inputting the second and third predetermined portions, respectively, of the memory address into said storage cell in response to receiving the second signal;
- data-in and data-out buffers each coupled to said storage cell;
- a write mode/read mode selection means coupled to said data-in and data-out buffers for receiving as an input a third signal with a state of the third signal determining whether a write mode is selected and whether a read mode is selected; and
- a buffer controller means, coupled to said column address decoder and said column address buffer counter, the buffer controller means for receiving at least the third signal as an input and for providing the second signal, with a state of the third signal determining whether a page mode or a nibble mode is selected, and wherein said page mode or said nibble mode is changeable during operation of said dynamic random access memory.

5,587,965
SURFACE MULTIPLE ATTENUATION VIA EIGENVALUE DECOMPOSITION


William H. Dragoset, Jr., and Zeljko Jericevic, both of Houston, Tex., assignors to Western Atlas International, Inc., Houston, Tex.

Filed Apr. 26, 1996, Ser. No. 638,282

Int. Cl.⁶ G01V 1/38; 1/36

U.S. Cl. 367—24

9 Claims



1. A method for substantially attenuating surface multiples from marine seismic signal, comprising the steps of:

transforming said marine seismic signal from time domain into frequency domain to generate a transformed signal represented by matrix D ; truncating said marine seismic signal in time to generate a truncated signal and transforming said truncated signal from time domain into frequency domain to generate a transformed truncated signal represented by truncated matrix D_T ;

computing eigenvalue decomposition $D_T = S \cdot A \cdot S^{-1}$ of said truncated matrix D_T ; where A is the diagonal matrix whose elements are the eigenvalues of D_T , S is the square matrix whose rows are the corresponding eigenvectors of D_T and S^{-1} is the inverse of S ;

solving for source wavelet w by minimizing total energy in matrix product $[D \cdot S][I - w^{-1}A]^{-1}S^{-1}$ in an iterative loop;

solving for primary matrix P by inserting said solved value for said source wavelet w into the expression

$$P = [D \cdot S][I - w^{-1}A]^{-1}S^{-1}; \text{ and}$$

inverse transforming said primary matrix P from frequency domain into time domain.

5,587,966

SONIC WELL LOGGING METHODS AND APPARATUS FOR PROCESSING FLEXURAL WAVE IN OPTIMAL FREQUENCY BAND

Christopher V. Kimball, West Redding, Conn., and David J. Schelbner, Tokyo, Japan, assignors to Schlumberger Technology Corporation, Ridgefield, Conn.

Filed Oct. 13, 1994, Ser. No. 322,885


Int. Cl.⁶ G01V 1/40; G06F 15/48

U.S. Cl. 367—31

21 Claims

1. A method of determining a frequency band for the frequency-dependent processing of flexural wave information obtained in a borehole traversing a formation, comprising:

- a) obtaining a determination of a diameter of the borehole;
- b) obtaining a preliminary estimate of a shear slowness of the formation;
- c) choosing a frequency band with a center frequency which is a function of said preliminary estimate of a shear slowness of the formation, and a function of the product of said estimate shear slowness and said borehole diameter, said frequency band having a bandwidth less than twice said center frequency; and



d) processing the flexural wave information in said frequency band to obtain an indication of a parameter of the formation.

5,587,967

METHOD FOR IMPROVEMENT OF SEISMIC SECTIONS Ralf G. Ferber, Hanover, Germany, assignor to Prakla-Seismos GmbH, Hanover, Germany

Continuation of Ser. No. 182,006, Jan. 13, 1994, abandoned.


This application Mar. 11, 1996, Ser. No. 613,923

Claims priority, application European Pat. Off., May 15, 1992, 92108259; May 29, 1992, 92109082

Int. Cl.⁶ G01V 1/36; 1/24

U.S. Cl. 367—53

8 Claims



1. A method for improving seismic sections comprising the steps of generating seismic signals at a plurality of source stations; recording seismic traces at a plurality of receiver stations; selecting a common point (MMOCMP) having a position defined by

$$l^2 = h^2 + b^2 + r^2$$

wherein

h is a half-offset between a source station and a receiver station and defines RAWCMP,

b is a distance between RAWCMP and a point on a line joining said source station and receiver station corrected by dip moveout, thereby defining DMOCMP,

r is a distance between DMOCMP and MMOCMP, and l is a distance between the selected common point MMOCMP and the RAWCMP;

gathering the recorded seismic traces as a first gather at said common point; redefining half-offset l as a function of the common point; and sorting the seismic traces as a function of the redefined half-offset l , thereby forming a second gather of traces.

5,587,968

METHOD FOR MEASURING THE NEAR-SURFACE SHEAR WAVE VELOCITY FOR USE IN DETERMINING 3-COMPONENT 3-D STATICS


Frederick J. Barr, Houston, Tex., assignor to Western Atlas International, Inc., Houston, Tex.

Filed Aug. 25, 1995, Ser. No. 519,463

Int. Cl.⁶ G01V 1/36

U.S. Cl. 367—75

6 Claims



1. A method for scaling static time corrections for application to shear wave reflection data received by at least two sets of two co-located shear wave sensors having first and second mutually perpendicular polarization directions respectively, the sets being distributed in spaced-apart relationship along a line of survey, comprising:

- a) acoustically irradiating a first microspread including a plurality of spaced-apart seismic sensors, the microspread being aligned along a first azimuth aligned with said first polarization direction;
- b) determining the phase velocity of a compressional wave, propagating directly through a near-surface earth layer, from measurement of the arrival times of the compressional wave detected by each said sensor as a function of sensor spacing;
- c) determining the group velocity of a boundary wave, propagating along the upper boundary of said near-surface earth layer, from the arrival time of the boundary wave detected by each said sensor as a function of sensor spacing;
- d) resolving the so-determined velocities to define a first near-surface shear-wave velocity vector directed along said first azimuth;
- e) repeating steps a) through d) for a microspread oriented along a second azimuth aligned with said second polarization direction, to define a second near-surface shear-wave velocity vector directed along said second azimuth;
- f) defining a scaling coefficient from the ratio between said first and second near-surface shear wave velocity vectors;
- g) applying said scaling coefficient to static time corrections applicable to seismic recordings received by shear-wave sensors whose polarization directions are aligned with said second azimuth.

5,587,969

PROCESS FOR THE RECOGNITION AND SEPARATION OF USEFUL AND INTERFERING ECHOES IN THE RECEIVED SIGNALS OF DISTANCE SENSORS WHICH OPERATE IN ACCORDANCE WITH THE PULSE-ECHO PRINCIPLE

Nils Kroemer, Hohenstein-Ernstthal; Martin Vossiek, München; Peter-Christian Eccardt, Ottobrunn, and Valentin Magori, München, Germany, assignors to Siemens Aktiengesellschaft, Munich, Germany

PCT No. PCT/DE94/00249, § 371 Date Sep. 5, 1995, § 102(e) Date Sep. 5, 1995, PCT Pub. No. WO94/22033, PCT Pub. Date Sep. 29, 1994


PCT Filed Mar. 10, 1994, Ser. No. 522,310

Claims priority, application Germany, Mar. 16, 1993, 43 08 373.0

Int. Cl.⁶ G01S 15/00; 7/52; G01F 23/28

U.S. Cl. 367—99

7 Claims



1. A method for the recognition and separation of useful and interfering echoes in a received signal of a pulse-echo distance sensor, said method comprising the steps of:
 - detecting maxima in said received signal and associating each maxima with an echo;
 - identifying a form factor with each echo characterizing a form of that echo, and storing the form factors for the respective echoes;
 - identifying an amplitude and a time of occurrence for each maximum, and storing the respective amplitude and time of occurrence for all of said maxima;
 - measuring a difference between the amplitudes of the respective maxima and expected amplitude values;
 - measuring a difference between the time of occurrence of each maximum and expected time of occurrence values;
 - measuring a difference between the form factor for each echo and expected form factor values;
 - assigning a probability to each echo as to whether that echo comprises a multiple echo by evaluating each of the amplitude, time of occurrence and form factor differences with a smaller difference resulting in an increased probability that said echo comprises a multiple echo; and
 - assigning a probability to each echo as to whether that echo comprises an interfering echo with the probability that said echo comprises an interfering echo being greater as the probability of said echo comprising a multiple echo increases.

5,587,970

PERSONAL ATTACK/HELP ALARM


Julie A. Greenwood, 33 Russell Dr., Wollaton, Nottingham NG8 2BA, United Kingdom

Filed Nov. 29, 1994, Ser. No. 346,418

Int. Cl.⁶ G04B 47/00; G08B 15/00; 13/00

U.S. Cl. 368—10

8 Claims



1. A personal attack/help alarm incorporated within a watch to be worn by an operator, the alarm comprising an alarm signal generating device and activating means accessible externally to enable the alarm to be activated by the operator, and in which the activating means is a pin switch arrangement, in which the pin switch arrangement comprises a two position device, a first position for testing the alarm and a second position for full activation of the alarm, and in which the second position the pin is completely removed from the watch.

5,587,971

MODE PRESELECT FUNCTION FOR A MULTIMODE ELECTRONIC TIMEPIECE


Tom Thinesen, Sunnyvale, Calif., assignor to Timex Corporation, Middlebury, Conn.

Filed Feb. 20, 1996, Ser. No. 603,972

Int. Cl.⁶ G04B 19/30; G04C 19/00

U.S. Cl. 368—70

8 Claims



1. An improved multimode electronic timepiece of the type having a display, a plurality of manually actuated switches, and an integrated circuit programmed to keep time, to provide a set of at least three operating modes, including time-of-day, in a continuous loop, and to permit an operator of the timepiece to shift said operating modes sequentially by selectively and repetitively actuating a first of said switches, wherein the improvement comprises:
 - mode preselect function means responsive to selective actuation of a second of said switches, said mode preselect function means comprising a program for the integrated circuit which provides a set of at least one preselect function mode in a continuous loop, each preselect function mode displaying

information from a preselected operating mode along with information from another operating mode;

said program being adapted to permit the operator of the timepiece to shift sequentially through the set of preselect function modes by selectively, and where there is more than one preselect function mode in the set, repetitively actuating a third of said switches; and

said mode preselect function means being further responsive to selective actuation of a fourth of said switches, actuation of said fourth switch causing the timepiece to shift between a preselect function mode and the operating mode, other than the preselected operating mode, having its information displayed by said preselect function mode.

5,587,972

CONTROL CIRCUIT USING DELAY LINES TO GENERATE CLOCK AND CONTROL SIGNALS DURING A CLOCK CYCLE OF THE SYSTEM CLOCK


Ronald D. Schofield, Ridgecrest, Calif., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Mar. 4, 1996, Ser. No. 610,502

Int. Cl.⁶ G04F 8/00; G06F 1/04

U.S. Cl. 368—118

20 Claims



1. A control signal generating circuit comprising:
 - state machine means for receiving a system clock signal, said state machine means, responsive to said system clock signal, generating a plurality of state variable signals;
 - a plurality of decoding means coupled to said state machine means, each of said decoding means receiving said plurality of state variable signals, each of said decoding means decoding said plurality of state variable signals to provide a group of timing and control signals;
 - first delay means coupled to three of said plurality of decoding means, said first delay means receiving and then delaying for a first predetermined time period some of said group of timing and control signals from each of said three decoding means coupled to said first delay means; and
 - second delay means coupled to two of said plurality of decoding means, said second delay means receiving and then delaying for a second predetermined time period at least one of said timing and control signals from each of said two decoding means coupled to said second delay means.

5,587,973

MAGNETO-OPTICAL DISK DRIVE SYSTEM WITH MAGNETIC HEAD RETRACTING MECHANISM AND MANUAL CARTRIDGE EJECTING MECHANISM

Hiroshi Kanazawa; Isao Okuda; Shimpei Shinozaki, and Suguru Takishima, all of Tokyo, Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Division of Ser. No. 86,432, Jul. 6, 1993, abandoned. This application Mar. 23, 1995, Ser. No. 408,977

Claims priority, application Japan, Jul. 7, 1992, 4-179922; Nov. 16, 1992, 4-78734

Int. Cl.⁶ G11B 11/00; 33/02

U.S. Cl. 369—13

6 Claims



1. A magneto-optical disk drive system utilizing a magnetic field modulation recording method, comprising:
 - a housing;
 - a disk cartridge for housing a magneto-optical disk therein, said disk cartridge being insertable into said housing;
 - a magnetic head for writing information on the magneto-optical disk held in said disk cartridge, said magnetic head being movably disposed in said housing;
 - cam means supported on said housing for guiding said disk cartridge to move between a first unloading position and a first loading position when said disk cartridge is inserted in said housing, and guiding said magnetic head to move between a second unloading position from said disk cartridge toward a second loading position close to said disk cartridge; resilient means acting between said housing and said cam means normally urging said magnetic head to move from said second loading position to a standby position between said first loading position and said second unloading position;
 - electromagnetic locking means energizable for holding said cam means to lock said magnetic head in said second loading position against a bias of said resilient means, and de-energizable for releasing said cam means to move said magnetic head from said second loading position into said standby position under the bias of said resilient means;
 - a lock arm for engaging said cam means to prevent said magnetic head from moving from said standby position toward said second unloading position when said electromagnetic locking means is de-energized;
 - a manual ejecting lever slidably supported in said housing and manually pressable for moving said lock arm out of engagement with said cam means and moving said cam means to guide said disk cartridge to move from said first loading position to said first unloading position;
 - a guide plate assembly movably supported on said housing;
 - a magnetic head carriage supporting said magnetic head;
 - a cartridge holder for holding said disk cartridge, and wherein said cam means includes a first cam pin mounted on said cartridge holder and movably disposed in a first cam groove defined in said guide plate assembly, and a second cam pin mounted on said cartridge holder and movably disposed in a second cam groove defined in said guide plate assembly.

category code which is separate from and indicates the information category to which the information contained therein relates, different ones of the information packets containing coded text or image information relating to different information categories and being interleaved; and
an arrangement for reading the information carrier, including:
reading means for reading the sub-information;
selection means for selecting one of the information categories to which the information contained in the information packets relates as a selected information category; and
separating means for separating the one or more information packets containing coded text or image information relating to the selected information category from the sub-information on the basis of the category codes.

5,587,980

METHOD DERIVING A QUALITY SIGNAL FROM A READ SIGNAL, AND READING AND RECORDING DEVICES WHICH EMPLOY THAT METHOD

Johannes G. F. Kahlau; Winslow M. Minnagh, and Petrus C. J. Hoeven, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Mar. 29, 1994, Ser. No. 219,321

Claims priority, application Belgium, Apr. 22, 1993, 09300398

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—54

25 Claims



1. A method of deriving a quality signal which is indicative of the quality of a read signal having constant-length bit cells, which bit cells individually have a first or a second logic value, the method comprising:

obtaining the read signal by reading an information pattern of optically detectable effects which represent groups of successive bit cells having the first logic value, in which first read signal portions of the read signal exceeding a reference value correspond to the effects; and
deriving the quality signal on the basis of the first read signal portions, such derivation involving determining a first measure of first length deviation between lengths of the first read signal portions which represent groups of n successive bit cells and n times the bit cell length, where n is a value such that sensitivity of the length deviation for the value of n to certain parameter changes is relatively large in comparison with sensitivity of the first length deviation for other values of n to the parameter changes.

5,587,981

MULTI-STANDARD OPTICAL DISK READING METHOD HAVING DISTINCTION PROCESS

Yasuo Kamatani, 2-12-2 Yokoyama, Sagami-hara-shi, Kanagawa 229, Japan


Filed Sep. 5, 1995, Ser. No. 523,461

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—58

3 Claims

1. An optical disk reading method comprising the steps of:



reading a total of contents data in a read-in region of an optical disk to identify total number of data layers and pit configuration standard of the optical disk; and
setting modulation of servomechanism means dependent upon the total of contents data;

(a) the servomechanism means including:
a focusing lens servo to modulate position of a focusing lens; and
a tracking servo to modulate movement of a pickup.

5,587,982

OPTICAL DISK DRIVE DEVICE CAPABLE OF DETECTING MISPLACEMENT OF OPTICAL DISKS

Tae-Young Choi, Uiwang, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Filed Oct. 23, 1995, Ser. No. 547,070

Claims priority, application Rep. of Korea, May 12, 1995, 11766/1995

Int. Cl.⁶ G11B 3/90; 23/00

U.S. Cl. 369—58

15 Claims



1. An optical disk driving apparatus for preventing misplacement of an optical disk within said optical disk driving apparatus, said optical disk driving apparatus comprising:

a main body having an opening through which said optical disk is transferred into and out from said optical disk driving apparatus;
transfer means for transferring said optical disk into and out from said main body;
driving means, positioned within said main body, for rotatably driving said optical disk when said optical disk is loaded upon said driving means;

an optical pickup for detecting information recorded on said optical disk while said optical disk is rotated by said driving means;

light emitting means for irradiating first light onto at least one surface of said optical disk while said optical disk is being inserted into said main body via said transfer means;

light receiving means, positioned apart from said light emitting means, for receiving second light reflected by said optical disk in response to said first light irradiated by said light emitting means; and

circuit means for determining whether said optical disk is being properly inserted into said main body in dependence upon an amount of said second light received by said light receiving means, said circuit means controlling said transfer means to eject said optical disk from said main body before said optical disk is loaded upon said driving means when said optical disk is not being properly inserted into said main body.

5,587,983

SYSTEM FOR RECORDING DIGITAL INFORMATION IN A PULSE-LENGTH MODULATION FORMAT


Jack H. Bailey, Villa Park, Calif., assignor to Discovision Associates, Irvine, Calif.

Continuation of Ser. No. 119,655, Sep. 13, 1993, which is a continuation of Ser. No. 75,275, Jun. 11, 1993, Pat. No. 5,321,680, which is a continuation of Ser. No. 948,267, Sep. 21, 1992, Pat. No. 5,253,244, which is a continuation of Ser. No. 825,640, Jan. 24, 1992, abandoned, which is a continuation of Ser. No. 645,638, Jan. 25, 1991, Pat. No. 5,084,852, which is a continuation of Ser. No. 499,217, Mar. 16, 1990, Pat. No. 5,003,526, which is a continuation of Ser. No. 782,156, Oct. 2, 1985, abandoned, which is a continuation of Ser. No. 169,238, Jul. 16, 1980, abandoned. This application Jun. 7, 1995, Ser. No. 473,737

Int. Cl.⁶ H04N 5/76; 5/78

U.S. Cl. 369—59

8 Claims



1. A disc-shaped record medium for storing digital information in a succession of substantially circular and concentric recording tracks,

wherein each recording track includes a succession of alternating marks and spaces, lengths of successive marks and spaces being modulated in accordance with information to be recorded, the digital information derived from a succession of multi-bit binary code blocks, said digital information being converted to a succession of output pulses having discretely-variable time durations,

wherein each recording track includes lengths on which are recorded marks and spaces representing digital information to be recorded interspersed with lengths on which are recorded supermark synchronization patterns,

wherein the lengths of the succession of marks and spaces are modulated in discrete steps in accordance with the discrete lengths of the succession of said output pulses, and wherein

said record medium includes information thereon which is indicative of a particular location of said information on the record medium.

5,587,984

HOLOGRAM PRINTED ON OPTICAL RECORDING MEDIUM FOR COPY PROTECTION

Hideo Owa, and Seiji Kobayashi, both of Kanagawa, Japan.

assignors to Sony Corporation, Tokyo, Japan


Filed Sep. 8, 1995, Ser. No. 525,191

Claims priority, application Japan, Sep. 13, 1994, 6-218543

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—103

17 Claims



1. An optical recording medium having signals optically recorded therein, the optical recording medium comprising a hologram for recording medium discrimination recorded in an area other than an information recording area in which information signals are recorded.

5,587,985

SIGNAL PROCESSING DEVICE FOR AN OPTICAL INFORMATION REPRODUCING APPARATUS

Kousei Sano, Neyagawa, and Shin-ichi Kadowaki, Hirakata, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Division of Ser. No. 207,859, Mar. 8, 1994. This application

Sep. 25, 1995, Ser. No. 533,527


Claims priority, application Japan, Mar. 9, 1993, 5-47701;

Mar. 10, 1993, 5-48917; Apr. 2, 1993, 5-76636

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—124

29 Claims



1. An apparatus capable of optically reproducing information from a recording medium, the apparatus comprising:

an optical pickup head for outputting a first signal mainly including information recorded at a desired position and a second signal including information recorded at positions

adjacent to the desired position, when informations are to be reproduced by a light beam from the recording medium having tracks in which the informations are recorded;

an operation circuit for receiving the first and second signals and for performing an adding or subtracting operation;

a variable gain amplifier for controlling the level or polarity of the first or second signal which is input into the operation circuit; and

a signal processing means for receiving the first signal or a signal output from the operation circuit and for outputting a signal for adjusting a gain of the variable gain amplifier.

5,587,986

ON-TRACK DETECTING CIRCUIT FOR USE IN TRACKING SERVO APPARATUS

Kyota Funamoto, Tokorozawa, Japan, assignor to Pioneer Electronic Corporation, Tokyo, Japan


Filed Oct. 6, 1995, Ser. No. 540,402

Claims priority, application Japan, Oct. 14, 1994, 6-276140

Int. Cl. G11B 7/00

3 Claims

U.S. Cl. 369-124



1. An on-track detecting circuit in a tracking servo apparatus of an optical disk apparatus for recording or reproducing to/from a disk having wobble pits formed by deviating from a track center in the opposite directions for the disk radial direction by a predetermined track pitch and clock pits formed on the track center, comprising:

- sample and hold circuits for sampling and holding outputs from at least the two wobble pits existing in a same servo byte;
- an adding circuit for adding outputs of said sample and hold circuits;
- a mean value circuit for obtaining a mean value of an output of said adding circuit;
- a sample and hold circuit for sampling and holding an output from the clock pit, and
- a comparator for comparing an output of said mean value circuit and an output of said sample and hold circuit obtained by sampling and holding the output from the clock pit, wherein said comparator generates an on-track signal for setting an on-track state when the output of said sample and hold circuit from the clock pit is larger than the output of said mean value circuit.

5,587,987

INFORMATION RECORDING METHOD HAVING A LIQUID CRYSTAL SUBSTRATE

Masato Okabe, Tokyo, Japan, assignor to Dai Nippon Printing Co., Ltd., Tokyo, Japan

Filed Sep. 22, 1995, Ser. No. 532,153


Claims priority, application Japan, Sep. 22, 1994, 6-227944

Int. Cl. G11B 7/00

7 Claims

U.S. Cl. 369-126

1. An information recording method using an integrated type of information recording system having a photoconductive layer, a



dielectric interlayer, a liquid crystal recording layer and an electrode layer stacked on a transparent electrode in the described order, wherein the photoconductive layer is exposed to information light with voltage applied across both electrodes of the system so that the liquid crystals are oriented to record image information depending on the quantity of the exposure light, characterized in that:

from the following equations:

$$V_S(t) = \frac{C_M C_L}{C_S C_M + C_M C_L + C_L C_S} V_{AP}$$

$$V_M(t) = \frac{C_L C_S}{C_S C_M + C_M C_L + C_L C_S} V_{AP}$$

$$V_L(t) = \frac{C_S C_M}{C_S C_M + C_M C_L + C_L C_S} V_{AP}$$

$$I_S + C_S(dV_S/dt) = I_M + C_M(dV_M/dt) \\ = I_L + C_L(dV_L/dt)$$

$$V_S + V_M + V_L = V_{AP}$$

$$dV_M/dt = \frac{C_L I_S - (C_S + C_L) I_M + C_S I_L}{C_S C_M + C_M C_L + C_L C_S}$$

$$dV_L/dt = \frac{C_M I_S + C_S I_M - (C_S + C_M) I_L}{C_S C_M + C_M C_L + C_L C_S}$$

$$V_M(t + \Delta t) = V_M(t) + (dV_M/dt)\Delta t \\ V_L(t + \Delta t) = V_L(t) + (dV_L/dt)\Delta t$$

where V_{AP} is the voltage applied across both electrodes; C_S , C_L and C_M are the capacities of the photoconductive layer, the liquid crystal recording layer and the interlayer, respectively; V_S , V_L and V_M are the voltages applied on the respective layers; I_S , I_L and I_M are the currents flowing through the respective layers; and $V_S(0)$, $V_M(0)$ and $V_L(0)$ are the voltages applied on the respective layers just after the application of voltages, changes-with-time in the voltages of exposed and unexposed portions of the liquid crystal recording layer with respect to the photoconductive layer having a varying dark current value are found by varying the applied voltage, and the applied voltage and the value of the dark current through the photoconductive layer are determined such that when the voltage of the unexposed portion of the liquid crystal recording layer reaches the threshold voltage of the liquid crystal recording layer, the difference in voltage between the exposed and unexposed portions of the liquid crystal recording layer reaches a maximum, so that information is recorded with the photoconductive layer and at the applied voltage, where a potential difference is obtained, which is at least one half of the difference maximum contrast in the voltages applied on the liquid crystals at the exposed and unexposed portions of the liquid crystal recording layer.

5,587,988

COMPUTER CONTROLLED DISK STORAGE UNIT WITH A TELESCOPIC ARM FOR READING AND WRITING INFORMATION ON A DISK LOCATED IN A MAGAZINE


Gilles Boulanger, 2100 Route 112 #106, Magog, Quebec, Canada

Filed Nov. 17, 1993, Ser. No. 153,917

Int. Cl. G11B 17/24

U.S. Cl. 369-178

3 Claims




1. A computer controlled disk storage unit used for selecting any one of a plurality of disks and reading and/or writing from and onto any of the said disks, said unit comprising:

- a toroidal magazine means comprising a plurality of slots to hold individual disks in place and to allow rotation of said disks, each one of said slots includes a pressure plate on each side of the slot located on the inside of the slot so that the pressure plates are freely rotating against said slot for firmly holding the disks, rubber caps on each side of the slot located on the inside of the slot with each rubber cap adjacent a side of one of said pressure plates, said rubber caps fit inside a center hole of one of said plurality of disks to firmly hold and center the disk, and a friction gear on one side of the slot located on the outside of the slot on a side of one of the pressure plates opposite to the side the rubber cap is located on;

a player/recorder means embodied in the form of a telescopic arm situated in the middle of the toroidal magazine and able to align itself with any one of the slots containing disks and said telescopic arm provided with means for extending itself to reach any one of said disks situated inside any one of said slots to rotate and read or write information from and onto said disk while the disk is in said slot;

said telescopic arm made of two parallel prongs extending outwardly from its base, one of said prongs being a drive shaft with a second friction gear on one end of said shaft that engages with the friction gear located on the outside of the slot of a selected disk to induce rotation using power from a motor situated at the base of the telescopic arm, and the other of said prongs holding a data reading/writing means to read and/or write data from/onto said selected disk in said slot.



5,587,990

OPTICAL DISC SYSTEM AND OPTICAL DISC THEREFOR

Tetsu Watanabe, and Yoshio Aoki, both of Tokyo, Japan, assignors to Sony Corporation, Tokyo, Japan


Continuation-in-part of Ser. No. 383,351, Feb. 3, 1995, Pat. No. 5,533,001, which is a division of Ser. No. 277,357, Jul. 19, 1994, Pat. No. 5,392,263, which is a continuation of Ser. No. 761,874, Sep. 13, 1991, abandoned. This application Jul. 7, 1995, Ser. No. 499,331

Claims priority, application Japan, Jan. 31, 1990, 2-21210

Int. Cl. G11B 7/24

U.S. Cl. 369-275.2

4 Claims



1. An optical recording medium used in an optical recording and/or reproducing apparatus having at least one light source for radiating a light beam and at least one objective lens for converging the light beam on an optical axis thereof, the wavelength of the light beam radiated from the light source falling within a range of 635 to 650 nm, the numerical aperture of the objective lens being 0.6, said medium comprising:

- a recording layer; and
- a light-transmitting cover layer provided on the one surface of said recording layer and transmitting the light beam to irradiate on said recording layer, wherein the thickness of the light transmitting cover layer falls within a range of 0.55 to 0.6 mm.

5,587,989

CARTRIDGE CHANGING APPARATUS INCLUDING A PAIR OF BASE CARRIERS AND A PAIR OF SLIDE CARRIERS

Tatsunori Fujiwara; Yasuyuki Nakanishi; Koutarou Oka; Kei Shirahata, and Shigehiro Itou, all of Hyogo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Apr. 18, 1995, Ser. No. 423,751

Claims priority, application Japan, Oct. 3, 1994, 6-238903

Int. Cl. G11B 3/00; 17/04; 17/08

U.S. Cl. 369-178

17 Claims

1. A cartridge changing apparatus for replacing a cartridge containing a disc, said cartridge changing apparatus comprising: a plurality of holders, each holding a cartridge inserted therein; a plurality of pins fixed to said plurality of holders; a loading motor, loading any cartridge held in any of said plurality of holders; and a synchronizing shaft, transmitting a rotating force of said loading motor;

5,587,991

RECORDING MEDIUM, SIGNAL RECORDING APPARATUS THEREOF, AND SIGNAL REPRODUCING APPARATUS THEREOF

Daiki Nabeshima, and Naoki Ozaki, both of Yokohama, Japan, assignors to Kabushiki Kaisha Toshiha, Kawagawa-ken, Japan


Filed Jan. 18, 1995, Ser. No. 375,428

Claims priority, application Japan, Mar. 16, 1994, 6-046010

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—275.3

7 Claims



4. A signal recording apparatus of a recording medium, comprising:

- DSV calculating means for calculating a DSV of a signal wave form recorded on the recording medium;
- cancel code generating means for generating a cancel code for suppressing a DC component of the signal wave form corresponding to the DSV calculated by said DSV calculating means; and
- recording means for connecting a synchronous code and record data to the cancel code generated by said cancel code generating means and recording the cancel code, the synchronous code, and the record data on the recording medium so that the cancel code and the synchronous code are adjacently disposed, the synchronous code being adapted for synchronizing with data.

5,587,992

SAMPLED-SERVO TYPE OPTICAL DISK HAVING CLOCK PITS ARRANGED OFFSET FROM EACH OTHER IN THE DISK RADIAL DIRECTION

Hideki Hayashi, Tsurugashima, Japan, assignor to Pioneer Electronic Corporation, Tokyo, Japan


Filed Nov. 17, 1994, Ser. No. 343,947

Claims priority, application Japan, Nov. 19, 1993, 5-290959

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—275.4

4 Claims



1. An optical disk of a sampled servo type comprising:
- a plurality of tracks which are spaced from each other in a radial direction of the disk;
 - a plurality of synchronization pits, each disposed on a corresponding one of said tracks in a servo area of the disk and aligned with each other in the radial direction of the disk; and
 - a plurality of clock pits formed in said servo area on each of said tracks and arranged to deviate from each other in a reading direction of said disk per adjacent track.

5,587,993

OPTICAL TAPE CARTRIDGE HAVING IMPROVED TAPE MOVEMENT MECHANISM


David P. Gregg, Culver City, Calif., assignor to DiscoVision Associates, Irvine, Calif.

Filed Jun. 30, 1994, Ser. No. 268,992

Int. Cl.⁶ G11B 7/24

U.S. Cl. 369—291

26 Claims



1. An optical tape cartridge suitable for playing by a player, the player associated with a voltage supply capable of supplying said optical tape cartridge with a controllably variable voltage, said optical tape cartridge comprising:

- a sealed cartridge housing;
- first and second tape reels disposed within said sealed cartridge housing, said first and second tape reels each being freely rotatable and acting as tape supply and tape take up reels;
- an optical tape having a first surface end and an optically recordable side, said optical tape being wound on and thereby coupling each of said first and second reels by a
- an optical tape having a first surface and an optically recordable side, said optical tape being wound on and thereby coupling each of said first and second reels by a segment of said optical tape so that said optically recordable side faces away from each of said reels, said optical tape further having a conductive layer extending substantially the length thereof, said conductive layer being grounded;

sealed window means being positioned on a surface of said sealed cartridge housing and disposed across a portion of said segment of said optical tape for enabling optical reading from said segment; and

conductive guide means for guiding said segment of said optical tape past said sealed window means, said conductive guide means having a portion disposed adjacent said sealed window means and being connected to the controllably variable voltage supplied by the voltage supply, said first surface of said segment thereby being maintained a predetermined, substantially fixed distance from said sealed window means by electrostatically attracting said conductive layer of said segment toward said conductive guide means with an attractive force controlled by the supplied voltage, said attractive force being changeable by corresponding changes in applied voltage so that a preselected fixed distance is maintained between said conductive guide means and said segment of optical tape.

5,587,994

CARTRIDGE USED FOR A DISC-SHAPED RECORDING MEDIUM

Toshikazu Nagaura, Nara; Zenjiro Yamashita, Yamatoko-riyama; Kazuhiko Arikawa, Yamabe-gun, and Kenji Ohta, Kitakatsuragi-gun, all of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 63,950, May 20, 1993, abandoned.


This application Oct. 11, 1994, Ser. No. 321,451

Claims priority, application Japan, Jun. 3, 1992, 4-142732

Int. Cl.⁶ G11B 17/03; 23/00

U.S. Cl. 369—291

22 Claims



1. A cartridge used for a disc-shaped recording medium comprising:

- a recording medium which is shaped into a disc having a center hole for use in positioning and a recessed section formed around the center hole;
 - a clamping plate formed into a hat shape having a flat brim for clamping the recording medium by the use of magnetic force, the flat brim having a top and bottom surface and an outer edge surface perpendicular to the top and bottom surfaces that forms an outermost edge surface of the clamping plate the flat brim extending outwardly in a radial direction, the clamping plate being placed in the recessed section so that, the outermost edge surface is located totally in the recessed section and is completely surrounded by a wall of the recessed section, with the total area of the bottom surface in direct physical contact with the recessed section, a part of the recording medium being sandwiched between the bottom surface and a turntable that is inserted into the center hole; and
 - a case for housing the recording medium and the clamping plate so as to permit them to freely rotate therein, the case being provided with a through hole which allows the turntable to be removably inserted therein.
- wherein the recessed section is formed into a shape that is recessed toward the through hole and houses the clamping plate so as to permit it to move therein, the clamping plate being provided with a height dimension in a rotational-axis direction of the recording medium that is set to be greater than the distance between the recording medium and the inner surface of the case.

5,587,995

SERIAL CONTROLLER

Makoto Takebe, and Masao Hagiwara, both of Hiratsuka, Japan, assignors to Kabushiki Kaisha Komatsu Seisakusho, Japan

Division of Ser. No. 861,862, Jun. 17, 1992, Pat. No.

5,461,617. This application May 8, 1995, Ser. No. 436,931

Claims priority, application Japan, Dec. 26, 1989, 1-336888; Dec. 27, 1989, 1-343482; Jan. 30, 1990, 2-19933; Oct. 30, 1990, 2-113743


Int. Cl.⁶ H04J 3/14

U.S. Cl. 370—248

6 Claims

1. A serial controller in which a plurality of nodes and a main controller are connected in series through a signal line, the main controller including:

- data transmission means for transmitting data frame signals serially at a predetermined period to the plurality of nodes;



reception means for receiving the data frame signals inputted through the plurality of nodes,

each node including:

- reception time interval measurement means for measuring a reception time interval of successive data frame signals;
- a plurality of measured value storage means for storing measured values measured by the reception time interval measurement means for a plurality of reception periods, respectively;
- broken-line detection time setting reference value selection means for selecting one of the measured values which is most frequently measured in the plurality of reception periods stored in the plurality of measured value storage means and, setting the selected one of the measured values as a reference value for a broken-line detection time setting;
- broken-line detection time setting means for setting the broken-line detection time on the basis of the reference value selected by the broken-line detection time setting reference value selection means; and
- comparison means for comparing the set value set by the broken-line detection time setting means with the measured value measured by the reception time interval measurement means for each reception interval and outputting a broken-line detection signal when the measured value is greater than the set value.

5,587,996

METHOD OF RADIO-LINE RELIEF AND RADIO EQUIPMENT IN SDH NETWORK

Shingo Mizuno, Kawasaki, Japan, assignor to Fujitsu Limited, Kanagawa, Japan


Filed Sep. 18, 1995, Ser. No. 529,663

Claims priority, application Japan, Feb. 2, 1995, 7-015749

Int. Cl.⁶ H04B 10/08

U.S. Cl. 370—228

16 Claims



1. A method of relieving a radio line in a synchronous digital hierarchy (SDH) network in which a radio transmission line is introduced between optical transmission lines each of which has a plurality of optical lines, comprising the steps of:
- providing radio working lines corresponding to respective ones of optical lines and providing one radio standby line;
 - monitoring occurrence of failure in each optical line and occurrence of failure in the radio working lines;

when occurrence of failure in an optical line has been detected, making rank for relief of the radio working line corresponding to this optical line lower than rank for relief of radio working lines corresponding to optical lines that have not failed; and when failure has occurred in two or more radio working lines, transmitting data, which is to be sent to a radio standby line having a higher rank for relief, via the radio standby line and relieving the radio working lines in which the failure has occurred.

5,587,997

METHOD AND APPARATUS FOR DETERMINING WHEN ALL PACKETS OF A MESSAGE HAVE ARRIVED


David M. Jacobson, Santa Clara, Calif., assignor to Hewlett-Packard Company, Palo Alto, Calif.

Filed Feb. 24, 1995, Ser. No. 393,650

Int. Cl.⁶ H04J 3/22

U.S. Cl. 370—253

26 Claims



1. An apparatus for determining when all packets of a message sent across a computer network have arrived at their destination, comprising:

a counter located at at least one source computer, said counter storing an initial value therein and being adapted to assign a delta value to each packet in a message, wherein a first delta value is assigned to each packet in a message but the last packet;

means for decrementing said counter for each packet sent, wherein said counter stores a second delta value that is to the initial value store in the counter decreased by the number of packets previously sent, and wherein said second delta value is assigned to said last packet; and

an accumulator located at a destination computer, said accumulator being adapted to extract said delta value from each packet of said message; wherein said destination computer is notified that all packets in said message have arrived only when the sum of said extracted delta values stored in said accumulator is equal to the initial value stored in said accumulator.

5,587,998

METHOD AND APPARATUS FOR REDUCING RESIDUAL FAR-END ECHO IN VOICE COMMUNICATION NETWORKS

Patrick M. Velardo, Jr., Belleville, and Woodson D. Wynn, Basking Ridge, both of N.J., assignors to AT&T, Holmdel, N.J.

Filed Mar. 3, 1995, Ser. No. 398,272


Int. Cl.⁶ H04B 3/20

U.S. Cl. 370—289

35 Claims

6. A method for processing FAR-IN communication signals received by a local network from a remote network, thereby to reduce energy content that is attributable to echoes, returned by the remote network, of NEAR-IN signals that were placed in the local network for transmission to the remote network, the method comprising:

- measuring a delay between the NEAR-IN signals and the arrival of corresponding echoes in the FAR-IN signals;
- analyzing the FAR-IN signals into a plurality of frequency sub-band components to be referred to as FAR-IN sub-band



signals, delaying the NEAR-IN signals by the measured delay, and analyzing the delayed NEAR-IN signals into a plurality of frequency sub-band components, to be referred to as NEAR-IN sub-band signals;

c) processing a copy of each NEAR-IN sub-band signal to create a time-varying signal which represents the smoothed energy content of the NEAR-IN sub-band signal delayed by the measured delay and attenuated by an estimated transmission loss for echoes, said time-varying signal to be referred to as a TEMPLATE;

d) in a non-linear processor, passing each FAR-IN sub-band signal substantially without attenuation if it exceeds a threshold derived at least in part from the corresponding TEMPLATE;

e) in the non-linear processor, attenuating each FAR-IN sub-band signal if it lies within a defined range below the corresponding said threshold, and

f) synthesizing the nonlinearly processed FAR-IN sub-band signals to form an echo-reduced fullband FAR-IN signal.

5,587,999

D CHANNEL PACKET COMMUNICATION SYSTEM AND A METHOD OF D CHANNEL PACKET COMMUNICATION

Koji Endo, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan


Filed Aug. 14, 1995, Ser. No. 514,743

Claims priority, application Japan, Aug. 12, 1994, 6-190332

Int. Cl.⁶ H04J 3/12; H04L 12/56

U.S. Cl. 370—352

9 Claims



1. A D channel packet communication system in a private branch exchange having a plurality of line circuits, each one of said plurality of line circuits connecting a plurality of subscriber lines for packet terminals to said private branch exchange, a plurality of trunk circuits, each one of said plurality of trunk circuits connected to a plurality of subscriber lines of a public ISDN switching system in a network, a time division switch for providing connection paths between each one of said plurality of line circuits and each one of said plurality of trunk circuits and a call processor for controlling overall operations of said private branch exchange, said D channel packet communication system comprising:

a conversion control unit comprising

means for receiving first conversion information including first connection control information allocated to a D channel packet transferred between one of said packet terminals and said private branch exchange, and second connection control information allocated to D channel packet transferred between said private branch exchange and said network;

means for deriving second conversion information having correspondences between said first connection control information and said second connection control information at a beginning of D channel packet communication based on said first conversion information, said deriving means cooperating with said receiving means; and

converting means for converting said first connection control information in said D channel packet received from one of said packet terminals to said second connection control information for a D channel packet to be sent to said network, converting said second connection control information in said D channel packet received from said network to said first connection control information for said D channel packet to be sent to one of said packet terminals, based on said second conversion information, said converting means cooperating with said receiving means;

a plurality of first switching control units, each one of said plurality of first switching control units connecting to one of said plurality of subscriber lines for one of said packet terminals, identifying D channel information received from one of said packet terminals, establishing a path to said conversion control unit where a D channel packet is being received, and establishing a path to said call processor where information other than said D channel packet is being received;

a plurality of second switching control units; each one of said plurality of second switching control units connected to one of said plurality of subscriber lines of said public ISDN switching system, identifying D channel information from said public ISDN switching system, establishing a path to said time division switch where a D channel packet is being received and establishing a path to said call processor where information other than said D channel packet is being received; and

a plurality of permanent connection paths in said time division switch, each making a permanent connection between said conversion control unit and one of said second switching control units.

5,588,000

APPARATUS FOR REORDERING DATA FRAMES WITHIN AN INTERFACE DEVICE


Wayne T. Rickard, Oceanside, Calif., assignor to Emulex Corporation, Costa Mesa, Calif.

Filed Mar. 27, 1995, Ser. No. 410,712

Int. Cl.⁶ H04L 12/54

U.S. Cl. 370—428

6 Claims



1. An interface device for coupling a receiving device to a communications link and for ensuring that frames of data received by the interface device, each frame being included within a

sequence of frames, are communicated to the receiving device in a predetermined order defined by an external transmitting device, the interface device including:

(a) a control circuit for processing information contained in each frame of data; and

(b) a comparator window circuit coupled to, and controlled by, the control circuit, wherein each valid frame received by the interface device is associated with a value that indicates the relative position of that frame within the predetermined order, the comparator window circuit having:

- a missing frame window storing means for storing a missing frame window which indicates whether the last received frame is the next expected frame in the order defined by the external transmitting device,
- a counter, operatively coupled to the control circuit, for storing the value associated with the next expected frame and capable of incrementing the value stored in the counter by a predetermined value upon command from the control circuit when the missing frame window indicates that the last received frame is the next expected frame,

(3) a comparator, coupled to the counter and the control circuit, for comparing a value associated with the next expected frame with a value associated with a last received frame and indicating whether the value associated with the last received frame is within a predetermined range of values relative to the value of the next expected frame, and

- a shift register coupled to the control circuit and coupled to an input to the missing frame window storing means, such that a missing frame window input to the missing frame window storing means may be shifted under the control of the control circuit prior to being stored in the missing frame window storing means when the missing frame window indicates that the last received frame is the next expected frame.

5,588,001

Patent Not Issued For This Number

5,588,002

MULTIPLEX TRANSMISSION APPARATUS FOR SUPPORTING PRIORITIZED COMMUNICATIONS AMONG A PLURALITY OF NETWORK NODES

Toshiaki Kawanishi, Yoshikazu Nobutoki, Seiji Hirano, and Koji Terayama, all of Hiroshima, Japan, assignors to Mazda Motor Corporation, Hiroshima, Japan

Continuation of Ser. No. 100,965, Aug. 3, 1993, abandoned.


This application Mar. 22, 1995, Ser. No. 408,190

Claims priority, application Japan, Aug. 6, 1992, 4-210245

Int. Cl.⁶ H04L 12/46

U.S. Cl. 370—462

7 Claims




1. A multiplex transmission apparatus having a plurality of control units connected independently of one another over a plurality of multiplex transmission lines, each of said plurality of

means for inhibiting, in the central processing unit, transmission of the signal which is to be transmitted to the first transmission line, if it is judged that the received signal is identical with the signal to be transmitted to the first transmission line


U.S. Cl. 370—516 9 Claims

U.S. Cl. 370—468 23 Claims




U.S. Cl. 370—346 6 Claims


1. A method of tracking assets comprising the steps of:
affixing a battery powered tracking unit to each asset to be tracked;
communicating with each tracking unit from a central station to receive from each tracking unit identification (ID), location, battery strength, and signal quality;



U.S. Cl. 371—3 10 Claims




U.S. Cl. 371-21.2 13 Claims



U.S. Cl. 371-27 8 Claims

1. A method for generating test patterns for use with a scan circuit to detect a degenerative failure in a synchronous sequential circuit having a memory element comprising a predetermined scan register and a combinational circuit for inputting a value from an



external input of the synchronous sequential circuit and said memory element, and for outputting a value to an external output of the synchronous sequential circuit and said memory element, said method for generating test patterns comprising:

- a step of generating, for an undetected first failure, a first test pattern for use in a combinational circuit; and
- a step of pattern expansion for generating a second test pattern for detecting a second failure by changing the external input value of the synchronous sequential circuit, with value set in the predetermined scan register of said memory element fixed, with regard to the first test pattern generated in said generating step; and
- a step of adding a mark for use when the undetected failure cannot be checked in the second test pattern.

5,588,009


PERSONAL PAGING, COMMUNICATIONS, AND LOCATING SYSTEM

Craig A. Will, 37675 Fremont Blvd. No. 23, Fremont, Calif. 94536

Filed Feb. 3, 1994, Ser. No. 191,111
Int. Cl.⁶ H04L 1/18

U.S. Cl. 371-33

25 Claims



1. A method for transmitting a message to an individual, comprising the steps of:

- originating said message addressed to said individual;
- transmitting the message to a central communications station;
- receiving and storing the message at said central communications station;
- creating a packet containing data from the message;
- transmitting said packet to a communications unit carried by the individual by the steps of:
- (1) computing an error checking code and adding said code to the packet;
- (2) adding a code to the packet identifying said communications unit;
- (3) transmitting the packet by means of radio to the communications unit;
- (4) receiving the packet at the communications unit;
- (5) computing an error checking code;
- (6) determining whether the packet has been correctly received by comparing the error checking code com-

puted at the communications unit with the error checking code contained in the packet;

- (7) constructing a packet at the communications unit comprising a code identifying the communications unit;
- (8) adding a code identifying and thus acknowledging the received packet to said packet constructed at the communications unit, should the received packet contain a correct error checking code;
- (9) transmitting the packet constructed at the communications unit from the communications unit via a medium selected from the group consisting of infrared light and ultrasonic sound to one or more of a plurality of remote stations, should the received packet contain a correct error checking code;
- (10) receiving the packet constructed at the communications unit from the communications unit at a remote station and temporarily storing it;
- (11) transmitting the packet constructed at the communications unit from said remote station, by means of a communications unit carried by the individual, until all data in the message has been transmitted from the central station to the communications unit;

repeating the steps of creating the packet containing data from the message and transmitting the packet to a communications unit carried by the individual, until all data in the message has been transmitted from the central station to the communications unit;

displaying said message to the individual.

5,588,010


PARALLEL ARCHITECTURE ERROR CORRECTION AND CONVERSION SYSTEM

William R. Hardell, Jr., and Amjad Z. Qureshi, both of Austin, Tex., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jul. 29, 1994, Ser. No. 282,334
Int. Cl.⁶ H03M 13/00; G06F 11/10

U.S. Cl. 371-37.6

11 Claims



1. An error correction code conversion system, comprising:

- means for generating error correction code checkbits from uncorrected input data;
- means for identifying corrections needed in the generated error correction code checkbits based upon the uncorrected input data and input checkbits related thereto; and
- means for correcting the generated error correction code checkbits responsive to the means for identifying.

5,588,011 TUNED VITERBI DETECTOR AND EQUALIZER SYSTEM


C. M. Riggle, 12995 Morris Trail, Colorado Springs, Colo. 80908-3232, assignor to C. M. Riggle, Colorado Springs, Colo.

Continuation of Ser. No. 288,475, Aug. 10, 1994, abandoned.
This application Feb. 5, 1996, Ser. No. 596,927

Int. Cl.⁶ G06F 11/10; G11B 5/09

U.S. Cl. 371-43

37 Claims



1. A method for use in detecting an input data stream via a Viterbi system, said method comprising the steps of:

providing a Viterbi detector capable of receiving input data samples and converting said input data samples into a digital output signal indicative of data stored on a recording medium or transmitted over a communication channel, said Viterbi detector comprising a trellis structure including:

- a plurality of nodes arranged in a plurality of rows and columns, each row associated with a distinct state of said Viterbi detector and each column associated with a distinct level of said Viterbi detector;
- a plurality of state metrics, each state metric associated with one of said distinct states of said Viterbi detector; and
- a plurality of paths between nodes in adjacent levels in said Viterbi detector, each path having a corresponding transition reference value;

tuning a transition reference value associated with a first path of said trellis structure by changing said transition reference value from a first value to a second value, said first path beginning at a state in a first level and terminating at a state in a second level;

calculating a transition metric for said first path using said second value of said transition reference value and at least one of said input data samples;

combining said transition metric corresponding to said first path with a state metric corresponding to said beginning state in said first level to update said state metric associated with said terminating state in said second level; and

choosing a most likely path through said trellis structure using said updated state metric, said most likely path being representative of said digital output signal;

wherein said step of tuning improves the error rate performance of said Viterbi detector.

5,588,012

APPARATUS AND METHOD FOR ENSURING DATA IN EXTERNAL STORAGE SYSTEM

Yumiko Oizumi, Kawasaki, Japan, assignor to Fujitsu Limited, Japan

Filed Dec. 17, 1992, Ser. No. 992,450


Claims priority, application Japan, Feb. 10, 1992, 4-023750
Int. Cl.⁶ G11C 29/00

U.S. Cl. 371-51.1

13 Claims

1. An apparatus for ensuring data written to and read from an external storage system comprising:

- a host device;
- at least one external storage device for writing and reading data to and from a recording medium, said external storage device having a device controller including a buffer and a check data verification circuit; and
- a data transfer external storage controller disposed between said host device and said device controller for controlling said external storage device in accordance with a command issued



from a host device, said external storage controller transferring read data from said device controller to said host device and transferring write data from the host device to said device controller;

wherein said external storage controller adds check data to said write data from said host device, each time write data is transferred from said host device to said external storage device, said storage controller calculating said check data using distinctive information on a position of said external storage device in which said write data is written as a seed value so that said check data is representative of both data content and location, and

wherein said external storage controller transfers said write data, to which said check data is added, to said device controller, and said device controller buffers the data in said buffer, and said check data verification circuit verifies that the write data is correct using said check data,

said device controller further transferring said write data and said check data to said external storage device if the check data circuit verifies that the write data is correct.

5,588,013


POLARIZATION CONTROLLED TUNEABLE RING LASER

Paul Reitz, Palmyra, and Hatem Abdelkader, Harrisburg, both of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Nov. 30, 1994, Ser. No. 347,537
Int. Cl.⁶ H01S 3/098

U.S. Cl. 372-19

6 Claims



1. A controlled polarization, tuneable ring laser, comprising:

- (a) A source for optical pumping coupled to means for multiplexing light signals;
- (b) A section of fiber twisted to induce a selected amount of birefringence in said section of twisted fiber connected to said means for multiplexing light signals;
- (c) A first segment of optical fiber connecting said section of twisted fiber to a polarizing optical isolator polarizer;
- (d) Means for optically selecting a mode of light traveling in said ring laser to a selected bandwidth connected to said polarizing optical isolator, said means for tuning light connected to an output coupler; and

- (e) A second segment of optical fiber connected to said output coupler, said second further connected to a section of doped optical fiber, said doped fiber further connected to said multiplexer, thereby completing a laser ring cavity.


5,588,014

OPTICAL WAVELENGTH CONVERTING APPARATUS
Yoji Okazaki, Chiaki Goto, Hiroaki Hyuga, and Akinori Harada, all of Kanagawa-ken, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan
Division of Ser. No. 208,139, Mar. 9, 1994, Pat. No. 5,432,807, which is a division of Ser. No. 843,719, Feb. 28, 1992, Pat. No. 5,315,433. This application Apr. 6, 1995, Ser. No. 417,673
Claims priority, application Japan, Feb. 28, 1991, 3-33954; Mar. 1, 1991, 3-36098; Apr. 12, 1991, 3-79849; Apr. 15, 1991, 3-82333; Apr. 17, 1991, 3-85322; Apr. 17, 1991, 3-85595; Apr. 18, 1991, 3-86404; Apr. 18, 1991, 3-86617

Int. Cl.⁶ H01S 3/10

U.S. Cl. 372-22

6 Claims



1. An optical wavelength converting apparatus, which comprises:

- a crystal of a nonlinear optical material, which is located in a resonator of a laser diode pumped solid laser, said crystal converting a laser beam, which has been obtained from solid laser oscillation and serves as a fundamental wave which impinges upon said crystal, into its second harmonic by effecting the type II of phase matching between said fundamental wave and its second harmonic; and
- a wavelength selecting device, which is located in said resonator and selects the wavelength of said laser beam obtained from the solid laser oscillation such that the wavelength of said laser beam may be adjusted appropriately.

5,588,015

LIGHT EMITTING DEVICES BASED ON INTERBAND TRANSITIONS IN TYPE-II QUANTUM WELL HETEROSTRUCTURES


Rui Q. Yang, Houston, Tex., assignor to University of Houston, Houston, Tex.

Filed Aug. 22, 1995, Ser. No. 518,101

Int. Cl.⁶ H01S 3/19

U.S. Cl. 372-45

21 Claims



1. A light emitting device comprising:

- a first cladding region of semiconductor material having conduction and valence allowed energy bands defined by corresponding band edges spaced apart by an energy band-gap;
a second cladding region of semiconductor material having conduction and valence allowed energy bands defined by corresponding band edges spaced apart by an energy band-gap;
a first quantum well region of semiconductor material having conduction and valence allowed energy bands defined by corresponding band edges spaced apart by an energy band-gap, said first quantum well region which is adjacent to said first cladding region having at least one energy state residing in said conduction band of said first quantum well region; and
a second quantum well region of semiconductor material having conduction and valence allowed energy bands defined by corresponding band edges spaced apart by an energy band-gap, said second quantum well region sandwiched between said first quantum well region and second cladding region, said first and second quantum well regions forming a type-II heterojunction, said second quantum well region having at least one energy state which is lower in energy than said energy state in said conduction band of said first quantum well region and is within said valence band of said second quantum well region, under a bias voltage each of said energy states residing within said allowed energy bands of said adjacent cladding region and simultaneously residing within at least one of the band-gaps of said adjacent quantum well region and the other cladding region.

5,588,016

SEMICONDUCTOR LASER DEVICE

Hiroshi Otoma; Nobuaki Ueki; Hideki Fukunaga; Hideo Nakayama; Yasuji Seko, and Mario Fuse, all of Kanagawa, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan

Filed Sep. 5, 1995, Ser. No. 523,389

Claims priority, application Japan, Sep. 6, 1994, 6-212650

Int. Cl.⁶ H01S 3/19

U.S. Cl. 372-46

16 Claims



1. A semiconductor laser device, comprising:

- a substrate;
- a first cladding layer made of semiconductor material of a first conductivity type and layered on said substrate;
- a quantum well active layer made of semiconductor material and layered on said first cladding layer;
- a second cladding layer layered on said quantum well active layer, said second cladding layer being made of semiconductor material of a second conductivity type that is opposite to said first conductivity type;
- an intermediate layer made of semiconductor material of said first conductivity type or nonconductive type semiconductor, said intermediate layer being layered on said second cladding layer;
- a contact layer made of semiconductor material of said first conductivity type of nonconductive type semiconductor, said contact layer being layered on said intermediate layer;
- a mixed-crystal region of said first conductivity type in said intermediate layer, said second cladding layer, and said quantum well active layer, said mixed-crystal region not extending under said contact layer; and
- a low resistance region of said second conductivity type extended over a range from said contact layer, through said intermediate layer, to said second cladding layer, said low resistance region being isolated from said mixed-crystal region by said intermediate layer.

5,588,017

OPTOELECTRONIC SEMICONDUCTOR DEVICE, SYSTEM FOR OPTICAL GLASS FIBRE COMMUNICATION HAVING SUCH A DEVICE, SEMICONDUCTOR DIODE LASER FOR USE IN SUCH A DEVICE, AND METHOD OF MANUFACTURING SUCH A DEVICE

Maurice Groten, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed May 22, 1995, Ser. No. 446,977

Claims priority, application European Pat. Off., May 24, 1994, 94201450

Int. Cl.⁶ H01S 3/08; 3/19

U.S. Cl. 372-49

19 Claims



1. A optoelectronic semiconductor device (100) comprising a semiconductor diode laser (10) which at a first side (50) thereof emits a first radiation beam (80) with a first wavelength (λ_1) and which forms a radiation waveguide (3) for a second radiation beam (90) with a second wavelength (λ_2) greater than the first wavelength (λ_1), which second beam (90) can enter the semiconductor diode laser (10) at the first side (50), and a semiconductor photodiode (20) which is present at a second side (60) of the semiconductor diode laser (10) opposed to the first side (50), which is aligned relative to the semiconductor diode laser (10), and which is sensitive to radiation of the second wavelength (λ_2), characterized in that the semiconductor diode laser (10) and the semiconductor photodiode (20) are discrete semiconductor components which are provided in series along a single straight radiation path, and the semiconductor device (100) is provided with coating means (51, 61, 71) whereby during use the major portion of the emission of the semiconductor diode laser (10) is formed by the first radiation beam (80), substantially exclusively the first radiation beam (80) issues from the first side (50) of the semiconductor diode laser (10), and substantially the entire second radiation beam (90) is capable of reaching the semiconductor photodiode (20).

5,588,018

METALLURGICAL CONTAINER COMPRISING A HEARTH BOTTOM ELECTRODE

Philippe Destannes, Metz, France, assignor to Usinor Sacilor Societe, Puteaux, and Clecim Societe, Cergy Pontoise Cedex, both of France

Filed Oct. 14, 1994, Ser. No. 324,094


Claims priority, application France, Oct. 15, 1993, 93 12471

Int. Cl.⁶ H05B 7/02

U.S. Cl. 373-72

18 Claims

1. Metallurgical container comprising:
a vessel having an inner refractory lining and a bottom wall;
a hearth bottom electrode extending through the bottom wall of the vessel and through the refractory lining, said bottom electrode comprising and comprising in a superposed condition, 1), a bar which is flush with surface of the refractory lining and 2) a connector which is fastened under the bar, the connector being internally cooled, having an outer diameter smaller than that of a diameter of the bar, and being attached to the bar at an upper front face of the connector at a level situated within a thickness of the refractory lining, and



- a ring, which is interlocked to the bottom wall, which surrounds the connector, and which has an upper face 1) located below the bar and 2) capable of contacting and supporting the bar, wherein the bar includes a skirt which extends downwardly towards the bottom wall and which surrounds the connector laterally.

5,588,019


HIGH PERFORMANCE INDUCTION MELTING COIL
Robert S. Ruffini, Birmingham; Robert J. Madeira, Sterling Heights, and Robert T. Ruffini, Southfield, all of Mich., assignors to Fluxtrol Manufacturing, Inc., Troy, Mich.

Continuation of Ser. No. 866,051, Apr. 8, 1992, Pat. No. 5,418,811. This application Feb. 15, 1995, Ser. No. 389,013

Int. Cl.⁶ H05B 5/16

U.S. Cl. 373-152

19 Claims



1. An induction heating apparatus operable for melting a workpiece, comprising:
a hollow crucible;
an induction melting coil wound to concentrically surrounding said crucible;
power source means operable for establishing an electromagnetic field within said induction melting coil, said electromagnetic field operable for inductively heating said workpiece disposed within said crucible;
support means for maintaining a predetermined spatial relationship between adjacent winding of said induction melting coil; and
insert means for substantially encapsulating said induction melting coil, said insert means made from a homogeneous material comprising powdered ferromagnetic material dispersed in a binder whose composition acts to concentrate said electromagnetic field with respect to said workpiece, said insert means generating a low reluctance path within which said electromagnetic field travels while concomitantly confining said electromagnetic field to inhibit inductive heating of auxiliary conductive materials located in close proximity to said induction melting coil.

5,588,020

SPREAD SPECTRUM CDMA COMMUNICATIONS SYSTEM


Donald L. Schilling, Sands Point, N.Y., assignor to InterDigital Technology Corporation, Wilmington, Del.

Continuation of Ser. No. 622,235, Dec. 5, 1990, Pat. No. 5,351,269. This application Sep. 12, 1994, Ser. No. 304,650

Int. Cl. H04L 9/00

U.S. Cl. 370-337

15 Claims



1. A spread spectrum CDMA communications system for communicating data between a plurality of PCN units, said spread spectrum CDMA communications system located within a same geographical region as occupied by a mobile cellular system with each cell of the mobile cellular system having a cellular bandwidth divided into predetermined channels with guard bands between the predetermined channels, and having cellular-users communicating on the predetermined channels, said spread spectrum CDMA communications system comprising:

- a plurality of PCN-base stations located within the mobile cellular system for communicating data to the plurality of PCN units, each of said plurality of PCN-base stations including,
 - a base modulator for converting the format of the data into a form suitable for communicating over radio waves;
 - a pseudorandom generator for generating a selected-chip code;
 - a product device coupled to said pseudorandom generator and to said base modulator, for spread spectrum processing the converted data from said base modulator with the selected-chip code; and
 - a transmitter coupled to said product device for transmitting across the cellular bandwidth, the spread-spectrum-processed-converted data to a PCN unit;
- a plurality of PCN units, each of said plurality of PCN units including,
 - a PCN antenna; and
 - PCN detection means coupled to said PCN antenna and including PCN-spread-spectrum-processing means, for recovering the spread-spectrum-processed-converted data communicated from each of said plurality of PCN-base stations.

5,588,021

REPEATER FOR USE IN A CONTROL NETWORK

Mark A. Hunt, Derby, and Andrew Murray, Sutton Coldfield, both of United Kingdom, assignors to Light & Sound Design Limited, Edinburgh, United Kingdom

Filed Jun. 24, 1993, Ser. No. 80,717

Claims priority, application United Kingdom, Sep. 25, 1992, 9220308; Apr. 20, 1993, 9308069


Int. Cl. H04B 17/02; 1/38

U.S. Cl. 375-211

5 Claims

1. A repeater for use in a control network comprising:
- a root input/output isolating transformer,
 - a plurality of branch input/output isolating transformers,
 - a line receiver circuit,
 - line driver circuits coupled to said branch input/output isolating transformers,

common voltage detector means for detecting a common voltage at a root side of said root input/output isolating transformer,



common voltage applying means for applying to a branch side of each of the branch input/output isolating transformers a common mode voltage determined by said common voltage detector means,

normal data flow enabling means for enabling the line receiver circuit coupled to the root input/output isolating transformer and the line driver circuit directly connected to the branch input/output isolating transformers when a normal common mode voltage is detected, so that data signals received by the root input/output isolating transformer are transmitted from each of the branch input/output isolating transformers,

reverse data flow enabling means for enabling the line receivers coupled to the branch isolating input/output transformers when a different common mode voltage is detected,

a data signal discriminating means, coupled to the line receiver circuits for detecting valid data signals at an output of any one of the line receiver circuits coupled to the branch input/output isolating transformers, and

means for enabling the line driver circuit coupled to said root input/output isolating transformer when such valid data signals are detected and for routing it to the output of the one of the line receiver circuits at which valid data signals have been detected.

5,588,022

METHOD AND APPARATUS FOR AM COMPATIBLE DIGITAL BROADCASTING


Mark J. Dapper, Cincinnati; Michael J. Geile, Loveland, and Barry W. Carlin, Greenhills, all of Ohio, assignors to Xetron Corp., Cincinnati, Ohio

Filed Mar. 7, 1994, Ser. No. 206,368

Int. Cl. H04L 27/00; 27/28; 27/18; 23/02

U.S. Cl. 375-216

25 Claims




1. A radio frequency broadcasting method, said method comprising the steps of:

amplitude modulating a first carrier signal by an analog signal to generate a first radio frequency signal having a first frequency spectrum;

generating a plurality of digitally modulated carrier signals for broadcast said signals being within a frequency range which encompasses the frequency spectrum of the first radio frequency signal, each of said digitally modulated carrier signals being digitally modulated by a portion of a digital signal, wherein a first group of said digitally modulated carrier signals overlap said first frequency spectrum and are modulated in-quadrature with said first carrier signal, and wherein second and third groups of said digitally modulated carrier signal be outside of said first frequency spectrum and are modulated both in-phase and in-quadrature with said first carrier signal and

simultaneously broadcasting said first radio frequency signal and said plurality of digitally modulated carrier signals.



5,588,023

HIGH CONTENT INFORMATION TRANSMISSION SYSTEM


Kai-Fai Ho, P.O. Box 54504, North Point, Hong Kong

Continuation of Ser. No. 268,797, Nov. 8, 1988, abandoned, which is a continuation-in-part of Ser. No. 853,480, Apr. 18, 1986, Pat. No. 4,809,299. This application Apr. 18, 1995, Ser. No. 423,126

Int. Cl. H03K 7/08; 9/00

U.S. Cl. 375-238

20 Claims



1. A process for transmitting information comprising a series of message units selected from a set of more than two defined message units, said transmission process comprising the steps of:

- a) defining the message units comprising said set of defined message units;
- b) assigning a wavelet duration to each defined message unit;
- c) converting each of said defined message unit of the information to be transmitted into an alternate-state wavelet at a rate of one message unit per wavelet state, each of said defined message unit being a member of said set of defined message units, the duration of said alternate-state wavelet being varied for each of said defined message unit to conform to the wavelet duration defined for each of said defined message unit, successive converted wavelets corresponding to respective message units being contiguous and alternating;
- d) transmitting said converted wavelet, said information to be transmitted being transmitted as succeeding alternating wavelets;
- e) receiving said transmitted wavelet;
- f) determining a received wavelet duration of said received wavelet;
- g) deconvolving said received wavelet duration to a message unit in accordance with the assigned wavelet duration, thereby to convey the information.

5,588,024

FREQUENCY SUBBAND ENCODING APPARATUS

Hideto Takano, Tokyo, Japan, assignor to NEC Corporation, Japan

Filed Sep. 25, 1995, Ser. No. 533,100

Claims priority, application Japan, Sep. 26, 1994, 6-229889

Int. Cl. H04B 1/04

U.S. Cl. 375-242

3 Claims

1. A frequency subband encoding apparatus comprising:

- a subband filter for dividing a digital audio signal into a plurality of frequency subbands;
- a signal to mask level ratio calculator for calculating mask levels for the individual frequency subbands from the digital audio signal based on a psychoacoustic model, detecting signal levels of the individual frequency subbands from samples of the frequency subbands and outputting signal to mask level ratios which are ratios between the signal levels and the mask levels for the individual frequency subbands;
- a bit allocator for determining a reference NMR which is a value obtained by subtracting from a signal to mask level ratio of the entire frequency band a signal to noise ratio calculated from a reference bit number to be allocated to one of the frequency subbands which exhibits a maximum signal to mask level ratio and adjusting the reference NMR to perform bit allocation, wherein said bit allocator temporarily allocates to those of the frequency subbands which have higher signal to mask level ratios than the reference NMR, bit numbers corresponding to differences between the signal to mask level ratios and the reference NMR and then adjusts the reference NMR to perform bit allocation repetitively until a remaining bit number after the temporary bit allocation exhibits a minimum value; and
- a quantizer for quantizing samples of the individual frequency subbands with quantization step numbers calculated from bit allocation amounts to the individual frequency subbands.

5,588,025

SINGLE OSCILLATOR COMPRESSED DIGITAL INFORMATION RECEIVER


Christopher H. Strolle, Glenside, Pa.; Steven T. Jaffe, Freehold, and Paul W. Lyons, New Egypt, both of N.J., assignors to David Sarnoff Research Center, Inc., Princeton, N.J.

Filed Mar. 15, 1995, Ser. No. 406,216

Int. Cl. H04L 27/06; 27/14; 27/22; 7/00

U.S. Cl. 375-316


21 Claims



1. A receiver for demodulating a packetized input signal containing encoded timing information, comprising:
- an oscillator for generating a sampling signal;
 - digitizing means, connected to said oscillator, for digitizing the packetized input signal using the sampling signal;
 - interpolating means, connected to said digitizing means, for interpolating the digitized signal to produce an interpolated signal;


14 Claims

4 Claims




detecting said received digital phase shift signal;
raising the detected digital signal to M-th power (M is the number of information phases) producing M-th power signal;
to remove a modulation factor from said received signal;
accumulating the M-th power signals for N symbols and deriving a phase component of the accumulated M-th power signal;
dividing the derived phase component into M so as to obtain an estimation value with respect to phase shift due to the frequency offset which represents frequency deviation from a true carrier frequency contained in the received signal;
multiplying the received signal by the obtained estimation value in a form of a conjugate complex number to remove phase shift due to frequency offset from the received signal; and

U.S. ENVIRONMENTAL PROTECTION AGENCY




producing, for each given one of said allowed transitions, a branch metric value representing the difference between the value of the symbol representing said one allowed transition and the value of the corresponding symbol in said sequence as received over said channel, selecting, as second candidate transitions, those transitions having the most favorable branch metric value, calculating for each of said first and second candidate transitions the combined value of said branch metric value and the path metric value previously stored for the state at which said transition originated, comparing said combined values to select that candidate transitions having the most favorable combined value, saving said most favorable combined value as the new path metric for said given state, and saving an identification of the selected candidate transition having the most favorable combined value; and sequentially tracing a connected chain of a plurality of said selected transitions from a current one of states to produce a decoded output symbol corresponding to a prior transition in said chain.

U.S. Cl. 375—364 22 Claims



1. A decoding system for decoding a data stream including frames of encoded data, each frame including a plurality of subframes of integrally encoded data, comprising:
decoding means for decoding said subframes; and
synchronization means for controlling the decoding means to skip a subframe if a predetermined decoding time for said subframe is earlier than a current time; and to repeat said subframe if said predetermined decoding time is later than said current time.

Int. Cl.⁶ H04L 7/00

1. A method for detecting the beginning of data in a bit stream, wherein the bit stream comprises sequences of a preamble, byte synchronizing and data, wherein the byte synchronizing comprises an EOP bit sequence which identifies the end of the preamble and the beginning of the data, said method comprising the steps of:

- determining a frequency and phase related to the bit stream for clock synchronization;
- wherein said step of determining is completed within an initial portion of a pattern of bits in the preamble, said pattern being a repetition of instances of a specific bit string having a bit with a first value and one or more bits having a different second value;
- performing EOP searches to detect a first occurrence of said EOP bit sequence in said bit stream, wherein at least one of said EOP searches commences at a first bit position within said bit stream, said first bit position separated by a second bit position from a third bit position at which a next EOP search is commenced, wherein no EOP search commences at said second bit position; and
- determining where the data begins in the bit stream using an EOP bit sequence detected in one of said EOP searches;

wherein said step of performing EOP searches allows an EOP bit sequence to be used which is shorter than a bit sequence which would be required if an EOP search were commenced at said second bit position.

5,588,031

APPARATUS FOR REINFORCING A REACTOR VESSEL CORE SHROUD


Bruce W. Bevilacqua, Export; Louis J. Malandra, McKeesport; Robert E. Meuschke, Monroeville, and Alex W. Harkness, Gibsonia, all of Pa., assignors to Westinghouse Electric Corporation, Pittsburgh, Pa.

Filed Oct. 27, 1994, Ser. No. 330,058

Int. Cl. G21C 9/00

U.S. Cl. 376-287

3 Claims



1. An apparatus, which reinforces a core shroud that is contained within a reactor vessel, operable in the event of cracking or events of similar magnitude in the core shroud, the apparatus comprising:

- a reactor vessel wall positioned surrounding the shroud;
- a plurality of beams positioned generally axially and in a spaced apart relationship with each other around the shroud, each beam attached to the shroud for absorbing the forces generated in the shroud, each beam having a generally U-shaped cross section for allowing easy installation of each said radial support, and each beam having a support shelf positioned in its interior; and
- a plurality of radial supports positioned between each said beam and said reactor vessel wall for transmitting any forces absorbed by each said beam to said reactor vessel wall which, in effect, reduces the loads in each said beam and also maintains generally uniform distribution of the loads absorbed by each said beam for allowing each said beam to efficiently absorb the generated forces, each said radial support including a mating portion which attaches to the beam shelf for assisting in transmitting the absorbed forces in said beam to the wall.

5,588,032

APPARATUS AND METHOD FOR IMAGING WITH WAVEFIELDS USING INVERSE SCATTERING TECHNIQUES

Steven A. Johnson, 1916 E. Browning Ave., Salt Lake City, Utah 84108; James W. Wiskin, 1021 Medical Towers, Salt Lake City, Utah 84112; David T. Borup, 1133 E. Sunnyside Ave., Salt Lake City, Utah 84103; Douglas A. Christensen, 8520 S. Top of the World Cir., Salt Lake City, Utah 84121, and Frank Stenger, 680 Ter. Hills Dr., Salt Lake City, Utah 84103


Filed Oct. 14, 1992, Ser. No. 961,768

Int. Cl. G01N 23/201; G01V 1/00

U.S. Cl. 378-8

120 Claims

107. A method of producing an image of an object from wavefield energy that has been transmitted into and scattered by the object, said image comprising a high resolution map of the scatter-



ing potential at all points within the object, said image being stored in a memory of a central processing unit (CPU), and said method comprising the steps of:

- electronically transmitting an electric signal at one or more frequencies and transducing said electric signal at each said frequency into wavefield energy propagated toward said object from one or more of antennae transmitter positions;
- electronically processing said electric signal to determine an incident field corresponding to said propagated wavefield energy, said incident field being stored in the memory of the CPU in the form of digitized electric signals;
- detecting at one or more of antennae receiver positions said wavefield energy transmitted into and scattered by said object;
- electronically processing said detected wavefield energy so as to transform said detected wavefield energy into one or more digitized electric signals stored in said memory of said CPU and corresponding to a scattered field detected at said one or more antennae receiver positions;
- said CPU setting an initialized estimate of the scattering potential for said object at each said frequency and storing each said scattering potential estimate in said memory; and
- said CPU computing an updated scattering potential from said incident field and said scattered field detected.

5,588,033

METHOD AND APPARATUS FOR THREE DIMENSIONAL IMAGE RECONSTRUCTION FROM MULTIPLE STEREOTACTIC OR ISOCENTRIC BACKPROJECTIONS


Kah T. D. Yeung, Cordova, Tenn., assignor to St. Jude Children's Research Hospital, Memphis, Tenn.

Filed Jun. 6, 1995, Ser. No. 466,829

Int. Cl. G01N 23/083

U.S. Cl. 378-4

16 Claims



1. A method for reconstructing a three dimensional image of an object from a plurality of radiographic images, comprising the steps of:

backprojecting each radiographic image through a reconstruction volume to produce a plurality of corresponding backprojected images; and determining an intersection of said plurality of backprojected images in said reconstruction volume, said intersection defining a three dimensional, reconstructed image of the object.

5,588,034

APPARATUS AND METHOD FOR INSPECTING A CRYSTAL

David K. Bowen, and Charles R. Thomas, both of Warwickshire, England, assignors to Rolls-Royce PLC, London, and University of Warwick, Coventry, both of England


Filed Apr. 21, 1995, Ser. No. 426,602

Claims priority, application United Kingdom, Apr. 22, 1994, 9408012

Int. Cl. G01N 23/207

U.S. Cl. 378-73

23 Claims



1. An apparatus for detecting defects in a crystal comprising a specimen holder arranged to hold a crystal, a polychromatic x-ray generator arranged to produce a beam of polychromatic x-rays, a collimator arranged to receive the beam of polychromatic x-rays from the polychromatic x-ray generator, the collimator having means to produce a plurality of separate parallel polychromatic x-ray beams in a predetermined pattern and to direct the plurality of separate parallel polychromatic x-ray beams in the predetermined pattern onto the surface layers of the crystal, an x-ray detector arranged to detect at least one separate diffracted x-ray beam diffracted by the surface layers of the crystal, each of the separate diffracted x-ray beams corresponding to a respective one of the plurality of separate parallel polychromatic x-ray beams directed onto the surface layers of the crystal, the x-ray detector determining whether any of the separate diffracted x-ray beams have been displaced from the predetermined pattern to indicate that there is a defect in the surface layers of the crystal.

5,588,035

X-RAY TUBE NOISE AND VIBRATION REDUCTION

Paul G. Christean, and Dennis H. Runnoe, both of Salt Lake City, Utah, assignors to Varian Associates, Inc., Palo Alto, Calif.


Filed Jul. 17, 1995, Ser. No. 503,114

Int. Cl. H01J 35/20

U.S. Cl. 378-132

16 Claims

1. An X-ray tube comprising: a housing; a vacuum envelope disposed within said housing, said vacuum envelope comprising a head portion and a neck portion; an anode assembly disposed within said vacuum envelope and extending through said head and neck portion, said anode assembly comprising a rotatable target, a shaft mounted to said target, said shaft extending inwardly along a tube axis, a rotor mounted to said shaft for rotation said anode assembly about said axis at a predetermined speed;



- a bearing and support structure, said anode assembly mounted to said bearing and support structure;
- a cathode assembly disposed within said head portion in proximity to said anode assembly for generating and focusing a beam of electrons onto said target for producing X-rays;
- a high voltage source for maintaining a potential between said rotating anode and said cathode assembly; and
- a flexible isolating member disposed between said neck portion of said vacuum envelope and said bearing and support structure along said tube axis for providing independent respective movement for said vacuum envelope and said bearing and support structure to prevent transmission of the vibrational energy from said anode assembly to said vacuum envelope, said flexible isolating member being integral with said vacuum envelope.

5,588,036

X-RAY CT APPARATUS AND RADIOGRAPHING METHOD USING SAME

Masakuni Fujise, Otawara, and Hiroshi Ishikawa, Mitaka, both of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Continuation of Ser. No. 266,631, Jun. 28, 1994, abandoned.


This application Feb. 15, 1996, Ser. No. 601,967

Claims priority, application Japan, Jun. 28, 1993, 5-157470

Int. Cl. G21K 5/10

U.S. Cl. 378-146

18 Claims



1. An X-ray CT apparatus for performing a scanning operation on an examined region of a patient lying on a bed, in which an

X-ray from an X-ray tube irradiating the patient passes through the patient and is detected by a detecting means, the X-ray CT apparatus comprising:

- a scan condition file means into which past scan condition including a predetermined scan pitch and a predetermined slicing width for patients to be scanned are stored the past scan condition being acquired by means of previously performing at least one scanning operation on the examined region of the patient;
- means for individually designating a specific one of the patients; means for reading out the past scan condition of the designated specific one of the patient from the scan condition file means; and
- a main controller for setting a scan condition in accordance with the past scan condition of the examined region of the designated patient and for performing the scanning operation on the examined region of the designated patient in accordance with the set scan condition.

5,588,037


REMOTE ACCESS TELEPHONE CONTROL SYSTEM
Robert M. Fuller, Redmond; Frederick A. Epler, Issaquah, and Maxwell E. Manowski, Enumclaw, all of Wash., assignors to Accessline Technologies, Inc., Bellevue, Wash.

Division of Ser. No. 249,453, May 26, 1994, which is a division of Ser. No. 480,242, Feb. 15, 1990, Pat. No. 5,375,161, which is a continuation-in-part of Ser. No. 439,601, Nov. 21, 1989, abandoned, which is a continuation-in-part of Ser. No. 841,931, Mar. 20, 1986, Pat. No. 4,893,335, which is a continuation-in-part of Ser. No. 650,821, Sep. 14, 1984, abandoned. This application Jul. 8, 1994, Ser. No. 273,008

Int. Cl. H04M 3/42

U.S. Cl. 379-57

55 Claims



1. A control system for connection to a telephone network, said network including at least one telephone switch which is capable of connecting a plurality of telephone lines such that a plurality of parties can simultaneously be in telephone contact with other parties at the same time via said switch, said control system receiving and processing calls from callers to users, the control system comprising: input/output means for connection to telephone network lines to input and output telephone calls; switch control means for controlling said at least one switch to connect a call on

one line to a different line; memory means for controllably storing and recalling electronic signals; and electronic processing means for accessing said memory means and said switch control means to direct the flow of input and output calls, said electronic processing means including means for:

- a) processing calls to the system directed to a user in a selected one of at least two distinct programmable modes, one such mode being call forwarding in which case the processing means proceeds with functions b) through c);
- b) recalling from said memory means a forwarding number for said user;
- c) causing said switch control means to switch the caller's call in said switch to said forwarding number;
- d) monitoring a call to said system from said user, including during calls made by said user via said control system to one or more third parties;
- e) in response to the user transmitting a predetermined command while the call is being monitored, placing the user's call in a control mode wherein user may enter commands to change a users call processing mode.

5,588,038


SYSTEM AND METHOD FOR SIGNALING A DEVICE AT A REMOTE LOCATION OVER A WIRELESS NETWORK
Bernard M. Snyder, San Diego, Calif., assignor to J.F.A. Tech., Inc., San Diego, Calif.

Continuation-in-part of Ser. No. 154,818, Nov. 19, 1993, abandoned. This application Dec. 5, 1994, Ser. No. 349,548

Int. Cl. H04Q 7/12

U.S. Cl. 379-57

21 Claims



- 1. A system for remotely stopping a vehicle theft, comprising: a transmitter for generating a calling code and a predetermined security code;
 - a central switching unit for receiving said calling code and said predetermined security code and for generating a forward wireless communication including said calling code and said predetermined security code;
 - a satellite for receiving and transmitting said forward wireless communication;
 - a pager transceiver, located in a vehicle, for receiving said wireless communication and for transmitting a reverse wireless communication, wherein said pager unit is responsive to said calling code and generates a first signal in response to receiving said predetermined security code;
 - a tripping circuit, responsive to said first signal and located in said vehicle, for generating a second signal; and
 - a switch, responsive to said second signal and located in said vehicle, for disabling said vehicle;
- wherein said pager transceiver is a digital transceiver that receives and sends only low-power short digital data packets and that cannot receive digital and analog voice transmissions;

wherein said reverse wireless communication can be relayed through said satellite to said central switching unit.

5,588,039

MOBILE COMMUNICATION SYSTEM CAPABLE OF AVOIDING LOCAL CONGESTION

Kazuko Ohkubo, and Masahiko Yahagi, both of Tokyo, Japan, assignors to NEC Corporation, Tokyo, Japan


Filed Jun. 13, 1994, Ser. No. 258,815

Claims priority, application Japan, Jun. 15, 1993, 5-143695

Int. Cl. H04Q 7/22

U.S. Cl. 379-58

2 Claims



- 1. A mobile communication system comprising: an integrated service digital network (ISDN); a plurality of mobile base stations directly connected to said ISDN as subscribers of said ISDN, each of said mobile base stations comprising means for receiving a call request with a destination subscriber number from one of a plurality of mobile stations, and means for transmitting to said ISDN a call information signal including an identification of said one of said mobile stations and the destination subscriber number;
 - a home memory station, directly connected to said ISDN as a subscriber of said ISDN, for storing update location information of said plurality of mobile stations with respect to said mobile base stations, said home memory station comprising: (i) means for receiving said call information signal and for searching the stored update location information to determine to which mobile base stations the destination subscriber number belongs, and (ii) means for returning an information signal including an ISDN subscriber number of at least one of said mobile base stations to which the destination subscriber number belongs and an identification number of the destination subscriber number via said ISDN to said one of said mobile base stations.
- wherein each of said mobile base stations further comprises:
- (i) means for receiving said information signal and for establishing a call connection to at least one of said mobile base stations, without passing through said home memory station, based on the ISDN subscriber number thereof, and
 - (ii) means for calling one of said mobile stations having the identification number of the destination subscriber number.

5,588,040

Patent Not Issued For This Number

5,588,041


CELLULAR SPEAKERPHONE AND METHOD OF OPERATION THEREOF

George W. Meyer, Jr., Buffalo Grove; Allen Wong, Streamwood; John H. Spears, McHenry; David L. Bond, Hoffman Estates, and Thomas F. Vondrak, Libertyville, all of Ill., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Jan. 5, 1995, Ser. No. 369,021

Int. Cl. H04Q 7/32

15 Claims



- 1. A portable cellular speakerphone comprising: a housing;
- a transceiver circuit disposed within said housing;
- a processor and switching circuit disposed in said housing and coupled to said transceiver circuit for controlling said transceiver circuit;
- a coupler carried on said housing and coupled to said processor and switching circuit for communicating with an optional handset; and
- a hands-free user interface disposed within said housing and coupled to said processor and switching circuit, said hands-free user interface including a first microphone and a first speaker for operating the portable cellular speakerphone in a default hands-free mode, said processor and switching circuit coupling said hands-free user interface to said transceiver circuit in a default hands-free mode, and said processor and switching circuit responsive to detecting an activation indication signal from an optional handset coupled to said coupler to automatically interrupt the default hands-free mode to permit the portable cellular speakerphone to operate in a handset mode.

5,588,042

INTERACTIVE ROAMER CONTACT SYSTEM FOR CELLULAR MOBILE RADIOTELEPHONE NETWORK FOR AUTOMATICALLY INITIATING A COMMUNICATION WITH AN AUTONOMOUSLY REGISTERING CELLULAR MOBILE RADIOTELEPHONE

Edward I. Comer, Marietta, Ga., assignor to BellSouth Corporation, Atlanta, Ga.


Continuation of Ser. No. 647,719, Jan. 28, 1991. This application Jun. 6, 1995, Ser. No. 468,794

Int. Cl. H04Q 7/22

U.S. Cl. 379-59

120 Claims

1. In or for a cellular mobile radiotelephone (CMR) system, an automated customer class identification and contacting system, comprising:



means for monitoring identification information provided by an autonomously registering mobile radiotelephone as it autonomously registers into said CMR system by powering up or entering an area of coverage of a cell of said CMR system; means responsive to said identification information for detecting predetermined identifying characteristics of said autonomously registering mobile radiotelephone; and communicating means responsive to detection of a selected predetermined identifying characteristic of said autonomously registering mobile radiotelephone for initiating a voice channel communication with a selected autonomously registering mobile radiotelephone having said selected predetermined identifying characteristic.

5,588,043

COMPREHENSIVE MOBILE COMMUNICATIONS DEVICE REGISTRATION METHOD


Edward G. Tiedemann, Jr.; Gadi Karmi, and Frank Quick, all of San Diego, Calif., assignors to Qualcomm Incorporated, San Diego, Calif.

Continuation of Ser. No. 370,771, Dec. 23, 1994, abandoned, which is a continuation of Ser. No. 26,899, Mar. 5, 1993, abandoned, which is a continuation-in-part of Ser. No. 763,091, Sep. 20, 1991, Pat. No. 5,289,527. This application Feb. 16, 1996, Ser. No. 602,683

Int. Cl. H04Q 7/22

U.S. Cl. 379—63

16 Claims



1. In a cellular communication system having a plurality of base stations, each of said plurality of base stations having a corresponding coverage area, in which a mobile station initially registers through a first base station with a system controller so that a message for said mobile station from said system controller may be communicated to said mobile station through at least one of said base stations in a predetermined manner, a method of registration comprising the steps of:

changing at said mobile station, during a time when active communication between said system controller and said mobile station is not established, a parameter which effects said predetermined manner of communication; and registering said parameter via a radio frequency signal generated by said mobile station and transmitted to a base station corresponding to a coverage area in which said mobile station is currently located, wherein said parameter which effects said predetermined manner of communication is a slot cycle of said mobile station; receiving at said mobile station location information from said first base station; receiving at said mobile station location information from a second base station; computing a distance between said second base station and said first base station; and registering by said mobile station through said second base station if said computed distance exceeds a threshold.

5,588,044


VOICE RESPONSE SYSTEM WITH PROGRAMMING LANGUAGE EXTENSION

Dan M. Lofgren, Milpitas, and William A. Dietrich, Sunnyvale, both of Calif., assignors to Voysys Corporation, Fremont, Calif.

Filed Nov. 22, 1994, Ser. No. 343,721
Int. Cl. G06F 15/419; H04M 1/64

U.S. Cl. 379—67

24 Claims



1. Telephony server apparatus, for use with a plurality of telephony channels, comprising:
a processor structure;
channel control hardware coupled to said telephony channels and to said processor structure; and
a memory structure having stored therein a plurality of channel programs each associated with a respective one of said telephony channels, multi-tasking operating system software instructions executable by said processor structure, database engine software instructions executable by said processor structure under a different task of said operating system for each of said telephony channels, and a database, said database engine software instructions including instructions which, when executing under a given task of said operating system, interpret the channel program associated with the telephony channel of said given task and perform both database and telephony operations in response to such channel program associated with the telephony channel of said given task, said database operations including at least one operation from the group consisting of reading data from and writing data to said database, and said telephony operations including at least one operation from the group consisting of speaking a predefined prompt onto the telephony channel associated with the given task, receiving and storing DTMF-encoded input from the telephony channel associated with the given task, and recording audio input from the telephony channel associated with the given task.

5,588,045

VOICE/DATA TRANSFER METHOD AND APPARATUS UTILIZING AN ALTERNATE LINE


Michael J. Locke, Santa Clara, Calif., assignor to Siemens Rdm Communications Inc., Santa Clara, Calif.

Filed Feb. 3, 1995, Ser. No. 485,031

Int. Cl. H04M 1/78

U.S. Cl. 379—67

15 Claims



1. An apparatus for transferring data from a first port of an application processor to a telephone which having an internal alternate line and a second port of the application processor, comprising:

means for seizing the second port;
means for detecting dialing of the second port;
means for confirming the detection of dialing from the first port;
means for initiating a transfer of the call to the alternate line; and
means for transferring the call to the second port, wherein said alternate line is configured such that said alternate line will not go off-hook prior to said call being connected to said second port.

5,588,046

DIGITAL TELEPHONE ANSWERING DEVICE AND METHOD OF TESTING MESSAGE STORAGE MEMORY THEREIN


Stephen B. Knuth, Mission Viejo, Santoro M. Brown III, Cardiff by the Sea, and Mark A. Karnowski, Westminster, all of Calif., assignors to Casio PhoneMate Inc., Torrance, Calif.

Filed Oct. 23, 1995, Ser. No. 546,810

Int. Cl. G11C 11/34 29/00; G06F 1/00; H04M 1/64

U.S. Cl. 379—67

11 Claims



1. A method for testing a storage memory in a digital telephone answering device, the method comprising the steps of:
performing an initial test of only a predetermined portion of said memory, said predetermined portion of said memory having a size sufficient to store a first user input of information required to perform a basic telephone answering device func-

tion, said initial test being performed immediately after power is supplied to said device, without testing a remainder of said memory.

thereafter performing a continuous repetitive series of tests on at least said remainder of said memory while waiting for subsequent user input of information relating to any telephone answering device function, said continuous repetitive series of tests being performed in a depth-banded sequence of said memory.

marking said depth-banded sections of said memory, processing said subsequent user inputs when said subsequent user inputs occur.

stopping performance of said continuous repetitive series of tests simultaneously with said processing of said subsequent user inputs, and

returning to said step of performing said continuous repetitive series of tests after completion of said processing of said subsequent user inputs.

5,588,047

INTERFACE FOR SIMULATING A TELEPHONE LINE CONNECTION BETWEEN TWO DEVICES FOR ESTABLISHING A COMMUNICATION PATH BETWEEN THE DEVICES


Lars Rosengren, Huskvarna, and Ingemar Ericsson, Jonkoping, both of Sweden, assignors to Rosengren Teknik AB, Huskvarna, Sweden.

Filed Feb. 2, 1995, Ser. No. 12,520

Int. Cl. H04M 1/78

U.S. Cl. 379—60

10 Claims



1. A circuit connected between a transmitting device and a receiving device, which are disposed in close proximity to each other for simulating a telephone ring signal provided to the transmitting device to facilitate the transmission of data from the transmitting device to the receiving device, said circuit comprising:
an input terminal for connection to the transmitting device;
sensing means connected to said input terminal for sensing when transmission of data from the transmitting device is imminent;
an output terminal for connection to the receiving device, said output terminal being connected to said input terminal for providing a transmission path for data from said input terminal;

a voltage terminal connected to said input and output terminals for providing a transmission voltage to the transmitting and receiving devices during the transmission of data;

a telephone ring generator circuit connected to said sensing means for generating, for a preset time duration, a signal representative of a telephone ring when imminent transmission of data is sensed by said sensing means, said signal being provided to said input terminal during said preset time duration;

a timing circuit powered by said voltage terminal and connected to said ring generator circuit for instructing said ring generator circuit when to cease generating said representative ring signal; and


switching means connected between said voltage terminal and said timing circuit for providing voltage from said voltage terminal to said timing circuit when said sensing means senses that transmission of data from the transmitting device is imminent.

5,588,053

DTMF DETECTOR SYSTEM AND METHOD WHICH PERFORMS STATIC AND DYNAMIC THRESHOLDING
Zheng-yi Xie, Austin, Tex., assignor to Advanced Micro Devices, Sunnyvale, Calif.

Continuation of Ser. No. 563,973, Nov. 29, 1995. This application Jan. 11, 1996, Ser. No. 585,530
Int. Cl.⁶ H04M 1/50

U.S. Cl. 379-386 28 Claims



1. A method for detecting dual tone multifrequency (DTMF) signals which uses static and dynamic thresholding, comprising: receiving a plurality of digital samples of a received signal, wherein said received signal includes a plurality of tones, wherein said plurality of tones comprise two or more tones from a plurality of different uncorrelated frequencies, wherein said plurality of different uncorrelated frequencies comprise two or more frequency groups; determining energy values for each of said different uncorrelated frequencies comprising said two or more frequency groups; determining a maximum energy value among said different uncorrelated frequencies for each of said two or more frequency groups; comparing each of said maximum energy values for each of said two or more frequency groups with a first fixed value; determining if each of said maximum energy values for each of said two or more frequency groups is greater than said first fixed value; calculating a plurality of ratios of said maximum energy values with other energy values of said different uncorrelated frequencies from respective ones of said two or more frequency groups; comparing each of said plurality of ratios with a second fixed value; and determining if said calculated ratios are greater than said second fixed value.

5,588,054


POWER CONSERVATION SYSTEM FOR A MODEM IN A COMPUTER SYSTEM

Seongkee Shin, and Sangho Lee, both of Kyungki-do, Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea

Filed Apr. 20, 1995, Ser. No. 425,530
Claims priority, application Rep. of Korea, Oct. 27, 1994, 94-27666

U.S. Cl. 379-413 21 Claims

15. A power conservation system for a modem in a computer system having a primary power supply and an auxiliary power supply, comprising:
ring detect means coupled to a telephone ring signal line for generating a ring detect signal in response to detection of a ring signal on said telephone ring signal line, said ring detect means also being coupled to a power supply voltage to supply power to said ring detect means during a normal mode of operation;
power management means having an input coupled to said ring detect means and an output coupled to the primary power




supply, said power management means being responsive to said ring detect signal for switching the primary power supply from a first level corresponding to a power conservation mode of operation of the computer system to a second level corresponding to said normal mode of operation; and, wherein said auxiliary power supply is coupled to said ring detect means for supplying power to said ring detect means when the computer system is in said power conservation mode of operation, whereby said ring detect circuit is maintained in an active state even during said power conservation mode of operation of the computer system.

5,588,055

TELEPHONE HOLDER WITH MOUNTING ASSEMBLY
Robert Williamson, 7753 SE. Heather Ct., Milwaukie, Ore. 97222; Alan Poole, 12685 SE. Sonoma, Clackamas, Ore. 97015, and Michael S. Weinert, 5715 SE. 17th, Portland, Ore. 97202

Continuation-in-part of Ser. No. 379,136, Jan. 27, 1995, abandoned. This application Jun. 3, 1996, Ser. No. 659,112
Int. Cl.⁶ H04M 1/00

U.S. Cl. 379-446 11 Claims



1. A telephone holder mounting assembly connected to a back wall of a telephone holder, wherein the mounting assembly is for mounting the holder to a top edge of a generally vertical surface, the mounting assembly comprising:


a hooking bracket for mounting over the top edge of the surface, wherein the bracket includes a rearwardly extending portion projecting from the back wall and a downwardly extending portion extending therefrom, and
a spring-biased buttress for stabilizing and leveling the holder against the surface by contacting and pushing against the surface, wherein the buttress is connected to the back wall and when not contacting the surface, the buttress is a substantially planar expanse which acutely extends rearwardly and downwardly away from the back wall and, when contacting the surface while the holder is mounted thereto, the buttress bends so that the buttress does not extend past a plane defined by the vertical surface.

5,588,056

METHOD AND SYSTEM FOR GENERATING PRONOUNCEABLE SECURITY PASSWORDS
Ravi Ganesan, Arlington, Va., assignor to Bell Atlantic Network Services, Inc., Arlington, Va.

Filed Oct. 25, 1994, Ser. No. 328,226
Int. Cl.⁶ H04L 9/00

U.S. Cl. 380-4 55 Claims



1. A method implemented on a computing device for forming a pronounceable security password using a plurality of first word segment portions, each having at least one character, and a plurality of second word segment portions, each having at least one character, with each of said plurality of first word segment portions (i) having an associated set of one or more said second word segment portions, each said second word segment portion within said associated set being different from others within said set and being combinable with said associated first word segment portion to form a pronounceable word segment and (ii) having a transition number corresponding to the number of said second word segment portions within the associated set of second word segment portions, comprising the steps of:

selecting a first one of said plurality of first word segment portions, wherein selection of any one of said plurality of first word segment portions is of substantially equal probability;
selecting a first one of said plurality of second word segment portions from said set of second word segment portions associated with said selected first word segment portion, wherein selection of any one of said second word segment portions within said associated set of second word segment portions is of substantially equal probability;
combining said selected first word segment portion and said selected second word segment portion to form a first pronounceable word segment; and
generating a pronounceable security password including said first pronounceable word segment only if consecutive characters of said first pronounceable word segment fail to correspond to those of said plurality of first word segment portions having a transition number less than a first threshold transition number.

5,588,057

APPARATUS FOR DEFEATING RADAR SPEED DETECTION SIGNALS


M. David Sullivan, Los Altos, Calif., assignor to Voodoo Scientific, Inc.

Continuation of Ser. No. 57,160, May 4, 1993, abandoned.

This application Jun. 20, 1995, Ser. No. 492,472
Int. Cl.⁶ G01S 7/38

U.S. Cl. 380-15 10 Claims

1. An apparatus for inhibiting capture by a remote seeking radar signal receiver of a return signal of a Doppler-type seeking radar signal, said apparatus comprising:



a microwave voltage-controlled oscillator means (MVCO) coupled to an antenna means for receiving seeking radar signals and for emitting a local oscillator signal;
a sweep control means coupled to said MVCO for sweeping a frequency range of said seeking radar signals at a first sweep rate with said local oscillator signal;
means coupled to said MVCO and to said first sweep control means for detecting an intercept of said seeking radar signals by said local oscillator signal by heterodyning said local oscillator signal and said seeking radar signals and for stopping sweeping of said local oscillator signal within an injection locking bandwidth of said intercept so that said oscillator signal locks to said seeking radar signals; and
means coupled to said MVCO for frequency modulating said local oscillator signal in order to cause emission through said antenna means of a frequency modulated carrier signal with deviation greater than the injection-locking bandwidth of said local oscillator signal.

5,588,058


METHOD AND DEVICE FOR SCRAMBLING AND DESCRAMBLING OF A SPECIFIC TELEVISION BROADCAST

Jacques Le Berre, Puteaux, France, assignor to U.S. Philips Corporation, New York, N.Y.

Filed Mar. 29, 1994, Ser. No. 219,055

Claims priority, application France, Mar. 31, 1993, 93 03777
Int. Cl.⁶ H04N 7/167

U.S. Cl. 380-20 12 Claims



1. A method of scrambling, at the level of a transmitter, and descrambling, at the level of receivers, a specific television transmission of limited duration, scrambling being performed by means of a pseudo-random generator which is initialized by a control word, descrambling involving the reconstruction upon reception, by means of a memory card device, of the control word which initializes a pseudo-random generator which is identical to that of the transmitter, said pseudo-random generator supplying the data necessary for descrambling, wherein in advance there are defined a table of numbers and different feasible modes of generating a control word by reading the table of numbers, and wherein the table is written into a read-only memory, the read-only memory being contained in descrambling cards issued to the users of receivers, after which at an instant of said specific television

broadcast, the mode of reading a control word in the table is chosen in real time from among the various predefined feasible modes, which control word is read in conformity with said chosen mode in order to supply the control word to the transmitter in real time, and immediately a signal is broadcast to the receivers so as to indicate a relevant mode of extracting the control word from the table, wherein the indicated mode corresponds to the chosen mode of the different feasible mode at the transmitter, as a result of which the receivers generate this control word according to the indicated mode from a descrambling card, the descrambling card comprising a simple memory in which the table of numbers is written.

5,588,059

COMPUTER SYSTEM AND METHOD FOR SECURE REMOTE COMMUNICATION SESSIONS


Ronald V. Chandos, Tempe, and Robert I. Foster, Mesa, both of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Mar. 2, 1995, Ser. No. 398,181

Int. Cl.⁶ H04L 9/00; 9/08

U.S. Cl. 380—21

14 Claims



7. A remote terminal for providing security for a communication session between said remote terminal and a host computer, said remote terminal comprising:

- a first memory region containing encrypted user identifying data and an encrypted portion of a host traffic key;
- a second memory region containing an encrypted remote terminal traffic key;
- a modem for sending said encrypted user identifying data from said remote terminal to said host computer;
- a user input device for obtaining a crypto-uncovering agent from a user of said remote terminal;
- a controller coupled to said user input device, said first and second memory regions, and said modem for deciphering said encrypted remote terminal traffic key in response to said crypto-uncovering agent to obtain a deciphered remote terminal traffic key and for sending said encrypted user identifying data and said encrypted portion of said host traffic key to said host computer through said modem.

5,588,060

METHOD AND APPARATUS FOR A KEY-MANAGEMENT SCHEME FOR INTERNET PROTOCOLS

Ashar Aziz, Fremont, Calif., assignor to Sun Microsystems, Inc., Mountain View, Calif.

Filed Jun. 10, 1994, Ser. No. 258,272


Int. Cl.⁶ H04L 9/30

U.S. Cl. 380—30

20 Claims

1. An improved method for a first data processing device (node 1) to send data to a second data processing device (node 2), comprising the steps of:

- providing an element for performing the step of providing a secret value i , and a public value $\omega^i \bmod p$ to said node 1;
- providing an element for performing the step of providing a secret value j , and a public value $\omega^j \bmod p$ to said node 2;



said node 1 including an element for performing the steps of: obtaining a Diffie-Helman (DH) certificate for node 1 and determining said public value $\omega^i \bmod p$ from said DH certificate;

computing the value of $\omega^i \bmod p$, said node 1 further deriving a key K_{ij} from said value $\omega^i \bmod p$;

utilizing said key K_{ij} to encrypt a randomly generated transient key K_p , and encrypting a data packet to be transmitted to node 2 using said key K_p ;

providing an element for performing the step of said node 1 sending said data packet encrypted using said key K_p to said node 2.

5,588,061

SYSTEM AND METHOD FOR IDENTITY VERIFICATION, FORMING JOINT SIGNATURES AND SESSION KEY AGREEMENT IN AN RSA PUBLIC CRYPTOSYSTEM


Ravi Ganesan, Arlington, Va., and Yacov Yacobi, Berkeley Heights, N.J., assignors to Bell Atlantic Network Services, Inc., Arlington, Va., and Bell Communications Research, Inc., Livingston, N.J.

Filed Jul. 20, 1994, Ser. No. 277,808

Int. Cl.⁶ H04L 9/30

U.S. Cl. 380—30

43 Claims



1. A method for using an RSA cryptosystem comprising the steps of:

generating a private exponent key, having an associated modulus N of a predetermined bit length, and a corresponding public exponent key;

dividing said private exponent key into a first private key portion and a second private key portion, wherein said first private key portion has a bit length of no greater than fifteen percent of the bit length of the associated modulus N but not less than 56 bits;

disclosing said first private key portion to a first user; and disclosing said second private key portion to a selected one or more other users of the RSA system.

5,588,062

SECURE COMMUNICATION SETUP METHOD

Barry N. Altschuler, Scottsdale; Douglas A. Hardy, Mesa; James A. Stephens, Chandler, and Joseph Kish, III, Gilbert, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.



Division of Ser. No. 172,971, Dec. 27, 1993, Pat. No.

5,465,300. This application Jul. 13, 1995, Ser. No. 501,799

Int. Cl.⁶ H04L 9/30

U.S. Cl. 380—30

6 Claims



a memory coupled to a system bus for storing sets of instructions to operate the computer;

a processor coupled to the system bus for executing the sets of instructions stored in the memory;

a display coupled to the system bus having a front, viewing surface and adjacent left side and right side surfaces;

a right and left speaker unit respectively comprised of a right and a left plurality of small speakers arranged in vertical linear arrays to the right and the left side surfaces of the display, each speaker unit having an exterior height dimension substantially equal to an exterior height dimension of the display and a width dimension substantially smaller than its exterior height dimension to minimize a total width of the display and the speaker units, each speaker in the right and left speaker units receiving a right or a left electrical signal from the personal computer respectively, so that the speakers in each speaker unit become a phased array;

means for locating a user's position in front of the display comprising at least two of the small speakers receiving the right or left electrical signal, to emit sound impulses which reflect off the user and to receive the reflected sound impulses; and

means for altering the left and right signals optimize sound at the located user's position.

5,588,064

HEARING AID BATTERY COVER SWITCH


John P. McSwiggen, Inver Grove Heights, and Randall W. Roberts, Eden Prairie, both of Minn., assignors to Wilbrecht Electronics, Inc., St. Paul, Minn.

Filed Jan. 16, 1996, Ser. No. 586,212

Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—69.2

13 Claims



1. A battery cover switch for a hearing aid, comprising:

a battery cover pivotally attachable to the hearing aid;

a shorting contact cantileverly mounted to said battery cover and movable between a first, rest position and a second, contact position, said shorting contact comprising:

a flexible contact arm affixed at one end thereof to said battery cover and having an opposite, free, contact end disposed beyond the structural periphery of said battery cover in contacting juxtaposition to a contact member;

said contact member positioned to be touched by said shorting contact when said shorting contact is moved from said first, rest position to said second contact position.

5,588,063

PERSONAL MULTIMEDIA SPEAKER SYSTEM

Albert D. Edgar, Austin, Tex., assignor to International Business Machines Corporation, Armonk, N.Y.

Continuation of Ser. No. 969,677, Oct. 30, 1992, abandoned.

This application May 18, 1994, Ser. No. 245,519

Int. Cl.⁶ H04R 5/00

U.S. Cl. 381—24

2 Claims

2. A personal computer equipped with a speaker system comprising:

5,588,065

BASS REPRODUCTION SPEAKER APPARATUS

Shoji Tanaka, Kobe; Katsuhiko Imura, Osaka and Satoshi Kageyama, Takatsuki, all of Japan, assignors to Matsushita Electric Industrial Co., Kadoma, Japan


Continuation of Ser. No. 992,028, Dec. 17, 1992. This application May 23, 1995, Ser. No. 447,429

Claims priority, application Japan Dec. 20, 1991, 3-338093; Dec. 20, 1991, 3-338094; Dec. 25, 1991, 3-342676; Dec. 28, 1991, 3-359521

Int. Cl.⁶ H04R 3/00

U.S. Cl. 381—96

23 Claims



1. A bass reproduction speaker apparatus, comprising:
 - a cabinet with an opening, having a division member inside thereof;
 - a speaker unit disposed at the division member;
 - a passive radiator disposed in the opening;
 - an amplifying means for driving the speaker unit;
 - a detection means for detecting motion of a moving system of the speaker unit; and
 - a feedback means for feeding back an output signal from the detection means to the amplifying means; the feedback means conducting both a velocity-type motion feedback and an acceleration-type motion feedback simultaneously over the same frequency band such that the acceleration-type motion feedback substantially aligns a height of peaks in an output sound pressure level versus frequency response of the speaker apparatus at two resonance frequencies in a low frequency range with each other; and the velocity-type motion feedback suppresses the peaks to obtain a substantially flat output sound pressure level over a wide range of low frequencies.

5,588,066

SPEAKER MOUNTING STRUCTURE

Su-Pei Yang, 2F, No. 110, Lane 103, Sec. 2, Nei Hu Rd., and Shyh-Lee Chen, No. 16, Alley 12, Lane 190, Chong Yang Rd., Nan Gang District, both of Taipei, Taiwan

Filed May 7, 1996, Ser. No. 646,012

Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—188

2 Claims

1. A speaker mounting structure, comprising:
 - a speaker casing which is an annular structure integrally formed by punching, said speaker having a stepped circumferential wall consisting of an upper wall of a smaller diameter and a lower wall of a larger diameter, a notch being formed in said upper wall at a determined position by punching, a slot being provided at said lower wall at a position corresponding to that of said notch, and two positioning holes being disposed at both sides of said slot respectively;

5,588,067

MOTION DETECTION AND IMAGE ACQUISITION APPARATUS AND METHOD OF DETECTING THE MOTION OF AND ACQUIRING AN IMAGE OF AN OBJECT

Fred M. Peterson, 401 Varsity Estates Bay N.W., Calgary, Canada, and James A. Yee, 76 Silver Springs Drive, N.W., Calgary, Canada


Filed Feb. 19, 1993, Ser. No. 19,847

Int. Cl.⁶ G06K 9/00; G06K 9/64; H04N 7/18

U.S. Cl. 382—103

35 Claims

1. Apparatus for capturing images of a record of micro-images, the record of micro-images including non-sparse images, the apparatus comprising:
 - image acquisition means for repeatedly acquiring and at least temporarily storing successive non-sparse images from the record of micro-images;



- the image acquisition means including an area sensor disposed to receive light from the non-sparse images;
- and the apparatus further including a second sensor disposed to receive light from the record of micro-images, the second sensor being operatively connected to the storage means for supplying images to the storage means;
- correlation means for correlating successive non-sparse images from the record of micro-images to create a correlation matrix and determine if motion of the record of micro-images has occurred between successive images of the record of micro-images;
- the correlation means including means to:
 - (i) calculate the Fourier transform of the correlation matrix to produce a phase spectrum, the Fourier transform defining a frequency space having axes and the phase spectrum defining a plane in the frequency space; and
 - (ii) calculate the degree of movement of the current image from the reference image using the projection of the plane onto the axes of the frequency space; and
- storage means for permanently storing an image of the record of micro-images when motion has occurred between successive images.

5,588,068

METHODS AND APPARATUS FOR INSPECTING THE APPEARANCE OF SUBSTANTIALLY CIRCULAR OBJECTS


H. Cary Longest, Midlothian, and James L. Lynch, Richmond, both of Va., assignors to Philip Morris Incorporated, New York, N.Y.

Continuation-in-part of Ser. No. 985,875, Dec. 4, 1992, Pat. No. 5,353,357. This application Sep. 30, 1994, Ser. No. 315,643. The portion of the term of this patent subsequent to Dec. 4, 2012, has been disclaimed.

Int. Cl.⁶ G06K 9/00

U.S. Cl. 382—141


40 Claims



Patent Not Issued For This Number

**IDENTIFYING AN AREA OF INTEREST USING
HISTOGRAM DATA ARRANGED IN PREDETERMINED
SEQUENCE**
**John C. Schultz, Afton, Minn., assignor to Minnesota Mining
and Manufacturing Company, St. Paul, Minn.**
Filed Oct. 26, 1994, Ser. No. 329,493
Int. Cl.⁶ G06K 9/36

23 Claims




1. A method of analyzing a data set of a digitized image to identify an area of interest, the method comprising the steps of:
dividing the digitized image into a plurality of regions;
calculating histogram data for frequencies of image values within each of the plurality of regions;
organizing the histogram data for each of the regions according to a predetermined sequence of the plurality of regions to create a data set for an image in histogram space of the plurality of regions; and
analyzing said data set for the image in histogram space of the plurality of regions to identify localities of maxima and minima in grouped image value characteristics which correspond to the area of interest within the digitized image.

Shin-Ywan Wang, Tustin, Calif., assignor to Canon Kabushiki
Kaisha, Tokyo, Japan
Filed Dec. 22, 1993, Ser. No. 171,720
Int. Cl.⁶ G06K 9/36

49 Claims

1. A method of selecting blocks of pixels from pixel image data comprising:

- a) an outlining step in which contours of connected components in the pixel image data are outlined;
- b) a first connecting step in which connected components are selectively connected widthwisely based on size and proximity to other connected components to form lines;
- c) a second connecting step in which lines of widthwise connected components are selectively connected vertically based on size and proximity to other lines to form rectangles around blocks of pixel image data; and



a forming step in which an irregularly-shaped curve is formed around each block of pixel image data surrounded by a rectangle which overlaps another block of pixel image data.


5,588,073

**ONLINE HANDWRITTEN CHARACTER RECOGNIZING
SYSTEM AND METHOD THEREOF**

Heun J. Lee, Seoul, and Moon J. Joe, Kyoungki-do, both of
Rep. of Korea, assignors to Goldstar Co., Ltd., Seoul, Rep. of
Korea

Continuation of Ser. No. 309,569, Sep. 20, 1994, abandoned,
which is a continuation of Ser. No. 971,649, Nov. 5, 1992,
abandoned. This application Oct. 30, 1995, Ser. No. 550,227
Claims priority, application Rep. of Korea, Feb. 14, 1992
1992-2214

9 Claims




1. An online handwritten character recognizing system, comprising:

- an input device inputting a character and outputting a character signal including character points of said character;
- a preprocessor connected to said input device and receiving said character signal and converting said character points into sample points which have normalized magnitude and uniform sampling interval;
- feature extracting means for receiving said sample points from said preprocessor and transforming a coordinate function made from said sample points into Fourier coefficients representing the character;
- character recognition means for receiving said Fourier coefficients from said feature extracting means, and recognizing the inputted character from said Fourier coefficients, wherein said character recognition means including:
- a first neural network for generating a plurality of first signals responsive to real part of said Fourier coefficients;


a second neural network for generating a plurality of second signals responsive to imaginary part of said Fourier coefficients; and
MIN/MAX algorithm means for selecting a plurality of smaller values from the plurality of first and second signals, each smaller value being selected as the smaller of a corresponding pair of first and second signals, and selecting a largest value from the plurality of smaller values to recognize the inputted character.

5,588,074
DATA RECOGNITION EQUIPMENT AND METHOD
USING PARTIAL PATTERN RECOGNITION
Mitsumasa Sugiyama, Yokohama, Japan, assignor to Canon
Kabushiki Kaisha, Tokyo, Japan
Continuation of Ser. No. 504,625, Apr. 4, 1990, abandoned.
This application Oct. 4, 1993, Ser. No. 131,913
Claims priority, application Japan, Apr. 6, 1989, 1-085655
Int. Cl.⁶ G06K 9/62; 9/46

11 Claims



1. Data recognition equipment comprising:
dictionary means for storing partial pattern data and pattern data;
inputting means for inputting segmented pattern data;
recognition means for recognizing partial pattern data among
input pattern data from said inputting means by comparison
with the partial pattern data stored in said dictionary means;
selection means for selecting a candidate pattern having the
recognized partial pattern from said dictionary means;
first comparing means for comparing the selected candidate
pattern with the input pattern data for each part other than the
recognized partial pattern data and for outputting a distance
obtained from the comparison in correspondence to the
selected candidate pattern;
second comparing means for comparing the output distance
from said first comparing means with a reference value; and
third comparing means for comparing the selected candidate
pattern with the input pattern data at a part of the recognized
partial pattern if it is determined that the distance is smaller
than the reference value by said second comparing means;
and
output means for outputting character information representing
the candidate pattern compared with the input pattern data by
said third comparing means.



- a reference image holding step of holding reference image data;
- an image holding step of holding said input image data;
- an effective block detecting step of dividing said input image data which is at present a target to be compressed and said reference image data into blocks each including (m×n) pixels, and comparing and detecting each block having a change as an effective block;
- a compressing order deciding step of grouping said blocks into macro blocks each having a predetermined number of said blocks, and deciding a compressing order of said macro blocks in accordance with a number of effective blocks in each macro block;
- an address generating step of generating pixel addresses of said input image data on a block unit basis in accordance with the compressing order of the macro blocks decided in said compressing order deciding step;
- a compressing step of reading out said input image data by pixels according to the pixel addresses generated in said address generating step and converting said input image data into codes on a block unit basis;
- a code output step of outputting encoded data obtained by combining the order information decided in said compressing order deciding step and the codes converted in said compressing step; and
- a compressing end step of stopping the compression in said compressing step and processing next image data in the case where a code amount by said compressing step exceeds a threshold value before the compression of the image data of one picture screen is finished and processing the next image data in the case where the compression of the image data of one picture screen is finished before said code amount exceeds said threshold value.

5,588,075

METHOD AND APPARATUS FOR ENCODING AND
DECODING IMAGE DATA

Hirotaka Chiba; Kimitaka Murashita, and Tsugio Noda, all of
Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki,
Japan

Claims priority, application Japan, Sep. 2, 1993, 5-218269
Int. Cl.⁶ G06K 9/36

22 Claims

1. A compressing method of image data which is continuously input, comprising:

5,588,076

OPTICAL FIBRE MANAGEMENT SYSTEM

John Peacock, Otley; Peter L. J. Frost, and John Kerry, both of Ipswich, all of England, assignors to British Telecommunications public limited company, London, England


Continuation-in-part of Ser. No. 202,190, Feb. 24, 1994, Pat. No. 5,548,678. This application Jul. 21, 1994, Ser. No. 278,217

Claims priority, application European Pat. Off., Sep. 10, 1993, 93307145; Apr. 28, 1994, 94303091

Int. Cl.⁶ G02B 6/35

8 Claims

1. An optical fibre management system for managing a plurality of optical fibres in an optical fibre communication system having at




5,588,078
NON-RECIPROCAL OPTICAL WAVEGUIDE COUPLING DEVICE

Yihao Cheng, Kanata, and Gary S. Duck, Nepean, both of Canada, assignors to JDS Fitel Inc., Nepean, Canada
Continuation-in-part of Ser. No. 164,547, Dec. 10, 1993, abandoned. This application Aug. 9, 1995, Ser. No. 513,028
Int. Cl.⁶ G02B 6/26

U.S. Cl. 385—33

18 Claims



least one fibre separation point between a terminal site and an optical signal processing node such that the fibre of each single optical fibre circuit is routed separately from the fibre of other circuits, said system comprising:


- a plurality of individually accessible fibre service trays with access ports for optical fibres, and
- each said service tray having therein only optical fibre for a single circuit carrying optical signals between a first separation point and either a terminal or a second separation point, whereby optical signals carried by any given single circuit are not degraded by handling operations carried out on the fibres of other circuits.

5,588,077

IN-LINE, TWO-PASS, FIBER OPTIC ROTARY JOINT
Shane H. Woodside, Lower Sackville, Canada, assignor to Focal Technologies, Inc., Nova Scotia, Canada
Filed May 22, 1995, Ser. No. 445,752
Int. Cl.⁶ G02B 6/26

U.S. Cl. 385—26

10 Claims



2. A two-channel fiber optic rotary joint for transmission of optical signals, comprising:


- (a) a rotational portion aligned with a stationary portion, having a rotational axis extending therealong, and a plane of separation between said rotational and stationary portions;
- (b) means for mounting first and second optical fibers in said rotational portion, spaced apart along said axis;
- (c) means for mounting third and fourth optical fibers in said stationary portion, spaced apart along said axis;
- (d) means for optically coupling first channel light between said first optical fiber and one of said third or fourth optical fibers;
- (e) means for optically coupling second channel light between said second optical fiber and the other of said third or fourth fibers so that said second channel light shares the same physical space as said first channel light; and
- (f) the mounting means and the coupling means positioned in said rotational portion on one side of said plane of separation being a mirror image of the mounting means and the coupling means positioned in said stationary portion on the other side of said plane of separation.

5,588,079

OPTICAL CONNECTOR
Takashi Tanabe, and Kouji Yamamoto, both of Tokyo, Japan, assignors to NEC Corporation, Japan
Filed Feb. 17, 1995, Ser. No. 390,471
Int. Cl.⁶ G02B 6/36


U.S. Cl. 385—78

6 Claims



1. An optical connector, comprising:
- a housing having a round opening with equally spaced pointed ridges positioned around the periphery of said round opening, said round opening including a guide for receiving a ferrule for an optical fiber, said guide comprising:
 - a first tier comprising:
 - first sloped portions extending down a side of said equally spaced pointed ridges;

- second, rounded sloped portions, adjacent said first sloped portions;
- a second tier comprising:
- first rectangular flat surfaces abutting said first sloped portions centered about said equally spaced pointed ridges; and
- second rectangular flat surfaces positioned between two of said first rectangular flat surfaces;
- a stopper surface positioned at a bottom end of said second tier, said stopper surface having a round center opening; and
- a ferrule, comprising:
- a capillary support for supporting an optical fiber;
- a capillary being insertable into said round center opening of said stopper surface; and
- a flange, connected between said capillary and said capillary support and shaped to fit into said second tier to hold said ferrule in a stationary position when said flange is guided by said first tier into said second tier against said stopper surface.




5,588,080

CONNECTOR FOR CONNECTING AN OPTICAL FIBER CABLE

Shigeto Kawamura, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Japan
Filed May 19, 1995, Ser. No. 445,354
Claims priority, application Japan, May 25, 1994, 6-111170
Int. Cl.⁶ G02B 6/38

U.S. Cl. 385—78

8 Claims



1. A connector for connecting an optical fiber (A) having a core (a) and a sheath (b), said optical fiber (A) having a mating end, said core (a) protecting axially beyond said sheath (b) at said mating end, said connector comprising a housing (10) unitarily formed with a ferrule (11), and a fixing member (20) comprising a holding plate (21) formed with an insertion hole (21a) through which the optical fiber cable (A) is inserted, flexible core retainers (22) extending forward from the holding plate (21) and having projections (22a) formed on a leading end thereof for pressing the core (a) of the optical fiber cable (A), flexible sheath retainers (23) extending forward from the holding plate (21) and having projections (23b) formed on a leading end thereof for pressing the sheath (b) of the optical fiber cable (A), and locking portions (24) for locking the fixing member (20) with the housing (10), wherein, for coupling the connector with a mating connector (30), coupling structure is provided on the connector, said coupling structure comprising at least one of locking arms (25) formed on the fixing member (20) for engaging portions (32) formed on the mating connector (30) and a friction lock projection (13) formed on the housing (10) for pressing the mating connector (30).

5,588,082

OPTICAL CABLE FUSION SPLICE

Peter J. Whitesmith, "Aisling", Wyche Lane, Bunbury, Tarporley, Cheshire CW6 9PS, England

Filed Sep. 19, 1995, Ser. No. 529,999

Claims priority, application United Kingdom, Sep. 20, 1994, 9418878

Int. Cl.⁶ G02B 6/00; 6/36

U.S. Cl. 385—96

13 Claims

1. A method of forming a fusion splice between two optical ribbon cables, which comprises:
- (i) positioning end portions of the ribbon cables to be spliced in line with one another, and separated from one another by a pre-determined distance;
 - (ii) firing a preparation arc across the ends of the ribbon cables of sufficient energy to soften the ends of the optical fibres forming the ribbon cables;
 - (iii) firing a fusion arc across the ends of the ribbon cables after a defined period of time following termination of the preparation arc to fuse the ends of the fibres; and

5,588,081


LIGHT COUPLING DEVICE TO COUPLE A LIGHT SOURCE TO AN OPTICAL FIBER

Mitsuo Takahashi, Matsudo, Japan, assignor to Seikoh Giken Co., Ltd., Matsudo, Japan
Filed May 24, 1995, Ser. No. 448,981
Claims priority, application Japan, Nov. 11, 1994, 6-303041
Int. Cl.⁶ G02B 6/42

U.S. Cl. 385—93

7 Claims

1. A light coupling device for coupling a light source to an optical fiber comprising:



(iv) simultaneously with, or subsequent to the fusion arc, moving the ribbon cables toward one another into contact, thereby to effect a fusion splice between the ribbon cables.

5,588,083

NON-LINEAR OPTICALLY ACTIVE POLYCARBONATE
Tjerk O. Boonstra, SK Duiven, and Ulfert E. Wiersum, AV Velp, both of Netherlands, assignors to Akzo Nobel N.V., Arnhem, Netherlands

Filed Sep. 26, 1994, Ser. No. 312,254

Claims priority, application Netherlands, Sep. 29, 1993, 9301679


Int. Cl.⁶ G02B 6/00; C08G 64/00

U.S. Cl. 385—122

13 Claims

1. An optical waveguide component, characterized in that it comprises a non-linear optically active side chain polycarbonate which sandwiched between defective layers of lower index of refraction than the non-linear optically active side chain condensation polymer and which is obtained from a monomer mixture comprising:

an NLO diol satisfying formula 1:



wherein D is a trivalent donor group comprising 2-10 aliphatic, alicyclic, aromatic or heterocyclic carbon atoms, and comprising at least one alkoxy-oxygen atom, at least one sulphur atom, at least one selenium atom, or a nitrogen atom directly or conjugatedly bonded to the benzene ring, and

wherein

X stands for —CR₂=CR₂—, —N=N—, —CR₂=N— or —N=CR₂—,

Y stands for —CN, —NO₂, CR₂=C(CN)₂, —CF₃, SO₂R⁴, —C(CN)=C(CN)₂, barbiturate groups, or thiobarbiturate groups,


AR stands for a six-membered aromatic ring, a six-membered aromatic ring substituted with one or more R¹ groups, a non-saturated 6 membered ring, a non-saturated six-membered ring substituted with one or more R² groups, a five-membered heteroatomic ring containing O, N, S, Se, a five-membered heteroatomic ring substituted with one or more R₂ groups and containing O, N, S or Se, a fused ring structure,

R¹ stands for —halogen, —R², —OR², —COR², —CN or —CF₃

R² stands for —H, —halogen, an alkyl group having 1-6 carbon atoms, a halo substituted alkyl group having 1-6 carbon atoms,

R² stands for —halogen, —R², —OR², COR², —CN, NO₂, SO₂R⁴ or CF₃.

R⁴ stands for an (halogenated) alkyl group having 1-4 carbon atoms,
n is an integer from 0 to 4, with the X-groups being the same or different, and
a compound according to formula 2:



formula 2

wherein:

P stands for —Cl, O—R, an imidazole group or —O—Ph.

Q stands for —Cl, O—R, an imidazole group or —O—Ph.

R stands for an alkylene group having 1-6 carbon atoms.

Ph stands for phenyl.

A stands for —Ph—, halogenated —Ph—, —Ph—C(CH₃)₂—Ph—, —Ph—SO₂—Ph—, a cycloalkylene group having 1-24 carbon atoms, a halo substituted cycloalkylene group having 1-24 carbon atoms, an arylene group having 1-20 carbon atoms, or a naphthalene group.

m is an integer from 0 to 5, with the A-groups being the same or different.

5,588,084

SCINTILLATING OPTICAL FIBERS CONTAINING NON-UNIFORMLY DISTRIBUTED DOPANTS AND PROCESS FOR PREPARING SAME


Kurtis F. Johnson, 112 E. Sinclair Rd., Tallahassee, Fla.

Filed Apr. 28, 1995, Ser. No. 431,281

Int. Cl.⁶ G02B 6/02; F21V 9/16

U.S. Cl. 385—123

24 Claims



1. A scintillating fiber comprising an outer layer, an inner layer, a fiber center and an interface between the inner and outer layers, wherein the distance between the fiber center and any point of the interface in a fiber cross section defines a radius and the distance between the fiber center and any point located along the radius defines a fractional radius, and wherein the outer layer has an index of refraction lower than that of the inner layer and wherein the inner layer contains a dopant non-uniformly distributed within the inner layer.

5,588,085

RADIOLYTIC METHOD FOR MAKING A MODE-FIELD TRANSFORMING OPTICAL WAVEGUIDE

Benjamin I. Greene, Westfield; Chellappan Narayanan, North Plainfield, and Herman M. Preshy, Highland Park, all of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Apr. 17, 1996, Ser. No. 633,323

Int. Cl.⁶ G02B 6/02; C03B 37/023

U.S. Cl. 385—123

14 Claims

1. A method for making a silicate optical waveguide structure for transforming an optical beam of a first modal spot size to a beam of a second modal spot size, said method comprising the step of:

selecting an irradiation energy that is at least partially absorbed by the cladding;

applying a variable dosage of radiation along the length of said structure, said radiation having an energy equal to said irradiation energy such that a refractive index change of the core.

5,588,087

OVERLAPPING FUSION ATTENUATOR


David J. Emmons, Plymouth, and Liang-Ju Lu, Eden Prairie, both of Minn., assignors to ADC Telecommunications, Inc., Minneapolis, Minn.

Continuation of Ser. No. 205,342, Mar. 8, 1994, abandoned, which is a continuation of Ser. No. 582, Jan. 4, 1993, abandoned, which is a continuation of Ser. No. 815,963, Jan. 2, 1992, abandoned. This application Sep. 14, 1994, Ser. No. 306,241

Int. Cl.⁶ G02B 6/26

U.S. Cl. 385—140

32 Claims




diation energy such that a refractive index change of the cladding is greater than a refractive index change of the core.

8. A silicate optical waveguide structure having a core and cladding for transforming an optical beam of a first modal spot size to a beam of a second modal spot size, said structure fabricated by a method including the steps of:

selecting an irradiation energy that is at least partially absorbed by the cladding;

applying a variable dosage of radiation along the length of said structure, said radiation having an energy equal to said irradiation energy such that a refractive index change of the core.



24. A fiber optic attenuator comprising: first and second segments, each having respective first and second ends, a portion of each segment including the first end being referred to as a first end portion, said fiber segments being characterized by a fiber diameter and having respective cores having respective ends;

said respective first end portions being fused to each other with said ends of said cores completely encapsulated and overlapping each other in an overlap region by an axial distance that is greater than said fiber diameter, said respective second ends being located on longitudinally opposite sides of said overlap region.

5,588,088

HOT WATER TEMPERING SYSTEM UTILIZING A STORAGE TANK, A BYPASS LINE AND A PROPORTIONAL FLOW CONTROLLER


Michael T. Flaman, 20 Treeline Court, Etobicoke, Ontario, Canada

Filed Jun. 20, 1994, Ser. No. 262,705

Int. Cl.⁶ F24H 1/18

U.S. Cl. 392—449

13 Claims



1. A hot water tempering system comprising in combination: a hot water storage tank having an inlet line and an outlet line, the inlet line being connectable to a cold water supply line; a bypass line connected between the inlet line and the outlet line; and

5,588,086

FIBER OPTIC HERMETIC BULKHEAD PENETRATOR FEEDTHROUGH MODULE AND METHOD OF FABRICATING SAME


Robert J. Fan, Canoga Park, Calif., assignor to LiteCom, Inc., Canoga Park, Calif.

Filed Apr. 1, 1993, Ser. No. 41,724

Int. Cl.⁶ G02B 6/00


U.S. Cl. 385—138

31 Claims



1. A hermetic pressure differential and temperature differential feedthrough system comprising:

a signal transmitting optical fiber or plurality of optical fibers; a hermetic sealing material providing an extremely high fluid or gas differential pressure and temperature differential seal; a feedthrough housing of suitable material to provide a substantial bond between said housing and said hermetic sealing material; said signal transmitting optical fibers which are suitably cleaned and may be stripped of buffer coatings to provide a substantial bond between said fibers and said hermetic sealing material; said signal transmitting optical fibers passing through said feedthrough housing which may have a connector interface on either or both sides of said feedthrough comprised of fibers hermetically sealed within a fiber optic terminus or other system requiring interfaces and requiring interconnecting means to couple the feedthrough housing to a connector half; said bonds between said hermetic sealing material and said signal transmitting optical fiber, between said hermetic sealing material and said fiber optic termini, and between said sealing material and said housing are provided by mechanical, chemical or environmental means.



examination, or, if the pixel under examination is not a designated restricted pixel and its adjacent pixels are in the second state, changing the state of the pixel under examination to a state different from the second state and thereby causing an update of the rendered bit map; and producing a completed update of the rendered bit map by repeating the examining and determining steps for multiple pixels in each of multiple lines in each set, the completed update of the rendered bit map reducing dot overlap in a printed image via linear spot growth to provide uniform darkening and the use of a supercell structure to maximize the number of gray scale levels, the printed image corresponding to the completed update of the rendered bit map.

5,588,095

SYSTEM AND METHOD OF PRINTER BANDING


Stephen V. Dennis, Bothell, and Gabe L. Newell, Seattle, both of Wash., assignors to Microsoft Corporation, Redmond, Wash.

Division of Ser. No. 911,523, Jul. 10, 1992. This application Jun. 7, 1995, Ser. No. 472,502

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—116

4 Claims



1. A computer for processing data to be printed by a printer coupled to the computer and receiving data from the computer, for printing a page of data on the printer with unidirectional page movement, using an unprocessed data file that describes a plurality of objects to be printed on the page and a user specified appearance of the plurality of objects to be printed on the page, by defining a plurality of bands for the page, each of the bands having a selected

band size, the printer containing a conversion means to sequentially convert data corresponding to the plurality of bands into sequential bit-map data files corresponding to the plurality of bands for printing on the page, buffer storage means for temporarily storing the sequential bit-map data files until printed, and print means for sequentially printing the bit-map data files on the page, the computer comprising:

storage means for storing the unprocessed data file;

rendering means for transforming said stored data file into bandable primitives for each band, said bandable primitives for each band corresponding to the plurality of objects and portions of the plurality of objects within that band, and for storing said bandable primitives in a manner indicative of a data processing sequence determined by the user specified appearance of the plurality of objects to be printed on the page;

dividing means for dividing said bandable primitives into sets of banded primitives corresponding to the bands to generate a set of banded primitives for each of the bands with each of said set of banded primitives describing only the plurality of objects and portions of the plurality of objects within the respective one of the corresponding bands, said set of banded primitives for each band maintaining said data processing sequence determined by the user specified appearance of the plurality of objects to be printed on the page; and

an interface to transfer said sets of banded primitives to the printer for printing, whereby the computer does not process said stored data file one time for each of the bands in order to generate the bit-map data files.

5,588,096

OBJECT IMAGE DISPLAY DEVICES

Shinichiro Sato, Syunsuke Akaza, Fussa, and Hiroyuki Yoshino, Higashiyamato, all of Japan, assignors to Casio Computer Co., Ltd., Tokyo, Japan


Continuation of Ser. No. 169,501, Dec. 16, 1993. This application May 15, 1996, Ser. No. 665,060

Claims priority, application Japan, Dec. 21, 1992, 4-340298; Dec. 30, 1992, 4-360896; Dec. 30, 1992, 4-360900

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—135

7 Claims



1. An object image display device comprising: part image storage means for storing a plurality of groups of part images having different shapes, each of the groups corresponding to a respective one of a plurality of predetermined different parts which compose an object, a respective one of the part images of each of the groups being disposable at a position corresponding to one of the plurality of predetermined different parts of the object, said part image storage means also storing designating data for designating the respective part images;

object image storage means for selecting a plurality of part images from among the part images having different shapes of a corresponding one of the groups stored in said part image storage means, and for storing an object image of the object as a combination of the selected plurality of part images;

object image display means for displaying the object image stored in said object image storage means;

part image display means for reading from said part image storage means at least one group of different part images corresponding to at least one part of the object image displayed by said object image means, and for displaying the at least one read group of different part images;

select means for sequentially selecting part images to be successively changed and displayed from among the at least one group of different part images displayed by said part image display means;

designating data storage means for reading sequentially from said part image storage means designating data corresponding to the respective part images selected by said select means, and for storing the read designating data in order;

change start commanding means for initiating a start of successive changes of the respective part images selected by said select means; and

display control means responsive to said change start commanding means for sequentially reading out the designating data stored in order in said designating data storage means, for sequentially reading out from said part image storage means part images corresponding to the respective read designating data, and for sequentially substituting the read part images for the corresponding one of the object image displayed on said object image display means, to thereby display the resulting object image as if at least one of the part images of the resulting object image is moved successively.

5,588,097

GRAPHIC DISPLAY METHOD AND APPARATUS FOR ROTATING AN OBJECT IN THREE-DIMENSIONAL SPACE

Makoto Ono, Yokohama, and Hiroshi Minakata, Tokyo, both of Japan, assignors to International Business Machines Corporation, Armonk, N.Y.


Filed Feb. 24, 1993, Ser. No. 22,252

Claims priority, application Japan, Mar. 4, 1992, 4-047303

Int. Cl.⁶ G06T 17/40

U.S. Cl. 395—137

5 Claims



1. A method of rotating an object being displayed in three-dimensional space by a graphic display apparatus, comprising the steps of:

displaying, on said display apparatus, a semitransparent spherical surface enclosing said object being displayed and having an origin;

specifying four points on said spherical surface, a first one and a second one of said four specified points defining two pairs of polar surface coordinates in a polar coordinate system, and

a third one and a fourth one of said four specified points defining an angle α with respect to said second point; computing a difference between said two pairs of polar surface coordinates;

performing a first calculation for rotating said object in said polar coordinate system in accordance with said computed difference; performing a second calculation for rotating said object about an axis connecting said origin to said second point by said angle α ; and displaying, on said display apparatus, said object after being subjected to rotations in accordance with said first and second calculations.

5,588,098

METHOD AND APPARATUS FOR DIRECT MANIPULATION OF 3-D OBJECTS ON COMPUTER DISPLAYS


Michael Chen, Mountain View, Calif.; Stephanie L. Houde, Cambridge, Mass., and Robert H. Seidl, Palo Alto, Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Continuation of Ser. No. 329,695, Oct. 26, 1994, abandoned, which is a continuation of Ser. No. 769,198, Nov. 22, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 475,405

Int. Cl.⁶ G06T 17/40

U.S. Cl. 395—137

94 Claims



1. A method for manipulating an object displayed in three-dimensional representation on a computer controlled display system having a computer and a display coupled to the computer, comprising the steps of:

- providing a user actuated input controller signal for selectively positioning a reference indicator on the display;
- positioning the reference indicator over the displayed object and signaling the computer to activate a control movement mode;
- providing on the display a three-dimensional representation of a bounding region including at least two portions which specify respective predefined control movement types, one of said types being rotation around an axis parallel to the portion which specifies rotation around that axis;
- positioning the reference indicator over one of said portions;
- signaling the computer to activate a predefined control movement type specified by the portion of the bounding region under the reference indicator, and while the reference indicator is over said portion, repositioning the reference indicator to define a movement of the specified type; and
- re-displaying the displayed object in accordance with the defined movement of the specified type.

5,588,099

METHOD AND SYSTEM FOR AUTOMATICALLY RESIZING TABLES

Alex Mogilevsky, and Kornel R. Marton, both of Redmond, Wash., assignors to Microsoft Corporation, Redmond, Wash.


Filed Sep. 1, 1994, Ser. No. 299,932

Int. Cl.⁶ G06T 3/00

U.S. Cl. 395—139

26 Claims

1. A method in a computer system for automatically resizing a table, the table having a plurality of columns, each column having a column width and a width of longest data, the method comprising the steps of:



for each column in which the column width is greater than the width of the longest data, setting the column width to the width of the longest data; and
when a sum of the column widths of all the columns is greater than a specified width, proportionally decreasing the column width of each column so that the sum of the column widths of all the columns is equal to the specified width.


5,588,100 METHOD AND SYSTEM FOR CREATING A FREEFORM DRAWING OBJECT

David C. Parker, Menlo Park, Calif., assignor to Microsoft Corporation, Redmond, Wash.

Filed May 18, 1992, Ser. No. 884,392
Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—142

26 Claims



1. A method in a computer system for determining a line type for each of a plurality of lines to be created, the line type being either freehand or polygonal, the computer system having a mouse with a button, the button having a released position and a depressed position, the method comprising the steps of:
detecting a first change in position of the button;
detecting movement of the mouse; and
after detecting movement of the mouse, detecting a second change in position of the button; and
after detecting the second change in position of the button, when the button is in the released position, creating a line having a freehand line type; and
when the button is in the depressed position, creating a line having a polygonal line type.


5,588,101
BIT DATA PROCESSOR
Shigeru Ueda, Wako, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan
Division of Ser. No. 141,706, Oct. 27, 1993, which is a continuation of Ser. No. 750,696, Aug. 20, 1991, abandoned, which is a continuation of Ser. No. 378,489, Jul. 12, 1989, abandoned, which is a continuation of Ser. No. 875,564, Jun. 18, 1986, abandoned. This application Jun. 7, 1995, Ser. No. 471,880

Claims priority, application Japan, Jun. 27, 1985, 60-138979
Int. Cl.⁶ G06F 3/00; 9/00

U.S. Cl. 395—792

10 Claims

1. A method for storing dot pattern data representing a character pattern in a memory of which each address is bits of predetermined length, including the steps of:



receiving dot pattern data composed of a part of the character pattern and shift amount data representing an amount to be shifted for the dot pattern data;

generating a bit string of predetermined length as the dot pattern data shifted in accordance with the received dot pattern data and the received shift amount data;

designating an address of the memory at which the bit string of predetermined length generated in said generating step is to be written; and

writing the bit string of predetermined length at the address of the memory designated in said designating step, wherein when any bit string is already written at the designated address, the bit string as already written and the bit string of predetermined length generated in said generating step are combined and the thus-combined bit string of predetermined length is written at the address of the memory as designated in said designating step.

5,588,102

Patent Not Issued For This Number

5,588,103
DOCUMENT EDITOR HAVING FUNCTION FOR CONTROLLING DISPLAY PROCESSING OF DETAILS
Yoshihiko Aoyagi, Kawasaki, Japan, assignor to Fujitsu Limited, Kawasaki, Japan

Filed Jul. 14, 1994, Ser. No. 274,691

Claims priority, application Japan, Oct. 5, 1993, 5-249169
Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—326


4 Claims

1. A document editor for editing and displaying elements of a graphic with a logic structure including at least one of inclusive, side-by-side, and connective relationships, comprising:

editing means for editing at least one element of the graphic having the logic structure and obtaining a reflected result of the editing on other elements, said editing means including means for setting display stages and allocating the elements of the graphic to respective display stages;

output means, having a display unit, for displaying the reflected result of the editing; and

control means for selectively designating display or non-display in the respective display stages for each element of the



graphic having the logic structure associated with the respective display stages, including the reflected result of the editing, and for controlling, based on the designating, said display unit to display or not display the reflected result of the editing.



5,588,104 METHOD AND APPARATUS FOR CREATING VIRTUAL WORLDS USING A DATA FLOW NETWORK

Jaron Z. Lanier, Palo Alto; Ann Lasko-Harvill, San Mateo; Chuck L. Blanchard, Palo Alto, and Joe L. Sparks, San Francisco, all of Calif., assignors to VPL Research, Inc., Redwood City, Calif.

Continuation of Ser. No. 931,881, Aug. 13, 1992, abandoned, which is a continuation of Ser. No. 620,490, Nov. 30, 1990, abandoned. This application Oct. 4, 1994, Ser. No. 317,341
Int. Cl.⁶ G06T 17/00

U.S. Cl. 395—326

42 Claims



1. An apparatus for creating a virtual world, the virtual world including a virtual object which represents a physical object, wherein a first point of the virtual object represents a first part of the physical object and the first point moves in relation to second and third points of the virtual object which represent second and third parts of the physical object, wherein a movement of the first point is based on changes in inputs to a data flow network, the data flow network describing the movement of the first point in relation to the second and third points when the movement of the first point is not based on either one of a rotation and a translation of the virtual object, the apparatus comprising:
a computer display; and

means, connected to the computer display, for generating a data flow network for calculating a movement of a first point of a virtual object in a virtual world in relation to a second point and a third point of the virtual object when the movement is not based on either one of a rotation and a translation of the virtual object, the data flow network including a plurality of interconnected units, and the plurality of interconnected units including at least one input unit representing at least one source of input data for providing input data to the data flow network, a plurality of function units which transform the input data, and a plurality of output units each representing one dimension of a corresponding vector of the first point in a three-dimensional coordinate system, wherein the corresponding vector of the first point generates a first spatial position and a first orientation of the first point in the three-dimensional coordinate system in the virtual world.


5,588,105
STATUS BAR FOR APPLICATION WINDOWS
Gregg S. Foster, Woodside, and Stephen P. Capps, San Carlos, both of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Continuation of Ser. No. 976,970, Nov. 16, 1992, abandoned. This application Feb. 24, 1995, Ser. No. 393,880

Int. Cl.⁶ G06F 3/14; 3/033

U.S. Cl. 395—326

40 Claims



1. A computer system for displaying a status bar for a window of an application program comprising:

a central processing unit (CPU);
read/write memory coupled to said CPU;
a computer screen coupled to said CPU;

means for selecting a status bar template from a plurality of predefined status bar templates, said selected status bar template to be associated with an application program, each of said plurality of status bar templates being able to provide a status bar for different application programs usable on said computer system and each template including a different number or type of active area;

means for providing a status bar from said selected status bar template independently of said application program and independently of an application window of said application program;

means for displaying said status bar on said computer screen such that said status bar is displayed external to said window and is visibly associated with a window of said application program which is also displayed on said computer screen, wherein said status bar is associated only with said application program and is always displayed when said window of said associated application program is displayed; and
means for displaying an active area within said status bar, said active area always being displayed within said status bar and being unable to be removed from said status bar while said

status bar is displayed, said active area including an icon or a label.

5,588,106

HARDWARE ARRANGEMENT FOR CONTROLLING MULTIPLE OVERLAPPING WINDOWS IN A COMPUTER GRAPHIC SYSTEM


Shinichi Habata, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Aug. 16, 1993, Ser. No. 106,561

Int. Cl.⁶ G06T 1/20

U.S. Cl. 395—340

7 Claims




7. An arrangement for displaying a plurality of video images in multiple windows in a computer graphics system, comprising: a processor configured to control an overall operation of said arrangement, said processor being coupled to a bus; a frame buffer coupled to said bus and configured to store one frame video image to be displayed on a display; a video controller operatively coupled to said frame buffer and configured to display said one frame video image stored in said frame buffer on said display; a plurality of video capture units each coupled to said bus and respectively configured to acquire a plurality of video images into said arrangement; a plurality of window pixel data transfer controllers respectively coupled between a corresponding one of said video capture units and said bus, said plurality of window pixel data transfer controllers being arranged to respectively define a plurality of windows and to respectively transfer a corresponding one of said video images to said frame buffer through a corresponding one of said windows, each of said plurality of window pixel data transfer controllers being arranged to determine an exposed portion of a corresponding one of said windows in a case where said corresponding one of said windows is overlapped by another one of said windows, said each of said window pixel data transfer controllers allowing the corresponding one of said video images to be supplied to said frame buffer through said exposed portion of said corresponding one of said windows, wherein said video images are capable of being supplied to said frame buffer in parallel by said plurality of window pixel data transfer controllers, and wherein each of said plurality of window pixel data transfer controllers receives successively corresponding windows defining data from said processor when each of said plurality of window pixel data transfer controllers defines said corresponding one of said windows, each of said plurality of window pixel data transfer controllers being respectively assigned a corresponding window identification number which is respectively applied to said plurality of window pixel data transfer controllers from said processor.

5,588,107
METHOD AND APPARATUS FOR SELECTABLY EXPANDABLE MENUS
Lori Bowden, Santa Rosa; Sharon L. Jochums, Sebastopol, and Erol Otus, El Cerrito, all of Calif., assignors to Island Graphics Corporation, San Rafael, Calif.
Filed Mar. 22, 1993, Ser. No. 35,460
Int. Cl.⁶ G06F 3/14

U.S. Cl. 395—344

20 Claims




1. A method for presenting and selecting menu options on a display of a computer system having a processor and an input device, the method comprising the steps of: bounding a panel region on the display, by use of the processor, into a plurality of menu panels, each menu panel comprising a menu option, said plurality of menu panels having a position relationship to each other; operating the input device to select a first particular one of said plurality of menu panels comprising a first particular one menu option; and expanding said first particular one menu panel to present a first expanded menu panel having options associated with but excluding said first particular one menu option, said first expanded menu panel presented in place of said first particular one menu panel while maintaining said position relationship of said plurality of menu panels.

5,588,108
SYSTEM AND METHOD FOR GENERATING GRAPHICS CHARTS
Pramathesh Kumar, Mountain View; Matthias Grabiak, Oakland, and Ivan Ivanek, Sausalito, all of Calif., assignors to Micrografx, Inc., Richardson, Tex.
Filed Sep. 27, 1994, Ser. No. 314,041
Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—348

28 Claims



1. A method for generating computer graphics on a computer display with a computer having a processor, the method comprising the steps of:

generating on the display an adjustable grid associated with each type of graphics chart, each grid providing predetermined placement positions for text and shapes on each type of graphics chart; and providing snap zones associated with each grid for controlling the orientation of the shapes and text placed on the grid.

5,588,109

USER INTERFACE FOR A REMOTE DIAGNOSTIC DEVICE


Ian J. Dickinson, Wilmington, Del.; Horst Elchberger, Karlsruhe, Germany; David W. Messaros, Wallingford, Pa., and Hans-Dieter Walter, Ditzingen, Germany, assignors to Hewlett-Packard Company, Palo Alto, Calif.

Filed Jan. 23, 1995, Ser. No. 376,720

Int. Cl.⁶ G06F 3/00; 3/14

U.S. Cl. 395—326

19 Claims



1. An apparatus for remote diagnostics of an instrument, comprising: a computer for executing a software application program which provides for communication of commands from the computer to the instrument, and the communication of information accessed from the instrument in response to the commands, the computer further comprising: a graphical user interface comprising a plurality of interrelated windows for displaying the accessed information, wherein, displaying information in one window effects the display of information in at least one other window, the interrelated windows further comprising: an instrument schematic window providing a graphical depiction of the instrument in which the instrument is the combination of a plurality of components, each of which may be accessed individually, an instrument variables window for displaying the current output value of the accessed components; a memo pad window for displaying those output values of the accessed components which have been identified for continuous review even though they may not be currently displayed in the instrument schematic window.

5,588,110
METHOD FOR TRANSFERRING DATA BETWEEN TWO DEVICES THAT INSURES DATA RECOVERY IN THE EVENT OF A FAULT

Rodney A. DeKoning; Donald R. Humlicek, and Max L. Johnson, all of Wichita, Kans., assignors to Symbios Logic Inc., Fort Collins, Colo.


Filed May 23, 1995, Ser. No. 447,377

Int. Cl.⁶ G06F 13/14

U.S. Cl. 395—182.03

31 Claims

1. A method of insuring recovery of a quantity of write request data in a computer system having a host device and a storage device, with the storage device having a first controller and a second controller, comprising the steps of:




transferring the write request data from said host device to said first controller so as to store the write request data therein; allocating a memory area in said second controller for use by said first controller; and maintaining a control block in said second controller for indicating status of the write request data stored in said first controller.

5,588,111
FAULT-TOLERANT COMPUTER SYSTEM HAVING SWITCHABLE I/O BUS INTERFACE MODULES
Richard W. Cutts, Jr., Georgetown; Randall G. Banton, and Douglas E. Jewett, both of Austin, all of Tex., assignors to Tandem Computers, Incorporated, Cupertino, Calif.
Continuation of Ser. No. 84,869, Jun. 30, 1993, abandoned, which is a continuation of Ser. No. 664,495, Mar. 5, 1991, Pat. No. 5,276,823, which is a continuation of Ser. No. 283,574, Dec. 13, 1988, abandoned. This application Jan. 31, 1995, Ser. No. 381,467

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—182.07

14 Claims



1. A fault tolerant computer system to Input/Output (I/O) data to an external device, the external device having an I/O device controller associated therewith, the I/O device controller coupled to a non-duplicated I/O bus, comprising: a plurality of Central Processor Units (CPUs) executing the same instruction stream; first and second I/O processors, each coupled to be accessible by all of said CPUs; first and second I/O busses coupled to said first and second I/O processors, respectively; a bus interface module, coupled to the non-duplicated I/O bus of said I/O device controller, wherein the bus interface module also is coupled to both of said first and second I/O busses; wherein the I/O device controller is coupled to said first I/O bus via said bus interface module, and wherein said bus interface

module includes means for switching to the second I/O bus so that said I/O device controller is coupled to the second I/O bus, in response to an indication of a fault.

5,588,112


DMA CONTROLLER FOR MEMORY SCRUBBING
Glenn Dearth, Groton, and Thomas D. Bissett, Northboro, both of Mass., assignors to Digital Equipment Corporation, Maynard, Mass.

Continuation of Ser. No. 998,717, Dec. 30, 1992, abandoned.
This application Feb. 20, 1996, Ser. No. 603,968

Int. Cl.⁶ G06F 11/34

U.S. Cl. 395—182.07

20 Claims



14. A fault tolerant computer comprising:
a first computing zone comprising:

- a first direct memory access (DMA) controller, said first controller comprising:
 - first means for storing an address of a location in memory for which an error in data read from said location is detected;
 - first means for reading said location in memory, for correcting said error in data read from said location, and for writing said corrected data back to said memory location;
- a second computing zone, comprising:
 - a second direct memory access (DMA) controller, said second controller comprising:
 - second means for storing an address of a location in memory for which an error in data read from said location is detected;
 - second means for reading said location in memory, for correcting said error in data read from said location, and for writing said corrected data back to said memory location; and
 - means for synchronizing the correction of the memory in the first zone with correction of the memory in the second zone.

5,588,113

REGISTER FILE BACKUP QUEUE

Anders R. Johnson, Fremont, Calif., assignor to Seiko Epson Corporation, Tokyo, Japan

Continuation of Ser. No. 846,237, Mar. 5, 1992, Pat. No. 5,398,330. This application Mar. 13, 1995, Ser. No. 403,527


Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—182.13

14 Claims

1. A computer system which processes instructions to generate results which thereby change the visual state of the computer system comprising:

- a memory;
- a bus coupled to said memory; and
- a register file coupled to said bus with a plurality of addressable locations for storing result data; and
- a register file backup system, coupled to said bus, adapted to return a visual state of the computer system to a previous state if an instruction generates an exception, said register file



backup system utilizing less overhead so as to provide easier register file backup than a comparable software or hardware device, said register file backup system comprising:

- a first-in, first-out result tag queue that sequentially stores in program order, address information corresponding to destination locations in said register file where instruction results are to be stored, said first-in, first-out result tag queue having first and second outputs for transferring said address information stored therein,
 - (a) said first output coupled to the register file for transferring a first destination location to said register file, and
 - (b) said second output for transferring a second destination location to said register file; a last-in, first-out backup queue, coupled to
 - (i) said second output of said first-in, first-out result tag queue, for receiving and storing said second destination location, and
 - (ii) the register file, for receiving and backup storing backup data corresponding to contents of said second destination location in the register file before that destination location is changed; and
- means for transferring said backup data from said last-in, first-out backup queue back to said register file locations according to said second portion of said address information stored in said last-in first-out backup queue means after an instruction generates an exception.

5,588,114

METHOD AND APPARATUS FOR PASSIVE LOOPBACK TESTING OF SOFTWARE-CONTROLLABLE PARALLEL PORTS


Pradeep H. Bhatia, Salem, N.H., assignor to Sun Microsystems, Inc., Mountain View, Calif.

Filed Jul. 6, 1995, Ser. No. 499,016

Int. Cl.⁶ G01R 31/28; G06F 11/00

U.S. Cl. 395—183.01

19 Claims



1. A passive device for testing integrity of a software-controllable output parallel port and output parallel port connector pins in a host device, comprising:
 - a test connector, sized to matingly engage said output parallel port connector pins;
 - said test connector having an AUTOFEED pin and a FAULT pin coupled-together to form a first loop-back connection, an

INITIALIZE pin and a SELECT pin coupled-together to form a second loop-back connection, a SELECT IN pin and a PRINTER ERROR pin coupled-together to form a third loop-back connection, and a STROBE pin and a BUSY pin coupled-together to form a fourth loop-back connection, and further having SIGNAL GROUND pins coupled to ground; a passive logic unit coupled to logically-OR DATA control line pins on said test connector and to passively provide a logical-OR output signal to an ACKNOWLEDGE pin on said test connector;

wherein during a test mode, combinations of "0" and "1" signals provided by said host device to said test connector result in a signal at said ACKNOWLEDGE pin of said test connector enabling said output parallel port to be tested for at least one condition selected from the group consisting of (i) open pins, (ii) shorted-to-ground pins, and (iii) shorted-to-power supply pins.

5,588,115

REDUNDANCY ANALYZER FOR AUTOMATIC MEMORY TESTER


Michael H. Augarten, Newbury Park, Calif., assignor to Tera-dyne, Inc., Boston, Mass.

Filed Jan. 29, 1993, Ser. No. 11,003

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—183.05

28 Claims



1. Memory test apparatus for testing a memory under test (MUT) formed from physical structures which define a plurality of storage locations organized into a plurality of regions, said apparatus comprising:

- a) means for testing the plurality of storage locations in the MUT and generating fault signals indicating which of the plurality of storage locations in the MUT is faulty;
- b) a plurality of region modules, each said module having an input, and each said region module comprising:
 - i) a region fault RAM storing data,
 - ii) analysis means, connected to said region fault RAM, for analyzing the data in the region fault RAM to identify faulty structures within the MUT, and
 - iii) input means, coupled to the input of the region module and the region fault RAM, for storing information from the input to the region fault RAM, and
- c) interface means, having an input connected to the means for testing and a plurality of outputs, each output coupled to a region module, for routing fault signals indicating a faulty location to the input of a region module which is selected based on the region of the MUT which contains the faulty location.

5,588,116

Patent Not Issued For This Number

5,588,117

SENDER-SELECTIVE SEND/RECEIVE ORDER PROCESSING ON A PER MESSAGE BASIS


Alan H. Karp, Palo Alto; Ming C. Hao, Los Altos Hills, and Rajiv Gupta, Los Altos, all of Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif.

Filed May 23, 1994, Ser. No. 247,387

Int. Cl.⁶ G06F 13/14; 13/24

U.S. Cl. 395—200.03

22 Claims



1. An apparatus having a mixed-mode communications protocol that enables a sending application to select whether a particular message is to be processed in send order mode, or receive order mode, relative to other messages, comprising:

- a sending portion that sends a sequence of messages to a destination, including a particular message formatted to include a data field representing desired order of processing relative to other messages of the sequence; wherein the data field includes sequence information, which identifies the particular message relative to the other messages in the sequence, and desired queue information, which indicates to the receiving portion that the corresponding message is to be queued until a predetermined number of messages of the sequence have been processed;
- a receiving portion at the destination that receives the messages of the sequence and places them in a receiver-maintained order, but that processes the particular message in the order indicated by the desired queue information, the receiving portion including:
 - a comparator that compares, for the particular message, the desired queue information with an indicator of number of messages before the particular message in the receiver-maintained-order, and provides an output, and
 - a message processor, operatively connected to the comparator, the message processor processing the particular message in response to the output of the comparator; and
- wherein the particular message is processed in send-order mode by selectively setting the desired queue information to correspond to a number of prior messages in the sequence which are to be processed first, and in receive order mode by selectively setting the desired queue information to have a value indicating that no prior messages in the sequence are to be processed first.

5,588,118

SINGLE CHIP DUAL PROCESSOR

Babu S. Mandava, Campbell, and E. Eugene Weddle, San Jose, both of Calif., assignors to Zilog, Inc., Campbell, Calif.


Continuation of Ser. No. 748,257, Aug. 21, 1991, abandoned.
This application Dec. 23, 1994, Ser. No. 363,481

Int. Cl.⁶ G06F 15/163

U.S. Cl. 395—200.05

7 Claims

1. A method of providing, from a single computer program, program instructions to be executed by a first processor to said first processor and program instructions to be executed by a second processor to said second processor, comprising:



reading a program instruction from said single computer program; and
storing, if said program instruction is an opcode instruction of said first processor, said program instruction into an instruction register of said first processor, and storing, if said program instruction is a load data instruction of said first processor, data associated with said load data instruction into a pseudo instruction register accessible to said second processor, wherein said data loaded into said pseudo instruction register corresponds to a program instruction to be executed by said second processor.

5,588,119


METHOD FOR CORRELATING LOGICAL DEVICE NAMES WITH A HUB PORT IN A LOCAL AREA NETWORK

Ronald Vincent, 3803-B2 Rolling Green Ct., Raleigh, N.C. 27604; Marshall Sprague, 5979 Dixon Dr., Raleigh, N.C. 27609, and Duncan Hare, 2600 Sherrill Parke Ct., Richardson, Tex. 75082

Filed Aug. 23, 1993, Ser. No. 110,507
Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—200.15

8 Claims



8. A local area SNA network comprising:

- a communications media including one or more intelligent hubs, each of which has a plurality of hub ports, said hub including means for obtaining therefrom hub port identification data and adapter addresses assigned to a plurality of connected devices;
- said plurality of devices connected by said communication media to respective hub ports, each said device including data transmission and receiving means for communicating with other devices on the network by transmitting and receiving SNA data in frames;
- data storage means in a device connected to the network, said data storage means containing a resource definition file having SNA logical names and XID numbers for said devices connected to the network;
- processing means in at least one of said devices connected to the network for:
 - extracting the SNA logical name and XID numbers from the resource definition file;
 - extracting XID numbers and corresponding adapter addresses from the frames transmitted on the network;

- correlating the adapter addresses from the transmitted frames with the SNA logical names by comparing the XID numbers extracted from the resource definition file with the XID numbers extracted from the transmitted frames;
- obtaining the hub port identification data and corresponding adapter address from the intelligent hubs; and
- correlating the hub port identification data with a corresponding SNA logical name by comparing the adapter address extracted from the transmitted frames with the adapter address obtained from the hub.


5,588,120

COMMUNICATION CONTROL SYSTEM FOR TRANSMITTING, FROM ONE DATA PROCESSING DEVICE TO ANOTHER, DATA OF DIFFERENT FORMATS ALONG WITH AN IDENTIFICATION OF THE FORMAT AND ITS CORRESPONDING DMA CONTROLLER

Yasuharu Shitara, Ashikaga; Noboru Hayasaka, Oizumi-machi, and Toshiya Kosuka, Chiyoda-machi, all of Japan, assignors to Sanyo Electric Co., Ltd., Osaka, Japan
Division of Ser. No. 316,830, Oct. 3, 1994, Pat. No. 5,430,844.
This application Apr. 20, 1995, Ser. No. 425,620
Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—200.15

16 Claims



1. A communication control system comprising:

- a transmission side communication control device including a transmitter for transmitting information in one of first and second formats, said transmission side communication control device comprising means for adding an identification bit to information to be transmitted by said transmitter, the identification bit identifying the format;
- a receiving side communication control device comprising:
 - a receiver for receiving the information transmitted from said transmitter;
 - a first memory for storing information received by said receiver;
 - a second memory for storing information received by said receiver;
 - a first direct memory access control means for controlling writing of received information into the first memory;
 - a second direct memory access control means for controlling writing of received information into the second memory; and
 - selection control means for judging whether information received by said receiver is in either the first format or second format, based on the identification bit added to said information, said selection control means being adapted to initiate control by the first direct memory access control means if the information is in the first format and to initiate

- a communication cable connected between said transmitter and said receiver, said cable having a first end connected to said transmission side communication control device and a second end connected to said receiving side communication control device.

5,588,121

PARALLEL COMPUTER HAVING MAC-RELAY LAYER SNOOPED TRANSPORT HEADER TO DETERMINE IF A MESSAGE SHOULD BE ROUTED DIRECTLY TO TRANSPORT LAYER DEPENDING ON ITS DESTINATION

Timothy G. Reddin, Stockport; David S. Walsh, Rossendale, and Jeremy S. Round, Warrington, all of Great Britain, assignors to International Computers Limited, London, England

Continuation of Ser. No. 176,784, Jan. 3, 1994, abandoned.


This application May 9, 1996, Ser. No. 647,192

Claims priority, application United Kingdom, Jan. 19, 1993, 9300942

Int. Cl.⁶ G06F 13/00; 13/14

U.S. Cl. 395—200.15

4 Claims



1. A parallel computer system comprising:

- at least one processing element including a protocol stack comprising a transport layer, a network layer, a logical link layer, a MAC-relay layer, and a network link layer;
- at least one communication element including a protocol stack comprising a transport layer, a network layer, a logical link layer, a MAC-relay layer, a network link layer, and an external MAC layer;
- an internal network interconnecting said processing element and said communication element for transmitting messages between said communication element and said processing element; each of said messages including transport header and MAC-relay header; and
- an external network coupled to said communication element with some other communication elements, for transmitting messages destined for said communication element and for said processing element, each of said messages including a transport header, a logical link header, and a MAC header;
- wherein said MAC layer and said MAC-relay layer in said communication element includes:
 - means for receiving a message from said external network by said MAC layer;
 - means for snooping on the transport header of said message by said MAC-relay layer to find whether the message is destined for service by the transport layer in the communication element or for service by the transport layer in the processing element;
 - means operative in the event that the message is destined for service by the transport layer in the communication element, for routing the message through the logical link

5,588,122

UNIVERSAL BUFFERED INTERFACE FOR COUPLING MULTIPLE PROCESSORS MEMORY UNITS, AND I/O INTERFACES TO A COMMON HIGH-SPEED INTERCONNECT

Armando Garcia, Yorktown Heights, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.


Continuation of Ser. No. 734,206, Jul. 22, 1991, abandoned.

This application Jun. 15, 1994, Ser. No. 260,107

Int. Cl.⁶ G06F 15/16

U.S. Cl. 395—250

33 Claims



1. Interface circuitry for use in a data processing system, said interface circuitry forming an interface unit and comprising:

- first interface means for coupling to a plurality of signal lines of a local bus, the local bus having a plurality of local bus agents coupled thereto, said local bus and said plurality of local bus agents being disposed external to said interface unit;
- second interface means for coupling to a plurality of signal lines of a global bus, the global bus having a plurality of global bus agents coupled thereto, said global bus and said plurality of global bus agents being disposed external to said interface unit;
- a plurality of input queue means each having an input coupled to the second interface means for receiving at least control information and data information from said global bus through the second interface means, each of the input queue means having an output coupled to the first interface means; and
- a plurality of output queue means each having an input coupled to the first interface means for receiving address information, control information, and data information from said local bus through the first interface means, each of the output queue means having an output coupled to the second interface means; wherein individual ones of the plurality of local bus agents each have dedicated thereto an individual one of the input queue means and an individual one of the output queue means for receiving information from the global bus and for transmitting information to the global bus, respectively; and wherein the second interface means includes means for selectively coupling an output of the second interface means to an input of the first interface means for bypassing the input queue means when the input queue means is empty.

5,588,123 BUS SYSTEM


Josef Loibl, Regen, Germany, assignor to Siemens Aktiengesellschaft, Munich, Germany

Filed May 26, 1994, Ser. No. 249,540

Claims priority, application European Pat. Off., Nov. 26, 1991, 91120166

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—287



1. A bus system, comprising:
 - a plurality of control devices;
 - a bus interconnecting said control devices, said control devices exchanging data via said bus;
 - a central device;
 - said central device reading out data transmitted on said bus, evaluating the data and generating items of information from the data;
 - said central device outputting the items of information through said bus as messages with a low transmission repetition frequency; and
 - said control devices extracting the items of information from said bus as individually required.

5,588,124 MICROCOMPUTER


Katsunobu Hongo, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Nov. 29, 1994, Ser. No. 351,000

Claims priority, application Japan, Nov. 29, 1993, 5-298087

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—287



1. A microcomputer to be connected with external circuits having different access cycles via a multiplex bus which transfers an address/data signal and control signals, comprising:
 - a means for generating a first control signal having a first level when a first external circuit is to be accessed, and otherwise having a second level; and
 - a control signal generating circuit responsive to said first control signal, for generating a second control signal when another external circuit is to be accessed, said second control signal changing from said second level to said first level at a different time than said first control signal.

5,588,125 METHOD AND APPARATUS FOR INCREASING BUS BANDWIDTH ON A SYSTEM BUS BY INHIBITING INTERRUPTS WHILE POSTED I/O WRITE OPERATIONS ARE PENDING


Brian R. Bennett, Laguna Niguel, Calif., assignor to AST Research, Inc., Irvine, Calif.

Continuation of Ser. No. 139,468, Oct. 20, 1993, abandoned.

This application Mar. 24, 1995, Ser. No. 410,560

Int. Cl.⁶ G06F 13/38; 9/46

U.S. Cl. 395—306



1. A method of increasing the bus bandwidth on a system bus in a computer system having a processor and a plurality of input/output (I/O) devices on an I/O bus, said system bus coupled to said I/O bus via a bus bridge such that said processor may communicate on said system bus independently of I/O activities on said I/O bus, said processor being able to communicate with said I/O devices on said I/O bus via said bus bridge, said computer system further comprising an interrupt controller having an output which propagates interrupts to said processor from said I/O devices, said method comprising the steps of:
 - posting a write operation from said processor directed to said I/O bus in said bus bridge;
 - inhibiting said output from said interrupt controller to preclude interrupts from propagating from said I/O bus to said system bus while said write operation is posted in said bus bridge;
 - transferring said posted write operation from said bus bridge to said I/O bus; and
 - uninhibiting said output from said interrupt controller to allow said interrupts to propagate from said I/O bus to said system bus after said write operation is transferred from said bus bridge to said I/O bus.

5,588,126 METHODS AND APPARATUS FOR FORWARDING BUFFERED STORE DATA ON AN OUT-OF-ORDER EXECUTION COMPUTER SYSTEM

Jeffrey M. Abramson, Aloha; Haitham Akkary, Portland; Andrew F. Glew, Hillsboro; Glenn J. Hinton; Kris G. Konigsfeld, both of Portland; Paul D. Madland, and David B. Papworth, both of Beaverton, all of Oreg., assignors to Intel Corporation, Santa Clara, Calif.


Division of Ser. No. 176,111, Dec. 30, 1993, abandoned. This application May 19, 1995, Ser. No. 446,030

Int. Cl.⁶ G06F 9/30

U.S. Cl. 395—376

8 Claims

1. An apparatus comprising:
 - a first buffer having a first plurality of buffer slots for buffering a plurality of memory store operations (STs) issued over a period of time for execution, potentially in an out-of-order (OOO) manner, each of said buffered STs including at least a store opcode, a store address and store data, and said first



- plurality of buffer slots being allocated to said buffered STs in a circular wraparound manner;
- a second buffer having a second plurality of buffer slots for correspondingly storing a plurality of allocation states of said first buffer for a plurality of memory load operations (LDs) issued for execution, also potentially in an OOO manner, each LD including at least a load opcode and a load address, each of said allocation states identifying the allocation state of said first buffer at the time the corresponding LD is issued;
- circuitry coupled to said first and second buffers for conditionally signaling said store buffer to output store data of one of said buffered STs on behalf of a buffered LD, and identifying the store data to be output for said store buffer, when the buffered LD is being executed, said circuitry including one of said allocation states that is corresponding to the buffered LD being executed as inputs, in determining whether said store buffer is to be signaled and identifying the appropriate store data to be output.

5,588,127 HIGH SPEED MICROPROCESSOR BRANCH DECISION CIRCUIT


Patrick W. Bosshart, Plano, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Continuation of Ser. No. 953,637, Sep. 29, 1992, Pat. No. 5,270,955. This application Jun. 7, 1995, Ser. No. 477,002

Int. Cl.⁶ G06F 9/302; 9/305; 9/34

U.S. Cl. 395—376

20 Claims



16. A circuit for providing a branch decision signal comprising:
 - a. an arithmetic logic unit carrying out an arithmetic logic operation, said arithmetic logic unit having as outputs a plurality of alu status signals, each alu status signal having at least two unique states, said plurality of alu status signals including a late arriving first alu status signal available from said arithmetic logic unit last among said plurality of alu status signals, said arithmetic logic unit having N bits, where N is an integer greater than one, said arithmetic logic unit consisting of an N-1 bit arithmetic logic unit having the architecture of an N bit arithmetic logic unit without carry-in and a 1 bit most significant bit arithmetic logic unit;
 - b. a first candidate branch decision circuit, said first candidate decision circuit being operable to compute a first candidate branch decision signal based upon said first alu status signal prior to availability of said first alu status signal from said

- arithmetic logic unit by assuming a first candidate value for said first alu status signal;
- c. a second candidate branch decision circuit, said second candidate decision circuit being operable to compute a second candidate branch decision signal based upon said first alu status signal prior to availability of said first alu status signal from said arithmetic logic unit by assuming a second candidate value for said first alu status signal, said second candidate value being a different unique state from said first candidate value;
- d. a first selection circuit for selecting from said first branch decision signal and said second branch decision signal, based upon an actual value of said first alu status signal when received from said arithmetic logic unit, the output of said first selection circuit being said branch decision signal.

5,588,128

DYNAMIC DIRECTION LOOK AHEAD READ BUFFER
Gary D. Hickok, Mesa, Ariz.; Eric A. Hildebrandt, and Micheal H. Zhu, both of San Jose, Calif., assignors to VLSI Technology, Inc., San Jose, Calif.


Continuation of Ser. No. 42,323, Apr. 2, 1993, abandoned.

This application Feb. 27, 1996, Ser. No. 607,372

Int. Cl.⁶ G06F 12/08; 13/00

U.S. Cl. 395—414

11 Claims



1. A look ahead read buffer comprising, in combination:
 - memory means for storing data;
 - control circuitry means coupled to said memory means for writing said data into said memory means in a sequential order and for reading said data out of said memory means in a read sequence in said sequential order, said sequential order being determined by a sequence of sequential addresses corresponding to locations of said data; and
 - dynamic direction means within said control circuitry means for changing direction of said read sequence from a first state to a second state and from said second state to said first state, said first state corresponding to an ascending sequence of said sequential addresses and said second state corresponding to a descending sequence of said sequential addresses, said dynamic direction means comprising:
 - range comparator means for comparing a first portion of a previous read address with a first like portion of a current read address, and having a range output in a true logic state when said first portion of said previous read address is equal to said first like portion of said current read address, and having said range output in a false logic state when said first portion of said previous read address is not equal to said first like portion of said current read address;
 - directional comparator means for comparing a second portion of said previous read address with a second like portion of said current read address, and having a direction output in a first logic state when said second portion of said previous read address is less than said second like portion of said current read address, and having said direction output in a second logic state when said second portion of said previous read address is not less than said second like portion of said current read address; and

logic means coupled to said range output and to said direction output for generating an UP/DOWN output indicating said prefetch direction, said UP/DOWN output reflecting the logic state of said direction output when said range output is in said true logic state.

5,588,129

CACHE FOR OPTICAL STORAGE DEVICE AND METHOD FOR IMPLEMENTING SAME

Clinton L. Ballard, 4721 NW. Blackhawk Ct., Bremerton, Wash. 98312


Continuation of Ser. No. 193,991, Feb. 9, 1994, abandoned.

This application Jan. 16, 1996, Ser. No. 585,808

Int. Cl.⁶ G06F 12/16

U.S. Cl. 395—440

2 Claims



1. A cache apparatus for storing data for a plurality of optical disk storage media alternatively loadable into a common optical disk drive, the apparatus comprising:

volatile memory and non-volatile memory for storing disk data read from the plurality of optical disk storage media, the volatile memory serving as a primary cache and the non-volatile memory serving as a secondary cache, the secondary cache comprising a portion of a

a plurality to a respective optical disk identification codes stored in non-volatile memory and corresponding to a plurality of optical disk storage media alternatively loadable into the common optical disk drive, each identification code unique to a corresponding optical disk storage media;

an index stored in non-volatile memory pointing among said plurality of identification codes to a currently accessible optical disk storage media;

a first data structure stored in non-volatile memory for mapping at least a portion of said disk data stored in the non-volatile memory to corresponding address locations on an associated optical disk storage media, said first data structure comprising a first tag associated with first disk data read from a first optical disk storage media and a second tag associated with second disk data read from a second optical disk storage media; and

a digital processing means allocating the nonvolatile memory no comprise:

a second data structure for storing disk data, the stored disk data in the second data structure being organized into a plurality of groups of disk data, and wherein only one group of the plurality of groups of disk data is active at one time, each one group being a physically contiguous sector area within the non-volatile memory;

a third data structure for storing a plurality of markers and a corresponding plurality of optical disk sector addresses, each marker of said plurality of markers corresponding to a group of

said plurality of groups of cached data; and the digital processing means allocating the volatile memory to comprise a fourth data structure for storing a portion of the disk data stored in the second data structure of the nonvolatile memory; the digital processing means processing a request to read disk data from an optical disk storage media in a and comprising:

(i) means for defining the index pointing among said plurality of identification codes which corresponds to a current optical disk storage media;

(ii) means for accessing the first data structure to identify whether disk data is stored in non-volatile memory; and

(iii) means for retrieving first disk data from said non volatile memory without first re-storing said first disk data from said first optical disk storage media into the non-volatile memory following changes in the current optical disk storage media away from the first optical disk storage media, when said disk data is stored in said non-volatile memory; and

said digital processing means executing a first computer program for covering stored disk data after a restoration of power, and further comprising:

(iv) means for determining one marker of the plurality of markers as being invalid and each other marker of the plurality of markers as being valid by scanning among the plurality of markers to identify a last valid marker before said one invalid marker;

(v) means for defining a next marker unique to all valid markers in said third data structure, wherein said next marker is an increment of said last valid marker;

(vi) means for deriving a next location in the second data structure corresponding to said next marker for storing disk data.

5,588,130

SEMICONDUCTOR MEMORY DEVICE FOR SIMPLE CACHE SYSTEM

Kazuyasu Fujishima; Yoshio Matsuda, and Mikio Asakura, all of Hyogo-ken, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 63,487, May 19, 1993, Pat. No.

5,353,427, which is a division of Ser. No. 564,657, Aug. 9,


1990, Pat. No. 5,226,147, which is a continuation of Ser. No. 266,601, Nov. 3, 1988. This application Aug. 1, 1994, Ser. No. 283,367

Claims priority, application Japan, Nov. 6, 1987, 62-281619; Dec. 17, 1987, 62-322126

Int. Cl.⁶ G06F 13/00; G11C 15/00

U.S. Cl. 395—445

27 Claims



1. A semiconductor memory device comprising:

a main memory including a plurality of memory cells, each storing information, arranged in a plurality of rows and a plurality of columns, said main memory being divided into a plurality of blocks in the unit of a plurality of columns, each block being formed on a semiconductor substrate in a physically gathered manner, a boundary region being provided between adjacent blocks on said semiconductor substrate, and

a cache memory including a plurality of storage elements arranged in a plurality of rows for storing in block units information read out in block units from said main memory.

5,588,131

SYSTEM AND METHOD FOR A SNOOPING AND SNARFING CACHE IN A MULTIPROCESSOR COMPUTER SYSTEM


Paul L. Borrell, Cupertino, Calif., assignor to Sun Microsystems, Inc., Mountain View, Calif.

Filed Mar. 9, 1994, Ser. No. 208,170

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—473

28 Claims



1. An apparatus configured to be inserted into a multiprocessor system having a plurality of data elements and a plurality of processor nodes coupled together by a shared interconnect, the shared interconnect configured to carry a plurality of data elements, the apparatus comprising:

a processor node;

a cache configured to cache a group of the plurality of data elements for the processor node; and

a snarfing mechanism, coupled to the cache, the snarfing mechanism, when inserted into the multiprocessor system, configured to check the cache to determine if the cache contains a copy of a data element appearing on the shared interconnect, and further programmed to snarf the data element off the shared interconnect if the cache has no copy of the data element.

5,588,132

METHOD AND APPARATUS FOR SYNCHRONIZING DATA QUEUES IN ASYMMETRIC REFLECTIVE MEMORIES


Wayne M. Cardoza, Amherst, N.H., assignor to Digital Equipment Corporation, Maynard, Mass.

Filed Oct. 20, 1994, Ser. No. 326,682

Int. Cl.⁶ G06F 13/14

U.S. Cl. 395—475

7 Claims



4. An apparatus for synchronizing modification of a common data structure shared by a plurality of processors, comprising:

an asymmetric reflective memory having a global write-only address space shared by the plurality of processors and a local read/write address space for each of the plurality of processors;

a queue element stored in the global write-only address space of the asymmetric reflective memory by a first processor, the asymmetric reflective memory to copy the queue element to the local read/write address space of a second processor the queue element storing common data to be shared by the plurality of processors;

a queue header stored in the global write-only address space of the asymmetric reflective memory by the first processor, the asymmetric reflective memory to copy the queue header to the local read/write address space of the second processor;

in response to detecting the queue element, means for reading the queue header and writing a zero in the queue header, the means for reading and writing the queue header performing the reading and writing steps atomically in the local read/write address space of the second processor;

means for processing the common data stored in the queue element; and

means for marking the queue element as processed in the global address space.

5,588,133

REGISTER BLOCK CIRCUIT FOR CENTRAL PROCESSING UNIT OF MICROCOMPUTER

Kazuyoshi Yoshida, Tokyo; Hiroshi Itoh; Hiroshi Fukuoka, both of Yokohama, and Makoto Shinohara, Kawasaki, all of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Continuation of Ser. No. 52,287, Apr. 26, 1993, Pat. No. 5,450,566, which is a continuation of Ser. No. 461,004, Jan. 4, 1990, abandoned. This application Jun. 2, 1995, Ser. No. 460,780

Claims priority, application Japan, Jan. 13, 1989, 1-7432

Int. Cl.⁶ G06F 12/06

U.S. Cl. 395—477

5 Claims



1. A register block circuit comprising:

a register array having a matrix structure made up of rows and columns, said rows having a plurality of banks, said banks having a plurality of registers corresponding to respective of the columns, and wherein the registers store data;

a plurality of data buses;

first selecting means for selecting one bank from among the banks of the register array;

second selecting means for selecting a plurality of registers from the bank selected by said first selecting means, and for connecting the selected registers to the data buses;

said second selecting means including:

first register number storing means for storing a plurality of register numbers which are used for reading out data,

second register number storing means for storing at least one register number which is used for writing data.

first register selecting means for selecting a plurality of registers used for reading out data from the bank selected by the first selecting means, on the basis of register numbers supplied from the first register number storing means, and for connecting the registers to the data buses, and second register selecting means for selecting at least one register used for writing data in the bank selected by the second register number storing means, on the basis of a register number or numbers supplied from the second register number storing means, and for connecting said at least one register to the data buses.

5,588,134


SYSTEM FOR ESTABLISHING PRIORITY AMONG SELECTED TASKS BASED ON LOCATION OF TASKS AND SEQUENCE THAT THE TASKS WERE STORED WHEREAS TASK IS ALWAYS STORED IN LOCATION WITH THE LOWEST AVAILABLE ADDRESS

John C. Oneto, Campbell, and Stephen P. Russell, Morgan Hill, both of Calif., assignors to Amdahl Corporation, Sunnyvale, Calif.

Filed Sep. 25, 1992, Ser. No. 951,387

Int. Cl. G06F 7/00; 7/04; 13/34

U.S. Cl. 395—485




1. In a system having a plurality of sources for generating tasks and a plurality of receivers for receiving said tasks wherein a plurality of said tasks for one or more said receivers may be generated at the same time by one or more of said sources, each said receiver having a unique address within said system, an apparatus comprising:

- storage means for storing said tasks generated by said sources into addressed locations within said storage means where a task when received by said storage means is always stored in a location which has the lowest address in said storage means and which is available to accept a task;
- address means for generating, in each system cycle, the address of one of said receivers; and
- priority means connected to said address means and said storage means for establishing priority among selected tasks, said selected tasks being those tasks for receiver whose address is being generated by said address means, and for generating a signal indicating which task of said selected tasks has priority, where said priority is established as a function of said selected tasks' location in said storage means and the sequence that said selected tasks were stored in said storage means.

5,588,135
DATA PROCESSING DEVICE IN A VIRTUAL MEMORY HAVING A PAGING FUNCTION
Takehiko Tanaka, Kawasaki, Japan, assignor to Fujitsu Limited, Kawasaki, Japan
Filed Oct. 7, 1993, Ser. No. 133,220
Claims priority, application Japan, Oct. 7, 1992, 4-268325
Int. Cl. G06F 12/06

U.S. Cl. 395—487

14 Claims



1. A data processing device having a paging function in which a main memory is divided into a plurality of page frames, a program is divided into pages of which size is the same as a page frame, page-out is performed when a required page is not written in the main memory, and, thereafter, page-in is performed to write a required page from an external memory into the main memory, comprising:

- measuring means for measuring for every page stored in the main memory time elapsed since the page was last referred to;
- grouping means for grouping the pages into page groups in which each page has the same elapsed time;
- counting means for counting a number of pages in each group of pages;
- adding means for adding the counted numbers for each of the groups, in order of decreasing the elapsed time for the group from longer elapsed time to shorter elapsed time, when a page fault occurs and some pages are requested to be paged-out;
- referenced elapsed time determining means for determining a elapsed time for a group, adding of the counted number for which causes a result of the adding to exceed a number of requested pages to be paged-out, as a reference elapsed time for pages to be paged out; and
- means for comparing the elapsed time of each page with the reference elapsed time and for determining the pages in which the elapsed time is greater than the reference elapsed time.

5,588,136
MEMORY CONTROL METHOD AND APPARATUS THEREFOR

Kimio Watanabe, Kawasaki, Japan, assignor to Fujitsu Limited, Kanagawa, Japan

Filed Jul. 26, 1994, Ser. No. 279,857

Claims priority, application Japan, Jan. 11, 1994, 6-001209


Int. Cl. G06F 11/00

U.S. Cl. 395—187

4 Claims

1. A memory controlling apparatus for serially storing the record information on an event into a memory of a predetermined size, storing the record information on a new event at the address at which the oldest record information is stored when said memory becomes full, and storing the record information on a new event at an apparently vacant address where the record information which has proved to be unnecessary as a result of reference is stored, said memory controlling apparatus comprising:

- a vacant address controller for storing the address data for specifying the vacant addresses where the record information



which is referred to has been stored, supplying the address data in the order of storage, and designating the addresses for storing the record information on new events by the supplied address data;

an LRU means for serially storing an address data which specifies the address of said memory at which record information is stored, said address data being input every time said record information is stored there and, if the same address data as that stored in said LRU means is input, eliminating the latter and storing the input address data as the latest address data;

a control unit for obtaining the address at which the oldest record information is stored from said LRU means, if no address is designated by said vacant address controller when a new event occurs, and storing the record information on said new event at said address obtained, while storing said record information on said new event at the designated address when said address is designated by said vacant address controller.

a means for monitoring the number of pieces of record information as an object of retrieval which inputs the address data for specifying n number of addresses where said record information referred to is stored to said vacant address controller and said LRU means in the order of reference, holds the latest n as the number of pieces of record information as an object of next retrieval and adds 1 to the number n of the pieces of record information as the objects of retrieval every time a new event occurs after new n events have occurred; and

a retrieving means for obtaining the addresses of the latest n pieces of record information in said memory from said LRU means, and retrieving the record information which satisfies a predetermined condition from said latest n pieces of record information.

5,588,137
DATA FLOW CONTROL APPARATUS AND MEMORY APPARATUS

Masato Yoneda, and Yoshiaki Shibata, both of Tokyo, Japan, assignors to Kawasaki Steel Corporation, Hyogo-ken, Japan

Filed May 31, 1994, Ser. No. 251,290

Claims priority, application Japan, Jun. 2, 1993, 5-131944; Jun. 10, 1993, 5-138635; Jun. 10, 1993, 5-138756; Jul. 19, 1993, 5-178044

Int. Cl. G06F 12/14; H04K 1/00; H04L 9/00

U.S. Cl. 395—490

33 Claims


1. A data flow control apparatus comprising:

- a first input terminal for sequentially receiving a first input data;
- a second input terminal for sequentially receiving a second input data;

an output terminal through which output data are sequentially outputted;

memory means for storing one or more replacement data which are defined for associated one or more arrays, respectively, each including a plurality of said first input data; and

data switching means for outputting through said output terminal, as said output data, mutually different data which are selected from among a data group in accordance with whether or not a plurality of said first input data, which include an up-to-date first input data entered through said first input terminal and go back from the up-to-date first input data to



5,588,138

DYNAMIC PARTITIONING OF MEMORY INTO CENTRAL AND PERIPHERAL SUBREGIONS

Baocheng Bai, Havertown; Mahmut Guner, Landenberg; Duojia Lu, Norristown; David A. Rosenblitt, Unionville, and Kaaren L. Stuck, West Chester, all of Pa., assignors to Gestalt Technologies, Incorporated, Landenberg, Pa.


Continuation of Ser. No. 141,778, Oct. 22, 1993, abandoned.

This application Feb. 8, 1996, Ser. No. 598,401

Int. Cl. G06F 12/02

U.S. Cl. 395—497.04

27 Claims



1. A distributed memory system for a computer system having means for concurrently executing a plurality of processes comprising:

- (a) a memory;
- (b) means for dynamically partitioning the memory into variable-size regions, each region including a central subregion and at least four sibling peripheral subregions, and means for further subdividing each peripheral subregion into a center subregion and at least four sibling subregions;
- (c) means for allocating each central subregion to a specific concurrently executing process; and

(d) means within each region for dynamically controlling memory use within that region and for directly addressing memory locations without requiring any relocation of data.

5,588,139

METHOD AND SYSTEM FOR GENERATING OBJECTS FOR A MULTI-PERSON VIRTUAL WORLD USING DATA FLOW NETWORKS


Jaron Z. Lanier, Palo Alto; Jean-Jacques G. Grimaud, Portola Valley; Young L. Harvill; Ann Lasko-Harvill, both of San Mateo; Chuck L. Blanchard, Palo Alto; Mark L. Oberman, Mountain View, and Michael A. Teitel, La Honda, all of Calif., assignors to VPL Research, Inc., Redwood City, Calif. Continuation of Ser. No. 535,253, Jun. 7, 1990, abandoned.

This application Oct. 8, 1993, Ser. No. 133,802

Int. Cl. G06F 9/455

U.S. Cl. 395-500

30 Claims



1. A simulating apparatus comprising: modeling means for creating a model of a physical environment in a computer database; first body sensing means, disposed in close proximity to a part of a first body, for sensing a physical status of the first body part relative to a first reference position; second body sensing means, disposed in close proximity to a part of a second body, for sensing a physical status of the second body part relative to a second reference position; first body emulating means, coupled to the first body sensing means, for creating a first cursor in the computer database, the first cursor including plural first cursor nodes and emulating the physical status of the first body part, the first body emulating means including a first point hierarchy and a first data flow network, the first point hierarchy for controlling a shape and an orientation of the first cursor nodes hierarchically with at least one other of the plural first cursor nodes, the first data flow network for controlling motion of the first cursor and the first data flow network including a first interconnection of first input units, first function units and first output units, the first input unit receiving the physical status of the first body part, each first function unit including at least one input and at least one output and calculating, based on the at least one input, a value for each of the at least one output, and the first output units for producing position and orientation values for a portion of the plural first cursor nodes; first integrating means, coupled to the modeling means and to the first emulating means, for integrating the first cursor with the model; second body emulating means, coupled to the second body sensing means, for creating a second cursor in the computer database, the second cursor including plural second cursor nodes and emulating the physical status of the second body part, the second body emulating means including a second point hierarchy and a second data flow network, the second point hierarchy for controlling a shape and an orientation of

the second cursor and for attaching each of the plural second cursor nodes hierarchically with at least one other of the plural second cursor nodes, the second data flow network for controlling motion of the second cursor and the second data flow network including a second interconnection of second input units, second function units and second output units, the second input units receiving the physical status of the second body part, each second function unit including at least one input and at least one output and calculating, based on the at least one input, a value for each of the at least one output, and the second output units for producing position and orientation values for a portion of the plural second cursor nodes; and second integration means, coupled to the modeling means and to the second body emulating means, for integrating the second cursor with the model.

5,588,140

TRANSPARENT EXTENSION OF PERIPHERAL FROM HOST


Eugene D. Misukanis, Little Canada; John H. Long, Richfield; Lawrence A. Dean, Vadnais Heights, and Douglas J. Kullgowski, Brooklyn Park, all of Minn., assignors to Computer Network Technology Corporation, Minneapolis, Minn.

Filed Mar. 15, 1993, Ser. No. 31,543

Int. Cl. G06F 9/455; 13/00; 15/00

U.S. Cl. 395-500

13 Claims



1. A method of extending the operating distance between a host computer and a peripheral device, comprising the steps of: (a) providing a host extender for communicating directly with the host computer; (b) providing a peripheral extender for communicating directly with the peripheral device and connecting the host extender and the peripheral extender; (c) obtaining data storage characteristics of the peripheral device in order for the host extender to emulate the peripheral device, comprising the steps of: (1) generating a channel program in the host extender to read the data storage characteristics of the peripheral device; (2) transmitting the channel program to the peripheral extender; (3) the peripheral extender querying the peripheral device in accordance with the channel program; (4) the peripheral extender receiving the data storage characteristics from the peripheral device; (5) the peripheral extender transmitting the data storage characteristics to the host extender; and (6) the host extender storing the data storage characteristics in a host extender cache; (d) the host extender receiving one or more channel commands from the host computer; and (e) the host extender responding to the host computer as if it were the peripheral device, based at least in part on the data storage characteristics of the peripheral device stored in the extender cache.

SYSTEM FOR EXECUTING DIFFERENT FUNCTIONS ASSOCIATED WITH DIFFERENT CONTEXTS CORRESPONDING TO DIFFERENT SCREEN EVENTS BASED UPON INFORMATION STORED IN UNIFIED DATA STRUCTURE


Walter R. Smith, Palo Alto, and Stephen P. Capps, San Carlos, both of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Filed Jul. 30, 1993, Ser. No. 99,852

Int. Cl. G06F 9/006

U.S. Cl. 395-500

27 Claims



1. A computer-implemented method for accomplishing unified data structure operations in connection with a computer including a unified data structure, a computer interface system, and a computer execution system, said method including the steps of:

- activating a selected screen on a computer display by effecting a screen event with a predetermined context, said selected screen being implemented by said computer interface system wherein a plurality of predetermined contexts are available with said computer display, and each one of said plurality of predetermined contexts is associated with a different one of a plurality of screen events;
- sending a message with respect to the predetermined context of the indicated screen event to a first unified data structure element of said unified data structure, said first unified data structure element being associated with said predetermined context, and said unified data structure being common to, and able to be shared by, the computer interface system and the computer execution system;
- responding to the message according to the predetermined context of the associated screen event, including execution by the computer execution system utilizing said unified data structure of at least a single function object associated with the predetermined context of the message, wherein different function objects are associated with different ones of said plurality of predetermined contexts; and
- referring to at least a second unified data structure element of said unified data structure pointed to by the first unified data structure element according to the predetermined context of the message, the referring under control of the computer execution system.

5,588,142

METHOD FOR SIMULATING A CIRCUIT

David Sharrit, Santa Rosa, Calif., assignor to Hewlett-Packard Company, Palo Alto, Calif.


Filed May 12, 1995, Ser. No. 440,204

Int. Cl. G06F 9/455; 17/50

U.S. Cl. 395-500

5 Claims

1. In a method for simulating the response of a circuit to a stimulating signal using a digital computer, said circuit being



represented by a plurality of nodes, each said node being connected to one or more devices, each said device corresponding to a computer routine that provides the current sourced by the corresponding device when said nodes are held at a set of potentials provided to said routine, the improvement comprising the step of approximating said stimulating signal, $v(t)$, by

$$v(t) = \text{Real} \left(\sum_{k=1}^K V_k(t) e^{j\omega_k t} \right)$$

where $V_k(t)$ is a time varying voltage, and $K \geq 0$.

5,588,143

AUTOMATIC COMPUTER UPGRADING


Richard A. Stupek, Jr., Houston; David S. Shaffer; Curtis R. Jones, both of Cypress; Steve Davis, and William D. Justice, Jr., both of Houston, all of Tex., assignors to Compaq Computer Corporation, Houston, Tex.

Continuation of Ser. No. 303,173, Sep. 8, 1994. This application May 23, 1995, Ser. No. 447,980

Int. Cl. G06F 7/02

U.S. Cl. 395-500

4 Claims



1. A method for use in changing a resource of a computer from a first version of the resource to a second version of the resource, comprising: digitally storing, on a portable medium, the second version of the resource and replacement information which identifies the second version, describes features of the second version relative to at least one earlier version of the resource, identifies the location of the second version of the resource on the portable medium, provides instructions for installation of the second version of the resource, describes at least one reason for the second version, indicates a type of change from other versions to the second version, and indicates the importance of the change from the other versions to the second version, digitally storing in the computer information identifying the first version, by computer, automatically determining which of the other versions is the first version.


based on the results of the determining step,
automatically determining whether to change the resource,
and
automatically changing the resource.

5,588,144

STORAGE SYSTEM HAVING A BUS COMMON TO A PLURALITY OF KINDS OF GROUPS OF PACKAGES
Mitsuru Inoue, Odawara, and Hiroyuki Kurosawa, Hiratsuka, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Nov. 29, 1994, Ser. No. 346,440
Claims priority, application Japan, Dec. 3, 1993, 5-303775
Int. Cl.⁶ G06F 1/14

U.S. Cl. 395—555

10 Claims



1. A storage system for connection to a host computer, the system having a common bus and comprising:
a plurality of host interface logic devices to be connected to the host computer and constituting an interface to the host computer; and
a storage device for storing data;
a plurality of storage device interface logic devices connected to the storage device each constituting an interface to said storage device; and
a plurality of cache memory devices each for temporarily storing data transmitted between said host interface logic devices and said storage interface logic devices;
wherein each of said plurality of host interface logic devices, said plurality of storage device interface logic devices, and said cache memory devices constitutes a package which is connected to said common bus respectively, the common bus connecting these devices to each other, and each said package has an independently operable clock circuit for supplying a clock to the circuit therein and a control means for executing a blocking processing by stopping the supply of said clock to said circuit therein, and each package is detachably mounted to the common bus.

5,588,145

METHOD AND ARRANGEMENT FOR CLOCK ADJUSTMENT USING PROGRAMMABLE PERIOD BINARY RATE MULTIPLIER

John A. Wishneusky, Bolton, Mass., assignor to Cirrus Logic, Inc., Fremont, Calif.


Filed Mar. 31, 1995, Ser. No. 415,021

Int. Cl.⁶ G06F 1/08

U.S. Cl. 395—555

51 Claims

1. An apparatus for scaling a first clock frequency output by a computer device clock to generate a second clock frequency, comprising:



counter means responsive to said clock for counting pulses of said first clock frequency;
first comparator means responsive to said counter means and a period count value for generating a periodic clock frequency; and
second comparator means responsive to said periodic clock frequency and a divisor count value for scaling said periodic clock frequency to generate said second clock frequency.

5,588,146

METHOD FOR THE ACQUISITION OF SOFTWARE AND DATA-PROCESSING SYSTEM TO IMPLEMENT THE METHOD


Jean-Yves Leroux, Bouc Bel Air, France, assignor to Gemplus Card International, Gemenos, France

Filed Oct. 21, 1993, Ser. No. 140,661

Claims priority, application France, Oct. 23, 1992, 92 12702
Int. Cl.⁶ G06F 17/30; 12/14; 15/163

U.S. Cl. 395—601

20 Claims



1. A method for the acquisition of software programs from a database service center by a computer, the method comprising the steps of:

loading a plurality of software programs into the data base service center;
providing a user of a microcomputer with a first removable electronic memory carrier containing a right of access to a specific subset of the plurality of software programs of the database service center, the first memory carrier having insufficient capacity to store the specific subset of the plurality of software programs;
providing the user of the microcomputer with a right of use proper to the specific subset of the plurality of software programs, the right of use being provided on a second removable electronic memory carrier;
introducing the first memory carrier into a first memory carrier drive of the microcomputer;
remote-loading the specific subset of the plurality of software programs from the service center into the microcomputer, the remote-loading being authorized based on the right of access contained in the first memory carrier provided to the user;
introducing the second memory carrier into a second memory carrier drive of the microcomputer;
executing the specific subset of the plurality of software programs, the executing step being performed by the microcomputer; and
interrogating the memory carrier to check the right of use, and permitting or prohibiting continued execution of the specific subset of the plurality of software programs based on the interrogating step.

5,588,147

REPLICATION FACILITY


Yuval Neeman, Bellevue; Peter Cook, Redmond; Arnold S. Miller, Bellevue, and Balan Raman, Redmond, all of Wash., assignors to Microsoft Corporation, Redmond, Wash.

Filed Jan. 14, 1994, Ser. No. 181,704

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—601

29 Claims



1. In a distributed system having a replication facility and a number of computer systems that each include a storage device, a method comprising the steps of:
providing a plurality of files organized into a tree of files;

replicating a single one of the files that is stored in the storage device of one of the computer systems using the replication facility so that a copy of the file is stored in the storage device of another of the computer systems; and
replicating a subtree of files of multiple levels, from the tree of files, that is stored in the storage device of one of the computer systems using the replication facility so that a copy of the subtree of files is stored in the storage device of another of the computer systems.

5,588,148

METHOD FOR MANAGING DATA TRANSFER BETWEEN COMPUTING DEVICES


Michael R. Landis; Anthony J. Yeates, both of Cary, and Thomas J. Gavin, Arlington Heights, all of Ill., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Sep. 6, 1994, Ser. No. 301,374

Int. Cl.⁶ G06F 17/30

U.S. Cl. 395—601

13 Claims



1. A method, comprising the steps of:
receiving a message identifying a particular data set and a client profile;
determining whether the particular data set represents a complete data set;
confirming that the particular data set represents the complete data set, when the particular data set does represent the complete data set; and
using the client profile to determine whether to transmit additional data to complete the particular data set, or the complete data set to replace the particular data set, when the particular data set does not represent the complete data set.

5,588,149

DOCUMENT CLASSIFICATION AND RETRIEVAL WITH TITLE-BASED ON-THE-FLY CLASS MERGE

Kenji Hirose, Yokohama, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Filed Sep. 16, 1994, Ser. No. 306,947


Claims priority, application Japan, Sep. 21, 1993, 5-234979

Int. Cl.⁶ G06F 17/30

U.S. Cl. 395—601

2 Claims

1. A data processing system, comprising:
first recording means for recording a plurality of data;
second recording means for recording retrieval titles including a plurality of retrieving keys used for retrieving data recorded in the first recording means;



third recording means for recording a correspondence table in which a plurality of different symbols respectively correspond to a plurality of series of letters respectively used as retrieving keys;

retrieval title producing means for producing the retrieval titles to be recorded in the second recording means by designating a symbol in the correspondence table recorded in the third recording means, and recording the designated symbol as a retrieving key;

first designating means for designating a plurality of series of letters recorded in the correspondence table in the third recording means in order to integrate the designated series of letters into one series of letters;

second designating means for designating a new series of letters for the plurality of series of letters designated by the first designating means;

third designating means for designating a symbol corresponding to the new series of letters designated by the second designating means;

first processing means for deleting the plurality of series of letters designated by the first designating means from the correspondence table in the third recording means and for recording in the correspondence table the new series of letters in correspondence with the symbol designated by the third designating means; and

second processing means for extracting a symbol corresponding to the series of letters to be integrated, designated by the first designating means, from the retrieval titles recorded in the second recording means, and changing the extracted symbol to the symbol designated by the third designating means.

5,588,150

PUSH DOWN OPTIMIZATION IN A DISTRIBUTED, MULTI-DATABASE SYSTEM

Eileen T. Lin, San Jose, and Yun Wang, Saratoga, both of Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 29, 1994, Ser. No. 310,797


Int. Cl.⁶ G06F 17/30

U.S. Cl. 395—601

7 Claims

1. In a heterogeneous, distributed database system having a plurality of database instances, a computer-based method of optimizing performance of the database system by determining whether a query can be pushed down to a single database instance, comprising the steps of:

(1) evaluating the query for data coverage by determining whether all data referenced in the query is located within a single database instance;



- (2) evaluating the query for capability coverage by determining whether all capabilities referenced in the query can be performed by said single database instance; and
- (3) pushing down the query to the single database instance if said data coverage and said capability coverage are satisfied.

5,588,151

APPARATUS AND METHOD FOR COMMUNICATION SWITCHING INCLUDING PROVIDING INFORMATION OVERFLOW INDICATIONS

Jacob Segal, Ra'Anana; Josef Ben-Moshe, Holon; Zvika Weinstein, Petach Tikva, and Zvika Harnik, Rishon LeZion, all of Israel, assignors to Lannet Data Communications Ltd., Tel Aviv, Israel

Continuation of Ser. No. 217,328, Mar. 24, 1994, abandoned.

This application Sep. 8, 1995, Ser. No. 525,500

Claims priority, application Israel, Jan. 31, 1994, 108505

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—800

12 Claims



1. Communication switching apparatus for providing LAN communication among a multiplicity of digital information processors, each said processor conventionally including an activity detector operative to cause the processor to refrain from transmitting information onto a medium when the activity detector encounters a symptom of activity on said medium,

the switching apparatus including:

- a plurality of ports each communicating with at least one of the digital information processors via said medium;
- a LAN port interconnector interconnecting at least two of said plurality of ports; and
- an overflow indicator, sensing overflow at at least one of the LAN port interconnector; and
- at least one of the plurality of ports;

the switching apparatus being characterized in that the overflow indicator, upon sensing said overflow, provides an artificially generated symptom of activity to at least one said activity detector.

5,588,152

ADVANCED PARALLEL PROCESSOR INCLUDING ADVANCED SUPPORT HARDWARE

Michael C. Dapp, Endwell; Thomas N. Barker, Vestal; James W. Dieffenderfer, Owego; Billy J. Knowles, Kingston; Donald M. Lesmeister, Vestal; Richard E. Nier, Apalachin; David B. Rolfe, West Hurley, and Vincent J. Smoral, Endwell, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Continuation of Ser. No. 380,230, Jan. 30, 1995, abandoned, and Ser. No. 887,612, May 22, 1992, abandoned, and a continuation-in-part of Ser. No. 324,295, Oct. 17, 1994, Pat. No. 5,475,856, and Ser. No. 301,278, Sep. 6, 1994, which is a continuation of Ser. No. 611,594, Nov. 13, 1990, abandoned.

This application Aug. 25, 1995, Ser. No. 519,859


Int. Cl.⁶ G06F 15/80

U.S. Cl. 395—800

16 Claims

1. A computer system, comprising:

- a plurality of processor-memory elements (PME's), each processor-memory element (PME) containing a processor, a memory, and a multi-bit parallel data path therebetween;



a plurality of nodes interconnected as a multi-dimensional network cluster, each node containing a plurality of processor-memory elements (PME's); and

a cluster controller for said plurality of nodes;

wherein each processor-memory element (PME) of a node has a plurality of communication paths to processor-memory elements (PME's) within the node and at least one communication path to a processor-memory element (PME) external to the node.

VOL
11 93

ISS
4

DE
24

19 96

UMI

DESIGN PATENTS
GRANTED December 24, 1996

ERRATA

For	See
CLASS	PATENT NO.
D12-220	D376,792
D008-354	D376,815

VOL
11 93

ISS
4

DE
24

1996

UMI

DESIGNS

DECEMBER 24, 1996

376,679

GARMENT WITH DETACHABLE BIB

John G. Edens, and LouAnn S. Edens, both of 1623 Fawn-
haven Way, Lodi, Calif. 95240

Filed Mar. 3, 1995, Ser. No. 35,606

Term of patent 14 years

U.S. Cl. D2—733



376,681

HEADWRAP WITH DETACHABLE VISOR

John P. Riesenman, and Terri S. Riesenman, both of 2097 E.
Washington St., #1E397, Colton, Calif. 92324

Filed Nov. 28, 1995, Ser. No. 47,148

Term of patent 14 years

U.S. Cl. D2—879



376,680


LONG PANTS

Luigi Volpati, Piazza Padella 7, I-00062 Bracciano (Roma),
Italy

Filed Oct. 7, 1994, Ser. No. 29,497

Term of patent 14 years

U.S. Cl. D2—742



376,682


RIGID CAP

Claude P. Johnson, 2301 N. 50th St., Philadelphia, Pa. 19131

Filed Jun. 15, 1995, Ser. No. 40,358

Term of patent 14 years

U.S. Cl. D2—882




376,683

OUTSOLE FOR A ATHLETIC SHOE

Paul A. Gaudio, Lake Oswego, and Keven C. Malkewitz, Portland, both of Oreg., assignors to Adidas AG, Germany
 Filed Aug. 25, 1995, Ser. No. 43,367

Term of patent 14 years

U.S. Cl. D2—954



376,685


PAINTED GLASS PILL CONTAINER WITH ATTACHABLE MOUNTING PLATE

Laurence A. Weller, and Helen L. Weller, both of 2101 Santa Clara Dr., Las Vegas, Nev. 89104

Filed Apr. 15, 1996, Ser. No. 53,130

Term of patent 14 years

U.S. Cl. D3—203



376,684

SHOE UPPER

Mike Brooks, Nelsonville; Edgar H. Simpson; Theodore A. Kastner, both of Lancaster, and Diana A. Wurfain, Athens, all of Ohio, assignors to Rocky Shoes & Boots, Inc., Nelsonville, Ohio

Filed Mar. 2, 1995, Ser. No. 35,556

Term of patent 14 years

U.S. Cl. D2—970



376,686


RUCKSACK

Martial Daboudet, 23, rue des Solitaires, 75019 Paris, France

Filed Jul. 12, 1995, Ser. No. 41,392

Term of patent 14 years

U.S. Cl. D3—217



376,687


GOLF ACCESSORY

Michael R. Carretta, Tranquility, N.J., and Harry Balestrieri, Plantation, Fla., assignors to M. R. Carretta & Co., Inc., Allamuchy, N.J.

Filed Dec. 21, 1995, Ser. No. 48,174

Term of patent 14 years

U.S. Cl. D3—221



376,689


COMBINATION CHAISE CUSHION AND CARRY BAG

Jerald Doppelt, 6 Linden Ave., West Orange, N.J. 07052

Filed Jan. 2, 1996, Ser. No. 48,814

Term of patent 14 years

U.S. Cl. D3—274



376,688


SEMICONDUCTOR WAFER CASSETTE TRANSPORT BOX

Gary M. Gallagher; Boyd C. Wittman, both of Colorado Springs, Colo., and Edmund B. Neumann, Corvallis, Oreg., assignors to Empak, Inc., Chanhassen, Minn.

Filed Dec. 20, 1994, Ser. No. 32,529

Term of patent 14 years

U.S. Cl. D3—273



376,690


BATTERY STORAGE CASE HAVING A FOAM INSERT FOR RECEIVING A PLURALITY OF DIFFERENT SIZED BATTERIES

Andrew J. Lockerby, 11 Rosenfeld Rd., Millis, Mass. 02054

Filed Feb. 9, 1996, Ser. No. 50,171

Term of patent 14 years

U.S. Cl. D3—284



376,691


PORTABLE SECURITY CASE

Robert L. Naas, Skaneateles, and Mark A. Ferguson, Jamesville, both of N.Y., assignors to John D. Brush & Co., Inc., Rochester, N.Y.

Filed Mar. 8, 1995, Ser. No. 35,857

Term of patent 14 years

U.S. Cl. D3—294



376,693


STORAGE CONTAINER LID

Stacy L. Wolff, Akron, Ohio, assignor to Rubbermaid Incorporated, Wooster, Ohio

Filed May 5, 1995, Ser. No. 38,451

Term of patent 14 years

U.S. Cl. D3—323



376,694

BRUSH

Sanjay Aiyar, 18671 E. Woodwind Ln., Anaheim, Calif. 92807

Filed Oct. 18, 1995, Ser. No. 46,633

Term of patent 14 years

U.S. Cl. D4—102

376,692



LOG CARRIER

Larry E. Hartman, 15520 98th Avenue #204, Edmonton, Alberta, Canada

Filed Jul. 12, 1995, Ser. No. 41,372

Term of patent 14 years

U.S. Cl. D3—315



376,695


HANDLE FOR A TOOTHBRUSH AND TONGUE CLEANER

Rimvydas Tveras, 8945 W. 103rd St., Palos Hills, Ill. 60465, assignor to Rimvydas Tveras, Palos Hills, Ill.

Filed Dec. 4, 1995, Ser. No. 47,405

Term of patent 14 years

U.S. Cl. D4—104



376,697


COMBINED CONTAINER AND APPLICATOR

Carl E. Green, and Alexandra R. Green, both of 322 S. Hamilton, Lincoln, Ill. 62656

Filed Apr. 24, 1995, Ser. No. 37,887

Term of patent 14 years

U.S. Cl. D4—114



376,696


TOOTH BRUSH WITH REMOVABLE HEAD

William T. Vogel, Jr., 266 Center St., Lackawanna, N.Y. 14218

Filed Oct. 3, 1994, Ser. No. 29,317

Term of patent 14 years

U.S. Cl. D4—104



376,698


BROOM

Dennis Mikuljan, 4119 Independence Ave., Mississauga, ON, Canada

Filed Dec. 19, 1995, Ser. No. 48,047

Term of patent 14 years

U.S. Cl. D4—132



376,699


PROTECTIVE CLOTHES HANGER

Sharon A. Wood, 3355 S. Tulare Ct., Denver, Colo. 80231

Filed Jan. 23, 1995, Ser. No. 33,907

Term of patent 14 years

U.S. Cl. D6—318



376,701


ROTATIONAL BOLSTER SEAT

Donald P. Thompson, Sarasota, Fla., assignor to Genmar Industries, Inc., Minneapolis, Minn.

Filed Dec. 1, 1995, Ser. No. 47,327

Term of patent 14 years

U.S. Cl. D6—367



376,700


CHAIR

Frederick Brush, 53 East Ave., Norwalk, Conn. 06851

Filed Oct. 17, 1994, Ser. No. 29,793

Term of patent 14 years

U.S. Cl. D6—334



376,702


STACK CHAIR

Gary S. Cretcher, 7669 Harrisburg Hollow, Bata, N.Y. 14810

Filed Sep. 29, 1995, Ser. No. 44,752

Term of patent 14 years

U.S. Cl. D6—379



376,703

CHAIR

Chan-shin Lee, No. 303, Tzuli 1st Rd., Sanmin Dist., Kaohsiung, Taiwan

Filed Mar. 11, 1996, Ser. No. 51,449

Term of patent 14 years

U.S. Cl. D6—380



376,705


FREESTANDING WORKSTATION

John P. Stoddard; Roberto G. Fraquelli, both of London, England, and David F. Lyons, Grosse Pointe Farms, Mich., assignors to Haworth, Inc., Holland, Mich.

Filed Jun. 9, 1995, Ser. No. 40,056

Term of patent 14 years

U.S. Cl. D6—426



376,706


DESK

B. Cameron Smith, Seattle, Wash., assignor to Hon Industries Inc., Muscatine, Iowa

Filed Sep. 27, 1995, Ser. No. 44,636

Term of patent 14 years

U.S. Cl. D6—426



376,704


KITCHEN UTILITY RACK

Johanna Burt, 2125 Palm Vista Dr., Apopka, Fla. 32712

Filed Sep. 18, 1995, Ser. No. 44,099

Term of patent 14 years

U.S. Cl. D6—396



376,707


TRI-LEVEL COMPUTER CENTER

Randy G. Beason, 6445 N. Merck St., Kansas City, Mo. 64118

Filed Dec. 18, 1995, Ser. No. 47,975

Term of patent 14 years

U.S. Cl. D6—426



376,709

ADVERTISING DISPLAY FOR SHELVING


Richard Markson, Goshen, N.Y., assignor to Markson

Rosenthal & Company, Edgewater, N.J.

Filed Jul. 19, 1995, Ser. No. 41,618

Term of patent 14 years

U.S. Cl. D6—449



376,708


PATIO/BALCONY RAIL TABLE

Edward J. Robertson, Winchester, and Norbert Lyons, Middleton, both of Mass., assignors to Syroco, Inc., East Boston, Mass.

Filed Jul. 31, 1995, Ser. No. 42,027

Term of patent 14 years

U.S. Cl. D6—429



376,710


DISPLAY BOX

Salim G. Kara, Houston, Tex., assignor to Post N Mail, L.C., Houston, Tex.

Filed Jun. 14, 1995, Ser. No. 40,296

Term of patent 14 years

U.S. Cl. D6—470



376,711


TABLE

Charles C. Harris, High Point, N.C., assignor to Victus, Ltd., Greensboro, N.C.

Filed Apr. 25, 1995, Ser. No. 39,788

Term of patent 14 years

U.S. Cl. D6—480



376,713


ADJUSTABLE LEG

Francis F. Kelso, 1546 S. Devonshire Ave., Westlake Village, Calif. 91361

Filed Jun. 21, 1995, Ser. No. 40,526

Term of patent 14 years

U.S. Cl. D6—496



376,714


WALL MOUNTED PLANTER

Chris J. Dallimore, 5084 S. 10th East, Salt Lake City, Utah 84117

Continuation-in-part of Ser. No. 7,570, Apr. 27, 1993, Pat. No. Des. 362,405. This application Jun. 7, 1995, Ser. No. 40,452

Term of patent 14 years

U.S. Cl. D6—556



376,712

TABLE

Wolfgang C. R. Mezger, Eislingen, Germany, assignor to Wilhelm Renz GmbH & Co., Germany

Filed Mar. 24, 1995, Ser. No. 36,675

Claims priority, application Germany, Sep. 28, 1994, M 94 07 813.0

U.S. Cl. D6—487



376,715


RECREATIONAL VEHICLE PEDESTAL

Jeffrey P. Few, West Hills, Calif., assignor to Norco Industries, Inc., Compton, Calif.

Filed Aug. 18, 1994, Ser. No. 27,325

Term of patent 14 years

U.S. Cl. D6—500



376,717

Patent Not Issued For This Number

376,718


BANDAGE DISPENSER

Kimberly A. Wilcox, 4904 Lucille Ave. SE., Salem, Ore. 97302

Filed Oct. 18, 1995, Ser. No. 45,388

Term of patent 14 years

U.S. Cl. D6—518



376,716

CHAIR ARMREST

Steve J. Nemeth, Jr., Park Township, Ottawa County, Mich., assignor to Haworth, Inc., Holland, Mich.

Filed Jun. 9, 1995, Ser. No. 40,055

Term of patent 14 years

U.S. Cl. D6—501



376,719


WALL-MOUNTED SOAP DISH

Beril-Volf Leykekhmakher, 2400 E. 3rd St. #203, Brooklyn, N.Y. 11223-5303, and Anna Berenbaum, 2-37 29th St., Fair Lawn, N.J. 07410

Filed Sep. 25, 1995, Ser. No. 44,499

Term of patent 14 years

U.S. Cl. D6—540



376,720

COMFORTER HAVING SEPARABLE HALVES

Wayne P. Thode, and Monique J. Thode, both of 6 Pleasant St., C-7, Hooksett, N.H. 03106

Filed Mar. 7, 1995, Ser. No. 35,829

Term of patent 14 years

U.S. Cl. D6—603



376,722

FIELD OVEN


Tor A. Oftedal, Oslo, and Odd Halsnes, Båstad, both of Norway, assignors to Forsvarets Forskningsinstitutt Avdeling for vaper og materiell, Kjeller, Norway

Filed Jul. 11, 1994, Ser. No. 25,755

Claims priority, application Norway, Jan. 17, 1994, D940027

Term of patent 14 years

U.S. Cl. D7—332



376,721


TEAPOT

Kuo-Chang Chen, Tainan Shien, Taiwan, assignor to Songson Industrial Arts Co., Ltd., Tainan Hsien, Taiwan

Filed Jan. 4, 1996, Ser. No. 44,827

Term of patent 14 years

U.S. Cl. D7—371



376,723


PIZZA SERVING DISH

David J. Asner, Moore, Okla., assignor to Aco, Inc., Oklahoma City, Okla.

Filed May 17, 1995, Ser. No. 38,975

Term of patent 14 years

U.S. Cl. D7—359



376,724


FRYER/COOKER

Lewis A. Mendelson, Overland Park, Kans., and Foster L. Taige, III, Kansas City, Mo., assignors to Dazey Corporation, New Century, Kans.

Filed May 23, 1995, Ser. No. 39,311

Term of patent 14 years

U.S. Cl. D7—360



376,726

HANDLE FOR A COOKING VESSEL


Jeffrey Rohrer, Kewaskum, Wis., assignor to Regal Ware, Inc., Kewaskum, Wis.

Division of Ser. No. 35,299, Feb. 24, 1995, Pat. No. Des.

369,718. This application Sep. 15, 1995, Ser. No. 44,077

Term of patent 14 years

U.S. Cl. D7—393



376,725


HOME PASTA MAKER

Eddy Kang, Taipei, Taiwan, assignor to Mitco International Ltd., Hsin Tien, Taiwan

Filed Jul. 8, 1994, Ser. No. 25,704

Term of patent 14 years

U.S. Cl. D7—376



376,727

HANDLE FOR UTENSIL

Gerd-Diethard Baumgarten, Wilsdorf-Wilden, Germany, assignor to Heinrich Baumgarten KG Spezialfabrik fuer Beschlagteile, Neunkirchen, Germany

Filed Aug. 3, 1995, Ser. No. 42,196

Term of patent 14 years

U.S. Cl. D7—395



376,728


BEVERAGE CUP

Theodore N. Richards, Sr., and Emily G. Richards, both of Rear 38, W. Enterprise St., Glen Lyon, Pa. 18617

Filed Dec. 12, 1994, Ser. No. 31,987

Term of patent 14 years

U.S. Cl. D7—507



376,730

DRINK CONTAINER

Dwayne S. Hurst, Tampa, and Charles B. Williams, Odessa, both of Fla., assignors to Palomino Sports, Inc., Odessa, Fla.


Filed Feb. 9, 1994, Ser. No. 18,535

The portion of the term of this patent subsequent to Aug. 20,

2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D7—515



376,731

MUG

Rick Lin, Tainan, Taiwan, assignor to Juei Chywan Enterprise Co., Ltd., Tainan, Taiwan


Filed Jun. 12, 1995, Ser. No. 40,160

The portion of the term of this patent subsequent to Apr. 30,

2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D7—536



376,729


GLASS WITH INSET HAND GRIP

Mary Maki, 6641 202nd St. N., Forest Lake, Minn. 55025

Filed Dec. 8, 1995, Ser. No. 47,638

Term of patent 14 years

U.S. Cl. D7—514



376,732

PLATE WITH CENTER HOT DOG COMPARTMENT


Bette E. Smith, 23681 Posey La., West Hills, Calif. 91304

Filed May 1, 1995, Ser. No. 38,223

The portion of the term of this patent subsequent to Sep. 10, 2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D7—555



376,734

BABY FORMULA CASE


Aidan J. Petrie, Providence, R.I., assignor to The First Years Inc., Avon, Mass.

Continuation of Ser. No. 31,020, Nov. 15, 1994, abandoned.

This application Sep. 29, 1995, Ser. No. 44,818

Term of patent 14 years

U.S. Cl. D7—629



376,733

DRINK HOLDER


Don Bellisario, 161 North Rivermede Rd. Unit #5, Toronto, Ontario, Canada

Filed Dec. 26, 1995, Ser. No. 48,327

Claims priority, application Canada, Nov. 4, 1995, 1995-2464

Term of patent 14 years

U.S. Cl. D7—619



376,735


NAPKIN HOLDER WITH A MOVABLE PROTECTION CAP

Fiorentino DeSimone, Largo Olgiata 15 - Isola 2E, 00123 Rome, Italy

Filed Jun. 1, 1995, Ser. No. 39,675

Term of patent 14 years

U.S. Cl. D7—631



376,736

JUICE EXTRACTOR


Jong-Gill Kim, 301, Hyundai Villa, 2/1, 810-14, Banghae-dong, Seocho-ku, Seoul, Rep. of Korea

Filed Oct. 25, 1995, Ser. No. 45,653

Claims priority, application Rep. of Korea, May 15, 1995, 8986/1995

Term of patent 14 years

U.S. Cl. D7—665



376,738

LUNCH BOX

Paul S. Wang, 22428 Steeple Chase La., Diamond Bar, Calif. 91765

Filed Nov. 22, 1995, Ser. No. 47,106

Term of patent 14 years

U.S. Cl. D7—709



376,737


CUTTING BOARD WITH PLASTIC BAG HOLDER

Raymond G. Hecker, 300 Twin Dr., Caseyville, Ill. 62232

Filed Jun. 5, 1995, Ser. No. 39,723

Term of patent 14 years

U.S. Cl. D7—698



376,739


CUTTING LINE FOR A ROTATING LINE TRIMMER

David B. Skinner, Columbia, S.C., assignor to Shakespeare Company, Columbia, S.C.

Filed Sep. 12, 1995, Ser. No. 43,774

Term of patent 14 years

U.S. Cl. D8—8



376,740


HEDGE TRIMMER

Paul Gildersleeve, Lutherville, Md., assignor to Black & Decker Inc., Newark, Del.

Filed Jul. 28, 1995, Ser. No. 41,993

Term of patent 14 years

U.S. Cl. D8—8



376,742


TOOL HANDLE

Christine E. Filowiak, West Fairview, and Barry R. Albert, Camp Hill, both of Pa., assignors to True Temper Hardware Company, Camp Hill, Pa.

Filed Jul. 27, 1995, Ser. No. 41,946

Term of patent 14 years

U.S. Cl. D8—13



376,741


MULCHING ATTACHMENT FOR A LAWN MOWER

Gerald R. Sadlowski, Sr., 4515 Groveland St., Bradenton, Fla. 34207

Filed Sep. 25, 1995, Ser. No. 44,449

Term of patent 14 years

U.S. Cl. D8—8



376,743


COMBINED FOLDING KNIFE HANDLE AND BLADE SEGMENTS

Brett P. Seber, Escondido, and Roy L. Helton, Jr., San Diego, both of Calif., assignors to Buck Knives, Inc., El Cajon, Calif.

Continuation-in-part of Ser. No. 138,703, Oct. 18, 1993, abandoned, Ser. No. 138,670, Oct. 18, 1993, abandoned, Ser. No. 26,042, Jul. 18, 1994, Pat. No. Des. 369,287, and Ser. No. 26,044, Jul. 18, 1994. This application Sep. 16, 1994, Ser. No. 28,510

Term of patent 14 years

U.S. Cl. D8—99



376,744

SUPPORT PLATE


Gerd Eisenblätter, Königsdorf, Germany, assignor to Gerd Monico Abeyta, 1323 S. 40th St., Tacoma, Wash. 98408

Eisenblätter GmbH, Geretsried, Germany

Filed Aug. 3, 1994, Ser. No. 26,695

Term of patent 14 years

U.S. Cl. D8—70




376,746

WINDOW FRAME EXTRACTING TOOL

Filed Dec. 1, 1995, Ser. No. 47,369

Term of patent 14 years

U.S. Cl. D8—88



376,745

HUB DRIVING GRADE ROD

Benjamin A. Scott, Rte. 1, Box 303A, Corinth, Miss. 38834

Filed Sep. 12, 1995, Ser. No. 43,771

Term of patent 14 years

U.S. Cl. D8—75



376,747


DOOR SECURITY DEVICE

Ronald E. Jackson, 216 W. Southport Rd., Indianapolis, Ind. 46217

Filed Aug. 3, 1994, Ser. No. 26,680

Term of patent 14 years

U.S. Cl. D8—330




376,748

PADLOCK SHACKLE GUARD

Michael H. Small, 4966 Red Bluff Rd., Riverside, Calif. 92503,
and Kevin E. Small, 270 Main St., Cedarville, Calif. 96104
Filed Jun. 29, 1995, Ser. No. 40,864

Term of patent 14 years

U.S. Cl. D8—346



376,750


GAS DISPENSER PROP

Patrick Ferguson, 528 Ft. Washington Ave., Ft. Washington,
Pa. 19034, and Rocco J. Bucci, 1720 Hood La., Maple Glen,
Pa. 19002

Filed Aug. 2, 1995, Ser. No. 42,147

Term of patent 14 years

U.S. Cl. D8—354




376,749

BRACKET

Allen C. Hertzog, 306 Rte. 9 Apt. 40, Cape May, N.J. 08204
Filed Feb. 15, 1995, Ser. No. 34,883

Term of patent 14 years

U.S. Cl. D8—349



376,751


FLANGED RECEIVER MOUNTING BRACKET

Marvin L. Hanson, Vandalia, Mich.; Richard McCoy, Granger,
Ind., and Jon L. Krager, Cassopolis, Mich., assignors to
Reese Products, Inc., Elkhart, Ind.

Filed Oct. 20, 1995, Ser. No. 46,644

Term of patent 14 years

U.S. Cl. D8—354



376,752


CLEAT FIXABLE TO THE TOE RAIL OF A BOAT FOR
ATTACHING A SPRING LINE

Ronald Benveniste, 3600 Ridgewood, suite 506, Montreal, Que-
bec, Canada

Filed Nov. 24, 1995, Ser. No. 47,006

Term of patent 14 years

U.S. Cl. D8—356



376,754


REVEAL TRACK

Bryan Livingston; Douglas Hopkins; Harry O'Neil, and Rob
Reilly, all of 885 B S. Pickett St., Alexandria, Va. 22304

Filed May 5, 1995, Ser. No. 38,419

Term of patent 14 years

U.S. Cl. D8—377



376,753

FOOT MEMBER


Toshirobu Nakamura, Tokyo, Japan, assignor to Shinagawa
Shoko Co., Ltd., Tokyo, Japan

Filed Mar. 1, 1996, Ser. No. 50,990

Claims priority, application Japan, Nov. 13, 1995, 7-33912

Term of patent 14 years

U.S. Cl. D8—374



376,755


CURTAIN ROD HANGER

Lonnie E. Cox, 179 Richardson Rd., Maynard, Ark. 72444

Filed Oct. 31, 1995, Ser. No. 47,803

Term of patent 14 years

U.S. Cl. D8—380



376,756


REMOVABLE FASTENER

William E. Adams, Portersville, Pa., assignor to Adams Mfg. Corp., Portersville, Pa.

Filed Dec. 29, 1995, Ser. No. 48,474

Term of patent 14 years

U.S. Cl. D8—382



376,758

CONTAINER


Richard D. Bradfield, Fetcham, United Kingdom, assignor to Thomas J. Lipton Co., Division of Conopco, Inc., Englewood Cliffs, N.J.

Filed Jun. 7, 1995, Ser. No. 39,930

Claims priority, application United Kingdom, Dec. 9, 1994, 2043840

Term of patent 14 years

U.S. Cl. D9—430



376,759

CONTAINER


Richard D. Bradfield, Fetcham, United Kingdom, assignor to Thomas J. Lipton Co., Division of Conopco, Inc., Englewood Cliffs, N.J.

Filed Jun. 7, 1995, Ser. No. 39,931

Claims priority, application United Kingdom, Dec. 9, 1994, 2043839

Term of patent 14 years

U.S. Cl. D9—432



376,757


SUGAR HOUSE SYRUP CONTAINER WITH CAP

Elmer E. Kress, Southbury, Conn., and Richard G. Haas, South Deerfield, Mass., assignors to Hillside Plastics, Inc., Turners Falls, Mass.

Filed Mar. 28, 1995, Ser. No. 36,807

Term of patent 14 years

U.S. Cl. D9—322



376,760

BOTTLE

Donald J. Sykes, Upper Saddle River, N.J., assignor to Marpac Industries, Inc., Waldwick, N.J.

Filed Apr. 28, 1994, Ser. No. 22,103

Term of patent 14 years

U.S. Cl. D9—500



376,762


BOTTLE

Russell R. Fenton, and Elmer H. Goss, both of East Amherst, N.Y., assignors to FWJ Plastics, Inc., Tonawanda, N.Y.

Filed Nov. 30, 1995, Ser. No. 47,269

Term of patent 14 years

U.S. Cl. D9—549



376,761

COMBINED BOTTLE AND CAP

Gregory A. Lathrop, Manchester; Mark D. Gerhart, Westminster; David F. Gnadt; Arnold Brown, both of Owings Mills, all of Md.; Frank E. Gonda, Fairfield, Conn., and Harry H. Houbert, Freehold, N.J., assignors to Lever Brothers Company, Division of Conopco, Inc., New York, N.Y.

Filed Mar. 31, 1995, Ser. No. 36,988

The portion of the term of this patent subsequent to Sep. 10, 2014, has been disclaimed.

Term of patent 14 years

U.S. Cl. D9—528



376,763


ELECTRONIC TEMPERATURE MONITOR CASING

Neal P. Flora, Anaheim; Taylor C. Fletcher, Fullerton, and Carl E. Lind, Santa Ana, all of Calif., assignors to FSW, Inc., Anaheim, Calif.

Filed Oct. 6, 1995, Ser. No. 45,060

Term of patent 14 years

U.S. Cl. D10—52



376,764


BABY MONITOR TRANSMITTER

Blair S. Barnes, Denver, Colo., assignor to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 2, 1995, Ser. No. 45,914

Term of patent 14 years

U.S. Cl. D10—104



376,766


**HAND-HELD PERSONAL SECURITY DEVICE FOR
EMITTING A CHEMICAL SPRAY AS WELL AS
PROVIDING AN AUDIBLE ALARM AND A LIGHT**

Richard Cranford, 401 Greensward La., A104, Del Ray Beach, Fla. 33445, and D. Robert Jordan, 1094 Fisher La., Winnetka, Ill. 60093

Filed Nov. 14, 1994, Ser. No. 31,207

Term of patent 14 years

U.S. Cl. D10—106



376,765

BABY MONITOR RECEIVER

Blair S. Barnes, Denver, Colo., assignor to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 6, 1995, Ser. No. 46,029

Term of patent 14 years

U.S. Cl. D10—104



376,767


COMBINED REMOTE CONTROL AND ALARM UNIT

Jesus Duran, 4383 Dante Ave., Fresno, Calif. 93722

Filed Nov. 16, 1995, Ser. No. 46,832

Term of patent 14 years

U.S. Cl. D10—106



376,768

DUAL HOLE EARRING

Margaret M. Ross, 3695 Duxbury La., Lansing, Mich. 48906

Filed Jan. 30, 1995, Ser. No. 34,197

Term of patent 14 years

U.S. Cl. D11—41



376,770

GIFT PACKAGE ORNAMENT

Michelle Vasquez, 5297 Clato St., Kalamazoo, Mich. 49004

Filed Dec. 1, 1995, Ser. No. 47,366

Term of patent 14 years

U.S. Cl. D11—184



376,769


**ARTIFICIAL GREENERY/FLORAL ARRANGEMENT
DEVICE**

Gary L. Kreidler, South Chicago Heights, Ill., assignor to H.O.S. Floral Supply, Inc., South Chicago Heights, Ill.

Filed Jun. 2, 1995, Ser. No. 39,712

Term of patent 14 years

U.S. Cl. D11—155



376,771


BUCKLE FASTENER FOR IN-LINE SKATE

Ching-Hwo Cheng, 26 Lane 93, Changliwu Road, Changhwa County, Taiwan

Filed Jan. 18, 1996, Ser. No. 49,148

Term of patent 14 years

U.S. Cl. D11—216



376,772

TRUCK BODY


Roger Martin, Toronto, Canada, assignor to Unicell Limited, Toronto, Canada

Filed Sep. 22, 1994, Ser. No. 28,766

Claims priority, application Canada, Mar. 22, 1994, 1994 0559

Term of patent 14 years

U.S. Cl. D12—96



376,774


VEHICLE TRAILER BODY

Osamu Shikado, Rochester Hills; Thomas C. Slanec, Grosse Pointe Woods, and John E. Crain, Birmingham, all of Mich., assignors to Chrysler Corporation, Auburn Hills, Mich.

Filed Dec. 19, 1995, Ser. No. 48,077

Term of patent 14 years

U.S. Cl. D12—102



376,773

BICYCLE TRAILER


Robert Bell, 16 Oxford Street, Guelph, Ontario, Canada

Filed Aug. 29, 1994, Ser. No. 27,760

Claims priority, application Canada, Mar. 15, 1994, 1994-0493

Term of patent 14 years

U.S. Cl. D12—101



376,775


DECORATIVE BICYCLE FRAME SHROUD

Mu-tung Fang, No. 8-1, Hsin Yi Rd., Tainan City, Taiwan

Filed Dec. 7, 1995, Ser. No. 47,571

Term of patent 14 years

U.S. Cl. D12—117



376,776

BICYCLE SUPPORT

Beat Götschi, and Hans Pletscher, both of Marthalen, Switzerland, assignors to Gebrüder Pletscher AG, Marthalen, Switzerland


Division of Ser. No. 25,749, Jul. 11, 1994. This application

Dec. 14, 1995, Ser. No. 47,926

Claims priority, application Switzerland, Feb. 8, 1994, DMA/002422

Term of patent 14 years

U.S. Cl. D12—120



376,778

AUTOMOBILE TIRE


Yoshimasa Hashimoto; Sadakazu Takei; Toshihiko Suzuki, all of Hiratsuka; Izumi Kuramochi, and Hiroshi Tokizaki, both of Tokyo, all of Japan, assignors to The Yokohama Rubber Co., Ltd., Tokyo, Japan

Filed Feb. 27, 1995, Ser. No. 35,498

Claims priority, application Japan, Aug. 31, 1994, 6-25937

Term of patent 14 years

U.S. Cl. D12—147



376,779

AUTOMOBILE TIRE


Masatoshi Kuwajima; Sadakazu Takei, and Toshihiko Suzuki, all of Hiratsuka, Japan, assignors to The Yokohama Rubber Co., Ltd., Tokyo, Japan

Filed Mar. 15, 1995, Ser. No. 36,225

Claims priority, application Japan, Sep. 21, 1994, 6-28412

Term of patent 14 years

U.S. Cl. D12—147



376,777


DUAL ACTION WALKER

Clive G. Stevens, 7F, No. 291, Ta Tun 4th Street, Taichung City, Taiwan

Filed Sep. 11, 1995, Ser. No. 43,711

Term of patent 14 years

U.S. Cl. D12—130



376,780


ADJUSTABLE HEIGHT HITCH BALL UNIT

Richard McCoy, Granger, Ind., assignor to Reese Products, Inc., Elkhart, Ind.

Filed Oct. 20, 1995, Ser. No. 45,459

Term of patent 14 years

U.S. Cl. D12—162



376,782


EXTENDED VEHICLE BRUSHGUARD

Mark S. Kincart, 19511 N. 53rd Dr., Glendale, Ariz. 85308

Filed Jan. 22, 1996, Ser. No. 49,286

Term of patent 14 years

U.S. Cl. D12—171



376,781

ROOF RACK SIDE SUPPORT FOR A PASSENGER CAR


Thilo Ludewig, Leonberg, and Erhard Wolf, Stuttgart, both of Germany, assignors to Dr. Ing. h.c.F. Porsche AG, Weissach, Germany

Filed May 12, 1995, Ser. No. 38,737

Claims priority, application Germany, Nov. 12, 1994, M 94 08 827.6

Term of patent 14 years

U.S. Cl. D12—406



376,783


AXLE BRAKE

Manuel C. Magalhaes, 9 Saljon Ct., Centereach, N.Y. 11720

Filed Jul. 24, 1995, Ser. No. 41,758

Term of patent 14 years

U.S. Cl. D12—180



376,784


TIRE LADDER

Dennis W. Miller, Clearwater, Fla., assignor to Pasha Enterprises, Inc., Clearwater, Fla.

Filed Aug. 30, 1995, Ser. No. 43,261

Term of patent 14 years

U.S. Cl. D12—203



376,786


RIBBED COAXIAL WELDING CABLE

Alexander Binzel, Jr., Hallenweg 18, CH 4132 Muttens, Switzerland

Filed May 19, 1995, Ser. No. 39,055

Term of patent 14 years

U.S. Cl. D13—153



376,785

INVERTER


Kumiko Ikeda; Tsunehisa Yamaguchi; Wataru Suematsu; Masatake Yoshihara, and Tomoyasu Hachiro, all of Tokyo, Japan, assignors to Kabushiki Kaisha Meidensha, Tokyo, Japan

Filed Jul. 22, 1994, Ser. No. 26,223

Claims priority, application Japan, Jan. 27, 1994, 6-1496; Jan. 27, 1994, 6-1497

Term of patent 14 years

U.S. Cl. D13—110



376,787


VIDEO DISPLAY PEDESTAL

Clifford T. Calfee, Richardson, Tex., assignor to Vu Rytte, Inc., Tyler, Tex.

Continuation-in-part of Ser. No. 873,035, Apr. 22, 1992. This application Dec. 14, 1994, Ser. No. 32,207

Term of patent 14 years

U.S. Cl. D14—114



376,788


CURSOR CONTROL WITH PISTON GRIP

Robert L. Emery, Morgan Hill, Calif., assignor to MicroSpeed, Inc., Fremont, Calif.

Filed Jun. 19, 1995, Ser. No. 40,441

Term of patent 14 years

U.S. Cl. D14—114



376,790

COMPUTER HAND CONTROLLER

Matthew G. Goulet, 1606 Chatham St., Racine, Wis. 53402, and Robert E. Taylor, 15 Alina St., Fairport, N.Y. 14450

Filed Dec. 21, 1995, Ser. No. 48,147

Term of patent 14 years

U.S. Cl. D14—114



376,789


ELECTRONIC CONTROL DEVICE

James D. Tickle, Thousand Oaks, Calif., assignor to Interlink Electronics, Inc., Camarillo, Calif.

Filed Nov. 13, 1995, Ser. No. 46,287

Term of patent 14 years

U.S. Cl. D14—114



376,791


MOUSE PAD

Michael J. Schreiner, Bay Village, Ohio, assignor to Hunt Holdings, Inc., Wilmington, Del.

Filed Aug. 4, 1992, Ser. No. 924,540

Term of patent 14 years

U.S. Cl. D14—114



376,792


WINDSHIELD WIPER BLADE

Richard W. Chodkiewicz, 16217 Dale St., Detroit, Mich. 48219

Filed Dec. 8, 1995, Ser. No. 47,616

Term of patent 14 years

U.S. Cl. D12—220



376,794

FACSIMILE


Bong W. Lim, Kyungki-do, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea

Filed Jan. 16, 1996, Ser. No. 49,637

Claims priority, application Rep. of Korea, Jul. 25, 1995, 1995-14068

Term of patent 14 years

U.S. Cl. D14—118



376,793

FACSIMILE MACHINE

Keiichiro Satoh, Nara, and Hidetoshi Fujimoto, Yamatoko-riyama, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan

Filed Jan. 4, 1996, Ser. No. 48,577

Claims priority, application Japan, Jul. 18, 1995, 7-20796; Jul. 18, 1995, 7-20797

Term of patent 14 years

U.S. Cl. D14—118



376,795

GAME CARTRIDGE


Kenichiro Ashida, Kyoto, Japan, assignor to Nintendo of America, Inc., Redmond, Wash.

Filed May 2, 1995, Ser. No. 38,389

Claims priority, application Japan, Jan. 18, 1995, 7-961; Jan. 18, 1995, 7-962; Jan. 18, 1995, 7-963; Jan. 18, 1995, 7-964; Apr. 11, 1995, 7-10168; Apr. 17, 1995, 7-10709

Term of patent 14 years

U.S. Cl. D14—121




376,796

**RIBBON CASSETTE FOR A VIDEO GAME MACHINE
WITH SEAL PRINTER**

Yukinori Hirasawa, Tokyo, Japan, assignor to Casio Computer Co., Ltd., Tokyo, Japan
Filed Dec. 28, 1995, Ser. No. 48,440
Term of patent 14 years

U.S. Cl. D14—121




376,798

CONSOLE TELEVISION

Thomas E. Renk, Indianapolis, Ind., assignor to Thomson Consumer Electronics, Inc., Indianapolis, Ind.
Filed Aug. 23, 1995, Ser. No. 46,778
Term of patent 14 years

U.S. Cl. D14—133




376,799

TELEPHONE BASE

Joost Godee, and Daniel Harden, both of Palo Alto, Calif., assignors to Proteg Technologies Pte. Ltd., Singapore, Singapore

Filed Aug. 14, 1995, Ser. No. 42,619
Term of patent 14 years

U.S. Cl. D14—150



376,797

VCR PROTECTOR

John R. Harris, and Robin Ball, both of Box 2472, St. Mary's, ON, Canada

Filed Feb. 20, 1996, Ser. No. 50,436
Term of patent 14 years

U.S. Cl. D14—121




376,800

RADIO RECEIVER

Tomoyuki Shudo, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Filed Mar. 7, 1995, Ser. No. 35,790
Term of patent 14 years

U.S. Cl. D14—197




376,802

SPEAKER ENCLOSURE

Frankie J. Asencio, Columbus, Ohio, assignor to Network Entertainment Systems, Inc., Columbus, Ohio

Filed Aug. 29, 1995, Ser. No. 43,212
Term of patent 14 years

U.S. Cl. D14—213




376,801

**COMBINED MINIATURE BOOM BOX AND CLOCK
RADIO**

James L. Hanig, Highland Park; Richard L. Ettelson, Chicago, both of Ill., and Leung Y. Mina, Victoria, Australia, assignors to Hanig & Co., Inc., Lincolnwood, Ill.

Filed Jan. 2, 1996, Ser. No. 48,520
Term of patent 14 years

U.S. Cl. D14—171



376,803

KARAOKE MICROPHONE

Kee-Woon Lee, Buchon, Rep. of Korea, assignor to Sycom International Corp., Taichung City, Taiwan

Filed Mar. 25, 1996, Ser. No. 52,150
Term of patent 14 years

U.S. Cl. D14—228



376,804


WIRELESS LOCAL LOOP HANDSET

Steven A. Mergenthaler, Boulder, Colo., and Dawn E. Beattie, Carlsbad, Calif., assignors to QUALCOMM Incorporated, San Diego, Calif.

Filed Dec. 1, 1995, Ser. No. 47,359

Term of patent 14 years

U.S. Cl. D14—248



376,806


COMPOUND MITER SAW

Jeffrey S. Holly; Andrew L. Itzov, both of Menomonee Falls; Charles A. Hirsch, Brown Deer; Robert D. Davis, Oshkosh, and Richard P. Brault, Cedarburg, all of Wis., assignors to Milwaukee Electric Tool Corporation, Brookfield, Wis.

Filed Jul. 20, 1994, Ser. No. 26,145

Term of patent 14 years

U.S. Cl. D15—133



376,805

HOLDER FOR MOBILE PHONE IN VEHICLES


Ebbe Johansson, Karlsborg, Sweden, assignor to Brodit Plast AB, Karlsborg, Sweden

Filed Sep. 25, 1995, Ser. No. 44,457

Claims priority, application Sweden, Jun. 2, 1995, 95-1130

Term of patent 14 years

U.S. Cl. D14—253



376,807

METAL SLOTING CUTTER


Amir Satran, and Yaron Elzen, both of Kfar Vradim, Israel, assignors to Iscar Ltd., Migdal Tefen, Israel

Filed Jun. 6, 1995, Ser. No. 39,828

Claims priority, application Israel, Dec. 7, 1994, 23636

Term of patent 14 years

U.S. Cl. D15—139



376,808

MILLING HEAD


Wlajko Mihic, Gävle, Sweden, assignor to Mircona Aktiebolag, Gävle, Sweden

Filed Sep. 20, 1995, Ser. No. 44,220

Claims priority, application Sweden, Mar. 22, 1995, 95-0597

Term of patent 14 years

U.S. Cl. D15—139



376,810


FRAMES OF SUNGLASSES

Yuzuru Ohie, Higashiosaka, Japan, assignor to OGK Hanbai Co. Ltd., Osaka, Japan

Filed Jan. 22, 1996, Ser. No. 49,228

Term of patent 14 years

U.S. Cl. D16—326



376,809

SPADE-TYPE BORING BIT


Paul A. Stone, York County, Pa.; Rickey J. Thomas, Carroll County, and Chris McKenna, Baltimore, both of Md., assignors to Black & Decker Inc., Newark, Del.

Division of Ser. No. 32,861, Dec. 30, 1994. This application

Nov. 7, 1995, Ser. No. 46,087

Term of patent 14 years

U.S. Cl. D15—139



376,811

PAIR OF FALSE SIDEBURNS FOR SUNGLASSES


Allen Lowe, 1148 12th St. S., Birmingham, Ala. 35205

Continuation of Ser. No. 930,048, Aug. 17, 1992, abandoned.

This application Sep. 12, 1994, Ser. No. 28,333

Term of patent 14 years

U.S. Cl. D16—341



376,812


**ELECTRONIC TYPEWRITER HAVING A FULL-SIZE
DISPLAY SCREEN**Toshimi Chiba, Irvine, Calif., assignor to Canon Business
Machines, Inc., Costa Mesa, Calif.

Filed Sep. 7, 1995, Ser. No. 43,606

The portion of the term of this patent subsequent to Oct. 29,
2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D18—1



376,814


PRINTERTomonari Asai, and Shinji Matsumoto, both of Toyokawa,
Japan, assignors to Minolta Co., Ltd., Osaka, Japan

Filed Dec. 7, 1994, Ser. No. 31,837

Claims priority, application Japan, Jun. 10, 1994, 6-17043

Term of patent 14 years

U.S. Cl. D18—50



376,813


BINDING DEVICEAndreas Haug; Tom Schönherr, both of Stuttgart, Germany,
and Hiroshi Otsuka, Funabashi, Japan, assignors to King
Jim Co., Ltd., Tokyo, Japan

Filed Nov. 28, 1995, Ser. No. 47,194

Claims priority, application Japan, May 31, 1995, 7-15164

Term of patent 14 years

U.S. Cl. D18—34




376,815

INSERTJames H. Vermillion, 2025 W. Century Way, Boise, Id. 83709
Filed Aug. 25, 1994, Ser. No. 27,632

Term of patent 14 years

U.S. Cl. D8—354




376,816

BUSINESS FORMJeffrey M. Sisilli, North Hollywood, Calif., assignor to The
Reynolds and Reynolds Company, Dayton, Ohio

Filed Dec. 14, 1995, Ser. No. 48,777

Term of patent 14 years

U.S. Cl. D19—1



376,818

TALKING GLOBE BASEDennis J. Graham, Long Beach; Gregory B. Bergeron, La
Habra, and Damon R. Saddler, Inglewood, all of Calif.,
assignors to Educational Insights, Inc., Carson, Calif.

Filed Jan. 31, 1996, Ser. No. 49,787

Term of patent 14 years

U.S. Cl. D19—61



376,817

WRITING INSTRUMENTMaria Boix Gacia, Barcelona, Spain, assignor to Inoxcrom,
S.A., Barcelona, Spain

Filed Dec. 28, 1995, Ser. No. 48,418

Term of patent 14 years

U.S. Cl. D19—51




376,819

VENDING MACHINE HOUSINGDuncan J. Milcetic, 91 Clapham Ave., Manhasset, N.Y. 11030
Continuation-in-part of Ser. No. 208,724, Mar. 9, 1994, Pat.
No. 5,472,074. This application Jun. 20, 1995, Ser. No. 40,488

Term of patent 14 years

U.S. Cl. D20—1



376,820

ROADSIDE ADDRESS POST

Steven K. Bosman, 539 E. Smith Rd., Bellingham, Wash. 98226
 Filed Feb. 14, 1995, Ser. No. 34,839

Term of patent 14 years

U.S. Cl. D20—17



376,822


HAND-HELD ELECTRONIC GAME HOUSING

Ralph F. Osterhout, San Francisco, Calif., assignor to Tiger Electronics, Inc., Vernon Hills, Ill.

Filed Jan. 17, 1995, Ser. No. 33,610

Term of patent 14 years

U.S. Cl. D21—13



376,821


COMBINED CROWD CONTROL AND ADVERTISING DEVICE

Norman B. Hathaway, North Salem, N.Y., assignor to Stainless Image Inc., Danbury, Conn.

Filed Jul. 11, 1995, Ser. No. 41,845

Term of patent 14 years

U.S. Cl. D20—41



376,823

MAGNET OPTICAL DISC PLAYER COMBINED WITH DISPLAY MONITOR


Takashi Ikenaga, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Filed Nov. 28, 1995, Ser. No. 47,165

Claims priority, application Japan, Jun. 7, 1995, 7-16015

Term of patent 14 years

U.S. Cl. D21—13



376,824


CHESS GAME BOARD

Clifton W. King, 715 Shawnee Dr., Nashville, Tenn. 37205

Filed Aug. 31, 1994, Ser. No. 27,844

Term of patent 14 years

U.S. Cl. D21—32



376,826

CONTROLLER FOR GAME MACHINE

Kenichiro Ashida, Kyoto, Japan, assignor to Nintendo of America, Inc., Redmond, Wash.

Filed May 2, 1995, Ser. No. 38,390

Claims priority, application Japan, Dec. 19, 1994, 6-38779;
 Apr. 25, 1995, 7-11888; Apr. 25, 1995, 7-11889

Term of patent 14 years

U.S. Cl. D21—48



376,825

VIDEO BLACKJACK TABLE

Cory J. Hanscom, New Hope, Minn., assignor to Innovative Gaming Corporation of America, Reno, Nev.

Filed Sep. 22, 1994, Ser. No. 28,792

Term of patent 14 years

U.S. Cl. D21—37



376,827


TOY BUILDING ELEMENT

Ib T. Skov, Billund, Denmark, assignor to INTERLEGO AG, Baar, Switzerland

Filed Sep. 14, 1995, Ser. No. 43,996

Term of patent 14 years

U.S. Cl. D21—108



376,828

ENCLOSURE FOR AN EXERCISE APPARATUS

Kristin Conley, Lynnfield, Mass.; Jerry W. Lee, Kirkland, and
Craig L. Johnson, Bothell, both of Wash., assignors to Stair-
Master Sports/Medical Products, L.P., Kirkland, Wash.

Filed Jul. 24, 1995, Ser. No. 41,785

Term of patent 14 years

U.S. Cl. D21—191



376,830


GOLF TEE

William W. Bess, 5731 E. Duncan St., Mesa, Ariz. 85205

Filed Nov. 7, 1995, Ser. No. 46,101

Term of patent 14 years

U.S. Cl. D21—208



376,834

PISTOL

Harold F. Resuggan, Handsworth Wood, England, assignor to

Webley & Scott Limited, Birmingham, England

Filed Jan. 12, 1995, Ser. No. 33,417

Claims priority, application United Kingdom, Aug. 11, 1994,
2040929

Term of patent 14 years

U.S. Cl. D22—104



376,829


MECHANISM FOR INVERSE EXERCISE

Sue Kuo, 9 Ground Pine Ct., Dix Hills, N.Y. 11746

Filed Nov. 2, 1995, Ser. No. 45,939

Term of patent 14 years

U.S. Cl. D21—191



376,832

BOW SUPPORT

Kenneth R. Mills, P.O. Box 54, Sarepta, La. 71071

Filed Sep. 18, 1995, Ser. No. 44,121

Term of patent 14 years

U.S. Cl. D22—107



376,834


FISH LURE

Mark H. Moore, #5 Lakeview Dr., Haines City, Fla. 32789

Filed Oct. 30, 1995, Ser. No. 45,769

Term of patent 14 years

U.S. Cl. D22—133



376,835

FISHING REEL

Shinichi Asano, Musashino; Takeo Miyazaki, and Shigeo

Mimura, both of Higashikurume, all of Japan, assignors to

Daiwa Seiko, Inc., Tokyo, Japan


Division of Ser. No. 24,974, Jun. 24, 1994, Pat. No. Des.

369,848. This application Oct. 3, 1995, Ser. No. 44,937

Claims priority, application Japan, Dec. 27, 1993, 5-39752;
May 17, 1994, 6-13953

Term of patent 14 years

U.S. Cl. D22—140



376,833

FISHING LURE

Doyle E. Hodgin, Durham, N.C., assignor to Inspiration Lures,


Inc., Apex, N.C.

Division of Ser. No. 40,192, Jun. 12, 1995, Pat. No. Des.

372,293. This application Apr. 3, 1996, Ser. No. 52,555

Term of patent 14 years

U.S. Cl. D22—128



376,836


FISH HOOK WITH DETACHABLE WEIGHT

Barry W. Banks, and James W. Riddle, both of 6857 E. Sonia Dr., Tacoma, Wash. 98404

Filed Dec. 1, 1995, Ser. No. 47,371

Term of patent 14 years

U.S. Cl. D22—144



376,838


AUTOMOBILE CLEANING WAND

Elmer Potts, and Sandra L. Potts, both of P.O. Box 125, Campti, La. 71411

Filed Dec. 1, 1995, Ser. No. 47,370

Term of patent 14 years

U.S. Cl. D23—223



376,837


SUPPORT FOR SALT FOR USE IN A WATER SOFTENER

Steven M. Peddicord, 5310 Rustle Leaf, Arlington, Tex. 76017, and Donald B. Peddicord, 200 Oak St., Lewisville, Tex. 75067

Division of Ser. No. 850,080, Mar. 12, 1992, Pat. No. Des. 363,971. This application Aug. 2, 1995, Ser. No. 42,156

Term of patent 14 years

U.S. Cl. D23—207



376,839


SPRAY GUN

Tsang-Chung Hung, Changhua Hsien, Taiwan, assignor to Ruey Ryh Enterprise Co., Ltd., Changhua Hsien, Taiwan

Filed Feb. 9, 1996, Ser. No. 50,176

Term of patent 14 years

U.S. Cl. D23—226



376,840


REFILLABLE TOILET TANK DISPENSER

Ernest L. Perkins, 1502 Kettering Way, Orange Park, Fla. 32073

Filed Dec. 22, 1995, Ser. No. 48,804

Term of patent 14 years

U.S. Cl. D23—313



376,842


HEAT RECOVERY VENTILATOR

John Franklin, London; Peter K. Grinbergs, Dorchester, and Grant W. Miles, London, all of Canada, assignors to Nutech Energy Systems Inc., Canada

Filed Apr. 12, 1995, Ser. No. 37,426

Term of patent 14 years

U.S. Cl. D23—370



376,841


TOILET SEAT

William E. Von Obenauer, 1943 NE. 6th Ct. #W-107, Fort Lauderdale, Fla. 33304

Filed Mar. 11, 1996, Ser. No. 51,431

Term of patent 14 years

U.S. Cl. D23—311



376,843

TABLE/DESK FAN

Brent J. Wortham, Wilmington, Calif., assignor to Envirotech Electric, Inc., Cerritos, Calif.

Filed Feb. 10, 1995, Ser. No. 34,721

Term of patent 14 years

U.S. Cl. D23—382



376,844


FORCED AIR VENT

Thomas Hester; Cindy Hester; Wayne Price, and Pam Price, all of Rte. 1, Box 30, Sharon, Tenn. 38255

Filed Feb. 20, 1996, Ser. No. 50,435

Term of patent 14 years

U.S. Cl. D23—393



376,846

BLADE MEDALLION FOR A CEILING FAN

Julia A. Morrow, 3305 Rogers Ave., Fort Worth, Tex. 76109, assignor to Julia A. Morrow, Fort Worth, Tex.

Filed Dec. 29, 1995, Ser. No. 48,482

Term of patent 14 years

U.S. Cl. D23—411



376,847

PHARMACEUTICAL TABLET


Martin R. Alden, and Alexander McCall, both of Dartford, England, assignors to Burroughs Wellcome Co., Research Triangle Park, N.C.

Filed Dec. 21, 1992, Ser. No. 2,757

Claims priority, application United Kingdom, Jun. 30, 1992, 2023937

Term of patent 14 years

U.S. Cl. D24—101



376,845


CEILING FAN HOUSING

Li-Su Chen, 3rd F. No. 23, Yuan Huang West Road, Fung Yung, Taichung, Taiwan

Filed Jun. 19, 1995, Ser. No. 40,472

Term of patent 14 years

U.S. Cl. D23—411



376,848

INFUSION PUMP CASSETTE

Avi Zeilig, Rosh-Ha'ain, Israel, and Jeffery Pribil, Algonquin, Ill., assignors to Sabratek Corporation, Niles, Ill.

Filed Mar. 6, 1995, Ser. No. 35,766

Term of patent 14 years

U.S. Cl. D24—111



376,850


ADHESIVE BANDAGE BACKING

Wayne K. Dunshee, and Peter W. Dunshee, both of Maplewood, Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jun. 14, 1995, Ser. No. 40,266

Term of patent 14 years

U.S. Cl. D24—189



376,849

SINGLE PIECE ORAL CAVITY CLEANING DEVICE

Nathmal S. Tarfare, 4786 Mount Vernon Blvd., Hamburg, N.Y. 14075, and Merry S. Riehm, Buffalo, N.Y., assignors to Nathmal S. Tarfare, Hamburg, N.Y.

Filed Nov. 22, 1995, Ser. No. 47,096

Term of patent 14 years

U.S. Cl. D24—152



376,851


EXPANDER DEVICE

Lawrence A. Brown, Pekin, Ind., and Karen L. Bonn, Brandenburg, Ky., assignors to Restorative Medical, Inc., Brandenburg, Ky.

Filed Dec. 29, 1995, Ser. No. 48,505

Term of patent 14 years

U.S. Cl. D24—190



376,852


HANDRAIL RIM FOR A SPA

Don T. Allen, Norman, Okla., assignor to Mapletree Investments, Norman, Okla.

Continuation-in-part of Ser. No. 8,143, May 11, 1993. This application Sep. 24, 1993, Ser. No. 13,480

Term of patent 14 years

U.S. Cl. D24—204



376,854


SHOPPING CART CORRAL

Anthony M. DiPaolo, and John T. Hood, both of 19221 Edison Ave., Chesterfield, Mo. 63005

Filed Jun. 9, 1995, Ser. No. 40,116

Term of patent 14 years

U.S. Cl. D25—18



376,853

MASSAGER

Chen-Chia Hsia, 56, Shing Kung 4th Road, Tien Chung Town, Changhua, Taiwan

Filed Dec. 11, 1995, Ser. No. 47,684

Term of patent 14 years

U.S. Cl. D24—214



376,855

EXTRUSION


Kai H. Leung, 2D Pak Sui Yuen, 17 Science Museum Road, Tsimshatsui, Kowloon, Hong Kong

Filed Dec. 1, 1994, Ser. No. 31,623

Claims priority, application New Zealand, Jun. 2, 1994, 25941

Term of patent 14 years

U.S. Cl. D25—124



376,856


DOOR JAMB

Tony DiGiorgio, Woodbridge, Canada, assignor to Dominion Plastics Inc., Woodbridge, Canada

Filed Nov. 7, 1995, Ser. No. 46,105

Term of patent 14 years

U.S. Cl. D25—124



376,858

FLUORESCENT LAMP


Takeshi Matsumura, Osaka, and Masashi Sangen, Hyogo, both of Japan, assignors to Matsushita Electronics Corporation, Osaka, Japan

Filed Aug. 24, 1995, Ser. No. 43,053

Claims priority, application Japan, Mar. 24, 1995, 7-7924

Term of patent 14 years

U.S. Cl. D26—26



376,857


CASEMENT FRAME

Tony DiGiorgio, Woodbridge, Canada, assignor to Dominion Plastics Inc., Woodbridge, Canada

Filed Dec. 22, 1995, Ser. No. 48,253

Term of patent 14 years

U.S. Cl. D25—124



376,859


FLASHLIGHT

Paul G. Garrity, Sr., Madison, Conn., assignor to Garrity Industries, Inc., Madison, Conn.

Filed Sep. 20, 1995, Ser. No. 44,206

Term of patent 14 years

U.S. Cl. D26—37



376,860


HEAD FOR A FLASHLIGHT

Paul S. Santarsiero, Avon, Conn., assignor to Black & Decker Inc., Newark, Del.

Filed Apr. 17, 1995, Ser. No. 37,603

Term of patent 14 years

U.S. Cl. D26—43



376,862


HEAD FOR A FLASHLIGHT

Richard J. Carbone, Southbury, Conn., assignor to Black & Decker Inc., Newark, Del.

Filed May 22, 1995, Ser. No. 39,169

Term of patent 14 years

U.S. Cl. D26—43



376,861


HEAD FOR A FLEXIBLE FLASHLIGHT

Scott Johnstone, Pleasant Valley, and Aaron Szymanski, Bristol, both of Conn., assignors to Black & Decker Inc., Newark, Del.

Filed Apr. 17, 1995, Ser. No. 37,616

Term of patent 14 years

U.S. Cl. D26—43



376,863

WEATHER PROOF LANTERN


Se Kit Yuen, Kowloon, Hong Kong, assignor to John Manufacturing Limited, Kowloon, Hong Kong

Filed Dec. 1, 1995, Ser. No. 47,333

Claims priority, application United Kingdom, Jul. 24, 1995, 2049027

Term of patent 14 years

U.S. Cl. D26—48



376,864

MULTI-FUNCTIONAL LANTERN


Se K. Yuen, Hong Kong, Hong Kong, assignor to John Manufacturing Limited, Kowloon, Hong Kong

Filed Feb. 16, 1996, Ser. No. 50,400

Claims priority, application United Kingdom, Dec. 1, 1995, 2052407

Term of patent 14 years

U.S. Cl. D26—50




376,866

MOTION PICTURE LIGHT COVER

Robert S. Scott, 14319 Tilden Rd., Winter Garden, Fla. 34787

Filed Apr. 26, 1995, Ser. No. 38,018

Term of patent 14 years



376,865


CLAMP-ON LAMP

Kam-Hoi Chan, Shatin, Hong Kong, assignor to Go-Gro Industries, Ltd., Kowloon Bay, Hong Kong

Filed Jan. 24, 1996, Ser. No. 49,370

Term of patent 14 years

U.S. Cl. D26—60



376,867


LAMP SHADE

San-Jhy Yan, 3F., No. 23, Yuan Huang West Rd., Fong Yuan, Taichung Hsien, Taiwan

Filed Jan. 24, 1996, Ser. No. 49,368

Term of patent 14 years

U.S. Cl. D26—127



376,868
LIGHTER


Ichikawa Makoto, Tokyo, Japan, assignor to Modern Royal Co. Ltd., Tokyo, Japan

Filed Dec. 8, 1995, Ser. No. 47,822

Claims priority, application Rep. of Korea, Aug. 10, 1995, 95-15152

Term of patent 14 years

U.S. Cl. D27—157

376,870
LIGHTER

Makoto Ichikawa, Tokyo, Japan, assignor to Modern Royal Co. Ltd., Tokyo, Japan

Filed Dec. 8, 1995, Ser. No. 50,528

Claims priority, application Rep. of Korea, Aug. 10, 1995, 95-15150

Term of patent 14 years

U.S. Cl. D27—157

376,869
LIGHTER


Makoto Ichikawa, Tokyo, Japan, assignor to Modern Royal Co. Ltd., Tokyo, Japan

Filed Dec. 8, 1995, Ser. No. 48,765

Claims priority, application Rep. of Korea, Aug. 10, 1995, 95-15151

Term of patent 14 years

U.S. Cl. D27—157

376,871
HOLDER FOR CIGARETTE LIGHTER

Michael H. Sanchez, and Rosemary A. Sanchez, both of 6103 E. Star Valley St., Mesa, Ariz. 85215

Filed Nov. 2, 1995, Ser. No. 45,921

Term of patent 14 years

U.S. Cl. D27—183

376,872
SEAT RESTRAINT

Robert W. Stroud, 9000 E. Memorial, Jones, Okla. 73049

Filed Aug. 16, 1995, Ser. No. 42,648

Term of patent 14 years

U.S. Cl. D29—101


376,874
WIRE BIRD CAGE

Ricardo C. Reyes, III, 14831 Germain st., Mission Hills, Calif. 91345

Filed Apr. 27, 1995, Ser. No. 38,069

Term of patent 14 years

U.S. Cl. D30—114

376,875
PET BED

Todd D. Glickstein, 2680 Steinburg Rd., Quakertown, Pa. 18951

Filed Sep. 1, 1994, Ser. No. 27,919

Term of patent 14 years

U.S. Cl. D30—118


376,873
HAIR SPRAY SHIELD

Marco N. Bronzini, P.O. Box 277, Zellwood, Fla. 32798

Filed Feb. 2, 1996, Ser. No. 49,868

Term of patent 14 years

U.S. Cl. D29—108



376,876

FEED BOTTLE


Ross G. McInnes, Main Road, P.O. Box 115, Waipu, New Zealand

Filed Dec. 12, 1994, Ser. No. 32,261

Claims priority, application New Zealand, Jun. 10, 1994, 25964

Term of patent 14 years

U.S. Cl. D30—121



376,878

VACUUM CLEANER UPPER PORTION

John D. Essex, North Canton, Ohio, assignor to The Hoover Company, North Canton, Ohio

Filed Apr. 12, 1995, Ser. No. 37,409

Term of patent 14 years

U.S. Cl. D32—31



376,877


BIRD FEEDER

Stewart Hardison, P.O. Box 333, Bainbridge, N.Y. 13733

Filed Sep. 5, 1995, Ser. No. 43,470

Term of patent 14 years

U.S. Cl. D30—124



376,879


HOUSING DESIGN FOR POWER NOZZLE

Steven R. Selewski, Cadillac; John J. Alberts, III, Marion; Dean R. Rohn, Cadillac; Todd C. Cote, Cadillac; Roy O. Erickson, Jr., Cadillac, all of Mich.; Roger H. Ramsey, Akron, Ohio; Robert G. Martinez, Akron, Ohio, and Dennis M. Futo, Strongsville, Ohio, assignors to Rexair, Inc., Troy, Mich.

Continuation-in-part of Ser. No. 146,656, Nov. 2, 1993, abandoned. This application Jul. 8, 1994, Ser. No. 25,696

Term of patent 14 years

U.S. Cl. D32—32



376,880


SHOE ATTACHED CLEANING IMPLEMENT

Robert F. Liebscher, 174 Cranberry Bog Rd., Danielson, Conn. 06239

Filed Oct. 25, 1995, Ser. No. 45,642

Term of patent 14 years

U.S. Cl. D32—35



376,882


TILTED DRAIN BOARD

Everett W. Cook, 11 Howard Dr., Milton, Vt. 05468

Filed Oct. 3, 1995, Ser. No. 44,897

Term of patent 14 years

U.S. Cl. D32—55



376,881

WINDSHIELD ICE SCRAPER

Arthur S. Kleinnpell, 2565 Kent Ridge Ct., Bloomfield Township, Mich. 48301, and Lori Wachler, 26524 Hendrie Blvd., Huntington Woods, Mich. 48070

Filed Jun. 12, 1995, Ser. No. 40,169

Term of patent 14 years

U.S. Cl. D32—43



376,883


CLOTHESPIN

Michael E. Olk, and Ramona T. Olk, both of P.O. Box 113, Kimball, Minn. 55353

Filed Feb. 6, 1995, Ser. No. 34,443

Term of patent 14 years

U.S. Cl. D32—61



376,884

WASTE CONTAINER LID

Donald C. Presnell, and Robert J. Tokash, both of Stephens City, Va., assignors to Rubbermaid Commercial Products Inc., Winchester, Va.

Filed Oct. 26, 1995, Ser. No. 45,670

Term of patent 14 years

U.S. Cl. D34—11



376,886

INVALID HOIST


Robert Dunn; Michael G. Gill, both of Gloucestershire; John Greaves, Hampshire; Richard I. Lees, Gloucestershire, and Bruce E. Somerton, Gloucester, all of United Kingdom, assignors to Arjo, Ltd., Gloucester, England

Filed Jun. 12, 1995, Ser. No. 40,145

Claims priority, application United Kingdom, Jan. 27, 1995, 2044806

Term of patent 14 years

U.S. Cl. D34—28



376,885

PORTABLE LIFTING UNIT

James E. Carey, 1131 E. Timberridge Dr., Prescott, Ariz. 86303, and Jesse Lacey, 25101 DeSalle, Laguna Hills, Calif. 92653

Filed Apr. 7, 1995, Ser. No. 37,235

Term of patent 14 years

U.S. Cl. D34—28



376,887


CAMERA CRANE ARM

Leonard T. Chapman, North Hollywood, Calif., assignor to Leonard Studio Equipment, Inc., North Hollywood, Calif.

Filed Oct. 4, 1994, Ser. No. 30,014

Term of patent 14 years

U.S. Cl. D34—33



376,888


YARD CRANE

Harry Mohrlang, Brush, Colo., assignor to Mohrlang Manufacturing, Inc., Brush, Colo.

Filed Apr. 1, 1996, Ser. No. 52,708

Term of patent 14 years

U.S. Cl. D34—33



376,890

MEMORIAL MARKER

Peggy Caldwell, 45 Jackson St., Wellsboro, Pa. 16901

Filed Jan. 5, 1995, Ser. No. 33,125

Term of patent 14 years

U.S. Cl. D99—17



376,889

DESIGN FOR MATERIAL HANDLING SUPPORT RACK

George F. Pilla, Alliance, Ohio, assignor to Ohio Rack, Inc., Alliance, Ohio

Filed Feb. 2, 1995, Ser. No. 34,339

Term of patent 14 years

U.S. Cl. D34—38



376,891


MAILBOX CADDY

Frederick A. Wooten, Jr., and Alice M. Ratliff-Wooten, both of Rte. 3, Box 38, Albany, Ohio 45710

Filed Jun. 16, 1995, Ser. No. 40,384

Term of patent 14 years

U.S. Cl. D99—31



376,892

MAILBOX WITH A HURRICANE LAMP

Frank Tsao, 5th Fl., No. 14, Lane 128, Yungyuan Rd., Yungho City, Taipei Hsien, Taiwan

Filed Aug. 8, 1995, Ser. No. 42,398

Term of patent 14 years

U.S. Cl. D99—31



LIST OF PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 24th DAY OF DECEMBER, 1996

NOTE—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- A-I All Weather Roofing, Inc.: *See—*
Tawzer, Charles, 5,586,414, Cl. 52:57.000.
- A.J.C.: *See—*
Charmes, Michel, 5,586,877, Cl. 431-115.000.
- A. L. Hansen Mfg. Co.: *See—*
Bullock, Charles E.; and Juga, Douglas L., 5,586,459, Cl. 70:224.000.
- AAI Corporation: *See—*
McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeafra, Larry A.; and McGrath, Thomas P., 5,586,887, Cl. 434:20.000.
- Aaltonen, Frank; and Alajaski, Timo, to CAE Investments B.V. Screen cylinder or plate having a grooved first face and a stepless second face, 5,587,077, Cl. 210:498.000.
- Aavid Laboratories, Inc.: *See—*
Phillips, Richard J.; and Larson, Ralph L., 5,587,880, Cl. 361-687.000.
- ABB Management AG: *See—*
Jaecklin, André; Ramezani, Ezatollah; Roggwiller, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.
- Wettstein, Hans, 5,586,866, Cl. 416-96.00A.
- ABB Research Ltd.: *See—*
Döbbeling, Klaus; Santner, Johannes; and Steinbach, Christian, 5,586,878, Cl. 431-351.000.
- Abbestee, Rob: *See—*
van Holst, Gerrit J.; Kreuger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, 5,587,312, Cl. 435-240.460.
- Abbeycrest Plc.: *See—*
Schmid, Peter, 5,586,452, Cl. 63-19.000.
- Abbott Laboratories: *See—*
Acosta, Phyllis J. B.; Grondalski, Richard A.; Liebrecht, Jeffrey W.; and Reynolds, Patricia A., 5,587,399, Cl. 514-561.000.
- Lawless, Michael W.; Soberon, Peter A.; Kaul, Asbok, Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., 5,586,868, Cl. 417-53.000.
- Abdelkader, Hatem: *See—*
Reitz, Paul; and Abdelkader, Hatem, 5,588,013, Cl. 372-19.000.
- Abe, Hiroomi; Nagaoka, Kenji; and Sanada, Takashi, to Sumitomo Chemical Company, Limited, Resin composition and process for producing same, 5,587,427, Cl. 525-145.000.
- Abe, Katsuo: *See—*
Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokubo; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332.000.
- Abe, Mariko; Ebata, Shuji; Abe, Takafumi; and Higuchi, Hirofumi, to Mitsubishi Gas Chemical Company, Inc. Process for preparing silica-titania catalyst, 5,587,349, Cl. 502-236.000.
- Abe, Mitsutaka: *See—*
Nakatani, Takuya; Abe, Mitsutaka; Dono, Shigeru; and Urano, Yoji, 5,586,387, Cl. 29-703.000.
- Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, to Toyota Jidosha Kabushiki Kaisha; MEC International Corporation; and Ojima, Heijiro, Method of removing metal contained in solution, 5,587,060, Cl. 204-554.000.
- Abe, Tadafumi: *See—*
Katsuta, Kazuo; and Abe, Tadafumi, 5,586,377, Cl. 29-91.500.
- Abe, Takafumi; Nishikawa, Mitsuhiro; and Naitoh, Susumu, to Mitsubishi Gas Chemical Company, Inc. Process for purifying methacrylate, 5,587,453, Cl. 528-488.000.
- Abe, Takafumi: *See—*
Abe, Mariko; Ebata, Shuji; Abe, Takafumi; and Higuchi, Hirofumi, 5,587,349, Cl. 502-236.000.
- Abela, George S. Cell transfection apparatus and method, 5,586,982, Cl. 606-28.000.
- Abo, Keiju, to Nissan Motor Co., Ltd. System for controlling a continuously variable transmission in response to a sensed wheel deceleration, 5,586,953, Cl. 477-47.000.
- Abrams, Steven R.; Koren, James U.; Srinivasan, Vijay; and Tarahanis, Konstantinos, to Statasys, Inc. Method employing sequential two-dimensional geometry for producing shells for fabrication by a rapid prototyping system, 5,587,913, Cl. 364-468.260.
- Abramson, Jeffrey M.; Akkary, Haitham; Grew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., to Intel Corporation. Methods and apparatus for forwarding buffered store data on an out-of-order execution computer system, 5,588,126, Cl. 395-376.000.
- Abrams, Rolin L. Nestable and stackable storage unit, 5,586,656, Cl. 206-501.000.
- Abushanab, Elie: *See—*
Panzea, Raymond P.; El Subbagh, Hussein I.; and Abushanab, Elie, 5,587,494, Cl. 549-512.000.
- Accessline Technologies, Inc.: *See—*
Fuller, Robert M.; Epler, Frederick A.; and Manowski, Maxwell E., 5,588,037, Cl. 379-57.000.
- Acer Incorporated: *See—*
Tsai, Philip; Hung, Chun-Yen; and Wu, Fen-Shiung, 5,587,878, Cl. 361-683.000.
- Acevedo, Oscar L.: *See—*
Cook, P. Dan; Acevedo, Oscar L.; and Andrews, Robert S., 5,587,470, Cl. 536-23.100.
- Cook, Phillip D.; Ecker, David J.; Acevedo, Oscar L.; and Davis, Peter, 5,587,471, Cl. 536-25.300.
- Acosta, Phyllis J. B.; Grondalski, Richard A.; Liebrecht, Jeffrey W.; and Reynolds, Patricia A., to Abbott Laboratories. Method for preparing medical foods for the nutritional support of infants/toddlers with metabolic diseases, 5,587,399, Cl. 514-561.000.
- ACT Distribution, Inc.: *See—*
Lund, William J., 5,586,572, Cl. 137-337.000.
- Actel Corporation: *See—*
Kowshik, Vikram, 5,587,603, Cl. 257-316.000.
- Adachi, Fumaki; Amano, Tadashi; Shiota, Yoshihiro; and Okuno, Yoshitaka, to Shin-Etsu Chemical Co., Ltd. Process of producing vinyl chloride type polymer, 5,587,437, Cl. 526-68.000.
- Adachi, Hiroshi: *See—*
Tanaka, Chiaki; Sasaki, Masaomi; Aruga, Tamotsu; Shimada, Tomoyuki; and Adachi, Hiroshi, 5,587,516, Cl. 564-405.000.
- Adachi, Nobukazu: *See—*
Kimura, Shoji; and Adachi, Nobukazu, 5,586,758, Cl. 271-303.000.
- Adachi, Shuhei; and Inami, Junichi, to Yamaba Hatsudoki Kabushiki Kaisha. Valve seat insert, 5,586,530, Cl. 123-188.800.
- Adam, Paul; Tillmann, Heinz, deceased (by Zita M. Tillmann, executor); Werner, Michael; Renn, Peter; Reif, Joachim; and Dölling, Uwe, to TEMIC Bayern-Chemie Airbag GmbH. Hybrid gas generator for filling a gas bag, 5,586,783, Cl. 280-737.000.
- Adamkoski, Paul L.: *See—*
Knorowski, Victor J.; Reluzco, George; Robertson, Kenneth J.; and Adamkoski, Paul L., 5,586,864, Cl. 415-209.200.
- Adams, William J., to Silicon Systems, Inc. Multiplier based transconductance amplifiers and transconductance control circuits, 5,587,687, Cl. 330-253.000.
- Adaptec, Inc.: *See—*
Suri, Salil; and Teymour, Sassan, 5,587,686, Cl. 327-552.000.
- ADC Telecommunications, Inc.: *See—*
Emmons, David J.; and Lu, Liang-Ju, 5,588,087, Cl. 385-140.000.
- ADI, Limited: *See—*
Landine, Robert; De Garie, Claude; and Cocci, Albert, 5,587,080, Cl. 210-603.000.
- Adkins, Jeffrey A.: *See—*
Adkins, Joseph E.; and Adkins, Jeffrey A., 5,586,959, Cl. 482-96.000.
- Adkins, Joseph E.; and Adkins, Jeffrey A. Exercise machine, 5,586,959, Cl. 482-96.000.
- Advanced Micro Devices: *See—*
Xie, Zheng-yi, 5,588,053, Cl. 379-386.000.
- Advanced Micro Devices, Inc.: *See—*
Agrawal, Om P.; Wright, Michael J.; and Shen, Ju, 5,587,921, Cl. 364-489.000.
- Lin, Jonathan; Peng, Jack Z.; Barsan, Radu; and Mehta, Sunil, 5,587,945, Cl. 365-185.100.
- Advanced Microbotics Corporation: *See—*
Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P., 5,587,273, Cl. 430-269.000.
- AEG Schienenfahrzeuge GmbH: *See—*
Heubusch, Harald; and Rösler, Jörg, 5,586,506, Cl. 105-3.000.
- Alga-Gevaert N.V.: *See—*
Deheuw, Geert, 5,587,269, Cl. 430-203.000.
- Atione, Sandra: *See—*
Carter, Barrie J.; Flotte, Terence; Atione, Sandra; and Solow, Rikki, 5,587,308, Cl. 435-240.200.
- Agematsu, Masaya: *See—*
Sato, Toshikuni; and Agematsu, Masaya, 5,587,854, Cl. 360-97.010.
- Agency Of Industrial Science And Technology, Ministry Of International Trade And Industry: *See—*
Shibasaki, Yasuo; Oda, Kiichi; and Fukuda, Takeshi, 5,587,010, Cl. 106-287.170.
- Agfa-Gevaert N.V.: *See—*

- Defieuw, Geert; Janssens, Wilhelmus; and Vanmaele, Luc, 5,587,268, Cl. 430:200.000.
- Heugebaert, Franciscus; and Van Hunsel, Johan, 5,587,271, Cl. 430:204.000.
- Horsten, Bartholomeus C.; Uytendaele, Carlo A.; Jansen, Guy D. A.; and Schuerweggen, Ronald, 5,587,350, Cl. 503:201.000.
- Janssens, Wilhelmus; Van den Bogaert, Jan; Vanmaele, Luc; and Defieuw, Geert, 5,587,270, Cl. 430:203.000.
- Agrawal, Om P.; Wright, Michael J.; and Shen, Ju, to Advanced Micro Devices, Inc. Array of configurable logic blocks each including a look up table having inputs coupled to a first multiplexer and having outputs coupled to a second multiplexer, 5,587,921, Cl. 364:489.000.
- Agrawal, Raj K.; Lynam, Niall R.; and Galer, James K., to Donnelly Corporation. Interior rear view mirror mounting system utilizing one-package structural adhesive, 5,587,236, Cl. 428:334.000.
- Agrusa, Mauro; See—
- Iardella, Carlo A.; and Agrusa, Mauro, 5,587,718, Cl. 342:443.000.
- Ahlgren, Frederic F.; See—
- Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313:634.000.
- Ahlstrom Consumer Products Ltd.; See—
- Torvio, Ilkka; Toivio, Terttu; and Olkkonen, Kari, 5,586,348, Cl. 5:710.000.
- Ahlstrom Machinery Corporation; See—
- LeBlanc, Peter, 5,587,078, Cl. 210:512.100.
- Aho, Wilho V., Jr.; Jones, Stephen R.; Chetta, Gregory E.; and Strout, Terry H., to United Technologies Corporation. Multi-attitude deaerator for oil tank, 5,587,068, Cl. 210:188.000.
- Ahrné, Siv; See—
- Bengmark, Stig; Ahrné, Siv; Molin, Göran; and Jeppson, Bengt, 5,587,314, Cl. 435:252.900.
- Aidlin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier, Kenneth; Ledwith, Robert; and Hencke, Robert J. Variable angle conveyor assembly with stepped cleat, 5,586,637, Cl. 198:397.000.
- Aidlin, Stephen H.; See—
- Aidlin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier, Kenneth; Ledwith, Robert; and Hencke, Robert J., 5,586,637, Cl. 198:397.000.
- Aikawa Iron Works Co., Ltd.; See—
- Aikawa, Yoshihiko, 5,586,662, Cl. 209:411.000.
- Aikawa, Yoshihiko, to Aikawa Iron Works Co., Ltd. Basket for a paper-making screen and method for producing same, 5,586,662, Cl. 209:411.000.
- Airlux AG; See—
- Frischknecht, Willi, 5,586,347, Cl. 5:713.000.
- Aisin AW Co., Ltd.; See—
- Asano, Hirosi; Ishikawa, Wataru; and Nimura, Mitsuhiro, 5,587,911, Cl. 364:444.200.
- Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masahiro; and Yamamoto, Yoshihisa, 5,586,954, Cl. 477:93.000.
- Aisin Seiki Kabushiki Kaisha; See—
- Iguchi, Yutaka; Sato, Kazuo; Kobayashi, Toshihiro; and Sato, Masayuki, 5,587,529, Cl. 73:504.130.
- Takeuchi, Kiyoshi; Takeda, Shin; and Nakamura, Masao, 5,586,462, Cl. 72:150.000.
- Aizawa, Yuichi, to Daiwa Seiko, Inc. Hollow club head with sole plate support structure, 5,586,949, Cl. 473:345.000.
- Akadiri, Adebola T.; See—
- Warren, Raphael; and Akadiri, Adebola T., 5,587,176, Cl. 424:443.000.
- Akahoshi, Toshiaki; See—
- Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kanji, 5,587,132, Cl. 423:62.000.
- Akashi, Shunji; See—
- Matsuda, Yoshio; Akashi, Shunji; and Yoshida, Hiroshi, 5,586,369, Cl. 24:392.000.
- Akatsuka, Masanori; See—
- Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356:367.000.
- Akaza, Syunsuke; See—
- Sato, Shinichi; Akaza, Syunsuke, and Yoshino, Hiroyuki, 5,588,096, Cl. 395:135.000.
- Akazawa, Taro; See—
- Takizawa, Toshiaki; Horikawa, Yasuo; and Akazawa, Taro, 5,587,420, Cl. 524:572.000.
- Akers, Denver; See—
- Horde, Boice F.; and Akers, Denver, 5,586,464, Cl. 72:405.160.
- Akiba, Yoshiyuki; See—
- Nakai, Toshiaki; Amano, Mitsuoyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki; and Sato, Masahiro, 5,587,547, Cl. 84:645.000.
- Akita Electronics Co., Ltd.; See—
- Masayuki, Watanabe; Toshio, Sugano; Senchiro, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima, 5,587,341, Cl. 437:206.000.
- Akiyoshi, Kazunori; and Niwano, Masahiro, to Sunimoto Chemical Company, Limited. Process for producing aromatic polyamide film, 5,587,450, Cl. 528:310.000.
- Akkary, Haitham; See—
- Abramsen, Jeffrey M.; Akkary, Haitham; Glew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395:376.000.
- Aktiebolaget Electrolux; See—
- Dellby, Fredrik; and Fonsel, Per Åke, 5,586,680, Cl. 220:467.000.
- Akutsu, Kensuke, to Nippon Paint Co., Ltd. High voltage sphere-gap discharge switch, high voltage pulse generation circuit and high voltage discharge switching method, 5,587,868, Cl. 361:231.000.
- Akzo Nobel N.V.; See—
- Boonstra, Tjerk O.; and Wiersum, Ulfert E., 5,588,083, Cl. 385:122.000.
- Alajaaski, Timo; See—
- Aaltonen, Frank; and Alajaaski, Timo, 5,587,077, Cl. 210:498.000.
- Ålander, Casper; and Mononen, Tarmo, to Rautaruukki Oy. Composite construction of reinforced concrete, 5,586,418, Cl. 52:450.000.
- Albemarle Corporation; See—
- Lin, Ronny W.; Atkinson, Eldon E., Jr.; and Balhoff, Donald E., 5,587,512, Cl. 562:565.000.
- Albert, Donn E.; See—
- England, Robert L.; and Albert, Donn E., 5,586,617, Cl. 182:238.000.
- Albom, William E., Jr.; Hoskins, JoAnn; Skatrud, Paul L.; and Ñal, Serhat, to Eli Lilly and Company. FemA gene of *staphylococcus epidermidis*, femA protein, and vectors and microorganisms comprising the femA gene, 5,587,307, Cl. 435:240.100.
- Alcatel Canada Wire Inc.; See—
- Simmons, Frederick H. G., 5,587,537, Cl. 73:862.392.
- Alcinii, Raymond R.; and Ritola, Dan E. Press brake controller positioning system, 5,586,465, Cl. 72:441.000.
- Alexander, Dennis R.; See—
- Curcuta, Victor; Alexander, Dennis R.; Deangelis, Robert J.; and Robertson, Brian W., 5,586,714, Cl. 228:122.100.
- Alexander, Edward M.; and Spezio, Anthony E., to United States of America, Navy. Method and apparatus for signal filtering, 5,587,829, Cl. 359:287.000.
- Alexander, James C., to United Dominion Industries, Inc. Automatic return to dock mechanism for mechanical dock leveler, 5,586,356, Cl. 14:71.100.
- Alexander, James C.; See—
- Metz, Donald; and Alexander, James C., 5,586,355, Cl. 14:69.500.
- Alexander, Tommy; and Jenkins, Shawn B., to Alexander, Tommy. Shoulder holster and method of carrying a portable telephone near the body of a user, 5,586,704, Cl. 224:605.000.
- Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Chanakshu, Sandeep; Koipillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., to General Electric Company. Protocol and mechanism for primary and matter mode communication for asset tracking, 5,588,005, Cl. 370:346.000.
- Alkon, Daniel L.; Vogl, Thomas P.; Blackwell, Kim T.; and Barbour, Garth S., to Environmental Research Institute of Michigan. Dynamically stable associative learning neural network system, 5,588,091, Cl. 395:24.000.
- Allen-Bradley Company, Inc.; See—
- Wieloch, Christopher J.; Kappel, Mark A.; Annis, Jeffrey R.; Benard, David J.; Boehmer, Ellen; and Hildebrandt, Gernot, 5,587,861, Cl. 361:14.000.
- Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert; and Froen, Diane, to Monsanto Company. The Preparation of (S)-decahydroquinoline-3-carboxylic acid-1-butylamide, 5,587,481, Cl. 546:146.000.
- Allen, Gary R.; See—
- Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313:634.000.
- Allen, Jerry L., to Vikimatic Sales, Inc. Method of manufacturing a conduit assembly with a floating divider, 5,587,115, Cl. 264:1.240.
- Allen, Loyd V., Jr.; and Wang, Bingnan, to University of Oklahoma, The Board of Regents of the. Process for making a particulate support matrix for making a rapidly dissolving tablet, 5,587,180, Cl. 424:499.000.
- Allen, Patrick; and Gold, Larry, to University Research Corporation. High affinity nucleic acid ligands to HIV integrase, 5,587,468, Cl. 536:22.100.
- Allen, Peter B., to Lockheed Martin Corporation. Tapered plug foam spray apparatus, 5,586,724, Cl. 239:112.000.
- Allergan; See—
- Burk, Robert M., 5,587,391, Cl. 514:357.000.
- Burke, James A.; Garst, Michael E.; and Wheeler, Larry A., 5,587,376, Cl. 514:249.000.
- AlliedSignal Europe Services Techniques; See—
- Mery, Jean-Claude, 5,586,623, Cl. 188:72.600.
- AlliedSignal Inc.; See—
- Foot, Steven A.; and Stoddard, Damon R., 5,587,530, Cl. 73:514.230.
- Leung, Roger Y., 5,587,345, Cl. 501:32.000.
- Lin, Leroy C.; Wilson, Laura G.; Bhatnagar, Ashok; and Li, Hsin L., 5,587,230, Cl. 428:245.000.
- Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., 5,586,782, Cl. 280:730.200.
- Almén, Torsten; Berg, Arne; Dugstad, Harald; Klaveness, Jo; Krautwurst, Klaus D.; and Rongved, Pål, to Nycomed Imaging AS. Dazine chelating agents for diagnostic imaging, 5,587,144, Cl. 424:9.361.
- Alpegiani, Marco; Bissolino, Pierluigi; and Perrone, Ettore, to Farnitalia Carlo Erba S.r.l. 2-acyloxycephem derivatives, 5,587,373, Cl. 514:202.000.

- Altekrüger, Burkhard; Aufreiter, Joachim; Brüss, Dieter; and Kalkowski, Klaus, to Leybold Aktiengesellschaft. Controlled feeding Czochralski apparatus, 5,587,016, Cl. 117:214.000.
- Altschuler, Barry N.; Hardy, Douglas A.; Stephens, James A.; and Kish, Joseph, III, to Motorola, Inc. Secure communication setup method, 5,588,062, Cl. 380:30.000.
- Alumase Limited; See—
- Gotch, Henry E.; and Hyde, Roger J., 5,586,691, Cl. 222:113.000.
- Amalgamated Software of North America, Inc.; See—
- Ferguson, David E., 5,587,940, Cl. 364:762.000.
- Amamo, Mitsuoyoshi; See—
- Nakai, Toshiaki; Amamo, Mitsuoyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki; and Sato, Masahiro, 5,587,547, Cl. 84:645.000.
- Amamo, Tadashi; See—
- Adachi, Fumaki; Amamo, Tadashi; Shirota, Yoshihiro; and Okuno, Yoshitaka, 5,587,437, Cl. 526:68.000.
- Amatucci, Glenn G.; and Tarascon, Jean-Marie, to Bell Communications Research, Inc. Delithiated cobalt oxide and nickel oxide phases and method of preparing same, 5,587,133, Cl. 423:138.000.
- Amaya, Mikio; See—
- Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhiro; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355:219.000.
- Amec Engineering Co.; See—
- Ryan, Thomas P.; and Stelzer, Glen A., 5,587,877, Cl. 361:683.000.
- Amidat Corporation; See—
- Oneto, John C.; and Russell, Stephen P., 5,588,134, Cl. 395:485.000.
- American Institute of Taxidermy, Inc.; See—
- Rinehart, John R., 5,586,805, Cl. 297:188.090.
- American Sigma, Inc.; See—
- Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary, Sak, Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364:510.000.
- Americorp Inc.; See—
- Liu, Simon Y., 5,586,488, Cl. 99:331.000.
- Ammermann, Eberhard; See—
- Wingen, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schellberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514:63.000.
- Amphenol Corporation; See—
- Del Negro, James; Brown, Russell, and Avery, Roger, 5,586,910, Cl. 439:584.000.
- Amphenol-Telcel Electronics GmbH; See—
- Braun, Gerhard, 5,586,890, Cl. 439:66.000.
- Analog Devices, Inc.; See—
- Bowers, Derek E., 5,587,689, Cl. 330:254.000.
- Analogic Corporation; See—
- Botka, Alexander E.; Tuval, Ben; and Marcovici, Sorin, 5,587,611, Cl. 257:458.000.
- Anderson, Charles D.; See—
- Lennon, George E.; Martin, James R.; and Anderson, Charles D., 5,586,963, Cl. 493:299.000.
- Anderson, Colin J. Variable ride height vehicle suspension system, 5,586,781, Cl. 280:708.000.
- Anderson, Dennis R.; and Anderson, Katherine D. Self locking male and female connectors for electrical cords, 5,586,898, Cl. 439:287.000.
- Anderson, Katherine D.; See—
- Anderson, Dennis R.; and Anderson, Katherine D., 5,586,898, Cl. 439:287.000.
- Anderson, Peter L.; Cowell, Michael J.; and Hoteik, Dan J., to Societe Civile des Brevets Henri Vidal. Dual purpose modular block for construction of retaining walls, 5,586,841, Cl. 405:286.000.
- Anderson, Wayne A.; Jia, Quanxi; Yi, Junsin; and Chang, Lin-Huang, to Research Foundation of State University of New York. Nanocrystalline layer thin film capacitors, 5,587,870, Cl. 361:313.000.
- Andersson, Mats; and Törnquist, Anders, to Nobelpharma AB. Computer aided processing of three-dimensional object and apparatus therefor, 5,587,912, Cl. 364:468.040.
- Ando, Ryo; See—
- Mori, Hirotsugu; and Ando, Ryo, 5,587,771, Cl. 355:208.000.
- Ando, Shigeru; See—
- Nagao, Kenji; Sohma, Masaki; Ando, Shigeru; and Kobayakawa, Michihiro, 5,587,927, Cl. 364:514.00A.
- Andou, Yukinori; See—
- Miyaji, Takashi; Nishikawa, Yoshiyazu; Andou, Yukinori; Yamanaka, Toshio; and Kadowaki, Hideaki, 5,587,777, Cl. 355:245.000.
- Andrews, Robert S.; See—
- Cook, P. Dan; Acevedo, Oscar L.; and Andrews, Robert S., 5,587,470, Cl. 536:23.100.
- Andrianov, Lev A.; Dimitri B. Gudkov, executors, Ekaterina L. Andrianova, executrix; See—
- Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P., deceased, 5,587,295, Cl. 435:11.000.
- Andrianova, Irina P., deceased (by Lev A. Andrianov, Dimitri B. Gudkov, executors, Ekaterina L. Andrianova, executrix); See—
- Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P., deceased, 5,587,295, Cl. 435:11.000.
- Andrievsky, Andrei; See—
- Sessler, Jonathan L.; Král, Vladimir; and Andrievsky, Andrei, 5,587,478, Cl. 540:474.000.
- Angelone, Philip P., Jr.; Karassik, Nancy M.; and Grace, William R., to Gillette Company, The. Clear, gelled aluminum and zirconium salt containing antiperspirant formulation, 5,587,153, Cl. 424:66.000.
- Angermann, Dirk; See—
- Vossman, Gregor; and Angermann, Dirk, 5,586,833, Cl. 403:359.000.
- Annis, Jeffrey R.; See—
- Wieloch, Christopher J.; Kappel, Mark A.; Annis, Jeffrey R.; Benard, David J.; Boehmer, Ellen; and Hildebrandt, Gernot, 5,587,861, Cl. 361:14.000.
- Ansanay, Virginie; See—
- Barre, Pierre; Dequin, Sylvie; and Ansanay, Virginie, 5,587,304, Cl. 435:139.000.
- Anser Tool & Machinery Technologies, Inc.; See—
- Diederiks, Everett G., Jr.; and Puett, Edwin E., Jr., 5,586,360, Cl. 15:410.000.
- Antes, Todd D.; See—
- Oldfield, William W.; Brinkcetter, Thomas R.; and Antes, Todd D., 5,587,934, Cl. 364:571.010.
- Antonuccio, Robert S.; See—
- Spano, Joseph M.; Antonuccio, Robert S.; and Carney, James M., 5,587,879, Cl. 361:665.000.
- Ao, Kenichi; See—
- Kano, Kazuhiko; Takeuchi, Yukihiko; Watanabe, Takamoto; Ao, Kenichi; Kanoue, Masakazu; and Uenoyama, Hirofumi, 5,587,343, Cl. 437:228.000.
- Aoki, Hideji; Tashima, Takahiro; Nakashima, Suekazu; Osako, Yoshiyuki; and Yamasaki, Hidetaka, to Mitsubishi Denki Kabushiki Kaisha, and Mitsubishi Electric Engineering Co., Ltd. Press control method and press apparatus, 5,587,633, Cl. 318:164.000.
- Aoki, Katuyuki; See—
- Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Kozumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454:320.000.
- Aoki, Yoshio; See—
- Watanabe, Tetsu; and Aoki, Yoshio, 5,587,990, Cl. 369:275.200.
- Aoshima, Sadahiro; See—
- Frechet, Jean M. J.; and Aoshima, Sadahiro, 5,587,441, Cl. 526:238.000.
- Frechet, Jean M. J.; and Aoshima, Sadahiro, 5,587,446, Cl. 526:333.000.
- Aoyagi, Yoshihiko, to Fujitsu Limited. Document editor having function for controlling display processing of details, 5,588,103, Cl. 395:326.000.
- Aoyama, Takashi, to Sony Corporation. Disc loading mechanism including a damper mounted in a base plate recess, 5,587,856, Cl. 360:99.020.
- Apparate-Und Werkzeugbau AG; See—
- Krummenacher, Josef, 5,586,651, Cl. 206:310.000.
- Apple Computer, Inc.; See—
- Chen, Michael; Houde, Stephanie L.; and Seidl, Robert H., 5,588,098, Cl. 395:137.000.
- Foster, Gregg S.; and Capps, Stephen P., 5,588,105, Cl. 395:326.000.
- O'Brien, John; and Iye, Jonathan, 5,587,876, Cl. 361:682.000.
- Price, Noah M.; Takahashi, Duane M. P.; and Buick, David C., 5,587,887, Cl. 361:794.000.
- Smith, Walter R.; and Capps, Stephen P., 5,588,141, Cl. 395:500.000.
- Williams, Lance J.; and Kass, Michael, 5,587,711, Cl. 341:144.000.
- Applewhite, John; See—
- Johnson, Lonnie G.; and Applewhite, John, 5,586,688, Cl. 222:61.000.
- Applied Research Associates, Inc.; See—
- Bratton, Wes, 5,587,538, Cl. 73:863.330.
- ARA Electronics Corp.; See—
- Desai, Dhimat R.; Tayse, Louis C.; and Gideon, Richard W., 5,587,634, Cl. 318:257.000.
- Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayo; Iwaoaka, Kazuhiro; and Yamashita, Takayuki, to Fuji Xerox Co., Ltd. Image forming apparatus having image signal discrimination device, 5,587,772, Cl. 355:208.000.
- Arai, Tatsuo; and Saito, Takayoshi, to Mitsubishi Materials Corporation. Face milling cutting insert having convex rakes with obtusely intersecting flat surfaces, 5,586,845, Cl. 407:113.000.
- Arai, Yoshihisa; See—
- Mizukami, Masamichi; Yui, Tomoyuki; Arai, Yoshihisa; and Gocho, Yoshihiro, 5,587,106, Cl. 252:299.610.
- Araki, Dai; See—
- Hamada, Susumu, deceased, and Araki, Dai, 5,587,918, Cl. 364:488.000.
- Araki, Tohru, to Mitsubishi Denki Kabushiki Kaisha. Sensor characteristic adjustment circuit for adjusting output characteristics of a semiconductor sensor, 5,587,653, Cl. 324:132.000.
- Araki, Yoshitaka; See—
- Konoike, Toshiro; Araki, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Ken-ji; and Tozoy, Takehiko, 5,587,505, Cl. 558:272.000.
- Araneo, Barbara A.; See—
- Daynes, Raymond A.; and Araneo, Barbara A., 5,587,369, Cl. 514:178.000.
- Arata, Masami; See—
- Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, 5,587,406, Cl. 523:116.000.
- Araya, Junji; See—
- Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiko; Kugo, Harumi; Sakai, Kazuhiro; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355:210.000.
- Arch Development Corporation; See—

- Horwitz, Earl P., and Chianzia, Renato, 5,587,142, Cl. 423-658,500.
 Archer, Shreve M., III, to Entropy Racing, Inc. Back guard with tunnel for spinal column, 5,586,561, Cl. 128-846,000.
 Arenäs, Anders, *See*—
 Bergström, Jan O., Liljegren, Lars, Skarhed, Ove, and Arenäs, Anders, 5,587,863, Cl. 361-93,000.
 Aretz, Werner, *See*—
 Then, Johann; Aretz, Werner; and Sauber, Klaus, 5,587,319, Cl. 435-280,000.
 Arikawa, Kazuhiko, *See*—
 Nagaura, Toshiyuki; Yamashita, Zenjiro; Arikawa, Kazuhiko, and Ohta, Kenji, 5,587,994, Cl. 369-291,000.
 Arita, Kiyoshi, and Takahashi, Kouchi, to Matsushita Electric Industrial Co., Ltd. Method for wire bonding, 5,586,713, Cl. 228-102,000.
 Arita, Soichi, *See*—
 Kato, Tetsuaki; Arita, Soichi, and Nakamura, Masaru, 5,587,638, Cl. 318-568,140.
 Antonino, Kouichi, *See*—
 Ikegawa, Akihito; Antonino, Kouichi, Tsukamoto, Kazuki, and Yamashita, Michiya, 5,587,551, Cl. 118-661,000.
 Arizona Board of Regents, *See*—
 Bao, Qingcheng, Sorensen, Ian, and Glaunsinger, William, 5,587,130, Cl. 422-88,000.
 Arizona Chemical Company, *See*—
 Curvin, Daniel R., 5,587,007, Cl. 106-23,000.
 Aron, Jerome, to Kuhn S.A. Haymaking machine, 5,586,421, Cl. 56-367,000.
 Atomec Pharmaceuticals, Inc., *See*—
 King, C. Richter, Kasprzyk, Philip G., and Bird, Robert E., 5,587,458, Cl. 530-387,300.
 Arreguit, Xavier, *See*—
 Venier, Philippe; Debergh, Patrick, and Arreguit, Xavier, 5,587,580, Cl. 250-206,100.
 Arte Corporation, *See*—
 Tanaka, Nobuo; Otani, Seiji; Kawakita, Hiroyuki, and Matsuda, Teruo, 5,586,975, Cl. 604-89,000.
 Arthurs, Scott A., *See*—
 Weinmann, Lee S., and Arthurs, Scott A., 5,586,458, Cl. 70-208,000.
 Aruga, Tamotsu, *See*—
 Tanaka, Chiaki; Sasaki, Masao; Aruga, Tamotsu; Shimada, Tomoyuki, and Adachi, Hiroshi, 5,587,516, Cl. 564-405,000.
 Asahi Glass Company Ltd., *See*—
 Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Junjima, Tomoki; Ooi, Yoshitaka; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62,000.
 Asahi Kasei Kogyo Kabushiki Kaisha, *See*—
 Sakigara, Masayuki, and Kubo, Isao, 5,587,358, Cl. 514-11,000.
 Asahi Kogyo Kogyo Kabushiki Kaisha, *See*—
 Iizuka, Takashi, 5,587,825, Cl. 359-204,000.
 Ito, Takayuki, 5,587,841, Cl. 359-680,000.
 Kanazawa, Hiroshi; Okuda, Isao; Shimozaki, Shimppei; and Takishima, Suguru, 5,587,973, Cl. 369-13,000.
 Asai, Isao, and Hasegawa, Toshinori, to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho. Roving bobbin changing method and apparatus for spinning machine, 5,586,428, Cl. 57-269,000.
 Asaka, Tatsuya, *See*—
 Mori, Katsumi; Asaka, Tatsuya; Iwano, Hidenori, and Kondo, Takayuki, 5,587,335, Cl. 437-129,000.
 Asakura, Mikio, *See*—
 Fujishima, Kazuyasu; Matsuda, Yoshio, and Asakura, Mikio, 5,588,130, Cl. 395-445,000.
 Asami, Goro, *See*—
 Eguchi, Tomoo; and Asami, Goro, 5,586,372, Cl. 24-452,000.
 Asami, Shinya, *See*—
 Konde, Norikazu; Yamazaki, Shiro; Umezaki, Junichi, and Asami, Shinya, 5,587,593, Cl. 257-94,000.
 Asano, Hitoshi; Ishikawa, Wataru, and Nimura, Mitsuhiro, to Arin AW Co., Ltd. Navigation system with selective intersection display, 5,587,911, Cl. 364-444,200.
 Asaoka, Junichi, *See*—
 Kojima, Yuri; Mototani, Yuji, and Asaoka, Junichi, 5,587,254, Cl. 429-206,000.
 Asaoka, Masanobu, *See*—
 Togano, Takeshi; Takao, Hideaki; Asaoka, Masanobu, and Kojima, Makoto, 5,587,211, Cl. 428-1,000.
 Asea Brown Boveri AB, *See*—
 Bergström, Jan O., Liljegren, Lars, Skarhed, Ove, and Arenäs, Anders, 5,587,863, Cl. 361-93,000.
 Ashcraft, Walter M., and Wales, Matthew A., to Atwood Industries, Inc. Fold-away gas appliance, 5,586,546, Cl. 126-42,000.
 Ashikawa, Teruo, *See*—
 Katagiri, Shingo, and Ashikawa, Teruo, 5,586,654, Cl. 206-387,100.
 Ashley Furniture, Industries, Inc., *See*—
 Wanek, Ronald G.; Dotta, James C.; Konkel, Brian, and Herold, Duane, 5,586,830, Cl. 403-59,000.
 Asprey, Robert R., to Cybox Computer Products Corporation. Open collector communications link, 5,587,824, Cl. 359-154,000.
 Assay Research, Inc., *See*—
 Tamarkin, Lawrence; and Paciotti, Giulio F., 5,587,294, Cl. 435-7,930.
 AST Research, Inc., *See*—
 Bennett, Brian R., 5,588,125, Cl. 395-306,000.
 Aston, Graeme, to Electric Propulsion Laboratory, Inc. Safe potential arc channel enhanced arc head, 5,587,093, Cl. 219-121,480.
 Asyst Technologies, Inc., *See*—
 Bonora, Anthony C., and Oen, Joshua T., 5,586,585, Cl. 141-93,000.
 Aszodi, Jozsef; Chantot, Jean-François; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, to Roussel Uclaf Cephalosporins, 5,587,372, Cl. 514-202,000.
 AT&T, *See*—
 Velardo, Patrick M., Jr.; and Wynn, Woodson D., 5,587,998, Cl. 370-289,000.
 AT&T Global Information Solutions Company, *See*—
 Crooks, John E., and Protheroe, Robert L., 5,587,560, Cl. 178-18,000.
 Schmitt, Kenneth C., 5,587,675, Cl. 327-99,000.
 Athey, Phillip S., and Kiefer, Garry E., to Dow Chemical Company, The. Process for preparing polyazamacrocycles, 5,587,451, Cl. 528-345,000.
 Atkinson, Eldon E., Jr., *See*—
 Lin, Ronny W.; Atkinson, Eldon E., Jr., and Balhoff, Donald E., 5,587,512, Cl. 562-565,000.
 Atmel Corporation, *See*—
 Jazayeri, Mehdi; Hui, Edward S., and Korsh, George J., 5,587,951, Cl. 365-203,000.
 Atoma International Of America, Inc., *See*—
 Taggart, Russell C., 5,586,807, Cl. 297-218,500.
 Atwood Industries, Inc., *See*—
 Ashcraft, Walter M., and Wales, Matthew A., 5,586,546, Cl. 126-42,000.
 Audebert, Serge, and Audibert, Francis, to Sollac. Process for the preparation of a cooling agent containing iron for a steel-making converter, 5,587,002, Cl. 75-770,000.
 Audett, Jay D., and McElrath, Kenneth O., to Exxon Chemical Patents Inc. UV/EB curable butyl copolymers for lithographic and corrosion-resistant coating, 5,587,261, Cl. 430-18,000.
 Audibert, Francis, *See*—
 Audebert, Serge; and Audibert, Francis, 5,587,002, Cl. 75-770,000.
 Aufreiter, Joachim, *See*—
 Altekrieger, Burkhard; Aufreiter, Joachim; Brüss, Dieter, and Kalkowski, Klaus, 5,587,016, Cl. 117-214,000.
 Augarten, Michael H., to Teradyne, Inc. Redundancy analyzer for automatic memory tester, 5,588,115, Cl. 395-183,050.
 Ausimont S.p.A., *See*—
 Marzolini, Fausto; Calmanti, Giulio, and Sacchi, Gianpiero, 5,587,049, Cl. 162-40,000.
 Austrian Energy & Environment, SGP/Wagner-Biro GmbH, *See*—
 Bobik, Michael; Lindbauer, Ralf L., and Glasner, Alfred, 5,587,138, Cl. 423-242,100.
 Autio, Jukka, and Kujala, Timo, to Valmet Corporation. Apparatus and method for tensioning a fabric in a paper machine, 5,587,052, Cl. 162-273,000.
 Automated Packaging Systems, Inc., *See*—
 Lerner, Bernard; Hess, Richard W.; Cronauer, William M.; Wehrmann, Rick S.; and Kramer, James D., 5,586,708, Cl. 226-172,000.
 Auty, Ronald E., and Gerbasi, Dennis G., to Xerox Corporation. Optimizing electrostatic brush interferences for increased detoning efficiency, 5,587,781, Cl. 355-301,000.
 Avery Dennison Corporation, *See*—
 Burns, Barbara J., and Shuman, Ralph J., 5,587,408, Cl. 523-160,000.
 Merser, F. Gerard, 5,586,353, Cl. 12-142,01C.
 Avery, Roger, *See*—
 Del Negro, James; Brown, Russell, and Avery, Roger, 5,586,910, Cl. 439-584,000.
 Awar, Takashi, *See*—
 Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Awar, Takashi; Tomoda, Akihito; and Ishida, Yasushi, 5,587,733, Cl. 347-185,000.
 Aziz, Ashar, to Sun Microsystems, Inc. Method and apparatus for a key-management scheme for internet protocols, 5,588,060, Cl. 380-301,000.
 Azuma, Toshikazu, *See*—
 Hioki, Yuchii; Kunita, Kazuhiko; Kawabata, Keiko, and Azuma, Toshikazu, 5,587,353, Cl. 504-116,000.
 Azumi, Takeshi; Yamaoka, Osamu; and Kubota, Kazuyuki, to Murata Manufacturing Co., Ltd. High-voltage capacitor manufacturing method and high-voltage capacitor, 5,587,869, Cl. 361-301,300.
 B. Bunch Company, Inc., *See*—
 Chase, Walter W., 5,586,964, Cl. 493-413,000.
 B.E.L.-Tromes Limited, *See*—
 Martinson, Glen D., and Malik, Stephen T., 5,587,916, Cl. 364-483,000.
 B.F. Goodrich Company, The, *See*—
 Lawson, Dennis L., and Determan, Robert E., 5,587,419, Cl. 524-527,000.
 B-Line Systems, Inc., *See*—
 Rinderer, Eric R., 5,587,555, Cl. 174-49,000.
 Baasch, Detlef, *See*—
 Bailly, Gerhard; Baasch, Detlef, and Gazykan, Unal, 5,586,470, Cl. 74-477,000.
 Babcock & Wilcox Company, The, *See*—
 Jeeve, John M., and Dow, Randall P., 5,587,025, Cl. 148-274,000.
 Babey, Jacques; Salmon, Brian; De Borst, Eric; and Tallier, Bernard, to Philip Morris Incorporated. Method for varying tobacco rod density and tobacco rods with varying density produced thereby, 5,586,565, Cl. 131-84,200.
 Bahuder, Kirt M.; Joseph, Douglas A.; Piskor, Donald, and Stupica, L. Joseph, to Devlieg-Bullard, Inc. Bar stock feeder method and apparatus having separable guide tube sections, 5,586,477, Cl. 82-126,000.

- Bader, Mansour S. Precipitation and separation of inorganic species from aqueous solutions, 5,587,088, Cl. 210-729,000.
 Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry, Arnold W.; Heeks, George J., and Fratangello, Louis D., to Xerox Corporation. Radiation induced grafting of polyorganosiloxanes to fluoroclastomers, 5,587,208, Cl. 427-503,000.
 Bae, Sang I., *See*—
 Bae, Tae H.; Bae, Sang Y.; and Bae, Sang I., 5,586,842, Cl. 407-29,140.
 Bae, Sang Y., *See*—
 Bae, Tae H.; Bae, Sang Y.; and Bae, Sang I., 5,586,842, Cl. 407-29,140.
 Bae, Tae H.; Bae, Sang Y.; and Bae, Sang I. File grinder, 5,586,842, Cl. 407-29,140.
 Bag-It Products Corp., *See*—
 McBride, John C., 5,586,655, Cl. 206-388,000.
 Bagepalli, Bharat S., and Dine, Osman S., to General Electric Company. Gas-path leakage seal for a gas turbine made from metallic mesh, 5,586,773, Cl. 277-167,500.
 Bähr, Klaus, to Heidelberg Druckmaschinen. Adjusting device for a matching table, 5,586,508, Cl. 108-2,000.
 Bai, Baocheng; Guner, Mahmut; Lu, Duoqia; Rosenblitt, David A.; and Stuck, Kaaren L., to Gestalt Technologies, Incorporated. Dynamic partitioning of memory into central and peripheral subregions, 5,588,138, Cl. 395-497,040.
 Bailey, Jack H., to Discovision Associates. System for recording digital information in a pulse-length modulation format, 5,587,983, Cl. 369-59,000.
 Bailey, William R., *See*—
 Hupp, Lawrence R.; Koryzinski, Jacek; Bailey, William R.; and Lesesky, Alan, 5,587,890, Cl. 361-826,000.
 Bailly, Gerhard; Baasch, Detlef, and Gazykan, Unal, to ZF Friedrichshafen AG. Gear-changing device for a gear box, in particular a motor vehicle gear box, 5,586,470, Cl. 74-477,000.
 Baker, Anna L., and Garrigus, Darryl E., to Boeing Company, The. Micro-particle enhanced fibrous ceramics, 5,587,228, Cl. 428-34,500.
 Baker, Evan, *See*—
 Bigley, Jon, and Baker, Evan, 5,586,632, Cl. 192-69,410.
 Baker Hughes Incorporated, *See*—
 Clark, David E.; and Dye, William M., 5,586,608, Cl. 175-40,000.
 Isbell, Matthew R.; and Pessier, Rudolf C. O., 5,586,612, Cl. 175-353,000.
 Baker, Neil M., to Securistyle Limited. Anti-rubbing block, 5,586,362, Cl. 16-193,000.
 Baker, Ronald J.; Fisher, Douglas G.; Rupert, Martha L.; and Swartz, David M., to Whitaker Corporation. The Electrical connector with contacts at different insertion depths, 5,586,915, Cl. 439-733,100.
 Baldwin, Stephen P., *See*—
 Kesseli, James B., and Baldwin, Stephen P., 5,586,429, Cl. 60-39,070.
 Balhoff, Donald E., *See*—
 Lin, Ronny W.; Atkinson, Eldon E., Jr.; and Balhoff, Donald E., 5,587,512, Cl. 562-565,000.
 Balistreri, Anthony M., *See*—
 Vogley, Wilbur C.; Balistreri, Anthony M.; Guttage, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartman, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221,000.
 Ballard, Clinton L. Cache for optical storage device and method for implementing same, 5,588,129, Cl. 395-440,000.
 Balu, Patrick J., to Tecnoma. Device for producing an air stream having a flattened shape in transverse section, 5,586,725, Cl. 239-172,000.
 Bamba, Noriko, *See*—
 Kagawa, Shunichi; Chiba, Kazuhiro; Bamba, Noriko; and Okuno, Yoshiaki, 5,588,050, Cl. 382-167,000.
 Bamber, David J.; Leung, Benson; and Leung, Vincent, to Coleman Company, Inc., The. Flashlight, 5,586,819, Cl. 362-158,000.
 Banba, Tsuyoshi, *See*—
 Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, 5,587,406, Cl. 523-116,000.
 Banitt, David, and Shlomo, Moshe B., to Exsight Ltd. Laser-induced metallic plasma for non-contact inspection, 5,587,664, Cl. 324-752,000.
 Banks, William A., *See*—
 Vander Meer, Robert K.; Banks, William A.; and Lofgren, Clifford S., 5,587,401, Cl. 514-675,000.
 Bansal, Madan L., and Vaidya, Jayant G., to Sundstrand Corporation. Dual output synchronous-induction starting/generating system, 5,587,647, Cl. 322-45,000.
 Banton, Randall G., *See*—
 Cutts, Richard W., Jr.; Banton, Randall G.; and Jewett, Douglas E., 5,588,111, Cl. 395-182,070.
 Bao, Qingcheng; Sorensen, Ian; and Glaunsinger, William, to Arizona Board of Regents. Selected area adhesion and surface passivation of metal films, 5,587,130, Cl. 422-88,000.
 Barbour, Garth S., *See*—
 Alkon, Daniel L.; Vogl, Thomas P.; Blackwell, Kim T.; and Barbour, Garth S., 5,588,091, Cl. 395-24,000.
 Barford, Lee A., *See*—
 Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein, Michael J.; and Wilker, Julie D., 5,587,914, Cl. 364-468,010.
 Bar-Kana, Izhak; and Filipovic, Predrag, to Kulicke and Soffa Investments, Inc. Observer-compensator for an electric motor system, 5,587,636, Cl. 318-561,000.
 Barker, Scott, *See*—
 Kimberlin, Robert R.; Bodell, Steven W.; Chang, Ted C.; Diesel, Robert M.; and Barker, Scott, 5,586,606, Cl. 173-62,000.
 Barker, Thomas N., *See*—
 Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800,000.
 Barkyoumb, John; Kahacoff, Lawrence T.; and Land, David J., to United States of America, Navy. Method of measuring the thermal conductivity of microscopic graphite fibers, 5,586,824, Cl. 374-44,000.
 Barnes, Steven J., and Spence, Scott R., to ITT Automotive Electrical Systems, Inc. Electric motor driven fan with water baffle, 5,586,871, Cl. 417-423,110.
 Barnes, Travis E., to Caterpillar Inc. Method of correcting engine maps based on engine temperature, 5,586,538, Cl. 123-446,000.
 Barnett, Richard I., *See*—
 Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Keith W.; Glover, Stephen E.; Barnen, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710,000.
 Barr, Frederick J., to Western Atlas International, Inc. Method for measuring the near-surface shear wave velocity for use in determining 3-component 3-D statics, 5,587,968, Cl. 367-75,000.
 Barr, Josef J. Method of making jewelry articles, 5,586,390, Cl. 29-896,411.
 Barre, Pierre; Dequin, Sylvie; and Ansanay, Virginie, to Institut National de la Recherche Agronomique - I.N.R.A. Cloning and expression of the gene of the malolactic enzyme of *Lactococcus lactis*, 5,587,304, Cl. 435-139,000.
 Barrett, Alfred H., to Delco Electronics Corp. Multi-phase power converter with harmonic neutralization, 5,587,892, Cl. 363-44,000.
 Barrett, Stephen L.; and Brown, Michael G., to Instratek, Inc. Instrumentation and surgical procedure for decompression for Morton's neuroma, 5,586,564, Cl. 128-898,000.
 Barsan, Radu, *See*—
 Lin, Jonathan; Peng, Jack Z.; Barsan, Radu, and Mehta, Sunil, 5,587,945, Cl. 365-185,100.
 Barta, Patrick J.; and Ponierheld, Ann L. Drinking glass, 5,586,647, Cl. 206-217,000.
 Barten, Michael, and Toutaoui, Mustapha, to Otis Elevator Company. Method for adjusting an elevator door, 5,587,566, Cl. 187-316,000.
 Bartingale, Peter, *See*—
 Sawyer, Colin; Wallis, John; and Bartingale, Peter, 5,586,933, Cl. 454-299,000.
 Bartok, Stephen. Expanding helical ratchet switch, 5,586,645, Cl. 200-527,000.
 BASF Aktiengesellschaft, *See*—
 Brandstetter, Franz; Gausepohl, Hermann; and Thiele, Reiner, 5,587,423, Cl. 525-52,000.
 Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Burger, Gert; and Pfl, Paul, 5,587,135, Cl. 423-239,100.
 Heider, Marc; Henkelmann, Jochem; and Karcher, Michael, 5,587,503, Cl. 556-427,000.
 Knühl, Klaus; Karl, Ulrich; Müller, Stefan; and de Potzoli, Bernd, 5,587,506, Cl. 560-12,000.
 Kröner, Hubertus; Jahns, Ekkehard; and Mielke, Manfred, 5,587,404, Cl. 522-85,000.
 Schnitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas, 5,586,992, Cl. 8-653,000.
 Schwerteger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochem; and Mielke, Manfred, 5,587,107, Cl. 252-315,000.
 Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Haberle, Karl, 5,587,421, Cl. 524-591,000.
 Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schelberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63,000.
 Batesville Casket Company, *See*—
 Enneking, John R.; and Schultz, John, 5,586,376, Cl. 27-27,000.
 Battist, Gerald E., *See*—
 Cherkuri, Subraman R.; Myers, Garry L.; Battist, Gerald E.; and Fuisz, Richard C., 5,587,172, Cl. 424-401,000.
 Baumann, Heinrich, to Robert Knips GmbH & Co. KG. Coffee machine, 5,586,485, Cl. 99-295,000.
 Bayer AG, *See*—
 Wood, Louis L.; and Caltan, Gary J., 5,587,146, Cl. 424-49,000.
 Bayer Aktiengesellschaft, *See*—
 Eisen, Norbert; Godhardt, Lutz-Peter; and Haas, Peter, 5,587,117, Cl. 264-45,700.
 Heiliger, Ludwig; Schmidt, Adolf; and Probst, Joachim, 5,587,443, Cl. 526-240,000.
 Langstein, Gerhard; Krüger, Ralf; Piejko, Karl-Erwin; Eisele, Ulrich; and Morbitzer, Leo, 5,587,424, Cl. 525-63,000.
 Meltzer, Aaron D.; and Karbach, Alexander, 5,587,435, Cl. 525-437,000.
 Salzburg, Herbert; Steinhoff, Georg; Gosch, Andreas; and Hufen, Gerd, 5,587,511, Cl. 562-513,000.
 Schünderhütte, Karl-Heinz; and Herd, Karl J., 5,587,465, Cl. 534-635,000.
 Bayer Corporation, *See*—
 Dattagupta, Nanibhushan; and Köcher, Jürgen, 5,587,472, Cl. 536-26,200.

- Meltzer, Aaron D., and Karbach, Alexander, 5,587,435, Cl. 525-437.000.
 Sanderson, Thomas, McGinley, Michael J., Zimmerman, Jeffrey J., Hill, Howard T., Meetz, Michael C., Pirtle, Eugene C., Swenson, Sabrina L., and Shibles, George P., 5,587,164, Cl. 424-218.000.
 Bayerische Motoren Werke AG, *See*—
 Huemer, Gerhart, and Lemberger, Heinz, 5,586,432, Cl. 60-274.000.
 Bayne, Donald E., Incontinence device, 5,586,978, Cl. 604-327.000.
 BCM International, Inc., *See*—
 Gross, Clifford M., 5,587,933, Cl. 364-558.000.
 Nelson, Arthur J., and Gross, Clifford M., 5,586,557, Cl. 128-779.000.
 BCM Engineers, Inc., *See*—
 Morrow, Steven R., 5,586,836, Cl. 405-128.000.
 Beamond, Trevor W., *See*—
 Dohbear, Keith D., Beamond, Trevor W., and Schofield, Kerry G., 5,586,626, Cl. 188-250.000.
 Beattie, Gillian M., *See*—
 Rubin, Jeffrey, Hayek, Alberto, Beattie, Gillian M., and Otonkoski, Timo P. J., 5,587,309, Cl. 435-240.200.
 Beaumont, Hendrikus, Haas, Hanns Otto, Wiese, Holger, and Lindner, Bernd, to MAN Roland Druckmaschinen AG, Method for eliminating gear train backlash in a drive for a multi-color sheet-fed printing machine having face printing and perfecting modes, 5,586,499, Cl. 101-211.000.
 Beck, Steven R., *See*—
 Rosch, Hans J., and Beck, Steven R., 5,586,678, Cl. 220-263.000.
 Beekends, John G., Muller, Frank, and van Ravesteijn, Robertus L. A., to Koninklijke PTT Nederland N.V., Bark amplitude component coder for a sampled analog signal and decoder for the coded signal, 5,588,089, Cl. 395-2-140.
 Behan, Dominic P., Vale, Wylie W., Jr., Fischer, Wolfgang H., and Lowry, Philip J., to Salk Institute For Biological Studies, The Brain-derived membrane-associated CRF binding proteins, 5,587,462, Cl. 530-350.000.
 Beitzmann, Michel, to Societe de Constructions de Matériel Metallique, Ventable container, 5,587,192, Cl. 426-118.000.
 Bélanger, Pierre-André, *See*—
 Champagne, Yves, Paré, Claude, and Bélanger, Pierre-André, 5,587,786, Cl. 356-121.000.
 Belcher, James F., Frank, Steven N., Tang, John P., and Jones, Jeanée, to Texas Instruments Incorporated, Multiple level mask for patterning of ceramic materials, 5,587,090, Cl. 216-17.000.
 Belden, Donald E., to Facet International, Inc., Replaceable element fluid filter, 5,587,071, Cl. 210-232.000.
 Bell Atlantic Network Services, Inc., *See*—
 Ganesan, Ravi, 5,588,056, Cl. 380-4.000.
 Ganesan, Ravi, and Yacobi, Yacov, 5,588,061, Cl. 380-30.000.
 Bell Communications Research, Inc., *See*—
 Anantucci, Glenn G., and Tarascon, Jean-Marie, 5,587,133, Cl. 423-138.000.
 Ganesan, Ravi, and Yacobi, Yacov, 5,588,061, Cl. 380-30.000.
 Gozdz, Antoni S., Schmutz, Caroline N., and Warren, Paul C., 5,587,253, Cl. 429-192.000.
 Bell, Laurence A. G., Calendar writing page, 5,587,215, Cl. 428-40.100.
 Belleau, Bernard, deceased (by Pierre, Belleau, executor), Nguyen-Ba, Nghe, Kong, Laval C. C., Mansour, Tarek, Jin, Haolun, and Brasili, Livio, to BioChem Pharma, Inc., Substituted 1,3-oxathiolanes and substituted 1,3-dithiolanes with antiviral properties, 5,587,480, Cl. 544-310.000.
 Belleau, Pierre, executor, *See*—
 Belleau, Bernard, deceased, Nguyen-Ba, Nghe, Kong, Laval C. C., Mansour, Tarek, Jin, Haolun, and Brasili, Livio, 5,587,480, Cl. 544-310.000.
 Belleville, Claude, Van Nette, Richard, Caron, Serge, Houle, Alain C., and Thibault, Pierre, to Citicq, Optical interferometric current sensor and method using a single mode birefringent waveguide and a pseudo-polarizer for measuring electrical current, 5,587,791, Cl. 356-345.000.
 BellSouth Corporation, *See*—
 Comer, Edward L., 5,588,042, Cl. 379-59.000.
 Belot, Dominique, *See*—
 Karimith, Pierre, Bultenot, Marc, and Belot, Dominique, 5,587,283, Cl. 431-10.000.
 Beltzer, Morton, Berlowitz, Paul J., and Kim, Jeonok T., to Exxon Research and Engineering Company, High load-carrying turboshafts containing amine phosphate and thiophene carboxylic acid derivatives, 5,587,355, Cl. 508-302.000.
 Benade, Martinus J., Brick press, 5,587,187, Cl. 425-409.000.
 Benard, David J., *See*—
 Wieloch, Christopher J., Kappel, Mark A., Annis, Jeffrey R., Benard, David J., Boehmer, Ellen, and Hildebrandt, Gernot, 5,587,861, Cl. 361-14.000.
 Benckert, Hartmut, and Muenzenmaier, Werner, to Putzmeister-Werk Maschinenfabrik GmbH, Initial pressure governor for a variable displacement pump, 5,586,869, Cl. 417-218.000.
 Bengmark, Stig, Ahne, Sivi, Molin, Göran, and Jeppson, Bengt, to Probi AB, Intestine colonizing lactobacilli, 5,587,314, Cl. 435-252.900.
 Ben-Moshe, Josef, *See*—
 Segal, Jacob, Ben-Moshe, Josef, Weinstock, Zvika, and Harnik, Zvika, 5,588,151, Cl. 395-800.000.
 Bennardo, Gilbert, and Goubely, Aime, to Eaton Corporation, Adjustable solenoid valve with improved stability, 5,586,747, Cl. 251-129.180.
 Bennett, Brian R., to AST Research, Inc., Method and apparatus for increasing bus bandwidth on a system bus by inhibiting interrupts while posted I/O write operations are pending, 5,588,125, Cl. 395-306.000.
 Bennett, Michael J., Nino, John E., and Todoroff, Brian D., to Mikohn Gaming Corporation, Automated gaming table tracking system and method therefor, 5,586,936, Cl. 463-25.000.
 Benoit, Louis, to Salomon S.A., Hook closure for boot, 5,586,367, Cl. 24-68.05K.
 Bensch, Christopher J., *See*—
 Warner, Joseph G., and Bensch, Christopher J., 5,586,785, Cl. 280-762.000.
 Benthin Aktiengesellschaft, *See*—
 Benthin, Siegfried, 5,586,631, Cl. 192-8.00R.
 Benthin, Siegfried, to Benthin Aktiengesellschaft, Window shade, 5,586,631, Cl. 192-8.00R.
 Bently, John F., Quick connector for joining large diameter vacuum hose to ductwork, 5,586,789, Cl. 285-38.000.
 Ben-Yair, Igal, Berger, Haim, and Perlmutter, Oleg, to Israel Aircraft Industries, Ltd., Air combat monitoring system and methods and apparatus useful therefor, 5,587,904, Cl. 364-449.700.
 Berbi Gesellschaft m.b.H., *See*—
 Binder, Bernd, 5,587,291, Cl. 435-7.400.
 Berdul, Elbert, Levitation system using permanent magnets for use with trains and the like type of right-of-way vehicles, 5,586,505, Cl. 104-283.000.
 Berg, Arne, *See*—
 Almén, Torsten, Berg, Arne, Dugstad, Harald, Klavens, Jo, Krautwurst, Klaus D., and Kongved, Pal, 5,587,144, Cl. 424-9.361.
 Bergamini, Giorgio, and Minini, Venanzio, to Nuovopignone Industrie Meccaniche e Fonderie S.p.A., Electropneumatic converter with solenoid valve control, 5,586,575, Cl. 137-488.000.
 Bergemont, Albert, and Chi, Min-Hwa, to National Semiconductor Corporation, Method for programming an ETOX EPROM or flash memory when cells of the array are formed to store multiple bits of data, 5,587,949, Cl. 365-185.240.
 Bergemont, Albert, *See*—
 Chi, Min-Hwa, Bergemont, Albert, and Haggag, Hosam, 5,587,596, Cl. 257-223.000.
 Bergen, Franciscus H. M., Rutte, Jan J., Nijssen, Stephanus J. J., and De With, Peter H. N., to U.S. Philips Corporation, Extended definition video signal converter for use with a video recorder, 5,587,802, Cl. 386-26.000.
 Bergen, Richard E., to Xerox Corporation, Apparatus for charging a film on the internal surface of a drum, 5,587,584, Cl. 250-325.000.
 Berger, Edward A., Moss, Bernard, Fuerst, Thomas R., Pastan, Ira, Fitzgerald, David, Mirakami, Taino, and Chaudhary, Vijay K., to United States of America, Health and Human Services, Cytotoxic agent against specific virus infection, 5,587,455, Cl. 530-324.000.
 Berger, Haim, *See*—
 Ben-Yair, Igal, Berger, Haim, and Perlmutter, Oleg, 5,587,904, Cl. 364-449.700.
 Berger, Thomas A., to Pace Company, Airflow measuring centrifugal fan, 5,586,861, Cl. 415-118.000.
 Berget, Mark D., *See*—
 Sibik, Lee L., and Berget, Mark D., 5,586,447, Cl. 62-141.000.
 Bergevin, Jerry G., to Turf Systems International, Inc., Surface for sports and other uses, 5,586,408, Cl. 47-1.010.
 Bergman, Rolf S., *See*—
 Parham, Thomas G., Dynys, Frederick W., Gunter, Carl V., Davenport, John M., Goltz, Thomas M., Bergman, Rolf S., Ahlgren, Frederic F., Allen, Gary R., Duffy, Mark E., and Hansler, Richard L., 5,587,626, Cl. 313-634.000.
 Bergmann, Wolfgang R., *See*—
 Domke, Todd W., and Bergmann, Wolfgang R., 5,587,147, Cl. 421-54.000.
 Bergström, Jan O., Liljegen, Lars, Skarhed, Ove, and Arenas, Anders, to Asea Brown Boveri AB, Digital interface unit, 5,587,863, Cl. 361-931.000.
 Berkean, Ertugrul, and Seymour, Raymond K., to General Electric Company, Alternating current sensor based on parallel-plate geometry and having a conductor for providing separate self-powering, 5,587,651, Cl. 324-127.000.
 Berkean, Ertugrul, Seymour, Raymond K., and Grzelecki, John C., to General Electric Company, Alternating current sensor based on parallel-plate geometry and having a shunt for self-powering, 5,587,652, Cl. 324-127.000.
 Berkowitz, Gary M., Daugherty, Thomas H., Edwards, Rand J., Klerer, S. Mark, Meader, Lyla R., and Strohecker, Gary A., Sr., to Lucent Technologies, Inc., Method for dynamically provisioning telephone service, 5,588,051, Cl. 379-243.000.
 Berlowitz, Paul J., *See*—
 Beltzer, Morton, Berlowitz, Paul J., and Kim, Jeonok T., 5,587,355, Cl. 508-302.000.
 Bernard, Leroy A., Jr., Adjustable window tinting system, 5,587,828, Cl. 359-275.000.
 Bernheiser, Charles A., to Gargoyles, Inc., Interchangeable eyeglass lens system, 5,587,747, Cl. 351-105.000.
 Bertrand, Jean-Louis, Charrier, Gilles A., Guyonnet, Xavier J. A., and Picard, Jean-Louis, to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation "Snecma", Turbo aero engine provided with a device for heating turbine disks on revving up, 5,586,860, Cl. 415-115.000.
 Besse, Michael E., Ross, Cynthia L., and Kleaver, Helen A., to Ecobal Inc., Adhesive release agent applied to surface for improved cleaning, 5,587,009, Cl. 106-244.000.
 Bessler, Warren F., to General Electric Company, Low refrigerant charge detection using a combined pressure/temperature sensor, 5,586,445, Cl. 62-126.000.

- Beth Israel Hospital Association, The, *See*—
 Strom, Terry B., 5,587,162, Cl. 424-183.100.
 Betsui, Keichi, *See*—
 Fukuta, Shinya, and Betsui, Keichi, 5,587,720, Cl. 345-75.000.
 Betz, Richard T., Surface covering, 5,587,218, Cl. 428-67.000.
 Bevilacqua, Bruce W., Malandra, Louis J., Meuschke, Robert E., and Harkness, Alex W., to Westinghouse Electric Corporation, Apparatus for reinforcing a reactor vessel core shroud, 5,588,031, Cl. 376-287.000.
 Bhatta, Pradeep H., to Sun Microsystems, Inc., Method and apparatus for passive loopback testing of software-controllable parallel ports, 5,588,114, Cl. 395-183.010.
 Bhatnagar, Ashok, *See*—
 Lin, Leroy C., Wilson, Laura G., Bhatnagar, Ashok, and Li, Hsin L., 5,587,230, Cl. 428-245.000.
 Bhowmik, Santi R., *See*—
 Cherukuri, Subraman R., Yang, Robert K., Bowles, Cecil A., Zamudio-Tena, Jose F., and Bhowmik, Santi R., 5,587,198, Cl. 426-660.000.
 Bidan, Gérard, *See*—
 Vieil, Eric, Bidan, Gérard, Gadelle, Andrée, and Mendes-Viegas, Maria-Fatima, 5,587,466, Cl. 536-4.100.
 Bielig, Peter M., Brähler, Klaus, and Gschöbmann, Günther, to Knorr-Bremse Systeme für Nutzfahrzeuge GmbH, Electronic control equipment for motor vehicles, particularly, electronic brake control equipment, 5,587,865, Cl. 361-45.000.
 Bigley, Jon, and Baker, Evan, Pulse actuated interlock mechanism, 5,586,632, Cl. 192-69.410.
 Binder, Bernd, to Berbi Gesellschaft m.b.H., Method for the determination of plasmin d2-antiplasmin complexes and the use of this method as a mean of determining changes in the fibrinolytic system, 5,587,291, Cl. 435-7.400.
 Binelli, James C., to Lab Holding Company, Tubing bracket assembly, 5,586,738, Cl. 248-73.000.
 Binga, Tonya D., *See*—
 Visser, Susan A., Hewitt, Charles E., Binga, Tonya D., Ferrar, Wayne T., Fichtner, Michael W., and Fitzgerald, John J., 5,587,245, Cl. 428-447.000.
 Binsbergen, Frederik L., Bos, Alouisius N. R., and Santen, Augustinus, to Shell Oil Company, Process for preparing styrene polymers, 5,587,438, Cl. 526-88.000.
 BioChem Pharma, Inc., *See*—
 Belleau, Bernard, deceased, Nguyen-Ba, Nghe, Kong, Laval C. C., Mansour, Tarek, Jin, Haolun, and Brasili, Livio, 5,587,480, Cl. 544-310.000.
 Biophysics Technologies, Inc., *See*—
 Krause, Andrew W., 5,587,832, Cl. 359-385.000.
 Biotechnology Australia Pty. Ltd., *See*—
 Cobon, Gary S., Moore, Joanna T., Johnston, Law A. Y., Willadsen, Peter, Kemp, David H., Srisanthana, Alagacane, and Riding, George A., 5,587,311, Cl. 435-240.200.
 Biotechnology Research and Development Corporation, *See*—
 Briggs, Robert E., and Tatum, Fred M., 5,587,305, Cl. 435-172.100.
 Bird, Robert E., *See*—
 King, C. Richter, Kasprzyk, Philip G., and Bird, Robert E., 5,587,458, Cl. 530-387.300.
 Birkner, John M., *See*—
 Chan, Andrew K., Birkner, John M., and Chua, Hua T., 5,587,669, Cl. 326-38.000.
 Bissell, *See*—
 Wolfe, Jack, and Ping, Roy C. C., 5,586,358, Cl. 15-334.000.
 Bissett, Thomas D., *See*—
 Dearth, Glenn, and Bissett, Thomas D., 5,588,112, Cl. 395-182.070.
 Bissolino, Pierluigi, *See*—
 Alpegiani, Marco, Bissolino, Pierluigi, and Perrone, Ettore, 5,587,373, Cl. 514-202.000.
 Bito, Toshiaki, *See*—
 Minato, Tetsuya, Yonehara, Toshimitsu, Teranishi, Junichi, Toyoda, Shohci, Bito, Toshiaki, and Takashima, Kazushige, 5,587,694, Cl. 336-65.000.
 Bizerba-Werk Wilhelm Kraut GmbH & Co. KG, *See*—
 Kraut, Ingolf, 5,586,640, Cl. 198-692.000.
 Black, Robert H., Method of rinsing showers, 5,587,022, Cl. 134-26.000.
 Blackwell, Kim T., *See*—
 Alkon, Daniel L., Vogl, Thomas P., Blackwell, Kim T., and Barbour, Garth S., 5,588,091, Cl. 395-24.000.
 Blake, Thomas B., *See*—
 Borlinghaus, Hans J., Nini, James P., and Blake, Thomas B., 5,586,740, Cl. 248-157.000.
 Blakelock, Philip, *See*—
 Pfizenmaier, Heinz, Blakelock, Philip, Prime, Brian, and Dawson, David, 5,587,713, Cl. 342-70.000.
 Blanchard, Chuck L., *See*—
 Lanier, Jaron Z., Lasko-Harvill, Ann, Blanchard, Chuck L., and Sparks, Joe L., 5,588,104, Cl. 395-326.000.
 Lanier, Jaron Z., Grimaud, Jean-Jacques G., Harvill, Young L., Lasko-Harvill, Ann, Blanchard, Chuck L., Oberman, Mark L., and Teitel, Michael A., 5,588,139, Cl. 395-500.000.
 Blecher, Leo, Longworth, Ralph C., Murray, F. Scott, Jonas, Philip A., and Boiarski, Michael, to Internagetics General Corporation, MRI cryostat cooled by open and closed cycle refrigeration systems, 5,586,437, Cl. 62-47.100.
 Bleicher, Edit, *See*—
 Hajimichael, Janis, Botar, Sandor, Bleicher, Edit, Pap, Laszlo, Szekely, Istvan, Marmarosi née Kellner, Katalin, and Ori, Janos, 5,587,370, Cl. 514-183.000.
 Blomet, Joël, Blomet épouse Meyer, Marie-Claude, and Jahan, Dominique F., to Blomet épouse Meyer, Marie-Claude, Physiological composition for the treatment of thermal or chemical burns, 5,587,400, Cl. 514-566.000.
 Blomet épouse Meyer, Marie-Claude, *See*—
 Blomet, Joël, Blomet épouse Meyer, Marie-Claude, and Jahan, Dominique F., 5,587,400, Cl. 514-566.000.
 Bluthgen, Björn, to U.S. Philips Corporation, and Dupont Optical Company, Information carrier having information packets containing coded text or image information relating to different categories, arrangement for reading such information carrier and a system including such arrangement and information carrier, 5,587,979, Cl. 369-32.000.
 Board of Governors for Higher Education, State of Rhode Island and Providence Plantations, The, *See*—
 Panzica, Raymond P., El Subhagh, Hussein I., and Abushanab, Elie, 5,587,494, Cl. 549-512.000.
 Board of Regents, The University of Texas System, *See*—
 Sessler, Jonathan L., Hemmi, Gregory W., and Murai, Toshiaki, 5,587,463, Cl. 534-15.000.
 Sessler, Jonathan L., Král, Vladimir, and Andrievsky, Andrei, 5,587,478, Cl. 540-474.000.
 Board of Supervisors of Louisiana State University and Agricultural and Mechanical College, *See*—
 Laine, Roger A., and Lo, Wai C. J., 5,587,292, Cl. 435-7.900.
 Board of Trustees Leland Stanford, Jr. University, *See*—
 White, Robert L., 5,587,223, Cl. 428-195.000.
 Board of Trustees operating Michigan State University, *See*—
 Boyd, Stephen A., and Kukkadapu, Ravi, 5,587,084, Cl. 210-691.000.
 Board of Trustees, Univ. of TX Sys., *See*—
 Sessler, Jonathan L., Mody, Tarak D., Hemmi, Gregory W., Král, Vladimir A., and Magda, Darren, 5,587,371, Cl. 514-185.000.
 Boardman, William J., *See*—
 Chang, Kuang-Yeh, Nariani, Subhash R., and Boardman, William J., 5,587,332, Cl. 437-43.000.
 Bob, Alexander, *See*—
 Gründl, Andreas, Bob, Alexander, and Bob, Konstantin, 5,586,968, Cl. 600-114.000.
 Bob, Konstantin, *See*—
 Gründl, Andreas, Bob, Alexander, and Bob, Konstantin, 5,586,968, Cl. 600-114.000.
 Bobik, Michael, Lindbauer, Ralf L., and Glasner, Alfred, to Austrian Energy & Environment, SGP/Wagner-Biro GmbH, Process for preventing the formation of harmful organic substances and steam generator for carrying out the process, 5,587,138, Cl. 423-242.100.
 Bobo, Donald E., Jr., and Doupe, Thomas H., to Innerspace, Inc., Blood pressure monitoring pad assembly and method, 5,586,555, Cl. 128-672.000.
 BOC Group, Inc., The, *See*—
 Bulow, Martin, Dao, Loc, and Fitch, Frank R., 5,587,003, Cl. 95-123.000.
 Bode, Udo D., *See*—
 Grossa, Mario, Bode, Udo D., Sondergeld, Manfred, Wiedenmann, Karl-Heinz, Convers, Ronald J., Kalo, Steven M., and Kudva, Ashok K., 5,587,272, Cl. 430-257.000.
 Bodell, Steven W., *See*—
 Kimberlin, Robert R., Bodell, Steven W., Chang, Ted C., Diesel, Robert M., and Barker, Scott, 5,586,606, Cl. 173-62.000.
 Boeckeler, Rudolph H., to Sartomer Company, Inc., Esters of hydroxy terminated polybutadiene compositions and methods for making same, 5,587,433, Cl. 525-333.200.
 Boegner, Walter, Kraemer, Michael, Kruttsch, Bernd, Wenninger, Guenter, Wirbeleit, Friedrich, and Weisweiler, Werner, to Daimler-Benz AG, Process and apparatus for selective catalyzed no-reduction in oxygen-containing exhaust gases, 5,586,433, Cl. 60-274.000.
 Boehmer, Ellen, *See*—
 Wieloch, Christopher J., Kappel, Mark A., Annis, Jeffrey R., Benard, David J., Boehmer, Ellen, and Hildebrandt, Gernot, 5,587,861, Cl. 361-14.000.
 Boehringer Mannheim Italia, SpA, *See*—
 Krapcho, A. Paul, Hacker, Miles P., Cavallenti, Ennio, and Giuliani, Ferdinando C., 5,587,382, Cl. 514-290.000.
 Boeing Company, The, *See*—
 Baker, Anna L., and Garrigus, Darryl F., 5,587,228, Cl. 428-34.500.
 Matsen, Marc R., Poel, Richard J., Crow, Wesley B., and Nansen, David S., 5,587,098, Cl. 219-615.000.
 Micale, Antonio C., 5,586,391, Cl. 29-897.200.
 Bohland, William, Lawn game apparatus for use with a water hose, 5,586,767, Cl. 273-349.000.
 Böhm, Robert, *See*—
 Spiegel, Herbert, and Böhm, Robert, 5,586,720, Cl. 237-8.00R.
 Boiarski, Michael, *See*—
 Blecher, Leo, Longworth, Ralph C., Murray, F. Scott, Jonas, Philip A., and Boiarski, Michael, 5,586,437, Cl. 62-47.100.
 Böke, Winfried, *See*—
 Hambitzer, Günther, Böke, Winfried, and Oertel, Armin, 5,587,064, Cl. 205-742.000.
 Bolan, Michael L., *See*—

- Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.
- Bollens, Eric: *See*—
Philippe, Michel; Semeria, Didier; and Bollens, Eric, 5,587,169, Cl. 424-401.000.
- Holt Beranek and Newman Inc.: *See*—
Murray, Bruce S.; Noble, Howard C.; and Quinn, Wilma W., 5,587,615, Cl. 310-30.000.
- Bond, David L.: *See*—
Meyer, George W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F., 5,588,041, Cl. 379-59.000.
- Bonitati, John A.; Case, Kirt L.; Hawkins, Michael E.; and Hoag, Stephen H., to Zimmer, Inc. Bone cement preparation kit, 5,586,821, Cl. 366-139.000.
- Bonora, Anthony C.; and Oem, Joshua T., to Asyst Technologies, Inc. Direct loadlock interface, 5,586,585, Cl. 141-93.000.
- Borne, Steven F.; and Ho, Edward J., to Mark IV Transportation Products Corp. Transponder having microprocessor generated frequency shift signals, 5,587,712, Cl. 342-42.000.
- Boon-Falleur, Thierry: *See*—
Lurquin, Christopher; and Boon-Falleur, Thierry, 5,587,289, Cl. 435-6.000.
- Bowstra, Tjerk O.; and Wiersum, Ulteri E., to Akzo Nobel N.V. Non-linear optically active polycarbonate, 5,588,083, Cl. 385-122.000.
- Booth, John W., to Sunjet Corporation. Method of removing a whirlpool jet apparatus from a whirlpool bathtub for inspection, cleaning or repair, 5,587,023, Cl. 134-32.000.
- Borchers, Gerd; Duke, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zilahala, Richard; Rimsa, Stephen; Losomis, Gary; Tatarka, Paul; and Mauzac, Olivier, to National Starch and Chemical Investment Holding Corporation. Esterified starch composition, 5,587,412, Cl. 524-47.000.
- Borden, Inc.: *See*—
Shustack, Paul J., 5,587,403, Cl. 522-42.000.
- Borg-Warner Automotive, Inc.: *See*—
Sullivan, Chris; Wells, Jim; and Prevost, Michael, 5,587,092, Cl. 219-113.000.
- Boeinghaus, Hans J.; Nini, James P.; and Blake, Thomas B., to General Motors Corporation. Chuckless power seat adjuster slide, 5,586,740, Cl. 248-157.000.
- Bormann, James E.: *See*—
Melver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A., 5,587,906, Cl. 364-424.045.
- Bormann, Thomas: *See*—
Pall, David B.; Gsell, Thomas C.; Markovich, Vlado I.; and Bormann, Thomas, 5,587,070, Cl. 210-202.000.
- Borrill, Paul L., to Sun Microsystems, Inc. System and method for a snooping and snatching cache in a multiprocessor computer system, 5,588,131, Cl. 395-473.000.
- Borsboom, Antonius H.; Gennari, Anthony A.; Rudolph, Kenneth G.; and Zaber, Peter J., to General Electric Company. Reinforced material handling container, 5,586,675, Cl. 220-6.000.
- Borup, David T.: *See*—
Johnson, Steven A.; Wiskin, James W.; Borup, David T.; Christensen, Douglas A.; and Stenger, Frank, 5,588,032, Cl. 378-8.000.
- Bos, Alouisius N. R.: *See*—
Bimbergen, Frederik L.; Bos, Alouisius N. R.; and Santen, Augustinus, 5,587,438, Cl. 526-88.000.
- Bosmans, Jean-Paul R. M. A.: *See*—
Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdunck, Marc G. C.; and Janssen, Paul A. J., 5,587,387, Cl. 514-312.000.
- Bosshart, Patrick W., to Texas Instruments Incorporated. High speed microprocessor branch decision circuit, 5,588,127, Cl. 395-376.000.
- Botar, Sandor: *See*—
Hajmicheal, Janis; Botar, Sandor; Blecher, Edit; Pap, Laszlo; Szekely, Istvan; Marmaros née Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
- Botka, Alexander T.; Tuvai, Ben; and Marcovici, Sorin, to Analogic Corporation. Coplanar X-ray photodiode assemblies, 5,587,611, Cl. 257-458.000.
- Bouchard, Hervé; Bourzat, Jean-Dominique; and Commercon, Alain, to Rhone-Poulenc Rorer S.A. Process for preparing taxoids, 5,587,493, Cl. 549-510.000.
- Boudet, François: *See*—
Le Corre, Hervé; Grimault, Jean-Luc; and Boudet, François, 5,587,809, Cl. 358-405.000.
- Boulanger, Gilles. Computer controlled disk storage unit with a telescopic arm for reading and writing information on a disk located in a magazine, 5,587,988, Cl. 369-178.000.
- Bourboulon, Marie-Alix: *See*—
Junino, Alex; LaGrange, Alan; N'Guyen, Quang L.; and Bourboulon, Marie-Alix, 5,587,173, Cl. 424-401.000.
- Bourzat, Jean-Dominique: *See*—
Bouchard, Hervé; Bourzat, Jean-Dominique; and Commercon, Alain, 5,587,493, Cl. 549-510.000.
- Bouse, Earl F.: *See*—
Leonard, R. Leon; Bouse, Earl F.; and McQueen, Anne T., 5,586,510, Cl. 110-345.000.
- Boutos, David. Collapsible seating apparatus, 5,586,560, Cl. 128-845.000.
- Bowden, Lori; Jochims, Sharon L.; and Orus, Erol, to Island Graphics Corporation. Method and apparatus for selectively expandable menus, 5,588,107, Cl. 395-344.000.
- Bowen, David K.; and Thomas, Charles R., to Rolls-Royce PLC; and University of Warwick. Apparatus and method for inspecting a crystal, 5,588,034, Cl. 378-73.000.
- Bowers, Derek E., to Analog Devices, Inc. Voltage controlled amplifier with a negative resistance circuit for reducing non-linearity distortion, 5,587,689, Cl. 330-254.000.
- Bowles, Cecil A.: *See*—
Cherukun, Subraman R.; Yang, Robert K.; Bowles, Cecil A.; Zamudio-Tena, Jose F.; and Bhowmik, Santi R., 5,587,198, Cl. 426-660.000.
- Boyd, Stephen A.; and Kukkadapu, Ravi, to Board of Trustees operating Michigan State University. Method of removing organic contaminants from air and water with organophilic, quaternary phosphonium ion-exchanged smectite clays, 5,587,084, Cl. 210-691.000.
- Bracco International B.V.: *See*—
Tourmier, Hervé; Hyacinthe, Roland; and Schneider, Michel, 5,587,199, Cl. 427-2.120.
- Bradford, John F.: *See*—
McCullough, James D., Jr.; and Bradford, John F., 5,587,434, Cl. 525-333.800.
- Brady USA, Inc.: *See*—
Hying, Clement F.; Perko, Jack E.; and Wenzler, Larry E., 5,587,043, Cl. 156-566.000.
- Braet, Johan: *See*—
Bruggeman, Aimé; and Braet, Johan, 5,587,047, Cl. 159-47.300.
- Brähler, Klaus: *See*—
Bielig, Peter M.; Brähler, Klaus; and Gschöbmann, Günther, 5,587,865, Cl. 361-45.000.
- Braithwaite, Paul C.; Lund, Gary K.; and Wardle, Robert B., to Thiokol Corporation. High performance pressable explosive compositions, 5,587,553, Cl. 149-19.600.
- Brandstetter, Franz; Gausepohl, Hermann; and Thiele, Reiner, to BASF Aktiengesellschaft. Preparation of block copolymers by ionic polymerization, 5,587,423, Cl. 525-52.000.
- Brandstrom, Per: *See*—
Franke, Rickard; Kaneko, Yutaka; and Brandstrom, Per, 5,586,576, Cl. 137-550.000.
- Branner, Donald L.; Ray, Andrew E.; Peters, Scott M.; and Huber, Richard M., to Motorola, Inc. Method and apparatus for power off control of a selective call radio, 5,587,706, Cl. 340-825.440.
- Brasca, Maria G.: *See*—
Buzzeiti, Franco; Fustinoni, Silvia; Brasca, Maria G.; and Penco, Sergio, 5,587,385, Cl. 514-309.000.
- Brasil, Lívio: *See*—
Belleau, Bernard; deceased, Nguyen-Bai, Nghie; Kong, Laval C. C.; Mansour, Tarek; Jin, Haolun; and Brasil, Lívio, 5,587,480, Cl. 544-310.000.
- Brattesant, Steven J. Periodontal probe tip and method for using, 5,587,284, Cl. 433-72.000.
- Bratton, Wes, to Applied Research Associates, Inc. Downhole volatile organic compounds trap for improved sampling of volatile organic compounds using cone penetrometer testing techniques, 5,587,538, Cl. 73-863.330.
- Braun, Gerhard, to Amphenol-Tüchel Electronics GmbH. Contacting apparatus for a chipcard, 5,586,890, Cl. 439-66.000.
- Bray, Robert, Jr. Microsurgical curette, 5,586,989, Cl. 606-160.000.
- Breeze, Brian A.: *See*—
Paterson, Robert L.; and Breeze, Brian A., 5,586,605, Cl. 173-4.000.
- Breidenbach, Diane; and Mille, Laurence, to Fragrance Systems International, Inc. Perfume applicator with replaceable cartridges, 5,586,694, Cl. 222-183.000.
- Brennan, James M. Digital photo kiosk, 5,587,740, Cl. 348-373.000.
- Brent, S. Shannon; and Forbes, Craig W. Fishing rod bite indicator, 5,586,402, Cl. 43-17.000.
- Bridgeman, Mark; and Penou, Pierre. Vehicle locking systems, 5,586,646, Cl. 200-541.000.
- Bridgestone Corporation: *See*—
Fujimoto, Mikio, 5,587,040, Cl. 156-394.100.
- Nakane, Shinsuke; Kanou, Kazuhiko; and Hashimoto, Takatsugu, 5,587,417, Cl. 524-495.000.
- Takizawa, Toshiki; Horikawa, Yasuo; and Akazawa, Taro, 5,587,420, Cl. 524-572.000.
- Yasunaga, Kuniaki; and Ueno, Shigeru, 5,587,731, Cl. 347-86.000.
- Bridgestone Metalph Corporation: *See*—
Miura, Yoshihiro; and Goto, Masami, 5,586,733, Cl. 242-125.200.
- Briem, Eberhard: *See*—
Graudejus, Wolfgang; Briem, Eberhard; Haettich, Wilhelm; and Geiselmann, Herbert, 5,586,663, Cl. 209-582.000.
- Briggs, Robert E.; and Tatum, Fred M., to United States of America. Agriculture; and Biotechnology Research and Development Corporation. *Pasteurella haemolytica* transformants, 5,587,305, Cl. 435-172.100.
- Bringman, Timothy S.: *See*—
Nedwin, Glenn E.; Bringman, Timothy S.; and Couraud, Pierre-Olivier, 5,587,460, Cl. 530-396.000.
- Brinkoetter, Thomas R.: *See*—
Oldfield, William W.; Brinkoetter, Thomas R.; and Antes, Todd D., 5,587,934, Cl. 364-571.010.
- Briscoe, Noel A.: *See*—
McIntosh, Bruce M.; Smith, Francis S.; and Briscoe, Noel A., 5,587,541, Cl. 84-297.005.
- Bristol, Edgar H.: *See*—
Hansen, Peter D.; and Bristol, Edgar H., 5,587,896, Cl. 364-148.000.
- Bristol-Myers Squibb Company: *See*—

- Robl, Jeffrey A., 5,587,375, Cl. 514-213.000.
- British Technology Group Limited: *See*—
Donachie, William, 5,587,166, Cl. 424-255.100.
- British Telecommunications public limited company: *See*—
Peacock, John; Frost, Peter L. J.; and Kerry, John, 5,588,076, Cl. 385-20.000.
- Brocchetta, Marino: *See*—
De Haen, Christoph; Uggeri, Fulvio; Gazzotti, Omella; and Brocchetta, Marino, 5,587,487, Cl. 548-561.000.
- Brock, James H.; and Foster, Robert P. Golf swing training device, 5,586,761, Cl. 473-207.000.
- Brooks, Jeffrey S.; and Dohanich, Stephen L., to International Business Machines Corporation. Integrated software development system including group decision support subsystem, application development subsystem, and bridge subsystem therebetween, 5,587,935, Cl. 364-578.000.
- Brother Kogyo Kabushiki Kaisha: *See*—
Nakata, Takashi, 5,586,828, Cl. 400-185.000.
- Sugahara, Hiroto; and Takahashi, Yoshikazu, 5,587,727, Cl. 347-12.000.
- Takami, Hiroshi; Yasui, Yoshihiro; and Okumura, Takashi, 5,586,500, Cl. 101-327.000.
- Brousseau, Claude, to Etalex Inc. Gravity fed bottle dispensing and display rack, 5,586,665, Cl. 211-59.200.
- Brown, Donald C., to Heyco Stamped Products, Inc. Blade receptacle, 5,586,920, Cl. 439-857.000.
- Brown, Jerry W.; and Brubaker, Stewart. Method and apparatus for prevention of register receipt falsification, 5,586,787, Cl. 283-67.000.
- Brown, Michael G.: *See*—
Barrett, Stephen L.; and Brown, Michael G., 5,586,564, Cl. 128-898.000.
- Brown, Robert H., III: *See*—
Kowalczyk, Robert M.; Brown, Robert H., III; and Heller, Jack W., 5,587,957, Cl. 365-230.030.
- Brown, Russell: *See*—
Del Negro, James; Brown, Russell; and Avery, Roger, 5,586,910, Cl. 439-584.000.
- Brown, Sanford M., III: *See*—
Knuth, Stephen B.; Brown, Sanford M., III; and Karmowski, Mark J., 5,588,046, Cl. 379-67.000.
- Brown, Scott H.; Zisman, Stan A.; and Kimble, James B., to Phillips Petroleum Company. Alkyne hydrogenation catalyst and process, 5,587,348, Cl. 502-230.000.
- Brubaker, Stewart: *See*—
Brown, Jerry W.; and Brubaker, Stewart, 5,586,787, Cl. 283-67.000.
- Bruggeman, Aimé; and Braet, Johan, to Studiecentrum voor Kernenergie. Method for separating boric acid, 5,587,047, Cl. 159-47.300.
- Brüker Analytische Messtechnik GmbH: *See*—
Simon, Arno; and Gast, Jürgen, 5,587,831, Cl. 359-350.000.
- Brüker Instruments, Inc.: *See*—
Sukumar, Subramaniam, 5,587,658, Cl. 324-309.000.
- Brüss, Dieter: *See*—
Altekrüger, Burkhard; Aufreiter, Joachim; Brüss, Dieter; and Kalkowski, Klaus, 5,587,016, Cl. 117-214.000.
- Bryant, Bruce D.: *See*—
Hampo, Richard J.; Marko, Kenneth A.; and Bryant, Bruce D., 5,587,524, Cl. 73-116.000.
- Buchfink, Adolf, to Claudius Peters Aktiengesellschaft. Process and apparatus for screening a stream of bulk material, 5,586,660, Cl. 209-3.000.
- Buday, Mahdi; and Kolff, Jack. Stethoscope shield, 5,587,561, Cl. 181-131.000.
- Budget Lamp Reclaimers, Inc.: *See*—
Mortrud, Jon P., 5,586,730, Cl. 241-24.220.
- Buechele, Wolfgang: *See*—
Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Buerger, Gert; and Pijl, Paul, 5,587,135, Cl. 423-239.100.
- Buerger, Gert: *See*—
Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Buerger, Gert; and Pijl, Paul, 5,587,135, Cl. 423-239.100.
- Buffenoir, Marc: *See*—
Karinth, Pierre; Buffenoir, Marc; and Belot, Dominique, 5,587,283, Cl. 431-10.000.
- Buis, Edwin J.: *See*—
Heeren, Theodorus A. G.; and Buis, Edwin J., 5,587,779, Cl. 355-271.000.
- Bull, James R.; Fritzmeier, Karl-Heinrich; and Hegele-Hartung, Christa, to Schering Aktiengesellschaft. 15,15-dialkyl-substituted derivatives of estradiol, 5,587,496, Cl. 552-629.000.
- Bullen, George N., to Northrop Grumman Corporation. Self leveling independently programmable system, 5,587,900, Cl. 364-167.010.
- Bullock, Charles E.; and Juga, Douglas L., to A. L. Hansen Mfg. Co. Locking handle, 5,586,459, Cl. 70-224.000.
- Bulow, Martin; Dao, Loc; and Fitch, Frank R., to BOC Group, Inc., The. Removal of carbon dioxide from gas streams, 5,587,003, Cl. 95-123.000.
- Bundy Corporation: *See*—
Kalahashy, Gopichand; and Zinke, James R., II, 5,586,792, Cl. 285-319.000.
- Burchfield, Mark E., to Cyrix Corporation. Sense amplifier slew circuitry, 5,587,666, Cl. 326-17.000.
- Burguera, Bartolome; and Stanzak, Richard K. Disappearing ink marking system, 5,586,501, Cl. 104-368.000.
- Burk, Robert M., to Allergan. Cyclopentane(ene)heptenoic or heptanoic acids and derivatives thereof useful as therapeutic agents, 5,587,391, Cl. 514-357.000.
- Burke, James A.; Garst, Michael E.; and Wheeler, Larry A., to Allergan. Methods for using (2-imidazolin-2-ylamino) quinoxaline derivatives, 5,587,376, Cl. 514-249.000.
- Burke, Philip J.; Dowell, Robert I.; Mauger, Anthony B.; and Springer, Caroline J., to Zeneca Limited; and Cancer Research Campaign Technology Limited. Prodrugs for antibody directed enzyme prodrug therapy, 5,587,161, Cl. 424-178.100.
- Burndy Corporation: *See*—
Eslampour, Robert A.; Shiley, Robert J., II; and Hendry, Allan W., 5,586,912, Cl. 439-620.000.
- Burns, Barbara J.; and Shuman, Ralph J., to Avery Dennison Corporation. Solid erasable marking composition, 5,587,408, Cl. 523-160.000.
- Burns, Thomas J., to H2Oil, Inc. Mobile system for the collection, separation and disposal of wet solid, oily and/or watery waste, 5,587,065, Cl. 210-104.000.
- Burroughs, Richard H., to Krueger International, Inc. Beverage container holder for a folding chair, 5,586,804, Cl. 297-188.080.
- Buschmohle, Dennis R.: *See*—
Wiand, Richard K.; and Buschmohle, Dennis R., 5,586,928, Cl. 451-177.000.
- Buse, Henry: *See*—
Focke, Heinz; and Buse, Henry, 5,586,648, Cl. 206-264.000.
- Bustos, Rafael T.; and LaPolice, George, to L&P Property Management Company. Temperature maintained food dispensing system and method, 5,586,686, Cl. 221-211.000.
- Butcher, Hayden L.; and Butcher, Karen N. Precision cut off machine, 5,586,929, Cl. 451-213.000.
- Butcher, Karen N.: *See*—
Butcher, Hayden L.; and Butcher, Karen N., 5,586,929, Cl. 451-213.000.
- Butterfield, Ted: *See*—
Chen, Shikui; and Butterfield, Ted, 5,586,723, Cl. 239-102.200.
- Buuck, David C.: *See*—
Price, Noah M.; Takahashi, Duane M. P.; and Buuck, David C., 5,587,887, Cl. 361-794.000.
- Buzzetti, Franco; Fustinoni, Silvia; Brasca, Maria G.; and Penco, Sergio, to Farmitalia Carlo Erba S.r.l. Arylidene-heterocyclic derivatives and process for their preparation, 5,587,385, Cl. 514-309.000.
- BW1 KartidgPak Co.: *See*—
Hawkins, Christopher J., 5,586,642, Cl. 198-803.110.
- BYK Gulden Lomberg Chemische Fabrik GmbH: *See*—
Kohl, Bernhard; Senn-Bilfinger, Jörg; and Grundler, Gerhard, 5,587,389, Cl. 514-338.000.
- Bynum, Kurt K., to Moeller Manufacturing Co., Inc. Fluid coupling and fastener capture device, 5,586,790, Cl. 285-89.000.
- C & D Biomedical S.A.: *See*—
Lemaire, Ivan; and Gonon, Bertrand, 5,586,973, Cl. 604-19.000.
- C.R. Bard, Inc.: *See*—
Dorsey, James H., III, 5,586,977, Cl. 604-264.000.
- Caballero Pichardo, Antonio. Device for the treatment of polluted water, 5,587,113, Cl. 261-116.000.
- Cabri, Walter; De Bernardinis, Silvia; Francalanci, Franco; and Penco, Sergio, to Farmitalia Carlo Erba S.r.l. 4-substituted anthracyclines and anthracene glycosides and the process for preparing them, 5,587,495, Cl. 552-220.000.
- CAE Investments B.V.: *See*—
Aaltonen, Frank; and Alajaaski, Timo, 5,587,077, Cl. 210-498.000.
- Caisey, Laurence; and Sturla, Jean M., to L'Oréal. Colloidal suspension based on inorganic fillers as a cosmetic composition, 5,587,170, Cl. 424-401.000.
- Cal, Yigang: *See*—
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cal, Yigang, 5,586,504, Cl. 104-282.000.
- Calmanti, Giulio: *See*—
Marzolini, Fausto; Calmanti, Giulio; and Sacchi, Gianpiero, 5,587,049, Cl. 162-40.000.
- Calton, Gary J.: *See*—
Wood, Louis L.; and Calton, Gary J., 5,587,146, Cl. 424-49.000.
- Camco International Inc.: *See*—
Pringle, Ronald E., 5,586,601, Cl. 166-212.000.
- Campardo, Giovanni; Crisenza, Giuseppe; and Dallabora, Marco, to SGS-Thomson Microelectronics S.r.l. Method of reading, erasing and programming a nonvolatile flash-EEPROM memory array using source line switching transistors, 5,587,946, Cl. 365-185.020.
- Campbell, Donald T.: *See*—
Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew; Kraft, Robert E.; and Vander Plas, Hubert A., 5,586,715, Cl. 228-248.100.
- Canada, Her Majesty the Queen in right of: *See*—
Gledde, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., 5,586,411, Cl. 47-57.600.
- Canadian Plastics Inc.: *See*—
Taveroff, Alan L., 5,586,653, Cl. 206-362.000.
- Cancer Research Campaign Technology Limited: *See*—
Burke, Philip J.; Dowell, Robert I.; Mauger, Anthony B.; and Springer, Caroline J., 5,587,161, Cl. 424-178.100.
- Canon Kabushiki Kaisha: *See*—
Fukushima, Hisashi; Takeuchi, Tatsuo; Sakoh, Harumi; and Sasanuma, Nobuatsu, 5,587,778, Cl. 355-246.000.

- Hashimoto, Hiroyuki, 5,587,587, Cl. 250-492.210.
 Iijima, Ryunosuke; and Kaneda, Kitahiro, 5,587,842, Cl. 359-698.000.
 Itoh, Yoshinori, 5,587,840, Cl. 359-686.000.
 Kasuya, Michio, 5,587,812, Cl. 358-498.000.
 Katayama, Akihiro; and Yasuda, Yasuhiko, 5,588,069, Cl. 382-166.000.
 Masaki, Junya, 5,587,644, Cl. 320-1.000.
 Mihara, Akio; and Hashimoto, Seiji, 5,587,814, Cl. 358-512.000.
 Miyamoto, Takao; and Tajima, Hisao, 5,587,817, Cl. 349-187.000.
 Miyazaki, Yuki, 5,587,800, Cl. 358-296.000.
 Nagatsuka, Osamu, 5,587,859, Cl. 360-108.000.
 Nishimura, Naoki, 5,587,974, Cl. 369-13.000.
 Noguchi, Miyoko, 5,587,834, Cl. 359-558.000.
 Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.
 Sekine, Masayoshi; Kondo, Toshiaki; and Kino, Yoshiki, 5,587,737, Cl. 348-208.000.
 Shinohara, Mahito, 5,587,738, Cl. 348-302.000.
 Sugino, Osamu; and Yamamoto, Takeo, 5,587,780, Cl. 355-274.000.
 Sugiyama, Mitsumasa, 5,588,074, Cl. 382-209.000.
 Tanaka, Yasuyuki, 5,587,744, Cl. 348-556.000.
 Togan, Takeshi; Takao, Hideaki; Asaka, Masanobu; and Kojima, Makoto, 5,587,211, Cl. 428-1.000.
 Ueda, Shigeru, 5,588,101, Cl. 395-792.000.
 Wang, Shin-Ywan, 5,588,072, Cl. 382-176.000.
 Watabe, Masahiro; Yanai, Noriyuki; Niwano, Kentaro; and Yamamoto, Akihiro, 5,587,776, Cl. 355-245.000.
 Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiko; Kugo, Harumi; Sakaizawa, Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210.000.
 Cantrell, Aron: See—
 Wittek, Robert; S., Cantrell, Aron; and Sopko, Terry, 5,586,942, Cl. 473-168.000.
 Capps, Stephen P.: See—
 Foster, Gregg S.; and Capps, Stephen P., 5,588,105, Cl. 395-326.000.
 Smith, Walter R.; and Capps, Stephen P., 5,588,141, Cl. 395-500.000.
 Cardoza, Wayne M., to Digital Equipment Corporation. Method and apparatus for synchronizing data queues in asymmetric reflective memories. 5,588,132, Cl. 395-475.000.
 Carlin, Barry W.: See—
 Dapper, Mark J.; Geile, Michael J.; and Carlin, Barry W., 5,588,022, Cl. 375-2.000.
 Carlin, Mark A.: See—
 Melver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A., 5,587,906, Cl. 364-424.045.
 Carlson, J. Martin. Article of footwear for more efficient running. 5,586,398, Cl. 36-114.000.
 Carlson, Leonard A., to Tetra Laval Holdings & Finance SA. Method and apparatus for carton sterilization. 5,587,127, Cl. 422-28.000.
 Carney, James M.: See—
 Spano, Joseph M.; Antonuccio, Robert S.; and Carney, James M., 5,587,879, Cl. 361-685.000.
 Carney, Laurann T.: See—
 Olson, Timothy L.; Carney, Laurann T.; Johnson, Gary C.; and Strom, William M., 5,587,883, Cl. 361-723.000.
 Caron, Serge: See—
 Belleville, Claude; Van Neste, Richard; Caron, Serge; Houle, Alain C.; and Thibault, Pierre, 5,587,791, Cl. 356-345.000.
 Carpenter, Barry K.: See—
 Hess, George P.; Carpenter, Barry K.; Ramesh, Doraiswamy; and Wieholdt, Raymond, 5,587,509, Cl. 560-130.000.
 Carpenter, John K. Grab sampler. 5,587,539, Cl. 73-863.520.
 Carpenter, Robert H.: See—
 McAnalley, Bill H.; Carpenter, Robert H.; and McDaniel, Harley R., 5,587,364, Cl. 514-54.000.
 Carr, Anthony H., to Unipath Limited. Magnetic stirring system. 5,586,823, Cl. 366-274.000.
 Carrano, James A., to DEC International, Inc. Milking cluster air fork. 5,586,518, Cl. 119-14.510.
 Carrier Corporation: See—
 Tollar, Paul S.; and Wood, Russell E., 5,586,450, Cl. 62-192.000.
 Yasnascoli, Donald; and Leyderman, Alexander D., 5,586,876, Cl. 418-60.000.
 Carrington Laboratories, Inc.: See—
 McAnalley, Bill H.; Carpenter, Robert H.; and McDaniel, Harley R., 5,587,364, Cl. 514-54.000.
 Carter, Barrie J.; Flotte, Terence; Afiene, Sandra; and Solow, Rikki, to United States of America, Health and Human Services. Modified adeno-associated virus vector capable of expression from a novel promoter. 5,587,308, Cl. 435-240.200.
 Carter, E. Ray. Light standard apparatus. 5,586,742, Cl. 248-545.000.
 Case, Kirt L.: See—
 Bonitati, John A.; Case, Kirt L.; Hawkins, Michael E.; and Hoag, Stephen H., 5,586,821, Cl. 366-139.000.
 Casey, Daniel T.; and Yohn, Brent D., to Whitaker Corporation. The Heater ring connector assembly. 5,586,896, Cl. 439-218.000.
 Casinovations, Inc.: See—
 Forte, Steven L.; and Sines, Randy D., 5,586,766, Cl. 273-309.000.
 Casio Computer Co., Ltd.: See—
 Sato, Minoru, 5,586,892, Cl. 439-91.000.
 Sato, Shinichiro; Akaza, Syunsuke; and Yoshino, Hiroyuki, 5,588,096, Cl. 395-135.000.
 Yoshino, Hiroyuki; and Kojo, Takashi, 5,587,823, Cl. 359-143.000.
 Casio PhoneMate, Inc.: See—
 Knuth, Stephen B.; Brown, Sanford M., III; and Karnowski, Mark J., 5,588,046, Cl. 379-67.000.
 Castello, Rinaldo: See—
 Colli, Gianluca; Franciotta, Massimo; and Castello, Rinaldo, 5,587,682, Cl. 327-357.000.
 Castiglione, Paul J.: See—
 Ondrejko, Richard T.; Castiglione, Paul J.; and Miller, Robert J., 5,586,875, Cl. 418-3.000.
 Caterpillar Inc.: See—
 Barnes, Travis E., 5,586,538, Cl. 123-446.000.
 Faletti, James J.; Feucht, Dennis D.; and Sinn, Scott G., 5,586,532, Cl. 123-321.000.
 Feucht, Dennis D., 5,586,533, Cl. 123-321.000.
 League, Richard B.; and Lay, Norman K., 5,587,929, Cl. 364-516.000.
 Mast, Donald R.; McNabb, Robert L.; and Rapp, Joseph A., 5,586,784, Cl. 280-756.000.
 Smith, James C.; and Walling, Dennis R., 5,586,744, Cl. 251-61.500.
 Yesel, Leon P.; and Kitzrow, John P., 5,587,905, Cl. 364-424.082.
 Cavalletti, Ennio: See—
 Krapcho, A. Paul; Hacker, Miles P.; Cavalletti, Ennio; and Giuliani, Ferdinando C., 5,587,382, Cl. 514-290.000.
 Cazares, Ricardo: See—
 Donsbach, Kurt W.; and Cazares, Ricardo, 5,587,191, Cl. 426-66.000.
 Cebal, S.A.: See—
 Schneider, Bernard; and Hoslet, René, 5,586,672, Cl. 215-250.000.
 Cecchi, Joseph L.; and Stevens, James E., to Princeton University. Apparatus and process for producing high density axially extending plasmas. 5,587,038, Cl. 156-345.000.
 Cement Industry Environment Consortium: See—
 Leonard, R. Leon; Bouse, Earl E.; and McQueen, Anne T., 5,586,510, Cl. 110-345.000.
 Central Sales & Service, Inc.: See—
 Deaver, Ralph, 5,586,772, Cl. 277-166.000.
 Centre International de Recherches Dermatologiques Galderma (CIRD Galderma): See—
 Reichert, Uwe; Schmidt, Rainer; and Shroot, Brahm, 5,587,367, Cl. 514-171.000.
 Chabbert, Philippe; Chateau, Alain; and Meux, Dominique, to Thomson-CSF. Process for evaluating the remaining charge in an accumulator battery. 5,587,660, Cl. 324-426.000.
 Chadfield, Garth R. Padlock with tamper alarm. 5,587,702, Cl. 340-542.000.
 Chafin, Andrew P.: See—
 Stenger-Smith, John D.; Norris, William P.; and Chafin, Andrew P., 5,587,488, Cl. 549-59.000.
 Chaguturu, Munirathnam K.: See—
 Henric, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chaguturu, Munirathnam K.; Ray, Panha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.
 Chai-Tech Corporation: See—
 Dor, Zvi; and Gershon, David, 5,587,395, Cl. 514-501.000.
 Chambers, Kenneth W.: See—
 Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
 Champagne, Yves; Paré, Claude; and Bélanger, Pierre-André, to Université Laval. Apparatus for measuring a beam width $D_{\perp}$ along a transverse direction of a laser beam and method thereof. 5,587,786, Cl. 356-121.000.
 Chan, Andrew K.; Birkner, John M.; and Chua, Hua T., to QuickLogic Corporation. Programmable application specific integrated circuit and logic cell therefor. 5,587,669, Cl. 326-38.000.
 Chandos, Ronald V.; and Foster, Robert J., to Motorola, Inc. Computer system and method for secure remote communication sessions. 5,588,059, Cl. 380-21.000.
 Chang, Bobby. Dual mode pneumatic signature feeding spring and disabling apparatus. 5,586,756, Cl. 271-11.000.
 Chang, Byung J.; and Tedesco, James M., to Kaiser Optical Systems. Laser protection window using holographic optical element and channel plates. 5,587,847, Cl. 359-890.000.
 Chang, Jeffrey C.: See—
 Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,587,351, Cl. 503-227.000.
 Chang, Jia-Hwang: See—
 Chang, Shang-De; Chang, Jia-Hwang; and Chow, Edwin, 5,587,947, Cl. 365-185.300.
 Chang, Jui Y., to Ciba-Geigy Corporation. Aromatic acids. 5,587,461, Cl. 530-404.000.
 Chang, Kuang-Yeh; Nariani, Subhash R.; and Boardman, William J., to VLSI Technology, Inc. Method of making flash memory cell. 5,587,332, Cl. 437-43.000.
 Chang, Lin-Huang: See—
 Anderson, Wayne A.; Jia, Quanxi; Yi, Junsin; and Chang, Lin-Huang, 5,587,870, Cl. 361-313.000.
 Chang, Shang-De; Chang, Jia-Hwang; and Chow, Edwin, to Rohm Corporation. Low voltage one transistor flash EEPROM cell using Fowler-Nordheim programming and erase. 5,587,947, Cl. 365-185.300.
 Chang, Ted C.: See—

- Kimberlin, Robert R.; Bodell, Steven W.; Chang, Ted C.; Diesel, Robert M.; and Barker, Scott, 5,586,606, Cl. 173-62.000.
 Channakeshu, Sandeep: See—
 Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
 Chantot, Jean-Francois: See—
 Aszodi, Jozsef; Chantot, Jean-Francois; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.
 Chao, James L.; Lee, Yu-Chen; and Gao, Chao, to HMT Technology Corporation. Lubricant composition and method. 5,587,217, Cl. 428-65.400.
 Charier, Gilles A.: See—
 Bertrand, Jean-Louis; Charier, Gilles A.; Guyonnet, Xavier J.A.; and Picard, Jean-Louis, 5,586,860, Cl. 415-115.000.
 Charnes, Michel, to A.J.C. Infrared ray emitters with catalytic burner. 5,586,877, Cl. 431-115.000.
 Chase, Walter W., to B. Bunch Company, Inc. System for delivering folded paper. 5,586,964, Cl. 493-413.000.
 Chateau, Alain: See—
 Chabbert, Philippe; Chateau, Alain; and Meux, Dominique, 5,587,660, Cl. 324-426.000.
 Chaudhary, Vijay K.: See—
 Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324.000.
 Chauvin, Jean-Michel: See—
 Jean, Pierre; and Chauvin, Jean-Michel, 5,586,513, Cl. 114-74.00A.
 Chavkin, Leonard: See—
 Mackles, Leonard; and Chavkin, Leonard, 5,587,152, Cl. 424-65.000.
 Chemetics International Company Ltd.: See—
 Twardowski, Zbigniew, 5,587,083, Cl. 210-652.000.
 Chemin, Gilles, to Framatome Connectors International. Connector having a grid for secondary locking of terminals. 5,586,918, Cl. 439-752.000.
 Chemithon Corporation, The: See—
 Hovda, Keith D., 5,587,500, Cl. 554-98.000.
 Chen, Chung-Chin: See—
 Teng, David, 5,587,893, Cl. 363-61.000.
 Chen, Jim, to Industrial Technology Research Institute. Zoom lens mechanism. 5,587,843, Cl. 359-700.000.
 Chen, Kuo-Raid G.; Misner, Raymond H.; Windham, Elbert P.; and Richardson, Bernard D., to Delaware Capital Formation, Inc. Apparatus for movement of U-shaped clips along a rail. 5,586,424, Cl. 53-138.200.
 Chen, Michael; Houde, Stephanie L.; and Seidl, Robert H., to Apple Computer, Inc. Method and apparatus for direct manipulation of 3-D objects on computer displays. 5,588,098, Cl. 395-137.000.
 Chen, Shikui; and Bunkerfield, Ted, to Spraying Systems Co. Liquid spray nozzle with liquid injector/extractor. 5,586,723, Cl. 239-102.200.
 Chen, Shyh-Lee: See—
 Yang, Su-Pei; and Chen, Shyh-Lee, 5,588,066, Cl. 381-188.000.
 Chen, Stephen L. Device and method for biomolecule purification. 5,587,061, Cl. 204-613.000.
 Cheng, Chin-chang. Foldable apparatus of a baggage cart. 5,586,775, Cl. 280-38.000.
 Cheng, Kwang-Ting; and Entrena, Luis, to Lucent Technologies, Inc. Apparatus and method for logic optimization by redundancy addition and removal. 5,587,919, Cl. 364-489.000.
 Cheng, Wilfred W. T.: See—
 Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., 5,587,183, Cl. 425-4.00R.
 Cheng, Yihao; and Duck, Gary S., to JDS Fitel Inc. Non-reciprocal optical waveguide coupling device. 5,588,078, Cl. 385-33.000.
 Cheng, Yung-Chi: See—
 Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, 5,587,362, Cl. 514-46.000.
 Cherukuri, Subraman R.; Myers, Garry L.; Battist, Gerald E.; and Fuisz, Richard C., to Fuisz Technologies Ltd. Process for forming quickly dispersing comestible unit and product therefrom. 5,587,172, Cl. 424-401.000.
 Cherukuri, Subraman R.; Yang, Robert K.; Bowles, Cecil A.; Zamudio-Tena, Jose F.; and Bhowmik, Santi R., to Fuisz Technologies Ltd. Positive hydration method of preparing confectionery and product therefrom. 5,587,198, Cl. 426-660.000.
 Chetta, Gregory E.: See—
 Aho, Wilho V., Jr.; Jones, Stephen R.; Chetta, Gregory E.; and Strout, Terry H., 5,587,068, Cl. 210-188.000.
 Cheung, Ambrose; and Fischetti, Vincent A., to Rockefeller University. The Regulation of exoprotein in *Staphylococcus aureus*. 5,587,288, Cl. 435-6.000.
 Chevallier, Yvonick; and Rabeyrin, Michel, to Rhone-Poulenc Chimie. Dispersible silica particulates and reinforcement of elastomer/rubber matrices therewith. 5,587,416, Cl. 524-492.000.
 Chi, Kuan-Mei: See—
 Chi, Kuan-Jen, 5,586,354, Cl. 12-146.0BR.
 Chi, Kuan-Jen, to Chi, Kuan-Mei. Method for forming patterns on shoe sole. 5,586,354, Cl. 12-146.0BR.
 Chi, Min-Hwa; Bergemont, Albert; and Haggag, Hosam, to National Semiconductor Corporation. Single MOS transistor active pixel sensor cell with automatic anti-blooming and wide dynamic range. 5,587,596, Cl. 257-223.000.
 Chi, Min-hwa: See—
 Bergemont, Albert; and Chi, Min-hwa, 5,587,949, Cl. 365-185.240.
 Chiarizia, Renato: See—
 Horwitz, Earl P.; and Chiarizia, Renato, 5,587,142, Cl. 423-658.500.
 Chiba, Hirotaka; Murashita, Kimitaka; and Noda, Tsugio, to Fujitsu Limited. Method and apparatus for encoding and decoding image data. 5,588,075, Cl. 382-239.000.
 Chiba, Kazuhiro: See—
 Kagawa, Shuichi; Chiba, Kazuhiro; Bamba, Noriko; and Okuno, Yoshiaki, 5,588,050, Cl. 382-167.000.
 Chiba, Syusaku: See—
 Sakaguchi, Shozo; Ikeda, Mitsuhiko; and Chiba, Syusaku, 5,586,436, Cl. 60-585.000.
 Chikami, Kunio, to Chikami, Kunio. Indicator for use in fixing a device for correcting teeth irregularities to a surface of each tooth. 5,586,881, Cl. 433-3.000.
 Chin, Leo: See—
 Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A., 5,587,767, Cl. 355-27.000.
 Chin, Richard; and Le Fevre, David, to Hughes Electronics. Thermal imaging device. 5,587,583, Cl. 250-332.000.
 Chinoiz Gyogyszert es Vegyeszeti Termekkek Gyar RT: See—
 Hajimichael, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Szekely, Istvan; Marmaros né Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
 Chipman, Brian A.: See—
 Kosakowski, Steven J.; and Chipman, Brian A., 5,586,357, Cl. 15-111.000.
 Chisso Corporation: See—
 Uchida, Manabu; Izumizawa, Takenori; and Furukawa, Kenji, 5,587,444, Cl. 526-247.000.
 Chiu, Chung-Yen, to Industrial Technology Research Institute. Division technique unified quantizer-dequantizer. 5,587,708, Cl. 341-76.000.
 Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vineski, James, to American Sigma, Inc. Refrigerated fluid sampling apparatus and method with variable volume sampling system. 5,587,926, Cl. 364-510.000.
 Cho, Hyung J., to Samsung Heavy Industries Co., Ltd. Mono-block control valve with side bypass passage. 5,586,577, Cl. 137-596.130.
 Cho, Sung-il: See—
 Moon, Byung-Joon; Cho, Sung-il; and Shin, Ki-ho, 5,587,804, Cl. 386-2.000.
 Choi, Ho I.: See—
 Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
 Choi, Hong-gyu: See—
 Rho, Hwan-chul; Choi, Hong-gyu; and Kim, Jae-myung, 5,587,201, Cl. 427-64.000.
 Choi, Hyung K.; and Xin, Zhong C. Pharmaceutical composition for prophylaxis and treatment of premature ejaculation. 5,587,167, Cl. 424-195.100.
 Choi, Tae-Young, to Samsung Electronics Co., Ltd. Optical disk drive device capable of detecting misplacement of optical disks. 5,587,982, Cl. 369-58.000.
 Choo, Chang Y.; Ran, Xiaonong; Porter, Christine A.; and Motamedi, Mohammad R., to National Semiconductor Corporation. Syntax based arithmetic coder and decoder. 5,587,710, Cl. 341-107.000.
 Chou, Kuei C., to Mei-Chi-Na Beauty International, Inc. Integrated needle for permanent pigment applicator. 5,586,473, Cl. 81-9.220.
 Chow, Edwin: See—
 Chang, Shang-De; Chang, Jia-Hwang; and Chow, Edwin, 5,587,947, Cl. 365-185.300.
 Chowdhury, Vivek, to S GS - Microelectronics Limited. Driver circuit. 5,587,676, Cl. 327-108.000.
 Choy, Nakyeon: See—
 Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
 Choy, Terence A.: See—
 Hippely, Keith A.; Wood, Larry R.; Walsh, Brian E.; and Choy, Terence A., 5,586,923, Cl. 446-14.000.
 Chraplyvy, Andrew R.; and Tkach, Robert W., to Lucent Technologies Inc. High capacity optical fiber network. 5,587,830, Cl. 359-341.000.
 Chretien, Gary L., to ReplicaTech, Inc. Replica plating device. 5,587,322, Cl. 435-309.400.
 Christean, Paul G.; and Runnec, Dennis H., to Varian Associates, Inc. X-ray tube noise and vibration reduction. 5,588,035, Cl. 378-132.000.
 Christensen, Douglas A.: See—
 Johnson, Steven A.; Wiskin, James W.; Borup, David T.; Christensen, Douglas A.; and Stenger, Frank, 5,588,032, Cl. 378-8.000.
 Christy, Kenneth G., Jr.: See—
 Scalice, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L., 5,587,287, Cl. 435-6.000.
 Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, to Univ. of GA Research Foundation; and Yale University. L-nucleosides. 5,587,362, Cl. 514-46.000.
 Chu, Jianhua: See—
 Hong, Jibi; Chu, Jianhua; and Wu, Hongxiang, 5,587,347, Cl. 501-155.000.

Chu, Peter Y.; and Tadros, Alfred H., to Space Systems/Loral, Inc. Spacecraft antenna pointing error correction. 5,587,714, Cl. 342-354.000.

Chua, Hua T.: See—
Chan, Andrew K.; Birkner, John M.; and Chua, Hua T., 5,587,669, Cl. 326-38.000.

Chung, Bu-Chin: See—
Salimian, Stamak; Delfino, Michelangelo; and Chung, Bu-Chin, 5,587,039, Cl. 156-345.000.

Chung, Chan H., to Hyundai Electronics Industries Co., Inc. First-in-first-out buffer memory. 5,587,953, Cl. 365-220.000.

Chung, Chong-sam: See—
Yoo, Jang-hwan; Rim, Kyung-hwa; Chung, Chong-sam; and Lee, Chul-woo, 5,587,976, Cl. 369-13.000.

Chung, Fa-Chih, to Juh Yih Hardware Co., Ltd. 360 degrees fast spot gluing machine for screws. 5,587,018, Cl. 118-679.000.

Chupp, John P.; Hamper, Bruce C.; and Wettach, Richard H., to Monsanto Company. Heterocyclic- and carbocyclic- substituted benzoic acids and synthesis thereof. 5,587,485, Cl. 548-377.100.

Church & Dwight Co., Inc.: See—
Domke, Todd W.; and Bergmann, Wolfgang R., 5,587,147, Cl. 424-54.000.

Ciba Corning Diagnostics Corp.: See—
Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,590, Cl. 141-386.000.

Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,673, Cl. 215-310.000.

Ciba-Geigy Corporation: See—
Chang, Jui Y., 5,587,461, Cl. 530-404.000.

Cinquemani, James, Jr.: See—
Willis, Tucker; and Cinquemani, James, Jr., 5,586,517, Cl. 116-173.000.

Cirrus Logic, Inc.: See—
Wishneusky, John A., 5,588,145, Cl. 395-555.000.

Citeq: See—
Belleville, Claude; Van Neste, Richard; Caron, Serge; Houle, Alain C.; and Thibault, Pierre, 5,587,791, Cl. 356-345.000.

Citizen Watch Co., Ltd.: See—
Sakanishi, Ei; and Kitahara, Kiyoshi, 5,587,725, Cl. 345-195.000.

Cizek, Vlastimil: See—
Meraldi, Jean-Paul; Cizek, Vlastimil; and Huston, Rima, 5,587,238, Cl. 428-357.000.

Clark, Dale A.: See—
McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeeffa, Larry A.; and McGrath, Thomas P., 5,586,887, Cl. 434-20.000.

Clark, David E.; and Dye, William M., to Baker Hughes Incorporated. Method of making an anti-bit balling well fluid using a polyol having a cloud point, and method of drilling. 5,586,608, Cl. 175-40.000.

Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., to Woodbridge Foam Corporation. Mold having vent passageways to obviate trimming of flash. 5,587,183, Cl. 425-4.000.

Clark, Steven S.: See—
Gould, Michael N.; Crowell, Pamela L.; Elson, Charles E.; and Clark, Steven S., 5,587,402, Cl. 514-729.000.

Clark, William H. H.: See—
McCamy, T. H.; and Clark, William H. H., 5,587,221, Cl. 428-96.000.

Claudius Peters Aktiengesellschaft: See—
Buchfink, Adolf, 5,586,660, Cl. 209-3.000.

Clay, Hattie S. Golf training device. 5,586,943, Cl. 473-214.000.

Cleary, Timothy J. Method of maintaining the appearance of equestrian jumps. 5,586,520, Cl. 119-705.000.

Clecin Societe: See—
Destannes, Philippe, 5,588,018, Cl. 373-72.000.

Clementini, Luciano; Galambos, Adam E.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starnic, Michael E., to Montell North America Inc. Resilient, high shrinkage propylene polymer yarn and articles made therefrom. 5,587,229, Cl. 428-224.000.

Clouse, John D., to Jana, Inc. Angular porting system and shotgun barrel equipped therewith. 5,587,549, Cl. 89-14.300.

Cloyd, Miles W.; and Ramsey, Keith M., to University of Texas System. Generation serological assay for monitoring HIV exposure. 5,587,285, Cl. 435-5.000.

Clupper, Harold E.: See—
Kremer, Frederic B., and Clupper, Harold E., 5,586,980, Cl. 606-4.000.

CMD Corporation: See—
Saindon, Stephen A.; Gietman, Peter J., Jr.; and Nagel, Nicholas J., 5,587,032, Cl. 156-64.000.

Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srisankha, Alagacane; and Riding, George A., to Biotechnology Australia Pty. Ltd.; and Commonwealth Scientific and Industrial Research Organization. DNA encoding a cell membrane glycoprotein of a tick gut. 5,587,311, Cl. 435-240.200.

Cocci, Albert: See—
Landine, Robert; De Garie, Claude; and Cocci, Albert, 5,587,080, Cl. 210-603.000.

Cocito, Carlo: See—
Helquist, Paul; and Cocito, Carlo, 5,587,475, Cl. 540-456.000.

Coen, Daniele; and Garbagnati, Carlo, to Regina Sud S.p.A. Chain conveyor having improved running features. 5,586,644, Cl. 198-853.000.

Coffey, Howard T.: See—
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cai, Yigang, 5,586,504, Cl. 104-282.000.

Cohick, Christopher B.: See—
Smith, Donald D.; Cohick, Christopher B.; and Lindsley, Herbert B., 5,587,321, Cl. 435-305.300.

Colditz, Johannes K. E., to U.S. Philips Corporation. Image intensifier tube. 5,587,621, Cl. 313-366.000.

Coleman Company, Inc.: See—
Bamber, David J.; Leung, Benson; and Leung, Vincent, 5,586,819, Cl. 362-158.000.

Colgate-Palmolive Co.: See—
Rhinesmith, Robert, 5,587,357, Cl. 510-417.000.

Colin Corporation: See—
Sakai, Hiroshi, 5,586,552, Cl. 128-633.000.

Colli, Gianluca; Franciotta, Massimo; and Castello, Rinaldo, to SGS-Thomson Microelectronics S.r.l. Four-quadrant biCMOS analog multiplier. 5,587,682, Cl. 327-357.000.

Collin, Edwin J.: See—
Kelaite, Joseph B., Jr.; and Collin, Edwin J., 5,587,570, Cl. 200-50.010.

Comeau, Alain, to Mitel Corporation. Method of preparing antimony doped semiconductor with intrinsic gettering. 5,587,325, Cl. 437-10.000.

Comer, Edward L., to BellSouth Corporation. Interactive roamer contact system for cellular mobile radiotelephone network for automatically initiating a communication with an autonomously registering cellular mobile radiotelephone. 5,588,042, Cl. 379-59.000.

Commercon, Alain: See—
Bouchard, Hervé; Bourzat, Jean-Dominique; and Commercon, Alain, 5,587,493, Cl. 549-510.000.

Commissariat A L'Energie Atomique: See—
Vieil, Eric; Bidan, Gérard; Gadelle, Andrée; and Mendes-Viegas, Maria-Fátima, 5,587,466, Cl. 536-4.100.

Commonwealth Scientific and Industrial Research Organization: See—
Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srisankha, Alagacane; and Riding, George A., 5,587,311, Cl. 435-240.200.

CompuCite Corporation: See—
Kamentsky, Louis A., 5,587,833, Cl. 359-393.000.

Computer Network Technology Corporation: See—
Misukanis, Eugene D.; Long, John H.; Dean, Lawrence A.; and Kuligowski, Douglas J., 5,588,140, Cl. 395-500.000.

Conair Corporation: See—
Lewis, Gordon A. C., 5,586,443, Cl. 62-115.000.

Concept Designs, Inc.: See—
Hsiao, Louis, 5,586,649, Cl. 206-303.000.

Concept Packaging Limited: See—
Hallam, Christopher P., 5,586,717, Cl. 229-116.100.

Concrete Coring Company: See—
Nishio, Tadashi; and Fukuda, Shuichi, 5,586,840, Cl. 405-267.000.

Conley, Richard W.; Visalli, Robert G.; and Daniels, James R., to Kerotest Manufacturing Corp. Composite polyethylene and transition valve. 5,586,749, Cl. 251-315.050.

Connors, James T., Jr.: See—
Pall, David B.; and Connors, James T., Jr., 5,586,997, Cl. 55-361.000.

Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein, Michael J.; and Wilker, Julie D., to Hewlett-Packard Company. Apparatus and method for computer-aided design of sheet metal fabricated parts. 5,587,914, Cl. 364-468.010.

Convers, Ronald J.: See—
Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Convers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., 5,587,272, Cl. 430-257.000.

Cook, P. Dan; Acevedo, Oscar L.; and Andrews, Robert S., to ISIS Pharmaceuticals, Inc. 3-deazapurines. 5,587,470, Cl. 536-23.100.

Cook, Peter: See—
Neeman, Yuval; Cook, Peter; Miller, Arnold S.; and Raman, Balan, 5,588,147, Cl. 395-601.000.

Cook, Phillip D.; and Hoke, Glenn, to Isis Pharmaceuticals, Inc. Oligonucleotides having phosphorothioate linkages of high chiral purity. 5,587,361, Cl. 514-44.000.

Cook, Phillip D.; Ramasamy, Kanda S.; and Manoharan, Muthiah, to Isis Pharmaceuticals, Inc. Oligonucleotides containing N-2 substituted purines. 5,587,469, Cl. 536-23.100.

Cook, Phillip D.; Ecker, David J.; Acevedo, Oscar L.; and Davis, Peter, to ISIS Pharmaceuticals, Inc. Method of making oligonucleotide libraries. 5,587,471, Cl. 536-25.300.

Coolbear, Bruce S.: See—
Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard E., 5,586,911, Cl. 439-607.000.

Coons, Russell L.: See—
Thonebe, Douglas A.; and Coons, Russell L., 5,586,431, Cl. 60-226.100.

Cooper Industries, Inc.: See—
Happ, Lawrence R.; Korczynski, Jacek; Bailey, William R.; and Lesesky, Alan, 5,587,890, Cl. 361-826.000.

Cooperman, Barbara; and Huff, Robert M., to Springs Industries, Inc. Two-piece shower curtain hook. 5,586,375, Cl. 24-716.000.

Copytele, Inc.: See—
Hou, Wei-Hsin; Lloyd, Thomas B.; and Schubert, Frederic E., 5,587,242, Cl. 428-402.000.

Cordonnier, Kenneth: See—
Aidlin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier, Kenneth; Ledwith, Robert; and Hencke, Robert J., 5,586,637, Cl. 198-397.000.

Cornell Research Foundation, Inc.: See—
Frechet, Jean M. J.; and Aoshima, Sadahito, 5,587,441, Cl. 526-238.000.

Frechet, Jean M. J.; and Aoshima, Sadahito, 5,587,446, Cl. 526-333.000.

Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,587,422, Cl. 524-779.000.

Henion, Jack D.; Sheppard, Robin L.; and Wachs, Timothy, 5,587,582, Cl. 250-288.000.

Hess, George P.; Carpenter, Barry K.; Ramesh, Doraiswamy; and Wieboldt, Raymond, 5,587,509, Cl. 560-130.000.

Coming Incorporated: See—
Swaroop, Srinivas H.; and Wusirika, Raja R., 5,587,137, Cl. 423-239.200.

Correll, John D. Designer-cover box. 5,586,716, Cl. 229-110.000.

Correll, Robert S., Jr.: See—
Frantz, Robert H.; Larkin, John T., Jr.; and Correll, Robert S., Jr., 5,586,907, Cl. 439-500.000.

Costrini, Gregory: See—
Keller, John H.; and Costrini, Gregory, 5,587,045, Cl. 156-627.100.

Couraud, Pierre-Olivier: See—
Nedwin, Glenn E.; Bringham, Timothy S.; and Couraud, Pierre-Olivier, 5,587,460, Cl. 530-396.000.

Courtney, Mick. Self contained plumb bob and ink line marker with line capable of automatic braking and retraction. 5,586,394, Cl. 33-394.000.

Coutoumanos, Vincent M. Medical syringe needle sheath holding device. 5,586,976, Cl. 604-192.000.

Covington, Edward A., to Dana Corporation. Barrel shaped spring center tube for a fluid filter. 5,587,066, Cl. 210-130.000.

Cowell, Michael J.: See—
Anderson, Peter L.; Cowell, Michael J.; and Hotek, Dan J., 5,586,841, Cl. 405-286.000.

Cox, James P.; and Duffy Cox, Robert W. Stabilization of biowastes. 5,587,157, Cl. 424-76.500.

Craig, Frank; Straeter, Joseph G.; and Weder, Donald E., to Southpac Trust International, Inc. Article packaging system and method. 5,586,425, Cl. 53-449.000.

Craven, Glen E.: See—
Leung, Ka-Ngo; Wells, Russell P.; and Craven, Glen E., 5,587,226, Cl. 428-210.000.

Creagan, Christopher C.: See—
Griesbach, Henry L.; Creagan, Christopher C.; and Gwaltney, Sharon W., 5,587,225, Cl. 428-198.000.

Credit Managers Association of California: See—
Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerrani, Nagender; Hackett, Roger W.; von Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.

Cribari, John C., to Valeo Engine Cooling, Inc. Heat exchanger. 5,586,600, Cl. 165-173.000.

Crisenza, Giuseppe: See—
Campardo, Giovanni; Crisenza, Giuseppe; and Dallabora, Marco, 5,587,946, Cl. 365-185.020.

Critical Dimension, Incorporated: See—
Widowik, Mark S., 5,587,156, Cl. 424-73.000.

Cronauer, William M.: See—
Lerner, Bernard; Hess, Richard W.; Cronauer, William M.; Wehrmann, Rick S.; and Kramer, James D., 5,586,708, Cl. 226-172.000.

Crooks, John E.; and Protheroe, Robert L., to AT&T Global Information Solutions Company. Portable handwritten data capture device and method of using. 5,587,560, Cl. 178-18.000.

Crosspoint Solutions, Inc.: See—
Iranmanesh, Ali, 5,587,613, Cl. 257-530.000.

Crow, Wesley B.: See—
Matsen, Marc R.; Poel, Richard J.; Crow, Wesley B.; and Nansen, David S., 5,587,098, Cl. 219-615.000.

Crowell, Pamela L.: See—
Gould, Michael N.; Crowell, Pamela L.; Elson, Charles E.; and Clark, Steven S., 5,587,402, Cl. 514-729.000.

Crown Equipment Corporation: See—
Dammeyer, Ned E.; Fullenkamp, Todd M.; and Stanimen, Harold A., 5,586,620, Cl. 187-227.000.

CSSEM Centre Suisse d'Electronique et de Microtechnique SA: See—
Venier, Philippe; Debergh, Patrick; and Arreguit, Xavier, 5,587,580, Cl. 250-206.100.

Cullen, Thomas G.: See—
Henrie, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chagaturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.

Cummins Engine Company, Inc.: See—
Vittorio, David A., 5,586,531, Cl. 123-320.000.

Cuneo, Gregory S. Clip-on computer disc holder. 5,586,741, Cl. 248-229.260.

Curci, Michèle; Mieloszynski, Jean-Luc; and Paquer, Daniel, to ILLF Atochem S.A. (Meth) acrylic compounds, process for their preparation and their application to the synthesis of new polymers. 5,587,499, Cl. 554-85.000.

Curcuta, Victor; Alexander, Dennis R.; Deangelis, Robert J.; and Robertson, Brian W., to University of Nebraska, Board of Regents of the, Method of bonding metal to a non-metal substrate. 5,586,714, Cl. 228-122.100.

Curry, Stephen M.: See—

Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.

Curvin, Daniel R., to Arizona Chemical Company. Modified dicyclopentadiene resins. 5,587,007, Cl. 106-23.000.

Custom Graphics: See—
Fellner, Alan E., 5,587,037, Cl. 156-231.000.

Cutts, Richard W., Jr.; Banton, Randall G.; and Jewett, Douglas E., to Tandem Computers, Incorporated. Fault-tolerant computer system having switchable I/O bus interface modules. 5,588,111, Cl. 395-182.070.

Cyber Computer Products Corporation: See—
Asprey, Robert R., 5,587,824, Cl. 359-154.000.

Cypress Services, Inc.: See—
Dorosz, Daniel E. D., 5,586,611, Cl. 175-369.000.

Cypros Pharmaceutical Corporation: See—
Fox, Anthony W., 5,587,397, Cl. 514-557.000.

Cyril Corporation: See—
Burchfield, Mark E., 5,587,666, Cl. 326-17.000.

Daewoo Electronics Co., Ltd.: See—
Kim, Sang-Ho, 5,587,741, Cl. 348-416.000.

Lee, Dong-Hee, 5,586,818, Cl. 353-101.000.

Dahn, Jeffery R.: See—
Wilson, Alfred M.; and Dahn, Jeffery R., 5,587,256, Cl. 429-218.000.

Dai Nippon Printing Co. Ltd.: See—
Iijima, Masayuki; Dantani, Kyoji; Obata, Hiroyuki; Matsuo, Makoto; Utsuni, Minoru; and Take, Seiji, 5,587,264, Cl. 430-57.000.

Okabe, Masato, 5,587,987, Cl. 369-126.000.

Tamura, Yoshihiko; and Tsuchiya, Mitsuru, 5,587,352, Cl. 503-227.000.

Daiel Chemical Industries, Ltd.: See—
Murakami, Tatsushi; and Ichida, Akito, 5,587,467, Cl. 536-18.500.

Daiichi Pharmaceutical Co., Ltd.: See—
Hayakawa, Isao; and Kimura, Youichi, 5,587,386, Cl. 514-312.000.

Daijin Industries, Ltd.: See—
Yamana, Masayuki; and Isogan, Tomohiro, 5,587,110, Cl. 252-511.000.

Dailey, Earl J.: See—
Kissel, James L.; Dailey, Earl J.; and Dolan, Daniel E., 5,586,849, Cl. 410-10.000.

Daimler-Benz AG: See—
Boegner, Walter; Kraemer, Michael; Krutzsch, Bernd; Wenninger, Guenter; Wirbelreit, Friedrich; and Weisweiler, Werner, 5,586,433, Cl. 60-274.000.

König, Ulf; Grubbe, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-31.000.

Daimler-Benz Aktiengesellschaft: See—
Neuhand, Horst; Korec, Jacek; Stein, Erhart; and Silber, Dieter, 5,587,595, Cl. 257-141.000.

Dainichi Kinzoku Kogyo Co., Ltd.: See—
Hoshino, Teruo, 5,586,478, Cl. 82-133.000.

Daiss, John L.: See—
Scalice, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L., 5,587,287, Cl. 435-6.000.

Daiwa Seiko, Inc.: See—
Aizawa, Yutichi, 5,586,949, Cl. 473-345.000.

Dake, Ingo: See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrachala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Manzac, Olivier, 5,587,412, Cl. 524-47.000.

Dallabora, Marco: See—
Campardo, Giovanni; Crisenza, Giuseppe; and Dallabora, Marco, 5,587,946, Cl. 365-185.020.

Dallas Semiconductor Corporation: See—
Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.

D'Amato, Antonio, to Seda S.p.A. Squeezable receptacle having a cut-out portion in an end section thereof. 5,586,689, Cl. 222-92.000.

D'Ambrienes, Solange G.: See—
Aszodi, Jozsef; Chantot, Jean-François; Fauveau, Patrick; D'Ambrienes, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.

Dammeyer, Ned E.; Fullenkamp, Todd M.; and Stammen, Harold A., to Crown Equipment Corporation. Remote viewing apparatus for fork lift trucks. 5,586,620, Cl. 187-227.000.

Dana Corporation: See—
Covington, Edward A., 5,587,066, Cl. 210-130.000.

Danda, Sylvain; Kvant, Magnus; and Pescher, Yvette, to Kernthone France. Purification of aqueous media using aluminum polychloride/iron compound/salt-based coagulant compositions. 5,587,086, Cl. 210-723.000.

Danelski, Darin L.: See—
Dorner, Wolfgang C.; Hosh, Michael A.; Danelski, Darin L.; and Remsing, David A., 5,586,685, Cl. 221-197.000.

Danielewski, Marek: See—
Hashimoto, Koji; Habazaki, Hiroki; Mrowec, Stanislaw; and Danielewski, Marek, 5,587,028, Cl. 148-403.000.

Daniels, James R.: See—
Conley, Richard W.; Visalli, Robert G.; and Daniels, James R., 5,586,749, Cl. 251-315.050.

Danner, Michael. Centrifugal pump having a slidable gate. 5,586,862, Cl. 415-146.000.

- Dannevang, Flemming, to Haldor Topsøe A/S. Process for decomposing ammonia in an off-gas. 5,587,134, Cl. 423-237.000.
- Danstrom, Eric J., to SGS-Thomson Microelectronics, Inc. Comparator with built-in hysteresis. 5,587,674, Cl. 327-67.000.
- Dantani, Kyoji. *See*—
Iijima, Masayuki; Dantani, Kyoji; Ohata, Hiroyuki; Matsuo, Makoto; Utsun, Minoru, and Take, Seiji, 5,587,264, Cl. 430-57.000.
- Dao, Loe. *See*—
Bulow, Martin; Dao, Loe; and Fitch, Frank R., 5,587,003, Cl. 95-123.000.
- Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., to International Business Machines Corporation. Advanced parallel processor including advanced support hardware. 5,588,152, Cl. 395-800.000.
- Dapper, Mark J.; Geile, Michael J.; and Carlin, Barry W., to Xetron Corp. Method and apparatus for AM compatible digital broadcasting. 5,588,022, Cl. 375-216.000.
- Da Silva Marques, Carlos A. Musical instrument. 5,587,543, Cl. 84-411.000.
- Dataproducts Corporation. *See*—
Liguori, Thomas A., 5,587,811, Cl. 358-456.000.
- Dattagupta, Nambhushani, and Kocher, Jürgen, to Bayer Corporation. Coumarin-labeled nucleoside 5'-triphosphates. 5,587,472, Cl. 536-26.200.
- Dauderman, Shelley L.; McWilliams, Linda C.; Nair, Hari A.; and Staud, Gary G., to Procter & Gamble Company, The. Thickened, highly aqueous, cost effective liquid detergent compositions. 5,587,356, Cl. 510-320.000.
- Daugherty, Thomas H. *See*—
Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Iyla R.; and Stroebecker, Cary A., Sr., 5,588,051, Cl. 379-243.000.
- Dausch, Mark E. *See*—
Smith, John M.; Schneider, David A.; Dausch, Mark E.; and Whipple, Walter, III, 5,586,567, Cl. 134-57.000.
- Dave, Pankaj J. *See*—
Patel, Mahendra R.; Reddy, Kasireddy C.; and Dave, Pankaj J., 5,587,377, Cl. 514-253.000.
- Davenport, Charles I. Lock for slide bolt latches. 5,586,793, Cl. 292-67.000.
- Davenport, John M. *See*—
Parham, Thomas G.; Dynns, Frederick W.; Gunter, Carl V.; Davenport, John M.; Goltz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic E.; Allen, Gary R.; Duffy, Mark E.; and Hämeler, Richard L., 5,587,626, Cl. 313-634.000.
- Davenport, Ricky W. Fuels blending system and method of using. 5,586,729, Cl. 241-21.000.
- David Sarnoff Research Center, Inc. *See*—
Hseuh, Fu-Lung; Ipri, Alfred C.; Dolny, Gary M.; and Stewart, Roger G., 5,587,329, Cl. 437-40.000.
- Strolle, Christopher H.; Jaffe, Steven T.; and Lyons, Paul W., 5,588,025, Cl. 375-316.000.
- Davidson Texton Inc. *See*—
Poe, Charles A., 5,586,853, Cl. 411-372.000.
- Davis, Mark E. Method and recording for producing sounds and messages to achieve alpha and theta brainwave states and positive emotional states in humans. 5,586,967, Cl. 600-28.000.
- Davis, Peter. *See*—
Cook, Phillip D.; Ecker, David J.; Acevedo, Oscar L.; and Davis, Peter, 5,587,471, Cl. 536-25.300.
- Davis, Steve. *See*—
Stupek, Richard A., Jr.; Shaffer, David S.; Jones, Curtis R.; Davis, Steve; and Justice, William D., Jr., 5,588,143, Cl. 395-500.000.
- Davis, William L. *See*—
Manson, Larry J.; Sember, Chris A.; and Davis, William L., 5,587,642, Cl. 318-812.000.
- Dawes, Paul J.; Krulvitch, Thomas A.; and Krulvitch, Peter A. Adjustable snowboard boot binding apparatus. 5,586,779, Cl. 280-14.200.
- Dawson, David. *See*—
Pfeiffermaier, Heinz; Jibkebeck, Philip; Prime, Brian; and Dawson, David, 5,587,713, Cl. 342-70.000.
- Dawson, Ted M. *See*—
Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H., 5,587,384, Cl. 514-309.000.
- Dawson, Valina L. *See*—
Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H., 5,587,384, Cl. 514-309.000.
- Daynes, Raymond A., and Araneo, Barbara A., to University of Utah Research Foundation. Methods for preventing progressive tissue necrosis, reperfusion injury, bacterial translocation and adult respiratory distress syndrome. 5,587,369, Cl. 514-178.000.
- Dayton Walther Corporation. *See*—
Julow, Jay K.; DeRegnaucourt, Robert A.; and Hall, John C., 5,586,625, Cl. 188-218.000.
- Dean, Lawrence A. *See*—
Miskakis, Eugene D.; Long, John H.; Dean, Lawrence A.; and Kuligowski, Douglas J., 5,588,140, Cl. 395-500.000.
- Deangelis, Robert J. *See*—
Curcuta, Victor; Alexander, Dennis R.; Deangelis, Robert J.; and Robertson, Brian W., 5,586,714, Cl. 228-122.100.
- Dearth, Glenn, and Bissett, Thomas D., to Digital Equipment Corporation. DMA controller for memory scrubbing. 5,588,112, Cl. 395-182.070.
- Deaver, Ralph, to Central Sales & Service, Inc. Retrofit gasket assembly for railroad hopper having reinforcing portions. 5,586,772, Cl. 277-166.000.
- Debergh, Patrick. *See*—
Venier, Philippe; Debergh, Patrick; and Arreguit, Xavier, 5,587,580, Cl. 250-206.100.
- De Bernardinis, Silvia. *See*—
Cabri, Walter; De Bernardinis, Silvia; Francalanci, Franco; and Penco, Sergio, 5,587,495, Cl. 552-220.000.
- De Bono, Edward, and Kanbar, Maurice S. Siamese case for storing and playing two games. 5,586,763, Cl. 273-285.000.
- De Borst, Eric. *See*—
Babey, Jacques; Salmon, Brian; De Borst, Eric; and Tallier, Bernard, 5,586,565, Cl. 131-84.200.
- DEC International, Inc. *See*—
Carrano, James A., 5,586,518, Cl. 119-14.510.
- Deere & Company. *See*—
Wanie, Lee J., 5,586,955, Cl. 477-99.000.
- Deheuw, Geert; Janssens, Wilhelmus, and Vanmaele, Luc, to Agla-Gevaert N.V. Thermal transfer imaging process. 5,587,268, Cl. 430-200.000.
- Deheuw, Geert, to Agla-Gevaert N.V. Thermal transfer imaging process and donor element for use therein. 5,587,269, Cl. 430-203.000.
- Deheuw, Geert. *See*—
Janssens, Wilhelmus; Van den Bogaert, Jan; Vanmaele, Luc; and Deheuw, Geert, 5,587,270, Cl. 430-203.000.
- DeLandre, André; Dubois, Michel; Forestier, Serge; and Richard, Hervé, to L'Oréal. Photostable cosmetic screening composition containing a UV-A screening agent and an alkyl β , β -diphenylacrylate or (cyano- β , β -diphenylacrylate. 5,587,150, Cl. 424-59.000.
- DeForest, Marvin. *See*—
Riggle, C. M.; and DeForest, Marvin, 5,588,030, Cl. 375-368.000.
- De Garie, Claude. *See*—
Landine, Robert; De Garie, Claude; and Cocci, Albert, 5,587,080, Cl. 210-603.000.
- Degroot, Marc. *See*—
Levitt, David A.; Degroot, Marc; and Lanier, Jaron Z., 5,587,936, Cl. 364-578.000.
- De Haen, Christoph; Uggeri, Fulvio; Gazzotti, Ornella; and Brocchetta, Marino, to Dibra S.p.A. Tetraolopyrrole derivatives as contrast medium and as antiseptic. 5,587,487, Cl. 548-561.000.
- Deierling, Kevin E. *See*—
Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.
- de Jong, Johannes. *See*—
Winter, Ari; and de Jong, Johannes, 5,587,567, Cl. 187-395.000.
- DeKoning, Rodney A.; Humlcek, Donald R.; and Johnson, Max L., to Symbios Logic Inc. Method for transferring data between two devices that insures data recovery in the event of a fault. 5,588,110, Cl. 395-182.030.
- De Latorcade, Vincent, to L'Oréal. Liquid dispenser comprising a dispensing valve and a push button. 5,586,693, Cl. 222-182.000.
- Delaware Capital Formation, Inc. *See*—
Chen, Kuo-Raid G.; Misner, Raymond H.; Windham, Elbert P.; and Richardson, Bernard D., 5,586,424, Cl. 53-138.200.
- Delco Electronics Corp. *See*—
Barrett, Alfred H., 5,587,892, Cl. 363-44.000.
- Del Fabbro, Giorgio, and Del Fabbro, Marcello, to M.E.P. Macchine Elettromeccaniche Piegatrici SpA. Device to compensate the elongation of at least two wire rods or round bars, which is associated with a drawing assembly. 5,586,709, Cl. 226-177.000.
- Del Fabbro, Marcello. *See*—
Del Fabbro, Giorgio; and Del Fabbro, Marcello, 5,586,709, Cl. 226-177.000.
- Delfino, Michelangelo. *See*—
Salimian, Stamak; Delfino, Michelangelo; and Chung, Bu-Chin, 5,587,039, Cl. 156-445.000.
- Dell USA, L.P. *See*—
Swamy, N. Deepak, 5,587,885, Cl. 361-777.000.
- Delby, Fredrik, and Föster, Per Åke, to Aktiebolaget Electrolux. Box constituting vacuum insulated walls of a refrigerator or freezer cabinet. 5,586,680, Cl. 220-467.000.
- Del Negro, James; Brown, Russell; and Avery, Roger, to Anphenol Corporation. Clamp nut retaining feature. 5,586,910, Cl. 439-584.000.
- Delta and Pine Land Company. *See*—
Waddington, James B., 5,586,412, Cl. 47-58.000.
- Delta Kogyo Co., Ltd. *See*—
Tsubota, Kazuaki; and Yamamoto, Takeshi, 5,586,831, Cl. 403-305.000.
- Delta Tooling Co., Ltd. *See*—
Tsubota, Kazuaki; and Yamamoto, Takeshi, 5,586,831, Cl. 403-305.000.
- DeLuca, Hector F.; Schmoes, Heinrich K.; Perlman, Kato L.; Siemski, Rafal R.; and Prühl, Jean M., to Wisconsin Alumni Research Foundation. 19-nor-vitamin D compounds. 5,587,497, Cl. 552-653.000.
- De Marco, Doreano, to Procond Elettronica S.p.A. Air purifier apparatus with an electrostatic filter. 5,587,005, Cl. 96-26.000.
- Demoise, Thomas J. *See*—
Kanjo, Wajih; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7.000.
- Dengg, Franz. *See*—
Gantner, Gebhard; Dengg, Franz; Ofner, Peter; and Münzenberger, Herbert, 5,586,739, Cl. 248-74.100.
- Denis, Philippe; Patois, Carl; and Perron, Robert, to Rhone-Poulenc Chimie. Separation of aliphatic diacids from adipic acid admixtures thereof. 5,587,056, Cl. 203-29.000.

- Dennis, Stephen V.; and Newell, Gabe L., to Microsoft Corporation. System and method of printer handling. 5,588,095, Cl. 395-116.000.
- Dennis, Timothy A., to Harris Corporation. Composition, and method for using same, for etching metallic alloys from a substrate. 5,587,103, Cl. 252-79.300.
- Dentale, Patsy. Spring supported in-line skate. 5,586,774, Cl. 280-11.220.
- de Potzoli, Bernd. *See*—
Knühl, Klaus; Karl, Ulrich; Müller, Stefan; and de Potzoli, Bernd, 5,587,506, Cl. 560-12.000.
- Dequin, Sylvie. *See*—
Barre, Pierre; Dequin, Sylvie; and Ansanay, Virginie, 5,587,304, Cl. 435-139.000.
- DeRegnaucourt, Robert A. *See*—
Julow, Jay K.; DeRegnaucourt, Robert A.; and Hall, John C., 5,586,625, Cl. 188-218.000.
- De Riese-Meyer, Loert. *See*—
Kuhm, Peter; Schroeder, Christine; Sander, Volker; Lindener, Juergen; and De Riese-Meyer, Loert, 5,587,063, Cl. 205-173.000.
- Desai, Dhimat R.; Tayse, Louis C.; and Gideon, Richard W., to ARA Electronics Corp. Human body actuated control apparatus and system for commercial sewing machines. 5,587,634, Cl. 318-257.000.
- Deshon, Mary. *See*—
Jones, Oliver; Deshon, Mary; Ericsson, Staffan; and Flach, James, 5,587,928, Cl. 364-514.00A.
- Destannes, Philippe, to Usinor Sacilor Societe; and Clecim Societe. Metallurgical container comprising a hearth bottom electrode. 5,588,018, Cl. 373-72.000.
- Destruelle, Monika. *See*—
Klionsky, Daniel; Holzer, Helmut; and Destruelle, Monika, 5,587,290, Cl. 435-6.000.
- Detering, Greig R.; Gallick, Robert L.; and Hewell, James F. Method for the automatic insertion of removal of a calling number identification (CNID) blocking prefix from within a telephone number in a personal computer based telephone management system. 5,588,049, Cl. 379-142.000.
- Detterman, Robert E. *See*—
Lawson, Dennis L.; and Detterman, Robert E., 5,587,419, Cl. 524-527.000.
- Devlieg-Bullard, Inc. *See*—
Bahuder, Kirt M.; Joseph, Douglas A.; Pistor, Donald; and Stupica, L. Joseph, 5,586,477, Cl. 82-126.000.
- De Vries, Nadine H. C., to Du Pont de Nemours, E. I., and Company. Process for treating iron-containing sulfidic rocks and ores. 5,587,001, Cl. 75-743.000.
- Dewald, James E., Jr.; McManus, Martin P.; and McManus, Patrick W. Linkage for guiding a retractable room. 5,586,802, Cl. 296-26.000.
- De With, Peter H. N. *See*—
Bergen, Franciscus H. M.; Rotte, Jan J.; Nijssen, Stephanus J. J.; and De With, Peter H. N., 5,587,802, Cl. 386-26.000.
- Diaz, Donald R. *See*—
Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.
- Dibra S.p.A. *See*—
De Haen, Christoph; Uggeri, Fulvio; Gazzotti, Ornella; and Brocchetta, Marino, 5,587,487, Cl. 548-561.000.
- Dickie, Neil M.; and Hudson, Steven M., to Flight Refuelling Limited. Data transfer. 5,587,707, Cl. 340-870.090.
- Dickinson, Ian J.; Eichberger, Horst; Messaros, David W.; and Walter, Hans-Dieter, to Hewlett-Packard Company. User interface for a remote diagnostic device. 5,588,109, Cl. 395-326.000.
- Diederiks, Everett G., Jr.; and Puett, Edwin E., Jr., to Anser Tool & Machinery Technologies, Inc. Attachment for pneumatic cleaning device. 5,586,360, Cl. 15-410.000.
- Dieffenderfer, James W. *See*—
Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- Diehl, Matthew D., to Martin Marietta Corporation. Combination ball valve and pressure relief valve assembly. 5,586,579, Cl. 137-614.170.
- Dierke, Gregg. *See*—
Maturi, Greg; and Dierke, Gregg, 5,588,029, Cl. 375-364.000.
- Diesel, Robert M. *See*—
Kimberlin, Robert R.; Bodell, Steven W.; Chang, Ted C.; Diesel, Robert M.; and Barker, Scott, 5,586,606, Cl. 173-62.000.
- Dietrich, Harry. *See*—
König, Ulf; Gruhle, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-31.000.
- Dietrich, William A. *See*—
Lofgren, Dan M.; and Dietrich, William A., 5,588,044, Cl. 379-67.000.
- Digital Equipment Corporation. *See*—
Cardoza, Wayne M., 5,588,132, Cl. 395-475.000.
- Dearth, Glenn, and Bissett, Thomas D., 5,588,112, Cl. 395-182.070.
- Rosich, Mitchell N.; and Lippitt, William L., 5,587,964, Cl. 365-238.500.
- Dijkman, Eise C., to U.S. Philips Corporation. Integrated circuit having an output stage with a Miller capacitor. 5,587,678, Cl. 327-108.000.
- Dillehay, David R.; and Turner, David W., to Thiokol Corporation. Infrared illuminating composition. 5,587,552, Cl. 149-19.500.
- Diller, Barbara J. *See*—
Diller, Robert J.; and Diller, Barbara J., 5,586,491, Cl. 99-450.000.
- Diller, Robert J.; and Diller, Barbara J. Disposable barbecue grill shield. 5,586,491, Cl. 99-450.000.
- DiMaio, Anthony J., to Quantum Chemical Corporation. Polymer supported catalyst for olefin polymerization. 5,587,439, Cl. 526-142.000.
- Dimond, Randall L. *See*—
Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stebnitz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.
- Dinc, Osman S. *See*—
Bagepalli, Bharat S.; and Dinc, Osman S., 5,586,773, Cl. 277-167.500.
- Dini, Christophe. *See*—
Aszodi, Jozsef; Chantot, Jean-Francois; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.
- Dinkelaker, Albrecht. *See*—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrachala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- DiNorcia, Anthony, Jr. *See*—
DiNorcia, Anthony, Jr.; and DiNorcia, Donato L., 5,586,925, Cl. 451-35.000.
- DiNorcia, Anthony, Sr.; DiNorcia, Anthony, Jr.; and DiNorcia, Donato L., to DiNorcia, Donato; DiNorcia, Jr., Anthony; and DiNorcia, Sr., Anthony. Apparatus and method for processing marble. 5,586,925, Cl. 451-35.000.
- DiNorcia, Donato. *See*—
DiNorcia, Anthony, Sr.; DiNorcia, Anthony, Jr.; and DiNorcia, Donato L., 5,586,925, Cl. 451-35.000.
- DiNorcia, Donato L. *See*—
DiNorcia, Anthony, Sr.; DiNorcia, Anthony, Jr.; and DiNorcia, Donato L., 5,586,925, Cl. 451-35.000.
- DiPaolo, Nunzio; and Ferguson, Daniel J., to International Business Machines Corporation. Process and apparatus for contamination-free processing of semiconductor parts. 5,587,095, Cl. 219-388.000.
- Dipti Kr. Datta. *See*—
Yazici, Muammer; and Richarz, Werner, 5,587,563, Cl. 181-224.000.
- Director-General of Industrial Science and Technology. *See*—
Ohshima, Satoshi; Yumura, Motoo; Kuriki, Yasunori; Uchida, Kunio; and Ikazaki, Fumikazu, 5,587,141, Cl. 423-445.00B.
- Director General of National Agriculture Research Center, Ministry of Agriculture, Forestry and Fisheries. *See*—
Horigane, Akira; Matsukura, Ushio; and Kamio, Masayoshi, 5,587,298, Cl. 435-41.000.
- Dirt, Josef. Process for encoding and transmitting information. 5,587,797, Cl. 358-261.100.
- DiSalvo, Francis J. *See*—
Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,587,422, Cl. 524-779.000.
- Discovision Associates. *See*—
Bailey, Jack H., 5,587,983, Cl. 369-59.000.
- Gregg, David P., 5,587,993, Cl. 369-291.000.
- DJS&T Limited Partnership. *See*—
Stern, Donald J.; and Treleven, Dan, 5,587,102, Cl. 252-62.540.
- Döbbling, Klaus; Samner, Johannes; and Steinbach, Christian, to ABB Research Ltd. Premixing burner. 5,586,878, Cl. 431-351.000.
- Dohanich, Stephen L. *See*—
Brooks, Jeffrey S.; and Dohanich, Stephen L., 5,587,935, Cl. 364-578.000.
- Doi, Yoshitada. *See*—
Fukano, Yoshihiro; and Doi, Yoshitada, 5,586,570, Cl. 137-271.000.
- Dolait, Jean-Pierre. *See*—
Hashimoto, Masashi; Frantz, Gene A.; Moravec, John V.; and Dolait, Jean-Pierre, 5,587,962, Cl. 365-230.090.
- Dolan, Daniel E. *See*—
Kissel, James L.; Dailey, Earl J.; and Dolan, Daniel E., 5,586,849, Cl. 410-10.000.
- Dolbear, Keith D.; Beamond, Trevor W.; and Schofield, Kerry G., to Ferodo Limited and British Railways Board. Brakes. 5,586,626, Cl. 188-250.00B.
- Dolby Laboratories Licensing Corporation. *See*—
Goldberg, Paul R.; and Richards, Martin J., 5,587,749, Cl. 352-27.000.
- Dolgas, Patrick A.; Walton, Ballard E.; and Staton, Larry E., to Globe Products Inc. Stator winding method. 5,586,383, Cl. 29-596.000.
- Dolle, Volker. *See*—
Winter, Andreas; Dolle, Volker; and Spaleck, Walter, 5,587,501, Cl. 556-53.000.
- Dölling, Uwe. *See*—
Adam, Paul; Tillmann, Heinz; deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dölling, Uwe, 5,586,783, Cl. 280-737.000.
- Dolny, Gary M. *See*—
Hseuh, Fu-Lung; Ipri, Alfred C.; Dolny, Gary M.; and Stewart, Roger G., 5,587,329, Cl. 437-40.000.
- Dombrowski, Larry A.; Goldsmith, Daniel S.; Goldsmith, Judith; and Goldsmith, Walter J. Wall safe. 5,586,934, Cl. 454-309.000.
- Domke, Todd W.; and Bergmann, Wolfgang R., to Church & Dwight Co., Inc. Aqueous zinc-polyamide complex solution. 5,587,147, Cl. 424-54.000.
- Donachie, William, to British Technology Group Limited. Vaccine against Pasteurella. 5,587,166, Cl. 424-255.100.
- Donnelly Corporation. *See*—
Agrawal, Raj K.; Lynam, Niall R.; and Galer, James K., 5,587,236, Cl. 428-334.000.
- Donner, Hans-Christian. *See*—

- Neumaier, Anton, and Donner, Hans Christian, 5,586,607, Cl. 173-117,000.
- Dono, Shigeru: *See—*
Nakatani, Takuya; Abe, Mitsutaka; Dono, Shigeru, and Urano, Youji, 5,586,387, Cl. 29-703,000.
- Donsbach, Kurt W.; and Cazares, Ricardo, to Kim, Chang S., Donsbach, Kurt W.; and Cazares, Ricardo: Process for making highly oxygenated drinking water and drinking water made by the process, 5,587,191, Cl. 426-66,000.
- Doolley, Kevin A., to Pratt & Whitney Canada Inc.: Continuous plasma ignition system, 5,587,630, Cl. 315-209,000.
- Dopp, Robert B., Oltman, John E., and Passamti, Joseph L., to Rayovac Corporation: Metal-air cathode and cell having a hardened current collecting substrate, 5,587,259, Cl. 429-233,000.
- Dori, Zvi; and Gershon, David, to Chai-Tech Corporation: Metallo-organic cobalt compounds and uses thereof, 5,587,395, Cl. 514-501,000.
- Dorius, Lee K.; and Samuelson, Laurence S., to International Business Machines Corporation: Negative pressure slider with optimized leading pocket for profile control, 5,587,858, Cl. 360-103,000.
- Dorner Mfg. Corp.: *See—*
Dorner, Wolfgang C.; Hosch, Michael A.; Danelski, Darr L.; and Remsing, David A., 5,586,685, Cl. 221-197,000.
- Dorner, Wolfgang C.; Hosch, Michael A.; Danelski, Darr L.; and Remsing, David A., to Dorner Mfg. Corp.: Apparatus for dispensing articles, 5,586,685, Cl. 221-197,000.
- Dorner GmbH: *See—*
Spueh, Richard; Schaefer, Wolfgang; Stolten, Detlef, and Fandel, Marco, 5,587,251, Cl. 429-33,000.
- Dorosz, Daniel E. D., to Cypress Services, Inc.: Drill bit having dual split bushings for cutter support and retention, 5,586,611, Cl. 175-369,000.
- Dorsey, James H., III, to C.R. Bard, Inc.: Quick disconnect fitting for coupling interchangeable probe tip to laparoscopic instrument, 5,586,977, Cl. 604-264,000.
- Dorzbach-Lange, Cornelia: *See—*
Pohner, Klaus; Weber, Rainer; Dorzbach-Lange, Cornelia; Haida, Reinhard; and Moretto, Hans-Heinrich, 5,587,513, Cl. 564-84,000.
- Dosch, Joseph: *See—*
Dosch, Thomas J.; and Dosch, Joseph, 5,586,940, Cl. 473-140,000.
- Dosch, Thomas J.; and Dosch, Joseph: Golf practice apparatus, 5,586,940, Cl. 473-140,000.
- Dotta, James C.: *See—*
Wanek, Ronald G.; Dotta, James C.; Konkil, Brian, and Herold, Duane, 5,586,830, Cl. 403-59,000.
- Doupe, Thomas H.: *See—*
Bobo, Donald E., Jr.; and Doupe, Thomas H., 5,586,555, Cl. 128-672,000.
- Dow Chemical Company, The: *See—*
Athey, Phillip S.; and Kiefer, Garry E., 5,587,451, Cl. 528-345,000.
- Dow, Randall P.: *See—*
Jevce, John M.; and Dow, Randall P., 5,587,025, Cl. 148-274,000.
- Dowell, Robert I.: *See—*
Burke, Philip J.; Dowell, Robert I.; Mauger, Anthony B.; and Springer, Caroline J., 5,587,161, Cl. 424-178,100.
- Dowell, Teresa J.; Newell, Gerald P.; and Zeffren, Eugene, to Helene Curtis, Inc.: Shampoo compositions and suspending agent therefor, 5,587,154, Cl. 424-70,110.
- Downey, Wayne F., Jr.: Water decontamination apparatus using peroxide photolysis ionizer, 5,587,069, Cl. 210-192,000.
- Doyle, Richard W.: *See—*
McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeafra, Larry A.; and McGrath, Thomas P., 5,586,887, Cl. 434-20,000.
- Dr. Karl Thomae GmbH: *See—*
Narr, Berthold; Haeu, Norbert; Van Meel, Jacques; Wienen, Wolfgang; Entzerth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381,000.
- Dragoset, William H., Jr., and Jericevic, Zeljko, to Western Atlas International, Inc.: Surface multiple attenuation via eigenvalue decomposition, 5,587,965, Cl. 367-24,000.
- Dreishach, Lisa B.: *See—*
Pierschbacher, Michael D.; Honsik, Cyril J.; and Dreishach, Lisa B., 5,587,456, Cl. 530-326,000.
- Dreishach, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoenel, Michael; and Stengel-Rutkowski, Bernhard, to Hoechst Aktiengesellschaft: Curing agents for aqueous epoxy resin dispersions, 5,587,409, Cl. 523-404,000.
- Dresser Rand Company: *See—*
Sine, Andrew L., 5,586,483, Cl. 92-255,000.
- DSM N.V.: *See—*
Koning, Cornelis E.; and Teuwen, Lillian M. J., 5,587,452, Cl. 528-350,000.
- Du Pont de Nemours, E. I., and Company: *See—*
De Vries, Nadine H. C., 5,587,001, Cl. 75-743,000.
- Gridnev, Alexei A.; and Itiel, Steven D., 5,587,431, Cl. 525-269,000.
- Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Conyers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., 5,587,272, Cl. 430-257,000.
- Johnson, Melvin H.; and Willis, Frank M., 5,587,116, Cl. 264-1,250.
- Odum, James M., 5,587,317, Cl. 435-262,500.
- Talkowski, Charles J., 5,587,430, Cl. 525-196,000.
- Dube, William P.: *See—*
McColekey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., 5,587,534, Cl. 73-623,000.
- Dubois, Michel: *See—*
Deflandre, André; Dubois, Michel; Forestier, Serge; and Richard, Hervé, 5,587,150, Cl. 424-59,000.
- Duck, Gary S.: *See—*
Cheng, Yihao; and Duck, Gary S., 5,588,078, Cl. 385-33,000.
- Duffy, Mark E.: *See—*
Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634,000.
- Duffy Cox, Robert W.: *See—*
Cox, James P.; and Duffy Cox, Robert W., 5,587,157, Cl. 424-76,500.
- Dugstad, Harald: *See—*
Almén, Torsten; Berg, Arne; Dugstad, Harald; Klaveness, Jo; Kraurwurst, Klaus D.; and Rongved, Pål, 5,587,144, Cl. 424-9,361.
- Duke University: *See—*
Kane, William H.; and Ortel, Thomas L., 5,587,310, Cl. 435-240,200.
- Dumont, Charles, Universal merchandise tag, 5,587,703, Cl. 340-572,000.
- Duncan, William M., Jr., to Integrity Industries, Inc.: Drilling fluid and drilling fluid additive, 5,587,354, Cl. 507-137,000.
- Dunfield, John C.; and Oveyssi, Kamran, to Seagate Technology, Inc.: Integrated passive magnetic bearing system and spindle magnet for use in an axial magnet spindle motor, 5,587,617, Cl. 310-90,500.
- Dupont Optical Company: *See—*
Bluthgen, Bjorn, 5,587,979, Cl. 369-32,000.
- Dupuis, Christine: *See—*
Lion, Bertrand; Mondet, Jean; and Dupuis, Christine, 5,587,145, Cl. 424-45,000.
- Duque, Pilar: *See—*
Punto, Louis; Potini, Chmi; Duque, Pilar; and Gould, Eva, 5,587,149, Cl. 424-59,000.
- Dussinger, Peter M.: *See—*
Hantenstine, John R.; and Dussinger, Peter M., 5,586,549, Cl. 126-635,000.
- Dye, William M.: *See—*
Clark, David E.; and Dye, William M., 5,586,608, Cl. 175-40,000.
- Dynys, Frederick W.: *See—*
Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634,000.
- E. I. DuPont de Nemours and Company: *See—*
Priester, Donnan E., 5,587,429, Cl. 525-187,000.
- E. J. A. Engineering PLC: *See—*
Mohtasham, Mehdi, 5,587,569, Cl. 200-17,000.
- E. R. St. Denis & Sons Ltd.: *See—*
St. Denis, Lucien, 5,587,042, Cl. 156-477,100.
- E-Systems, Inc.: *See—*
White, David M., 5,587,119, Cl. 264-104,000.
- Eastern Company, The: *See—*
Weinerman, Lee S.; and Arthurs, Scott A., 5,586,458, Cl. 70-208,000.
- Eastern Michigan University: *See—*
Jones, Frank N.; Fu, Shou-Kuan; Hua, Jun; and Yuan, Xiaoying, 5,587,428, Cl. 525-165,000.
- Eastman Kodak Company: *See—*
Mehra, Madhavi; and Manico, Joseph A., 5,587,756, Cl. 396-515,000.
- Petruchik, Dwight J., 5,587,752, Cl. 396-315,000.
- Roy, Carl W.; and Tschiderer, Paul E., 5,586,479, Cl. 83-74,000.
- Seamans, Tom; and Stepienson, Stanley W., III, 5,587,757, Cl. 396-536,000.
- Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.; Fichtner, Michael W.; and Fitzgerald, John J., 5,587,245, Cl. 428-447,000.
- Wilson, Matthew; and Lauricella, Frank P., 5,587,755, Cl. 396-380,000.
- Eaton Corporation: *See—*
Bennardo, Gilbert; and Goubely, Armé, 5,586,747, Cl. 251-129,180.
- Elms, Robert T., 5,587,917, Cl. 364-487,000.
- Ehata, Shuji: *See—*
Abe, Mariko; Ehata, Shuji; Abe, Takafumi; and Higuchi, Hirofumi, 5,587,349, Cl. 502-236,000.
- Eberspacher, J.: *See—*
Humburg, Michael, 5,586,721, Cl. 237-12,300.
- Eby, Devon; Love, Dale; and Reed, James L., to Great Creations, Inc.: Clamp, 5,586,373, Cl. 24-525,000.
- Eccardt, Peter-Christian: *See—*
Kroemer, Nils; Vossiek, Martin; Eccardt, Peter-Christian; and Magori, Valentin, 5,587,969, Cl. 367-99,000.
- Ecker, David J.: *See—*
Cook, Phillip D.; Ecker, David J.; Acevedo, Oscar L.; and Davis, Peter, 5,587,471, Cl. 536-25,300.
- Ecolab Inc.: *See—*
Besse, Michael E.; Ross, Cynthia L.; and Kleaver, Helen A., 5,587,009, Cl. 106-244,000.
- Ed, Donald A. N.: *See—*
O'Brien, John L.; Thomas, Edward M.; and Ed, Donald A. N., 5,586,352, Cl. 5-662,000.
- Ed. Scharwachter GmbH & Co. KG: *See—*
Tölle, Karl-Heinz; and Grothe, Hermann, 5,586,361, Cl. 16-51,000.
- Edgar, Albert D., to International Business Machines Corporation: Optical feedback printer, 5,587,728, Cl. 347-19,000.
- Edgar, Albert D., to International Business Machines Corporation: Personal multimedia speaker system, 5,588,063, Cl. 381-24,000.

- Edman, Timothy J.: *See—*
Leonard, William K.; Mohn, Stephen W.; Edman, Timothy J.; and Schiller, Phillip D., 5,587,184, Cl. 425-133,500.
- Edwards, Michael B.: *See—*
Klimek, Thaddeus W.; and Edwards, Michael B., 5,587,436, Cl. 526-59,000.
- Edwards, Rand J.: *See—*
Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Lyla R.; and Strohecker, Cary A., Sr., 5,588,051, Cl. 379-243,000.
- Edwards, Robert W.; Fulmer, Terry M.; and Schultz, Patrick J., to Tokheim Corporation: Fluid exchanger with fluid reconciliation, 5,586,583, Cl. 141-83,000.
- Eggebrecht, Charles M.: *See—*
van Alstine, Daniel W.; and Eggebrecht, Charles M., 5,586,737, Cl. 246-448,000.
- Egger, Norbert K.: *See—*
Kampe, Klaus-Dieter; ter Meer, Hans-Ulrich; Egger, Norbert K.; and Vogel, Martin A., 5,587,476, Cl. 540-472,000.
- Eguchi, Tomoko; and Asami, Goro, to Nifco Inc.: Fastening device, 5,586,372, Cl. 24-452,000.
- Ehlers, Jens; and Walter, Jutta, to Hoechst Aktiengesellschaft: Process for the preparation of ultrahigh molecular weight polyethylene having a high bulk density, 5,587,440, Cl. 526-153,000.
- Ehsani, Mehrdad, to Texas A&M University System, The: Electrically peaking hybrid system and method, 5,586,613, Cl. 180-65,200.
- Eichberger, Horst: *See—*
Dickinson, Ian J.; Eichberger, Horst; Messaros, David W.; and Walter, Hans-Dieter, 5,588,109, Cl. 395-326,000.
- Eisai Chemical Co., Ltd.: *See—*
Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58,000.
- Eisai Co., Ltd.: *See—*
Negi, Shigetoshi; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222,000.
- Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58,000.
- Eisele, Ulrich: *See—*
Langstein, Gerhard; Krüger, Ralf; Piejko, Karl-Erwin; Eisele, Ulrich; and Morbitzer, Leo, 5,587,424, Cl. 525-63,000.
- Eisen, Norbert; Godhardt, Lutz-Peter; and Haas, Peter, to Bayer Aktiengesellschaft: Process for insulating pipes using polyurethane rigid foams by the rotational casting process, 5,587,117, Cl. 264-45,700.
- Eisen, Yosef; Gilat, Chaim; and Keinan, Giora: Light weight gamma-camera head and gamma-camera assemblies containing it, 5,587,585, Cl. 250-370,000.
- Ejima, Katsumi: *See—*
Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203,000.
- Ek, Anders; and Hegardt, Johan, to Tetra Laval Holdings & Finance S.A.: Delayed safety braking apparatus for a servomotor control system, 5,587,640, Cl. 318-638,000.
- Ektrom Industries, Inc.: *See—*
Robinson, Darrell; Loehr, Karl; Pruhs, Allen V.; and Learmont, Robert O., 5,586,913, Cl. 439-638,000.
- Elder, Albert B.: *See—*
Owens, Steve C.; Lovvorn, Richard V.; and Elder, Albert B., 5,587,181, Cl. 425-3,000.
- Electric Power Research Institute, Inc.: *See—*
Roy, Timothy A.; Mackerer, Carl R.; and Goldstein, Lawrence, 5,587,324, Cl. 436-183,000.
- Electric Propulsion Laboratory, Inc.: *See—*
Aston, Graeme, 5,587,093, Cl. 219-121,480.
- Electronic Designs Inc.: *See—*
Pirani, Gary P.; Gulachenski, Alan M.; and Kelly, David J., 5,586,891, Cl. 439-71,000.
- Elephant Chain Block Company, Ltd.: *See—*
Ueno, Yoshio; Wada, Yasuo; and Honda, Munenobu, 5,586,751, Cl. 254-352,000.
- Wada, Yasuo; and Ueno, Yoshio, 5,586,752, Cl. 254-372,000.
- ELF Atochem S.A.: *See—*
Curci, Michèle; Mieloszynski, Jean-Luc; and Paquer, Daniel, 5,587,499, Cl. 554-85,000.
- Eli Lilly and Company: *See—*
Alborn, William E., Jr.; Hoskins, JoAnn; Skatrud, Paul L.; and Unal, Serhat, 5,587,307, Cl. 435-240,100.
- Ellis, Craig D.: *See—*
Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenith W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710,000.
- Elmaleh, David R.; and Fischman, Alan J., to Elmaleh, David R.: Meta substituted arylalkylamines and therapeutic and diagnostic uses thereof, 5,587,398, Cl. 514-654,000.
- Elms, Robert T., to Eaton Corporation: Data collection and processing for digital AC power system monitor/analyzer, 5,587,917, Cl. 364-487,000.
- Elonox I.P. Holdings, Ltd.: *See—*
Kikinis, Dan, 5,586,498, Cl. 101-127,000.
- Elson, Charles E.: *See—*
Gould, Michael N.; Crowell, Pamela L.; Elson, Charles E.; and Clark, Steven S., 5,587,402, Cl. 514-729,000.
- El Subbagh, Hussein I.: *See—*
Panzica, Raymond P.; El Subbagh, Hussein I.; and Abushanab, Elie, 5,587,494, Cl. 549-512,000.
- Emhart Glass Machinery Investments Inc.: *See—*
Mann, Philip A.; and Green, Ian, 5,587,000, Cl. 65-260,000.
- Emmons, David J.; and Lu, Liang-Ju, to ADC Telecommunications, Inc.: Overlapping fusion attenuator, 5,588,087, Cl. 385-140,000.
- Emory University: *See—*
Liotta, Dennis C.; and Lagu, Bharat R., 5,587,514, Cl. 564-134,000.
- Emricsson, Ingemar: *See—*
Rosengren, Lars; and Emricsson, Ingemar, 5,588,047, Cl. 379-100,000.
- Emulex Corporation: *See—*
Rickard, Wayne T., 5,588,000, Cl. 370-428,000.
- Endo, Kazuhito; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto, Manabu; and Hirai, Nobuaki, to Mitsubishi Denki Kabushiki Kaisha: Record/reproduction apparatus for recording/reproducing multi-channel signals in different areas of a recording medium, 5,587,978, Cl. 369-32,000.
- Endo, Koji, to NEC Corporation: D channel packet communication system and a method of D channel packet communication, 5,587,999, Cl. 370-352,000.
- Endo, Naoto: *See—*
Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332,000.
- Endo, Seichiro, to Sumitomo Rubber Industries, Ltd.: Golf ball, 5,586,950, Cl. 473-356,000.
- Endo, Takayoshi: *See—*
Yagi, Sakai; Tsuji, Masanori; Kashiwaya, Motohisa; and Endo, Takayoshi, 5,586,900, Cl. 439-310,000.
- Engen, Paul T., to Minnesota Mining and Manufacturing: Reaction system for producing a polyurethane and method of using same to seal a surface, 5,587,448, Cl. 528-55,000.
- England, Robert L.; and Albert, Donn E., to England, Robert L.: Automatic emergency escape for tall structures, 5,586,617, Cl. 182-238,000.
- Enneking, John R.; and Schultz, John, to Batesville Casket Company: Decorative casket carrying and presentation tray, 5,586,376, Cl. 27-27,000.
- Enokida, Takashi; Naraki, Akihiro; Yamashita, Eiichi; and Tatsu, Haruyoshi, to Nippon Mektron, Limited: Fluorine rubber composition, 5,587,413, Cl. 524-200,000.
- Entrena, Luis: *See—*
Cheng, Kwang-Ting; and Entrena, Luis, 5,587,919, Cl. 364-489,000.
- Entropy Racing, Inc.: *See—*
Archer, Shreve M., III, 5,586,561, Cl. 128-846,000.
- Entzerth, Michael: *See—*
Narr, Berthold; Haeu, Norbert; Van Meel, Jacques; Wienen, Wolfgang; Entzerth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381,000.
- Environmental Dynamics, Inc.: *See—*
Tharp, Charles E., 5,587,114, Cl. 261-124,000.
- Environmental L.L.C.: *See—*
Kiser, Weldon C., 5,587,234, Cl. 428-327,000.
- Environmental Research Institute of Michigan: *See—*
Alkon, Daniel L.; Vogl, Thomas P.; Blackwell, Kim T.; and Barbour, Garth S., 5,588,091, Cl. 395-24,000.
- Environmental Technologies Group, Inc.: *See—*
Stroosnyder, Peter C., 5,587,581, Cl. 250-287,000.
- Envision Medical Corporation: *See—*
Walls, Robert R., 5,587,736, Cl. 348-65,000.
- Epler, Frederick A.: *See—*
Fuller, Robert M.; Epler, Frederick A.; and Manowski, Maxwell E., 5,588,037, Cl. 379-57,000.
- Erickson, Robert: *See—*
Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert; and Froen, Diane, 5,587,481, Cl. 546-146,000.
- Ericsson, Staffan: *See—*
Jones, Oliver; Deshon, Mary; Ericsson, Staffan; and Flach, James, 5,587,928, Cl. 364-514,000.
- Errico, Joseph P.; Errico, Thomas J.; and Ralph, James D., to Fastenex, L.L.C.: Polyaxial locking screw and coupling element assembly for use with rod fixation apparatus, 5,586,984, Cl. 606-61,000.
- Errico, Thomas J.: *See—*
Errico, Joseph P.; Errico, Thomas J.; and Ralph, James D., 5,586,984, Cl. 606-61,000.
- Erwin, James W.: *See—*
Halsey, James H.; Juds, Scott; and Erwin, James W., 5,586,684, Cl. 221-90,000.
- Esders, Theodore W.: *See—*
Scalice, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L., 5,587,287, Cl. 435-6,000.
- Eshleman, Roger D.: Apparatus and method for infedding batched materials, 5,586,855, Cl. 414-160,000.
- Eslampour, Robert A.; Shiley, Robert J., II; and Hendry, Allan W., to Burndy Corporation: High density filtered connector, 5,586,912, Cl. 439-620,000.
- Esser, Karl-Joseph, to Mannesmann Aktiengesellschaft: Process and device for machining bars, tubes or tube blanks, 5,586,476, Cl. 82-1,110.
- Etalex Inc.: *See—*
Brousseau, Claude, 5,586,665, Cl. 211-59,200.
- Ethicon, Inc.: *See—*
Lennard, David J., 5,587,122, Cl. 264-178,000.
- Ethyl Petroleum Additives Limited: *See—*

- Scattergood, Roger, 5,587,432, Cl. 525-327.600.
 Etore, Steven P.; Lane, Joseph J.; and Vandergriff, Douglas S., to 21st Century Containers, Ltd. Bulk container with removable liner, discharge flament for the liner, and adapter for connection to discharge port of the container, 5,586,690, Cl. 222-105.000.
 Eurogreen International Inc.: See—
 Lindh, Leif, and Lindh, Kjell, 5,586,778, Cl. 280-40.000.
 European Touch Co., Inc.: See—
 Schick, Michael R., 5,587,108, Cl. 252-364.000.
 Evans, John C., to Smith & Nephew plc. Crepe effect bandage, 5,586,972, Cl. 602-76.000.
 Everly, Philip. Tunable plectrum, 5,587,542, Cl. 84-322.000.
 Ewing, Joan R.: See—
 Hsieh, Bing R.; Mort, Joseph; Machonkin, Mary A.; and Ewing, Joan R., 5,587,224, Cl. 428-195.000.
 Exar Corporation: See—
 Salcedo, Jose A., 5,587,684, Cl. 327-538.000.
 Exedy Corporation: See—
 Okubo, Mamoru; and Yoneyama, Koji, 5,586,434, Cl. 60-345.000.
 Exisight Ltd.: See—
 Banitt, David; and Shlomo, Moshe B., 5,587,664, Cl. 324-752.000.
 Exxon Chemical Patents Inc.: See—
 Audett, Jay D.; and McElrath, Kenneth O., 5,587,261, Cl. 430-18.000.
 Krogh, James A.; Mokadam, Anita R.; and Smith, B. Brian, 5,587,498, Cl. 554-69.000.
 Exxon Production Research Company: See—
 Krebs, Jerome R., 5,587,942, Cl. 367-50.000.
 Exxon Research and Engineering Company: See—
 Beltzer, Morton; Berlowitz, Paul J.; and Kim, Jeenuk T., 5,587,355, Cl. 508-302.000.
 Ezawa, Hirokazu: See—
 Idaka, Toshiaki; and Ezawa, Hirokazu, 5,587,337, Cl. 437-183.000.
 Ezo, Takuji. Guide type cable engine, 5,586,750, Cl. 254-134.35C.
 F.A.S.: See—
 Krzywdziak, Alain, 5,586,822, Cl. 366-247.000.
 F. C. Young & Co., Inc.: See—
 Young, Kevin, 5,587,031, Cl. 156-148.000.
 Fabricius, Dietrich M.; Harms, Ralf H.; and Welter, James J., to Sterling Diagnostic Imaging, Inc. Zeromethine merocyanine dyes useful as spectral sensitizers in photographic elements, 5,587,482, Cl. 548-179.000.
 Facet International, Inc.: See—
 Belden, Donald E., 5,587,071, Cl. 210-232.000.
 Fahey, William D.: See—
 Willis, Kenneth E.; Fahey, William D.; and Whang, David S., 5,587,550, Cl. 102-217.000.
 Fahy, Gregory M., to Organ, Inc.; and I.R.T. Inc. Portable device for preserving organs by static storage or perfusion, 5,586,438, Cl. 62-78.000.
 Fahy, Gregory M., to Organ, Inc.; and Life Resuscitation Technologies, Inc. Anastomosis cuff, 5,586,987, Cl. 606-155.000.
 Fair, Samuel S. Shore erosion control structures, 5,586,835, Cl. 405-30.000.
 Falempin, Francois; Fourt, Olivier; and Pastre, Jean-Louis, to Office National d'Etudes et de Recherches Aérospatiales. Two-dimensional supersonic and hypersonic air intake, with three movable ramps, for the combustion air of an aircraft engine, 5,586,735, Cl. 244-53.00B.
 Faletti, James J.; Feucht, Dennis D.; and Sinn, Scott G., to Caterpillar Inc. Recirculation of actuating fluid in an engine braking system, 5,586,532, Cl. 123-321.000.
 Fallon Luminous Products: See—
 Mohacsi, Ferenc, 5,587,622, Cl. 313-493.000.
 Faloan, Michael D.; Perry, William; and Hess, Arthur, to United Technologies Automotive Systems Inc. Exterior mirror with information display, 5,587,699, Cl. 340-475.000.
 Fan, Joseph C.: See—
 Greaves, Brian; Poole, Stephen C.; Hwa, Chih M.; and Fan, Joseph C., 5,587,109, Cl. 252-392.000.
 Fan, Robert J., to LiteCom, Inc. Fiber optic hermetic bulkhead penetrator feedthrough module and method of fabricating same, 5,588,086, Cl. 385-138.000.
 Fandel, Marco: See—
 Spach, Richard; Schaefer, Wolfgang; Stolten, Detlef; and Fandel, Marco, 5,587,251, Cl. 429-33.000.
 Fanuc Ltd.: See—
 Kato, Tetsuaki; Arita, Soichi; and Nakamura, Masaru, 5,587,638, Cl. 318-568.140.
 Nagatomi, Takashi, 5,587,915, Cl. 364-474.190.
 Watanabe, Atsushi; Nihei, Ryo; and Terada, Akihiro, 5,587,635, Cl. 318-434.000.
 Fanuzzi, John M. Indexing hinge, 5,586,363, Cl. 16-342.000.
 Farah, Anthony: See—
 Leitner, Johann R.; and Farah, Anthony, 5,587,575, Cl. 235-384.000.
 Farkas, Laszlo: See—
 Hahnen, Kevin F.; Farkas, Laszlo; and Gordon, David P., 5,586,990, Cl. 606-170.000.
 Farmitalia Carlo Erba S.r.l.: See—
 Alpegiani, Marco; Bissolino, Pierluigi; and Perrone, Ettore, 5,587,373, Cl. 514-202.000.
 Buzzetti, Franco; Eustoni, Silvia; Brasca, Maria G.; and Penco, Sergio, 5,587,385, Cl. 514-309.000.
 Farmitalia Carlo Erba S.r.l.: See—
 Cabri, Walter; De Bernardinis, Silvia; Francalanci, Franco; and Penco, Sergio, 5,587,495, Cl. 552-220.000.
 Fastenett, L.L.C.: See—
 Errico, Joseph P.; Errico, Thomas J.; and Ralph, James D., 5,586,984, Cl. 606-61.000.
 Fauveau, Patrick: See—
 Aszodi, Jozsef; Chantot, Jean-Francois; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.
 Fear, Christopher, to Siemens Electromechanical Components, Inc. Polarized electromagnetic relay, 5,587,693, Cl. 335-78.000.
 FED Corporation: See—
 Jones, Gary W., 5,587,623, Cl. 313-497.000.
 Fehrmann, Gerd; Frömmel, Rainer; and Wolf, Rüdiger, to Litronik Batterie-technologie GmbH & Co. Galvanic cell having improved cathode, 5,587,258, Cl. 429-228.000.
 Fel-Pro Incorporated: See—
 Novil, Martin; and O'Brien, Michael, 5,586,769, Cl. 277-1.000.
 Feldman, Howard R., to International Mobile Satellite Organization. Communication apparatus for disabling messages specifying non-standard communication features, 5,587,810, Cl. 358-442.000.
 Fellner, Alan E., to Custom Graphics. Multi-layer sheet material having a refractive surface and method for making same, 5,587,037, Cl. 156-231.000.
 Ferber, Ralf G., to Prakla-Seismos GmbH. Method for improvement of seismic sections, 5,587,967, Cl. 367-53.000.
 Ferguson, Daniel J.: See—
 DiPaolo, Nunzio; and Ferguson, Daniel J., 5,587,095, Cl. 219-388.000.
 Ferguson, David E., to Amalgamated Software of North America, Inc. Non-heuristic decimal divide method and apparatus, 5,587,940, Cl. 364-762.000.
 Ferodo Limited and British Railways Board: See—
 Dolbear, Keith D.; Beamond, Trevor W.; and Schofield, Kerry G., 5,586,626, Cl. 188-250.00B.
 Ferrante, Antonio: See—
 Rathjen, Deborah A.; and Ferrante, Antonio, 5,587,457, Cl. 530-326.000.
 Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., to Fluke Corporation. On-board measurement system, 5,587,932, Cl. 364-556.000.
 Ferrar, Wayne T.: See—
 Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.; Fichtner, Michael W.; and Fitzgerald, John J., 5,587,245, Cl. 428-447.000.
 Ferrari, Franco; and Migli, Carlo, to Ferrari, Franco. Fastening element for hardware parts and hinge embodying such elements, 5,586,364, Cl. 16-383.000.
 Ferris, Andrew, to SGS-Thomson Microelectronics Limited. Integrated circuit memory device with voltage boost, 5,587,960, Cl. 365-230.030.
 Ferry, Julian J.: See—
 Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard F., 5,586,911, Cl. 439-607.000.
 Fessler, Charles B.: See—
 Kanjo, Wajibi; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7.000.
 Fetzner, Thomas; Buechele, Wolfgang; Wistruba, Hermann; Otto, Bernhard; Buenger, Gert; and Pyl, Paul, to BASF Aktiengesellschaft. Process for the catalytic decomposition of dinitrogen monoxide in a gas stream, 5,587,135, Cl. 423-239.100.
 Feucht, Dennis D., to Caterpillar Inc. Engine compression braking valve actuator apparatus, 5,586,533, Cl. 123-321.000.
 Feucht, Dennis D.: See—
 Faletti, James J.; Feucht, Dennis D.; and Sinn, Scott G., 5,586,532, Cl. 123-321.000.
 Fichtner, Michael W.: See—
 Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.; Fichtner, Michael W.; and Fitzgerald, John J., 5,587,245, Cl. 428-447.000.
 Fiddes, Neil G.; King, Christopher G.; Mantone, Anthony; and Shaffer, Frank D., to General Electric Company. Apparatus for joining foils used in superconducting magnets, 5,586,712, Cl. 228-5.700.
 Fiech, Manfred M. Unitized fuel storage system, 5,586,586, Cl. 141-98.000.
 Fike, Jody R. Fishing lure, 5,586,405, Cl. 43-42.310.
 Filipovic, Predrag: See—
 Bar-Kana, Izhak; and Filipovic, Predrag, 5,587,636, Cl. 318-561.000.
 Firma Carl Freudenberg: See—
 Stief, Reinhard; and Müller-Broll, Gerhard, 5,587,564, Cl. 181-295.000.
 Fischer, Wolfgang H.: See—
 Behan, Dominic P.; Vale, Wylie W., Jr.; Fischer, Wolfgang H.; and Lowry, Philip J., 5,587,462, Cl. 530-350.000.
 Fischerwerke, Arrur Fischer GmbH & Co KG: See—
 Haage, Manfred, 5,586,851, Cl. 411-10.000.
 Fischetti, Vincent A.: See—
 Cheung, Ambrose; and Fischetti, Vincent A., 5,587,288, Cl. 435-6.000.
 Fischman, Alan J.: See—
 Elmaleh, David R.; and Fischman, Alan J., 5,587,398, Cl. 514-654.000.
 Fisher, Douglas G.: See—
 Baker, Ronald J.; Fisher, Douglas G.; Rupert, Martha L.; and Swartz, David M., 5,586,915, Cl. 439-733.100.
 Fisher, Fred M.; and Powis, Jack R. Flashing device for use with exterior siding, 5,586,415, Cl. 52-58.000.
 Fisher-Rosemount Systems, Inc.: See—

- Ho, Weng K.; Hang, Chang C.; and Wojsznis, Wilhelm K., 5,587,899, Cl. 364-157.000.
 Fisher, William D.: See—
 Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein, Michael J.; and Wilker, Julie D., 5,587,914, Cl. 364-468.010.
 Fisk, Allan T.; and Freed, David I., to Gas Research Institute. Apparatus and method for internally sealing pipes, 5,586,580, Cl. 138-98.000.
 Fitch, Frank R.: See—
 Bülow, Martin; Dao, Loc; and Fitch, Frank R., 5,587,003, Cl. 95-123.000.
 Fitzgerald, David: See—
 Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324.000.
 Fitzgerald, John J.: See—
 Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.; Fichtner, Michael W.; and Fitzgerald, John J., 5,587,245, Cl. 428-447.000.
 Fitzner, John E.; and McCoy, Thomas J. Mail carrier, 5,586,700, Cl. 224-219.000.
 Fitzsimmons, James N.; and Schickert, Randy R., to Huff Corporation. Basketball goal unit, 5,586,759, Cl. 273-1.50R.
 Flach, James: See—
 Jones, Oliver; Deshon, Mary; Ericsson, Staffan; and Flach, James, 5,587,928, Cl. 364-514.00A.
 Flaman, Michael T. Hot water tempering system utilizing a storage tank, a bypass line and a proportional flow controller, 5,588,088, Cl. 392-449.000.
 Fleck, David C.; and Tsuchida, Yoichi, to Wacom Co., Ltd. Control method of a plurality of locators and control device of same, 5,587,559, Cl. 178-18.000.
 Fleetwood Systems, Inc.: See—
 Mojdén, Andrew E.; and Hoinacki, Richard P., 5,586,638, Cl. 198-419.000.
 Fleischer, Dietrich; Hoffmückel, Michael; Mück, Karl-Friedrich; and Sextro, Günter, to Hoechst Aktiengesellschaft. Process for the preparation of polyacetal copolymers, 5,587,449, Cl. 528-232.000.
 Fleischer, Thomas B.: See—
 Ostermayer, Volker; and Fleischer, Thomas B., 5,587,051, Cl. 162-198.000.
 Flight Refuelling Limited: See—
 Dickie, Neil M.; and Hudson, Steven M., 5,587,707, Cl. 340-870.090.
 Flinchbaugh, David E. Low pressure medical silicone gasket, 5,587,244, Cl. 428-447.000.
 Florida State University: See—
 Holton, Robert A.; and Kim, Seokchan, 5,587,489, Cl. 549-229.000.
 Flotte, Terence: See—
 Carter, Barrie J.; Flotte, Terence; Afione, Sandra; and Solow, Rikki, 5,587,308, Cl. 435-240.200.
 Fluid Propulsion Technologies, Inc.: See—
 Ivi, Yehuda; and Wu, Cheng H., 5,586,550, Cl. 128-200.160.
 Fluke Corporation: See—
 Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., 5,587,932, Cl. 364-556.000.
 Flum, Alan: See—
 Staros, Theodore; and Flum, Alan, 5,586,906, Cl. 439-483.000.
 Fluoroware, Inc.: See—
 Nyseth, David L., 5,586,658, Cl. 206-711.000.
 Fluxtrol Manufacturing, Inc.: See—
 Ruffini, Robert S.; Madeira, Robert J.; and Ruffini, Robert T., 5,588,019, Cl. 373-152.000.
 FM Industries, Inc.: See—
 Seay, O. Elwyn; Nickles, Stephen K.; and Haley, John E., 5,586,669, Cl. 213-43.000.
 FMC Corporation: See—
 Henrie, Robert N. H.; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chaguturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.
 Fobbeater, Ian G., to Plessey Semiconductors Limited. DC restoration circuit, 5,587,681, Cl. 327-307.000.
 Focal Technologies, Inc.: See—
 Woodside, Shane H., 5,588,077, Cl. 385-26.000.
 Focke & Co. (GmbH & Co.): See—
 Focke, Heinz; and Buse, Henry, to Focke & Co. (GmbH & Co.). Hinge-lid cigarette pack made from a one-piece blank, 5,586,648, Cl. 206-264.000.
 Fogelström, Joacim: See—
 Kellström, Magnus; Fogelström, Joacim; and Wittmeyer, Henning, 5,586,826, Cl. 384-450.000.
 Fonser, Per Åke: See—
 Dellby, Fredrik; and Fonser, Per Åke, 5,586,680, Cl. 220-467.000.
 Foos, Douglas E., to Plastofilm Industries, Inc. Thermoformed foldover package with easy open feature, 5,586,677, Cl. 220-260.000.
 Foote, Steven A.; and Stoddard, Damon R., to AlliedSignal Inc. Low stress magnet interface for a force rebalance accelerometer, 5,587,530, Cl. 73-514.230.
 Forbes, Craig W.: See—
 Brent, S. Shannon; and Forbes, Craig W., 5,586,402, Cl. 43-17.000.
 Ford Motor Company: See—
 Gale, Allan R.; and Toepfer, Craig B., 5,587,864, Cl. 361-44.000.
 Hampo, Richard J.; Marko, Kenneth A.; and Bryant, Bruce D., 5,587,524, Cl. 73-116.000.
 Ondrejko, Richard T.; Castiglione, Paul J.; and Miller, Robert J., 5,586,875, Cl. 418-3.000.
 Stevenson, Paul E.; Stephan, Craig H.; Samman, Amer M.; and Spangler, Leland J., 5,587,518, Cl. 73-1.00D.
 Szpak, Archana, 5,586,879, Cl. 445-24.000.
 Forestier, Serge: See—
 Defandre, André; Dubois, Michel; Forestier, Serge; and Richard, Hervé, 5,587,150, Cl. 424-59.000.
 Forneck, Kevin: See—
 Mehnert, David W.; Forneck, Kevin; Prince, Steven; and Major, Michael D., 5,587,196, Cl. 426-611.000.
 Forte, Steven L.; and Sines, Randy D., to Casinoventions, Inc. Blackjack game system and methods, 5,586,766, Cl. 273-309.000.
 Fortunko, Christopher M.: See—
 McColskey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., 5,587,534, Cl. 73-623.000.
 Foster, Alice M., executrix: See—
 Foster, George H., Jr., deceased; and Metzger, Donald L., 5,586,914, Cl. 439-676.000.
 Foster, Clark B.: See—
 Haber, Terry M.; Smedley, William H.; and Foster, Clark B., 5,586,946, Cl. 473-295.000.
 Foster, George H., Jr., deceased (by Alice M. Foster, executrix); and Metzger, Donald L., to Whitaker Corporation. The Electrical connector and an associated method for compensating for crosstalk between a plurality of conductors, 5,586,914, Cl. 439-676.000.
 Foster, Gregg S.; and Capps, Stephen P., to Apple Computer, Inc. Status bar for application windows, 5,588,105, Cl. 395-326.000.
 Foster, Robert I.: See—
 Chandos, Ronald V.; and Foster, Robert I., 5,588,059, Cl. 380-21.000.
 Foster, Robert P.: See—
 Brock, James H.; and Foster, Robert P., 5,586,761, Cl. 473-207.000.
 Foster, Samuel T. Code blue light audio and visual alarm apparatus, 5,587,704, Cl. 340-573.000.
 Fourt, Olivier: See—
 Falempin, Francois; Fourt, Olivier; and Pastre, Jean-Louis, 5,586,735, Cl. 244-53.00B.
 Fox, Anthony W., to Cypros Pharmaceutical Corporation. Reduction of elevated blood lactate using twice-daily dichloroacetate, 5,587,397, Cl. 514-557.000.
 Foxboro Company, The: See—
 Hansen, Peter D.; and Bristol, Edgar H., 5,587,896, Cl. 364-148.000.
 Fraga, Robert L. Method and apparatus for the preparation of fowl, 5,586,489, Cl. 99-419.000.
 Fragrance Systems International, Inc.: See—
 Breidenbach, Diane; and Mille, Laurence, 5,586,694, Cl. 222-183.000.
 Framatome Connectors International: See—
 Chemin, Gilles, 5,586,918, Cl. 439-752.000.
 Hoffmann, Manfred, 5,586,903, Cl. 439-352.000.
 Hopf, Gustav; and Steinhart, Helmut, 5,586,902, Cl. 439-352.000.
 Framatome Technologies, Inc.: See—
 Jevce, John M.; and Dow, Randall P., 5,587,025, Cl. 148-274.000.
 Francalanci, Franco: See—
 Cabri, Walter; De Bernardinis, Silvia; Francalanci, Franco; and Penco, Sergio, 5,587,495, Cl. 552-220.000.
 France Telecom Etablissement Autonome de Droit Public: See—
 Le Corre, Hervé; Grimaud, Jean-Luc; and Boudet, François, 5,587,809, Cl. 358-405.000.
 Franciotta, Massimo: See—
 Colli, Gianluca; Franciotta, Massimo; and Castello, Rinaldo, 5,587,682, Cl. 327-357.000.
 Francis, Dale. System for lubricating threaded members, 5,586,618, Cl. 184-14.000.
 Frank, Steven N.: See—
 Belcher, James F.; Frank, Steven N.; Long, John P.; and Jones, Jeanée, 5,587,090, Cl. 216-17.000.
 Frank, William D., Sr. Ground fault interrupter bucket combination, 5,587,862, Cl. 361-42.000.
 Franke, Rickard; Kaneko, Yutaka; and Brandstrom, Per, to Tetra Laval Holdings & Finance S.A. Dosing valve having seal failure detection, 5,586,576, Cl. 137-559.000.
 Frankholz, Christian: See—
 Humpert, Jürgen; Heimann, Bruno; and Frankholz, Christian, 5,586,746, Cl. 251-129.040.
 Frantz, Gene A.: See—
 Hashimoto, Masashi; Frantz, Gene A.; Moravec, John V.; and Dolait, Jean-Pierre, 5,587,962, Cl. 365-230.090.
 Frantz, Robert H.; Larkin, John T., Jr.; and Correll, Robert S., Jr., to Whitaker Corporation. The Battery connector, 5,586,907, Cl. 439-500.000.
 Fraser, Paul E. Reinforcing devices for doors and door frames, 5,586,796, Cl. 292-346.000.
 Fratangelo, Louis D.: See—
 Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry, Arnold W.; Heeks, George J.; and Fratangelo, Louis D., 5,587,208, Cl. 427-503.000.
 Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V.: See—
 Hambitzer, Günther; Böke, Winfried; and Oertel, Armin, 5,587,064, Cl. 205-742.000.
 Frayssé, Philippe: See—

- Koerberle, Yves; and Frayssé, Philippe, 5,586,451, Cl. 62-646,000.
 Frechet, Jean M. J.; and Aoshima, Sadahito, to Cornell Research Foundation, Inc. Hyperbranched polymers from AB monomers, 5,587,441, Cl. 526-238,000.
 Frechet, Jean M. J.; and Aoshima, Sadahito, to Cornell Research Foundation, Inc. Hyperbranched polymers from AB monomers, 5,587,446, Cl. 526-333,000.
 Frechet, Jean M. J.: See—
 Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,587,422, Cl. 524-779,000.
 Freed, David I.: See—
 Fisk, Allan T.; and Freed, David I., 5,586,580, Cl. 138-98,000.
 Freeman, Gary M.: See—
 Marshall, Carl J., Jr.; and Freeman, Gary M., 5,587,011, Cl. 106-416,000.
 Freeman, Lewis G. Die cast vent block, 5,586,596, Cl. 164-253,000.
 Freitas, Michael J. Fishpole storage system, 5,586,404, Cl. 43-21,200.
 Fricke, Jochen: See—
 Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred, 5,587,107, Cl. 252-315,600.
 Friedrich Grohe Aktiengesellschaft: See—
 Humpert, Jürgen; Heimann, Bruno; and Frankholz, Christian, 5,586,746, Cl. 251-129,040.
 Frischknecht, Willi, to Airlux AG. Mattress with an integrated air system, 5,586,347, Cl. 5-713,000.
 Fritz Industries, Inc.: See—
 Montgomery, Daniel P., 5,587,012, Cl. 106-823,000.
 Fritzmeier, Karl Heinrich: See—
 Bull, James R.; Fritzmeier, Karl-Heinrich; and Hegele-Hartung, Christa, 5,587,496, Cl. 552-629,000.
 Froen, Diane: See—
 Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert, and Froen, Diane, 5,587,481, Cl. 546-146,000.
 Frömmel, Rainer: See—
 Fehrmann, Gerd; Frömmel, Rainer; and Wolf, Rüdiger, 5,587,258, Cl. 429-228,000.
 Frontier Manufacturing Company: See—
 Glaze, Bradley S.; and Warner, Kenneth R., 5,586,731, Cl. 241-56,000.
 Frost, Peter L. J.: See—
 Peacock, John; Frost, Peter L. J.; and Kerry, John, 5,588,076, Cl. 385-20,000.
 Frullini, Alberto; and Frullini, Paolo. Method and apparatus for treating stitches of knit articles, 5,586,453, Cl. 66-148,000.
 Frullini, Paolo: See—
 Frullini, Alberto; and Frullini, Paolo, 5,586,453, Cl. 66-148,000.
 Fu, Chin-Jen: See—
 Ko, Wen-Chung; Ko, Kent, and Fu, Chin-Jen, 5,586,624, Cl. 188-164,000.
 Fu, Shou-Kuan: See—
 Jones, Frank N.; Fu, Shou-Kuan; Hua, Jun, and Yuan, Xiaoying, 5,587,428, Cl. 525-165,000.
 Fudaki, Tsutomu, to YKK Corporation. Separable bottom stop assembly for slide fastener, 5,586,370, Cl. 24-433,000.
 Fuderer, Miha: See—
 Van Heels-Bergen, Teunis R.; and Fuderer, Miha, 5,587,656, Cl. 324-307,000.
 Fuerst, Thomas R.: See—
 Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324,000.
 Fuisz, Richard C.: See—
 Cherukuri, Subraman R.; Myers, Garry L.; Battist, Gerald E.; and Fuisz, Richard C., 5,587,172, Cl. 424-401,000.
 Fuisz Technologies Ltd.: See—
 Cherukuri, Subraman R.; Myers, Garry L.; Battist, Gerald E.; and Fuisz, Richard C., 5,587,172, Cl. 424-401,000.
 Chenikuri, Subraman R.; Yang, Robert K.; Bowles, Cecil A.; Zamudio-Tena, Jose F.; and Bhowmik, Santi R., 5,587,198, Cl. 426-660,000.
 Fuji Electric Co., Ltd.: See—
 Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyoe; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367,000.
 Oyabe, Kazunori; Yoshida, Kazuhiko; and Fujihira, Tatsuhiko, 5,587,655, Cl. 323-312,000.
 Fuji Oil Company, Ltd.: See—
 Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, 5,587,197, Cl. 426-658,000.
 Fuji Photo Film Co., Ltd.: See—
 Kokubo, Hideyuki, 5,587,732, Cl. 347-183,000.
 Fuji Photo Film Co., Ltd.: See—
 Ikeda, Hideo; Shuto, Sadanobu; and Hara, Takefumi, 5,587,280, Cl. 430-567,000.
 Katagiri, Shingo; and Ashikawa, Teruo, 5,586,654, Cl. 206-387,100.
 Katoh, Kazunobu, 5,587,276, Cl. 430-440,000.
 Kawamoto, Fumio, 5,587,278, Cl. 430-533,000.
 Mifune, Hiroyuki; Yamanouchi, Junichi; and Ishiguro, Shoji, 5,587,279, Cl. 430-567,000.
 Mogi, Fumio, 5,587,004, Cl. 95-157,000.
 Nakatsugawa, Haruyasu; Yoneyama, Masakazu; and Urabe, Shigeharu, 5,587,282, Cl. 430-637,000.
 Okazaki, Yoji; Goto, Chiaki; Hyuga, Hiroaki; and Harada, Akinori, 5,588,014, Cl. 372-22,000.
 Saitou, Mitsuo; Yamanouchi, Junichi; and Hosoya, Yoichi, 5,587,281, Cl. 430-567,000.
 Suzuki, Hideki; and Kobda, Katsuhiko, 5,587,033, Cl. 156-164,000.
 Yamamoto, Takashi; Sakaguchi, Yasunobu; and Utsugi, Makoto, 5,587,768, Cl. 355-41,000.
 Fuji Photo Optical Co., Ltd.: See—
 Miyano, Hitoshi; and Yamamoto, Chikara, 5,587,839, Cl. 359-660,000.
 Ohno, Kazunori, 5,587,844, Cl. 359-717,000.
 Fuji Xerox Co., Ltd.: See—
 Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayo; Iwaoka, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl. 355-208,000.
 Mori, Hirokazu; and Ando, Ryo, 5,587,771, Cl. 355-208,000.
 Nukada, Katsumi; Imai, Akira; and Igarashi, Ryosaku, 5,587,263, Cl. 430-56,000.
 Otoma, Hiromi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, 5,588,016, Cl. 372-46,000.
 Fujie, Koji, to NEC Corporation. Apparatus for use in epitaxial crystal growth, 5,587,019, Cl. 118-725,000.
 Fujihira, Tatsuhiko: See—
 Oyabe, Kazunori; Yoshida, Kazuhiko; and Fujihira, Tatsuhiko, 5,587,655, Cl. 323-312,000.
 Fujii, Akiyoshi: See—
 Nishino, Hiromi; and Fujii, Akiyoshi, 5,586,385, Cl. 29-603,160.
 Fujii, Junji; and Okumura, Yukimasa, to Yamaha Corporation. Drum, 5,587,544, Cl. 84-411,00R.
 Fujikoki Mfg. Co., Ltd.: See—
 Sasaki, Keiji; and Koguchi, Masayuki, 5,587,535, Cl. 73-726,000.
 Fujimori, Naoki: See—
 Ikegaya, Akihiko; Tanabe, Keiichi; and Fujimori, Naoki, 5,587,013, Cl. 117-89,000.
 Fujimoto, Mikio, to Bridgestone Corporation. Apparatus for manufacturing recapped tire, 5,587,040, Cl. 156-394,100.
 Fujimoto, Sachio: See—
 Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684,000.
 Fujimoto, Takanori, to Mitsubishi Denki Kabushiki Kaisha. System for detecting fully closed state of the throttle valve for use in internal combustion engine, 5,586,534, Cl. 123-325,000.
 Fujinaga, Chikako: See—
 Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kuguminato, Hideo, 5,587,027, Cl. 148-320,000.
 Fujino, Masaru; and Takagi, Hiroshi, to Murata Manufacturing Co., Ltd. Apparatus for production of single crystal oxide films by liquid-phase epitaxy, 5,587,015, Cl. 117-200,000.
 Fujise, Masakuni; and Ishikawa, Hiroshi, to Kabushiki Kaisha Toshiba. X-ray CT apparatus and radiographing method using same, 5,588,036, Cl. 378-146,000.
 Fujishima, Kazuyasu; Matsuda, Yoshio; and Asakura, Mikio, to Mitsubishi Denki Kabushiki Kaisha. Semiconductor memory device for simple cache system, 5,588,130, Cl. 395-445,000.
 Fujita, Akifumi: See—
 Nakatani, Masayuki; Sengoku, Koji; and Fujita, Akifumi, 5,587,194, Cl. 426-521,000.
 Fujitsu Limited: See—
 Aoyagi, Yoshihiko, 5,588,103, Cl. 395-326,000.
 Chiba, Hirokazu; Murashita, Kimitaka; and Noda, Tsugio, 5,588,075, Cl. 382-239,000.
 Fukuta, Shinya; and Betsui, Keiichi, 5,587,720, Cl. 345-75,000.
 Mizuno, Shingo, 5,587,996, Cl. 370-228,000.
 Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhito; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219,000.
 Nakata, Tsuneo, 5,588,008, Cl. 371-27,000.
 Ohba, Toshimitsu; Shikata, Kiyotaka; and Sekihata, Osamu, 5,588,003, Cl. 370-468,000.
 Ozumi, Yumiko, 5,588,012, Cl. 371-51,100.
 Tanaka, Takehiko, 5,588,135, Cl. 395-487,000.
 Watanabe, Kimio, 5,588,136, Cl. 395-187,000.
 Fujitsu Miyagi Electronics Ltd.: See—
 Sekiba, Takashi, 5,587,606, Cl. 257-670,000.
 Fujiwara, Shinji; Tabuchi, Hiroshi; and Takahashi, Akihiko, to Sumitomo Chemical Company, Limited. Process for producing powders of transition metal boride, 5,587,140, Cl. 423-297,000.
 Fujiwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei; and Itou, Shigehiro, to Mitsubishi Denki Kabushiki Kaisha. Cartridge changing apparatus including a pair of base carriers and a pair of slide carriers, 5,587,989, Cl. 369-178,000.
 Fukano, Yoshihiro; and Doi, Yoshitada, to SMC Kabushiki Kaisha. Directional control valve, 5,586,570, Cl. 137-271,000.
 Fukuda, Shuichi: See—
 Nishio, Tadashi; and Fukuda, Shuichi, 5,586,840, Cl. 405-267,000.
 Fukuda, Takeshi: See—
 Shibasaki, Yasuo; Oda, Kiichi; and Fukuda, Takeshi, 5,587,010, Cl. 106-287,170.
 Fukui, Yuji: See—
 Kubouchi, Kenji; Fukui, Yuji; and Inoue, Kunitoshi, 5,586,776, Cl. 277-235,00B.

- Fukunaga, Hideki: See—
 Otoma, Hiromi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, 5,588,016, Cl. 372-46,000.
 Fukuoka, Hiroshi: See—
 Yoshida, Kazuyoshi; Itoh, Hiroshi; Fukuoka, Hiroshi; and Shinehara, Makoto, 5,588,133, Cl. 395-477,000.
 Fukushima, Hisashi; Takeuchi, Tatsuo; Sakoh, Harumi; and Sasanuma, Nobuatsu, to Canon Kabushiki Kaisha. Overlaid image forming apparatus, 5,587,778, Cl. 355-246,000.
 Fukuta, Shinya; and Betsui, Keiichi, to Fujitsu Limited. Field emitter array and cleaning method of the same, 5,587,720, Cl. 345-75,000.
 Fukuyama, Keiji: See—
 Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169,100.
 Fullenkamp, Todd M.: See—
 Dammeier, Ned E.; Fullenkamp, Todd M.; and Stammen, Harold A., 5,586,620, Cl. 187-227,000.
 Fuller, Robert M.; Epler, Frederick A.; and Manowski, Maxwell E., to Accessline Technologies, Inc. Remote access telephone control system, 5,588,037, Cl. 379-57,000.
 Fulmer, Terry M.: See—
 Edwards, Robert W.; Fulmer, Terry M.; and Schultz, Patrick J., 5,586,583, Cl. 141-83,000.
 Funamoto, Kyoto, to Pioneer Electronic Corporation. On-track detecting circuit for use in tracking servo apparatus, 5,587,986, Cl. 369-124,000.
 Fung, Kwok K., to Tyler Refrigeration. Control for commercial refrigeration system, 5,586,444, Cl. 62-117,000.
 Furuhashi, Keizo: See—
 Wakamoto, Akiko; Takahashi, Osamu; Furuhashi, Keizo; and Miura, Akira, 5,587,303, Cl. 435-116,000.
 Furukawa Denchi Kabushiki Kaisha: See—
 Saito, Ken; Hinotsu, Naoyoshi; Sakamoto, Hikaru; and Hoshino, Koichi, 5,586,993, Cl. 29-623,200.
 Furukawa, Ken: See—
 Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58,000.
 Furukawa, Kenji: See—
 Uchida, Manabu; Izumizawa, Takenori; and Furukawa, Kenji, 5,587,444, Cl. 526-247,000.
 Furukawa, Mitsuhito: See—
 Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhito; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219,000.
 Furukawa, Shigeaki: See—
 Yoshioka, Kazumi; Ohta, Takeo; Furukawa, Shigeaki; and Kawahara, Katsumi, 5,587,216, Cl. 428-64,400.
 Furuta, Hitoshi: See—
 Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, 5,587,197, Cl. 426-658,000.
 Furuta, Toshiyuki; Motomura, Shuji; Watanabe, Takahiro; and Stork, David G., to Ricoh Company, Ltd. Signal processing apparatus, 5,588,090, Cl. 395-23,000.
 Furutani, Kiyohiro: See—
 Yasuda, Kenichi; Furutani, Kiyohiro; and Miyamoto, Hiroshi, 5,587,607, Cl. 257-690,000.
 Furuya, Tadashi: See—
 Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiro; Kugo, Harumi; Sakaizawa, Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210,000.
 Furuya, Yuji; and Iino, Kenichi, to Zexel Corporation. Collision type fuel injection nozzle and method of manufacturing the nozzle, 5,586,726, Cl. 239-533,120.
 Fuse, Mario: See—
 Otoma, Hiromi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, 5,588,016, Cl. 372-46,000.
 Fustini, Silvia: See—
 Buzzetti, Franco; Fustini, Silvia; Brasca, Maria G.; and Penco, Sergio, 5,587,385, Cl. 514-309,000.
 Gadelle, André: See—
 Vieil, Eric; Bidan, Gérard; Gadelle, André; and Mendes-Viegas, Maria-Fátima, 5,587,466, Cl. 536-4,100.
 Galambos, Adam F.: See—
 Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E., 5,587,229, Cl. 428-224,000.
 Gale, Allan R.; and Toepfer, Craig B., to Ford Motor Company. Short circuit and ground fault protection for an electrical system, 5,587,864, Cl. 361-44,000.
 Galer, James K.: See—
 Agrawal, Raj K.; Lynam, Niall R.; and Galer, James K., 5,587,236, Cl. 428-334,000.
 Gallick, Robert L.: See—
 Detering, Greig R.; Gallick, Robert L.; and Howell, James F., 5,588,049, Cl. 379-142,000.
 Gallo, Joseph S. Fresh flower holder, 5,586,410, Cl. 47-55,000.
 Gandy, Richard F.: See—
 Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard F., 5,586,911, Cl. 439-607,000.
 Ganem, Charles F. Right angle turning attachment for milling machine, 5,586,382, Cl. 29-560,000.
 Ganesan, Ravi, to Bell Atlantic Network Services, Inc. Method and system for generating pronounceable security passwords, 5,588,056, Cl. 380-4,000.
 Ganesan, Ravi; and Yacobi, Yacov, to Bell Atlantic Network Services, Inc.; and Bell Communications Research, Inc. System and method for identity verification, forming joint signatures and session key agreement in an RSA public cryptosystem, 5,588,061, Cl. 380-30,000.
 Ganter, Bernhard, to Otto Ganter & Co. KG. Spring-loaded press pin, 5,586,852, Cl. 411-353,000.
 Gantner, Gebhard; Dengg, Franz; Ofner, Peter; and Münzenberger, Herbert, to Hilti Aktiengesellschaft. Pipe clamp, 5,586,739, Cl. 248-74,100.
 Gao, Chao: See—
 Chao, James L.; Lee, Yu-Cheun; and Gao, Chao, 5,587,217, Cl. 428-65,400.
 Garbagnati, Carlo: See—
 Coen, Daniele; and Garbagnati, Carlo, 5,586,644, Cl. 198-853,000.
 Garcia, Armando, to International Business Machines Corporation. Universal buffered interface for coupling multiple processors memory units, and I/O interfaces to a common high-speed interconnect, 5,588,122, Cl. 395-250,000.
 Garcia, Graham A.: See—
 Reedy, Ronald E.; Garcia, Graham A.; and Lagnado, Isaac, 5,587,597, Cl. 257-351,000.
 Gardner, Richard K., to Ingersoll-Rand Company. Pneumatic motor, 5,586,480, Cl. 91-169,000.
 Gargoyles, Inc.: See—
 Bernheiser, Charles A., 5,587,747, Cl. 351-105,000.
 Garin-Chesa, Pilar: See—
 Rettig, Wolfgang J.; Scanlan, Matthew J.; Garin-Chesa, Pilar; and Old, Lloyd J., 5,587,299, Cl. 435-69,100.
 Garrett, Scott M., to Motorola, Inc. Thermal performance matched current limiting circuit, and battery using same, 5,587,649, Cl. 323-369,000.
 Garrigus, Darryl E.: See—
 Baker, Anna L.; and Garrigus, Darryl E., 5,587,228, Cl. 428-34,500.
 Garst, Michael E.: See—
 Burke, James A.; Garst, Michael E.; and Wheeler, Larry A., 5,587,376, Cl. 514-249,000.
 Garza, Mario, to LSI Logic Corporation. Method of forming photoresist film exhibiting uniform reflectivity through electrostatic deposition, 5,587,267, Cl. 430-168,000.
 Gas Research Institute: See—
 Fisk, Allan T.; and Freed, David I., 5,586,580, Cl. 138-98,000.
 Sibik, Lee L.; and Berget, Mark D., 5,586,447, Cl. 62-141,000.
 Gasaway, Kim B.: See—
 Shepherd, Marjorie H.; and Gasaway, Kim B., 5,587,006, Cl. 106-1,050.
 Gast, Jürgen: See—
 Simon, Arno; and Gast, Jürgen, 5,587,831, Cl. 359-350,000.
 Gately, Catherine G.: See—
 Riley, David R., 5,586,558, Cl. 128-781,000.
 Gately, Stanley E.: See—
 Riley, David R., 5,586,558, Cl. 128-781,000.
 Gausepohl, Hermann: See—
 Brandstetter, Franz; Gausepohl, Hermann; and Thiele, Reiner, 5,587,423, Cl. 525-52,000.
 Gauthier, Thierry, to Institut Français Du Pétrole. Co-current cyclone separation extractor, 5,586,998, Cl. 55-391,000.
 Gavin, Thomas J.: See—
 Landis, Michael R.; Yeates, Anthony J.; and Gavin, Thomas J., 5,588,148, Cl. 395-601,000.
 Gaviraghi, Giovanni: See—
 Perboni, Alcide; Rossi, Tino; Gaviraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonella, 5,587,374, Cl. 514-210,000.
 Gaydos, George G. Router accessory for producing cuts having a contoured depth, 5,586,591, Cl. 144-145,200.
 Gaztransport & Technigaz: See—
 Jean, Pierre; and Chauvin, Jean-Michel, 5,586,513, Cl. 114-74,00A.
 Gazyakan, Unal: See—
 Bailly, Gerhard; Baasch, Detlef; and Gazyakan, Unal, 5,586,470, Cl. 74-477,000.
 Gazzotti, Ornella: See—
 De Haen, Christoph; Uggeri, Fulvio; Gazzotti, Ornella; and Brocchetta, Marino, 5,587,487, Cl. 548-561,000.
 GEC Alstom T & D SA: See—
 Perret, Michel, 5,587,571, Cl. 218-60,000.
 Geen, Graham R.: See—
 Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance, 5,587,483, Cl. 548-252,000.
 Geibel, Wolfram: See—
 Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401,000.
 Geile, Michael J.: See—
 Dapper, Mark J.; Geile, Michael J.; and Carlin, Barry W., 5,588,022, Cl. 375-216,000.
 Geisler, Joerg-Peter: See—
 Dreischhoff, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoene, Michael; and Stengel-Rutkowski, Bernhard, 5,587,409, Cl. 523-404,000.
 Geiss, Michael J., II. Multi-purpose, mobile storage cabinet with horizontally and vertically adjustable shelf structure, 5,586,816, Cl. 312-301,000.
 Geisselmann, Heribert: See—
 Graudejus, Wolfgang; Briem, Eberhard; Haettich, Wilhelm; and Geisselmann, Heribert, 5,586,663, Cl. 209-582,000.

- Gemplus: See—
Serra, Didier, 5,587,578, Cl. 235-492,000.
- Gemplus Card International: See—
Lernux, Jean-Yves, 5,588,146, Cl. 395-601,000.
- Genentech, Inc.: See—
Goeddel, David V.; Kohr, William J.; Pennica, Diane; and Vohar, Gordon A., 5,587,159, Cl. 424-94,640.
- General Electric Company: See—
Ali, Irfan, Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koipillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346,000.
- Bagepalli, Bharat S.; and Dinc, Osman S., 5,586,773, Cl. 277-167,500.
- Berkcan, Erugrul, and Seymour, Raymond K., 5,587,651, Cl. 324-127,000.
- Berkcan, Erugrul; Seymour, Raymond K.; and Grzelecki, John C., 5,587,652, Cl. 324-127,000.
- Bessler, Warren F., 5,586,445, Cl. 62-126,000.
- Borsboom, Antonius H.; Gennari, Anthony A.; Rudolph, Kenneth G.; and Zuber, Peter J., 5,586,675, Cl. 220-6,000.
- Fiddes, Neil G.; King, Christopher G.; Mantone, Anthony; and Shaffer, Frank D., 5,586,712, Cl. 228-5,700.
- Kelaita, Joseph B., Jr.; and Collin, Edwin J., 5,587,570, Cl. 200-50,010.
- Kingsley, Jack D.; and Pussini, George E., 5,587,591, Cl. 257-59,000.
- Korowski, Victor J.; Reluzco, George; Robertson, Kenneth J.; and Adamowski, Paul L., 5,586,864, Cl. 415-209,200.
- Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634,000.
- Paul, William C.; and Sietoff, Ronald F., 5,587,206, Cl. 427-558,000.
- Smith, John M.; Schneider, David A.; Dauseh, Mark E.; and Whipple, Walter, III, 5,586,567, Cl. 134-57,000.
- General Motors Corporation: See—
Borlinghaus, Hans J.; Nini, James P., and Blake, Thomas B., 5,586,740, Cl. 248-157,000.
- Tibbets, Gary G.; Nazri, Gholam-Abbas; and Howie, Blake J., 5,587,257, Cl. 429-218,000.
- General Railway Signal Corporation: See—
van Alstine, Daniel W.; and Eggebrecht, Charles M., 5,586,737, Cl. 246-448,000.
- Genna, Robert A. Automatic tire pressure control system for a vehicle, 5,587,698, Cl. 340-442,000.
- Gennari, Anthony A.: See—
Borsboom, Antonius H.; Gennari, Anthony A.; Rudolph, Kenneth G.; and Zuber, Peter J., 5,586,675, Cl. 220-6,000.
- Gerbas, Dennis G.: See—
Auty, Ronald E.; and Gerbas, Dennis G., 5,587,781, Cl. 355-301,000.
- Gergely, Gerhard, Gergely, Thomas; and Gergely, Irmgard, to Gerhard Gergely, Pharmaceutical formulation in the form of an effervescent and/or disintegrating tablet or of instant granulate, and process for their preparation, 5,587,179, Cl. 424-466,000.
- Gergely, Irmgard: See—
Gergely, Gerhard, Gergely, Thomas; and Gergely, Irmgard, 5,587,179, Cl. 424-466,000.
- Gergely, Thomas: See—
Gergely, Gerhard, Gergely, Thomas; and Gergely, Irmgard, 5,587,179, Cl. 424-466,000.
- Gerhard Gergely: See—
Gergely, Gerhard, Gergely, Thomas; and Gergely, Irmgard, 5,587,179, Cl. 424-466,000.
- Gershon, David: See—
Dori, Zvi; and Gershon, David, 5,587,395, Cl. 514-501,000.
- Gesensway, David: See—
Putnam, Matthew D., and Gesensway, David, 5,586,985, Cl. 606-69,000.
- Gestalt Technologies, Incorporated: See—
Bai, Baocheng; Guner, Mahmut; Lu, Duoqia; Rosenblitt, David A.; and Stuck, Kaaren L., 5,588,138, Cl. 395-497,040.
- GF-OTO Melara Breda Bresciana S.r.l.: See—
Iardella, Carlo A.; and Agrusa, Mauro, 5,587,718, Cl. 342-443,000.
- Gibbon, Michael A.; Maxwell, Ian; and Toporkiewicz, Marian, to IMAX Corporation, Film transport mechanism, 5,587,750, Cl. 352-184,000.
- Gibbs, John A.: See—
Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., 5,587,932, Cl. 364-556,000.
- Gideon, Richard W.: See—
Desai, Dhimat R.; Tayse, Louis C.; and Gideon, Richard W., 5,587,634, Cl. 318-257,000.
- Gietman, Peter J., Jr.: See—
Saindon, Stephen A.; Gietman, Peter J., Jr.; and Nagel, Nicholas J., 5,587,032, Cl. 156-64,000.
- Gilat, Chaim: See—
Eisen, Yosef; Gilat, Chaim; and Keinan, Giora, 5,587,585, Cl. 250-370,000.
- Gilbert, Ronald E.; Mordue, George S.; and Vild, Chris T., to Metallurgy Systems Co., L.P. Molten metal pump with vane impeller, 5,586,863, Cl. 415-200,000.
- Gillespie, Harvey D. Yieldable cable bolt, 5,586,839, Cl. 405-259,100.
- Gillette Company, The: See—
Angelone, Philip P., Jr.; Karassik, Nancy M.; and Grace, William R., 5,587,153, Cl. 424-66,000.
- Girotti, Michael: See—
Kamjo, Wajuh; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7,000.
- Giuliani, Ferdinando C.: See—
Krapcho, A. Paul; Hacker, Miles P.; Cavalletti, Ennio; and Giuliani, Ferdinando C., 5,587,382, Cl. 514-290,000.
- Glasner, Alfred: See—
Bobik, Michael; Lindbauer, Ralf L.; and Glasner, Alfred, 5,587,138, Cl. 423-242,100.
- Glaunsinger, William: See—
Bao, Qingcheng; Sorensen, Ian; and Glaunsinger, William, 5,587,130, Cl. 422-88,000.
- Glaxo SpA: See—
Perboni, Alcide; Rossi, Tino; Gavraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonella, 5,587,374, Cl. 514-210,000.
- Glaxo Wellcome Inc.: See—
Miller, Alistair A.; Nobbs, Malcolm S.; Hyde, Richard M.; and Leach, Michael J., 5,587,380, Cl. 514-275,000.
- Glaze, Bradley S.; and Warner, Kenneth R., to Frontier Manufacturing Company, Compost mixing and aerating apparatus, 5,586,731, Cl. 241-56,000.
- Gleason Works, The: See—
Suwijn, Paul W., 5,586,848, Cl. 409-137,000.
- Gledde, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., to Canada, Her Majesty the Queen in right of; and Philom Bios Inc. Method of preparing a seed treatment composition, 5,586,411, Cl. 47-57,600.
- Glenn, William E.: See—
Schneider, John K.; and Glenn, William E., 5,587,533, Cl. 73-614,000.
- Glew, Andrew F.: See—
Abramson, Jeffrey M.; Akkary, Haitham; Glew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395-376,000.
- Globe International Inc.: See—
Zabron, Florian S.; Marlette, Mary E.; Rothman, Miles S.; and Hanrahan, William D., 5,586,643, Cl. 198-853,000.
- Globe Products Inc.: See—
Dolgas, Patrick A.; Walton, Ballard E.; and Staton, Larry E., 5,586,383, Cl. 29-596,000.
- Newman, Lawrence E., 5,586,384, Cl. 29-596,000.
- Glover, Stephen E.: See—
Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenith W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710,000.
- Gobbi, Jose-Maria: See—
Johansson, Ted; and Gobbi, Jose-Maria, 5,587,333, Cl. 437-60,000.
- Gocho, Yoshihiro: See—
Mizukami, Masamichi; Yui, Tomoyuki; Arai, Yoshihisa; and Gocho, Yoshihiro, 5,587,106, Cl. 252-299,610.
- Goda, Yoshimasa, to Sony Corporation, Object lens holder, 5,587,845, Cl. 359-819,000.
- Godau, Claus: See—
Dreischhoff, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoenel, Michael; and Stengel-Rukowski, Bernhard, 5,587,409, Cl. 523-404,000.
- Godthardt, Lutz-Peter: See—
Eisen, Norbert; Godthardt, Lutz-Peter; and Haas, Peter, 5,587,117, Cl. 264-45,700.
- Goeddel, David V.; Kohr, William J.; Pennica, Diane; and Vohar, Gordon A., to Genentech, Inc. Human tissue plasminogen activator, 5,587,159, Cl. 424-94,640.
- Gohil, Kishor C.: See—
Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P., 5,587,454, Cl. 530-324,000.
- Gold, Larry: See—
Allen, Patrick; and Gold, Larry, 5,587,468, Cl. 536-22,100.
- Goldberg, Paul R.; and Richards, Martin J., to Dolby Laboratories Licensing Corporation, Apparatus and method for reading motion picture film photographic dye soundtracks, 5,587,749, Cl. 352-27,000.
- Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., to Cornell Research Foundation, Inc. Single phase solids containing metallopolymers, 5,587,422, Cl. 524-779,000.
- Goldman, Lee J.: See—
Kuhn, James O.; and Goldman, Lee J., 5,587,099, Cl. 219-728,000.
- Goldsmith, Daniel S.: See—
Dombrowski, Larry A.; Goldsmith, Daniel S.; Goldsmith, Judith; and Goldsmith, Walter J., 5,586,934, Cl. 454-309,000.
- Goldsmith, Judith: See—
Dombrowski, Larry A.; Goldsmith, Daniel S.; Goldsmith, Judith; and Goldsmith, Walter J., 5,586,934, Cl. 454-309,000.
- Goldsmith, Walter J.: See—
Dombrowski, Larry A.; Goldsmith, Daniel S.; Goldsmith, Judith; and Goldsmith, Walter J., 5,586,934, Cl. 454-309,000.
- Goldstar Co., Ltd.: See—
Lee, Heun J.; and Joe, Moon J., 5,588,073, Cl. 382-187,000.
- Lee, Je H.; Kim, Soo K.; Woo, Sang J.; and Yang, Tae S., 5,587,789, Cl. 386-68,000.
- Goldstein, Lawrence: See—
Roy, Timothy A.; Mackerer, Carl R.; and Goldstein, Lawrence, 5,587,324, Cl. 436-183,000.

- Golicz, Roman M., to Roll Systems, Inc. Power stapler, 5,586,710, Cl. 227-155,000.
- Golz, Thomas M.: See—
Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634,000.
- Gomi, Masao: See—
Lee, Ghai K.; and Gomi, Masao, 5,587,729, Cl. 347-32,000.
- Gonon, Bertrand: See—
Lemaire, Ivan; and Gonon, Bertrand, 5,586,973, Cl. 604-19,000.
- Goodman, Milton. Hand held teach and test device, 5,586,889, Cl. 434-327,000.
- Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., to Credit Managers Association of California, Method of inactivation of viral and bacterial blood contaminants, 5,587,490, Cl. 549-282,000.
- Gordon, Bruce R.: See—
Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., 5,587,366, Cl. 514-78,000.
- Gordon, David P.: See—
Hahnen, Kevin F.; Farkas, Laszlo; and Gordon, David P., 5,586,990, Cl. 606-170,000.
- Gornstein, Viktor L., to Philips Electronics North America Corporation, Transformerless high-voltage generator circuit, 5,587,629, Cl. 315-200,000.
- Gorodetsky, Victor V.; Nebuchilov, Vladimir A.; and Krolotyrkin, Y. M., to Karpov Institute of Physical Chemistry, Electrode and method of preparation thereof, 5,587,058, Cl. 204-290,000.
- Gorokhovskiy, Vladimir I. Arc assisted CVD coating and sintering method, 5,587,207, Cl. 427-571,000.
- Goronkin, Herbert: See—
Shen, Jun; and Goronkin, Herbert, 5,587,944, Cl. 365-175,000.
- Gosch, Andreas: See—
Salzburg, Herbert; Steinhoff, Georg; Gosch, Andreas; and Hufen, Gerd, 5,587,511, Cl. 562-513,000.
- Goss, William: See—
Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364-510,000.
- Gotch, Henry E.; and Hyde, Roger J., to Alumasc Limited, Combination dispense tap and customer information display, 5,586,691, Cl. 222-113,000.
- Goto, Chiaki: See—
Okazaki, Yoji; Goto, Chiaki; Hyuga, Hiroaki; and Harada, Akinori, 5,588,014, Cl. 372-22,000.
- Goto, Fumio, to Kabushiki Kaisha Sato, Label cassette retaining device for labeler, 5,587,044, Cl. 156-577,000.
- Goto, Hiroshi: See—
Ishida, Kiyoshi; and Goto, Hiroshi, 5,587,735, Cl. 348-14,000.
- Goto, Masami: See—
Mura, Yoshihiro; and Goto, Masami, 5,586,733, Cl. 242-125,200.
- Goto, Tetsuro, to Nikon Corporation, Camera capable of performing divisional photometry, 5,587,765, Cl. 396-234,000.
- Goubely, Aimé: See—
Bennardo, Gilbert; and Goubely, Aimé, 5,586,747, Cl. 251-129,180.
- Gould, Eva: See—
Punto, Louis; Porini, Chini; Duque, Pilar; and Gould, Eva, 5,587,149, Cl. 424-59,000.
- Gould, Michael N.; Crowell, Pamela L.; Elson, Charles E.; and Clark, Steven S., to Wisconsin Alumni Research Foundation, Regression of mammalian leukemia cell tumors, 5,587,402, Cl. 514-729,000.
- Gozdz, Antoni S.; Schmutz, Caroline N.; and Warren, Paul C., to Bell Communications Research, Inc. Low resistance rechargeable lithium-ion battery, 5,587,253, Cl. 429-192,000.
- GPS Mobile, Inc.: See—
Lewis, Peter T., 5,587,715, Cl. 342-357,000.
- Grabiak, Matthias: See—
Kumar, Prathmesh; Grabiak, Matthias; and Ivanek, Ivan, 5,588,108, Cl. 395-348,000.
- Grace, William R.: See—
Angelone, Philip P., Jr.; Karassik, Nancy M.; and Grace, William R., 5,587,153, Cl. 424-66,000.
- Graco Children's Products: See—
Nielsen, Robert A.; and Pizzi, Vladimir, 5,586,345, Cl. 5-99,100.
- Graef, Dieter O. Apparatus for the wetting of cereals with a liquid, 5,586,492, Cl. 99-516,000.
- Graham, Martin H.; and Taylor, Matthew, to Tut Systems, Inc. Common mode current cancellation in twisted pairs, 5,587,692, Cl. 333-12,000.
- Grano Environmental Corporation: See—
Keith, Robert C., 5,587,053, Cl. 202-172,000.
- Keith, Robert C., 5,587,054, Cl. 202-182,000.
- Graudejus, Wolfgang; Briem, Eberhard; Haettich, Wilhelm; and Geisselmann, Heribert, to H.F. & Ph.F. Reemismia GmbH & Co. Processing for the optical sorting of bulk material, 5,586,663, Cl. 209-582,000.
- Greaves, Brian; Poole, Stephen C.; Hwa, Chih M.; and Fan, Joseph C., to W. R. Grace & Co.-Conn. Method for inhibition of oxygen corrosion in aqueous systems by the use of a tannin activated oxygen scavenger, 5,587,109, Cl. 252-392,000.
- Green, Ian: See—
Mann, Philip A.; and Green, Ian, 5,587,000, Cl. 65-260,000.
- Greene, Benjamin I.; Narayanan, Chellappan; and Presby, Herman M., to Lucent Technologies Inc. Radiolytic method for making a mode-field transforming optical waveguide, 5,588,085, Cl. 385-123,000.
- Greene, Robert H. Composite filled hollow structure, 5,587,035, Cl. 156-187,000.
- Greenwald, Kenneth. Bottle security system, 5,586,670, Cl. 215-207,000.
- Greenwich Industries, L.P.: See—
Hergott, Arthur, 5,586,806, Cl. 297-188,110.
- Greenwood, Julie A. Personal attack/help alarm, 5,587,970, Cl. 368-10,000.
- Gregg, David P., to DiscoVision Associates, Optical tape cartridge having improved tape movement mechanism, 5,587,993, Cl. 369-291,000.
- Gridnev, Alexei A.; and Ittel, Steven D., to Du Pont de Nemours, E. I., and Company, Synthesis of terminally unsaturated oligomers, 5,587,431, Cl. 525-269,000.
- Griepentrog, Dal F.; and Sendelweck, Gene K., to Thomson Consumer Electronics, Inc. Adjustment of scan velocity modulation concurrent with the amount of transition rise time, pre-shoot, and overshoot of a video signal, 5,587,745, Cl. 348-626,000.
- Griesbach, Henry L.; Creagan, Christopher C.; and Gwaltney, Sharon W., to Kimberly-Clark Corporation, Knit-like nonwoven composite fabric, 5,587,225, Cl. 428-198,000.
- Grieser-Schmitz, Stefan: See—
Schneider, Thomas; Grieser-Schmitz, Stefan; and Walther, Michael, 5,587,661, Cl. 324-556,000.
- Grimaud, Jean-Jacques G.: See—
Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., 5,588,139, Cl. 395-500,000.
- Grimault, Jean-Luc: See—
Le Corre, Hervé; Grimault, Jean-Luc; and Boudet, François, 5,587,809, Cl. 358-405,000.
- Grimberg, Georges S. Medicament having a pediatric presentation for facilitating the ingestion thereof by a child, 5,587,177, Cl. 424-454,000.
- Grondalski, Richard A.: See—
Acosta, Phyllis J. B.; Grondalski, Richard A.; Liebrecht, Jeffrey W.; and Reynolds, Patricia A., 5,587,399, Cl. 514-561,000.
- Gross, Clifford M., to BCAM International, Inc. Support enhancing device and associated method, 5,587,933, Cl. 364-558,000.
- Gross, Clifford M.: See—
Nelson, Arthur J.; and Gross, Clifford M., 5,586,557, Cl. 128-779,000.
- Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Coners, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., to Du Pont de Nemours, E. I., and Company, Process for preparing multiple color proofs, 5,587,272, Cl. 430-257,000.
- Groten, Maurice, to U.S. Philips Corporation, Optoelectronic semiconductor device, system for optical glass fibre communication having such a device, semiconductor diode laser for use in such a device, and method of manufacturing such a device, 5,588,017, Cl. 372-49,000.
- Grothe, Hermann: See—
Tolle, Karl-Heinz; and Grothe, Hermann, 5,586,361, Cl. 16-51,000.
- Group-J, Inc.: See—
Thomas, Betty M., 5,586,679, Cl. 220-410,000.
- Grreat Creations, Inc.: See—
Eby, Devon; Love, Dale; and Reed, James L., 5,586,373, Cl. 24-525,000.
- Gruhle, Andreas: See—
König, Ulf; Gruhle, Andreas; Schuppen, Andreas; Kihbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-31,000.
- Gründl, Andreas; Boh, Alexander; and Boh, Konstantin. Method and apparatus for moving an endoscope along a canal-shaped cavity, 5,586,968, Cl. 600-114,000.
- Grundler, Gerhard: See—
Kohl, Bernhard; Senn-Bilfinger, Jörg; and Grundler, Gerhard, 5,587,389, Cl. 514-338,000.
- Grzelecki, John C.: See—
Berkcan, Erugrul; Seymour, Raymond K.; and Grzelecki, John C., 5,587,652, Cl. 324-127,000.
- Gschöbmann, Günther: See—
Bielig, Peter M.; Brähler, Klaus; and Gschöbmann, Günther, 5,587,865, Cl. 361-45,000.
- Gsell, Thomas C.: See—
Pall, David B.; Gsell, Thomas C.; Matkovich, Vlado I.; and Bormann, Thomas, 5,587,070, Cl. 210-202,000.
- Guezennec, Yannick; Koziat, Joseph; and Thiry, Michel, to Ricard, Pernod. Dietary drink intended to enable sustained activity, 5,587,190, Cl. 426-2,000.
- Guillermo, Pedro M. Apparatus and method for replacing the diverter valve assembly in a faucet, 5,586,571, Cl. 137-315,000.
- Gulachenski, Alan M.: See—
Pirani, Gary P.; Gulachenski, Alan M.; and Kelly, David J., 5,586,891, Cl. 439-71,000.
- Guner, Mahmut: See—
Bai, Baocheng; Guner, Mahmut; Lu, Duoqia; Rosenblitt, David A.; and Stuck, Kaaren L., 5,588,138, Cl. 395-497,040.
- Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, to Asahi Glass Company Ltd. LCD device including an illumination device having a polarized light separating sheet between a light guide and the display, 5,587,816, Cl. 349-62,000.
- Gunter, Carl V.: See—

- Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634.000.
- Gupta, Rajiv: See—
Karp, Alan H.; Hao, Ming C.; and Gupta, Rajiv, 5,588,117, Cl. 395-200.030.
- Guttig, Karl M.: See—
Vogley, Wilbur C.; Balistreri, Anthony M.; Guttig, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Guyonnet, Xavier J.A.: See—
Bertrand, Jean-Louis; Charier, Gilles A.; Guyonnet, Xavier J.A.; and Picard, Jean-Louis, 5,586,860, Cl. 415-115.000.
- Gwaltney, Sharon W.: See—
Griesbach, Henry L.; Creagan, Christopher C.; and Gwaltney, Sharon W., 5,587,225, Cl. 428-198.000.
- H.F. & Ph.F. Roemtsma GmbH & Co.: See—
Graudejus, Wolfgang; Briem, Eberhard; Haetich, Wilhelm; and Geiselmann, Herbert, 5,586,663, Cl. 209-582.000.
- H-Tech, Inc.: See—
Lynch, Gerard J.; and Quinn, Joseph, 5,587,074, Cl. 210-411.000.
- H2Oil, Inc.: See—
Burns, Thomas J., 5,587,065, Cl. 210-104.000.
- Haage, Manfred, to Fischerwerke, Artur Fischer GmbH & Co KG: Prestress-monitoring element for screw-type anchors, 5,586,851, Cl. 411-10.000.
- Haas, Hanns-Otto: See—
Beaumont, Hendrikus; Haas, Hanns-Otto; Wiese, Holger; and Lindner, Bernd, 5,586,499, Cl. 101-211.000.
- Haas, Peter: See—
Eisen, Norbert; Godthardt, Lutz-Peter; and Haas, Peter, 5,587,117, Cl. 264-45.700.
- Habata, Shinichi, to NEC Corporation: Hardware arrangement for controlling multiple overlapping windows in a computer graphic system, 5,588,106, Cl. 395-340.000.
- Habazaki, Hiroki: See—
Hashimoto, Koji; Habazaki, Hiroki; Mrowec, Stanislaw; and Danielewski, Marek, 5,587,028, Cl. 148-403.000.
- Haber, Terry M.; Smedley, William H.; and Foster, Clark B., to Hahley Medical Technology Corporation: Golf club having a segmented, variable position grip assembly, 5,586,946, Cl. 473-295.000.
- Häberle, Karl: See—
Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, 5,587,421, Cl. 524-591.000.
- Habley Medical Technology Corporation: See—
Haber, Terry M.; Smedley, William H.; and Foster, Clark B., 5,586,946, Cl. 473-295.000.
- Hacker, Miles P.: See—
Krapcho, A. Paul; Hacker, Miles P.; Cavalletti, Ennio; and Giuliani, Ferdinando C., 5,587,382, Cl. 514-290.000.
- Hackett, Roger W.: See—
Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borsum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.
- Haddock, Richard S.: See—
Heisler, Kurt W.; and Haddock, Richard S., 5,586,699, Cl. 224-628.000.
- Haetich, Wilhelm: See—
Graudejus, Wolfgang; Briem, Eberhard; Haetich, Wilhelm; and Geiselmann, Herbert, 5,586,663, Cl. 209-582.000.
- Hagen, Urs A.; Schmid, Martin; and Owen, Gwyn P., to Services Algou International Anstalt: Relating to boarding ramps, 5,586,516, Cl. 114-362.000.
- Haggag, Hosam: See—
Chi, Min-Hwa; Bergemont, Albert; and Haggag, Hosam, 5,587,596, Cl. 257-223.000.
- Hagihara, Hayato; and Hongu, Takahiro, to NEC Corporation: Image processing apparatus for identifying character, photo and dot images in image area, 5,587,808, Cl. 358-462.000.
- Hagiwara, Haruo: See—
Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyairi, Yoshio; Hattori, Toshio; and Hagiwara, Haruo, 5,586,456, Cl. 68-18.00R.
- Hagiwara, Masao: See—
Takebe, Makoto; and Hagiwara, Masao, 5,587,995, Cl. 370-248.000.
- Hahnen, Kevin F.; Farkas, Laszlo; and Gordon, David P., to Symbiosis Corporation: Endosurgical instrument with a radially movable end effector, 5,586,990, Cl. 606-170.000.
- Haida, Reinhard: See—
Pohmer, Klaus; Weber, Rainer; Dorzbach-Lange, Cornelia; Haida, Reinhard; and Moretto, Hans-Heinrich, 5,587,513, Cl. 564-84.000.
- Hajmichal, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Srekely, Istvan; Marmarosy né Kellner, Katalin; and Ori, Janos, to Chinoir Gyo-gyszter es Vegyeszeti Termek Gyar RT: Acaricidally active tetrazine derivatives, 5,587,370, Cl. 514-183.000.
- Hakimi, Farhad: See—
Hakimi, Hosain; and Hakimi, Farhad, 5,587,827, Cl. 359-249.000.
- Hakimi, Hosain; and Hakimi, Farhad: Apparatus for compensating chromatic and polarization dispersion and frequency chirp in fiber optics and for pulse compression in laser systems, 5,587,827, Cl. 359-249.000.
- Haldemann, Pol N.: Fencing tool and method of operation, 5,586,584, Cl. 140-123.500.
- Haldor Topsoe A/S: See—
Dannevang, Flemming, 5,587,134, Cl. 423-237.000.
- Haley, John E.: See—
Seay, O. Elwyn; Nickles, Stephen K.; and Haley, John E., 5,586,669, Cl. 213-43.000.
- Halili, Edgardo C.; and Mastrototaro, John J., to MiniMed Inc.: Transcutaneous sensor insertion set, 5,586,553, Cl. 128-635.000.
- Hall, John C.: See—
Julow, Jay K.; DeRegnaucourt, Robert A.; and Hall, John C., 5,586,625, Cl. 188-218.00R.
- Hallam, Christopher P., to Concept Packaging Limited: Carton and carton hinge construction, 5,586,717, Cl. 229-116.100.
- Hallmark, Timothy M.: Multiple sport training and exercise apparatus, 5,586,962, Cl. 482-129.000.
- Halsey, James H.; Juds, Scott; and Erwin, James W., to IDX, Inc.: Vending apparatus and method having improved reliability, 5,586,684, Cl. 221-90.000.
- Hamada, Nozomu, heir: See—
Hamada, Susumu, deceased; and Araki, Dai, 5,587,918, Cl. 364-488.000.
- Hamada, Susumu, deceased (by Nozomu Hamada, heir); and Araki, Dai, to Kabushiki Kaisha Toshiba: Circuit pattern comparison apparatus, 5,587,918, Cl. 364-488.000.
- Hamamatsu Photonics K.K.: See—
Ikeda, Tomoyuki; Ito, Yoshinobu; and Matui, Ryotaro, 5,587,625, Cl. 313-613.000.
- Hambitzer, Günther; Böke, Winfried; and Oertel, Armin, to Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V.: Waste water purification process and apparatus, 5,587,064, Cl. 205-742.000.
- Hamilton, Peter W.: See—
Thomas, Hewin N.; Haney, Jack E.; and Hamilton, Peter W., 5,586,671, Cl. 215-209.000.
- Hammer, David R.; Sego, Kenneth W., Jr.; and Labun, Lance C., to Simula Inc.: Vacuum packaged escape slide, 5,586,615, Cl. 182-48.000.
- Hampel, Manfred: See—
Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Scheiberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63.000.
- Hamper, Bruce C.: See—
Chupp, John P.; Hamper, Bruce C.; and Wettach, Richard H., 5,587,485, Cl. 548-377.100.
- Hampo, Richard J.; Marko, Kenneth A.; and Bryant, Bruce D., to Ford Motor Company: Misfire detection assembly, 5,587,524, Cl. 73-116.000.
- Hanawa, Ryotaro: See—
Tomioka, Jun; Uetani, Yasunori; Nakanishi, Hirotochi; Hanawa, Ryotaro; and Ida, Ayako, 5,587,492, Cl. 549-406.000.
- Hand, Barry D.: See—
Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenith W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
- Haney, Jack E.: See—
Thomas, Hewin N.; Haney, Jack E.; and Hamilton, Peter W., 5,586,671, Cl. 215-209.000.
- Hang, Chang C.: See—
Ho, Weng K.; Hang, Chang C.; and Wojsznis, Wilhelm K., 5,587,899, Cl. 364-157.000.
- Hank, Mark A.: See—
Streisel, Robert C.; Hank, Mark A.; Mulcahy, Leo T.; and Peterson, Ralph S., 5,587,048, Cl. 162-7.000.
- Hannant, Keith, to Smiths Industries Public Limited Company: Trolleys, 5,586,349, Cl. 5-614.000.
- Hanning, John R.; and Olmsted, Daniel C., to Parker-Hannifin Corporation: Pneumatic pressure regulator, 5,586,569, Cl. 137-116.500.
- Hanrahan, William D.: See—
Zabron, Florian S.; Marlette, Mary E.; Rothman, Miles S.; and Hanrahan, William D., 5,586,643, Cl. 198-853.000.
- Hansen, Paul, to Xerox Corporation: Misfeed detector for a stack of different weight sheets, 5,586,755, Cl. 271-9.060.
- Hansen, Peter D.; and Bristol, Edgar H., to Foxboro Company, The: Self-tuning controller, 5,587,896, Cl. 364-148.000.
- Hansler, Richard L.: See—
Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golz, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., 5,587,626, Cl. 313-634.000.
- Hanson, G. Herbert: Self-ligating orthodontic brackets, 5,586,882, Cl. 433-13.000.
- Hao, Ming C.: See—
Karp, Alan H.; Hao, Ming C.; and Gupta, Rajiv, 5,588,117, Cl. 395-200.030.
- Happ, Lawrence R.; Korczynski, Jacek; Bailey, William R.; and Lesesky, Alan, to Cooper Industries, Inc.: Vehicle electric power distribution system, 5,587,890, Cl. 361-826.000.
- Hara, Takefumi: See—
Ikeda, Hideo; Shuto, Sadanobu; and Hara, Takefumi, 5,587,280, Cl. 430-567.000.
- Harada, Akinori: See—

- Okazaki, Yoiji; Goto, Chiaki; Hyuga, Hiroaki; and Harada, Akinori, 5,588,014, Cl. 372-22.000.
- Harada, Hiroyuki: See—
Kubo, Kohji; Nezu, Shoichi; Ishibashi, Fumio; Harada, Hiroyuki; and Shigematsu, Yuji, 5,587,247, Cl. 428-523.000.
- Harada, Masahiro; and Inaba, Yasuo, to Mitsubishi Gas Chemical Co., Inc.: Copolyamide production method, 5,587,447, Cl. 528-347.000.
- Harada, Mikio: See—
Kurasawa, Koichi; Harada, Mikio; and Ito, Takaaki, 5,587,867, Cl. 361-118.000.
- Harada, Toshiharu: See—
Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323.000.
- Hardell, William R., Jr.; and Qureshi, Amjad Z., to International Business Machines Corporation: Parallel architecture error correction and conversion system, 5,588,010, Cl. 371-37.600.
- Hardy, Douglas A.: See—
Altschuler, Barry N.; Hardy, Douglas A.; Stephens, James A.; and Kish, Joseph, III, 5,588,062, Cl. 380-30.000.
- Hare, Duncan: See—
Vincet, Ronald; Sprague, Marshall; and Hare, Duncan, 5,588,119, Cl. 395-200.150.
- Harkins, Michael T.: Electrical power supply with single output from range of input voltages, 5,587,895, Cl. 363-89.000.
- Harkness, Alex W.: See—
Bevilacqua, Bruce W.; Malandra, Louis J.; Meuschke, Robert E.; and Harkness, Alex W., 5,588,031, Cl. 376-287.000.
- Harmon Industries, Inc.: See—
Mollet, Samuel R., 5,586,736, Cl. 246-194.000.
- Harms, Ralf H.: See—
Fabricius, Dietrich M.; Harms, Ralf H.; and Welter, James J., 5,587,482, Cl. 548-179.000.
- Harnik, Zvika: See—
Segal, Jacob; Ben-Moshe, Josef; Weinstock, Zvika; and Harnik, Zvika, 5,588,151, Cl. 395-800.000.
- Harrington, Steven J., to Xerox Corporation: Color mapping to preserve detail, 5,588,093, Cl. 395-109.000.
- Harris Corporation: See—
Dennis, Timothy A., 5,587,103, Cl. 252-79.300.
- Harris, Matthew B.: See—
Kelley, Arthur W.; and Harris, Matthew B., 5,587,662, Cl. 324-713.000.
- Harris, Olan D.: Method and apparatus for filling structural holes, 5,586,420, Cl. 52-514.500.
- Harrold, Jonathan: See—
May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harrold, Jonathan, 5,587,820, Cl. 359-72.000.
- Harsco Corporation: See—
Madison, Harry; and Tilley, Jeffrey L., 5,586,507, Cl. 105-215.200.
- Hartenstein, John R.; and Dussinger, Peter M., to Thermacore, Inc.: Combined solar and gas heater, 5,586,549, Cl. 126-635.000.
- Hartigan, Joseph P.: See—
Vogley, Wilbur C.; Balistreri, Anthony M.; Guttig, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Hartman, Michael O.; Kinder, Dale J.; Rainey, Randy E.; Helfmich, Arthur R.; and Willis, Daniel E., to Hartman, Michael O.: Water distilling apparatus and method, 5,587,055, Cl. 203-1.000.
- Harvey, Thomas B., III: See—
So, Franky; Shi, Song Q.; and Harvey, Thomas B., III, 5,587,589, Cl. 257-40.000.
- Harvill, Young L.: See—
Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., 5,588,139, Cl. 395-500.000.
- Hasebe, Hiroshi: See—
Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Hasegawa, Rei: See—
Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shinichi; and Kawata, Yasushi, 5,587,819, Cl. 349-106.000.
- Hasegawa, Toshinori: See—
Asai, Isao; and Hasegawa, Toshinori, 5,586,428, Cl. 57-269.000.
- Hasegawa, Toshiro; Shimoda, Kazuhiko; Makino, Kunio; and Tomioka, Mituo, to Matsushita Electric Industrial Co., Ltd.: Method for manufacture of a lead acid storage battery, 5,586,994, Cl. 29-623.500.
- Hashimoto, Hiroyuki, to Canon Kabushiki Kaisha: Ion implanting apparatus and ion implanting method, 5,587,587, Cl. 250-492.210.
- Hashimoto, Kenji; and Matsumura, Yoshito, to Sanden Corporation: Reed valve arrangement for a reciprocating compressor, 5,586,874, Cl. 417-569.000.
- Hashimoto, Koji; Habazaki, Hiroki; Mrowec, Stanislaw; and Danielewski, Marek, to Hashimoto, Koji; and YKK Corporation: Amorphous alloys resistant to hot corrosion, 5,587,028, Cl. 148-403.000.
- Hashimoto, Masashi; Frantz, Gene A.; Moravec, John V.; and Dolait, Jean-Pierre, to Texas Instruments Incorporated: Memory circuit accommodating both serial and random access including an alternate address buffer register, 5,587,962, Cl. 365-230.090.
- Hashimoto, Seiji: See—
Mihara, Akio; and Hashimoto, Seiji, 5,587,814, Cl. 358-512.000.
- Hashimoto, Takao: See—
Yamanaka, Shizuo; and Hashimoto, Takao, 5,587,017, Cl. 118-424.000.
- Hashimoto, Takatsugu: See—
Nakane, Shinsuke; Kanou, Kazuhiko; and Hashimoto, Takatsugu, 5,587,417, Cl. 524-495.000.
- Hashimoto, Toru: See—
Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhisa; and Kasai, Satoshi, 5,587,909, Cl. 364-431.080.
- Haskell, Christopher F.: Holder for scorecards, 5,586,707, Cl. 224-684.000.
- Hassan, Amer A.: See—
Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
- Hatanaka, Fumio: See—
Nakamatsu, Yasuhiro; Otsuka, Masao; Hatanaka, Fumio; and Tsunoda, Arihiro, 5,586,757, Cl. 271-145.000.
- Hatanaka, Kazuhisa, to Kabushiki Kaisha Toshiba: Semiconductor device with charge-up preventing function, 5,587,598, Cl. 257-355.000.
- Hatanaka, Tadashi: See—
Nakagawa, Naohi; Hatanaka, Tadashi; Hayashibara, Tatsuhiro; and Shiono, Manzo, 5,587,486, Cl. 548-448.000.
- Hatanaka, Yoshinori: See—
Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
- Hatano, Takuji: See—
Sato, Akira; and Hatano, Takuji, 5,587,815, Cl. 359-11.000.
- Hathaway, George D.: Direct current homopolar machine, 5,587,618, Cl. 310-178.000.
- Hattanda, Hirokatsu; Ogiso, Mitsukazu; Koike, Yasuta; and Takagi, Kazuhiro, to Tokyo Yogyo Kabushiki Kaisha: Gas injection nozzle for pouring liquid metal, 5,587,101, Cl. 222-603.000.
- Hattori, Ryo: See—
Nishizawa, Seiji; Takahashi, Tokuji; and Hattori, Ryo, 5,587,792, Cl. 355-356.000.
- Hattori, Ryuichi: See—
Suzuki, Shinichi; Seki, Yukihiro; and Hattori, Ryuichi, 5,588,004, Cl. 370-516.000.
- Hattori, Toshio: See—
Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyairi, Yoshio; Hattori, Toshio; and Hagiwara, Haruo, 5,586,456, Cl. 68-18.00R.
- Hau, Clarence J.-Y.; Stuc, Kevin J.; and Vavreck, Kenneth E., to Panasonic Technologies, Inc.: Flexible parallel processing architecture for video resizing, 5,587,742, Cl. 348-441.000.
- Hauel, Norbert: See—
Narr, Berthold; Hauel, Norbert; Van Meel, Jacques; Wienen, Wolfgang; Entzeroth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381.000.
- Hauter, Bradley D.: Soccer training belt for use with a cord suspended soccer ball, 5,586,760, Cl. 273-58.00C.
- Hawkeye Concrete Products Co.: See—
Schmidgall, Hartzell H.; and Schmidgall, Jon A., 5,587,185, Cl. 425-229.000.
- Hawkins, Christopher J., to BWI KartidgPak Co.: Conveyor systems, 5,586,642, Cl. 198-803.110.
- Hawkins, Michael E.: See—
Bonitati, John A.; Case, Kirt L.; Hawkins, Michael E.; and Hoag, Stephen H., 5,586,821, Cl. 366-139.000.
- Hawkins, Phillip R.; Wilde, Craig G.; and Seithamer, Jeffrey J., to Incyte Pharmaceuticals, Inc.: DNA encoding a hyaluronan receptor expressed in human umbilical vein endothelial cells, 5,587,301, Cl. 435-69.100.
- Hawkins, Phillip R.; and Seithamer, Jeffrey J., to Incyte Pharmaceuticals, Inc.: Phospholipase C homolog, 5,587,306, Cl. 435-198.000.
- Hayabuchi, Masahiro: See—
Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masahiro; and Yamamoto, Yoshihisa, 5,586,954, Cl. 477-93.000.
- Hayakawa, Isao; and Kimura, Youichi, to Daiichi Pharmaceutical Co., Ltd.: Optically active pyridinecarboxylic acid derivatives, 5,587,386, Cl. 514-312.000.
- Hayakawa Rubber Co., Ltd.: See—
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Hayakawa, Tadashi: See—
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Hayasaka, Noboru: See—
Shitara, Yasuhiro; Hayasaka, Noboru; and Kosuka, Toshiya, 5,588,120, Cl. 395-200.150.
- Hayashi, Hideki, to Pioneer Electronic Corporation: Sampled-servo type optical disk having clock pits arranged offset from each other in the disk radial direction, 5,587,992, Cl. 369-275.400.
- Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, to Toda Kogyo Corporation: Non-magnetic particles for non-magnetic undercoating layer of magnetic recording medium, non-magnetic undercoating layer containing the same, and magnetic recording medium having the undercoating layer, 5,587,232, Cl. 428-323.000.
- Hayashi, Teruoki; and Shibai, Yoshio, to Sanwa Kenna Kogyo Co., Ltd.: Grinding chip fitting type grinding plate, 5,586,930, Cl. 451-548.000.

- Hayashi, Tetsuyoshi: See—
Konoike, Toshiro; Araki, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Ken-
suke; and Tozoy, Takehiko, 5,587,505, Cl. 558-272.000.
- Hayashihara, Tatsuhiko: See—
Nakagawa, Naoshi; Hatanaka, Tadashi; Hayashihara, Tatsuhiko; and
Shiono, Manzo, 5,587,486, Cl. 548-448.000.
- Hayek, Alberto: See—
Rubin, Jeffrey; Hayek, Alberto; Beattie, Gillian M.; and Otonowski,
Timo P. J., 5,587,309, Cl. 435-240.200.
- Hayes, David: See—
Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak,
Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364-510.000.
- He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John
R.; Mulcahy, Thomas M.; and Cal, Yigang, to United States of America,
Energy. Dual-keel electromagnetic maglev system, 5,586,504, Cl. 104-
282.000.
- Healey, David T.: See—
Venooker, Ronald J.; Scavino, John A.; Karkantis, Peter N.; Healey,
David T.; and Travers, Richard L., 5,586,590, Cl. 141-386.000.
- Venooker, Ronald J.; Scavino, John A.; Karkantis, Peter N.; Healey,
David T.; and Travers, Richard L., 5,586,673, Cl. 215-310.000.
- Heeks, George J.: See—
Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry,
Arnold W.; Heeks, George J.; and Fratangelo, Louis D., 5,587,208, Cl.
427-503.000.
- Heeren, Theodorus A. G.; and Buis, Edwin J., to Océ-Nederland, B.V.
Apparatus for transferring toner images, 5,587,779, Cl. 355-271.000.
- Heering, Jürgen R.: See—
Vollhardt, Frohmüt; and Heering, Jürgen R., 5,586,995, Cl. 55-227.000.
- Hefner, Heinz-Achim: See—
König, Ulf; Grubbe, Andreas; Schuppen, Andreas; Kibbel, Horst;
Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-
31.000.
- Hegardt, Johan: See—
Ek, Anders; and Hegardt, Johan, 5,587,640, Cl. 318-638.000.
- Hegele-Hartung, Christa: See—
Bull, James R.; Fritzmeier, Karl-Heinrich; and Hegele-Hartung, Christa,
5,587,496, Cl. 552-629.000.
- Heidelberger Druckmaschinen: See—
Bähr, Klaus, 5,586,508, Cl. 108-2.000.
- Heider, Marc; Henkelmann, Jochem; and Karcher, Michael, to BASF
Aktiengesellschaft. Preparation of silicon-containing vinyl ethers and vinyl
thioethers, 5,587,503, Cl. 556-427.000.
- Heiliger, Ludwig; Schmidt, Adolf; and Probst, Joachim, to Bayer Aktiengesellschaft. Polymerizable emulsifiers and reactive groups and polymers of
emulsifiers and other monomers, 5,587,443, Cl. 526-240.000.
- Heimann, Bruno: See—
Humpert, Jürgen; Heimann, Bruno; and Frankholz, Christian, 5,586,746,
Cl. 251-129.040.
- Heister, Kurt W.; and Haddock, Richard S., to Johnson Worldwide Associates,
Inc. Backpack support, 5,586,699, Cl. 224-628.000.
- Helene Curtis, Inc.: See—
Dowell, Teresa J.; Newell, Gerald P.; and Zeffren, Eugene, 5,587,154, Cl.
424-70.110.
- Helifix Ltd.: See—
Paterson, Robert I.; and Breeze, Brian A., 5,586,605, Cl. 173-4.000.
- Helios Research Corp.: See—
Nicomemus, Carl D., 5,586,442, Cl. 62-107.000.
- Heller DeJulio Corporation: See—
Heller, Samuel, 5,587,643, Cl. 318-821.000.
- Heller, Jack W.: See—
Kowalczyk, Robert M.; Brown, Robert H., III; and Heller, Jack W.,
5,587,957, Cl. 365-230.030.
- Heller, Samuel, to Heller DeJulio Corporation. Rotary induction machine
having control of secondary winding impedance, 5,587,643, Cl. 318-
821.000.
- Helmich, Arthur R.: See—
Hartman, Michael O.; Kinder, Dale J.; Rainey, Randy E.; Helmich,
Arthur R.; and Willis, Daniel E., 5,587,055, Cl. 203-1.000.
- Helmshofer, John A. Cover assembly and method for covering undersink
piping, 5,586,568, Cl. 137-15.000.
- Helquist, Paul; and Cocito, Carlo, to University of Notre Dame. Derivatized
virginiamycin M., 5,587,475, Cl. 540-456.000.
- Hemmi, Gregory W.: See—
Sessler, Jonathan L.; Mody, Tarak D.; Hemmi, Gregory W.; Král,
Vladimir A.; and Magda, Darren, 5,587,371, Cl. 514-185.000.
- Sessler, Jonathan L.; Hemmi, Gregory W.; and Murai, Toshiaki,
5,587,463, Cl. 534-15.000.
- Hencke, Robert J.: See—
Aidin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier,
Kenneth; Ledwith, Robert; and Hencke, Robert J., 5,586,637, Cl.
198-397.000.
- Henderson, Allan P.; and Patrick, Miller B. Tensionless pier foundation,
5,586,417, Cl. 52-295.000.
- Henderson, Robert W., to Nutramax Laboratories, Inc. Aminosugar and
glycosaminoglycan composition for the treatment and repair of connective
tissue, 5,587,363, Cl. 514-54.000.
- Hendrickson, Bruce A.; and Leland, Robert W., to Sandia Corporation.
Multidimensional spectral load balancing, 5,587,922, Cl. 364-489.000.
- Hendry, Allan W.: See—
Esampour, Robert A.; Shiley, Robert J., II; and Hendry, Allan W.,
5,586,912, Cl. 439-620.000.
- Henion, Jack D.; Sheppard, Robin L.; and Wachs, Timothy, to Cornell
Research Foundation, Inc. Self-aligning liquid junction, 5,587,582, Cl.
250-288.000.
- Henkel Kommanditgesellschaft auf Aktien: See—
Kuhm, Peter; Schroeder, Christine; Sander, Volker; Lindener, Juergen;
and De Riese-Meyer, Loert, 5,587,063, Cl. 205-173.000.
- Zeise, Christiane; Raehse, Wilfried; Jacobs, Jochen; and Hoffmeister,
Juergen, 5,587,104, Cl. 510-298.000.
- Henkelmann, Jochem: See—
Heider, Marc; Henkelmann, Jochem; and Karcher, Michael, 5,587,503,
Cl. 556-427.000.
- Hennessy, David R.: See—
Nelson, Chris; Hennessy, David R.; and LeClaire, James P., 5,586,635,
Cl. 192-85.00A.
- Henrie, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.;
Chaguturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., to
FMC Corporation. Insecticidal 5-substituted-2,4-diaminopyrimidine
derivatives, 5,587,379, Cl. 514-275.000.
- Henry, Arnold W.: See—
Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry,
Arnold W.; Heeks, George J.; and Fratangelo, Louis D., 5,587,208, Cl.
427-503.000.
- Henry, Raymond L.: See—
Viegas, Tacey X.; Reeve, Lorraine E.; and Henry, Raymond L.,
5,587,175, Cl. 424-427.000.
- Hepler, Douglas C., to Polysht Corporation. Multitip hot runner system,
5,587,188, Cl. 425-549.000.
- Herbelleau, Yves, to Sedepro. Tire having carcass reinforcement formed of
strips, 5,587,030, Cl. 152-555.000.
- Herbert, William G., to Xerox Corporation. Constant concentration rinseable
slurry device, 5,586,927, Cl. 451-88.000.
- Herd, Karl J.: See—
Schündebüttel, Karl-Heinz; and Herd, Karl J., 5,587,465, Cl. 534-
635.000.
- Hergott, Arthur, to Greenwich Industries, L.P. Underseat article holder
apparatus, 5,586,806, Cl. 297-188.110.
- Herman Berstorff Maschinenbau GmbH: See—
Voigt, Jürgen, 5,587,186, Cl. 425-310.000.
- Herman Miller, Inc.: See—
Szmazinski, John A., 5,586,809, Cl. 297-353.000.
- Hermann, Robert A.: See—
Lawless, Michael W.; Soberon, Peter A.; Kaul, Ashok; Minick, Steven
E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen
J., 5,586,868, Cl. 417-53.000.
- Herold, Duane: See—
Wanek, Ronald G.; Dotta, James C.; Konkel, Brian; and Herold, Duane,
5,586,830, Cl. 403-59.000.
- Hershey, John E.: See—
Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.;
Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B.,
II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
- Heruth, Kenneth T.: See—
Shoberg, Bret R.; and Heruth, Kenneth T., 5,586,629, Cl. 141-21.000.
- Herzog AG: See—
Herzog, Kurt, 5,587,076, Cl. 210-461.000.
- Herzog, Kurt, to Herzog AG. Filter nozzle for injection molding machines
processing thermoplastics, 5,587,076, Cl. 210-461.000.
- Hess, Arthur: See—
Falcon, Michael D.; Perry, William; and Hess, Arthur, 5,587,699, Cl.
340-475.000.
- Hess, Brian K. Portable alarm system, 5,587,701, Cl. 340-541.000.
- Hess, George P.; Carpenter, Barry K.; Ramesh, Doraiswamy; and Wieboldt,
Raymond, to Cornell Research Foundation, Inc. Caged caboxyl compounds
and use thereof, 5,587,509, Cl. 560-130.000.
- Hess, Harold: See—
Hess, John, III; and Hess, Harold, 5,586,416, Cl. 52-169.500.
- Hess, John, III; and Hess, Harold. Concrete form with integral drain,
5,586,416, Cl. 52-169.500.
- Hess, Richard W.: See—
Lerner, Bernard; Hess, Richard W.; Cronauer, William M.; Wehrmann,
Rick S.; and Kramer, James D., 5,586,708, Cl. 226-172.000.
- Heubusch, Harald; and Rösler, Jörg, to AEG Schienenfahrzeuge GmbH.
Ball-and-socket coupling, particularly for railway cars, 5,586,506, Cl.
105-3.000.
- Heugebaert, Franciscus; and Van Hunsel, Johan, to Agfa-Gevaert, N.V.
Dampening solution for printing with a lithographic printing plate and a
method for printing therewith, 5,587,271, Cl. 430-204.000.
- Hewell, James F.: See—
Detering, Greig R.; Gallick, Robert L.; and Hewell, James F., 5,588,049,
Cl. 379-142.000.
- Hewitt, Charles E.: See—
Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.;
Fichtner, Michael W.; and Fitzgerald, John J., 5,587,245, Cl. 428-
447.000.
- Hewlett-Packard Company: See—
Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein,
Michael J.; and Wilker, Julie D., 5,587,914, Cl. 364-468.010.
- Dickinson, Ian J.; Eichberger, Horst; Messaros, David W.; and Walter,
Hans-Dieter, 5,588,109, Cl. 395-326.000.

- Jacobson, David M., 5,587,997, Cl. 370-253.000.
- Johansson, Christopher W., 5,587,685, Cl. 327-546.000.
- Karp, Alan H.; Hao, Ming C.; and Gupta, Rajiv, 5,588,117, Cl. 395-
200.030.
- Lee, Ghai K.; and Gomi, Masao, 5,587,729, Cl. 347-32.000.
- Patel, Chandrakant, 5,587,882, Cl. 361-705.000.
- Rhodes, Robert P., 5,587,520, Cl. 73-25.030.
- Ruby, Richard C.; and Merchant, Paul P., 5,587,620, Cl. 310-346.000.
- Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew;
Kraft, Robert E.; and Vander Plas, Hubert A., 5,586,715, Cl. 228-
248.100.
- Sharrit, David, 5,588,142, Cl. 395-500.000.
- Heyco Stamped Products, Inc.: See—
Brown, Donald C., 5,586,920, Cl. 439-857.000.
- Heydinger, Matthew: See—
Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew;
Kraft, Robert E.; and Vander Plas, Hubert A., 5,586,715, Cl. 228-
248.100.
- Hibino, Hideo; Yokonuma, Norikazu; Kazami, Kazuyuki; and Yamazaki,
Youchi, to Nikon Corporation. Information recording device and method
with feeding speed control, 5,587,751, Cl. 396-319.000.
- Hicok, Gary D.; Hildebrandt, Eric A.; and Zhu, Michael H., to VLSI
Technology, Inc. Dynamic direction look ahead read buffer, 5,588,128, Cl.
395-414.000.
- Higashida, Masaaki: See—
Ootsuka, Takeshi; and Higashida, Masaaki, 5,587,807, Cl. 386-46.000.
- Higashimura, Masayo: See—
Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura,
Masayo; Iwaoaka, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl.
355-208.000.
- Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasuharu; and
Nagao, Masaya, to Snow Brand Milk Products Co., Ltd. Human derived
glycoprotein, biologically active factor which includes glycoprotein and
pharmaceutical product, 5,587,359, Cl. 514-12.000.
- Higuchi, Hirofumi: See—
Abe, Mariko; Ebata, Shuji; Abe, Takafumi; and Higuchi, Hirofumi,
5,587,349, Cl. 502-236.000.
- Hildebrandt, Eric A.: See—
Hicok, Gary D.; Hildebrandt, Eric A.; and Zhu, Michael H., 5,588,128,
Cl. 395-414.000.
- Hildebrandt, Gernot: See—
Wieloch, Christopher J.; Kappel, Mark A.; Annis, Jeffrey R.; Benard,
David J.; Boehmer, Ellen; and Hildebrandt, Gernot, 5,587,861, Cl.
361-14.000.
- Hill & Griffith Co.: See—
LaFay, Victor S.; and Neltner, Stephen L., 5,587,008, Cl. 106-38.510.
- Hill, Bruce U., Jr. Stockings and methods therefore, 5,586,341, Cl. 2-239.000.
- Hill, Howard T.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill,
Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina
L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.
- Hilliard, Kenneth R. Oxygen mask with nebulizer, 5,586,551, Cl. 128-
203.290.
- Hilt Aktiengesellschaft: See—
Gantner, Gebhard; Dengg, Franz; Ofner, Peter; and Münzenberger,
Herbert, 5,586,739, Cl. 248-74.100.
- Neumaier, Anton; and Donner, Hans-Christian, 5,586,607, Cl. 173-
117.000.
- Hinchliffe, Peter W. J., to United States Surgical Corporation. Instrument for
closing trocar puncture wounds, 5,586,986, Cl. 606-147.000.
- Hinotsu, Naoyoshi: See—
Saito, Ken; Hinotsu, Naoyoshi; Sakamoto, Hikaru; and Hoshino, Koichi,
5,586,993, Cl. 29-623.200.
- Hinton, Glenn J.: See—
Abramson, Jeffrey M.; Akkary, Haitham; Glew, Andrew F.; Hinton,
Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David
B., 5,588,126, Cl. 395-376.000.
- Ilioki, Yuichi; Kurita, Kazuhiko; Kawabata, Keiko; and Azuma, Toshikazu, to
KAO Corporation. Agricultural chemical composition kit comprising qua-
ternary di(polyoxyalkylene) ammonium alkyl sulfates, 5,587,353, Cl. 504-
116.000.
- Hippely, Keith A.; Wood, Larry R.; Walsh, Brian E.; and Choy, Terence A.,
to Mantel, Inc. Toy vehicle playset for thermochromic vehicles, 5,586,923,
Cl. 446-14.000.
- Hirahara, Shinichi; and Morimoto, Hiroki, to Honda Giken Kogyo Kabushiki
Kaisha. Automotive door assembly, 5,586,797, Cl. 296-146.600.
- Hirai, Nobuaki: See—
Endo, Kazuhiko; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto,
Manabu; and Hirai, Nobuaki, 5,587,978, Cl. 369-32.000.
- Hirakawa, Tatsuya: See—
Nagamoto, Itsushi; Sumikawa, Noburo; Hirakawa, Tatsuya; and Nakan-
ishi, Tatsuo, 5,586,944, Cl. 473-248.000.
- Hirano, Seiji: See—
Kawanishi, Toshiaki; Nobutoki, Yoshikazu; Hirano, Seiji; and Terayama,
Koiji, 5,588,002, Cl. 370-462.000.
- Hirano, Takayuki: See—
Imai, Toru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro;
Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12.020.
- Hirano, Yoshihito: See—
Johdai, Akiyoshi; Ohnata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu;
and Hirano, Yoshihito, 5,587,782, Cl. 355-309.000.
- Hirao, Yasunobu; Motoyama, Yuji; Nagasaka, Takashi; and Katsuyama,
Hidekazu, to Nippondenso Co., Ltd. Method for producing multi-board
electronic device, 5,586,388, Cl. 29-830.000.
- Hirao, Yasunobu; Koyama, Makoto; and Motoyama, Yuji, to Nippondenso
Co., Ltd. Method for producing multi-board electronic device, 5,586,389,
Cl. 29-841.000.
- Hirose, Kenji, to Kabushiki Kaisha Toshiba. Document classification and
retrieval with title-based on-the-fly class merge, 5,588,149, Cl. 395-
601.000.
- Hiroyuki, Nakata: See—
Taniuchi, Osamu; and Hiroyuki, Nakata, 5,586,894, Cl. 439-157.000.
- Hirschmann, Klaus: See—
Schnabel, Eberhard; Raff, Lothar; and Hirschmann, Klaus, 5,586,543,
Cl. 123-696.000.
- Hitachi Koki Co., Ltd.: See—
Shinohara, Makoto; Matsumoto, Yoshikane; and Suematsu, Shigenori,
5,586,496, Cl. 101-93.040.
- Hitachi, Ltd.: See—
Inoue, Mitsuru; and Kurosawa, Hiroyuki, 5,588,144, Cl. 395-555.000.
- Ishida, Kiyoshi; and Goto, Hiroshi, 5,587,735, Cl. 348-14.000.
- Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro;
and Kashiwabara, Yasushige, 5,586,857, Cl. 415-23.000.
- Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki;
Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Maki, Atsushi; Kawaguchi, Fumio; Yamashita, Yuichi; and Ito, Yoshi-
toshi, 5,586,554, Cl. 128-653.100.
- Masayuki, Watanabe; Toshio, Sugano; Seiichiro, Tsukui; Takashi, Ono;
and Yoshiaki, Wakashima, 5,587,341, Cl. 437-206.000.
- Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Ter-
unuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi;
and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.
- Saito, Hiroshi; Suzuki, Yasumichi; and Tamura, Naoyuki, 5,587,205, Cl.
427-553.000.
- Shindo, Yasuhiro; Yamaguti, Usaburo; Ioka, Kazuo; Suzuki, Tosio;
Minagawa, Akihiro; and Kitahatake, Syoichi, 5,587,320, Cl. 435-
290.100.
- Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki,
Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo,
5,587,235, Cl. 428-332.000.
- Suzuki, Shinichi; Seki, Yukihiko; and Hattori, Ryuchi, 5,588,004, Cl.
370-516.000.
- Yumiyama, Shigeru; Onodera, Ko; and Mori, Yoshimi, 5,587,619, Cl.
310-201.000.
- Hitachi Maxell, Ltd.: See—
Umehayashi, Nobuhiko; Mizushima, Kunio; Miyake, Akira; and Miyata,
Teruhisa, 5,587,860, Cl. 360-133.000.
- Hitachi Tobu Semiconductor, Ltd.: See—
Masayuki, Watanabe; Toshio, Sugano; Seiichiro, Tsukui; Takashi, Ono;
and Yoshiaki, Wakashima, 5,587,341, Cl. 437-206.000.
- Hladik, Stephen M.: See—
Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.;
Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B.,
II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
- HMT Technology Corporation: See—
Chao, James L.; Lee, Yu-Chen; and Gao, Chao, 5,587,217, Cl. 428-
65.400.
- Ho, Edward J.: See—
Boone, Steven F.; and Ho, Edward J., 5,587,712, Cl. 342-42.000.
- Ho, Kit-Fun. High content information transmission system, 5,588,023, Cl.
375-238.000.
- Ho, Weng K.; Hang, Chang C.; and Wojsznis, Wilhelm K., to Fisher-
Rosemount Systems, Inc. Method and apparatus for determining the
ultimate gain and ultimate period of a controlled process, 5,587,899, Cl.
364-157.000.
- Hoag, Stephen H.: See—
Bonitati, John A.; Case, Kirt L.; Hawkins, Michael E.; and Hoag,
Stephen H., 5,586,821, Cl. 366-139.000.
- Hoarty, W. Leo: See—
Lauder, Gary M.; Hoarty, W. Leo; and Soske, Joshua W., 5,587,734, Cl.
348-10.000.
- Hoch, Dieter: See—
Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel,
Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401.000.
- Hochiki Corporation: See—
Nagashima, Tetsuya, 5,587,790, Cl. 356-338.000.
- Hoechst Aktiengesellschaft: See—
Dreischhoff, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoemel,
Michael; and Stengel-Rutkowski, Bernhard, 5,587,409, Cl. 523-
404.000.
- Ehlers, Jens; and Walter, Jutta, 5,587,440, Cl. 526-153.000.
- Fleischer, Dietrich; Hoffmocker, Michael; Mück, Karl-Friedrich; and
Sextro, Günter, 5,587,449, Cl. 528-232.000.
- Kampe, Klaus-Dieter; ter Meer, Hans-Ulrich; Egger, Norbert K.; and
Vogel, Martin A., 5,587,476, Cl. 540-472.000.
- Scholz, Guido, 5,587,517, Cl. 568-16.000.
- Thönnessen, Franz; and Mühlhaus, Hans H., 5,586,350, Cl. 5-636.000.
- Then, Johann; Aretz, Werner; and Sauber, Klaus, 5,587,319, Cl. 435-
280.000.
- Winter, Andreas; Dölle, Volker; and Spaack, Walter, 5,587,501, Cl.
556-53.000.

- von Gentzkow, Wolfgang; Huber, Jürgen; Kapitzka, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413.000.
- Hoenel, Michael: *See—*
- Dreischhoff, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoenel, Michael, and Stengel-Rutkowski, Bernhard, 5,587,409, Cl. 523-404.000.
- Hoerner, Gregory G.: *See—*
- Lawless, Michael W.; Soberon, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., 5,586,868, Cl. 417-53.000.
- Hoersch, Guido; and Hoersch, Reinhard, to Hoersch, Guido, Method and apparatus for the cleaning and/or care of floors and/or floor coverings of all types, 5,587,021, Cl. 134-1.000.
- Hoersch, Reinhard: *See—*
- Hoersch, Guido; and Hoersch, Reinhard, 5,587,021, Cl. 134-1.000.
- Hoetzel, Juergen, to Robert Bosch GmbH, Method and device for maneuvering a motor vehicle out of a parking space, 5,587,938, Cl. 364-578.000.
- Hoeven, Petrus C. J.: *See—*
- Kahlau, Johannes G. F.; Minnagh, Winslow M.; and Hoeven, Petrus C. J., 5,587,980, Cl. 369-54.000.
- Hofer, John C.: *See—*
- Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., 5,586,782, Cl. 280-730.200.
- Hoffmann, Donald J., to Wallace Computer Services, Inc. Label assembly with multi-ply insert, 5,587,222, Cl. 428-192.000.
- Hoffmann, Manfred, to Framatome Connectors International, Plug connector in which the cables are led out at an angle and with a releasable secondary lock, 5,586,903, Cl. 439-352.000.
- Hoffmeister, Juergen: *See—*
- Zeise, Christiane; Raehse, Wilfried; Jacobs, Jochen; and Hoffmeister, Juergen, 5,587,104, Cl. 510-298.000.
- Hoffmeyer, Michael: *See—*
- Fleischer, Dietrich; Hoffmeyer, Michael; Mück, Karl-Friedrich; and Sextro, Günter, 5,587,449, Cl. 528-232.000.
- Hoffner, Terrell W., Log illusion vinyl log siding, 5,586,422, Cl. 52-529.000.
- Hoffmann Werkstatt-Technik GmbH: *See—*
- Rothamel, Karl; Lenhardt, Lorenz; and Kihn, Gottfried, 5,587,528, Cl. 73-462.000.
- Hohmann, Ralf: *See—*
- Kirchner, Harry; Hohmann, Ralf; and Spors, Ralf, 5,586,791, Cl. 285-179.000.
- Holmick, Richard P.: *See—*
- Mojden, Andrew E.; and Holmick, Richard P., 5,586,638, Cl. 198-419.100.
- Hoke, Glenn: *See—*
- Cook, Philip D.; and Hoke, Glenn, 5,587,361, Cl. 514-44.000.
- Holland Sweetener Company V.O.F.: *See—*
- Slangen, Hubertus J. M., 5,587,178, Cl. 424-464.000.
- Holton, Robert A.; and Kim, Seokchan, to Florida State University, Taxane and baccatin III analogs bearing new C2 and C4 functional groups, 5,587,489, Cl. 549-229.000.
- Holzer, Helmut: *See—*
- Klionsky, Daniel; Holzer, Helmut; and Destruelle, Monika, 5,587,290, Cl. 435-6.000.
- Honda Giken Kogyo Kabushiki Kaisha: *See—*
- Hirahara, Shinichi; and Morimoto, Hiroki, 5,586,797, Cl. 296-146.600.
- Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
- Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.
- Kouchi, Takao; and Suzuki, Hideaki, 5,586,614, Cl. 180-190.000.
- Saegusa, Hiroyuki, 5,586,798, Cl. 296-146.150.
- Honda, Munenobu: *See—*
- Ueno, Yoshio; Wada, Yasuo; and Honda, Munenobu, 5,586,751, Cl. 254-352.000.
- Hong, Jibi; Chu, Jianhua; and Wu, Hongxiang, to Panzhihua Iron and Steel (Group) Co., Raw materials for producing color ceramic products, 5,587,347, Cl. 501-155.000.
- Hongo, Katsunobu, to Mitsubishi Denki Kabushiki Kaisha, Microcomputer, 5,588,124, Cl. 395-287.000.
- Hongu, Takahiro: *See—*
- Hagihara, Hayato; and Hongu, Takahiro, 5,587,808, Cl. 358-462.000.
- Honma, Noriyuki: *See—*
- Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Honsik, Cyril J.: *See—*
- Pierschbacher, Michael D.; Honsik, Cyril J.; and Dreisbach, Lisa B., 5,587,456, Cl. 530-326.000.
- Hooper, Kimberly A.: *See—*
- Kohn, Joachim B.; and Hooper, Kimberly A., 5,587,507, Cl. 560-40.000.
- Hopf, Gustav; and Steinhardt, Helmut, to Framatome Connectors International, Electric connector, 5,586,902, Cl. 439-352.000.
- Hoppensteadt, Dale; and Mirocha, Joseph L., Electrical busway meter service panel combination, 5,587,874, Cl. 361-663.000.
- Hor, Ah-Mee: *See—*
- Pinkney, Heidi; Hor, Ah-Mee; and Popovic, Zoran D., 5,587,262, Cl. 430-54.000.
- Horde, Boice F.; and Akers, Denver, to Lavernois Die and Automation, Modular die transfer system, 5,586,464, Cl. 72-405.160.
- Hori, Ryoichi: *See—*
- Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Hori, Satoshi; Omori, Teruyo; and Sakagami, Makoto, to Mitsubishi Denki Kabushiki Kaisha, Fault diagnosis device, 5,587,930, Cl. 364-551.010.
- Horigane, Akira; Matsukura, Ushio; and Kamio, Masayoshi, to Director General of National Agriculture Research Center, Ministry of Agriculture, Forestry and Fisheries, Bioreactor, 5,587,298, Cl. 435-41.000.
- Horioka, Hiroshi: *See—*
- Kondo, Kazuhiko; Horioka, Hiroshi; and Iwasaki, Tameo, 5,587,474, Cl. 540-350.000.
- Horioka, Yasuo: *See—*
- Takizawa, Toshiki; Horioka, Yasuo; and Akazawa, Taro, 5,587,420, Cl. 524-572.000.
- Horsten, Bartholomeus C.; Uytendaele, Carlo A.; Jansen, Guy D. A.; and Schuerwegen, Ronald, to Agfa Gevaert N.V. Direct thermal imaging material, 5,587,350, Cl. 503-201.000.
- Horton, Inc.: *See—*
- Nelson, Chris; Hennessy, David R.; and LeClaire, James P., 5,586,635, Cl. 192-85.00A.
- Horwitz, Earl P.; and Chiarizia, Renato, to Arch Development Corporation, Method of dissolving metal oxides with di- or polyphosphoric acid and a redundant, 5,587,142, Cl. 423-658.500.
- Hosch, Michael A.: *See—*
- Dörner, Wolfgang C.; Hosch, Michael A.; Danelski, Darin L.; and Remsing, David A., 5,586,685, Cl. 221-197.000.
- Hoshino, Koichi: *See—*
- Saito, Ken; Hinotsu, Naoyoshi; Sakamoto, Hikaru; and Hoshino, Koichi, 5,586,993, Cl. 29-623.200.
- Hoshino, Teruo, to Daimichi Kinzoku Kogyo Co., Ltd., Centering device having work rest control responsive to carriage movement, 5,586,478, Cl. 82-133.000.
- Hoshinouchi, Susumu: *See—*
- Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
- Hoshizaki Denki Kabushiki Kaisha: *See—*
- Torimitsu, Hiroshi, 5,586,446, Cl. 62-126.000.
- Hoskins, JoAnn: *See—*
- Alborn, William E., Jr.; Hoskins, JoAnn; Skatrud, Paul L.; and Unal, Serhat, 5,587,307, Cl. 435-240.100.
- Hoslet, René: *See—*
- Schneider, Bernard; and Hoslet, René, 5,586,672, Cl. 215-250.000.
- Hosoya, Kazuki: *See—*
- Tanaka, Hiroshi; and Hosoya, Kazuki, 5,586,598, Cl. 165-133.000.
- Hosoya, Ryouzou: *See—*
- Sakai, Michio; Hosoya, Ryouzou; Orito, Nobuyuki; and Nakahata, Minoru, 5,587,873, Cl. 361-603.000.
- Hosoya, Yoichi: *See—*
- Santou, Mitsuo; Yamanouchi, Junichi; and Hosoya, Yoichi, 5,587,281, Cl. 430-567.000.
- Hoteik, Dan J.: *See—*
- Anderson, Peter L.; Cowell, Michael J.; and Hoteik, Dan J., 5,586,841, Cl. 405-286.000.
- Hou, Wei-Hsin; Lloyd, Thomas B.; and Schubert, Frederic E., to Copytele, Inc., Colored polymeric dielectric particles and method of manufacture, 5,587,242, Cl. 428-402.000.
- Houde, Stephanie L.: *See—*
- Chen, Michael; Houde, Stephanie L.; and Seidl, Robert H., 5,588,098, Cl. 395-137.000.
- Houle, Alain C.: *See—*
- Belleville, Claude; Van Neste, Richard; Caron, Serge; Houle, Alain C.; and Thibault, Pierre, 5,587,791, Cl. 356-345.000.
- House Foods Corporation: *See—*
- Nakatani, Masayuki; Sengoku, Koji; and Fujita, Akifumi, 5,587,194, Cl. 426-521.000.
- Hovda, Keith D., to Chemithon Corporation, The Sulfonation of fatty acid esters, 5,587,500, Cl. 554-98.000.
- Howie, Blake J.: *See—*
- Tibbets, Gary G.; Nazri, Gholam-Abbas; and Howie, Blake J., 5,587,257, Cl. 429-218.000.
- Hoye, Thomas R.; and Tan, Lushi, to University of Minnesota, Regents of the, Method for the synthesis of bis-tetrahydrofuranyl Annonaceous acetogenins, 5,587,491, Cl. 549-320.000.
- Hsieh, Fu-Lung; Ipri, Alfred C.; Dolny, Gary M.; and Stewart, Roger G., to David Sarnoff Research Center, Inc., Method for fabricating a switching transistor having a capacitive network proximate a drift region, 5,587,329, Cl. 437-40.000.
- Hsia, Chih-Yu, Floating solar heater for pool water, 5,586,548, Cl. 126-565.000.
- Hsiao, Louis, to Concept Designs, Inc., Wheel retaining device, 5,586,649, Cl. 206-303.000.
- Hsieh, Bing R.; Mori, Joseph; Machonkin, Mary A.; and Ewing, Joan R., to Xerox Corporation, Developing apparatus including a coated developer roller, 5,587,224, Cl. 428-195.000.
- Hu, Stephen, Brake of a baby's walker, 5,586,622, Cl. 188-20.000.
- Hu, Xin-Hua, to Hu, Xin-Hua, Treatment of cutaneous vascular and pigmented lesions, 5,586,981, Cl. 606-9.000.
- Hua, Jun: *See—*

- Jones, Frank N.; Fu, Shou-Kuan; Hua, Jun; and Yuan, Xiaoying, 5,587,428, Cl. 525-165.000.
- Huang, James P. S., Process and the contrivance employed for producing heat energy without combustion, 5,587,100, Cl. 219-772.000.
- Huang, Ming H., Safety structure improvement of a bulb socket, 5,586,904, Cl. 439-419.000.
- Huang, Tien F., to Tsai, Wen H., Toy car structure, 5,586,924, Cl. 446-462.000.
- Hubbard, David; and Wolog, Walter, to Pitney Bowes Inc., Drawer interlock apparatus, 5,586,817, Cl. 312-334.440.
- Huber, Jürgen: *See—*
- von Gentzkow, Wolfgang; Huber, Jürgen; Kapitzka, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413.000.
- Huber, Richard M.: *See—*
- Branner, Donald L.; Ray, Andrew E.; Peters, Scott M.; and Huber, Richard M., 5,587,706, Cl. 340-825.440.
- Hudson, Steven M.: *See—*
- Dickie, Neil M.; and Hudson, Steven M., 5,587,707, Cl. 340-870.090.
- Huemer, Gerhart; and Lemberger, Heinz, to Bayerische Motoren Werke AG, Device for regulation of a motor vehicle engine at idle speed, 5,586,432, Cl. 60-274.000.
- Hufen, Gerd: *See—*
- Salzburg, Herbert; Steinhoff, Georg; Gosch, Andreas; and Hufen, Gerd, 5,587,511, Cl. 562-513.000.
- Huff, Robert M.: *See—*
- Cooperman, Barbara; and Huff, Robert M., 5,586,375, Cl. 24-716.000.
- Huffy Corporation: *See—*
- Fitzsimmons, James N.; and Schickert, Randy R., 5,586,759, Cl. 273-1.50R.
- Hughes Electronics: *See—*
- Chin, Richard; and Le Fevre, David, 5,587,583, Cl. 250-332.000.
- Kebo, Reynold S., 5,587,837, Cl. 359-643.000.
- Pines, Michael Y.; and King, Donald F., 5,587,784, Cl. 356-4.010.
- Hui, Edward S.: *See—*
- Jazayeri, Mehdi; Hui, Edward S.; and Korsh, George J., 5,587,951, Cl. 365-203.000.
- Hull, John R.: *See—*
- He, Jianjiang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cal, Yigang, 5,586,504, Cl. 104-282.000.
- Hull, Richard L.: *See—*
- Yach, Randy L.; and Hull, Richard L., 5,587,866, Cl. 361-90.000.
- Humburg, Michael, to Eberspächer, J., Dual-circuit vehicle heater, 5,586,721, Cl. 237-12.30B.
- Humlicek, Donald R.: *See—*
- DeKoning, Rodney A.; Humlicek, Donald R.; and Johnson, Max L., 5,588,110, Cl. 395-182.030.
- Humpert, Jergen; Heimann, Bruno; and Frankholz, Christian, to Friedrich Grohe Aktiengesellschaft, Faucet with motion-detector on/off control, 5,586,746, Cl. 251-129.040.
- Hunbert, Daniel: *See—*
- Asroch, Josef; Chantot, Jean-Francois; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.
- Hung, Chun-Yen: *See—*
- Tsai, Philip; Hung, Chun-Yen; and Wu, Fen-Shiung, 5,587,878, Cl. 361-683.000.
- Hunt Holdings, Inc.: *See—*
- Schwartz, David L., 5,586,593, Cl. 160-135.000.
- Hunt, Mark A.; and Murray, Andrew, to Light & Sound Design Limited, Repeater for use in a control network, 5,588,021, Cl. 375-211.000.
- Hunter, Craig A.: *See—*
- Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., 5,587,183, Cl. 425-4.00R.
- Hunter Technical Developments Limited: *See—*
- Sawyer, Colin; Wallis, John; and Baringale, Peter, 5,586,933, Cl. 454-299.000.
- Huston, Rima: *See—*
- Meraldi, Jean-Paul; Cizek, Vlastimil; and Huston, Rima, 5,587,238, Cl. 428-357.000.
- Hutin, Patrice, to Skis Rossignol SA, Golf clubhead and golf club fitted with such a head, 5,586,947, Cl. 473-324.000.
- Huvar, Gary S.; and Lobo, Alfred D., De-labelling for removing apparatus labels adhered to a diskette utilizing opposed heaters, 5,587,096, Cl. 219-521.000.
- Hwa, Chih M.: *See—*
- Greaves, Brian; Poole, Stephen C.; Hwa, Chih M.; and Fan, Joseph C., 5,587,109, Cl. 252-392.000.
- Hwang, Chong-Lii; and Teng, Clarence W., to Texas Instruments Incorporated, Microplanarization of rough electrodes by thin amorphous layers, 5,587,614, Cl. 257-532.000.
- Hyacinthe, Roland: *See—*
- Tournier, Hervé; Hyacinthe, Roland; and Schneider, Michel, 5,587,199, Cl. 427-2.120.
- Hyde, Richard M.: *See—*
- Miller, Alistair A.; Nobbs, Malcolm S.; Hyde, Richard M.; and Leach, Michael J., 5,587,380, Cl. 514-275.000.
- Hyde, Roger J.: *See—*
- Gotch, Henry E.; and Hyde, Roger J., 5,586,691, Cl. 222-113.000.
- Hydromatic Ltd.: *See—*
- Shekalim, Avraham, 5,586,727, Cl. 239-542.000.
- Hying, Clement F.; Perko, Jack E.; and Wenzler, Larry E., to Brady USA, Inc., Thin label applicator, 5,587,043, Cl. 156-566.000.
- HYMO Corporation: *See—*
- Takeda, Hisao, 5,587,415, Cl. 524-458.000.
- Hyuga, Hiroaki: *See—*
- Okazaki, Yoji; Goto, Chiaki; Hyuga, Hiroaki; and Harada, Akinori, 5,588,014, Cl. 372-22.000.
- Hyundai Electronics America: *See—*
- Schmitt, Kenneth C., 5,587,675, Cl. 327-99.000.
- Hyundai Electronics Industries Co., Inc.: *See—*
- Chung, Chan H., 5,587,953, Cl. 365-220.000.
- Hyundai Electronics Industries Co., Ltd.: *See—*
- Jang, Yong J., 5,587,717, Cl. 342-359.000.
- Hyundai Motor Company: *See—*
- Shin, Dong-Yup, 5,587,139, Cl. 423-275.000.
- Iardella, Carlo A.; and Agrusa, Mauro, to GF-OTO Melara Breda Bresiana S.r.l., Method for discovering and designating air targets, 5,587,718, Cl. 342-443.000.
- Iatron Laboratories, Inc.: *See—*
- Tsubota, Hiroyuki; and Shimada, Reiko, 5,587,296, Cl. 435-14.000.
- Ichida, Akito: *See—*
- Murakami, Tatsushi; and Ichida, Akito, 5,587,467, Cl. 536-18.500.
- Ichikawa, Shunji: *See—*
- Suzuki, Fumio; Shinada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi, 5,587,378, Cl. 514-264.000.
- Ichikawa, Tadashi: *See—*
- Kato, Satoru; Ito, Hiroshi; Ichikawa, Tadashi; and Kagami, Manabu, 5,587,785, Cl. 356-28.500.
- Ichimura, Etsuo: *See—*
- Kawakami, Takahiro; Ogawa, Akira; and Ichimura, Etsuo, 5,587,531, Cl. 73-514.120.
- Ichino, Tomio: *See—*
- Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58.000.
- Ichinohe, Shoji: *See—*
- Mochizuki, Shigeo; Matsumoto, Masahiro; Yamazaki, Toshio; and Ichinohe, Shoji, 5,587,445, Cl. 526-271.000.
- ICTV, Inc.: *See—*
- Lauder, Gary M.; Hoarty, W. Leo; and Soske, Joshua W., 5,587,734, Cl. 348-10.000.
- Ida, Ayako: *See—*
- Tomioka, Jun; Uetani, Yasunori; Nakanishi, Hiroto; Hanawa, Ryo-taro; and Ida, Ayako, 5,587,492, Cl. 549-406.000.
- Idaka, Toshiaki; and Ezawa, Hirokazu, to Kabushiki Kaisha Toshiba, Semiconductor process for forming bump electrodes with tapered sidewalls, 5,587,337, Cl. 437-183.000.
- Idemitsu Kosoan Co., Ltd.: *See—*
- Shibata, Mitsuru; Sakamoto, Masashi; and Nasuno, Ichiro, 5,587,484, Cl. 548-364.400.
- IDX, Inc.: *See—*
- Halsey, James H.; Judd, Scott; and Erwin, James W., 5,586,684, Cl. 221-90.000.
- Igarashi, Ryosaku: *See—*
- Nakada, Katsumi; Imai, Akira; and Igarashi, Ryosaku, 5,587,263, Cl. 430-56.000.
- Iguchi, Yutaka; Sato, Kazuo; Kobayashi, Toshihiro; and Sato, Masayuki, to Aisin Seiki Kabushiki Kaisha, Angular rate detector, 5,587,529, Cl. 73-504.130.
- Iida, Giichi, to Kioritz Corporation, Leaf vacuum with rotary cutting blade, 5,586,359, Cl. 15-339.000.
- Iida, Kazuhiro, to NEC Corporation, Optimization device, 5,587,897, Cl. 364-148.000.
- Iida, Yoshikazu: *See—*
- Nakamura, Toshiyuki; and Iida, Yoshikazu, 5,587,764, Cl. 396-55.000.
- Iijima, Masayuki; Dantani, Kyoji; Obata, Hiroyuki; Matsuo, Makoto; Utsumi, Minoru; and Take, Seiji, to Dai Nippon Printing Co. Ltd., Electrostatic information recording medium and electrostatic information recording and reproducing method, 5,587,264, Cl. 430-57.000.
- Iijima, Ryunosuke; and Kaneda, Kitahiro, to Canon Kabushiki Kaisha, Lens control system, 5,587,842, Cl. 359-698.000.
- Iimura, Katsuhiko: *See—*
- Tanaka, Shoji; Iimura, Katsuhiko; and Kageyama, Satoshi, 5,588,065, Cl. 381-96.000.
- Iino, Kenichi: *See—*
- Furuya, Yuji; and Iino, Kenichi, 5,586,726, Cl. 239-533.120.
- Iizuka, Takashi, to Asahi Kogaku Kogyo Kabushiki Kaisha, Scanning optical system, 5,587,825, Cl. 359-204.000.
- Ikazaki, Fumikazu: *See—*
- Ohshima, Satoshi; Yumura, Motoo; Kuriki, Yasunori; Uchida, Kunio; and Ikazaki, Fumikazu, 5,587,141, Cl. 423-445.00B.
- Ikeda, Hideo; Shuto, Sadanobu; and Hara, Takefumi, to Fuji Photo Film Co., Ltd., Light-sensitive silver halide emulsion and photographic light-sensitive material using the same, 5,587,280, Cl. 430-567.000.
- Ikeda, Keiji: *See—*
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,921, Cl. 440-38.000.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,922, Cl. 440-88.000.
- Ikeda, Mitsuhiro: *See—*

- Sakaguchi, Shozo; Ikeda, Mitsuhiro; and Chiba, Syusaku, 5,586,436, Cl. 60-585.000.
- Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, to Sanden Corporation; and Honda Giken Kogyo Kabushiki Kaisha. Defrosting control system for use in an air-conditioner in an electric vehicle. 5,586,448, Cl. 62-156.000.
- Ikeda, Tomohiro: See—
Yamamoto, Takatsuo; Kobayashi, Shigehiko; and Ikeda, Tomohiro, 5,587,556, Cl. 174-74.00R.
- Ikeda, Tomoyuki; Ito, Yoshinobu; and Matui, Ryotaro, to Hamamatsu Photonics K.K. Gas discharge tube. 5,587,625, Cl. 313-613.000.
- Ikegawa, Akihito; Arimoto, Kouichi; Tsukamoto, Kazuki; and Yamashita, Michiya, to Minolta Camera Kabushiki Kaisha. Developing apparatus. 5,587,551, Cl. 118-661.000.
- Ikegawa, Akihito: See—
Taniguchi, Kazuko; Ikegawa, Akihito; Uno, Koji; and Saito, Hitoshi, 5,587,775, Cl. 355-219.000.
- Ikegaya, Akihiko; Tanabe, Keiichi; and Fujimori, Naoki, to Sumitomo Electric Industries, Ltd. Methods of synthesizing and polishing a flat diamond film and free-standing diamond film. 5,587,013, Cl. 117-89.000.
- Ikemoto, Yoshiaki: See—
Tsutsumi, Haruki; Ikemoto, Yoshiaki; Maehama, Mitsuhiro; Oyanagi, Toshiki; and Matsubara, Tsugio, 5,587,246, Cl. 428-511.000.
- Ikenoue, Yoshikazu: See—
Kamel, Nobuo; Ikenoue, Yoshikazu; and Yamamoto, Hideo, 5,587,801, Cl. 358-296.000.
- Ikeoka, Naoki: See—
Ogawa, Kazuo; and Ikeoka, Naoki, 5,586,495, Cl. 100-207.000.
- Iketaka, Satoshi: See—
Ohmura, Hitoshi; Koyakumaru, Yasuhiro; and Iketaka, Satoshi, 5,587,248, Cl. 428-610.000.
- Ikeuchi, Michio: See—
Murata, Yasumoto; Ikeuchi, Michio; Yoshikawa, Shuichi; and Watanabe, Masahiko, 5,588,052, Cl. 379-283.000.
- Ikeyama, Nobuhide; and Iwanaga, Yutaka, to Mitsui Mining Co., Ltd. Dry process desulfurization and denitrification process. 5,587,136, Cl. 423-239.100.
- Illinois Tool Works Inc.: See—
Maki, Roger M., 5,586,661, Cl. 209-397.000.
- Imai, Akira: See—
Nukada, Katsumi; Imai, Akira; and Igarashi, Ryosaku, 5,587,263, Cl. 430-56.000.
- Imai, Masahiro: See—
Imai, Toru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12.020.
- Imai, Toru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, to Kabushiki Kaisha. Float-type clutch for automatic washing machine. 5,586,455, Cl. 68-12.020.
- Imamura, Makoto, to Yokogawa Electric Corporation. Pulse generator including slow rate controller without complementary transistors. 5,587,679, Cl. 327-170.000.
- IMAX Corporation: See—
Gibson, Michael A.; Maxwell, Ian; and Toporkiewicz, Marian, 5,587,750, Cl. 352-184.000.
- Imperial Chemical Industries PLC: See—
Leenslag, Jan W.; and Verbeke, Hans G. G., 5,587,414, Cl. 524-394.000.
- Ina, Toshiro: See—
Sasaki, Ryo; and Ina, Toshiro, 5,587,418, Cl. 524-504.000.
- Ina Walzinger Schaeffler KG: See—
Speil, Walter, 5,586,528, Cl. 123-90.510.
- Inaba, Yasuo: See—
Harada, Masahiro; and Inaba, Yasuo, 5,587,447, Cl. 528-347.000.
- Inami, Daijiro; and Sato, Yuichi, to NEC Corporation. Output buffer circuit for high-speed logic operation. 5,587,667, Cl. 326-17.000.
- Inami, Junichi: See—
Adachi, Shuhei; and Inami, Junichi, 5,586,530, Cl. 123-188.800.
- Incyte Pharmaceutical Corporation: See—
Nedwin, Glenn E.; Bringman, Timothy S.; and Couraud, Pierre-Olivier, 5,587,460, Cl. 530-396.000.
- Incyte Pharmaceuticals, Inc.: See—
Hawkins, Phillip R.; Wilde, Craig G.; and Seilhamer, Jeffrey J., 5,587,301, Cl. 435-69.100.
- Hawkins, Phillip R.; and Seilhamer, Jeffrey J., 5,587,306, Cl. 435-198.000.
- Indeck, Ronald S.; and Muller, Marcel W., to Washington University. Method and apparatus for noise reduction in magnetic media recordings. 5,587,654, Cl. 324-225.000.
- Industrial Technology Research Institute: See—
Chen, Jim, 5,587,843, Cl. 359-700.000.
- Chiu, Chung-Yen, 5,587,708, Cl. 341-76.000.
- Ingersoll-Rand Company: See—
Gardner, Richard K., 5,586,480, Cl. 91-169.000.
- Kimberlin, Robert R.; Bodell, Steven W.; Chang, Ted C.; Diesel, Robert M.; and Barker, Scott, 5,586,606, Cl. 173-62.000.
- Sajatovic, James N., 5,586,610, Cl. 175-195.000.
- Inland Craft Products Co.: See—
Wiand, Richard K.; and Buschmohle, Dennis R., 5,586,928, Cl. 451-177.000.
- Innerspace, Inc.: See—
Bobo, Donald E., Jr.; and Doupe, Thomas H., 5,586,555, Cl. 128-672.000.
- Inoue, Atsuo: See—
Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
- Inoue, Kunitoshi: See—
Kubouchi, Kenji; Fukui, Yuji; and Inoue, Kunitoshi, 5,586,776, Cl. 277-235.00B.
- Inoue, Mitsuru; and Kurosawa, Hiroyuki, to Hitachi, Ltd. Storage system having a bus common to a plurality of kinds of groups of packages. 5,588,144, Cl. 395-555.000.
- Inoue, Sadayuki: See—
Inoue, Tohru; Onishi, Ken; Inoue, Sadayuki; and Okuma, Ikuo, 5,587,803, Cl. 386-33.000.
- Inoue, Tohru; Onishi, Ken; Inoue, Sadayuki; and Okuma, Ikuo, to Mitsubishi Denki Kabushiki Kaisha. Digital signal recording and reproducing apparatus and error-correcting apparatus. 5,587,803, Cl. 386-33.000.
- Institut Francais Du Pétrole: See—
Gauthier, Thierry, 5,586,998, Cl. 55-391.000.
- Institut National de la Recherche Agronomique - I.N.R.A.: See—
Barre, Pierre; Dequin, Sylvie; and Ansanay, Virginie, 5,587,304, Cl. 435-139.000.
- Institute for Laser Technology: See—
Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367.000.
- Instratek, Inc.: See—
Barrett, Stephen L.; and Brown, Michael G., 5,586,564, Cl. 128-898.000.
- Integrated Microtransducer Electronics Corporation: See—
Torok, James; and Spitzer, Richard, 5,587,943, Cl. 365-158.000.
- Integrity Industries, Inc.: See—
Duncan, William M., Jr., 5,587,354, Cl. 507-137.000.
- Intel Corporation: See—
Abramson, Jeffrey M.; Akkary, Hatham; Glew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395-376.000.
- Kowalczyk, Robert M.; Brown, Robert H., III; and Heller, Jack W., 5,587,957, Cl. 365-230.030.
- Massie, Harold L., 5,587,650, Cl. 323-282.000.
- InterDigital Technology Corporation: See—
Schilling, Donald L., 5,588,020, Cl. 370-337.000.
- Interface, Inc.: See—
Terry, Claude E.; Triestman, Douglas E.; and Price, Daniel L., 5,587,407, Cl. 523-122.000.
- Intermagnetics General Corporation: See—
Blecher, Leo; Longworth, Ralph C.; Murray, F. Scott; Jonas, Philip A.; and Bojarski, Michael, 5,586,437, Cl. 62-47.100.
- International Business Machines Corporation: See—
Brooks, Jeffrey S.; and Dohanich, Stephen L., 5,587,935, Cl. 364-578.000.
- Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- DiPaolo, Nunzio; and Ferguson, Daniel J., 5,587,095, Cl. 219-388.000.
- Dorius, Lee K.; and Samuelson, Laurence S., 5,587,858, Cl. 360-103.000.
- Edgar, Albert D., 5,587,728, Cl. 347-19.000.
- Edgar, Albert D., 5,588,063, Cl. 381-24.000.
- Garcia, Armando, 5,588,122, Cl. 395-250.000.
- Hardell, William R., Jr.; and Qureshi, Amjad Z., 5,588,010, Cl. 371-37.600.
- Keller, John H.; and Costini, Gregory, 5,587,045, Cl. 156-627.100.
- Kotwa, Atsushi, 5,587,721, Cl. 345-89.000.
- Kurihara, Mikio; Nishi, Satoru; Onodera, Takahiro; and Kushima, Kazunari, 5,587,557, Cl. 174-266.000.
- Lin, Eileen T.; and Wang, Yun, 5,588,150, Cl. 395-601.000.
- Machesney, Brian J.; Mandelman, Jack A.; and Nowak, Edward J., 5,587,604, Cl. 257-350.000.
- Muyshondt, Jorge E.; Parker, Gary A.; and Wilkie, Bruce J., 5,587,920, Cl. 364-489.000.
- Ono, Makoto; and Minakata, Hiroshi, 5,588,097, Cl. 395-137.000.
- Voldman, Steven H.; Wallash, Albert J.; and Wilcox, Reginald B., Jr., 5,587,857, Cl. 360-103.000.
- International Computers Limited: See—
Reddin, Timothy G.; Walsh, David S.; and Round, Jeremy S., 5,588,121, Cl. 395-200.150.
- International Minicut, Inc.: See—
Miniccozzi, Alfonso, 5,586,843, Cl. 407-42.000.
- International Mobile Satellite Organization: See—
Feldman, Howard R., 5,587,810, Cl. 358-442.000.
- International Paper Company: See—
Kinsey, Joe L., Jr.; and Lanham, Robert L., Jr., 5,587,204, Cl. 427-411.000.
- Invamed, Inc.: See—
Patel, Mahendra R.; Reddy, Kasireddy C.; and Dave, Pankaj J., 5,587,377, Cl. 514-254.000.
- Ioka, Kazuo: See—

- Shindo, Yasuhiro; Yamaguti, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro; and Kitabatake, Syoichi, 5,587,320, Cl. 435-290.100.
- Iomega Corporation: See—
Ma, Yiping, 5,588,007, Cl. 371-21.200.
- Iowa State University Research Foundation, Inc.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.
- Ipri, Alfred C.: See—
Hseuh, Fu-Lung; Ipri, Alfred C.; Dolny, Gary M.; and Stewart, Roger G., 5,587,329, Cl. 437-40.000.
- Iranmanesh, Ali, to Crosspoint Solutions, Inc. Low-capacitance, isotropically etched antifuse and method of manufacture therefor. 5,587,613, Cl. 257-530.000.
- Isbell, Matthew R.; and Pessier, Rudolf C. O., to Baker Hughes Incorporated. Roller cone bit with positive and negative offset and smooth running configuration. 5,586,612, Cl. 175-353.000.
- Ishibashi, Fumio: See—
Kubo, Kohji; Nezu, Shoichi; Ishibashi, Fumio; Harada, Hiroyuki; and Shigematsu, Yuji, 5,587,247, Cl. 428-523.000.
- Ishida, Kiyoshi; and Goto, Hiroshi, to Hitachi, Ltd. Video telephone. 5,587,735, Cl. 348-14.000.
- Ishida, Masayuki: See—
Endo, Kazuhito; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto, Manabu; and Hirai, Nobuaki, 5,587,978, Cl. 369-32.000.
- Ishida, Yasushi: See—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.
- Ishida, Yoshinobu: See—
Endo, Kazuhito; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto, Manabu; and Hirai, Nobuaki, 5,587,978, Cl. 369-32.000.
- Ishiguro, Shoji: See—
Mifune, Hiroyuki; Yamanouchi, Junichi; and Ishiguro, Shoji, 5,587,279, Cl. 430-567.000.
- Ishii, Akio: See—
Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi, 5,587,378, Cl. 514-264.000.
- Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro; and Kashiwabara, Yasushige, to Hitachi, Ltd. Rotating stall prevention system for compressor. 5,586,857, Cl. 415-23.000.
- Ishii, Mitsuo, to Sharp Kabushiki Kaisha. Magnetic head driving device with prerecording energization. 5,587,851, Cl. 360-59.000.
- Ishikawa Gasket Co., Ltd.: See—
Udagawa, Tsunekazu; and Yamada, Kenji, 5,586,770, Cl. 277-11.000.
- Ishikawa, Hiraoku, to NEC Corporation. Method for fabricating an oxynitride film for use in a semiconductor device. 5,587,344, Cl. 437-238.000.
- Ishikawa, Hiroshi: See—
Fujise, Masakuni; and Ishikawa, Hiroshi, 5,588,036, Cl. 378-146.000.
- Ishikawa, Hiroyasu; and Kobayashi, Hideo, to Kokusai Denzetsu Denwa Co., Ltd. Method of compensating phase shift keying frequency offset. 5,588,026, Cl. 375-329.000.
- Ishikawa, Mitsuru: See—
Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
- Ishikawa, Wataru: See—
Asano, Hitoshi; Ishikawa, Wataru; and Nimura, Mitsuhiro, 5,587,911, Cl. 364-444.200.
- ISIS Pharmaceuticals, Inc.: See—
Cook, P. Dan; Acevedo, Oscar L.; and Andrews, Robert S., 5,587,470, Cl. 536-23.100.
- Cook, Phillip D.; and Hoke, Glenn, 5,587,361, Cl. 514-44.000.
- Cook, Phillip D.; Ramasamy, Kanda S.; and Manoharan, Muthiah, 5,587,469, Cl. 536-23.100.
- Cook, Phillip D.; Ecker, David J.; Acevedo, Oscar L.; and Davis, Peter, 5,587,471, Cl. 536-25.300.
- Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A., to Xerox Corporation. Digital film heat processor and method of developing digital film. 5,587,767, Cl. 355-27.000.
- Island Graphics Corporation: See—
Bowden, Lori; Jochums, Sharon L.; and Otus, Erol, 5,588,107, Cl. 395-344.000.
- Isoai, Masaru: See—
Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323.000.
- Isoe, Toshimi: See—
Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
- Isogai, Tomohiro: See—
Yamana, Masayuki; and Isogai, Tomohiro, 5,587,110, Cl. 252-511.000.
- Isorced, Inc.: See—
Mercer, Charles L.; and Philipps, Thomas E., 5,587,231, Cl. 428-283.000.
- Israel Aircraft Industries, Ltd.: See—
Ben-Yair, Igal; Berger, Haim; and Perelmutter, Oleg, 5,587,904, Cl. 364-449.700.
- Istituto Luso Farmaco D'Italia S.p.A.: See—
Salimbeni, Aldo; Paleari, Fabio; Mizrahi, Jacques; and Scolastico, Carlo, 5,587,390, Cl. 514-341.000.
- Itagaki, Yasuharu: See—
Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasuharu; and Nagao, Masaya, 5,587,359, Cl. 514-12.000.
- Ito, Hiroaki: See—
Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Ito, Hiroshi: See—
Kato, Satoru; Ito, Hiroshi; Ichikawa, Tadashi; and Kagami, Manabu, 5,587,785, Cl. 356-28.500.
- Ito, Koji: See—
Yamato, Shuhei; Ito, Koji; and Yamada, Mitsuo, 5,587,059, Cl. 204-505.000.
- Ito, Takaaki: See—
Kurasawa, Koichi; Harada, Mikio; and Ito, Takaaki, 5,587,867, Cl. 361-118.000.
- Ito, Takayuki, to Asahi Kogaku Kogyo Kabushiki Kaisha. Zoom lens system. 5,587,841, Cl. 359-689.000.
- Ito, Yoshinobu: See—
Ikeda, Tomoyuki; Ito, Yoshinobu; and Matui, Ryotaro, 5,587,625, Cl. 313-613.000.
- Ito, Yoshitoshi: See—
Maki, Atsushi; Kawaguchi, Fumio; Yamashita, Yuichi; and Ito, Yoshitoshi, 5,586,554, Cl. 128-653.100.
- Itoh, Hiroshi: See—
Yoshida, Kazuyoshi; Itoh, Hiroshi; Fukuoka, Hiroshi; and Shinohara, Makoto, 5,588,133, Cl. 395-477.000.
- Itoh, Kiyon: See—
Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Itoh, Kunio: See—
Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Issei; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.
- Itoh, Manabu: See—
Murakami, Kimihiro; Ohnishi, Shuhei; Yano, Takashi; and Itoh, Manabu, 5,587,392, Cl. 514-359.000.
- Itoh, Motoi: See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, 5,587,240, Cl. 428-367.000.
- Itoh, Yoshinori, to Canon Kabushiki Kaisha. Zoom lens. 5,587,840, Cl. 359-686.000.
- Itou, Shigehiro: See—
Fujiwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei; and Itou, Shigehiro, 5,587,989, Cl. 369-178.000.
- Itou, Takeo: See—
Shimizu, Kazuhiko; Itou, Takeo; and Matsuda, Hidemi, 5,587,835, Cl. 359-589.000.
- ITT Automotive Electrical Systems, Inc.: See—
Barnes, Steven J.; and Spence, Scott R., 5,586,871, Cl. 417-423.110.
- ITT Corporation: See—
Lothamer, Thomas J.; Pontecorvo, Carl A.; Schattke, Thomas L.; and Osterhout, Richard A., 5,587,568, Cl. 200-16.00R.
- Mosquera, Rene, 5,586,893, Cl. 439-108.000.
- Itel, Steven D.: See—
Gridnev, Alexei A.; and Ite, Steven D., 5,587,431, Cl. 525-269.000.
- Ivanek, Ivan: See—
Kumar, Pramatheesh; Grabiak, Matthias; and Ivanek, Ivan, 5,588,108, Cl. 395-348.000.
- Ive, Jonathan: See—
O'Brien, John; and Ive, Jonathan, 5,587,876, Cl. 361-682.000.
- Ive, Ronald A. Infant support pad with adjustable pillow. 5,586,351, Cl. 5-655.000.
- Ivri, Yehuda; and Wu, Cheng H., to Fluid Propulsion Technologies, Inc. Apparatus and methods for the delivery of therapeutic liquids to the respiratory system. 5,586,550, Cl. 128-200.160.
- Iwai, Kazuo: See—
Takizawa, Toshiaki; and Iwai, Kazuo, 5,586,595, Cl. 160-330.000.
- Iwanaga, Yutaka: See—
Ikeyama, Nobuhide; and Iwanaga, Yutaka, 5,587,136, Cl. 423-239.100.
- Iwano, Hideaki: See—
Mori, Katsumi; Asaka, Tatsuya; Iwano, Hideaki; and Kondo, Takayuki, 5,587,335, Cl. 437-129.000.
- Iwao, Kazuhiro: See—
Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayo; Iwao, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl. 355-208.000.
- Iwasaki, Hitoshi; Ohsawa, Yuichi; and Kondoh, Reiko, to Kabushiki Kaisha Toshiba. Ferromagnetic film. 5,587,026, Cl. 148-313.000.
- Iwasaki, Keisuke: See—
Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323.000.
- Iwasaki, Osamu: See—
Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiro; Kugo, Harumi; Sakazawa, Kazuhiro; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210.000.
- Iwasaki, Takao: See—

- Sonobe, Naohiro; Maruyama, Koji; and Iwasaki, Takao, 5,587,255, Cl. 429-218,000.
- Iwasaki, Tameo: See—
Kondo, Kazuhiko; Horikawa, Hiroshi; and Iwasaki, Tameo, 5,587,474, Cl. 540-350,000.
- Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masa-hiro; and Yamamoto, Yoshihisa, to Aisin AW Co., Ltd. Control system for automatic transmission, 5,586,954, Cl. 477-93,000.
- Iwata, Katsuchi: See—
Tsuchimoto, Tomonori; Iwata, Katsuchi; and Kurashima, Yoshihiko, 5,587,252, Cl. 429-49,000.
- Iyechika, Yasushi; and Takada, Tomoyuki, to Sumitomo Chemical Company, Limited. Method for manufacturing group III-V compound semiconductor crystals, 5,587,014, Cl. 117-90,000.
- Izawa, Yasukazu: See—
Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyoe; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367,000.
- Izumizawa, Takenori: See—
Uchida, Manabu; Izumizawa, Takenori; and Furukawa, Kenji, 5,587,444, Cl. 526-247,000.
- Izutsu, Tomoyoshi; and Kawashima, Kazuki, to NTN Corporation. Hydraulic autotensioner, 5,586,952, Cl. 474-110,000.
- J.F.A. Tech., Inc.: See—
Snyder, Bernard M., 5,588,038, Cl. 379-57,000.
- J. M. Huber Corporation: See—
Marshall, Carl J., Jr.; and Freeman, Gary M., 5,587,011, Cl. 106-416,000.
- J. Müller AG: See—
Jäger, Heinz, 5,587,787, Cl. 356-141,100.
- J. Vogel Premium Water: See—
Vogel, Gerald A.; and Tholen, Joseph H., 5,587,089, Cl. 210-164,000.
- Jacobs, Jochen: See—
Zeise, Christiane; Raehse, Wilfried; Jacobs, Jochen; and Hoffmeister, Juergen, 5,587,104, Cl. 510-298,000.
- Jacobson, Bruce S.; and Schnitzer, Jan E., to University of California, The Regents of the. Method for identification of disease-specific surface components of vascular endothelial cells, 5,587,297, Cl. 435-29,000.
- Jacobson, David M., to Hewlett-Packard Company. Method and apparatus for determining when all packets of a message have arrived, 5,587,997, Cl. 370-253,000.
- Jaacklin, André; Ramezani, Ezatollah; Roggwiller, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jörg, to ABB Management AG. Semiconductor component having gate turn-off thyristor and reduced thermal impairment, 5,587,594, Cl. 257-138,000.
- Jaffe, James M.: See—
Owen, William H.; and Jaffe, James M., 5,587,573, Cl. 235-380,000.
- Jaffe, Steven T.: See—
Strolle, Christopher H.; Jaffe, Steven T.; and Lyons, Paul W., 5,588,025, Cl. 375-316,000.
- Jäger, Heinz, to J. Müller AG. Process for measuring relative angles, 5,587,787, Cl. 356-141,100.
- Jahan, Dominique E.: See—
Blomet, Joël; Blomet épouse Meyer, Marie-Claude; and Jahan, Dominique F., 5,587,400, Cl. 514-566,000.
- Jahns, Ekkehard: See—
Kröner, Hubertus; Jahns, Ekkehard; and Mielke, Manfred, 5,587,404, Cl. 522-85,000.
- Jamieson, Bruce W. Safety vases for umbrella tables, 5,586,409, Cl. 47-41,010.
- Jana, Inc.: See—
Clouse, John D., 5,587,549, Cl. 89-14,300.
- Jang, Yong J., to Hyundai Electronics Industries Co., Ltd. Manual antenna alignment apparatus and method for very small aperture terminal, 5,587,717, Cl. 342-359,000.
- Jansen, Guy D. A.: See—
Horsten, Bartholomeus C.; Uyttendaele, Carlo A.; Jansen, Guy D. A.; and Schuerwegen, Ronald, 5,587,350, Cl. 503-201,000.
- Jansen, Leo B.: See—
Pherigo, Douglas E.; and Jansen, Leo B., 5,586,393, Cl. 33-288,000.
- Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdonck, Marc G. C.; and Janssen, Paul A. J., to Janssen Pharmaceutica N.V. Heterocycle-substituted benzenemethanamine derivatives, 5,587,387, Cl. 514-312,000.
- Janssen, Paul A. J.: See—
Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdonck, Marc G. C.; and Janssen, Paul A. J., 5,587,387, Cl. 514-312,000.
- Janssen Pharmaceutica N.V.: See—
Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdonck, Marc G. C.; and Janssen, Paul A. J., 5,587,387, Cl. 514-312,000.
- Janssens, Wilhelmus; Van den Bogaert, Jan; Vanmaele, Luc; and Defeuw, Geert, to Agfa-Gevaert N.V. Thermal imaging process and an assemblage of a donor and receiving element for use therein, 5,587,270, Cl. 430-203,000.
- Janssens, Wilhelmus: See—
Defeuw, Geert; Janssens, Wilhelmus; and Vanmaele, Luc, 5,587,268, Cl. 430-200,000.
- Javitt, Norman B., to New York University. Administration of a 27-hydroxycholesterol or related compound or sterol-27-hydroxylase stimulant to prevent restenosis following vascular endothelial injury, 5,587,368, Cl. 514-177,000.
- Jazayeri, Mehdi; Hui, Edward S.; and Korsh, George J., to Atmel Corporation. High speed, low voltage non-volatile memory, 5,587,951, Cl. 365-203,000.
- JDS Fitel Inc.: See—
Cheng, Yihao; and Duck, Gary S., 5,588,078, Cl. 385-33,000.
- Jean, Pierre; and Chauvin, Jean-Michel, to Gaztransport & Technigaz. Water-tight and thermally insulating tank built into a bearing structure, 5,586,513, Cl. 114-74,00A.
- JEM Industries, Inc.: See—
Kish, Arthur S., 5,586,748, Cl. 251-149,800.
- Jenkins, Scott: See—
Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert; and Froen, Diane, 5,587,481, Cl. 546-146,000.
- Jenkins, Shawn B.: See—
Alexander, Tommy; and Jenkins, Shawn B., 5,586,704, Cl. 224-605,000.
- Jeong, Deog-Kyoon, to Jeong, Deog-Kyoon; and Sun Microsystems, Inc. High speed serial link for fully duplexed data communication, 5,587,709, Cl. 341-100,000.
- Jeppson, Bengt: See—
Bengmark, Stig; Ahmè, Siv; Molin, Göran; and Jeppson, Bengt, 5,587,314, Cl. 435-252,900.
- Jericevic, Zeljko: See—
Dragoset, William H., Jr.; and Jericevic, Zeljko, 5,587,965, Cl. 367-24,000.
- Jet-Tech, Inc.: See—
Norcross, Kenneth L.; and Li, Yanlong, 5,587,081, Cl. 210-604,000.
- Jevic, John M.; and Dow, Randall P., to Framatome Technologies, Inc.; and Babcock & Wilcox Company, The. Nuclear steam generator chemical cleaning passivation solution, 5,587,025, Cl. 148-274,000.
- Jewett, Douglas E.: See—
Cutts, Richard W., Jr.; Banton, Randall G.; and Jewett, Douglas E., 5,588,111, Cl. 395-182,070.
- Jia, Quanxi: See—
Anderson, Wayne A.; Jia, Quanxi; Yi, Junsin; and Chang, Lin-Huang, 5,587,870, Cl. 361-313,000.
- Jiang, Chun, to VLSI Technology, Inc. Testing hot carrier induced degradation to fall and rise time of CMOS inverter circuits, 5,587,665, Cl. 326-16,000.
- Jidosha Kiki Co., Ltd.: See—
Watanabe, Makoto, 5,586,481, Cl. 91-376,00R.
- Jin, Haolun: See—
Belleau, Bernard, deceased; Nguyen-Ba, Nghe; Kong, Laval C. C.; Mansour, Tarek; Jin, Haolun; and Brasili, Livio, 5,587,480, Cl. 544-310,000.
- Jimbo, Shinichi; and Mori, Shigeru, to Mitsubishi Denki Kabushiki Kaisha. Power supply circuit for generating an internal power supply potential based on an external potential, 5,587,648, Cl. 323-269,000.
- Jiuh Yih Hardware Co., Ltd.: See—
Chung, Fa-Chih, 5,587,018, Cl. 118-679,000.
- Jo, Hae-Seog; Ko, Chang-Kyung; and Lee, Dong-Ho, to Samsung Electronics Co., Ltd. Device for detecting remaining level of toner, 5,587,770, Cl. 355-208,000.
- Jochums, Sharon L.: See—
Bowden, Lori; Jochums, Sharon L.; and Otus, Erol, 5,588,107, Cl. 395-344,000.
- Joe, Moon J.: See—
Lee, Heun J.; and Joe, Moon J., 5,588,073, Cl. 382-187,000.
- Johansson, Christopher W., to Hewlett-Packard Company. System for suppressing power transients when connecting a disk drive in an operating raid system, 5,587,685, Cl. 327-546,000.
- Johansson, Gert A. Garment hanger, 5,586,697, Cl. 223-85,000.
- Johansson, Ted; and Gobbi, Jose-Maria, to Telefonaktiebolaget LM Ericsson. Capacitor in an integrated function block or an integrated circuit having high capacitance, a method for manufacturing said capacitor and utilizing of said capacitor as an integrated decoupling capacitor, 5,587,333, Cl. 437-60,000.
- Johdai, Akiyoshi; Ohhata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu; and Hirano, Yoshihito, to Minolta Co., Ltd. Copying machine for copying documents in two-in-one mode, 5,587,782, Cl. 355-309,000.
- Johns Hopkins University, The: See—
Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H., 5,587,384, Cl. 514-309,000.
- Johns, Joseph J. Portable dowel boring tool, 5,586,846, Cl. 408-72,00R.
- Johnsen, Tyrone A., to Sundstrand Corporation. Rotor for a dynamoelectric machine having a one-piece rotation rectifier, 5,587,616, Cl. 310-68,00D.
- Johnson & Johnson Clinical Diagnostics, Inc.: See—
Scalice, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L., 5,587,287, Cl. 435-6,000.
- Johnson, Anders R., to Seiko Epson Corporation. Register file backup queue, 5,588,113, Cl. 395-182,130.
- Johnson, Gary C.: See—
Olson, Timothy L.; Carney, Lauriann T.; Johnson, Gary C.; and Strom, William M., 5,587,883, Cl. 361-723,000.
- Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance, to SmithKline Beecham PLC. Process for preparing tetrazol-5-yl substituted benzopyran compounds, 5,587,483, Cl. 548-252,000.
- Johnson, James H. Truck bed cargo divider, 5,586,850, Cl. 410-138,000.

- Johnson, Kurtis F. Scintillating optical fibers containing non-uniformly distributed dopants and process for preparing same, 5,588,084, Cl. 385-123,000.
- Johnson, Lonnie G.; and Applewhite, John, to Johnson Research & Development Company, Inc. Electric pump toy water gun, 5,586,688, Cl. 222-61,000.
- Johnson, Max L.: See—
DeKoning, Rodney A.; Humlicek, Donald R.; and Johnson, Max L., 5,588,110, Cl. 395-182,030.
- Johnson, Melvin H.; and Willis, Frank M., to Du Pont de Nemours, E. I., and Company. Process for injection molding optical ferrules, 5,587,116, Cl. 264-1,250.
- Johnson Research & Development Company, Inc.: See—
Johnson, Lonnie G.; and Applewhite, John, 5,586,688, Cl. 222-61,000.
- Johnson, Steven A.; Wiskin, James W.; Borup, David T.; Christensen, Douglas A.; and Stenger, Frank. Apparatus and method for imaging with wavefields using inverse scattering techniques, 5,588,032, Cl. 378-8,000.
- Johnson Worldwide Associates, Inc.: See—
Heisler, Kurt W.; and Haddock, Richard S., 5,586,699, Cl. 224-628,000.
- Johnston, Law A. Y.: See—
Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srikantha, Alagacane; and Riding, George A., 5,587,311, Cl. 435-240,200.
- Joist, Michael, to Schöffel GmbH. Extracting device for plug-in modules, 5,587,888, Cl. 361-802,000.
- Jonas, Philip A.: See—
Blecher, Leo; Longworth, Ralph C.; Murray, F. Scott; Jonas, Philip A.; and Boiarski, Michael, 5,586,437, Cl. 62-47,100.
- Jones, Curtis R.: See—
Stupek, Richard A., Jr.; Shaffer, David S.; Jones, Curtis R.; Davis, Steve; and Justice, William D., Jr., 5,588,143, Cl. 395-500,000.
- Jones, Frank N.; Fu, Shou-Kuan; Hua, Jun; and Yuan, Xiaoyang, to Eastern Michigan University. Polymeric vehicle effective for providing solventless coating compositions, 5,587,428, Cl. 525-165,000.
- Jones, Gary W., to FED Corporation. Field emitter structure and method of making the same, 5,587,623, Cl. 313-497,000.
- Jones, Jeanee: See—
Belcher, James F.; Frank, Steven N.; Long, John P.; and Jones, Jeanee, 5,587,090, Cl. 216-17,000.
- Jones, Joel W.; and Wu, Ya, to Tri-Way Machine Ltd. Tool condition monitoring system, 5,587,931, Cl. 364-551,020.
- Jones, Oliver; Deshon, Mary; Ericsson, Staffan; and Flach, James, to Vivo Software, Inc. Computer teleconferencing method and apparatus, 5,587,928, Cl. 364-514,00A.
- Jones, Stephen R.: See—
Aho, Wilho V., Jr.; Jones, Stephen R.; Chetta, Gregory E.; and Strout, Terry H., 5,587,068, Cl. 210-188,000.
- Joseph, Douglas A.: See—
Babuder, Kirt M.; Joseph, Douglas A.; Pistoore, Donald; and Stupica, L. Joseph, 5,586,477, Cl. 82-126,000.
- Juds, Scott: See—
Halsey, James H.; Juds, Scott; and Erwin, James W., 5,586,684, Cl. 221-90,000.
- Juga, Douglas L.: See—
Bullock, Charles E.; and Juga, Douglas L., 5,586,459, Cl. 70-224,000.
- Julow, Jay K.; DeRegnaucourt, Robert A.; and Hall, John C., to Dayton Walther Corporation. Method for final balancing a brake drum, 5,586,625, Cl. 188-218,00R.
- Jun, Young-Kwon. Method of forming a contact hole for a metal line in a semiconductor device, 5,587,331, Cl. 437-41,000.
- Jung, Pan S.; and Yaniv, Daphna R., to Molecular Imaging Corporation. Atomic force microscope employing beam tracking, 5,587,523, Cl. 73-105,000.
- Jung, Richard H.: See—
Lian, Ke K.; Li, Changming; Jung, Richard H.; and Kines, Joseph G., 5,587,872, Cl. 361-525,000.
- Junino, Alex; LaGrange, Alain; N'Guyen, Quang L.; and Bourboulon, Marie-Alix, to L'Oreal. Utilization of derivatives of 2,5 dihydroxyphenyl-carboxylic acid amides and their salts in preparation of a cosmetic or dermatological composition with a depigmenting action, 5,587,173, Cl. 424-401,000.
- Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P., to Neurex Corporation. Omega conopeptide compositions, 5,587,454, Cl. 530-324,000.
- Justice, William D., Jr.: See—
Stupek, Richard A., Jr.; Shaffer, David S.; Jones, Curtis R.; Davis, Steve; and Justice, William D., Jr., 5,588,143, Cl. 395-500,000.
- Kabacoff, Lawrence T.: See—
Barkyoub, John; Kabacoff, Lawrence T.; and Land, David J., 5,586,824, Cl. 374-44,000.
- Kabakov, Viktor G.: See—
Skobelev, Valery V.; Slavin, Mikhail A.; Selezov, Evgeny A.; Kabakov, Viktor G.; and Puzikov, Gennady S., 5,586,872, Cl. 417-477,800.
- kabelmetal electro GmbH: See—
Schauer, Friedrich; and Neuner, Andreas, 5,586,381, Cl. 29-434,000.
- Kablau, Johannes G. F.; Mimmagh, Winslow M.; and Hoeven, Petrus C. J., to U.S. Philips Corporation. Method deriving a quality signal from a read signal, and reading and recording devices which employ that method, 5,587,980, Cl. 369-54,000.
- Kabushiki Kaisha B-AI: See—
Nakada, Takashi; Kazami, Keiichi; and Kaneko, Kenji, 5,587,545, Cl. 84-600,000.
- Kabushiki Kaisha Daikin Seisakusho: See—
Mizukami, Hiroshi; Uenohara, Norihisa; and Takeuchi, Hiroshi, 5,586,633, Cl. 192-70,250.
- Kabushiki Kaisha Komatsu Seisakusho: See—
Ogawa, Kazuo; and Ikeoka, Naoaki, 5,586,495, Cl. 100-207,000.
- Takebe, Makoto; and Hagiwara, Masao, 5,587,995, Cl. 370-248,000.
- Yoshida, Koji; Yamazaki, Taku; and Mori, Akira, 5,587,094, Cl. 219-121,680.
- Kabushiki Kaisha Muraharu Seisakusho: See—
Murakami, Toshiyuki, 5,586,683, Cl. 221-33,000.
- Kabushiki Kaisha Riken: See—
Ooya, Masaki, 5,587,227, Cl. 428-217,000.
- Kabushiki Kaisha Sato: See—
Goto, Fumio, 5,587,044, Cl. 156-577,000.
- Kabushiki Kaisha Toshiba: See—
Fujise, Masakuni; and Ishikawa, Hiroshi, 5,588,036, Cl. 378-146,000.
- Hamada, Susumu, deceased; and Araki, Dai, 5,587,918, Cl. 364-488,000.
- Hatanaka, Kazuhisa, 5,587,598, Cl. 257-355,000.
- Hirose, Kenji, 5,588,149, Cl. 395-601,000.
- Idaka, Toshiaki; and Ezawa, Hirokazu, 5,587,337, Cl. 437-183,000.
- Imai, Toru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12,020.
- Iwasaki, Hitoshi; Ohsawa, Yuichi; and Kondoh, Reiko, 5,587,026, Cl. 148-313,000.
- Kanazawa, Hitoshi, 5,587,657, Cl. 324-309,000.
- Kaneko, Tetsuya; and Ohsawa, Takashi, 5,587,958, Cl. 365-230,060.
- Kawasaki, Masayuki; Kuwasima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, 5,587,683, Cl. 327-538,000.
- Nabeshima, Daiki; and Ozaki, Naoki, 5,587,991, Cl. 369-275,300.
- Nakai, Hiroto, 5,587,948, Cl. 365-185,170.
- Nozuyama, Yasuyuki, 5,588,006, Cl. 371-3,000.
- Sato, Toshikuni; and Agetatsu, Masaya, 5,587,854, Cl. 360-97,010.
- Shimizu, Kazuhiko; Ito, Takeo; and Matsuda, Hidemi, 5,587,835, Cl. 359-589,000.
- Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shini-chi; and Kawata, Yasushi, 5,587,819, Cl. 349-106,000.
- Toda, Haruki; Saito, Shozo; and Tokushige, Kaoru, 5,587,963, Cl. 365-236,000.
- Yoshida, Kazuyoshi; Itoh, Hiroshi; Fukuoka, Hiroshi; and Shinohara, Makoto, 5,588,133, Cl. 395-477,000.
- Kabushiki Kaisha Toyoda Jidoshokki Seisakusho: See—
Asai, Isao; and Hasegawa, Toshinori, 5,586,428, Cl. 57-269,000.
- Kawaguchi, Masahiro; Sonobe, Masanori; Kanzaki, Shigeki; and Yokono, Tomohiko, 5,586,870, Cl. 417-222,200.
- Kabushiki Kaisha Toyota Chuo Kenkyusho: See—
Kato, Satoru; Ito, Hiroshi; Ichikawa, Tadashi; and Kagami, Manabu, 5,587,785, Cl. 356-28,500.
- Kabushiki Kaisha Yakult Honsha: See—
Murakami, Toshiyuki, 5,586,683, Cl. 221-33,000.
- Kadono, Shinya: See—
Yamada, Masazumi; Kadono, Shinya; and Kato, Shiro, 5,587,806, Cl. 386-68,000.
- Kadowaki, Hideaki: See—
Miyaji, Takashi; Nishikawa, Yoshikazu; Andou, Yukinori; Yamanaka, Toshio; and Kadowaki, Hideaki, 5,587,777, Cl. 355-245,000.
- Kadowaki, Shin-ichi: See—
Sano, Kousei; and Kadowaki, Shin-ichi, 5,587,985, Cl. 369-124,000.
- Kagami, Manabu: See—
Kato, Satoru; Ito, Hiroshi; Ichikawa, Tadashi; and Kagami, Manabu, 5,587,785, Cl. 356-28,500.
- Kagawa, Shuichi; Chiba, Kazuhiro; Bamba, Noriko; and Okuno, Yoshiaki, to Mitsubishi Denki Kabushiki Kaisha. Method and apparatus for performing color conversion, 5,588,050, Cl. 382-167,000.
- Kageyama, Satoshi: See—
Tanaka, Shoji; Iimura, Katsuhiko; and Kageyama, Satoshi, 5,588,065, Cl. 381-96,000.
- Kaiser Optical Systems: See—
Chang, Byung J.; and Tedesco, James M., 5,587,847, Cl. 359-890,000.
- Kajiura, Yasuya, to Mitsubishi Denki Kabushiki Kaisha. Distance measurement device and vehicle velocity control device for maintaining inter-vehicular distance, 5,587,908, Cl. 364-426,041.
- Kalahasthy, Gopichand; and Zinke, James R., II, to Bundy Corporation. Quick connector with integral release mechanism, 5,586,792, Cl. 285-319,000.
- Kalkowski, Klaus: See—
Altekrüger, Burkhard; Aufreiter, Joachim; Brüss, Dieter; and Kalkowski, Klaus, 5,587,016, Cl. 117-214,000.
- Kalo, Steven M.: See—
Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Convers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., 5,587,272, Cl. 430-257,000.
- Kamata, Atsushi: See—
Negi, Shigetoe; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222,000.
- Kamatani, Yasuo. Multi-standard optical disk reading method having distinction process, 5,587,981, Cl. 369-58,000.

- Kamei, Nobuo; Ikenoue, Yoshikazu; and Yamamoto, Hideo, to Minolta Camera Kabushiki Kaisha. Digital image forming apparatus. 5,587,801, Cl. 358-296,000.
- Kamentsky, Louis A., to CompuCyt Corporation. Computerized microscope specimen encoder. 5,587,833, Cl. 359-393,000.
- Kamio, Masayoshi: See—
Horigane, Akira; Matsukura, Ushio; and Kamio, Masayoshi, 5,587,298, Cl. 435-41,000.
- Kampe, Klaus-Dieter; ter Meer, Hans-Ulrich; Egger, Norbert K.; and Vogel, Martin A., to Hoechst Aktiengesellschaft. Fullerene derivatives, method of synthesizing them and their use. 5,587,476, Cl. 540-472,000.
- Kanai, Masao. Drying apparatus having rotating vane assemblies and drying method using the same. 5,586,396, Cl. 34-59,000.
- Kanada, Kenta; and Kawamura, Kiyoshi, to Nippon Shokubai Co., Ltd. Aqueous resin composition. 5,587,410, Cl. 523-410,000.
- Kanazawa, Hiroshi; Okuda, Isao; Shinozaki, Shimpai; and Takishima, Suguru, to Asahi Kogaku Kogyo Kabushiki Kaisha. Magneto-optical disk drive system with magnetic head retracting mechanism and manual cartridge ejecting mechanism. 5,587,973, Cl. 369-13,000.
- Kanazawa, Hitoshi, to Kabushiki Kaisha Toshiba. Magnetic resonance imaging apparatus. 5,587,657, Cl. 324-309,000.
- Kanbar, Maurice S.: See—
De Bono, Edward; and Kanbar, Maurice S., 5,586,763, Cl. 273-285,000.
- Kane, William H.; and Ortel, Thomas L., to Duke University. Chimeric blood coagulation proteins. 5,587,310, Cl. 435-240,200.
- Kaneda, Kitahiro: See—
Iijima, Ryunosuke; and Kaneda, Kitahiro, 5,587,842, Cl. 359-698,000.
- Kaneko, Kenji: See—
Nakada, Takashi; Kazami, Keiichi; and Kaneko, Kenji, 5,587,545, Cl. 84-600,000.
- Kaneko, Tetsuya; and Ohsawa, Takashi, to Kabushiki Kaisha Toshiba. Semiconductor memory device including a boost potential generation circuit. 5,587,958, Cl. 365-230,060.
- Kaneko, Yoshio: See—
Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500,000.
- Kaneko, Yutaka: See—
Frank, Rickard; Kaneko, Yutaka; and Brandstrom, Per, 5,586,576, Cl. 137-559,000.
- Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, to Mazda Motor Corporation. Upper body structure of a vehicle. 5,586,799, Cl. 296-203,000.
- Kanjo, Wajih; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, to Westinghouse Air Brake Company. Railway braking apparatus. 5,586,812, Cl. 303-7,000.
- Kano, Kazuhiko; Takeuchi, Yukihiro; Watanabe, Takamoto; Ao, Kenichi; Kanosue, Masakazu; and Uenoyama, Hirofumi, to Nippondenso Co., Ltd. Semiconductor sensor method. 5,587,343, Cl. 437-228,000.
- Kanosue, Masakazu: See—
Kano, Kazuhiko; Takeuchi, Yukihiro; Watanabe, Takamoto; Ao, Kenichi; Kanosue, Masakazu; and Uenoyama, Hirofumi, 5,587,343, Cl. 437-228,000.
- Kanou, Kazuhiko: See—
Nakane, Shinsuke; Kanou, Kazuhiko; and Hashimoto, Takatsugu, 5,587,417, Cl. 524-495,000.
- Kansai Paint Company, Limited: See—
Yukawa, Yoshiyuki; Yabuta, Motoshi; Nakahata, Akimasa; and Sugimura, Yoh, 5,587,426, Cl. 525-124,000.
- Kansei Corporation: See—
Kawakami, Takahiro; Ogawa, Akira; and Ichimura, Etsuo, 5,587,531, Cl. 73-514,120.
- Kanzaki, Shigeki: See—
Kawaguchi, Masahiro; Sonobe, Masanori; Kanzaki, Shigeki; and Yokono, Tomohiko, 5,586,870, Cl. 417-222,200.
- KAO Corporation: See—
Hioki, Yuichi; Kurita, Kazuhiko; Kawabata, Keiko; and Azuma, Toshikazu, 5,587,353, Cl. 504-116,000.
- Ochiai, Ryujii; Morita, Kouzi; and Yahagi, Kazuyuki, 5,587,155, Cl. 424-70,280.
- Kapitz, Heinrich: See—
von Gentzkow, Wolfgang; Huber, Jürgen; Kapitz, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413,000.
- Kappel, Mark A.: See—
Wieloch, Christopher J.; Kappel, Mark A.; Annis, Jeffrey R.; Benard, David J.; Boehmer, Ellen; and Hildebrandt, Gernot, 5,587,861, Cl. 361-14,000.
- Karassik, Nancy M.: See—
Angelone, Philip P., Jr.; Karassik, Nancy M.; and Grace, William R., 5,587,153, Cl. 424-66,000.
- Karbach, Alexander: See—
Meltzer, Aaron D.; and Karbach, Alexander, 5,587,435, Cl. 525-437,000.
- Karcher, Michael: See—
Heider, Marc; Henkelmann, Jobem; and Karcher, Michael, 5,587,503, Cl. 556-427,000.
- Karinthi, Pierre; Buffenoir, Marc; and Belot, Dominique, to L'Air Liquide. Societe Anonyme pour l'Etude et l'Exploitation des Procédés Georges Claude. Combustion process. 5,587,283, Cl. 431-10,000.
- Karkantis, Peter N.: See—
Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,590, Cl. 141-386,000.
- Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,673, Cl. 215-310,000.
- Karl, Ulrich: See—
Knühl, Klaus; Karl, Ulrich; Müller, Stefan; and de Pozzoli, Bernd, 5,587,506, Cl. 560-12,000.
- Karmi, Gadi: See—
Tiedemann, Edward G., Jr.; Karmi, Gadi; and Quick, Frank, 5,588,043, Cl. 379-63,000.
- Karnowski, Mark J.: See—
Knuth, Stephen B.; Brown, Sanford M., III; and Karnowski, Mark J., 5,588,046, Cl. 379-67,000.
- Karp, Alan H.; Hao, Ming C.; and Gupta, Rajiv, to Hewlett-Packard Company. Sender-selective send/receive order processing on a per message basis. 5,588,117, Cl. 395-200,030.
- Karpov Institute of Physical Chemistry: See—
Gordetsky, Victor V.; Neburchilov, Vladimir A.; and Kolotykin, Y. M., 5,587,058, Cl. 204-290,000.
- Karube, Takaaki: See—
Sato, Shigehiro; Matsunaga, Yoshiyuki; Ono, Tsuyoshi; and Karube, Takaaki, 5,587,097, Cl. 219-543,000.
- Karz, Robert S., to Xerox Corporation. Redundant full width array thermal ink jet printing for improved reliability. 5,587,730, Cl. 347-43,000.
- Kasahara, Masayuki: See—
Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro; and Kashiwabara, Yasushige, 5,586,857, Cl. 415-23,000.
- Kasai, Satoshi: See—
Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhisa; and Kasai, Satoshi, 5,587,909, Cl. 364-431,080.
- Kashima-Kita Electric Power Corporation: See—
Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kanji, 5,587,132, Cl. 423-62,000.
- Kashiwabara, Yasushige: See—
Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro; and Kashiwabara, Yasushige, 5,586,857, Cl. 415-23,000.
- Kashiwagi, Akira: See—
Nezu, Takashi; and Kashiwagi, Akira, 5,586,627, Cl. 188-299,000.
- Kashiyama, Motohisa: See—
Yagi, Sakai; Tsuji, Masanori; Kashiyama, Motohisa; and Endo, Takayoshi, 5,586,900, Cl. 439-310,000.
- Kasihara, Takasi, to Matsushita Electric Industrial Co., Ltd. Projection lens unit. 5,587,838, Cl. 359-649,000.
- Kasprzyk, Philip G.: See—
King, C. Richter; Kasprzyk, Philip G.; and Bird, Robert E., 5,587,458, Cl. 530-387,300.
- Kass, Michael: See—
Williams, Lance J.; and Kass, Michael, 5,587,711, Cl. 341-144,000.
- Kasuya, Michio, to Canon Kabushiki Kaisha. Facsimile apparatus with common sheet conveying path. 5,587,812, Cl. 358-498,000.
- Katagiri, Shingo; and Ashikawa, Teruo, to Fuji Photo Film Co., Ltd. Cassette accommodating case. 5,586,654, Cl. 206-387,100.
- Katayama, Akihiro; and Yasuda, Yasuhiko, to Canon Kabushiki Kaisha. Image processing apparatus for advantageously encoding blocks of data having either substantially the same or varied colors. 5,588,069, Cl. 382-166,000.
- Katayama, Akira; and Terunuma, Hiroshi, to Nikon Corporation. Camera with guiding of rectilinear lens movement. 5,587,754, Cl. 396-144,000.
- Katckla, Jay R. Control system for a hot water tank construction, control device therefor and methods of making the same. 5,586,719, Cl. 236-21,000.
- Kato, Hidenobu: See—
Matsuda, Yoshio; and Kato, Hidenobu, 5,586,454, Cl. 66-193,000.
- Kato, Hideto, to Shin-Etsu Chemical Co., Ltd. Photosensitive resin composition and a process for forming a patterned polyimide film using the same. 5,587,275, Cl. 430-283,100.
- Kato, Hirokazu; and Mino, Hiroshi, to Yamaha Corporation. Karaoke apparatus having extendible and fixed libraries of song data files. 5,587,546, Cl. 84-609,000.
- Kato, Satoru; Ito, Hiroshi; Ichikawa, Tadashi; and Kagami, Manabu, to Kabushiki Kaisha Toyota Chuo Kenkyusho. Laser doppler velocimeter. 5,587,785, Cl. 356-28,500.
- Kato, Shiro: See—
Yamada, Masazumi; Kadono, Shinya; and Kato, Shiro, 5,587,806, Cl. 386-68,000.
- Kato, Tetsuaki; Arita, Soichi; and Nakamura, Masaru, to Fanuc Ltd. Flexible servo control method capable of specifying flexibility on working coordinates. 5,587,638, Cl. 318-568,140.
- Kato, Toshiyuki: See—
Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kuguminato, Hideo, 5,587,027, Cl. 148-320,000.
- Kato, Yukari: See—
Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203,000.
- Katoh, Akira: See—
Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachito; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684,000.
- Katoh, Kazumasa, to Fuji Photo Film Co., Ltd. Image formation method. 5,587,276, Cl. 430-440,000.
- Katoh, Yasuhiro: See—

- Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro; and Kashiwabara, Yasushige, 5,586,857, Cl. 415-23,000.
- Katsu, Kanemasa: See—
Negi, Shigeto; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222,000.
- Katsuki, Syuji: See—
Kawasaki, Masayuki; Kuwasima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, 5,587,683, Cl. 327-538,000.
- Katsuta, Kazuo; and Abe, Tadafumi, to Tachi-S Co., Ltd. System for covering a cushion member with a trim cover assembly. 5,586,377, Cl. 29-91,500.
- Katsuyama, Hidekazu: See—
Hirao, Yasunobu; Motoyama, Yuji; Nagasaka, Takashi; and Katsuyama, Hidekazu, 5,586,388, Cl. 29-830,000.
- Katz, Daniel B. Card game set having block shaped tiles. 5,586,764, Cl. 273-293,000.
- Kauffman, Joel M.; and Litak, Peter T., to Philadelphia College of Pharmacy and Science. Benzazole compounds with ESITP fluorescence. 5,587,112, Cl. 252-589,000.
- Kaul, Ashok: See—
Lawless, Michael W.; Soberon, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., 5,586,868, Cl. 417-53,000.
- Kauvar, Lawrence M.; and Villar, Hugo O., to Terrapin Technologies, Inc. Method to identify binding partners. 5,587,293, Cl. 435-7,210.
- Kawabata, Keiko: See—
Hioki, Yuichi; Kurita, Kazuhiko; Kawabata, Keiko; and Azuma, Toshikazu, 5,587,353, Cl. 504-116,000.
- Kawabe, Yuzo; and Sakaguchi, Noboru, to Shimano Inc. Spinning reel having an anti-reverse mechanism. 5,586,734, Cl. 242-247,000.
- Kawagoe, Tadashi; and Zyokko, Keizo, to Nippondenso Co., Ltd. Method and apparatus for controlling resistance welding. 5,587,091, Cl. 219-110,000.
- Kawaguchi, Fumio: See—
Maki, Atsushi; Kawaguchi, Fumio; Yamashita, Yuichi; and Ito, Yoshitoshi, 5,586,554, Cl. 128-653,100.
- Kawaguchi, Masahiro; Sonobe, Masanori; Kanzaki, Shigeki; and Yokono, Tomohiko, to Kabushiki Kaisha Toyota Jidoshokki Seisakusho. Bearing structure used in a compressor. 5,586,870, Cl. 417-222,200.
- Kawahara, Fumio: See—
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554,000.
- Kawahara, Ichiro; Wada, Isao; and Sasaoka, Michio, to Otsuka Kagaku Kabushiki Kaisha. Process for producing diazomethane derivatives. 5,587,464, Cl. 534-558,000.
- Kawahara, Katsumi: See—
Yoshioka, Kazumi; Ohta, Takeo; Furukawa, Shigeaki; and Kawahara, Katsumi, 5,587,216, Cl. 428-64,400.
- Kawahara, Yoshiaki; Kudo, Kazunori; Nakatani, Yoshihide; and Takagawa, Hiroyuki, to Mitsubishi Jukogyo Kabushiki Kaisha. Crankcase compression type two-cycle engine. 5,586,523, Cl. 123-65,0VB.
- Kawakami, Atsushi: See—
Kishida, Takahito; Matsumura, Akira; and Kawakami, Atsushi, 5,587,274, Cl. 430-270,100.
- Kawakami, Takahiro; Ogawa, Akira; and Ichimura, Etsuo, to Kansei Corporation. Semiconductor strain gauge acceleration sensor. 5,587,531, Cl. 73-514,120.
- Kawakita, Hiroyuki: See—
Tanaka, Nobuo; Otani, Seiji; Kawakita, Hiroyuki; and Matsuda, Teruo, 5,586,975, Cl. 604-89,000.
- Kawamoto, Fumio, to Fuji Photo Film Co., Ltd. Polyester photographic support. 5,587,278, Cl. 430-533,000.
- Kawamura, Harumi: See—
Kori, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato; and Ogawa, Kazuyuki, 5,587,849, Cl. 360-69,000.
- Kawamura, Kiyoshi: See—
Kanada, Kenta; and Kawamura, Kiyoshi, 5,587,410, Cl. 523-410,000.
- Kawamura, Koichiro; and Uehara, Ryo, to Nikon Corporation. Camera which sets an internal aperture value in accordance with a converted photographic lens aperture value. 5,587,766, Cl. 396-257,000.
- Kawamura, Motomi; Kishi, Masamichi; and Morikawa, Takeshi, to Minolta Camera Kabushiki Kaisha. Copying machine with reserved copying at a predetermined time. 5,587,799, Cl. 358-296,000.
- Kawamura, Shigeto, to Sumitomo Wiring Systems, Ltd. Connector for connecting an optical fiber cable. 5,588,080, Cl. 385-78,000.
- Kawanishi, Toshiaki; Nobutoki, Yoshikazu; Hirano, Seiji; and Terayama, Koji, to Mazda Motor Corporation. Multiplex transmission apparatus for supporting prioritized communications among a plurality of network nodes. 5,588,002, Cl. 370-462,000.
- Kawasaki, Masayuki; Kuwasima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, to Kabushiki Kaisha Toshiba. Booster circuit device. 5,587,683, Cl. 327-538,030.
- Kawasaki Steel Corporation: See—
Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kuguminato, Hideo, 5,587,027, Cl. 148-320,000.
- Yoneda, Masato; and Shibata, Yoshiaki, 5,588,137, Cl. 395-490,000.
- Kawasaki, Toyotoshi: See—
Miyano, Masaaki; Kawasaki, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824,000.
- Kawashima, Kazuki: See—

Izutsu, Tomoyoshi; and Kawashima, Kazuki, 5,586,952, Cl. 474-110,000.

Kawata, Yasushi: See—
Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shini-chi; and Kawata, Yasushi, 5,587,819, Cl. 349-106,000.

Kazami, Kazuyuki; and Wakabayashi, Tsutomu, to Nikon Corporation. Film feeding control device for accurate alignment of film frames and camera aperture. 5,587,753, Cl. 396-397,000.

Kazami, Kazuyuki: See—
Hibino, Hideo; Yokonuma, Norikazu; Kazami, Kazuyuki; and Yamazaki, Yuichi, 5,587,751, Cl. 396-319,000.

Kazami, Keiichi: See—
Nakada, Takashi; Kazami, Keiichi; and Kaneko, Kenji, 5,587,545, Cl. 84-600,000.

Kazemzadeh, Massoud, to MJM Technologies. Process for manufacturing fat-enriched foods. 5,587,193, Cl. 426-448,000.

Keana, John F. W.: See—
Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P., 5,587,273, Cl. 430-269,000.

Kebo, Reynold S., to Hughes Electronics. Binocular eyepiece with extended eye relief. 5,587,837, Cl. 359-643,000.

Keener, Manuel L. Vehicle anti-theft device. 5,586,457, Cl. 70-201,000.

Keinan, Giora: See—
Eisen, Josef; Gilat, Chaim; and Keinan, Giora, 5,587,585, Cl. 250-370,090.

Keiper Recaro GmbH & Co.: See—
Vossman, Gregor; and Angermann, Dirk, 5,586,833, Cl. 403-359,000.

Keith, Robert C., to Grano Environmental Corporation. Boiler/condenser assembly for high efficiency purification system. 5,587,053, Cl. 202-172,000.

Keith, Robert C., to Grano Environmental Corporation. Vapor compression distillation system. 5,587,054, Cl. 202-182,000.

Kelaita, Joseph B., Jr.; and Collin, Edwin J., to General Electric Company. Circuit breaker interlock unit to prevent single phasing. 5,587,570, Cl. 200-50,010.

Keller, John H.; and Costriani, Gregory, to International Business Machines Corporation. Getting of particles from an electro-negative plasma with insulating chuck. 5,587,045, Cl. 156-627,100.

Kelley, Arthur W.; and Harris, Matthew B., to North Carolina State University. Method and apparatus for nondisruptively measuring line impedance at frequencies which are relatively close to the line frequency. 5,587,662, Cl. 324-713,000.

Kelley, Richard D. Portable pet waste container. 5,586,521, Cl. 119-858,000.

Kellström, Magnus; Fogelström, Joacim; and Wittmeyer, Henning, to SKF Sverige AB. Roller bearing provided with roller skew control and long life characteristics. 5,586,826, Cl. 384-450,000.

Kelly, David J.: See—
Pirani, Gary P.; Gulachenski, Alan M.; and Kelly, David J., 5,586,891, Cl. 439-71,000.

Kelsey-Hayes Company: See—
Negrin, Dan, 5,586,815, Cl. 303-143,000.

Kemp, David H.: See—
Coburn, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srisantha, Alagacone; and Riding, George A., 5,587,311, Cl. 435-240,200.

Kemrhorne, France: See—
Danda, Sylvain; Kvant, Magnus; and Pescher, Yvette, 5,587,086, Cl. 210-723,000.

Kendrick, Ralph C., Jr. Cable directing device. 5,587,554, Cl. 174-37,000.

Kenotest Manufacturing Corp.: See—
Conley, Richard W.; Visalli, Robert G.; and Daniels, James R., 5,586,749, Cl. 251-315,050.

Kerry, John: See—
Peacock, John; Frost, Peter L. J.; and Kerry, John, 5,588,076, Cl. 385-20,000.

Kert, Jimmie. Dental file/reamer instrument. 5,586,885, Cl. 433-102,000.

Kertula, Reima; and Yli-Kauppi, Jouko, to Valmet Corporation. Dryer sections of a paper machine. 5,586,397, Cl. 34-114,000.

Kesseli, James B.; and Baldwin, Stephen P., to Northern Research & Engineering Corporation. Brayton cycle industrial air compressor. 5,586,429, Cl. 60-39,070.

Kibbel, Horst: See—
König, Ulf; Gruhle, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-31,000.

Kiefer, Garry E.: See—
Athey, Phillip S.; and Kiefer, Garry E., 5,587,451, Cl. 528-345,000.

Kiessling, Laura L.; Manning, David D.; and Mortell, Kathleen H. Polyglycomers. 5,587,442, Cl. 526-238,200.

Kikimis, Dan, to Elonex I.P. Holdings, Ltd. Duplicate copies from a printer or copier. 5,586,498, Cl. 101-127,000.

Kilbey, Brian E.: See—
Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard F., 5,586,911, Cl. 439-607,000.

Kim, Chang S.: See—
Donsbach, Kurt W.; and Cazares, Ricardo, 5,587,191, Cl. 426-66,000.

Kim, Jae-myung: See—
Rho, Hwan-chul; Choi, Hong-gyu; and Kim, Jae-myung, 5,587,201, Cl. 427-64,000.

Kim, Jeonok T.: See—

- Beltzer, Morton; Berlowitz, Paul J.; and Kim, Jeonok T., 5,587,355, Cl. 508-302.000.
- Kim, Jong-min, to Samsung Display Devices Co., Ltd. Multiple micro-tips field emission device. 5,587,588, Cl. 257-10.000.
- Kim, Kwang-Kyu, to Samsung Electronics Co., Ltd. Supporting device for minimizing vibration, noise and external impact of a hard disk drive. 5,587,855, Cl. 360-97.020.
- Kim, Kwon K., to Samduck Sanggong Co., Ltd. Handgun holster. 5,586,701, Cl. 224-243.000.
- Kim, Ryeu K., and Lee, Im S. Zig-zag method of braiding hair. 5,586,566, Cl. 132-200.000.
- Kim, Sang S., See—
- Kim, Sung C.; Choy, Nakyen; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
- Kim, Sang-Ho, to Daewoo Electronics Co., Ltd. Apparatus and method for detecting motion vectors to half-pixel accuracy. 5,587,741, Cl. 348-416.000.
- Kim, Seokchan, See—
- Holton, Robert A.; and Kim, Seokchan, 5,587,489, Cl. 549-229.000.
- Kim, Soo K., See—
- Lee, Je H.; Kim, Soo K.; Woo, Sang J.; and Yang, Tae S., 5,587,789, Cl. 386-68.000.
- Kim, Sung C.; Choy, Nakyen; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., to Lucky Limited. Irreversible HIV protease inhibitors, intermediates, compositions and processes for the preparation thereof. 5,587,388, Cl. 514-314.000.
- Kimball, Christopher V.; and Scheibner, David J., to Schlumberger Technology Corporation. Sonic well logging methods and apparatus for processing flexural wave in optimal frequency band. 5,587,966, Cl. 367-31.000.
- Kimberlin, Robert R.; Bodell, Steven W.; Chang, Ted C.; Diesel, Robert M.; and Barker, Scott, to Ingersoll-Rand Company. System for lubricating and reciprocating a piston in a fluid-activated, percussive paving breaker. 5,586,606, Cl. 173-62.000.
- Kimberly-Clark Corporation, See—
- Griesbach, Henry L.; Creagan, Christopher C.; and Gwaltney, Sharon W., 5,587,225, Cl. 428-198.000.
- Kimble, James B., See—
- Brown, Scott H.; Zisman, Stan A.; and Kimble, James B., 5,587,348, Cl. 502-230.000.
- Kimura, Shoji; and Adachi, Nobukazu, to Canon Kabushiki Kaisha. Sheet discharge apparatus and image forming apparatus having such sheet discharge apparatus. 5,586,758, Cl. 271-303.000.
- Kimura, Youichi, See—
- Hayakawa, Isao; and Kimura, Youichi, 5,587,386, Cl. 514-312.000.
- Kincaid, Larry, See—
- Aidlin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier, Kenneth; Ledwith, Robert; and Hencke, Robert J., 5,586,637, Cl. 198-397.000.
- Kines, Joseph G., See—
- Lian, Ke K.; Li, Changming; Jung, Richard H.; and Kines, Joseph G., 5,587,872, Cl. 361-525.000.
- Kinder, Dale J., See—
- Hartman, Michael O.; Kinder, Dale J.; Rainey, Randy E.; Helmich, Arthur R.; and Willis, Daniel E., 5,587,055, Cl. 203-1.000.
- King, Christopher G., See—
- Hidde, Neil G.; King, Christopher G.; Mantone, Anthony; and Shaffer, Frank D., 5,586,712, Cl. 228-5.700.
- King, C. Richter; Kasprzyk, Philip G.; and Bird, Robert E., to Aronex Pharmaceuticals, Inc. Anti-erbB-2 antibodies, combinations thereof, and therapeutic and diagnostic uses thereof. 5,587,458, Cl. 530-387.300.
- King, Donald E., See—
- Pines, Michael Y.; and King, Donald E., 5,587,784, Cl. 356-4.010.
- King, Paul B., See—
- Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Keith W.; Glover, Stephen E.; Barnett, Richard J.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
- Kingsley, Jack D., and Possin, George E., to General Electric Company. Solid state fluoroscopic radiation imager with thin film transistor addressable array. 5,587,591, Cl. 257-59.000.
- Kino, Yoshiki, See—
- Sekine, Masayoshi; Kondo, Toshiaki; and Kino, Yoshiki, 5,587,737, Cl. 348-208.000.
- Kinpo Electronics, See—
- Lan, Si-Chi, 5,587,886, Cl. 361-781.000.
- Kinsey, Joe L., Jr.; and Lanham, Robert L., Jr., to International Paper Company. Recyclable paperboard composites. 5,587,204, Cl. 427-411.000.
- Kioritz Corporation, See—
- Iida, Giichi, 5,586,359, Cl. 15-339.000.
- Kirby Devon Limited, See—
- Kirby, John, 5,587,572, Cl. 235-98.000.
- Kirby, John, to Kirby Devon Limited. Batch counter. 5,587,572, Cl. 235-98.000.
- Kirby, John J., See—
- Porter, Michael R.; Mulcahey, Charles E.; and Kirby, John J., 5,586,511, Cl. 112-2.100.
- Kirchner, Hary; Hohmann, Ralf; and Spors, Ralf, to Rasmussen GmbH. Push-fit connector for joining a fluid line to a pipe. 5,586,791, Cl. 285-179.000.
- Kiser, Thomas E., to Professional Supply, Inc. Environmental control air-house with variable output. 5,586,932, Cl. 454-229.000.
- Kiser, Weldon C., to Environmental L.L.C. Elastomeric polysulfide composites and method. 5,587,234, Cl. 428-327.000.
- Kish, Arthur S., to JEM Industries, Inc. Disconnect valve assembly for connecting a source of fluid with a container to be filled. 5,586,748, Cl. 251-149.800.
- Kish, Joseph, III, See—
- Altschuler, Barry N.; Hardy, Douglas A.; Stephens, James A.; and Kish, Joseph, III, 5,588,062, Cl. 380-30.000.
- Kishi, Masamichi, See—
- Kawamura, Motomi; Kishi, Masamichi; and Morikawa, Takeshi, 5,587,799, Cl. 358-296.000.
- Kishida, Takahito; Matsumura, Akira; and Kawakami, Atsushi, to Nippon Paint Co., Ltd. Resist composition. 5,587,274, Cl. 430-270.100.
- Kissel, James L.; Dailey, Earl J.; and Dolan, Daniel F., to Rushmore Vehicle Restraints, L.L.C. Wheel restraint device and quick-connect hooks for use therewith. 5,586,849, Cl. 410-10.000.
- Kitabatake, Syoichi, See—
- Shindo, Yasuhiro; Yamaguti, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro; and Kitabatake, Syoichi, 5,587,320, Cl. 435-290.100.
- Kitagawa, Hiroshi, See—
- Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.
- Kitahara, Kiyoshi, See—
- Sakanishi, Ei; and Kitahara, Kiyoshi, 5,587,725, Cl. 345-195.000.
- Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, to Honda Giken Kogyo Kabushiki Kaisha. Fuel injection amount control system for internal combustion engines and intake passage wall temperature-estimating device used therein. 5,586,544, Cl. 123-684.000.
- Kitukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, to Hitachi, Ltd. Dynamic random access memory including read preamplifiers activated before rewrite amplifiers. 5,587,952, Cl. 365-207.000.
- Kitzerow, John P., See—
- Yesel, Leon P.; and Kitzerow, John P., 5,587,905, Cl. 364-424.082.
- Kiuchi, Noriyuki, See—
- Soda, Yoshio; Kohno, Takefumi; Shinagawa, Masaaki; and Kiuchi, Noriyuki, 5,587,203, Cl. 427-228.000.
- Klaveness, Jo, See—
- Almén, Torsten; Berg, Arne; Dugstad, Harald; Klaveness, Jo; Krautwurst, Klaus D.; and Rongved, Pål, 5,587,144, Cl. 424-9.361.
- Klearman, Melvin. Golf putting practice device. 5,586,941, Cl. 473-160.000.
- Kleaver, Helen A., See—
- Besse, Michael E.; Ross, Cynthia L.; and Kleaver, Helen A., 5,587,009, Cl. 106-244.000.
- Klebahn, Perry A., See—
- Stone, Kevin R.; Klebahn, Perry A.; and Knapp, William R., 5,586,559, Cl. 128-782.000.
- Kleckner, Robert J., See—
- Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A., 5,587,767, Cl. 355-27.000.
- Klein, Anthony A., See—
- Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A., 5,587,767, Cl. 355-27.000.
- Klein Bicycle Corporation, See—
- Klein, Gary G.; Voss, Darrell W.; and Pauls, Lonney, 5,586,780, Cl. 280-275.000.
- Klein, Gary G.; Voss, Darrell W.; and Pauls, Lonney, to Klein Bicycle Corporation. High efficiency bicycle suspension. 5,586,780, Cl. 280-275.000.
- Klein, Loraine, See—
- Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert; and Froen, Diane, 5,587,481, Cl. 546-146.000.
- Kleiner, Hans-Jerg, See—
- von Gentzow, Wolfgang; Huber, Jürgen; Kapitza, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413.000.
- Klerer, S. Mark, See—
- Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Lyla R.; and Strohecker, Cary A., Sr., 5,588,051, Cl. 379-243.000.
- Klimek, Thaddeus W.; and Edwards, Michael B., to Quantum Chemical Corporation. Process for controlling the polymerization of propylene and ethylene and copolymer products. 5,587,436, Cl. 526-59.000.
- Klink, Andrew K. Multidirectional task lamp. 5,586,820, Cl. 362-402.000.
- Klionsky, Daniel; Holzer, Helmut; and Destruelle, Monika, to University of California, The Regents of the. Stress tolerant yeast mutants. 5,587,290, Cl. 435-6.000.
- Knapp, Philip A., to United States of America, Energy. Value for controlling flow of cryogenic fluid. 5,586,745, Cl. 251-121.000.
- Knapp, William R., See—
- Stone, Kevin R.; Klebahn, Perry A.; and Knapp, William R., 5,586,559, Cl. 128-782.000.
- Knelson, Benjamin V. Centrifugal separator with conical bowl section and axially spaced recesses. 5,586,965, Cl. 494-29.000.
- Knight, Nancy R., See—

- Moczygemba, George A.; Knight, Nancy R.; Trepka, William J.; and Stacy, Nathan E., 5,587,425, Cl. 525-98.000.
- Knorowski, Victor J.; Reluzco, George; Robertson, Kenneth J.; and Adamkoski, Paul L., to General Electric Company. Turbine nozzle diaphragm and method of assembly. 5,586,864, Cl. 415-209.200.
- Knorr-Bremse Systeme Für Nutzfahrzeuge GmbH, See—
- Bielig, Peter M.; Brähler, Klaus; and Gschöbmann, Günther, 5,587,865, Cl. 361-45.000.
- Knowles, Billy J., See—
- Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- Knox, Lee B. Apparatus and method for pressurizing and drafting liquid contained within food-grade containers. 5,586,588, Cl. 141-285.000.
- Knühl, Klaus; Karl, Ulrich; Müller, Stefan; and de Potzoli, Bernd, to BASF Aktiengesellschaft. Preparation of N-protected N-alkylated amino acids. 5,587,506, Cl. 560-12.000.
- Knuth, Stephen B.; Brown, Sanford M., III; and Karnowski, Mark J., to Casio PhoneMate, Inc. Digital telephone answering device and method of testing message storage memory therein. 5,588,046, Cl. 379-67.000.
- Ko, Chang-Kyung, See—
- Jo, Hae-Seung; Ko, Chang-Kyung; and Lee, Dong-Ho, 5,587,770, Cl. 355-28.000.
- Ko, Kent, See—
- Ko, Wen-Chung; Ko, Kent; and Fu, Chin-Jen, 5,586,624, Cl. 188-164.000.
- Ko, Wen-Chung; Ko, Kent; and Fu, Chin-Jen. Fly wheel brake device for an exercise bicycle. 5,586,624, Cl. 188-164.000.
- Kobayakawa, Michihiro, See—
- Nagao, Kenji; Sohma, Masaki; Ando, Shigeru; and Kobayakawa, Michihiro, 5,587,927, Cl. 364-514.00A.
- Kobayashi, Hideo, See—
- Ishikawa, Hiroyasu; and Kobayashi, Hideo, 5,588,026, Cl. 375-329.000.
- Kobayashi, Hisashi, to Praxair Technology, Inc. Method for producing glass with lower alkali content. 5,586,999, Cl. 65-134.300.
- Kobayashi, Makoto, See—
- Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.
- Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, to Toray Industries, Inc. Carbon fibers and process for preparing same. 5,587,240, Cl. 428-367.000.
- Kobayashi, Minoru, See—
- Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
- Kobayashi, Naoyuki, See—
- Mizutani, Hideo; Kobayashi, Naoyuki; and Magome, Nobutaka, 5,587,794, Cl. 356-375.000.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, to Yamaha Hatsudoki Kabushiki Kaisha. Watercraft. 5,586,921, Cl. 440-38.000.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, to Yamaha Hatsudoki Kabushiki Kaisha. Watercraft. 5,586,922, Cl. 440-38.000.
- Kobayashi, Seiji, See—
- Owa, Hideo; and Kobayashi, Seiji, 5,587,984, Cl. 369-103.000.
- Kobayashi, Shigehiko, See—
- Yamamoto, Takatatsu; Kobayashi, Shigehiko; and Ikeda, Tomohiro, 5,587,556, Cl. 174-74.00R.
- Kobayashi, Shinji, See—
- Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500.000.
- Kobayashi, Shoji, to Sony Corporation. Magneto-optical disk reproducing apparatus with gain and offset controlled by a reference pattern read from the disk. 5,587,975, Cl. 369-13.000.
- Kobayashi, Toshihiro, See—
- Iguchi, Yutaka; Sato, Kazuo; Kobayashi, Toshihiro; and Sato, Masayuki, 5,587,529, Cl. 73-504.130.
- Koblitz, Karl R., See—
- Wilber, James A.; and Koblitz, Karl R., 5,587,631, Cl. 315-403.000.
- Köcher, Jürgen, See—
- Dattagupta, Nanibhushan; and Köcher, Jürgen, 5,587,472, Cl. 536-26.200.
- Kodama, Naoki, See—
- Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhito; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332.000.
- Koeberle, Yves; and Frayse, Philippe, to L'Air Liquide, Societe Anonyme Pour l'Etude et l'Exploitation des Procédes Georges Claude. Process and installation for the production of oxygen by distillation of air. 5,586,451, Cl. 62-646.000.
- Koguchi, Masayuki, See—
- Sasaki, Keiji; and Koguchi, Masayuki, 5,587,535, Cl. 73-726.000.
- Koh, Jong S., See—
- Kim, Sung C.; Choy, Nakyen; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
- Kohda, Katsuhiko, See—
- Suzuki, Hideo; and Kohda, Katsuhiko, 5,587,033, Cl. 156-164.000.
- Kohjin Co., Ltd., See—
- Takao, Yuuichi; and Oogami, Hidetoshi, 5,587,515, Cl. 564-135.000.
- Kohl, Bernhard; Senn-Bilfinger, Jörg; and Grundler, Gerhard, to BYK Gulden Lomberg Chemische Fabrik GmbH. Substituted heteroarylthiopyridines for controlling helicobacter bacteria. 5,587,389, Cl. 514-338.000.
- Kohn, Joachim B.; and Hooper, Kimberly A., to Rutgers, The State University. Synthesis of tyrosine derived diphenol monomers. 5,587,507, Cl. 560-40.000.
- Kohno, Takefumi, See—
- Soda, Yoshio; Kohno, Takefumi; Shinagawa, Masaaki; and Kiuchi, Noriyuki, 5,587,203, Cl. 427-228.000.
- Kohr, William J., See—
- Goeddel, David V.; Kohr, William J.; Pennica, Diane; and Vehar, Gordon A., 5,587,159, Cl. 424-94.640.
- Koide, Norikatsu; Yamazaki, Shiro; Umezaki, Junichi; and Asami, Shinya, to Toyoda Gosei Co., Ltd.; and Research Development Corporation of Japan. Light-emitting semiconductor device using group III nitrogen compound. 5,587,593, Cl. 257-94.000.
- Koide, Yasuo, See—
- Murakami, Masanori; Koide, Yasuo; Teraguchi, Nobuaki; and Tomomura, Yoshitaka, 5,587,609, Cl. 257-744.000.
- Koike, Nobuaki, See—
- Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi, 5,587,378, Cl. 514-264.000.
- Koike, Yasuta, See—
- Hattanda, Hirokatsu; Ogiso, Mitsukazu; Koike, Yasuta; and Takagi, Kazuhiko, 5,587,101, Cl. 222-603.000.
- Koilpillai, Ravinder D., See—
- Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
- Koiva, Atsushi, to International Business Machines Corporation. Liquid crystal driving apparatus. 5,587,721, Cl. 345-89.000.
- Koiva, Mitsuru, See—
- Taruya, Masaaki; and Koiva, Mitsuru, 5,586,542, Cl. 123-609.000.
- Koizumi, Hideaki, See—
- Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
- Kojima, Makoto, See—
- Togano, Takeshi; Takao, Hideaki; Asaoka, Masanobu; and Kojima, Makoto, 5,587,211, Cl. 428-1.000.
- Kojima, Yori; Mototani, Yuji; and Asaoka, Junichi, to Matsushita Electric Industrial Co., Ltd. Alkaline battery having a gelled negative electrode. 5,587,254, Cl. 429-206.000.
- Kojo, Takashi, See—
- Yoshino, Hiroyuki; and Kojo, Takashi, 5,587,823, Cl. 359-143.000.
- Kokalis, George P., to Servo Kinetics. Hydraulic closed loop control system. 5,586,435, Cl. 60-416.000.
- Kokubo, Hideyuki, to Fuji Photo Film Co., Ltd. Color thermal printing method and apparatus. 5,587,732, Cl. 347-183.000.
- Kokusai Denshin Denwa Co., Ltd., See—
- Ishikawa, Hiroyasu; and Kobayashi, Hideo, 5,588,026, Cl. 375-329.000.
- Kolff, Jack, See—
- Budayr, Mahdi; and Kolff, Jack, 5,587,561, Cl. 181-131.000.
- Kolotyrkin, Y. M., See—
- Gorodetsky, Victor V.; Neburchilov, Vladimir A.; and Kolotyrkin, Y. M., 5,587,058, Cl. 204-290.00F.
- Komaki, Toshihiro, to Pioneer Electronic Corporation. Plasma display panel. 5,587,624, Cl. 313-584.000.
- Komatsu, Yuuki, See—
- Negi, Shigeto; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222.000.
- Komiya, Hirofumi; Sakai, Keita; Koshi, Kazumine; and Saito, Noriyuki, to Matsushita Electric Industrial Co., Ltd. Printer control circuit and the printer controlled thereby. 5,588,092, Cl. 395-109.000.
- Kondo, Kazuhiko; Horikawa, Hiroshi; and Iwasaki, Tameo, to Tanabe Seiyaku Co., Ltd. Method for removing the protecting group for carboxyl group. 5,587,474, Cl. 540-350.000.
- Kondo, Takayuki, See—
- Mori, Katsumi; Asaka, Tatsuya; Iwano, Hideaki; and Kondo, Takayuki, 5,587,335, Cl. 437-129.000.
- Kondo, Toshiaki, See—
- Sekine, Masayoshi; Kondo, Toshiaki; and Kino, Yoshiki, 5,587,737, Cl. 348-208.000.
- Kondoh, Reiko, See—
- Iwasaki, Hitoshi; Ohsawa, Yuichi; and Kondoh, Reiko, 5,587,026, Cl. 148-313.000.
- Kone Oy, See—
- Winter, Ari; and de Jong, Johannes, 5,587,567, Cl. 187-395.000.
- Kong, Laval C. C., See—
- Belleau, Bernard, deceased; Nguyen-Ba, Nghe; Kong, Laval C. C.; Mansour, Tarek; Jin, Haolun; and Brasili, Livio, 5,587,480, Cl. 544-310.000.
- Konica Corporation, See—
- Kurata, Noriaki, 5,587,759, Cl. 396-630.000.
- Kurata, Noriaki; and Kuwae, Kenji, 5,587,760, Cl. 396-630.000.
- Ujihara, Junji; and Ohira, Akira, 5,587,266, Cl. 430-133.000.
- Yamashita, Hiroshi; and Ueda, Yutaka, 5,587,277, Cl. 430-458.000.

- König, Udo; Van Den Berg, Hendrikus; and Tabersky, Ralf, to Widia GmbH. Composite body and its use. 5,587,233, Cl. 428-325.000.
- König, Ulf; Grubbe, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, to Daimler Benz AG; and Temictele-tunken Microelectronic GmbH. Process for preparing a heterojunction bipolar transistor. 5,587,327, Cl. 437-31.000.
- Königsfeld, Kris G.: See—
Abramson, Jeffrey M.; Akkary, Hitham; Glew, Andrew E.; Hinton, Glenn J.; Königsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395-376.000.
- Koning, Cornelis E.; and Teuwen, Lillian M. J., to DSM N.V. Polyamide-imide. 5,587,452, Cl. 528-350.000.
- Koninklijke PTT Nederland N.V.: See—
Beerends, John G.; Müller, Frank; and van Ravesteijn, Robertus L. A., 5,588,089, Cl. 395-2,140.
- Konishi, Yasuhiro: See—
Sawada, Seiji; and Konishi, Yasuhiro, 5,587,950, Cl. 365-201.000.
- Konkel, Brian: See—
Wanek, Ronald G.; Dotta, James C.; Konkel, Brian; and Herold, Duane, 5,586,830, Cl. 403-59.000.
- Konno, Masao; and Yuasa, Yoshifumi, to Takasago International Corporation. (Sp)-2-aryl-3-chloropropionic acid and process for the preparation thereof. 5,587,510, Cl. 562-496.000.
- Konoike, Toshiro; Araki, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Kensuke; and Toyoy, Takehiko, to Shionogi & Co., Ltd. Triterpene derivatives and endothelin-receptor antagonists containing the same. 5,587,505, Cl. 558-272.000.
- Konrad, Eugen: See—
Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401.000.
- Korczynski, Jack: See—
Happ, Lawrence R.; Korczynski, Jack; Bailey, William R.; and Lesesky, Alan, 5,587,890, Cl. 361-826.000.
- Korec, Jack: See—
Neubrand, Horst; Korec, Jack; Stein, Erhart; and Silber, Dieter, 5,587,595, Cl. 257-141.000.
- Korein, James U.: See—
Abrams, Steven R.; Korein, James U.; Srinivasan, Vijay; and Tarahanis, Konstantinos, 5,587,913, Cl. 364-468.260.
- Kori, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato; and Ogawa, Kazuyuki, to Sony Corporation. Mechanism for securing recorded contents of recording medium cassette. 5,587,849, Cl. 360-69.000.
- Korpman, Dennis: See—
Korpman, Ralf; Korpman, Vera; Korpman, Michael; and Korpman, Dennis, 5,587,237, Cl. 428-355.000.
- Korpman, Michael: See—
Korpman, Ralf; Korpman, Vera; Korpman, Michael; and Korpman, Dennis, 5,587,237, Cl. 428-355.000.
- Korpman, Ralf; Korpman, Vera; Korpman, Michael; and Korpman, Dennis, to Ralf Korpman Associates, Inc. Pressure sensitive adhesive. 5,587,237, Cl. 428-355.000.
- Korpman, Vera: See—
Korpman, Ralf; Korpman, Vera; Korpman, Michael; and Korpman, Dennis, 5,587,237, Cl. 428-355.000.
- Korsh, George J.: See—
Jazayeri, Mehdi; Hui, Edward S.; and Korsh, George J., 5,587,951, Cl. 365-203.000.
- Kosakowski, Steven J.; and Chipman, Brian A. Hand-held scratch ticket scraper. 5,586,357, Cl. 15-111.000.
- Koshi, Kazumine: See—
Komiya, Hirofumi; Sakai, Keita; Koshi, Kazumine; and Saito, Noriyuki, 5,588,092, Cl. 395-109.000.
- Koshio, Shuichi: See—
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Koskinen, Pertti. Sliding seal with hole and groove for distribution of pressurized friction reducing medium. 5,586,771, Cl. 277-34.000.
- Kosuka, Toshiya: See—
Shitara, Yasuharu; Hayasaka, Noboru; and Kosuka, Toshiya, 5,588,120, Cl. 395-200.150.
- Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiroshi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, to Mitsubishi Denki Kabushiki Kaisha. Air-direction adjusting apparatus for air-conditioning equipment. 5,586,935, Cl. 454-320.000.
- Kouchi, Takao; and Suzuki, Hideaki, to Honda Giken Kogyo Kabushiki Kaisha. Snow vehicle. 5,586,614, Cl. 180-190.000.
- Kowalezyk, Robert M.; Brown, Robert H., III; and Heller, Jack W., to Intel Corporation. Circuit for sharing a memory of a microcontroller with an external device. 5,587,957, Cl. 365-230.030.
- Kowshik, Vikram, to Acel Corporation. Two-transistor zero-power electrically alterable non-volatile latch. 5,587,603, Cl. 257-316.000.
- Koyakumaru, Yasuhiro: See—
Ohmura, Hitoshi; Koyakumaru, Yasuhiro; and Iketaka, Satoshi, 5,587,248, Cl. 428-610.000.
- Koyama, Makoto: See—
Hirao, Yasunobu; Koyama, Makoto; and Motoyama, Yuji, 5,586,389, Cl. 29-841.000.
- Koyanagi, Tomoyoshi: See—

- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,921, Cl. 440-38.000.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,922, Cl. 440-38.000.
- Kozai, Yoshio: See—
Takatani, Muneco; Kozai, Yoshio; Tonimatsu, Kiminori; and Shibouta, Yumiko, 5,587,383, Cl. 514-300.000.
- Koziet, Joseph: See—
Guezennec, Yannick; Koziet, Joseph; and Thiry, Michel, 5,587,190, Cl. 426-2.000.
- Kraemer, Michael: See—
Boegner, Walter; Kraemer, Michael; Krutzsch, Bernd; Wenninger, Guenter; Wirbeleit, Friedrich; and Weisweiler, Werner, 5,586,433, Cl. 60-274.000.
- Kraft Foods, Inc.: See—
Mehner, David W.; Forneck, Kevin; Prince, Steven; and Major, Michael D., 5,587,196, Cl. 426-611.000.
- Kraft, Robert E.: See—
Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew; Kraft, Robert E.; and Vander Plas, Hubert A., 5,586,715, Cl. 228-248.100.
- Král, Vladimir: See—
Sessler, Jonathan L.; Král, Vladimir; and Andrievsky, Andrei, 5,587,478, Cl. 540-474.000.
- Král, Vladimir A.: See—
Sessler, Jonathan L.; Mody, Tarak D.; Hemmi, Gregory W.; Král, Vladimir A.; and Magda, Darren, 5,587,371, Cl. 514-185.000.
- Kramer, James D.: See—
Lerner, Bernard; Hess, Richard W.; Cronauer, William M.; Wehrmann, Rick S.; and Kramer, James D., 5,586,708, Cl. 226-172.000.
- Krapcho, A. Paul; Hacker, Miles P.; Cavalleni, Ennio; and Giuliani, Ferdinando C., to Boehringer Mannheim Italia, SpA. 6,9-bis[(2-aminoethyl) amino]benzo [g]isoquinoline-5,10-dione dimaleate; an azo-anthracenedione with reduced cardiotoxicity. 5,587,382, Cl. 514-290.000.
- Kraus, Richard F. Dental articulator. 5,586,884, Cl. 433-60.000.
- Krause, Andrew W., to Biophysica Technologies, Inc. Spatially light modulated confocal microscope and method. 5,587,832, Cl. 359-385.000.
- Kraut, Ingolf, to Bizerba-Werke Wilhelm Kraut GmbH & Co. KG. Conveyor chain. 5,586,640, Cl. 198-692.000.
- Krautwurst, Klaus D.: See—
Almén, Torsten; Berg, Arne; Dugstad, Harald; Klavness, Jo; Krautwurst, Klaus D.; and Rongved, Pål, 5,587,144, Cl. 424-9.361.
- Krebs, Jerome R., to Exxon Production Research Company. 3D wave equation migration of a 2D grid of seismic data. 5,587,942, Cl. 367-50.000.
- Kreinick, Stephen J.: See—
Lawless, Michael W.; Soheron, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., 5,586,868, Cl. 417-53.000.
- Kremer, Frederic B.; and Clupper, Harold E. Microkeratome. 5,586,980, Cl. 606-4.000.
- Kreuger, Marc: See—
van Holst, Gerrit J.; Kreuger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, 5,587,312, Cl. 435-240.460.
- Kreuter, Peter, to Meta Motoren-und Energie-Technik GmbH. Device for the variable control of the valves of internal combustion engines, more particularly for the throttle-free load control of 4-stroke engines. 5,586,527, Cl. 123-90.150.
- Kricka, Larry J.: See—
Wilding, Peter; and Kricka, Larry J., 5,587,128, Cl. 422-50.000.
- Kripp, Thomas: See—
Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401.000.
- Krist, Gene. Hydronic interface system, method and apparatus. 5,586,449, Cl. 62-179.000.
- Kroemer, Nils; Vossiek, Martin; Eccardt, Peter-Christian; and Magori, Valentin, to Siemens Aktiengesellschaft. Process for the recognition and separation of useful and interfering echoes in the received signals of distance sensors which operate in accordance with the pulse-echo principle. 5,587,969, Cl. 367-99.000.
- Krogh, James A.; Mokadam, Anita R.; and Smith, B. Brian, to Exxon Chemical Patents, Inc. Method for amide preparation. 5,587,498, Cl. 554-69.000.
- Kromm, Erich: See—
Schnitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas, 5,586,992, Cl. 8-653.000.
- Kröner, Hubertus; Jahns, Ekkehard; and Mielke, Manfred, to Basf Aktiengesellschaft. Gels with thermotropic properties. 5,587,404, Cl. 522-85.000.
- Krown, Stephen M., to Tektronix, Inc. Post-processing bit-map decimation compensation method for printing high quality images. 5,588,094, Cl. 395-109.000.
- Krueger International, Inc.: See—
Burroughs, Richard H., 5,586,804, Cl. 297-188.080.
- Krueger, Rudolf: See—
Schnitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas, 5,586,992, Cl. 8-653.000.
- Krueger, Steven D.: See—

- Vogley, Wilbur C.; Balistreri, Anthony M.; Guttig, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Krüger, Ralf: See—
Langstein, Gerhard; Krüger, Ralf; Piejko, Karl-Erwin; Eisele, Ulrich; and Morbitzer, Leo, 5,587,424, Cl. 525-63.000.
- Kruit, Pieter, to U.S. Philips Corporation. Particle-optical apparatus comprising an electron source with a needle and a membrane-like extraction electrode. 5,587,586, Cl. 250-423.00F.
- Kruevitch, Peter A.: See—
Dawes, Paul J.; Kruevitch, Thomas A.; and Kruevitch, Peter A., 5,586,779, Cl. 280-14.200.
- Kruevitch, Thomas A.: See—
Dawes, Paul J.; Kruevitch, Thomas A.; and Kruevitch, Peter A., 5,586,779, Cl. 280-14.200.
- Krummenacher, Josef, to Apparate-Und Werkzeugbau AG. Disk holder in a CD box. 5,586,651, Cl. 206-310.000.
- Krutzsch, Bernd: See—
Boegner, Walter; Kraemer, Michael; Krutzsch, Bernd; Wenninger, Guenter; Wirbeleit, Friedrich; and Weisweiler, Werner, 5,586,433, Cl. 60-274.000.
- Krzywdziak, Alain, to F.A.S. Stirrer lid for color cans of stirring machines. 5,586,822, Cl. 366-247.000.
- Ksenych, Nick. Rotatable scaffold. 5,586,616, Cl. 182-222.000.
- KTR Kupplungstechnik GmbH: See—
Schürhörster, Josef, 5,586,938, Cl. 464-92.000.
- Kubo, Isao: See—
Sukigara, Masayuki; and Kubo, Isao, 5,587,358, Cl. 514-11.000.
- Kubo, Kohji; Nezu, Shiochi; Ishibashi, Fumio; Harada, Hiroyuki; and Shigematsu, Yuji, to Sumitomo Chemical Company, Limited. Resin composition for extrusion molding. 5,587,247, Cl. 428-523.000.
- Kubo, Masahiko: See—
Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayoshi; Iwao, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl. 355-208.000.
- Kubota, Kazuyuki: See—
Azumi, Takeshi; Yamaoka, Osamu; and Kubota, Kazuyuki, 5,587,869, Cl. 361-301.300.
- Kubouchi, Kenji; Fukui, Yuji; and Inoue, Kunitoshi, to Nippon Gasket Co., Ltd. Laminated metal gasket having a varying bead structure, thickness, and overlap width. 5,586,776, Cl. 277-235.00B.
- Kudo, Kazunori: See—
Kawahara, Yoshitaka; Kudo, Kazunori; Nakatani, Yoshihide; and Takagawa, Hiroyuki, 5,586,523, Cl. 123-65.0VB.
- Kudva, Ashok K.: See—
Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Conyers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., 5,587,272, Cl. 430-257.000.
- Kugimiya, Shuzo, to Sharp Kabushiki Kaisha. Translating system for processing text with markup signs. 5,587,902, Cl. 395-752.000.
- Kugo, Harumi: See—
Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiko; Kugo, Harumi; Sakai, Kazuo; Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210.000.
- Kuguminato, Hideo: See—
Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kuguminato, Hideo, 5,587,027, Cl. 148-320.000.
- Kuhary, Daniel B.: See—
Nitschke, John S.; and Kuhary, Daniel B., 5,586,486, Cl. 99-330.000.
- Kuhm, Peter; Schroeder, Christine; Sander, Volker; Lindener, Juergen; and De Riese-Meyer, Loert, to Henkel Kommanditgesellschaft auf Aktien. Method for electrolytic coloring of aluminum surfaces using alternating current. 5,587,063, Cl. 205-173.000.
- Kühn, Gottfried: See—
Rothamel, Karl; Lenhardt, Lorenz; and Kühn, Gottfried, 5,587,528, Cl. 73-462.000.
- Kuhn, James O.; and Goldman, Lee J. Safety container for microwave oven baking utensil. 5,587,099, Cl. 219-728.000.
- Kuhn, Joachim: See—
Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred, 5,587,107, Cl. 252-315.600.
- Kuhn S.A.: See—
Aron, Jerome, 5,586,421, Cl. 56-367.000.
- Kujala, Timo: See—
Autio, Jukka; and Kujala, Timo, 5,587,052, Cl. 162-273.000.
- Kukkadapu, Ravi: See—
Boyd, Stephen A.; and Kukkadapu, Ravi, 5,587,084, Cl. 210-691.000.
- Kulicke and Soffa Investments, Inc.: See—
Bar-Kana, Izhak; and Filipovic, Predrag, 5,587,636, Cl. 318-561.000.
- Kuligowski, Douglas J.: See—
Misukanis, Eugene D.; Long, John H.; Dean, Lawrence A.; and Kuligowski, Douglas J., 5,588,140, Cl. 395-500.000.
- Kulite Semiconductor Products, Inc.: See—
Kurtz, Anthony D., 5,587,601, Cl. 257-417.000.
- Kumagai, Katsuhiko: See—
Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachito; Kitagawa, Hiroshi; Tsuruki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.
- Kumar, Pramathesh; Grabiak, Matthias; and Ivanek, Ivan, to Micrografx, Inc. System and method for generating graphics charts. 5,588,108, Cl. 395-348.000.
- Kume, Masahiro: See—
Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Issei; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.
- Kuo, Hui-Pei. Field emitter with a tapered gate for flat panel display. 5,587,628, Cl. 315-169.300.
- Kuraray Co., Ltd.: See—
Nakagawa, Naoshi; Hatanaka, Tadashi; Hayashibara, Tatsuhiko; and Shiono, Manzo, 5,587,486, Cl. 548-448.000.
- Kurasawa, Koichi; Harada, Mikio; and Ito, Takaaki, to Mitsubishi Materials Corporation. Surge absorber. 5,587,867, Cl. 361-118.000.
- Kurashima, Yoshihiko: See—
Tsuchimoto, Tomonori; Iwata, Katsuichi; and Kurashima, Yoshihiko, 5,587,252, Cl. 429-49.000.
- Kurata, Noriaki, to Konica Corporation. Automatic developing apparatus for silver halide photosensitive materials. 5,587,759, Cl. 396-630.000.
- Kurata, Noriaki; and Kuwae, Kenji, to Konica Corporation. Automatic developing apparatus used for silver halide photosensitive material. 5,587,760, Cl. 396-630.000.
- Kurebayashi, Hideki: See—
Nakadera, Kazuo; Okutani, Haruo; and Kurebayashi, Hideki, 5,587,265, Cl. 430-109.000.
- Kureha Gosen Kabushiki Kaisha: See—
Ueba, Hisaaki; Sunaga, Yosio; and Nagasima, Tosio, 5,587,239, Cl. 428-362.000.
- Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Ueba, Hisaaki; Sunaga, Yosio; and Nagasima, Tosio, 5,587,239, Cl. 428-362.000.
- Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Sonobe, Naohiro; Maruyama, Koji; and Iwasaki, Takao, 5,587,255, Cl. 429-218.000.
- Kurihara, Mikio; Nishi, Satoru; Onodera, Takahiro; and Kushima, Kazunari, to International Business Machines Corporation. Printed circuit board and liquid crystal display. 5,587,557, Cl. 174-266.000.
- Kuriki, Yasunori: See—
Ohshima, Satoshi; Yumura, Motoo; Kuriki, Yasunori; Uchida, Kunio; and Ikazaki, Fumikazu, 5,587,141, Cl. 423-445.00B.
- Kurita, Kazuhiko: See—
Hioki, Yuichi; Kurita, Kazuhiko; Kawabata, Keiko; and Azuma, Toshikazu, 5,587,353, Cl. 504-116.000.
- Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Keiichi, to Matsushita Graphic Communication Systems, Inc. Encoding and decoding methods for use in facsimile. 5,587,798, Cl. 358-261.100.
- Kurkowski, Hal: See—
Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221.000.
- Kuroe, Akio: See—
Shimotashiro, Masafumi; and Kuroe, Akio, 5,587,848, Cl. 360-46.000.
- Kurosaki, Tsuyoshi; Tomioka, Atsuo; and Yamato, Takashi, to Toa Medical Electronics Co., Ltd. Apparatus for automatically analyzing specimen. 5,587,129, Cl. 422-64.000.
- Kurosawa, Hiroyuki: See—
Inoue, Mitsuru; and Kurosawa, Hiroyuki, 5,588,144, Cl. 395-555.000.
- Kurtz, Anthony D., to Kulite Semiconductor Products, Inc. Support structure for a semiconductor pressure transducer. 5,587,601, Cl. 257-417.000.
- Kusaka, Yosuke; and Utagawa, Ken, to Nikon Corporation. Auto focus camera and method of auto focus control. 5,587,579, Cl. 250-201.800.
- Kusaka, Yosuke; Muramatsu, Masaru; Utagawa, Ken; and Yamano, Shozo, to Nikon Corporation. Automatic focusing apparatus. 5,587,761, Cl. 396-95.000.
- Kushida, Hideo: See—
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Kushima, Kazunari: See—
Kurihara, Mikio; Nishi, Satoru; Onodera, Takahiro; and Kushima, Kazunari, 5,587,557, Cl. 174-266.000.
- Kuwae, Kenji: See—
Kurata, Noriaki; and Kuwae, Kenji, 5,587,760, Cl. 396-630.000.
- Kuwana, Minoru: See—
Miyano, Masaaki; Kawasaki, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824.000.
- Kuwatima, Yasunori: See—
Kawasaki, Masayuki; Kuwatima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, 5,587,683, Cl. 327-538.000.
- Kvant, Magnus: See—
Danda, Sylvain; Kvant, Magnus; and Pescher, Yvette, 5,587,086, Cl. 210-723.000.
- Kyowa Hakko Kogyo Co., Ltd.: See—
Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nomaka, Hiromi, 5,587,378, Cl. 514-264.000.
- L&P Property Management Company: See—
Bustos, Rafael T.; and LaPolice, George, 5,586,686, Cl. 221-211.000.
- La Jolla Cancer Research Foundation: See—

- Pierschbacher, Michael D.; Honsik, Cyril J.; and Dreisbach, Lisa B., 5,587,456, Cl. 530-326.000.
- La Poste: See—
Le Corre, Hervé; Grimault, Jean-Luc; and Boudet, François, 5,587,809, Cl. 358-405.000.
- Lab Holding Company: See—
Binelli, James C., 5,586,738, Cl. 248-73.000.
- Labun, Lance C.: See—
Hammer, David R.; Sego, Kenneth W., Jr.; and Labun, Lance C., 5,586,615, Cl. 182-48.000.
- Labus, Rainer H.; and Tucker, Stephen L.: Sprayed liquid dispensing apparatus, 5,586,695, Cl. 222-396.000.
- Lachat, Michael J.: See—
Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., 5,586,782, Cl. 280-730.200.
- Lackey, Glenn D.: Method of playing a word scramble game, 5,586,765, Cl. 273-299.000.
- LaFay, Victor S.; and Neltner, Stephen L., to Hill & Griffith Co.: Sand molding media for iron castings, 5,587,008, Cl. 106-38.510.
- Lagnado, Isaac: See—
Reedy, Ronald E.; Garcia, Graham A.; and Lagnado, Isaac, 5,587,597, Cl. 257-351.000.
- LaGrange, Alain: See—
Junino, Alex; LaGrange, Alain; N'Guyen, Quang L.; and Bourboulon, Marie-Alix, 5,587,173, Cl. 424-401.000.
- Richard, Hervé; Leduc, Madeleine; and LaGrange, Alain, 5,587,151, Cl. 424-59.000.
- Lagu, Bharat R.: See—
Liotta, Dennis C.; and Lagu, Bharat R., 5,587,514, Cl. 564-134.000.
- Laine, Roger A.; and Lo, Wai C. J., to Board of Supervisors of Louisiana State University and Agricultural and Mechanical College: Diagnosis of fungal infections with a chitinase, 5,587,292, Cl. 435-7.900.
- L'Air Liquide, Societe Anonyme pour l'Etude et l'Exploitation des Procédés Georges Claude: See—
Karinthi, Pierre; Buffenoir, Marc; and Belot, Dominique, 5,587,283, Cl. 431-10.000.
- Koeberle, Yves; and Frayssé, Philippe, 5,586,451, Cl. 62-646.000.
- Ronge, Catherine; Mail, Alain; and Marot, Yves, 5,587,519, Cl. 73-1.000.
- Lan, Si-Chi, to Kinpo Electronics: Structure for contact points of a shift switch used in a computer, 5,587,886, Cl. 361-781.000.
- Lanasa, Douglas: Pipe testing system, 5,587,521, Cl. 73-49.100.
- Land, David J.: See—
Barkyoub, John; Kabacoff, Lawrence T.; and Land, David J., 5,586,824, Cl. 374-44.000.
- Landine, Robert; De Garie, Claude; and Cocci, Albert, to ADI, Limited: Fermentation process, 5,587,080, Cl. 210-603.000.
- Landis, Michael R.; Yeates, Anthony J.; and Gavin, Thomas J., to Motorola, Inc.: Method for managing data transfer between computing devices, 5,588,148, Cl. 395-601.000.
- Landry, Camille J.: Mobile crane with main and auxiliary counterweight assemblies, 5,586,667, Cl. 212-196.000.
- Landry, Paul G.: See—
Sheehan, Gary T.; and Landry, Paul G., 5,586,401, Cl. 40-737.000.
- Lane, Joseph J.: See—
Ettore, Steven P.; Lane, Joseph J.; and Vandergriff, Douglas S., 5,586,690, Cl. 222-105.000.
- Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, to Wella Aktiengesellschaft: Cosmetic composition for treating skin and hair containing apple wax and methods of making them, 5,587,174, Cl. 424-401.000.
- Lang, Michael: See—
Sciammarella, Eduardo; and Lang, Michael, 5,587,645, Cl. 320-2.000.
- Langstein, Gerhard; Krüger, Ralf; Pfejko, Karl-Erwin; Eisele, Ulrich; and Morbitzer, Leo, to Bayer Aktiengesellschaft: Mixture of fluorocarbon rubber and silicone/acrylate core/shell rubber, 5,587,424, Cl. 525-63.000.
- Lanham, Robert L., Jr.: See—
Kinsey, Joe L., Jr.; and Lanham, Robert L., Jr., 5,587,204, Cl. 427-411.000.
- Lanier, Jaron Z.; Lasko-Harvill, Ann; Blanchard, Chuck L.; and Sparks, Joe L., to VPL Research, Inc.: Method and apparatus for creating virtual worlds using a data flow network, 5,588,104, Cl. 395-326.000.
- Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., to VPL Research, Inc.: Method and system for generating objects for a multi-person virtual world using data flow networks, 5,588,139, Cl. 395-500.000.
- Lanier, Jaron Z.: See—
Levitt, David A.; Degroot, Marc; and Lanier, Jaron Z., 5,587,936, Cl. 364-578.000.
- Lannet Data Communications Ltd.: See—
Segal, Jacob; Ben-Moshe, Josef; Weinstock, Zvika; and Harnik, Zvika, 5,588,151, Cl. 395-800.000.
- LaPolice, George: See—
Bustos, Rafael T.; and LaPolice, George, 5,586,686, Cl. 221-211.000.
- Larkin, John T.: See—
Frantz, Robert H.; Larkin, John T., Jr.; and Correll, Robert S., Jr., 5,586,907, Cl. 439-500.000.
- Larson, Ralph I.: See—
Phillips, Richard J.; and Larson, Ralph I., 5,587,880, Cl. 361-687.000.
- Lasko-Harvill, Ann: See—
Lanier, Jaron Z.; Lasko-Harvill, Ann; Blanchard, Chuck L.; and Sparks, Joe L., 5,588,104, Cl. 395-326.000.
- Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., 5,588,139, Cl. 395-500.000.
- Lathan, Betty S.: Outer protective garment apparatus, 5,586,339, Cl. 2-46.000.
- Latta, Bernd: Liquid mixture for internal use, for prophylactic health protection, 5,587,163, Cl. 424-195.100.
- Lauder, Gary M.; Hoarty, W. Leo; and Soske, Joshua W., to ICTV, Inc.: User interface for selecting television information services through pseudo-channel access, 5,587,734, Cl. 348-10.000.
- Laurash, David F., to Standard Register Company: The Label for operation control system, 5,586,788, Cl. 283-81.000.
- Lauricella, Frank P.: See—
Wilson, Matthew; and Lauricella, Frank P., 5,587,755, Cl. 396-380.000.
- Lawless, Michael W.; Soberon, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., to Abbott Laboratories: Method of delivering liquid to a patient via a disposable pumping cassette having a flow control & pressure monitoring member, 5,586,868, Cl. 417-53.000.
- Lawson, Dennis L.; and Determan, Robert E., to B.F. Goodrich Company: The Method for the manufacture of weatherable, rigid extrusion profiles having improved surface appearance, 5,587,419, Cl. 524-527.000.
- Lay, Norman K.: See—
League, Richard B.; and Lay, Norman K., 5,587,929, Cl. 364-516.000.
- Le, Duy-Loan T.: See—
Vogley, Wilbur C.; Balistreri, Anthony M.; Guttag, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Potet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Leach, Michael J.: See—
Miller, Alistair A.; Nobbs, Malcolm S.; Hyde, Richard M.; and Leach, Michael J., 5,587,380, Cl. 514-275.000.
- League, Richard B.; and Lay, Norman K., to Caterpillar Inc.: System and method for tracking objects using a detection system, 5,587,929, Cl. 364-516.000.
- Learmont, Robert O.: See—
Robinson, Darrell; Loehr, Karl; Pruehs, Allen V.; and Learmont, Robert O., 5,586,913, Cl. 439-638.000.
- Le Berre, Jacques, to U.S. Philips Corporation: Method and device for scrambling and descrambling of a specific television broadcast, 5,588,058, Cl. 380-20.000.
- LeBlanc, Peter, to Ahlstrom Machinery Corporation: Centrifugal cleaner, 5,587,078, Cl. 210-512.100.
- LeClaire, James P.: See—
Nelson, Chris; Hennessy, David R.; and LeClaire, James P., 5,586,635, Cl. 192-85.00A.
- Le Corre, Hervé; Grimault, Jean-Luc; and Boudet, François, to France Telecom Etablissement Autonome de Droit Public; and La Poste: System and a process for transmission of secure faxes, 5,587,809, Cl. 358-405.000.
- Leder, Armin: See—
Leifeld, Ferdinand; and Leder, Armin, 5,586,365, Cl. 19-105.000.
- Leduc, Madeleine: See—
Richard, Hervé; Leduc, Madeleine; and LaGrange, Alain, 5,587,151, Cl. 424-59.000.
- Ledwith, Robert: See—
Aidlin, Samuel S.; Aidlin, Stephen H.; Kincaid, Larry; Cordonnier, Kenneth; Ledwith, Robert; and Hencke, Robert J., 5,586,637, Cl. 198-397.000.
- Lee, Chang S.: See—
Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
- Lee, Chul-woo: See—
Yoo, Jang-hoon; Rim, Kyung-hwa; Chung, Chong-sam; and Lee, Chul-woo, 5,587,976, Cl. 369-13.000.
- Lee, Dong-Hee, to Daewoo Electronics Co., Ltd.: Three dimensional projection system, 5,586,818, Cl. 353-101.000.
- Lee, Dong-Ho: See—
Jo, Hae-Seog; Ko, Chang-Kyung; and Lee, Dong-Ho, 5,587,770, Cl. 355-208.000.
- Lee, Ghai K.; and Gomi, Masao, to Hewlett-Packard Company: Rotatable service station for ink-jet printer, 5,587,729, Cl. 347-32.000.
- Lee, Heun J.; and Joe, Moon J., to Goldstar Co., Ltd.: Online handwritten character recognizing system and method thereof, 5,588,073, Cl. 382-187.000.
- Lee, Im S.: See—
Kim, Ryeu K.; and Lee, Im S., 5,586,566, Cl. 132-200.000.
- Lee, Jae-won, to Samsung Electronics Co., Ltd.: Liquid crystal orientation control layer method and apparatus for manufacturing the same and mask for use in the manufacturing, 5,587,822, Cl. 349-124.000.
- Lee, Je H.; Kim, Soo K.; Woo, Sang J.; and Yang, Tae S., to Goldstar Co. Ltd.: Apparatus and method for controlling recording and reproduction in digital video cassette tape recorder, 5,587,789, Cl. 386-68.000.
- Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurtowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., to Dallas Semiconductor Corporation: Electronic token, 5,587,955, Cl. 365-221.000.
- Lee, Sangho: See—
Shin, Seongke; and Lee, Sangho, 5,588,054, Cl. 379-413.000.

- Lee, Si-Hyun, to Samsung Display Devices Co., Ltd.: Three color LCD with a black matrix and red and/or blue filters on one substrate and with green filters and red and/or blue filters on the opposite substrate, 5,587,818, Cl. 349-106.000.
- Lee, Yu-Cheun: See—
Chao, James L.; Lee, Yu-Cheun; and Gao, Chao, 5,587,217, Cl. 428-65.400.
- Leenslag, Jan W.; and Verbeke, Hans G. G., to Imperial Chemical Industries PLC: Compatibilising agents, 5,587,414, Cl. 524-394.000.
- Le Fevre, David: See—
Chin, Richard; and Le Fevre, David, 5,587,583, Cl. 250-332.000.
- Leggett, Mary E.: See—
Gledzie, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., 5,586,411, Cl. 47-57.600.
- Leica Inc.: See—
Luce, David A.; and Miller, Donald E., 5,587,748, Cl. 351-208.000.
- Leifeld, Ferdinand; and Leder, Armin, to Trützschler GmbH & Co. KG: Fiber tuft feeder for a fiber processing textile machine, 5,586,365, Cl. 19-105.000.
- Leifeld, Ferdinand; and Temburg, Konrad, to Trützschler GmbH & Co. KG: Apparatus for cleaning and opening fiber tufts, 5,586,366, Cl. 19-105.000.
- Leifeld, Ferdinand, to Trützschler GmbH & Co. KG: Apparatus for feeding slivers to a drawing frame, 5,586,641, Cl. 198-720.000.
- Leininger, Daniel R.; and Moore, Walter A., to Morton International, Inc.: High rate pressure vessel filling process, 5,586,587, Cl. 141-196.000.
- Leitner, Johann R.; and Farah, Anthony, to Spescom (Proprietary) Limited: Identification of vehicles including code comparison, 5,587,575, Cl. 235-384.000.
- Leland, Robert W.: See—
Hendrickson, Bruce A.; and Leland, Robert W., 5,587,922, Cl. 364-489.000.
- Leland Stanford Junior University, The Board of Trustees of the: See—
Smith, Julius O., III, 5,587,548, Cl. 84-659.000.
- Lemaire, Ivan; and Gonon, Bertrand, to C & D Biomedical S.A.: Method and device for controlled irrigation and suctioning of a liquid clarificant during endoscopic surgery, 5,586,973, Cl. 604-19.000.
- Lemberger, Heinz: See—
Huemer, Gerhart; and Lemberger, Heinz, 5,586,432, Cl. 60-274.000.
- Lenhardt, Lorenz: See—
Rothamel, Karl; Lenhardt, Lorenz; and Kühn, Gottfried, 5,587,528, Cl. 73-462.000.
- Lennard, David J., to Ethicon, Inc.: In-line annealing of sutures, 5,587,122, Cl. 264-178.000.
- Lennon, George E.; Martin, James R.; and Anderson, Charles D., to Sonoco Products Company: Single-ply paperboard tube and method of forming same, 5,586,963, Cl. 493-299.000.
- Leonard, James, to Lowe Alpine Systems International Limited: Rucksack harness, 5,586,705, Cl. 224-631.000.
- Leonard, R. Leon; Bouse, Earl F.; and McQueen, Anne T., to Cement Industry Environment Consortium: Method and system for controlling pollutant emissions in combustion operations, 5,586,510, Cl. 110-345.000.
- Leonard, W. Burt: Two-stage fluidic actuator, 5,586,482, Cl. 91-519.000.
- Leonard, William K.; Mohr, Stephen W.; Edman, Timothy J.; and Schiller, Phillip D., to Minnesota Mining and Manufacturing: Coating die with slot thickness control, 5,587,184, Cl. 425-133.500.
- Lerner, Bernard; Hess, Richard W.; Cronauer, William M.; Wehrmann, Rick S.; and Kramer, James D., to Automated Packaging Systems, Inc.: Packaging machine feed mechanism, 5,586,708, Cl. 226-172.000.
- Leroux, Jean-Yves, to Gemplus Card International: Method for the acquisition of software and data-processing system to implement the method, 5,588,146, Cl. 395-601.000.
- Lesca, Giuseppe: See—
Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E., 5,587,229, Cl. 428-224.000.
- Lesesky, Alan: See—
Happ, Lawrence R.; Korczynski, Jacek; Bailey, William R.; and Lesesky, Alan, 5,587,890, Cl. 361-826.000.
- Lesmeister, Donald M.: See—
Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- Leung, Benson: See—
Bamber, David J.; Leung, Benson; and Leung, Vincent, 5,586,819, Cl. 362-158.000.
- Leung, Ka-Ngo; Wells, Russell P.; and Craven, Glen E., to Regents, University of California: Porcelain-coated antenna for radio-frequency driven plasma source, 5,587,226, Cl. 428-210.000.
- Leung, Roger Y., to AlliedSignal Inc.: High flexural strength carbon fiber reinforced silicon carbide composite, 5,587,345, Cl. 501-32.000.
- Leung, Vincent: See—
Bamber, David J.; Leung, Benson; and Leung, Vincent, 5,586,819, Cl. 362-158.000.
- Levine, Daniel M.: See—
Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., 5,587,366, Cl. 514-78.000.
- Levitt, David A.; Degroot, Marc; and Lanier, Jaron Z., to VPL Research, Inc.: Method and apparatus for creating sounds in a virtual world by simulating sound in specific locations in space and generating sounds as touch feedback, 5,587,936, Cl. 364-578.000.
- Lew, Albert C.: See—
Henrie, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chaguturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.
- Lewis, Douglas E.; and Moore, Christine M., to United States Drug Testing Laboratories, Inc.: Meconium assay procedure, 5,587,323, Cl. 436-178.000.
- Lewis, Gordon A. C., to Conair Corporation: Refrigerant conservation system and method, 5,586,443, Cl. 62-115.000.
- Lewis, Peter T., to GPS Mobile, Inc.: Method and apparatus for tracking a moving object, 5,587,715, Cl. 342-357.000.
- Leybold Aktiengesellschaft: See—
Ahelkrüger, Burkhard; Aufreiter, Joachim; Brüss, Dieter; and Kalkowski, Klaus, 5,587,016, Cl. 117-214.000.
- Leyderman, Alexander D.: See—
Yasnaskoli, Donald; and Leyderman, Alexander D., 5,586,876, Cl. 418-60.000.
- Li, Changming: See—
Lian, Ke K.; Li, Changming; Jung, Richard H.; and Kines, Joseph G., 5,587,872, Cl. 361-525.000.
- Li, Cheng J., to Simonds Industries, Inc.: File testing techniques, 5,587,925, Cl. 364-508.000.
- Li, Hsin L.: See—
Lin, Leroy C.; Wilson, Laura G.; Bhatnagar, Ashok; and Li, Hsin L., 5,587,230, Cl. 428-245.000.
- Li, Yanlong: See—
Norcross, Kenneth L.; and Li, Yanlong, 5,587,081, Cl. 210-604.000.
- Lian, Ke K.; Li, Changming; Jung, Richard H.; and Kines, Joseph G., to Motorola, Inc.: Electrochemical cell having symmetric inorganic electrodes, 5,587,872, Cl. 361-525.000.
- Liang, Mong-Song: See—
Su, Chung-Hui; Liang, Mong-Song; Wu, Shou-Gwo; and Wang, Chen-Jong, 5,587,696, Cl. 338-314.000.
- Liang, Tui-Chang: Portable toilet, 5,586,344, Cl. 4-484.000.
- Liebrecht, Jeffrey W.: See—
Acosta, Phyllis J. B.; Grondalski, Richard A.; Liebrecht, Jeffrey W.; and Reynolds, Patricia A., 5,587,399, Cl. 514-561.000.
- Life Resuscitation Technologies, Inc.: See—
Fahy, Gregory M., 5,586,987, Cl. 606-155.000.
- Light & Sound Design Limited: See—
Hunt, Mark A.; and Murray, Andrew, 5,588,021, Cl. 375-211.000.
- Light, Glenn M.: See—
McCalskey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., 5,587,534, Cl. 73-623.000.
- Liguori, Thomas A., to Dataproducts Corporation: Half-tone screen using spot function to rank pixels following one or more design rules, 5,587,811, Cl. 358-456.000.
- Liljegen, Lars: See—
Bergström, Jan O.; Liljegen, Lars; Skarhed, Ove; and Årenäs, Anders, 5,587,863, Cl. 361-93.000.
- Lim, Moo-Gil, to Samsung Electronics Co., Ltd.: Digital demodulating method and circuit for use in a time-division multiple access channel, 5,588,027, Cl. 375-330.000.
- Lin, Eileen T.; and Wang, Yun, to International Business Machines Corporation: Push down optimization in a distributed, multi-database system, 5,588,150, Cl. 395-601.000.
- Lin, Jonathan; Peng, Jack Z.; Barsan, Radu; and Mehta, Sunil, to Advanced Micro Devices, Inc.: CMOS EEPROM cell with tunneling window in the read path, 5,587,945, Cl. 365-185.100.
- Lin, Jong-Kai; Lytle, William H.; and Subrahmanyam, Ravichandran, to Motorola, Inc.: Method of forming an electrical interconnect, 5,587,342, Cl. 437-209.000.
- Lin, Leroy C.; Wilson, Laura G.; Bhatnagar, Ashok; and Li, Hsin L., to AlliedSignal Inc.: High strength composite, 5,587,230, Cl. 428-245.000.
- Lin, Ronny W.; Atkinson, Eldon E., Jr.; and Balhoff, Donald E., to Albemarle Corporation: Process for obtaining [S,S]-ethylenediamine-n,n'-disuccinic acid from a salt solution of such acid and l-aspartic acid, 5,587,512, Cl. 562-565.000.
- Lin, Wen-Hwa: Detachable bicycle pedal mounting structure, 5,586,472, Cl. 74-594.100.
- Lin, Yong C.: See—
Lin, Yong F.; and Lin, Yong C., 5,586,406, Cl. 43-55.000.
- Lin, Yong F.; and Lin, Yong C.: Live bait container, 5,586,406, Cl. 43-55.000.
- Lindbauer, Ralf L.: See—
Bobik, Michael; Lindbauer, Ralf L.; and Glasner, Alfred, 5,587,138, Cl. 423-242.100.
- Lindgren, Ulf: See—
Lorenz, Hans P.; Straehler, Bernd; and Lindgren, Ulf, 5,587,200, Cl. 427-2.240.
- Lindner, Juergen: See—
Kuhm, Peter; Schroeder, Christine; Sander, Volker; Lindner, Juergen; and De Riese-Meyer, Loert, 5,587,063, Cl. 205-173.000.
- Lindh, Kjell: See—
Lindh, Leif; and Lindh, Kjell, 5,586,778, Cl. 280-40.000.
- Lindh, Leif; and Lindh, Kjell, to Eurogreen International Inc.: Collapsible golf cart, 5,586,778, Cl. 280-40.000.
- Lindner, Bernd: See—
Beaumont, Hendrikus; Haas, Hanns-Otto; Wiese, Holger; and Lindner, Bernd, 5,586,499, Cl. 101-211.000.
- Lindquist, Henning, to MAN B&W Diesel A/S: Large two-stroke internal combustion engine, 5,586,526, Cl. 123-90.120.
- Lindsley, Herbert B.: See—

- Smith, Donald D.; Cohick, Christopher B.; and Lindsley, Herbert B., 5,587,321, Cl. 435-305.300.
- Linnig, Karl-Heinz, Friction clutch, particularly for a fan wheel of a motor vehicle engine fan, 5,586,636, Cl. 192-48.200.
- Lion, Bertrand; Mondet, Jean; and Dupuis, Christine, to L'Oreal Aqueous aerosol lacquer for setting hair, 5,587,145, Cl. 424-45.000.
- Liotta, Dennis C.; and Lagu, Bharat R., to Emory University, Diastereoselective synthesis of hydroxyethylene dipeptide isosteres, 5,587,514, Cl. 564-134.000.
- Lippitt, William L., See—
Rosich, Mitchell N.; and Lippitt, William L., 5,587,964, Cl. 365-238.500.
- Litak, Peter T., See—
Kaufman, Joel M.; and Litak, Peter T., 5,587,112, Cl. 252-589.000.
- LiteCom, Inc., See—
Fan, Robert J., 5,588,086, Cl. 385-138.000.
- Litronik Batterie-technologie GmbH & Co., See—
Fehrmann, Gerd; Frömmel, Rainer; and Wolf, Rüdiger, 5,587,258, Cl. 429-228.000.
- Little, Oscar L., Sr. Lower leg exercise device, 5,586,958, Cl. 482-79.000.
- Liu, Simon Y., to Americorp Inc. Portable pizza oven, 5,586,488, Cl. 99-331.000.
- Liu, Yang-Ting, Adjustable headrest, 5,586,810, Cl. 297-406.000.
- Livengood, Rodney C. Water bottle assist device, 5,586,692, Cl. 222-166.000.
- Livernois Die and Automation, See—
Horde, Boice F.; and Akers, Denver, 5,586,464, Cl. 72-405.160.
- Lloyd, Thomas B., See—
Hou, Wei-Hsin; Lloyd, Thomas B.; and Schubert, Frederic E., 5,587,242, Cl. 428-402.000.
- Lo, Wai C. J., See—
Laine, Roger A.; and Lo, Wai C. J., 5,587,292, Cl. 435-7.900.
- Löh, Rüdiger, See—
Schröder-Brumloop, Helmut; and Löh, Rüdiger, 5,587,565, Cl. 187-316.000.
- Lobo, Alfred D., See—
Huvar, Gary S.; and Lobo, Alfred D., 5,587,096, Cl. 219-521.000.
- Locke, Michael E., to Siemens Rdm Communications Inc. Voice/data transfer method and apparatus utilizing an alternate line, 5,588,045, Cl. 379-67.000.
- Lockheed Martin Corporation, See—
Allen, Peter B., 5,586,724, Cl. 239-112.000.
- Lockheed Martin Energy Systems, Inc., See—
Taleyarkhan, Russi P., 5,586,597, Cl. 164-487.000.
- Lockman, Mark E., See—
Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., 5,587,932, Cl. 364-556.000.
- Loehr, Karl, See—
Robinson, Darrell; Loehr, Karl; Pruehs, Allen V.; and Learmont, Robert O., 5,586,913, Cl. 439-638.000.
- Lofgren, Clifford S., See—
Vander Meer, Robert K.; Hanks, William A.; and Lofgren, Clifford S., 5,587,401, Cl. 514-675.000.
- Lofgren, Dan M.; and Dietrich, William A., to Voysys Corporation, Voice response system with programming language extension, 5,588,044, Cl. 379-67.000.
- Loibl, Josef, to Siemens Aktiengesellschaft, Bus system, 5,588,123, Cl. 395-287.000.
- Long, John H., See—
Misukakis, Eugene D.; Long, John H.; Dean, Lawrence A.; and Kuligowski, Douglas J., 5,588,140, Cl. 395-500.000.
- Long, John P., See—
Belcher, James F.; Frank, Steven N.; Long, John P.; and Jones, Jeanée, 5,587,090, Cl. 216-17.000.
- Longest, H. Cary; and Lynch, James L., to Philip Morris Incorporated, Methods and apparatus for inspecting the appearance of substantially circular objects, 5,588,068, Cl. 382-141.000.
- Longworth, Ralph C., See—
Blecher, Leo; Longworth, Ralph C.; Murray, F. Scott; Jonas, Philip A.; and Boiarski, Michael, 5,586,437, Cl. 62-47.100.
- Loomis, Gary, See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrahala, Richard; Rimya, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P., deceased (by Lev A. Andrianov, Dmitry B. Gudkov, executors, Ekaterina L. Andrianova, executrix), to 2860601 Canada Inc. Method for producing affino-enzymatic compounds and visualizing agent and application thereof, 5,587,295, Cl. 435-11.000.
- L'Oreal, See—
Carsey, Laurence; and Sturla, Jean M., 5,587,170, Cl. 424-401.000.
- De Laforcade, Vincent, 5,586,693, Cl. 222-182.000.
- Deffandre, André; Dubois, Michel; Forestier, Serge; and Richard, Hervé, 5,587,150, Cl. 424-59.000.
- Junino, Alex; LaGrange, Alain; N'Guyen, Quang L.; and Bourbonloul, Marie-Alix, 5,587,173, Cl. 424-401.000.
- Lion, Bertrand; Mondet, Jean; and Dupuis, Christine, 5,587,145, Cl. 424-45.000.
- N'Guyen, Quang L., 5,587,171, Cl. 424-401.000.
- Philippe, Michel; Semeria, Didier; and Bollens, Eric, 5,587,169, Cl. 424-401.000.
- Richard, Hervé; Leduc, Madeleine; and LaGrange, Alain, 5,587,151, Cl. 424-59.000.
- Lorenz, Gisela, See—
Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schelberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63.000.
- Lorenz, Hans P.; Straehler, Bernd; and Lindegren, Ulf, to Pacesetter AB, Method for manufacturing a medical electrode, 5,587,200, Cl. 427-2.240.
- Lorrain, Henri L. P., to U.S. Philips Corporation, Safety unit for an electric 3-phase circuit, 5,586,908, Cl. 439-511.000.
- Lothamer, Thomas J.; Pontecorvo, Carl A.; Schatke, Thomas L.; and Osterhoof, Richard A., to ITT Corporation, Interlock switch, 5,587,568, Cl. 200-16.000.
- Love, Dale, See—
Eby, Devon; Love, Dale; and Reed, James L., 5,586,373, Cl. 24-525.000.
- Love, Leonard S., to Sydio Inc. Wastewater treatment apparatus, 5,587,067, Cl. 210-155.000.
- Lovvorn, Richard V., See—
Owens, Steve C.; Lovvorn, Richard V.; and Elder, Albert B., 5,587,181, Cl. 425-3.000.
- Lowe Alpine Systems International Limited, See—
Leonard, James, 5,586,705, Cl. 224-631.000.
- Lowry, Philip J., See—
Behan, Dominic P.; Vale, Wylie W., Jr.; Fischer, Wolfgang H.; and Lowry, Philip J., 5,587,462, Cl. 530-350.000.
- LRT, Inc., See—
Fahy, Gregory M., 5,586,438, Cl. 62-78.000.
- LSI Logic Corporation, See—
Garza, Mario, 5,587,267, Cl. 430-168.000.
- Maturi, Greg; and Dietke, Gregg, 5,588,029, Cl. 375-364.000.
- Wang, Deborah C., 5,587,923, Cl. 364-490.000.
- Lu, Duojia, See—
Bai, Baoheng; Guner, Mahmut; Lu, Duojia; Rosenblitt, David A.; and Stuck, Kaaren L., 5,588,138, Cl. 395-497.040.
- Lu, Liang-Ju, See—
Emmons, David J.; and Lu, Liang-Ju, 5,588,087, Cl. 385-140.000.
- Lubowitz, Hyman R., See—
Sheppard, Clyde H.; and Lubowitz, Hyman R., 5,587,105, Cl. 252-183.110.
- Luce, David A., and Miller, Donald E., to Leica Inc. Joystick override control for an ophthalmic instrument, 5,587,748, Cl. 351-208.000.
- Lucent Technologies Inc., See—
Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Lyla R.; and Strohecker, Cary A., Sr., 5,588,051, Cl. 379-243.000.
- Cheng, Kwang-Ting; and Entrena, Luis, 5,587,919, Cl. 364-489.000.
- Chraplyvy, Andrew R.; and Tkach, Robert W., 5,587,830, Cl. 359-341.000.
- Greene, Benjamin I.; Narayanan, Chellappan; and Presby, Herman M., 5,588,085, Cl. 385-123.000.
- Lucky Limited, See—
Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
- Ludwig Institute for Cancer Research, See—
Lurquin, Christophe; and Boon-Falleur, Thierry, 5,587,289, Cl. 435-6.000.
- Van Snick, Jacques; Uytendhove, Catherine; and Simpson, Richard J., 5,587,302, Cl. 435-69.500.
- Lumley, John M.; and Paik, Ho J., to Oxford Instruments (UK) Limited, Proof mass support and sensing system, 5,587,526, Cl. 73-382.000.
- Lund, David R., to Victory in Jesus Ministries, Inc. Torque transfer tool, 5,586,474, Cl. 81-57.300.
- Lund, Gary K., See—
Brailwaite, Paul C.; Lund, Gary K.; and Wardle, Robert B., 5,587,553, Cl. 149-19.600.
- Lund, William J., to ACT Distribution, Inc. Hydrothermal stabilizer, 5,586,572, Cl. 137-337.000.
- Luo, Min, See—
Teraoka, Iwao; and Luo, Min, 5,587,082, Cl. 210-635.000.
- Luo, Serena M., See—
Wang, Tsing-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisca; and Massingill, Thomas J., 5,587,336, Cl. 437-183.000.
- Lurquin, Christophe; and Boon-Falleur, Thierry, to Ludwig Institute for Cancer Research, Isolated nucleic acid molecules which are members of the MAGE-Xp family and uses thereof, 5,587,289, Cl. 435-6.000.
- Luttrell, Gerald H., See—
Yoon, Roe-Hwan; and Luttrell, Gerald H., 5,587,085, Cl. 210-711.000.
- Lynam, Niall R., See—
Agrawal, Raj K.; Lynam, Niall R.; and Galer, James K., 5,587,236, Cl. 428-334.000.
- Lynch, Gerard J.; and Quinn, Joseph, to H-Tech, Inc. Fluid filter with enhanced backflush flow, 5,587,074, Cl. 210-411.000.
- Lynch, James L., See—
Longest, H. Cary; and Lynch, James L., 5,588,068, Cl. 382-141.000.
- Lynd, L. Grant, to National Packaging Corporation, Beverage container cap with stirrer, 5,586,676, Cl. 220-212.000.
- Lyons, Paul W., See—
Strolle, Christopher H.; Jaffe, Steven T.; and Lyons, Paul W., 5,588,025, Cl. 375-316.000.
- Lytle, William H., See—
Lin, Jong-Kai; Lytle, William H.; and Subrahmanyam, Ravichandran, 5,587,342, Cl. 437-209.000.

- M.E.P. Machine Elettroniche Piegatrici SpA, See—
Del Fabro, Giorgio; and Del Fabro, Marcello, 5,586,709, Cl. 226-177.000.
- Ma, Chen-Chi M., to National Science Council, Process for pultruding fiber reinforced furan composites, 5,587,034, Cl. 156-166.000.
- Ma, Yiping, to Iomega Corporation, Method for detecting transient write errors in a disk drive, 5,588,007, Cl. 371-21.200.
- Macaraeg, Marlita F., See—
Wang, Tsing-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisca; and Massingill, Thomas J., 5,587,336, Cl. 437-183.000.
- MacDonald, James B., to Wang Laboratories, Inc. Clock frequency multiplying and squaring circuit and method, 5,587,673, Cl. 326-93.000.
- Machesney, Brian J.; Mandelman, Jack A.; and Nowak, Edward J., to International Business Machines Corporation, Contacted body silicon-on-insulator field effect transistor, 5,587,604, Cl. 257-350.000.
- Machida, Hiroshi, to Mitsubishi Gas Chemical Company, Inc. Process for producing 2,6-naphthalenedicarboxylic acid and ester thereof, 5,587,508, Cl. 560-77.000.
- Machida, Yoshimasa, See—
Negi, Shigeto; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222.000.
- Machonkin, Mary A., See—
Hsieh, Bing R.; Mori, Joseph; Machonkin, Mary A.; and Ewing, Joan R., 5,587,224, Cl. 428-195.000.
- Mackler, Carl R., See—
Roy, Timothy A.; Mackler, Carl R.; and Goldstein, Lawrence, 5,587,324, Cl. 436-183.000.
- Mackles, Leonard; and Chavkin, Leonard, Clear solid topical deodorant compositions comprising a water-insoluble ester of a water-soluble acid, 5,587,152, Cl. 424-65.000.
- Madeira, Robert J., See—
Ruffini, Robert S.; Madeira, Robert J.; and Ruffini, Robert T., 5,588,019, Cl. 373-152.000.
- Madison Chemical Co., Inc., See—
Shepherd, Marjorie H.; and Gasaway, Kim B., 5,587,006, Cl. 106-1.050.
- Madison, Harry; and Tilley, Jeffrey L., to Harsco Corporation, Rail guide wheel apparatus with double overcenter linkage, 5,586,507, Cl. 105-215.200.
- Madland, Paul D., See—
Abramson, Jeffrey M.; Akkary, Haim; Glew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395-376.000.
- Maeda, Hirokazu; Furuta, Hideo; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, to Fuji Oil Company, Ltd. Process for production of water-soluble vegetable fiber, 5,587,197, Cl. 426-658.000.
- Maehama, Mitsuhiro, See—
Tatsumi, Haruki; Ikemoto, Yoshiaki; Maehama, Mitsuhiro; Oyanagi, Toshiaki; and Matsubara, Tsugio, 5,587,246, Cl. 428-511.000.
- Magda, Darren, See—
Sessler, Jonathan L.; Mody, Tarak D.; Hemmi, Gregory W.; Král, Vladimir A.; and Magda, Darren, 5,587,371, Cl. 514-185.000.
- Magee, Robert B., See—
Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., 5,587,183, Cl. 425-4.000.
- Magnet-Physik Dr. Steingrover GmbH, See—
Steingrover, Erich, 5,586,460, Cl. 72-56.000.
- Magome, Nobutaka, See—
Mizutani, Hideo; Kobayashi, Naoyuki; and Magome, Nobutaka, 5,587,794, Cl. 356-375.000.
- Magori, Valentin, See—
Kroemer, Nikl; Vossiek, Martin; Eccardt, Peter-Christian; and Magori, Valentin, 5,587,969, Cl. 367-99.000.
- Mahnkopf, Reinhard; and Vom Felde, Andreas, to Siemens Aktiengesellschaft, Bipolar transistor and manufacturing method, 5,587,599, Cl. 257-370.000.
- Mail, Alain, See—
Ronge, Catherine; Mail, Alain; and Marot, Yves, 5,587,519, Cl. 73-1.000.
- Majima, Yoshihiro, See—
Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, 5,586,539, Cl. 123-458.000.
- Major, Michael D., See—
Mehner, David W.; Forneck, Kevin; Prince, Steven; and Major, Michael D., 5,587,196, Cl. 426-611.000.
- Maki, Atsushi; Kawaguchi, Fumio; Yamashita, Yuichi; and Ito, Yoshitoshi, to Hitachi, Ltd. Optical system for measuring metabolism in a body, 5,586,554, Cl. 128-653.100.
- Maki, Roger M., to Illinois Tool Works Inc. Dam member for a screen deck, 5,586,661, Cl. 209-397.000.
- Maki, Yasuhito, to Sony Corporation, Solid-state image-sensing device and bar code reader operable with low voltage power supplies and using two charge transfer devices of different sizes, 5,587,576, Cl. 235-462.000.
- Makimoto, Mitsuo, See—
Yabuki, Hiroyuki; Sagawa, Morikazu; and Makimoto, Mitsuo, 5,587,690, Cl. 331-2.000.
- Makino, Kunio, See—
Hasegawa, Toshiro; Shimoda, Kazuhiko; Makino, Kunio; and Tonioka, Mitsuo, 5,586,994, Cl. 29-623.500.
- Makk, Stephen T., See—
Martinson, Glen D.; and Makk, Stephen T., 5,587,916, Cl. 364-483.000.
- Makovec, Francesco; Rovati, Lucio C.; and Rovati, Luigi A., to Rotta Research Laboratorium S.p.A. Basic derivatives of glutamic acid and aspartic acid as gastrin or cholecystokinin antagonists, 5,587,479, Cl. 544-70.000.
- Malandra, Louis J., See—
Bevilacqua, Bruce W.; Malandra, Louis J.; Meuschke, Robert E.; and Harkness, Alex W., 5,588,031, Cl. 376-287.000.
- Malczewski Holdings, Inc., See—
Malczewski, Jerry P., 5,586,395, Cl. 33-471.000.
- Malczewski, Jerry P., to Malczewski Holdings, Inc. Level angle gauge, 5,586,395, Cl. 33-471.000.
- Malkin, Boris; Perlov, Gena; and Yannai, Shmuel, to Ozontech Ltd. System for an efficient manufacture of ozone, 5,587,131, Cl. 422-186.110.
- Mallonee, William C. Process for making fiber for a carpet face yarn, 5,587,118, Cl. 264-78.000.
- Malter, James S., to Wisconsin Alumni Research Foundation, Method to increase regulatory molecule production, 5,587,300, Cl. 435-69.100.
- Mama, Takashi, See—
Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500.000.
- MAN B&W Diesel A/S, See—
Lindquist, Henning, 5,586,526, Cl. 123-90.120.
- Man Gutehoffnungshütte Aktiengesellschaft, See—
Vollhardt, Frohmuth; and Heering, Jürgen R., 5,586,995, Cl. 55-227.000.
- MAN Roland Druckmaschinen AG, See—
Beaumont, Hendrikus; Haas, Hanns-Otto; Wiese, Holger; and Lindner, Bernd, 5,586,499, Cl. 101-211.000.
- Rakitsch, Peter; and Zehentbauer, Hans, 5,587,796, Cl. 356-445.000.
- Mandava, Babu S.; and Weddle, E. Eugene, to Zilog, Inc. Single chip dual processor, 5,588,118, Cl. 395-200.050.
- Mandelman, Jack A., See—
Machesney, Brian J.; Mandelman, Jack A.; and Nowak, Edward J., 5,587,604, Cl. 257-350.000.
- Mangold, Anita L., See—
Mangold, Howard L.; and Mangold, Anita L., 5,586,509, Cl. 108-28.000.
- Mangold, Howard L.; and Mangold, Anita L. Card table food, beverage, bidding box and convention card holding apparatus, 5,586,509, Cl. 108-28.000.
- Manico, Joseph A., See—
Mehra, Madhav; and Manico, Joseph A., 5,587,756, Cl. 396-515.000.
- Manitowoc Company, Inc., The, See—
Schlosser, Charles E.; Mueller, Lee G.; and McDougal, Gregory, 5,586,439, Cl. 62-78.000.
- Mann, Inderjit S., See—
Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance, 5,587,483, Cl. 548-252.000.
- Mann, Philip A.; and Green, Ian, to Emhart Glass Machinery Investments Inc. Takeout mechanism in glassware forming machine, 5,587,000, Cl. 65-260.000.
- Mannesmann Aktiengesellschaft, See—
Esser, Karl-Joseph, 5,586,476, Cl. 82-1.110.
- Manning, David D., See—
Kiessling, Laura L.; Manning, David D.; and Mortell, Kathleen H., 5,587,442, Cl. 526-238.200.
- Manning, Troy, See—
Zagar, Paul; and Manning, Troy, 5,587,671, Cl. 326-83.000.
- Manoharan, Muthiah, See—
Cook, Phillip D.; Ramasamy, Kanda S.; and Manoharan, Muthiah, 5,587,469, Cl. 536-23.100.
- Manookian, Arman K., Jr. Vapor separating device, 5,586,996, Cl. 55-321.000.
- Manowski, Maxwell E., See—
Fuller, Robert M.; Epler, Frederick A.; and Manowski, Maxwell E., 5,588,037, Cl. 379-57.000.
- Manson, Larry J.; Scriber, Chris A.; and Davis, William L., to Whirlpool Corporation, Fan motor brown-out control algorithm, 5,587,642, Cl. 318-812.000.
- Mansour, Tarek, See—
Belleau, Bernard, deceased; Nguyen-Ba, Nghe; Kong, Laval C. C.; Mansour, Tarek; Jin, Haolun; and Brasili, Livio, 5,587,480, Cl. 544-310.000.
- Mantone, Anthony, See—
Fiddes, Neil G.; King, Christopher G.; Mantone, Anthony; and Shaffer, Frank D., 5,586,712, Cl. 228-5.700.
- Manyak, David M., See—
Weiner, Ronald M.; and Manyak, David M., 5,587,313, Cl. 435-252.100.
- Marchello, Joseph M., See—
Sandusky, Donald A.; and Marchello, Joseph M., 5,587,041, Cl. 156-441.000.
- Marchywka, Michael J.; and Pehrsson, Pehr E., to United States of America, Navy, Growing and releasing diamonds, 5,587,210, Cl. 427-523.000.
- Marcovici, Sorin, See—
Botka, Alexander T.; Tuval, Ben; and Marcovici, Sorin, 5,587,611, Cl. 257-458.000.
- Marino, Francis E. Pasta percolator, 5,586,487, Cl. 99-330.000.
- Mark IV Transportation Products Corp., See—
Boone, Steven F.; and Ho, Edward J., 5,587,712, Cl. 342-42.000.
- Marko, Kenneth A., See—

- Hampo, Richard J.; Marko, Kenneth A.; and Bryant, Bruce D., 5,587,524, Cl. 73-116.000.
- Marlette, Mary E.: See—
Zabron, Florian S.; Marlette, Mary E.; Rothman, Miles S.; and Hanrahan, William D., 5,586,643, Cl. 198-853.000.
- Marmarosi née Kellner, Katalin: See—
Hajimichael, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Szekely, Istvan; Marmarosi née Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
- Marot, Yves: See—
Ronge, Catherine; Mail, Alain; and Marot, Yves, 5,587,519, Cl. 73-1.00G.
- Marshall, Carl J., Jr.; and Freeman, Gary M., to J. M. Huber Corporation. Optically whitened clay pigments, 5,587,011, Cl. 106-416.000.
- Marshall, Robert C.; and Pansari, Frank, Jr., to Moles Incorporated. Insulation displacement electrical connector with improved strain relief, 5,586,905, Cl. 439-463.000.
- Martin, James R.: See—
Lennon, George E.; Martin, James R.; and Anderson, Charles D., 5,586,963, Cl. 493-299.000.
- Martin Marietta Corporation: See—
Diehl, Matthew D., 5,586,579, Cl. 137-614.170.
- Martinez, Evelyn R. Hair growing mannequin head, 5,586,696, Cl. 223-66.000.
- Martinez, Marcus J.; and Tafaya, Anthony S., to Olympus America, Inc. Continuously adjustable high flow insufflator valve, 5,586,974, Cl. 604-26.000.
- Matinson, Glen D.; and Makk, Stephen T., to B.E.L.-Tronics Limited. Low voltage sensing circuits for battery powered devices having a micro-processor, 5,587,916, Cl. 364-483.000.
- Matton, Kornel R.: See—
Mogilevsky, Alex; and Matton, Kornel R., 5,588,099, Cl. 395-139.000.
- Maruyama, Koji: See—
Sonobe, Naohiro; Maruyama, Koji; and Iwasaki, Takao, 5,587,255, Cl. 429-218.000.
- Mary Kay Inc.: See—
Smith, Walter P., 5,587,396, Cl. 514-557.000.
- Marzec, Steven E.; and Marzec, Willy. Multiple stage supercharging system, 5,586,540, Cl. 123-559.100.
- Marzec, Willy: See—
Marzec, Steven E.; and Marzec, Willy, 5,586,540, Cl. 123-559.100.
- Marzolini, Fausto; Calmanti, Giulio; and Sacchi, Gianpiero, to Ausimont S.p.A. Process for delignifying raw cellulosic material impregnated with monopersulfuric acid, 5,587,049, Cl. 162-40.000.
- Masaki, Junya, to Canon Kabushiki Kaisha. Charging control device for flash device, 5,587,644, Cl. 320-1.000.
- Masaki, Kiyoshi: See—
Yoshiura, Tsukasa; and Masaki, Kiyoshi, 5,587,852, Cl. 360-78.120.
- Masao Nakamura: See—
Takeuchi, Kiyoshi; Takeda, Shin; and Nakamura, Masao, 5,586,462, Cl. 72-150.000.
- Masayuki, Watanabe; Toshio, Sugano; Seichiro, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima, to Hitachi, Ltd.; Hitachi Tobu Semiconductor, Ltd.; and Akita Electronics Co., Ltd. Process for manufacturing a stacked integrated circuit package, 5,587,341, Cl. 437-206.000.
- Maschinenfabrik Hennecke GmbH: See—
Sulzbach, Hans-Michael; and Rohrig, Lothar, 5,587,182, Cl. 425-4.00C.
- Massachusetts Institute of Technology: See—
Massie, Thomas H.; and Salisbury, J. Kenneth, Jr., 5,587,937, Cl. 364-578.000.
- Masse, Jean M. Air/fuel mixture supply device for a two-stroke internal-combustion engine, 5,586,525, Cl. 123-73.00B.
- Massie, Harold L., to Intel Corporation. High precision switching regulator circuit, 5,587,650, Cl. 323-282.000.
- Massie, Thomas H.; and Salisbury, J. Kenneth, Jr., to Massachusetts Institute of Technology. Force reflecting haptic interface, 5,587,937, Cl. 364-578.000.
- Massingill, Thomas J.: See—
Wang, Tsing-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisca; and Massingill, Thomas J., 5,587,336, Cl. 437-183.000.
- Mast, Donald R.; McNabb, Robert L.; and Rapp, Joseph A., to Caterpillar Inc. Rollover protective structure and method, 5,586,784, Cl. 280-756.000.
- Mastrototaro, John J.: See—
Halili, Edgardo C.; and Mastrototaro, John J., 5,586,553, Cl. 128-635.000.
- Matsushita Electric Industrial Co.: See—
Tanaka, Shoji; Imura, Katsuhiko; and Kageyama, Satoshi, 5,588,065, Cl. 381-96.000.
- Matkovich, Vlado I.: See—
Pall, David B.; Gsell, Thomas C.; Matkovich, Vlado I.; and Bormann, Thomas, 5,587,070, Cl. 210-202.000.
- Matsen, Marc R.; Puel, Richard J.; Crow, Wesley B.; and Nansen, David S., to Boeing Company. The joining large structures using localized induction heating, 5,587,098, Cl. 219-615.000.
- Matson, Donald P.: See—
Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., 5,587,932, Cl. 364-556.000.
- Matsubara, Tsugio: See—
Tsutsumi, Haruki; Ikemoto, Yoshiaki; Maehama, Mitsuhiro; Oyanagi, Toshiki; and Matsubara, Tsugio, 5,587,246, Cl. 428-511.000.
- Matsubara, Yoshihisa, to NEC Corporation. Test piece for X-ray inspection, 5,587,590, Cl. 257-48.000.
- Matsuda, Eichika, to Sharp Kabushiki Kaisha. Portable terminal device, 5,587,724, Cl. 345-156.000.
- Matsuda, Hidemi: See—
Shimizu, Kazuhiko; Ito, Takeo; and Matsuda, Hidemi, 5,587,835, Cl. 359-589.000.
- Matsuda, Teruo: See—
Tanaka, Nobuo; Otani, Seiji; Kawakita, Hiroyuki; and Matsuda, Teruo, 5,586,975, Cl. 604-89.000.
- Matsuda, Yoshio; Akashi, Shunji; and Yoshida, Hiroshi, to YKK Corporation. Double-layer slide fastener tape, 5,586,369, Cl. 24-392.000.
- Matsuda, Yoshio; and Kato, Hidenobu, to YKK Corporation. Warp-knit tape for slide fastener, 5,586,454, Cl. 66-193.000.
- Matsuda, Yoshio: See—
Fujishima, Kazuyasu; Matsuda, Yoshio; and Asakura, Mikio, 5,588,130, Cl. 395-445.000.
- Matsuhisa, Yoji: See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, 5,587,240, Cl. 428-367.000.
- Matsuhita Electric Industrial Co., Ltd.: See—
Yoshiura, Tsukasa; and Masaki, Kiyoshi, 5,587,852, Cl. 360-78.120.
- Matsukura, Ushio: See—
Horigane, Akira; Matsukura, Ushio; and Kamio, Masayoshi, 5,587,298, Cl. 435-41.000.
- Matsumoto, Masahiro: See—
Mochizuki, Shigeo; Matsumoto, Masahiro; Yamazaki, Toshio; and Ichinobe, Shoji, 5,587,445, Cl. 526-271.000.
- Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhisa; and Kasai, Satoshi, to Mitsubishi Jidosha Kogyo Kabushiki Kaisha. Mishire detecting method, 5,587,909, Cl. 364-431.080.
- Matsumoto, Tetsuro: See—
Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Matsumoto, Yoshikane: See—
Shinohara, Makoto; Matsumoto, Yoshikane; and Suematsu, Shigenori, 5,586,496, Cl. 101-93.040.
- Matsumura, Akira: See—
Kishida, Takahito; Matsumura, Akira; and Kawakami, Atsushi, 5,587,274, Cl. 430-270.100.
- Matsumura, Miki: See—
Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, 5,587,260, Cl. 430-7.000.
- Matsumura, Yoshito: See—
Hashimoto, Kenji; and Matsumura, Yoshito, 5,586,874, Cl. 417-569.000.
- Matsunaga, Yoshiyuki: See—
Sato, Shigehiro; Matsunaga, Yoshiyuki; Ono, Tsuyoshi; and Karube, Takaaki, 5,587,097, Cl. 219-543.000.
- Matsuo, Hirokazu: See—
Johdai, Akiyoshi; Ohhata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu; and Hirano, Yoshihito, 5,587,782, Cl. 355-309.000.
- Matsuo, Makoto: See—
Iijima, Masayuki; Dantani, Kyoji; Ohata, Hiroyuki; Matsuo, Makoto; Utsumi, Minoru; and Take, Seiji, 5,587,264, Cl. 430-57.000.
- Matsushima, Kenichi, to Seiko Instruments Inc. Coordinate detecting apparatus having acceleration detectors, 5,587,558, Cl. 178-18.000.
- Matsushita Electric Industrial Co., Ltd.: See—
Arita, Kiyoshi; and Takahashi, Kouichi, 5,586,713, Cl. 228-102.000.
- Hasegawa, Toshiro; Shimoda, Kazuhiko; Makino, Kunio; and Tomioka, Mitsuo, 5,586,994, Cl. 29-623.500.
- Kasihara, Takasi, 5,587,838, Cl. 359-649.000.
- Kojima, Yuri; Mototani, Yuji; and Asaoka, Junichi, 5,587,254, Cl. 429-206.000.
- Komiya, Hirofumi; Sakai, Keita; Koshi, Kazumine; and Saito, Noriyuki, 5,588,092, Cl. 395-109.000.
- Minato, Tetsuya; Yonehara, Toshimitsu; Teranishi, Junichi; Toyoda, Shohei; Bito, Toshiaki; and Takashima, Kazushige, 5,587,694, Cl. 336-65.000.
- Nagao, Kenji; Sohma, Masaki; Ando, Shigeru; and Kobayakawa, Michihiro, 5,587,927, Cl. 364-514.00A.
- Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Issei; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.
- Nakamura, Masahiko; Yamamoto, Hajime; and Terada, Hiroshi, 5,587,783, Cl. 355-326.00R.
- Ogawa, Kazufumi, 5,587,220, Cl. 428-71.000.
- Otsuka, Takeshi; and Higashida, Masaaki, 5,587,807, Cl. 386-46.000.
- Sano, Kousei; and Kadowaki, Shin-ichi, 5,587,985, Cl. 369-124.000.
- Shimotashiro, Masafumi; and Kurse, Akio, 5,587,848, Cl. 360-46.000.
- Soga, Mamoru; Mino, Norihisa; Ogawa, Kazufumi; Mochizuki, Yusuke; and Shibata, Tsuneo, 5,587,209, Cl. 427-503.000.
- Yabuki, Hiroyuki; Sagawa, Morikazu; and Makimoto, Mitsuo, 5,587,690, Cl. 331-2.000.
- Yamada, Masazumi; Kadono, Shinya; and Kato, Shiro, 5,587,806, Cl. 386-68.000.
- Yoshioka, Kazumi; Ohta, Taken; Furukawa, Shigeaki; and Kawahara, Katsumi, 5,587,216, Cl. 428-64.400.
- Matsushita Electric Works, Ltd.: See—
Nakatani, Takuya; Abe, Mitsuataka; Dono, Shigeru; and Urano, Youji, 5,586,387, Cl. 29-703.000.

- Naruo, Masahiro, 5,587,894, Cl. 363-84.000.
- Matsushita Graphic Communication Systems, Inc.: See—
Kunita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Keiichi, 5,587,798, Cl. 358-261.100.
- Matsushita, Kunio: See—
Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin-ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
- Matel, Inc.: See—
Hippely, Keith A.; Wood, Larry R.; Walsh, Brian E.; and Choy, Terence A., 5,586,923, Cl. 446-14.000.
- Matern, Charles J., Jr.; and Tatum, Lawrence G. Power tool adapter, 5,586,847, Cl. 408-239.00A.
- Manis, Henry J. Spikes for field aerator, 5,586,603, Cl. 172-21.000.
- Matui, Ryotaro: See—
Ikeda, Tomoyuki; Ito, Yoshinobu; and Matui, Ryotaro, 5,587,625, Cl. 313-613.000.
- Marui, Greg; and Dierke, Gregg, to LSI Logic Corporation. MPEG audio synchronization system using subframe skip and repeat, 5,588,029, Cl. 375-364.000.
- Matz, Warren W. Device for sensing and treating bruxism, 5,586,562, Cl. 128-848.000.
- Mauger, Anthony B.: See—
Burke, Philip J.; Dowell, Robert I.; Mauger, Anthony B.; and Springer, Caroline J., 5,587,161, Cl. 424-178.100.
- Mauk, Albert L.: See—
Metzler, David M. A.; and Mauk, Albert L., 5,587,057, Cl. 204-228.000.
- Maurer, Mike: See—
Maurer, Uwe, 5,587,075, Cl. 210-411.000.
- Maurer, Uwe, to Maurer, Mike. Pressure filter, 5,587,075, Cl. 210-411.000.
- Mauzac, Olivier: See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrahala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- Maxtor Corporation: See—
Riggle, C. M.; and DeForest, Marvin, 5,588,030, Cl. 375-368.000.
- Maxwell, Ian: See—
Gibbon, Michael A.; Maxwell, Ian; and Toporkiewicz, Marian, 5,587,750, Cl. 352-184.000.
- May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harold, Jonathan, to Sharp Kabushiki Kaisha. Integrated electro-optical liquid crystal device and method of using such a device, 5,587,820, Cl. 359-72.000.
- Mayle, Dawn M. Wheel chair with a removable toilet bowl and seat, 5,586,343, Cl. 4-480.000.
- Mazda Motor Corporation: See—
Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203.000.
- Kawanishi, Toshiaki; Nobutoki, Yoshikazu; Hirano, Seiji; and Terayama, Koji, 5,588,002, Cl. 370-462.000.
- Shibata, Mineharu; and Takehara, Shin, 5,587,907, Cl. 364-424.046.
- McAnally, Bill H.; Carpenter, Robert H.; and McDaniel, Harley R., to Carrington Laboratories, Inc. Uses of aloe products in the treatment of inflammatory diseases, 5,587,364, Cl. 514-54.000.
- McBride, John C., to Bag-It Products Corp. Line storage device, 5,586,655, Cl. 206-388.000.
- McCabe, Thomas: See—
Kanjo, Wajih; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7.000.
- McCamy, T. H.; and Clark, William H. H. Insecticidal carpet and pretreatment process for producing insecticidal carpet, 5,587,221, Cl. 428-96.000.
- McCaslin, John A. Compressed gas gun, 5,586,545, Cl. 124-73.000.
- McColsky, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., to United States of America, Commerce. Wall thickness and flow detection apparatus and method for gas pipelines, 5,587,534, Cl. 73-623.000.
- McCoy, Thomas J.: See—
Fitzner, John E.; and McCoy, Thomas J., 5,586,700, Cl. 224-219.000.
- McCullough, James D., Jr.; and Bradford, John F., to Union Carbide Chemicals & Plastics Technology Corporation. Process for polymer degradation, 5,587,434, Cl. 525-333.800.
- McCurdy, Roger A.: See—
McIver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A., 5,587,906, Cl. 364-424.045.
- McDaniel, Harley R.: See—
McAnally, Bill H.; Carpenter, Robert H.; and McDaniel, Harley R., 5,587,364, Cl. 514-54.000.
- McDougal, Gregory: See—
Schlosser, Charles E.; Mueller, Lee G.; and McDougal, Gregory, 5,586,439, Cl. 62-78.000.
- McElrath, Kenneth O.: See—
Audent, Jay D.; and McElrath, Kenneth O., 5,587,261, Cl. 430-18.000.
- McEntee, Marjorie N. Paper recycling rack, 5,586,493, Cl. 100-34.000.
- McGinley, Michael J.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.
- McGrath, Thomas P.: See—
McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeaffa, Larry A.; and McGrath, Thomas P., 5,586,887, Cl. 434-20.000.
- McGregor, Thomas. Rolling shutter and shutter drive, 5,586,592, Cl. 160-133.000.
- McIntosh, Bruce M.; Smith, Francis S.; and Briscoe, Noel A., to Zyex Limited. Musical instrument strings, 5,587,541, Cl. 84-297.00S.
- McIver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A., to TRW Inc. Method and apparatus for sensing a vehicle crash condition using velocity enhanced acceleration crash metrics, 5,587,906, Cl. 364-424.045.
- McKay, Albert A.; and Smith, Eric G., to Westinghouse Air Brake Company. Electro-pneumatic freight brake control system, 5,586,813, Cl. 303-22.400.
- McKenry, Michael V. Pre-plant soil treatment method and apparatus, 5,586,728, Cl. 239-734.000.
- McManus, Martin P.: See—
Dewald, James E., Jr.; McManus, Martin P.; and McManus, Patrick W., 5,586,802, Cl. 296-26.000.
- McManus, Patrick W.: See—
Dewald, James E., Jr.; McManus, Martin P.; and McManus, Patrick W., 5,586,802, Cl. 296-26.000.
- McNabb, Robert L.: See—
Mast, Donald R.; McNabb, Robert L.; and Rapp, Joseph A., 5,586,784, Cl. 280-756.000.
- McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeaffa, Larry A.; and McGrath, Thomas P., to AAI Corporation. Howitzer strap-on kit for crew performance evaluation and training method, 5,586,887, Cl. 434-20.000.
- McQueen, Anne T.: See—
Leonard, R. Leon; Bouse, Earl F.; and McQueen, Anne T., 5,586,510, Cl. 110-345.000.
- McShane, William J.: See—
Slaughter, John E.; Olson, George; and McShane, William J., 5,587,788, Cl. 356-246.000.
- McSwiggen, John P.; and Roberts, Randall W., to Wilbrecht Electronics, Inc. Hearing aid battery cover switch, 5,588,064, Cl. 381-69.200.
- McWilliams, Linda C.: See—
Dauderman, Shelley L.; McWilliams, Linda C.; Nair, Hari A.; and Staud, Gary G., 5,587,356, Cl. 510-320.000.
- MDV Technologies, Inc.: See—
Viegas, Tacey X.; Reeve, Lorraine E.; and Henry, Raymond L., 5,587,175, Cl. 424-427.000.
- Mead Corporation, The: See—
Spamer, William S.; Suttles, J. Marshall; Parham, Dennis E.; and Whiten, James D., 5,586,687, Cl. 221-298.000.
- Meader, Lyla R.: See—
Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Lyla R.; and Strohecker, Cary A., Sr., 5,588,051, Cl. 379-243.000.
- MEC International Corporation: See—
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554.000.
- Mechtronics Corporation: See—
Squitteri, Anthony C., 5,586,666, Cl. 211-175.000.
- Media Solutions, Inc.: See—
Mitchell, Chauncey T., Jr., 5,587,214, Cl. 428-40.100.
- Medical College of Ohio: See—
Morgan, Alan R.; and Selman, Steven H., 5,587,394, Cl. 514-185.000.
- Medtronic, Inc.: See—
Shoberg, Bret R.; and Heruth, Kenneth T., 5,586,629, Cl. 141-21.000.
- Medvedik, Douglas E.: See—
Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., 5,586,782, Cl. 280-730.200.
- Meetz, Michael C.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.
- Mehlos, Michael D. Direct mounted fan apparatus, 5,586,867, Cl. 417-45.000.
- Mehner, David W.; Forneck, Kevin; Prince, Steven; and Major, Michael D., to Kraft Foods, Inc. Methods and compositions to add flavor to food products containing lipid, 5,587,196, Cl. 426-611.000.
- Mehra, Madhav; and Manico, Joseph A., to Eastman Kodak Company. Film cartridge with visual indicator for verifying film loading in camera, 5,587,756, Cl. 396-515.000.
- Mehta, Sunil: See—
Lin, Jonathan; Peng, Jack Z.; Barsan, Radu; and Mehta, Sunil, 5,587,945, Cl. 365-185.100.
- Mei-Chi-Na Beauty International, Inc.: See—
Chou, Kuei C., 5,586,473, Cl. 81-9.220.
- Meltzer, Aaron D.; and Karbach, Alexander, to Bayer Corporation; and Bayer Aktiengesellschaft. Polyethersulfone/polyester block copolymers and a process for their preparation, 5,587,435, Cl. 525-437.000.
- Memorial Sloan-Kettering Cancer Center: See—
Rettig, Wolfgang J.; Scanlan, Matthew J.; Garin-Chesa, Pilar; and Old, Lloyd J., 5,587,299, Cl. 435-69.100.
- Menashe, Julian. Interactive, computerized gaming system with remote terminals, 5,586,937, Cl. 463-41.000.
- Mendes-Viegas, Maria-Fatima: See—
Vieil, Eric; Bidan, Gérard; Gadelle, Andrée; and Mendes-Viegas, Maria-Fatima, 5,587,466, Cl. 536-4.100.

- Mendoza, Leopoldo G.: *See—*
Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stebnitz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.
- Meng, Ching-Ming: Structure heat sink for power semiconductors, 5,587,608, Cl. 257-712.000.
- Menicon Co., Ltd.: *See—*
Mochizuki, Shigeo; Matsumoto, Masahiro; Yamazaki, Toshio; and Ichinoh, Shoji, 5,587,445, Cl. 526-271.000.
- Meraldi, Jean-Paul; Cizek, Vlastimil; and Huston, Rima, to Michelin Recherche Et Techni UE S.A.: Composition having a base of cellulose formate capable of producing fibers or films, 5,587,238, Cl. 428-357.000.
- Mercedes-Benz AG: *See—*
Steiner, Manfred, 5,586,814, Cl. 303-116.200.
- Merchant, Paul P.: *See—*
Ruby, Richard C.; and Merchant, Paul P., 5,587,620, Cl. 310-346.000.
- Merck Patent GmbH: *See—*
Sawyer, Roy T., 5,587,360, Cl. 514-21.000.
- Mereer, Charles L.; and Philipps, Thomas E., to Isord, Inc.: Syntactic foam core material and method of manufacture, 5,587,231, Cl. 428-283.000.
- Meroth, John: Method of making synthetic diamond film with reduced bowing, 5,587,124, Cl. 264-430.000.
- Merser, F. Gerard, to Avery Dennison Corp.: Plastic fastener for shoe-lasting applications, 5,586,353, Cl. 12-142.0LC.
- Mery, Jean-Claude, to AlliedSignal Europe Services Techniques: Reduced-bulk brake motor, 5,586,623, Cl. 188-72.600.
- Messaros, David W.: *See—*
Dickinson, Ian J.; Eichberger, Horst; Messaros, David W.; and Walter, Hans-Dieter, 5,588,109, Cl. 395-326.000.
- Meta Motoren-und Energie-Technik GmbH: *See—*
Kreuter, Peter, 5,586,527, Cl. 123-90.150.
- Metaullics Systems Co., L.P.: *See—*
Gilbert, Ronald E.; Mordue, George S.; and Vild, Chris T., 5,586,863, Cl. 415-200.000.
- Metz, Donald, and Alexander, James C., to United Dominion Industries, Inc.: Safety device for a vertically stored dock leveler, 5,586,355, Cl. 14-69.500.
- Metzger, Donald L.: *See—*
Foster, George H., Jr., deceased; and Metzger, Donald L., 5,586,914, Cl. 439-676.000.
- Metzler, David M. A.; and Mauk, Albert L., to Metzler, David M. A.: Highly conductive liquid media electrocoagulation, 5,587,057, Cl. 204-228.000.
- Meuschke, Robert E.: *See—*
Bevilacqua, Bruce W.; Malandra, Louis J.; Meuschke, Robert E.; and Harkness, Alex W., 5,588,031, Cl. 376-287.000.
- Meux, Dominique: *See—*
Chabbert, Philippe; Chatenay, Alain; and Meux, Dominique, 5,587,660, Cl. 324-426.000.
- Meyer, Robert W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F., to Motorola, Inc.: Cellular speakerphone and method of operation thereof, 5,588,041, Cl. 379-59.000.
- Meyer, Robert D.: Soil sampling device with latch assembly having a variable circumferential shape, 5,587,540, Cl. 73-864.440.
- Meyer, Thomas G.: *See—*
Nardone, Vincent C.; Thompson, Mark S.; and Meyer, Thomas G., 5,586,471, Cl. 74-572.000.
- Micale, Antonio C., to Boeing Company, The: Method of making airplane fuselage, 5,586,391, Cl. 29-897.200.
- Michaels, John M.: *See—*
Shwe, Than; and Michaels, John M., 5,587,525, Cl. 73-15.520.
- Michelin Recherche Et Techni UE S.A.: *See—*
Meraldi, Jean-Paul; Cizek, Vlastimil; and Huston, Rima, 5,587,238, Cl. 428-357.000.
- Michaels, William E.: Fence vegetation barrier, 5,586,753, Cl. 256-32.000.
- Mick, Phillip J.: Metal wood golf club head, 5,586,948, Cl. 473-332.000.
- Microchip Technology Incorporated: *See—*
Yach, Randy L.; and Huff, Richard L., 5,587,866, Cl. 361-90.000.
- Micrografix, Inc.: *See—*
Kumar, Pramatheesh; Grabiak, Matthias; and Ivanek, Ivan, 5,588,108, Cl. 395-348.000.
- Micron Technology, Inc.: *See—*
Wright, Jeffrey P.; and Zheng, Hua, 5,587,961, Cl. 365-233.000.
- Zagar, Paul; and Manning, Troy, 5,587,671, Cl. 326-83.000.
- Micronics Computers Inc.: *See—*
Yin, Ji-Zhong, 5,586,865, Cl. 415-213.100.
- Microsoft Corporation: *See—*
Dennis, Stephen V.; and Newell, Gabe L., 5,588,095, Cl. 395-116.000.
- Mogilevsky, Alex; and Marton, Kornel R., 5,588,099, Cl. 395-139.000.
- Neeman, Yuval; Cook, Peter; Miller, Arnold S.; and Raman, Balan, 5,588,147, Cl. 395-601.000.
- Parker, David C., 5,588,100, Cl. 395-142.000.
- Mielke, Manfred: *See—*
Kroner, Hubertus; Jahns, Ekkehard; and Mielke, Manfred, 5,587,404, Cl. 522-85.000.
- Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred, 5,587,107, Cl. 252-315.600.
- Mieloszynski, Jean-Luc: *See—*
Curci, Michele; Mieloszynski, Jean-Luc; and Paquer, Daniel, 5,587,499, Cl. 554-85.000.
- Mifune, Hiroyuki; Yamanouchi, Junichi; and Ishiguro, Shoji, to Fuji Photo Film Co., Ltd.: Silver halide emulsion and method of preparing the same, 5,587,279, Cl. 430-567.000.
- Migli, Carlo: *See—*
Ferrari, Franco; and Migli, Carlo, 5,586,364, Cl. 16-383.000.
- Mihara, Akio; and Hashimoto, Seiji, to Canon Kabushiki Kaisha: Color image sensor including plural light-receiving windows and color filters, 5,587,814, Cl. 358-512.000.
- Mikami, Kazuhiro: *See—*
Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masahiro; and Yamamoto, Yoshihisa, 5,586,954, Cl. 477-93.000.
- Mikohn Gaming Corporation: *See—*
Bennett, Michael J.; Nino, John E.; and Todoroff, Brian D., 5,586,936, Cl. 463-25.000.
- Miljanich, George P.: *See—*
Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P., 5,587,454, Cl. 530-324.000.
- Mille, Laurence: *See—*
Brendenbach, Diane; and Mille, Laurence, 5,586,694, Cl. 222-183.000.
- Miller, Alistair A.; Nobbs, Malcolm S.; Hyde, Richard M.; and Leach, Michael J., to Glaxo Wellcome Inc.: Certain 2,4-diamino-5-(2,3,5-tri-chlorophenyl)-6-substituted-pyrimidines which are pharmacologically active CNS compounds, 5,587,380, Cl. 514-275.000.
- Miller, Arnold S.: *See—*
Neeman, Yuval; Cook, Peter; Miller, Arnold S.; and Raman, Balan, 5,588,147, Cl. 395-601.000.
- Miller, Craig A., to Westinghouse Air Brake Company: Imbedded electrical connector, 5,586,668, Cl. 213-1.300.
- Miller, Donald E.: *See—*
Luce, David A.; and Miller, Donald E., 5,587,748, Cl. 351-208.000.
- Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard F., to Whitaker Corporation, The: Shielding data connector, 5,586,911, Cl. 439-607.000.
- Miller, Robert J.: *See—*
Ondrejko, Richard T.; Castiglione, Paul J.; and Miller, Robert J., 5,586,875, Cl. 418-3.000.
- Miller, William J.: *See—*
Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., 5,587,605, Cl. 257-666.000.
- Mimnagh, Winslow M.: *See—*
Kablau, Johannes G. F.; Mimnagh, Winslow M.; and Hoeven, Petrus C. J., 5,587,980, Cl. 369-54.000.
- Minagawa, Akihiro: *See—*
Shindo, Yasuhiro; Yamaguchi, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro; and Kitabatake, Syoichi, 5,587,320, Cl. 435-290.100.
- Minagawa, Kazuji: *See—*
Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, 5,586,539, Cl. 123-458.000.
- Minakata, Hiroshi: *See—*
Ono, Makoto; and Minakata, Hiroshi, 5,588,097, Cl. 395-137.000.
- Minato, Tetsuya; Yonehara, Toshimitsu; Teranishi, Junichi; Toyoda, Shohei; Bito, Toshiaki; and Takashima, Kazushige, to Matsushita Electric Industrial Co., Ltd.: Reactor with core gap spacers, 5,587,694, Cl. 336-65.000.
- Minck, John L., Jr.: *See—*
Plyley, Alan K.; Vidal, Claude A.; Minck, John L., Jr.; and Solyntjes, Alan J., 5,586,711, Cl. 227-176.100.
- Minick, Steven E.: *See—*
Lawless, Michael W.; Soheron, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J., 5,586,868, Cl. 417-53.000.
- Minicozzi, Alfonso, to International Minicut, Inc.: Indexable cutting insert for rotary cutting tools, 5,586,843, Cl. 407-42.000.
- MiniMed Inc.: *See—*
Halli, Edgardo C.; and Mastrototaro, John J., 5,586,553, Cl. 128-635.000.
- Mininni, Venzazio: *See—*
Bergamini, Giorgio; and Mininni, Venzazio, 5,586,575, Cl. 137-488.000.
- Minister of Natural Resources, Canadian Forest Service: *See—*
Wall, Ronald; Prasad, Raghubir; and Sela, Elaine, 5,587,158, Cl. 424-93.500.
- Minnesota Mining and Manufacturing: *See—*
Engen, Paul T., 5,587,448, Cl. 528-55.000.
- Leonard, William K.; Mohn, Stephen W.; Edman, Timothy J.; and Schiller, Phillip D., 5,587,184, Cl. 425-133.500.
- Minnesota Mining & Manufacturing Company: *See—*
Moren, Dean M.; and Owen, Ian R., 5,587,502, Cl. 556-420.000.
- Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,587,351, Cl. 503-227.000.
- Newman, Charles L., 5,586,563, Cl. 128-849.000.
- Schultz, John C., 5,588,071, Cl. 382-168.000.
- Wedell, Eric D.; and Strecker, Darlene N., 5,586,926, Cl. 451-59.000.
- Mino, Hiroshi: *See—*
Kato, Hirokazu; and Mino, Hiroshi, 5,587,546, Cl. 84-609.000.
- Mino, Norihisa: *See—*
Soga, Mamoru; Mino, Norihisa; Ogawa, Kazufumi; Mochizuki, Yusuke; and Shibata, Tsuneo, 5,587,209, Cl. 427-503.000.
- Minolta Camera Kabushiki Kaisha: *See—*
Ikegawa, Akihito; Antomo, Kouichi; Tsukamoto, Kazuki; and Yamashita, Michiya, 5,587,551, Cl. 118-661.000.

- Kamei, Nobuo; Ikenoue, Yoshikazu; and Yamamoto, Hideo, 5,587,801, Cl. 358-296.000.
- Kawamura, Motomi; Kishi, Masamichi; and Morikawa, Takeshi, 5,587,799, Cl. 358-296.000.
- Sato, Akira; and Hatano, Takuji, 5,587,815, Cl. 359-11.000.
- Minolta Co., Ltd.: *See—*
Johdai, Akiyoshi; Ohhata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu; and Hirano, Yoshihiro, 5,587,782, Cl. 355-309.000.
- Miyano, Masaaki; Kawasaki, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824.000.
- Sawada, Kenji; Sato, Masahiro; Sekino, Hitoshi; and Sakamoto, Masashi, 5,587,769, Cl. 355-200.000.
- Taniguchi, Kazuko; Ikegawa, Akihito; Uno, Koji; and Saito, Hitoshi, 5,587,775, Cl. 355-219.000.
- Mirocha, Joseph L.: *See—*
Hoppensteadt, Dale; and Mirocha, Joseph L., 5,587,874, Cl. 361-663.000.
- Misner, Raymond H.: *See—*
Chen, Kuo-Raid G.; Misner, Raymond H.; Windham, Elbert P.; and Richardson, Bernard D., 5,586,424, Cl. 53-138.200.
- Misukanis, Eugene D.; Long, John H.; Dean, Lawrence A.; and Kuligowski, Douglas J., to Computer Network Technology Corporation: Transparent extension of peripheral from host, 5,588,140, Cl. 395-500.000.
- Mita Industrial Co., Ltd.: *See—*
Nakamatsu, Yasuhiro; Otsuka, Masao; Hatanaka, Fumio; and Tsunoda, Akihiro, 5,586,757, Cl. 271-145.000.
- Mitani, Hidenaga; and Morimoto, Hiroshi, to NSK Ltd.: Out-of-circuit ball preventing structure for ball screw nut, 5,586,469, Cl. 74-459.000.
- Mitchell, Chauncey T., Jr., to Media Solutions, Inc.: Laminated thermal transfer printable labels, 5,587,214, Cl. 428-40.100.
- Mitchell, Kim; and Mitchnick, Mark, to SunSmart, Inc.: Visibly transparent UV sunblock agents and methods of making same, 5,587,148, Cl. 424-59.000.
- Mitchnick, Mark: *See—*
Mitchell, Kim; and Mitchnick, Mark, 5,587,148, Cl. 424-59.000.
- Mitel Corporation: *See—*
Comeau, Alain, 5,587,325, Cl. 437-10.000.
- Mitsubishi Chemical Corporation: *See—*
Ue, Makoto; Sato, Tomohiro; and Takeda, Masayuki, 5,587,871, Cl. 361-504.000.
- Mitsubishi Denki Kabushiki Kaisha: *See—*
Aoki, Hideji; Tashima, Takahiro; Nakashima, Suekazu; Osaka, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164.000.
- Araki, Tohru, 5,587,653, Cl. 324-132.000.
- Endo, Kazuhito; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto, Manabu; and Hirai, Nobuaki, 5,587,978, Cl. 369-32.000.
- Fujimoto, Takanori, 5,586,534, Cl. 123-225.000.
- Fujishima, Kazuyasu; Matsuda, Yoshio; and Asakura, Mikio, 5,588,130, Cl. 395-445.000.
- Fujiwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei; and Itou, Shigehiro, 5,587,989, Cl. 369-178.000.
- Hongo, Katsunobu, 5,588,124, Cl. 395-287.000.
- Hori, Satoshi; Omeri, Teruyou; and Sakagami, Makoto, 5,587,930, Cl. 364-551.010.
- Inoue, Tohru; Onishi, Ken; Inoue, Sadaaki; and Okuma, Ikuro, 5,587,803, Cl. 386-33.000.
- Jimbo, Shinichi; and Mori, Shigeru, 5,587,648, Cl. 323-269.000.
- Kagawa, Shuichi; Chiba, Kazuhiro; Bamba, Noriko; and Okuno, Yoshiaki, 5,588,050, Cl. 382-167.000.
- Kajiura, Yasuya, 5,587,908, Cl. 364-426.041.
- Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin-ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kuno; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
- Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
- Sakai, Michio; Hosoya, Ryouzou; Orito, Nobuyuki; and Nakahata, Minoru, 5,587,873, Cl. 361-603.000.
- Sawada, Seiji; and Konishi, Yasuhiro, 5,587,950, Cl. 365-201.000.
- Tanida, Susumu, 5,587,956, Cl. 365-226.000.
- Tariya, Masaaki; and Koiwa, Mitsuru, 5,586,542, Cl. 123-609.000.
- Tsukude, Masaki, 5,587,959, Cl. 365-230.060.
- Yasuda, Kenichi; Furutani, Kiyohiro; and Miyamoto, Hiroshi, 5,587,607, Cl. 257-690.000.
- Mitsubishi Electric Engineering Co., Ltd.: *See—*
Aoki, Hideji; Tashima, Takahiro; Nakashima, Suekazu; Osaka, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164.000.
- Mitsubishi Gas Chemical Company, Inc.: *See—*
Abe, Mariko; Ehata, Shuji; Abe, Takafumi; and Higuchi, Hirofumi, 5,587,349, Cl. 502-236.000.
- Abe, Takafumi; Nishikawa, Mitsuhiko; and Naitoh, Susumu, 5,587,453, Cl. 528-488.000.
- Harada, Masahiro; and Inaba, Yasuo, 5,587,447, Cl. 528-347.000.
- Machida, Hiroshi, 5,587,508, Cl. 560-77.000.
- Mizukami, Masamichi; Yui, Tomoyuki; Arai, Yoshihisa; and Gocho, Yoshihiro, 5,587,106, Cl. 252-299.610.
- Mitsubishi Jidosha Kogyo Kabushiki Kaisha: *See—*
Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhisa; and Kasai, Satoshi, 5,587,909, Cl. 364-431.080.
- Mitsubishi Jukogyo Kabushiki Kaisha: *See—*
Kawahara, Yoshitaka; Kudo, Kazunori; Nakatani, Yoshihide; and Takagawa, Hiroyuki, 5,586,523, Cl. 123-65.0VB.
- Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyairi, Yoshio; Hattori, Toshio; and Hagiwara, Haruo, 5,586,456, Cl. 68-18.00R.
- Mitsubishi Materials Corporation: *See—*
Arai, Tatsuo; and Saito, Takayoshi, 5,586,845, Cl. 407-113.000.
- Kurasawa, Koichi; Harada, Mikio; and Ito, Takaaki, 5,587,867, Cl. 361-118.000.
- Nakayama, Ryoji; Takeshita, Takuo; and Watanabe, Muneaki, 5,587,024, Cl. 148-101.000.
- Mitsuda, Shinjiro: *See—*
Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasu-haru; and Nagao, Masaya, 5,587,359, Cl. 514-12.000.
- Mitsui Mining Co., Ltd.: *See—*
Ikeyama, Nobuhide; and Iwanaga, Yutaka, 5,587,136, Cl. 423-239.100.
- Mitsui Toatsu Chemicals, Inc.: *See—*
Tsutsumi, Haruki; Ikemoto, Yoshiaki; Maehama, Mitsuhiro; Oyanagi, Toshiki; and Matsubara, Tsugio, 5,587,246, Cl. 428-511.000.
- Miura, Akira: *See—*
Wakamoto, Akiko; Takahashi, Osamu; Furuhashi, Keizo; and Miura, Akira, 5,587,303, Cl. 435-116.000.
- Miura, Makoto: *See—*
Togawa, Yoshiyuki; and Miura, Makoto, 5,587,062, Cl. 204-613.000.
- Miura, Yoshihiro; and Goto, Masami, to Bridgestone Metalpha Corporation: Take-up reel for metallic filaments, 5,586,733, Cl. 242-125.200.
- Miwa, Makoto: *See—*
Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, 5,586,539, Cl. 123-458.000.
- Miya, Takashi: *See—*
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Miyairi, Yoshio: *See—*
Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyairi, Yoshio; Hattori, Toshio; and Hagiwara, Haruo, 5,586,456, Cl. 68-18.00R.
- Miyaji, Takashi; Nishikawa, Yoshikazu; Andou, Yukinori; Yamanaka, Toshio; and Kadowaki, Hideaki, to Sharp Kabushiki Kaisha: Developing unit having interlocking mechanism, 5,587,777, Cl. 355-245.000.
- Miyake, Akira: *See—*
Umebayashi, Nobuhiro; Mizushima, Kunio; Miyake, Akira; and Miyata, Teruhisa, 5,587,860, Cl. 360-133.000.
- Miyamoto, Hiroshi: *See—*
Yasuda, Kenichi; Furutani, Kiyohiro; and Miyamoto, Hiroshi, 5,587,607, Cl. 257-690.000.
- Miyamoto, Kazuhiro: *See—*
Nakai, Toshiki; Amano, Mitsuyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki; and Sato, Masuhiro, 5,587,547, Cl. 84-645.000.
- Miyamoto, Takao; and Tajima, Hisao, to Canon Kabushiki Kaisha: Liquid crystal panel unit having liquid crystal panel affixed to panel fixing using adhesive and height-regulating pins, 5,587,817, Cl. 349-187.000.
- Miyano, Hitoshi; and Yamamoto, Chikara, to Fuji Photo Optical Co., Ltd.: Objective lens system for endoscope, 5,587,839, Cl. 359-660.000.
- Miyano, Masaaki; Kawasaki, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, to Minolta Co., Ltd.: Lens moving apparatus, 5,587,846, Cl. 359-824.000.
- Miyata, Teruhisa: *See—*
Umebayashi, Nobuhiro; Mizushima, Kunio; Miyake, Akira; and Miyata, Teruhisa, 5,587,860, Cl. 360-133.000.
- Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, to Sumitomo Chemical Company, Limited: Method of forming a functional film, 5,587,260, Cl. 430-7.000.
- Miyazaki, Yuki, to Canon Kabushiki Kaisha: Image processing method and apparatus, 5,587,800, Cl. 358-296.000.
- Miyazawa, Masayuki: *See—*
Miyano, Masaaki; Kawasaki, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824.000.
- Mizrahi, Jacques: *See—*
Salimbeni, Aldo; Paleari, Fabio; Mizrahi, Jacques; and Scolastico, Carlo, 5,587,390, Cl. 514-341.000.
- Mizukami, Hiroshi; Uenohara, Norihisa; and Takeuchi, Hiroshi, to Kabushiki Kaisha Daikin Seisakusho: Clutch cover assembly, 5,586,633, Cl. 192-70.250.
- Mizukami, Masamichi; Yui, Tomoyuki; Arai, Yoshihisa; and Gocho, Yoshihiro, to Mitsubishi Gas Chemical Company, Inc.: Liquid crystal display devices and liquid crystal substances therefor, 5,587,106, Cl. 252-299.610.
- Mizukami, Tamio: *See—*
Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324.000.
- Mizuno, Koji: *See—*
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554.000.
- Mizuno, Shingo, to Fujitsu Limited: Method of radio-line relief and radio equipment in SDH network, 5,587,996, Cl. 370-228.000.
- Mizushima, Kunio: *See—*
Umebayashi, Nobuhiro; Mizushima, Kunio; Miyake, Akira; and Miyata, Teruhisa, 5,587,860, Cl. 360-133.000.

- Mizutani, Hideo; Kobayashi, Naoyuki; and Magome, Nobutaka, to Nikon Corporation. Surface position detection apparatus. 5,587,794, Cl. 356-375,000.
- Mizutani, Mikio. *See—*
Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Keiichi. 5,587,798, Cl. 358-261,000.
- MJM Technologies. *See—*
Kazemzadeh, Masoud. 5,587,193, Cl. 426-448,000.
- Mobil Oil Corporation. *See—*
Roy, Timothy A.; Mackerer, Carl R.; and Goldstein, Lawrence. 5,587,324, Cl. 436-183,000.
- Mochida Pharmaceutical Co., Ltd. *See—*
Murakami, Kimihito; Ohnishi, Shuhei; Yano, Takashi; and Itoh, Manabu. 5,587,392, Cl. 514-359,000.
- Mochizuki, Shigeo; Matsumoto, Masahiro; Yamazaki, Toshio; and Ichinohe, Shoji, to Memcon Co., Ltd. Highly oxygen-permeable heat-resistant material. 5,587,445, Cl. 526-271,000.
- Mochizuki, Yusuke. *See—*
Soga, Manoru; Mino, Norihisa; Ogawa, Kazufumi; Mochizuki, Yusuke; and Shibata, Tsuneo. 5,587,209, Cl. 427-503,000.
- Moczygemba, George A.; Knight, Nancy R.; Trepka, William J.; and Stacy, Nathan E., to Phillips Petroleum Company. Blends of copolymers of monovinylarenes and conjugated dienes containing two interior tapered blocks. 5,587,425, Cl. 525-98,000.
- Modi, Tarak D. *See—*
Sessler, Jonathan L.; Modi, Tarak D.; Hemmi, Gregory W.; Král, Vladimir A.; and Magda, Darren. 5,587,371, Cl. 514-185,000.
- Moeller Manufacturing Co., Inc. *See—*
Bynum, Kurt K. 5,586,790, Cl. 285-89,000.
- Moffat, Guy, to Sun Microsystems, Inc. Method and apparatus for increasing the speed of operation of a double buffered display system. 5,587,726, Cl. 345-201,000.
- Mogi, Fumio, to Fuji Photo Film Co., Ltd. Defoaming device and method for aeration. 5,587,004, Cl. 95-157,000.
- Mogilevsky, Alex; and Marton, Kornel R., to Microsoft Corporation. Method and system for automatically resizing tables. 5,588,099, Cl. 395-139,000.
- Mohaci, Ferenc, to Fallon Luminous Products. Low pressure gas discharge lamps with low profile sealing cover plate. 5,587,622, Cl. 313-493,000.
- Mohn, Stephen W. *See—*
Leonard, William K.; Mohn, Stephen W.; Edman, Timothy J.; and Schiller, Phillip D. 5,587,184, Cl. 425-133,500.
- Mohitasham, Mehdi, to E. J. A. Engineering PLC. Safety switch assemblies. 5,587,569, Cl. 200-17,000.
- Mojden, Andrew E.; and Hoinacki, Richard P., to Fleetwood Systems, Inc. Discharge apparatus for article handling system. 5,586,638, Cl. 198-419,100.
- Mokadam, Anita R. *See—*
Krogh, James A.; Mokadam, Anita R.; and Smith, B. Brian. 5,587,498, Cl. 554-69,000.
- Molecular Imaging Corporation. *See—*
Jung, Pan S.; and Yaniv, Daphna R. 5,587,523, Cl. 73-105,000.
- Molex Incorporated. *See—*
Marshall, Robert C.; and Pansari, Frank, Jr. 5,586,905, Cl. 439-463,000.
- Moli Energy (1990) Limited. *See—*
Wilson, Alfred M.; and Dahm, Jeffery R. 5,587,256, Cl. 429-218,000.
- Molin, Göran. *See—*
Bengmark, Stig; Ahméd, Siv; Molin, Göran; and Jeppson, Bengt. 5,587,314, Cl. 435-252,000.
- Mollet, Samuel R., to Harmon Industries, Inc. Cab signal sensor with noise suppression. 5,586,736, Cl. 246-194,000.
- Momono, Tatsunobu. *See—*
Unno, Tetsuo; Shoda, Yoshio; and Momono, Tatsunobu. 5,586,827, Cl. 384-450,000.
- Mondet, Jean. *See—*
Lion, Bertrand; Mondet, Jean; and Dupuis, Christine. 5,587,145, Cl. 424-45,000.
- Mononen, Tarmo. *See—*
Ålander, Casper; and Mononen, Tarmo. 5,586,418, Cl. 52-450,000.
- Monsanto Company, The. *See—*
Allen, David R.; Jenkins, Scott; Klein, Loraine; Erickson, Robert; and Froen, Diane. 5,587,481, Cl. 546-146,000.
- Chupp, John P.; Hamper, Bruce C.; and Wettach, Richard H. 5,587,485, Cl. 548-377,100.
- Voelker, Scott C. 5,586,589, Cl. 141-349,000.
- Montell North America Inc. *See—*
Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E. 5,587,229, Cl. 428-224,000.
- Montgomery, Daniel P., to Fritz Industries, Inc. Composition for and method of pumping concrete. 5,587,012, Cl. 106-823,000.
- Montgomery, Gerald D.; and Norrish, Jay B., to WavePhone, Inc. Signal processors for transparent and simultaneous transmission and reception of a data signal in a video signal. 5,587,743, Cl. 348-473,000.
- Moon, Byung-Joon; Cho, Sung-il; and Shin, Ki-ho, to Samsung Electronics Co., Ltd. Reproduction error correction circuit for a video reproduction system & the method for operating it. 5,587,804, Cl. 386-2,000.
- Moon, Tracy L.; and Schlener, Lewis C. Safety chocks for boat trailers and the like. 5,586,621, Cl. 188-4,000.
- Moore, Christine M. *See—*
Lewis, Douglas E.; and Moore, Christine M. 5,587,323, Cl. 436-178,000.
- Moore, E. Frank, III. Fabric holder with complimentary clamping surfaces and method. 5,586,400, Cl. 38-102,200.
- Moore, Joanna T. *See—*
Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srikantha, Alagacone; and Riding, George A. 5,587,311, Cl. 435-240,200.
- Moore, Walter A. *See—*
Leininger, Daniel R.; and Moore, Walter A. 5,586,587, Cl. 141-196,000.
- Moravec, John V. *See—*
Hashimoto, Masashi; Frantz, Gene A.; Moravec, John V.; and Dolant, Jean-Pierre. 5,587,962, Cl. 365-230,000.
- Morbitzner, Leo. *See—*
Langstein, Gerhard; Krüger, Ralf; Prejko, Karl-Erwin; Eisele, Ulrich; and Morbitzner, Leo. 5,587,424, Cl. 525-63,000.
- Mordue, George S. *See—*
Gilbert, Ronald E.; Mordue, George S.; and Vild, Chris T. 5,586,863, Cl. 415-200,000.
- More, Georgina. *See—*
Thomas, George; and More, Georgina. 5,587,250, Cl. 429-3,000.
- Moren, Dean M.; and Owen, Ian R., to Minnesota Mining & Manufacturing Company. Hydroxy functional alkoxysilane and alkoxysilane functional polyurethane made therefrom. 5,587,502, Cl. 556-420,000.
- Moretto, Hans-Heinrich. *See—*
Pohmer, Klaus; Weber, Rainer; Dörzbach-Lange, Cornelia; Haida, Reinhard; and Moretto, Hans-Heinrich. 5,587,513, Cl. 564-84,000.
- Morgan, Alan R.; and Selman, Steven H., to University of Toledo, The; and Medical College of Ohio. Production and use of diels alder adducts of vinyl porphyrins, of metal complexes thereof, and of compositions containing such adducts and complexes. 5,587,394, Cl. 514-185,000.
- Morgan Crucible Company plc, The. *See—*
Murphy, Maurice W. 5,586,461, Cl. 72-137,000.
- Mori, Akira. *See—*
Yoshida, Koji; Yamazaki, Taku; and Mori, Akira. 5,587,094, Cl. 219-121,680.
- Mori, Hiroaki; and Ando, Ryo, to Fuji Xerox Co., Ltd. Image sampling and color shift correction system in multiple image forming apparatus. 5,587,771, Cl. 355-208,000.
- Mori, Hiroyuki. *See—*
Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu. 5,587,197, Cl. 426-658,000.
- Mori, Katsumi; Asaka, Tatsuya; Iwano, Hideaki; and Kondo, Takayuki, to Seiko Epson Corporation. Method of making surface emission type semiconductor laser. 5,587,335, Cl. 437-129,000.
- Mori, Shigeru. *See—*
Jimbo, Shinichi; and Mori, Shigeru. 5,587,648, Cl. 323-269,000.
- Mori, Yoshimi. *See—*
Yumiyama, Shigeru; Onodera, Ko; and Mori, Yoshimi. 5,587,619, Cl. 310-201,000.
- Morikawa, Takeshi. *See—*
Kawamura, Motomi; Kishi, Masamichi; and Morikawa, Takeshi. 5,587,799, Cl. 358-296,000.
- Morimoto, Hiroki. *See—*
Hirahara, Shinichi; and Morimoto, Hiroki. 5,586,797, Cl. 296-146,600.
- Morimoto, Hiroshi. *See—*
Mitani, Hidenaga; and Morimoto, Hiroshi. 5,586,469, Cl. 74-459,000.
- Morin, Daniel, to Texas Instruments Incorporated. Sensor for use with air bag inflator and method for making. 5,586,386, Cl. 29-622,000.
- Morishita, Kazuhiro. *See—*
Shinji, Yasuhisa; Morishita, Kazuhiro; and Takase, Hiraji. 5,586,916, Cl. 439-752,000.
- Morita, Kouzi. *See—*
Ochiai, Ryujio; Morita, Kouzi; and Yahagi, Kazuyuki. 5,587,155, Cl. 424-70,280.
- Morris, Gary J. Multiple alert smoke detector. 5,587,705, Cl. 340-628,000.
- Morris, John; and Stafford, Gary, to Orthopedic Technology, Inc. Articulating adjustable condylar pad for knee brace. 5,586,970, Cl. 602-26,000.
- Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., to Minnesota Mining and Manufacturing Company. Thermal transfer systems having vanadium oxide antistatic layers. 5,587,351, Cl. 503-227,000.
- Morrow, Steven R., to BCM Engineers, Inc. Bootstrapping process optimization for two phase vacuum extraction systems. 5,586,836, Cl. 405-128,000.
- Mort, Joseph. *See—*
Hsieh, Bing R.; Mort, Joseph; Machonkin, Mary A.; and Ewing, Joan R. 5,587,224, Cl. 428-195,000.
- Mortell, Kathleen H. *See—*
Kiessling, Laura L.; Manning, David D.; and Mortell, Kathleen H. 5,587,442, Cl. 526-238,200.
- Morton International, Inc. *See—*
Leininger, Daniel R.; and Moore, Walter A. 5,586,587, Cl. 141-196,000.
- Mortrud, Jon P., to Budget Lamp Reclaimers, Inc. Fluorescent lamp collection and separation method and apparatus. 5,586,730, Cl. 241-24,220.
- Mosquera, Rene, to ITT Corporation. IC card connector shield grounding. 5,586,893, Cl. 439-108,000.
- Moss, Bernard. *See—*
Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K. 5,587,455, Cl. 530-324,000.
- Motamedi, Mohammad R. *See—*
Choo, Chang Y.; Ran, Xiaomeng; Porter, Christine A.; and Motamedi, Mohammad R. 5,587,710, Cl. 341-107,000.
- Motomura, Shuji. *See—*
Furuta, Toshiyuki; Motomura, Shuji; Watanabe, Takahiro; and Stork, David G. 5,588,090, Cl. 395-23,000.
- Motorola. *See—*
Shen, Jun; and Goronkin, Herbert. 5,587,944, Cl. 365-175,000.
- So, Franky; Shi, Song Q.; and Harvey, Thomas B., III. 5,587,589, Cl. 257-40,000.
- Motorola, Inc. *See—*
Altschuler, Barry N.; Hardy, Douglas A.; Stephens, James A.; and Kish, Joseph, III. 5,588,062, Cl. 380-30,000.
- Branner, Donald L.; Ray, Andrew E.; Peters, Scott M.; and Huber, Richard M. 5,587,706, Cl. 340-825,440.
- Chandos, Ronald V.; and Foster, Robert L. 5,588,059, Cl. 380-21,000.
- Garrett, Scott M. 5,587,649, Cl. 323-369,000.
- Landis, Michael R.; Yeates, Anthony J.; and Gavin, Thomas J. 5,588,148, Cl. 395-601,000.
- Lian, Ke K.; Li, Changming; Jung, Richard H.; and Kines, Joseph G. 5,587,872, Cl. 361-525,000.
- Lin, Jong-Kai; Lytle, William H.; and Subrahmanyam, Ravichandran. 5,587,342, Cl. 437-209,000.
- Meyer, George W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F. 5,588,041, Cl. 379-59,000.
- Olson, Timothy L.; Carney, Lauriam T.; Johnson, Gary C.; and Strom, William M. 5,587,883, Cl. 361-723,000.
- Ramsey, Kenneth C.; Miller, William J.; and Strom, William M. 5,587,605, Cl. 257-666,000.
- Thomas, George; and More, Georgina. 5,587,250, Cl. 429-3,000.
- Motomi, Yuji. *See—*
Kojima, Yuki; Motomi, Yuji; and Asaka, Junichi. 5,587,254, Cl. 429-206,000.
- Motoyama, Yuji. *See—*
Hirao, Yasunobu; Motoyama, Yuji; Nagasaka, Takashi; and Katsuyama, Hidekazu. 5,586,388, Cl. 29-830,000.
- Hirao, Yasunobu; Koyama, Makoto; and Motoyama, Yuji. 5,586,389, Cl. 29-841,000.
- Mrowec, Stanislaw. *See—*
Hashimoto, Koji; Babazaki, Hiroki; Mrowec, Stanislaw; and Danielewski, Marek. 5,587,028, Cl. 148-403,000.
- MTS Systems Corporation. *See—*
Smith, Stephen W. 5,587,680, Cl. 327-291,000.
- Mück, Karl-Friedrich. *See—*
Fleischer, Dietrich; Hoffmückel, Michael; Mück, Karl-Friedrich; and Sextro, Günter. 5,587,449, Cl. 528-232,000.
- Muckley, Ronald A. *See—*
McIver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A. 5,587,906, Cl. 364-424,045.
- Mueller, Lee G. *See—*
Schlosser, Charles E.; Mueller, Lee G.; and McDougal, Gregory. 5,586,439, Cl. 62-78,000.
- Muenzenmaier, Werner. *See—*
Benckert, Hartmut; and Muenzenmaier, Werner. 5,586,869, Cl. 417-218,000.
- Mühlhaus, Hans H. *See—*
Thomassen, Franz; and Mühlhaus, Hans H. 5,586,350, Cl. 5-636,000.
- Mulbrook, Mark M., to Rockwell International Corp. Differential automatic gain-control amplifier having an enhanced range. 5,587,688, Cl. 330-253,000.
- Mulcahey, Charles E. *See—*
Porter, Michael R.; Mulcahey, Charles E.; and Kirby, John J. 5,586,511, Cl. 112-2,100.
- Mulcahey, Leo T. *See—*
Streisel, Robert C.; Hank, Mark A.; Mulcahey, Leo T.; and Peterson, Ralph S. 5,587,048, Cl. 162-7,000.
- Mulcahey, Thomas M. *See—*
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahey, Thomas M.; and Cal, Yigang. 5,586,504, Cl. 104-282,000.
- Mullen, George P. Building handrail bracket. 5,586,423, Cl. 52-653,200.
- Muller, Frank. *See—*
Beerends, John G.; Muller, Frank; and van Ravesteijn, Robertus L. A. 5,588,089, Cl. 395-2,140.
- Muller, Marcel W. *See—*
Indeck, Ronald S.; and Muller, Marcel W. 5,587,654, Cl. 324-225,000.
- Müller, Stefan. *See—*
Knühl, Klaus; Karl, Ulrich; Müller, Stefan; and de Potzelli, Bernd. 5,587,506, Cl. 560-12,000.
- Müller-Broll, Gerhard. *See—*
Stief, Reinhard; and Müller-Broll, Gerhard. 5,587,564, Cl. 181-295,000.
- Münzenberger, Herbert. *See—*
Gantner, Gebhard; Dengge, Franz; Ofner, Peter; and Münzenberger, Herbert. 5,586,739, Cl. 248-74,100.
- Murai, Toshiaki. *See—*
Sessler, Jonathan L.; Hemmi, Gregory W.; and Murai, Toshiaki. 5,587,463, Cl. 534-15,000.
- Murakami, Katsuya. *See—*
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heiji. 5,587,040, Cl. 204-554,000.

- Murakami, Kimihito; Ohnishi, Shuhei; Yano, Takashi; and Itoh, Manabu, to Mochida Pharmaceutical Co., Ltd. Aryl methyl phenyl derivatives having aromatase inhibitory activity. 5,587,392, Cl. 514-359,000.
- Murakami, Masanori; Koide, Yasuo; Teraguchi, Nobuaki; and Tomomura, Yoshitaka, to Sharp Kabushiki Kaisha. II-VI group compound semiconductor device metallic nitride ohmic contact for p-type. 5,587,609, Cl. 257-744,000.
- Murakami, Tatsushi; and Ichida, Akito, to Daicel Chemical Industries, Ltd. Separating agent for optical isomers and process for producing the same. 5,587,467, Cl. 536-18,500.
- Murakami, Toshiyuki, to Kabushiki Kaisha Muraharu Sersakusho; Ninkura Scales Co., Ltd.; and Kabushiki Kaisha Yakult Honsha. Storage device for umbrella sacks. 5,586,683, Cl. 221-33,000.
- Muramatsu, Masaru. *See—*
Kusaka, Yosuke; Muramatsu, Masaru; Utagawa, Ken; and Yamano, Shozo. 5,587,761, Cl. 396-95,000.
- Murashita, Kimitaka. *See—*
Chiba, Hiroaki; Murashita, Kimitaka; and Noda, Tsugio. 5,588,075, Cl. 382-239,000.
- Murata Manufacturing Co., Ltd. *See—*
Azumi, Takeshi; Yamaoka, Osamu; and Kubota, Kazuyuki. 5,587,869, Cl. 361-301,300.
- Fujino, Masaru; and Takagi, Hiroshi. 5,587,015, Cl. 117-200,000.
- Yoshida, Kazuhiro. 5,587,328, Cl. 437-40,000.
- Murata, Yasumoto, to Sharp Kabushiki Kaisha. Recording/reproducing apparatus having means to detect the exchange of an external memory. 5,587,977, Cl. 369-25,000.
- Murata, Yasumoto; Ikeuchi, Michio; Yoshikawa, Shuichi; and Watanabe, Masahiko, to Sharp Kabushiki Kaisha. DTMF signal judging apparatus. 5,588,052, Cl. 379-283,000.
- Murayama, Kojiro. *See—*
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heiji. 5,587,060, Cl. 204-554,000.
- Murphy, Maurice W., to Morgan Crucible Company plc, The. Methods and apparatus for manufacturing helical products. 5,586,461, Cl. 72-137,000.
- Murray, Andrew. *See—*
Hunt, Mark A.; and Murray, Andrew. 5,588,021, Cl. 375-211,000.
- Murray, Bruce S.; Noble, Howard C.; and Quinn, Wilma W., to Bolt Beranek and Newman Inc. Electromagnetic force generator. 5,587,615, Cl. 310-30,000.
- Murray, F. Scott. *See—*
Blecher, Leo; Longworth, Ralph C.; Murray, F. Scott; Jonas, Philip A.; and Biedarski, Michael. 5,586,437, Cl. 62-47,100.
- Murray, Jerome L. Temperature and flow control valve. 5,586,722, Cl. 236-93,000.
- Muta, Junji, to Sumitomo Wiring Systems, Ltd. Connector assembly with cooperating terminals and method for connecting same. 5,586,901, Cl. 439-342,000.
- Muyshondt, Jorge E.; Parker, Gary A.; and Wilkie, Bruce J., to International Business Machines Corporation. Computer including a Faraday cage on printed circuit board. 5,587,920, Cl. 364-489,000.
- Myers, Garry L. *See—*
Cherukuri, Subraman R.; Myers, Garry L.; Battisti, Gerald E.; and Futsz, Richard C. 5,587,172, Cl. 424-401,000.
- Nabeshima, Daiki; and Ozaki, Naoki, to Kabushiki Kaisha Toshiba. Recording medium, signal recording apparatus thereof, and signal reproducing apparatus thereof. 5,587,991, Cl. 369-275,300.
- Nachbauer, Armand E. Golf club cover holding device for attachment to a golf bag. 5,586,674, Cl. 206-315,400.
- Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhito; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, to Fujitsu Limited. Cleanerless electrographic imaging device. 5,587,774, Cl. 355-219,000.
- Nagamoto, Itsushi; Sumikawa, Noburo; Hirakawa, Tatsuya; and Nakanishi, Tatsuo, to Yamaha Corporation. Golf club head. 5,586,944, Cl. 473-248,000.
- Nagano, Toru. *See—*
Yagi, Sakai; Watanabe, Tamio; and Nagano, Toru. 5,586,917, Cl. 439-752,000.
- Nagao, Kenji; Sohma, Masaki; Ando, Shigeru; and Kobayakawa, Michihito, to Matsushita Electric Industrial Co., Ltd. Detecting apparatus for detecting a contour of a moving region in a dynamic image. 5,587,927, Cl. 364-514,000.
- Nagao, Masaya. *See—*
Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasuharu; and Nagao, Masaya. 5,587,359, Cl. 514-12,000.
- Nagaoka, Kenji. *See—*
Abe, Hiroomi; Nagaoka, Kenji; and Sanada, Takashi. 5,587,427, Cl. 525-145,000.
- Nagasaka, Takashi. *See—*
Hirao, Yasunobu; Motoyama, Yuji; Nagasaka, Takashi; and Katsuyama, Hidekazu. 5,586,388, Cl. 29-830,000.
- Nagashima, Tetsuya, to Hochiki Corporation. Light scattering type smoke detector having an improved zero-point level. 5,587,790, Cl. 356-338,000.
- Nagasima, Tosio. *See—*
Ueba, Hisaaki; Sunaga, Yosio; and Nagasima, Tosio. 5,587,239, Cl. 428-362,000.
- Nagata, Hiroyuki. *See—*
Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shinichi; and Kawata, Yasushi. 5,587,819, Cl. 349-106,000.

- Nagatomi, Takashi, to Fanuc Ltd. Tool damage prevention system. 5,587,915, Cl. 364-474.190.
- Nagatsuka, Osamu, to Canon Kabushiki Kaisha. Recording and/or reproducing apparatus having rotary transformer. 5,587,859, Cl. 360-108.000.
- Nagaura, Toshikazu, Yamashita, Zenjiro, Arikawa, Kazuhiko, and Ohta, Kenji, to Sharp Kabushiki Kaisha. Cartridge used for a disc-shaped recording medium. 5,587,994, Cl. 369-291.000.
- Nagel, Nicholas J.: See—
- Saindon, Stephen A.; Gierman, Peter J., Jr., and Nagel, Nicholas J., 5,587,032, Cl. 156-64.000.
- Nair, Hari A.: See—
- Dauderman, Shelley L.; McWilliams, Linda C.; Nair, Hari A.; and Staud, Gary G., 5,587,356, Cl. 510-320.000.
- Naito, Hiroki; Kume, Masahiro; Sugura, Hideyuki; Takayama, Toru; Itoh, Kunito; Ohta, Issei, and Shimizu, Hirokazu, to Matsushita Electric Industrial Co., Ltd. Semiconductor laser device fabrication method. 5,587,334, Cl. 437-129.000.
- Naitoh, Susumu: See—
- Abe, Takafumi; Nishikawa, Mitsuhiro; and Naitoh, Susumu, 5,587,453, Cl. 528-488.000.
- Nakada, Takashi; Kazami, Keiichi; and Kaneko, Kenji, to Kabushiki Kaisha B-AI. Musical toy with sound producing body. 5,587,545, Cl. 84-600.000.
- Nakada, Yasuo, to Tsudakoma Kogyo Kabushiki Kaisha. Support assembly for a planetary-type selvage unit on a loom. 5,586,582, Cl. 139-430.000.
- Nakade, Shinichi: See—
- Sakaki, Toshiaki; and Nakade, Shinichi, 5,587,411, Cl. 524-17.000.
- Nakadera, Kazuo; Okutani, Haruo; and Kurebayashi, Hideki, to Tomoe-gawa Paper Co., Ltd. Toner for developing static charge images and process for preparing the same. 5,587,265, Cl. 430-109.000.
- Nakagawa, Naoshi; Hatanaka, Tadashi; Hayashihara, Tatsuhiko; and Shiono, Manzo, to Kuraray Co., Ltd. 1-amino-2-cyclohexene derivative and production process therefor. 5,587,486, Cl. 548-448.000.
- Nakagawa, Yutaka: See—
- Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Nakahata, Akimasa: See—
- Yukawa, Yoshiyuki; Yabuta, Motohiro; Nakahata, Akimasa; and Sugimura, Yoh, 5,587,426, Cl. 525-124.000.
- Nakahata, Minoru: See—
- Sakai, Michio; Hosoya, Ryonzo; Orito, Nobuyuki, and Nakahata, Minoru, 5,587,873, Cl. 361-603.000.
- Nakai, Hiroto, to Kabushiki Kaisha Toshiba. Nonvolatile semiconductor memory with NAND structure memory arrays. 5,587,948, Cl. 365-185.170.
- Nakai, Sadao; Izawa, Yasukazu; Yamana, Masanobu; Ohmi, Masato; Akatsuka, Masamori; Yamana, Chiyoe; and Yonezawa, Yoshiyuki, to Nakai, Sadao; Institute for Laser Technology; and Fuji Electric Co., Ltd. Breifingence distribution measuring method. 5,587,793, Cl. 356-367.000.
- Nakai, Toshiaki; Anzono, Mitsuyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki, and Sato, Masahiro, to Pioneer Electronic Corporation. Musical sound producing device with pitch change circuit for changing only pitch variable data of pitch variable/invariable data. 5,587,547, Cl. 84-645.000.
- Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kampo, to Kashima-Kita Electric Power Corporation. Method for producing high purity vanadium electrolytic solution. 5,587,132, Cl. 423-62.000.
- Nakajima, Yoshitatsu: See—
- Suzuki, Yoshio; and Nakajima, Yoshitatsu, 5,587,722, Cl. 345-94.000.
- Nakakuki, Toshio, to Sanyo Electric Co., Ltd. Image signal processor for obtaining digital image signals. 5,587,746, Cl. 348-708.000.
- Nakamatsu, Yasuhiro; Otsuka, Masao; Hatanaka, Fumio; and Tsunoda, Akihito, to Mira Industrial Co., Ltd. Paper regulating mechanism and paper cassette. 5,586,757, Cl. 271-145.000.
- Nakamura, Jop: See—
- Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Jop; Shiozaki, Shuzo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi, 5,587,378, Cl. 514-264.000.
- Nakamura, Kiyoshi: See—
- Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mitsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi, and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.
- Nakamura, Masahiko; Yamamoto, Hajime; and Terada, Hiroshi, to Matsushita Electric Industrial Co., Ltd. Color electrophotographic apparatus having an intermediate transfer belt variable in speed. 5,587,783, Cl. 355-326.000.
- Nakamura, Masao: See—
- Takeuchi, Kiyoshi; Takeda, Shin; and Nakamura, Masao, 5,586,462, Cl. 72-150.000.
- Nakamura, Masaru: See—
- Kato, Tetsuaki; Arita, Soichi; and Nakamura, Masaru, 5,587,638, Cl. 318-568.140.
- Nakamura, Toshiyuki; and Iida, Yoshikazu, to Nikon Corporation. Camera-shake correcting camera. 5,587,764, Cl. 396-55.000.
- Nakane, Shinsuke; Kanou, Kazuhiko; and Hashimoto, Takatsugu, to Bridge-stone Corporation. Rubber composition for tire tread. 5,587,417, Cl. 524-495.000.
- Nakanishi, Hiroko; and Ohnishi, Hiroshi, to Sharp Kabushiki Kaisha. Liquid crystal display device having a particular compensator. 5,587,821, Cl. 349-118.000.
- Nakanishi, Hiroto: See—
- Tomoka, Jun; Uetani, Yasunori; Nakanishi, Hiroto; Hanawa, Ryotaro; and Iida, Ayako, 5,587,492, Cl. 549-406.000.
- Nakanishi, Tatsuo: See—
- Nagamoto, Itsushi; Sumikawa, Noburo; Hirakawa, Tatsuya; and Nakanishi, Tatsuo, 5,586,944, Cl. 473-248.000.
- Nakanishi, Yasuyuki: See—
- Fujiwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei; and Ito, Shigehiro, 5,587,989, Cl. 369-178.000.
- Nakano, Tsuyoshi: See—
- Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, 5,587,260, Cl. 430-7.000.
- Nakao, Koh: See—
- Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203.000.
- Nakashima, Suekazu: See—
- Aoki, Hideki; Tashima, Takahiro; Nakashima, Suekazu; Osaka, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164.000.
- Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mitsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, to Hitachi, Ltd. Electric power converting apparatus. 5,587,891, Cl. 363-41.000.
- Nakata, Takashi, to Brother Kogyo Kabushiki Kaisha. Printer with printing hammer. 5,586,828, Cl. 400-185.000.
- Nakata, Tsuneo, to Fujitsu Limited. Method for generating test patterns for use with a scan circuit. 5,588,008, Cl. 371-27.000.
- Nakatani, Masayuki; Sengoku, Koji; and Fujita, Akifumi, to House Foods Corporation. Apparatus and method for sterilizing food. 5,587,194, Cl. 426-521.000.
- Nakatani, Takuya; Abe, Mitsuaki; Dono, Shigeru; and Urano, Youji, to Matsushita Electric Works, Ltd. Automated part assembly machine. 5,586,387, Cl. 29-703.000.
- Nakatani, Yoshhide: See—
- Kawahara, Yoshitaka; Kudo, Kazunori; Nakatani, Yoshhide; and Takagawa, Hiroyuki, 5,586,523, Cl. 123-65.0VB.
- Nakatsugawa, Haruyasu; Yoneyama, Masakazu; and Urabe, Shigeharu, to Fuji Photo Film Co., Ltd. Silver halide photographic material. 5,587,282, Cl. 430-637.000.
- Nakayama, Hideo: See—
- Onuma, Hiromi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, 5,588,016, Cl. 372-46.000.
- Nakayama, Ryoji; Takeshita, Takuo; and Watanabe, Muneaki, to Mitsubishi Materials Corporation. Solid resin-coated magnet powder and a method for producing an anisotropic bonded magnet therefrom. 5,587,024, Cl. 148-101.000.
- Nakisher, Robert G.; and Uditsky, Daniel. Gold-plated dental matrix band. 5,586,883, Cl. 433-39.000.
- Naldee Corporation: See—
- Shibata, Mineharu; and Takehara, Shin, 5,587,907, Cl. 364-424.046.
- Namiki, Koichi: See—
- Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhiro; and Kasai, Satoshi, 5,587,909, Cl. 364-431.080.
- NanoSystems L.L.C.: See—
- Wong, Sui-Ming, 5,587,143, Cl. 424-9.100.
- Nansen, David S.: See—
- Matsen, Marc R.; Pisel, Richard J.; Crow, Wesley B.; and Nansen, David S., 5,587,098, Cl. 219-615.000.
- Naraki, Akihiro: See—
- Enokida, Takashi; Naraki, Akihiro; Yamashita, Eiichi; and Iatsu, Haruyoshi, 5,587,413, Cl. 524-200.000.
- Narayanan, Chellappan: See—
- Greene, Benjamin L.; Narayanan, Chellappan; and Preshy, Herman M., 5,588,085, Cl. 385-123.000.
- Nardone, Vincent C.; Thompson, Mark S.; and Meyer, Thomas G., to United Technologies Corporation. Energy storage flywheel device. 5,586,471, Cl. 74-572.000.
- Narumi, Subhash R.: See—
- Chang, Kuang-Yeh; Narumi, Subhash R.; and Boardman, William J., 5,587,332, Cl. 437-43.000.
- Narr, Berthold; Hanel, Norbert; Van Meel, Jacques; Wiene, Wolfgang; Entzeroth, Michael; and Ries, Uwe; to Dr. Karl Thomae GmbH. Benzimidazoles, pharmaceutical compositions containing these compounds and processes for preparing them. 5,587,393, Cl. 514-381.000.
- Naruo, Masahiro, to Matsushita Electric Works, Ltd. Power source device. 5,587,894, Cl. 363-84.000.
- Narusawa, Toshiaki: See—
- Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhiro; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219.000.
- Nasuno, Ichiro: See—
- Shibata, Mitsuru; Sakamoto, Masashi; and Nasuno, Ichiro, 5,587,484, Cl. 548-364.400.
- National Laboratory for High Energy Physics: See—
- Sakai, Izumi, 5,587,632, Cl. 315-507.000.
- National Packaging Corporation: See—
- Lynd, L. Grant, 5,586,676, Cl. 220-212.000.
- National Science Council: See—
- Ma, Chen-Chi M., 5,587,034, Cl. 156-166.000.
- National Semiconductor Corporation: See—
- Bergemont, Albert; and Chi, Min-hwa, 5,587,949, Cl. 365-185.240.
- Chi, Min-Hwa; Bergemont, Albert; and Haggag, Hosam, 5,587,596, Cl. 257-223.000.

- Choo, Chang Y.; Ran, Xiaonong; Porter, Christine A.; and Motamedi, Mohammad R., 5,587,710, Cl. 341-107.000.
- National Starch and Chemical Investment Holding Corporation: See—
- Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrhala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- Natschke, Scott: See—
- Karjo, Wajih; Smith, Eric; Demouze, Thomas J.; Giromi, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7.000.
- Nazri, Gholam-Abbas: See—
- Tibbets, Gary G.; Nazri, Gholam-Abbas; and Howie, Blake J., 5,587,257, Cl. 429-218.000.
- Neal, Joseph H.: See—
- Vogley, Wilbur C.; Balistreri, Anthony M.; Gurtag, Karl M.; Krueger, Steven D.; Le, Duy-Luan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Nebuchitlov, Vladimir A.: See—
- Gordetsky, Victor V.; Nebuchitlov, Vladimir A.; and Kolotyryn, Y. M., 5,587,058, Cl. 204-290.000.
- NEC Corporation: See—
- Endo, Koji, 5,587,999, Cl. 370-352.000.
- Furie, Koji, 5,587,019, Cl. 118-725.000.
- Habata, Shinichi, 5,588,106, Cl. 395-340.000.
- Hagihara, Yohito; and Hongu, Takahiro, 5,587,808, Cl. 358-462.000.
- Iida, Kazuhiro, 5,587,897, Cl. 364-148.000.
- Inami, Daijiro; and Sato, Yuichi, 5,587,667, Cl. 326-17.000.
- Ishikawa, Hiraku, 5,587,344, Cl. 437-238.000.
- Matsubara, Yoshio, 5,587,590, Cl. 257-48.000.
- Ohkubo, Kazuko; and Yahagi, Masahiko, 5,588,039, Cl. 379-58.000.
- Sugiyama, Mitsuhiro, 5,587,612, Cl. 257-506.000.
- Takano, Hideto, 5,588,024, Cl. 375-242.000.
- Takemura, Hisashi, 5,587,326, Cl. 437-31.000.
- Tanabe, Takashi; and Yamamoto, Kouji, 5,588,079, Cl. 385-78.000.
- Watanabe, Masayuki, 5,587,610, Cl. 257-758.000.
- Nedwin, Glenn E.; Bringham, Timothy S.; and Couraud, Pierre-Oliver, to Incyte Pharmaceutical Corporation. 14-beta-gal mammalian lectins. 5,587,460, Cl. 530-396.000.
- Neeman, Yuval; Cook, Peter; Miller, Arnold S.; and Raman, Balan, to Microsoft Corporation. Replication facility. 5,588,147, Cl. 395-601.000.
- Netteodach, Ltd.: See—
- Vagin, Vladimir P., 5,586,602, Cl. 166-249.000.
- Negi, Shigeto; Yamana, Mototsuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, to Eisai Co., Ltd. 7-acyl-3-(substituted carbamoyloxy) cephen compounds and process for their preparation. 5,587,473, Cl. 540-222.000.
- Negrin, Dan, to Kelsey-Hayes Company. Method and system for detecting false four-wheel drive indication in antilock brake systems. 5,586,815, Cl. 303-143.000.
- Nelson, Arthur J.; and Gross, Clifford M., to BCAM International, Inc. Functional ambulation performance scoring device. 5,586,557, Cl. 128-779.000.
- Nelson, Chris; Hennessy, David R.; and LeClaire, James P., to Horton, Inc. Rotational control apparatus. 5,586,635, Cl. 192-85.00A.
- Nelson Metal Products Corporation: See—
- Shimmell, Dennis S., 5,586,380, Cl. 29-413.000.
- Nelson, Richard L. Locking attachment. 5,586,368, Cl. 24-390.000.
- Neltner, Stephen L.: See—
- Lafay, Victor S.; and Neltner, Stephen L., 5,587,008, Cl. 106-38.510.
- Nemoto, Hiroaki: See—
- Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Keiichi, 5,587,798, Cl. 358-261.100.
- NeoMagg Corp.: See—
- Ranganathan, Ravi; and Puar, Deepraj S., 5,587,672, Cl. 326-93.000.
- Neubrand, Horst; Korec, Jacek; Stein, Erhart; and Silber, Dieter, to Daimler-Benz Aktiengesellschaft. Lateral field-effect-controlled semiconductor device on insulating substrate. 5,587,595, Cl. 257-141.000.
- Neunhaer, Anton; and Domer, Hans-Christian, to Hilti Aktiengesellschaft. Manually operated chipping tool. 5,586,607, Cl. 173-117.000.
- Neuner, Andreas: See—
- Schauer, Friedrich; and Neuner, Andreas, 5,586,381, Cl. 29-434.000.
- Neures Corporation: See—
- Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P., 5,587,454, Cl. 530-324.000.
- Neville, Daniel E., to 800 Adept, Inc. Geographically mapped telephone routing method and system. 5,588,048, Cl. 379-127.000.
- New York University: See—
- Javitt, Norman B., 5,587,368, Cl. 514-177.000.
- Newell, Gabe L.: See—
- Dennis, Stephen V.; and Newell, Gabe L., 5,588,095, Cl. 395-116.000.
- Newell, Gerald P.: See—
- Dowell, Teresa J.; Newell, Gerald P.; and Zeffren, Eugene, 5,587,154, Cl. 424-70.110.
- Newman, Charles L., to Minnesota Mining and Manufacturing Company. Method for making a surgical drape. 5,586,563, Cl. 128-849.000.
- Newman, Lawrence E., to Globe Products Inc. Stator manufacturing method and apparatus. 5,586,384, Cl. 29-596.000.
- Newman, Nancy M. Invisible bandage assembly. 5,586,971, Cl. 602-58.000.
- Newport News Shipbuilding and Dry Dock Company: See—
- Sawyer, David R.; and Wheeler, Douglas M., 5,586,801, Cl. 294-1.100.
- Nezu, Shoichi: See—
- Kubo, Kohji; Nezu, Shoichi; Ishibashi, Fumio; Harada, Hiroyuki; and Shigematsu, Yuji, 5,587,247, Cl. 428-523.000.
- Nezu, Takashi; and Kashiwagi, Akira, to Tokico, Ltd. Hydraulic shock absorber of damping force adjustable type. 5,586,627, Cl. 188-299.000.
- NGK Insulators, Ltd.: See—
- Tsuchimoto, Tomonori; Iwata, Katsuiichi; and Kurashima, Yoshihiko, 5,587,252, Cl. 429-49.000.
- N'Guyen, Quang L., to L'Oreal. Cosmetic of dermopharmaceutical composition containing, in combination, a lauroylmethionate of a basic amino acid and at least one polyphenol. 5,587,171, Cl. 424-401.000.
- N'Guyen, Quang L.: See—
- Junino, Alex; LaGrange, Alain; N'Guyen, Quang L.; and Bourboulon, Marie-Alix, 5,587,173, Cl. 424-401.000.
- Nguyen-Ba, Nghe: See—
- Belleau, Bernard; deceased; Nguyen-Ba, Nghe; Kong, Laval C. C.; Mansour, Tarek; Jin, Haolun; and Brasili, Livio, 5,587,480, Cl. 544-310.000.
- Nicholls, Howard C.: See—
- Wyborn, Graeme M.; and Nicholls, Howard C., 5,587,339, Cl. 437-195.000.
- Nickles, James A. Fishing rod storage apparatus and method. 5,586,515, Cl. 114-255.000.
- Nickles, Stephen K.: See—
- Seay, O. Elwyn; Nickles, Stephen K.; and Haley, John E., 5,586,669, Cl. 213-43.000.
- Nicodemus, Carl D., to Helios Research Corp. Thermal absorption compression cycle. 5,586,442, Cl. 62-107.000.
- Nielsen, Robert A.; and Pizzi, Vladimiro, to Graco Children's Products. Mobile portable playyard system. 5,586,345, Cl. 5-99.100.
- Nier, Richard E.: See—
- Dapp, Michael C.; Barker, Thomas N.; Dietlenderter, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- Nifco Inc.: See—
- Eguchi, Tomoo; and Asami, Goro, 5,586,372, Cl. 24-452.000.
- Nihei, Ryo: See—
- Watanabe, Atsushi; Nihei, Ryo; and Terada, Akihito, 5,587,635, Cl. 318-434.000.
- Nii, Hiroki: See—
- Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shunichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Niikura Scales Co., Ltd.: See—
- Murakami, Toshiyuki, 5,586,683, Cl. 221-33.000.
- Niimi, Hideki, to Wako Plastics Industries Co., Ltd. Molding device for register of synthetic resin. 5,587,189, Cl. 425-577.000.
- Niizaki, Nobuya: See—
- Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, 5,587,260, Cl. 430-7.000.
- Nijssen, Stephanus J. J.: See—
- Bergen, Franciscus H. M.; Rotte, Jan J.; Nijssen, Stephanus J. J.; and De With, Peter H. N., 5,587,802, Cl. 386-26.000.
- Nikon Corporation: See—
- Goto, Tetsuro, 5,587,765, Cl. 396-234.000.
- Hibino, Hideo; Yokonuma, Norikazu; Kazami, Kazuyuki; and Yamazaki, Youichi, 5,587,751, Cl. 396-319.000.
- Katayama, Akira; and Terunuma, Hiroshi, 5,587,754, Cl. 396-144.000.
- Kawamura, Koichiro; and Uehara, Ryo, 5,587,766, Cl. 396-257.000.
- Kazami, Kazuyuki; and Wakabayashi, Tsutomu, 5,587,753, Cl. 396-397.000.
- Kusaka, Yosuke; and Utagawa, Ken, 5,587,579, Cl. 250-201.800.
- Kusaka, Yosuke; Muramatsu, Masaru; Utagawa, Ken; and Yamano, Shozo, 5,587,761, Cl. 396-95.000.
- Mizutani, Hideo; Kobayashi, Naoyuki; and Magome, Nobutaka, 5,587,794, Cl. 356-375.000.
- Nakamura, Toshiyuki; and Iida, Yoshikazu, 5,587,764, Cl. 396-55.000.
- Suzuki, Takeshi; and Sekine, Atsushi, 5,587,739, Cl. 348-347.000.
- Uchiyama, Shigeyuki, 5,587,763, Cl. 396-114.000.
- Watanabe, Toshiro, 5,587,762, Cl. 396-95.000.
- Nimura, Mitsuhiro: See—
- Asano, Hitoshi; Ishikawa, Wataru; and Nimura, Mitsuhiro, 5,587,911, Cl. 364-444.200.
- Nini, James P.: See—
- Borlinghaus, Hans J.; Nini, James P.; and Blake, Thomas B., 5,586,740, Cl. 248-157.000.
- Nino, John E.: See—
- Bennett, Michael J.; Nino, John E.; and Todoroff, Brian D., 5,586,936, Cl. 463-25.000.
- Nintendo Co., Ltd.: See—
- Otake, Masahiro; Takahashi, Toyofumi; Nishitani, Satoshi; and Otsuki, Takashi, 5,587,723, Cl. 345-118.000.
- Nippon Gasket Co., Ltd.: See—
- Kubouchi, Kenji; Fukui, Yuji; and Inoue, Kunio, 5,586,776, Cl. 277-235.000.
- Nippon Mektron, Limited: See—
- Enokida, Takashi; Naraki, Akihiro; Yamashita, Eiichi; and Tatsu, Haruyoshi, 5,587,413, Cl. 524-200.000.
- Nippon Mining Company, Ltd.: See—

- Wakamoto, Akiko; Takahashi, Osamu; Furuhashi, Keizo; and Miura, Akira, 5,587,303, Cl. 435-116.000.
 Nippon Oil Co.: *See*—
 Soda, Yoshio; Kohno, Takefumi; Shinagawa, Masaaki; and Kiuchi, Noriyuki, 5,587,203, Cl. 427-228.000.
 Nippon Paint Co., Ltd.: *See*—
 Akutsu, Kensuke, 5,587,868, Cl. 361-231.000.
 Kishida, Takahito; Matsumura, Akira; and Kawakami, Aitsushi, 5,587,274, Cl. 430-270.100.
 Yamoto, Shuhei; Ito, Koji; and Yamada, Mitsuo, 5,587,059, Cl. 204-505.000.
 Nippon Shokubai Co., Ltd.: *See*—
 Kanada, Kenta; and Kawamura, Kiyoshi, 5,587,410, Cl. 523-410.000.
 Nippondenso Co., Ltd.: *See*—
 Hirao, Yasunobu; Motoyama, Yuji; Nagasaka, Takashi; and Katsuyama, Hidekazu, 5,586,388, Cl. 29-830.000.
 Hirao, Yasunobu; Koyama, Makoto; and Motoyama, Yuji, 5,586,389, Cl. 29-841.000.
 Kano, Kazuhiko; Takeuchi, Yukihiko; Watanabe, Takamitsu; Ao, Ken-ichi; Kanoue, Masakazu; and Uenoyama, Hirofumi, 5,587,343, Cl. 437-228.000.
 Kawagoe, Tadashi; and Zyosuko, Keizo, 5,587,091, Cl. 219-110.000.
 Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, 5,586,539, Cl. 123-458.000.
 Nishi, Terry E., to Servi-Tech, Inc. Stabilizing of CAM in automated beverage filling machinery, 5,586,379, Cl. 29-401.100.
 Nishi, Satoru: *See*—
 Kurihara, Mikio; Nishi, Satoru; Onodera, Takahiro; and Kushima, Kazunari, 5,587,557, Cl. 174-266.000.
 Nishi, Shonosuke: *See*—
 Yamauchi, Hiroshige; and Nishi, Shonosuke, 5,586,732, Cl. 241-168.000.
 Nishida, Shoichi. Clasp mechanism, 5,586,374, Cl. 24-599.800.
 Nishikawa, Mitsuhiro: *See*—
 Abe, Takafumi; Nishikawa, Mitsuhiro; and Naitoh, Susumu, 5,587,453, Cl. 528-488.000.
 Nishikawa, Yoshikazu: *See*—
 Miyaji, Takashi; Nishikawa, Yoshikazu; Andou, Yukimori; Yamanaka, Toshio; and Kadowaki, Hideaki, 5,587,777, Cl. 355-245.000.
 Nishimura, Hiroshi: *See*—
 Imai, Tooru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12.020.
 Nishimura, Naoki, to Canon Kabushiki Kaisha. Magneto-optical recording medium having two magnetic layers with perpendicular magnetic anisotropy, and information recording method having the same, 5,587,974, Cl. 369-13.000.
 Nishimura, Nobuichi: *See*—
 Imai, Tooru; Nishimura, Hiroshi; Nishimura, Nobuichi; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12.020.
 Nishino, Hiroshi; and Fujii, Akiyoshi, to Sharp Kabushiki Kaisha. Method of manufacturing a thin film magnetic head, 5,586,385, Cl. 29-603.160.
 Nishio, Tadashi; and Fukuda, Shunichi, to Concrete Coring Company. Apparatus for digging soil foundation and method for constructing underground wall by using the apparatus, 5,586,840, Cl. 405-267.000.
 Nishitani, Satoshi: *See*—
 Otake, Masahiro; Takahashi, Toyofumi; Nishitani, Satoshi; and Otsuki, Takashi, 5,587,723, Cl. 345-118.000.
 Nishizawa, Seiji; Takahashi, Tokuji; and Hattori, Ryo. Apparatus and method for measuring thickness of thin semiconductor multi-layer film, 5,587,792, Cl. 355-356.000.
 Nissan Motor Co., Ltd.: *See*—
 Abo, Keiju, 5,586,953, Cl. 477-47.000.
 Sasaki, Ryo; and Ina, Toshiro, 5,587,418, Cl. 524-504.000.
 Nitschke, John S.; and Kuhary, Daniel B., to Vend-It Corporation. Automated deep fryer, 5,586,486, Cl. 99-330.000.
 Niwano, Kentaro: *See*—
 Watabe, Masahiro; Yanai, Noriyuki; Niwano, Kentaro; and Yamamoto, Akihiro, 5,587,776, Cl. 355-245.000.
 Niwano, Masahiro: *See*—
 Akiyoshi, Kazunori; and Niwano, Masahiro, 5,587,450, Cl. 528-310.000.
 Nixon, Austin D. Instantaneous gas water heater, 5,586,547, Cl. 126-351.000.
 Nobbs, Malcolm S.: *See*—
 Miller, Alistair A.; Nobbs, Malcolm S.; Hyde, Richard M.; and Leach, Michael J., 5,587,380, Cl. 514-275.000.
 Nobelpharma AB.: *See*—
 Andersson, Mats; and Törnquist, Anders, 5,587,912, Cl. 364-468.040.
 Noble, Howard C.: *See*—
 Murray, Bruce S.; Noble, Howard C.; and Quinn, Wilma W., 5,587,615, Cl. 310-30.000.
 Nohutoku, Yoshikazu: *See*—
 Kawamitsu, Toshiaki; Nobutoki, Yoshikazu; Hirano, Seiji; and Terayama, Koji, 5,588,002, Cl. 370-462.000.
 Noda, Tsugio: *See*—
 Chiba, Hiroaki; Murashita, Kimitaka; and Noda, Tsugio, 5,588,075, Cl. 382-239.000.
 Noguchi, Miyoko, to Canon Kabushiki Kaisha. Semiconductor device manufacturing method and projection exposure apparatus using the same, 5,587,834, Cl. 359-558.000.
 Noguchi, Osamu: *See*—
 Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Kenichi, 5,587,798, Cl. 358-261.100.
 Nolcheff, Nick A., to United Technologies Corporation. Flow aligned plenum endwall treatment for compressor blades, 5,586,859, Cl. 415-58.500.
 Noma, Nobuhiko: *See*—
 Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Kenichi, 5,587,798, Cl. 358-261.100.
 Nomura, Yutaka: *See*—
 Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kanji, 5,587,132, Cl. 423-62.000.
 Nonaka, Hiromi: *See*—
 Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi, 5,587,378, Cl. 514-264.000.
 Nonaka, Kimihiko; and Ohtani, Hiroaki, to Sanshin Kogyo Kabushiki Kaisha. Fuel injection control system for internal combustion engine, 5,586,524, Cl. 123-73.00A.
 Norand Corporation: *See*—
 Schultz, Darald R., 5,587,577, Cl. 235-472.000.
 Norcross, Kenneth L.; and Li, Yanlong, to Jet-Tech, Inc. Thermophilic aerobic waste treatment process, 5,587,081, Cl. 210-604.000.
 Nordeco Inc.: *See*—
 Weber, Robert M., 5,586,502, Cl. 104-17.200.
 Noritsu Koki Co., Ltd.: *See*—
 Shima, Kazunobu; and Yamamoto, Yui, 5,587,758, Cl. 390-613.000.
 Norris, William P.: *See*—
 Stenger-Smith, John D.; Norris, William P.; and Chafin, Andrew P., 5,587,488, Cl. 549-59.000.
 Norrish, Jay B.: *See*—
 Montgomery, Gerald D.; and Norrish, Jay B., 5,587,743, Cl. 348-473.000.
 North Carolina State University: *See*—
 Kelley, Arthur W.; and Harris, Matthew B., 5,587,662, Cl. 324-713.000.
 Northern Research & Engineering Corporation: *See*—
 Kesseli, James B.; and Baldwin, Stephen P., 5,586,429, Cl. 60-39.070.
 Northrop Grumman Corporation: *See*—
 Bullen, George N., 5,587,900, Cl. 364-167.010.
 Norrner, Richard A., to Sloan Valve Company. Faucet and sensor mounting, 5,586,573, Cl. 137-359.000.
 Norwood, Roger D.: *See*—
 Vogley, Wilbur C.; Balistreri, Anthony M.; Guttig, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poter, Kenneth A.; Hamgan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
 Novack, Vance: *See*—
 Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance, 5,587,483, Cl. 548-252.000.
 Novak, Pavel; and Reibholz, Clemens. Tube pump with retractable rollers, 5,586,873, Cl. 417-477.800.
 Novil, Martin; and O'Brien, Michael, to Fel-Pro Incorporated. Head gasket with pre-embedded metal shim and method of using same, 5,586,769, Cl. 277-1.000.
 Nowak, Edward J.: *See*—
 Machnesney, Brian J.; Mandelman, Jack A.; and Nowak, Edward J., 5,587,604, Cl. 257-350.000.
 Nozuyama, Yasuyuki, to Kabushiki Kaisha Toshiba. Logic circuit having a control signal switching logic function and having a testing arrangement, 5,588,006, Cl. 371-3.000.
 NSK Ltd.: *See*—
 Mitani, Hidenaga; and Morimoto, Hiroshi, 5,586,469, Cl. 74-459.000.
 Unno, Tetsuo; Shoda, Yoshio; and Momono, Tatsunobu, 5,586,827, Cl. 384-450.000.
 NTN Corporation: *See*—
 Izutsu, Tomoyoshi; and Kawashima, Kazuki, 5,586,952, Cl. 474-110.000.
 Nukada, Katsumi; Imai, Akira; and Igarashi, Ryosaku, to Fuji Xerox Co., Ltd. Electrophotographic photoreceptor using triarylamine compounds, 5,587,263, Cl. 430-56.000.
 Nuovopignone-Industrie Meccaniche e Fonderia S.p.A.: *See*—
 Bergamini, Giorgio; and Mininni, Venanzio, 5,586,575, Cl. 137-488.000.
 NuPipe, Inc.: *See*—
 Steketee, Campbell H., Jr., 5,587,126, Cl. 264-568.000.
 Nutramax Laboratories, Inc.: *See*—
 Henderson, Robert W., 5,587,363, Cl. 514-54.000.
 Nycomed Imaging AS.: *See*—
 Almén, Torsten; Berg, Arne; Dugstad, Harald; Klaveness, Jo; Krau (wurst, Klaus D.; and Rongved, Pål, 5,587,144, Cl. 424-9.361.
 Nyman, Folke, to Sandvik AB. Toolholder clamping wedge with insert engaging protrusions, 5,586,844, Cl. 407-105.000.
 Nyseth, David L., to Fluoroware, Inc. Wafer cushions for wafer shipper, 5,586,658, Cl. 206-711.000.
 Obata, Hiroyuki: *See*—
 Iijima, Masayuki; Dantani, Kyoji; Obata, Hiroyuki; Matsuo, Makoto; Utsumi, Minoru; and Take, Seiji, 5,587,264, Cl. 430-57.000.
 Oberman, Mark L.: *See*—
 Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., 5,588,139, Cl. 395-500.000.

- O'Brien, John; and Iye, Jonathan, to Apple Computer, Inc. Modular monitor architecture, 5,587,876, Cl. 361-682.000.
 O'Brien, John L.; Thomas, Edward M.; and Ed, Donald A. N. Support pole with a pivoting and locking handrail for elderly and disabled persons, 5,586,352, Cl. 5-662.000.
 O'Brien, Michael: *See*—
 Novil, Martin; and O'Brien, Michael, 5,586,769, Cl. 277-1.000.
 Oce-Nederland, B.V.: *See*—
 Heeren, Theodorus A. G.; and Buis, Edwin J., 5,587,779, Cl. 355-271.000.
 Ochiai, Ryuji; Morita, Kouzi; and Yagiagi, Kazuyuki, to Kao Corporation. Hair cosmetic composition, 5,587,155, Cl. 424-70.280.
 Oda, Kiichi: *See*—
 Shibasaki, Yasuo; Oda, Kiichi; and Fukuda, Takeshi, 5,587,010, Cl. 106-287.170.
 Oda, Masaaki: *See*—
 Watanabe, Kazuhiro; Oshima, Michihiro; Setoguchi, Kazuhiro; and Oda, Masaaki, 5,587,111, Cl. 252-514.000.
 Oda, Yasuhiro: *See*—
 Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayuki; Iwaoaka, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl. 355-208.000.
 Odom, James M., to Du Pont de Nemours & E. I., and Company. Chemical-histological process for dehalogenation of halogenated organic compounds, 5,587,317, Cl. 435-262.500.
 Oelke, Frank. Chair with lateral frame parts connected by transverse rods supporting seat and backrest, 5,586,808, Cl. 297-287.000.
 Oen, Joshua T.: *See*—
 Bonora, Anthony C.; and Oen, Joshua T., 5,586,585, Cl. 141-93.000.
 Oertel, Armin: *See*—
 Hambitzer, Günther; Böke, Winfried; and Oertel, Armin, 5,587,064, Cl. 205-742.000.
 Office National d'Etudes et de Recherches Aérospatiales: *See*—
 Failepin, François; Fourt, Olivier; and Pastre, Jean-Louis, 5,586,735, Cl. 244-53.00B.
 Ofner, Peter: *See*—
 Gammter, Gebhard; Dengg, Franz; Ofner, Peter; and Münzenberger, Herbert, 5,586,739, Cl. 248-74.100.
 Ogale, Kumar: *See*—
 Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E., 5,587,229, Cl. 428-224.000.
 Ogawa, Akira: *See*—
 Kawakami, Takahiro; Ogawa, Akira; and Ichimura, Eisuo, 5,587,531, Cl. 73-514.120.
 Ogawa, Kazufumi, to Matsushita Electric Industrial Co., Ltd. Formed plastic and method of manufacturing the same, 5,587,220, Cl. 428-71.000.
 Ogawa, Kazufumi: *See*—
 Soga, Mamoru; Mino, Norihisa; Ogawa, Kazufumi; Mochizuki, Yusuke; and Shibata, Tsuneo, 5,587,209, Cl. 427-503.000.
 Ogawa, Kazuo; and Ikeoka, Naoki, to Kabushiki Kaisha Komatsu Seisakusho. Transfer press, 5,586,495, Cl. 100-207.000.
 Ogawa, Kazuyuki: *See*—
 Kori, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato; and Ogawa, Kazuyuki, 5,587,849, Cl. 360-69.000.
 Ogihara, Tsutomu: *See*—
 Yabe, Hiroshi; and Ogihara, Tsutomu, 5,587,691, Cl. 331-44.000.
 Ogiso, Mitsukazu: *See*—
 Hattanda, Hirokatsu; Ogiso, Mitsukazu; Koike, Yasuta; and Takagi, Kazuhiro, 5,587,101, Cl. 222-603.000.
 Oguma, Tomoko: *See*—
 Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
 Ohba, Toshimitsu; Shikata, Kiyotaka; and Sekihata, Osamu, to Fujitsu Limited. LAN-WAN-LAN communication method, and apparatus for LAN-WAN connection, 5,588,003, Cl. 370-468.000.
 Ohhata, Akira: *See*—
 Johdai, Akiyoshi; Ohhata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu; and Hirano, Yoshihiro, 5,587,782, Cl. 355-309.000.
 Ohira, Akira: *See*—
 Ujihara, Junji; and Ohira, Akira, 5,587,266, Cl. 430-133.000.
 Ohira, Takuya: *See*—
 Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
 Ohkubo, Kazuko; and Yahagi, Masahiko, to NEC Corporation. Mobile communication system capable of avoiding local congestion, 5,588,039, Cl. 379-58.000.
 Ohmi, Masato: *See*—
 Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367.000.
 Ohmi, Tadashi: *See*—
 Shibata, Tadashi; and Ohmi, Tadashi, 5,587,668, Cl. 326-36.000.
 Ohmura, Hitoshi; Koyakumaru, Yasuhiro; and Iketaka, Satoshi, to Toyo Kohan Co., Ltd. Corrosion resistant nickel plating steel sheet or strip and manufacturing method thereof, 5,587,248, Cl. 428-610.000.
 Ohnishi, Hiroshi: *See*—
 Nakanishi, Hiroko; and Ohnishi, Hiroshi, 5,587,821, Cl. 349-118.000.

- Ohnishi, Shuhei: *See*—
 Murakami, Kimihiko; Ohnishi, Shuhei; Yano, Takashi; and Itoh, Manabu, 5,587,392, Cl. 514-359.000.
 Ohno, Kazunori, to Fuji Photo Optical Co., Ltd. Albada type inverted galilean finder for camera, 5,587,844, Cl. 359-717.000.
 Ohsawa, Takashi: *See*—
 Kaneko, Tetsuya; and Ohsawa, Takashi, 5,587,958, Cl. 365-230.060.
 Ohsawa, Teisu, to Tokyo Electron Limited; and Tokyo Electron Tohoku Limited. Heat treatment apparatus and heat treatment boat, 5,586,880, Cl. 432-241.000.
 Ohsawa, Yuichi: *See*—
 Iwasaki, Hitoshi; Ohsawa, Yuichi; and Kondoh, Reiko, 5,587,026, Cl. 148-313.000.
 Ohshima, Satoshi; Yumura, Motoo; Kuriki, Yasunori; Uchida, Kunio; and Ikazaki, Fumikazu, to Director-General of Industrial Science and Technology. Method and device for the production of fullerenes, 5,587,141, Cl. 423-445.00B.
 Ohsugi, Minoru: *See*—
 Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323.000.
 Ohta, Issei: *See*—
 Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Issei; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.
 Ohta, Kenji: *See*—
 Nagaura, Toshikazu; Yamashita, Zenjiro; Arikawa, Kazuhiko; and Ohta, Kenji, 5,587,994, Cl. 369-291.000.
 Ohta, Takeo: *See*—
 Yoshioka, Kazumi; Ohta, Takeo; Furukawa, Shigeaki; and Kawahara, Katsumi, 5,587,216, Cl. 428-64.400.
 Ohtaka, Kazuto: *See*—
 Sakai, Hitoshi; and Ohtaka, Kazuto, 5,586,854, Cl. 411-429.000.
 Ohtani, Hiroaki: *See*—
 Nonaka, Kimihiko; and Ohtani, Hiroaki, 5,586,524, Cl. 123-73.00A.
 Ohya, Keishi, to Tatsumo Kabushiki Kaisha. Robot arm device capable of conveying an article in circumferential and radial directions, 5,587,637, Cl. 318-568.110.
 Oi, Kiyotoshi: *See*—
 Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, 5,586,539, Cl. 123-458.000.
 Oizumi, Yumiko, to Fujitsu Limited. Apparatus and method for ensuring data in external storage system, 5,588,012, Cl. 371-51.100.
 Ojima, Heiji: *See*—
 Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heiji, 5,587,060, Cl. 204-554.000.
 Oka, Koutarou: *See*—
 Fujiwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei; and Ito, Shigehiro, 5,587,989, Cl. 369-178.000.
 Okabe, Masato, to Dai Nippon Printing Co., Ltd. Information recording method having a liquid crystal substrate, 5,587,987, Cl. 369-126.000.
 Okada, Naohisa, to Sumitomo Wiring Systems, Ltd. Electrical terminal, 5,586,899, Cl. 439-287.000.
 Okazaki, Yoji; Goto, Chiaki; Hyuga, Hiroaki; and Harada, Akinori, to Fuji Photo Film Co., Ltd. Optical wavelength converting apparatus, 5,588,014, Cl. 372-22.000.
 Okubo, Mamoru; and Yoneyama, Koji, to Exedy Corporation. One way clutch mechanism for a torque converter, 5,586,434, Cl. 60-345.000.
 Okuda, Isao: *See*—
 Kanazawa, Hiroshi; Okuda, Isao; Shinozaki, Shimpei; and Takishima, Suguru, 5,587,973, Cl. 369-13.000.
 Okuma, Ikuo: *See*—
 Inoue, Tohru; Onishi, Ken; Inoue, Sadayuki; and Okuma, Ikuo, 5,587,803, Cl. 386-33.000.
 Okumura, Takashi: *See*—
 Takami, Hiroshi; Yasui, Yoshihiro; and Okumura, Takashi, 5,586,500, Cl. 101-327.000.
 Okumura, Yukimasa: *See*—
 Fujii, Junji; and Okumura, Yukimasa, 5,587,544, Cl. 84-411.00R.
 Okuno, Yoshiaki: *See*—
 Kagawa, Shuichi; Chiba, Kazuhiro; Bamba, Noriko; and Okuno, Yoshiaki, 5,588,050, Cl. 382-167.000.
 Okuno, Yoshitaka: *See*—
 Adachi, Fumiaki; Amano, Tadashi; Shiota, Yoshihiro; and Okuno, Yoshitaka, 5,587,437, Cl. 526-68.000.
 Okutani, Haruo: *See*—
 Nakadera, Kazuo; Okutani, Haruo; and Kurebayashi, Hideki, 5,587,265, Cl. 430-109.000.
 Old, Lloyd J.: *See*—
 Rettig, Wolfgang J.; Scanlan, Matthew J.; Garin-Chesa, Pilar; and Old, Lloyd J., 5,587,299, Cl. 435-69.100.
 Oldfield, William W.; Brinkoetter, Thomas R.; and Antes, Todd D., to Wiltron Company. Automatic VNA calibration apparatus, 5,587,934, Cl. 364-571.010.
 Olkkonen, Kari: *See*—
 Toivio, Ilkka; Toivio, Terttu; and Olkkonen, Kari, 5,586,348, Cl. 5-710.000.
 Olmsted, Daniel C.: *See*—
 Hanning, John R.; and Olmsted, Daniel C., 5,586,569, Cl. 137-116.500.
 Olsen, Perry E.: *See*—

- Gledde, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., 5,586,411, Cl. 47-57.600.
- Olson, George: *See—*
Slaughter, John E.; Olson, George; and McShane, William J., 5,587,788, Cl. 356-246.000.
- Olson, Timothy L.; Carney, Lauriann T.; Johnson, Gary C.; and Strom, William M., to Motorola, Inc. Lead frame assembly for surface mount integrated circuit power package. 5,587,883, Cl. 361-723.000.
- Oltman, John E.: *See—*
Dopp, Robert B.; Oltman, John E.; and Passaniti, Joseph L., 5,587,259, Cl. 429-233.000.
- Olympus America, Inc.: *See—*
Martinez, Marcus J.; and Tafoya, Anthony S., 5,586,974, Cl. 604-26.000.
- Olympus Optical Co., Ltd.: *See—*
Takahashi, Koichi; and Togino, Takayoshi, 5,587,836, Cl. 359-630.000.
- Omori, Teruyo: *See—*
Hori, Satoshi; Omori, Teruyo; and Sakagami, Makoto, 5,587,930, Cl. 364-551.010.
- Ondrejko, Richard T.; Castiglione, Paul J.; and Miller, Robert J., to Ford Motor Company. Assembly of rotary hydraulic pumps. 5,586,875, Cl. 418-3.000.
- O'Neal, Robert G.: *See—*
Wilson, Wilbert J.; and O'Neal, Robert G., 5,586,441, Cl. 62-99.000.
- Oneto, John C.; and Russell, Stephen P., to Amdahl Corporation. System for establishing priority among selected tasks based on location of tasks and sequence that the tasks were stored whereas task is always stored in location with the lowest available address. 5,588,134, Cl. 395-485.000.
- Onishi, Ken: *See—*
Inoue, Tohru; Onishi, Ken; Inoue, Sadaaki; and Okuma, Ikuo, 5,587,803, Cl. 386-33.000.
- Ono, Makoto; and Minakata, Hiroshi, to International Business Machines Corporation. Graphic display method and apparatus for rotating an object in three-dimensional space. 5,588,097, Cl. 395-137.000.
- Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, to Canon Kabushiki Kaisha. Recording apparatus which avoids ink sheet sticking and image streaking. 5,587,733, Cl. 347-185.000.
- Ono, Tsuyoshi: *See—*
Sato, Shigehiro; Matsunaga, Yoshiyuki; Ono, Tsuyoshi; and Karube, Takaaki, 5,587,097, Cl. 219-543.000.
- Onodera, Ko: *See—*
Yumiyama, Shigeru; Onodera, Ko; and Mori, Yoshinori, 5,587,619, Cl. 310-201.000.
- Onodera, Takahiro: *See—*
Kunihara, Mikio; Nishi, Satoru; Onodera, Takahiro; and Kushima, Kazunari, 5,587,557, Cl. 174-266.000.
- Oogami, Hidetoshi: *See—*
Takao, Yuichi; and Oogami, Hidetoshi, 5,587,515, Cl. 564-135.000.
- Ooi, Yoshiharu: *See—*
Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Otsuka, Takeshi; and Higashida, Masaaki, to Matsushita Electric Industrial Co., Ltd. Apparatus for processing digital video data with error correction partly comprising error concealment means. 5,587,807, Cl. 386-46.000.
- Ouya, Masaki, to Kabushiki Kaisha Riken. Coating of chromium and nitrogen having good wear resistance properties. 5,587,227, Cl. 428-217.000.
- Orbeck, Finn, to Orian Technology Limited. Ship's hull vibration damper. 5,586,512, Cl. 114-65.000.
- Orbital Sciences Corporation: *See—*
Steffy, David A., 5,587,719, Cl. 343-895.000.
- Organ, Inc.: *See—*
Fahy, Gregory M., 5,586,438, Cl. 62-78.000.
Fahy, Gregory M., 5,586,987, Cl. 606-155.000.
- Ori, Janos: *See—*
Hajmichael, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Szekely, Istvan; Marmarosi née Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
- Orian Technology Limited: *See—*
Orbeck, Finn, 5,586,512, Cl. 114-65.000.
- Orito, Nobuyuki: *See—*
Sakai, Michio; Hosoya, Ryouzou; Orito, Nobuyuki; and Nakahata, Minoru, 5,587,873, Cl. 361-603.000.
- Oritel, Thomas L.: *See—*
Kane, William H.; and Oritel, Thomas L., 5,587,310, Cl. 435-240.200.
- Orthopedic Technology, Inc.: *See—*
Morris, John; and Stafford, Gary, 5,586,970, Cl. 602-26.000.
- Orzal, Gregory J., to Wacker Corporation. Spring applied/fluid released parking brake. 5,586,630, Cl. 192-4.000.
- Osako, Yoshiyuki: *See—*
Aoki, Hideji; Tashima, Takahiro; Nakashima, Suekazu; Osako, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164.000.
- Oshikiri, Koji: *See—*
Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500.000.
- Oshima, Michihiro: *See—*
Watanabe, Kazuhiro; Oshima, Michihiro; Setoguchi, Kazuhiro; and Oda, Masaaki, 5,587,111, Cl. 252-514.000.
- Osram Sylvania, Inc.: *See—*
Zuk, Karlene J., 5,587,346, Cl. 501-152.000.
- Osterhout, Richard A.: *See—*
Lothamer, Thomas J.; Pontecorvo, Carl A.; Schattke, Thomas L.; and Osterhout, Richard A., 5,587,568, Cl. 200-16.000.
- Ostermayer, Volker; and Fleischer, Thomas B. Simplified laser apparatus and method for measuring stock thickness on papermaking machines. 5,587,051, Cl. 162-198.000.
- Otake, Masahiro; Takahashi, Toyofumi; Nishiumi, Satoshi; and Otsuki, Takashi, to Nintendo Co., Ltd.; and Ricoh Co., Ltd. Display range control apparatus and external storage unit for use therewith. 5,587,723, Cl. 345-118.000.
- Otani, Seiji: *See—*
Tanaka, Nobuo; Otani, Seiji; Kawakita, Hiroyuki; and Matsuda, Teruo, 5,586,975, Cl. 604-89.000.
- Otari Development and Construction Department of Hokkaido Development Bureau: *See—*
Tsuiji, Tomoyuki, 5,586,834, Cl. 404-60.000.
- Otis Elevator Company: *See—*
Barten, Michael; and Toutaoui, Mustapha, 5,587,566, Cl. 187-316.000.
Schröder-Brumloop, Helmut; and Löb, Rüdiger, 5,587,565, Cl. 187-316.000.
- Otoma, Hiromi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, to Fuji Xerox Co., Ltd. Semiconductor laser device. 5,588,016, Cl. 372-46.000.
- Otonkoski, Timo P. J.: *See—*
Rubin, Jeffrey; Hayek, Alberto; Beattie, Gillian M.; and Otonkoski, Timo P. J., 5,587,309, Cl. 435-240.200.
- Otsuka Kagaku Kabushiki Kaisha: *See—*
Kawahara, Ichiro; Wada, Isao; and Sasaoka, Michio, 5,587,464, Cl. 534-558.000.
- Otsuka, Masao: *See—*
Nakamatsu, Yasuhiro; Otsuka, Masao; Hatanaka, Fumio; and Tsunoda, Akihito, 5,586,757, Cl. 271-145.000.
- Otsuki, Takashi: *See—*
Otake, Masahiro; Takahashi, Toyofumi; Nishiumi, Satoshi; and Otsuki, Takashi, 5,587,723, Cl. 345-118.000.
- Otto, Bernhard: *See—*
Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Buerger, Gert; and Pijl, Paul, 5,587,135, Cl. 423-239.100.
- Otto Ganter & Co. KG: *See—*
Ganter, Bernhard, 5,586,852, Cl. 411-353.000.
- Otus, Erol: *See—*
Bowden, Lori; Jochums, Sharon L.; and Otus, Erol, 5,588,107, Cl. 395-344.000.
- Overpeck, Willard T. Portable picnic table. 5,586,803, Cl. 297-158.300.
- Oveyssi, Kamran: *See—*
Dunfield, John C.; and Oveyssi, Kamran, 5,587,617, Cl. 310-90.500.
- Owa, Hideo; and Kobayashi, Seiji, to Sony Corporation. Hologram printed on optical recording medium for copy protection. 5,587,984, Cl. 369-103.000.
- Owen, Gwyn P.: *See—*
Hagen, Urs A.; Schmid, Martin; and Owen, Gwyn P., 5,586,516, Cl. 114-362.000.
- Owen, Ian R.: *See—*
Moren, Dean M.; and Owen, Ian R., 5,587,502, Cl. 556-420.000.
- Owen, William H.; and Jaffe, James M., to Xicor, Inc. Wireless powering and communication system for communicating data between a host system and a stand-alone device. 5,587,573, Cl. 235-380.000.
- Owens, Steve C.; Lovvorn, Richard V.; and Elder, Albert B., to Southwire Company. Magnetic support system for cable insertion tube. 5,587,181, Cl. 425-3.000.
- Oxford Instruments (UK) Limited: *See—*
Lumley, John M.; and Paik, Ho J., 5,587,526, Cl. 73-382.000.
- Oyabe, Kazunori; Yoshida, Kazuhiko; and Fujihira, Tatsuhiko, to Fuji Electric Co., Ltd. Constant current circuit. 5,587,655, Cl. 323-312.000.
- Oyanagi, Toshiki: *See—*
Tsutsumi, Haruki; Ikemoto, Yoshiaki; Maehama, Mitsuhiro; Oyanagi, Toshiki; and Matsubara, Tsugio, 5,587,246, Cl. 428-511.000.
- Ozaki, Naoki: *See—*
Nabeshima, Daiki; and Ozaki, Naoki, 5,587,991, Cl. 369-275.300.
- Ozarowski, Ryszard S.: *See—*
Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
- Ozeki, Masao: *See—*
Gunjima, Tomoki; Ooi, Yoshiharu; Ozeki, Masao; Ito, Hiroaki; Hasebe, Hiroshi; Matsumoto, Tetsuro; and Nakagawa, Yutaka, 5,587,816, Cl. 349-62.000.
- Ozeki, Yukihiro: *See—*
Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiro; Kugo, Harumi; Sakai, Kazuhiro; Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210.000.
- Ozontech Ltd.: *See—*
Malkin, Boris; Perlov, Gena; and Yannai, Shmuel, 5,587,131, Cl. 422-186.110.
- Pace Company: *See—*
Berger, Thomas A., 5,586,861, Cl. 415-118.000.
- Pacesetter AB: *See—*
Lorenz, Hans P.; Straehler, Bernd; and Lindegren, Ulf, 5,587,200, Cl. 427-2.240.
- Paciotti, Giulio F.: *See—*

- Tamarkin, Lawrence; and Paciotti, Giulio F., 5,587,294, Cl. 435-7.930.
- Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandi, Lisa; Stebnitz, Kathleen K.; and Mendoza, Leopoldo G., to Promega Corporation. Methods and kits for detection of cells in food materials. 5,587,286, Cl. 435-6.000.
- Pai, Balakrishna S.: *See—*
Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, 5,587,362, Cl. 514-46.000.
- Paik, Ho J.: *See—*
Lumley, John M.; and Paik, Ho J., 5,587,526, Cl. 73-382.000.
- Paleari, Fabio: *See—*
Salimbeni, Aldo; Paleari, Fabio; Mizrahi, Jacques; and Scolastico, Carlo, 5,587,390, Cl. 514-341.000.
- Pall Corporation: *See—*
Pall, David B.; and Connors, James T., Jr., 5,586,997, Cl. 55-361.000.
Pall, David B.; Gsell, Thomas C.; Matkovich, Vlado I.; and Bormann, Thomas, 5,587,070, Cl. 210-202.000.
- Pall, David B.; and Connors, James T., Jr., to Pall Corporation. Bag filter. 5,586,997, Cl. 55-361.000.
- Pall, David B.; Gsell, Thomas C.; Matkovich, Vlado I.; and Bormann, Thomas, to Pall Corporation. System for processing biological fluid. 5,587,070, Cl. 210-202.000.
- Palm, Rainer, to Siemens Aktiengesellschaft. Method and apparatus for fuzzy control. 5,587,898, Cl. 364-148.000.
- Pan, David H.: *See—*
Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry, Arnold W.; Heeks, George J.; and Fratangelo, Louis D., 5,587,208, Cl. 427-503.000.
- Panasonic Technologies, Inc.: *See—*
Hau, Clarence J.-Y.; Stec, Kevin J.; and Vavreck, Kenneth E., 5,587,742, Cl. 348-441.000.
- Pansari, Frank, Jr.: *See—*
Marshall, Robert C.; and Pansari, Frank, Jr., 5,586,905, Cl. 439-463.000.
- Panzhuhua Iron and Steel (Group) Co.: *See—*
Hong, Jibi; Chu, Jianhua; and Wu, Hongxiang, 5,587,347, Cl. 501-155.000.
- Panzica, Raymond P.; El Subhagh, Hussein I.; and Abushanab, Elie, to Board of Governors for Higher Education, State of Rhode Island and Providence Plantations, The. Practical, cost-efficient chiral synthesis of dihydrospingosines. 5,587,494, Cl. 549-512.000.
- Pap, Laszlo: *See—*
Hajmichael, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Szekely, Istvan; Marmarosi née Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
- Papworth, David B.: *See—*
Abramson, Jeffrey M.; Akkary, Haitham; Glew, Andrew F.; Hinton, Glenn J.; Konigsfeld, Kris G.; Madland, Paul D.; and Papworth, David B., 5,588,126, Cl. 395-376.000.
- Paquer, Daniel: *See—*
Curci, Michele; Mieloszynski, Jean-Luc; and Paquer, Daniel, 5,587,499, Cl. 554-85.000.
- Paré, Claude: *See—*
Champagne, Yves; Paré, Claude; and Bélanger, Pierre-André, 5,587,786, Cl. 356-121.000.
- Parham, Dennis E.: *See—*
Spamer, William S.; Suttles, J. Marshall; Parham, Dennis E.; and Whiten, James D., 5,586,687, Cl. 221-298.000.
- Parham, Thomas G.; Dynys, Frederick W.; Gunter, Carl V.; Davenport, John M.; Golt, Thomas M.; Bergman, Rolf S.; Ahlgren, Frederic F.; Allen, Gary R.; Duffy, Mark E.; and Hansler, Richard L., to General Electric Company. Patterned optical interference coatings for only a portion of a high intensity lamp envelope. 5,587,626, Cl. 313-634.000.
- Parizlsky, Vladimir, to U.S. Robotics. Simplified trellis decoder. 5,588,028, Cl. 375-341.000.
- Park, Chi H.: *See—*
Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.
- Park, Ku-man, to Samsung Electronics Co., Ltd. Method for recording images in a digital video cassette recorder. 5,587,805, Cl. 386-68.000.
- Parker, David C., to Microsoft Corporation. Method and system for creating a freeform drawing object. 5,588,100, Cl. 395-142.000.
- Parker, Gary A.: *See—*
Muyshondt, Jorge E.; Parker, Gary A.; and Wilkie, Bruce J., 5,587,920, Cl. 364-489.000.
- Parker-Hannifin Corporation: *See—*
Hanning, John R.; and Olmsted, Daniel C., 5,586,569, Cl. 137-116.500.
- Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., to Rogosin Institute, The. Compositions useful in prophylaxis and therapy of endotoxin related conditions. 5,587,366, Cl. 514-78.000.
- Pasquale, Michael J. Swing stroke gardening tool. 5,586,392, Cl. 30-318.000.
- Passaniti, Joseph L.: *See—*
Dopp, Robert B.; Oltman, John E.; and Passaniti, Joseph L., 5,587,259, Cl. 429-233.000.
- Pastan, Ira: *See—*
Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324.000.
- Pastre, Jean-Louis: *See—*
Falempin, Francois; Fourt, Olivier; and Pastre, Jean-Louis, 5,586,735, Cl. 244-53.000.
- Patel, Chandrakant, to Hewlett-Packard Company. Thermal interface for a heat sink and a plurality of integrated circuits mounted on a substrate. 5,587,882, Cl. 361-705.000.
- Patel, Mahendra R.; Reddy, Kasireddy C.; and Dave, Pankaj J., to Invamed, Inc. Terazosin crystalline polymorph and pharmaceutical compositions thereof. 5,587,377, Cl. 514-254.000.
- Paterson, Robert I.; and Breeze, Brian A., to Helifix Ltd. Multi-wall tie apparatus. 5,586,605, Cl. 173-4.000.
- Patois, Carl: *See—*
Denis, Philippe; Patois, Carl; and Perron, Robert, 5,587,056, Cl. 203-29.000.
- Patrick, Miller B.: *See—*
Henderson, Allan P.; and Patrick, Miller B., 5,586,417, Cl. 52-295.000.
- Paul, William C.; and Sietloff, Ronald F., to General Electric Company. Method and apparatus for coating corrugated sheet material. 5,587,206, Cl. 427-558.000.
- Pauls, Lonney: *See—*
Klein, Gary G.; Voss, Darrell W.; and Pauls, Lonney, 5,586,780, Cl. 280-275.000.
- Pavonetti, Onofrio F. Collapsible/portable soccer goal. 5,586,768, Cl. 273-411.000.
- Peacock, John; Frost, Peter L. J.; and Kerry, John, to British Telecommunications public limited company. Optical fibre management system. 5,588,076, Cl. 385-20.000.
- Peake, Clinton J.: *See—*
Henrie, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chaguturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.
- Pehrsson, Pehr E.: *See—*
Marchyuka, Michael J.; and Pehrsson, Pehr E., 5,587,210, Cl. 427-523.000.
- Penco, Sergio: *See—*
Buzzetti, Franco; Fustinoni, Silvia; Brasca, Maria G.; and Penco, Sergio, 5,587,385, Cl. 514-309.000.
- Cabri, Walter; De Bernardinis, Silvia; Francalanci, Franco; and Penco, Sergio, 5,587,495, Cl. 552-220.000.
- Peng, Jack Z.: *See—*
Lin, Jonathan; Peng, Jack Z.; Barsan, Radu; and Mehta, Sunil, 5,587,945, Cl. 365-185.100.
- Pennica, Diane: *See—*
Goeddel, David V.; Kohr, William J.; Pennica, Diane; and Vehar, Gordon A., 5,587,159, Cl. 424-94.640.
- Peptide Technology Limited: *See—*
Rathjen, Deborah A.; and Ferrante, Antonio, 5,587,457, Cl. 530-326.000.
- Perboni, Alcide; Rossi, Tino; Gaviraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonella, to Glaxo SpA. 10(1-hydroxyethyl)-11-oxo-1-azatricyclo[7.2.0.0^{2,7}]undec-2-ene-2-carboxylic acid esters and a process for preparing thereof. 5,587,374, Cl. 514-210.000.
- Perelmutter, Oleg: *See—*
Ben-Yair, Igal; Berger, Haim; and Perelmutter, Oleg, 5,587,904, Cl. 364-449.700.
- Periou, Pierre: *See—*
Bridgeman, Mark; and Periou, Pierre, 5,586,646, Cl. 200-541.000.
- Perko, Jack E.: *See—*
Hying, Clement F.; Perko, Jack E.; and Wenzler, Larry E., 5,587,043, Cl. 156-566.000.
- Perlman, Kato L.: *See—*
DeLuca, Hector F.; Schnoes, Heinrich K.; Perlman, Kato L.; Scinski, Rafal R.; and Prah, Jean M., 5,587,497, Cl. 552-653.000.
- Perlov, Gena: *See—*
Malkin, Boris; Perlov, Gena; and Yannai, Shmuel, 5,587,131, Cl. 422-186.110.
- Perret, Michel, to GEC Alstom T & D SA. Combined-action puffer circuit-breaker. 5,587,571, Cl. 218-60.000.
- Perron, Robert: *See—*
Denis, Philippe; Patois, Carl; and Perron, Robert, 5,587,056, Cl. 203-29.000.
- Perrone, Ettore: *See—*
Alpegiani, Marco; Bissolino, Pierluigi; and Perrone, Ettore, 5,587,373, Cl. 514-202.000.
- Perry, William: *See—*
Falcon, Michael D.; Perry, William; and Hess, Arthur, 5,587,699, Cl. 340-475.000.
- Pescher, Yvette: *See—*
Danda, Sylvain; Kvant, Magnus; and Pescher, Yvette, 5,587,086, Cl. 210-723.000.
- Pessier, Rudolf C. O.: *See—*
Isbell, Matthew R.; and Pessier, Rudolf C. O., 5,586,612, Cl. 175-353.000.
- Peters, Scott M.: *See—*
Branner, Donald L.; Ray, Andrew E.; Peters, Scott M.; and Huber, Richard M., 5,587,706, Cl. 340-825.440.
- Peterson, Fred M.; and Yee, James A. Motion detection and image acquisition apparatus and method of detecting the motion of and acquiring an image of an object. 5,588,067, Cl. 382-103.000.
- Peterson, Ralph S.: *See—*
Streisel, Robert C.; Hank, Mark A.; Mulcahy, Leo T.; and Peterson, Ralph S., 5,587,048, Cl. 162-7.000.

- Petruchik, Dwight J., to Eastman Kodak Company. Camera, system and method for producing composite photographic image. 5,587,752, Cl. 396-315.000.
- Phizenmaier, Heinz; Blakelock, Philip; Prime, Brian; and Dawson, David, to Plessey Semiconductors Limited, and Robert Bosch GmbH. Radar transmitter/receivers. 5,587,713, Cl. 342-70.000.
- Pharmacyclics, Inc.: See—
Sessler, Jonathan L.; Mody, Tarak D.; Hemmi, Gregory W.; Král, Vladimir A.; and Magda, Darren, 5,587,371, Cl. 514-185.000.
- Pherigo, Douglas E.; and Jansen, Leo B., to Textron Inc. Headlamp level indicator. 5,586,393, Cl. 33-288.000.
- Philadelphia College of Pharmacy and Science: See—
Kauffman, Joel M., and Litak, Peter T., 5,587,112, Cl. 252-589.000.
- Philip Morris Incorporated: See—
Babey, Jacques; Salmon, Brian; De Borst, Eric; and Tallier, Bernard, 5,586,565, Cl. 131-84.200.
- Longest, H. Cary; and Lynch, James L., 5,588,068, Cl. 382-141.000.
- Philippe, Michel; Senieria, Didier; and Bollens, Eric, to L'Oréal. Cosmetic or pharmaceutical composition comprising an alkyl carbamate as hydrating agent. 5,587,169, Cl. 424-401.000.
- Philips, Thomas E.: See—
Mereer, Charles L., and Philipps, Thomas E., 5,587,231, Cl. 428-283.000.
- Philips Electronics North America Corporation: See—
Gornstein, Viktor L., 5,587,629, Cl. 315-200.000.
- Phillips Petroleum Company: See—
Brown, Scott H.; Zisman, Stan A.; and Kimble, James B., 5,587,348, Cl. 502-230.000.
- Moczygemba, George A.; Knight, Nancy R.; Trepka, William J.; and Stacy, Nathan E., 5,587,425, Cl. 525-98.000.
- Phillips, Richard J.; and Larson, Ralph L., to Aavid Laboratories, Inc. Computer cooling system operable under the force of gravity in first orientation and against the force of gravity in second orientation. 5,587,880, Cl. 361-687.000.
- Phillips, Lawrence R.; and VanDenBerg, Eugene W., II. Cylinder head for internal combustion engines. 5,586,522, Cl. 123-41.82R.
- Philom Bios Inc.: See—
Gledhill, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., 5,586,411, Cl. 47-57.600.
- Piazza, Pietro. Espresso coffee maker. 5,586,484, Cl. 99-287.000.
- Picard, Jean-Louis: See—
Bertrand, Jean-Louis; Charier, Gilles A.; Guyonnet, Xavier J.A.; and Picard, Jean-Louis, 5,586,860, Cl. 415-115.000.
- Piejko, Karl-Erwin: See—
Laugstein, Gerhard; Krüger, Ralf; Piejko, Karl-Erwin; Eisele, Ulrich; and Morbitzer, Leo, 5,587,424, Cl. 525-63.000.
- Pierschbacher, Michael D.; Honsik, Cyril J.; and Dreisbach, Lisa B., to La Jolla Cancer Research Foundation. Hydrophobic attachment site for adhesion peptides. 5,587,456, Cl. 530-326.000.
- Pijl, Paul: See—
Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Burger, Gert; and Pijl, Paul, 5,587,135, Cl. 423-239.100.
- Pines, Michael Y.; and King, Donald F., to Hughes Electronics. Multispectral-staring sensor. 5,587,784, Cl. 356-4.010.
- Ping, Roy C. C.: See—
Wolfe, Jack; and Ping, Roy C. C., 5,586,358, Cl. 15-334.000.
- Pinkney, Heidi; Hor, Ah-Mee; and Popovic, Zoran D., to Xerox Corporation. Photoconductive imaging members. 5,587,262, Cl. 430-54.000.
- Pioneer Electronic Corporation: See—
Funamoto, Kyoto, 5,587,986, Cl. 369-124.000.
- Hayashi, Hideki, 5,587,992, Cl. 369-275.400.
- Komaki, Toshihiro, 5,587,624, Cl. 313-584.000.
- Nakai, Toshiaki; Amano, Mitsuyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki; and Sato, Masuhiro, 5,587,547, Cl. 84-645.000.
- Sato, Masatoshi, 5,587,562, Cl. 181-167.000.
- Pirani, Gary P.; Gulachenski, Alan M.; and Kelly, David J., to Electronic Designs Inc. Electrical socket for high-frequency applications. 5,586,891, Cl. 439-71.000.
- Pirosche, Beverly M.: See—
Rowley, Michael V.; Warkentin, Douglas D.; and Piroshko, Beverly M., 5,587,079, Cl. 210-603.000.
- Pirtle, Eugene C.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.
- Pistor, Donald: See—
Bahuder, Kirt M.; Joseph, Douglas A.; Pistor, Donald; and Stupica, L. Joseph, 5,586,477, Cl. 82-126.000.
- Pitney Bowes Inc.: See—
Hubbard, David; and Wolog, Walter, 5,586,817, Cl. 312-334.440.
- Pizzi, Vladimiro: See—
Nielsen, Robert A.; and Pizzi, Vladimiro, 5,586,345, Cl. 5-99.100.
- Plastohlm Industries, Inc.: See—
Foos, Douglas E., 5,586,677, Cl. 220-260.000.
- Platz, Matthew S.: See—
Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.
- Plessey Semiconductors Limited: See—
Fobbeater, Ian G., 5,587,681, Cl. 327-307.000.
- Phizenmaier, Heinz; Blakelock, Philip; Prime, Brian; and Dawson, David, 5,587,713, Cl. 342-70.000.
- Plyley, Alan K.; Vidal, Claude A.; Minck, John L., Jr.; and Solyntjes, Alan J., to United States Surgical Corporation. Surgical stapler with mechanisms for reducing the firing force. 5,586,711, Cl. 227-176.100.
- Poe, Charles A., to Davidson Textron Inc. Fastener cage for a panel. 5,586,853, Cl. 411-372.000.
- Poel, Richard J.: See—
Matsen, Marc R.; Poel, Richard J.; Crow, Wesley B.; and Nansen, David S., 5,587,098, Cl. 219-615.000.
- Pohmer, Klaus; Weber, Rainer; Dörzbach-Lange, Cornelia; Haida, Reinhard; and Moretto, Hans-Heinrich. Polyether-substituted imide compounds and their use. 5,587,513, Cl. 564-84.000.
- Pohn, Romeo; and Schüller, Edmund, to Rieter Ingolstadt Spinnereimaschinenbau AG. Device for adjusting the contact pressure of a pressure roller against the draw-off shaft of a rotor spinning machine. 5,586,427, Cl. 57-264.000.
- Policapelli, Nini E. Container for dispensing liquids. 5,586,681, Cl. 220-674.000.
- Polyshot Corporation: See—
Hepler, Douglas C., 5,587,188, Cl. 425-549.000.
- Pontecorvo, Carl A.: See—
Lothamer, Thomas J.; Pontecorvo, Carl A.; Schattke, Thomas L.; and Osterhout, Richard A., 5,587,568, Cl. 200-16.00R.
- Poole, Alan: See—
Williamson, Robert; Poole, Alan; and Weinert, Michael S., 5,588,055, Cl. 379-446.000.
- Poole, Stephen C.: See—
Greaves, Brian; Poole, Stephen C.; Hwa, Chih M.; and Fan, Joseph C., 5,587,109, Cl. 252-392.000.
- Popovic, Zoran D.: See—
Pinkney, Heidi; Hor, Ah-Mee; and Popovic, Zoran D., 5,587,262, Cl. 430-54.000.
- Porter, Christine A.: See—
Choo, Chang Y.; Ran, Xiaonong; Porter, Christine A.; and Motamedi, Mohammad R., 5,587,710, Cl. 341-107.000.
- Porter, Michael R.; Mulcahey, Charles E.; and Kirby, John J., to Porter Sewing Machines, Inc. Method and apparatus for assembly of pillow-top mattress covers. 5,586,511, Cl. 112-2.100.
- Porter Sewing Machines, Inc.: See—
Porter, Michael R.; Mulcahey, Charles E.; and Kirby, John J., 5,586,511, Cl. 112-2.100.
- Porterfield, Ann L.: See—
Barta, Patrick J.; and Porterfield, Ann L., 5,586,647, Cl. 206-217.000.
- Possin, George E.: See—
Kingsley, Jack D.; and Possin, George E., 5,587,591, Cl. 257-59.000.
- Postema, Leonard F. Aerator. 5,586,604, Cl. 172-21.000.
- Postma, Erik: See—
van Holst, Gerrit J.; Krueger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, 5,587,312, Cl. 435-240.460.
- Poswick, Pierre G.: See—
Vieslet, Jean-Paul B.; Vieslet, Bernard P.; and Poswick, Pierre G., 5,587,120, Cl. 264-118.000.
- Poteet, Kenneth A.: See—
Vogley, Wilbur C.; Balistreri, Anthony M.; Guttig, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221.000.
- Potini, Chim: See—
Punto, Louis; Potini, Chim; Duque, Pilar; and Gould, Eva, 5,587,149, Cl. 424-59.000.
- Powis, Jack R.: See—
Fisher, Fred M.; and Powis, Jack R., 5,586,415, Cl. 52-58.000.
- Prahl, Jean M.: See—
DeLuca, Hector F.; Schnoes, Heinrich K.; Perlman, Kato L.; Sicinski, Rafal R.; and Prahl, Jean M., 5,587,497, Cl. 552-653.000.
- Prakla-Seismos GmbH: See—
Ferber, Ralf G., 5,587,967, Cl. 367-53.000.
- Prasad, Raghubir: See—
Wall, Ronald; Prasad, Raghubir; and Sela, Elaine, 5,587,158, Cl. 424-93.500.
- Pratt & Whitney Canada Inc.: See—
Dooley, Kevin A., 5,587,630, Cl. 315-209.00T.
- Praxair Technology, Inc.: See—
Kobayashi, Hisashi, 5,586,999, Cl. 65-134.300.
- Presby, Herman M.: See—
Greene, Benjamin I.; Narayanan, Chellappan; and Presby, Herman M., 5,588,085, Cl. 385-123.000.
- Prest, William M., Jr.: See—
Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry, Arnold W.; Heeks, George J.; and Fratangello, Louis D., 5,587,208, Cl. 427-503.000.
- Prevost, Michael: See—
Sullivan, Chris; Wells, Jim; and Prevost, Michael, 5,587,092, Cl. 219-113.000.
- Price, Daniel L.: See—
Terry, Claude E.; Triestman, Douglas E.; and Price, Daniel L., 5,587,407, Cl. 523-122.000.
- Price, Noah M.; Takahashi, Duane M. P.; and Buuck, David C., to Apple Computer, Inc. Printed circuit board having a configurable voltage supply. 5,587,887, Cl. 361-794.000.

- Priest, John H.: See—
Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stehnitz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.
- Priester, Donnan E., to E. I. DuPont de Nemours and Company. Processing and system for polyolefins. 5,587,429, Cl. 525-187.000.
- Prime, Brian: See—
Phizenmaier, Heinz; Blakelock, Philip; Prime, Brian; and Dawson, David, 5,587,713, Cl. 342-70.000.
- Prince, Steven: See—
Mehner, David W.; Fomeck, Kevin; Prince, Steven; and Major, Michael D., 5,587,196, Cl. 426-611.000.
- Princeton University: See—
Cecchi, Joseph L.; and Stevens, James E., 5,587,038, Cl. 156-345.000.
- Pringle, Ronald E., to Camco International Inc. Mechanism for anchoring well tool. 5,586,601, Cl. 166-212.000.
- Probi AB: See—
Bengmark, Stig; Ahné, Siv; Molin, Göran; and Jeppson, Bengt, 5,587,314, Cl. 435-252.900.
- Probst, Joachim: See—
Heiliger, Ludwig; Schmidt, Adolf; and Probst, Joachim, 5,587,443, Cl. 526-240.000.
- Procond Electronica S.p.A.: See—
De Marco, Doreano, 5,587,005, Cl. 96-26.000.
- Procter & Gamble Company, The: See—
Daiderman, Shelley L.; McWilliams, Linda C.; Nair, Hari A.; and Staud, Gary G., 5,587,356, Cl. 510-320.000.
- Thomas, Dennis A., 5,586,371, Cl. 24-452.000.
- Thomas, Dennis A., 5,586,979, Cl. 604-382.000.
- Thomas, Hewin N.; Haney, Jack E.; and Hamilton, Peter W., 5,586,671, Cl. 215-209.000.
- Warren, Raphael; and Akadiri, Adebola T., 5,587,176, Cl. 424-443.000.
- Productive Environments, Inc.: See—
Schwartz, David C., 5,586,829, Cl. 402-79.000.
- Professional Supply, Inc.: See—
Kiser, Thomas E., 5,586,932, Cl. 454-229.000.
- Pronega Corporation: See—
Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stehnitz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.
- Protheroe, Robert L.: See—
Crooks, John F.; and Protheroe, Robert L., 5,587,560, Cl. 178-18.000.
- Pruehs, Allen V.: See—
Robinson, Darrell; Loehr, Karl; Pruehs, Allen V.; and Learmont, Robert O., 5,586,913, Cl. 439-638.000.
- Puar, Deepraj S.: See—
Ranganathan, Ravi; and Puar, Deepraj S., 5,587,672, Cl. 326-93.000.
- Puett, Edwin E., Jr.: See—
Diederiks, Everett G., Jr.; and Puett, Edwin E., Jr., 5,586,360, Cl. 15-410.000.
- Punto, Louis; Potini, Chim; Duque, Pilar; and Gould, Eva, to R.P. Scherer Corporation. Topical application emulsions. 5,587,149, Cl. 424-59.000.
- Putnam, Matthew D.; and Gesensway, David, to University of Minnesota. Regents of the. Method and apparatus for fixation of distal radius fractures. 5,586,985, Cl. 606-69.000.
- Putzmeister-Werk Maschinenfabrik GmbH: See—
Benckert, Hartmut; and Muenzenmaier, Werner, 5,586,869, Cl. 417-218.000.
- Puzikov, Gennady S.: See—
Skoblev, Valery V.; Shixin, Mikhail A.; Selezov, Evgeny A.; Kabakov, Viktor G.; and Puzikov, Gennady S., 5,586,872, Cl. 417-477.800.
- Qualcomm Incorporated: See—
Tiedemann, Edward G., Jr.; Karmi, Gad; and Quick, Frank, 5,588,043, Cl. 379-63.000.
- Quantic Industries, Inc.: See—
Willis, Kenneth E.; Fahey, William D.; and Whang, David S., 5,587,550, Cl. 102-217.000.
- Quantum Chemical Corporation: See—
DiMaio, Anthony J., 5,587,439, Cl. 526-142.000.
- Klimek, Thaddeus W.; and Edwards, Michael B., 5,587,436, Cl. 526-59.000.
- Quantum Corporation: See—
Ton-that, Luam, 5,587,850, Cl. 360-77.080.
- Quick, Frank: See—
Tiedemann, Edward G., Jr.; Karmi, Gad; and Quick, Frank, 5,588,043, Cl. 379-63.000.
- QuickLogic Corporation: See—
Chan, Andrew K.; Birkner, John M.; and Chua, Hua T., 5,587,669, Cl. 326-38.000.
- Quinn, Joseph: See—
Lynch, Gerard J.; and Quinn, Joseph, 5,587,074, Cl. 210-411.000.
- Quinn, Wilma W.: See—
Murray, Bruce S.; Noble, Howard C.; and Quinn, Wilma W., 5,587,615, Cl. 310-30.000.
- Quint, Jeffrey T. Aquatic exercise equipment. 5,586,961, Cl. 482-111.000.
- Qureshi, Amjad Z.: See—
Hardell, William R., Jr.; and Qureshi, Amjad Z., 5,588,010, Cl. 371-37.600.
- R.P. Scherer Corporation: See—
Punto, Louis; Potini, Chim; Duque, Pilar; and Gould, Eva, 5,587,149, Cl. 424-59.000.
- Rabeyrin, Michel: See—
Chevallier, Yvonick; and Rabeyrin, Michel, 5,587,416, Cl. 524-492.000.
- Rabovsky, Alexander B.: See—
Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P.; deceased, 5,587,295, Cl. 435-11.000.
- Radar, Elizabeth; and Radar, James R. Dual field pack. 5,586,703, Cl. 224-601.000.
- Radar, James R.: See—
Radar, Elizabeth; and Radar, James R., 5,586,703, Cl. 224-601.000.
- Radford, Neal T.; and Waddle, Roy J. Handheld density meter. 5,587,527, Cl. 73-439.000.
- Rachse, Wilfried: See—
Zeise, Christiane; Rachse, Wilfried; Jacobs, Jochen; and Hoffmeister, Juergen, 5,587,104, Cl. 510-298.000.
- Raff, Lothar: See—
Schnabel, Eberhard; Raff, Lothar; and Hirschmann, Klaus, 5,586,543, Cl. 123-696.000.
- Rainey, Randy E.: See—
Hartman, Michael O.; Kinder, Dale J.; Rainey, Randy E.; Helmich, Arthur R.; and Willis, Daniel E., 5,587,055, Cl. 203-1.000.
- Rakitsch, Peter; and Zehentbauer, Hans, to MAN Roland Druckmaschinen AG. Photoelectric measuring head for the contactless scanning of measuring fields on a printing sheet with an air permeable annular disk. 5,587,796, Cl. 356-445.000.
- Ralf Korman Associates, Inc.: See—
Korman, Ralf; Korman, Vera; Korman, Michael; and Korman, Dennis, 5,587,237, Cl. 428-255.000.
- Ralph, James D.: See—
Errico, Joseph P.; Errico, Thomas J.; and Ralph, James D., 5,586,984, Cl. 606-61.000.
- Raman, Balan: See—
Neeman, Yuval; Cook, Peter; Miller, Arnold S.; and Raman, Balan, 5,588,147, Cl. 395-601.000.
- Raman, Venkat A., to Whitaker Corporation. The. Electrical connector jack with encapsulated signal conditioning components. 5,587,884, Cl. 361-728.000.
- Ramasamy, Kanda S.: See—
Cook, Phillip D.; Ramasamy, Kanda S.; and Manoharan, Muthiah, 5,587,469, Cl. 536-23.100.
- Ramesh, Doraiswamy: See—
Hess, George P.; Carpenter, Barry K.; Ramesh, Doraiswamy; and Wieboldt, Raymond, 5,587,509, Cl. 560-130.000.
- Ramezani, Ezzatollah: See—
Jaeklin, André; Ramezani, Ezzatollah; Roggwiller, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.
- Ramsey, Keith M.: See—
Cloyd, Miles W.; and Ramsey, Keith M., 5,587,285, Cl. 435-5.000.
- Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., to Motorola, Inc. Package for mating with a semiconductor die. 5,587,605, Cl. 257-666.000.
- Ran, Xiaonong: See—
Choo, Chang Y.; Ran, Xiaonong; Porter, Christine A.; and Motamedi, Mohammad R., 5,587,710, Cl. 341-107.000.
- Randolph, Gary: See—
Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364-510.000.
- Ranganathan, Ravi; and Puar, Deepraj S., to NeoMagic Corp. Dynamic logic having power-down mode with periodic clock refresh for a low-power graphics controller. 5,587,672, Cl. 326-93.000.
- Rapp, Joseph A.: See—
Mast, Donald R.; McNabb, Robert L.; and Rapp, Joseph A., 5,586,784, Cl. 280-756.000.
- Rasmussen GmbH: See—
Kirchner, Hary; Hohmann, Ralf; and Spors, Ralf, 5,586,791, Cl. 285-179.000.
- Rasmussen, John. Differential pressure sensing device for pneumatic cylinders. 5,587,536, Cl. 73-744.000.
- Rathjen, Deborah A.; and Ferrante, Antonio, to Peptide Technology Limited. Neutrophil stimulating peptides. 5,587,457, Cl. 530-326.000.
- Rautaruukki Oy: See—
Alander, Casper; and Mononen, Tarmo, 5,586,418, Cl. 52-450.000.
- Ray, Andrew E.: See—
Branner, Donald L.; Ray, Andrew E.; Peters, Scott M.; and Huber, Richard M., 5,587,706, Cl. 340-825.440.
- Ray, Partha S.: See—
Hennie, Robert N.; H. Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chaguturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.
- Raymond, Anthony E. Swatter and method of using the same. 5,586,407, Cl. 43-137.000.
- Raynes, Edward P.: See—
May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harrold, Jonathan, 5,587,820, Cl. 359-72.000.
- Rayovac Corporation: See—
Dopp, Robert B.; Oltman, John E.; and Passaniti, Joseph L., 5,587,259, Cl. 429-233.000.
- Ward, Thomas F.; and Smith, Grant W., 5,586,657, Cl. 206-705.000.
- Rebholz, Clemens: See—
Novak, Pavel; and Rebholz, Clemens, 5,586,873, Cl. 417-477.800.

- Reddin, Timothy G.; Walsh, David S., and Round, Jeremy S., to International Computers Limited. Parallel computer having MAC-relay layer snooped transport header to determine if a message should be routed directly to transport layer depending on its destination. 5,588,121, Cl. 395-200.150. Reddy, Kasireddy C.: See—
Patel, Mahendra R.; Reddy, Kasireddy C.; and Dave, Pankaj J., 5,587,377, Cl. 514-254.000.
- Reed, James L.: See—
Eby, Devon; Love, Dale; and Reed, James L., 5,586,373, Cl. 24-525.000.
- Reedy, Ronald E.; Garcia, Graham A.; and Lagnado, Isaac, to United States of America. Navy. Semiconductor-on-insulator device interconnects. 5,587,597, Cl. 257-351.000.
- Reeve, Lorraine E.: See—
Viegas, Tacey X.; Reeve, Lorraine E., and Henry, Raymond L., 5,587,175, Cl. 424-427.000.
- Regan, Francis A. Storm sewer outlet filter. 5,587,072, Cl. 210-232.000.
- Regents, University of California.: See—
Leung, Ka-Ngo; Wells, Russell P.; and Craven, Glen E., 5,587,226, Cl. 428-210.000.
- Regina Sud S.p.A.: See—
Coen, Daniele; and Garbagnati, Carlo, 5,586,644, Cl. 198-853.000.
- Rehorn, Don W. Passenger restraint system. 5,586,503, Cl. 104-241.000.
- Reichert, Jürgen.: See—
Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, 5,587,421, Cl. 524-591.000.
- Reichert, Uwe; Schmidt, Rainer; and Shroot, Brahm, to Centre International de Recherches Dermatologiques Galderma (CIRD Galderma). Pharmaceutical or cosmetic composition containing a combination of a retinoid and a steroid. 5,587,367, Cl. 514-171.000.
- Reif, Joachim.: See—
Adam, Paul; Tillmann, Heinz; deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dolling, Uwe, 5,586,783, Cl. 280-737.000.
- Reitz, Paul; and Abdelkader, Hatem, to Whitaker Corporation. The Polarization controlled tuneable ring laser. 5,588,013, Cl. 372-19.000.
- Reluzco, George.: See—
Knorowski, Victor J.; Reluzco, George; Robertson, Kenneth J., and Adamkoski, Paul L., 5,586,864, Cl. 415-209.200.
- Remsing, David A.: See—
Dorner, Wolfgang C.; Hoesch, Michael A.; Danelski, Darin L., and Remsing, David A., 5,586,685, Cl. 221-197.000.
- Renken, Martin C.: See—
McCloskey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II, and Light, Glenn M., 5,587,534, Cl. 73-623.000.
- Renn, Peter.: See—
Adam, Paul; Tillmann, Heinz; deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dolling, Uwe, 5,586,783, Cl. 280-737.000.
- Rent, Michael P. Chime alarm apparatus. 5,587,697, Cl. 340-392.400.
- Renz, Hans.: See—
Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, 5,587,421, Cl. 524-591.000.
- ReplicaTech, Inc.: See—
Chrebet, Gary L., 5,587,322, Cl. 435-309.400.
- Research Development Corporation of Japan.: See—
Koide, Norikatsu; Yamazaki, Shiro; Umezaki, Junichi, and Asami, Shinya, 5,587,593, Cl. 257-94.000.
- Research Foundation of State University of New York.: See—
Anderson, Wayne A.; Jia, Quanxi; Yi, Junsun; and Chang, Lin-Huang, 5,587,870, Cl. 361-313.000.
- Retting, Wolfgang J.; Scanlan, Matthew J.; Garin-Chesa, Pilar; and Old, Lloyd J., to Memorial Sloan-Kettering Cancer Center. Isolated nucleic acid molecule coding for fibroblast activation protein alpha and uses thereof. 5,587,299, Cl. 435-69.100.
- Reynolds Metals Company.: See—
Sirear, Subhashish, 5,587,029, Cl. 148-438.000.
- Reynolds, Patricia A.: See—
Acosta, Phyllis J. B.; Grondalski, Richard A.; Liebrecht, Jeffrey W.; and Reynolds, Patricia A., 5,587,399, Cl. 514-561.000.
- Rhinesmith, Robert, to Colgate-Palmolive Co. Liquid cleaning compositions. 5,587,357, Cl. 510-417.000.
- Rho, Hwan-chul; Choi, Hong-gyu; and Kim, Jae-myung, to Samsung Display Devices Co., Ltd. Filming composition for cathode ray tube and method of manufacturing screen using the same. 5,587,201, Cl. 427-64.000.
- Rhodes, Robert P., to Hewlett-Packard Company. Thermal conductivity detector. 5,587,520, Cl. 73-25.030.
- Rhone-Poulenc Chimie.: See—
Chevallier, Yvonick; and Rabeyrin, Michel, 5,587,416, Cl. 524-492.000.
- Denis, Philippe; Patois, Carl; and Perron, Robert, 5,587,056, Cl. 203-29.000.
- Rhone-Poulenc Rorer S.A.: See—
Bouchard, Hervé; Bourzat, Jean-Dominique; and Commercon, Alain, 5,587,493, Cl. 549-510.000.
- Ricard, Pernod.: See—
Guezennec, Yannick; Kotzet, Joseph; and Thiry, Michel, 5,587,190, Cl. 426-2.000.
- Rice, Wendell A.: See—
Gledde, Sanford C.; Leggett, Mary E.; Rice, Wendell A.; and Olsen, Perry E., 5,586,411, Cl. 47-57.600.
- Richard, Hervé; Leduc, Madeleine; and LaGrange, Alain, to L'Oreal. Photoprotective/cosmetic compositions comprising oxanilido-substituted polyorganosiloxanes/polyorganosilanes. 5,587,151, Cl. 424-59.000.
- Richard, Hervé.: See—
Deflandre, André; Dubois, Michel; Forestier, Serge; and Richard, Hervé, 5,587,150, Cl. 424-59.000.
- Richards, Martin J.: See—
Goldberg, Paul R.; and Richards, Martin J., 5,587,749, Cl. 352-27.000.
- Richardson, Bernard D.: See—
Chen, Kuo-Raid G.; Misner, Raymond H.; Windham, Elbert P., and Richardson, Bernard D., 5,586,424, Cl. 53-138.200.
- Richarz, Werner.: See—
Yazici, Muammer; and Richarz, Werner, 5,587,563, Cl. 181-224.000.
- Rickard, Wayne T., to Emulex Corporation. Apparatus for reordering data frames within an interface device. 5,588,000, Cl. 370-428.000.
- Ricoh Company, Ltd.: See—
Fumita, Toshiyuki; Motomura, Shuji; Watanabe, Takahiro; and Stork, David G., 5,588,090, Cl. 395-23.000.
- Orake, Masahiro; Takahashi, Toyofumi; Nishiumi, Satoshi; and Otsuki, Takashi, 5,587,723, Cl. 345-118.000.
- Shibaguchi, Takashi, 5,587,826, Cl. 359-216.000.
- Tanaka, Chiaki; Sasaki, Masao; Aruga, Tamotsu; Shimada, Tomoyuki; and Adachi, Hiroshi, 5,587,516, Cl. 564-405.000.
- Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500.000.
- Riding, George A.: See—
Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srikantha, Alagaccone; and Riding, George A., 5,587,311, Cl. 435-240.200.
- Ries, Uwe.: See—
Narr, Berthold; Haeufel, Norbert; Van Meel, Jacques; Wiene, Wolfgang; Entzeroth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381.000.
- Rieter Ingolstadt Spinnereimaschinenbau AG.: See—
Pohn, Romeo; and Schuller, Edmund, 5,586,427, Cl. 57-264.000.
- Riggle, C. M., to Riggle, C. M. Tuned viterbi detector and equalizer system. 5,588,011, Cl. 371-43.000.
- Riggle, C. M.; and DeForest, Marvin, to Maxtor Corporation. Apparatus and method for the synchronization of data in a bit stream. 5,588,030, Cl. 375-368.000.
- Riley, David R., to Gately, Stanley E.; and Gately, Catherine G. Optimizer measuring unit. 5,586,558, Cl. 128-781.000.
- Rim, Kyung-hwa.: See—
Yoo, Jang-boon; Rim, Kyung-hwa; Chung, Chong-sam; and Lee, Chul-woo, 5,587,976, Cl. 369-13.000.
- Rimsa, Stephen.: See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrachala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- Rinderer, Eric R., to B-Line Systems, Inc. Conductor holding device. 5,587,555, Cl. 174-49.000.
- Rinehart, John R., to American Institute of Taxidermy, Inc. Portable combination seat and container. 5,586,805, Cl. 297-188.000.
- Riso Kagaku Corporation.: See—
Shimada, Shingo, 5,586,497, Cl. 101-128.400.
- Ritola, Dan E.: See—
Alcini, Raymond R., and Ritola, Dan E., 5,586,465, Cl. 72-441.000.
- Rison, John D. Battery connector. 5,586,919, Cl. 439-757.000.
- Ritzheim, Mary E. Waist bag. 5,586,706, Cl. 224-671.000.
- Roime, James B. Rotary handpiece for endodontic instruments. 5,586,886, Cl. 433-224.000.
- Robert Bosch GmbH.: See—
Hoetzel, Juergen, 5,587,938, Cl. 364-578.000.
- Phizemmer, Heinz; Blakelock, Philip; Prime, Brian; and Dawson, David, 5,587,713, Cl. 342-7.000.
- Schnaibel, Eberhard; Raff, Lothar; and Hirschmann, Klaus, 5,586,543, Cl. 123-696.000.
- Schneider, Thomas; Grieser-Schmitz, Stefan; and Walther, Michael, 5,587,661, Cl. 324-556.000.
- Robert Krups GmbH & Co. KG.: See—
Baumann, Heinrich, 5,586,485, Cl. 99-295.000.
- Roberts, Gerald E.; and Roberts, Michael E., to XTAL Technologies, Ltd. Method for measuring the inductance of each resonator of a coupled-dual resonator crystal. 5,587,663, Cl. 324-727.000.
- Roberts, Michael E.: See—
Roberts, Gerald E.; and Roberts, Michael E., 5,587,663, Cl. 324-727.000.
- Roberts, Randall W.: See—
McSwiggen, John P.; and Roberts, Randall W., 5,588,064, Cl. 381-69.200.
- Robertson, Brian W.: See—
Curicuta, Victor; Alexander, Dennis R.; Deangelis, Robert J.; and Robertson, Brian W., 5,586,714, Cl. 228-122.100.
- Robertson, Kenneth J.: See—
Knorowski, Victor J.; Reluzco, George; Robertson, Kenneth J.; and Adamkoski, Paul L., 5,586,864, Cl. 415-209.200.
- Robinson, Darrell; Loehr, Karl; Pruehs, Allen V.; and Learmont, Robert O., to Ekstrom Industries, Inc. S to B watt-hour meter socket adapter. 5,586,913, Cl. 439-638.000.
- Robinson, Michael G.: See—

- May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harrold, Jonathan, 5,587,820, Cl. 359-72.000.
- Robl, Jeffrey A., to Bristol-Myers Squibb Company. Azepinone compounds useful in the inhibition of ACE and NEP. 5,587,375, Cl. 514-213.000.
- Rockefeller University, The.: See—
Cheung, Ambrose; and Fischetti, Vincent A., 5,587,288, Cl. 435-6.000.
- Rockwell International Corp.: See—
Mulbrook, Mark M., 5,587,688, Cl. 330-253.000.
- Woodard, Jeffrey P., 5,587,910, Cl. 364-443.000.
- Roggwiller, Peter.: See—
Jaacklin, André; Ramezani, Ezatollah; Roggwiler, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.
- Rogler, Wolfgang.: See—
von Gentz/kow, Wolfgang; Huber, Jürgen; Kapitzka, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jörg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413.000.
- Rogosin Institute, The.: See—
Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., 5,587,366, Cl. 514-78.000.
- Rohm Corporation.: See—
Chang, Shang-De; Chang, Jia-Hwang; and Chow, Edwin, 5,587,947, Cl. 365-185.300.
- Röhrig, Lothar.: See—
Sulzbach, Hans-Michael; and Röhrig, Lothar, 5,587,182, Cl. 425-4.000.
- Rolle, David B.: See—
Dapp, Michael C.; Barker, Thomas N.; Dielfenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J., 5,588,152, Cl. 395-800.000.
- Roll Systems, Inc.: See—
Goliz, Roman M., 5,586,710, Cl. 227-155.000.
- Rolls-Royce PLC.: See—
Bowen, David K.; and Thomas, Charles R., 5,588,034, Cl. 378-73.000.
- Romedier, Peter.: See—
Stadler, Maximilian; Schwab, Günter; Romedier, Peter; and Trifellner, Gabriele, 5,587,046, Cl. 156-662.100.
- Rongce, Catherine; Mail, Alain; and Marot, Yves, to L'Air Liquide, Société Anonyme pour l'Étude et l'Exploitation des Procédés Georges Claude. Process and device for supplying gas to an analyzer of traces of impurities in a gas. 5,587,519, Cl. 73-1.000.
- Rongved, Pål.: See—
Almén, Torsten; Berg, Arne; Dugstad, Harald; Klaveness, Jo; Krautwurst, Klaus D.; and Rongved, Pål, 5,587,144, Cl. 424-9.361.
- Rosch, Hans J.; and Beck, Steven R., to TIC United Corp. Bulk hopper tank lid opener assembly. 5,586,678, Cl. 220-263.000.
- Rose, Douglas N., to United States of America, Army. Method of measuring crack propagation in opaque materials. 5,587,532, Cl. 73-579.000.
- Rosenblitt, David A.: See—
Bai, Baocheng; Guner, Mahmut; Lu, Duoqia; Rosenblitt, David A.; and Stuck, Kaaren L., 5,588,138, Cl. 395-497.040.
- Rosengren, Lars; and Enricsson, Ingemar, to Rosengren Teknik AB. Interface for simulating a telephone line connection between two devices for establishing a communication path between the devices. 5,588,047, Cl. 379-100.000.
- Rosengren Teknik AB.: See—
Rosengren, Lars; and Enricsson, Ingemar, 5,588,047, Cl. 379-100.000.
- Rosich, Mitchell N.; and Lippitt, William L., to Digital Equipment Corporation. Page mode and nibble mode DRAM. 5,587,964, Cl. 365-238.500.
- Rösler, Jörg.: See—
Heubusch, Harald; and Rösler, Jörg, 5,586,506, Cl. 105-3.000.
- Ross, Cynthia L.: See—
Besse, Michael E.; Ross, Cynthia L.; and Kleaver, Helen A., 5,587,009, Cl. 106-244.000.
- Rossi, Markku J., to Compaq Computer Corporation. Automatic system for handling batteries. 5,587,924, Cl. 364-496.000.
- Rossi, Tino.: See—
Perboni, Alcide; Rossi, Tino; Gaviraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonello, 5,587,374, Cl. 514-210.000.
- Rote, Donald M.: See—
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cal, Yigang, 5,586,504, Cl. 104-282.000.
- Rothamel, Karl; Lenhardt, Lorenz; and Kühn, Gottfried, to Hofmann Werkstatt-Technik GmbH. Apparatus and method for correcting unbalance on a motor vehicle wheel. 5,587,528, Cl. 73-462.000.
- Rothman, Miles S.: See—
Zabron, Florian S.; Marlette, Mary E.; Rothman, Miles S.; and Hanrahan, William D., 5,586,643, Cl. 198-853.000.
- Rotta Research Laboratorum S.p.A.: See—
Makovec, Francesco; Rovati, Lucio C.; and Rovati, Luigi A., 5,587,479, Cl. 544-70.000.
- Rotte, Jan J.: See—
Bergen, Franciscus H. M.; Rotte, Jan J.; Nijssen, Stephanus J. J.; and De Wit, Peter H. N., 5,587,802, Cl. 386-26.000.
- Round, Jeremy S.: See—
Reddin, Timothy G.; Walsh, David S.; and Round, Jeremy S., 5,588,121, Cl. 395-200.150.
- Roussel Uclaf.: See—
Aszodi, Josef; Chantot, Jean-François; Fauveau, Patrick; D'Ambrières, Solange G.; Hunbert, Daniel; and Dini, Christophe, 5,587,372, Cl. 514-202.000.
- Rovati, Lucio C.: See—
Makovec, Francesco; Rovati, Lucio C.; and Rovati, Luigi A., 5,587,479, Cl. 544-70.000.
- Rovati, Luigi A.: See—
Makovec, Francesco; Rovati, Lucio C.; and Rovati, Luigi A., 5,587,479, Cl. 544-70.000.
- Rowley, Michael V.; Warkentin, Douglas D.; and Piroshco, Beverly M. Process for treating solutions containing sulfate and metal ions. 5,587,079, Cl. 210-603.000.
- Roy, Carl W.; and Tschiderer, Paul E., to Eastman Kodak Company. Cutting apparatus for cutting an image from a receiving sheet. 5,586,479, Cl. 83-74.000.
- Roy, Timothy A.; Mackerer, Carl R.; and Goldstein, Lawrence, to Mobil Oil Corporation; and Electric Power Research Institute, Inc. Process for coal tar remediation. 5,587,324, Cl. 436-183.000.
- Roychowdhury, Suranjana, to Schneider (USA) Inc. Non-coextrusion method of making multi-layer angioplasty balloons. 5,587,125, Cl. 264-515.000.
- Rozman, Gregory I., to Sundstrand Corporation. VSCF start system with precise voltage control. 5,587,641, Cl. 318-801.000.
- Rubin, Albert L.: See—
Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., 5,587,366, Cl. 514-78.000.
- Rubin, Jeffrey; Hayek, Alberto; Beattie, Gillian M.; and Otonkoski, Timo P. J., to United States of America, Health and Human Services; and Whinler Institute for Diabetes and Endocrinology. Method of stimulating proliferation and differentiation of human fetal pancreatic cells ex vivo. 5,587,309, Cl. 435-240.200.
- Ruby, Richard C.; and Merchant, Paul P., to Hewlett-Packard Company. Tunable thin film acoustic resonators and method for making the same. 5,587,620, Cl. 310-346.000.
- Rudolph, Kenneth G.: See—
Borsboom, Antonius H.; Gennari, Anthony A.; Rudolph, Kenneth G.; and Zuber, Peter J., 5,586,675, Cl. 220-6.000.
- Ruegg, Andreas.: See—
Jaacklin, André; Ramezani, Ezatollah; Roggwiler, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.
- Ruffini, Robert S.; Madeira, Robert J.; and Ruffini, Robert T., to Fluxtrol Manufacturing, Inc. High performance induction melting coil. 5,588,019, Cl. 373-152.000.
- Ruffini, Robert T.: See—
Ruffini, Robert S.; Madeira, Robert J.; and Ruffini, Robert T., 5,588,019, Cl. 373-152.000.
- Runnoe, Dennis H.: See—
Christean, Paul G., and Runnoe, Dennis H., 5,588,035, Cl. 378-132.000.
- Rupert, Martha L.: See—
Baker, Ronald J.; Fisher, Douglas G.; Rupert, Martha L.; and Swartz, David M., 5,586,915, Cl. 439-733.100.
- Ruschmann, Robert M. Stretch adornments. 5,587,213, Cl. 428-12.000.
- Rushmore Vehicle Restraints, L.L.C.: See—
Kissel, James L.; Dailey, Earl J.; and Dolan, Daniel E., 5,586,849, Cl. 410-10.000.
- Russell A Division Of Arco, Inc.: See—
Wilson, Wilbert J.; and O'Neal, Robert G., 5,586,441, Cl. 62-99.000.
- Russell, Stephen P.: See—
Oneto, John C.; and Russell, Stephen P., 5,588,134, Cl. 395-485.000.
- Russo, Peter J. Multifunction swimsuit and casual wear undergarment. 5,586,340, Cl. 2-67.000.
- Rutgers, The State University.: See—
Kohn, Joachim B.; and Hooper, Kimberly A., 5,587,507, Cl. 560-40.000.
- Ryan, Thomas P.; and Stelzer, Glen A., to Amco Engineering Co. Computer organizer enclosure and method. 5,587,877, Cl. 361-683.000.
- S. C. Johnson & Son, Inc.: See—
Sandvick, Paul E.; and Verbrugge, Calvin J., 5,587,202, Cl. 427-155.000.
- S GS - Microelectronics Limited.: See—
Chowdhury, Vivek, 5,587,676, Cl. 327-108.000.
- Saal, Stuart D.: See—
Parker, Thomas S.; Levine, Daniel M.; Rubin, Albert L.; Gordon, Bruce R.; and Saal, Stuart D., 5,587,366, Cl. 514-78.000.
- Saha, Toshikazu, to Sumitomo Wiring Systems, Ltd. Sealing structure for a panel-mounted electrical connector. 5,586,909, Cl. 439-559.000.
- Sacchi, Gianpiero.: See—
Marzolini, Fausto; Calmanti, Giulio; and Sacchi, Gianpiero, 5,587,049, Cl. 162-40.000.
- Sacherman, Jim. Edge connector for securing a mountable electronic component to a device with receiving apertures for edge connector. 5,587,889, Cl. 361-809.000.
- Sachetto, Jean-Pierre.: See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrachala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.
- Sadler, William R. Vehicle cargo carrier. 5,586,702, Cl. 224-521.000.
- Saegusa, Hiroyuki, to Honda Giken Kogyo Kahushiki Kaisha. Curved window glass panel and method of installing curved window glass panel on automobile body. 5,586,798, Cl. 296-146.150.
- Sagawa, Morikazu.: See—
Yabuki, Hiroyuki; Sagawa, Morikazu; and Makimoto, Mitsuo, 5,587,690, Cl. 331-2.000.

Saindon, Stephen A.; Gietman, Peter J., Jr.; and Nagel, Nicholas J., to CMD Corporation, Method and apparatus for registration of a seal on a plastic bag, 5,587,032, Cl. 156-64,000.

Saito, Hiroshi; Suzuki, Yasumichi; and Tamura, Naoyuki, to Hitachi, Ltd., Plasma processing method and an apparatus for carrying out the same, 5,587,205, Cl. 427-553,000.

Saito, Hitoshi: *See*—
Taniguchi, Kazuko; Ikegawa, Akihito; Uno, Koji; and Saito, Hitoshi, 5,587,775, Cl. 355-219,000.

Saito, Ken; Hinotsu, Naoyoshi; Sakamoto, Hikaru; and Hoshino, Koichi, to Furukawa Denchi Kabushiki Kaisha, Sealed storage battery and manufacturing method thereof, 5,586,993, Cl. 29-623,200.

Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, to Mitsubishi Denki Kabushiki Kaisha, Planar display apparatus having exposed insulated substrate portion, 5,587,627, Cl. 315-169,100.

Saito, Noriyuki: *See*—
Komiya, Hirofumi; Sakai, Keita; Koshi, Kazumine, and Saito, Noriyuki, 5,588,092, Cl. 395-109,000.

Saito, Shozo: *See*—
Toda, Haruki; Saito, Shozo; and Tokushige, Kaoru, 5,587,963, Cl. 365-236,000.

Saito, Takayoshi: *See*—
Arai, Tatsuo; and Saito, Takayoshi, 5,586,845, Cl. 407-113,000.

Saito, Toshiaki: *See*—
Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chienji; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, 5,587,197, Cl. 426-658,000.

Saitou, Mitsuo; Yamanouchi, Junichi; and Hosoya, Yoichi, to Fuji Photo Film Co., Ltd., Method for producing silver halide grain and silver halide emulsion using the grain, 5,587,281, Cl. 430-567,000.

Sajatovic, James N., to Ingersoll-Rand Company, Kelly bar having hardened flutes, 5,586,610, Cl. 175-195,000.

Sak, Cheryl: *See*—
Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vneski, James, 5,587,926, Cl. 364-510,000.

Sakagami, Makoto: *See*—
Hori, Satoshi; Omori, Teruyo; and Sakagami, Makoto, 5,587,930, Cl. 364-551,010.

Sakaguchi, Noboru: *See*—
Kawabe, Yuzo; and Sakaguchi, Noboru, 5,586,734, Cl. 242-247,000.

Sakaguchi, Shozo; Ikeda, Mitsuhiro; and Chiba, Syusaku, Master cylinder reservoir, 5,586,436, Cl. 60-585,000.

Sakaguchi, Yasunobu: *See*—
Yamamoto, Takashi; Sakaguchi, Yasunobu; and Utsugi, Makoto, 5,587,768, Cl. 355-41,000.

Sakai, Hiroshi, to Colin Corporation, Physical-information detecting system, 5,586,552, Cl. 128-633,000.

Sakai, Hiroshi; and Ohnaka, Kazuo, to Yazaki Corporation, Connector fastening nut and bolt-nut fastened connector, 5,586,854, Cl. 411-429,000.

Sakan, Izumi, to National Laboratory for High Energy Physics, Injection apparatus both for positive and negative ions, 5,587,632, Cl. 315-507,000.

Sakai, Keita: *See*—
Komiya, Hirofumi; Sakai, Keita; Koshi, Kazumine, and Saito, Noriyuki, 5,588,092, Cl. 395-109,000.

Sakai, Michio; Hosoya, Ryosuzou; Orito, Nobuyuki; and Nakahata, Minoru, to Mitsubishi Denki Kabushiki Kaisha, Distributor, 5,587,873, Cl. 361-603,000.

Sakai, Tsukasa: *See*—
Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Kenichi, 5,587,798, Cl. 358-261,100.

Sakazawa, Katsuhiko: *See*—
Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiko; Kugo, Harumi; Sakazawa, Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, 5,587,773, Cl. 355-210,000.

Sakaki, Toshiaki; and Nakade, Shinichi, to Sumitomo Rubber Industries, Ltd., Rubber composition and method of producing rubber products using the same composition, 5,587,411, Cl. 524-17,000.

Sakamoto, Hikaru: *See*—
Saito, Ken; Hinotsu, Naoyoshi; Sakamoto, Hikaru; and Hoshino, Koichi, 5,586,993, Cl. 29-623,200.

Sakamoto, Masashi: *See*—
Sawada, Kenji; Sato, Masahiro; Sekino, Hitoshi; and Sakamoto, Masashi, 5,587,769, Cl. 355-200,000.

Shibata, Mitsuru; Sakamoto, Masashi; and Nasuno, Ichiro, 5,587,484, Cl. 548-364,400.

Sakanishi, Ei; and Kitahara, Kiyoshi, to Citizen Watch Co., Ltd., Font data compression method in a character generator, 5,587,725, Cl. 345-195,000.

Sako, Yoichiro: *See*—
Yamagami, Tamotsu; Sako, Yoichiro; and Yamamoto, Masanobu, 5,587,901, Cl. 369-275,300.

Sakoh, Harumi: *See*—
Fukushima, Hisashi; Takeuchi, Tatsuo; Sakoh, Harumi; and Sasanuma, Nobuatsu, 5,587,778, Cl. 355-246,000.

Sakuma, Choji: *See*—
Ikeda, Susumu; Isobe, Toshiaki; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156,000.

Sakuma, Kiyoshi: *See*—

Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320,000.

Sakurai, Kensuke: *See*—
Konoike, Toshiro; Araki, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Kensuke; and Tozoy, Takehiko, 5,587,505, Cl. 558-272,000.

Salcedo, Jose A., to Exar Corporation, Power down circuit for use in integrated circuits, 5,587,684, Cl. 327-538,000.

Salimbeni, Aldo; Palcari, Fabio; Mizrahi, Jacques; and Scolastico, Carlo, to Istituto Luso Farmaco D'Italia S.p.A., Imidazole derivatives having a II antagonist activity, 5,587,390, Cl. 514-341,000.

Salimian, Siamak; Delfino, Michelangelo; and Chung, Bu-Chin, to Varian Associates, Inc., Plasma etch equipment, 5,587,039, Cl. 156-345,000.

Salisbury, J. Kenneth, Jr.: *See*—
Massie, Thomas H.; and Salisbury, J. Kenneth, Jr., 5,587,937, Cl. 364-578,000.

Salk Institute For Biological Studies, The: *See*—
Behan, Dominic P.; Vale, Wylie W., Jr.; Fischer, Wolfgang H.; and Lowry, Philip J., 5,587,462, Cl. 530-350,000.

Salmon, Brian: *See*—
Babey, Jacques; Salmon, Brian; De Borst, Eric; and Tallier, Bernard, 5,586,565, Cl. 131-84,200.

Salomon S.A.: *See*—
Benoit, Louis, 5,586,367, Cl. 24-68,05K.

Salzburg, Herbert; Steinhoff, Georg; Gosch, Andreas; and Hufen, Gerd, to Bayer Aktiengesellschaft, Process for obtaining adipic acid, 5,587,511, Cl. 562-513,000.

Saman, Shukri T., to SGS-Thomson Microelectronics S.A., Combined CMOS and NPN output pull-up circuit, 5,587,677, Cl. 327-108,000.

Sanduck Sanggong Co., Ltd.: *See*—
Kim, Kwon K., 5,586,701, Cl. 224-243,000.

Samman, Amer M.: *See*—
Stevenson, Paul E.; Stephan, Craig H.; Samman, Amer M.; and Spangler, Leland J., 5,587,518, Cl. 73-1,000.

Samsung Display Devices Co., Ltd.: *See*—
Kim, Jong-min, 5,587,588, Cl. 257-10,000.

Lee, Si-Hyun, 5,587,818, Cl. 349-106,000.

Rho, Hwan-chul; Choi, Hong-gyu; and Kim, Jae-myung, 5,587,201, Cl. 427-64,000.

Samsung Electronics Co., Ltd.: *See*—
Choi, Tae-Young, 5,587,982, Cl. 369-58,000.

Jo, Hae-Seong; Ko, Chang-Kyung; and Lee, Dong-Ho, 5,587,770, Cl. 355-208,000.

Kim, Kwang-Kyu, 5,587,855, Cl. 360-97,020.

Lee, Jae-won, 5,587,822, Cl. 349-124,000.

Lim, Moo-Gil, 5,588,027, Cl. 375-330,000.

Moon, Byung-Joon; Cho, Sung-il; and Shin, Ki-ho, 5,587,804, Cl. 386-2,000.

Park, Ku-man, 5,587,805, Cl. 386-68,000.

Shin, Seong-ke; and Lee, Sangho, 5,588,054, Cl. 379-413,000.

Yoo, Jang-hoon; Rim, Kyung-hwa; Chung, Chong-sam; and Lee, Chul-woo, 5,587,976, Cl. 369-13,000.

Samsung Heavy Industries Co., Ltd.: *See*—
Cho, Hyung J., 5,586,577, Cl. 137-596,130.

Seo, Jeong Y.; and Song, Myung H., 5,586,536, Cl. 123-352,000.

Samuelson, Laurence S.: *See*—
Dorius, Lee K.; and Samuelson, Laurence S., 5,587,858, Cl. 360-103,000.

Sanada, Shimichi: *See*—
Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shimichi; and Kawata, Yasushi, 5,587,819, Cl. 349-106,000.

Sanada, Takashi: *See*—
Abe, Hiromu; Nagaoka, Kenji; and Sanada, Takashi, 5,587,427, Cl. 525-145,000.

Sanden Corporation: *See*—
Hashimoto, Kenji; and Matsumura, Yoshito, 5,586,874, Cl. 417-569,000.

Ikeda, Susumu; Isobe, Toshiaki; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156,000.

Tanaka, Hiroshi; and Hosoya, Kazuki, 5,586,598, Cl. 165-133,000.

Sander, Volker: *See*—
Kuhm, Peter; Schroeder, Christine; Sander, Volker; Lindener, Juergen; and De Riese-Meyer, Loert, 5,587,063, Cl. 205-173,000.

Sanders, Albert E.; and Sanders, James O., Bone clamp of shape memory material, 5,586,983, Cl. 606-61,000.

Sanders, James O.: *See*—
Sanders, Albert E.; and Sanders, James O., 5,586,983, Cl. 606-61,000.

Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meitz, Michael C.; Pirle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., to Bayer Corporation, and Iowa State University Research Foundation, Inc., Potent reproductive and respiratory syndrome virus antigen and processes for the preparation and use of said antigen in vaccines and diagnostics, 5,587,164, Cl. 424-218,100.

Sandia Corporation: *See*—
Hendrickson, Bruce A.; and Leland, Robert W., 5,587,922, Cl. 364-489,000.

Sandoz Ltd.: *See*—
van Holst, Gerrit J.; Kreuger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, 5,587,312, Cl. 435-240,460.

Sandusky, Donald A.; and Marchello, Joseph M., to United States of America, National Aeronautics and Space Administration, Composite prepreg application device, 5,587,041, Cl. 156-441,000.

Sandvick, Paul E.; and Verbrugge, Calvin J., to S. C. Johnson & Son, Inc., Repulpable hot melt polymer/fatty acid compositions for fibrous products, 5,587,202, Cl. 427-155,000.

Sandvik AB: *See*—
Nyman, Folke, 5,586,844, Cl. 407-105,000.

Sanijet Corporation: *See*—
Booth, John W., 5,587,023, Cl. 134-32,000.

Sano, Hiromi: *See*—
Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320,000.

Sano, Kousei; and Kadowaki, Shin-ichi, to Matsushita Electric Industrial Co., Ltd., Signal processing device for an optical information reproducing apparatus, 5,587,985, Cl. 369-124,000.

Sanshin Kogyo Kabushiki Kaisha: *See*—
Nonaka, Kimihiko; and Ohtani, Hiroaki, 5,586,524, Cl. 123-73,00A.

Santen, Augustinus: *See*—
Binsbergen, Frederik L.; Bos, Alouisius N. R.; and Santen, Augustinus, 5,587,438, Cl. 526-88,000.

Santner, Johannes: *See*—
Döbeling, Klaus; Santner, Johannes; and Steinbach, Christian, 5,586,878, Cl. 431-351,000.

Sanwa Kenna Kogyo Co., Ltd.: *See*—
Hayashi, Teruoki; and Shibai, Yoshio, 5,586,930, Cl. 451-548,000.

Sanyo Electric Co., Ltd.: *See*—
Nakakuki, Toshio, 5,587,746, Cl. 348-708,000.

Shitara, Yasuharu; Hayasaka, Noboru; and Kosuka, Toshiya, 5,588,120, Cl. 395-200,150.

Sartomer Company, Inc.: *See*—
Boeckeler, Rudolph H., 5,587,433, Cl. 525-333,200.

Sasada, Tetsuo: *See*—
Ishii, Hiroshi; Sasada, Tetsuo; Kasahara, Masayuki; Katoh, Yasuhiro; and Kashiwabara, Yasushige, 5,586,857, Cl. 415-23,000.

Sasaki, Keiji; and Koguchi, Masayuki, to Fujikoki Mfg. Co., Ltd., Pressure sensor including a pair of slidable contacts between a strain gage and a print circuit board, 5,587,535, Cl. 73-726,000.

Sasaki, Masaomi: *See*—
Tanaka, Chiaki; Sasaki, Masaomi; Aruga, Tamotsu; Shimada, Tomoyuki; and Adachi, Hiroshi, 5,587,516, Cl. 564-405,000.

Sasaki, Ryo; and Ina, Toshiro, to Nissan Motor Co., Ltd.; and TBL Co., Ltd., Thermosetting coating composition and coated body, 5,587,418, Cl. 524-504,000.

Sasaki, Sachio: *See*—
Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhiro; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219,000.

Sasaki, Shunji, to Takigien Manufacturing Co., Ltd., Embedded-type handle assembly, 5,586,795, Cl. 292-336,300.

Sasanuma, Nobuatsu: *See*—
Fukushima, Hisashi; Takeuchi, Tatsuo; Sakoh, Harumi; and Sasanuma, Nobuatsu, 5,587,778, Cl. 355-246,000.

Sasaoka, Michio: *See*—
Kawahara, Ichiro; Wada, Isao; and Sasaoka, Michio, 5,587,464, Cl. 534-558,000.

Sassen, Cornelis L., to Van den Bergh Foods Co., Division of Conopco, Inc., Plastic fat spread comprising a hardstock, 5,587,195, Cl. 426-607,000.

Sato, Akira; and Hatano, Takaji, to Minolta Camera Kabushiki Kaisha, Phase modulation holographic device for generating two different wavefronts, 5,587,815, Cl. 359-11,000.

Sato, Kaku: *See*—
Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kuguminato, Hideo, 5,587,027, Cl. 148-320,000.

Sato, Kanji: *See*—
Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kanji, 5,587,132, Cl. 423-62,000.

Sato, Kazuo: *See*—
Iguchi, Yutaka; Sato, Kazuo; Kobayashi, Toshihiro; and Sato, Masayuki, 5,587,529, Cl. 73-504,130.

Sato, Masahiro: *See*—
Sawada, Kenji; Sato, Masahiro; Sekino, Hitoshi; and Sakamoto, Masashi, 5,587,769, Cl. 355-200,000.

Sato, Masatoshi, to Tohoku Pioneer Electronic Corporation; and Pioneer Electronic Corporation, Diaphragm for electro-dynamic type loudspeakers, 5,587,562, Cl. 181-167,000.

Sato, Masayuki: *See*—
Iguchi, Yutaka; Sato, Kazuo; Kobayashi, Toshihiro; and Sato, Masayuki, 5,587,529, Cl. 73-504,130.

Sato, Masuhito: *See*—
Nakai, Toshiaki; Amano, Mitsuyoshi; Miyamoto, Kazuhiro; Akiba, Yoshiyuki; and Sato, Masuhito, 5,587,547, Cl. 84-645,000.

Sato, Minoru, to Casio Computer Co., Ltd., Electrically connecting structure, 5,586,892, Cl. 439-91,000.

Sato, Nobuyuki: *See*—
Yamaguchi, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500,000.

Sato, Shigehiro; Matsunaga, Yoshiyuki; Ono, Tsuyoshi; and Karube, Takaaki, to Toshiba Lighting & Technology Corporation, Fixing heater and method of manufacturing fixing heater, 5,587,097, Cl. 219-543,000.

Sato, Shinichiro; Akaza, Syunsuke; and Yoshino, Hiroyuki, to Casio Computer Co., Ltd., Object image display devices, 5,588,096, Cl. 395-135,000.

Sato, Tomohiro: *See*—
Ue, Makoto; Sato, Tomohiro; and Takeda, Masayuki, 5,587,871, Cl. 361-504,000.

Sato, Toshikuni; and Agematsu, Masaya, to Kabushiki Kaisha Toshiba, Case unit having a dual case structure formed by an outer case member and an inner case member for a disk storage apparatus, 5,587,854, Cl. 360-97,010.

Sato, Yuichi: *See*—
Inami, Daijiro; and Sato, Yuichi, 5,587,667, Cl. 326-17,000.

Satoh, Hideto, to Suzuki Motor Corporation, Automotive tool storage device, 5,586,698, Cl. 224-42,240.

Sauber, Klaus: *See*—
Then, Johann; Aretz, Werner; and Sauber, Klaus, 5,587,319, Cl. 435-280,000.

Saur, Reinhold: *See*—
Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schelberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63,000.

Sauter, Hubert: *See*—
Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schelberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63,000.

Sawada, Kenji; Sato, Masahiro; Sekino, Hitoshi; and Sakamoto, Masashi, to Minolta Co., Ltd., Image forming apparatus allowing simple replacement of intermediate transfer member and easy maintenance and handling of paper jams, 5,587,769, Cl. 355-200,000.

Sawada, Seiji; and Konishi, Yasuhiro, to Mitsubishi Denki Kabushiki Kaisha, Test circuit in clock synchronous semiconductor memory device, 5,587,950, Cl. 365-201,000.

Sawahata, Masatoshi: *See*—
Nakajima, Masato; Akahoshi, Toshiaki; Sawahata, Masatoshi; Nomura, Yutaka; and Sato, Kanji, 5,587,132, Cl. 423-62,000.

Sawatari, Norio: *See*—
Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhiro; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219,000.

Sawyer, Colin; Wallis, John; and Bartingale, Peter, to Hunter Technical Developments Limited, Heating, ventilating and air conditioning systems, 5,586,933, Cl. 454-299,000.

Sawyer, David R.; and Wheeler, Douglas M., to Newport News Shipbuilding and Dry Dock Company, Stud mounted hoist ring, 5,586,801, Cl. 294-1,100.

Sawyer, Roy T., to Merck Patent GmbH, Platelet adhesion inhibitor, 5,587,360, Cl. 514-21,000.

Scalce, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L., to Johnson & Johnson Clinical Diagnostics, Inc., Thermostable polymerase specific antibody-containing DNA amplification composition and kit, 5,587,287, Cl. 435-6,000.

Scanlan, Matthew J.: *See*—
Rettig, Wolfgang J.; Scanlan, Matthew J.; Garin-Chesa, Pilar; and Old, Lloyd J., 5,587,299, Cl. 435-69,100.

Scattergood, Roger, to Ethyl Petroleum Additives Limited, Dispersants for lubricating oil, 5,587,432, Cl. 525-327,600.

Scavitto, John A.: *See*—
Venooker, Ronald J.; Scavitto, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,590, Cl. 141-386,000.

Venooker, Ronald J.; Scavitto, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,673, Cl. 215-310,000.

Schaefer, Wolfgang: *See*—
Spaeh, Richard; Schaefer, Wolfgang; Stollen, Detlef; and Fandel, Marco, 5,587,251, Cl. 429-33,000.

Schattke, Thomas L.: *See*—
Lothamer, Thomas J.; Pontecorvo, Carl A.; Schattke, Thomas L.; and Osterhout, Richard A., 5,587,568, Cl. 200-16,000.

Schauer, Friedrich; and Neuner, Andreas, to kabelmetal electro GmbH, Method for the production of a device for the transmission of a signal between two end points, 5,586,381, Cl. 29-434,000.

Scheibner, David J.: *See*—
Kimball, Christopher V.; and Scheibner, David J., 5,587,966, Cl. 367-31,000.

Schelberger, Klaus: *See*—
Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schelberger, Klaus; and Hampel, Manfred, 5,587,365, Cl. 514-63,000.

Scherer Aktiengesellschaft: *See*—
Bull, James R.; Fritzmeier, Karl-Heinrich; and Hegele-Hartung, Christa, 5,587,496, Cl. 552-629,000.

Scherpenberg, Francis A.: *See*—
Lee, Robert D.; Curry, Stephen M.; Bolan, Michael L.; Kurkowski, Hal; Diaz, Donald R.; Scherpenberg, Francis A.; and Deierling, Kevin E., 5,587,955, Cl. 365-221,000.

Schick, Michael R., to European Touch Co., Inc., Styrene monomer based nail tip blender and brush cleaner, 5,587,108, Cl. 252-364,000.

Schickert, Randy R.: *See*—
Fitzsimmons, James N.; and Schickert, Randy R., 5,586,759, Cl. 273-1,50R.

Schiller, Phillip D.: *See*—

- Leonard, William K.; Mohn, Stephen W.; Edman, Timothy J.; and Schiller, Phillip D.: 5,587,184, Cl. 425-133.000.
- Schilling, Donald L.: to InterDigital Technology Corporation. Spread spectrum CDMA communications system. 5,588,020, Cl. 370-337.000.
- Schlener, Lewis C.: See—
- Moon, Tracy L.; and Schlener, Lewis C.: 5,586,621, Cl. 188-4.000.
- Schlosser, Charles E.; Mueller, Lee G.; and McDougal, Gregory: to Manitowoc Company, Inc. The ice making machine. 5,586,439, Cl. 62-78.000.
- Schlueter, Harald: See—
- Schnitzler, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas: 5,586,992, Cl. 8-653.000.
- Schlumberger Technology Corporation: See—
- Kimball, Christopher V.; and Scheibner, David J.: 5,587,966, Cl. 367-31.000.
- Schmid, Martin: See—
- Hagen, Urs A.; Schmid, Martin; and Owen, Gwyn P.: 5,586,516, Cl. 114-362.000.
- Schmid, Peter: to Abbeystret Plc. Jewelry with an integral hinge. 5,586,452, Cl. 63-19.000.
- Schmidgall, Hartzell H.; and Schmidgall, Jon A.: to Hawkeye Concrete Products Co. Automated system for handling and cleaning concrete pipe-making components. 5,587,185, Cl. 425-229.000.
- Schmidgall, Jon A.: See—
- Schmidgall, Hartzell H.; and Schmidgall, Jon A.: 5,587,185, Cl. 425-229.000.
- Schmidt, Adolf: See—
- Heiliger, Ludwig; Schmidt, Adolf; and Probst, Joachim: 5,587,443, Cl. 526-240.000.
- Schmidt, Rainer: See—
- Reichert, Uwe; Schmidt, Rainer; and Shrook, Braham: 5,587,367, Cl. 514-171.000.
- Schmitt, Kenneth C.: to AT&T Global Information Solutions Company, Hyundai Electronics America; and Symbios Logic Inc. Multiclock controller. 5,587,675, Cl. 327-99.000.
- Schmitt, Michael: See—
- Schmitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas: 5,586,992, Cl. 8-653.000.
- Schmitz, Caroline N.: See—
- Gozdz, Antoni S.; Schmitz, Caroline N.; and Warren, Paul C.: 5,587,253, Cl. 429-192.000.
- Schnabel, Iherhard; Raff, Lothar; and Hirschmann, Klaus: to Robert Bosch GmbH. Mixture controller for an internal combustion engine. 5,586,543, Cl. 123-696.000.
- Schneider, Bernard; and Hosler, René; to Cebal, S.A. Tube made of plastics material having a tearable cap, said tube with a cover. 5,586,672, Cl. 215-250.000.
- Schneider, David A.: See—
- Smith, John M.; Schneider, David A.; Dausch, Mark E.; and Whipple, Walter III: 5,586,567, Cl. 134-57.000.
- Schneider (USA) Inc.: See—
- Roychowdhury, Suranjan: 5,587,125, Cl. 264-515.000.
- Schneider, John K.; and Glenn, William E.: to Ultra-Scan Corporation. Surface feature mapping using high resolution C-scan ultrasonography. 5,587,533, Cl. 73-614.000.
- Schneider, Michel: See—
- Tournier, Hervé; Hyacinthe, Roland; and Schneider, Michel: 5,587,199, Cl. 427-2.120.
- Schneider, Thomas; Grieser-Schmitz, Stefan; and Walther, Michael: to Robert Bosch GmbH. Device for indicating errors in a control line of an electric control units. 5,587,661, Cl. 324-556.000.
- Schnitzler, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas: to BASF Aktiengesellschaft. Dyeing cellulose-containing textile material with hydrogenated indigo. 5,586,992, Cl. 8-653.000.
- Schnitzler, Jan F.: See—
- Jacobson, Bruce S.; and Schnitzler, Jan F.: 5,587,297, Cl. 435-29.000.
- Schnoes, Heinrich K.: See—
- DeLuca, Hector E.; Schnoes, Heinrich K.; Perlman, Kato L.; Scinski, Rafal R.; and Prah, Jean M.: 5,587,497, Cl. 552-653.000.
- Schofield, Kerry G.: See—
- Dolbear, Keith D.; Beaudon, Trevor W.; and Schofield, Kerry G.: 5,586,626, Cl. 188-250.000.
- Schofield, Lois E.: Neck cushioning towel. 5,587,219, Cl. 428-68.000.
- Schofield, Ronald D.: to United States of America, Navy. Control circuit using delay lines to generate clock and control signals during a clock cycle of the system clock. 5,587,972, Cl. 368-118.000.
- Scholz, Guido: to Hoechst Aktiengesellschaft. Process for the preparation of chlorophenylphosphanes. 5,587,517, Cl. 568-16.000.
- Schramm, Raymond E.: See—
- McColkey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M.: 5,587,534, Cl. 73-623.000.
- Schröder-Brumloop, Helmut; and Loh, Rüdiger: to Otis Elevator Company. Method for controlling elevator doors. 5,587,565, Cl. 187-316.000.
- Schroeder, Christine: See—
- Kuhn, Peter; Schroeder, Christine; Sander, Volker; Lindener, Juergen; and De Riese-Meyer, Loert: 5,587,063, Cl. 205-173.000.
- Schroff GmbH: See—
- Joist, Michael: 5,587,888, Cl. 361-802.000.
- Schubert, Frederic E.: See—
- Hou, Wei-Hsin; Lloyd, Thomas B.; and Schubert, Frederic E.: 5,587,242, Cl. 428-402.000.
- Schubert, Ulrich: See—
- Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred: 5,587,107, Cl. 252-315.000.
- Schuerwegen, Ronald: See—
- Horsien, Bartholomeus C.; Uytendaele, Carlo A.; Jansen, Guy D. A.; and Schuerwegen, Ronald: 5,587,350, Cl. 503-201.000.
- Schub, Frank J.: to Telejet Technologies, Inc. Method and apparatus for drilling with high-pressure, reduced solid content liquid. 5,586,609, Cl. 175-65.000.
- Schuller, Edmund: See—
- Pohn, Romeo; and Schuller, Edmund: 5,586,427, Cl. 57-264.000.
- Schultz, Darald R.: to Norand Corporation. Modular scanner with hand-held data terminal. 5,587,577, Cl. 235-472.000.
- Schultz, John: See—
- Enneking, John R.; and Schultz, John: 5,586,376, Cl. 27-27.000.
- Schultz, John C.: to Minnesota Mining and Manufacturing Company. Identifying an area of interest using histogram data arranged in predetermined sequence. 5,588,071, Cl. 382-168.000.
- Schultz, Patrick J.: See—
- Edwards, Robert W.; Fulmer, Terry M.; and Schultz, Patrick J.: 5,586,583, Cl. 141-83.000.
- Schundehütte, Karl-Heinz; and Herd, Karl J.: to Bayer Aktiengesellschaft. 5-chloro-4-fluoropyrimidinyl substituted diazopyridone. 5,587,465, Cl. 534-635.000.
- Schuppen, Andreas: See—
- König, Ulf; Grühler, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Helmer, Heinz-Achim: 5,587,327, Cl. 437-31.000.
- Schürhörster, Josef: to KTR Kupplungstechnik GmbH. Toothed torque transmitting device having reinforcement ribs. 5,586,938, Cl. 464-92.000.
- Schwab, Günter: See—
- Stadler, Maximilian; Schwab, Günter; Romeder, Peter; and Trifellner, Gabriele: 5,587,046, Cl. 156-662.100.
- Schwartz, David C.: to Productive Environments, Inc. Single footprint same face tri-pocket array. 5,586,829, Cl. 402-79.000.
- Schwartz, David L.: to Hunt Holdings, Inc. Partitioning system. 5,586,593, Cl. 160-135.000.
- Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred: to BASF Aktiengesellschaft. SiO₂ aerogels containing carbon particles and their preparation. 5,587,107, Cl. 252-315.000.
- Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew; Kraft, Robert E.; and Vander Plas, Hubert A.: to Hewlett-Packard Company. Method of making solder balls by contained paste deposition. 5,586,715, Cl. 228-248.100.
- Sciannarella, Eduardo; and Lang, Michael: to Sony Corporation, and Sony Electronics Inc. Battery charger with night light for a cordless telephone. 5,587,645, Cl. 320-2.000.
- Scolastico, Carlo: See—
- Salimbeni, Aldo; Paleari, Fabio; Mizrahi, Jacques; and Scolastico, Carlo: 5,587,390, Cl. 514-341.000.
- Scriber, Chris A.: See—
- Manson, Larry J.; Scriber, Chris A.; and Davis, William L.: 5,587,642, Cl. 318-812.000.
- Seagate Technology, Inc.: See—
- Dunfield, John C.; and Oveyssi, Kamran: 5,587,617, Cl. 310-90.500.
- Seamans, Tom; and Stephenson, Stanley W., III: to Eastman Kodak Company. Camera access door interlock mechanism. 5,587,757, Cl. 396-536.000.
- Seay, O. Elwyn; Nickles, Stephen K.; and Haley, John E.: to FM Industries, Inc. Cushioning unit fault detector. 5,586,669, Cl. 213-43.000.
- Securistyle Limited: See—
- Baker, Neil M.: 5,586,362, Cl. 16-193.000.
- Seda Sp.A.: See—
- D'Amato, Antonio: 5,586,689, Cl. 222-92.000.
- Sedepro: See—
- Herbelleau, Yves: 5,587,030, Cl. 152-555.000.
- Segal, Jacob; Ben-Moshe, Josef; Weinstock, Zvika; and Harnik, Zvika: to Lanmet Data Communications Ltd. Apparatus and method for communication switching including providing information overflow indications. 5,588,151, Cl. 395-800.000.
- Sego, Kenneth W., Jr.: See—
- Hammer, David R.; Sego, Kenneth W., Jr.; and Lahun, Lance C.: 5,586,615, Cl. 182-48.000.
- Seibert, Horst: See—
- Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Haberle, Karl: 5,587,421, Cl. 524-591.000.
- Seidl, Robert H.: See—
- Chen, Michael; Houde, Stephanie L.; and Seidl, Robert H.: 5,588,098, Cl. 395-137.000.
- Seiichi, Tsukui: See—
- Masayuki, Watanabe; Toshio, Sugano; Seiichi, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima: 5,587,341, Cl. 437-206.000.
- Seiko Epson Corporation: See—
- Johnson, Anders R.: 5,588,113, Cl. 395-182.130.
- Mori, Katsumi; Asaka, Tatsuya; Iwano, Hideaki; and Kondo, Takayuki: 5,587,335, Cl. 437-129.000.

- Yabe, Hiroshi; and Ogihara, Tsutomu: 5,587,691, Cl. 331-44.000.
- Seiko Instruments Inc.: See—
- Matsushima, Kenichi: 5,587,558, Cl. 178-18.000.
- Seiko Seiki Kabushiki Kaisha: See—
- Tomotaki, Katsura: 5,586,468, Cl. 74-89.150.
- Seikoh Giken Co., Ltd.: See—
- Takahashi, Mitsuo: 5,588,081, Cl. 385-93.000.
- Seilhamer, Jeffrey J.: See—
- Hawkins, Phillip R.; Wilde, Craig G.; and Seilhamer, Jeffrey J.: 5,587,301, Cl. 435-69.100.
- Hawkins, Phillip R.; and Seilhamer, Jeffrey J.: 5,587,306, Cl. 435-198.000.
- Seki, Yukihito: See—
- Suzuki, Shimichi; Seki, Yukihito; and Hattori, Ryuichi: 5,588,004, Cl. 370-516.000.
- Sekiba, Takashi: to Fujitsu Miyagi Electronics Ltd. Lead frame having deflectable and thereby precisely removed tie bars. 5,587,606, Cl. 257-670.000.
- Sekihata, Osamu: See—
- Ohba, Toshimitsu; Shikata, Kiyotaka; and Sekihata, Osamu: 5,588,003, Cl. 370-468.000.
- Sekine, Atushi: See—
- Suzuki, Takeshi; and Sekine, Atushi: 5,587,739, Cl. 348-347.000.
- Sekine, Masayoshi; Kondo, Toshiaki; and Kino, Yoshiki: to Canon Kabushiki Kaisha. Shakeproof camera wherein shake correction parameters may be changed. 5,587,737, Cl. 348-208.000.
- Sekino, Hitoshi: See—
- Sawada, Kenji; Sato, Masahiro; Sekino, Hitoshi; and Sakamoto, Masashi: 5,587,769, Cl. 355-200.000.
- Seko, Yasuji: See—
- Otoma, Hironori; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario: 5,588,016, Cl. 372-46.000.
- Sela, Elaine: See—
- Wall, Ronald; Prasad, Raghubir; and Sela, Elaine: 5,587,158, Cl. 424-93.500.
- Selby, Theodore W.: Multiple-part and/or supported gas-containing vessel to establish desired heat flux. 5,587,522, Cl. 73-54.280.
- Selevoz, Evgeny A.: See—
- Skobelev, Valery V.; Slavin, Mikhail A.; Selevoz, Evgeny A.; Kabakov, Viktor G.; and Puzikov, Gennady S.: 5,586,872, Cl. 417-477.800.
- Sellers, Charles A.: to Compaq Computer Corporation. Collapsible notebook computer keyboard structure with horizontally and downwardly shiftable key return domes. 5,587,875, Cl. 361-680.000.
- Selman, Steven H.: See—
- Morgan, Alan R.; and Selman, Steven H.: 5,587,394, Cl. 514-185.000.
- Semeria, Didier: See—
- Philippe, Michel; Semeria, Didier; and Bollens, Eric: 5,587,169, Cl. 424-401.000.
- Semiconductor Energy Laboratory Co., Ltd.: See—
- Yamazaki, Shunpei: 5,587,330, Cl. 437-41.000.
- Yamazaki, Shunpei: 5,587,340, Cl. 437-203.000.
- Sendelweck, Gene K.: See—
- Griesentrog, Dal F.; and Sendelweck, Gene K.: 5,587,745, Cl. 348-626.000.
- Sengoku, Koji: See—
- Nakatani, Masayuki; Sengoku, Koji; and Fujita, Akihito: 5,587,194, Cl. 426-521.000.
- Senn-Billinger, Jörg: See—
- Kohl, Bernhard; Senn-Billinger, Jörg; and Grundler, Gerhard: 5,587,389, Cl. 514-338.000.
- Seo, Jeong Y.; and Song, Myung H.: to Samsung Heavy Industries Co., Ltd. Apparatus for and method of controlling engine RPM in hydraulic construction equipment. 5,586,536, Cl. 123-352.000.
- Seria, Didier: to Gemplus. Method and apparatus for optimizing magnetic flux through an electronic label of a contact-free identification system. 5,587,578, Cl. 235-492.000.
- Servo-Tech, Inc.: See—
- Nish, Terry E.: 5,586,379, Cl. 29-401.100.
- Services Algoa International Anstalt: See—
- Hagen, Urs A.; Schmid, Martin; and Owen, Gwyn P.: 5,586,516, Cl. 114-362.000.
- Servo Kinetics: See—
- Kokalis, George P.: 5,586,435, Cl. 60-416.000.
- Sessler, Jonathan L.; Mody, Tarak D.; Henimi, Gregory W.; Král, Vladimir A.; and Magda, Darren: to Pharmachem, Inc.; and Board of Trustees, Univ. of TX Sys. Texaphyrin-oligonucleotide conjugates. 5,587,371, Cl. 514-185.000.
- Sessler, Jonathan L.; Henimi, Gregory W.; and Murai, Toshiaki: to Board of Regents, The University of Texas System. Texaphyrin macrocycles and metal complexes thereof. 5,587,463, Cl. 534-15.000.
- Sessler, Jonathan L.; Král, Vladimir; and Andrievsky, Andrei: to Board of Regents, The University of Texas System. Sapphyrin multimers. 5,587,478, Cl. 540-474.000.
- Setoguchi, Kazuhiro: See—
- Watanabe, Kazuhiro; Oshima, Michihiro; Setoguchi, Kazuhiro; and Oda, Masaaki: 5,587,111, Cl. 252-514.000.
- Sevrain, Christophe J. P.: See—
- Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P.: 5,587,273, Cl. 430-269.000.
- Sextro, Günter: See—
- Fleischer, Dietrich; Hoffmückel, Michael; Mück, Karl-Friedrich; and Sextro, Günter: 5,587,449, Cl. 528-232.000.
- Seyfried, Elisabeth: See—
- Schwertfeger, Fritz; Schubert, Ulrich; Seyfried, Elisabeth; Kuhn, Joachim; Fricke, Jochen; and Mielke, Manfred: 5,587,107, Cl. 252-315.000.
- Seymour, Raymond K.: See—
- Berkan, Ertugrul; and Seymour, Raymond K.: 5,587,651, Cl. 324-127.000.
- Berkan, Ertugrul; Seymour, Raymond K.; and Grzelecki, John C.: 5,587,652, Cl. 324-127.000.
- SGS-Thomson Microelectronic S.A.: See—
- Samani, Davoud: 5,587,677, Cl. 327-108.000.
- SGS-Thomson Microelectronics, Inc.: See—
- Danstrom, Eric J.: 5,587,674, Cl. 327-67.000.
- SGS-Thomson Microelectronics Limited: See—
- Ferns, Andrew: 5,587,960, Cl. 365-230.030.
- Wyborn, Graeme M.; and Nicholls, Howard C.: 5,587,339, Cl. 437-195.000.
- SGS-Thomson Microelectronics S.r.l.: See—
- Campardo, Giovanni; Crisenza, Giuseppe; and Dallabona, Marco: 5,587,946, Cl. 365-185.020.
- Colli, Gianluca; Franciotta, Massimo; and Castello, Rinaldo: 5,587,682, Cl. 327-357.000.
- Shaffer, David S.: See—
- Stupek, Richard A., Jr.; Shaffer, David S.; Jones, Curtis R.; Davis, Steve; and Justice, William D., Jr.: 5,588,143, Cl. 395-500.000.
- Shaffer, Frank D.: See—
- Fiddes, Neil G.; King, Christopher G.; Mantone, Anthony; and Shaffer, Frank D.: 5,586,712, Cl. 228-5.700.
- Shapoff, Stanley N.: Inflatable wall. 5,586,594, Cl. 160-135.000.
- Sharkey, David J.: See—
- Scalice, Edward R.; Sharkey, David J.; Christy, Kenneth G., Jr.; Esders, Theodore W.; and Daiss, John L.: 5,587,287, Cl. 435-6.000.
- Sharon, Arie N.: Self on center leveling pot hanger. 5,586,413, Cl. 47-67.000.
- Sharp Kabushiki Kaisha: See—
- Ishii, Mitsuo: 5,587,851, Cl. 360-59.000.
- Kugimiyu, Shuzo: 5,587,902, Cl. 395-752.000.
- Matsuda, Eichika: 5,587,724, Cl. 345-156.000.
- May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harold, Jonathan: 5,587,820, Cl. 359-72.000.
- Miyaji, Takashi; Nishikawa, Yoshikazu; Andou, Yukinori; Yamanaka, Toshio; and Kadowaki, Hideaki: 5,587,777, Cl. 355-245.000.
- Murakami, Masanori; Koide, Yasuo; Teraguchi, Nobuaki; and Tomomura, Yoshitaka: 5,587,609, Cl. 257-744.000.
- Murata, Yasumoto: 5,587,977, Cl. 369-25.000.
- Murata, Yasumoto; Ikeuchi, Michio; Yoshikawa, Shuichi; and Watanabe, Masahiko: 5,588,052, Cl. 379-283.000.
- Nagaura, Toshikazu; Yamashita, Zenjiro; Arikawa, Kazuhiko; and Ohta, Kenji: 5,587,994, Cl. 369-291.000.
- Nakanishi, Hiroko; and Ohnishi, Hiroshi: 5,587,821, Cl. 349-118.000.
- Nishino, Hiroshi; and Fujii, Akiyoshi: 5,586,385, Cl. 29-603.160.
- Sharrit, David: to Hewlett-Packard Company. Method for simulating a circuit. 5,588,142, Cl. 395-500.000.
- Shayan, Yousef: See—
- Soleymani, Mohammad R.; and Shayan, Yousef: 5,587,939, Cl. 364-724.160.
- Sheehan, Gary T.; and Landry, Paul G.: Art work display apparatus. 5,586,401, Cl. 40-737.000.
- Sheen, Reen-Yuan: Pipe bending device. 5,586,463, Cl. 72-166.000.
- Shickalim, Avraham: to Hydromatic Ltd. Flow reducer devices and drip irrigation emitter including same. 5,586,727, Cl. 239-542.000.
- Shell Oil Company: See—
- Binsbergen, Frederik L.; Bos, Alouisius N. R.; and Santen, Augustinus: 5,587,438, Cl. 526-88.000.
- Shen, Ju: See—
- Agrawal, Om P.; Wright, Michael J.; and Shen, Ju: 5,587,921, Cl. 364-489.000.
- Shen, Jun; and Goronkin, Herbert: to Motorola. High density multistate SRAM and cell. 5,587,944, Cl. 365-175.000.
- Shepherd, Marjorie H.; and Gasaway, Kim B.: to Madison Chemical Co., Inc. Composition and process for mechanical plating of nickel-containing coatings on metal substrates. 5,587,006, Cl. 106-1.050.
- Sheppard, Clyde H.; and Lubowitz, Hyman R.: Methods for making liquid molding compounds using diamines and dicyanates. 5,587,105, Cl. 252-183.110.
- Sheppard, Robin L.: See—
- Henion, Jack D.; Sheppard, Robin L.; and Wachs, Timothy: 5,587,582, Cl. 250-288.000.
- Sheynblat, Len: to Trimble Navigation, Ltd. Gap coverage for GPS signals. 5,587,716, Cl. 342-357.000.
- Shi, Song Q.: See—
- So, Frank; Shi, Song Q.; and Harvey, Thomas B., III: 5,587,589, Cl. 257-40.000.
- Shibaguchi, Takashi: to Ricoh Company, Ltd. Optical beam scanning apparatus adjusting focal point over entire image forming area by feedback control. 5,587,826, Cl. 359-216.000.
- Shibai, Yoshio: See—
- Hayashi, Teruoki; and Shibai, Yoshio: 5,586,930, Cl. 451-548.000.

- Shibasaki, Yasuo, Oda, Kiuchi, and Fukuda, Takeshi, to Agency Of Industrial Science And Technology, Ministry Of International Trade And Industry, and YKK Corporation. Process for producing fine flaky alumina particles and alumina-based plastic material. 5,587,010, Cl. 106-287.170.
- Shibata, Mineharu, and Takehara, Shin, to Naldec Corporation, and Mazda Motor Corporation. Vehicle suspension apparatus capable of preventing generation of transitional vibration in rolling movement. 5,587,907, Cl. 364-424.046.
- Shibata, Mitsuru, Sakanoto, Masashi, and Nasuno, Ichiro, to Idemitsu Kosan Co., Ltd. Pyrazole process and intermediates. 5,587,484, Cl. 548-364.400.
- Shibata, Tadashi, and Ohmi, Tadashi. Semiconductor devices utilizing neutron MOS transistors. 5,587,668, Cl. 326-36.000.
- Shibata, Tsuneo. See—
Soga, Mamoru; Mino, Norihisa; Ogawa, Kazutami; Mochizuki, Yusuke, and Shibata, Tsuneo. 5,587,209, Cl. 427-503.000.
- Shibata, Yoshiaki. See—
Yoneda, Masator, and Shibata, Yoshiaki. 5,588,137, Cl. 395-490.000.
- Shibley, George P. See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meitz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L., and Shibley, George P. 5,587,164, Cl. 424-218.100.
- Shibutsu, Yumiko. See—
Takami, Muneo; Kozai, Yoshio; Tomimatsu, Kiminori, and Shibutsu, Yumiko. 5,587,383, Cl. 514-300.000.
- Shigematsu, Yuji. See—
Kubo, Kohji; Nezu, Shonchi; Ishibashi, Fumio; Harada, Hiroyuki, and Shigematsu, Yuji. 5,587,247, Cl. 428-523.000.
- Shikata, Kiyotaka. See—
Ohba, Toshimitsu; Shikata, Kiyotaka, and Sekhata, Osamu. 5,588,003, Cl. 370-468.000.
- Shiles, Robert J., II. See—
Eslampour, Robert A.; Shiles, Robert J., II, and Hendry, Allan W. 5,586,912, Cl. 439-620.000.
- Shima, Hisato. See—
Kuri, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato, and Ogawa, Kazuyuki. 5,587,849, Cl. 360-69.000.
- Shima, Kazunobu, and Yamamoto, Yui, to Noritsu Koki Co., Ltd. Photo-developing apparatus. 5,587,758, Cl. 396-613.000.
- Shima, Nobuyuki. See—
Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasuharu, and Nagao, Masaya. 5,587,359, Cl. 514-12.000.
- Shimada, Junichi. See—
Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio, and Nonaka, Hiromi. 5,587,378, Cl. 514-264.000.
- Shimada, Reiko. See—
Tsubota, Hiroyuki, and Shimada, Reiko. 5,587,296, Cl. 435-14.000.
- Shimada, Shingo, to Riso Kagaku Corporation. Stencil printing machine with stencil tensioning member. 5,586,497, Cl. 101-128.400.
- Shimada, Tomoyuki. See—
Tanaka, Chiaki; Sasaki, Masaomi; Aruga, Tamotsu; Shimada, Tomoyuki, and Adachi, Hiroshi. 5,587,516, Cl. 564-405.000.
- Shimadzu Corporation. See—
Togawa, Yoshiyuki, and Miura, Makoto. 5,587,062, Cl. 204-613.000.
- Shimakura Chemical Co., Ltd. See—
Yamauchi, Hiroshige, and Nishi, Shonosuke. 5,586,732, Cl. 241-168.000.
- Shimano Inc. See—
Kawabe, Yuzo, and Sakaguchi, Noboru. 5,586,734, Cl. 242-247.000.
- Shimizu, Hirokazu. See—
Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kuni; Ohta, Issei, and Shimizu, Hirokazu. 5,587,334, Cl. 437-129.000.
- Shimizu, Kazuharu. See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji, and Shimizu, Kazuharu. 5,587,240, Cl. 428-367.000.
- Shimizu, Kazuhiko; Ito, Takeo; and Matsuda, Hidemi, to Kabushiki Kaisha Toshiba. Antireflection film and display apparatus. 5,587,835, Cl. 359-589.000.
- Shimizu, Toshikazu. See—
Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio, and Ichino, Tomio. 5,587,504, Cl. 558-58.000.
- Shimmell, Dennis S., to Nelson Metal Products Corporation. Method for making mated molded parts assembly. 5,586,380, Cl. 29-413.000.
- Shimoda, Kazuhiko. See—
Hasegawa, Toshiro; Shimoda, Kazuhiko; Makino, Kunio, and Tomioka, Mitsuo. 5,586,994, Cl. 29-623.500.
- Shimotashiro, Masafumi, and Kuroe, Akio, to Matsushita Electric Industrial Co., Ltd. Digital signal magnetic recording and reproducing apparatus for both metal evaporation tapes and metal powder tapes. 5,587,848, Cl. 360-46.000.
- Shin, Dong-Yup, to Hyundai Motor Company. High density nickel hydroxide containing boron and a method for preparing it. 5,587,139, Cl. 423-275.000.
- Shin-Etsu Chemical Co., Ltd. See—
Adachi, Fumaki; Amano, Tadashi; Shirota, Yoshihito, and Okuno, Yoshitaka. 5,587,437, Cl. 526-68.000.
- Kato, Hideto. 5,587,275, Cl. 430-283.100.
- Shin, Ki-ho. See—
Moon, Byung-Joon; Cho, Sung-il, and Shin, Ki-ho. 5,587,804, Cl. 386-2.000.
- Shin, Seongkee, and Lee, Sangho, to Samsung Electronics Co., Ltd. Power conservation system for a modem in a computer system. 5,588,054, Cl. 379-413.000.
- Shinagawa, Masaaki. See—
Soda, Yoshio; Kohno, Taketumi; Shinagawa, Masaaki, and Kiuchi, Noriyuki. 5,587,203, Cl. 427-228.000.
- Shindo, Yasuhiro; Yamaguchi, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro, and Kitabatake, Syoichi, to Hitachi, Ltd. Solid organic waste processing apparatus. 5,587,320, Cl. 435-290.100.
- Shinji, Yasuhisa, and Takase, Hiraji, to Yazaki Corporation. Waterproof connector. 5,586,897, Cl. 439-271.000.
- Shinji, Yasuhisa, Monshita, Kazuhiro, and Takase, Hiraji, to Yazaki Corporation. Waterproof cover for connector. 5,586,916, Cl. 439-752.000.
- Shinohara, Mahito, to Canon Kabushiki Kaisha. Solid-state image pickup device having plural switches for subtracting a stored signal from a pixel output. 5,587,738, Cl. 348-302.000.
- Shinohara, Makoto; Matsumoto, Yoshikane, and Suematsu, Shigenori, to Hitachi Koki Co., Ltd. Dot line printer with adjusted dot positions for canceling sheet feed error. 5,586,496, Cl. 101-93.040.
- Shinohara, Makoto. See—
Yoshida, Kazuyoshi; Itoh, Hiroshi; Fukuoka, Hiroshi, and Shinohara, Makoto. 5,588,133, Cl. 395-477.000.
- Shinozaki, Shimppei. See—
Kanazawa, Hiroshi; Okuda, Isao; Shinozaki, Shimppei, and Takishima, Suguru. 5,587,973, Cl. 369-13.000.
- Shiono, Manzo. See—
Nakagawa, Naoshi; Hatanaka, Tadashi; Hayashihara, Tatsuhiko, and Shiono, Manzo. 5,587,486, Cl. 548-448.000.
- Shionogi & Co., Ltd. See—
Konoike, Toshiro; Araki, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Ken-suke, and Tozoy, Takehiko. 5,587,505, Cl. 558-272.000.
- Shiozaki, Shizuo. See—
Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio, and Nonaka, Hiromi. 5,587,378, Cl. 514-264.000.
- Shirahata, Kei. See—
Fujwara, Tatsunori; Nakanishi, Yasuyuki; Oka, Koutarou; Shirahata, Kei, and Ito, Shigehiro. 5,587,989, Cl. 369-178.000.
- Shirota, Yoshihito. See—
Adachi, Fumaki; Amano, Tadashi; Shirota, Yoshihito, and Okuno, Yoshitaka. 5,587,437, Cl. 526-68.000.
- Shitara, Yasuharu, Hayasaka, Noboru, and Kosuka, Toshiya, to Sanyo Electric Co., Ltd. Communication control system for transmitting, from one data processing device to another, data of different formats along with an identification of the format and its corresponding DMA controller. 5,588,120, Cl. 395-200.150.
- Shlomo, Moshe B. See—
Banitt, David, and Shlomo, Moshe B. 5,587,664, Cl. 324-752.000.
- Shoberg, Bret R., and Heruth, Kenneth T., to Medtronic, Inc. Pressure controlled system for filling an implantable drug infusion pump. 5,586,629, Cl. 141-21.000.
- Shoda, Yoshio. See—
Unno, Tetsuo; Shoda, Yoshio, and Momono, Tatsunobu. 5,586,827, Cl. 384-450.000.
- Shrova, Braham. See—
Reichen, Uwe; Schmidt, Rainer, and Shrova, Braham. 5,587,367, Cl. 514-171.000.
- Shuman, Ralph J. See—
Burns, Barbara J., and Shuman, Ralph J. 5,587,408, Cl. 523-160.000.
- Shustack, Paul J., to Borden, Inc. Organic solvent & water resistant hydrolytically stable ultraviolet radiation curable coatings for optical fibers. 5,587,403, Cl. 522-42.000.
- Shuto, Sadanobu. See—
Ikeda, Hideo; Shuto, Sadanobu, and Hara, Taketumi. 5,587,280, Cl. 430-567.000.
- Shwe, Than, and Michaels, John M., to Western Atlas International, Inc. Formation fluid flow rate determination method and apparatus for electric wireline formation testing tools. 5,587,525, Cl. 73-15.520.
- Sibik, Lee L., and Berget, Mark D., to Gas Research Institute. Concentration control in an absorption chiller. 5,586,447, Cl. 62-141.000.
- Sicinski, Rafal R. See—
DeLuca, Hector F.; Schmoes, Heinrich K.; Perlman, Kato L.; Sicinski, Rafal R., and Prah, Jean M. 5,587,497, Cl. 552-653.000.
- Sieloff, Ronald F. See—
Paul, William C., and Sieloff, Ronald F. 5,587,206, Cl. 427-558.000.
- Siemens Aktiengesellschaft. See—
Kroemer, Nils; Vossiek, Martin; Ewaldt, Peter-Christian, and Magori, Valentin. 5,587,969, Cl. 367-99.000.
- Loibl, Josef. 5,588,123, Cl. 395-287.000.
- Mahnkopf, Reinhard, and Vom Felde, Andreas. 5,587,599, Cl. 257-370.000.
- Palm, Rainer. 5,587,898, Cl. 364-148.000.
- von Gentzow, Wolfgang; Huber, Jürgen; Kapitza, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jörg, and Wilhelm, Dieter. 5,587,243, Cl. 428-413.000.
- Siemens Electromechanical Components, Inc. See—
Fear, Christopher. 5,587,693, Cl. 335-78.000.
- Siemens Rdm Communications, Inc. See—
Locke, Michael E. 5,588,045, Cl. 379-67.000.
- Sih, Charles I., to Wisconsin Alumni Research Foundation. Process for preparing(s)- α -methylarylacetic acids. 5,587,318, Cl. 435-280.000.

- Silber, Dieter. See—
Neubrand, Horst; Korec, Jacek; Stein, Erhart, and Silber, Dieter. 5,587,595, Cl. 257-141.000.
- Silicon Systems, Inc. See—
Adams, William J. 5,587,687, Cl. 330-253.000.
- Simmons, Frederick H. G., to Alcatel Canada Wire Inc. Method and apparatus for weld testing. 5,587,537, Cl. 73-862.392.
- Simon, Arno, and Gast, Jürgen, to Bruker Analytische Messtechnik GmbH. Semiconductor foil beam-splitter for an infrared spectrometer. 5,587,831, Cl. 359-350.000.
- Simonds Industries, Inc. See—
Li, Cheng J. 5,587,925, Cl. 364-508.000.
- Simonis, Jürgen, to Welger GmbH. Swivelling piston press. 5,586,494, Cl. 100-189.000.
- Simpson, Richard J. See—
Van Snick, Jacques; Uytendhoe, Catherine, and Simpson, Richard J. 5,587,302, Cl. 435-69.500.
- Simula Inc. See—
Hammer, David R.; Sego, Kenneth W., Jr.; and Labun, Lance C. 5,586,615, Cl. 182-48.000.
- Sinclair, John D. Method for terminating methadone maintenance through extinction of the opiate-taking responses. 5,587,381, Cl. 514-282.000.
- Sine, Andrew L., to Dresser-Rand Company. Piston and rod assembly. 5,586,483, Cl. 92-255.000.
- Sines, Randy D. See—
Forte, Steven L., and Sines, Randy D. 5,586,766, Cl. 273-309.000.
- Singh, Tejinder. See—
Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P. 5,587,454, Cl. 530-324.000.
- Sinn, Scott G. See—
Faletti, James J.; Feucht, Dennis D.; and Sinn, Scott G. 5,586,532, Cl. 123-321.000.
- Sircar, Subhasish, to Reynolds Metals Company. Machineable aluminum alloys containing In and Sn and process for producing the same. 5,587,029, Cl. 148-438.000.
- Sjostrom, Anders, to Tetra Laval Holdings & Finance SA. Heat exchanger. 5,586,599, Cl. 165-143.000.
- Skarhed, Ove. See—
Bergström, Jan O.; Liljegen, Lars; Skarhed, Ove; and Årenäs, Anders. 5,587,863, Cl. 361-93.000.
- Skatrud, Paul L. See—
Alborn, William E., Jr.; Hoskins, JoAnn; Skatrud, Paul L.; and Ünal, Serhat, 5,587,307, Cl. 435-240.100.
- SKF Sverige AB. See—
Kellström, Magnus; Fogelström, Joacim; and Wittmeyer, Henning. 5,586,826, Cl. 384-450.000.
- Skis Rossignol SA. See—
Hutin, Patrice. 5,586,947, Cl. 473-324.000.
- Skobelev, Valery V.; Slavin, Mikhail A.; Selezov, Evgeny A.; Kabakov, Viktor G.; and Puzikov, Gennady S. Adjustable peristaltic pump. 5,586,872, Cl. 417-477.800.
- Slangen, Hubertus J. M., to Holland Sweetener Company V.o.F. Process for the treatment of aspartame. 5,587,178, Cl. 424-464.000.
- Slaughter, John E.; Olson, George, and McShane, William J., to Texas Instruments Incorporated. Sampling apparatus for inline spectrographic analysis of viscous materials. 5,587,788, Cl. 356-246.000.
- Slavin, Mikhail A. See—
Skobelev, Valery V.; Slavin, Mikhail A.; Selezov, Evgeny A.; Kabakov, Viktor G.; and Puzikov, Gennady S. 5,586,872, Cl. 417-477.800.
- Sloan Valve Company. See—
Nortier, Richard A. 5,586,573, Cl. 137-359.000.
- SMC Kabushiki Kaisha. See—
Fukano, Yoshihiro, and Doi, Yoshitada. 5,586,570, Cl. 137-271.000.
- Smedley, William H. See—
Haber, Terry M.; Smedley, William H.; and Foster, Clark B. 5,586,946, Cl. 473-295.000.
- Smilanick, Steve-Frank. Bicycle torque coupling. 5,586,652, Cl. 206-335.000.
- Smith & Nephew plc. See—
Evans, John C. 5,586,972, Cl. 602-76.000.
- Smith, B. Brian. See—
Krogh, James A.; Mokadam, Anita R.; and Smith, B. Brian. 5,587,498, Cl. 554-69.000.
- Smith, Dean E. Air system control. 5,586,574, Cl. 137-487.500.
- Smith, Donald D.; Cohnick, Christopher B.; and Lindsley, Herbert B., to University of Kansas. Moated tissue culture plate. 5,587,321, Cl. 435-305.300.
- Smith, Eric. See—
Kanjo, Wajih; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott. 5,586,812, Cl. 303-7.000.
- Smith, Eric G. See—
McKay, Albert A.; and Smith, Eric G. 5,586,813, Cl. 303-22.400.
- Smith, Francis S. See—
McIntosh, Bruce M.; Smith, Francis S.; and Briscoe, Noel A. 5,587,541, Cl. 84-297.005.
- Smith, Grant W. See—
Ward, Thomas F.; and Smith, Grant W. 5,586,657, Cl. 206-705.000.
- Smith, James C.; and Walling, Dennis R., to Caterpillar Inc. Boost device bypass valve. 5,586,744, Cl. 251-61.500.
- Smith, John M.; Schneider, David A.; Dausch, Mark E.; and Whipple, Walter, III, to General Electric Company. Dishwasher with turbidity sensing mechanism. 5,586,567, Cl. 134-57.000.
- Smith, Julius O., III, to Leland Stanford Junior University. The Board of Trustees of the Musical tone synthesis system having shortened excitation table. 5,587,548, Cl. 84-659.000.
- Smith, Neil. See—
Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance. 5,587,483, Cl. 548-252.000.
- Smith, Stephen W., to MTS Systems Corporation. Pulse generator with charge pump. 5,587,680, Cl. 327-291.000.
- Smith, Steven D. Ball joint extractor. 5,586,378, Cl. 29-257.000.
- Smith, Walter P., to Mary Kay Inc. Method of ameliorating cellulite by disrupting the barrier function of the stratum corneum. 5,587,396, Cl. 514-557.000.
- Smith, Walter R.; and Capps, Stephen P., to Apple Computer, Inc. System for executing different functions associated with different contexts corresponding to different screen events based upon information stored in unified data structure. 5,588,141, Cl. 395-500.000.
- SmithKline Beecham PLC. See—
Johnson, Graham; Smith, Neil; Geen, Graham R.; Mann, Inderjit S.; and Novack, Vance. 5,587,483, Cl. 548-252.000.
- Smiths Industries Public Limited Company. See—
Hannant, Keith. 5,586,349, Cl. 5-614.000.
- Smoral, Vincent J. See—
Dapp, Michael C.; Barker, Thomas N.; Dieffenderfer, James W.; Knowles, Billy J.; Lesmeister, Donald M.; Nier, Richard E.; Rolfe, David B.; and Smoral, Vincent J. 5,588,152, Cl. 395-800.000.
- Snow Brand Milk Products Co., Ltd. See—
Higashio, Kanji; Mitsuda, Shinjiro; Shima, Nobuyuki; Itagaki, Yasuharu, and Nagao, Masaya. 5,587,359, Cl. 514-12.000.
- Snyder, Bernard M., to J.F.A. Tech., Inc. System and method for signaling a device at a remote location over a wireless network. 5,588,038, Cl. 379-57.000.
- Snyder, Solomon H. See—
Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H. 5,587,384, Cl. 514-309.000.
- So, Franky; Shi, Song Q.; and Harvey, Thomas B., III, to Motorola. Two dimensional organic light emitting diode array for high density information image manifestation apparatus. 5,587,589, Cl. 257-40.000.
- Soberon, Peter A. See—
Lawless, Michael W.; Soberon, Peter A.; Kaul, Ashok; Minick, Steven E.; Hoerner, Gregory G.; Hermann, Robert A.; and Kreinick, Stephen J. 5,586,868, Cl. 417-53.000.
- Societe Civile des Brevets Henri Vidal. See—
Anderson, Peter L.; Cowell, Michael J.; and Hotek, Dan J. 5,586,841, Cl. 405-286.000.
- Societe de Constructions de Material Metallique. See—
Beizermann, Michel. 5,587,192, Cl. 426-118.000.
- Societe Nationale d'Etude et de Construction de Moteurs d'Aviation "Sneema". See—
Bertrand, Jean-Louis; Charier, Gilles A.; Guyonnet, Xavier J.A.; and Picard, Jean-Louis. 5,586,860, Cl. 415-115.000.
- Soda, Yoshio; Kohno, Takefumi; Shinagawa, Masaaki; and Kiuchi, Noriyuki, to Nippon Oil Co. Method for preparing a carbon/carbon composite material. 5,587,203, Cl. 427-228.000.
- Sodolak, Eddie A. Auger stand. 5,586,743, Cl. 248-671.000.
- Soga, Mamoru; Mino, Norihisa; Ogawa, Kazufumi; Mochizuki, Yusuke; and Shibata, Tsuneo, to Matsushita Electric Industrial Co., Ltd. Fluorocarbon-based polymer lamination coating film and method of manufacturing the same. 5,587,209, Cl. 427-503.000.
- Sohma, Masaki. See—
Nagao, Kenji; Sohma, Masaki; Ando, Shigeru; and Kobayakawa, Michihiro. 5,587,927, Cl. 364-514.00A.
- Soleymani, Mohammad R.; and Shayan, Yousef, to Spar Aerospace Limited. Half-band filter for a cellular group demultiplexer. 5,587,939, Cl. 364-724.160.
- Sollac. See—
Audebert, Serge; and Audibert, Francis. 5,587,002, Cl. 75-770.000.
- Solow, Rikki. See—
Carter, Barrie J.; Flotte, Terence; Afione, Sandra; and Solow, Rikki. 5,587,308, Cl. 435-240.200.
- Solyntjes, Alan J. See—
Plyley, Alan K.; Vidal, Claude A.; Minck, John L., Jr.; and Solyntjes, Alan J. 5,586,711, Cl. 227-176.100.
- Son, Young C. See—
Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S. 5,587,388, Cl. 514-314.000.
- Sondergeld, Manfred. See—
Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Convers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K. 5,587,272, Cl. 430-257.000.
- Song, Myung H. See—
Seo, Jeong Y.; and Song, Myung H. 5,586,536, Cl. 123-352.000.
- Sonnenberg, Hardy. See—
Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A. 5,587,767, Cl. 355-27.000.
- Sonobe, Masanori. See—
Kawaguchi, Masahiro; Sonobe, Masanori; Kanzaki, Shigeki; and Yokono, Tomohiko. 5,586,870, Cl. 417-222.200.

Sonobe, Naohiro; Maruyama, Koji; and Iwasaki, Takao, to Kureha Kagaku Kogyo Kabushiki Kaisha. Carbonaceous electrode material for secondary battery. 5,587,255, Cl. 429-218.000.

Sonoco Products Company. See—

Lennon, George E.; Martin, James R.; and Anderson, Charles D., 5,586,963, Cl. 493-299.000.

Sony Corporation. See—

Aoyama, Takashi, 5,587,856, Cl. 360-99.020.

Goda, Yoshimasa, 5,587,845, Cl. 359-819.000.

Kobayashi, Shoji, 5,587,975, Cl. 369-13.000.

Kori, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato; and Ogawa, Kazuyuki, 5,587,849, Cl. 360-69.000.

Maki, Yasuhiro, 5,587,576, Cl. 235-462.000.

Owa, Hideo; and Kobayashi, Seiji, 5,587,984, Cl. 369-103.000.

Sciammarella, Eduardo; and Lang, Michael, 5,587,645, Cl. 320-2.000.

Staros, Theodore; and Flum, Alan, 5,586,906, Cl. 439-483.000.

Suzuki, Yoshio; and Nakajima, Yoshiharu, 5,587,722, Cl. 345-94.000.

Watanabe, Tetsu; and Aoki, Yoshio, 5,587,990, Cl. 369-275.000.

Yamagami, Tamotsu, Sako, Yoichiro; and Yamamoto, Masanobu, 5,587,901, Cl. 369-275.300.

Sony Electronics Inc. See—

Sciammarella, Eduardo; and Lang, Michael, 5,587,645, Cl. 320-2.000.

Staros, Theodore; and Flum, Alan, 5,586,906, Cl. 439-483.000.

Sopko, Terry. See—

Witteck, Robert, Sr.; Cantrell, Aron; and Sopko, Terry, 5,586,942, Cl. 473-168.000.

Sorensen, Ian. See—

Bao, Qingcheng; Sorensen, Ian; and Glaunsinger, William, 5,587,130, Cl. 422-88.000.

Sorensen, Kurt I. Towable array for measuring the resistivity of a terrain utilizing a low power level. 5,587,659, Cl. 324-357.000.

Soske, Joshua W. See—

Lauder, Gary M.; Hoarty, W. Leo; and Soske, Joshua W., 5,587,734, Cl. 348-10.000.

Southpac Trust International, Inc. See—

Craig, Frank; Straeter, Joseph G.; and Weder, Donald E., 5,586,425, Cl. 53-449.000.

Southwire Company. See—

Owens, Steve G.; Lovvorn, Richard V.; and Elder, Albert B., 5,587,181, Cl. 425-1.000.

Space Systems/Loral, Inc. See—

Chu, Peter Y.; and Tador, Alfred H., 5,587,714, Cl. 342-354.000.

Spaeh, Richard; Schaefer, Wolfgang; Stolten, Detlef; and Fandel, Marco, to Dornier GmbH. Ceramic gas supply components for fuel cells comprising zirconium oxide solid electrolyte. 5,587,251, Cl. 429-33.000.

Spagnoli, Leonardo. See—

Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E., 5,587,229, Cl. 428-224.000.

Spaleck, Walter. See—

Winter, Andreas; Dolle, Volker; and Spaleck, Walter, 5,587,501, Cl. 556-53.000.

Spamer, William S.; Suttles, J. Marshall; Parham, Dennis E.; and Whiten, James D., to Mead Corporation. The Gravity feed bottle dispensing device having a track-blocking gate mechanism. 5,586,687, Cl. 221-298.000.

Spangler, Leland J. See—

Stevenson, Paul E.; Stephan, Craig H.; Samman, Amer M.; and Spangler, Leland J., 5,587,518, Cl. 73-1.000.

Spano, Joseph M.; Antonuccio, Robert S.; and Carney, James M., to Sun Microsystems, Inc. Mounting arrangement for computer hardware components and method. 5,587,879, Cl. 361-685.000.

Spar Aerospace Limited. See—

Soleymani, Mohammad R.; and Shayan, Yousef, 5,587,939, Cl. 364-724.160.

Sparks, Joe L. See—

Lanier, Jaron Z.; Lasko-Harvill, Ann; Blanchard, Chuck L.; and Sparks, Joe L., 5,588,104, Cl. 395-326.000.

Spears, John H. See—

Meyer, George W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F., 5,588,041, Cl. 379-59.000.

Speece, Stephen A., to Steel City Corporation. Security mail box lock assembly. 5,586,718, Cl. 232-17.000.

Speil, Walter, to Ina Walzinger Schaeffler KG. Tappet for the valve drive of an internal combustion engine. 5,586,528, Cl. 123-90.510.

Spence, Scott R. See—

Barnes, Steven J.; and Spence, Scott R., 5,586,871, Cl. 417-423.110.

Spescom (Proprietary) Limited. See—

Leitner, Johann R.; and Farah, Anthony, 5,587,575, Cl. 235-384.000.

Spezio, Anthony E. See—

Alexander, Edward M.; and Spezio, Anthony E., 5,587,829, Cl. 359-287.000.

Spiegel, Herbert; and Böhm, Robert, to Spiegel, Herbert. Hot water supply system with a ring pipeline. 5,586,720, Cl. 237-8.000.

Spitzer, Richard. See—

Torok, James; and Spitzer, Richard, 5,587,943, Cl. 365-158.000.

Spivey, Thomas R.; and Zahler, Byron G., to T.Z. Medical, Inc. Pacemaker and heart monitoring and data transmitting device and method. 5,586,556, Cl. 128-697.000.

Spors, Ralf. See—

Kirchner, Hary; Hohmann, Ralf; and Spors, Ralf, 5,586,791, Cl. 285-179.000.

Sprague, Marshall. See—

Vincent, Ronald; Sprague, Marshall; and Hare, Duncan, 5,588,119, Cl. 395-200.150.

Spraying Systems Co. See—

Chen, Shikui; and Butterfield, Ted, 5,586,723, Cl. 239-102.200.

Springer, Caroline J. See—

Burke, Philip J.; Dowell, Robert I.; Mauger, Anthony B.; and Springer, Caroline J., 5,587,161, Cl. 424-178.100.

Springer, William O. Lift apparatus. 5,586,856, Cl. 414-462.000.

Springs Industries, Inc. See—

Cooperman, Barbara; and Huff, Robert M., 5,586,375, Cl. 24-716.000.

Squitteri, Anthony C., to Mechtronics Corporation. Foldable and expandable promotional pallet. 5,586,666, Cl. 211-175.000.

Srinivasan, Vijay. See—

Abrams, Steven R.; Korein, James U.; Srinivasan, Vijay; and Tarabanis, Konstantinos, 5,587,913, Cl. 364-468.260.

Sriskantha, Alagacane. See—

Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srisantha, Alagacane; and Riding, George A., 5,587,311, Cl. 435-240.200.

St. Jude Children's Research Hospital. See—

Yeung, Kah T. D., 5,588,033, Cl. 378-4.000.

Stacy, Nathan E. See—

Moczysgemba, George A.; Knight, Nancy R.; Treпка, William J.; and Stacy, Nathan E., 5,587,425, Cl. 525-98.000.

Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard J.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., to Support Systems, International. Method and apparatus for supporting and for supplying therapy to a patient. 5,586,346, Cl. 5-710.000.

Stadler, Maximilian; Schwab, Günter; Römder, Peter; and Trifellner, Gabriele, to Wacker Siltronic Gesellschaft Für Halbleitermaterialien Aktiengesellschaft. Process for treating semiconductor material with an acid-containing fluid. 5,587,046, Cl. 156-662.100.

Stafford, Gary. See—

Morris, John; and Stafford, Gary, 5,586,970, Cl. 602-26.000.

Stammen, Harold A. See—

Dammeyer, Ned E.; Fullenkamp, Todd M.; and Stammen, Harold A., 5,586,620, Cl. 187-227.000.

Standard Register Company, The. See—

Laurash, David F., 5,586,788, Cl. 283-81.000.

Stanzak, Richard K. See—

Burguera, Bartolome; and Stanzak, Richard K., 5,586,501, Cl. 104-368.000.

Staros, Theodore; and Flum, Alan, to Sony Corporation; and Sony Electronics Inc. Electrical connector having an improved grip member. 5,586,906, Cl. 439-483.000.

Staroselsky, Semeon, to V.T.S. Trenching Systems Ltd. Vertical trencher apparatus employing cutter having helical channel of varying rise angle. 5,586,399, Cl. 37-351.000.

Starsinic, Michael E. See—

Clementini, Luciano; Galambos, Adam F.; Lesca, Giuseppe; Ogale, Kumar; Spagnoli, Leonardo; and Starsinic, Michael E., 5,587,229, Cl. 428-224.000.

Staton, Larry E. See—

Dolgas, Patrick A.; Walton, Ballard E.; and Staton, Larry E., 5,586,383, Cl. 29-596.000.

Staud, Gary G. See—

Dauderman, Shelley L.; McWilliams, Linda C.; Nair, Hari A.; and Staud, Gary G., 5,587,356, Cl. 510-320.000.

St. Denis, Lucien, to E. R. St. Denis & Sons Ltd. Adhesive curing system and method for a hemming machine. 5,587,042, Cl. 156-477.100.

Stehnitz, Kathleen K. See—

Pahuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stebnitz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.

Stec, Kevin J. See—

Hau, Clarence J.-Y.; Stec, Kevin J.; and Vavreck, Kenneth E., 5,587,742, Cl. 348-441.000.

Steel City Corporation. See—

Speece, Stephen A., 5,586,718, Cl. 232-17.000.

Steffy, David A., to Orbital Sciences Corporation. Axially arrayed helical antenna. 5,587,719, Cl. 343-895.000.

Stein, Erhart. See—

Neubrand, Horst; Korec, Jacek; Stein, Erhart; and Silber, Dieter, 5,587,595, Cl. 257-141.000.

Steinbach, Christian. See—

Döbeling, Klaus; Santer, Johannes; and Steinbach, Christian, 5,586,878, Cl. 431-351.000.

Steiner, George A. Non-slip sleeve for float level sensor shaft. 5,586,466, Cl. 73-319.000.

Steiner, Manfred, to Mercedes-Benz AG. Braking pressure control device with maximum vehicle deceleration during automatic braking. 5,586,814, Cl. 303-116.200.

Steingrover, Erich, to Magnet-Physik Dr. Steingrover GmbH. Device with peak current loop and process for the magnetic shaping of metal parts. 5,586,460, Cl. 72-56.000.

Steinhardt, Helmut. See—

Hopf, Gustav; and Steinhardt, Helmut, 5,586,902, Cl. 439-352.000.

Steinhoff, Georg. See—

Salzburg, Herbert; Steinhoff, Georg; Gosch, Andreas; and Hufen, Gerd, 5,587,511, Cl. 562-513.000.

Stekette, Campbell H., Jr., to NuPipe, Inc. Method of manufacturing a pipe liner for installation in an existing conduit. 5,587,126, Cl. 264-568.000.

Stelzer, Glen A. See—

Ryan, Thomas P.; and Stelzer, Glen A., 5,587,877, Cl. 361-683.000.

Stengel-Rutkowski, Bernhard. See—

Dreischhoff, Dieter; Geisler, Joerg-Peter; Godau, Claus; Hoemel, Michael; and Stengel-Rutkowski, Bernhard, 5,587,409, Cl. 523-404.000.

Stenger, Frank. See—

Johnson, Steven A.; Wiskin, James W.; Borup, David T.; Christensen, Douglas A.; and Stenger, Frank, 5,588,032, Cl. 378-8.000.

Stenger-Smith, John D.; Norris, William P.; and Chafin, Andrew P., to United States of America, Navy. Bis-sulfonium salts of amino substituted bis(halomethyl) benzene. 5,587,488, Cl. 549-59.000.

Stephan, Craig H. See—

Stevenson, Paul E.; Stephan, Craig H.; Samman, Amer M.; and Spangler, Leland J., 5,587,518, Cl. 73-1.000.

Stephens, James A. See—

Altschuler, Barry N.; Hardy, Douglas A.; Stephens, James A.; and Kish, Joseph, III, 5,588,062, Cl. 380-30.000.

Stephenson, Stanley W., III. See—

Seamans, Tom; and Stephenson, Stanley W., III, 5,587,757, Cl. 396-536.000.

Sterling Diagnostic Imaging, Inc. See—

Fabricius, Dietrich M.; Harms, Ralf H.; and Welter, James J., 5,587,482, Cl. 548-179.000.

Stern, Donald J.; and Treleven, Dan, to DJS&T Limited Partnership. Magnetic paint composition and method. 5,587,102, Cl. 252-62.540.

Stevens, James E. See—

Cecchi, Joseph L.; and Stevens, James E., 5,587,038, Cl. 156-345.000.

Stevenson, Paul E.; Stephan, Craig H.; Samman, Amer M.; and Spangler, Leland J., to Ford Motor Company. Accelerometer with a combined self-test and ground electrode. 5,587,518, Cl. 73-1.000.

Stewart, Roger G. See—

Hseuh, Fu-Lung; Ipri, Alfred C.; Dolny, Gary M.; and Stewart, Roger G., 5,587,329, Cl. 437-40.000.

Stief, Reinhard; and Müller-Broll, Gerhard, to Firma Carl Freudenberg. Noise damper. 5,587,564, Cl. 181-295.000.

Stiftung, Carl Zeiss. See—

Weber, Uwe, 5,586,467, Cl. 74-57.000.

Stillwagon, Woodrow C. Resealable fastening device. 5,586,794, Cl. 292-252.000.

Stockmeier, Thomas. See—

Jaacklin, André; Ramezani, Ezatollah; Roggwiller, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.

Stoddard, Damon R. See—

Foot, Steven A.; and Stoddard, Damon R., 5,587,530, Cl. 73-514.230.

Stolten, Detlef. See—

Spaeh, Richard; Schaefer, Wolfgang; Stolten, Detlef; and Fandel, Marco, 5,587,251, Cl. 429-33.000.

Stone, Kevin R.; Klebahn, Perry A.; and Knapp, William R. Arthrometer with gravity switches and adjustable limit signaling. 5,586,559, Cl. 128-782.000.

Stopa, John M. Balanced dual flow regenerator heat exchanger system and core driving system. 5,586,430, Cl. 60-39.511.

Stork, David G. See—

Furuta, Toshiyuki; Motomura, Shuji; Watanabe, Takahiro; and Stork, David G., 5,588,090, Cl. 395-23.000.

Straehler, Bernd. See—

Lorenz, Hans P.; Straehler, Bernd; and Lindegren, Ulf, 5,587,200, Cl. 427-2.240.

Straeter, Joseph G. See—

Craig, Frank; Straeter, Joseph G.; and Weder, Donald E., 5,586,425, Cl. 53-449.000.

Stratasy, Inc. See—

Abrams, Steven R.; Korein, James U.; Srinivasan, Vijay; and Tarabanis, Konstantinos, 5,587,913, Cl. 364-468.260.

Strecker, Darlene N. See—

Wedell, Eric D.; and Strecker, Darlene N., 5,586,926, Cl. 451-59.000.

Streisel, Robert C.; Hank, Mark A.; Mulcahy, Leo T.; and Peterson, Ralph S., to Westvaco Corporation. Pulp and paper products produced from recycled high lignin content, waste paper. 5,587,048, Cl. 162-7.000.

Streit, Peter. See—

Jaacklin, André; Ramezani, Ezatollah; Roggwiller, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.

Strohecker, Cary A., Sr. See—

Berkowitz, Gary M.; Daugherty, Thomas H.; Edwards, Rand J.; Klerer, S. Mark; Meader, Lyla R.; and Strohecker, Cary A., Sr., 5,588,051, Cl. 379-243.000.

Strolle, Christopher H.; Jaffe, Steven T.; and Lyons, Paul W., to David Sarnoff Research Center, Inc. Single oscillator compressed digital information receiver. 5,588,025, Cl. 375-316.000.

Strom, Terry B., to Beth Israel Hospital Association, The. Treatment of allograft rejection with IL-2 receptor-specific cytotoxins. 5,587,162, Cl. 424-183.100.

Strom, William M. See—

Olson, Timothy L.; Carney, Lauriann T.; Johnson, Gary C.; and Strom, William M., 5,587,883, Cl. 361-723.000.

Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., 5,587,605, Cl. 257-666.000.

Stroosnyder, Peter C., to Environmental Technologies Group, Inc. Method and an apparatus for an air sample analysis. 5,587,581, Cl. 250-287.000.

Strout, Terry H. See—

Aho, Wilho V., Jr.; Jones, Stephen R.; Chetta, Gregory E.; and Strout, Terry H., 5,587,068, Cl. 210-188.000.

Stuck, Kaaren L. See—

Bai, Baocheng; Guner, Mahmut; Lu, Duojia; Rosenblitt, David A.; and Stuck, Kaaren L., 5,588,138, Cl. 395-497.040.

Studiecentrum voor Kernenergie. See—

Bruggeman, Aimé; and Braet, Johan, 5,587,047, Cl. 159-47.300.

Stupek, Richard A., Jr.; Shaffer, David S.; Jones, Curtis R.; Davis, Steve; and Justice, William D., Jr., to Compaq Computer Corporation. Automatic computer upgrading. 5,588,143, Cl. 395-500.000.

Stupica, L. Joseph. See—

Babuder, Kirt M.; Joseph, Douglas A.; Pistor, Donald; and Stupica, L. Joseph, 5,586,477, Cl. 82-126.000.

Sturla, Jean M. See—

Caisey, Laurence; and Sturla, Jean M., 5,587,170, Cl. 424-401.000.

Sturm, Alwin. See—

Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, 5,587,421, Cl. 524-591.000.

Su, Chung-Hui; Liang, Mong-Song; Wu, Shou-Gwo; and Wang, Chen-Jong, to Taiwan Semiconductor Manufacturing Company Ltd. High resistance polysilicon resistor for integrated circuits and method of fabrication thereof. 5,587,696, Cl. 338-314.000.

Su, Liang-Feng. Easel show file display books. 5,586,786, Cl. 281-33.000.

Subrahmanyam, Ravichandran. See—

Lin, Jong-Kai; Lytle, William H.; and Subrahmanyam, Ravichandran, 5,587,342, Cl. 437-209.000.

Sueda, Akihiro. See—

Kawasaki, Masayuki; Kuwasima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, 5,587,683, Cl. 327-538.000.

Suematsu, Shigenori. See—

Shinohara, Makoto; Matsumoto, Yoshikane; and Suematsu, Shigenori, 5,586,496, Cl. 101-93.040.

Suetsch, Franz. See—

Schnitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas, 5,586,992, Cl. 8-653.000.

Sugahara, Hiroto; and Takahashi, Yoshikazu, to Brother Kogyo Kabushiki Kaisha. Ink jet apparatus using pressure wave intersection to eject ink droplets. 5,587,727, Cl. 347-12.000.

Suganuma, Tsuneo. See—

Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332.000.

Sugimura, Yoh. See—

Yukawa, Yoshiyuki; Yabuta, Motoshi; Nakahata, Akimasa; and Sugimura, Yoh, 5,587,426, Cl. 525-124.000.

Sugino, Osamu; and Yamamoto, Takeo, to Canon Kabushiki Kaisha. Image forming apparatus with different potentials in different developing zones. 5,587,780, Cl. 355-274.000.

Sugiura, Hideyuki. See—

Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Issei; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.

Sugiura, Koichi. See—

Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554.000.

Sugiura, Michihiko, to Yokohama Rubber Co., Ltd., The. Golf ball. 5,586,951, Cl. 473-379.000.

Sugiyama, Isao. See—

Negi, Shigeto; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222.000.

Sugiyama, Mitsuhiro, to NEC Corporation. Semiconductor device having semiconductor active and dummy regions with the dummy regions lower in height than the active regions. 5,587,612, Cl. 257-506.000.

Sugiyama, Mitsumasa, to Canon Kabushiki Kaisha. Data recognition equipment and method using partial pattern recognition. 5,588,074, Cl. 382-209.000.

Sukigara, Masayuki; and Kubo, Isao, to Asahi Kasei Kogyo Kabushiki Kaisha. Potentiators of antimicrobial activity. 5,587,358, Cl. 514-11.000.

Sukumar, Subramaniam, to Bruker Instruments, Inc. Shimming method for NMR magnet using unshielded gradient systems. 5,587,658, Cl. 324-309.000.

Sullivan, Chris; Wells, Jim; and Prevost, Michael, to Borg-Warner Automotive, Inc. Method of welding vanes into a shell for a torque converter. 5,587,092, Cl. 219-113.000.

Sullivan, M. David, to Voodoo Scientific, Inc. Apparatus for defeating radar speed detection signals. 5,588,057, Cl. 380-15.000.

Sulzbach, Hans-Michael; and Röhrig, Lothar, to Maschinenfabrik Hennecke GmbH. Apparatus for the production of endless polyurethane moldings. 5,587,182, Cl. 425-4.000.

Sumikawa, Noburo. See—

Nagamoto, Itsushi; Sumikawa, Noburo; Hirakawa, Tatsuya; and Nakanishi, Tatsuo, 5,586,944, Cl. 473-248.000.
 Sumitomo Chemical Company, Limited: See—
 Abe, Hiroaki; Nagaoka, Kenji; and Sanada, Takashi, 5,587,427, Cl. 525-145.000.
 Akiyoshi, Kazunori; and Niwano, Masahiro, 5,587,450, Cl. 528-310.000.
 Fujiwara, Shinji; Tabuchi, Hiroshi; and Takahashi, Akihiko, 5,587,140, Cl. 423-297.000.
 Iyechika, Yasushi; and Takada, Tomoyuki, 5,587,014, Cl. 117-90.000.
 Kubo, Kohji; Nezu, Shochi; Ishibashi, Fumio; Harada, Hiroyuki; and Shigematsu, Yui, 5,587,247, Cl. 428-523.000.
 Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, 5,587,260, Cl. 430-7.000.
 Tomioka, Jun; Uetani, Yasunori; Nakanishi, Hiroto; Hanawa, Ryotaro; and Ida, Ayako, 5,587,492, Cl. 549-406.000.
 Sumitomo Electric Industries, Ltd.: See—
 Ikegaya, Akihiko; Tanabe, Kenichiro; and Fujimori, Naoki, 5,587,013, Cl. 117-89.000.
 Sumitomo Metal Industries, Ltd.: See—
 Yamanaka, Shiro; and Hashimoto, Takao, 5,587,017, Cl. 118-424.000.
 Sumitomo Rubber Industries, Ltd.: See—
 Endo, Seichiro, 5,586,950, Cl. 473-356.000.
 Sakaki, Toshiaki; and Nakade, Shinichi, 5,587,411, Cl. 524-17.000.
 Sumitomo Wiring Systems, Ltd.: See—
 Kawamura, Shigetoshi, 5,588,080, Cl. 385-78.000.
 Muta, Junji, 5,586,901, Cl. 439-342.000.
 Okada, Naohisa, 5,586,899, Cl. 439-287.000.
 Saba, Toshikazu, 5,586,909, Cl. 439-559.000.
 Taniuchi, Osamu; and Hiroyuki, Nakata, 5,586,894, Cl. 439-157.000.
 Sumiyoshi, Masayuki: See—
 Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugiura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heiji, 5,587,060, Cl. 204-554.000.
 Sun Medical Co., Ltd.: See—
 Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, 5,587,406, Cl. 523-116.000.
 Sun Microsystems, Inc.: See—
 Aziz, Ashar, 5,588,060, Cl. 380-30.000.
 Bhatia, Pradeep H., 5,588,114, Cl. 395-183.010.
 Borrelli, Paul L., 5,588,131, Cl. 395-473.000.
 Jeong, Deog-Kyoon, 5,587,709, Cl. 341-100.000.
 Moffat, Guy, 5,587,726, Cl. 345-201.000.
 Spano, Joseph M.; Antonuccio, Robert S.; and Carney, James M., 5,587,879, Cl. 361-685.000.
 Sunaga, Yosio: See—
 Ueba, Hisaaki; Sunaga, Yosio; and Nagasima, Tosio, 5,587,239, Cl. 428-362.000.
 Sundstrand Corporation: See—
 Bansal, Madan L.; and Vaidya, Jayant G., 5,587,647, Cl. 322-45.000.
 Johnson, Tyrone A., 5,587,616, Cl. 310-68.000.
 Rozman, Gregory J., 5,587,641, Cl. 318-801.000.
 Sunohara, Kazuyuki; Hasegawa, Rei; Nagata, Hiroyuki; Sanada, Shinichi; and Kawata, Yasushi; to Kabushiki Kaisha Toshiba. Display device, 5,587,819, Cl. 349-106.000.
 SunSmart, Inc.: See—
 Mitchell, Kim; and Mitchell, Mark, 5,587,148, Cl. 424-59.000.
 Support Systems, International: See—
 Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard J.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
 Suri, Salil; and Teymour, Sassan; to Adaptec, Inc. Time domain signal filter, 5,587,686, Cl. 327-552.000.
 Suttles, J. Marshall: See—
 Spamer, William S.; Suttles, J. Marshall; Parham, Dennis E.; and Whiten, James D., 5,586,687, Cl. 221-298.000.
 Suron, William T.: See—
 Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard J.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710.000.
 Suwa, Mitsuru; to Tsudakoma Kogyo Kabushiki Kaisha. Cloth roll driving apparatus for driving the cloth roll at two different speeds, 5,586,581, Cl. 139-304.000.
 Suwijn, Paul W.; to Gleason Works, The. Machine tool chip removal system, 5,586,848, Cl. 409-137.000.
 Suzuki, Fumio; Shimada, Junichi; Koike, Nobuaki; Nakamura, Joji; Shiozaki, Shizuo; Ichikawa, Shunji; Ishii, Akio; and Nonaka, Hiromi; to Kyowa Hakko Kogyo Co., Ltd. Therapeutic agent for Parkinson's disease, 5,587,378, Cl. 514-264.000.
 Suzuki, Hideaki: See—
 Kouchi, Takao; and Suzuki, Hideaki, 5,586,614, Cl. 180-190.000.
 Suzuki, Hideki; and Kohda, Katsuhiko; to Fuji Photo Film Co., Ltd. Process for the preparation of radiation image storage panels, 5,587,033, Cl. 156-164.000.
 Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo; to Hitachi, Ltd. Magnetic recording medium and magnetic recording apparatus, 5,587,235, Cl. 428-332.000.
 Suzuki, Masato: See—

Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.
 Suzuki Motor Corporation: See—
 Satoh, Hideto, 5,586,698, Cl. 224-42.240.
 Syomura, Nobuyuki, 5,586,535, Cl. 123-352.000.
 Suzuki, Ryo: See—
 Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshinouchi, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
 Suzuki, Shinichi; Seki, Yukihiko; and Hattori, Ryuichi; to Hitachi, Ltd. Bus synchronizing method and system based thereon, 5,588,004, Cl. 370-516.000.
 Suzuki, Shin'ichi: See—
 Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
 Suzuki, Takeshi; and Sekine, Atsushi; to Nikon Corporation. Variable magnification image taking device, 5,587,739, Cl. 348-347.000.
 Suzuki, Tosio: See—
 Shindo, Yasuhiro; Yamaguchi, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro; and Kitabatake, Syoichi, 5,587,320, Cl. 435-290.100.
 Suzuki, Yasumichi: See—
 Saito, Hiroshi; Suzuki, Yasumichi; and Tamura, Naoyuki, 5,587,205, Cl. 427-553.000.
 Suzuki, Yoshio; and Nakajima, Yoshiharu; to Sony Corporation. Active matrix display device, 5,587,722, Cl. 345-94.000.
 Swamy, N. Deepak; to Dell USA, L.P. Mechanical printed circuit board/laminated multi chip module interconnect apparatus, 5,587,885, Cl. 361-777.000.
 Swaroop, Srinivas H.; and Wusirika, Raja R.; to Corning Incorporated. Exhaust gas conversion method using thermally stable zeolites, 5,587,137, Cl. 423-239.200.
 Swartz, David M.: See—
 Baker, Ronald J.; Fisher, Douglas G.; Rupert, Martha L.; and Swartz, David M., 5,586,915, Cl. 439-733.100.
 Swenson, Sabrina L.: See—
 Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,161, Cl. 424-218.100.
 Swinney, Louis E. Constant velocity joint with spherical ball and tongue and groove interconnection, 5,586,939, Cl. 464-106.000.
 Sydio Inc.: See—
 Love, Leonard S., 5,587,067, Cl. 210-155.000.
 Symbios Logic Inc.: See—
 DeKoning, Rodney A.; Humlick, Donald R.; and Johnson, Max L., 5,588,110, Cl. 395-182.030.
 Schmitt, Kenneth C., 5,587,675, Cl. 327-99.000.
 Symbiosis Corporation: See—
 Hahnen, Kevin F.; Farkas, Laszlo; and Gordon, David P., 5,586,990, Cl. 606-170.000.
 Syomura, Nobuyuki; to Suzuki Motor Corporation. Engine rotational number controller, 5,586,535, Cl. 123-352.000.
 Szekely, Istvan: See—
 Hajmichael, Janis; Botar, Sandor; Bleicher, Edit; Pap, Laszlo; Szekely, Istvan; Marmaros, nee Kellner, Katalin; and Ori, Janos, 5,587,370, Cl. 514-183.000.
 Szmadzinski, John A.; to Herman Miller, Inc. Height adjustment mechanism for a chair backrest, 5,586,809, Cl. 297-353.000.
 Szpak, Archana; to Ford Motor Company. Fluorescent electroluminescent lamp, 5,586,879, Cl. 445-24.000.
 T Z Medical, Inc.: See—
 Spivey, Thomas R.; and Zahler, Byron G., 5,586,556, Cl. 128-697.000.
 Tabersky, Ralf: See—
 König, Udo; Van Den Berg, Hendrikus; and Tabersky, Ralf, 5,587,233, Cl. 428-325.000.
 Tabuchi, Hiroshi: See—
 Fujiwara, Shinji; Tabuchi, Hiroshi; and Takahashi, Akihiko, 5,587,140, Cl. 423-297.000.
 Tachi-S Co., Ltd.: See—
 Katsuta, Kazuo; and Abe, Tadafumi, 5,586,377, Cl. 29-91.500.
 Tachibana, Hidehiko: See—
 Kawasaki, Masayuki; Kuwasima, Yasunori; Tachibana, Hidehiko; Katsuki, Syuji; and Sueda, Akihiro, 5,587,683, Cl. 327-538.000.
 Tadros, Alfred H.: See—
 Chu, Peter Y.; and Tadros, Alfred H., 5,587,714, Cl. 342-354.000.
 Tafoya, Anthony S.: See—
 Martinez, Marcus J.; and Tafoya, Anthony S., 5,586,974, Cl. 604-26.000.
 Taggart, Russell C.; to Atoma International Of America, Inc. Vehicle seat trim cover retainer, 5,586,807, Cl. 297-218.500.
 Tai, David. Manually operated video cassette adapter, 5,587,853, Cl. 360-94.000.
 Taiwan Semiconductor Manufacturing Company Ltd.: See—
 Su, Chung-Hui; Liang, Mong-Song; Wu, Shou-Gwo; and Wang, Chen-Jong, 5,587,696, Cl. 338-314.000.
 Tajima, Hisao: See—
 Miyamoto, Takao; and Tajima, Hisao, 5,587,817, Cl. 349-187.000.
 Tajiri, Akihiro: See—

Ikeda, Susumu; Isohe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
 Takada, Tomoyuki: See—
 Iyechika, Yasushi; and Takada, Tomoyuki, 5,587,014, Cl. 117-90.000.
 Takagaki, Tokuhiko: See—
 Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332.000.
 Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyairi, Yoshio; Hattori, Toshio; and Hagiwara, Haruo; to Mitsubishi Jukogyo Kabushiki Kaisha. Apparatus for washing and drying clothes, 5,586,456, Cl. 68-18.000.
 Takagawa, Hiroyuki: See—
 Kawahara, Yoshitaka; Kudo, Kazunori; Nakatani, Yoshihide; and Takagawa, Hiroyuki, 5,586,523, Cl. 123-65.0VB.
 Takagi, Hiroshi: See—
 Fujino, Masaru; and Takagi, Hiroshi, 5,587,015, Cl. 117-200.000.
 Takagi, Kazuhiro: See—
 Hattanda, Hirokatsu; Ogiso, Mitsukazu; Koike, Yasuta; and Takagi, Kazuhiro, 5,587,101, Cl. 222-603.000.
 Takagi, Masahiro: See—
 Ikeda, Susumu; Isohe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.
 Takahashi, Akihiko: See—
 Fujiwara, Shinji; Tabuchi, Hiroshi; and Takahashi, Akihiko, 5,587,140, Cl. 423-297.000.
 Takahashi, Duane M. P.: See—
 Price, Noah M.; Takahashi, Duane M. P.; and Buuck, David C., 5,587,887, Cl. 361-794.000.
 Takahashi, Jun: See—
 Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.
 Takahashi, Koichi; and Togino, Takayoshi; to Olympus Optical Co., Ltd. Visual display apparatus, 5,587,836, Cl. 359-630.000.
 Takahashi, Kouichi: See—
 Arita, Kiyoshi; and Takahashi, Kouichi, 5,586,713, Cl. 228-102.000.
 Takahashi, Mitsuo; to Seikoh Giken Co., Ltd. Light coupling device to couple a light source to an optical fiber, 5,588,081, Cl. 385-93.000.
 Takahashi, Osamu: See—
 Wakamoto, Akiko; Takahashi, Osamu; Furuhashi, Keizo; and Miura, Akira, 5,587,303, Cl. 435-116.000.
 Takahashi, Tokuji: See—
 Nishizawa, Seiji; Takahashi, Tokuji; and Hattori, Ryo, 5,587,792, Cl. 355-356.000.
 Takahashi, Toyofumi: See—
 Otake, Masahiro; Takahashi, Toyofumi; Nishiumi, Satoshi; and Otsuki, Takashi, 5,587,723, Cl. 345-118.000.
 Takahashi, Yoshikazu: See—
 Sugahara, Hiroto; and Takahashi, Yoshikazu, 5,587,727, Cl. 347-12.000.
 Takama, Kazushi: See—
 Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohsugi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323.000.
 Takami, Hiroshi; Yasui, Yoshihiro; and Okumura, Takashi; to Brother Kogyo Kabushiki Kaisha. Stencil stamp, 5,586,500, Cl. 101-327.000.
 Takano, Hideto; to NEC Corporation. Frequency subband encoding apparatus, 5,588,024, Cl. 375-242.000.
 Takao, Hideaki: See—
 Togano, Takeshi; Takao, Hideaki; Asaoka, Masanobu; and Kojima, Makoto, 5,587,211, Cl. 428-1.000.
 Takao, Yuuechi; and Oogami, Hidetoshi; to Kohjin Co., Ltd. Method of manufacturing N-monosubstituted (meth)acrylamides, 5,587,515, Cl. 564-135.000.
 Takasago International Corporation: See—
 Konno, Masao; and Yuasa, Yoshifumi, 5,587,510, Cl. 562-496.000.
 Takase, Hiraji: See—
 Shinji, Yasuhisa; and Takase, Hiraji, 5,586,897, Cl. 439-271.000.
 Shinji, Yasuhisa; Morishita, Kazuhiro; and Takase, Hiraji, 5,586,916, Cl. 439-752.000.
 Takashi, Ono: See—
 Masayuki, Watanabe; Toshio, Sugano; Seichiro, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima, 5,587,341, Cl. 437-206.000.
 Takashima, Kazushige: See—
 Minato, Tetsuya; Yonehara, Toshimitsu; Teranishi, Junichi; Toyoda, Shohji; Bito, Toshiaki; and Takashima, Kazushige, 5,587,694, Cl. 336-65.000.
 Takatani, Munee; Kozai, Yoshio; Tomimatsu, Kiminori; and Shibouta, Yumiko; to Takeda Chemical Industries, Ltd. Imidazopyridine derivatives and their use, 5,587,383, Cl. 514-300.000.
 Takayama, Toru: See—
 Naito, Hiroki; Kume, Masahiro; Sugiura, Hideyuki; Takayama, Toru; Itoh, Kunio; Ohta, Isser; and Shimizu, Hirokazu, 5,587,334, Cl. 437-129.000.
 Take, Seiji: See—
 Iijima, Masayuki; Dantani, Kyoji; Obata, Hiroyuki; Matsuo, Makoto; Utsumi, Minoru; and Take, Seiji, 5,587,264, Cl. 430-57.000.
 Takebe, Hiroshi; and Hagiwara, Masao; to Kabushiki Kaisha Komatsu Seisakusho. Serial controller, 5,587,995, Cl. 370-248.000.
 Takeda Chemical Industries, Ltd.: See—

Takatani, Munee; Kozai, Yoshio; Tomimatsu, Kiminori; and Shibouta, Yumiko, 5,587,383, Cl. 514-300.000.
 Tanaka, Nobuo; Otani, Seiji; Kawakita, Hiroyuki; and Matsuda, Teruo, 5,586,975, Cl. 604-89.000.
 Takeda, Hisao; to HYMO Corporation. Process for preparation of dispersion of water-soluble cationic polymer the dispersion produced thereby and its use, 5,587,415, Cl. 524-458.000.
 Takeda, Masayuki: See—
 Ue, Makoto; Sato, Tomohiro; and Takeda, Masayuki, 5,587,871, Cl. 361-504.000.
 Takeda, Shin: See—
 Takeuchi, Kiyoshi; Takeda, Shin; and Nakamura, Masao, 5,586,462, Cl. 72-150.000.
 Takehara, Shin: See—
 Shibata, Mineharu; and Takehara, Shin, 5,587,907, Cl. 364-424.046.
 Takei, Chiemi: See—
 Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, 5,587,197, Cl. 426-658.000.
 Takemura, Hisashi; to NEC Corporation. Method of forming bipolar junction transistor of epitaxial planar type, 5,587,326, Cl. 437-31.000.
 Takeshita, Takuo: See—
 Nakayama, Ryoji; Takeshita, Takuo; and Watanabe, Muneaki, 5,587,024, Cl. 148-101.000.
 Takeuchi, Hiroshi: See—
 Mizukami, Hiroshi; Uenohara, Norihisa; and Takeuchi, Hiroshi, 5,586,633, Cl. 192-70.250.
 Takeuchi, Kiyoshi; Takeda, Shin; and Nakamura, Masao; to Aisin Seiki Kabushiki Kaisha; and Masao Nakamura. Device and method for forming bent pipe of non-annular cross-section, 5,586,462, Cl. 72-150.000.
 Takeuchi, Tatsuo: See—
 Fukushima, Hisashi; Takeuchi, Tatsuo; Sakoh, Harumi; and Sasanuma, Nobuatsu, 5,587,778, Cl. 355-246.000.
 Takeuchi, Yukihiko: See—
 Kano, Kazuhiko; Takeuchi, Yukihiko; Watanabe, Takamoto; Ao, Kenichi; Kanosue, Masakazu; and Uenoyama, Hirofumi, 5,587,343, Cl. 437-228.000.
 Takigen Manufacturing Co., Ltd.: See—
 Sasaki, Shunji, 5,586,795, Cl. 292-336.300.
 Takishima, Suguru: See—
 Kanazawa, Hiroshi; Okuda, Isao; Shinozaki, Shimpei; and Takishima, Suguru, 5,587,973, Cl. 369-13.000.
 Takizawa, Toshiaki; and Iwai, Kazuo; to YKK Corporation. Curtain attachment connector, 5,586,595, Cl. 160-330.000.
 Takizawa, Toshiaki; Horikawa, Yasuo; and Akazawa, Taro; to Bridgestone Corporation. Diene polymer obtained by adding a tin compound in the polymerization with an organolithium initiator, 5,587,420, Cl. 524-572.000.
 Taleyarkhan, Rusi P.; to Lockheed Martin Energy Research Corp. Method to prevent/mitigate steam explosions in casting pits, 5,586,597, Cl. 164-487.000.
 Talkowski, Charles J.; to Du Pont de Nemours, E. I., and Company. Ethylene-acid copolymer and ionomer blends having improved high temperature properties and processibility, 5,587,430, Cl. 525-196.000.
 Tallier, Bernard: See—
 Babey, Jacques; Salmon, Brian; De Borst, Eric; and Tallier, Bernard, 5,586,565, Cl. 131-84.200.
 Tamarkin, Lawrence; and Paciotti, Giulio F.; to Assay Research, Inc. Method and kit for measuring endogenous cytokines, 5,587,294, Cl. 435-7.930.
 Tamura, Manabu: See—
 Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203.000.
 Tamura, Naoyuki: See—
 Saito, Hiroshi; Suzuki, Yasumichi; and Tamura, Naoyuki, 5,587,205, Cl. 427-553.000.
 Tamura, Yoshihiko; and Tsuchiya, Mitsuru; to Dai Nippon Printing Co., Ltd. Thermal transfer image-receiving sheet and process for producing the same, 5,587,352, Cl. 503-227.000.
 Tan, Lushi: See—
 Hoyer, Thomas R.; and Tan, Lushi, 5,587,491, Cl. 549-320.000.
 Tanabe, Kenichiro: See—
 Ikegaya, Akihiko; Tanabe, Kenichiro; and Fujimori, Naoki, 5,587,013, Cl. 117-89.000.
 Tanabe Seiyaku Co., Ltd.: See—
 Kondo, Kazuhiko; Horikawa, Hiroshi; and Iwasaki, Tameo, 5,587,474, Cl. 540-350.000.
 Tanabe, Takashi; and Yamamoto, Kouji; to NEC Corporation. Optical connector, 5,588,079, Cl. 385-78.000.
 Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Koshida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi; to Yoshino Kogyo Co., Ltd.; and Hayakawa Rubber Co., Ltd. Ink compositions, 5,587,405, Cl. 522-98.000.
 Tanaka, Chiaki; Sasaki, Masami; Aruga, Tamotsu; Shimada, Tomoyuki; and Adachi, Hiroshi; to Ricoh Company, Ltd. Electrophotographic photoconductor comprising pyrenylamine derivative, the pyrenylamine derivative, intermediate for preparation thereof, and method for preparing the pyrenylamine derivative and the intermediate, 5,587,516, Cl. 564-405.000.
 Tanaka, Harumi: See—
 Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, 5,587,406, Cl. 523-116.000.
 Tanaka, Hiroshi; and Hosoya, Kazuki; to Sanden Corporation. Heat exchanger, 5,586,598, Cl. 165-133.000.

- Tanaka, Nobuo; Orani, Seiji; Kawakita, Hiroyuki; and Matsuda, Teruo, to Takeda Chemical Industries, Ltd., and Arte Corporation, Air and liquid tight container with a slidable gasket. 5,586,975, Cl. 604-89,000.
- Tanaka, Shoji; Imura, Katsuhiko; and Kageyama, Satoshi, to Masushita Electric Industrial Co., Bass reproduction speaker apparatus. 5,588,065, Cl. 381-96,000.
- Tanaka, Takehiko, to Fujitsu Limited, Data processing device in a virtual memory having a paging function. 5,588,135, Cl. 395-487,000.
- Tanaka, Yasuyuki, to Canon Kabushiki Kaisha, Image display apparatus. 5,587,744, Cl. 348-556,000.
- Tanaka, Yasuyuki, *See*—
Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohnogi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323,000.
- Tanemachi, Tokunosuke, *See*—
Nakata, Kiyoshi; Tanemachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41,000.
- Tandem Computers, Incorporated, *See*—
Cuttis, Richard W., Jr.; Banton, Randall G.; and Jewett, Douglas E., 5,588,111, Cl. 395-182,070.
- Tani, Kazutoshi, *See*—
Imai, Toru; Nishimura, Hiroshi; Nishimura, Nobuchir; Imai, Masahiro; Tani, Kazutoshi; and Hirano, Takayuki, 5,586,455, Cl. 68-12,020.
- Tanida, Susumu, to Mitsubishi Denki Kabushiki Kaisha, Semiconductor memory device having function of generating boosted potential. 5,587,950, Cl. 365-226,000.
- Taniguchi, Kazuko; Ikegawa, Akihito; Uno, Koji; and Saito, Hitoshi, to Minolta Co., Ltd., Image forming apparatus with rotating brush for charging. 5,587,775, Cl. 355-219,000.
- Tanuchi, Osamu, and Hiroyuki, Nakata, to Sumitomo Wiring Systems, Ltd., Multiple lever connector assembly. 5,586,894, Cl. 439-157,000.
- Tarabans, Constantin, *See*—
Abrams, Steven R.; Korein, James U.; Srinivasan, Vijay; and Tarabans, Constantin, 5,587,913, Cl. 364-468,260.
- Taraseon, Jean-Marie, *See*—
Amatucci, Glenn G., and Taraseon, Jean-Marie, 5,587,133, Cl. 423-138,000.
- Tariya, Masaaki, and Koiwa, Mitsuru, to Mitsubishi Denki Kabushiki Kaisha, Ignition apparatus for internal combustion engine. 5,586,542, Cl. 123-609,000.
- Tarzia, Giorgio, *See*—
Perboni, Alcide; Rossi, Tino; Gavraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonella, 5,587,374, Cl. 514-210,000.
- Tasaka, Yoshihiro, *See*—
Miyano, Masaaki; Kawasaka, Toyotoshi; Kuwana, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824,000.
- Tashima, Takahiro, *See*—
Aoki, Hideji; Tashima, Takahiro; Nakashima, Suckazu; Osako, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164,000.
- Tatarka, Paul, *See*—
Borchers, Gerald; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrhalak, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mazurek, Olivier, 5,587,412, Cl. 524-47,000.
- Tatsu, Haruyoshi, *See*—
Enokida, Takashi; Naraki, Akihito; Yamashita, Eiichi; and Tatsu, Haruyoshi, 5,587,413, Cl. 524-200,000.
- Tatsumo Kabushiki Kaisha, *See*—
Ohyama, Keisshi, 5,587,637, Cl. 318-568,110.
- Tatum, Fred M., *See*—
Briggs, Robert E.; and Tatum, Fred M., 5,587,305, Cl. 435-172,100.
- Tatuni, Lawrence G., *See*—
Mattern, Charles J., Jr.; and Tatum, Lawrence G., 5,586,847, Cl. 408-239,000.
- Taveroff, Alan L., to Canadian Plastics Inc., Cosmetic package. 5,586,653, Cl. 206-362,000.
- Tawzer, Charles, to A-1 All Weather Roofing, Inc., System for resurfacing a roof with a cantilever edge. 5,586,414, Cl. 52-57,000.
- Taylor, Matthew, *See*—
Graham, Martin H.; and Taylor, Matthew, 5,587,692, Cl. 333-12,000.
- Taylor, Stephen D., Display arrangement. 5,586,664, Cl. 211-58,000.
- Tayse, Louis C., *See*—
Desai, Dhimit R.; Tayse, Louis C.; and Gideon, Richard W., 5,587,634, Cl. 318-257,000.
- THL Co., Ltd., *See*—
Sasaki, Ryo; and Ina, Toshiro, 5,587,418, Cl. 524-504,000.
- Tecnoma, *See*—
Ballu, Patrick J., 5,586,725, Cl. 239-172,000.
- Tedesco, James M., *See*—
Chang, Hyung J.; and Tedesco, James M., 5,587,847, Cl. 359-890,000.
- Tetel, Michael A., *See*—
Lamer, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Tetel, Michael A., 5,588,139, Cl. 395-500,000.
- Tektronix, Inc., *See*—
Kroon, Stephen M., 5,588,094, Cl. 395-109,000.
- Telefonaktiebolaget LM Ericsson, *See*—
Johansson, Ted; and Gohbi, Jose-Maria, 5,587,333, Cl. 437-60,000.
- Teletex Technologies, Inc., *See*—
Schub, Frank J., 5,586,609, Cl. 175-65,000.
- Teller, Cecil M., II, *See*—
McCloskey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., 5,587,534, Cl. 73-623,000.
- Temburg, Konrad, *See*—
Leifeld, Ferdinand; and Temburg, Konrad, 5,586,366, Cl. 19-105,000.
- TEMIC Bayern-Chemie Airbag GmbH, *See*—
Adam, Paul; Tillmann, Heinz, deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dolling, Uwe, 5,586,783, Cl. 280-737,000.
- Temteletfunken Microelectronic GmbH, *See*—
Kong, Ull; Grubbe, Andreas; Schuppen, Andreas; Kibbel, Horst; Dietrich, Harry; and Hefner, Heinz-Achim, 5,587,327, Cl. 437-31,000.
- Teng, Clarence W., *See*—
Hwang, Chong-Lit; and Teng, Clarence W., 5,587,614, Cl. 257-532,000.
- Teng, David, to Chen, Chung-Chin, Video display high voltage generator. 5,587,893, Cl. 363-61,000.
- Terada, Akihito, *See*—
Watanabe, Atsushi; Nihet, Ryo; and Terada, Akihito, 5,587,635, Cl. 318-434,000.
- Terada, Hiroshi, *See*—
Nakamura, Masahiko; Yamamoto, Hajime; and Terada, Hiroshi, 5,587,783, Cl. 355-326,000.
- Teradyne, Inc., *See*—
Aygarten, Michael H., 5,588,115, Cl. 395-183,050.
- Teraguchi, Nobuaki, *See*—
Murakami, Masanori; Koide, Yasuo; Teraguchi, Nobuaki; and Tomomura, Yoshitaka, 5,587,609, Cl. 257-744,000.
- Terajima, Hisao, *See*—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185,000.
- Teramishi, Junichi, *See*—
Minato, Tetsuya; Yonehara, Toshimitsu; Teramishi, Junichi; Toyoda, Shobei; Hito, Toshiaki; and Takashima, Kazushige, 5,587,694, Cl. 336-65,000.
- Teraoka, Iwao, and Luo, Min, High osmotic pressure chromatography. 5,587,082, Cl. 210-635,000.
- Terayama, Koji, *See*—
Kawanishi, Toshiaki; Nobutoki, Yoshikazu; Hirano, Seiji; and Terayama, Koji, 5,588,002, Cl. 370-462,000.
- ter Meer, Hans-Ulrich, *See*—
Kampe, Klaus-Dieter; ter Meer, Hans-Ulrich; Egger, Norbert K.; and Vogel, Martin A., 5,587,476, Cl. 540-472,000.
- Terrapin Technologies, Inc., *See*—
Kauvar, Lawrence M.; and Villar, Hugo O., 5,587,293, Cl. 435-7,210.
- Terry, Claude E.; Triestman, Douglas E.; and Price, Daniel L., to Interface, Inc., Biocidal polymeric coating for heat exchanger coils. 5,587,407, Cl. 523-122,000.
- Terunuma, Hiroshi, *See*—
Katayama, Akira; and Terunuma, Hiroshi, 5,587,754, Cl. 396-144,000.
- Terunuma, Mutsuhiro, *See*—
Nakata, Kiyoshi; Tanemachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41,000.
- Tetra Laval Holdings & Finance S.A., *See*—
Ek, Anders; and Hegardt, Johan, 5,587,640, Cl. 318-638,000.
- Tetra Laval Holdings & Finance SA, *See*—
Carlson, Leonard A., 5,587,127, Cl. 422-28,000.
- Sjostrom, Anders, 5,586,599, Cl. 165-143,000.
- Teuwen, Lihan M. J., *See*—
Koning, Cornelis E.; and Teuwen, Lihan M. J., 5,587,452, Cl. 528-350,000.
- Texas A&M University System, The, *See*—
Ehsani, Mehrdad, 5,586,613, Cl. 180-65,200.
- Texas Instruments Incorporated, *See*—
Belcher, James E.; Frank, Steven N.; Long, John P.; and Jones, Jeanee, 5,587,090, Cl. 216-17,000.
- Bosshart, Patrick W., 5,588,127, Cl. 395-376,000.
- Hashimoto, Masashi; Frantz, Gene A.; Moravec, John V.; and Dolan, Jean-Pierre, 5,587,962, Cl. 365-230,090.
- Hwang, Chong-Lit; and Teng, Clarence W., 5,587,614, Cl. 257-532,000.
- Morin, Daniel, 5,586,386, Cl. 29-622,000.
- Slaughter, John E.; Olson, George; and McShane, William J., 5,587,788, Cl. 356-246,000.
- Vogley, Wilbur C.; Balistren, Anthony M.; Guttig, Karl M.; Krieger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., 5,587,954, Cl. 365-221,000.
- Texton Inc., *See*—
Pierigo, Douglas E.; and Jansen, Leo B., 5,586,393, Cl. 33-288,000.
- Teymour, Sassan, *See*—
Sun, Salil; and Teymour, Sassan, 5,587,686, Cl. 327-552,000.
- Tharp, Charles E., to Environmental Dynamics, Inc., Aeration system employing retrievable aeration modules. 5,587,114, Cl. 261-124,000.
- Then, Johann; Aretz, Werner; and Sauber, Klaus, to Hoechst Aktiengesellschaft, Process for the preparation of L-phosphinothricin using transaminases of different specificities in a linked process. 5,587,319, Cl. 435-280,000.

- Thermacore, Inc., *See*—
Hartenstine, John R.; and Dussinger, Peter M., 5,586,549, Cl. 126-635,000.
- Thibault, Pierre, *See*—
Belleville, Claude; Van Neste, Richard; Caron, Serge; Houle, Alain C.; and Thibault, Pierre, 5,587,791, Cl. 356-345,000.
- Thiele, Reiner, *See*—
Brandstetter, Franz; Gausepohl, Hermann; and Thiele, Reiner, 5,587,423, Cl. 525-52,000.
- Thinesen, Tom, to Times Corporation, Mode preselect function for a multi-mode electronic timepiece. 5,587,971, Cl. 368-70,000.
- Thiokol Corporation, *See*—
Braithwaite, Paul C.; Lund, Gary K.; and Wardle, Robert B., 5,587,553, Cl. 149-19,600.
- Dillehay, David R.; and Turner, David W., 5,587,552, Cl. 149-19,500.
- Thirion de Briel, Jacques, to Valeo, Clutch mechanism, especially for a motor vehicle. 5,586,634, Cl. 192-70,270.
- Thiry, Michel, *See*—
Guezennec, Yannick; Koziot, Joseph; and Thiry, Michel, 5,587,190, Cl. 426-2,000.
- Tholen, Joseph H., *See*—
Vogel, Gerald A.; and Tholen, Joseph H., 5,587,089, Cl. 210-164,000.
- Thomas, Betty M., to Group J, Inc., Disposable body container. 5,586,679, Cl. 220-310,000.
- Thomas, Charles R., *See*—
Bowen, David K.; and Thomas, Charles R., 5,588,034, Cl. 378-73,000.
- Thomas, Dennis A., to Procter & Gamble Company, The, Method for manufacturing refastenable fastening systems including a female loop fastening component and the product produced therefrom. 5,586,371, Cl. 24-452,000.
- Thomas, Dennis A., to Procter & Gamble Company, The, Disposable absorbent article core integrity support. 5,586,979, Cl. 604-382,000.
- Thomas, Edward M., *See*—
O'Brien, John L.; Thomas, Edward M.; and Ed, Donald A. N., 5,586,352, Cl. 5-662,000.
- Thomas, George; and Moré, Georgina, to Motorola, Inc., Hybrid energy storage system. 5,587,250, Cl. 429-3,000.
- Thomas, Hewin N.; Haney, Jack E.; and Hamilton, Peter W., to Procter & Gamble Company, The, Child resistant package. 5,586,671, Cl. 215-209,000.
- Thomas, James M. C., *See*—
Stacy, Richard B.; Ellis, Craig D.; Hand, Barry D.; Thomas, James M. C.; Chambers, Kenneth W.; Glover, Stephen E.; Barnett, Richard I.; King, Paul B.; Ozarowski, Ryszard S.; and Sutton, William T., 5,586,346, Cl. 5-710,000.
- Thomas, Mark S., Rechargeable table lighting system with protection from short circuits. 5,587,646, Cl. 320-25,000.
- Thompson, Mark S., *See*—
Nardone, Vincent C.; Thompson, Mark S.; and Meyer, Thomas G., 5,586,471, Cl. 74-572,000.
- Thomson Consumer Electronics, Inc., *See*—
Griepentrog, Dal E.; and Sendelweck, Gene K., 5,587,745, Cl. 348-626,000.
- Wilber, James A.; and Koblitz, Karl R., 5,587,631, Cl. 315-403,000.
- Thomson CSF, *See*—
Chabbert, Philippe; Chateau, Alain; and Meus, Dominique, 5,587,660, Cl. 324-426,000.
- Thomebe, Douglas A., and Coons, Russell L., to United Technologies Corporation, Aircraft nacelle ventilation and engine exhaust nozzle cooling. 5,586,431, Cl. 64-226,100.
- Thonnessen, Franz; and Mulihhaus, Hans H., to Hoechst Aktiengesellschaft, Low flammability pillow. 5,586,350, Cl. 5-636,000.
- Tibbets, Gary G.; Nazri, Ghulam-Ahmad; and Howie, Blake J., to General Motors Corporation, Method of making lithium-ion cell having deactivated carbon anodes. 5,587,257, Cl. 429-218,000.
- TIC United Corp., *See*—
Roesch, Hans J.; and Beck, Steven R., 5,586,678, Cl. 220-263,000.
- Tiedemann, Edward G., Jr.; Karmi, Gad; and Quick, Frank, to Qualcomm Incorporated, Comprehensive mobile communications device registration method. 5,588,043, Cl. 379-63,000.
- Tilley, Jeffrey L., *See*—
Madison, Harry; and Tilley, Jeffrey L., 5,586,507, Cl. 105-215,200.
- Tillmann, Heinz, deceased (by Zita M. Tillmann, executor), *See*—
Adam, Paul; Tillmann, Heinz, deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dolling, Uwe, 5,586,783, Cl. 280-737,000.
- Tillmann, Zita M., executor, *See*—
Adam, Paul; Tillmann, Heinz, deceased; Werner, Michael; Renn, Peter; Reif, Joachim; and Dolling, Uwe, 5,586,783, Cl. 280-737,000.
- Timex Corporation, *See*—
Thinesen, Tom, 5,587,971, Cl. 368-70,000.
- Timmons, Alban, Method and apparatus for treating liquids. 5,587,087, Cl. 210-724,000.
- Tkach, Robert W., *See*—
Chaplysky, Andrew R.; and Tkach, Robert W., 5,587,830, Cl. 359-341,000.
- Toa Medical Electronics Co., Ltd., *See*—
Kurosaki, Tsuyoshi; Tomioka, Atsuo; and Yamato, Takashi, 5,587,129, Cl. 422-64,000.
- Toda, Haruki; Saito, Shozo; and Tokushige, Kaoru, to Kabushiki Kaisha Toshiba, Semiconductor memory device. 5,587,963, Cl. 365-236,000.
- Toda Kogyo Corporation, *See*—
Hayashi, Kazuyuki; Iwasaki, Keisuke; Tanaka, Yasuyuki; Ohnogi, Minoru; Harada, Toshiharu; Isoai, Masaru; and Takama, Kazushi, 5,587,232, Cl. 428-323,000.
- Todoroff, Brian D., *See*—
Bennett, Michael J.; Nino, John E.; and Todoroff, Brian D., 5,586,936, Cl. 463-25,000.
- Toepfer, Craig B., *See*—
Gale, Allan R.; and Toepfer, Craig B., 5,587,864, Cl. 361-44,000.
- Togano, Takeshi; Takao, Hideaki; Asaoka, Masanobu; and Kojima, Makoto, to Canon Kabushiki Kaisha, Liquid crystal device and liquid crystal apparatus including same. 5,587,211, Cl. 428-1,000.
- Togawa, Yoshiyuki; and Miura, Makoto, to Shimadzu Corporation, Sample collecting apparatus by gel electrophoresis. 5,587,062, Cl. 204-613,000.
- Togino, Takayoshi, *See*—
Takahashi, Koichi; and Togino, Takayoshi, 5,587,836, Cl. 359-630,000.
- Tohoku Pioneer Electronic Corporation, *See*—
Sato, Masatoshi, 5,587,562, Cl. 181-167,000.
- Toivio, Ilkka; Toivio, Terttu; and Oikkonen, Kari, to Ahlstrom Consumer Products Ltd., Air mattress and method for adjusting it. 5,586,348, Cl. 5-710,000.
- Toivio, Terttu, *See*—
Toivio, Ilkka; Toivio, Terttu; and Oikkonen, Kari, 5,586,348, Cl. 5-710,000.
- Tokheim Corporation, *See*—
Edwards, Robert W.; Fulmer, Terry M.; and Schultz, Patrick J., 5,586,583, Cl. 141-83,000.
- Tokico, Ltd., *See*—
Nezu, Takashi; and Kashiwagi, Akira, 5,586,627, Cl. 188-299,000.
- Tokushige, Kaoru, *See*—
Toda, Haruki; Saito, Shozo; and Tokushige, Kaoru, 5,587,963, Cl. 365-236,000.
- Tokyo Electron Limited, *See*—
Ohsawa, Tetsu, 5,586,880, Cl. 432-241,000.
- Tokyo Electron Tohoku Limited, *See*—
Ohsawa, Tetsu, 5,586,880, Cl. 432-241,000.
- Tokyo Yogyo Kabushiki Kaisha, *See*—
Hattanda, Hirokatsu; Ogiso, Mitsukazu; Koike, Yasuta; and Takagi, Kazuhiro, 5,587,101, Cl. 222-603,000.
- Tollar, Paul S.; and Wood, Russell E., to Carrier Corporation, Plural compressor oil level control. 5,586,450, Cl. 62-192,000.
- Tölle, Karl-Heinz; and Grothe, Hermann, to Ed. Scharwachter GmbH & Co. KG, Door stop, in particular for motor vehicle doors. 5,586,361, Cl. 16-51,000.
- Tombling, Craig, *See*—
May, Paul; Tombling, Craig; Robinson, Michael G.; Raynes, Edward P.; and Harrold, Jonathan, 5,587,820, Cl. 359-72,000.
- Tomimatsu, Kiminori, *See*—
Takatani, Munio; Kozai, Yoshio; Tomimatsu, Kiminori; and Shibouta, Yumiko, 5,587,383, Cl. 514-300,000.
- Tomioka, Atsuo, *See*—
Kurosaki, Tsuyoshi; Tomioka, Atsuo; and Yamato, Takashi, 5,587,129, Cl. 422-64,000.
- Tomioka, Jun; Uetani, Yasunori; Nakanishi, Hiroto; Hanawa, Ryotaro; and Ida, Ayako, to Sumitomo Chemical Company, Limited, Polyhydric phenol compound and positive resist composition comprising the same. 5,587,492, Cl. 549-406,000.
- Tomioka, Mitsuo, *See*—
Hasegawa, Toshiro; Shimoda, Kazuhiko; Makino, Kunio; and Tomioka, Mitsuo, 5,586,994, Cl. 29-623,500.
- Tomisawa, Naoki; and Watanabe, Satoru, to Unisia Jecs Corporation, Fuel property detecting apparatus for internal combustion engines. 5,586,537, Cl. 123-435,000.
- Tomita, Keichi, *See*—
Kurita, Kazuo; Mizutani, Mikio; Noma, Nobuhiko; Sakai, Tsukasa; Noguchi, Osamu; Nemoto, Hiroyuki; and Tomita, Keichi, 5,587,798, Cl. 358-261,100.
- Tomlinson, Harold W., *See*—
Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346,000.
- Tomoda, Akihiro, *See*—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185,000.
- Tomogawa Paper Co., Ltd., *See*—
Nakadera, Kazuo; Okutani, Haruo; and Kurebayashi, Hideki, 5,587,265, Cl. 430-109,000.
- Tomomura, Yoshitaka, *See*—
Murakami, Masanori; Koide, Yasuo; Teraguchi, Nobuaki; and Tomomura, Yoshitaka, 5,587,609, Cl. 257-744,000.
- Tomono, Mitsuru, *See*—
Abe, Naoki; Mizuno, Koji; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugura, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554,000.
- Tomotaki, Katsura, to Seiko Seiki Kabushiki Kaisha, Table driving device. 5,586,468, Cl. 74-89,150.
- Ton-that, Luan, to Quantum Corporation, Data track pattern including embedded servo sectors for magneto-resistive read/inductive write head structure for a disk drive. 5,587,850, Cl. 360-77,080.
- Toporkiewicz, Marian, *See*—

Gibbon, Michael A.; Maxwell, Ian; and Toporkiewicz, Marian, 5,587,750, Cl. 352-184.000.

Toray Industries, Inc. See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, 5,587,240, Cl. 428-367.000.

Torimitsu, Hiroshi, to Hoshizaki Denki Kabushiki Kaisha. Monitoring system for ice making machine, 5,586,446, Cl. 62-126.000.

Tornero, Lino E. Adjustment device for chair arms, 5,586,811, Cl. 297-411.360.

Törnquist, Anders. See—
Andersson, Mats; and Törnquist, Anders, 5,587,912, Cl. 364-468.040.

Torok, James; and Spitzer, Richard, to Integrated Microtransducer Electronics Corporation. Nonvolatile magnetoresistive memory with fully closed flux operation, 5,587,943, Cl. 365-158.000.

Tosaka, Akio; Fujinaga, Chikako; Kato, Toshiyuki; Sato, Kaku; and Kugumimoto, Hideo, to Kawasaki Steel Corporation. Method of manufacturing canning steel sheet with non-aging property and superior workability, 5,587,027, Cl. 148-320.000.

Toshiba Lighting & Technology Corporation. See—
Sato, Shigehiro; Matsunaga, Yoshiyuki; Ono, Tsuyoshi; and Karube, Takaaki, 5,587,097, Cl. 219-543.000.

Toshio, Sugano. See—
Masayuki, Watanabe; Toshio, Sugano; Senchiro, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima, 5,587,341, Cl. 437-206.000.

Tourner, Hervé; Hyacinthe, Roland; and Schneider, Michel, to Bracco International B.V. Process of preparing particles for NMR imaging, 5,587,199, Cl. 427-2.120.

Toutaoui, Mustapha. See—
Baren, Michael; and Toutaoui, Mustapha, 5,587,566, Cl. 187-316.000.

Toyo Kohan Co., Ltd. See—
Ohmura, Hitoshi; Koyakumaru, Yasuhiro; and Iketaka, Satoshi, 5,587,248, Cl. 428-610.000.

Toyoda Gosei Co., Ltd. See—
Kode, Norikatsu; Yamazaki, Shiro; Umezaki, Junichi; and Asami, Shinya, 5,587,593, Cl. 257-94.000.

Toyoda, Shiohei. See—
Minato, Tetsuya; Yonehara, Toshimitsu; Teranishi, Junichi; Toyoda, Shohji; Bito, Toshiaki; and Takashima, Kazushige, 5,587,694, Cl. 336-65.000.

Toyota, Eiichi. See—
Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.

Toyota Iidosha Kabushiki Kaisha. See—
Abe, Naoki; Mizuno, Kyo; Sumiyoshi, Masayuki; Murakami, Katsuya; Murayama, Kojiro; Sugita, Koichi; Kawahara, Fumio; Tomono, Mitsuru; and Ojima, Heijiro, 5,587,060, Cl. 204-554.000.

Tozyo, Takehiko. See—
Kinokke, Toshiro; Arai, Yoshitaka; Hayashi, Tetsuyoshi; Sakurai, Ken-ichi; and Tozyo, Takehiko, 5,587,505, Cl. 558-272.000.

Travers, Richard L. See—
Venooker, Ronald J.; Scavotto, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,590, Cl. 141-386.000.

Venooker, Ronald J.; Scavotto, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., 5,586,673, Cl. 215-310.000.

Treiber, Reinhard. See—
Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, 5,587,421, Cl. 524-591.000.

Treleven, Dan. See—
Stern, Donald J.; and Treleven, Dan, 5,587,102, Cl. 252-62.540.

Trepka, William J. See—
Moczygemba, George A.; Knight, Nancy R.; Trepka, William J.; and Stacy, Nathan E., 5,587,425, Cl. 525-98.000.

Tri-Way Machine Ltd. See—
Jones, Joel W.; and Wu, Ya, 5,587,931, Cl. 364-551.020.

Triestman, Douglas E. See—
Terry, Claude E.; Triestman, Douglas E.; and Price, Daniel L., 5,587,407, Cl. 523-122.000.

Tritellner, Gabriele. See—
Stadler, Maximilian; Schwab, Günter; Romeder, Peter; and Tritellner, Gabriele, 5,587,046, Cl. 156-662.100.

Trimble Navigation, Ltd. See—
Sheynblat, Len, 5,587,716, Cl. 342-357.000.

Triplet, Kelvin N. High chair tray, 5,586,800, Cl. 297-148.000.

Trout, John F. Positive sequence fluid transfer assembly, 5,586,578, Cl. 137-596.180.

Trumbo, Timothy F. Combination gift box and greeting card, 5,586,659, Cl. 206-768.000.

Trutzschler GmbH & Co. KG. See—
Leifeld, Ferdinand; and Ieder, Armin, 5,586,365, Cl. 19-105.000.

Leifeld, Ferdinand; and Temburg, Konrad, 5,586,366, Cl. 19-105.000.

Leifeld, Ferdinand, 5,586,641, Cl. 198-720.000.

TRW Inc. See—
Melver, George W.; Carlin, Mark A.; Bormann, James E.; Muckley, Ronald A.; and McCurdy, Roger A., 5,587,906, Cl. 364-424.045.

Tsai, Chun-Tie. Auxiliary assembly for improving the combustion efficiency of an engine, 5,586,541, Cl. 123-574.000.

Tsai, Philip; Hung, Chun-Yen; and Wu, Fen-Shiung, to Acer Incorporated. Anti-theft mechanism in a computer system having removable modules, 5,587,878, Cl. 361-683.000.

Tsai, Wen-Ho. See—
Huang, Tien E., 5,586,924, Cl. 446-462.000.

Tschiderer, Paul E. See—
Roy, Carl W.; and Tschiderer, Paul E., 5,586,479, Cl. 83-74.000.

Tseng, Horng-Huei, to Vanguard International Semiconductor Corporation. Polysilicon contact stud process, 5,587,338, Cl. 437-186.000.

Tsubaki, Yasuhiro. See—
Takagawa, Hiroyuki; Tsubaki, Yasuhiro; Miyari, Yoshio; Hattori, Toshio; and Hagiwara, Haruo, 5,586,456, Cl. 68-18.00R.

Tsubota, Hiroyuki; and Shimada, Reiko, to Iatron Laboratories, Inc. Reagent for assaying glucose, 5,587,296, Cl. 435-14.000.

Tsubota, Kazuaki; and Yamamoto, Takeshi, to Delta Tooling Co., Ltd.; and Delta Kogyo Co., Ltd. Connector for connecting two plate-like members, 5,586,831, Cl. 403-305.000.

Tsuchida, Yoichi. See—
Fleck, David C.; and Tsuchida, Yoichi, 5,587,559, Cl. 178-18.000.

Tsuchimoto, Tomonori; Iwata, Katsuchi; and Kurashima, Yoshihiko, to NGK Insulators, Ltd. Process for disposing of spent NaS cells, 5,587,252, Cl. 429-49.000.

Tsuchiya, Mitsuru. See—
Tamura, Yoshihiko; and Tsuchiya, Mitsuru, 5,587,352, Cl. 503-227.000.

Tsudakoma Kogyo Kabushiki Kaisha. See—
Nakada, Yasuo, 5,586,582, Cl. 139-430.000.

Suwa, Mitsuru, 5,586,583, Cl. 139-304.000.

Tsujii, Masanori. See—
Yagi, Sakai; Tsujii, Masanori; Kashiyama, Motohisa; and Endo, Takayoshi, 5,586,900, Cl. 439-310.000.

Tsujii, Tomoyuki, to Onaru Development and Construction Department of Hokkaido Development Bureau. Joint structure for coupling precast concrete pavement slabs, 5,586,834, Cl. 404-60.000.

Tsukamoto, Kazuki. See—
Ikegawa, Akihito; Arimoto, Kouichi; Tsukamoto, Kazuki; and Yamashita, Michiya, 5,587,551, Cl. 118-661.000.

Tsukamoto, Kazumasa. See—
Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masahiro; and Yamamoto, Yoshihisa, 5,586,954, Cl. 477-93.000.

Tsukamoto, Manabu. See—
Endo, Kazuhito; Ishida, Masayuki; Ishida, Yoshinobu; Tsukamoto, Manabu; and Hirai, Nobuaki, 5,587,978, Cl. 369-32.000.

Tsukude, Masaki, to Mitsubishi Denki Kabushiki Kaisha. Semiconductor memory device, 5,587,959, Cl. 365-230.000.

Tsumura, Kazunobu. See—
Maeda, Hirokazu; Furuta, Hitoshi; Takei, Chiemi; Saito, Toshiaki; Mori, Hiroyuki; and Tsumura, Kazunobu, 5,587,197, Cl. 426-658.000.

Tsunoda, Akihito. See—
Nakamatsu, Yasuhiro; Otsuka, Masao; Hatanaka, Fumio; and Tsunoda, Akihito, 5,586,757, Cl. 271-145.000.

Tsurugi, Tomio. See—
Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsurugi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58.000.

Tsuruoka, Akihiko. See—
Negi, Shigetoshi; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222.000.

Tsutsui, Yoshio. See—
Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.

Tsutsui, Haruki; Ikemoto, Yoshiaki; Machama, Mutsuhiro; Oyanagi, Toshiaki; and Matsubara, Tsugio, to Mitsui Toatsu Chemicals, Inc. Water-resistant surface coating formulations and paper coated therewith, 5,587,246, Cl. 428-511.000.

Tsuzuki, Shunichi. See—
Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhito; Fujimoto, Sachio; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.

TTI. See—
Wolfe, Jack; and Ping, Roy C. C., 5,586,358, Cl. 15-334.000.

Tucker, Stephen L. See—
Labus, Rainer H.; and Tucker, Stephen L., 5,586,695, Cl. 222-396.000.

Tuckey, Charles H., to Walbro Corporation. Regenerative fuel pump, 5,586,858, Cl. 415-55.100.

Tung, Francisca. See—
Wang, Tsong-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisca; and Massingill, Thomas J., 5,587,336, Cl. 437-183.000.

Turf Systems International, Inc. See—
Bergevin, Jerry G., 5,586,408, Cl. 47-1.010.

Turner, David W. See—
Dillehay, David R.; and Turner, David W., 5,587,552, Cl. 149-19.500.

fu Systems, Inc. See—
Graham, Martin H.; and Taylor, Matthew, 5,587,692, Cl. 333-12.000.

Tuval, Ben. See—
Borka, Alexander T.; Tuval, Ben; and Marcovici, Sorin, 5,587,611, Cl. 257-458.000.

Twardowski, Zbigniew, to Chemetics International Company Ltd. Nanohil-tration of concentrated aqueous salt solutions, 5,587,083, Cl. 210-652.000.

Tyler Refrigeration. See—
Fung, Kwok K., 5,586,444, Cl. 62-117.000.

Uchida, Kunito. See—
Ohshima, Satoshi; Yumura, Motoo; Kurita, Yasunori; Uchida, Kunito; and Ikazaki, Fumikazu, 5,587,141, Cl. 423-445.00B.

Uchida, Manabu; Izumizawa, Takenori; and Furukawa, Kenji, to Chisso Corporation. Copolymer, a process for producing the same and an electroluminescent element using the same, 5,587,444, Cl. 526-247.000.

Uchiyama, Shigeyuki, to Nikon Corporation. Focus detection device and method, 5,587,763, Cl. 396-114.000.

Uckun, Fatih M., to University of Minnesota, Regents of the. Immunoconjugates comprising tyrosine kinase inhibitors, 5,587,459, Cl. 530-391.100.

Udagawa, Tsunekazu; and Yamada, Kenji, to Ishikawa Gasket Co., Ltd. Metal laminate gasket with engaging device, 5,586,770, Cl. 277-11.000.

Udelle, Steven D. Rainwater leaf guard and cleaning device, 5,586,837, Cl. 405-119.000.

Uditsky, Daniel. See—
Nakisher, Robert G.; and Uditsky, Daniel, 5,586,883, Cl. 433-39.000.

Ue, Makoto; Sato, Tomohiro; and Takeda, Masayuki, to Mitsubishi Chemical Corporation. Electrolyte solution for electrolytic capacitor and electrolytic capacitor using the same, 5,587,871, Cl. 361-504.000.

Ueha, Hisaaki; Sunaga, Yosio; and Nagasima, Tosio, to Kureha Kagaku Kogyo Kabushiki, and Kureha Gosen Kabushiki Kaisha. Ball-like structures and contacting materials for wastewater-treatment, 5,587,239, Cl. 428-362.000.

Ueda, Shigeru, to Canon Kabushiki Kaisha. Bit data processor, 5,588,101, Cl. 395-792.000.

Ueda, Yutaka. See—
Yamashita, Hiroshi; and Ueda, Yutaka, 5,587,277, Cl. 430-458.000.

Uehara, Ryo. See—
Kawamura, Koichiro; and Uehara, Ryo, 5,587,766, Cl. 396-257.000.

Ueki, Nobuaki. See—
Otsuka, Hiroshi; Ueki, Nobuaki; Fukunaga, Hideki; Nakayama, Hideo; Seko, Yasuji; and Fuse, Mario, 5,588,016, Cl. 372-46.000.

Ueno, Shigeru. See—
Yasunaga, Kuniaki; and Ueno, Shigeru, 5,587,731, Cl. 347-86.000.

Ueno, Yoshio; Wada, Yasuo; and Honda, Munenobu, to Elephant Chain Block Company, Ltd. Manual chain block, 5,586,751, Cl. 254-352.000.

Ueno, Yoshio. See—
Wada, Yasuo; and Ueno, Yoshio, 5,586,752, Cl. 254-372.000.

Uenohara, Norihisa. See—
Mizukami, Hiroshi; Uenohara, Norihisa; and Takeuchi, Hiroshi, 5,586,633, Cl. 192-70.250.

Uenoyama, Hirofumi. See—
Kano, Kazuhiko; Takeuchi, Yukihiko; Watanabe, Takamoto; Ao, Ken-ichi; Kanosue, Masakazu; and Uenoyama, Hirofumi, 5,587,343, Cl. 437-228.000.

Uetani, Yasunori. See—
Tomioaka, Jun; Uetani, Yasunori; Nakanishi, Hiroto; Hanawa, Ryo-taro; and Ida, Ayako, 5,587,492, Cl. 549-406.000.

Ueyama, Masayuki. See—
Miyano, Masaaki; Kawasaki, Toyotoshi; Kiyama, Minoru; Miyazawa, Masayuki; Ueyama, Masayuki; and Tasaka, Yoshihiro, 5,587,846, Cl. 359-824.000.

Uggeri, Fulvio. See—
De Haen, Christoph; Uggeri, Fulvio; Gazzotti, Ornella; and Brocchetta, Marino, 5,587,487, Cl. 548-561.000.

Ujihara, Junji; and Ohira, Akira, to Konica Corporation. Manufacturing method for an electrophotographic photoreceptor, 5,587,266, Cl. 430-133.000.

Ultra-Scan Corporation. See—
Schneider, John K.; and Glenn, William E., 5,587,533, Cl. 73-614.000.

Umebayashi, Nobuhiro; Mizushima, Kunio; Miyake, Akira; and Miyata, Teruhisa, to Hitachi Maxell, Ltd. Magnetic disc cartridge including a magnetic disc having a cleaning sheet composed of a non-theroplastic fiber, 5,587,860, Cl. 360-133.000.

Umezaki, Junichi. See—
Kuide, Norikatsu; Yamazaki, Shiro; Umezaki, Junichi; and Asami, Shinya, 5,587,593, Cl. 257-94.000.

Ünal, Serhat. See—
Alborn, William E., Jr.; Hoskins, JoAnn; Skatrud, Paul L.; and Ünal, Serhat, 5,587,307, Cl. 435-240.100.

Union Carbide Chemicals & Plastics Technology Corporation. See—
McCullough, James D., Jr.; and Bradford, John E., 5,587,434, Cl. 525-333.800.

Unipath Limited. See—
Carr, Anthony H., 5,586,823, Cl. 366-274.000.

Unisia Jecs Corporation. See—
Tomisawa, Naoki; and Watanabe, Satoru, 5,586,537, Cl. 123-435.000.

United Dominion Industries, Inc. See—
Alexander, James C., 5,586,356, Cl. 14-71.100.

Metz, Donald; and Alexander, James C., 5,586,355, Cl. 14-69.500.

United Microelectronics Corporation. See—
Yang, Ming T., 5,587,600, Cl. 257-391.000.

United States Drug Testing Laboratories, Inc. See—
Lewis, Douglas E.; and Moore, Christine M., 5,587,323, Cl. 436-178.000.

United States of America, The. See—
Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H., 5,587,384, Cl. 514-309.000.

United States of America Agriculture. See—
Briggs, Robert E.; and Tatum, Fred M., 5,587,305, Cl. 435-172.100.

Vander Meer, Robert K.; Banks, William A.; and Lofgren, Clifford S., 5,587,401, Cl. 514-675.000.

Army. See—

Rose, Douglas N., 5,587,532, Cl. 73-579.000.

Warner, Joseph G.; and Bensch, Christopher J., 5,586,785, Cl. 280-762.000.

Commerce. See—
McCloskey, Joseph D.; Dube, William P.; Fortunko, Christopher M.; Schramm, Raymond E.; Renken, Martin C.; Teller, Cecil M., II; and Light, Glenn M., 5,587,534, Cl. 73-623.000.

Energy. See—
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cal, Yigang, 5,586,504, Cl. 104-282.000.

Knapp, Philip A., 5,586,745, Cl. 251-121.000.

Health and Human Services. See—
Berger, Edward A.; Moss, Bernard; Fuerst, Thomas R.; Pastan, Ira; Fitzgerald, David; Mizukami, Tamio; and Chaudhary, Vijay K., 5,587,455, Cl. 530-324.000.

Carter, Barrie J.; Flotte, Terence; Alfione, Sandra; and Solow, Rikki, 5,587,308, Cl. 435-240.200.

Rubin, Jeffrey; Hayek, Alberto; Beattie, Gillian M.; and Otonkoski, Timo P. J., 5,587,309, Cl. 435-240.200.

National Aeronautics and Space Administration. See—
Sandusky, Donald A.; and Marchello, Joseph M., 5,587,041, Cl. 156-441.000.

Navy. See—
Alexander, Edward M.; and Spezio, Anthony E., 5,587,829, Cl. 359-287.000.

Barkyoub, John; Kahacoff, Lawrence T.; and Land, David J., 5,586,824, Cl. 374-44.000.

Marchywka, Michael J.; and Pehrsson, Pehr E., 5,587,210, Cl. 427-523.000.

Reedy, Ronald E.; Garcia, Graham A.; and Lagnado, Isaac, 5,587,597, Cl. 257-351.000.

Schofield, Ronald D., 5,587,972, Cl. 368-118.000.

Stenger-Smith, John D.; Norris, William P.; and Chafin, Andrew P., 5,587,488, Cl. 549-59.000.

U.S. Philips Corporation. See—
Bergen, Franciscus H. M.; Rote, Jan J.; Nijssen, Stephanus J. J.; and De With, Peter H. N., 5,587,802, Cl. 386-26.000.

Blüthgen, Björn, 5,587,979, Cl. 369-32.000.

Colditz, Johannes K. E., 5,587,621, Cl. 313-366.000.

Dijkmans, Eise C., 5,587,678, Cl. 327-108.000.

Groten, Maurice, 5,588,017, Cl. 372-49.000.

Kablau, Johannes G. E.; Mimmagh, Winslow M.; and Hoeven, Petrus C. J., 5,587,980, Cl. 369-54.000.

Kruit, Pieter, 5,587,586, Cl. 250-423.000.

Le Berre, Jacques, 5,588,058, Cl. 380-20.000.

Lorrain, Henri L. P., 5,586,908, Cl. 439-511.000.

Van Heels-Bergen, Teunis R.; and Fuderer, Miha, 5,587,656, Cl. 324-307.000.

U.S. Robotics. See—
Parizhsky, Vladimir, 5,588,028, Cl. 375-341.000.

United States Surgical Corporation. See—
Hinchliffe, Peter W. J., 5,586,986, Cl. 606-147.000.

Plyley, Alan K.; Vidal, Claude A.; Minck, John L., Jr.; and Solyntjes, Alan J., 5,586,711, Cl. 227-176.100.

United Technologies Automotive Systems Inc. See—
Falcon, Michael D.; Perry, William; and Hess, Arthur, 5,587,699, Cl. 340-475.000.

United Technologies Corporation. See—
Aho, Wilho V., Jr.; Jones, Stephen R.; Chetta, Gregory E.; and Strout, Terry H., 5,587,068, Cl. 210-188.000.

Nardone, Vincent C.; Thompson, Mark S.; and Meyer, Thomas G., 5,586,471, Cl. 74-572.000.

Nolcheff, Nick A., 5,586,859, Cl. 415-58.500.

Thonebe, Douglas A.; and Coons, Russell L., 5,586,431, Cl. 60-226.100.

Univ. of GA Research Foundation. See—
Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, 5,587,362, Cl. 514-46.000.

Université Laval. See—
Champagne, Yves; Paré, Claude; and Bélanger, Pierre-André, 5,587,786, Cl. 356-121.000.

University of California, The Regents of the. See—
Jacobson, Bruce S.; and Schnitzer, Jan E., 5,587,297, Cl. 435-29.000.

Klonsky, Daniel; Holzer, Helmut; and Destruelle, Monika, 5,587,290, Cl. 435-6.000.

University of Houston. See—
Yang, Rui Q., 5,588,015, Cl. 372-45.000.

University of Kansas. See—
Smith, Donald D.; Cohick, Christopher B.; and Lindsley, Herbert B., 5,587,321, Cl. 435-305.300.

University of Maryland. See—
Weiner, Ronald M.; and Manyak, David M., 5,587,313, Cl. 435-252.100.

University of Minnesota, Regents of the. See—
Hoye, Thomas R.; and Tan, Lushi, 5,587,491, Cl. 549-320.000.

Purnam, Matthew D.; and Gesensway, David, 5,586,985, Cl. 606-69.000.

Uckun, Fatih M., 5,587,459, Cl. 530-391.100.

University of Nebraska, Board of Regents of the. See—
Curicuta, Victor; Alexander, Dennis R.; Deangelis, Robert J.; and Robertson, Brian W., 5,586,714, Cl. 228-122.100.

University of Notre Dame. See—

- Helquist, Paul; and Cocito, Carlo, 5,587,475, Cl. 540-456.000.
University of Oklahoma, The Board of Regents of the: See—
Allen, Loyd V., Jr.; and Wang, Bingnan, 5,587,180, Cl. 424-499.000.
University of Oregon, State of Oregon Acting by and through the State Board of Higher Education on Behalf of the: See—
Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P., 5,587,273, Cl. 430-269.000.
University of Pennsylvania, The Trustees of the: See—
Wilding, Peter; and Kricka, Larry J., 5,587,128, Cl. 422-50.000.
University of Texas System: See—
Cloyd, Miles W.; and Ramsey, Keith M., 5,587,285, Cl. 435-5.000.
University of Toledo, The: See—
Morgan, Alan R.; and Selman, Steven H., 5,587,394, Cl. 514-185.000.
University of Utah Research Foundation: See—
Daynes, Raymond A.; and Araneo, Barbara A., 5,587,369, Cl. 514-178.000.
University of Warwick: See—
Bowen, David K.; and Thomas, Charles R., 5,588,034, Cl. 378-73.000.
University Research Corporation: See—
Allen, Patrick; and Gold, Larry, 5,587,468, Cl. 536-22.100.
Unno, Kenichi: See—
Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
Unno, Tetsuo; Shoda, Yoshio; and Momono, Tatsunobu, to NSK Ltd. Ball bearing with controlled dynamic imbalance, 5,586,827, Cl. 384-450.000.
Uno, Koji: See—
Taniguchi, Kazuki; Ikegawa, Akihito; Uno, Koji; and Saito, Hitoshi, 5,587,775, Cl. 355-219.000.
Urahe, Shigeharu: See—
Nakatsugawa, Haruyasu; Yoneyama, Masakazu; and Urahe, Shigeharu, 5,587,282, Cl. 430-637.000.
Urano, Youji: See—
Nakatani, Takuya; Abe, Mitsutaka; Dono, Shigeru; and Urano, Youji, 5,586,387, Cl. 29-703.000.
Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsunagi, Tomio; and Ichino, Tomio, to Eisai Co., Ltd.; and Eisai Chemical Co., Ltd. Sulfonyloxy-biphenylcarboxylic ester derivatives which are intermediates, 5,587,504, Cl. 558-58.000.
Ursini, Antonella: See—
Perboni, Alcide; Rossi, Tino; Gaviraghi, Giovanni; Tarzia, Giorgio; and Ursini, Antonella, 5,587,374, Cl. 514-210.000.
Usinor Sacilor Societe: See—
Destannes, Philippe, 5,588,018, Cl. 373-72.000.
Utagawa, Ken: See—
Kusaka, Yosuke; and Utagawa, Ken, 5,587,579, Cl. 250-201.800.
Kusaka, Yosuke; Muramatsu, Masaru; Utagawa, Ken; and Yamano, Shozo, 5,587,761, Cl. 396-95.000.
Utisch, Gerhard: See—
Utisch, Joachim; Utisch, Gerhard; and Utisch, Manfred, 5,587,036, Cl. 156-219.000.
Utisch, Joachim; Utisch, Gerhard; and Utisch, Manfred, to Utisch, Joachim. Process for the production of blanks for motor vehicle license plates, 5,587,036, Cl. 156-219.000.
Utisch, Manfred: See—
Utisch, Joachim; Utisch, Gerhard; and Utisch, Manfred, 5,587,036, Cl. 156-219.000.
Utsugi, Makoto: See—
Yamamoto, Takashi; Sakaguchi, Yasunobu; and Utsugi, Makoto, 5,587,768, Cl. 355-41.000.
Utsumi, Minoru: See—
Iijima, Masayuki; Dantani, Kyoji; Ohata, Hiroyuki; Matsuo, Makoto; Utsumi, Minoru; and Take, Seiji, 5,587,264, Cl. 430-57.000.
Uytendaele, Carlo A.: See—
Horsten, Bartholomeus C.; Uytendaele, Carlo A.; Jansen, Guy D. A.; and Schuerwegen, Ronald, 5,587,350, Cl. 503-201.000.
Uytendaele, Catherine: See—
Van Snick, Jacques; Uytendaele, Catherine; and Simpson, Richard J., 5,587,302, Cl. 435-69.500.
V.T.S. Trenching Systems Ltd.: See—
Staroselsky, Semeon, 5,586,399, Cl. 37-351.000.
Vacuum Metallurgical Co., Ltd.: See—
Watanabe, Kazuhiro; Oshina, Michihiro; Setoguchi, Kazuhiro; and Oda, Masaaki, 5,587,111, Cl. 252-514.000.
Vagin, Vladimir P., to Nefteodacha, Ltd. Method and apparatus for shock wave stimulation of an oil-bearing formation, 5,586,602, Cl. 166-249.000.
Vaidya, Jayant G.: See—
Bansal, Madan L.; and Vaidya, Jayant G., 5,587,647, Cl. 322-45.000.
Vale, Wylie W., Jr.: See—
Behan, Dominic P.; Vale, Wylie W., Jr.; Fischer, Wolfgang H.; and Lowry, Philip J., 5,587,462, Cl. 530-350.000.
Valentino, Karen L.: See—
Justice, Alan; Singh, Tejinder; Gohil, Kishor C.; Valentino, Karen L.; and Miljanich, George P., 5,587,454, Cl. 530-324.000.
Valeo: See—
Thirion de Briel, Jacques, 5,586,634, Cl. 192-70.270.
Valeo Engine Cooling, Inc.: See—
Cribari, John C., 5,586,600, Cl. 165-173.000.
Valery, Jeff: See—

- Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364-510.000.
Valve, Serge. Pneumatic engine valve spring assembly, 5,586,529, Cl. 123-90.650.
Valmet Corporation: See—
Autio, Jukka; and Kujala, Timo, 5,587,052, Cl. 162-273.000.
Kertula, Reima; and Yli-Kauppi, Jouko, 5,586,397, Cl. 34-114.000.
Van den Bergh Foods Co., Division of Conopco, Inc.: See—
Sassen, Cornelis L., 5,587,195, Cl. 426-607.000.
van Alstine, Daniel W.; and Eggebrecht, Charles M., to General Railway Signal Corporation. Switch machine cam bar, 5,586,737, Cl. 246-448.000.
van Borssum Waalkes, Marjan: See—
Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.
Van Daele, Georges H. P.: See—
Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdonck, Marc G. C.; and Janssen, Paul A. J., 5,587,387, Cl. 514-312.000.
VanDenBerg, Eugene W., II: See—
Phillips, Lawrence R.; and VanDenBerg, Eugene W., II, 5,586,522, Cl. 123-41.82R.
Van Den Berg, Hendrikus: See—
König, Udo; Van Den Berg, Hendrikus; and Tabersky, Ralf, 5,587,233, Cl. 428-325.000.
Van den Bogaert, Jan: See—
Janssens, Wilhelms; Van den Bogaert, Jan; Vanmaele, Luc; and Defieuw, Geert, 5,587,270, Cl. 430-203.000.
Vandergriff, Douglas S.: See—
Enore, Steven P.; Lane, Joseph J.; and Vandergriff, Douglas S., 5,586,690, Cl. 222-105.000.
Vander Meer, Robert K.; Banks, William A.; and Lofgren, Clifford S., to United States of America, Agriculture. Repellents for ants, 5,587,401, Cl. 514-675.000.
van der Meer, Wiert: See—
van Holst, Gerrit J.; Kreuger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, 5,587,312, Cl. 435-240.460.
Vander Plas, Hubert A.: See—
Schwiebert, Matthew K.; Campbell, Donald T.; Heydinger, Matthew; Kraft, Robert E.; and Vander Plas, Hubert A., 5,586,715, Cl. 228-248.100.
Vande Wetering, Gerry: See—
Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., 5,587,183, Cl. 425-4.00R.
Van Geel, Edward. Non-contact reader, 5,587,574, Cl. 235-380.000.
Vanguard International Semiconductor Corporation: See—
Tseng, Horng-Huei, 5,587,338, Cl. 437-186.000.
Van Heels-Bergen, Teunis R.; and Fuderer, Miha, to U.S. Philips Corporation. Magnetic resonance imaging method and apparatus, 5,587,656, Cl. 324-307.000.
van Holst, Gerrit J.; Kreuger, Marc; van der Meer, Wiert; Postma, Erik; and Abbestee, Rob, to Sandoz Ltd. Somatic embryogenesis method, 5,587,312, Cl. 435-240.460.
Van Hunsel, Johan: See—
Heugebaert, Franciscus; and Van Hunsel, Johan, 5,587,271, Cl. 430-204.000.
Vanmaele, Luc: See—
Defieuw, Geert; Janssens, Wilhelms; and Vanmaele, Luc, 5,587,268, Cl. 430-200.000.
Janssens, Wilhelms; Van den Bogaert, Jan; Vanmaele, Luc; and Defieuw, Geert, 5,587,270, Cl. 430-203.000.
Van Meel, Jacques: See—
Narr, Berthold; Haevel, Norbert; Van Meel, Jacques; Wiennen, Wolfgang; Entzeroth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381.000.
Van Neste, Richard: See—
Belleville, Claude; Van Neste, Richard; Caron, Serge; Houle, Alain C.; and Thibault, Pierre, 5,587,791, Cl. 356-345.000.
Vanonou, Ilana. Cosmetic preparations, 5,587,168, Cl. 424-401.000.
van Ravesteijn, Robertus L. A.: See—
Beerends, John G.; Muller, Frank; and van Ravesteijn, Robertus L. A., 5,588,089, Cl. 395-2.140.
Van Snick, Jacques; Uytendaele, Catherine; and Simpson, Richard J., to Ludwig Institute For Cancer Research. T cell growth factor, 5,587,302, Cl. 435-69.500.
Varian Associates, Inc.: See—
Christean, Paul G.; and Runnoe, Dennis H., 5,588,035, Cl. 378-132.000.
Salimian, Siamak; Delfino, Michelangelo; and Chung, Bu-Chin, 5,587,039, Cl. 156-345.000.
Vaughan, Gerald L.; and Weaver, Samuel C. Mineral fibers and whiskers exhibiting reduced mammalian cell toxicity, and method for their preparation, 5,587,241, Cl. 428-375.000.
Vavreck, Kenneth E.: See—
Hau, Clarence J.-Y.; Stec, Kevin J.; and Vavreck, Kenneth E., 5,587,742, Cl. 348-441.000.
Veggian, Eric D.: See—
Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., 5,586,782, Cl. 280-730.200.
Vehar, Gordon A.: See—
Goeddel, David V.; Kohr, William J.; Pennica, Diane; and Vehar, Gordon A., 5,587,159, Cl. 424-94.640.

- Velardo, Patrick M., Jr.; and Wynn, Woodson D., to AT&T. Method and apparatus for reducing residual far-end echo in voice communication networks, 5,587,998, Cl. 370-289.000.
Vend-It Corporation: See—
Nitschke, John S.; and Kuhary, Daniel B., 5,586,486, Cl. 99-330.000.
Venier, Philippe; Debergh, Patrick; and Arreguit, Xavier, to CSEM Centre Suisse d'Electronique et de Microtechnique SA. Optoelectronic sensor for measuring the intensity and the direction of incidence of a light beam, 5,587,580, Cl. 250-206.100.
Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., to Ciba Corning Diagnostics Corp. Coupler for fluid delivery system, 5,586,590, Cl. 141-386.000.
Venooker, Ronald J.; Scavito, John A.; Karkantis, Peter N.; Healey, David T.; and Travers, Richard L., to Ciba Corning Diagnostics Corp. Cap assembly for fluid delivery system, 5,586,673, Cl. 215-310.000.
Verbeke, Hans G. G.: See—
Leenslag, Jan W.; and Verbeke, Hans G. G., 5,587,414, Cl. 524-394.000.
Verbrugge, Calvin J.: See—
Sandvick, Paul E.; and Verbrugge, Calvin J., 5,587,202, Cl. 427-155.000.
Verdonck, Marc G. C.: See—
Janssen, Marcel A. C.; Van Daele, Georges H. P.; Bosmans, Jean-Paul R. M. A.; Verdonck, Marc G. C.; and Janssen, Paul A. J., 5,587,387, Cl. 514-312.000.
Vesa, Juha. Method and apparatus for the production of a gas-pervious part in a gas-pervious mould and a product made by this method, 5,587,121, Cl. 264-126.000.
Victory in Jesus Ministries, Inc.: See—
Lund, David R., 5,586,474, Cl. 81-57.300.
Vidal, Claude A.: See—
Plyley, Alan K.; Vidal, Claude A.; Minck, John L., Jr.; and Solyntjes, Alan J., 5,586,711, Cl. 227-176.100.
Viegas, Tacey X.; Reeve, Lorraine E.; and Henry, Raymond L., to MDV Technologies, Inc. Medical uses of in situ formed gels, 5,587,175, Cl. 424-427.000.
Vieil, Eric; Bidan, Gérard; Gadelle, Andrée; and Mendes-Viegas, Maria-Fátima, to Commissariat A L'Energie Atomique. Conductive polymer doped by a sulphonated cyclodextrin salt and device for obtaining and/or supplying an active substance incorporating said polymer, 5,587,466, Cl. 536-4.100.
Vieslet, Bernard P.: See—
Vieslet, Jean-Paul B.; Vieslet, Bernard P.; and Poswick, Pierre G., 5,587,120, Cl. 264-118.000.
Vieslet, Jean-Paul B.; Vieslet, Bernard P.; and Poswick, Pierre G. Method for shaping a polymer mixture into a block with a stable shape and size, 5,587,120, Cl. 264-118.000.
Vikimatic Sales, Inc.: See—
Allen, Jerry L., 5,587,115, Cl. 264-1.240.
Vild, Chris T.: See—
Gilbert, Ronald E.; Mordue, George S.; and Vild, Chris T., 5,586,863, Cl. 415-200.000.
Villar, Hugo O.: See—
Kauvar, Lawrence M.; and Villar, Hugo O., 5,587,293, Cl. 435-7.210.
Vincent, David M. Pneumatic refrigeration system and method, 5,586,440, Cl. 62-87.000.
Vincent, Ronald; Sprague, Marshall; and Hare, Duncan. Method for correlating logical device names with a hub port in a local area network, 5,588,119, Cl. 395-200.150.
Vineski, James: See—
Chiu, Francis; Goss, William; Hayes, David; Randolph, Gary; Sak, Cheryl; Valery, Jeff; and Vineski, James, 5,587,926, Cl. 364-510.000.
Virginia Tech Intellectual Property Inc.: See—
Yoon, Roe-Hoan; and Luttrell, Gerald H., 5,587,085, Cl. 210-711.000.
Visalli, Robert G.: See—
Conley, Richard W.; Visalli, Robert G.; and Daniels, James R., 5,586,749, Cl. 251-315.050.
Visser, Susan A.; Hewitt, Charles E.; Binga, Tonya D.; Ferrar, Wayne T.; Fichtner, Michael W.; and Fitzgerald, John J., to Eastman Kodak Company. Fusing member having zinc oxide-filled, addition cured layer, 5,587,245, Cl. 428-447.000.
Vittorio, David A., to Cummins Engine Company, Inc. Engine retarder cycle, 5,586,531, Cl. 123-320.000.
Vivo Software, Inc.: See—
Jones, Oliver; Deshon, Mary; Ericsson, Staffan; and Flach, James, 5,587,928, Cl. 364-514.00A.
VLSI Technology: See—
Wang, Tsing-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisca; and Massingill, Thomas J., 5,587,336, Cl. 437-183.000.
VLSI Technology, Inc.: See—
Chang, Kuang-Yeh; Nariani, Subhash R.; and Boardman, William J., 5,587,332, Cl. 437-43.000.
Hicok, Gary D.; Hildebrandt, Eric A.; and Zhu, Michael H., 5,588,128, Cl. 395-414.000.
Jiang, Chun, 5,587,665, Cl. 326-16.000.
Voelker, Scott C., to Monsanto Company. Refillable closed container system, 5,586,589, Cl. 141-349.000.
Vogel, Gerald A.; and Tholen, Joseph H., to J. Vogel Premium Water. Water purification and dispensing system, 5,587,089, Cl. 210-164.000.
Vogel, Martin A.: See—
Kampe, Klaus-Dieter; ter Meer, Hans-Ulrich; Egger, Norbert K.; and Vogel, Martin A., 5,587,476, Cl. 540-472.000.

- Vogl, Thomas P.: See—
Alkon, Daniel L.; Vogl, Thomas P.; Blackwell, Kim T.; and Barbour, Garth S., 5,588,091, Cl. 395-24.000.
Vogley, Wilbur C.; Balistrieri, Anthony M.; Gutttag, Karl M.; Krueger, Steven D.; Le, Duy-Loan T.; Neal, Joseph H.; Poteet, Kenneth A.; Hartigan, Joseph P.; and Norwood, Roger D., to Texas Instruments Incorporated. Random access memory arranged for operating synchronously with a microprocessor and a system including a data processor, a synchronous DRAM, a peripheral device, and a system clock, 5,587,954, Cl. 365-221.000.
Voigt, Jürgen, to Herman Berstorff Maschinenbau GmbH. Apparatus for pelletizing plastics, 5,587,186, Cl. 425-310.000.
Voldman, Steven H.; Wallash, Albert J.; and Wilcox, Reginald B., Jr., to International Business Machines Corporation. Silicon chip with an integrated magnetoresistive head mounted on a slider, 5,587,857, Cl. 360-103.000.
Vollhardt, Frohmuth; and Heering, Jürgen R., to Man Gutehoffnungshütte Aktiengesellschaft. Filter for separating pollutants from flue gases, 5,586,995, Cl. 55-227.000.
Vom Felde, Andreas: See—
Mahnkopf, Reinhard; and Vom Felde, Andreas, 5,587,599, Cl. 257-370.000.
Vonderhaar, James D. Golf putting trainer, 5,586,945, Cl. 473-258.000.
Vondrak, Thomas F.: See—
Meyer, George W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F., 5,588,041, Cl. 379-59.000.
von Gentzkow, Wolfgang; Huber, Jürgen; Kapitzka, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, to Siemens Aktiengesellschaft; and Hoechst Aktiengesellschaft. Epoxy resin mixtures containing phosphonic/phosphinic acid anhydride adducts, 5,587,243, Cl. 428-413.000.
Voodoo Scientific, Inc.: See—
Sullivan, M. David, 5,588,057, Cl. 380-15.000.
Voss, Darrell W.: See—
Klein, Gary G.; Voss, Darrell W.; and Pauls, Lonney, 5,586,780, Cl. 280-275.000.
Vossiek, Martin: See—
Kroemer, Nils; Vossiek, Martin; Eccardt, Peter-Christian; and Magori, Valentin, 5,587,969, Cl. 367-99.000.
Vossmann, Gregor; and Angermann, Dirk, to Keiper Recaro GmbH & Co. Articulated fitting for seats with adjustable backrest, in particular motor vehicle seats, 5,586,833, Cl. 403-359.000.
Voysys Corporation: See—
Lofgren, Dan M.; and Dietrich, William A., 5,588,044, Cl. 379-67.000.
VPL Research, Inc.: See—
Lanier, Jaron Z.; Lasko-Harvill, Ann; Blanchard, Chuck L.; and Sparks, Joe L., 5,588,104, Cl. 395-326.000.
Lanier, Jaron Z.; Grimaud, Jean-Jacques G.; Harvill, Young L.; Lasko-Harvill, Ann; Blanchard, Chuck L.; Oberman, Mark L.; and Teitel, Michael A., 5,588,139, Cl. 395-500.000.
Levirt, David A.; Degroot, Marc; and Lanier, Jaron Z., 5,587,936, Cl. 364-378.000.
W. R. Grace & Co.-Conn.: See—
Greaves, Brian; Poole, Stephen C.; Hwa, Chih M.; and Fan, Joseph C., 5,587,109, Cl. 252-392.000.
Wachs, Timothy: See—
Henion, Jack D.; Sheppard, Robin L.; and Wachs, Timothy, 5,587,582, Cl. 250-288.000.
Wacker Corporation: See—
Orzal, Gregory J., 5,586,630, Cl. 192-4.00R.
Wacker Siltronic Gesellschaft Für Halbleitermaterialien Aktiengesellschaft: See—
Stadler, Maximilian; Schwab, Günter; Romeder, Peter; and Trifellner, Gabriele, 5,587,046, Cl. 156-662.100.
Wacom Co., Ltd.: See—
Fleck, David C.; and Tsuchida, Yoichi, 5,587,559, Cl. 178-18.000.
Wada, Isao: See—
Kawahara, Ichiro; Wada, Isao; and Sasaoka, Michio, 5,587,464, Cl. 534-558.000.
Wada, Satoshi: See—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Awai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.
Wada, Yasuo; and Ueno, Yoshio, to Elephant Chain Block Company Limited. Load chain retainer for a chain block, 5,586,752, Cl. 254-372.000.
Wada, Yasuo: See—
Ueno, Yoshio; Wada, Yasuo; and Honda, Munenobu, 5,586,751, Cl. 254-352.000.
Waddle, Roy J.: See—
Radford, Neal T.; and Waddle, Roy J., 5,587,527, Cl. 73-439.000.
Wadlington, James B., to Delta and Pine Land Company. Method for recovery of cotton seed from lint, 5,586,412, Cl. 47-58.000.
Wakabayashi, Tsutomu: See—
Kazami, Kazuyuki; and Wakabayashi, Tsutomu, 5,587,753, Cl. 396-397.000.
Wakamoto, Akiko; Takahashi, Osamu; Furuhashi, Keizo; and Miura, Akira, to Nippon Mining Company, Ltd. Production process of L-amino acids with bacteria, 5,587,303, Cl. 435-116.000.
Wako Plastics Industries Co., Ltd.: See—
Niimi, Hideki, 5,587,189, Cl. 425-577.000.
Walbro Corporation: See—
Tuckey, Charles H., 5,586,858, Cl. 415-55.100.

- Waldmeyer, Jürg: *See*—
Jaacklin, André; Ramezani, Ezatollah; Roggwiler, Peter; Ruegg, Andreas; Stockmeier, Thomas; Streit, Peter; and Waldmeyer, Jürg, 5,587,594, Cl. 257-138.000.
- Wales, Matthew A.: *See*—
Ashcraft, Walter M.; and Wales, Matthew A., 5,586,546, Cl. 126-42.000.
- Wall, Ronald; Prasad, Raghubir; and Sela, Elaine, to Minister of Natural Resources, Canadian Forest Service, Biological control for weed trees, 5,587,158, Cl. 424-93.500.
- Wallace Computer Services, Inc.: *See*—
Hoffmann, Donald J., 5,587,222, Cl. 428-192.000.
- Wallash, Albert J.: *See*—
Voldman, Steven H.; Wallash, Albert J.; and Wilcox, Reginald B., Jr., 5,587,857, Cl. 360-103.000.
- Walling, Dennis R.: *See*—
Smith, James C.; and Walling, Dennis R., 5,586,744, Cl. 251-61.500.
- Wallis, John: *See*—
Sawyer, Colin; Wallis, John; and Bartingale, Peter, 5,586,933, Cl. 454-299.000.
- Walls, Robert R., to Envision Medical Corporation, Sterilizable CCD video camera, 5,587,736, Cl. 348-65.000.
- Walsh, Brian E.: *See*—
Hippely, Keith A.; Wood, Larry R.; Walsh, Brian E.; and Choy, Terence A., 5,586,923, Cl. 446-14.000.
- Walsh, David S.: *See*—
Reddin, Timothy G.; Walsh, David S.; and Round, Jeremy S., 5,588,121, Cl. 395-200.150.
- Walsh, Thomas M. Sealed marine post, 5,586,838, Cl. 405-216.000.
- Walter, Hans-Dieter: *See*—
Dickinson, Ian J.; Eichberger, Horst; Messaros, David W.; and Walter, Hans-Dieter, 5,588,109, Cl. 395-326.000.
- Walter, Jutta: *See*—
Ehlers, Jens; and Walter, Jutta, 5,587,440, Cl. 526-153.000.
- Walther, Michael: *See*—
Schneider, Thomas; Grieser-Schmitt, Stefan; and Walther, Michael, 5,587,661, Cl. 324-556.000.
- Walton, Ballard E.: *See*—
Dolgas, Patrick A.; Walton, Ballard E.; and Staton, Larry E., 5,586,383, Cl. 29-596.000.
- Wanek, Ronald G.; Datta, James C.; Konkil, Brian; and Herold, Duane, to Ashley Furniture Industries, Inc. Pivoting and variable height table, 5,586,830, Cl. 403-59.000.
- Wang, Bingnan: *See*—
Allen, Lloyd V., Jr.; and Wang, Bingnan, 5,587,180, Cl. 424-499.000.
- Wang, Chen-Jong: *See*—
Su, Chung-Hui; Liang, Mong-Song; Wu, Shou-Gwo; and Wang, Chen-Jong, 5,587,696, Cl. 338-314.000.
- Wang, Deborah C., to LSI Logic Corporation, Method for estimating routability and congestion in a cell placement for integrated circuit chip, 5,587,923, Cl. 364-490.000.
- Wang, Joseph, Power supply chassis for personal computers, 5,587,881, Cl. 361-695.000.
- Wang Laboratories, Inc.: *See*—
MacDonald, James B., 5,587,673, Cl. 326-93.000.
- Wang, Shin-Ywan, to Canon Kabushiki Kaisha, Method and apparatus for selecting blocks of image data from image data having both horizontally and vertically-oriented blocks, 5,588,072, Cl. 382-176.000.
- Wang, Tsing-Chow; Luo, Serena M.; Macaraeg, Marlita F.; Tung, Francisco; and Massingill, Thomas J., to VLSI Technology, Bump formation on yielded semiconductor dies, 5,587,336, Cl. 437-183.000.
- Wang, Yuan L., Structure of a telescopic handle for wheeled luggage, 5,586,628, Cl. 190-115.000.
- Wang, Yun: *See*—
Lin, Eileen T.; and Wang, Yun, 5,588,150, Cl. 395-601.000.
- Wang, Zian: *See*—
He, Jianliang; Wang, Zian; Rote, Donald M.; Coffey, Howard T.; Hull, John R.; Mulcahy, Thomas M.; and Cal, Yigang, 5,586,504, Cl. 104-282.000.
- Wanie, Lee J., to Deere & Company, Neutral start mechanism for a hydrostatic transmission, 5,586,955, Cl. 477-99.000.
- Ward, Maurice, Illuminated fishing rod, 5,586,403, Cl. 43-17.500.
- Ward, Thomas F.; and Smith, Grant W., to Rayovac Corporation, Security blister package, 5,586,657, Cl. 206-705.000.
- Wardle, Robert B.: *See*—
Braithwaite, Paul C.; Lund, Gary K.; and Wardle, Robert B., 5,587,553, Cl. 149-19.600.
- Warkentin, Douglas D.: *See*—
Rowley, Michael V.; Warkentin, Douglas D.; and Proshco, Beverly M., 5,587,079, Cl. 210-603.000.
- Warkentine, James P. Semi-automated harvester, 5,586,426, Cl. 56-327.100.
- Warman International Limited: *See*—
Wood, Warwick N., 5,586,966, Cl. 494-37.000.
- Warmerdam, Petrus, to Zellweger Luwa AG, Measuring transformer for solid-state electricity meters, 5,587,695, Cl. 336-84.000.
- Warner, Joseph G.; and Bensch, Christopher J., to United States of America, Army, Vehicle wire cutter, 5,586,785, Cl. 280-762.000.
- Warner, Kenneth R.: *See*—
Glaze, Bradley S.; and Warner, Kenneth R., 5,586,731, Cl. 241-56.000.
- Warren, Paul C.: *See*—
Gozdz, Antoni S.; Schmutz, Caroline N.; and Warren, Paul C., 5,587,253, Cl. 429-192.000.
- Warren, Raphael, and Akadir, Adebola T., to Procter & Gamble Company, The, Methods of using hesperetin for sebum control and treatment of acne, 5,587,176, Cl. 424-443.000.
- Washington University: *See*—
Indeck, Ronald S.; and Muller, Marcel W., 5,587,654, Cl. 324-225.000.
- Watabe, Masahiro; Yanai, Noriyuki; Niwano, Kentaro; and Yamamoto, Akihiro, to Canon Kabushiki Kaisha, Member comprising a polyurethane rubber composition containing an amino catalyst for regulating quantity of developer and developing unit using the same, 5,587,776, Cl. 355-245.000.
- Watanabe, Atsushi; Nihei, Ryo; and Terada, Akihiro, to Fanuc Ltd, Robot control apparatus for monitoring load on robot, 5,587,635, Cl. 318-434.000.
- Watanabe, Kazuhiro; Oshima, Michihiro; Setoguchi, Kazuhiro; and Oda, Masaaki, to Vacuum Metallurgical Co., Ltd, Metal paste, process for producing same and method of making a metallic thin film using the metal paste, 5,587,111, Cl. 252-514.000.
- Watanabe, Keiji: *See*—
Saito, Masato; Suzuki, Ryo; Fukuyama, Keiji; Ohira, Takuya; Watanabe, Keiji; Kobayashi, Minoru; Hoshino, Susumu; and Hatanaka, Yoshinori, 5,587,627, Cl. 315-169.100.
- Watanabe, Kinio, to Fujitsu Limited, Memory control method and apparatus therefor, 5,588,136, Cl. 395-187.000.
- Watanabe, Makoto, to Jidosha Kiki Co., Ltd, Apparatus for preventing disengagement of seal member in a booster, 5,586,481, Cl. 91-376.000.
- Watanabe, Masahiko: *See*—
Murata, Yasumoto; Ikeuchi, Michio; Yoshikawa, Shuichi; and Watanabe, Masahiko, 5,588,052, Cl. 379-283.000.
- Watanabe, Masami: *See*—
Kitamura, Toru; Katoh, Akira; Kumagai, Katsuhiko; Fujimoto, Sachito; Kitagawa, Hiroshi; Tsuzuki, Shunichi; Takahashi, Jun; and Watanabe, Masami, 5,586,544, Cl. 123-684.000.
- Watanabe, Masayuki, to NEC Corporation, Semiconductor device having a conductive layer with an aperture, 5,587,610, Cl. 257-758.000.
- Watanabe, Muneaki: *See*—
Nakayama, Ryoji; Takeshita, Takuo; and Watanabe, Muneaki, 5,587,024, Cl. 148-101.000.
- Watanabe, Satoru: *See*—
Tomisawa, Naoki; and Watanabe, Satoru, 5,586,537, Cl. 123-435.000.
- Watanabe, Takahiro: *See*—
Furuta, Toshiyuki; Motomura, Shuji; Watanabe, Takahiro; and Stork, David G., 5,588,090, Cl. 395-23.000.
- Watanabe, Takamoto: *See*—
Kano, Kazuhiko; Takeuchi, Yukihiko; Watanabe, Takamoto; Ao, Kenichi; Kanoue, Masakazu; and Uenoyama, Hirotomi, 5,587,343, Cl. 437-228.000.
- Watanabe, Takao: *See*—
Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Watanabe, Tamio: *See*—
Yagi, Sakai; Watanabe, Tamio; and Nagano, Toru, 5,586,917, Cl. 439-752.000.
- Watanabe, Tetsu; and Aoki, Yoshio, to Sony Corporation, Optical disc system and optical disc therefor, 5,587,990, Cl. 369-275.200.
- Watanabe, Toshimi, to Nikon Corporation, Automatic focusing device, 5,587,762, Cl. 396-95.000.
- Watanuki, Tsuneo: *See*—
Nagahara, Akira; Sasaki, Sachio; Furukawa, Mitsuhiro; Watanuki, Tsuneo; Sawatari, Norio; Amaya, Mikio; and Narusawa, Toshiaki, 5,587,774, Cl. 355-219.000.
- WavePhone, Inc.: *See*—
Montgomery, Gerald D.; and Norrish, Jay B., 5,587,743, Cl. 348-473.000.
- Widowik, Mark S., to Critical Dimension, Incorporated, Shaving compositions containing particulate additives, 5,587,156, Cl. 424-73.000.
- Wearley, Jon P. Method of playing a quadrilateral chess game, 5,586,762, Cl. 273-261.000.
- Weaver, Samuel C.: *See*—
Vaughan, Gerald L.; and Weaver, Samuel C., 5,587,241, Cl. 428-375.000.
- Webb, Marlene K. Method of adapting a pair of children's shoes, 5,586,888, Cl. 434-258.000.
- Weber, Rainer: *See*—
Pohmer, Klaus; Weber, Rainer; Dörzbach-Lange, Cornelia; Haida, Reinhard; and Moretto, Hans-Heinrich, 5,587,513, Cl. 564-84.000.
- Weber, Robert M., to Nordco Inc, Apparatus for installing and removing rail clips, 5,586,502, Cl. 104-17.200.
- Weber, Uwe, to Stiftung, Carl Zeiss, Impact protected cam drive free of backlash, 5,586,467, Cl. 74-57.000.
- Weddle, E. Eugene: *See*—
Mandava, Babu S.; and Weddle, E. Eugene, 5,588,118, Cl. 395-200.050.
- Wedell, Eric D.; and Strecker, Darlene N., to Minnesota Mining and Manufacturing Company, Method for texturing a metallic thin film, 5,586,926, Cl. 451-59.000.
- Weder, Donald E.: *See*—
Craig, Frank; Straeter, Joseph G.; and Weder, Donald E., 5,586,425, Cl. 53-449.000.
- Wehrmann, Rick S.: *See*—
Lerner, Bernard; Hess, Richard W.; Crmauer, William M.; Wehrmann, Rick S.; and Kramer, James D., 5,586,708, Cl. 226-172.000.
- Weiner, Ronald M.; and Manyak, David M., to University of Maryland, Method for fermentation of marine bacteria, 5,587,313, Cl. 435-252.100.

- Weinerman, Lee S.; and Arthurs, Scott A., to Eastern Company, The, Handle operable rotary latch and lock, 5,586,458, Cl. 70-208.000.
- Weinert, Michael S.: *See*—
Williamson, Robert; Poole, Alan; and Weinert, Michael S., 5,588,055, Cl. 379-446.000.
- Weinstein, Michael J.: *See*—
Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein, Michael J.; and Wilker, Julie D., 5,587,914, Cl. 364-468.010.
- Weinstock, Zvika: *See*—
Segal, Jacob; Ben-Moshe, Josef; Weinstock, Zvika; and Harnik, Zvika, 5,588,151, Cl. 395-800.000.
- Weiper-Idelmann, Andreas: *See*—
Schnitzer, Georg; Suetsch, Franz; Schmitt, Michael; Kromm, Erich; Schlueter, Harald; Krueger, Rudolf; and Weiper-Idelmann, Andreas, 5,586,992, Cl. 8-653.000.
- Weisweiler, Werner: *See*—
Boegner, Walter; Kraemer, Michael; Krutzsch, Bernd; Wenninger, Guenter; Wirbeleit, Friedrich; and Weisweiler, Werner, 5,586,433, Cl. 60-274.000.
- Weiger GmbH: *See*—
Simonis, Jürgen, 5,586,494, Cl. 100-189.000.
- Wella Aktiengesellschaft: *See*—
Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401.000.
- Welles, Kenneth B., II: *See*—
Ali, Irfan; Hershey, John E.; Hladik, Stephen M.; Hassan, Amer A.; Channakeshu, Sandeep; Koilpillai, Ravinder D.; Welles, Kenneth B., II; and Tomlinson, Harold W., 5,588,005, Cl. 370-346.000.
- Wells, Jim: *See*—
Sullivan, Chris; Wells, Jim; and Prevost, Michael, 5,587,092, Cl. 219-113.000.
- Wells, Russell P.: *See*—
Leung, Ka-Ngo; Wells, Russell P.; and Craven, Glen E., 5,587,226, Cl. 428-210.000.
- Welter, James J.: *See*—
Fabricius, Dietrich M.; Harms, Ralf H.; and Welter, James J., 5,587,482, Cl. 548-179.000.
- Wendel, Harald: *See*—
Lang, Günther; Hoch, Dieter; Konrad, Eugen; Geibel, Wolfram; Wendel, Harald; and Kripp, Thomas, 5,587,174, Cl. 424-401.000.
- Wenner, Jeffrey W. Ratcheting type tool having free wheeling sleeve to facilitate use, 5,586,475, Cl. 81-60.000.
- Wenninger, Guenter: *See*—
Boegner, Walter; Kraemer, Michael; Krutzsch, Bernd; Wenninger, Guenter; Wirbeleit, Friedrich; and Weisweiler, Werner, 5,586,433, Cl. 60-274.000.
- Wenzler, Larry E.: *See*—
Hyng, Clement F.; Perko, Jack E.; and Wenzler, Larry E., 5,587,043, Cl. 156-566.000.
- Werner, Michael: *See*—
Adam, Paul; Tillmann, Heinz; deceased, Werner, Michael; Renn, Peter; Reif, Joachim; and Dölling, Uwe, 5,586,783, Cl. 280-737.000.
- Western Atlas International, Inc.: *See*—
Barr, Frederick J., 5,587,968, Cl. 367-75.000.
- Dragoset, William H., Jr.; and Jericevic, Zeljko, 5,587,965, Cl. 367-24.000.
- Shwe, Than; and Michaels, John M., 5,587,525, Cl. 73-15.520.
- Westinghouse Air Brake Company: *See*—
Kanjo, Wajih; Smith, Eric; Demoise, Thomas J.; Girotti, Michael; McCabe, Thomas; Fessler, Charles B.; and Natschke, Scott, 5,586,812, Cl. 303-7.000.
- McKay, Albert A.; and Smith, Eric G., 5,586,813, Cl. 303-22.400.
- Miller, Craig A., 5,586,668, Cl. 213-1.300.
- Westinghouse Electric Corporation: *See*—
Bevilacqua, Bruce W.; Malandra, Louis J.; Meuschke, Robert E.; and Harkness, Alex W., 5,588,031, Cl. 376-287.000.
- Westvaco Corporation: *See*—
Streisel, Robert C.; Hank, Mark A.; Mulcahy, Leo T.; and Peterson, Ralph S., 5,587,048, Cl. 162-7.000.
- Wettach, Richard H.: *See*—
Chupp, John P.; Hamper, Bruce C.; and Wettach, Richard H., 5,587,485, Cl. 548-377.100.
- Wettstein, Hans, to ABB Management AG, Baffle-cooled wall part, 5,586,866, Cl. 416-96.00A.
- Weyland, Peter; Treiber, Reinhard; Sturm, Alwin; Seibert, Horst; Renz, Hans; Reichert, Jürgen; and Häberle, Karl, to BASF Aktiengesellschaft, Mixtures containing water-emulsifiable isocyanates, 5,587,421, Cl. 524-591.000.
- Whang, David S.: *See*—
Willis, Kenneth E.; Fahey, William D.; and Whang, David S., 5,587,550, Cl. 102-217.000.
- Wheeler, Douglas M.: *See*—
Sawyer, David R.; and Wheeler, Douglas M., 5,586,801, Cl. 294-1.100.
- Wheeler, Larry A.: *See*—
Burke, James A.; Garst, Michael E.; and Wheeler, Larry A., 5,587,376, Cl. 514-249.000.
- Whipple, Walter, III: *See*—
Smith, John M.; Schneider, David A.; Dausch, Mark E.; and Whipple, Walter, III, 5,586,567, Cl. 134-57.00D.
- Whirlpool Corporation: *See*—
Manson, Larry J.; Scriber, Chris A.; and Davis, William L., 5,587,642, Cl. 318-812.000.
- Whitaker Corporation, The: *See*—
Baker, Ronald J.; Fisher, Douglas G.; Rupert, Martha L.; and Swartz, David M., 5,586,915, Cl. 439-733.100.
- Casey, Daniel T.; and Yohn, Brent D., 5,586,896, Cl. 439-218.000.
- Foster, George H., Jr., deceased; and Metzger, Donald L., 5,586,914, Cl. 439-676.000.
- Frantz, Robert H.; Larkin, John T., Jr.; and Correll, Robert S., Jr., 5,586,907, Cl. 439-500.000.
- Miller, Mitchell E.; Ferry, Julian J.; Kilbey, Brian E.; Coolbear, Bruce S.; and Gandy, Richard F., 5,586,911, Cl. 439-607.000.
- Raman, Venkat A., 5,587,884, Cl. 361-728.000.
- Reitz, Paul; and Abdelkader, Hatem, 5,588,013, Cl. 372-19.000.
- White, David M., to E-Systems, Inc. Method for manufacturing a coaxial interconnect, 5,587,119, Cl. 264-104.000.
- White, Robert L., to Board of Trustees Leland Stanford, Jr. University, High density magnetic information storage medium, 5,587,223, Cl. 428-195.000.
- Whiten, James D.: *See*—
Spamer, William S.; Suttles, J. Marshall; Parham, Dennis E.; and Whiten, James D., 5,586,687, Cl. 221-298.000.
- Whitesmith, Peter J. Optical cable fusion splice, 5,588,082, Cl. 385-96.000.
- Whittier Institute for Diabetes and Endocrinology: *See*—
Rubin, Jeffrey; Hayek, Alberto; Beattie, Gillian M.; and Oronoski, Timo P. J., 5,587,309, Cl. 435-240.200.
- Wiand, Richard K.; and Buschmole, Dennis R., to Inland Craft Products Co., Grinding apparatus with touch-top work surface, 5,586,928, Cl. 451-177.000.
- Widia GmbH: *See*—
König, Udo; Van Den Berg, Hendrikus; and Tabersky, Ralf, 5,587,233, Cl. 428-325.000.
- Wieboldt, Raymond: *See*—
Hess, George P.; Carpenter, Barry K.; Ramesh, Doraiswamy; and Wieboldt, Raymond, 5,587,509, Cl. 560-130.000.
- Wiedenmann, Karl-Heinz: *See*—
Grossa, Mario; Bode, Udo D.; Sondergeld, Manfred; Wiedenmann, Karl-Heinz; Convers, Ronald J.; Kalo, Steven M.; and Kudva, Ashok K., 5,587,272, Cl. 430-257.000.
- Wieloch, Christopher J.; Kappel, Mark A.; Annis, Jeffrey R.; Benard, David J.; Boehmer, Ellen; and Hildebrandt, Gernot, to Allen-Bradley Company, Inc. Method for interrupting electrical power between two conductors, 5,587,861, Cl. 361-14.000.
- Wienen, Wolfgang: *See*—
Narr, Berthold; Haeul, Norbert; Van Meel, Jacques; Wienen, Wolfgang; Entzeroth, Michael; and Ries, Uwe, 5,587,393, Cl. 514-381.000.
- Wiersum, Ulfert E.: *See*—
Boonstra, Tjerk O.; and Wiersum, Ulfert E., 5,588,083, Cl. 385-122.000.
- Wiese, Holger: *See*—
Beaumont, Hendrikus; Haas, Hanns-Otto; Wiese, Holger; and Lindner, Bernd, 5,586,499, Cl. 101-211.000.
- Wilber, James A.; and Koblitz, Karl R., to Thomson Consumer Electronics, Inc. Resistor-matched deflection apparatus for a video display, 5,587,631, Cl. 315-403.000.
- Wilbrecht Electronics, Inc.: *See*—
McSwiggen, John P.; and Roberts, Randall W., 5,588,064, Cl. 381-69.200.
- Wilcox, Reginald B., Jr.: *See*—
Voldman, Steven H.; Wallash, Albert J.; and Wilcox, Reginald B., Jr., 5,587,857, Cl. 360-103.000.
- Wilde, Craig G.: *See*—
Hawkins, Phillip R.; Wilde, Craig G.; and Seilhamer, Jeffrey J., 5,587,301, Cl. 435-69.100.
- Wilding, Peter; and Kricka, Larry J., to University of Pennsylvania, The Trustees of the, Mesoscale polynucleotide amplification devices, 5,587,128, Cl. 422-50.000.
- Wilhelm, Dieter: *See*—
von Gentzow, Wolfgang; Huber, Jürgen; Kapitza, Heinrich; Rogler, Wolfgang; Kleiner, Hans-Jerg; and Wilhelm, Dieter, 5,587,243, Cl. 428-413.000.
- Wilker, Julie D.: *See*—
Conradson, Scott A.; Barford, Lee A.; Fisher, William D.; Weinstein, Michael J.; and Wilker, Julie D., 5,587,914, Cl. 364-468.010.
- Wilkie, Bruce J.: *See*—
Muyschondt, Jorge E.; Parker, Gary A.; and Wilkie, Bruce J., 5,587,920, Cl. 364-489.000.
- Wilkinson, Everett, Bale feeder, 5,586,519, Cl. 119-60.000.
- Wilkinson, William T., to Wilkinson, William T. Adjustable length, adjustable weight, adjustable shock absorption, multi purpose exercise poles with electronics package, 5,586,957, Cl. 482-74.000.
- Will, Craig A. Personal paging, communications, and locating system, 5,588,009, Cl. 371-33.000.
- Willadsen, Peter: *See*—
Cobon, Gary S.; Moore, Joanna T.; Johnston, Law A. Y.; Willadsen, Peter; Kemp, David H.; Srisantha, Alagacone; and Riding, George A., 5,587,311, Cl. 435-240.200.
- Williams, Lance J.; and Kass, Michael, to Apple Computer, Inc. Method and system for reconstructing quantized signals, 5,587,711, Cl. 341-144.000.
- Williams, Linda K.: *See*—
Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,587,351, Cl. 503-227.000.
- Williams, Richard M., Jr. Hand operated crab leg opener with multiangled blade, 5,586,931, Cl. 452-6.000.

- Williams, Robert D. Self aligning substrate transmittance meter. 5,587,795, Cl. 356-432.000.
- Williams, Thomas. Portable security alarm unit. 5,587,700, Cl. 340-541.000.
- Williams, Willis R. Grid block workpiece clamping apparatus. 5,586,754, Cl. 269-99.000.
- Williams-Hughes, Christine M.: See—
- Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.
- Williamson, Robert. Poole, Alan; and Weiner, Michael S. Telephone holder with mounting assembly. 5,588,055, Cl. 379-446.000.
- Willis, Daniel E.: See—
- Hartman, Michael O.; Kinder, Dale J.; Rainey, Randy E.; Helmich, Arthur R.; and Willis, Daniel E., 5,587,055, Cl. 203-1.000.
- Willis, Frank M.: See—
- Johnson, Melvin H., and Willis, Frank M., 5,587,116, Cl. 264-1.250.
- Willis, Kenneth E.; Fahey, William D., and Whang, David S., to Quantic Industries, Inc. Internally timed, multi-output impulse cartridge. 5,587,550, Cl. 102-217.000.
- Willis, Tucker; and Cinquemani, James, Jr. Flag support and angulation system. 5,586,517, Cl. 116-173.000.
- Wilson, Alfred M.; and Dahn, Jeffery R., to Moli Energy (1990) Limited. Carbonaceous insertion compounds and use as anodes in rechargeable batteries. 5,587,256, Cl. 429-218.000.
- Wilson, Laura G.: See—
- Lin, Leroy C.; Wilson, Laura G.; Bhatnagar, Ashok; and Li, Hsin L., 5,587,230, Cl. 428-245.000.
- Wilson, Matthew; and Lauricella, Frank P., to Eastman Kodak Company. Variable format viewfinder for camera. 5,587,755, Cl. 396-380.000.
- Wilson, Wilbert J.; and O'Neal, Robert G., to Russell A Division Of Arco, Inc. Heat pipe defrost of evaporator drain. 5,586,441, Cl. 62-99.000.
- Willtron Company: See—
- Oldfield, William W.; Brinkoetter, Thomas R.; and Antes, Todd D., 5,587,934, Cl. 364-571.010.
- Windham, Elbert P.: See—
- Chen, Kuo-Raid G.; Misner, Raymond H.; Windham, Elbert P., and Richardson, Bernard D., 5,586,424, Cl. 53-138.200.
- Wingert, Horst; Sauter, Hubert; Ammermann, Eberhard; Lorenz, Gisela; Saur, Reinhold; Schellberger, Klaus; and Hampel, Manfred, to BASF Aktiengesellschaft. Fungicidal mixtures. 5,587,365, Cl. 514-63.000.
- Winter, Andreas; Dollé, Volker; and Spaleck, Walter, to Hoechst Aktiengesellschaft. Process for the preparation of syndiotactic polyolefins having a broad molecular weight distribution. 5,587,501, Cl. 556-53.000.
- Winter, Ari; and de Jong, Johannes, to Kone Oy. Push button panel for an elevator. 5,587,567, Cl. 187-395.000.
- Wirbeleit, Friedrich: See—
- Buegner, Walter; Kraemer, Michael; Kruttsch, Bernd; Wenninger, Guenter; Wirbeleit, Friedrich; and Weissweiler, Werner, 5,586,433, Cl. 60-274.000.
- Wisconsin Alumni Research Foundation: See—
- DeLuca, Hector F.; Schmoes, Heinrich K.; Perlman, Kato L.; Sicinski, Rafal R.; and Frahl, Jean M., 5,587,497, Cl. 552-653.000.
- Gould, Michael N.; Crowell, Pamela L.; Elson, Charles E.; and Clark, Steven S., 5,587,402, Cl. 514-729.000.
- Sih, Charles L., 5,587,318, Cl. 435-280.000.
- Wisconsin Alumni Research Foundation: See—
- Malter, James S., 5,587,300, Cl. 435-69.100.
- Wishneusky, John A., to Cirrus Logic, Inc. Method and arrangement for clock adjustment using programmable period binary rate multiplier. 5,588,145, Cl. 395-555.000.
- Wiskin, James W.: See—
- Johnson, Steven A.; Wiskin, James W.; Borup, David T.; Christensen, Douglas A.; and Stenger, Frank, 5,588,032, Cl. 378-8.000.
- Wistuba, Hermann: See—
- Fetzer, Thomas; Buechele, Wolfgang; Wistuba, Hermann; Otto, Bernhard; Buerger, Gert; and Pijl, Paul, 5,587,135, Cl. 423-239.100.
- Wittek Golf Supply Co., Inc.: See—
- Wittek, Robert, Sr.; Cantrell, Aron; and Sopko, Terry, 5,586,942, Cl. 473-168.000.
- Wittek, Robert, Sr.; Cantrell, Aron; and Sopko, Terry, to Wittek Golf Supply Co., Inc. Tee divider for golf driving range. 5,586,942, Cl. 473-168.000.
- Wittmeyer, Henning: See—
- Kellström, Magnus; Fogelström, Joacim; and Wittmeyer, Henning, 5,586,826, Cl. 384-450.000.
- Wojsznis, Wilhelm K.: See—
- Ho, Weng K.; Haug, Chang C.; and Wojsznis, Wilhelm K., 5,587,899, Cl. 364-157.000.
- Wolf, David. In line skate with dynamically adjustable wheels. 5,586,777, Cl. 280-11.220.
- Wolf, Rüdiger: See—
- Fehrmann, Gerd; Frömmel, Rainer; and Wolf, Rüdiger, 5,587,258, Cl. 429-228.000.
- Wolfe, Jack; and Ping, Roy C. C., to Bissell, and TTI. Hand carriage vacuum cleaner with accessory attachment. 5,586,358, Cl. 15-334.000.
- Wolog, Walter: See—
- Hubbard, David; and Wolog, Walter, 5,586,817, Cl. 312-334.440.
- Wong, Allen: See—
- Meyer, George W., Jr.; Wong, Allen; Spears, John H.; Bond, David L.; and Vondrak, Thomas F., 5,588,041, Cl. 379-59.000.
- Wong, Sui-Ming, to NanoSystems L.L.C. Butylene oxide-ethylene oxide block copolymer surfactants as stabilizer coatings for nanoparticle compositions. 5,587,143, Cl. 424-9.100.
- Wong, Victoria A.: See—
- Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.
- Wong, Warren H.: See—
- Ferrante, Joseph V.; Lockman, Mark E.; Matson, Donald P.; Gibbs, John A.; and Wong, Warren H., 5,587,932, Cl. 364-556.000.
- Woo, Sang J.: See—
- Lee, Je H.; Kim, Soo K.; Woo, Sang J.; and Yang, Tae S., 5,587,789, Cl. 386-68.000.
- Wood, Larry R.: See—
- Hippely, Keith A.; Wood, Larry R.; Walsh, Brian E.; and Choy, Terence A., 5,586,923, Cl. 446-14.000.
- Wood, Louis L.; and Calton, Gary J., to Bayer AG. Method of preventing deposition of tartar on teeth. 5,587,146, Cl. 424-49.000.
- Wood, Russell E.: See—
- Tollar, Paul S.; and Wood, Russell E., 5,586,450, Cl. 62-192.000.
- Wood, Warwick N., to Warman International Limited. Apparatus and method for separating solid/fluid mixtures. 5,586,966, Cl. 494-37.000.
- Woodard, Jeffrey P., to Rockwell International Corporation. Vehicle navigation system with non-overflow digital filter. 5,587,910, Cl. 364-443.000.
- Woodbridge Foam Corporation: See—
- Clark, Leslie E.; Hunter, Craig A.; Magee, Robert B.; Vande Wetering, Gerry; and Cheng, Wilfred W. T., 5,587,183, Cl. 425-4.00R.
- Woodside, Shane H., to Focal Technologies, Inc. In-line, two-pass, fiber optic rotary joint. 5,588,077, Cl. 385-26.000.
- Wright, Jeffrey P.; and Zheng, Hua, to Micron Technology, Inc. Synchronous memory allowing early read command in write to read transitions. 5,587,961, Cl. 365-233.000.
- Wright, Michael J.: See—
- Agrawal, Om P.; Wright, Michael J.; and Shen, Ju, 5,587,921, Cl. 364-489.000.
- Wu, Cheng H.: See—
- Ivri, Yehuda; and Wu, Cheng H., 5,586,550, Cl. 128-200.160.
- Wu, Fen-Shiung: See—
- Tsai, Philip; Hung, Chun-Yen; and Wu, Fen-Shiung, 5,587,878, Cl. 361-683.000.
- Wu, Hongxiang: See—
- Hong, Jibi; Chu, Jianhua; and Wu, Hongxiang, 5,587,347, Cl. 501-155.000.
- Wu, Ya: See—
- Jones, Joel W.; and Wu, Ya, 5,587,931, Cl. 364-551.020.
- Wusirika, Raja R.: See—
- Swaroop, Srinivas H.; and Wusirika, Raja R., 5,587,137, Cl. 423-239.200.
- Wuu, Shou-Gwo: See—
- Su, Chung-Hui; Liang, Mong-Song; Wu, Shou-Gwo; and Wang, Chen-Jong, 5,587,696, Cl. 338-314.000.
- Wyborn, Graeme M.; and Nicholls, Howard C., to SGS-Thomson Microelectronics Ltd. Method of forming contacts in vias formed over interconnect layers. 5,587,339, Cl. 437-195.000.
- Wybourne, Martin N.: See—
- Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P., 5,587,273, Cl. 430-269.000.
- Wynn, Woodson D.: See—
- Velardo, Patrick M., Jr.; and Wynn, Woodson D., 5,587,998, Cl. 370-289.000.
- Xerox Corporation: See—
- Auty, Ronald E.; and Gerbasi, Dennis G., 5,587,781, Cl. 355-301.000.
- Badesha, Santokh S.; Pan, David H.; Prest, William M., Jr.; Henry, Arnold W.; Heeks, George J.; and Frangello, Louis D., 5,587,208, Cl. 427-503.000.
- Bergen, Richard F., 5,587,584, Cl. 250-325.000.
- Hansen, Paul, 5,586,755, Cl. 271-9.060.
- Harrington, Steven J., 5,588,093, Cl. 395-109.000.
- Herbert, William G., 5,586,927, Cl. 451-88.000.
- Hsieh, Bing R.; Mori, Joseph; Machonkin, Mary A.; and Ewing, Joan R., 5,587,224, Cl. 428-195.000.
- Islam, Abu S.; Kleckner, Robert J.; Chin, Leo; Sonnenberg, Hardy; and Klein, Anthony A., 5,587,767, Cl. 355-27.000.
- Karz, Robert S., 5,587,730, Cl. 347-43.000.
- Pinkney, Heidi; Hor, Ah-Mee; and Popovic, Zoran D., 5,587,262, Cl. 430-54.000.
- Xetron Corp.: See—
- Dapper, Mark J.; Geile, Michael J.; and Carlin, Barry W., 5,588,022, Cl. 375-216.000.
- Xicor, Inc.: See—
- Owen, William H.; and Jaffe, James M., 5,587,573, Cl. 235-380.000.
- Xie, Zheng-yi, to Advanced Micro Devices. DTMF detector system and method which performs static and dynamic thresholding. 5,588,053, Cl. 379-386.000.
- Xin, Zhong C.: See—
- Choi, Hyung K.; and Xin, Zhong C., 5,587,167, Cl. 424-195.100.
- XTAL Technologies, Ltd.: See—
- Roberts, Gerald E.; and Roberts, Michael E., 5,587,663, Cl. 324-727.000.
- Yabe, Hiroshi; and Ogihara, Tsutomu, to Seiko Epson Corporation. Digital trimming for frequency adjustment. 5,587,691, Cl. 331-44.000.

- Yahuki, Hiroyuki; Sagawa, Morikazu; and Makimoto, Mitsuo, to Matsushita Electric Industrial Co., Ltd. Ring resonator oscillator usable in frequency synthesizers and communication apparatus. 5,587,690, Cl. 331-2.000.
- Yabuta, Motoshi: See—
- Yukawa, Yoshiyuki; Yabuta, Motoshi; Nakahata, Akimasa; and Sugimura, Yoh, 5,587,426, Cl. 525-124.000.
- Yach, Randy L.; and Hull, Richard L., to Microchip Technology Incorporated. Power-on reset circuit. 5,587,866, Cl. 361-90.000.
- Yacobi, Yacov: See—
- Ganesan, Ravi; and Yacobi, Yacov, 5,588,061, Cl. 380-30.000.
- Yagi, Sakai; Tsuji, Masanori; Kashiya, Motohisa; and Endo, Takayoshi, to Yazaki Corporation. Connector terminal test jig. 5,586,900, Cl. 439-310.000.
- Yagi, Sakai; Watanabe, Tamio; and Nagano, Toru, to Yazaki Corporation. Connector having an ascertainment hole for visually checking engagement. 5,586,917, Cl. 439-752.000.
- Yahagi, Kazuyuki: See—
- Ochiai, Ryuji; Morita, Kouzi; and Yahagi, Kazuyuki, 5,587,155, Cl. 424-70.280.
- Yahagi, Masahiko: See—
- Ohkubo, Kazuko; and Yahagi, Masahiko, 5,588,039, Cl. 379-58.000.
- Yale, Thomas W. Artificial intelligence language program. 5,587,903, Cl. 395-759.000.
- Yale University: See—
- Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, 5,587,362, Cl. 514-46.000.
- Yamada, Kenji: See—
- Udagawa, Tsunekazu; and Yamada, Kenji, 5,586,770, Cl. 277-11.000.
- Yamada, Kosaku: See—
- Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kushida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.
- Yamada, Masazumi; Kadono, Shinya; and Kato, Shiro, to Matsushita Electric Industrial Co., Ltd. Apparatus for separately recording input coded video signal and important data generated therefrom. 5,587,806, Cl. 386-68.000.
- Yamada, Mitsuo: See—
- Yamoto, Shubei; Ito, Koji; and Yamada, Mitsuo, 5,587,059, Cl. 204-505.000.
- Yamagami, Tamotsu; Sako, Yoichiro; and Yamamoto, Masanobu, to Sony Corporation. Optical recording medium having a pre-formed recording track which is offset along its width to record frame sync signals of information. 5,587,901, Cl. 369-275.300.
- Yamagishi, Yoji: See—
- Urawa, Yoshio; Furukawa, Ken; Shimizu, Toshikazu; Yamagishi, Yoji; Tsunagi, Tomio; and Ichino, Tomio, 5,587,504, Cl. 558-58.000.
- Yamaguchi, Kunihiko: See—
- Kitsukawa, Goro; Watanabe, Takao; Hori, Ryoichi; Honma, Noriyuki; Yamaguchi, Kunihiko; and Itoh, Kiyoo, 5,587,952, Cl. 365-207.000.
- Yamaguti, Usaburo: See—
- Shindo, Yasuhiro; Yamaguti, Usaburo; Ioka, Kazuo; Suzuki, Tosio; Minagawa, Akihiro; and Kitabatake, Syoichi, 5,587,320, Cl. 435-290.100.
- Yamaha Corporation: See—
- Fujii, Junji; and Okumura, Yukimasa, 5,587,544, Cl. 84-411.00R.
- Kato, Hirokazu; and Mino, Hiroshi, 5,587,546, Cl. 84-609.000.
- Nagamoto, Itsushi; Sumikawa, Noburo; Hirakawa, Tatsuya; and Nakanishi, Tatsuo, 5,586,944, Cl. 473-248.000.
- Yamaha Hatsudoki Kabushiki Kaisha: See—
- Adachi, Shubei; and Inami, Junichi, 5,586,530, Cl. 123-188.800.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,921, Cl. 440-38.000.
- Kobayashi, Noboru; Koyanagi, Tomoyoshi; and Ikeda, Keiji, 5,586,922, Cl. 440-88.000.
- Yamakawa, Takeshi: See—
- Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, 5,587,813, Cl. 358-500.000.
- Yamamoto, Akihiro: See—
- Watabe, Masahiro; Yanai, Noriyuki; Niwano, Kentaro; and Yamamoto, Akihiro, 5,587,776, Cl. 355-245.000.
- Yamamoto, Chikara: See—
- Miyano, Hitoshi; and Yamamoto, Chikara, 5,587,839, Cl. 359-660.000.
- Yamamoto, Hajime: See—
- Nakamura, Masahiko; Yamamoto, Hajime; and Terada, Hiroshi, 5,587,783, Cl. 355-326.00R.
- Yamamoto, Hideo: See—
- Kamei, Nobuo; Ikenoue, Yoshikazu; and Yamamoto, Hideo, 5,587,801, Cl. 358-296.000.
- Yamamoto, Kaoru: See—
- Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hiromi; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.
- Yamamoto, Kouji: See—
- Tanabe, Takashi; and Yamamoto, Kouji, 5,588,079, Cl. 385-78.000.
- Yamamoto, Masanobu: See—
- Yamagami, Tamotsu; Sako, Yoichiro; and Yamamoto, Masanobu, 5,587,901, Cl. 369-275.300.
- Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, to Sun Medical Co., Ltd. Primer composition and curable composition. 5,587,406, Cl. 523-116.000.
- Yamamoto, Takashi; Sakaguchi, Yasunobu; and Utsugi, Makoto, to Fuji Photo Film Co., Ltd. Photographic projector-printer assembly. 5,587,768, Cl. 355-41.000.
- Yamamoto, Takatsugu; Kobayashi, Shigetoshi; and Ikeda, Tomohiro, to Yazaki Corporation. Protective casing for end connecting part of wire. 5,587,556, Cl. 174-74.00R.
- Yamamoto, Takeo: See—
- Sugino, Osamu; and Yamamoto, Takeo, 5,587,780, Cl. 355-274.000.
- Yamamoto, Takeshi: See—
- Tsubota, Kazuaki; and Yamamoto, Takeshi, 5,586,831, Cl. 403-305.000.
- Yamamoto, Yoshihisa: See—
- Iwata, Akihito; Tsukamoto, Kazumasa; Mikami, Kazuhiro; Hayabuchi, Masahiro; and Yamamoto, Yoshihisa, 5,586,954, Cl. 477-93.000.
- Yamamoto, Yuji: See—
- Shima, Kazunobu; and Yamamoto, Yuji, 5,587,758, Cl. 396-613.000.
- Yamana, Masayuki; and Isogai, Tomohiro, to Daikin Industries, Ltd. Composition being capable of imparting conductivity and non-tackifying property, paint using the composition, and roller. 5,587,110, Cl. 252-511.000.
- Yamanaka, Chiyo: See—
- Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367.000.
- Yamanaka, Masanobu: See—
- Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367.000.
- Yamanaka, Motosuke: See—
- Negi, Shigeto; Yamanaka, Motosuke; Katsu, Kanemasa; Sugiyama, Isao; Komatsu, Yuuki; Kamata, Atsushi; Tsuruoka, Akihiko; and Machida, Yoshimasa, 5,587,473, Cl. 540-222.000.
- Yamanaka, Shizuo; and Hashimoto, Takao, to Sumitomo Metal Industries, Ltd. Process and apparatus for producing molten metal coated steel sheets. 5,587,017, Cl. 118-424.000.
- Yamanka, Toshio: See—
- Miyaji, Takashi; Nishikawa, Yoshikazu; Andou, Yukinori; Yamanaka, Toshio; and Kadowaki, Hideaki, 5,587,777, Cl. 355-245.000.
- Yamano, Shozo: See—
- Kusaka, Yosuke; Muramatsu, Masaru; Utagawa, Ken; and Yamano, Shozo, 5,587,761, Cl. 396-95.000.
- Yamanouchi, Junichi: See—
- Mifune, Hiroyuki; Yamanouchi, Junichi; and Ishiguro, Shoji, 5,587,279, Cl. 430-567.000.
- Saitou, Mitsuo; Yamanouchi, Junichi; and Hosoya, Yoichi, 5,587,281, Cl. 430-567.000.
- Yamaoka, Osamu: See—
- Azumi, Takeshi; Yamaoka, Osamu; and Kubota, Kazuyuki, 5,587,869, Cl. 361-301.300.
- Yamasaki, Hidetaka: See—
- Aoki, Hideji; Tashima, Takahiro; Nakashima, Sukekazu; Osako, Yoshiyuki; and Yamasaki, Hidetaka, 5,587,633, Cl. 318-164.000.
- Yamashita, Eiichi: See—
- Enokida, Takashi; Naraki, Akihiro; Yamashita, Eiichi; and Tatsu, Haruyoshi, 5,587,413, Cl. 524-200.000.
- Yamashita, Hiroki: See—
- Johdai, Akiyoshi; Ohhata, Akira; Yamashita, Hiroki; Matsuo, Hirokazu; and Hirano, Yoshihito, 5,587,782, Cl. 355-309.000.
- Yamashita, Hiroshi; and Ueda, Yutaka, to Konica Corporation. Solid processing composition for silver halide light-sensitive photographic material and method of processing by the use thereof. 5,587,277, Cl. 430-458.000.
- Yamashita, Michiya: See—
- Ikegawa, Akihito; Aritomo, Kouichi; Tsukamoto, Kazuki; and Yamashita, Michiya, 5,587,551, Cl. 118-661.000.
- Yamashita, Takayuki: See—
- Arai, Kazuhiko; Oda, Yasuhiro; Kubo, Masahiko; Higashimura, Masayo; Iwaoka, Kazuhiro; and Yamashita, Takayuki, 5,587,772, Cl. 355-208.000.
- Yamashita, Yuichi: See—
- Maki, Atsushi; Kawaguchi, Fumio; Yamashita, Yuichi; and Ito, Yoshitoshi, 5,586,554, Cl. 128-653.100.
- Yamashita, Zenjiro: See—
- Nagaura, Toshikazu; Yamashita, Zenjiro; Arikawa, Kazuhiko; and Ohta, Kenji, 5,587,994, Cl. 369-291.000.
- Yamato, Takashi: See—
- Kurosaki, Tsuyoshi; Tomioka, Atsuo; and Yamato, Takashi, 5,587,129, Cl. 422-64.000.
- Yamauchi, Hiroshige; and Nishi, Shonosuke, to Shimadzu Chemical Co., Ltd. Crushing and dispersing bag. 5,586,732, Cl. 241-168.000.
- Yamazaki, Hiroshi: See—
- Kori, Teruhiko; Yamazaki, Hiroshi; Kawamura, Harumi; Shima, Hisato; and Ogawa, Kazuyuki, 5,587,849, Cl. 360-69.000.
- Yamazaki, Shiro: See—
- Koide, Norikatsu; Yamazaki, Shiro; Umezaki, Junichi; and Asami, Shinya, 5,587,593, Cl. 257-94.000.
- Yamazaki, Shuichi; Mama, Takashi; Sato, Nobuyuki; Yamakawa, Takeshi; Kobayashi, Shinji; Kaneko, Yoshio; and Oshikiri, Koji, to Ricoh Company, Ltd. Data transfer device for an image forming apparatus. 5,587,813, Cl. 358-500.000.
- Yamazaki, Shunpei, to Semiconductor Energy Laboratory Co., Ltd. Method for manufacturing semiconductor device. 5,587,330, Cl. 437-41.000.

Yamazaki, Shunpei, to Semiconductor Energy Laboratory Co., Ltd. Method of forming a semiconductor device in a substrate depression. 5,587,340, Cl. 437-203.000.

Yamazaki, Taku: See—
Yoshida, Koji; Yamazaki, Taku; and Mori, Akira, 5,587,094, Cl. 219-121.680.

Yamazaki, Toshio: See—
Mochizuki, Shigeo; Matsumoto, Masahiro; Yamazaki, Toshio; and Ichinobe, Shoji, 5,587,445, Cl. 526-271.000.

Yamazaki, Youichi: See—
Hibino, Hideo; Yokonuma, Norikazu; Kazami, Kazuyuki; and Yamazaki, Youichi, 5,587,751, Cl. 396-319.000.

Yamoto, Shuhei; Ito, Koji; and Yamada, Mitsuo, to Nippon Paint Co., Ltd. Anticorrosive cathodic electrodeposition paint. 5,587,059, Cl. 204-505.000.

Yan, Mingdi; Keana, John F. W.; Wybourne, Martin N.; and Sevrain, Christophe J. P., to Advanced Microbotics Corporation; and University of Oregon, State of Oregon Acting by and through the State Board of Higher Education on Behalf of the Molecularly Imprinted Materials, method for their preparation and devices employing such materials. 5,587,273, Cl. 430-269.000.

Yanai, Noriyuki: See—
Watabe, Masahiro; Yanai, Noriyuki; Niwano, Kentaro; and Yamamoto, Akihiro, 5,587,776, Cl. 355-245.000.

Yang, Ming T., to United Microelectronics Corporation. Series MOS ROM with tapered oxide side walls. 5,587,600, Cl. 257-391.000.

Yang, Robert K.: See—
Cherukuri, Subraman R.; Yang, Robert K.; Bowles, Cecil A.; Zamudio-Tena, Jose F.; and Bhowmik, Santi R., 5,587,198, Cl. 426-660.000.

Yang, Rui Q., to University of Houston. Light emitting devices based on interband transitions in type-II quantum well heterostructures. 5,588,015, Cl. 372-45.000.

Yang, Su-Pei; and Chen, Shyh-Lee. Speaker mounting structure. 5,588,066, Cl. 381-188.000.

Yang, Tae S.: See—
Lee, Je H.; Kim, Soo K.; Woo, Sang J.; and Yang, Tae S., 5,587,789, Cl. 386-68.000.

Yaniv, Daphna R.: See—
Jung, Pan S.; and Yaniv, Daphna R., 5,587,523, Cl. 73-105.000.

Yannai, Shmuel: See—
Malkin, Boris; Perlov, Gena; and Yannai, Shmuel, 5,587,131, Cl. 422-186.110.

Yano, Hideyuki; Araya, Junji; Ozeki, Yukihiko; Kugo, Harumi; Sakaizawa, Katsuhiko; Furuya, Tadashi; and Iwasaki, Osamu, to Canon Kabushiki Kaisha. Electrophotographic apparatus for performing image exposure and development simultaneously. 5,587,773, Cl. 355-210.000.

Yano, Takashi: See—
Murakami, Kimihiko; Ohnishi, Shuhei; Yano, Takashi; and Itoh, Manabu, 5,587,392, Cl. 514-359.000.

Yao, Gang-Qing: See—
Chu, Chung K.; Cheng, Yung-Chi; Pai, Balakrishna S.; and Yao, Gang-Qing, 5,587,362, Cl. 514-46.000.

Yasnascoli, Donald; and Leyderman, Alexander D., to Carrier Corporation. Rotary compressor having oil pumped through a vertical drive shaft. 5,586,876, Cl. 418-60.000.

Yasuda, Kenichi; Furutani, Kiyohiro; and Miyamoto, Hiroshi, to Mitsubishi Denki Kabushiki Kaisha. Semiconductor integrated circuit device having improvement arrangement of pads. 5,587,607, Cl. 257-690.000.

Yasuda, Kouji: See—
Nakata, Kiyoshi; Tanamachi, Tokunosuke; Nakamura, Kiyoshi; Terunuma, Mutsuhiro; Suzuki, Masato; Tsutsui, Yoshio; Toyota, Eiichi; and Yasuda, Kouji, 5,587,891, Cl. 363-41.000.

Yasuda, Yasuhiko: See—
Katayama, Akihiro; and Yasuda, Yasuhiko, 5,588,069, Cl. 382-166.000.

Yasui, Yoshihiro: See—
Takami, Hiroshi; Yasui, Yoshihiro; and Okumura, Takashi, 5,586,500, Cl. 101-327.000.

Yasukawa, Junichi: See—
Miyazaki, Susumu; Nakano, Tsuyoshi; Niizaki, Nobuya; Yasukawa, Junichi; and Matsumura, Miki, 5,587,260, Cl. 430-7.000.

Yasunaga, Kuniaki; and Ueno, Shigeru, to Bridgestone Corporation. Ink retainer. 5,587,731, Cl. 347-86.000.

Yazaki Corporation: See—
Sakai, Hitoshi; and Ohtaka, Kazuto, 5,586,854, Cl. 411-429.000.

Shinji, Yasuhisa; and Takase, Hiraji, 5,586,897, Cl. 439-271.000.

Shinji, Yasuhisa; Morishita, Kazuhiro; and Takase, Hiraji, 5,586,916, Cl. 439-752.000.

Yagi, Sakai; Tsuji, Masanori; Kashiyama, Motohisa; and Endo, Takayoshi, 5,586,900, Cl. 439-310.000.

Yagi, Sakai; Watanabe, Tamio; and Nagano, Toru, 5,586,917, Cl. 439-752.000.

Yamamoto, Takatatsu; Kobayashi, Shigehiko; and Ikeda, Tomohiro, 5,587,556, Cl. 174-74.000.

Yazaki Industrial Chemical Co.: See—
Yoshino, Shuji, 5,586,639, Cl. 198-690.000.

Yazici, Muammer; and Richarz, Werner; to Düpi Kr. Datta. Air handling structure for pan inlet and outlet. 5,587,563, Cl. 181-224.000.

Yeager, Walter H.: See—
Hennie, Robert N., II; Peake, Clinton J.; Cullen, Thomas G.; Lew, Albert C.; Chagaturu, Munirathnam K.; Ray, Partha S.; and Yeager, Walter H., 5,587,379, Cl. 514-275.000.

Yeates, Anthony J.: See—
Landis, Michael R.; Yeates, Anthony J.; and Gavin, Thomas J., 5,588,148, Cl. 395-601.000.

Yee, James A.: See—
Peterson, Fred M.; and Yee, James A., 5,588,067, Cl. 382-103.000.

Yeh, Frank. Handle grip piece for use in gripping a drinking mug. 5,586,682, Cl. 220-755.000.

Yeh, Sheng-Fu. CD bank. 5,586,650, Cl. 206-308.100.

Yerram, Nagender: See—
Goodrich, Raymond P., Jr.; Platz, Matthew S.; Yerram, Nagender; Hackett, Roger W.; van Borssum Waalkes, Marjan; Williams-Hughes, Christine M.; and Wong, Victoria A., 5,587,490, Cl. 549-282.000.

Yesel, Leon P.; and Kitzerow, John P., to Caterpillar Inc. Transmission and engine overspeed control. 5,587,905, Cl. 364-424.082.

Yeung, Kah T. D., to St. Jude Children's Research Hospital. Method and apparatus for three dimensional image reconstruction from multiple stereoscopic or isocentric backprojections. 5,588,033, Cl. 378-4.000.

Yewer, Edward H., Jr. Reversible support belt. 5,586,969, Cl. 602-19.000.

Yi, Junsin: See—
Anderson, Wayne A.; Jia, Quanxi; Yi, Junsin; and Chang, Lin-Huang, 5,587,870, Cl. 361-313.000.

Yin, Ji-Zhong, to Micronics Computers Inc. Fan with transition chamber for providing enhanced convective flow. 5,586,865, Cl. 415-213.100.

YKK Corporation: See—
Fudaki, Tsutomu, 5,586,370, Cl. 24-433.000.

Hashimoto, Koji; Habazaki, Hiroki; Mrowec, Stanislaw; and Danielewski, Marek, 5,587,028, Cl. 148-403.000.

Matsuda, Yoshio; Akashi, Shunji; and Yoshida, Hiroshi, 5,586,369, Cl. 24-392.000.

Matsuda, Yoshio; and Kato, Hidenobu, 5,586,454, Cl. 66-193.000.

Shibasaki, Yasuo; Oda, Kiichi; and Fukuda, Takeshi, 5,587,010, Cl. 106-287.170.

Takizawa, Toshiaki; and Iwai, Kazuo, 5,586,595, Cl. 160-330.000.

Yli-Kauppi, Jouko: See—
Kerttula, Reima; and Yli-Kauppi, Jouko, 5,586,397, Cl. 34-114.000.

Yohn, Brent D.: See—
Casey, Daniel T.; and Yohn, Brent D., 5,586,896, Cl. 439-218.000.

Yokogawa Electric Corporation: See—
Imamura, Makoto, 5,587,679, Cl. 327-170.000.

Yokohama Rubber Co., Ltd.: See—
Sugiura, Michihiko, 5,586,951, Cl. 473-379.000.

Yokono, Tomohiko: See—
Kawaguchi, Masahiro; Sonobe, Masanori; Kanzaki, Shigeki; and Yokono, Tomohiko, 5,586,870, Cl. 417-222.200.

Yokonuma, Norikazu: See—
Hibino, Hideo; Yokonuma, Norikazu; Kazami, Kazuyuki; and Yamazaki, Youichi, 5,587,751, Cl. 396-319.000.

Yokoyama, Minoru: See—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.

Yoneda, Masato; and Shibata, Yoshiaki, to Kawasaki Steel Corporation. Data flow control apparatus and memory apparatus. 5,588,137, Cl. 395-490.000.

Yonehara, Toshimitsu: See—
Minato, Tetsuya; Yonehara, Toshimitsu; Teranishi, Junichi; Toyoda, Shoji; Bito, Toshiaki; and Takashima, Kazushige, 5,587,694, Cl. 336-65.000.

Yonekawa, Masao; Minagawa, Kazuji; Oi, Kiyotoshi; Miwa, Makoto; and Majima, Yoshihiro, to Nippondenso Co., Ltd. Fuel supplying apparatus for internal combustion engine. 5,586,539, Cl. 123-458.000.

Yonekawa, Takao: See—
Suzuki, Hiroyuki; Kodama, Naoki; Yonekawa, Takao; Takagaki, Tokuhiko; Endo, Naoto; Abe, Katsuo; and Suganuma, Tsuneo, 5,587,235, Cl. 428-332.000.

Yoneyama, Koji: See—
Okubo, Mamoru; and Yoneyama, Koji, 5,586,434, Cl. 60-345.000.

Yoneyama, Masakazu: See—
Nakatsugawa, Haruyasu; Yoneyama, Masakazu; and Urabe, Shigeharu, 5,587,282, Cl. 430-637.000.

Yonezawa, Yoshiyuki: See—
Nakai, Sadao; Izawa, Yasukazu; Yamanaka, Masanobu; Ohmi, Masato; Akatsuka, Masanori; Yamanaka, Chiyo; and Yonezawa, Yoshiyuki, 5,587,793, Cl. 356-367.000.

Yoo, Jang-hoon; Rim, Kyung-hwa; Chung, Chong-sam; and Lee, Chul-woo, to Samsung Electronics Co., Ltd. Optical pickup for optical magnetic disc. 5,587,976, Cl. 369-13.000.

Yoon, Heungsik: See—
Kim, Sung C.; Choy, Nakyeon; Lee, Chang S.; Son, Young C.; Choi, Ho I.; Koh, Jong S.; Yoon, Heungsik; Park, Chi H.; and Kim, Sang S., 5,587,388, Cl. 514-314.000.

Yoon, InBae. Safety penetrating instrument. 5,586,991, Cl. 606-185.000.

Yoon, Roe-Hwan; and Luttrell, Gerald H., to Virginia Tech Intellectual Property Inc. Method for dewatering particles. 5,587,085, Cl. 210-711.000.

Yoshiaki, Wakashima: See—
Masayuki, Watanabe; Toshio, Sugano; Seichiro, Tsukui; Takashi, Ono; and Yoshiaki, Wakashima, 5,587,341, Cl. 437-206.000.

Yoshida, Hiroshi: See—
Matsuda, Yoshio; Akashi, Shunji; and Yoshida, Hiroshi, 5,586,369, Cl. 24-392.000.

Yoshida, Kazuhiko: See—

Oyabe, Kazunori; Yoshida, Kazuhiko; and Fujihira, Tatsuhiro, 5,587,655, Cl. 323-312.000.

Yoshida, Kazuhiro, to Murata Manufacturing Co., Ltd. Method for manufacturing semiconductor device. 5,587,328, Cl. 437-40.000.

Yoshida, Kazuyoshi; Itoh, Hiroshi; Fukuoka, Hiroshi; and Shinohara, Makoto, to Kabushiki Kaisha Toshiba. Register block circuit for central processing unit of microcomputer. 5,588,133, Cl. 395-477.000.

Yoshida, Koji; Yamazaki, Taku; and Mori, Akira, to Kabushiki Kaisha Komatsu Seisakusho. Laser marking apparatus. 5,587,094, Cl. 219-121.680.

Yoshida, Takayuki: See—
Kotoh, Satoru; Sakuma, Kiyoshi; Yoshida, Takayuki; Sano, Hironori; Aoki, Katuyuki; Suzuki, Shin'ichi; Koizumi, Hideaki; Yamamoto, Kaoru; Matsushita, Kunio; Unno, Kenichi; and Oguma, Tomoko, 5,586,935, Cl. 454-320.000.

Yoshida, Takehiro: See—
Ono, Takeshi; Yoshida, Takehiro; Kobayashi, Makoto; Wada, Satoshi; Terajima, Hisao; Yokoyama, Minoru; Arai, Takashi; Tomoda, Akihiro; and Ishida, Yasushi, 5,587,733, Cl. 347-185.000.

Yoshida, Yasuhisa: See—
Matsumoto, Takuya; Hashimoto, Toru; Namiki, Koichi; Yoshida, Yasuhisa; and Kasai, Satoshi, 5,587,909, Cl. 364-431.080.

Yoshii, Noboru: See—
Kanemitsu, Norihiko; Tamura, Manabu; Nakao, Koh; Kato, Yukari; Ejima, Katsumi; and Yoshii, Noboru, 5,586,799, Cl. 296-203.000.

Yoshikawa, Shuichi: See—
Murata, Yasumoto; Ikeuchi, Michio; Yoshikawa, Shuichi; and Watanabe, Masahiko, 5,588,052, Cl. 379-283.000.

Yoshino, Hiroyuki; and Koji, Takashi, to Casio Computer Co., Ltd. Radio communication devices. 5,587,823, Cl. 359-143.000.

Yoshino, Hiroyuki: See—
Sato, Shinichi; Akaza, Syunsuke; and Yoshino, Hiroyuki, 5,588,096, Cl. 395-135.000.

Yoshino Kogyosho Co., Ltd.: See—
Tanaka, Ban; Nii, Hiroki; Yamada, Kosaku; Kishida, Hideo; Miya, Takashi; Koshio, Shuichi; and Hayakawa, Tadashi, 5,587,405, Cl. 522-98.000.

Yoshino, Shuji, to Yazaki Industrial Chemical Co. Powered roller conveyor for light loads. 5,586,639, Cl. 198-690.200.

Yoshoka, Kazumi; Ohta, Takeo; Furukawa, Shigeaki; and Kawahara, Katsumi, to Matsushita Electric Industrial Co., Ltd. Optical recording medium. 5,587,216, Cl. 428-64.400.

Yoshiura, Tsukasa; and Masaki, Kiyoshi, to Matsushita Electric Industrial Co., Ltd. Disk head driving device using linear actuator with multipolar magnets. 5,587,852, Cl. 360-78.120.

Young, Kevin, to F. C. Young & Co., Inc. Edge-folded tinsel garland and method of production. 5,587,031, Cl. 156-148.000.

Young, Randy C. Rotary siphon flusher. 5,586,342, Cl. 4-368.000.

Young, Roland O. Lifting apparatus. 5,586,619, Cl. 187-226.000.

Yuan, Xiaoying: See—
Jones, Frank N.; Fu, Shou-Kuan; Hua, Jun; and Yuan, Xiaoying, 5,587,428, Cl. 525-165.000.

Yusaa, Yoshifumi: See—
Konno, Masao; and Yusaa, Yoshifumi, 5,587,510, Cl. 562-496.000.

Yui, Tomoyuki: See—
Mizukami, Masamichi; Yui, Tomoyuki; Arai, Yoshihisa; and Gocho, Yoshihiro, 5,587,106, Cl. 252-299.610.

Yukawa, Yoshiyuki; Yabuta, Motohiko; Nakahata, Akimasa; and Sugimura, Yoh, to Kansai Paint Company, Limited. Process for preparing self-crosslinking resin. 5,587,426, Cl. 525-124.000.

Yumiyama, Shigeru; Onodera, Ko; and Mori, Yoshimi, to Hitachi, Ltd. Rotary armature and method of forming armature coil. 5,587,619, Cl. 310-201.000.

Yumura, Motoo: See—
Ohashima, Satoshi; Yumura, Motoo; Kuriki, Yasunori; Uchida, Kunio; and Ikazaki, Fumikazu, 5,587,141, Cl. 423-445.000.

Yuri, Nobuyuki: See—
Ikeda, Susumu; Isobe, Toshimi; Inoue, Atsuo; Tajiri, Akihiro; Takagi, Masahiro; Ishikawa, Mitsuru; Sakuma, Choji; and Yuri, Nobuyuki, 5,586,448, Cl. 62-156.000.

Yuscavage, Thomas M. Mooring device. 5,586,514, Cl. 114-230.000.

Zabron, Florian S.; Marlette, Mary E.; Rothman, Miles S.; and Hanrahan, William D., to Globe International Inc. Modular belting having antimicrobial characteristics and method of manufacture. 5,586,643, Cl. 198-853.000.

Zagar, Paul; and Manning, Troy, to Micron Technology, Inc. Semiconductor device having an output buffer which reduces signal degradation due to leakage of current. 5,587,671, Cl. 326-83.000.

Zahler, Byron G.: See—
Sprvey, Thomas R.; and Zahler, Byron G., 5,586,556, Cl. 128-697.000.

Zamudio-Tena, Jose F.: See—
Cherukuri, Subraman R.; Yang, Robert K.; Bowles, Cecil A.; Zamudio-Tena, Jose F.; and Bhowmik, Santi R., 5,587,198, Cl. 426-660.000.

Zandt, Lisa: See—
Pabuski, Edward E.; Dimond, Randall L.; Priest, John H.; Zandt, Lisa; Stehntz, Kathleen K.; and Mendoza, Leopoldo G., 5,587,286, Cl. 435-6.000.

Zdrachala, Richard: See—
Borchers, Gerd; Dake, Ingo; Dinkelaker, Albrecht; Sachetto, Jean-Pierre; Zdrachala, Richard; Rimsa, Stephen; Loomis, Gary; Tatarka, Paul; and Mauzac, Olivier, 5,587,412, Cl. 524-47.000.

Zeafra, Larry A.: See—
McNelis, Niall B.; Doyle, Richard W.; Clark, Dale A.; Zeafra, Larry A.; and McGrath, Thomas P., 5,586,887, Cl. 434-20.000.

Zeffren, Eugene: See—
Dowell, Teresa J.; Newell, Gerald P.; and Zeffren, Eugene, 5,587,154, Cl. 424-70.110.

Zehentbauer, Hans: See—
Rakitsch, Peter; and Zehentbauer, Hans, 5,587,796, Cl. 356-445.000.

Zehring, Raymond E. Power transfer hinge. 5,586,895, Cl. 439-165.000.

Zeise, Christiane; Raehse, Wilfried; Jacobs, Jochen; and Hoffmeister, Jürgen, to Henkel Kommanditgesellschaft auf Aktien. Readily soluble dry concentrates containing ingredients of detergents. 5,587,104, Cl. 510-298.000.

Zellweger Luwa AG: See—
Warnerdam, Petrus, 5,587,695, Cl. 336-84.000.

Zeneca Limited: See—
Burke, Philip J.; Dowell, Robert L.; Mauger, Anthony B.; and Springer, Caroline J., 5,587,161, Cl. 424-178.100.

Zeng, Weiping: See—
Yamamoto, Takashi; Zeng, Weiping; Arata, Masami; Banba, Tsuyoshi; and Tanaka, Harumi, 5,587,406, Cl. 523-116.000.

Zexel Corporation: See—
Furuya, Yuji; and Iino, Kenichi, 5,586,726, Cl. 239-533.120.

ZF Friedrichshafen AB: See—
Bailly, Gerhard; Baasch, Detlef; and Gazykan, Unal, 5,586,470, Cl. 74-477.000.

Zhang, Jie; Dawson, Valina L.; Dawson, Ted M.; and Snyder, Solomon H., to Johns Hopkins University, The; and United States of America, The. Inhibitors of poly(ADP-ribose) synthetase and use thereof to treat NMDA neurotoxicity. 5,587,384, Cl. 514-309.000.

Zheng, Hua: See—
Wright, Jeffrey P.; and Zheng, Hua, 5,587,961, Cl. 365-233.000.

Zhu, Micheal H.: See—
Hicok, Gary D.; Hildebrandt, Eric A.; and Zhu, Micheal H., 5,588,128, Cl. 395-414.000.

Zilog, Inc.: See—
Mandava, Babu S.; and Weddle, E. Eugene, 5,588,118, Cl. 395-200.050.

Zimmer, Inc.: See—
Bonitati, John A.; Case, Kirt L.; Hawkins, Michael E.; and Hoag, Stephen H., 5,586,821, Cl. 366-139.000.

Zimmerman, Jeffrey J.: See—
Sanderson, Thomas; McGinley, Michael J.; Zimmerman, Jeffrey J.; Hill, Howard T.; Meetz, Michael C.; Pirtle, Eugene C.; Swenson, Sabrina L.; and Shibley, George P., 5,587,164, Cl. 424-218.100.

Zimmerman, Ronald A., II; Hofer, John C.; Medvedik, Douglas E.; Veggian, Eric D.; and Lachat, Michael J., to AlliedSignal Inc. Dual pressure side impact air bag. 5,586,782, Cl. 280-730.200.

Zinke, James R., II: See—
Kalahasthy, Gopichand, and Zinke, James R., II, 5,586,792, Cl. 285-319.000.

Zisman, Stan A.: See—
Brown, Scott H.; Zisman, Stan A.; and Kimble, James B., 5,587,348, Cl. 502-230.000.

Zittel, David R. End supported double drum waste water screen. 5,587,073, Cl. 210-372.000.

Zuber, Peter J.: See—
Borsboom, Antonius H.; Gennari, Anthony A.; Rudolph, Kenneth G.; and Zuber, Peter J., 5,586,675, Cl. 220-6.000.

Zuk, Karlene J., to Osram Sylvania, Inc. Translucent polycrystalline alumina. 5,587,346, Cl. 501-152.000.

Zvesky, Viktor V.: See—
Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P.; deceased, 5,587,295, Cl. 435-11.000.

Zyex Limited: See—
McIntosh, Bruce M.; Smith, Francis S.; and Briscoe, Noel A., 5,587,541, Cl. 84-297.005.

Zylka, Karl-Heinz. Two piece interlocking shaft attachment. 5,586,832, Cl. 403-344.000.

Zyouko, Keizo: See—
Kawagoe, Tadashi; and Zyouko, Keizo, 5,587,091, Cl. 219-110.000.

21st Century Containers, Ltd.: See—
Ettore, Steven P.; Lane, Joseph J.; and Vandergniff, Douglas S., 5,586,690, Cl. 222-105.000.

2800001 Canada Inc.: See—
Lopukhin, Jury M.; Zvesky, Viktor V.; Rabovsky, Alexander B.; Andrianova, Irina P.; deceased, 5,587,295, Cl. 435-11.000.

800 Adept, Inc.: See—
Neville, Daniel E., 5,588,048, Cl. 379-127.000.

LIST OF REISSUE PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 24th DAY OF DECEMBER, 1996

NOTE—Arranged in accordance with the first significant character or word of the name
(in accordance with city and telephone directory practice).

Moore, Sidney D. Electrically addressable opto-electronic indicator for making dynamic evaluations of microscopic or larger subjects. Re. 35,409, Cl. 364-525.000.
Patent Development & Investment S.A.: See—

Petruson, Björn. Re. 35,408, Cl. 128-858.000.
Petruson, Björn, to Patent Development & Investment S.A. Nasal devices. Re. 35,408, Cl. 128-858.000.

LIST OF REEXAMINATION PATENTEEES

TO WHOM

CERTIFICATES WERE ISSUED

Anderson, Mark. See—
Ennis, James F., III, and Anderson, Mark, B1 4,981,472, Cl. 604-117.000.
Ennis, James F., III, and Anderson, Mark, to Anderson, Mark. Cannula assembly for syringe. B1 4,981,472, Cl. 604-117.000.
Fenelli, Steven P. See—
Paul, Charles W.; Schultz, Rose A.; and Fenelli, Steven P., B1 5,138,028, Cl. 528-353.000.
Kochloeff, Karl. See—
Schneider, Michael; Maletz, Gerd, and Kochloeff, Karl, B1 5,217,937, Cl. 502-242.000.
Maletz, Gerd. See—
Schneider, Michael; Maletz, Gerd, and Kochloeff, Karl, B1 5,217,937, Cl. 502-242.000.
National Starch and Chemical Investment Holding Corporation. See—

Paul, Charles W.; Schultz, Rose A.; and Fenelli, Steven P., B1 5,138,028, Cl. 528-353.000.
Paul, Charles W.; Schultz, Rose A.; and Fenelli, Steven P., to National Starch and Chemical Investment Holding Corporation. Polyimides end-capped with diaryl substituted acetylene. B1 5,138,028, Cl. 528-353.000.
Schneider, Michael; Maletz, Gerd, and Kochloeff, Karl, to Sud-Chemie Aktiengesellschaft. SiO₂-containing copper oxide-chromium oxide catalyst for the hydrogenation of fatty acids and fatty esters. B1 5,217,937, Cl. 502-242.000.
Schultz, Rose A. See—
Paul, Charles W.; Schultz, Rose A.; and Fenelli, Steven P., B1 5,138,028, Cl. 528-353.000.
Sud-Chemie Aktiengesellschaft. See—
Schneider, Michael; Maletz, Gerd, and Kochloeff, Karl, B1 5,217,937, Cl. 502-242.000.

LIST OF DESIGN PATENTEEES

Abeyta, Monica. Window frame extracting tool. 376,746, Cl. D8-88.000.
Aco, Inc. See—
Asner, David J., 376,723, Cl. D7-359.000.
Adams Mfg. Corp. See—
Adams, William E., 376,756, Cl. D8-382.000.
Adams, William E., to Adams Mfg. Corp. Removable fastener. 376,756, Cl. D8-382.000.
Adidas AG. See—
Gaudin, Paul A., and Malkewitz, Keven C., 376,683, Cl. D2-954.000.
Aiyar, Sanjay. Brush. 376,694, Cl. D4-102.000.
Albert, Barry R. See—
Filowiak, Christine E.; and Albert, Barry R., 376,742, Cl. D8-13.000.
Alberts, John J., III. See—
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
Alden, Martin R.; and McCall, Alexander, to Burroughs Wellcome Co. Pharmaceutical tablet. 376,847, Cl. D24-101.000.
Allen, Don T., to Mapletree Investments. Handrail rim for a spa. 376,852, Cl. D24-104.000.
Arjo, Ltd. See—
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., 376,886, Cl. D34-28.000.
Asai, Tomonari; and Matsumoto, Shinji, to Minolta Co., Ltd. Printer. 376,814, Cl. D18-50.000.
Asano, Shinichi; Miyazaki, Takeo; and Mimura, Shigeo, to Daiwa Seiko, Inc. Fishing reel. 376,835, Cl. D22-140.000.
Avencio, Frankie J., to Network Entertainment Systems, Inc. Speaker enclosure. 376,802, Cl. D14-213.000.
Ashida, Kenichiro, to Nintendo of America, Inc. Game cartridge. 376,795, Cl. D14-121.000.
Ashida, Kenichiro, to Nintendo of America, Inc. Controller for game machine. 376,826, Cl. D21-48.000.
Asner, David J., to Aco, Inc. Pizza serving dish. 376,723, Cl. D7-359.000.
Balestrieri, Harry. See—
Carretta, Michael R.; and Balestrieri, Harry, 376,687, Cl. D3-221.000.
Ball, Robin. See—
Harris, John R., and Ball, Robin, 376,797, Cl. D14-121.000.
Banks, Barry W.; and Riddle, James W. Fish hook with detachable weight. 376,836, Cl. D22-144.000.
Barnes, Blair S., to Gerry Baby Products Company. Baby monitor transmitter. 376,764, Cl. D10-104.000.

Barnes, Blair S., to Gerry Baby Products Company. Baby monitor receiver. 376,765, Cl. D10-104.000.
Baumgarten, Gerd-Diethard, to Heinrich Baumgarten KG Spezialfabrik fuer Beschlagteile. Handle for utensil. 376,727, Cl. D7-395.000.
Beason, Randy G. Tri-level computer center. 376,707, Cl. D6-426.000.
Beattie, Dawn E. See—
Mergenthaler, Steven A.; Beattie, Dawn E.; Jacobs, Paul E.; Heimbigner, Wade L.; Stowers, David C.; and Millman, Mark E., 376,804, Cl. D14-248.000.
Bell, Robert. Bicycle trailer. 376,773, Cl. D12-101.000.
Bellisario, Don. Drink holder. 376,733, Cl. D7-619.000.
Benveniste, Ronald. Cleat fixable to the toe rail of a boat for attaching a spring line. 376,752, Cl. D8-356.000.
Berenbaum, Anna. See—
Leykekhmakher, Benl-Volf; and Berenbaum, Anna, 376,719, Cl. D6-540.000.
Bergeron, Gregory B. See—
Graham, Dennis J.; Bergeron, Gregory B.; and Saddler, Damon R., 376,818, Cl. D19-61.000.
Bess, William W. Golf tee. 376,830, Cl. D21-208.000.
Binzel, Alexander, Jr. Ribbed coaxial welding cable. 376,786, Cl. D13-153.000.
Black & Decker Inc. See—
Carbone, Richard J., 376,862, Cl. D26-43.000.
Gildersleeve, Paul, 376,740, Cl. D8-8.000.
Johnstone, Scott; and Szymanski, Aaron, 376,861, Cl. D26-43.000.
Santastiero, Paul S., 376,860, Cl. D26-43.000.
Stone, Paul A.; Thomas, Rickey J., and McKenna, Chris, 376,809, Cl. D15-139.000.
Box Gacia, Maria, to Inoxrom, S.A. Writing instrument. 376,817, Cl. D19-51.000.
Bonn, Karen L. See—
Brown, Lawrence A., and Bonn, Karen L., 376,851, Cl. D24-190.000.
Bosman, Steven K. Roadside address post. 376,820, Cl. D20-17.000.
Bradfield, Richard D., to Thomas J. Lipton Co., Division of Conopco, Inc. Container. 376,758, Cl. D9-430.000.
Bradfield, Richard D., to Thomas J. Lipton Co., Division of Conopco, Inc. Container. 376,759, Cl. D9-432.000.
Brault, Richard P. See—
Holly, Jeffrey S.; Izov, Andrew L.; Hirsch, Charles A.; Davis, Robert D.; and Brault, Richard P., 376,806, Cl. D15-133.000.
Brodit Plast AB. See—

DECEMBER 24, 1996

LIST OF DESIGN PATENTEEES

PI 83

Johansson, Ebbe, 376,805, Cl. D14-253.000.
Bronzini, Marco N. Hair spray shield. 376,873, Cl. D29-108.000.
Brooks, Mike; Simpson, Edgar H.; Kastner, Theodore A.; and Wurfbain, Diana A., to Rocky Shoes & Boots, Inc. Shoe upper. 376,684, Cl. D2-970.000.
Brown, Arnold. See—
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528.000.
Brown, Lawrence A.; and Bonn, Karen L., to Restorative Medical, Inc. Expander device. 376,851, Cl. D24-190.000.
Brush, Frederick. Chair. 376,700, Cl. D6-334.000.
Bucci, Rocco J. See—
Ferguson, Patrick; and Bucci, Rocco J., 376,750, Cl. D8-354.000.
Buck Knives, Inc. See—
Seber, Brett P.; and Helton, Roy L., Jr., 376,743, Cl. D8-99.000.
Burroughs Wellcome Co. See—
Alden, Martin R.; and McCall, Alexander, 376,847, Cl. D24-101.000.
Burt, Johanna. Kitchen utility rack. 376,704, Cl. D6-396.000.
Caldwell, Peggy. Memorial marker. 376,890, Cl. D99-17.000.
Calfee, Clifford T., to Vu Rytte, Inc. Video display pedestal. 376,787, Cl. D14-114.000.
Canon Business Machines, Inc. See—
Chiba, Toshimi, 376,812, Cl. D18-1.000.
Carbone, Richard J., to Black & Decker Inc. Head for a flashlight. 376,862, Cl. D26-43.000.
Carey, James E.; and Lackey, Jesse. Portable lifting unit. 376,885, Cl. D34-28.000.
Carretta, Michael R.; and Balestrieri, Harry, to M. R. Carretta & Co., Inc. Golf accessory. 376,687, Cl. D3-221.000.
Casio Computer Co., Ltd. See—
Hirasawa, Yukinori, 376,796, Cl. D14-121.000.
Chan, Kam-Hoi, to Go-Gro Industries, Ltd. Clamp-on lamp. 376,865, Cl. D26-60.000.
Chapman, Leonard T., to Leonard Studio Equipment, Inc. Camera crane arm. 376,887, Cl. D34-33.000.
Chen, Kuo-Chang, to Songson Industrial Arts Co., Ltd. Teapot. 376,721, Cl. D7-371.000.
Chen, Li-Su. Ceiling fan housing. 376,845, Cl. D23-411.000.
Cheng, Ching-Hwo. Buckle fastener for in-line skate. 376,771, Cl. D11-216.000.
Chiba, Toshimi, to Canon Business Machines, Inc. Electronic typewriter having a full-size display screen. 376,812, Cl. D18-1.000.
Chodkiewicz, Richard W. Windshield wiper blade. 376,792, Cl. D12-220.000.
Chrysler Corporation. See—
Shikado, Osamu; Slanec, Thomas C.; and Crain, John E., 376,774, Cl. D12-102.000.
Conley, Kristin; Lee, Jerry W.; and Johnson, Craig L., to StairMaster Sports/Medical Products, L.P. Enclosure for an exercise apparatus. 376,828, Cl. D21-191.000.
Cook, Everett W. Tilted drain board. 376,882, Cl. D32-55.000.
Cote, Todd C. See—
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
Cox, Lonnie E. Curtain rod hanger. 376,755, Cl. D8-380.000.
Crain, John E. See—
Shikado, Osamu; Slanec, Thomas C.; and Crain, John E., 376,774, Cl. D12-102.000.
Cranford, Richard; and Jordan, D. Robert. Hand-held personal security device for emitting a chemical spray as well as providing an audible alarm and a light. 376,766, Cl. D10-106.000.
Cretcher, Gary S. Stack chair. 376,702, Cl. D6-379.000.
Daboudet, Martial. Rucksack. 376,686, Cl. D3-217.000.
Daiwa Seiko, Inc. See—
Asano, Shinichi; Miyazaki, Takeo; and Mimura, Shigeo, 376,835, Cl. D22-140.000.
Dallimore, Chris J. Wall mounted planter. 376,714, Cl. D6-556.000.
Davis, Robert D. See—
Holly, Jeffrey S.; Izov, Andrew L.; Hirsch, Charles A.; Davis, Robert D.; and Brault, Richard P., 376,806, Cl. D15-133.000.
Dazey Corporation. See—
Mendelson, Lewis A.; and Talge, Foster L., III, 376,724, Cl. D7-360.000.
DeSimone, Fiorentino. Napkin holder with a movable protection cap. 376,735, Cl. D7-631.000.
DiGiorgio, Tony, to Dominion Plastics Inc. Door jamb. 376,856, Cl. D25-124.000.
DiGiorgio, Tony, to Dominion Plastics Inc. Casement frame. 376,857, Cl. D25-124.000.
DiPaolo, Anthony M.; and Hood, John T. Shopping cart corral. 376,854, Cl. D25-18.000.
Dominion Plastics Inc. See—
DiGiorgio, Tony, 376,856, Cl. D25-124.000.
DiGiorgio, Tony, 376,857, Cl. D25-124.000.
Duppelt, Jerald. Combination chaise cushion and carry bag. 376,689, Cl. D3-274.000.
Dr. Ing. h.c.F. Porsche AG. See—
Ludewig, Thilo; and Wolf, Erhard, 376,781, Cl. D12-406.000.
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., to Arjo, Ltd. Invalid hoist. 376,886, Cl. D34-28.000.
Dunshee, Peter W. See—

Dunshee, Wayne K.; and Dunshee, Peter W., 376,850, Cl. D24-189.000.
Dunshee, Wayne K.; and Dunshee, Peter W., to Minnesota Mining and Manufacturing Company. Adhesive bandage backing. 376,850, Cl. D24-189.000.
Duran, Jesus. Combined remote control and alarm unit. 376,767, Cl. D10-106.000.
Edens, John G.; and Edens, LouAnn S. Garment with detachable bib. 376,679, Cl. D2-733.000.
Edens, LouAnn S. See—
Edens, John G.; and Edens, LouAnn S., 376,679, Cl. D2-733.000.
Educational Insights, Inc. See—
Graham, Dennis J.; Bergeron, Gregory B.; and Saddler, Damon R., 376,818, Cl. D19-61.000.
Eisenblätter, Gerd, to Gerd Eisenblätter GmbH. Support plate. 376,744, Cl. D8-70.000.
Eizen, Yaron. See—
Satran, Amir; and Eizen, Yaron, 376,807, Cl. D15-139.000.
Emery, Robert L., to MicroSpeed, Inc. Cursor control with piston grip. 376,788, Cl. D14-114.000.
Empak, Inc. See—
Gallagher, Gary M.; Wittman, Boyd C.; and Neumann, Edmund B., 376,688, Cl. D3-273.000.
Envirotech Electric, Inc. See—
Wortham, Brent J., 376,843, Cl. D23-382.000.
Erickson, Roy O., Jr. See—
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
Essex, John D., to Hoover Company, The. Vacuum cleaner upper portion. 376,878, Cl. D32-31.000.
Ettelson, Richard L. See—
Hanig, James L.; Ettelson, Richard L.; and Mina, Leung Y., 376,801, Cl. D14-171.000.
Fang, Mu-tung. Decorative bicycle frame shroud. 376,775, Cl. D12-117.000.
Fenton, Russell R.; and Goss, Elmer H., to FWJ Plastics, Inc. Bottle. 376,762, Cl. D9-549.000.
Ferguson, Mark A. See—
Naas, Robert L.; and Ferguson, Mark A., 376,691, Cl. D3-294.000.
Ferguson, Patrick; and Bucci, Rocco J. Gas dispenser prop. 376,750, Cl. D8-354.000.
Few, Jeffrey P., to Norco Industries, Inc. Recreational vehicle pedestal. 376,715, Cl. D6-500.000.
Filowiak, Christine E.; and Albert, Barry R., to True Temper Hardware Company. Tool handle. 376,742, Cl. D8-13.000.
First Years Inc., The. See—
Petrie, Aidan J., 376,734, Cl. D7-629.000.
Fletcher, Taylor C. See—
Flora, Neal P.; Fletcher, Taylor C.; and Lind, Carl E., 376,763, Cl. D10-52.000.
Flora, Neal P.; Fletcher, Taylor C.; and Lind, Carl E., to FSW, Inc. Electronic temperature monitor casing. 376,763, Cl. D10-52.000.
Forsvarets Forskningsinstitut Avdeling for vapen og materiell. See—
Ofstedal, Tor A.; and Halsnes, Odd, 376,722, Cl. D7-332.000.
Franklin, John; Grinbergs, Peter K.; and Miles, Grant W., to Nutech Energy Systems Inc. Heat recovery ventilator. 376,842, Cl. D23-370.000.
Fraquelli, Roberto G. See—
Stoddard, John P.; Fraquelli, Roberto G.; and Lyons, David F., 376,705, Cl. D6-426.000.
FSW, Inc. See—
Flora, Neal P.; Fletcher, Taylor C.; and Lind, Carl E., 376,763, Cl. D10-52.000.
Fujimoto, Hidetoshi. See—
Sato, Keiichiro; and Fujimoto, Hidetoshi, 376,793, Cl. D14-118.000.
Futo, Dennis M. See—
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
FWJ Plastics, Inc. See—
Fenton, Russell R.; and Goss, Elmer H., 376,762, Cl. D9-549.000.
Gallagher, Gary M.; Wittman, Boyd C.; and Neumann, Edmund B., to Empak, Inc. Semiconductor wafer cassette transport box. 376,688, Cl. D3-273.000.
Garrity Industries, Inc. See—
Garrity, Paul G., Sr., 376,859, Cl. D26-37.000.
Garrity, Paul G., Sr., to Garrity Industries, Inc. Flashlight. 376,859, Cl. D26-37.000.
Gaudin, Paul A.; and Malkewitz, Keven C., to Adidas AG. Outsole for an athletic shoe. 376,683, Cl. D2-954.000.
Gebrüder Pletscher AG. See—
Götschi, Beat; and Pletscher, Hans, 376,776, Cl. D12-120.000.
Genmar Industries, Inc. See—
Thompson, Donald P., 376,701, Cl. D6-367.000.
Gerd Eisenblätter GmbH. See—
Eisenblätter, Gerd, 376,744, Cl. D8-70.000.
Gerhart, Mark D. See—
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528.000.
Gerry Baby Products Company. See—
Barnes, Blair S., 376,764, Cl. D10-104.000.
Barnes, Blair S., 376,765, Cl. D10-104.000.
Gildersleeve, Paul, to Black & Decker Inc. Hedge trimmer. 376,740, Cl. D8-8.000.

- Gill, Michael G.: *See—*
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., 376,886, Cl. D34-28,000.
- Glickstein, Todd D.: Pet bed, 376,875, Cl. D30-118,000.
- Gnadt, David F.: *See—*
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528,000.
- Go-Gro Industries, Ltd.: *See—*
Chan, Kam-Hoi, 376,865, Cl. D26-60,000.
- Godee, Joost, and Harden, Daniel, to Proteg Technologies Pte. Ltd., Telephone base, 376,799, Cl. D14-150,000.
- Gonda, Frank E.: *See—*
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528,000.
- Goss, Elmer H.: *See—*
Fenton, Russell R., and Goss, Elmer H., 376,762, Cl. D9-519,000.
- Görschi, Beat, and Pletscher, Hans, to Gebrüder Pletscher AG, Bicycle support, 376,776, Cl. D12-120,000.
- Goulet, Matthew G., and Taylor, Robert E., Computer hand controller, 376,790, Cl. D14-114,000.
- Graham, Dennis J.; Bergeron, Gregory B.; and Saddler, Damon R., to Educational Insights, Inc., Talking globe base, 376,818, Cl. D19-61,000.
- Greaves, John.: *See—*
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., 376,886, Cl. D34-28,000.
- Green, Alexandra R.: *See—*
Green, Carl E.; and Green, Alexandra R., 376,697, Cl. D4-114,000.
- Green, Carl E.; and Green, Alexandra R.: Combined container and applicator, 376,697, Cl. D4-114,000.
- Grinbergs, Peter K.: *See—*
Franklin, John; Grinbergs, Peter K.; and Miles, Grant W., 376,842, Cl. D23-370,000.
- H.O.S. Floral Supply, Inc.: *See—*
Kreidler, Gary L., 376,769, Cl. D11-155,000.
- Haas, Richard G.: *See—*
Kress, Elmer E.; and Haas, Richard G., 376,757, Cl. D9-322,000.
- Hachiro, Tomoyasu.: *See—*
Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, 376,785, Cl. D13-110,000.
- Halsnes, Odd.: *See—*
Ofedal, Tor A.; and Halsnes, Odd., 376,722, Cl. D7-332,000.
- Hanig & Co., Inc.: *See—*
Hanig, James L.; Ettelson, Richard L.; and Mina, Leung Y., 376,801, Cl. D14-171,000.
- Hanig, James L.; Ettelson, Richard L.; and Mina, Leung Y., to Hanig & Co., Inc., Combined miniature boom box and clock radio, 376,801, Cl. D14-171,000.
- Hanscom, Cory J., to Innovative Gaming Corporation of America, Video blackjack table, 376,825, Cl. D21-37,000.
- Hanson, Marvin L.; McCoy, Richard; and Krager, Jon L., to Reese Products, Inc., Flanged receiver mounting bracket, 376,751, Cl. D8-354,000.
- Harden, Daniel.: *See—*
Godee, Joost; and Harden, Daniel, 376,799, Cl. D14-150,000.
- Hardison, Stewart.: Bird feeder, 376,877, Cl. D30-124,000.
- Harris, Charles C., to Victor, Ltd., Table, 376,711, Cl. D6-480,000.
- Harris, John R.; and Hall, Robin.: VCR protector, 376,797, Cl. D14-121,000.
- Hartman, Larry E.: Log carrier, 376,692, Cl. D3-315,000.
- Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, to Yokohama Rubber Co., Ltd., The, Automobile tire, 376,778, Cl. D12-147,000.
- Hathaway, Norman B., to Stainless Image Inc., Combined crowd control and advertising device, 376,821, Cl. D20-41,000.
- Haubert, Harry H.: *See—*
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528,000.
- Haug, Andreas; Schönherr, Tom; and Otsuka, Hiroshi, to King Jim Co., Ltd., Binding device, 376,813, Cl. D18-34,000.
- Haworth, Inc.: *See—*
Nemeth, Steve J., Jr., 376,716, Cl. D6-501,000.
- Stoddard, John P.; Fraquelli, Roberto G.; and Lyons, David F., 376,705, Cl. D6-426,000.
- Hecker, Raymond G.: Cutting board with plastic bag holder, 376,737, Cl. D7-698,000.
- Heimbigner, Wade L.: *See—*
Mergenthaler, Steven A.; Beattie, Dawn E.; Jacobs, Paul E.; Heimbigner, Wade L.; Stowers, David C.; and Millman, Mark E., 376,804, Cl. D14-248,000.
- Heinrich Baumgarten KG Spezialfabrik fuer Beschlagteile.: *See—*
Baumgarten, Gerd-Diethard, 376,727, Cl. D7-395,000.
- Helton, Roy L., Jr.: *See—*
Seber, Brett P.; and Helton, Roy L., Jr., 376,743, Cl. D8-99,000.
- Hertzog, Allen C.; Bracker, 376,749, Cl. D8-349,000.
- Hester, Cindy.: *See—*
Hester, Thomas; Hester, Cindy; Price, Wayne; and Price, Pam, 376,844, Cl. D23-393,000.
- Hester, Thomas; Hester, Cindy; Price, Wayne; and Price, Pam.: Forced air vent, 376,844, Cl. D23-393,000.
- Hillside Plastics, Inc.: *See—*
Kress, Elmer E.; and Haas, Richard G., 376,757, Cl. D9-322,000.
- Hirasawa, Yukinori, to Casio Computer Co., Ltd., Ribbon cassette for a video game machine with seal printer, 376,796, Cl. D14-121,000.
- Hirsch, Charles A.: *See—*
Holly, Jeffrey S.; Itzov, Andrew L.; Hirsch, Charles A.; Davis, Robert D.; and Brault, Richard P., 376,806, Cl. D15-133,000.
- Hodgin, Doyle E., to Inspiration Lures, Inc., Fishing lure, 376,833, Cl. D22-128,000.
- Holly, Jeffrey S.; Itzov, Andrew L.; Hirsch, Charles A.; Davis, Robert D.; and Brault, Richard P., to Milwaukee Electric Tool Corporation, Compound miter saw, 376,806, Cl. D15-133,000.
- Hon Industries Inc.: *See—*
Smith, B.; Cameron, 376,706, Cl. D6-426,000.
- Hoed, John T.: *See—*
DiPaolo, Anthony M.; and Hoed, John T., 376,854, Cl. D25-18,000.
- Hovser Company, The.: *See—*
Essex, John D., 376,878, Cl. D32-31,000.
- Hopkins, Douglas.: *See—*
Livingston, Bryan; Hopkins, Douglas; O'Neil, Harry; and Reilly, Rob., 376,754, Cl. D8-377,000.
- Hsia, Chen-Chia.: Massager, 376,853, Cl. D24-214,000.
- Hung, Tsang-Chung, to Rucy Rsh Enterprise Co., Ltd., Spray gun, 376,839, Cl. D25-226,000.
- Hunt Holdings, Inc.: *See—*
Schreiner, Michael J., 376,791, Cl. D14-114,000.
- Hurst, Dwayne S., and Williams, Charles B., to Palomino Sports, Inc., Drink container, 376,730, Cl. D7-515,000.
- Ichikawa, Makoto, to Modern Royal Co. Ltd., Lighter, 376,870, Cl. D27-157,000.
- Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, to Kabushiki Kaisha Meidensha, Inverter, 376,785, Cl. D13-110,000.
- Ikenaga, Takashi, to Sony Corporation, Magnet optical disc player combined with display monitor, 376,823, Cl. D21-13,000.
- Innovative Gaming Corporation of America.: *See—*
Hanscom, Cory J., 376,825, Cl. D21-37,000.
- Inovcrom, S.A.: *See—*
Boix Gacia, Maria, 376,817, Cl. D19-51,000.
- Inspiration Lures, Inc.: *See—*
Hodgin, Doyle E., 376,833, Cl. D22-128,000.
- INTERLEGO AG.: *See—*
Skov, Ib T., 376,827, Cl. D21-108,000.
- Interlink Electronics, Inc.: *See—*
Tickle, James D., 376,789, Cl. D14-114,000.
- Iscar Ltd.: *See—*
Satran, Amir; and Eizen, Yaron, 376,807, Cl. D15-139,000.
- Itzov, Andrew L.: *See—*
Holly, Jeffrey S.; Itzov, Andrew L.; Hirsch, Charles A.; Davis, Robert D.; and Brault, Richard P., 376,806, Cl. D15-133,000.
- Jackson, Ronald E.: Door security device, 376,747, Cl. D8-330,000.
- Jacobs, Paul E.: *See—*
Mergenthaler, Steven A.; Beattie, Dawn E.; Jacobs, Paul E.; Heimbigner, Wade L.; Stowers, David C.; and Millman, Mark E., 376,804, Cl. D14-248,000.
- Johansson, Ebbe, to Brodit Plast AB, Holder for mobile phone in vehicles, 376,805, Cl. D14-253,000.
- John D. Brush & Co., Inc.: *See—*
Naas, Robert L.; and Ferguson, Mark A., 376,691, Cl. D3-294,000.
- John Manufacturing Limited.: *See—*
Yuen, Se Kit, 376,864, Cl. D26-50,000.
- Yuen, Se Kit, 376,863, Cl. D26-48,000.
- Johnson, Claude P.: Rigid cap, 376,682, Cl. D2-882,000.
- Johnson, Craig L.: *See—*
Conley, Kristin; Lee, Jerry W.; and Johnson, Craig L., 376,828, Cl. D21-191,000.
- Johnstone, Scott, and Szymanski, Aaron, to Black & Decker Inc., Head for a flexible flashlight, 376,861, Cl. D26-43,000.
- Jordan, D. Robert.: *See—*
Cranford, Richard; and Jordan, D. Robert, 376,766, Cl. D10-106,000.
- Juei Chywan Enterprise Co., Ltd.: *See—*
Lin, Rick, 376,731, Cl. D7-536,000.
- Kabushiki Kaisha Meidensha.: *See—*
Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, 376,785, Cl. D13-110,000.
- Kang, Eddy, to Miteo International Ltd., Home pasta maker, 376,725, Cl. D7-376,000.
- Kara, Salim G., to Post N Mail, L.C., Display box, 376,710, Cl. D6-470,000.
- Kastner, Theodore A.: *See—*
Brooks, Mike; Simpson, Edgar H.; Kastner, Theodore A.; and Wurthban, Diana A., 376,684, Cl. D2-970,000.
- Kelso, Francis F.: Adjustable leg, 376,713, Cl. D6-496,000.
- Kim, Jong-Gill.: Juice extractor, 376,736, Cl. D7-665,000.
- Kincart, Mark S.: Extended vehicle brushguard, 376,782, Cl. D12-171,000.
- King, Clifton W.: Chess game board, 376,824, Cl. D21-32,000.
- King Jim Co., Ltd.: *See—*
Haug, Andreas; Schönherr, Tom; and Otsuka, Hiroshi, 376,813, Cl. D18-34,000.
- Klempell, Arthur S., and Wächter, Lori.: Windshield ice scraper, 376,881, Cl. D32-43,000.
- Krager, Jon L.: *See—*
Hanson, Marvin L.; McCoy, Richard; and Krager, Jon L., 376,751, Cl. D8-354,000.
- Kreidler, Gary L., to H.O.S. Floral Supply, Inc., Artificial greenery/floral arrangement device, 376,769, Cl. D11-155,000.

- Kress, Elmer E.; and Haas, Richard G., to Hillside Plastics, Inc., Sugar house syrup container with cap, 376,757, Cl. D9-322,000.
- Kuo, Sue.: Mechanism for inverse exercise, 376,829, Cl. D21-191,000.
- Kuramochi, Izumi.: *See—*
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,778, Cl. D12-147,000.
- Kuwajima, Masatoshi; Takei, Sadakazu; and Suzuki, Toshihiko, to Yokohama Rubber Co., Ltd., The, Automobile tire, 376,779, Cl. D12-147,000.
- Lackey, Jesse.: *See—*
Carey, James E.; and Lackey, Jesse, 376,885, Cl. D34-28,000.
- Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., to Lever Brothers Company, Division of Conopco, Inc., Combined bottle and cap, 376,761, Cl. D9-528,000.
- Lee, Chan-shin.: Chair, 376,703, Cl. D6-380,000.
- Lee, Jerry W.: *See—*
Conley, Kristin; Lee, Jerry W.; and Johnson, Craig L., 376,828, Cl. D21-191,000.
- Lee, Kee-Woon, to Sycom International Corp., Karaoke microphone, 376,803, Cl. D14-228,000.
- Lees, Richard I.: *See—*
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., 376,886, Cl. D34-28,000.
- Leonard Studio Equipment, Inc.: *See—*
Chapman, Leonard T., 376,887, Cl. D34-33,000.
- Leung, Kai H.: Extrusion, 376,855, Cl. D25-124,000.
- Lever Brothers Company, Division of Conopco, Inc.: *See—*
Lathrop, Gregory A.; Gerhart, Mark D.; Gnadt, David F.; Brown, Arnold; Gonda, Frank E.; and Haubert, Harry H., 376,761, Cl. D9-528,000.
- Leykehmakher, Benl-Volf; and Berenbaum, Anna.: Wall-mounted soap dish, 376,719, Cl. D6-540,000.
- Liescher, Robert F.: Shoe attached cleaning implement, 376,880, Cl. D32-35,000.
- Lim, Bong W., to Samsung Electronics Co., Ltd., Facsimile, 376,794, Cl. D14-118,000.
- Lin, Rick, to Juei Chywan Enterprise Co., Ltd., Mug, 376,731, Cl. D7-536,000.
- Lind, Carl E.: *See—*
Flora, Neal P.; Fletcher, Taylor C.; and Lind, Carl E., 376,763, Cl. D10-52,000.
- Livingston, Bryan; Hopkins, Douglas; O'Neil, Harry; and Reilly, Rob.: Reveal track, 376,754, Cl. D8-377,000.
- Lockerby, Andrew J.: Battery storage case having a foam insert for receiving a plurality of different sized batteries, 376,690, Cl. D3-284,000.
- Lowe, Allen.: Pair of false sideburns for sunglasses, 376,811, Cl. D16-341,000.
- Ludewig, Thilo; and Wolf, Erhard, to Dr. Ing. h.c.F. Porsche AG, Roof rack support for a passenger car, 376,781, Cl. D12-406,000.
- Lyons, David F.: *See—*
Stoddard, John P.; Fraquelli, Roberto G.; and Lyons, David F., 376,705, Cl. D6-426,000.
- Lyons, Norbert.: *See—*
Robertson, Edward J.; and Lyons, Norbert, 376,708, Cl. D6-429,000.
- M. R. Carretta & Co., Inc.: *See—*
Carretta, Michael R.; and Balestrieri, Harry, 376,687, Cl. D3-221,000.
- Magalhaes, Manuel C.: Axle brake, 376,783, Cl. D12-180,000.
- Maki, Mary.: Glass with inset hand grip, 376,729, Cl. D7-514,000.
- Makoto, Ichikawa, to Modern Royal Co. Ltd., Lighter, 376,868, Cl. D27-157,000.
- Makoto, Ichikawa, to Modern Royal Co. Ltd., Lighter, 376,869, Cl. D27-157,000.
- Mohrlang, Harry, to Mohrlang Manufacturing, Inc., Yard crane, 376,888, Cl. D34-33,000.
- Mohrlang Manufacturing, Inc.: *See—*
Mohrlang, Harry, 376,888, Cl. D34-33,000.
- Moore, Mark H.: Fish lure, 376,834, Cl. D22-133,000.
- Morrow, Julia A., to Morrow, Julia A.: Blade medallion for a ceiling fan, 376,846, Cl. D23-411,000.
- Naas, Robert L.; and Ferguson, Mark A., to John D. Brush & Co., Inc., Portable security case, 376,691, Cl. D3-294,000.
- Nakamura, Toshinobu, to Shinagawa Shoko Co., Ltd., Foot member, 376,753, Cl. D8-374,000.
- Nemeth, Steve J., Jr., to Haworth, Inc., Chair armrest, 376,716, Cl. D6-501,000.
- Network Entertainment Systems, Inc.: *See—*
Asencio, Frankie J., 376,802, Cl. D14-213,000.
- Neumann, Edmund B.: *See—*
Gallagher, Gary M.; Wittman, Boyd C.; and Neumann, Edmund B., 376,688, Cl. D3-273,000.
- Nintendo of America, Inc.: *See—*
Ashida, Kenichiro, 376,795, Cl. D14-121,000.
- Ashida, Kenichiro, 376,826, Cl. D21-48,000.
- Norco Industries, Inc.: *See—*
Few, Jeffrey P., 376,715, Cl. D6-500,000.
- Nutech Energy Systems Inc.: *See—*
Franklin, John; Grinbergs, Peter K.; and Miles, Grant W., 376,842, Cl. D23-370,000.
- Ofedal, Tor A.; and Halsnes, Odd., to Forsvarets Forskningsinstitut Avdeling for vapo og materiell, Field oven, 376,722, Cl. D7-332,000.
- OGK Hanbai Co. Ltd.: *See—*
Ohie, Yuzuru, 376,810, Cl. D16-326,000.
- Ohie, Yuzuru, to OGK Hanbai Co. Ltd., Frames of sunglasses, 376,810, Cl. D16-326,000.
- Ohio Rack, Inc.: *See—*
Pilla, George F., 376,889, Cl. D34-38,000.
- Olk, Michael E.; and Olk, Ramona T.: Clothespin, 376,883, Cl. D32-61,000.
- Olk, Ramona T.: *See—*
Olk, Michael E.; and Olk, Ramona T., 376,883, Cl. D32-61,000.
- O'Neil, Harry.: *See—*
Livingston, Bryan; Hopkins, Douglas; O'Neil, Harry; and Reilly, Rob., 376,754, Cl. D8-377,000.
- Osterhout, Ralph F., to Tiger Electronics, Inc., Hand-held electronic game housing, 376,822, Cl. D21-13,000.

- Otsuka, Hiroshi: *See—*
Haug, Andreas; Schönherr, Tom; and Otsuka, Hiroshi, 376,813, Cl. D18-34.000.
- Palomino Sports, Inc.: *See—*
Hurst, Dwayne S.; and Williams, Charles B., 376,730, Cl. D7-515.000.
- Pasha Enterprises, Inc.: *See—*
Miller, Dennis W., 376,784, Cl. D12-203.000.
- Peddlicord, Donald B.: *See—*
Peddicord, Steven M.; and Peddicord, Donald B., 376,837, Cl. D23-207.000.
- Peddlicord, Steven M.; and Peddicord, Donald B.: Support for salt for use in a water softener, 376,837, Cl. D23-207.000.
- Perkins, Ernest L.: Refillable toilet tank dispenser, 376,840, Cl. D23-313.000.
- Petrie, Aidan J.; to First Years Inc., The: Baby formula case, 376,734, Cl. D7-629.000.
- Pilla, George F.; to Ohio Rack, Inc.: Design for material handling support rack, 376,889, Cl. D34-38.000.
- Pletscher, Hans: *See—*
Götschi, Beat; and Pletscher, Hans, 376,776, Cl. D12-120.000.
- Post N Mail, L.C.: *See—*
Kara, Salim G., 376,710, Cl. D6-470.000.
- Potts, Elmer; and Potts, Sandra L.: Automobile cleaning wand, 376,838, Cl. D23-223.000.
- Potts, Sandra L.: *See—*
Potts, Elmer; and Potts, Sandra L., 376,838, Cl. D23-223.000.
- Presnell, Donald C.; and Tokash, Robert J.; to Rubbermaid Commercial Products Inc.: Waste container lid, 376,884, Cl. D34-11.000.
- Pribil, Jeffery: *See—*
Zeilig, Avi; and Pribil, Jeffery, 376,848, Cl. D24-111.000.
- Price, Pam: *See—*
Hester, Thomas; Hester, Cindy; Price, Wayne; and Price, Pam, 376,844, Cl. D23-393.000.
- Price, Wayne: *See—*
Hester, Thomas; Hester, Cindy; Price, Wayne; and Price, Pam, 376,844, Cl. D23-393.000.
- Proteg Technologies Pre, Ltd.: *See—*
Godee, Joost; and Harden, Daniel, 376,799, Cl. D14-150.000.
- QUALCOMM Incorporated: *See—*
Mergenthaler, Steven A.; Beattie, Dawn E.; Jacobs, Paul E.; Heimbigner, Wade L.; Stowers, David C.; and Millman, Mark E., 376,804, Cl. D14-248.000.
- Ramsey, Roger H.: *See—*
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
- Ratliff-Wooten, Alice M.: *See—*
Wooten, Frederick A., Jr.; and Ratliff-Wooten, Alice M., 376,891, Cl. D99-31.000.
- Reese Products, Inc.: *See—*
Hanson, Marvin L.; McCoy, Richard; and Krager, Jon L., 376,751, Cl. D8-354.000.
- McCoy, Richard, 376,780, Cl. D12-162.000.
- Regal Ware, Inc.: *See—*
Rohrer, Jeffrey, 376,726, Cl. D7-393.000.
- Reilly, Rob: *See—*
Livingston, Bryan; Hopkins, Douglas; O'Neil, Harry; and Reilly, Rob, 376,754, Cl. D8-377.000.
- Renk, Thomas E.; to Thomson Consumer Electronics, Inc.: Console television, 376,798, Cl. D14-133.000.
- Restorative Medical, Inc.: *See—*
Brown, Lawrence A.; and Bonn, Karen L., 376,851, Cl. D24-190.000.
- Revugan, Harold F.; to Webley & Scott Limited: Pistol, 376,831, Cl. D22-104.000.
- Rexair, Inc.: *See—*
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
- Reyes, Ricardo C., III: Wire bird cage, 376,874, Cl. D30-114.000.
- Reynolds and Reynolds Company, The: *See—*
Sisilli, Jeffrey M., 376,816, Cl. D19-1.000.
- Richards, Emily G.: *See—*
Richards, Theodore N., Sr.; and Richards, Emily G., 376,728, Cl. D7-507.000.
- Richards, Theodore N., Sr.; and Richards, Emily G.: Beverage cup, 376,728, Cl. D7-507.000.
- Riddle, James W.: *See—*
Banks, Barry W.; and Riddle, James W., 376,836, Cl. D22-144.000.
- Riehm, Merry S.: *See—*
Tarfare, Nathaniel S.; and Riehm, Merry S., 376,849, Cl. D24-152.000.
- Riesenman, John P.; and Riesenman, Terri S.: Headwrap with detachable visor, 376,681, Cl. D2-879.000.
- Riesenman, Terri S.: *See—*
Riesenman, John P.; and Riesenman, Terri S., 376,681, Cl. D2-879.000.
- Robertson, Edward J.; and Lyons, Norbert; to Syroco, Inc.: Patio/balcony rail table, 376,708, Cl. D6-429.000.
- Rocky Shoes & Boots, Inc.: *See—*
Brooks, Mike; Simpson, Edgar H.; Kastner, Theodore A.; and Wurfain, Diana A., 376,684, Cl. D2-970.000.
- Rohn, Dean R.: *See—*
Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M., 376,879, Cl. D32-32.000.
- Rohrer, Jeffrey; to Regal Ware, Inc.: Handle for a cooking vessel, 376,726, Cl. D7-393.000.
- Ross, Margaret M.: Dual hole earring, 376,768, Cl. D11-41.000.
- Rubbermaid Commercial Products Inc.: *See—*
Presnell, Donald C.; and Tokash, Robert J., 376,884, Cl. D34-11.000.
- Rubbermaid Incorporated: *See—*
Wolff, Stacy L., 376,693, Cl. D3-323.000.
- Ruey Ryh Enterprise Co., Ltd.: *See—*
Hung, Tsang-Chung, 376,839, Cl. D23-226.000.
- Sabratek Corporation: *See—*
Zeilig, Avi; and Pribil, Jeffery, 376,848, Cl. D24-111.000.
- Saddler, Damon R.: *See—*
Graham, Dennis J.; Bergeron, Gregory B.; and Saddler, Damon R., 376,818, Cl. D19-61.000.
- Sadlowski, Gerald R., Sr.: Mulching attachment for a lawn mower, 376,741, Cl. D8-8.000.
- Sanisung Electronics Co., Ltd.: *See—*
Lim, Bong W., 376,794, Cl. D14-118.000.
- Sanchez, Michael H.; and Sanchez, Rosemary A.: Holder for cigarette lighter, 376,871, Cl. D27-183.000.
- Sanchez, Rosemary A.: *See—*
Sanchez, Michael H.; and Sanchez, Rosemary A., 376,871, Cl. D27-183.000.
- Sangen, Masashi: *See—*
Matsumura, Takeshi; and Sangen, Masashi, 376,858, Cl. D26-26.000.
- Santarsiero, Paul S.; to Black & Decker Inc.: Head for a flashlight, 376,860, Cl. D26-43.000.
- Satoh, Keiichiro; and Fujimoto, Hidetoshi; to Sharp Kabushiki Kaisha: Facsimile machine, 376,793, Cl. D14-118.000.
- Satran, Amir; and Eizen, Yaron; to Iscar Ltd.: Metal slotting cutter, 376,807, Cl. D15-139.000.
- Schönherr, Tom: *See—*
Haug, Andreas; Schönherr, Tom; and Otsuka, Hiroshi, 376,813, Cl. D18-34.000.
- Schreiner, Michael J.; to Hunt Holdings, Inc.: Mouse pad, 376,791, Cl. D14-114.000.
- Scott, Benjamin A.: Hub driving grade rod, 376,745, Cl. D8-75.000.
- Scott, Robert S.: Motion picture light cover, 376,866, Cl. D26-119.000.
- Seber, Brett P.; and Helton, Roy L., Jr.; to Buck Knives, Inc.: Combined folding knife handle and blade segments, 376,743, Cl. D8-99.000.
- Selewski, Steven R.; Alberts, John J., III; Rohn, Dean R.; Cote, Todd C.; Erickson, Roy O., Jr.; Ramsey, Roger H.; Martinez, Robert G.; and Futo, Dennis M.; to Rexair, Inc.: Housing design for a power nozzle, 376,879, Cl. D32-32.000.
- Shakespeare Company: *See—*
Skinner, David B., 376,739, Cl. D8-8.000.
- Sharp Kabushiki Kaisha: *See—*
Satoh, Keiichiro; and Fujimoto, Hidetoshi, 376,793, Cl. D14-118.000.
- Shikado, Osamu; Slanec, Thomas C.; and Crain, John E.; to Chrysler Corporation: Vehicle trailer body, 376,774, Cl. D12-102.000.
- Shinagawa Shoko Co., Ltd.: *See—*
Nakamura, Toshinobu, 376,753, Cl. D8-374.000.
- Shudo, Tomoyuki; to Sony Corporation: Radio receiver, 376,800, Cl. D14-197.000.
- Simpson, Edgar H.: *See—*
Brooks, Mike; Simpson, Edgar H.; Kastner, Theodore A.; and Wurfain, Diana A., 376,684, Cl. D2-970.000.
- Sisilli, Jeffrey M.; to Reynolds and Reynolds Company, The: Business form, 376,816, Cl. D19-1.000.
- Skinner, David B.; to Shakespeare Company: Cutting line for a rotating line trimmer, 376,739, Cl. D8-8.000.
- Skov, Ib T.; to INTERLEGO AG: Toy building element, 376,827, Cl. D21-108.000.
- Slanec, Thomas C.: *See—*
Shikado, Osamu; Slanec, Thomas C.; and Crain, John E., 376,774, Cl. D12-102.000.
- Small, Kevin E.: *See—*
Small, Michael H.; and Small, Kevin E., 376,748, Cl. D8-346.000.
- Small, Michael H.; and Small, Kevin E.: Padlock shackle guard, 376,748, Cl. D8-346.000.
- Smith, B. Cameron; to Hon Industries Inc.: Desk, 376,706, Cl. D6-426.000.
- Smith, Bette E.: Plate with center hot dog compartment, 376,732, Cl. D7-555.000.
- Somerton, Bruce E.: *See—*
Dunn, Robert; Gill, Michael G.; Greaves, John; Lees, Richard I.; and Somerton, Bruce E., 376,886, Cl. D34-28.000.
- Songsong Industrial Arts Co., Ltd.: *See—*
Chen, Kuo-Chang, 376,721, Cl. D7-371.000.
- Sony Corporation: *See—*
Ikenaga, Takashi, 376,823, Cl. D21-13.000.
- Shudo, Tomoyuki, 376,800, Cl. D14-197.000.
- Stainless Image Inc.: *See—*
Hathaway, Norman B., 376,821, Cl. D20-41.000.
- StairMaster Sports/Medical Products, L.P.: *See—*
Conley, Kristin; Lee, Jerry W.; and Johnson, Craig L., 376,828, Cl. D21-191.000.
- Stevens, Clive G.: Dual action walker, 376,777, Cl. D12-130.000.

- Stoddard, John P.; Fraquelli, Roberto G.; and Lyons, David F.; to Haworth, Inc.: Freestanding workstation, 376,705, Cl. D6-426.000.
- Stone, Paul A.; Thomas, Rickey J.; and McKenna, Chris; to Black & Decker Inc.: Spade-type boring bit, 376,809, Cl. D15-139.000.
- Stowers, David C.: *See—*
Mergenthaler, Steven A.; Beattie, Dawn E.; Jacobs, Paul E.; Heimbigner, Wade L.; Stowers, David C.; and Millman, Mark E., 376,804, Cl. D14-248.000.
- Stroud, Robert W.: Seat restraint, 376,872, Cl. D29-101.000.
- Suematsu, Wataru: *See—*
Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, 376,785, Cl. D13-110.000.
- Suzuki, Toshihiko: *See—*
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,778, Cl. D12-147.000.
- Kuwajima, Masatoshi; Takei, Sadakazu; and Suzuki, Toshihiko, 376,779, Cl. D12-147.000.
- Sycom International Corp.: *See—*
Lee, Kee-Woon, 376,803, Cl. D14-228.000.
- Sykes, Donald J.; to Marpac Industries, Inc.: Bottle, 376,760, Cl. D9-500.000.
- Syroco, Inc.: *See—*
Robertson, Edward J.; and Lyons, Norbert, 376,708, Cl. D6-429.000.
- Szymanski, Aaron: *See—*
Johnstone, Scott; and Szymanski, Aaron, 376,861, Cl. D26-43.000.
- Takei, Sadakazu: *See—*
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,778, Cl. D12-147.000.
- Kuwajima, Masatoshi; Takei, Sadakazu; and Suzuki, Toshihiko, 376,779, Cl. D12-147.000.
- Talge, Foster L., III: *See—*
Mendelson, Lewis A.; and Talge, Foster L., III, 376,724, Cl. D7-360.000.
- Tarfare, Nathaniel S.; and Riehm, Merry S.; to Tarfare, Nathaniel S.: Single piece oral cavity cleaning device, 376,849, Cl. D24-152.000.
- Taylor, Robert E.: *See—*
Goulet, Matthew G.; and Taylor, Robert E., 376,790, Cl. D14-114.000.
- Thode, Monique J.: *See—*
Thode, Wayne P.; and Thode, Monique J., 376,720, Cl. D6-603.000.
- Thode, Wayne P.; and Thode, Monique J.: Comforter having separable halves, 376,720, Cl. D6-603.000.
- Thomas J. Lipton Co., Division of Conopco, Inc.: *See—*
Bradfield, Richard D., 376,758, Cl. D9-430.000.
- Bradfield, Richard D., 376,759, Cl. D9-432.000.
- Thomas, Rickey J.: *See—*
Stone, Paul A.; Thomas, Rickey J.; and McKenna, Chris, 376,809, Cl. D15-139.000.
- Thompson, Donald P.; to Genmar Industries, Inc.: Rotational bolster seat, 376,701, Cl. D6-367.000.
- Thomson Consumer Electronics, Inc.: *See—*
Renk, Thomas E., 376,798, Cl. D14-133.000.
- Tickle, James D.; to Interlink Electronics, Inc.: Electronic control device, 376,789, Cl. D14-114.000.
- Tiger Electronics, Inc.: *See—*
Osterhout, Ralph F., 376,822, Cl. D21-13.000.
- Tokash, Robert J.: *See—*
Presnell, Donald C.; and Tokash, Robert J., 376,884, Cl. D34-11.000.
- Tokizaki, Hiroshi: *See—*
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,778, Cl. D12-147.000.
- True Temper Hardware Company: *See—*
Filowiak, Christine E.; and Albert, Barry R., 376,742, Cl. D8-13.000.
- Tsao, Frank: Mailbox with a hurricane lamp, 376,892, Cl. D99-31.000.
- Tveras, Rimvydas; to Tveras, Rimvydas: Handle for a toothbrush and tongue cleaner, 376,695, Cl. D4-104.000.
- Unicell Limited: *See—*
Martin, Roger, 376,772, Cl. D12-96.000.
- Vasquez, Michelle: Gift package ornament, 376,770, Cl. D11-184.000.
- Vermillion, James H.: Insert, 376,815, Cl. D8-354.000.
- Vicrus, Ltd.: *See—*
Harris, Charles C., 376,711, Cl. D6-480.000.
- Vogel, William T., Jr.: Tooth brush with removable head, 376,696, Cl. D4-104.000.
- Volpati, Luigi: Long pants, 376,680, Cl. D2-742.000.
- Von Obenauer, William E.: Toilet seat, 376,841, Cl. D23-311.000.
- Vu Rye, Inc.: *See—*
Calfee, Clifford T., 376,787, Cl. D14-114.000.
- Wachler, Lori: *See—*
Kleinpell, Arthur S.; and Wachler, Lori, 376,881, Cl. D32-43.000.
- Wang, Paul S.: Lunch box, 376,738, Cl. D7-709.000.
- Webley & Scott Limited: *See—*
Resuggan, Harold F., 376,831, Cl. D22-104.000.
- Weller, Helen L.: *See—*
Weller, Laurence A.; and Weller, Helen L., 376,685, Cl. D3-203.000.
- Weller, Laurence A.; and Weller, Helen L.: Painted glass pill container with attachable mounting plate, 376,685, Cl. D3-203.000.
- Wilcox, Kimberly A.: Bandage dispenser, 376,718, Cl. D6-518.000.
- Wilhelm Renz GmbH & Co.: *See—*
Mezger, Wolfgang C. R., 376,712, Cl. D6-487.000.
- Williams, Charles B.: *See—*
Hurst, Dwayne S.; and Williams, Charles B., 376,730, Cl. D7-515.000.
- Wittman, Boyd C.: *See—*
Gallagher, Gary M.; Wittman, Boyd C.; and Neumann, Edmund B., 376,688, Cl. D3-273.000.
- Wolf, Erhard: *See—*
Ludewig, Thilo; and Wolf, Erhard, 376,781, Cl. D12-406.000.
- Wolff, Stacy L.; to Rubbermaid Incorporated: Storage container lid, 376,693, Cl. D3-323.000.
- Wood, Sharon A.: Clothes hanger, 376,699, Cl. D6-318.000.
- Wooten, Frederick A., Jr.; and Ratliff-Wooten, Alice M.: Mailbox caddy, 376,891, Cl. D99-31.000.
- Wortham, Brent J.; to Envirotech Electric, Inc.: Table/desk fan, 376,843, Cl. D23-382.000.
- Wurfain, Diana A.: *See—*
Brooks, Mike; Simpson, Edgar H.; Kastner, Theodore A.; and Wurfain, Diana A., 376,684, Cl. D2-970.000.
- Yamaguchi, Tsunehisa: *See—*
Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, 376,785, Cl. D13-110.000.
- Yan, San-Jhy: Lamp shade, 376,867, Cl. D26-127.000.
- Yokohama Rubber Co., Ltd., The: *See—*
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,778, Cl. D12-147.000.
- Kuwajima, Masatoshi; Takei, Sadakazu; and Suzuki, Toshihiko, 376,779, Cl. D12-147.000.
- Yoshihara, Masatake: *See—*
Ikeda, Kumiko; Yamaguchi, Tsunehisa; Suematsu, Wataru; Yoshihara, Masatake; and Hachiro, Tomoyasu, 376,785, Cl. D13-110.000.
- Yuen, Se K.; to John Manufacturing Limited: Multi-functional lantern, 376,864, Cl. D26-50.000.
- Yuen, Se Kit; to John Manufacturing Limited: Weather proof lantern, 376,863, Cl. D26-48.000.
- Zeilig, Avi; and Pribil, Jeffery; to Sabratek Corporation: Infusion pump cassette, 376,848, Cl. D24-111.000.

LIST OF PLANT PATENTEEES

Dummen, Günter, to Dummen Jungpflanzenkulturen. Geranium plant named 'HWD Ravelina'. 9,767, Cl. Plt.-87.120.
 Dummen Jungpflanzenkulturen: See—
 Dummen, Günter, 9,767, Cl. Plt.-87.120.
 Haring, Gabriele, 9,766, Cl. Plt.-87.120.
 Floris AG: See—
 Utecht, Angelika, 9,761, Cl. Plt.-87.120.
 Utecht, Angelika, 9,762, Cl. Plt.-87.120.
 Utecht, Angelika, 9,763, Cl. Plt.-87.120.
 Utecht, Angelika, 9,764, Cl. Plt.-87.120.
 Utecht, Angelika, 9,765, Cl. Plt.-87.120.
 Haring, Gabriele, to Dummen Jungpflanzenkulturen. Geranium plant named 'HWD Corelli'. 9,766, Cl. Plt.-87.120.
 Lopez, Jose M. A., to Plantas de Navarra, S.A. Strawberry plant named 'Aires'. 9,757, Cl. Plt.-49.000.
 Messick Company: See—
 Sapia, Flavio, 9,758, Cl. Plt.-70.700.
 Sapia, Flavio, 9,759, Cl. Plt.-70.700.
 Plantas de Navarra, S.A.: See—
 Lopez, Jose M. A., 9,757, Cl. Plt.-49.000.

Sapia, Flavio, to Messick Company. Carnation plant named 'Velvet'. 9,758, Cl. Plt.-70.700.
 Sapia, Flavio, to Messick Company. Carnation plant named 'Paco'. 9,759, Cl. Plt.-70.700.
 Shiigi, David R. Guzman. 'Puna Gold'. 9,768, Cl. Plt.-88.800.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisalb'. 9,761, Cl. Plt.-87.120.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisbraris'. 9,762, Cl. Plt.-87.120.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisvideo'. 9,763, Cl. Plt.-87.120.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisblu'. 9,764, Cl. Plt.-87.120.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisbravo'. 9,765, Cl. Plt.-87.120.
 VandenBerg, Cornelis P., to Yoder Brothers, Inc. Chrysanthemum plant named 'Peach Cinderella'. 9,760, Cl. Plt.-78.000.
 Yoder Brothers, Inc.: See—
 VandenBerg, Cornelis P., 9,760, Cl. Plt.-78.000.

CLASSIFICATION OF PATENTS

ISSUED DECEMBER 24, 1996

NOTE—First number, class; second number, subclass; third number, patent number

46	CLASS 2	5,586,339	114	CLASS 36	5,586,398	12 02	CLASS 68	5,586,455	26	CLASS 96	5,587,005	90 15	5,586,527	CLASS 144	
67		5,586,340				18 R		5,586,456		CLASS 99		90 51	5,586,528		
239		5,586,341	351	CLASS 37	5,586,399		CLASS 70		287	5,586,484		90 65	5,586,529	CLASS 148	
	CLASS 4			CLASS 38		201	5,586,457		295	5,586,485		188.8	5,586,530	101	5,587,024
368		5,586,342		102.2	5,586,400	208	5,586,458		330	5,586,486		320	5,586,531	274	5,587,025
480		5,586,343				224	5,586,459		331	5,586,487		321	5,586,532	313	5,587,026
484		5,586,344		CLASS 40			CLASS 72		419	5,586,488		325	5,586,533	320	5,587,027
	CLASS 5		737	5,586,401		56	5,586,460		421 R	5,586,490		352	5,586,534	403	5,587,028
99 1		5,586,345		CLASS 43		137	5,586,461		450	5,586,491		435	5,586,535	438	5,587,029
614		5,586,349		17	5,586,402	150	5,586,462		516	5,586,492		446	5,586,536		
636		5,586,350		17.5	5,586,403	405 16	5,586,464					458	5,586,537	CLASS 149	
655		5,586,351		21.2	5,586,404	319	5,586,466		34	5,586,493		559.1	5,586,538	19.5	5,587,552
662		5,586,352		42.31	5,586,405		CLASS 73		189	5,586,494		574	5,586,539	19.6	5,587,553
710		5,586,346		55	5,586,406	1 D	5,587,518		207	5,586,495		609	5,586,540	CLASS 152	
713		5,586,347		137	5,586,407	1 G	5,587,519					684	5,586,541	555	5,587,030
	CLASS 8			CLASS 47		15.52	5,587,520		CLASS 101		73	5,586,545		CLASS 156	
653		5,586,392		1.01	5,586,408	25.03	5,587,521		93.04	5,586,496			64	5,587,032	
	CLASS 12			41.01	5,586,409	49 1	5,587,522		127	5,586,497		CLASS 126	148	5,587,031	
142 LC		5,586,353		55	5,586,410	54 28	5,587,523		128.4	5,586,498		42	5,586,546	164	5,587,033
146 BR		5,586,354		57.6	5,586,411	105	5,587,524		211	5,586,499		351	5,586,547	166	5,587,034
	CLASS 14			58	5,586,412	116	5,587,525		327	5,586,500		565	5,586,548	219	5,587,036
69 5		5,586,355		67	5,586,413	319	5,587,526		217	5,587,550		635	5,586,549	231	5,587,037
71.1		5,586,356		CLASS 52		382 G	5,587,527							345	5,587,038
	CLASS 15			57	5,586,414	439	5,587,528		CLASS 104		200.16	5,586,550		394.1	5,587,040
111		5,586,357		58	5,586,415	462	5,587,529		17.2	5,586,502		203.29	5,586,551	441	5,587,041
334		5,586,358		169 5	5,586,416	504 13	5,587,531		241	5,586,503		633	5,586,552	477.1	5,587,042
339		5,586,359		295	5,586,417	514.12	5,587,532		292	5,586,504		635	5,586,553	506	5,587,043
410		5,586,360		450	5,586,418	514.23	5,587,533		283	5,586,505		653.1	5,586,554	577	5,587,044
	CLASS 16			514.5	5,586,420	579	5,587,534		368	5,586,506		672	5,586,555	627.1	5,587,045
51		5,586,361		529	5,586,422	623	5,587,535					697	5,586,556	662.1	5,587,046
193		5,586,362		653.2	5,586,423	726	5,587,536		CLASS 105		779	5,586,557		CLASS 159	
342		5,586,363		CLASS 53		744	5,587,537		215 2	5,586,506		781	5,586,558	47.300	5,587,047
383		5,586,364		138 2	5,586,424	862.392	5,587,538		105	5,587,006		782	5,586,559	CLASS 160	
	CLASS 19			449	5,586,425	863.33	5,587,539		23	5,587,007		845	5,586,560	133	5,586,592
105		5,586,365		CLASS 55		863.52	5,587,540		38.51	5,587,008		846	5,586,561	135	5,586,593
		5,586,366		227	5,586,426	864.44	5,587,541		244	5,587,009		848	5,586,562	330	5,586,594
68 SK		5,586,367		321	5,586,427	57	5,586,467		287.17	5,587,010		849	5,586,563	CLASS 162	
390		5,586,368		361	5,586,428	89.15	5,586,468		416	5,587,011		858	5,586,564	7	5,587,048
392		5,586,369		391	5,586,429	459	5,586,469		823	5,587,012		898	5,586,565	40	5,587,049
433		5,586,370		CLASS 56		477	5,586,470							198	5,587,051
452		5,586,371		327.1	5,586,426	572	5,586,471		CLASS 108		84.2	5,586,566		273	5,587,052
	CLASS 24			367	5,586,421	594 1	5,586,472		2	5,586,508		200	5,586,566	CLASS 164	
525		5,586,373		CLASS 57					28	5,586,509				253	5,586,596
599.8		5,586,374		264	5,586,427				345	5,586,510				487	5,586,597
716		5,586,375		269	5,586,428									CLASS 165	
	CLASS 27			39 07	5,586,429				CLASS 110		1	5,587,021		133	5,586,598
27		5,586,376		39.511	5,586,430				CLASS 112		26	5,587,022		143	5,586,599
	CLASS 29			226.1	5,586,431				CLASS 114		32	5,587,023		173	5,586,600
91 5		5,586,377		274	5,586,432				65 R	5,586,512		57 D	5,586,567	CLASS 166	
257		5,586,378		345	5,586,433				74 A	5,586,513				212	5,586,601
401 1		5,586,379		416	5,586,434				230	5,586,514				249	5,586,602
413		5,586,380		585	5,586,435				255	5,586,515				CLASS 172	
434		5,586,381		CLASS 62					362	5,586,516				21	5,586,603
560		5,586,382		47.1	5,586,437				CLASS 116		359	5,586,572		CLASS 173	
596		5,586,383		78	5,586,438				173	5,586,517		487.5	5,586,574	4	5,586,605
		5,586,384		87	5,586,439							488	5,586,575	62	5,586,606
603 16		5,586,385		99	5,586,441				CLASS 117		596 13	5,586,576		117	5,586,607
622		5,586,386		107	5,586,442				89	5,587,013		596 18	5,586,577		
623.2		5,586,387		115	5,586,443				200	5,587,014		614 17	5,586,578		
623.5		5,586,388		117	5,586,444				214	5,587,015			5,586,579		
703		5,586,389		126	5,586,445									CLASS 174	
830		5,586,390		141	5,586,446				CLASS 118		98	5,586,580		37	5,587,554
841		5,586,391		156	5,586,447				424	5,587,017				49	5,587,555
896 411		5,586,392		179	5,586,448				661	5,587,018				74 R	5,587,556
897.2		5,586,393		192	5,586,449				679	5,587,019				266	5,587,557
	CLASS 30			646	5,586,451				725	5,587,020				CLASS 175	
318		5,586,392		CLASS 63					CLASS 119		123.5	5,586,584		40	5,586,608
	CLASS 33			19	5,586,452				14 51	5,586,518				65	5,586,609
288		5,586,393		CLASS 65					705	5,586,519				195	5,586,610
394		5,586,394		134 3	5,586,453				858	5,586,521				353	5,586,612
471		5,586,395		261	5,587,000									369	5,586,611
	CLASS 34			CLASS 66					CLASS 123		21	5,586,629		CLASS 178	
59		5,586,396		148	5,586,453				41 82 R	5,586,522		93	5,586,583	18	5,587,558
114		5,586,397		193	5,586,454				65 VB	5,586,523		98	5,586,584		5,587,559
									73 A	5,586,524		196	5,586,585		5,587,560
									73 B	5,586,525		285	5,586,586		
									90.12	5,586,526		386	5,586,587		
													5,586,588		
													5,586,589		
													5,586,590		
														CLASS 180	
														65 2	5,586,613

190	5,586,614	CLASS 181	104	5,587,065	631	5,586,705	514	5,587,111	CLASS 285	556	5,587,661	
			130	5,587,066	671	5,586,706	589	5,587,112	38	5,586,789	713	5,587,662
			155	5,587,067					89	5,586,790	727	5,587,663
131	5,587,561		164	5,587,069	CLASS 226	134.3	SC	5,586,750	179	5,586,791	752	5,587,664
167	5,587,562		188	5,587,069	172	5,586,708	352	5,586,751	319	5,586,792	CLASS 326	
224	5,587,563		192	5,587,070	177	5,586,709	372	5,586,752			16	5,587,665
295	5,587,564		202	5,587,071	CLASS 227				67	5,586,793	17	5,587,666
			232	5,587,072	155	5,586,710	32	5,586,753	252	5,586,794	16	5,587,667
48	5,586,615		372	5,587,073	176.1	5,586,711			336.3	5,586,795	36	5,587,668
222	5,586,616		411	5,587,074	CLASS 228				346	5,586,796	39	5,587,671
238	5,586,617			5,587,075	CLASS 228	10	5,587,588	CLASS 294			83	5,587,672
			461	5,587,076	5.7	5,586,712	40	5,587,589	1.1	5,586,801	93	5,587,673
			498	5,587,077	102	5,586,713	48	5,587,590				
14	5,586,618		512.1	5,587,078	122.1	5,586,714	59	5,587,591	CLASS 296			
			603	5,587,079	248.1	5,586,715	94	5,587,593	26	5,586,802	67	5,587,674
				5,587,080	CLASS 229				146.15	5,586,798	99	5,587,675
226	5,586,619			5,587,081	110	5,586,716	138	5,587,594	26	5,586,803	108	5,587,676
227	5,586,620			5,587,082	116.1	5,586,717	141	5,587,595	146.6	5,586,799		5,587,677
316	5,587,565		635	5,587,083			223	5,587,596	203			5,587,678
	5,587,566		652	5,587,084	CLASS 232							5,587,679
395	5,587,567		691	5,587,085	17	5,586,718	351	5,587,597	CLASS 297			170
			711	5,587,086			355	5,587,598	158.3	5,586,803	291	5,587,680
4 R	5,586,621		724	5,587,087	CLASS 235				188.08	5,586,804	307	5,587,681
20	5,586,622		729	5,587,088	98 R	5,587,572	370	5,587,599	188.09	5,586,805	358	5,587,682
72.6	5,586,623				380	5,587,573	391	5,587,600				5,587,683
164	5,586,624					5,587,574	417	5,587,601	188.11	5,586,806	546	5,587,684
218 R	5,586,625		58	5,586,664	384	5,587,575	458	5,587,611	218.5	5,586,807	552	5,587,685
250 B	5,586,626		59.2	5,586,665	462	5,587,576	506	5,587,612	247	5,586,808	580	5,587,686
299	5,586,627		175	5,586,666	472	5,587,577	530	5,587,613	353	5,586,809		
					492	5,587,578	666	5,587,614			CLASS 330	
							670	5,587,605	411.36	5,586,810	253	5,587,687
							690	5,587,606			254	5,587,688
							712	5,587,608	CLASS 303			
							744	5,587,609	7	5,586,812		
							758	5,587,610	22.4	5,586,813	CLASS 331	
									116.2	5,586,814	2	5,587,690
									143	5,586,815	44	5,587,691
											CLASS 333	
											12	5,587,692

14	5,587,735	717	5,587,844	152	5,588,019	CLASS 374	214	5,588,089	216	5,586,838	65	5,587,736	819	5,587,845	259.1	5,586,839	208	5,587,737	824	5,587,846	267	5,586,840	302	5,587,738	890	5,587,847	272	5,586,841	347	5,587,739	724.16	5,587,937	286	5,586,842	373	5,587,740	44	5,588,824	29.14	5,586,843	416	5,587,741	158	5,587,943	211	5,588,021	5,588,094	42	5,587,742	175	5,587,944	216	5,588,022	5,588,095	473	5,587,743	185.02	5,587,945	238	5,588,023	5,588,096	556	5,587,744	185.1	5,587,946	242	5,588,024	5,588,097	626	5,587,745	185.17	5,587,947	316	5,588,025	5,588,098	708	5,587,746	185.24	5,587,948	329	5,588,026	5,588,099	CLASS 349	62	5,587,816	97.01	5,587,855	201	5,587,950	330	5,588,027	5,588,100	106	5,587,818	99.02	5,587,856	203	5,587,951	341	5,588,028	5,588,101	118	5,587,819	103	5,587,857	207	5,587,952	364	5,588,029	5,588,111	124	5,587,821	108	5,587,858	220	5,587,953	187	5,587,817	133	5,587,859	221	5,587,954	368	5,588,030	5,588,112	CLASS 351	14	5,587,861	230.03	5,587,960	287	5,588,031	5,588,113	CLASS 353	105	5,587,747	230.06	5,587,958	4	5,588,033	5,588,114	208	5,587,748	44	5,587,865	230.09	5,587,959	8	5,588,034	5,588,115	CLASS 352	90	5,587,749	233	5,587,966	287	5,588,035	5,588,116	184	5,587,750	118	5,587,866	236	5,587,967	187	5,588,036	5,588,117	CLASS 355	27	5,587,767	238.5	5,587,968	4	5,588,037	5,588,118	41	5,587,768	663	5,587,873	247	5,587,969	8	5,588,038	5,588,119	200	5,587,769	680	5,587,874	274	5,587,970	100	5,588,039	5,588,120	208	5,587,770	682	5,587,875	274	5,587,971	59	5,588,040	5,588,121	210	5,587,771	685	5,587,876	274	5,587,972	59	5,588,041	5,588,122	219	5,587,772	687	5,587,877	274	5,587,973	59	5,588,042	5,588,123	245	5,587,773	695	5,587,878	274	5,587,974	59	5,588,043	5,588,124	246	5,587,774	705	5,587,879	274	5,587,975	59	5,588,044	5,588,125	271	5,587,775	705	5,587,880	274	5,587,976	59	5,588,045	5,588,126	274	5,587,776	705	5,587,881	274	5,587,977	59	5,588,046	5,588,127	301	5,587,777	723	5,587,882	274	5,587,978	59	5,588,047	5,588,128	301	5,587,778	723	5,587,883	274	5,587,979	59	5,588,048	5,588,129	301	5,587,779	723	5,587,884	274	5,587,980	59	5,588,049	5,588,130	301	5,587,780	723	5,587,885	274	5,587,981	59
----	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-----	-----------	----	-----------	-----	-----------	-------	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	--------	-----------	-----	-----------	-----	-----------	----	-----------	-------	-----------	-----	-----------	-----	-----------	-----	-----------	-----------	----	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	--------	-----------	-----	-----------	-----------	-----	-----------	-------	-----------	-----	-----------	-----------	-----	-----------	--------	-----------	-----	-----------	-----------	-----	-----------	--------	-----------	-----	-----------	-----------	-----------	----	-----------	-------	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-------	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----------	-----------	----	-----------	--------	-----------	-----	-----------	-----------	-----------	-----	-----------	--------	-----------	---	-----------	-----------	-----	-----------	----	-----------	--------	-----------	---	-----------	-----------	-----------	----	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----------	-----------	----	-----------	-------	-----------	---	-----------	-----------	----	-----------	-----	-----------	-----	-----------	---	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	-----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----	-----------	-----------	-----	-----------	-----	-----------	-----	-----------	----

255.1	5,587,166	228	5,587,258	43	5,587,331	CLASS 474	CLASS 522	310	5,587,480
401	5,587,168	233	5,587,259	49	5,587,332	CLASS 475	CLASS 523	CLASS 546	
	5,587,169			129	5,587,333	CLASS 476	CLASS 524	CLASS 547	
	5,587,170	7	5,587,260	183	5,587,334	CLASS 477	CLASS 525	CLASS 548	
	5,587,171	18	5,587,261	195	5,587,335	CLASS 478	CLASS 526	CLASS 549	
427	5,587,172	54	5,587,262	186	5,587,336	CLASS 479	CLASS 527	CLASS 550	
443	5,587,173	56	5,587,263	195	5,587,337	CLASS 480	CLASS 528	CLASS 551	
454	5,587,174	57	5,587,264	203	5,587,338	CLASS 481	CLASS 529	CLASS 552	
464	5,587,175	109	5,587,265	206	5,587,339	CLASS 482	CLASS 530	CLASS 553	
466	5,587,176	133	5,587,266	209	5,587,340	CLASS 483	CLASS 531	CLASS 554	
499	5,587,177	168	5,587,267	228	5,587,341	CLASS 484	CLASS 532	CLASS 555	
	5,587,178	200	5,587,268	238	5,587,342	CLASS 485	CLASS 533	CLASS 556	
	5,587,179	203	5,587,269	238	5,587,343	CLASS 486	CLASS 534	CLASS 557	
	5,587,180		5,587,270		5,587,344	CLASS 487	CLASS 535	CLASS 558	
		204	5,587,271			CLASS 488	CLASS 536	CLASS 559	
3	5,587,181	257	5,587,272	66	5,587,345	CLASS 489	CLASS 537	CLASS 560	
4 C	5,587,182	269	5,587,273	71	5,587,346	CLASS 490	CLASS 538	CLASS 561	
4 R	5,587,183	270.1	5,587,274	91	5,587,347	CLASS 491	CLASS 539	CLASS 562	
133.5	5,587,184	283.1	5,587,275	108	5,587,348	CLASS 492	CLASS 540	CLASS 563	
229	5,587,185	440	5,587,276	157	5,587,349	CLASS 493	CLASS 541	CLASS 564	
310	5,587,186	458	5,587,277	165	5,587,350	CLASS 494	CLASS 542	CLASS 565	
409	5,587,187	533	5,587,278	218	5,587,351	CLASS 495	CLASS 543	CLASS 566	
549	5,587,188	567	5,587,279	271	5,587,352	CLASS 496	CLASS 544	CLASS 567	
577	5,587,189		5,587,280	287	5,587,353	CLASS 497	CLASS 545	CLASS 568	
		637	5,587,281	300	5,587,354	CLASS 498	CLASS 546	CLASS 569	
			5,587,282	310	5,587,355	CLASS 499	CLASS 547	CLASS 570	
2	5,587,190		5,587,283	342	5,587,356	CLASS 500	CLASS 548	CLASS 571	
66	5,587,191		5,587,284	352	5,587,357	CLASS 501	CLASS 549	CLASS 572	
118	5,587,192	10	5,587,285	419	5,587,358	CLASS 502	CLASS 550	CLASS 573	
448	5,587,193	115	5,587,286	463	5,587,359	CLASS 503	CLASS 551	CLASS 574	
521	5,587,194	351	5,587,287	483	5,587,360	CLASS 504	CLASS 552	CLASS 575	
607	5,587,195		5,587,288	511	5,587,361	CLASS 505	CLASS 553	CLASS 576	
611	5,587,196		5,587,289	559	5,587,362	CLASS 506	CLASS 554	CLASS 577	
658	5,587,197	241	5,587,290	584	5,587,363	CLASS 507	CLASS 555	CLASS 578	
660	5,587,198		5,587,291	607	5,587,364	CLASS 508	CLASS 556	CLASS 579	
			5,587,292	620	5,587,365	CLASS 509	CLASS 557	CLASS 580	
2.12	5,587,199	3	5,587,293	638	5,587,366	CLASS 510	CLASS 558	CLASS 581	
2.24	5,587,200	13	5,587,294	676	5,587,367	CLASS 511	CLASS 559	CLASS 582	
64	5,587,201	39	5,587,295	731.1	5,587,368	CLASS 512	CLASS 560	CLASS 583	
155	5,587,202	60	5,587,296	752	5,587,369	CLASS 513	CLASS 561	CLASS 584	
228	5,587,203	72	5,587,297	752	5,587,370	CLASS 514	CLASS 562	CLASS 585	
411	5,587,204	102	5,587,298	752	5,587,371	CLASS 515	CLASS 563	CLASS 586	
503	5,587,205	224	5,587,299	752	5,587,372	CLASS 516	CLASS 564	CLASS 587	
	5,587,206		5,587,300		5,587,373	CLASS 517	CLASS 565	CLASS 588	
523	5,587,207		5,587,301		5,587,374	CLASS 518	CLASS 566	CLASS 589	
553	5,587,208	20	5,587,302		5,587,375	CLASS 519	CLASS 567	CLASS 590	
558	5,587,209	258	5,587,303		5,587,376	CLASS 520	CLASS 568	CLASS 591	
571	5,587,210	327	5,587,304		5,587,377	CLASS 521	CLASS 569	CLASS 592	
	5,587,211		5,587,305		5,587,378	CLASS 522	CLASS 570	CLASS 593	
1	5,587,212	5	5,587,306		5,587,379	CLASS 523	CLASS 571	CLASS 594	
12	5,587,213	6	5,587,307		5,587,380	CLASS 524	CLASS 572	CLASS 595	
34.5	5,587,214		5,587,308		5,587,381	CLASS 525	CLASS 573	CLASS 596	
40.1	5,587,215		5,587,309		5,587,382	CLASS 526	CLASS 574	CLASS 597	
64.4	5,587,216	7.21	5,587,310		5,587,383	CLASS 527	CLASS 575	CLASS 598	
65.4	5,587,217	7.4	5,587,311		5,587,384	CLASS 528	CLASS 576	CLASS 599	
67	5,587,218	7.9	5,587,312		5,587,385	CLASS 529	CLASS 577	CLASS 600	
68	5,587,219	7.93	5,587,313		5,587,386	CLASS 530	CLASS 578	CLASS 601	
71	5,587,220	11	5,587,314		5,587,387	CLASS 531	CLASS 579	CLASS 602	
96	5,587,221	14	5,587,315		5,587,388	CLASS 532	CLASS 580	CLASS 603	
192	5,587,222	29	5,587,316		5,587,389	CLASS 533	CLASS 581	CLASS 604	
195	5,587,223	41	5,587,317		5,587,390	CLASS 534	CLASS 582	CLASS 605	
	5,587,224	69.1	5,587,318		5,587,391	CLASS 535	CLASS 583	CLASS 606	
198	5,587,225		5,587,319		5,587,392	CLASS 536	CLASS 584	CLASS 607	
210	5,587,226		5,587,320		5,587,393	CLASS 537	CLASS 585	CLASS 608	
217	5,587,227	69.5	5,587,321		5,587,394	CLASS 538	CLASS 586	CLASS 609	
224	5,587,228	116	5,587,322		5,587,395	CLASS 539	CLASS 587	CLASS 610	
245	5,587,229	139	5,587,323		5,587,396	CLASS 540	CLASS 588	CLASS 611	
283	5,587,230	172.1	5,587,324		5,587,397	CLASS 541	CLASS 589	CLASS 612	
323	5,587,231	198	5,587,325		5,587,398	CLASS 542	CLASS 590	CLASS 613	
325	5,587,232	240.1	5,587,326		5,587,399	CLASS 543	CLASS 591	CLASS 614	
327	5,587,233	240.2	5,587,327		5,587,400	CLASS 544	CLASS 592	CLASS 615	
332	5,587,234		5,587,328		5,587,401	CLASS 545	CLASS 593	CLASS 616	
334	5,587,235		5,587,329		5,587,402	CLASS 546	CLASS 594	CLASS 617	
355	5,587,236		5,587,330		5,587,403	CLASS 547	CLASS 595	CLASS 618	
357	5,587,237		5,587,331		5,587,404	CLASS 548	CLASS 596	CLASS 619	
362	5,587,238	240.46	5,587,332		5,587,405	CLASS 549	CLASS 597	CLASS 620	
367	5,587,239	252.1	5,587,333		5,587,406	CLASS 550	CLASS 598	CLASS 621	
375	5,587,240	252.9	5,587,334		5,587,407	CLASS 551	CLASS 599	CLASS 622	
402	5,587,241	262.5	5,587,335		5,587,408	CLASS 552	CLASS 600	CLASS 623	
413	5,587,242	280	5,587,336		5,587,409	CLASS 553	CLASS 601	CLASS 624	
447	5,587,243		5,587,337		5,587,410	CLASS 554	CLASS 602	CLASS 625	
	5,587,244	290.1	5,587,338		5,587,411	CLASS 555	CLASS 603	CLASS 626	
	5,587,245	305.3	5,587,339		5,587,412	CLASS 556	CLASS 604	CLASS 627	
511	5,587,246	309.4	5,587,340		5,587,413	CLASS 557	CLASS 605	CLASS 628	
523	5,587,247		5,587,341		5,587,414	CLASS 558	CLASS 606	CLASS 629	
610	5,587,248		5,587,342		5,587,415	CLASS 559	CLASS 607	CLASS 630	
		178	5,587,323		5,587,416	CLASS 560	CLASS 608	CLASS 631	
		183	5,587,324		5,587,417	CLASS 561	CLASS 609	CLASS 632	
3	5,587,250		5,587,325		5,587,418	CLASS 562	CLASS 610	CLASS 633	
33	5,587,251		5,587,326		5,587,419	CLASS 563	CLASS 611	CLASS 634	
49	5,587,252	10	5,587,327		5,587,420	CLASS 564	CLASS 612	CLASS 635	
192	5,587,253	31	5,587,328		5,587,421	CLASS 565	CLASS 613	CLASS 636	
206	5,587,254		5,587,329		5,587,422	CLASS 566	CLASS 614	CLASS 637	
218	5,587,255	40	5,587,330		5,587,423	CLASS 567	CLASS 615	CLASS 638	
	5,587,256		5,587,331		5,587,424	CLASS 568	CLASS 616	CLASS 639	
	5,587,257	41	5,587,332		5,587,425	CLASS 569	CLASS 617	CLASS 640	

CLASSIFICATION OF DESIGNS

D2—	733	376,679	501	376,716	376,815	153	376,786	32	376,824	43	376,860
	742	376,680	518	376,718	376,787	114	376,787	37	376,825		376,861
	879	376,681	540	376,719	376,788		376,788	48	376,826		376,862
	882	376,682	556	376,721	376,789		376,789	108	376,827	48	376,863
	954	376,683	603	376,720	376,790		376,790	191	376,828	50	376,864
	970	376,684	332	376,722	376,791		376,791	101	376,829	60	376,865
D3—	203	376,685	359	376,723	376,792	118	376,792	208	376,830	119	376,866
	217	376,686	360	376,724	376,793		376,793	104	376,831	127	376,867
	221	376,687	371	376,721	376,794	121	376,794	107	376,832	157	376,868
	273	376,688	376	376,725	376,795		376,795	128	376,833		376,869
	274	376,689	393	376,726	376,796		376,796	133	376,834		376,870
	284	376,690	395	376,727	376,797	133	376,797	140	376,835		376,871
	294	376,691	507	376,728	376,798	133	376,798	144	376,836	183	376,872
	315	376,692	514	376,729	376,799	150	376,799	207	376,837	101	376,873
	323	376,693	515	376,730	376,800	171	376,800	223	376,838	108	376,874
D4—	102	376,694	536	376,731	376,801	197	376,801	226	376,839	114	376,875
	104	376,695	555	376,732	376,802	213	376,802	311	376,840	118	376,876
	114	376,696	619	376,733	376,803	228	376,803	313	376,841	121	376,877
	114	376,697	629	376,734	376,804	248	376,804	370	376,842	124	376,878
	132	376,698	631	376,735	376,805	253	376,805	382	376,843	124	376,878
D6—	318	376,699	665	376,736	376,806	339	376,806	393	376,844	31	376,879
	334	376,700	698	376,737	376,807	139	376,807	411	376,845	32	376,879
	367	376,701	709	376,738	376,808		376,808		376,846	35	376,880
	379	376,702	8	376,739	376,809		376,809		376,847	43	376,881
	380	376,703	102	376,740	376,810	326	376,810	101	376,847	55	376,881
	396	376,704	117	376,741	376,811	341	376,811	111	376,848	61	376,882
	426	376,705	120	376,742	376,812	341	376,812	152	376,849	11	376,883
	376,706	13	376,743	376,813	30	376,813	189	376,850	28	376,883	
	376,707	75	376,745	376,814	40	376,814	190	376,851		376,884	
	429	376,708	88	376,746	376,815	51	376,815	204	376,852		376,884
	449	376,709	99	376,743	376,816	51	376,816	214	376,853	33	376,885
	470	376,710	330	376,747	376,817	61	376,817	218	376,854		376,885
	480	376,711	346	376,748	376,818	17	376,820	224	376,855	38	376,886
	487	376,712	349	376,749	376,819	41	376,821	124	376,856		376,886
	496	376,713	354	376,750	376,820	17	376,822		376,857	17	376,889
	500	376,715	376,751	376,821	376,823	13	376,823	26	376,858	31	376,889
				376,825	376,825	37	376,825	37	376,859		376,890

VOL
11 93

ISS
4

DE
24

1996

UMI

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

01	5,586,457	5,586,585	5,587,336	5,587,811	5,588,118	5,586,415
	5,586,593	5,586,592	5,587,358	5,587,837	5,588,125	5,586,431
	5,586,594	5,587,361	5,587,850	5,588,131	5,588,131	5,586,442
	5,587,204	5,586,617	5,587,376	5,587,858	5,588,134	5,586,449
	5,587,824	5,586,645	5,587,391	5,587,876	5,588,139	5,586,457
04	5,586,407	5,586,649	5,587,394	5,587,882	5,588,141	5,586,562
	5,586,615	5,586,652	5,587,397	5,587,887	5,588,142	5,586,586
	5,586,742	5,586,681	5,587,454	5,587,889	5,588,150	5,586,637
	5,586,964	5,586,682	5,587,456	5,587,900	5,588,151	5,586,674
	5,587,130	5,586,695	5,587,460	5,587,906	5,586,395	5,586,748
	5,587,215	5,586,696	5,587,462	5,587,910	5,587,093	5,586,764
	5,587,342	5,586,703	5,587,469	5,587,914	5,587,156	5,586,767
	5,587,523	5,586,711	5,587,470	5,587,919	5,587,468	5,586,832
	5,587,589	5,586,715	5,587,471	5,587,921	5,587,518	5,586,837
	5,587,605	5,586,719	5,587,472	5,587,923	5,587,534	5,586,859
	5,587,743	5,586,728	5,587,488	5,587,934	5,587,591	5,586,905
	5,587,866	5,586,755	5,587,490	5,587,936	5,587,675	5,586,906
	5,587,883	5,586,756	5,587,542	5,587,940	5,587,795	5,586,925
	5,587,944	5,586,763	5,587,548	5,587,945	5,588,011	5,586,931
	5,587,957	5,586,779	5,587,550	5,587,947	5,588,030	5,586,977
	5,588,049	5,586,865	5,587,573	5,587,949	5,586,340	5,586,990
	5,588,059	5,586,868	5,587,583	5,587,951	5,586,392	5,587,022
	5,588,062	5,586,893	5,587,594	5,587,971	5,586,471	5,587,068
	5,588,128	5,586,895	5,587,596	5,587,972	5,586,484	5,587,149
05	5,586,558	5,586,898	5,587,597	5,587,983	5,586,666	5,587,168
	5,586,684	5,586,923	5,587,603	5,587,993	5,586,710	5,587,244
	5,587,055	5,586,943	5,587,613	5,587,997	5,586,793	5,587,401
	5,587,549	5,586,946	5,587,617	5,588,000	5,586,817	5,587,489
06	Re. 35,409	5,586,948	5,587,620	5,588,009	5,586,910	5,587,703
	5,586,404	5,586,967	5,587,628	5,588,029	5,586,912	5,587,706
	5,586,409	5,586,970	5,587,646	5,588,038	5,586,919	5,587,880
	5,586,417	5,586,971	5,587,658	5,588,043	5,586,958	5,588,048
	5,586,441	5,586,989	5,587,665	5,588,044	5,586,986	5,588,064
	5,586,465	5,587,039	5,587,669	5,588,045	5,587,099	5,586,339
	5,586,489	5,587,053	5,587,672	5,588,046	5,587,396	5,586,426
	5,586,491	5,587,054	5,587,684	5,588,057	5,587,422	5,586,461
	5,586,498	5,587,148	5,587,686	5,588,060	5,587,570	5,586,540
	5,586,510	5,587,159	5,587,687	5,588,072	5,587,608	5,586,644
	5,586,522	5,587,191	5,587,689	5,588,086	5,587,966	5,586,671
	5,586,529	5,587,217	5,587,692	5,588,090	4,981,472	5,586,686
	5,586,548	5,587,223	5,587,710	5,588,098	5,587,001	5,586,687
	5,586,550	5,587,226	5,587,711	5,588,100	5,587,229	5,586,688
	5,586,553	5,587,267	5,587,714	5,588,104	5,587,429	5,586,690
	5,586,555	5,587,284	5,587,716	5,588,105	5,587,430	5,586,761
	5,586,559	5,587,290	5,587,726	5,588,107	5,587,431	5,586,794
	5,586,561	5,587,293	5,587,734	5,588,108	5,587,431	5,587,011
	5,586,566	5,587,301	5,587,736	5,588,113	5,587,458	5,587,118
	5,586,572	5,587,306	5,587,749	5,588,115	5,587,715	5,587,181
		5,587,332	5,587,784	5,588,117	5,586,390	5,587,221

5,587,225	23	5,587,292	27	5,586,368	5,586,768	5,587,103	5,586,564
5,587,250		5,587,312		5,586,398	5,586,773	5,587,115	5,586,601
5,587,262		5,586,353		5,586,501	5,586,774	5,587,176	5,586,608
5,587,407		5,586,382		5,586,563	5,586,816	5,587,231	5,586,699
5,587,514		5,587,862		5,586,629	5,586,820	5,587,349	5,586,612
5,587,527		5,586,438		5,586,635	5,586,838	5,587,403	5,586,613
5,587,560		5,586,571		5,586,658	5,586,848	5,587,419	5,586,669
5,587,649		5,586,824		5,586,661	5,586,862	5,587,439	5,586,743
5,587,916		5,586,842		5,586,709	5,586,876	5,587,536	5,586,754
5,588,042		5,586,887		5,586,888	5,586,889	5,587,626	5,586,765
5,586,659		5,586,957		5,586,926	5,586,927	5,587,701	5,586,787
5,586,745		5,586,987		5,586,985	5,586,927	5,587,701	5,586,850
5,587,671		5,586,991		5,587,009	5,586,940	5,587,701	5,586,962
5,587,685		5,587,146		5,587,089	5,586,984	5,587,701	5,586,976
5,587,961		5,587,161		5,587,125	5,586,997	5,587,701	5,586,983
5,586,393		5,587,210		5,587,127	5,586,997	5,587,701	5,587,012
5,586,416		5,587,294		5,587,193	5,586,999	5,587,701	5,587,023
5,586,459		5,587,308		5,587,351	5,587,045	5,587,701	5,587,090
5,586,502		5,587,309		5,587,459	5,587,070	5,586,394	5,587,119
5,586,504		5,587,313		5,587,491	5,587,078	5,586,402	5,587,234
5,586,532		5,587,363		5,587,502	5,587,082	5,586,414	5,587,285
5,586,533		5,587,384		5,587,943	5,587,095	5,586,423	5,587,354
5,586,538		5,587,455		5,588,064	5,587,137	5,586,556	5,587,364
5,586,546		5,587,526		5,588,071	5,587,152	5,586,731	5,587,371
5,586,576		5,587,581		5,588,087	5,587,188	5,586,861	5,587,434
5,586,578		5,587,832		5,588,140	5,587,208	5,587,061	5,587,451
5,586,638		5,588,091		5,586,412	5,587,224	5,587,126	5,587,463
5,586,677		5,586,357		5,586,425	5,587,245	5,587,273	5,587,478
5,586,679		5,586,410		5,586,487	5,587,287	5,587,650	5,587,521
5,586,679		5,586,487		5,586,519	5,587,288	5,587,895	5,587,525
5,586,723		5,586,511		5,586,589	5,587,299	5,588,055	5,587,552
5,586,744		5,586,580		5,586,736	5,587,366	5,588,064	5,587,666
5,586,760		5,586,590		5,586,941	5,587,368	5,588,126	5,587,728
5,586,784		5,586,673		5,587,057	5,587,441	5,586,341	5,587,798
5,586,805		5,586,675		5,587,114	5,587,446	5,586,401	5,587,828
5,586,812		5,586,707		5,587,321	5,587,509	5,586,405	5,587,875
5,586,883		5,586,741		5,587,485	5,587,533	5,586,483	5,587,885
5,586,884		5,586,777		5,587,530	5,587,592	5,586,493	5,587,899
5,586,942		5,586,891		5,587,654	5,587,584	5,586,514	5,587,920
5,586,945		5,586,829		5,586,363	5,587,614	5,586,540	5,587,924
5,587,109		5,586,841		5,586,584	5,587,629	5,586,591	5,587,942
5,587,142		5,586,891		5,586,762	5,587,643	5,587,955	5,587,955
5,587,154		5,587,124		5,586,678	5,587,651	5,586,610	5,587,962
5,587,196		5,587,153		5,586,714	5,587,652	5,586,668	5,587,965
5,587,222		5,587,162		5,586,560	5,587,730	5,586,692	5,587,968
5,587,323		5,587,219		5,586,656	5,587,748	5,586,749	5,588,010
5,587,345		5,587,297		5,586,766	5,587,752	5,586,803	5,588,015
5,587,406		5,587,346		5,586,936	5,587,755	5,586,836	5,588,053
5,587,441		5,587,398		5,586,429	5,587,756	5,586,855	5,588,053
5,587,555		5,587,408		5,588,114	5,587,757	5,586,866	5,588,063
5,587,561		5,587,615		5,588,132	5,587,767	5,586,907	5,588,111
5,587,616		5,587,673		5,586,475	5,587,781	5,586,915	5,588,127
5,587,634		5,587,827		5,586,722	5,587,870	5,586,980	5,588,143
5,587,640		5,587,833		5,586,847	5,587,913	5,587,031	5,586,379
5,587,641		5,587,879		5,586,820	5,587,926	5,587,035	5,586,587
5,587,647		5,587,906		5,587,603	5,587,933	5,587,069	5,586,839
5,587,712		5,587,925		5,587,074	5,587,935	5,587,072	5,587,369
5,587,872		5,587,927		5,587,122	5,588,005	5,587,094	5,587,553
5,587,874		5,587,928		5,587,133	5,588,020	5,587,112	5,588,007
5,587,877		5,587,964		5,587,172	5,588,093	5,587,116	5,588,032
5,587,890		5,588,112		5,587,196	5,588,122	5,587,124	5,588,035
5,587,903		5,588,145		5,586,380	5,588,152	5,587,143	5,586,579
5,587,905		5,586,380		5,587,237	5,586,400	5,587,147	5,587,382
5,587,929		5,586,430		5,587,253	5,586,424	5,587,242	5,587,538
5,588,028		5,586,435		5,587,322	5,586,569	5,587,272	5,587,604
5,588,041		5,586,464		5,587,324	5,586,704	5,587,317	5,587,611
5,588,148		5,586,600		5,587,329	5,586,811	5,587,375	5,587,700
5,586,373		5,586,632		5,587,355	5,586,911	5,587,435	5,587,857
5,586,376		5,586,716		5,587,357	5,586,914	5,587,483	5,586,360
5,586,444		5,586,738		5,587,377	5,586,981	5,587,520	5,586,606
5,586,531		5,586,740		5,587,379	5,587,066	5,587,636	5,586,621
5,586,596		5,586,782		5,587,412	5,587,310	5,587,884	5,586,801
5,586,751		5,586,785		5,587,507	5,587,482	5,587,917	5,586,846
5,586,802		5,586,790		5,587,601	5,587,623	5,588,013	5,587,007
5,586,821		5,586,792		5,587,645	5,587,662	5,588,025	5,587,029
5,587,006		5,586,807		5,587,704	5,587,662	5,588,031	5,587,041
5,587,206		5,586,809		5,587,742	5,588,119	5,588,138	5,587,085
5,587,307		5,586,835		5,587,830	5,586,619	5,586,386	5,587,096
5,587,356		5,586,858		5,587,998	5,586,856	5,587,494	5,587,230
5,587,475		5,586,875		5,588,051	5,586,343	5,586,342	5,587,554
5,587,568		5,586,879		5,588,085	5,586,371	5,586,346	5,587,663
5,587,631		5,586,913		5,588,098	5,586,383	5,586,474	5,587,719
5,587,745		5,586,928		5,588,108	5,586,384	5,586,712	5,587,829
5,587,892		5,586,929		5,588,122	5,586,384	5,587,048	5,588,056
5,587,164		5,586,934		5,588,152	5,586,440	5,587,051	5,588,061
5,587,185		5,586,978		5,587,038	5,586,458	5,586,616	5,588,068
5,587,305		5,587,084		5,587,540	5,586,477	5,586,849	5,586,378
5,587,577		5,587,092		5,587,922	5,586,480	5,586,849	5,586,391
5,587,688		5,587,175		5,586,355	5,586,486	5,586,507	5,586,408
5,586,819		5,587,236		5,586,375	5,586,568	5,586,597	5,586,521
5,586,939		5,587,257		5,586,437	5,586,620	5,586,772	5,586,647
5,587,081		5,587,428		5,586,443	5,586,676	5,586,853	5,586,780
5,586,110		5,587,522		5,586,445	5,586,708	5,586,963	5,586,800
5,586,567		5,587,524		5,586,450	5,586,718	5,587,214	5,587,098
5,586,574		5,587,532		5,586,479	5,586,788	5,587,241	5,587,103
5,586,625		5,587,622		5,586,520	5,586,863	5,588,033	5,587,105
5,587,937		5,587,642		5,586,557	5,586,871	5,588,041	5,587,157
5,586,490		5,587,674		5,586,588	5,586,932	5,586,911	5,587,218
5,586,618		5,587,693		5,586,643	5,586,979	5,586,482	5,587,228
5,586,667		5,587,699		5,586,670	5,587,008	5,586,509	5,587,300
5,586,724		5,587,747		5,586,694	5,587,025	5,586,517	5,587,330
5,586,724		5,587,864		5,586,700	5,587,037	5,586,545	5,587,359
5,586,729		5,588,019		5,586,737	5,587,065	5,586,551	5,587,377

5,587,932	55	5,586,439	5,586,706	5,586,955	5,587,259	5,587,448
5,588,037		5,586,447	5,586,730	5,586,969	5,587,261	5,587,497
5,588,095		5,586,488	5,586,759	5,587,032	5,587,286	5,587,498
5,588,099		5,586,518	5,586,769	5,587,043	5,587,300	5,587,740
5,588,129		5,586,630	5,586,804	5,587,073	5,587,318	5,587,861
5,588,147		5,586,657	5,586,805	5,587,108	5,587,402	5,587,861
5,586,959		5,586,685	5,586,830	5,587,184	5,587,433	5,586,603
5,587,705		5,586,702	5,586,867	5,587,202	5,587,442	

DESIGN PATENTS

01	376,811	376,874		376,873	376,774	376,821	376,890
04	376,782	376,887	16 :	376,815	376,792	376,829	376,734
	376,830	376,688	17 :	376,695	376,879	376,849	376,739
	376,871	376,699		376,697	376,881	376,877	376,824
	376,885	376,764		376,737	376,729	376,711	376,844
05	376,755	376,765		376,769	376,825	376,833	376,710
06	376,679	376,804		376,801	376,850	376,684	376,787
	376,681	376,888		376,848	376,883	376,693	376,837
	376,694	376,700	18 :	376,747	376,745	376,791	376,846
	376,713	376,757	28 :	376,707	376,707	376,802	376,714
	376,715	376,859	29 :	376,798	376,854	376,878	376,882
	376,732	376,860		376,851	376,685	376,889	376,754
	376,738	376,861	20 :	376,724	376,720	376,891	376,884
	376,743	376,862	22 :	376,832	376,687	376,723	376,706
	376,748	376,880		376,838	376,689	376,852	376,746
	376,763	376,701	24 :	376,740	376,749	376,872	376,820
	376,767	376,704		376,761	376,760	376,683	376,836
	376,788	376,730	25 :	376,690	376,691	376,718	376,726
	376,789	376,741		376,708	376,696	376,682	376,790
	376,799	376,766		376,728	376,702	376,728	376,806
	376,812	376,784	26 :	376,705	376,709	376,742	
	376,816	376,834		376,716	376,719	376,750	
	376,818	376,840		376,751	376,762	376,756	
	376,822	376,841		376,768	376,783	376,809	
	376,843	376,856		376,770	376,819	376,875	

VOL
11 93

ISS
4

DE
24

19 96

UMI

CHANGE OF ADDRESS FORM

NAME - FIRST, LAST																							
COMPANY NAME OR ADDITIONAL ADDRESS LINE																							
STREET ADDRESS																							
CITY												STATE				ZIP CODE							

PLEASE PRINT OR TYPE

(or) COUNTRY											
--------------	--	--	--	--	--	--	--	--	--	--	--

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

Attach last subscription
label here.

UMI

Important: Please be sure to include this completed order form with your remittance.

**Thank you for
your order!**

UMI

Important: Please be sure to include this completed order form with your remittance.



**Thank you for
your order!**

UMI

Important: Please be sure to include this completed order form with your remittance.

**Thank you for
your order!**

UMI

Important: Please be sure to include this completed order form with your remittance.



**Thank you for
your order!**

VOL
11 93

ISS
4

DE
24

1996

UMI

VOL
11 93

ISS
4

DE
24

1996

U.S. DEPARTMENT OF COMMERCE
Michael Kantor, Secretary
PATENT AND TRADEMARK OFFICE
Bruce Lehman, Commissioner

UMI

VOL
11 93

ISS
5

DE
31

1996


UMI

OFFICIAL GAZETTE

of the
UNITED STATES PATENT AND TRADEMARK OFFICE

PATENTS

December 31, 1996



U.S.
DEPARTMENT
OF COMMERCE

Patent
and
Trademark
Office

PUBLISHED WEEKLY BY AUTHORITY OF CONGRESS

VOL
11 93

ISS
5

DE
31
1996

UMI

OFFICIAL GAZETTE of the
UNITED STATES PATENT AND TRADEMARK OFFICE
December 31, 1996 Volume 1193 Number 5

CONTENTS

		Page
Patent and Trademark Office Notices		
Patent Cooperation Treaty (PCT) Information	1193	OG 93
Notice of Maintenance Fees Payable	1193	OG 93
Notice of Expiration of Patents Due to Failure to Pay Maintenance Fee	1193	OG 94
Reissue Applications Filed	1193	OG 101
Commissioner Ordered Reexaminations	1193	OG 102
Requests for Reexaminations Filed	1193	OG 102
Notice of Expiration of Trademark Registrations Due to Failure to Renew	1193	OG 102
Service by Publication	1193	OG 104
Registration To Practice	1193	OG 104
Erratum	1131	OG 104
Reinstatement to Register	1193	OG 105
Notice of Policy Change	1193	OG 106
Changes in Signature and Filing Requirements	1193	OG 106
Erratum	1193	OG 107
Certificate of Correction	1193	OG 107
Summary of Final Decisions Issued by the Trademark Trial and Appeal Board	1193	OG 108
Special Boxes for Mail	1193	OG 109
Reference Collections of U.S. Patents Available for Public Use in		
Patent Depository Libraries	1193	OG 111
Patent Examining Corps	1193	OG 113
Condition of Trademark Applications	1193	OG 114
Reexaminations		3137
Reissue Patents Granted (35,410)		3143
Plant Patents Granted (9,769)		3147
Patents Granted		
General and Mechanical (5,588,153)		3149
Chemical (5,588,969)		3433
Electrical (5,589,627)		3617
Design Patents Granted (376,893)		3897
Index of Patentees		PI 1
Indices of Reissue, Reexaminations, Design and Plant Patents		PI 106
Classification of		
Patents (Including Reissues and Reexaminations)		PI 115
Designs and Plants Applications		PI 119
Geographical Index of Residence of Inventors		
Patents (Including Reissues and Reexaminations)		PI 121
Designs and Plants Applications		PI 123
Change of Address Form		PI 125
Subscription Order Form		PI 127

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C. 20402, to whom all subscriptions should be made payable and all communications addressed. VISA or MasterCard may be used for telephone orders, (202)-512-1800.

THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly, Stock No. 703-033-00000-8
THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, Stock No. 703-034-00000-4
PATENT AND TRADEMARK OFFICE NOTICES, issued weekly, Stock No. 703-035-00000-1
GENERAL INFORMATION concerning PATENTS, Stock No. 003-004-00661-7

COPIES OF PATENTS are furnished by the Patent and Trademark Office at \$3.00 each; PLANT PATENTS in color, \$12.00 each; copies of TRADEMARKS at \$3.00 each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C. 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S.P.T.O.

For sale by the U.S. Government Printing Office
Superintendent of Documents, Mail Stop: SSOP, Washington, DC 20402-9328

VOL
11 93

ISS
5

DE
31

1996

UMI

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty (PCT) Information

For information concerning PCT member countries, see the notice appearing in the *Official Gazette* at 1190 O.G. 3, on September 3, 1996.

For use of the European Patent Office as an International Searching Authority for international applications filed in the United States Receiving Office, see the notice appearing in the *Official Gazette* at 1022 O.G. 52, on September 28, 1982.

For use of the European Patent Office as an International Preliminary Examining Authority for international applications filed in the United States Receiving Office, see the notices appearing in the *Official Gazette* at 1080 O.G. 2, on July 7, 1987, and at 1091 O.G. 2, on June 7, 1988. There is no longer a limit on the number of such international applications accepted for international preliminary examination by the European Patent Office; see the notice appearing at 1116 O.G. 32, on July 17, 1990.

The search fee of the European Patent Office was changed, effective July 1, 1996, due to a change in the exchange rate of the U.S. dollar with regard to the German mark, and was announced in the *Official Gazette* at 1187 O.G. 73, on June 25, 1996.

International fees were changed, effective on January 1, 1996, due to a change in the exchange rate of the U.S. dollar with regard to the Swiss franc, and were announced in the *Official Gazette* at 1181 O.G. 49, on December 19, 1995.

Certain domestic PCT fees and charges for International Search and Preliminary Examination were changed, effective October 1, 1996, and were announced in the *Official Gazette* at 1189 O.G. 62, on August 20, 1996.

The schedule of PCT fees (in U.S. dollars), effective October 1, 1996, is as follows:

International Application (PCT Chapter I) fees:	
Transmittal fee.....	230.00
Search Fee	
U.S. Patent and Trademark Office (USPTO) as International Searching Authority (ISA)	
— No corresponding prior U.S. national application filed.....	680.00
— Corresponding prior U.S. national application filed.....	440.00
— Supplemental search fee, per additional invention (payable only upon invitation).....	200.00
European Patent Office as ISA.....	1585.00
International fees	
Basic fee.....	677.00
Basic supplemental fee (for each page over 30).....	13.00
Designation fee per country or region	
— For the first 11 national or regional offices designated.....	164.00
— For each designation in excess of 11 offices.....	No Charge
Precautionary designation fee and confirmation fee for each precautionary designation confirmed (PCT Rule 15.5)	
— Designation fee.....	164.00
— Confirmation fee.....	82.00
International Application (PCT Chapter II) fees associated with filing a Demand for Preliminary Examination:	
Handling fee.....	207.00
Preliminary examination fee	
USPTO as International Preliminary Examining Authority (IPEA)	
— USPTO was ISA in PCT Chapter I.....	480.00

— Additional examination fee, per additional invention (payable only upon invitation).....	140.00
— USPTO was not ISA in PCT Chapter I	730.00
— Additional examination fee, per additional invention (payable only upon invitation).....	260.00

U.S. National Stage Fees	Small Entity	Regular
Basic National fee		
USPTO was IPEA		
— All claims presented satisfied provisions of PCT Article 33(2) to (4).....	48.00	96.00
— All claims presented did not satisfy provisions of PCT Article 33(2) to (4).....	350.00	700.00
USPTO was ISA but not IPEA.....	385.00	770.00
USPTO was neither ISA nor IPEA		
— Search report has not been prepared by the European Patent Office or the Japanese Patent Office.....	520.00	1040.00
— Search report has been prepared by the European Patent Office or the Japanese Patent Office.....	455.00	910.00

Other National fees		
— For each independent claim in excess of 3.....	40.00	80.00
— For each claim in excess of 20.....	11.00	22.00
— For each application containing a multiple dependent claim.....	130.00	260.00
— Surcharge for filing oath or declaration after the time limit applicable under PCT Article 22 or 39(1).....	65.00	130.00
— Processing fee for filing English translation after the time limit applicable under PCT Article 22 or 39(1).....	130.00	130.00

Sept. 10, 1996

BRUCE A. LEHMAN
Assistant Secretary of Commerce and
Commissioner of Patents and Trademarks

Notice of Maintenance Fees Payable

Title 37 Code of Federal Regulations (CFR), Section 1.362(d) provides that maintenance fees may be paid without surcharge for the six-month period beginning 3, 7, and 11 years after the date of issue of patents based on applications filed on or after Dec. 12, 1980. An additional six-month grace period is provided by 35 U.S.C. 41(b) and 37 CFR 1.362(e) for payment of the maintenance fee with the surcharge set forth in 37 CFR 1.20(h), as amended effective Dec. 16, 1991. If the maintenance fee is not paid in the patent requiring such payment the patent will expire on the 4th, 8th, or 12th anniversary of the grant.

Attention is drawn to the patents which were issued on December 28, 1993 for which maintenance fees due at 3 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 5,272,770 through 5,274,844
Reissue Patents based on the above identified patents.

Attention is drawn to the patents which were issued on December 26, 1989 for which maintenance fees due at 7 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 4,888,825 through 4,890,334
Reissue Patents based on the above identified patents.

Attention is drawn to the patents which were issued on December 24, 1985 for which maintenance fees due at 11 years and six months may now be paid. The patents have patent numbers within the following ranges:

Utility Patents 4,559,646 through 4,561,120
Reissue Patents based on the above identified patents.

No maintenance fees are required for design or plant patents.

Payments of maintenance fees in patents should be directed to "Commissioner of Patents and Trademarks, Box M. Fee, Washington, D.C. 20231."

For patents based on applications filed on or after Dec. 12, 1980, but before Aug. 27, 1982, patent owners must establish small entity status according to 37 CFR 1.27 if they have not done so and if they wish to pay the small entity amount.

The current amounts of the maintenance fees due at 3 years and six months, 7 years and six months, and 11 years and six months are set forth in 37 CFR 1.20(e)-(g), as amended Oct. 1, 1996, which are reproduced below:

37 CFR § 1.20 Post-issuance fees

(e) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980, in force beyond 4 years; the fee is due by three years and six months after the original grant:

By a small entity (§ 1.9(f))\$510.00
By other than a small entity\$1,020.00

(f) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980 in force beyond 8 years; the fee is due by seven years and six months after the original grant:

By a small entity (§ 1.9(f))\$1,025.00
By other than a small entity\$2,050.00

(g) For maintaining an original or reissue patent, except a design or plant patent, based on an application filed on or after Dec. 12, 1980 in force beyond 12 years; the fee is due by eleven years and six months after the original grant:

By a small entity (§ 1.9(f))\$1,540.00
By other than a small entity\$3,080.00

The amount of the surcharge for paying the maintenance fee during the grace period or after expiration of the patent are set forth in 37 CFR 1.20(h), and (i) which are reproduced below:

(h) Surcharge for paying a maintenance fee during the 6 month grace period following the expiration of three years and six months, seven years and six months, and eleven years and six months after the date of the original grant of a patent based on an application filed on or after Dec. 12, 1980:

By a small entity (§ 1.9(f))\$65.00
By other than a small entity\$130.00

(i) Surcharge for accepting a maintenance fee after expiration of a patent for non-timely payment of a maintenance fee where the delay is shown to the satisfaction of the Commissioner to have been:

(1) unavoidable\$680.00
(2) unintentional\$1,600.00

Notice of Expiration of Patents Due to Failure to Pay Maintenance Fee

35 U.S.C. 41 and 37 CFR 1.362(g) provide that if the required maintenance fee and any applicable surcharge are not paid in a patent requiring such payment, the patent will expire at the end of the 4th, 8th or 12th anniversary of the grant of the patent depending on the first maintenance fee which was not paid.

According to the records of the Office, the patents listed below have expired due to failure to pay the required maintenance fee and any applicable surcharge.

PATENTS WHICH EXPIRED October 23, 1996 DUE TO FAILURE TO PAY MAINTENANCE FEES

Patent Number	Serial Number	Issue Date
Re. 34,475	07/821,348	12/14/93
(4,779,252)	(06/745,558)	(10/18/88)
4,477,929	06/545,708	10/23/84
4,477,931	06/477,020	10/23/84
4,477,934	06/478,388	10/23/84
4,477,938	06/427,711	10/23/84
4,477,941	06/338,043	10/23/84
4,477,944	06/398,185	10/23/84
4,477,946	06/450,383	10/23/84
4,477,947	06/437,283	10/23/84
4,477,948	06/477,387	10/23/84
4,477,963	06/467,406	10/23/84
4,477,966	06/361,794	10/23/84
4,477,973	06/397,976	10/23/84
4,477,986	06/456,039	10/23/84
4,477,996	06/484,175	10/23/84
4,478,010	06/555,240	10/23/84
4,478,018	06/287,590	10/23/84
4,478,020	06/330,846	10/23/84
4,478,026	06/500,880	10/23/84
4,478,031	06/404,972	10/23/84
4,478,032	06/462,674	10/23/84
4,478,035	06/358,803	10/23/84
4,478,038	06/420,139	10/23/84
4,478,039	06/501,591	10/23/84
4,478,042	06/437,849	10/23/84
4,478,044	06/290,256	10/23/84
4,478,054	06/513,182	10/23/84
4,478,062	06/413,863	10/23/84
4,478,066	06/423,129	10/23/84
4,478,070	06/440,566	10/23/84
4,478,078	06/491,634	10/23/84
4,478,085	06/408,276	10/23/84
4,478,086	06/456,504	10/23/84
4,478,089	06/393,259	10/23/84
4,478,106	06/277,976	10/23/84
4,478,109	06/306,167	10/23/84
4,478,110	06/446,205	10/23/84
4,478,117	06/375,488	10/23/84
4,478,119	06/424,724	10/23/84
4,478,120	06/441,271	10/23/84
4,478,125	06/441,788	10/23/84
4,478,126	06/423,339	10/23/84
4,478,129	06/249,925	10/23/84
4,478,130	06/245,478	10/23/84
4,478,131	06/295,393	10/23/84
4,478,145	06/538,448	10/23/84
4,478,153	06/352,793	10/23/84
4,478,154	06/330,629	10/23/84
4,478,155	06/333,448	10/23/84
4,478,161	06/459,622	10/23/84
4,478,165	06/476,665	10/23/84
4,478,166	06/219,338	10/23/84
4,478,167	06/260,314	10/23/84
4,478,170	06/510,691	10/23/84
4,478,171	06/528,811	10/23/84
4,478,174	06/580,229	10/23/84
4,478,177	06/449,517	10/23/84
4,478,180	06/466,780	10/23/84

Patent Number	Serial Number	Issue Date	4,478,588	06/519,221	10/23/84
4,478,186	06/377,489	10/23/84	4,478,590	06/335,301	10/23/84
4,478,191	06/459,140	10/23/84	4,478,592	06/421,862	10/23/84
4,478,192	06/459,493	10/23/84	4,478,596	06/444,376	10/23/84
4,478,201	06/583,063	10/23/84	4,478,602	06/348,238	10/23/84
4,478,202	06/277,287	10/23/84	4,478,606	06/417,872	10/23/84
4,478,211	06/389,630	10/23/84	4,478,608	06/417,871	10/23/84
4,478,217	06/358,213	10/23/84	4,478,610	06/577,046	10/23/84
4,478,224	06/444,782	10/23/84	4,478,612	06/517,594	10/23/84
4,478,230	06/329,893	10/23/84	4,478,613	06/410,693	10/23/84
4,478,258	06/426,654	10/23/84	4,478,617	06/429,277	10/23/84
4,478,292	06/399,421	10/23/84	4,478,618	06/519,028	10/23/84
4,478,297	06/430,988	10/23/84	4,478,624	06/404,328	10/23/84
4,478,302	06/435,427	10/23/84	4,478,625	06/450,818	10/23/84
4,478,310	06/478,849	10/23/84	4,478,626	06/413,839	10/23/84
4,478,311	06/289,820	10/23/84	4,478,629	06/281,500	10/23/84
4,478,312	06/428,595	10/23/84	4,478,632	06/393,656	10/23/84
4,478,315	06/440,350	10/23/84	4,478,645	06/470,118	10/23/84
4,478,327	06/382,541	10/23/84	4,478,647	06/524,503	10/23/84
4,478,340	06/372,073	10/23/84	4,478,650	06/543,649	10/23/84
4,478,341	06/521,419	10/23/84	4,478,657	06/456,336	10/23/84
4,478,345	06/508,116	10/23/84	4,478,668	06/572,308	10/23/84
4,478,351	06/440,527	10/23/84	4,478,690	06/452,570	10/23/84
4,478,353	06/352,938	10/23/84	4,478,693	06/459,410	10/23/84
4,478,368	06/387,437	10/23/84	4,478,698	06/567,876	10/23/84
4,478,370	06/360,103	10/23/84	4,478,703	06/594,577	10/23/84
4,478,378	06/434,073	10/23/84	4,478,704	06/454,487	10/23/84
4,478,380	06/446,456	10/23/84	4,478,718	06/405,745	10/23/84
4,478,385	06/536,822	10/23/84	4,478,722	06/538,887	10/23/84
4,478,386	06/528,158	10/23/84	4,478,727	06/416,939	10/23/84
4,478,387	06/313,725	10/23/84	4,478,729	06/388,047	10/23/84
4,478,392	06/381,616	10/23/84	4,478,734	06/478,669	10/23/84
4,478,398	06/398,980	10/23/84	4,478,735	06/376,963	10/23/84
4,478,399	06/399,011	10/23/84	4,478,740	06/467,990	10/23/84
4,478,410	06/418,792	10/23/84	4,478,749	06/358,140	10/23/84
4,478,412	06/382,136	10/23/84	4,478,753	06/426,069	10/23/84
4,478,423	06/601,835	10/23/84	4,478,754	06/437,918	10/23/84
4,478,428	06/333,521	10/23/84	4,478,755	06/439,566	10/23/84
4,478,430	06/436,793	10/23/84	4,478,758	06/393,497	10/23/84
4,478,435	06/439,396	10/23/84	4,478,760	06/249,069	10/23/84
4,478,439	06/362,288	10/23/84	4,478,762	06/416,391	10/23/84
4,478,441	06/424,467	10/23/84	4,478,763	06/435,578	10/23/84
4,478,450	06/395,165	10/23/84	4,478,777	06/469,617	10/23/84
4,478,452	06/221,388	10/23/84	4,478,778	06/508,700	10/23/84
4,478,454	06/271,662	10/23/84	4,478,779	06/526,145	10/23/84
4,478,456	06/285,856	10/23/84	4,478,780	06/463,351	10/23/84
4,478,461	06/411,139	10/23/84	4,478,782	06/532,139	10/23/84
4,478,467	06/453,876	10/23/84	4,478,788	06/399,932	10/23/84
4,478,475	06/534,941	10/23/84	4,478,791	06/444,932	10/23/84
4,478,476	06/369,479	10/23/84	4,478,792	06/532,682	10/23/84
4,478,477	06/388,888	10/23/84	4,478,795	06/434,934	10/23/84
4,478,479	06/407,671	10/23/84	4,478,796	06/467,372	10/23/84
4,478,480	06/453,362	10/23/84	4,478,799	06/447,821	10/23/84
4,478,482	06/262,329	10/23/84	4,478,805	06/534,906	10/23/84
4,478,487	06/379,328	10/23/84	4,478,806	06/443,317	10/23/84
4,478,492	06/442,926	10/23/84	4,478,814	06/431,495	10/23/84
4,478,499	06/307,207	10/23/84	4,478,816	06/385,727	10/23/84
4,478,501	06/481,653	10/23/84	4,478,819	06/488,683	10/23/84
4,478,505	06/422,176	10/23/84	4,478,824	06/521,078	10/23/84
4,478,511	06/400,163	10/23/84	4,478,840	06/540,763	10/23/84
4,478,518	06/530,698	10/23/84	4,478,845	06/459,189	10/23/84
4,478,522	06/421,388	10/23/84	4,478,846	06/545,251	10/23/84
4,478,529	06/378,041	10/23/84	4,478,847	06/377,135	10/23/84
4,478,538	06/426,244	10/23/84	4,478,849	06/474,199	10/23/84
4,478,540	06/388,999	10/23/84	4,478,850	06/489,516	10/23/84
4,478,541	06/435,289	10/23/84	4,478,852	06/377,598	10/23/84
4,478,542	06/470,799	10/23/84	4,478,859	06/382,903	10/23/84
4,478,546	06/332,618	10/23/84	4,478,861	06/369,926	10/23/84
4,478,555	06/409,323	10/23/84	4,478,865	06/429,087	10/23/84
4,478,559	06/281,617	10/23/84	4,478,875	06/508,584	10/23/84
4,478,562	06/420,802	10/23/84	4,478,886	06/372,527	10/23/84
4,478,568	06/506,120	10/23/84	4,478,888	06/520,095	10/23/84
4,478,569	06/506,119	10/23/84	4,478,894	06/445,099	10/23/84
4,478,571	06/423,587	10/23/84	4,478,912	06/407,394	10/23/84
4,478,572	06/453,866	10/23/84	4,478,913	06/381,127	10/23/84
4,478,573	06/457,030	10/23/84	4,478,922	06/553,931	10/23/84
4,478,583	06/544,488	10/23/84	4,478,924	06/314,456	10/23/84
4,478,585	06/461,876	10/23/84	4,478,927	06/384,118	10/23/84
			4,478,932	06/367,679	10/23/84

Patent Number	Serial Number	Issue Date	4,777,692	07/034,674	10/18/88
4,478,936	06/409,986	10/23/84	4,777,693	06/900,637	10/18/88
4,478,941	06/444,632	10/23/84	4,777,696	06/886,504	10/18/88
4,478,945	06/287,701	10/23/84	4,777,697	07/003,636	10/18/88
4,478,948	06/520,142	10/23/84	4,777,701	07/010,194	10/18/88
4,478,950	06/488,505	10/23/84	4,777,705	07/115,395	10/18/88
4,478,954	06/497,401	10/23/84	4,777,706	07/096,613	10/18/88
4,478,955	06/552,556	10/23/84	4,777,712	06/919,053	10/18/88
4,478,958	06/396,707	10/23/84	4,777,714	06/907,887	10/18/88
4,478,959	06/537,471	10/23/84	4,777,718	06/880,613	10/18/88
4,478,963	06/499,618	10/23/84	4,777,719	06/833,349	10/18/88
4,478,964	06/334,668	10/23/84	4,777,723	07/138,834	10/18/88
4,478,973	06/575,647	10/23/84	4,777,726	07/055,617	10/18/88
4,478,976	06/420,317	10/23/84	4,777,727	07/086,950	10/18/88
4,478,979	06/507,583	10/23/84	4,777,730	06/892,836	10/18/88
4,478,984	06/535,184	10/23/84	4,777,731	07/126,782	10/18/88
4,478,985	06/560,467	10/23/84	4,777,733	07/001,453	10/18/88
4,479,001	06/467,552	10/23/84	4,777,736	07/068,970	10/18/88
4,479,003	06/265,635	10/23/84	4,777,743	07/038,910	10/18/88
4,479,004	06/430,104	10/23/84	4,777,745	06/787,491	10/18/88
4,479,005	06/450,500	10/23/84	4,777,748	07/127,517	10/18/88
4,479,008	06/391,995	10/23/84	4,777,760	06/888,332	10/18/88
4,479,011	06/440,952	10/23/84	4,777,762	07/160,861	10/18/88
4,479,020	06/500,039	10/23/84	4,777,765	06/946,062	10/18/88
4,479,024	06/443,722	10/23/84	4,777,767	07/083,037	10/18/88
4,479,025	06/496,451	10/23/84	4,777,768	07/090,129	10/18/88
4,479,026	06/497,269	10/23/84	4,777,769	06/946,644	10/18/88
4,479,035	06/369,819	10/23/84	4,777,772	07/037,663	10/18/88
4,479,043	06/483,306	10/23/84	4,777,773	07/040,633	10/18/88
4,479,046	06/334,761	10/23/84	4,777,777	07/172,754	10/18/88
4,479,050	06/426,221	10/23/84	4,777,778	06/902,708	10/18/88
4,479,058	06/418,528	10/23/84	4,777,779	07/006,887	10/18/88
4,479,068	06/404,720	10/23/84	4,777,786	06/525,496	10/18/88
4,479,082	06/329,029	10/23/84	4,777,788	07/042,076	10/18/88
4,479,085	06/370,770	10/23/84	4,777,792	07/030,140	10/18/88
4,479,087	06/225,580	10/23/84	4,777,794	07/007,513	10/18/88
4,479,088	06/382,278	10/23/84	4,777,797	07/161,376	10/18/88
4,479,094	06/398,350	10/23/84	4,777,798	06/807,983	10/18/88
4,479,095	06/347,244	10/23/84	4,777,803	07/099,093	10/18/88
4,479,111	06/340,907	10/23/84	4,777,806	06/946,484	10/18/88
4,479,113	06/423,396	10/23/84	4,777,821	07/081,674	10/18/88
4,479,117	06/348,101	10/23/84	4,777,824	06/919,706	10/18/88
4,479,118	06/283,640	10/23/84	4,777,825	07/066,772	10/18/88
4,479,119	06/393,114	10/23/84	4,777,829	07/073,672	10/18/88
4,479,126	06/383,627	10/23/84	4,777,830	07/103,780	10/18/88
4,479,130	06/390,967	10/23/84	4,777,835	07/022,027	10/18/88
4,479,135	06/384,366	10/23/84	4,777,842	06/723,761	10/18/88
4,479,147	06/384,431	10/23/84	4,777,843	07/042,529	10/18/88
4,479,148	06/317,265	10/23/84	4,777,844	07/058,726	10/18/88
4,479,150	06/351,564	10/23/84	4,777,847	06/945,633	10/18/88
4,479,159	06/406,696	10/23/84	4,777,851	07/082,941	10/18/88
4,479,162	06/454,206	10/23/84	4,777,854	06/914,625	10/18/88
4,479,163	06/358,627	10/23/84	4,777,856	07/053,822	10/18/88
4,479,182	06/328,397	10/23/84	4,777,859	06/895,350	10/18/88
4,479,187	06/341,579	10/23/84	4,777,862	07/086,850	10/18/88
4,479,192	06/468,916	10/23/84	4,777,866	07/068,714	10/18/88
4,479,198	06/302,724	10/23/84	4,777,872	06/913,732	10/18/88
4,479,208	06/551,223	10/23/84	4,777,873	07/078,158	10/18/88
4,479,210	06/388,832	10/23/84	4,777,874	07/008,478	10/18/88
4,479,214	06/275,478	10/23/84	4,777,875	07/096,276	10/18/88
4,479,218	06/393,040	10/23/84	4,777,887	07/006,311	10/18/88
4,479,225	06/452,567	10/23/84	4,777,889	07/076,775	10/18/88
4,479,229	06/354,325	10/23/84	4,777,890	07/053,868	10/18/88
4,479,242	06/430,944	10/23/84	4,777,892	07/040,619	10/18/88
4,479,244	06/422,330	10/23/84	4,777,895	06/878,279	10/18/88
4,479,248	06/425,512	10/23/84	4,777,896	07/046,941	10/18/88
4,479,252	06/454,652	10/23/84	4,777,897	07/014,583	10/18/88
4,479,257	06/313,629	10/23/84	4,777,903	06/859,084	10/18/88
4,479,259	06/442,551	10/23/84	4,777,904	07/034,251	10/18/88
4,479,260	06/262,213	10/23/84	4,777,905	06/945,436	10/18/88
4,479,263	06/406,936	10/23/84	4,777,907	07/021,370	10/18/88
4,479,266	07/016,664	10/18/88	4,777,928	07/078,708	10/18/88
4,777,671	06/502,440	10/18/88	4,777,930	07/094,390	10/18/88
4,777,674	06/877,030	10/18/88	4,777,932	06/837,760	10/18/88
4,777,678	07/004,439	10/18/88	4,777,934	06/915,733	10/18/88
4,777,679	07/042,285	10/18/88	4,777,939	07/028,809	10/18/88
4,777,687	06/920,775	10/18/88	4,777,942	06/473,531	10/18/88
4,777,691			4,777,947	07/100,599	10/18/88
				06/910,538	10/18/88

Patent Number	Serial Number	Issue Date	4,778,244	07/040,758	10/18/88
4,777,949	07/048,002	10/18/88	4,778,246	06/734,736	10/18/88
4,777,956	06/893,794	10/18/88	4,778,249	06/823,506	10/18/88
4,777,957	06/744,926	10/18/88	4,778,250	07/023,243	10/18/88
4,777,971	07/088,471	10/18/88	4,778,253	06/844,357	10/18/88
4,777,972	07/061,229	10/18/88	4,778,263	07/055,275	10/18/88
4,777,973	07/078,357	10/18/88	4,778,268	06/827,185	10/18/88
4,777,978	07/114,444	10/18/88	4,778,274	06/930,749	10/18/88
4,777,979	07/121,813	10/18/88	4,778,276	06/896,815	10/18/88
4,777,982	07/073,960	10/18/88	4,778,277	06/763,828	10/18/88
4,777,987	07/112,169	10/18/88	4,778,281	06/452,537	10/18/88
4,777,988	06/775,796	10/18/88	4,778,283	06/947,717	10/18/88
4,777,990	06/905,874	10/18/88	4,778,287	07/043,183	10/18/88
4,777,994	07/071,706	10/18/88	4,778,291	07/042,173	10/18/88
4,777,995	07/053,343	10/18/88	4,778,296	07/111,664	10/18/88
4,777,998	07/112,078	10/18/88	4,778,302	07/070,043	10/18/88
4,778,003	07/047,072	10/18/88	4,778,322	06/768,267	10/18/88
4,778,007	07/000,349	10/18/88	4,778,330	06/844,202	10/18/88
4,778,009	07/072,493	10/18/88	4,778,333	07/025,346	10/18/88
4,778,015	06/944,248	10/18/88	4,778,336	07/071,626	10/18/88
4,778,020	07/054,487	10/18/88	4,778,337	06/945,871	10/18/88
4,778,028	06/926,224	10/18/88	4,778,344	06/909,880	10/18/88
4,778,033	07/113,517	10/18/88	4,778,345	06/839,664	10/18/88
4,778,040	07/013,809	10/18/88	4,778,354	06/913,130	10/18/88
4,778,043	07/004,315	10/18/88	4,778,355	06/906,260	10/18/88
4,778,044	07/084,624	10/18/88	4,778,358	07/006,666	10/18/88
4,778,046	07/127,225	10/18/88	4,778,359	07/116,513	10/18/88
4,778,060	06/781,375	10/18/88	4,778,366	07/027,898	10/18/88
4,778,062	06/909,068	10/18/88	4,778,372	06/930,024	10/18/88
4,778,068	07/124,972	10/18/88	4,778,373	07/049,709	10/18/88
4,778,073	07/066,189	10/18/88	4,778,374	07/126,727	10/18/88
4,778,078	07/020,780	10/18/88	4,778,375	07/065,526	10/18/88
4,778,081	07/017,713	10/18/88	4,778,377	07/121,339	10/18/88
4,778,089	07/115,391	10/18/88	4,778,386	06/928,249	10/18/88
4,778,093	07/037,427	10/18/88	4,778,390	06/914,166	10/18/88
4,778,098	06/932,870	10/18/88	4,778,391	07/116,842	10/18/88
4,778,101	07/025,183	10/18/88	4,778,396	06/577,428	10/18/88
4,778,108	07/014,811	10/18/88	4,778,397	06/903,852	10/18/88
4,778,111	07/096,652	10/18/88	4,778,398	07/057,999	10/18/88
4,778,117	07/060,610	10/18/88	4,778,400	06/769,942	10/18/88
4,778,118	07/084,407	10/18/88	4,778,405	06/658,093	10/18/88
4,778,123	07/086,472	10/18/88	4,778,406	07/051,544	10/18/88
4,778,125	07/072,017	10/18/88	4,778,408	07/014,089	10/18/88
4,778,126	06/816,853	10/18/88	4,778,418	07/091,584	10/18/88
4,778,128	06/836,418	10/18/88	4,778,422	06/802,413	10/18/88
4,778,130	06/860,915	10/18/88	4,778,424	06/900,394	10/18/88
4,778,131	07/104,301	10/18/88	4,778,427	07/060,135	10/18/88
4,778,138	06/912,502	10/18/88	4,778,428	07/030,675	10/18/88
4,778,148	07/064,819	10/18/88	4,778,447	06/496,766	10/18/88
4,778,149	07/079,215	10/18/88	4,778,449	07/009,525	10/18/88
4,778,156	06/946,502	10/18/88	4,778,452	07/065,644	10/18/88
4,778,157	07/066,096	10/18/88	4,778,454	06/938,462	10/18/88
4,778,160	07/019,522	10/18/88	4,778,457	06/927,929	10/18/88
4,778,161	07/004,711	10/18/88	4,778,458	07/039,139	10/18/88
4,778,163	07/079,933	10/18/88	4,778,459	07/004,771	10/18/88
4,778,167	06/947,705	10/18/88	4,778,460	06/785,369	10/18/88
4,778,174	07/090,536	10/18/88	4,778,467	06/884,088	10/18/88
4,778,175	06/903,297	10/18/88	4,778,470	06/725,237	10/18/88
4,778,178	07/044,515	10/18/88	4,778,471	06/932,742	10/18/88
4,778,179	07/015,127	10/18/88	4,778,472	06/939,558	10/18/88
4,778,185	07/098,491	10/18/88	4,778,479	07/026,581	10/18/88
4,778,194	07/072,637	10/18/88	4,778,482	07/070,649	10/18/88
4,778,196	07/100,986	10/18/88	4,778,487	07/033,320	10/18/88
4,778,198	06/890,397	10/18/88	4,778,492	07/016,575	10/18/88
4,778,199	06/859,675	10/18/88	4,778,493	06/856,490	10/18/88
4,778,200	06/921,239	10/18/88	4,778,494	07/079,301	10/18/88
4,778,201	07/074,191	10/18/88	4,778,496	07/120,401	10/18/88
4,778,202	07/053,236	10/18/88	4,778,500	07/084,049	10/18/88
4,778,208	07/051,693	10/18/88	4,778,506	07/042,038	10/18/88
4,778,212	07/039,229	10/18/88	4,778,511	06/830,593	10/18/88
4,778,218	06/941,294	10/18/88	4,778,512	07/093,416	10/18/88
4,778,220	06/941,500	10/18/88	4,778,513	06/908,768	10/18/88
4,778,225	07/083,491	10/18/88	4,778,515	06/905,015	10/18/88
4,778,227	07/059,108	10/18/88	4,778,516	06/926,482	10/18/88
4,778,229	06/886,837	10/18/88	4,778,523	07/067,429	10/18/88
4,778,237	06/618,032	10/18/88	4,778,524	07/031,087	10/18/88
4,778,239	07/009,967	10/18/88	4,778,527	06/947,171	10/18/88
4,778,243	07/121,042	10/18/88	4,778,529	06/917,862	10/18/88
			4,778,530	07/120,183	10/18/88

Patent Number	Serial Number	Issue Date	4,778,808	06/839,041	10/18/88
4,778,542	06/885,943	10/18/88	4,778,817	06/838,565	10/18/88
4,778,547	07/005,267	10/18/88	4,778,818	07/039,407	10/18/88
4,778,550	07/118,813	10/18/88	4,778,819	07/148,810	10/18/88
4,778,554	06/848,958	10/18/88	4,778,820	07/086,997	10/18/88
4,778,555	06/846,363	10/18/88	4,778,824	07/065,613	10/18/88
4,778,559	06/919,313	10/18/88	4,778,825	06/901,927	10/18/88
4,778,563	07/031,105	10/18/88	4,778,830	07/127,270	10/18/88
4,778,565	07/119,827	10/18/88	4,778,831	06/725,375	10/18/88
4,778,568	07/076,135	10/18/88	4,778,834	07/018,367	10/18/88
4,778,570	06/706,852	10/18/88	4,778,848	07/729,211	10/18/88
4,778,578	07/122,645	10/18/88	4,778,857	07/054,971	10/18/88
4,778,580	07/009,445	10/18/88	4,778,862	07/007,505	10/18/88
4,778,583	07/048,112	10/18/88	4,778,865	07/072,938	10/18/88
4,778,589	06/901,341	10/18/88	4,778,874	07/051,804	10/18/88
4,778,590	06/901,344	10/18/88	4,778,886	07/152,473	10/18/88
4,778,591	06/901,342	10/18/88	4,778,892	07/048,325	10/18/88
4,778,592	06/901,345	10/18/88	4,778,893	07/000,540	10/18/88
4,778,594	06/889,131	10/18/88	4,778,897	07/055,105	10/18/88
4,778,597	07/133,317	10/18/88	4,778,898	06/921,914	10/18/88
4,778,599	06/927,879	10/18/88	4,778,907	06/936,473	10/18/88
4,778,602	06/856,368	10/18/88	4,778,908	07/055,692	10/18/88
4,778,604	07/065,761	10/18/88	4,778,910	07/133,131	10/18/88
4,778,607	07/026,595	10/18/88	4,778,912	06/933,210	10/18/88
4,778,610	06/813,803	10/18/88	4,778,915	06/920,105	10/18/88
4,778,612	06/921,921	10/18/88	4,778,917	07/115,294	10/18/88
4,778,613	06/813,296	10/18/88	4,778,918	07/115,292	10/18/88
4,778,614	06/785,606	10/18/88	4,778,920	06/922,902	10/18/88
4,778,615	06/905,608	10/18/88	4,778,928	06/940,311	10/18/88
4,778,619	06/842,648	10/18/88	4,778,931	06/803,122	10/18/88
4,778,628	06/863,485	10/18/88	4,778,933	07/073,704	10/18/88
4,778,629	06/922,277	10/18/88	4,778,934	07/145,437	10/18/88
4,778,633	07/047,557	10/18/88	4,778,939	07/029,896	10/18/88
4,778,635	07/098,241	10/18/88	4,778,946	07/052,178	10/18/88
4,778,646	06/760,414	10/18/88	4,778,949	07/006,728	10/18/88
4,778,654	06/926,048	10/18/88	4,778,956	07/116,440	10/18/88
4,778,657	06/905,200	10/18/88	4,778,957	07/058,416	10/18/88
4,778,660	06/868,476	10/18/88	4,778,959	07/042,763	10/18/88
4,778,661	07/006,408	10/18/88	4,778,963	07/037,645	10/18/88
4,778,664	07/015,905	10/18/88	4,778,965	07/129,932	10/18/88
4,778,667	06/937,112	10/18/88	4,778,973	06/871,105	10/18/88
4,778,668	06/944,756	10/18/88	4,778,974	07/037,662	10/18/88
4,778,672	06/802,779	10/18/88	4,778,978	07/018,945	10/18/88
4,778,682	07/046,886	10/18/88	4,778,981	06/796,695	10/18/88
4,778,684	06/883,259	10/18/88	4,778,985	07/095,884	10/18/88
4,778,688	06/786,787	10/18/88	4,778,997	06/772,420	10/18/88
4,778,689	06/856,020	10/18/88	4,779,008	07/063,542	10/18/88
4,778,690	06/896,691	10/18/88	4,779,021	07/018,801	10/18/88
4,778,696	07/063,892	10/18/88	4,779,022	07/060,815	10/18/88
4,778,698	07/030,730	10/18/88	4,779,024	06/901,065	10/18/88
4,778,705	07/040,899	10/18/88	4,779,026	07/039,662	10/18/88
4,778,709	07/100,183	10/18/88	4,779,031	06/819,202	10/18/88
4,778,714	06/786,735	10/18/88	4,779,034	06/894,111	10/18/88
4,778,716	07/030,475	10/18/88	4,779,038	06/839,787	10/18/88
4,778,721	06/883,620	10/18/88	4,779,040	07/007,485	10/18/88
4,778,722	07/048,038	10/18/88	4,779,044	07/095,009	10/18/88
4,778,724	07/006,368	10/18/88	4,779,046	06/880,553	10/18/88
4,778,726	07/044,640	10/18/88	4,779,050	06/901,186	10/18/88
4,778,742	07/105,621	10/18/88	4,779,051	07/033,156	10/18/88
4,778,749	06/616,534	10/18/88	4,779,055	07/003,015	10/18/88
4,778,759	06/689,514	10/18/88	4,779,063	07/007,459	10/18/88
4,778,760	06/795,774	10/18/88	4,779,064	07/032,665	10/18/88
4,778,766	06/772,735	10/18/88	4,779,071	06/942,753	10/18/88
4,778,767	06/682,373	10/18/88	4,779,074	07/096,742	10/18/88
4,778,768	06/732,003	10/18/88	4,779,075	06/938,505	10/18/88
4,778,779	07/037,506	10/18/88	4,779,079	06/758,109	10/18/88
4,778,783	07/022,563	10/18/88	4,779,090	06/893,648	10/18/88
4,778,784	07/124,419	10/18/88	4,779,094	06/933,178	10/18/88
4,778,785	06/902,293	10/18/88	4,779,096	06/848,568	10/18/88
4,778,787	06/811,375	10/18/88	4,779,098	07/006,573	10/18/88
4,778,791	07/046,889	10/18/88	4,779,099	07/017,855	10/18/88
4,778,795	06/903,545	10/18/88	4,779,100	07/076,324	10/18/88
4,778,796	06/884,717	10/18/88	4,779,104	07/086,916	10/18/88
4,778,798	06/892,247	10/18/88	4,779,122	06/927,171	10/18/88
4,778,799	07/102,240	10/18/88	4,779,125	06/819,089	10/18/88
4,778,801	07/067,218	10/18/88	4,779,128	06/927,782	10/18/88
4,778,805	07/064,152	10/18/88	4,779,129	06/901,667	10/18/88
4,778,807	07/106,662	10/18/88	4,779,132	07/070,999	10/18/88
			4,779,135	06/911,777	10/18/88

Patent Number	Serial Number	Issue Date	5,156,074	07/370,150	10/20/92
4,779,141	07/001,250	10/18/88	5,156,077	07/760,531	10/20/92
4,779,145	06/850,252	10/18/88	5,156,096	07/670,532	10/20/92
4,779,148	07/004,581	10/18/88	5,156,104	07/720,933	10/20/92
4,779,150	07/033,308	10/18/88	5,156,108	07/835,838	10/20/92
4,779,154	06/923,299	10/18/88	5,156,109	07/377,886	10/20/92
4,779,185	07/038,405	10/18/88	5,156,111	07/639,035	10/20/92
4,779,196	06/831,695	10/18/88	5,156,120	07/834,628	10/20/92
4,779,198	07/148,098	10/18/88	5,156,121	07/530,754	10/20/92
4,779,199	06/904,371	10/18/88	5,156,122	07/792,387	10/20/92
4,779,202	06/943,694	10/18/88	5,156,137	07/663,563	10/20/92
4,779,204	06/887,624	10/18/88	5,156,141	07/667,656	10/20/92
4,779,207	07/000,582	10/18/88	5,156,159	07/505,689	10/20/92
4,779,218	06/772,962	10/18/88	5,156,162	07/751,920	10/20/92
4,779,231	06/937,502	10/18/88	5,156,168	07/664,334	10/20/92
4,779,233	06/911,348	10/18/88	5,156,169	07/609,975	10/20/92
4,779,235	06/814,471	10/18/88	5,156,170	07/713,939	10/20/92
4,779,238	07/037,666	10/18/88	5,156,173	07/699,935	10/20/92
4,779,241	06/877,752	10/18/88	5,156,175	07/760,376	10/20/92
4,779,242	06/752,599	10/18/88	5,156,176	07/669,636	10/20/92
4,779,257	07/004,151	10/18/88	5,156,186	07/705,287	10/20/92
4,779,264	06/837,935	10/18/88	5,156,202	07/754,324	10/20/92
4,779,265	06/923,328	10/18/88	5,156,204	07/550,192	10/20/92
4,779,267	07/019,838	10/18/88	5,156,205	07/726,778	10/20/92
4,779,271	06/928,380	10/18/88	5,156,206	07/722,130	10/20/92
4,779,275	06/846,451	10/18/88	5,156,212	07/703,453	10/20/92
4,779,277	06/473,411	10/18/88	5,156,214	07/628,042	10/20/92
4,779,278	06/938,266	10/18/88	5,156,215	07/723,586	10/20/92
4,779,280	06/867,933	10/18/88	5,156,222	07/612,909	10/20/92
4,779,283	06/854,753	10/18/88	5,156,224	07/666,739	10/20/92
4,779,284	07/031,031	10/18/88	5,156,225	07/559,604	10/20/92
4,779,286	07/066,146	10/18/88	5,156,226	07/554,363	10/20/92
5,155,863	07/704,818	10/18/88	5,156,228	07/648,298	10/20/92
5,155,875	07/583,797	10/20/92	5,156,231	07/719,662	10/20/92
5,155,877	07/692,696	10/20/92	5,156,235	07/760,972	10/20/92
5,155,883	07/496,589	10/20/92	5,156,236	07/871,283	10/20/92
5,155,887	07/642,347	10/20/92	5,156,247	07/584,759	10/20/92
5,155,894	07/575,299	10/20/92	5,156,248	07/746,717	10/20/92
5,155,898	07/757,610	10/20/92	5,156,258	07/797,703	10/20/92
5,155,901	07/814,502	10/20/92	5,156,267	07/715,403	10/20/92
5,155,902	07/736,792	10/20/92	5,156,270	07/760,646	10/20/92
5,155,908	07/692,130	10/20/92	5,156,272	07/735,442	10/20/92
5,155,910	07/801,014	10/20/92	5,156,275	07/696,593	10/20/92
5,155,919	07/826,409	10/20/92	5,156,286	07/791,995	10/20/92
5,155,920	07/692,658	10/20/92	5,156,288	07/732,629	10/20/92
5,155,921	07/733,861	10/20/92	5,156,290	07/571,670	10/20/92
5,155,924	07/636,758	10/20/92	5,156,291	07/632,760	10/20/92
5,155,925	07/810,673	10/20/92	5,156,292	07/646,680	10/20/92
5,155,931	07/845,835	10/20/92	5,156,296	07/817,326	10/20/92
5,155,932	07/659,294	10/20/92	5,156,302	07/653,644	10/20/92
5,155,942	07/428,493	10/20/92	5,156,306	07/638,103	10/20/92
5,155,946	07/729,320	10/20/92	5,156,326	07/766,761	10/20/92
5,155,952	07/392,982	10/20/92	5,156,328	07/734,141	10/20/92
5,155,956	07/492,458	10/20/92	5,156,332	07/764,757	10/20/92
5,155,957	07/658,842	10/20/92	5,156,333	07/712,790	10/20/92
5,155,963	07/645,217	10/20/92	5,156,335	07/631,001	10/20/92
5,155,966	07/505,017	10/20/92	5,156,338	07/623,776	10/20/92
5,155,970	07/701,841	10/20/92	5,156,339	07/779,324	10/20/92
5,155,978	07/742,338	10/20/92	5,156,346	07/758,610	10/20/92
5,155,987	07/669,002	10/20/92	5,156,347	07/626,520	10/20/92
5,155,989	07/483,742	10/20/92	5,156,348	07/604,841	10/20/92
5,155,990	07/645,196	10/20/92	5,156,349	07/794,779	10/20/92
5,156,000	07/692,686	10/20/92	5,156,353	07/037,764	10/20/92
5,156,002	07/658,858	10/20/92	5,156,357	06/406,686	10/20/92
5,156,004	07/603,995	10/20/92	5,156,361	07/232,456	10/20/92
5,156,019	07/615,493	10/20/92	5,156,366	07/727,869	10/20/92
5,156,021	07/740,110	10/20/92	5,156,367	07/657,391	10/20/92
5,156,026	07/694,421	10/20/92	5,156,373	07/740,748	10/20/92
5,156,027	07/740,106	10/20/92	5,156,375	07/659,982	10/20/92
5,156,029	07/568,794	10/20/92	5,156,378	07/691,458	10/20/92
5,156,030	07/661,585	10/20/92	5,156,383	07/732,925	10/20/92
5,156,034	07/656,084	10/20/92	5,156,393	07/668,505	10/20/92
5,156,036	07/747,034	10/20/92	5,156,394	07/597,561	10/20/92
5,156,038	07/739,035	10/20/92	5,156,397	07/776,892	10/20/92
5,156,042	07/373,237	10/20/92	5,156,399	07/853,589	10/20/92
5,156,049	07/817,310	10/20/92	5,156,400	07/766,329	10/20/92
5,156,054	07/562,259	10/20/92	5,156,401	07/775,743	10/20/92
5,156,072	07/720,672	10/20/92	5,156,403	07/848,041	10/20/92
		10/20/92	5,156,407	07/836,828	10/20/92

Patent Number	Serial Number	Issue Date	5,156,718	07/643,391	10/20/92
5,156,408	07/804,003	10/20/92	5,156,720	07/306,505	10/20/92
5,156,413	07/385,729	10/20/92	5,156,721	07/621,278	10/20/92
5,156,414	07/613,838	10/20/92	5,156,729	07/430,676	10/20/92
5,156,416	07/526,729	10/20/92	5,156,734	07/599,656	10/20/92
5,156,418	07/689,549	10/20/92	5,156,737	07/683,426	10/20/92
5,156,421	07/648,928	10/20/92	5,156,743	07/673,074	10/20/92
5,156,425	07/487,923	10/20/92	5,156,761	07/666,554	10/20/92
5,156,427	07/737,136	10/20/92	5,156,762	07/868,052	10/20/92
5,156,431	07/671,476	10/20/92	5,156,767	07/842,732	10/20/92
5,156,435	07/445,596	10/20/92	5,156,768	07/681,026	10/20/92
5,156,436	07/656,288	10/20/92	5,156,769	07/540,597	10/20/92
5,156,440	07/864,313	10/20/92	5,156,771	07/527,773	10/20/92
5,156,444	07/466,329	10/20/92	5,156,782	07/769,820	10/20/92
5,156,446	07/826,081	10/20/92	5,156,790	07/735,869	10/20/92
5,156,447	07/729,312	10/20/92	5,156,795	07/349,664	10/20/92
5,156,448	07/702,532	10/20/92	5,156,804	07/591,094	10/20/92
5,156,449	07/622,566	10/20/92	5,156,812	07/722,849	10/20/92
5,156,451	07/803,789	10/20/92	5,156,819	07/503,792	10/20/92
5,156,454	07/738,609	10/20/92	5,156,821	07/685,180	10/20/92
5,156,455	07/834,950	10/20/92	5,156,822	07/632,815	10/20/92
5,156,457	07/831,450	10/20/92	5,156,824	07/368,955	10/20/92
5,156,458	07/322,378	10/20/92	5,156,827	07/323,311	10/20/92
5,156,459	07/839,663	10/20/92	5,156,832	07/670,669	10/20/92
5,156,462	07/740,904	10/20/92	5,156,837	07/582,290	10/20/92
5,156,475	07/623,116	10/20/92	5,156,845	07/519,073	10/20/92
5,156,478	07/580,638	10/20/92	5,156,865	07/746,337	10/20/92
5,156,481	07/453,748	10/20/92	5,156,870	07/706,934	10/20/92
5,156,482	07/703,659	10/20/92	5,156,871	07/693,887	10/20/92
5,156,486	07/636,886	10/20/92	5,156,872	07/827,431	10/20/92
5,156,489	07/770,258	10/20/92	5,156,875	07/716,386	10/20/92
5,156,491	07/763,946	10/20/92	5,156,880	07/650,048	10/20/92
5,156,494	07/737,075	10/20/92	5,156,891	07/833,078	10/20/92
5,156,497	07/796,986	10/20/92	5,156,897	07/872,386	10/20/92
5,156,500	07/595,188	10/20/92	5,156,901	07/565,426	10/20/92
5,156,505	07/662,621	10/20/92	5,156,909	07/445,794	10/20/92
5,156,512	07/580,677	10/20/92	5,156,910	07/565,130	10/20/92
5,156,516	07/599,100	10/20/92	5,156,913	07/448,401	10/20/92
5,156,517	07/664,831	10/20/92	5,156,920	06/904,171	10/20/92
5,156,518	07/658,520	10/20/92	5,156,926	07/450,567	10/20/92
5,156,525	07/660,484	10/20/92	5,156,929	07/670,846	10/20/92
5,156,528	07/687,646	10/20/92	5,156,936	07/650,528	10/20/92
5,156,546	07/428,164	10/20/92	5,156,976	07/712,003	10/20/92
5,156,549	07/610,952	10/20/92	5,156,997	07/653,609	10/20/92
5,156,551	07/771,363	10/20/92	5,157,004	07/575,552	10/20/92
5,156,552	07/484,421	10/20/92	5,157,026	07/840,241	10/20/92
5,156,562	07/732,043	10/20/92	5,157,033	07/685,942	10/20/92
5,156,564	07/712,978	10/20/92	5,157,035	07/637,091	10/20/92
5,156,565	07/623,705	10/20/92	5,157,038	07/566,274	10/20/92
5,156,569	07/737,269	10/20/92	5,157,040	07/681,216	10/20/92
5,156,570	07/763,567	10/20/92	5,157,043	07/593,598	10/20/92
5,156,571	07/668,603	10/20/92	5,157,044	07/535,573	10/20/92
5,156,574	07/731,976	10/20/92	5,157,048	07/790,042	10/20/92
5,156,575	07/856,319	10/20/92	5,157,050	07/587,543	10/20/92
5,156,580	07/694,501	10/20/92	5,157,051	07/846,092	10/20/92
5,156,584	07/697,244	10/20/92	5,157,060	07/218,442	10/20/92
5,156,604	07/781,320	10/20/92	5,157,064	07/499,588	10/20/92
5,156,619	07/538,325	10/20/92	5,157,073	07/684,808	10/20/92
5,156,629	07/493,691	10/20/92	5,157,077	07/515,794	10/20/92
5,156,636	07/617,802	10/20/92	5,157,080	07/677,507	10/20/92
5,156,640	07/761,338	10/20/92	5,157,082	07/611,845	10/20/92
5,156,641	07/489,918	10/20/92	5,157,089	07/699,439	10/20/92
5,156,644	07/779,635	10/20/92	5,157,094	07/564,919	10/20/92
5,156,647	07/806,945	10/20/92	5,157,096	07/554,129	10/20/92
5,156,648	07/550,009	10/20/92	5,157,097	07/746,730	10/20/92
5,156,655	07/622,585	10/20/92	5,157,101	07/532,857	10/20/92
5,156,661	07/828,505	10/20/92	5,157,121	07/731,460	10/20/92
5,156,667	07/684,706	10/20/92	5,157,122	07/642,778	10/20/92
5,156,669	07/682,296	10/20/92	5,157,123	07/322,214	10/20/92
5,156,672	07/553,775	10/20/92	5,157,124	07/853,671	10/20/92
5,156,678	07/673,990	10/20/92	5,157,126	07/834,945	10/20/92
5,156,681	07/705,834	10/20/92	5,157,130	07/499,430	10/20/92
5,156,685	07/635,602	10/20/92	5,157,131	07/779,496	10/20/92
5,156,691	07/583,901	10/20/92	5,157,132	07/525,545	10/20/92
5,156,695	07/622,740	10/20/92	5,157,153	07/790,790	10/20/92
5,156,696	07/490,154	10/20/92	5,157,155	07/667,748	10/20/92
5,156,711	07/598,981	10/20/92	5,157,165	07/796,440	10/20/92
5,156,712	07/482,908	10/20/92	5,157,175	07/767,395	10/20/92
			5,157,187	07/636,828	10/20/92

Patent Number	Serial Number	Issue Date	5,157,703	07/700,357	10/20/92
5,157,189	07/616,584	10/20/92	5,157,706	07/795,790	10/20/92
5,157,192	07/790,624	10/20/92	5,157,707	07/752,623	10/20/92
5,157,199	07/677,905	10/20/92	5,157,717	07/658,042	10/20/92
5,157,204	07/715,943	10/20/92	5,157,718	07/443,116	10/20/92
5,157,207	07/475,869	10/20/92	5,157,719	07/491,933	10/20/92
5,157,210	07/789,857	10/20/92	5,157,721	07/629,225	10/20/92
5,157,211	07/830,077	10/20/92	5,157,736	07/688,173	10/20/92
5,157,212	07/655,110	10/20/92	5,157,758	07/611,654	10/20/92
5,157,217	07/581,312	10/20/92	5,157,769	07/860,293	10/20/92
5,157,219	07/710,342	10/20/92			
5,157,220	07/643,132	10/20/92			
5,157,221	07/622,828	10/20/92			
5,157,223	07/702,146	10/20/92			
5,157,225	06/486,475	10/20/92			
5,157,232	07/524,852	10/20/92			
5,157,240	07/681,338	10/20/92			
5,157,243	07/456,708	10/20/92			
5,157,246	07/506,800	10/20/92			
5,157,253	07/585,764	10/20/92			
5,157,254	07/657,742	10/20/92			
5,157,255	07/795,609	10/20/92			
5,157,261	07/707,414	10/20/92			
5,157,266	07/573,040	10/20/92			
5,157,288	07/670,070	10/20/92			
5,157,312	07/601,936	10/20/92			
5,157,316	07/721,151	10/20/92			
5,157,318	07/762,554	10/20/92			
5,157,320	07/742,111	10/20/92			
5,157,334	07/468,420	10/20/92			
5,157,337	07/593,727	10/20/92			
5,157,342	07/752,294	10/20/92			
5,157,346	07/690,930	10/20/92			
5,157,349	07/792,675	10/20/92			
5,157,360	07/711,847	10/20/92			
5,157,366	07/650,801	10/20/92			
5,157,370	07/827,263	10/20/92			
5,157,377	07/519,286	10/20/92			
5,157,379	07/740,093	10/20/92			
5,157,380	07/657,446	10/20/92			
5,157,383	07/719,634	10/20/92			
5,157,396	07/765,733	10/20/92			
5,157,401	07/789,039	10/20/92			
5,157,402	07/570,856	10/20/92			
5,157,404	07/801,462	10/20/92			
5,157,424	07/582,362	10/20/92			
5,157,428	07/719,924	10/20/92			
5,157,460	07/540,125	10/20/92			
5,157,462	07/475,078	10/20/92			
5,157,485	07/638,687	10/20/92			
5,157,490	07/668,896	10/20/92			
5,157,524	07/411,394	10/20/92			
5,157,525	07/601,136	10/20/92			
5,157,528	07/368,366	10/20/92			
5,157,535	07/827,665	10/20/92			
5,157,537	07/650,559	10/20/92			
5,157,551	07/390,164	10/20/92			
5,157,555	07/802,231	10/20/92			
5,157,556	07/392,991	10/20/92			
5,157,586	07/826,077	10/20/92			
5,157,587	07/632,902	10/20/92			
5,157,589	07/546,963	10/20/92			
5,157,591	07/761,164	10/20/92			
5,157,594	07/760,350	10/20/92			
5,157,595	07/667,249	10/20/92			
5,157,598	07/490,593	10/20/92			
5,157,602	07/475,775	10/20/92			
5,157,604	07/297,567	10/20/92			
5,157,650	07/746,061	10/20/92			
5,157,659	07/534,484	10/20/92			
5,157,665	07/533,895	10/20/92			
5,157,668	07/375,839	10/20/92			
5,157,675	07/813,003	10/20/92			
5,157,678	07/725,785	10/20/92			
5,157,684	07/781,430	10/20/92			
5,157,685	07/688,549	10/20/92			
5,157,689	07/751,819	10/20/92			
5,157,697	07/672,847	10/20/92			

Reissue Applications Filed

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.12(b)).

4,693,399, Re. S.N. 08/731,975, Oct. 23, 1

CIRCUIT, Dao-Long Chen, Owner of Record: *Symbio's Logic Inc., Fort Collins, Colo.*, Attorney or Agent: Donald F. Zinger, Ex. Gp.: 2502

5,485,089, Re. S.N. 08/747,723, Nov. 12, 1996, Cl. 324/346, METHOD AND APPARATUS FOR MEASURING DISTANCE AND DIRECTION BY MOVABLE MAGNETIC FIELD SOURCE, Arthur F. Kurkes, Owner of Record: *Vector Magnetics Inc., Ithaca, N.Y.*, Attorney or Agent: George M. Coope, Ex. Gp.: 2215

5,536,539, Re. S.N. 08/736,410, Oct. 24, 1996, Cl. 428/31, INJECTION MOLDED PLASTIC ARTICLE WITH INTEGRAL WEATHERABLE PIGMENTED FILM SURFACE, Thomas M. Ellison, Owner of Record: *Rexam Industries Corp., Charlotte, N.C.*, Attorney or Agent: Raymond O. Linker, Jr., Ex. Gp.: 1315

Commissioner Ordered Reexaminations

Notice under 37 CFR 1.11(c). The orders for reexamination listed below are open to inspection by the general public in the indicated Examining Group. Copies of the orders and other related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.2(b)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.24(a)(5) and 1.525(b)).

5,550,709, Reexam. No. 90/004,442, Nov. 29, 1996, Cl. 361/684, EXTERNAL STORAGE DEVICE, Hiroshi Iwasaki, Owner of Record: *Kabushiki Kaisha Toshiba, Kawasaki-Shi, Japan*, Attorney or Agent: Finnegan Henderson Farabow Garrett & Dunner, Washington, D.C., Ex. Gp.: 2103, Requester: Commissioner of Patents and Trademarks, Washington, D.C.

Requests for Reexaminations Filed

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.19(a)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.24(a)(5) and 1.525(b)).

4,587,796, Reexam. No. 90/004,456, Nov. 19 1996, Cl. 053/588, PACKAGING MACHINE, Matti Haliola, Owner of Record: *Newtec International, Aix-Les-Bains Cedex, France*, Attorney or Agent: Steven W. Weinrieb, Schwartz & Weinrieb, Arlington, Va., Ex. Gp.: 3201, Requester: Owner

4,949,718, Reexam. No. 90/004,457, Nov. 12, 1996, Cl. 607/105, INTRAUTERINE CAUTERIZING APPARATUS, Robert S. Newirth, et. al., Owner of Record: *Gynelab Prod., Raleigh, N.C.*, Attorney or Agent: Patrick J. Birdie, Kenyon & Kenyon, New York, N.Y., Ex. Gp.: 3311, Requester: Benton S. Duffett, Burns, Doane, Swecker & Mathis, Alexandria, Va.,

5,105,808, Reexam. No. 90/004,458, Nov. 12, 1996, Cl. 607/1, INTRAUTERINE CAUTERIZING METHOD, Robert S. Newirth, et. al., Owner of Record: *Gynelab Products, Raleigh, N.C.*, Attorney or Agent: Kenyon & Kenyon, New York, N.Y., Ex. Gp.: 3311, Requester: Benton S. Duffett, Burns, Doane, Swecker & Mathis, Alexandria, Va.,

5,166,178, Reexam. No. 90/004,459, Nov. 19, 1996, Cl. 514/573, OCULAR HYPOTENSIVE AGENTS, Ryuzo Ueno, et. al., Owner of Record: *R-Tech Ueno, Ltd., Osaka-Shi, Japan*, Attorney or Agent: Louis Gubinsky, Shugrue Mion Zino Mac Peak & Seas, Washington, D.C., Ex. Gp.: 1209, Requester: Owner

5,550,709, Reexam. No. 90/004,442, Nov. 29, 1996, Cl. 361/684, EXTERNAL STORAGE DEVICE, Hiroshi Iwasaki, Owner of Record: *Kabushiki Kaisha Toshiba, Kawasaki-Shi, Japan*, Attorney or Agent: Finnegan Henderson Farabow Garrett & Dunner, Washington, D.C., Ex. Gp.: 2103, Requester: Commissioner of Patents and Trademarks, Washington, D.C.

Notice of Expiration of Trademark Registrations Due To Failure to Renew

15 U.S.C. 1059 provides that each trademark registration may be renewed for periods of ten years from the end of the expiring period upon payment of the prescribed fee and the filing of an acceptable application for renewal. This may be done at any time within six months before the expiration of the period for which the registration was issued or renewed, or it may be done within three months after such expiration on payment of an additional fee.

According to the records of the Office, the trademark registrations listed below are expired due to failure to renew in accordance with 15 U.S.C. 1059.

TRADEMARK REGISTRATIONS WHICH EXPIRED SEPTEMBER 02, 1996 DUE TO FAILURE TO RENEW

Reg. Number	Serial Number	Reg. Date
107,461	71/087,546	11/30/1915
330,185	71/354,990	11/26/1935
330,186	71/354,991	11/26/1935
330,202	71/367,947	11/26/1935
330,204	71/367,949	11/26/1935
330,215	71/368,098	11/26/1935
330,237	71/367,582	11/26/1935
330,240	71/367,635	11/26/1935
330,247	71/366,918	11/26/1935
330,251	71/366,977	11/26/1935
330,284	71/366,085	11/26/1935
330,323	71/362,502	11/26/1935
330,333	71/360,786	11/26/1935
330,352	71/366,418	11/26/1935
616,715	71/683,456	11/29/1955
616,723	71/669,544	11/29/1955
616,724	71/669,546	11/29/1955
616,726	71/675,618	11/29/1955
616,729	71/677,169	11/29/1955
616,730	71/677,336	11/29/1955
616,738	71/680,308	11/29/1955
616,751	71/680,524	11/29/1955
616,755	71/683,381	11/29/1955
616,757	71/683,649	11/29/1955
616,768	71/668,879	11/29/1955
616,774	71/675,174	11/29/1955
616,776	71/682,755	11/29/1955
616,782	71/656,420	11/29/1955
616,784	71/668,334	11/29/1955
616,790	71/680,893	11/29/1955
616,801	71/678,758	11/29/1955
616,815	71/678,859	11/29/1955
616,831	71/680,465	11/29/1955
616,834	71/646,826	11/29/1955
616,843	71/652,492	11/29/1955
616,846	71/674,042	11/29/1955
616,854	71/648,553	11/29/1955
616,856	71/648,896	11/29/1955
616,860	71/671,764	11/29/1955
616,863	71/673,037	11/29/1955
616,875	71/679,407	11/29/1955
616,897	71/680,043	11/29/1955
616,902	71/680,256	11/29/1955
616,903	71/680,276	11/29/1955
616,907	71/680,537	11/29/1955
616,914	71/675,844	11/29/1955
616,916	71/679,702	11/29/1955
616,919	71/667,893	11/29/1955

Reg. Number	Serial Number	Reg. Date	1,025,707	73/038,825	11/25/1975
616,920	71/667,894	11/29/1955	1,025,708	73/016,883	11/25/1975
616,921	71/667,896	11/29/1955	1,025,710	73/018,441	11/25/1975
616,922	71/667,897	11/29/1955	1,025,711	73/027,124	11/25/1975
616,923	71/679,398	11/29/1955	1,025,712	73/027,132	11/25/1975
616,941	71/667,230	11/29/1955	1,025,714	73/012,821	11/25/1975
616,942	71/670,137	11/29/1955	1,025,715	73/014,528	11/25/1975
616,943	71/670,295	11/29/1955	1,025,718	73/020,486	11/25/1975
616,948	71/675,277	11/29/1955	1,025,719	73/029,113	11/25/1975
616,953	71/632,232	11/29/1955	1,025,720	73/029,907	11/25/1975
616,955	71/509,571	11/29/1955	1,025,722	73/031,170	11/25/1975
616,956	71/602,194	11/29/1955	1,025,724	73/032,953	11/25/1975
616,964	71/673,647	11/29/1955	1,025,728	73/039,031	11/25/1975
616,967	71/626,382	11/29/1955	1,025,729	73/039,048	11/25/1975
616,968	71/626,383	11/29/1955	1,025,733	73/003,459	11/25/1975
616,975	71/679,077	11/29/1955	1,025,734	73/006,943	11/25/1975
616,976	71/679,078	11/29/1955	1,025,735	73/036,773	11/25/1975
616,979	71/681,979	11/29/1955	1,025,738	73/050,263	11/25/1975
616,985	71/674,425	11/29/1955	1,025,739	73/034,417	11/25/1975
616,987	71/644,250	11/29/1955	1,025,743	73/021,267	11/25/1975
616,991	71/664,535	11/29/1955	1,025,746	73/036,045	11/25/1975
617,012	71/656,263	11/29/1955	1,025,749	73/042,367	11/25/1975
617,016	71/675,026	11/29/1955	1,025,750	73/044,372	11/25/1975
617,019	71/688,043	11/29/1955	1,025,751	73/044,377	11/25/1975
1,025,519	73/004,014	11/25/1975	1,025,752	73/047,537	11/25/1975
1,025,524	73/017,705	11/25/1975	1,025,756	73/036,988	11/25/1975
1,025,525	73/018,313	11/25/1975	1,025,757	73/038,061	11/25/1975
1,025,529	73/022,276	11/25/1975	1,025,759	73/019,447	11/25/1975
1,025,537	73/031,791	11/25/1975	1,025,764	73/009,527	11/25/1975
1,025,538	73/032,313	11/25/1975	1,025,767	73/025,016	11/25/1975
1,025,547	73/039,530	11/25/1975	1,025,769	73/037,701	11/25/1975
1,025,551	73/046,536	11/25/1975	1,025,778	73/016,908	11/25/1975
1,025,564	73/002,941	11/25/1975	1,025,781	73/018,648	11/25/1975
1,025,566	73/012,941	11/25/1975	1,025,782	73/018,734	11/25/1975
1,025,568	73/016,541	11/25/1975	1,025,791	73/033,417	11/25/1975
1,025,570	73/016,646	11/25/1975	1,025,792	73/034,649	11/25/1975
1,025,572	73/016,945	11/25/1975	1,025,794	73/037,231	11/25/1975
1,025,573	73/017,001	11/25/1975	1,025,795	73/037,321	11/25/1975
1,025,584	73/031,984	11/25/1975	1,025,796	73/037,550	11/25/1975
1,025,590	73/041,082	11/25/1975	1,025,798	73/039,795	11/25/1975
1,025,592	73/046,503	11/25/1975	1,025,799	73/042,119	11/25/1975
1,025,595	73/048,258	11/25/1975	1,025,800	73/042,323	11/25/1975
1,025,597	73/048,799	11/25/1975	1,025,806	73/045,695	11/25/1975
1,025,598	73/048,924	11/25/1975	1,025,808	73/045,698	11/25/1975
1,025,603	73/049,592	11/25/1975	1,025,809	73/045,699	11/25/1975
1,025,604	73/049,822	11/25/1975	1,025,814	73/005,495	11/25/1975
1,025,609	73/022,277	11/25/1975	1,025,817	73/013,222	11/25/1975
1,025,610	73/028,763	11/25/1975	1,025,821	73/031,219	11/25/1975
1,025,611	73/029,064	11/25/1975	1,025,826	73/039,191	11/25/1975
1,025,612	73/029,223	11/25/1975	1,025,832	73/034,014	11/25/1975
1,025,615	73/036,475	11/25/1975	1,025,833	73/035,124	11/25/1975
1,025,620	73/039,371	11/25/1975	1,025,835	73/037,367	11/25/1975
1,025,626	73/049,517	11/25/1975	1,025,839	73/039,665	11/25/1975
1,025,629	73/020,404	11/25/1975	1,025,841	73/049,339	11/25/1975
1,025,630	73/020,406	11/25/1975	1,025,843	73/027,662	11/25/1975
1,025,633	73/012,148	11/25/1975	1,025,846	73/045,504	11/25/1975
1,025,635	73/027,875	11/25/1975	1,025,847	73/045,505	11/25/1975
1,025,636	73/028,487	11/25/1975	1,025,848	73/047,418	11/25/1975
1,025,637	73/039,042	11/25/1975	1,025,849	73/048,419	11/25/1975
1,025,638	73/040,283	11/25/1975	1,025,852	73/031,513	11/25/1975
1,025,645	73/002,591	11/25/1975	1,025,859	73/046,216	11/25/1975
1,025,650	73/019,336	11/25/1975	1,025,860	73/003,041	11/25/1975
1,025,656	73/027,116	11/25/1975	1,025,862	73/010,328	11/25/1975
1,025,659	73/035,956	11/25/1975	1,025,863	73/010,574	11/25/1975
1,025,660	73/036,818	11/25/1975	1,025,865	73/020,449	11/25/1975
1,025,663	73/036,897	11/25/1975	1,025,866	73/024,064	11/25/1975
1,025,666	73/038,541	11/25/1975	1,025,870	73/026,615	11/25/1975
1,025,671	73/041,231	11/25/1975	1,025,871	73/031,031	11/25/1975
1,025,678	73/048,968	11/25/1975	1,025,872	73/031,326	11/25/1975
1,025,681	73/019,052	11/25/1975	1,025,874	73/043,000	11/25/1975
1,025,685	73/031,270	11/25/1975	1,025,878	73/024,102	11/25/1975
1,025,686	73/032,659	11/25/1975	1,025,880	73/029,929	11/25/1975
1,025,691	73/040,997	11/25/1975	1,025,884	73/036,578	11/25/1975
1,025,698	73/032,237	11/25/1975	1,025,886	73/043,059	11/25/1975
1,025,699	73/033,412	11/25/1975	1,025,887	73/007,811	11/25/1975
1,025,700	73/035,258	11/25/1975	1,025,888	73/019,058	11/25/1975
1,025,702	73/029,666	11/25/1975	1,025,892	73/041,631	11/25/1975
1,025,704	73/049,556	11/25/1975	1,025,895	73/021,656	11/25/1975
			1,025,899	73/036,309	11/25/1975

Reg. Number	Serial Number	Reg. Date
1,025,900	73/036,310	11/25/1975
1,025,903	73/035,173	11/25/1975
1,025,905	73/011,672	11/25/1975
1,025,906	73/014,297	11/25/1975
1,025,908	73/018,858	11/25/1975
1,025,924	73/039,931	11/25/1975
1,025,925	73/039,932	11/25/1975
1,025,928	73/041,604	11/25/1975
1,025,930	73/044,867	11/25/1975
1,025,933	72/420,906	11/25/1975
1,025,938	72/458,380	11/25/1975
1,025,942	72/446,648	11/25/1975
1,025,947	72/461,497	11/25/1975
1,025,949	72/429,550	11/25/1975
1,025,950	72/423,176	11/25/1975
1,025,951	72/442,063	11/25/1975
1,025,952	72/370,162	11/25/1975
1,025,954	72/448,580	11/25/1975
1,025,963	73/034,117	11/25/1975
1,025,965	73/016,821	11/25/1975
1,025,966	73/019,689	11/25/1975
1,025,968	73/022,242	11/25/1975
1,025,974	73/036,559	11/25/1975

Service by Publication

A petition to cancel the registrations identified below having been filed, and the notice of such proceedings sent by certified mail to registrants at the last known address having been returned by the Postal Service as undeliverable, notice is hereby given that unless the registrants listed herein, their assigns or legal representatives, shall enter an appearance within thirty days of this publication, the cancellation will proceed as in the case of default.

Beauty Concepts Pty. Ltd., McLean, Va., Reg. No. 1,598,057, for the mark "SUN BALANCE", Canc. No. 24,625.

Weinmann Aktiengesellschaft, New York, N.Y., Reg. No. 1,114,056, for the mark "WEINMANN CARRERA", Canc. No. 25,423.

Exquisite Form Industries, Inc., Pelham Manor, N.Y., Reg. No. 660,160, for the mark "CO STAR" and Design, Canc. No. 25,216.

Colony Sportswear, Inc., Statesville, N.C., Reg. No. 1,771,531, for the mark "COLONY BAY", Canc. No. 23,908.

Pet Peeve, Inc., Hopkins, Minn., Reg. No. 1,144,341, for the mark "PET PEEVE AND DESIGN", Canc. No. 23,902.

Margaret Parker dba Lew Parker Industries, Birmingham, Ala., Reg. No. 677,935, for the mark "DELAY", Canc. No. 25,206.

JEAN BROWN
Technical Support Manager,
Trademark Trial
and Appeal Board, for
ROBERT M. ANDERSON
Deputy Assistant Commissioner
for Trademarks

Service by Publication

A petition to cancel the registrations identified below having been filed, and a copy of the petitions together with the notice of institution of such proceeding is being sent to registrant at its last known address. Simultaneously therewith, notice is hereby given that unless the registrants listed herein, their assigns or legal representatives, shall enter an appearance within thirty days of this publication, or unless an answer or other response to the petition is filed within forty days after the

mailing of the institution notice, or within an extension of time therefor, the cancellation will proceed as in the case of default.

Aceco Inc., Houston, Tex., Reg. No. 1,391,871, for the mark "AUTO CHECK" and design, Canc. No. 25,370.

Aceco Inc., Houston, Tex., Reg. No. 1,391,870, for the mark "AUTO CHECK", Canc. No. 25,371.

JEAN BROWN
Technical Support Manager,
Trademark Trial
and Appeal Board, for
ROBERT M. ANDERSON
Deputy Assistant Commissioner
for Trademarks

Registration To Practice

The following person successfully passed the registration examination that was held April 13, 1994, and has been given provisional recognition pursuant to 37 CFR 10.9(a) to prepare and prosecute patent applications before the Office until applicant's registration certificate is mailed to applicant. Final approval for registration is subject to establishing to the satisfaction of the Director of the Office of Enrollment and Discipline that the person seeking registration is of good moral character and repute. [37 CFR 10.7(a)]. Accordingly, any information tending to affect the eligibility of the following applicant on moral, ethical, or other grounds should be furnished to the Director, Office of Enrollment and Discipline on or before February 14, 1997.

Horie, Tadashi, 441 E. Erie, #5803, Chicago, Ill., 60611

October 23, 1996

KAREN L. BOVARD, Director
Office of Enrollment and Discipline

Registration To Practice

The following person successfully passed the registration examination that was held November 2, 1994, and has been given provisional recognition pursuant to 37 CFR 10.9(a) to prepare and prosecute patent applications before the Office until applicant's registration certificate is mailed to applicant. Final approval for registration is subject to establishing to the satisfaction of the Director of the Office of Enrollment and Discipline that the person seeking registration is of good moral character and repute. [37 CFR 10.7(a)]. Accordingly, any information tending to affect the eligibility of the following applicant on moral, ethical, or other grounds should be furnished to the Director, Office of Enrollment and Discipline on or before February 14, 1997.

Yip, Gwendolyn H., 129 Truman Rd., Newton, Mass., 02159

October 23, 1996

KAREN L. BOVARD, Director
Office of Enrollment and Discipline

Erratum

John M. Pollaro (Reg. No. 27,670) and Thomas J. Vetter (Reg. No. 30,597) were listed in the Official Gazette dated September 3, 1996, as being removed from the register. Their names were published in error. We regret any inconvenience the publication may have caused.

December 6, 1996

KAREN L. BOVARD, Director
Office of Enrollment & Discipline

Reinstatement to Register

The following list of persons, whose names have been previously removed from the Register of Attorneys and Agents pursuant to the provisions of 37 CFR 10.11(b), have been reinstated in view of the required fee and information they furnished to the Office of Enrollment and Discipline.

Bailey, Gary C., Eastman Chemical Co., P.O. Box 511, Kingsport, Tenn., 37662

Bell, Craig M., Dann, Dorfman, Herrell & Skillman, 1601 Market St., Suite 720, Philadelphia, Pa., 19102

Corum, William A., 1103 Russell Dr., Highland Beach, Fla., 33487

Dent, Boyce C., The Ward Machinery Co., Law Dept., 10615 Beaver Dam Rd., Cockeysville, Md., 21030

Donofrio, John, Allied Signal Inc., P.O. Box 2245, 101 Columbia Rd., Morristown, N.J., 07962

Flynn, Brian J., Nanometrics Inc., P.O. Box 61704, Sunnyvale, Calif., 94088

Kasell, Brian W., Brobeck, Phleger & Harrison, 550 S. Hope St., Ste. 2100, Los Angeles, Calif., 90071

Langley, Jr., Harry Dale, 600 Congress Ave., 1600 One American Cir., Austin, Tex., 78701

Madden, Thomas J., Venable, Baetjer, Howard & Civiletti, Suite 1000, 1200 New York Ave., N.W., Washington, D.C., 20005

Moran, John F., Walter Reed Army Institute of Research, Attn: MCMR-UWZ-I, Washington, D.C., 20307

Motsenbocker, Marvin A., Foley & Lardner, 3000 K St., N.W., Suite 500, Washington, D.C., 20007

Mueller, Robert W., Greenblum & Bernstein, P.L.C., 1941 Roland Clarke Pl., Reston, Va., 20191

Murray, Kittie A., 24 Main St., P.O. Box 668, Henniker, N.H., 03242

Pawl, Marc C., 2 Delaware Rd., Whitehouse Station, N.J., 08889

Phillips, Stephen J., Intergraph Corp., Mailstop HQ 034, Huntsville, Ala., 35894

Ray, Patricia L., 990 Bendemeer Rd., 1233, Singapore

Rueggegger, Martin C., Piedmont Natural Gas Co., Inc., 1915 Rexford Rd., Charlotte, N.C., 28211

Sabath, Robert P., Oblon, Spivak, McClelland, Maier & Neustadt, P.C., 224 Airport Pkwy., Ste. 300, San Jose, Calif., 95110

Sachar, Surinder, Oblon, Spivak, McClelland, Maier & Neustadt, P.C., 1755 Jefferson Davis Hwy., Ste. 400, Arlington, Va., 22202

Sadler, Clifford Lincoln, 50 Moorland Dr., Grosse Pointe Shore, Mich., 48236

Sako, Katie E., Microsoft Corp., One Microsoft Way, Redmond, Wash., 98052

Sander, Dorothy L., 12 George St., #4B, Charleston, S.C., 29401

Sarnoff, Joshua D., Moran, Lewis & Bockius, 1800 M St., N.W., Washington, D.C., 20036

Saxe, Jon Sheldon, Saxe Associates, 435 Old Oak Ct., Los

Altos, Calif., 94022

Schaefer, Robert K., 7735 Falstaff Rd., McLean, Va., 22102

Schaukowitz, Carl, Oliff & Berridge, 700 S. Washington St., Alexandria, Va., 22314

Schechter, Minda R., Graham & James, 801 S. Figueroa St., 14th Flr. Los Angeles, Calif., 90017

Schnurr, Mary J., American National Can Co., 8770 W. Bryn Mawr Ave., Chicago, Ill., 60631

Schroeder, Larry C., Texas Instruments, Inc., P.O. Box 655474, M.S. 241, Dallas, Tex., 75265

Schwartz, Herbert Frederick, Fish & Neave, 1251 Avenue of the Americas, New York, N.Y., 10020

Seaburg, Jean, Olds & Associates, P.A., 10800 Lyndale Ave., S., Minneapolis, Minn., 55420

Seas, Jr., Robert John, Sughrue, Mion, Zinn, Mac Peak & Seas, 2100 Pennsylvania Ave., N.W., Ste. 800, Washington, D.C., 20037

Seeley, Mark V., Intel Corp., Legal Dept., 2200 Mission College Blvd., M.S. S.C., 4-202, Santa Clara, Calif., 95052

Sender, Stuart D., Kaye, Scholer, Fierman, Hays & Handler, L.L.P., 425 Park Ave., New York, N.Y., 10022

Serbin, David J., Leydig Voigt & Mayer, 700 Thirteenth St., N.W., Ste. 300, Washington, D.C., 20005

Shea, II, Timothy J., Perkins, Smith & Cohen, One Beacon St., Boston, Mass., 02108

Shehata, Magdy W., 6071 Joust Lane, Alexandria, Va., 22315

Sherrill, Michael S., 4756 Banning Ave., Ste. 200, White Bear Lake, Minn., 55110

Siegel, Jaime A., Kenyon & Kenyon, One Broadway, New York, N.Y., 10004

Sipio, William J., Pennie & Edmonds, 1155 Avenue of the Americas, New York, N.Y., 10036

Sirota, Neil P., Brumbaugh, Graves, Donohue & Raymond, 30 Rockefeller Plaza, New York, N.Y., 10112

Smith, Charles B., 401 East Linton Blvd., Apt. 518, Delray Beach, Fla., 33483

Smith, Norman R., B.F. Goodrich, 9911 Brecksville Rd., Cleveland, Ohio, 44141

Smith, Pei-Pei C., Logos Research Systems, Inc., 715 S.E. Fidalgo Ave., Oak Harbor, Wash., 98277

Sprunt, Diane H., 3385 S.W. Vista Dr., Portland, Oreg., 97225

Stahl, Scott B., Texas Instruments, Inc., P.O. Box 655474, M.S. 219, Dallas, Tex., 75265

Stanback, Willard A., 409 N. Pine St., Langhorne, Pa., 19047

Stanford, Gary R., Stanford & Bennett, L.L.P., 221 W. 6th St., Ste. 1550, Austin, Tex., 78701

Starkweather, Michael W., CTS Corp., 905 W. Blvd., N., Elkhart, Ind., 46514

Steinmetz, Jr., Richard C., Allen-Bradley Co., Inc., 1201 S. Second St., Milwaukee, Wisc., 53204

Stephens, Lawrence K., Cooley Goodward, L.L.P., Five Palo Alto Sq., 3000 El Camino Real, Palo Alto, Calif., 94306

Stevens, Lauren L., Affymax Research Institute, 4001 Miranda Ave., Palo Alto, Calif., 94304

Stewart, Richard C., Champion International Corp., One Champion Plaza, Stamford, Conn., 06921

Stroup, Sharon E., 1411 Grady Randall Ct., Mc Lean, Va., 22101

Strozier, Robert W., Gilbreth & Strozier, P.O. Box 61305, Houston, Tex., 77208

Strunk, Stephen S., IBM Corp., P.O. Box 218, M.S. 39-277, Yorktown Heights, N.Y., 10598

Suter, David L., The Procter & Gamble Co., Miami Valley Labs., P.O. Box 538707, Cincinnati, Ohio, 45253

Swiatek, Mafia S., Flehr Hohbach Test Albriton & Herbert, 850 Hansen Way, Suite 200, Palo Alto, Calif., 94304

Weisz, Paul B., Foxdale Village, A1500 E. Marylyn Ave., State College, Pa., 16801

Wright, Stephen R., Andrews & Kurth, L.L.P., 4200 Texas Commerce Tower, Houston, Tex., 77002

December 6, 1996

KAREN L. BOVARD, *Director*
Office of Enrollment & Discipline

Notice of Policy Change - Change in Time Requirement For Diligently Monitoring Trademark Applications and Registrations

The timeliness standard for due diligence in trademark cases is extended to twelve months.

On October 27, 1992, the Assistant Commissioner for Trademarks announced that applicants and registrants had a duty to monitor the status of their pending trademark application and registration matters every six months. 1143 TMOG 73 (October 27, 1992); see Trademark Manual of Examining Procedure, § 413 (2d ed. May 1993). In response to public comment, and effective immediately, the Office is extending the timeliness standard for due diligence to twelve months.

The PTO generally processes applications, responses and other papers in the order in which they are received in the Office. In addition, examining attorneys are required to act on new cases within 14 days of receipt and amended cases within 21 days of receipt. Accordingly, applicants and registrants can expect to receive notice concerning their filings within predictable time periods. However, delays in processing certain types of trademark filings have led the Office to re-evaluate its policy regarding due diligence in trademark cases.

Since it is reasonable to expect some notice from the PTO about a pending matter within twelve months of the filing or receipt of any documents, a party who has not received the expected written action or telephone call from the PTO within that time frame is considered on notice that the filing may have become lost. The party awaiting notification has the burden of inquiring as to the cause of the delay. In order to be considered diligent in the monitoring of applications or registrations, parties expecting notification from the PTO should inquire within twelve months. **Waiting until the end of the twelve-month period is not recommended.** Parties should inquire as soon as they suspect that a problem exists.

If nothing has been received from the PTO within a twelve-month period, the party awaiting notification has the burden of inquiring as to the status. Should the status inquiry reveal that the relevant document is lost, or some other problem exists, a petition to the Commissioner, or other required action, should be filed within 60 days. 37 CFR § 2.146(d). Failure to act diligently and to follow up with the appropriate action may result in denial of the requested relief.

Whenever possible, status inquiries should be made by calling the Trademark Status Line at (703) 305-8747. The Status Line provides the current status and status date of all active federal trademark applications and registrations, and is avail-

able from 6:30 a.m. until midnight, Eastern Time, Monday through Friday. Status Line information is limited to Status Code items, e.g., whether or not an Office action has been mailed.

Although written status inquiries are discouraged, they may be appropriate when a party has difficulty interpreting the Status Line information. In lieu of written status inquiries, clarification and additional information regarding a file may be obtained by contacting the Trademark Assistance Center at (703) 308-9000.

For further information regarding this Notice, please contact Nancy Omelko, Administrator for Petitions, Office of the Assistant Commissioner for Trademarks, at (703) 308-8910, ext. 39.

December 9, 1996

PHILIP G. HAMPTON, II
Assistant Commissioner for Trademarks

**Department of Commerce
Patent and Trademark Office**

37 CFR Part 1
[Docket No. 961030301-6301-01]
RIN 0651-AA55

Changes in Signature and Filing Requirements for Correspondence Filed in the Patent and Trademark Office

Agency: Patent and Trademark Office, Commerce.
Action: Correcting amendment.

Summary: This document contains a further correction to the final regulations which were published Friday, October 22, 1993 (58 FR 54494). The regulations related to the changes in signature and filing requirements for correspondence filed in the Patent and Trademark Office. The correction re-inserts part of a rule (37 CFR 1.741) that was inadvertently deleted when the rule was amended.

Effective Date: December 3, 1996.

For Information Contact: Karin Tyson by telephone at (703) 305-9285; by mail marked to her attention and addressed to the Assistant Commissioner for Patents, Box COMMENTS - PATENTS, Washington, D.C. 20231; or by fax marked to her attention at (703) 308-6916.

**Supplementary Information:
Background**

The final regulation that is the subject of this correction was revised to change "Certificate of Mailing" to "Certificate of Mailing or Transmission" in 37 CFR 1.741(a) as published at 58 FR 54494 (October 22, 1993), corrected at 58 FR 64154 (December 6, 1993), and in the Official Gazette of the Patent and Trademark Office at 1156 Off. Gaz. Pat. Office 61 (November 16, 1993), corrected at 1157 Off. Gaz. Pat. Office 87 (December 28, 1993).

Need for Correction

As published, the final regulation inadvertently deleted the last sentence of the first paragraph of paragraph (a) of Rule 741 and paragraphs (a)(1) — (a)(6).

Paperwork Reduction Act Statement

Notwithstanding any other provision of law, no person is required to respond to nor shall a person be subject to a penalty for failure to comply with a collection of information subject to the requirements of the Paperwork Reduction Act (PRA) unless that collection of information displays a currently valid OMB control number.

OMB has approved the collection of the information required by this rule under OMB # 0651-0020.

List of Subjects in 37 CFR Part 1

Administrative practice and procedure, Freedom of Information, inventions and patents, Reporting and record keeping

requirements.

PART 1—RULES OF PRACTICE IN PATENT CASES

Accordingly, 37 CFR Part 1 is corrected by making the following correcting amendment:

1. The authority citation for 37 CFR part 1 continues to read as follows:

Authority: 35 U.S.C. 6, unless otherwise noted.

2. In § 1.741, paragraph (a) is revised to read as follows:

§ 1.741 *Filing date of application.*

(a) The filing date of an application for extension of a patent is the date on which a complete application is received in the Patent and Trademark Office or filed pursuant to the "Certificate of Mailing or Transmission" procedures of 37 CFR 1.8 or "Express Mail" provisions of 37 CFR 1.10. A complete application shall include:

- (1) An identification of the approved product;
- (2) An identification of each Federal statute under which regulatory review occurred;
- (3) An identification of the patent for which an extension is being sought;
- (4) An identification of each claim of the patent which claims the approved product or a method of using or manufacturing the approved product;
- (5) Sufficient information to enable the Commissioner to determine under 35 U.S.C. 156 subsections (a) and (b) the eligibility of a patent for extension and the rights that will be derived from the extension and information to enable the Commissioner and the Secretary of Health and Human Services or the Secretary of Agriculture to determine the length of the regulatory review period; and
- (6) A brief description of the activities undertaken by the marketing applicant during the applicable regulatory review period with respect to the approved product and the significant dates applicable to such activities.

November 26, 1996

BRUCE A. LEHMAN
*Assistant Secretary of Commerce and
Commissioner of Patents and Trademarks*

Erratum

In the Notice of Certificate of Correction appearing at 1191 O.G. 3, delete all reference to Patent No. B1-4,974,979 of November 15, 1996, since no Certificate of Correction was granted.

**Certificate of Correction
For Week of December 31, 1996**

D. 370,910	5,286,741	5,403,908	5,450,056
4,451,745	5,286,743	5,404,473	5,450,445
4,816,017	5,293,685	5,406,605	5,452,344
4,846,806	5,311,601	5,420,583	5,452,703
4,945,045	5,316,300	5,427,930	5,453,304
4,983,383	5,316,487	5,429,056	5,453,356
5,074,991	5,335,865	5,429,787	5,458,089
5,136,502	5,344,712	5,430,602	5,458,639
5,165,449	5,358,891	5,430,674	5,459,470
5,171,534	5,360,820	5,434,093	5,460,952
5,184,147	5,379,415	5,435,990	5,460,969
5,195,049	5,384,367	5,436,576	5,461,445
5,241,334	5,386,181	5,438,248	5,462,576
5,248,909	5,388,298	5,438,370	5,463,271
5,258,943	5,389,818	5,438,546	5,464,239
5,262,007	5,390,718	5,438,746	5,464,264
5,272,735	5,391,135	5,439,647	5,465,891
5,273,208	5,392,437	5,442,300	5,472,869
5,278,995	5,398,789	5,443,279	5,473,552
5,280,510	5,399,010	5,446,348	5,473,756

5,474,765	5,517,136	5,534,956	5,550,144
5,475,456	5,517,388	5,535,431	5,550,220
5,476,663	5,517,452	5,535,493	5,550,696
5,477,150	5,517,530	5,535,577	5,550,865
5,477,262	5,518,180	5,535,849	5,550,930
5,477,979	5,518,373	5,536,323	5,550,975
5,478,329	5,518,516	5,536,449	5,551,211
5,480,030	5,518,964	5,536,709	5,552,008
5,481,686	5,519,517	5,537,517	5,552,256
5,481,725	5,519,777	5,537,598	5,552,627
5,483,102	5,520,245	5,537,882	5,552,834
5,483,777	5,520,882	5,538,236	5,553,231
5,486,751	5,520,980	5,538,878	5,553,314
5,487,289	5,521,027	5,539,081	5,553,375
5,488,446	5,521,288	5,539,308	5,553,660
5,488,709	5,521,386	5,539,524	5,553,689
5,489,326	5,521,766	5,539,526	5,553,793
5,489,884	5,522,046	5,539,553	5,553,835
5,489,949	5,522,995	5,539,555	5,554,035
5,490,022	5,523,049	5,539,683	5,554,368
5,490,109	5,523,054	5,540,945	5,554,479
5,493,377	5,523,283	5,541,228	5,555,143
5,493,514	5,523,291	5,541,400	5,556,441
5,493,683	5,523,678	5,541,829	5,556,855
5,497,039	5,523,888	5,542,351	5,557,012
5,497,620	5,524,180	5,542,445	5,557,178
5,499,356	5,524,219	5,543,490	5,557,625
5,500,842	5,524,729	5,544,343	5,557,700
5,501,417	5,526,242	5,543,886	5,558,092
5,502,441	5,526,272	5,545,030	5,558,463
5,503,115	5,526,437	5,545,087	5,558,667
5,503,441	5,526,881	5,545,222	5,559,131
5,503,963	5,527,300	5,545,736	5,560,028
5,504,839	5,528,280	5,545,997	5,560,131
5,505,227	5,528,281	5,546,141	5,560,941
5,506,923	5,528,715	5,546,213	5,561,002
5,507,143	5,528,914	5,546,364	5,561,408
5,508,060	5,529,352	5,546,373	5,561,705
5,508,250	5,529,406	5,546,389	5,561,978
5,508,252	5,529,776	5,546,513	5,562,022
5,508,281	5,530,135	5,546,672	5,562,167
5,508,418	5,530,262	5,546,770	5,562,232
5,508,648	5,530,462	5,546,929	5,562,439
5,509,913	5,531,783	5,547,779	5,562,742
5,510,504	5,532,397	5,547,961	5,563,029
5,510,818	5,532,861	5,548,026	5,564,203
5,511,514	5,532,990	5,548,091	5,564,244
5,512,893	5,533,301	5,548,254	5,564,409
5,513,007	5,533,407	5,548,370	5,564,465
5,513,518	5,533,417	5,548,372	5,564,856
5,514,304	5,533,499	5,548,505	5,564,961
5,514,712	5,533,591	5,548,730	5,564,992
5,515,361	5,534,373	5,548,736	5,567,832
5,515,719	5,534,464	5,549,843	5,568,142
5,516,600	5,534,473	5,549,960	5,571,366
5,516,865	5,534,525	5,550,130	

Summary of Final Decisions
Issued by the
Trademark Trial and Appeal Board
November 4-8, 1996

Date Issued	Type of Case ¹⁾	Proceeding or App'n No.	Party/Parties	Issue	TTAB Decision	Opposer's Mark and Goods/Services	Applicant's Mark and Goods/Services	Mark and Goods Cited by Examining Attorney	Recommended for Publication
11-5	OPP	91,722	Warner-Lambert Co. v. Richardson-Vicks Inc.	2(d)	Opposition Sustained	"ACUPRIL" [coronary preparations]	"ACUPRIL" [low dosage aspirin]		No
11-7	EX	74/503,251	Stewart Electronics Corp.	2(d)	Refusal Affirmed		"STEWART ELECTRONICS" [professional electronic audio products, namely, power amplifiers, mixers, digital-to-analog converters, power supplies, speaker connectors and impedance matching and single polarity matching electronic interface box, etc.]	"STEWART" [radios, tape recorders, and tape players]	No
11-8	EX EX	74/482,238 74/482,242	Internet Services Corp.	2(e)(1)	Refusal Reversed (in both cases)		"INTERACTIVE DISTRIBUTION" [pre-recorded audio and audio-video tapes and CDs, books and magazines, etc.—all featuring sales, training, educational, and motivational information and advice for entrepreneurs and businesswomen, conducting seminars, etc. in the field of business operation, motivation, etc.; wholesale sales and distribution services in connection with the applicant's goods]		No
11-8	EX	74/352,450	Collegeville Flag & Mfg. Co.	2(d)	Refusal Affirmed		"ACADEMY" [cloth flags]	"ACADEMY TENT AND CANVAS" [textile banners and pennants]	No

(1) EX = EX PARTE APPEAL; OPP = OPPOSITION; CANCELLATION; CONC = CONCURRENT USE; (S) = SUMMARY JUDGMENT; (R) = REQ FOR RECONSIDERATION

SPECIAL BOXES FOR PATENT MAIL

Special box designations should be used to allow forwarding of particular types of mail to the appropriate areas as quickly as possible. Such mail is forwarded to the appropriate area without being opened. Only the specified type of document should be placed in an envelope addressed to one of these special boxes. If any documents other than the specified type identified for each special box are addressed to that box, they will be significantly delayed in reaching the appropriate area for which they are intended.

Please address mail as follows:

Box _____
Assistant Commissioner for Patents
Washington, D.C. 20231

Box Designations	Explanation
Box 7	Reissue applications for patents involved in litigation and subsequently filed related papers.
Box 12	Contributions to the Examiner Education Program.
Box 313b	Petitions under 37 CFR 1.313(b) to withdraw a patent application from issue after payment of the issue fee and any papers associated with the petition, including papers necessary for filing a continuing application.
Box AF	Expedited procedure for processing amendments and other responses after final rejection.
Box Comments Patents	Public comments regarding patent related regulations and procedures.
Box DAC	Petitions decided by the Office of Petitions including petitions to revive and petitions to accept late payment of issue fees or maintenance fees.
Box DD	Disclosure Documents or materials related to the Disclosure Document Program.
Box FWC	Requests for File Wrapper Continuation Applications (under 37 CFR 1.62).
Box Issue Fee	All communications following the receipt of a PTOL-85, "Notice of Allowance and Issue Fee Due," and prior to the issuance of a patent should be addressed to Box Issue Fee, unless advised to the contrary. Assignments are the exception. Assignments should be submitted in a separate envelope and not be sent to Box Issue Fee.
Box Missing Parts	Response to the Notice to File Missing Parts of Application and associated papers and fees.
Box MPEP	Submissions concerning the Manual of Patent Examining Procedures.
Box Non-Fee Amendment	Non-fee amendments to patent applications.
Box PATENT APPLICATION	(Use Box AF for responses after final rejection).
Box Patent Ext.	New patent applications and associated papers and fees.
Box PCT	Applications for patent term extension and any communications relating thereto.
Box Provisional Patent Application	Mail related to applications filed under the Patent Cooperation Treaty.
Box Reconstruction	The filing of all provisional patent applications and any communications relating thereto.
Box Reexam	Correspondence pertaining to the reconstruction of lost patent files.
Box Sequence	Requests for Reexamination for <i>original</i> request papers <i>only</i> .
Box SN	Submission of diskette for biotechnical application.
	For fee and petitions under 37 CFR 1.182 to obtain date received and/or serial number for patent applications <i>prior</i> to the Office's standard notification (return post card or the official "Filing Receipt," "Notice to File Missing Parts," or "Notice of Incomplete Application").

SPECIAL BOXES FOR TRADEMARK MAIL

Special box designations should be used to allow forwarding of particular types of trademark mail to the appropriate areas as quickly as possible. In addition to these box designations, filers are encouraged to indicate whether the contents of the envelope contain a fee. Envelopes containing a fee should be marked "FEE;" envelopes not containing a fee should be marked "NO FEE." Box designations and "FEE/NO FEE" indicators should appear on the envelope as well as on the cover sheet or first page of any document.

Please address mail as follows:

Box _____
FEE (or NO FEE)
Assistant Commissioner for Trademarks
2900 Crystal Drive
Arlington, Virginia 22202-3513

Box Designations	Explanation
Box NEW APP FEE	New trademark applications and fees.
Box ITU FEE	Statements of Use (SOU) and extension requests.
Box TTAB FEE	Oppositions, cancellation petitions, and ex parte appeals.
Box TTAB NO FEE	Interferences, motions, and extension requests.
Box STATUS NO FEE	Written status inquiries.
Box POST REG FEE	Affidavits, renewals, corrections and amendments.
Box RESPONSES NO FEE	Responses to Examining Attorneys' Office actions and Post Registration actions.

SPECIAL BOXES APPLICABLE TO BOTH PATENT AND TRADEMARK MAIL

The following special box designations are applicable to both patent and trademark related mail, and the recommendations for "Special Boxes for Patent Mail" (above) should be followed for the types of mail listed below.

Please address mail as follows:

Box _____
Commissioner of Patents and Trademarks
Washington, D.C. 20231

Box Designations	Explanation
Box 3	Mail for the Office of Personnel from NFC.
Box 4	Mail for the Deputy Assistant Secretary of Commerce and Deputy Commissioner of Patents and Trademarks; Office of Legislative and International Affairs.
Box 6	Mail for the Office of Procurement.
Box 8	All papers for the Office of the Solicitor <i>except</i> communications relating to <i>pending litigation and disciplinary proceedings</i> ; papers relating to pending litigation in court cases shall be mailed only to Office of the Solicitor, P.O. Box 15667, Arlington, Virginia 22215 and papers relating to pending disciplinary proceedings before the Administrative Law Judge or the Commissioner shall be mailed only to the Office of the Solicitor, P.O. Box 16116, Arlington, Virginia 22215.
Box 9	Coupon orders for U.S. patent and trademark copies.
Box 10	Orders for certified copies of PTO documents.
Box 11	Electronic Ordering Service (EOS).
Box 13	Mail for the Employee and Labor Relations Division.
Box 14	Mail directed to the APS Contracts Office.
Box 16	Deposit Account Replenishment Checks.
Box 17	Invoices directed to the Office of Finance.
Box 171	Vacancy Announcement Applications.
Box Assignment	All assignment documents except those filed with new applications.
Box EEO	Mail for the Office of Civil Rights.
Box Interference	Communications relating to interferences and applications and patents involved in interference.
Box M Fee	Correspondence regarding patent maintenance fees and related matter.
Box OED	Mail for the Office of Enrollment and Discipline.

Reference Collections of U.S. Patents and Trademarks
Available for Public Use in Patent and Trademark Depository Libraries

The following libraries, designated as Patent and Trademark Depository Libraries (PTDLs), receive patent and trademark information in various formats from the U.S. Patent and Trademark Office. Many PTDLs have on file all full-text patents issued since 1790, trademarks published since 1872, and select collections of foreign patents. All PTDLs have both the patent and trademark sections of the *Official Gazette of the U.S. Patent and Trademark Office*. The full-text utility and design patents are distributed numerically on 16 mm microfilm, and plant patents on color microfiche. Patent and trademark search systems on CD-ROM (Compact Disc-Read Only) format are available at all PTDLs to increase utilization of and enhance access to the information found in patents and trademarks. It is through the CD-ROM systems that preliminary patent and trademark searches can be conducted through the numerically arranged collections.

All information is available for use by the public free of charge.

In addition, each PTDL offers reference publications which outline and provide access to the patent and trademark classification systems, as well as other documents and publications which supplement the basic search tools. PTDLs provide technical staff assistance in using all materials. Facilities for making paper copies of patent and trademark information are generally provided for a fee.

Since there are variations in the scope of patent and trademark collections among the PTDLs, and their hours of service to the public vary, anyone contemplating use of these collections at a particular library is urged to contact that library in advance about its collections, services, and hours in order to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Auburn University Libraries	(205) 844-1747
	Birmingham Public Library	(205) 226-3620
Alaska	Anchorage: Z.J. Loussac Public Library	(907) 562-7323
Arizona	Tempe: Noble Library, Arizona State University	(602) 965-7010
Arkansas	Little Rock: Arkansas State Library	(501) 682-2053
California	Los Angeles Public Library	(213) 228-7220
	Sacramento: California State Library	(916) 654-0069
	San Diego Public Library	(619) 236-5813
	San Francisco Public Library	(415) 557-4500
	Sunnyvale Center for Innovation, Invention and Ideas	(408) 730-7290
Colorado	Denver Public Library	(303) 640-6249
Connecticut	New Haven: Science Park Library	(203) 786-5447
Delaware	Newark: University of Delaware Library	(302) 831-2965
Dist. of Columbia	Washington: Howard University Libraries	(202) 806-7252
Florida	Fort Lauderdale: Broward County Main Library	(305) 357-7444
	Miami-Dade Public Library	(305) 375-2665
	Orlando: University of Central Florida Libraries	(407) 823-2562
	Tampa Campus Library, University of South Florida	(813) 974-2726
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4508
Hawaii	Honolulu: Hawaii State Public Library System	(808) 586-3477
Idaho	Moscow: University of Idaho Library	(208) 885-6235
Illinois	Chicago Public Library	(312) 747-4450
	Springfield: Illinois State Library	(217) 782-5659
Indiana	Indianapolis-Marion County Public Library	(317) 269-1741
	West Lafayette: Siegesmund Engineering Library, Purdue University	(317) 494-2872
Iowa	Des Moines: State Library of Iowa	(515) 281-4118
Kansas	Wichita: Ablah Library, Wichita State University	(316) 689-3155
Kentucky	Louisville Free Public Library	(502) 574-1611
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Maine	Orono: Raymond H. Fogler Library, University of Maine	(207) 581-1678
Maryland	College Park: Engineering and Physical Sciences Library, University of Maryland	(301) 405-9157
Massachusetts	Amherst: Physical Sciences Library, University of Massachusetts	(413) 545-1370
	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Ann Arbor: Media Union Library, University of Michigan	(313) 647-5735
	Big Rapids: Abigail S. Timme Library, Ferris State University	(616) 592-3602
	Detroit: Great Lakes Patent and Trademark Center	(313) 833-3379
Minnesota	Minneapolis Public Library and Information Center	(612) 372-6570
Mississippi	Jackson: Mississippi Library Commission	(601) 359-1036
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 390
Montana	Butte: Montana College of Mineral Science and Technology Library	(406) 496-4281
Nebraska	Lincoln: Engineering Library, University of Nebraska-Lincoln	(402) 472-3411
Nevada	Reno: University of Nevada, Reno Library	(702) 784-6500 Ext. 257
New Hampshire	Concord: New Hampshire State Library	(603) 271-2239
New Jersey	Newark Public Library	(201) 733-7782
	Piscataway: Library of Science and Medicine, Rutgers University	(908) 445-2895
New Mexico	Albuquerque: University of New Mexico General Library	(505) 277-4412
New York	Albany: New York State Library	(518) 474-5355
	Buffalo and Erie County Public Library	(716) 858-7101

Reference Collections of U.S. Patents and Trademarks Available for Public Use in Patent and Trademark Depository Libraries—(continued)

State	Name of Library	Telephone Contact
North Carolina North Dakota Ohio	New York Public Library (The Research Libraries)	(212) 592-7000
	Raleigh: D.H. Hill Library, North Carolina State University	(919) 515-3280
	Grand Forks: Chester Fritz Library, University of North Dakota	(701) 777-4888
	Akron - Summit County Public Library	(303) 643-9075
	Cincinnati and Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 292-6175
Oklahoma	Toledo/Lucas County Public Library	(419) 259-5212
	Stillwater: Oklahoma State University Center for International Trade Development	(405) 744-7086
	Portland: Paul L. Boley Law Library, Lewis & Clark College	(503) 768-6786
Oregon Pennsylvania	Philadelphia: The Free Library of	(215) 686-5331
	Pittsburgh, Carnegie Library of	(412) 622-3138
Puerto Rico Rhode Island South Carolina South Dakota	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
	Mayaguez General Library, University of Puerto Rico	(787) 832-4040 Ext. 3459
	Providence Public Library	(401) 455-8027
	Clemson University Libraries	(803) 656-3024
Tennessee	Rapid City: Devereaux Library, South Dakota	(605) 394-6822
	School of Mines and Technology	(901) 725-8877
Texas	Memphis & Shelby County Public Library and Information Center	(615) 322-2775
	Nashville: Stevenson Science Library, Vanderbilt University	(512) 495-4500
	Austin: McKinney Engineering Library, University of Texas at Austin	(512) 495-4500
	College Station: Sterling C. Evans Library, Texas A & M University	(409) 845-3826
	Dallas Public Library	(214) 670-1468
Utah Virginia	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
	Lubbock: Texas Tech University	Not Yet Operational
	Salt Lake City: Marriott Library, University of Utah	(801) 581-8394
	Richmond: James Branch Cabell Library, Virginia Commonwealth University	(804) 828-1104
Washington West Virginia Wisconsin	Seattle: Engineering Library, University of Washington	(206) 543-0740
	Morgantown: Evansdale Library, West Virginia University	(304) 293-2510
	Madison: Kurt F. Wendt Library, University of Wisconsin	(608) 262-6845
	Madison	(414) 286-3051
Wyoming	Milwaukee Public Library	(307) 237-4935
	Casper: Natrona County Public Library	(307) 237-4935

PATENT EXAMINING CORPS

BRUCE A. LEHMAN, Commissioner
LAWRENCE J. GOFFNEY Jr., Assistant Commissioner for Patents
EDWARD R. KAZENSKE, Deputy Assistant Commissioner for Patents
STEPHEN G. KUNIN, Deputy Assistant Commissioner for Patent Policy

PATENT EXAMINING GROUPS	Phone number Area Code 703	New Case Date*
CHEMICAL EXAMINING GROUPS		
GENERAL METALLURGICAL, INORGANIC, PETROLEUM AND ELECTRICAL CHEMISTRY, ENGINEERING AND DESIGNS, GROUP 1100— JOHN E. KITTLE, Director	308-0661	05/19/95
ORGANIC CHEMISTRY, DRUG, BIO-AFFECTING AND BODY TREATING COMPOSITION, GROUP 1200—RICHARD V. FISHER, Director	308-1235	07/26/95
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 1300—JOHN F. TERAPANE, Director	308-0651	08/03/95
HIGH POLYMER CHEMISTRY, PLASTICS, COATING, PHOTOGRAPHY STOCK MATERIALS AND COMPOSITIONS, GROUP 1500—THEODORE MORRIS, Director	308-2351	09/01/95
BIOTECHNOLOGY, GROUP 1800—JOHN J. DOLL, Director	308-0196	01/15/95
ELECTRICAL EXAMINING GROUPS		
INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 2100—STEWART LEVY, Director	308-1782	01/15/95
SPECIAL LAWS AND ADMINISTRATION, GROUP 2200—ROBERT E. GARRETT, Director	308-0511	05/25/95
COMPUTER SYSTEMS AND COMPUTER APPLICATION, GROUP 2300— JOSEPH J. ROLLA, Director	305-9600	02/15/95
SPECIAL COMPUTER APPLICATIONS: COMPUTER GRAPHICS, BUSINESS PRACTICES, & DIAGNOSTIC TESTING, GROUP 2400—GERALD GOLDBERG, Director	305-3800	02/25/95
ELECTRONIC AND OPTICAL SYSTEMS AND DEVICES, GROUP 2500— JANICE A. HOWELL, Director	308-0956	04/30/95
TELECOMMUNICATIONS, GROUP 2600—NICHOLAS P. GODICI, Director	305-4700	03/03/95
DESIGN, GROUP 2900—JOHN E. KITTLE, Director	308-0661	04/10/95
MECHANICAL EXAMINING GROUPS		
HANDLING AND TRANSPORTATION MEDIA, GROUP 3100—MARGARET FOCARINO, Acting Director	308-1113	07/02/95
MATERIAL SHAPING, ARTICLE MANUFACTURING AND TOOLS, GROUP 3200—ETHEL CROSS, Director	308-1148	06/15/95
MEDICAL INSTRUMENTS, DIAGNOSTIC EQUIPMENT AND TREATMENT DEVICES: SURGERY AND SURGICAL SUPPLIES; AMUSEMENT AND EXERCISING DEVICES; ANIMAL HUSBANDRY; SPORTING GOODS; TOBACCO PRODUCTS AND MANUFACTURING EQUIPMENT; AND PRINTING, GROUP 3300—J.J. LOVE, Director	308-0858	08/14/95
SOLAR, HEAT, POWER, AND FLUID ENGINEERING DEVICES, GROUP 3400—DONALD G. KELLY, Director	308-0861	07/14/95
GENERAL CONSTRUCTION, PETROLEUM AND MINING ENGINEERING, GROUP 3500—A.L. SMITH, Director	308-1021	09/03/95

*A communication from the examiner should have been received in most applications filed prior to this date.

Patents will Expire as Follows:

- (1) The term of any utility or plant patent that is in force on or results from an application filed before June 8, 1995 is the greater of the 20 year term provided in 35 U.S.C. 154(a)(2) or 17 years from grant subject to any terminal disclaimers. 35 U.S.C. 154(c)(1).
- (2) All utility and plant patents granted on applications having an actual United States filing date on or after June 8, 1995 are granted for a term which begins on the date on which the patent is granted and ends 20 years from the date on which the application was filed in the United States. If the application contains a specific reference to an earlier application under 35 U.S.C. 120, 121 or 365(c), the patent term ends twenty years from that date on which the earliest application was filed. 35 U.S.C. 154(a)(2).
- (3) All design patents are granted for a term of 14 years from the date of the grant. However, the term of any patent may have been curtailed by disclaimer under the provisions of 35 U.S.C. 153, have lapsed due to failure to pay maintenance fees, or have been extended under the provisions of 35 U.S.C. 154, 155, or 156. Thus, if more reliable information is needed with respect to a particular patent, then the specific patent file should be reviewed to determine the actual date of patent expiration.

TRADEMARK OPERATION

Bruce A. Lehman, Commissioner
 Philip G. Hampton, II, Assistant Commissioner
 Robert M. Anderson, Deputy Assistant Commissioner
 David E. Bucher, Director, Trademark Examining Office
 Condition of Trademark Applications as of December 1, 1996

	Oldest Date	
	New*	Amendment Filed
Law Office		
Law Office 101—Ron Williams, Managing Attorney, (703) 308-9101—4th Floor Foods, Beverages, Wines & Spirits—Int. Classes 29, 30, 31, 32, 33 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/22/96	10/01/96
Law Office 102—Myra Kurzbard, Managing Attorney, (703) 308-9102—5th Floor Scientific Equipment & Furniture—Int. Classes 9, 20 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/13/96	07/08/96
Law Office 103—Kathryn Erskine, Managing Attorney, (703) 308-9103—5th Floor Scientific Equipment & Furniture—Int. Classes 9, 20 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/05/96	11/12/96
Law Office 104—Sidney Moskowitz, Managing Attorney, (703) 308-9104—6th Floor Unwrought metals, Industrial Equipment, Tools, Installation, Vehicles, Firearms, Musical Instruments, Building Materials & Floor Coverings—Int. Classes 6, 7, 8, 11, 12, 13, 15, 19, 27 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/03/96	08/20/96
Law Office 105—Thomas Howell, Managing Attorney, (703) 308-9105—6th Floor Chemicals, Paints, Lubricants, Pharmaceuticals, Medical Apparatus & Tobacco—Int. Classes 1, 2, 4, 5, 10, 34 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	07/03/96	06/19/96
Law Office 106—Mary Sparrow, Managing Attorney, (703) 308-9106—7th Floor Cosmetics, Cleaning Preparations, Paper Products & Toys—Int. Classes 3, 16, 28 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/11/96	08/23/96
Law Office 107—Thomas Lamone, Managing Attorney, (703) 308-9107—7th Floor Cosmetics, Cleaning Preparations, Paper Products & Toys—Int. Classes 3, 16, 28 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	06/27/96	10/09/96
Law Office 108—David Shallant, Managing Attorney, (703) 308-9108—8th Floor Precious metals, Fibers, Leather goods, Housewares, Cordage, Yarns, Fabrics, Clothing & Notions—Int. Classes 14, 17, 18, 21, 22, 23, 24, 25, 26 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/26/96	07/24/96
Law Office 109—Deborah Cohn, Managing Attorney, (703) 308-9109—8th Floor Precious metals, Fibers, Leather goods, Housewares, Cordage, Yarns, Fabrics, Clothing & Notions—Int. Classes 14, 17, 18, 21, 22, 23, 24, 25, 26 Services—Int. Classes 35, 36, 37, 38, 39, 40, 41, 42	05/15/96	08/15/96
**Collective Marks—Class 200 **Certification Marks—Classes A & B		
Office of Trademark Services—Teron Simms, Director, (703) 308-9100 Trademark Assistance Center—(703) 308-9000 Pre-Examination—Alan Lambert, Supervisor, (703) 308-9401 ext. 188 Intent-To-Use—(ITU)—(703) 308-9500 Post Registration Section—Mary Bowman, Supervisor, (703) 308-9500 ext. 126 Affidavits Under Sections 8 & 15 (All Classes)..... Renewals (All Classes)..... Section 12(c) Publications (All Classes).....	10/04/96 10/11/96 06/10/96	—0— —0— —0—

1. ** Assigned to all Law Office

2. Applicants with inquiries concerning the status of their applications and a touch telephone should call (703) 305-8747 from 6:30 a.m. to Midnight EST, Monday through Friday. This automated voice system will provide the current status of your application. Applicants are urged not to file unnecessary inquiries concerning the status of their applications. See SECTION 411 of the TRADEMARK MANUAL OF EXAMINING PROCEDURE.

3. * These dates identify the oldest unassigned new case in each Law Office. All cases with earlier dates have either been examined and made the subject of an action or are currently being worked on by the assigned examining attorney.


REEXAMINATIONS

DECEMBER 31, 1996

Matter enclosed in heavy brackets [] appears in the patent but forms no part of this reexamination specification; matter printed in italics indicates additions made by reexamination.

B1 Re. 34,957 (3084th)
**LEAK PROOF, PRELOADED, HIGH-BIASING FORCE
 FLOAT-OPERATED OVER-CENTER VALVE ACTUATING
 MECHANISM**
 Armand Francart, Jr., R.D. #2 Box 119Z, Rte. 896, Landenberg, Pa. 19350
 Reexamination Request No. 90/004,026, Nov. 22, 1995.
 Reexamination Certificate for Reissue Patent Re. 34,957,
 issued Aug. 25, 1992, Ser. No. 795,155, Nov. 20, 1991.
 Reissued No. 1,034,957, dated May 30, 1995, Ser. No. 233,407,
 Apr. 26, 1994.

Int. Cl.⁶ F04B 9/08
 U.S. Cl. 417—133



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 1, 2, 13, 14 and 25 are determined to be patentable as amended.


Claims 3-12 and 15-24, dependent on an amended claim, are determined to be patentable.

1. An automatic liquid pump comprising:
 a sealed pressure vessel having a bottom and a top, the bottom including a liquid inlet opening and a liquid outlet opening, said top having a gas inlet adapted to be connected to a compressed gas source, a gas outlet, an inlet valve controlling the gas inlet, and an outlet valve controlling the gas outlet, a float within the housing, a snap-over toggle linkage valve actuating mechanism to alternately open and close the valves, first opening the gas outlet valve and second closing the gas inlet valve and then closing the gas outlet valve and opening the gas inlet valve, the improvement wherein said snap-over toggle valve actuating mechanism comprises a relatively fixed mainframe supported internally by said vessel, at least one compression force preload arm pivotally mounted to said fixed mainframe for pivoting about a first pivot axis A, a first toggle link pivoted at a first end to said mainframe about said first pivot axis A, a second toggle link operatively pivoted at a first end to said compression force preload arm at a point on said arm remote from said first pivot axis for pivoting about a second pivot axis C parallel to said first pivot axis A, pivot means pivoting a second end of said first toggle link to a second end of said second toggle link for pivoting about a third axis B, coupling means for operatively coupling said float to said [compressive] compression force preload arm at a point remote from said first axis A, and said second toggle link comprising compressible and expandable means for constantly applying a compressive force on said pivot connection between said first and second toggle links such that, upon pivoting of said at least one [compressive] compression force preload arm by rise and fall of liquid within said vessel about said first pivot axis A toward a position of longitudinal alignment with the longitudinal axis of [the at least one compression force preload arm] said first toggle link, an increasing

compressive force is applied to said first toggle link to maintain said first toggle link stationary in one of two oblique, over-center positions with respect to a center line extending parallel to the longitudinal axis of said at least one compression force preload arm, and said second toggle link pivots about said axis B and said compressible and expandable means axially compresses until said first and second links become longitudinally aligned, and move across the center line [Y], and wherein said compressible and expandable means comprises a stiff compression coil spring having opposite ends, being formed of relatively large diameter wire, of short axial length, having coil turns of large diameter relative to the length of the coil spring, and said compression coil spring being unrestrained intermediate of said opposite ends and having a large spring constant, thereby providing a large biasing force, whereupon, both toggle links instantly snap over into oppositely oblique over-center positions and said second toggle link compressible and [expandable] expandable means expands to dissipate the energy of compression.

B2 4,457,847 (3085th)
**CARBOXYLATE POLYMERS FOR INTERNAL SCALE
 CONTROL AGENTS IN BOILER SYSTEMS**
 Walter F. Lorenc, Harvey; John G. Kelly, Woodridge, both of Ill., and Frederick S. Mandel, Baton Rouge, La., assigns to Nalco Chemical Company
 Reexamination Request Nos. 90/001,942, Feb. 20, 1990 and 90/003,157, Aug. 3, 1993.
 Reexamination Certificate for Patent 4,457,847, issued Jul. 3, 1984, Ser. No. 382,567, May 28, 1982.
 Continuation-in-part of Ser. No. 318,665, Nov. 5, 1981, abandoned.

Int. Cl.⁶ C02F 5/10
 U.S. Cl. 210—698



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 1-14 are cancelled.

[1. A method of treating hardness including calcium and magnesium present in boiler waters which are in contact with heat transfer surfaces exposed to boiler operating conditions to prevent formation of scale including calcium and magnesium on, and to remove previously formed scale from, these heat transfer surfaces, which comprises treating the boiler waters with a non-corrosive treatment composition substantially free of potentially corrosive chelants, and containing a water-soluble sequesterant anionic vinyl polymer containing at least 30% by weight of carboxylate functionality, said polymer being chosen from the group consisting of:
 (a) homopolymers of the group consisting of acrylic acid, methacrylic acid, maleic acid, and fumaric acid;

- (b) copolymers of one member of the group consisting of acrylic acid, methacrylic acid, maleic acid, and fumaric acid, with at least one other member of the group consisting of acrylic acid, methacrylic acid, maleic acid, and fumaric acid;
- (c) copolymers of at least one member of the group consisting of acrylic acid, methacrylic acid, maleic acid and fumaric acid with acrylamide;
- (d) copolymers of at least one member of the group consisting of acrylic acid, methacrylic acid, maleic acid and fumaric acid with vinyl sulfonate; and
- (e) hydrolyzed polyacrylamide;
- said polymer further having a molecular weight within the range of 500-50,000 and a chelation value of at least 200, which chelation value represents the milligrams of calcium or magnesium expressed in terms of calcium carbonate complexed by one gram of a sequestrant, and with the amount of said sequestrant anionic vinyl polymer being based upon the amount of hardness present, and being within the range of 3-30 ppm of polymer per ppm of hardness present in such boiler waters, whereby the hardness in the boiler waters is sequestered by the water-soluble sequestrant anionic vinyl polymer, thereby preventing formation of scale on, and removing previously formed scale from, the heat transfer surfaces exposed to boiler waters.]


B1 4,625,557 (3086th)

ACOUSTICAL IMAGING SYSTEM

Jerry Rutherford, Anaheim, Calif., assignor to Lora E. Rutherford, Lake Barrington, Ill.

Reexamination Request No. 90/004,046, Nov. 30, 1995.
 Reexamination Certificate for Patent 4,625,557, issued Dec. 2, 1986, Ser. No. 703,315, Feb. 20, 1985.
 Int. Cl.⁶ G01N 29/06

U.S. Cl. 73-635



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1 to 19 is confirmed.

1. An imaging system for non-destructively imaging the cross-section of a workpiece, said cross-section being taken substantially orthogonal to the surface of said workpiece along an operator selected course on said surface, said image system comprising:
 - a scanner means for providing a series of acoustical pulses in response to a corresponding series of acoustical drive signals; for receiving reflected acoustical waves from said workpiece surface and providing an echo signal corresponding to the received acoustical waves for each acoustical pulse; and for providing a series of distance increment signals at substantially equal incremental distances in response to motion of said scanner means on said workpiece surface along said operator selected course;
 - a transmit and receive control means responsive to each distance increment signal for providing an acoustical drive signal and a column clock signal set comprising a predetermined number of consecutive spaced column clock signals, the duration of said column clock signal set characterizing an echo interval as

the time required for said acoustical waves resulting from each acoustical pulse to move through said workpiece and return to said scanner means;

sampling means responsive to said column clock signal set for converting each said echo signal into a corresponding column series of digital values, each value characterizing the amplitude of said echo signal at time corresponding to a respective column clock signal within said echo interval;

storage means for storing each column series of digital values as successive column arrays to form an image array of digital values, each digital value having a corresponding column and row address, and for reading and outputting said image array of digital values as display data in display compatible format;

display means for forming an image from said display data formed from said image array of digital values, each digital value controlling the gray scale level of a pixel on said image, said image characterizing the cross-section of said workpiece.

B1 4,642,317 (3087th)

PROCESS FOR FEEDING RUMINANT ANIMALS AND COMPOSITION FOR USE THEREIN

Donald L. Palmquist, Wooster, and Thomas C. Jenkins, Apple Creek, both of Ohio, assignors to Ohio Agricultural Research and Development Center, Wooster, Ohio

Reexamination Request Nos. 90/003,412, Apr. 29, 1994 and 90/003,537, Aug. 23, 1994 and 90/003,579, Sep. 19, 1994.
 Reexamination Certificate for Patent 4,642,317, issued Feb. 10, 1987, Ser. No. 567,617, Jan. 3, 1984.
 Continuation of Ser. No. 274145, Jun. 16, 1981, abandoned.
 Int. Cl.⁶ A61K 31/20

U.S. Cl. 514-558

AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 1-15 are cancelled.

1. A process for supplying a fatty acid containing at least 10 carbon atoms to ruminant animals which comprises feeding to said animals the calcium salt of said fatty acid in an amount equal to at least about 1% of the dry matter content of said animals' feed.]


B1 4,713,147 (3088th)

EXTENDED NIP PRESS WITH DISPLACEABLE CENTRE OF GRAVITY FOR THE SUPPORTING FORCE

Esko Saarinen, Tampere, Finland, assignor to Valmet Paper Machinery Inc., Helsinki, Finland

Reexamination Request No. 90/004,158, Mar. 10, 1996.
 Reexamination Certificate for Patent 4,713,147, issued Dec. 15, 1987, Ser. No. 489,830, Apr. 29, 1983.
 Claims priority, application Finland, May 5, 1982, 821584
 Int. Cl.⁶ D21F 3/06

U.S. Cl. 162-358.3



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1-14 is confirmed.

1. An extended nip press for a paper machine for removing water from a wet paper, cardboard or similar fibrous or porous web, said press comprising
 - a rotating press roll,
 - at least one stationary loading shoe parallel to the axis of said press roll and pivotable around an axis parallel to said axis, said loading shoe together with said press roll forming an extended press zone,
 - at least one dewatering felt passing between said press roll and a band for passing the web to be dewatered through said press zone, and
 - a support means located between said loading shoe and its supporting frame for applying a supporting force on said loading shoe, said supporting force pressing said loading shoe against said press roll, said support means being provided with transfer elements for displacing the centre of gravity of the supporting force acting on said loading shoe in the direction of movement of the web to be dewatered.



B3 4,803,445 (3089th)

VARIABLE FREQUENCY OSCILLATOR

Richard G. Yamasaki, Torrance, Calif., assignor to Silicon Systems, Inc., Tustin, Calif.

Reexamination Request No. 90/003,909, Aug. 4, 1995.
 Reexamination Certificate for Patent 4,803,445, issued Feb. 7, 1989, Ser. No. 41,767, Apr. 22, 1987.
 Int. Cl.⁶ H03K 3/281

U.S. Cl. 331-177 R



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 1 and 6 are determined to be patentable as amended.

Claims 2-5 and 7-9, dependent on an amended claim, are determined to be patentable.

1. A circuit for providing a variable frequency oscillator (VFO) comprising:
 - oscillating means having a center frequency and outputting a first clock signal;
 - first control means coupled to a control voltage and said oscillating means for controlling said first clock signal;
 - second control means coupled to said oscillating means for controlling said center frequency and outputting a plurality of [second clock] timing signals external to said oscillating means, wherein [at least one of] said plurality of [clock]

timing signals [is] are coupled to a plurality of timing [circuit] circuits, said second control means independent of said first control means.


B1 5,367,884 (3090th)

GENERATOR-ABSORBER-HEAT EXCHANGE HEAT TRANSFER APPARATUS AND METHOD AND USE THEREOF IN A HEAT PUMP

Benjamin A. Phillips, Benton Harbor; Thomas S. Zawacki, St. Joseph, both of Mich., and Joseph Marsala, Glen Ellyn, Ill., assignors to Phillips Engineering Co., St. Joseph, Mich.

Reexamination Request No. 90/003,736, Feb. 22, 1995.
 Reexamination Certificate for Patent 5,367,884, issued Nov. 29, 1994, Ser. No. 76,759, Jun. 15, 1993.
 Continuation-in-part of Ser. No. 793,644, Nov. 18, 1991, Pat. No. 5,271,235, which is a continuation-in-part of Ser. No. 668,198, Mar. 12, 1991, abandoned.
 Int. Cl.⁶ F25B 15/00

U.S. Cl. 62-101



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 10-12 are cancelled.

Claims 1, 15, 16, 21, 26, 30, 41, 46, 55-59, 70, 74, 79, 88 and 89 are determined to be patentable as amended.

Claims 2-9, 13-14, 17-20, 22-25, 27-29, 31-40, 42-45, 47-54, 60-69, 71-73, 75-78 and 80-87 dependent on an amended claim, are determined to be patentable.

New claims 90-93 are added and determined to be patentable.

1. [In a] A generator-absorber heat exchange apparatus [including] comprising: a generator and an absorber, the absorber having an interior pressure lower than the pressure of the generator interior and having an absorber heat exchange region, and each having high and low temperature regions at opposite ends establishing respective temperature ranges and a heat transfer region, the temperature ranges defining the respective heat transfer regions overlapping; a fluid flow pathway circulating a weak liquor from the high temperature region of the generator and a rich liquor from the low temperature region of the absorber to and through the high temperature, heat transfer and low temperature regions of the generator and the absorber, [the improvement comprising:] with the rich liquor being circulated from the low temperature region of the absorber through the absorber heat exchange region of the absorber; and a heat exchange circuit receiving a portion of the liquor from the fluid flow pathway and circulating said portion of the liquor between said heat transfer regions transferring heat from the absorber to the generator.

B1 5,383,454 (3091st)

SYSTEM FOR INDICATING THE POSITION OF A SURGICAL PROBE WITHIN A HEAD ON AN IMAGE OF THE HEAD

Richard D. Bucholz, St. Louis, Mo., assignor to Sofamor Danek Group, Inc., Memphis, Tenn.



Reexamination Request No. 90/003,899, Jul. 24, 1995.

Reexamination Certificate for Patent 5,383,454, issued Jan. 24, 1995, Ser. No. 909,097, Jul. 2, 1992.

Continuation of Ser. No. 600,753, Oct. 19, 1990, abandoned.

Int. Cl.⁶ A61B 5/103

U.S. Cl. 128—653.1



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1–20 is confirmed.

3. The system of claim 2 wherein the second means comprises: a base adapted to be mounted on the body in a position having a fixed relationship with the reference points means of the body; and means for measuring the position of the base with respect to the reference means.

B1 5,387,211 (3092nd)

MULTI-HEAD LASER ASSEMBLY


Vahid Saadatmanesh, Irvine, and Marvin P. Loeb, Huntington Beach, both of Calif., assignors to Trimedyne, Inc., Irvine, Calif.

Reexamination Request No. 90/004,023, Oct. 30, 1995.

Reexamination Certificate for Patent 5,387,211, issued Feb. 7, 1995, Ser. No. 28,839, Mar. 10, 1993.

Int. Cl.⁶ A61N 3/00

U.S. Cl. 606—10



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1–19 is confirmed.

1. A laser device for co-axial positioning of plural laser beams along a single axis, which device comprises:
at least two laser oscillators for producing a laser beam by each oscillator;
rotary reflector means positioned for intercepting at least one of said produced laser beams and directing the intercepted laser beam separately from, but along a single axis defined by, the other laser beam;
alignment means for aligning the respective laser beams of each said oscillator at an angle along paths which intersect at a region;
said reflector means includes a reflecting member rotation means for rotating said reflecting member through said path intersection region; and
said device includes control means for operating one of said oscillators to emit a pulse of said one laser beam only as said reflecting member rotates through said path intersection region so as to reflect said one beam pulse along said single axis and for operating another of said oscillators to emit a pulse of said other laser beam only when said reflecting member has rotated beyond said path intersection region so that said other beam pulse passes unobstructed along said single axis.

B1 5,426,344 (3093rd)

ELECTRONIC BALLASTS

Slew E. Wong, Mount Ousley, and Thien S. Yang, Connells Point, both of Australia, assignors to Ultralite International Pty. Limited, New South Wales, Australia

Reexamination Request No. 90/004,106, Dec. 21, 1995.

Reexamination Certificate for Patent 5,426,344, issued Jun. 20, 1995, Ser. No. 192,993, Feb. 7, 1994.


Continuation of Ser. No. 875,761, Apr. 29, 1992, abandoned.

Claims priority, application Australia, Aug. 31, 1990,

PK2084

Int. Cl.⁶ H05B 41/14

U.S. Cl. 315—200 R



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

Claims 1–3 are cancelled.

1. In a ballast circuit for a fluorescent lamp in which the ballast circuit has a rectifier bridge (D1), a mylar capacitor (C3) across the rectifier bridge and a smoothing capacitance in parallel with the mylar capacitor, the improvement comprising:
an additional diode (D2) have an electrode connected to the junction of the mylar capacitor and the rectifier bridge and the other electrode connected to the smoothing capacitance, said additional diode being a high speed switching type polarized so that during half cycles of the supply voltage when the supply voltage is less than the voltage on the smoothing capacitance, said additional diode blocks current from flowing from the smoothing capacitance to thereby improve the power factor and reduce harmonic distortion of the ballast circuit.

B1 5,462,535 (3094th)

SYRINGE SYSTEM

Frits F. Bonnichsen, Lyngø, and Peter N. Jørgensen, Brønshøj, both of Denmark, assignors to Novo Nordisk A/S, Bagsvaerd, Denmark

Reexamination Request No. 90/004,192, Mar. 25, 1996.

Reexamination Certificate for Patent 5,462,535, issued Oct. 31, 1995, Ser. No. 323,401, Oct. 14, 1994.

Continuation-in-part of Ser. No. 167,831, Dec. 16, 1993, abandoned.

Int. Cl.⁶ A61M 5/32

U.S. Cl. 604—272



AS A RESULT OF REEXAMINATION, IT HAS BEEN DETERMINED THAT:

The patentability of claims 1–10 is confirmed.

1. An insulin injection system comprising a pen shaped syringe comprising a cartridge with insulin and an injection needle, wherein the needle is a G30 needle and the cartridge contains an insulin type which may freely flow through the G30 needle.

REISSUES

DECEMBER 31, 1996

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in *italics* indicates additions made by reissue.

Re. 35,410

SPA WITH RECESSED FILTER CHAMBER


Carson D. Adcock, Huntingdon Valley, Pa., and Robert Lauter, Fort Wayne, Ind., assignors to W. W. Adcock, Inc., Huntingdon Valley, Pa.

Original No. 4,552,658, dated Nov. 12, 1985, Ser. No. 645,870, Aug. 31, 1994. Application for reissue Jun. 14, 1993, Ser. No. 77,346

Int. Cl.⁶ A61H 33/00

U.S. Cl. 4—541.3

4 Claims



1. A spa with a water recirculation system, comprising a molded shell for [the] spa water having a filter cavity integrally molded with the shell below the [water] level of the spa, water and upwardly open for access from above the water level, the cavity being inwardly open to the interior of the shell to receive water therefrom and having a filter chamber in the lower portion thereof positioned to receive a filter in a horizontal position at a level below the water level in the shell, *said filter chamber in the lower portion of said cavity being separated from the interior of the shell by a partition*, and the filter chamber having a suction connection extended exteriorly of the shell, and a renewable filter positioned horizontally in said chamber to receive water flowing into the filter chamber from the interior of the shell and delivering [the] filtered water to said suction connection.

Re. 35,411

BELT CASTING OF MOLTEN METAL


Sankaranarayanan Ashok, West Haven, and Harvey P. Cheskis, North Haven, both of Conn., assignors to Olin Corporation, New Haven, Conn.

Original No. 5,131,451, dated Jul. 21, 1992, Ser. No. 628,074, Dec. 14, 1990. Application for reissue Jul. 20, 1994, Ser. No. 277,849

Int. Cl.⁶ B22D 23/00

U.S. Cl. 164—46

8 Claims



1. A method of casting metal [strip] comprising:

providing a moving substrate having edge dams thereon for the containment of the molten metal in a direction transverse to the movement of said substrate, atomizing a stream of molten metal into highly liquid droplets, depositing said spray of droplets; onto said moving substrate with a highly liquid content such that the deposited metal flows in a direction transverse to the direction of movement of the substrate against the edge dams, and causing said deposited molten metal to solidify as said substrate moves the metal in a direction away from the spray being deposited.

Re. 35,412

DOUBLE TANK PINCH TRIGGER PUMP WATER GUN


Lonnie G. Johnson, Smyrna, Ga., and Bruce M. D'Andrade, Whitehouse Station, N.J., assignors to Larami Limited, Mt. Laurel, N.J.

Original No. 5,150,819, dated Sep. 29, 1992, Ser. No. 841,762, Feb. 28, 1992. Continuation of Ser. No. 680,247, Apr. 3, 1991, abandoned, which is a continuation-in-part of Ser. No. 578,145, Sep. 6, 1990, Pat. No. 5,074,437. Application for reissue Aug. 26, 1994, Ser. No. 296,438

Int. Cl.⁶ A63H 3/18

U.S. Cl. 222—79

26 Claims



20. A toy water gun comprising a storage reservoir adapted to hold water and air, said storage reservoir having a vent which allows air to enter said water storage reservoir; a pressure tank adapted to hold water and air; first conduit means for conveying water or air from said storage reservoir to said pressure tank, said first conduit means being coupled with said storage reservoir in a position so that the orientation of water within the storage reservoir determines whether water or air is drawn from within said storage reservoir; drawing means for selectively drawing air or water or a combination of air and water from said storage reservoir and depositing the drawn air or water or combination thereof into said pressure tank through said first conduit means; second conduit means for conveying water from said pressure tank to ambience; and control means for controlling the flow of water through said second conduit means.

Re. 35,413

ELECTROSPRAY ION SOURCE WITH REDUCED NEUTRAL NOISE AND METHOD

Iain C. Mylchreest, Milpitas, Calif., and Mark E. Hall, Yardley, Pa., assignors to Finnigan Corporation, San Jose, Calif.

Original No. 5,171,990, dated Dec. 15, 1992, Ser. No. 703,471, May 17, 1991. Application for reissue Mar. 30, 1994, Ser. No. 220,963

Int. Cl.⁶ B01D 59/44; H01J 49/00

U.S. Cl. 250—282

2 Claims

4. A method of operating an ion source, said ion source including a low pressure chamber having a skimmer with an orifice, and

3143

PLANT PATENTS

GRANTED DECEMBER 31, 1996

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

9,769

HYBRID TEA ROSE PLANT NAMED 'MALJOANNA'
Mark G. Maltagliati, 1698 Manor Dr., San Pablo, Calif. 94801
Filed Jan. 19, 1996, Ser. No. 582,351
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—18

1 Claim

1. A new and distinct variety of rose plant of the Hybrid Tea class, substantially as herein shown and described.

9,772

CHRYSANTHEMUM PLANT NAMED 'DREAMY TRACY'
Leon Glicenstein, Salinas, Calif., assignor to Yoder Brothers, Inc., Barberton, Ohio
Filed Aug. 18, 1995, Ser. No. 516,564
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—82.2

1 Claim

1. A new and distinct Chrysanthemum plant named Dreamy Tracy, as described and illustrated.

9,770

STRAWBERRY PLANT NAMED 'ARENA'
Jose M. A. Lopez, Tudela, Spain, assignor to Plantas de Navarra, S.A., Navarra, Spain
Filed Aug. 9, 1995, Ser. No. 513,006
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—48

1 Claim

1. A new and distinct variety of strawberry plant, substantially as shown and described.

9,773

GERANIUM PLANT NAMED 'FISMEGA'
Angelika Utecht, Montabaur, Germany, assignor to Floris AG, Binningen, Switzerland
Filed Aug. 29, 1995, Ser. No. 518,894
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. It is claimed a new and distinct cultivar of geranium plant named Fismega as illustrated and described.

9,771

ROBINIA PLANT NAMED 'LACE LADY'
Peter Cunningham, Auckland, New Zealand, assignor to Trustees of the Peter Cunningham Family Trust, and Trustees of the Sharyn Cunningham Family Trust, both of Auckland, New Zealand
Filed Apr. 25, 1995, Ser. No. 428,703
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—51.1

1 Claim

1. A new and distinct variety of *Robinia pseudoacacia* plant, substantially as illustrated and described, which exhibits:

- (a) a bushy shrub growth habit,
- (b) the formation of branches having a generally short zigzag internodal growth configuration,
- (c) the propensity to form spines on at least some branches, and
- (d) the formation of mature leaves that commonly possess severely curled leaflets.

9,774

GERANIUM PLANT NAMED 'FISBOOGY'
Angelika Utecht, Montabaur, Germany, assignor to Floris AG, Binningen, Switzerland
Filed Aug. 29, 1995, Ser. No. 520,715
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—87.12

1 Claim

1. A new distinct cultivar of geranium plant named Fisboogy, as illustrated and described.

9,775

AGLAONEMA PLANT NAMED DEBORAH
J. Glenn Barnes, Apopka, and Marcus S. Lambert, Zolfo Springs, both of Fla., assignors to Sunshine Foliage World, Zolfo Springs, Fla.
Filed Sep. 1, 1995, Ser. No. 523,490
Int. Cl.⁶ A01H 5/00

U.S. Cl. Pkt.—88.1

1 Claim

1. A new and distinct cultivar of Aglaonema plant named Deborah, as illustrated and described.

VOL
11 93

ISS
5

DE
31
1996

UMI

PATENTS
GRANTED December 31, 1996

ERRATA	
For CLASS	See PATENT NO.
131-259	5,588,448
242-378	5,588,626
242-599	5,588,627
242-607	5,588,628
473-456	5,588,645
473-426	5,588,646
473-470	5,588,647
473-451	5,588,648
463-018	5,588,649
473-206	5,588,651
473-168	5,588,652
473-218	5,588,653
473-429	5,588,655
508-168	5,589,095
510-514	5,589,099
264-004	5,589,370
427-250	5,589,425
417-063	5,589,633
396-548	5,589,900
396-012	5,589,901
396-003	5,589,902
396-428	5,589,903
396-055	5,589,904
396-431	5,589,905
396-505	5,589,906
396-287	5,589,907
396-051	5,589,908
396-096	5,589,909
396-106	5,589,910
396-080	5,589,911
396-055	5,589,912
399-114	5,589,913
399-060	5,589,914
399-120	5,589,915
399-286	5,589,916
399-274	5,589,917
399-114	5,589,918
399-262	5,589,919

VOL
11 93

ISS
5

DE
31

1996

UMI

ERRATA-CONTINUED

For CLASS	See PATENT NO.
399-145	5,589,920
399-297	5,589,921
399-315	5,589,922
399-078	5,589,923
399-350	5,589,924
399-323	5,589,925
399-302	5,589,926
386-121	5,589,943
386-084	5,589,944
386-083	5,589,945
386-042	5,589,946
386-096	5,589,947
349-016	5,589,958
349-088	5,589,959
349-076	5,589,960
349-041	5,589,961
349-046	5,589,962
349-119	5,589,963
349-160	5,589,964
349-165	5,589,965
349-174	5,589,966
395-204	5,590,037
395-241	5,590,038
395-759	5,590,039

PATENTS

GRANTED DECEMBER 31, 1996


GENERAL AND MECHANICAL

5,588,153
SURGICAL GOWN
Roger G. Ignon, Palos Verdes Estates, and Ronald E. Thomas, Jr., Alta Loma, both of Calif., assignors to Stackhouse, Inc., Riverside, Calif.

Filed Apr. 28, 1995, Ser. No. 440,495
Int. Cl. A41D 13/00


U.S. Cl. 2-457

10 Claims



1. A surgical gown adapted to be operatively disposed to substantially cover a surgeon wearing a ventilator including a wait mounted power unit, a head mounted manifold structure, and at least one tube extending therebetween, the gown having a front and a back and further comprising:

- a head section sized and configured to receive the head of the surgeon;
- a waist section disposed beneath the head section when the gown is operatively disposed on the surgeon, the waist section being sized and configured to receive the waist of the surgeon;
- a shoulder section disposed between the head section and the waist section when the gown is operatively disposed on the surgeon, the shoulder section being sized and configured to receive the shoulders of the surgeon;
- a ventilator section disposed between the head section and the waist section when the gown is operatively disposed on the surgeon, the ventilator section forming a tube channel extending along the back of the gown sized and configured to receive the at least one tube of the ventilator; wherein the ventilator section forms an enlargement on the back of the gown which facilitates movement of the head of the surgeon and the at least one tube of the ventilator without substantially restricting the movement of the head section of the gown.




- (c) an inverted pocket at said back body section, with a bottom opening defined between said back body section and a free edge of said yoke;
- (d) shirt display panels detachably secured within said breast pockets and said inverted pocket, said shirt display panels being adapted to be confined within said breast pockets and said inverted pocket out of sight or extended outwardly from said breast pockets and said inverted pocket for viewing;
- (e) said trouser construction including a riser, a pair of legs, slant side pockets in said riser and side patch pockets under said slant side pockets at the sides of said legs;
- (f) trouser display panels detachably secured within said side patch pockets, said trouser display panels being adapted to be confined within said side patch pockets out of sight or extended outwardly from said side patch pockets for viewing; and
- (g) whereby, when all of said display panels of said breast pockets, said inverted pocket and said side patch pockets are deployed, the summation of said panels are available for viewing substantially throughout a 360-degree periphery about said wearer.

5,588,155
LIQUID IMPERVIOUS SURGICAL GOWN CUFF AND METHOD FOR MAKING THE SAME
Jerry W. Baker, Roswell, and Timothy W. Reader, Suwanee, both of Ga., assignors to Kimberly-Clark Corporation, Neenah, Wis.

Filed Mar. 31, 1995, Ser. No. 414,989
Int. Cl. A41B 7/00

U.S. Cl. 2-123

8 Claims



5,588,154
UNIFORM WITH OPTIONALLY CONCEALED/DEPLOYED VISUAL PANELS FOR DISPLAY ABOUT A 360 DEGREE PERIPHERY
Stephen Blauer, Lexington, Mass., and Mark Mordechai, Hampton, N.H., assignors to Blauer Manufacturing Co. Inc., Boston, Mass.

Filed Oct. 7, 1994, Ser. No. 319,876
Int. Cl. A41B 1/00

U.S. Cl. 2-69

35 Claims

1. A uniform for a human wearer, said uniform comprising matching shirt and trouser-constructions:

- (a) said shirt construction including a back body section, right and left front body sections, pairs of arms and sleeves, a collar, and a selectively secured, selectively free yoke that extends across said wearer's shoulders from arm to arm and over said shoulders and about said collar between said back body section and said front body sections;
- (b) said front body sections having breast pockets, said breast pockets having tops that are open and overlapped by free edges of said yoke;

1. A surgical gown comprising:


- a sleeve and a cuff secured to the sleeve; wherein the cuff is formed from an elastic necked-stretched laminate; and
- wherein the elastic necked-stretched laminate includes a neckable material layer joined to an elastic aqueous liquid impervious layer.

5,588,156

ARTICLE OF CLOTHING HAVING HIGH VISIBILITY
George S. Panton, Jr., Melbourne Beach, Fla., assignor to
Diamond Safety Gear, Inc., Indialantic, Fla.
Filed Jun. 7, 1995, Ser. No. 470,584
Int. Cl.⁶ A41D 13/00; 27/08

U.S. Cl. 2—243.1

19 Claims




16. An article of clothing, comprising at least one first diamond-shaped retroreflective material and at least one second diamond-shaped retroreflective material, which first diamond-shaped retroreflective material encloses a first colored accent area and which diamond-shaped retroreflective material is enclosed, in whole or in part, by a second colored accent area and which second diamond-shaped retroreflective material is enclosed, in whole or in part, by a third colored accent area, in which said first and second colored accent areas are diamond-shaped and said third colored accent area is triangular.

5,588,157

TOILET VALVE SEAT ACTUATOR ASSEMBLY
Ralph L. Mayfield, 1233 W. Lydia, Wichita, Kans. 67213
Filed Mar. 10, 1995, Ser. No. 402,183
Int. Cl.⁶ E03D 1/35

U.S. Cl. 4—397

11 Claims



1. A toilet valve seat actuator assembly for use in connection with a toilet tank, said assembly being adapted for engagement with a trip handle mechanism and operable to lift a tank ball from a valve seat upon activation by said trip handle, thereby initiating a flush sequence, and to guide said tank ball back onto said valve seat upon completion of said sequence, said assembly comprising: a support bracket adapted for mounting within said tank at a position generally overlying said valve seat;

a sleeve having an upper end, a lower end and a generally cylindrical wall, said sleeve being mounted to said support bracket at said upper end and disposed to extend substantially vertically downwardly over said valve seat, said sleeve defining a longitudinal canal in said wall, said canal terminating above said lower end;
a tube telescoped within said sleeve and adapted for movement along the axis of said sleeve, said tube defining a lateral hole generally alignable with said canal;
an arm defining a vertical slot adapted to engage said trip handle mechanism exteriorly of said sleeve and having a tongue securing said arm to said tube, said tongue having its greatest dimension in the vertical plane for slidable movement within said canal, said tongue also being fixably received through said hole in said tube and extending substantially across the same;
a bore defined in said tongue, the axis of said bore being generally concentric with the axis of said tube; and
a lift rod having an upper end and a lower end slidably received within said bore, said upper end including a stop having a horizontal dimension greater than the diameter of said bore, thereby prohibiting movement of said stop therethrough, and said lower end including means for attachment to said tank ball.

5,588,158


BATH RING

Keith L. Poulson, Westminster; Robert M. Parker, Aurora, both of Colo.; Jon R. Rossman, Chelmsford, and Bryan R. Hotelling, Arlington, both of Mass., assignors to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 7, 1995, Ser. No. 554,729
Int. Cl.⁶ A47K 3/024

U.S. Cl. 4—572.1

23 Claims



1. A bath ring, comprising:
(a) a base portion;
(b) a ring portion having a back portion for supporting the back of a person seated on said base portion;
(c) attachment means connecting said ring portion to said base portion;
(d) restraining means extending upwardly from a front edge of said base portion, said restraining means further comprising:
(1) a first portion being pivotable about said base portion;
(2) a second portion having a pair of distal ends; and
(3) a lock mechanism associated with said first and second portions which is adapted to engage with and disengage from a pair of slots located in an inwardly facing surface of said ring portion; and
said lock mechanism further comprising:
(i) a first element including a pair of oppositely extending arm members and a central member from which each arm

member extends, said central member having the ability to be compressed so that said arm members may be brought closer together; and

(ii) a second element extending substantially along said first portion;

wherein said first and second elements are located in adjoining relation so that said central member of said first element is compressed as said second element is moved upwardly.

5,588,159


INFANT BATHTUB WITH MULTIPLE-POSITION INFANT SUPPORT

Keith L. Poulson, Westminster; Robert M. Parker, Aurora; Jeffrey T. Samson, Boulder, and Harry B. Taylor, Lafayette, all of Colo., assignors to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 13, 1995, Ser. No. 559,167
Int. Cl.⁶ A47K 3/024

U.S. Cl. 4—572.1

10 Claims



1. In an infant bathtub for comfortably supporting the head, back and bottom of an infant in any one of multiple inclined positions, comprising:

a tub having a generally horizontal bottom wall, a head end wall portion extending upwardly from said bottom wall and having an upper inside surface, and a generally vertical wall extending upwardly from and encompassing the remainder of said bottom wall for retaining bath water between said bottom wall and the upwardly extending walls;

a removable, elongated infant-supporting insert having an upper surface contoured to comfortably support the bottom, back and head of an infant, and an underside surface opposite said upper surface; and

interengagable means on the underside surface of said insert and integrally formed on the upper inside surface of said head end wall for firmly supporting and maintaining said insert in at least two different angles of inclination in said tub, said interengagable means including:

i. a first gripping portion at the upper inside surface of said head end wall; and
ii. a pair of second gripping portions on the underside of said insert, said pair of second gripping portions being spaced longitudinally along said insert and each one of said pair being independently engageable with said first gripping portion whereby only one of said pair of second gripping portions is active to support and maintain said insert in cooperation with said first gripping portion in a given one of said different angles of insert inclination.

5,588,160


TOTAL BODY BRUSH SHOWER

Timothy G. Nichols, Rte. 4, Box 250, Galax, Va. 24333
Filed Sep. 5, 1995, Ser. No. 523,552
Int. Cl.⁶ A47K 7/02

U.S. Cl. 4—606

1 Claim

1. A shower brush assembly comprising:
a front piece having resilient bristles on an outer surface thereof and at least one opening therethrough;
a tubing fixture comprising at least one shower nozzle with water carrying tubing attached thereto;



a back piece having a plurality of suction cups formed on a rear surface thereof, said suction cups being sufficient to attach said assembly to a wall of a shower, said back piece rear surface further having a plurality of hand attachment straps formed thereon wherein said assembly may alternatively be attached to a person's hand;

said front piece having means on a surface opposite said outer surface for attachment of said tubing;

said front piece being attached to said back piece in a manner enclosing said tubing with said at least one shower nozzle extending at least partially through said at least one opening; means for attaching said tubing to a water source wherein water may flow from said source through said tubing and be expelled from said at least one nozzle to shower a user.


5,588,161

FOOT BATH

George Barradas, 15 River View Ct., Greenwich, Conn. 06831
Filed Nov. 3, 1995, Ser. No. 552,785
Int. Cl.⁶ A47K 3/022

U.S. Cl. 4—662


9 Claims



1. A portable foot bath adapted for connection to a power source, comprising a tub having a floor and a base platform connected to said floor for supporting the tub, said platform having a base surrounded by generally vertical side walls, a heater platform supported on said base platform and provided with a heater element on a top surface thereof, a motor having a vibratory coil for vibrating the floor of said tub, said motor located within said base platform and suspended from a bottom surface of said heater platform, said tub adapted for receiving the user's feet and positioned above said heater element, a thin metal heat transmitting panel positioned between said heater element and the floor of said tub engaging the latter as well as said heater element so that heat is transferred to the water in the tub.

radiated throughout the floor of the tub, and spaced rounded projections rising from the floor of the tub for vibratory massage of the feet.

5,588,162
POWER ACTUATED TOILET SEAT
Gary C. Robinson, P.O. Box 24, Cooter, Mo. 63839
Filed Nov. 17, 1994, Ser. No. 341,375
Int. Cl.⁶ A47K 13/10; 17/00
U.S. Cl. 4—667



1. A toilet seat assembly comprising:
 - a frame including a plurality of legs rigidly connected to each other by a plurality of cross members, said cross members including an upper cross bar abutting and located above a lower cross bar;
 - b. a hinge mounted on the upper cross bar;
 - c. a toilet seat connected at a forward end thereof to the hinge, thereby permitting pivotal movement of the toilet seat about the upper cross bar;
 - d. an actuator assembly connected to the toilet seat for raising and lowering the toilet seat, the actuator assembly configured for electrical operation; and
 - e. a switch mounted to the frame and in electrical communication with the actuator assembly to permit a user to selectively raise and lower the toilet seat in response to manipulation of the switch, whereby the toilet seat assembly functions to assist such a user in moving between a standing and a sitting position about a toilet.

5,588,163
SUPPORT DECK FOR MATTRESS OR SEAT
John E. Miller, 1016 Monroe St., Tupelo, Miss. 38801
Continuation-in-part of Ser. No. 66,993, May 25, 1993, which is a continuation-in-part of Ser. No. 588,351, Sep. 26, 1990, Pat. No. 5,231,709. This application May 19, 1995, Ser. No. 444,685
Int. Cl.⁶ A47C 17/02
U.S. Cl. 5—13


12. A support assembly for seating or bedding comprising a plurality of support members extending in the same general direction to form a support, said support members having adjacent ends connected to each other for movement relative to each other, means preventing movement of said ends in one direction and allowing movement of said ends in a direction opposite said one direction, said support members being provided in a plurality of rows laterally positioned relative to each other, and wherein each support member has on one end a generally T-shaped portion and an end portion opposite said one end including a slot dimensioned

2 Claims

to receive during assembly the T-shaped portion of an adjacent support member, said support member being pivotable about an axis extending through the T-shaped portion such that said support members are pivotable relative to each other in one direction.

5,588,164
INFANT SEAT ROCKER AND AMUSEMENT UNIT
Genevieve C. Proulx, 1475 Waltham Street, Gloucester, Ontario, Canada
Filed Aug. 22, 1995, Ser. No. 517,848
Int. Cl.⁶ A47C 3/02; A47D 9/02; 13/10; A63H 18/08
U.S. Cl. 5—109


11 Claims



1. A base unit for supporting an infant carrier seat comprising a housing having a curved bottom surface for rocking on a generally flat support surface, said housing having an upper central portion on which an infant carrier seat is removably mountable, an endless closed loop pathway circumscribing said central portion, a weight, and power means to move said weight along said path in a closed loop at a selected rate of speed to cause said base unit to rock.

5,588,165
CUSHIONING ASSEMBLY HAVING PLASTIC SPRINGS FOR SUPPORTING A PAD
Heinrich Fromme, Schloss Holte-Stukenbrock, Germany, assignor to Senne Lizenz & Produkte GmbH, Schloss Holte-Stukenbrock, Germany
Filed Nov. 10, 1994, Ser. No. 338,804
Claims priority, application Germany, Nov. 10, 1993, 9317114 U; Mar. 10, 1994, 9404021 U; Jul. 30, 1994, 9412330 U
Int. Cl.⁶ A47C 27/06; 31/12
U.S. Cl. 5—247

16 Claims




1. A cushioning assembly, comprising:
 - a foundation; and
 - a plurality of springs mounted on said foundation, said springs arranged in substantially parallel rows, each row including two springs arranged adjacent respective ends of the row and a plurality of springs disposed between said two springs, whereby said springs of all of said rows together define a support area adapted to support a pad, each spring comprising:
 - an elastically compressible portion formed of plastic and comprising a hollow body forming at least one through-chamber defining an axis,
 - a mounting portion disposed at a bottom of said elastically compressible portion and including structure for connection with said foundation, and
 - a pad-supporting plate disposed at a top of said elastically compressible portion and adapted for supporting a pad;
- said axes of said springs lying in a common plane oriented parallel to said pad-supporting plates and perpendicular to a loading applied to the spring assembly by a user,
- wherein said foundation comprises a plurality of parallel slats, said springs being mounted along said slats, said springs mounted on each slat defining one of said rows, said mounting portion forming a slat chamber extending completely through said spring and through which a slat extends.

5,588,166
MEDICAL ATTACHMENT DEVICE
John Burnett, 1009 #B Constitution Ave. NE., Washington, D.C. 20002
Filed Jan. 4, 1995, Ser. No. 368,439
Int. Cl.⁶ F16L 3/08
U.S. Cl. 5—503.1

5 Claims

1. An attachment device for attaching a wheeled auxiliary apparatus, which comprises an upright pole, to a patient transport vehicle, which comprises a horizontally disposed part, for synchronized movement of said apparatus and said vehicle, comprising:
 - A) a holding member comprising an inner flat side, a top side, and an outer side, said inner and outer sides being spaced apart by an insertion distance, wherein said outer side comprises a pair of stiffening ridges that are spaced apart in



parallel and across said outer side, at least one of said inner and outer sides having a width greater than said distance and having at least one threadedly and perpendicularly attached screw for pressing said horizontally disposed part against the other of said sides, whereby said part is thereby rigidly held by said member; and


- B) a grasping member, attached to said outer side, for grasping said upright pole, said grasping member comprising a pair of pole clamps which are mounted upon said pair of ridges, each said pole clamp comprising:
 - 1) a hat-shaped member having a central base which is rigidly attached to one said ridge, a pair of flat outer leaves on each side of said base and outwardly spaced therefrom, a pivot lug mounted on one said leaf, and a holding lug mounted on the other said leaf, and
 - 2) a swivel plate mounted on said pivot lug at one end thereof and having a slot in the other end thereof for engaging said holding lug.

5,588,167
APPARATUS AND METHOD FOR MANAGING WASTE FROM PATIENT CARE MAINTENANCE AND TREATMENT
Demetrios A. Pahnou, Mt. Pleasant; James R. Stolpmann, Charleston, and James M. C. Thomas, Mt. Pleasant, all of S.C., assignors to SSI Medical Services, Inc., Charleston, S.C.

Continuation of Ser. No. 74,860, Jun. 11, 1993, Pat. No. 5,438,721, which is a continuation-in-part of Ser. No. 792,216, Nov. 13, 1991, Pat. No. 5,269,030. This application May 11, 1995, Ser. No. 438,714
Int. Cl.⁶ A61G 7/02

U.S. Cl. 5—606

12 Claims



1. An apparatus for managing waste arising from at least one of the care, maintenance, and treatment of a patient, the apparatus comprising:
 - a) means for supporting at least a portion of the patient's body, said supporting means including a flexible member inflatable

- with pressurized air, said flexible member including a plurality of flexible surfaces forming in combination a discontinuous surface for receiving said portion of the patient's body;
- b) a means for catching waste, said waste catching means being carried by said supporting means;
- c) a vacuum blower disposed for sucking the wastes from said catching means; and
- d) a holding reservoir disposed in communication with said catching means and said vacuum blower to receive the waste sucked from said catching means by said vacuum blower.


5,588,168

CONTOURED SYMMETRICAL DIFFERENTIAL-ELASTICITY NECK PILLOW

Thomas Byrne, 10055 S. Maplewood, Chicago, Ill. 60655, and John O'Connor, 10504 S. Claremont, Chicago, Ill. 60643
Filed Jan. 23, 1996, Ser. No. 599,482
Int. Cl.⁶ A47G 9/00

U.S. Cl. 5—636

4 Claims



1. A contoured neck pillow comprising:
- a round central pad comprised of resilient foam having a compression of approximately seven pounds and a diameter of approximately eight inches;
- an annular ring comprised of resilient foam having a compression of from fifteen to twenty pounds, and having an outer diameter of approximately sixteen inches; and
- two foam sections enclosing the central pad and annular ring, and permanently attached thereto; whereby the pillow provides differential elasticity that is not altered by inverting or rotating the pillow.

5,588,169


TOOL ASSEMBLY FOR BICYCLE

Louis Chuang, 11th Floor, - 1 No. 367, Gong Yi Road, Taichung, Taiwan
Filed Apr. 24, 1995, Ser. No. 427,437
Int. Cl.⁶ B25F 1/02

U.S. Cl. 7—138

7 Claims

1. A tool assembly for a bicycle comprising:
- a body (10) including a first end and a second end, the first end having at least one engaging hole (12, 13) defined therein and at least one engaging opening (11, 14) defined in a peripheral portion thereof, the second end having a socket (15) formed on a first side thereof and including a block (20) secured thereto, the block (20) extending in a direction traverse to a longitudinal direction of the body (10) and including a slot (21) defined in a middle portion thereof for receiving a chain means having pivot shafts therein, the block further comprising a first end having a screw hole (22) defined therein and



extending along a longitudinal direction thereof for engaging with a bolt means (30), the bolt means (30) including an extension (31) for disengaging the pivot shafts from the chain means; and

a rod (40) including a first end having a first driving tool bit (41) projecting longitudinally and outwardly therefrom and a second end having a second driving tool bit (43) projecting outwardly in a direction perpendicular to the longitudinal direction of the rod (40), the second driving tool bit (43) including a first end with two sides which is integral with the second end of the rod, and a third driving tool bit (42) and a fourth driving tool bit (420) respectively projecting laterally and outwardly from the two sides of the second driving tool bit in a direction perpendicular to the longitudinal direction of the rod and perpendicular to a longitudinal direction of the second driving bit.

5,588,170


METHOD AND DEVICE FOR TREATING AN IN PARTICULAR TENSION-SENSITIVE TEXTILE WEB

Christian Strahm, Bronschhofen, Switzerland, assignor to Solipat AG, Zug, Switzerland
Filed Jan. 20, 1995, Ser. No. 375,653
Claims priority, application Switzerland, Jan. 28, 1994, 00254/94

U.S. Cl. 8—149.1

Int. Cl.⁶ D06B 3/12

15 Claims



1. Method of treating a tension-sensitive textile web with a treatment medium, said method comprising steps of
- moving the textile web over at least two rollers, through a narrow shaft defined by walls, said walls having at least one curved segment formed in part by a surface portion of one of said rollers, and
- applying said treatment medium under pressure to the web at said curved segment.

5,588,171

DRAIN LINE CLEANING APPARATUS

James L. Hamann, Eldridge, Iowa, assignor to Pettibone Corporation, Lisle, Ill.
Filed Mar. 24, 1995, Ser. No. 410,478
Int. Cl.⁶ B08B 9/00

U.S. Cl. 15—104.12

9 Claims

1. A drain line cleaning apparatus comprising:
- a spin head adapted to rotate about a spin head axis; said spin head defining a cylinder; said cylinder further defining an internal surface having one or more notches each having a first surface and a second surface, said first surface forming a first angle with respect to said second surface;
- said first surface of said one or more notches defining an axis perpendicular to said first surface, said axis of said first surface forming a second angle with respect to said spin head axis;
- a generally cylindrical insert received at least partially within said spin head;
- cutting means attached to said spin head and adapted to revolve about said axis when said spin head rotates;
- means for providing pressurized water to said one or more notches of said spin head, whereby said spin head rotates when said one or more notches are impacted by pressurized water;
- said pressurized water providing means including at least one jet passageway defined by said insert along a radial plane of said insert, said radial plane being perpendicular to said spin head axis;
- wherein said pressurized water is directed by said at least one jet passageway to said first surface of said notch; and
- wherein said first surface of said one or more notches deflects said pressurized water along a path away from said spin head to generate thrust to propel said drain line cleaning apparatus.

respective one of the locking stations to operably affix the brush segment to the core and each brush segment including sides terminally defined by the inner end and the outer end of the brush segment;

the locking stations, locking portions and brush segments selected so that the entire side of each brush segment contacts the entire side of an adjacent brush segment, and the fibers of each segment extending parallel to a first plane, and the brush segments affixed relative to each other and the core to dispose the first plane orthogonal to the axis.

5,588,173

WINDSHIELD WIPER SYSTEM WITH ELECTRIC MOTOR


Stefan Battlogg, Haus Nr. 26, A-6771 St. Anton i/M, Austria
PCT No. PCT/AT93/00054, § 371 Date Nov. 23, 1994, § 102(e)
Date Nov. 23, 1994, PCT Pub. No. WO93/18944, PCT Pub. Date Sep. 30, 1993

PCT Filed Mar. 22, 1993, Ser. No. 313,028

Claims priority, application Austria, Mar. 23, 1992, 586/92
Int. Cl.⁶ B60S 1/08; 1/34

U.S. Cl. 15—250.3

17 Claims



1. In an automobile which includes a windshield wiper system for wiping a windshield, said system comprising:
- a wiper arm pivotally supported on an automobile and drive means for pivoting said wiper arm, said drive means including a reversible electric motor stationarily mounted on the automobile and a control unit controlling said electric motor, said electric motor having a stator portion and a rotor portion;
- a housing formed of a first housing part and a second housing part closing off said first housing part, said first housing part carrying said stator portion of said electric motor and being stationarily mounted on the automobile, said second housing part being drivingly connected to said rotor portion of said electric motor, being rotatable relative to said first housing part, and being non-rotatingly connected to said wiper arm.

5,588,174

DISPOSABLE HAZARDOUS MEDICAL WASTE COLLECTION SYSTEM

Geoffrey L. Godfrey, 9006 E. Camino Del Santo, Scottsdale, Ariz. 85260
Filed Aug. 21, 1995, Ser. No. 520,208
Int. Cl.⁶ A47L 13/52

U.S. Cl. 15—257.2

5 Claims

1. A disposable, single use collecting pan and brush comprising, in combination:
- (a) a collecting pan made of recycled paper and which has leading portion, a trailing portion, opposite end portions extending between said leading and trailing portions, side walls at each end thereof which extend between said leading and trailing portions and which together cooperate with a dividing wall to define first and second holding areas located at respective top and bottom portions of the collecting pan for collecting and receiving debris therein; said trailing portion


5,588,172

RADIAL BRUSH


Peter M. Blocca, Rochester, N.Y., assignor to Abtex Corporation, Dresden, N.Y.
Filed Jul. 11, 1994, Ser. No. 273,379
Int. Cl.⁶ A46B 3/02; 13/02

U.S. Cl. 15—179

9 Claims



1. A radial brush for rotation about an axis, comprising:
- (a) a core having a plurality of locking stations circumferentially spaced about the core; and
- (b) a plurality of preformed independent brush segments, each brush segment having an inner end and a spaced apart outer end, and a plurality of fibers integrally bonded at the inner end with free ends of the fibers defining the outer end, the inner end including a locking portion for mechanically engaging a



further including a gripping portion with a first elongated hole for receiving the user's fingers and a second hole for receiving the user's thumb;

- (b) a brush made of recycled plastic and which comprises a substantially planar body having a plurality of bristles extending from and along a side edge thereof, said bristles being substantially coplanar with said body, said brush being adapted to fit into either one of said holding areas; and
- (c) the collecting pan being easily utilized by both right and left-handed persons by selecting a respective one of said holding areas and by facing the other of said holding areas to the surface being cleaned.


5,588,175

FOOT VACUUM

John Zahner, 61-32 233rd St., Bayside, N.Y. 11364
Filed May 8, 1995, Ser. No. 438,103
Int. Cl.⁶ A47L 5/38

U.S. Cl. 15—310

5 Claims



1. A self-contained shoe soil removing device installable in a floor of a structure and being able to internally maintain soil having a weight being removed from a shoe of a person stepping thereon, comprising:

- a) a hollow and rectangular-paralleliped-shaped housing having a rectangular-paralleliped-shape, so that said self-contained shoe soil removing device can be easily stacked, stored, displayed, transported, and installed in, and removed out of, the floor of the structure as a result of its regular shape that is free of obstructions that could unintentionally engage the floor during installation and removal; said hollow and rectangular-paralleliped-shaped housing being positionable in the floor of the structure and containing a single chamber; said hollow and rectangular-paralleliped-shaped housing having an open top being flush with the floor of the structure when said hollow and rectangular-paralleliped-shaped housing is positioned in the floor of the structure, a flat, closed, and horizontally-oriented bottom disposed below said open top of said hollow and rectangular-paralleliped-shaped housing, and a closed and vertically-oriented side extending vertically perpendicularly upwardly from an end of said flat, closed, and horizontally-oriented bottom of said hollow and rectangular-paralleliped-shaped housing;

- b) a grill having a weight and covering said open top of said hollow and rectangular-paralleliped-shaped housing and being contactable by the shoe of the person stepping thereon;
- c) a hollow manifold contained in said hollow and rectangular-paralleliped-shaped housing; said hollow manifold having:
 - i) a hollow and vertically-downwardly-tapering upper portion with a wide open top being flush with said open top of said hollow and rectangular-paralleliped-shaped housing, a narrow open bottom being disposed below, and narrower than, said wide open top of said hollow and vertically-downwardly-tapering upper portion of said hollow manifold, and a side with at least one throughbore extending therethrough;
 - ii) a hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion extending horizontally-laterally-outwardly from below, and being in fluid communication with, said hollow and vertically-downwardly-tapering upper portion of said hollow manifold; said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold having an open top being coincident with said narrow open bottom of said hollow and vertically-downwardly-tapering upper portion of said hollow manifold, a first closed side being collinear with a side of said hollow and vertically-downwardly-tapering upper portion of said hollow manifold, a second closed side being parallel to said first closed side of said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold and extending outwardly from an opposite side of said hollow and vertically-downwardly-tapering upper portion of said hollow manifold, and a partially open bottom being disposed below said open top of said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold and having an open portion and a horizontally-oriented closed portion with a vertically-oriented throughbore extending vertically therethrough; and
 - iii) a hollow and rectangular-paralleliped-shaped lower portion extending horizontally-laterally-outwardly from below, in the same direction as, and in fluid communication with, said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold; said hollow and rectangular-paralleliped-shaped lower portion of said hollow manifold having a partially open top with an open portion being coincident with said open portion of said partially open bottom of said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold, a closed and horizontally-oriented bottom disposed below said open top of said hollow and rectangular-paralleliped-shaped lower portion of said hollow manifold and resting completely on said flat, closed, and horizontally-oriented bottom of said hollow and rectangular-paralleliped-shaped housing so as to be reinforced thereby, and a closed and vertically-oriented side extending vertically-perpendicularly-upwardly from an end of said closed and horizontally-oriented bottom of said hollow and rectangular-paralleliped-shaped housing so as to be reinforced thereby, so that said hollow and rectangular-paralleliped-shaped lower portion of said hollow manifold can withstand the weight of the soil being deposited and stored therein for eventual removal therefrom;
- d) a motor contained in said hollow and rectangular-paralleliped-shaped housing, external to said hollow manifold, so that the soil flowing through said hollow manifold does not contact said motor and cause damage thereto; said motor resting on said flat, closed, and horizontally-oriented bottom of said hollow and rectangular-paralleliped-shaped housing so as to be supported thereby;
- e) motor activating means for selectively starting and stopping said motor; said motor activating means contained in said

hollow and rectangular-paralleliped-shaped housing and contacting said grill and being in electrical communication with said motor;

- f) a vertically oriented shaft connected to, and extending vertically upwardly from, said motor and passing vertically through said vertically-oriented throughbore in said horizontally-oriented closed portion of said partially open bottom of said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold; and
- g) a horizontally-oriented turbine contained in said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold and being attached directly to said shaft for rotation therewith, so that when the person steps on said grill, said motor activating means causes said motor to start and rotate, which in turn causes said shaft to rotate, which in turn causes said horizontally-oriented turbine to horizontally rotate in said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold and create a low pressure area thereat which causes a vacuum to be created thereat that creates an air flow thereto that causes the soil from the shoe of the person stepping on the grill to be removed and directed downwardly through said hollow and vertically-downwardly-tapering upper portion of said hollow manifold to said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold where the centrifugal force created by the rotation of said horizontally-oriented turbine throws the soil horizontally outwardly through said hollow, horizontally-laterally-oriented, and parallelogram-shaped intermediate portion of said hollow manifold to said open portion of said partially open top of said hollow and rectangular-paralleliped-shaped lower portion of said hollow manifold where gravity directs the soil downwardly in said hollow and rectangular-paralleliped-shaped lower portion of said hollow manifold where the soil is deposited and isolated from disturbances created by the rotation of said horizontally-oriented turbine and stored for eventual removal therefrom without escaping into the atmosphere since said hollow manifold is completely contained within said hollow and rectangular-paralleliped-shaped housing.

for regulation of fluid flow and a means for controlling said fluid flow of said valve;

- c) a suction hose and integral water delivery tube secured to said narrow opening on one end, and secured on the other end to the outlet end of the valve frame housing by a water delivery tube;
- d) together with means having a suitable vacuum source and a fluid delivery tube secured to the inlet side of the mounted valve on said valve frame;
- e) a bristle support ring surrounding said dependent body portion of brush ring frame having vertically dependent air pervious bristles, an inside band of non-air pervious foam forming a throat to said dependent bristles, a primary layer of flexible, non-air pervious foam surrounding said bristle support ring and dependent bristles, a secondary layer of non-air pervious foam surrounding said primary foam layer, and an outside layer of non-air pervious protective foam surrounding the primary and secondary said layers;
- f) a spray nozzle mounted in said brush ring housing centrally of said depending body portion which is supplied by the water delivery tube extending through said hollow brush ring frame housing.

5,588,177

BACKPACK VACUUM CLEANER

Steen M. Eriksen, Houmanns Allé 2, Copenhagen NV, Denmark

PCT No. PCT/DK94/00208, § 371 Date Nov. 28, 1995, § 102(e)
Date Nov. 28, 1995, PCT Pub. No. WO94/27485, PCT Pub.
Date Dec. 8, 1994


PCT Filed May 27, 1994, Ser. No. 553,282

Claims priority, application Denmark, May 28, 1993, 0619/93

Int. Cl.⁶ A47L 5/36

U.S. Cl. 15—327.5

12 Claims



1. A backpack vacuum cleaner comprising a housing enclosing a motor and an impeller to provide the suction effect and with a compartment for a filter bag, a connection branch for a suction hose, a hip strap to be applied around the hips of the bearer and a pair of shoulder straps, wherein the housing is divided in upper and lower parts connected with a flexible connection allowing a tilting movement between said upper and lower parts, said hip strap being fastened to the lower housing part and said shoulder straps extending from said lower housing part to said upper housing part and being mutually interconnected by means of an equalizing device for equalizing differences in tension between the straps in the pair of shoulder straps.

5,588,176


WATER RECOVERY WASH BRUSH

Thomas G. Sixsmith, 21812 Bass Lake Cir., Lake Forest, Calif. 92630, assignor to Thomas G. Sixsmith, Lake Forest, Calif.
Filed Jun. 12, 1995, Ser. No. 488,176

Int. Cl.⁶ A47L 9/06

U.S. Cl. 15—322

5 Claims



1. A hand operated washing device suitable for cleaning automotive or truck surfaces that captures and recovers used water or water/soap medium, said device comprising:

- a) a hollow brush ring frame housing having a circular narrow opening on one end and a dependent body portion of a wider circular opening on the other end;
- b) a hollow valve frame housing with identical circular openings on both inlet and outlet ends onto which is mounted a valve

5,588,178

IMPELLER FOR BLOWER/VACUUM


Li-Hsiung Liu, Tucson, Ariz., assignor to McCulloch Corporation, Tucson, Ariz.

Filed Jun. 7, 1995, Ser. No. 478,449

Int. Cl.⁶ A47L 5/24

U.S. Cl. 15—330

5 Claims



1. Apparatus having a vacuum mode of operation, comprising a housing, a drive shaft mounted in said housing for rotation on an axis, an impeller fastened to said drive shaft and rotatable therewith, said housing forming an air flow channel around said impeller, said channel having a central air intake opening adjacent said axis and an air outlet opening adjacent the outer periphery of said impeller, said impeller comprising a hub fastened to said drive shaft, a plurality of blades extending generally radially outwardly from said hub, and a back plate extending generally radially outwardly from said hub, each of said blades having a back edge attached to said back plate, said plurality of blades including a first set of blades and a second set of blades, said second set of blades including a mulching part adjacent said hub, said mulching part of said second set of blades extending substantially parallel to said axis of rotation and extending forwardly of said first set of blades.

5,588,179

DUST BOX EMPTYING DEVICE


Douglas A. Bargiel, Bowling Green; Jack L. Burgoon, Toledo, and Michael D. Combs, Bowling Green, all of Ohio, assignors to Clarke Industries, Inc., Bowling Green, Ohio

Filed Feb. 1, 1995, Ser. No. 381,726

Int. Cl.⁶ E01H 1/08

U.S. Cl. 15—349

15 Claims



1. In a sweeper having a hopper separated into a main hopper and a dust box, a filter disposed within the dust box and dividing the dust box into a clean side and a dirty side, the hopper having an inlet for influx of debris, the dust box having an inlet for influx of debris, the hopper being movable between a debris accumulation position and a debris discharge position, and an outlet in a wall of the dust box for removal of debris accumulated within the dust box, the sweeper characterized by:

a flap of resilient material disposed over the dust box outlet and operable to close the dust box outlet when the hopper is in the

debris accumulation position, and to open the dust box outlet in the debris discharge position, said flap having at least one opening therein through which debris is adapted to be discharged when the hopper is in its said debris discharge position.

5,588,180
HINGE


Brian Chester, Potts Point, Australia, assignor to Trychrest Proprietary Limited, Potts Point, Australia

Filed Aug. 22, 1994, Ser. No. 293,706

Int. Cl.⁶ E05D 1/00

U.S. Cl. 16—225

9 Claims



1. A hinge assembly provided between first and second members having respective side faces permanently hinged to one another to permit their hinging movement relative to one another, each of said members having an elongated edge face and being formed with a socket that opens at its elongated edge face; the hinge assembly comprising a rigid, one-piece, hinging element composed of first and second axially parallel trunnions and at least one intervening bar all integrally formed in said element, said bar being formed as a web and said trunnions each including at least one cylindrical section, the cylindrical sections of respective trunnions being interconnected by said bar and said first and second members respectively received in said sockets in said first and second members respectively in a manner which allows rotation of each member about the axis of the respective trunnion; the bar interconnecting the trunnions extending through the openings from the sockets, which openings are shaped to allow angular displacement of the bar about an axis extending parallel to and lying between the axes of respective trunnions, and wherein the axial length of said one cylindrical section of each trunnion is greater than the length parallel to said elongated edge face of the opening through which the bar extends, whereby the socket completely surrounds part of the axial length of the trunnion.

5,588,181

HINGE FOR A GLASS SHOWER DOOR

Michael R. Sutton, 15745 E. Alta Vista Way, San Jose, Calif. 95127


Filed Mar. 23, 1995, Ser. No. 409,200

Int. Cl.⁶ E05D 5/02

U.S. Cl. 16—252

20 Claims

1. A hinge, comprising:
at least one clamping member, said clamping member being generally U-shaped, said clamping member having a first leg and a second leg, said first leg having an end,
a strip member, said strip member being generally shaped like a lower case h, said strip member having an upper leg, said upper leg having an end,
and a point of rotation at which said end of said first leg of said clamping member is joined with said end of said upper leg of said strip member.



5,588,182

ARRANGEMENT FOR SECURING A DOOR TO AN ENCLOSURE


Alan W. Brownlie; David T. Middleton, Jr., both of Skaneateles, N.Y.; James W. Robertson, Oberlin, and Francis J. Shay, Palmyra, both of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Division of Ser. No. 32,890, Mar. 18, 1993, Pat. No. 5,473,115. This application May 31, 1995, Ser. No. 455,925

Int. Cl.⁶ E05D 1/06

U.S. Cl. 16—268

8 Claims



1. A securing arrangement for securing a door to an enclosure to permit pivoting of the door between open and closed positions, comprising:

at least one leg extending to an end thereof from a door for pivotal connection thereof to an enclosure;

a mounting section of said enclosure associated with said leg and shaped to define a clearance for said leg end to permit said leg end to be pivoted a selected angular distance when said door is rotated between open and closed positions; and an axle at least including a segment protruding from a side surface of said leg end transversely to define a pivoting axis, said axle being affixed to said leg end and said mounting section in a manner permitting pivoting with respect to at least one of said leg and said mounting section,

said mounting section including a bearing surface adjacent said side surface of said leg end and having an axle-receiving aperture extending at least into said bearing surface, said bearing surface being shaped to define a two-tiered seating providing for said leg end and said side surface thereof to be translated along said pivot axis between first and second positions respectively,

said mounting section further including stop means cooperable with said leg end when said door has been rotated to said open position and said side surface of said leg end has become translated to said second level, to selectively inhibit rotation of said door from said open position to said closed position, whereby said two-tiered seating permits said leg end and its said side surface to be translated along said pivoting axis, from a first level when said door is in said closed position, to said second level when said door has been pivoted to said open position, and prevents said door to be pivoted from said open position to said closed position unless said leg end has first been translated to said first level by manipulation of said door.

5,588,183

Patent Not Issued For This Number

5,588,184

BELT BUCKLE


Kuo-Jen Chen, No. 187, Hua Yin Street, Taipei, Taiwan

Filed Feb. 20, 1996, Ser. No. 604,023

Int. Cl.⁶ A44B 1/00

U.S. Cl. 24—170

2 Claims



1. A belt buckle of the type comprising a belt having a fixed end, a free end, and a longitudinal series of transverse teeth raised from said free end at a back side, a buckle body, a belt catch holder pivotably connected to said buckle body by a first pivot pin, a serrate plate pivotably connected to said belt catch holder by a second pivot pin to hold down the fixed end of said belt, and belt catch means for securing the free end of said belt to said buckle body, wherein said belt catch means comprises:

a recess formed on said belt catch holder through which said first pivot pin passes;

a horizontal rib raised from said belt catch holder above said recess;

a belt catch mounted in said recess and turned about said first pivot pin, said belt catch comprising a stop wall stopped against said horizontal rib, an arched pawl forced into engagement with the transverse teeth of the free end of said belt, a bottom blind hole; and

a compression spring mounted within said recess, having one end stopped at a bottom wall inside said recess and an opposite end fastened to the bottom blind hole of said belt catch to render an outward pressure to said belt catch, causing said belt catch to force said pawl into engagement with the transverse teeth of said belt.

5,588,185

ZIPPER CLOSURE


Christian Covi, Fritzens, and Werner Steinechner, Jenbach, both of Austria, assignors to D. Swarovski & Co., Wattens, Austria

Filed May 10, 1995, Ser. No. 437,979

Int. Cl.⁶ A44B 19/02; 19/06

U.S. Cl. 24—381

10 Claims



1. A zipper closure comprising:
first and second longitudinal bands each having a longitudinal edge bead;
first and second rows of plastic teeth mounted on said beads of said first and second bands, respectively, such that said first row of teeth face said second row of teeth and are offset therefrom in the longitudinal direction of said bands;
each said tooth extending in a direction normal to said longitudinal direction and having a base end mounted on the respective said band and a free end having formed therein a channel extending parallel to said longitudinal direction, each said tooth having a configuration that is symmetrical relative to a center plane of said tooth extending in said normal direction thereof, each said tooth having an upper surface having embedded therein a decorative stone, and each said tooth having on opposite sides thereof and on opposite sides of said center plane thereof respective support surfaces, each said support surface extending outwardly from and defining with an adjacent side surface of said tooth a recess that is open toward opposite ends thereof in a direction of thickness of said tooth;
said zipper closure having a closed position whereat said first and second rows of teeth mesh, with said channel at said free end of each said tooth receiving said edge bead of the respective other said band, with said opposite support surfaces of each said tooth being in abutting contact with support surfaces of adjacent teeth of said other band, and with middle points of said decorative stones of all of said teeth aligned in a straight line extending in said longitudinal direction.

5,588,186

BELT WITH RATCHET TYPE BUCKLING MEANS

Soon-Myung Ko, 122-1703 Olympic APT, Bangee-Dong, Songpa-gu, Seoul 138-150, Rep. of Korea


Filed May 26, 1995, Ser. No. 451,179

Int. Cl.⁶ A44B 11/00

U.S. Cl. 24—585

3 Claims

1. A belt with ratchet type buckling means comprising:
a buckle coupled to an end portion of the belt, the top and bottom walls of said buckle having a screw hole and a rectangular hole respectively;
a ratchet part provided on the back surface of the other end portion of the belt; and
a rotatable cylinder vertically placed between the screw hole and the rectangular hole and rotatably coupled to the screw hole;
a pawl coupled to said cylinder and adapted for selectively engaging with said ratchet part;
a vertically movable push rod received in said cylinder such that the bottom of the push rod projects out of the rectangular hole, said push rod being biased by a spring member downward; and



means for selectively rotating said cylinder along with the pawl to make the pawl disengage from the ratchet part when said push rod vertically moves up in the cylinder.

5,588,187

EXTRUDED ZIPPERS FOR UPHOLSTERY APPLICATIONS


Henry L. Swain, Readington, N.J., assignor to Illinois Tool Works Inc., Glenview, Ill.

Filed Aug. 17, 1995, Ser. No. 516,297

Int. Cl.⁶ A44B 17/00; B65D 33/00

U.S. Cl. 24—587

9 Claims



1. An extruded zipper comprising:
a first flexible closure strip and a second flexible closure strip;
each flexible closure strip being extruded from a polymeric resin material, and having a web, an interlocking portion, and a flange; said web and said flange of each flexible closure strip extending from its respective interlocking portion substantially parallel to one another and defining therebetween on each flexible closure strip a groove; said interlocking portions of said first and second flexible closure strips being interlockable with one another in an interference fit; wherein said web and said interlocking portion of said first flexible closure strip are substantially coplanar with one another; said web and said flange of said second flexible closure strip are substantially coplanar with one another; and said grooves between said flange and said web of each of said first and second flexible closure strips are of substantially identical width;
so that, when said interlocking portions of said first and second flexible closure strips are interlocked with one another, said flanges of said first and second flexible closure strips are substantially coplanar with one another and said webs of said first and second flexible closure strips are substantially coplanar with one another.

5,588,188

SWAGED CABLE SWIVEL HOOK ASSEMBLY AND SWIVEL HOOK THEREFOR


Richard A. Jermyn, Jr., Panama City, Fla., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Nov. 20, 1995, Ser. No. 559,877

Int. Cl.⁶ A44B 13/00

U.S. Cl. 24—598.7

20 Claims



5. A swaged swivel hook assembly for attachment to an elongated cable, said assembly comprising:

- (a) a swivel hook including
(i) an arcuate-shaped hook body defining a cavity and having a pair of upper and lower end portions spaced apart from one another and defining an opening through said hook body to said cavity;
(ii) means defining an upper bore through said upper end portion of said hook body;
(iii) means defining a lower bore through said lower end portion of said hook body, said upper and lower bores for receiving a portion of an elongated cable to provide a closure of said opening through said hook body to said cavity;
(iv) means forming an upper socket in said upper end portion of said hook body adjacent to said upper bore therethrough; and
(v) means forming a lower socket in said lower end portion of said hook body adjacent to said lower bore therethrough;
(b) an upper swage element for attachment to the portion of the elongated cable at a first location thereon and being removably seatable within said upper socket in said upper end portion of said hook body for supporting said hook body on the elongated cable; and
(c) a lower swage element for attachment to the portion of the elongated cable at a second location thereon spaced below the first location thereon and being removably seatable within said lower socket in said lower end portion of said hook body for securing to and releasing from said hook body the closure provided by the portion of the cable extending through said upper and lower bores of said hook body.

5,588,189

BUCKLE FOR VEHICLE SEAT BELT SYSTEM

Patrick J. Gorman, White Lake; Phillip D. Yee, Troy, both of Mich., and Mark F. Gray, New Market, Canada, assignors to TRW Vehicle Safety Systems Inc., Lyndhurst, Ohio


Filed Aug. 23, 1995, Ser. No. 518,231

Int. Cl.⁶ A44B 11/00

U.S. Cl. 24—632

16 Claims

1. A buckle for use in a vehicle seat belt system, said buckle comprising:
a base at least partially defining a cavity for receiving first and second tongues of the seat belt system, each of the tongues



- being movable a fully inserted distance into the cavity along first and second insertion paths, respectively;
a first latch plate supported by said base and being movable between a latched position preventing withdrawal of the first tongue from the cavity and an unlatched position permitting withdrawal of the first tongue from the cavity;
a second latch plate supported by said base and being movable between a latched position preventing withdrawal of the second tongue from the cavity and an unlatched position permitting withdrawal of the second tongue from the cavity;
a first blocking member having a portion located in the second insertion path for blocking movement of the second tongue the fully inserted distance into the cavity until the first tongue moves a first predetermined distance into the cavity along the first insertion path; and
a second blocking member having a portion located in the first insertion path for blocking movement of the first tongue the fully inserted distance into the cavity until the second tongue moves a second predetermined distance into the cavity along the second insertion path.

5,588,190

ACCESSORIES


Takashi Sato, Chiba, Japan, assignor to Murao Co., Ltd., Chiba, Japan

Filed Jun. 30, 1995, Ser. No. 497,395

Int. Cl.⁶ A44C 11/00; A44B 21/00

U.S. Cl. 24—682.1

8 Claims



1. An accessories wherein a series of decorative bodies are coupled one after another by means of wire string, each end of the wire string is passed through a through-passages formed in a wire string fastener and through a turn-back portion of clasp, the end of the wire string thus passed through is then turned back to be again passed through the through-passages where said each of the wire string is fixed by means of a fixing means, which is characterized in that:
each of said wire string fasteners is provided with a fastening hole, one end of which being communicated with said through-passages and the other end of which being open to outside;

said fixing means is formed of fixing pin which can be fittingly inserted into said fastening hole; and said fixing pin is provided on its peripheral wall portion with a collapsible projected portion extending slightly larger than the inner diameter of said fastening hole, said projected portion being disposed at such a location on said fixing pin that said projected portion can be press-contacted with the vicinity of the opening portion of the fastening hole so as to be held by said opening of the fastening hole before the tip portion of the fixing pin is introduced into said through-passage and that said projected portion can be collapsed and frictionally held by the inner wall of said fastening hole when said tip portion of said fixing pin is further inserted into said through-passage.

5,588,191

ANCHORING EYELET FOR TARPAULINS AND SIMILAR COVERINGS

Peter Solbeck, Rungsted Kyst, Denmark, assignor to Polysheet A/S, Herlev, Denmark

PCT No. PCT/DK93/00314, § 371 Date Apr. 20, 1995, § 102(e) Date Apr. 20, 1995, PCT Pub. No. WO94/09232, PCT Pub. Date Apr. 28, 1994



PCT Filed Sep. 30, 1993, Ser. No. 416,891

Claims priority, application Denmark, Oct. 20, 1992, 1278/92; Dec. 28, 1992, 1564/92

Int. Cl.⁶ A43C 5/00

U.S. Cl. 24—713.6

12 Claims



1. An anchoring eyelet for tarpaulins and similar coverings of a thermoplastic foil material, which eyelet is designed as a relatively thin, flat and substantially annular disc (1) of plastic material provided with an eyelet opening (2), characterized in that the peripheral part of the eyelet disc is designed with indentations to provide increased resiliency to said peripheral part.

5,588,192

PROFLED CYLINDER FOR TEASELING AND/OR FLUFFING MACHINES

Franco Bertoldo, Brogliano, and Gino Dalla Vecchia, Santorso, both of Italy, assignors to Sperotto Rimar S.p.A., Milan, Italy

Filed Jan. 27, 1995, Ser. No. 379,154


Claims priority, application Italy, Jan. 27, 1994, M194A0130

Int. Cl.⁶ D06C 11/00

U.S. Cl. 26—37

1 Claim

1. A profiled cylinder for a teasinging and/or fluffing machine, comprising:
a cylinder having a generally cylindrical outer peripheral surface, two axially opposite ends, and, projecting axially outwards at said ends, two respective support hubs, for rotation of the cylinder about a longitudinal axis thereof;



each said outer peripheral surface having a circumferentially extending series of alternating crests and recesses, each extending from end to end of said surface;
each crest being defined between two angularly opposite flanks, both of which are oblique to said longitudinal axis, so as to twist about said axis;
said surface being arranged for abraiding engagement with a fabric by turning of the cylinder about said axis while maintaining the fabric in engagement with said surface;
each said crest and each recess being generally arched in transverse cross-sectional shape, each recess having a smaller radius of curvature in transverse cross-sectional shape than each crest;
both said flanks of each crest twisting about said axis in two opposite angular senses, so that each crest is trapezoid-shaped in front elevational profile; and
on each crest, a respective one of said flanks being generally flat in transverse cross-sectional profile and the other being generally convex in transverse cross-sectional profile.

5,588,193

Patent Not Issued For This Number

5,588,194

METHOD AND DEVICE FOR THE ACCUMULATION OF A YARN OVERLENGTH BETWEEN A BOBBIN CREEL AND THE BEAM ON A BEAMING MACHINE

Horst Ulbrich, and Martin Fuhr, both of Niederuzwil, Switzerland, assignors to Benninger AG, Uzwil, Switzerland

Filed Oct. 4, 1995, Ser. No. 538,649



Claims priority, application Switzerland, Nov. 10, 1994, 3363/94

Int. Cl.⁶ D02H 13/22

U.S. Cl. 28—194

11 Claims

1. Method of accumulating an overlength of yarns between a



bobbin creel (1) and the beam (5) of a beaming machine (4), upon cessation in beaming, said method comprising steps of

deflecting a yarn warp (2) from a beaming position into an accumulation position under the formation of yarn loops by means of accumulator rollers (13, 13') that are displaceable in relation to one another, while rotating the beam (5) in a reverse direction,

subjecting each yarn to a defined braking tension at the bobbin creel, while maintaining the reverse speed of the beam at less than the accumulation speed of the accumulator rollers so that the length difference arising from the difference between the reverse speed and the accumulation speed is compensated for by further withdrawal of yarns from the bobbin creel under the influence of yarn braking tension.

5,588,195

ELECTRONIC-COMPONENT MOUNTING APPARATUS

Koichi Asai, Nagoya; Koso Matsumoto, Aichi, and Yasuo Muto, Chiryu, all of Japan, assignors to Fuji Machine Mfg. Co., Ltd., Aichi-ken, Japan


Filed Sep. 14, 1995, Ser. No. 527,984

Claims priority, application Japan, Sep. 26, 1994, 6-229496

Int. Cl.⁶ H05K 13/04

U.S. Cl. 29—33 M

11 Claims



1. An electronic-component mounting apparatus, including a frame member,
a movable member supported by said frame member such that said movable member is movable relative to the frame member,
a moving device which moves said movable member relative to said frame member,
a mounting head which is provided on said movable member and mounts an electronic component on an object such as a printed circuit board, and
at least two devices selected from (a) at least one rotating device including a first actuator which rotates said mounting head about an axis line thereof, (b) at least one advancing and retracting device including a second actuator which advances and retracts said mounting head in opposite directions parallel to an axis line thereof, respectively, (c) at least one vacuum-supply control device including a third actuator which controls vacuum supply to a suction nozzle of said mounting head, and (d) at least one suction-nozzle selecting device including a fourth actuator which selects one of a plurality of suction nozzles of said mounting head,
said at least two devices including at least two actuators selected from at least one said first actuator, at least one said second actuator, at least one said third actuator, and at least one said fourth actuator,

wherein the improvement comprises:

said at least two actuators including at least two electric actuators which are provided on said movable member and are operable on electric energy;

a power source which is provided on said frame member and provides said electric energy;

a main control device which is provided on said frame member;

an actuator control device which is provided on said movable member and controls said electric actuators;

an electricity supplying device which includes a first supplying section provided on said frame member and a second supplying section provided on said movable member and which supplies said electric energy from said power source to said actuator control device, without having any wire connection between said first and second supplying sections; and

an information transmitting device which includes a first transmitting section provided on said frame member and a second transmitting section provided on said movable member and which transmits, between said main control device and said actuator control device, information needed to control said electric actuators, without having any wire connection between said first and second transmitting sections.

5,588,196

METHOD FOR MAKING A CONTAINER FROM RECYCLED PRODUCT

Judy A. Samelson, 75 Wilson's Ln., Needham, Mass. 02194


Division of Ser. No. 154,820, Nov. 19, 1993, Pat. No.

5,464,108. This application Jun. 23, 1995, Ser. No. 493,891

Int. Cl.⁶ B21K 21/16

U.S. Cl. 29—401.1

2 Claims



1. A method of recycling a plastic, substantially cylindrical, conventional, soda bottle having an upwardly extending and gradually inwardly sloping neck extending from the cylindrical holding section, into a container for articles comprising the steps of:

a. cutting the cylindrical side wall of said bottle with a first horizontal cut extending between points on a diameter of the side wall of said bottle;

b. making a second cut in an arc extending between said points on said same diameter toward the neck of said bottle, and


c. removing said neck end from said cylindrical holding section, said holding section thereby forming a holding cavity and a closing mechanism, at least a portion of said remaining portion of said side wall defining a fold-over flap, hinged about said points on said diameter, said first cut and said second cut extending between said diameter points in the side wall of said bottle.

5,588,197

METHOD OF MANUFACTURING METALLIC VACUUM DOUBLE-WALLED CONTAINER
 Yasuhiko Satomi, Seiichi Itoh, Eiji Otsuka, Jun Yamaki, and Takashi Kato, all of Tokyo, Japan, assignors to Nippon Sanso Corporation, Tokyo, Japan
 Division of Ser. No. 165,405, Dec. 10, 1993, abandoned. This application May 16, 1995, Ser. No. 442,202
 Claims priority, application Japan, Dec. 24, 1992, 4-344927
 Int. Cl.⁶ B23P 19/04

U.S. Cl. 29-455.1

2 Claims



1. A metallic vacuum double-walled container manufacturing method comprising the steps of:
 rolling at least the steel plate of an outer container to a Vickers hardness of 250-600;
 shaping said outer container into a cylindrical body;
 forming a metallic double-walled container by joining said outer container and a processed inner container at their mouth portions;
 heat treating said metallic double-walled container at a temperature of 200°-600° C. under a vacuum; and
 vacuum sealing the space between the two walls of said metallic double-walled container.


5,588,198

METHOD OF REGULATING RESONANCE FREQUENCY OF SURFACE-MOUNTABLE ANTENNA
 Kazunari Kawahata, and Yuichi Kushihi, both of Kyoto, Japan, assignors to Murata Manufacturing Co., Ltd., Japan
 Filed Mar. 6, 1995, Ser. No. 399,238
 Claims priority, application Japan, Mar. 9, 1994, 6-038680
 Int. Cl.⁶ H01P 11/00

U.S. Cl. 29-600

12 Claims

1. A method of regulating the resonance frequency of a surface-



mountable antenna, comprising the steps of:


- preparing a surface-mountable antenna including a substrate made of a dielectric material, a groove being formed on an upper surface of said substrate to have end portions at a pair of opposite end surfaces of said substrate, a radiating electrode being formed on the inner peripheral surface of said groove, a feeding electrode being formed on one of said pair of opposite end surfaces of said substrate in conductive connection with said radiating electrode, a ground electrode being formed on one of said pair of end surfaces to be insulated from said feeding electrode, and an end electrode being formed on the other one of said pair of opposite end surfaces of said substrate; and
 partially trimming said radiating electrode, said ground electrode or said end electrode for regulating the resonance frequency of said surface-mountable antenna.

5,588,199

LAPPING PROCESS FOR A SINGLE ELEMENT MAGNETORESISTIVE HEAD
 Mohamad T. Krounbi; Hin P. E. Lee, both of San Jose, and David J. Seagle, Morgan Hill, all of Calif., assignors to International Business Machines Corporation, Armonk, N.Y.
 Filed Nov. 14, 1994, Ser. No. 339,523
 Int. Cl.⁶ G11B 5/42

U.S. Cl. 29-603.1

3 Claims




1. A method of manufacturing a magnetoresistive head, comprising the steps of:
 depositing a magnetoresistive element on a substrate, said magnetoresistive element having end regions separated by a central region;
 depositing first and second electrically conductive leads in contact with said magnetoresistive element in said end regions, each said conductive lead having a portion extending beyond said magnetoresistive element;
 depositing at least one shunt resistor between said magnetoresistive element and an air bearing surface, said shunt resistor being electrically connected at a first end thereof to said extending portion of the first conductive lead and being electrically connected at a second end thereof to said extending portion of the second conductive lead, said shunt resistor being electrically connected at a central point thereof to said magnetoresistive element in said central region, said shunt resistor and said MR element forming a resistor network;
 lapping said air bearing surface for removing said shunt resistor, said extending portions of the conductive leads and portions of said magnetoresistive element for providing a magnetoresistive element having a desired element height; and
 monitoring the electrical resistance of said resistive network during said lapping for determining the amount of lapping skew.

5,588,200

TIGHTENED DISTRIBUTION OF MAGNETIC-HEAD SUSPENSION-ASSEMBLY STATIC ROLL BY INFRARED STRESS RELIEF
 Dale F. Schudel, T. Lamsai A. Wangnoi THX, assignor to K. R. Precision Public Company Limited, Axutthaya THX
 Filed May 15, 1995, Ser. No. 441,351
 Int. Cl.⁶ G11B 5/10

U.S. Cl. 29-603.01

14 Claims



1. In a manufacturing process for a magnetic head suspension assembly having a head slider mounted on a metallic suspension intended for read/write application in very close proximity over a surface of a magnetic disc, a method for adjusting static roll characteristics of said suspension assembly to conform to a predetermined parameter, wherein said static roll characteristics are measured by at least one deformation parameter indicative of the suspension assembly's static roll attitude, the process comprising the following steps:

- (a) flexing said suspension assembly to a predetermined degree of deformation to cause said at least one deformation parameter indicative of the suspension assembly's static roll attitude to conform to said predetermined parameter; and
 (b) while the suspension assembly is in such flexed state, applying a beam of thermal energy to a predetermined target area in the suspension assembly for a predetermined time to relieve stresses in the suspension assembly so as to cause said at least one deformation parameter to conform to said predetermined parameters while the suspension assembly is in a free state.

5,588,201

PROCESS FOR PRODUCING A CAST RESIN COIL
 Friedrich Alber, Könen; Rudolf Dedelmahr, Aichtal; Winfried Jungnitz, Wellheim-Engelsberg; Hans Schott, Lenningen; Heinz Sesterhelm, Kirchheim, and Siegfried Weiss, Bissingen, all of Germany, assignors to Siemens Aktiengesellschaft, Munich, Germany
 PCT No. PCT/EP91/00552, § 371 Date Sep. 21, 1993, § 102(e) Date Sep. 21, 1993, PCT Pub. No. WO92/16955, PCT Pub. Date Oct. 1, 1992

PCT Filed Mar. 21, 1991, Ser. No. 122,424


Int. Cl.⁶ H01F 7/06

U.S. Cl. 29-605

14 Claims

1. A process for producing a cast resin coil comprising a plurality of axially superimposed flat coils each of the flat coils including an inner winding, an outer winding, and a plurality of spacers disposed between the inner and outer windings thereby defining a plurality of sector-shaped intervening spaces between the inner and outer windings, said method comprising the steps of:

- a) producing a first flat coil by:
 winding a first inner winding using a first conductive element;
 disposing a first plurality of spacers;
 winding a first outer winding from said first conductive element;



- applying a first layer of impregnable material between the first inner and outer windings in a first plurality of circumferential sections between each of the first plurality of spacers; and
 transferring the first conductive element from the first inner winding to the first outer winding in a first connecting web between two of the first plurality of spacers;
 b) producing a second flat coil by:
 winding a second inner winding using a second conductive element;
 disposing a second plurality of spacers;
 winding a second outer winding from said second conductive element;
 applying a second layer of impregnable material between the second inner and outer windings in a second plurality of circumferential sections between each of the second plurality of spacers; and
 transferring the second conductive element from the second inner winding to the second outer winding in a second connecting web between two of the second plurality of spacers;
 c) axially superimposing said first and second flat coils;
 d) aligning said first and second plurality of sector-shaped intervening spaces thereby forming a plurality of axial cooling channels;
 e) disposing a molding into each of the plurality of axial cooling channels;
 f) encapsulating the superimposed first and second flat coils, whereby the first and second plurality of spacers form stiffening webs between the inner and outer windings when encapsulated; and
 g) removing every molding from the plurality of axial cooling channels after encapsulation.

5,588,202

METHOD FOR MANUFACTURING AN OVERMOLDED SENSOR

Wayne L. Ehlers, Lanark; Kenneth L. Eichholz, Jr., and Mark F. Johnston, both of Freeport, all of Ill., assignors to Honeywell Inc., Minneapolis, Minn.


Filed Mar. 17, 1995, Ser. No. 406,079

Int. Cl.⁶ H01F 7/06

U.S. Cl. 29-606

17 Claims

1. A method for manufacturing a proximity sensor, comprising:
 providing a printed circuit board having a first side and a second side;
 perforating said printed circuit board to form a plurality of substrate sections connected together by a plurality of ribs, each of said plurality of substrate sections having a first plurality of electrically conductive paths formed thereon;
 attaching a first plurality of electronic components to said first side of each of said plurality of substrate sections, each of said first plurality of electronic components being connected in electrical communication with at least one of said first plurality of electrically conductive paths of a preselected one of said




plurality substrate sections to form a first electrical circuit on each of said plurality of substrate sections;
attaching an electrical coil to a first end of each of said plurality of substrate sections;
attaching an electrical connector to a second end of each of said plurality of substrate sections;
calibrating each of said first electrical circuits;
simultaneously forming a plurality of encapsulations, each of said plurality of encapsulations being disposed around one of said plurality of substrate sections and its associated electronic components, coil and connector; and
severing said ribs to detach each of said plurality of encapsulations from said printed circuit board.

5,588,203

NOZZLE FOR A VACUUM MOUNTING HEAD
Branko Bldefeld, Marietta, Ga., assignor to Matsushita Communication Industrial Corporation of America, Peachtree City, Ga.

Filed Feb. 28, 1995, Ser. No. 397,634
Int. Cl.⁶ B23P 19/04; H01L 21/68; H05K 13/04
U.S. Cl. 29—743 17 Claims




1. A nozzle for a mounting head of a component placement machine, comprising:
a positioning block defined by a top and a bottom, said top of said block having a particular area, and said bottom of said block having an area that is less than or equal to said particular area;

said block defining a plurality of spaced apart pads on top of said block, each of said pads having a top, and a pad hole in said top or said pad;
said block timer defining an opening in said bottom of said block; and
said block defining an interior air passage connecting each of said pad holes with said opening.

5,588,204

APPARATUS FOR INSTALLING SPRING RETAINING RINGS
Kenneth J. Rossman, Kendall Park, N.J., assignor to Rotor Clip Company, Inc., Somerset, N.J.
Continuation-in-part of Ser. No. 309,854, Sep. 21, 1994, abandoned. This application Aug. 21, 1995, Ser. No. 517,407
Int. Cl.⁶ B23Q 7/10; B23P 19/04
U.S. Cl. 29—809 8 Claims




6. An apparatus for installing a spring retaining ring having two legs separated by a gap into a groove of a workpiece, said apparatus comprising:
storage means for initial storage of said spring retaining ring;
a passageway for delivery of said spring retaining ring from said storage means to said groove of the workpiece;
a receiving window positioned at the junction of said storage means and said passageway, said passageway having interior and exterior portions and an open end remotely located from said receiving window, and orientation means positioned within said interior portion of the passageway for orientation of said spring retaining ring, said orientation means being an elongated member extending along a longitudinal axis of said passageway; and
a pusher movable within said passageway for forcible delivery of said spring retaining ring to said groove;
whereby upon engagement of said ring with said pusher said ring is moved through said passageway in such a manner that said orientation means is slidably received within said recess of said spring retaining ring preventing rotational movement of said ring within said passageway and said legs and said gap of the retaining ring face said groove of said workpiece.

5,588,205

METHOD OF MANUFACTURING A HIGH DENSITY INTEGRATED CIRCUIT MODULE HAVING COMPLEX ELECTRICAL INTERCONNECT RAILS
Jerry M. Roane, Austin, Tex., assignor to Staktek Corporation, Austin, Tex.
Division of Ser. No. 337,558, Jan. 24, 1995. This application Sep. 5, 1995, Ser. No. 523,201
Int. Cl.⁶ H05K 3/36
U.S. Cl. 29—830 6 Claims


1. A method of manufacturing a high density integrated circuit module which includes serpentine electrical interconnect rails, comprising the steps of:



(a) providing a stack of integrated circuit devices;
(b) mounting a rail assembly, comprised of a plurality of non-linear interconnect rails, to the upper major surface of the uppermost integrated circuit device within said stack, wherein said rail assembly includes upper and lower shorting bars;
(c) removing said upper shorting bar from an upper portion of said rail assembly, wherein said upper portion extends over said uppermost integrated circuit device in said stack;
(d) aligning said rails with selected electrical interconnect leads protruding from said integrated circuit devices in said stack; wherein selected electrical interconnect leads are inserted into openings formed in said rails;
(e) soldering said selected leads protruding through said openings in said rails to said rails; and
(f) removing said lower shorting bar from said rail assemblies.

5,588,206

METHOD FOR INSERTING WIRE-EQUIPPED TERMINAL IN CONNECTOR HOUSING
Takamichi Maejima; Toshihiro Inoue; Hiroshi Hasegawa, and Atsushi Nakano, all of Shizuoka, Japan, assignors to Yazaki Corporation, Tokyo, Japan
Filed Nov. 22, 1994, Ser. No. 344,665
Claims priority, application Japan, Nov. 29, 1993, 5-298102
Int. Cl.⁶ H01R 43/00
U.S. Cl. 29—845 5 Claims




1. A method of inserting a series of wire-equipped terminals held in clips of a wire-clamping rod into containers of a connector housing by means of openable and closable terminal-grasping picks and wire-clamping plates of an insertion unit, comprising the steps of:

a) vertically moving said insertion unit from a first position to a second position with respect to said wire-clamping rod in a direction to locate said picks in grasping relation with respect to the terminal of a first wire-equipped terminal and said plates in clamping relation to the wire thereof;
b) activating said picks and said plates to grasp said terminal and clamp said wire;
c) vertically moving said insertion unit in a reverse direction to separate said first wire-equipped terminal from said the associated clip;

d) advancing said insertion unit with respect to said connector housing while sequentially opening said picks and said plates to insert said first wire-equipped terminal in a first predetermined container in said housing for receiving said first wire-equipped terminal;
e) returning said insertion unit to said first position;
f) at anytime during the period of performance of step c) to step e) with respect to said first wire-equipped terminal, establishing the position of a second wire-equipped terminal with respect to a second predetermined container in said connector housing for receiving said second wire-equipped terminal; and
g) repeating steps a) through f) with respect to each of said second and succeeding wire-equipped terminals in said series.

5,588,207

METHOD OF MANUFACTURING TWO-SIDED AND MULTI-LAYERED PRINTED CIRCUIT BOARDS
Kouji Kawakita, Joyo; Masahide Tsukamoto, Nara; Yasukiho Horio, Osaka; Seichi Nakatani, Hirakata, and Akihito Hatakeyama, Kadoma, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan
Division of Ser. No. 124,317, Sep. 20, 1993, Pat. No. 5,440,075.
This application May 5, 1995, Ser. No. 437,085
Claims priority, application Japan, Sep. 22, 1992, 4-252594
Int. Cl.⁶ H01K 3/10; H05K 3/20
U.S. Cl. 29—852 36 Claims




1. A method for producing a two-sided printed circuit board, comprising the steps of:
forming a plurality of through-holes in a base;
inserting a conductive spherical ball into each of the through-holes; and
heating and pressurizing the base and the conductive spherical balls while holding the base between two conductive layers so that the conductive spherical balls are deformed to substantially fill the through-holes thereby electrically connecting the conductive spherical balls and the two conductive layers, wherein the thickness of the base after the step of heating and pressurizing is smaller than the diameter of the conductive spherical ball before the step of heating and pressurizing.

5,588,208

METHOD OF ASSEMBLING SET OIL RING ON PISTON
Yutaka Sato; Koichi Morita; Shuzo Fujimoto; Satoru Ichihashi, and Kohji Ohsawa, all of Sayama, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan
Filed Dec. 13, 1994, Ser. No. 357,270
Claims priority, application Japan, Dec. 22, 1993, 5-325364
Int. Cl.⁶ B23P 15/00
U.S. Cl. 29—888,044 4 Claims

1. A method of assembling a set oil ring in a piston ring groove having opposed wall surfaces in a piston in spaced relation from an end thereof, the set oil ring comprising a spacer ring and a pair of side rail rings having split end portions wherein the side rail rings



are to be placed in the piston ring groove on both sides of the spacer ring, including the steps of:

mounting the pair of side rail rings in axially spaced relation on a periphery of a guide member which can be fitted onto an external surface of the piston;


moving the guide member into concentric fitted disposition with respect to said piston;

sequentially pushing the pair of side rail rings from a front end of the guide member while the guide member is kept fitted onto the external surface of the piston, into first and second groove portions defined between cooperating oppositely spaced surfaces of the spacer ring and the piston ring groove when the spacer ring is positioned in the piston ring groove, said first groove portion being on the side of the spacer ring proximate the end of the piston, and said second groove portion being on the side of the spacer ring away from the end of the piston;

the improvement comprising the steps of:

in assembling one of the side rail rings into the first groove portion, axially moving one of the guide member and the piston relative to the other to a first position to locate the front end of the guide member at substantially the same level as a wall surface of the first groove wall portion, disposing a restricting member in front of the guide member while leaving a clearance exposing the first groove portion, and pushing the one of the side rail rings from the front end of the guide member into the first groove portion while continuously preventing overlap of the split end portions of the spacer ring by the restricting member; and in assembling the other of the side rail rings into the second groove portion, axially moving one of the guide member and the piston relative to the other to a second position to locate the front end of the guide member at substantially the same level as the surface of the spacer ring defining the second groove portion, and pushing the other of the side rail rings from the front end of the guide member into the second groove portion while continuously preventing overlap of the split end portions of the spacer ring by an internal surface of the guide member, whereby the assembling of one of the side rail rings into the first groove portion and the assembling of the other of the side rail rings into the second groove portion are made continuously by sequentially changing the position of the restricting member relative to the first groove portion and the position of the guide member relative to the second groove portion while always preventing overlap of the split end portions of the spacer ring throughout the assembling steps of the side rail rings.


5,588,209
METHOD AND APPARATUS TO MANUFACTURE STABILIZER BARS
Ian A. Fisher, Chesterfield, and Phillip Ferdani, Rugby, both of United Kingdom, assignors to The Tempered Spring Company Limited, England
Filed May 4, 1994, Ser. No. 237,759
Int. Cl.⁶ B28B 5/00; B23P 17/00
U.S. Cl. 29—897.2 14 Claims



1. A method of manufacturing a vehicle sway bar comprising:
 - (i) forming a steel rod into a desired shape of bar,
 - (ii) defining for said bar a first portion at which a first suspension component is to be molded onto the bar; a second portion spaced a predetermined distance along said bar from said first portion, at which a second suspension component is to be molded onto said bar; and a datum point separated from said first portion of said bar by a predetermined spacing,
 - (iii) disposing said bar with respect to a molding apparatus, said apparatus having a mold adapted to receive and enclose one of said first and second portions of said bar, a first reference part separated from said mold by said predetermined spacing and a second reference part spaced from said first reference part by a distance equal to said predetermined distance between said first and second portions of said bar, with said datum point of said bar at said first reference part of the apparatus so that said first portion is within said mold,
 - (iv) molding onto said first portion of said bar from rubber or plastics material a first suspension component,
 - (v) thereafter disposing said bar with respect to the molding apparatus with said first suspension component at said second reference part so that said second portion of said bar is within said mold, and
 - (vi) molding onto said second portion of said bar from rubber or plastics material a second suspension component.
7. A method of manufacturing a vehicle sway bar comprising:
 - (i) forming a steel rod into a desired shape of bar,
 - (ii) defining for said bar shape a first portion at which a first suspension component is to be molded onto said bar; a second portion spaced a predetermined distance along said bar from said first portion, at which a second suspension component is to be molded onto said bar, and a datum point separated from said first portion by a predetermined spacing,
 - (iii) disposing said bar with respect to a molding apparatus, said apparatus having a first mold adapted to receive and enclose said first portion of said bar, a second mold adapted to receive and enclose said second portion of said bar, a first reference part separated from said first mold by said predetermined spacing, and a second reference part spaced from said first mold and spaced from said second mold by a distance equal to said predetermined distance between the first and second

- portions of said bar, with the datum point of said bar at said first reference part of the apparatus so that said first portion of said bar is within said first mold,
- (iv) molding onto said first portion of said bar from rubber or plastics material a first suspension component,
- (v) thereafter disposing said bar with respect to said molding apparatus with said first suspension component at said second reference part so that said second portion of said bar is within said second mold, and
- (vi) molding onto said second portion of said bar from rubber or plastics material a second suspension component.


5,588,210
METHOD OF MANUFACTURING A UNITIZED SEAL
Frederick E. Lederman, Sandusky, Ohio, assignor to General Motors Corporation, Detroit, Mich.
Filed Aug. 5, 1994, Ser. No. 286,362
Int. Cl.⁶ B29C 45/08
U.S. Cl. 29—898 2 Claims



1. A method of manufacturing and assembling a unitized seal for installation in an annular space between outer and inner, relatively rotatable members, said annular space being bisected widthwise by a central imaginary cylinder and bisected lengthwise by a central imaginary plane perpendicular thereto, said method comprising,
 - providing an outer, generally channel-shaped casing with an annular web extending radially inwardly past said bisecting cylinder and a cylindrical seal wall extending in one axial direction from said annular web to a terminal edge, said terminal edge having a predetermined radial thickness,
 - providing an inner, generally channel-shaped casing with an annular web extending radially outwardly past said bisecting cylinder and a cylindrical seal wall substantially identical in length to said outer casing seal wall but extending in the opposite axial direction from said annular web to a terminal edge having a comparable radial thickness,
 - providing an integrally molded seal unit having, in a pre-assembly state, a pair of inner and outer disks lying on said central plane and sized so as to abut outer and inner casing annular webs respectively, said inner and outer disks also being joined at a frangible seam lying on said central bisecting cylinder, said inner and outer disks each having a pair of axially oppositely extending converging seal lips symmetrically disposed about said outer and inner casing seal walls respectively and defining an annular opening of lesser radial width than said seal walls,
 - concentrically aligning said inner and outer casings with said seal unit axially between, and
 - moving said aligned inner and outer casing axially together, thereby pushing said inner and outer casing cylindrical seal wall terminal edges axially into said respective annular openings and against said inner and outer disks, fracturing said seam, and pushing said inner and outer disks into abutment with said respective annular webs.

5,588,211
RAZOR WITH ANGLED BLADES AND GUIDES
Rafael Elul, P.O. Box 882941, San Francisco, Calif. 94188
Filed Oct. 29, 1994, Ser. No. 328,717
Int. Cl.⁶ B26B 21/06 5 Claims


U.S. Cl. 30—48



1. A razor comprising
 - an elongated blade having a longitudinal axis,
 - a blade holder connected to said blade,
 - an elongated member interconnected to said blade, said member having a slider plate fixedly inclined at an angle θ relative to the longitudinal axis of said blade and forming an elongated gap therebetween, said slider plate having a first end and a second end, the first end being attached to said blade holder, and
 - a support arm extending from said blade holder and attached to the second end of said slider plate.

5,588,212
SAFETY-BELT CUTTER
Antero Riihimäki, Soukankuja 4 B, FIN-02360, Espoo, Finland
Continuation-in-part of Ser. No. 23,084, Feb. 26, 1993, abandoned. This application Jan. 30, 1995, Ser. No. 380,424
Claims priority, application Finland, Mar. 17, 1992, U920219
Int. Cl.⁶ B26B 29/06; B60R 22/32 15 Claims


U.S. Cl. 30—123



1. A safety-belt cutter for cutting a safety-belt in the event of an emergency, the safety-belt cutter comprising:
 - a frame having an opening adapted for receiving a safety-belt therethrough, the frame completely encircling said safety-belt;
 - a cutting blade having a cutting edge attached to the frame and protruding into the opening, the blade engageable with the safety-belt disposed in said opening to cut the same upon movement of said frame transversely over said safety-belt positioned in said opening;
 - a slide disposed within the frame opening for receiving and closely supporting the safety-belt, support portions of the slide constraining the safety-belt to keep the safety-belt taut during the cutting movement of said blade; and


a guard means detachably secured to the frame and including a sheath positioned in front of the cutting blade cutting edge to prevent cutting of the safety-belt from inadvertent pulling movements upon said frame, the guard means detachable from the frame to remove said sheath from in front of the cutting edge to permit cutting of the safety belt.

5,588,213
CIRCULAR SAW WITH DUST TRAPPER
Alan M. Swanberg, 734 San Carlos Ct., Palo Alto, Calif. 94306
Filed Mar. 7, 1995, Ser. No. 400,036
Int. Cl.⁶ B27B 9/02
U.S. Cl. 30—124



1. A tool for collecting dust generated when sawing a board having a board surface using a saw of the type having a motor with a face surface and a mounting shaft extending perpendicularly from said face surface, said mounting shaft being coupled perpendicularly to a motor shaft of said motor with a circular saw blade rotatably mounted on said mounting shaft, said tool comprising:
a mounting plate having holes arranged for bolting said mounting plate to said face surface of said motor with a said mounting plate against said face surface with said mounting shaft extending through one of said holes of said mounting plate;
a hood having a base side with a slot and a first side having an edge joined perpendicularly to said base side along an edge of said base side and a second side having an exit opening adapted for attachment to a means for exhausting kerf from said hood and a plurality of other sides;
said base side, second side and said plurality of sides bounding an interior region within said hood;
said first side having an elongated slot through which said mounting shaft extends into said interior region of said hood and supports said blade in said interior region;
said mounting plate positioned slidably against and rotatably mounted on said first side between a first position with respect to said hood and a second position with respect to said hood; said first position being when said base side is positioned against said board surface and said circular saw is entirely positioned within said interior region and said interior region communicates only with said means for exhausting; and
said second position being wherein an edge of said saw blade extends through said slot and away from said base side whereby kerf generated in said interior region can escape only through said exit opening to said means for exhausting; a spring means for biasing said hood toward said first position.

5,588,214
SELF DEFENSE RING
Joe B. Nelson, 2012 Ogden La., Lancaster, Calif. 93535
Filed Oct. 10, 1995, Ser. No. 541,328
Int. Cl.⁶ B26B 27/00
U.S. Cl. 30—368




1. A new and improved self defense ring assembly comprising: ring means positionable on the hand of a user, said ring means including at least two ring members positionable over at least two fingers of said user, said at least two ring members being fixedly attached together by a center section, said center section includes a hollow interior portion;
and
blade assembly means forming a part of said ring means and including a retractable blade utilizable for self defense purposes, said blade assembly means being substantially retained within said hollow interior portion.

5,588,215
TRANSPORTABLE MEASUREMENT DEVICE FOR CHILDREN'S CLOTHES
Penny F. Hart, 500 E. 83rd St., Apt. 2G, New York, N.Y. 10028
Filed May 25, 1994, Ser. No. 248,702
Int. Cl.⁶ G01B 3/10
U.S. Cl. 33—2 R




1. An apparatus for translating the value of a child's age into a set of physical dimensions representing an approximation of the child's anatomical measurements for comparison with an item of apparel, comprising:
(a) an elongated member having a surface;
(b) a first reference-point on said surface and at least one age-based marking on said surface, each said at least one age-based marking indicating a unique age-based value, such that the distance between each said at least one age-based marking and said first reference-point approximates an anatomical dimension of a child having an age equal to that indicated by said at least one age-based marking, and further wherein each of said age-based markings states a different, specific, approximate age in months of a child wherein the distance between said first reference point and a select least one age-based marking can be compared to an item of apparel to determine if the item of apparel will fit a child whose age is approximately equal to the age represented by said select one of said at least one age-based marking.

5,588,216
GAS TANK GRAPHIC POSITIONING FIXTURE
David B. Rank, Waukesha, Wis.; Randall A. Bonebrake, Red Loin, and Spurgeon C. Stoner, York, both of Pa., assignors to Harley-Davidson Motor Company, Milwaukee, Wis.
Filed May 19, 1995, Ser. No. 444,999
Int. Cl.⁶ G01B 11/27; G03B 21/00
U.S. Cl. 33—286



1. A fixture for use in applying graphics to a part, said fixture having a support base, means mounted on said support base for fixing a part in a pre-determined fixed position on said base, said part fixing means including support means for supporting the part at three horizontally spaced apart locations for defining a fixed support plane for the part, a support member positioned horizontally above said support base, a pair of laser transmitters fixedly mounted on said support member in a horizontal spaced apart relation and vertically above said support base, said laser transmitters being constructed and arranged for projecting laser beams downwardly toward said base in planes, said laser transmitters being positioned such that said laser beams impact on a three dimensional part on said base as lines having a predetermined fixed alignment pattern whereby graphic material may be aligned on successive parts in an accurate repeatable basis.


5,588,217
LEVEL VIAL ASSEMBLY WITH ENCAPSULATED VIAL
Thomas A. Lindner, West Bend, and Joseph B. Coel, Watertown, both of Wis., assignors to Emplre Level Mfg. Co., Milwaukee, Wis.
Filed Mar. 1, 1995, Ser. No. 397,430
Int. Cl.⁶ G01C 9/24
U.S. Cl. 33—379



1. A liquid vial assembly comprising:
a liquid-containing vial having a seamless cylindrical wall made of plastic material;
a generally-cylindrical transparent outer sleeve extending along the wall and being slightly stretched therearound, such sleeve being made of a resilient material selected from a group of materials including polyvinyl chloride and polyurethane;
and wherein:


substantially the entirety of the vial is visible through the sleeve; and
the sleeve has ends which are open and free of seals, whereby the resistance of the vial to breakage is improved.

5,588,218
TEACHING PROTRACTOR
David Barry, and Camilla Barry, both of 49 Lomita Dr., Mill Valley, Calif. 94941
Filed May 24, 1995, Ser. No. 449,489
Int. Cl.⁶ G01B 5/24
U.S. Cl. 33—471



1. A protractor device for measuring and drawing angles, comprising:
first and second generally flat members each defining a pivot point, each member having a straight edge portion extending generally radially from said pivot points,
said straight edge portions offset from a line extending radially from said pivot point by an amount greater than 0.1 mm and less than 1.5 mm,
a means for rotatably attaching the two generally flat members such that the straight edge portions define an angle,
said first member further defining a semi-circular portion having a center coincident with the pivot point,
angle indicia located on said semi-circular edge portion, and
an indicator portion on the second member which intersects the angle indicia of the first member enabling the angle defined by the two straight edge portions to be measured.

5,588,219
ROLLED SHEET MATERIAL HAVING RELEASABLE ANTI-TACK GUIDE STRIP
Jeffrey A. Seabrooks, 1316 Coronado Blvd., Reynoldsburg, Ohio 43068
Filed Aug. 18, 1994, Ser. No. 292,935
Int. Cl.⁶ B65H 61/00
U.S. Cl. 33—733



1. A rolled sheet material having a guide strip, comprising:
- a rolled sheet material having a lateral width, lateral sides, lateral edges and a longitudinal axis; and
 - a guide strip disposed along one said lateral side of said rolled sheet material, said guide strip being coiled in a spiral so as to be substantially uniformly distributed between said lateral edges of said rolled sheet material, said guide strip being adhered to said rolled sheet material by a releasable adhesive and being releasable from said rolled sheet material, and said guide strip having a lateral width less than said lateral width of said rolled sheet material.

5,588,220

MEASURING TAPE DEVICE INCLUDING EXTERNAL CLEANING MEMBER


Michael Cousins, New York, N.Y.; Douglas Patrick, Lexington, Ky., and Carol T. Bassett, Patchogue, N.Y., assignors to U.S. Tape Company, Inc., Patchogue, N.Y.

Filed Feb. 28, 1994, Ser. No. 202,836

Int. Cl.⁶ G01B 3/10

U.S. Cl. 33—768

4 Claims



1. A container for a measuring tape, wherein the tape is wound around an internal spring and is arranged to be pulled from the container for a desired length of measurement, said container comprising:

- a housing within which said tape is wound, said housing having an opening formed therein for allowing said tape to be pulled from the housing;
- a flexible wiper flap located on an exterior surface of said housing so as to be located outside of said opening, said flexible wiper flap being urged against a surface of said measuring tape and said flexible wiper flap having a width and a length such that said flexible wiper flap and said measuring tape cover said opening to prevent dust and contaminants from entering the interior of the measuring tape container.

5,588,221

DRIVE SHAFT FOR A PAINT BRUSH AND ROLLER COVER CLEANING MACHINE

Larry Hoeltke, Alden, and Roger Fischer, Lancaster, both of N.Y., assignors to Shur-Line, Inc., Lancaster, N.Y.


Filed Sep. 28, 1995, Ser. No. 535,719

Int. Cl.⁶ F26B 17/24

U.S. Cl. 34—58

4 Claims

1. A drive shaft assembly for a manually operated paint brush and roller cover cleaning machine designed to free said brush and said roller cover of paint by centrifugal spinning, having a drive rod having a uniformly twisted spiralling blade portion and a flange extending radially from said blade portion, and having a clutch disk generated about an axis comprising a body portion having an opening through which said clutch disk axis passes and arms projecting radially from said clutch disk body portion, said



blade portion passing through said clutch disk opening and said clutch disk freely slidable on said blade portion, and having a wheel, and having a tubular shaft, and having a paint applicator holding device, said wheel and said tubular shaft providing a continuous bore through which said blade portions pass, and said clutch disk operatively arranged to impart rotation to said wheel, said tubular shaft and said paint applicator holding device as said clutch disk is rotated by said blade portion passing through said clutch disk opening, said improvement comprising:

- a blank clutch disk generated about an axis having an opening through which said blank clutch disk axis passes, and said blank clutch disk freely slidable on said blade portion, and said blank clutch disk located along said blade portion on the side of said clutch disk closer to said flange, and said blank clutch disk opening sized to allow passage of said blade portion but not said flange;

whereby said blank clutch disk prevents the unintentional removal of said drive rod from said drive shaft assembly by precluding passage of said flange beyond said clutch disk.

5,588,222

PROCESS FOR RECYCLING COMBUSTION GASES IN A DRYING SYSTEM

Stanley P. Thompson, Topeka, Kans., assignor to Beloit Technologies, Inc., Beloit, Wis.


Filed Mar. 15, 1995, Ser. No. 404,589

Int. Cl.⁶ F26B 7/00

U.S. Cl. 34—379

12 Claims

1. A process for drying material in a drying system having a first stage dryer and at least two second stage dryers, the first and second stage dryers each having a combustion chamber coupled therewith, the process comprising:
- supplying a quantity of heated gas to the first stage dryer from the combustion chamber coupled therewith;
 - exposing material to be dried to said quantity of heated gas in the first stage dryer;
 - separating dried material from said quantity of heated gas;
 - splitting said quantity of heated gas into a first stream of heated gas and a second stream of heated gas after dried material has been separated from said quantity of heated gas;
 - introducing said first stream into the combustion chamber coupled with the first stage dryer so that the gases generated in this combustion chamber and said first stream are combined to constitute said quantity of heated gas;
 - introducing at least a portion of said second stream into each combustion chamber coupled with a second stage dryer;



- supplying each second stage dryer with a current of heated gas from the combustion chamber coupled therewith, said portion of said second stream constituting a portion of each said current;
- exposing material to be dried to said current in a second stage dryer; and
- separating dried material from said current.

5,588,223

RESTRAINED PAPER DRYER


Hugh G. Marshall, Hudson, Canada, assignor to Asea Brown Boveri Inc., Quebec, Canada

Filed Jun. 14, 1994, Ser. No. 259,503

Int. Cl.⁶ F26B 5/04

U.S. Cl. 34—414

14 Claims



1. An improved method of drying a moving paper web in an elongated drying apparatus comprising the steps of:
- holding the web in a restrained position on an open weave fabric by means of air suction from 3 to 12 inches H₂O imposed progressively along the length of the drying apparatus from underneath the web and sufficient to prevent shrinkage of the web; and
 - applying a drying medium to said web in the form of high temperature, high velocity air or superheated steam, whereby shrinkage of said web is substantially inhibited, ring crush strength is increased and fibre requirements are reduced.

5,588,224

CHILL ROLL ASSEMBLY

John S. Gianforte, Southlake, and Anthony C. Cox, Hurst, both of Tex., assignors to EGS Americas, Inc.


Filed Jun. 7, 1995, Ser. No. 488,381

Int. Cl.⁶ F26B 3/00

U.S. Cl. 34—447

13 Claims

1. A chill roll assembly, comprising:
- a plurality of sets of chill rolls;



- a plurality of means for driving said plurality of chill roll sets, each of said means for driving connected to actuate a corresponding set of chill rolls; and
- means for controlling said plurality of means for driving said plurality of chill roll sets in a first mode to synchronously actuate said plurality of sets of chill rolls in processing a single web through said plurality of chill rolls sets or in a second mode to asynchronously actuate said plurality of chill roll sets in processing multiple webs, on a one web per set of chill rolls basis, through said plurality of chill roll sets.

5,588,225

METHOD OF DRYING AN INJECTION MOLDING TOOL

Achim Becker, Darmstadt, and Michael Zlotos, Biebesheim, both of Germany, assignors to Filterwerk Mann & Hummel GmbH, Ludwigsburg, Germany


Filed Jun. 30, 1995, Ser. No. 497,329

Claims priority, application Germany, Jun. 30, 1994, 44 22 674.8

Int. Cl.⁶ F26B 3/00

U.S. Cl. 34—474

13 Claims



1. A method of drying a surface of an injection molding tool comprising the steps of:
- feeding dry air from a drying device into a lower area of a chamber defined by a housing enclosing the tool;
 - removing moist air from an upper area of the chamber; and
 - returning said moist air to said drying device which removes moisture from the moist air.

5,588,226

UNIDIRECTIONAL AIR TRANSFER SYSTEM FOR SHOES

Décio L. Schenkel, Rua Gal. Emílio Lúcio Esteves, 1353-Taguara/RS, Brazil

Filed May 1, 1995, Ser. No. 431,721

Claims priority, application Brazil, Feb. 17, 1995, 9500679

Int. Cl.⁶ A43B 7/08

U.S. Cl. 36—3 B

8 Claims



1. A shoe comprising an outsole with openings formed therethrough; an assembly inner-sole with openings formed therethrough; and a unidirectional air transfer set disposed between said outsole and said inner-sole and including tissues separated by a breathable membrane permitting passage of humid air in one direction only, said unidirectional air transfer set being interposed between said openings in said inner-sole and said openings in said outsole to permit humid air to pass through said breathable membrane and tissues in one direction only from an interior of said shoe to an exterior of said shoe.

5,588,227

ATHLETIC SHOE HAVING AIR BLADDER PRESSURE INDICATING MEANS

Mark R. Goldston, Los Angeles, Calif.; Jon L. Bemis, Middleboro, Mass.; Daniel M. Wickemeyer, and David Potter, both of Venice, Calif., assignors to L.A. Gear, Inc., Santa Monica, Calif.


PCT No. PCT/US92/03593, § 371 Date Apr. 30, 1992, § 102(e) Date Apr. 30, 1992

PCT Filed Apr. 30, 1992, Ser. No. 849,433

Int. Cl.⁶ A43B 7/14; 13/20; 23/26

U.S. Cl. 36—93

16 Claims



1. An athletic shoe having a sole, an upper, and a tongue, wherein the athletic shoe comprises:
bladder means for altering the fit of the athletic shoe, said bladder means being inflatable and incorporated into the construction of the athletic shoe;
pump means for inflating said bladder means;
pressure sensing means for sensing the pressure within said bladder means, said pressure sensing means including an arcuately expanding bellows having a plurality of pleats formed therein; and
indicator means, responsive to movement of said bellows, for indicating the pressure sensed by said pressure sensing means.

5,588,228

SPORTS SHOE WITH A REINFORCING SHELL-FRAME

Giancarlo Foscaro, Treviso; Mirco Tesser, Montebelluna; Mirco Battistella, Spresiano; Mirco Bergamin, Castelfranco, and Gilberto Canil, Noale, all of Italy, assignors to Nordica S.p.A., Treviso, Italy


Filed Aug. 29, 1994, Ser. No. 297,277

Claims priority, application Italy, Sep. 10, 1993, TV93A0080; May 23, 1994, TV94A0057

Int. Cl.⁶ A43B 7/20; 5/04; 5/16

U.S. Cl. 36—118.2

47 Claims



17. A sports shoe having a heel region, a region lying above the heel region, a tip region, a foot instep region, a foot inner side region, and a foot outer side region, the sports shoe comprising:

- a sole having a resting surface;
 - a shell connected to the sole;
 - a shell rigid reinforcing frame; and
 - a shell soft portion connected to said shell rigid reinforcing frame for forming said shell, said shell soft portion being relatively less rigid than said shell rigid reinforcing frame;
- said reinforcing frame comprising bands of plastic material extending at least along a first inclined directrix and a second inclined directrix such that open regions are defined in said shell reinforcing frame, in which said first inclined directrix extends at least at one of the foot inner side region and the foot outer side region from the tip region towards the region lying above the heel region and such that said first inclined directrix is inclined with respect to the extension of said sole, and in which said second inclined directrix also extends at least at said one of the foot inner side region and the foot outer side region from the heel region towards the foot instep region and such that said second inclined directrix is inclined with respect to the extension of said sole;
- the bands of plastics material of said reinforcing frame which extend along said first directrix and said second directrix being mutually connected at an intersection point of said first and second directrices; and
- said open regions of said shell reinforcing frame comprising at least

5,588,229

SKI BOOT

Gilles Marmonier, Saint Etienne de Crosse, France, assignor to Lange International S.A., Fribourg, Switzerland

Continuation of Ser. No. 205,581, Mar. 3, 1994, abandoned.


This application Feb. 26, 1996, Ser. No. 605,453

Claims priority, application Switzerland, Apr. 2, 1993, 01026/93

Int. Cl.⁶ A43B 5/04

U.S. Cl. 36—118.9

5 Claims



1. A ski boot having a front and a back end for a skier's foot, heel and leg, comprising: a rear having a shell (1) intended to surround the foot and the heel, a shaft (3; 3') having a closed position and being articulated on the shell and being comprised of two parts, namely a first part (5; 15; 25) forming a stirrup (6; 16; 19) having an upper edge and extending around and above the heel and a second part having a rear end (7, 18) surrounding at least the rear of the leg, these two parts being able to be fixed to each other with respect to rotation by connecting means, at least in the closed position of the shaft, wherein the said connecting means consist of a rocker (9; 14; 17; 22) having an axis and end and being articulated on the rear of the second part of the shaft so as to be able to bear on and engage the stirrup, said rocker including at least one beak movable to a

- (1) first position wherein said beak bears and engages the stirrup and maintains the stirrup integral in backwards rotation with said second part, whereby rotation of the second part relative to the first part is prevented to define the closed position of the shaft and
- (2) a second position wherein said beak is disengaged from the stirrup and said second part can rotate backwards independently from the stirrup, whereby the second part is adapted to tilt backwards to formulate putting on and removal of the boot.

5,588,230

APPARATUS FOR EXCAVATING SOIL USING A PLURALITY OF INDEPENDENTLY PIVOTABLE BRUSHES

William R. Bath, and Charles R. Yemington, both of Houston, Tex., assignors to Sonsub, Inc., Houston, Tex.


Filed May 31, 1995, Ser. No. 455,848

Int. Cl.⁶ E02F 3/24

U.S. Cl. 37—190

14 Claims

1. An apparatus for removing soil comprising:
a frame;



a collection box supported within said frame;
means for sweeping soil pivotally attached to said frame, said sweeping means comprising a plurality of brushes rotatably mounted and each said brush mounted for independent vertical positioning; and
means for conveying the soil from said sweeping means into said collection box.

5,588,231

SELF CONTAINED SNOW REMOVAL APPARATUS AND METHOD OF USE THEREFOR


Kostas Mavrianos, P.O. Box 954, Nome, Ak. 99762

Filed Jul. 10, 1995, Ser. No. 500,182

Int. Cl.⁶ E01H 5/10

U.S. Cl. 37—227

11 Claims



1. A snow removal system comprising:

- a) a means for collecting snow from a ground surface;
- b) a hopper, having a front wall, a rear wall, two oppositely disposed sides and a floor;
- c) at least one boiler in thermal communication with said means for melting snow;
- d) a means for transferring said snow from the means for collecting snow, to said hopper;
- e) a means for melting snow, fixedly placed within said hopper, said means for melting snow including: i) a plurality of elongated pyramids being hydraulically interconnected and also being connected to said boiler to allow a flow of heated water therethrough;
- f) a means for collecting melted snow, fixedly placed within said hopper;
- g) a container for receiving and storing the melted snow;

- h) a heating pipe, fixedly mounted to the rear wall of said hopper, above said screen to melt snow accumulating on said rear wall of said hopper; and
i) a means for pumping said melted snow from said hopper to said container for receiving and storing said melted snow.

5,588,232

VEHICLE LINKAGE


Peter J. Renwick, Hexham, England, assignor to Pearson Engineering Limited, Newcastle-on-Tyne, England
Filed Sep. 1, 1994, Ser. No. 299,576

Claims priority, application United Kingdom, Sep. 4, 1993, 9318392

Int. Cl.⁶ E01H 5/04

U.S. Cl. 37—232

19 Claims



1. A linkage for coupling a vehicle to a ground-engaging implement to allow said ground-engaging implement to be lifted and tilted, said linkage comprising a first link and a second link, each said link having a first end and a second end and a longitudinal axis passing through the first and second ends of each said link, said first end of said first link being pivotally connected to the vehicle to allow pivotal movement between the vehicle and the first end of said first link both around said longitudinal axis of said first link and around a line transverse to said longitudinal axis of said first link, and said second end of said first link being pivotally connected to the ground-engaging implement to allow pivotal movement between the ground-engaging implement and the second end of said first link only around a line transverse to said longitudinal axis of said first link; said first end of said second link being pivotally connected to the vehicle to allow pivotal movement between the vehicle and the first end of said second link only around a line transverse to said longitudinal axis of said second link and said second end of said second link being pivotally connected to the ground-engaging implement to allow pivotal movement between the ground-engaging implement and the second end of said second link around said longitudinal axis of said second link and also around a line transverse to said longitudinal axis of said second link.

5,588,233

PAPER PRODUCT AND METHOD OF MAKING


Carolyn K. Volkert, Evanston, and Andrew M. Volkert, Northfield, both of Ill., assignors to Volkert, Inc., Northfield, Ill.
Filed Aug. 5, 1994, Ser. No. 286,674

Int. Cl.⁶ G09F 3/00

U.S. Cl. 40—124.1

20 Claims

1. A blank for fabricating an attention-attracting piece, said blank comprising sheet material designed to be formed into at least first and second panels connected to each other along a main hinge line.



die-cut means in said first panel forming a stand-out structure having a main body portion, at least one line of weakness in said blank along which said main body portion is hinged to the remainder of said blank, said die-cut means also forming link means in said sheet material as a part of said stand-out structure, said link means being hinged to said main body portion of said stand-out structure, and bonding means for interconnecting said stand-out structure in said first panel to a region of said second panel of said sheet material which lies across said main hinge line from said first panel, so that interconnection between said stand-out structure and said second panel occurs upon manipulation of said sheet material to achieve superimposition of one said panel upon said other panel, thereby completing said fabricated piece whereby opening of said fabricated piece thereafter causes said stand-out structure to move prominently away from the remainder of said first panel in an attention-attracting mode.

5,588,234

FRAUD-RESISTANT ELECTRONIC IDENTIFICATION DEVICE


Hendrik J. de Jong, Groenlo, and Ebele M. Postma, Nijmegen, both of Netherlands, assignors to N.V. Nederlandsche Apparatenfabriek Nedap, De Groenlo, Netherlands
Filed Sep. 21, 1993, Ser. No. 123,967

Claims priority, application Netherlands, Sep. 21, 1992, 9201626; Feb. 16, 1993, 9300289

Int. Cl.⁶ G09F 3/00

U.S. Cl. 40—301

32 Claims



1. A device for identifying animals or articles, said device comprising:

an identification member including an identification device located internally of said identification member with an electronic identification circuit storing a code and enabling automatic remote detection of the code of the identification device.

said identification member being made of hard, non-resilient material and an external shape of said identification member being frustoconical, starting from a base which in operation abuts against the article or the animal, narrows substantially taperingly and smoothly to an end which in operation is located remote from the article or animal, so that said identification member cannot be gripped by another animal between its teeth or be caught on obstacles or other objects,

an attachment member for attaching said identification member to the article or animal, said attachment member being resilient and deformable upon contact with said identification member,

a bore of said identification member extending between said base and said end and transversely to the base, and retaining means located in said bore for receiving a pin-shaped element of said attachment member.

5,588,235

LIGHT PROCESSING APPARATUS FOR CREATING VISUAL EFFECTS


Victor Y. Juchymenko, Toronto; J. Richard Howard, Oakville; Andrew J. Laczynski, and James S. Angus, both of Toronto, all of Canada, assignors to Roberts Systems, Inc., Charlotte, N.C.

Continuation-in-part of Ser. No. 79,585, Jun. 22, 1993, Pat. No. 5,508,892. This application May 31, 1994, Ser. No. 252,007

Int. Cl.⁶ G09F 13/00

U.S. Cl. 40—547

17 Claims



1. Light processing apparatus for creating on a display surface special effects which simulate movement, using light from a light source, comprising:

(a) a multiplicity of flexible fibre optic light guides having input ends for receiving the light from the light source and output ends, the light guides being grouped into groups, each group creating a particular special effect, wherein the input ends of each group of light guides are placed in distinct receptor zones which define a pre-selected geometry and the output ends of each group of light guides are positioned in a pre-selected pattern; and

(b) a moveable color changing means for periodically changing the color of the light from the light source, comprising a plurality of discrete colored filter zones which transmit light of various colors, wherein each of the filter zones defines a preselected geometry which is substantially the same width and geometric pattern as said receptor zone wherein the filter zones successively register with and sweep across the correlated receptor zones, thereby periodically changing the color of the light which is transmitted to the input ends of various groups of light guides.

5,588,236

VISUAL PANEL


Teruo Suzuki, Urayasu, Japan, assignor to SCS Promotion Company Limited, Chiba, Japan

Continuation-in-part of Ser. No. 039,070, Apr. 8, 1993, Pat. No. 5,398,436. This application Dec. 16, 1994, Ser. No. 357,326

Claims priority, application Japan, Oct. 25, 1991, 3-306627 Int. Cl.⁶ G09F 13/00; 17/00

U.S. Cl. 40—558

2 Claims



1. A visual panel comprising:

a frame;
a flexible sheet having swollen portions at opposing edge portions thereof, respectively;
sheet stretching means for slidably accommodating said swollen portions at said opposing edge portions of said sheet and for stretching said sheet over said frame; and
tension adjusting means for adjusting a tension to be applied to said sheet;

said stretching means comprising a first stretching device for accommodating one of said swollen portion portions at one edge portion of said sheet and a second stretching device for accommodating another of said swollen portions at the other edge portion of said sheet;

said first stretching device and said second stretching device each being provided with a hole for accommodating said swollen portions at said edge portions, respectively, of said sheet and a slit through which said edge portion of said sheet continuing to said swollen portion is extended,

said second stretching device being disposed movably with respect to said frame,

said tension adjusting means comprising a rotatable arm rotatably mounted on said frame by means of a pivotal pin, a screw having one end rotatably and pivotally connected to said rotatable arm, and a nut member threadably fitted to a screw portion of said screw and rotatably mounted on said frame,

said tension adjusting means being provided between said second stretching device and said frame.

5,588,237

SYSTEM FOR MOUNTING BILLBOARDS

Jeffrey A. Chase, 1388 Keenan Way, San Jose, Calif. 95125, and Joseph L. Chase, 1159 Chippewah Dr., Chattanooga, Tenn. 37412


Filed Jan. 18, 1994, Ser. No. 183,035

Int. Cl.⁶ G09F 21/04

U.S. Cl. 40—597

4 Claims

1. An apparatus for temporarily displaying a sign from an exterior surface of a vehicle, the apparatus comprising:



a frame configured for holding a sign, the frame including an upper portion and a generally rectangular portion configured for housing the sign;
a hook mounted to the upper portion of the frame;
a plurality of vacuum cups, each having an open end for positioning against the surface;
hook receiving means mounted to at least one of the cups for detachably engaging with the hook;
vacuum means for removing air from the vacuum cups when the open ends are positioned against the exterior surface of the vehicle to create a substantially airtight seal between the cups and the exterior surface of the vehicle; and
stabilizing means for stabilizing a lower portion of the frame against the exterior surface of the vehicle;
and wherein the frame further comprises a plurality of upper support members extending from an upper portion of the rectangular portion, the upper support members detachably connected to the vacuum cups and adjustable to accommodate vehicles of varying sizes.


5,588,238

SIGN COMPRISED OF A CARRIER FRAME AND MANUALLY ARRANGEABLE MODULAR INFORMATION GRIDS AND PICTORIALS

Joseph E. Visocky, Racine, and Everett Evans, Hales Corners, Wis., assignors to Everbrite, Inc., Greenfield, Wis.
Filed Jun. 14, 1995, Ser. No. 490,470
Int. Cl.⁶ G09F 7/02

U.S. Cl. 40—618

8 Claims



1. A sign system comprising:

a carrier frame including longitudinally extending side rail members that have nominally upper and lower end portions and are laterally spaced from and parallel to each other, upper and lower cross rail members extending laterally between the side rail members and each cross rail member having opposite ends, the opposite ends of the upper cross rail member joined with the upper end portions, respectively, of the side rail members and the opposite ends of the lower cross rail member joined with the lower end portions, respectively, of the side rail members to thereby define a rigid carrier frame, said side rail members having guide tracks substantially coextensive with the length of the side rail members,

at least one grid unit comprised of at least one grid module including upper and lower laterally extending parallel longitudinally spaced apart cross bars having opposite corresponding ends and laterally spaced apart longitudinally extending tie bars at each end rigidly connecting corresponding ends of the cross bars to thereby define a window opening, and said ends of the cross bars for each grid module are configured for engaging with said guide tracks at said upper ends of the side rail members to provide for sliding said grid unit in the carrier frame for being retained between the side rail members and,

upper and lower pictorial assembly retainer bars each having opposite end portions configured for sliding on said tracks of said side rail members into the carrier frame for being arranged in longitudinal spaced apart relationship, the upper retainer bar having a downwardly presented slot and the lower retainer bar having an upwardly presented slot, and, a pictorial assembly comprised of front and rear light transmissive panels and a transparency panel disposed between said panels, said panels having corresponding upper edges of registering in the slot of the upper retainer bar and having corresponding lower edges for registering in the slot of the lower retainer bar for holding the pictorial assembly in the carrier frame.

5,588,239


EXPANDED CONTENT LABEL ADAPTED FOR APPLICATION TO CURVED SURFACES

Robert J. Anderson, Sioux Falls, S. Dak., assignor to CCL Label, Inc., Sioux Falls, S. Dak.

Filed Feb. 13, 1995, Ser. No. 387,067
Int. Cl.⁶ G09F 3/02

U.S. Cl. 40—630

11 Claims



1. An expanded content label comprising:
a base label having first and second unconnected base label segments, each of said segments having upper and lower surfaces, said first segment having longitudinally opposed inner and outer side edges, said inner side edge facing said second segment;
adhesive on said lower surface of each of said segments;
a booklet including longitudinally opposed bound and free edges, said booklet including a bottom sheet secured to said upper surface of said first base label segment and not to said second base label segment, said booklet oriented with said

bound edge toward said outer side edge and said free edge toward said inner side edge; and
an overlamine adhered both to said booklet and to said second base label segment, said overlamine including a perforation means for providing access to said booklet, said perforation means located proximate said free edge of said booklet.

5,588,240

INTERLOCKING PICTURE FRAME


Kent Zilliox, 361 Halsey Ave., San Jose, Calif. 95128

Filed Mar. 18, 1994, Ser. No. 215,094

Int. Cl.⁶ G09F 1/12

U.S. Cl. 40—729

15 Claims



1. A picture frame, comprising:

a first frame body, said first frame body having a perimeter, said first frame body having at least one connector, said connector being selected from the group consisting of a male connector and a female connector, said male connector being a projection from said perimeter of said first frame body, said female connector being an indent in said perimeter of said first frame body, said first frame body having a front surface, and a display means for holding a display item for viewing, said display means comprises a first recess in said front surface for receiving said display item,

and wherein said first recess comprises a back surface and a second recess within said back surface, said second recess having a back wall, said second recess having at least one hole through said back wall.

2. The picture frame of claim 1 further comprising a transparent cover means for covering said display item received in said first recess.

5,588,241

HIGH CAPACITY CONVERSION MAGAZINE

William W. Hurley, Temple Main Post Office, 401 N. Main, Temple, Tex. 76501


Filed Feb. 26, 1990, Ser. No. 484,239

Int. Cl.⁶ F41A 9/65

U.S. Cl. 42—50

3 Claims

1. A readily detachable, externally loadable, box magazine adapted to replace the original-equipment box magazine of a rifle, the original-equipment magazine having a "clam-shell" configuration utilizing a pair of magazine halves connected at a forward pivot site, the lower half being pivotable to allow the interior portions thereof to be accessed, the rifle having a stock with a



vertical through-hole adapted to be covered at its top by a barrel and receiver, covered at its rear underside by a trigger mechanism, and covered at its forward underside by said original-equipment magazine, the original equipment magazine being retained within the stock at its forward end at a fixed attachment site and at its rearward end by a spring-biased retaining latch on the trigger mechanism such that the original-equipment magazine may only be removed from the rifle after prior removal of the lower half of the original-equipment magazine to retain the original-equipment magazine in a closed configuration during use, the readily detachable magazine comprising:

a hollow body formed from front, side and back walls and adapted to house a plurality of cartridges, said hollow body having a top opening allowing cartridges to pass therethrough; a spring and follower combination disposed within said hollow body to facilitate the extraction of cartridges from within said hollow body during use of the rifle;

an elongated extension section attached at one end to the front wall of said hollow body proximate the top thereof and projecting normally to and forward from said front wall to terminate in a free end having a forward latch projection disposed thereon for readily detachable engagement with the fixed attachment site of the rifle, said extension section substantially covering the underside portion of the through-hole forward of said hollow body when the readily detachable magazine is attached to the rifle; and

a rear latch projection attached to the rear wall of said hollow body projecting normally to and rearward therefrom, said rear latch projection being configured for readily detachable engagement with the spring-biased retaining latch of the rifle, whereby the readily detachable magazine may be secured to the rifle by engaging the forward latch projection with the fixed attachment site and the rearward latch projection with the spring-biased retaining latch of the rifle, and the readily detachable magazine may be removed from the rifle by disengaging the forward latch projection from the fixed attachment site and the spring-biased retaining latch of the rifle from the rear latch projection of the readily detachable magazine.

5,588,242

GUN BARREL CLEANING ROD AND METHOD

Jeffrey T. Hughes, Winston-Salem, N.C., assignor to Hughes Products Company, Inc., Thomasville, N.C.


Continuation of Ser. No. 391,765, Feb. 21, 1995, abandoned.
This application Apr. 1, 1996, Ser. No. 625,095

Int. Cl.⁶ F41A 29/00

U.S. Cl. 42—95

20 Claims

1. A gun barrel cleaning rod comprising: a coiled, uniformly flexible, wholly polymeric shaft, and a cleaning implement, said cleaning implement affixed to said polymeric shaft, said polymeric



shaft having rigidity sufficient to overcome compression forces encountered while said cleaning implement is urged tightly through said gun barrel.


5,588,243

FISHING LINE DEVICE

Gregory Caldwell, 3701 Buttonwood La., Carmel, N.Y. 10512
Filed Apr. 6, 1995, Ser. No. 417,678

Int. Cl.⁶ A01K 97/00

U.S. Cl. 43—4



1. Apparatus for imparting an irregular jerking motion to a fishing line from a rowboat by releasably securing said fishing line to a downrigger clamp means located at the paddle portion end of an oar of said boat, said oar having a handle at one end and a paddle portion at the second end said apparatus comprising an attachment to said oar releasably secured to said paddle portion of said oar, a mounting bracket secured to said oar adjacent to said handle of said oar, a pulley arm holding a pulley line, said pulley arm extending from said attachment, said mounting bracket and said downrigger clamp means secured to said pulley line and crimp means on either side of said downrigger clamp means to secure said downrigger clamp means to said pulley line.

5,588,244

FISHING ROD WITH A PRE-INSERTED FISHING LINE GUIDE MEMBER


Masaru Akiba, and Tomoyoshi Tsurufuji, both of Saitama, Japan, assignors to Daiwa Seiko, Inc., Tokyo, Japan
Filed Jul. 22, 1994, Ser. No. 277,315

Claims priority, application Japan, Jul. 30, 1993, 5-045854 U
Int. Cl.⁶ A01K 87/04

U.S. Cl. 43—24

13 Claims

1. A fishing line guide member for mounting on an end of a fishing rod pipe held generally horizontal during fishing, a fishline extends through the fishing line guide member into the fishing rod



pipe and is generally pulled in a downward vertical direction during fishing, said line guide member comprising:
a forward portion engaging and mounted on the end of the fishing rod pipe;
a rearward portion connected to said forward portion, said rearward portion is in contact with and guides the fishing line into the rod pipe, said rearward portion being enlarged in diameter with respect to said forward portion, an end of said rearward portion opposite said forward portion defining a passage for the fishing line and including a periphery, said periphery being offset asymmetrically with respect to an axis passing longitudinally through said line guide member and the rod pipe.

5,588,245


FISHING LURE PROTECTIVE CONTAINER

Joseph E. Vance, 1113 Como Pl., St. Paul, Minn. 55103
Filed May 31, 1995, Ser. No. 454,829

Int. Cl.⁶ A01K 97/06

U.S. Cl. 43—25.2

20 Claims



7. The combination of:

a fishing rod comprising an elongate rod shaft having guide rings mounted thereon with a fishing line threaded through said guide rings and terminating in a free end,
a fishing lure attached to said free end of said fishing line, and
a container comprising a relatively stiff longitudinal perimeter wall structure and spaced end walls transverse to said perimeter wall structure, said perimeter wall structure of said container being split longitudinally into two container parts hinged along a longitudinal axis to permit pivot opening and closure of the parts, said container being removably mounted in a longitudinal manner on said fishing rod by pivot closure of said container parts about said fishing rod shaft so as to form a protective fishing lure chamber within which said lure is held, said container being mountable on said fishing rod shaft with said rod shaft passing through said container so as to permit mounting of said container at various locations along said rod shaft, at least one of said transverse end walls of the container being formed of a deformable material such that said deformable end wall transversely pinches and deforms against said rod shaft in a frictionally engaging manner, said frictional engagement being such as to resist longitudinal slippage of said container along said rod shaft.

5,588,246

INTERCHANGEABLE EYES FOR FISHING LURES


Curtis J. Hill, 920-28th Ave. S., Moorhead, Minn. 56560

Filed Apr. 27, 1995, Ser. No. 429,664

Int. Cl.⁶ A01K 85/00

U.S. Cl. 43—42.06

3 Claims



1. Interchangeable eyes for a fishing lure comprising:
eye fastening members secured in spaced relationship on a head of said fishing lure;
simulated eyes detachably attached to said eye fastening members, each of said simulated eyes having a simulated pupil protruding therefrom and a rim extending about the perimeter thereof, said pupil and rim defining an annular portion therebetween; and
spongy material removably retentive to each of said eye, for retaining and releasing fish-alluring scents into water to attract fish to said fishing lure, said spongy material being retentively received in said annular portion.

E) a transverse passage extending through said body, one end of said passage having a greater diameter than the other end, said larger diameter end of said passage constituting a rattle chamber,
F) a cap closure covering the rattle chamber,
G) at least one noise-making rattle element loosely held within the rattle chamber,
H) a fiber weed guard secured to and extending radially outward from said body, spaced rearward of the barb of said fish hook, said fiber weed guard being composed of a bundle of stiff semi-rigid filaments adhesively sealed at one end within the smaller diameter end of the transverse passage, and
I) an eyelet secured to the rearward end of said body for attaching the jig to a fish line.

5,588,248

FISHING WEIGHT


Thomas W. Cornell, Jr., and John L. Reinbold, both of c/o C. R. Steel 377 41 St., Lindenhurst, N.Y. 11757

Continuation of Ser. No. 84,614, Jul. 1, 1993, abandoned. This application Apr. 11, 1995, Ser. No. 420,583

Int. Cl.⁶ A01K 97/02

U.S. Cl. 43—44.9

3 Claims



1. A solid, non-hollow fishing weight, said fishing weight having a body portion, said body portion having a solid interior and an outer surface, the body portion having a central axis, the solid interior extending outwardly from said central axis, the exterior of said fishing weight being substantially symmetrical and being substantially devoid of any interruptions, the solid interior of said body portion being formed from a zinc alloy and having a protective coating covering the entire outer surface, said coating being non-corrosive when exposed to water, said protective coating being a powder coating having a thickness of between approximately 1.5 and 1.7 mm which has been electrostatically applied to the outer surface.

5,588,247

RATTLE JIG


John E. Wicht, 17515 Territorial Rd., Osseo, Minn. 55369

Filed Aug. 30, 1993, Ser. No. 113,185

Int. Cl.⁶ A01K 91/00

U.S. Cl. 43—42.31

9 Claims



1. A rattle jig for use in bass fishing which comprises:
A) a solid brass body of generally circular cross-section,
B) a forwardly extending integral body extension of lesser diameter,
C) a fish hook secured to the forwardmost end of said body extension, the shank of said fish hook being generally in alignment with the longitudinal axis of the body,
D) at least one annular channel in the surface of the body extension,

5,588,249

HUMANE RODENT TRAP

John Flinner, 104 Sundance Pass, Lafayette, La. 70508


Filed May 10, 1995, Ser. No. 438,392

Int. Cl.⁶ A01M 23/20

U.S. Cl. 43—61

15 Claims

1. A humane rodent trap, comprising:
(a) a outer housing comprised of a front wall, a rear wall, 24, 26 a pair of side walls, a bottom, and a top;
(b) a partition having an upper and a lower surface, horizontally disposed in said outer housing, whereby said partition internally divides said rodent trap into an upper compartment and a lower compartment;
(c) means for opening said top to an open-position and closing said top to a closed position;
(d) an inlet opening in a lower section of said front wall, whereby a rodent may enter said lower compartment of said rodent trap by passing through said inlet opening;



- (e) a trap door which is vertically slidable between an upper and a lower position wherein said inlet opening is closed when said trap door is in said lower position and said inlet opening is open when said door is in said upper position;
- (f) a tensioning means for urging said trap door towards said lower position;
- (g) a mechanical intensifier having a stored energy device, a kinetic member, a trip mechanism, a release member, and a base, disposed on the upper surface of said partition;
- (h) a release means for releasably engaging said trap door in said upper position and for releasing said trap door to move under the influence of said tensioning means when said trip mechanism is operated;
- (i) a upper linkage connecting said release means to said kinetic member;
- (j) a trigger mechanism pivotally disposed in said lower compartment;
- (k) a trigger linkage connecting said trip mechanism to a pivotably movable portion of said trigger mechanism.


5,588,250

ADHESIVE INSECT TRAPPING HOUSING
Hiromi Chiba, and Kenji Furumori, both of Osaka, Japan,
assignors to Nitto Denko Corporation, and Oct Co. Ltd.,
both of Osaka, Japan

Filed Dec. 20, 1994, Ser. No. 360,003
Claims priority, application Japan, Dec. 20, 1993, 5-319448-
Int. Cl.⁶ A01M 1/14

U.S. Cl. 43-114

13 Claims



1. An adhesive insect trapping housing, for trapping flying insects, utilizing an adhesive sheet disposed within said housing, comprising:

- a hollow cover body defining a substantially rectangular opening extending in a longitudinal direction thereof, said cover body having at least three side walls, said side walls including a top

side wall, and left and right side walls, a substantially middle portion of said top side wall being curved inwardly as compared to opposite longitudinal end portions of said top side wall, said inwardly curved middle portion extending from said left side wall to said right side wall;

an odorant member, disposed on the interior of said cover body, for attracting insects; and

a tray, disposed facing said top side of said cover body, onto which the adhesive sheet is mounted,

wherein a first distance from said tray to said inwardly curved middle portion of said top side wall is less than a second distance from said tray to said end portions of said top side wall such that said insects are directed toward said adhesive sheet.

5,588,251

DEVICE FOR THE PREVENTION OF COLLISIONS OF BIRDS WITH TRANSPARENT BARRIERS


Sam W. Young, 1203 White Rd., Opelika, Ala. 36801

Filed Feb. 10, 1995, Ser. No. 386,446

Int. Cl.⁶ H01M 29/00

U.S. Cl. 43-119

10 Claims



5. A device for deterring birds from colliding with a transparent window barrier, said device comprising:
- a means for deterring birds from a transparent window barrier, said means for deterring birds comprising a substrate bearing the image of a spider stabilimentum and a center portion of a spider web, and said substrate having adhesive means on one surface thereof, wherein said substrate is adhesively attached to said transparent window barrier.

5,588,252

MOLE GASSING DEVICE

Jerry L. Jones, 14070 290th Ave., Zimmerman, Minn. 55398

Filed Jan. 29, 1996, Ser. No. 592,917

Int. Cl.⁶ A01M 13/00

U.S. Cl. 43-124

4 Claims

4. A mole gassing device utilizing gas exhaust fumes produced by a gasoline engine, comprising
- a gas fume conducting hose,
 - a terminal portion of said hose being fed through a sleeve,
 - an internal sleeve within said sleeve,
 - an annular flange as an extension of said internal sleeve supported upon said sleeve,
 - said internal sleeve frictionally receiving therethrough said terminal portion of said hose, positioning the extension therethrough of said sleeve,
 - means locking in position said hose within said sleeve,
 - a plate member underlying said sleeve being integral therewith, said plate member having a plurality of depending ground engaging positioning rods,
 - a ground engaging cylindrical seal member depending from said plate member centrally thereof, and

5,588,254

PLANT CULTIVATION METHOD

Takashi Adachi, Takafumi Ishii, and Hidemasa Hidaka, all of Kanagawa, Japan, assignors to Meiji Seika Kaisha, Ltd., Tokyo, Japan

Continuation of Ser. No. 109,374, Oct. 19, 1987, abandoned.

This application Aug. 22, 1990, Ser. No. 571,003


Claims priority, application Japan, Oct. 17, 1986, 61-245400; Mar. 3, 1987, 62-48385

Int. Cl.⁶ A01H 1/00; A01N 63/00; 65/00

U.S. Cl. 47-57.6

6 Claims

1. A method of accelerating growth of a plant which comprises applying to the plant, the seeds of the plant or the locus of the plant a plant growth accelerating amount of a plant growth accelerating oligosaccharide, wherein the plant growth accelerating oligosaccharide is alginic acid oligosaccharide, inulooligosaccharide, fucoidan oligosaccharide, gum arabic oligosaccharide or polyethylene glycol alginic acid oligosaccharide, wherein the oligosaccharide comprises 2 to 20 monosaccharides polymerized.



- a terminal portion of said hose extending through said plate member centrally of said seal member into a mole passage.

5,588,255

CAPILLARY WICK HYDROPONIC PROCESS


Christopher S. Johnson, 2679 B Walnut St., Los Alamos, N.M. 87544

Filed Jun. 14, 1995, Ser. No. 490,532

Int. Cl.⁶ A01G 31/02

U.S. Cl. 47-58

2 Claims



5,588,253

METHOD AND APPARATUS FOR DISPLAYING FLORAL ARRANGEMENTS


James W. Boodley, Kent; James P. Noe, Seville, and Daniel Hann, Akron, all of Ohio, assignors to Smithers-Oasis Company, Cuyahoga Falls, Ohio

Filed May 29, 1992, Ser. No. 891,393

Int. Cl.⁶ A01G 5/00; A47G 7/00

U.S. Cl. 47-41.12

13 Claims



1. A floral display support assembly comprising:
- backing means;
 - floral foam bonded to said backing means to define a pre-shaped display configuration having a longitudinal axis;
 - said floral foam being an open-celled thermoset capable of absorbing moisture;
 - moisture barrier means oriented transversely of said longitudinal axis and separating said floral foam into adjacent segments;
 - said longitudinally adjacent segments being separated along said longitudinal axis by said moisture barrier means to prevent the formation of a bridging meniscus between successive, longitudinally disposed segments;
 - said segments having a dimension along said longitudinal axis that is no greater than will assure moisture retention within each segment by minimizing hydraulic head pressure and capillarity.

1. A green plant or microbial culture method involving the steps of:

- providing a biological culture or support media which has a growing zone and a saturation zone, and
- providing a watering means which will introduce water into said biological culture or support media and cause fluid to flow through said biological culture or support media towards said saturation zone, and
- placing a capillary wick means in contact with said saturation zone in order to adsorb liquid solutions or suspensions which may contain metabolic products thereon while simultaneously or subsequently
- applying an accelerating force such as gravity, liquid pump means, or centripetal force to said liquid for the purpose of recovering liquid water or to remove suspended or dissolved materials from the culture environment to a desired point of removal from the capillary wick means
- where return flow of said liquid to said media by said wick means is substantially prevented, and where said plant or culture is supplied with nutrients from any supply means.


5,588,256 HYDROPONIC CULTIVATION APPARATUS AND METHOD

Charles O. Sherfield, 815 W. Marshall, Phoenix, Ariz. 85013
Division of Ser. No. 87,506, Jul. 2, 1993, Pat. No. 5,381,626,
which is a continuation-in-part of Ser. No. 625,078, Dec. 10,
1990, Pat. No. 5,224,291. This application Apr. 20, 1995, Ser.
No. 426,625

Int. Cl.⁶ A01G 31/00

U.S. Cl. 47—62

21 Claims



1. An apparatus for hydroponically cultivating a plant having roots and a stem and for retarding evaporation while protecting said plant roots, said apparatus comprising:
 - a container adapted to retain a nutrient solution, said container having an opening therein;
 - a seal coupled to a section of said container which immediately surrounds said opening, said seal having a hole therein, said hole being dimensioned for physical contact between said seal and said plant stem;
 - a porous support medium into which said plant roots grow, located within said container proximate said opening; and
 - a hollow tube being sufficiently long to contact said support medium while projecting outward from said container through said seal hole, said hollow tube being for retaining a plant seed in position relative to said seal hole and for guiding growth of said plant through said seal hole.

5,588,257 GARAGE DOOR OPERATOR


Dean C. Duhamel, Roseville; Richard P. Spens, Howell; Dana Lowell, Clarkston, all of Mich.; Chin-Feng Chan, Nan Kang, and Ming-Iwa Shou, Hsin Tien, both of Taiwan, assignors to The Stanley Works, New Britain, Conn.

Filed Aug. 24, 1994, Ser. No. 295,272

Int. Cl.⁶ E05F 11/00

U.S. Cl. 49—199

17 Claims



1. An apparatus for operating a garage door including:
 - (a) a motor;
 - (b) a drive assembly coupled to said motor, said drive assembly comprising:
 - (i) a drive screw extending longitudinally and having a first end coupled to said motor for rotation, said drive screw including at least two drive segments;
 - (ii) coupling means for coupling ends of said segments; and
 - (iii) means for maintaining compression on said segments in a longitudinal direction toward said coupling means to maintain said segment ends in engagement with said coupling means; and
 - (c) means coupled to said door, responsive to rotation of said drive screw and moving therealong in said longitudinal direction for moving said door in response thereto.

5,588,258 POWER OPERATOR FOR PIVOTABLE VEHICLE CLOSURE ELEMENT


Kevin Wright, Southfield; Lloyd W. Rogers, Jr., Shelby; Robert W. Baughman, Mt. Clemens, and David J. Chapman, Sterling Heights, all of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Mar. 1, 1995, Ser. No. 396,992

Int. Cl.⁶ E05F 11/24

U.S. Cl. 49—340

8 Claims



1. An operator in combination with a closure element of a vehicle comprising:
 - a power drive unit;
 - an extensible strut including a first and second link slidably engaging each other and connectable between the closure element and the vehicle;
 - a first drive cable connected between the power drive unit and the strut;
 - a sprocket rotatably fixed to the first link;
 - a connector fixed to the second link; and
 - a chain extending through the strut from the connector around the sprocket and connected to the first drive cable.

5,588,259 SUPPORTING ARM WITH LOCKING MEANS FOR A HINGED PANEL

Chris Kolefas, 1017 Edgewood La., Fort Lee, N.J. 07024

Filed Jul. 15, 1994, Ser. No. 276,098

Int. Cl.⁶ E05B 65/06

U.S. Cl. 49—394

18 Claims

1. A device used to support a hinged panel in an open position and to lock the hinged panel in a closed position, the hinged panel being hinged to a fixed structure, the device comprising:
 - a pivot point secured to the fixed structure;
 - a pin secured to the panel; and
 - a drive screw extending longitudinally and having a first end coupled to said motor for rotation, said drive screw including at least two drive segments;
 - (ii) coupling means for coupling ends of said segments; and
 - (iii) means for maintaining compression on said segments in a longitudinal direction toward said coupling means to maintain said segment ends in engagement with said coupling means; and
 - (c) means coupled to said door, responsive to rotation of said drive screw and moving therealong in said longitudinal direction for moving said door in response thereto.



1. A gutter assembly adapted to be attached to a fascia board located below a building roof, said gutter assembly comprising: a half-cylinder including an upper flange and a lower flange, each of said flanges extending radially outward from said half-cylinder and generally defining a single plane, said flanges adapted to be attached to said fascia board; a gutter defining a fluid receiving trough having a modified channel shape and being adapted to be mounted immediately below and adjacent to said half-cylinder on said fascia board such that fluid flowing off said building roof is directed over and around the half-cylinder and into said gutter.

5,588,260 CONSTRUCTION OF A VEHICLE DOOR PROVIDED WITH A WIRING HARNESS AND A WATERPROOF GROMMET USED IN THE CONSTRUCTION

Shigemichi Suzuki, and Sadahisa Endo, both of Omiya, Japan, assignors to Kansei Corporation, Omiya, Japan


Filed May 30, 1995, Ser. No. 452,525

Claims priority, application Japan, May 30, 1994, 6-116352; Oct. 31, 1994, 6-266464; Mar. 17, 1995, 7-59313

Int. Cl.⁶ B60J 5/04

U.S. Cl. 49—502

23 Claims



1. In a construction of a vehicle door provided with a wiring harness, comprising a door trim mounted on an interior surface of a door panel of a door with which an entry of a vehicle is closed; and a wiring harness inserted between said door trim and the interior surface of said door panel, bent along a side face of said door panel to which a door hinge is attached, and extended to a part of a vehicle body enclosing the door from the side face; said construction further comprising:
 - a waterproof grommet through which said harness passes, mounted on the side face;
 - said waterproof grommet being made of an elastic substance and having a grommet body and a fastening means for fastening

said grommet body to the side face by pressing an edge of a mounting plate included in said grommet body against the side face, so that said harness is watertightly laid between said grommet body and the side face by said fastening means.

5,588,261 DISCRIMINATOR RAIN GUTTER SYSTEM


Ian O. MacConochie, 300 Old Landing Rd., Yorktown, Va. 23692

Filed Jun. 24, 1994, Ser. No. 265,127

Int. Cl.⁶ E04D 13/00

U.S. Cl. 52—11

5 Claims



1. A gutter assembly adapted to be attached to a fascia board located below a building roof, said gutter assembly comprising: a half-cylinder including an upper flange and a lower flange, each of said flanges extending radially outward from said half-cylinder and generally defining a single plane, said flanges adapted to be attached to said fascia board; a gutter defining a fluid receiving trough having a modified channel shape and being adapted to be mounted immediately below and adjacent to said half-cylinder on said fascia board such that fluid flowing off said building roof is directed over and around the half-cylinder and into said gutter.

5,588,262 LANDSCAPING BLOCK SYSTEM


William B. Dawson, Maple Grove, Minn., assignor to Keystone Retaining Wall Systems, Inc., Bloomington, Minn.

Filed May 19, 1994, Ser. No. 246,256

Int. Cl.⁶ E02D 17/00

U.S. Cl. 52—102

12 Claims



6. A landscaping system comprising:
 - (a) a landscaping block anchor, the landscaping block anchor partially embedded in a substrate having an upper surface;
 - (b) one or more landscaping blocks, each of the blocks comprising a top and a generally opposed bottom, first and second generally opposed sides, each side extending from the top to

the bottom, the first side of each block comprising a first upper face extending from the top downward to an inner edge of a first lip, the first lip extending outward from the first upper face to an outer edge of the first lip for alignment of the outer edge of the first lip with the upper surface of the substrate when the block is inserted in the substrate, and a first lower face extending from the outer edge of the first lip to the bottom, and the second side of each block comprising a second upper face extending from the top downward to an inner edge of a second lip, the second lip extending outward from the second upper face to an outer edge of the second lip for alignment of the outer edge of the second lip with the upper surface of the substrate when the block is inserted into the substrate, and a second lower face extending from the outer edge of, first and second generally opposed ends, each end extending from the top to the bottom and from the first side to the second side, the bottom comprising an anchor coupler, wherein each block is coupled with the landscaping block anchor by the anchor coupler receiving the landscaping block anchor.

5,588,263


DOUBLE ADAPTOR BAR FOR SINGLE INSERTS USED IN CASTING CONCRETE

David L. Kelly, Sacramento, Calif., and Sidney E. Francies, III, San Antonio, Tex., assignors to HEM Trading, Long Beach, Calif.

Filed Sep. 21, 1994, Ser. No. 309,808
Int. Cl.⁶ E04G 21/14

U.S. Cl. 52—125.4

10 Claims




1. An anchor assembly interconnecting two anchors provided for embedment in a concrete tilt-up wall section, comprising: at least two anchors, each having a body with whole and narrowed cross-sections, and an elongated adaptor bar including first and second cutouts, each cutout being complementary in shape to the whole cross-section of the anchors and having a narrowed connecting passage extending the cutout through an adjacent edge of the elongated adaptor bar, each narrowed connecting passage having a width corresponding to the narrowed cross-section of the anchors to allow the narrowed cross-section to pass there-through into the cutout, the cutout longitudinally movable along the anchor to the whole cross-section for securely engaging it within the cutout, thereby allowing the anchor to be retained at each end of the elongated adaptor bar for releasable interconnection in a spaced relationship.

METHOD AND APPARATUS FOR SUPPORTING A BUILDING SURFACE

Claude Buzon, 2 Place Licourt, 4040 Herstal, Belgium
Filed Feb. 17, 1995, Ser. No. 390,851
Int. Cl.⁶ B66F 3/10; E04F 15/024

U.S. Cl. 52—126.6

6 Claims



5. An apparatus for supporting a platform which may be exposed to fluids, comprising: a support member having a support surface to engage the platform having a first threaded surface and a first fluid pathway having an input on the support surface for removing fluids from the support surface; a base member having a second threaded surface for engaging the first threaded surface and a second fluid pathway in communication with the first fluid pathway and having a plurality of outlets in the base member for transporting fluids radially outward from said base and support members into the exterior environment, wherein said base member includes contacting portions that contact a fixed surface on which said base member is supported and in which the support surface is elevated by rotating said contacting portions of said base member relative to said support member; and means for indicating provided with at least one of said support member and said base member, said means for indicating including an indicator slot formed in one of said first threaded surface and said second threaded surface with said indicator slot extending for a predetermined number of threads and with said indicator slot being movable when said contacting portions of said base member rotate relative to said support member.


5,588,265

EARTHQUAKE PROTECTIVE STRUCTURE

Danny A. Gill, 1428 Mt. Pleasant St., Los Angeles, Calif. 90042
Filed Aug. 26, 1994, Ser. No. 297,264
Int. Cl.⁶ E04H 9/00

U.S. Cl. 52—167.1

9 Claims



1. An earthquake protective structure attached to one of a door jamb or other portal of a building comprising: a) a first side section having an upper end, a lower end, an inward surface, an outward surface, a front end and a rear end, b) a second side section having an upper end, a lower end, an inward surface, an outward surface, a front end and a rear end, c) an upper section having a first side end, a second side end, an inward surface, an outward surface, a front end and a rear end,

where the first side end is attached by an attachment means, to the upper end of said first side section and the second side end is attached by an attachment means to the upper end of said second side section.

- d) at least two angle iron supports each having a first leg and a second leg, where said supports are spaced around the outer surface of said upper section and said first and second side sections with the first leg attached to said structure by an attachment means and said second leg surrounding said first and second side sections and said upper section having a multiplicity of bolt bores therethrough where into each of said bolt bores is inserted a threaded bolt that is threaded into said door jamb portal of a building, and
- e) a base plate having first side end and a second side end where the first side end is attached by an attachment means to the lower end of the first side section, and the second side end is attached by an attachment means, to the lower end of said second side section, where said attached structure is sized to allow at least one person to stand under said structure to protect a person from falling debris resulting from an earthquake.

being sized and positioned to extend into a crevice between said threshold cap and a wall of said upwardly open channel in which said threshold cap is supported to hold the protective cover removably in place on said assembly.


5,588,267

MULTI-SIZE ROOF FLASHINGS

Roberto Rodriguez, Cleveland, and Edward T. Shroka, Rocky River, both of Ohio, assignors to Oatey Co., Cleveland, Ohio
Filed Jul. 6, 1995, Ser. No. 498,574
Int. Cl.⁶ E04D 13/14

U.S. Cl. 52—219

18 Claims



1. A roof flashing with an elastomeric collar for establishing a weather-proof seal with upstanding pipes of different diameters extending through exterior openings in building structures, said collar comprising a frusto-conical shape member having an opening in an apex end for passage of the pipe, said member including smaller and larger diameter seals for sealingly engaging different diameter pipes, an internal annular groove in said member immediately above said larger diameter seal providing a frangible wall section in said member to facilitate removal of said smaller diameter seal from said member when said member is to be used to seal against larger diameter pipes, and an external annular bead on said member for resisting stretching of said member when engaged by a gripping tool immediately above said groove and pulled to provide a relatively clean tear in a region of said groove around an entire periphery of said member to separate said smaller diameter seal from said member.

5,588,266

CONTINUOUS SIDELIGHT SILL WITH ADAPTABLE THRESHOLD CAPS AND REMOVABLE PAINT SHIELD

J. Charles Headrick, 5775 Bethelview Rd., Cumming, Ga. 30130

Continuation-in-part of Ser. No. 160,975, Dec. 3, 1993, which is a continuation-in-part of Ser. No. 5,621, Mar. 8, 1993. This application May 16, 1994, Ser. No. 243,259

Int. Cl.⁶ B05C 21/00; E06B 1/70

U.S. Cl. 52—204.1

8 Claims



1. A threshold and door sill assembly with removable paint shield, said assembly comprising:

- an elongated frame member having an outside edge portion and an inside edge portion, said member being formed with a longitudinally extending upwardly open channel adjacent and extending along said inside edge portion and a will shaped to provide a surface that extends laterally and slopes downwardly from said channel to a forward lip at the outside edge portion of said frame member;

an elongated threshold cap sized and configured to be received and supported within said upwardly open channel, said threshold cap having an upper surface, a forward surface, and a rear surface;

said threshold cap being disposed and supported in said upwardly open channel with its upper surface projecting from the channel;

an elongated protective cover having to top with a forward edge portion and a rear edge portion, said protective cover being shaped and sized to fit onto said elongated frame member with the top of said protective cover spanning and covering at least said upper surface of said threshold cap within said upwardly open channel;

means for releasably securing said protective cover to said threshold and door sill assembly to protect at least said threshold cap from damage during construction of a building in which said assembly is installed;

said means for releasably securing said protective cover to said threshold and door sill assembly comprising a tab depending from said upper surface of said protective cover with said tab

5,588,268

PLATE ELEMENT FOR A BUILDING PANEL ASSEMBLY

Fritz Sterflinger, Papenburg, and Hans Möhlenkamp, Sögel, both of Germany, assignors to Jos. L. Meyer Werft GmbH & Co., Papenburg, Germany

PCT No. PCT/DE94/00692, § 371 Date Feb. 22, 1995, § 102(e) Date Feb. 22, 1995, PCT Pub. No. WO95/00725, PCT Pub. Date Jan. 5, 1995

PCT Filed Jun. 17, 1994, Ser. No. 392,759


Claims priority, application Germany, Jun. 23, 1993, 43 20 740.5; Dec. 22, 1993, 43 43 859.8
Int. Cl.⁶ E04B 5/10; E04C 2/08; B63B 3/48

U.S. Cl. 52—236.7

2 Claims

1. A building panel assembly adapted for installation on a lower chord of a support construction comprising:

- a steel plate element comprising:
- an upper and a lower outer sheet extending in parallel spaced relation to one another, each outer sheet having an inner surface facing the other sheet;
 - a plurality of web strips interposed between said outer sheets, each web strip having opposite longitudinal edges welded to said inner surfaces of respective outer sheets with a laser weld which passes through each outer sheet to interconnect said outer sheets with one another;



said plate element having a cutout extending therethrough and being adapted to lie across the lower chord with the cutout directly overlying the lower chord; and
a tubular support part, having a collar flange and a hollow interior bordered by an inside wall, disposed within the cutout and adapted to be supported by the lower chord and connected thereto by a weld on said inside wall, wherein said collar flange rests on said upper outer sheet and is welded thereto.

5,588,269

PREFABRICATED CONSTRUCTION SYSTEM FOR A TIMBER HOUSE

Edmund Wagner, Wiesbaden, Germany, assignor to Zorbedo GmbH, Wiesbaden, Germany

Filed Aug. 31, 1994, Ser. No. 297,919

Claims priority, application Germany, Sep. 1, 1993, 43 29 413.8

Int. Cl.⁶ E04B 2/00

U.S. Cl. 52—270

13 Claims



1. A prefabricated construction assembly, comprising: a plurality of box-shaped rectangular panel elements, each panel element having:
 - at least first and second solid, continuous wood girders separated from one another by a distance and being parallel to one another to form two opposite first sides of the respective panel element, and
 - at least first and second panels connected to said girders and sandwiching said girders therebetween to form two opposite second sides of the respective panel element, said girders and said panels of the respective panel element collectively forming four sides of a box,
 wherein two adjacent panel elements are connected together with a tongue-and-groove joint, said tongue-and-groove joint being formed by projecting said first girder from between said panels along one of the first sides, and setting back the second girder within said panels by a corresponding measure along the other of the first sides, and wherein said panels project beyond the ends of said girders at two oppositely located third sides of said panel element to define an upper and a lower end

of the respective panel element and form continuous receiving elements extending in a direction from one of the first sides to the other of the first sides, and

- a plurality of continuous orienting beams insertable into the respective receiving elements to be parallel thereto for orientating said panel elements in relation to each other at the third sides, said panel elements being placed next to each other and connected to each other by the tongue-and-groove joint, said orienting beams having rectangular cross sections and dimensions which are such that when said orienting beams are inserted into the respective receiving elements, the orienting beams abut against the inner sides of said panels, and form at each of the upper and lower ends at least one continuous free space between said orienting beams and the respective ends of said girders to receive supply lines, and at least at the upper end of said panel elements, the respective ends of said first and second girders form a support for said orienting beam designated for the respective receiving element.

5,588,270

GARAGE DOOR BRACE


Carey E. Keating, 2106, 13531 Deer Run Boulevard SE., Calgary, Alberta, Canada

Filed Jun. 26, 1995, Ser. No. 494,947

Int. Cl.⁶ E04G 23/00

U.S. Cl. 52—291

4 Claims



1. A system for reinforcing multi-sectional doors of the type including multiple horizontal panels interconnected at each longitudinal side to adjacent panels, the system including corner plate means adapted for attachment to opposite lower corners of a bottom panel section of said door; first and second strut means one end of each said strut means fixedly attached to a respective one of said corner plate means, each said strut means extending upwardly and inwardly of said panel structure; an upper end of each said strut means being terminally attached to upper connector means such that said corner means, said strut means and said connector means define a substantially rigid triangular frame means within the confines of said bottom panel structure adjacent an inner facing surface thereof; pin means operably associated with said upper connector means to extend vertically downwardly therefrom to lower bracket means, adapted for attachment to a bottom said door; intermediate bracket means located vertically above said lower bracket means and spaced between said lower bracket means and said connector means, said intermediate bracket means adapted for attachment to said door and configured to positionally support and guide said pin means; means to put said pin means into tension and exert an upward force on the bottom of said door, while exerting a compressive force via said strut means to said corner plate means, thus compensating for door weight and eliminating sagging.

5,588,271

INTERLOCKING BUILDING BLOCK

Peter R. Pitchford, 170 Ellis Park Road, Toronto, Ontario, Canada

PCT No. PCT/CA93/00038, § 371 Date Sep. 29, 1993, § 102(e)

Date Sep. 29, 1993, PCT Pub. No. WO93/15286, PCT Pub.

Date Aug. 5, 1993


PCT Filed Jan. 29, 1993, Ser. No. 122,485

Claims priority, application Canada, Jan. 30, 1992, 2060379-8

Int. Cl.⁶ E04C 1/00; E04B 2/00

U.S. Cl. 52—306

7 Claims



1. An interlocking building block comprising:

a block having spaced-apart front and rear walls and peripheral end walls, the block being shaped such that a plurality of such blocks may be arranged in a contiguous manner with respective end walls touching to form a wall, there being at least two adjacent peripheral end walls on each block intersecting at an angle;

each of said intersecting end walls having an elongate rib and means defining a parallel elongate groove spaced therefrom and adapted to mate with a corresponding respective elongate groove and rib on an adjacent block;

a first interlocking means formed on one of the rib and the groove in one of said intersecting end walls adapted to engage a complementary interlocking means on a first adjacent block to prevent longitudinal sliding movement of the rib in the groove with respect to said first adjacent block;

a second interlocking means formed on one of the rib and the groove in the other of said intersecting end walls adapted to engage a complementary interlocking means on a second adjacent block to prevent longitudinal sliding movement of the rib in the groove with respect to said second adjacent block; and

the first and second interlocking means being one of a lateral projection formed on the rib and means defining a lateral slot adjacent to the groove and located to receive a lateral projection formed on a rib of an adjacent block.

5,588,272

REINFORCED MONOLITHIC CONCRETE WALL STRUCTURE FOR SPANNING SPACED-APART FOOTINGS AND THE LIKE

Edward L. Haponski, P.O. Box 456, Coats, N.C. 27521

Filed Nov. 28, 1994, Ser. No. 345,857


Int. Cl.⁶ E04B 1/04

U.S. Cl. 52—309.12

22 Claims

1. A precast, reinforced concrete wall structure for spanning spaced-apart footings and forming a part of a building structure, comprising:

a) a noncast vertical main section including a pair of opposed concrete panels, an insulation board disposed between the concrete panels such that the insulation board is covered on opposite sides with concrete and effectively embedded within



the concrete that forms the pair of opposed concrete panels whereby the embedded insulation board retains heat within the building structure, and reinforcing material embedded within each concrete panel;

b) wherein the opposed concrete panels wrap around the insulation board and form a single concrete structure;

c) a plurality of vertical concrete columns integral with the concrete panels and extending continuously from a bottom portion of the concrete wall structure to a top portion of the concrete wall structure and wherein the insulation board is disposed between the plurality of vertical concrete columns and wherein the columns are reinforced and disposed about opposite end portions of the concrete wall structure so as to permit the concrete wall structure to span two spaced apart footings; and

d) an upper horizontal concrete beam integral with and positioned atop the vertical main section and the vertical concrete columns, the upper horizontal concrete beam including a plurality of horizontal reinforcing members and being thicker than the vertical main section, and wherein the upper concrete beam strengthens the concrete wall structure such that the same can span the spaced-apart footings.

5,588,273

STRUCTURAL BEAM


Paul F. Csagoly, 2519 McMullen Booth Rd., Ste. 510, Clearwater, Fla. 34621

Filed Feb. 6, 1995, Ser. No. 384,144

Int. Cl.⁶ E04C 3/08

U.S. Cl. 52—634

15 Claims



1. A structural beam comprising:

a top flange,

a bottom flange,


a substantially planar web joining the top and bottom flanges;

a plurality of apertures located within the web;

a top chord, said top chord including said top flange and a longitudinally uninterrupted web portion, said top chord further including a neutral axis;

a bottom chord, said bottom chord including said bottom flange and a longitudinally uninterrupted web portion, said bottom chord further including a neutral axis;
a plurality of joining members located in said web between the top and bottom chord;
each said joining member adapted to transmit loading forces along a diagonal axis, said diagonal axes of adjacent joining members intersecting at panel points, said panel points located substantially along the neutral axis of a respective chord; and
haunches located in the plane of the web providing local structural deepenings of the top and bottom chords in the regions of the panel points;
wherein said haunches are substantially trapezoidal-shaped, each substantially trapezoidal-shaped haunch having a first side located proximate its respective chord and a second side, parallel with the first side, located distal from its respective chord, said first side being longer than said second side and, wherein each joining member includes a pair of opposing side edges, each said side edge terminating at a location spaced from both said top and bottom chords.

5,588,274
MODULAR STRUCTURAL FRAMING SYSTEM
Fredric Lange, 13690 Elm Creek Rd., Osseo, Minn. 55369-9343
Filed Jul. 16, 1993, Ser. No. 92,602
Int. Cl.⁶ F04H 12/10; E04B 1/38; F16B 5/06
U.S. Cl. 52—653.1 32 Claims



1. Modular structural framing system comprising, in combination: first and second structural members each having first and second faces, with the first faces of the first and second structural members having complementary shapes for abutting with each other, with each of the first and second structural members having at least first ports formed therein, with the first ports extending through the first and second faces of the first and second structural members and being of the same size; a clamp comprising, in combination: a primary band including a central wall having a length less than the perimeter of the first ports, with the primary band being generally annular but U-shaped and having first and second free ends, with the primary band having a normal shape which is of a size smaller than and for insertion into the ports, first and second secondary bands each having first and second ends, means for pivotally mounting the first ends of the first and second secondary bands together about a first axis, means for pivotally mounting the second end of the first secondary band relative to the first free end of the primary band, and means for pivotally mounting the second end of the second secondary band relative to the second free end of the primary band, with pivotal movement of the first and second secondary bands about the first axis causing the

primary band to distort from its normal shape to further separate the first and second free ends of the primary band; wherein at least the first structural member is three-dimensional and hollow, with the first structural member being formed by a plurality of attachment panels having thicknesses and first edges and by means for removably securing the first edge of one attachment panel to the first edge of another attachment panel, with the removably securing means comprising, in combination: a plurality of latches extending from and equally spaced along the first edge, with each of the latches lying within the same plane, and at least one detent portion formed in each of the latches, with the detent portions intersecting the plane of the latches at a nonlinear angle, with the ports formed in the attachment panels; an accessory comprising, in combination: an end plate having a periphery of a size larger than the port, a channel formed in the end plate and extending from a first point of the periphery to a second point spaced from a third point of the periphery diametrically opposite the first point a distance less than the size of the port, with the channel having a width greater than and for slideably receiving the thickness of the panel, and a support member secured to the end plate, with the attachment panels having rectangular slits spaced from the first edges, inside surfaces and outside surfaces; a clip comprising, in combination: a first portion for abutting with the inside surface of the attachment panel, a second portion extending continuously and at a non-linear angle to the first portion, a third portion extending continuously and at a non-linear angle to the second portion in a direction away from but parallel to the first portion, with the third portion abutting with the outside surface of the attachment panel, and means secured to the third portion for holding accessories to the attachment panel, with at least the first and second portions including rectangular cross sections having a width and thickness for slideable receipt in the rectangular slit, with the second portion spacing the first and second portions a distance generally equal to the thickness of the attachment panel between the inside surface and the outside surface, with the latches and detent portions of the attachment panels being L-shaped, with the latches and detent portions of first and second attachment panels having a generally T-shape in a latched condition; and a connector comprising means for forming a T-shaped slot of a size for slideable receipt upon the generally T-shape of the latches and detent portions of the first and second attachment panels in the latched condition.


5,588,275

Patent Not Issued For This Number

5,588,276
SLEEVEING MACHINE

Herman F. Terjung, 412 N. Exeter St., Baltimore, Md. 21202, and David P. Crum, 4207 Kolb Ave., Baltimore, Md. 21206
Continuation-in-part of Ser. No. 25,843, Mar. 3, 1993, Pat. No. 5,379,570. This application Dec. 5, 1994, Ser. No. 349,433
Int. Cl.⁶ B65B 13/02; 19/18; 57/06; 57/18 23 Claims

U.S. Cl. 53—399
19. A method for automatically inserting a tray of postal mail into a sleeve, the sleeve having a top, a bottom, two opposite sides therebetween and two open ends, the sides each having a height, the method comprising the steps of:
providing a transport station having a first side, a second side, a first end and a second end, the sides being substantially perpendicular to the ends;
providing a continuous transport means disposed between the sides of the transport station, providing at least one pusher means attached to the transport means such that the at least one pusher means may engage the tray;
placing the tray on the transport means at the first end of the transport station and moving said tray to the second end of the transport station;
providing a sleeving station adjacent to the second end of the transport station, the sleeving station having a base surface, a




first sidewall and an opposite second sidewall, the transport means extending through the sleeving station between the sidewalls of the sleeving station, wherein the at least one pusher means advances the tray in a direction from the transport station to the sleeving station;
the first sidewall of the sleeving station being a hopper, providing a plurality of collapsed sleeves within the hopper, providing means within the hopper for dispensing the collapsed sleeves one at a time as desired, into the sleeving station, dispensing the collapsed sleeve into the sleeving station such that when dispensed from the hopper, the sleeve is received between the opposite sidewalls of the sleeving station, the base surface of the sleeving station supporting the bottom of the sleeve, the hopper supporting one of the sides of the sleeve providing a source of vacuum and a suction head interruptably connected to the source of vacuum, adjustably disposing the suction head above the sleeving station for engaging the top of the collapsed sleeve;
applying vacuum to the suction head and fully opening the collapsed sleeve;
discontinuing application of vacuum to the suction head;
advancing the tray into the opened sleeve in the sleeving station and pushing the sleeve containing the tray out of the sleeving station and sequentially repeating of the steps.

5,588,277
BAND APPLICATOR FOR APPLYING A BAND ABOUT A SHEET OF MATERIAL AND A POT


Donald E. Weder, Highland; William F. Straeter, Breese, and Joseph G. Straeter, Highland, all of Ill., assignors to Southpac Trust International, Inc., Oklahoma City, Okla.
Continuation of Ser. No. 934,832, Aug. 24, 1992, Pat. No. 5,426,914, which is a continuation-in-part of Ser. No. 819,311, Jan. 9, 1992, abandoned, which is a continuation of Ser. No. 765,416, Sep. 26, 1991, Pat. No. 5,105,599, which is a continuation of Ser. No. 530,491, May 29, 1990, abandoned, which is a continuation of Ser. No. 315,169, Feb. 24, 1989, abandoned, said Ser. No. 934,832 is a continuation-in-part of Ser. No. 832,096, Feb. 6, 1992, abandoned, which is a continuation-in-part of Ser. No. 765,416, Sep. 26, 1991, Pat. No. 5,105,599, which is a continuation of Ser. No. 530,491, May 29, 1990, abandoned, which is a continuation of Ser. No. 315,169, Feb. 24, 1989, abandoned. This application Apr. 17, 1995, Ser. No. 423,678
Int. Cl.⁶ B65B 13/02; 67/08 10 Claims

U.S. Cl. 53—399
1. A method for placing a band about a sheet of material for holding the sheet of material about at least a portion of the outer peripheral surface of a flower pot and thereby provide a decorative cover for the flower pot wherein an open upper end of the flower pot remains substantially uncovered by the decorative cover, comprising:
providing a pot frame having a pot receiving space formed therein;



positioning at least one sheet of material on the pot frame so that the sheet of material is disposed over the pot receiving space in the pot frame;
moving the flower pot and the sheet of material into the pot receiving space in the pot frame for forming the sheet of material into a decorative cover extending about the outer peripheral surface of the flower pot and for holding the decorative cover about the outer peripheral surface of the flower pot while maintaining the open upper end of the flower pot substantially uncovered by the decorative cover;
positioning a band about a decorative cover to secure the decorative cover about the outer peripheral surface of the flower pot while the decorative cover is held about the outer peripheral surface of the flower pot by the pot frame; and
removing the flower pot with the decorative cover secured thereto by the band from the pot receiving space in the pot frame.

5,588,278
BROCCOLI BANDING MACHINE
Ed Wynn, Monterey; Javier Diaz-Infante, Salinas, and Peter deGroot, Carmel, all of Calif., assignors to Dole Fresh Vegetables Co., Salinas, Calif.
Filed Jun. 27, 1995, Ser. No. 495,235
Int. Cl.⁶ B65B 53/00; 11/00 8 Claims



5. A process including a broccoli banding machine for placing a rubber band about a bouquet of broccoli comprising the steps of:
providing a broccoli banding machine including:
a plate with a central aperture;
a light sensor mounted immediate said central aperture;
a light source for emanating a beam across the central aperture to said light sensor;
band engaging fingers attached to said plate and moveable between a first position juxtaposed one to another at said central aperture to a second position wherein said fingers are separate from one another; and,
a motor drive for moving said band engaging fingers between said first and second position;
bunching a bouquet of broccoli with the stems of said bouquet held together;

interrupting said light beam with said bunched stems of broccoli;
 actuating said motor drive responsive to interruption of said light beam to move said fingers from said second position wherein said fingers are away from said central aperture to said first position wherein said fingers are juxtaposed to one another at said central aperture to place a rubber band about said broccoli stems;
 removing said broccoli bouquet with said rubber band on said stems;
 placing a replacement rubber band on said fingers; and
 actuating said motor drive after said rubber band is on said fingers to move said fingers from said first position wherein said fingers are juxtaposed to one another at said central aperture to said second position where said fingers are away from said central aperture to expand said rubber band upon expiration of a time delay.

5,588,279

APPARATUS AND METHOD FOR TRANSPORTING A CONTAINER BETWEEN PROCESSING STATIONS OF A PACKAGING MACHINE


Bo Runnberg, Dalby, Sweden, and Tommy B. G. Ljungström, Buffalo Grove, Ill., assignors to Tetra Laval Holdings & Finance S.A., Pully, Switzerland

Filed Sep. 26, 1994, Ser. No. 311,963

Int. Cl.⁶ B65B 3/00; 7/20; 43/46; 55/04

U.S. Cl. 53—426

34 Claims




1. An apparatus for use while moving a container from a first processing station to a second processing station of a packaging machine, said container including a top portion defined by a plurality of sealing panels, said apparatus comprising:

- (a) pincers for temporarily holding said sealing panels of said container in a generally closed condition as said container is moved along a container path having a first end defined by said first processing station and a second end defined by said second processing station, the pincers comprising
 - i. a first arm at least partially rotatable about a first pivot axis extending in the direction of the container path,
 - ii. a second arm at least partially rotatable about a second pivot axis extending in the direction of the container path, said first and second arms being rotatable toward one another to grip and temporarily seal said sealing panels; and
- (b) means for moving said pincers along with the container along at least a substantial distance of the container path while maintaining the container in the closed condition.

5,588,280
COUPON INSERTING APPARATUS AND METHOD
 Thomas G. Kotsiopoulos, Northfield, Ill., assignor to Carol Joyce Witt, Lake Zurich, Ill.
 Continuation of Ser. No. 129,482, Sep. 29, 1993, abandoned, which is a continuation of Ser. No. 819,766, Jan. 13, 1992, abandoned, which is a continuation of Ser. No. 634,923, Dec. 21, 1990, Pat. No. 5,079,901, which is a continuation of Ser. No. 348,860, May 8, 1989, abandoned. This application Jun. 7, 1995, Ser. No. 486,766
 Int. Cl.⁶ B65H 35/10

U.S. Cl. 53—435

20 Claims



20. A method of delivering coupons, one at a time, to moving containers as the containers move past a predetermined point of insertion, the coupons being provided in a continuous web wherein a trailing edge of a forwardmost coupon is detachably connected to a leading edge of a successive coupon by a weakened separable portion therebetween and wherein each coupon after the successive coupon is similarly connected in the web, the method thereby manufacturing containers having coupons therein and comprising the steps of:

- sensing the movement of the containers relative to the predetermined point of insertion and generating a timing signal based upon the movement of the containers, the timing signal pertaining to when one of the containers will be at the predetermined point of insertion;
- sensing the presence and absence of the forwardmost coupon at a sensing position and generating a sensing signal pertaining thereto;
- providing a coupon separation and delivery subassembly between the continuous web of coupons and the predetermined point of insertion, the subassembly including feed rolls and positioning rolls, the positioning rolls disposed downstream of the feed rolls;
- advancing the continuous web of coupons utilizing the feed rolls;
- providing a first output signal based in part upon the timing signal and the sensing signal, and
- separating the forwardmost coupon from the successive coupon in response to the first output signal and delivering the forwardmost coupon to one of the moving containers as said container moves past the predetermined point of insertion.

5,588,281

METHOD OF PRODUCING CARTONS OF CIGARETTES WITH A RIGID HINGED-LID WRAPPING


Silvano Boriani, and Antonio Gamberini, both of Bologna, Italy, assignors to G.D. Società Per Azioni, Bologna, Italy
 Filed May 15, 1995, Ser. No. 440,776

Claims priority, application Italy, May 16, 1994, B094A-0213
 Int. Cl.⁶ B65B 35/30

U.S. Cl. 53—443

5 Claims

1. A method of producing cartons of cigarettes with a rigid hinged-lid wrapping, the method being characterized in that it comprises the steps of:
 forming groups of packets of cigarettes by feeding stacks of cigarettes successively along a given path and in a first



direction parallel to the longer axes of the packets; successively expelling the stacks from said path in a second direction; rotating each stack 90° about an axis crosswise to said first and second directions, so that said longer axes are parallel to said second direction; and again feeding the stacks, so oriented, in said second direction, so that each stack is positioned end to end alongside another stack, thus forming a respective said group of at least two end to end stacks in which each packet in each stack is laid flat with its longer axis horizontal and aligned with the longer axis of a corresponding packet in the other stack;

feeding a flat blank of said rigid wrapping into a position between said group of at least two end to end stacks and a folding spindle, the spindle facing the group in a direction crosswise to the longer axes of the packets; and feeding each group, crosswise to the longer axes of the packets and together with said flat blank, into engagement with said spindle, so as to fold the blank in contact with the spindle, and so that the bottom wall of the spindle supports the group with the interposition of a panel of the blank corresponding to a lateral wall of the rigid wrapping.

5,588,282 CONTINUOUS MOTION CASE PACKING APPARATUS AND METHOD


Thomas P. Hartness, Greenville, S.C., assignor to Hartness International, Inc., Greenville, S.C.

Filed Nov. 10, 1994, Ser. No. 338,026

Int. Cl.⁶ B65B 5/08; 21/06; 21/18

U.S. Cl. 53—473

76 Claims



1. Apparatus for packing articles conveyed in at least one longitudinal row into cases in a continuous motion comprising:

a slug feeder receiving said row of articles for forming a slug containing a predetermined number of said articles in said row and conveying said articles to a slug pick-up station; said slug pick-up station supporting said slug of articles in a position to be picked up for transfer to a case packing station; a vertical revolving carriage which carries a plurality of article transfer arms; a plurality of article pick-up heads carried by said transfer arms which reciprocate in a linear motion relative to said transfer arms for picking up said slug of articles at said slug pick-up station; said carriage carrying said transfer arms and pick-up heads in a curved, vertical plane path which includes a linear transfer section between said slug pick-up station and said case packing station in a generally straight line path; an actuator associated with said pick-up heads having a first position in which a slug of articles is retained by said pick-up head at said slug pick-up station for transfer, and said actuator having a second position in which said slug of articles is released for deposit into said case at said case packing station; and a case indexing conveyor for conveying indexed cases to said case packing station for receiving said released slug in synchronization with said moving carriage and said slug feeder.

5,588,283

LIDDING MACHINE


Herman W. Martin, Aldergrove, Canada, assignor to Ropak Canada Inc., Delta, Canada

Filed Jun. 7, 1995, Ser. No. 483,758

Int. Cl.⁶ B67B 1/04; 3/22; B65B 7/28

U.S. Cl. 53—486

9 Claims



1. An apparatus for lidding and sealing a resilient pail having a sealing lip and lip flange, with a lid having a lip sealing surface corresponding to the pail lip, comprising:

- a. a pail holding tool in a base;
- b. a lid press plate slidably engaged in a bridge on a base for sliding movement in a direction normal to the base while the lid press plate is substantially parallel to the base, the lid press plate having alignment guides depending from its edges for engaging the lip flanges of the pail and conforming the pail lip shape to the lid sealing surface shape as the lid is pressed by the plate onto the pail.

5,588,284

METHOD AND APPARATUS FOR PACKING A PLURALITY OF ARTICLES IN CARTONS


John M. Klover, Canton, and Philip F. Hamrick, Atwater, both of Ohio, assignors to Hamrick Manufacturing & Service, Inc., Mogadore, Ohio

Filed Apr. 10, 1995, Ser. No. 419,423

Int. Cl.⁶ B65B 5/10; 21/10

U.S. Cl. 53—534

19 Claims



1. An apparatus for continuously packing a plurality of articles into cartons, said apparatus comprising:
a loading station;
said loading station incorporating a plurality of support rollers disposed in longitudinally spaced series;
a belt means freely rotatable across said series of support rollers; and
a brake means to adjust the resistance provided said belt to a carton traversing said loading station;
a carton delivery queue for providing a continuous sequence of cartons to said loading station;
means to transport the cartons along said carton delivery queue and to maintain at least the next successive carton in said queue in continuously juxtaposed, longitudinal engagement with any carton on said loading station;
an article orienting and delivery queue for longitudinally aligning a plurality of articles in the desired side-by-side relationship;
a slide assembly included in said article orienting and delivery queue;
said slide assembly being inclined to assure that the articles will be gravity-propelled to a sufficient degree longitudinally to traverse said slide assembly and be received at said loading station;
flight means longitudinally to space the articles in the predetermined grouping required for that carton at said loading station; and
said gravity-propelled, descending movement of the articles and the resulting engagement of the articles with a carton at said loading station effecting synchronous movement of the carton along said loading station relative to the movement of the articles along said slide assembly so that the articles will be continuously deposited within the carton.

5,588,285

SYSTEM FOR LOADING PACKAGES INTO A BOX

Heinz F. Odenthal, Zülplch, Germany, assignor to Ostma Maschinenbau GmbH, Zülplch, Germany

Filed Jul. 6, 1995, Ser. No. 498,941


Claims priority, application Germany, Jul. 12, 1994, 94 10 970.2 U

Int. Cl.⁶ B65B 35/30

U.S. Cl. 53—534

4 Claims

1. A system for packing a plurality of packages into a container, the system comprising:
means including an input conveyor for delivering the packages one at a time at regular intervals and at a constant input speed to a transfer station;



an output conveyor having a perforated lower belt and an upper belt together defining a path extending from an upstream end at the transfer station to a downstream end at a loading station, the downstream end being vertically displaceable at the loading station;
a container conveyor extending past the loading station under the downstream end of the output conveyor;
means for advancing the container conveyor at a relatively high container speed and at a relatively low container speed for displacing a succession of the containers through the station;
means connected to the downstream end of the output conveyor for displacing it between a lower position in one of the containers in the loading station and an upper position out of the way of the containers passing on the container conveyor;
means connected to the output conveyor for displacing it and any packages held by it at a relatively low stacking speed that is slower than the input speed and at a relatively high gapping speed that is higher than the input speed, whereby when the output conveyor is running at the slow stacking speed packages deposited on it by the input conveyor will overlap one another and when the output conveyor is running at the high gapping speed a space will be formed between packages on the output conveyor and packages deposited thereon by the input conveyor;
a suction box underneath the perforated lower belt at the transfer station; and
control means connected to the suction box and to all of the means for
operating the output conveyor at the low stacking speed to form an overlapped group of the packages on the output conveyor while drawing air via the suction box in through the lower belt to adhere the packages to the lower belt, periodically switching the output conveyor from the low stacking speed to the high gapping speed when a predetermined number of the packages have been deposited on the output conveyor by the input conveyor to form a space on the output conveyor between succeeding groups of packages,
operating the container conveyor at the low speed and simultaneously moving the output-conveyor downstream end into the lower position dipped into one of the containers in the loading station to deposit a group of the packages into the container in the loading station, and
operating the container conveyor at the high speed and simultaneously moving the output-conveyor downstream end into the upper position clear of the container in the loading station to displace a full container out of the loading station, the control means switching the container conveyor between its high and low speeds synchronously with switching of the output conveyor between its gapping and stacking speeds.

5,588,286

FOLDING DEVICE, ESPECIALLY FOLDING TURRET, WITH FOLDING MANDREL

Heinz Focke, Verden, and Hans-Jürgen Bretthauer, Bremen, both of Germany, assignors to Focke & Co. (GmbH & Co.), Verden, Germany


Filed Oct. 18, 1995, Ser. No. 544,476

Claims priority, application Germany, Oct. 19, 1994, 44 37 404.6

Int. Cl.⁶ B65B 11/02; 19/24; B31B 1/28; B23K 26/00

U.S. Cl. 53—575

11 Claims



1. A folding device, for pack blanks (12) and pack contents (10), comprising a folding mandrel (13) which is positioned so as to project from one side of the folding device, which is open at two opposite ends thereof, and which is made of thin-walled metallic material, wherein the folding mandrel (13) comprises at least one sheet of said material, said sheet having at least one longitudinal laser-weld seam (21, 22, 29, 30).

5,588,287

WRAPPING APPARATUS WITH BARRIER


Ruth Lerner, and John Fain, both of Louisville, Ky., assignors to Lantech, Inc., Louisville, Ky.

Continuation-in-part of Ser. No. 338,165, Nov. 10, 1994, abandoned. This application Jun. 15, 1995, Ser. No. 490,763

Int. Cl.⁶ B65B 11/04

U.S. Cl. 53—588

24 Claims



1. An apparatus for wrapping a load with packaging material comprising:
a dispenser for dispensing a sheet of packaging material;
a turntable assembly including a turntable base and a powered turntable having a generally horizontal support surface for supporting the load and mounted in the base for rotation about a generally vertical axis to wrap the sheet of packaging material around the load, the support surface having a peripheral edge;
a horizontally displaceable barrier mounted to the turntable for rotation with the turntable and positioned along at least a portion of the peripheral edge of the support surface, the barrier having an outer surface at a position normally spaced

at a greater distance from the vertical axis than the peripheral edge of the support surface along which the displaceable barrier is mounted; and
means for automatically returning the barrier to its normally spaced position after being horizontally displaced.

5,588,288

BOOT FOR SHOD ANIMAL'S HOOVES

Ambrogio Origi, Via Canova, 12-29010 Pioszano (Piacenza), and Silver Pecis, Via Vallunga, 5-24060 Foresto Sparso (Bergamo), both of Italy


Filed Nov. 8, 1994, Ser. No. 337,831

Claims priority, application Italy, Nov. 10, 1993, MI93U0875

Int. Cl.⁶ B68C 5/00

U.S. Cl. 54—82

12 Claims



1. A boot made of flexible elastic material for the hooves of hoofed animals, comprising:
a sole part; and
an upper part that is integral with the sole part and defines therewith a housing to accommodate a hoof, wherein the sole part has a seat formed inside to accommodate a shoe fitted to the hoof and at least one hollow at the back for protruding heel parts of the shoe, said at least one hollow being defined at its top by an elastic check tooth, wherein said check tooth has a sloping upper surface tapered downwardly toward the inside of the sole part, and a sharply projecting lower surface.

5,588,289

GARDEN CUTTING TOOLS


Graham J. Wilson, Brownroyd, 263 Pensby Rd., Pensby, Wirral, L61 5UA, England

Filed Nov. 8, 1994, Ser. No. 336,751

Int. Cl.⁶ A01D 55/00

U.S. Cl. 56—13.1

38 Claims



1. A cutting tool for use in the garden and workshops, comprising a body which houses a screw impeller which can be driven by a motor, the screw impeller being arranged to generate an air flow and to move waste along a flow path extending generally coaxial

with the screw impeller, through the body from an inlet to an outlet, the outlet being connectable to a receptacle which is adapted to entrap any material extrained by the air flow, a cutting blade which is rotatable coaxially with the screw impeller being arranged to be driven by the screw impeller and being located adjacent to the inlet and aligned with a fixed cutting blade which is fixed relative to the body to cut material projecting therebetween, which cut material is entrained through the body by the screw impeller and collected in the receptacle.

5,588,290

REEL-TO-REEL PIPE WRAP MACHINE


Robert E. Cobb, Rte. 8, Box 267-B, Claremore, Okla. 74017

Filed Apr. 17, 1995, Ser. No. 424,735

Int. Cl.⁶ D02G 3/36

U.S. Cl. 57—3

10 Claims



1. A pipe wrapping system comprising: a feeder reel for dispensing pipe coiled thereon; a take-up reel for collecting the dispensed pipe in coils thereabout; means independently disposed between said feeder and take-up reels and engaged with the pipe for travel along said pipe for spirally wrapping tape about the pipe; and means for varying a rate of travel of said wrapping means in relation to the pipe to maintain said wrapping means between said feeder and take-up reels as a rate of travel of the pipe varies.

5,588,291

METHOD FOR CONTROLLING THE HEATING OF AN ELECTRICALLY HEATABLE CATALYTIC CONVERTER

Wolfgang Maus, Rolf Brück, and Helmut Swars, all of Bergisch Gladbach, Germany, assignors to Emitec Gesellschaft fuer Emissionstechnologie mbH, Lohmar, Germany


Filed Jun. 2, 1995, Ser. No. 458,493

Claims priority, application Germany, Dec. 9, 1992, 42 41 494.6

Int. Cl.⁶ F01N 3/20

U.S. Cl. 60—274

19 Claims



1. In a method for controlling the heating of a catalytic converter being connected downstream of an internal combustion engine of a motor vehicle and having at least a short portion to be quickly electrically heated, the improvement which comprises: turning on electric heating only after a delay after starting the internal combustion engine, if a rate of temperature change in the heatable portion of the catalytic converter, being caused by heat contained in exhaust gases of the internal combustion

engine, is no greater than approximately a rate of temperature change attainable by electric heating.

5,588,292

EXHAUST GAS PURIFIER

Masahiro Hiraishi, Kyoto, and Shin-ichi Kuroda, Osaka, both of Japan, assignors to Shimadzu Corporation, Japan


Filed Jun. 20, 1995, Ser. No. 493,213

Claims priority, application Japan, Jun. 28, 1994, 6-146499

Int. Cl.⁶ F01N 3/28

U.S. Cl. 60—300

20 Claims



1. An exhaust gas purifier comprising: a honeycomb of an electrically non-conductive material, formed with a plurality of longitudinally extending throughholes and having end surfaces which are longitudinally opposite each other wherein an exhaust gas can flow through said through-holes from one to the other of said end surfaces; a conductive layer formed with an electrically conductive material on inner surfaces of parts of said honeycomb, said parts including at least a portion of each of said end surfaces and a selected portion of said honeycomb longitudinally extended between said end surfaces; a catalyst layer containing a catalyst, formed on inner surfaces of said honeycomb; heating means for heating said honeycomb by causing an electric current to pass through said conductive layer and thereby activating said catalyst.

5,588,293

FLUID ENERGY CONVERSION APPARATUS

Rikuro Nozu, 13-1, Chishirodai Higashi 4-chome, Wakaba-ku, Chiba-shi Chiba, Japan

PCT No. PCT/JP92/01365, § 371 Date Jun. 18, 1993, § 102(e) Date Jun. 18, 1993, PCT Pub. No. WO93/08375, PCT Pub. Date Apr. 29, 1993

PCT Filed Oct. 21, 1992, Ser. No. 81,288


Claims priority, application Japan, Oct. 21, 1991, 3-336386

Int. Cl.⁶ F16D 31/02

U.S. Cl. 60—398

6 Claims

1. A fluid energy conversion apparatus, comprising: a fluid path assembly including an outside guide assembly provided with a cylindrical wall inside surface at a principal portion of an inside wall thereof; at least one inside guide assembly having an outside surface formed in a shape of rotation symmetry arranged symmetrically on the central axis of said cylindrical wall inside surface; a cylindrical partition wall which extends between said outside guide assembly and said inside guide assembly, with its central axis set on the central axis of said cylindrical wall inside surface, said cylindrical wall inside surface of said outside guide assembly and said cylindrical partition wall defining an annular outside path therebetween, the outside peripheral surface of said inside guide assembly and said cylindrical partition wall defining an annular inside path therebetween; and a plurality of support struts connecting said outside guide assembly, said inside guide assembly and said cylindrical partition wall;



- a first rotor shaft having a rotational central axis on the central axis of said cylindrical wall inside surface of said outside guide assembly, and rotatably supported on said fluid path assembly;
- a second rotor shaft arranged coaxially with and rotatably on said first rotor shaft;
- a first rotary member having a first annular hub located adjacent a first end portion of said inside guide assembly in the axial direction thereof and coaxially fixed on said first rotor shaft, and a plurality of first turbine rotor blades fixed on said first annular hub and radially protruding in said annular inside path;
- a second rotary member having a second annular hub located adjacent a second end portion of said inside guide assembly in the axial direction thereof, supported coaxially with and rotatably on said second rotor shaft and drivingly coupled with said second rotor shaft through an overdrive gearing; a first annular ring member having substantially the same radius as that of said cylindrical partition wall and supported on said second annular hub coaxially with said second rotor shaft by a plurality of support struts protruding into said annular inside path; a plurality of second turbine rotor blades each fixed on an outside surface of said first annular ring member and protruding radially into said annular outside path;
- first stator blades including a first row of a plurality of stator blades and a second row of a plurality of stator blades, each stator blade in said first row having a corresponding stator blade in said second row, each of said corresponding stator blades forming a pair of stator blades, each of said stator blades being fixed at one end thereof on said cylindrical wall inside surface of said outside guide assembly, with each pair of stator blades radially protruding into said outside path at both sides of said second turbine rotor blades in the direction of the central axis of said cylindrical wall inside surface at a substantially equal spacing in a circumferential direction of said cylindrical wall inside surface; and
- a fluid pressurizing-accelerating device including a casing means fixed on said inside guide assembly at the inside thereof and having a discharge port directed towards said first annular hub of said first rotary member, a rotor means located inside of said casing means and fixedly mounted on said second rotor shaft;
- said first annular hub of said first rotary member having in an outer peripheral edge portion on one side thereof a collector port for receiving a fluid from said discharge port of said fluid pressurizing-accelerating device; each of said first turbine rotor blades having a symmetrical airfoil blade section having a chord line existing in a plane normal to said first rotor shaft and a fluid exhaust path which is communicated at one end thereof with said collector port of said first annular hub and also communicates at the other end thereof with an exhaust nozzle formed in both sides of each of said first turbine rotor blades in a position adjacent to a trailing edge of each of said first turbine rotor blades; and

5,588,294

HYDROSTATIC TRANSMISSION

Shinya Sakakura, Ryota Ohashi, and Shigenori Sakikawa, all of Amagasaki, Japan, assignors to Kanzaki Kokyukoki Mfg. Co. Ltd., Japan


Filed Jul. 31, 1995, Ser. No. 508,395

Claims priority, application Japan, Sep. 13, 1994, 6-218611

Int. Cl.⁶ F16D 31/02; 39/00

U.S. Cl. 60—464

9 Claims



1. A hydrostatic transmission, comprising: a hydraulic motor; a hydraulic pump; a closed circuit having a low pressure side and a high pressure side for connecting said hydraulic pump and said hydraulic motor in fluid communication with each other, said closed circuit including a first side circuit and a second side circuit; a supply circuit for supplying oil to said closed circuit; wherein said first side circuit and said second side circuit each includes a valve casing; a check valve disposed within said valve casing, said check valve including a valve body and a bore formed within said valve body, said check valve allowing oil to be supplied only to the low pressure side of said closed circuit; a relief valve disposed opposite to said check valve within said valve casing, said relief valve including a relief spring, wherein high pressure within said closed circuit acts on said relief valve through said bore to thereby regulate pressure within said closed circuit, and a cover detachably mounted to one end of said valve casing.


5,588,295

TRI-STRIP MEMORY METAL ACTUATOR

Gregory R. Brotz, P.O. Box 1322, Sheboygan, Wis. 53081
Continuation-in-part of Ser. No. 349,793, Dec. 6, 1994, which
is a continuation-in-part of Ser. No. 921,631, Jul. 30, 1992,
abandoned. This application Sep. 22, 1995, Ser. No. 532,352
Int. Cl.⁶ F01B 29/10

U.S. Cl. 60—528

2 Claims



1. An actuator, comprising:

- a first arcuate strip of memory metal having electrically conductive properties, said first arcuate strip having a convex side and a concave side;
- a second arcuate strip of memory metal having electrically conductive properties, said second arcuate strip having a convex side and a concave side; and
- a straight central strip of material having electrically conductive properties, said central strip being composed of a material dissimilar from that of said first and second arcuate strips; said central strip having a first side and a second side, said convex side of said first and second arcuate strips, when in its memory shape state, being attached to said first side of said central strip and forms a first junction with said central strip, said convex side of said second arcuate strip being attached to said second side of said central strip and forms a second junction with said central strip, so that said first and second arcuate strips clad, respectively, on said first and second sides of said central strip form a Peltier junction whereby passing a current through said strips of said actuator causes one of said junctions to heat and the other junction to cool and become amorphous, malleable and formable while said arcuate strip forming said junction that heats crystallizes and assumes its original arcuate shape thereby causing said actuator to bend and assume that arcuate shape, said actuator when the direction of said current is reversed bending in the opposite direction and assuming the arcuate shape of the other arcuate strip.

5,588,296

FUSION HEAT RECOVERY AND COMBUSTION GASES FILTERING SYSTEM WITH ELECTRIC POWER PRODUCTION

Antonio N. Aparici, Villafames, Spain, assignor to Colorohbia Espana, S.A., Villafames, Spain


Filed Dec. 20, 1994, Ser. No. 359,906

Claims priority, application Spain, Dec. 20, 1993, 9302634
Int. Cl.⁶ F01K 25/00

U.S. Cl. 60—671

3 Claims

1. A fusion heat recovery and combustion gases filtering system



with electric power production, applicable to a ceramic enamelling

plant and the like having a plurality of ovens (1), the system comprising a plurality of operative filter units (3), each operative filtering unit (3) of said plurality including a filter (5), an input heat exchanger (4) receiving fumes from a respective oven to cool the fumes down to an appropriate temperature for filtering the fumes in said filter, said filter being selected from a group consisting of a textile bag and a cap filter in which a powder enamel is recovered to be sent back to the respective oven (1) and hence recycled; a heat transmitting circuit (8) coupled to input exchangers (4) of all operating filtering units (3) of said ovens to receive hot heat transmission fluid from and send cooled heat transmission fluid to said input heat exchangers (4); and an organic cycle power plant (10), the operative filtering units (3) cooperating with the respective ovens (1) having input heat exchangers (4) thereof connected in parallel to said heat transmitting circuit (8) wherein a second exchanger (9) is provided that works as an output exchanger for transmitting heat received from said hot heat transmission fluid from said input heat exchangers (4) and absorbed thereby to said organic cycle power plant (10) which generates electric power.

5,588,297

THERMAL POWER GENERATOR


Haruo Uehara, and Yasuyuki Ikegami, both of Saga, Japan,
assignors to Saga University, Saga, Japan

Filed Jun. 7, 1994, Ser. No. 255,968

Claims priority, application Japan, Sep. 22, 1993, 5-236432
Int. Cl.⁶ F01K 25/06

U.S. Cl. 60—673

6 Claims



2. A thermal power generator comprising:

- a high heat source pump supplying a high heat source fluid;
- first and second cold working fluid pumps each pumping a cold working fluid;
- an evaporator receiving the high heat source fluid from said high heat source pump, and a warmed working fluid, the high heat source fluid being heat-exchanged with the warmed working fluid to form a vapor-liquid working fluid;
- a liquid-vapor separator connected to said evaporator and receiving the vapor-liquid working fluid therefrom, said liquid-vapor separator separating the vapor-liquid working fluid into a vapor working fluid and a liquid working fluid;
- a turbine and generator, said turbine being connected to said liquid-vapor separator and receiving the vapor working fluid therefrom, said turbine discharging the vapor working fluid received therein through two separate branches;
- a heater connected to said turbine using one of the branches, and receiving a portion of the vapor working fluid discharged from said turbine, said heater further receiving the cold-working fluid from said second cold working fluid pump, the vapor working fluid being heat-exchanged with the cold working fluid to warm the cold working fluid, and cool and condense the vapor working fluid, said heater discharging the working fluids received therein;
- means for storing and mixing the working fluids discharged from said heater to form a stored working fluid, and supplying the stored working fluid to said first cold working fluid pump;

a regenerator receiving the liquid working fluid from said separator, and the cold working fluid from said first cold working fluid pump, said regenerator heat-exchanging the liquid working fluid with the cold-working fluid to change the liquid working fluid into a regenerated working fluid, and the cold working fluid into the warmed working fluid, the warmed working fluid being discharged to said evaporator;

an absorber connected to said turbine using the other one of the branches, and to said regenerator for heat-exchanging and mixing the regenerated working fluid with the remaining vapor working fluid received from said turbine;

a low heat source pump supplying a low heat source fluid; condensation means connected to said absorber, and receiving the low heat source fluid from said low heat source pump for forming the cold-working fluid;

a storage tank connected to said condensation means for storing the cold-working fluid; and

means for supplying the cold working fluid from said storage tank to said second cold working fluid pump.

5,588,298

SUPPLYING HEAT TO AN EXTERNALLY FIRED POWER SYSTEM


Alexander I. Kalina, Hillsborough, and Mark D. Mirolli, Hayward, both of Calif., assignors to Exergy, Inc., Hayward, Calif.

Filed Oct. 20, 1995, Ser. No. 546,419

Int. Cl.⁶ F01K 13/00

U.S. Cl. 60—676

22 Claims



1. A method for supplying heat to an externally fired power system that includes the steps of:

- supplying a first stream of air and a first portion of total amount of combustion fuel to a first combustion zone,
- combusting said first portion of fuel in said first combustion zone to form a first flue gas stream,
- transferring heat from said first combustion zone to a first working fluid stream from said externally fired power system in first heat exchanger conduits located within said first combustion zone, an amount of fuel and air supplied to the first combustion zone being adjusted to control the first combustion zone temperature to a first predetermined value,
- supplying said first flue gas stream, a second stream of air, and a second portion of the total amount of combustion fuel to a second combustion zone,
- combusting said second portion of fuel in said second combustion zone to form a second flue gas stream, and
- transferring heat from said second combustion zone to a second working fluid stream from said externally fired power system in second heat exchanger conduits exposed located within said second combustion zone, said second working fluid stream being independent of said first working fluid stream, an amount of fuel and air supplied to the second combustion

zone being adjusted to control the second combustion zone temperature to a second predetermined value.

5,588,299

ELECTROSTATIC FUEL INJECTOR BODY WITH IGNITER ELECTRODES FORMED IN THE HOUSING

Dennis M. DeFreitas, Oxford, N.Y., assignor to Simmonds Precision Engine Systems, Inc., Akron, Ohio


Division of Ser. No. 67,652, May 26, 1993, Pat. No. 5,515,681.

This application Jun. 6, 1995, Ser. No. 470,521

Int. Cl.⁶ F02C 7/266

U.S. Cl. 60—740

18 Claims



1. A flame injector for initiating combustion of a main air/fuel supply to a combustor, comprising: a housing having a body with an orifice at an end thereof; an electrostatic nozzle connectable to a fuel supply, said nozzle disposed in said housing and that produces an electrostatically atomized fuel spray into said orifice; and an igniter disposed at said orifice to ignite said electrostatically atomized fuel spray; said igniter comprises two electrodes formed in said housing about an external surface of said body that defines said orifice, said electrodes being electrically insulated from each other.

5,588,300

THERMOELECTRIC REFRIGERATION SYSTEM WITH FLEXIBLE HEATCONDUCTING ELEMENT

Stefan Larsson, Sjömansgatan 17 D, Göteborg, Sweden, and
Christer Tennstedt, Smedjegatan 14, Gävle, Sweden

PCT No. PCT/SE92/00687, § 371 Date Apr. 1, 1994, § 102(e)

Date Apr. 1, 1994, PCT Pub. No. WO93/07426, PCT Pub.

Date Apr. 15, 1993

PCT Filed Oct. 2, 1992, Ser. No. 211,396


Claims priority, application Sweden, Oct. 4, 1991, 9102875

Int. Cl.⁶ F25B 21/02

U.S. Cl. 62—3.61

10 Claims

1. A refrigeration device for use on a boat comprising a room for keeping objects, a thermo-electric cooling element having a first end connected by a first heat conducting element to said room, and a second end connected to a second heat conducting element that is adapted to be thermally coupled with water surrounding the boat for exchange of heat therewith and wherein at least one of the heat conducting elements includes a flexible heat conducting element formed by a plurality of flexible thin wires of a material with a high thermal conductivity, and further comprising a first thermostat means for detecting the temperature in said room and a second thermostat means arranged to detect the temperature of the second heat conducting element at a portion of the element that connects to said thermo-electric cooling element and regulation means for regulating operation of the thermo-electric cooling element in response to said detected temperature information and temperature differences between said first and second thermostat means.



5,588,301

AIR SCOOP AND METHOD OF USE WITH ROOF MOUNTED VEHICLE AIR CONDITIONER


Gerald J. Deroche, Sr., 231 Saint Anthony St., Luling, La. 70070

Filed Jul. 24, 1995, Ser. No. 506,399

Int. Cl.⁶ B60H 1/32

U.S. Cl. 62—61

4 Claims



1. A method of increasing the cooling effect of roof mounted air conditioners of the type having a condenser air intake located on a rear sidewall of said air conditioner, said method comprising the steps of:

- 1) providing a scoop member having an inlet and an outlet aperture connected via a conduit having between a seventy and a one-hundred-ten degree bend therein, said outlet aperture having a length measuring between seventy and one-hundred-twenty percent of a length of said condenser air intake; and
- 2) securing said scoop member to said air conditioner in a manner such that said inlet aperture of said scoop member is directed toward a front of said air conditioner and said outlet aperture is directed toward said condenser air intake.

5,588,302

CAR AIR CONDITIONER

Yoshitaka Suzuki; Masako Kondo, both of Wakoh; Takashi Endo; Toshihiro Zama, both of Yamato; Yuji Shimoda, and Hiroshi Takata, both of Yokohama, all of Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, and Stanley Electric Co., Ltd.

Filed May 22, 1995, Ser. No. 445,923


Claims priority, application Japan, May 23, 1994, 6-130851

Int. Cl.⁶ B60H 1/00

U.S. Cl. 62—161

1 Claim

1. A car air conditioner comprising:



a D flip-flop circuit having a reset terminal, a clock terminal and an inverted output terminal, an outlet vent selection switch having a defroster contact, a flow rate control switch having a compressor contact for generating an L-logical value when closed, and a push-on type AC switch,

characterized in that said AC switch is urged by the L-logical value generated when said compressor contact of said flow rate control switch is closed and at the same time connected to the clock terminal of said D flip-flop circuit by way of a rise shaping circuit, that the defroster contact of said outlet vent selection switch is connected to said reset terminal of said D flip-flop circuit by way of a pulse shaping circuit for generating a pulse when said defroster contact is selected and that the inverted output terminal of said D flip-flop circuit is connected to an AC relay by way of a NOR-gate for calculating the logical sum of the L-logical values generated when said compressor contact is closed.

5,588,303

ARMORED VEHICLE SURFACE COOLING SYSTEM


Jeffery S. Parks, 21727 Harper Lake Ave., St. Clair Shores, Mich. 48080

Filed Aug. 22, 1995, Ser. No. 521,378

Int. Cl.⁶ F28D 3/00; F02M 23/14

U.S. Cl. 62—171

9 Claims



1. A semi-passive cooling system for an armored vehicle, comprising: an intermittent pressure source on the vehicle; means for storing pressurized fluid from the pressure source, the storing means comprising of a vessel downstream of the pressure source; a first valve connected between the pressure source and the vessel; first means to open the first valve in response to a predetermined pressure fall in the vessel; a reservoir containing water; a second valve connected between the vessel and the reservoir; means for stabilizing pressure in the reservoir at a pressure lower than a pressure in the vessel, the stabilizing means comprising:

including means to actuate the second valve in response to a predetermined pressure level in the reservoir; a sheet of water-absorbent, wicking skin on an exterior zone of the vehicle; means for causing releasable mechanical adhesion between the sheet and the zone; means for feeding water from the reservoir to the sheet; the feeding means including a third valve; means for supplying power to the third valve; means attached to the sheet for distributing water from the feeding means throughout the sheet; a releasable fluid connection between the feeding means and the distributing means; a heat sensor between the sheet and the zone; a switch between the supplying means and the third valve, the switch responsive to a signal from the heat sensor.

5,588,305

AIR CONDITIONING SYSTEM FOR A VEHICLE

Hwan-Oh Sim, Kyungsangnam-Do, Rep. of Korea, assignor to Hyundai Motor Company, Ltd., Seoul, Rep. of Korea


Filed Jun. 2, 1995, Ser. No. 458,873

Claims priority, application Rep. of Korea, Jun. 3, 1994, 94-12955

Int. Cl.⁶ F25D 17/06

U.S. Cl. 62—419

5 Claims



1. An air conditioning system for a vehicle, said air conditioning system comprising:

- a unit case;
- a pair of blow fans and corresponding blow motors disposed within said unit case;
- an evaporator disposed at a forward space of said unit case and at an exhaust side of said pair of blow fans;
- an upper blow case and a lower blow case disposed around each of said pair of blow fans, respectively, said lower blow case including an initial semispherical protrusion formed therein and said upper blow case including an arcuate portion complementary in shape to the semispherical protrusion;
- an air inlet disposed at a lower space of each of said pair of blow fans and formed within said lower blow case for effectively intaking the fresh air therethrough and directing the intake air vertically at said pair of blow fans; and
- an air outlet disposed at a side of said evaporator opposite to said pair of blow fans, whereby the air conditioning system provides a clean condition since the semispherical protrusion prevents dust from settling on a floor surface of the lower blow case, and effectively supplies fresh air through the air inlet.

5,588,306

PROCESS FOR OBTAINING AN ETHANE-RICH FRACTION FOR REFILLING AN ETHANE-CONTAINING REFRIGERANT CIRCUIT OF A PROCESS FOR LIQUEFACTION OF A HYDROCARBON-RICH FRACTION

Hans Schmidt, Wolfratshausen, Germany, assignor to Linde Aktiengesellschaft, Germany

Filed Nov. 9, 1995, Ser. No. 556,191


Claims priority, application Germany, Nov. 11, 1994, 44 40 407.7

Int. Cl.⁶ F25J 3/00

U.S. Cl. 62—614

17 Claims

1. A process for obtaining an ethane-rich fraction and refilling a refrigerant circuit for liquefaction of a hydrocarbon-rich fraction, said process comprising: cooling and liquefying a hydrocarbon-rich fraction by heat exchange against an ethane-containing refrigerant circulated in a refrigerant circuit; removing a partial stream of liquefied hydrocarbon-rich fraction and supplying said partial stream to a C₁/C₂/C₃ separation column; withdrawing an ethane-rich fraction from said C₁/C₂/C₃ separation column; and optionally after intermediate storage in a buffer tank, introducing said ethane-rich fraction to said refrigerant circuit.



5,588,307

PROCESS FOR LIQUEFACTION OF A PRESSURIZED HYDROCARBON-RICH FRACTION

Hans Schmidt, Wolftrathausen, Germany, assignor to Linde Aktiengesellschaft, Germany


Filed Nov. 9, 1995, Ser. No. 556,192

Claims priority, application Germany, Nov. 11, 1994, 44 40 406.9

Int. Cl.⁶ F25J 1/00

U.S. Cl. 62—614

21 Claims



1. A process for liquefaction of a pressurized gas stream containing hydrocarbons comprising:

- cooling and liquefying a pressurized hydrocarbon-rich gas stream by heat exchange with process streams to be heated,
 - expanding the resultant liquefied stream by means of at least one expansion means into at least one storage tank, and
 - removing flash gas/boil-off gas stream from said at least one storage tank and compressing said flash gas/boil-off gas stream in at least one compression stage,
- wherein throughput of said flash gas/boil-off gas stream in said at least one compression stage is kept constant by controlling the position of said at least one expansion valve or expansion turbine by an FIC controller,
- whereby pressure immediately downstream of said at least one expansion means is maintained substantially constant.

RECOMPRESSION CYCLE FOR RECOVERY OF NATURAL GAS LIQUIDS


Tamara L. Daugherty, Allentown, and Christopher F. Harris, Old Zionsville, both of Pa., assignors to Air Products And Chemicals, Inc., Allentown, Pa.

Filed Aug. 21, 1995, Ser. No. 517,524

Int. Cl.⁶ F25J 3/02

U.S. Cl. 62—622

11 Claims



1. A method for the recovery of hydrocarbons heavier than methane from mixtures of methane and said hydrocarbons which comprises:

- (a) cooling and partially liquefying a compressed natural gas feed stream containing methane and said hydrocarbons;
- (b) separating the resulting partially condensed feed stream into a methane-rich vapor and a first liquid;
- (c) introducing said first liquid into a stripping column which operates at or below the pressure of said partially condensed feed stream;
- (d) recovering from said stripping column a methane-rich overhead vapor and a stripper bottoms liquid rich in said hydrocarbons heavier than methane; and
- (e) expanding said stripper bottoms liquid and vaporizing the resulting expanded stream by indirect heat exchange with said compressed natural gas feed stream, thereby providing at least a portion of the cooling for said compressed natural gas feed stream in step (a) and yielding a vaporized stripper bottoms stream rich in said hydrocarbons heavier than methane.

5,588,309

EARRING BACK ADAPTER


Joseph J. Chioffe, 2710 Neaton Ct., Wellington, Fla. 33414

Filed Jul. 5, 1995, Ser. No. 498,137

Int. Cl.⁶ A44C 7/00

U.S. Cl. 63—12

1 Claim



1. An earring back adapter comprising:

- a first ornament holder having a friction post;
- a back clutch with a central opening to accommodate and hold said friction post of said first ornament holder;
- a back clutch adapter having a central opening through which said friction post of said first ornament holder may pass, said back clutch adapter having a base portion, a top disk and a

central stem that define a channel, and said top disk of said back clutch adapter having a depressed receiving area for frictional engagement and securement of said back clutch;

- a bridge consisting of a bent spring wire having a U-shape and long ends of said bent spring wire passing through said channel defined in said back clutch adapter, and said back clutch adapter being moveable along said spring wire of said bridge mechanism, bottom ends of said bent spring wire being bent outward to define feet; and,

- a second ornament holder connected to said ends of said bent spring wire of said bridge mechanism, wherein said feet at the bottoms of said bent spring wire are held under tension within openings in said second ornament holder.

5,588,310

JEWELRY WITH CHANGEABLE ORNAMENTATION


Danny S. Lai, New York, N.Y., assignor to Gramercy Enterprises (U.S.A.) Corp., New York, N.Y.

Filed Aug. 18, 1995, Ser. No. 516,131

Int. Cl.⁶ A44C 9/00

U.S. Cl. 63—15

6 Claims



1. An item of jewelry with changeable ornamentation, comprising:

- a body portion including an opening therein, two vertical slots at opposite sides of said opening, and two platform members; and

- an ornament piece having a plurality of display surfaces including a first display surface on one side thereof and a second display surface on another side thereof, said ornament piece being rotatably mounted in said body portion such that said ornament piece is rotatable between a first display position in which said first display surface is displayed through said opening in said body portion and a second display position in which said second display surface is displayed through said opening in said body portion, said ornament piece including two pins extending from opposite sides thereof defining an axis about which said ornament piece is rotatable, said pins being rotatably and slidably mounted in said slots of said body portion,

- wherein said ornament piece includes two locking projections extending therefrom adapted to engage said platform members of said body portion to releasably lock said ornament piece in one of said first and second display positions and thereby restrain said ornament piece from movement with respect to said body portion, and

- wherein said locking projections or said platform members or both are resiliently deformable such that said locking projections can be forced out of engagement with said platform members to free said ornament piece for sliding movement with respect to said body portion such that said ornament piece can be slidably moved away from said opening to enable said platform members and said projections to be sufficiently spaced from each other to enable generally free rotation of said ornament piece to change display positions.

5,588,311

CONTROL METHOD FOR A CARRIER OF A KNITTING MACHINE AND ITS APPARATUS

Takeshi Kiribuchi, Wakayama, Japan, assignor to Shima Seiki Manufacturing Ltd., Wakayama, Japan


Filed Oct. 30, 1995, Ser. No. 550,099

Claims priority, application Japan, Oct. 31, 1994, 6-292443

Int. Cl.⁶ D04B 15/56

U.S. Cl. 66—60 R

6 Claims



1. A control method for a carrier of a knitting machine, wherein the knitting machine includes at least a carriage for driving the needles of at least a needle bed and at least a carrier for feeding yarn to the needle bed, and wherein the carriage is driven by a first servo motor and the carrier is driven to travel on a carrier rail by a second servo motor, the method comprising figuring a pin of a carrier catching apparatus connected to the carriage configured to engage with the carrier so as to catch the carrier by the carriage and providing a torque limiting means coupled to said second servo motor such that, during the catching, an output torque of the second servo motor is limited by the torque limiting means.

5,588,312

DRIVING APPARATUS FOR NEEDLES OF KNITTING MACHINE

Seishiro Hashimoto, Ishikawa-ken, Japan, assignor to Tsudakoma Kogyo Kabushiki Kaisha, and Kyowa Denki Kogyo Kabushiki Kaisha, both of Japan


Filed Dec. 8, 1995, Ser. No. 569,493

Claims priority, application Japan, Dec. 14, 1994, 6-332358

Int. Cl.⁶ D04B 15/00

U.S. Cl. 66—75.2

7 Claims



1. A driving apparatus for needle of a knitting machine, comprising a linear motor for reciprocally moving said needle, said linear motor including:

- a pair of stator assemblies opposed to each other with a space left therebetween in the horizontal direction, each of stator assemblies having first magnet means thereon;

a moving assembly having second magnet means and disposed vertically between said stator assemblies so as to move in a direction of movement of the needle;
coupling means for supporting said moving assembly on at least one of said stator assemblies at a location either above or below a position at which said second magnet means is arranged; and
a position sensor for detecting a position of said moving assembly with respect to said stator assemblies.

5,588,313


AUTOMATIC WASHING MACHINE FITTED FOR DRYING

Gerald Hildebrand, Berlin, Germany, assignor to Bosch-Siemens Hausgeraete GmbH, Munich, Germany
Filed Oct. 13, 1995, Ser. No. 542,671
Claims priority, application Germany, Oct. 13, 1994, 44 36 673.6

Int. Cl.⁶ D06F 25/00; 39/02

U.S. Cl. 68—17 R

13 Claims



1. An automatic front-loading washing machine, comprising:
a tub having a lower portion, a lowest point and a fill opening with an air inlet neck;
a tub drain connected to said lowest point of said tub;
a detergent dispenser having a multiplicity of chambers;
a detergent supply line leading into said lower portion of said tub;
a closed air recirculation circuit being associated with said tub for drying and including a waste air conduit leading out of said tub and having a condensation device, a blower, a heating conduit, and an air inlet conduit opening into said air inlet neck to said fill opening of said tub;
said waste air conduit and said detergent supply line being one component; and
dehumidified waste air being carried outside said chambers through said detergent dispenser to said blower.

5,588,314

SECURITY GATE LOCK ASSEMBLY

Anthony D. Knezovich, P.O. Box 1166, Rock Spring, Wyo. 82902


Filed Dec. 27, 1995, Ser. No. 580,437

Int. Cl.⁶ E05B 67/38

U.S. Cl. 70—56

14 Claims

1. A gate lock assembly adapted for releasably locking a gate to a fixed vertical support comprising:
a bolt receiver for being fixed to one of said gate and said support; and
a locking bolt assembly for being mounted on the other of said gate and said support including:
(a) a fixed mounting tube;



(b) a slidable locking bolt extending through said mounting tube for slidable movement between an extended locking position in which one end of said locking bolt is disposed in said receiver and a retracted, unlocked position in which said one end is removed from said receiver;
(c) a locking wedge extending through aligned slots in said mounting tube and said locking bolt when said locking bolt is in the extended position; and
(d) a locking member for releasably engaging said wedge when said wedge is positioned in said aligned slots whereby when said locking member is locked said wedge is restrained against movement through said aligned slots and said locking bolt is retained in the extended locking position.

5,588,315

SAFETY DEVICE FOR A BOX


Bertil Holmgren, Vellinge, Sweden, assignor to M W Trading APS, Denmark
PCT No. PCT/SE93/00241, § 371 Date Sep. 22, 1994, § 102(e) Date Sep. 22, 1994, PCT Pub. No. WO93/19268, PCT Pub. Date Sep. 30, 1993

PCT Filed Mar. 23, 1993, Ser. No. 307,748

Claims priority, application Sweden, Mar. 24, 1992, 9200902
Int. Cl.⁶ E05B 65/00

U.S. Cl. 70—57.1

6 Claims



1. A safety device for a box, comprising:
a frame, said frame being adapted to conform to dimensions of the box, said frame including an insert opening for inserting the box in the frame;
a blocking element for blocking the insert opening, the blocking element being movable between a first engaged position, where the insert opening is blocked, and a second disengaged position where the insert opening is not blocked;
means for slidably and pivotally mounting the blocking element to said frame, said mounting means being connected to said frame;
restraining means for preventing pivotal movement of the blocking element when the blocking element is in the first engaged position, the restraining means being connected to the frame;
a latch operatively connected to the blocking element for selectively releasing the blocking element, the latch being movable between a first position where the blocking element cannot be displaced and remains engaged, whereby the insert opening is blocked, and a second position where the blocking element can be displaced and disengaged, whereby the insert opening is unblocked; and

wherein said latch comprises:

- a spring blade fixedly attached at one end thereof to the blocking element; and
- a shoulder on said frame, said spring blade engaging said shoulder in said first position thereof to prevent sliding motion of said blocking element.

5,588,316

LOCKING DEVICE FOR SELECTIVELY PREVENTING ACCESS TO THE VALVE HANDLES OF A DOMESTIC WATER TAP


Steven Jones, 96, Domaine Montaubois, R.R. 1, Mont Rolland, J0R 1G0, Canada

Filed Apr. 4, 1995, Ser. No. 422,086

Int. Cl.⁶ F16K 35/10

U.S. Cl. 70—178

5 Claims



1. A locking device for selectively preventing access to the valve handles of a domestic water tap, said locking device comprising:
a pair of substantially hollow handle enclosing components, each one of said handle enclosing components having a substantially concave-shaped wall, each one of said substantially concave-shaped walls defining a peripheral edge, each one of said peripheral edges defining an aperture, said handle enclosing components being positioned so that said apertures face one another, each one of said substantially hollow handle enclosing components being configured and sized in order to receive one of said valve handles;
a pair of substantially rigid connecting rods, each one of said substantially rigid connecting rods extending substantially outwardly from one of said peripheral edges;
a locking means for releasably locking said substantially rigid connecting rods together.

5,588,317

METHOD AND APPARATUS FOR SEQUENTIALLY UNLOCKING COMPARTMENTS

James S. Bianco, 217 Brainard Rd., Enfield, Conn. 06082


Filed Feb. 9, 1995, Ser. No. 386,153

Int. Cl.⁶ E05B 53/00

U.S. Cl. 70—265

6 Claims

1. An apparatus for sequentially unlocking a series of locked compartments, comprising:
(a) means to unlock a first one of said locked compartments so that said first one of said locked compartments can be opened and then closed; and
(b) means to sense closing of said first one of said locked compartments and to automatically unlock a second one of said locked compartments in response to said closing of said first one of said locked compartments.



5,588,318

DOOR LOCK

Shelby M. Osborne, Lexington, Ky., assignor to FireKing International, Inc., Lexington, Ky.


Filed Jul. 23, 1992, Ser. No. 917,592

The portion of the term of this patent subsequent to Dec. 19, 2012, has been disclaimed.

Int. Cl.⁶ E05B 17/00

U.S. Cl. 70—469

7 Claims




1. A door lock device for selectively locking and unlocking a door, the door lock device comprising:
a door latch mechanism, a casing and an elongate lock bolt;
the door latch mechanism including a lock bolt abutment surface;
a casing having a lock bolt receiving channel with a lock bolt receiving aperture slidably receiving the lock bolt in the channel and further comprising biasing means for resiliently biasing the lock bolt in the channel toward the bolt-receiving aperture, the channel having a closed end with the biasing means being captured between the closed end and the lock bolt, the casing to be attached to a door with the bolt-receiving aperture facing the door latch mechanism;
the lock bolt having a projecting end with an abutment face at the projecting end thereof at an acute angle to the longitudinal axis of the lock bolt;
first bolt stop means cooperating with the abutment face of the lock bolt to limit sliding movement of the lock bolt toward the bolt-receiving aperture so that the lock bolt projects through the bolt-receiving aperture a predetermined distance defining a locking position of the lock bolt, the first bolt stop means comprises a shelf extending between one edge of the bolt-receiving aperture and one longitudinal side of the lock bolt-receiving channel; and
second bolt stop means selectively cooperating with the lock bolt when the lock bolt is in the locking position to prevent sliding movement of the lock bolt to an unlocking position, the second bolt stop means further comprising means defining a notch in the lock bolt, a pin movable into and out of the notch, and means for selectively moving the pin into and out of the notch;
the lock bolt slidably mounted within the casing for movement at an acute angle relative to the bolt abutment surface of the

door latch mechanism between a locking position whereat the projecting end of the lock bolt projects through the bolt-receiving aperture and into abutting relationship with the bolt abutment surface of the door latch mechanism, and an unlocking position whereat the lock bolt is retracted into the casing, the lock bolt being responsive to abutment by the lock bolt abutment surface of the door latch mechanism to retract into the casing.

5,588,319
METHOD AND APPARATUS FOR MAKING HEAT EXCHANGER FINS
Sabatino A. Bianchi, Bloomfield Hills, and Richard P. Stoyneff, Woodhaven, both of Mich., assignors to Livernois Research & Development Company, Dearborn, Mich.
Continuation-in-part of Ser. No. 170,720, Dec. 21, 1993, abandoned. This application Nov. 7, 1995, Ser. No. 554,542
Int. Cl.⁶ B21D 37/01; 53/06

U.S. Cl. 72—186

9 Claims



1. A heat exchange fin manufacturing tool for forming a strip of fins with louvers comprising
fin forming rolls including stacked carbide plates having edges for rolling, cutting and forming fins with louvers that are cut and twisted so that they project from each fin, the tool having the characteristic of enhanced wear resistance, each edge having
a primary cutting surface for rolling, cutting, and forming fins before localized brittle fracture occurs during service life; and
a secondary cutting edge extending from the primary cutting edge as a result of localized brittle fracture after exposure to service conditions, the secondary cutting edge continually replacing the primary cutting edge in a self-rejuvenated manner with renewed rolling, cutting, and forming ability.

5,588,320
CORNERBEAD CRIMPING TOOL
Guy Lallier, 3837 Coco Plum, Circle, Karanda Village 3, Pompano Beach, Fla. 33063
Continuation-in-part of Ser. No. 513,987, Apr. 24, 1990, Pat. No. 5,209,097, which is a continuation-in-part of Ser. No. 448,737, Dec. 11, 1989, abandoned. This application Dec. 20, 1991, Ser. No. 811,782
Int. Cl.⁶ B23P 11/00

U.S. Cl. 72—325

19 Claims



1. A modular tool kit for crimping profiled cornerbead, wherein said cornerbead is available in a plurality of different profiles, comprising:


- (1) a housing module comprising a housing module body extending longitudinally from a front end to a back end and defining a longitudinal bore therethrough;
- (2) a plurality of interchangeable crimper modules, each of said crimper modules comprising:
 - (a) guide means, having a profiled guide surface complementary to a respective profiled cornerbead, for receiving the respective profiled cornerbead;
 - (b) attachment means for releasably securing guide means to said front end of said housing module;
 - (c) articulated crimper arm means, for crimping a respective profiled cornerbead received in the guide means wherein said crimper arm means comprises a pair of opposed crimper blades, pivotably mounted on said guide means and said crimper arm means, having an open position wherein said opposed blades are pivotably displaced apart from each other and having a crimping position wherein said crimper blades are pivotably displaced toward each other; and
 - (d) lug means, pivotably connected to said articulated crimper arm means and slidably receivable within the longitudinal bore of the housing module, for mounting said arms between said open and crimping positions;
- (3) a plurality of interchangeable power modules, each of said power modules comprising:
 - (a) a power module body;
 - (b) means for releasably securing said power module body to said back end of said housing module;
 - (c) actuator means, longitudinally displaceable relative to said power module body and releasably securable to said articulated crimper arm means; and
 - (d) transducer means for receiving energy input and for translating said energy input into longitudinal movement of said actuator means;

wherein said power module comprises a manual power module, wherein the actuator means of said manual power module comprises a rod, wherein the transducer means of said manual power module comprises a plunger slidably mounted within the manual power module and wherein energy is input to said manual power module by applying impact energy to said plunger.

5,588,321
SEGMENTED SCRIBING ROLLER FOR REFINING THE DOMAIN STRUCTURE OF ELECTRICAL STEELS BY LOCAL MECHANICAL DEFORMATION
Ralph E. Snyder, Export; Dominic A. Sorace, Sarver, and James G. Benford, Pittsburgh, all of Pa., assignors to Allegheny Ludlum Corporation, Pittsburgh, Pa.
Division of Ser. No. 378,891, Jan. 25, 1995, Pat. No. 5,463,889.
This application Jun. 26, 1995, Ser. No. 494,475
Int. Cl.⁶ B21B 1/22

U.S. Cl. 72—366.2

7 Claims




1. A method for refining the magnetic domain wall spacing of a grain-oriented silicon steel strip, said method including the steps of:

subjecting the strip to be scribed to a rolling contact pressure area formed while the strip is moving between a segmented scribing roller means and a rotatable anvil roll means; and imposing a uniform mechanical deformation transversely of said strip within said rolling contact pressure area by resilient support of scribing roller means segments clamped side-by-side and each having a series of outer peripheral surface projections arranged such that upon rotation about a rotational axis of the scribing roller means, the surface projections penetrate one surface of the strip independently of other scribing surface projections on other segments while the strip is supported by said anvil roll means.

5,588,322
UNIVERSAL SUPPORT AND POSITIONING STRUCTURE FOR TOOLS USED BY AN ELONGATE ELEMENT BENDING MACHINE
Carlo Passone, Vinovo, Italy, assignor to Bending Tooling S.R.L., Vinovo, Italy
PCT No. PCT/EP93/00813, § 371 Date Dec. 7, 1994, § 102(e) Date Dec. 7, 1994, PCT Pub. No. WO93/19864, PCT Pub. Date Oct. 14, 1993
PCT Filed Apr. 2, 1993, Ser. No. 313,299
Claims priority, application Italy, Apr. 6, 1992, TO92A0313
Int. Cl.⁶ B21D 7/02

U.S. Cl. 72—383

14 Claims




1. A universal support and positioning structure for tools useable by a machine for clamping and bending elongate elements such as tubes or profiled sections, including at least one base body and a support platform for said tools movably mounted on the base body and provided with means for rotating the support platform circumferentially with respect to a pivot fixed to the base body and characterized in that it further includes means for displacing the support platform radially with respect to the pivot contemporaneously to its rotation.

5,588,323
HAND-HELD RIVET BUCKING TOOL USING ENERGY DISSIPATIVE POLYMER
Craig Peterson, Milford, Mich., assignor to U.S. Industrial Tool and Supply, Plymouth, Mich.
Filed May 22, 1995, Ser. No. 447,198
Int. Cl.⁶ B21J 9/18

U.S. Cl. 72—465

6 Claims

1. A bucking tool, comprising:
a housing having an interior chamber;
an impact receiving member slidably received in said interior cavity, said member having a first end with an externally exposed impact-receiving surface and a second end terminating in a stem within said cavity; and




a cylindrical mass of visco-elastic energy dissipative polymer bonded around said stem, said mass defining an outer surface and circular edge oriented in opposed relation from said impact-receiving surface, said edge being retained within said interior cavity, causing said stem to move within and stretch polymer as to dissipate at least a portion of the vibration energy associated with an impact received by said member.

5,588,324
METHOD FOR DETERMINING THE LEVEL OF A SUBMERGED LAYER OF LIQUIFIED MATERIAL
Bernard E. Speranza, 9216 White Oak Ave., Munster, Ind. 46321
Filed Jun. 14, 1994, Ser. No. 259,782
Int. Cl.⁶ G01F 23/00

U.S. Cl. 73—290 R

20 Claims



1. For a vessel containing a first layer of liquified metal having an upper metal surface, said layer of liquified metal being submerged below a contiguous second layer of slag, a method for determining the level of said upper metal surface of said first layer of liquified metal, the method comprising:
providing a tube having first and second opposing tube ends;
providing a sacrificial cap to cover said first tube end;
inserting said first tube end through said slag layer into said first layer of liquified metal;
permitting said cap to substantially disintegrate after insertion into said layer of liquified metal, such that pressure pushes a portion of said liquified metal into said tube to an internal metal level substantially equal to the level of said upper metal surface of said first layer of liquified metal while preventing entry of said slag into said tube; and
utilizing a non-invasive level gauge to determine the level of said internal metal level of said portion in said tube without

further invasion into said metal, which internal metal level substantially corresponds to the level of said upper metal surface.

5,588,325

AUXILIARY POWER TAKE OFF ASSEMBLY AND METHOD


Norman E. Green, Harper, and Kenneth V. Sowers, Kingman, both of Kans., assignors to DewEze Manufacturing, Inc., Harper, Kans.

Filed May 30, 1995, Ser. No. 453,921

Int. Cl.⁶ B60K 25/02; F16H 7/02

U.S. Cl. 74—15.63

11 Claims



1. A PTO assembly for attachment of a rotary driven power unit to an OEM engine, said engine including a cooling fan and a fan belt which is attached between a drive pulley attached to an engine crankshaft and said cooling fan, said drive pulley including a sheave and a circular harmonic balancer positioned behind said sheave, said assembly comprising:

- a pulley ring shrink-fit over said harmonic balancer, said pulley ring being equipped with one or more external grooves to facilitate placement and retention of a drive belt thereon; and
- an auxiliary drive belt placed around said pulley ring and a sheave on said rotary driven power unit to thereby drive said power unit.

5,588,326

FEEDING DEVICE FOR PARTS TO BE MOUNTED

Hermann Ströter, Wuppertal; Frank Obst, Haan; Rolf Kamps, Wuppertal; Holger Reich, and Rainer Siegemund, both of Wuppertal, all of Germany, assignors to Stocko Fasteners GmbH, Wuppertal, Germany

Filed Mar. 15, 1995, Ser. No. 404,646

Claims priority, application Germany, Mar. 15, 1994, 44 08 694.6

Int. Cl.⁶ A41H 37/00; B21J 15/10


U.S. Cl. 74—50

17 Claims

1. A feeding device for feeding parts to be mounted to at least one of an upper tool and a lower tool of a mounting machine, said feeding device comprising:

- a carriage;
- at least one feeding push rod connected to said carriage;
- a center push crank, connected to said carriage, for moving in a reciprocating movement said carriage in a longitudinal direction of said at least one push rod to thereby move said at least one feeding push rod between an extended and a retracted position;

wherein said center push crank comprises a roller;



wherein said carriage comprises a curved guide slot; and wherein said roller is positioned and guided in said curved guide slot.

5,588,327

MULTIPLEXED HYDRAULIC CLUTCH CONTROL


Robert C. Downs, Clarkston; James K. Malquist, Troy; Larry T. Nitz, Rochester, and William L. Aldrich, III, Davisburg, all of Mich., assignors to Saturn Corporation, Troy, Mich.

Filed Sep. 25, 1995, Ser. No. 533,571

Int. Cl.⁶ F16H 61/08

U.S. Cl. 74—335

5 Claims



1. A method of overriding a hydraulic priority during a clutch-to-clutch shift in an automatic transmission having a first speed ratio controllably engaged by a first fluid operated friction device and a second speed ratio controllably engaged by a second fluid operated friction device, said first and second speed ratios having interposed therebetween a third speed ratio controllably engaged by a third fluid operated friction device, a controllable line pressure, a first solenoid fluid valve for supplying a first fluid pressure from said line pressure to one of the first and second fluid operated friction devices via a controllable multiplex valve, a second fluid valve for supplying a second fluid pressure from said line pressure to the third fluid operated friction device, a clutch priority valve hydraulically interposed between the first fluid valve and the multiplex valve responsive to a net fluid pressure comprising first and second fluid pressures effective to disengage the one of the fluid operated friction devices supplied by the first fluid pressure, the method comprising:

during a fill phase of one of the first and second fluid operated friction devices wherein said first and second solenoid fluid valves are simultaneously supplying fluid pressure to respective fluid operated friction devices, reducing the second fluid pressure to a value that maintains engagement of the third

clutch and that ensures the net fluid pressure does not cause the clutch priority valve to disengage the one of the fluid operated friction devices supplied by the first fluid pressure.

fourth intermediate gear engages the output gear at the rear, relative to the rotational direction of the input gear, sides of the tooth flanks of the output gear.

5,588,328

GEAR MECHANISM IMPROVED TO REMOVE BACKLASH

Ryo Nihei; Akihiro Terada, both of Fujiyoshida, and Hidenori Kurebayashi, Yamanashi, all of Japan, assignors to Fanuc Ltd., Yamanashi, Japan


Filed Jul. 7, 1995, Ser. No. 499,504

Claims priority, application Japan, Jul. 8, 1994, 6-157415

Int. Cl.⁶ F16H 1/00; 55/18

U.S. Cl. 74—409

8 Claims



1. A gear mechanism comprising:

- a housing;
- an input gear of helical gear supported by the housing for rotation in first and second rotational directions and adapted to be connected to a rotational power source, the input gear having tooth flanks;
- an output gear of a helical gear supported by the housing for rotation, the output gear having tooth flanks;
- a first gear train for transmitting the rotational power from the input gear to the output gear when the input gear rotates in the first rotational direction;
- a second gear train for transmitting the rotational power from the input gear to the output gear when the input gear rotates in the second rotational direction;
- the first gear train having a first spline shaft rotationally supported by the housing, first and second intermediate gears mounted on the first spline shaft slidably along the shaft, and a means for biasing first and second intermediate gears in the opposite directions along the shaft;
- the first intermediate gear being biased such that when the input gear rotates in the first rotational direction, the first intermediate gear engages the input gear at the front, relative to the rotational direction of the input gear, sides of the tooth flanks of the input gear;
- the second intermediate gear being biased such that when the output gear rotates in the first rotational direction, the second intermediate gear engages the output gear at the rear, relative to the rotational direction of the input gear, sides of the tooth flanks of the output gear;
- the second gear train having a second spline shaft rotationally supported by the housing; third and fourth intermediate gears mounted on the second spline shaft slidably along time shaft; and a means for biasing third and fourth intermediate gears in the opposite directions along the shaft;
- the third intermediate gear being biased such that when the input gear rotates in the second rotational direction, the third intermediate gear engages the input gear at the front, relative to the rotational direction of the input gear, sides of the tooth flanks of the input gear; and
- the fourth intermediate gear being biased such that when the output gear rotates in the second rotational direction, the

5,588,329

SNAP TOGETHER SHIFT KNOB CONSTRUCTION


Mitsuyuki Nedachi, 16-21 Ohsugi 1-chome, Edogawa-ku, Tokyo, Japan

Filed Feb. 9, 1995, Ser. No. 386,317

Int. Cl.⁶ B60K 23/00

U.S. Cl. 74—473 R

1 Claim



1. A mounting structure for connecting a knob to a shaft, comprising:

- a rotation preventing projection formed on a side of shaft;
- a first sleeve disposed on the shaft, said first sleeve having a groove for receiving said rotation preventing projection and for preventing relative rotation between the shaft and said first sleeve, said first sleeve having an annular shoulder portion from which first fastening clicks project in a spaced essentially parallel relationship with the shaft;
- means defining annular recess in the shaft;
- a second sleeve disposed on said shaft so as to seat on the annular shoulder, said second sleeve having second fastening clicks which engage in said annular recess and lock both said first and second sleeves axially in position on the shaft; and
- means defining recesses in the walls of a bore formed in the knob into which the first clicks can engage to lock the knob on the shaft.

5,588,330

GEAR SHIFTING DEVICE WITH LOCKING DISENGAGEABLE MECHANISM MANUALLY OPERATED BY A TOOL

Yoshimasa Kataumi, and Yoshihiro Takikawa, both of Shizuoka, Japan, assignors to Fujikiko Kabushiki Kaisha, Tokyo, Japan

Filed Mar. 13, 1995, Ser. No. 403,058

Claims priority, application Japan, Mar. 31, 1994, 6-063480


Int. Cl.⁶ B60K 17/00

U.S. Cl. 74—483 R

12 Claims

1. A gear shifting device comprising:


- a frame;
- a shifting lever provided on an underside thereof with a positioning pin and pivotally attached to said frame;
- a locking member pivotally attached to said frame for preventing said positioning pin from falling when said shifting lever is in a parking position;
- an actuator for operating said locking member; and
- a hand-operated locking disengageable mechanism including:
 - a disengaging member slidably attached to said frame for moving said locking member to a locking-release position where the positioning pin is not locked;



causes said screw driving member to rotate, which drives said drag member to move within said stroke, and which in turn drives the derailleur cable to cause the change of engagement of the derailleur to another predetermined gear;

(e) wherein one end of said rotary member is provided with a washer, said washer is connected to a spring member while thrusting against a cover plate, and said cover plate is connected to said fixing seat so as to enable said rotary member to be limited to a specific location of said fixing seat.

5,588,332
COLLAPSIBLE STEERING COLUMN ASSEMBLY
 Gregory T. Hedderly, Livonia, Mich., assignor to Ford Motor Company, Dearborn, Mich.
 Filed Mar. 31, 1995, Ser. No. 414,562
 Int. Cl.⁶ B62D 1/19
 U.S. Cl. 74-493 12 Claims




b) a core pin removably attached to said frame so as to oppose said disengaging member, said core pin being rotatable between a locked position and an unlocked position by aid of a tool;

c) a lid member removably attached to said frame so as to cover said core pin; and

d) urging means for urging said disengaging member toward said core pin,

wherein said core pin includes a cylindrical part, a flange part formed around said cylindrical part, and a pair of convex parts formed around said cylindrical part and under said flange part, and said core pin is provided inside said cylindrical part with an engagement groove for engaging with said tool, and wherein said flange part is provided with at least one notch which is so arranged as to face one of said convex parts.

5,588,331
ROTARY SHIFTER FOR BICYCLE
 Jack Huang, Tainan; Chung-Ping Chiang, Kaohsiung, and Chan-Hua Feng, Hsinchu, all of Taiwan, assignors to Industrial Technology Research Institute, Hsinchu Hsien, Taiwan
 Filed Mar. 21, 1995, Ser. No. 407,565
 Int. Cl.⁶ F16C 1/10; G05G 11/00
 U.S. Cl. 74-489 11 Claims



1. A rotary shifter for use with a bicycle for driving a derailleur cable to be engaged with a predetermined gear among a plurality of gears, comprising:


- (a) a fixing seat mounted on a handlebar of said bicycle;
- (b) a drag member for driving the derailleur cable to produce an extension thereof in response to a predetermined stroke exerted by a bicycle rider;
- (c) a limit member mounted on said fixing seat for limiting said drag member to move within said predetermined stroke; and
- (d) a rotary member which is mounted on said handlebar of said bicycle and is capable of rotating around an axial direction of said handlebar, said rotation of said rotary member enables a screw driving member to drive said drag member in axial movement, said screw driving member is mounted on said rotary member, such that a rotation of said rotary member

1. A collapsible steering column assembly for a vehicle, comprising:

- a main housing rigidly supported in the vehicle;
- a lower bearing retainer connected to said main housing;
- a lower steering column assembly rotatably supported with respect to said lower bearing retainer, normally axially fixed with respect to said lower bearing retainer, and including a collapsible intermediate shaft, said intermediate shaft being collapsible when said bearing retainer is not connected to said main housing; and
- a telescope housing telescopically moveable with respect to said main housing, and sufficiently engageable with said bearing retainer to disconnect said bearing retainer from said main housing when sufficient load is exerted on said telescope housing, whereby to allow collapse of said intermediate shaft.

5,588,333
LENGTH-ADJUSTING DEVICE FOR CONTROL CABLE
 Yoshiharu Kitamura, Aikawa-machi, Japan, assignor to NHK Spring Co. Ltd., Yokohama, and Uniflex, Inc., Ina, both of Japan
 Division of Ser. No. 41,480, Apr. 2, 1993, Pat. No. 5,435,202.
 This application Apr. 13, 1995, Ser. No. 422,303
 Claims priority, application Japan, Apr. 6, 1992, 29310; Jul. 24, 1994, 218405
 Int. Cl.⁶ F16C 1/10
 U.S. Cl. 74-502.4 1 Claim

1. In combination, a length-adjusting device for a control cable, comprising:



a stationary base member to which an outer cable or an inner cable of said control cable is fixedly secured, and into which an adjusting pipe, having formed and disposed thereon parallel latching teeth, is inserted and is movable axially thereof; an adjusting piece, having parallel pairs of similarly pitched locking teeth for engagement to and release from said latching teeth, which is movably inserted in a direction rectangular to the axis of said adjusting pipe and into an aperture in said stationary base member;

a resilient spring installed between said base member and said adjusting piece, said resilient spring biasing said locking teeth of said adjusting piece so as to engage with said latching teeth provided on said adjusting pipe; and


said length-adjusting device comprising a pair of projections provided on the outer sides of said adjusting piece;

a pair of guide grooves guiding said projections of said adjusting piece, provided on each of the inner sides of said stationary base member;

each of said guide grooves comprising a straight groove guiding said adjusting piece up and down, and an inclined groove continuously shaped along said straight groove; and

each of said inclined grooves comprising an inclined face, a slant face opposing said inclined face, and a vertical face downwardly shaped from said slant face.

5,588,334
CABLE CORE ADJUSTER WITH LOCK MEMBERS
 Jian G. Lu, Troy, and Ronald L. Beckmann, Rochester, both of Mich., assignors to General Motors Corporation, Detroit, Mich.
 Filed Apr. 27, 1995, Ser. No. 429,961
 Int. Cl.⁶ F16C 1/10
 U.S. Cl. 74-502.6 2 Claims




1. A cable adjustment mechanism comprising:

- a cable body member having a first toothed locking structure formed thereon;
- a cable core member having a second toothed locking structure formed thereon;
- a lock member for engaging both said first and second toothed locking structures to secure a positional relation between said cable body member and said cable core member; and

a cover member formed separately of said lock member and disposed on said cable core member for selectively overlapping said lock member to prevent disengagement of said lock member from said first and second toothed locking structures and including a top surface for covering said lock member and a bottom surface including two arm, each having tab means disposed thereon for selective engagement with shoulder means defined on said cable core member to secure said cover member in overlapping relationship with said lock member.

5,588,335
TORSION LOCK PARKING BRAKE ACTUATOR WITH PUSH DOWN RELEASE
 Daniel L. Strait, 11856 Silver Creek Dr., Apt. 1, Birch Run, Mich. 48415
 Filed Apr. 28, 1995, Ser. No. 430,859
 Int. Cl.⁶ G05G 5/06
 U.S. Cl. 74-512 5 Claims




1. A torsion lock parking brake actuator comprising:

- a frame that is adapted to be mounted on a support member;
- a transfer lever pivotally mounted on the frame for applying a parking brake responsive to rotation of the transfer lever;
- an operator lever pivotally mounted on the frame for rotating the transfer lever;
- a torsion lock operatively connected to the transfer lever for locking the transfer lever in a brake set position where the parking brakes are applied, and
- a torsion lock release mechanism operatively connected to the operator lever that engages the torsion lock when the transfer lever is in the brake set position to release the transfer lever responsive to rotation of the operator lever, said torsion lock release mechanism including:
- a sector ratchet that is attached the operator lever, and
- a lock pawl that is pivotally mounted on the frame that includes a tooth that is shaped to engage the teeth of the sector ratchet, and
- an arm that engages the torsion lock to release the transfer lever.

5,588,336
HANDLEBAR STEM COUPLING MODULE FOR A BICYCLE
 Chen-chang Chou, No. 9, Chingchuan Rd., Taya Hsiang, Taichung Hsien, Taiwan
 Filed Oct. 16, 1995, Ser. No. 543,304
 Int. Cl.⁶ B62K 21/18
 U.S. Cl. 74-551.1 2 Claims

1. A handlebar stem coupling module for a bicycle comprising a steerer tube, a handlebar stem having a compression connector formed on one distal end thereof and mounted around an outer wall of said steerer tube, a polygonal passage longitudinally defined



through an inner wall of said compression connector, an urging sleeve securely mounted between the outer wall of said steerer tube and the inner wall of said compression connector, a polygonal outer wall formed on said urging sleeve and received in said polygonal passage of said compression connector, a plurality of graduations formed on said polygonal outer wall of said urging sleeve, a circular hole vertically defined through an inner wall of said urging sleeve for receiving said steerer tube therein, and an elongated slit laterally and vertically defined in said urging sleeve and extending along a length thereof and communicating with said circular hole.

5,588,337


MOTOR VEHICLE STEERING COLUMN

Thomas J. Milton, Bay City, Mich., assignor to General Motors Corporation, Detroit, Mich.

Continuation-in-part of Ser. No. 340,999, Nov. 17, 1994, abandoned. This application Apr. 11, 1995, Ser. No. 420,162

Int. Cl.⁶ B62D 1/10

U.S. Cl. 74—552



1. A motor vehicle steering column including a steering shaft, a steering wheel having a hub at the center thereof, a cylindrical passage in said hub interrupted by a first pair of flat sides parallel to a longitudinal centerline of said cylindrical passage converging in a V-shape from a wide side of said cylindrical passage to a narrow side of said cylindrical passage, a cylindrical journal on said steering shaft interrupted by a second pair of flat sides parallel to a longitudinal centerline of said cylindrical journal converging in a V-shape corresponding to the V-shape of said first pair of flat sides of said cylindrical passage from a wide side of said cylindrical journal to a narrow side of said cylindrical journal,

said cylindrical journal being received in said cylindrical passage with said first pair of flat sides facing said second pair of flat sides, and means on said steering shaft and on said hub operative to induce lateral thrust between said hub and said steering shaft so that said first pair of flat sides is wedged between said second pair of flat sides and to positively prevent dislodgment of said cylindrical journal from said cylindrical passage.

characterized in that said means to induce lateral thrust between said hub and said steering shaft and to positively prevent dislodgment of said cylindrical journal from said cylindrical passage comprises:

- a lateral bore in said hub intersecting said cylindrical passage across said wide side thereof and including a first segment on a first side of said cylindrical passage and a second segment on an opposite second side of said cylindrical passage on a common centerline of said lateral bore with said first segment,
- a control rod in said lateral bore rotatable about said common centerline having a frustoconical body and a first end on one side of said frustoconical body in said first segment of said lateral bore and a second end on the other side of said frustoconical body journaled in said second segment of said lateral bore,

an internal screw thread in said first segment of said lateral bore, an external screw thread on said first end of said control rod engaging said internal screw thread and cooperating therewith to effect linear translation of said control rod in said lateral bore in the direction of said common centerline in response to rotation of said control rod, and

- a lateral notch in said first cylindrical journal across said wide side thereof registering with said lateral bore in said hub having a surface at an angle to said common centerline substantially equal to the cone angle of said frustoconical body of said control rod so that said frustoconical body and said surface of said lateral notch cooperate to convert linear translation of said control rod in the direction of said common centerline into lateral thrust of said hub relative to said steering shaft.

5,588,338

SNAP-IN PEDAL WITH END CAPS


James E. Carr, Waterford, and Mark A. Lindsey, Westland, both of Mich., assignors to General Motors Corporation, Detroit, Mich.

Continuation-in-part of Ser. No. 86,418, Jul. 2, 1993, Pat. No. 5,398,569. This application Nov. 30, 1994, Ser. No. 347,566

Int. Cl.⁶ G05G 1/14; F16C 11/06

U.S. Cl. 74—560

14 Claims



1. In a mounting for a control pedal on a motor vehicle for rotation about an axis, the combination comprising: a mounting bracket fixed relative to the vehicle and having first and second apertures defining the axis of rotation; the pedal having first and second bearings defining a pivot axis and a spring, wherein the first and second bearings are biased by the spring to axially outer positions and wherein the spring is compressible such that opposing forces on the bearings axially moves the bearings into axially compressed positions;

wherein the spring forces the bearings in the axially outer positions when the pedal is positioned so that the bearings are exterior of the bracket;

wherein the bracket forces the bearings in the axially compressed positions when the bearings are located within the bracket and not within the first and second apertures;

wherein the spring forces the bearings in the axially outer positions when the bearings are in the first and second apertures, whereby the pedal snaps into the bracket; and

a pair of pedal end caps disposed between the pedal and the bracket when the bearings are in the first and second apertures.

5,588,339

ADJUSTABLE STROKE DRIVE FOR A DISPLACEMENT PISTON PUMP

Viktor Dulger, Heidelberg, Germany, assignor to ProMinent Dosiertechnik GmbH, Heidelberg, Germany


Filed Aug. 4, 1994, Ser. No. 285,957

Claims priority, application Germany, Aug. 7, 1993, 43 26 621.5; Sep. 28, 1993, 43 32 947.0

Int. Cl.⁶ F16H 21/20

U.S. Cl. 74—836

12 Claims



12. A stroke drive for a displacement piston pump, having a drive shaft, a first driven eccentric, a push rod with a support therefor and a push element articulately connected to said push rod and being guided in a linear manner, a second eccentric supported on said first eccentric, the second eccentric being formed as a disc and being mounted on said first eccentric which has been formed as a crank journal, said disc carrying said push rod bearing at its circumference, the second eccentric being formed as a part of a cross-staff head coupling and means for connecting said push rod support to said second eccentric, an intermediate drive for coupling said eccentrics to each other and for conveying a synchronous rotation thereto, and an arrestable adjusting device for changing the relative position of the eccentricities of the eccentrics relative to each other, wherein the intermediate drive includes:

- a) a differential having a first input connected to said first eccentric, a second input connected to said adjusting device, and an output leading to said second eccentric, and
- b) a reduction drive between the output of the differential and said coupling and reducing the speed at a ratio of 2:1.

5,588,340

HAND HELD IMPLEMENT SHARPENING DEVICE


Dennis H. Hancock, Mt. Green, Utah, assignor to All Rite Products, Inc., Mt. Green, Utah

Filed Mar. 14, 1995, Ser. No. 404,169

Int. Cl.⁶ B24D 13/06

U.S. Cl. 76—82

17 Claims



1. An implement sharpening device comprising:

a body member having a handle end and an engagement end; a plate having a composition and engagement surface configuration useful for sharpening a steel blade, said plate being positioned at said engagement end and partially enclosed within said body member such that the engagement surface is exposed;

said plate having at least one notch therein, said notch being at least partially disposed within said body member such that portions of said body member extend into the notch so as to hold said plate in a substantially rigid position with respect to said body member;

a curved plurality of ridges disposed along said handle end thereby providing a finger grip;

a curved portion disposed along said handle end opposite said ridges thereby contouring to the palm of the hand of a user; a dished area disposed at the joining of said handle end and said engagement end thereby providing an area for placement of the thumb of a user; and

a raised ridge disposed along one side of said dished area so as to provide bracing for the thumb of a user.

5,588,341

FUSE EXTRACTION TOOL

Eiji Higuchi, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Japan


Filed Jun. 26, 1995, Ser. No. 494,826

Claims priority, application Japan, Jun. 30, 1994, 6-149096

Int. Cl.⁶ B25B 27/14

U.S. Cl. 81—3.8

14 Claims



1. A fuse extraction tool comprising an end portion having opposed resilient forks extending therefrom, said forks having free ends, and said free ends having opposed teeth for engagement with a blade type fuse, wherein said forks are divided from said end portion in the direction of said free ends so as to form two legs of each fork, the legs lying in a plane perpendicular to the plane of the forks, opposite legs of each fork being connected by respective link members which constitute said end portion, and the legs connected by respective link members being movable towards and away from each other, one of said link members having a projection to urge legs connected to the other link member apart such that

in use when the link members are urged together in a direction substantially perpendicular to the plane of said forks, the free ends of said forks are urged apart.


5,588,342 CORK PULLER FOR PULLING CORKS FROM A RANGE OF BOTTLE TOP SIZES

Dexter D. Ahlgren, and Valerie E. Ahlgren, both of P.O. Box 909, Boulder Creek, Calif. 95006

Filed May 24, 1995, Ser. No. 448,656
Int. Cl.⁶ B67B 7/04

U.S. Cl. 81—3.47

17 Claims



1. A cork pulling device comprising:
 - a bottle neck receiving seat having a central opening, the central opening defining a longitudinal axis of the device;
 - a first pair of links pivotally attached to the bottle neck receiving seat by pivotal connections;
 - a second pair of links having a curvilinear shape when viewed from along said longitudinal axis, the second pair of links pivotally attached to the first pair of links by pivotal connections;
 - a third pair of links pivotally attached to the second pair of links by pivotal connections;
 - a handle having a curvilinear shape attached to the third pair of links and mounted to pivot between a first position used in inserting the cork pulling device into a cork and a second position used in pulling the cork from a bottle, wherein in the first position, the curvilinear shape of the handle is aligned with the curvilinear shape of the second pair of links, and wherein in second position, the curvilinear shape of the handle is unaligned with the curvilinear shape of the second pair of links; and
 - a screw attached to the second pair of links at a central pivot and depending through the central opening of the bottle neck receiving seat.

5,588,343 HANDLE WITH IMPROVED GRIP ASSEMBLY FOR HAMMERS AND THE LIKE AND METHOD OF MAKING SAME


Howell B. Rust, Manchester, and Kenneth W. Hreha, Tullahoma, both of Tenn., assignors to The Stanley Works, New Britain, Conn.

Filed Sep. 15, 1994, Ser. No. 306,835
Int. Cl.⁶ B25G 1/01

U.S. Cl. 81—489

20 Claims

1. A handle for hammers and the like comprising:



- (a) an elongated core member having a tool engaging end and a grip end;
- (b) a synthetic resin sleeve on and securely interlocked with said core member adjacent said tool engaging end, said sleeve having a peripheral collar extending about its end disposed towards said grip end; and
- (c) a grip member of relatively resilient material extending about said core member from said grip end and having an end portion overlying and interlocked with said collar on said sleeve, said grip member being securely interlocked with said core member.


5,588,344 ELECTRIC SERVO MOTOR PUNCH PRESS RAM DRIVE

Victor L. Chun, Charlotte, N.C., assignor to Murata Machinery, Ltd., Kyoto, Japan

Filed Jun. 13, 1994, Ser. No. 261,052
Int. Cl.⁶ B26D 5/14

U.S. Cl. 83—13

10 Claims



8. A method of driving a ram of a punch press through a programmed punching operation comprising the steps of:
 - coupling a reversible electrical servo motor to a crankshaft having an eccentric journal, the journal receiving an upper end of a pitman arm which has a lower end coupled to said ram;
 - rotating the electrical servo motor under program control to cause the crankshaft to oscillate through a range of rotation corresponding to a ram punching stroke; wherein said crankshaft is oscillated through a range of movement through bottom dead center from a position partially rotated before bottom dead center to a position partially rotated past bottom dead center, corresponding to a punching stroke between a partially retracted hover height and a fully extended ram position.


5,588,345 FIN SHEET CONTROL APPARATUS FOR PRESS

Lawrence A. Franks, Sturgis, Mich.; Galen B. Harman, La Grange, Ind., and Herman Flint, Sturgis, Mich., assignors to Burr Oak Tool & Gauge Company, Sturgis, Mich.

Filed Nov. 22, 1993, Ser. No. 156,263
Int. Cl.⁶ B26D 5/22; 9/00; B65H 35/06

U.S. Cl. 83—95

11 Claims



7. A sheet metal working apparatus, comprising:
 - a sheet metal working press;
 - sheet metal supply means adapted to supply an elongated and flat strip of sheet metal stock to an inlet of said press and along a path of movement;
 - intermittent first drive means for effecting an intermittent movement of said strip of sheet metal stock relative to said press;
 - intermittent second drive means for effecting a metal working engagement of a tool means on said press with said strip of sheet metal stock during intervals of time between said intermittent movement of said strip of sheet metal stock to produce a continuous strip of finished sheet metal fin stock; and
 - wherein said sheet metal supply means includes a roll of sheet metal stock and support means for rotatably supporting said roll, and further includes, between said roll and said inlet, a means for forming and maintaining said strip of sheet metal stock into a generally upwardly opening, laterally extending, trough so that when said strip of sheet metal stock is moved into said inlet caused by said intermittent first drive means, said strip of sheet metal stock will be drawn from said trough rather than directly from said roll of sheet metal stock, said means for forming and maintaining said strip of sheet metal stock into said trough including wall means defining at least one upstanding wall surface oriented along a side of said trough adjacent said inlet and an air blowing means having an air outlet oriented above said trough and aiming air exiting said air outlet into said trough and at a sufficient volume to urge said strip of sheet metal stock into frictional sliding engagement with said upstanding wall surface so as to cause said strip of sheet metal stock to be kept under tension and free of wrinkling as said sheet metal stock is pulled into said inlet by said intermittent first drive means.

5,588,346 PNEUMATIC BOOSTER

Jean Pierre Gautier, Ulysse Verbo, both of Aulnay-Sous-Bois, and Miguel Perez Revilla, Argenteuil, all of France, assignors to AlliedSignal Europe Services Techniques, Drancy, France

PCT No. PCT/FR94/00536, § 371 Date May 20, 1994, § 102(e) Date May 20, 1994, PCT Pub. No. WO94/29152, PCT Pub. Date Dec. 22, 1994

PCT Filed May 6, 1994, Ser. No. 244,165

Claims priority, application France, Jun. 14, 1993, 93 07121

U.S. Cl. 91—369.002

6 Claims

1. A pneumatic brake booster including a casing having a piston with a hub, said hub having a tubular part a portion of which extends backwards and passes in a sealed fashion through said casing, said hub supporting a skirt and including an annular groove for receiving an internal peripheral bead of a rolling seal, said rolling seal defining a front chamber in said casing which is

permanently connected to a source of vacuum and a back chamber which is selectively connected to the front chamber and to the atmosphere in response to an input force applied by a front face of a plunger, on a reaction disk secured by a second face on a push rod, characterized in that said tubular part of the piston has a front end having a bead which penetrates into a peripheral groove formed on said hub, said tubular part being permanently connected to said hub by clipping.

5,588,347 HYDRAULIC AXIAL PISTON MACHINE WITH AN INCLINED PLATE

Hardy P. Jepsen, Nordborg, Denmark, assignor to Danfoss A/S, Nordborg, Denmark

PCT No. PCT/DK94/00021, § 371 Date Jun. 6, 1995, § 102(e) Date Jun. 6, 1995, PCT Pub. No. WO94/16224, PCT Pub. Date Jul. 21, 1994

PCT Filed Jan. 12, 1994, Ser. No. 464,689


Claims priority, application Germany, Jan. 18, 1993, 43 01

121.7

Int. Cl.⁶ F01B 3/00

U.S. Cl. 92—12.2

14 Claims



1. A hydraulic axial piston machine having a inclined plate on which a slider shoe of at least one piston slides on relative movement between a cylinder body receiving the piston and the inclined plate, and a pressure plate articulated on the cylinder body and holding the slider shoe in engagement with the inclined plate, and in which between the pressure plate and cylinder body there is arranged a bearing element with a bearing surface of plastic material which slides with low friction on a counterpart made of metal lying against the bearing surface.

5,588,348 BRAKE ACTUATOR WITH CENTERING DOME IN SERVICE CHAMBER

Ronald S. Plantan, and Henry T. Dangson, both of Charlotte, N.C., assignors to Indian Head Industries, Inc., Charlotte, N.C.


Filed Aug. 7, 1995, Ser. No. 512,022

Int. Cl.⁶ F01B 19/00; 31/00

U.S. Cl. 92—63

18 Claims

1. A combination for use in a service chamber of a spring brake actuator comprising:
 - a diaphragm having a central permanently deformed portion;
 - a push rod having a piston, said piston having a permanently deformed portion corresponding to the shape of the permanently deformed portion of said diaphragm; and



the cross-sectional shape of said permanently deformed portion of said piston and said diaphragm being generally frusto-conical, to correspond to the shape of a dome extending from a central housing into the service chamber.

5,588,349

SERVO WITH ENHANCED SAFETY


Jean-Pierre Gautier; Ulysse Verbo, both of Aulnay-Sous-Bois, and Maurice Gebauer, Sevran, all of France, assignors to AlliedSignal Europe Services Techniques, Drancy, France
PCT No. PCT/FR95/00029, § 371 Date Jan. 30, 1995, § 102(e)
Date Jan. 30, 1995, PCT Pub. No. WO95/21083, PCT Pub. Date Aug. 10, 1995

PCT Filed Jan. 10, 1995, Ser. No. 379,464

Claims priority, application France, Feb. 4, 1994, 94 01250
Int. Cl. F01B 11/02; F15B 9/10

U.S. Cl. 92—169.3

5 Claims



1. A pneumatic servo for brake boosting intended for motor vehicles having a rigid casing defined by first and second shells, said first and second shell being divided into at least two chambers by means of a flexible membrane, said first and second shells being joined together by at least first and second tie rods to define a sealed casing, said first and second tie rods being reacting to any force which tends to move said first and second shell apart, said first and second tie rods each being characterized by a cable which joins said first shell to said second shell together in an axial direction to maintain said sealed casing while being compressible to allow an external impact force applied to said first shell to be dissipated without being transferred into said second shell.

5,588,350


MANUFACTURE OF BANDED PISTONS

Richard A. Bowell, Sr., Huber Heights, Ohio, assignor to Freudenberg-NOK General Partnership, Plymouth, Mich.
Continuation-in-part of Ser. No. 236,019, May 13, 1994, which is a continuation-in-part of Ser. No. 86,054, Jul. 6, 1993, Pat. No. 5,345,860. This application Feb. 10, 1995, Ser. No. 431,151

Int. Cl. F16J 9/00; F16K 41/00

U.S. Cl. 92—192

14 Claims



1. Apparatus for banding a relatively thin, flat fluoropolymer washer having a central hole onto an outer cylindrical surface of a piston having a head end, a tail end, a circumferential washer anchoring groove closely adjacent said head end and a plurality of circumferential material-receiving grooves intermediate said anchoring groove and said tail end, and wherein said washer is mounted in said anchoring groove with the washer assuming a circumferentially-beveled shape having the largest diameter of the bevel located toward said piston tail end, said apparatus comprising:

- a heat-conducting banding tube having a cylindrical internal diameter greater than the piston diameter and essentially of the diameter of a hydraulic or pneumatic cylinder with which said piston is to be ultimately cooperatively assembled;
- means for heating said banding tube to a predetermined hot-forming temperature for a predetermined time period to cause heated fluoropolymer to flow into said material grooves while a piston and washer assembly are located in said heated tube;
- a cooling tube in coaxial alignment with said heated tube for cooling and setting the hot-formed fluoropolymer material after the washer has conformed to the cylindrical shape of the piston;
- an inwardly beveled heated entrance end at that end of said heated tube opposite said cooling tube, said beveled heated end corresponding closely to the circumferentially-beveled shape of said washer in said anchoring groove;
- means for applying a preheating temperature to said beveled entrance end whereby the beveled washer placed in contact with the surface of said beveled entrance end may be raised to a temperature greater than ambient temperature but less than the temperature at which said material becomes flowable; and
- means for sequentially urging said piston, after the washer anchored to the piston has had its beveled surface in contact with said beveled entrance end for a predetermined time period sufficient to preheat the washer, from said beveled entrance end into and through said banding and cooling tubes for time periods sufficient to hot-form and set said washer into a cylindrical band about said piston.

7. The method of banding a piston having a plurality of material-receiving grooves with a relatively thin, flat fluoropolymer washer having a central hole by initially attaching the washer by means of said central hole to a grip in an anchoring groove adjacent a head end of said piston and thereafter drawing the piston and washer unit through a hot-forming sizing tube under pressure and heat to convert said washer into sleeve form encompassing the piston periphery, comprising the steps of:

providing said tube with a beveled entrance end, a first hot-forming section and a second hot-forming section through which said unit sequentially passes;

heating said first section and beveled entrance end to a temperature substantially greater than the temperature at which the material of said fluoropolymer washer becomes flowable;

heating said second section to a temperature at which said material becomes flowable sufficiently to be reshaped but below that at which said material begins to gel;

resting said unit on the beveled entrance end for a few seconds with said washer being in surface contact with said bevel and said piston head end facing toward said hot-forming sections in order to initially preheat said washer to a temperature substantially above ambient but below flow-inducing temperature;

rapidly urging said preheated unit inwardly of said tube through said first section and thereby simultaneously converting said washer into sleeve shape while elongating said sleeve away from the piston head end;

moving said unit into said second hot-forming section for a time period and under heat and pressure sufficient to cause said material to flow into the material-receiving piston grooves and tightly conform to the piston periphery; and

cooling said unit while retaining said sleeve at the diameter at which it was hot-formed in said second section until said fluoropolymer material solidifies and retains the shape to which it was hot-formed.

5,588,351

HEAD FOR TWO PIECE ARTICULATED PISTON

Andre Lippai; Jorge K. Tanigami, both of Sao Paulo, and Paulo T. Dellanoe, Sao Caetano do Sul, all of Brazil, assignors to Metal Leve S/A Industria E Comercio, Sao Paulo, Brazil


Continuation of Ser. No. 34,091, Mar. 22, 1993, abandoned, which is a division of Ser. No. 767,047, Sep. 27, 1991, Pat. No. 5,245,752. This application Oct. 28, 1994, Ser. No. 331,176

Claims priority, application Brazil, Sep. 28, 1990, 9004990

Int. Cl. F16J 1/04; F02F 7/00

U.S. Cl. 92—208

13 Claims



1. A head as one piece of a two piece oil cooled piston to which a separate skirt is to be attached as the second piece to form the two piece piston for internal combustion engines comprising:

a substantially cylindrical first monolithic metallic blank having on its lower face a machined circumferential groove for receiving oil as a cooling chamber, said circumferential groove being of variable width with an outer wall which is axially symmetric and an inner wall which is axially asymmetric with the blank longitudinal axis, said first blank having on its upper face a recessed combustion bowl axially offset of

the first blank longitudinal axis and concentric with the inner wall of said circumferential groove,

and an originally separate substantially cylindrical second blank of the same material as said first blank having an annular rib on one face joined to the part of the lower face of the first blank interior of said circumferential groove inner wall to complete the head and leaving access to said circumferential groove.

5,588,352

APPLIANCE FOR MAKING YEAST DOUGHS AND COOKING BAGELS


Robert G. Harrison, Seattle, Wash., assignor to PMI International Corporation, Seattle, Wash.

Continuation-in-part of Ser. No. 372,518, Jan. 13, 1995, Pat. No. 5,526,734. This application May 30, 1995, Ser. No. 452,509

Int. Cl. A47J 37/12; A23B 4/03

U.S. Cl. 99—339

18 Claims



1. A bagel dough making and bagel cooking appliance which comprises:

a casing;

a boiler zone in said casing; a first heating means for boiling water in said boiling zone;

an oven zone in the casing; a second heating means in said oven zone;

a bagel support means which is installable in and removable from said casing;

a user-actuatable means for shifting said bagel support means to said boiler zone to boil bagels supported on said bagel support means and for shifting said bagel support means to the oven zone to bake the boiled bagels; and

dough making means installable in and removable from said casing.

5,588,353

AUTOMATIC BREAD-MAKING APPARATUS

Dov Z. Glucksmann, Wenham, and Karl H. Weidemann, Hull, both of Mass., assignors to Appliance Development Corp., Danvers, Mass.

Filed Jul. 18, 1995, Ser. No. 503,557


Int. Cl. A47J 27/00

U.S. Cl. 99—348

18 Claims

1. An automatic bread making apparatus for baking dough, said apparatus comprising:

a housing having an interior surface and defining a top opening;



- a top cover for covering the top opening of said housing, said top cover having an interior partition, said interior partition defining a first compartment adjacent one side of said partition for circulating cool air and a second compartment adjacent a second side of said partition for circulating hot air;
- a baking chamber having interior and exterior surfaces, said baking chamber positioned within said housing to form an air space between the interior surface of said housing and the exterior surface of said baking chamber, said air space coupled to said first compartment;
- a baking pan made of a heat-conductive material, said baking pan positioned within said baking chamber to define an air space between the interior surface of said baking chamber and said baking pan, said air space coupled to said second compartment;
- a first impeller coupled to said second compartment and configured to supply and circulate heated air; and
- a second impeller coupled to said first compartment and configured to supply and circulate cool air.

5,588,354

APPARATUS FOR CONVEYORIZED GRIDDLE-LIKE COOKING OF FOOD PRODUCTS


Robert M. Stuck, Lake Wylie, S.C., and James Rapier, III, Charlotte, N.C., assignors to Marshall Air Systems, Inc., Charlotte, N.C.

Filed Sep. 21, 1995, Ser. No. 531,709

Int. Cl.⁶ A23L 1/00; A47J 37/00; 37/04

U.S. Cl. 99—386

12 Claims



1. Apparatus for conveyORIZED heating of a food product simultaneously on two opposed sides, the apparatus comprising a pair of heating elements arranged in opposed spaced facing relation for

emitting thermal energy toward one another, two endless food transport conveyors each having a substantially continuous perforate food contacting surface, and means for driving the conveyors to travel between the heating elements along respective food-conveying runs in a common transport direction in sufficiently closely spaced, generally parallel relation to transport the food product to be heated between the conveyors and between the cooking elements by contact of the respective food contacting surfaces of the conveyors with opposite sides of the food product, the drive means comprising a pair of rollers supporting each conveyor and a drive motor connected in synchronous driving relation to one roller of each pair.

5,588,355

KNOCKDOWN COMPACTABLE FOOD SMOKER AND METHOD OF USE THEREOF


Julian E. Mead, and James B. Mead, both of P.O. Box 871908, Wasilla, Ak. 99687-1908

Filed Apr. 17, 1995, Ser. No. 423,279

Int. Cl.⁶ A23B 4/04; F24C 5/20

U.S. Cl. 99—449

8 Claims



1. A portable, compactable smokehouse comprising:

- a front frame unit;
- a rear frame unit;
- a pair of oppositely disposed side walls, said oppositely disposed sidewalls being removably attached to the front frame unit and the rear frame unit, thereby forming a box-like structure;
- a top, removably attached to said box-like structure;
- a means for supporting food, removably installed within said box-like structure;
- a means for providing smoke into said box-like structure;
- a first access door, hingably installed on said box-like structure to permit access to said means for providing smoke into said box-like structure;
- a second access door, hingably installed on said box-like structure to permit access to aid means for supporting food; and
- a means for supporting the second access door such that the second access door assumes a horizontal, flat plane surface when opened.

5,588,356

CHAIN MOLD FOR PREPARING SOLID FOOD PRODUCTS, OR FILLED FOOD PRODUCTS, OF DIFFERENT THREE DIMENSIONAL SHAPES

Roberto Rizzi, and Mario Rizzi, both of Via Trieste 62, Martinengo (Bergamo), Italy


Filed Jan. 16, 1996, Ser. No. 584,940

Claims priority, application Italy, Jun. 26, 1995, MI95A1365

Int. Cl.⁶ A21C 3/06; 9/00; 11/00; A23P 1/00

U.S. Cl. 99—450.6

10 Claims



1. A chain mold for making solid food products, in particular filled food products, having different three dimensional shapes, said chain mold comprising:

- a supporting construction including two shoulders respectively supporting an upper shaft and an upper axle and a bottom shaft and a bottom axle having horizontal and parallel rotary axes;
- gear wheels mounted on each of said shafts and axles respectively meshing with an upper chain and a bottom chain;
- said upper and bottom chains each having chain links mutually facing along a vertical intermediate plane and sequentially defining dihedral shaped articles;
- the dihedral shaped articles of the bottom chain having a cutting edge for cutting a food product head;
- each link of said upper chain slidably supporting along said dihedral articles, a pair of controllably movable half-molds which are movable toward and away from a corresponding pair of half-molds supported by an opposite link so as to form a mold for a food product piece from said food product head supplied along said intermediate plane, said mold having a set length to provide a food product with a set proper shape; and
- operating systems provided for controlling said half-molds so as to drive said half-molds and align them to provide a precise cutting of said food product head.

5,588,357

SHOCK WAVE STERILIZER

Hisao Tomikawa, Takatsuki; Hideo Matsuo, and Kazuhito Fujiwara, both of Kumamoto, all of Japan, assignors to Tsubakimoto Chain Co., Osaka, Japan

Filed Oct. 25, 1994, Ser. No. 328,830


Claims priority, application Japan, Oct. 25, 1993, 5-266403

Int. Cl.⁶ A23L 3/32

U.S. Cl. 99—451

10 Claims

1. A shock wave sterilizer, comprising:
- an elastic container for containing a fluid medium to be sterilized;
 - a shock wave source disposed to face said elastic container, said shock wave source comprising an electrical conductor connected to a source of electrical current of a value sufficient to heat said electrical conductor to a point at which said electrical conductor vaporizes and produces a shock wave; and
 - a pressure transfer medium interposed between said shock wave source and said elastic container convey the force of the shock wave to said elastic container and the medium therein.



5,588,358

TRASH HANDLING DEVICE


Frank H. Klepacki, 724 Pinecrest Ct., Hinsdale, Ill. 60521, and David G. Klepacki, 1660 Stoney Point Ct., Colorado Springs, Colo. 80919

Filed Nov. 7, 1995, Ser. No. 554,843

Int. Cl.⁶ B30B 15/14; 1/04

U.S. Cl. 100—53

7 Claims



1. A trash handling device comprising a housing within which a trash container is received, said container having an open upper end, said housing including an access door swingable inwardly to allow trash to be delivered to said container, a compactor including a compacting plate pivotally mounted within the housing and swingable into said container to compact trash therein, lever means exterior of the housing connected to said compacting plate for selectively driving the plate into said container and compacting trash therein, means normally biasing said compacting plate to a rest position above said container and permitting said access door to freely swing inward for depositing trash in said container, and safety lock means preventing said access door from swinging inwardly when said compacting plate is moved from the rest position to prevent a person from being injured during a compacting operation.

5,588,359

METHOD FOR FORMING A SCREEN FOR SCREEN PRINTING A PATTERN OF SMALL CLOSELY SPACED FEATURES ONTO A SUBSTRATE

Jim Hofmann, and Darryl Stansbury, both of Boise, Id., assignors to Micron Display Technology, Inc., Boise, Id.


Filed Jun. 9, 1995, Ser. No. 488,704

Int. Cl.⁶ B41N 1/24

U.S. Cl. 101—128.21

22 Claims

1. A method for forming a screen for screen printing a substrate, said method comprising:



providing a mesh including screen wires interwoven to form screen openings of a predetermined size and frequency; depositing an emulsion on the mesh; providing a mask having open areas spaced to form a desired pattern; aligning the open areas of the mask with the screen openings by viewing the open areas and screen openings through a viewing device and adjusting a location of the mask or screen; and patterning the emulsion by directing a laser light through the mask to ablate the emulsion and form a pattern of openings therethrough in alignment with the screen openings.

from the rotating body, and the first return channel being shaped to direct the cold air back into the stream of cold air being blown through the blowing device; means for producing a vacuum region in the blowing device along the stream of cold air blowing through the blowing device toward the rotating body, and the vacuum region communicating with the first return channel for drawing recirculated cold air back into the stream of cold air.

5,588,361

DEVICE AND METHOD FOR INSERTING OR REMOVING OPERATING PARTS INTO OR FROM A PRINTING MACHINE


Einar K. Riis, Skodsborg, Denmark, assignor to Werner Kammann Maschinenfabrik GmbH, Bunde, Germany
PCT No. PCT/DK94/00051, § 371 Date Jul. 28, 1995, § 102(e) Date Jul. 28, 1995, PCT Pub. No. WO94/18007, PCT Pub. Date Aug. 18, 1994

PCT Filed Feb. 2, 1994, Ser. No. 500,902

Claims priority, application Denmark, Feb. 3, 1993, 126/93
Int. Cl.⁶ B41F 13/20; 13/40; 13/44

U.S. Cl. 101—216

4 Claims



1. A device for selectively inserting and removing operating parts (3,4,5,6) into and from a printing machine (13) having a removable front panel, said device comprising:

- a carriage (1) adapted to be placed in a position facing said removable front panel in the printing machine (13);
- a frame (2) mounted on said carriage (1) for movement transversely relative thereto into and out of the printing machine (13) after said front panel has been removed, said frame having first releasable securing means (7,8,10,11,12) for releasably securing at least one of said operating parts (3,4,5,6) to be selectively inserted and removed, said first releasable securing means being released by cooperation with releasing means (14,17) situated in the printing machine (13);
- second releasable securing means situated in the printing machine (13) for releasably securing at least one of said operating parts (3,4,5,6) to be selectively inserted and removed;
- individual power-driven transfer means (15,18,19,20,21,22) adapted after releasing of said second releasable securing means to transfer at least one of said operating parts (3,4,5,6) from the first releasable securing means (7,8,10,11,12) on the frame (2) to the second releasable securing means in the printing machine (13) after releasing thereof, and vice versa; and
- means situated in the printing machine (13) adapted to bring the first and second releasable securing means into their securing positions when removing the frame (2) from the printing machine (13).


5,588,360 TEMPERATURE-CONTROL DEVICE FOR ROTATING BODIES IN PRINTING MECHANISMS

Hans-Joachim Kurz, Grossaltingen, Germany, assignor to Baldwin-Gegenheimer GmbH, Germany
Filed Mar. 7, 1994, Ser. No. 206,794
Claims priority, application Germany, Mar. 11, 1993, 43 07 732.3

Int. Cl.⁶ B41F 13/22

U.S. Cl. 101—212

14 Claims



1. A temperature control device for rotating bodies in a printing mechanism, which bodies include at least one of printing cylinders, inking rolls and rubber blanket cylinders, the temperature control device comprising:

- a blowing device having a generally box shape, having a length along the axis of the associated rotating body and extending circumferentially partly around the rotating body, and being shaped for blowing a stream of cold air through the blowing device and onto the outer surface of the rotating body substantially over the entire length of the body;
- means for generating cold air, including an air inlet for air to be chilled by the generating means and an air outlet for cold air; a blower for blowing cold air in the stream through the blowing device, the blower being connected with the air outlet from the generating means for receiving cold air therefrom;
- a first air recirculation circuit in the blowing device including a first cold air return channel having an inlet region near the rotating body and placed so as to draw cold air which has been blown onto and then deflected by the rotating body away

5,588,362

CYLINDER THROW-ON AND THROW-OFF MECHANISM FOR PRINTING PRESS


Hiroyuki Sugiyama; Norio Hirose, both of Ibaragi; Teruyoshi Hamabuchi, Kanagawa, and Hikoji Muto, Tokyo, all of Japan, assignors to Komori Corporation, Japan
Filed May 2, 1995, Ser. No. 433,224

Claims priority, application Japan, May 6, 1994, 6-116079

Int. Cl.⁶ B41F 13/24

U.S. Cl. 101—218

9 Claims



1. A cylinder throw-on and throw-off mechanism for a printing press having a plate cylinder and a printing cylinder, which are disposed with outer surfaces being separated from each other, and a blanket cylinder disposed therebetween, comprising:

- driving means, having a motor serving as a driving source, for moving said blanket cylinder between an impression-on position where said blanket cylinder is pressed against said plate cylinder and simultaneously pressed against said printing cylinder through a paper sheet and an impression throw-off position where said blanket cylinder is separated from said plate cylinder and said printing cylinder in accordance with a direction of rotation and a number of revolutions of said motor;
- control means for setting an operation pattern of said motor, which is defined by a total number of revolutions of said motor and a relationship between a mechanical rotation phase and said total number of revolutions of said motor, and driving and controlling said motor in accordance with said set operation pattern, wherein said control means determines an operation timing and said operation pattern such that a gap angle of said blanket cylinder is included within ranges of a gap angle of said plate cylinder and a gap angle of said printing cylinder;
- sheet thickness data generation means for generating sheet thickness data of a printing paper sheet, and wherein said control means sets the operation pattern of said motor on the basis of the sheet thickness data; and
- phase detection means for detecting a rotation phase of said printing press, and wherein said control means calculates an operation timing of an impression-on/impression throw-off operation of said blanket cylinder in accordance with a phase signal output from said phase detection means and drives and control said motor in accordance with said operation pattern.

5,588,363

METHOD AND DEVICE FOR PERFORMING OPERATING STEPS IN AN ADJUSTMENT OF A PRINTING PRESS

Willi Becker, Bammental, Germany, assignor to Heidelberger Druckmaschinen AG, Heidelberg, Germany

Filed Jan. 23, 1995, Ser. No. 376,430


Claims priority, application Germany, Jan. 21, 1994, 44 01 684.0

Int. Cl.⁶ B41F 5/02; 21/10; 1/20

U.S. Cl. 101—230

9 Claims

1. A printing machine having a plurality of adjusting components comprising:



- a pressure medium source for providing a first pressure medium;
- a first pressure system supplied with the first pressure medium;
- a second pressure system filled with a second pressure medium in operative engagement with the adjusting components, and means for pressurizing the second pressure medium in the second pressure system in response to pressure applied to said first pressure system by said pressure medium source; and means for moving each of said plurality of adjusting components in response to a fluid under pressure from said pressure medium source for acting against a respective counter force;
- said second pressure system in operative engagement with the adjusting components for moving each of the adjusting components against a respective counter force;
- means for causing the first pressure system to apply pressure at different pressure stages to second pressure system;
- said adjusting components are divided into groups, and wherein the counter forces are different from group to group;
- means for balancing the counter force against the adjusting components of a respective group against the corresponding pressure stage;
- means for performing a first work step under pressure of a first pressure stage and for performing a further work step under pressure of a further pressure stage, and
- means for providing a pressure to the further pressure stage greater than the pressure of a preceding pressure stage.

5,588,364

PRINT UNIT DAMAGE PREVENTION ASSEMBLY

Claus A. Bolza-Schünemann, Würzburg, Germany, assignor to Koenig & Bauer Aktiengesellschaft, Würzburg, Germany
Filed May 18, 1995, Ser. No. 444,363

Claims priority, application Germany, May 20, 1994, 44 17 661.9


Int. Cl.⁶ B41F 13/24

U.S. Cl. 101—247

8 Claims

1. A print unit damage prevention assembly usable to prevent damage to print units in a web-fed rotary printing press, said assembly comprising:

- a plurality of rubber blanket cylinders pivotally supported in side frames of a printing press;
- a counter-pressure cylinder supported in said side frames, said rubber blanket cylinders being selectively in contact with each other and said counter-pressure cylinder;
- controllable adjustment means usable to shift said blanket cylinders in said side frames;



an energy reservoir which can receive and store electrical energy during normal operation of said printing press in which said blanket cylinders are located; and
a control means interposed between said energy reservoir and said adjustment means for said blanket cylinders, said control means being operable upon a failure of an electrical supply to said printing press to provide power to said adjustment means from said energy reservoir to move at least one of said blanket cylinders to a pressure release position out of contact with its associated blanket cylinders and counter-pressure cylinder.

5,588,365

APPARATUS FOR METERING LIQUID MEDIA IN OFFSET PRINTING MACHINES

Manfred Herold, Hainburg; Georg Hartung, Seligenstadt; Hans-Willy Schutz, Freigericht, and Ulrich Jung, Limburg, all of Germany, assignors to MAN Roland Druckmaschinen AG, Germany


Filed Dec. 23, 1994, Ser. No. 371,268

Claims priority, application Germany, Dec. 23, 1993, 43 44 084.3

Int. Cl.⁶ B41F 31/04; 31/06; 3/30

U.S. Cl. 101—350

8 Claims



1. An offset printing machine comprising
an impression cylinder,
a form cylinder,
a first liquid media supply subassembly located at a first location adjacent the form cylinder, said subassembly including
a metering roller,
a dipping roller, said metering roller being in contact with said dipping roller, said metering roller and said dipping roller having different surface hardnesses, and
a reservoir containing a first liquid media of determined viscosity, said dipping roller being rotatable within the reservoir such that the first liquid media is transferred to the surface of the dipping roller.

said first subassembly being selectively movable between an inoperative position in which said metering roller is in disengaged relation to the form cylinder and an operative position in which said metering roller is in contacting engagement with said form cylinder for supplying said first liquid media to said form cylinder,

a second liquid media supply subassembly located at a second location adjacent said form cylinder different from said first location, said second subassembly comprising
a screen applicator roller,

a chamber doctor comprising at least one doctor blade supported along the circumference of the screen applicator roller, and

a supply of a second liquid media of higher viscosity than said first liquid media, said second supply supplying liquid to the surface of the screen applicator roller, the chamber doctor metering the application of the second liquid media to the screen applicator roller.

said second subassembly being selectively movable between an inoperative position in which said screen applicator roller is out of contact with said form cylinder and an operative position in which said screen applicator roller contacts said form cylinder at a location different from the location of contact of the metering roller of said first subassembly, said second subassembly supplying the second liquid media to the form cylinder when said second subassembly is in the operative position and said first subassembly is in the inoperative position.

5,588,366

METHOD OF MONITORING THE WEAR ON PRINTING FORMS IN A PRINTING MACHINE

Gerhard Löffler, Walldorf, Germany, assignor to Heidelberger Druckmaschinen AG, Heidelberg, Germany


Filed Apr. 20, 1995, Ser. No. 425,825

Claims priority, application Germany, Apr. 20, 1994, 44 13 736.2

Int. Cl.⁶ B41F 33/02

U.S. Cl. 101—484

2 Claims



1. A method of monitoring wear on printing forms in a printing machine, which method comprises:
defining a first measurement location on a print image, the first measurement location having a defined first tonal value above a given upper tonal value;
defining a second measurement location on the print image, the second measurement location having a defined second tonal value below a given lower tonal value;
scanning, with an image recording device, a printed image on a printed surface of a print product at the first and second measurement locations;
producing image signals of the first and second measurement locations with the image recording device and supplying the image signals to a control unit; and
deducing, from the image signals, wear on the printing forms and outputting signals representing the wear with the control unit.

5,588,367

RAILWAY VEHICLE SUSPENSIONS

Herbert Scheffel, 83 A Van Wouw Street, Groenkloof, Pretoria, Transvaal, South Africa


Filed Mar. 9, 1994, Ser. No. 207,730

Claims priority, application South Africa, Mar. 9, 1993, 93/1668


Int. Cl.⁶ B61D 5/38; 5/26

U.S. Cl. 105—168

13 Claims



1. A railway vehicle which includes a frame suspended on at least two wheelsets coupled to one another and spaced from one another along a longitudinal axis of said frame, each of said coupled wheelsets having a live axle which has ends mounted in respective axle boxes, and couplings which are attached to the frame and which couple the axleboxes of one of the coupled wheelsets to the axleboxes of the other of the coupled wheelsets in such a manner as to constrain relative movements between the coupled wheelsets in a lateral plane, each coupling including:
interconnected crank levers which operate to uncouple lateral movements of the frame from the movements of the coupled wheelsets, and
links which connect the crank levers to the respective axleboxes of the coupled wheelsets and which are inclined relative to said longitudinal axis, the links which connect the crank levers to the axleboxes at the ends of each of the coupled wheelsets lying on axes which intersect substantially at said longitudinal axis.



5,588,369

PASSIVE STABILIZATION PLATFORM


Emad Rizkalla, and David Newbury, both of St. John's, Canada, assignors to Zedd Technologies Inc., St. John's, Canada

Filed May 12, 1994, Ser. No. 241,858

Int. Cl.⁶ A47F 5/12

U.S. Cl. 108—2

4 Claims



1. A passive stabilizing platform which comprises:
(a) a base;
(b) a platform;
(c) at least three vertically-upright hollow cylindrical legs, each of said legs having a lower end and an upper end, each of said legs being secured at the lower end thereof to said base, and being disposed equi-angularly around said base, wherein in use, each of said hollow cylindrical legs contains a cylindrical column of water therein;
(d) a plurality of hollow cylindrical tubes, two tubes being connected to each of said hollow cylindrical legs near the lower end of each of said hollow cylindrical legs thereby interconnecting said hollow cylindrical legs to each other to allow free unimpeded movement of water between said interconnected hollow cylindrical legs so that an upper surface of water in each of said hollow cylindrical legs automatically moves to an equilibrium level;
(e) a spherical float member disposed in each of said hollow cylindrical legs, said spherical float member being movable only vertically upwardly or vertically downwardly within the hollow cylindrical leg within which said spherical float member is disposed, said movement being dependent solely, and in conjunction with, said upper surface of water in the hollow cylindrical leg within which said float member is disposed;
(f) a plurality of support arms, each of said support arms having an upper end and a lower end, each of said support arms being fixed at said lower end to an associated said float member and extending upwardly from said associated float member and

5,588,368

SECONDARY SUSPENSION FOR RAIL VEHICLES

Wolfgang-Dieter Richter, Winkelhaid; Lutz Uebel, Heroldsberg, and Engelbert Weeger, Nürnberg, all of Germany, assignors to MAN GHH Schienenverkehrstechnik GmbH, Nürnberg, Germany

PCT No. PCT/DE93/00671, § 371 Date Mar. 30, 1994, § 102(e) Date Mar. 30, 1994, PCT Pub. No. WO94/03340, PCT Pub. Date Feb. 17, 1994

PCT Filed Jul. 30, 1993, Ser. No. 211,367

Int. Cl.⁶ B61F 5/00

U.S. Cl. 105—199.1

4 Claims

1. A secondary suspension for rail vehicles, comprising:
a supplementary spring;
means for fixing said supplementary spring means between a car body and a bogey frame of said rail vehicle;
means for fixing said supplementary spring means between a car body and a bogey frame of said rail vehicle;
means for compressing said supplementary spring when said rail vehicle is stopped, thereby lowering said car body;
means for permitting extension of said supplementary spring when said rail vehicle is in motion;
said means for permitting extension includes at least one lifting element;
said at least one lifting element includes means for locking said lifting element at an upper end position thereof;
said means for locking includes at least one latch;
said at least one latch engages a slot in said lifting element.


being fixed at said upper end to said platform, to cause rotation of said platform about a vertical axis upon vertical movement of said support arms;

(g) a joint secured between said hollow cylindrical legs and said platform to permit said complete rotation of said platform about a vertical axis;

(h) a depending vertical shaft rigidly secured to said platform; and

(i) a counterweight hanging on said depending vertical shaft below said joint;

whereby said passive stabilizing platform compensates for the effects of rolls, pitches, yaws, vibrations and accelerations simultaneously, to keep said platform level in the "X" and "Y" axes at all times.



5,588,370

RIGID SHELF STRUCTURE


Jonathan T. Longley, 15 Westwood Rd., Lexington, Mass. 02173

Filed Apr. 3, 1995, Ser. No. 415,732

Int. Cl.⁶ A47B 23/00

U.S. Cl. 108—42

17 Claims



1. A shelf structure, suitable for mounting in a corner, comprising:

- an upper surface;
- a first abutment surface depending from said upper surface;
- a second abutment surface depending from said upper surface, said second abutment surface further conjoined to said first abutment surface;
- a front face depending from said upper surface, said front face further extending between said abutment surfaces; and
- a torsion member unitary with said upper surface, said torsion member extending between said front face and at least one of said abutment surfaces.

5,588,371

SKID FOR HEAVY PAYLOADS

Robert Looker, Carpinteria, Calif., assignor to Satco, Inc., El Segundo, Calif.

Filed Apr. 21, 1994, Ser. No. 230,630

Int. Cl.⁶ B65D 19/38

U.S. Cl. 108—51.1


33 Claims

1. A skid for transporting a payload, the skid comprising:

- a skid platform;
- a plurality of feet on the platform, each foot including:
- an upper section attached to the platform;
- a lower section secured to the upper section;
- a shock absorber extending between the upper section and the lower section;

1. Stackable pallet skid members for storing and dispensing reels of wire, with each of the pallet skid members being substantially rectangular in shape and having a front portion, a rear portion and two side portions, including in combination:

- four corner post members extending vertically upwardly in substantially parallel alignment, with each of said corner post members having upper and lower ends each terminating in a single plane;
- end support members secured and connected to respective pairs of said corner posts members adjacent to said upper and lower ends to define the side portions of the pallet skid members;
- at least one rear support member secured and connected to the pair of said corner post members intermediate the end thereof to define the rear portion of the pallet skid members;
- end retaining means supports extending between respective pairs of said corner post members intermediate the upper and lower



5,588,372

STACKABLE DISPENSING APPARATUS FOR WIRE REELS

Patrick J. Kelly, Hartlebury, England, assignor to National-Standard Company

Filed May 9, 1994, Ser. No. 239,278

Int. Cl.⁶ B65D 19/44

U.S. Cl. 108—55.1

26 Claims

ends thereof, said end retaining means supports having bracket members mounted thereto;

a plurality of rail members horizontally extending from the lower front edge portion to the rear edge portion of the skid member, with each pair of said rail members structurally arranged to receive and support the reel sides of a reel of wire when the reel of wire is vertically oriented in a side-by-side relationship on the pallet skid member;

upper support members secured and connected to the upper ends of each pair of said corner post members and extending the length of the front and rear portions of the skid members;

lower support members secured and connected to the lower ends of each pair of said corner post members and extending the length of the front and rear portions of the skid members, with said upper support members and said lower support members structurally arranged to provide a linear extending nesting and stacking of the pallet skid members when one pallet skid member is positioned on top of another pallet skid member; and

retaining means hingedly mounted to said bracket members on said end retaining means supports of the pallet skid member, with said retaining means adapted to pivotally move from a closed position wherein the vertically oriented reels of wire are retained on the pallet skid member to an open position wherein the vertically oriented reels of wire may be removed from the pallet skid member by rolling the reels along said rail members.

5,588,373

LIQUID CONTAINMENT PALLET


Stephen A. Bacskay, Central Islip, N.Y., assignor to Chem-tainer Industries, Inc., West Babylon, N.Y.

Filed Feb. 14, 1995, Ser. No. 388,522

Int. Cl.⁶ B65D 19/44

U.S. Cl. 108—55.3

9 Claims



1. A liquid containment pallet for supporting at least one container for storing liquids, comprising:

- a confined basin defined by integral sidewalls and a bottom wall, said bottom wall having integral means for receiving a pallet lifting means for lifting and moving said pallet; and
- a platform for detachably supporting at least one container, said platform having receiving means for supporting said at least one container in an elevated position relative to said bottom wall of said confined basin and preventing said container from sliding appreciably relative to said platform when supported on said platform, said platform including means for supporting said platform with respect to said basin and draining means for communicating spillage from said container to said basin, said platform and said basin collectively forming a liquid containment volume for accumulating said spillage.

5,588,374

TRANSPORT AND STORAGE SYSTEM AND APPLICABLE SUPPORT AND MOUNTING EQUIPMENT

Dieter Urbach, Grünwald, Germany, assignor to Oeco-Team Unternehmens-und Umweltberatung GmbH, Grünwald, Germany

PCT No. PCT/EP92/00176, § 371 Date Aug. 16, 1993, § 102(e) Date Aug. 16, 1993, PCT Pub. No. WO93/08088, PCT Pub. Date Apr. 29, 1993


PCT Filed Jan. 28, 1992, Ser. No. 78,278

Claims priority, application Germany, Oct. 22, 1991, 41 34 849.4; Nov. 12, 1991, 41 37 166.6

Int. Cl.⁶ B65D 19/12

U.S. Cl. 108—56.3

59 Claims



1. In a transport and storage system (1) having a goods mounting arrangement (2) which includes a support apparatus that has at least one support footing (3) having an upper end and a lower end, the upper end having a connection device in the form of two outwardly extending shoulders (4, 5) which, when attached to the mounting arrangement (2) form an upper (4) and a lower (5) outwardly extending shoulder, the lower shoulder (5) having a feed opening (8) and a downwardly extending tongue (9), the improvement comprising:

wherein the upper shoulder (4) has, in an area above the feed opening (8), at least one flexible lip (10, 11) that can be flexed from an upper plane which includes the upper shoulder (4), wherein the shoulders (4, 5) are made as annular shaped edge strips running parallel to each other with each lid (10, 11) being formed by a slot (12) which runs radially outwardly from the support footing (3), and by another slot (13, 14) which runs along an interior load side (16) of the upper shoulder (4).

5,588,375

MOUNTING TRACK

Michael J. Cotterill, Lot 5, Tugalong Road, Canyonleigh N.S.W. 2577, Australia

PCT No. PCT/AU93/00231, § 371 Date Nov. 17, 1994, § 102(e) Date Nov. 17, 1994, PCT Pub. No. WO93/22950, PCT Pub. Date Nov. 25, 1993

PCT Filed May 19, 1993, Ser. No. 338,494

Claims priority, application Australia, May 19, 1992, PL2522; Aug. 7, 1992, PL4023


Int. Cl.⁶ A47B 11/00

U.S. Cl. 108—102

16 Claims

1. A workstation including:

- two generally horizontal support members;
- a linkage mechanism for maintaining a predetermined vertical displacement between the members;
- the mechanism being fixed at one end to one of the members and at the other end including at least one longitudinally extending support formation; and
- at least one mounting track for connecting the other support member and the support formation for relative longitudinal




movement, the track including a longitudinally extending body for abutting the said other of the support members and first and second transverse arms extending from the body and having respective opposed substantially parallel first and second engagement surfaces which, in combination with the body, define an open ended channel for retaining the support formation, the free end of the first arm both extending beyond the free end of the second arm and including a peripherally depending lip for partly closing the channel to restrain transverse movement of the support formation, for longitudinal slideable engagement therewith.

5,588,376
SYSTEM FOR MOUNTING ONE OR MORE ITEMS TO THE LEG STRUCTURE OF A WORKTABLE
 Lon D. Seidl, and David R. Funk, both of Green Bay, Wis., assignors to Krueger International, Green Bay, Wis.
 Filed Feb. 24, 1994, Ser. No. 201,465
 Int. Cl.⁶ A47B 9/00

U.S. Cl. 108—106

2 Claims



1. In a worktable including a work surface supported above a pair of spaced legs, each leg including a first inner surface facing toward the other leg and a second outer surface facing away from the other leg, a system for mounting an item to the worktable, comprising:


- a pair of spaced vertical slot patterns provided on at least one of the inner and outer surfaces of each leg;
- a pair of bracket members mounted to the item mounted to the worktable, the bracket members being spaced apart a distance substantially equal to the spacing of the slot patterns, each bracket member including structure engaged with one of the slot patterns for removably mounting the item to the worktable leg;
- wherein the item comprises an overhead storage unit including an upper storage area and a pair of sides depending therefrom,

wherein each side is interconnected with the pair of bracket members for mounting to one of the legs;
 wherein each side of the overhead storage unit is interconnected with the pair of bracket members by means of pocket structure to which the bracket members are connected and within which the lower end of each side of the overhead storage unit is received; and
 a pair of rollers mounted adjacent the work surface and extending outwardly one from each side of the work surface above one of the legs, and wherein each roller is engaged with one of the overhead storage unit sides to stabilize the overhead storage unit during adjustment of the vertical position of the work surface.

5,588,377
CONVERTIBLE TABLE CONFIGURABLE BETWEEN EXPANDED AND COMPRESSED POSITIONS
 Hal Fahman, Riverside, Calif., assignor to Fleetwood Enterprises, Inc., Riverside, Calif.
 Filed Apr. 25, 1995, Ser. No. 428,030
 Int. Cl.⁶ A47B 9/00

U.S. Cl. 108—145

19 Claims



1. A convertible table, comprising:
 - (a) four legs supporting the convertible table above a supporting surface;
 - (b) a table bottom unit, comprising:
 - (1) a bottom planar surface parallel to the supporting surface, the bottom planar surface having a rectangular parameter, and
 - (2) four bottom sidewalls surrounding the rectangular parameter, each of the bottom sidewalls extending above and perpendicular to the bottom planar surface, the four bottom sidewalls forming four corners, the table bottom unit being connected to the four legs near the four corners;
 - (c) four bottom hinge brackets connected to the table bottom unit near the four corners;
 - (d) a table top unit comprising:
 - (1) a top planar surface parallel to the supporting surface; and
 - (2) four top sidewalls surrounding approximately the same rectangular parameter as the four bottom sidewalls, the four top sidewalls forming four corners, each of the top sidewalls extending below and perpendicular to the top planar surface;
 - (e) four top hinge brackets connected to the table top unit near the four corners formed by the four top sidewalls; and
 - (f) a table hinge positioned between the table bottom unit and the table top unit, comprising:
 - (1) an upper-front elongated member having two upper-front dowels at opposing ends, the two upper-front dowels fitting into a corresponding two of the four top hinge brackets;
 - (2) an upper-rear elongated member having two upper-rear dowels at opposing ends, the two upper-rear dowels fitting into a corresponding two of the four top hinge brackets;


- (3) a lower-front elongated member having two lower-front dowels at opposing ends, the two lower-front dowels fitting into a corresponding two of the four bottom hinge brackets;
- (4) a lower-rear elongated member having two lower-rear dowels at opposing ends, the two lower-rear dowels fitting into a corresponding two of the four bottom hinge brackets;
- (5) a first set of parallel fingers connected between the upper-front elongated member and the lower-rear elongated member, the upper-front elongated member and the lower-rear elongated member being parallel to one another and perpendicular to the first set of parallel fingers;
- (6) a second set of parallel fingers connected between the lower-front elongated member and the upper-rear elongated member, the lower-front elongated member and the upper-rear elongated member being parallel to one another and perpendicular to the second set of parallel fingers; and
- (7) a pin running through a center area of each of the fingers of the first and second sets of parallel fingers, the fingers rotating about the pin to bring the upper-front and lower-front elongated members into contact with one another and, at the same time, to bring the upper-rear and lower-rear elongated members into contact with one another to thereby bring the table hinge into a compressed configuration.

5,588,378
COMBUSTION ENHANCEMENT SYSTEM WITH IN-BED FOILS

Rick A. Mancini, Endicott, N.Y., assignor to New York State Electric & Gas Corporation, Binghamton, N.Y.
 Filed Apr. 18, 1995, Ser. No. 423,088
 Int. Cl.⁶ F23K 3/00


U.S. Cl. 110—101 A

38 Claims



1. A stoker combustion enhancing system for a furnace, comprising:
 - a traveling grate for supporting a bed of fuel, said grate having an upper movable grate surface extending between a first end of said grate for receiving fuel to be burned and a second end of said grate for discharging spent fuel;
 - a first piping system for supplying combustion air beneath said upper grate surface of said grate;
 - a combustion enhancing member with a fluid receiving cavity positioned above said upper grate surface, said combustion enhancing member having a fuel engaging exterior surface with at least one passageway in fluid communication with said cavity for ejecting the fluid from said cavity into the fuel moving along said grate; and
 - a second piping system, independent from said first piping system, providing a source of pressurized fluid in fluid communication with said cavity of said combustion enhancing member for injecting a non-aqueous combustion enhancing agent into an area of the bed of fuel,
- said combustion enhancing member being located in at least one oxygen deficient zone or maximum reactivity zone of ignited fuel on the bed of fuel.

5,588,379
MIXING DEVICE AND METHOD FOR GASEOUS LIQUID OF PULVERISED SUBSTANCES
 Gustaaf J. Witteveen, Stationsstraat 41, 6584 AS Molenhoek, Netherlands
 Continuation of Ser. No. 117,209, Sep. 14, 1993, abandoned.
 This application Apr. 18, 1995, Ser. No. 423,354
 Claims priority, application Netherlands, Mar. 20, 1991, 9100490
 Int. Cl.⁶ F23C 7/00; F23D 11/10; B01F 5/00; B05B 7/10
 U.S. Cl. 110—262 13 Claims




1. A burner which mixes a combustion air flow with a fuel comprising:
 - a vortex chamber which is axially symmetric about a longitudinal axis, said vortex chamber including an upstream side at one longitudinal end and a downstream side at the other longitudinal end defining an axial flow direction from the upstream side to the downstream side,
 - a central opening at the downstream side,
 - a tapering portion which tapers from a maximum radial inside diameter provided between the upstream and downstream side to a radial inside diameter at the central opening which is 70-90% of the maximum radial diameter,
 - a feed means for feeding combustion air into said vortex chamber to create a rotational movement of the combustion air about the longitudinal axis, said feed means including a plurality of openings through which the combustion air is fed to said vortex chamber, said openings being located at a periphery of said vortex chamber immediately upstream from the tapering portion,
 - a fuel inlet located at or upstream of said openings such that mixing of the rotating combustion air fed through the openings with fuel from the fuel inlet in said vortex chamber creates a vortex flow pattern of a fuel/air mixture about the longitudinal axis in said vortex chamber; and
 - a flame room fluidly connected with the central opening at the downstream side of said vortex chamber, said flame room including an inside diameter directly adjacent the central opening of said vortex chamber which is at least 2.5 times greater than the minimum radial inside diameter of the central opening whereby the conditions in the flame room are such that the vortex flow pattern of the fuel/air mixture breaks down upon entry of the fuel/air mixture into said flame room and combustion of the fuel/air mixture takes place in a substantially toroidal zone in the flame room.

5,588,380
DIFFUSER FOR COAL NOZZLE BURNER
 Jeffrey A. LaRose, Stow, Ohio, assignor to The Babcock & Wilcox Company, New Orleans, La.
 Filed May 23, 1995, Ser. No. 448,206
 Int. Cl.⁶ F23D 1/00

U.S. Cl. 110—263

9 Claims

1. A diffuser for a coal burner having a coal nozzle with an axis and an inner surface, the diffuser comprising:
 - a reducing area cone having tapering upstream and downstream ends, for positioning in a coal nozzle at the coal nozzle axis;



a frusto-conical shroud having a small diameter upstream end and a large diameter downstream end, positioned around the reducing area cone; and
a plurality of support legs fixed rigidly to the reducing area cone and extending radially outwardly through the shroud for fastening to the coal nozzle, each of the support legs being inclined at an acute angle to the axis of the coal nozzle for evenly spreading pulverized coal supplied through the coal nozzle and past the diffuser.

5,588,381


METHOD AND SYSTEM FOR BURNING WASTE MATERIALS

Markus Jennebach, Dachau, Germany, and Joao A. Birkhan, Viamao-Rs, Brazil, assignors to Leslie Technologies, Inc., Tallahassee, Fla., and Gruntec Ltda., Brazil

Filed Mar. 7, 1995, Ser. No. 399,847

Int. Cl.⁶ F23J 11/00; 15/00

U.S. Cl. 110—345



20. A method for the two-stage combustion of a flammable gas generated during the treatment of waste materials, comprising the steps of: providing a pair of combustion chambers including a first substantially-horizontal chamber and a second substantially-vertical chamber disposed at a right angle to each other and communicating therebetween, the first chamber having an inlet portion for receiving the flammable gas in a horizontal direction thereof, injection of primary air into the first chamber, thereby forming a mixture of air and the flammable gas and thereby igniting the mixture for partial oxidation thereof, discharging the partially-oxidized mixture of air and the flammable gas tangentially into the second chamber, through a converging distal portion thereof, injection of secondary air tangentially into the second chamber, thereby substantially completely oxidizing the partially-oxidized mixture of air and the flammable gas, and discharging of the waste gas resulting from the two-stage combustion of the flammable gas through an outlet portion thereof.

5,588,382 ZONE TILLER ATTACHMENT FOR PLANTERS


Gary L. Embree, and Robert A. Williams, both of Garden City, Kans., assignors to Acra Products, L.L.C., Garden City, Kans.

Filed May 27, 1993, Ser. No. 68,233

Int. Cl.⁶ A01C 5/04

U.S. Cl. 111—139

22 Claims



36 Claims

1. A zone tiller attachment for a farm implement for use in tilling a strip of loosened soil and simultaneously deflecting trash out of the tilled strip, said attachment comprising:
a support adapted for mounting on said implement; and
a pair of generally upright, downwardly and forwardly converging spoked wheels rotatably mounted on said support, each of said wheels comprising a generally dish-shaped body having a slightly concave front side, a slightly convex back side, and an outermost, circumferential periphery, said body including a central, generally circular trash-deflecting portion and a marginal spoked tillage portion encircling said trash-deflecting portion, said trash-deflecting portion extending approximately one-half the radial distance from said center axis to the periphery of the body and the spoked portion extending the balance of the radial distance from said axis to the periphery of the body, said trash-deflecting portion having an imperforate front face on the front side of the body for engaging and deflecting trash out of the strip when the wheel is in use on the implement and the wheel is rolling along the strip at an oblique angle to the strip, said spoked portion including a peripheral series of circumferentially spaced, elongated, straight spokes projecting beyond the trash-deflecting portion, said support including structure for positioning the wheels in side-by-side relationship for ground-driven rotation about respective, generally transverse axes as the tiller is moved forward with the spokes of the wheels in penetrating engagement with the ground, the wheels being so positioned that the spokes move through arcuate paths of travel during rotation of the wheels and overlap into crossed relationship with one another along the bottom of the tiller and the lower front extremity thereof, each of said spokes being raked back with respect to the direction of rotation of the wheels such that the spokes approach the center of their wheel obliquely with an inner end of each spoke leading an outer, trailing end thereof with respect to said direction of rotation, said crossed relationship of the spokes extending from the lower front extremity of the tiller to an area adjacent the low point on the arcuate paths of travel of the spokes so that the crossed spokes are disposed for churning and cultivating the soil as

they move rearwardly through the soil, leaving a band-like zone of tilled soil in their wake.

5,588,383

APPARATUS AND METHOD FOR PRODUCING PATTERNED TUFTED GOODS


David L. Davis, Indianola; Michael J. Black, Seattle; Richard A. Dolf, Seattle; Sean E. Gorman, Seattle; John M. Havard, Seattle, and Milton R. Sigelmann, Seattle, all of Wash., assignors to Tapistron International, Inc., Ringgold, Ga.

Filed Mar. 2, 1995, Ser. No. 397,742

Int. Cl.⁶ D05C 15/24

U.S. Cl. 112—80.16

3 Claims



1. Knife assembly for mounting to a frame and cutting yarn implanted into a backing by a hollow needle comprising:
a flat, elongate blade having longitudinal edges and a cutting edge extending between the longitudinal edges for shearing engagement with the needle;
a blade holder block having a passage for receiving the blade and a protrusion within the passage, the protrusion having a flat face; and
a screw extending through the block into the passage for selectively engaging the flat blade and holding the blade flush against the flat face, and alternatively, releasing the blade, the longitudinal edges of the blade extending beyond the flat face when the blade is engaged by the screw so that the blade can flex and conform to the needle when the blade engages the needle.

5,588,384

METHOD AND APPARATUS OF FOLDING OPPOSITE ENDS OF A PIECE OF TAPE

Nobuji Miyachi, and Kouji Miyachi, both of Kyoto, Japan, assignors to HAMS Corporation, Kyoto, Japan

Filed Aug. 15, 1995, Ser. No. 518,397

Claims priority, application Japan, Aug. 19, 1994, 6-230142


Int. Cl.⁶ D05B 35/06

U.S. Cl. 112—475.06

7 Claims

1. A method of folding opposite ends of a piece of tape which is to be sewn as a belt loop on a garment, said method comprising the steps of:

- (a) placing the piece of tape on a tape receiving member;
- (b) pressing opposite ends of the piece of tape downwardly;
- (c) holding the opposite ends of the piece of tape using two bifurcated tape folding shafts with at least one flat spring pressed against each of the bifurcated tape folding shafts; and



(d) rotating the bifurcated tape folding shafts in opposite directions to fold the opposite ends of the piece of tape with each of the opposite ends sandwiched between the flat spring and associated one of the bifurcated tape folding shafts.

5,588,385

METHOD FOR MANUFACTURING IMPROVED BACK POCKET BLANK FOR PANTS


Edward A. Sand, St. Louis, Mo., assignor to Western Textile Products Company, St. Louis, Mo.

Filed Dec. 22, 1994, Ser. No. 362,218

Int. Cl.⁶ A41D 27/20

U.S. Cl. 112—475.09

15 Claims



1. The method of forming a back pocket blank for attachment to pants within a back pocket opening, comprising the steps of:
forming an elongated generally rectangular shaped back pocket blank having an opposed pair of longitudinal side edge portions and an opposed pair of shorter end edge portions extending generally transverse to the longitudinal side edge portions; longitudinally folding a predetermined area of each of the longitudinal side edge portions back upon itself to provide a longitudinal side edge fold on each side of the back pocket blank;
creasing each longitudinal side edge fold to provide a flattened longitudinal side edge folded over section on each side of the back pocket blank;
transversely folding a predetermined area of the entire back pocket blank back upon itself along a transverse fold to

provide a transversely folded over area and a non-folded area of the back pocket blank, said transverse folding leaving the shorter end edge portion of the transversely folded over area spaced from the shorter end edge portion of the non-folded area while positioning the flattened longitudinal side edge folded over sections of the transversely folded over and non-folded areas in superimposed relationship to one another; creasing the transverse fold to maintain the transversely folded over area in superimposed proximity to the non-folded over area of back pocket blank; and subsequently sewing the thus formed back pocket blank with a back pocket opening of pants.


5,588,386

PORTABLE COLLAPSIBLE VENTILATOR

John A. Schilt, 2800 Robin La., Muskogee, Okla. 74403
Filed Feb. 13, 1996, Ser. No. 600,550
Int. Cl.⁶ B63J 2/00

U.S. Cl. 114—211

5 Claims



1. A portable ventilating device adapted to deflect a stream of air into an opening of an enclosed space such as a boat hull, comprising:

- a resilient frame joined at the apex, which is bendable into a semi-circular shape to form the ventilator opening;
- an adjustable length of line tied to the opposite ends of said resilient frame and stretched between said ends forming the bottom of said ventilator opening;
- two lengthwise tubular supporting members to provide support for said ventilator, the top of each of said tubular member being attached to said resilient frame away from said joint at the apex and extending from the front of said ventilator rearward to the bottom of each of said tubular member;
- a securing rod designed to be of a size larger than the diameter or longer side of said opening of a boat hull or compartment, with a length of line, from said bar to a mounting point fixedly attached at the apex of said resilient frame said securing rod inserted inside said opening of a boat hull or compartment;
- a cloth or fabric cover affixed to said resilient frame in the shape of a bonnet extending from said resilient frame outwardly and rearward and enclosing the above described structure; and
- said portable ventilating device thus securely affixed to said opening of a boat hull or compartment by means of the tension of said resilient frame and said supporting rod and said lines.

5,588,387

FLOATING PLATFORM


Wentworth J. Tellington, P.O. Box 68291, Tucson, Ariz. 85737
Continuation-in-part of Ser. No. 154,119, Nov. 18, 1993, Pat. No. 5,398,635. This application Mar. 14, 1995, Ser. No. 404,049

Int. Cl.⁶ B63B 35/44

U.S. Cl. 114—261

20 Claims

- 1. A floating platform comprising:



a plurality of independently buoyant modules releasably and flexibly connected to one another to form a single structure, wherein each module comprises at least one walking-beam pontoon system, propulsion means and means for fastening said module to said structure, said walking-beam pontoon system comprising:

- a substantially rigid beam having two ends and a midsection pivotally mounted on a fulcrum in the module; and
- at least one pontoon mounted substantially at each end of said beam.


5,588,388

HULL SHAPE OF SMALL WATERCRAFT

Haruyoshi Maruyama, Kakogawa; Shin Ogata, Himeji, and Yoshiro Tsumiyama, Miki, all of Japan, assignors to Kawasaki Jukogyo Kabushiki Kaisha, Hyogo, Japan
Filed Jun. 7, 1995, Ser. No. 483,313
Claims priority, application Japan, Oct. 3, 1994, 6-264503
Int. Cl.⁶ B63B 1/00

U.S. Cl. 114—271

13 Claims



1. A hull shape of a small watercraft comprising a hull bottom which is substantially V-shaped in transverse section and on whose underside at least one longitudinal chine, extending in a longitudinal direction from the aft part toward the fore part of a hull, and at least one backwardly curved unitary transverse chine, continuously extending in transverse directions substantially across the fore part of said hull, are provided protruding from said hull bottom, and wherein said unitary transverse chine is formed in such a manner as to cross one of (a) the forward part of said longitudinal chine and (b) an imaginary line extended forwardly from said longitudinal chine.


5,588,389

DUAL LIFT BOAT HULL

Jay Carter, Jr., 1404 Chaparral, Burkburnett, Tex. 76354
Filed Mar. 30, 1995, Ser. No. 413,605
Int. Cl.⁶ B63B 1/00

U.S. Cl. 114—271

9 Claims



1. A dual lift boat hull comprising:

- a bow lifting surface having a first angle of attack selected to maximize lift to drag;
- a stepped bottom aft of the bow lifting surface to create an air space between the water and the bottom of the hull at cruising speeds;

a stern lifting surface extending downwardly from the stepped bottom and having a second selected angle of attack relative to the water flow to maximize lift to drag; wherein the hull is flat bottomed and said first and said second selected angles of attack are in a range of about six to eight degrees; and whereby the bow lifting surface and the stern lifting surface maximize lift and reduce drag by lifting the hull and stepped bottom vertically to reduce the wetted hull surface area and enhance performance.


5,588,390

UNIVERSAL CAVITATION PLATE SYSTEM

Leon D. French, Rte. 3, Box 87-L, Los Fresnos, Tex. 78566
Filed Dec. 22, 1995, Ser. No. 557,476
Int. Cl.⁶ B63B 1/24


U.S. Cl. 114—274

12 Claims



1. A universal cavitation plate assembly comprising:

- a cavitation plate having
- a leading edge,
- a trailing edge on the opposite side of the cavitation plate from the leading edge, and
- a longitudinal slot opening in the trailing edge and extending toward the leading edge for part of a length of the cavitation plate, where the slot has a forward portion toward the leading edge, and where the longitudinal slot receives a lower unit of a boat engine, and where the longitudinal slot has at least one ledge;
- an elastomeric insert adapted to fit in the longitudinal slot of the cavitation plate at the forward portion between the forward portion and the lower unit, and where the elastomeric insert has a tongue adapted to overlap said at least one ledge; and
- a filler piece to occupy space remaining in the longitudinal slot between the lower unit and the trailing edge.



5,588,392

RESIN TRANSFER MOLDING PROCESS

Francis V. Bailey, Racine, Wis., assignor to Outboard Marine Corporation
Filed Apr. 18, 1995, Ser. No. 423,783
Int. Cl.⁶ B63B 5/24

U.S. Cl. 114—357

21 Claims



1. A method for manufacturing, in a resin transfer molding process, a fiber-reinforced polymer object having first and second exterior surface portions, the method comprising the steps of:

- providing a first mold with an inner surface,
- placing dry reinforcement material on the first mold inner surface,
- providing a second mold including at least one flexible portion with an inner surface having the shape of the object first exterior surface portion, and the second mold also including at least one rigid portion with an inner surface having the shape of the object second exterior surface portion,
- placing the second mold over the dry reinforcement material to define a space between the first mold inner surface and the inner surfaces of the flexible and rigid portions,
- reducing the pressure, relative to ambient pressure, in the space between the molds,
- injecting resin into the space, and
- curing the resin.


5,588,393

COLLAPSIBLE PET BED

Eric W. Heilborn, 2216 1 St., Bellingham, Wash. 98225
Filed Jun. 19, 1995, Ser. No. 491,786
Int. Cl.⁶ A01K 1/035

U.S. Cl. 119—285

11 Claims



1. A pet bed which is collapsible as a unit for packaging, said bed comprising:

5,588,391

FIN WITH TRAILING EDGE FIXED FLAPS FOR SHIPS

Alain Tessandier, Le Havre, France, assignor to Societe Nouvelle des Ateliers et Chantiers du Harve, Le Havre, France
Filed May 17, 1995, Ser. No. 443,404
Claims priority, application France, Dec. 29, 1994, 94 15881
Int. Cl.⁶ B63B 1/22


U.S. Cl. 114—284

12 Claims

1. A fin with trailing edge fixed flaps for ships comprising a main fin to which is operatively associated at least one pair of fixed flaps of mean camber, said fixed flaps being located near a trailing edge of said main fin and placed symmetrically on a lower face and an upper face of said main fin, said main fin being equipped with end plane plates and struts on which are fixedly connected said at least one pair of fixed flaps,

wherein said at least one pair of flaps is placed so that tangents to said mean camber at said leading edge are parallel to a mean plane of said main fin.

a generally planar cushion member;
a resiliently collapsible wall member which at least partially surrounds said cushion member when said bed is in an expanded configuration; and
a fabric cover member, said cover member comprising:
a first enclosure enclosing said cushion member; and
a second enclosure enclosing said wall member;
said second enclosure being attached to said first enclosure at a junction along an edge thereof, at least a part of said junction being displaceable in a vertical direction relative to said wall member so as to permit said cushion member in said first enclosure to be tilted up as first and second portions of said wall member are pushed together, to a collapsed position in which said cushion member is substantially parallel to and sandwiched between said first and second portions of said wall member.



regions mounted on a common base each of the regions being provided with a drinking trough, the fluid containment regions being separated by slots extending across the base, the slots receiving the removable dividers to provide one fluid containment region for each section of the shipping container and to stabilize all of the drinking troughs through the contact of the dividers and the common base.

5,588,394


AUTOMATIC ANIMAL FEEDER

Thomas R. Balistreri, 2177 W. Forest La., Anaheim, Calif. 92804

Filed Sep. 1, 1995, Ser. No. 522,698
Int. Cl.⁶ A01K 5/02; 7/02

U.S. Cl. 119—51.11

12 Claims



1. An automatic dry feed and water animal feeder comprising: mounting means having a substantially rigid vertical structure on a horizontal base for resting on a flat surface;
feed storage means attached to the mounting means vertical structure for retaining a reserve of animal feed;
weight actuated feed measuring means in intimate relationship with the storage means for metering and dispensing a predetermined amount of feed and water from the storage means when weight is added;
animal feed access means directly beneath the measuring means for receiving feed from the measuring means while providing a convenient receptacle for an animal to approach the feed;
weight adding and timing means to sequence interval and duration of adding weight to the measuring means for automatic operation of the feeder; and
reset means to restore the measuring means to a replenished position after weight has been removed therefrom.

5,588,395

DRINKING TRAY FOR SMALL ANIMALS SHIPPED IN CONTAINERS

Eng-Hong Lee, 7 Tamarack Place, Guelph, Ontario, Canada
Filed Apr. 6, 1993, Ser. No. 43,488

Int. Cl.⁶ A01K 7/00

U.S. Cl. 119—72

5 Claims


1. In combination a shipping container for transport of small animals, the shipping container being divided into at least two sections by at least one removable divider, and a transport drinking tray, the drinking tray comprising a plurality of fluid containment

5,588,396
SPAWNING CASE FOR USE IN AN AQUARIUM
Nobuyuki Yoshida, Tokyo, Japan, assignor to Nihon Doubutsu Yakuhin Kabushikigaisya, Tokyo, Japan
Filed Apr. 21, 1995, Ser. No. 426,714
Claims priority, application Japan, May 17, 1994, 6-006539 U

Int. Cl.⁶ A01K 63/00

U.S. Cl. 119—252

5 Claims



3. A fish spawning case for disposition in an aquarium comprising:
a rectangular case body for disposition interiorly of an aquarium having water therein;
said case body having a bottom wall and side walls extending upwardly from said bottom wall;
said bottom wall having a plurality of passage openings and two opposing side walls of said case body having a plurality of passage openings for communicating with the interior thereof;
a filter removably mountable on an external surface of one of said opposing side walls of said case body;
said filter having an intake on a side thereof for fluid communication with said passage openings on said one of said opposing side walls and a discharge port on an upper portion thereof; and
said discharge port including means for selectively directing flow from said filter toward either the interior or the exterior of said case body.

5,588,397

BIRD PERCH APPARATUS


E. Kimble Johnakin, III, Alpharetta, Ga., assignor to Just Selling, Inc., Clermont, Ga.

Filed Feb. 17, 1995, Ser. No. 390,632

Int. Cl.⁶ A01K 31/12

U.S. Cl. 119—468

22 Claims



1. A bird perch apparatus for connection to a structure, the apparatus comprising:
an elongated first member,
wherein said first member includes
a first end,
a second end, and
an exterior first surface extending between said first end and said second end and including a first plurality of grits, and
wherein the elongated axis of said first member extends in a direction defined generally between said first end and said second end, and
a second member connected to said first member proximate to said second end and extending generally perpendicularly and substantially away from said first surface of said first member and said elongated axis for generally 360 degrees about said elongated axis, wherein said second member includes an exterior second surface including a second plurality of grits.

5,588,398

REMOTELY CONTROLLED DOG MUZZLE


Harvey S. Allen, II, 437 N. Olive, Orange, Calif. 92666; E. William Berke, 2949 Feather Hill, Orange, Calif. 92667, and Gary B. Erwin, Ocoee, Tenn., assignors to Harvey S. Allen, II; E. William Berke, both of Orange, Calif.; Ken Newgard, Kalispell, Mont., and Nicholas Vertucci, Irvine, Calif.

Filed May 15, 1995, Ser. No. 441,423

Int. Cl.⁶ A01K 29/00

U.S. Cl. 119—822

27 Claims



1. An apparatus for use with trained dogs comprising:

a stimulus module for producing stimuli perceptible by humans in the presence of the dog, said stimulus module being remotely actuable;
b. remote controller means for remotely actuating said stimulus module, and
c. means for removably attaching said stimulus module to the body of a dog, said means including:
i. a muzzle including a cup-shaped snout shield,
ii. means for attaching said muzzle to the body of a dog, and
iii. means for attaching said stimulus module to said muzzle.

5,588,399

FLUE FOR WATER HEATER


Thomas K. Kim, 1168 Forest Vale La., BB-8, Norcross, Ga. 30093

Filed Jun. 16, 1995, Ser. No. 491,263

Int. Cl.⁶ F22B 5/00

U.S. Cl. 122—17

6 Claims



1. A water heater comprising a water tank defining at least one flue opening through said water tank, heating means disposed beneath said water tank and generally aligned with said flue opening so the heat rising from said heating means will pass through said flue opening, said flue opening comprising at least a first section having a relatively large diameter and a second section having a smaller diameter than said first section, a step defined between said first section and said second section, said step consisting of the transition between said first section and said second section, said first section and said second section being coaxial, and wherein said step comprises a surface disposed at an acute angle with respect to the wall of said first section.

5,588,400

METHOD OF GENERATING STEAM IN A FORCED-THROUGH-FLOW BOILER

Ion Stefan, and Friedrich Cesnik, both of Gummersbach, Germany, assignors to L. & C. Steinmüller GmbH, Gummersbach, Germany

PCT No. PCT/EP94/00367, § 371 Date Dec. 2, 1994, § 102(e) Date Dec. 2, 1994, PCT Pub. No. WO94/18498, PCT Pub. Date Aug. 18, 1994

PCT Filed Feb. 9, 1994, Ser. No. 313,170


Claims priority, application Germany, Feb. 9, 1993, 43 036 13.9

Int. Cl.⁶ F22D 7/00

U.S. Cl. 122—406.1

5 Claims

1. A method of generating steam in a forced-through-flow boiler, said method including the steps of:
during operation, conveying water through a preheater and an evaporator, whereby for a forced-through-flow boiler operated with a flow of gas from which waste heat is to be extracted, said evaporator is divided into at least two sections, wherein when viewed in a direction of flow of said gas from which waste heat is to be extracted, a first one of said evaporator




5,588,402
CONTROL DEVICE FOR EXHAUST TIMING OF A TWO CYCLE ENGINE USING INTAKE SYSTEM PRESSURE
Thomas G. Lawrence, Clarkston, Mich., assignor to Chrysler Corporation, Auburn Hills, Mich.

Filed Nov. 6, 1995, Ser. No. 553,911

Int. Cl.⁶ F02B 75/02

U.S. Cl. 123—65 PE

7 Claims



sections is supplied with water at a beginning of a start-up phase and is included in a water circulation, while downstream from said first evaporator section when viewed in said direction of flow of said waste heat gas, a second one of said evaporator sections, starting from a dry state, is gradually supplied with water in a controlled manner until, in an operating state, water successively flows through both of said evaporator sections;

at least during said start-up phase, conveying a water-stream mixture from said first evaporator section to a separation tank, from which steam is withdrawn and separated feed water is supplied to said preheater, which is disposed downstream from said second evaporator section when viewed in said direction of flow of said waste heat gas; and

disposing a three-way valve in a connecting line between said preheater and said evaporator, with said three-way valve having a branch line that acts as a bypass line and leads to said first one of said evaporator sections.

5,588,401
SPARK IGNITION INTERNAL-COMBUSTION ENGINE
Yakihiko Matsumoto, and Hisashi Yokotaki, both of Wako, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Mar. 17, 1995, Ser. No. 405,248

Claims priority, application Japan, Mar. 18, 1994, 6-072833

Int. Cl.⁶ F02D 7/00

U.S. Cl. 123—41.31

30 Claims



1. A spark ignition internal-combustion engine comprising an ignition coil mounted on an engine body in the vicinity of a distributor fixedly mounted directly on said engine body, said ignition coil being disposed directly behind an opening section of a radiator fan.

5,588,403
RACK AND PINION VALVE OPERATING SYSTEM
Douglas J. Williams, 25940 Colorette Ct., Valencia, Calif. 91335
Continuation of Ser. No. 160,448, Dec. 1, 1993, abandoned, which is a continuation of Ser. No. 971,948, Nov. 4, 1992, abandoned. This application May 25, 1995, Ser. No. 450,013

Int. Cl.⁶ F01L 9/04; 1/30

U.S. Cl. 123—90.11

2 Claims

1. A valve assembly for an internal combustion engine having a crankshaft for moving a piston within a cylinder, the cylinder having a bore, at least one opening into the bore, and a head interconnected at the cylinder opening and the head having a cavity with the cavity having at least one opening, comprising:


a) a valve disposed within the cavity of the head and having a valve stem and a valve head, wherein the valve head is positioned adjacent the cylinder opening for being moved between:

1) an open position of the cylinder opening, wherein, gas flow is enabled between the cylinder bore and the head; and

2) a closed position of the cylinder opening, wherein, gas flow is disabled between the cylinder bore and the head;

b) sensor means for determining the position of the crankshaft and producing a position signal in response thereto;

c) command mechanism, coupled to the sensor means, for processing the position signal and producing a variable valve drive signal in response thereto; and



d) an actuator electrically coupled to the command mechanism, for intermittently and variably moving the valve between the open and closed position in response to the variable valve drive signal received from the command mechanism, the actuator including a rack and pinion gear system for transforming rotary motion from a motor into linear motion of the valve, the valve being connected with a rack moving in a linear non-rotatable motion, and the pinion engaging with the rack and being coupled to said motor to rotate the pinion.


5,588,404
VARIABLE CAM PHASER AND METHOD OF ASSEMBLY
Thomas H. Lichti, Rochester; Daniel R. Cuatt; Mark A. Shost, both of Henrietta; Ronald A. Waydelis, Rochester, and Michael J. Fox, Stafford, all of N.Y., assignors to General Motors Corporation, Detroit, Mich.

Filed Dec. 12, 1994, Ser. No. 353,776

Int. Cl.⁶ F01L 1/344

U.S. Cl. 123—90.17

18 Claims



1. A variable cam phaser including coaxial drive and driven members drivingly connected by a first annular phase control piston having inner and outer helical splines of varying lead engaging respective mating splines of said members, the piston being axially movable to vary the phase relation between said drive and driven members, force means operative to act against the piston for moving the piston axially, and the improvement comprising:

one of said drive and driven members including a hub provided with outer helical splines as part of said mating splines and a hub flange supporting the hub; and

locking means operative in an unlocked position to allow angular adjustment of said hub on said hub flange after assembly with the other of said drive and driven members to provide a selected angular orientation of said drive and driven members, said locking means being movable to a locked position wherein it is operative to maintain said angular orientation until installation of the cam phaser on a camshaft.

5,588,405
ARRANGEMENT OF OIL PASSAGE TO VALVE SYSTEM
Atsushi Sawa, and Hiroyuki Kawakubo, both of Saitama, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jun. 7, 1995, Ser. No. 476,571

Claims priority, application Japan, Dec. 28, 1994, 6-337588

Int. Cl.⁶ F01M 5/00; 9/10

U.S. Cl. 123—90.33

20 Claims



1. An arrangement of oil passages for a valve system for an internal combustion engine, the engine having a cylinder block and a cylinder head, the arrangement comprising oil passages extending to a valve system of the engine, at least one of the oil passages being formed integrally with the cylinder block and the cylinder head, the at least one oil passage formed integrally with the cylinder block and cylinder head being disposed along outer surfaces of the cylinder block and cylinder head, a valve system drive transmission being disposed between the at least one oil passage and a combustion chamber of the engine.

5,588,406
STRUCTURE FOR LUBRICATING CAM SLIDING SURFACE IN AN INTERNAL COMBUSTION ENGINE
Katsuhiko Ito; Hideo Kobayashi; Yukio Ishiuchi, and Toshio Shlmada, all of Saitama, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 13, 1995, Ser. No. 501,863

Claims priority, application Japan, Jul. 13, 1994, 6-184101

Int. Cl.⁶ F01M 9/10; 1/06; F01L 1/04

U.S. Cl. 123—90.34


17 Claims

9. A lubricating section for a cam sliding surface in an internal combustion engine comprising:

a cam shaft having at least one cam surface defining a base circle for operatively imparting motion to a cam follower;


at least one recessed portion extending in an axial direction of said cam shaft, said recessed portion being formed on said base circle of said cam surface;

projecting ribs extending across a predetermined circumference of said cam shaft for directing lubrication into said recessed portion.




5,588,407
RECIPROCATING PISTON ENGINE WITH WEIGHT COMPENSATION
Mathias von Essen, Alsdorf; Christoph Bollig, Stolberg, and Werner Bick, Würselen, all of Germany, assignors to FEV Motorentechnik GmbH & Co. KG, Aachen, Germany
Filed Dec. 1, 1994, Ser. No. 352,806

Claims priority, application Germany, Dec. 1, 1993, 9318308 U; Apr. 29, 1994, 9407145 U
Int. Cl.⁶ F02B 75/06
U.S. Cl. 123—192.2 12 Claims



1. A reciprocating piston engine, comprising: an engine housing having at least one piston cylinder formed therein;
- a piston located within the piston cylinder and being movable in a back-and-forth motion therein;
- a crankshaft connected to said piston and being driven by said piston to rotate about an axis;
- a cam disc connected to said crankshaft so as to rotate therewith, said cam disc having a selected control profile;
- at least one compensating weight attached to said engine housing and being in engagement with the control profile of said cam disc, said compensating weight being driven by said cam disc in a predetermined back and forth motion as a function of the rotation of the crankshaft so as to compensate for at least one of inertia forces and moments of inertia occurring in the piston engine; and
- at least one torsion spring connected to said compensating weight and urging said compensating weight in a direction of said cam disc to maintain a constant contact between the control profile of said cam disc and said compensating weight.


5,588,408
ENGINE UNIT
Katsumi Koriyama, Nagoya, Japan, assignor to Ryohi Limited, Tokyo, Japan
Filed Dec. 21, 1995, Ser. No. 576,299
Claims priority, application Japan, Dec. 22, 1994, 6-336145
Int. Cl.⁶ F01M 9/06
U.S. Cl. 123—196 W 6 Claims



1. An engine unit comprising: a housing defining a crank chamber and a cam chamber which is communicated with said crank chamber therein;
- a crank shaft disposed in the crank chamber to be rotatable so as to extend in a perpendicular direction in a state of use;
- a piston-cylinder assembly mounted to the housing and including a cylinder and a piston operatively connected to the crank shaft;
- a valve mechanism operatively connected to the piston-cylinder assembly for sucking and discharging air in the cylinder;
- a valve moving mechanism for driving the valve mechanism so as to open or close the same, said valve moving mechanism including a push-rod means;
- a push-rod cover member covering the push-rod means with a space therebetween;
- a rocker chamber connected to the push-rod cover so as to communicate with said space;
- a drain passage means disposed between said rocker chamber and said crank chamber so as to establish communication therebetween with an inclination in the state of use;
- an agitation means mounted to said crank shaft so as to agitate and splash a lubrication oil in the crank chamber; and
- a guide means provided for the housing for guiding the splashed lubrication oil to said valve moving mechanism.


5,588,409
IGNITION TIMING CONTROL DEVICE FOR AN ENGINE
Hiroyuki Mizuno, Toyota; Akio Okamoto, Takahama, and Suehiro Kubo, Toyota, all of Japan, assignors to Toyota Jidosha Kabushiki Kaisha, Toyota, Japan
Filed Jul. 3, 1995, Ser. No. 497,894
Claims priority, application Japan, Jul. 19, 1994, 6-166924; Apr. 28, 1995, 7-106442
Int. Cl.⁶ F02D 41/16; F02P 5/15
U.S. Cl. 123—339.11 13 Claims

1. An ignition timing control device for an engine, said engine comprising an inlet air passage and a throttle valve disposed on said inlet air passage, an inlet air bypass passage connecting the portions of the inlet air passage upstream and downstream of the throttle valve for supplying inlet air to the engine without passing through the throttle valve, and an idle speed control means for controlling the idle speed of the engine by adjusting the amount of air passing through the inlet air bypass passage, wherein said ignition timing control device comprises: an engine load condition detecting means for detecting the load condition of the engine;
- a failure detecting means for detecting the failure of the idle speed control means; and




an ignition retarding means for retarding the ignition timing of the engine by an amount determined in accordance with the engine load conditions detected by the engine load condition detecting means when the idle speed control means fails.

5,588,410
AIR-FUEL RATIO CONTROL METHOD
Hiroki Tamura, Naoki Yamazaki, Akihiro Takeyama; Hitoshi Kamura, all of Tokyo, and Tetsuo Maeda, Himeji, all of Japan, assignors to Mitsubishi Jidosha Kogyo Kabushiki Kaisha, and Mitsubishi Denki Kabushiki Kaisha, both of Tokyo, Japan
PCT No. PCT/JP95/00680, § 371 Date Oct. 12, 1995, § 102(e) Date Oct. 12, 1995, PCT Pub. No. WO95/27846, PCT Pub. Date Oct. 19, 1995
PCT Filed Apr. 6, 1995, Ser. No. 532,669
Claims priority, application Japan, Apr. 7, 1994, 6-069265
Int. Cl.⁶ F02D 41/14
U.S. Cl. 123—416 20 Claims




1. An air-fuel ratio control method for selecting a stoichiometric air-fuel ratio and a lean air-fuel ratio as a target air-fuel ratio for an engine to control the air-fuel ratio of the engine depending on the selected target air-fuel ratio, said engine having multiple cylinders, variable ignition timing control, and variable intake air flow control, said method comprising: changing said air-fuel ratios for each said cylinder over respectively offset timing intervals during said changing of said air-fuel ratio to said target air-fuel ratio; and varying intake air flow during said change.

5,588,411
METHOD FOR CONTROLLING AN INTERNAL COMBUSTION ENGINE WITH EXTERNAL IGNITION SYSTEM AND WITH A FUEL INJECTION SYSTEM
Peter Kreuter, and Peter Heuser, both of Aachen, Germany, assignors to Meta Motoren- und Energie-Technik GmbH, Herzogenrath, Germany
Filed Jan. 18, 1996, Ser. No. 599,435
Claims priority, application Germany, Jan. 18, 1995, 195 01 386.7
Int. Cl.⁶ F02P 5/00
U.S. Cl. 123—418 24 Claims



1. A method for controlling power output of an internal combustion engine with an external ignition system; said method comprising the steps of: providing at least one inlet valve for each cylinder of the internal combustion engine for determining the charge input of a combustion chamber during an intake stroke of the internal combustion engine;
- providing a fuel injection system for injecting, in an injection step, fuel into the combustion chamber;
- setting with a control device a relative phase position between a first and a second cam shaft operating at identical rpm for determining an opening function of the inlet valve, the opening function being defined by the stroke and duration of an open state of the inlet valve;
- adjusting a position of the control device according to an accelerator pedal position and at least one operational parameter of the combustion engine; and
- controlling at least one of the ignition timing and the amount of injected fuel directly according to the position of the control device and the rpm of the internal combustion engine.

5,588,412
VARIABLE INJECTION HOLE TYPE FUEL INJECTION NOZZLE
Shinya Nozaki, Saitama, Japan, assignor to Zexel Corporation, Tokyo, Japan
Filed Nov. 22, 1995, Ser. No. 562,168
Claims priority, application Japan, Nov. 25, 1994, 6-314338
Int. Cl.⁶ F02M 37/04
U.S. Cl. 123—496 7 Claims



1. A variable injection hole type fuel injection nozzle, comprising:

a nozzle needle having a seat portion;
a nozzle body into which said nozzle needle is inserted, said nozzle body having a bottomed hole for guiding pressurized fuel to a leading end portion of said nozzle needle below the seat portion of said nozzle needle, and at least first and second injection hole groups at axially different first and second positions in a side wall of the bottomed hole, respectively, said first injection hole group having a plurality of injection holes being different in diameter from those of said second injection hole group;

a spring;

a spool valve having a valve portion which passes through an axial center of said nozzle needle and a leading end portion fitted into the bottomed hole of said nozzle body, said valve portion being urged by said spring so that a lower end of said valve portion abuts against a base of said bottomed hole in a normal condition, said valve portion defining a fuel passage therein, said fuel passage communicating with said first injection hole groups in the normal condition and communicating with said second injection hole group at a position where said valve portion is displaced axially against a force of said spring on receiving the pressure of the pressurized fuel; and
braking means arranged in an upper region of said spool valve for selectively securely holding said valve portion of said spool valve at one of said first and second positions.

5,588,413

ENGINE ASSEMBLY WITH LEAF SPRING CAM FOLLOWER


Dwight V. Stone, East Peoria, Ill.; Douglas A. Long, Delphi, Ind., and Jose M. Salazar-Vior, Washington, Ill., assignors to Caterpillar Inc., Peoria, Ill.

Filed Mar. 14, 1995, Ser. No. 404,025

Int. Cl.⁶ F02M 37/04

U.S. Cl. 123—508

15 Claims



1. An engine assembly comprising:
an engine block having a cylinder disposed therein;
a fuel injector for periodically injecting fuel into said cylinder;
a pushrod;
a rocker arm disposed for periodic movement and having a first end and a second end, said first end of said rocker arm being disposed adjacent said fuel injector and said second end of said rocker arm being disposed adjacent said pushrod;
a cam shaft having a cam; and
a cam follower operatively coupled between said cam and said pushrod, said cam follower having a first portion which supports a cam roller and a second portion which makes contact with said pushrod, said second portion of the cam follower comprises a flexible plate, said first and second portions of said cam follower being spring-biased with respect to each other.

5,588,414 CONSTRUCTION FOR MAINTAINING ASSEMBLED AXIAL INTEGRITY OF AN ELECTRICALLY ACTUATED VALVE


Bernard J. Hrytzak, Chatham, Canada; Takeshi Gomi, Saitama, Japan; Hirotomi Nemoto, Saitama, Japan, and Yoshio Yamamoto, Saitama, Japan, assignors to Siemens Electric Limited, Ontario, Canada, and Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Aug. 29, 1995, Ser. No. 520,543

Int. Cl.⁶ F02M 25/07; F16K 37/00; H01F 7/08

U.S. Cl. 123—571

13 Claims



1. An electric exhaust gas recirculation (EGR) valve for an internal combustion engine comprising an enclosure including a base, an entrance at which engine exhaust gas to be recirculated enters said base, a passage that extends through said base for conveying engine exhaust gas that has entered said entrance, an exit at which engine exhaust gas that has passed through said passage exits said base, a valve mechanism disposed within said base for controlling flow through said passage, an electric actuator disposed within said enclosure for operating said valve mechanism, said enclosure comprising a shell having a sidewall terminating at an axial end axially beyond said electric actuator relative to said valve mechanism, said axial end comprising a radially outwardly directed rim, a closure closing said axial end and having a rim of polymeric material disposed against said rim of said axial end of said shell sidewall, and means for clinching said rims in assembly comprising a circular ring having a sidewall disposed radially outward of and axially overlapping both said rims, said circular ring comprising a first flange directed radially inwardly of said ring's sidewall to radially overlap said rim of said closure and a second flange directed radially inwardly of said ring's sidewall to radially overlap said rim of said axial end of said shell sidewall, and said circular ring further comprising a plurality of circumferentially arranged sharp pointed barbs that bite into the polymeric material of said closure rim, and said ring exerting axial forces forcing said rims axially together.

5,588,415

ENGINE MANAGEMENT SYSTEM

Steven R. Ahern, Claremont, Australia, assignor to Orbital Engine Company Pty. Limited, Balcatta, Australia
Division of Ser. No. 87,712, Jul. 14, 1993, Pat. No. 5,427,083.
This application Jun. 7, 1995, Ser. No. 475,346


Claims priority, application Australia, Jan. 14, 1991, PK4177

Int. Cl.⁶ F02M 51/00

U.S. Cl. 123—676

6 Claims

1. A method for controlling fuel supplied to an internal combustion engine based upon determination of induced air mass per



cylinder per cycle therethrough (IACC) without need for an air flow sensor, comprising the steps of:

determining engine operating characteristics from tests conducted on a representative sample of a family of engines at ambient conditions and at selective elevated charge air temperatures (T_{CH}) while keeping all other conditions equal, repeating these tests at a series of engine speed and load combinations, taking measurements of charge temperature (T_{CH}), and developing therefrom look-up maps so that T_{CH} and a selected load demand coefficient K_{LD} can be looked up for any combination of engine speed and load;

conducting further tests on said representative sample engine and taking measurements of at both wide open throttle (WOT) and over a range of engine speeds at ambient conditions and at induced exhaust back pressures respectively and, using these measurements and the previously developed look-up maps of T_{CH} and K_{LD} , developing look-up maps of cylinder displacement constant (K_1) and exhaust pressure coefficient (K_2) over said speed range;

inputting signals to a memory of ECU look-up maps of respective coefficients relating to P_{AT} , P_{EX} and T_{CH} for selected engine speeds within said range of engine speeds corresponding to an operating speed range of an operational engine;

inputting signals to memory of the ECU look up maps of coefficients relating IACC_{WOT} to IACC at selected load demands below WOT at each said selected speed;

providing input signals to the ECU of T_{CH} , P_{AT} and P_{EX} from said sensors while operating engines of said family;

calculating IACC_{WOT} from said input signals and said look up maps provided said ECU;

calculating based upon IACC_{WOT}, a value for fuel per cylinder per cycle to be delivered to the engine (FPC_{DELV});

providing a signal from said ECU to the engine of FPC_{DELV} to control the delivery of the fuel;

subsequent to said tests, operating engines of said family with sensors provided to obtain signals indicating respectively engine load, engine speed, charge air temperature (T_{CH}), ambient pressure (P_{AT}), and exhaust pressure (P_{EX});

calculating from sensor signals T_{CH} , P_{AT} , P_{EX} , and using values from look-up maps of K_1 , K_2 , and T_{CH} based on engine load and engine speed, a value for IACC_{WOT} in accordance with the algorithm

$$IACC_{WOT} = \frac{K_1 \times D_{CY} \times P_{AT} [1 - K_2 (P_{EX})^2] P_{AT}}{T_{CH} \times T_{CH}}$$

wherein IACC_{WOT} is induced air mass per cylinder per cycle at wide open throttle and D_{CY} is a calibration coefficient previously determined experimentally;

looking up a value of K_{LD} based upon load and speed, and calculating a value of IACC_{LD} for existing engine operating conditions according to $IACC_{LD} = IACC_{WOT} \times K_{LD}$; and

controlling fuel supply to the engine based upon said calculated IACC_{LD}.

5,588,416 FUEL CONTROL SYSTEM FOR GASEOUS FUELED ENGINE


Toshio Suzuki, and Yoshikatsu Iida, both of Iwata, Japan, assignors to Yamaha Hatsudoki Kabushiki Kaisha, Iwata, Japan


Filed Mar. 9, 1995, Ser. No. 401,344

Claims priority, application Japan, Mar. 15, 1994, 6-044235
Int. Cl.⁶ F02D 41/14

U.S. Cl. 123—684

62 Claims






5,588,418
SAW ASSEMBLY WITH HANDLE-ACTUATED GUIDE MECHANISM
 William K. Holmes, Simi Valley; Albert E. Joneikis, Long Beach, and Kwok W. Wong, Walnut, all of Calif., assignors to Boart Longyear Company, Salt Lake City, Utah
 Filed Jan. 26, 1995, Ser. No. 390,306
 Int. Cl.⁶ B28D 1/04

U.S. Cl. 125—13.01

31 Claims




1. A saw assembly comprising:
 a track mountable to a wall, floor or ceiling;
 a carriage guided by the track for movement along the length of the track, the carriage including a cutting mechanism and a carrying handle for manually grasping the carriage; and
 a guide mechanism removably securing the movable carriage to the track, the guide mechanism comprising a pair of guide elements mounted on opposite sides of the carriage for pivotal movement in substantially opposite directions between an engaged position, in guiding contact with the track, and a retracted position, out of contact with the track, by movement of said carrying handle.

5,588,419
SEMICONDUCTOR WAFER HUBBED SAW BLADE
 Charles N. Ekbre, Santa Rosa, Calif., assignor to Dynatex International, Santa Rosa, Calif.
 Filed Dec. 16, 1994, Ser. No. 357,504
 Int. Cl.⁶ B28D 1/04

U.S. Cl. 125—15

4 Claims

1. A saw blade comprising in combination:




a circular aluminum blank for attaching to a saw blade arbor at a central aperture and a circular periphery defining a side for holding the saw blade;
 a cutting rim bounded by peripheral sides, the cutting rim and the peripheral sides having plated nickel embedded abrading particles with abrading particles exposed on the peripheral sides of the cutting rim;
 a copper substrate having a first opposite side and a second opposite side with the first opposite side fastened to the circular aluminum blank at the circular periphery defining a side and to one of the peripheral sides of the cutting rim on the second opposite side, the copper substrate having deposited abrading particles extending across an interface of the copper substrate with the cutting rim at the second opposite side.

5,588,420
CHARCOAL-BURNING OUTDOOR HEATER
 Curtis M. Dickson, 1029 Lofty Pine Dr., Columbia, S.C. 29212
 Filed Jun. 2, 1995, Ser. No. 459,819
 Int. Cl.⁶ A47J 37/00

U.S. Cl. 126—25 R

13 Claims



1. A heater, comprising:
 a rectangular body having an interior, said body including first ledges formed on said interior of said body, said first ledges running the periphery of said body;
 second ledges formed on said interior of said body;
 first venting means for venting said interior of said body, said first venting means positioned between said first ledges and said second ledges of said body.

and
 a bottom;
 a lid dimensioned to fit over said body, said lid having second venting means for venting said interior of said body when said lid is on said body; and
 a charcoal-supporting grill inside said body resting on said second ledges.

5,588,421
HEAT-INSULATING VIEWING WINDOW OR VIEWING DOOR FOR AN APPARATUS HAVING AN INTERIOR TEMPERATURE DEVIATING FROM THE AMBIENT TEMPERATURE THEREOF

Dietrich Busch, Simmern, and Roland Leroux, Stadacken-Elsheim, both of Germany, assignors to Schott Glaswerke, Mainz, Germany


Filed Sep. 29, 1994, Ser. No. 315,116

Claims priority, application Germany, Sep. 29, 1993, 43 33 033.9

U.S. Cl. 126—200

Int. Cl.⁶ F23M 7/00

19 Claims



1. A heat-insulating window in a door for an apparatus operable in an ambient atmosphere having a first temperature, the apparatus having an interior cavity at a second temperature deviating from said first temperature, said window in a door comprising:

a first plate having a side in contact with the ambient atmosphere;
 a second plate having a side facing toward said interior cavity;
 a frame common to said first and second viewing plates for holding said plates in spaced relationship to each other so that said plates define an intermediate space therebetween;
 a third plate disposed in said intermediate space;
 mounting means for mounting and holding said third plate in position between said first and second plates;
 said third plate having a peripheral edge;
 said mounting means being an elongated spacing member extending along said peripheral edge and joining said third plate to said first plate;
 said elongated spacing member being a compressible tube;
 said tube having an annular cross section and being defined by a wall having a substantially uniform thickness;
 said first and third plates and said compressible tube conjointly defining an enclosure containing a gas which expands to increase pressure in said enclosure in response to a change of said second temperature relative to said first temperature;
 a temperature-resistant adhesive for joining said compressible tube, said first plate and said third plate to each other; and
 said tube having an opening formed therein allowing gas in said tube to escape whereby said tube collapses to compensate for the increase in pressure of said gas contained in said enclosure.

5,588,422
METHODS AND PHARMACEUTICAL COMPOSITIONS FOR ENHANCED CARDIOPULMONARY RESUSCITATION

Keith G. Lurie, and Barbara S. Gold, both of Minneapolis, Minn., assignors to Regents of the University of Minnesota, Minneapolis, Minn.

Filed Nov. 17, 1992, Ser. No. 977,498


Int. Cl.⁶ A61M 15/00

U.S. Cl. 128—200.24

6 Claims

1. A method for resuscitating a patient suffering from cardiac arrest, said method comprising:

(a) actively inducing venous blood transport into the heart and arterial blood transport from the heart;




(b) ventilating the patient's lungs;

(c) administering to the patient concurrently with said inducing and ventilating steps, a bolus of medicament comprising epinephrine and nitroglycerin in amounts of from 1 mg to 10 mg and 25 µg to 200 µg, respectively.

5,588,423
HUMIDIFIER CHAMBER
 Malcolm D. Smith, Auckland, New Zealand, assignor to Fisher & Paykel Limited, Auckland, New Zealand
 Filed Sep. 18, 1995, Ser. No. 529,523
 Claims priority, application New Zealand, Aug. 20, 1994, 264485

U.S. Cl. 128—203.26

12 Claims



1. A respiratory humidifier chamber for attachment to a heater base, said chamber comprising:

a closed watertight vessel having a heat conductive base,
 said vessel having a gases inlet for receiving gases from a ventilator and a gases outlet for delivering humidified gases to a patient,
 a thermal insulating partition inside said vessel dividing said vessel into a first heated reservoir, and a second supply reservoir, said first reservoir defined by at least said partition and a first portion of said vessel, said first portion including said heat conductive base, said second reservoir defined by at least said partition and a second portion of said vessel, said second portion not including said heat conductive base,
 at least one liquid communication path between said first and second reservoirs at or adjacent the bottom of said partition, and
 at least one gases communication path between said first and second reservoirs at or adjacent the top of said partition.

5,588,424


BRONCHIAL BLOCKER ENDOTRACHEAL APPARATUS
Steven R. Insler, Cleveland Heights, and Erik J. Kraenzler,
Brecksville, both of Ohio, assignors to The Cleveland Clinic
Foundation, Cleveland, Ohio

Filed Jun. 28, 1995, Ser. No. 495,823

Int. Cl.⁶ A61M 16/00

U.S. Cl. 128—207.15

20 Claims



1. An endotracheal apparatus for insertion through the mouth and into the trachea of a patient for ventilating one lung and blocking the other lung comprising:

- a first elongated flexible tube having an external wall portion, a proximal end and a distal end, the distal end being positioned in the trachea when in use and adapted for ventilating air;
- a second elongated flexible tube, separate from the first tube, having a proximal end and a distal end, an external wall portion of the second elongated flexible tube being closely joined in a side-by-side relation to said external wall portion of the first elongated flexible tube, the second elongated flexible tube for receiving an endobronchial blocker;
- a first inflatable and deflatable cuff extending about the first and second elongated flexible tubes toward the distal ends of the first and second tubes, the first inflatable and deflatable cuff being positioned and operable when inflated to engage the trachea;
- an endobronchial blocker comprising an elongated catheter having a proximal end and a distal end, being slidably receivable in the second elongated flexible tube, the elongated catheter having an inflatable and deflatable cuff disposed about the distal end of the elongated catheter; and,
- an air passage defined in a wall of the first elongated flexible tube and terminating within the first inflatable and deflatable cuff.

5,588,425

METHOD AND APPARATUS FOR DISCRIMINATING BETWEEN VALID AND ARTIFACTUAL PULSE WAVEFORMS IN PULSE OXIMETRY

Marvin A. Sackner, Miami Beach, and Dana M. Inman, Miami, both of Fla., assignors to Nims, Incorporated, Miami Beach, Fla.


Continuation of Ser. No. 66,593, May 21, 1993, abandoned. This application May 1, 1995, Ser. No. 431,469

Int. Cl.⁶ G06F 15/42

U.S. Cl. 128—632

29 Claims

1. A method for discriminating between artifactual and non-artifactual pulse waveforms generated by a pulse oximeter for



validating indicated arterial oxygen saturation levels of a subject also generated by the pulse oximeter, the pulse waveforms each being defined, at least partially, by a systolic upstroke time and a diastolic time, the method comprising:

- selecting a predetermined range of a first parameter indicative of a correct pulse waveform, said first parameter being selected from the group consisting of systolic upstroke times and diastolic times;
- receiving from the pulse oximeter, in a first receiving step, pulse waveforms;
- receiving from the pulse oximeter, in a second receiving step, signals indicative of the arterial oxygen saturation level of the subject;
- measuring said first parameter of the received pulse waveforms, wherein said measuring step comprises measuring the systolic upstroke times corresponding to received pulse waveforms;
- comparing the measured systolic upstroke times to a predetermined range of, systolic upstroke times;
- rejecting as artifactual any of the pulse waveforms having a systolic upstroke time outside said predetermined range of systolic upstroke times; and
- determining the arterial oxygen saturation levels indicated by the received signals corresponding temporally to the non-rejected pulse waveforms.

5,588,426

Patent Not Issued For This Number

5,588,427

ENHANCEMENT OF PHYSIOLOGICAL SIGNALS USING FRACTAL ANALYSIS

Jonathan Tien, Redmond, Wash., assignor to SpaceLabs Medical, Inc., Redmond, Wash.


Filed Nov. 20, 1995, Ser. No. 559,846

Int. Cl.⁶ A61B 5/00

U.S. Cl. 128—633

30 Claims

11. A system for the enhancement of physiological signals



5,588,429

PROCESS FOR PRODUCING OPTIMAL CURRENT PATTERNS FOR ELECTRICAL IMPEDANCE TOMOGRAPHY


David Isaacson, Latham, and Margaret Cheney, Troy, both of N.Y., assignors to Rensselaer Polytechnic Institute, Troy, N.Y.

Continuation-in-part of Ser. No. 734,591, Jul. 23, 1991, Pat. No. 5,381,333, Ser. No. 727,075, Jul. 9, 1991, Pat. No. 5,390,110, and Ser. No. 132,457, Oct. 6, 1993, Pat. No. 5,544,662. This application Oct. 5, 1994, Ser. No. 317,678

Int. Cl.⁶ A61B 5/05

U.S. Cl. 128—734

2 Claims



1. In an electrical impedance tomography system that includes a body with an array of electrodes on its surface, means for injecting spatial patterns of current into the electrodes consecutively, subject to a limitation on the maximum current in any electrode, and means for measuring the real and reactive voltage components at all the electrodes, an improved method for finding the values of an unknown distribution of permittivities from which images may be formed, comprising:

- (a) selecting an arbitrary guessed permittivity distribution and applying an arbitrary guessed set of current patterns to the electrodes to generate a voltage pattern on the array for each current pattern;
- (b) measuring all electrode voltages for each current pattern applied which are in quadrature with the current pattern;
- (c) calculating values of all theoretical voltages that should have appeared on the electrodes for the body due to the arbitrary set of guessed current patterns and the arbitrary guessed permittivity distribution;
- (d) calculating a new set of current patterns based on differences between the measured and calculated voltage values;
- (e) calculating the differences between electrode currents of the arbitrary set of current patterns and the calculated new set of current patterns, to form current differences;
- (f) if any of the current differences are greater than a selected tolerance, applying the new set of current patterns to the electrode array and repeating steps (b) to (e);
- (g) when the current differences are smaller than the selected tolerance, testing whether any of the voltage differences between the measured and calculated values at the electrodes, using the last set of current patterns, are larger than a predetermined value;
- (h) if so, computing a new permittivity distribution as a function of the new set of current patterns and the measured voltage values;
- (i) repeating steps (b) through (f) using the new permittivity distribution to replace the previously assumed distribution in order to find a set of current patterns that better distinguishes the actual permittivity distribution from the new one; and

representative of a physiological phenomenon in a subject, the system comprising:

- a sensor positioned in proximity with the subject to detect physiological signals and to generate signals indicative of said detected physiological signals, said detected signals having a first portion arising from the physiological phenomenon and a second portion arising from an interference source;
- an analyzer to analyze and determine a complexity value for said generated signals, said complexity value being indicative of a complexity of said generated signals; and
- a processor, responsive to said complexity value, to generate a processed signal

5,588,428

METHOD AND APPARATUS FOR NON-INVASIVE VOLUME AND TEXTURE ANALYSIS


Daniel J. Smith, Stow, and Shailesh Bhat, Akron, both of Ohio, assignors to The University of Akron, Akron, Ohio

Filed Apr. 28, 1993, Ser. No. 54,797

Int. Cl.⁶ G06F 15/00, A61B 5/05, 6/00

U.S. Cl. 128—653.1

19 Claims



1. An apparatus to image a three dimensional surface for analysis of surface profile, volume or surface texture comprising:

- a laser source for emitting a predetermined wavelength beam which is reflected off the surface being imaged,
- a laser detecting means positioned relative to said laser source for receiving the reflected beam to generate a first signal corresponding to the amount of laser energy reflected off said surface, wherein said reflected beam is indicative of changes in the depth of said surface relative to said laser source,
- a sound source having a frequency less than 1 MHz for generating a coherent beam of sound waves which are reflected off said surface, said sound source not being in physical contact with said surface,
- a sound detecting means positioned relative to said sound source for receiving reflected sound waves to generate a second signal corresponding to the amount of sound waves reflected off said surface, wherein the reflected sound waves are indicative of at least the texture of said surface, and
- a process means to receive and independently process said first and second signals and to use said first and second signals to generate an image of said surface.

5,588,436

PULSED DOPPLER PROBE


Krishna Narayanan, Pittsburgh; Vasant Padmanabhan, Monroeville; Fredrick J. Shipko, Spring Church; Louis Goode, Evans City, all of Pa., and Neal E. Fearnot, West Lafayette, Ind., assignors to Cook Pacemaker Corporation, Leechburg, Pa., and MED Institute, West Lafayette, Ind.

Filed Oct. 11, 1995, Ser. No. 540,852

Int. Cl.⁶ A61B 8/00

U.S. Cl. 128—662.03

20 Claims



1. A pulsed Doppler probe (10) for monitoring blood flow within a blood vessel (12), comprising:
 - a plurality of longitudinally extending electrically conductive wires (26) having distal ends (28);
 - an ultrasonic transducer (18) operatively connected to the distal ends (28) of the wires (26), the transducer (18) having an operative surface (20);
 - means (22) having a longitudinal axis (38) and fixing the orientation of the operative surface (20) of the ultrasonic transducer (18) with respect to at least one of the longitudinally extending electrically conductive wires and, the longitudinal axis (38);
 - a band (44) adapted to encircle the blood vessel (12); and
 - remotely operable means (46) for detachably securing the orientation fixing means (22) to the band (44) so that the ultrasonic transducer (18) is positioned adjacent to the blood vessel (12); whereby remote operation of the securing means (46) permits withdrawal of the ultrasonic transducer (18), wires (26) and orientation fixing means (22) from the blood vessel (12) while leaving the band (44) encircled about the blood vessel (12).

5,588,437

BLOOD FLOW DETERMINATION

Phillip O. Byrne, and Timothy J. H. Essex, both of Newcastle Upon Tyne, England, assignors to British Technology Group Limited, London, England

Continuation of Ser. No. 768,862, Sep. 27, 1991, abandoned.

This application Feb. 16, 1994, Ser. No. 197,442


Claims priority, application United Kingdom, Mar. 29, 1989, 8907101

Int. Cl.⁶ A61B 5/02

U.S. Cl. 128—691

19 Claims

1. A method of determination of blood flow to produce a map of said blood flow, said method comprising the steps of:
 - scanning a rod of laser light in two directions over an area of a surface beneath which area of the surface blood flow in a vessel or vascular bed is to be determined,
 - collecting light returning from the rod of light scattered by the surface and by blood flowing beneath the surface,
 - measuring a spectrum of frequencies in said collected light,
 - determining, from differences in said frequencies in said spectrum, blood flow in a vessel or vascular bed beneath said surface, and
 - producing from said determined blood flow the map of blood flow for a given area of said surface.



5,588,438

SYSTEM AND METHOD FOR CONTROLLING THE TEMPERATURE OF A CATHETER-MOUNTED HEATER


Russell C. McKown, Dallas; Michael D. Quinn, and Mark L. Yelderman, both of Plano, all of Tex., assignors to Interfl Medical, Inc., Plano, Tex.

Division of Ser. No. 334,443, Nov. 4, 1994, which is a continuation of Ser. No. 833,013, Feb. 10, 1992, abandoned, which is a continuation-in-part of Ser. No. 647,578, Jan. 29, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 473,738

Int. Cl.⁶ A61B 5/00

U.S. Cl. 128—692

16 Claims



1. A heater resistance verification system, comprising:
 - (i) means for measuring, in vivo, a temperature of blood when the blood is in contact with a thermomodulation catheter;
 - (ii) a power supply for supplying electric power to an electric resistance-type heater element;
 - (iii) a power monitor for monitoring an amount of electric power that is supplied to the electric resistance-type heater element by the power supply;
 - (iv) a resistance monitor for monitoring an electrical resistance of the electric resistance-type heater element; and
 - (v) control means in communication with the means for measuring, the power supply, the power monitor, and the resistance monitor, for:
 - (a) empirically determining a relationship between the amount of electric power supplied and the electrical resistance of the electric resistance-type heater element under in vivo conditions;
 - (b) using the empirically determined relationship to estimate what electrical resistance the electric resistance-type heater element would have at a reference temperature;

- (c) comparing the estimated resistance of the electric resistance-type heater element at the reference temperature with a known resistance of the electric resistance-type heater element at the reference temperature; and
- (d) determining whether the difference between the estimated resistance and the known resistance of the electric resistance-type heater element exceeds a predetermined maximum.

- (b) means for measuring the sound generated by the skin tissue in said area;
- wherein said means for measuring the moisture content and said means for measuring sound indicate the presence of skin lesion when the moisture content and the sound reading are both abnormally high.

5,588,439

ACOUSTIC IMPULSE RESPIROMETER AND METHOD


Seth D. Hollub, Overland Park, Kans., assignor to Nellcor Incorporated, Pleasanton, Calif.

Filed Jan. 10, 1995, Ser. No. 370,623

Int. Cl.⁶ A61B 5/08

U.S. Cl. 128—721

15 Claims



1. A detector for measuring motion of a patient's body during respiration, comprising:
 - an acoustic impulse generator adapted to be disposed at a first position on the patient's body;
 - an acoustic impulse receiver adapted to be disposed at a second position on the patient's body, being disposed in spaced relationship to the acoustic impulse generator to detect impulses therefrom upon passage of the impulses through the patient's body; and
 - means for determining changes in a spaced relationship distance between the acoustic impulse generator and the acoustic impulse receiver induced by the patient's respiration.

5,588,440

METHOD AND APPARATUS FOR LOCATING AND ASSESSING SOFT TISSUE LESIONS


Jocelyn W. Cowie, P.O. Box 1495, 6700 Danshin Village Road, Grand Forks, B.C., Canada

Filed Aug. 10, 1995, Ser. No. 513,406

Int. Cl.⁶ A61B 5/05


U.S. Cl. 128—734

8 Claims



1. Apparatus for diagnosing the skin condition of a human being or animal, comprising a probe for contacting a desired area of skin, said probe having
 - (a) means for measuring the moisture content of the skin at said area; and

1. An allergy testing apparatus for testing a patient for a plurality of substances, comprising:
 - a first member having a plurality of engaging means arranged at respective positions on said first member for selectively engaging a respective pricking or piercing element;
 - a plurality of pricking or piercing elements which are selectively engaged with selected engaging means of said first member, at selected positions on said first member, said pricking or piercing elements extending in a given direction from said first member for pricking or piercing the skin of a patient in use;
 - said first member having a side wall extending in said given direction so as to at least partly surround said pricking or piercing elements, said side wall having a free end portion for placement against the skin of a patient;
 - said side wall of said first member including a resilient compressible portion for controlling a downward movement distance of said pricking or piercing elements which are engaged with said first member;
 - a well tray having a plurality of receptacles for receiving substances for which a patient is to be tested at selected receptacles corresponding in position to the pricking or piercing elements which are engaged with said selected engaging means at said selected positions of said first member, said first member with said pricking or piercing elements engaged thereon, being engageable with said well tray for causing the pricking or piercing elements mounted to said first member to contact said substances in respective associated receptacles, said first member being thereafter removable from said well tray for application of said substances to a patient;



said removed first member then being adapted to be placed with said free ends of said side walls thereof against the skin of a patient and to be pressed downwardly against the skin of the patient to compress said compressible portion and to cause said pricking or piercing elements to contact the skin of the patient and to apply said substances at respective spaced apart positions on the skin of the patient, the respective spaced apart positions on the skin of the patient being spaced apart a distance corresponding to the positions at which the pricking or piercing elements are engaged with said first member.

5,588,442


SHAFT MOVEMENT CONTROL APPARATUS AND METHOD

Brian Scovil, New Hope; Todd A. Berg, Lino Lakes; Kevin Kiltz, Plymouth; Thomas J. Bachinski, Lakeville; John W. Humphrey, Eden Prairie; Scott Thome, Waite Park, and Roger Hastings, Maple Grove, all of Minn., assignors to SciMed Life Systems, Inc., Maple Grove, Minn.
Continuation-in-part of Ser. No. 48,492, Apr. 16, 1993, Pat. No. 5,555,893, which is a continuation-in-part of Ser. No. 929,083, Aug. 12, 1992. This application Mar. 2, 1995, Ser. No. 397,578

Int. Cl.⁶ A61B 5/00

U.S. Cl. 128—772

36 Claims



1. A device for use in exchanging a first guide catheter for a second guide catheter, the device comprising:
a. a support member insertable within the first guide catheter, having a proximal end and a distal end; and
b. means for coupling responsive to a magnetic source, carried by the support member, wherein the means for coupling maintains the support member stationary relative to a guide wire while exchanging the first guide catheter for the second guide catheter.

5,588,443


ZIRCONIUM OXIDE AND ZIRCONIUM NITRIDE COATED GUIDE WIRES

James A. Davidson, Germantown, Tenn., assignor to Smith & Nephew Richards, Inc., Memphis, Tenn.
Division of Ser. No. 112,587, Aug. 26, 1993, Pat. No. 5,496,359, which is a continuation-in-part of Ser. No. 919,932, Jul. 27, 1992, Pat. No. 5,282,850, which is a continuation-in-part of Ser. No. 830,720, Feb. 4, 1992, Pat. No. 5,258,022, which is a continuation-in-part of Ser. No. 557,173, Jul. 23, 1990, Pat. No. 5,152,794, which is a continuation-in-part of Ser. No. 385,285, Jul. 25, 1989, Pat. No. 5,037,438. This application Jun. 6, 1995, Ser. No. 467,164

Int. Cl.⁶ A61M 25/09

U.S. Cl. 128—772

12 Claims



1. A flexible guide wire for insertion into a living body, the guide wire comprising:

- (a) an elongate core having a distal end for insertion into a living body, a proximal end and surfaces, said core comprising a low elastic modulus metallic composition; and
- (b) a corrosion-resistant, biocompatible, hemocompatible, durable, stable coating selected from the group consisting of zirconium oxides, ranging in color from blue to black, and zirconium nitrides, ranging in color from yellow to orange, said coating disposed on the surfaces of the distal end of the core.

5,588,444

HUMAN RANGE OF MOTION MEASUREMENT SYSTEM


Michael R. Petragallo, 10003 NE 123rd, Kirkland, Wash. 98034

Continuation-in-part of Ser. No. 978,587, Nov. 19, 1992, abandoned. This application Feb. 28, 1994, Ser. No. 203,995

Int. Cl.⁶ A61B 5/103

U.S. Cl. 128—782

8 Claims



1. A modular ROM measurement system comprising:
a transometer having a horizontal support surface on which are mounted a magnetic north seeking means, a leveling means for measurement in a transverse plane, and, releasably attached to the horizontal support surface, at least one additional modular component selected from the group of components consisting of an inclinometer for determining a degree of inclination of the horizontal support surface from the horizontal, a headband, a stabilizer plate, one or more elastic bands, one or more vertical mode plates selected from a group of plates consisting of a thorax plate and an extremity plate, one or more soft level adjusting means;
whereby each of the modular components from the above said group of components may be releasably and temporarily interengaged with one another and the horizontal support surface of the transometer, so that
a plurality of separate instrument configurations may each be temporarily assembled for performing a specific ROM measurement function, and then be disassembled for compact storage or for reassembly into the same or different instrument configurations.

5,588,445

HEAD AND NECK PROTECTOR FOR CHILDREN

Hemayatullah S. Ohaidi, 905 University Village Dr., Richardson, Tex. 75081

Filed May 22, 1996, Ser. No. 651,776

Int. Cl.⁶ A61F 5/37

U.S. Cl. 128—846

20 Claims

1. A head and neck protector comprising:
a flexible resilient back member sized to cover the back shoulders and head of a child having a substantially smooth child

5,588,447

BRUSH FOR APPLYING NAIL VARNISH AND METHOD

Jean-Louis H. Gueret, Paris, France, assignor to L'Oréal, Paris, France


Filed Nov. 7, 1994, Ser. No. 337,223

Claims priority, application France, Nov. 5, 1993, 93 13214

Int. Cl.⁶ A45D 34/04; A46B 3/16

U.S. Cl. 132—200

30 Claims




contacting surface and constructed from a flexible mesh member surrounded by resilient foam and covered with a fabric covering;

an adjustable torso strap assembly secured to said resilient back member including first and second adjustable length torso straps securable about said torso of a child;

first and second adjustable shoulder straps secured to said child contacting surface, each of said first and second shoulder straps having a securing mechanism on a distal end thereof for securing said shoulder strap to one of said first and second torso straps;

a removable sloped cushion member; and

a cushion retaining strap attached to said back member and forming a cushion retaining loop into which said sloped cushion member is inserted and held.



1. Brush for the application of varnishes, comprising bristles forming a tuft obtained from a bundle of bristles which are substantially parallel and folded in two approximately halfway along their length, the folded part being fixed in a housing opening at an end of a rod, the bristles having cross-sections which are bounded by a circle of constant diameter, wherein the bristles of the tuft comprise at least two groups, the bristles of one group being arranged to have a different mechanical behavior in flexure from that of the bristles of another group so that these groups give a brush tuft which is open to the air and spread out with relatively large spaces between adjacent bristles, to promote good capillary action for varnishes whose viscosity may vary over a wide range.

5,588,446

CIGARETTE WITH IMPROVED CELLULOSIC SUBSTRATE


Jack F. Clearman, Blakely, Ga., assignor to R. J. Reynolds Tobacco Company, Winston-Salem, N.C.

Continuation of Ser. No. 71,132, Jun. 2, 1993. This application Sep. 13, 1994, Ser. No. 305,405

Int. Cl.⁶ A24F 1/22; 47/00

U.S. Cl. 131—194

9 Claims



1. A smoking article comprising:

(a) a combustible fuel element less than about 30 mm in length prior to smoking; and

(b) a physically separate aerosol generating means disposed longitudinally behind the fuel element comprising a cellulosic substrate material bearing an amount of aerosol forming material sufficient to substantially eliminate the burning of the substrate under smoking conditions of 50 ml volume per puff of 2 seconds duration, followed by 28 seconds of smolder, the substrate material being positioned in a barrier tube formed from a paper/foil laminated web having an isolating joint by which the substrate is isolated from contact with the paper layer of the paper/foil laminated web.

5,588,448

SMOKING ARTICLE HOLDER


John G. Photakis, 53 Winifred Ave., Worcester, Mass. 01602

Filed Jun. 6, 1995, Ser. No. 470,913

Int. Cl.⁶ A24F 1/312

U.S. Cl. 131—259


8 Claims



1. A smoking article holder, for use with a golf tee having a head portion, and for use with a smoking article, said holder comprising:
(a) a generally oblong upper member having an elongated, concave upper surface and a lower surface, said upper surface being adapted for receiving at least a part of the smoking article, and
(b) a lower member, depending from said lower surface of said upper member, intermediate the length thereof, said lower member being adapted to receive at least a part of the head portion of the golf tee.

5,588,449
HAIR ROLLER APPARATUS AND METHOD FOR HIGHLIGHTING HAIR

William C. Falcon, 192 E. International Speedway Blvd., Daytona Beach, Fla. 32118
 Continuation-in-part of Ser. No. 209,973, Mar. 15, 1994, abandoned. This application Jun. 7, 1995, Ser. No. 475,535
 Int. Cl.⁶ A61K 7/13; A45D 6/16
 U.S. Cl. 132—208 20 Claims




increasing the spacing between the bristle and a helical ply formed after twisting, thereby creating a disorganized arrangement of the section of the bristles, said bristles having a transverse section in the shape of an L being mixed with harder bristles so as to form an assembly, and said assembly being ground in order to obtain bristles having a transverse section in the shape of an L and whose ends are located beyond those of the harder bristles made shorter by grinding.

1. A hair roller apparatus comprising:
 an elongated roller stem having first and second opposing ends;
 a first end flange mounted to said first end of said elongated roller stem;
 an elongated cap member removably and rotatably mounted to said elongated roller stem in covering relation to said elongated roller stem;
 wherein said elongated cap member includes an elongated cap body having first and second ends, and a first end wall mounted to said first end of said elongated cap body;
 wherein said first end wall of said elongated cap member includes an engagement portion;
 wherein said first end flange includes an engagement portion which is selectively and disengageably securable to said engagement portion of said first end wall;
 wherein a second end flange is mounted to said second end of said elongated roller stem;
 wherein said second end flange is circular and projects radially outwardly from said elongated roller stem;
 wherein said first end flange is oblong and projects radially outwardly from said elongated roller stem; and
 wherein said first end wall of said elongated cap member protrudes outwardly beyond said elongated cap body in a direction perpendicular to a longitudinal direction of said elongated cap body.

5,588,450
BRUSH FOR APPLYING A MAKE-UP PRODUCT, PARTICULARLY MASCARA

Jean-Louis H. Gueret, Paris, France, assignor to L'Oreal, Paris, France
 PCT No. PCT/FR94/00729, § 371 Date Feb. 21, 1995, § 102(e) Date Feb. 21, 1995, PCT Pub. No. WO95/00050, PCT Pub. Date Jan. 5, 1995
 PCT Filed Jun. 17, 1994, Ser. No. 387,802
 Claims priority, application France, Jun. 23, 1993, 93 07609
 Int. Cl.⁶ A45D 40/26 2 Claims

1. Brush for applying a make-up product, comprising a wand equipped at one end with a core formed by two branches made from metal wire which are twisted into turns between which bristles extending transversely with respect to the core are trapped, wherein at least a fraction of the bristles of the brush has a transverse section in the shape of an L so that a zone of a bristle wedged between the turns of the core undergoes a flattening by the effect of one of unfolding when an angle between the branches of the L opens, and folding when the angle between the branches of the L closes, said flattening reducing the rigidity of the bristle and



5,588,451
HAIR RETAINER

Helen A. Peters, 2992 Paradise Dr., West Bend, Wis. 53095
 Filed May 2, 1995, Ser. No. 434,206
 Int. Cl.⁶ A45D 8/04; 8/34; 8/36 15 Claims

U.S. Cl. 132—273



1. A retainer for retaining a flock of hair, the retainer comprising:
 at least one elongate rigid member having a pointed leading end and a following end; and
 at least one protuberance extending radially outwardly from the member, the protuberance is defined by at least a leading surface and a following surface, the leading surface located relatively closer to the leading end than the following surface, the leading surface having first proximal and first distal ends, the first proximal end located relatively closer to the leading end than the first distal end, the leading surface sloping radially outwardly from the first proximal end to the first distal end so as to form a first angle between the leading surface and a first line tangent to a portion of the member adjacent the leading surface, the following surface having second proximal and second distal ends, the following surface sloping radially inwardly from the second distal end to the second proximal end so as to form a second angle between the following surface and a second line tangent to a portion of the member adjacent the following surface, the first angle is of an obtuse degree and the second angle is of a lesser degree than the first.

5,588,452
TOOTH CLEANSING AND FLOSSING IMPLEMENT AND METHOD


Granger Peck, 6 Legend La., Sandy, Utah 84115
 Filed May 10, 1995, Ser. No. 438,258
 Int. Cl.⁶ A61C 15/00 13 Claims

1. A unitary tooth cleansing implement comprising an elongate, slender shaft having generally planar upper and lower surfaces, with a thickness of from about 0.4 millimeters to 0.8 millimeters

5,588,454
DUAL LOCKING MECHANISM FOR USE IN UMBRELLA HANDLES

Chin S. Kou, No. 27-1, Lane 188, Chin Mar Road, Sec. 3, Chang Hua, Taiwan
 Filed Feb. 5, 1996, Ser. No. 596,625
 Int. Cl.⁶ A45B 25/14 1 Claim

U.S. Cl. 135—24



and a width of from about 0.5 millimeters to 2.5 millimeters, the upper and lower surfaces being roughened, said shaft being constructed of polymer material and being longitudinally stiff and laterally flexible.

5,588,453
MANICURE DEVICE

Mary A. Fraysher, 660 Springhill Dr., Hurst, Tex. 76054
 Filed Jul. 13, 1995, Ser. No. 502,123
 Int. Cl.⁶ A45D 29/18 6 Claims

U.S. Cl. 132—76.4



1. A manicuring device for use in honing a nail of a user having an inner surface, the device comprising:
 an elongated cylindrical body having an outer surface and a first tapered end and a second end distal from the first tapered end;
 an abrasive surface affixed to the outer surface of the body proximate the second end; and
 the abrasive surface and the body comprising a perforation line comprising perforations passing through the abrasive surface and partially into the body, the perforation line surrounding the cylindrical body at a constant distance from the second end of the body such that the user of the device may use the abrasive surface to hone the inner surface of the user's nail and may fracture the abrasive surface and the body at the perforation line to allow for the use of a portion of the abrasive surface proximate the perforation line.

1. A dual locking mechanism of an umbrella handle, said handle being attached to the lower end of an umbrella rod, with a runner slidably embracing the outer surface of the rod, comprising:
 a base and a transversely movable button disposed inside said umbrella handle, the base being provided with an opening;
 said handle having a hole on its side surface and said base having an opening disposed at a corresponding position thereof and a slot formed on a top portion of said base above the opening, thereby allowing the button to be placed into the base;
 said button having a raised portion on side thereof piercing through said opening of the handle with a top portion of the raised portion engaging with the slot of the base;
 said button being further provided symmetrically with an upper stepped groove and a lower stepped groove on a side of said button opposite to the side thereof containing the raised portion, both grooves having a recessed portion respectively formed on bottom portions thereof, said button having a cavity formed between said grooves for accommodating a spring;
 the base being provided an upper guide groove and a lower guide groove formed in positions respectively corresponding to the upper and the lower stepped grooves of the button;
 an upper and a lower locking element being respectively situated in the guide grooves, and each locking element comprising one wedged end and an opposing end provided with a stub on which a spring is mounted to furnish the locking element a resilient force toward the center of the base;
 said upper locking element and said lower locking element having, respectively on a bottom surface of the upper locking element and a top surface of the lower locking element, a raised block that engages with said stepped grooves of the button;
 said dual locking mechanism holding the umbrella's runner in an upper position in a normal operation of closing the umbrella and fixing it in a lower position if further shortening is needed and releasing the runner by pressing said button.

5,588,455

SECURING RUNNER OF AN UMBRELLA


Cheng M. L. Kuo, No. 18, Alley 15, Lane 582, Sea Ta Road, Hsinchu, Taiwan

Filed May 14, 1996, Ser. No. 645,815

Int. Cl.⁶ A45B 25/06

U.S. Cl. 135—28

1 Claim



1. A securing runner of an umbrella including a sleeve, a nest portion, and a base; wherein the sleeve has an upper groove and a lower groove on one side related to a curved end and a holding end of a detent positioned in a main tube of the umbrella; the nest portion connecting with stretchers of the umbrella and the base being provided around the sleeve that the base has an inner circular rim to fit into a circular groove provided on lower part of the sleeve to obtain a good engagement between both; and while the runner being pull downward, the sleeve urges the detent spring moving inwardly directly and the runner can be slid down to close the umbrella.

5,588,456

ORTHOTIC WALKER

David Hart, Keighley, England, assignor to Ontario Crippled Children's Centre, Toronto, Canada

Division of Ser. No. 330,832, Oct. 27, 1994. This application


Jul. 12, 1995, Ser. No. 501,683

Claims priority, application Canada, Nov. 2, 1994, 2115528

Int. Cl.⁶ A61H 3/00

U.S. Cl. 135—67

5 Claims



1. A walking support orthosis comprising: a wheeled frame;

a support member for a body brace, the support member being located to extend at least partially behind the body of a user; a body brace including leg braces, and having support engagement means to engage said support member, the engagement means being located on a rear part of the body brace, and the leg braces having generally hip level connections to the support member to allow for articulation of a hip joint of a user;

each leg brace including:

- a stirrup for supporting the foot of a user, the stirrup means comprising a generally horizontal support bar located to lie under the instep of the foot of a user and a stirrup leg fixed to the support bar at one leg end extending rearwardly upwardly from the support bar to a pivotal connection with a lower end of a shank member of the leg brace;
- a stop being provided to limit pivotal travel of the stirrup leg to inhibit swivelling of the support bar; and
- a clamp being provided to clamp a shoe of the user to be fixed against swivelling on the support bar.

5,588,457

ROLLER CANE TO AID THE HANDICAPPED PERSON IN WALKING AND IN MANEUVERING


John A. Tartaglia, 108 Stoddard Rd., Waterbury, Conn. 06708

Filed Nov. 17, 1994, Ser. No. 341,639

Int. Cl.⁶ A61H 3/02

U.S. Cl. 135—85

3 Claims



1. A cane assembly comprising a cylindrical tube, a curved handle, and a base bracket, wherein the tube has an upper and lower end, said handle extending from said upper end, said base bracket being attached to said lower end at approximately a mid-point of said bracket, said bracket having a front and rear end, wherein two front swivel wheels are attached to the front end and two fixed rear wheels are attached to said rear end.

5,588,458

VACUUM VALVE CONTROLLER FOR VACUUM SEWER SYSTEM

Akihiro Ushitora, and Osamu Shimizu, both of Kanagawa-ken, Japan, assignors to Ebara Corporation, Tokyo, Japan

Filed Apr. 6, 1995, Ser. No. 417,764

Claims priority, application Japan, Apr. 19, 1994, 6-104587; Feb. 2, 1995, 7-039362

Int. Cl.⁶ E03C 1/12

U.S. Cl. 137—205

11 Claims

1. A vacuum valve controller for a vacuum sewer system having a suction pipe which is communicated with a vacuum system by opening a vacuum valve, and which is cut off from the vacuum system by closing said vacuum valve so that soil water in a soil water basin is sucked through said suction pipe and sent to a predetermined place by opening said vacuum valve, said vacuum valve controller comprising:

- means for detecting that said suction pipe begins to suck air from a lower end thereof when the soil water level has fallen as a result of suction of soil water through said suction pipe; and

5,588,460

FIRE HYDRANT VALVE GUIDE WITH LOCKING SLEEVE AND WRENCH THEREFOR


Aaron B. Meneses, 32527 Jacklynn Dr., Union City, Calif. 94587

Filed Jul. 24, 1995, Ser. No. 506,425


Int. Cl.⁶ F16K 35/10; E03B 9/06

U.S. Cl. 137—296

5 Claims



control means for closing said vacuum valve when said detecting means detects that said suction pipe has begun to suck air, wherein said detecting means detects that said suction pipe begins to suck air from a change of pressure difference between two points in said suction pipe which are different in height from each other.



1. A fire hydrant protector against unauthorized use comprising: a fire hydrant having a valve means with a valve carrier portion and a valve stem, a valve stem guide, said valve stem guide having a pair of open ends with an intermediate threaded portion disposed therebetween, said valve stem guide threaded portion is threadably secured within a threaded fire hydrant opening, with one of said open ends being disposed within said fire hydrant and said other open end extending exteriorly of said fire hydrant, said valve stem guide is removably guided along said valve carrier portion through said open ends, said valve stem having an exposed portion extending coaxially and into one of said ends when said valve means is threadably secured within said fire hydrant opening valve stem guide including screw means for screwing said stem guide into the hydrant, the valve stem coaxially extending from said screw means;

a tubular shield concentrically attached at said exterior open end adjacent said screw means said shield being coaxial with said valve stem and having a length longer than the extension of said valve stem from said valve stem guide, said shield having an interior threaded portion located at said exterior open end; a threaded plug removably adapted to fit completely within wherein said plug reinforces said shield and prevents said shield from becoming deformed and badly bent, if attempts are made to break said shield, said plug having a deeply grooved pentagonal keyway in its flat outer surface, said plug and said valve stem being rotatable by a single special wrench having an elongated male socket for removably securing said plug within said interior threaded portion and a female pentagonal socket for rotating said valve stem to open and close said valve means, while preventing unauthorized use.

5,588,461

HAZARDOUS MATERIAL CONTAINMENT SYSTEM

Joseph M. Plecnik, Long Beach, Calif., assignor to Philipp Brothers Chemicals, Inc., N.J.

Filed Apr. 8, 1994, Ser. No. 225,376

Int. Cl.⁶ B67D 5/32; G01M 3/18


U.S. Cl. 137—312

22 Claims

1. An apparatus for containing hazardous material leaks from a shipping container having a first valve allowing the hazardous material to flow into and out of said shipping container, said apparatus comprising:

1. A sewage removal device for use with an RV and the like comprising:

- (a) a housing having an interior cavity and connecting means for attaching said device to a sewage drain conduit on said RV;
- (b) a first opening in said device providing fluid communication between said sewage drain conduit and said interior cavity when said device is attached to said sewage drain conduit;
- (c) a fluid outlet conduit extending from the lower portion of said cavity to the exterior of said housing; and
- (d) a fluid inlet conduit extending from the exterior of said housing and into an interior portion of said housing, said inlet conduit including a nozzle extending from a discharge end thereof and into said cavity in coaxial alignment with said outlet conduit, said nozzle being adapted to discharge a liquid jet stream into the interior of said housing toward said fluid outlet conduit and in alignment with the longitudinal axis of said fluid outlet conduit, whereby fluid discharged from said nozzle and into said outlet conduit creates a pumping action for removing sewage from said cavity and into said outlet conduit which expedites waste removal therefrom.



a removable dome having an open bottom shaped to fit over a portion of said container that includes the first valve, said dome being adapted to be placed over said portion of said container during at least one of filling and discharging of hazardous material through said first valve;

sealing means for creating an air-tight seal between said dome and said container such that any leakage of hazardous material at said portion of said container will flow into said dome so as to prevent leakage of the hazardous material into a surrounding environment;

means, in vacuum communication with the interior of said dome, for maintaining at least a partial vacuum within said dome and for neutralizing said hazardous material;

first detector means, mounted within said dome, for detecting the presence of said hazardous material and for generating a first control signal in response thereto; and

a remotely controlled shutoff valve connected to said first valve, said shut off valve being coupled to said first detector means and responsive to shutoff the flow of the hazardous material when said first control signal is generated due to a leakage of hazardous material into said dome.

5,588,462

VALVE AND SENSOR ARRANGEMENT


George J. McHugh, Broomall, Pa., assignor to AGF Manufacturing, Inc., Warren, N.J.

Continuation-in-part of Ser. No. 926,285, Aug. 10, 1992, Pat. No. 5,406,979, which is a continuation-in-part of Ser. No. 752,479, Mar. 8, 1990, Pat. No. 5,269,344, which is a continuation-in-part of Ser. No. 320,716, Mar. 8, 1989, Pat. No. 4,993,453, Ser. No. 413,292, Sep. 27, 1989, Pat. No. 4,971,109, Ser. No. 416,111, Oct. 3, 1989, Pat. No. 5,036,883, and Ser. No. 320,713, Mar. 8, 1989, Pat. No. 4,995,423, which is a continuation-in-part of Ser. No. 138,436, Dec. 28, 1987, Pat. No. 4,852,610, which is a continuation-in-part of Ser. No. 881,270, Jul. 2, 1986, Pat. No. 4,741,361, which is a continuation-in-part of Ser. No. 874,653, Jun. 16, 1986, abandoned. This application Apr. 17, 1995, Ser. No. 422,789

Int. Cl.⁶ F16K 37/00

U.S. Cl. 137—557

30 Claims



1. A valve and sensor arrangement, comprising:

a valve including a housing and a valve member, said housing comprising an interior chamber and an inlet and an outlet, said valve member being provided within said interior chamber and comprising a passageway, said valve member being movable about a turning axis between a first position which provides communication between the inlet and the outlet of the housing and a second position which restricts communication between the inlet and the outlet of the housing; and

sensor means for sensing a condition of the passageway of the valve member, said sensor means including a sensor element which is provided within said passageway of said valve member, said sensor means being mounted on said housing of the valve with said sensor element being provided within said passageway of said valve member, said sensor element extending within the valve member through an opening in the valve member at an angle with respect to the turning axis of said valve member.

5,588,463

MODULE FOR CONTROLLING PRESSURE IN A HYDRAULIC CIRCUIT

Gilbert Kervagoret, Argenteuil, France, assignor to AlliedSignal Europe Services Technique, Drancy, France

PCT No. PCT/FR94/01151, § 371 Date Oct. 20, 1994, § 102(e) Date Oct. 20, 1994, PCT Pub. No. WO95/12155, PCT Pub. Date May 4, 1995


PCT Filed Oct. 4, 1994, Ser. No. 325,199

Claims priority, application France, Oct. 29, 1993, 93 12912

Int. Cl.⁶ F15B 13/044

U.S. Cl. 137—596.15

9 Claims



1. A module for controlling pressure in a hydraulic circuit, comprising at least one generator of pressurized fluid, at least one reservoir of low pressure fluid, and at least one pressure receiver, said module including a solenoid valve having an electric coil and a movable magnetic core plunger, said plunger on moving controlling a position of a distributor slide valve which slides in a bore formed in a body, said bore communicating with a feed passage connected to said generator of pressurized fluid, a distribution passage connected to said pressure receiver, and a pressure relief passage connected to said reservoir of low pressure fluid, said module being characterized by a pressure controlled valve located between said generator and said feed passage, said pressure controlled valve being switched into an opened position when said core plunger actuates the distributor slide valve such that pressurized fluid is directly communicated to said feed passage for communication to distribution passage for transmission to said pressure receiver.

5,588,464

GAS SHUT-OFF VALVE


Gordon Tylosky, 3461 53rd Ave. West, Mukilteo, Wash. 98275

Filed Mar. 13, 1995, Ser. No. 402,843

Int. Cl.⁶ E03B 1/00; F16K 31/143

U.S. Cl. 137—613

18 Claims



1. A fluid shut-off system comprising:

a first valve including:

a first valve chamber having a first inlet and a first outlet, said inlet being engagable with a fluid supply line supplying fluid at a supply pressure;

a first valve seat provided at one of said inlet and said outlet; a first sealing piston housing positioned in registry with said first valve seat and communicating with said first valve chamber;

a first sealing piston positioned within said first sealing piston housing, said first sealing piston being movable between a first open position allowing fluid flow through said first valve chamber and a first closed position sealingly abutting said first valve seat, said sealing piston being biased to move to said first closed position; and

a pressure responsive locking mechanism retaining said first sealing piston in said first open position and allowing said first sealing piston to move to said first closed position in response to above normal fluid pressure in said first valve chamber; and

a second valve acting to interrupt fluid flow through said fluid shut-off system in response to lower than normal pressure downstream of said shut-off system.

5,588,465

VALVE BLOCK

Edgar Witowski, Rutesheim, and Guenter Mayer, Murr, both of Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

PCT No. PCT/DE94/00102, § 371 Date Apr. 6, 1995, § 102(e) Date Apr. 6, 1995, PCT Pub. No. WO94/19611, PCT Pub. Date Sep. 1, 1994

PCT Filed Feb. 3, 1994, Ser. No. 416,720


Claims priority, application Germany, Feb. 24, 1993, 43 05 608.3

Int. Cl.⁶ F15B 13/043; 13/08

U.S. Cl. 137—625.64

8 Claims

1. A valve block, comprising a baseplate provided with connection orifices in a connection side, ducts for incoming and outgoing air, and a well; a plurality of directional valves arranged next to one another on said connection side of said baseplate with an adapted connection hole pattern; at least one pilot valve assigned to each of said directional valves; an electromagnet actuating said pilot valve; an electrical installation device arranged in said well for extending in said well and having a plug connection; an electrical connecting plug by which said electromagnet engages into said plug connection of said electrical installation device; a common housing in which said pilot valve and said electromagnet are arranged and which has a lateral attachment face bearing against an end face of an associated one of said directional valves;



and a plate-shaped extension projecting laterally from said attachment face of said housing near an underside of said housing and assigned to said connecting plug, said plate-shaped extension being arranged so that said directional valve bears with its connection side against said plate-shaped extension and said baseplate bears with its connection side against said plate-shaped extension, said plate-shaped extension having a plurality of passage bores congruent with said connection orifices of said baseplate and of said directional valve.

5,588,466

MAGNETOSTRICTIVE TRANSDUCER

Gerhard Benz, Boeblingen; Gottfried Flik, Leonberg; Christoph Treutler, Wannweil, and Heinz Friedrich, Frieolzhelm, all of Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

PCT No. PCT/DE93/00489, § 371 Date Dec. 20, 1994, § 102(e) Date Dec. 20, 1994, PCT Pub. No. WO94/00695, PCT Pub. Date Jan. 6, 1994


PCT Filed Jun. 8, 1993, Ser. No. 356,281

Claims priority, application Germany, Jun. 20, 1992, 42 20 226.4

Int. Cl.⁶ F16K 31/02; F15C 5/00

U.S. Cl. 137—831

17 Claims



1. A magnetostriuctive transducer comprising:

means for producing a magnetic field; and

a drive including a first thin layer of magnetostriuctive material arranged on a flexible element in the magnetic field, the first thin layer being composed of $Tb_{(1-x)}Dy_{(x)}Fe_2$ ($0 < x < 1$) and being deposited from a metal vapor.

5,588,467 ORIFICE FITTING


Dreu E. Crane, Broken Arrow, Okla., assignor to Crane Manufacturing, Inc., Tulsa, Okla.

Filed Mar. 15, 1995, Ser. No. 404,516

Int. Cl.⁶ F15D 1/02

U.S. Cl. 138—44

18 Claims



1. An orifice fitting for measurement of fluid flow therethrough, which fitting comprises:

a plate carrier having an orifice plate and carrier plate seals, said plate carrier movable between an orifice body lower chamber and an orifice body upper chamber wherein said plate carrier has two opposed sides;

two entry plugs to allow access to both sides of said plate carrier, said entry plugs have external threads which mate with threads on seal rings;

means to seal said upper body chamber to said plate carrier to produce a fluid-tight seal between said upper body chamber and carrier and between said upper and lower chambers; and means to allow access to said plate carrier, to said orifice plate and to said carrier plate seals while in said upper chamber without interrupting or disabling fluid flow through said lower chamber.

5,588,468

BLOW-MOLDED COOLANT CONDUIT

Wolfgang Pfleger, Tamins, Switzerland, assignor to EMS-Inventa AG, Zürich, Switzerland

Continuation of Ser. No. 360,321, Dec. 21, 1994, abandoned.

This application Mar. 18, 1996, Ser. No. 617,309


Claims priority, application Germany, Dec. 23, 1993, 9319880 U

Int. Cl.⁶ F16L 11/11

U.S. Cl. 138—121

13 Claims

1. A coolant conduit which is an elongate tubular article for an



apparatus requiring cooling by a cooling agent and which is blow molded, consisting essentially of

a plurality of layers which are provided by, in combination, discharging a co-axial melt hose, 3D tubing manipulation, and blow molding thereof, each layer of the plurality being comprised of a thermoplastic polymeric material which is thermoplastically processable,

wherein the plurality of layers comprises:

at least one inner layer which is comprised of a polymeric material which is substantially inert to the cooling agent, which is substantially non-swelling, and which is at least one polymer selected from the group consisting of homopolyolefins and copolyolefins, which at least one polymer may be halogenated or nonhalogenated, and which at least one polymer is provided with functional groups that cause it to be compatible with the outer layer; and an outer layer which is comprised of at least one polyamide and which is pressure resistant.

5,588,469

HOSE FOR AUTOMOTIVE FUEL PIPING

Daisuke Kakiuchi, Okayama; Yasumichi Ogawa, Kurashiki; Hifumi Yasumatsu, Okayama-ken, and Kazutaka Shiraga, Kurashiki, all of Japan, assignors to Marugo Rubber Industries, Ltd., Okayama-ken, Japan


Filed Oct. 12, 1995, Ser. No. 542,111

Claims priority, application Japan, Oct. 17, 1994, 6-250784

Int. Cl.⁶ F16L 11/04

U.S. Cl. 138—137

3 Claims



1. A hose for automotive fuel piping comprising:

an inner layer of a terpolymeric fluororesin prepared from tetrafluoroethylene, hexafluoropropylene and vinylidene fluoride,

an outer layer which is a molding obtained by vulcanizing a vulcanization composition comprising a member selected from the group consisting of an epichlorohydrin rubber and a NBR/PVC blend wherein each of the epichlorohydrin rubber and NBR/PVC blend is compounded with a 1,8-diazabicyclo(5.4.0)undecene-7 salt and with an organophosphonium salt, and

an innermost layer of a vulcanization composition comprising a member selected from the group consisting of an NBR rubber, NBR/PVC, hydrogenated NBR rubber and a fluororubber wherein each of the NBR rubber and fluororubber is compounded with a 1,8-diazabicyclo(5.4.0)undecene-7 salt and with an organophosphonium salt,

the above layers being firmly bonded to each other.

5,588,470 WEFT INSERTING DEVICE FOR AN AIR JET LOOM HAVING REED PIECES WITH RECESSED WEFT GUIDE OPENINGS

Masao Shlraki, Kariya; Fujio Suzuki, Toyota, and Kazunori Yoshida, Nagoya, all of Japan, assignors to Kabushiki Kaisha Toyota Jidoshokki Seisakusho, Kariya, and Kabushiki Kaisha Toyota Chuo Kenkyusho, Nagakute-cho, both of Japan


Filed Jul. 5, 1995, Ser. No. 498,786

Claims priority, application Japan, Jul. 5, 1994, 6-153939; May 16, 1995, 7-117411

Int. Cl.⁶ D03D 47/30

U.S. Cl. 139—435.5

15 Claims



1. A weft inserting device of an air jet type loom comprising: a sley;

a reed mounted on said sley, said reed including a plurality of adjacent reed pieces arranged along an inserting direction of a weft, each of said plurality of reed pieces having a recess into which the weft is inserted, a plurality of said recesses being aligned to form a weft passage;

a main nozzle for generating an air jet to insert the weft into the recesses; and

a plurality of supplemental nozzles for generating respective air jets to assist the insertion of the weft into said recesses, said recesses being open towards said air jets generated by said supplemental nozzles;

said recess of each of said reed pieces being substantially defined by three walls, an upper wall, a lower wall and a deep wall, said lower wall being connected to said deep wall by a lower connecting portion having a first radius of curvature and said upper wall being connected to said deep wall by an upper connecting portion having a second radius of curvature, said deep wall being substantially flat and connecting said upper connecting portion to said lower connecting portion, said second radius of curvature being smaller than said first radius of curvature, to converge the air jet generated by said supplemental nozzles toward said upper connecting portion.

5,588,471

CONTAINER FILLING APPARATUS

Terry B. Lowe, 133 Pagosa Way, Fremont, Calif. 94539


Continuation of Ser. No. 584,202, Sep. 18, 1990, abandoned, which is a division of Ser. No. 103,519, Oct. 1, 1987, Pat. No. 4,957,147. This application Mar. 9, 1995, Ser. No. 401,462

Int. Cl.⁶ B65B 3/28

U.S. Cl. 141—83

3 Claims

1. In apparatus for filling a container with a liquid: a base, an arm mounted on the base for movement between raised and lowered positions, a filling lance carried by the arm for introducing the liquid into the container, valve means for controlling the flow of liquid through the lance, a drip catcher movable between advanced and retracted positions relative to the lance, a flexible cable which is relaxed when the arm is in its lowered position and is drawn taut



by movement of the arm toward its raised position, and means connecting the cable to the drip catcher in such manner that the drip catcher is moved to its advanced position upon further movement of the arm toward its raised position.

5,588,472

METHOD FOR COMBINED GAS FILL AND PROOF TEST OF PRESSURE VESSELS


Kelly B. Johnson, Layton, Utah, assignor to Morton International, Inc., Chicago, Ill.

Filed Jun. 14, 1995, Ser. No. 490,185

Int. Cl.⁶ B65B 1/30; 3/26

U.S. Cl. 141—83

12 Claims



1. A method of gas filling and pressure proof testing a pressure vessel comprising the steps of:

- controlling the volume and temperature of the gas going into the pressure vessel to ensure a consistent gas fill mass,
- setting the controlled temperature of the gas high enough to cause the fill pressure of the vessel to exceed the required proof pressure of the vessel, and
- rapidly discharging the gas fill mass into the pressure vessel and immediately sealing the vessel after filling and allowing the pressure to decrease as the gas fill mass cools.

5,588,473

INTERFACE DEVICE FOR THE TRANSFER OF FLUID PRODUCTS BETWEEN TWO CONTAINERS


Charles Glachet, Vendôme, France, assignor to Snc La Calhene, Velizy Cedex, France

Filed May 25, 1995, Ser. No. 451,130

Claims priority, application France, May 31, 1994, 94 06608
Int. Cl.⁶ B65B 1/04

U.S. Cl. 141—387

24 Claims



1. Interface device of the transfer of fluid products between two containers, comprising a tight chamber having two aligned openings, a door and a transfer tube formed from at least two sections and placed in said chamber, as well as manipulating means able to displace the door and the transfer tube between an operative position, in which the door seals a first of the openings and the transfer tube is retracted in the tight chamber, laterally with respect to the aligned openings, and a transfer position, in which the door is retracted into the chamber, laterally with respect to the aligned openings, and the transfer tube connects the containers in tight manner coaxially to the openings, wherein the two sections of the transfer tube have a substantially uniform and identical internal cross-section and are placed end to end in the transfer position.

5,588,474

FEED RATE CONTROL SYSTEM FOR STUMP CUTTERS


Philip J. Egging, Pella, Iowa, assignor to Vermeer Manufacturing Company, Pella, Iowa

Filed Jun. 7, 1995, Ser. No. 473,102

Int. Cl.⁶ A01G 23/06

U.S. Cl. 144—24.12

25 Claims



1. In a stump cutter having an engine operable at a speed of rotation including an optimum speed of rotation, a cutter disposed to cut a tree stump, and means for advancing the cutter toward the stump to engage an uncut area of the stump over a range of movement at a rate of advancement, a method comprising the steps of:

sensing the speed of rotation of the engine; and

controlling the movement of said advancing means based on the speed of rotation of said engine.

5,588,475

WATER DIVERSION CHANNEL FOR THE JOINT BETWEEN DOOR SECTIONS OF A SECTIONAL DOOR


David O. Martin, Salt Lake City, Utah, assignor to Martin Door Manufacturing, Inc., Salt Lake City, Utah

Filed Apr. 5, 1995, Ser. No. 417,387

Int. Cl.⁶ E06B 7/14

U.S. Cl. 160—44

7 Claims



1. A tongue of a tongue and groove joint between adjacent door, said sectional door being disposable in a vertical closed position and a horizontal open position, sections of a sectional door, said tongue including a water diversion channel comprising:

- a leading face on said tongue, said leading face having an undercut, said undercut formed by two walls defining an acute angle therebetween forming a basal element of said water diversion channel when the sectional door is oriented toward the horizontal position

5,588,476

REMOVABLE WINDOW SHADE


Brig E. A. Trethewey, 4238 N. 68th Pl., Scottsdale, Ariz. 85251-2312

Filed Aug. 19, 1994, Ser. No. 293,136

Int. Cl.⁶ B60J 3/00

U.S. Cl. 160—370.21

2 Claims



1. A window shade for use with a roll down window of a vehicle, said shade comprising in combination:

- a) a flexible, resilient, self-supporting sheet of solar radiation filtering material generally conforming in planform with the window;
- b) at least one upper suction cup for securing the upper edge of said sheet adjacent the upper part of the window;
- c) a lower suction cup for securing the lower edge of said sheet adjacent the lower part of the window;
- d) an automatic release mechanism for detaching said lower suction cup from the window to permit displacement of the

lower part of said sheet from the window to accommodate lowering of the window;

- e) a folded lower edge of said sheet for stiffening the lower part of said sheet; and
- f) means for deflecting said folded lower edge of said sheet away from the window upon lowering of the window.

wherein said mixture comprises at least 30% by volume of said metal distributed substantially uniformly throughout said particles.

5,588,477

METHOD OF MAKING METAL MATRIX COMPOSITE


Gerald E. Sokol, Shelby Township; Howard H. Lee, Bloomfield Hills, and Bradley W. Kibbel, Ferndale, all of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Sep. 29, 1994, Ser. No. 314,738

The portion of the term of this patent subsequent to Sep. 29, 2014, has been disclaimed.
Int. Cl.⁶ B22D 19/14; 19/16

U.S. Cl. 164—34

17 Claims



1. A method of making a heterogeneous metal matrix composite comprising the steps of:

- providing a fugitive, open-cell, foam substrate comprising a plurality of ligaments interconnected by a plurality of nodes together forming a three-dimensional reticulum defining a multitude of interstitial cells;
- impregnating said substrate with a mass of filler particles sufficient to fill said cells with about 5% to 70% by volume of said particles, and to leave at least 30% to about 95% percent by volume interstitial void space between said filler particles in said cells;
- heating said particle-filled substrate sufficiently to burn-off said substrate and leave a three-dimensional reticulated network of particle-free capillaries pervading said mass and conforming substantially to the configuration of said substrate;
- filling said 30% to about 95% by volume interstitial void space and said capillaries with molten metal; and
- allowing said molten metal to cool and solidify to form a metal matrix composite having a network of said metal conforming to said network of particle-free capillaries pervading a mixture of said metal and said particles wherein said mixture comprises at least 30% by volume of said metal distributed substantially uniformly throughout said particles.

8. A method of making a heterogeneous metal matrix composite comprising the steps of:

- providing an open-cell, foam metal substrate comprising a plurality of ligaments interconnected by a plurality of nodes which together form a three-dimensional reticulum defining a multitude of interstitial cells;
- impregnating said substrate with a slurry of filler particles suspended in a fugitive vehicle, said particles being sufficient to fill said cells with about 5% to 70% by volume of said particles, and to leave 30% to about 95% percent by volume interstitial void space between said filler particles in said cells upon removal of said vehicle;
- removing said vehicle;
- filling said 30% to about 95% by volume interstitial void space with molten metal; and
- allowing said molten metal to cool and solidify within the interstices between said filler particles to form a metal matrix composite having a network of metal conforming to said substrate pervading a mixture of said metal and said particles

CONTROL OF STICKING IN TWIN ROLL CASTING

Ijjoon Jin; David J. Lloyd; Roland S. Timsit, all of Kingston, and Eric R. Lees, Harrowsmith, all of Canada, assignors to Alcan International Limited, Montreal, Canada


Continuation of Ser. No. 986,244, Dec. 7, 1992, abandoned.
This application Jan. 18, 1994, Ser. No. 182,683

Claims priority, application Canada, Apr. 28, 1992, 2067438

Int. Cl.⁶ B22D 11/06

U.S. Cl. 164—480

5 Claims



5. In a high speed twin roll casting process for forming a metal strip in which molten Al—Mg alloy containing less than 2 wt % Mg is fed through a feed nose into a convergent cavity formed between the walls of two rotating rolls with a meniscus of hot metal extending from the feeding nose tip in a casting zone and the metal strip formed in the casting zone is reduced in a rolling zone, the improvement which comprises shrouding the hot metal meniscus with an oxygen enriched atmosphere by feeding into the region of said meniscus a gas containing at least 25% oxygen to prevent sticking of the alloy strip to the rolls, and adding a small amount of at least one further alloying element to the Al—Mg alloy for inhibiting sticking, said further element being selected from the group consisting of nickel, lead, bismuth and indium.

5,588,479

STRIP CASTING


Darren J. Leadbeater, Dapto, Australia; Heiji Kato, Yokosuka, and Hisahiko Fukase, Tokyo, both of Japan, assignors to Ishikawajima-Harima Heavy Industries Company Limited, Tokyo, Japan, and BHP Steel (JLA) Pty Ltd., Melbourne, Australia

Filed Oct. 24, 1995, Ser. No. 547,657

Claims priority, application Australia, Jan. 12, 1995, PN0512
Int. Cl.⁶ B22D 11/06

U.S. Cl. 164—480

4 Claims



1. A method of casting metal strip comprising:

supporting a casting pool of molten metal on a pair of chilled casting rolls forming a nip between them;
 confining the casting pool by applying a pair of side closure structures to end surfaces of the rolls at the ends of the nip;
 and
 rotating the chilled rolls in mutually opposite directions to produce a solidified strip product passing downwardly from the nip;
 wherein the side closure structures are applied to said end surfaces of the rolls by a pair of generally horizontally acting thrusters connected one to each of the closure structures by pivot connections allowing tilting movements of the closure structures, the thrusters apply opposing inward forces to the side closure structures at said pivot connections, and each of the pivot connections is disposed at or below the centre of effort of the outward forces applied to the respective side closure structure by the molten metal of the pool.

5,588,480


AUTOMOBILE HEAT TRANSFER APPARATUS

Frank Armanno, Sr., 14399 Picea Ct., Fort Pierce, Fla. 34951

Filed Apr. 10, 1995, Ser. No. 419,351

Int. Cl.⁶ F25B 29/00; B60H 1/08; 1/32; F28F 7/00

U.S. Cl. 165—300 4 Claims



1. Apparatus for controlling the temperature of objects over a wide temperature range, typically between 40 and 80 degrees F., using as the source of heating and cooling a heating and air conditioning system designed to maintain a relatively narrow range of room temperatures, typically between 50 and 70 degrees F., said apparatus maintaining said wide temperature of said objects while said heating and air-conditioning system maintains said narrow range of room ambients, said heating and air-conditioning system having a vent through which issues a first air stream, said air stream being generally above room ambient when the heating portion of said heating and air-conditioning system is activated and is generally below room ambient when said air-conditioning portion of said heating and air-conditioning system is activated, said apparatus comprising:

- An enclosure to hold said objects, said enclosure having a plurality of sides;
- a first side of said enclosure having a first aperture, said first side being positioned opposite said vent of said heating and air-conditioning system with said first side oriented to place said first aperture in a location to capture at least a portion of said first air stream for entry of said first air stream into said enclosure;
- means for securing said first side in said position opposite said vent;
- a second side of said enclosure, said second side having a second aperture, said second aperture releasing air from said enclosure which entered said enclosure through said first aperture, said air released from said second aperture forming a second air stream;
- a third side of said enclosure to hold said objects in said enclosure and subject said objects to said first air stream to

control the temperature of said objects by means of heat transfer between said objects and said first air stream.

- a plate rotatably connected to said enclosure, said plate having a rotational path with respect to said enclosure and said plate being positioned on said enclosure in a first position in its rotational path to cover said second aperture and a second position in its rotational path to uncover said second aperture to block and release said second air stream, respectively, and wherein positions of said plate intermediate of said first and second positions provide varying degrees of blockage to said second air stream to control the flow of air through said enclosure and to control the temperature of said objects within said enclosure, said plate being generally positioned in the horizontal plane and located on top of said enclosure, said plate being rotated to a position that only partially blocks said second air stream by said air stream impinging on said plate, the degree of blockage of said second air stream being controlled by the weight of said plate, the amount of flow within said second air stream and the pressure of said second air stream, the adjustment of the weight of said plate providing one means of varying the blockage of said second air stream and consequently the temperature of the objects within said enclosure

5,588,481

SYSTEM FOR PROVIDING HEATING, AIR CONDITIONING AND VENTILATION FOR A VEHICLE

Krzysztof E. Dziama, Solihull, and John Tipping, Warwick, both of England, assignors to Rover Group Limited, Birmingham, England


Filed Jul. 17, 1995, Ser. No. 503,011

Claims priority, application United Kingdom, Jul. 30, 1994, 9415417.6

Int. Cl.⁶ B60H 1/00

U.S. Cl. 165—42

6 Claims



1. A system for providing a supply of air to the passenger compartment of a vehicle, the system comprising ducting for supplying air to a vehicle passenger compartment, a blower for propelling air through the ducting, a heat supply for supplying heat to the air, an air cooler for cooling the air, a vehicle speed detector, and a control unit for controlling the speed of the blower, wherein the control unit is arranged to limit the blower to a predetermined blower speed if the blower has been operating for a predetermined period while the vehicle speed is below a predetermined vehicle speed.

5,588,482

DUCTED COOLING SYSTEM FOR AN AUTOMOTIVE VEHICLE


Thomas C. Holka, Milford, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Sep. 26, 1994, Ser. No. 311,975

Int. Cl.⁶ F28D 7/16; F01P 7/02; 11/10; B60K 11/08

U.S. Cl. 165—44

3 Claims



1. A cooling apparatus for cooling an engine of an automotive vehicle, comprising:

- a radiator in fluid communication with the engine and having a coolant flowing therethrough for cooling the engine, said radiator having a front face for receiving ambient air therethrough and a rear face disposed proximate the engine;
- a duct assembly for drawing a flow of air into said radiator and directing the flow of air exiting the radiator away from said vehicle engine, said assembly comprising:
 - a generally rectangular body partially enclosing said radiator and sealably secured thereto, said body including a selectively openable bleed port disposed proximate said vehicle engine for allowing RAM air to pass therethrough;
 - a pair of generally curvilinear plenums formed integrally with said body, each of said pair in fluid communication with said body and extending longitudinally from said body, each of said plenums including an engine inlet opening disposed proximate said vehicle engine for drawing engine compartment air therein and an exit end for directing air exiting therefrom to ambient air;
- a plurality of generally arcuate, comb-shaped vanes disposed in said body immediately adjacent said rear face of radiator, each of said vanes having a predetermined length and a predetermined radius of curvature depending upon its location relative to a centerline of said radiator, wherein the length of each vane decreases from a larger of two predetermined values for a vane adjacent the centerline of said radiator to a smaller of two predetermined values for a vane adjacent the side edge thereof, wherein approximately half of said plurality of vanes is generally curved toward the plenum disposed on a respective side of said radiator, said plurality of vanes being operative to direct the flow of air exiting said radiator;
- a fan assembly disposed in each of said engine inlet openings in said plenums for drawing air through said radiator, said body and said pair of plenums and away from said engine compartment.

5,588,483

HEAT RADIATING APPARATUS

Yoshio Ishida, Osaka, Japan, assignor to Diamond Electric Mfg. Co., Ltd., Osaka, Japan


Filed Jan. 26, 1996, Ser. No. 590,083

Claims priority, application Japan, Jan. 27, 1995, 7-031579

Int. Cl.⁶ F28D 11/00

U.S. Cl. 165—86

7 Claims



1. A heat radiating apparatus comprising:
 a metal pipe attached to at least one side of a metal plate;
 a heat pipe inserted into an internal hollow of said metal pipe, the hollow being filled with grease having high thermal conductivity;
 a sleeve seal provided at least one longitudinal end of said metal pipe for sealing the grease in such a way as to permit said heat pipe to freely rotate; and
 a heat receiving section through which a part of said heat pipe is in contact with a heating body.

5,588,484

REFRIGERATION FAN SYSTEM


Gerald N. Baker, Florissant, and Gregory R. Maes, Winchester, both of Mo., assignors to Emerson Electric Co., St. Louis, Mo.

Filed Aug. 19, 1994, Ser. No. 292,848

Int. Cl.⁶ B60H 1/32

U.S. Cl. 165—122

4 Claims



1. In a fan assembly in a refrigerator, by which air is drawn over coils through a coil passage that is thin relative to its width, said coil passage containing said coils, said coil passage being defined by generally parallel front and back walls and side walls extending between said front and back walls, the improvement comprising a fan housing with front, back and side walls, said fan housing having an inlet passage defined by inlet front, back and side walls and having an inlet mouth communicating with said coil passage, an outlet passage having an outlet mouth oriented generally one hundred eighty degrees from said inlet mouth, said outlet passage being defined by outlet front, back and side walls, an intermediate

back wall, joining the inlet back wall and a back wall surface defining an edge of the outlet mouth; an elongated, cylindrical transverse flow fan supported by and mounted for rotation, about an axis of rotation, between said inlet side walls, said fan having blades outer edges of which lie in a cylindrical surface of revolution, an electric motor connected to rotate said fan; an outlet baffle having a scoop part with a first edge oriented parallel to the axis of rotation of said fan, spaced closely from said surface of revolution of said fan, said scoop part being concave from said first edge toward said outlet mouth on a side facing an inner surface of said intermediate back wall to receive air leaving said fan and exiting said outlet mouth and walls within said housing spaced from one another in a direction along the axis of rotation of said fan, said walls extending perpendicular to the axis of rotation of said fan from the inlet mouth to the outlet mouth of said fan housing, said walls having openings in them through which said fan extends.

5,588,485

PLATE-TYPE HEAT EXCHANGER, FOR USE ESPECIALLY AS AN OIL COOLER

Hélène Gire, Asnières, France, assignor to VALEO Thermique
Moteur, Le Mesnil-Saint-Denis, France


Filed Oct. 4, 1994, Ser. No. 317,468

Claims priority, application France, Oct. 12, 1993, 93 12133

Int. Cl.⁶ F28F 3/08

6 Claims

U.S. Cl. 165—157



1. A plate-type heat exchanger, for effecting heat transfer between a first fluid and a second fluid and comprising: a casing; inlet means and outlet means for the second fluid disposed on the casing; a central tube extending through the casing and defining a stacking direction; and a stack of heat exchange plates disposed in the casing around the central tube, said plates being disposed in alternating pairs each having a first plate and a second plate, with the plates of each pair defining between them a first flow channel for the first fluid, the pairs of plates defining between one pair and another second flow channels for the second fluid within the casing, the second flow channels being in communication with each other, the heat exchanger further having an inlet for the first fluid, an outlet for the first fluid, and communication means through the successive pairs of plates defining a flow path for the first fluid from said first fluid inlet to said first fluid outlet, wherein each said first plate has a first cylindrical internal collar portion, and each said second plate has a second cylindrical internal collar portion, with said collar portions surrounding the central tube and extending parallel to said stacking direction, and with each said first collar portion of said first plate overlapping a corresponding said second collar portion of said second plate in each of said said defining pair of plates, wherein each first plate has a generally flat annular face joined directly to its said first collar portion, and each said second plate has a generally flat annular face and a raised annular portion joining its said annular face to the second collar portion of the second plate, said raised portion being in contact with the flat annular face of the first plate of an adjacent said pair of plates, so as to define a sealing junction between the pairs.

5,588,486 DOWN-HOLE GAS SEPARATOR FOR PUMP Bernard Heinrichs, Calgary, Canada, assignor to Elan Energy Inc., Calgary, Canada


Filed Mar. 29, 1995, Ser. No. 412,557

Claims priority, application Canada, Mar. 30, 1994, 2120283

Int. Cl.⁶ E21B 43/38

16 Claims

U.S. Cl. 166—50



1. A gas separation unit for use with a liquid pump inlet within a horizontal or inclined passageway comprising:
a. a nozzle having a proximal portion and a distal portion,
i. said distal portion defining an inlet opening in the nozzle on only one side of said nozzle for liquid ingress and
ii. said proximal portion adapted to be coupled to the liquid pump inlet so that liquid entering the nozzle through the inlet opening is drawn into the liquid pump inlet,
b. said distal portion including counterweight means for causing the nozzle inlet opening to seek a lowermost position; and
c. means for spacing apart said nozzle and said passageway.

5,588,487

TOOL FOR BLOCKING AXIAL FLOW IN GRAVEL- PACKED WELL ANNULUS


David W. Bryant, Abita Springs, La., assignor to Mobil Oil
Corporation, Fairfax, Va.

Filed Sep. 12, 1995, Ser. No. 527,116

Int. Cl.⁶ E21B 43/04; 43/08

U.S. Cl. 166—51

13 Claims



1. A well screen for gravel-packing an interval within a wellbore, said well screen comprising:
at least two joints, each of said joints comprising:
a length of screen section; and
at least one axially-extending shunt conduit carried by screen section; and
a well tool for connecting said at least two joints together, said well tool comprising:

at least one by-pass tube axially aligned and forming a fluid path between said at least one axially-extending shunt conduit on each of said joints; and
means on said well tool for preventing any substantial annular, axial flow of fluids past said tool when said well screen is in an operable position within the wellbore.

9. A well tool for connecting at least two joints of well screen together, said well tool comprising:
a central conduit;
at least one by-pass tube axially aligned on said central conduit and adapted to form a fluid path between at least one axially-extending shunt conduit on each of said joints when connected together; and
means on well tool for preventing any substantial annular, axial flow of fluids by said tool when said well screen is in an operable position within the wellbore.

5,588,488

CEMENTING MULTI-LATERAL WELLS

Jan P. Vijn, Leiderdorp; Zacharias Xenakis, Alkmaar, both of
Netherlands; Daniel L. Bour, and Jerry D. Childs, both of
Duncan, Okla., assignors to Halliburton Company, Duncan,
Okla.

Filed Aug. 22, 1995, Ser. No. 518,082


Int. Cl.⁶ E21B 33/14; C04B 7/00

U.S. Cl. 166—293

20 Claims

1. A method of cementing conduits in a multi-lateral subterranean well whereby the set cement can withstand impacts and shocks subsequently generated by drilling and other well operations without shattering, comprising the steps of:

(a) introducing a cement slurry composition which sets into a high strength impact resistant solid mass between said conduits and the walls of said well, said cement slurry composition comprising
a styrene/butadiene aqueous latex,
an effective amount of a latex stabilizer selected from the group consisting of surfactants having the formula



wherein R is an alkyl group having from 5 to 30 carbon atoms, Ph is phenylene and m is an integer in the range of from about 5 to about 50, and surfactants of the general formula



wherein R₁ is selected from table group consisting of C₁–C₃₀ alkyl groups, C₅–C₆ cycloalkyl groups, C₁–C₄ alkyl substituted C₅–C₆ cycloalkyl groups, phenyl, alkyl substituted phenyl of the general formula (R₃)_nPh—where Ph is phenylene, R₃ is a C₁–C₁₈ alkyl group and a is an integer of from 1 to 3, and phenyl (C₁–C₁₈) alkyl groups having a total of from about 8 to about 28 carbon atoms, R₂ is a substituted ethylene group of the formula —CH₂CH R₄ wherein R₄ is selected from hydrogen, methyl, ethyl or mixtures thereof, and n is a number from 0 to about 40 provided that when R₁ is phenyl or alkyl substituted phenyl, n is at least 1 and X is any compatible cation, and hydraulic cement; and

(b) allowing said cement slurry composition to set in said well.

5,588,489

LIGHTWEIGHT WELL CEMENT COMPOSITIONS AND METHODS

Jiten Chatterji, Duncan; James E. Griffith, Loco; Patty L. Totten, and Bobby J. King, both of Duncan, all of Okla., assignors to Halliburton Company, Duncan, Okla.

Filed Oct. 31, 1995, Ser. No. 551,101

Int. Cl.⁶ E21B 33/138

U.S. Cl. 166—293

36 Claims

1. A method of cementing a zone in a well comprising the steps of:

providing a cement composition consisting essentially of slag cement, water present in an amount sufficient to form a pumpable slurry, a gas present in an amount sufficient to foam said slurry and a foaming agent; and
placing said cement composition in the zone.

5,588,490

METHOD AND SYSTEM TO ACHIEVE TWO DIMENSIONAL AIR SPARGING


Suthan S. Suthersan, Yardley, Pa.; Boris Dynkin, Newton, and
Richard Cushing, Reading, both of Mass., assignors to Geraghty & Miller, Inc., Denver, Colo.

Filed May 31, 1995, Ser. No. 456,231

Int. Cl.⁶ E21B 43/18; B01D 19/00

U.S. Cl. 166—370

11 Claims



1. A process for removing volatile contaminants in a two-dimensional configuration from a contaminated area of the earth, wherein the contaminated area of the earth has a phreatic zone, the contaminant being present in the phreatic zone, the process comprising the steps of:

establishing a first borehole in said earth, said first borehole terminating in said phreatic zone;
establishing a second borehole spaced from said first borehole in said earth and which terminates in said phreatic zone;
positioning a first conduit in said first borehole;
positioning a second conduit in said second borehole;
applying air under pressure to said first conduit effective to induce a flow of air from said first conduit into said phreatic zone; and
applying a vacuum to said second conduit effective to induce a flow of air and a gas containing vapor of said contaminant present in said phreatic water out of said second conduit, wherein said air flow through said phreatic zone is substantially perpendicular to the natural flow of said phreatic water.

7. A system for removing volatile contaminants from the phreatic zone of a contaminated ground area, which comprises:
a first borehole terminating in said phreatic zone;
a first conduit disposed within said first borehole;
a second borehole spaced apart from said first borehole and terminating in said phreatic zone;
a second conduit disposed within said second borehole;
a blower operatively connected to said first conduit wherein said first conduit is in fluid flow communication with said blower; and


a vacuum operatively connected to said second conduit wherein said second conduit is in fluid flow communication with said vacuum.

5,588,491

ROTATING BLOWOUT PREVENTER AND METHOD
James D. Brugman, Spring, and Paul L. Tasson, Missouri City, both of Tex., assignors to Varco Shaffer, Inc., Houston, Tex.
Filed Aug. 10, 1995, Ser. No. 513,436
Int. Cl. E21B 33/06; 33/08

U.S. Cl. 166—383

20 Claims



1. A rotatable blowout preventer for use in a hydrocarbon recovery operation including a tubular member passing through the blowout preventer, the rotatable blowout preventer assembly comprising:

a stationary outer housing defining a bore therein for receiving the tubular member, the outer housing having a central axis generally concentric with an axis of the tubular member, and the outer housing including a fluid closing port and a fluid output port therein;

an inner housing rotatable within the outer housing and having an inner curved surface thereon substantially defined by a portion of a sphere having a center substantially adjacent the central axis of the bore;

an annular sealing assembly supported within the inner housing for sealed engagement with the tubular member, a sealing assembly including a plurality of rigid elements circumferentially arranged about the bore of the outer housing, each rigid element having an outer surface for sliding engagement with the inner curved surface of the inner housing, and the sealing assembly including a resilient member for sealed engagement with the tubular member;

a rotatable piston axially movable within the outer housing in response to pressurized fluid in the fluid closing port for causing both axial and radial movement of the annular sealing assembly;

a lower rotary seal between the piston and a lower portion of the stationary outer housing for sealing pressurized fluid within the stationary outer housing from a lower end of the bore in the outer housing;

a flow restriction member between the rotatable inner housing and an upper portion of the stationary outer housing for reducing fluid pressure downstream of the flow restriction member to less than 40% of the pressure upstream from the flow restriction member; and

an upper rotary seal between the rotatable inner housing and the upper portion of the stationary outer housing and downstream from the flow restriction member for sealing the reduced

pressure fluid within the outer housing from an upper end of the bore in the outer housing.

16. A method of controlling actuation of a rotatable blowout preventer for use in a hydrocarbon recovery operation including a tubular member passing through the blowout preventer, the rotatable blowout preventer including a stationary outer housing defining a bore therein for receiving the tubular member, an inner housing rotatable within the outer housing, an annular sealing assembly supported within the inner housing for sealed engagement with the tubular member, a piston movable within the outer housing for causing radial movement of the annular sealing assembly, and a fluid closing port and a fluid output port in the outer housing for passing pressurized fluid to the piston, the method comprising:

providing a lower rotary seal between the piston and a lower portion of the outer housing for sealing pressurized fluid within the stationary outer housing from a lower end of the bore in the outer housing;

providing a flow restriction between the rotatable inner housing and an upper portion of the stationary outer housing for reducing fluid pressure downstream of the flow restriction member to less than 40% of the pressure upstream from the flow restriction; and

providing an upper rotary seal between the rotatable inner housing and an upper portion of the stationary outer housing and downstream from the flow restriction for sealing the reduced pressure fluid within the stationary outer housing from an upper end of the bore in the outer housing.

5,588,492


HAND INJECTOR GAS FIRE EXTINGUISHER
Masaru Fujiki, Tokyo, Japan, assignor to Glory Kiki Co., Ltd., Himeji, Japan

Filed Oct. 5, 1994, Ser. No. 318,296

Claims priority, application Japan, Apr. 7, 1994, 6-095883
Int. Cl. A62C 35/02

U.S. Cl. 169—11

8 Claims



1. A hand injector gas fire extinguisher comprising a hand injector and a cylinder which is filled only with a fire extinguishing gas in a liquid state having a cooling fire extinguishing function based on gasification latent heat of a liquefied gas when gasified and an oxygen deficiency fire extinguishing function based on expansion thereof and which is sealed at a head portion of said cylinder with a seal member, said hand injector having a firing pin unit for breaking said seal member of said cylinder, a cylinder receiving unit for retaining said cylinder and supporting said firing pin unit, a retainer unit for maintaining said firing pin unit in an

inoperative state, and a retainer operating device for releasing said retainer unit by a manual operation and thereby operating said firing pin unit.

wherein said cylinder has a thread on an outer circumferential surface of said head portion thereof, said thread corresponding and engaging a thread on an inner surface on a first end of said cylinder receiving unit, said cylinder receiving unit consisting of a cylinder receiver having a hollow portion into which said head portion is inserted from a first end of said hollow portion by engaging said thread on said cylinder with the thread on the inner surface of a first end of said cylinder receiver, said cylinder receiver also having a through bore, a diameter of said through bore being slightly smaller than that of said hollow portion on a second end of said cylinder receiver and adjacent to said hollow portion; said hollow portion and said through bore communicating with each other so that a joint portion thereof forms a stepped portion,

wherein said firing pin unit consists of:

a shaft which has a flange at a first end thereof, and a recess in which an O-ring is fitted on a second end thereof, the shaft further having a retainer recess in which the retainer unit is fitted in between the second end of said shaft and said O-ring-fitted recess, the shaft being inserted into said cylinder receiver so that the first end of the shaft and the second end of the shaft are respectively fitted in said hollow portion and said through bore of said cylinder receiver;

a firing pin projecting from and fixed to the first end of said shaft; and

a spring provided in a normally compressed state between said flange of said shaft fitted in said cylinder receiver and said hollow portion and said stepped portion constituting said joint portion,

wherein said retainer unit consists of a bent retainer having a pair of leg portions engaged in said retainer recess, and a bolt inserted through a head portion of said retainer unit fixing said head portion to the second end of the cylinder receiver,

wherein said retainer operating device consists of a manual cam engaged between said leg portions of said bent retainer, in such a manner that said leg portions can be opened by turning said cam pivotally around on a surface of a second end of said cylinder receiving unit, and a safety pin provided vertically on the second end of said cylinder receiving unit so as to maintain said leg portions in a normally unopenable condition,

wherein said cam consists of a cam portion having a pair of vertical projections having a width substantially equal to a distance between said leg portions, said projections being opposite each other so that they are spaced from each other by a distance equal to that between said leg portions when moved to an open state, and a manual lever portion joined to said cam portion.

5,588,493

FIRE EXTINGUISHING METHODS AND SYSTEMS
Yechiel Spector; Esther Jacobson, both of Tel Aviv; Vida Naishut, Kiriat Gat; Michael Vittenberg, and Zohar Beinert, both of Beersheva, all of Israel, assignors to Spectronix Ltd., Sderot, Israel

Division of Ser. No. 120,497, Sep. 14, 1993, abandoned. This application Oct. 25, 1994, Ser. No. 328,993

Claims priority, application Israel, Feb. 16, 1993, 104758; Jul. 18, 1993, 106382

Int. Cl. A62C 2/00; 3/00; A62D 1/06


U.S. Cl. 169—46

2 Claims

1. A method of extinguishing a fire in a volume comprising:

(a) submerging a nontoxic fire extinguishing device in a liquid coolant, said device includes means for preventing entry of said coolant into said device; said device includes a composition which comprises:

- (1) a first oxidant reactant; and
- (2) a second reductant reactant;



(b) activating said fire extinguishing device by reacting said composition comprising said first reactant and said second reactant, to create solid particulate products having a diameter of about one micron or less, such that when said products come in contact with the fire, said products chemically inhibit the chain reactions of the fire flame and bring about the extinguishing of the fire; and

(c) passing the said solid particulate products into said liquid coolant without any accompanied destruction of said nontoxic fire extinguishing device.

5,588,494


CROP INVERTER AND METHOD OF USING SAME
J. Paul Pickett; Dee L. Jones, and Jay D. Christensen, all of Burley, Id., assignors to Pickett Equipment, Burley, Id.

Filed Aug. 25, 1995, Ser. No. 519,316

Int. Cl. A01D 29/00

U.S. Cl. 171—124

45 Claims



1. An inverter for digging and inverting crops having pods which are disposed in soil, the inverter comprising:

digging means for loosening soil and for lifting the crops from the soil, the digging means comprising a first rotating bar disposable below the pods of the crop so as to sever roots extending below the pods and a second rotating bar disposed at a level adjacent said pods and disposed such that rotation of the second rod lifts the pods in the soil;

pick-up means for lifting the crops above the soil and for allowing soil to fall from the crops;

inverting means for inverting the crops from an upright growing orientation and placing the crops in a windrow such that the pods are disposed on top of the windrow; and

slinger means disposed between the pick-up means and the inverter means for conveying the crops between the pick-up means and the inverter means and for removing soil from the crops, the slinger means comprising at least one rotatable tube.

5,588,495

ADAPTOR FOR HAND-HELD POWER TOOL

Aiden R. Dear, Stotfold Nr. Hitchin, and John E. Higgs, Potters Bar, both of England, assignors to Avdel Systems Limited, Hertfordshire, England


Filed May 26, 1995, Ser. No. 450,146

Claims priority, application United Kingdom, May 27, 1994, 9410697

Int. Cl.⁶ B23B 51/12

U.S. Cl. 173—170

24 Claims



1. An adaptor for a hand-held power tool which comprises a tool body and a tool trigger located at a position fixed in relation to the body, which adaptor comprises:
securing means for being releasably secured to the tool body in a fixed relationship thereto;
a grip for being gripped by an operator, said grip having a longitudinal axis and being rotatable about the longitudinal axis of the grip when the securing means is secured to the tool body;
an auxiliary trigger mounted on the grip; and
intermediate means for operatively connecting the auxiliary trigger on the rotatable grip to the tool trigger on the tool body; actuation of the auxiliary trigger causes the intermediate means to actuate the tool trigger over a range of relative rotational positions of the grip means and the tool body.

5,588,496

SLIP CLUTCH ARRANGEMENT FOR POWER TOOL

William A. Elger, Waukesha, Wis., assignor to Milwaukee Electric Tool Corporation, Brookfield, Mich.


Filed Jul. 14, 1994, Ser. No. 275,151

Int. Cl.⁶ B60K 41/02; F16D 3/56

U.S. Cl. 173—178

21 Claims

1. A power tool comprising a tool housing, an output shaft



rotatably mounted in the tool housing and including an outer

surface including a plurality of circumferentially spaced detent depressions, a driving member mounted in the tool housing, and a clutch assembly operable to transmit torque from the driving member to the output shaft and including an annular clutch member supported on the output shaft and including a like plurality of circumferentially spaced pockets respectively corresponding to the detent depressions on the output shaft and respectively including ramps extending in acute relation to said output shaft, a like plurality of torque transmitting elements respectively retained in the pockets against circumferential movement relative to the clutch member and being movable between seated positions in the detent depressions to engage torque transmission between the clutch member and the output shaft and unseated positions with respect to the detent depressions to disengage torque transmission between the clutch member and the output shaft, and biasing means engaging the torque transmitting elements to bias the torque transmitting elements against said ramps and toward the seated positions in the detent depressions.

5,588,497

MOUNTING DRILL BITS


Peter R. Thorburn, Welkom, South Africa, assignor to Galison Drilling (Proprietary) Limited, Welkom, South Africa

Filed Feb. 14, 1995, Ser. No. 388,457

Int. Cl.⁶ E21B 10/52; 10/56, 10/62

U.S. Cl. 175—420.1

16 Claims



1. A method of mounting a hard insert in a cutting tool comprising the steps of:
providing a hard insert having a head and a tapered shank;
providing a cutting tool having a body defining at least one seat shaped and tapered complementally to the shank of the insert, the seat having an inner end, an outer end and an upstanding sidewall extending between the inner and outer ends; and
urging the insert into the seat so that the shank of the insert engages the sidewall of the seat in a friction fit, with the end of the shank clear of the inner end of the seat,
wherein both the shank of the hard insert and the sidewall of the seat are tapered conically, with the cone angle of the shank being greater than that of the sidewall, so that when the insert is urged into the seat sufficiently far that the lower end of the shank contacts the sidewall of the seat adjacent the inner end of the seat, the material of the cutting tool body is deformed outwardly at the upper edge of the seat by the upper end of the shank.

5. A cutting tool comprising:
a body defining at least one seat, the seat having an inner end, an outer end and an upstanding sidewall extending between the inner and outer ends; and
a hard insert having a head and a tapered shank retained in the at least one seat;
the seat being shaped and tapered complementally to the shank of the hard insert so that the shank of the insert engages the sidewall of the seat in a friction fit, with the end of the shank clear of the inner end of the seat, wherein both the shank of the hard insert and the sidewall of the seat are tapered conically, with the cone angle of the shank being greater than that of the sidewall.

5,588,498

ELECTRIC HYBRID VEHICLE

Shinichiro Kitada, Tokyo, Japan, assignor to Nissan Motor Co., Ltd., Yokohama, Japan


Filed Oct. 13, 1993, Ser. No. 135,515

Claims priority, application Japan, Oct. 21, 1992, 4-282562

Int. Cl.⁶ B60K 6/02

U.S. Cl. 180—65.4

15 Claims



8. An engine system for driving a generator applied to an electric vehicle, said engine system comprising:
an internal combustion engine intermittently operating for generating electric power by operation of the generator and connected to an intake system and an exhaust system;
an intake air control valve connected to the intake system; and
an intake air control valve controller controlling said intake air control valve so as to suppress the intake air amount at a predetermined small flow rate for a predetermined time after starting of said engine.

5,588,499

TREE STAND


Steven N. Carriere, P.O. Box 792, Lindsay, Ontario, Canada

Filed Mar. 10, 1995, Ser. No. 401,501

Int. Cl.⁶ E04G 3/00

U.S. Cl. 182—135

16 Claims



1. A removable stand for temporary attachment to a tree trunk or the like comprising:
a platform adapted for extending laterally outwardly from the tree trunk, the platform having a load supporting portion between opposing sides;
engaging means on an inward portion of the platform adapted for releasably engaging an adjacent segment of the tree trunk;
a chain having two ends each secured to an opposing side of the platform, the chain adapted for releasably encompassing the

tree trunk upward of said engaging means and defining a plane transverse an axis of the tree trunk, the chain being flexible in said plane and resistant to flexure perpendicular to said plane; and

resilient biasing means engaging the chain for resiliently urging the flexible chain, during lifting or lowering of the stand, in a direction of said plane outwardly from the tree trunk to disengage the chain from the tree trunk;

wherein the chain is comprised of two parallel spaced apart rows of overlapping links transversely interconnected by pins disposed substantially normal to said plane, the links and pins defining a longitudinal series of apertures therebetween;

wherein the biasing means comprise an elongate flexible member having an inherent tendency to assume a selected configuration when unstressed;

the elongate flexible member extending along the length of the chain engaging each link of the chain;

the strand further including a support bracket on each opposed side of the platform, the brackets each comprising:

securing means for adjustably connecting an associated end of the chain to an upper portion of the bracket;

an upwardly extending post having a lower end pivotally connected to an inward portion of an associated side;

an upwardly inwardly inclined strut having a lower end pivotally connected to an outward portion of the associated side; and

connecting means for releasably connecting the upper ends of associated posts and struts members for rotation between an erect operative position and a folded storage position; and

wherein each strut is an inwardly open hollow tube, an associated end of the chain being telescopically housed within each strut, and including a removable connecting rod projecting through mating bores in the upper ends of an associated post and hollow strut, the rod projecting through an aperture of the chain housed within the associated strut.

5,588,500

ELEVATABLE WORK FACILITY

Yoshihiro Yonahara, Ohmiya, Japan, assignor to Japan Steels International Inc., Tokyo, Japan


Filed Nov. 22, 1994, Ser. No. 346,230

Claims priority, application Japan, Sep. 14, 1994, 6-247017

Int. Cl.⁶ E04G 1/18

U.S. Cl. 182—141

15 Claims



1. An elevatable work facility comprising:
a substantially horizontal scaffolding floor having four corners;
four substantially vertical struts respectively comprising four substantially vertical first casings having upper ends respectively connected to said four corners of said scaffolding floor,

and four substantially vertical second casings respectively telescopically coupled with said first casing, one of said first casing and said second casing constituting outer casing and the other of said first casing and said second casing constituting inner casing;

a plurality of transverse rods connected between said outer casings of said struts;

a jack supporting frame fixed between lower parts of said struts;

a fluid-actuated jack attached to said jack supporting frame and extending substantially vertically in parallel to said struts, said jack including a cylinder and a piston slidably mounted in said cylinder, one of said cylinder and said piston being fixed to said jack supporting frame and constituting a fixed jack member, and the other of said cylinder and said piston constituting a movable jack member;

a rotary member rotatably mounted to an upper end of said movable jack member;

a support frame protruding downwardly from said scaffolding floor; and

an elongated flexible member having a first end fixed to said fixed jack member, a second end fixed to said support frame, and an intermediate portion engaged about said rotary member;

whereby movement of said movable jack member a first distance relative to said fixed jack member causes said scaffolding floor to be moved substantially twice said first distance.

5,588,501

Patent Not Issued For This Number

5,588,502


QUICK CONNECT NIPPLE HAVING A CYLINDRICAL MAGNET

Ram D. Bedi, and Adrianus J. van der Griendt, both of Bloomfield Hills, Mich., assignors to K. J. Manufacturing Co., Wixom, Mich.

Filed Aug. 30, 1995, Ser. No. 521,596
Int. Cl.⁶ F16C 3/14

U.S. Cl. 184-1.5

3 Claims



1. A one-piece device for a vehicle for changing oil in an internal combustion engine having an oil pan reservoir, the oil pan reservoir having a floor bottom and an access aperture in the floor bottom; the device comprising:

a quick connect nipple having a first end threadably mating into the access aperture and a second end releasably engageable with a mating quick connect fitting positioned on an externally located fluid delivery device, and having a throughbore therebetween;

means for establishing fluid tight closure of said quick connect nipple when said nipple is disengaged from said fluid delivery device; and

a magnet secured to the first end of the quick connect nipple for capturing metallic material in the oil pan reservoir, said magnet having a through center passage and an upper end exposed to fluid in the oil pan reservoir, said magnet positioned adjacent the throughbore so that oil passes through the center passage of the cylindrical magnet prior to entering the throughbore during the oil changing process.

5,588,503


FLOW CONTROLLER

John M. Rinaldo, E. Greenbush, N.Y., assignor to Atlas Copco Aktiebolag, Sweden

Filed Aug. 21, 1995, Ser. No. 517,505
Int. Cl.⁶ F01M 1/18

U.S. Cl. 184-6.4

18 Claims



1. A flow control apparatus for protecting a rotating machine that is coupled to a primary pump from experiencing lubrication starvation in the event the machine and pump go into reverse rotation, the apparatus including:

a housing having an inlet channel connected to the discharge side of the primary pump and an outlet channel being spaced apart from said inlet channel, said outlet channel being connected to the suction side of the primary pump;

said housing further including a first shuttle passage connecting said spaced apart channels and a second discharge passage spaced apart from said shuttle passage also connecting said spaced apart channels;

a first flow means for connecting said shuttle passage with an oil reservoir;

a second flow means for connecting said discharge passage to the rotating machine for providing lubricating oil to said machine;

a shuttle having axially spaced sealing elements, said shuttle being slidably mounted upon a first slide rod that is centrally positioned in said shuttle passage, said shuttle being arranged to slide along said first slide rod in response to pressure being exerted thereon by oil flowing through said housing to selectively place said first flow means in fluid flow communication with one of said channels; and

a pair of free floating sealing disks that are slidably mounted upon a second slide rod that is centrally mounted in said discharge passage, said disks being arranged to slide along said second slide rod in response to pressure being exerted thereon by oil flowing through said housing to selectively place said second flow means in fluid flow communication with one of said channels.

5,588,504

PROCESS AND ARRANGEMENT FOR SUPPLYING LUBRICANT TO A RECIPROCATING PISTON ENGINE

Leo Spiegel, and Franz Pischinger, both of Aachen, Germany, assignors to FEV Motorentechnik GmbH & Co., Aachen, Germany

PCT No. PCT/EP94/02262, § 371 Date Jun. 1, 1995, § 102(e)
Date Jun. 1, 1995, PCT Pub. No. WO95/02753, PCT Pub. Date Jan. 26, 1995


PCT Filed Jul. 11, 1994, Ser. No. 403,746

Claims priority, application Germany, Jul. 12, 1993, 43 23 262.0

Int. Cl.⁶ F01M 1/00

U.S. Cl. 184-6.8

23 Claims



1. A process for supplying a liquid lubricant to points of a reciprocating piston engine which are to be lubricated and which include at least running surfaces of a piston-cylinder tube unit of the reciprocating piston engine, the reciprocating piston engine having a piston and a cylinder, the process comprising the steps of:

uniting the lubricant in at least one conditioning device with a gaseous transport medium;

forming, in the conditioning device, a lubricating mixture including small liquid particles of lubricant carried by the gaseous transport medium;

passing at least one of the lubricating mixture and the lubricant with the gaseous transport medium through a plurality of supply ducts corresponding to the points to be lubricated; and drawing away, through at least one drain disposed in a region of the points to be lubricated, the gaseous transport medium and excess lubricant from the points to be lubricated.

13. An assembly comprising:

a reciprocating piston engine including a piston cylinder tube unit having:

a cylinder including a cylinder wall, the cylinder wall having therein at least one supply bore for supplying lubricant as small liquid particles carried in a gaseous transport medium to points of the piston cylinder tube unit to be lubricated;

a piston having an outermost surface, an interior region, a piston bearing disposed in the interior region, an uppermost piston ring and a lowermost piston ring, the piston rings being disposed in a circumferential direction about the outermost surface of the piston, the piston being disposed in the cylinder such that it defines an interstice between its outermost surface and the cylinder wall and further being adapted to move axially between a bottom dead center position and a top dead center position, the supply bore in the cylinder wall being disposed such that it discharges lubricant into the interstice and below the uppermost piston

ring when the piston is in its bottom dead center position, the outermost surface of the piston further including:

at least one groove having:

at least one axial groove portion extending, at a region beginning at a lower end of the piston, essentially in an axial direction of the piston, the axial groove further including:

a bottom end disposed at the lower end of the piston such that the supply bore discharges lubricant into the bottom end when the piston is at its bottom dead center position; a lower end portion extending axially upward from the bottom end; and

an upper end portion adjoining and circumferentially offset with respect to the lower end portion such that, during a downward axial movement of the piston before bottom dead center is reached, the supply bore does not communicate with the upper end portion and is covered by the outermost surface of the piston over a predetermined range of the axial movement of the piston;

a circumferential groove portion adjoining the axial groove portion and extending in the circumferential direction of the piston below the lowermost piston ring; and

a transition groove portion disposed between and adjoining both the upper end portion and the circumferential groove portion; and

a draining means for draining the lubricant away from the points of the piston cylinder tube unit to be lubricated, the draining means including a venting bore communicating with the circumferential groove portion and discharging lubricant into the piston bearing disposed in the interior region of the piston; and

a means for supplying liquid lubricant to the reciprocating piston engine, the means being operatively connected to the reciprocating piston engine and including means for transporting the liquid lubricant to the supply bore of the piston cylinder tube unit.

5,588,505

CLEANING ATTACHMENT FOR INTERNAL TUBE MANDREL


Phillip T. Heath, Shelbyville, Tenn., assignor to Calsonic North America, Inc., Irvine, Calif.

Filed Jun. 12, 1995, Ser. No. 489,215

Int. Cl.⁶ F16N 1/00

U.S. Cl. 184-18

21 Claims



1. A cleaning attachment for cleaning the interior surface of a tube during a bending operation that employs an internal mandrel assembly, said cleaning attachment comprising:

a linking member having a free end, a connecting end configured to pivotally couple to said internal mandrel assembly,

and a mounting surface originating proximate said free end and terminating between said connecting end and said free end;

a wiper sized to fit within said tube and having a central mounting hole formed therein, said central mounting hole being configured to slidably engage said mounting surface; and

means for securing said wiper to said linking member.

18. A method for cleaning and supporting the interior surface of a tube during a bending operation, said method comprising the steps of:

providing an internal mandrel assembly having a mandrel shank, a mandrel ball assembly pivotally coupled to said mandrel shank, a socket formed within said mandrel ball assembly, a linking member having a free end and a substantially ball-shaped connecting end configured to reside within said socket such that said connecting end pivotally couples to said mandrel ball assembly, a wiper attached to said linking member proximate said free end, said wiper having a central mounting hole configured to slidably engage said linking member, and a locating rod attached to said mandrel shank;

inserting said internal mandrel assembly into said tube;

applying a lubricant to said interior surface of said tube;

performing a bending operation upon said tube while said interior surface is supported by said internal mandrel assembly;

advancing said tube relative to said internal mandrel assembly during said performing step; and


cleaning said interior of said tube with said wiper during said advancing step.

5,588,506

AIRCRAFT MAINTENANCE ELEVATOR SYSTEM
Ray W. Born, 4211 W. 1st St., Space 21, Santa Ana, Calif. 92704
Filed Jul. 14, 1994, Ser. No. 276,044
Int. Cl. B66F 7/26

U.S. Cl. 187—209

10 Claims



1. An aircraft maintenance elevator system comprising a plurality of elevator platforms;

a plurality of electro-mechanical drive assemblies, each of said drive assemblies being coupled to and operable to selectively raise and lower a respective one of said elevator platforms and comprising:

a plurality of machine screw actuators attached to a respective one of said elevator platforms and mechanically synchronized to maintain the elevator platform level throughout the operational sequence thereof; and

at least two reversible electric drive motors having drive shafts which are mechanically coupled to said machine screw actuators;

wherein the rotation of the drive shafts in a first direction causes the machine screw actuators to raise the elevator

platform and the rotation of the drive shafts in a second direction causes the machine screw actuators to lower the elevator platform;

a control device electrically connected to said drive assemblies, said control device being operational in a first mode wherein said elevator platforms may be raised and lowered independently of each other and a second mode wherein said elevator platforms may be simultaneously raised and lowered.


5,588,507

AIRCRAFT BRAKE ASSEMBLY PROVIDING ADDITIONAL WEARABLE FRICTION MATERIAL
George C. Beardsley, South Bend, Ind.; Brian K. Berk, St. Joseph, Mich.; Albert E. Kartman, South Bend, Ind.; Stanley W. May, Mishawaka, Ind.; Douglas J. Wise, South Bend, Ind.; and Michael J. Zarembka, Granger, Ind., assignors to AlliedSignal, Inc., Morristown, N.J.

Filed Sep. 15, 1995, Ser. No. 529,260
Int. Cl. F16D 55/24

U.S. Cl. 188—71.5

7 Claims



1. An aircraft brake assembly with increased wearable friction material, comprising a torque tube connected with a piston housing, a heat stack comprising friction material stator discs connected with the torque tube and friction material rotor discs for connection with a wheel, and the piston housing including a plurality of pistons for direct engagement with an adjacent friction material stator disc and a piston housing axial extension extending from the piston housing toward the adjacent friction material stator disc, the adjacent friction material stator disc including a recess for receiving the axial extension of the piston housing, the recess comprising a radially extending surface bounded in section view by radially spaced-apart axially extending edges of the recess, whereby an overall axial length of the heat stack, as compared to an aircraft brake assembly having said axial extension and a heat stack including an adjacent friction material stator disc without said recess, is increased to provide additional wearable friction material.

5,588,508

DISK BRAKE USING A PULLED PAD WITH PERMANENT BEARING

Gerard Le Deit, Courtry, France, assignor to AlliedSignal Europe Services Technique, Drancy, France
PCT No. PCT/FR94/00175, § 371 Date Mar. 7, 1994, § 102(e)
Date Mar. 7, 1994, PCT Pub. No. WO94/24454, PCT Pub. Date Oct. 27, 1994


PCT Filed Feb. 17, 1994, Ser. No. 204,246

Claims priority, application France, Apr. 15, 1993, 93 04393
Int. Cl. F16D 55/00

U.S. Cl. 188—73.31

8 Claims

1. A disk brake for a motor vehicle, comprising: a first support which is fixed with respect to the vehicle, a second support shaped into a caliper and slidable with respect to said first support, one of said first and second supports constituting a pad support, first and second pads being held by said pad support so as to resist drive forces developed during a brake application, and a brake motor associated with said second support and capable of being actuated



so as to give rise to the application of said first and second pads onto a rotor by moving in a direction substantially perpendicular to the rotor, said first and second pads each having a central friction zone where a resultant of the drive forces is applied and first and second lateral ends, said first lateral end of at least one of said first and second pads end being offset with respect to said central friction zone in a direction of rotation of said rotor and at least said second lateral end of at least one of said first and second pads having a drive profile, each pad being supported by first and second housings, said second housing having a retaining profile interacting with said drive profile on said second lateral end of at least one of said first and second pads to define a fastening zone to retain each of said pads when each of said pads is stressed in the direction of rotation of the rotor by drive forces, and at least said first lateral end of each pad having an external contact surface suitable for abutting a bearing zone in a corresponding internal contact surface of a first bearing surface located on said first housing, characterized in that each pad is stressed with respect to said first and second housings towards said bearing zone by an elastic force having at least a first component pointing along the radius of the rotor which passes through said central friction zone, said first and second pads each having a relative freedom of rotation in a plane about said fastening zone and said internal and external contact surfaces together define in said bearing zone a tangent in a plane containing each pad and in that a straight line connecting said fastening zone to said bearing zone defines, together with said tangent, an angle inside which said central friction zone is located, said angle being obtuse and less than a flat angle.


5,588,509

SPLINED VIBRATION DAMPING DEVICE USING ER FLUIDS

David A. Weitzenhof, Bath, Ohio; Isao Watanabe, Iruma, Japan; Carmen S. Santa Maria, Uniontown; William S. Niaura, Akron, both of Ohio, and Gareth H. McKinley, Ayer, Mass., assignors to Bridgestone/Firestone, Inc., Akron, Ohio
Filed Oct. 17, 1995, Ser. No. 544,079
Int. Cl. F16F 15/03

U.S. Cl. 188—267

17 Claims



1. A vibrating damping device including:
a metal inner housing forming a piston chamber;

a piston axially movable within the piston chamber and dividing said chamber into two separate fluid chambers, said piston having a piston rod extending out of said inner housing;

an outer housing formed of a dielectric material surrounding at least a portion of the inner housing;

first means for connecting the piston rod to a first support structure;

second means for connecting one of the housings to a second structure spaced from the first structure, whereby a load on said damping device is supported by said one housing and the piston rod;

fluid transfer duct means formed between said inner and outer housings providing fluid communication between said fluid chambers on opposite sides of said piston, said fluid chambers adapted to be filled with an electrorheological (ER) fluid;

metal electrode means mounted in the outer housing and located adjacent the transfer duct means, said electrode means being formed with a plurality of circumferentially spaced splines and intervening grooves extending longitudinally along and adjacent an inner surface of the outer housing throughout at least a portion of the duct means; and

electrical connector means extending through the outer housing and electrically connected to the electrode means for applying the electric field across a portion of the duct means to increase the flow resistance of the ER fluid passing therethrough.


5,588,510

VARIABLE DAMPING FORCE SHOCK ABSORBER
Raud A. Wilke, Dousman, Wis., assignor to HUSCO International, Inc., Waukesha, Wis.

Filed Sep. 25, 1995, Ser. No. 533,234
Int. Cl. F16F 9/46

U.S. Cl. 188—299

22 Claims



1. A shock absorber for variably damping the transmission of forces between a body of a vehicle and a suspension member supporting a road wheel, the vehicle being of the type which has an apparatus for sensing one or more operating conditions and transmitting one or more control signals which are indicative of the operating conditions, the shock absorber comprising:

(a) a housing adapted for connection to one of the vehicle body and the suspension member and defining an internal space, and a piston adapted for connection to the other of the vehicle body and the suspension member and disposed within the internal space for dividing the internal space into a first working chamber and a second working chamber and for moving relative to the housing, the working chambers containing a working fluid;

(b) an assembly of a threshold valve and a main valve adapted to supplementarily control the flow of fluid from the first work-

ing chamber to a receiving chamber, the threshold valve and the main valve having front sides subject to the pressure in the first working chamber and opposite back sides;

(c) a pilot fluid path from the front sides of the threshold and main valves to the back sides;

(d) a pilot circuit providing fluid communication from the pilot fluid path through a variable orifice to the receiving chamber;

(e) an orifice modifier adapted to vary the size of the variable orifice in the pilot circuit;

(f) a remotely controlled actuator adapted to operate the orifice modifier, the actuator being controlled by the one or more control signals;

(g) means for providing for a complete circuit of the fluid among the working chambers and the receiving chamber;

(h) whereby varying the cross sectional area of the variable orifice varies the pressure on the back sides of the threshold valve and the main valve and thereby varies the amount of pressure in the first working chamber needed to open the threshold valve and the main valve.


5,588,511
SEISMIC PIPE RESTRAINT AND METHOD FOR USING THE SAME

Ralph M. Kallenbach, Elgin, Ill., assignor to Sargent & Lundy, Chicago, Ill.

Filed May 15, 1995, Ser. No. 441,138
Int. Cl. F16F 7/12

U.S. Cl. 188—374

15 Claims




1. A load limiting device comprising:
a housing defining a generally cylindrical hollow portion and including a wall defining an inner surface, an outer surface and multiple diameters;
said wall including a first shoulder at a first location where the diameter of said wall changes and a second shoulder at a second location where the diameter of said wall changes;
a shaft at least partially received by said housing;
said shaft including a first wedge defining a first angled surface and a second wedge defining a second angled surface;
said first and second wedges received by said housing and movable within said housing;
one of said housing and said shaft being fixedly connected to an object subject to displacement relative to a support structure and the other of said housing and said shaft being connected to said support structure;
means, located between said first shoulder and said second shoulder, for resisting the movement of said first and second wedges in the region of said housing defined between said first shoulder and said second shoulder;
said resisting means having a first resistance in a first region adjacent said first shoulder, a second resistance in a second region adjacent said second shoulder and a third resistance in a third region between said first region and said second region, said third resistance being substantially greater than said first resistance and said second resistance; and
said first angled surface of said first wedge engaging said first shoulder and plastically deforming said wall once a predetermined amount of relative force has been imparted between said first wedge and said first shoulder and said second angled surface of said second wedge engaging said second shoulder and plastically deforming said wall once a predetermined amount of relative force has been imparted between said second wedge and said second shoulder.

5,588,512
INTERNAL FRAME FOR A WHEELED SUITCASE
Jerhng Lin, Suite 3, 9th Fl, #294, Tun Hwa S. Rd Section 1, Taipei, Taiwan

Filed Jan. 11, 1995, Ser. No. 371,401
Int. Cl. A45C 5/14; 13/04; 13/26

U.S. Cl. 190—115

18 Claims



1. A substantially rectangular internal frame for supporting a wheeled suitcase comprising:
(1) a base having a bottom panel, a left panel and a right panel, the lower ends of the left and right panels vertically connected to the left and right ends of the bottom panel separately;
(2) a U-shaped frame mounted on top of the base comprising a top panel and two side panels, the upper ends of the two side panels vertically connected to the left and right ends of the top panel, the lower ends of the two side panels mounted to the left and right panels of the base separately;
(3) a central frame comprising:
(a) a horizontal U-shaped member having two legs, and
(b) two vertical elongated supporting members, the top ends of the two supporting members connected to the two legs of the U-shaped member; and
(4) a rigid supporting plate; wherein the U-shaped member of the central frame is mounted to the approximately central part of the top panel of the U-shaped frame with the rigid supporting plate mounted in between for strengthening the structure of the central frame and also the connection between the U-shaped member and the top panel and each of the lower ends of the two vertical elongated supporting members of the central frame is mounted to the bottom panel of the base whereby the structure of the internal frame is greatly strengthened by the central frame.


5,588,513
TILT-LOCKING PULL HANDLE FOR A WHEELED SUITCASE
Jerhng Lin, 7548 Donegal Dr., Cupertino, Calif. 95014

Filed Mar. 7, 1995, Ser. No. 400,042
Int. Cl. A45C 5/14; 13/26

U.S. Cl. 190—115

2 Claims

1. A wheeled suitcase comprising:
(1) a substantially rectangular body portion having a rear end and a rear bottom end;
(2) a plurality of wheels mounted on the rear bottom end of the body portion;
(3) a pull handle having a gripping means for gripping the pull handle and at least one elongated rod member connected to said gripping means;
(4) rod receiving means mounted on the rear end of the body portion for slidably receiving the rod member of said pull handle; said rod receiving means comprising an elongated




guiding track on its lower end for guiding said rod member and a head piece on its upper end fixedly connected to said guiding track for restricting said rod member at an utmost position within said guiding track wherein the lower part of said rod member is slidably engaged and restricted within said guiding track by said head piece; said guiding track comprising a U-shaped channel along its centerline and two protruding edges along two opposite ends of said U-shaped channel, each of said two protruding edges further comprising a plurality of fastening holes for fastening said head piece wherein said head piece is fastened to said fastening holes of said guiding track by a plurality of fasteners; and
(5) locking means installed in said rod receiving means for locking said rod member to prevent said rod member from moving downward when said rod member is extended to said utmost position within said rod receiving means and said wheeled suitcase is tilted toward its rear end by using said gripping means of the pull handle, and unlocking said rod member when said wheeled suitcase is repositioned to an upright position;
wherein said head piece further comprises a hooking means for hooking the top end of said guiding track wherein said head piece is fixedly connected to said guiding track by using said fasteners on its lower end and said hooking means on its upper end.

5,588,514
STEERING COLUMN MECHANICAL BRAKE INTERLOCK SYSTEM
William M. Snell, Grand Blanc, Mich., assignor to Chrysler Corporation, Auburn Hills, Mich.

Filed May 15, 1995, Ser. No. 442,246
Int. Cl. B60K 41/26

U.S. Cl. 192—4 A

4 Claims



4. In a transmission shift control assembly including a detent plate having a plurality of detents formed thereon including a Park detent, a shift lever having an end thereof pivotable into and out of the Park detent and rotatable to selected detents, a pivotally mounted spring-loaded flip cam, a blocker member pivotally mounted on said detent plate, a linkage member operatively connected between said flip cam and said blocker member adapted to selectively pivot said blocker member into and out of engagement with the end of the shift lever while the shift lever is in the Park detent position, a brake lever and associated brake pedal, and a

spring for urging the brake lever from a depressed state to an undepressed state, a mechanical brake interlock system comprising spring-loaded cable means operatively connected between an actuator assembly and said blocker member, said brake lever abutting against said actuator assembly to prevent said blocker member from being pivoted away from said end of said shift lever until said brake pedal is depressed and released from said actuator assembly, said actuator assembly including a bracket, an actuator member having first and second ends and pivotally mounted between said ends on said bracket, said cable means including a cable having one end secured to the first end of said actuator member, a second spring having one end secured to said actuator member and the other end secured to said bracket, and a link connected to the second end of said pivotally mounted actuator member, said bracket lever serving when said brake pedal is not depressed to abut against said link to thereby pivot said actuator member against the force of said second spring to pull on said cable and in turn, pivot said blocker member.

5,588,515
METHOD OF AND APPARATUS FOR SPEED CHANGE CONTROL

Makoto Toyama, and Yoshikazu Asai, both of Ishikawa, Japan, assignors to Kabushiki Kaisha Komatsu Seisakusho, Tokyo, Japan


PCT No. PCT/JP93/01289, § 371 Date Mar. 10, 1995, § 102(e) Date Mar. 10, 1995, PCT Pub. No. WO94/05523, PCT Pub. Date Mar. 17, 1994

PCT Filed Sep. 10, 1993, Ser. No. 397,206

Claims priority, application Japan, Sep. 10, 1992, 4-268082 Int. Cl. B60K 41/26

U.S. Cl. 192—4 C

16 Claims



selecting from the thus stored braking data a braking force in accordance with the thus detected rotational speed of said output shaft;

applying, in response to a providing of said signal directing a shift between forward travel and reverse travel, the thus selected braking force to said output shaft to effect a braking torque on said output shaft;

engaging a predetermined clutch among said plurality of clutches in response to a providing of said signal directing a shift between forward travel and reverse travel;

increasing the thus applied braking force until a speed of said vehicle is reduced to a predetermined value, and

then gradually decreasing the thus applied braking force to zero while gradually increasing an engagement of said predetermined clutch so as to cause a deceleration/acceleration of the vehicle given through said output shaft to smoothly change along said target deceleration/acceleration curve to thereby decrease shock to the vehicle upon a completion of the engagement of said predetermined clutch.

5,588,516

SYNCHRONIZER WITH SELF-ENERGIZING


Eugene R. Braun, Royal Oak, and Otis J. Olson, Farmington Hills, both of Mich., assignors to Eaton Corporation, Cleveland, Ohio

Continuation-in-part of Ser. No. 408,453, Mar. 22, 1995, abandoned, which is a continuation of Ser. No. 172,789, Dec. 27, 1993, abandoned. This application May 23, 1995, Ser. No. 448,158

Int. Cl.⁶ F16D 23/08; F16H 3/38

U.S. Cl. 192—48.91

19 Claims



1. A clutch mechanism for frictionally synchronizing and positively connecting first and second drive members disposed for relative rotation about a common axis; the clutch mechanism including:

- first drive means including a plurality of circumferentially spaced apart first drive teeth and a first drive friction surface affixed to the first drive member;
- a hub affixed to the second drive member and including an outer circumference and first and second axially oppositely facing ends, the outer circumference including a plurality of first grooves defined by flank surfaces of circumferentially spaced apart external splines;
- a first baulk ring axially interposed between the hub and the first drive means and axially movable therebetween, the baulk ring including circumferentially spaced apart angled blocker surfaces axially facing in the direction of the hub, the baulk ring including a friction surface engageable with the first drive

friction surface for producing a synchronizing torque, and the baulk ring including abutment means for limiting rotation of the baulk ring relative to the hub;

a shift sleeve having an inner circumference and an axial length defined between first and second axially facing ends thereof, the inner circumference including a plurality of circumferentially spaced apart first teeth axially movable from a neutral position disposed in the first grooves to engaged positions with the first drive teeth in response to an axially directed shift force (+F_s) acting on the sleeve, the sleeve first teeth in the direction of the baulk ring including ends at the sleeve first end having angled blocker surfaces;

pre-energizer means operative in response to initial axial movement of the sleeve from the neutral position to move the baulk ring friction surface into engagement with the first drive friction surface for rotating the baulk ring angled blocker surfaces to positions engaged by the sleeve first teeth angled blocker surfaces for blocking asynchronous engagement of the first drive teeth and sleeve first teeth, for transmitting the shift force (+F_s) across the engaged blocker surfaces to effect an increased engagement force of the baulk ring friction surface with the first drive friction surface, and for producing via the angled blocker surfaces a torque counter to the synchronizing torque for moving the baulk ring and sleeve first teeth angled blocker surfaces out of engagement as synchronization is reached;

self-energizing means including first angled self-energizing surfaces affixed to the sleeve and hub and movable into engagement in response to engagement of the blocker surfaces and relative rotation between the sleeve and hub, the angled self-energizing surfaces positioned oblique to a plane normal to the axis and operative when engaged to react to the synchronizing torque for producing an additive axial force (+F_a) transmitted across the blocker surfaces in the direction of the shift force (+F_s) for further increasing the engagement force of the friction surfaces; the improvement comprising:

the sleeve first teeth having a length less than the sleeve length and extending axially from the sleeve first end toward the sleeve second end, the sleeve inner circumference including a plurality of circumferentially spaced apart second teeth extending axially from the sleeve second end toward the sleeve first end, adjacent pairs of the first and second teeth having a combined length less than or equal to the axial length of the sleeve;

the hub including a plurality of second grooves defined by flank surfaces of the splines and alternately spaced between the first grooves and slidably receiving the sleeve second teeth, the flank surfaces of axially extending portions of the first and second grooves respectively having at least a portion of the sleeve first and second teeth disposed therein during the neutral position and the engaged position of the blocker surfaces, the flank surfaces of the axially extending portions having a circumferential spacing relative to the teeth therein for allowing the relative rotation between the sleeve and hub to effect engagement of the self-energizing means, and the flank surfaces of another axially extending portion of the second grooves closely receiving the sleeve second teeth when the first drive and sleeve first teeth are engaged for preventing relative rotation therebetween.

5,588,517

CLUTCH OPERATING APPARATUS

Ad Kooy, Lauf; Helmar Bier, Ettlingen, and Norbert Mebus, Bühlertal, all of Germany, assignors to LuK Lamellen und Kupplungshau GmbH, Bühl, Germany

Filed Sep. 13, 1994, Ser. No. 305,519


Claims priority, application Germany, Sep. 13, 1993, 43 30 886.4; May 25, 1994, 44 18 023.3

Int. Cl.⁶ F16D 13/54

U.S. Cl. 192—70.25

45 Claims

1. Apparatus for operating a clutch, particularly a friction clutch located between a prime mover and a transmission, said clutch having operating means rotatable about a predetermined axis and movable in the direction of said axis between first and second



positions in which the clutch is respectively engaged and disengaged and said operating means being moved in the direction of said axis as a result of progressing wear upon at least one component of the clutch, comprising:

- a bearing including a rotary portion movable in the direction of said axis to move said operating means from one to the other of said positions;
- a carrier;
- at least one support mounted on said carrier;
- an actuator mounted on said at least one support for rotation about said axis relative to said at least one support and for movement relative to said carrier in the direction of said axis to thus move said operating means from one to the other of said positions by way of said bearing;
- means for moving said actuator relative to said at least one support in the direction of said axis in response to rotation of said actuator relative to said at least one support; and
- means for at least partially compensating for said wear, including means for moving said bearing in the direction of said axis relative to said carrier.

5,588,518

CLUTCH DISC WITH A REINFORCED HUB

Reinhard Feldhaus, Ebenhausen, Germany, assignor to Fichtel & Sachs AG, Schweinfurt, Germany

Filed Mar. 8, 1995, Ser. No. 400,365

Claims priority, application Germany, Mar. 9, 1994, 44 07 766.1


Int. Cl.⁶ F16D 13/68; 3/12

U.S. Cl. 192—204

19 Claims

1. Clutch disc for a motor vehicle clutch, said clutch disc comprising:

- a first cover plate;
- a second cover plate;
- means for substantially fixedly connecting said first and second cover plates with respect to one another;
- a hub;
- said hub having means for connecting with a transmission of a motor vehicle;
- said hub being being oriented concentrically about a rotational axis;
- said hub having a length;
- the length of said hub being defined generally parallel with the rotational axis;
- said hub comprising an inner surface;
- said hub comprising an outer peripheral surface;
- said outer peripheral surface being disposed substantially further away from the rotational axis than said inner surface;
- said outer peripheral having a length;



the length of said outer peripheral surface being defined generally parallel to the rotational axis;

the length of said outer peripheral surface being substantially similar to the length of said hub;

torsional damper means for damping torsional vibrations;

said torsional damper means comprising:

- an input portion;
 - an output portion; and
 - means for transmitting a torsional force from said input portion to said output portion;
- means for stiffening said hub so as to inhibit plastic deformation of said hub;
- said stiffening means comprising at least one stiffening portion, said at least one stiffening portion comprising at least a portion of at least one of said input portion and said output portion of said torsional damper means; and
- said at least one stiffening portion being oriented generally parallel with respect to the rotational axis of said hub;
- said at least one stiffening portion comprising at least one essentially tubular member; and
- said at least one essentially tubular member being in contact with said outer peripheral surface over a substantial portion of the length of said outer peripheral surface.

5,588,519

Patent Not Issued For This Number

5,588,520

CROSSBELT SORTATION SYSTEM

Artemio Affaticati, Cadeo; Claudio Cerutti, Borgomanero, and Teodoro Ceglia, Turin, all of Italy, assignors to Rapistan Demag Corp., Grand Rapids, Mich.

Continuation of Ser. No. 300,968, Sep. 6, 1994, abandoned.


This application Feb. 26, 1996, Ser. No. 606,547

Int. Cl.⁶ B65G 47/46

U.S. Cl. 198—370.06

63 Claims

1. A method of conveying parcels on a plurality of transport units moving in a conveying path between an induction station and a discharge station, each transport unit having a driven carrier belt thereon which is moveable orthogonally to the conveying path, said induction station having at least one induction belt extending at an angle to the conveying path, said discharge station having a plurality of receiving ports positioned along said conveying path, including:



determining the length of parcels at said induction station; for parcels having a length less than a given length operating said at least one induction belt and said carrier belts of at least one of said transport units to position a parcel on said one of said transport units; and for parcels having a length greater than said given length operating said at least one induction belt and said carrier belts of at least two contiguous transport units in order to position a parcel on said at least two transport units.

5,588,521


METHOD AND APPARATUS FOR MATERIAL HANDLING

Jon Laidig; Dale Updike, and Alan Amick, all of St. Joseph County, Ind., assignors to Laidig, Inc., Mishawaka, Ind.
Filed Jun. 5, 1995, Ser. No. 463,766

Int. Cl.⁶ B65G 47/19

U.S. Cl. 198—532

10 Claims




1. An apparatus for controlling the flow of particulate, granular or fluidized matter between a storage receptacle and a conveyor, that apparatus being disposed between said receptacle and said conveyor and comprising:

- a plurality of individually movable flow gates, each of which defines an opening between said receptacle and said conveyor, and
- a cam member sequentially engagable with said flow gates to selectively open and close said flow gates to permit said matter to move between said receptacle and said conveyor.

5,588,522 RECIPROCATING FLOOR CONVEYOR FOR CONVEYING PALLETIZED LOADS OR THE LIKE Raymond K. Foster, and Randall M. Foster, both of Madras, Oreg., assignors to Raymond Keith Foster, Madras, Oreg. Filed Oct. 24, 1994, Ser. No. 327,630 Int. Cl.⁶ B65B 25/00

U.S. Cl. 198—775

20 Claims



1. A reciprocating floor conveyor for conveying articles having fixed-form wide bases, comprising:
a support frame;
a plurality of laterally spaced-apart conveyor slats mounted on the support frame for longitudinal reciprocation between a start position and an advanced position, the conveyor slats having upper surface portions with a constant vertical height that defines a horizontal conveying plane;
a plurality of laterally spaced-apart holding slats mounted on the frame for vertical movement between an up position in which the upper surfaces of the holding slats are above the conveying plane defined by the conveyor slats and the articles are supported by the holding slats, and a down position in which the upper surfaces of the holding slats are below the conveying plane and the articles are supported by the conveyor slats; each holding slat including a top, two laterally spaced sides extending downwardly from the top, and two bottom flanges, one extending laterally from a bottom portion of each side; the conveyor slats and the holding slats being distributed across the conveyor in a pattern resulting in both conveyor slats and holding slats being below each article on the conveyor;
a holding slat base for each holding slat, each holding slat base having opposite laterally extending flanges positioned between the bottom flanges and the top of the corresponding holding slat to limit vertical movement of the holding slat; wherein a collapsible pocket is formed vertically between the holding slat and its base; and
an expandable member located in each collapsible pocket, wherein expansion of the expandable members raises the holding slats from their down position to their up position to lift any articles on the conveyor up off the conveyor slats to permit the conveyor slats to be retracted from their advanced position to their start position while the conveyor slats are out of contact with the articles.

5,588,523

ROLLER DRIVING DEVICE

Shoji Hara; Takenori Yanai, both of Kounan, and Kazuhiko Ishikawa, Inuyama, all of Japan, assignors to Murata Kikai Kabushiki Kaisha, Kyoto, Japan


Filed Dec. 7, 1994, Ser. No. 350,531

Claims priority, application Japan, Dec. 10, 1993, 5-341480
Int. Cl.⁶ B65G 13/06

U.S. Cl. 198—781.08

4 Claims

1. A roller driving device comprising:
a base frame;
a carrier roller mounted in said base frame for rotation about a central axis;
a driving rotation shaft disposed below said carrier roller;
a bearing member disposed beneath said carrier roller;
a pivot shaft disposed perpendicularly with respect to said central axis of said carrier roller and mounting said bearing member for pivotal movement;
a transmission roller and a wheel concentric thereto rotatably carried by said bearing member on one side of said pivot shaft;
a brake shoe carried by said bearing member on the other side of said pivot



a an endless belt extending around said wheel and the driving rotation shaft for rotating said transmission roller; and means for pivoting said bearing member about said pivot shaft to place either said transmission roller or said brake shoe alternatively in contact with said carrier roll.

5,588,524


PUSH WHEEL SWITCH

Ching-Lung Wu, P.O. Box No. 2103, Taichung City, Taiwan
Filed Oct. 6, 1995, Ser. No. 540,553

Int. Cl.⁶ H01H 13/00

U.S. Cl. 200—552

4 Claims



1. A push wheel switch comprising:
a housing having a cavity open on one end formed by a bottom wall extending between a pair of longitudinally directed side walls and first and second end walls;
said first end wall having a pair of push button holes formed therethrough and a display window disposed between said pair of push button holes;
a circuit board positioned over said housing open end and forming a closure therefor;
an inner shaft seat extending from said housing bottom wall into said cavity, said inner shaft seat having attached thereto a longitudinally directed first stopper block, said first stopper block having a distal end to which is attached a pair of oppositely directed second stopper blocks, each of said pair of second stopper blocks being directed in a direction transverse said first stopper block;
a toothed wheel disposed within said cavity and having a shaft hole formed therethrough for rotatable coupling about said shaft seat, said toothed wheel having an outer peripheral surface defining a numeral face for displaying a predetermined number of display numerals through said display window; said toothed wheel having a predetermined number of peripheral tooth spaces, each of said peripheral tooth spaces being formed by a pair of opposing tooth faces;

5,588,525

CONTAINER FOR ANNULAR WORKPIECE

Peter Rösler, Wangen, Germany, assignor to Rose-Plastic GmbH, Hergensweiler, Germany


Filed Feb. 8, 1996, Ser. No. 598,458

Claims priority, application Germany, Feb. 13, 1995, 295 02 288.4

Int. Cl.⁶ B65D 85/02

U.S. Cl. 206—303

12 Claims



1. A container for storing annular workpieces having a slot across a circumference thereof, said container comprising:
an inner core part having a first length section formed as a smooth cylindrical body having a rib extending parallel to a container axis substantially along an entire longitudinal extent of the first section for engagement in slots of the stored annular workpieces, and a second length section adjoining the first length section and formed as a substantially cylindrical body having a diameter larger than a diameter of the smooth cylindrical body forming the first section; and


an outer jacket part having an inner circumferential surface spaced from an outer circumferential surface of the smooth cylindrical body forming the first section and adjoining an outer circumferential surface of the cylindrical body forming the second section.

5,588,526

FLAT BOX SYSTEM WITH MULTIPLE VIEW OPTICS
Stephen D. Fantone, Lynnfield, Mass.; Anthony L. Gelardi, Cape Porpoise, and John A. Gelardi, Kennebunkport, both of Me., assignors to Insight, Inc., Lynnfield, Mass.
Continuation-in-part of Ser. No. 222,632, Apr. 1, 1994. This application Nov. 14, 1994, Ser. No. 338,246
Int. Cl.⁶ B65D 85/57

U.S. Cl. 206—308.1

38 Claims



1. A box system for containing at least one flat object and providing visual information about the flat object, said box system comprising:

- a multisided flat box comprising a pair of opposed flat walls interconnected by a plurality of shallow side walls to provide an interior chamber for the flat object, said pair of opposed flat walls and said plurality of shallow side walls being joined to releasably receive the flat object, at least one of said pair of opposed flat walls having a transparent lenticulated section composed of a plurality of parallel lenticules having a focal plane optically associated therewith;
- a compliant insert bearing at least two interlaced preprinted images, said compliant insert being removably insertable into said interior chamber and located in a plane substantially parallel and proximate to said transparent lenticulated section so that said interlaced preprinted images are in optical registration therewith, said compliant insert being further located substantially in said focal plane of said transparent lenticulated section to provide different information to an observer looking at said transparent lenticulated section from different angular perspectives.


5,588,527

STORAGE CONTAINER WITH INTEGRAL FLAP
Ross O. Youngs, Dublin, Ohio, assignor to Univenture, Inc., Dublin, Ohio
Continuation of Ser. No. 276,055, Jul. 15, 1994, Pat. No. 5,462,160, which is a continuation of Ser. No. 998,957, Dec. 31, 1992, abandoned. This application Jun. 6, 1995, Ser. No. 468,724
Int. Cl.⁶ B65D 85/30; 85/57

U.S. Cl. 206—308.1

4 Claims

- 1. A storage container for storing a compact disc having an aperture and an edge, said storage container comprising:
 - a first flexible sheet;
 - a nonwoven fabric sheet overlaying said first flexible sheet;
 - a second flexible sheet overlaying said nonwoven fabric sheet opposite said first flexible sheet and joined to said first flexible sheet through said nonwoven fabric sheet to define a compact



disc storage area for holding said compact disc, said second flexible sheet having a cut to define a flap portion which hinges along a hinge line and opens along an opening line to allow access to said compact disc storage area, wherein said flap portion extends from said hinge line at least to an approximate center point of said compact disc storage area to overlie at least a portion of the aperture of said compact disc when said compact disc is fully received in said compact disc storage area thereby permitting simultaneous access to both the edge and aperture of said compact disc upon opening of said flap portion;

- a binding strip along one edge of said container including binding structure for enabling a plurality of said storage containers to be bound together;
- an elongate graphics storage pocket disposed between said compact disc storage area and said binding strip.

5,588,528

OPTICAL RECORDING DISC STORING DEVICE
Jiro Ozeki, Toshima-ku, Japan, assignor to Slidex Corporation, Tokyo, Japan


Filed Apr. 16, 1996, Ser. No. 632,833

Claims priority, application Japan, Sep. 29, 1995, 7-252125

Int. Cl.⁶ B65D 85/57

U.S. Cl. 206—308.1

11 Claims



- 1. An optical recording disc storing device which comprises:
 - a sheet-like storing element having at least one rectangular frame formed on at least one side thereof and a circular frame formed in said rectangular frame which surrounds a circular bottom area, at least a portion of said circular area being cutout to form a cutout opening, said circular frame being cut-off at a position adjacent to at least one of four corners of said rectangular frame;

a film of a flexible material attached to said storing element at said one side to cover said area surrounded by said circular frame;

said circular frame of said storing element having an inner diameter which is larger than outer diameter of a recording disc which is to be stored in said circular frame, said circular frame having an inner periphery slanted radially inwardly to provide a slanted surface for receiving peripheral edge portion of the recording disc to support the disc with a clearance against said bottom area surrounded by said circular frame;


said film of the flexible material being formed with a slit along a split line extending in a direction crossing said circular frame so that said film can be turned over at one side of said split line to have an access by fingers to the edge portion of the recording disc stored in said circular frame to take out the recording disc.

5,588,529

BASEBALL/SOFTBALL EQUIPMENT BAG
Michael W. Speck, 6624 Wanita, Houston, Tex. 77007
Continuation of Ser. No. 247,327, May 23, 1994, abandoned.
This application Sep. 1, 1995, Ser. No. 522,542
Int. Cl.⁶ B65D 85/20

U.S. Cl. 206—315.1

5 Claims



- 1. A hanging baseball equipment bag comprising:

a flexible, elongated bag having a length, a top end and a bottom end, a front, a back, a left side and a right side, said elongated bag being non-rigid in a direction between said top and bottom ends;

fence clips for vertically hanging said elongated bag from a chain link fence;

a substantially planar and rigid interior shelf substantially medially positioned between said top and bottom ends within said flexible, elongated bag, said interior shelf is substantially horizontal when said flexible, elongated bag vertically hangs from said fence clips in a substantially vertical position;

a flexible interior rear panel attached to the interior of said flexible, elongated bag and oriented substantially parallel to said back, said interior rear panel dividing said flexible, elongated bag into a front compartment extending substantially the length of said elongated bag and a rear compartment extending substantially the length of said elongated bag, said front compartment divided into an upper front compartment and a lower front compartment by said interior shelf,

wherein said front compartment is located between said front and said interior rear panel and said rear compartment is located between said back and said interior rear panel; and means for accessing said front compartment and said rear compartment in said front and said top end.

5,588,530


WRAPPING MATERIAL FOR WRAPPING A FLORAL GROUPING HAVING STAGGERED STRIPS OF ADHESIVE MATERIAL APPLIED THERETO AND METHOD

Donald E. Weder, Highland, Ill., and Franklin J. Craig, Valley Park, Mo., assignors to Southpac Trust International, Inc., Oklahoma City, Okla.

Continuation of Ser. No. 803,318, Dec. 4, 1991, Pat. No. 5,344,016, which is a continuation-in-part of Ser. No. 707,417, May 28, 1991, abandoned, which is a continuation of Ser. No. 502,358, Mar. 29, 1990, abandoned, which is a continuation-in-part of Ser. No. 391,463, Aug. 9, 1989, abandoned. This application May 16, 1994, Ser. No. 243,339
Int. Cl.⁶ B41L 1/32; B65D 5/02; B65B 25/14

U.S. Cl. 206—451

7 Claims



- 1. A pad of wrapping material, comprising:

a plurality of sheets of material stacked one on top of the other to form the pad, each sheet of material having an upper surface, a lower surface and a strip of adhesive disposed on one of the upper and lower surfaces such that each sheet of material is releasably connected to an adjacent sheet of material via the strip of adhesive, the strips of adhesive arranged on the sheets of material in alternating vertical alignment such that each sheet of material is disposed substantially parallel to the adjacently disposed sheet of material.

5,588,531

GLASS SUBSTRATE TRANSPORT BOX
Toshio Yoshida, Osaka, and Toshio Akai, Kyoto, both of Japan, assignors to Yodogawa Kasei Kabushiki Kaisha, and Sharp Kabushiki Kaisha, both of Osaka, Japan


Filed Nov. 8, 1994, Ser. No. 337,424

Claims priority, application Japan, Nov. 9, 1993, 5-304668

Int. Cl.⁶ B65D 85/48

U.S. Cl. 206—454

2 Claims



- 1. In a glass substrate transport box comprising either (A) a generally rectangular, bottomed body and a lid or (B) a generally

rectangular, unbottomed body, a lid and a bottom member, said bottomed or unbottomed body having grooves on at least one pair of its opposed inner walls for supporting glass substrates, the improvement wherein

each of said body, lid and bottom member is a molded piece of polyolefin foam with a foaming ratio of 4-25 as a whole, inner and outer sides of the wall of said body, lid and bottom member have a dense skin layer relative to the interior portion of the wall, where a relative density of the skin layer down to a depth of 1 mm from the surface is at least 2 times as great as the interior portion density of the wall, and said polyolefin foams are those obtained by filling metal mold with polyolefin beads containing a blowing agent or a primary foam obtained from such beads and heating the mold.

5,588,532

SELF-SEALING INFLATABLE BAG AND METHOD FOR PACKAGING AN ARTICLE THEREIN


Daniel A. Pharo, Valencia, Calif., assignor to Air Packaging Technologies, Inc., Del.

Filed Sep. 15, 1994, Ser. No. 306,883

Int. Cl.⁶ B65D 81/02

U.S. Cl. 206-522

12 Claims



1. A inflatable package adapted to be formed into a packaging system for retaining an item therein comprising:

a pair of overlying inner panels defining an item-receiving zone therebetween to have an item retained therein;

a pair of outer panels each overlying a respective one of said inner panels, each said outer panel being associated with a different one of said inner panels to form an inflatable chamber therebetween;

securing means for securing overlying edge portions of each respective pair of said inner and outer panels together along all overlying edge portions of each respective pair of said inner and outer panels and for securing overlying edge portions of said inner panels together along at least two substantially parallel edge portions of said inner panels so that said inner panels remain unattached to each other along at least one section of the overlying edge portions of said inner panels to allow insertion of said item into said item-receiving zone; inflating means for at least partially inflating said inflatable chambers with a filler medium;

wherein said inflatable chambers are divided into a plurality of sections by bonding each respective pair of said inner and outer panels along an interior portion of each respective pair of said inner and outer panels, so that the bonding between each respective pair of said inner and outer panels is not uniform and complete, the filling medium can pass between adjacent sections, the bonding is not co-extensive with said two substantially parallel edge portions of said inner panels, and there is a portion of each of said inflatable chambers which is shaped to substantially enclose said item-receiving zone upon inflation;

said filling medium communicates between said inflatable chambers through said inner panels via respective holes in said inner panels, said inner panels being bonded together around said holes;

said inflatable chambers are sealed upon inflation by inflation pressure acting upon said inflating means; and said item-receiving zone is automatically sealed upon inflation of said inflatable chambers to retain said item therein.

5,588,533

INFLATABLE PACKAGING CUSHION


Brian K. Farison, New Milford, and William R. Armstrong, Newtown, both of Conn., assignors to Sealed Air Corporation, Saddle Brook, N.J.

Filed Dec. 1, 1995, Ser. No. 565,664

Int. Cl.⁶ B65D 81/02

U.S. Cl. 206-522

11 Claims



1. An inflatable packaging cushion of flexible material adapted to be at least partially charged with filler medium and having an external peripheral edge adapted to the shape and dimensions of a packaging receptacle comprising:

said cushion having at least one internal opening capable of receiving an article to be packaged such that the sides of said article are completely encircled a pair of inflatable end chambers interconnected with a pair of inflatable side chambers via passageways;

a pair of inflatable bottom panels interconnected to each of said end panels and at least one tie strap located in said internal opening connecting said bottom panels so as to maintain them in position when said cushion is inflated;

a plurality of recesses extending from said internal opening toward the peripheral edges of said recesses delimiting wedging parts as portion of said side chambers, said wedging parts capable of coming into contact with the sides of said article, zones for pivoting of the wedging parts being defined between the recesses and the peripheral edge,

said wedging parts being adapted so as to automatically pivot during inflation of the inflatable packaging cushion about a line extending generally between two successive recesses in order to vary the size and shape of each internal opening, said internal opening being completely encircled by said wedging parts;

at least one internal opening between each of said bottom panels and said end chambers to facilitate said cushion extending around the bottom ends of said article; and filling means for at least partially charging said cushion with filler medium.

9. An inflatable packaging cushion of flexible thermoplastic material adapted to be at least partially charged with air and having an external peripheral edge adapted to the shape and dimensions of a packaging receptacle comprising:

said cushion having a pair of juxtaposed thermoplastic sheets having the outer peripheral edges thereof sealed together to form said cushion and having at least one internal opening capable of receiving an article to be packaged such that the sides of said article are completely encircled a pair of inflatable end chambers interconnected with a pair of inflatable side chambers via passageways;

a pair of inflatable bottom panels interconnected to each of said end panels and at least one tie strap located in said internal opening connecting said bottom panels so as to maintain them in position when said cushion is inflated;

a plurality of recesses extending from said internal opening toward the peripheral edges of said recesses delimiting wedging parts as portion of said side chambers, said wedging parts capable of coming into contact with the sides of said article, zones for pivoting of the wedging parts being defined between the recesses and the peripheral edge,

said wedging parts being adapted so as to automatically pivot during inflation of the inflatable packaging cushion about a line extending generally between two successive recesses in order to vary the size and shape of each internal opening, said internal opening being completely encircled by said wedging parts;

at least one internal opening between each of said bottom panels and said end chambers to facilitate said cushion extending around the bottom ends of said article;

at least on internal opening between each of said bottom panels and said end panels;

at least one inflatable top chamber interconnected to said end chamber and having at least one internal opening between said at least one top chamber and said end chamber; and a single self-sealing inflation valve for at least partially charging said cushion with air.

5,588,534

GARBAGE SEPARATOR SYSTEM


Denis Harel, 2160 Blvd. Lafleche, Baie Comeau, Quebec, Canada

Filed Sep. 30, 1994, Ser. No. 315,441

Int. Cl.⁶ B07C 5/02

U.S. Cl. 209-3.1

11 Claims



1. A garbage separating apparatus comprising at least first and second conveyors, each of said conveyors having an input end and a discharge end, said conveyors being arranged such that material discharged from a side of said first conveyor will be deposited on said second conveyor, each conveyor being tilted with respect to the horizontal in a direction substantially normal to the direction of conveyor operation, vibrating means operatively associated with each of said conveyors to impart a vibratory movement thereto, and means for feeding material to the input end of said first conveyor.

5,588,535

SAMPLE PREPARATION SYSTEM FOR SEPARATING WEAR PARTICLES BY SIZE AND MAGNETIC CHARACTERISTICS


Michael G. Thornton, and Janine M. Thornton, both of Littleton, Colo., assignors to Synectic Technology, Inc., Littleton, Colo.

Filed Oct. 12, 1994, Ser. No. 322,185

Int. Cl.⁶ B03C 1/30

U.S. Cl. 209-38

20 Claims



1. A system for preparing samples of wear particles comprising: a filter;

a housing having a passage with an inlet for receiving a flow of wear particles suspended in a fluid and an outlet;

at least one particle trap having openings for retaining wear particles larger than a predetermined size and for passing fluid and wear particles smaller than said size, with mounting means for selectively moving said particle trap between a first position in which said particle trap substantially blocks said housing passage while said flow of wear particles and fluid is introduced into said inlet, and a second position in which said passage is substantially unblocked by said particle trap;

means for rinsing wear particles from said particle trap in said second position; and

means for selectively directing said flow from said outlet of said housing onto at least a first sample portion of said filter when said particle trap is in said first position, and onto at least a second sample portion of said filter when said particle trap is in said second position.

5,588,536

DREDGE WITH BI-DIRECTIONAL GRIZZLY

Jochen Rohr, 1 Field La., Cincinnati, Ohio 45208

Filed Mar. 13, 1995, Ser. No. 404,176

Int. Cl.⁶ B07B 1/52; B65G 45/00

U.S. Cl. 209-385


19 Claims

1. A system for separating recoverable material from waste material, said system comprising:

a stationary sieve for straining a portion of material deposited thereon;

a first and a second rake, said first and second rakes being movable and initially positioned at first and second spaced ends of said sieve, respectively; and

a driver assembly connected to said first and second rakes to selectively move said first and second rakes across said sieve in first and second directions, said driver assembly selectively moving said first rake in said first direction to slide waste deposited on said sieve off of said sieve for disposal, said



driver assembly also selectively moving said second rake in said second direction to slide recoverable material deposited on said sieve off of said sieve for processing.

5,588,537

MERCHANDISE DISPLAY SYSTEM


Gerald M. Hagopian, Oak Creek, Wis., assignor to KCS Industries, Inc., Milwaukee, Wis.

Filed Sep. 13, 1994, Ser. No. 305,039

Int. Cl.⁶ E05B 73/00

U.S. Cl. 211—4

24 Claims



1. A merchandise display system comprising a framework including a support member and a locking member, the support member being adapted to receive at least one locking tab of an attachment member associated with an article of merchandise for supporting the article of merchandise for display on the support member, the support member including a pivot axis and being movable about the pivot axis, the locking member being adapted to contact the locking tab to prevent removal of the merchandise from the support member when the locking member is in a first position with respect to the locking tab, the locking tab being movable with respect to the locking member to avoid contact between the tab and the locking member to permit removal of the merchandise when the locking member is in a second position with respect to the locking tab.


5,588,538
TIRE STACKING METHOD AND APPARATUS
Christopher Rundle, 12598 SW. 60th Ct., Miami, Fla. 33156,
and Michael Borell, 7787 SW. 86th St., Apt. 310, Miami, Fla.
33143

Filed Sep. 13, 1995, Ser. No. 527,629

Int. Cl.⁶ B65D 85/06

U.S. Cl. 211—23

14 Claims



11. A banding post comprising:
an elongated cylindrical rigid rod having a first end and a second end;
a first member means coupled to said rod and formed from a slidable sleeve having at least two legs hingedly attached to said sleeve with a distal end of said legs foldable outwardly into a perpendicular stance when said sleeve is placed adjacent to said first end of said rod;
a second member means coupled to said rod and formed from a slidable sleeve having at least two legs hingedly attached to said sleeve with a distal end of said legs foldable outwardly into a perpendicular stance when said sleeve is placed adjacent to said second end of said rod;
means for binding said distal ends of said first member means to said second member means for securing a plurality of split tires therebetween.

5,588,539
PLASTIC DISH DRAINER HAVING INTEGRAL CUP AREA


Dennis D. Belden, Jr., Akron; Keith E. Brighthill, Wooster; Stephen P. Casteel, Wadsworth; Charles W. Craft, Apple Creek, and Diana W. Juratovac, Columbus, all of Ohio, assignors to Rubbermaid Incorporated, Wooster, Ohio

Filed Dec. 14, 1994, Ser. No. 355,548

Int. Cl.⁶ A47F 7/00

U.S. Cl. 211—41

16 Claims



1. A dish draining rack comprising:
a rack body for containing assorted dishware, the rack body having a central, upward opening dishware receiving chamber

extending from a top rim to a floor surface and defined along opposite sides by a first side panel and a second side panel, the side panels intersecting the floor surface at a bottom end and extending upward therefrom to a top end; and
at least one of the side panels having an inwardly opening, substantially vertical depression integrally formed to extend therein defined by depression sidewalls sized to receive and support an inverted glass and maintain the glass in an inverted condition within the one side panel, whereby water from the inverted glass is directed to the chamber floor surface.

5,588,540

MODULAR STORAGE UNIT KIT


Joel A. Schmit, 1916 NW. 86th Cir., Vancouver, Wash. 98665

Continuation of Ser. No. 243,846, May 16, 1994, Pat. No. 5,495,954. This application Mar. 5, 1996, Ser. No. 610,996

Int. Cl.⁶ A47F 5/00

U.S. Cl. 211—90

5 Claims



1. An easily assembled storage unit kit securable to a vertical support wall and supported on a non level floor surface, comprising:
a support rail having predetermined mounting positions and adapted for attachment to the vertical support wall in a level orientation;
a framework having mounting positions mated to the predetermined mounting positions of the support rail for mounting the framework to said support rail at said mated mounting positions and independent of said floor surface and achieving thereby level orientation of the framework; and
an adjustable bottom support on said framework, said support adjustable as between the level framework and the non level floor surface and thereby adding to the wall support cooperative support for the framework by said non level floor surface.

5,588,541

HEAVY-DUTY DECORATIVE SHELVE

Charles R. Goetz, Carnegie, Pa., assignor to Alco Industries, Inc., Valley Forge, Pa.


Filed Oct. 5, 1994, Ser. No. 318,074

Int. Cl.⁶ A47B 47/00

U.S. Cl. 211—188

14 Claims

1. A modular shelf system comprising:
at least one set of horizontal shelf members vertically spaced from each other, each said horizontal shelf member including a plurality of aligned upper and lower leg cavities and a leg supporting lip between said upper leg cavity and said lower leg cavity; and
a plurality of leg members coupled to each said shelf member for spacing said shelf members from each other, wherein each said leg member is received in one said lower leg cavity and includes a supporting shoulder configured to abut against said leg supporting lip to support one of said shelf members which is positioned on top of said shoulder and a leg engaging



portion extending into said upper leg cavity configured for interlocking said leg member with another said leg member positioned above said supported shelf member by being slidably received within said another leg member.

5,588,542

FISHING ROD RACK

Louis J. Winkler, Jr., Rt. 1, Box 110, Hiwassee, Va. 24347, and Louis J. Winkler, Sr., 9 Hopkins St., Glen Burnie, Md. 21061

Filed Apr. 10, 1995, Ser. No. 419,458

Int. Cl.⁶ A47F 5/00

U.S. Cl. 211—70.8

11 Claims



1. A fishing rod rack comprising:
a lower engaging means which can be mounted to a vertical support surface for receiving and supporting a lower end of a fishing rod;
an upper mounting means securable to a wall surface for receiving and supporting an upper end of the fishing rod, wherein the upper engaging means comprises an upper mounting plate; a fixed upper support plate mounted to the upper mounting plate and including an upper surface spaced from a lower surface and a longitudinal outer edge, the fixed upper support plate being shaped so as to define a plurality of semi-cylindrical bores directed into the outer edge and extending from the upper surface thereof to the lower surface; a pivoting upper support plate pivotally mounted to an end of the fixed upper support plate, the pivoting upper support plate including an upper surface spaced from a lower surface and a longitudinal inner edge, the pivoting upper support plate

being shaped so as to define a plurality of semi-cylindrical bores directed into the inner edge and extending from the upper surface thereof to the lower surface, wherein the semi-cylindrical bores of the support plates cooperate to define a plurality of upper receiving apertures through which an upper portion of the fishing rod can project; wherein the upper engaging means further comprises a latch secured to ends of the support plates; wherein the upper mounting plate of the upper engaging means includes upper lateral portions extending therefrom, the upper lateral portions being shaped so as to define mounting apertures directed therethrough; wherein the lower engaging means comprises a lower mounting plate; a lower support plate extending from the lower mounting plate, the lower support plate being shaped so as to define a plurality of spaced lower receiving apertures which receive a lower portion of a fishing rod; and wherein the lower mounting plate includes opposed upper and lower surfaces, the lower receiving apertures being directed through the lower support plate from the upper surface to the lower surface thereof.

5,588,543

ADJUSTABLE SHELVING SYSTEM


Gary E. Finger, Voorhees, N.J., assignor to Aircraft Wire Works, Inc., Pennsauken, N.J.

Filed Apr. 25, 1994, Ser. No. 232,670

Int. Cl.⁶ A47F 5/00

U.S. Cl. 211—90

13 Claims



1. An adjustable shelving system comprising:
a frame having a plurality of spaced apart vertical bars and a plurality of spaced apart horizontal bars extending across said vertical bars;
a shelf having a front and a back;
an upper connecting means connected to and extending rearwardly from said back of said shelf, said upper connecting means being engagable with one of said horizontal bars located behind said back of said shelf;
a lower connecting means extending downwardly from said upper connecting means, said lower connecting means extending rearwardly beneath and being engagable with one of said horizontal bars located below the horizontal bar to which said upper connecting means is engaged, and
said lower connecting means being comprised of a pair of members that extend downwardly and rearwardly from said upper connecting means, each of said downwardly and rearwardly extending members including a lower end, said lower connecting means further including a horizontal support member extending between said lower ends of said downwardly and rearwardly extending members, said horizontal support member being situated behind said one of said horizontal bars.

5,588,544
BOTTLE NECK STRUCTURE AND A MANUFACTURING METHOD THEREFOR

Tadayoshi Takashima, Kobe; Takahiro Chiba, Kawagoe, and Takashi Tanaka, Kobe, all of Japan, assignors to Yamamura Glass Co., Ltd., Hyogo-ken, Japan

Continuation of Ser. No. 560,600, Jul. 13, 1990, abandoned.


This application Aug. 3, 1992, Ser. No. 925,584

Claims priority, application Japan, Jul. 31, 1989, 1-199989; Dec. 31, 1989, 1-344814

Int. Cl.⁶ B65D 1/02

U.S. Cl. 215—42

27 Claims



1. A bottle neck structure of a synthetic resin bottle comprising:
a resin core member;
said resin core member having a cylindrical body;
said cylindrical body having through-holes therein;
a bottle resin layer covering substantially all of an inside surface of said resin core member;
said bottle resin layer passing through said through-holes and covering a portion of an outside surface of said resin core member; and
said portion of an outside surface having an outside shape adapted for affixing a cap thereto;
said cylindrical body having a circumferential wall;
a flange constituting a support ring of the bottle neck structure comprising at least one exposed surface portion of said outside surface to be in contact with a preform mold when a bottle preform is molded; and
said through-holes being formed in said circumferential wall of said cylindrical body.

5,588,545

CHILD-RESISTANT AND ELDERLY FRIENDLY
CLOSURE FOR CONTAINERS

Roger M. King, Latimer, United Kingdom, assignor to Beeson and Sons Limited, Herts, United Kingdom

Continuation of Ser. No. 121,970, Sep. 15, 1993, abandoned,

which is a continuation of Ser. No. 796,946, Nov. 22, 1991,

abandoned. This application Jan. 30, 1995, Ser. No. 380,201

Claims priority, application United Kingdom, Sep. 23, 1991,


9120264; Oct. 17, 1991, 9122097

Int. Cl.⁶ B65D 55/02

U.S. Cl. 215—216

11 Claims

1. A child resistant container closure assembly comprising:
a container neck and a container closure;
said container neck carrying a first screw thread and said container neck further carrying a first locking element;
said container closure comprising:
an inner part and an outer part;



said inner part carrying a second screw thread for screw threaded engagement with said first screw thread of said container neck;

co-operating retaining projections on the inner and outer parts for retaining the inner part within the outer part, and for permitting limited axial movement of the inner part within the outer part;

a first set of castellations on the inner part;

a second set of castellations on the outer part arranged to inter-engage the first set of castellations on the inner part when the outer part is moved axially towards the inner part to permit full torque to be applied to the inner part;

a set of resilient blades extending from a first of the inner and outer parts, said resilient blades bearing against said second of said inner and outer parts to urge said outer part axially in a direction away from said inner part such that said first and second sets of castellations are normally held out of inter-engagement;

each of said resilient blades having a remote end and comprising an abutment surface at said remote end;

said second of said inner and outer parts comprising a set of adjacent ratchet projections, each of said ratchet projections comprising a stop surface and a ramp surface, said stop surface being substantially radial and being constructed and arranged to engage the abutment surface of one of said resilient blades when the outer part is rotated in a first direction to apply the closure to said neck, thereby to permit full torque to be applied to said inner part in said first direction of rotation;

each said ramp surface being constructed and arranged to cam one of the resilient blades over said ratchet projections when the outer closure part is rotated in a second direction opposite to said first direction so that said blades can slip relative to the ratchet projections if said outer part is rotated in said second direction without the first and second sets of castellations being in inter-engagement, said resilient blades transmitting only a limited torque to said ratchet projections owing to frictional engagement of said resilient blades slipping over said ramp surfaces of said ratchet projections;

further comprising a second locking element on said inner part for engaging said first locking element of said container neck when said container closure is screwed into a closed position on said neck to hold said container closure in said closed position;

said first and second locking elements are disengaged from one another at said closed position by (1) moving said outer part axially towards the inner part so that said first and second sets of castellations inter-engage one another and (2) then screwing said closure in said second direction, wherein said first and second locking elements are constructed and arranged to resist loosening of said container closure from the closed position until a predetermined release torque is applied to said inner part in said second direction, which predetermined release torque is greater than said limited frictional torque of said resilient blades and said ratchet projections when said

outer part is rotated in said second direction without said first and second sets of castellations being inter-engaged.

5,588,546

CLOSURE WITH STAY-OPEN LID


Nicholas Farside, Lancaster, Pa., assignor to Kerr Group, Inc., Lancaster, Pa.

Filed May 26, 1994, Ser. No. 249,769

Int. Cl.⁶ B65D 43/14

U.S. Cl. 215—237

26 Claims



26. A closure with a stay-open lid, comprising:

(a) a base including:

(i) a base wall having an opening thereon and an outer periphery;
(ii) a first skirt depending from the periphery of the base wall, having an outer edge formed at the juncture of the base wall outer periphery and the skirt;
(iii) an outlet coupled to the base wall and in fluid communication with the opening in the base wall;

(b) a lid connected to said base by a hinge, the closure having a void formed at the juncture of said outer edge and said hinge and at least partially within said hinge, said lid including:

(iv) a lid wall;
(v) a second skirt depending from the periphery of the lid wall;
(vi) a plug depending from the lid wall, the plug being received in the outlet when the lid is in a closed position;
(vii) a nib extending from an edge of the second skirt, the nib being received in the void when the lid is in a closed position on the base, and the nib frictionally engaging the sides of the void when the lid is in the open position, such that the lid is at least partially prevented from closing by the frictional engagement of the nib with the sides of the void.

5,588,547

COVERING DEVELOPED FOR INFUSION BOTTLE

Klaus Derksen, Karlsbad-Ittersbach, Netherlands, assignor to Carl Freudenberg, Weinheim, Germany


Filed Nov. 10, 1994, Ser. No. 337,675

Claims priority, application Germany, Dec. 9, 1993, 43 44 134.3

Int. Cl.⁶ B65D 41/58

U.S. Cl. 215—247

8 Claims



1. A covering for closing an infusion bottle, the covering comprising:

a first cap flanged at its lower edge for gripping a neck of the bottle, the first cap having a hole in its top for the information of a puncture region;
a supplementary cap comprising a pierceable foil and being enclosed by the first cap, the foil including a foil section; wherein the hole is closed by the foil section of the supplementary cap;
the foil of the supplementary cap extends to the lower edge of the first cap and within the lower edge of the first cap to be flanged with a flange of the first cap;
the foil section of the supplementary cap has a thickness enabling a puncturing of the foil section, the foil being secured to the first cap by an adherence attachment; and
the adherence attachment comprises a formation of edge burrs having an intermeshing of the foil of the supplementary cap with the flange of the first cap.

5,588,548

ADJUSTABLE BABY BOTTLENECK


Jacob R. Brankley, 10509 Qualla Rd., Chesterfield, Va. 23832

Filed Jun. 2, 1995, Ser. No. 460,594

Int. Cl.⁶ A61J 9/00, B65D 25/48

U.S. Cl. 215—388

20 Claims



1. A baby bottle neck adaptor for use with a conventional baby bottle and a conventional nipple comprising:
 - (a) a plastic body having a first end with an opening therein and a second end with an opening therein, said opening in said first end communicating with said opening in said second end, said second end having means for mounting a securing ring, said plastic body having means for providing and maintaining a non coaxial alignment of said opening in said first end with said opening in said second end;
 - (b) external threads at said first end for engaging threads of a securing ring of a conventional baby bottle nipple;
 - (c) a mounted securing ring mounted at said second end having internal threads for engaging threads of a conventional baby bottle and
 - (d) a liner having an opening first end and an open second end terminating in means for mating with said mounted securing ring.

5,588,549

CONTAINER WITH SWIVELLING SIDEWALLS

Josef Furtner, Enns, Austria, assignor to Steiner Freizeitmöbel Gesellschaft m.b.H. & Co. K.G., Pinsdorf/Aurachkirchen, Austria

PCT No. PCT/AT93/00166, § 371 Date Jun. 1, 1995, § 102(e)

Date Jun. 1, 1995, PCT Pub. No. WO94/11259, PCT Pub.

Date May 26, 1994


PCT Filed Oct. 29, 1993, Ser. No. 436,358

Claims priority, application Austria, Nov. 18, 1992, 2284/92

Int. Cl.⁶ B65D 6/18

U.S. Cl. 220—7

24 Claims



1. A container comprising
 - (a) a base having
 - (1) a surface,
 - (2) an underside and
 - (3) longitudinally and transversely extending circumferential side faces between the surface and the underside,
 - (b) a first pair of side walls facing each other and a second pair of side walls facing each other, each side wall having
 - (1) a surface facing the surface of the base and
 - (2) end faces circumferentially delimiting the surface of the side wall,
 - (c) an articulation device pivotally connecting at least one side wall of each pair to the base whereby the pivotally connected side wall may be outwardly pivoted about a pivoting axis from a first position wherein the side wall extends perpendicularly to the base to a second position wherein the side wall is coplanar with the base,
 - (1) the surfaces of the base and of the side walls defining an interior chamber of the container in the first position, and
 - (2) opposite ones of the end faces of the side walls of the second pair defining overlapping regions with the surfaces of the side walls of the first pair,
 - (d) a connecting device arranged in each overlapping region, the connecting device comprising
 - (1) a coupling comprised of an extending part defining a slot-shaped recess and an opening arranged to be engaged by the extending part, and
 - (2) a centering device comprised of an extending part and a receiving portion, the extending part of the centering device being arranged to be received in the receiving portion,
 - (3) the extending parts of the coupling and centering device projecting from a respective one of the opposite end faces of the side walls of the second pair,
 - (4) the openings and the receiving portions being arranged in a respective one of the surfaces of the side walls of the first pair in the transition regions, and
 - (5) an elastically deformable detent arm arranged to project into and engage a contact face of the slot-shaped recess facing the end face of the side walls of the second pair in the first position, each detent arm having an end face facing a bearing face of the opening and enclosing an acute angle with the surface of the side wall of the first pair to extend in a direction facing away from the interior chamber, the elastically deformable detent arm exerting a spring force upon the contact face.

5,588,550

COMPARTMENTED CONTAINER INCLUDING CLOSURE WITH ACCESS TO INDIVIDUAL COMPARTMENTS


Robert C. Meyer, Wilton, Conn., assignor to Pepsico, Inc., Purchase, N.Y.

Filed Oct. 10, 1995, Ser. No. 541,313

Int. Cl.⁶ B65D 1/04; 51/18

U.S. Cl. 220—525

15 Claims



1. A container, comprising:
 - a body portion including a bottom wall and a side wall defining a cavity;
 - a shoulder portion extending from said body portion and further defining said cavity;
 - a plurality of compartments for holding separate contents, said compartments separated by a partitioning member positioned in said cavity, said compartments and partitioning member extending through said cavity;
 - a neck portion extending from said shoulder portion having inner and outer wall surfaces, said neck portion defining an opening to said container, said neck inner surface including means for retaining a fitment, wherein said partitioning member terminates below said neck opening and said retaining means; and
 - a fitment positioned within said neck portion and engaged with said inner wall surface, said fitment being in sealed relationship with said neck portion at said retaining means and freely rotatable relative to said neck portion, said portion including a cover substantially traversing said inner wall and having an opening therein;
- wherein said cover is substantially pressure tight and said cover opening is rotatable with said portion into and out of alignment with each of said plurality of compartments for providing access to each of said plurality of compartments for removal of said content therefrom without substantial loss of pressure in each of said plurality of compartments not accessed; and
- an access wall extending over said compartments and partitioning member and sealably attached to said partitioning member, said access wall including a number of holes therein leading to said compartments with each hole corresponding to one of said compartments, wherein said opening aligns with said holes via rotation of said portion for acquiring access to said compartments.

5,588,551

EATING AID


Megan J. Morrow, and Dennis Morrow, both of P.O. Box 123, Wilmington, Vt. 05363

Filed May 15, 1996, Ser. No. 647,654

Int. Cl.⁶ A47G 19/02

U.S. Cl. 220—574.1

8 Claims



1. An eating aid comprising: a one-piece, integral, elastically deformable member having a top wall and a continuous side wall with a bottom edge surrounding a depression, wherein the member cooperates with a substantially smooth and planar surface to form a closed chamber when the bottom edge is disposed thereon and adheres to the surface by suction in response to a downward deformation of the top wall and wherein the side wall extends upwardly from the surface when the member is adhered thereto to form an abutment surface with an overhanging lip configured to force food pushed against the abutment surface by an eating utensil onto the utensil when a user is eating food off of the planar surface.

5,588,552

DISPOSABLE ROLLED RIM CUP AND LID CLOSURE


Timothy C. Johnson, 287-3 Dorchester St., Boston, Mass. 02127

Filed Jun. 5, 1995, Ser. No. 463,056

Int. Cl.⁶ A47G 19/22

U.S. Cl. 220—712

9 Claims



7. A closure and a container, the container having (i) a circular sidewall with a bottom and an open end with a rim defining a volume for containing a liquid, the closure comprising: a circular substrate having: (a) a diameter to fit within the circular sidewall of the container and to seal the container and (b) a plurality of peripheral talon tabs extending beyond the diameter of the substrate, each talon tab having an opening adapted and located so that, when the closure is placed to seal the container, the talon tabs seal the container.

firmly engages the rim of the container by means of the opening to prevent the closure from being pushed into the container.

5,588,553 ISSUING DEVICE FOR DISC-SHAPED PARKING TICKETS

Hans Farmont, Ratingen, Germany, assignor to Farmont Technik GmbH & Co. KG, Germany


Filed Apr. 21, 1995, Ser. No. 426,173

Claims priority, application Germany, Apr. 23, 1994, 44 14 303.6

Int. Cl. G07F 11/00

U.S. Cl. 221-76

17 Claims



1. An issuing device for disc-shaped parking tickets having a supply container for parking tickets having at least one target station for the removal of parking tickets, having a transporter which runs between the supply container and the target station and is in the form of a drivable turntable which exhibits receptacles which are distributed over the circumference of the turntable and are intended for temporarily receiving in each case at least one parking ticket which is to be issued from the supply container and for guidance during the transporting movement of the turntable, and having at least one measuring device for identification of the parking ticket which is to be issued in each case, wherein the turntable is arranged displaceably, as a stripper for parking tickets beneath an outlet duct which receives a parking ticket stack, is open on the base side and belongs to the supply container the parking-ticket stack, guided laterally by way of the outlet shaft being supported on the turntable by means of the respectively lowermost parking ticket, and the supporting level, in the region of the receptacles of the turntable, being sunken by the height of a parking ticket for the purpose of lateral release of at least the lowermost parking ticket.

5,588,554 FEEDING FASTENERS TO A WORKPIECE

Darrell D. Jones, Lynnwood, Wash., assignor to The Boeing Company, Seattle, Wash.

Division of Ser. No. 949,177, Aug. 21, 1992, abandoned. This application Jun. 6, 1995, Ser. No. 468,684


Int. Cl. G07F 11/00

U.S. Cl. 221-88

11 Claims

1. A fastener feed system for selecting a fastener needed for a particular fastening location from a fastener storage area and delivering the fastener to a workpiece where the fastener is to be installed, comprising:

a tray comprising a block of material into which cell holes have been drilled having a floor and a grid partition arrangement



defining a multiplicity of vertically elongated, upwardly opening cells for holding single fasteners in a vertical orientation said grid partition arrangement comprising the material of said block between said cell holes;

a delivery tube for conveying said fasteners, selected and extracted from said tray, to a device for inserting said fasteners into the workpiece;

a suction head attached to said proximal end of said delivery tube for contacting a top edge of said grid partition arrangement and applying suction to a selected cell to suck the fastener in said cell through said suction head and into said delivery tube;

an air hole in the bottom of each of said cell holes and communicating with the bottom surface of said tray; whereby air can flow from below said tray up through said air hole and through said selected cell when said suction head sucks said fastener out of said selected cell;

a motive device for positioning said suction head over said selected cell; and

a control system for controlling said motive device.

5,588,555

SYNTHETIC APPARATUS FOR INSPECTION OF BLOOD
Shigeo Kanamori, Mikishi; Kensaku Aota, Hyogoken; Takashi Demachi, Tarumiku; Takahiro Inoue, Himejishi, and Kiyoyuki Tanaka, Onoshi, all of Japan, assignors to TOA Medical Electronics Co., Ltd., Kobe, Japan

Division of Ser. No. 975,407, Nov. 12, 1992, Pat. No.

5,356,595, which is a division of Ser. No. 865,344, Apr. 8,

1992, Pat. No. 5,270,012, which is a division of Ser. No.

577,689, Sep. 4, 1990, Pat. No. 5,209,903. This application

Sep. 8, 1994, Ser. No. 302,543

Claims priority, application Japan, Sep. 6, 1989, 1-230675; Oct. 6, 1989, 1-118146; Jun. 13, 1990, 2-62283; Jun. 13, 1990, 2-62284; Jun. 13, 1990, 2-62285; Jun. 13, 1990, 2-62286; Jun. 13, 1990, 2-62287

Int. Cl. B65H 1/00

U.S. Cl. 221-197

8 Claims

1. A slide supply device comprising:

a base;

means for accepting at least one cassette on said base;

said at least one cassette containing a plurality of slides;

said at least one cassette being removably aligned on said base by said means for accepting;


a slide outlet port in said at least one cassette;

said slide outlet port positioned to allow an individual slide of said plurality of slides to pass through transversely from said cassette;

dispensing means to sequentially dispense said plurality of slides; closing means being vertically movable on said cassette with a first open position and a second closed position;

said first open position effective to enable said dispensing means;

said second closed position effective to prevent said plurality of slides from passing through said outlet port; and



cooperating means, between said cassette and said means for accepting, for moving said closing means to a position permitting said slides to pass through said outlet port.

5,588,556

METHOD FOR GENERATING GAS TO DELIVER LIQUID FROM A CONTAINER

Gregory E. Sencoff, Rancho Santa Fe; Mark C. Doyle, San Diego, and Frederic P. Field, Solana Beach, all of Calif., assignors to River Medical, Inc., San Diego, Calif.

Division of Ser. No. 205,875, Mar. 3, 1994, Pat. No. 5,398,850,

and a continuation-in-part of Ser. No. 105,327, Aug. 6, 1993,


Pat. No. 5,398,851, and Ser. No. 105,284, Aug. 6, 1993, Pat.

No. 5,397,303. This application Jun. 5, 1995, Ser. No. 461,871

Int. Cl. B65D 83/14

U.S. Cl. 222-1

7 Claims



1. In an apparatus for the delivery of a liquid from a container, of the type wherein the apparatus includes a first and a second chemical, the first and second chemical being reactive to generate carbon dioxide gas, with the first chemical being disposed in solid form and the second chemical being disposed as a liquid, the improvement comprising:

the first chemical being admixed with a rate limiting amount of a rate controlling moiety and formed into a solid mass.

5,588,557

BEVERAGE DISPENSER

William M. Topar, 4664 W. Puget, Glendale, Ariz. 85302


Filed May 19, 1995, Ser. No. 446,565

Int. Cl. B67D 5/08

U.S. Cl. 222-54

10 Claims

1. A beverage dispenser for control of the delivery and mix of a liquid from its source with an ingredient, the dispenser comprising: means for mixing the liquid and the ingredient, the mixer means being in electrical isolation from the source; means for delivering the liquid from the source to the mixer means, the liquid providing a conductive path and thereby providing electrical continuity between the source and the mixer means during delivery;



a sensor for detecting the electrical continuity between the source and the mixer means, the sensor being in electrical communication with a control board;

means for delivering the ingredient to the mixer means, the ingredient delivery means being in electrical communication with the control board, the control board activating the ingredient delivery means when the sensor detects the electrical continuity.

5,588,558

LIQUID BEVERAGE DISPENSER


Vance Cox, and Barbara Cox, both of Trenton, Mo., assignors to Van-Bar Enterprises, Inc., Trenton, Mo.

Filed Mar. 17, 1995, Ser. No. 405,847

Int. Cl. B67D 5/08

U.S. Cl. 222-64

8 Claims



1. A liquid dispenser comprising:

a transparent liquid dispensing chamber positioned atop a cabinet for holding and dispensing a liquid therefrom while permitting customers to view the liquid contained therein;

means for dispensing the liquid from said dispensing chamber;

an auger positioned within said dispensing chamber for stirring the liquid contained in said liquid dispensing chamber;

a switch for activating said auger;

a liquid storage chamber for storing additional amounts of the liquid therein;

means for transferring the liquid from said storage chamber to said dispensing chamber; and

a liquid level sensor including measuring means for measuring the liquid level in said dispensing chamber and activating means for activating said transferring means to transfer liquid from said storage chamber to said dispensing chamber when the liquid level drops below a predetermined level, said liquid level sensor including an optical sensor.

5,588,559

USE OF POLYMERIC MEMBRANES IN THE DISPENSING OF PHARMACEUTICAL SOLUTIONS THAT CONTAIN QUATERNARY AMMONIUM COMPOUNDS AS PRESERVATIVES AND CORRESPONDING DOSE DISPENSER

Alberto Vallet Mas, Barcelona, and Francesc X. Gimenez Guasch, Premia de Mar, both of Spain, assignors to Laboratorios Cusi, S.A., El Masnou, Spain

Filed Jun. 24, 1994, Ser. No. 265,409

Claims priority, application Spain, Jun. 25, 1993, 9301443; Jun. 9, 1994, 9401260

Int. Cl.⁶ B65D 1/08

U.S. Cl. 222—92

12 Claims



2. A dose dispenser for pharmaceutical solutions, comprising:
- a) an easily deformable container;
 - b) a dropper having a bottom part and a top part said bottom part being received in the container, the top part having a first cylinder unit and the bottom part having a second cylinder unit aligned with the first cylinder unit, said first and second cylinder units containing duct forming projections;
 - c) at least one polymeric membrane located within the first cylinder unit and the second cylinder unit and between the top part and the bottom part, and
 - d) a cap constructed to be received on the container over the dropper and including means for securing the cap to the container.

5,588,560

ERGONOMIC DISPENSER FOR VISCOUS MATERIALS


Dale G. Benedict, Marysville; Frank R. Wilgus, Powell, both of Ohio; Henry J. Fuls, and William T. Gagliardi, both of Midland, Mich., assignors to Dow Corning Corporation, Midland, Mich.

Filed Jan. 11, 1996, Ser. No. 584,855

Int. Cl.⁶ B65D 35/18

U.S. Cl. 222—106

19 Claims



1. A device for dispensing a viscous material comprising an elongated collapsible tube for containing viscous material, the tube

being closed at one end and open at its other end for discharging the contents of the tube; an applicator nozzle formed generally in the shape of an elongated, hollow, tubular-like member, the applicator nozzle having an inlet end with an opening, the inlet end of the applicator nozzle being secured to the open end of the tube, the applicator nozzle having an outlet end with an opening adapted to extrude a bead from contents squeezed out of the tube, the applicator nozzle including an arched throat portion extending upwardly from the inlet end of the applicator nozzle to the outlet end of the applicator nozzle, the arched throat portion being so constructed and arranged so as to provide a gradual transition and change in the cross-sectional shape of the applicator nozzle inlet opening from the inlet end of the applicator nozzle to the outlet end of the applicator nozzle; and a slot formed integrally in the outlet end of the applicator nozzle, the slot providing an applicator blade which extends beyond the outlet end of the applicator nozzle over the opening for extruding the bead; whereby as the tube is squeezed and the bead is extruded on a surface, the applicator blade smoothes the bead as it is being laid along the surface.

5,588,561

PORTABLE FOOD CONTAINER AND METHOD FOR STORING AND CONSUMING DRY AND LIQUID FOOD


Richard B. Ness, 7710 128th St. West, Apple Valley, Minn. 55124

Filed Mar. 10, 1995, Ser. No. 401,813

Int. Cl.⁶ B67D 5/56

U.S. Cl. 222—129

5 Claims



1. A portable food container comprising:
- a) a divided compartment cup having a rigid compartment for holding dry food and a flexible compartment for holding liquid food, wherein said flexible compartment is relatively more flexible than said rigid compartment; and
 - b) a container lid for covering the compartments of said divided compartment cup, said container lid having a first opening for delivering dry food from said rigid compartment and a second opening for delivering liquid food from said flexible compartment.

5,588,562

TAMPER EVIDENT RESEALABLE PLASTIC CLOSURE

Dieter Sander, Mississauga, and Uwe F. Meyer, Islington, both of Canada


Filed Oct. 31, 1994, Ser. No. 332,140

Int. Cl.⁶ B67D 5/33

U.S. Cl. 222—153.06

12 Claims

1. An improvement in a resilient molded plastic resealable closure for a bottle having a neck surrounding an opening, said neck having a spiral thread extending outwardly of said neck; the improvement comprising in combination: a cap having a top portion, an annular depending flange on said top portion; a segmented spiral thread in said annular depending portion, a plurality of



circumferentially spaced outwardly extending frangible elements on said depending flange, a thin flexible annular band on the outer ends of said frangible elements is spaced in relation thereto, said flexible annular band having a plurality of annularly circumferentially spaced elevated bridge portions thereon extending axially towards said depending flange, the elevated bridge portions defining areas of decreased ring spacing from said depending flange therebetween, said frangible elements extending from said elevated bridge portions and from said flexible annular band interconnecting with a bottom edge of said depending flange, a plurality of circumferentially spaced radially inwardly extending arcuate projections on said flexible annular band registerable with an annular locking flange on said bottle's neck on which the closure is positioned, an internal pour spout on said top portion communicating with an opening in said top, said pour spout having an apertured secondary top thereon, and means for positioning a plug in spaced relation to said secondary top portion and said aperture, a top cap movably positioned on said pouring spout and having an opening registerable with said plug defining a closure when said top cap is in a first position, a band having a plurality of frangible elements integrally connected with said band with said top cap in said first position, a plurality of upstanding stops on said band between said frangible elements, a flange on said pour spout retaining said band in said first position when said top cap is moved away from said first position to a second position locating said opening is said top cap in spaced relation to said plug, said flange on said pour spout having a tapered top portion, means for spacing said top cap in relation to said pour spout and means for retaining said top cap on said pour spout in said second position.

5,588,563

QUANTITATIVE DISPENSER

Chin-Ching Liu, No. 25, Lane 16, Tunghsing St., Shu-Lin Town, Taipei Hsien, Taiwan

Continuation-in-part of Ser. No. 328,193, Oct. 21, 1994, abandoned. This application Oct. 6, 1995, Ser. No. 540,265

Int. Cl.⁶ G01F 11/46

U.S. Cl. 222—158

2 Claims



1. A quantitative dispenser comprising:

a cylindrical body with a lower part that converges to a bottom, an inner portion of a top end of said body comprises a stepwise annular slot, said slot includes a peripheral flange protruding from said slot, said annular slot angles downward and inward so as to converge toward an inside center of said body;

a separator plate engaged in said inner annular slot at the top of said cylindrical body, having an engaging hole at its center and a flow-through opening near its periphery; its edge angles downward and inward so as to converge toward said inside center of said body;

a volumetric cover with a bottom of said cover engaging said flange at said top end of said body, said cover comprises an outlet projecting vertically from a curved upper outer surface of said cover, a sealing cap on said outlet, a hollow engaging shaft extending from an inner center of said cover toward said central engaging hole, and an annular slot at a lower end of said hollow shaft, wherein said annular slot engages said engaging hole at the center of said separator plate and thereby engages said cover with said separator plate; an outer surface of said cover further comprises a scale and a numerical display;

a cut-out sector converging inwardly at a side of said cover, said cut-out sector comprising sealed sidewalls at each of two sides and a bottom plate in an integral construction with said cover, wherein said bottom plate seals said flow-through opening on said separator plate, and wherein said outlet is provided near one of said sides of said cut-out sector; and said sealing cap is connected with an annular plug via a connecting belt, wherein said annular plug is engaged an outer upper end of said engaging shaft;

a scale divider, comprising a sleeve part and a wing part integral to each other, wherein said sleeve part slips on the outside of said hollow engaging shaft of said cover, and an upper peripheral profile of said wing part matches an arcuate undercut beneath an arcuate profile of said cover and a bottom edge of said wing part contacts the surface of said separator plate; wherein, said upper profile of said wing part can be fixed on an inside periphery of said cover, thereby, in combination with said sidewall of said cut-out sector forming a measuring space.

5,588,564

EYE SPRAY MIST DISPENSER


Clifford L. Hutson, 4440 J Shadow Hills Cir., Santa Barbara, Calif. 93105, and Robert Demangus, 1715 N. Pacific Ave., Glendale, Calif. 91202-1108

Filed Aug. 21, 1995, Ser. No. 518,143

Int. Cl.⁶ B67D 5/40


U.S. Cl. 222—383.1

5 Claims



1. A device operable for controlling the delivery of a fluid mist discharged from the ejection nozzle of a spray mist dispenser to a person's eye comprising:

- (a) a hollow hemi-ellipsoidal eye cup having a substantially elliptical proximal open end dimensioned to encircle a person's eye and having a skin-contacting rim on said open end contoured to anatomically conform to infra-orbital tissue adjacent to the person's eye and a distal circular open end;
- (b) an axially adjustable tube portion comprising a cylindrical outer tube concentrically overlying a cylindrical inner tube, and having an axial mist-conducting lumen coextensive therewith, said outer tube having a proximal end attached to said eye cup to provide fluid communication between said mist-conducting lumen and said distal circular open end of said eye cup and a distal end, said inner tube being slideably disposed within said outer tube and having a proximal end and a distal end, said distal end of said inner tube including attachment means adapted to releasably attach to the nozzle of the spray mist dispenser, said mist-conducting lumen providing a conduit having an adjustable axial length operable for conducting a fluid mist from said distal end of said inner tube to said proximal end of said outer tube.




5,588,565
VALVE FOR DISPENSING PRESSURIZED FLUID THROUGH A FLEXIBLE TUBE

Sidney H. Miller, 850 E. Louther St., Carlisle, Pa. 17013
Filed Feb. 14, 1994, Ser. No. 195,645
Int. Cl.⁶ B65D 83/00

U.S. Cl. 222—394

7 Claims



1. A dispensing valve comprising a flexible dispensing tube, the dispensing tube having one end inside of a container and a discharge end outside of the container; a disk attached to the dispensing tube for positioning the tube within the container, said disk being held between a cap and a container top lip; a seal being formed between the disk and the dispensing tube when the dispensing tube expands radially from pressure from a pressurized fluid contained within the container; the dispensing valve further comprising a lever attached to said cap, the lever and the cap having cooperating pinching means for regulating the flow of the pressurized fluid out of the container; and a resilient band encircling the lever and the cap proximal to the dispensing end of the dispensing tube for biasing the lever towards the cap in order to permit discharge of the pressurized fluid only when the lever is actuated.

5,588,566
DEVICE FOR ACTUATING A DISPENSING MECHANISM SUCH AS A VALVE FITTED TO A PRESSURIZED AEROSOL CONTAINER

Vincent de Laforcade, Rambouillet, and Franck Lacout, Athis-Mons, both of France, assignors to L'Oréal, Paris, France
Filed Mar. 4, 1996, Ser. No. 610,291
Claims priority, application France, Mar. 3, 1995, 95 02499
Int. Cl.⁶ B65D 83/22

U.S. Cl. 222—402.11

8 Claims

1. An actuating device for a dispensing mechanism fitted to a container, said device comprising:
a fixed annular collar;

an actuating plate with a circular base defining a periphery pivotally mounted in said annular collar and articulated over a limited area of the periphery of said base to said annular collar, said plate having on a lower face an axial tube for engagement with a valve of the container, said tube having an interior passage extended by a passage projecting upward from said plate up to a terminal dispensing nozzle, said plate having on an upper face a force application area essentially diametrically opposite said articulation area on said annular collar;


a radial cutout in said force application area, said radial cutout including a recess defining a bearing surface; and
a tongue engageable with said recess, said tongue being joined at one end to said annular collar and having a free end, said tongue being positionable in both a first locking position wherein its free end engages said recess and abuts said bearing surface to prevent pivotal movement of said plate, and a second dispensing position in which said tongue is retracted inside said plate out of engagement with said bearing surface to allow pivotal movement of said plate around said articulated limited area of the periphery of said base.

5,588,567
HANDLE ARRANGEMENT FOR TEA KETTLES
Kuo-Strai Yeh, No. 15, Lane 33, Wei Kun St., Tainan City, 701, Taiwan

Filed Nov. 24, 1995, Ser. No. 562,397
Int. Cl.⁶ A47G 19/14

U.S. Cl. 222—475.1

2 Claims




1. A tea kettle comprising:
a tea kettle body having a spout;
a handle base removably mounted to the tea kettle body and having a bore for receiving the spout and an engaging block; and
a handle removably mounted to the handle base and including a hollow member formed at a lower end thereof, the hollow member having an engaging slot defined therein for releasably receiving the engaging block of the handle base.

5,588,568
EYELET THREADER
James M. Flavin, and Myra E. Flavin, both of 2966 Foxcroft Dr., Tallahassee, Fla. 32308
Filed Jul. 20, 1995, Ser. No. 504,425
Int. Cl.⁶ D05B 87/02; 87/00

U.S. Cl. 223—99

5 Claims




1. An eyelet threader for threading a needle comprising:
a resiliently deformable closed loop member, having a first end for insertion through an eyelet of a needle and receiving a thread therethrough and a second end;
a post member having a first end for insertion in the eyelet of a needle and for guiding the loop member through the eyelet, wherein said post is disposed in generally parallel adjacent orientation to the loop member with the second end of the loop member attached to a second end of the post.

5,588,569
CARRIER BAG
Masako Mitomi, Yokohama, and Ryo Hoshino, Tokyo, both of Japan, assignors to Nifco, Inc., and Kabushiki Kaisha Cosmo Area, both of Japan
Continuation of Ser. No. 16,223, Feb. 11, 1993, Pat. No. 5,447,223. This application Apr. 11, 1995, Ser. No. 420,158
Claims priority, application Japan, Feb. 12, 1992, 4-5152
Int. Cl.⁶ A45F 4/02

U.S. Cl. 224—153

15 Claims




1. A carrier bag comprising:
a box member including a bottom plate and first and second pairs of adjoining side plates extending from an outer periphery of said bottom plate, said second pair of side plates including opposing upper and lower plates, and said first pair of side plates extending a height above the bottom plate, wherein the height of the first pair of side plates decreases along a longitudinal direction of the box member from said lower plate to said upper plate such that the box member has a generally tapered side profile, whereby the first and second

pairs of side plates provide a peripheral edge which defines an opening that lies in a plane inclined with respect to said bottom plate;
a soft cover attached to the peripheral edge of said side plates, said soft cover covering said opening;
a connecting member provided along said soft cover to allow said soft cover to be partially openable; and
first and second casters each being provided at a respective corner portion of said box member, and when said lower plate is disposed horizontally, said first and second casters support said box member such that said bottom plate is in a substantially vertical state.

5,588,570
COMBINATION BACKPACK AND SEAT DEVICE
Kurt D. Zirbel, 1715 S. Delaware, Mason City, Iowa 50401
Filed Dec. 28, 1994, Ser. No. 365,086
Int. Cl.⁶ A45F 4/02

U.S. Cl. 224—155

20 Claims



1. A combination backpacking and seating device, comprising:
a frame having an upper frame member with forward and rearward sides and opposite top and bottom ends, and a lower frame member extending rearwardly from the upper frame member adapted to support the upper frame member in an upright position on a support surface;
a cushion having a top end and a bottom end, the bottom end of the cushion being attached to the bottom end of the upper frame member and the top end of the cushion being movable between a raised position adjacent the forward side of the upper frame member and a lowered position extending forwardly from the bottom end of the upper frame member, the cushion engaging the support surface when moved to the lowered position and the lower frame member is positioned on the support surface;
a storage pouch attached to the upper frame member and residing on the rearward side thereof; and
shoulder straps attached to the upper frame member; wherein the cushion provides a back pad for a user when in the raised position and wherein the cushion provides a seat pad for the user when moved to the lowered position.

5,588,571
WRIST WALLET AND CARRYING POUCH
Charles Mazzo, 10 Lachlan St., Liverpool, New South Wales, Australia
Continuation-in-part of Ser. No. 305,446, Sep. 13, 1994, abandoned. This application Jan. 2, 1996, Ser. No. 582,089
Claims priority, application Australia, Oct. 29, 1993, 50338/93

U.S. Cl. 224—222

4 Claims

1. A waterproof wallet and pouch combination, adapted to be worn around the wrist of a user;

5,588,572

ARTICLE CARRIER

Gary M. Cronce, Port Huron, and Craig A. Stapleton, Troy,
both of Mich., assignors to Advanced Accessory Systems
L.L.C., Port Huron, Mich.


Continuation of Ser. No. 187,449, Jan. 26, 1994, abandoned.

This application Aug. 31, 1995, Ser. No. 521,843

Int. Cl.⁶ B60R 9/00

U.S. Cl. 224—321

15 Claims



wherein said pouch comprises: a front member; and a back member forming a cavity there between, said back member having an extension portion which extends on one side beyond the respective side of said front member and forming an opening into the cavity, along the respective side of said front member;

a first hook and loop type fastener located on the front of said extension portion of said back member;

a second hook and loop type fastener located on the front of said front member adjacent said opening of the pouch; whereby said hook and loop type fasteners releasably seal to each other, with said extension portion of said back member folded over and sealing said opening, with a portion of said front member between said opening and said second hook and loop type fastener folding back on itself;

a third hook and loop type fastener located on the back of said extension portion of said back member;

a first strap, having a fourth hook and loop type fastener thereon, extending from one side edge of said extension portion of said back member;

a first ring member located on the other side edge of said extension portion of said back member;

a second strap being connected, adjacent its free ends, to said pouch, adjacent the side edges of said pouch, and extending free across the front of the front member of said pouch substantially parallel to said opening;

a fifth hook and loop type fastener located on said second strap;


a third strap having a sixth hook and loop type fastener thereon extending from one side edge of said pouch adjacent said second strap;

a second ring member located on the other side edge of said pouch adjacent said second strap;

whereby, in use, the back member of the pouch is against the wrist of the user, and the first strap passes through the first ring member with the fourth hook and loop type fastener thereon being releasably secured to the third hook and loop type fastener, and the third strap passes through the second ring member, with the sixth hook and loop type fastener thereon being releasably secured to the fifth hook and loop type fastener, thereby securing the pouch to the wrist of the user;

wherein said cavity is adapted to removably hold said wallet therein, when the wallet is in its folded configuration,

and wherein said wallet comprises three substantially equal in length flexible sections, extending along the length of the wallet, said sections being a first end section, a middle section, and a second end section; and said wallet further comprises a first compartment extending along all three sections, and at least a second compartment located on the first end section, whereby the wallet is in its folded configuration when said second end section is folded over the middle section.



1. A crossbar for use with an article carrier, said article carrier having a roof rail including at least one detent, said crossbar comprising:

an elongated member;

a latch carried by the elongated member for releasably positioning the crossbar at the at least one detent, said latch having an external actuator and an engager having a contact;

said engager adapted for selectively positioning said contact at a recessed position disengaged from the rail, wherein said crossbar is freely slidable along the roof rail, and selectively positioning said contact in latched position engaging the roof rail at the at least one detent for securing said crossbar at a fixed position along the roof rail and means for resiliently urging said contact to said latched position, and

a retainer for selectively maintaining said contact in said recessed position;

wherein said external actuator is a lever pivotably secured to said support member;

wherein said lever includes a flange and said retainer is an elastically deformable prong extending from said support member adapted to cooperate with said flange, whereby in said latched position said contact is received in said at least one detent, and in said recessed position said flange engages said prong to hold said contact outside said at least one detent, and

said prong is elastically deformed when said flange travels from said latched position to said recessed position.

5,588,573

LOAD-CARRIER FOR VEHICLES

Gerhard Mann, Ulricehamn, Sweden, assignor to Mont Blanc
Industri AB, Dalsjöfors, Sweden

PCT No. PCT/SE93/00361, § 371 Date Dec. 20, 1994, § 102(e)

Date Dec. 20, 1994, PCT Pub. No. WO94/00315, PCT Pub.
Date Jan. 6, 1994

PCT Filed Apr. 26, 1993, Ser. No. 362,473


Claims priority, application Sweden, Jun. 26, 1992, 9201975

Int. Cl.⁶ B60R 9/00

U.S. Cl. 224—329

20 Claims

1. A load-carrier having a load-carrying tubular rail and adapted to extend across a vehicle roof in a transverse direction of a vehicle, a foot member positionable at each lateral edge of the vehicle roof to support the load-carrying tubular rail, the foot



member adapted to rest on an upper vehicle roof face comprising: a clamping element projecting into an interior of the load-carrying rail from a support on the foot member, the clamping element, which is arranged to be clamped against an inner face of the rail, being connected in a motion-transferring fashion to an actuating member mounted in the foot member, the clamping element comprising a resilient finger having a first and second end, the first end connected to the foot member and the second end of which acts in abutment against the inner face of the load-carrying rail, the resilient finger being directed obliquely outwards in a direction towards said abutting end such that in a tightened position through a lever action said resilient finger tends to displace an upper portion of the foot member inwards, towards a vehicle center.

5,588,574

CYCLE RACK

Erik Schmidt, Herning, Denmark, assignor to Erik Schmidt
Autotilbehør Aps, Herning, Denmark

Continuation of Ser. No. 926,642, Aug. 10, 1992, Pat. No.

5,388,736, which is a continuation of Ser. No. 743,032, Aug. 9,
1991, abandoned. This application Feb. 14, 1995, Ser. No.


388,405

Claims priority, application Denmark, Apr. 30, 1991, 0792/91

Int. Cl.⁶ B60R 9/00

U.S. Cl. 224—520

20 Claims



1. A cycle rack for carrying a longitudinally extending object, the cycle rack comprising:

a pair of branches connected to each other at an acute angle at a lower portion thereof so as to be mutually pivotable with respect to each other; and

gripping and holding means for enabling a gripping and holding of the cycle rack on a towing ball hitch;

wherein each of the pair of branches includes at least one carrying arm being mounted on said branch pivotally about a pivot axis extending through said branch in direction of the other branch in the pair of branches, so that the carrying arm is pivotable to occupy a carrying position,

wherein said carrying arm has an inner most portion which is angle shaped and supports a carrying portion of the carrying

arm, said carrying portion having an inner end portion which in a carrying position of the carrying arm is positioned at said branch at a lower level than said pivot axis, so that said carrying arm is pivotable from the carrying position up above a top of said branch.

5,588,575

NEEDLE FOR USE IN THE RODLESS DISPENSING OF PLASTIC FASTENERS


Paul A. Davignon, Uxbridge, Mass., assignor to Avery Denni-
son Corporation, Pasadena, Calif.

Filed Sep. 13, 1994, Ser. No. 305,486

Int. Cl.⁶ D05B 85/00; 97/10; B25B 31/00

U.S. Cl. 227—67

15 Claims



1. A needle for use in dispensing a fastener of the type having a flexible filament and a cross-bar, the cross-bar being disposed at one end of the flexible filament, said needle comprising an elongated member, said elongated member terminating at its front end in a closed-ended tip adapted to penetrate a desired article of commerce, said elongated member also having a chamber adapted to receive a cross-bar of a fastener, said chamber having an opening spaced rearwardly a distance from said closed-ended tip, said chamber being appropriately sized and shaped so that, when the cross-bar is placed within said chamber through said opening and inserted through an article of commerce using said elongated member, the cross-bar is retained within said chamber during insertion of the cross-bar into the article of commerce but is discharged from said chamber through said opening when a predetermined tensile force is applied to said fastener after insertion of the cross-bar and chamber through the article of commerce.

5,588,576

FEEDER FOR COMPONENTS, IN PARTICULAR COMPONENTS DESIGNED WITH A HEAD

Harold Knetsch, Herborn, Germany, assignor to Emhart Inc.,
Newark, Del.


Filed Apr. 19, 1995, Ser. No. 424,981

Claims priority, application Germany, Apr. 21, 1994,
9406687 U

Int. Cl.⁶ B25B 23/04; B23Q 7/08

U.S. Cl. 227—119

9 Claims



1. A feeder for elongated components comprising a feed tube, said feed tube having an inlet orifice adapted for connection to a feed line and a gripper with at least two gripping arms (1) with a channel therebetween, said arms having a front gripping region (2) and a rear pivot axis region (3), characterized in that

- a) said feed tube has an internal cross section with a lower plane surface and an upper plane surface opposed to said lower plane surface, and said gripper being disposed partially in said feed tube and including an outwardly extending portion;
- b) said gripping arms (1) each have a guide step (6) tapering and extending from said pivot axis region to said gripping region (2) said guide step (6) facing toward said upper plane surface, said guide step (6) serving to guide an elongated component; and
- c) said gripping arms (1) have, in the gripping region (2), a recess (7) corresponding to the external shape of the elongated components to be gripped.

5,588,577

MAGAZINE ASSEMBLY FOR PNEUMATIC STAPLE GUNS


Jacob Chen, Taichung, Taiwan, assignor to Testo Industry Corp., Taipei, Taiwan

Filed Jun. 14, 1995, Ser. No. 490,252

Int. Cl.⁶ B25C 3/00; 7/00; 1/04

U.S. Cl. 227—120

3 Claims



1. A magazine assembly for a pneumatic staple gun, comprising a magazine base, a mounting plate fixedly secured to said magazine base for connecting said base to a gun body of the pneumatic staple gun, a magazine cover covering on said magazine base at one side, and a follow plate connected to said magazine cover by a spring for forcing staples into position for driving, wherein said magazine cover has a rear end connected with an end block and a constraint member, said end block having a head for being grasped by the hand of an operator to pull said magazine cover backwards from said magazine base, said constraint member having a hook and being turned about a pivot on said end block for hooking up said magazine cover in position; said magazine base has a rear end fixedly mounted with a hooked stop plate at one side, said hooked stop plate having a guide slope for guiding the hook of said constraint member into engagement with said hooked stop plate when said magazine cover is covering on said magazine base.

5,588,578

NAIL FLATTENING APPARATUS

James J. Doyle, 1851 Hidden Oaks Dr., Germantown, Tenn. 37138

Filed Sep. 2, 1994, Ser. No. 300,710


Int. Cl.⁶ B27F 7/04; B23P 19/00

U.S. Cl. 227—155

13 Claims

9. An apparatus for compressing nail stubble on top and bottom surfaces of a pallet stringer, comprising:

- (a) a conveyor defining a loading station, whereupon a plurality of said stringers may be individually placed in said apparatus,



and an operating station, whereupon each said stringer is individually compressed, said conveyor having a moving upper surface;

- (b) an anvil disposed adjacent said upper surface of said conveyor in the vicinity of said operating station;
- (c) a hammer disposed adjacent said upper surface of said conveyor in the vicinity of said operating station facing said anvil, said hammer being reciprocally moveable between extended and retracted positions; and

(d) driving means for forcibly driving said hammer to said extended position, said hammer being relatively close to said anvil when in said extended position;

wherein a stringer, placed longitudinally in said loading station with said top and bottom surfaces projecting laterally, is moved by said conveyor into said operating station, whereupon said hammer is moved to said extended position such that said hammer and said anvil forcibly engage said top and bottom surfaces of said stringer, thereby compressing any nail stubble extending therefrom;

said apparatus further comprising:

- (e) at least one lifting member disposed beneath said operating station, selectively moveable between raised and lowered positions, wherein in said raised position said at least one lifting member elevates said stringer above the upper surface of said conveyor while maintaining said stringer in said operating station intermediate said hammer and said anvil.

5,588,579

ANVIL FOR CIRCULAR STAPLER

Robert H. Schnut, Carmel, N.Y.; John C. Robertson, Bloomfield, Conn.; Richard J. Gallagher, Milford, Conn., and David N. Fowler, Trumbull, Conn., assignors to United States Surgical Corporation, Norwalk, Conn.


Continuation of Ser. No. 296,218, Aug. 25, 1994, abandoned.

This application Nov. 15, 1995, Ser. No. 558,341

Int. Cl.⁶ A61B 17/068

U.S. Cl. 227—175.1

24 Claims



21. An anvil assembly for a circular stapling instrument comprising:

- a shaft having proximal and distal end portions;

an anvil pivotally associated with the shaft distal end portion; and

locking means for locking the anvil in a substantially perpendicular orientation relative to the shaft, the locking means at least partially contacting a portion of the shaft.

5,588,580

SURGICAL INSTRUMENT


Michel A. Paul, Naperville, Ill., and Jorge Gutierrez, Cincinnati, Ohio, assignors to Ethicon Endo-Surgery, Inc., Cincinnati, Ohio

Division of Ser. No. 259,322, Jun. 10, 1994, which is a continuation-in-part of Ser. No. 959,184, Oct. 9, 1992, Pat. No. 5,381,943. This application May 23, 1996, Ser. No. 651,465

Int. Cl.⁶ A61B 17/068

U.S. Cl. 227—176.1

4 Claims



1. A system for attaching a longitudinally rotatable cartridge of fasteners to a surgical fastener-applying instrument that includes a frame, said system comprising:

- a holder on said frame fixed relative to said frame against longitudinal rotation, said holder defining an axially open receiving structure having a first engaging member;

a rotatable carrier having a proximal end retained axially in said holder receiving structure to accommodate longitudinal rotation relative to said holder and to accommodate limited axial movement between proximal and distal axial positions relative to said holder, said carrier having a proximally extending second engaging member for engaging said first engaging member to prevent carrier rotation only when said carrier is in said proximal axial position, said carrier having at least one radially projecting lug; and

a housing integral with said cartridge for being received on said carrier, said housing including at least one radially projecting rib adapted to be disposed proximally of said at least one carrier lug whereby axial movement of said housing onto said carrier with said at least one rib angularly offset from said at least one lug urges said carrier to said proximal axial position for preventing rotation thereof while said housing can be rotated relative to said carrier to position at least a portion of said at least one rib proximally of said at least one lug with at least portions of said at least one rib and at least one lug having an axially aligned relationship to prevent axial withdrawal of said housing from said carrier.

5,588,581

SURGICAL INSTRUMENT


Sean P. Conlon, Cincinnati; Saleem U. Oureshi, West Chester; John A. Hibner, Mainville; Livyn O. Okorocho, Cincinnati, and Gregory D. Bishop, Hamilton, all of Ohio, assignors to Ethicon Endo-Surgery, Inc., Cincinnati, Ohio

Division of Ser. No. 259,322, Jun. 10, 1994, which is a continuation-in-part of Ser. No. 959,184, Oct. 9, 1992, Pat. No. 5,381,943. This application May 23, 1996, Ser. No. 652,266

Int. Cl.⁶ A61B 17/068

U.S. Cl. 227—176.1

3 Claims



1. In a surgical instrument for advancing fasteners from a stored plurality of fasteners wherein said instrument has (1) a frame, (2) an elongated tube mounted to said frame for rotation relative thereto, and (3) a support defining a longitudinal axis and pivotally mounted to said tube for movement to a pivoted position relative to said tube, an actuating system comprising:

- a cartridge containing said fasteners and a reciprocable advancing member in said cartridge for advancing said fasteners, said cartridge mounted to said support for rotation relative thereto about said longitudinal axis;

a dual function operating rod engaged with said advancing member and extending to said frame, said rod including a flexible portion to accommodate pivoting of said support, said rod being longitudinally reciprocable to move said advancing member and also being rotatable to rotate said cartridge relative to said support; and

an arcuate path-defining structure carried by at least one of said tube and said support for receiving said rod flexible portion to establish a frictional engagement preventing rotation of said cartridge relative to said support when said cartridge is subjected to an externally applied torque that is less than a predetermined minimum torque.

5,588,582

COOLING DRUM FOR A CONTINUOUS CASTING SYSTEM AND METHOD FOR MANUFACTURING THE SAME

Kunimasa Sasaki, Youichi Wakiyama, Takahiro Matsumoto; Kisaburo Tanaka, and Keiichi Yamamoto, all of Hiroshima, Japan, assignors to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 257,746, Jun. 9, 1994, Pat. No. 5,469,909.


This application May 25, 1995, Ser. No. 450,404

Int. Cl.⁶ B23K 20/00

U.S. Cl. 228—127

1 Claim

1. A method for manufacturing a cooling drum for a continuous casting system, comprising of the steps of fitting a hollow cylindrical rigid member in a hollow cylindrical cooling member to establish a set of bonding surfaces, fitting a restraining member around an outer circumferential surface of said cooling member



with a releasing agent interposed between said restraining member and said outer surface of said cooling member, raising a temperature of the bonding surfaces of said rigid member and said cooling member and then holding said temperature at 900° C. or higher while maintaining the bonding surface in an evacuated state, further heating said rigid member from its inner circumference side to raise its temperature higher than the temperature of said restraining member wherein the bonding surfaces are metallurgically bonded by pressing them as a result of difference in thermal expansion therebetween, and after effecting bonding of the bonding surfaces, electro-deposition plating a heat-resistance member on said outer surface of said cooling member.

5,588,583


PAPERBOARD CONTAINER HAVING FLEXIBLE PRODUCT DIVIDING KEEL

John W. Cargile, Jr., Decatur, Ga., assignor to Kliklok Corporation, Decatur, Ga.

Filed May 17, 1995, Ser. No. 443,231
Int. Cl.⁶ B65D 25/04

U.S. Cl. 229—120.17

20 Claims



1. A container comprising:

- a first keel panel;
- a second keel panel attached to said first keel panel along a first fold line, said first and second keel panels combining to at least partially form a keel;
- a first floor panel attached to said first keel panel along a second fold line;
- a second floor panel attached to said second keel panel along a third fold line; and
- a first notched side panel attached to said first base panel along a fourth fold line and defining an open-ended notch which fits over and accepts a portion of said keel by contacting at least said second keel panel upon the folding of said container along said first, second, third, and fourth fold lines, said notch having its open end generally directed towards the axis of said fourth fold line.


5,588,584
LIPLESS FOLDING CARTONS AND BLANKS
Karl F. DeMay, Newark, N.Y., assignor to Fold-Pak Corporation, Newark, N.Y.
Continuation of Ser. No. 198,993, Feb. 18, 1994, Pat. No. 5,484,102, which is a continuation-in-part of Ser. No. 974,975, Nov. 12, 1992, Pat. No. 5,288,012, which is a continuation-in-part of Ser. No. 796,758, Nov. 25, 1991, abandoned. This application Jun. 2, 1995, Ser. No. 458,896

The portion of the term of this patent subsequent to Nov. 12, 2012, has been disclaimed.

Int. Cl.⁶ B65D 5/28; 5/66

U.S. Cl. 229—132

1 Claim



1. A carton assembled from a foldable blank, said carton comprising:

- (a) cover, top, rear, bottom and front panels hingedly connected in the order named, said cover, top, rear, bottom and front panels each having left and right ends and said front panel further having a first edge free of a first lip portion and said top panel being hingedly connected to said cover panel by way of a first fold line;
- (b) left and right bottom panel end flaps hingedly connected to said left and right ends of said bottom panel, said left bottom panel end flap having a second edge free of a second lip portion and said right bottom panel end flap having a third edge free of a third lip portion;
- (c) left and right front panel end flaps hingedly connected to said left and right ends of said front panel, said left front panel end flap having a fourth edge free of a fourth lip portion and said right front panel end flap having a fifth edge free of a fifth lip portion;
- (d) left and right top panel end flaps hingedly connected to said left and right ends of said top panel by way of second and third fold lines, respectively;
- (e) left and right rear panel end flaps hingedly connected to said left and right ends of said rear panel;
- (f) left and right cover panel end flaps hingedly connected to said left and right ends of said cover panel;
- (g) said cover panel is adhesively connected to said front panel;
- (h) said left bottom panel end flap is folded first, said left front panel end flap is folded second to overlie a portion of said left bottom panel end flap, said left top panel end flap is folded third, said left rear panel end flap is folded fourth and at least two of said left panel end flaps are adhesively connected together;
- (i) said right bottom panel end flap is folded first, said right front panel end flap is folded second to overlie a portion of said right bottom panel end flap, said right top panel end flap is folded third, said right rear panel end flap is folded fourth and at least two of said right panel end flaps are adhesively connected together;
- and wherein at least one of said edges free of a lip portion engages at least one of said fold lines.

5,588,585

AUTOMATIC SET-UP CARTON WITH CORNER POSTS


Jack A. McClure, Garden City, Kans., assignor to Inland Container Corporation, Indianapolis, Ind.

Filed Mar. 15, 1996, Ser. No. 616,593

Int. Cl.⁶ B65D 21/032; 21/036

U.S. Cl. 229—191

15 Claims



1. A carton formed from a one-piece blank, comprising:

- a floor;
- a pair of opposed first side walls hingedly joined to the floor along respective fold lines;
- a pair of opposed second side walls hingedly joined to the floor along respective fold lines, said first side walls and said second side walls each having opposed side edges located at outside corners of the carton;
- and at least one corner post extending from a side edge of one of said second side walls adjacent a side edge of one of said first side walls and, said corner post comprising a serial succession of post panels joined end-to-end by fold lines, the post panels folded with a double-reentrant fold to generally form a Z-shape cross-section.

5,588,586

INTERLOCKING ARRANGEMENT

Emanuel Negelen, Schweich, Germany, assignor to Riverwood International Ltd., Bristol, United Kingdom

PCT No. PCT/GB93/02060, § 371 Date May 10, 1995, § 102(e) Date May 10, 1995, PCT Pub. No. WO94/07759, PCT Pub. Date Apr. 14, 1994


PCT Filed Oct. 4, 1993, Ser. No. 411,659

Claims priority, application United Kingdom, Oct. 7, 1992, 9221130

Int. Cl.⁶ C65D 77/22

U.S. Cl. 229—198.2

15 Claims



1. An interlocking device for coupling two pieces of sheet material, comprising:

- guide means for enabling the two pieces to be moved towards and away from each other, the guide means including a projecting portion on a first piece of said two pieces and

means for defining an associated opening in a second piece of said two pieces, said opening for receiving said one projecting portion; and

means for locking said two pieces together comprising at least one hinged tongue having a free end and formed in one of said first piece or said second piece and, in use, extending towards the other of said first piece or said second piece, said locking means further comprising at least one flap formed in said other piece and being hingedly connected to said other piece thereby defining a hole in said other piece;

said projecting portion, said opening, said tongue, and said flap are positioned relative to each other such that said projecting portion is inserted into said opening and the tongue is pushed into engagement with the flap, said flap pivoting to allow the tongue to pass through the hole;

wherein said flap has a resilience such that the flap firmly engages a bottom surface of the tongue as the tongue is being pushed into the hole, said tongue and said flap causing said first and second pieces to become interlocked to each other; and

wherein the opening is enclosed within the second piece and is generally arcuate with an edge portion of the second piece being narrowest approximately at a center of the opening.

5,588,587

DUAL OVENABLE FOOD PACKAGE


David E. Stier, Middletown, and Katherine S. Liquori, Goshen, both of N.Y., assignors to International Paper, Purchase, N.Y.

Filed Nov. 22, 1995, Ser. No. 561,729

Int. Cl.⁶ B65D 5/20; 6/06

U.S. Cl. 229—232

7 Claims



1. A container formed from a unitary blank of paperboard and being of generally rectangular parallelepiped form for packaging a food containing dish, the container having a bottom wall, four side walls, and a top wall, one of said container side walls being a first of said container side walls defined by a depending wall from said top wall and an upstanding wall from said bottom wall to thereby define a first container side wall of two plies of paperboard, a dish positioned on said container bottom wall, said dish having a bottom and upstanding side walls, said dish bottom resting on said container bottom wall, said dish having an upper horizontal flange extending radially outwardly therefrom, said horizontal flange having a first radially outwardly extending ear, said a first flange ear being bent downwardly and sandwiched between said two plies of paperboard of said first container side wall, means carried by said container top wall for facilitating ripping off a portion thereof to yield an access opening to said dish, said access opening being

smaller in dimension than said dish flange to thereby prevent said dish from being removed from said container after said ripping.

5,588,588

SIGNAL DEVICE FOR USE WITH A MAILBOX


Harold N. Byrd, Purdon, Tex., assignor to B&B Partnership, Corsicana, Tex.

Filed Feb. 2, 1995, Ser. No. 382,571

Int. Cl.⁶ B65D 91/00

U.S. Cl. 232—35

13 Claims



1. A signal device for a mailbox having a front end, a rear end, a downward facing side, and a door, said door mounted to the front end of said mailbox, said signal device comprising:

(a) an angle plate adapted for attachment to the downward facing side of said mailbox, said angle plate having a top portion and a side portion;

said top portion oriented generally horizontal;

said side portion depending from said top portion in a generally vertical direction and having first and second ends;

said first end having a pivot pin formed thereon;

said second end having upper and lower arms extending rearward from said second end forming a rearward opening notch therebetween, said upper arm having a length greater than said lower arm so as to form a shoulder on the upper side of said notch; and

(b) a lever member having a shank member and an indicating member;

said shank member having first and second ends and a central portion therebetween;

said central portion having an elongated slot formed therein, said slot slidably and pivotally engaging said pivot pin on said angle plate;

said first end having a friction surface formed thereon;

said indicating member mounted on said second end of said shank member;

said indicating member dimensioned to engage said notch in said angle plate when said lever member has been pivoted until said shank member encounters said shoulder and said lever member has further been translated into a forward position; and

said indicating member further dimensioned to disengage said notch in said angle plate when said lever member is translated rearward.

5,588,589

AIR CONDITIONER


Manabu Ishihara; Tsuyoshi Rakuma, both of Gunma-ken; Hiroshi Kanai, Saitama-ken; Takashi Fudo, and Masato Watanabe, both of Gunma-ken, all of Japan, assignors to Sanyo Electric Co., Ltd., Osaka, Japan

Filed May 22, 1995, Ser. No. 447,068

Claims priority, application Japan, Aug. 19, 1994, 6-195781
Int. Cl.⁶ G05D 23/00

U.S. Cl. 236—46 R

9 Claims



1. A device for regulating the temperature in a room comprising: room temperature detection means for detecting the temperature in the room;

temperature setting means for setting a target temperature;

air conditioning means for performing an air conditioning operation to bring the room temperature detected by said room temperature detection means toward said target temperature; and

target temperature changing means for correcting said target temperature to rise and fall periodically in accordance with a predetermined rule after the room temperature has substantially reached said target temperature by operation of said air conditioning means and shifting the average value of said target temperature after the correction has been made in such a direction that the air conditioning load on said air conditioning means is reduced from that for attaining said target temperature before the correction.

5,588,590

EXPANSION VALVE COMBINED WITH A SOLENOID VALVE


Hisayoshi Sakakibara, Nishio; Tomoo Okada, and Tadaaki Ikeda, both of Sayama, all of Japan, assignors to Kabushiki Kaisha Saginomiya Seisakusho, Tokyo, and Nippondenso Co., Ltd., Aichi, both of Japan

Filed Nov. 29, 1994, Ser. No. 350,061

Claims priority, application Japan, Nov. 30, 1993, 5-299887
Int. Cl.⁶ F25B 41/04

U.S. Cl. 236—92 B

11 Claims



1. An expansion valve combined with a solenoid valve for use in a refrigerant cycle, comprising:
a valve body with a primary port and a secondary port formed therein;

a refrigerant passage formed in said valve body between said primary port and said secondary port;

a solenoid valve attached to said valve body to open and close said refrigerant passage at an intermediate portion thereof;

a diaphragm defining an outer pressure chamber and an inner pressure chamber, said outer pressure chamber being communicated to a temperature sensing means;

an expansion valve member moved by action of said diaphragm to come into and out of contact with a valve seat formed at said primary port side of said refrigerant passage on an upstream side of said solenoid valve for performing a cooling operation; and

an inner pressure equalizing hole formed in said valve body to communicate said secondary port side on a downstream side of said solenoid valve with said inner pressure chamber.

5,588,591

HEAT DISSIPATION UNIT


Bruce K. Sweitzer, Jr., 2145 N. Glade Rd., Swanton, Md. 21561

Filed Aug. 31, 1995, Ser. No. 522,494

Int. Cl.⁶ F24D 3/10

U.S. Cl. 237—8 C

6 Claims



4. A heating system for heating a plurality of rooms within a building, said heating system comprising:

a source of heating fluid supplying heating fluid;

a piping system for conducting said heating fluid to each of the plurality of rooms, said source of heating fluid being in communication with said piping system;

a pump for circulating said heating fluid through said piping system; and

at least one heat dissipation sub-system provided in each of the plurality of rooms, said heat dissipation sub-system receiving heating fluid from said piping system, said heat dissipation sub-system including:

a heat dissipation unit having an inlet opening and a discharge opening, said heat dissipation unit being dimensioned and configured to allow heat transfer from said heating fluid flowing therethrough to air contained in a respective one of the plurality of rooms, said discharge opening being in fluid communication with a discharge conduit,

an anti-backup fitting provided intermediate said discharge opening and said discharge conduit, said anti-backup fitting having a bend portion, said bend portion being located at an elevation above said discharge opening,

a three-way valve having a movable member, said movable member being movable between a first and a second position, said three-way valve having a valve inlet, a first outlet, and a second outlet, said movable member allowing fluid communication between said valve inlet and said first outlet when in said first position, said movable member allowing fluid communication between said valve inlet and said second outlet when in said second position, and said first outlet being in fluid communication with said inlet opening, and

a bypass pipe having a bypass pipe inlet and a bypass pipe outlet, said bypass pipe inlet being in fluid communication with said second outlet, and said bypass pipe outlet being in

fluid communication with said discharge conduit, whereby said three-way valve selectively directs heating fluid through said heat dissipation unit and said bypass pipe;

said piping system includes a heating fluid supply pipe communicating with said valve inlet of said at least one heat dissipation sub-system in each of the plurality of rooms, and a heating fluid return pipe communicating with said discharge conduit of said at least one heat dissipation sub-system in each of the plurality of rooms.

5,588,592

METHOD AND APPARATUS FOR DETECTING THE ONSET OF FLOODING OF AN ULTRASONIC ATOMIZER

Robert F. Wilson, Vancouver, Canada, assignor to J. Eberspächer, Esslingen, Germany


Filed Apr. 13, 1995, Ser. No. 421,685

Claims priority, application Germany, Apr. 14, 1994, 44 12 900.9

Int. Cl.⁶ H03B 5/30; B05B 1/08

U.S. Cl. 239—4

20 Claims



6. An atomizer comprising:

a transducer means for converting driving signals into vibrations;

excitation means for sending said driving signals to said transducer means, said excitation means generating said driving signals to correspond to a natural resonance frequency of said transducer means, said excitation means changing said driving signals to follow changes in said natural resonance frequency of said transducer means;

frequency detection means for monitoring said driving signals and for determining a rate of change of said frequency of said natural resonance frequency, said frequency detection means also generating a flooding signal when said rate of change of said frequency of said natural resonance frequency exceeds a threshold value.

5,588,593

SAFETY APPARATUS FOR HIGH PRESSURE LIQUID JET SYSTEM

Thomas B. Boisture, Baytown, Tex., assignor to C.H. Heist Corp., Baytown, Tex.


Filed Jun. 5, 1995, Ser. No. 464,958

Int. Cl.⁶ B05B 1/02; B26F 3/00

U.S. Cl. 239—67

17 Claims

1. A safety apparatus for use in a high pressure fluid jet system for operation by an operator, said fluid jet system includes a high pressure fluid source for supplying fluid, a nozzle for ejecting said fluid, and an electrically operated valve having an on-off flowthrough path, said flowthrough path coupled between said high pressure fluid source and said nozzle, said safety apparatus comprising:



a trigger switch operable by the operator of the high pressure fluid jet system and
a proximity switch located near the nozzle for indicating when said proximity switch is within a first distance of a structure to be operated on by the high pressure fluid jet system,
said trigger switch and said proximity switch connected to the valve to operate the valve when said trigger switch is operated by the operator and said proximity switch indicates proximity to the structure at a concurrent time.

5,588,594

ADJUSTABLE ARC SPRAY NOZZLE


Carl L. C. Kah, Jr., 778 Lakeside Dr., North Palm Beach, Fla. 33408

Filed Feb. 3, 1995, Ser. No. 383,073

Int. Cl.⁶ B05B 1/32; 15/02

U.S. Cl. 239—107

20 Claims



1. An adjustable orifice sprinkler spray nozzle assembly, comprising fixed housing means defining a passage having an inlet for attachment to a source of pressurized water and an outlet defined by a spiraled edge having radially offset ends for dispensing water, said outlet having an axis, said radially offset ends being connected; and moveable means including means defining a sloped axially spiraled surface cooperating with said spiraled edge of said fixed housing means for defining an adjustable arcuate dispensing orifice adjustable about the axis of said outlet.

5,588,595

NUTATING SPRINKLER

Frederick J. Sweet, College Place, and Larry P. Meyer, Walla Walla, both of Wash., assignors to Nelson Irrigation Corporation, Walla Walla, Wash.


Continuation-in-part of Ser. No. 212,938, Mar. 15, 1994, Pat. No. 5,439,174. This application May 19, 1995, Ser. No. 446,099

Int. Cl.⁶ B05B 3/02

U.S. Cl. 239—222.17

15 Claims

1. A sprinkler comprising a body portion having a nozzle at one end and a cap assembly supported thereon at an opposite end, said



cap assembly supporting a spray plate located downstream of said nozzle, said spray plate having a plurality of stream distributing grooves formed on one side thereof configured to cause said spray plate to rotate when struck by a stream emitted from said nozzle; and wherein said spray plate includes a mounting shaft extending from said spray plate and having a part spherical head received within a bearing cage in said cap assembly, said bearing cage including a bearing separator holding a plurality of ball bearings in a substantially horizontal array arranged about a longitudinal center axis of said sprinkler, said part spherical head located centrally above and in engagement with said plurality of ball bearings, thereby permitting said spray plate to wobble as it rotates.

5,588,596

FALLING FILM EVAPORATOR WITH REFRIGERANT DISTRIBUTION SYSTEM


Jon P. Hartfield, and Duane F. Sanborn, both of La Crosse, Wis., assignors to American Standard Inc., Piscataway, N.J.

Filed May 25, 1995, Ser. No. 449,965

Int. Cl.⁶ A23C 3/04; B05B 15/00

U.S. Cl. 239—542

18 Claims



1. A spray tree distribution system comprising:
a fluid inlet;
a manifold operably connected to the fluid inlet and adapted to receive fluid therefrom;
a plurality of substantially horizontal fluid distributing devices operably connected to the manifold and adapted to receive fluid therefrom;
wherein each of the fluid distributing devices includes an outer tube defining an interior chamber having at least one fluid outlet from the interior chamber and an inner connected to the manifold and having at least one fluid outlet open to the interior chamber.

5,588,597

NOZZLE PLATE FOR A LIQUID JET PRINT HEAD

Holger Reinecke; Nezhil Unal, both of Dortmund; Ralf-Peter Peters, Bergisch-Gladbach; Frank Bartels, Hattingen, and Friedolin F. Noker, Karlsruhe, all of Germany, assignors to MicroParts GmbH, Dortmund, Germany


Filed Aug. 30, 1994, Ser. No. 297,780

Claims priority, application Germany, Sep. 3, 1993, 43 29 728.5

Int. Cl.⁶ B05B 1/14; B41J 2/14

U.S. Cl. 239—553.5

1 Claim



1. A nozzle comprising:
a cast plate structure; and
functional regions in said plate structure, said functional regions including at least one nozzle, at least one liquid chamber, at least one supply container and connection channels connecting said at least one nozzle, said at least one liquid chamber and said at least one supply container, wherein said plate structure has at least one nozzle on opposite sides thereof, including further plates assembled to said opposite sides and having heating elements and electrical connections for said nozzles.

separating ferrous materials from said materials stream by vibrating said stream of commingled materials in a non-magnetizable vibrating receptor;
moving a magnetic belt over said vibrating stream of commingled materials and magnetically lifting ferrous material from said stream of commingled materials;
splitting off from said stream of commingled materials a substream of mixed particulate and passing said substream onto a variable speed conveyor, varying the speed of the conveyor to accommodate variation in the amount of materials in said substream and hand sorting unlike particulate one from the other from said substream;
splitting off from said stream of commingled materials a substream of particles of varying density comprising first particles having at least a predetermined density and second particles of less density than said first particles;
carrying said second particles away from said first particles in a stream of air to split said substream of particles of varying density into a sub-substream of said first particles and a sub-substream of said second particles.

5,588,599

METHOD OF MANUFACTURE OF POLYESTER-CHIP PRODUCTS FOR CASTING ARTIFICIAL-STONE ARTICLES


James P. Novak, 4625 S. 3rd Ave., Tucson, Ariz. 85714

Filed Sep. 12, 1994, Ser. No. 304,148

Int. Cl.⁶ B02C 19/00; 19/12

U.S. Cl. 241—23

12 Claims



5,588,598

COMMINGLED RECYCLABLES RECOVERY AND RECYCLING PROCESS AND RELATED APPARATUSES

John C. Becker, 12 Ella St., Valley Stream, N.Y. 11580; John D. Cameron, Jr., 59 Royal Ct., Rockville Center, N.Y. 11570; William L. Cameron, 241 W. Pine St., Long Beach, N.Y. 11561, and Bryan W. Sinram, 7 Bucknell La., Stony Brook, N.Y. 11561


Continuation of Ser. No. 863,044, Apr. 3, 1992, Pat. No. 5,333,797. This application Jul. 28, 1994, Ser. No. 281,927

The portion of the term of this patent subsequent to Aug. 2, 2011, has been disclaimed.

Int. Cl.⁶ B02C 23/40

U.S. Cl. 241—19

7 Claims



1. A recycling process, comprising:
receiving a stream of commingled materials;
mechanically splitting said stream of commingled materials into a plurality of substreams, comprising:

1. A method for preparing resin chips for use as an intermediate product in the manufacture of artificial-granite and artificial-stone articles, comprising the following steps:

- (a) mixing a thermoplastic polyester resin with a filler material in predetermined proportions and feeding the resulting mixture through a heated extruder at a temperature sufficiently high to melt the thermoplastic polyester resin;
- (b) cooling the output from the extruder to a temperature below a melting point of the thermoplastic polyester resin to produce a solid material;
- (c) grinding said solid material to produce resin chips of a predetermined particle size;

- (d) screening said resin chips of a predetermined particle size to separate them from undersize fines of resin material; and
(e) recycling at least a portion of said undersize fines as feed-stock to the extruder in step (a).

5,588,600



PROCESS AND APPARATUS FOR MAKING CRUMB RUBBER FROM VEHICLE TIRES

Kenneth F. Perfido, 12 Autumn Dr., Mount Sinai, N.Y. 11766, and Anthony M. Cialone, 34 Carnation Ave., Floral Park, N.Y. 11001

Filed Jun. 7, 1995, Ser. No. 484,233
Int. Cl.⁶ B02C 19/12; 23/08

U.S. Cl. 241-23

39 Claims



1. A process for recovering crumb rubber from vehicle tires comprising:

- shredding vehicle tires to provide rubber particles which include embedded fiber and/or ferrous metal;
- contacting said rubber particles produced in step (a) with a cryogenic liquid wherein said rubber particles are chilled and cryogenic liquid vaporized;
- collecting and conveying said cryogenic fluid utilized in step (b) to a cryogenic reliquefaction means;
- reducing the particle size of said particles treated with said cryogenic liquid in step (b);
- removing substantially all of said fiber and said ferrous metal from said product of step (d) whereby fiber- and ferrous metal-free rubber particles are produced;
- contacting said rubber particles produced in step (e) with a cryogenic liquid wherein said rubber particles are cooled and cryogenic liquid is vaporized;
- collecting and conveying said cryogenic fluid product of step (f) to said cryogenic reliquefaction means;
- reducing the size of said cryogenic liquid-contacted rubber particles produced in step (f);
- recycling Cryogenic liquid reliquefied in said cryogenic reliquefaction means to steps (b) and (f) for reuse therein; and
- screening said rubber particles produced in step (h) and recovering a crumb rubber product.

YARN WINDING METHOD AND APPARATUS FOR CARRYING OUT SAME

Ralf Korber, Remscheid, Germany, assignor to Barmag AG, Remscheid, Germany
PCT No. PCT/EP93/03104, § 371 Date Jul. 26, 1994, § 102(e)
Date Jul. 26, 1994, PCT Pub. No. WO94/12421, PCT Pub. Date Jun. 9, 1994

PCT Filed Nov. 5, 1993, Ser. No. 256,843


Claims priority, application Germany, Nov. 26, 1992, 42 39 752.9

Int. Cl.⁶ B65H 67/04; 54/00

U.S. Cl. 242-18 EW

29 Claims

9. A method of winding a continuously advancing yarn onto a



rotating bobbin to form a yarn package, and comprising the steps of

- winding the advancing yarn onto a rotating bobbin positioned on a winding spindle at a winding position and including traversing the yarn at a location upstream of the winding position to thereby form a cross wound package on the bobbin;
- laterally moving the winding spindle and the rotating bobbin from said winding position to a doffing position upon the package becoming full;
- terminating the traverse of the advancing yarn and then depositing the yarn on the rotating full package on said winding spindle in an axially narrow region of the package surface so as to form a yarn accumulation.

severing the advancing yarn to form a free yarn end, and pressing the free yarn end into the yarn accumulation on the surface of the rotating package, and such that the free yarn end is secured to the package and is easily locatable.

- An apparatus for winding a continuously advancing yarn onto a rotating bobbin to form a yarn package, and comprising a spindle adapted to coaxially mount a bobbin;
- means for rotating the spindle and a bobbin mounted thereon;
- means for winding the advancing yarn onto a rotating bobbin which is mounted on said spindle while traversing the yarn at a location upstream of the bobbin to thereby form a rotating cross wound package;
- means for terminating the traverse of the advancing yarn and then depositing the yarn on the rotating package in an axially narrow region of the package surface so as to form a yarn accumulation;
- means for severing the advancing yarn to form a free yarn end, and
- means for pressing the free yarn end into the yarn accumulation on the surface of the rotating package while mounted on the spindle, and such that the free yarn end is secured to the package and easily locatable.

5,588,602

PACKAGE CHANGING SYSTEM FOR SUPPLYING AND DISCHARGING LOADED AND EMPTY PACKAGES TO AND FROM A MACHINE FRAME

Toshiyuki Uno, Kusatsu, and Yasuhiko Kubota, Kyoto, both of Japan, assignors to Murata Kikai Kabushiki Kaisha, Kyoto, Japan


Filed Feb. 14, 1994, Ser. No. 195,477

Claims priority, application Japan, Feb. 16, 1993, 5-051492; Jul. 13, 1993, 5-172888

Int. Cl.⁶ D01H 9/10; 9/14

U.S. Cl. 242-35.50 A

11 Claims



1. A package changing system having:
a first rail vertically movable parallel with a plurality of horizontal rows of spindles for which empty packages and full-loaded packages are to be replaced with each other;
a second rail connected to said first rail in a raised position of said first rail; and
a conveyance unit for travel along said second rail having means for changing packages and for entering and leaving said first rail.

5,588,603

YARN TAKE-UP TUBE SUPPLYING APPARATUS FOR A WINDER

Fumiaki Nakaji, Kyoto, Japan, assignor to Murata Kikai Kabushiki Kaisha, Kyoto, Japan


Filed Jun. 6, 1995, Ser. No. 468,752

Claims priority, application Japan, Jun. 13, 1994, 6-155256

Int. Cl.⁶ B65H 54/02; 63/00

U.S. Cl. 242-35.5 A

5 Claims



1. A yarn take-up tube supplying apparatus for a winder, comprising:

- a winder having a number of winding units in a row;
- a doffing device movably positioned at the side of said winder for transferring yarn take-up tubes;
- a storage means for storing take-up tubes, said storage means being provided on each of said winding units;
- conveyor means provided along said winder and above said storage means for supplying said yarn take-up tubes to said storage means; and
- drop-in means for dropping the yarn take-up tubes conveyed by said conveyor means into said storage means, said drop-in means including dampening means for engaging and releasing each of said tubes as said tubes are dropped in said drop-in means from said conveyor into said storage means.

5,588,604

DEVICE FOR TRANSPORTING YARN WITH A CENTRAL MAST

Gerhard Vetter, Süssen, and Eberhard Markert, Rechenhausen, both of Germany, assignors to Michael Harauf Maschinenfabrik GmbH & Co. KG, Donzdorf, Germany


Filed Apr. 12, 1995, Ser. No. 420,766

Claims priority, application Germany, Apr. 12, 1994, 44 12 433.3

Int. Cl.⁶ B65H 51/24

U.S. Cl. 242-47.05

25 Claims



1. A device for transporting yarn, comprising:
a central mast,
a plurality of circulating transport belts carried by the central mast, said plurality of transport belts exhibiting yarn support runs which extend longitudinally of the central mast and which are arranged such that they form corners of a polygonal form,
a belt drive for driving the transport belts,
a yarn winding device for winding yarn in controlled loops around the central mast and transport belts,
a first central mast support disposed at a central mast end adjacent the yarn winding device, and
a second central mast support disposed spaced from the first mast support in a travel direction of the yarn, said second central mast support including at least one supported roller carried by the central mast, at least one supporting roller having a circumferential support surface engaging a circumferential surface of an associated one of the at least one supported rollers, and a supporting roller drive mechanism for rotatably driving the at least one supporting roller, said supporting roller drive mechanism being independent from the belt drive,
wherein said belt drive and said supporting roller drive are operable to drive the supporting roller and supported roller with circumferential speeds synchronized with the belt speeds.

5,588,605

BRAKING FORCE ADJUSTING DEVICE IN A FISHING REEL


Nobuyuki Yamaguchi, Tokyo, Japan, assignor to Daiwa Seiko, Inc., Tokyo, Japan

Filed Sep. 7, 1994, Ser. No. 301,886

Claims priority, application Japan, Sep. 8, 1993, 5-053616 U
Int. Cl.⁶ A01K 89/015; 89/02

U.S. Cl. 242-268

13 Claims



1. A braking force adjusting device in a fishing reel in which an adjuster adjusts the braking force of a drive gear which is rotatably mounted on and frictionally coupled through a braking member to a handle shaft to the end of which a handle is connected, said adjuster being threadably engaged with said handle shaft so as to be freely moved back and forth along a longitudinal axis of said handle shaft, comprising an improvement wherein:

said adjuster includes an operation member adapted to be turned with an operator's fingers, and a threaded engaging member, said operation member and said threaded engaging member being formed separately from each other; said threaded engaging member is axially slidably received and non-rotatably fitted in a fitting recess which is formed in said operation member, said threaded engaging member comprising at least one outer planar surface extending an entire axial length of said threaded engaging member, said outer planar surface contacting said fitting recess along at least one inner planar surface formed on said operation member to prevent relative rotation therebetween, wherein said planar surface permits said threaded engaging member to slide axially relative to said operation member; and an engaging portion adjacent to said fitting recess is adapted to push said braking member.

5,588,606

COVER OF TAPE CARTRIDGE AND ASSEMBLY METHOD OF SAME CARTRIDGE

Shuichi Kikuchi, and Shintaro Higuchi, both of Miyagi, Japan, assignors to Sony Corporation, Tokyo, Japan

Division of Ser. No. 428,517, Apr. 25, 1995. This application Jan. 31, 1996, Ser. No. 594,699

Claims priority, application Japan, Apr. 28, 1994, 6-091672
Int. Cl.⁶ G11B 23/04; 23/087


U.S. Cl. 242-347

5 Claims

1. A method of assembling a tape cartridge, comprising the following steps:

applying grease to portions of a base plate with which portions of a drive roller and a corner roller are respectively in contact; assembling the drive roller, the corner roller and a hub to the base plate;

temporarily fixing a cover to the base plate in a state where a main body of the cover is separated from the base plate, the cover having at least one pin for temporarily fixing the cover to the base plate, the pin extending from the main body of the cover and having a first engagement portion and a second engagement portion which are located at a tip end section of



the pin, the first engagement portion being located between the cover main body and the second engagement portion, wherein said temporarily fixing includes engaging the second engagement portion with an engaging section formed in the base plate;

removing the cover from the base plate;

winding a tape on the hub;

cutting off and removing the second engagement portion of the pin; and

provisionally fixing the cover to the base plate, wherein said provisionally fixing includes engaging the first engagement portion of the pin with the engaging section of the base plate.

5,588,607

APPARATUS WITH A DRIVE ARRANGEMENT OF INFORMATION CARRIERS IN THE FORM OF TAPES

Arthur R. Van Es; Gerard Van Engelen; Theodor H. M. De Nier, and Johannes F. Hoefnagels, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Feb. 27, 1995, Ser. No. 394,978

Claims priority, application European Pat. Off., Mar. 2, 1994, 94200528

Int. Cl.⁶ G11B 15/44

U.S. Cl. 242-356.3

20 Claims



1. An apparatus comprising a drive arrangement for winding an information carrier in the form of a tape between a first reel hub and a second reel hub and vice versa, which apparatus comprises a motor having a motor shaft drivable in a positive direction of rotation and an opposite negative direction of rotation

a first drive spindle for driving the first reel hub and including a first spindle wheel,

a second drive spindle for driving the second reel hub and including a second spindle wheel,

a first, a second, a third and a fourth transmission device, respectively, comprising a first, a second, a third and a fourth set of drive wheels, each set of drive wheels including one of the spindle wheels and being directly drivable by said motor, which transmission devices are switchable between inactive and active states and respectively serve for the motor shaft to drive

the first drive spindle with a first transmission ratio, the second drive spindle with a first transmission ratio, the first drive spindle with a second transmission ratio, and the second drive spindle with a second transmission ratio,

switching mechanisms for switching the first, the second, the third and the fourth transmission device between active and inactive states,

a rotatable cam disc having guide surfaces which cooperate with at least one switching mechanism, and

a cam disc drive wheel for driving the cam disc, the cam disc being rotatable to a plurality of stop positions each corresponding to one of the states of one of the transmission devices while at the same time the other transmission devices are in their inactive states, characterised in that: said states of the first, the second, the third and the fourth transmission device are determined exclusively by the cam disc, and

the cam disc is rotatable both in a clockwise direction of rotation and in an opposite counterclockwise direction of rotation and cooperates with the switching mechanisms in each of the directions of rotation of the cam disc.

5,588,608

PRETENSIONER

Kelsuke Imai; Keiichi Kato; Takayuki Ando; Fuminori Terakawa, and Kenji Matsui, all of Aichi-ken, Japan, assignors to Kabushiki Kaisha Tokai-Rika-Denki Seisakusho, Aichi-ken, Japan


Filed Aug. 24, 1994, Ser. No. 294,917

Claims priority, application Japan, Aug. 30, 1993, 5-046979

Int. Cl.⁶ B60R 22/46

U.S. Cl. 242-374

15 Claims



1. A pretensioner which forcibly rotates a webbing take-up shaft when a vehicle suddenly decelerates and which tenses a webbing in a direction of restraining a vehicle occupant, comprising:

a rotating drum connected to an axial end portion of said webbing take-up shaft via a clutch mechanism;

a frame including a support plate and a pair of opposing leg plates for rotatably supporting said take up shaft;

a cylinder having sidewalls into which gas, which is generated when the vehicle suddenly decelerates, flows;

a piston having a bottom and sidewalls, and being slidably disposed within said cylinder and, said bottom of said piston receiving gas pressure of the gas which flows into said cylinder to slide within said cylinder;

a movable pulley which is axially, rotatably supported inside of said piston;

a wire, one end of said wire being wound around said rotating drum, another end of said wire being fixed to a bottom portion of said cylinder, and an intermediate portion of said wire being trained around said movable pulley, said wire containing doubled-back portions before and after a portion around said movable pulley, and extending through said bottom of said piston inside said cylinder, said doubled back-ports being parallel with each other, and disposed within said cylinder,

a fixed pulley exterior of said cylinder for changing the direction of movement of said wire between said movable pulley and said rotating drum.

wherein said sidewalls of said cylinder are mounted adjacent to said frame side by side to each other such that the diameter dimension of said take-up shaft is located within a range of a height of the cylinder for increasing the compactness of said pretensioner, and

wherein said parallel portion of said doubled-back portions of said wire nearest to said take-up shaft extends through said cylinder and engages said direction-changing fixed pulley for further increasing the compactness of the pretensioner.

5,588,609

SEAT BELT WINDING DEVICE

Sadanori Ohsumi, Kanagawa, Japan, assignor to NSK Ltd., Tokyo, Japan


Filed Apr. 11, 1995, Ser. No. 419,989

Claims priority, application Japan, Apr. 13, 1994, 6-097891; Apr. 18, 1994, 6-101701

Int. Cl.⁶ B60R 22/28; 22/42

U.S. Cl. 242-376

20 Claims



14. A seat belt winding device for a webbing in a vehicle, comprising:

a retractor base;

a winding shaft rotatably supported by the retractor base; and

a bobbin rotated integrally with the winding shaft, the bobbin including a plastically deforming member on an outer periphery of the bobbin, the plastically deforming member being of a strength to be deformed by a load acting on the webbing which exceeds a first predetermined value;

clamping means disposed in the retractor base for directly holding the webbing in an emergency of the vehicle, the clamping means releasing the webbing from holding when a load acting on the webbing exceeds a second predetermined value.


5,588,610

POWER STRING AND CHALK LINE

Daniel McGee, P.O. Box 26, Greenbank, Wash. 98253
Continuation-in-part of Ser. No. 393,080, Feb. 23, 1995, abandoned. This application Jul. 18, 1995, Ser. No. 503,816
Int. Cl.⁶ B44D 3/38

U.S. Cl. 242—379

7 Claims



1. A straight line or chalk line tool for obtaining a straight line reference using a line having a wound end and a free end, comprising:

- a housing having an upper face and a lower face, a support rod mounted between the upper and the lower face, and a line aperture;
- a spool, having two end plates separated by a hollow axle, sized to fit within the housing and rotatably mounted about the support rod inside the housing, such that the wound end of the line can be wound around the spool and the free end of the line can be pulled from the housing via the line aperture;
- a coil spring, affixed to the spool, for maintaining rotational tension on the spool, such that as the free end of the line is pulled from the spool, the rotational tension of the spring increases, biasing the spool against removal of the line from the spool and toward rewinding line onto the spool; and
- a slip-lock means that allows continuous movement of the spool in either direction, but restricts movement of the spool if continuous movement of the spool is halted.

5,588,611

RETRACTOR WITH A CLAMPING MECHANISM

Sadanori Osumi; Kiyoshi Ogawa; Toshifumi Taguchi, all of Kanagawa, and Mutsumu Haraoka, Aichi, all of Japan, assignors to NSK Ltd., Tokyo, and Toyota Jidosha Kabushiki Kaisha, Toyota, both of Japan

Filed Mar. 7, 1995, Ser. No. 399,634

Claims priority, application Japan, Mar. 10, 1994, 6-065441; Mar. 10, 1994, 6-065443; Mar. 10, 1994, 6-066557


Int. Cl.⁶ B60R 22/42

U.S. Cl. 242—381.1

22 Claims

1. A retractor with a clamping mechanism for directly holding a webbing in an emergency vehicle, comprising:

- a lower plate fixed to the retractor base;
- a movable clamp member for holding a webbing between the lower plate and the clamp member;
- a guide member for guiding the clamp member to a webbing holding position; and
- a holding means for preventing a movement of the guide member in a webbing draw-out direction, the holding means



including a plastically deforming portion which is deformed in accordance with a further movement of the clamp member in the webbing draw-out direction beyond the webbing holding position;

wherein the guide member is fixed to the holding means so that the clamp member is moved in the webbing draw-out direction, while the clamp member holds the webbing, by deforming the plastically deforming portion of the holding means in accordance with the further movement of the clamp member in the webbing draw-out direction when a tensile force exceeding a predetermined value acts on the webbing.

5,588,612

SAFETY BELT BLOCKING DEVICE WITH SELF-BLOCKING PREVENTION

Ulrich Laun, Drage, Germany, assignor to Autoliv Development AB, Vargarda, Sweden


Filed Dec. 15, 1995, Ser. No. 573,255

Claims priority, application Germany, Dec. 15, 1994, 44 655.1

Int. Cl.⁶ B60R 22/405; 22/41; 22/42

U.S. Cl. 242—383.1

4 Claims



1. A blocking device for a safety belt; said blocking device comprising:
a safety belt retractor with a housing and a belt reel for receiving the safety belt, said belt reel positioned in said housing;
said safety belt retractor having a control wheel with outer toothing, said control wheel fixedly connected to said belt reel so as to rotate with said belt reel;

a control plate pivotable between a disengaged position and a blocking position upon withdrawing the safety belt from said belt reel, in which blocking position said control plate triggers blocking of safety belt withdrawal;

a safety-belt-sensitive control means acting on said control wheel, said safety-belt-sensitive control means comprising a first sensor pawl for coupling said control wheel and said control plate when said safety-belt-sensitive control means is triggered;

a vehicle-sensitive control means acting on said control wheel, said vehicle-sensitive control means comprising a second sensor pawl engaging said toothing of said control wheel when said vehicle-sensitive control means is triggered;

a pilot pawl pivotably connected to said control plate, said pilot pawl pivotable between a rest position and an abutment position, wherein said pilot pawl is moved from said rest position into said abutment position, when said control plate is rotated from said disengaged position into said blocking position;

wherein said pilot pawl in said abutment position secures said control plate upon return from said blocking position into said disengaged position in an intermediate position before reaching said disengaged position in which intermediate position a relative movement between said control wheel and said control plate is possible; and

wherein due to said relative movement said first and second sensor pawls are released, subsequently said pilot pawl is returned into said rest position, and said control plate is returned into said disengaged position.

5,588,613

FISH TAPE REEL ATTACHMENT APPARATUS USED IN COMBINATION WITH A FISH TAPE REEL


Peter Nagy, 24761 Nellie Gail Rd., Laguna Hills, Calif. 92653

Filed Mar. 27, 1995, Ser. No. 411,269

Int. Cl.⁶ B65H 57/12; 75/40; H02G 1/08

U.S. Cl. 242—395

15 Claims



1. A fish tape reel attachment apparatus used in combination with a fish tape reel which has an elongated stiff, resilient tape wound on the reel and having means on one end thereof to which a length of wire may be secured to be pulled through a conduit, the apparatus comprising:

- a generally rectangular shaped frame member having a pair of opposite transverse parallel bars connected at their ends to a pair of opposite longitudinally elongated parallel bars and forming a space therebetween, one of the pair of opposite longitudinally parallel bars being removably detachable for installing said fish tape reel within the space of the frame member;
- an internal hub member mounted between said pair of longitudinally parallel bars such that said fish tape reel is fitted onto the internal hub member;
- a gear mechanism including a large gear wheel meshed with a small gear wheel, the large gear wheel mounted on a first shaft which in turn interconnects, and is located adjacent, to said internal hub member for rotating said internal hub member at a higher torque, the first shaft mounted between said pair of longitudinally parallel bars and having first connection means, the small gear wheel mounted on a second shaft which in turn is mounted to the other one of said pair of longitudinally parallel bars for rotating said large gear wheel which in

5,588,614

ELECTRONIC-COMPONENT SUPPLYING CARTRIDGE

Yukinori Takada, Anjo; Tokiyuki Kuno, Nagoya; Yasuo Muto, Chiryu, and Koichi Asai, Nagoya, all of Japan, assignors to Fuji Machine Mfg. Co., Ltd., Aichi-ken, Japan


Filed Jul. 3, 1995, Ser. No. 497,750

Claims priority, application Japan, Jul. 7, 1994, 6-156246

Int. Cl.⁶ B65H 20/02

U.S. Cl. 242—538.2

13 Claims




1. A cartridge for supplying a carrier tape which carries a plurality of electronic components, the tape having a plurality of pockets for accommodating the respective components, and a pair of side portions on both sides of the pockets, the pockets projecting downward from the side portions, the cartridge comprising:

- a cartridge frame;
- a tape feeding device mounted on said cartridge frame, for feeding said carrier tape in a feeding direction;
- a pair of rails provided on said cartridge frame such that said rails extend parallel to said feeding direction, said pair of rails supporting said pair of side portions of said carrier tape, respectively, and permitting movement of said pockets of the tape when the tape is fed on the rails by said tape feeding device;
- a tape positioning device which positions said carrier tape with respect to a lateral direction in which said pair of side portions of the tape are spaced from each other; and

a rail adjusting device which adjusts a spacing between said pair of rails to each of a plurality of different values.

5,588,615
ROTATABLE PAPER ROLL HOLDER
Curtis L. Batts, 407 S. Alexander Ave., Duncanville, Tex. 75116
Filed Mar. 24, 1995, Ser. No. 409,430
Int. Cl.⁶ B65H 19/10
U.S. Cl. 242—598.3

5 Claims




1. A rotatable paper roll holder comprising:
a mounting means for securing said roll holder to a support surface;
a yoke including spaced lateral yoke arms;
a spindle removably positioned between the lateral yoke arms of the yoke;
an adjustable angle coupling means interposed between the mounting means and the yoke for supporting the yoke relative to the mounting means and permitting selective rotation of the yoke about an axis directed through the mounting means and orthogonally intersecting a longitudinal axis of the spindle, wherein the mounting means comprises a mounting boss defining a hollow interior with the adjustable angle coupling means being secured to the mounting boss, and wherein the mounting boss includes an axle aperture directed therethrough, and further wherein the adjustable angle coupling means comprises an axle guide projecting from the mounting boss and positioned over the axle aperture extending through the mounting boss; an axle projecting from the yoke and extending through the axle guide and into the hollow interior of the mounting boss; an end cap secured to a free distal end of the axle within the hollow interior of the mounting boss; a spring interposed between the end cap and an interior surface of the mounting boss for biasing the yoke against an exterior surface of the axle guide.

5,588,616
STATIC VENT UNITS
Terrence L. Perkins, Yeovil, England, assignor to Westland Helicopters Limited, Yeovil, England
Filed Oct. 3, 1994, Ser. No. 316,465
Claims priority, application United Kingdom, Oct. 7, 1993, 9320678
Int. Cl.⁶ B64D 45/00


11 Claims

1. A static vent unit located in the side of a helicopter fuselage with an outer surface of a support plate substantially flush with a surface of the fuselage, a circular vent port through the plate and an elongated strake extending substantially horizontally below the vent port with an upper surface facing the vent port and extending generally perpendicular to said support plate surface, and further including airflow deflection means independent of said elongated strake, said airflow deflection means being located below the strake to deflect airflow away from the perpendicularly extending portion of the strake when the unit is operating in airflow at a positive incidence as herein defined.



5,588,617
MOTOR OPERATED RESTRICTOR VALVE
Daniel L. Bliss, Wichita, Kans.; Steven E. Marshall, Renton, and Michael I. Ruby, Kirkland, both of Wash., assignors to The Boeing Company, Seattle, Wash.
Division of Ser. No. 48,028, Apr. 14, 1993, Pat. No. 5,574,101.
This application Jan. 17, 1995, Ser. No. 373,812
Int. Cl.⁶ B64D 45/00
U.S. Cl. 244—1 N

2 Claims




1. A method for preventing noise from entering the cabin of an aircraft through drain openings comprising the steps of inserting a motor operated restrictor valve between a drain hose and a drain mast;
spring loading said restrictor valve to an open position to provide full flow of fluid between said drain hose and said drain mast; and then
applying power to said motor operated restrictor valve, thereby producing a shock wave to block noise from entering the cabin.

5,588,618
COUNTER-TORQUE DEVICE WITH ROTOR AND FLOW-STRAIGHTENING STATOR, BOTH OF WHICH ARE DUCTED, AND PHASE MODULATION OF THE BLADES OF THE ROTOR, FOR HELICOPTER
Henri-James R. Marze, Rognac; Vincent Jean-Luc Routhieu, Aix-En-Provence; Gilles L. Arnaud, Marseille, and Rémy E. Arnaud, Vitrolles, all of France, assignors to Eurocopter France, Marignane Cedex, France
Filed Aug. 30, 1994, Ser. No. 298,080
Claims priority, application France, May 4, 1994, 94 05478
Int. Cl.⁶ B64C 27/82

15 Claims


1. Counter-torque device for a helicopter, comprising a variable-pitch multi-blade rotor mounted so that it can rotate substantially coaxially in a duct for a flow of air of axis substantially transversal



to the helicopter and passing through a fairing incorporated into the tail part of the helicopter, so that the pitch change axes of the blades move in a plane of rotation substantially perpendicular to the axis of the fairing duct, as well as a flow-straightening stator fixed into the duct downstream of the rotor and including stationary vanes located substantially in a star configuration about the axis of the duct and each exhibiting an asymmetric aerodynamic profile, of which the camber and the angular setting with respect to the axis of the duct are such that the vanes straighten out the airflow downstream of the rotor substantially parallel to the axis of the duct, wherein the blades of the rotor are distributed angularly about the axis of the rotor with uneven azimuth modulation, such that any angle between any two arbitrary blades of the rotor is different from any angle between any two arbitrary vanes of the flow-straightener.

5,588,619
PROPELLER SYNCRO-PULSING
Leroy LoPresti, 2050 13th, and Jim LoPresti, 2620 Airport N. Dr., both of Vero Beach, Fla. 32960
Filed Nov. 21, 1994, Ser. No. 343,042
Int. Cl.⁶ B64C 11/00
U.S. Cl. 244—53 R

1 Claim




1. An improvement in the combination of an aircraft propeller and an internal combustion engine comprising:
said aircraft propeller providing a high energy wake at its trailing edge which travels aft in a helical pattern and provides a driving thrust, and said aircraft propeller being driven by said internal combustion engine;
said improvement comprising: said internal combustion engine having an induction inlet in close proximity to a portion of said propeller, said propeller having a blade extension located on said propeller at said portion in close proximity to said induction inlet and said propeller being indexed in relation to the opening and closing of an inlet valve of said internal combustion engine such that an impulse of air created by said

blade extension will enter said induction inlet and arrive at said intake valve when it is open, thereby resulting in an additional power increase from said internal combustion engine.

5,588,620
RADIAL-FORCE SPOILER SYSTEM
Raymond D. Gilbert, 6501 Inwood Dr., Springfield, Va. 22150
Continuation-in-part of Ser. No. 935,284, Aug. 26, 1992, Pat. No. 5,445,346, and Ser. No. 158,749, Nov. 26, 1993, Pat. No. 5,458,304. This application Dec. 1, 1994, Ser. No. 296,668
Int. Cl.⁶ G05D 1/08; B64C 5/10; 9/00
U.S. Cl. 244—90 A

14 Claims



1. In an aircraft comprised of a fuselage, wing, engine, autopilot and electric power supply, a stress reduction apparatus further comprising:


segmented spoiler apparatus,
mounted at the front of the engine,
sensor means, and
stress-limiting computer means;
wherein segmented spoiler means are located in concave arcs along a line parallel to an air entry mouth of the jet engine, and
wherein sensor means generate data that is processed by the stress-limiting computer means to actuate segmented spoilers with amplitude and timing sufficient to minimize accumulated stress within aircraft structures.

5,588,621
UNIVERSAL MOUNTING APPARATUS AND METHOD FOR BAR CODE SCANNERS
Donald A. Collins, Jr., Duluth, and Rex A. Aleshire, Buford, both of Ga., assignors to AT&T Global Information Solutions Company, Dayton, Ohio
Filed Feb. 23, 1995, Ser. No. 392,581
Int. Cl.⁶ G12B 9/00

4 Claims

1. A mounting apparatus for a replacement bar code scanner comprising:

a cover plate having a size large enough to cover an aperture in a checkout counter created for a removed bar code scanner which is larger than the replacement bar code scanner, wherein the cover plate also has a bottom surface; and
a support member which fastens to the bottom surface of the cover plate and which suspends the replacement bar code scanner from the bottom surface of the cover plate within the




aperture, including a box-like enclosure, including a base portion containing the replacement bar code scanner and a lid portion which fastens to the base portion and to the bottom surface of the cover plate.

5,588,622 BAG HOLDER

M. Brian Gordon, Sr., 403 N. Main St., P.O. Box 392, Columbiana, Ala. 35051-0392
Filed Jan. 17, 1995, Ser. No. 373,393
Int. Cl.⁶ B65B 67/04
U.S. Cl. 248—101

17 Claims



1. A one piece bag holder device, comprising:
a closed inner ring having a handle portion attached to a periphery thereof;
an open outer ring attached to said closed inner ring at a hinge portion which is adjacent to said handle portion on a first side of said handle portion;
locking means for engaging a second end of said open outer ring on a second side of said handle portion opposite said first side; and
a socket portion for receiving a handle;
wherein said open outer ring is adapted to be wrapped around a periphery of said closed inner ring in order to secure a bag therebetween and is locked in place by said locking means;
wherein said bag holder device is made of one piece of plastic; and
wherein said locking means includes an outer ring locking member disposed on an end of said open outer ring, and a base locking member, wherein said base locking member and


said outer ring locking member engage with each other to firmly secure said open outer ring around the periphery of said closed inner ring.

5,588,623

STERILIZATION SYSTEM

Steven Leduc, 10807 E. Harvard Dr., Aurora, Colo. 80014
Division of Ser. No. 104,981, Aug. 10, 1993, Pat. No. 5,364,602. This application Nov. 14, 1994, Ser. No. 338,689
Int. Cl.⁶ F16M 11/00
U.S. Cl. 248—164

3 Claims



1. A device for supporting medical or dental instruments to be sterilized in a sterilization chamber, said instruments having first and second ends, comprising:

an elongated frame with leg portions for supporting the frame on a flat surface, said frame having first and second X-shaped end members connected by elongated intermediate members, an instrument supporting member on said first end for engaging the first end of said instrument,

a second instrument supporting member at the second end of said frame, said second instrument supporting member and having opposed ends biased toward one another, and facing surfaces on said ends adapted to engage the second end of said instrument, said biasing force being sufficient to support said second end of said instrument.

said instrument engaging members being slidably movable along to said elongated members, whereby the space between the first and second instrument engaging members can be adjusted.


5,588,624

TABLE LEG EXTENSION

Annie R. Woodham, 297 Batiste Way, Jonesboro, Ga. 30236
Filed Apr. 5, 1995, Ser. No. 417,194
Int. Cl.⁶ F16M 11/24
U.S. Cl. 248—188.4

5 Claims

1. A table leg extension comprising:
a receiving tube adapted for receiving a leg of a table, the receiving tube being shaped so as to define an upper end spaced from lower end, with an arcuate aperture directed into the upper end thereof, the arcuate aperture permitting the upper end of the receiving tube to be bent over an integral bend of the leg of the table, the receiving tube is shaped so as to define internal threads extending about an internal surface thereof;
an abutment plate mounted within the receiving tube and adapted to engage a lower end of the leg so as to support the lower end of the leg in a spaced relationship relative to the lower end of the receiving tube, and the abutment plate is shaped so as to define external threads which are threadably engaged to the internal threads of the receiving tube so as to define an adjustment means, the adjustment means adjustably positioning the abutment plate relative to a ground surface;
an elastomeric foot secured to the lower end of the receiving tube for engaging a ground surface.



5,588,625


MONITOR STAND ASSEMBLY

Soon-ki Beak, Suwon, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-do, Rep. of Korea
Filed Aug. 16, 1995, Ser. No. 515,896
Claims priority, application Rep. of Korea, Aug. 16, 1994, 94-20087

U.S. Cl. 248—371

Int. Cl.⁶ A47G 29/00

4 Claims



1. A monitor stand assembly having an upper stand portion for seating a monitor thereon, a stand base portion supporting the upper stand portion, said assembly providing lateral rotation and vertical tilt movement for adjustability of a user's viewing position, the improvement comprising:

the upper stand portion having a horizontal locking aperture formed therein and having first and second guide ribs protrudently disposed in a diagonally opposed relation to one another and said locking aperture; and


the stand base portion having a coupler securely fixed in a vertical orientation in a substantially centered area for coupling to said locking aperture and thereby providing vertical tilt movement of the upper stand portion relative to the stand base portion, the stand base portion also including a first control rib located on one side of said coupler and a second control rib located diametrically across said coupler, said second control rib including an upwardly protrudent rib integrally formed on a movable resilient tab, said first and second control ribs configured to cooperate with said first and second guide ribs for controlling the rotational angle of the upper stand portion relative to the stand base portion in a lateral direction.

5,588,626

FLEXIBLY ADAPTABLE AND REMOVABLE CABLE WINDING AND COLLECTING APPARATUS

Dah-Rong Yang, Tao-Yuan, Taiwan, assignor to Delta Electronics, Inc., Taipei, Taiwan
Filed May 16, 1995, Ser. No. 442,315
Int. Cl.⁶ B65H 75/48
U.S. Cl. 242—378.1

8 Claims



1. A bi-level both-end wire collecting drum adaptable to a wire winding and collecting apparatus for engaging a rotation force asserting means for rotational winding and collecting a wire therein, said wire collecting drum comprising:

a bottom wire collecting means including a bottom spindle with a bottom wire collecting ridge disposed substantially in a central portion of said bottom spindle;

a top wire collecting means including a top spindle with a top wire collecting ridge disposed substantially in a central portion of said top spindle;

said top spindle including a tilted surface portion having a slightly tilted surface for constituting a wire adapting and removing opening extended axially from said center portion of said top spindle to an outer edge;

said top wire collecting ridge in said center portion of said top spindle constituting a partial top circular ridge having a top ridge opening disposed at said wire adapting and removing opening; and

said bottom wire collecting ridge in said center portion of said bottom spindle constituting a partial bottom circular ridge having a bottom ridge opening aligned with said wire adapting and removing opening wherein said bottom wire collecting ridge securely engaging said top wire collecting ridge constituting a hi-level transition portion for allowing said wire to smoothly pass from said bottom wire collecting ridge to said top wire collecting ridge for smooth and continuous winding and collecting said wire therein.

5,588,627


PAPER ROLLER

Norton Sharpe, Los Angeles, Calif., assignor to Franklin Brass Manufacturing Company, Rancho Dominguez, Calif.
Filed Sep. 19, 1995, Ser. No. 530,482
Int. Cl.⁶ B65H 75/02
U.S. Cl. 242—599

10 Claims

1. A paper roll support for use with a pair of supporting brackets having cylindrically-shaped cavities for receiving an end of the support, said support comprising:

a generally tubular unitary member independent from the brackets, wherein the tubular member comprises at least two flexible pleated portions and a cylindrical portion positioned between the pleated portions.




5,588,628
COLLAPSIBLE REEL

Harold G. Sachleben, 19 Adams Ave., Bellmawr, N.J. 08031
Filed Nov. 28, 1994, Ser. No. 348,985

Int. Cl.⁶ B65H 75/24; 75/22

U.S. Cl. 242—607.1


24 Claims



1. A collapsible reel comprising:
first and second flanges having respective facing inner surfaces;
a plurality of spaced members extending between, and being pivotally connected to, said inner surfaces to maintain said inner surfaces in mutually parallel planes, said members having respective longitudinal axes arranged parallel to one another, said members being connected to said first flange about respective pivot axes which extend parallel to said inner surface of said first flange, said plurality of members comprising at least one first member and at least one second member; and


an actuator member engaged with said at least one first member and movable between first and second positions for rotating said at least one first member about said longitudinal axis thereof between, respectively: (1) a first rotational position in which said pivot axis of said at least one first member is in nonparallel relationship with the corresponding pivot axis of said at least one second member, and (2) a second rotational position in which said pivot axis of said at least one first member is in parallel relationship with the corresponding pivot axes of the remaining members, thereby permitting collective pivotal movement of said members with respect to said flanges between a collapsed position when said second rotational position is obtained, at which said flanges are positioned substantially adjacent to one another, and an operative position at which said flanges are spaced such that the planes of said inner surfaces are perpendicular to said longitudinal axes of said members, said flanges being retained in said operative position when said actuator member is moved to said first position.

5,588,629
WALL ARTICLE HANGING DEVICE
Renny H. Barnes, 8146 Crestridge Rd., Fairfax Station, Va. 22039
Filed May 22, 1995, Ser. No. 445,698
Int. Cl.⁶ A47F 7/14
U.S. Cl. 248—475.1
19 Claims



1. A wall article hanging device for attaching an article to a wall surface comprising:
a) an elongated plate having an uppermost and a lower edge;
b) means extending outwardly from said plate for rigidly attaching said elongated plate to a rear surface of said article; and
c) at least a pair of spaced prongs integrally formed and extending outwardly from said elongated plate, each said prong having an upper and a lower planar face decreasing in width from said elongated plate to a terminating tip said tip being angled downwardly towards said lower edge such that each said lower planar face forms an acute angle with respect to a transverse section of said elongated plate, said prongs in opposing relationship with said means for rigid attachment and designed for penetration of and attachment to said wall wherein;
d) said elongated plate has spring qualities and has a bend from a center thereof towards each end, said spring qualities causing said elongated plate to flatten during attachment to said wall and spring back after said attachment to direct said prongs in a direction generally opposite said spring back.

5,588,630
ADJUSTABLE BASE TO HOLD FLAG BANNERS
Huang Chen-Chao, No. 20, Lane 124, Sec. 5, Hsin Hai Rd., Taipei, Taiwan
Filed Jan. 19, 1995, Ser. No. 374,826
Int. Cl.⁶ F16M 13/00
U.S. Cl. 248—514
2 Claims




1. An adjustable base for holding a pair of flag banner poles, comprising:

a base including (1) a ground plate having a plurality of mounting holes formed therethrough for securement to a base surface, and (2) a base table extending orthogonally from a central portion of said ground plate, said base table having a centrally disposed first screw hole formed therethrough and a plurality of radially disposed first cogwheel teeth formed on one side thereof;

a pole cylinder adjustably coupled to said base, said pole cylinder including (1) a longitudinally extended tubular cylinder having an open upper end for receiving a first of the pair of flag banner poles therein, said tubular cylinder having a threaded opening formed through a side wall thereof adjacent said open end, (2) a first bolt threadedly engaged with said threaded opening for securing the first of the pair of flag banner poles within said tubular cylinder, (3) a connecting table extending from a lower end of said tubular cylinder, said connecting table having a centrally disposed second screw hole formed therethrough and a plurality of radially disposed second cogwheel teeth formed on one side thereof, and (4) a pair of longitudinally spaced loops formed on an external surface of said tubular cylinder for receiving a second of the pair of flag banner poles therein; and,
means for releasably coupling said connection table to said base table, said releasable coupling means including a second bolt extending through said first and second screw holes with said first cogwheel teeth facing said second cogwheel teeth and a nut threadedly engaged on said second bolt, wherein said tubular cylinder is angularly adjusted by rotation of said connection table relative to said base table and fixed thereat by tightening said nut on said second bolt.

5,588,631
LOCKING ARTICLE ANCHORING ASSEMBLY FOR TRUCK BEDS
William J. Yee, 4361 Keystone Ave., Culver City, Calif. 90232
Filed May 2, 1994, Ser. No. 236,171
Int. Cl.⁶ A47F 7/00
U.S. Cl. 248—553
11 Claims




1. An assembly for anchoring articles such as storage boxes for tools to a structure, said assembly comprising:
a. a longitudinally elongated hollow beam member having a hollow interior space, said beam member having means for fastening said beam member to a structure and having a wall provided therethrough with at least a first perforation,
b. at least one article locking member fastenable to an article to be anchored, said locking member including an elongated portion having a smaller transverse section than said perforation and insertable therethrough, said elongated portion having proximate an outer transverse end thereof engagement means for lockable engagement to prevent removal of said elongated portion from said perforation,
c. a locking bar within said hollow interior space of said beam, said locking bar having therethrough a first cutout section alignable with and non-obstructing of said perforation through said wall of said beam with said locking bar in a first

unlocked position permitting insertion of said elongated locking member through said perforation, said locking bar being slidable to a locking position in which portions of said locking bar obstruct a portion of said perforation, said obstructing portion of said locking bar lockingly engaging said lockable engagement means of said locking member protruding through said perforation, said locking bar being of sufficiently less longitudinal extent than said hollow beam member to permit said locking bar to be slid between said locking and unlocked positions without protruding from either end of said hollow beam member, said locking bar including an elongated plate section parallel and proximate to the inner surface of said perforated wall of said beam, said plate section having a second cutout section alignable with said perforation through said beam wall with said locking bar slid to a second unlocked position longitudinally spaced apart from said first unlocked position, and an elongated base section angled away from said plate section.

d. means for longitudinally slidably supporting said base section of said locking bar, and

e. slidable operating means located longitudinally between opposite transverse ends of said hollow beam for slidably moving said locking bar between said locking and unlocked positions.

5,588,632
DYNAMIC SUPPORT STRUCTURE
Peter R. Solomon, West Hartford, Conn., assignor to Advanced Fuel Research, Inc., East Hartford, Conn.
Continuation of Ser. No. 308,153, Sep. 19, 1994, abandoned, which is a division of Ser. No. 837,622, Jan. 19, 1992, Pat. No. 5,349,438, which is a continuation-in-part of Ser. No. 773,225, Oct. 19, 1991, Pat. No. 5,196,902. This application Dec. 4, 1995, Ser. No. 567,085
Int. Cl.⁶ G01B 9/02
U.S. Cl. 248—560
4 Claims



1. Dynamic support structure, comprising a multiplicity of rigid members including a pair of opposing side members and a pair of opposing end members, said members being flexibly interconnected so as to provide a frame and to permit conjoint displacement of said side members in opposite directions along parallel axes of shifting, with said end members rotating in the same direction about pivot points, said structure comprising at least two planar pieces of similar configuration affixed in substantiality coextensive, superposed relationship and cooperatively providing at least one contiguous pair of said members consisting of a side member and an end member, and providing a flexible joint between said members of said contiguous pair, each of said planar pieces being of integrally formed, unitary construction and including first and second elongate elements having longitudinal axes and contiguous end portions, and a flexible web element joining said contiguous end portions and extending therebetween on an oblique axis to both of said longitudinal axes when said longitudinal axes are mutually perpendicular, said first elements of said two pieces together providing said side member of said contiguous pair, said second elements of said two pieces together providing said end member of said contiguous pair, and said web elements of

said two pieces together providing said flexible joint therebetween, said oblique axes crossing one another and thereby causing said web elements to constrain said member of said contiguous pair to relative movement about a single axis of flexure, disposed at the intersection of said oblique axes.

5,588,633

MOUNTING BRACKET

Alan I. McCrerie, Preston, Great Britain, assignor to Winch & Engineering Limited, Lancashire, Great Britain
PCT No. PCT/GB93/00077, § 371 Date Sep. 7, 1994, § 102(e)
Date Sep. 7, 1994, PCT Pub. No. WO93/14015, PCT Pub.
Date Jul. 22, 1993


PCT Filed Jan. 14, 1993, Ser. No. 256,546

Claims priority, application United Kingdom, Oct. 20, 1992,
9222015; Jan. 14, 1993, 9201015

Int. Cl.⁶ B66D 1/00; B60F 1/00

U.S. Cl. 248-647

8 Claims



1. A mounting bracket, comprising:

a base plate; and
attachment means for loosely attaching the mounting bracket to a vehicle's ball hitch so that the mounting bracket may move relative to the ball hitch, said attachment means being in a form of a first housing, which is secured to the base plate and has a lower end defining an opening, and a second housing which is located within the first housing and is capable of sliding upwardly and downwardly relative thereto, said second housing providing a socket for fitting over a ball member of the ball hitch, and the weight of the mounting bracket acting under gravity to slide said first housing downwards over said second housing to a position where said first housing serves to retain the ball member within said socket.

5,588,634

FLUID FLOW CONTROL DEVICE PINCH MECHANISM


William S. Nettekoven, Sandy, Utah, assignor to MegaDyne Medical Products, Inc., Draper, Utah

Filed Dec. 11, 1995, Ser. No. 570,641

Int. Cl.⁶ F16K 7/06

U.S. Cl. 251-9

16 Claims



1. An improved flow control pinch mechanism comprising in combination:

(a) a first fluid-conducting tubular member having an internal fluid conducting channel, said member having a resilient region capable of resilient deformation to controllably occlude said fluid conducting channel to control fluid flow therethrough;

(b) a trumpet-type fluid control actuator having a spring-loaded piston;

(c) a cam assembly for imparting fluid control force to said resilient region of said fluid conducting channel, said cam assembly comprising:

(i) a cam having a principal camming surface,

(ii) a cam follower engaging said cam and having a non-rectilinear principal axis with first and second ends lying at ends of said non-rectilinear principal axis, said cam follower having at said first end a pivot support for positioning said first end; and

means including said trumpet-type fluid control actuator effective when said trumpet-type fluid control actuator is depressed for correspondingly causing relative movement between said cam and said cam follower to correspondingly cause said cam follower to pivot about said pivot support and correspondingly reduce said fluid control force.

5,588,635

LIQUID FLOW VELOCITY DIFFUSER



Thomas A. Hartman, 700 Capac Ct., St. Louis, Mo. 63125

Filed Aug. 26, 1994, Ser. No. 296,949

Int. Cl.⁶ F16K 47/14; F15D 1/06

U.S. Cl. 251-127

19 Claims



1. An apparatus for diffusing velocity of liquid flowing in a conduit, the apparatus comprising:

at least one wall positioned inside the conduit for directing the liquid flowing through the conduit radially outwardly toward an inner peripheral surface of the conduit creating an annular layer of liquid flow adjacent to the inner peripheral surface of the conduit;

said at least one wall having a peripheral end and an opposite interior end, the peripheral end of the wall being secured to the conduit with the wall positioned inside the conduit projecting toward a center axis of the conduit as the wall extends from its peripheral end toward its interior end.

5,588,636

WATER FIXTURE CONTROL SYSTEM

Heinz-Dieter Eichholz, Iserlohn, and Hans-Peter Rudrich, Windischeschenbach, both of Germany, assignors to Friedrich Grohe Aktiengesellschaft, Hemer, Germany


Filed Jun. 8, 1995, Ser. No. 488,629

Claims priority, application Germany, Jun. 10, 1994, 44 20 334.9

Int. Cl.⁶ F16K 31/02

U.S. Cl. 251-129.04

14 Claims




1. A water-control device comprising:

an electrically controllable valve for dispensing water in a sanitary fixture;

a control circuit operatively connected to said valve and provided with a proximity detector for operating said valve in response to proximity of a user of said fixture and with system parameters and operating parameters including flow duration and operating range of said proximity detector;

a voltage source connected to said control circuit; means in wireless communication with said control circuit for contactless setting of at least one of said system and operating parameters in said control circuit; and

at least one nonvolatile memory connected to said control circuit for storing said system and operating parameters independently of failure of said voltage source whereby operation of said control circuit with said system and operating parameters is automatically restored by said nonvolatile memory upon restoration of said voltage source to said control circuit.



a value of the control signal that is indicative of a measured current value that is greater than a predetermined current value, and wherein the switching mechanism opens to disconnect the motor from the power supply in response to the second value of the switching signal.

5,588,638

BALL VALVE


Bryce T. Bunting, 1900 Country Club Rd., Statesboro, Ga. 30458, and Lalan W. Cook, 5957 St. Lukes Church Rd., Prosperity, S.C. 29127

Filed Sep. 5, 1995, Ser. No. 523,690

Int. Cl.⁶ F16K 5/06

U.S. Cl. 251-315.05

3 Claims



1. A ball valve for controlling fluid flow, said ball valve having an open position that allows the fluid to flow through said ball valve and a closed position that prevents fluid from flowing through said ball valve, said ball valve comprising:

a housing having an inside surface, and an upstream channel and a downstream channel, said upstream channel having a size and shape;

a ball element dimensioned to fit inside said housing so that said ball element can rotate within said housing, said ball element having an exterior surface,

a first port, a second port forming a fluid conduit through said ball element with said first port, and a third port intersecting said fluid conduit,

said ball valve being in the open position when said first and said second ports of said ball element are aligned with said upstream and downstream channels and being in the closed position when said third port is aligned with said upstream channel and said first and second ports are not aligned with said upstream and downstream channels.

5,588,637

AUXILIARY AUTOMATIC VALVE SHUT-OFF SYSTEM

Robert L. Carsten, 1098 Redding, Costa Mesa, Calif. 92626, and Bernard E. Wilberger, Orange, Calif., assignors to Robert L. Carsten, Costa Mesa, Calif.

Filed May 30, 1995, Ser. No. 453,643

Int. Cl.⁶ F16K 31/02

U.S. Cl. 251-129.03

42 Claims

1. A system for automatically actuating a valve in response to an actuation signal, comprising:

a first device that generates an actuation signal; a second device that generates a switching signal having a first value in response to the actuation signal; an electric motor operatively coupled to the valve;

an electrical power supply; a switching mechanism that closes to connect the motor to the power supply in response to the first value of the switching signal; and

a third device that generates a control signal having a value that is proportional to the measured value of the current drawn by the motor from the power supply through the switching mechanism when the switching mechanism is closed; wherein the second device receives the control signal and generates a switching signal having a second value in response to

said third port being dimensioned to be no smaller than the upstream channel so that, when said ball valve is in said closed position, said ball element provides no portion of its exterior surface on which seal from said fluid can build up to affect the rotation of said ball element, wherein said exterior surface of said ball element is impregnated with a fluoropolymer; and

a fluoropolymer jacket carried by said inside surface of said housing to match said exterior surface of said ball element to facilitate rotation of said ball element within said housing.

5,588,639

ONE MAN LIFT FOR MOTORCYCLES


John A. Holman, 10424 S. Church St., Chicago, Ill. 60643

Filed Apr. 6, 1995, Ser. No. 417,819

Int. Cl.⁶ B66F 3/00

U.S. Cl. 254—133 R

8 Claims



1. A support structure for lifting a motorcycle in combination with a jack, said support structure comprising a cylindrical cradle adapted to fit over an elevatable portion of the jack and having a tubular member extending across said cylindrical cradle positioned above the bottom of said cylindrical cradle to provide a rocking or tilting motion of said cradle with respect to the elevatable portion, said cylindrical cradle has a pair of longitudinally extending tubular support members connected to the top of said cylindrical cradle at the periphery thereof, said cylindrical cradle having a shiftable fit with respect to said elevatable portion of the jack to permit tilting of said support members supporting the motorcycle providing access to either the front or rear wheel of the motorcycle.

5,588,640

AIR-SPRING LEG WITH A PRESSURE CHAMBER FOR MOTOR VEHICLES

Matthias Römer, Weinstadt, Germany, assignor to Mercedes-Benz AG, Stuttgart, Germany


Filed Oct. 17, 1995, Ser. No. 544,005

Claims priority, application Germany, Oct. 26, 1994, 44 38 192.1

Int. Cl.⁶ F16F 9/02; F16K 17/04; B60G 11/27; 17/04

U.S. Cl. 267—64.11

13 Claims



1. Air-spring leg of a spring bellows-type with a pressure chamber, having an interior and an exterior, for motor vehicles, in which the pressure chamber can be subjected to different pressures via a connector, arranged in a wall of the pressure chamber, leading to the exterior, wherein an automatically operating pressure relief valve is provided in the connector for maintaining a minimum pressure which can be predetermined for the pressure chamber; wherein said pressure relief valve opens at a pressure which is acting from the interior of the pressure chamber or from the exterior and is above the minimum pressure and closes at a pressure below the minimum pressure; and wherein the flow path leading through the connector passes through a connection space which is located within the pressure relief valve, and wherein an elastomer is movably arranged in the pressure relief valve dependent on the pressure in the connection space, to prevent a throughflow of the connection space at a pressure prevailing there below the minimum pressure and to permit such throughflow at a pressure above the minimum pressure, the elastomer being pre-stressed to achieve flow prevention.

5,588,641

GAS SPRING WHICH AFTER COMPRESSION HAS A TIME DELAYED RETURN TO ITS ORIGINAL LENGTH


Gunnar Sand, Huskvarna, Sweden, assignor to Stromsholmens Mekaniska Verkstad AB, Sweden

Continuation-in-part of Ser. No. 119,206, Nov. 26, 1993, Pat. No. 5,435,530. This application Jun. 6, 1995, Ser. No. 471,978

Int. Cl.⁶ F16F 5/00

U.S. Cl. 267—119

5 Claims



1. An apparatus for a gas spring, comprising: a first cylinder closed at both ends by first and second end walls; a first piston capable of axial displacement being disposed inside a fluid-filled inner space of the first cylinder, the first piston dividing the cylinder into first and second sub-spaces, the first sub-space is bounded by the first end wall, the first piston, and a first interjacent part of two side walls of the first cylinder, the second sub-space is bounded by the second end wall, the first piston, and a second interjacent part of the two side walls of the first cylinder; a first piston rod, connected to the piston, being mounted in a sliding and sealing fashion in the second end wall; a second cylinder closed at both ends by third and fourth end walls; a second piston being disposed inside a fluid-filled inner space of the second cylinder capable of axial displacement therein, the second piston dividing the second cylinder into first and second cylindrical chambers, the first cylindrical chamber is bounded by the third end wall, the second piston, and a third interjacent part of two side walls of the second cylinder, the second cylindrical chamber is bounded by the fourth end wall, the second piston, and a fourth interjacent part of the two side walls of the second cylinder; a second piston rod, connected to the second piston, being mounted in a sliding and sealing fashion in the fourth end wall; the first and second piston rods being forced downwards by a force to increase pressure inside the first cylindrical chamber

and the first sub-space and to decrease pressure inside the second cylindrical chamber and the second sub-space; valve means for selectively communicating among the first and second sub-spaces and first and second cylindrical chambers to decrease pressure inside the first sub-space so as to cause the first piston to be locked for a predetermined period of time, and for causing the first and second pistons to move upwards and back to an initial position of each of the first and second pistons after a predetermined delay; wherein the valve means includes a plurality of openable and closable valves which are controlled by a control device; and wherein the plurality of the valves include first, second, and third valves, the first sub-space communicates with the second sub-space via the first valve, the second sub-space communicates with the first cylindrical chamber via the second valve, and the first sub-space communicates with an enclosed space, which is bounded by the first end wall, a fifth end wall, and extension walls of the two side walls of the first cylinder, via the third valve.

5,588,642

CLAMPING APPARATUS

Keitaro Yonezawa, Kobe, Japan, assignor to Kabushiki Kaisha Kosmek, Japan

Continuation of Ser. No. 331,101, Oct. 28, 1994, abandoned.


This application May 15, 1996, Ser. No. 648,291

Claims priority, application Japan, Nov. 5, 1993, 5-275844

Int. Cl.⁶ B25B 1/00

U.S. Cl. 209—244

20 Claims



1. A clamping apparatus comprising: a housing; a first threaded member having a first, longitudinally extending axis; means for supporting said first threaded member within said housing for rotation about said first axis while restricting longitudinal movement of said first threaded member relative to said housing; a second threaded member having a second, longitudinally extending axis, an outer periphery and an associated longitudinal length, said second threaded member being threadably engaged with said first threaded member for movement through a longitudinal clamping stroke with the outer periphery and the entire said associated longitudinal length of said second threaded member being substantially entirely surrounded and guidably supported throughout said longitudinal clamping stroke by said housing for relative longitudinal movement; means, interconnected between said second threaded member and said housing, for permitting said second threaded member to move longitudinally along said second axis while restricting rotational movement of said second threaded member about said second axis; an impact wrench mounted to said housing and connected to said first threaded member for rotating said first threaded member about said first axis; and

a clamping member movable between a clamping position and an unclamping position, said clamping member having an input portion connected to said second threaded member.

5,588,643

METHOD AND DEVICE FOR WITHDRAWING FLAT FOLDED CARTON BLANKS FROM A MAGAZINE AND FOR FEEDING THEM TO A CARTON SET UP LINE

Roberto Tagliaferri, Castel S. Pietro, and Rodolfo Caroli, Imola, both of Italy, assignors to I.M.A. Industria Macchine Automatiche S.p.A., Ozzano Emilia, Italy


Filed Feb. 6, 1995, Ser. No. 383,634

Claims priority, application Italy, Feb. 8, 1994, BO94A0049

Int. Cl.⁶ B65H 3/04

U.S. Cl. 271—35

14 Claims



1. A device for withdrawing flat folded carton blanks from a magazine where said carton blanks are stored in a flat folded condition to form a stack, and for feeding said carton blanks to a feeding line, said device comprising: supporting bars located under said magazine for supporting said stack of flat folded tubular carton blanks; stop means located downstream of said magazine and over said supporting bars, said stop means cooperating with said supporting bars to delimit an opening having a height equal to a thickness of a folded carton blank; and belt conveyor means situated under said magazine and featuring a plurality of lugs regularly spaced apart and protruding upwardly beyond said supporting bars, said lugs engaging a rear edge of a lowermost carton blank of said stack for stripping said lowermost blank and conducting said lowermost blank through said opening delimited by said supporting bars and said stop means situated thereabove; said magazine including front vertical guides and rear vertical guides, with reference to advancement movements of said belt conveyor means, with at least said front vertical guides supported by a carriage that is slidably supported by a frame forming part of said magazine, and that is moved by rack means, so that said front vertical guides can be moved to adjust longitudinal dimensions of said magazine.

5,588,644

INTERLEAVING APPARATUS FOR ROLLED UP SEGMENTS

Ronald L. Lotto, Bonduel; Ernest H. Teske, Green Bay, and Peter Hatchell, New Franken, all of Wis., assignors to FMC Corporation, Chicago, Ill.


Continuation of Ser. No. 409,484, Mar. 21, 1995, which is a continuation of Ser. No. 889,230, May 27, 1992, abandoned, which is a continuation of Ser. No. 651,676, Feb. 6, 1991, Pat. No. 5,161,793. This application Dec. 4, 1995, Ser. No. 566,796

Int. Cl.⁶ B65H 29/68

U.S. Cl. 271—183

2 Claims

1. A method for overlapping individual plastic webs of material comprising the steps of:



feeding a continuous sheet of plastic film having perforations thereon in between a pair of feed rolls driven at a first speed, said perforations defining individual plastic webs to be formed;
separating a leading individual plastic web and a trailing individual plastic web at a perforation between said webs;
interleaving said individual leading and trailing plastic webs;
providing said interleaved webs to a pair of driving rolls driven at a speed slower than said first speed, and
providing said interleaved webs to a winder, said winder being downstream from said driving rolls.

5,588,645


BASEBALL PITCHING APPARATUS

Fred W. Schwan, Cary, and William C. Francis, McHenry, both of Ill., assignors to Commercial Concepts, Inc., Cary, Ill.

Filed Jul. 24, 1995, Ser. No. 506,089
Int. Cl.⁶ A63B 69/40

U.S. Cl. 473-456

6 Claims



1. A baseball pitching apparatus comprising:

a frame defining at least three, different generally rectangular planes, a first plane formed by a pair of mirror image tubular base members that are parallel, horizontal and spaced a predetermined distance apart from one another and each having a front and rear end, each base member having two upwardly extensions that taper at their ends, one extension is angled approximately 90° from the horizontal length of the base member and the other extension is angled toward the front end of the base at an angle less than a 90° angle, a first pair of U-shaped cross bar members having tapered leg ends inserted into the front and rear ends of the base members, a second plane formed by a first pair of upright member having lower and upper ends, said lower ends inserted over the tapered ends of the angled extension and having a U-shaped cross bar member having tapered leg ends inserted into the upper ends of said pair of upright members, a third plane formed by a

second pair of uprights having lower and upper ends, said lower ends inserted over the tapered ends of the vertical extensions and having a U-shaped cross bar member having tapered leg ends inserted into the upper ends of said second pair of upright members; and

a tarp of a generally rectangular shape having means for attaching it to the front cross bar member, the angled upright cross bar member and the vertical upright cross bar member so that the tarp drapes between the front and angled cross bar members to form a channel for catching errant pitches and drapes between the angled and vertical cross bar members having means attached to the tarp hanging down from the vertical upright cross bar to form a baffle between the drape over the angled and vertical cross bars, said tarp having a target opening through the drape over the angled upright cross bar so that a baseball maybe thrown through the target opening to be stopped by the rear drape over the vertical cross bar and then drop to the baffle therebetween for later retrieval.

5,588,646

TETHERED BALL BATTING PRACTICE DEVICE


John W. Dickson, 16131 Fifth St., Lathrop, Calif. 95330

Filed Aug. 1, 1995, Ser. No. 521,391

Int. Cl.⁶ A63B 69/40

U.S. Cl. 473-426

17 Claims



1. A batting practice device consisting of:

a horizontal frame base having an intersection formed by a leg member and arm members interconnected in the shape of a "T";

a vertical member affixed to the intersection of said horizontal "T";

a horizontal member centered and affixed to the top of said vertical member to form arms of a vertical "T" that parallel arms of said horizontal "T";

a flexible means forming a ball suspension system containing a target ball with first and second ends secured to ends of the arms of said vertical "T", a third end secured to an end of the leg member of said horizontal "T" to form a "Y" shape configuration angled at a degree relative to the ground, a fourth end secured to the intersection of said horizontal and vertical "T"s to stop return velocity of the ball target after being hit, and

said flexible means of said ball suspension system intersects with and is secured to said ball target to facilitate suspension of said ball target therein.

5,588,647

METHOD OF PLAYING A FOOTBALL GAME


Elliot Rudell, 1619 Gramercy Ave., Torrance, Calif. 90501, and George Foster, Signal Hill, Calif., assignors to Elliot Rudell, Torrance, Calif.

Division of Ser. No. 82,491, Jun. 28, 1993, Pat. No. 5,467,981, which is a continuation-in-part of Ser. No. 873,727, Apr. 27, 1992, Pat. No. 5,228,690. This application Aug. 24, 1995, Ser. No. 519,140

Int. Cl.⁶ A63B 67/00

U.S. Cl. 473-470

3 Claims



1. A method for playing a football game, between a plurality of first players and a plurality of second players comprising the steps of:

- initiating a play wherein one of the first players holds a football that has a detachable tail;
- running toward a goal by the first player with said football;
- pursuing the first player with said football by at least one second player;
- detaching said tail from said football by a second player, wherein said detachment of said tail is indicative of a tackle and termination of the play; and
- repeating steps (a)-(d) until a first player with said football crosses the goal and scores.

5,588,648

TRAINING BALL FOR BASEBALL AND SOFTBALL BATTING PRACTICE


Scott Stebbins, 8606 31st St. W., Tacoma, Wash. 98466

Filed May 22, 1995, Ser. No. 445,795

Int. Cl.⁶ A63B 37/06

U.S. Cl. 473-451

18 Claims



1. A weighted training ball for baseball batting training, comprising:

- a substantially spherical, solid body of molded elastomeric material, wherein the body has a circumference of approximately 9 inches, a weight of between approximately 7.5-10 ounces, an average density of the elastomeric material forming the body of between approximately 0.0214-0.05885 pounds per cubic inch, and a type A-2 Shore durometer at a surface of the body of between approximately 40-70.

5,588,649

MULTI TOKEN GAMING METHOD

Barry B. Blumberg, Yardley, Pa.; James M. Pecka, Mt. Laurel, N.J., and Bruce S. Allen, Feasterville, Pa., assignors to CompuScan Technologies, Inc., Delran, N.J.


Continuation of Ser. No. 238,237, May 4, 1994, abandoned.

This application Dec. 8, 1995, Ser. No. 569,318

Int. Cl.⁶ A63F 9/24

U.S. Cl. 463-18

43 Claims



1. A promotional gaming method for enticing a patron to purchase at least two products that are being promoted by an establishment using an electronic promotional system, the products including a good or a service, the method comprising the steps of: distributing a plurality of tokens to a patron of the establishment, each of said plurality of tokens being associated with a product and including a machine readable code; presenting by the patron at least two of said plurality of tokens at a code reading location in the electronic promotional system; reading said machine readable codes on said at least two tokens presented by said patron at said code reading location by said electronic promotional system to thereby provide a group of inputs;

determining by said electronic promotional system if said group of inputs for each patron includes a set of inputs matching a preselected set of actuating codes, said preselected set of actuating codes corresponding to one or more products which are being promoted by the establishment; and actuating a random selection process if said set of inputs matches said predetermined set of actuating codes so as to randomly award prizes only to patrons who have presented tokens with machine readable codes that match said predetermined set of actuating codes, whereby a patron who purchases at least two products which are being promoted is rewarded with an opportunity to win a prize.

5,588,650

AUTOMATED INTERACTIVE ROULETTE WITH PROGRESSIVE JACKPOT


Richard G. Eman, Wilhelminastraat 24, and Luis E. Mansur, Bachstraat 5, both of Oranjestad, Aruba

Filed Jul. 19, 1995, Ser. No. 504,236

Int. Cl.⁶ A63F 5/00

U.S. Cl. 273-142 B

15 Claims



1. An automated roulette device having an annular ball track and a centrally disposed rotatable wheel with a plurality of ball receptor zones about a periphery thereof, and a ball adapted for travel about the ball track and subsequent receipt, by chance, within any of said ball receptor zones to determine a winning outcome of each spin of the roulette wheel, said device comprising:

wheel control means for controlling actuation and a speed of rotation of the roulette wheel, said wheel control means being structured to allow the roulette wheel to slow after actuating rotation thereof, until said roulette wheel comes to a rest, a ball launching mechanism for launching the ball into the ball track after actuation of rotation of said roulette wheel, detection means for continuously monitoring and visually indicating the location of the ball relative to each of the ball receptor zones as the ball travels about the ball track until coming to rest within one of the ball receptor zones,

a processor interconnected to the roulette wheel, said wheel control means, said ball launching mechanism and said detection means for operating said wheel control means and receiving input from said detection means and determining the winning outcome of each spin of the roulette wheel,

play display means interconnected with said processor for visually indicating the winning outcome of each spin of the roulette wheel,

at least one player console interconnected to said processor for entering wagers on the winning outcome of each spin of the roulette wheel and comprising:

cash input means for reception of money therein, and translation thereof by said processor into units of wagering credit, credit display means for displaying current wagering credit available for entering wagers,


bet input means for inputting said wagers to be received by said processor,

bet display means for displaying said input wagers,

ball launch control means for allowing player control of time of release of the ball by said ball launching mechanism into said annular ball track and for further allowing player control of the velocity of the ball at its release by said ball launching mechanism,

cash-out means for terminating player participation and printing credit receipts to indicate a remaining amount of said current wagering credit available at the time of termination of play, and

said processor being structured to compare said input wagers with said winning outcome to determine an amount of wagering credit units to add or subtract from said current wagering credit available.



having several separate sensitive areas and several separate trough areas, the hand pivoting at the transverse crease during the squeezing of said handle such that the tough ball, heel and thumb base move in a direction toward said handle during the squeezing, a hand accessory to be positioned between said handle and the hand, said hand accessory comprising:

a plug having primarily a slightly arcuate front surface to engage with said handle, said plug having a back surface which is to press against the hand, said back surface of said plug having a plurality of curved surfaces and concave areas to engage the sensitive areas and to allow movement of said pivoting;

ridges and protrusions to engage the tough, fleshy areas serving to maintain position of said plug within the hand and resisting the inertial movement of said handle toward the web, a glove worn over the hand presses certain areas of said plug against the hand, said plug being bendable to permit deflection of said front surface during said pivoting of the hand so that said front surface closely conforms to said handle during the squeezing, whereby said plug facilitates the transmission of a manual swinging force between the hand and said handle; and said plug includes a locking recess, a portion of the index finger to fit within said locking recess, whereby said locking recess functions to locate the position of said plug within the hand such that force is transmitted through the fingers of the hand.

5,588,652

GOLF RANGE GAME

John Lang, P.O. Box 3426, Scenic Caves Road, R.R. #3, Collingwood, Ontario, Canada

Filed Sep. 18, 1995, Ser. No. 529,770

Int. Cl.⁶ A63B 67/02; 69/36

U.S. Cl. 473-168

19 Claims

1. A facility for playing a game with a golf club and golf balls, the facility comprising:

a site having a range area visibly divided into a plurality of contiguous target regions, each said target region being associated with a target identifier, and a tee area having a plurality of contiguous tees from which golf balls may be hit toward said range area;

scoring means located at said site for scoring a game, said scoring means setting out a sequence of said target identifiers so as to establish a corresponding sequence of designated target regions to which golf balls are to be hit from the tee with a golf club in order, and said scoring means providing means for recording a point score for each time a player hits a golf ball; and

a scoring system associated with said scoring means for awarding a point score according to the observed resting position of the golf ball relative to the designated target region.

5,588,651

HAND ACCESSORY FOR SWINGING AN IMPLEMENT HANDLE

John H. Frost, 6900 Canby Ave.-#110, Reseda, Calif. 91335


Continuation-in-part of Ser. No. 262,242, Jun. 20, 1994, abandoned. This application Oct. 5, 1995, Ser. No. 539,215

Int. Cl.⁶ A63B 57/00

U.S. Cl. 473-206

30 Claims

1. In combination with the handle of an implement when said handle is to be manually swung in motion by the hand of a human with the hand gripping and squeezing said handle, the hand having a concave palm from which extend a thumb and fingers, the fingers named from the inside of the hand nearest the thumb being the index finger, the middle finger, the ring finger and the little finger, the hand having a plurality of tough fleshy areas, the hand having a plurality of sensitive areas, the hand having a web located between the base of the thumb and the index finger, the concave palm including a lifeline crease which in part contours the thumb base, the concave palm bordered by a transverse crease located directly adjacent and below the knuckles of the fingers, the concave palm bordered on the outside by a tough ball directly adjacent and below the little finger and bordered by a sensitive heel located below the tough ball directly adjacent the concave palm and a tougher heel located below the sensitive heel, the concave palm



5,588,653

GOLF SWING PRACTICE DEVICE

Gary G. Robinson, R. R. #4, Komoka, Ontario, Canada


Filed Oct. 17, 1995, Ser. No. 543,893

Claims priority, application Canada, Oct. 6, 1995, 2160059

Int. Cl.⁶ A63B 69/36

U.S. Cl. 473-218

22 Claims



1. A device for use in combination with golf clubs to assist golfers in practicing appropriate aspects of a golf swing, said device comprising:

a plate having two opposed faces;

first connector means for detachable connection with a shaft of a first golf club on one face of said plate; and

second connector means for detachable connection with a shaft of a second golf club on the opposed face of said plate, said first connector means and said second connector means each having respective axes, the axis of said second connector means being oriented so that it is at a predetermined angle to the axis of said first connector means.

5,588,654

GAME PLAYING APPARATUS

Carl E. Voigt, IV, Indianapolis, Ind., and Cheung K. Chow, Shatin, Hong Kong, assignors to Third Quarter Corporation, Indianapolis, Ind.

Filed Feb. 9, 1995, Ser. No. 386,291


Int. Cl.⁶ A63F 3/00

U.S. Cl. 273-284

7 Claims

1. A game playing apparatus, comprising:

a housing having an opening therein;



first and second spindles rotatably engaged with the housing and positioned on opposite sides of the opening;

an elongate sheet having first and second ends, the first end being attached to the first spindle and the second end being attached to the second spindle, wherein the elongate sheet has a plurality of game playing surfaces marked thereon, such that rotation of one of the first and second spindles is operative to align a selected one of the game playing surfaces with the opening; and

a die-throwing device coupled to the housing and including a die, the die-throwing device including an actuator operable to cause the die to randomly display a die face in response to activation of the actuator.

5,588,655

VOLLEYBALL TRAINING DEVICE


Leontiy Slupsky, 240 Mt. Vernon Pl., #4D, Newark, N.J. 07106

Filed Nov. 6, 1995, Ser. No. 554,354

Int. Cl.⁶ A63B 69/00


U.S. Cl. 473-429

4 Claims




1. A volleyball training device, comprising a bracket: a turnable support mounted on said bracket turnably about its axis; at least one ball; a ball holder which holds said ball and is connected with said turnable support so as to turn together with the latter, said ball holder being formed as a substantially curved element extending in a plane substantially perpendicular to said axis, so that when an attacking strike is delivered by a player against said ball, said ball together with said ball holder and said support is turned about said axis in said plane; and means for counting a number of strikes against the ball, said counting means being connected with said turnable support.

5,588,656
CRANKSHAFT SEAL HAVING RESILIENT PORTION EMBEDDED IN RIGID RETAINER
 Noboru Matsushima, Fukushima, Japan, assignor to NOK Corporation, Tokyo, Japan
 Filed Feb. 3, 1995, Ser. No. 383,489
 Claims priority, application Japan, Feb. 7, 1994, 6-035319
 Int. Cl.⁶ F16J 15/32
 U.S. Cl. 277—35 5 Claims



1. A sealing structure comprising a retainer, a lip means for providing a sealing effect and a rigid ring fixed to the retainer and having an inner periphery and an outer periphery, the lip means being fixed to the ring, the lip means including an inner lip means which is annular and placed at the inner periphery of the ring and an outer lip means which is annular and placed at the outer periphery of the ring, the outer lip means having a resilient or elastic portion embedded in the retainer in such a manner that the retainer can support the ring and the inner lip means in a floating condition, wherein the elastic or resilient portion of the inner lip means includes a first outer lip projecting in an oblique direction from an intermediate portion of the ring and a second outer lip projecting in an oblique direction from an outer edge portion of the ring.


5,588,657
LAMINATED METAL GASKET WITH DIVERSE BEAD HEIGHT
 Katsuhide Fujisawa, Eichi Tahara, and Tetsuya Hida, all of Yamato, Japan, assignors to Nippon Reinz Co., Ltd., Kanagawa, Japan
 Filed Oct. 3, 1995, Ser. No. 538,399
 Int. Cl.⁶ F16J 15/08
 U.S. Cl. 277—180 13 Claims



1. A laminated metal gasket disposed between a pair of joint surfaces having at least one hole to be sealed comprising: at least one intermediate plate made of a metal plate, and a pair of surface plates made of elastic metal plates laminated on both sides of said intermediate plate, said intermediate plate and said surface plates each having at least one hole portion corresponding to said hole to be sealed, said intermediate plate being equipped, adjacent to said hole portion, with an annular folded portion which is made by

folding back the inner peripheral edge portion thereof to said surface plate coming into contact with the joint surface to be subjected to more significant distortion and deformation during operation among the pair of joint surfaces, and said surface plates each being equipped with a bead surrounding said hole portion outside said folded portion, wherein said bead of said surface plate coming into contact with the joint surface to be subjected to more significant distortion and deformation is made higher than the bead of said surface plate coming into contact with the other joint surface.

5,588,658
APPARATUS FOR MOUNTING SKATE ROLLERS IN INLINE ROLLER SKATES
 Johann Perner, Graz, and Gerhard Trinkaus, Voitsberg, both of Austria, assignors to Koflach Sport Gesellschaft m.b.H. & Co. KG, Austria
 PCT No. PCT/AT94/00062, § 371 Date Jan. 10, 1995, § 102(e) Date Jan. 10, 1995, PCT Pub. No. WO94/26367, PCT Pub. Date Nov. 24, 1994
 PCT Filed May 9, 1994, Ser. No. 367,144
 Claims priority, application Austria, May 12, 1993, 935/93
 Int. Cl.⁶ A63C 17/06
 U.S. Cl. 280—11.22 6 Claims




1. A device for mounting rollers in inline roller skates, in which the roller axes extend through openings in a frame and are mounted in a sub-frame, in which the inner diameter of the openings in the frame is larger than the outer diameter of the roller axes, and the sub-frame can be secured to the frame in at least two different vertical positions, characterized in that, the sub-frame (6, 19) is positively lockable in at least two different vertical positions using an insert member (10) extending through the frame (3) and free flanks of the sub-frame (6, 19).


5,588,659
TOOL CART
 James A. Boes, Chad W. Boes, and Douglas W. Boes, all of Sullivan, Ind., assignors to Triple B Trenching, Inc., Sullivan, Ind.
 Filed Mar. 29, 1995, Ser. No. 412,569
 Int. Cl.⁶ B62B 1/00
 U.S. Cl. 280—47.19 15 Claims

1. A tool cart comprising an upright stand, a work bench mounted on the upper end of the stand, an upright frame extending upwardly from the stand at one edge of the work bench, storage means supported from said stand and accessible from an edge of the work bench opposite to said frame, first tool supporting means mounted on said stand adjacent the work bench and second tool supporting means mounted on said frame above the work bench, said second tool supporting means mounted on said frame including a plurality of elongated members, each of said elongated members having pivotal connection at one end thereof with said

5,588,661
WHEEL MOUNTING BRACKET AND SPACER
 Robert M. Wolfe, 24042 Sprig St., Mission Viejo, Calif. 92691
 Filed Jan. 10, 1995, Ser. No. 370,899
 Int. Cl.⁶ B62J 11/00
 U.S. Cl. 280—202 9 Claims




1. A support bracket for mounting on a first axle assembly of a first wheel, the support bracket comprising a rigid body providing a peripheral edge defining the extent of a pair of opposing, spaced apart, side surfaces, each surface situated in opposing parallel planes defining a body thickness therebetween, and further providing an elongate mounting slot open to the peripheral edge and extending into the body therefrom, and a round mounting hole including a counterbore from one of the side surfaces, the slot and hole extending through the body between the side surfaces, each providing clearance therethrough, the slot sized and oriented such that with the mounting hole operably engaged with the first axle assembly, the mounting slot is positioned for receiving an axle of a second axle assembly of a second wheel, for supporting the second wheel lateral to the first wheel.




1. A support bracket for mounting on a first axle assembly of a first wheel, the support bracket comprising a rigid body providing a peripheral edge defining the extent of a pair of opposing, spaced apart, side surfaces, each surface situated in opposing parallel planes defining a body thickness therebetween, and further providing an elongate mounting slot open to the peripheral edge and extending into the body therefrom, and a round mounting hole including a counterbore from one of the side surfaces, the slot and hole extending through the body between the side surfaces, each providing clearance therethrough, the slot sized and oriented such that with the mounting hole operably engaged with the first axle assembly, the mounting slot is positioned for receiving an axle of a second axle assembly of a second wheel, for supporting the second wheel lateral to the first wheel.

5,588,660
STEERING AXLE
 Richard L. Paddison, Ortonville, Mich., assignor to General Motors Corporation, Detroit, Mich.
 Filed Sep. 28, 1995, Ser. No. 535,428
 Int. Cl.⁶ B62D 7/08
 U.S. Cl. 280—95.1 4 Claims



1. A steering axle comprising: an axle beam having an elongated body and a longitudinal centerline with first and second ends, each end being capable of carrying a steering knuckle assembly that is pivotably rotatable, wherein each end of the axle beam includes a pair of stops formed integrally therewith, the two stops within each pair of stops being disposed on opposite sides of the longitudinal centerline and at first and second distances along the axle beam relative to the end wherein the axle beam is reversibly assemblable with the first and second ends interchangeable to alternatively provide two different ranges of maximum steering angles.

5,588,662
ADJUSTABLE BICYCLE REAR AXLE SUPPORT ASSEMBLY
 Robert L. Fortier, 502 W. Blum St., Alvin, Tex. 77511
 Filed Mar. 1, 1995, Ser. No. 396,572
 Int. Cl.⁶ B62K 19/24; 25/02
 U.S. Cl. 280—288 9 Claims



1. An adjustable bicycle rear axle support assembly comprising: a bicycle frame having a rear vertical member, with the rear vertical member including an upper portion, and a lower portion; a rear axle support member pivotally mounted to the lower portion of the rear vertical member of the frame, the rear axle support member extending rearwardly of the bicycle frame and being adapted to rotatably mount a rear wheel relative to the bicycle frame, the rear axle support member comprises a

support member plate pivotally mounted to the lower portion of the rear vertical member of the bicycle frame, a first lateral rear axle support arm projecting from the support member plate and adapted to be positioned about a first lateral area of a bicycle rear wheel;

an adjustment means extending between the rear axle support member and an upper portion of the rear vertical member for adjustably positioning the rear axle support member into a fixed angular orientation relative to the rear vertical member, the adjustment means comprises a first receiver pivotally mounted to the upper portion of the rear vertical member, a second receiver pivotally mounted to the rear axle support member, and threaded projection means threadably engaged to the first and second receivers for adjustably positioning the first receiver in a spaced relationship relative to the second receiver, the second receiver of the adjustment means is pivotally mounted to the support member plate, the support member plate being shaped so as to define a mounting cavity extending into the support member plate within which a portion of the second receiver is positioned.

5,588,663

WHEELCHAIR TRAY ACCESSORY


Christopher Rundle, 12588 SW. 60th Ct., Miami, Fla. 33156, and Michael Borell, 7787 SW. 86th St. Apt. 310, Miami, Fla. 33143

Filed May 15, 1995, Ser. No. 440,756

Int. Cl.⁶ A47B 83/02; A47C 7/68

U.S. Cl. 280—304.1

10 Claims



1. A wheelchair accessory for use in combination with a wheelchair having a frame construction with pivoting front wheels and enlarged rear wheels supporting a horizontal seat member and vertical back member, the wheelchair having spaced apart armrests positioned above an upper surface of the seat member leading to rear push handles disposed behind the vertical back member, said accessory comprising: a detachable housing means having an upper wall adjoined to a bottom wall by two side walls and a first and second end wall defining a chamber therebetween; guide means for securing said housing means to the wheelchair; first hinge means coupled to said second end wall for holding said second end wall in a closed position sealing said chamber, said first end wall having an angular shape, said second end wall rotatable to an over-center open position allowing access to said chamber; a pivotal tray means having a planar surface; a second hinge means coupled to said housing means for holding said tray means in a storage position juxtaposition to said upper wall allowing rotation to a generally horizontal position adjacent to the armrests;

wherein said housing means is slidably secured to said wheelchair positioning a portion of said second end wall beneath a portion of one armrest preventing said second end wall from

opening, said housing means slidable to a second position adjacent to the armrest allowing the rotation of said second end wall to said open position allowing access of items placed within the chamber of the housing means whereby the return of the housing means to the first position secures items within the chamber by preventing the opening of said second end wall, said housing means detachable from said wheelchair with the angular shape providing a ramp for rolling said wheelchair onto said housing means providing a ramp.

5,588,664

LINK DEVICE OF A LATERAL ROD FOR A VEHICLE


Tae J. Moon, Yangsan-kun, Rep. of Korea, assignor to Hyundai Motor Company, Ltd., Seoul, Rep. of Korea

Filed Dec. 29, 1995, Ser. No. 581,426

Int. Cl.⁶ B60G 11/20

U.S. Cl. 280—689

3 Claims



1. A link device of a lateral rod for a vehicle, comprising: a bracket fixed to a rear axle of said vehicle; an inner pipe attached to said bracket by a mounting bolt, said inner pipe having a raised portion extending from one side thereof; an outer socket extending from one end of said lateral rod, said outer socket having a pair of upper and lower protruding portions wherein said upper and lower protruding portions extend from upper and lower portions thereof, and said outer socket surrounding said inner pipe for forming a ring-shaped space therebetween; and a buffer member disposed within the ring shaped space between said inner pipe and said outer socket, whereby when the vehicle turns in any direction and rides over a bump, one of the protruding portions rotates into engagement with the raised portion of said inner pipe, thereby extending a vertical displacement of said lateral rod.

5,588,665

TRAILING ARM SUSPENSION WITH LEVER ARM

William C. Pierce, and Gregory A. Richardson, both of Muskegon, Mich., assignors to Nai Neway, Inc., Muskegon, Mich.


Filed Mar. 19, 1996, Ser. No. 618,318

Int. Cl.⁶ B62D 61/12; B60G 900/11/56

U.S. Cl. 280—704

25 Claims

1. In a suspension for a vehicle comprising a frame, the suspension including a pair of trailing arms pivotally mounted to the frame for vertical swinging movement relative thereto about a transverse axis between at least a retracted position and a road engaging position, an axle mounted to and between the trailing arms for carrying wheels for contact with a road surface, and a selectably variable force spring between the trailing arms and the frame for cushioning the swinging movement of the trailing arms in the road engaging position, the improvement comprising:



a lever arm fixedly mounted to at least one trailing arm and extending upwardly therefrom, the lever arm being positioned to define a moment arm relative to the transverse axis that increases as the at least one trailing arm is moved toward the retracted position, and a compression spring mounted between the frame and the lever arm above the transverse trailing arm axis to bias the at least one trailing arm to the retracted position, whereby the force of the compression spring exerted on the lever arm tends to raise the at least one trailing arm to the retracted position when the force on the variable force spring is reduced.

5,588,666

DRIVER SIDE AIR BAG COVER MOUNTING ASSEMBLY


Shigeo Numata, Patchogue, N.Y., assignor to Izumi Corporation, Yaphank, N.Y.

Filed Jun. 27, 1994, Ser. No. 266,250

Int. Cl.⁶ B60R 21/16

U.S. Cl. 280—728.2

4 Claims



1. A mounting arrangement for a vehicle air bag comprising: a boss means affixed to a component of a vehicle, spoke means extending from said boss means, a base plate having a first mounting portion on which an air bag is mounted and a second mounting portion on which said boss means is attached, a plurality of attachment clips, and a plurality of fasteners connecting said attachment clips to said second mounting portion of said base plate and said boss means, each of said attachment clips having generally straight, flexible leg sections and a central section connecting said leg sections together, each of said leg sections having an end portion, each of said end portions having an aperture therethrough for receiving a shank portion of one of said plurality of fasteners and for attaching together said second mounting portion and said boss means and wherein said boss means, said second mounting portion, and said attachment clips are formed of magnesium, aluminum and steel materials, respectively, said

attachment clips spaced apart from said spoke means, boss mounting portion disposed generally perpendicular to said base plate, each boss mounting portion defining a channel and having slots formed in opposite sides thereof, each of said attachment clips frictionally engaging one of said slots formed in said boss mounting portion and one side of said second mounting portion for mounting said air bag, each said slot being tapered in opposite directions.

5,588,667

VEHICLE OCCUPANT RESTRAINT APPARATUS AND METHOD OF ASSEMBLY


Al S. Emambakhsh, Flat Rock; Michael P. Pionk, Marysville; Al A. Saberan, New Baltimore, and John P. Wallner, Rochester, all of Mich., assignors to TRW Vehicle Safety Systems Inc., Lyndhurst, Ohio

Filed Sep. 30, 1994, Ser. No. 315,590

Int. Cl.⁶ B60R 21/16

U.S. Cl. 280—728.2

2 Claims



1. Apparatus comprising: a canister, said canister having wall means for defining a chamber, a side opening facing outward from said chamber in a first direction, and a deployment opening facing outward from said chamber in a second direction perpendicular to said first direction; an inflator structure having means for directing inflation fluid into said chamber, said inflator structure being movable to an installed position in said chamber from said first direction through said side opening; and a restraint assembly including an inflatable vehicle occupant restraint and support means for supporting said restraint in fluid communication with said inflator structure, said restraint assembly having an installed position engaged with said canister, said restraint being expandable from said deployment opening in said second direction upon inflation of said restraint when said restraint assembly is in said installed position; said canister and said support means having cooperating means for guiding movement of said restraint assembly to said installed position in sliding contact with said canister in a third direction perpendicular to said second direction; said wall means including a wall portion having a bendable tab formed as one piece with said wall portion; said canister further including a closure wall having means for defining a slot, said closure wall being receivable in a closed position in which said closure wall blocks movement of said inflator structure and said restraint assembly from said installed positions, said tab being receivable through said slot and being bendable into a fastening position in which said tab retains said closure wall in said closed position; said wall means including a side wall of said canister which has an annular inner edge surface defining said side opening in a circular shape, said closure wall extending across said side opening when said closure wall is in said closed position.

5,588,668

AIR BAG MODULE


Ali S. Emambakhsh, Rochester Hills, and Russell E. Stein, Leonard, both of Mich., assignors to TRW Vehicle Safety Systems Inc., Lyndhurst, Ohio

Filed May 26, 1995, Ser. No. 452,124

Int. Cl.⁶ B60R 21/16

U.S. Cl. 280—728.2

20 Claims



11. A safety apparatus for protecting an occupant of a vehicle, said apparatus comprising:
an inflatable vehicle occupant restraint having a deflated condition and an inflated, occupant protecting condition;
an inflator for inflating said inflatable restraint, said inflator having a housing;
a canister defining a chamber for receiving said housing;
said canister having a main wall including upper and lower main wall portions and having first upper and lower main flanges projecting away from said upper and lower main wall portions, respectively, and away from each other;
each one of said first upper and lower flanges having a pair of first recessed portions;
said canister having a plurality of second recessed portions forming standoffs which project into said chamber and which define spaced surfaces for engaging spaced surface portions of said housing; and
securing means for clamping said surface portions of said inflator housing against said surfaces on said standoffs, said securing means being in engagement with said inflator housing and having portions located in said first recessed portions on said first upper and lower flanges.

5,588,669

COVER ATTACHMENT FOR AN AIR BAG MODULE

Timothy J. Leonard, Stuttgart, Germany, and Kurt E. Kottke, Bountiful, Utah, assignors to Morton International, Inc., Chicago, Ill.


Filed Apr. 26, 1995, Ser. No. 429,380

Int. Cl.⁶ B60R 21/16

U.S. Cl. 280—728.3

18 Claims

1. A cover attachment arrangement for an air bag module,



comprising:

a housing constructed and arranged to be secured to a structural element of a vehicle, said housing defining a chamber containing a cushion operatively connected to a gas generator, said housing including a plurality of mounting tabs extending therefrom;

a cover having a main panel with a periphery and a skirt having a rectangular periphery extending from said panel, said skirt sized to fit through an opening in a cabin element of the vehicle, said skirt including a plurality of slots, each said slot receiving an associated one of said mounting tabs, each said slot being larger than said associated tab to permit said cover to move with respect to said housing, and a plurality of placement tabs extending from said skirt, at least one of said placement tabs extending from each edge of said rectangular skirt, said placement tabs being spaced from said panel a distance to receive a peripheral edge of the opening in the cabin element of the vehicle.

5,588,670

SEAT STRUCTURE PRESSURE VESSEL FOR AIRBAG INSTALLATION

J. Kirk Storey, Farmington, and Brent K. Olson, Clearfield, both of Utah, assignors to Morton International, Inc., Chicago, Ill.


Filed Jul. 20, 1995, Ser. No. 503,884

Int. Cl.⁶ B60R 21/22

U.S. Cl. 280—730.2

7 Claims

1. In a motor vehicle having passenger chairs therein including



at least one air bag module, an inflation initiator and a pressurized inflation-gas, the improvement comprising:

at least one of said chairs having a structural framework, said framework storing said pressurized inflation-gas, said at least one air bag module and said initiator mounted to and substantially externally on said framework.

5,588,671

RESEALABLE TEAR SEAM FOR SEAT DEPLOYED SIDE IMPACT AIR BAG

Mohamed Boumarafi, Rochester Hills; Jonathan P. Hurford, Lake Orion; William V. Collier, Milford, all of Mich., and Ralph Lichlyter, Danridge, Tenn., assignors to Takata, Inc., Auburn Hills, Mich.


Filed Sep. 21, 1995, Ser. No. 531,517

Int. Cl.⁶ B60R 21/22

U.S. Cl. 280—730.2

20 Claims

1. A vehicle seat apparatus comprising:
an internal seat frame;
an external covering; and
a seat deployed air bag contained within said seat and covered by said covering wherein said air bag is deployed through a



resealable seam in said covering, said seam having a first seam member having at least two arm members which together form at least two female connectors configured to form a resealable interlocking bond with a second seam member having at least two arm members which together form at least two female connectors, wherein said first member at least two arm members engage said second member at least two female connectors and said second member at least two arm members engage said first member at least two female connectors to form said resealable interlocking bond, said air bag being inflated during deployment forcing said air bag to expand thus causing said interlocking bond to open along said seam allowing said air bag to expand outside of the vehicle seat.

5,588,672

SIDE IMPACT HEAD RESTRAINT WITH INFLATABLE DEPLOYMENT


James P. Karlow, Milford; Mohamed Boumarafi, Rochester Hills, and Jonathan P. Hurford, Lake Orion, all of Mich., assignors to Takata, Inc., Auburn Hills, Mich.

Filed Oct. 20, 1995, Ser. No. 545,944

Int. Cl.⁶ B60R 21/22

U.S. Cl. 280—730.2

20 Claims



1. A side impact head restraint system for cushioning a vehicle occupant's head during a side impact collision including means for sensing the side impact collision and generating a crash signal thereupon, said system comprising:

a restraint curtain mounted inside the vehicle adjacent a window area of a side door of the vehicle, said curtain having at least three securing points, wherein first and second securing points are fixedly attached on an upper rail of said side door and a third securing point is movably mounted on a generally vertical track located adjacent a track edge of said window area, said track running along said track edge from an upper edge toward a lower edge of said window area, said first securing point being located near said upper edge and a rear edge of said window area and said second securing point being located near said upper edge and a forward edge of said window area;

an inflatable member carried by said restraint curtain;

a gas generator in fluid communication with said inflatable member, said gas generator for generating gas in response to said crash signal wherein said generated gas inflates said inflatable member causing said third securing point to move along said track, driven by said inflatable member, from an undeployed position near said upper edge of said window area to a deployed position near said lower edge of said window area thereby pulling said curtain into a deployed condition covering at least a portion of said window area thus providing restraint for the vehicle occupant's head, wherein said third securing point locks into position at the end of travel along said track when said curtain is fully deployed.

5,588,673

MEMBRANE SWITCH FOR USE OVER A STEERING WHEEL AIRBAG ASSEMBLY


Mark Green, Eden Prairie, and Robert B. Hartline, Richfield, both of Minn., assignors to The Bergquist Company, Minneapolis, Minn.

Filed Feb. 1, 1994, Ser. No. 189,936

Int. Cl.⁶ B60R 21/20

U.S. Cl. 280—731

18 Claims



1. A membrane switch, comprising:

a pair of flexible, opposing, planar conductive electrodes electrically isolated from one another, each said opposing electrode having an outer surface and an inner surface, said inner surfaces opposing one another, each of said outer surfaces having a continuous flexible non-conductive layer disposed thereon;

a generally planar dielectric member disposed between said opposing electrodes having a high-density pattern of interlaced wall portions defining a plurality of geometric shapes having an axis, said geometric shapes defining a plurality of opposing electrode contact portions on said inner surfaces of said opposing electrodes which remain unobstructed by said dielectric member; and

a plurality of outwardly extending protrusions disposed as a high density pattern on the outer surface of each said nonconductive layer, each of said plurality of outwardly extending protrusions having an axis and being arranged in generally axially aligned relation with each of said plurality of opposing electrode contact portions, such that pressure exerted on each said outwardly extending protrusions causes the correspondingly aligned, opposing electrode contact portions to make electrical contact with one another.

5,588,674

INTERVENING CLOTH ON AN AIR BAG

Toshifumi Yoshimura, Ryo Kikuchi, and Shoji Inuma, all of Fujisawa, Japan, assignors to Isuzu Motors Limited, Tokyo, Japan


Filed May 3, 1995, Ser. No. 434,301

Claims priority, application Japan, Oct. 7, 1994, 6-244298

Int. Cl.⁶ B60R 21/22; 21/16

U.S. Cl. 280—732

5 Claims



1. An air bag device for installation in a dash board of a vehicle, said air bag device comprising:
 - a case having an open side and adapted to be inserted into an opening of a dash board of a vehicle;
 - an air bag having an open end, said air bag being folded within said case with the open end secured to said case adjacent the open side thereof, said air bag being inflatable to deploy out from said case through the case open side and the dash board opening and into the interior of the vehicle;
 - a door of predetermined width and height, said door closing said case open side with said air bag folded therein and being adapted to be opened upon inflation of said air bag to permit said air bag to deploy into the interior of the vehicle;
 - a substantially planar intervening cloth secured between said air bag and said door and adapted to intervene between said air bag and said door as said air bag is inflated, said intervening cloth having a length permitting said intervening cloth to extend beyond said door and into the interior of the vehicle and to intervene between said air bag and interior components of the vehicle as said air bag deploys.

5,588,675

AIR BAG MODULE WITH GAS AUGMENTATION

John A. Lotzpih, Englewood, Ohio, assignor to General Motors Corporation, Detroit, Mich.


Division of Ser. No. 169,124, Dec. 20, 1993, abandoned. This

application Jun. 19, 1995, Ser. No. 491,807

Int. Cl.⁶ B60R 21/30; 21/20

U.S. Cl. 280—738

13 Claims



5. An air bag module comprising:
 - an inflatable air bag having an inflation opening;
 - an inflator for discharging inflation gas upwardly towards the inflation opening to inflate the air bag;

a container for housing the air bag and inflator, the container including longitudinally elongated side walls and end walls interconnecting the side walls and defining an upper air bag deployment opening;

one of the side walls being generally planar in a vertical direction parallel to the discharging inflator gas, the side wall being laterally spaced apart from the inflator;

the one of the side walls having a plurality of aspiration holes therein to aspirate ambient air to augment the discharging inflation gas during air bag inflation and for venting the inflation gas to facilitate air bag collapse;

at least one longitudinally extending rib disposed on the one of the side walls and projecting inwardly into the container, the rib being located directly beneath the plurality of aspiration holes, the rib being vertically spaced above the inflator in the direction of the discharging inflation gas such that discharging inflation gas passes over the rib prior to passing over the plurality of aspiration holes and creates a pressure drop over the aspiration holes located above the rib to cause augmentation of ambient air aspiration during air bag inflation.

5,588,676

STAMPED METAL TOROIDAL HYBRID GAS GENERATOR

Randall J. Clark, Pleasant View; Bradley W. Smith, Ogden; Kirk H. Rasmussen, West Point, all of Utah, and Leland B. Kort, Lakewood, Colo., assignors to Morton International, Inc., Chicago, Ill.


Division of Ser. No. 321,786, Oct. 12, 1994, Pat. No. 5,516,147.

This application Mar. 14, 1996, Ser. No. 615,898

Int. Cl.⁶ B60R 21/28

U.S. Cl. 280—741

10 Claims



1. A hybrid inflator comprising a housing having:
 - A) an upper stamped metal housing part including a top wall and a cylindrical sidewall depending therefrom;
 - B) a lower stamped metal housing part including a bottom wall, a cylindrical sidewall extending upwardly therefrom and engaged with the cylindrical sidewall of the upper housing part and welded thereto, and a generally cylindrical center tie integrally formed in one piece with the bottom wall and extending from the bottom wall to the top wall and welded to the top wall;
 - C) an upper wall integrally formed in one piece with one of the upper or lower housing parts and extending across the upper end of the center tie;
 - D) the housing defining a gas storage chamber surrounding the center tie and the center tie defining at least one inlet opening to the gas storage chamber and the housing further defining a rupturably sealed outlet orifice from the gas storage chamber; and
 - E) an igniter assembly mounted in the center tie and including a pyrotechnic gas generant material for producing and delivering hot gases to the gas storage chamber through the inlet opening thereto.

5,588,677

SAFETY BELT TENSIONER FOR MOTOR VEHICLES

Robert Kopetzky, Lonsee, and Günther Häge, Langenau, both of Germany, assignors to Takata (Europe) Vehicle Safety Technology GmbH


Filed Jun. 19, 1995, Ser. No. 492,286

Claims priority, application Germany, Jun. 23, 1994, 44 22 022.7

Int. Cl.⁶ B60R 22/36

U.S. Cl. 280—806

20 Claims



1. Safety belt tensioner for motor vehicles which can be mounted on a vehicle chassis (12), the tensioner comprising an elongate drive device (11) which is to be arranged substantially horizontally in the motor vehicle, a flexible draw element (13) which is displaceable in its longitudinal direction by the drive device (11) and which is guided upwardly from the drive device (11) via deflection member (14), which is secured to the vehicle chassis (12), to a belt lock part (15) which cooperates with a counter-piece (17) arranged at the end of a three-point belt or of a lap belt (16) and which is mounted there so as to transmit a tensile force, characterised in that:
 - the deflection member (14) is simultaneously designed as a mounting element which secures the drive device (11) to the vehicle chassis (12), and is directly and firmly connectable to the vehicle chassis (12);
 - the deflection member has a bolt or sleeve section (14') mountable to the vehicle chassis (12) and a deflection section (14''); and
 - the deflection section (14'') has a round peripheral surface which is dimensionally matched to the draw element (13) and which projects radially outwardly beyond the bolt or sleeve section (14') to form ring step (14'') between the bolt or sleeve section and the deflection section; and
 - a projection (20) of the drive device (11) having a through bore (19) through which the bolt or sleeve section can be inserted with the ring step abutting and pressing against the projection.

5,588,678

TALKING TRADING CARD

Steven R. Young, Dallas, Tex., assignor to Great Western Press, Inc., Dallas, Tex.

Continuation-in-part of Ser. No. 265,961, Jun. 27, 1994. This


application Mar. 14, 1995, Ser. No. 403,637

Int. Cl.⁶ B42D 15/00

U.S. Cl. 283—67

7 Claims

1. A method of providing a consumer with information concerning a particular subject with the use of a talking trading card comprising the steps of:
 - providing a substrate housing having a top and a bottom side;
 - attaching a trading card surface to each side of said housing;



- providing indicia on at least one of said trading card surfaces pertaining to a person, place, object, or cartoon character;
 - providing a voice-chip circuit in the housing for storing a predetermined voice message that is related to the printed indicia to create a talking trading card;
 - energizing the voice chip through power terminals thereon;
 - coupling a loudspeaker means in the housing to the voice-chip circuit for generating the message audibly; and
 - coupling switch means to the voice-chip circuit for selectively causing the voice-chip circuit to provide the consumer with the predetermined talking trading card voice message through the loudspeaker.

5,588,679

TAMPER RESISTANT LABELING

Richard T. Skov, Spencer, and John R. Pennace, Paxton, both of Mass., assignors to FLEXcon Company, Inc., Spencer, Mass.

Continuation of Ser. No. 875,552, Apr. 24, 1992, abandoned,

which is a continuation of Ser. No. 162,239, Feb. 29, 1988,

abandoned, which is a division of Ser. No. 941,998, Dec. 15,


1986, abandoned. This application Jun. 7, 1995, Ser. No.

479,553

Int. Cl.⁶ B42D 15/00; B32B 7/10

U.S. Cl. 283—67

25 Claims



1. A method of producing a coated label material, comprising the steps of:
 - providing a film;
 - applying a light transmitting layer as a predetermined indicia which is initially visible to selected areas of a surface of said film while allowing other areas of said surface to remain exposed; and
 - adhering a continuous light transmitting coating to said layer and to the exposed areas of said surface, wherein said coating and said layer forming said indicia have indices of refraction which render said coating and said layer visually indiscernible with respect to one another.


5,588,680
PIPE LAP JOINT WITH IMPROVED COLLAPSIBLE SEALING ZONE

Scott T. Cassel, Bloomfield Hills, and Michael E. Amedure, Orion, both of Mich., assignors to BKS Company, Birmingham, Mich.

Continuation-in-part of Ser. No. 359,531, Dec. 20, 1994, abandoned. This application Dec. 4, 1995, Ser. No. 566,726
 Int. Cl.⁶ F16L 35/00

U.S. Cl. 285—3

18 Claims



1. In a coupling for a pipe lap joint of the type comprising: an inside pipe and an outside pipe having respective pipe walls in telescoping relationship which provides an overlap region on the end of each pipe, said overlap region on the outside pipe including a pair of slots, the first slot of said pair having first and second sidewalls extending axially inwardly from the end of said outside pipe and terminating in an inner end wall within said overlap region, and the second slot of said pair being spaced inwardly from the end of said outer pipe and circumferentially offset from said first slot and having first and second sidewalls extending inwardly from an outer end wall to an inner end wall, a clamping band disposed around said outside pipe and covering said second slot and the inner end of said first slot, tightening means for clamping said band around said outside pipe to clamp the pipes together and collapse outer pipe into close fitting engagement with said inner pipe within the overlap region to cause sealing engagement of said outer pipe with said inner pipe and with said band, the improvement wherein:

said first sidewalls of the first and second slots are disposed with the outer end of the first sidewall of the second slot circumferentially offset from the inner end of the first sidewall of the first slot, said first sidewalls being connected together by a frangible bridging segment of the wall of the outside pipe, and said end walls extend transversely of said first sidewalls, whereby said first and second slots are substantially isolated from each other when said frangible bridging segment is deformed and when it is fractured into two parts by collapse of the overlap region of said outer pipe.

5,588,681
VALVE MOUNTING DEVICE USEFUL WITH FLEXIBLE PIPE


Alan D. Parks, 1351 Charlotte St., Altamonte Springs, Fla. 32701

Filed Aug. 1, 1994, Ser. No. 283,735
 Int. Cl.⁶ F16L 5/00

U.S. Cl. 285—46

9 Claims

1. A mounting device useful with a valve communicating with flexible pipe, the device comprising:
 means for guiding a flexible pipe through a predetermined orientation, the guiding means adapted for engaging and holding the pipe for communicating with a valve;
 means for affixing the guiding means to a structural support, the support sufficiently rigid for holding the guiding means in a fixed position; and
 means for positioning a valve communicating with the flexible pipe, the valve having a supply tube exit portion extending radially therefrom, the positioning means having a tubular




sleeve for receiving the valve, the tubular sleeve affixed to and communicating with the guiding means for receiving the flexible pipe, the tubular sleeve further having a notch at an exit end for receiving the supply tube exit portion for preventing valve rotation during valve operation.

5,588,682
ELECTRICALLY INSULATING GAS LINE SYSTEM
 Dean E. Breese, Upper Arlington, Ohio, assignor to Schwler Manufacturing Company Inc., Hilliard, Ohio

Filed Jun. 26, 1995, Ser. No. 494,985
 Int. Cl.⁶ F16L 55/00; 19/02

U.S. Cl. 285—52

19 Claims



1. A system for electrically insulating conduits carrying combustible gas comprising:

a gas meter including a threaded spud;
 an electrically conductive conduit portion, said conduit portion having an annular longitudinal end, wherein said end includes an opening, said opening adapted for flow of combustible gas therethrough, and further comprising an annular radially extending conduit flange portion, and an annular tapered portion longitudinally disposed from said conduit flange portion;

a generally annular, continuous electrically insulating portion attached to said longitudinal end, said insulating portion extending in surrounding relation of said longitudinal end, said insulating portion including an annular radially outward extending insulating flange portion and a neck portion extending from said insulating flange portion in a longitudinal direction and away from said opening, wherein said conduit flange portion underlies said insulating flange portion both longitudinally and radially, and wherein said annular tapered portion of said conduit portion has a tapered portion diameter greater than a neck diameter of said neck portion, and wherein said tapered portion diameter of said tapered portion of said conduit terminates at a

generally radially extending step, wherein said step is in close adjacent longitudinal relation with said neck portion; and

a nut portion, said nut portion including a nut aperture, said neck portion extending through said nut aperture, said nut portion further including an annular, radially inward extending lip portion bounding said aperture, and an annular threaded portion longitudinally disposed from said lip portion, wherein said threaded portion is engageable with said spud, and said lip portion is engageable with said insulating flange portion.

5,588,683
ANTI-RESONANCE PIPE CLIP

Lothar Schliessner, Linden, Germany, assignor to Emhart, Inc., Newark, Del.


Filed Jan. 19, 1995, Ser. No. 374,068

Claims priority, application Germany, Jan. 27, 1994, 9401393 U

Int. Cl.⁶ F16L 3/08; 3/22

U.S. Cl. 285—62

3 Claims



1. A resilient pipe clip for supporting elongated tubular objects in an automobile so as to reduce vibration thereof, said clip comprising

a support mount adapted to be attached to and supported on a surface in an automobile;

a web member extending from said support mount, said web member being spaced from and generally parallel to the surface;

at least one article securing member for receiving and retaining a tubular object, said article securing member being disposed on the side of said web facing the surface;

a flexible bridge member attached to said article securing member; and

a pair of curved flexing elements each connected to one end of said bridge member and to said web to resiliently support said bridge member in a position spaced from said support mount to reduce vibration of the tubular object.

5,588,684
NON-ROTATABLE MECHANICAL ATTACHMENT AND METHOD THEREFOR

James Kiefer, Grand Rapids, Mich., assignor to RAN Enterprises, Inc., Grand Rapids, Mich.

Filed May 24, 1995, Ser. No. 449,094

Int. Cl.⁶ F16L 3/00

U.S. Cl. 285—62

20 Claims



1. A mechanical connection comprising:

a first member including receiving structure defining a generally cylindrically-shaped hole with a longitudinal axis and first and second laterally extending shoulders located at opposite ends of the hole;

a tubular member having an end section shaped to mateably engage the cylindrically-shaped hole, said end section including a flared end and a circumferentially extending ridge spaced from said flared end, said ridge and said flared end engaging said first and second laterally extending shoulders, respectively;

said first laterally extending shoulder being circumferentially uniform so that the tubular member can be extended into the hole and the ridge engaged with the first shoulder without regard to angular orientation of the tubular member relative to the first member; and

said second laterally extending shoulder being ring-shaped but including radially-extending depressions and being circumferentially non-uniform, said flared end including material flared after engagement of the end section with the hole that engages said non-uniform second shoulder to prevent rotation of said tubular member relative to said first member, whereby said first member and said tubular member are fixedly mechanically connected both axially and non-rotatably by engagement of said first shoulder and said ridge, and by interlocking engagement of said second shoulder and said flared end.

5,588,685
PUSH-PULL PIPE JOINT


Joie L. Folkers, Wichita Falls, Tex., assignor to Ameron International Corporation, Pasadena, Calif.

Filed Jul. 6, 1995, Ser. No. 498,983

Int. Cl.⁶ F16L 7/00

U.S. Cl. 285—94

26 Claims



1. A push-pull pipe joint for connecting a smaller pipe to a larger pipe, wherein the larger pipe has an inside diameter larger than the outside diameter of the smaller pipe and one end of said smaller pipe is positioned within said larger pipe, comprising:

an inner annular gasket having an inside diameter smaller than the outside diameter of the smaller pipe and an inclined outer surface wherein one side of the gasket is thicker than the other, wherein the inner gasket is stretch fitted over the outer surface of the smaller pipe at said one end and wherein the thickest side of the inner gasket faces said one end; and

an outer annular gasket having an outside diameter larger than the inside diameter of the larger pipe, wherein the outer gasket has an inner surface a portion of which is inclined increasing in diameter toward the inner gasket, wherein the outer gasket is compression fitted on the inner surface of the larger diameter pipe and wherein the inner gasket inclined surface slides underneath the increased diameter portion of the outer gasket and wedges against the inclined surface of the outer gasket forming a sealed joint.

5,588,686


TEMPERATURE RESPONSIVE MECHANISM FOR CONTROLLABLY DEADLOCKING A DOOR TO A DOOR FRAME

Rory M. Riley, Santa Ana; Alan K. Uyeda, Pico Rivera, and Michael Winardi, Rowland Heights, all of Calif., assignors to Adams Rite Manufacturing Company, City of Industry, Calif.

Filed Dec. 5, 1994, Ser. No. 349,744
Int. Cl.⁶ E05B 65/10

U.S. Cl. 292-92

16 Claims



1. Locking and unlocking safety mechanism, for a door, comprising

- a push mechanism including actuator means to be carried by said door;
- a single rod operatively connected with the push mechanism to be displaced by operation of the push mechanism;
- a single door latch mechanism operable to latch and unlatch said door in response to movement of said single rod;
- said door latch mechanism being on said door, above the level of said push mechanism actuator means, said door latch mechanism being the only door latch mechanism on the door, said push mechanism actuator means being free of any push rod extending therebelow to any other door latch mechanism;
- temperature responsive blocking means associated with the rod and latch mechanism to block operation of the latch mechanism to unlatch said door, in response to a predetermined increase in ambient temperature;
- said temperature responsive blocking means including a spring-urged element and a heat fusible part blocking spring-urged movement of said element into a position to block rod movement that would otherwise unlatch the door, said heat fusible part having a fixed, non-rotatable position, and blocking movement of said element until fusing of said part.

5,588,687

CHILD PROOF REFRIGERATOR DOOR LATCH

William R. Pinkerton, P.O. Box 3035, Brownsville, Tex. 78523
Continuation-in-part of Ser. No. 140,851, Oct. 25, 1993, Pat. No. 5,387,018. This application Aug. 11, 1994, Ser. No. 288,826


Int. Cl.⁶ E05C 19/18

U.S. Cl. 292-259 R

19 Claims

1. A device for making a refrigerator door or other closure child resistant, comprising:

- first and second mounting plates each having front and back sides and each being from about 1 square inch to 250 square inches in area and from about one sixteenth inch to one half inch thick and each having lanyard attaching means comprising a flat loop mounted to its front side in a perpendicular plane relative to the plane of the mounting plate and being tangent along a segment of said loop with said mounting plate and an adhesive surface on said back side of each mounting



plate, wherein further said loop has an inner diameter of from about one half inch to about two inches and is oval or approximately square; wherein said first and second mounting plates are made from any one or two or any combination of the following materials: wood, plastic, steel, brass, bronze, copper, stainless steel, fiberglass, aluminum, magnesium, zinc coated iron, corrosion resistant metal alloys, non photo degradable plastic;

- a length of shock cord from two to thirty inches long, sometimes hereafter referred to as, lanyard, said lanyard having a limited stretch capability of from about thirty percent of diameter to about 250 percent of diameter and having first and second ends with said lanyard first end mounted to said loop on said second mounting plate;
- a releasable spring clasp having a clasp end and a plain or swivel eyelet butt end mounted by said butt end to said lanyard second end for attaching said lanyard second end to said first mounting plate via the spring clasp when said first mounting plate is adhered via its adhesive backing to one part of a two part closure of the refrigerator door and said second mounting plate is mounted to the other part of said closure so that the lanyard is fully extended to slightly stretched when so connected but having enough stretching capability remaining to allow an adult to easily remove said spring clasp attached to said lanyard from said first mounting plate.

5,588,688

ROBOTIC GRASPING APPARATUS

Stephen C. Jacobsen, Salt Lake City; Dwight Potter, Stansbury Park, and Fraser Smith, Salt Lake City, all of Utah, assignors to Sarcos, Inc., Salt Lake City, Utah
Continuation-in-part of Ser. No. 58,690, May 7, 1993, Pat. No. 5,328,224, which is a continuation of Ser. No. 963,831, Oct. 20, 1992, abandoned, which is a continuation of Ser. No. 563,399, Aug. 6, 1990, Pat. No. 5,172,951. This application

Jul. 8, 1994, Ser. No. 272,196

Int. Cl.⁶ B25J 15/10

U.S. Cl. 294-106

39 Claims

1. Robotic gripping apparatus comprising:

- a support base, and
- first and second fingers attached at proximal ends to the support base to extend forwardly therefrom, and selectively moveable in a plane toward or away from one another, each of said fingers including
- a base section attached at one end to the support base, and
- a tip section pivotally attached at a pivot end to the other end of the base section and pivotable downwardly in a direction generally normal to the plane of movement of the fingers, and
- a facing side facing the other finger, each facing side including

5,588,690

DOUBLE BACK GOLF CART ENCLOSURE


Jerry M. Showalter, Wesley Chapel, Fla., assignor to Tampa G Manufacturing Co., Tampa, Fla.

Filed Dec. 8, 1995, Ser. No. 569,787


Int. Cl.⁶ B60J 9/00

U.S. Cl. 296-77.1

11 Claims



- a first plurality of substantially rigid protuberances projecting toward the other facing side, and
- a second plurality of substantially flexible, resilient protuberances projecting toward the other facing side.



1. An enclosure for a golf cart or other vehicle having a roof structure secured above a body portion of the vehicle and a club carrier bracket, said enclosure comprising in combination:

- a roof panel having an underside generally corresponding to the configuration of the roof structure of the golf cart, said roof panel overlying said roof structure;
- a hem portion coupled to said roof panel about its periphery;
- a first back cover coupled to and suspended from said roof panel about said roof panel's rearward periphery;
- a second back cover coupled to and suspended from said roof panel about said roof panel's rearward periphery;
- a first securing means positioned about the rearward periphery of said roof panel for retaining said first back cover under said hem portion in a rolled state; and
- a second securing means positioned about the rearward periphery of said roof panel for retaining said second back cover under said hem portion in a rolled state.

5,588,689

DENTAL INSTRUMENT HOLDER


Eric W. Ochs, 22448 Hoffman, St. Clair Shores, Mich. 48082

Filed Apr. 7, 1995, Ser. No. 418,202

Int. Cl.⁶ B25B 7/00; B25J 15/00

U.S. Cl. 294-118

8 Claims



1. A dental instrument holder for releasably holding at least one elongated, rigid dental instrument having opposed ends, the holder comprising:

- first and second tong members, each including a jaw lever portion and an opposed handle portion;
- means for pivotally connecting the first and second tong members for opposing pivotal movement;
- each jaw lever portion including only first and second spaced jaws interconnected by a cross arm integrally extending from the handle portion;
- at least one of the first and second jaws on the first and second tong members having an arcuate concave shape extending from the cross arm to an outer end; and
- the first and second jaws on the first tong member spaced apart at a different spacing from the first and second jaws on the second tong member to dispose the first jaws and the second jaws on the first and second tong members in respective side-by-side relationship, with the outer ends of each first and second jaw pivoted beyond the outer end of the opposed first and second jaw to form a variably sized closed opening between the first and second jaws for supporting the opposed first and second ends of the at least one dental instrument.

5,588,691

WINDSHIELD MOLDING FOR VEHICLES AND THE PRODUCTION METHOD THEREOF

Yukihiko Yada, Nagoya, and Yoichi Hirai, Ohbu, both of Japan, assignors to Tokai Kogyo Kabushiki Kaisha, Ohbu, Japan

Continuation of Ser. No. 168,192, Dec. 17, 1993, abandoned, which is a continuation-in-part of Ser. No. 30,066, Mar. 24, 1993, abandoned. This application Jan. 3, 1996, Ser. No. 582,598

Claims priority, application Japan, Jul. 25, 1991, 3-208600


Int. Cl.⁶ B60J 1/02

U.S. Cl. 296-93

23 Claims

1. A windshield molding for vehicles having an upper molding section and a side molding section to be fitted along the periphery of the windshield glass fitted into the window frame opening of the body panel and further including a corner molding section interconnecting the upper molding section and the side molding section, said windshield molding comprising:

- a support leg located between the periphery of said windshield glass and an inner edge of the window frame opening of the body panel, a decorative portion provided on the outside edge of the support leg to cover said space from the outside, said support leg having an enlarged thickened section along the side molding section and a rainwater groove opening to the inner periphery of the windshield molding,
- wherein said decorative portion has a outer contour extending throughout the entire length of the windshield molding and is projected outwards apart from the windshield glass surface at least along a part of the side molding section,
- said enlarged thickened section is located between the decorative portion and an outer surface of the windshield glass, said



enlarged thickened section increasing in height from said corner molding section and extending along said side molding section with a substantially uniform height to a lower portion of the side molding section, said enlarged thickened section additionally completely surrounding upper and lower ends of the rainwater groove, and

said rainwater groove is provided in the enlarged thickened section of said support leg wherein a depth of the groove is changed along a longitudinal axis of the windshield molding.

8. A windshield molding for vehicles having an upper molding section and a side molding section to be fitted along the periphery of the windshield glass fitted into the window frame opening of the body panel and further including a corner molding section interconnecting the upper molding section and the side molding section, said windshield molding comprising:

a support leg inserted into a space between the periphery of said windshield glass and an inner edge of the window frame opening of the body panel, a decorative portion provided on the outside edge of the support leg to cover said space from the outside, and a rainwater groove opening to the inner periphery of the windshield molding,

wherein said rainwater groove is provided at a central portion of the side molding section, said support leg along the side molding section having an enlarged thickened section, said enlarged thickened section increasing in height from said corner molding section and along said side molding section, said enlarged thickened section additionally completely upper and lower ends of the rainwater groove.

5,588,692

PUSH-OUT VEHICLE SIDE DOOR

Umesh N. Gandhi, Grand Blanc, and Douglas J. Osmak, Clarkston, both of Mich., assignors to General Motors Corporation, Detroit, Mich.


Filed Oct. 11, 1995, Ser. No. 541,165

Int. Cl. B60R 21/04

U.S. Cl. 296—146.7

10 Claims

1. An automotive vehicle door comprising:
 - a first generally rigid outer structure having first and second ends;
 - a second generally rigid inner structure with a major portion spaced from the first outer structure, the second inner structure having first and second ends generally positionally aligned with the first and second ends of the first outer structure, the second inner structure having an opening;
 - a trim panel positioned generally adjacent the second inner structure;



a target positioned in alignment with the opening of the second inner structure adjacent the first end of the second inner structure, the target also having a portion adjacent the first outer structure; and

a beam having a first end generally fixed with respect to the second inner structure first end and a second end fixed with respect to the second inner structure second end, the beam crossing over the target straddling a portion of the opening of the rigid inner structure and wherein an impact on the door first outer structure causes the target to move inwardly through the opening, contacting the beam between the beam first and second ends to force the beam second end to dislodge the trim panel from the second inner panel end and move the trim panel inwardly.

5,588,693

MODULAR TRUCK CARGO AREA BODY


Roy C. Higginson, Ramsden Farm Box 4000 Rd. 4, Birdsboro, Pa. 19508, and Paul L. Whiteman, R.D. #1 Box 63, Morgantown, Pa. 15543

Filed Aug. 31, 1994, Ser. No. 299,219

Int. Cl. B60R 27/00

U.S. Cl. 246—183

19 Claims



1. A modular frame structure for a cargo area body of a truck comprising:

- (a) first and second spaced apart substantially co-planar bottom rails, each bottom rail comprising:
 - (1) a lower rail portion attachable to a truck sub-structure of a truck;
 - (2) an upper rail portion which interlockingly engages the lower rail portion;
 - (3) means for interlockingly engaging the lower rail portion and the upper rail portion;
 - (4) means for sealing disposed proximate the means for interlockingly engaging, the means for sealing comprising at least an elongated O-ring seal;
- (b) first and second spaced apart substantially co-planar top rails, each top rail being associated with a corresponding bottom rail, each top rail comprising:
 - (1) a side rail portion;
 - (2) a roof rail portion which interdigitately engages the side rail portion;
 - (3) means for interlockingly engaging the side rail portion and the roof rail portion;

- (4) means for sealing disposed proximate the means for interlocking engaging, the means for sealing comprises at least an elongated O-ring seal;
- (c) at least one side wall support extending between each associated bottom rail and top rail and secured thereto; and
- (d) a roof structure extending between the top rails.

5,588,694

ARRANGEMENT FOR INCREASING THE BUCKLING STRENGTH OF WINDSHIELD PILLARS OF A VEHICLE

Robert Koehr, Neustadt, Germany, assignor to Dr. Ing. h.c.F. Porsche AG, Weissach, Germany


Filed Dec. 6, 1994, Ser. No. 354,068

Claims priority, application Germany, Dec. 6, 1993, 43 41 499.0

Int. Cl. B60R 21/02

U.S. Cl. 296—188

12 Claims



1. An arrangement for increasing the buckling strength of windshield pillars of a vehicle having a lateral vehicle door, comprising:

- at least one supporting strut;
- an activating device, said at least one supporting strut interacting with said activating device and extending approximately in a longitudinal direction of the vehicle, said supporting strut being aligned approximately horizontally in a deposited position and extending in an upper area of the lateral vehicle door having an inside door panel;
- a guide rail located on the windshield pillar, wherein an end of the supporting strut facing the windshield pillar, in a danger event, is moved upwards by said activating device along the guide rail to an upper end area into an operative position;
- an impression formed in the vehicle door facing a passenger compartment, said supporting strut being detachably fixed on said impression in a deposited position;
- wherein said supporting strut is completely uncoupled from the vehicle door in a swivelled-up position and said operative position; and
- a receiving device arranged adjacent to the vehicle door and being fixed at a body side of the vehicle, wherein in said operative position said supporting strut is connected on one side in a force-transmitting manner with the upper end area of the windshield pillar and, on the other side, with said receiving device.

5,588,695

FOLDABLE BEACH CHAIR

Daniel Gomes, P.O. Box 117, Worcester, N.Y. 12197-0117


Continuation-in-part of Ser. No. 553,163, Jul. 13, 1990, abandoned. This application May 19, 1995, Ser. No. 444,656

Int. Cl. A47C 4/00

U.S. Cl. 297—56

21 Claims

14. A foldable chair comprising:
 - a) back members joined together along the top of said chair;
 - b) seat members joined together along the front of said chair;



- c) intermediate seat members interlaced between said back and said seat members and joined to each of said back and seat members such that flexible and pivotable joints are formed from connections of one end of said intermediate members to said back members and from connection of the other end of said intermediate members to said seat members;
- d) leg members extending from said back members and said seat members such that said chair is supported when folded open for use and placed upon a flat surface;
- e) at least one tip prevention member joined along the front of said chair between said seat members such that said tip prevention member can be alternately extended downward or stored when said chair is in use and contacts said flat surface when a person is seated in said chair and said tip prevention member prevents said chair from tipping forward;
- f) means for joining said back, seat and intermediate members of said chair together.

5,588,696

CONVERTIBLE CHAIR WITH ARMRESTS WHICH CONVERTS TO A BACKPACK


John C. Jay, 18 Sea St., Manchester, Mass. 01944, and Clay A. Burns, 8 Claremont Park #2, Boston, Mass. 02118

Filed Jun. 29, 1995, Ser. No. 496,450

Int. Cl. A47C 4/42

U.S. Cl. 297—129

18 Claims



1. A backpack assembly which is convertible to a multiposition chair comprising:
 - generally parallel front and back panels having tops and bottoms, said front panel intended to be closer to the back of a person carrying the assembly as a backpack;
 - said front panel including a front cross bar and left and right front vertical side bars lying in a first plane, said back panel

having a back cross bar and left and right back vertical side bars lying in a second plane;
left and right base members each rigidly attached to a lower portion of the left and right side bars of the front panel, respectively; and pivotally attached to the lower portion of each left and right side bar of the back panel, respectively; said base members establishing a substantial gap between the front and back panels when the assembly is in the backpack configuration defining the substantial carrying volume of the backpack;

at least one strap attached to the assembly for mounting the assembly on a person's back;

rigid cross member having ends rigidly attached to each side bar of said front panel and forming a bottom support when the assembly is configured as a backpack; said cross member forming a ground based leg support when the assembly is configured as a chair;

left and right armrests, one each pivotally mounted to the back panel side bars, a bracket mounted on each of the left and right armrests at the ends of the armrests remote from the pivot mounts, each bracket having an elongated aperture; and left and right armrest posts each having one end pivotally engaged with the apertures of the left and right armrest brackets, respectively, and a central portion pivotally attached to the left and right side bars of the front panel, whereby the assembly changes into a chair configuration when the back panel is angularly displaced relative to the front panel.

5,588,697

TABLE MEANS FOR VEHICLE


Masami Yoshida, Utsunomiya, and Hidetsugu Okazaki, Wako, both of Japan, assignors to Tokyo Seat Corporation, Saitama-ken, and Honda Giken Kogyo Kabushiki Kaisha, Tokyo, both of Japan

Filed May 19, 1995, Ser. No. 445,301

Claims priority, application Japan, May 23, 1994, 6-133788
Int. Cl.⁶ A47B 39/04; B33/02

U.S. Cl. 297—173

16 Claims



1. Table means for a vehicle comprising:

a table body;

support means for attaching to a side of a vehicle seat for pivotally supporting said table body;

linkage means provided between said table body and said support means for facilitating maintaining of said table body in a horizontal state during use of said table body and facilitating collapsing of said table body after use of said table body; and

operating means for operating said linkage means; said operating means comprising lever means pivotally connected to said table body, bracket means including a first bracket member and a second bracket member, and an operating bar having a first end portion and a second end portion; said first bracket member being attached to said table body; said operating bar being connected at said first end portion thereof to said lever means and movably coupled at said second end portion thereof to said bracket means; and said linkage means and said second bracket member being pivotally connected to said first bracket member.


5,588,698
RECLINABLE MOTORCYCLE BACKREST WITH
SADDLE CUSHION COVER HAVING SUN RAY
BLOCKING FUNCTION

Tien-Chu Hsueh, 467, Yuan-Shan Rd., Chung-Ho City, Taiwan
Filed May 23, 1994, Ser. No. 247,900

Int. Cl.⁶ A47C 7/62

U.S. Cl. 297—184.11

5 Claims



1. A reclinable motorcycle backrest having a sun-shielding saddle cover and being mounted on a motorcycle cargo rack, comprising:

a support bracket mounted on the motorcycle cargo rack having a set of receptacles, each of said receptacles being provided with one of a corresponding set of arresting recesses; and a backrest assembly including: a main body having a soft pad on one side and a retraction compartment on another side, said main body being jointed pivotally at bottom ends with said support bracket; a scroll having one flat end protruding out of said main body; a roll of sun-shielding cloth having one end fixed onto said scroll; a back-cover board having a slot for covering said roll of sun-shielding cloth stored in said retraction compartment wherein said sun-shielding cloth is pulled out through said slot; a crank bar having a cranking hole composed of a long hole and a round hole formed at one end; and a pivotal rod having two latching ears at each end, each of said latching ears latching onto one of said set of arresting recesses, thereby stopping said backrest assembly from reclining down.

5,588,699

INFLATABLE SAFETY CUSHION

Christopher Rundle, 12598 SW. 60th Ct., Miami, Fla. 33156, and Michael Borell, 7787 SW. 86th St., Apt. 310, Miami, Fla. 33143

Filed Aug. 3, 1995, Ser. No. 510,602

Int. Cl.⁶ B60J 1/42


U.S. Cl. 297—216.11

15 Claims



1. A safety device for a child used in combination with a seat belt harness, said device comprising:

a one-piece inflatable structure defined by a front side surface spaced apart from a rear side surface by a continuous outer side wall, said structure delineated by an upper section having a width approximating the width of a child's head, a middle section having a width approximating the width of a child's torso, and a lower section having a width approximating the width of a child's thighs; an aperture centrally disposed in said upper section and sized for placement over a child's head, an inner side wall having a minimal spacial separation from said outer side wall defining said upper section; an inlet means for inflating said structure; said structure placed beneath a seat belt harness for securing said structure to the child wherein a child's head is inserted through said aperture with said middle section residing against the torso of the child and said lower section placed over the thighs of the child whereby a seat belt harness placed over the front surface of said structure allows said structure to be inflated through said inlet means to remove excess space between the seat belt harness and child providing the child with a properly positioned restraint that further operates as an air cushion.



5,588,700

CHILD SAFETY SEAT WITH SIDE BOLSTERS


Robert I. Homier, Plymouth, Mich., assignor to Douglas & Lomason Company, Farmington Hills, Mich.

Filed Feb. 28, 1994, Ser. No. 202,998

Int. Cl.⁶ B60N 2/30

U.S. Cl. 297—238

9 Claims



1. A child seat adapted to be integrated into a vehicle seat and movable from a stowed position to a deployed position relative to the vehicle seat by reclining a seatback member and lowering a seat member, the improvement comprising interconnection means associated with said seatback member and said seat member for automatically reclining said seatback member in coordination with lowering of said seat member, said interconnection means including a first link and a second link on each lateral side of the child seat has been inserted before "each" and each having a first end with a first pivot and a second end with a second pivot, each of said first pivots and each of said second pivots directly pivotally connected to said seat member and to said seatback member respectively; one of said second pivots on each lateral side being pivotally connected to an upper end of the seatback member.

5,588,701

DEVICE FOR MOUNTING BABY CHAIR TO BICYCLE
Shi W. Chuang, No. 7th Floor-8, No. 20, Ta Lon Road, Taichung, Taiwan

Filed Jun. 12, 1995, Ser. No. 489,355

Int. Cl.⁶ A47D 1/10

U.S. Cl. 297—256.16

3 Claims

1. A baby chair and rack combination comprising:

a rack including a front portion and including a rear portion having a puncture formed therein, and including a channel laterally formed in said rear portion and communicating with said puncture, said rack including an orifice formed in said rear portion thereof and communicating with said channel, a baby chair including a front portion for engaging with said front portion of said rack and including a rear portion having a base secured thereto, a block secured to said base for engaging in said puncture of said rack and having a first securing means for engaging with said rack so as to secure said base to said rack, said block including an aperture formed therein for aligning with said channel of said rack, and a catch means for engaging in said channel of said rack and in said aperture of said block, said catch means including a second securing means for engaging with said block so as to secure said catch to said block, said catch means including a cavity formed therein for slidably engaging with a button, and said catch means including means for biasing said button outward of said catch means so as to engage said button in said orifice and so as to further secure said catch means to said rack.

5,588,702

GARDEN ROCKING-CHAIR

Stanislaw Litwin, Przybyslawice 96, 63-400 Ostrow Wielkopolski, Poland


Filed Aug. 28, 1995, Ser. No. 519,766

Claims priority, application Poland, Jul. 28, 1995, 309835

Int. Cl.⁶ A63G 9/00

U.S. Cl. 297—277


2 Claims



2. A rocking-chair characterized by a bracket support having an upper part, having a lower part with legs, and having a pallet that is pendulously attached and that has a bottom portion, characterized in that the pallet is formed of a tubular frame with a material stretched upon it and is suspended on the bracket support by a lifting joint that comprises an eye-bolt covered with a cylindrical, metallic shield attached to the bracket support, an intermediate link and a hook covered with a cylindrical shield welded onto the frame.


of the pallet, and the cylindrical shields are covered by an elastic bellows jacket, and furthermore the legs of the rocking-chair are slidably fixed together and secured by screws into four tubular elements welded onto the lower part of the bracket support, and furthermore the rocking chair has a tangent umbrella separably attached to the upper part of the bracket support and on a definite height above the bottom level portion of the pallet and has a grading arm with a first end separably attached to the bracket support and with a second end terminating in a table top, and the table top comprises a tubular frame with a material stretched upon it.

5,588,703
LUMBAR SUPPORT DEVICE FOR VEHICLE SEAT
 Kenichi Itou, Akishima, Japan, assignor to Tachi-S Co., Ltd., Tokyo, Japan
 Filed Oct. 12, 1995, Ser. No. 542,190
 Int. Cl.⁶ A47C 3/025
 U.S. Cl. 297—284.4 11 Claims



1. A lumbar support device in a vehicle seat, the vehicle seat having a seat back and a seat back frame within the seat back, said lumbar support device comprising:
 a lumbar plate having a connecting means provided integrally therein;
 a torsion bar having a first end portion connected to said connecting means of said lumbar plate, a second end portion, and a crank portion integrally engaged between said first end portion and said second end portion;
 a crank means by which said crank portion of said torsion bar is rotatably fixed to said seat back frame;
 a cam means having discrete cam surfaces on which said second end portion of said torsion bar is slidably engaged, said cam means having a shaft means provided integrally therewith;
 a bracket means having a hole means with a narrowed hole means communicating with said hole means, said cam means being rotatably supported in said hole means after said shaft means on said cam means is inserted through said narrowed hole means into said hole means; and
 an operation lever connected to one end of said shaft means of said cam means;
 wherein said crank means is provided integrally with a snap action means for permitting said crank portion of said torsion bar to be snap inserted therethrough and rotatably secured in said crank means;
 wherein said crank means comprises at least one generally omega shaped crank member having a generally circular body in which said crank portion of said torsion bar is rotatably secured and a securing leg portion to be welded to said seat back frame, and wherein said snap action means comprises at least one projected part formed integrally in a neck portion of said generally omega shape crank member between said generally circular body and said securing leg portion.


5,588,704
ERGONOMIC ANTIFATIGUE SEATING DEVICE AND METHOD
 Richard D. Harza, 655 Sheridan Rd., Winnetka, Ill. 60093
 Continuation of Ser. No. 308,621, Sep. 19, 1994, abandoned, which is a continuation of Ser. No. 929,964, Aug. 13, 1992, abandoned. This application Apr. 15, 1996, Ser. No. 632,770
 Int. Cl.⁶ A61H 1/00
 U.S. Cl. 297—314 6 Claims



1. An ergonomic antifatigue device for moving the hips and lower midsection of a person seated in a seating apparatus, the device comprising:
 a first support having a support element positioned under the hips of the seated person, said support element comprising a left side and a right side;
 a central point located substantially within said support element;
 a second support structure connected to said support element at said central point for maintaining said central point in a substantially non-moving position while allowing movement of all portions of said support element other than said central point; and
 a motor and coupling connected to said first support;
 said motor and coupling automatically and alternately pivoting said left side of said support element up and down about said central point, and automatically and alternately pivoting said right side of said support element up and down about said central point, thereby automatically and alternately lifting one hip of the seated person and then the other hip;
 said motor and coupling also automatically and alternately rotating said support element back and forth about said central point as a series of cyclical rotations and counter-rotations, thereby cyclically moving backward and forward the hips of the seated person;
 whereby motion and stimulation are translated to the seated person in a similar fashion to the motion and stimulation imparted to a person through walking.

5,588,705
SEATBACK RECLINER MECHANISM
 Chung L. Chang, 22834 Lazy Trail Rd., Diamond Bar, Calif. 91765
 Division of Ser. No. 132,663, Oct. 6, 1993, Pat. No. 5,433,507.
 This application May 1, 1995, Ser. No. 431,441
 Int. Cl.⁶ B60N 2/02
 U.S. Cl. 297—367 6 Claims


1. A hinge fitting for a reclining vehicle seat structure, comprising:
 a fixed support assembly comprising a pair of sandwich bracket plates;
 a seatback support assembly pivotally connected to said fixed support assembly by a first pivot assembly, said seatback support assembly being movable from an upright position, rearwardly through a range of rearwardly inclined positions;



a rotatable locking member positioned at least partially between said bracket plates, pivotally connected to said fixed support assembly by a second pivot assembly, said second pivot assembly fixing said seatback support assembly in adjusted positions throughout the range of rearwardly inclined positions, said locking member defining a first face and first engagement surface, said first face and said first engagement surface being generally perpendicular to one another and intersecting along a first edge, said first face of said locking member defining a first alignment marking extending substantially to said first edge;
 a lock actuator assembly, said lock actuator assembly including a rotatable cam pivotally connected to said fixed support assembly by a third pivot assembly, said cam defining a second face and a second engagement surface, said second face and said second engagement surface being generally perpendicular to each other and intersecting along a second edge, said second face of said cam defining a second alignment marking extending substantially to said second edge, said second engagement surface engageable with said locking member to cam said locking member into said locking position and engaging said locking member at an engagement point when said locking member is in said locking position; wherein said locking member and said cam are sized and shaped such that when said first alignment marking is positioned to a predetermined side of said second alignment marking said engagement point is located such that a force acting perpendicularly at said engagement point urges said cam into engagement with said locking member, thereby preventing movement of said locking member out of said locking position in response to forces applied to said seatback support member.

5,588,706
CONTROL MECHANISM FOR THE SEAT CARRIERS OF CHAIRS, ESPECIALLY SWIVEL CHAIRS
 Maria Neumueller, and Angelika Gebhard, both of Burgthann, Germany, assignors to Sifa Sitzfabrik GmbH, Sulzbach-Rosenberg, Germany
 Filed Oct. 14, 1994, Ser. No. 322,994
 Claims priority, application Germany, Oct. 14, 1993, 43 35 017.8
 Int. Cl.⁶ A47C 1/027 12 Claims


U.S. Cl. 297—374
 1. A clamping mechanism for a seat carrier of a chair, comprising:
 a fixed part;
 a pivotable part;



said pivotable part being clamped and released by means of lamellae;
 first ends of said lamellae being rotatably anchored to a one of said fixed and said pivotable parts without play;
 second ends of said lamellae being rotatably anchored to another of said parts with play;
 a locking force of said second ends pushing against a lateral inside wall of a one of said parts;
 said lamellae, when locked, being released by at least one control lever acting against said locking force;
 said lamellae second ends having holes through which pass a clamping bolt that can slide, inside said clamping mechanism, horizontally and transversely toward said lamellae against a spring force that causes said locking force;
 said clamping bolt being fitted, on a first side of said clamping mechanism opposite to a second clamping mechanism side at which clamping action takes place, into a pressure sleeve of a diameter greater than a diameter of said lamellae second end holes;
 said clamping bolt passing through said second mechanism side; said clamping bolt having, outside said second mechanism side and at a distance from said second side, a first pressure spring and a mounting for said first pressure spring;
 said first pressure spring acting between said clamping bolt and said second side to push said clamping bolt outward, thereby directing said locking force to said lamellae;
 said control lever being pivotally mounted, outside said second side in a support rigidly anchored to said second side;
 a pressure nose bearing against a head of said clamping bolt; and said control lever urging said clamping bolt transversely and horizontally toward said lamellae against the force of said first pressure spring, behind said pressure sleeve, said clamping bolt having a stop that bears against said pressure sleeve at least when said clamping mechanism is activated
 said support has an alignment hole for said clamping bolt and a pair of lateral necks;
 said control lever surrounds said support with at least two flaps directed toward said support; and
 said control lever is rotatably mounted on said pair of lateral necks through recesses in said flaps.

5,588,707
FOLDING SEAT
 James Bolsworth, Sterling Heights, and Robert E. Adamson, Jr., Warren, both of Mich., assignors to General Motors Corporation, Detroit, Mich.
 Filed Nov. 14, 1995, Ser. No. 557,265
 Int. Cl.⁶ B60N 2/02 2 Claims

U.S. Cl. 297—378.12
 1. A vehicle seat comprising:
 a front leg having first and second ends, the front leg being pivotally attached to the vehicle floor generally adjacent the front leg first end;



a seat cushion with front and rear ends, the seat cushion front end being pivotally connected to the front leg second end;
 a rear leg with a second end pivotally connected adjacent the seat cushion rear end, the rear leg having a first end pivotally connected with respect to the vehicle floor, the rear leg first end having a first gear attached thereto;
 a sector link having first and second ends, the sector link second end pivotally connected with respect to the vehicle floor, the sector link second end having a second gear attached thereto, the second gear being meshed with the first gear;
 an intermediate link with a rear end and a front end, the intermediate link front end being pivotally connected to the sector link adjacent the sector link first end; and
 a seat back pivotally connected with respect to the vehicle floor and pivotally connected to the rear end of the intermediate link, whereby when folding the seat back forwardly, the seat cushion forward end is displaced forwardly to a position more adjacent to the vehicle floor.

5,588,708

ARRANGEMENT IN A FURNITURE MEMBER, ESPECIALLY A LEG SUPPORTING MEMBER FOR A CHAIR


Arne O. Rykken, Øystese, 5610 Øystese, Norway, and Søren Meinert, Bagergade 37, 5700 Svendborg, Denmark
 PCT No. PCT/N093/00154, § 371 Date Apr. 19, 1995, § 102(e)
 Date Apr. 19, 1995, PCT Pub. No. WO94/08494, PCT Pub.
 Date Apr. 28, 1994

PCT Filed Oct. 18, 1993, Ser. No. 416,866

Claims priority, application Norway, Oct. 19, 1992, 924044
 Int. Cl.⁶ A47C 7/50

U.S. Cl. 297—423.2

23 Claims



1. An arrangement for supporting a calf for a chair comprising a chair seat part and a back part, the calf-supporting arrangement comprising: a chiefly non-stiffened web-shaped portion which is supported by a moveable supporting/carrying device and which runs in a loop via at least one curved guide device attached to the moveable supporting/carrying device so that the web-shaped portion is continuously moveable between a shielded, inactive retracted position underneath the chair seat part and an active protruded calf-supporting position, chiefly flush with the chair seat part, the moveable supporting/carrying device further including a sheet-shaped supporting/carrying carriage arranged to support said chiefly non-stiffened web-shaped portion.

5,588,709

KNOCKDOWN SEAT



William J. Lewallen, Sr., 12026 Co. Rd L., Napoleon, Ohio
 43545

Filed Jun. 26, 1995, Ser. No. 494,953

Int. Cl.⁶ A47C 4/03

U.S. Cl. 297—440.19

2 Claims



1. A knockdown seat comprising: a back panel of substantially elongated planar configuration shaped so as to define a receiving aperture directed therethrough, the receiving aperture separating the back panel into a back rest extending in a first direction from the receiving aperture, and a front support leg extending in an opposite second direction from the receiving aperture; a seat panel shaped so as to define a rear support leg which extends through the receiving aperture of the back panel, and a seat bottom which resides adjacent to a front face of the back panel, wherein the rear support leg projects through the receiving aperture and extends from a rear face of the back panel and where the back panel is shaped so as to define longitudinal edges extending in a substantially spaced and parallel orientation along a length of the back panel, with the front support leg of the back panel being shaped so as to define a beveled engaging and extending substantially orthogonally between the longitudinal edges of the back panel and where the back rest is further shaped so as to define an upper edge extending substantially orthogonally with respect to the longitudinal edges of the back panel, and angled corner edges extending at an oblique angle between the upper edge and the respective longitudinal edges, wherein the angled corner edges permit shoulder blades of an individual to project beyond the back panel and where the seat bottom of the seat panel is shaped so as to define spaced and parallel longitudinal edges oriented a first transverse distance apart, the seat bottom further including a forward edge extending substantially orthogonally relative to the longitudinal edges of the seat bottom, with angled corner edges extending at an oblique angle between opposed ends of the forward edge and the respective longitudinal edges of the seat bottom and where the rear support leg of the seat panel further includes substantially spaced and parallel longitudinal edges which are spaced a second transverse distance apart, wherein the first transverse distance is substantially greater than the second transverse distance so as to define a reduced transverse dimension of the rear support leg relative to the seat bottom and where the seat panel includes abutment edges extending substantially orthogonally between the longitudinal edges of the seat bottom and the longitudinal edges of the rear support leg, the abutment edges engaging the front face of the back panel when the rear support leg of the seat panel is positioned through the receiving aperture of the back panel and where the rear support leg is shaped so as to define a beveled engaging end extending substantially orthogonally between the longitudinal edges thereof and where the receiving aperture is shaped so as to

accommodate corresponding shape of the rear support leg and where the rear support leg of the seat panel is shaped so as to define a planar upper surface oriented in a substantially spaced and parallel orientation to a planar lower surface, the support leg of the seat panel being further shaped so as to define orthogonal longitudinal edges extending substantially orthogonally in a spaced and parallel orientation from the upper surface, and beveled longitudinal edges of planar configuration extending at an oblique angle between the respective orthogonal edges and the lower surface increasing the rear support leg's strength.

5,588,710

WALL AVOIDING RECLINING FURNITURE MECHANISM


Glenn N. Wiecek, Shelbyville, Ky., assignor to L&P Property Management Company, Chicago, Ill.

Filed Feb. 28, 1995, Ser. No. 395,577

Int. Cl.⁶ A47C 15/00

U.S. Cl. 297—463.1

8 Claims



1. A linkage mechanism for an item of reclining furniture having a unitary seat and armrest frame structure, a backrest frame structure and a footrest frame structure each being movable with respect to each other between fully upright and fully reclined positions, said mechanism comprising:

- a stationary base mounting member;
- front and rear drive links pivotally connected at spaced locations to said base mounting member;
- a seat link having upper front and rear sections and a lower section therebetween;
- a seat supporting linkage assembly connected generally between said front and rear drive links and between said base mounting member and said seat link, said seat supporting linkage assembly including a seat actuating linkage assembly pivotally connected at one end to an upper portion of said front drive link and at another end to an upper portion of said rear drive link;
- a footrest linkage assembly connected to said front end of said seat link and movable between extended and retracted positions relative to said seat link; and,
- footrest actuating linkage including:

- a) a handle link having front and rear ends and being pivotal about an axis disposed between said handle link front and rear ends;
- b) a footrest drive link pivotally connected between said handle link rear end and said footrest linkage assembly;
- c) a ratio connecting link pivotally connected between said handle link front end and said front drive link; and,
- d) a torsion bar rigidly connected for rotation with said handle link about said axis, said torsion bar extending transversely to said linkage mechanism and adapted to connect with a handle link of a second linkage mechanism.

5,588,711

SIDE DUMPING CONTAINER


Daniel J. Hall, Voorbaai, South Africa, assignor to John Daniel Containers (Proprietary) Limited, George, South Africa
 Filed Mar. 16, 1995, Ser. No. 404,875

Claims priority, application South Africa, Mar. 16, 1994, 94/1833; Jun. 3, 1994, 94/3913

Int. Cl.⁶ B65D 88/54

U.S. Cl. 298—18

16 Claims



1. A container for use in the transportation of goods, which container is mountable on a load carrying vehicle and includes a floor;

a pair of opposed side walls each of which is supported for displacement about a pivotal axis adjacent its upper edge and one of which is hingedly connected adjacent its lower edge to the floor;

displacement means for displacing the floor and at least said one side wall between a rest position in which goods can be contained within the container and a discharge position in which goods contained within the container can be discharged therefrom; and

friction reducing floor support means supporting the floor to facilitate displacement thereof between its rest and discharge positions, the friction reducing floor support means including a plurality of longitudinally spaced apart transversely extending tracks and longitudinally spaced apart sets of rollers which run on the tracks.

5,588,712

DEVICE AND METHOD FOR LOWERING A DUMP TRUCK BED ACCORDING TO THE TRANSMISSION STATE OF THE VEHICLE

Louie J. Brooks, 1142 Littlevine Church Rd., Villa Rica, Ga.
 30180

Division of Ser. No. 100,681, Aug. 2, 1993, Pat. No. 5,452,942.

This application Jun. 21, 1995, Ser. No. 492,754

Int. Cl.⁶ B60P 1/16

U.S. Cl. 298—22 C


7 Claims

1. An improved dump vehicle, comprising;
 a dump bed whereby material is carried in and dumped from said dump bed;
 means for operating said dump bed;
 a powered wheel drive with a transmission;
 said transmission comprising pneumatic manual transmission control means for selectively shifting said transmission in reverse, neutral and various forward gears for corresponding selective operation of said powered wheel drive and;
 means responsive to said pneumatic manual transmission control means for automatically lowering said dump bed when said transmission is shifted to or above a predetermined gear wherein said predetermined gear may be set before the vehicle begins travel.




METHOD FOR MANUFACTURING BRUSHES

9 Claims



Tom D. Stevenson, 2413 Pelham Dr., Houston, Tex. 77019
Filed Dec. 20, 1995, Ser. No. 575,883


U.S. Cl. 299—5 12 Claims



- (a) pumping hot water into an underground Nahcolite (NaHCO_3)-rich formation to dissolve the Nahcolite (NaHCO_3);
- (b) returning the dissolved Nahcolite (NaHCO_3) to the surface of the formation in the form of a saturated brine pregnant liquor solution;
- (c) de-gassing the pregnant liquor solution under pressure in a pressure controlled system;
- (d) mixing the de-gassed pregnant liquor solution with a salt slurry containing an amount of NaCl sufficient to saturate the de-gassed pregnant liquor solution and reducing the temperature of the de-gassed pregnant liquor solution sufficient to saturate the de-gassed pregnant liquor solution with NaCl and to force precipitation of Nahcolite (NaHCO_3) out of the de-gassed pregnant liquor solution;
- (e) while mixing the de-gassed pregnant liquor solution with said salt slurry, injecting carbon dioxide (CO_2) into the mixture to facilitate precipitation and conversion of any sodium carbonate (Na_2CO_3) present into sodium bicarbonate (NaHCO_3);
- (f) dewatering and filtering the sodium bicarbonate (NaHCO_3) to form a sodium bicarbonate (NaHCO_3) filter cake, and washing the filter cake with fresh water to remove NaCl, sodium carbonate (Na_2CO_3), and other impurities as a salt-rich brine filtrate; and
- (g) drying the washed sodium bicarbonate (NaHCO_3) filter cake to produce a high grade of natural sodium bicarbonate (NaHCO_3).

NON-ROTATING WHEEL COVER ASSEMBLY

U.S. Cl. 301—37.25 **Int. Cl.⁶ B60B 7/20** **10 Claims**
1. A non-rotatable wheel cover assembly including mounting



a cup-like member secured to said wheel support assembly, said cup-like member having a top closure portion provided with an axial opening having a seal therein;

first attaching means including a member mounted on said inner surface of said wheel cover and extending inwardly therefrom:

second attaching means including a member having a first end disposed for secured relation with said wheel cover supporting member of said first attaching means and a second end disposed for secured relation with said distal end of said axle, said first attaching means disposed for secured relation with said member of said second attachment means for non-rotational support of said wheel cover, said member of said second attaching means including a first end and a second end, said first end disposed for extending through said seal of said cup-like member for secured relation with said wheel cover supporting member of said first attachment means and said second end disposed for secured relation with said distal end of said axle; and

wheel cover position retention means disposed on said wheel cover for retaining the orientation of said wheel cover in a stationary, non-rotating position.

**METHOD AND DEVICE FOR ELECTRONICALLY
CONTROLLING THE BRAKE SYSTEM OF A VEHICLE**
Werner Stumpe, Stuttgart, Germany, assignor to Robert Bosch
GmbH, Stuttgart, Germany


Filed Oct. 25, 1995, Ser. No. 548,025

Claims priority, application Germany, Oct. 26, 1994, 44 38 252.9

Int. Cl.⁶ B60T 8/18;13/66

U.S. Cl. 303—7

14 Claims



correcting the brake signal (eTr) for the trailer during braking by the correction value K, whereby said actual deceleration (Zact) substantially equals to said prescribed deceleration (Zdes).

applying brake pressure at the towing vehicle and the trailer based on the respective brake signals.

VALVE UTILIZING SHAPE MEMORY ALLOYS AND AN ANTI-LOCK BRAKE SYSTEM WITH THE VALVE

Sang K. Kim; PahngRoc Oh, and Hong J. Lee, all of Seoul, Rep. of Korea, assignors to Daewoo Electronic Co., Ltd., Seoul, Rep. of Korea


Filed Jul. 13, 1995, Ser. No. 501,935

Claims priority, application Rep. of Korea, Jul. 15, 1994,
94-17255

Int. Cl.⁶ F16K 31/66

U.S. Cl. 303—84.2

10 Claims



1. A valve comprising:

an electronic control unit for generating a first control current and a second control current;

a housing including a bore formed in an upper portion thereof having an inlet for introducing a fluid from a fluid supply and an outlet for discharging the fluid, and a compartment formed in a lower portion thereof;

a valve spool for closing the inlet at a first position of said valve spool and for opening the inlet at a second position of said valve spool;

biasing means for applying a biasing force to said valve spool to maintain said valve spool at the first position of said valve spool;

a shape memory alloy member for moving said valve spool to the second position of said valve spool while overcoming the biasing force of said biasing means when the first control current is supplied from said electronic control unit;

holding means for maintaining said valve spool at the second position of said valve spool when said valve spool moves to the second position of said valve spool by said shape memory alloy member; and

releasing means for releasing a state of said valve spool which is maintained at the second position of said valve spool by means of said holding means when the second control current is supplied from said electronic control unit, so that said valve spool is moved to the first position of said valve spool by said biasing means.

wherein said biasing means is a spring installed between a bottom surface of said compartment and a lower end of said valve spool.

said shape memory alloy member is installed between said valve spool and the bottom surface of said compartment is electrically connected to said electronic control unit, and has a shape of a linear wire, and

said holding means comprises:

a shaft transversely-installed within said compartment;

a plate pivotally mounted about said shaft;
a plate spring installed between an inner sidewall of said compartment and a lower surface of said plate for elastically supporting said plate; and
a ratchet formed at a lower end of said valve spool for being locked to said plate when said valve spool is positioned at the second position of said valve spool.


5,588,718 **VEHICLE HYDRAULIC BRAKE SYSTEM OPERATING WITH POWER ASSISTANCE**

Hermann Winner, and Alain Gaillard, both of Karlsruhe, Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

PCT No. PCT/DE94/01287, § 371 Date Jun. 16, 1995, § 102(e) Date Jun. 16, 1995, PCT Pub. No. WO95/14595, PCT Pub. Date Jun. 1, 1995

PCT Filed Nov. 2, 1994, Ser. No. 454,331
Claims priority, application Germany, Nov. 27, 1993, 43 40 467.7

Int. Cl.⁶ B60T 8/32; 8/48; 8/60; 13/12
U.S. Cl. 303—113.1 17 Claims



1. A vehicle hydraulic brake system which comprises a twin circuit emergency brake pressure source which can be put into operation by a pedal, wheel brakes which can be supplied from the emergency brake pressure source, emergency brake main conduits laid as a twin circuit and extending from the emergency brake pressure source to the wheel brakes and with a power-assisted brake device which can be controlled electrically by means of the pedal, said brake device has at least one fluid pump which can be supplied from a reservoir, a power reservoir which can be charged by said at least one pump, and at least one controllable first valve arrangement (29, 30) per brake circuit, for the selection of a brake pressure source, between the emergency brake pressure source and wheel brakes and said brake device has at least one electrically controllable second valve arrangement (37, 38, 39, 40, 37a, 37b, 37c), for brake pressure setting, a required brake pressure value generator (35) which can be controlled by means of the pedal, and a control unit (36) connected to the required brake pressure value generator (35), said control unit (36) controls the at least one second valve arrangement (37, 38, 39, 40, 37a, 37b, 37c) in order to generate brake pressures from the energy of the power source and to change these brake pressures, wherein the at least one first valve arrangement (29, 30) for selecting the brake pressure sources (6, 23) is arranged to open the associated emergency brake main conduits (12, 13) to a return conduit (59) which leads to the reservoir (7), wherein the at least one second valve arrangement (37, 38, 39, 40, 37a, 37b, 37c) is connected to the emergency brake main conduits (12, 13) and at least one of the wheel brakes (8, 9, 10, 11) to set brake pressures while relaying a pressure medium from the power source (23) and is arranged in such a way that said at least one second valve arrangement connects the emergency brake main conduits (12, 13) to the wheel brakes (8, 9, 10, 11) when no electrical current is applied to the at least one electromagnet (71, 73, 83) and separates the wheel brakes (8, 9, 10, 11) from the power source (23) and, in power-assisted brake operation, connects the wheel brakes (8, 9, 10, 11) to the power source (23)


for the purpose of a brake pressure increase and to the emergency brake main conduits (12, 13), which can be opened to the reservoir (7), for the purpose of brake pressure reduction.

5,588,719 **ANTI-WHEEL-LOCK BRAKING SYSTEM FOR A MOTOR VEHICLE**

Francois Bailleux, Val D'Alban, France, assignor to Automobiles Peugeot, Paris, and Automobiles Citroen, Neuilly Sur Seine, both of France

Filed Aug. 30, 1994, Ser. No. 297,884
Claims priority, application France, Sep. 2, 1993, 93 10466
Int. Cl.⁶ B60T 8/88

U.S. Cl. 303—122.04 14 Claims




1. An anti-lock braking system for a motor vehicle having front and rear wheels, comprising:
a main electronic controller including (i) wheel speed inputs and (ii) means to detect a failure of the main electronic controller and to generate a signal independently of wheel speed inputs when the main electronic controller fails; and
an emergency electronic controller independent of the main electronic controller and independent of wheel speed inputs, having means to directly decrease braking of the rear wheels when the means to detect a failure generates a signal that a failure of the main electronic controller is detected.

5,588,720 **CIRCUIT ARRANGEMENT FOR A BRAKE SYSTEM WITH ANTI-LOCK SYSTEM AND/OR TRACTION CONTROL**

Klaus-Peter Mattern, Beilstein, Germany, assignor to Robert Bosch GmbH, Stuttgart, Germany

Filed Dec. 29, 1995, Ser. No. 580,891
Claims priority, application Germany, Jan. 5, 1995, 195 00 188.5

Int. Cl.⁶ B60T 8/32; B60K 28/16
U.S. Cl. 303—122.08 15 Claims



1. A circuit arrangement for a brake system with anti-lock system and/or traction control with input circuits for conditioning


sensor signals, which represent rotational behavior of individual vehicle wheels, with output circuits for outputting control signals, with control circuits for processing the conditioned sensor signals and for generating control signals, with monitoring circuits to which the conditioned sensor signals can be fed, for processing a model algorithm which constitutes a simplified simulation of the control algorithm, with comparator circuits for comparing the signals of the control circuits with the corresponding signals of the monitoring circuits and with circuits for switching off the control in the event of a fault, wherein both the control circuits (16) and the monitoring circuits (17) comprise watchdog circuits (23, 24) for continuously processing a watchdog algorithm which tests the functioning of the control and monitoring circuits (16, 17) and comparator circuits (25, 26) for comparing the results of the processed watchdog algorithms, and wherein the output circuits (21, 22) only enable the control if both the control signals output by the control circuits (16) correspond to the corresponding signals of the monitoring circuits (17) and the results of the watchdog algorithms respectively processed in the watchdog circuits (23, 24) correspond.

5,588,721 **VIBRATION ANALYSIS OF THE ROTATING WHEEL FOR CONTROLLING ANTI-LOCK BRAKING OPERATION**

Katsuhiko Asano; Masaru Sugai; Hiroyuki Yamaguchi, and Takaji Umeno, all of Aichi-ken, Japan, assignors to Kabushiki Kaisha Toyota Chuo Kenkyusho, Aichi-ken, Japan

Filed Aug. 28, 1995, Ser. No. 519,965
Claims priority, application Japan, Aug. 29, 1994, 6-203510; Jun. 5, 1995, 7-138306

Int. Cl.⁶ B60T 8/66
U.S. Cl. 303—163 23 Claims




1. An anti-lock brake controlling apparatus comprising:
detecting means for detecting a vibration characteristic of a wheel which is rotating at a certain speed; and
controlling means for controlling a mean braking force acting on the wheel on the basis of the detected vibration characteristic such that a slip ratio between a tire and a road surface is not larger than a value at which a coefficient of friction between the tire and the road surface substantially reaches a peak value.

5,588,722 **BRAKING SYSTEM HAVING MECHANISM FOR CONTROLLING RESISTANCE OF FLUID FLOW FROM PUMP INTO LOW-PRESSURE BRAKE CYLINDER DEPENDING UPON PRESSURE DIFFERENCE BETWEEN LOW-PRESSURE AND HIGH-PRESSURE BRAKE CYLINDERS**

Noboru Noguchi, Nagoya, Japan, assignor to Toyota Jidosha Kabushiki Kaisha, Toyota, Japan

Filed Oct. 26, 1995, Ser. No. 548,894
Claims priority, application Japan, Nov. 11, 1994, 6-277416
Int. Cl.⁶ B60T 13/00

U.S. Cl. 303—186 9 Claims




1. A braking system comprising:
a reservoir for storing a working fluid;
a pump which is operated to pressurize the working fluid received from the reservoir so as to intermittently deliver the pressurized fluid;
two brake cylinders to which the pressurized fluid delivered from the pump is distributed;
an electrically operated pressure control device connected to the reservoir, pump and two brake cylinders;
a controller for electrically controlling the electrically operated pressure control device to electrically control the pressures in the two brake cylinders; and
a flow resistance control mechanism provided in a pump passage connecting said pump and said two brake cylinders, said flow resistance control mechanism controlling flows of the working fluid during operation of said pump such that when a difference between pressures of the fluid in said two brake cylinders is relatively large, a resistance of flow of the fluid from the pump toward a low-pressure cylinder of said two brake cylinders is increased relative to a resistance of flow of the fluid from the pump toward a high-pressure cylinder of said two brake cylinders.

5,588,723 **ADJUSTABLE KITCHEN APPLIANCE GARAGE**

B. Jerry Sivin, Parsons Pine Products, Inc. P.O. Box 670, Ashland, Oreg. 97520

Filed Feb. 13, 1995, Ser. No. 387,256
Int. Cl.⁶ A47B 45/00

U.S. Cl. 312—205 16 Claims
1. A variable height storage device for placement between a lower surface, an upper surface and a rear surface, comprising:
a) a left wall having a left wall front portion with a left wall front portion lip extending therefrom;
b) a right wall having a right wall front portion with a right wall front portion lip extending therefrom, the right wall being displaced a distance from the left wall and defining a storage space therebetween;



- c) a cross member connecting the left wall to the right wall and having a left end and a right end, the left end of the cross member being attached to the left wall front portion lip and the right end of the cross member being attached to the right wall front portion lip;
- d) a retractable door disposed within the left wall front portion lip and the right wall front portion lip capable of moving between a closed position covering the storage space and an open position; and
- e) a shroud removably mounted to the cross member and joining the variable height storage device to the upper surface so that the space between the variable height storage device and the upper surface is aesthetically enclosed while providing support for the mounted variable height storage device.


5,588,724

CAMP KITCHEN CABINET

David Emery, 108A Taylortown Rd., Boonton, N.J. 07005
Filed Apr. 10, 1995, Ser. No. 419,440
Int. Cl.⁶ A47B 77/08

U.S. Cl. 312—236

4 Claims



1. A camp kitchen cabinet comprising, a housing having a first side wall spaced from a second side wall, a top wall spaced from a bottom wall, and a front wall spaced from a rear wall, and at least one intermediate wall extending between the top wall and the bottom wall, and

- a plurality of shelf plates, wherein one of said plurality of shelf plates extends from the at least one intermediate wall to the first side wall to define a storage support member, and a further shelf plate of said plurality of shelf plates extends from a further intermediate wall to the second side wall to define a first storage cavity between the further shelf plate and the top wall, and a second storage cavity between the further shelf plate and the bottom wall, with a storage member slideably received within the first storage cavity, and
- a cooler container slideably received within the second storage cavity, and
- retaining means extending from the cooler container and through the cabinet second side wall for selectively securing the cooler container within the second storage cavity when the cooler container is complementarily received within the second storage cavity, and
- a top wall plate, wherein the top wall plate is arranged to include a hinge member hingedly securing the top wall plate to the rear wall, and the top wall plate is coextensive with the top wall in a first position and is substantially coplanar with the top wall in a second position, a continuous flange integrally secured to the top wall plate, the continuous flange extending about a periphery of the top wall plate, at least one hook member secured to the cabinet front wall, at least one further hook member secured to the continuous flange, and at least one resilient cord member, the resilient cord member having a cord hook at each end thereof for securement to each said hook to extend over the first storage cavity and the second storage cavity.


5,588,725

DECORATIVE MULTI-PURPOSE EMERGENCY CABINET

Carmella L. Frank, 112 Overlook Dr., East Islip, N.Y. 11730
Filed Aug. 30, 1995, Ser. No. 521,523
Int. Cl.⁶ A47B 67/02

U.S. Cl. 312—245

1 Claim



1. A decorative emergency cabinet mounted upon a vertical flat member in an upright position for holding various emergency type articles in one place, so that during an emergency situation the articles can be retrieved quickly for immediate use comprising:
- a) a flat, horizontal top panel, a pair of flat, vertical side panels, and a rear panel forming an open front compartment;
- b) a shelf within said compartment about a third of the distance up from said bottom panel dividing said compartment into upper and lower chambers;
- c) a hinge along one free edge of one side panel between said top panel and said shelf, and a door connected to said hinge to open and close the upper chamber;
- d) planter means comprising said bottom panel extending from said rear panel a sufficient distance beyond said door when closed so as to form a planter in front of said lower chamber

- and forward of said door when closed for holding flowering house plants therein, said side panels being L-shaped and a vertical front panel to enclose the sides of said planter;
- e) means separating said planter from said lower chamber comprising a narrow partition on the bottom panel extending between the side panels and being of the same height as said planter for gaining access to said lower chamber;
- f) said door including a transparent pane with a decorative lattice thereon.

5,588,726

CABINET WALL BOARD ASSEMBLY


Shang-Ming Lee, 5F-1, No. 3, Lane 179, Yen-Ping S. Rd., Taipei, Taiwan

Filed Oct. 24, 1995, Ser. No. 547,203

Int. Cl.⁶ A47B 47/00

U.S. Cl. 312—263

1 Claim



1. A cabinet wall board assembly comprising:
- a horizontal board formed with a connecting channel;
- multiple adjoining members each having a first end for inserting into the connecting channel and a second end disposed with multiple equally spaced tenons, each tenon having an arch bottom, an end face and a root portion, the tenon being tapered from the end face to the root portion, each said adjoining member further having an engaging face under the tenons; and
- a wall board having an upper end disposed with multiple dovetail mortises corresponding to the tenons of the adjoining members and having a supporting face on the inner side of the dovetail mortises for engaging with the engaging faces of the adjoining members.

5,588,727

DESKTOP ORGANIZER FOR AN OFFICE WORKSTATION

Amos D'Agaro, Udine; Adriano Marino, Novara, and Andrea Venturini, Udine, all of Italy, assignors to Exponent Italia S.r.l., Udine, Italy


Filed Apr. 5, 1995, Ser. No. 417,114

Claims priority, application Italy, Nov. 3, 1994, PN940039 U
Int. Cl.⁶ A47B 97/00

U.S. Cl. 312—283

20 Claims

1. A desktop organizer for organizing an office workstation that includes at least a monitor of a computer, said desktop organizer comprising: a container in the form of a box having a top, a bottom, a front end, a rear end and first and second opposite sides, the front end and said first side of the container being open to the interior of the container, and the container including a rigid member having a substantially planar upper surface defining the top of the container, whereby a computer monitor can be supported on top of the container; a first runner disposed inside the container and extending in a first direction between the front end and the rear end of the container; a second runner disposed inside the container and



- extending in a section direction between the first and second sides of the container, said second direction being orthogonal to said first direction; and a drawer housed within said container and supported by said first and second runners so as to be pullable out of and pushable into the container through both the front end of the container and said first side of the container.

5,588,728


PORTABLE DISK DRIVE CARRIER AND CHASSIS

Robert A. Eldridge, Beaverton; Ed J. Unrein, Lake Oswego; David L. Brown, Milwaukee, and Scott L. Noble, Beaverton, all of Oreg., assignors to Intel Corporation, Santa Clara, Calif.

Continuation of Ser. No. 346,039, Nov. 29, 1994. This application Dec. 29, 1995, Ser. No. 580,489
Int. Cl.⁶ A47B 95/02; H01R 13/62

U.S. Cl. 312—332.1

14 Claims



1. A disk drive carrier adapted to be housed in a disk drive chassis comprising:
- an integrated carrying handle and locking mechanism suitable for handling said disk drive carrier and for providing a one-hand activated locking mechanism for locking and unlocking said disk drive carrier in the disk drive chassis;
- wherein said carrying handle includes:
- first and second swing arms each having a first end, said swing arms for pivotally mounting said carrying handle to said drive bay;
- a single cross member having opposing ends, said single cross member being coupled to said first ends of said first and second swing arms proximal to said opposing ends of said single cross member; wherein said first and second swing arms have second ends, said second ends each having locking post engagement grooves;
- first and second axially aligned cylindrical attachment posts protruding from said first and second swing arms, respectively; and
- a drive bay for receiving and holding a hard disk drive, said drive bay including first and second opposing side walls, each side wall having a front end and defining an aperture, said aperture aligned proximal to said front end for receiving attachment posts associated with the carrying handle; wherein


said apertures each define a flexible locking member which allows for the pivotal locking of said attachment posts.

5,588,729 HARDWARE DEVICE FOR THE VERTICAL ADJUSTMENT OF DRAWERS

Horst Berger, Bielefeld, Germany, assignor to MEPLA-Werke Lautenschläger GmbH & Co. KG, Germany
Filed Sep. 14, 1995, Ser. No. 527,872
Claims priority, application Germany, Sep. 15, 1994, 44 32 820.6

Int. Cl.⁶ A47B 88/00
U.S. Cl. 312—334.4

8 Claims



1. A hardware device for the vertically adjustable mounting of a drawer mounted by means of drawer slides in a furniture carcass interior, in which the drawer slides have each one guide rail to be fastened in the carcass interior and one runner rail provided on the drawer, said runner rail being provided with roller means.

the hardware device comprising a flat adjuster of substantially sector-shaped outline for mounting for rotation about a vertical axis towards an end of a drawer slide adjacent a front end of a furniture carcass, the adjuster being shaped as a wedge increasing in thickness from an approximately radial defining edge in a direction of rotation towards a rear edge of the adjuster, and wherein

the adjuster is rotatable about a vertical axis and is insertable between a runner rail of a drawer slide and a bottom face of a drawer bottom to thereby effect a vertical adjustment of the drawer bottom with respect to the runner rail

wherein a lever arm acting as a handle extends outwardly from an outer circumference of the adjuster, running radially to the axis of rotation, and

the adjuster being oriented such that the substantially radially running edge of the adjuster in an initial position lies directly beside the runner rail, running in a lengthwise direction of the runner rail

wherein the adjuster is journaled in a separately formed mounting device attached to the drawer-front end of the runner rail.

5,588,730 FITTING

Erich Röck, Höchst, and Edgar Huber, Hard, both of Austria, assignors to Julius Blum Gesellschaft m.b.H., Höchst, Austria


Filed Jan. 13, 1995, Ser. No. 372,328
Claims priority, application Austria, Jan. 17, 1994, A 77/94
Int. Cl.⁶ A47B 88/00

U.S. Cl. 312—348.2

14 Claims

1. A fitting for use in attaching a rear wall of a drawer to a side part of the drawer, said fitting comprising:

a holding part including a flange to extend in a direction to be parallel to a rear surface of the rear wall and to be attached thereto, and a housing portion integral with said flange and



extending laterally therefrom in a direction such that when said flange is attached to the rear surface of the rear wall said housing portion is positioned at a location of a respective lateral end of the rear wall to form a lateral extension thereof; said housing portion including a closure wall extending parallel to said flange in a direction to form a closed lateral continuation of a front surface of the rear wall, a member connecting said flange to one lateral end of said closure wall, a side wall integral with an opposite lateral end of said closure wall and defining therewith a corner, said side wall extending perpendicular to said closure wall in a direction to be rearward of the drawer, and locating holes formed in said side wall; and a supporting part to be attached to the side part of the drawer, said supporting part having extending laterally therefrom fixing lugs to engage in said locating holes to thereby attach said holding part to said supporting part with said housing portion positioned laterally between the side part and the rear wall of the drawer.

5,588,731

REFRIGERATOR DOOR CONSTRUCTION


Christopher G. Schmidt, Evansville; Michael H. Fisher, Princeton, both of Ind.; Amilton F. de Almeida, and Edson T. Tanl, both of Sao Paulo, Brazil, assignors to Whirlpool Corporation, Benton Harbor, Mich.

Filed Jul. 17, 1995, Ser. No. 503,358

Int. Cl.⁶ A47B 96/04; S1/00

U.S. Cl. 312—405

9 Claims



1. In the construction of a refrigerator door, the door having an external panel and an inside liner with an insulation material applied there between, the improvement comprising:
said external panel having a front wall and side walls defining a C-shaped cross section with the side walls defining the perim-

eter of the panel and being generally perpendicular to the front wall and terminating in edge portions to define an open face of the panel;

a border trim for applying around the perimeter of said panel, said border trim having a connection means for connecting to said edge portions, and said border trim further having a flange portion extending inwardly from said side walls;

a gasket having a portion disposed between the liner and the border trim and lying adjacent the flange; and

wherein the insulation material structurally unitizes the panel, border trim, liner and gasket and presses said portion of the gasket against the flange to prevent the escape of the insulation material between the border trim and the liner.

5,588,732

VIDEO LIGHTING APPARATUS AND ELECTRODE APPARATUS THEREFOR

Yuu Sasaki, Chiba; Junichi Iwasawa, and Masahiro Yamada, both of Kanagawa, all of Japan, assignors to Sony Corporation, Japan, and Asahi Research Corp., both of Japan
Continuation of Ser. No. 881,799, May 12, 1992, abandoned.


This application Jul. 1, 1994, Ser. No. 269,616

Claims priority, application Japan, May 17, 1991, 3-113512

Int. Cl.⁶ G03B 15/021

U.S. Cl. 362—10

9 Claims



1. A lighting apparatus attachable to a video camera comprising:
a lighting apparatus body attachable to said video camera;
illumination means associated with said lighting apparatus body for providing illumination, said illumination means being arranged so as to moveably project from a first position close to said lighting apparatus body to a second position distance from said lighting apparatus body by a predetermined distance;

spring-biasing means associated with said lighting apparatus body for spring-biasing said illumination means in said second position;

engaging means associated with said lighting apparatus body for engaging said illumination means at said first position;

a mode switch means associated with said lighting apparatus body for selecting an automatic mode and a manual mode;

releasing means associated with said lighting apparatus body for releasing said engaging means and for switching said illumination means on in accordance with said movement of said illumination means, from said first position to said second position, when said releasing means releases said engaging means at the time of said manual mode; and

a current detecting circuit means associated with said lighting apparatus body for detecting current of an internal circuit of said video camera at the time of said automatic mode; wherein said illumination means lights according to the detection of said current detecting circuit means.

5,588,733

HEAD LAMP DEVICE FOR VEHICLE

Shinichirou Gotou, Saitama-ken, Japan, assignor to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan



Filed Jun. 7, 1995, Ser. No. 472,225

Claims priority, application Japan, Jan. 17, 1995, 7-020898

Int. Cl.⁶ B60Q 1/12

U.S. Cl. 362—37

17 Claims



1. A head lamp device for a vehicle in which a lighting region in front of the vehicle can be adjusted in rightward and leftward directions,

said device comprises:

direction indicating signal outputting means for detecting an operation of a winker device and outputting a direction indicating signal;

steering signal outputting means for detecting a steering angle of a steering device and outputting a steering angle signal;

map information outputting means for outputting map information including road data;

present position detecting means for detecting a present position of a proper vehicle on the map; and

control means for inputting said direction indicating signal, steering angle signal, map information and information of the present position and adjusting the lighting region of said head lamp based thereon, and

said control means selects a first control mode when said direction indicating signal is inputted; a second control mode for adjusting the lighting region in response to said steering angle when said first mode is not selected and said present position is not found on the road data of said map information or a steering angle of said steering angle exceeds a predetermined range; and a third control mode for adjusting the lighting region in compliance with an expectation of a forward road shape in a traveling direction of the vehicle in reference to said map information and the present position when said first and second control modes are not selected.

5,588,734

SIDE LIGHT FOR IN-LINE ROLLER SKATE


John A. Talamo, 131 Seafare, Laguna Niguel, Calif. 92677, and
Angela C. Hoy, 222 Prospect Ave., Newport Beach, Calif.
92663

Filed Jul. 6, 1995, Ser. No. 498,575

Int. Cl.⁶ A63C 17/26

U.S. Cl. 362—61

7 Claims



1. A side light for use in combination with an in-line skate having a foot-receiving portion, a frame beneath the foot-receiving portion, and a plurality of wheels supported by the frame, said side light comprising:

- a power unit having a housing defining an interior cavity, a rear lens, and an on/off switch;
- an attachment strap for securing said housing to the foot-receiving portion of the in-line skate;
- battery power means within said interior cavity coupled to said on/off switch;
- at least one rear light element supported by said housing and coupled to said power unit for illuminating said rear lens;
- an elongated tube defining a passage therein and formed of a light-transmissive material;
- a plurality of side light elements supported within said passage and coupled to said battery power means; and
- attachment means for attaching said elongated tube to the frame of the in-line skate.

5,588,735

STICK

Noboru Harada, 2-25-11, Chuo, Edogawa-ku, Tokyo, Japan

Filed May 18, 1995, Ser. No. 443,670

Claims priority, application Japan, Jun. 14, 1994, 6-154334

Int. Cl.⁶ A45B 3/04

U.S. Cl. 362—102

2 Claims

1. A stick comprising a bar having a handle portion at an upper end of said bar, a power source battery contained in said bar, an illuminating light source connected to said power source battery for illuminating an area close to feet of a user having said stick, a warning source connected to said power source battery for drawing a third person's attention, a transparent cover disposed on a front surface of said illuminating light source, and a control circuit for supplying a drive signal to each of said sources by opening/closing a switch of a feed line from said power source battery, wherein a drive signal is output from said control circuit on the basis of an AND logic of an output signal from each of a brightness sensor for detecting a brightness range and a sensible sensor for detecting a user's body temperature.



5,588,736

SELF-LIGHTED SAFETY HELMET


Raymond E. Shea, Sr., 1030 Stafford St., Rochdale, Mass.
01542

Filed Oct. 27, 1995, Ser. No. 549,326

Int. Cl.⁶ F21L 15/14

U.S. Cl. 362—106

19 Claims



1. A self-lighted safety helmet, comprising:
a helmet body with a phosphorescent outer shell member; and
a radiation source providing radiation to said outer shell capable of inducing phosphorescence of said outer shell, to project luminescence from the helmet to increase helmet visibility.

5,588,737

MODULAR RECESSED LIGHTING SYSTEM

Raymond J. Kusmer, Yorba Linda, Calif., assignor to Thomas Industries, Inc., Los Angeles, Calif.


Filed Nov. 10, 1994, Ser. No. 339,193

Int. Cl.⁶ F21S 1/02

U.S. Cl. 362—148

16 Claims

1. A modular recessed light fixture, comprising:
a plaster frame defining a major plane;
a junction box mounted on said plaster frame, said junction box defining a first face;
means for selectively attaching a junction face plate at said first face of said junction box, said means for selectively attaching comprises a recess in said plaster frame, said recess lying in said major plane; and



a junction face plate selectively attachable at said first face by said means for selectively attaching, a tab on said junction face plate for selective insertion into said recess in said major plane of said plaster frame, said junction face plate including means for adapting said junction box to an installation configuration wherein said installation configuration comprises a component selected from the group comprising: a transformer, a thermal protector, a ballast and a conduit connector.

5,588,738

LANTERN


Rudy B. Meoli, 1660 Orchard Dr., Placentia, Calif. 92670

Filed Jul. 10, 1995, Ser. No. 500,050

Int. Cl.⁶ F21L 7/00

U.S. Cl. 362—184

11 Claims



1. An elongate vertically extending lantern including upper and lower housing sections and a central elongate vertically extending tubular globe with spaced apart oppositely disposed transparent front and rear walls, spaced apart oppositely disposed transparent side walls and upper and lower ends sealingly engaging the upper and lower housing sections, a plurality of spaced apart vertically extending fluorescent tubes positioned within the globe and having upper and lower ends that are within the upper and lower housing sections, a battery power supply within the lower housing section, electric circuit means connecting the battery power supply with the lower ends of the tubes, a manually operable multi-position switch connected with the power supply by the electric circuit means and having a normal open position and a first closed position, electric conductors connecting the first closed position of the switch to the upper ends of the tubes, a flat vertically and laterally extending, forwardly disposed, reflector panel positioned within the rear portion of the lantern and selectively shiftable between a down stored position within the lower housing section to an up operating

position within the globe, rearward of the tubes and forward of the rear wall and of the globe.

5,588,739

FLASHLIGHT WITH SIGNALING LAMP

Masashi Nakao, Tokyo, Japan, assignor to Kyoyu Corporation,
Tokyo, Japan

PCT No. PCT/JP94/00529, § 371 Date Dec. 14, 1994, § 102(e)

Date Dec. 14, 1994, PCT Pub. No. WO94/27085, PCT Pub.

Date Nov. 24, 1994


PCT Filed Mar. 30, 1994, Ser. No. 356,208

Claims priority, application Japan, May 11, 1993, 5-133003

Int. Cl.⁶ F21L 11/00

U.S. Cl. 362—205

6 Claims



1. A flashlight with signaling lamp comprising:

a main body (10) comprising a tubular casing (11) having a space sufficient to accommodate a battery (31, 32), a housing (14) for attaching a lamp bulb (40), and a rotary switch (13, 130) provided between the tubular casing and the housing; and

a slide body (20) comprising an illuminating tubular portion (21) and a signaling tubular portion (22, 220), said illuminating tubular portion accommodating a transparent plate (24) which is fitted to an upper end of the illuminating tubular portion and a reflection plate positioned (25) for irradiating light through the transparent plate and said signaling tubular portion having an upper end being connected to a lower end of the illuminating tubular portion and comprised of a transparent material,

wherein said rotary switch includes a fixed portion (13A, 132, 136, 139) fixed on the tubular casing and a rotary portion, associated with the slide body, (13B, 131, 133, 134, 135, 137) rotating with a central axis (X) in a length direction of the main body being as axis of rotation and constitutes a power supply path for delivering a power from the battery accommodated within the tubular casing to the lamp bulb, said power supply path being ON/OFF controlled by rotating the rotary portion, and

wherein the slide body is a slidably attached to an outside of the main body so that the transparent plate is directed toward the housing and so that said slide body can slide along said central axis and can rotate with said central axis as axis of rotation, said slide body including engagement means (22C, 220C) for transmitting a rotational movement of the slide body to the rotary portion of the rotary switch.

5,588,740

BACKLIGHT DEVICE FOR A LIQUID CRYSTAL DISPLAY FACILITATING THE REPLACEMENT OF A LAMP THEREOF


Koji Kasuga, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Oct. 28, 1994, Ser. No. 331,192

Claims priority, application Japan, Oct. 29, 1993, 5-292506
Int. Cl.⁶ F21V 23/00

U.S. Cl. 362-221

10 Claims



1. A backlight device for a liquid crystal display comprising: a lamp having a first electrode and a second electrode at opposite ends thereof; and a lamp reflector made of a conductive material for reflecting light issuing from said lamp, said lamp reflector being electrically connected to a ground terminal of a power source at one end and mating with said first electrode of said lamp at the other end, wherein said second electrode is electrically connected to a positive terminal of said power source, and wherein said other end of said lamp reflector is squeezed inward in a funnel configuration for mating with said first electrode of said lamp.

5,588,741

LAMP HOLDER ASSEMBLY


Angus Huang, 7F, No. 15, Alley 17, Lane 79, Sec. 2, Kee-Lung Rd., Taipei, Taiwan

Filed Oct. 13, 1995, Ser. No. 542,502

Int. Cl.⁶ F21V 31/02

U.S. Cl. 362-267

3 Claims



1. A lamp holder assembly comprising an upper shell, a hanger connected to said upper shell, an electric wire, a wire holder mounted on said upper shell to hold said electric wire, a ceramic socket fixed to the inside of said upper shell and connected to said electric wire to hold a lamp bulb, a bottom shell mounted around said ceramic socket and fixed to said upper shell, and a lampshade

retained between said upper shell and said bottom shell around the lamp bulb, wherein: said upper shell is made of hollow, cap-like structure, comprising an outward flange around the periphery of a bottom end thereof, an inner thread, a cylindrical top section, which holds said wire holder, two screw holes on said cylindrical top section at two opposite sides, and two screws respectively threaded into said screw holes and stopped against said electric wire at two opposite sides to secure said hanger in place and to hold down said electric wire; said bottom shell is made of cylindrical shape fitting said upper shell, having an outer thread threaded into the inner thread of said upper shell, an outward flange attached to the outward flange of said upper shell to hold a top side of said lampshade between, and a center through hole, which receives said ceramic socket.

5,588,742

INTERNALLY ILLUMINATED SIGN


Gregory J. Subisak, Gahanna, Ohio, and Douglas S. Hammond, Vicksburg, Mich., assignors to Holophone Corporation, Newark, Ohio

Division of Ser. No. 961,262, Oct. 15, 1992, Pat. No. 5,355,291, which is a continuation-in-part of Ser. No. 646,917, Jan. 28, 1991, Pat. No. 5,188,453. This application Jun. 29, 1994, Ser. No. 267,970

Int. Cl.⁶ F21V 11/00

U.S. Cl. 362-291

8 Claims



1. In a sign having at least two spatially separated faces adapted to be illuminated from light radiated into the interior of said sign between said spatially separated faces, said at least two spatially separated faces including at least one translucent face, the improvement comprising:

a luminaire mountable on the periphery of said sign having means for providing light in the region between said spatially separated faces, means for eliminating bright spots on said at least one translucent face adjacent said luminaire, said elimination means comprising a plurality of spatially separated painted louvers, and means for disbursing light in the interior of said sign between said spatially separated faces to uniformly illuminate at least one translucent face.

5,588,743

LUMINAIRES

Kevin Mayo, and Mark Wiltshire, both of Nr Banbury, United Kingdom, assignors to Menvier (Electronic Engineers) Ltd., Banbury, United Kingdom

Filed Oct. 17, 1994, Ser. No. 324,761

Claims priority, application United Kingdom, Nov. 17, 1993, 9323663

Int. Cl.⁶ F21V 7/12

U.S. Cl. 362-299

8 Claims

1. A luminaire comprising: a light source; and a light redirecting element disposed behind the light source to cause light impinging upon the redirecting element from the light source to be redirected back past the light source at a chosen angle, the redirecting element being a Fresnel type

5,588,745

METHODS AND APPARATUS FOR MIXING BONE CEMENT COMPONENTS USING AN EVACUATED MIXING CHAMBER



Kazuna Tanaka, Cos Cob; Jeffrey Kapec, Westport, both of Conn., and Allan B. Chochinov, New York, N.Y., assignors to Howmedica

Filed Sep. 2, 1994, Ser. No. 300,045


Int. Cl.⁶ B01F 13/06; 15/02

U.S. Cl. 366-130

73 Claims



lens having a first plurality of inclined faces at a lens surface nearest the light source and a second plurality of inclined faces at a lens surface furthest from the light source.



5,588,744

GALLERY RING ASSEMBLIES FOR CHANDELIERS

John M. Lucas, Cadyville; Arnold Schonbek, and Georg Bayer, both of Plattsburgh, all of N.Y., assignors to Schoenbek Worldwide Lighting, Inc., Plattsburgh, N.Y.

Filed Jan. 6, 1995, Ser. No. 369,384

Int. Cl.⁶ F21S 1/06

U.S. Cl. 362-405

22 Claims



1. A gallery ring assembly for a decorative lighting chandelier, comprising:

a plurality of decorative members, each having a mounting hole; and

a gallery ring having a plurality of locations for mounting said decorative members, each of said mounting locations including a mounting hole, each of said decorative members being secured to said gallery ring by a mounting screw that passes through the mounting hole in said decorative member and the mounting hole in said gallery ring, each of said decorative members and each of the mounting locations on said gallery ring having interlocking elements to prevent rotation of said decorative member about said mounting screw relative to said gallery ring.

37. A mixing device for mixing a powdered and a liquid component comprising: (a) a first evacuated container containing a powdered component mass; (b) a second container containing a liquid component; (c) means for connecting said first and second containers, after the evacuation of said first container, allowing said liquid component to be drawn into said first container, and (d) means for introducing said liquid component into said first container in a manner which substantially wets the powdered component mass stored therein by wetting said powdered component mass from outside and from within the stored powdered component mass.

5,588,746

APPARATUS FOR THERMAL ANALYSIS

Masao Minobe, Tsuchiura; Noboru Shiraga, Tsukuba, and Nobutaka Nakamura, Gotenba, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, and Seiko Instruments, Inc., Tokyo, both of Japan


Filed Jul. 19, 1994, Ser. No. 277,046

Claims priority, application Japan, Jul. 22, 1993, 5-181639

Int. Cl.⁶ G01N 25/00; 5/00; 25/20

U.S. Cl. 374-10

8 Claims



1. An apparatus for thermal analysis comprising a sample chamber having a portion for a sample to be analyzed at which the

sample is placed and a signal detection chamber provided with a signal detection member which detects a physical change or a chemical change in the sample during the thermal analysis, wherein

the signal detection chamber comprises an inlet port through which a purging gas is supplied into the signal detection chamber,

a partition member having a passage through which the purging gas passes is provided between the sample chamber and the signal detection chamber so as to separate the sample chamber from the signal detection chamber, and

the sample chamber is provided with an inlet port through which an atmosphere gas is supplied into the sample chamber so that the sample is subjected to a predetermined atmosphere comprising the atmosphere gas, and the sample chamber is provided with an outlet port through which the atmosphere gas and the purging gas are withdrawn to the outside of the apparatus, wherein the partition member is so constructed that a ratio of a cross sectional area of the purging gas passage (A) to a cross sectional area of the partition member (B) which is adjacent to the sample chamber on one side thereof and also to the signal detection chamber on the other side thereof is not larger than $\frac{1}{2}$ and not smaller than $\frac{1}{100}$.

5,588,747

MEASURING CUP WITH EXTERNALLY-MOUNTED LIQUID CRYSTAL THERMOMETER


Terry D. Blevins, 5808 Tree Mountain Pkwy., Stone Mountain, Ga. 30083

Continuation-in-part of Ser. No. 252,588, Jun. 1, 1994, abandoned. This application Jan. 5, 1995, Ser. No. 369,678

Int. Cl.⁶ G01K 1/14; 13/12

U.S. Cl. 374—157

2 Claims



1. A device adapted for use in mixing proper quantities of ingredients at a desired temperature, comprising:

(a) an insulated measuring cup having a structure which defines an upper-rim and interior and exterior walls joined thereto, the interior wall defining a receptacle, contiguous portions of the interior and exterior walls located downwardly of the upper rim being spaced apart from each other and separated by an air gap; and

(b) a liquid crystal thermometer fixedly attached to the exterior wall of the cup so that the thermometer is thermally isolated from the receptacle.

5,588,748 PROBE COVER FOR USE IN TYMPANIC THERMOMETER

Toshiyuki Nomura, Yuji Tsujioaka, and Naohiro Osuga, all of Miyahigashi-machi, Japan, assignors to Horiba, Ltd., Kyoto, Japan


Continuation of Ser. No. 501,696, Jul. 12, 1995, abandoned, which is a continuation of Ser. No. 121,361, Sep. 14, 1993, abandoned. This application Jun. 28, 1996, Ser. No. 668,517

Claims priority, application Japan, Sep. 19, 1992, 4-275543

Int. Cl.⁶ G01K 1/08

U.S. Cl. 374—158

17 Claims



17. A probe cover for use with a thermometer having an elongate probe, the probe defining a receiving groove at its base, the probe cover comprising:

a flexible retaining member having at least two end edge portions and a substantially centrally located opening, the opening being dimensioned to admit the elongate probe and to engage the receiving groove; and

a film member secured to the retaining member at the end edge portions, the film member covering the opening;

the film member contacting the probe and being urged through the opening of the retaining member by the probe when the probe cover is urged over the probe, thereby drawing the end edge portions of the retaining member inwardly toward the opening.

5,588,749

MULTIFUNCTIONAL BAG

Hiromi Ishikawa, Tokyo, Japan, assignor to Office Ishikawa Co., Ltd., Tokyo, Japan


Filed Mar. 29, 1995, Ser. No. 412,884

Claims priority, application Japan, Apr. 6, 1994, 6-004704

Int. Cl.⁶ B65D 30/10; 33/10; A41D 3/08; 15/04

U.S. Cl. 383—4

10 Claims



1. A multifunctional bag device comprising:

a bag including first and second bag members, each of said first and second bag members including a hinge edge along a portion of a periphery thereof and fastener edges having

fasteners thereon along other portions of the periphery, said first and second bag members being hinged together at their respective hinge edges and being detachably attached along their respective fastener edges by said fasteners, so that said bag is closable into a bag-shape for containing items therein by folding said first and second bag members toward one another about said hinge edges and fastening together the respective fastener edges of said first and second bag members with said fasteners, and so that said bag is openable to form a pair of seats by detaching the respective fastener edges from one another and unfolding said first and second bag members from one another along said hinge edges;

an elongate foldable sheet removably insertable in said bag when said bag is closed into said bag-shape and said sheet is folded, said sheet having fasteners provided along peripheral edges thereof for enabling said sheet to be formed into a sleeping bag by being folded along a longitudinal center and having said fasteners along the peripheral edges thereof fastened together so that one longitudinal end of the sleeping bag is closed by the fasteners, a first longitudinal side of the sleeping bag formed by folding along the longitudinal center of said sheet is closed and at least a portion of a second longitudinal side of said sleeping bag, opposite said first longitudinal side of said sleeping bag, is closed by the fasteners, said fasteners being unfastenable to allow said sheet to be unfolded for use as a lap robe or a body portion of a hooded poncho; and

a hood removably insertable in said bag when said bag is closed into said bag-shape, said hood having a fastener provided along a bottom edge thereof for detachable attachment to a portion of one of the fasteners provided along the peripheral edges of said sheet, such that said hood and said sheet, when fastened together by the respective fasteners, form the hooded poncho.

5,588,750

BALL RETAINER WITH INNER SEAL FOR LINEAR GUIDE APPARATUS

Nobuyuki Osawa, and Masayuki Katahira, both of Gunma, Japan, assignors to NSK Ltd., Tokyo, Japan


Filed Jul. 20, 1995, Ser. No. 504,579

Claims priority, application Japan, Jul. 20, 1994, 6-168184

Int. Cl.⁶ F16C 29/06

U.S. Cl. 384—15

8 Claims



1. A linear guide apparatus comprising:

a guide rail including in a side surface thereof a first ball rolling groove extending in an axial direction of the guide rail;

a slider including in an inside surface thereof a second ball rolling groove formed in opposition to the first ball rolling groove, the slider hanging over the guide rail so that the slider is movable in the axial direction with respect to the guide rail;

a plurality of balls loaded into the mutually opposing ball rolling grooves; and

a ball retainer being mounted into the slider and including an inner seal disposed in a space formed within the slider and the guide rail, wherein the inner seal has side edges comprising:

a pair of ball holding parts for holding the balls loaded into the second ball rolling groove to thereby prevent the balls

from falling away from the second ball rolling groove when the slider is removed from the guide rail; and

a pair of thin-plate shaped inner seal parts respectively extending along and fixed integrally to the ball holding parts, the inner seal parts including end portions slidably contactable with an upper surface of the guide rail.

5,588,751

ROLLING BEARING AND METHOD OF FABRICATING THE SAME

Ryuji Nakata, Osaka, and Hiroshi Komiya, Kashiwara, both of Japan, assignors to Koyo Seiko Co., Ltd., Japan


Filed Mar. 13, 1996, Ser. No. 614,473

Claims priority, application Japan, Mar. 13, 1995, 7-053010; Mar. 5, 1996, 8-047743

Int. Cl.⁶ F16C 33/66

U.S. Cl. 384—463

16 Claims



1. A rolling bearing comprising:

a pair of races for defining an annular region therebetween;

a plurality of rolling elements arranged in the region and rolling on each of the races;

a cage arranged in the region and having pockets for holding the respective rolling elements; and

a solid lubricating composition which is composed of a mixture of a resin and a lubricating component, with which the region is filled;

a film including a lubricating component being formed between the pocket and the rolling element in a state where the solid lubricating composition is prevented from being interposed therebetween.

5,588,752

BEARING AND JOURNAL ASSEMBLY

Mark W. K. Fetty, Hopewell, Va., assignor to Brenco, Incorporated, Petersburg, Va.


Filed Mar. 4, 1996, Ser. No. 610,304

Int. Cl.⁶ F16C 33/78

U.S. Cl. 384—477

12 Claims

1. In combination with a rail car axle having a coaxial, cylindrical journal portion at and extending inwardly from a free end of the axle and a coaxial, cylindrical shoulder portion spaced from the free end and having a diameter larger than the diameter of the journal, and a fillet merging the cylindrical journal surface into the shoulder, an improved bearing assembly fitted onto the journal and retained thereon by an end cap mounted on said free end to permit relative rotation between the axle and an element supported by the bearing, said bearing assembly comprising, an inboard bearing cone and an outboard bearing cone mounted on said journal in axially spaced relation to one another, each said cone defining frustoconical inner raceway and each having an inner diameter providing an interference fit with said journal, a cylindrical spacer element mounted on said journal between said bearing cones and



maintaining said bearing cones in said axially spaced relation, a bearing cup defining a pair of inwardly directed frustoconical outer raceways located one in radially outwardly spaced relation to each of said inner raceways, rolling elements located between the outer and inner raceways, a backing ring mounted on said shoulder, said backing ring having a counterbore formed therein providing an interference fit with said cylindrical shoulder surface and a contoured surface complementary to and engaging said fillet surface over a portion of the axial extent of said fillet in a manner to radially and axially fix the backing ring on the axle, a second counterbore formed in said backing ring providing an annular, substantially planar axially outwardly directed abutment surface at an axial location spaced between the maximum and minimum diameter portions of said fillet, a first seal wear ring mounted on said journal and having a first end surface engaging said backing ring abutment surface and a second end surface engaging said inboard bearing cone, a second seal wear ring mounted in contact with said outboard bearing cone and said end cap, and a pair of annular sealing elements interposed one between each end of said bearing cup and each said seal wear ring forming a lubricant barrier at each end of the bearing, said first seal wear ring having an inner generally cylindrical surface providing an interference fit with said cylindrical journal surface over a portion of the axial length of said first seal wear ring and having an outer cylindrical surface providing an interference fit with said second cylindrical bore in said backing ring, said outer cylindrical surface of said first seal wear ring having a diameter at least equal to the mean diameter of said inner raceways.


5,588,753

DISK DRIVE MOTOR WITH LABYRINTH SEAL
Shinji Kinoshita, and Mitsuru Ide, both of Nagano, Japan,
assignors to Kabushiki Kaisha Sankyo Seiki Seisakusho,
Nagano, Japan

Filed Aug. 15, 1995, Ser. No. 518,486
Claims priority, application Japan, Aug. 17, 1994, 6-193446
Int. Cl.⁶ F16C 33/80

U.S. Cl. 384-488

8 Claims



1. A disk drive motor comprising:
a center shaft;

ball bearings, inner rings thereof being fixedly fitted with the center shaft while interposing a predetermined distance therebetween;
a hub supported so as to be rotatable about the center shaft with outer rings of the ball bearings being fixed to an inner hole thereof;
a drive magnet secured to the hub;
a stator core arranged so as to confront the drive magnet;
first and second seals arranged along respective paths in the disk drive motor, said paths leading to a space outside the motor, at least one of said paths communicating the ball bearings with the space outside the motor;
an annular spacer fixedly fitted with the center shaft between the inner rings of the pair of ball bearings, wherein an outer circumferential surface of the spacer confronts an inner circumferential surface of the inner hole of the hub while interposing a small gap therebetween, so that a labyrinth seal mechanism is formed.

5,588,754

BACKUP BEARINGS FOR EXTREME SPEED TOUCH DOWN APPLICATIONS


Robin M. Miller, Ellington, Conn., assignor to United Technologies Automotive, Inc., Dearborn, Mich.

Filed Dec. 29, 1995, Ser. No. 581,080

Int. Cl.⁶ F16C 19/10; 32/04

U.S. Cl. 384-609

18 Claims



1. A backup bearing for providing backup to magnetic bearings comprising:
an outer race disposed about an axis, and mounted for rotational movement with respect thereto;
an inner race spaced from the outer race and disposed about the axis, the inner race being substantially stationary with respect to the axis;
a plurality of rolling elements each having a central axis with each element being spaced from the inner race and disposed between the inner and outer race for rotational movement therebetween;
wherein rotation of the outer race causes corresponding rotation of the plurality of rolling elements such that upon contact of the rolling elements with the inner race, the speed differential between the rotating rolling elements and the substantially stationary inner race causes each rolling element contacting the inner race to accelerate about its central axis.

5,588,755

UNWINDING APPARATUS FOR UNWINDING TAPE-LIKE SHEET MEMBER


Wataru Nimura, Ome, Japan, assignor to Casio Computer Co., Ltd., Tokyo, Japan

Filed Apr. 21, 1995, Ser. No. 425,421

Claims priority, application Japan, Apr. 30, 1994, 6-113606
Int. Cl.⁶ B41J 33/14

U.S. Cl. 400-234

15 Claims



1. An unwinding apparatus for use with a cassette including upper and lower opening portions at upper and lower portions thereof and a tape-like sheet member therein, said unwinding apparatus comprising:

an apparatus main body having a cassette inlet and outlet opening at a side portion thereof such that the cassette 13 detachable with the apparatus main body through the cassette inlet and outlet opening of the apparatus main body, the apparatus main body including a winding shaft and an unwinding shaft such that the tape-like sheet member is bridged between the winding shaft and the unwinding shaft when inserted in the apparatus main body;

a head member inserted into the cassette through the upper opening portion formed on the cassette by pressing down the sheet member to position below the lower opening portion;
a head attaching member attached with the head member and movably disposed on the apparatus main body in an upward and downward direction so as to bring the head member into contact with the sheet member and to separate the head member from the sheet member;

an abutting member disposed on the apparatus main body at a position opposed to the head member so as to abut the head member through the sheet member; and
unwinding means for rotating the unwinding shaft to move the sheet member in an unwinding direction in connection with the movement of the head attaching member when the head attaching member moves in a direction to separate the head member from the sheet member, so as to move the sheet member in a tensioning direction.

5,588,756

INK RIBBON CARTRIDGE AND METHOD OF INSTALLING SAME

Paul H. Hamisch, Jr., Franklin, and John D. Mistyurik, Troy, both of Ohio, assignors to Monarch Marking Systems, Inc., Dayton, Ohio

Continuation of Ser. No. 137,660, Oct. 15, 1993, abandoned.


This application Aug. 31, 1995, Ser. No. 522,184

Int. Cl.⁶ B41J 33/52

U.S. Cl. 400-234

6 Claims

1. An ink ribbon cartridge for use in a printer having a platen and a print head cooperable with the platen for printing on a web of record members, the ink ribbon cartridge comprising: a cartridge housing, an ink ribbon supply roll having a tubular core onto which an ink ribbon has been wound, the core having an inner surface, a shaft within the cartridge housing for mounting the ink ribbon supply roll, means within the cartridge housing for mounting a roll of spent ink ribbon, the shaft including first and second shaft members, the first shaft member including a first terminal end portion terminating at a first surface, the first terminal end portion



having an axial hole, the second shaft member including a second terminal end portion having a second surface and terminating at an axial projection, the projection being received in the hole, the first and second surfaces being in opposed relationship to each other and being spaced apart, a tubular brake member having a frictional outer surface received on the projection between the spaced apart first and second surfaces, the frictional outer surface of the brake member being in frictional contact with the inner surface of the core.

5,588,757

RECORDING APPARATUS WITH DETACHABLE MAGNETIC SENSOR

Yasuhiro Unosawa, Tokyo; Shinji Kanemitsu; Makoto Kashimura, both of Yokohama; Makoto Takemura, Tokyo; Shoji Kikuchi, Yokohama; Shinya Matsui, Tokyo; Toshiyuki Onishi, Yokohama; Tetsuhiro Nitta, Yokohama; Masaru Sato, Yokohama, and Hisashi Morioka, Kawagoe, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Continuation of Ser. No. 141,520, Oct. 27, 1993, abandoned.


This application Mar. 20, 1996, Ser. No. 618,784

Claims priority, application Japan, Oct. 28, 1992, 4-313011; Nov. 10, 1992, 4-324863; Aug. 19, 1993, 5-226567

Int. Cl.⁶ B41J 19/00

U.S. Cl. 400-279

17 Claims



1. A recording apparatus having a magnetic linear encoder, comprising:
a carriage mounted with a recording head movable in recording scan directions;
a magnetized scale;
a detection unit, including a magnetic linear encoder and a bearing member, for detecting magnetized information magnetized to said scale, said scale being inserted in said bearing member so that said detection unit is movable along said scale, said detection unit including said magnetic linear encoder in combination with said scale; and
connection means for snap-locking said detection unit, in which said scale is received in said bearing member, to said carriage, said connection means including clicks formed on one of said detection unit and said carriage, and click engaging portions formed on the other one of said detection unit and said carriage, said click engaging portions engaging with said clicks with the result that said detection unit is fixed to said carriage.

5,588,764

LOCK FOR DEFLECTABLE WRITING UTENSIL

Hiroyasu Kato, Takizaki, Japan, assignor to Katoh Kinzoku Kogyo Kabushiki Kaisha, Tomioka, Japan


Filed Jul. 5, 1995, Ser. No. 498,124

Claims priority, application Japan, Jan. 26, 1995, 7-030135

Int. Cl.⁶ B43K 7/12; 24/00

U.S. Cl. 401-99

1 Claim



1. A writing utensil comprising:
 - a forward external casing;
 - a rearward external casing;
 - a deflecting mechanism interposed between said forward external casing and said rearward external casing effective, when exposed, to permit angular deflection between said rearward external casing and said forward external casing;
 - an inserting tube carrying a writing implement slidably disposed within said forward casing and having a backward end containing a sliding head extending into said rearward external casing;
 - a supporting body having a cam surface thereon carried by said rearward external casing operative to extend said writing implement forwardly when said rearward external casing is angularly deflected with respect to said forward external casing; and
 - a lock casing slidably mounted on said rearward external casing and being operative, when in an extended position, to cover said deflecting mechanism and prevent deflection between said rearward external casing and said forward external casing and, when in a retracted position, to expose said deflecting mechanism whereby angular deflection between said casings is permitted to effect extension and retraction of said writing implement thereby.

5,588,765

APPARATUS FOR ANALYZING SIGNATURES


Robert K. Campbell, Anaheim, Calif., assignor to Signa Scan, Inc., Anaheim, Calif.

Division of Ser. No. 98,582, Jul. 28, 1993, abandoned. This application Dec. 16, 1994, Ser. No. 358,008

Int. Cl.⁶ B43K 7/00; 7/10

U.S. Cl. 401-216

2 Claims



1. A ballpoint pen having a supply of ink and comprising a rolling ball retained within a rim at the forward end of the pen for applying the supply of ink to a writing surface and a plurality of indentations formed around the rim of said pen to produce a corresponding plurality of projections extending radially inward of said rim and aligned with said rolling ball to interrupt some of the supply of ink being applied by said rolling ball to the writing surface to thereby cause micro-striations to appear in each ink line applied to the writing surface, the distance between at least some

of said plurality of indentations formed in said rim being greater than the distance between at least some other of said plurality of indentations such that the number of micro-striations in an ink line and the distance between the micro-striations in the ink line are indicative of whether the ink line was deposited by said ballpoint pen.

5,588,766

ASCENDING/DESCENDING STRUCTURE


Yu-Shan Lai, F4-3, No. 288, Tzu-Yu Rd., Chia-I Hsien, Taiwan

Filed Jan. 11, 1996, Ser. No. 583,821

Int. Cl.⁶ F16B 7/14

U.S. Cl. 403-105

1 Claim



1. An ascending/descending structure comprising a pull bar, a locking pin having a board-like locking pin seat with a rearwardly extending reverse hooking portion, a resilient retaining member, and a locking tube having saw tooth-like locking notches, said structure being characterized in that:
 - the pull bar is a rectangular bar having bent stopper portions at a bottom end for limiting movement of the resilient retaining member, a substantially rectangular window being formed on the pull bar near the bottom end thereof, the rectangular window having a hook-like slot therein for limiting a movement of the rearwardly extending reverse hooking portion, a recess being formed in the rectangular window for retaining a spring therein;
 - the locking pin is a cylindrically shaped member integrally connected with the board-like locking pin seat, the rearwardly extending reverse hooking portion corresponds to the hook-like slot of the window of the pull bar, the board-like locking pin seat being formed with an arch dent pushable by the spring in the window of the pull bar so as to keep the locking pin abutting against one of the saw tooth-like locking notches of the locking tube;
 - the resilient retaining member is a plate-like member made of a resilient material, the resilient retaining member is formed with a window having an extending guide slot for engaging with the locking pin, a resilient arm extending from one side of the resilient retaining member for abutting against an inner wall of the locking tube;
 - the locking tube is a hollow rectangular bar formed with the saw tooth-like locking notches on one side and two locating slots extending respectively from two sides of the saw tooth-like locking notches; and
 - the board-like locking pin seat is placed in the rectangular window of the pull bar with the spring aligned with the arch dent of the board-like locking pin seat, the resilient retaining member being disposed on the board-like locking pin seat and the pull bar with the locking pin passing through the window of the resilient retaining member, the extending guide slot facing toward the bent stopper portions, the resilient arm being on the same side as the hook-like slot of the pull bar, wherein the pull bar, the locking pin, and the resilient retaining member are placed into the locking tube, the spring forcing the locking pin into said one of the saw tooth-like locking notches to be locked therein, whereby when it is desired to descend the pull bar, the pull bar being first pulled outward to a limitation position with the locking pin limited

within the extending guide slot of the resilient retaining member and then pushed inward.

5,588,767

LOCKING JOINT MECHANISM

Werner O. Merlo, 51203 Range Rd. 265, Spruce Grove, Alberta, Canada


Continuation-in-part of Ser. No. 435,363, May 5, 1995, abandoned. This application Jun. 27, 1995, Ser. No. 495,104

Claims priority, application United Kingdom, May 5, 1994, 9408893

Int. Cl.⁶ F16C 11/06

U.S. Cl. 403-128

12 Claims



1. In an angularly adjustable, releasably lockable joint mechanism for rigidly joining first and second parts at a selected orientation, said mechanism comprising a rounded member having a plurality of concavities on its surface and being secured to the first part, a disengageable actuator having a rounded tip and being operative to advance the tip to lock up with the rounded member by penetrating a concavity or to retract the tip to disengage it from the rounded member, said actuator being connected with the second part, and means for holding the parts, rounded member and actuator together, said means being operative to allow the parts to change relative orientation when the actuator head is retracted,

the improvement comprising:

- the rounded member having a plurality of patterns of spaced-apart protuberances covering at least part of its surface, the protuberances of each pattern forming a concavity therebetween;
- the patterns and protuberances being consistent in shape, area and size, the patterns having a regular polygonal configuration;
- the protuberances, actuator tip and patterns being dimensioned relative to each other so that the tip can penetrate the concavity of each pattern and simultaneously contact all of the protuberances of the pattern that it penetrates, with the contact between said actuator and protuberances being located so that said actuator remains spaced from the surface of the rounded member at full penetration, whereby the tip and pattern of protuberances lock together without said tip contacting the surface of said rounded member.

5,588,768

LOCKING ARRANGEMENT

Robert I. Hedley, Via Singleton, Australia, assignor to Hedweld Engineering Pty Ltd., New South Wales, Australia


Filed Aug. 4, 1994, Ser. No. 286,012

Claims priority, application Australia, Aug. 5, 1993, PM0408

Int. Cl.⁶ F16B 7/00; 13/00; B25G 3/00; F16G 11/00

U.S. Cl. 403-294

9 Claims



1. A locking arrangement for releasably securing a first member to a second member,
 - a surface of said first member having anchor means projecting therefrom with a lip portion of said anchor means transversely extending from an extremity of at least a portion of said anchor means;
 - a surface of said second member having a cutout portion defining an opening adapted to lockingly engage said anchor means, at least a portion of said cutout having a tongue around the opening thereof shaped to be positioned underneath said lip portion of said anchor means;
 - such that during use, a surface of each of said first and second members is aligned by positioning said anchor means within said cutout opening by sliding one member relative to the other and thereby cause engagement of said tongue underneath said lip portion, two keepers inserted in at least a part of said cutout not occupied by said anchor means to releasably secure said first member to said second member; wherein movement between said members is inhibited, each of said keepers having releasable interlocking portions adapted to retain said keepers together.

5,588,769

CONNECTIBLE LOCKING MECHANISM

Paul Graefenhain, Heerbrugg, Switzerland, assignor to Leica AG, Heerbrugg, Switzerland


Filed Sep. 29, 1995, Ser. No. 536,172

Claims priority, application Germany, Sep. 30, 1994, 44 34 997.1

Int. Cl.⁶ G05G 5/06; G02B 21/24; 15/00

U.S. Cl. 403-322

12 Claims



1. A connectible locking mechanism for a continuously operating zoom system of a microscope, comprising:

a drive unit including a drive shaft for setting a zoom;
 a locking disk provided axially on and fixedly connected to the drive shaft, the locking disk defining grooves which are arranged side by side;
 a locking spring arranged fixedly to an instrument of said microscope;
 a locking slider provided with a recess and arranged between the locking spring and the locking disk; and
 a ball arranged between the locking spring and the locking disk in the recess of the locking slider, the ball being movable into and out of engagement with the grooves of the locking disk through a sliding motion of the locking slider.

5,588,770

QUICK RELEASE AND ADJUSTABLE PALLET ASSEMBLY FOR TEXTILE SCREEN PRINTING MACHINE


Mark Bart, DesPlaines, Ill., assignor to A.W.T. World Trade, Inc., Chicago, Ill.

Filed Sep. 27, 1995, Ser. No. 534,284

Int. Cl.⁶ B41M 1/12; F16B 5/06

U.S. Cl. 403—325

6 Claims



1. A quick release locking mechanism for mounting a pallet on a support bed or platform of a single or multi-color screen printing apparatus, said locking mechanism adapted to be installed on the underside of the platform and said pallet having rail means protruding from its undersurface opposite its work surface on which a workpiece is to be carried for printing of a multi-color composite image thereon, said mechanism comprising:

- A) a pair of housings adapted to be secured to a medial portion of said underside of the platform spaced apart and laterally aligned one with the other;
- B) an elongate linear member slidable in each housing and having opposite ends thereof protruding from opposite extremities of its associated housing, one of said protruding ends of each linear member having a locking member upstanding thereon to form a track-like space between the locking member and the associated housing for accommodating the rail means therein;
- C) the opposite end of each elongate member having an upstanding pin member thereon;
- D) a slidable plate positioned in said space between the housings and having a pair of angularly displaced slots therein each having a pin member slidably engaged therein; and
- E) articulated linkage means connected to said plate for sliding same in said space for reciprocating the pins in the slots whereby to selectively engage said locking members against the rail means and withdraw the locking members from engagement with said rail means thereby freeing the pallet from the platform.

5,588,771

CONNECTOR FOR COUPLING A PAIR OF RODS

Gregory H. Scott, Salina, and Melvin P. Kejr, Brookville, both of Kans., assignors to Kejr Engineering, Inc., Salina, Kans.

Filed Apr. 20, 1995, Ser. No. 425,931

Int. Cl.⁶ F16B 7/22

U.S. Cl. 403—353

8 Claims



1. Structure for connecting a pair of elongated rods in axial alignment for transmitting axial and rotational forces along a longitudinal axis of the rods through the connection, said structure comprising:

- interfitting male and female sections projecting in longitudinal extension from their corresponding respective rods;
- the male section including an elongated transversely polygonal member which comprises an elongated transversely rectangular bar projecting from an end of the male section, said elongated transversely rectangular member having a transversely extending notch having endwalls presenting a pair of oppositely facing shoulders extending transversely of the corresponding elongated rod;
- the female section comprising an elongated channel having a cross-section configuration for complementally receiving the male section for rotation with the latter and having a transversely extending segment configured to be received in the notch when the rods are in axial alignment to lock the rods together for axial movement as a unit;
- the female section including a pair of elongated apertures respectively positioned on opposite facing surfaces of the channel relative to the longitudinal axis, the apertures communicating the channel with the exterior of the female section, the apertures being positioned to permit the sections to be moved into or removed from their connected positions when the rods are disposed in positions with their respective longitudinal axes at an angle with respect to one another; and
- wherein the elongated bar includes the transversely extending notch on one side, and a second transversely extending notch on an opposite side of the longitudinal axis from the one side and longitudinally offset from the first transversely extending notch.

5,588,772

HIGH STRENGTH, QUICK CONNECT/DISCONNECT COUPLING


George P. Johnson, Jr., Tomball, Tex., assignor to North Houston Machine, Inc., Tomball, Tex.

Continuation-in-part of Ser. No. 82,663, Jun. 25, 1993, Pat. No. 5,409,324. This application Mar. 13, 1995, Ser. No. 403,279

Int. Cl.⁶ F16L 25/06; F16B 21/12


U.S. Cl. 403—355

19 Claims



1. A quick connect/disconnect coupling for transferring torque comprising:

- a first cylindrical member having an outer peripheral surface and an end portion, said end portion having a transverse keyway in said outer peripheral surface;
 - a second cylindrical member having a receiving end portion, said receiving end portion having an end face with a longitudinal bore therein for receiving said end portion of said first cylindrical member, said receiving end portion having a transverse slot therethrough;
 - a key received in said transverse keyway and protruding therefrom into said transverse slot; and
 - a retainer member extending over said key in said transverse slot of said receiving end portion of said second cylindrical member,
- wherein said key is freely received within said transverse keyway and said transverse slot and freely contained between said retainer member and said transverse keyway, said key non-rotatably connects said first cylindrical member to said second cylindrical member.



gripper stop, a gripper pivotally connected on the hollow shaft and resiliently supported against the gripper stop, a thrust piece having an inner side matching the circumferential profile of the hollow shaft, and at least one clamping bolt having a bolt part and a nut part threaded thereon, said steel belt being fixed to said nut part of said clamping bolt, and said bolt part of said clamping bolt being turnable so as to clamp said thrust piece radially with respect to the central longitudinal axis of the hollow shaft.

5,588,774

APPARATUS FOR ARRESTING THE PROGRESS OF VEHICLES

Kevin Beban, Watford, United Kingdom, assignor to CatsClaw Limited, St. Albans, United Kingdom

PCT No. PCT/GB92/01598, § 371 Date May 4, 1994, § 102(e)

Date May 4, 1994, PCT Pub. No. WO93/05236, PCT Pub. Date Mar. 18, 1993


PCT Filed Sep. 1, 1992, Ser. No. 199,324

Claims priority, application United Kingdom, Sep. 3, 1991, 9118817; Nov. 13, 1991, 9124137

Int. Cl.⁶ E01F 13/00

U.S. Cl. 404—6

15 Claims



1. Apparatus for selectively arresting the progress of vehicles, comprising: a plurality of releasably connected modules, each module being shaped to lie on a road surface to allow the passage of a vehicle thereover, and having vehicle arresting means moveable between a retracted position inside the module and an operative position in which the arresting means protrudes from the module to prevent progress of the vehicle, the modules being interconnected by an actuating means which enables simultaneous actuation of all the arresting means, the actuating means comprising male and female connectors, each male connector comprising a member adapted to locate in a female connector and including cooperating means such that rotation of the male member causes rotation of the female connector, wherein the female connector comprises a channel into which the male member is received, the channel having a lip portion for preventing axial removal of the

5,588,773

DEVICE FOR CONNECTING A MACHINE ELEMENT TO A STRUCTURAL MEMBER MOVABLE ABOUT ITS LONGITUDINAL AXIS SO THAT THE MACHINE ELEMENT AND THE STRUCTURAL MEMBER ARE SECURED AGAINST RELATIVE ROTATION

Jens Friedrichs, Heidelberg, and Karl-Heinz Helmstädter, Sinsheim, both of Germany, assignors to Heidelberger Druckmaschinen AG, Heidelberg, Germany

Filed May 26, 1994, Ser. No. 249,549

Claims priority, application Germany, May 26, 1993, 43 17 429.9

Int. Cl.⁶ B41F 21/04

U.S. Cl. 403—373

7 Claims

1. In combination, a gripper stop of a printing press, a hollow shaft oscillatory movable about a central longitudinal axis thereof, and a device for clamping the gripper stop at the circumference of the hollow shaft, at one of an infinite number of phase angles with respect to the hollow shaft, so that the gripper stop and the hollow shaft are secured against relative rotation, the device comprising a steel belt embracing more than 180° of the circumference of the hollow shaft and being firmly connected to the

male connector and the distance from a base of the channel to the plane of the lip being greater than the depth of at least a portion of the part of the male member which, in situ, is located directly between the lip and base to allow limited axial and/or tilting movement of the male member in the channel.

5,588,775


PAVING STONE SET AND PROCESS AND DEVICE FOR THE MANUFACTURE THEREOF

Gerhard Hagenah, Worpswede, Germany, assignor to SF-Kooperation GmbH Beton-Konzepte, Bermer, Germany
Continuation of Ser. No. 244,103, May 19, 1994, Pat. No. 5,486,066. This application Sep. 29, 1995, Ser. No. 556,289
Claims priority, application Germany, Nov. 23, 1991, 41 38 564.0

Int. Cl.⁶ E01C 11/16

U.S. Cl. 404—45

3 Claims



1. A paving stone set made up of a region of concrete paving stones (10) which are spaced apart to create a region of longitudinal gaps (16) and transverse gaps (17), wherein the concrete paving stones are joined together by a holding grid (11) and are secured against displacement, and wherein:

- said concrete paving stones (10) are joined together exclusively by said holding grid (11);
- said holding grid (11) consists of tension-resistant and non-perishable elastic material;
- said holding grid (11) lies continually exposed in said region of said longitudinal gaps (16) and transverse gaps (17);
- said holding grid (11) is fully embedded in said concrete paving stones (10) exclusively in said region thereof;
- said holding grid (11) is embedded in said concrete paving stones (10) at a distance from a bottom side (15) of said concrete paving stones (10), which distance corresponds to one-quarter to one-third of the total height of one of said concrete paving stones (10); and
- said holding grid (11) comprises spaced-apart longitudinal strands (12) and spaced apart transverse strands (13), the spacing between the longitudinal strands (12) and between the transverse strands (13) measuring 2 cm to 5 cm.

5,588,776

PAVING MACHINE HAVING AUTOMATIC METERING SCREED CONTROL


George W. Swisher, Jr., Oklahoma City, and John F. Phillips, Yukon, both of Okla., assignors to CMI Corporation, Oklahoma City, Okla.

Continuation-in-part of Ser. No. 185,428, Jan. 21, 1994, Pat. No. 5,452,966. This application Jun. 6, 1995, Ser. No. 469,139
Int. Cl.⁶ E01K 19/18

U.S. Cl. 404—72

16 Claims

1. A paving machine comprising:
a frame;
means for propelling said frame over a surface to be paved;
distributing means, carried by said frame, for providing volume of unhardened concrete on the surface beneath said frame;



a metering screed carried by said frame and adapted to engage and meter out the concrete at a selected target depth over the surface beneath said frame;
a sensor carried by said frame and adapted to produce measurements of the distance between said sensor and the surface of the concrete at an area behind said metering screed;
link means, connected to said metering screed and said sensor, for vertical movement of said sensor in response to the opposite vertical movement of said metering screed; and
control means, operatively connected to said sensor and said metering screed, for positioning said metering screed to change the volume of concrete being metered out by said metering screed, said control means being adapted to receive the sensor measurements and a tolerance from an operator of the paving machine, the tolerance being a range of distances corresponding to a selected depth for the concrete;
wherein said control means re-positions said metering screed in response to the sensor measurements which are outside the tolerance.

5,588,777

WASTEWATER TREATMENT SYSTEM


Rein Laak, 149 Browns Rd., Storrs Mansfield, Conn. 06268-2808

Filed Jun. 30, 1995, Ser. No. 497,616

Int. Cl.⁶ E02B 11/00

U.S. Cl. 405—40

5 Claims



1. A subterranean wastewater treatment system that receives wastewater containing both nitrates and other waste products and comprising in combination:
a holding tank having an inlet for receiving the wastewater and settling out the waste products so that a liquid effluent with nitrates included therein is provided in the holding tank, and said holding tank further including an outlet for discharging the effluent from said holding tank,
a leaching field to provide an anaerobic atmosphere for receiving the effluent from said tank outlet,

a porous bed below said field, said bed including at least one horizontally disposed in-drain provided in said porous bed, and
conduit means coupled to said in-drain for injecting a liquid soap into said in-drain to enhance biological activity of the nitrates in the effluent reaching said in-drain in an anaerobic atmosphere.

5,588,778

LEACHING CHAMBER WITH ANGLED END


James M. Nichols, Old Saybrook, and Bryan A. Coppes, Clinton, both of Conn., assignors to Infiltrator Systems Inc., Old Saybrook, Conn.

Filed May 19, 1995, Ser. No. 444,388

Int. Cl.⁶ E02B 13/00

U.S. Cl. 405—48

13 Claims



1. In a chamber, for dispersing or gathering liquids within soil, of the type having an arch shape cross section, wherein the base of the chamber corresponds with the base of the arch; the chamber having opposing first and second ends spaced apart along a primary longitudinal axis, the ends having terminuses shaped to enable mating of the chamber with other chambers to form a string of chambers; the improvement comprising: a first end of the chamber having a first terminus angled with respect to the chamber longitudinal axis, the first terminus enabling a similar chamber to be mated thereto, to provide a basic axial alignment angle greater than zero between the mated chambers; wherein, the improvement enables a string of like chambers to be connected to follow an approximate curve.

5,588,779

SIGHT, VENT, AND DRAIN ASSEMBLY FOR AN UNDERGROUND TANK


Stanley L. Merrett, Dadeville, Ala., assignor to Schlumberger Industries, Inc., Norcross, Ga.

Filed Jun. 7, 1995, Ser. No. 483,408

Int. Cl.⁶ G01F 23/56

U.S. Cl. 405—54

12 Claims



1. An improved apparatus for fire suppression of the type comprising a tank disposed beneath the ground for holding fluid therein and a dry hydrant head having a first end above the ground and an opposite second end in communication with the fluid in the tank.

wherein the improvement comprises means for visually determining the level of the fluid inside the tank which is disposed beneath the ground and used for fire suppression.

12. A method of fire suppression using a tank disposed beneath the ground for holding fluid therein, a dry hydrant head having a first end above the ground and an opposite second end in communication with the fluid in the tank, comprising the steps of:

- adding fluid to the tank;
- applying a demand pressure to the dry hydrant head to begin drawing fluid from the tank for fire suppression; and
- viewing a color indicator so as to determine the level of fluid in the tank.

5,588,780

METHOD AND INSTALLATION FOR LAYING A PIPE-LINE

Dick R. Wolbers, 's-Gravenhage, and Ronkers Koerse, Twisk, both of Netherlands, assignors to All Seas Group S.A., Switzerland


Filed Jun. 7, 1995, Ser. No. 475,802

Claims priority, application Netherlands, Aug. 6, 1994, 9400933

Int. Cl.⁶ F16L 1/12

U.S. Cl. 405—170

9 Claims



1. Method for laying a pipe-line (27) on a seabed, wherein pipes on a vessel are welded to each other along a ring weld (3) and wherein the ring weld (3) is covered with a ring of mastic (6), the thickness of which is greater than 30 mm, which mastic comprises bitumen and filler, characterized in that the mastic is arranged around the ring weld (3), said mastic at a temperature wherein it is in a deformable state.

5,588,781

LIGHTWEIGHT, WIDE-BODIED COMPLIANT TOWER

Susan L. Smolinski; Denby G. Morrison, both of Houston, Tex.; Peter W. Marshall, Stockfield, England, and David A. Huete, Spring, Tex., assignors to Shell Oil Company, Houston, Tex.


Filed Dec. 30, 1993, Ser. No. 175,898

Int. Cl.⁶ E02B 17/00

U.S. Cl. 405—195.1

20 Claims

1. A lightweight, wide-bodied compliant tower for conducting hydrocarbon recovery operations from a deepwater offshore reservoir, comprising:
a foundation;
a compliant framework, comprising:
a plurality of vertically extending legs secured to the foundation; and
a plurality of horizontal bracing directly interconnecting the legs in a manner defining a substantially open riser suspension corridor extending substantially the entire length of the compliant framework without regular vertical intervals of riser load transfer structure; and



- a topside facility supported by the compliant framework.
2. A lightweight, wide-bodied compliant tower for conducting hydrocarbon recovery operations from a deepwater offshore reservoir, comprising:
- a foundation;
 - a compliant framework, comprising:
 - a plurality of vertically extending legs secured to the foundation; and
 - a plurality of horizontal bracing interconnecting the legs in a manner maintaining a substantially open riser suspension corridor extending substantially the entire length of the compliant framework;
 - a topside facility supported by the compliant framework; and
 - a freely suspended riser extending through the riser suspension corridor from the vicinity of the topside facility to communicate with the reservoir.
14. A method for economically reducing the natural period of the whipping mode harmonic response in a deepwater compliant tower having a vertically extending compliant framework secured to a foundation at an ocean floor and supporting a topside facility above the ocean surface and having a plurality of risers communicating between the topside facility and a plurality of wells at the ocean floor through a running span, the method comprising:
- providing the compliant framework in a wide body configuration such that the following relation is met over at least 70% of the length of the compliant framework:

$$L/\sqrt{A} < 12$$

where:

L is the total length of the compliant framework; and
A is the area of a cross section of the compliant framework at a given elevation;

providing a substantially open vertically extending riser suspension corridor that is braced only at its periphery; and
suspending the risers in a top-tensioned relation from a riser support at the top end of the compliant framework and deploying the running spans of the risers through the riser suspension corridor without supplying intermediate supports at regular intervals along the compliant framework.

17. A method for improving the fatigue characteristics of a compliant tower by enhancing a wave cancellation effect, comprising:

establishing a compliant framework having a plurality of legs interconnected with a plurality of horizontal bracing in a manner which maintains a substantially open riser suspension corridor extending through the compliant framework at least the full depth of the wave zone; and
freely suspending risers through the riser suspension corridor; the compliant framework and freely suspended risers presenting surfaces such that waves impact a first side of the compliant

tower, pass through the risers and the interior of the compliant framework substantially unimpeded, and impact a second side of the compliant tower with a force which is significant in relation to the force of the impact on the first side.

5,588,782

PORTABLE BOAT DOCK


William F. Haring, 8839 Holly La., Riverside, Calif. 92503

Filed Feb. 8, 1995, Ser. No. 385,453

Int. Cl.⁶ B63C 1/00

U.S. Cl. 405—218

22 Claims



16. A dock, comprising:
- a first dock section having a first end, a second end, and a first deck portion extending therebetween;
 - means for anchoring said first end of said first dock section to a supporting surface;
 - a second dock section having a first end, a second end, and a second deck portion extending therebetween, said first end having support member engagement means thereon;
 - a hinge attached to said second end of said first dock section and to said second end of said second dock section;
 - a fastener attached to said first and second dock sections for securing together said first and second dock sections in a storage configuration of said dock;
 - at least one support member attached to said engagement means on said second dock section and contacting said supporting surface of upholding said dock;
 - means for retaining each support member between said first and second dock sections in the storage configuration; and
 - at least one handle attached to at least one of said first and second dock sections for transporting said dock.

5,588,783

SOIL REINFORCEMENT WITH ADHESIVE-COATED FIBERS

William N. Brabston, and Philip G. Malone, both of Vicksburg, Miss., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed May 8, 1992, Ser. No. 880,414

Int. Cl.⁶ E02D 3/12

U.S. Cl. 405—258

12 Claims

1. A method of soil reinforcement, comprising:
- providing at least one fiber;
 - coating said at least one fiber with an adhesive material;
 - mixing said coated at least one coated fiber with the soil, thereby adding strength and cohesion to the soil and reducing erosion and shear failure in the soil.

5,588,784

SOIL OR ROCK NAIL WALL WITH OUTER FACE AND METHOD OF CONSTRUCTING THE SAME


Ernest D. Brandl, Houston, Tex., and David E. Weatherly, Potomac, Md., assignors to Schnabel Foundation Company, Sterling, Va.

Filed Jun. 7, 1995, Ser. No. 485,276

Int. Cl.⁶ E02D 5/20

U.S. Cl. 405—262

66 Claims



1. A method of constructing a retaining wall comprising the following steps:
- excavating a cut in successive sections to form exposed cut faces;
 - temporarily shoring up the exposed cut face of each successively excavated section with a temporary support means, said temporary support means comprising a nail installed through the exposed cut face into the ground, a first end of said nail extending outwardly from said exposed cut face; and
 - forming an outer face by
 - positioning a first attachment means adjacent to said exposed cut face, said first attachment means having a first end and a second end,
 - securing said first end of said first attachment means to said exposed cut face,
 - erecting a first facing element,
 - securing said first facing element to said second end of said first attachment means,
 - erecting a second facing element adjacent to said first facing element,
 - placing reinforced concrete along the area of said retaining wall adjacent to said first end of said nail between said exposed cut face and said first and second facing elements, said reinforced concrete thereby forming a permanent structural connection between said first and second facing elements and said nail by encasing said first end of said nail, and
 - placing backfill material along the remaining area of said retaining wall between said exposed cut face and said first and second facing elements.

5,588,785

LIQUID HYDROCARBON SORBING AND SOLIDIFYING PILLOW

Herbert W. Holland, 2314 Chimney Rock, Houston, Tex. 77056


Continuation-in-part of Ser. No. 222,844, Apr. 5, 1994, Pat. No. 5,462,785. This application Jul. 24, 1995, Ser. No. 506,091

Int. Cl.⁶ E02D 31/00; B32B 3/00

U.S. Cl. 405—270

21 Claims

1. A liquid hydrocarbon absorbent device comprising:
- a pillow having a plurality of chambers formed in stratification therein by internal layers of textile material;



a polymer material disposed in the chambers having a property of acting to absorb and solidify liquid hydrocarbon substances coming into contact with the pillow and migrating to its interior;

a plurality of quilting seams in the pillow defining a multiplicity of hydrocarbon absorption consolidation points therein and subdividing each chamber into distinct hydrocarbon absorption units within the pillow; and

an outer facing layer of an impermeable material extending over a surface of the pillow and acting to retain liquids within the pillow.

5,588,786

COMBINATION RETAINING WALL AND METHOD OF CONSTRUCTION

Randall H. House, Johann H. Hofmann, both of San Antonio, and Freddie C. Birck, Boerne, all of Tex., assignors to Marylyn House, San Antonio, Tex.

Continuation-in-part of Ser. No. 917,841, Jul. 21, 1992, Pat. No. 5,471,811, which is a continuation-in-part of Ser. No. 675,503, Mar. 26, 1991, and Ser. No. 601,413, Oct. 22, 1990,


Pat. No. 5,131,786, which is a continuation-in-part of Ser. No. 347,482, May 4, 1989, Pat. No. 4,964,750. This application

Jun. 7, 1995, Ser. No. 475,212

Int. Cl.⁶ E02D 5/10; E02D 5/20; E04B 2/00

U.S. Cl. 405—285

18 Claims



1. A precast concrete wall capable of being rapidly and efficiently constructed and capable of withstanding nominally applied overturning and destructive forces comprising:

- a plurality of C-shaped wall segments wherein said C-shaped wall segments have a generally similar C-shaped cross-section, each C-shaped wall segment comprising:
 - i. a vertically arranged precast concrete panel having a thickness, a height, and a first generally vertical edge and a second generally vertical edge;
 - ii. a first generally vertically disposed U-shaped member and a second generally vertically disposed U-shaped member, each said first and said second U-shaped member having a front leg and a rear leg, and a thickness and a height substantially similar to said thickness and said height of


5,588,792

PIPETTE TIP RACK LOADER

Allan Tiso, 879 Del Valle Dr., Fallbrook, Calif. 92028
Filed Mar. 16, 1995, Ser. No. 405,083Int. Cl.⁶ B65G 59/06

U.S. Cl. 414—404

23 Claims



1. A dispenser for dispensing pipette tips downwardly under the force of gravity, said dispenser comprising:
 - a frame having a top end and a bottom end spaced from said top end;
 - means in said dispenser defining an interruptible tip passage path;
 - a top plate coupled to said top end of said frame, said plate being formed with a plurality of apertures therethrough, each said aperture being adapted to receive a plurality of tips in a mutually nested stack, the bottom tip in the stack of tips extending through said aperture, said apertures defining the top portion of said tip passage path;
 - means below said top plate cooperative with the shape and configuration of each tip to selectively prevent the tips from passing completely through said apertures in said top plate and out the bottom end of said frame;
 - means for wedging apart the bottom tip from the next upper tip nested in the bottom tip by retaining in position the bottom-most tip while moving the remainder of the stack of tips apart therefrom; and
 - means for selectively permitting the bottom tip to pass completely through said tip passage path and fall independently from the remaining tips in the nested stack through said aperture and out the bottom end of said frame, said wedging means being shaped and configured to retain the remaining tips in the nested stack in said aperture in said top plate when the bottom tip passes out the bottom end of said frame.

5,588,793

ELEVATOR MECHANISM FOR VEHICLE

Hueng-San Chang, 12, Si Wei St., Taoyuan, Taiwan
Filed Mar. 2, 1995, Ser. No. 397,407Int. Cl.⁶ B60P 1/26; B60F 1/00

U.S. Cl. 414—557

3 Claims

1. An elevator mechanism for a vehicle comprising:
 - at least one support for securing an elevator mechanism to a vehicle, said support including an upper portion and a lower portion;
 - at least one coupler including an upper portion, a middle portion and a lower portion;
 - at least one first link pivotally coupled between said upper portion of said support and said upper portion of said coupler;
 - at least one second link pivotally coupled between said lower portion of said support and said lower portion of said coupler for stably supporting said coupler.



- at least one first actuator means engaged between said first link and said second link and including a first end pivotally coupled to said lower portion of said support and a second end pivotally connected to said coupler for moving said coupler upward and downward;
- a panel pivotally coupled to said upper portion of said coupler and rotatable about said upper portion of said coupler, said panel including a bottom surface having a middle portion, and
- at least one second actuator means pivotally coupled between said middle portion of said bottom surface of said panel and said middle portion of said coupler for rotating said panel about said upper portion of said coupler.

5,588,794

ROBOTIC GRIPPER


James R. Panyard, Westland, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Jul. 18, 1994, Ser. No. 276,574

Int. Cl.⁶ B66C 1/10

U.S. Cl. 414—729

19 Claims



8. A robotic gripper system for gripping a workpiece having a pair of spaced apart longitudinally extending contoured faces and at least two extending cylindrical bores, each cylindrical bore having an inner surface, and the contoured faces disposed at an angle in relation to the each other, the robotic gripper system comprising:
 - an industrial robot having a movable robotic arm;
 - a gripper base pivotally mounted on a distal end of said robotic arm;

- a pair of spaced apart longitudinally extending stabilizing members, each affixed to said base, each of said stabilizing members having an engagement surface adapted to abuttingly engage a respective contoured face of said workpiece;
- at least one pair of opposing clamping arms pivotally connected to said stabilizing members, each said clamping arm being pivotable from a first position wherein said clamping arm is disposed adjacent a respective cylindrical bore to a second position wherein said clamping arm abuttingly engages the inner surface of a respective one of said cylindrical bores;
- a first biasing means connected to one of said pair of clamping arms by a first over the center type toggle link for moving said one clamping arm from said first position to said second position;
- a second biasing means being connected to the other of said pair of clamping arms by a second over the center type toggle link for moving said other clamping arm from said first position to said second position; and
- a control means in communication with the biasing means for selectively controlling actuation of said first and second biasing means, so that once the clamping arms are in the second position, each biasing means must be retracted to release the clamping arms, whereby clamping force is maintained by the over center clamping toggle link during power outages or in the event of a disconnected biasing means.

5,588,795

HANDLING APPARATUS

Helmut F. Jäger, Königsbach-Stein; Jürgen Peschina, Knittlingen, both of Germany, and Bernard Dietrich, Rixheim, France, assignors to Felsomat GmbH & Co KG, Königsbach-Stein, Germany


Filed Jul. 14, 1994, Ser. No. 275,168

Claims priority, application Germany, Jul. 15, 1993, 43 23 736.3

Int. Cl.⁶ B66C 1/00

U.S. Cl. 414—733

23 Claims



1. Handling apparatus for moving an object along a U-shaped locus curve, said apparatus comprising:
 - an engaging element for engaging the object;
 - a machine frame;
 - a first rocker element disposed on said machine frame for rotation about a first horizontal axis;
 - a second rocker element disposed on one end of said first rocker element opposite said first horizontal axis for rotation about a second horizontal axis, said second rocker element carrying said engaging element at an end opposite said second horizontal axis; and
 - a first linkage coupling said first and second rocker elements for rotation with a fixed transmission ratio;
- wherein said transmission ratio of said first linkage is substantially 1:4 to effect movement of said engaging element, as said first rocker element is rotated about said first horizontal axis, along the U-shaped locus curve having at least one horizontal section and one vertical section, and said horizontal and said vertical sections are largely straight;
- wherein an arm length ratio (k) defined by a quotient of an arm length (a2) of said second rocker element—which is defined by an axial spacing between said second horizontal axis and a

center axis of said engaging element—and an arm length (a1) of said first rocker element—which is defined by an axial spacing between said first and second horizontal axis—lies in the range between substantially 0.09 and 0.25 such that:

$$0.09 \leq k = a2/a1 \leq 0.25.$$

5,588,796

APPARATUS AND METHOD FOR HANDLING INFORMATION STORAGE MEDIA


Gary C. Ricco, Redding; Michael D. Shannon, Sunnyvale, and Tyler R. Wilkins, Menlo Park, all of Calif., assignors to ATG Cygnit Inc., San Jose, Calif.

Filed Apr. 18, 1994, Ser. No. 229,406

Int. Cl.⁶ B25J 15/00

U.S. Cl. 414—741

34 Claims



10. A media handling apparatus for picking and flipping an informational media item including a parallelepiped shaped media item having no surface notches or protrusions to latch to, said apparatus comprising:
 - means for cradling and frictionally gripping and supporting said media item including said parallelepiped shaped media item having no surface notches or protrusions;
 - means for transporting said media item from a first location into a recessed region of said media handling apparatus;
 - said means for cradling and frictionally supporting being operable to cradle and support said media item even when said media item is positioned outside of said recessed region;
 - means for transporting said media item from said recessed region into a second location; and
 - means for flipping said media item retained within said recessed region of said apparatus.

5,588,797

IC TRAY HANDLING APPARATUS AND METHOD

Nathan R. Smith, Stillwater, Minn., assignor to Advantek, Inc., Minnetonka, Minn.


Filed Jul. 18, 1994, Ser. No. 276,336

Int. Cl.⁶ B65G 59/06

U.S. Cl. 414—797.5

18 Claims

1. An apparatus for handling trays accommodating microchips comprising: a generally horizontal table for supporting a plurality of trays holding microchips, rib means secured to the table for locating the trays on the table and guiding one tray along the table, upright post means mounted on the table engageable with the trays to locate a stack of trays on the table in a first position, tray handling means for lifting the stack of trays, except the bottom one tray, supported on the table, first means operable to move the one tray on the table from the first position to a second position, second means for removing microchips from the one tray and placing the microchips in a selected location, said first means being operable to move the one tray from the second position to a third position on the table when all of the microchips have been removed from the one tray, said tray handling means being operable to lower the



stack of trays on the table and subsequently raise the stacks of trays leaving a second bottom tray on the table, said first means being operable to move the second bottom tray from the first position to the second position so that microchips can be removed from the second bottom tray.

5,588,798

ROTATING MACHINE PART, IN PARTICULAR A ROTOR OF A CYCLOID SHIP'S PROPELLER

Werner Fork, Heidenheim, Germany, assignor to J.M. Voith GmbH, Germany

PCT No. PCT/EP94/03614, § 371 Date Jul. 5, 1995, § 102(e) Date Jul. 5, 1995, PCT Pub. No. WO95/12520, PCT Pub. Date May 11, 1995


PCT Filed Nov. 3, 1994, Ser. No. 481,329

Claims priority, application Germany, Nov. 5, 1993, 43 37 761.0

Int. Cl.⁶ F04D 29/00

U.S. Cl. 415—111

14 Claims



1. A rotating machine part having a base, an outer wall around the base, the rotating machine part defining a rotor having a rotation axis at the rotor axis, wherein the machine part is rotatable in a medium which is able to transmit heat away from the outer wall to a sufficient extent to produce a cooling effect on the rotor; means toward the rotor axis for introducing a liquid heat transmission medium into the rotor and the rotor being shaped so as to permit the introduced transmission medium to move radially outward through the machine part; a plurality of transmission medium return lines, each line having an inlet for the heat transmission medium to be returned and the inlet being arranged in the radially outer region of the rotor, the return lines being directed for delivering the heat transmission medium to the vicinity of the central axis of the rotor.

5,588,799

DIFFUSOR FOR A TURBO-MACHINE WITH OUTWARDLY CURVED GUIDED PLATE

Franz Kreitmeyer, Baden, Switzerland, assignor to ABB Management AG, Baden, Switzerland


Filed Jun. 7, 1995, Ser. No. 473,938

Claims priority, application Germany, Jun. 29, 1994, 44 22 700.0

Int. Cl.⁶ F01D 1/02; F04D 29/44

U.S. Cl. 415—211.2

12 Claims



1. In an axial-flow turbo-machine having a fluid flow channel containing a plurality of rows of rotor blades past which a fluid may flow in a substantially axial flow direction to produce a fluid flow having a rotational flow component at a downstream end of said plurality of rotor blades in the flow direction, said channel having a channel height at a downstream-most row of said rotor blades, a diffuser positioned downstream of said rotor blades in the flow direction and comprising:

- a radially outer diffuser ring having an upstream end forming a first kink angle with a radially outer wall of said fluid flow channel;
- a radially inner diffuser ring having an upstream end forming a second kink angle with a radially inner wall of said fluid flow channel, a diffuser channel being defined between said inner and outer diffuser rings, said inner and outer diffuser rings being configured such that said diffuser channel has an axial inlet and a radial outlet;
- a radially outwardly curved flow-guiding plate positioned in said diffuser channel, said flow-guiding plate subdividing said diffuser channel into inner and outer channels between a fluid flow inlet of said diffuser channel and a fluid flow outlet of said diffuser channel;
- a plurality of radial-flow ribs positioned in said outer channel at a substantially radial fluid flow portion thereof; and
- a plurality of diagonal-flow ribs positioned in said inner channel at a substantially diagonal fluid flow portion thereof, said radial and diagonal flow ribs comprising a mechanism substantially cancelling the rotational flow component of the fluid flow;

wherein said first and second kink angles are selected such that a total pressure profile over said channel height is substantially equalized.

5,588,800

BLADE VORTEX INTERACTION NOISE REDUCTION TECHNIQUES FOR A ROTORCRAFT


Bruce D. Charles; Ahmed A. Hassan, both of Mesa; Hormoz Tadghighi, Gilbert; Ram D. JanakiRam, Mesa, all of Ariz., and Lakshmi N. Sankar, Atlanta, Ga., assignors to McDonnell Douglas Helicopter Co., Mesa, Ariz.

Filed May 31, 1994, Ser. No. 251,329

Int. Cl.⁶ F01D 5/00

U.S. Cl. 416—24

17 Claims



1. An active control device for reducing blade vortex-interaction (BVI) noise generated by a rotorcraft having a rotor blade including a tip end, a root end, a leading edge, and a trailing edge, said rotor blade being attached at said root end to a rotor hub on said rotorcraft and extending radially outwardly therefrom, having a radius R and a chord C, such that when said rotor hub is rotatably driven, said rotor blade rotates about said hub through a 360 degree azimuth, said active control device comprising:

a movable flap pivotally attached to said rotor blade trailing edge by a hinge oriented generally radially along said rotor blade, at least a portion of said flap being positioned near said rotor blade tip, in about the outboard 25% of the rotor blade radial length, said flap having a chord width within a range of approximately 0.25 C–0.35 C, along at least a portion of its radial length;

an actuator for deflecting and retracting the flap about said hinge;

wherein said flap is adapted to be actuated to a deflected position during rotation of said rotor blade through predetermined regions of said rotor azimuth, and is further adapted to be actuated to a retracted position through the remaining regions of said rotor azimuth, thereby functioning to reduce BVI noise during operation of said rotorcraft.

a plurality of blades, each blade being attached to a hub of the rotor by an attachment part, said attachment part being joined to the hub by means for holding and articulating; said flap stops device comprising for each said blade, a corresponding upper stop mounted so as to move on the hub; an elastic return means for returning said upper stop to a ground position, wherein each upper stop directly faces and has a clearance away from a stop track of an upper bearing shoe, said upper bearing shoe being mounted on said attachment part of a corresponding blade so as to limit upwards flapping of said blade by contacting said stop track against a corresponding upper stop at rotational speeds of the rotor within a range between zero and below a threshold corresponding to a speed which is sufficient to allow the rotor to be controlled using rotorcraft flight controls;

at least one flyweight mounted so that it can pivot on said hub about a pin which is substantially parallel to an axis of rotation of the rotor and mechanically joined to at least one upper stop so that at rotational speeds of the rotor which are greater than said threshold each flyweight is moved away from said axis of rotation of the rotor by centrifugal force.

the upper stops are moved against said elastic return means into a flight position such that said upper stops no longer face said upper bearing shoes of the blades, said blades no longer being limited in terms of upwards flapping by the upper stops, and

said upper stops each project outwards from a rotary ring which is substantially coaxial with the hub, said ring being mounted so as to rotate about the axis of rotation of the rotor on an upper part of the hub, and each flyweight being mechanically joined to said ring by means for driving the ring in rotation about the axis of rotation of the rotor from the ground to the flight position of the upper stops when said flyweight is moved away from this axis by centrifugal force, and against the elastic return means which return the ring to the ground position of the upper stops and each flyweight towards the axis of rotation of the rotor.

5,588,802

Patent Not Issued For This Number

5,588,801

FLAP STOPS DEVICE WITH RETRACTABLE UPPER STOPS RING, AND ROTOR HEAD INCLUDING IT

Sylvie J. Commelin, Carry le Rouet, and Jean J. Mondet, Pelissanne, both of France, assignors to Eurocopter France, Marignane, France


Filed Oct. 5, 1995, Ser. No. 539,692

Claims priority, application France, Oct. 12, 1994, 94 12168

Int. Cl.⁶ B64C 27/51

U.S. Cl. 416—46

15 Claims



1. In combination, a flap stops device for a rotorcraft and a main rotor, said main rotor comprising:

CENTRIFUGAL IMPELLER WITH SIMPLIFIED MANUFACTURE

Stephan M. Vetter, Lockport, and Mark J. Parisi, East Amherst, both of N.Y., assignors to General Motors Corporation, Detroit, Mich.


Filed Dec. 1, 1995, Ser. No. 566,101

Int. Cl.⁶ F04D 29/28

U.S. Cl. 416—186 R

1 Claim

1. A centrifugal blower impeller, comprising, a central hub having a center axis and an annular rim, a regularly spaced series of substantially identical impeller blades extending axially upwardly from said hub rim, each blade having a substantially unsupported tip and a radial width sufficient to require external support to said blade tip to prevent excessive flexure in use, each blade tip further having a pair of radially separated, axially opening notches therein, each notch of each pair lying on a common diameter with the remaining blade tip notches, a circular band surrounding and integrally molded to said blade tips, said circular band being located entirely radially outboard of said hub rim, and, an annular locking ring having a radial width comparable to said blade tips, said ring having a pair of generally circular channels, each lying on a diameter equal to said blade tip notches and having a cross sectional shape matching the shape of said



notches, said locking ring also having a cylindrical flange the inner surface of which closely matches the outer surface of said band, whereby said locking ring is assembled to said blades by aligning and axially inserting said cylindrical flange over said band as said channels are concurrently axially inserted into said blade tip notches, thereby completing said impeller and preventing said blade tips from flexing excessively during impeller rotation.

5,588,804


HIGH-LIFT AIRFOIL WITH BULBOUS LEADING EDGE
Michael J. Neely, Dayton, and John R. Savage, Kettering, both of Ohio, assignors to ITT Automotive Electrical Systems, Inc., Auburn Hills, Mich.

Filed Nov. 18, 1994, Ser. No. 342,358

Int. Cl.⁶ F01D 5/14

U.S. Cl. 416—223 R

17 Claims



1. An airfoil defining the shape of the blades of a vehicle engine-cooling fan assembly and comprising:
an unpointed leading edge;
a rounded bulbous nose section adjacent said leading edge;
a trailing edge;
a continuously curved pressure surface extending smoothly, without discontinuity, and without a planar portion from said nose section to said trailing edge;
a continuously curved suction surface extending smoothly and without discontinuity from said nose section to said trailing edge; and
a thin, highly cambered aft section formed adjacent said trailing edge and between said pressure surface and said suction surface, said aft section having a location of maximum camber;
said nose section having a thickness which is greater than the thickness of said airfoil between said pressure surface and said suction surface and said nose section blending smoothly into said pressure surface via a first blend radius and a second blend radius approximately equal to said first blend radius and into said suction surface, said first blend radius forming a

convex surface extending from said nose section adjacent said leading edge and said second radius forming a concave surface extending from said convex surface to said pressure surface of said airfoil.

5,588,805

VIBRATION AND PRESSURE ATTENUATOR FOR HYDRAULIC UNITS


Kerry G. Geringer, Ames, Iowa, assignor to Sauer Inc., Ames, Iowa

Filed Aug. 28, 1995, Ser. No. 520,083

Int. Cl.⁶ F04B 1/26

U.S. Cl. 417—53

12 Claims



1. A method of attenuating vibration and pressure within a hydraulic unit having a swashplate therein connected to a servo piston disposed in a servo piston cylinder bore fluidly connected to the hydraulic unit, the hydraulic unit displacing pressurized fluid having a periodic component therein exerted at a troublesome frequency on the fluid in the servo piston cylinder bore due to vibrational movement of the swashplate, the method comprising:
connecting the servo piston cylinder bore to an oscillator tuned to the troublesome frequency, the oscillator having a substantially rigid inertial portion and a hydraulic spring portion fluidly connected to the inertial portion;
allowing pressurized fluid to enter the inertial portion and thence enter into the hydraulic spring portion;
compressing the pressurized fluid in the hydraulic spring portion to cause a phase change of the periodic component and introduce a phase shifted second periodic component into the pressurized fluid in the hydraulic spring portion whereby the second periodic component will transfer back through the pressurized fluid in the inertial portion to the servo piston cylinder bore whereupon the servo piston will transmit the second periodic component to the swashplate to attenuate the vibrational movement thereof.

5,588,806

LIQUID RING MACHINE AND PROCESS FOR OPERATING IT

Peter Trimborn, Feucht, and Kurt-Willy Mugele, Erlangen, both of Germany, assignors to Siemens Aktiengesellschaft, Munich, Germany

PCT No. PCT/DE94/00131, § 371 Date Aug. 15, 1995, § 102(e) Date Aug. 15, 1995, PCT Pub. No. WO94/19610, PCT Pub. Date Sep. 1, 1994

PCT Filed Feb. 9, 1994, Ser. No. 505,228


Claims priority, application Germany, Feb. 22, 1993, 43 05 424.2

Int. Cl.⁶ F04B 47/12

U.S. Cl. 417—68

30 Claims

1. A method for operating a liquid ring machine comprising the steps of:



providing a working chamber within the liquid ring machine, the working chamber having an apex in the geodetic upper area and a rotatable impeller, wherein the working chamber is divided into at least two partial working chambers;
providing a supply of operating liquid;
separating at least one partial working chamber from the supply of operating liquid;
blocking the partial working chamber on either the suction side or the discharge side or both; and
draining the supply of operating liquid from the at least one partial working chamber so that the operating liquid does not contact the rotating impeller in the at least one partial working chamber, while another partial working chamber remains in operation so that the operating liquid does contact the rotating impeller in the another partial working chamber.

5,588,807

SWASH PLATE TYPE VARIABLE DISPLACEMENT COMPRESSOR

Kazuya Kimura, Hiroaki Kayukawa, Toru Takeichi, and Osamu Hiramatsu, all of Kariya, Japan, assignors to Kabushiki Kaisha Toyota Jidoshokki Seisakusho, Kariya, Japan


PCT No. PCT/JP93/01655, § 371 Date Jun. 2, 1994, § 102(e) Date Jun. 2, 1994, PCT Pub. No. WO94/11636, PCT Pub. Date May 26, 1994

PCT Filed Nov. 12, 1993, Ser. No. 244,448

Claims priority, application Japan, Nov. 12, 1992, 4-302593 Int. Cl.⁶ F04B 1/29

U.S. Cl. 417—222.2

8 Claims



1. A swash plate type variable displacement compressor in which a variably inclined swash plate is located in a crank chamber within a housing, the inclination angle of said swash plate being adjustable in accordance with the pressure difference between said crank chamber and a gas suction chamber, and a piston is provided for reciprocation with a stroke related to the inclination angle of said swash plate for compressing gas supplied from said suction chamber to a compression chamber, whereby the volume of gas discharged from a gas discharge chamber is controlled, said compressor comprising:

a communication passage in said housing independent of said crank chamber for connecting said gas discharge chamber to said gas suction chamber without passing through said crank chamber;
a branch passage branching from said communication passage and communicating with said crank chamber;
valve means, disposed in said communication passage between said gas discharge chamber and a point where said branch passage branches from said communication passage, for selectively opening and closing said communication passage to alter the pressure in said crank chamber; and
a restriction, provided downstream of said point where said branch passage branches from said communication passage, for throttling the flow of gas from said gas discharge chamber to said gas suction chamber.

5,588,808

PUMP PRESSURE MULTIPLIER


Gerard J. De Santis, Battle Creek, Mich., assignor to Hytech Pumps International, Inc., Bedford, Mich.

Filed Dec. 8, 1994, Ser. No. 352,316

Int. Cl.⁶ F04B 35/02

U.S. Cl. 417—225

9 Claims



1. A device for elevating a pressure acting on a liquid, comprising:
a first pressure elevating means for supplying a liquid under a first positive pressure and at a selected volume of liquid per unit of time flow rate to a liquid inlet port;
a second liquid pressure elevating means for receiving the liquid under the first positive pressure and at the selected volume of liquid per unit of time flow rate from the inlet port and supplying the liquid under a second positive pressure substantially greater than the first pressure and at said selected volume of liquid per unit of time flow rate to an outlet port and a liquid utilizing load connected thereto, said second pressure being sufficiently high enough to cause the liquid to become substantially compressed to thereby result in said second pressure to vary during intervals of time that the liquid is being compressed; and
control means for accommodating the compressibility of the liquid so as to maintain a substantially constant second pressure.

5,588,809

METERING PUMP WITH A VENT VALVE

Joachim Klein, Vachendorf, and Herbert Hunklinger, Siegsdorf, both of Germany, assignors to Lang Apparatebau GmbH, Siegsdorf, Germany

PCT No. PCT/EP93/03333, § 371 Date Aug. 7, 1995, § 102(e) Date Aug. 7, 1995, PCT Pub. No. WO94/13956, PCT Pub. Date Jun. 23, 1994


PCT Filed Nov. 27, 1993, Ser. No. 448,516

Claims priority, application Germany, Dec. 5, 1992, 42 41 030.4

Int. Cl.⁶ F04B 21/00

U.S. Cl. 417—283

15 Claims



1. A metering pump for measuring the amount of liquids being delivered to an intake container, comprising:
 - an intake line at one end for connection to an intake container;
 - a suction valve installed in said intake line;
 - a pump chamber having one end opening into said intake line for series connection therewith, and another end;
 - a pump element mounted in said pump chamber for alternately changing the displacement volume of said pump chamber;
 - a non-return valve;
 - a valve chamber having one end separated from and coupled to said pump chamber via said non-return valve located therebetween;
 - a first displaceable wall mounted between said nonreturn valve and said pump chamber;
 - a vent valve mounted in said valve chamber, said vent valve being controlled by said first displaceable wall, whereby said vent valve opens during a suction stroke of said pump element, and closes during a compression stroke thereof;
 - a metering line connector having a liquid flow path opening into said valve chamber proximate said vent valve; and
 - a pressure valve mounted in the liquid flow path of said metering line connector, and responsive to the pressure in said valve chamber exceeding a given value for opening to permit liquid to flow therebetween.

5,588,810

LOW NOISE REFRIGERANT COMPRESSOR

Michael A. DiFlora; Prakash N. Pandey, both of Bristol, Tenn.; Christopher S. Robinson, Abingdon, Va., and Philip C. Wagner, Bristol, Tenn., assignors to Bristol Compressors, Inc., Bristol, Va.


Filed Sep. 1, 1995, Ser. No. 522,793

Int. Cl.⁶ H02K 5/04

U.S. Cl. 417—312

8 Claims

1. A sound barrier cover for a compressor unit, said unit having a housing comprising a substantially continuous wall having a



longitudinal axis and a radial axis and containing a compressor and being provided with a plurality of porting means mounted through said wall, said barrier cover comprising first and second shell sections configured to lie close to said housing and substantially envelope said housing, said shell sections being configured to provide two substantially longitudinally oriented halves each having sound absorbing material affixed to its inner surface, said halves having perimeters with portions thereof formed with mating tongue and groove means, cooperating components of snap-fasteners on said halves in close proximity to the perimeters thereof, said snap-fasteners being adapted to hold said perimeters in contact with each other and with said sound absorbing material in resilient contact with said housing wall and exerting radially outward force on said barrier cover.

5,588,811

AIR BED DIAPHRAGM PUMP


Gerald H. Price, Burlington, Canada, assignor to Price Manufacturing, Inc., Burlington, Canada

Filed Jul. 14, 1994, Ser. No. 275,125

Int. Cl.⁶ F04B 1/28; 39/10

U.S. Cl. 417—350

11 Claims



1. A diaphragm pump comprised of a shaft, means for rotating said shaft at a speed of less than 3,300 revolutions per minute, a first flange assembly connected to said shaft such that the axis of rotation of said shaft forms an angle other than 90 degrees with the axis of rotation of said first flange assembly, a second flange assembly connected to said shaft such that the axis of rotation of said shaft forms an angle other than 90 degrees with the axis of rotation of said second flange assembly, a first connecting rod connected to a first diaphragm, a second connecting rod connected to a second diaphragm, a third connecting rod connected to a third diaphragm, a fourth connecting rod connected to a fourth diaphragm, and means for converting rotary motion of said flange assemblies into reciprocating linear motion of both said first con-

necting rod, said second connecting rod, said third connecting rod, and said fourth connecting rod wherein:

- (a) as said first connecting rod is moved in a first direction at a first rate of travel, said second connecting rod is simultaneously moved in a second linear direction at a second rate of travel, wherein said second rate of travel is equal to said first rate of travel, and said second linear direction is the opposite of said first linear direction, and
- (b) as said third connecting rod is moved in a third direction at a third rate of travel, said fourth connecting rod is simultaneously moved in a fourth linear direction at a fourth rate of travel, wherein said fourth rate of travel is equal to said third rate of travel, and said fourth linear direction is the opposite of said third linear direction;
- (c) said first flange assembly is connected to each of said first connecting rod and said second connecting rod by means of a ball and socket assembly;
- (d) said second flange assembly is connected to each of said third connecting rod and said fourth connecting rod by means of a ball and socket assembly;
- (e) said first flange assembly is comprised of a first inner flange disposed within a first outer flange and separated from said first outer flange by first bearings; and
- (f) said second flange assembly is comprised of a second inner flange disposed within a second outer flange and separated from said second outer flange by second bearings; and
- (g) said first diaphragm communicates with a first inlet and outlet valve pair, said second diaphragm communicates with a second inlet and outlet valve pair, said third diaphragm communicates with a third inlet and outlet valve pair, and said fourth diaphragm communicates with a fourth inlet and outlet valve pair.

5,588,812

IMPLANTABLE ELECTRIC AXIAL-FLOW BLOOD PUMP


Lynn P. Taylor, Camino; Pieter W. J. C. le Blanc, Pollock Pines; Kenneth C. Butler, Carmichael, and Timothy R. Maher, Orangevale, all of Calif., assignors to Nimbus, Inc., Rancho Cordova, Calif.

Filed Apr. 19, 1995, Ser. No. 424,165

Int. Cl.⁶ F04B 17/03

U.S. Cl. 417—356

17 Claims



1. An implantable blood pump comprising:

- a) a cylindrical blood conduit;
- b) a motor stator surrounding said blood conduit;
- c) a pump rotor having inlet and outlet ends and containing a motor rotor for motive interaction with said motor stator, said pump rotor being arranged to rotate in said blood conduit;
- d) inlet stator blades disposed in said blood conduit, said inlet stator blades supporting an inlet hub;
- e) outlet stator blades disposed in said blood conduit, said outlet stator blades supporting an outlet hub; and
- f) a ball-and-cup structure interposed between each of said inlet and outlet ends of said pump rotor and the corresponding one of said hubs for supporting said rotor, said ball-and-cup structures being washed by the blood flow through said blood conduit;

- g) said ball-and-cup structure having a substantially smaller diameter than said pump rotor and presenting to said blood flow a substantially continuous surface through which substantially no blood can penetrate between said ball and cup.

5,588,813

FLUID MOTOR DRIVEN PUMP ARRANGEMENT HAVING MOTIVE FLUID EXHAUST INTO THE PUMP CHAMBER

Jorgen Berke-Jorgensen, Gramvej 76, Fruering, DK-8660, Skanderborg, Denmark


PCT No. PCT/DK93/00151, § 371 Date Jan. 27, 1995, § 102(e) Date Jan. 27, 1995, PCT Pub. No. WO93/22556, PCT Pub. Date Nov. 11, 1993

PCT Filed May 5, 1993, Ser. No. 331,660

Claims priority, application Denmark, May 7, 1992, 0600/92 Int. Cl.⁶ F04B 9/115

U.S. Cl. 417—391

9 Claims



1. Dosing arrangement for the dosing of at least a first liquid medium A into a second liquid medium B and which comprises a piston type liquid motor which is driven by the second liquid medium B and consists of two mutually connected motor pistons (1, 1') on a common piston rod (12) each motor piston traveling in its own motor cylinder (2, 2'), and having a length of stroke, motor inlet valves (6, 6') and motor outlet valves (7, 7') for delivery and discharge of the second liquid B to and from the motor cylinders (2, 2') and at least one dosing pump, for the first liquid A, the at least one dosing pump being embodied as a piston pump consisting of two pump pistons (3, 3') traveling each in its own pump cylinder (4, 4'), which are positioned outward from, in continuation of and coaxially with the motor cylinders (2, 2') and which are mechanically connected to the motor pistons (1, 1'), motor outlet valves for delivery and discharge of the first liquid medium A to and from the pump cylinders (4, 4'), pipe connections for supply of the first liquid medium A from the dosing pumps to a discharge pipe from the liquid motor, and means for regulation of the proportion of mix, the dosing arrangement comprising the motor pistons and the pump pistons (3, 1, 3', 1') being mutually permanently connected and attached to a central body (5), the one of the motor cylinders and one of the pump cylinders (2, 4, 2', and 4') being positioned on opposite sides of the central body from the other of the motor cylinders and the other of the pump cylinders, the central body having a width which is greater than the length of stroke of the motor piston (1, 1'), in which the motor inlet valves (6, 6') for delivery and the motor outlet valves (7, 7') for discharge of the second liquid B to and from the motor cylinders (2, 2') are built in, the motor inlet valves (6, 6') being embodied as seat valves, which are mutually connected by an inlet valve rod (8) being moved in a direction parallel with the direction of travel of the motor pistons (1, 1'), and which in their extreme positions close a delivery opening (6a, 6a') to the motor cylinders (2, 2'), respectively, the motor inlet valves (6, 6') by means of the inlet valve rod (8) being instantaneously changed from one extreme position to the other by means of a spring mechanism coupled to a push rod (9), said push rod (9) being displaceably embedded in the central body (5) so that the push rod can move in a direction parallel with the inlet valve rod (8), being placed and having a length so that when one of the

motor inlet valves (6, 6') is closed, the push rod protrudes a short distance (X) into the motor cylinder, respectively (2, 2') and is displaced by the motor piston, (1, 1') when the latter travels towards its bottom dead center towards the central body 5, the motor outlet valves (7, 7') being embodied as seat valves which are mutually connected by an outlet valve rod (10), which is parallel with the inlet valve rod (8) being moved in a direction which is parallel with the direction of movement of the motor inlet valves (6, 6') and in their extreme positions said motor inlet valves (6, 6') can close the discharge openings (11, 11') from the motor cylinders (2, 2'), respectively, and that the movement of the motor outlet valves (7, 7') are firmly coupled to the movement of the motor inlet valves (6, 6'), the central body (5) being hollow and filled with the second liquid medium B, the central body (5) incorporating an opening/closing arrangement which, in correspondence with the movement of a piston rod (12), delivers a desired and variable volume of the second liquid medium B from the central body (5) to the pump cylinder (4, 4'), which is under suction pressure.

5,588,814

ELECTRONIC SWITCHING FAN ASSEMBLY FOR A VEHICLE

Pietro De Filippis, Monza; Ernesto Quartero, and Alberto Petrone, both of Collegno, all of Italy, assignors to Bitron S.P.A., Italy


Filed May 11, 1995, Ser. No. 439,360

Claims priority, application Italy, May 12, 1994, T094A0386

Int. Cl.⁶ F04B 35/04

U.S. Cl. 417—423.7

25 Claims



1. An electric fan assembly for a vehicle compartment, comprising:
 - an electric motor including a rotor to which a fan wheel is secured for rotation and a stator having a stack of laminations, the stator being mounted to a die-cast bearing fitted in an open box in communication with a scroll from which the fan wheel sucks air to be sent to the vehicle compartment;
 - a card including a printed circuit for determining operation of said electric motor;
 - wherein the bearing has two main opposite faces, one of which is a lower face and the other of which is an upper face, for mounting the stator and defining a seat for the assembly formed by the card;
 - a plurality of MOSs projecting from edges of the card, said MOSs being substantially coplanar to said card;
 - said seat having a depth dimensioned to receive a layer of solidifying resin covering and protecting the printed circuit and connections of the printed circuit;
 - said bearing having a plurality of central channels axially disposed along a cross-sectional axis of the die-cast bearing, the central channels providing electric connections between stator winding leads and a plurality of electric contacts located on the card proximate to at least one opening obtained in said card at said central channels; and
 - a plurality of axial fins extending from the upper face of said bearing for engaging the stator axially and radially.

5,588,815
SURGICAL CASSETTE LOADING AND UNLOADING SYSTEM


Richard L. Zaleski, II, San Juan Capistrano, Calif., assignor to Alcon Laboratories, Inc., Fort Worth, Tex.

Filed Nov. 15, 1995, Ser. No. 559,016

Int. Cl.⁶ F04B 43/08

U.S. Cl. 417—477.2

2 Claims



1. A system for loading and unloading a surgical cassette having a peristaltic pump tube from a cassette receiving portion of a surgical console, comprising:
 - a) a peristaltic pump roller head having a flared and beveled notch, the roller head being located in the cassette receiving portion of the surgical console; and
 - b) an extendable cylinder within the cassette receiving portion of the surgical console aligned so as to engage the peristaltic pump tube.

5,588,816

DISPOSABLE CASSETTE FOR CARDIOPLEGIA DELIVERY SYSTEM

Martyn Abbott, Richardson, and Thomas C. Thompson, McKinney, both of Tex., assignors to Quest Medical, Inc., Allen, Tex.


Division of Ser. No. 67,683, May 26, 1993, Pat. No. 5,385,540.

This application Jan. 31, 1995, Ser. No. 382,299

Int. Cl.⁶ F04B 23/00; 43/02

U.S. Cl. 417—479

6 Claims



1. A pump cassette usable with a clinical pump for delivering a plurality of fluids comprising:
 - (a) a first valved cassette inlet for receiving a first fluid;
 - (b) a second valved cassette inlet for receiving a second fluid;
 - (c) a common fluid outlet for conveying a combined flow of said first and second fluids;
 - (d) a common inlet path communicating with said first and second valved cassette inlets;
 - (e) separate first and second valved pump flow paths communicating with said common inlet path;
 - (f) first and second pump chambers communicating with, respectively, said first and second valved pump flow paths, each of said chambers having a deformable wall for varying the chamber volume; and

(g) first and second valved outlet paths communicating with said common fluid outlet.

5,588,817

PRESSURE-MEDIUM-TRAVERSED PISTON OF A RECIPROCATING PISTON PUMP

Wilhelm Zirps, Hemmingen; Wolfgang Schuller, Sachsenheim, and Martin Urban, Blaichach, all of Germany, assignors to Robert Bosch GmbH, Stuttgart, Germany

PCT No. PCT/DE94/00651, § 371 Date Jul. 17, 1995, § 102(e)

Date Jul. 17, 1995, PCT Pub. No. WO95/00759, PCT Pub.

Date Jan. 5, 1995


PCT Filed Jun. 10, 1994, Ser. No. 491,981

Claims priority, application Germany, Jun. 24, 1993, 43 20 902.5

Int. Cl.⁶ F04B 21/04

U.S. Cl. 417—549

8 Claims



1. A piston (13) of a reciprocating piston pump (10) through which a pressure medium flows for slip-regulated braking systems of motor vehicles, having the following features:
 - said piston (13) is provided with an inlet valve (19), the piston (13) exhibits a longitudinal bore (31) connected to a pressure-medium supply (26);
 - in the region of a piston face (30), the longitudinal bore (31) opens out into a valve seat (33) of the inlet valve (19);
 - a valve disk (37) of a closing member (34) of the inlet valve (19) is supported against the valve seat (33);
 - a stem (40) of the closing member (34) emanates from the valve disk (37) and emanates into the longitudinal bore (31) of the piston (13);
 - a biased closing spring (46) of the inlet valve (19) is received on the stem (40) and upon a flank, facing away from the valve seat (33), of a shoulder of the longitudinal bore (31), which shoulder is located on the valve seat side;
 - the stem (40) of the closing member (34) is embraced by an at least approximately frustoconical helical compression spring acting as a closing spring (46);
 - the closing spring (46) is held, with an end segment (47) of smaller diameter, non-twistably against the stem (40), and the shoulder of the longitudinal bore (31) exhibits at least one cross-sectional alteration for a screw-like action upon the end segment (40) of larger diameter of the closing spring (46).

5,588,818

ROTOR-TO-ROTOR COUPLING

Mitchell J. Houmand, Richmond, and James E. Kraus, Kingwood, both of Tex., assignors to Horizon Directional Systems, Inc., Houston, Tex.


Filed Apr. 20, 1995, Ser. No. 433,544

Int. Cl.⁶ F03C 2/08; F16D 1/08

U.S. Cl. 418—5

20 Claims

1. A rotor to rotor coupling comprising:
 - a rotor end having at least two, spaced apart, internal longitudinal grooves in a cavity adjacent the rotor end;
 - a connecting rod having at least two correspondingly spaced longitudinal, external grooves adjacent one end of the rod, wherein the rod end containing the external grooves is sized



to be telescopically received within the rotor end containing the internal grooves such that the external and internal grooves form at least two spaced chambers; at least two pins sized to fit within the spaced chambers; and means for releasably securing the rotor end to the rod end with the pins captured within the spaced chambers wherein the releasably securing means is sized to fit about the connecting rod and includes a threaded connector having at one end external threads for mating with internal threads within the rotor end cavity to contain the captured pins within the chambers.

5,588,819

COMPLIANT DRIVE FOR SCROLL MACHINE


Frank S. Wallis, Sidney, Ohio, assignor to Copeland Corporation, Sidney, Ohio

Filed Jun. 16, 1995, Ser. No. 490,906

Int. Cl.⁶ F04C 18/04

U.S. Cl. 418—39

39 Claims



1. A motor-compressor assembly comprising:
 - a shell;
 - first and second scroll members disposed in said shell, each of said scroll members having a spiral wrap thereon, said scroll members facing one another with said wraps inter-meshed with one another so that orbiting movement of said first scroll member with respect to said second scroll member will cause said wraps to create pockets of progressively decreasing volume towards the center of said scrolls;

a crankshaft defining a crankshaft axis drivingly engaging said first scroll member to cause said orbiting movement of said first scroll member, said crankshaft including a crank pin having a flat driving surface;

a motor disposed in said shell and connected to said crankshaft to power same; and

a drive bushing defining a bushing axis and having first and second surfaces capable of being driven by said flat driving surface, said bushing being disposed between said crank pin and said first scroll member, said drive bushing and said crankshaft forming a drive angle defined as the angle between said flat driving surface and a line connecting said crankshaft axis and said bushing axis, said drive bushing being selectively assembled between a first position wherein said bushing axis is located a first distance from said flat driving surface when said flat driving surface is in engagement with said first bushing surface such that said drive angle produces a first radial flank load component due to said motor powering said crankshaft in a forward direction and a second position wherein said bushing axis is located a second distance from said flat driving surface when said flat driving surface is in engagement with said second bushing surface such that said drive angle produces a second radial flank load component due to said motor powering said crankshaft in said forward direction, said first distance being different from said second distance such that said second radial flank load is different than said first radial flank load.

5,588,820

SCROLL COMPRESSOR HAVING AN AXIAL COMPLIANCE PRESSURE CHAMBER


Joe T. Hill, Bristol, Va.; Gene M. Fields, and John R. Williams, both of Bristol, Tenn., assignors to Bristol Compressors, Inc., Bristol, Va.

Filed Feb. 21, 1995, Ser. No. 391,733

Int. Cl.⁶ F04C 18/04; 27/00

U.S. Cl. 418—55.4

5 Claims



1. A scroll compressor having a housing means, a non-orbiting scroll fixed in position angularly, radially and axially on the compressor housing means, an orbiting scroll nested with said non-orbiting scroll, each of said scrolls having base means formed with a free side and a pressure side and a wrap extending outwardly from said pressure side, said orbiting scroll being mounted on an eccentric of a compressor crankshaft for orbital motion about the longitudinal axis of the compressor to produce a pressure continuum between the wraps and base means of said scrolls, the free side of said base means of said orbiting scroll having an overall substantially annular planar configuration with annular groove means provided therein and formed with side and top wall means and being juxtaposed a substantially annular planar sealing surface formed on said housing means, passage means formed through said base means of said orbiting scroll and placing said groove means in fluid communication with an intermediate pressure section of said pressure continuum for providing an axial compliance force against said top wall means of said groove means for urging said orbiting scroll axially toward said non-orbiting scroll to bring the wrap tips of each said scroll toward sealing engagement with the adjacent base means of the other scroll, annular seal means in said groove means having an annular web means provided with a substantially planar contact side positioned

in sliding, sealing contact with said sealing surface of said housing means, and further having annular, elastomeric, side sealing components slidably sealed against the side wall means of said groove means to provide axial compliance pressure chamber means which is sealed from ambient pressures, wherein said seal means comprises annular ring means which is axially slidably mounted in said groove means, annular shoulder means on the inner and outer peripheries of said ring means, and annular, elastomeric seal components sealingly contacting and being supported on said shoulder means and sealingly contacting the walls of said groove means to provide said axial compliance pressure chamber means, and wherein annular recess means is formed in a radially central portion of said contact side of said web means for reducing the contact area thereof, and aperture means is provided through said web means and placing said recess means in fluid communication with said chamber means for reducing the total force which is exerted on said web means and which urges it against said sealing surface on said housing means.

5,588,821

VACUUM PUMP WITH PLANETARY GEAR ACCELERATOR

Takashi Kinoshita, Hyogo, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed May 26, 1995, Ser. No. 451,428

Claims priority, application Japan, Nov. 4, 1994, 6-271452

Int. Cl.⁶ F04C 18/34; 25/02

U.S. Cl. 418—259

16 Claims



1. A vacuum displacement pump for use in a servo assisted brake or actuator in an automobile, said vacuum displacement pump comprising:

- a housing having a pump chamber;
- an input shaft for providing a rotational force to said vacuum pump;
- a rotor shaft connected to said input shaft and receiving a rotational force therefrom;
- a rotor eccentrically mounted in said pump chamber and connected to said rotor shaft and receiving a rotational force therefrom;
- a pump chamber assembly comprising:
 - an inlet for permitting entrance of a gas into said pump chamber;
 - an outlet for expelling said gas from said pump chamber;
 - a plurality of vanes, each vane slidably disposed in a groove of said rotor, wherein a suction is created in said pump chamber resulting from movement of said vanes due to a force created by the rotation of said rotor;
- a planetary gear device comprising:
 - a sun gear located on said rotor shaft;
 - a plurality of planetary gears connected to said input shaft and engaging said sun gear;
 - a ring gear which engages said planetary gears, wherein said planetary gear device has a gear ratio which is set so that the rotation of said rotor is accelerated relative to the rotation of said input shaft.

5,588,822

FLAME TRAP FOR USE IN A PULSE COMBUSTOR

Tsuneasu Hayakawa, and Makoto Kimura, both of Aichi, Japan, assignors to Paloma Kogyo Kahushiki Kaisha, Nagoya, Japan


Filed Apr. 19, 1995, Ser. No. 424,808

Claims priority, application Japan, Jul. 1, 1994, 6-173750

Int. Cl.⁶ F23C 11/04

U.S. Cl. 431—1

2 Claims



1. A flame trap and pulse combustor combination in which a mixture of air and fuel gas is supplied into a combustion chamber and subjected to pulse combustion, said flame trap comprising:

- a first metal foil tape;
- a second metal foil tape that is welded to one side of said first metal foil tape in such a manner that said second metal foil tape is corrugated so as to define cells between said first and second metal tapes;
- said first and second metal foil being spirally wound;
- wherein each of said cells in said flame trap is 2.25 mm² or less in aperture area, and
- a total numerical aperture of said flame trap is 75% or more.

5,588,823

ALCOHOL LAMP


Jung-Wuan Wu, 7F-2, No. 95-8 Chang Ping Road, Sec. 1, Taichung, Taiwan

Filed Nov. 13, 1995, Ser. No. 556,411

Int. Cl.⁶ F23D 11/44

U.S. Cl. 431—241

4 Claims



1. An alcohol lamp comprising:

- a container for containing alcohol having a less diameter protrudent opening projected upward from the top thereof;
- a cap member fitted to said opening having a large diameter upper portion fitted to a rim of said opening, a first thru hole

5,588,824

INJECTION NOZZLE

Robin T. D. McMillan, Untersiggenthal, Switzerland, assignor to ABB Management AG, Baden, Switzerland


Filed Nov. 2, 1995, Ser. No. 552,121

Claims priority, application Germany, Dec. 19, 1994, 44 45 279.9

Int. Cl.⁶ F23Q 9/08

U.S. Cl. 431—285

7 Claims



1. An injection nozzle for introducing fuels into compressed gaseous media, for use in premixing burners (10) for example, the injection nozzle (1) consisting primarily of a fuel conduit (2) and a passage (7) branching off from the fuel conduit, the fuel conduit (2) extending lengthwise essentially at right angles to the direction of introduction of the fuel and the passage (7) extending parallel to the direction of introduction of the fuel, wherein the fuel is fed via slots (6) in the fuel conduit and by means of the passage (7) to an atomization edge (5), the inside of the passage (7) being made up of distribution panels (3) between which distribution pins (4) are arranged.

5,588,825

LEAN PREMIXED FUEL BURNER


Larry W. Kostliuk, Edmonton, and Matthew R. Johnson, Antigonish, both of Canada, assignors to Governors of the University of Alberta, Edmonton, Canada

Filed Dec. 13, 1995, Ser. No. 572,269

Int. Cl.⁶ F23D 14/58

U.S. Cl. 431—349

9 Claims



1. A burner for burning a flow of premix lean gaseous fuel mixtures having an equivalence ratio of less than one comprising a nozzle having an outer periphery defining a passage through which said flow passes, an outer ring stabilizer means positioned within said passage and spaced from said periphery to directly divide said flow of gaseous fuel mixture through said passage into a primary flow portion and a secondary flow portion, said secondary flow portion being adjacent to said periphery and being of significantly less volume than said primary flow portion, flame dividing stabilizer means positioned to divide said primary flow portion into a plurality of discrete subsidiary flow portions, each said subsidiary flow portion forming a subsidiary flame having a base dimension correlated with the desired maximum height of its subsidiary flame, said flame dividing stabilizer means having at least one stabilizer element arranged to define spaces through which said subsidiary flows pass and that correspond with and define said base dimensions of said subsidiary flame immediately downstream thereof, each said ring and said at least one flame stabilizer element having a blunt cross sectional shape to generate recirculating flows of hot product gases that extend across its downstream end, said recirculating flows continually igniting its adjacent subsidiary flows to stabilize its adjacent said flames.

5,588,826
BURNER

Klaus Döbeling, Windisch; Jürgen Haumann, Rekingen; Hans P. Knöpfel, Besenbüren; Bettina Paikert, Oberrohrdorf; Thomas Ruck, Mellingen; Thomas Sattelmayer, Mandach, and Christian Steinhach, Neuenhof, all of Switzerland, assignors to ABB Management AG, Baden, Switzerland

Filed Aug. 3, 1995, Ser. No. 510,659


Claims priority, application Germany, Oct. 1, 1994, 44 35 266.2

Int. Cl.⁶ F23D 14/62

U.S. Cl. 431—354

18 Claims

1. A burner for a heat generator, the burner having a direction of flow, comprising:
a swirl generator for introducing a swirled combustion air flow into the burner;
means for injecting fuel into the combustion air flow in the swirl generator;
a mixing section connected at a downstream end of the swirl generator to receive the combustion air flow and fuel; and



transition means between the swirl generator and the mixing section including transition passages to guide the swirled combustion air flow and injected fuel from the swirl generator into the mixing section.

5,588,827

PASSIVE GAS SUBSTRATE THERMAL CONDITIONING APPARATUS AND METHOD

Richard S. Muka, Topsfield, Mass., assignor to Brooks Automation Inc., Chelmsford, Mass.


Continuation-in-part of Ser. No. 169,432, Dec. 17, 1993. This

application Jun. 7, 1995, Ser. No. 480,128

Int. Cl.⁶ F27B 5/04; F27D 7/02; 9/00

U.S. Cl. 432—5

12 Claims



1. An apparatus for changing temperature of a substantially planar substrate, the apparatus comprising:
a chamber;

a plate located in the chamber, the plate having a top surface with grooves therealong, the top surface having means for supporting a substrate thereon with a small gap between the substrate and the top surface;
means for introducing a gas into the chamber; and
means for heating the plate, wherein heat is transferred between the top surface of the plate and the substrate by gas conduction.

5,588,828

VERTICAL BRIGHT ANNEALING FURNACE FOR CONTINUOUS HEAT TREATMENT OF METAL STRIPS

Masato Nagata, Ikoma, Japan, and José Cornejo, Algeciras-Cádiz, Spain, assignors to Chugal Ro Co., Ltd., Osaka, Japan, and Acerinox, S.A., Madrid, Spain

Filed Mar. 31, 1995, Ser. No. 414,232

Claims priority, application Japan, Mar. 31, 1994, 6-062498

Int. Cl.⁶ F27B 9/28

U.S. Cl. 432—59

5 Claims



1. A vertical bright-annealing furnace for continuous heat treatment of metal strips, comprising a heating zone for heating a metal strip to a predetermined annealing temperature and a cooling zone for cooling the heated metal strip to a predetermined low temperature, characterized in that said heating zone comprises:

a muffle-type heating station composed of a shell lined with a heat-insulating material, a muffle arranged in said shell, and a first heating means for heating said muffle; and
a refractory-type heating station arranged just above said muffle-type heating station and composed of a shell lined with a heat-insulating material, and a second heating means for heating said metal strip;

said muffle-type and refractory-type heating stations being connected to one another by a flexible connecting unit which is extensible in the longitudinal direction of the heating zone, whereby allowing the metal strip to pass through the refractory-type heating station subsequent to the muffle-type heating station to heat it to a predetermined annealing temperature.

5,588,829

THRUST GRATING COOLER AND METHOD FOR COOLING HOT MATERIAL

Hans-Juergen Stahl, Koeln; Guenter Dittmann, Dessau; Reimer Doege, Zerbst; Richard Schnelder, Wermelskirchen, and Ralf Filges, Bergisch Gladbach 1, all of Germany, assignors to Kloeckner-Humboldt-Deutz AG, Koeln, Germany

Continuation of Ser. No. 11,180, Jan. 29, 1993, abandoned.

This application May 19, 1994, Ser. No. 273,147


Claims priority, application Germany, Jan. 31, 1992, 42 02 777.2; Dec. 16, 1992, 42 42 374.0

Int. Cl.⁶ F27D 15/02; F23K 3/08; F23H 3/02

U.S. Cl. 432—77

20 Claims

1. A thrust grating cooler for cooling hot material comprising:
a plurality of stationary grating plate carriers formed of hollow beams for receiving cooling air;
a plurality of reciprocally movable grating plate carriers formed of hollow beams for receiving cooling air;
a longitudinally reciprocally movable push frame secured to and carrying said movable grating plate carriers;



at least one cooling air channel arranged so as to move together with said push frame;
rigid connecting means for providing communication between said cooling air channel and said movable grating plate carriers; and
a seal for engagement between an air entry end of said movable cooling air channel and a stationary cooling air delivery nozzle.

5,588,830

COMBINED RADIANT AND CONVECTION HEATING OVEN


Leif E. B. Josefsson, Lake Orion, and Robert F. Monte, Fair Haven, both of Mich., assignors to ABB Paint Finishing, Inc., Auburn Hills, Mich.

Filed Jan. 13, 1995, Ser. No. 372,595

Int. Cl.⁶ F27B 9/00

U.S. Cl. 432—147

35 Claims



1. A combined radiant and convection heating oven for heating an object therein comprising:

a heating chamber extending along a longitudinal axis of the oven;
at least one motor-driven fan having an output in fluid communication with the heating chamber for delivering a convection gas to the chamber and having an input for receiving convection gas returning from the chamber;
at least one radiant heat emitting surface extending substantially parallel to the longitudinal axis and positioned within the heating chamber;
a duct carrying a heated gas and associated with the at least one radiant heat emitting surface for transferring heat thereto;
a source of the heated gas having an output coupled to the duct;
a temperature sensor positioned to monitor temperature of the convection gas returning from the chamber; and

means coupled to the temperature sensor for varying a rate at which heat is transferred from the convection gas and the radiant heat emitting surface to the object while maintaining ambient temperature in the chamber substantially at a predetermined set point.

5,588,831

FURNACE SYSTEM EQUIPPED WITH PROTECTED COMBUSTION NOZZLE USED IN FABRICATION OF SEMICONDUCTOR DEVICE


Satoru Okuyama, Yamagata, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Jan. 19, 1995, Ser. No. 492,446

Claims priority, application Japan, Jun. 23, 1994, 6-141421
Int. Cl.⁶ F27B 3/00

U.S. Cl. 432—159

18 Claims



1. A furnace system used in a fabrication of a semiconductor device, comprising:
a wafer chamber for treating at least one semiconductor wafer with heat;
a combustion sub-system including a combustion chamber, a first outlet gas nozzle for injecting oxygen gas into said combustion chamber and a second outlet gas nozzle formed of quartz for injecting hydrogen gas into said combustion chamber for generating said heat through a combustion with said oxygen gas; and
a guard member provided for said second outlet gas nozzle so as to space a high temperature region of a flame generated in said combustion from said second outlet gas nozzle, thereby preventing breakage of said second outlet gas nozzle due to said high temperature region.

5,588,832

METHOD OF FABRICATING METAL INSTRUMENTS FROM RAW MATERIAL AND ORTHODONTIC PLIERS MADE THEREBY


Farrokh Farzin-Nia, Inglewood, Calif., assignor to Ormco Corporation, Glendora, Calif.

Filed Aug. 23, 1994, Ser. No. 294,653

Int. Cl.⁶ A61C 3/00; B21D 28/00; B25B 7/02; B21K 5/00
U.S. Cl. 433—4

21 Claims

1. A method of fabricating an instrument having a handle and a



head each formed of a portion of two pivotally interconnected parts each having a convexly curved surface thereon, the method comprising the steps of:

providing a bar of raw metallic material having an elongated cross-section, generally flat parallel top and bottom surfaces and two opposite convex side surfaces;
separating the bar into two pieces by a cut through the bar to at least partially form a part from each of the pieces, each part having two ends and an outer surface of a convex shape defined by a convex side surface of the bar;
manufacturing from the parts an instrument having at least two outer surfaces having the convex shape;
forming a handle portion at one end of each of the parts that includes the outer surface thereof of the convex shape, and forming a head portion at the other end of each of the parts; and
pivotally interconnecting the parts between the handle portion and head portion to form an instrument having a handle and a head such that the force can be applied against the convex shape of the outer surfaces of the parts to pivot the head portions toward each other.

5,588,833

SYSTEM OF TREATMENT FOR USE IN FUNCTIONAL ORTHODONTICS

Georg Risse, Bogenstrasse 15-16, D-4400 Münster, Germany

Continuation of Ser. No. 965,408, Feb. 23, 1993, abandoned.

This application Nov. 16, 1994, Ser. No. 340,645

Int. Cl.⁶ A61C 3/00

16 Claims

U.S. Cl. 433—24

1. Apparatus comprising at least one orthodontic wire for use as an archwire and at least one bracket, said at least one wire having a rectangular cross-section and having two short edges and two long edges, said short edges being not longer than 0.015 inches (0.381 mm) and said long edges being not longer than 0.020 inches (0.508 mm), said at least one bracket having a single rectangular cross-section slot, said slot having two short sides and two long sides, the short sides being 0.018 inches (0.457 mm) and the long sides being 0.022 inches (0.559 mm), the dimensions of said at least one wire and said slot being selected so that, when said at least one wire is inserted into said slot, there is play of the wire in the slot.

5,588,834

SYSTEM FOR COLOR MATCHING A DENTAL PROSTHESIS

Richard E. Resk, 85-14 158th Ave., Howard Beach, N.Y. 11414;
Jeffrey R. Shapiro, 35 Liberty St. #19C, New York, N.Y. 10005, and Daniel Materdomini, P.O. Box 781, Woodland Hills, Calif. 91365


Filed May 18, 1995, Ser. No. 444,150

Int. Cl.⁶ A61C 19/10; 5/08

15 Claims

U.S. Cl. 433—26

1. A system for customized color matching of a dental prosthesis



comprising:

- a color range finder comprising a plurality of color elements, each of said elements identifying a different color than the remaining elements;
- a plurality of shells comprising individual shell groups, the shells of each of said group specially designed and anatomically configured for selective direct placement intimately over a specific anterior or posterior tooth that has been prepared for receiving said dental prosthesis, at least one of said specially designed and anatomically configured shells in each shell group corresponding in color to the basic color of each of said range finder elements; and
means for selectively coloring a selected shell.

5,588,835

ENDODONTIC OBTURATOR

Jimmie Kert, Norrevanget 76, DK-3500 Værløse, Denmark

Continuation of Ser. No. 325,664, Oct. 19, 1994, abandoned.

This application Nov. 1, 1995, Ser. No. 551,698

Int. Cl.⁶ A61G 5/02; A61C 5/02

U.S. Cl. 433—81

6 Claims



1. Appliance for use in filling an endodontically prepared root canal and of the kind comprising:
a) a central insertion rod (2) surrounded partly by
b) an elongate filler body (3, 4) of plastic material consisting of a core (4) and an outer filler body (3), said core (4) surrounding said rod (2) and said outer filler body (3) surrounding said core (4), said core (4) and said outer filler body (3) consisting of materials of differing softening points, and
c) the softening point of the material of said core (4) being lower than that of the material of said outer filler body (3).

5,588,836

MOUTH PROP AND TONGUE DEFLECTOR APPARATUS


Timothy J. Landis, Loomis, and Scott M. Perry, Auburn, both of Calif., assignors to OP-D-OP, Inc., Roseville, Calif.

Filed Oct. 23, 1995, Ser. No. 543,843

Int. Cl.⁶ A61C 17/06; 17/14

U.S. Cl. 433—93

20 Claims



1. A mouth prop and tongue retractor apparatus, comprising:

- (a) a handle;
- (b) a base, said handle rotatably coupled to said base;
- (c) a mouth prop, said mouth prop coupled to said base;
- (d) tongue retractor means for positioning a patient's tongue;
- (e) suction means for removing saliva from a patient's mouth, said suction means coupled to said tongue retractor means;
- (f) gimbal adjustment means for adjustably positioning said tongue retractor means and said suction means relative to said mouth prop; and
- (g) extension adjustment means for positioning said tongue retractor means and said suction means relative to said handle and said base.

5,588,837

METHOD AND EQUIPMENT FOR THE FORMATION OF PROSTHETIC TOOTH STRUCTURES FOR FASTENING TO IMPLANTS

Gunter Rubeling, Bremerhaven, and Burghard Otten, Misselwarden, both of Germany, assignors to Günter Rübeling, Germany


Filed Jan. 11, 1995, Ser. No. 373,639

Claims priority, application Germany, Jan. 28, 1994, 44 02 511.4

Int. Cl.⁶ A61C 13/12; 13/225; 8/00

U.S. Cl. 433—172

8 Claims



1. A method of forming prosthetic tooth structures for fastening to implants in a patient's jawbone, comprising the steps of:
producing a pattern from a portion of the patient's jawbone containing the implants and arranging metal pattern sockets in the pattern so that positions of the pattern sockets in the pattern correspond to positions of the implants in the patient's jawbone;
releasably fastening dummy implants into each of the pattern sockets, heads of the dummy implants corresponding to heads of respective implants in the patient's jawbone;
producing a metal prosthetic tooth structure using the pattern and the dummy implants;
replacing the dummy implants with metal implant electrodes releasably fastened in the pattern sockets, heads of the implant electrodes corresponding with the heads of respective implants in the patient's jawbone when taking into consideration a sparkgap for spark erosion;
connecting the prosthetic tooth structure and either the pattern sockets or the implant electrodes to spark erosion equipment so that the prosthetic tooth structure forms a first electrode and, respectively, either the pattern sockets or the implant electrodes form a second electrode, and
moving the pattern and the prosthetic tooth structure against each other so as to erode the prosthetic tooth structure so that the prosthetic tooth structure is adapted to the heads of the implants in the patient's jawbone.

5,588,838


FIXTURE FOR USE IN A DENTAL IMPLANT SYSTEM
 Stig G. V. Hansson, Askim, and Anders Holmén, Sweden, both of Sweden, assignors to Astra Aktiebolag, Södertälje, Sweden
 PCT No. PCT/SE93/00871, § 371 Date Apr. 26, 1995, § 102(e)
 Date Apr. 26, 1995, PCT Pub. No. WO94/09717, PCT Pub. Date May 11, 1994

PCT Filed Oct. 25, 1993, Ser. No. 424,404

Claims priority, application Sweden, Oct. 28, 1992, 9203184
 Int. Cl.⁶ A61C 8/00

U.S. Cl. 433—173

9 Claims



1. In a fixture for use in a dental implant system, said fixture having an outer end provided with a conically flaring outer surface intended to at least partly abut the bone tissue, the improvement wherein said conically flaring outer surface is provided with a circumferentially oriented, defined micro-roughness (9, 109) having a height between 0.02 and 0.20 mm.

5,588,839

INFORMATION PROCESSING APPARATUS

Isamu Shimoda, Zama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 77,050, Jun. 16, 1993, abandoned.


This application Feb. 15, 1996, Ser. No. 601,819

Claims priority, application Japan, Jun. 16, 1992, 4-157053

Int. Cl.⁶ G09B 21/00

U.S. Cl. 434—114

23 Claims



1. An information processing apparatus for physically-handicapped users, said apparatus comprising:
 control means for generating information on the operating state of said information processing apparatus;
 input means for inputting information to said control means;
 a first display output unit for displaying a plurality of information on the operating state of said information processing apparatus as visual display information;
 said control means generating a plurality of kinds of output signals corresponding to each of the plurality of information to be displayed visually on said first display output unit;

conversion means for converting output signals generated by said control means to one of auditory display information adapted to be auditorily perceived by a visually impaired user and tactile display information adapted to be perceived using tactile perception by a hearing impaired user; and
 a second display output unit, for outputting the information converted by said conversion means as a sound, or vibration, comprising an electromechanically vibrated member.

23. An electronic apparatus for processing information, said apparatus comprising:

generating means for generating mode information relating to the functioning of said apparatus and output signals corresponding to the kinds of mode information;
 input means for inputting information to said generating means;
 display means for displaying the mode information generated by said generating means;
 conversion means for converting the output signals generated by said generating means to a sound or vibration corresponding to the kinds of the mode information;
 output means, comprising an electromechanically vibrated member, for outputting the output signals corresponding to the kind of mode information displayed by said display means with the sound or the vibration converted by conversion means; and
 instruction means for instructing said output means to output the output signals corresponding to the kind of mode information displayed by said display means.

5,588,840

Patent Not Issued For This Number

5,588,841

APPARATUS AND METHOD FOR THE TEACHING OF STANDING BALANCE


Richard W. Mechling, 526 St. Charles Ave. NE., Atlanta, Ga. 30308

Filed Apr. 5, 1995, Ser. No. 416,639

Int. Cl.⁶ G09B 19/00

U.S. Cl. 434—255

5 Claims



1. A method of teaching the skill of standing balance, comprising the steps of:
 (a) providing lower-leg support to allow maintenance of a relatively vertical tibial and calf position;
 (b) providing foot support to allow maintenance of foot position relative to said lower-leg support;
 (c) situating a subject in a standing position with lower legs and feet supported by said lower-leg support and said foot support, respectively;

- (d) selecting a degree of calf and tibial movement relative to vertical to be allowed by said lower-leg support and;
- (e) allowing the subject to attempt to perform standing balance with said foot position and with said allowed degree of tibial and calf movement relative to vertical.

5,588,842

KARAOKE CONTROL SYSTEM FOR A PLURALITY OF KARAOKE DEVICES

Osamu Nishimura, and Hiroshi Nishikawa, both of Nagoya, Japan, assignors to Brother Kogyo Kabushiki Kaisha, Nagoya, and Xing Inc., Aichi-ken, both of Japan


Filed Apr. 5, 1995, Ser. No. 417,389

Claims priority, application Japan, Apr. 6, 1994, 6-093696

Int. Cl.⁶ G09B 5/00; G10H 1/36

U.S. Cl. 434—307 A

13 Claims



1. A karaoke control system for controlling a plurality of karaoke devices to play accompaniment music of desired songs while displaying lyrics of the desired songs and background images suitable for the desired songs, the karaoke control system comprising:

- a central control device including song data storing means for storing song data for a plurality of songs, the song data for each song including music data representative of an accompaniment music of the corresponding song and lyric data representative of lyrics of the corresponding song, the song data being added with image genre data representative of an image genre most suitable for the corresponding song; and
- a plurality of karaoke devices connected to the central control device via a transmission line, each of the plurality of karaoke devices including song selecting means for selecting a song desired to be sung out of the plurality of songs, wherein the central control device further includes:
 song data retrieving means for retrieving song data for the songs selected at the karaoke devices;
- a plurality of image data memory means for storing a plurality of image data groups of a plurality of image genres, each image data group being made from two or more image data edited to represent images of a corresponding image genre, and at least one image data group of at least one common image genre, each common image genre being common to several ones of the plurality of image genres, the image data group of each common image genre being made from two or more image data edited to represent images of a corresponding common image genre;
- a plurality of image data retrieval means for retrieving image data from the plurality of image data memory means;
- image genre determination means for determining image genres most appropriate for the selected songs, based on the image genre data added to the song data retrieved for the selected songs;
- control means for controlling the image data retrieval means to retrieve image data from the plurality of image data memory

means, the control means controlling each of the image data retrieval means to retrieve image data from one of an image data group of the determined image genre and an image data group of a common image genre that is common to the determined image genre; and

transmission means for transmitting the retrieved song data and the retrieved image data to the karaoke devices, and

wherein each of the plurality of karaoke devices includes:

music play means for receiving the music data included in the transmitted song data and for playing accompaniment music based on the song data; and

image reproduction means for receiving the lyric data included in the transmitted song data and the transmitted image data, for combining the lyrics represented by the lyric data and the images represented by the image data as background images, and for displaying the combined images.

11. A karaoke control system for controlling a plurality of karaoke devices to play accompaniment music of desired songs while displaying lyrics of the desired songs and background images suitable for the desired songs, the karaoke control system comprising:

a central control device and a plurality of karaoke devices connected to the central control device via a transmission line, wherein the central control device includes:

a song data storing unit for storing song data for a plurality of songs, the song data for each song including music data representative of an accompaniment music of the corresponding song and lyric data representative of lyrics of the corresponding song, the song data being added with image genre data representative of an image genre most suitable for the corresponding song;

a plurality of image data memories for storing a plurality of image data groups of a plurality of image genres, each group being formed from two or more sets of image data edited to represent images of a corresponding image genre, and at least one common image data group, each group being formed from two or more sets of image data edited to represent images of a corresponding common image genre that is common to several ones of the plurality of image genres; and
 a plurality of image data retrieval units for retrieving image data from the plurality of image data memories;

wherein each of the plurality of karaoke devices includes a song selecting unit for selecting a song desired to be sung out of the plurality of songs,

wherein the central control device further includes:

a song data retrieving unit for retrieving song data for the songs selected at the karaoke devices from the song data storing unit;

an image genre distinguishing unit for distinguishing image genres most appropriate for the selected songs, based on the image genre data added to the song data retrieved for the selected songs;

a control unit for controlling the image data retrieval units to retrieve image data from the plurality of image data memories, the control unit controlling each of the image data retrieval unit to retrieve image data of an image data group of the distinguished image genre, the control unit compulsorily controlling at least one of the plurality of image retrieval units to retrieve image data of an image data group of a common image genre common to the distinguished image genre, regardless of what image genre is distinguished by the image genre distinguishing unit, when the number of image genres distinguished by the image genre distinguishing unit increases to a value close to the number of image data retrieval units; and

a transmission unit for transmitting the retrieved song data and the retrieved image data to the karaoke devices.

5,588,843

ROTARY ELECTRICAL CONNECTOR


Mohi Sobhani, Encino, Calif., assignor to Hughes Aircraft Company, Los Angeles, Calif.

Filed Dec. 8, 1994, Ser. No. 351,914

Int. Cl.⁶ H01R 39/00

U.S. Cl. 439—22

14 Claims



1. A rotary electrical connector, comprising:
 - a first-side connector member comprising a printed wiring board and having a first-side connector face lying perpendicular to a rotational axis, the first-side connector face having a plurality of first-side engagement members arranged as concentric rings thereon;
 - a plurality of first-side electrical conductors, each of the first-side electrical conductors including a first-side electrical contact with at least one of the plurality of first-side engagement members;
 - a second-side connector member having a second-side connector face lying perpendicular to the rotational axis, the second-side connector face having a plurality of second-side engagement members thereon disposed such that each of the second-side engagement members contacts one of the first-side engagement members when the first-side engagement face and the second-side engagement face are placed into facing contact;
 - a plurality of second-side electrical conductors, each of the second-side electrical conductors including a second-side electrical contact with at least one of the plurality of second-side engagement members;
 - support means for positioning the first-side connector member in facing contact with the second-side connector member and for permitting the second-side connector member to rotate with respect to the first-side connector member about the rotational axis; and
 - biasing means for biasing the first-side connector face against the second-side connector face.

5,588,844

VARIABLE ORIENTATION, SURFACE MOUNTED CONNECTOR

Lynn R. Sipe, Lewistown, Pa., assignor to The Whitaker Corporation, Wilmington, Del.


Continuation of Ser. No. 342,934, Nov. 21, 1994, Pat. No. 5,520,545. This application Mar. 14, 1996, Ser. No. 615,382

Int. Cl.⁶ H01R 13/73; 23/72

U.S. Cl. 439—65

13 Claims

1. An electrical connector comprising an insulative housing and a plurality of electrical contacts, each of said contacts being mounted in said housing so as to be surface mountable to a printed circuit board regardless of whether said electrical connector is mounted vertically or horizontally thereto, and two board mounts laterally disposed in two corresponding cavities, wherein each of said board mounts is adapted to rotate relative to said housing between (i) a first position wherein said electrical connector is oriented vertically with respect to said printed circuit board when



surface mounted thereto, and (ii) a second position wherein said electrical connector is oriented horizontally with respect to said printed circuit board when surface mounted thereto.

5,588,845

CONNECTORS FOR BASE BOARDS AND METHODS OF CONNECTOR OF BASE BOARDS

Takaki Naitoh, Inagi, and Okitsugu Furuya, Tokyn, both of Japan, assignors to The Whitaker Corporation, Wilmington, Del.


Filed Dec. 8, 1994, Ser. No. 351,982

Claims priority, application Japan, Feb. 9, 1994, 6-036551

Int. Cl.⁶ H01R 4/58; 9/09

U.S. Cl. 439—66

18 Claims



1. A connector for interconnecting first and second base boards each having a plurality of electrical lands, comprising:
 - a plurality of first contacts each having a connecting section arranged for engaging a respective one of the electrical lands on the first base board, and a contacting section;
 - a plurality of second contacts each having a connecting section arranged for engaging a respective one of the electrical lands on the second base board, and a contacting section; and
 - an elastic connecting component interconnecting the contacting sections of the first contacts with respective ones of the contacting sections of the second contacts.

5,588,846

RIGHT ANGLE ELECTRICAL CONNECTOR


Robert D. Irlbeck, Greensboro; Warren A. Bates, Winston-Salem, both of N.C.; Robert Dumas, North Palm Beach, Fla., and Keith L. Volz, Jamestown, N.C., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Aug. 25, 1995, Ser. No. 519,208

Int. Cl.⁶ H01R 9/09

U.S. Cl. 439—66

14 Claims



1. An electrical connector for electrically interconnecting circuit traces on a printed circuit board and circuit traces on an electrical device, said electrical connector comprising:
 - a resilient electrical component with a flexible film circuit wrapped around a center thereof for electrical interconnection with said circuit traces;
 - a connector block member disposed adjacent to said electrical device;
 - first and second walls formed on said electrical device and said block member, respectively, said walls defining a chamber for receipt of said resilient electrical component; and
 - a biasing member located within said chamber for biasingly engaging said resilient electrical component when said resilient electrical component is pressed into said chamber, whereby said resilient electrical component is translated and deformed within said chamber by the pressing action of said printed circuit board.

5,588,847

CHIP CARRIER MOUNTING SYSTEM

John O. Tate, P.O. Box 353, Uxbridge, Mass. 01569


Filed Apr. 13, 1995, Ser. No. 421,839

Int. Cl.⁶ H01R 9/09

U.S. Cl. 439—71

4 Claims

1. A chip carrier mounting system capable of mounting a computer chip on a printed circuit board, said mounting system comprising:
 - a chip carrier socket adapted for mounting on a printed circuit board, said chip carrier socket having a rectangular frame with inwardly facing surfaces which define a rectangular opening, and a plurality of spaced-apart, inwardly projecting contact members each being mounted on the frame and resiliently movable along a plane generally perpendicular to the plane of its respective surface, each contact member being constructed of electrically conductive material and having a leg with a base and an inwardly extending, tapered foot portion; and
 - a chip carrier constructed and arranged for receiving and securing a chip thereto, said chip carrier having outwardly facing surfaces adapted to face the inwardly facing surfaces of the chip carrier socket when placing the chip carrier within the opening of the socket, and a plurality of spaced-apart receiving slots in registry with and capable of receiving said contact members therein for securing the chip carrier to the chip carrier socket, each receiving slot having an electrically con-



ductive surface mount for providing electrical connection between the chip, chip carrier, chip carrier socket and printed circuit board when said foot portion of each contact member is in resilient engagement with the electrically conductive surface mount of its respective receiving slot, wherein said foot portion of each contact member is formed to taper from the base of the leg in a widthwise dimension to a narrowed, rounded end for enhancing the electrical connection between said contact member and surface mount and for maintaining said chip carrier and said chip carrier socket in assembled relation.

5,588,848

LOW INDUCTANCE SURFACE-MOUNT CONNECTORS FOR INTERCONNECTING CIRCUIT DEVICES AND METHOD FOR USING SAME


Ronald L. Law, Allen; Apurba Roy, Rockwall, and Steven A. Shewmake, Mesquite, all of Tex., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Sep. 8, 1994, Ser. No. 302,559

Int. Cl.⁶ H01R 9/09

U.S. Cl. 439—83


19 Claims



1. A surface-mount connector for electrically interconnecting two circuit devices comprising:
 - a metallic rectangular parallelepiped which is hollow along one axis, said parallelepiped having at least one slot in a plane transverse to said axis and extending over three of the four sidewalls of said hollow parallelepiped, the remaining sidewall being unslotted.

5,588,849
CONNECTOR WITH PIN TERMINALS ADAPTED FOR SURFACE MOUNTING
 Richard A. Kile, Harrisburg, Pa., assignor to The Whitaker Corporation, Wilmington, Del.
 Continuation of Ser. No. 325,007, Oct. 18, 1994, abandoned.
 This application Aug. 2, 1996, Ser. No. 691,441
 Int. Cl.⁶ H01R 9/09
 U.S. Cl. 439—83

5 Claims



1. An electrical connection arrangement comprising:
 a circuit board having a connector site having a plurality of contact pads in an array of at least two rows thereof on a board surface, and at least two through-holes substantially at ends of the array of contact pads, the contact pads and at least two through-holes defining electrical connection sites; and
 an electrical connector comprising an insulative housing including a base having a bottom surface mounted on a surface of a circuit board, and including at least twelve conductive terminals disposed in said housing and including respective pin terminal portions, said pin terminal portions extending initially orthogonally beyond said bottom surface of said base in an array of at least two rows, at least two of the pin terminal portions at ends of said at least two rows being unbent to provide locating pin terminal portions adapted to be soldered in the at least two through holes of the circuit boards, and remaining pin terminal portions being bent to extend parallel to the base and across respective contact pads along the surface of the circuit board, with ones of said bent terminal portions extending in a first direction and others thereof extending in an opposed second direction to provide at least two rows of surface mount electrical connections with said at least two rows of contact pads.

remaining portions of said conductive terminals being identical within said housing, and said at least two through-holes being located asymmetrically within the array of contact pads, and said at least two unbent terminal portions being correspondingly located asymmetrically within the array of terminal portions.

whereby the circuit board need not provide a through-hole at every electrical connection site thereof, and said connector is keyed by selecting said at least two terminal portions located asymmetrically within the array of terminal portions to remain unbent while the remaining terminal portions are bent, to establish polarization with respect to the circuit board to allow mounting in only a single orientation.

5,588,850
GROUNDING MEANS FOR MEMORY CARD CONNECTOR
 H. T. Pan, and Chu-Mei Chen, both of Taipei Hsien, Taiwan, assignors to Tongrand Limited, Queensway, Hong Kong
 Filed Aug. 8, 1995, Ser. No. 512,335
 Int. Cl.⁶ H01R 13/62

U.S. Cl. 439—92

9 Claims

1. A grounding arrangement for a memory card connector, said memory card connector comprising a guide frame having a pair of guiding slots, each of said guiding slots having formed therein a



first pair of horizontally extending notches and a vertically extending receiving slot, said grounding arrangement being fastened to and generally received within only a corresponding one of said guiding slots and comprising:

an elongated body;

a curved contact portion proximate one end of said elongated body that has a portion above a surface of said elongated body;

an end portion integrally extending from said contact portion and positioned at a remote end beyond said contact portion of said elongated body;


a first pair of horizontally extending bent portions respectively located at opposing sides of said elongated body and extending perpendicular to and away from the surface of said elongated body, each of said first bent portions having thereon a latching arrangement;

wherein when said grounding arrangement is assembled to a designated location on said guide frame of said memory card connector, said end portion is received in said receiving slot of said guiding slot, each of said first pair of bent portions is inserted into a corresponding one of said first pair of notches, and said latching arrangement of said first pair of bent portions latch with corresponding configurations inside said corresponding notches.

5,588,851
CONNECTOR FOR A CABLE FOR HIGH FREQUENCY SIGNALS
 Danny Morlion, St. Amandsberg; Luc Jonckheere, Leuven, and Jan P. K. van Koetsem, Zwijndrecht, all of Belgium, assignors to Framatome Connectors International, Paris, France
 Division of Ser. No. 399,171, Mar. 2, 1995, Pat. No. 5,525,066.
 This application Jan. 31, 1996, Ser. No. 594,765
 Claims priority, application Netherlands, Mar. 3, 1994, 9400321

Int. Cl.⁶ H01R 4/66

10 Claims




1. Connector for a cable for high frequency signals, in particular for connecting the cable with contact pins on a printed circuit board, comprising female signal contact members, a ground plate and a housing of dielectric material with cavities having the female contact members therein, wherein a central part of the ground plate

is bent into a U-shaped part with opposite legs to form a female ground contact member unitary with the ground plate, contact springs being formed in the opposite legs of the U-shaped part, said contact springs being adapted to engage a ground contact pin insertable into the U-shaped part, wherein the female signal contact members are provided at each side of the female ground contact member.

5,588,852
ELECTRICAL CONNECTOR HAVING SOCKET CONTACTS WITH SAFETY SHIELDS
 Dean A. Puerner, Maricopa, Ariz., assignor to The Whitaker Corporation, Wilmington, Del.
 Filed Mar. 21, 1995, Ser. No. 408,050
 Int. Cl.⁶ H01R 13/44; 13/187

U.S. Cl. 439—135

8 Claims



1. A plug connector which is matable with a receptacle connector to form an electrical connector assembly, the plug connector comprising:

a dielectric housing having at least one cavity which extends inwardly from a mating face of the housing;

an electrically conductive socket contact disposed in the at least one cavity, the socket contact being generally tubular with inner and outer surfaces and having a contact section adapted for mating with a corresponding pin contact of the receptacle connector, the contact section having an end face disposed in a vicinity of the mating face;

a first dielectric member disposed on the socket contact and extending at least over the end face; and

a second dielectric member disposed within the socket contact the second dielectric member having a post disposed in the contact section so as to define a gap between the post and the inner surface of the contact section;

wherein inadvertent electrical engagement with the socket contact is prevented.

5,588,853
CLOSURE CAP WITH GASKET FOR ELECTRICAL CONNECTOR HOUSING
 John C. Anthony, Fairfield, Conn., assignor to Hubbell Incorporated, Orange, Conn.
 Filed May 17, 1995, Ser. No. 442,897
 Int. Cl.⁶ H01R 13/44

U.S. Cl. 439—136


25 Claims

1. A sealing arrangement for sealing a mounted electrical connector housing, comprising:

a closure cap including an annular sealing member constructed of a sealing material for releasably engaging the electrical connector housing;

a gasket having a body portion with an opening which is sized for accommodating a portion of the mounted electrical connector through said opening of said body portion; and


a strap directly attached to said closure cap and to said gasket.



5,588,854
ELECTRICAL CONNECTION DEVICE BETWEEN HANDLE AND STEERING COLUMN
 Tohru Ikumi, Nobuhiko Suzuki, and Satoshi Ishikawa, all of Shizuoka-ken, Japan, assignors to Yazaki Corporation, Tokyo, Japan
 Filed Aug. 22, 1995, Ser. No. 517,623
 Claims priority, application Japan, Aug. 26, 1994, 6-202250
 Int. Cl.⁶ H01R 3/00

U.S. Cl. 439—164

6 Claims



1. An electrical connection device between a handle having an axle and a steering column for a vehicle, said device comprising:
 a rotor into which the handle axle is fixed, said rotor having an annular projection with an axially facing radially convex surface;

a housing fixed to the steering column to rotatably support said rotor, said housing and said rotor defining an annular space, said housing having an annular recess with a radially concave surface for engaging the axially facing convex surface of said rotor; and

a flexible flat cable accommodated in the annular space and of a length to accommodate clockwise and counterclockwise rotations of said rotor, said flexible flat cable having one end connected to said housing and another end connected to said rotor thereby to electrically connect said housing with said rotor.

2. An electrical connection device as claimed in claim 1, wherein said rotor comprises a first rotor element to which said another end of said flat cable is connected, and a second rotor element having an axial end engaged with a side of the first rotor element from outside of said housing and having another axial end exposed outside of said housing.

5,588,855

CONNECTOR


Yuichi Nankoh, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Yokkaichi, Japan

Filed Apr. 10, 1995, Ser. No. 419,422

Claims priority, application Japan, Apr. 20, 1994, 6-106086
Int. Cl.⁶ H01R 31/08

U.S. Cl. 439—188

11 Claims



1. A connector comprising:

- a housing having a plurality of supply terminal cavities and at least one short-circuit terminal cavity, said housing further including a mount hole communicating with said supply terminal cavities and with said short-circuit terminal cavity;
- a plurality of supply circuit terminals in the respective supply terminal cavities of the housing;
- a short-circuit terminal in the short-circuit terminal cavity of the housing, said short-circuit terminal including a plurality of contact portions aligned respectively with the supply circuit terminals; and
- a retainer movable from a temporary locking position in said mount hole to a main locking position therein, said retainer having a locking means for locking engagement with said supply circuit terminals and with said short-circuit terminal when said retainer is in said main locking position, said retainer further having biasing means for pressing the contact portions of the short-circuit terminal into shorting electrical contact with the respective supply circuit terminals.

5,588,856

SEALING MEMBER AND METHODS OF SEALING

Mary A. Collins, Fremont; David G. Perkins, Union City, and Harry E. White, Newark, all of Calif., assignors to Raychem Corporation, Menlo Park, Calif.


Continuation-in-part of Ser. No. 584,320, Sep. 18, 1991, abandoned. This application Jan. 14, 1992, Ser. No. 762,533

Int. Cl.⁶ H01R 4/60

U.S. Cl. 439—204

9 Claims

7. A preformed sealing member for sealing an open end of a hollow member which comprises a self-supporting article having at least one layer of sealant positioned longitudinally between two constraining layers, wherein each of said layers has substantially the same lateral dimensions and at least one of said constraining layers comprises a compressible foam.



5,588,857

CENTERING SPRING SUPPORT FOR PANEL MOUNT CONNECTORS

Günter Feldmeier, Lorsch, and Christian Schrettinger, Bensheim, both of Germany, assignors to The Whitaker Corporation, Wilmington, Del.


Filed Dec. 22, 1994, Ser. No. 362,319

Claims priority, application United Kingdom, Jan. 4, 1994, 9400024

Int. Cl.⁶ H01R 13/64

U.S. Cl. 439—248

8 Claims



1. An electrical connector securable to a panel, and being movable with respect to the panel, the connector being characterized in that the connector comprises a securing member comprised of a resilient centering spring member and a separate fastener member, said spring member cooperable with the fastener member for flatably securing said connector to the panel, and biasing said connector toward a central axial position with respect to the panel.

5,588,858

CONNECTOR SYSTEM WITH WEDGE AND GROMMET RETAINER

Lester J. Lester, Signal Hill, and Gary N. Van Trump, Santa Ana, both of Calif., assignors to ITT Corporation, Santa Ana, Calif.

Filed Mar. 15, 1995, Ser. No. 404,894


Int. Cl.⁶ H01R 13/52

U.S. Cl. 439—275

9 Claims

1. A connector having an axis, having a housing front insulator portion with a plurality of contact-receiving holes, and having an elastomeric grommet lying within said housing at a location rearward of said front insulator with said grommet having a plurality of axially-extending through holes for passing wires, characterized by:

- a retainer mounted on said housing rearward of said grommet and having a plurality of retainer holes that can pass wires



that extend through said grommet holes, said retainer having a plurality of forwardly projecting posts arranged in a first pattern;

said grommet has a rear end with a plurality of post-receiving holes arranged in said first pattern to receive said posts.

5,588,859

HERMAPHRODITE CONTACT AND A CONNECTION DEFINED BY A PAIR OF SUCH CONTACTS

Denis Maurice, Rimogne, France, assignor to Alcatel Cable Interface, Vigne Aux Bois, France


Filed Sep. 15, 1994, Ser. No. 306,595

Claims priority, application France, Sep. 20, 1993, 93 11162

Int. Cl.⁶ H01R 4/24

U.S. Cl. 439—290

7 Claims



1. A hermaphrodite contact, flat and substantially rectangular in shape, comprising a first end portion and a corresponding first end edge, a second end portion and a corresponding second end edge of said contact opposite said first end portion and said first end edge, an intermediate portion between said first and second end portions, at least one resilient arm which extends along said intermediate and second end portions and defines a hermaphrodite coupling terminal arm along said second end portion of the contact for hermaphrodite coupling of said contact to another substantially identical contact provided with at least one corresponding resilient arm, at least one truncated branch which extends from the first end portion towards the second end portion and along each resilient arm and is shorter than this resilient arm, and a main insulating displacement fork which extends substantially along the intermediate portion of the contact and between each resilient arm and the truncated branch and has an opening access facing the second end portion of said contact.

5,588,860

BULB SOCKET

Takahiro Uchiyama, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Japan


Filed Jul. 20, 1994, Ser. No. 277,770

Claims priority, application Japan, Aug. 6, 1993, 5-215035

Int. Cl.⁶ H01R 4/48

U.S. Cl. 439—336

6 Claims



1. A bulb socket for receiving a bulb having a plus electrode and a minus electrode, said bulb socket comprising: a socket housing having a bottom wall, an outer side wall, an inner side wall and retaining portion, said bottom wall and inner side wall defining a bulb receiving portion, said outer side wall surrounding the inner side wall, and said retaining portions being disposed between the inner and outer side walls, a bottom surface of the retaining portions having spaced openings of connection holes extending at least partially therethrough in an axial direction of the socket housing; a plus terminal mounted in said socket housing, said plus terminal including a bulb-side plus terminal portion for electrically connecting with the plus electrode of the bulb and a feeder-side plus terminal portion for electrically connecting with an external plus terminal, said bulb-side plus terminal portion and said feeder-side plus terminal portion being disposed in a juxtaposed condition within said socket housing; and a minus terminal mounted in said socket housing, said minus terminal including a bulb-side minus terminal portion for electrically connecting with the minus electrode of the bulb and a feeder-side minus terminal portion for electrically connecting with an external minus terminal, said bulb-side minus terminal portion and said feeder-side minus terminal portion being disposed in a juxtaposed condition within said socket housing, wherein said feeder-side plus terminal portion and said feeder-side minus terminal portion each have a portion that extend in the axial direction within the connection holes of the retaining portions.

5,588,861

ZIF CHIP SOCKET

Peter K. Townsend, Camp Hill, Pa., assignor to Berg Technology, Inc., Reno, Nev.

Continuation-in-part of Ser. No. 275,959, Jul. 15, 1994, This application Dec. 30, 1994, Ser. No. 367,085


Int. Cl.⁶ H01R 4/50

U.S. Cl. 439—342

1 Claim

1. A pin grid array socket for connecting an integrated circuit (IC) having a plurality of pins to a circuit substrate, said socket comprising:

- a base having a plurality of contacts and said base being mountable on said circuit substrate so that said contacts can be directly electrically connected to said circuit substrate said



base having at least two side walls therein, each of said side walls having a plurality of support receiving slots;
a cover having a plurality of insertion holes for receiving said plurality of pins and said cover being attached to said base and slidably from a first position to a second position so that said plurality of pins can be moved from said first position to said second position to form an electrical interface with said plurality of contacts;
a plurality of buttresses connected to said cover each of said buttresses directly supporting a corresponding pin when the cover is in the first and second positions and
said contacts each comprising a moveable contact beam element for engaging the corresponding pin, a base member including a barb for helping engage the contact with the base and an integral spring support means having an opposed pair of transverse arcuate arms each of said arcuate arms having a bent portion bearing against one of the side walls and a terminal end portion which engages one of the slots in one of the side walls of the base, wherein the base further comprises a plurality of buttresses projecting upwardly therefrom for directly supporting the contacts.

5,588,862

LOCKING MECHANISM


Richard W. Perkins, 13800 Valerio St., Van Nuys, Calif. 91405, and Bradley L. Read, 3905 Division St., Los Angeles, Calif. 90065

Filed Dec. 14, 1994, Ser. No. 364,295

Int. Cl.⁶ H01R 4/50

U.S. Cl. 439—347

6 Claims



1. A locking mechanism, comprising:

- a male base member;
- a male connector that has a plurality of male pins that extend from said male base member, each male pin having a locking aperture;
- a female connector that has a plurality of female pins that are coupled to a handle by a chassis that is located within a channel of a female base member, said female pins being capable of moving between an engaged position and non-engaged position, said female base member having a plurality of alignment apertures that contain said female pins and receive said male pins so that said female pins are engaged and moved by said male pins so that said female pins become

aligned with said locking apertures and slide through said locking apertures to secure said male base member to said female base member;
said handle includes a button that is coupled to said chassis to simultaneously move said female pins when said button is depressed and;
a spring member that is coupled to said button and said chassis to simultaneously push said female pins into said engaged position when said button is released.

5,588,863

LIGHT BULB SOCKET STRUCTURE HAVING A BULB HOUSING WITH ENGAGING MEANS

Hsin-Wei Wu, 5, Lane 193, Kong Yean Road, Chinchu, Taiwan

Filed Sep. 26, 1995, Ser. No. 534,243

Int. Cl.⁶ H01R 13/627

U.S. Cl. 439—356

1 Claim



1. An improved light bulb socket structure, comprising:

- a longitudinally extended socket shell having a cavity formed therein, said cavity being open on a first end of said socket shell, said first end of said socket shell having a resilient engagement rim formed thereon with a plurality of longitudinally directed slots formed therein, said socket shell including a latch member extending from a second end thereof;
- a small light bulb disposed at least partially within said cavity of said socket shell;
- a socket cap having a tubular wall defining a cavity extending longitudinally from an open first end of said socket cap for receiving said socket shell therein, said tubular wall having an opening formed therethrough adjacent a partially closed second end of said socket cap for releasable locking engagement with said latch member for securement of said socket shell within said cavity of said socket cap;
- a plurality of conductor plates disposed within said cavity of said socket cap for electrical coupling with conductors of said small light bulb; and,
- a bulb-shaped outer housing open on one end and releasably coupled to said socket shell, said outer housing having a hollow interior for receiving at least a portion of said small light bulb therein, said open end of said outer housing having a raised flange formed on an outer surface thereof for engagement with said resilient engagement rim.

5,588,864

CONNECTION DEVICE OF A COMPUTER CONNECTOR

Chao-Tsung Lin, 1st Fl., No. 2, Alley 9, Lane 45, Pao-Hsin Road, Hsin-Tien, Taipei, Taiwan

Filed Mar. 11, 1994, Ser. No. 208,595

Int. Cl.⁶ H01R 13/627

U.S. Cl. 439—357

1 Claim

1. A computer connector having a connection device, said connection device comprising:

5,588,866

CONNECTOR SYSTEM WITH A ROLLER LATCHING MECHANISM


Richard E. Rothenberger, Harrisburg, Pa., assignor to The Whitaker Corporation, Wilmington, Del.

Filed Nov. 1, 1994, Ser. No. 332,975

Int. Cl.⁶ H01R 13/631

U.S. Cl. 439—372


9 Claims



a clip piece including a metal leaf spring and a press cap fixed to a top of the metal leaf spring, and an insertion socket formed at one side of an inner shell of said computer connector; said metal leaf spring of said clip piece having a bottom end formed with two hooks for firmly hooking on a head portion of a mating computer connector;

said insertion socket is formed at a middle portion of a side wall of said inner shell, wherein said insertion socket includes an insertion plate extending inwardly from an end of said middle portion of said side wall, a stop plate extending upwardly from said sidewall and defining an insertion opening above said insertion plate and a through hole adjacent to said insertion plate;

said clip piece has an inwardly protruding hooking plate at a position corresponding to said insertion plate, such that when said clip piece is inserted into said insertion socket, said hooking plate extends into said through hole and said insertion opening, causing said clip piece to be directly clamped in place between said insertion plate and said stop plate, and wherein said hooking plate includes a detent positioned thereon so that said clip piece is retained firmly in said insertion socket when said clip piece is fully inserted into said insertion socket.



1. In a connector system for electrically mating and unmating opposing surfaces of at least two substrates wherein the surfaces each include a substantial plurality of electrical contact pads, one of said substrates includes an actuator having a leading end extending therebeyond for insertion through an aperture of said second substrate for interlocking means on a leading end of said actuator to cooperate with a camming surface of said second substrate adjacent said aperture, and further having an actuation section remote from said leading end.

wherein upon actuation of the actuator by the actuating section, said interlocking means cinch said first substrate to said second substrate by being urged along said camming surface from a force-free position to a force-applying position, and wherein during actuation substantial friction forces are applied against the interlocking means thereby requiring a substantial rotational torque to be applied to the actuator.

an improvement wherein said interlocking means comprise a pair of rollers secured to said leading end of said actuator, wherein upon actuation of said actuator, said pair of rollers are rotated about at least one roller support pin secured to said actuator and roll along the camming surface with no substantial friction forces from the force-free position to the force-applying position, thereby reducing a rotational torque required to achieve a high-load mechanical and electrical contact between said opposing surfaces of said substrates, over many mating/unmating cycles.

5,588,865

CONNECTOR FASTENING MECHANISM

Masayuki Yamamoto, Shizuoka, Japan, assignor to Yazaki Corporation, Tokyo, Japan


Filed Aug. 18, 1994, Ser. No. 292,776

Claims priority, application Japan, Aug. 20, 1993, 5-226702

Int. Cl.⁶ H01R 13/627

U.S. Cl. 439—364

6 Claims



1. A connector fastening mechanism comprising:

- a male connector and a female connector fittable with each other by a fastening member in one of a provisional engagement state and a complete engagement state;
- engaging means for retaining the male and female connectors against separation in the provisional engagement state; and
- elastic means for pressing one of the male and female connectors in a direction to separate the one connector from the other connector in the provisional engagement state.

5,588,867

CURVED SOCKET CONTACT

Armand P. Thévenaz, Auliens/Ollon, Switzerland, assignor to The Whitaker Corporation, Wilmington, Del.

Filed Mar. 29, 1995, Ser. No. 413,019


Claims priority, application United Kingdom, Apr. 19, 1994, 9407748

Int. Cl.⁶ H01R 9/09; 13/11

U.S. Cl. 439—381

9 Claims

1. A socket contact comprising a contact body having a longitudinal cavity disposed around and extending along an axis, the cavity for receiving a male contact therein for electrical connection therewith, characterized in that the contact body comprises slots extending from an outer periphery of the body transverse to the axis and intersecting the cavity for allowing supple bending of the contact body in a direction transverse to the axis from a free standing position to a connection position, the contact body being bent into a curved shape in its connection position, the curvature adapted to receive the male contact inserted into the cavity by



rotational movement in a direction along the axis, wherein adjacent said slots extend respectively from alternating opposing sides of the outer periphery.

5,588,868


STRAND CABLE PRESS-CONTACTING TERMINAL
Masanori Tsuji, Kimitoshi Abe, Osamu Sugiyama, and Hiroshi Yamamoto, all of Halhara-gun, Japan, assignors to Yazaki Corporation, Tokyo, Japan

Filed Mar. 28, 1995, Ser. No. 412,119

Claims priority, application Japan, Mar. 29, 1994, 6-058538
Int. Cl.⁶ H01R 4/24

U.S. Cl. 439—397

8 Claims



1. A strand cable press-contacting terminal for connecting thereto a strand cable comprising a plurality of twisted wires aligned in a first external layer of said cable, the plurality of twisted wires having a wire strand pitch, wherein an even number of the plurality of twisted wires are aligned in the first external layer of said cable, said terminal comprising:

a pair of fore and aft press-contacting pieces, arranged longitudinally in the terminal;
wherein said pair of fore and aft press-contacting pieces are spaced apart from each other a distance obtained by multiplying a quarter of the wire strand pitch by an odd number n.

5,588,869

TELECOMMUNICATIONS TERMINAL BLOCK
Michael L. Jensen, Cary; George D. Summers, Jr., Raleigh, and Thomas M. Baum, Apex, all of N.C., assignors to Raychem Corporation, Menlo Park, Calif.

Continuation of Ser. No. 46,339, Apr. 12, 1993, Pat. No. 5,423,694. This application May 1, 1995, Ser. No. 431,936


Int. Cl.⁶ H01R 4/24

U.S. Cl. 439—417

17 Claims

1. A telecommunications terminal block for interconnecting first wires and a second wire, comprising:

a base;
a connector member carried by said base, said connector member having one or more first wire receiving means for receiving and establishing electrical connection with respective ones of said first wires, and also having a second wire receiving



means for receiving and establishing electrical connection with said second wire;

wire termination means mounted upon and movable at an angle within the range of approximately 300°–75° relative to a bottom plane of said base for effecting progressive electrical connection of desired ones of said first wires to said connector member without disconnecting the electrical connection of any other of said first wires which were previously connected to said connector member by said wire termination means and disconnecting the electrical connection of said second wire to said connector member; and

drive means for imparting such movement to said wire termination means, said drive means being accessible from a direction oblique to the direction from which said wires access said wire receiving means.

5,588,870

ELECTRICAL CORD CLAMP


William C. Boteler, Bridgeport, and Lawrence J. Klein, Ansonia, both of Conn., assignors to Hubbell Incorporated, Orange, Conn.

Filed Jun. 7, 1995, Ser. No. 486,162

Int. Cl.⁶ H01R 13/58

U.S. Cl. 439—467

18 Claims



1. An electrical wiring device adapted to be coupled to an end of an electrical cord with a plurality of electrical conductors, comprising:

a housing including first and second cover halves coupled together to form a cord receiving cavity therebetween, said first and second cover halves having first and second cord clamp engaging surfaces, respectively;

a contact retainer body with terminals coupled to said first and second cover halves for coupling the electrical conductors thereto; and

a cord clamp including a first clamping member movably coupled within said cord receiving cavity along said first cord clamp engaging surface, and a second clamping member movably coupled within said cord receiving cavity along said second cord clamp engaging surface, said first and second clamping members being positioned substantially opposite each other for movably engaging the electrical cord therewith upon installation and assembly of said housing thereon to pull the electrical cord within said cord receiving cavity towards said terminals, each of said first and second clamping members having a spring element for biasing said first and second clamping members away from said terminals,

said first and second cord clamp engaging surfaces being first and second substantially smooth, inclined ramps, respectively, which allows said first and second clamping members to freely slide thereon during assembly and disassembly of said housing.

5,588,871

TERMINAL BOX FOR HERMETIC COMPRESSORS

Marco Salvaneschi, Barona di Albuzzano, Italy, assignor to Necchi Compressori S.r.l., Pavia, Italy


Continuation of Ser. No. 145,162, Nov. 3, 1993, abandoned.

This application May 8, 1995, Ser. No. 436,595

Claims priority, application Italy, Nov. 3, 1992, PV92U0011
Int. Cl.⁶ H01R 13/58

U.S. Cl. 439—469

5 Claims



1. A terminal box for a hermetic compressor for connecting electrically feeding lines to electrical components of a refrigerator casing and the compressor and suitable for coupling to a first plate fixed to the compressor, comprising a body, seats formed in an upper part of said body for housing terminals of said feeding lines, locking means in a lower part of said body for fixing said lines to said body and a cover for covering said body, said body having elastic means for removably elastically fixing said body to said first plate and said cover having elastic means for removably elastically fixing said cover to said first plate, said cover being removable from said body while said body remains fixed to said first plate, said locking means for fixing said lines being composed of a second plate having a projection provided with a pivot, two blocks pivotally mounted on said pivot, each said block having an elastic tongue, means on said second plate capable of coupling said elastic tongues with said second plate.

5,588,872

CONNECTOR WITH ENGAGEMENT CHECKING STRUCTURE

Masaru Fukuda, Shizuoka, Japan, assignor to Yazaki Corporation, Tokyo, Japan


Filed Sep. 29, 1994, Ser. No. 314,792

Claims priority, application Japan, Sep. 30, 1993, 5-245328
Int. Cl.⁶ H01R 3/00

U.S. Cl. 439—489

4 Claims

1. An engagement checking structure for coupled connector housings, comprising:



a first connector housing containing a resilient lock arm integrally formed on said first housing as a cantilever member having one end fixed to a surface of said housing and its other end resiliently movable perpendicularly to said surface.

a locking projection formed on said lock arm.

a second connector housing having an engagement portion cooperable with said locking projection to resiliently urge said lock arm toward said surface of said first connector housing as said connector housings are placed in incomplete engaged relation, and to cooperate with said locking projection to retain said connector housings in locked relation upon said locking arm resiliently returning to its original position when said connector housings are placed in complete engaged relation;

a pair of terminal pins operative for detecting complete engagement between said connector housings and disposed on said second housing in laterally spaced relation from said locking arm upon movement of said first connector housing with respect to said second connector housing; and

a short circuit contact element mounted on said lock arm, said contact element having contact pieces extending laterally oppositely from said arm and means for attaching said contact element to said arm intermediate said contact pieces, said contact pieces being engageable with said terminal pins when said connector housings are in complete engaged relation whereby electrical connections are made between said contact pieces and said terminal pins.

5,588,873

CONNECTOR ADAPTED FOR FIT DETECTION


Tsuyoshi Hamai, and Norimichi Yashima, both of Shizuoka, Japan, assignors to Yazaki Corporation, Tokyo, Japan

Filed Oct. 19, 1995, Ser. No. 545,088

Claims priority, application Japan, Oct. 19, 1994, 6-253614
Int. Cl.⁶ H01R 3/00

U.S. Cl. 439—489

6 Claims




A=[B1-W2-B1-W1-B1-W1-B2-W1-B1]

1. A connector comprising:

a female housing having a circumferential wall and having a bar code configured by a combination of bars of different colors printed on an outer face; and

a male housing adapted to fit into a fitting hole defined by the circumferential wall of said female housing, said male hous-

ing having a leading edge portion adapted to reach a desired position in said fitting hole when said male housing and said female housing completely fit together, and having an indicating portion of a color the same as one of said different colors disposed in a portion of a side face of said male housing, said indicating portion adapted to be located adjacent to a slit defined by the circumferential wall of said female housing when said male housing and said female housing completely fit together, the slit extending from said outer face to an inner face, and being formed within an area of a bar of said bar code.



5,588,874

WATTHOUR METER SOCKET ADAPTER FOR REPLACING AN OB WATTHOUR METER


Allen V. Pruehs, Howell; Darrell Robinson, Highland Township, and Robert O. Learmont, Walled Lake, all of Mich., assignors to Ekstrom Industries, Inc., Farmington Hills, Mich.

Filed Apr. 7, 1995, Ser. No. 418,824

Int. Cl.⁶ H02B 9/00

U.S. Cl. 439—517

14 Claims



1. A wathour meter adapter for a wathour meter having a peripheral mounting flange and a plurality of outwardly extending blade terminals, the wathour meter adapter comprising:
a housing having a bottom wall and an annular side wall extending from the bottom wall to an end mounting flange;
a plurality of jaw contacts mounted on the bottom wall for receiving blade terminals of a wathour meter in a snap-in connection; and
terminal block means, disposed within the peripheral confines of the annular side wall of the housing, for receiving external line and load conductors and internal conductors connected to the jaw contacts.

5,588,875

CONNECTOR

Yoshitsugu Sawada, Shizuoka-ken, Japan, assignor to Yazaki Corporation, Tokyo, Japan

Filed Dec. 19, 1994, Ser. No. 358,515

Claims priority, application Japan, Dec. 20, 1993, 5-320345

Int. Cl.⁶ H01R 13/40

U.S. Cl. 439—595

15 Claims

1. A connector having:
a connector housing formed with a terminal accommodating chamber and a lance;
a terminal rotatable within and inserted into the terminal accommodating chamber of the connector housing and engaged with the lance for prevention of removal of the terminal from the connector housing; and
terminal rotation preventing means provided on at least one of the lance or the terminal for preventing the terminal inserted into the terminal accommodating chamber of the connector housing from being rotated within the connector housing.

5,588,876

FUSED ELECTRICAL CONNECTORS


Brian B. Hayes, Melbourne, Australia, and Colin J. Hayes, London, England, assignors to Multico International Pty. Ltd., Melbourne, Australia

Continuation-in-part of Ser. No. 142,302, Nov. 23, 1993, Pat. No. 5,413,505. This application May 8, 1995, Ser. No. 437,189

Int. Cl.⁶ H01R 13/68

U.S. Cl. 439—622

5 Claims



1. A fused electrical connector comprising:
a body having a fuse receptacle;
spaced apart electrical contacts within said fuse receptacle;
a central block affixed between said electrical contacts, said central block including linear keyways;
a cylindrical fuse for insertion into said fuse receptacle, said fuse having a longitudinal axis and including end caps, each said end cap including an integral elongate connector, each said connector extending substantially perpendicular to said longitudinal axis for engaging one of said electrical contacts upon insertion of said fuse into said fuse receptacle; and
a central body secured to said fuse between said end caps, said central body including linear formations perpendicular to said longitudinal axis of said fuse to permit insertion of said fuse in a direction normal to the longitudinal axis of said fuse.

5,588,877

ELECTRICAL CONNECTOR WITH MULTIPLE BLADE CONTACTS

Wayne S. Davis, Harrisburg; Michael E. Shirk, Grantville, and Robert N. Whiteman, Jr., Harrisburg, all of Pa., assignors to The Whitaker Corporation, Wilmington, Del.


Filed Dec. 22, 1994, Ser. No. 361,608

Int. Cl.⁶ H01R 17/00

U.S. Cl. 439—660

10 Claims

1. An electrical connector comprising an insulating housing, an elongated plug receiving single cavity in a mating front of the housing defined between opposed side and end walls, and conduc-



tive multiple contacts in the housing, the contacts being spaced apart without insulation therebetween adjacent the mating front, leading portions of the contacts bridging across the single cavity to opposite sides of the single cavity upon insertion into said housing from an insertion face opposed to said mating front, and opposed side portions of said contact leading portions extend to opposed side edge portions through transverse slots in said cavity side walls extending to closed front ends adjacent said mating front, said side edge portions having resilient lances latched forwardly of latching surfaces defined in walls of said slots facing and remote from said mating front of said housing along opposite sides of said single cavity whereby said contacts are latchingly retained within said housing.

5,588,878

ELECTRICAL RECEPTACLE ASSEMBLY AND SPRING CONTACT THEREFOR


Bernadette M. Flinchbaugh, York Haven; Andrew J. Gabany, Mechanicsburg; Adrian L. Melnyk, York, and Christopher J. Schmid, Harrisburg, all of Pa., assignors to The Whitaker Corporation, Wilmington, Del.

Filed Mar. 14, 1995, Ser. No. 404,410

Int. Cl.⁶ H01R 13/10

U.S. Cl. 439—682

20 Claims



1. An electrical receptacle assembly for application to a printed circuit board, the assembly comprising:
an insulating housing having a rectangular cross section defining at least one row of contact receiving cavities each opening into first and second opposite external faces of the housing, each cavity having a contact receiving part of constant cross section and being defined by first, second, third and fourth orthogonally arranged, flat, elongate surfaces extending sub-

stantially from the first opposite external face of the housing to a position proximate to the second opposite external face of the housing; and

a spring contact in each cavity comprising a bowed, forward leaf contact spring extending from an intermediate planar retention portion having oppositely projecting retention ears, and a rearward contact tail extending from the retention portion, the retention portion being secured against the first flat surface by the retention ears, that extend into contact retention slots in communication with said first opposite external face, said contact retention slots coextending laterally along said first flat surface and into said second and third flat surfaces that are adjacent to said first and fourth flat surfaces, the contact tail projecting from the first external opposite face of the housing and the contact spring being bowed away from said first flat surface toward the fourth flat surface with a forward free ended portion of the contact spring engaging the first flat surface.

whereby an electrical pin inserted axially into said cavity to engage against the fourth flat surface will depress the contact spring toward the first flat surface.

5,588,879

DIRECT COUPLER DEVICE

Masami Kano, Kiryu, Japan, assignor to Mitsubishi Electric Manufacturing Co., Ltd., Gunma, Japan

Filed Dec. 23, 1994, Ser. No. 363,418


Claims priority, application Japan, Dec. 28, 1993, 5-074853

U

Int. Cl.⁶ H01R 13/502

U.S. Cl. 439—686

12 Claims



1. A direct coupler device wherein a lead wire connected to a brush of a motor is electrically connected to an electricity supplying wire of a wire harness through a female coupler and a male coupler, said direct coupler device comprising:

a male coupler including a main portion and a cap covering said main portion, said main portion having a recess and also having a bottom side and a top side,
a terminal having a male terminal portion and an end portion opposite to said male terminal portion, which end portion of said terminal is connected to an end portion of said lead wire, said terminal being received in said recess with said lead wire positioned at said bottom side of said male coupler; and
a part of said terminal being engaged with said cap whereby said terminal is held to and prevented from coming out of said male coupler by movement in the direction toward said cap.

5,588,880

TERMINAL BLOCK


Daniel P. Wood, Laurel Hill, N.C., assignor to Acme Electric Corporation, East Aurora, N.Y.

Filed Mar. 10, 1995, Ser. No. 401,722

Int. Cl.⁶ H01R 9/22

U.S. Cl. 439-709

12 Claims



1. A finger-safe terminal block including:
 - an insulator base having an exterior surface including a support surface to support said terminal block on a mount;
 - a cantilever arm on said base adapted to engage an opposite surface of the mount for the terminal block;
 - first and second screw apertures in the exterior surface of said insulator base;
 - first and second rotatable screws in said first and second screw apertures, respectively, leading to first and second clamp areas, respectively, of said insulator base;
 - first and second conductor apertures in said insulator base adapted to receive first and second external conductors therein, respectively;
 - said first and second conductor apertures leading from the exterior surface to said first and second clamp areas, respectively, of said base;
 - each screw having a tool access end accessible from the exterior surface of the base, wherein tightening of each screw is adapted to physically clamp an end of an external conductor in the respective clamp area;
 - said first and second screw apertures at the base exterior surface being sufficiently small and each screw being mounted in a respective screw aperture with the tool access end recessed from the base exterior surface sufficiently that it cannot be touched by an adult human's finger tip; and
 - a conductor in said insulator base to provide electrical connection between said first and second clamp areas at least when the screws are tightened.

5,588,881

CONNECTOR TERMINAL BLOCK WITH ELECTRONIC MODULE

Gerhard Eggert; Walter Hanning, both of Detmold; Uwe Fiene, Steinheim; Michael Schnatwinkel, Herford; Rudolf Steinmeier, and Manfred Wilmes, both of Detmold, all of Germany, assignors to Weldmueller Interface GmbH & Co., Detmold, Germany

Filed Oct. 18, 1995, Ser. No. 544,482


Claims priority, application Germany, Oct. 31, 1994, 44 38 800.4

Int. Cl.⁶ H01R 9/22

U.S. Cl. 439-709

10 Claims

1. Terminal block means for supplying electrical power to, and for testing the operation of, an electronic plug-in module such as a printed circuit board, comprising:
 - (a) terminal block means (1), including:
 - (1) a terminal block body (2) formed of insulating material;
 - (2) at least one main electrical terminal (4,4') mounted on said terminal block body;



- (3) at least one auxiliary electrical terminal (6,6') mounted on said terminal block body in spaced relationship relative to said main terminal; and
- (4) at least one electrical connecting means (5,5') connecting said auxiliary terminal with said main terminal;
- (b) electronic module means (7) removably mounted on said terminal block body, said module means including:
 - (1) a hollow housing (8) having a generally planar wall portion (8a); and
 - (2) at least one electronic component (PC1, PC2) mounted in said housing; and
 - (c) disconnect means for alternately electrically connecting and disconnecting said electronic component with respect to said auxiliary terminal, including:
 - (1) a disconnect body member (9, 9') movably connected with said housing wall portion for displacement between engaged and disengaged positions relative to said auxiliary terminal; and
 - (2) disconnect terminal means (10, 10') mounted on said disconnect body member for electrically connecting said auxiliary terminal with said electrical component when said disconnect body member is in said engaged position, said disconnect terminal means being disconnected from said auxiliary terminal when said disconnect body is in the disengaged position.

5,588,882

WALL SOCKET WITH TWIST LOCK PRONGS


Ng Y. Hung, Kowloon, Hong Kong, assignor to Helms-Man Industrial Co., Ltd., Kowloon, Hong Kong

Filed Apr. 28, 1995, Ser. No. 431,050

Int. Cl.⁶ H01R 13/415

U.S. Cl. 439-741

6 Claims



1. A system for fixing an electrical contact prong through a housing wall such that the prong may conduct electricity through the housing wall, comprising:
 - a slot in the housing wall having a generally constant rectangular slot cross section, the slot passing through the wall from a housing outer surface of the housing wall to a housing inner

- surface of the wall, the outer surface of the housing wall and the inner surface being separated by a thickness of said wall; and
- an elongated prong having a length and further comprising:
 - a main body portion for making electrical contact outside the housing and having a body cross section larger than the slot cross section in at least one dimension;
 - a neck portion disposed along the length of the prong adjacent the body portion and having a generally rectangular neck cross section substantially equal to the slot cross section;
 - a head portion, disposed along the length of the prong adjacent the neck portion and distal the body portion, the head portion having a head cross section no larger than the neck cross section such that the head portion may pass through the slot; and
 - a twist portion disposed along the length of the prong intermediate the neck portion and the head portion and having a twist cross section substantially less in area than the head cross section, such that the twist portion is weaker in torsion along the length of the prong than other portions of the prong;
 - a shoulder formed by a first cross-sectional discontinuity of the neck cross section and the body cross section;
 - a chin formed by a second cross-sectional discontinuity of the twist portion and the head portion;
 - a distance from the shoulder to the chin being substantially equal to the thickness of said wall;
- whereby when the prong is inserted into the slot, the shoulder abuts the outer surface of the housing, the head may be twisted relative to the neck about the length of the prong so that the chin abuts the inner surface of the housing, such that the neck portion is held firmly within the slot between the shoulder and the chin.

5,588,883

CONNECTOR

Kazuhiko Hattori, Yokkaichi, Japan, assignor to Sumitomo Wiring Systems, Ltd., Japan

Filed May 9, 1995, Ser. No. 437,365

Claims priority, application Japan, Jun. 3, 1994, 6-145511

Int. Cl.⁶ H01R 4/30

U.S. Cl. 439-761

10 Claims



1. A device for connection to a post comprising a fastening ring having a fastening internal diameter and adapted to surround said post, an outer ring adapted to surround said fastening ring and rotate between an initial position, wherein no inward pressure is exerted on said fastening ring, and a tightened position, wherein inward pressure is exerted on said fastening ring, said inward pressure causing said fastening diameter to decrease and said fastening ring to grip said post.

- a lever extending radially outwardly, on said outer ring, said lever adapted to rotate said rotatable ring between said initial position and said tightening position;
- a locking mechanism adapted to retain said lever in said tightened position;
- said locking mechanism comprising an engaging hole in said lever, a hook mounted on said fastening ring and complementary to said hole when said outer ring is in said tightened position, so that said hook enters said hole in said tightened position.

5,588,884

STAMPED AND FORMED CONTACTS FOR A POWER CONNECTOR


Edward Rudoy, Woodland Hills, and John S. Szalay, Corona Del Mar, both of Calif., assignors to Packard Hughes Interconnect Company, Irvine, Calif.

Filed Sep. 8, 1995, Ser. No. 525,469

Int. Cl.⁶ H01R 13/187

U.S. Cl. 439-845

4 Claims



1. A power connector system comprising:
 - a pin contact, a socket contact and a spring member;
 - said pin contact comprising a termination end for attachment to a wire, a transition section extending from the termination end, and two blades extending from the transition section and wherein said blades are connected by a U-shaped bridge;
 - a socket contact having a termination end for attachment to a wire, a transition section extending from the termination end, and a socket component connected to the transition section, said socket component having a body portion and two arms extending outward in opposite directions therefrom, each arm having a pair of opposed notches formed near one end of the arm and a pair of opposed notches formed near the other end of the arm, said body and arms being constructed and arranged to define two U-shaped cavities;
 - a U-shaped spring member received in each of said cavities and constructed and arranged to provide a frictional fit when said blades are inserted into the respective cavities.

5,588,885

CONNECTOR WITH TERMINALS HAVING ANTI-WICKING GEL

Klaus P. Götz, Lorsch; Manfred Schaarschmidt, Bensheim, and Günter Feldmeier, Lorsch, all of Germany, assignors to The Whitaker Corporation, Wilmington, Del.

Filed Dec. 22, 1994, Ser. No. 362,312


Claims priority, application United Kingdom, Feb. 1, 1994, 9401918

Int. Cl.⁶ H01R 4/20; 9/09

U.S. Cl. 439-876

6 Claims

1. An electrical connector comprising an insulative housing with terminal receiving cavities extending therethrough from a mounting face to a terminal receiving face, and electrical terminals



having contact tails, the terminals mountable in the terminal receiving cavities of the housing such that the contact tails project below the mounting face, wherein the contact tails have sealing material deposited thereon prior to mounting in the terminal receiving cavities and wherein the terminal receiving cavities comprise contact tail receiving cavity sections proximate the mounting face, the contact tail receiving cavity sections having a smaller periphery than the sealing material such that the sealing material is squeezed between the contact tails and contact tail receiving cavity sections for hermetic sealing therebetween when the terminals are mounted in the housing.


5,588,886

AIR ENCIRCLING MARINE PROPULSION APPARATUS
Grover W. Davis, 3024 Kings Harbor Rd., Panama City, Fla. 32405

Continuation of Ser. No. 262,884, Jun. 21, 1994, Pat. No. 5,482,482. This application Jan. 5, 1996, Ser. No. 583,661
Int. Cl.⁶ B63H 1/16

U.S. Cl. 440—67

6 Claims




1. An apparatus for increasing thrust in marine propulsion, comprising:
a first hollow body having a guiding surface to guide a propulsive stream of water and having an outlet, a portion of the guiding surface radially converging toward the outlet;
a second hollow body disposed to surround at least a portion of the first body including the outlet to form a space surrounding first body, the second hollow body extending in the flow direction beyond the outlet; and,
duct means for guiding air into the space surrounding the first body to form a blanket of air surrounding the outlet of the first body.

5,588,887
WATERCRAFT
Keijiro Ikeda, Iwata, Japan, assignor to Yamaha Hatsudoki Kabushiki Kaisha, Iwata, Japan
Continuation of Ser. No. 231,337, Apr. 22, 1994, Pat. No. 5,490,474. This application Jun. 7, 1995, Ser. No. 475,172
Claims priority, application Japan, Apr. 27, 1993, 5-100954; Apr. 28, 1993, 5-103100
Int. Cl.⁶ B63H 21/10

U.S. Cl. 440—88

5 Claims




1. A watercraft having a hull defining an engine compartment, an internal combustion engine supported within said engine compartment for driving a propulsion unit for propelling said watercraft, said engine being comprised of a crankcase chamber formed at a lower portion of said engine and a cam chamber formed above said crankcase chamber and at an upper portion of said engine, a lubricant drain for draining lubricant from said cam chamber to said crankcase chamber, and means for reducing the amount of lubricant that can flow through said drain from said crankcase chamber to said cam chamber when said watercraft is inverted and said crankcase chamber is disposed above said cam chamber.

5,588,888

WET MARINE EXHAUST MUFFLER
Walea Magharious, Thomasville, Ga., assignor to Centek Industries, Inc., Thomasville, Ga.
Filed Oct. 10, 1995, Ser. No. 541,802
Int. Cl.⁶ B63H 20/24; 21/32


U.S. Cl. 440—89

12 Claims



1. A marine muffler for attenuating noise in a marine exhaust stream comprising exhaust gas and cooling water, said marine muffler comprising a housing, a baffle plate means positioned in said housing for dividing said housing into an upstream expansion chamber and a downstream exhaust chamber, inlet means in said expansion chamber for communicating with said marine exhaust stream, said baffle plate means comprising a bore formed there-through, a baffle tube positioned in said bore and providing communication between said upstream expansion chamber and said downstream exhaust chamber, said baffle tube comprising a closed end portion extending into said expansion chamber and an open end portion disposed in said exhaust chamber, said baffle tube comprising swirl inlet means contiguous with said closed end of said baffle tube for imparting a swirling motion to said marine

exhaust stream, said baffle tube swirl inlet means including a notched radially extending opening, said baffle tube further including an imperforate tubular wall extending from said swirl inlet means along said baffle tube to said open end portion, said exhaust chamber comprising exhaust tube means therein for exhausting said stream from said exhaust chamber to a surrounding atmosphere, said exhaust tube means including an upstream end thereof extending into said exhaust chamber and a downstream exit end, said upstream end thereof comprising a closed end portion and an exhaust tube inlet means contiguous with said closed end for imparting swirling motion to said exhaust stream as it is exhausted to said surrounding atmosphere.




said shoe portion is of a flexible material and said blade portion is of a relatively stiffer material, said blade portion extends underneath the top interior surface of said sole of said shoe portion to form a sole part, and said ribs are formed on said sole part, from which they project into an interior of the said shoe portion.

5,588,889

TIMING BUOY WITH REMOTE TIMING CAPABILITY
Scott D. Easter, 322 N. Birchwood, Hendersonville, Tenn. 37075
Continuation-in-part of Ser. No. 432,572, May 1, 1995. This application Aug. 7, 1995, Ser. No. 512,121
Int. Cl.⁶ B63B 22/18

U.S. Cl. 441—1

19 Claims



1. A timing buoy for watercraft sports, comprising:
a shell configured to operably receive and operably withstand contact forces;
a timing device;
a switch operably attached to the shell enabling the switch to be actuated in response to contact forces applied to the shell;
connection means for transmitting an actuation signal from the switch to a transmitter in response to a contact force applied to the shell; and
wherein the transmitter is configured to send a signal to a remote receiver enabling the receiver to actuate the timing device in response to a contact force applied to the shell.

5,588,890

SWIMMING FIN
Giovanni Garofalo, Rapallo, Italy, assignor to HTM Sport S.p.A., Italy
Filed May 10, 1995, Ser. No. 438,912
Claims priority, application Italy, May 20, 1994, GE94A0062
Int. Cl.⁶ A63B 31/11

U.S. Cl. 441—64

8 Claims

1. Swimming fin of the type having an open shoe comprising:
a shoe portion having a sole, and a blade portion, wherein a top interior surface of said sole is provided with two or more longitudinal ribs.


5,588,892

COMBINATION FLOTATION DEVICE AND SWIMMING AID
Donna McMahon, Stuart, Fla., assignor to Donna McMahon, Inc., Stuart, Fla.
Filed Oct. 4, 1995, Ser. No. 538,862
Int. Cl.⁶ B63C 9/115

U.S. Cl. 441—116

16 Claims

1. A personal flotation device for providing support and lift to the wearer's body, face and head while in a body of water, comprising:



an anterior flotation panel portion and an opposing posterior flotation panel portion, the flotation panel portions being generally parallel with each other;
a first shoulder flotation portion and an opposing second shoulder flotation portion, the shoulder flotation portions being at the top of and extending tangentially from the flotation panel portions;
an anterior collar flotation portion and an opposing posterior collar flotation portion, the anterior collar flotation portion extending forward and tangentially from the top of the anterior panel flotation portion, the posterior collar flotation portion extending rearward and tangentially from the top of the posterior flotation panel portion;
the collar flotation portions being hinged together so that the collars may pivot to provide support to the wearer's face and head in relation to the water level line.

5,588,893

FIELD EMISSION CATHODE AND METHODS IN THE PRODUCTION THEREOF


V. S. Kaftanov, A. I. Suvorov, and E. P. Sheshin, all of Moscow, Russian Federation, assignors to Kentucky Research and Investment Company Limited, Tortola, Virgin Islands (Br.)

Filed Jun. 6, 1995, Ser. No. 467,825

Int. Cl.⁶ H01J 9/02

U.S. Cl. 445—6

7 Claims



1. A method in the production of a field emission cathode constituted by at least one body containing a first substance, said method comprising the steps of:
preparing said at least one body so as to provide it with at least one emitting surface (emitting surfaces) having irregularities facilitating electron field emission;
adding to said emitting surface a second substance with a lower work function than that of said first substance, in order to lower the electrical field strength required to induce electron field emission from said emitting surface; and
modifying said emitting surface by applying to said at least one body a variable electric field, in order to induce electron field emission from said emitting surface, and increasing said variable electric field, in such a manner that the deterioration of said irregularities of said emitting surface is limited.


5,588,894

FIELD EMISSION DEVICE AND METHOD FOR MAKING SAME

Sungho Jin, Millington; Gregory P. Kochanski, Dunellen, and Wei Zhu, North Plainfield, all of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.
Division of Ser. No. 299,674, Aug. 31, 1994. This application Oct. 26, 1995, Ser. No. 548,533
Int. Cl.⁶ H01J 9/02

U.S. Cl. 445—24

13 Claims



1. A method for making a field emission device comprising the steps of:
applying a layer of electron emitter material on a substrate;
applying masking particles to said emitter material;
applying over said masking particles and said emitter material successive layers of insulating material and conductive material;
removing said masking particles to reveal underlying apertures to the emitter material; and
finishing said device.


5,588,895

ANGEL ACTION FIGURE DOLL

Diana A. Larson, R.R. 1 Box 33B, Mt. Airy, Iowa 50854
Filed Nov. 17, 1995, Ser. No. 559,233
Int. Cl.⁶ A63H 3/08; 3/22; 3/46

U.S. Cl. 446—98

5 Claims



1. An angel action figure doll comprising:
a) a small adjustable mannequin, said small adjustable mannequin being in the form of a human being and including a torso having a neck, shoulders and hips, a head that swivels on the neck of said torso, a pair of jointed arms that extend outwardly from the shoulders of said torso, and a pair of jointed legs that extend downwardly from the hips of said torso, each said jointed arm including a star elbow joint assembly between a forearm segment and upper arm segment thereof, each said jointed leg including a star knee joint assembly between a shank segment and thigh segment thereof, each said jointed leg including a star ankle joint assembly between a boot segment and a shank segment thereof said small adjustable mannequin being fabricated out of a semi-soft plastic material;

- b) a wing assembly, said wing assembly including a pair of upper wings, and pair of lower wings;
c) means for mounting said wing assembly against a back of said small adjustable mannequin, said mounting means including a breastplate having a collar to be worn about a neck and shoulders of said small adjustable mannequin, a back plate having a tail, three star swivel assemblies for attaching a pair of upper wings and a pair of lower wings of said wings assembly to said back plate in a moveable manner, and a star connector assembly for securing said back plate to the collar of said breastplate;
d) a halo worn on a head of said small adjustable mannequin, to simulate a conventional representation of an immortal, which can be used as a plaything of a child, said halo carrying a small star and being fabricated out of an elastic material that glows in the dark;
e) a toga worn by said small adjustable mannequin.


5,588,897

BALLOON WITH CONNECTED PINWHEEL

George Valentino, 2667 Rockaway Ave., Oceanside, N.Y. 11572
Continuation of Ser. No. 86,336, Jul. 1, 1993, Pat. No. 5,395,276. This application Mar. 7, 1995, Ser. No. 400,981
Int. Cl.⁶ A63H 33/40

U.S. Cl. 446—217

12 Claims




5,588,896
TOY BALLOON INFLATION AND EJECTION DEVICE
Gregory L. Goodman, 303 E. 37th St. Apt. 6B, New York, N.Y. 10016

Filed Aug. 25, 1995, Ser. No. 519,545

Int. Cl.⁶ A63H 27/26; 3/06

U.S. Cl. 446—187

14 Claims



1. A toy device for inflating and ejecting a balloon having a bead, comprising:
(a) support means having two ends and a surface area on one of said ends to which the balloon will frictionally adhere when the bead is stretched open and pulled over, said surface area having intermittent indentations where the bead will not come into contact with said support means;
(b) inflation means connected to said support means to permit air to be blown into the balloon and maintained therein; and
(c) ejection means having intermittent projections in close proximity to said support means surface area in alignment with the intermittent indentations in said surface area, each of said projections having a surface area disposed perpendicular to said support means surface area, and said ejection means being movable so as to bring said projection surface areas into contact with the bead and to urge the bead off said support means.

5,588,898

DOLL TOY HEAD ROTATION DEVICE

Hideki Ooba, Tokyo, Japan, assignor to Kabushiki Kaisha Plex, Japan


Filed Oct. 12, 1995, Ser. No. 542,305

Claims priority, application Japan, Mar. 10, 1995, 7-079929

Int. Cl.⁶ A63H 3/12

U.S. Cl. 446—321

9 Claims



1. A doll toy head rotation device wherein:

- (a) there is provided a hollow torso part and a front opening is provided in the front of the torso part, an upper opening is provided in the top of the torso part and a rear opening is provided in the rear of the torso part, the front opening being continuous with the upper opening and the upper opening being continuous with the rear opening;
- (b) a front plate which opens and closes the front opening is mounted in the front opening open/closably about its lower portion, a rear plate which opens and closes the rear opening is mounted in the rear opening open/closably about its lower portion, and an upper plate which opens and closes the upper opening is mounted in the upper opening rotatably about its substantially central portion;
- (c) the upper plate has an upper head part mounted on its upper surface and a lower head part mounted on its lower surface;
- (d) the front plate and the rear plate are so linked to each other that they open substantially simultaneously; and
- (e) the upper plate is provided with a rotary body having the rotational center of the upper plate as its center; and
- (f) the front plate or the rear plate is provided with a pivoting member which after that plate opens through a predetermined angle rotates the rotary body and does not rotate the rotary body when the plate closes.

5,588,899


APPARATUS FOR GRINDING SPECTACLE LENSES
Lutz Gottschald, Meerbusch, Germany, assignor to Wernicke & Co. GmbH, Düsseldorf, Germany

Filed Apr. 28, 1995, Ser. No. 433,247

Claims priority, application Germany, Apr. 28, 1994, 44 14 784.8

Int. Cl. B24B 49/00

U.S. Cl. 451—5



1. An apparatus for peripheral grinding of a lens; said apparatus comprising:
- at least one CNC-control device for grinding the lens blank according to a selected contour of the lens to be produced from the lens blank, said CNC-control device comprising:
 - a) at least one grinding wheel,
 - b) at least one rotatable holder for a lens blank,
 - c) at least one input device for inputting the optical specifications of the lens to be produced, and
 - d) a controller for controlling grinding of the lens blank according to the selected contour;
 - at least one manipulation device for receiving and positioning the lens blank according to the optical specifications;
 - an opto-electronic detecting device for detecting markings of the lens blank, said opto-electronic detecting device arranged in the vicinity of said manipulation device; and
 - a first control unit, controlling said detecting device, and a second control unit, controlling said manipulation device, said first and said second control units cooperating for precisely positioning the lens blank on said holder.

5,588,900

SURFACE TREATING DEVICE

Fukashi Urakami, Yokohama, Japan, assignor to Urakami Research & Development, Kanagawa, and Honda Giken Kogyo Kabushiki Kaisha, Tokyo, both of Japan


PCT No. PCT/JP94/00797, § 371 Date Jan. 18, 1995, § 102(e) Date Jan. 18, 1995, PCT Pub. No. WO94/27784, PCT Pub. Date Dec. 8, 1994

PCT Filed May 18, 1994, Ser. No. 373,246

Claims priority, application Japan, May 23, 1993, 5-156025 Int. Cl. B24C 3/06

U.S. Cl. 451—92

6 Claims



1. A surface treating device having a nozzle for ejecting a surface treating material toward the surface of an object, which comprises

a swivel bearing mechanism, an oscillating tube connected to the swivel bearing mechanism so as to be free to pivot about an axis center of the swivel bearing mechanism and such that with respect to the axis center, an end portion thereof is positioned on the side facing the object surface and the other end portion thereof is positioned on the side opposite to the object surface, the nozzle connected to the one end portion side of the oscillating tube, and a self-revolving/else-revolving mechanism connected to the other end portion side of the oscillating tube and making the nozzle self-revolve and else-revolve about the axis center of the swivel bearing mechanism.

the self-revolving/else-revolving mechanism including a main crank which has a driven shaft positioned on an axis passing through the axis center of the swivel bearing mechanism on the other end portion side of the oscillating tube and rotationally driven by driving means, and which is rotationally driven integrally with the driven shaft; a subordinate crank having a rotating shaft mounted at a site eccentric from the axis of the main crank and having an axis obliquely intersecting the axis of the main crank; universal joint means connecting that site in the subordinate crank which is eccentric from the axis, to the other end portion side of the oscillating tube; a subordinate bevel gear connected to the rotating shaft of the subordinate crank and rotating integrally with the subordinate crank; a main bevel gear which is provided integrally on a shaft having an axis common to the driven shaft of the main crank and being disposed so as to be free to rotate relative to the driven shaft, and which is engaged with the subordinate bevel gear; and the subordinate bevel gear revolving about the main bevel gear according to the rotation of the main crank while revolving on its own axis.

5,588,901

CLEANING METHOD AND APPARATUS UTILIZING SODIUM BICARBONATE PARTICLES

Arthur C. Rubey, III; Andrew M. Taylor, both of San Antonio, Tex., and William E. Spears, Jr., Lawrenceville, N.J., assignors to Yelapa Corporation, San Antonio, Tex.


PCT No. PCT/US94/09638, § 371 Date Dec. 14, 1994, § 102(e) Date Dec. 14, 1994, PCT Pub. No. WO95/06526, PCT Pub. Date Mar. 9, 1995

Continuation-in-part of Ser. No. 116,405, Sep. 3, 1993, Pat. No. 5,366,560. This PCT application Aug. 31, 1994, Ser. No. 351,310

Int. Cl. B24C 1/00; 3/02; 7/00; 9/00

U.S. Cl. 451—99

17 Claims



1. Apparatus for cleaning a surface by blasting the surface with particles of abrasive entrained in a high velocity fluid stream comprising, in combination:

- a hopper for containing abrasive particles, said hopper having a top and a tapered bottom surface terminating in a vertical passage, the top of said hopper being exposed to atmospheric pressure;
- an orifice element removably mounted in said vertical passage defining an orifice bore of selected diameter to allow passage of the abrasive particles therethrough;
- an air pipe having a first end and a second end;
- a bore transversely intersecting said vertical passage below said orifice element, said transversely intersecting bore being disposed to receive abrasive particles passing through said orifice bore, said transversely intersecting bore being further disposed in communication with said air pipe;
- said first end of said air pipe communicating with atmospheric air, said first end of said air pipe being disposed upstream of said transversely intersecting bore;
- an applying nozzle;
- means defining a venturi passage connected to said applying nozzle,
- first hose means for supplying a stream of pressurized fluid through said venturi passage;
- means defining a suction fluid passage communicating with said venturi passage to produce a suction force; and
- second hose means connecting said suction fluid passage to said second end of said air pipe.

5,588,902

APPARATUS FOR POLISHING WAFERS

Hiro Yoshi Tominaga, and Yoshinori Suzuki, both of Fukushima-ken, Japan, assignors to Shin-Etsu Handotai Co., Ltd., Tokyo, Japan


Filed Feb. 13, 1995, Ser. No. 387,514

Claims priority, application Japan, Feb. 18, 1994, 6-044839 Int. Cl. B24B 5/00

U.S. Cl. 451—288

17 Claims

1. An apparatus for polishing wafers comprising:
- a polishing apparatus having a top ring mounted on a rotary shaft;
 - a wafer carrier made from a material with high rigidity for adhering wafers thereto, the wafer carrier composed of two plates including an upper plate and a lower plate which are superimposed with each other in tight adhesion, said upper plate being mounted to a lower portion of the top ring of the



polishing apparatus, a total thickness of the two plates being sufficient to prevent the plates from becoming deformed by a polishing load; and

a flexible thin plate secured to the lower portion of the top ring so as to form a sealed space within the top ring, the sealed space being in communication with a source of pressurized fluid and the upper plate being spaced apart and below a lower surface of the thin plate.

5,588,903

ERGONOMIC POWER TOOL


Robert A. Pennison, Bellville, Tex., assignor to Indresco Inc., Dallas, Tex.

Filed Aug. 8, 1994, Ser. No. 287,543

Int. Cl. B24B 23/00; 27/08

U.S. Cl. 451—344

8 Claims



1. An ergonomic hand-held air powered tool comprising:
- a motor;
 - a drive assembly coupled to the motor and having a first longitudinal axis;
 - a housing comprising:
 - a main body portion forming a cavity and having the motor secured in the cavity; and
 - a handle portion attached to the main portion and having a second longitudinal axis;
 - a chuck coupled to the drive assembly for releasably securing a tool element to the drive assembly;
 - a throttle associated with the motor for selectively controlling the speed of the motor, the throttle comprising:
 - a throttle valve comprising:
 - a biasing spring having a first end abutting a portion of the housing;
 - a valve seat;
 - a valve flange abutting a second end of the biasing spring for urging the valve flange towards the valve seat; and
 - linkage connected to a portion of the valve flange for causing the valve flange to unseat from the valve seat when depressed;
 - a throttle lever coupled to the throttle valve;
 - a pivot pin secured to one end of the throttle lever coupled to the throttle valve; and

the first longitudinal axis of the main body forming an angle less than 60 degrees and more than zero degrees with respect to the second longitudinal axis of the handle.


5,588,904 FINISHING TOOL

Anthony Allport, 2402 NE. 14th, Portland, Oreg. 97212
Continuation-in-part of Ser. No. 278,450, Jul. 21, 1994, Pat. No. 5,474,490. This application Aug. 29, 1995, Ser. No. 521,116

Int. Cl.⁶ B24D 17/00

U.S. Cl. 451—512

17 Claims



14. A method for securing replaceable finishing material to a finishing tool, comprising the steps of:
providing a block having an associated first holding element and a first slot, said first holding element being coupled to a retraction element so that said retraction element imparts on said first holding element a pulling force directed toward said first slot;
applying a backward force on said first holding element so as to overcome said pulling force of said retraction element and so that said first holding element is disposed substantially outside said first slot;
inserting a first length of finishing material in said first slot;
releasing said first holding element so that said retraction element pulls said first holding element into said first slot; and
aligning said first holding element in said first slot by operation of a guide element.

5,588,905 TOPICAL PATCH TO REDUCE FECAL CONTAMINATION DURING SLAUGHTER


William T. Nightingale, Alta Loma, Calif., assignor to Pacer Technology, Rancho Cucamonga, Calif.
Filed Dec. 5, 1995, Ser. No. 567,266

Int. Cl.⁶ A22C 21/00

U.S. Cl. 452—176

9 Claims

1. A patch for sealing the natural pelvic vents of animal car-



casses to prevent contamination of the carcasses with urine and fecal matter during later processing, comprising:

a rectangular strip of material having dimensions for application to the vents of corresponding male and female sexes of animal carcasses;
a tissue adhesive that cures in seconds and forms strong bonds to skin tissue applied to one side of the rectangular strip and providing for the sealing of the natural pelvic vents of the animal carcasses during slaughter processing wherein intestinal fecal matter and urine is prevented from leaking and contaminating said carcass.

5,588,906


OFFSET, POULTRY DEBONING SYSTEM

James F. Davis, 11976 Bells Ferry Rd., Canton, Ga. 30114
Continuation of Ser. No. 182,585, Jan. 18, 1994, Pat. No. 5,492,503. This application Feb. 8, 1996, Ser. No. 597,390

Int. Cl.⁶ A22B 7/00; A22C 17/04

U.S. Cl. 452—179

23 Claims



1. An apparatus for facilitating the processing of poultry comprising:
an elongated frame;
a continuous conveyor movably supported by said frame for movement along an elongated path and including a first elongated edge and a second elongated edge;
a plurality of support arm members, wherein each said support arm member of said plurality of support arm members extends from said continuous conveyor; and
a plurality of support fittings wherein, each said support fitting of said plurality of support fittings connects to one of said support arm members of said plurality of support arm members, and said plurality of support fittings includes, at least, a first plurality of support fittings proximate to said first elongated edge, and a second plurality of support fittings proximate to said second elongated edge.

5,588,907

PORTABLE GAME HOIST

Richard P. DePietro, 301 Mountain Rd., Boyertown, Pa. 19512, and Brian J. Wilkinson, 27 Longview Rd., Birdsboro, Pa. 19508


Filed Dec. 22, 1995, Ser. No. 577,090

Int. Cl.⁶ A22B 5/00; 5/16

U.S. Cl. 452—187

14 Claims

1. A portable game hoist comprising:
a main beam which can be secured relative to a support structure;
a winch secured relative to a first end of the main beam and storing a cable directed through the main beam to a second end of the main beam;
an outer pulley rotatably mounted at the second end of the main beam, the cable extending over the main beam and depending therefrom for coupling to an object; and



a plurality of abutment members being mounted to the main beam which operate to engage at least one rafter to preclude sliding of the main beam relative thereto with the main beam being placed across the at least one rafter of a support structure.

5,588,908

VENTILATION HOSE MOUNTING ASSEMBLY


Richard J. Camarota, Holland, Mich., assignor to ITC, Incorporated, Holland, Mich.

Filed Oct. 20, 1995, Ser. No. 546,376

Int. Cl.⁶ F23J 11/02; B60H 1/26

U.S. Cl. 454—78

13 Claims



1. A hose-and-fitting assembly adapted to be secured to a port formed in a panel, said assembly comprising:
a fitting including: a face plate; a set of spaced apart lock tabs that extend inwardly from said face plate, said lock tabs being dimensioned to subtend the outer perimeter of the port and being spaced apart to define interstitial gaps; and a set of fingers that extend inwardly from said face plate, said fingers being located adjacent to and diametrically outwardly spaced from said lock tab interstitial gaps and being formed with fastening elements configured to be secured to portions of the panel forming the port; and
a hose fitted over outside surfaces of said lock tabs and in said lock tab interstitial gaps so that when said fitting is secured in the port, said hose is compression secured to said fitting by said fingers.

5,588,909

SOLAR POWER-OPERATED COOLING SYSTEM FOR MOTOR VEHICLES

Shing-Lai Ferng, No. 29, Her Lih Street., Taipeng, Taichung Hsien, Taiwan


Filed Jun. 1, 1995, Ser. No. 456,315

Int. Cl.⁶ B60H 3/06

U.S. Cl. 454—141

3 Claims

1. A solar power-operated cooling system for circulating air in a motor vehicle, the system comprising:



(a) a solar power device including a frame, a plurality of photovoltaic cells mounted within the frame for conveying the radiant energy of sunlight into electric power, and a power output terminal for the output of electric power from the photovoltaic cells;
(b) an electric connector including an input terminal connected to the power output terminal of the solar power device, and first and second output terminals;
(c) a first blowing fan electrically connected to the first output terminal of the electric connector for installation in a first door assembly of a motor vehicle to draw outside fresh air into the interior of the motor vehicle through the first door assembly of the motor vehicle; and
(d) a first exhaust fan electrically connected to the second output terminal of the electric connector for installation in a second door assembly of the motor vehicle to draw inside hot air of the motor vehicle through drain holes in the second door assembly of the motor vehicle.

5,588,910

AIR OUTLET REGISTER FOR AN OPENING IN A VEHICLE


Robert J. Hutter, Plymouth; Christopher J. Martin, Northville, both of Mich., and Thomas W. Roesner, Pulheim, Germany, assignors to Ford Motor Company, Dearborn, Mich.
Continuation of Ser. No. 311,990, Sep. 26, 1994, abandoned.

This application Dec. 21, 1995, Ser. No. 576,931

Int. Cl.⁶ B60H 1/34

U.S. Cl. 454—154

12 Claims



1. An air outlet for an opening in a vehicle, comprising:
an elongated body having first and second end portions, a hollow interior, a front outer peripheral surface having a front opening and extending between said first and second end portions, a rear outer peripheral surface having a rear opening and extending between said first and second end portions, a longitudinal axis and a transverse axis;
a first set of stationary vanes oriented parallel to said longitudinal and transverse axes and to one another and extending in said front opening between said first and second end portions and extending from said outer peripheral surface into said hollow interior of said body;

a second set of stationary vanes with individual vanes oriented parallel to said longitudinal axis, nonparallel to said transverse axis and nonparallel to one another, said second set of stationary vanes extending in said front opening between said first and second end portions and extending from said outer peripheral surface into said hollow interior of said body; and means for pivoting said elongated body between a first position at which said first set of stationary vanes is aligned with said rear opening along said transverse axis to receive a direct, linear flow of air exiting said rear opening to direct said flow of air across said first set of stationary vanes and through said from opening in a single direction, and a second position at which said second set of stationary vanes is aligned with said rear opening along said transverse axis to receive a direct, linear flow of air exiting said rear opening to direct said flow of air across said second set of stationary vanes and through said from opening in multiple directions.

5,588,911

MECHANICAL CONTROL FOR CENTRAL AIR CONDITIONERS' OUTLETS


Reynaldo Gomez, Miami, Fla., assignor to AC Directional Control, Inc., Miami, Fla.

Filed Oct. 11, 1995, Ser. No. 540,698

Int. Cl.⁶ F24F 13/075

U.S. Cl. 454—290

4 Claims



1. A mechanical control for the air flowing through air conditioner's outlet, comprising:

- a) control means having a first lever that can be positioned in at least two positions;
- b) shielded cable means including an internal cable and an outer shield having each first and second ends, said internal cable is slidably housed by said outer shield, and the first end of said internal cable being connected to said first lever so that said internal cable moves in response to the actuation of said first lever; and
- c) outlet means having a plurality of fins pivotally mounted to said outlet and linking arm means commonly connected to said plurality of fins, a second lever that actuates said fins, said second lever being pivotally mounted to said outlet and being connected to said second end of said internal cable so that the movement of said first lever is transmitted through said internal cable causes said second lever to move to a corresponding predetermined position.

5,588,912

SIEVE FOR HARVESTING MACHINES

Gustav Schumacher, II, Gartenstrasse 8, and Friedrich W. Schumacher, Goldwiese 22, both of 57612 Eichelhardt, Germany


Filed Jul. 7, 1995, Ser. No. 499,768

Claims priority, application Germany, Jul. 13, 1994, 44 24 383.9

Int. Cl.⁶ A01F 12/32

U.S. Cl. 460—101

21 Claims



1. Sieve for separating grain crops from a chaff-straw mixture which is passed by a blower wind current from below and which comprises grooves (1) and channels (2) alternating with each other, said grooves and channels being elongated in a crop conveying direction and being aligned in parallel to the crop conveying direction, said grooves and channels being alternately open on the top and open on the bottom and having lateral legs (3) separating said grooves (1) from said channels (2), said lateral legs having openings (4) through which the harvested crop can pass from the grooves (1) open on top to the channels (2) open on the bottom.

5,588,913

GAMING SYSTEM AND PROCESS FOR GENERATING CARD FACES


Allen R. Hecht, 13360 Meadow Wood La., Granada Hills, Calif. 91344

Filed Jun. 14, 1994, Ser. No. 259,387

Int. Cl.⁶ A63F 9/24

U.S. Cl. 463—19

37 Claims



1. A process for generating a plurality of gaming card arrays, each formed of a plurality of symbols positioned in predetermined symbol display locations, in a remote device connected to a main station, the steps comprising:

- developing a plurality of seeds to be utilized as input for generating gaming card arrays, said developing step including the steps of seeding a first pseudo-random number generator at the main station to create the plurality of seeds, verifying

that each seed is not a duplicate of a previously created seed, and sending the plurality of seeds, less duplicates, to the remote device; and generating, at the remote device, gaming card arrays in accordance with input received from the main station utilizing a second pseudo-random number generator seeded by at least a portion of the plurality of seeds, wherein the second pseudo-random number generator always generates the same gaming card array as the first pseudo-random number generator for any given seed.

5,588,914

METHOD AND SYSTEM FOR GUIDING A USER IN A VIRTUAL REALITY PRESENTATION


John W. Adamczyk, Pasadena, Calif., assignor to The Walt Disney Company, Burbank, Calif.

Filed Jun. 28, 1994, Ser. No. 267,184

Int. Cl.⁶ G06F 3/00

U.S. Cl. 463—32

26 Claims



1. A method of guiding a user through a virtual reality experience in a virtual world having at least one virtual space, said user having a field of view, said method comprising:

- projecting said virtual space in the field of view of said user;
- defining at least one nominal path through said virtual space;
- projecting an object in said virtual space in the field of view of said user;
- moving said object along said at least one nominal path;
- preventing said object from moving other than along said at least one nominal path;
- allowing said user to move within said virtual space; and
- restraining said user from exceeding a defined distance from said object.

5,588,915

SEAL AND SEAL GUARD ASSEMBLY FOR UNIVERSAL JOINT

Johnny N. Smith, Toledo, Ohio, assignor to Dana Corporation, Toledo, Ohio

Filed Dec. 26, 1995, Ser. No. 578,273


Int. Cl.⁶ F16C 33/76; F16D 3/41; F16J 15/32

U.S. Cl. 464—14

20 Claims

1. A bearing cup assembly adapted for use with a cross member of a universal joint comprising:

- a hollow bearing cup including an open end, a reduced diameter portion located adjacent to said open end, an inner bearing surface, and a closed end;
- a seal assembly secured to said bearing cup and including a support ring and a seal secured to said support ring, said support ring including an axially extending portion and a radially extending flange portion; and
- a seal guard secured to said seal assembly, said seal guard including a body portion and a protrusion extending from said body portion into said reduced diameter portion of said bearing cup, said radially extending flange portion of said support



ring being trapped between said body portion and said protrusion of said seal guard to secure said seal guard to said seal assembly.

5,588,916

TORQUE CONTROL DEVICE FOR ROTARY MINE DRILLING MACHINE


Richard E. Moore, Humble, Tex., assignor to Duramax, Inc., Ohio

Filed Feb. 17, 1994, Ser. No. 197,726

Int. Cl.⁶ E21B 17/06

U.S. Cl. 464—20

13 Claims



1. A device for reducing the deleterious torque in a shock absorbing, rotary drive coupling unit for connecting a drive shaft and a driven shaft in a rotary mine drilling machine, said device comprising:

- a drive plate connectable to the drive shaft of the rotary drilling machine;
- a driven plate connectable to the driven shaft rotated by said drive shaft;
- a shock and torque-absorbing portion fastened to said drive plate and fastened to said driven plate, said shock and torque-absorbing portion comprising elastomeric material for transmitting torque between said drive plate and said driven plate; torque-relief means operatively connected to said drive plate and said driven plate for limiting the torque placed on said shock and torque-absorbing portion, said torque-relief means including:
- at least one first engagement member operatively connected to said drive plate, and
- at least one second engagement member connected to said driven plate, wherein said first engagement member contacts said second engagement member and said drive plate, and relieves the torque on said shock and torque-absorbing portion and directly drives said driven plate in response to a predetermined amount of torque being applied to said

driven plate, said predetermined amount of torque being selected to avoid torque-related damage to said elastomeric material from heavy loads;

wherein said drive plate moves longitudinally away from said driven plate in response to the movement of the drive shaft relative to the driven shaft in a direction putting tension on said elastomeric material through said movement of said drive plate, and wherein said device further comprises a tensile force relief apparatus, said tensile force relief apparatus including a tensile force relief member attached to said driven plate and spaced from said drive plate in the path of movement of said drive plate when the drive shaft puts tension on said elastomeric material at a distance in which said drive plate engages said tensile force relief member to prevent damage to said elastomeric material when said drive plate moves in said direction.

5,588,917

COUPLING WITH DUAL TORQUE TRANSMISSION PATHS


Steve D'Ercolo, Glenn Burnie, Md., assignor to KOP-Flex, Inc., Baltimore, Md.

Filed Nov. 14, 1994, Ser. No. 339,895

Int. Cl.⁶ F16D 3/56; 3/64; 3/78

U.S. Cl. 464-79

6 Claims



1. A coupling for accommodating misalignment between the axes of a drive shaft and a driven shaft, comprising:

a drive connector having an axis of rotation and being located at an end of the drive shaft;

an annular flexible coupler having a first member connected to said drive connector and a second axially spaced apart member connected to the driven shaft so as to transmit torque from the drive shaft to the driven shaft;

an annular secondary coupler having a first member connected to said drive connector and a second member located adjacent said second member of said annular flexible coupler for selectively engaging in torque transmitting relation with said second member of said annular flexible coupler when said annular flexible coupler is torsionally deflected beyond a threshold limit so as to continue torque transmission through said second member of said annular flexible coupler to the driven shaft, said drive connector comprising a ring having apertures spaced circumferentially about said ring for receiving bolts to connect the end of the drive shaft to said annular flexible coupler, said annular secondary coupler comprising a sleeve having an interior surface, said interior surface having gear teeth, said sleeve having at one end a radially extending flange provided with a plurality of apertures aligned with said apertures of said ring, said second member of said annular flexible coupler including a radially outer surface formed with gear teeth engageable with said gear teeth on said interior surface of said sleeve.

5,588,918

GOLF PUTTING CUP


Michael G. Eckman, and Paul A. Smallwood, both of Chesterfield, Mo., assignors to Taylor Nathan Co., Inc., St. Louis, Mo.

Filed Nov. 28, 1995, Ser. No. 563,343

Int. Cl.⁶ A63B 69/36

U.S. Cl. 473-187

19 Claims



1. A golf putting practice device comprising:

a base portion having at least one surface and a perimeter,

a plurality of substantially flat ramp structures, connected side-by-side around and substantially adjacent to the perimeter of the base portion, each ramp structure having a first end and a second end and extending continuously between the first end and the second end, the first ends of the ramp structures being disposed radially outward from a center of the base portion so as to define a central cup area, with the portion of the at least one surface of the base portion between the first ends of the plurality of ramp structures forming the floor of such central cup area, and

a plurality of pivotal connection structures mounted to the at least one surface, each of the ramp structures being loosely, pivotally connected at the first end thereof by a corresponding one of the plurality of pivotal connection structures to the at least one surface of the base portion, each one of the plurality of ramp structures, in normal putting practice position, extending outwardly from the pivotally connected first end thereof and downwardly until the second end of each of the ramp structures contacts a support surface for the device, to thereby facilitate rolling receipt of a golf ball into the central cup area of the base formed by the radially inwardly disposed first ends of the ramp structures.

5,588,919

GOLF SWING TRAINING DEVICE

Yoshikazu Nakamura, 4-25, Kamigasa 1-Chome, Kusatsu-shi, Shiga 525, Japan

Filed Jul. 17, 1995, Ser. No. 503,242

Claims priority, application Japan, Aug. 2, 1994, 6-201418; Oct. 23, 1994, 6-284485

Int. Cl.⁶ A63B 69/36

U.S. Cl. 473-212

17 Claims

1. A golf swing training device comprising upper arm angle detecting means mounted on a golfer's upper arm for movement therewith as the golfer makes a swing, thereby detecting the angle of the upper arm, and informing means for informing the golfer of the upper arm angle detected by the upper arm angle detecting means.

5,588,921

GOLF CLUB


Keith Parsick, 585 Bloomfield Ave. Apt. 34, West Caldwell, N.J. 07006

Filed Sep. 27, 1995, Ser. No. 534,132

Int. Cl.⁶ A63B 53/16

U.S. Cl. 473-299

15 Claims



5,588,920

HANDLE OF GOLF CLUB WITH IMPROVED CONTROL


Tsai C. Soong, 1839 Jackson Rd., Penfield, N.Y. 14526

Continuation-in-part of Ser. No. 503,311, Jul. 17, 1995, abandoned. This application Nov. 17, 1995, Ser. No. 560,113


Int. Cl.⁶ A63B 69/36

U.S. Cl. 473-231

15 Claims



1. A golf club having a handle portion, a shaft middle portion and a golf head, the shaft middle portion connecting the handle portion to the golf head adapted for striking a golf ball, the handle portion having at least a rigid outer tube covering at least partially a base shaft, said base shaft having two ends, a head end joining the base shaft to the shaft middle portion and a butt end which is close to a butt of the golf club, the improvement wherein said outer tube being at least partially hollow, having at least an elongated, approximate rectangular, symmetric cutout at one side of its outer wall, parallel to the longitudinal axis of the outer tube, said symmetric cutout having a length and width and being positioned such that when the golf club hits the golf ball and the impact force causes the base shaft to bend inside the outer tube, the displaced, curved part of the base shaft can slide freely in and out of the outer tube as is required during impact, without interference from the outer tube.



9. A golf club shaft, comprising:
a cylindrical shaft portion having a first end and a second end, said first end including means for attaching a golf club head to said cylindrical shaft portion; and
a flattened handle portion in the vicinity of said second end of said cylindrical shaft portion and integral with said cylindrical shaft portion, said flattened handle portion being flattened in a plane extending in a direction parallel to a direction faced by a golfer addressing a golf ball to be hit by said golf club, said flattened handle portion having a thickness in a direction parallel to said plane at least three times a thickness of said flattened handle portion in a direction perpendicular to said plane.

5,588,922

IRON GOLF CLUB HEAD WITH FORWARDLY DIVERGENT INTERIOR RECESS


Glenn H. Schmidt, Malibu, and Richard C. Helmstetter, Carlsbad, both of Calif., assignors to Callaway Golf Company, Carlsbad, Calif.

Continuation of Ser. No. 235,930, May 2, 1994, which is a continuation of Ser. No. 52,697, Apr. 30, 1993, Pat. No. 5,330,187, which is a continuation of Ser. No. 921,857, Aug. 5, 1992, Pat. No. 5,282,625. This application Dec. 12, 1994, Ser. No. 354,486

Int. Cl.⁶ B29C 43/18

U.S. Cl. 473-324

23 Claims



1. A golf club head having a heel, toe, upper flange, lower flange, and a front wall defining an upwardly and rearwardly inclined front face comprising

- a) the head defining a forwardly extending main recess located rearwardly of said front wall, and between said upper and lower flanges;
 b) said upper flange having a lower surface exposed to said recess;
 c) said lower flange having an upper surface exposed to said recess;
 d) said lower and upper surfaces relatively diverging, forwardly, from generally their rearwardmost extents and toward reduced thickness portions of said flanges proximate said front wall.

5,588,923


GOLF CLUB HEAD WITH ATTACHED SELECTED SWING WEIGHT COMPOSITE

Glenn H. Schmidt, Malibu, and Richard C. Helmstetter, Carlsbad, both of Calif., assignors to Callaway Golf Company, Carlsbad, Calif.

Continuation-in-part of Ser. No. 119,622, Sep. 13, 1993, Pat. No. 5,409,229, which is a continuation-in-part of Ser. No. 999,250, Jan. 19, 1993, Pat. No. 5,301,946, which is a continuation-in-part of Ser. No. 921,857, Aug. 5, 1992, Pat. No. 5,282,625. This application Apr. 6, 1995, Ser. No. 414,552 Int. Cl.⁶ A63B 53/04

U.S. Cl. 473—340

33 Claims



1. In combination:

- a) a golf club head having a front wall, said front wall having a rear side;
 b) and a composite adhered to said rear side, said composite including:
 i) a selected swing weight adjusting intermediary layer, and
 ii) a non-metallic rearwardly facing layer providing identification graphics which are rearwardly visible.

5,588,924

GOLF BALL

Michael J. Sullivan, Chicopee; John L. Nealon, Springfield, and R. Dennis Nesbitt, Westfield, all of Mass., assignors to Lisco, Inc., Tampa, Fla.


Continuation-in-part of Ser. No. 171,956, Dec. 22, 1993, Pat. No. 5,503,397, which is a continuation of Ser. No. 800,198, Nov. 27, 1991, Pat. No. 5,273,287. This application Aug. 8, 1995, Ser. No. 512,356

Int. Cl.⁶ A63B 37/12; 37/14

U.S. Cl. 473—377

10 Claims

1. A golf ball of improved playing characteristics comprising a ball having a core and a cover and a mean outside diameter of at least 1.70 inches;
 said ball weighing no more than substantially 1.62 ounces;
 a dimple pattern comprising a plurality of dimples on the surface of said ball, said dimple pattern covering at least 70.0% of the surface of said ball;
 said golf ball having a P.G.A. compression of 70 or less.



5,588,925

SHIFTER FOR TRANSMISSIONS ON BICYCLES


Markus Arbeiter, Würzburg, and Christian Weishaupt, Schweinfurt, both of Germany, assignors to Fichtel & Sachs AG, Schweinfurt, Germany

Filed Nov. 29, 1995, Ser. No. 563,996

Claims priority, application Germany, Dec. 2, 1994, 44 42 952.5

Int. Cl.⁶ F16H 59/00

8 Claims



1. Shifter for a derailleur for bicycles, comprising a housing, a detent element which is connected both to a manual actuator and to the derailleur, as well as a detent spring made of elastic plastic material, a lug of which interacts with detents of the detent element and can have a transition distance between the housing and the detent spring, wherein the detent spring is located in a recess of the housing, whereby also located in the recess, in addition to the detent spring, located downstream in the direction of movement, is a transition spring which can apply a bias between the housing and the detent spring and can be compressed into a block.

5,588,926

SELF-GUIDED CHAIN ASSEMBLIES

Philip J. Mott; David C. White, both of Dryden, and Thomas J. Becker, Auburn, all of N.Y., assignors to Borg-Warner Automotive, Inc., Sterling Heights, Mich.


Filed Apr. 20, 1995, Ser. No. 425,575

Int. Cl.⁶ F16G 13/04

U.S. Cl. 474—212

17 Claims

1. A silent chain assembly, comprising:
 a plurality of interleaved inner and outer links, said links being adapted to contact the teeth of a sprocket, pivot members connecting adjacent links, each link having a pair of apertures for receiving said pivot members;
 said outer links having a pair of depending toes extending downward below the apertures and defining a crotch therebetween said crotch having a height of a vertical distance extending between the lowest point on the toe to the highest point on the crotch, said toes having flanks that contact the teeth of a sprocket.



said inner links having a pair of depending toes extending downward below the apertures and defining a crotch therebetween said crotch having a height of a vertical distance extending between the lowest point on the toe to the highest point on the crotch, said toes having flanks that contact the teeth of a sprocket, and

said inner links each having a crotch of a first height, said outer links having a crotch of a second height, said second height being different from said first height.

5,588,927

CONTROL SYSTEM FOR AUTOMATIC TRANSMISSION

Kazumasa Tsukamoto, Toyota; Masahiko Ando, Okazaki; Masahiro Hayabuchi, Anjo; Akira Fukatsu, Anjo; Toshiyuki Mae, Anjo; Masato Kaigawa; Kagenori Fukumura, both of Toyota; Hidehiro Oba, Aichi-gun; Yasuo Hojo, Nagoya; Hiromichi Kimura; Atsushi Tabata, both of Okazaki; Tetsuo Hamajima, and Nobuaki Takahashi, both of Toyota, all of Japan, assignors to Aisin AW Co., Ltd., and Toyota Jidosha Kabushiki Kaisha, both of Japan


Filed Jun. 1, 1995, Ser. No. 455,677

Claims priority, application Japan, Jun. 2, 1994, 6-142203; Dec. 2, 1994, 6-329494

Int. Cl.⁶ F16H 61/00

U.S. Cl. 475—128

14 Claims



1. A control system for an automatic transmission comprising:
 a first frictional engagement element and a second frictional engagement element;

a first hydraulic servo for controlling the application/release of said first frictional engagement element and a second hydraulic servo for controlling the application/release of said second frictional engagement element;

an oil passage connected to said first hydraulic servo at a single point for feeding/releasing an oil pressure to/from said first hydraulic servo;

a regulator valve disposed in said oil passage for regulating the oil pressure in said oil passage, said regulator valve having a valve member providing a plurality of pressure receiving areas; and

signal pressure generating means for applying a signal pressure to said regulator valve during a shift to a predetermined gear

stage by engaging of one of said first and second frictional engagement elements and simultaneously releasing the other of said first and second frictional engagement elements, said signal pressure generating means changing said signal pressure during said shift in accordance with a predetermined pattern, said regulator valve regulating the oil pressure in said oil passage during said shift in accordance with said changing signal pressure.

wherein said pressure receiving areas of said valve member include:

a first pressure receiving area which receives the oil pressure to said first hydraulic servo as a feedback pressure and is thereby urged in a first direction;

a second pressure receiving area which receives said signal pressure and is thereby urged in a second direction opposite to said first direction;

a fourth pressure receiving area which receives the oil pressure to said second hydraulic servo and is thereby urged in said first direction during said shift; and

a third pressure receiving area which receives said signal pressure only during said shift and is thereby urged in said second direction and thereby participates in the regulation of the oil pressure in said first oil passage during said shift.

5,588,928

SELF-SYNCHRONIZING BRAKE BAND ACTUATING SYSTEM FOR AUTOMATIC CHANGE SPEED TRANSMISSIONS


Erkki A. Koivunen, 18260 Blue Heron Pointe Dr., Northville, Mich. 48167

Filed May 8, 1995, Ser. No. 436,756

Int. Cl.⁶ F16H 63/30

U.S. Cl. 475—126

13 Claims



1. A self-synchronizing brake band and a band control unit for the use in an automatic change gear ratio transmission having input and output means cooperating with a planetary gear unit with selectively engagable friction members to provide a plurality of transmission gear ratios, including a hydraulically operated clutch operable to condition the transmission for one gear ratio and a friction drum operatively connected to such said gear unit, said drum adapted to be frictionally engaged to condition the transmission for another gear ratio, a transmission case having a cavity formed therein, the improvement comprising

a friction band with apply and reaction ends disposed at least partially around said drum for the selective frictional engagement with said drum, said band having a first abutment member at said apply end and having a second abutment member at said reaction end,

a first piston operatively mounted for stroking movement in said cavity for effecting the frictional engagement of said band with said drum for establishing said another gear ratio,

an elongated force transmitting member operatively disposed between said first piston and said first abutment member,

a second piston operatively mounted in said cavity; an extension disposed between said second piston and said second abutment member and operative therebetween as a force transmitting member;

a source of fluid pressure;

fluid pressure chamber means for said first and second pistons; fluid conducting passages having an inlet port and a flow restricting means and an exhaust port, said inlet port leading between said chamber means and said source of fluid pressure;

a fluid control system controlling the fluid pressure in said fluid pressure chamber means;

said control system having a movable control valve element open to said inlet port for feeding pressure fluid through said flow restricting means into said fluid pressure chamber means; said control valve element being movable by varying brake band reaction force transmitted through said second abutment member to control and vary the degree of opening of said exhaust port and said chamber means to exhaust and thereby regulate the pressure of said fluid therein so that there is an increase in pressure in said chamber means when the transmitted torque of said band increases and a decrease in said pressure when the transmitted torque of said band decreases.

5,588,929

FOUR-SPEED AUTOMATIC TRANSMISSION


Howard L. Benford, Bloomfield Hills, Mich., assignor to Chrysler Corporation, Auburn Hills, Mich.

Filed Nov. 28, 1994, Ser. No. 345,669

Int. Cl.⁶ F16H 3/62

U.S. Cl. 475—276

17 Claims



1. A four-speed automatic transmission for a vehicle comprising a transmission housing;

an input member;

an output member;

three planetary gearsets for changing a ratio of torque between said input member and said output member;

a plurality of clutch assemblies to selectively couple said input member to predetermined gears of said planetary gearsets and a plurality of brake assemblies to selectively couple predetermined gears of said planetary gearsets to said transmission housing;

first means for allowing said output member and a planetary carrier from one of said planetary gearsets and an annulus gear of another of said planetary gearsets to rotate simultaneously;

said planetary gearsets comprising a first planetary gearset, a second planetary gearset axially spaced from said first planetary gearset and a third planetary gearset axially spaced from said second planetary gearset, said first planetary gearset being disposed between said input member and said second planetary gearset and said third planetary gearset being disposed between said second planetary gearset and said output member;

each of said first, second and third planetary gearsets comprising a sun gear, an annulus gear and a planetary carrier having a plurality of circumferentially spaced pinion gears disposed between said sun gear and said annulus gear; and

second means for allowing said sun gear of said first planetary gearset and said planetary carrier of said second planetary gearset and said annulus gear of said third planetary gearset to rotate or remain stationary simultaneously.

5,588,930

TWO-SPEED GEARBOX


Li-Yu Chen, Hsinchu, Taiwan, assignor to Industrial Technology Research Institute, Hsinchu, Taiwan

Filed Mar. 21, 1995, Ser. No. 407,566

Int. Cl.⁶ F16H 3/44

U.S. Cl. 475—300

1 Claim



1. A two-speed gearbox for use with a motor comprising:

- (a) a housing;
- (b) an input part, comprising:
 - (i) an input shaft which is connected from one end of the motor, said input shaft is provided with external splines;
 - (ii) a spline shaft which slides axially and rotates in the same direction as said input shaft and is located at a front end of said input shaft, wherein said spline shaft has a thick first end with a hollow portion provided with internal splines to mesh with said external splines of said input shaft; said spline shaft is also provided with external splines;
- (c) a gear shift mechanism, comprising a gear shift lever, a gear shift bearing, and a slider, wherein said gear shift lever is inserted from outside into said housing to drive said slider to slide on a fixed rod and, by use of said gear shift bearing, to connect a lower portion of said slider to a lock-in place on an outside surface of said spline shaft so as to drive said spline shaft to slide axially;
- (d) a speed reduction part comprising an annular gear, a planetary gear, a planetary gear frame and a sun gear, wherein said planetary gear frame is fixed to said housing by a pair of first bearings, said planetary gear is positioned to said planetary gear frame through a set of planetary gear shafts, said sun gear is positioned at said planetary gear frame by a second bearing, said planetary gear frame has an inner surface which is provided with internal splines and said sun gear also has an inner surface which is also provided with internal splines; said planetary gears and said sun gears are connected via a gear reducing means so as to cause a speed ratio to be effectuated;
- (e) an output part comprising an output shaft which is positioned at said housing by a pair of third bearings, said output shaft is provided with internal splines which are meshed with a matching set of external splines of a shaft coupler so as to cause both said output shaft and said shaft coupler to rotate synchronously after meshing and transmit power from said shaft coupler to said output shaft; said shaft coupler is also provided with internal splines;

(f) first and second position limiters provided on said spline shaft and said shaft coupler, respectively, wherein said first and second position limiters are positioned such that, during a normal operation condition, said spline shaft is stopped by said first position limiters so that a portion of said external splines of said spline shaft are engaged with said internal splines of said shaft coupler to transfer power thereto at a first gear ratio; with an increased force by which said gear shift lever pulls said spline shaft away from said shaft coupler, said first position limiter provided on the spline shaft will stop at said gear shaft beatings such that said external splines of said spline shaft are engaged with nothing, thus causing said gearbox to be at a neutral position; finally, when said gear shift lever pulls the spline shaft further away from said shaft coupler, said first and second position limiters and said gear shift bearing cooperatively cause said external splines of said shaft coupler to be engaged with said internal splines of said planetary gears frame, and said external splines of said spline shaft are to be engaged with said internal splines of said sun gears, so as to transfer power from said spline shaft to said shaft coupler at a second gear ratio.

5,588,932

DEVICE FOR THE SETTING OF THE MUTUAL POSITIONS OF PIVOTABLE ELEMENTS

Lennart Lindblad, Vårgårda, Sweden, assignor to Linvent AB, Vårgårda, Sweden

PCT No. PCT/SE93/00470, § 371 Date Dec. 27, 1994, § 102(e)

Date Dec. 27, 1994, PCT Pub. No. WO94/00314, PCT Pub.

Date Jan. 6, 1994


PCT Filed May 27, 1993, Ser. No. 362,593

Claims priority, application Sweden, Jun. 29, 1992, 9201988

Int. Cl.⁶ F16H 57/08

U.S. Cl. 475—341

9 Claims



1. A device for pivotably setting a relative position of a first and a second pivotable element, comprising:

- first and second driving components each having a plate-like configuration of a like thickness, and including coaxially aligned circular openings therein, each of said openings respectively defining a toothed periphery which forms a ring gear, each of said driving components circularly rotatable with respect to one another about a common and stationary axis, one of said ring gears having a larger diameter than the other;
- a sun gear spaced interiorly coaxially of said ring gears and circularly rotatable about said common axis;
- means for rotating said sun gear, said means disposed along said common axis and having said sun gear fixedly attached thereto;
- at least one planetary wheel gear, each of said planetary gears simultaneously enmeshed with said sun gear and each of said ring gears, each of said planetary wheel gears rotating about a respective axis, each of which is parallel to said common axis, each of said planetary wheel gear axis rotating circularly about said common axis as each said planetary wheel gear is rotatably driven, thereby rotating said ring gears and said first and second driven components coaxially with respect to one another;
- spacing means disposed between said driving components for maintaining a separation distance therebetween, said spacing means interposed between each of said planetary wheel gears;
- a pair of circular end discs coupled to each other, one said disc associated with said first driving component and the other said disc associated with said second component, said end disc arranged to enclose a respective said opening on said driving component, whereby said sun gear and said planetary wheel gears are retained interiorly of said ring gears;
- cylindrically configured bearing means for respectively supporting each of said planetary wheel gears along an axial direction, each of said bearing means of a like diameter and axially centered about its associated and respective planetary wheel gear axis, each of said bearing means extending between said end discs and received within a respective opening provided in each of said discs, said openings of a diameter larger than said diameter of said bearing means in order to provide limited radial movement of each bearing means from its respective planetary wheel gear axis; and
- means for simultaneously biasing each of said planetary gears radially outward into continuous enmeshed contact with each of said ring gears when said rotating means is acted upon, said biasing means continually eliminating any free slack between said planetary and ring gears.

5,588,931

PLANETARY REDUCER AND WHEEL BEARING UNIT

Franz Forster, Karlstadt-Mühlbach, Germany, assignor to Linde Aktiengesellschaft, Germany


Filed Jul. 6, 1994, Ser. No. 271,144

Claims priority, application Germany, Jul. 14, 1993, 43 23 539.5

Int. Cl.⁶ B60K 17/04; F16H 57/08

U.S. Cl. 475—338

25 Claims




1. An integral speed reduction and wheel mounting unit adapted to support a wheel on a motor vehicle, said unit comprising an axle pivot member having an outer surface, axially spaced annular bearings mounted on said outer surface of said axle pivot member, an annular axle housing having an inner surface mounted on said axially spaced bearings, whereby said axle pivot member is a driven member, a ring gear formed on said inner surface of said axle housing located between said axially spaced bearings, at least one intermediate shaft rotatably mounted in said axle pivot member, at least one radial recess formed in said axle pivot member and a planet gear fixed on said at least one intermediate shaft located partially within said radial recess and meshing with said ring gear, one end of said at least one intermediate shaft extending out of said axle pivot member and means for operatively connecting said one end of said at least one intermediate shaft to a drive shaft coaxial with the axis of rotation of said axle pivot member, whereby rotation of said at least one intermediate shaft rotates said axle pivot member relative to said annular axle housing.

5,588,933
INFINITE RATIOS CANT WHEEL TRANSMISSION
Delbert L. Hartman, Rte. #1 P.O. Box 292, McGeheysville, Va.
22840

Filed Aug. 23, 1993, Ser. No. 110,738
Int. Cl.⁶ F16H 15/18

U.S. Cl. 476-51

4 Claims




1. An infinitely variable ratio transmission including a housing a pair of laterally spaced and registered tapered input and output shafts journaled from said housing about substantially parallel axis and including adjacent peripheral portions disposed in substantially parallel planes, a pair of cantable intermediary power transmitting wheel journaled on said rack including surface areas disposed in optional resistance frictional engagement with the outer surface of said shafts and means operative to shift said cantable intermediary wheels along said rack also including two more intermediary wheels journaled within said bracket and means operative to reverse rotation of said output shaft.

5,588,934
SHIFTER WITH MEANS FOR ACTUATING CABLE TO KEY MECHANISM
Charles Osborn, Spring Lake; Robert M. Medema, Muskegon, and Andrew K. Ruiter, Spring Lake, all of Mich., assignors to Grand Haven Stamped Products, Grand Haven, Mich.
Filed Apr. 11, 1995, Ser. No. 419,804
Int. Cl.⁶ F16H 61/18; 63/36

U.S. Cl. 477-96

21 Claims



1. A transmission shifter for a vehicle including a shifter lever assembly having a handle, means for guiding said handle in movements along a serpentine path in shifting from "Park" position to other shifter positions, said serpentine path including move-

ments in fore and aft directions and sidewise directions transverse to said fore and aft directions, a cable connector for operatively connecting said lever assembly to a cable extending from a key mechanism of said vehicle to said shifter, the improvement comprising:


a first cam member;
a second cam member operatively connected to said cable connector; and
an operative connection between said lever assembly and said second cam member; said first cam member being mounted on said lever assembly and engaging said second cam member for moving said second cam member for actuating said cable connector to actuate said cable.

5,588,935
THROTTLE CONTROL FOR AUTOMATED MECHANICAL TRANSMISSION
Mark A. Dinski, Kalamazoo, and Donald D. Teadt, Vicksburg, both of Mich., assignors to Eaton Corporation, Cleveland, Ohio

Filed Sep. 29, 1995, Ser. No. 537,316
Int. Cl.⁶ B60K 41/03

U.S. Cl. 477-107

25 Claims



1. In combination, a throttle control assembly (36) and system controller (48) for controlling shifting in an automated mechanical transmission system (10) having a non-electronically controlled engine (14):

said throttle control assembly comprising a fuel controller (54) responsive to a control signal at an inlet (64/62) thereto to provide fueling of the engine in a minimum (idle) to a maximum amount, a first signal device (30) for providing a first signal (68) proportional to an operator setting of a manually controlled throttle device (32), a second signal device (74) for providing a second signal (76) effective when connected to said inlet to cause said fuel controller to fuel said engine to said maximum amount, said fuel controller biased to the position for fueling said engine in said minimum amount and effective to cause said engine to be fueled in said minimum amount in the absence of a signal at said inlet, a first control device (S1) having a first and second position and a second control device (S2) having a first and second position, said control devices cooperatively effective (i) when said first and second devices are both in the first positions thereof to connect said first signal to said inlet, (ii) when said first control device is in the first position thereof and said second control device is in the second position thereof, to cause an absence of a signal at said inlet, (iii) when said first control device is in the second position thereof and said second control device is in the first position thereof, to cause said first signal to be connected to said inlet, and (iv) when both said first and second control devices are in the second positions thereof, to cause said second signal to be connected to said inlet; and

said control having a memory for storing logic rules for (i) causing said first and second control devices to assume said first positions thereof when fueling of the engine is to be controlled by the operator, (ii) causing said first control device to assume said first position thereof and said second control

device to assume said second position thereof when decreased fueling of said engine is required, and (iii) causing said first and second control devices to assume said second positions thereof when increased fueling of said engine is required.


5,588,936
CONTROL APPARATUS FOR AUTOMATIC TRANSMISSION AND CONTROL METHOD THEREFORE
Makoto Uchida; Masahiko Ibamoto, both of Hitachinaka; Kazuhiko Sato, Hitachioota; Hiroshi Kuroiwa, Hitachi; Hiroshi Ohnishi, Hitachinaka, and Toshimichi Minowa, Toukai-mura, all of Japan, assignors to Hitachi, Ltd., and Hitachi Automotive Engineering Co., Ltd., both of Japan
Filed Apr. 27, 1995, Ser. No. 429,909

Claims priority, application Japan, Apr. 27, 1994, 6-089367; Jul. 20, 1994, 6-167704

Int. Cl.⁶ F02D 35/00; F16H 61/00

U.S. Cl. 477-155

22 Claims



1. A control apparatus for an automatic transmission mounted on a vehicle having a vehicle power train composed of an engine and an automatic transmission having a torque converter, and detecting means for detecting an engine rotational speed and an engine load of said vehicle power train and a vehicle speed of the vehicle, said control apparatus controlling said vehicle power train using signals detected by said detecting means, which control apparatus comprises:

characteristic memory means for storing an output power characteristic of the engine; and
means for obtaining a driving shaft torque in a first gear ratio before a gear shift of the automatic transmission, based on at least said engine rotational speed and said engine load detected by said detecting means and said output power characteristic stored in said characteristic memory means, estimating driving shaft torque in a second gear ratio after a gear shift of the automatic transmission, based on said engine load and said vehicle speed, and outputting a gear shifting signal to said automatic transmission at a time when said driving shaft torque before said gear shift falls below the value of said driving shaft torque after said gear is shifted, plus a certain predetermined value.


5,588,937
SLIP CONTROL APPARATUS FOR MOTOR VEHICLE LOCK-UP CLUTCH
Katsumi Kono, Toyota; Shinya Nakamura, Owariasahi, and Atsushi Honda, Susono, all of Japan, assignors to Toyota Jidosha Kabushiki Kaisha, Toyota, Japan
Filed Jul. 19, 1995, Ser. No. 504,078

Claims priority, application Japan, Jul. 22, 1994, 6-171469
Int. Cl.⁶ F16H 61/14

U.S. Cl. 477-169

8 Claims

1. An apparatus for controlling an amount of slip of a lock-up clutch connecting an input and an output rotary member of a fluid-filled power transmitting device of a motor vehicle, according to a slip control output such that an actual slip speed of the lock-up




clutch coincides with a target slip speed, said slip control output being determined according to a slip control equation including at least an integral action term, and on the basis of a feedback control value for zeroing a control error between said actual and target slip speeds, and a learning control value which is updated depending upon a running condition of the vehicle, said apparatus comprising: slip control means for providing said slip control output; and output change restricting means for adjusting said feedback control value such that an amount of change of said slip control output provided by said slip control means is smaller than an amount of change of said learning control value.

5,588,938
STRENGTH OF A MUSCLE TRAINING APPARATUS
Werner Schneider, Ermatingen; Hansueli Lerch, Steckborn, and Erich Hausmann, Ermatingen, all of Switzerland, assignors to Fritz Gegauf AG Bernina Nahmaschinenfabrik, Steckborn, Switzerland
Filed Nov. 18, 1994, Ser. No. 344,645
Claims priority, application Switzerland, Nov. 30, 1993, 03 569/93

U.S. Cl. 482-4

Int. Cl.⁶ A63B 21/00

19 Claims



1. A strength or muscle training apparatus comprising engaging elements for arm and foot training, program-controllable driving means for moving and loading said engaging elements, extension arms carrying said engaging elements, a supporting structure having a plurality of coupling means at different levels for attachment of each of said extension arms at a selectable fixed level of said supporting structure, the apparatus thus being adaptable for a wide variety of training conditions.

5,588,939

EXERCISE BIKE WITH AMUSEMENT FEATURES


Yu Zheng, 1065 Howard Ave., Covina, Calif. 91722

Filed Jan. 11, 1996, Ser. No. 584,171

Int. Cl.⁶ A63B 69/16

U.S. Cl. 482—57

6 Claims



1. An exercise apparatus, comprising:
a base comprising a seat assembly provided thereon;
a flywheel comprising a plurality of ornaments provided therein;
a housing assembly connected to the base for rotatably supporting the flywheel; and
a pedal assembly rotatably coupled to the housing assembly and the flywheel;
wherein rotation of the pedal assembly causes the flywheel to rotate, thereby causing the plurality of ornaments inside the flywheel to bounce around.

5,588,940

WEIGHT SUPPORTING BODY HARNESS


Eric M. Price, and Aaron R. Price, both of 63 Cambridge Dr., Short Hills, N.J. 07078

Filed Jun. 12, 1995, Ser. No. 489,392

Int. Cl.⁶ A63B 21/065

U.S. Cl. 482—105

4 Claims



1. A weight supporting body harness adapted to be positioned on the body of a user to facilitate the attachment of additional weight to the user, said weight supporting body harness comprising:
a continuous, nonelastic torso engaging webbing assembly including left and right suspending portions with left and right

front ends adapted to be positioned about the torso of a user with said suspending portions engageable with a user's shoulders;
a waist encircling webbing assembly including left and right side waist straps each having a forward end and a rear portion adapted to be positioned about the waist of a user;
means to adjust a length of said torso engaging webbing assembly;
means to adjust a length of said waist encircling webbing assembly;
a front hoop supported by said left and right front ends of said continuous torso engaging webbing assembly, said front hoop adapted to be positioned at a first portion of a user's waist;
means to connect said forward ends of said left and right side waist straps to said front hoop;
a rear hook connected to said continuous torso engaging webbing assembly generally at a midlength thereof, said rear hook adapted to be positioned at a rear portion of a user's waist;
means to connect said rear portions of said left and right side waist straps to said rear hook; and
a flexible weight suspending means having a front end releasably secured to said front hoop and a back end releasably secured to said rear hook said weight suspending means for use to support weight between the legs of a user of said weight supporting body harness.

5,588,941

SPINE THERAPY AND EXERCISE DEVICE


Gary L. Scott, 331 Indian Hills Circle, Clinton, Anderson County, Tenn. 37716

Filed May 22, 1995, Ser. No. 445,691

Int. Cl.⁶ A63B 21/00

U.S. Cl. 482—131

19 Claims



1. A spine therapy and exercise device for stretching and strengthening muscles associated with one of at least a person's back, abdomen, and legs, said spine therapy and exercise device comprising:
a belt member defining a loop configuration, said belt member including a torso engagement portion and a leg engagement portion each being fabricated from a durable and flexible material, said torso and leg engagement portions each defining a proximal end and a distal end, said torso engagement portion being dimensioned to circumvent at least a person's back and sides, said leg engagement portion being secured to said torso engagement portion in an end-to-end fashion and being dimensioned to receive a portion of at least one of the person's legs;
a harness carried by said belt member, said harness torso engagement portion of said belt member proximate an upper portion of the user's back; and
an adjustment member for varying a length of said loop configuration defined by said belt member, said adjustment member being secured to said proximal end of said torso engagement portion, said distal end of said leg engagement portion being

5,588,942

ADJUSTABLE EXERCISE DEVICE


Keith A. Dillard, 9108 Helena Rd., Pelham, Ala. 35124

Filed Apr. 21, 1995, Ser. No. 426,915

Int. Cl.⁶ A63B 21/00

U.S. Cl. 482—139

14 Claims



1. An adjustable exercise device comprising an elongated rigid bar having a longitudinal axis, a pair of spaced hand grips, each hand grip including a hand grip portion adapted to be manually gripped and a mounting portion for mounting the hand grip portion on said bar, said mounting portion being freely pivotally supported by said bar for pivotal movement about a pivot axis extending substantially perpendicular to said longitudinal axis, a swivel connection between said hand grip portion and said mounting portion so that the hand grip portion can swivel relative to said mounting portion through an angle of 360 degrees about an axis of rotation, said axis of rotation being disposed substantially perpendicular to and passing through said pivot axis at the point where said mounting portion is pivotally supported by said bar, said locking means for selectively locking said swivel connection to prevent the hand grip portion from swiveling relative to said mounting portion.

5,588,943

CARTON BOTTOM SEALING DIES

Vincent Mills, and Tim P. Hughes, both of Cedar Rapids, Iowa, assignors to International Paper Company, Purchase, N.Y.


Division of Ser. No. 215,173, Mar. 21, 1994, Pat. No.

5,482,204. This application Oct. 10, 1995, Ser. No. 541,943

Int. Cl.⁶ B31B 1/88

U.S. Cl. 493—58

5 Claims



1. A paperboard container bottom sealing tool comprising a cooperative pair of embossing dies, said pair including a convex surface die and a concave surface die, said concave surface die including at least three substantially parallel planar areas of concentrically diminishing areal magnitude aligned in a stepped sequence, two innermost planar areas being delineated by respective riser ridges about an outer perimeter thereof, said convex surface die including a plurality of substantially parallel planar areas of concentrically diminishing areal magnitude aligned in a stepped sequence and in meshing correspondence with planar areas respective to said concave die, said convex die having at least two interior planar areas delineated by respective riser ridges, the

interior planar area that is innermost of said convex die being transversely divided into at least two portions by an air venting channel therebetween.

5,588,944

APPARATUS FOR WELDING THE TUBULAR SECTIONS OF SACKS, BAGS OR THE LIKE

Fritz Achelpohl, Lienen, and Hermann Sandmeier, Bielefeld, both of Germany, assignors to Windmüller & Hölscher, Lengerich/Westf., Germany


Filed Aug. 1, 1994, Ser. No. 282,481

Claims priority, application Germany, Aug. 2, 1993, 43 25 877.8

Int. Cl.⁶ B31B 19/60; 21/60

U.S. Cl. 493—205

6 Claims



1. An apparatus for welding tubular sections of sacks, bags or the like, comprising:
a rotating drum,
welding stations arranged on the periphery of the drum so as to rotate with, while fixed relative to, the drum, wherein the welding stations are arranged laterally each on one of end sides of the drum;
on the drum, grippers that can be caused to open and close and are assigned to the individual welding stations for seizing, holding and release of the tubular sections; and
a movable welding jaw of the welding station, forming a flat bearing surface for the zone of the tubular section to be welded, while the drum itself has a cylindrical peripheral surface,
said welding station including upper and lower ones of said welding jaws, of which the lower welding jaw can be pivotally connected by means of resiliently deformable plates extending substantially parallel to each other, to a stand fixed to the drum and being pivotable by means of a piston-and-cylinder arrangement that is articulated on a knee lever.

5,588,945

METHOD AND DEVICE FOR SPACING A CORRUGATING FINGER RELATIVE TO A CORRUGATING ROLL

David M. Lauderbaugh, Roswell, Ga., assignor to Corrugated Gear & Services, Inc., Alpharetta, Ga.

Filed Feb. 21, 1995, Ser. No. 395,379


Int. Cl.⁶ B31B 1/00; B31F 1/20

U.S. Cl. 493—480

23 Claims

1. A device for spacing a corrugating guide finger, having an outer surface and an inner surface, a leading end and a trailing end, relative to a corrugating roll defining an outer surface, the corrugating guide finger and the corrugating roll being arranged so as to receive a corrugating medium therebetween, the device comprising:

a head, configured for engagement with the corrugating guide finger wherein the head further comprises a hole for receipt of the trailing end of the corrugating guide finger; and



a tail connected to the head and configured for placement between the inner surface of the corrugating guide finger and the outer surface of the corrugating roll.

5,588,946


CENTRIFUGE AND PHASE SEPARATION

Gary A. Graham, Rochester; Merrit N. Jacobs, Fairport, both of N.Y.; Russel H. Marvin, Riverton, Wyo.; James D. Shaw, Hilton, and Nicholas VaoBrunt, Rochester, both of N.Y., assignors to Johnson & Johnson Clinical Diagnostics, Inc., Rochester, N.Y.

Continuation-in-part of Ser. No. 265,536, Jun. 24, 1994, abandoned. This application Jun. 6, 1995, Ser. No. 466,640
Int. Cl.⁶ B04B 5/02; 1/3/00

U.S. Cl. 494—11

10 Claims



7. A centrifuge for spinning tubes containing a gel separator and patient sample, comprising

- a rotor;
- a motor operatively connected to said rotor to rotate it about a rotor axis to generate centrifugal forces in directions radiating from said axis;
- a sample tube holder pivotally mounted adjacent to one end on a pivot on said rotor and constructed to hold a patient sample test tube having a long axis;
- a latch disposed at a location adjacent the end of said holder opposite to said one end in position to removably engage said holder, said holder being freely pivotable about said pivot except when engaged by said latch, said latch location and said pivot forming a first position for said test tube axis that is misaligned with a radius of said rotor by a non-zero angle to provide the Boycott effect to a sample test tube in said tube holder when said rotor is rotating, said latch location being farther from said rotor axis than said pivot,
- and moving means on said rotor for unlatching and opening said latch in response to a predetermined centrifugal force generated by spinning said rotor, said moving means including a weight slidably mounted on said rotor and connected to said latch to move to unlatch said latch in response to a predeter-

mined centrifugal force in excess of force generated by rotating for said Boycott effect.

5,588,947


APPARATUS AND METHOD FOR TREATING HAZARDOUS WASTE MATERIAL

Michael K. Studer, Flower Mound; Thomas J. Zodrow, Grapevine, both of Tex., and Timothy J. Elms, Plant City, Fla., assignors to Entact Corporation, Irving, Tex.

Filed Nov. 29, 1994, Ser. No. 346,634
Int. Cl.⁶ A62D 3/00; B09B 3/00

U.S. Cl. 588—252

19 Claims



1. A device for transforming hazardous waste into a stable nonhazardous substance comprising:
 - a preliminary conditioning unit;
 - a screening unit coupled to the preliminary conditioning unit via a first conveyor; and
 - a recycling unit coupled to the screening unit via a second conveyor.

12. A method of transforming hazardous waste into a stable nonhazardous substance comprising the steps of:

- a) separating the hazardous waste into oversized materials and smaller materials in a first screening member;
- b) crushing the oversized materials;
- c) adding a bonding additive to the oversized materials;
- d) combining the crushed oversized materials with the smaller materials;
- e) separating oversized materials from smaller materials in a second screening member;
- f) adding a binding additive to the smaller materials to create a mixture; and
- g) grinding the mixture into the stable, nonhazardous substance.

5,588,948

STEREOSCOPIC ENDOSCOPE

Susumu Takahashi, Iruma; Masao Uehara, Hachioji; Shingo Kato, Chofu; Atsushi Kidawara, Tachikawa; Katsuyuki Saito, Hachioji; Masahito Goto, Saitama-ken; Wataru Ohno, Hachioji; Iwao Kanamori, Yokohama; Toyoharu Hanzawa, Fuchu; Kenji Yoshino, Hachioji; Akio Nakada, Hachioji; Akihiro Taguchi, Hachioji; Nobuaki Akai, Hino; Hitoshi Karasawa, Hachioji; Toshihiko Hashiguchi, Sagami-hara; Akihiko Mochida, Hachioji; Takashi Fukaya, Hachioji; Shinji Yamashita, Hachioji; Akira Murata, Hino; Hideki Koyanagi, Hachioji, and Keisuke Saito, Fuchu, all of Japan, assignors to Olympus Optical Co. Ltd., Tokyo, Japan


Filed Sep. 17, 1993, Ser. No. 122,303

Claims priority, application Japan, Feb. 17, 1993, 5-028278
Int. Cl.⁶ A61B 1/04; H04N 13/00

U.S. Cl. 600—111

14 Claims

9. A stereoscopic endoscope having an inserting section comprising:
 - an image forming optical system arranged in an inserting section of the endoscope and provided with a single objective lens system at a distal end of the inserting section for forming an object image, and an image transmission means including a



relay lens system for reforming said object image, said objective lens system and said relay lens system having a common optical axis;

pupil dividing shutter means for selectively making different areas of a pupil of said image forming optical system transmittable by receiving light transmitted through said relay lens system;

a single image sensing means for receiving images formed by light fluxes transmitted through said pupil dividing shutter means;

a first support means for supporting at least said objective lens system; and

a second support means for supporting at least said image sensing means,

said first and second support means each being independently rotatable relative to each other around an axis extending along the longitudinal dimension of the endoscope.

wherein said endoscope is separated into said inserting section supported by said first support means containing said objective lens system and said image transmission means and an operating/holding section supported by said second support means containing said pupil dividing shutter means and said image sensing means for picking up object images obtained by said pupil dividing means, said inserting section and said operating/holding section being rotatable relative to each other around the optical axis of the optical system.

5,588,949

STEREOSCOPIC PERCUTANEOUS VISUALIZATION SYSTEM

Charles S. Taylor, San Francisco; Brian S. Donlon, Palo Alto, and Timothy R. Machold, Moss Beach, all of Calif., assignors to Heartport, Inc., Redwood City, Calif.


Continuation-in-part of Ser. No. 135,387, Oct. 8, 1993, abandoned. This application Apr. 13, 1994, Ser. No. 227,366

Int. Cl.⁶ A61B 1/00; 1/313

U.S. Cl. 600—166

74 Claims

1. An improved surgical microscope of the type having a microscope body, lens device attached to the microscope body for magnifying an object image, and an eyepiece attached to the microscope body for viewing the magnified object image, the improvement comprising a supplementary lens and a coupling device attached to the microscope body for retaining the supplementary lens in optical alignment with the lens device, wherein the coupling device comprises a cannula having a passage in which the supplementary lens may be removably positioned, the cannula having a distal end configured for introduction into the body cavity through a percutaneous penetration.



5,588,950

PORTABLE ENDOSCOPE SYSTEM

Hiroshi Sano; Hirohisa Ueda; Rensuke Adachi; Kunitoshi Ikeda; Kunikiyo Kaneko, and Takashi Koeda, all of Tokyo, Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jul. 7, 1995, Ser. No. 499,128

Claims priority, application Japan, Jul. 11, 1994, 6-157748; Apr. 20, 1995, 7-094093; Apr. 20, 1995, 7-094622

Int. Cl.⁶ A61B 1/06

U.S. Cl. 600—178

9 Claims



1. A portable endoscope system having an illuminating light guide for transmitting light for illuminating an object, said illuminating light guide having an entrance end portion disposed in an endoscope control part, and an illuminating light supply unit for supplying illuminating light to said illuminating light guide, said illuminating light supply unit being detachably attached to said control part, said portable endoscope system comprising:

an AC/DC conversion adapter which is connected to an AC power supply to output a predetermined DC voltage, said AC/DC conversion adapter being connectable to said illuminating light supply unit;

wherein said illuminating light supply unit comprises a light source lamp for emitting illuminating light which is supplied to said illuminating light guide, and a battery for supplying lighting energy to said light source lamp, said AC/DC conver-

sion adapter being connected to said illuminating light supply unit through a space defined in said illuminating light supply unit by removal of said battery; and wherein the AC power supply supplies lighting energy to said light source lamp through said AC/DC conversion adapter.

5,588,951

INFLATABLE ENDOSCOPIC RETRACTOR WITH MULTIPLE RIB-REINFORCED PROJECTIONS

Yong H. Zhu, Loma Linda, and Wolff M. Kirsch, Redlands, both of Calif., assignors to Loma Linda University Medical Center, Loma Linda, Calif.


Division of Ser. No. 6,250, Jan. 19, 1993, Pat. No. 5,400,773.

This application Jan. 27, 1995, Ser. No. 379,258

Int. Cl.⁶ A61B 17/32; 10/00

U.S. Cl. 600—207

5 Claims



1. An inflatable retractor adapted for use in endoscopic surgery on a patient's body, comprising:

- a) an outer, elongate rigid cannula for insertion into said patient's body;
- b) a non-collapsible tube having a distal end and a proximal end, said tube being capable of being inserted into said cannula such that a portion of said proximal end of said inner tube remains outside the patient's body;
- c) a balloon having a plurality of inflatable projections joined at a single opening mounted on the distal end of said tube and supported and positioned by said tube;
- d) support ribs, wherein each of said projections has an attached support rib, said support rib being capable of being manipulated into a first bent position prior to insertion into said cannula, but adapted to straighten upon insertion into said cannula and then spring back into said first bent position upon exiting said cannula.

5,588,952

INTRACARDIAC ILLUMINATOR WITH SUCTION

Bhaktavatsala R. Dandolu, 585 General Patterson Dr., Philadelphia, Pa. 19038


Filed Aug. 2, 1993, Ser. No. 101,452

Int. Cl.⁶ A61B 1/06; A61M 1/00

U.S. Cl. 600—249

16 Claims

1. A flexible illumination and suction device comprising a flexible fiber optic cable having a distal end terminated directly below a transparent cover that forms part of a first section of a rigid, two section housing having a length that is a minor portion of the cable, and a proximal end connected to a light source disposed outside the device; a single flexible aspiration conduit having a distal end connected to and in fluid communication with an opening providing fluid communication with a second section of the rigid housing to create a single aspiration channel and a proximal end terminated by a suction connector; and a flexible tubular body surrounding the fiber optic cable and the aspiration conduit therein and sealed to the housing and the connector in a fluid tight manner, wherein the fiber optic cable comprises a bundle of fibers cut at an angle of less than 90 degrees relative to its longitudinal dimension and thereby directly emits light in a radial direction from the fibers of the bundle, and wherein the second section of the housing terminates in an aspiration tip disposed distally forward of the first section, whereby fluid is rapidly aspirated to permit an area of tissue to be observed.



5,588,953

ROLLER ASSEMBLY FOR MASSAGING DEVICE


Chien-Chung Chang, No. 82, Ho Tso Street, Sun Chung Li, Feng Yuan City, Taiwan

Filed Dec. 28, 1995, Ser. No. 580,310

Int. Cl.⁶ A61H 15/00; 39/04

U.S. Cl. 601—124

2 Claims



1. A roller assembly for a massaging device, said roller assembly comprises:

- a) a shaft having one end of a hollow construction and further having another end provided with two lugs and a ratchet located between said two lugs for holding securely a resilient cord, said one end of a hollow construction provided in an inner wall thereof with a plurality of retaining ribs arranged at an interval;
- b) a plurality of roller sleeves fitted rotatably over said shaft and provided respectively on an outer wall surface thereof with a plurality of massaging protuberances; and
- c) a locating plug having one end secured to said one end of said shaft, said one end of said locating plug provided in an outer wall surface thereof with a plurality of retaining slots engageable with said retaining ribs of said shaft when said locating plug is secured to said one end of said shaft, said locating plug further having another end provided with two lugs and a ratchet located between said two lugs for holding securely a resilient cord.

5,588,954

CONNECTOR FOR A GRADIENT SEQUENTIAL COMPRESSION SYSTEM

Philip P. Ribando; Kenneth M. Bolam; Donald H. Peeler, all of Charlotte, N.C., and Terry L. Sandman, Toledo, Ohio, assignors to Beiersdorf-Jobst, Inc., Charlotte, N.C.


Filed Apr. 5, 1994, Ser. No. 222,829

Int. Cl.⁶ A61H 1/00

U.S. Cl. 601—149

3 Claims

1. A connector for providing a continuous fluid passageway between a source of pressurized fluid and an elongated pressure



sleeve, said sleeve defining a plurality of inflatable chambers, each of said chambers having a means for attachment to the source of pressurized fluid at a connector interface having a plurality of outlet ports, said connector comprising:

- a) a flexible conduit comprising a plurality of elongate tubes, each of said tubes having a first end and a second end; and
- b) at least one elongate connecting partition integrally formed between an adjacent pair of said tubes;
- c) a plurality of fittings, each of said fittings attached to said first end of one of said tubes and forming a fluid-tight seal therewith, each of said fittings having means for forming a fluid-tight seal with one of said outlet ports to communicate the pressurized fluid; and
- d) a grip portion comprising at least one finger for engaging a hole provided in said at least one connecting partition to enhance the transfer of stresses from said conduit to said grip portion attached adjacent said first ends of said tubes and gripping said at least one connecting partition to transfer stresses induced in said conduit to said grip portion without substantially compressing said tubes, said grip portion releasably retaining said fittings in fluid-tight relationship with said outlet ports.

inflatable cuff means for applying pressure to the leg, said cuff means being in fluid communication with said reservoir, and said cuff means being configured to apply said therapeutic pressure substantially to the medial and lateral aspects of the leg.

means for facilitating the intermittent transmission of compressed fluid from said reservoir to said inflatable cuff means, said facilitating means comprising a valve means operatively disposed between said reservoir and said cuff means and a timer operatively coupled to said valve means, whereby said timer may be set to operate said valve means at predetermined intervals and for pre-determined periods of time to control the intermittent transmission of compressed fluid from said reservoir to said cuff means, said valve means also permitting exhaustion of fluid from said cuff means.

pressure relief means operatively coupled to said inflatable cuff means for controlling the pressure therein, and

further including an air cell adapted to be operatively disposed between said cuff means and the leg, and a bellows in sealed fluid communication with said air cell, said air cell and bellows adapted to provide an indication of the intermittent application of therapeutic pressure to said body portion.

5,588,956

METHOD FOR SUPPORTING BODY JOINTS AND BRACE THEREFOR

Joseph D. Billotti, 18 Powder Hill, Saddle River, N.J. 07458


Continuation-in-part of Ser. No. 366,316, Dec. 29, 1994, Pat. No. 5,527,267, which is a division of Ser. No. 137,830, Oct. 15, 1993, Pat. No. 5,378,224, which is a continuation-in-part of Ser. No. 73,722, Jun. 9, 1993, abandoned. This application

May 17, 1995, Ser. No. 442,782

Int. Cl.⁶ A61F 5/00

U.S. Cl. 602—13

10 Claims



1. A brace for supporting a weakened joint of the body, the weakened joint being a knee joint wherein both the anterior cruciate ligament and the posterior cruciate ligament are absent or have been repaired, so as to permit translation of the knee joint while restraining movement of the knee joint in directions which would tend to strain the cruciate ligaments to thereby support the weakened knee joint against movement of the knee joint in said directions and concomitant further injury to the knee joint, the brace comprising:

a) a flexible sheet adapted to be applied to the knee joint so as to protect the weakened knee joint from abrasion while permitting translation of the knee joint;

b) two inflatable chambers contained within the flexible sheet, each of said chambers including a medial section having a generally sinuous shape for juxtaposition with the weakened knee joint along a corresponding generally helical path of each of the cruciate ligaments around the knee joint to establish two corresponding generally helical paths around the knee joint as determined by the sinuous shapes of the inflatable chambers when the brace is applied to the weakened knee joint, one of said two helical paths corresponding to the path of the anterior

METHOD AND APPARATUS FOR PROVIDING THERAPEUTIC COMPRESSION FOR REDUCING RISK OF DVT


Glenn W. Johnson, Jr., Summit; Henry J. McVicker, and David C. Hargrave, both of Chatham, all of N.J., assignors to Aircast, Inc., Summit, N.J.

Continuation of Ser. No. 88,895, Jul. 8, 1993, abandoned. This application Apr. 12, 1995, Ser. No. 421,040

Int. Cl.⁶ A61H 9/00

U.S. Cl. 601—152

15 Claims



2. An apparatus for applying therapeutic intermittent pressure to a human leg, said apparatus comprising

- a) a pump means,
- b) a fluid reservoir for receiving a substantially steady flow of pressurized fluid from said pump means,

cruciate ligament and the other of said two helical paths corresponding to the path of the posterior cruciate ligament, said inflatable chambers being flexible when deflated, for conforming to said two generally helical paths around the knee joint, and being relatively stiff when inflated for contacting and supporting the weakened knee joint along said two generally helical paths around the knee joint such that anterior and posterior translations of the knee joint are permitted and motion of the knee joint in said directions which would place a strain on the cruciate ligaments is restrained;

means for holding the brace firmly in place when applied to the knee joint, with the inflatable chambers following the two generally helical paths around the weakened knee joint; and means for selectively inflating the inflatable chambers subsequent to applying the brace to the knee joint such that upon application of the brace to the knee joint and subsequent inflation of the inflatable chambers the weakened knee joint is supported with anterior and posterior translation of the knee permitted by virtue of the flexibility of the flexible sheet, while movement in said directions which would tend to strain the anterior and posterior cruciate ligaments is restrained by virtue of the stiffness and shape of the inflated chambers.


5,588,957 CERVICAL COLLAR

Bill Martin, Sr., Shepherdsville, Ky., assignor to Ambu International A/S, Glostrup, Denmark
Continuation of Ser. No. 237,139, May 3, 1994, abandoned, which is a continuation of Ser. No. 64,221, May 20, 1993, Pat. No. 5,336,438. This application Aug. 15, 1995, Ser. No. 515,219

Int. Cl.⁶ A61F 5/04

U.S. Cl. 602-18

14 Claims



1. A cervical collar comprising: an elongated neck encircling band, said elongated neck encircling band having a collar retaining means; a chin support brace secured to said elongated neck encircling band, said chin support brace having: a first chin support element; and a second chin support element; said first chin support element and said second chin support element each has a first end and a second end, said first end of each of said first chin support element and said second chin support element is rotatably affixed to first and second locations on said elongated neck encircling band, said second end of said first chin support element rotatably overlaps and is affixed to said second end of said second chin support element; and a locking means secured to said chin support brace whereby rotation of said first chin support element and said second chin support element into an operable and locked position bows said chin support brace.


5,588,958 CLOSED WOUND ORTHOPAEDIC DRAINAGE AND AUTOTRANSFUSION SYSTEM

Robert W. Cunningham, Cohasset, Mass.; Durmus Koch, Demarest, N.J.; Janine R. Mura, Colchester, Conn.; Augustus Felix, Providence, and Gary V. Halick, East Greenwich, both of R.I., assignors to C. R. Bard, Inc., Murray Hill, N.J.
Filed Sep. 21, 1994, Ser. No. 310,268

Int. Cl.⁶ A61M 37/00

U.S. Cl. 604-4

24 Claims



1. A closed wound orthopaedic drainage system for the collection of a patient's autologous shed blood following orthopaedic surgery comprising: a substantially rigid collection container having an interior, a liquid inlet and a liquid outlet; a patient drainage tube coupled with the liquid inlet of the rigid collection container and being adapted to be open to receive autologous shed blood from a wound and transfer it to the rigid collection container; a blood collection bag having a liquid inlet and liquid outlet for receiving the blood transferred from the rigid collection container for reinfusion back into the patient, the rigid container adapted to be elevated relative to the collection bag; a transfer tube coupled with the liquid outlet of the rigid collection container and liquid inlet of the bag for transferring the blood from the rigid collection container to the bag; a suction reservoir means separated from and in fluid communication with the interior of the rigid collection container for applying suction to the container interior to cooperate in draining the blood from the wound through the patient drainage tube into the collection container whereby elongated tubing means extending between the separated collection container and the suction reservoir means for coupling the interior of the rigid collection container and the interior of the suction reservoir means; coupling means for permitting the suction reservoir means to be coupled directly to the patient drainage tube, when the patient drainage tube is open and the transfer tube is closed and suction is applied to the collection container by the suction reservoir, the blood is adapted to flow from the patient wound through the transfer tube into the collection container, when blood is to be transferred from the collection container to the collection bag, the patient drainage tube is closed, the transfer tube is opened, suction is released from the system, the container is elevated relative to the bag to permit gravity flow of blood;

when the blood has been transferred to the collection bag, the transfer tube is closed, the patient drainage tube is opened and suction is reapplied by the suction reservoir means; when the blood transferred to the collection bag is to be reinfused into the patient, an administration set is coupled with the outlet of the bag, and the bag is suspended from an IV pole and the administration set is coupled with the patient.

5,588,959 HEMODIALYSIS RECIRCULATION MEASURING METHOD


Suhail Ahmad, Seattle; James J. Cole, Arlington, and Mahboob Ahmed, Bothell, all of Wash., assignors to University of Washington, Seattle, Wash.

Filed Aug. 9, 1994, Ser. No. 288,678

Int. Cl.⁶ A61M 37/00; 1/00

U.S. Cl. 604-6

5 Claims



1. A method for determining the amount of recirculation in a patient undergoing a dialysis treatment, comprising measuring temperature of an arterial limb and a venous limb of a dialysis access, changing temperature of blood being returned to the patient without adding volume, and measuring temperature of the arterial limb and the venous limb of the dialysis access to determine if there is a temperature change in the arterial limb to determine the amount of recirculation.

5,588,960 TRANSURETHRAL NEEDLE DELIVERY DEVICE WITH CYSTOSCOPE AND METHOD FOR TREATMENT OF URINARY INCONTINENCE

Stuart D. Edwards, Los Altos; Ronald G. Lax, Grass Valley, and Hugh R. Sharkey, Redwood City, all of Calif., assignors to Vidamed, Inc., Menlo Park, Calif.


Filed Dec. 1, 1994, Ser. No. 349,064

Int. Cl.⁶ A61B 17/39

U.S. Cl. 604-20

17 Claims

1. A medical device for use in a female human body to deliver an agent to a target volume of tissue including a sphincter muscle which surrounds a urethra in the body to treat urinary incontinence, the urethra formed by a urethral wall extending from a bladder to the exterior of the body, comprising an elongate probe member having proximal and distal extremities and a longitudinal axis, the elongate probe member being sized to be able to enter the urethra and having a length so that when the distal extremity is disposed in the vicinity of the target volume of tissue the proximal extremity is outside of the urethra, the elongate probe member having a passage extending from the proximal extremity to the distal extremity, at least one tubular needle disposed in the passage and having first



and second extremities and a flow passageway therein extending longitudinally from the first extremity to at least one opening provided in the second extremity, a control handle secured to the proximal extremity of the elongate probe member, operative means carried by the control handle and connected to the first extremity of the at least one tubular needle for causing movement of the at least one tubular needle in the passage and means carried by the elongate probe member for directing the at least one tubular needle through a curved path extending at an angle to the longitudinal axis as the at least one tubular needle moves in the passage, the tubular needle and the operative means included within means for introducing the agent into the target volume so as to add mechanical support to the sphincter muscle and thus increase the closure forces exerted by the sphincter muscle upon the urethra.



5,588,961 ELECTRO-OSMOTIC INFUSION CATHETER

James E. Leone, and Stephen M. Rowland, both of Miami, Fla., assignors to Cordis Corporation, Miami Lakes, Fla.
Division of Ser. No. 259,534, Jun. 14, 1994, Pat. No. 5,505,700. This application Jan. 5, 1996, Ser. No. 582,328

Int. Cl.⁶ A61M 31/00

U.S. Cl. 604-21

2 Claims



1. A method for infusion of a treatment fluid to a location within a living body, the method comprising the steps of: providing an infusion catheter having a treatment length along which are located at least one balloon member and at least two electrodes positioned on opposite sides of the balloon member, one of the electrodes having a charge the same as that of a treatment fluid, this electrode being closely positioned with respect to a location at which the treatment fluid infuses from a distal portion of the catheter assembly;

inserting the infusion catheter into a vessel or cavity of a living body;
 inflating the balloon member so as to engage the body vessel or cavity;
 applying an EMF source to the electrodes whereby said one electrode has one charge and the other electrode has the opposite charge;
 infusing medicament into the distal portion of the catheter assembly at a location generally along the internal catheter, the medicament having a charge the same as that of said one electrode to thereby move the medicament away from said one electrode and to the body vessel or cavity to be treated in accordance with the method; and
 migrating the medicament of the infusing step to the body vessel or cavity at a rate faster than that achievable by osmotic pressure alone.

5,588,962

DRUG TREATMENT OF DISEASED SITES DEEP WITHIN THE BODY


Peter M. Nicholas, South Dartmouth; Ronald A. Sahatjian, Lexington, and James J. Barry, Marlborough, all of Mass., assignors to Boston Scientific Corporation, Natick, Mass.

Filed Mar. 29, 1994, Ser. No. 219,108

Int. Cl.⁶ A61N 1/30

U.S. Cl. 604—52

27 Claims



1. A method for treating a diseased site in a vascular lumen deep within the body of a patient, comprising:
 - (a) providing a drug-localizing agent for a drug that is effective to treat said diseased site;
 - (b) providing a medical device capable of being placed into said vascular lumen at said diseased site and capable of delivering said localizing agent locally at said site;
 - (c) preparing said medical device for delivering said agent at said site;
 - (d) placing said medical device at said site;
 - (e) locally delivering said agent to said site in a manner that said agent is retained at said site;
 - (f) removing said medical device from said vascular lumen;
 - (g) providing said drug effective to treat said diseased site in a form suitable for systemic administration; and
 - (h) systematically administering said drug so that said drug is transported through the body of said patient and localized at said diseased site by the presence of said drug-localizing agent retained at said site.

5,588,963

METHOD FOR LIQUID FLOW MEASURING AND APPARATUS TO PRACTICE THIS METHOD

Bernardus J. G. M. Roelofs, Dammestraat 1, NL 5628 NM Eindhoven, Netherlands

PCT No. PCT/NL92/00193, § 371 Date Apr. 29, 1994, § 102(e) Date Apr. 29, 1994, PCT Pub. No. WO93/09407, PCT Pub. Date May 13, 1993


PCT Filed Oct. 28, 1992, Ser. No. 240,665

Claims priority, application Netherlands, Oct. 30, 1991, 9101825

Int. Cl.⁶ A61M 5/16

U.S. Cl. 604—65

16 Claims



11. An apparatus for measuring either a flow rate of a liquid, comprising:
 - a) a fluid outlet through which the liquid flows and forms a droplet;
 - b) an imaging means for imaging said droplet at different instants in time;
 - c) projection means for projecting images of said droplet onto said imaging means; and
 - d) processing means coupled to said imaging means for determining the different volumes of said droplet at different instants in time from the images of said droplet projected onto said imaging means, for taking the difference between said different volumes to provide a volume growth of said droplet, and for determining said flow rate based on said volume growth of said droplet over a period of time defined by said different instants.

5,588,964

STEERABLE CATHETER WITH ADJUSTABLE BEND LOCATION AND/OR RADIUS AND METHOD

Mir A. Imran, Palo Alto; Mark L. Pomeranz, Los Gatos, and Brian A. Glynn, Sunnyvale, all of Calif., assignors to Cardiac Pathways Corporation, Sunnyvale, Calif.


Continuation of Ser. No. 147,753, Nov. 5, 1993, Pat. No. 5,391,147, which is a continuation-in-part of Ser. No. 134,487, Oct. 12, 1993, Pat. No. 5,389,073, which is a continuation of Ser. No. 983,962, Dec. 1, 1992, abandoned. This application Feb. 2, 1995, Ser. No. 382,622

Int. Cl.⁶ A61M 37/00

U.S. Cl. 604—95

5 Claims

1. A steerable catheter comprising a flexible elongate tubular member having proximal and distal extremities, a handle secured



to the proximal extremity of the flexible elongate tubular member, said flexible elongate tubular member having a lumen extending therethrough, a mandrel slidably mounted in the lumen and extending into the distal extremity of the flexible elongate tubular member, means carried by the handle for causing slidable movement of the mandrel to determine the location of a bend to be formed in the distal extremity of the flexible elongate tubular member and operable means accessible from the handle extending through the flexible elongate tubular member for causing bending of the distal extremity of the flexible elongate tubular member with respect to the mandrel slidably mounted on the lumen to form a bend in the desired location in the distal extremity of the flexible elongate tubular member therein.

5,588,965

DEVICE FOR SLOWLY DILATING THE PROSTATIC URETHRA


John H. Burton, and Bradford G. Staehle, both of Minnetonka, Minn., assignors to American Medical Systems, Inc., Minnetonka, Minn.

Filed Mar. 7, 1995, Ser. No. 399,789

Int. Cl.⁶ A61M 29/00

U.S. Cl. 604—101

20 Claims



1. A device for slowly dilating an obstructed portion of a urethra which comprises,
 - a urinary catheter for insertion into the urethra, said catheter having a proximal portion and a distal portion;
 - dilation means capable of expanding radially outwardly, said means being disposed between said proximal and distal portion and having a length of at least that of the obstructed portion of the urethra;
 - pressure responsive means which is capable of sequentially contracting under pressure;
 - conduit means which maintains fluid communication between said pressure responsive means and said dilation means, thereby enabling fluid to flow from said pressure responsive means, when the latter is contracting under pressure, into said dilation means to cause the latter to gradually expand radially outwardly until dilation of the obstructed portion of the urethra occurs to a desired diameter and configuration; and
 - positioning means located on said catheter for positioning said device in the urethra, such that said dilation means is located in the obstructed portion of the urethra.

5,588,966

DEVICE FOR REMOVING A NEEDLE FROM A SYRINGE

Haruo Atsumi, Shizuoka-ken, Japan, assignor to A.C.E. Corporation, Shizuoka-ken, Japan


Filed Jul. 13, 1995, Ser. No. 502,309

Claims priority, application Japan, Jul. 25, 1994, 6-192798

Int. Cl.⁶ A61M 5/00

U.S. Cl. 604—110

4 Claims



1. A device for removing a needle from a syringe, the needle being non-threadedly attached to the syringe, the device comprising a supporting member, a syringe barrel receiving means attached to said supporting member slidably in a direction aligned with a longitudinal axis of the syringe, a first rotatable member having a needle removing means for pushing the needle from the syringe, a second rotatable member having a needle removing means for pushing the needle from the syringe in cooperation with said needle removing means of said first rotatable member, each of said rotatable members being attached to said supporting member so as to have an axis of rotation which is transverse to the longitudinal axis of the syringe, said rotatable members further having a spring means for keeping said rotatable members in contact with a portion of said syringe barrel receiving means and for returning said rotatable members and said syringe barrel receiving means to their original positions.

5,588,967

TISSUE CUTTING DIE


Steven K. Lemp, Santa Barbara; Philip J. Hudak, Burbank, and Charles S. Love, Newbury Park, all of Calif., assignors to Autogenics, Inc., Glasgow, United Kingdom

Continuation of Ser. No. 169,620, Dec. 17, 1993, Pat. No. 5,425,741. This application Apr. 10, 1995, Ser. No. 419,035

Int. Cl.⁶ A61B 17/32

U.S. Cl. 606—167


13 Claims



1. An apparatus for quickly and precisely cutting a piece of autologous, homologous, or heterologous tissue to a desired spatial

configuration, said apparatus applying a consistent cutting force substantially independent of the force applied by the operator so that the tissue is substantially completely and automatically cut along the perimeter of said desired spatial configuration, said apparatus comprising:

- a cover;
- a blade defining the perimeter of the desired spatial configuration, said blade supported by said cover, and means for sequentially forcing segments of a larger piece of said tissue against said blade so that said blade precisely cuts a smaller portion of tissue out of said larger tissue piece by shearing said larger tissue piece substantially along the entire perimeter of said blade.



5,588,968 METHOD FOR CONTROLLING THE BODY TEMPERATURE OF A PATIENT

Andrew L. Sternlicht, 355 Jerusalem Rd., Cohasset, Mass. 02025

Division of Ser. No. 911,897, Jul. 10, 1992, abandoned. This application Sep. 6, 1994, Ser. No. 301,297
Int. Cl.⁶ A61F 7/00

U.S. Cl. 607—107

7 Claims

1. A method for controlling the body temperature of a patient being disposed on a supporting surface and having a perimeter as defined by an outline of the patient on the supporting surface comprising:

- a) positioning an air hose having a plurality of side apertures on the supporting surface so that the air hose extends along at least a portion of the perimeter of the body of the patient;

b) filtering and heating air;

c) supplying the filtered and heated air to the air hose so that at least a portion of the filtered and heated air is dispensed through the apertures adjacent the portion of the perimeter of the body of the patient and

d) positioning a surgical drape over the portion of the body of the patient for retaining a portion of the filtered and heated air dispensed from the air hose adjacent the patient and for maintaining the sterility of a surgical site on the body of the patient.


5,588,969 METHOD FOR SUPPLYING PHOSPHOROUS VAPOR James N. Baillargeon, Springfield, and Alfred Y. Cho, Summit, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Mar. 29, 1995, Ser. No. 412,678

Int. Cl.⁶ B01D 7/00; C01B 25/02

U.S. Cl. 23—294 R

9 Claims



1. A method for supplying phosphorous vapor comprising the steps of:

- heating red phosphorous in a low pressure chamber to produce phosphorous vapor;
- permitting said phosphorous vapor to directly flow into contact with a cooling unit in said low pressure chamber in order to quickly cool said vapor to selectively condense the white allotrope of phosphorous, and
- permitting a flow of phosphorous vapor from said white phosphorous allotrope.


5,588,970 METHOD FOR VACUUM FILLING AND SEALING OF A BATTERY CELL

Elmer Hughett, Rte. 1, Box 151EC, Huntsville, Tenn. 37756, and Richard B. Alexandres, 5193 Lakeview Dr., Clear Lake, Iowa 50428

Continuation-in-part of Ser. No. 271,416, Jul. 6, 1994, Pat. No. 5,532,057. This application Jun. 7, 1995, Ser. No. 484,079
Int. Cl.⁶ H01M 2/04; 2/36

U.S. Cl. 29—623.2

2 Claims



1. A method of sealing and closing an open end of a battery cell casing containing battery components, comprising:

- a. positioning said open end of said battery cell casing in a closing fixture having an evacuation passage and a swage insert;
- b. subjecting said open end of said battery cell casing to a vacuum;
- c. placing a seal into said open end of said battery cell casing;

CHEMICAL

d. swaging said battery cell casing over and about said seal; and
e. removing said battery cell casing from said closing fixture.

5,588,971 CURRENT COLLECTOR DEVICE AND METHOD OF MANUFACTURING SAME


Denis G. Fauteux, Acton; Arthur A. Massucco, Natick; Ronnie D. Wilkins, Melrose, and Jie Shi, Arlington, all of Mass., assignors to Arthur D. Little, Inc., Cambridge, Mass.

Filed Oct. 19, 1994, Ser. No. 325,994

Int. Cl.⁶ H01M 4/04

U.S. Cl. 29—623.5

8 Claims



1. A method of manufacturing an aluminum current collector for use in a lithium electrolytic cell, wherein the aluminum current collector includes an hydrophobic surface layer and a native oxide layer thereon, the method comprising the steps of:

- reducing the native oxide layer from the aluminum current collector to, in turn, lower interfacial impedance of the aluminum current collector;
- converting the hydrophobic surface layer of the aluminum current collector to a surface layer which is hydrophilic;
- chemically etching a plurality of pores in the aluminum current collector;
- precluding re-growth of an oxide layer on the surface of the aluminum current collector by applying, and, in turn, adhering, a primer material suspended in an anhydrous solution to the hydrophilic surface of the aluminum current collector, and evaporating the solvent from the anhydrous solution.

5,588,972 ADDUCTS OF QUINONE COMPOUNDS AND AMINE- CONTAINING POLYMERS FOR USE IN LUBRICATING OILS AND IN FUELS


Abhimanyu O. Patil, Westfield, and Frank Femino, Kearney, both of N.J., assignors to Exxon Chemical Patents Inc., Linden, N.J.

Filed Nov. 23, 1994, Ser. No. 344,775

Int. Cl.⁶ C10L 1/22; C10M 149/14

U.S. Cl. 44—312

20 Claims



1. An oil soluble adduct useful as a fuel additive or lubricating oil additive comprising the reaction product of:
at least one quinone compound having at least one hydrogen on the quinone ring; and

an amine-containing polymer having within its structure at least one reactive amino group selected from the group consisting of primary amino groups, secondary amino groups and mixtures thereof, the amine-containing polymer being derived from a hydrocarbon polymer having a number average molecular weight of from about 700 to 15,000, the amine-containing polymer comprising the acylated amine reaction product of hydrocarbon polymer-substituted mono- or dicarboxylic acid producing material and an amine compound containing at least two reactive amino groups selected from the group consisting of primary amino groups, secondary amino groups, and mixtures thereof.

5,588,973

FUEL COMPOSITIONS CONTAINING A POLYISOBUTENE SUCCINIMIDE DETERGENT

John R. Blackborow, Edinburgh, Scotland, and Michael J. Clarke, Burton Pidsea, England, assignors to BP Chemicals Limited, London, England

Continuation of Ser. No. 40,162, Mar. 30, 1993, abandoned.

This application Jun. 7, 1995, Ser. No. 482,744

Claims priority, application United Kingdom, Apr. 10, 1992, 9208034

Int. Cl.⁶ C10L 1/22

U.S. Cl. 44—347

14 Claims

1. A fuel composition comprising a major amount of a liquid hydrocarbon fuel and, in an amount to provide detergency, a polyisobutene succinimide derived from the reaction of a polyisobutene-substituted succinic acylating agent and an amine having at least one reactive hydrogen bonded to an amine nitrogen wherein the polyisobutene-substituted succinic acylating agent is obtained by a thermal route thus avoiding halogen contamination and the polyisobutene substituent is derived from a highly reactive polyisobutene having greater than 50% of the residual olefinic double bonds represented by the formula $-\text{CH}_2\text{CMe}=\text{CH}_2$.

5,588,974

PROCESS, AND APPARATUS, FOR THE INJECTION OF PREHEATED OXYGEN INTO A HIGH TEMPERATURE REACTOR


Mark L. Tiller; James H. Taylor; Geoffrey R. Say; Norman J. Eger; Lawrence J. Delaune, and Gerald A. Wilcox, all of Baton Rouge, La., assignors to Exxon Research and Engineering Company, Florham Park, N.J.

Filed Apr. 4, 1995, Ser. No. 416,622

Int. Cl.⁶ B01J 8/18

U.S. Cl. 48—127.9

14 Claims



1. In a fluidized bed reaction vessel constituted of walls enclosing a reaction chamber, with outlets, and inlets for the introduction

of a low molecular weight hydrocarbon feed, steam, and oxygen, or a low molecular weight hydrocarbon feed and oxygen, for reaction at temperatures ranging from about 1500° F. to about 2500° F., or higher, to produce hydrogen and carbon monoxide the improved combination comprising

a nozzle inlet, or nozzle inlets, into the reactor through which high purity preheated oxygen can be introduced into the reaction chamber which comprises

a tubular body constituted of an alloy sufficient to withstand the oxidizing heat of the preheated oxygen without igniting and burning the alloy composition, the axial opening providing an inlet for introducing the preheated oxygen, and an oxygen outlet.

a plurality of small diameter tubes smaller than the axial opening, constituted of an alloy composition as defined by that of which said tubular body is constituted, communicated with said oxygen outlet, disposed upon the tubular body, and inclined downwardly at an angle, as measured from a line perpendicular to the axial opening through the tubular body, ranging from about 15° to about 60°.

refractory sleeves concentrically fitted upon the small diameter tubes such that a terminal end thereof projects outwardly beyond the terminal end of a small diameter tube a distance, d, which is at least equal to the inside diameter of a small diameter tube, sufficient to suppress ignition, burning or weakening of the alloy by the high temperature, and solids formation at the tips of the small diameter tubes, and an encapsulating refractory which surrounds the tubular body, plurality of small diameter tubes, and refractory sleeves to protect the nozzle against the intense heats of reaction, while the low molecular weight hydrocarbon feed and steam, or low molecular weight hydrocarbon feed, is fed into the reaction chamber via a different nozzle inlet.

5,588,975

COATED GRINDING TOOL


Mark S. Hammond, Houston, Tex., and Joseph D. Evans, Lafayette, Colo., assignors to SI Diamond Technology, Inc., Austin, Tex.

Filed May 25, 1995, Ser. No. 452,572

Int. Cl.⁶ B24D 5/00;3/06

U.S. Cl. 51—293

12 Claims



8. A method for manufacturing a grinding tool having a working surface comprised of a composite material, the composite material comprised of hard particles and a metal or metal alloy bonding material, said method comprising:

placing the working surface in a vacuum chamber with at least two cathodes of different transition metals; introducing a reactive gas at a controlled pressure and concentration into the chamber; and striking arcs with the cathodes while moving said working surface and to deposit a modulated composition of reaction products of the transition metals and the reactive gas on the working surface.

5,588,976

AIR FILTRATION MEDIA

Donald L. Miller, Defiance, Ohio, assignor to Schuller International, Inc., Denver, Colo.

Division of Ser. No. 168,746, Dec. 16, 1993, Pat. No.

5,454,848, which is a continuation-in-part of Ser. No. 40,783, May 19, 1993, abandoned. This application Jun. 8, 1995, Ser.

No. 488,984

Int. Cl.⁶ B01D 46/00

U.S. Cl. 55—514

2 Claims

1. A fiber glass air filtration media consisting essentially of: a blanket of glass fibers wherein about 25% to 35% by weight of the glass fibers are fine glass fibers having an average diameter between 1 and 3 microns and about 65% to 75% by weight of the glass fibers are coarse glass fibers having an average diameter between 4 and 6.5 microns, the fine glass fibers and the coarse glass fibers being randomly intermingled in the blanket, the fine glass fibers and the coarse glass fibers being adhesively bonded together in the blanket with a binder, the blanket having a thickness ranging from about 0.11 to about 1.50 inches, the blanket having a density between about 0.4 and about 1 pounds per cubic foot, and a porous, air permeable, backing mat adhesively bonded to one surface of the blanket by the binder.

5,588,977

METHOD OF PRODUCING GLASS MATERIALS FROM ASH-SLAG WASTE


Vyacheslav F. Pavlov; Vasily F. Shabanov; Alexandr G. Anshits, and Sergei G. Bayakin, all of Krasnoyarsk, Russian Federation, assignors to East West Trade Group, Inc., Alexandria, Va.

Continuation-in-part of Ser. No. 144,476, Nov. 2, 1993, abandoned. This application Jun. 6, 1995, Ser. No. 467,638

Int. Cl.⁶ C03B 19/08

U.S. Cl. 65—17.4

11 Claims



1. A method of producing foamed glass materials from ash-slag waste derived from burning coals comprising the steps of:

a) providing a charge of the ash-slag waste including calcium oxide and iron oxide in the following amounts of wt %:

CaO total	5.0-41.0
CaO unbound	4.0-13.0
Fe ₂ O ₃	1.0-24.0

b) heating and melting the charge; and
c) forming said foamed glass material by pouring said melted charge into a water bath;
d) wherein, prior to said heating and melting of the charge, a carbon content of the charge is adjusted to an amount effective to reduce the Fe₂O₃ content of the charge to less than 1% by weight and to form carbides in said melt whereby a gaseous medium is generated from the carbides to foam said melt to produce the foamed glass materials.

5,588,978

PROCESS AND APPARATUS FOR COLORING GLASS


Ronald D. Argent, Green County, Pa., and James A. Bolin, Tulsa County, Okla., assignors to IMTEC, Tulsa, Okla.

Continuation-in-part of Ser. No. 981,854, Nov. 24, 1992, abandoned. This application May 19, 1994, Ser. No. 246,064

Int. Cl.⁶ C03B 5/16;5/18;5/24;7/00

U.S. Cl. 65—29.1

16 Claims



1. Apparatus for coloring glass in the manufacture of glassware articles comprising:

at least one transport channel adapted to receive molten glass from a glass melting furnace;

a color treatment chamber having a floor, a charging end and an outlet end, joined by opposed side walls enclosed by a roof and defining a horizontally extending glass containment region therein, said chamber further having an inlet formed therein for receiving molten glass from said at least one transport channel;

means for abetting a flow of molten glass in said at least one transport channel;

charger means at a charger end of said color treatment chamber for introducing cullet and a color additive into the said containment region in said color treatment chamber;

heater means associated with said color treatment chamber to melt said cullet supplied to said containment region of said color treatment chamber and to further heat the molten glass and color additive to form a molten bath of colored glass in said containment region;

means associated with said containment region of said color treatment chamber for homogenizing the color and temperature of the molten bath of colored glass in said containment region; and

a distribution channel positioned and arranged at said outlet end of said color treatment chamber communicating with said containment region of said color treatment chamber for delivery of said molten colored glass to at least one remotely located glassware forming machine and positioned and arranged at an outlet of said glass melting furnace and at an inlet of said at least one transport channel to receive molten glass from said glass melting furnace and to supply said molten glass from said glass melting furnace to said at least one transport channel and to said at least one remotely located glassware forming machine.

the means for abetting a flow of molten glass in said at least one transport channel comprising a paddle wheel rotatably mounted in said at least one transport channel, a variable speed drive means operatively connected with said paddle wheel for rotating said paddle wheel, said paddle wheel having a plurality of radially extending vanes for engagement with molten glass in said at least one transport channel, and a sensor and control means for determining a level of glass in said distribution channel and for regulating said variable speed drive means to selectively increase or decrease the speed of rotation of said paddle wheel in response to a predetermined glass level.


5,588,979

APPARATUS FOR CONTINUOUSLY FORMING AND PROCESSING A GLASS-CERAMIC Mutsumi Miyazaki, and Toshiaki Yoshida, both of Sagami-hara, Japan, assignors to Kabushiki Kaisya Ohara, Kanagawa-Ken, Japan

Continuation-in-part of Ser. No. 175,960, Dec. 30, 1993, abandoned. This application Jan. 11, 1995, Ser. No. 371,387
 Claims priority, application Japan, Nov. 8, 1993, 5-278165
 Int. Cl.⁶ C03B 11/00

U.S. Cl. 65—164

6 Claims



1. An apparatus for continuously forming and processing a glass-ceramic comprising:
 - melting means for melting raw materials for a glass-ceramic into a melted glass;
 - a flow tube for conveying the melted glass flowing out of the melting means, said flow tube having a melted glass inlet and a melted glass outlet, inclining downwardly toward the melted glass outlet and having an inner diameter which becomes smaller toward the melted glass outlet, a cross section of said melted glass inlet being larger than a cross section of said melted glass outlet;
 - flow quantity control means connected to said flow tube for controlling the quantity of said melted glass flowing through said flow tube;
 - press means provided in a posterior stage to said flow tube for pressing the melted glass from the flow tube into a predetermined form;
 - glass preform checking means provided for measuring the weight or volume of a glass preform provided by the pressing means and for feeding back a difference signal corresponding to a difference between the measured value of the weight or volume and a reference value of the weight or volume to the flow quantity control means, said flow quantity control means controlling the quantity of the melted glass flowing through the flow tube in response to the difference signal to reduce the difference between the measured value and the reference value; and
 - crystallizing means provided in a posterior stage to the glass preform checking means for crystallizing the glass preform.

5,588,980


APPARATUS FOR MOLDING A GLASS OPTICAL ELEMENT WITH A TRANSPORTING SUPPORTING MEMBER

Hiroshi Ito, Hachiohji, Japan, assignor to Olympus Optical Co., Ltd., Japan
 Division of Ser. No. 20,649, Feb. 22, 1993, Pat. No. 5,378,255.
 This application Sep. 15, 1994, Ser. No. 306,462
 Claims priority, application Japan, Feb. 21, 1992, 4-072434
 Int. Cl.⁶ C03B 11/00

U.S. Cl. 65—223

18 Claims

1. An apparatus for molding an optical element from molten glass, comprising:
 - a glass ejection chamber including a receiving mold part having an end surface for receiving the molten glass, the end surface having a shape that substantially conforms to one of two major surfaces of the optical element, and a supporting member having an opening so as to expose the end surface of the receiving mold part when the supporting member is detachably mounted on the receiving mold part for receiving a desired amount of molten glass;



- a heating chamber connected to the glass ejection chamber for heating the glass, the heating chamber having a heating furnace for receiving the glass from the glass ejection chamber while the glass is separated from the receiving mold part and is supported on the supporting member;
- a precision press chamber connected to the heating chamber for receiving the heated glass supported on the supporting member from the heating chamber and for molding the glass into the optical element, the precision press chamber including a pair of mold parts having molding surfaces each having a shape that substantially conforms to a respective one of the two major surfaces of the optical element; and
- transport means movable into the glass ejection chamber, the heating chamber and the precision press chamber for transporting the supporting member.


5,588,981

APPARATUS FOR FORMING WIDE MOUTH GLASSWARE

Wayne E. Eilers, Perrysburg, Ohio, assignor to Owens-Brockway Glass Container Inc., Toledo, Ohio
 Filed Jul. 28, 1994, Ser. No. 281,718
 Int. Cl.⁶ C03B 9/193

U.S. Cl. 65—241

23 Claims



1. An apparatus for making wide-mouth glassware comprising
 - a solid blank mold,
 - a split blow mold comprising mold halves,
 - a split neck ring,
 - a plunger carrier having a movable plunger therein,
 - means for positioning the neck ring on said blank mold,
 - means for delivering a gob of glass to said blank mold,
 - means for positioning said plunger carrier into engagement with said neck ring such that the plunger extends into the blank mold to a first position,
 - said plunger carrier including means for extending the plunger further into said blank mold to a first position to deform the glass and force the glass into the neck ring to form a parison, and retracting the plunger and moving the plunger carrier away from the neck ring,
 - means for moving the neck ring with the parison thereon to a position between the open blow mold halves while maintaining the parison in vertical upright position and returning the

5,588,983

PRODUCTION OF COPPER POWDER

Hiroji Tanii, and Kazuhito Oshita, both of Nagaokakyo, Japan, assignors to Murata Manufacturing Co., Ltd., Japan
 Filed Feb. 16, 1995, Ser. No. 389,285
 Claims priority, application Japan, Feb. 16, 1994, 6-019196
 Int. Cl.⁶ B22F 9/04

U.S. Cl. 75—354

7 Claims

1. A method for producing copper powder comprising the steps of:
 - providing a mixture consisting of copper powder and 0.1 to 3 wt % stearic acid; and
 - ball milling said mixture until the copper powder has formed a fine powder with a particle size range from 0.3 to 7 microns.

5,588,984

APPARATUS AND METHOD TO INTERMITTENTLY MANUFACTURE AND DISPENSE NITROGEN


Nicholas A. Verini, 404 Lone Eagle Point, Lafayette, Colo. 80026

Filed Jul. 18, 1995, Ser. No. 503,596

Int. Cl.⁶ B01D 53/22

U.S. Cl. 95—15

19 Claims



1. A method for intermittent and automatic separating and storing nitrogen from air comprising the steps of:
 - (a) compressing and introducing said air into a module containing a permeable membrane means for separating said nitrogen from said air,
 - (b) said permeable membrane means separating said nitrogen from said air permitting oxygen, carbon dioxide, moisture and other gases to pass through said membrane means while enriching said nitrogen to a desired purity by removing other air components,
 - (c) providing an automatic means for controlling nitrogen pressure in said module,
 - (d) providing a means for containing and controlling the temperature of said air, said nitrogen, and said module,
 - (e) storing said nitrogen for intermittent discharge,
 - (f) providing a means for automatically controlling and discharging desired amounts of said nitrogen and,
 - (g) providing conduit to contain said air and said nitrogen in said apparatus when necessary until discharge.

5,588,985

METHODS OF USING A PORTABLE FILTRATION UNIT David M. Shagott, Duluth; Gary E. Kruse, Lawrenceville, both of Ga.; Blair L. Harber, Jr.; Daniel N. Sutherland, both of Ontario, Canada, and Terrell F. Travis, Oxford, Miss., assignors to Abatement Technologies, Inc., Lawrenceville, Ga.

Continuation-in-part of Ser. No. 97,753, Jul. 26, 1993, Pat. No. 5,433,763, which is a continuation-in-part of Ser. No. 766,000, Sep. 26, 1991, Pat. No. 5,230,723, which is a continuation-in-part of Ser. No. 613,212, Nov. 14, 1990, Pat. No. 5,069,691. This application Apr. 6, 1995, Ser. No. 418,249
 Int. Cl.⁶ B01D 35/143

U.S. Cl. 95—25

9 Claims

1. A method of cleaning HVAC ductwork containing fluid and particles comprising the steps of:

- neck ring to its original position adjacent the blank mold while the parison is being blown,
- means for opening the neck ring to release the parison in the blow mold,
- means for closing the blow mold about the parison and blowing the parison into a hollow glass article,
- said plunger extending from said plunger carrier such that the plunger begins to press glass as the plunger carrier moves into engagement with said neck ring,
- said plunger carrier including means for aligning the plunger carrier with said neck ring,
- said plunger carrier including means yieldingly engaging said neck ring,
- a neck ring arm, means pivoting said neck ring arm about a first fixed horizontal axis, a neck ring holder for holding said neck ring, means pivotally supporting said neck ring holder on said neck ring arm,
- means for moving said blank mold upwardly into position for receiving the glass gob,
- said means for moving the neck ring with the parison thereon to a position between the open blow mold halves while maintaining the parison in vertical upright position comprising a transfer arm, means pivoting one end of the transfer arm about a second fixed horizontal axis spaced from the first horizontal axis, means pivoting the other end of the transfer arm to the neck ring holder, means pivotally connecting said transfer arm to said first horizontal axis such that the pivotal movement of said neck ring arm about said first horizontal axis causes said transfer arm to move about said second horizontal axis and maintain said parison in vertical upright position as the neck ring is moved to a position between the open blow mold.

5,588,982

PROCESS FOR PRODUCING FOUNDRY IRON


Charles F. Hendrix, Pell City, Ala., assignor to Alabama Power Company, Birmingham, Ala.

Filed May 1, 1995, Ser. No. 431,845


Int. Cl.⁶ C21B 11/10

U.S. Cl. 75—10.50

34 Claims



1. A process of producing foundry iron comprising the steps of:
 - feeding a charge into a submerged arc furnace about electrodes thereof, said charge comprising a mixture of an iron source, a silicon source and a carbonaceous reducing agent, said iron source comprising scrap iron or steel,
 - supplying electrical energy to said electrodes to generate an electrical arc therebetween, and
 - heating the scrap iron or steel, the silicon source and the carbonaceous reducing agent in the furnace by the electrical arc between the electrodes to melt the scrap iron or steel and to produce foundry iron having a silicon content of about 0.05 percent to about 9.5 percent by weight.



- transporting to a site first and second modular assemblies, each having an inlet, an outlet, a surface, and a plurality of sides;
- placing the outlet of the first modular assembly in fluid communication with the inlet of the second modular assembly;
- detachably rigidly sealing the first modular assembly to the second modular assembly in fluid communication therewith to form a housing having a length and width and comprising:
 - a filtration system comprising:
 - a first filter; and
 - a HEPA filter;
 - means for maintaining the first filter within the housing between the inlet of the first modular assembly and the HEPA filter so as to encounter fluid entering the inlet before the fluid encounters the HEPA filter;
 - means, comprising a motor, for drawing a substantial volume of fluid through the filtration system;
 - an external control panel comprising means for indicating any substantial disruption of fluid flow through the filtration system;
 - a plurality of external wheels; and
 - external means, protruding from the housing intermediate the external wheels and providing a bearing surface when the housing is tilted, for facilitating conveying the housing up and down stairs;
- attaching one end of a length of hose to the HVAC ductwork and the other end to a rim connected to the surface and circumscribing the inlet of the first modular assembly;
- connecting the drawing means to a source of electricity, thereby:
 - causing fluid and particles within the HVAC ductwork to enter the length of hose and the inlet of the first modular assembly;
 - drawing the fluid having entered the inlet of the first modular assembly through the first filter to remove and retain therein a portion of the particles;
 - thereafter drawing the fluid and at least some of the remaining particles through the HEPA filter to remove and retain therein a substantial portion of the remaining particles;
 - exhausting the fluid through the outlet of the second modular assembly;
 - rendering operational the means for indicating any substantial disruption of fluid flow through the filtration system; and
- tilting the housing so that any stairs present at the site bear against the bearing surface of the external conveyance-facilitating means as the housing is transported up and down the stairs.

5,588,986
MASS OR ENERGY TRANSFER PROCESS USING FLUIDIZED BED
 Howard P. Davis, Petersham Richmond, England, and Wolfram Ruff, Stade, Germany, assignors to Euro-Matic Ltd., London, England, and VAW Aluminium AG, Bono, Germany
 Continuation-in-part of Ser. No. 76,481, Jun. 14, 1993, Pat. No. 5,376,165, which is a continuation of Ser. No. 767,043, Aug. 2, 1991, abandoned. This application Dec. 27, 1994, Ser. No. 364,220

Int. Cl.⁶ B01D 47/14; 53/14

U.S. Cl. 95—211

33 Claims

1. A method for performing a process selected from the group consisting of scrubbing, stripping, or heat transfer, wherein a gas stream is flowed through a column having a bed comprising fluidizable hollow packing elements, and a liquid stream is flowed through in a direction countercurrent to said gas stream into said column, said liquid stream having a liquid flow L and said gas stream having a gas flow G sufficient to maintain said bed in a fluidized state and a superficial gas velocity v ; comprising

- selecting an unknown value selected from the group consisting of L/G , v , ρ_p , ψ , s , ρ_g and ρ_L so that the following equation is satisfied for a predetermined value of $\Delta P/H_0$ greater than 1300 Pa/m^3 :

$$\frac{\Delta P}{H_0} = v \left\{ \frac{C_1 \rho_p R}{\psi s} + \frac{C_2 \rho_g R}{\psi} + C_3 \rho_L R \left[\frac{L}{G} \right] \right\}$$

wherein

ΔP is the pressure drop across the bed;

H_0 is the bed height in a state of rest;

C_1 is a numerical constant;

C_2 is a numerical system constant having units of seconds/meter or equivalent;

C_3 is a system constant having units of seconds/meter;

s is an element slip function in units of meters/second or equivalent;

ψ is a shape factor calculated as follows:

ψ/x , wherein x is the length of the short axis of the packing elements and y is the length of the long axis of the packing elements;

ρ_p is the density of the packing elements;

ρ_g is the density of the gas;

ρ_L is the density of the liquid;

g is the gravitational constant; and

(b) carrying out said process in accordance with said selection.

5,588,987
DISCHARGE STREAM CONDITIONER AND METHOD
 Paul O. Huston, 220 Snake Hill Rd., Trussville, Ala. 35173
 Filed Oct. 14, 1994, Ser. No. 321,840
 Int. Cl.⁶ B01D 19/00


U.S. Cl. 95—260

12 Claims

1. A discharge stream conditioner positioned in a pressurized liquid containment vessel comprising a tank filled with pressurized liquid, a syphon tube extending into said liquid, a valve means and a discharge means, said discharge stream conditioner being frictionally positioned within said syphon tube and comprising an elongated rod having a plurality of radiating, cambered, fingers attached thereto and extending outwardly therefrom and arranged in a repetitive, continuous spiral beginning at one end of said rod and continuing uninterrupted toward the opposite end of said rod so that at least a portion of said fingers are caused to frictionally engage the interior wall of said syphon tube.

11. A method of effectuating a partial separation of gas molecules dissolved in a liquid under pressure during discharge of said liquid from a pressurized liquid containment vessel having a tank filled with said liquid, a syphon tube, a valve means and a discharge means, said method comprising the steps of:

frictionally inserting an elongated rod having a plurality of radiating, cambered, fingers attached thereto and extending




outwardly therefrom into said syphon tube and the discharge flow path of said liquid and arranged in a repetitive, continuous spiral beginning at one end of said rod and continuing uninterrupted toward the opposite end of said rod so that at least a portion of said fingers are caused to frictionally engage the interior wall of said syphon tube; and, causing said liquid to flow or be discharged from said liquid containment vessel through said syphon tube and over and along the longitudinal axis of said rod and through said radiating fingers.

5,588,988
THERMAL DESORPTION DEVICE FOR A GAS CHROMATOGRAPH
 Eberhard Gerstel, An der Halde 49, 45475 Mulheim/Ruhr, and Ralf Bremer, Witthausstr. 29, 45470 Mulheim/Ruhr, both of Germany
 Filed Jun. 5, 1995, Ser. No. 461,869
 Claims priority, application Germany, Jun. 3, 1994, 44 19 596.6

Int. Cl.⁶ B01D 15/08

U.S. Cl. 96—101

11 Claims



1. A thermal desorption device for a gas chromatograph comprising: an oven; a holding chamber having an open receiving portion; an interchangeable sample holder tube, having a first end and a second end, receivable by said holding chamber;

a sample holder tube holder piece for engagement with said receiving portion of said holding chamber and having a proximal and a distal end, said distal end including a recess for placement of said first end of said sample holder tube; a first seal near said proximal end of said holder piece, for externally sealing said holding chamber; a second seal near said distal end of said holder piece; a first annular gap located around that portion of said holder piece between said first and second seals; a carrier gas connection opening in the region of said first annular gap; a third seal in said recess surrounding said sample holder tube at a point near said distal end of said holder piece, forming a seal between said sample holder tube and said holder piece; a second gap surrounding said first end of said sample holder tube up to said third seal; a connection through said holder piece between said first and second gaps; and a trap communication with the interior of said sample holder tube at said second end.

5,588,989
ZINC PHOSPHATE COATING COMPOSITIONS CONTAINING OXIME ACCELERATORS
 Donald R. Vonk, Clinton Township, and Jeffrey A. Greene, Ferndale, both of Mich., assignors to PPG Industries, Inc., Pittsburgh, Pa.
 Filed Nov. 23, 1994, Ser. No. 344,441

Int. Cl.⁶ C23C 22/07

33 Claims

1. An aqueous acidic composition for forming a zinc phosphate coating on a metal substrate comprising about 0.4 to 3.0 grams per liter (g/l) of zinc ion, about 5 to 20 g/l phosphate ion, and as an accelerator, about 0.5 to 20 g/l of an oxime.

5,588,990
POZZOLAN CEMENT COMPOSITIONS AND ADMIXTURES THEREFOR
 Jonathan E. Dongell, Scottsdale, Ariz., assignor to Universal Cement & Concrete Products, Inc., Glendale, Ariz.
 Filed Nov. 3, 1995, Ser. No. 552,635
 Int. Cl.⁶ C04B 22/06

U.S. Cl. 106—716

30 Claims

1. An admixture for subsequent addition to cement to create a blended cement, said blended cement having from about 15% to about 40% (w/w) of said admixture blended therein, said admixture comprising: from about 12.5% to about 67% (w/w) of calcined diatomaceous earth; from about 17.5% to about 67% (w/w) of calcined kaolin; from about 0% to about 22.5% (w/w) of talc; from about 0% to about 20% (w/w) of bentonite; and sufficient potassium to provide the blended cement with about 0.5% to about 4% (w/w) potassium.


5,588,991
PROCESS FOR PRODUCING CHLOROGALLIUM PHTHALOCYANINE CRYSTAL
 Kazuya Hongo, and Hitoshi Takimoto, both of Minami Ashigara, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan
 Filed Aug. 29, 1995, Ser. No. 521,042
 Claims priority, application Japan, Aug. 31, 1994, 6-229063; Feb. 21, 1995, 7-055234

Int. Cl.⁶ C30B 3/00

U.S. Cl. 117—2

5 Claims

1. A process for producing a chlorogallium phthalocyanine crystal, which comprises mechanically dry-grinding chlorogallium phthalocyanine with a grinding media to produce a crystal-converted chlorogallium phthalocyanine crystal, wherein the weight ratio of said chlorogallium phthalocyanine to said grinding media is from 1/5 to 1/1000.



5,588,992

CONVERSION OF DOPED POLYCRYSTALLINE MATERIAL TO SINGLE CRYSTAL MATERIAL


Curtis E. Scott, Mentor; Mary Sue Kaliszewski, Cleveland Heights, both of Ohio, and Lionel M. Levinson, Schenectady, N.Y., assignors to General Electric Company, Schenectady, N.Y.

Division of Ser. No. 195,187, Feb. 14, 1994, Pat. No. 5,487,353. This application Nov. 3, 1995, Ser. No. 552,700

Int. Cl.⁶ C30B 1/06

U.S. Cl. 117—2

14 Claims



1. A solid state process for converting a polycrystalline ceramic body doped with a selected conversion-enhancing dopant at a selected concentration to a single crystal body comprising the steps of:

- doping at least a portion of the polycrystalline ceramic material comprising said ceramic body with a conversion-enhancing dopant to a selected concentration; and
- heating the doped polycrystalline body to a selected temperature to convert the portion of the polycrystalline body doped to said selected concentration to a single crystal structure, said selected temperature being above one-half of the melting temperature of said doped ceramic material but below the melting temperature of said doped ceramic material.

5,588,993

METHOD FOR PREPARING MOLTEN SILICON MELT FROM POLYCRYSTALLINE SILICON CHARGE

John D. Holder, Lake St. Louis, Mo., assignor to MEMC Electronic Materials, Inc.


Filed Jul. 25, 1995, Ser. No. 507,055

Int. Cl.⁶ C30B 15/02

U.S. Cl. 117—13

40 Claims

1. A process for preparing a pool of molten silicon in a crucible for use in growing a single crystal silicon ingot by the Czochralski method, the process comprising:



- (a) forming a partially melted charge in a crucible, the partially melted charge comprising molten silicon having an upper surface and unmelted polycrystalline silicon exposed above the upper surface of the molten silicon;
- (b) feeding polycrystalline silicon onto the exposed unmelted polycrystalline silicon; and
- (c) melting the unmelted polycrystalline silicon and the polycrystalline silicon fed onto the exposed unmelted polycrystalline silicon to form a pool of molten silicon.

5,588,994


METHOD OF PRODUCING SHEETS OF CRYSTALLINE MATERIAL AND DEVICES MADE THEREFROM

Carl O. Bozler, Sudbury; John C. C. Fan, Chestnut Hill, and Robert W. McClelland, Norwell, all of Mass., assignors to Massachusetts Institute of Technology, Cambridge, Mass. Continuation of Ser. No. 291,389, Aug. 16, 1994, which is a continuation of Ser. No. 31,536, Mar. 15, 1993, Pat. No. 5,362,682, which is a continuation of Ser. No. 770,599, Oct. 3, 1991, abandoned, which is a continuation of Ser. No. 128,637, Dec. 4, 1987, abandoned, which is a continuation of Ser. No. 251,214, Apr. 6, 1981, Pat. No. 4,727,047, which is a continuation-in-part of Ser. No. 138,891, Apr. 10, 1980, abandoned. This application Jun. 6, 1995, Ser. No. 468,530 The portion of the term of this patent subsequent to Feb. 23, 2005, has been disclaimed.

Int. Cl.⁶ C30B 29/06

U.S. Cl. 117—89

26 Claims



- 1. An electronic device comprising: a substrate for supporting the electronic device;
- a first thin-film layer of semiconductor material, a second thin-film layer of semiconductor material, and a third thin-film layer of semiconductor material, each layer of semiconductor material comprising a respective electronic circuit having a thickness of about 10 microns or less; and
- two layers of adhesive material, a first layer of adhesive material being between the first thin-film layer and the second thin-film layer of semiconductor material to attach the first and second thin-film layers of semiconductor material together to form a circuit structure and a second layer of adhesive material to attach the circuit structure to the third thin-film layer of semiconductor material to form the electronic device.

5,588,995

SYSTEM FOR MONITORING THE GROWTH OF CRYSTALLINE FILMS ON STATIONARY SUBSTRATES

Peter Sheldon, Lakewood, Colo., assignor to Midwest Research Institute, Kansas City, Mich.


Division of Ser. No. 69,405, Jun. 1, 1993, Pat. No. 5,456,205.

This application May 3, 1995, Ser. No. 434,181

Int. Cl.⁶ C30B 25/16

U.S. Cl. 117—201

21 Claims



1. A monitoring apparatus for detecting intensity oscillations of a RHEED luminescent pattern on a screen that luminesces in response to impingement of electrons generated by an electron beam during growth of a crystalline film on a substrate, comprising:

- focusing means for selecting a spot of the RHEED luminescent pattern on the screen at which luminescent intensity can be detected;
- detector means for converting light emanating from said spot into an electronic signal indicative in real time of the luminescent intensity;
- filter means for transmitting primarily light of the wavelength that are produced by the screen and that reflects or absorbs light of different wavelengths;
- amplifying means for amplifying said electronic signal;
- processing means for reading each oscillation cycle of intensity of the luminescent spot;
- rotating means for rotating said substrate and crystalline film; and
- sampling means for sampling said electrical signal instantaneously in synchronization with a revolution of said substrate and crystalline film.

5,588,996

APPARATUS FOR SPRAY COATING FLAT SURFACES


Bernard J. Costello, Princeton, N.J., assignor to Argus International, Ringoes, N.J.

Filed Apr. 1, 1994, Ser. No. 222,125

Int. Cl.⁶ B05C 11/00

U.S. Cl. 118—668

34 Claims



1. Apparatus for coating workpieces comprising: conveyor means for conveying workpieces in a given direction;

means for moving said conveyor means including means for adjusting the moving speed of said conveyor means; a spray assembly including a spray head for producing a liquid spray in a given pattern; means for delivering a coating liquid to said spray assembly; means for reciprocally mounting said spray assembly above said conveyor means to deliver a liquid spray from said spray head downwardly toward an upper surface of a workpiece arranged on the conveyor means, said spray assembly being movable in a reciprocating fashion along a path transverse to said given direction; means for reciprocating said spray assembly as said conveyor means is moving workpieces beneath said spray assembly and said spray assembly emits a spray of coating liquid; means for adjusting the moving speed of said reciprocating means; and means for adjusting outer limits of reciprocating movement of the spray assembly along said transverse path according to size and/or arrangement of workpieces on the conveyor means to maximize efficient use of spray liquid and reduce waste thereof as well as facilitating setup changes of said apparatus to accommodate different coating thicknesses and workpieces of differing sizes.

5,588,997

DEVICE FOR COATING AN OPTICAL FIBER

Hans-Jürgen Lysson, Korschenbroich; Reiner Broden, and Hans-Detlef Leppert, both of Mönchengladbach, all of Germany, assignors to Kabel Rheydt AG, Monchen-Gladbach, Germany


Filed Nov. 17, 1994, Ser. No. 341,477

Claims priority, application Germany, Nov. 18, 1993, 9317617 U

Int. Cl.⁶ B05C 3/02

U.S. Cl. 118—405

13 Claims



1. A device for coating an optical fiber, comprising a housing having a lengthwise bore; a nozzle holder, which is located in said lengthwise bore, said nozzle holder having a receiving aperture formed therein; an inlet nozzle, having a first nozzle bore, received in one end of said receiving aperture; an outlet nozzle, having a second nozzle bore, received in an opposite end of said receiving aperture; said inlet nozzle and said outlet nozzle being arranged at a distance from one another with said first nozzle bore and said second nozzle bore being axially aligned such that an optical fiber can pass therethrough in a passage direction; wherein a coating material is applied to the optical fiber while passing between said inlet nozzle and said outlet nozzle; wherein the nozzle holder is press-fit into said lengthwise bore of said housing; wherein said inlet nozzle and said outlet nozzle are press-fit into said receiving aperture of said nozzle holder; and wherein said nozzle holder is made of a flexible plastic material having a low coefficient of friction, said material having a low

coefficient of friction simplifying the press-fit of said inlet and outlet nozzles into said receiving aperture of said nozzle holder, and said material having a low coefficient of friction providing a seal in a radial direction between said inlet and outlet nozzles and said nozzle holder to thereby prevent the passage of said coating material therebetween.


5,588,998

JET COATING APPARATUS

Jukka Koskinen, Helsinki, Finland, assignor to Valmet Corporation, Helsinki, Finland
Continuation-in-part of Ser. No. 142,728, Oct. 25, 1993, abandoned. This application Jun. 26, 1995, Ser. No. 494,365
Claims priority, application Finland, Oct. 26, 1992, 924841
Int. Cl.⁶ B05C 5/00

U.S. Cl. 118—410

6 Claims



1. A jet coating apparatus for applying coating mix into a moving web in a noncontacting manner in ambient pressure without a pressurized coating chamber, said apparatus comprising:
an upper lip placed close to the web and having a slot orifice bounding surface; and
a lower lip situated in the vicinity of the upper lip and having a slot orifice bounding surface, the lower lip being arranged essentially on a trailing side relative to the moving direction of the web so that the slot orifice bounding surface of the upper lip and the slot orifice bounding surface of the lower lip form a slot orifice suited for feeding the coating mix onto the web without a pressurized chamber, the slot orifice bounding surface moving direction of the web.


5,588,999

THIN FILM FORMING DEVICE

Hiroshi Takahashi, Ibaraki-ken, Japan, assignor to Elko Engineering Co., Ltd., Ibaraki-ken, Japan
Filed Aug. 9, 1995, Ser. No. 513,153
Claims priority, application Japan, Jan. 17, 1995, 7-023543
Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—715

7 Claims



1. A thin film forming device comprising:
a vacuum chamber which is vacuum inside;

a substrate holder provided in said vacuum chamber for holding a substrate;
an irradiation source of thin film material disposed in said vacuum chamber towards said substrate holder; and
an endoscope having a tip portion inserted close to a film-forming surface of said substrate in said vacuum chamber, said endoscope being disposed in a transparent protecting tube which separates said endoscope from an inner space of said vacuum chamber.


5,589,000

FIXTURE FOR DEPOSITION

Michael R. Harms, Woodbury; Richard J. Foss, Pine City; Jennifer L. Trice, Eagan, and Terence D. Neavin, St. Paul, all of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.
Filed Sep. 6, 1995, Ser. No. 524,340
Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—715

21 Claims



1. A fixture for use in deposition of a material over a substrate, the fixture comprising:
a first plate having a first side and a second side;
a second plate having a first side and a second side, wherein the first side of the second plate faces the first side of the first plate, the second side of the second plate supporting the substrate during deposition of the material over the substrate;
a plurality of thermoelectric devices disposed between the first plate and the second plate, the thermoelectric devices being in thermal communication with both the first plate and the second plate; and
a device for controlling each of the thermoelectric devices to generate thermal energy during deposition of the material over the substrate.
wherein a portion of the thermal energy is transferred to the substrate by the second plate and a portion of the thermal energy is transferred away from the thermoelectric devices by the first plate.

5,589,001

APPARATUS FOR FORMING A FILM ON A WAFER

Kazuo Maeda; Kouichi Ohira, and Hiroshi Chino, all of Tokyo, Japan, assignors to Canon Sales Co., Inc.; Alcan-Tech Co., Inc., and Semiconductor Process Laboratory Co., Ltd., all of Japan
Filed Nov. 30, 1993, Ser. No. 159,127
Claims priority, application Japan, Nov. 30, 1992, 4-320504
Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—722

8 Claims

1. An apparatus for forming a film on a wafer substrate comprising:
a rotary shaft;
a gas distributor, for discharging a reaction gas, including a plurality of gas dischargers arranged in a circle around said rotary shaft;


5,589,003

SHIELDED SUBSTRATE SUPPORT FOR PROCESSING CHAMBER


Jun Zhao, Cupertino; Frank P. Chang, San Jose, and Charles N. Dornfest, Fremont, all of Calif., assignors to Applied Materials, Inc., Santa Clara, Calif.
Filed Feb. 9, 1996, Ser. No. 599,015
Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—728

24 Claims



a wafer holder mounted on said rotary shaft for rotation relative to said gas distributor and including a plurality of wafer mounting surfaces arranged in a circle around said rotary shaft, said wafer mounting surfaces facing said gas dischargers;
vertical positioning means for moving either said gas distributor or said wafer holder between a first position where said wafer holder and said gas distributor are in a spaced, facing relationship for discharge of the reaction gas onto a wafer substrate and a second position where said wafer holder and said gas distributor are spaced further apart than in said first position;
cleaning means for cleaning said gas dischargers; and
horizontal positioning means for moving said cleaning means between a standby position, located radially intermediate (1) said wafer mounting surfaces and said gas dischargers and (2) said rotary shaft, said standby position being occupied by said cleaning means when said wafer holder and said gas distributor are in said first position, and a working position vertically intermediate one gas discharger and a wafer mounting surface where said cleaning means is in contact with said one gas discharger, said working position being occupied by said cleaning means when said wafer holder and said gas distributor are in said second position.



24. A processing chamber comprising:
a chamber housing;
a shielded substrate support, housed within the chamber housing, comprising:
a substrate support base having a support surface and a sidewall;
said sidewall of said base having a first effective coefficient of thermal expansion (CTE);
a base shield having a cover plate portion, at least partially covering and supported by the support surface, and a skirt portion adjacent to said sidewall;
the sidewall of said base and the skirt portion of the base shield comprising respective first and second locking surfaces;
said skirt portion of said base shield having a second effective CTE; and
said second CTE being smaller than said first CTE.


5,589,002

GAS DISTRIBUTION PLATE FOR SEMICONDUCTOR WAFER PROCESSING APPARATUS WITH MEANS FOR INHIBITING ARCING

Yuh-Jia Su, Cupertino, Calif., assignor to Applied Materials, Inc., Santa Clara, Calif.
Filed Mar. 24, 1994, Ser. No. 217,467
Int. Cl.⁶ C23C 16/00

U.S. Cl. 118—723 E

28 Claims



1. A gas distribution plate for a semiconductor processing apparatus which permits the flow of process gas into said processing apparatus while inhibiting arcing adjacent said plate during plasma processing comprising a plurality of non-circular openings in said gas distribution plate, each of said non-circular openings having:
a) a width:
i) smaller than the diameter at which arcing will occur with circular openings; but
ii) at least about 254 μ m (10 mils) to inhibit blockage by a halogen-containing plasma; and
b) a length greater than said width.


5,589,004

METHOD FOR REMEDIATING CONTAMINATED MATERIAL

Brent J. Lashmet, Embarrass; Doug C. Lashmet; H. W. Lashmet, both of Babbitt; Larry R. Herzog, Mt. Iron; Thomas P. Tri, Duluth, and Merideth L. Karpik, Eveleth, all of Minn., assignors to B&S Research, Inc., Embarrass, Minn.
Division of Ser. No. 283,611, Aug. 1, 1994, Pat. No. 5,492,139.
This application May 26, 1995, Ser. No. 450,140
Int. Cl.⁶ B08B 7/04; C02F 3/02

U.S. Cl. 134—10

12 Claims



1. A method for removing a contaminating material from a combination material containing said contaminating material and a reusable material, said method comprising:

placing said combination material in a tank having a cleaning fluid therein capable of separating said contaminating material from said reusable material;

said cleaning fluid containing oxygen consuming microorganisms capable of also consuming at least a portion of said contaminating material;

circulating oxygen through said cleaning fluid so as to provide oxygen for consumption by said microorganisms;

circulating said cleaning fluid around said combination material within said tank whereby said cleaning fluid will cause said contaminating material to separate from said reusable material and will cause at least some portion of said contaminating material to float on the top surface of said cleaning fluid within said tank;

drawing off said contaminating material which is floating on said top surface of said cleaning fluid and removing it from said tank through a skimming opening in said tank;

recirculating said cleaning fluid through said tank through an outlet opening therein which is remote from and lower than the skimming opening.

5,589,005

SYSTEM FOR SUPPLYING ULTRAPURE WATER AND METHOD OF WASHING SUBSTRATE, AND SYSTEM FOR PRODUCING ULTRAPURE WATER AND METHOD OF PRODUCING ULTRAPURE WATER

Tadahiro Ohmi, 1-17-301, Komagabukuro 2-chome, Aoba-ku Miyagi-ken Sendai-shi 980, Japan


PCT No. PCT/JP92/01450, § 371 Date May 31, 1994, § 102(e) Date May 31, 1994, PCT Pub. No. WO93/08931, PCT Pub. Date May 13, 1993

PCT Filed Nov. 9, 1992, Ser. No. 232,266

Claims priority, application Japan, Nov. 8, 1991, 3-320885 Int. Cl.⁶ B08B 3/00; C02F 1/02

U.S. Cl. 134—30

23 Claims



1. A system for supplying ultrapure water comprising:

- a source of a first ultrapure water
- a piping system connected to said source, said piping system having a use point;
- a steam generating means connected to said piping system for heating said first ultrapure water for conversion into a first steam;
- a steam heating means connected to said piping system between said steam generating means and said use point for further heating said first steam for conversion thereof into a second steam having a temperature higher than that of said first steam; and
- a cooling means connected to said piping system between said steam heating means and said use point for cooling said second steam and for conversion thereof into a second ultrapure water.

5,589,006 SOLAR BATTERY MODULE AND PASSIVE SOLAR SYSTEM USING SAME


Shigenori Itoyama; Kimitoshi Fukae, both of Nara; Masahiro Mori, Tsuzuki-gun; Yuji Inoue, Nara; Fumitaka Toyomura, Soura-gun, and Takashi Ohtsuka, Tsuzuki-gun, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Nov. 25, 1994, Ser. No. 348,938

Claims priority, application Japan, Nov. 30, 1993, 5-299819 Int. Cl.⁶ H01L 31/058; 31/048; E04D 13/18

U.S. Cl. 136—248

32 Claims



17. A passive solar system in which a vent layer is formed between a roof board and a roofing plate provided over the roof board, and in which solar heat absorbed through the roofing plate is converted into a heated air flow, said solar system comprising:

a solar cell module having a solar cell covered with a layer of filler, and an area of a back insulating member larger than that of said solar cell, another layer of said filler, and a back reinforcement member, superposed in this order on the non-light-receiving side of said solar cell, said back insulating member having at least one opening corresponding to at least one pierced portion of said module for accommodating a fixing means affixing said solar cell module to said roof board.

5,589,007

PHOTOVOLTAIC ELEMENTS AND PROCESS AND APPARATUS FOR THEIR FORMATION

Yasushi Fujioka; Shotaro Okabe, both of Nara; Masahiro Kanai, Soraku-gun; Hideo Tamura; Atsushi Yasuno, both of Nara; Akira Sakai, Soraku-gun, and Tadashi Hori, Tsuzuki-gun, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 187,550, Jan. 28, 1994, abandoned.


This application Sep. 5, 1995, Ser. No. 523,169

Claims priority, application Japan, Jan. 29, 1993, 5-013478; Jan. 29, 1993, 5-013562; Jan. 29, 1993, 5-013563

Int. Cl.⁶ H01L 31/075; 31/20

U.S. Cl. 136—249

21 Claims



8. A photovoltaic element comprising a first non-monocrystalline silicon-containing semiconductor layer of a first conductivity type, a first i-type non-monocrystalline silicon-containing semiconductor layer formed by microwave plasma CVD, a second i-type non-monocrystalline silicon-containing semiconductor layer formed by high-frequency plasma CVD, a

5,589,009 RE-FE-B MAGNETS AND MANUFACTURING METHOD FOR THE SAME

Andrew S. Kim, Pittsburgh, and Floyd E. Camp, Trafford, both of Pa., assignors to Crucible Materials Corporation, Syracuse, N.Y.


Division of Ser. No. 235,279, Apr. 29, 1994, Pat. No. 5,480,471.

This application Jun. 5, 1995, Ser. No. 462,959

Int. Cl.⁶ H01F 1/053

U.S. Cl. 148—302

8 Claims



5,589,008 PHOTOVOLTAIC CELL AND METHOD FOR FABRICATION OF SAID CELL

Herbert Keppner, Neuchatel, Switzerland, assignor to Université De Neuchatel, Neuchatel, Canada

PCT No. PCT/CH94/00192, § 371 Date May 31, 1995, § 102(e)

Date May 31, 1995, PCT Pub. No. WO95/10856, PCT Pub. Date Apr. 20, 1995


PCT Filed Sep. 27, 1994, Ser. No. 446,628

Claims priority, application France, Oct. 11, 1993, 93 12246

Int. Cl.⁶ H01L 31/06; 31/18

U.S. Cl. 136—259

30 Claims



1. A photovoltaic cell, comprising:

- a semiconductor substrate having opposed front and rear surfaces;
- a front passivation layer deposited on the front surface of the substrate;
- an emitter layer formed over the front passivation layer having a first conductivity type (p or n);
- a front transparent conductive layer formed over the emitter layer;
- a rear passivation layer deposited on the rear surface of the substrate;
- a rear layer formed over the rear passivation layer having a second conductivity type (p or n) opposite that of the emitter layer, said rear layer producing a back surface field; and
- a reflective element over the rear layer and comprising a rear transparent conductive layer, an adhesion layer formed on the transparent conductive rear layer, and a reflective layer secured to the adhesion layer.

5,589,010 ANNEALED POLYMER-BONDED SOFT MAGNETIC BODY


David E. Gay, Noblesville, Ind., assignor to General Motors Corporation, Detroit, Mich.

Continuation-in-part of Ser. No. 241,069, May 11, 1994, abandoned, which is a division of Ser. No. 44,421, Apr. 9, 1993, abandoned. This application Nov. 24, 1995, Ser. No. 563,436

Int. Cl.⁶ H01F 1/22

U.S. Cl. 148—306

3 Claims



1. A compression molded soft magnetic core comprising a coalesced body consisting essentially of a plurality of thermally stress-relieved soft ferromagnetic metal particles consisting essentially of iron which are each substantially surrounded and adhered together by a thermoplastic polymer having a heat deflection temperature of at least about 400° C. and selected from the group consisting of polybenzimidazole and polyimides wherein said polymer constitutes less than about one weight percent of said coalesced body.

5,589,011

NANOSTRUCTURED STEEL ALLOY

Kenneth E. Gonsalves, Storrs, Conn., assignor to The University of Connecticut, Storrs, Conn.

Filed Feb. 15, 1995, Ser. No. 389,778

Int. Cl.⁶ C22C 38/22; 38/24

U.S. Cl. 148—334

21 Claims



1. A steel alloy, comprising: nanostructured crystals comprised of iron, chromium, molybdenum, vanadium and carbon.

5,589,012

BEARING SYSTEMS


Gray D. Hobby, Stafford, and Bernard A. Riggs, Herndon, both of Va., assignors to Systems Integration and Research, Inc., Arlington, Va.

Filed Feb. 22, 1995, Ser. No. 392,236

Int. Cl.⁶ C22C 45/10

U.S. Cl. 148—561

28 Claims



1. A bearing having at least one surface made of an amorphous alloy having a coefficient of friction of less than 0.5, having a crystallization temperature lower than 497° C. and having a tensile strength of 1.0 GPa or greater.

5,589,013

ADHERING CEREMONIAL ROLL

Michael J. Stepanek, Hollis, N.H., assignor to Hampshire Paper Corp., Milford, N.H.

Continuation-in-part of Ser. No. 369,650, Jan. 6, 1995, Pat. No. 5,449,539, which is a continuation-in-part of Ser. No. 144,333, Nov. 1, 1993, Pat. No. 5,401,548, which is a continuation-in-part of Ser. No. 954,027, Sep. 30, 1992, abandoned.


This application Jun. 22, 1995, Ser. No. 493,576

Int. Cl.⁶ D06N 7/00; D04D 9/00

U.S. Cl. 156—71

6 Claims

1. A method of applying a removable, ceremonial material to a walkway comprising: providing a ceremonial roll of non-woven fabric said non-woven fabric comprising long, natural and synthetic fibers, said roll having a length, a starting end, a walking surface adapted to a



ceremony, a floor abutting surface and a width between 18 inches and 55 inches, said floor abutting surface having a double-sided, pressure sensitive adhesive attached to the starting end, the adhesive comprising a strip of material having a first side and a second side, each side having an adhesive such that first side of said strip is attached to the floor abutting surface;

securing the starting end of the floor abutting surface to a starting position on the walkway with the adhesive on the second side of the strip; unrolling the roll along the walkway so as to apply the material to the walkway, the roll resisting removal from the walkway when pulled with a force at an angle between 0 and 30 degrees relative to the walkway, and; removing the roll from the walkway by pulling the roll at an angle of greater than 30 degrees relative to the walkway.

5,589,014

METHOD FOR FORMING PLEATS IN A SHEET-LIKE MATERIAL

Dennis G. Hicks, Neenah, Wis., assignor to Converting, Inc., Clintonville, Wis.


Division of Ser. No. 983,472, Dec. 3, 1992, Pat. No. 5,389,188.

This application Jul. 21, 1994, Ser. No. 277,276

Int. Cl.⁶ B32B 31/08

U.S. Cl. 156—73.1

7 Claims



1. A method for forming a pleat in a sheet material, comprising the steps of: feeding a web of sheet material to a pleating surface; extending at least one pleating tooth carried by the pleating surface into said web, thereby altering the shape of the web to form a pleat; retracting said pleating tooth from said web after said pleat has been formed; holding the pleated web against the pleating surface following retraction of said pleating tooth from said web by applying vacuum pressure to said web on both sides of said pleat but not directly below said pleat; feeding the pleated web from the pleating surface to a bonding device; and bonding said pleat by operating the bonding device to prevent unraveling of said pleat.

5,589,015

METHOD AND SYSTEM FOR INSERTING REINFORCING ELEMENTS IN A COMPOSITE STRUCTURE

Thomas M. Fusco, Medford; Constance Magee, Wilmington, and Glenn Freitas, Foxboro, all of Mass., assignors to Foster-Miller, Inc., Waltham, Mass.


Continuation of Ser. No. 254,987, Jun. 7, 1994, abandoned.

This application Feb. 13, 1996, Ser. No. 600,473

Int. Cl.⁶ B32B 7/08; 31/16

U.S. Cl. 156—73.1

13 Claims



1. A method of inserting reinforcing pins in a composite structure, the method comprising: inserting a number of reinforcing pins in a compressible material to form a compressible material/pin combination structure; assembling said compressible material/pin combination structure on a composite structure which includes plies of fibers in a resin matrix; imparting ultrasonic energy to a plurality of said pins at the same time; and simultaneously applying pressure to said compressible material and said plurality of pins to compress the compressible material and insert said plurality of pins into the composite structure in unison.

5,589,016

PRESCORED FOAM FOR PANEL FABRICATION


Neil L. Hoopingarner, Everett, and Barry D. Matin, Maple Valley, both of Wash., assignors to The Boeing Company, Seattle, Wash.

Filed Apr. 29, 1994, Ser. No. 235,594

Int. Cl.⁶ B32B 3/12

U.S. Cl. 156—87

21 Claims



1. A method of fabricating composite panels, comprising: cutting foam edge pieces from a rigid foam board having a preembossed pattern of surface scores in at least one planar surface thereof, said pattern of surface scores including three series of parallel indentations in said surface of said foam board, each series extending at an angle of 60° to the others; laying up elements to be bonded together to make a panel, said elements including two face sheets of preimpregnated fabric

material, one each covering two opposite planar faces of an interior assembly, said interior assembly having a honeycomb core element in a core of said panel, and a foam edge around said core element, said foam edge made of at least one of said foam edge pieces;

heating said laid-up elements and applying pressure to cure said resin in said preimpregnated sheets and bond said elements together to form said panel;

generating gasses in copious quantities during said curing of said resin and bonding said elements together;

venting said gasses generated within said core of said panel through said pattern of scores in said faces of said foam edge pieces.

5,589,017

PREPARATION OF A SOLID OXIDE FUEL CELL HAVING THIN ELECTROLYTE AND INTERCONNECT LAYERS


Nguyen Q. Minh, Fountain Valley, Calif., assignor to AlliedSignal Inc., Morris Township, N.J.

Continuation-in-part of Ser. No. 11,052, Jan. 29, 1993, Pat. No. 5,368,667. This application Sep. 7, 1994, Ser. No. 301,930

Int. Cl.⁶ C04B 37/00

U.S. Cl. 156—87

12 Claims



1. A method of preparing a fuel cell, comprising the steps of: preparing a first unfired ceramic tape comprising an anode material; preparing a second unfired ceramic tape comprising an electrolyte material, the second ceramic tape being thinner than the first ceramic tape; laminating the first ceramic tape and the second ceramic tape together to form an unfired anode/electrolyte laminate; preparing a third unfired ceramic tape comprising a cathode material; preparing a fourth unfired ceramic tape comprising an interconnect material, the fourth ceramic tape being thinner than the third ceramic tape; laminating the fourth ceramic tape and the third ceramic tape together to form an unfired cathode/interconnect laminate; stacking the unfired anode/electrolyte laminate and the unfired cathode/interconnect laminate such that the second unfired ceramic tape is adjacent to the third unfired ceramic tape; and fabricating the unfired anode/electrolyte laminate and the unfired cathode/interconnect laminate into a fuel cell.

5,589,018

GLASS REPAIR KIT AND METHOD OF USE

Richard A. Campfield, 9249 Loquat Dr., Riverside, Calif. 92508

Continuation of Ser. No. 155,452, Nov. 19, 1993, Pat. No. 5,425,827, which is a continuation-in-part of Ser. No. 881,625,

May 12, 1992, Pat. No. 5,429,692, which is a continuation-in-part of Ser. No. 580,075, Sep. 10, 1990, Pat. No. 5,116,441.


This application May 8, 1995, Ser. No. 436,591

Int. Cl.⁶ B32B 35/00

U.S. Cl. 156—94

20 Claims

1. A kit for assembly of glass repair tools comprising:



a first bar of predetermined length having a first end, a second end, and a middle;
a second bar of predetermined length having a first end, a second end, and a middle;
means for connecting said first bar and said second bar substantially at a right angle to each other;
a resin injector;
means for attaching said resin injector to said first end of said first bar, adjustably for greater or lesser projection from said first bar;
a first suction cup and a second suction cup;
means for attaching said first suction cup to said first end of said second bar;
means for attaching said second suction cup to said second end of said second bar, said first and second suction cups being aligned when so attached;
a pressure bolt;
means for attaching said pressure bolt to said second end of said first bar adjustably for greater or lesser projection from said first bar;
means for attaching said pressure bolt to said middle of said second end bar adjustably for greater or lesser projection from said second bar;
means for attaching a suction cup to said middle of said first bar;
whereby the following tools may be assembled (1) a repair bridge in which said first and second bars are attached at their middles, the resin injector is adjustably attached at the first end of the first bar and the pressure bolt is adjustably attached at the second end of the first bar and suction cups are attached at the first and second end of the second bar, respectively and (2) a crack opener in which said suction cups are attached to said first and second ends of said second bar and said pressure bolt is adjustably attached to the middle of said second bar and (3) a repair bar tool in which said resin injector is adjustably attached to said first end of said first bar and said pressure bolt is adjustably attached to said second end of said first bar and a suction cup is attached to said middle of said first bar.

5,589,019

METHOD FOR APPLYING COVERING MATERIAL TO AN ELONGATE SUBSTRATE

Jozef Van Beersel, Temse, Belgium, and Robin C. John, Bath, United Kingdom, assignors to NV Raychem SA, Kessel-Loo, Belgium

PCT No. PCT/GB93/00487, § 371 Date Oct. 4, 1994, § 102(e) Date Oct. 4, 1994, PCT Pub. No. WO93/17857, PCT Pub. Date Sep. 16, 1993

PCT Filed Mar. 9, 1993, Ser. No. 295,896


Claims priority, application United Kingdom, Mar. 9, 1992, 9205073; Oct. 30, 1992, 9222797

Int. Cl.⁶ B32B 31/00

U.S. Cl. 156—184

2 Claims

1. A method of applying a wrapped covering material around a welded joint between two coated metal pipes bared of coating in the region of the weld, said method comprising:



(a) positioning an apparatus comprising
i) a hollow frame which can be positioned around the joint, and which is mounted on two or more wheels or rollers that, in use, can be rolled around the joint causing the frame to rotate around the joint in a circumferential manner;
ii) a covering material delivery device mounted on the frame, for receiving a wraparound covering material coated with an adhesive having a tack temperature and for delivering the adhesive-coated covering material onto a surface of the joint as the frame is rotated;
iii) at least two pressure rollers which are arranged to press radially inward onto the delivered covering material as the frame is rotated, one roller being arranged to press against the weld region and the other roller acting on the transition between the pipe coating; and
iv) a heater for heating the adhesive-coated covering material before it contacts the pressure rollers,
said positioning being such that the frame surrounds the joint and the rollers;
(b) mounting the adhesive-coated covering material in the delivery device;
(c) preheating the joint to 130° to 170° C.;
(d) preheating the adhesive-coated covering material to about the tack temperature of the adhesive with the heater; and
(e) rotating the frame circumferentially relative to the joint thereby delivering the covering material and causing the pressure rollers to press radially downward so that the roller pressing against the weld exerts a different pressure than the roller pressing against a transition between the pipe coating and the bared pipe.

5,589,020

APPARATUS FOR INSULATING CRYOGENIC DEVICES

Alexander P. Varghese, Bethlehem, Pa., assignor to Air Products and Chemicals, Inc., Allentown, Pa.


Continuation of Ser. No. 51,503, Apr. 21, 1993, abandoned.

This application Aug. 1, 1994, Ser. No. 283,343

Int. Cl.⁶ B31C 13/00

U.S. Cl. 156—185

4 Claims



1. A method of insulating a cryogenic device without directly applying insulation to the device comprising the steps of:

providing a sleeve having a generally circular cross-section and a longitudinal axis fabricated from a material having low thermal emissivities, the sleeve having a diameter larger than the device to be insulated;
positioning said sleeve for rotation about said longitudinal axis;
rotating said sleeve and wrapping said sleeve with the desired thickness of thermal insulating material; and
installing said device inside said sleeve after insulation of said sleeve is completed.

5,589,021

METHOD OF PRODUCING A SIGN

Hanley D. Bloom, Van Nuys, Calif., assignor to Colorprinting Specialists, Inc., North Hollywood, Calif.


Continuation-in-part of Ser. No. 47,915, Apr. 19, 1993, Pat. No. 5,399,217. This application Mar. 21, 1995, Ser. No.

407,614

Int. Cl.⁶ B32B 31/12

U.S. Cl. 156—219

8 Claims



1. A method of producing a sign having raised colored characters in a predetermined design comprising:
providing a generally planar male die presenting the predetermined design;
positioning a substrate layer against the male die;
providing a heatable pressure surface that is devoid of the predetermined design;
applying heat and pressure to the substrate layer utilizing the pressure surface to press the layer against the male die and emboss the predetermined design of the male die into the substrate layer as raised areas on the substrate layer;
applying color to the raised areas with the substrate layer positioned on the male die; and
separating the embossed and colored substrate layer from the male die.

5,589,022

METHOD OF MANUFACTURING EMBLEM OF THERMOPLASTIC SYNTHETIC RESIN SHEET

Eiji Kuwahara, Omiya Mansion, No. 25-18, Nakamiya 2-chome, Asahi-ku, Osaka-shi, Osaka-fu, Japan


Filed Jun. 5, 1995, Ser. No. 465,106

Claims priority, application Japan, Feb. 6, 1995, 7-039445

Int. Cl.⁶ B32B 3/02; 15/08

U.S. Cl. 156—231

12 Claims



1. A method of manufacturing an emblem comprising steps of:
arranging a composite sheet on a pole plate of an electrode die for high frequency induction, said composite sheet comprising a pattern sheet, a back-up layer of thermoplastic synthetic resin arranged under the pattern sheet, a tacky adhesion layer

arranged under said pattern sheet, a releasing paper sheet arranged under said tacky adhesion layer and a highly heat-resistant transparent carrier film, said pattern sheet comprising a transparent polyurethane film, a metal vapor deposition film formed under a lower surface of said transparent polyurethane film and a polyurethane film arranged under a lower surface of said metal vapor deposition film to cover said metal vapor deposition film;

pressing and heating said composite sheet from above by means of an engraving die to fusion-cut said pattern sheet and said back-up layer between said carrier film and said releasing paper sheet at least along the outer boundary off the pattern and weld them together;

peeling off either said carrier film or said releasing paper sheet; removing an unnecessary areas of the pattern; and bonding the peeled off carrier film or releasing paper sheet again.

5,589,023

METHOD FOR MAKING AND SHAPING OBJECTS OF RIGID INSULATION


John S. Rendall, and Massoud Ahghar, both of Albuquerque, N.M., assignors to Solv-Ex Corporation, Albuquerque, N.M.

Continuation-in-part of Ser. No. 183,477, Nov. 8, 1994, abandoned. This application Apr. 26, 1995, Ser. No. 429,195

Int. Cl.⁶ B29C 67/20

U.S. Cl. 156—245

9 Claims



1. A method for making panels and other shapes of rigid insulation, comprising the steps of:

mixing a double salt of aluminum potassium sulphate in powder form of $Al_2K_2(SO_4)_4 \cdot 24H_2O$ and a binding agent also in powder form;

spraying a mold-releasing agent to cover the inside surfaces of a mold that defines a final shape for said panels and other shapes of rigid insulation;

adding said mix of said double salt of aluminum potassium sulphate and said binding agent to said mold;

heating said mold and said mix for dehydration of said double salt of aluminum potassium sulphate in multiple steps of approximately 50° C., wherein said mix foams and expands to fill said inside surfaces of said mold;

separating a rigid state of said expanded foam of said dehydrated double salt of aluminum potassium sulphate and binding agent from said mold; and

applying a protective paper covering to exposed surfaces of said expanded foam of said dehydrated double salt of aluminum potassium sulphate and binding agent forming a piece of rigid insulation.

5,589,024

FABRICATION OF AN INTRAOCULAR LENS


Larry W. Blake, Irvine, Calif., assignor to Pharmacia Iovision, Inc., Irvine, Calif.

Division of Ser. No. 900,053, Jun. 27, 1992, which is a division of Ser. No. 705,771, May 28, 1991, Pat. No. 5,185,107, which is a division of Ser. No. 262,985, Oct. 26, 1988, Pat. No. 5,104,590. This application Jun. 5, 1995, Ser. No. 464,217

Int. Cl.⁶ B32B 31/12; B29D 11/00

U.S. Cl. 156—245

4 Claims



1. A method of incorporating a haptic into an intraocular lens comprising the steps of:
 surface charging an end of said haptic so as to improve the adhesive properties thereof;
 coating said surface charged end with a primer; and
 bonding said haptic to said intraocular lens, wherein said primer-coated end of said haptic is dusted with fumed silicon dioxide prior to said bonding step.

5,589,025

1 D CARD INTERMEDIATE AND METHOD

Ronald R. Garrison, Batavia, Ill., assignor to Wallace Computer Services, Inc., Lisle, Ill.


Continuation of Ser. No. 159,294, Nov. 30, 1993, abandoned.

This application Aug. 9, 1995, Ser. No. 512,988

Int. Cl.⁶ B32B 31/18; B29D 15/00

U.S. Cl. 156—268

3 Claims



1. A method for making an 1 D card intermediate comprising performing at a first site the steps of providing a two ply film laminate arranged in face-to-face relation with a dry, rupturable adhesive therebetween, providing a length of paper having top and bottom surfaces with first printed indicia relating to an 1 D card sponsor on said top surface, adhesively uniting said laminate to said bottom surface to position a first of said film plies adjacent said bottom surface, diecutting said paper length and said first of said film plies to provide a generally rectangular closed perimeter cut defining an 1 D card having said first film ply attached thereto with said film laminate extending beyond said diecut on all sides thereof, performing at a second site the step of laser imprinting second indicia on said top surface relating to the identity of the intended user of said 1 D card with both said first and second indicia being within said diecut and removing said 1 D card and said first film by rupturing said dry adhesive.

5,589,026

METHOD AND APPARATUS FOR ADHERING OBJECT TO A GLASS SURFACE


Jack L. Perceman, Golden Valley, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jun. 2, 1995, Ser. No. 460,181

Int. Cl.⁶ B32B 31/20

U.S. Cl. 156—286

17 Claims



1. A method for adhering an object having a heat activatable adhesive layer to a glass surface, comprising the steps of:

- (a) positioning the heat activatable layer of the object adjacent the glass surface;
- (b) enclosing the object in a sealed space after step (a);
- (c) at least partially evacuating the sealed space about the object after step (b) to remove trapped air bubbles between the glass surface and the object;
- (d) heating the heat activatable adhesive to adhere the object to the glass surface;
- (e) applying a force using a platen assembly having a contact surface conforming to the shape of the object to the adhesive layer to facilitate the adherence of the object to the glass surface, whereby the platen assembly is resiliently urged against the object by further evacuating the sealed space.

5,589,027

CUSTOM FABRICATED AND BORDERED RUG AND METHOD AND APPARATUS FOR FORMING IT


John Thornton, Chattanooga, Tenn.; Stanton J. Pool, Dalton, Ga., and Dennis R. Doll, Harrison, Tenn., assignors to American Rug Craftsmen, Inc., Sugar Valley, Ga.

Division of Ser. No. 30,631, Mar. 12, 1993, abandoned. This application Feb. 22, 1994, Ser. No. 199,057

Int. Cl.⁶ B29C 65/00

U.S. Cl. 156—304.4

12 Claims



1. A method of forming a composite bordered rug comprising:

bonding a plurality of border carpet segments to an edge of a central field carpet segment, each of said border carpet segments and said field segments comprising an upper surface and a carpet backing;

wherein said border carpet segments are bonded to said edge of said field carpet segment by abutting edges of said border carpet segments to said edge of said field carpet segment and applying a first hot-melt adhesive on said carpet backing of adjoining border carpet segments and said field carpet segment;

allowing said first hot-melt adhesive to solidify to form a bordered rug;

adhering a unitary carpet backing to a back side of said bordered rug wherein said carpet backing covers said border carpet segments and said field carpet segment by applying a layer of a second hot-melt adhesive between said back side of said bordered rug and said carpet backing and pressing said carpet backing against said back side of said bordered rug by passing the entire bordered rug between parallel moving runs of two endless belts and pressing said runs toward one another and heating said carpet backing as it passes between said runs, thereby forcing said carpet backing against the back side of said bordered rug and heating said layer of said second hot-melt adhesive as said bordered rug and said carpet backing move within said endless belts, thereby causing said hot-melt adhesive to adhere to said carpet backing and said back side of said bordered rug to form said composite bordered rug.

5,589,028

BONDING METHOD EMPLOYING TIE LAYERS FOR ADHERING POLYETHYLENE TO FLUOROPOLYMERS

Donald N. Robinson, Collegeville, and John H. Peltz, Glenolden, both of Pa., assignors to Elf Atochem North America, Inc., Philadelphia, Pa.

Division of Ser. No. 334,184, Nov. 3, 1994, abandoned. This application May 30, 1995, Ser. No. 453,796

Int. Cl.⁶ C09J 5/10

U.S. Cl. 156—306.6

5 Claims

1. A method of laminating a sheet of polyethylene to a sheet of a fluoropolymer resin comprising the steps of:
 blending a mixture consisting essentially of

- (a) 60–70% by weight of an aliphatic thermoplastic polyester-based polyurethane;
- (b) 20–35% by weight of a copolymer selected from
 - (1) the copolymers of ethylene, vinyl acetate and maleic anhydride and
 - (2) graft copolymers of polyethylene and maleic anhydride; and
- (c) 0–20% by weight of a homopolymer selected from low density polyethylene and low molecular weight polyvinylidene fluoride,

at a temperature between 125°–150° C. to form a molten polymer mixture;

compression molding the molten mixture at a temperature between 150°–177° C. to form a tie layer sheet having a thickness of 8–10 mil;

disposing the tie layer sheet between a sheet of polyethylene; and a sheet of PVDF or PVDF-fluoromonomer copolymer to form a composite; and

compression molding said composite at a temperature between 232° C. and 246° C. and under pressure sufficient to bond the sheet of polyethylene to the sheet of PVDF or PVDF-fluoromonomer copolymer.

5,589,029

SEMICONDUCTOR CHIP-SUPPLY METHOD AND APPARATUS

Hisako Matsui, Neyagawa, and Akira Kabeshita, Hirakats, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka-Fu, Japan


Filed Jul. 20, 1995, Ser. No. 504,748

Claims priority, application Japan, Jul. 21, 1994, 6-169447

Int. Cl.⁶ B32B 35/00

U.S. Cl. 156—344

11 Claims



1. A semiconductor chip-supply apparatus, comprising:
 a sucking member disposed below an adhesive sheet and having a suction face for sucking a lower face of the adhesive sheet thereto and holding the adhesive sheet thereon, a semiconductor chip being bonded to an upper face of the adhesive sheet with the adhesive sheet being positioned below the semiconductor chip;

a push-up needle that has a tip thereof positioned adjacent to the lower face of the adhesive sheet;

a driving means for moving said sucking member and the adhesive sheet that is sucked to and held by said sucking member downward relative to said push-up needle so as to cause relative upward movement of said push-up needle with respect to said sucking member and the adhesive sheet such that said push-up needle can carry out a push-up operation while said sucking member sucks the adhesive sheet thereto; and

a sucking collet for sucking and transporting the semiconductor chip separated from the adhesive sheet by the pushup operation of said push-up needle.

5,589,030

METHOD FOR PREPARING VANILLIN FROM OLD NEWSPRINT

Walter E. Sande, and Karl D. Sears, both of Shelton, Wash., assignors to Rhone-Poulenc Inc., Cranbury, N.J.

Filed Dec. 7, 1994, Ser. No. 350,835

Int. Cl.⁶ D21C 5/02

U.S. Cl. 162—7

9 Claims

1. A method for preparing vanillin from old newsprint comprising the steps of:

- a) converting old newsprint to a crumb pulp comprising of from about 20% to about 50% crumb pulp fiber solids by weight on an oven dry basis and the remainder water;
- b) cooking the crumb pulp in a medium comprising crumb pulp and cooking acid solution selected from the group consisting of sodium bisulfite, magnesium bisulfite, ammonium bisulfite, calcium bisulfite or mixtures thereof wherein the weight ratio of cooking acid solution to the crumb pulp fiber is from about 3 to about 6 for sufficient time and at sufficient temperature and pressure to form a spent sulfite liquor containing lignosulfonates;
- c) separating the cooked crumb pulp fiber from the spent sulfite liquor;
- d) removing the lignosulfonates from the spent sulfite liquor; and
- e) preparing vanillin from the removed lignosulfonates.

5,589,031

CHLORINE DIOXIDE BLEACHING OF CHEMICAL PULP

Per-Åke Färnstrand; Lars T. Sjödin, both of Sundsvall; Lars-Åke Lindström, Alnö, and K. Solveig E. Nordén, Njurunda, all of Sweden, assignors to Sunds Defibrator Industries Aktiebolag, Sweden
PCT No. PCT/SE91/00178, § 371 Date Oct. 2, 1992, § 102(e)
Date Oct. 2, 1992, PCT Pub. No. WO91/17306, PCT Pub. Date Nov. 14, 1991


PCT Filed Mar. 7, 1991, Ser. No. 930,665

Claims priority, application Sweden, Apr. 30, 1990, 9001548

Int. Cl. D21C 9/14; 9/17; 9/16

U.S. Cl. 162—65

8 Claims



range of from 0.3 to 1.5 and the mole ratio of sulfuric acid to the initial amount of hydrogen peroxide is maintained in the range of from 0.4 to 3.0, and wherein the concentration of H_2O_2 is sufficient to permit the overall conversion of H_2O_2 of approximately 60–90%.

5,589,033

PRODUCTION OF PREHYDROLYZED PULP

Panu Tikka, and Kari Kovasin, both of Rauma, Finland, assignors to Sunds Defibrator Porti OY, Finland


Filed May 13, 1994, Ser. No. 242,617

Claims priority, application Finland, Jan. 24, 1994, 940332

Int. Cl. D21C 1/06; 3/02

U.S. Cl. 162—84

28 Claims



1. A batch process for the preparation of pulp from lignin-containing cellulosic material comprising prehydrolyzing said cellulosic material in a reactor so as to produce prehydrolyzed cellulosic material and hydrolysate, neutralizing said hydrolysate and said prehydrolyzed cellulosic material in said reactor with alkaline neutralizing liquor containing sodium hydroxide and sodium sulfide so as to produce neutralized hydrolysate and neutralized prehydrolyzed cellulosic material and so as to dissolve hemicellulose contained in said cellulosic material, removing said neutralized hydrolysate from said reactor as a separate stream essentially comprising only said neutralized hydrolysate, and delignifying said neutralized prehydrolyzed cellulosic material with alkaline cooking liquor containing sodium sulfide and sodium hydroxide.

5,589,032

PROCESS FOR PREPARING A BLEACHING LIQUOR CONTAINING PERCARBOXYLIC ACID AND CARO'S ACID

Hou-Min Chang; Hasan Jameel; Junfu Song, all of Raleigh, N.C.; Dingru Pan, Beihing, China; Bijan Amini, Moorestown, N.J.; John R. Webster, Wilmington, and Bruce A. Evans, Hockessin, both of Del., assignors to North Carolina State University, Raleigh, N.C., and E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation-in-part of Ser. No. 948,122, Sep. 21, 1992, abandoned. This application Sep. 17, 1993, Ser. No. 123,532

Int. Cl. D21C 9/16

U.S. Cl. 162—76

4 Claims

1. A process for preparing a bleaching liquor containing a mixture of percarboxylic acid and Caro's acid which comprises mixing a carboxylic acid of the formula RCO_2H wherein R is an alkyl group of from 1 to 5 carbon atoms with an equilibrium solution of Caro's acid containing an initial amount of hydrogen peroxide and sulfuric acid wherein the mole ratio of carboxylic acid to the initial amount of hydrogen peroxide is maintained in the

5,589,034

POLYMER-REINFORCED PAPER HAVING IMPROVED CROSS-DIRECTION TEAR

David P. Hultman, Munising; Donald D. Watson, Christmas, and Edward W. Heribacka, Munising, all of Mich., assignors to Kimberly-Clark Corporation, Neenah, Wis.

Division of Ser. No. 167,746, Dec. 16, 1993, abandoned. This application May 31, 1995, Ser. No. 455,585

Int. Cl. D21H 21/18

U.S. Cl. 162—111

18 Claims

1. A polymer-reinforced paper comprising:
fibers, at least about 50 percent of which on a dry weight basis are cellulosic fibers;
a latex reinforcing polymer in an amount sufficient to provide the paper with from about 10 to about 70 percent, by weight, of reinforcing polymer, based on the dry weight of the paper; and
from about 15 to about 70 percent by weight, based on the dry weight of the cellulosic fibers, of a polyethylene glycol having a molecular weight of from about 100 to about 1,500;
wherein, when the paper has a moisture content less than about 5 percent by weight, the polymer-reinforced paper has an average cross-direction tear as measured with an Elmendorf Tear Tester in accordance with TAPPI Method T414 which is from about 10 to about 100 percent higher than the cross-direction tear of an otherwise identical polymer-reinforced paper which lacks the polyethylene glycol.

5,589,035

LIQUID TREATMENT DEVICE

Ingemar Sundqvist, Bergeforsen, Sweden, assignor to Sunds Defibrator Industries AB, Sweden


Filed Aug. 26, 1994, Ser. No. 296,707

Claims priority, application Sweden, Sep. 8, 1993, 9302898

Int. Cl. B30B 3/02

U.S. Cl. 162—232

3 Claims



1. Apparatus for liquid treatment and dewatering of material suspensions comprising a vat, first and second rotatably mounted cylindrical liquid permeable press rolls juxtaposed with each other to form a nip therebetween and at least partially enclosed within said vat, said vat including a bottom portion defining a converging space in the direction towards said nip between said first and second press rolls, whereby said vat is divided between said bottom portion of said vat and a remaining portion of said vat, wherein said bottom portion of said vat includes treatment liquid inlets which form a part of said bottom portion and wherein said bottom portion is openable so as to provide access to said vat, and sealing means for providing a liquid seal between said bottom portion of said vat and said remaining portion of said vat, said sealing means comprising a shoulder extending about said remaining portion of said vat and extending towards said bottom portion of said vat, and an adjustably extending about said bottom portion of said vat and extending towards said remaining portion of said vat, said bar means being connected to said treatment fluid inlets and said

bar means being adjustable whereby the position of said bottom portion of said vat, and said converging space, is determined thereby.

5,589,036

CONTROLLING PULP FLOW IN AN UPFLOW PULP TREATMENT TOWER

John A. Fleck, West Chester, Ohio, assignor to Champion International Corporation, Stamford, Conn.


Continuation of Ser. No. 884,947, May 18, 1992, abandoned.

This application Sep. 2, 1993, Ser. No. 115,110

Int. Cl. D21C 7/06

U.S. Cl. 162—246

1 Claim



1. A method for controlling movement of pulp stock in an upflow cylindrical pulp treatment tower, said method comprising the steps of:

- injecting jets of a diluent fluid into said tower through a side wall thereof, said jets moving along flow paths which vary from tangential of said tower in one or more first jets, to radial of said tower in one or more second jets;
- vectoring pulp flow streams resulting from said diluent jets with said tower toward a restricted discharge zone from said tower, which the discharge zone has a smaller area than the cross-sectional area of said tower wherein said pulp flow streams are initially converged toward the tower axis, subsequently deflected toward the tower circumference and reconverged toward the tower axis after said subsequent deflection step; and
- discharging said vectored pulp flow stream from said tower.

5,589,037

METHOD FOR REMOVING TETRANITROMETHANE FROM NITRIC ACID

Thomas L. Guggenheim, Mt. Vernon, Ind.; Sharon M. Fukuyama, Parkersburg, W. Va., and Gregory L. Warner, Schenectady, N.Y., assignors to General Electric Company, Pittsfield, Mass.

Filed Oct. 24, 1995, Ser. No. 547,516

Int. Cl. B01D 3/34

U.S. Cl. 203—35

15 Claims

1. A process for removing tetranitromethane from a tetranitromethane-contaminated concentrated nitric acid stream otherwise containing less than 5 percent by weight of organic compounds, comprising the steps of:

- adding concentrated sulfuric acid containing less than 5 percent by weight of organic compounds to said nitric acid stream to form a mixed acid stream that contains tetranitromethane, wherein the amount of sulfuric acid added is effective to render the tetranitromethane capable of removal

from the mixed acid stream by sparging the mixture with air or with an inert gas, and
(B) separating the tetranitromethane from the mixed acid stream.

5,589,038

MAGNETIC SUBSTANCE

Masafumi Ata, Kanagawa; Masataka Machida, Tokyo, and Haruo Watanabe, Kanagawa, all of Japan, assignors to Sony Corporation, Tokyo, Japan
Continuation of Ser. No. 939,723, Sep. 2, 1992, abandoned.

This application Nov. 13, 1995, Ser. No. 556,641

Claims priority, application Japan, Sep. 5, 1991, 3-254759; Oct. 31, 1991, 3-286353; Dec. 4, 1991, 3-320722
Int. Cl.⁶ C04B 35/00

U.S. Cl. 204—157.42 4 Claims
3. A method for making a magnetic recording medium comprising the steps of:

providing a dispersion of an organic polymer, an unsubstituted fullerene having the formula C_n , wherein n is an integer selected from 60, 70, 76 and 84 and a halogen or hydrogen-introducing agent wherein said halogen introducing agent is a halogen-containing salt;
ultrasonically irradiating said dispersion in a sealed container; and
maintaining the irradiated dispersion in said container until a magnetic recording medium comprising a matrix of a non-conductive material and a magnetized substituted fullerene having a ground state spin multiplicity in a doublet state is obtained.

5,589,039


IN-PLANE PARALLEL BIAS MAGNETIC FIELD GENERATOR FOR SPUTTER COATING MAGNETIC MATERIALS ONTO SUBSTRATES

Jon S. Hsu, Taipei, Taiwan, assignor to Sony Corporation, Tokyo, Japan, and Materials Research Corporation, Orangeburg, N.Y.

Filed Jul. 28, 1995, Ser. No. 508,865

Int. Cl.⁶ C23C 14/34

U.S. Cl. 204—192.12 15 Claims



1. A sputter coating apparatus having a biasing magnet for magnetically aligning domains in a thin film of material in the deposition thereof onto a substrate, comprising:

- a substrate support having a substrate support surface thereon lying in a plane;
- a central magnet having a pair of poles spaced a distance apart and located approximately in the plane at opposite ends of the substrate support surface;
- a pair of side magnets of approximately equal strength equally spaced on opposite sides of the support surface, each side magnet having a pair of corner poles spaced less than said distance from each other, the pairs of corner poles being approximately equally spaced from the poles of the central magnet on opposite sides thereof;

a pair of adjustable intermediate magnets of approximately equal strength positioned between the central and side magnets, the intermediate magnets each having a pair of poles spaced from each other on opposite ends of the support surface defining a gap therebetween;

the central, intermediate and side magnets having generally parallel polar axes, the poles of each magnet being magnetically interconnected by core material located generally outside of the plane; and

the magnets having strengths such that the resultant field therefrom is parallel to within approximately one degree on a substrate when supported in the plane on the substrate support surface.

5,589,040

PROCESS FOR PRODUCING OPTICAL RECORDING MEDIUM SPUTTERING METHOD AND SPUTTERING TARGET

Naoki Nishimura, Tokyo, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 131,734, Oct. 5, 1993, abandoned.


This application Dec. 20, 1995, Ser. No. 580,047

Claims priority, application Japan, Oct. 5, 1992, 4-288187; Aug. 26, 1993, 5-211613

Int. Cl.⁶ C23C 14/34

U.S. Cl. 204—192.26 16 Claims

(1,0,0) PLANE

○ N⁵⁺

1. A process for producing an optical recording medium comprising on a substrate an optical recording film and inorganic dielectric film containing a metalloid element, comprising: an optical recording film-forming step of forming the optical recording film on the substrate, and an inorganic dielectric film-forming step of subjecting at least one sputtering target comprising a crystal of the metalloid element to DC sputtering in a reactive gas atmosphere to form an inorganic dielectric film, wherein said crystal of the metalloid element has a diamond crystal structure, and the sputtering target is so constituted to have a sputtering surface substantially conforming to a lattice plane represented by Miller indices (1,0,0) of the diamond crystal structure.

5,589,041

PLASMA SPUTTER ETCHING SYSTEM WITH REDUCED PARTICLE CONTAMINATION


Alexander D. Lantsman, Middletown, N.Y., assignor to Sony Corporation, Tokyo, Japan, and Materials Research Corp., Orangeburg, N.Y.

Filed Jun. 7, 1995, Ser. No. 488,060

Int. Cl.⁶ C23C 14/34

U.S. Cl. 204—192.33 22 Claims

1. A plasma processing system for plasma sputter etching a substrate with reduced particle contamination comprising: a plasma processing chamber having an interior surface to define a processing space therein to contain a substrate to be sputter etched and including a vacuum system for creating a vacuum environment in said processing space;



an electrical element coupled to the plasma processing chamber for coupling electrical energy into at least a portion of the processing space through the interior surface for generating a plasma therein to etch the substrate which thereby produces a temperature rise in the processing chamber interior surface up to a processing temperature, the element being operable for interrupting the electrical energy to the processing space so that the plasma is extinguished when the plasma processing is complete;

- a heating device coupled to the plasma processing chamber externally of the vacuum processing space and operable for controllably heating the processing chamber interior surface;
 - a temperature control circuit connected to the heating device to control the operation and temperature of the heating device, the temperature control circuit turning the heating device to an ON state and operating the heating device for heating the processing chamber interior surface to approximately said processing temperature approximately at the time when the electrical element is interrupting energy to the processing chamber and the plasma is being extinguished, the temperature of the chamber interior space, after plasma generation, being maintained by the temperature control circuit approximately at the processing temperature of the processing chamber interior space during plasma generation, such that the chamber interior surface is maintained at a relatively constant temperature during plasma processing and for a predetermined time before and thereafter to prevent the flaking of deposited sputtered material from the processing chamber interior surface and the generation of contamination particles within the processing space;
- whereby contamination of the sputter etched substrate is reduced.

5,589,042


SYSTEM AND METHOD FOR FABRICATION OF PRECISION OPTICAL RAMP FILTERS

Klaus Robinson, Woodland Hills, and Hugh L. Garvin, Malibu, both of Calif., assignors to Hughes Aircraft Company, Los Angeles, Calif.

Filed Nov. 8, 1994, Ser. No. 336,592

Int. Cl.⁶ C23C 14/34

U.S. Cl. 204—192.34 8 Claims



1. A system for fabricating precision optical ramp filters, each of said filters having optical transmission and reflectance coefficients that vary as a function of position on said filter, comprising: a substrate which is optically transparent over a wavelength range of said optical ramp filter,

reflective material of a predetermined thickness disposed on said substrate, said reflective material having optical transmission and reflectance coefficients that vary with its thickness, an etching beam generator for generating a shaped etching beam whose width varies along its length, and a translator for imparting a relative translation between said beam and said substrate, with different portions of said reflective material exposed to different respective beam widths so that the thickness of said reflective material after etching varies as a function of position, with a corresponding positional variation in the reflective material's optical transmittance and reflectance.

5,589,043


MASK FOR PLATING METALS AND METHOD OF CONSTRUCTION THEREOF

James P. Edwards, 700 W. Fireweed La., Anchorage, Ak. 99503

Filed Oct. 31, 1995, Ser. No. 550,762

Int. Cl.⁶ C25D 1/00; 17/04; C25C 7/02; B29C 33/40

U.S. Cl. 204—281 17 Claims



1. A mask for selectively plating specific areas of a piece of metal comprising:

- a) a first mask part, including a rubberized mold, and a hard plastic mold cover, said hard plastic mold cover being fixedly attached to said rubberized mold, said rubberized mold and said hard plastic mold cover having an area therein cut in a specific pattern for applying plating metal to the specific areas of said piece of metal;
- b) a second mask part, including a rubberized mold, and a hard plastic mold cover, said hard plastic mold cover being fixedly attached to said rubberized mold, said rubberized mold and said hard plastic mold cover having an area therein cut in a specific pattern for applying plating metal to the specific areas of said piece of metal;
- c) means for securing and holding said first mask part and said second mask part about said piece of metal; and
- d) an electrode, fixedly attached to said second mask part such that said electrode is in electrical communication with said piece of metal when said second mask part is secured to said piece of metal for plating.

5,589,044

ELECTRODE FOR ELECTROLYSIS CELLS


Robert Scannell, Pfungstadt; Bernd Busse, Darmstadt, and Helmut Vormwald, Linsengericht, all of Germany, assignors to Heraeus Electrochemie GmbH, Hanau, Germany
Filed May 1, 1995, Ser. No. 431,898

Claims priority, application Germany, Jun. 1, 1994, 44 19 274.6

Int. Cl.⁶ C25B 11/02; 1/36

U.S. Cl. 204—286 11 Claims

1. Electrode for mercury chlor alkali electrolytic cells comprising a plurality of active electrode elements in the form of parallel bars, each bar having opposed lateral sidewall surfaces, an



upward facing top surface, and a downward facing bottom surface, said lateral sidewall surfaces being provided with recesses, each recess extending from said top surface to said bottom surface, at least two spaced apart current distributors extending transversely of said parallel bars and welded to said top surfaces, and means for supplying electrical current to said distributors.

5,589,045

DATA MANAGING METHOD IN PORTABLE BLOOD SUGAR VALUE-MEASURING AND PORTABLE BLOOD SUGAR VALUE-MEASURING APPARATUS USING SAME
Hiroshi Hyodo, Kyoto, Japan, assignor to Kyoto Daiichi Kagaku Co., Ltd., Kyoto, Japan

Filed Oct. 31, 1994, Ser. No. 331,813

Claims priority, application Japan, Nov. 2, 1993, 5-274228
Int. Cl.⁶ G01N 27/26

U.S. Cl. 204—406

27 Claims

1. A data managing method, to be carried out in a portable blood sugar value-measuring apparatus having no operation button, of selectively and removably mounting a selected one of several electrodes on the apparatus to execute a function corresponding to a resistance value of the selected electrode, comprising:
a preparatory process of mounting the electrode on the portable blood sugar value-measuring apparatus to set the apparatus to an operation start state and to select the function to be executed in correspondence with the mounted electrode;
a first clocking process of clocking a first period of time after the execution of the preparatory process terminates;
a first dropping-determining process for determining whether the first clocking process has been switched over to a blood sugar value-measuring process for measuring a blood sugar value of to-be-measured liquid which has been dropped to the mounted electrode while clocking of the first period of time is being executed in the first clocking process;
a storing process for storing a measured blood sugar value in storing means subsequent to the first clocking process being switched over to a blood sugar value-measuring process; and
a read-out process for reading out measured blood sugar data stored in the storing means from a termination point of the first period of time and outputting the measured blood sugar data read out from the storing means when the first period of time has terminated without the switchover from the first clocking process to the blood sugar value-measuring process being decided in the first dropping-determining process.

5,589,046

ROOM TEMPERATURE CARBON MONOXIDE GAS SENSOR AND THE PROCESS FOR PREPARING THE SAME

Wenfan Li, and Xuying Liu, both of Changchun, China, assignors to Chang Chun Institute of Applied Chemistry of the Chinese Academy of Sciences, Changchun, China
Filed Dec. 16, 1994, Ser. No. 358,217

Claims priority, application China, Mar. 17, 1994, 94101843.1

Int. Cl.⁶ G01N 27/12; 27/26

U.S. Cl. 204—424

2 Claims

1. A room temperature carbon monoxide gas sensor comprising two helical coil electrodes made from $\phi 0.03$ – 0.05 mm Pt filament, one of which having a greater coil diameter, and the other one having a smaller coil diameter, the length of the coil electrodes being in the range of 0.8–1.4 mm, the one having a greater diameter having a diameter in the range of 0.6–1 mm and being used as an anode, while the smaller diameter one having a diameter between 0.3–0.6 mm and being used as a cathode, the smaller diameter coil electrode being inserted in the greater diameter one, wherein, the two helical coil electrodes are coated by a composition having the following composition:
1 part (weight) of high purity SnO_2 ;
0.002–0.08 (weight) of high purity Pt black;
0.00025–0.065 part (weight) of high purity Y_2O_3 ;
0.00009–0.086 part (weight) of high purity La_2O_3 ;
0.00015–0.08 part (weight) of high purity Cr; and
0.0002–0.07 part (weight) of high purity Al_2O_3 .

5,589,047

METHODS FOR THE SELECTION, SEPARATION AND FUSION OF CELLS


Hans G. L. Coster, Randwick; Robert G. Ashcroft, Sandringham, and Tohsak Mahaworasilpa, Randwick, all of Australia, assignors to Fucell Pty Limited, Randwick, Australia
PCT No. PCT/AU92/00473, § 371 Date Apr. 5, 1994, § 102(e)
Date Apr. 5, 1994, PCT Pub. No. WO93/05166, PCT Pub. Date Mar. 18, 1993

PCT Filed Sep. 4, 1992, Ser. No. 204,253

Claims priority, application Australia, Sep. 5, 1991, PK8213
Int. Cl.⁶ C25B 7/00

U.S. Cl. 204—450

24 Claims



1. A method for the selective recovery of cells, vectors, particles or molecules expressing or presenting a defined ligand, comprising the steps of physically or chemically binding to a surface of a solid and immobile target a ligand or ligands complementary to the defined ligand, introducing the target into a suspension or solution of cells, vectors, particles or molecules in an electrically conductive liquid in which some of the cells, vectors, particles or molecules express or present the defined ligand, causing at least some of the cells, vectors, particles or molecules expressing or presenting the defined ligand to migrate into contact with the target and to

bind with the complementary ligand or ligands by establishing between a pair of electrodes in the suspension or solution an alternating electric field of such a frequency, intensity and inhomogeneity that at least some of the cells, vectors, particles, ligands or molecules expressing or presenting the defined ligand will move towards the target, and separating the cells, vectors, particles or molecules which have bound to the target due to a dielectrophoretic force induced by the said alternating electric field from at least some of the other cells, vectors, particles or molecules in the suspension or solution.

5,589,048

METHOD FOR THE PRODUCTION OF A RADIOGRAPHIC SCREEN

Nikolaas De Jaeger, Hove; Guy Damen, Dessel, both of Belgium; Gerhard Winter, Goslar, Germany, and Jao Van Havenbergh, Zwijndrecht, Belgium, assignors to AGFA-Gevaert, N.V., Mortsel, Belgium

Division of Ser. No. 983,708, Dec. 1, 1992, Pat. No. 5,296,117.


This application Feb. 17, 1994, Ser. No. 197,825

Claims priority, application European Pat. Off., Dec. 11, 1991, 91203238

Int. Cl.⁶ C25D 13/02; 13/10

U.S. Cl. 204—489

5 Claims



1. A radiographic screen wherein a supported phosphor-containing layer electrophoretically deposited particles are present in conjunction with a resin binder and the volume ratio of phosphor-to-resin binder is in the range from 80/20 to 99.9/0.1, the density of the phosphor is at least 5 g/m³ and wherein said phosphor particles are present in contact with a surface active compound which is a member selected from the group consisting of an alkyl aryl polyether sulphate, an organic phosphate, a phosphate ester, and a phospholipid.

5,589,049

METHOD OF COATING ELECTRICALLY CONDUCTIVE SUBSTRATES, AQUEOUS ELECTRODIP PAINTS, PROCESS FOR THE PREPARATION OF AN AQUEOUS DISPERSION OF CROSSLINKED POLYMER MICROPARTICLES AND DISPERSIONS PREPARED BY THIS PROCESS

Günther Ott; Hardy Reuter; Walter Jouck; Susanne Piontek; Ulrich Helmman, all of Münster, Germany, and John Gübert, Beverly Hills, Mich., assignors to BASF Lacke + Farben, AG, Muenster-Hiltrup, Germany

PCT No. PCT/EP93/00291, § 371 Date Aug. 22, 1994, § 102(e)

Date Aug. 22, 1994, PCT Pub. No. WO93/16139, PCT Pub. Date Aug. 19, 1993

PCT Filed Feb. 8, 1993, Ser. No. 284,406

Claims priority, application Germany, Feb. 15, 1992, 42 04 581.9

Int. Cl.⁶ C25D 13/04

U.S. Cl. 204—504

16 Claims

1. Method of coating electrically conductive substrates comprising the steps of

(1) immersing the electrically conductive substrate in an aqueous electrodeposit paint which contains at least one cathodically depositable synthetic resin together with crosslinked polymer microparticles,
(2) connecting the substrate as cathode,
(3) depositing a film by direct current on the substrate,
(4) removing the coated substrate from the electrodeposit paint, and
(5) baking the deposited paint film,
wherein the crosslinked polymer microparticles contained in the aqueous electrodeposit paint are prepared by reacting
(A) a compound which contains on average more than 1.0 epoxide group per molecule, or a mixture of such compounds, with
(B) a compound which contains a group reactive toward epoxide groups and at least one ketimine or aldimine group in the molecule, or a mixture of such compounds to give a non-crosslinked intermediate product (C), which contains on average at least one epoxide group per molecule, and dispersing the intermediate product in the presence of a Brønsted acid in an aqueous medium, and subsequently reacting the epoxide groups on the intermediate product (C) with the amino groups on the ketimine to form crosslinked particles.

5,589,050

ELECTRODIALYZER FOR DESALINATION

Igor N. Medvedev, Moscow, and Klim A. Schogenov, Nalchik, both of Russian Federation, assignors to Aquamin Company Limited

PCT No. PCT/GB93/00675, § 371 Date Mar. 16, 1995, § 102(e)
Date Mar. 16, 1995, PCT Pub. No. WO93/20012, PCT Pub. Date Oct. 14, 1993


PCT Filed Mar. 31, 1993, Ser. No. 313,284

Claims priority, application United Kingdom, Mar. 31, 1992, 9207080

Int. Cl.⁶ B01D 61/44; C02F 1/469

U.S. Cl. 204—630

5 Claims



1. An electrodialyzer comprising:
a container having
an input for supplying aqueous solution to be desalinated and an output for carrying substantially desalinated solution out of the container,
at least one membrane adapted to provide an anion exchange, at least one membrane adapted to provide a cation-exchange, a flow path from the input to the output across a surface of each of the membranes successively, and
a concentration chamber separated from successive portions of the flow path by an anion exchange membrane, and by a cation-exchange membrane, and
means for drawing off fluid accumulating in the concentration chamber, and
an anode arranged at the beginning of the flow path in abutment with the container and with a cation-exchange membrane.

5,589,051

CLAMP FOR USE WITH ELECTROPLATING APPARATUS AND METHOD OF USING THE SAME
Paul Henington, Tsuen Wan, Hong Kong, assignor to Process Automation International Limited, New Territories, Hong Kong


Filed Dec. 9, 1994, Ser. No. 353,197

Claims priority, application United Kingdom, Dec. 10, 1993, 9325297

Int. Cl.⁶ C25D 5/00; 17/06; 17/08

U.S. Cl. 205—80

17 Claims



5. A method for electrolytic deposition of a coating of metal on an electroplatable substrate, the substrate having a lower edge, the method comprising the following steps:

- supporting at least one substrate in a substantially vertical plane for submersion into an electrolyte bath;
 - positioning the substrate over the electrolyte bath;
 - submersing the substrate into the electrolyte bath; and
 - clamping the substrate at its lower edge as the substrate enters the electrolyte bath,
- wherein the step of clamping the substrate comprises the step of moving a clamp between an open position and a closed position as the substrate is submersed into the electrolyte bath, the clamp comprising at least two levers pivotally attached to each other at a fulcrum, and at least one gripping member located on each lever for gripping the substrate, wherein the clamp, when floating on top of the electrolyte bath is in an open position, but when submersed into the electrolyte bath is caused, by virtue of its buoyancy, to move to a closed position, such that in the open position the gripping members are spaced apart from each other, and such that in the closed position, the gripping members are adjacent to each other and on either side of the substrate so as to grip the substrate with the gripping members.

5,589,052

METHOD FOR ELECTROLYZING WATER
Takayuki Shimamune, Tokyo; Shuji Nakamatsu, Kanagawa; Isao Sawamoto, Kanagawa, and Yoshinori Nishiki, Kanagawa, all of Japan, assignors to Permelec Electrode Ltd., Kanagawa, Japan


Continuation of Ser. No. 413,495, Sep. 27, 1989. This application Sep. 17, 1991, Ser. No. 759,975

Claims priority, application Japan, Sep. 29, 1988, 1-244979

Int. Cl.⁶ C25B 1/00

U.S. Cl. 205—349

1 Claim



1. A method of water electrolysis using an electrolytic cell comprising an anode compartment, a cathode compartment, a

diaphragm separating the anode and cathode compartments, means for recycling electrolyte from the cathode compartment to the anode compartment comprising a conduit connecting the anode and cathode compartments, and a water supply line for the anode compartment, comprising the steps of supplying through said water supply line an electrolyte of pure water to the anode compartment alone and not to the cathode compartment, which water permeates the diaphragm to enter the cathode compartment, electrolyzing the water electrolyte to evolve an ozone-containing oxygen gas in the anode compartment and hydrogen in the cathode compartment, thereby resulting in a net transfer of electrolyte from the anode compartment to the cathode compartment through the diaphragm, maintaining the internal gas pressures of the anode and cathode compartments substantially equal to each other, and recycling the water electrolyte from the cathode compartment to the anode compartment through the conduit such that the liquid level in the anode and cathode compartments is kept substantially the same.

5,589,053

ELECTROLYSIS PROCESS FOR REMOVAL OF CAUSTIC IN HEMICELLULOSE CAUSTIC

Stephen W. Moran; John R. Jackson, both of Wilmington; Timothy J. Gallivan, Hampstead, all of N.C., and Richard E. Loftfield, Fruit Cove, Fla., assignors to Huron Tech Incorporated, Kingston

Filed Nov. 3, 1995, Ser. No. 553,019

Int. Cl.⁶ C02F 1/461

U.S. Cl. 205—698

10 Claims

1. A process for recovering pulping chemicals and hemicellulose from an essentially lignin free starting solution comprising hemicellulose and caustic said process comprising:

- A) electrolyzing in an anolyte compartment of an electrolytic cell a hemicellulose starting solution containing about 2 to about 20 percent by weight of caustic to reduce the caustic content of said anolyte to about 10 to about 20 grams per liter without precipitation of said hemicellulose to obtain a caustic content in a catholyte compartment of said cell of about 60 to about 80 percent of the caustic content of said starting solution, said cell comprising an anode in said anolyte compartment and a cathode in said catholyte compartment, and said anode and cathode separated by a cationic permselective membrane cell separator and
- B) removing a caustic solution from the catholyte of said cell having a concentration of up to about 490 grams per liter.

5,589,054

Patent Not Issued For This Number

5,589,055

METHOD FOR PREPARING CARBON FIBERS

Masanobu Kobayashi, Iyo-gun; Motoi Itoh, Iyo; Yoji Matsu-hisa, Iyo-gun, and Kazuharu Shimizu, Otsu, all of Japan, assignors to Toray Industries, Inc., Japan

Division of Ser. No. 293,817, Aug. 22, 1994, Pat. No.

5,462,799. This application Jun. 5, 1995, Ser. No. 460,917

Claims priority, application Japan, Aug. 25, 1993, 5-210282; Jan. 14, 1994, 6-002582; Feb. 16, 1994, 6-019219

Int. Cl.⁶ C25F 1/00

U.S. Cl. 205—768

11 Claims

2. A process for preparing a carbon fiber, comprising anodically electrolyzing a carbon fiber in an alkaline aqueous solution, or anodically electrolyzing a carbon fiber in an acidic aqueous solution followed by washing with an alkaline aqueous solution, and then applying a sizing agent consisting essentially of an aromatic compound with multiple epoxy groups and having 6-47 atoms between the epoxy groups and an aromatic ring, said atoms

between said epoxy groups and said aromatic ring having a linear structure and linking said epoxy groups and said aromatic ring, to the fiber.

5,589,056

PROCESS FOR ELECTROECLAMATION OF SOIL MATERIAL

Wieberen Pool, Kaliumstraat 46, 9743 RV Groningen, Netherlands


Continuation of Ser. No. 47,079, Apr. 16, 1993, Pat. No. 5,433,839, which is a continuation of Ser. No. 680,607, Apr. 1, 1991, abandoned, which is a continuation of Ser. No. 255,988, Oct. 11, 1988, abandoned. This application Apr. 19, 1995, Ser. No. 424,073

Claims priority, application Netherlands, Oct. 13, 1987, 8702437

Int. Cl.⁶ C25F 1/00

U.S. Cl. 205—766

10 Claims



1. An electroreclamation process for removing from soils polluted therewith, contaminants having the ability to move toward an electrode under the influence of an electric current, which comprises the steps of:

- (a) enclosing within a porous housing at least one electrode adapted to serve as a cathode when connected to the negative pole of a DC voltage source and placed in current conducting relationship with at least one anode;
- (b) enclosing within a separate porous housing at least one electrode adapted to serve as an anode when connected to the positive pole of a DC voltage source and placed in current conducting relationship with at least one cathode;
- (c) placing the separately housed electrodes of steps (a) and (b) in current-conducting relationship with one another and with the soil to be treated;
- (d) supplying a medium capable of conducting current to the housed electrode(s) of step (a) through a cathodic circulation system and supplying a medium capable of conducting current to the housed electrode(s) of step (b) through a separate anodic circulation system;
- (e) connecting the housed electrode(s) of step (a) to the negative pole of a DC voltage source and the housed electrode(s) of step (b) to the positive pole of a DC voltage source, thereby forming at least one cathode and at least one anode;
- (f) passing an electric current through the soil to be treated and between the cathode(s) and anode(s), thereby causing migration of contaminants through the soil;
- (g) removing the contaminants which migrate to the cathode(s) and the contaminants which migrate to the anode(s); and
- (h) monitoring, and when necessary, controlling and adjusting the pH, conductivity, temperature and current intensity of the medium within each of the cathodic circulation system and the anodic circulation system.

5,589,057

METHOD FOR EXTENDING THE LIFE OF HYDROPROCESSING CATALYST


Harold J. Trimble, Hercules, Calif., and Brian A. Darso, St. Louis Park, Minn., assignors to Chevron U.S.A. Inc., San Francisco, Calif.

Continuation-in-part of Ser. No. 235,043, Apr. 29, 1994, abandoned, which is a continuation-in-part of Ser. No. 215,254, Mar. 21, 1994, Pat. No. 5,409,598, which is a continuation of Ser. No. 14,847, Apr. 1, 1993, abandoned, which is a continuation of Ser. No. 727,656, Jul. 9, 1991, abandoned, which is a division of Ser. No. 381,948, Jul. 19, 1989, Pat. No. 5,076,908. This application Nov. 21, 1994, Ser. No. 342,527

Int. Cl.⁶ C10G 35/00

U.S. Cl. 208—148

26 Claims



1. A method for reducing the quantity of hydroprocessing catalyst required for upgrading a hydrocarbon feed stream to essentially the same degree as or when compared to the quantity of hydroprocessing catalyst required for upgrading the hydrocarbon feed stream in a once through hydroprocessing catalyst replacement mode, comprising the steps of:

- (a) withdrawing a volume of particulate catalyst from a hydroconversion reaction zone including a substantially packed bed of hydroprocessing catalyst having an initially packed bed volume and which is essentially plug-flowing downwardly in the hydroconversion reaction zone and wherein said withdrawn volume of particulate catalyst includes a high-activity less dense catalytic particulates and a low-activity more dense catalytic particulates;
- (b) separating in a separation zone said high-activity less dense catalytic particulates from said low-activity more dense catalytic particulates;
- (c) admixing said high-activity less dense catalytic particulates with fresh catalytic particulates to produce a catalytic mixture having a mixture volume that is less than the withdrawn volume of particulate catalyst; and
- (d) introducing said catalytic mixture of step (c) into said hydroconversion reaction zone of step (a) such that said substantially packed bed of hydroprocessing catalyst which is essentially plugflowing downwardly in said hydroconversion reaction zone of step (a), has a subsequent packed bed volume that is less than the initially packed bed volume.

5,589,058

APPARATUS FOR TREATMENT OF WATER

Matthew J. Bauer, Niles, Mich., assignor to M. J. Bauer Company, Inc., Granger, Ind.


Filed Oct. 28, 1994, Ser. No. 331,050

Int. Cl.⁶ C02F 1/42

U.S. Cl. 210—98

13 Claims


1. A water treatment system, comprising:
a treatment tank having an ion-exchange mineral bed therein;
a valve head assembly disposed on top of and in fluid communication with said treatment tank, said valve head assembly including a passage means for allowing a flow of fluid



through said valve head assembly, means disposed within said passage means for creating a vacuum pressure within said treatment tank, a drain disposed within said passage means and at a downstream side of said vacuum pressure creating means, a valve disposed within said passage means and at a downstream side of said vacuum pressure creating means, said valve movable to an open position and a closed position for allowing fluid flow through said vacuum pressure creating means, and means for directing a portion of the fluid flowing through said vacuum pressure creating means to said drain and directing a lesser remaining portion of the fluid flowing through said vacuum pressure creating means to said valve when said valve is in said open position.

5,589,059
OIL FILTER ADAPTER SYSTEM INCORPORATING AN ACCESSIBLE FILTER ELEMENT
James E. Semar, P.O. Box 9412, New Iberia, La. 70562
Filed Jun. 7, 1995, Ser. No. 481,106
Int. Cl.⁶ B01D 35/153
U.S. Cl. 210—109

15 Claims



12. A lubrication filter system adapted for use with an automobile engine in an engine compartment provided with a pre-existent threaded fitting for a disposable cartridge filter on the engine wherein the system comprises:


- (a) an adapter for threaded connection to an automobile engine in lieu of the replaceable cartridge filter normally placed in the engine oil lubrication system, wherein said adapter includes adapter inlet and adapter outlet connections;
- (b) a first oil flow line extending from said adapter outlet connection and connected by means of a filter housing inlet

fitting with a separate filter housing adapted to be installed at an elevated location within the engine compartment, wherein said housing:

- (i) receives a removable lubricant filter;
 - (ii) has a removable upper cover over a lower portion and said cover fits on said lower portion to define a leak proof chamber for receiving a removable and disposable cartridge filter fitting therein;
 - (iii) incorporates fluid flow passages so oil is forced to flow through said filter for filtration;
 - (iv) has a filter housing outlet fitting;
- c) a second oil flow line extending between said adapter inlet connection and said filter housing outlet fitting, wherein said flow lines incorporate a valve system to deliver oil there-through, and wherein said valve system prevents drainage of oil from said filter housing by means of a first valve means in said first flow line and a second valve means in said second flow line, and wherein said second flow line returns filtered oil through said adapter to the engine; and
- (d) a filtered oil storage reservoir which connects to said second flow line at a point between said filter housing outlet fitting and said second valve means, wherein said filtered oil storage reservoir includes:
- (i) a closed cylinder;
 - (ii) a piston in said cylinder;
 - (iii) a bias device acting to bias said piston to form pressure on oil in said cylinder;
 - (iv) an electrically operated device to move said piston momentarily to decrease pressure on oil in said cylinder and then restore pressure to the oil in said cylinder.

5,589,060
FILTER FOR LIQUIDS, IN PARTICULAR INTERNAL-COMBUSTION ENGINE LUBRICANT OILS
Hans Gebert, Hellbronn-Böckingen; Rolf Möhle, Scheppach; Dietmar Sonntag, Remseck; Elke Bruns, Asperg; Dietwart Guntert, Sachsenheim, and Hubert Müller, Stuttgart, all of Germany, assignors to Knecht Filterwerke GmbH, Stuttgart, Germany
PCT No. PCT/DE92/00228, § 371 Date Sep. 14, 1993, § 102(e) Date Sep. 14, 1993, PCT Pub. No. WO92/17262, PCT Pub. Date Oct. 15, 1992
PCT Filed Mar. 16, 1992, Ser. No. 117,210
Claims priority, application Germany, Mar. 28, 1991, 41 10 307.6; Sep. 20, 1991, 41 31 353.4; Jan. 17, 1992, 42 01 041.1
Int. Cl.⁶ B01D 35/02
U.S. Cl. 210—130

21 Claims



21. Filter for liquids, comprising
a filter housing including an inlet means and an outlet means, a cover separable from said housing, said housing containing at least one ring-shaped, exchangeable filter element separable

from said housing having two axial ends and having an interior space, each said axial end defining an inside and a face side;

a support part within said housing, said support part being separable from the at least one filter element and extending at least partly centrally through the interior space of the filter element, and said support part being supported on the cover by a support means;

first and second radial inner seals separating a crude space surrounding an exterior of said filter element from a clean space contained within interior space of the filter element, and said radial inner seals mounted within said filter element at the axial ends of the filter element;

said separable filter element being folded star-shaped and sealed on each said face side by an end disk and provided on the inside at each of its two axial ends with a sleeve having a radial inner surface for resting against a radial outer surface of the radial inner seals;

said radial inner seals comprising said first radial seal positioned on the support part for separating the crude space from the clean space and said second radial inner seal positioned on said outlet means; and

an overflow valve contained within the support part for establishing a flow connection between said crude space and said interior space when a pressure difference therebetween exceeds a predetermined value;


wherein said outlet means comprises a tubular short pipe projecting into the interior space of the filter element, said pipe being centrally shaped by molding on the filter housing for receiving said second radial inner seal separating the crude space from the clean space;

a return check valve within said short pipe for preventing flow into said interior space via said pipe; and

wherein said support means includes a releasable snap connection means on the support part for detachably connecting the housing cover to the support part.

5,589,061
PROCESS FOR THE PREPARATION OF CELLULOSE BASED CHIRAL SEPARATION LIQUID CHROMATOGRAPHY STATIONARY PHASE
John W. Russell, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.
Filed Mar. 13, 1995, Ser. No. 402,663
Int. Cl.⁶ B01D 15/08
U.S. Cl. 210—198.2


10 Claims



1. A process for preparing a cellulose ester liquid chromatographic stationary phase, comprising the step of: reacting solid cellulose with an aromatic acid halide in the presence of a base catalyst, the temperature being below the temperature at which the cellulose ester dissolves, the concentration of the base catalyst being below the concentration at which the cellulose ester dissolves, the reaction time being less than the reaction time at which the cellulose ester dissolves.

5,589,062
RADIAL FLOW CHROMATOGRAPHY
Richard G. Rice, Baton Rouge, La., assignor to Board of Supervisors of Louisiana State University and Agricultural and Mechanical College, Baton Rouge, La.
Division of Ser. No. 23,144, Feb. 24, 1993, Pat. No. 5,433,847, which is a continuation of Ser. No. 580,582, Sep. 11, 1990, abandoned, which is a continuation-in-part of Ser. No. 430,495, Nov. 1, 1989, abandoned. This application May 30, 1995, Ser. No. 452,851
The portion of the term of this patent subsequent to Jul. 18, 2012, has been disclaimed.
Int. Cl.⁶ B01D 15/08
U.S. Cl. 210—198.2

9 Claims



1. A replaceable, radial-flow chromatographic diskette comprising at least two chromatographic beds, a first said bed and a second said bed:

- (a) wherein each of said beds has the shape of a right circular cylinder having a width substantially greater than its height;
- (b) wherein each of said beds comprises sorbent particles having a mean diameter less than 300 micron;
- (c) wherein the distribution of the particles within each of said beds is substantially uniform;
- (d) wherein each of said beds has a porosity less than thirty percent;
- (e) wherein said diskette further comprises a plate in the shape of a right circular cylinder adjacent both the first said bed and the second said bed, which plate separates said first and second beds;
- (f) wherein the axes of symmetry of the first said bed, the second said bed, and said plate are collinear; and
- (g) wherein said diskette further comprises means for transporting a fluid from said first bed to said second bed, said transporting means comprising said plate, wherein said plate has grooves fluidly connecting said first and second beds.

5,589,063
COLUMN ANALYZER SYSTEM AND IMPROVED CHROMATOGRAPH COLUMN FOR USE IN THE SYSTEM

James R. M. Sanford, Vidor; Patrick M. Frank, Beaumont; Joseph H. Golias, Beaumont, and William C. Jennings, Beaumont, all of Tex., assignors to Helena Laboratories Corporation, Beaumont, Tex.

Division of Ser. No. 285,014, Sep. 16, 1994, Pat. No. 5,441,645, which is a division of Ser. No. 58,364, May 10, 1993, Pat. No. 5,358,641, which is a division of Ser. No. 779,186, Oct. 22, 1991, Pat. No. 5,228,988, which is a continuation-in-part of Ser. No. 733,714, Jul. 22, 1991, abandoned, which is a continuation-in-part of Ser. No. 708,298, May 31, 1991, Pat. No. 5,207,918, which is a division of Ser. No. 427,346, Oct. 27, 1989, Pat. No. 5,045,208. This application Jun. 6, 1995, Ser. No. 470,991
Int. Cl.⁶ B01D 15/08
U.S. Cl. 210—198.2

24 Claims

1. A chromatographic column, comprising:
a hollow plastic shell having a reservoir portion with an end, a tip portion with an end, and a barrel portion connected between the reservoir and tip portions;



a chromatographic medium in the barrel portion; and
a foil member attached to the end of the reservoir portion to close it, the foil member having a metal layer and at least one plastic layer which separates the metal layer from the shell.


5,589,064

APPARATUS FOR LIQUID SOLID SEPARATION OF LIQUID EFFLUENTS OR WASTEWATER
Samuel Elmaleh, 21 Rue De L'Abbe' Camoz, 34830 Clapiers, France

Filed Oct. 24, 1994, Ser. No. 327,939
Int. Cl.⁶ C02F 1/52

U.S. Cl. 210—206

8 Claims



1. Apparatus for treating liquid effluent or wastewater containing pollutant particles in a suspension comprising:
a vessel defining a reactor for receiving and containing a flow of a liquid effluent or wastewater containing pollutant particles in a suspension and having a chemical therein for assisting agglomeration of said particles;
said reactor having a lower volume therein defining a coagulation zone comprising an injector in said lower volume of said reactor for delivering said flow in a given direction in the said lower volume;
said reactor lower volume defining a coagulation zone comprising convergent internal reaction surfaces having a fixed configuration for effecting intense mixing of said flow received in said coagulation zone and flowing said flow upwardly in said lower volume of said reactor;
said injector in said lower volume of said reactor coactive with said internal reaction surfaces disposed for delivering said flow against the reaction surfaces to develop counterflows for

effectively causing said intense mixing by said reaction surfaces in the lower volume of said reactor defining said coagulation zone;

said reactor having a volume above and contiguous with the coagulation zone into which the intensely mixed effluent or wastewater and chemical therein rises upwardly from said coagulation zone, and dimensioned for effectively allowing the primary particles to coalesce therein and effective flocculation to take place so that a flocculation zone is defined in the reactor above the coagulation zone;

said reactor having at an upper part contiguous with the flocculation zone a volume free or turbulence receiving effluent or wastewater from the flocculation zone and defining a settling and separation zone for settling of flocculant comprising the coalesced contaminant particles and separation of solids and liquid; and

means for discharging the clarified water and solids from said settling and separation zone.

5,589,065


MAGNETOHYDRODYNAMIC DEVICE

Jacob G. Bogatin, Richboro, Pa., and Vladimir Podoyma, Leningrad State, U.S.S.R., assignors to YBM Magnetics, Inc., Newtown, Pa.

Filed Feb. 4, 1994, Ser. No. 191,838
Int. Cl.⁶ C02F 1/48

U.S. Cl. 210—222

11 Claims



1. An apparatus for magnetically treating a fluid comprised of non-polar molecular clusters flowing therethrough said apparatus comprising:

a housing having an inlet and an outlet, said housing being adapted to permit said fluid to flow therethrough between said inlet and outlet within the interior of said housing;

a first magnet stationarily positioned transverse to the fluid flow direction within said housing, said first magnet having first and second sides of opposite polarity and an opening there-through between said first and second sides;

a second magnet spaced from and substantially parallel to said first magnet, said second magnet having an outer circumference spaced from the interior surface of said housing, said second magnet having first and second sides of opposite polarity;

said first and second magnets being positioned adjacent and parallel to each other with sides of opposite polarity facing each other;

support means within said housing for resiliently supporting and spacing said magnet means within said housing, said support means being comprised of:

first support members between said first and second magnets resiliently spacing said first and second magnets from each other; and

second support members within said housing resiliently positioning said second magnet from the interior surface of said housing;

said second magnet having an opening therethrough between said first and second sides thereof; and

said first support member being comprised of a first plug fitted within said opening through said second magnet and said opening through said first magnet, and spacing said first and second magnets from each other, said first plug further having a plurality of channels therethrough communicating between the space between said first and second spaced magnets and said opening through said first magnet, said first plug being comprised of:

a first plug member fitted within said opening through said second magnet;

a plurality of first projections extending from said first plug member into said opening through said first magnet; and

a plurality of second projections transverse to said first projections between said first and second magnets.

5,589,066

PORTABLE WATER PURIFICATION SYSTEM

Buddy D. Gray, Dellrose, Tenn., assignor to Teledyne Industries, Inc., Los Angeles, Calif.


Division of Ser. No. 120,400, Sep. 14, 1993, Pat. No. 5,496,466.

This application Jul. 22, 1994, Ser. No. 277,316

Int. Cl.⁶ B01D 36/00

U.S. Cl. 210—258

4 Claims



1. A portable water purification system comprising:
a prefilter means connectable to a feed water source;
a pump system immediately connected to said prefilter means;
a reverse osmosis filter means connected to said pump system, said reverse osmosis filter means including an input means, permeate output means, and a concentrate output means;
a microbial control means connected to said permeate output means; and
a post filter means connected to said microbial control means; and

wherein said prefilter means includes:

a water pickup means connected to said feed water source for obtaining feed water from said feed water source;

a screen filter means connected to said water pickup means; and

an adsorption filter means connected to said screen filter means, wherein said adsorption filter means is connected to said pump system.

174-405 O.G.-96-12: QL3

5,589,067

EXPANDED METAL FILTER SUPPORT STRUCTURE


Patrick E. Rice, Winthrop Harbor, Ill., assignor to Jason, Inc., Milwaukee, Wis.

Filed Sep. 18, 1995, Ser. No. 529,308

Int. Cl.⁶ B01D 27/06

U.S. Cl. 210—493.5

12 Claims



1. A filter media support structure comprising:

a generally cylindrically shaped pleated shell with each pleat of the pleated shell aligned parallel to a longitudinal axis of the shell and distributed around a circumference of the shell to form a zig-Zag patterned outer wall of the pleated shell around a circumference of the shell, when viewed in cross-section;

a first row of perforations parallel to the longitudinal axis in a planar element of each pleat of the pleated shell, mutually separated one from another by a perforation distance; and

at least a second row of perforations parallel to the first row of perforations offset from the first row of perforations along the longitudinal axis by a first offset distance greater than zero and less than one-half the perforation distance and offset along a second orthogonal axis of the planar element transverse to the longitudinal axis by a second offset distance.

5,589,068

METHOD OF CONTROLLING WASTE WATER PURIFICATION PLANTS USING MULTIPLE CONTROL FUNCTIONS

Marinus K. Nielsen, Virum, Denmark, assignor to I. Krüger Systems A/S, Søborg, Denmark

PCT No. PCT/DK92/00290, § 371 Date Mar. 22, 1994, § 102(e)

Date Mar. 22, 1994, PCT Pub. No. WO93/07088, PCT Pub.

Date Apr. 15, 1993


PCT Filed Oct. 1, 1992, Ser. No. 211,333

Claims priority, application Denmark, Oct. 1, 1991, 1678/91

Int. Cl.⁶ C02F 3/00

U.S. Cl. 210—614

15 Claims



1. A method of automatically controlling a waste water purification plant comprising the steps of measuring at least one system parameter, determining a control parameter on the basis of the measurement results obtained and a selected control function, selecting a control action on the basis of the determined control parameter, and subsequently implementing the selected control action, wherein the control parameter is determined on the basis of the measurement results for at least two parameters and the control functions associated with said parameters.

5,589,069

METHOD FOR SEPARATING AND ANALYZING IONS BY ELECTROSTATIC ION CHROMATOGRAPHY AND A ZWITTERIONIC STATIONARY PHASE FOR ION CHROMATOGRAPHY AND METHOD FOR SEPARATING AND ANALYZING ANALYTES BY MULTIFUNCTIONAL LIQUID CHROMATOGRAPHY

Hu Wenzhi, Nagoya, Japan, assignor to Solchi Inoue, Japan
Continuation of Ser. No. 107,608, Aug. 18, 1993, abandoned.


This application Jun. 12, 1996, Ser. No. 661,892

Claims priority, application Japan, Oct. 5, 1992, 4-290739; Apr. 5, 1993, 5-103625

Int. Cl.⁶ B01D 15/08

U.S. Cl. 210—635

12 Claims



1. A method of separating and analyzing ions by electrostatic ion chromatography, comprising the steps of:

- injecting a sample solution containing analyte anions and cations into one end of a separation column packed with a solid phase, and
 - thereafter eluting the column with water to analyze individually the analyte ions via the difference in the retention time among the individual analyte ions,
- wherein the solid phase is a zwitterionic stationary phase comprising a support carrier and a zwitterionic layer formed on the surface of the support carrier by directly or indirectly coating thereon 3-[3-cholamidopropyl]dimethyl ammonio]-1-propanesulfonate, 3-[3-cholamidopropyl]dimethyl ammonio]-2-hydroxy-1-propanesulfonate, sodium taurodeoxycholate or sodium taurocholate.

5,589,070

METHOD AND APPARATUS FOR CLEANING A DIALYSATE CIRCUIT DOWNSTREAM OF A DIALYZER


Jo-Ann B. Maltis, Morrison, Colo.; Archie T. Wood, Toronto, Ohio, and Roy S. Hovland, Denver, Colo., assignors to COBE Laboratories, Inc., Lakewood, Colo.

Continuation-in-part of Ser. No. 92,705, Jul. 16, 1993, Pat. No. 5,409,612. This application Jan. 13, 1995, Ser. No. 372,112

Int. Cl.⁶ B01D 65/00; 61/30

U.S. Cl. 210—636

26 Claims



13. A method for cleaning a dialysis machine, comprising: providing a dialysis machine, the dialysis machine comprising: a dialyzer having a dialysate portion and a blood portion;

a dialysis delivery system to deliver dialysate to the dialysate portion of the dialyzer having an external dialysate line with a dialyzer inlet connector;

a dialysate waste system to remove spent dialysate from the dialysate portion of the dialyzer having an external spent dialysate line with a dialyzer outlet connector;

a blood delivery system for delivering a patient's blood to the blood portion of the dialyzer;

a blood return system for returning the patient's blood to the patient from the blood portion of the dialyzer;

a bypass block comprising a first bypass block connector adapted to connect to the dialyzer inlet connector and a second bypass block connector adapted to connect to the dialyzer outlet connector and a conduit interconnecting the first bypass block connector and the second bypass block connector;

a check valve located in the conduit intermediate the first and second bypass block connectors and oriented to permit fluid flow from the first bypass block connector to the second bypass block connector and to prevent fluid flow from the second bypass block connector to the first bypass block connector;

an injection means located in the conduit intermediate the check valve and the second bypass block connector; a container of cleaning agent

a cleaning agent connector adapted for connection to a container of cleaning agent;

a cleaning agent line interconnecting the injection means and the cleaning agent connector;

a pump located in the cleaning agent line intermediate the injection means and the cleaning agent connector and oriented to pump cleaning agent from the cleaning agent connector to the bypass means; and

a backflow prevention valve located in the cleaning agent line intermediate the pump and the injection means and oriented to permit fluid flow from the pump to the injection means and to prevent fluid flow from the injection means to the cleaning agent connector;

connecting the dialyzer inlet connector to the first bypass block connector;

connecting the dialyzer outlet connector to the second bypass block connector;

directing a flow of clean dialysate from the dialysate delivery system through the external dialysate line, bypass block and external spent dialysis line, to the spent dialysate system; and

pumping cleaning agent from the container of cleaning agent to the injection means to deliver a prescribed volume of cleaning agent at a prescribed rate.

5,589,071

ANION-EXCHANGE MEMBRANE EXTRACTOR FOR BORIC ACID SEPARATION

Kun-Jai Lee, Taejon, and Jong-Kil Park, Anyang, both of Rep. of Korea, assignors to Korea Advanced Institute of Science and Technology, Taejon, Rep. of Korea

Filed Jul. 14, 1995, Ser. No. 502,758

Claims priority, application Rep. of Korea, Jan. 25, 1995, 95-1320

Int. Cl.⁶ B01D 15/04

U.S. Cl. 210—638

2 Claims

2. A method of separating boric acid from a concentrate of radioactive liquid waste contained in an evaporator which comprises the steps of:

passing the concentrate through a concentrate cell of an anion-exchange membrane extractor while an extract contained in a monitor tank is passed through an extract cell of the extractor;

allowing borate ions contained in the concentrate to flow into the extract; and,

allowing the concentrate and the extract to leave the concentrate cell and the extract cell and to enter the evaporator and the tank, respectively,

wherein the anion-exchange membrane extractor comprises:

5,589,073

SYSTEM AND METHOD FOR REMOVING ASBESTOS AND OTHER SOLID PARTICLES FROM A SLURRY


Gordon R. Chapman, Missouri City; Donald R. Andruik, Houston; James V. Van Matre, Baytown; Andre Stenzel, Houston; Robert J. Logan, Humble; Edwin D. McCrory, Sugarland; Michael W. Singleton, Houston, all of Tex., and Robert M. Richmond, Bakersfield, Calif., assignors to Gas Research Institute, Chicago, Ill.

Continuation-in-part of Ser. No. 874,793, Apr. 27, 1992, Pat. No. 5,330,657. This application May 5, 1994, Ser. No. 239,201

Int. Cl.⁶ C02F 1/52; 1/24

U.S. Cl. 210—704

20 Claims



an upper cell equipped with an inlet, an outlet;


a concentrate cell, an extract cell, and a lower cell, each of which has an upper layer and each of which is equipped with an inlet, an outlet, fluid-injecting holes, and a supporting shelf on the upper layer;

a water-proofing means inserted into the interface between said cells; a transporting tube connected to the inlets and outlets of said cells;

a supporting screen held up on the supporting shelf positioned in each of said cells; and,

an anion-exchange membrane supported by the said supporting screen

wherein said extractor does not require the application of an electric potential across said membrane for its function.



1. A method for removing asbestos and other solid particles from a slurry collected during removal of coatings from pipelines, equipment or other structures, the method including:

- transferring the slurry from collection means to first separation means;
- injecting a first flocculent into the slurry;
- separating a first portion of solid particles from the slurry in said first separation means thereby forming a first remaining slurry containing solid particles;
- separating a second portion of solid particles from said first remaining slurry to form a second remaining slurry containing solid particles; and
- separating a third portion of solid particles from said second remaining slurry to form water recyclable to or dischargeable from said process.

5,589,072

TRACE CAPTURE IN BIOLOGICAL FLUIDS


Edward Shanbrom, 2252 Llane La., Santa Ana, Calif. 92705

Filed Jul. 26, 1995, Ser. No. 507,761

Int. Cl.⁶ B01D 15/00; A61M 1/14

U.S. Cl. 210—638

2 Claims



1. A method for treating blood, liquid blood fractions or protein solution comprising adding iodine to a biological fluid to be treated and thereafter capturing any residual iodine by passing the iodine-containing biological fluid through a substantially iodine free bio-compatible, polymeric, elastomeric, lint-free, uniformly swellable hydrophilic sponge having a uniform pore geometry and pore size distribution throughout its volume comprising the inorganic acid-catalyzed reaction product of formaldehyde and polyvinyl alcohol, said sponge being characterized by a variation in the size of the diameter of the pores of less than about 8 to 1.

5,589,074

USE OF SILICON CONTAINING POLYELECTROLYTES IN WASTEWATER TREATMENT

Ananthasubramanian Sivakumar, Naperville; John H. Collins, Bloomingdale, and Manian Ramesh, Lisle, all of Ill., assignors to Nalco Chemical Company, Naperville, Ill.

Filed Nov. 30, 1995, Ser. No. 565,479

Int. Cl.⁶ C02F 1/56

U.S. Cl. 210—727

11 Claims

1. A process for removing color from a paper mill waste effluent containing color bodies which comprises:


- treating the waste effluent containing color bodies with an effective color-removing amount of a water-soluble silicon-containing copolymer coagulant prepared from diallyldimethylammonium halide and a vinyltrialkoxysilane wherein said copolymer has a reduced specific viscosity in one molar sodium nitrate solution for one percent polymer actives from 0.2 to 5 dl/gm and the mole ratio of diallyldimethylammonium halide to vinyl trialkoxysilane ranges from 99:9.0.1 to 80:20;
- coagulating the color bodies present in the waste effluent; and
- removing the coagulated color bodies from the waste effluent.

5,589,076 METHOD AND APPARATUS FOR OPTIMIZING OPERATION OF A FILTER SYSTEM

Thomas H. Womack, Novato, Calif., assignor to Womack International, Inc., Novato, Calif.
Continuation of Ser. No. 240,856, May 10, 1994, abandoned.
This application Jan. 11, 1996, Ser. No. 585,144
Int. Cl.⁶ B01D 17/12; 33/70

U.S. Cl. 210—739

48 Claims



1. A method for optimizing operation of a pressure filter system comprising at least one readily replaceable porous membrane or filter media supplying filtered fluid to a process system characterized by varying demands for filtered fluid, the method comprising the steps of:

- controlling the filter system by a supply means for supplying filtered fluid to the process system at a flow rate generally proportional to the varying demands for filtered fluid from the process system;
- constantly sensing a selected operating parameter of the process system indicative of its varying demands for filtered fluid and generating feedback data representative of the varying demands for filtered fluid by the process system; and
- regulating operation of the filter system supply means by a device operable to vary supply of inlet fluid to the filter system at a flow rate determined by the feedback data provided by the selected operating parameter, whereby the filter system operates at a variable flow rate for supplying filtered fluid generally in proportion to the varying demands for filtered fluid by the process system to optimize operation of the filter system.

5,589,077 LIQUID FILTERING AND SUPPLY SYSTEM CONTROLLING RECIRCULATION RESPONSIVE TO PRESSURE DIFFERENCE ACROSS FILTER


Yoji Matsuda, Ichihara; Masao Morikawa, Sodegaura, and Masaaki Toma, Ichihara, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan
Continuation of Ser. No. 305,918, Sep. 16, 1994, abandoned.
This application Nov. 16, 1994, Ser. No. 341,919

Claims priority, application Japan, Sep. 20, 1993, 5-233211; Oct. 1, 1993, 5-246637

Int. Cl.⁶ B01D 37/04

U.S. Cl. 210—741

16 Claims



5. A liquid supply method for removing particles in a liquid using a filter disposed in a main line having ends connecting with

a liquid introducing part and a liquid supplying part and for supplying said liquid to a use point, comprising the steps of: determining a pressure difference between a first pressure detector disposed at an upstream side of said filter, in said main line, and a second pressure detector disposed at a downstream side of said filter, in said main line; and adjusting a flow rate through a first circulating line connecting a first diverging point disposed in said main line at a downstream side of said second pressure detector to said liquid introducing part, based on said pressure difference, and thus controlling said pressure difference.


5,589,078 ADVANCED FILTRATION TECHNIQUE FOR FLUID PURIFICATION

Brian E. Butters, 122 Fairview Ave., St. Thomas, Ontario, Canada, and Anthony L. Powell, 10 Moreau Crescent, London, Ontario, Canada

Filed Jun. 7, 1995, Ser. No. 478,226
Int. Cl.⁶ C02F 1/48

U.S. Cl. 210—748

22 Claims



1. A method for recovering a decontaminated effluent after photocatalytic decontamination of a contaminated fluid, comprising:

- forming a slurry by mixing a contaminated fluid with photocatalytic particles having an agglomeration property;
- exciting the photocatalytic particles of the slurry to render a treated slurry that includes a decontaminated fluid and agglomerated photocatalytic particles;
- directing the treated slurry into a filter unit that includes at least one separation element, each separation element having an inner surface defined by a channel extending through a substrate, each separation element having a plurality of pores which derive from the inner surface and extend through the substrate;
- passing the treated slurry through a separation element under certain conditions designed to induce the agglomerated photocatalytic particles to accumulate and form a layer at or near the inner surface of the separation element; and
- recovering the decontaminated fluid through the plurality of pores of the separation element.

5,589,079 CRYSTAL RECOVERY METHOD EMPLOYING A ROTARY VACUUM FILTRATION DRUM WITH VALVED HOPPER CAKE TREATMENT MEANS


David B. Park, Middleboro, Mass., and Michael F. Crawley, Maryville, Tenn., assignors to Baker Hughes Incorporated, Salt Lake City, Utah

Division of Ser. No. 197,965, Feb. 17, 1994, Pat. No. 5,470,473. This application May 17, 1995, Ser. No. 442,958
Int. Cl.⁶ B01D 33/06

U.S. Cl. 210—784

5 Claims

1. A method for recovering crystals from a slurry, comprising: providing a filtration unit including a rotatably mounted cylindrical filter; pressurizing said filtration unit;



feeding a slurry under pressure to an input of said filtration unit; rotating said filter during the pressurizing of said filtration unit and the feeding of said slurry;

discharging, into a first hopper, crystalline material separated from said slurry by the filtration unit and caked on an outer surface of said filter, said first hopper having an outlet with a first valve unit in a closed state second hopper having an outlet with a second valve unit in a closed state;

opening said first valve unit;

upon opening of said first valve unit, transferring crystalline material from said first hopper into said second hopper, while maintaining said second valve unit closed;

upon transferring crystalline material from said first hopper into said second hopper, closing said first valve unit;

upon transfer of crystalline material from said first hopper into said second hopper, opening said second valve unit to discharge the crystalline material from said second hopper to essentially atmospheric pressure; and

removing crystalline material caked on a wall of a given one of said first hopper and said second hopper.


5,589,080 LIQUID RECYCLING SYSTEM WITH MOVING CONCENTRATED COUNTERFLOW FOR FILTER CLEARANCE

Sung K. Cho, Roseville, and Lowell H. Schiebe, Corcoran, both of Minn., assignors to CFR Corporation, New Brighton, Minn.

Filed Apr. 4, 1995, Ser. No. 416,289
Int. Cl.⁶ B01D 29/66; A47L 9/18

U.S. Cl. 210—791

22 Claims



18. In a fluid cycling system including a reservoir for containing a liquid and means to move the liquid into and out of the reservoir, a process for maintaining a flow of the liquid through a filter contained within the reservoir and submerged in the liquid, the process comprising:

locating a filter having a liquid permeable filter wall within a reservoir, submerged within a liquid contained in the reservoir to define a chamber containing a portion of the liquid;

withdrawing some of the liquid from the chamber to a location outside of the reservoir, to promote a flow of the liquid contained in the reservoir through the filter wall and into the chamber;

supplying liquid under pressure to a spray assembly mounted inside of the chamber to spray the liquid under pressure from at least one orifice of the spray assembly onto said filter wall in a spray pattern that impinges upon a limited section of the filter wall comprising less than about fifteen percent of a surface area of the filter wall; and

while so supplying the liquid under pressure, moving said at least one orifice relative to the filter, thus to spray the filter wall over a sweep area at least six times the area of said limited section, thus tending to keep the filter wall free of contaminants at least over said sweep area;

wherein said moving of the at least one orifice comprises mounting the at least one orifice for movement in a first direction, and orienting the at least one orifice to produce a spray of the liquid in a direction counter to the first direction, whereby said at least one orifice is moved in the first direction as a reaction to said spray;


5,589,081 DIVIDED PHASE SEPARATOR FOR LIQUID/SOLID SEPERATION IN SLUDGE

Ronald B. Harris, 28109 Charlie Watts Rd., Livingston, La. 70754

Filed Jan. 11, 1996, Ser. No. 584,555
Int. Cl.⁶ B01D 29/05

U.S. Cl. 210—804

33 Claims



33. A method for offsetting the effects of blinding in a liquid-solid separator for separating liquids from target solids in a sludge comprising: a tank having walls extending upward from a bed, said bed and said walls having surfaces, said surfaces forming a sludge receiving cavity; a dividing wall extending upward from said bed; a liquid permeable filter positioned within said cavity for retaining target solids, said filter positioned to overlap said dividing wall; a first support means for supporting said filter over said bed and said walls, said support means providing a first free flow space between said filter and said bed and said walls; a second support means for supporting said filter over said dividing wall, said support means providing a second free flow space between said filter and said dividing wall; a first liquid removal means for removing liquids from said first free flow space; and a second liquid removal means for removing liquids from said second free flow space comprising: closing first liquid removal means prior to the introduction of sludge into said sludge receiving cavity; closing second liquid removal means prior to the introduction of sludge into said sludge receiving cavity; introducing sludge into said sludge receiving cavity; allowing sludge to stand and separate into two phases, a relatively solid free fluid phase and a remaining sludge phase; opening said first liquid removal means; and opening said second liquid removal means.

5,589,082

MICROELECTROMECHANICAL SIGNAL PROCESSOR FABRICATION


Liwei Lin; Clark T. Nguyen, both of Berkeley; Roger T. Howe, Lafayette, and Albert P. Pisano, Berkeley, all of Calif., assignors to The Regents of the University of California, Oakland, Calif.

Division of Ser. No. 298,233, Aug. 30, 1994, Pat. No. 5,537,083, which is a continuation of Ser. No. 990,582, Dec. 11, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 480,467

Int. Cl.⁶ H01L 21/00

U.S. Cl. 216—2

8 Claims



1. A method for fabrication of a microelectromechanical signal processor on a substrate, said method comprising the steps of:

- (a) fabricating a first patterned layer on said substrate;
- (b) fabricating a second patterned layer having an opening for anchoring a third patterned layer;
- (c) fabricating said third patterned layer;
- (d) fabricating a fourth patterned layer having an opening for anchoring a fifth patterned layer;
- (e) fabricating said fifth patterned layer; and
- (f) etching said fourth layer and said second layer.

5,589,083

METHOD OF MANUFACTURING MICROSTRUCTURE BY THE ANISOTROPIC ETCHING AND BONDING OF SUBSTRATES

Kun-Young Ahn; Kyung-Ho Park; Kee-Soo Nam, and Sang-Won Kang, all of Daejeon, Rep. of Korea, assignors to Electronics and Telecommunications Research Institute, Daejeon-Shi, Rep. of Korea


Filed Nov. 22, 1994, Ser. No. 346,205

Claims priority, application Rep. of Korea, Dec. 11, 1993, 93-27344; Dec. 18, 1993, 93-28479; Dec. 18, 1993, 93-28480

Int. Cl.⁶ H01L 21/00; B44C 1/22

U.S. Cl. 216—24

17 Claims



1. The method of manufacturing a microstructure by the anisotropic etching and bonding of substrates, comprising the following steps:

- (a) bonding a first substrate with a second substrate that has a different crystal orientation from the first substrate;
- (b) polishing the second substrate, the second substrate being thinner than the first substrate after the polishing step;
- (c) forming an etching protective mask on the first substrate;

forming a window in the etching protective mask so as to permit exposure of a region of the first substrate by using photolithography; etching the first substrate exposed through the window so as to form nozzles that are different from each other.


5,589,084

THIN FILM ACTUATED MIRROR ARRAY
Jeong B. Ji, Seoul, Rep. of Korea, and Gregory Um, Torrance, Calif., assignors to Daewoo Electronics Co. Ltd., Seoul, Rep. of Korea, and Aura Systems, Inc., El Segundo, Calif.
Division of Ser. No. 200,861, Feb. 23, 1994, Pat. No. 5,481,396. This application Jun. 7, 1995, Ser. No. 480,032

Int. Cl.⁶ B44C 1/22

U.S. Cl. 216—24

3 Claims



1. A method of fabricating a thin film mirror for an optical projection system comprising the steps of: providing an active matrix substrate; depositing a first layer to the substrate, the first layer including a first area corresponding to a pedestal member of the thin film mirror and a second sacrificial area corresponding to the remaining area of the thin film mirror area; treating the second sacrificial area of the first layer so as to be removable; depositing a thin film layer of metal on the first layer; depositing a thin film layer of piezoelectric material on the thin film layer of metal; depositing a second thin film layer of metal on the piezoelectric material layer; and removing the second sacrificial area of the first layer.

5,589,085

PROCESS OF MANUFACTURING A DETECTING UNIT FOR AN ELECTROLYTIC CELL WITH THIN FILM ELECTRODES


Jacob Mettes, New Hope, Pa., assignor to Meeco, Incorporated, Warrington, Pa.

Filed Aug. 4, 1995, Ser. No. 511,531

Int. Cl.⁶ C23F 1/02; G01N 27/26

U.S. Cl. 216—65

22 Claims



1. A process of manufacturing a detecting unit for an electrolytic cell with thin film electrodes comprising the steps of: (a) providing a long, narrow transparent, hollow glass tube having an inside surface, an outside surface, and an end with a rim;


5,589,087

PROCESS FOR PRODUCING A STEEL MOLD FOR CONCRETE PAVING BLOCKS WITH SPACERS
Guenter Burger, Allmendingen, Germany, assignor to Rampf Formen GmbH, Allmendingen, Germany
Filed Mar. 2, 1995, Ser. No. 397,672
Claims priority, application Germany, Mar. 8, 1994, 44 07 698.3

Int. Cl.⁶ B23K 11/14; B29C 33/40

U.S. Cl. 219—93

9 Claims



- (b) depositing a thin, noble metal film on the inside surface of the hollow glass tube;
- (c) directing a beam from a light source through the hollow glass tube to remove first and second portions of the noble metal film from the inside surface of the hollow glass tube and create first and second thin film electrodes separated by spacer areas; and
- (d) depositing an hygroscopic film on the entire inside surface of the hollow glass tube, covering completely the first and second electrodes and the spacer areas.

5,589,086

METHOD AND APPARATUS FOR ELECTRICAL DISCHARGE MACHINING WITH CONTROL OF A SERVOMECHANISM BY A POSITION LOOP AND A SPEED LOOP

Kiyoshi Sawada, Sunto-gun, and Shun'ichi Odaka, Oshino-mura, both of Japan, assignors to Fanuc Ltd., Yamanashi, Japan

PCT No. PCT/JP94/00148, § 371 Date Oct. 5, 1994, § 102(e) Date Oct. 5, 1994, PCT Pub. No. WO94/17948, PCT Pub. Date Aug. 18, 1994


PCT Filed Feb. 2, 1994, Ser. No. 313,278

Claims priority, application Japan, Feb. 5, 1993, 5-040717

Int. Cl.⁶ B23H 1/02; 7/18; 7/20

U.S. Cl. 219—69.16

17 Claims



1. A method for controlling electric discharge machining comprising:

- (a) detecting an electric discharge machining condition of a gap between a tool electrode and a workpiece;
- (b) producing speed commands for input into a speed loop from a deviation between the detected value of said electric discharge machining condition and a target value of said electric discharge machining condition;
- (c) correcting said speed commands with a position loop based upon a position deviation between a target position of said tool electrode and an actual position of said tool electrode;
- (d) driving a servomechanism in response to the corrected speed commands to relatively move said tool electrode with respect to said workpiece so that a detected value of said electric discharge machining condition agrees with a target value of said electric discharge machining condition.

5,589,088

METHOD OF REGULATING DC CURRENT IN RESISTANCE WELDERS
Reno C. Boilard, Windsor, Canada, assignor to Medar, Inc., Farmington Hills, Mich.

Filed Jun. 20, 1995, Ser. No. 493,803


Int. Cl.⁶ B23K 11/24

U.S. Cl. 219—110

8 Claims

1. A method of controlling a resistance welder of the type having a transformer provided with a primary coupled through a switch to a source of alternating current electrical power, a secondary, a weld controller for controlling the switch and means for delivering DC current from the transformer secondary to a workpiece to be welded, comprising the steps of:

- (A) storing in a look up table memory of the controller a set of data correlating a set of firing delay parameters with a set of DC current values representing the percentage of maximum DC current that is available to be delivered to the workpiece at a given power factor for the weld circuit, wherein the stored set of DC current values is a nonlinear function of the actual values of the DC current delivered to the workpiece;
- (B) retrieving from the lookup table memory a firing delay parameter;
- (C) controlling the switch in accordance with the firing delay parameter retrieved in step (B) to deliver a pulse of weld energy to the workpiece;
- (D) incrementing a counter to reflect the delivery of the weld energy pulse; and
- (E) repeating steps (C) and (D) until the count of the counter corresponds to a prescribed number of weld cycles.



5,589,089

YAG LASER MACHINE WITH SAFETY SYSTEM FOR BEAM PATH ADJUSTMENT


Akira Uesugi, Noda, Japan, assignor to Miyachi Technos Corporation, Chiba, Japan

Filed Oct. 14, 1994, Ser. No. 323,521

Claims priority, application Japan, Oct. 19, 1993, 5-261100
Int. Cl.⁶ B23K 26/00


U.S. Cl. 219—121.6

2 Claims




1. YAG laser processing machine characterized by a YAG laser generator; a guide beam generator for generating a visible guide beam used for optical axis adjustment of said YAG laser generator; detachable means for preventing the reflected beam portion of the laser beam from leakage outside the machine; a safety means interlocked with detaching movement of said detachable means for holding said YAG laser generator in its stopped state; detachable guide beam visual inspection means, comprising a fiber scope, mounted for optical axis adjustment operation for visual inspection of said guide beam; a safety means interlocked with the mounting movement of said detachable guide beam visual inspection means for holding said YAG laser generator in its stopped state when the inspection means is operably attached to the machine.

5,589,090
LASER CUTTING APPARATUS WITH MEANS FOR MEASURING CUTTING GROOVE WIDTH
Byung-Jun Song, 1209-1404, Jukong Apt., Chulsan-dong, Kwangmyung-city, Kyungki-do, Rep. of Korea
Filed Jan. 23, 1995, Ser. No. 376,366
Claims priority, application Rep. of Korea, Jan. 31, 1994, 94-1766; Feb. 16, 1994, 94-2713
Int. Cl.⁶ B23K 26/00
U.S. Cl. 219—121.62 15 Claims



1. A laser cutting apparatus including a laser oscillator for generating a laser beam and a laser condenser lens for condensing said laser beam from said laser oscillator to make a cutting groove of predetermined width into an object being processed, said laser cutting apparatus comprising:
means for adjusting distance between said object and said laser condenser lens for adjusting the width of said laser beam irradiating upon said object;
relative-speed regulating means for controlling the relative speed of said object with respect to said laser beam to regulate the irradiating time of said laser beam upon said object;
cutting-width measuring means for measuring of an upper portion and a lower portion of said cutting groove; and
controlling means for comparing the upper cutting width and the lower cutting width measured by said cutting-width measuring means, of said cutting groove with a standard dimension, and controlling said distance adjusting means and said relative-speed regulating means in accordance with the result of comparison.


5,589,091
GLOW PLUG WITH PRESTRESSED CONTACT SURFACES
Helmut Müller, Besigheim-Ottmarshelm, Germany, assignor to BERU Ruprecht GmbH & Co. KG, Germany
Filed Oct. 17, 1994, Ser. No. 325,950
Claims priority, application Germany, Oct. 15, 1993, 43 35 292.8
Int. Cl.⁶ F23Q 7/00; H05B 3/10
U.S. Cl. 219—270 19 Claims



1. Glow plug comprising a hollow body in which a ceramic heating rod, having a rod body formed entirely of sintered ceramic material, is disposed with the heating rod axially projecting from a first end of the hollow body; wherein a sintered-in heating element

is embedded within the sintered ceramic material of the unitary rod body so as to be fully enclosed by said sintered ceramic material, and wherein the sintered-in heating element is directly connected to power supply terminals by pressure contact therewith via contact surfaces integrally joined with the ceramic material of the rod body at an external surface of the rod body.

5,589,092
CONTROL CIRCUIT FOR CONTROLLING THE OPERATION OF A MULTIPURPOSE ELECTRONIC COOKER
Kwei-Tang Chang, No. 14, Lane 54, Luong Chuan St., Pan-chiao City, Taipei Hsien, Taiwan
Filed Mar. 17, 1995, Ser. No. 405,910
Int. Cl.⁶ H05B 1/02
U.S. Cl. 219—506 6 Claims




1. A multipurpose electronic cooker control circuit, comprising:
a rectifier filter circuit;
an electronic switch for ON/OFF control of an electric heater;
a comparator circuit for temperature control;
a single chip main control unit;
a time and temperature display unit;
a keyboard control circuit;
a buzzer;
wherein the rectifier filter circuit has first and second output terminals, the first output terminal of said rectifier filter circuit is respectively connected to first input terminals of said electronic switch, said comparator circuit, said time and temperature display unit, said keyboard control circuit, and said buzzer, the second output terminal of said rectifier filter circuit is connected to a first input terminal of the single chip main control unit;
wherein the single chip main control unit has first, second, third, and fourth output terminals, the first output terminal of said single chip main control unit is connected to a second input terminal of said electronic switch, the second output terminal of said single chip main control unit is connected to a second input terminal of said comparator circuit, the third output terminal of said single chip main control unit is connected to a second input terminal of said time and temperature display unit, the fourth output terminal of said single chip main control unit is connected to an input terminal of said buzzer;
wherein an output terminal of said comparator circuit is connected to a second input terminal of said single chip main control unit; and
wherein an output terminal of said keyboard control circuit is connected to a third input terminal of said single chip main control unit.

5,589,093
MICROWAVE HEATING CHAMBER FOR VENDING MACHINES
Jey-Cherng Chen, Hsin Chu, Taiwan, assignor to Electronics Research & Service Organization, Hsinchu, Taiwan
Filed Jul. 20, 1995, Ser. No. 504,731
Int. Cl.⁶ H05B 6/80 18 Claims

U.S. Cl. 219—679

18 Claims



1. A microwave heating chamber for use in a vending machine comprising:
a cylindrically shaped chamber having a chamber wall and a longitudinal axis, said chamber is equipped with an upper mounting flange at its upper extremity and a lower mounting flange at its lower extremity, said upper mounting flange being adapted to receive an object transported from a storage compartment, said lower mounting flange being adapted to deliver said object to a discharge chute of said vending machine;
a retractable upper end plate for sealingly engaging the inside peripheral area of said chamber when positioned perpendicular to the longitudinal axis of said chamber, said upper end plate being controlled and positioned by a first mounting means and a first retracting means through a first slot opening in the chamber wall of said heating chamber for moving horizontally into and out of said chamber such that when said plate is in a fully extended position, it substantially seals off the upper end of said chamber;
a retractable lower end plate for sealingly engaging the inside peripheral area of said chamber when positioned perpendicular to the longitudinal axis of said chamber, said lower end plate being controlled and positioned by a second mounting means and a second retracting means through a second slot opening in the chamber wall of said chamber for moving horizontally into and out of said chamber such that when said lower end plate is in a fully extended position, it substantially seals off the lower end of said chamber and forms a substantially sealed chamber cavity when said upper end plate is also in a fully extended position;
said chamber wall and said retractable upper end plate and lower end plate being made of a material that is substantially not transmissive or absorptive to microwave energy;
a retractable object holding plate for supporting an object to be heated by microwave energy positioned parallel to said upper end plate and said lower end plate, said object holding plate being controlled and positioned by a third mounting means and retracting means through a third slot opening in the chamber wall of said chamber such that when said holding plate is in a fully extended position, it holds the object to be heated at a position of maximum microwave energy;
said retractable object holding plate being made of a material that is transmissive but not absorptive to microwave energy;
a microwave generator sealingly engaging the chamber wall of said heating chamber through a mounting means and is in microwave transmissible communication with the chamber cavity of said chamber to supply microwave energy, and
a control means for controlling said first, second and third retracting means and said microwave generator to enable the supply of microwave energy to the chamber cavity for heating an object on demand.

5,589,094

MICROWAVE OVEN EMPLOYING THERMOPILE TYPE SENSOR

Jong U. Bu, Seoul, Rep. of Korea, assignor to Goldstar Co., Ltd., Seoul, Rep. of Korea


Filed Mar. 20, 1995, Ser. No. 406,507

Claims priority, application Rep. of Korea, Mar. 18, 1994, 5485/1994

Int. Cl.⁶ H05B 6/68

U.S. Cl. 219-711

10 Claims



1. A microwave oven comprising:

- an outer case;
- a cavity having an upper and a lower case facing each other, and a right and a left side cases facing each other, and an opening in the upper case;
- a table mounted on the lower case opposite the opening, wherein the table is adapted for placing food for cooking thereon;
- a thermopile type sensor mounted in the opening of the cavity for sensing a radiation temperature of food placed on the table using an absorption rate difference between a black body on a membrane of the thermopile sensor and a non-black body on radiation heating;
- a magnetron device mounted on one of the side cases of the cavity for generating microwaves for the cavity;
- a cooling fan mounted on the side case of the cavity under the magnetron device for cooling the air in the cavity;
- an A/D converter for A/D converting an output value of the thermopile type sensor;
- a microcomputer for receiving an output of the A/D converter and controlling automatic cooking according to the output of the A/D converter; and
- a power supply part for receiving the output of the microcomputer and operating the magnetron device and the cooling fan to make an automatic cooking of the food placed on the table possible according to the output of the microcomputer.

5,589,095

COOLANT/LUBRICANT FOR MACHINING OPERATIONS

Lin-Sen Yuan, Westlake Village, Calif., and Lu Yuan, Shanghai, China, assignors to Hughes Aircraft Company, Los Angeles, Calif.

Filed Sep. 30, 1994, Ser. No. 315,787

Int. Cl.⁶ C10M 173/02

U.S. Cl. 508-168

10 Claims

1. A high-load, high-stress machining coolant and lubricant composition, consisting essentially of a suspension of:
 - (a) about 8 to 15 wt % molybdenum disulfide;
 - (b) about 2 to 6.6 wt % of a sodium fatty-acidulate soap;
 - (c) about 6 to 12 wt % liquid polytetrafluoroethylene suspension; and
 - (d) about 66.4 to 84 wt % water, said water being in addition to such water as is intrinsically associated with said sodium fatty-acidulate soap and said liquid polytetrafluoroethylene suspension.

5,589,096

MAGNETIC MATERIAL FOR HIGH FREQUENCIES

Takehiro Konolke, Ashiya; Hiroshi Marusawa, Neyagawa; Hiroshi Takagi, and Kunisaburo Tomono, both of Ohtsu, all of Japan, assignors to Murata Manufacturing Co., Ltd., Japan


Filed Jul. 20, 1994, Ser. No. 277,909

Claims priority, application Japan, Jul. 20, 1993, 5-179150; Jun. 29, 1994, 6-147958

Int. Cl.⁶ C04B 35/44

U.S. Cl. 252-62.57

4 Claims



1. A magnetic material for high frequencies consisting essentially of a main component which contains Sn and Al and has a composition expressed by the general formula:



where x, y, z and w take respective values within the following ranges: $0.10 \leq x \leq 0.60$, $0.00 < y \leq 0.20$, $0.20 \leq z \leq 0.60$, $4.88 \leq w \leq 4.92$, and an additional component of CeO_2 incorporated therein in an amount of not less than 0.1 percent by weight but not more than 0.5 percent by weight.

5,589,097

METHOD FOR PREPARING MAGNETITE MAGNETIC POWDER

Yoshito Nihira, Chiba, Japan; Haoren Zhuang, Cincinnati, Ohio, and Takeshi Nomura, Chiba, Japan, assignors to TDK Corporation, Tokyo, Japan


Filed Dec. 23, 1994, Ser. No. 362,865

Claims priority, application Japan, Dec. 24, 1993, 5-347945; Dec. 27, 1993, 5-353918; May 25, 1994, 6-135004

Int. Cl.⁶ C04B 35/26

U.S. Cl. 252-62.59

23 Claims



1. A method for preparing a magnetite magnetic powder comprising the steps of:
 - using ferrous chloride as a starting material, and
 - roasting the starting material in a steam-containing atmosphere consisting essentially of a non-oxidizing gas and steam for pyrolysis thereof, thereby forming a magnetite magnetic powder having a saturation magnetization σ_s of 82 to 92 emu/g and a magnetite phase content of at least 90% by weight.

5,589,098

COMPOSITIONS OF DIFLUOROMETHANE AND TETRAFLUOROETHANE


Mark B. Shiflett, Newark, Del., and Donald B. Bivens, Kennett Square, Pa., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation of Ser. No. 143,761, Nov. 1, 1993, abandoned, which is a continuation of Ser. No. 963,310, Oct. 16, 1992, Pat. No. 5,290,466, which is a continuation-in-part of Ser. No. 787,872, Oct. 31, 1991, abandoned, and a continuation of Ser. No. 871,673, Apr. 21, 1992, abandoned. This application May 8, 1995, Ser. No. 436,777

Int. Cl.⁶ C09K 5/04

U.S. Cl. 252-67

6 Claims



1. A mixture consisting essentially of a substantially constant boiling, near-azeotropic composition consisting of 1-6 weight percent difluoromethane and 94-99 weight percent 1,1,2,2-tetrafluoroethane, wherein when the temperature is adjusted to about 25° C., the composition boils at a vapor pressure of about 78-91 psia, and wherein when 50 weight percent of the composition is evaporated, the vapor pressure of the composition changes by 10 percent or less.

2. A substantially constant boiling, near-azeotropic composition consisting essentially of difluoromethane, 1,1,2,2-tetrafluoroethane and 1,1,1,2-tetrafluoroethane, in the following proportions at about 25° C.: 4 weight percent difluoromethane, 1-95 weight percent 1,1,2,2-tetrafluoroethane and 1-95 weight percent 1,1,1,2-tetrafluoroethane, said composition boiling at a vapor pressure of about 86.0-107.9 psia; 3 weight percent difluoromethane, 1-96 weight percent 1,1,2,2-tetrafluoroethane and 1-96 weight percent 1,1,1,2-tetrafluoroethane, said composition boiling at a vapor pressure of about 83.6-105.5 psia; 2 weight percent difluoromethane, 1-97 weight percent 1,1,2,2-tetrafluoroethane and 1-97 weight percent 1,1,1,2-tetrafluoroethane, said composition boiling at a vapor pressure of about 81.2-103.0 psia; or 1 weight percent difluoromethane, 1-98 weight percent 1,1,2,2-tetrafluoroethane and 1-98 weight percent 1,1,1,2-tetrafluoroethane, said composition boiling at a vapor pressure of about 78.8-100.6 psia, wherein when 50 weight percent of the composition is evaporated, the vapor pressure of the composition changes by 10 percent or less.

5,589,099

LOW FOAMING RINSE AGENTS COMPRISING ETHYLENE OXIDE/PROPYLENE OXIDE BLOCK COPOLYMER

Burton M. Baum, Mendota Heights, Minn., assignor to Ecolab Inc., St. Paul, Minn.

Filed Apr. 20, 1993, Ser. No. 49,973

Int. Cl.⁶ C11D 1/66

U.S. Cl. 510-514

19 Claims

1. A food grade rinse agent composition comprising approved food additive ingredients, suitable for dilution to form an aqueous rinse, the composition comprising:

- (a) about 5 to 40 wt-% of a nonionic block copolymer composition, comprising ethylene oxide and propylene oxide, having

a molecular weight between 10,000 and 15,000 and a cloud point, measured using a 1 wt-% aqueous solution, greater than 100° C.;

(b) about 0.2 to 25 wt-% of a food additive defoamer composition; and

(c) up to about 95 wt-% of a water soluble diluent composition.

5,589,100

DICHROIC AZO DYES


Robert P. Grasso; Michael K. O'Brien, both of Wilmington, Del., and Paul J. Shannon, Exton, Pa., assignors to Hercules Incorporated, Wilmington, Del.

Continuation of Ser. No. 218,001, Mar. 25, 1994, abandoned, which is a division of Ser. No. 535,268, Jun. 8, 1990, Pat. No. 5,326,865. This application Mar. 20, 1996, Ser. No. 618,937

Int. Cl.⁶ C09K 19/00; 19/52

U.S. Cl. 252-299.01

8 Claims



1. A liquid crystal display comprising two substrates having disposed there between a guest-host composition comprising a liquid crystal host solvent and, as the guest, an arylazo or poly(arylazo) dichroic dye having one to five arylazo groups wherein the aryl radicals are selected from the group consisting of naphthyl, anthracyl and phenyl radicals, wherein at least one core radical is selected from a naphthyl or anthracyl radical and having at least one 2,3-dihydro-1, 3-dialkyl perimidine substituent.

5,589,101

LIQUID CRYSTAL FIBER ARRAY FOR OPTICAL LIMITING OF LASER PULSES AND FOR EYE/SENSOR PROTECTION


Iam-Choon Khoo, State College, Pa., assignor to The Penn State Research Foundation, University Park, Pa.

Filed Apr. 5, 1995, Ser. No. 417,332

Int. Cl.⁶ C09K 19/00; G02F 1/13; G02B 6/00

U.S. Cl. 252-299.01

11 Claims



1. A liquid crystal fiber array comprising:

a unitary body having incident and transmitting faces and including a plurality of capillary passages extending between said incident and transmitting faces;
a liquid phase liquid crystal material positioned in each of said capillary passages, said capillary passages having diameters in a range of about 2 microns to 500 microns; and
optically transparent closures positioned on said incident and transmitting faces for retaining said liquid phase liquid crystal material within said capillary passages, said liquid crystal material exhibiting an optical limiting effect upon incidence of high intensity optical energy.

5,589,102


BENZENE DERIVATIVES, AND LIQUID-CRYSTALLINE MEDIUM

Ekkehard Bartmann, Erzhausen, and Kazuaki Tarumi, Seebel, both of Germany, assignors to Merck Patent Gesellschaft mit beschränkter Haftung, Germany
Filed Sep. 5, 1995, Ser. No. 523,240

Claims priority, application Germany, Sep. 6, 1994, 44 31 737.9

Int. Cl.⁶ C09K 19/52; 19/30; C07C 25/13; G02F 1/13
U.S. Cl. 252—299.01 17 Claims

1. A benzene derivative of formula I



wherein

R is an alkyl or alkenyl radical having 1 to 15 carbon atoms which is optionally monosubstituted by CN or CF₃ or optionally at least monosubstituted by halogen, one or more CH₂ groups in these radicals optionally independently replaced by —O—, —S—,



—CO—, —CO—O—, —O—CO— or —O—CO—O— that O atoms are not linked directly to one another,

A¹ and A² are each independently

(a) a trans-1,4-cyclohexylene radical in which one or more non-adjacent CH₂ groups is optionally replaced by —O— and/or —S—,

(b) a 1,4-phenylene radical optionally monosubstituted or disubstituted by F or CN, and in which one or two CH groups is optionally replaced by N,

(c) 1,4-cyclohexenylene,

(d) a 1,4-bicyclo[2.2.2]octylene, piperidine-1,4-diyl, naphthalene-2,6-diyl, decahydro-naphthalene-2,6-diyl or 1,2,3,4-tetrahydronaphthalene-2,6-diyl radical, where the radicals (a) to (c) are optionally monosubstituted or polysubstituted by CN or fluorine,

Z¹ and Z² are each independently —CO—O—, —O—CO—, —CH₂O—, —OCH₂—, —CH₂CH₂—, —CH=CH—, —C≡C— or a single bond, or one of Z¹ and Z² is alternatively —(CH₂)₄— or —CH=CH=CH₂CH₂—,

L¹ and L² are each independently H or F,

m and n are each independently 0 or 1, and


X is halogenated C₁₋₆-alkyl, C₁₋₆-alkoxy, C₂₋₆-alkenyl, F or Cl.

5,589,103
MESOMORPHIC COMPOUND, LIQUID CRYSTAL COMPOSITION CONTAINING SAME, AND LIQUID CRYSTAL DEVICE USING SAME

Yoko Yamada, Ischara; Takao Takiguchi, Tokyo; Takashi Iwaki, Machida; Takeshi Togano, Yokohama; Shinichi Nakamura, Ischara, and Ikuo Nakazawa, Atsugi, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Jan. 4, 1994, Ser. No. 177,144

Claims priority, application Japan, Jan. 8, 1993, 5-001974; Dec. 14, 1993, 5-312924



Int. Cl.⁶ C09K 19/34; 19/32; C07D 239/02; G02F 1/13
U.S. Cl. 252—299.61 29 Claims




1. A mesomorphic compound represented by the following formula (I):



wherein R¹ and R² independently denote Q—Y¹—(CH₂)_m—Y²— or R¹, at least one of R¹ and R² being Q—Y¹—(CH₂)_m—Y²— wherein Q denotes



where X¹, X², X³, X⁴ independently denote H, F, CH₃, or CF₃; Y¹ denotes a single bond, —OCH₂—, —COO— or —OCO—; Y² denotes a single bond, —CH₂O—, —COO— or —OCO—; m is an integer of 3–16; and R³ is H, F, CF₃,




a linear or branched alkyl group having 1–18 carbon atoms capable of including at least one —CH₂— group which can be replaced with —O—, —S—, —CO—, —CH=CH—, —C≡C—, or




provided that heteroatoms are not adjacent to each other, and capable of including at least one H which can be replaced with F; or a cyclized alkyl group having 1–11 carbon atoms capable of including at least one —CH₂— group which can be replaced with —O—, —S—, —CO—, or —CH=CH—, provided that heteroatoms are not adjacent to each other and capable of including at least one H which can be replaced with F; and

A denotes —A¹—Z—A²— or —A¹—A²—Z—A³— wherein A¹, A², and A³ independently denote



where X⁵ and X⁶ independently denote H, F, CH₃, or CF₃, at least one of A¹, A² and A³ being any one of



and Z denotes a single bond, —C≡C—, —CH=CH—, —COO—, —OCO—, —COS— or —CH₂O—.

5,589,104


ELECTROPHORESIS SEPARATION GEL AND A METHOD FOR PREPARING AN ELECTROPHORESIS SEPARATION GEL

Gregory S. Bambeck, 1890 Georgetown Rd., Hudson, Ohio 44236

Filed Dec. 30, 1993, Ser. No. 177,271

Int. Cl.⁶ B01J 13/00; C25B 1/00
U.S. Cl. 252—315.1

8 Claims



1. A gel for use in an electrophoresis separation comprising: a plurality of gradients within said gel; each said gradient comprising a polyacrylamide matrix and a buffer;

wherein said polyacrylamide of one said gradient has a different and preselected chain length as compared to at least one other said gradient;

wherein said polyacrylamide matrix is a bi-functionally cross-linked acrylamide; and said buffer has a buffering capacity pH of from about 7.5 to about 9.5.

5,589,105

HETEROGENEOUS POLYMERIZATION IN CARBON DIOXIDE

Joseph M. DeSimone, Elise E. Maury, both of Chapel Hill; James R. Combes, Carboro, and Yusuf Z. Mencelglu, Chapel Hill, all of N.C., assignors to The University of North Carolina at Chapel Hill, Chapel Hill, N.C.

Division of Ser. No. 378,550, Jan. 25, 1995, Pat. No. 5,506,317, which is a division of Ser. No. 299,516, Sep. 1, 1994, Pat. No. 5,451,633, which is a division of Ser. No. 99,905, Jul. 30, 1993, Pat. No. 5,312,882. This application May 18, 1995, Ser. No. 443,478

Int. Cl.⁶ B01F 17/00; 1/00

U.S. Cl. 252—351

22 Claims

1. A mixture comprising carbon dioxide and a surfactant, wherein said surfactant comprises a carbon dioxide soluble segment and a CO₂-phobic group covalently linked to said carbon dioxide soluble segment, wherein said carbon dioxide soluble segment further comprises a fluoropolymer and wherein said surfactant is a copolymer selected from the group consisting of a graft copolymer and a block copolymer.

5,589,106

CARBON STEEL CORROSION INHIBITORS

Sang-Hea Shim, Naperville; Dennis P. Bakalik, Woodridge; Donald A. Johnson, Batavia; Bo Yang, and Frank F. Lu, both of Naperville, all of Ill., assignors to Nalco Chemical Company, Naperville, Ill.

Filed Feb. 14, 1995, Ser. No. 388,546


Int. Cl.⁶ C23F 11/18; 11/173

U.S. Cl. 252—387


11 Claims

1. A method for the control of corrosion and scale on the mild steel surfaces of an industrial cooling water system which comprises maintaining in the cooling water system:

- 5–70 ppm by weight hydroxycarboxylic acid;
- 10–100 ppm by weight of a water soluble silicate salt; and
- 0–50 ppm by weight of a water soluble polymeric dispersant having the formula:



wherein Q is selected from the group consisting of —OY, wherein Y is H, alkali metal or ammonium, or the group:



wherein "R₂" is hydrogen or methyl, "R₁" is hydrogen or alkyl and R is alkylene or phenylene, and "X" is sulfonate, phosphonate(poly)hydroxyl, (poly)carboxyl or carbonyl and combinations thereof, said polymer having a molecular weight of from 7,000–100,000.

5,589,107

METHOD AND COMPOSITION FOR INHIBITING CORROSION

Clarence Scheurman, III, Westlake, Ohio, assignor to Applied Specialties, Inc., Avon Lake, Ohio


Filed Aug. 15, 1994, Ser. No. 291,589

Int. Cl.⁶ C23F 11/14; C23C 22/00

U.S. Cl. 252—392

10 Claims

1. A composition which is useful for inhibiting corrosion of ferrous metal surfaces in an aqueous system comprising a first component and a second component, said first component being selected from the group consisting of carbonylhydrazide, water-soluble salts of carbonylhydrazide, hydrazine, water-soluble salts of hydrazine, and mixtures of any of the foregoing, said second component being selected from the group consisting of certain hydroxylamine compounds or mixtures thereof, said certain hydroxylamine compounds having the formula



where R_1 , R_2 , and R_3 are either the same or different and are selected from the group consisting of hydrogen and lower alkyl containing 1 to about 6 carbon atoms, or a water-soluble salt thereof; the weight ratio of the first component to the second component being a corrosion inhibiting ratio between about 4:1 and about 1:4.

5,589,108

SOLUBLE ALKOXY-GROUP SUBSTITUTED AMINO BENZENESULFONIC ACID ANILINE CONDUCTING POLYMERS

Shigeru Shimizu, Takashi Saitoh, Masashi Uzawa, and Yasuyuki Takayanagi, all of Yokohama, Japan, assignors to Nitto Chemical Industry Co., Ltd., Tokyo, Japan


Filed Dec. 22, 1994, Ser. No. 361,577

Claims priority, application Japan, Dec. 29, 1993, 5-353698; Apr. 4, 1994, 6-089091; Jul. 13, 1994, 6-183882; Aug. 1, 1994, 6-199051

Int. Cl.⁶ H01B 1/00; 1/12

U.S. Cl. 252—500

14 Claims



1. An aniline conducting polymer comprising, as a repeating unit, at least one member selected from the group consisting of an alkoxy group-substituted aminobenzenesulfonic acid, an alkali metal salt of alkoxy group-substituted aminobenzenesulfonic acid, an ammonium salt of alkoxy group-substituted aminobenzenesulfonic acid and a substituted ammonium salt of alkoxy group-substituted aminobenzenesulfonic acid in an amount of about 100%, and is a solid having a weight average molecular weight of about 1900 or more at room temperature and being soluble in acidic, basic and neutral aqueous solutions and organic solvents.

5,589,109

METHOD FOR PRODUCING A CATHODE MATERIAL CONTAINING SILVER AND BISMUTH

Joseph L. Passaniti, Fitchburg; El-Sayed A. Megahed, Madison, both of Wis., and Nuri A. Zreiba, Tripoli, Libyan Arab Jamahiriya, assignors to Rayovac Corporation, Madison, Wis.


Division of Ser. No. 75,889, Jun. 14, 1993, Pat. No. 5,389,469.

This application Feb. 10, 1995, Ser. No. 387,296

Int. Cl.⁶ H01B 1/00; C01G 5/00; 29/00

U.S. Cl. 252—518

9 Claims



1. A method for producing a cathode material for use in an electrochemical cell, said method comprising the steps of: (a) reacting together a reaction mixture, at a temperature between 40 degrees C. and the boiling point of said reaction mixture, for at least two hours, thereby obtaining a solid reaction product, the reaction taking place under reducing conditions, said reaction mixture comprising (i) an aqueous alkaline reaction medium, (ii) AgO comprising particles having a size of about 16 to about 62 microns, and (iii) a bismuth containing moiety selected from the group consisting of bismuth, a mixture of bismuth and sulfur, bismuth oxide, bismuth sulfate, bismuth sulfite, bismuth sulfide, and bismuth nitrate, said bismuth containing moiety comprising between about five percent and about fifteen percent by weight of the combination of said AgO and said moiety; and (b) recovering, as said cathode material, the solid reaction product so produced.

5,589,110

CONTAINER FOR LIQUID METAL ORGANIC COMPOUND

Takashi Motoda; Shoichi Karakida; Nobuaki Kaneno, and Shigeki Kageyama, all of c/o Mitsubishi Denki Kabushiki Kaisha Hikari Micro-ha Device Kenkyusho, 1 Mizuhara 4-chome, Itami-shi, Hyogo 664, Japan

Division of Ser. No. 131,529, Oct. 4, 1993, Pat. No. 5,496,408.

This application Sep. 25, 1995, Ser. No. 533,462

Claims priority, application Japan, Nov. 20, 1992, 4-335049; Feb. 12, 1993, 5-023121; Mar. 30, 1993, 5-071381


Int. Cl.⁶ B01F 3/04

U.S. Cl. 261—61

2 Claims

1. A metal organic compound container apparatus for containing a liquid metal organic compound, receiving a carrier gas, and producing a carrier gas stream saturated with vapor of the metal organic compound comprising:

a container for containing a liquid metal organic compound; an inlet pipe for introducing a carrier gas into said container; a first flow rate controller connected to said inlet pipe for controlling carrier gas flow into said inlet pipe; an exhaust pipe for exhausting the carrier from said container; a second flow rate controller connected to said exhaust pipe for controlling flow through said exhaust pipe; and adjusting pipes slidably provided at respective ends of said inlet pipe and said exhaust pipe for positioning of the inlet and the exhaust pipe above and spaced from a surface of a metal organic compound in said container.



5,589,111

POLYIMIDE PRECURSOR COMPOSITION FOR EXTRUSION MOLDING OF POLYIMIDE, PROCESS FOR PREPARING IT, AND PROCESS FOR PREPARING MOLDED ARTICLES OF POLYIMIDE

Hiroshi Haruta, and Takehiko Takahashi, both of Chiba, Japan, assignors to Chisso Corporation, Osaka, Japan


Filed May 11, 1995, Ser. No. 439,142

Claims priority, application Japan, May 13, 1994, 6-124150

Int. Cl.⁶ B29B 9/10; B29C 47/88

U.S. Cl. 264—8

19 Claims



1. A polyimide precursor composition for extrusion molding of a polyimide which comprises 30 to 45% by weight of a polyimide precursor, 0.1 to 5% by weight of a poor solvent having a low solubility for the polyimide precursor, and 35 to 69.9% by weight of a good solvent having a high solubility for the polyimide precursor.

3. A process for preparing a polyimide precursor composition for extrusion molding of a polyimide which comprises the steps of placing a poor solvent having a low solubility for a polyimide precursor in a mixer equipped with a stirrer having a stirring blade and a disc above the stirring blade, forming high-speed solvent layers of the poor solvent on the stirring blade and an inner wall of the mixer by rotating the stirring blade and the disc at a velocity of 100 rpm or more such that the upper surface of the disc, which is below the surface of the poor solvent when the disc is at rest, is above the level of the solvent when rotated at high speed, and then pouring in a thin flow state, onto the rotating disc, the polyimide precursor solution obtained by reacting (a) an aromatic tetracarboxylic dianhydride or its derivative with (b) an aromatic diamine or its derivative in a good solvent having a high solubility for the polyimide precursor, whereby the polyimide precursor solution is dispersed in the high speed solvent layers of the poor solvent by the centrifugal force of the disc to deposit (c) the polyimide precursor.

7. A process for preparing molded articles of a polyimide which comprises the steps of melting and extruding, at 50° to 100° C., a polyimide precursor composition for extrusion molding of polyimide comprising 30 to 45% by weight of (c) a polyimide precursor obtained by reacting (a) an aromatic tetracarboxylic dianhydride or its derivative with (b) an aromatic diamine or its derivative in a good solvent having a high solubility for the polyimide precursor and then depositing the resultant polyimide precursor (c) in a poor solvent having a low solubility for the polyimide precursor, 0.1 to 5% by weight of the poor solvent, and 35 to 69.9% by weight of the good solvent, and then heating the molded composition at 250° to 500° C. to imitate the same.

5,589,112

CONSTRUCTING A HIGH DENSITY CELL CULTURE SYSTEM

Glenn F. Spaulding, Houston, Tex., assignor to The United States of America as represented by the Administrator of the National Aeronautics and Space Administration, Washington, D.C.


Division of Ser. No. 996,263, Dec. 23, 1992, Pat. No.

3,330,908. This application Apr. 13, 1994, Ser. No. 227,827

Int. Cl.⁶ B29C 67/20; B23K 26/10

U.S. Cl. 264—413

5 Claims



1. A method for constructing a rotatable culture vessel for containing a liquid culture medium, and defining an annular culture chamber, for use with conventional laboratory roller devices, the method comprising:

subjecting a one piece, self-supporting and substantially rigid plastic molded annularly shaped housing having an inner cylindrically shaped wall and an outer cylindrically shaped wall forming therebetween an annular chamber disposed about a common longitudinal axis and an annular transverse end wall so as to have an open bore through said housing to bombardment means for producing microperforations through said inner and outer walls while rotating and moving the housing relative to the bombardment means to develop said microperforations along the length and about the periphery of said walls where such microperforations are sized for admitting oxygen in the atmosphere to the annular chamber while retaining the liquid culture media in the annular chamber.

5,589,113

PROCESS OF INVERTING AN ARTICLE OR AIR BAG

Rick J. Frye, Miamisburg; Jon T. Mitts, and Ron Rufener, both of Milford, all of Ohio, assignors to MIM Industries, Inc., Miamisburg, Ohio

Filed May 6, 1994, Ser. No. 239,327

Int. Cl.⁶ B29C 69/00

U.S. Cl. 264—40.5

16 Claims

1. A method of operating on an article defining a cavity comprising the steps of:

(a) inverting the article; and
(b) moving the entire article to cause the article to flatten.

5,589,114


TEMPERATURE REGULATING SYSTEM, METHOD AND APPARATUS

Rowland F. Evans, 25 Dunlin Drive, Featherstone WV10 7TC Staffordshire, United Kingdom
Division of Ser. No. 50,409, May 17, 1993, Pat. No. 5,452,999.
This application Jun. 2, 1995, Ser. No. 460,659
Claims priority, application United Kingdom, Nov. 16, 1990, 9025015

Int. Cl.⁶ B29C 33/02

U.S. Cl. 264—40.6

13 Claims



1. A method to maintain the temperature of a mould of a plastic injection moulding machine within a predetermined temperature range, the machine having cooperating closable moulds heated by plastic injection material supplied to the mould during successive machine cycles, a mould having a conduction circuit for circulation of coolant to remove excess heat introduced by said material, a coolant inflow duct and a coolant discharge duct connected to the conduction circuit, one of the inflow and discharge ducts including at least one valve having an open state allowing a maximum volumetric rate of flow of coolant and a closed state allowing a minimum volumetric rate of flow of coolant, the method comprising the steps of: continuously performing working cycles including closing together the moulds, and initiating during a cycle a first term in which the valve is in the closed state and a second term in which the valve is in the open state, characterized by cycle stage response means, by terminating said first term in dependence upon said response means so that the first term is the same for each cycle, and by terminating the said second term in accordance with a mould temperature measurement taken before the end of said first term.


5,589,115

METHOD FOR MAKING FIBER-REINFORCED CERAMIC MATRIX COMPOSITE

Diana L. Sherwood, Wellsville, N.Y., assignor to Corning Incorporated, Corning, N.Y.
Continuation of Ser. No. 121,413, Nov. 16, 1987, abandoned.
This application Jan. 23, 1990, Ser. No. 468,687
Int. Cl.⁶ C04B 33/36; B05D 3/06

U.S. Cl. 264—60

19 Claims



1. A method for the manufacture of a fiber-reinforced ceramic matrix composite article comprising the steps of:

- combining a particulate ceramic material and a binder material into a mixture and forming the mixture into a ceramic sheet;
- providing a fiber reinforcement material consisting essentially of a sheet of refractory inorganic fibers wherein the fibers are disposed in open array;
- combining the ceramic sheet and the fiber sheet to provide a multilayer preform comprising at least one layer consisting of the fiber sheet and at least one layer consisting of ceramic sheet; and
- applying heat and pressure to the preform to consolidate it into a unitary, substantially void-free, fiber-reinforced ceramic matrix composite article.

5,589,116

PROCESS FOR PREPARING A SILICON CARBIDE SINTERED BODY FOR USE IN SEMICONDUCTOR EQUIPMENT

Shoichi Kojima, Tokyo; Kazuhiro Minagawa, Amagasaki; Haruyuki Kano, Ibaraki-ken; Tadashi Miyazaki, Higashi-Yamato, and Hiroaki Wada, Kawasaki, all of Japan, assignors to Sumitomo Metal Industries, Ltd., Tokyo, Japan
Continuation-in-part of Ser. No. 913,961, Jul. 17, 1992, Pat. No. 5,318,761. This application Jan. 18, 1994, Ser. No. 101,945
Claims priority, application Japan, Jul. 18, 1991, 3-178309; Jan. 18, 1993, 5-006264

Int. Cl.⁶ C04B 35/54; 35/56

U.S. Cl. 264—65

24 Claims

1. A process for preparing a silicon carbide sintered body suitable for use in manufacture of semiconductor equipment comprising steps of shaping a silicon carbide powder to form a shaped body, calcining the shaped body in a non-oxidizing atmosphere to form a porous body, and subjecting the porous body to reaction sintering while being impregnated with molten silicon,

wherein the silicon carbide powder consists essentially of β -SiC and has an average particle diameter of about 0.5–20 μ m, a free carbon content of not greater than about 20% by weight, and a content of 1 ppm or less of each of alkali metal, alkaline earth metal, B, Al, Ga and heavy metal atoms, and wherein the silicon carbide powder is prepared by a method which comprises preparing a carbon- and silicon- containing starting mixture comprising (a) at least one siliceous material selected from liquid hydrolyzable silicon compounds and solid siliceous substances derived from a hydrolyzable silicon compound, and (b) at least one carbonaceous material selected from polymerizable or cross-linkable organic compounds prepared in the presence of a catalyst which is substantially free of each of alkali metal, alkaline earth metal, B, Al, Ga and heavy metal atoms, at least one material used as component (a) or (b) being a liquid substance, solidifying the starting mixture by heating, by use of a catalyst or a curing agent, or by a combination thereof to form a solid body, and forming the silicon carbide powder by heating the solid body at a temperature of from about 1600° C. to about 2000° C. in a non-oxidizing atmosphere.

5,589,117

INTEGRATED ABSORBENT STRUCTURES WITH DENSITY AND LIQUID AFFINITY GRADIENTS AND METHODS FOR MAKING THE SAME

Ching-Yun M. Yang, Princeton Junction, N.J., assignor to McNeil-PPC, Inc., Skillman, N.J.
Division of Ser. No. 176,747, Jan. 3, 1994, Pat. No. 5,525,407.
This application Jun. 8, 1995, Ser. No. 495,740

Int. Cl.⁶ B27N 3/04

U.S. Cl. 264—113

6 Claims

1. Utilizing a web-forming apparatus, a process for forming an absorbent composite having contiguous density and fluid affinity gradients wherein said process includes the step of increasing the amount of pulp fed into said web-forming apparatus relative to the

5,589,119


SILICONE ELASTOMER SEALS FOR MOLDED PLASTIC PARTS

Ray C. Hetherington, Virginia Beach, Va., assignor to New Southland, Inc., Virginia Beach, Va.
Filed Dec. 22, 1994, Ser. No. 362,276
Int. Cl.⁶ B29C 59/00

U.S. Cl. 264—129

23 Claims

1. A process comprising:
admixing an aromatic polyamide polymer and 0.01–1 wt. %, based on the total weight of said aromatic polyamide polymer, of an aminofunctional silicone fluid;
molding the resultant pretreated aromatic polyamide polymer, in the presence of moisture into a plastic part at a temperature sufficient to chemically graft the amino function of the silicone fluid to the aromatic carbonyl function of the aromatic polyamide polymer and to form silanol groups in the aminofunctional silicone fluid;
coating the molded plastic part with an organofunctional alkoxysilane having at least one vinyl group and heating the coated molded plastic part to convert the alkoxysilane into a siloxane polymer with vinyl and silanol groups and react the silanol groups thereof with silanol groups of the aminofunctional silicone fluid; and
applying a liquid silicone elastomer composition containing at least one Si—H group to the coated molded plastic part and heating same to form a covalent bond between vinyl groups of the siloxane polymer and Si—H groups of the elastomer, the liquid silicone elastomer forming a seal bonded to the molded plastic part.



amount of fiber fed into said web-forming apparatus, such that the composite produced has at least three integrated layers wherein the amount of pulp relative to the amount of fiber is different in each layer and the amount of pulp relative to the amount of fiber continuously increases from top to bottom of said absorbent composite.


5,589,118

PROCESS FOR RECOVERING IRON FROM IRON-CONTAINING MATERIAL

George W. Ford, Jr., Salt Lake City; Richard C. Lambert, Lehi, and Russell G. Madsen, Price, all of Utah, assignors to Covol Technologies, Inc., Lehi, Utah
Continuation-in-part of Ser. No. 184,099, Jan. 21, 1994, Pat. No. 5,453,103. This application Jun. 6, 1995, Ser. No. 468,104
Int. Cl.⁶ C22B 1/245; B29C 47/00

U.S. Cl. 264—122

13 Claims



1. A process for manufacturing articles from fine iron-containing material, the process comprising:

- mixing the iron-containing material, and carbon, to form an iron-containing/carbon mixture, the mixture being essentially free of oils and moisture;
- dissolving styrene or acrylonitrile polymer in a hygroscopic solvent;
- combining the dissolved styrene or acrylonitrile polymer, the iron-containing/carbon mixture, calcium carbonate, and an alumino-silicate binder;
- emulsifying polyvinyl polymer in water, adding the emulsion to the combination of step (c) and substantially homogenizing the resultant; and
- compressing the resultant from (d) into articles.


5,589,121

METHOD OF ENLARGING DESIGN PROVIDED ON A SYNTHETIC RESIN FILM

Jiro Inagaki, Takashi Shinoki, and Atsushi Hari, all of Kanagawa-ken, Japan, assignors to Teikoku Tsushin Kogyo Co., Ltd., Kanagawa-ken, Japan
Filed Dec. 14, 1994, Ser. No. 355,540
Claims priority, application Japan, Jul. 12, 1994, 6-183841
Int. Cl.⁶ B29C 45/16

U.S. Cl. 264—132

5 Claims



1. A method of enlarging a design possessed by a synthetic resin film, comprising:

a printing step of printing a desired design on a top side or bottom side of a synthetic resin film exhibiting flexibility; and an enlarging deformation step of enlarging the design by stretching a prescribed surface of the synthetic resin film which includes a portion on which the design has been printed and curvingly deforming the prescribed surface in such a manner that the surface will protrude above a plane defined by the synthetic resin film;

the design printed on the synthetic resin film at said printing step being printed in dependence upon rate of enlargement of each portion of the synthetic resin film stretched at said enlarging deformation step, with a portion of the design having a small rate of enlargement being printed at relatively large dimensions in comparison with other portions thereof and a portion of the design having a high rate of enlargement being printed at relatively small dimensions in comparison with other portions thereof, whereby the overall enlarged design after enlarging deformation takes on a desired shape;

in said printing step, a print layer for being clamped by upper and lower molds being printed on a surface or underside of the synthetic resin film on at least a portion thereof surrounding the portion deformed by enlargement;

said enlarging deformation step being performed by urging the synthetic resin film upward into intimate adhering contact with an inner surface of a cavity in the upper mold in a state in which the synthetic resin film is clamped between the upper mold and lower mold each of which has a cavity; and separating the upper and lower molds.

5,589,122


METHOD OF MAKING DOUBLE-SIDED PRESSURE-SENSITIVE ADHESIVE TAPE

William K. Leonard, Troy Township, Wis.; Klrit C. Mody, Shoreview, and Richard J. Rolando, Oakdale, both of Minn., assignors to Minnesota Mining And Manufacturing Company, St. Paul, Minn.

Division of Ser. No. 166,549, Dec. 14, 1993, abandoned, which is a continuation-in-part of Ser. No. 769,548, Oct. 1, 1991, abandoned. This application Mar. 29, 1995, Ser. No. 412,758 Int. Cl.⁶ B29C 47/06

U.S. Cl. 264—146

20 Claims



1. A solvent-free method for the manufacture of pressure-sensitive adhesive tape comprising the steps of:

- providing first and second solvent-free pressure-sensitive adhesive compositions and forming molten streams thereof;
- providing a solvent-free backing-forming material and forming a molten stream thereof;
- combining said streams into a single unified molten structure having a first layer of pressure-sensitive adhesive composition formed from said first molten stream of pressure-sensitive adhesive composition, a second layer of pressure-sensitive adhesive composition formed from said second molten stream of pressure-sensitive adhesive composition, and a layer of backing-forming material disposed between said pressure-

sensitive adhesive layers, wherein at least one of said layers of adhesive is not coextensive; and

- cooling said molten structure to yield a composite pressure-sensitive adhesive tape comprising a backing with first and second major surfaces formed from said backing-forming material, a first layer of normally tacky pressure-sensitive adhesive formed from said first layer of pressure-sensitive adhesive composition on said first major surface, and a second layer of normally tacky pressure-sensitive adhesive formed from said second layer of pressure-sensitive adhesive composition on said second major surface, wherein at least one of said layers of adhesive is non-coextensive.

5,589,123

PROCESS OF MAKING A TUBULAR SUPPORTING ELEMENT


Francesco Portas, Quattordio, Italy, assignor to Pirelli Cavi S.p.A., Milan, Italy

Division of Ser. No. 351,878, Dec. 8, 1994, which is a continuation of Ser. No. 985,182, Dec. 2, 1992, abandoned. This application Mar. 27, 1995, Ser. No. 411,421

Claims priority, application Italy, Dec. 16, 1991, M191A3362 Int. Cl.⁶ B29C 67A00

U.S. Cl. 264—154

6 Claims



1. Process for making a tubular supporting element for a sleeve for covering junctions of cables, the supporting element comprising a tubular body with a wall of a predetermined radial thickness having at least one reverse V-shaped helical incision therein with a radial dimension less than said predetermined thickness and with an outer surface and an inner surface coaxial with the axis of said body, said outer surface being engageable with an inner surface of said sleeve, comprising the steps of:

- constraining the supporting element to a supporting means under conditions of substantial axial containment and
- helically making at least one reverse V-shaped incision in said wall, which is continuous circumferentially of said axis, by means of a cutting blade in condition of axial containment of said supporting element,

wherein said incision separates portions of said wall from each other so as to define a strip between one turn of the incision and the next turn of the incision which strip thereby extends helically around said axis, said incision extends radially of said axis either from said outer surface of said tubular body toward said inner surface of said tubular body or from said inner surface of said tubular body toward said outer surface of said tubular body, and said incision has a reverse V-shaped cross-section having a mouth at said outer or inner surface and a width at said radial portion, said mouth having a width transverse to the helical length of said incision which is not greater than the said width at said radial portion.

5,589,124

METHOD OF FORMING COMPOSITE MASONRY BLOCKS


Michael E. Woolford, Lake Elmo, Minn., and Dick J. Sievert, New Richmond, Wis., assignors to Block Systems, Inc., North St. Paul, Minn.

Continuation of Ser. No. 157,830, Nov. 24, 1993, abandoned, which is a division of Ser. No. 651,322, Feb. 6, 1991, Pat. No. 5,294,216, which is a division of Ser. No. 534,831, Jun. 7, 1990, Pat. No. 5,062,610, which is a continuation-in-part of Ser. No. 413,400, Sep. 28, 1989, abandoned, and Ser. No. 413,050, Sep. 28, 1989, abandoned. This application Jun. 6, 1995, Ser. No. 469,795

Int. Cl.⁶ B28B 3/00; 11/14

U.S. Cl. 264—157

25 Claims



1. A method of using a masonry block mold to form masonry block having at least one flange extending therefrom, said mold having a fill-receiving cavity defined therein having an open top and bottom, said mold comprising a pair of opposed side walls connected by end walls, each of said side walls comprising a flange projecting into said fill-receiving cavity, each side wall comprising a top edge and a bottom edge, said bottom edges adapted to seat on a generally horizontal pallet, and said top edges each comprising at least one step so as to form first portions thereof which are higher than adjacent portions thereof, said method comprising the steps of:

- loading said mold with block fill through said top of said cavity;
- drawing excess block fill from said top of said cavity;
- holding block fill proximate said first portions at a level above that proximate said adjacent portions of said top edges to form at least one flange on said block fill;
- compressing said block fill within said mold with a compression head moving into said cavity from top to bottom wherein grooves are formed in said block fill by said mold side wall flanges;
- stripping a formed masonry block having at least one flange extending therefrom from said mold; and
- splitting said formed masonry block adjacent said grooves in said formed masonry block.

5,589,125

PROCESS OF AND APPARATUS FOR MAKING CELLULOSE MOULDINGS

Stefan Zikeli, Regau; Ernst Rauch, Schörfling; Hermann Koberger, Zipf; Friedrich Ecker, Timelkam; Hartmut Rief, Vöcklabruck; Raimund Jurkovic, and Franz Schwenninger, Both of Lenzing, all of Austria, assignors to Lenzing Aktiengesellschaft, Austria


PCT No. PCT/AT93/00053, § 371 Date Nov. 16, 1993, § 102(e) Date Nov. 16, 1993, PCT Pub. No. WO93/19230, PCT Pub. Date Sep. 30, 1993

PCT Filed Mar. 17, 1993, Ser. No. 142,313

Claims priority, application Austria, Mar. 17, 1992, 537/92 Int. Cl.⁶ D01F 2/24

U.S. Cl. 264—187

11 Claims



1. A process for the preparation of cellulose mouldings comprising the steps of:

- moulding a hot solution of cellulose in a tertiary amine-oxide by passing the cellulose solution through a spinneret,
- cooling the hot moulded solution by exposing it to a gas stream, wherein the direction of spinning is essentially at right angles to the gas stream, and
- introducing the cooled moulded solution into a precipitation bath thereby forming a cellulose moulding, whereby cooling of the hot moulded solution takes place immediately after the moulding process and before introduction into the bath.

5,589,126

PLASTICIZED POLYESTER FOR SHRINK FILM APPLICATIONS

Wayne K. Shih, and Ronald R. Light, both of Kingsport, Tenn., assignors to Eastman Chemical Company, Kingsport, Tenn.

Division of Ser. No. 410,594, Mar. 24, 1995, Pat. No. 5,534,570, which is a continuation of Ser. No. 157,546, Nov. 26, 1993, abandoned. This application Mar. 4, 1996, Ser. No. 608,021

Int. Cl.⁶ D01F 1/02

U.S. Cl. 264—211

2 Claims

1. A process for preparing a heat-shrinkable film comprising: (I) mixing at a temperature of 200° C. to 315° C.

- 90 to 99 weight percent of a polyester having a glass transition temperature of 40° C. to 150° C. and an inherent viscosity of 0.5 to 1.2 dL/g, comprising
 - a dicarboxylic acid component comprising repeat units from at least 80 mole percent of an aromatic dicarboxylic acid having 8 to 14 carbon atoms, and
 - a diol component comprising repeat units from at least 10 mole percent of 1,4-cyclohexanedimethanol, based on 100 mole percent dicarboxylic acid and 100 mole percent diol; and
- 1 to 10 weight percent of a plasticizer selected from a C₄ to C₂₀ alkyl ester of an epoxidized fatty acid having 12 to 20

carbon atoms provided the plasticizer has sufficient stability to permit its incorporation into the polyester at a temperature of 200° C. to 300° C., wherein the combined weights of (A) and (B) total 100 percent; and
(II) forming the blend into a film.

5,589,127

METHOD AND APPARATUS FOR FORMING RIBS WITH SIDEWARD PROJECTIONS IN A PLASTIC PIPE, AND A PLASTIC PIPE


Jyri Järvenkylä, Hollola, Finland; Dieter Scharwächter, Oettrup, Germany; Åke Johansson, and Ronny Kristensson, both of Fristad, Sweden, assignors to Uppon Innovation AB, Fristad, Sweden

Filed Feb. 15, 1994, Ser. No. 196,406

Claims priority, application Finland, Feb. 24, 1993, 930826
Int. Cl. B29D 16/00

U.S. Cl. 264—280

14 Claims



14. A method for providing annular ribs of a plastic pipe with oppositely sideward projections, comprising:
surrounding the plastic pipe having the annular ribs with rib rolling means and relatively moving the rib rolling means longitudinally to the pipe and rotatingly around a longitudinal axis of the pipe, the rib rolling means defining a conical rib-engaging rotation surface decreasing in diameter in the direction of the relative movement of the pipe for gradually compressing the ribs annularly and forming the oppositely sideward projections on each of the ribs and the rib rolling means comprising elongated rolls rotatable about and rotating about respective axes disposed circumferentially around the pipe.

5,589,128

PERFORMANCE SUPER HIGH FLOW ETHYLENE POLYMER COMPOSITIONS

Shih-Yaw Lai, Sugar Land; Lonnie G. Hazlett, and Pak-Wing S. Chum, both of Lake Jackson, all of Tex., assignors to The Dow Chemical Company, Midland, Mich.

Division of Ser. No. 924,775, Aug. 4, 1992, Pat. No. 5,346,732.
This application Aug. 12, 1994, Ser. No. 289,978


Int. Cl. B29B 7/00

U.S. Cl. 264—328.1

15 Claims

1. A method of forming a thermally formed article, comprising the steps of:

- melt extruding an ethylene polymer composition comprising at least one linear ethylene polymer having
 - a density from about 0.87 g/cm³ to about 0.965 g/cm³,
 - a melt index, I₂, as measured by ASTM D-1238(190° C./2.16 kg), from about 0.1 grams/10 minutes to about 2 grams/10 minutes,
 - a melt index, I₁₀, as measured by ASTM D-1238(190° C./10 kg), from about 28 grams/10 minutes to about 55 grams/10 minutes,
 - a melt flow ratio, I₁₀/I₂, from about 14 to about 550,



(e) a processing index from about 0.005 Kpoise to about 1 Kpoise, and
(f) molding the thermally formed article from the composition.

5,589,129

METHOD OF MANUFACTURING A MOLDING USING A FILLER OR AN ADDITIVE CONCENTRATED ON AN ARBITRARY PORTION OR DISTRIBUTED AT A GRADIENT CONCENTRATION

Tsuguo Kato, Fujisawa, and Cao M. Thai, Yokohama, both of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Continuation of Ser. No. 198,262, Feb. 18, 1994, abandoned.

This application Jun. 19, 1995, Ser. No. 491,687

Claims priority, application Japan, Feb. 19, 1993, 5-030161
Int. Cl. B29C 35/08

U.S. Cl. 264—437

18 Claims



1. A method of manufacturing a molding, which comprises the steps of:

- injecting a liquid resin composition containing at least one of an ionic material and a chargeable material into a mold;
- applying a DC voltage to the liquid resin composition to make said at least one of the ionic material and the chargeable material migrate, thereby forming a concentration gradation of said at least one of the ionic material and chargeable material in the liquid resin composition, the liquid resin composition being in a liquid state while the DC voltage is being applied; and
- solidifying the liquid resin composition.

5,589,130

METHOD OF INJECTION MOLDING A PREFORM AND APPARATUS FOR THE SAME

Minoru Takada; Koichi Sato, and Kazuyuki Yokobayashi, all of Ueda, Japan, assignors to Nissei ASB Machine Co., Ltd., Komori, Japan

PCT No. PCT/JP94/01247, § 371 Date Mar. 13, 1995, § 102(e) Date Mar. 13, 1995, PCT Pub. No. WO95/03930, PCT Pub. Date Feb. 9, 1995


PCT Filed Jul. 29, 1994, Ser. No. 403,742

Claims priority, application Japan, Jul. 30, 1993, 5-208547
Int. Cl. B29C 49/06; 49/64

U.S. Cl. 264—537

22 Claims

1. A method of injection molding a preform, comprising:



a step in an injection molding station of injection molding a preform in clamped molds including an injection cavity mold and injection core mold each of which has a cooling portion; a step in said injection molding station of releasing said preform from said injection cavity mold; a step of transferring said preform while being cooled by said injection core mold to a cooling and ejection station; and a step in said cooling and ejection station of cooling said preform by said injection core mold and thereafter ejecting said preform from said injection core mold during an injection molding cycle for a next preform in said injection molding station, wherein
in said injection molding step, said preform, which has a neck portion having an undercut with respect to a direction of mold-opening, is injection molded using a neck cavity mold defining the outer surface of said neck portion, and said neck cavity mold comprises a split pair of molds having cooling portions;
in said transfer step and said cooling step in said cooling and ejection station, said preform is cooled with said injection core mold and said neck cavity mold maintained in the clamped state; and
in said ejection step in said cooling and ejection station, said injection core mold is separated from said neck cavity mold by relative mold-opening driving through only a stroke sufficient to allow a space to open between said injection core mold and the inner surface of said preform held by said neck cavity mold, and thereafter said split pair of molds of said neck cavity mold is driven to be separated, and said preform is ejected.

5,589,131

METHOD FOR MANUFACTURING A REPLACEMENT PIPE FOR INSTALLATION IN AN EXISTING CONDUIT


Campbell H. Steketee, Jr., Salem, Oreg., assignor to NuPipe, Inc., Memphis, Tenn.

Continuation of Ser. No. 612,163, Nov. 9, 1990, abandoned, which is a division of Ser. No. 180,904, Apr. 13, 1988, abandoned, which is a continuation-in-part of Ser. No. 76,973, Jul. 28, 1987, Pat. No. 4,867,921, which is a continuation-in-part of Ser. No. 846,322, Mar. 31, 1986, abandoned. This application Mar. 19, 1993, Ser. No. 34,918

Int. Cl. B29C 47/90; 63/34

U.S. Cl. 264—568

19 Claims



1. A method of manufacturing a thermoplastic pipe in collapsed and folded form suitable for installation in an existing conduit by: extruding a thermoplastic pipe material while in a hot plastic state through a die to form it into a tubular shape of desired size and having a circumferential dimension;

feeding the resulting hot tubular thermoplastic pipe material while still in a plastic state through non-circular calibrator means having an opening for shaping the thermoplastic material fed therethrough, the openings sized and shaped to collapse, fold and hold the tubular thermoplastic material to the desired collapsed and folded form while subjecting the material to a partial vacuum, the pipe material having the desired collapsed and folded form;

cooling the collapsed and folded material while pulling it through and from the calibrator means, the material having a memory for the collapsed and folded form such that when reheated to render it pliable, it retains the collapsed and folded form;

hardening the thermoplastic material in collapsed and folded form,

reheating the collapsed and folded thermoplastic material to render it pliable, and

winding the pliable material in its collapsed and folded form onto a storage spool.

5,589,132

METHOD AND DEVICE FOR PURIFYING AND MOISTENING AIR

Gunther Zippel, Pommernstrasse 29, 93073 Neutraubling, Germany


Filed Feb. 1, 1995, Ser. No. 382,193

Claims priority, application Germany, Feb. 3, 1994, 44 03 358.3; Aug. 19, 1994, 44 29 502.2

Int. Cl. A61L 9/20; F24F 6/14

U.S. Cl. 422—24

14 Claims



1. A method for purifying and moistening air within restricted areas, especially living and working rooms, according to which a fan-driven air stream is drawn into a casing of an air treating device, is filtered at an entrance of said device, is sterilized by ultraviolet radiation, is brought into contact with a water supply, and is discharged into a room as a purified and moistened air stream, the method comprising the steps of:

passing an air stream through a channel-type passageway provided within a casing of an air treating device, sterilizing said air stream by ultraviolet radiation within said passageway, passing said air stream through an extension of said passageway over a substantially stagnant relatively large surface-area of a water supply provided within a tray and through an air channel formed by said water surface, a corrugated cover plate and side walls of said tray, and introducing discontinuities into said water surface of said tray and said air stream between said water supply and said cover plate above said water surface.

5,589,133

OXYGEN ELECTRODE, BIOSENSOR AND PROCESSES FOR MANUFACTURING SAME

Hiroaki Suzuki, Kawasaki, Japan, assignor to Fujitsu Limited, Kawasaki, Japan

Continuation of Ser. No. 41,054, Mar. 31, 1993, abandoned.


This application Oct. 5, 1994, Ser. No. 318,209

Claims priority, application Japan, Jul. 20, 1992, 4-191768

Int. Cl.⁶ G01N 27/404

U.S. Cl. 422—79

17 Claims



1. An oxygen electrode comprising:
 - a plastic sheet having a planar surface;
 - an Ag/AgCl anode pattern on said surface of the plastic sheet;
 - a first electrode lead and pad pattern formed on the surface of the plastic sheet and electrically connected to said anode pattern;
 - a cathode pattern formed on said surface of the plastic sheet;
 - a second electrode lead and pad pattern formed on the surface of the plastic sheet and electrically connected to said cathode pattern;
 - a paraffin layer located on said surface of the plastic sheet over said patterns, said paraffin layer comprising a paraffin having a softening point of about 100° to 150° C. and being configured so as to delineate a sensitive area of the plastic sheet where portions of said anode and cathode patterns are exposed;
 - a carrier sheet formed of a natural or synthetic paper or a woven or non-woven cloth overlying said sensitive area and contacting said portions of the anode and cathode patterns; and
 - a gas permeable membrane overlying a first portion of the carrier sheet and the paraffin layer, said membrane being positioned and configured so that there is a second portion of the carrier sheet which is not covered by the membrane, whereby an electrolyte solution may be impregnated through said second portion of the carrier sheet.

5,589,134

Patent Not Issued For This Number

5,589,135

HEIGHT ADJUSTABLE STAND FOR LABORATORY EQUIPMENT

Erwin Bossart, Flawil, Switzerland, assignor to Buchi Laboratories - Technik AG, Flawil, Switzerland

Filed Sep. 22, 1992, Ser. No. 948,439


Claims priority, application Switzerland, Oct. 18, 1991, 3063/91

Int. Cl.⁶ B01L 9/06

U.S. Cl. 422—99

6 Claims

1. A height adjustable stand for a laboratory flask, comprising:
 - a vertical stand post;
 - a flask holder supported on said post for movement therealong;



- a motorized continuous elevator drive for moving the flask holder at a predetermined speed, said elevator drive comprising a helically threaded, vertical, rotary spindle;
- a normally engaged clutch connecting the elevator drive to the flask holder, said clutch comprising toothed means for engaging said spindle thread; and
- means for manually releasing said clutch so that the flask holder can be moved independent from said elevator drive, said releasing means comprising a manually operable release lever pivotally mounted on said flask holder and connected to said toothed means, for moving said clutch means between engaged and disengaged positions with respect to said spindle.

5,589,136

SILICON-BASED SLEEVE DEVICES FOR CHEMICAL REACTIONS


M. Allen Northrup, Berkeley; Raymond P. Mariella, Jr., Danville; Anthony V. Carrano, and Joseph W. Balch, both of Livermore, all of Calif., assignors to Regents of the University of California, Oakland, Calif.

Filed Jun. 20, 1995, Ser. No. 492,678

Int. Cl.⁶ B01L 3/00

U.S. Cl. 422—102

22 Claims



1. In a microfabricated chemical reactor having a reaction chamber, the improvement comprising:
 - a sleeve reaction chamber,
 - said sleeve reaction chamber having a slot therein,
 - said slot being constructed to enable insertion of an insert or liner therein, and
 - heating means for said sleeve reaction chamber.

5,589,137

SPECIMEN CARRIER


Rodney S. Markin, Omaha, and Michael R. Newcomb, Papillion, both of Nebr., assignors to Lab-Interlink, Inc., Omaha, Nebr.

Filed Apr. 7, 1995, Ser. No. 418,958

Int. Cl.⁶ B01L 9/06

U.S. Cl. 422—104

31 Claims



1. A specimen carrier for transporting a laboratory specimen carried within a specimen tube or on a specimen slide, comprising:
 - a carrier body having a forward face and opposing rearward face, a top surface and opposing bottom surface, a right end wall and opposing left end wall an aperture having alternating curved portions forming a plurality of vertical cylindrical holes for receiving specimen tubes of varying diameter and depth dimensions, said aperture comprising:
 - a first vertical cylindrical hole formed in the top surface of the carrier body, said hole having a first diameter and depth dimensions so as to receive a first specimen tube partially therein; and
 - a second vertical cylindrical hole formed in the top surface of the carrier body said second hole having a second diameter and depth dimensions different from said first hole so as to receive a second specimen tube having diameter and depth dimensions different from said first tube; said second hole, overlapping the first hole to form a single cavity, wherein said cavity extends vertically from the lower end to an open upper end at the top surface of the carrier body and extends horizontally to include the diameter of each of said first and second holes, to retain fluid therein.

5,589,138

APPARATUS FOR AND METHODS OF STABILIZING AND REGENERATING METALWORKING FLUIDS


Peter H. Drechsler, New Britain, Conn., assignor to The Torrington Company, Torrington, Conn.

Division of Ser. No. 203,154, Feb. 28, 1994, Pat. No. 5,445,945. This application Mar. 31, 1995, Ser. No. 414,846

Int. Cl.⁶ G05B 13/00; G01N 30/96; B21B 45/02

U.S. Cl. 422—108

11 Claims



1. A system for controlling the state of a recirculating metalworking fluid (MWF), comprising:
 - a monitoring means for testing said MWF for the presence of free metal ions in solution therein;

- b. testing means for determining the concentration of free metal ions in said MWF; and
- c. addition means, responsive to the testing means, for adding in a controlled manner an effective amount of at least one chelating agent effective to chelate said free metal ions in said MWF.

5,589,139

DOWNFLOW FCC REACTION ARRANGEMENT WITH UPFLOW REGENERATION

Randy J. Zinke, Carol Stream, and William J. Koves, Hoffman Estates, both of Ill., assignors to UOP, Des Plaines, Ill.


Division of Ser. No. 235,049, Apr. 29, 1994. This application

Jun. 6, 1995, Ser. No. 479,098

Int. Cl.⁶ F27B 15/02

U.S. Cl. 422—144

7 Claims



1. An apparatus for the catalytic cracking of hydrocarbons, said apparatus comprising:
 - a) vertical reaction conduit defining an upper inlet for receiving catalyst particles and mean for introducing hydrocarbons into an upper portion of said conduit;
 - b) separator in communication a lower end of said conduit for separating gas from spent catalyst particles;
 - c) means for contacting catalyst particles from said reaction conduit with a stripping gas;
 - d) a catalyst collector communicating with a spent catalyst conduit to transfer spent catalyst from said collector to said spent catalyst conduit;
 - e) a first regenerator riser in communication at its lower end with a said spent catalyst conduit and a first regeneration gas conduit to transfer spent catalyst particles upwardly to the top of said riser;
 - f) a first regenerator cyclone communicating with an upper end of said first regenerator riser to separate said first regeneration gas from catalyst particles;
 - g) a second regenerator riser having a lower end in communication with said first regenerator cyclone for receiving catalyst particles therefrom and having means for contacting catalyst particles upwardly therein;
 - h) a second regenerator cyclone located above said reaction conduit having an inlet in communication with an upper end

of said second regenerator riser, a gas outlet communicating with said first regeneration gas conduit, and a primary dip pipe conduit in direct communication with said reaction conduit for directly transferring regenerated catalyst particles to the inlet of said reaction conduit.


5,589,140

CONTINUOUS DENITRATION APPARATUS

Yoshiharu Takahashi, Katsuta, Japan, assignor to Doryokuro Kakunenryo Kaihatsu Jigyodan, Tokyo, Japan
Continuation of Ser. No. 121,422, Sep. 16, 1993, abandoned.
This application Jan. 11, 1996, Ser. No. 583,934
Claims priority, application Japan, Sep. 16, 1992, 4-246708
Int. Cl.⁶ G21G 5/00

U.S. Cl. 422-159

6 Claims



1. A continuous denitration apparatus, operating on a nitrate solution, comprising:

- a nitrate solution processing area which is divided into a concentration zone which uses heat to evaporate and concentrate nitrate solution, a denitration zone which denitrifies the nitrate solution concentrated in the concentration zone to prepare a denitrated product, and a drying zone for drying the denitrated product prepared in the denitration zone;
- a screw element, extended along the nitrate solution processing area, and operating to convey the nitrate solution in a direction of its extended direction by rotating the screw element around a rotation axis thereof;
- a microwave source; and
- a critical shield plate formed of a microwave non-permeable material covering an entire length of the nitrate solution processing area, the critical shield plate including a microwave permeable portion provided in said denitration zone, over less than the entire length of the nitrate solution processing area, whereby microwaves from the microwave source are applied to the material for processing only at the microwave permeable part of the critical shield plate.

5,589,141

USE OF MIXED GASES IN HYBRID AIR BAG INFLATORS


James R. Sides, James D. Martin, and Robert S. Scheffee, all of Gainesville, Va., assignors to Atlantic Research Corporation, Vienna, Va.

Continuation-in-part of Ser. No. 414,565, Mar. 31, 1995, abandoned. This application Jul. 28, 1995, Ser. No. 492,955
Int. Cl.⁶ B60R 21/26

U.S. Cl. 422-164

28 Claims

1. A method of generating non-toxic gases without particulates comprising conducting an ignition of a propellant composition with an effective oxidizer, using a suitable propellant comprising aminoguanidine nitrate, in conjunction with a suitable binder, in the presence of argon and a molecular oxygen-containing gas, and selectively providing a ratio of said molecular oxygen-containing gas to argon prior to ignition to provide non-toxic reaction products in the exhaust gas.



PASSENGER SIDE INFLATOR

5,589,142


INTEGRATED REGENERATIVE CATALYTIC OXIDATION/SELECTIVE CATALYTIC REDUCTION ABATEMENT SYSTEM

Sean T. Gribbon, Farmington Hills, Mich., assignor to Salem Englehard, South Lyon, Mich.

Filed Jul. 27, 1994, Ser. No. 280,944
Int. Cl.⁶ F23G 7/06; F23D 14/00; B01D 50/00

U.S. Cl. 422-171

1 Claim



1. A system for removal of oxidizable contaminants and reducible gases from process emissions by an initial oxidation process and a subsequent reduction process, said system comprising:

- a pair of regenerative units for receiving contaminated process emissions, selectively;
- a source of contaminated process emissions;
- a pair of contaminated process emission inlet conduits connected to said source and to one side of each of said regenerative units respectively;
- a pair of cleansed emission outlet conduits communicating with the one side of said regenerative units, respectively and with the ambient atmosphere;
- a contaminated process emission heating chamber connected to each of said regenerative units on the opposite side thereof, respectively, from said contaminated emission source;
- a pair of catalytic oxidizers connected between said regenerative units, respectively, and said heating chamber for oxidizing contaminants in said process emissions;
- a pair of reducing gas injectors between said catalytic oxidizers, respectively, and said heating chamber;
- a pair of catalytic reduction units between said reducing gas injectors, respectively, and said heating chamber;
- a pair of inlet valves in said inlet conduit between the source of contaminated process emissions and the one side of each of said regenerative units, respectively;
- a pair of outlet valves in said outlet conduits between the one side of said regenerative units, respectively and with the ambient atmosphere, said inlet and outlet valves being openable and closable for reversing the flow of contaminated process emissions and cleansed exhaust to and from said regenerative units, respectively;
- a transition duct connected between the source of process emissions and said heating chamber for conducting contaminated process emissions directly to said heating chamber; and

a reducing gas injector communicating directly with said heating chamber for injecting reducing gas into contaminated emissions introduced into said heating chamber by said transition duct.

5,589,143


EXHAUST GAS PURIFICATION APPARATUS FOR INTERNAL COMBUSTION ENGINE

Hiroshi Mori, Ichinomiya, Masakazu Tanaka, Okazaki; Mamoru Mabuchi, Kariya, and Makoto Saito, Nishio, all of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan
Continuation of Ser. No. 120,384, Sep. 14, 1993, abandoned.
This application May 2, 1995, Ser. No. 434,320

Claims priority, application Japan, Sep. 16, 1992, 4-246903; Feb. 4, 1993, 5-040501; Feb. 25, 1993, 5-061036
Int. Cl.⁶ B01D 50/00; F01N 3/28

U.S. Cl. 422-171

5 Claims



1. An apparatus for purifying an exhaust gas emitted from an internal combustion engine having an exhaust gas flow path, the apparatus comprising:


- a catalyst unit provided in an exhaust gas flow path;
- a bypass passage having first and second ends, each in communication with the exhaust gas flow path downstream of said catalyst unit;
- an absorbent provided in said bypass passage for absorbing a hydrocarbon ("HC") gas contained in an exhaust gas emitted from an internal combustion engine;
- a circulation passage having first and second ends, said first end being connected to a location in the exhaust gas flow path upstream of said catalyst unit, and said second end being connected to said bypass passage, downstream of said absorbent;
- a circulation controlling means provided in said circulation passage for intermittently opening and closing said circulation passage in correspondence with an exhaust gas pulsation occurring at said location in the exhaust gas flow path upstream of said catalyst unit where said first end of said circulation passage is connected;
- exhaust gas flow path change-over means for directing the exhaust gas to flow through said bypass passage when a temperature of said exhaust gas is lower than a threshold temperature, and for directing the exhaust gas to flow only in the exhaust gas flow path when a temperature of the exhaust gas is higher than the threshold temperature.

5,589,144
THERMAL BARRIER FOR AN EXHAUST SYSTEM
John E. Filippi, R. R. 1, Box 400, Negaunee, Mich. 49866, and John A. Golen, 5765 Berwyn, Dearborn Heights, Mich. 48127

Filed May 1, 1990, Ser. No. 517,305
Int. Cl.⁶ B01D 50/00; B23K 31/02

U.S. Cl. 422-179

11 Claims




1. An exhaust system comprising:
a catalytic converter formed from a first half shell and a second half shell, said first and second half shells having an inside and an outside surface;
at least one intake pipe formed from a first half shell and a second half shell, said first and second half shells of said intake pipe having an inside and an outside surface; and
wherein the inside surface of the first and second half shells of the catalytic converter is coated with a thermal barrier coating by means of an arc plasma spray.

5,589,145
WASTE TREATMENT MATERIAL DISPENSING CANISTER

Jack W. Kaufman, 357 Frankel Blvd., Merrick, N.Y. 11566
Division of Ser. No. 306,363, Sep. 15, 1994, Pat. No. 5,543,118, which is a continuation-in-part of Ser. No. 507,966, Apr. 11, 1990, abandoned, which is a continuation-in-part of Ser. No. 215,370, Jul. 5, 1988, abandoned, which is a continuation-in-part of Ser. No. 105,875, Oct. 7, 1987, abandoned. This application Aug. 24, 1995, Ser. No. 519,134
Int. Cl.⁶ A61L 2/22; B65D 53/02; B67D 5/00; A61M 1/00

U.S. Cl. 422-292

28 Claims



1. A waste treatment material dispensing device for use with a closed waste fluid disposal vessel wherein said device is of a size and shape to be secured in a port disposed on said waste fluid disposal vessel, comprising:
(a) waste treatment material;

- (b) a container, said container defining a storage volume for holding said waste treatment material, said container capable of being lockably disposed in a port, and said container having an exit port open to said fluid disposal vessel;
- (c) a wall covering said exit port, said wall retaining said waste treatment material; and
- (d) an actuator provided on said container for releasing said waste treatment material into said vessel, said actuator opening said wall upon actuation.

5,589,146

METHOD FOR TREATING AMMONIA

Atsushi Morii; Osamu Naito; Toshiyuki Onishi; Hitoshi Nakamura, all of Nagasaki, and Kouzo Iida, Hiroshima, all of Japan, assignors to Mitsubishi Jukogyo Kaisha, Japan

Continuation of Ser. No. 169,606, Dec. 17, 1993, abandoned.


This application Apr. 2, 1996, Ser. No. 626,577

Claims priority, application Japan, Dec. 21, 1992, 4-339940

Int. Cl.⁶ C01C 3/00

U.S. Cl. 423—237

4 Claims



1. A method of treating ammonia in an exhaust gas downstream of a dry denitration device using ammonia as a reducing agent, comprising the steps of adsorbing ammonia in an ammonia adsorbent-filled tower at a point where said exhaust gas temperature is less than 200° C., conducting a gas heated to 300° to 400° C. into said adsorbing tower saturated with ammonia adsorption so as to desorb ammonia by heating, and decomposing ammonia by conducting the ammonia-desorbed gas into an ammonia decomposition tower containing an ammonia decomposition catalyst which is disposed on an ammonia desorption line that is installed separately from the main stream of the dry denitration device.

5,589,147

CATALYTIC SYSTEM FOR THE REDUCTION OF NITROGEN OXIDES

Maria D. Farnos, Wilmington, Del.; John P. McWilliams, Woodbury, N.J.; Sanjay B. Sharma, Langhorne, Pa., and David S. Shihabi, Pennington, N.J., assignors to Mobil Oil Corporation, Fairfax, Va.

Filed Jul. 7, 1994, Ser. No. 271,685

Int. Cl.⁶ C01B 21/00

U.S. Cl. 423—239.2

11 Claims

1. A method for treating an exhaust gas comprising NO_x and ammonia, said method comprising directing the exhaust gas along with a source of oxygen over a catalyst under treating conditions effective for the selective catalytic reduction of NO_x; said catalyst comprising a molecular sieve which has been physically mixed with a metal and a binder or a binder precursor under contacting conditions effective to produce a metal loading of about 0.01 wt. % to about 5 wt. % with reference to the molecular sieve; said molecular sieve being at least one selected from the group consisting of ZSM-5, ZSM-11, ZSM-12, ZSM-21, ZSM-22, ZSM-23, ZSM-35, ZSM-38, ZSM-48, ZSM-58, and combinations thereof, said binder or binder precursor comprising at least one selected from the group consisting of titania, zirconia, and silica; said process further comprising finished said catalyst in a humidified atmosphere under conditions effective to produce improved hydro-

thermal stability; the metal being selected from the group consisting of at least one of the Groups of the Periodic Table of IIIA, IB, IIB, VA, VIA, VIIA, VIIIA, and combinations thereof.

5,589,148

PROCESS FOR PURIFYING HALOGEN-CONTAINING GAS

Kenji Otsuka; Hideki Fukuda, and Setoshi Arakawa, all of Hiratsuka, Japan, assignors to Japan Pionics Co., Ltd., Tokyo, Japan

Filed Aug. 23, 1995, Ser. No. 518,240

Claims priority, application Japan, Oct. 5, 1994, 6-266382

Int. Cl.⁶ C01B 7/07

U.S. Cl. 423—240 S

19 Claims

1. A process for purifying a halogen-containing gas which comprises bringing said halogen-containing gas into contact with a purifying agent comprising a hydroxide of an alkaline earth metal and an iron oxide to remove at least one member selected from the group consisting of hydrogen halogenides and moisture that are contained as impurities in said halogen-containing gas.

5,589,149

PROCESS FOR ABSORPTION OF MERCAPTANS

Paul Garland, Aylesbury, United Kingdom; Craig N. Schubert; Richard A. Gregory, both of Belle Mead, N.J.; Eduardo Garcia-Rameau; Rickey Epps, both of Houston, Tex.; David Burns, and Robert J. Hlozek, both of The Woodlands, Tex., assignors to Union Carbide Chemicals & Plastics Technology Corporation, Danbury, Conn.

Continuation of Ser. No. 149,077, Nov. 9, 1993, abandoned.

This application Jul. 12, 1995, Ser. No. 501,702

Int. Cl.⁶ B01D 53/48

U.S. Cl. 423—242.4

14 Claims

1. A process for removing mercaptans having from 1 to about 8 carbon atoms per molecule from a feed gas stream containing the mercaptans, said mercaptans including methyl mercaptan said process comprising:

- (a) passing the feed gas stream to an absorption zone wherein the feed gas stream is contacted with a lean solvent stream containing an absorption solvent comprising:
- (i) from about 10 to 98 weight percent based on the weight of the absorption solvent on an anhydrous basis of an alkyl ether of a polyethylene glycol of the formula:




wherein:

R₁ is an alkyl group having 1 to about 4 carbon atoms;R₂ is hydrogen or an alkyl group having 1 to about 4 carbon atoms; and

x is 2 to about 10;

- (ii) from 1 to about 20 weight percent based on the weight of the absorption solvent on an anhydrous basis of a secondary monoalkanol amine of the formula:



wherein:


R₃ is an alkylene group having 1 to about 6 carbon atoms; andR₄ is an alkyl group having 1 to about 4 carbon atoms;

- (iii) from about 10 to about 60 weight percent of a dialkanol amine based on the weight of the absorption solvent on an anhydrous basis; and

- (iv) from about 0.1 to 80 weight percent water based on the total weight of the absorption solvent;

said absorption solvent being further characterized by having less than 0.005 moles of iodine per liter of absorption solvent;

- (b) discharging a product gas stream at least about 90% depleted in methyl mercaptan relative to the feed gas stream from the absorption zone;
- (c) discharging a rich solvent stream comprising the absorption solvent and at least a portion of the mercaptans from the absorption zone;
- (d) passing at least a portion of the rich solvent stream to a regeneration zone wherein absorbed mercaptans are desorbed from the rich solvent stream;
- (e) discharging a tail gas stream comprising mercaptans from the regeneration zone;
- (f) discharging a regenerated solvent stream comprising said absorption solvent; and
- (g) recycling at least a portion of the regenerated solvent stream to the absorption zone to comprise at least a portion of the lean solvent stream.



nitrogen, with the proviso that a process wherein the at least one adsorbent is a non-ion exchanged zeolite and the at least one impurity to be adsorbed is carbon monoxide is excluded.

5,589,152

CARBON FIBRILS, METHOD FOR PRODUCING SAME AND ADHESIVE COMPOSITIONS CONTAINING SAME

Howard G. Tennent, Kennett Square, Pa.; James J. Barber, Arlington, Mass., and Robert Hoch, Middle Village, N.Y., assignors to Hyperion Catalysis International, Inc., Cambridge, Mass.

Continuation of Ser. No. 978,634, Nov. 19, 1992, abandoned, which is a division of Ser. No. 593,319, Oct. 1, 1990, Pat. No. 5,165,909, which is a continuation of Ser. No. 871,676, Jun. 6, 1986, abandoned, which is a continuation-in-part of Ser. No. 678,701, Dec. 6, 1984, Pat. No. 4,663,230. This application

Jun. 6, 1995, Ser. No. 466,878

Int. Cl.⁶ D01F 9/12

U.S. Cl. 423—447.3

28 Claims

1. A fibril mat comprising a plurality of carbon fibrils formed by collecting said fibrils to form a mat, wherein each of said fibrils is characterized by a substantially constant diameter, length greater than about 5 times the diameter, an ordered outer region of catalytically grown, multiple, substantially continuous layers of ordered carbon atoms having an outside diameter between about 3.5 and 70 nanometers, and a distinct inner core region, each of the layers and the core being disposed substantially concentrically about the cylindrical axis of the fibril, wherein each of said fibrils is substantially free of pyrolytically deposited thermal carbon and the diameter of said fibril being equal to the outside diameter of said ordered outer region.

5,589,153

SYNTHESIS OF CRYSTALLINE POROUS SOLIDS IN AMMONIA

Juan M. Garces; Dean M. Millar, and Kevin E. Howard, all of Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Division of Ser. No. 333,670, Nov. 3, 1994. This application

Jun. 2, 1995, Ser. No. 460,166

Int. Cl.⁶ C01B 37/02

U.S. Cl. 423—705

2 Claims

1. A crystalline microporous silica having a composition represented by



wherein y' is a number ranging from 0 to about 0.5 and n' is a number ranging from 0 to about 1, the silica being isostructural with zeolite beta as determined by X-ray diffraction.

5,589,151

PROCESS FOR THE PREPARATION OF HIGH-PURITY LIQUID NITROGEN

Daniel Gary, Versailles, France, assignor to L'Air Liquide Societe Anonyme Pour L'Etude et L'Exploitation des Procédés Georges Claude, Paris, France

Continuation-in-part of Ser. No. 230,500, Apr. 20, 1994, abandoned. This application Jan. 25, 1995, Ser. No. 378,447

Claims priority, application France, Dec. 31, 1993, 93 15958; European Pat. Off., Dec. 22, 1994, 94402

Int. Cl.⁶ G01B 21/00

U.S. Cl. 423—351

36 Claims

1. Process for the preparation of high purity liquid nitrogen substantially free from at least one impurity selected from the group consisting of hydrogen, carbon monoxide and oxygen, comprising placing liquid nitrogen to be purified in contact with at least one adsorbent selected from the group consisting of non-ion exchanged zeolites, zeolites exchanged with at least one ion of a transition metal, and porous metal oxides, said adsorbent adsorbing at least one said impurity, and recovering said high purity liquid

5,589,154

METHODS FOR THE PREVENTION OR TREATMENT OF VASCULAR HEMORRHAGING AND ALZHEIMER'S DISEASE

Stephen Anderson, Princeton, N.J., assignor to Rutgers, The State University of New Jersey, Piscataway, N.J.

Filed Nov. 22, 1994, Ser. No. 347,144

Int. Cl.⁶ A61K 51/00;39/395;35/14; G01N 33/53

U.S. Cl. 424—1.41 5 Claims

1. A method for diagnosing the presence of β -amyloid peptide in an individual, which comprises administering to said individual a labeled agent that specifically binds to β -amyloid peptide, in an amount sufficient to permit the detection of any of said β -amyloid peptide that binds to said agent, wherein said agent is a tissue plasminogen activator analog that binds β -amyloid peptide or binds fibrils containing β -amyloid peptide, but which does not bind fibrin.

5,589,155

MUTAGENESIS TESTING USING TRANSGENIC NON-HUMAN ANIMALS CARRYING TEST DNA SEQUENCES

Joseph A. Sorge, San Diego, and Jay M. Short, Encinitas, both of Calif., assignors to Union Bank of California, N.A., San Francisco, Calif.

Continuation of Ser. No. 947,947, Sep. 18, 1992, abandoned, which is a continuation of Ser. No. 505,676, Apr. 5, 1990, abandoned, which is a continuation-in-part of Ser. No. 45,037, May 1, 1987, abandoned. This application Mar. 6, 1995, Ser. No. 398,933

Int. Cl.⁶ A61K 49/00; C12N 15/00

U.S. Cl. 424—9.2 6 Claims

1. A method for testing the mutagenic potential of an agent comprising:

- exposing a transgenic mouse to an agent to be tested, said transgenic mouse comprising somatic and germ cells containing an integrated transgenic test DNA sequence, said test DNA sequence being flanked by the cos sites of a lambda bacteriophage and recoverable from said cells via said cos sites, the expression of said test DNA sequence being capable of detection in *E. coli* by bioassay, wherein said test DNA sequence encodes a protein selected from the group consisting of LacZ and LacI;
- isolating a sample of genomic DNA from said exposed transgenic mouse;
- treating said sample of genomic DNA with a lambda bacteriophage packaging extract to excise said integrated transgenic test DNA sequence and then package said excised test DNA sequence;
- infecting *E. coli* with said packaged test DNA sequence;
- determining by bioassay in said infected *E. coli* the frequency of mutation of said test DNA sequence.

5,589,156

PRILOCAINE AND HYDROFLUOROCARBON AEROSOL PREPARATIONS

Richard A. Henry, 7 Toronto Street, Kingston, Ontario, Canada

Continuation-in-part of Ser. No. 408,877, Mar. 24, 1995, and Ser. No. 236,408, May 2, 1994, Pat. No. 5,453,445, and Ser. No. 405,930, Mar. 17, 1995. This application May 5, 1995, Ser. No. 435,812

Int. Cl.⁶ A61K 9/12

U.S. Cl. 424—45 29 Claims

1. An aerosol composition for delivering topical local anesthetic to a mammal, comprising:

1-99% wt of hydrofluorocarbon propellant selected from the group consisting of 1,1,1,2-tetrafluoroethane and 1,1,1,2,3,3,3-heptafluoropropane and combinations thereof, said hydrofluorocarbon propellant being the sole propellant in said aerosol composition;

1-99% wt prilocaine base solubilized within said hydrofluorocarbon propellant, said prilocaine base and said hydrofluorocarbon propellant forming a solution that is stable at reduced temperature of at least -82° C.; and

0.01-99% wt of a pharmaceutical other than prilocaine solubilized in said hydrofluorocarbon propellant selected from the group consisting of bronchodilators, antiinflammatories, antitussives, vasoactive drugs, vasoconstrictors, antibiotics which are not antiseptics, peptides which are not enzymes, steroids, enzymes, antihistamines, hormones, 5-aminolevulinic acid, antiseptics, disinfectants, procaine, cocaine, chlorprocaine, tetracaine, mepivacaine, lidocaine, bupivacaine, etidocaine, ropivacaine, benzocaine, and phenylephrine.

5,589,157

HAIRSPRAYS AND ACRYLIC POLYMER COMPOSITIONS FOR USE THEREIN

James C. Hatfield, St. Albans, W. Va., assignor to Amerchol Corporation, Edison, N.J.

Continuation-in-part of Ser. No. 953,496, Sep. 29, 1992, Pat. No. 5,413,775. This application May 8, 1995, Ser. No. 437,038

Int. Cl.⁶ A61K 7/11;7/075;9/16; C08F 218/10

U.S. Cl. 424—47 16 Claims

1. In an aqueous polymer composition comprising:
(1) a copolymer of (a) an alkyl acrylate wherein the alkyl group contains from 1 to 5 carbon atoms; (b) an alkyl methacrylate wherein the alkyl group contains from 1 to 5 carbon atoms; and (c) at least one acrylate acid having from 3 to 5 carbon atoms; and

(2) water;
the improvement wherein the polymer composition further comprises an alkoxylated surfactant having a surface tension of from greater than about 32.2 dynes/cm to less than about 48.2 dynes/cm and a residual level of said alkyl acrylate of less than 100 ppmw.

5,589,158

FLAVOR ENHANCER

Amrit S. Mankoo, New Hampton, N.Y., assignor to Bush Boake Allen Inc., Montvale, N.J.

Filed Nov. 17, 1994, Ser. No. 340,930

Int. Cl.⁶ A61K 7/16

U.S. Cl. 424—49 13 Claims

1. A flavor enhancing composition comprising:
between about 30% and 90% by weight benzyl benzoate; and,
between about 3% and 15% by weight neryl acetate.

5,589,159

DISPERSIBLE PARTICULATE SYSTEM FOR DESENSITIZING TEETH

Kenneth Markowitz, Fanwood, and Mikhail Y. Gelfer, Jersey City, both of N.J., assignors to Block Drug Company Inc., Jersey City, N.J.

Filed Apr. 11, 1995, Ser. No. 419,816

Int. Cl.⁶ A61K 7/16;7/18;47/04

U.S. Cl. 424—49 16 Claims

1. In a composition for treating hypersensitive teeth comprising an effective desensitizing amount of a desensitizing agent and a carrier therefor, the improvement which comprises the desensitizing agent being bectorite clay.

5,589,160

DENTIFRICE COMPOSITIONS

David E. Rice, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

Filed May 2, 1995, Ser. No. 434,149

Int. Cl.⁶ A61K 7/16;7/18

U.S. Cl. 424—49 10 Claims

1. A dentifrice composition, comprising:
A) a precipitated silica abrasive composition, comprising:
a.) a low or medium structure, precipitated silica, comprising particles wherein said particles have:
i.) a mean particle size of from about 5 to about 11 microns (s.d.< 9);
ii.) an Einlehnner hardness of from about 0.8 to about 2.5 for abrasive to brass screen and from about 5 to below about 8 for abrasive to polyester screen;
iii.) an oil absorption of from 95 ml/100 gm to about 135 ml/100 gm; and
iv.) a radioactive dentin abrasion of from about 25 to about below 80;

and
b.) a low or medium structure, precipitated silica, comprising particles wherein said particles have:
i.) a mean particle size of from about 5 to about 11 microns (s.d.< 9);

ii.) an Einlehnner hardness of from about 3 to about 8 for abrasive to brass screen and from 8 to about 11 for abrasive to polyester screen;
iii.) an oil absorption of from about 70 ml/100 gm to about below 95 ml/100 gm; and
iv.) a radioactive dentin abrasion of from 80 to about 200 wherein at least about 70% of all of said particles have a diameter of below about 25 microns and wherein the pellicle cleaning ratio is from about 90 to about 135 and the radioactive dentin abrasion is from about 60 to about 100 with a pellicle cleaning ratio/radioactive dentin abrasion ratio of from about 1.25 to about 1.75 and wherein the ratio of the silica in a.) to the silica in b.) is from about 90:10 to about 40:60, respectively;

and
B). from about 0.1% to about 99% of an orally-acceptable dentifrice carrier.

5,589,161

PIGMENTATION ENHANCER AND METHOD

Bryan B. Fuller, Edmond, Okla., assignor to The Board of Regents of the University Oklahoma, Norman, Okla.

Continuation of Ser. No. 943,998, Sep. 11, 1992, which is a continuation of Ser. No. 451,420, Dec. 15, 1989. This application Sep. 8, 1994, Ser. No. 302,153

Int. Cl.⁶ A61K 7/42;7/40

U.S. Cl. 424—59 12 Claims

1. A composition of matter for stimulating melanogenesis in melanocytes of human epidermis, comprising:
an effective amount of a methylxanthine effective in increasing tyrosinase activity in the melanocytes to an amount sufficient to result in increasing levels of melanin in a human melanocyte in vivo; and

an effective amount of a pharmaceutically acceptable topical carrier capable of delivering the methylxanthine to the melanocyte under in vivo conditions.

5,589,162

HAIR SETTING AGENT COMPOSITION

Tsutomu Muraoka, Tokyo, Japan, assignor to Kao Corporation, Tokyo, Japan

Filed Apr. 19, 1995, Ser. No. 425,062

Claims priority, application Japan, Apr. 28, 1994, 6-091315

Int. Cl.⁶ A61K 7/11;7/06

U.S. Cl. 424—70.12 6 Claims

1. A hair setting agent composition comprising:
(A) 0.01 to 10% by weight of a water-dispersible polyester resin having a —SO₃M group in which M is a hydrogen or metal ion in an amount sufficient to render the polyester dispersible in water;
(B) 0.01 to 10% by weight of at least one silicone derivative selected from the group consisting of a polyether-modified silicone, a dimethyl polysiloxane, a methylphenyl polysiloxane, a diphenyl polysiloxane, a C₁₀₋₅₀ alkyl-modified silicone, an alkoxy-modified silicone, an amino-modified silicone, a Bunte salt-modified silicone and a silicone resin; and
(C) 0.1 to 40% by weight of a C₁₂₋₂₀ hydrocarbon oil.

5,589,163

PERMANENT WAVE COMPOSITION AND METHOD


Paul Neill, Hinsdale; Lorelei Brandt, Cary; Priscilla Walling, Darien; Arun Nandagiri, Libertyville, and Norman Meltzer, Morton Grove, all of Ill., assignors to Helene Curtis, Inc., Chicago, Ill.

Continuation-in-part of Ser. No. 194,076, Feb. 9, 1994, abandoned. This application Dec. 14, 1994, Ser. No. 355,653

The portion of the term of this patent subsequent to Feb. 9, 2014, has been disclaimed.

Int. Cl.⁶ A61K 7/09;7/06

U.S. Cl. 424—70.51 12 Claims



1. A composition capable of breaking sulfur to sulfur bonds in human hair when in contact with said human hair so that said hair can be reconfigured, comprising an aqueous solution containing an ionic complex formed from a cationic compound, in solution, and an anionic compound, in solution, at a molar ratio of cationic compound to anionic compound of about 1:1, said aqueous solution having a pH of about 7 and having no acid that interferes with ionic complexing of said cationic and anionic compounds at the pH of the composition, thereby reducing the waving efficiency; wherein the cationic compound, in solution, forms a cation of cysteamine; and wherein the anionic compound, in solution, forms a thioglycolate anion.

5,589,164

STABILIZATION OF BIOWASTES

James P. Cox, and Robert W. Duffy Cox, both of 246 E. Bartlett Rd., Lynden, Wash. 98264

Continuation-in-part of Ser. No. 287,183, Aug. 8, 1994, abandoned, which is a continuation of Ser. No. 886,417, May 19, 1992, Pat. No. 5,352,444. This application Jun. 7, 1995, Ser. No. 476,268

Int. Cl.⁶ A61L 11/00

U.S. Cl. 424—76.5

51 Claims

1. A biowaste treatment agent comprising a surfactant component, a metal component, and an aldehyde; said surfactant component comprising about 1.0% to about 99.0% by weight of the treatment agent; said metal component comprising from about 0.5% to about 85.0% by weight of the treatment agent; and said aldehyde comprising about 0.1% to about 80.0% by weight of the treatment agent.

5,589,165

COSMETIC

Masashi Yoshida; Tomiyuki Nanba; Keiichi Uehara; Osamu Sakurai; Hideki Takahashi, and Hiroshi Fukui, all of Yokohama, Japan, assignors to Shiseido Co., Ltd., Tokyo, Japan
Filed Dec. 22, 1994, Ser. No. 361,598

Claims priority, application Japan, Dec. 28, 1993, 5-353169

Int. Cl.⁶ A61K 31/74; 7/027


U.S. Cl. 424—78.03

4 Claims


1. A cosmetic, comprising an organofluorinated modified silicone resin comprising units (1), (2) and (3) as shown below:

(1) R_1SiO_x units(2) SiO_2 units

(3) Rf_2SiO units and/or $RfSiO$ units wherein R denotes a hydrocarbon group with a carbon number of 1-6 or a phenyl group, and Rf denotes $-(CH_2)_mC_nF_{2n+1}$, m is an integer 2-4, and n is an integer 1-12, said cosmetic being selected from the group consisting of oil foundations, liquid foundations, liquid lip color, hand cream, mascara, pre-makeup, sunscreen, and powder foundations, said cosmetic further comprising at least one component selected from the group consisting of water, perfume, coloring agent(s), and powder, wherein the organofluorinated modified silicone resin is blended into the cosmetic with one or more silicone oils selected from the group consisting of



wherein n denotes an integer 0-5, and



wherein n denotes an integer 3-7.

5,589,166

CROSS-LINKED QUATERNARY AMMONIUM DERIVATIVES OF POLY(N,N-DIALKYLALLYL) AMMONIUM POLYMERS

Fergus McTaggart, Wilmslow; Denis Pemberton, Stockport, and Graham J. Smith, Macclesfield, all of United Kingdom, assignors to Zeneca Limited, London, United Kingdom
Division of Ser. No. 252,521, Jun. 1, 1994, Pat. No. 5,462,730, which is a continuation of Ser. No. 804,131, Dec. 6, 1991, abandoned. This application Jun. 5, 1995, Ser. No. 465,006

Claims priority, application United Kingdom, Dec. 7, 1990, 9026616; May 10, 1991, 9110180

Int. Cl.⁶ C08F 8/02; 12/002; C08J 3/24

U.S. Cl. 424—78.35

11 Claims

1. An insoluble swellable polymeric allylammonium derivative D1 comprising in random order:



(i) at least 10 mole percent of quaternary propylammonium structural units of formula I:



wherein one of R^1 , R^2 and R^3 is (1-16C)alkyl, (4-12C) cycloalkyl or phenyl-(1-4C)alkyl, the latter phenyl moiety optionally bearing one or two substituents independently selected from the group consisting of halogeno, (1-4C)alkyl and (1-4C) alkoxy;

another of R^1 , R^2 and R^3 is (1-4C)alkyl; and the other of R^1 , R^2 and R^3 is (1-4C)alkyl optionally bearing a carbamoyl substituent, or is (2-4C)alkyl bearing a hydroxy substituent on other than an α -carbon atom; and Y is a physiologically acceptable anion;

(ii) about 0.5 to 10 mole percent of cross-linking structural units of formula IIa and/or IIb:



wherein R^4 , R^6 , R^7 and R^8 are independently hydrogen or one of the values of R^1 , R^2 and R^3 defined above; one of R^9 and R^{10} is hydrogen or (1-4C)alkyl; the other of R^9 and R^{10} has one of the values of R^1 , R^2 and R^3 defined above;

Y has the meaning defined above; and

X is a cross-linking group; and

(iii) the remainder of structural propylamine units of formula III:



R^{11} and R^{12} are independently hydrogen or one of the values of R^1 , R^2 and R^3 defined above; and Y has the meaning defined above;

said derivative D1 having the property of swelling by between about 2 and 200 times in volume in at least one of water, 0.15M aqueous sodium chloride solution, and ethanol.

5,589,167

EXCIPIENT STABILIZATION OF POLYPEPTIDES TREATED WITH ORGANIC SOLVENTS

Jeffrey L. Cleland, San Carlos, and Andrew J. S. Jones, San Mateo, both of Calif., assignors to Genentech, Inc., South San Francisco, Calif.

PCT No. PCT/US94/01666, § 371 Date Apr. 8, 1994, § 102(e) Date Apr. 8, 1994, PCT Pub. No. WO94/19020, PCT Pub. Date Sep. 1, 1994

Continuation-in-part of Ser. No. 21,421, Feb. 23, 1993, abandoned. This PCT application Feb. 17, 1994, Ser. No. 256,187 Int. Cl.⁶ A61K 38/21; 38/27

U.S. Cl. 424—85.7

16 Claims

1. A method of stabilizing a polypeptide against denaturation in an organic solvent when treated with the organic solvent, wherein the method comprises admixing the polypeptide with a polyol, wherein the molecular weight of the polyol is less than about 70,000 kD and is trehalose, to form an admixture; and treating the admixture with the organic solvent.

5,589,168

PROBIOTIC

William D. Allen; Margaret A. Linggood, and Philip Porter, all of Bedford, Great Britain, assignors to Unilever Patent Holdings B.V., Vlaardingen, Netherlands

Continuation of Ser. No. 864,992, Apr. 8, 1992, abandoned.

This application Sep. 2, 1994, Ser. No. 300,207

Claims priority, application United Kingdom, Apr. 8, 1991, 9107305

Int. Cl.⁶ C12R 1/46; A61K 35/74; A23C 9/12

U.S. Cl. 424—93.4

4 Claims

1. Organisms of *Enterococcus faecium* selected from the group consisting of strain NCIMB 40371 and IBS-alleviating mutants thereof.

5,589,169

METHOD AND THERAPEUTIC COMPOSITIONS FOR THE PREVENTION OF FIBRIN DEPOSITION OR ADHESIONS

Marjorie A. Mohler, Oakland, and Tue H. Nguyen, San Mateo, both of Calif., assignors to Genentech, Inc., South San Francisco, Calif.

Continuation of Ser. No. 125,319, Nov. 25, 1987, abandoned, which is a continuation of Ser. No. 68,872, Jul. 1, 1987, abandoned. This application Apr. 13, 1990, Ser. No. 511,838

Int. Cl.⁶ A61K 38/49

U.S. Cl. 424—94.2

10 Claims

1. The method of treating an animal to prevent fibrin deposition or adhesion formation or reformation comprising administration of a composition to a site of potential fibrin or adhesion formation consequent to the animal undergoing surgery wherein the composition comprises a therapeutically effective amount of a sparingly soluble form of tissue plasminogen activator as a precipitated solid molecular form that is continuously released at that site for a period of time of about three days to two weeks.

5,589,170

CALCIUM INDEPENDENT CYTOSOLIC PHOSPHOLIPASE A₂/B ENZYMES

Simon Jones, Somerville, and Jin Tang, Canton, both of Mass., assignors to Genetics Institute, Inc., Cambridge, Mass.

Division of Ser. No. 281,193, Jul. 27, 1994, Pat. No. 5,466,595.

This application Apr. 14, 1995, Ser. No. 422,106

Int. Cl.⁶ A61K 38/46; C12N 9/20; C07H 21/04

U.S. Cl. 424—94.6

9 Claims

1. A composition comprising a purified phospholipase enzyme characterized by (a) activity in the absence of calcium; (b) a molecular weight of 86 kD on SDS-PAGE; and (c) the presence of

one or more amino acid sequences selected from the group consisting of SEQ ID NO: 3, SEQ ID NO: 4, SEQ ID NO: 5, SEQ ID NO: 6, SEQ ID NO: 7, SEQ ID NO: 8, SEQ ID NO: 9, SEQ ID NO: 10, SEQ ID NO: 11, SEQ ID NO: 12, SEQ ID NO: 13, SEQ ID NO: 14, and SEQ ID NO: 15, wherein Xaa represents any amino acid residue.

5,589,171

TREATMENT OF DUPUYTREN'S DISEASE WITH COLLAGENASE

Thomas L. Wegman, North Merrick, N.Y., assignor to Advance Biofactures of Curacao, Brevengat, Netherlands Antilles
Filed Aug. 22, 1994, Ser. No. 294,097

Int. Cl.⁶ A61K 38/48

U.S. Cl. 424—94.67

7 Claims

1. A method of treating an individual suffering from Dupuytren's disease which comprises applying an effective amount of collagenase to a fibrous of the affected fascia.

5,589,172

Patent Not Issued For This Number

5,589,173

METHOD AND THERAPEUTIC COMPOSITIONS FOR THE TREATMENT OF MYOCARDIAL INFARCTION

Donogh P. O'Brien, Harrow, England; Gordon A. Vehar, San Carlos, and Josiah N. Wilcox, Belmont, both of Calif., assignors to Genentech, Inc., South San Francisco, Calif.

Continuation of Ser. No. 76,280, Jun. 11, 1993, which is a continuation of Ser. No. 887,575, May 18, 1992, abandoned, which is a continuation of Ser. No. 237,595, Aug. 25, 1988, abandoned, which is a continuation of Ser. No. 209,665, Jun. 21, 1988, abandoned, which is a continuation-in-part of Ser. No. 110,255, Oct. 20, 1987, abandoned, which is a continuation-in-part of Ser. No. 926,977, Nov. 4, 1986, abandoned. This application Jun. 16, 1994, Ser. No. 260,662

Int. Cl.⁶ C07K 16/36; 14/745; A61K 39/395

U.S. Cl. 424—145.1

14 Claims

1. A method for dissolving and preventing reformation of an occluding thrombus precipitated by rupture of and atherosclerotic plaque in a mammal in need thereof comprising, administering to said mammal a tissue factor protein antagonist which neutralizes the procoagulant activity of tissue factor in an amount effective to prevent the reformation of the occluding thrombus and a thrombolytic agent in an amount effective to dissolve the occluding thrombus.

5,589,174

ANTI-HUMAN INFLUENZA VIRUS ANTIBODY

Yoshinobu Okuno, Toyonaka; Yuji Isegawa, Takatsuki; Fuyoko Sasao, Ibaraki, and Shigeharu Ueda, Nishinomiya, all of Japan, assignors to Takara Shuzo Co., Ltd., Kyoto-fu, Japan

Continuation-in-part of Ser. No. 054,016, Apr. 29, 1993, abandoned. This application Apr. 19, 1994, Ser. No. 229,781

Claims priority, application Japan, Sep. 17, 1992, 4-272538; Apr. 20, 1993, 5-115216; Mar. 16, 1994, 6-070194

Int. Cl.⁶ A61K 39/395; C07K 16/08; C12N 5/20; 15/06

U.S. Cl. 424—147.1

10 Claims

1. An anti-human influenza virus antibody having the following characteristics:

- (a) specifically binds to the stem region of hemagglutinin of human influenza A virus subtypes H1N1 and H2N2;
- (b) does not specifically bind to the stem region of hemagglutinin of human influenza A virus subtype H3N2;

- (c) has a neutralization activity for human influenza A virus subtypes H1N1 and H2N2; and
(d) has no neutralization activity for human influenza A virus subtype H3N2.

5,589,175

PEPTIDES FOR INDUCTION OF NEUTRALIZING ANTIBODIES AGAINST HUMAN IMMUNODEFICIENCY VIRUS

Anders Vahlne, Hovås; Bo Svennerholm, Göteborg; Lars Rymo, Hovås; Stig Jeansson, and Peter Horal, both of Göteborg, all of Sweden, assignors to Syntello Vaccine Development KB, Göteborg, Sweden
Continuation of Ser. No. 8,092, Jan. 22, 1993, abandoned, which is a continuation of Ser. No. 589,422, Sep. 27, 1990, abandoned. This application Mar. 27, 1995, Ser. No. 410,384
Int. Cl.⁶ A61K 39/21; 39/12; 38/14; C07K 5/00
U.S. Cl. 424—208.1

8 Claims


1. A composition consisting of a peptide of the amino acid sequence: X-Gly-Glu-Ile-Lys-Asn-Cys-Ser-Phe-Asn-Ile-Ser-Thr-Ser-Ile-Arg-Gly-Lys-Val-Gln-Lys-Glu-Tyr-Ala-Phe-Phe-Y-Z in an amount effective to elicit the production of antibodies to human immunodeficiency virus in a primate, wherein X is selected from the group consisting of a hydrogen atom of the amino terminal NH₂ group of the peptide and an additional amino acid selected to facilitate coupling; Y is absent or cysteine and Z is selected from the group consisting of the carboxyl group of the carboxy terminal amino acid and an amido group.

5,589,176

METHODS OF MAKING DOUBLY POROUS DEVICE

William J. Seare, Jr., 3190 Chula Vista Cir., Salt Lake City, Utah 84121
Division of Ser. No. 156,675, Nov. 22, 1993, which is a continuation of Ser. No. 779,387, Oct. 18, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 477,409
Int. Cl.⁶ A61K 9/00

25 Claims



1. A method of forming a device having a first porous portion having continuously interconnected pores and a second porous portion having continuously interconnected pores, said method comprising the steps of:

- obtaining an open-cell porous mold form corresponding to the first porous portion, said open-cell porous mold form comprising particles formed into a mass of continuously interconnected particles and shaped and solidified to thereby define continuously interconnected pores and connecting interstices within said first porous portion;
- selectively forming a stable coating layer upon the surface of the particles of said mold form to thereby define continuously interconnected pores and connecting interstices within the second porous portion, said stable coating layer being formed by the steps of:
 - selectively filling said pores and interstices of said open-cell porous mold form with a selected coating material such that the open-cell porous mold form mass is maintained;

- selectively removing a substantial portion of said coating material such that a continuous coating of a selected thickness remains upon the particles of said open-cell porous mold form; and
- solidifying said coating material; and
- selectively removing the open-cell porous mold form such that the stable coating layer defines a membrane separating the first porous portion and the second porous portion of said device.

5,589,177

RINSE-OFF WATER-IN-OIL-IN-WATER COMPOSITIONS

Craig A. Herb, Chicago; Liang B. Chen, Hoffman Estates; Judy B. Chung, Glenview; Michelle A. Long, Lombard; Wei M. Sun, Palatine; Gerald P. Newell, Hoffman Estates; Kimberly Kamis, Glenview, and Richard M. Brucks, Chicago, all of Ill., assignors to Helene Curtis, Inc., Chicago, Ill.
Filed Dec. 6, 1994, Ser. No. 349,963
Int. Cl.⁶ A61K 7/00; 7/08; C07F 7/08

22 Claims

1. A rinse-off water-in-oil-in-water multiple emulsion composition comprising:

- about 40% to about 99% by weight of the total composition of an external aqueous phase comprising water; and
 - about 1% to about 60% by weight of the total composition of a primary water-in-oil emulsion, said primary emulsion comprising:
 - about 1% to about 95% by weight of the primary emulsion of an aqueous phase, said aqueous phase comprising: (A) about 0.1% to about 30% by weight of the primary emulsion of a first topically-active compound selected from the group consisting of a hair fixative and a hair fixative resin and (B) water,
 - about 0.5% to about 95% by weight of the primary emulsion of an oil phase comprising a volatile silicone compound, and
 - about 0.1% to about 20% by weight of the primary emulsion of a surfactant phase comprising an oil-soluble silicon-based surfactant;
- wherein the external aqueous phase is free of a polymeric gelling agent.


5,589,178

COSMETIC AND/OR DERMATOLOGICAL COMPOSITION FOR THE TREATMENT OF AGING, CONTAINING CERAMIDES, AND THE USE THEREOF

Lucien Aubert, Cap d'Ail, and Francoise Gagnebien-Cabanne, Chatillon, both of France, assignors to L'Oréal, Paris, France
Filed Dec. 30, 1994, Ser. No. 366,760
Claims priority, application France, Jan. 10, 1994, 94 00173
Int. Cl.⁶ A61K 6/00; 31/615; 31/19; 31/16; 31/07

14 Claims

1. A method for combating the aging of skin, comprising applying to the skin of a subject in need thereof and whose skin is sensitive to the action of an anti-aging active agent, an effective amount of a composition comprising at least one anti-aging active agent having an irritant effect, a cosmetically or dermatologically acceptable medium, and a mollifying agent which is a ceramide of formula (I):




R₁ is a saturated or unsaturated, linear or branched C₁₀ to C₂₆ alkyl group;
R₂ is a saturated or unsaturated, linear or branched C₁₂ to C₃₂ alkyl group;
R₃ is H or $-\text{CO}-\text{CHOH}-\text{R}_2$; and
n is 0 or 1.

5,589,179

COMPOSITION CONTAINING A NON-PHOTOCATALYTIC METAL OXIDE AND TOCOPHEROL, ITS USE IN THE COSMETICS AND/OR DERMATOLOGICAL FIELD AND PROCESSES EMPLOYING IT

Boudiaf Boussouira, Paris, and Quang L. Nguyen, Antony, both of France, assignors to L'Oréal, Paris, France
Filed Mar. 13, 1995, Ser. No. 402,655
Claims priority, application France, Mar. 11, 1994, 94 02882
Int. Cl.⁶ A61K 7/48

U.S. Cl. 424—401
7 Claims



1. A composition for inhibiting the photoperoxidation of unsaturated lipids, which comprises:
- 0.02–6% by weight of at least one tocopherol selected from the group consisting of α-tocopherol, β-tocopherol, γ-tocopherol, δ-tocopherol and a mixture thereof;
 - 0.1–5% by weight of zinc oxide or dioxide; and
 - 0.005–0.3% by weight of a metal-inactivating complexing agent selected from the group consisting of ethylenediamine-tetra(methylenephosphonic acid), diethylenetriaminepenta(methylenephosphonic acid), sodium salts thereof, and a mixture thereof.

5,589,180

METHOD FOR TREATING NERVE INJURY PAIN ASSOCIATED WITH SHINGLES (HERPES-ZOSTER AND POST-HERPETIC NEURALGIA) BY TOPICAL APPLICATION OF LIDOCAINE

Harry Hind, Los Altos, Calif., assignor to Hind Health Care, Inc., Los Altos, Calif.
Continuation of Ser. No. 388,375, Feb. 14, 1995, abandoned, which is a continuation of Ser. No. 198,223, Feb. 16, 1994, Pat. No. 5,411,738, which is a continuation-in-part of Ser. No. 526,771, May 18, 1990, which is a continuation of Ser. No. 325,373, Mar. 17, 1989, abandoned. This application Mar. 5, 1996, Ser. No. 611,168

Int. Cl.⁶ A61F 13/00; 13/15; A61L 15/00; 15/16
U.S. Cl. 424—402
6 Claims
1. A plaster composition for treatment of pain from herpes zoster or post-herpetic neuralgia comprising:
a physiologically acceptable adhesive comprising 2–10% by weight lidocaine at least in part as the free base;
at least one of propylene glycol and glycerin as a co-solvent; and
a covering.

5,589,181

INSECT REPELLENT


Franz Bencsits, Wehrenbachhalde 54, 8053 Zürich, Switzerland, assignor to Franz Bencsits, and Perycut-Chemie AG, both of Switzerland
PCT No. PCT/EP93/00427, § 371 Date Nov. 23, 1994, § 102(e) Date Nov. 23, 1994, PCT Pub. No. WO93/16594, PCT Pub. Date Sep. 2, 1993
PCT Filed Feb. 24, 1993, Ser. No. 290,991
Claims priority, application Germany, Feb. 27, 1992, 42 06 090.7

Int. Cl.⁶ A01N 25/02
U.S. Cl. 424—405
16 Claims
1. An insect repellent consisting essentially of (a) an active substance combination of 1 to 99% by weight of at least one fatty acid alkyl ester having 1 to 4 carbon atoms in the alkyl group and 99 to 1% by weight of at least one natural, nature-identical or synthetic fatty alcohol having 5 to 18 carbon atoms in (b) a carrier of at least one natural or nature-identical normally liquid vegetable fatty oil selected from the group consisting of rape-seed oil, sunflower oil, peanut oil, soy oil, and coconut oil.

5,589,182

COMPOSITIONS AND METHOD OF TREATING CARDIO-, CEREBRO-VASCULAR AND ALZHEIMER'S DISEASES AND DEPRESSION

Renki Tashiro, Asahichyo 2-24-15, Fuchyu, Tokyo, Japan, and Ruth H. Pater, 106 Tuckahoe Trace, Yorktown, Va. 23693
Filed Dec. 6, 1993, Ser. No. 161,350
Int. Cl.⁶ A61K 9/08; 9/14; 9/20; 9/48; 35/78
U.S. Cl. 424—423
35 Claims



1. A pharmaceutical composition in unit dosage form suitable for the treatment of a condition selected from the group consisting of

cardiovascular disease and cerebrovascular disease comprising a therapeutically effective amount of a member selected from the group consisting of:

- I. a mixture of aqueous extracts of:
 - a. root tissue of the plant *Asparagus cochinchinensis* containing asparagine, β -sitosterol and 5-methoxymethylfurfural,
 - b. root tissue of the plant *Ophiopogon japonicus* containing glucose, starch, vitamin A and β -sitosterol,
 - c. root tissue of the plant *Salvia miltiorrhiza* containing tanshinone A $C_{18}H_{12}O_3$, tanshinone B $C_{19}H_{18}O_3$ and tanshinone C $C_{19}H_{20}O_3$,
 - d. root tissue of the plant *Angelica acutiloba kitagawa* containing ligustillide,
 - e. root tissue of the plant *Rehmannia glutinosa Liboschitz* containing rehmannin, xylitol, glucose, mannitol, iron, vitamin A and catalpol,
 - f. white stone-like material formed by bacteria on surface of underground root of tree *Poria cocos wolf* containing ergosterol,
 - g. ripe fruits of the plant *Schizandra chinensis* containing citral, schizandrin $C_{23}H_{32}O_6$, vitamin A, vitamin C and d-ylangene,
 - h. root tissue of the plant *Platycodon grandiflorum* containing polygalacic acid platycoside, inulin and phytosterol,
 - i. root tissue of the plant *Polygala tenuifolia* containing tenuifolin, polygallitol $C_6H_{12}O_5$ and onscin $C_{24}H_{42}O_5$,
 - j. dried seeds of the plant *Zizyphus jujuba* containing betulinic acid $C_{40}H_{74}O_4$, betulin $C_{30}H_{50}O_2$, β -sitosterol, fatty acids, vitamin A and organic acids,
 - k. dried seeds of the plant *Biota orientalis* containing borneol and fatty acids,
 - l. root tissue of the plant *Pueraria pseudo-hirsuta* containing flavon, puerarin and daidzein,
 - m. root tissue of the plant *Panax ginseng* containing ginsenoside, panacene $C_{15}H_{24}$, panaquilon $C_{32}H_{56}O_{14}$, panaxin $C_{23}H_{38}O_{10}$, organic acids, vitamin A, vitamin B₁, vitamin B₂, vitamin C, inorganic salts and starch,
 - n. root tissue of the plant *Codonopsis pilosula* containing alkaloid, saponin, protein, starch, vitamin B₁ and vitamin B₂,
 - o. root tissue of the plant *Scrophularia ningpoensis* containing harpagide, phytosterol, linoleic acid and alkaloid,
 - p. root tissue of the plant *Glycyrrhiza uralensis* containing glycyrrhizic acid, calcium salt, potassium salt, glycyrrhizin, glycyrrhizic acid, liquiritigenin $C_{21}H_{32}O_9$, glucose, mannitol, malic acid and l-asparagine,
 - q. root tissue of the plant *Panax pseudo-ginseng* containing pseudo-ginseng A $C_{30}H_{52}O_{10}$, pseudo-ginseng B $C_{23}H_{38}O_{10}$ and flavon,
 - r. the whole plant *Ganoderma japonicum* containing amino acid, protein, sterol and alkaloid,
 - s. root tissue of the plant *Coptis chinensis* containing berberine $C_{20}H_{19}O_5N$, coptisine $C_{19}H_{15}O_5N$, palmatine $C_{21}H_{23}O_5N$ and woorenine $C_{20}H_{17}O_5N$,
 - t. flower heads of the plant *Chrysanthemum morifolium* containing adenine $C_5H_5N_5$, stachydrine $C_7H_{13}NO$, choline and oil, and
 - u. skins of the plant *Phellodendron amurense* containing berberine, obakunone $C_{26}H_{40}O_7$, obakulactone $C_{26}H_{40}O_6$ and dictamnolactone $C_{28}H_{40}O_6$;

II. a mixture of the aqueous extracts of:

- I.a.,
- I.b.,
- I.c.,
- I.d.,
- I.e.,
- I.f.,
- I.g.,
- I.h.,
- I.i.,
- I.k.,
- I.l.,
- I.m.,
- I.n.,
- I.o.,

- I.p.,
- I.q., and
- I.r.,

III. a mixture of the aqueous extracts of:

- I.a.,
- I.b.,
- I.c.,
- I.d.,
- I.e.,
- I.f.,
- I.g.,
- I.h.,
- I.i.,
- I.k.,
- I.l.,
- I.m.,
- I.o.,
- I.p.,
- I.r.,
- I.s.,
- I.t., and

IV. a mixture of finely divided:

1. root tissue of the plant *Salvia miltiorrhiza* containing tanshinone A $C_{18}H_{12}O_3$, tanshinone B $C_{19}H_{18}O_3$ and tanshinone C $C_{19}H_{20}O_3$,
2. root tissue of the plant *Panax pseudo-ginseng* containing ginsenoside, panacene $C_{15}H_{24}$, panaquilon $C_{32}H_{56}O_{14}$, panaxin $C_{23}H_{38}O_{10}$, organic acids, vitamin A, vitamin B₁, vitamin B₂, vitamin C, inorganic salts and starch,
3. root tissue of the plant *Red ginseng* containing ginsenoside, panacene $C_{15}H_{24}$, panaquilon $C_{32}H_{56}O_{14}$, panaxin $C_{23}H_{38}O_{10}$, organic acids, vitamin A, vitamin B₁, vitamin B₂, vitamin C, inorganic salts and starch, and
4. Amber, a hard translucent fossil resin buried between roots of old trees, containing succinoabietinolic acid $C_{40}H_{60}O_5$, succinogluinic acid $C_{24}H_{36}O_2$, succinoresinol, succinoabietinol $C_{40}H_{60}O$ and fatty acids,

wherein, in composition I, the weight percentage of each plant tissue, based on the total weight of said plants from which said mixture of aqueous extracts is derived, is in the range of:

- from about 5% to about 20% of a.;
 - from about 5% to about 20% of b.;
 - from about 5% to about 20% of c.;
 - from about 5% to about 20% of d.;
 - from about 5% to about 20% of e.;
 - from about 5% to about 16% of f.;
 - from about 1% to about 15% of g.;
 - from about 1% to about 6% of h.;
 - from about 1% to about 10% of i.;
 - from about 1% to about 10% of j.;
 - from about 1% to about 10% of k.;
 - from about 1% to about 10% of l.;
 - from about 1% to about 10% of m.;
 - from about 1% to about 20% of n.;
 - from about 1% to about 15% of o.;
 - from about 0.1% to about 2% of p.;
 - from about 1% to about 15% of q.;
 - from about 1% to about 10% of r.;
 - from about 1% to about 5% of s.;
 - from about 1% to about 10% of t.; and
 - from about 1% to about 10% of u.;
- wherein, in composition II, the weight percentage of each plant tissue, based on the total weight of said plants from which said mixture of aqueous extracts is derived, is in the range of:
- from about 3% to about 15% of a.;
 - from about 3% to about 15% of b.;
 - from about 5% to about 20% of c.;
 - from about 3% to about 15% of d.;
 - from about 5% to about 20% of e.;
 - from about 5% to about 20% of f.;
 - from about 2% to about 15% of g.;
 - from about 1% to about 5% of h.;
 - from about 2% to about 15% of i.;
 - from about 2% to about 15% of j.;
 - from about 2% to about 5% of k.;

- from about 2% to about 15% of l.;
- from about 1% to about 10% of m.;
- from about 2% to about 15% of n.;
- from about 3% to about 15% of o.;
- from about 0.1% to about 2% of p.;
- from about 3% to about 15% of q.; and
- from about 3% to about 15% of r.;

wherein, in composition III, the weight percentage of each plant tissue, based on the total weight of said plants from which said mixture of aqueous extracts is derived, is in the range of:

- from about 5% to about 20% of a.;
- from about 2% to about 10% of b.;
- from about 2% to about 10% of c.;
- from about 2% to about 10% of d.;
- from about 2% to about 10% of e.;
- from about 2% to about 10% of f.;
- from about 2% to about 10% of g.;
- from about 2% to about 4% of h.;
- from about 2% to about 10% of i.;
- from about 2% to about 10% of j.;
- from about 1% to about 5% of k.;
- from about 2% to about 10% of l.;
- from about 2% to about 8% of m.;
- from about 2% to about 15% of o.;
- from about 0.1% to about 2% of p.;
- from about 2% to about 10% of r.;
- from about 1% to about 5% of s.; and
- from about 1% to about 5% of t.;

and wherein, in composition IV, the weight percentage of each plant tissue, based on the total weight of said plants from which said mixture of finely divided tissue is derived, is in the range of:

- from about 20% to about 60% of l.;
- from about 20% to about 60% of 2.;
- from about 10% to about 30% of 3.; and
- from about 5% to about 20% of 4.

5,589,183


METHOD AND APPARATUS FOR TREATMENT OF NEUROGENIC DIABETES MELLITUS, AND OTHER CONDITIONS

Peter J. Jannetta, 214 Schenley Rd., Pittsburgh, Pa. 15217
Filed Oct. 5, 1995, Ser. No. 539,341

Int. Cl.⁶ A61F 2/02

U.S. Cl. 424—423

25 Claims



1. A method for relieving pressure from a preselected region of the brainstem within the cranium of a subject, the subject having a disorder of the normal neuroendocrine servomechanism, the pressure resulting from the compression of the region by a blood vessel, the method comprising the steps of:

- a. gaining access to the preselected region using a first preselected surgical technique;
- b. exposing the preselected region according to a second preselected surgical technique;
- c. lifting the blood vessel from at least a portion of the region according to a third preselected surgical technique, thereby providing the pressure relief, the neuroendocrine servomechanism being responsive to the pressure relief on the region; and

- d. inserting a neurovascular bridge implant between the blood vessel and the preselected region, the implant maintaining the pressure relief.

5,589,184

PHARMACEUTICAL COMPOSITIONS AND METHODS OF TREATMENT OF THE CORNEA FOLLOWING LASER TREATMENT

Stella M. Robertson, Arlington, and Herman M. Kunkle, Jr., Mansfield, both of Tex., assignors to Alcon Laboratories, Inc., Fort Worth, Tex.

Continuation of Ser. No. 279,765, Jul. 25, 1994, Pat. No. 5,401,510, which is a continuation of Ser. No. 218,393, Mar. 28, 1994, abandoned, which is a division of Ser. No. 101,862, Aug. 4, 1993, Pat. No. 5,360,611, which is a continuation of Ser. No. 866,730, Apr. 10, 1992, Pat. No. 5,271,939, which is a continuation of Ser. No. 531,179, May 31, 1990, Pat. No. 5,124,392, which is a continuation-in-part of Ser. No. 253,009, Oct. 3, 1988, Pat. No. 4,939,135. This application Mar. 16, 1995, Ser. No. 405,466

Int. Cl.⁶ A61F 9/00; A61K 31/55; 31/435; 31/44

U.S. Cl. 424—427

7 Claims

1. A method for treating a corneal wound caused by laser irradiation and resulting photoablation and volumetric removal of corneal tissue, comprising: applying to an affected cornea a composition containing between about 0.1 wt. % and 4.0 wt. % of an antiallergic selected from the group consisting of cyproheptadine, azelastine, cimetidine, cromolyn, lodoxamide and pheniramine and a pharmaceutically acceptable carrier therefor.

5,589,185

PHARMACEUTICAL COMPOSITIONS AND METHODS OF TREATMENT OF THE CORNEA FOLLOWING LASER IRRADIATION

Stella M. Robertson, Arlington, and Herman M. Kunkle, Jr., Mansfield, both of Tex., assignors to Alcon Laboratories, Inc., Fort Worth, Tex.

Continuation of Ser. No. 279,765, Jul. 25, 1994, Pat. No. 5,401,510, which is a continuation of Ser. No. 218,393, Mar. 28, 1994, abandoned, which is a division of Ser. No. 101,862, Aug. 4, 1993, Pat. No. 5,360,611, which is a continuation of Ser. No. 866,730, Apr. 10, 1992, Pat. No. 5,271,939, which is a continuation of Ser. No. 531,179, May 31, 1990, Pat. No. 5,124,392, which is a continuation-in-part of Ser. No. 253,009, Oct. 3, 1988, Pat. No. 4,939,135. This application Mar. 16, 1995, Ser. No. 407,517

Int. Cl.⁶ A61F 9/00; A61K 33/04; 31/355; 31/34

U.S. Cl. 424—427

6 Claims

1. A method for treating a cornea following laser irradiation and resulting photoablation and volumetric removal of corneal tissue, comprising: applying to the affected cornea a composition containing between about 0.001 nanograms per milliliter and 1.0 milligram per milliliter of an antioxidant selected from the group consisting of ascorbic acid, glutathione, alpha tocopherol, selenous acid and sodium selenate and a pharmaceutically acceptable carrier therefor.

5,589,186

FEED COMPOSITION FOR RUMINANT ANIMALS AND METHOD OF FEEDING RUMINANT ANIMALS WITH THE SAME


Yoshio Isobe, Suginami-ku; Toshio Ito, Suita, and Fumio Shibata, Fujisawa, all of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

Continuation of Ser. No. 97,994, Jul. 29, 1993, abandoned. This application Apr. 6, 1995, Ser. No. 418,165

Claims priority, application Japan, Jan. 29, 1993, 5-034381 Int. Cl.⁶ A23K 1/18

U.S. Cl. 424—438

14 Claims



1. A feed composition for ruminant animals which comprises (a) 0.1 to 10 parts by weight of fumaric acid in a powdery or granular form having a mean particle diameter of not less than 75 mesh and

(b) 100 parts by weight of a ration comprising (i) 90 to 10% by weight of a concentrate feed containing 30 to 80% by weight of cereals based on the total weight of the concentrated feed and

(ii) 10 to 90% by weight of roughage, wherein said concentrate feed comprises at least one member selected from the group consisting of oil meals, feeds of animal origin, mineral feeds, vitamins, amino acids, and minerals, and

wherein said roughage comprises at least one member selected from the group consisting of plant stems, plant leaves, brans, and factory byproducts.

5,589,187

PROTECTIVE ENCAPSULATION OF MICRONUTRIENTS FOR INGESTION BY AVIAN SPECIES

Alice L. Wentworth, and Bernard C. Wentworth, both of Madison, Wis., assignors to Wisconsin Animal Research Foundation, Madison, Wis.

Filed Jun. 7, 1995, Ser. No. 482,736 Int. Cl.⁶ A61K 9/48

U.S. Cl. 424—439

24 Claims

1. A method of encapsulating foodstuff additives comprising: (a) coating a foodstuff additive with a first proteinaceous coating to form protein-coated grit particles; and (b) encapsulating the protein-coated grit particles within an enzymatically indigestible plastic to form plastic-encapsulated grit particles having a plastic coating capable of being mechanically degraded within gizzards of avian species, and wherein the enzymatically indigestible plastic is selected from the group consisting of thermoplastic or thermosetting polyesters, polystyrenes, polyacrylates, co-polymers thereof, and combinations thereof.

5,589,188

Patent Not Issued For This Number

5,589,189

LIPOSOME DISPERSION

Karen L. Moynihan, Brea, Calif., assignor to NeXstar Pharmaceuticals, Inc., Boulder, Colo.

Filed Sep. 14, 1994, Ser. No. 306,036 Int. Cl.⁶ A61K 9/127

U.S. Cl. 424—450

4 Claims

1. A process for producing a non-aggregating dispersion of liposomes, comprising:

- forming a dispersion of preformed liposomes containing an active therapeutic or an imaging agent;
 - adding a solution of a globular protein to the dispersion;
 - then subjecting the dispersion to a force sufficient to reduce the median size of the liposomes to less than 0.2 μ m wherein the resulting liposomes are unilamellar, provided that when the globular protein is added prior to an initial application of force the dispersion comprises an aqueous solution having an ionic strength of below 50 mM; and
 - filtering the resulting liposomes through a filter having a size less than or equal to 0.45 μ m,
- wherein the protein is selected from the group consisting of albumin, immunoglobulin, alpha, beta or gamma globulin, a lipoprotein and mixtures thereof.

5,589,190

SUSTAINED-RELEASE COMPOSITIONS OF ALFUZOSIN HYDROCHLORIDE

Véronique Andrieu, Boulogne Billancourt; Jean Montel, Chatou, and Alexander Wick, Saint Nom La Bretonne, all of France, assignors to Synthelabo, Le Plessis Robinson, France

Filed Mar. 20, 1995, Ser. No. 406,405

Claims priority, application France, Mar. 21, 1994, 94 03257 Int. Cl.⁶ A61K 31/505; 9/24; 9/32; 9/58

U.S. Cl. 424—462

14 Claims

1. Dosage composition which comprises at least one coated core that contains alfuzosin hydrochloride, which core is coated with a coating that contains a polymer that is insoluble in acid and soluble at pH 7 or above, and at least one uncoated core containing alfuzosin hydrochloride.

5,589,191

SLOW-RELEASE SODIUM VALPROATE TABLETS


Tadashi Ukigaya, and Hirohisa Endoh, both of Saltama, Japan, assignors to Nikken Chemicals Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 67,107, May 26, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 485,138

Claims priority, application Japan, May 29, 1992, 4-161785 Int. Cl.⁶ A61K 9/36

U.S. Cl. 424—480

5 Claims



1. A slow-release sodium valproate tablet comprising a core and a coating covering the surface of said core, wherein said core comprises sodium valproate and said coating comprises a mixture of ethyl cellulose and silicic acid anhydride.

5,589,192

GEL PHARMACEUTICAL FORMULATION FOR LOCAL ANESTHESIA


Hideaki Okabe; Eiichi Suzuki, both of Urawa; Masao Kogure, Saltama-ken, and Takanori Saito, Misato, all of Japan, assignors to Lintec Corporation, Tokyo, Japan

Filed Dec. 5, 1994, Ser. No. 353,322

Claims priority, application Japan, Dec. 3, 1993, 5-339439 Int. Cl.⁶ A61L 15/00

U.S. Cl. 424—486

25 Claims



1. A pharmaceutical article comprising: a supporting substrate having on a surface thereof an aqueous gel coating consisting essentially of a local anesthetic and a gelled crosslinked copolymer of alkyl (meth)acrylate and (meth)acrylic acid, which impregnates the substrate, which article is produced by forming a polymer/drug matrix of the local anesthetic and an uncrosslinked copolymer corresponding to the crosslinked copolymer, applying a coating of the polymer/drug matrix and crosslinking agent for the copolymer to a surface of the substrate to impregnate the substrate therewith, crosslinking the copolymer in the coating to form the crosslinked copolymer, and contacting the surface of the coating with an aqueous fluid, thereby converting the coating into a gel.

5,589,193

Patent Not Issued For This Number

5,589,194

METHOD OF ENCAPSULATION AND MICROCAPSULES PRODUCED THEREBY


Alexander C. Tsuel, Woodbury; Lorenz Kogl, III, Stillwater, and Daniel B. Pendergrass, Jr., Mendota Heights, all of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Sep. 20, 1993, Ser. No. 123,806

Int. Cl.⁶ A61K 9/50; A23L 1/236; A23P 1/04; B01J 13/04

U.S. Cl. 424—497

17 Claims



permitting the aqueous phase in said layer to evaporate, thereby forming a smooth, durable, dry film on said surface, wherein the formation of said film is attributable to said proteinaceous particulate material.

5,589,196

ANTIPERSPIRANT COMPOSITION

David T. Callaghan, Quincy; Alan M. Phipps, Framingham, both of Mass., and Stephen J. Provencal, Addison, Ill., assignors to The Gillette Company, Boston, Mass.

Continuation of Ser. No. 846,016, Mar. 4, 1992, abandoned, which is a division of Ser. No. 287,096, Dec. 20, 1988, Pat. No. 5,114,705, which is a continuation of Ser. No. 713,470, Mar. 19, 1985, abandoned, which is a continuation-in-part of Ser. No. 523,785, Aug. 16, 1983, abandoned. This application Jun. 1, 1994, Ser. No. 252,376

Int. Cl.⁶ A61K 33/24;7/32; C01G 25/00; C01F 7/00

U.S. Cl. 424—617

32 Claims

1. An intermediate for making an antiperspirant composition having high efficacy, said intermediate comprising an aqueous solution of aluminum chlorohydrate and zirconyl hydroxy chloride, the atomic ratio of Al to Zr being from 6:1 to 1:1, said solution, when stored at room temperature for no more than two hours and subjected to gel permeation chromatography at a concentration of 10% on cross-linked dextran having a molecular weight exclusion range of 1000 to 30,000 for globular proteins, showing a first peak at $K_d=0.7$ and a second peak at $K_d=0.5$, the ratio of the height of said first peak to that of said second peak being at least 1.5:1.

5,589,197

LOW SODIUM PERITONEAL DIALYSIS SOLUTION


Ty R. Shockley, Highland Park; Leo Martis, Long Grove; Lee W. Henderson, Lake Forest; John Moran, Evanston, all of Ill., and Masaaki Nakayama, Tokyo, Japan, assignors to Baxter International, Inc., Deerfield, Ill.

Continuation-in-part of Ser. No. 130,968, Oct. 4, 1993, abandoned. This application Mar. 3, 1994, Ser. No. 205,304

Int. Cl.⁶ A61K 31/70;31/715;33/00;33/14

U.S. Cl. 424—663

9 Claims



1. A peritoneal dialysis solution for providing a sustained osmotic gradient comprising:

- a polyglucose osmotic agent; and
- sodium in a concentration that is less than a sodium plasma concentration in a renal patient who is to receive the solution.

5,589,198
TREATMENT OF IODINE DEFICIENCY DISEASES
Bernard A. Eskin, 625 Harvard Rd., Bala Cynwyd, Pa. 19004, and R. Allison Ghent, Kingston, Canada, assignors to 943038 Ontario, Inc., Ontario, Canada, and Bernard A. Eskin, Philadelphia, Pa.

Continuation-in-part of Ser. No. 131,427, Oct. 4, 1993, Pat. No. 5,389,385, which is a division of Ser. No. 803,550, Dec. 9, 1991, Pat. No. 5,250,304, which is a division of Ser. No. 292,968, Jan. 3, 1989, Pat. No. 5,171,582, which is a

continuation-in-part of Ser. No. 889,947, Jul. 28, 1986, Pat. No. 4,816,255, which is a continuation-in-part of Ser. No. 760,950, Jul. 31, 1985, abandoned. This application Feb. 13, 1995, Ser. No. 388,026

Int. Cl.⁶ A01N 59/22; A61K 33/36

U.S. Cl. 424—667

11 Claims

1. A method for therapeutically treating or preventing an iodine deficiency disease or disorder selected from the group consisting of fibrocystic dysplasia, breast cancer, endometriosis, ovarian cysts and premenstrual syndrome, comprising administering to a mammal in need thereof a sufficient amount of elemental iodine.

5,589,199

APPARATUS FOR MAKING ENVIRONMENTALLY STABLE REACTIVE ALLOY POWDERS


Iver E. Anderson; Barbara K. Lograsso, and Robert L. Terpstra, all of Ames, Iowa, assignors to Iowa State University Research Foundation, Inc., Ames, Iowa

Division of Ser. No. 926,151, Aug. 5, 1994, Pat. No. 5,372,629, which is a continuation of Ser. No. 594,088, Oct. 9, 1990, abandoned. This application Oct. 24, 1994, Ser. No. 328,115

Int. Cl.⁶ B22F 9/08

U.S. Cl. 425—10

5 Claims



1. Apparatus for making powder from a melt having a composition including a reactive alloying element in selected concentration to provide desired end-use properties, comprising:

- a) means for atomizing a melt having a composition including a reactive alloying element into molten droplets for free fall downwardly in a manner as to cool as they fall;
- b) means for discharging a reactive gas downstream relative to the atomizing means for establishing a zone of said reactive gas downstream of the atomizing means at a selected location where the droplet temperature is so reduced by said cooling that said droplets have at least a solidified exterior and that the reactive gas reacts with said reactive alloying element as the droplets pass through the zone to form a reaction product layer thereon whose penetration into the droplets is limited in surface depth by the presence of said solidified surface so as to avoid selective removal of the reactive alloying element from said melt composition to a harmful level that substantially degrades the end-use properties of powder comprising said droplets; and
- c) means for collecting the solidified droplets.

5,589,200

SPLIT MOLD APPARATUS FOR A TIRE VULCANIZER
Nobuhiko Irie, Nagasaki, Japan, assignor to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo, Japan


Filed May 19, 1995, Ser. No. 446,571

Claims priority, application Japan, Jun. 3, 1994, 6-122661; Apr. 10, 1995, 7-084109

Int. Cl.⁶ B29D 30/06; B29C 33/24

U.S. Cl. 425—46

1 Claim



1. A split mold apparatus for a tire vulcanizer, having an upper disk to which an upper sidewall mold portion for molding one side of a tire is assembled, a lower disk to which a lower sidewall mold portion for molding the other side of the tire is assembled, a split segment to which a tread mold portion divided into plural pieces in the circumferential direction for molding a tire tread portion is assembled, and an outer ring having an inside inclined surface corresponding to an outside inclined surface of said segment and fitted so as to be capable of relative sliding concentrically with said segment with both said inclined surfaces being used as a sliding surface, wherein claws fitted to said upper and lower disks to prevent the separation of said upper and lower disks when the split mold apparatus is closed are provided at upper and lower parts of said segment, a cover plate whose outer periphery is fixed to said outer ring is provided above said upper disk, and a locking means for locking said upper disk and said cover plate when the split mold apparatus is closed is provided between said cover plate and said upper disk wherein:

said cover plate is elastically deformed to the side of said upper disk, and said locking means is operable so as to establish a locking condition wherein most of the elastic deformation is left when an inside claw of an outer locking means ring rotatably mounted to an inner peripheral portion of said cover plate is engaged with an outside claw of an inner locking means ring fixed to an inner peripheral portion of said upper disk.

5,589,201

APPARATUS FOR GAUGE DISTRIBUTION IN A TUBULAR PLASTIC FILM

Peter V. Tkach, and Frank G. Opit, both of Mississauga, Canada, assignors to Macro Engineering & Technology Inc., Mississauga, Canada

Filed May 5, 1995, Ser. No. 437,075


Int. Cl.⁶ B29C 53/20

U.S. Cl. 425—66

12 Claims

1. Apparatus for effecting gauge distribution in flattened tubular plastic film, said apparatus comprising: collapsing means for collapsing upwardly vertically moving expanded tubular plastic film to a two layer flattened condition, said collapsing means being located above the upwardly moving expanded tubular plastic film and aligned with the longitudinal central axis thereof, said collapsing means being rotatable about said central axis;

- a first motor for rotating the collapsing means about said central axis through 180° in each direction from a neutral position;
- a first horizontal film direction reverser secured to the collapsing means for rotation therewith and laterally spaced from said



central axis for reversing the direction of travel of said flattened film leaving the collapsing means from a radially outward direction away from said central axis to a radially inward direction toward said central axis.

a first horizontal turning bar located above the collapsing means and extending substantially through said central axis for receiving said flattened film from the first direction reverser, said flattened film passing around the first turning bar and leaving said first turning bar in a radially outward direction;

a first turning bar carrier carrying the first turning bar and rotatable about said central axis to rotate the first turning bar horizontally; and

a second horizontal film direction reverser laterally spaced from said central axis for reversing the direction of travel of the flattened film leaving the first turning bar from a radially outward direction to a radially inward direction towards the central axis;

a direction reverser carrier rotatable about said central axis and carrying the second film direction reverser for rotation therewith;

a second horizontal turning bar located about the first turning bar and extending substantially through said central axis for receiving said flattened film from the second film direction reverser, said flattened film passing around the second turning bar and leaving said second turning bar in a radially outward direction;

a second turning bar carrier carrying a second turning bar and rotatable about said central axis to rotate the second turning bar horizontally;

second motor means for simultaneously rotating the first turning bar carrier to rotate the first turning bar about said central axis through 135° in each direction from a neutral position, rotating the second film direction reverser about said central axis through 90° in each direction from the neutral position and rotating the second turning bar carrier to rotate the second turning bar about said central axis through 45° in each direction from the neutral position simultaneously with said rotation of the collapsing means and first direction reverser by said first motor, and thereby distribute gauge variations in the two layer flattened film leaving the collapsing means across the width of the flattened film.

5,589,202

APPARATUS FOR MOLDING POLYURETHANE FOAM
Hidenobu Okano, and Katsunori Watanabe, both of Inazawa, Japan, assignors to Toyota Gosei Co., Ltd., Japan

Division of Ser. No. 59,739, May 12, 1993, abandoned, which is a continuation of Ser. No. 712,716, Jun. 10, 1991, abandoned. This application Jun. 29, 1994, Ser. No. 267,398

Claims priority, application Japan, Jun. 12, 1990, 2-153439; Apr. 12, 1991, 3-108745


Int. Cl.⁶ B28B 1/50

U.S. Cl. 425—73

6 Claims

1. An apparatus for molding a polyurethane foam which covers a ring of a steering wheel, comprising:

- a mold made up of at least two mold parts which are opened and closed;



said mold defining a ring-shaped cavity when said mold parts are closed;
means defining a gate connected to said cavity;
a mechanism for injecting a polyurethane material into said cavity through said gate, polyurethane materials injected through said gate flowing in two directions through the ring-shaped cavity towards a final fill position in the mold;
means defining a vent hole at the final fill position in the mold where said polyurethane materials flowing in said two directions meet;
mating mold surfaces of said mold parts defining an air vent around substantially an entire periphery of said cavity when said mold parts are closed, whereby air is vented through said air vent as said polyurethane material flows through the ring-shaped cavity towards the final fill position;
a vacuum box surrounding said mold;
a space defined between said mold and said vacuum box, having a volume greater than said cavity, and in communication with said cavity both via said vent hole and via said air vent when said split molds are closed; and
a depressurizing means operatively connected to said space.

5,589,203


VACUUM KNEADING AND EXTRUDING APPARATUS
Takuya Sato, Suita, Japan, assignor to Sato Iron Works Co., Ltd., Osaka, Japan

Continuation of Ser. No. 189,476, Jan. 31, 1994, abandoned.
This application Jul. 13, 1995, Ser. No. 502,101

Claims priority, application Japan, Nov. 10, 1993, 5-280777
Int. Cl.⁶ B29C 47/92; 47/38

U.S. Cl. 425-147

10 Claims



1. A vacuum kneading and extruding apparatus comprising measuring devices for separately and continuously measuring and outputting plural types of material.
means for continuously transporting said material downstream from the measuring devices,
a kneading and degassing tank comprising a receiving hopper which receives material from said transport means, a kneading screw in said receiving hopper, and a vacuum chamber downstream of said receiving hopper, said kneading screw being rotatable about a vertical axis,
a first kneading mechanism disposed between said kneading screw and said vacuum chamber, said first kneading mechanism comprising a rotatable disk fixed to said kneading screw and a fixed disk fixed to said receiving hopper;

means for controlling the level of material in said receiving hopper so that the level of material in said receiving hopper constantly lies in a predetermined range,
a transport tube having therein a transport screw for transporting said material downstream from said vacuum chamber; and
forming means downstream of said transport tube for forming and extruding the material.


5,589,204

BOTTLE MOLD WITH ADJUSTABLE NECK BLOCK
Emanuel E. Wohlgenuth, 1381 Pea Pond Rd., North Bellmore, N.Y. 11710

Filed May 16, 1995, Ser. No. 491,552
Int. Cl.⁶ B29C 49/76

U.S. Cl. 425-182

8 Claims



1. A neck-finish top block for use in a container blow mold system and comprising:
a base having a parting face and a heel mounting surface perpendicular thereto,
a heel engaging said heel mounting surface and adapted for longitudinal translation relative to said base and normal to said parting face and including a tail surface transverse to and parallel to said parting face and separated therefrom by a certain longitudinal distance,
a cam engaging one of said base or said heel and rotatable about an axis fixed thereto, and having a displacement surface engaging the other of said base or said heel at a contact point, and adapted such that rotation of said cam causes longitudinal displacement of said contact point, and
wherein said contact point displacement facilitates longitudinal translation of said heel and thereby facilitates variation of said certain longitudinal distance.

5,589,205

APPARATUS FOR MANUFACTURING HOLLOW RESIN PRODUCTS

Hajime Ishikawa, Toyonaka; Masaaki Ogawa, Kobe; Ryosuke Hasegawa, Kobe, and Hideo Yamamoto, Kobe, all of Japan, assignors to Tigers Polymer Corporation, Toyonaka, Japan
Filed Oct. 25, 1994, Ser. No. 329,648


Claims priority, application Japan, Oct. 26, 1993, 5-266811;
Sep. 29, 1994, 6-234958

Int. Cl.⁶ B29C 49/64

9 Claims

U.S. Cl. 425-526

1. An apparatus for manufacturing hollow resin products, the apparatus comprising:
an extruder for extruding a tubular resin material and cutting the material into a parison with a specified length;
a blow molding machine having an upper mold and a lower mold which form a cavity of a specified shape inside; and
a parison delivering machine for receiving the parison from the extruder and feeding the parison into the cavity of the lower mold, the parison delivering machine comprising a conveyor which has a parison feeder for feeding a parison longitudinally from an inlet to an outlet, driver for driving the feeder



and at least four shafts which serve as pivots of three-dimensional movement of the conveyor wherein the parison delivering machine comprises six shafts, in which:

a first shaft is positioned vertically to a floor and serves as a pivot of a movement of the conveyor in parallel to the floor;
a second shaft is positioned on the first shaft and serves as a pivot of a forward/backward movement of the conveyor;
a third shaft is positioned on the second shaft and serves as a pivot of an upward/downward movement of the conveyor;
a fourth shaft is positioned on the third shaft and serves as a pivot of a swing of the conveyor in a plane perpendicular to a parison feeding direction;
a fifth shaft is positioned on the fourth shaft and serves as a pivot of a swing of the conveyor in a plane including the parison feeding direction; and
a sixth shaft is positioned on the fifth shaft and serves as a pivot of a rotation in substantially a horizontal plane on a central portion of the conveyor in the longitudinal dimension.

5,589,206


COMPACT DISC INJECTION MOLDING APPARATUS
Douglas C. Hepler, Rochester, N.Y., assignor to Polysht Corporation, Henrietta, N.Y.

Filed Jul. 22, 1994, Ser. No. 278,935

Int. Cl.⁶ B29C 45/20

U.S. Cl. 425-549

11 Claims



1. An injection molding system for fabricating thin, flat compact discs, said injection molding system comprising:

a pair of molding plates relatively moveable with respect to one another, one of said pair of molding plates being stationary and one moveable with respect to said stationary one;
a pair of molding blocks carried on said pair of said molding plates, at least one of said pair of said molding blocks being adapted to form a molding cavity for the compact discs, said pair of said molding plates and said pair of said molding blocks adapted to be moved between a closed position in which said molding cavity is closed for forming the compact discs and an open position in which the compact discs may be removed from said molding cavity, one of said molding

blocks being carried on said moveable molding plate and one being fixedly mounted to said stationary molding plate;
a heatable sprue bushing for use in transporting plasticized material from an injection nozzle to the edge of the mold cavity while controlling the temperature of the plasticized material, said heatable sprue bushing comprising:

an elongated body of given length having arranged in order along its length a head, a stem, and a distal end, said head having a reference seating surface which faces said distal end and a rear surface facing opposite said distal end, said elongated body having a through bore passing from end to end through said head, stem, and distal end thereof for transporting plasticized material through at least a portion of said elongated body from said head toward said distal end thereof, said elongated body having at least one non-through bore extending alongside said through bore, in heat conducting relationship with respect thereto, and adapted to receive an electrically powered heating cartridge for controlling the temperature of plasticized material as it travels along said through bore, said nonthrough bore having a length which extends from said head rear surface, through said head and said stem and into said distal end by a predetermined distance, said length of said nonthrough bore being shorter than said given length of said elongated body, said through bore being counter bored a given depth near said distal end of said elongated body, said body being fabricated of a material with a predetermined heat capacity and coefficient of thermal conductivity to provide it with a predetermined mass and heat transfer capability, a predetermined length of said elongated body extending through said stationary molding plate and said block fixedly attached thereto; and

a tip fitted into said counterbore of said elongated body so that part of said tip is in heat conducting relationship with respect to said elongated body while its remaining parts are thermally isolated therefrom, said tip being releasably mateable with said elongated body, having a single flow bore which is adapted to communicate with said through bore of said elongated body to receive plasticized material from it, and a curved forward end, said tip including a single flow channel of predetermined length that communicates with the gate of the cavity mold, said tip being fabricated of a material that has a thermal mass less than that of said body material and a coefficient of thermal conductivity substantially higher than that of said elongated body material so that said elongated body acts as a constant temperature source with respect to said tip so as to transfer heat to said tip at said portion thereof in thermal contact therewith to heat said tip, said predetermined length of said flow channel of said tip, said curved forward end of said tip, and said molding blocks being configured and arranged with respect to one another so that the temperature of said curved forward end of said tip gradually reduces to a level at which plasticized material just freezes at the gate to mold cavity at the end of a molding cycle before the beginning of a subsequent molding cycle.

5,589,207

METHOD OF PRODUCING A FROZEN YEAST DOUGH PRODUCT

Peter Larsen, deceased, late of Nice, France, and Henrik S. Pedersen, executor, Birkerød, Denmark, assignors to Kval Marketing Inc., Petaluma, Calif.

Continuation of Ser. No. 268,069, Jun. 28, 1994, abandoned, which is a continuation of Ser. No. 777,525, Sep. 15, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 479,813

Claims priority, application Denmark, Jul. 14, 1989, 3489/89
Int. Cl.⁶ A21D 8/04


U.S. Cl. 426-20

28 Claims

1. A method of producing a frozen, leavened laminated dough which is suitable for immediate baking when taken from the freezer comprising the steps of forming a dough essentially free of

fermentable mono and disaccharides by mixing baking dough forming ingredients, other than fermentable mono and disaccharides, including flour, fat, water, yeast and amylase, said amylase including an amylase component which remains active at temperatures above 60 degrees Centigrade, to form a baking dough to which fermentable mono and disaccharides have not been added, folding and rolling said dough to effect lamination thereof, leavening said dough and freezing the leavened dough, said amylase being added in an amount to generate sufficient fermentable saccharides under leavening conditions for yeast leavening of the dough and said component thereof which remains active above 60 degrees Centigrade being added in an amount sufficient to increase browning of the dough during baking thereof.


5,589,208
METHODS FOR COATING EGG YOLKS AND OTHER ARTICLES
Eustathios Vassiliou, 12 S. Townview La., Newark, Del. 19711
Filed Mar. 14, 1995, Ser. No. 403,424
Int. Cl.⁶ A23L 1/32; B01D 43/00
U.S. Cl. 426—89 16 Claims



1. A method of encapsulating a yolk disk with a restrictive barrier comprising the steps of:
 - (a) contacting the yolk with an excess of a first liquid containing a first reactant for the yolk to be wetted with said first reactant, the first reactant comprising a cross-linker;
 - (b) separating the yolk from the excess of the first liquid;
 - (c) subsequently treating the wetted yolk with an excess of a second liquid containing a second reactant, which second reactant reacts with the first reactant to form the restrictive barrier, the second liquid comprising a cross-linkable polymer; and
 - (d) separating the treated yolk from the second liquid; with the requirement that the separating steps (b) and (d) are performed in the absence of mechanically moving parts.


5,589,209
METHOD FOR A NON-DESTRUCTIVE DETERMINATION OF QUALITY PARAMETERS IN FRESH PRODUCE
Amos Mizrach, Rishon-Le-Zion; Naftali Galili, Afula, and Giora Rosenhouse, Haifa, all of Israel, assignors to State of Israel, Ministry of Agriculture, Bat Dagan, Israel
Filed Apr. 24, 1995, Ser. No. 427,219
Claims priority, application Israel, Apr. 24, 1994, 109406
Int. Cl.⁶ G05B 1/00 17 Claims

1. A method of determining quality parameter of fresh produce using ultrasonic sound waves, which comprises:
 - arranging a sample of fresh produce of an unknown maturity stage in an ultrasonic sound path;
 - transmitting ultrasonic sound waves along the sound path through the sample of the fresh produce;
 - detecting and receiving said sound waves after said sound waves pass through the fresh produce sample; and
 - calculating values of acoustical parameters, including at least wave velocity and signal attenuation of the detected sound



waves, to analyze said values which are indicative of quality of the fresh produce sample.

5,589,210
METHOD FOR COOKING WHEAT FLOUR PRODUCTS BY USING INFRARED RADIATION
Jose De La Luz Martinez, Puebla; Jesus Gonzalez-Hernandez, Tesoro; Feliciano Sanchez-Sinencio, Tecamachalco; Maximiano Ruiz-Torres, Morelia; Juan De Dios Figueroa C., Tamaulipas, and Fernando Martinez-Bustos, Veracruz, all of Mexico, assignors to Centro de Investigacion Y de Estudios Avanzados del I.P.N., Mexico City, Mexico
Filed Aug. 23, 1995, Ser. No. 519,060
Int. Cl.⁶ A23L 1/00 10 Claims



1. A method of cooking wheat flour tortillas comprising:
 - a) preparing a wheat flour based dough;
 - b) cutting and shaping the dough into circular flat pieces of predetermined diameter and thickness to form uncooked wheat flour tortillas;
 - c) generating infrared radiation waves to be irradiated within a cooking space for the wheat flour tortillas;
 - d) selecting an optimal wavelength band of said infrared radiation waves in which the absorption factor is independent from temperature and which will produce a maximum absorption of infrared radiation by the wheat flour tortillas to quickly evaporate water from the outermost surfaces thereof in order to form capping layers which will retain moisture within the inner portion of the tortillas; and
 - e) passing the uncooked wheat flour tortillas through said cooking space at a predetermined speed in order to produce the desired degree of cooking of the tortillas.

5,589,211
METHODS FOR PROCESSING POULTRY SHELL EGGS
James P. Cox; R. W. Duffy Cox, and Jeanne M. Cox, all of 246 E. Bartlett Rd., Lynden, Wash. 98264


Continuation-in-part of Ser. No. 746,940, Aug. 19, 1991, which is a continuation-in-part of Ser. No. 674,495, Mar. 25, 1991, Pat. No. 5,283,072, which is a continuation of Ser. No. 349,974, May 8, 1989, abandoned, which is a continuation of Ser. No. 196,878, May 19, 1988, abandoned, which is a continuation of Ser. No. 70,597, Jul. 8, 1987, abandoned, which is a continuation of Ser. No. 758,086, Jul. 23, 1985, abandoned.

This application Nov. 22, 1993, Ser. No. 156,273
The portion of the term of this patent subsequent to Aug. 19, 2011, has been disclaimed.

Int. Cl.⁶ A23B 5/005

U.S. Cl. 426—298

3 Claims



1. A method of making a poultry shell egg safer to eat, said method comprising the steps of:
 - promoting the transfer of heat to the egg by first heating said egg at a temperature above that at which the white of the egg will coagulate but not higher than about 170° F. but for a sufficiently short period of time to preclude significant coagulation of said white; and then
 - heating said egg at a second, lower, pasteurization temperature in the range of 130° F. to <140° F. and below the coagulation temperature of the egg white for a time sufficient to destroy infectious microorganisms throughout the mass of the egg.

5,589,212

Patent Not Issued For This Number

5,589,213
DUAL-STAGE PROCESS FOR MANUFACTURING POTATO CHIPS
Pravin M. Desai, Carrollton; Michael L. Pfeiffer; Mary M. Pohlmeier, both of Dallas, and Jennifer B. Raymond, Plano, all of Tex., assignors to Recot, Inc., Pleasanton, Calif.
Filed Apr. 7, 1995, Ser. No. 418,306
Int. Cl.⁶ A23L 1/217 30 Claims


U.S. Cl. 426—438

1. A dual-stage process for preparing potato chips consisting essentially of the steps of:
 - a first stage continuous process for preparing potato slices at a first location for indefinite storage comprising the steps of: slicing peeled potatoes to a thickness in the range of about 1.3 mm to about 2.8 mm;
 - washing said potato slices to remove surface starch thereon;
 - frying said washed potato slices for a time period sufficient to reduce the moisture content of the potato slices to about 3% to 30%; freezing said potato slices; and

storing said frozen potato slices at a temperature of -18° C. (0° F.) for an extended period of time; and
a second stage continuous process for preparing potato chips for consumer use comprising the steps of:
shipping said frozen potato slices to a plurality of second locations;
frying said frozen potato slices at each one of the plurality of second locations for a time period sufficient to form potato chips; and
bagging said potato chips for consumer use.

5,589,214
PROCESS FOR HEAT TREATMENT OF PARTICULATE MATERIALS SUCH AS FOOD
Bengt Palm, Genarp, Sweden, assignor to Alfa-Laval Food Engineering AB, Stockholm, Sweden
Division of Ser. No. 720,834, Jul. 12, 1991, Pat. No. 5,284,085.
This application Nov. 8, 1993, Ser. No. 148,352
Claims priority, application Sweden, Jan. 27, 1989, 8900297; WIPO, Jan. 25, 1990, PCT/SE90/08482
Int. Cl.⁶ A23L 3/16 3 Claims

U.S. Cl. 426—506



1. A process for the treatment of particulate materials in a treatment vessel having an inlet for material to be treated and an outlet for treated material, to evacuate and pressurize the vessel, said vessel further having a horizontal treatment chamber and a hollow oscillating agitation device having a plurality of perforations, said process comprising directing material to be treated into the vessel such that said particulate material fills only a lower part of said vessel in the form of a layer, stirring said material by oscillating said agitation device, subjecting said vessel to vacuum, heating said material by injecting steam into said material while stirring said material, flash cooling said material by spraying the outside of said vessel with a cooling liquid, pressurizing said vessel with gaseous nitrogen, and removing the treated material from the vessel wherein said steam is injected into said material through the perforations of said agitation device and said oscillating movement is effected in such manner that the agitating device is moved through said particulate material to a turning point just below the surface of said layer and then changes direction and moves through said layer past a vertical position to a second turning point just under the surface of the layer on an opposing side of said vessel in such manner as to impart even heat treatment to all of said particulate material.

5,589,215
METHOD OF MAKING AND USING A FAT MIMETIC IN REDUCED FAT/CHOLESTEROL FOODSTUFFS
Pamela S. Tang, Palatine, Ill., assignor to Griffith Laboratories Worldwide, Inc., Alsip, Ill.
Filed Sep. 29, 1993, Ser. No. 128,602
Int. Cl.⁶ A21D 2/00; A23L 1/0522 23 Claims

U.S. Cl. 426—549

1. A fat-free composition for use as a mimetic said composition consisting essentially of:
 - about 10–85 percent by weight starch;
 - about 2–25 percent by weight cellulose;
 - about 4–70 percent by weight protein;

about 0-4 percent by weight gum; and
about 0-8.2 percent by weight flavoring.

5,589,216

REDUCED CALORIE CONFECTIONERY COMPOSITIONS WHICH CONTAIN REDUCED CALORIE FATS WHICH EXHIBIT RAPID TRANSFORMATION TO BETA PHASE

Gerald J. Guskey, Montgomery; James A. Hellyer, Milford; Bernard W. Kluesener, Harrison, and Gordon K. Stipp, Cincinnati, all of Ohio, assignors to The Procter and Gamble Company, Cincinnati, Ohio

Filed Nov. 8, 1994, Ser. No. 336,157

Int. Cl.⁶ A23G 1/00

U.S. Cl. 426-607

18 Claims

1. A process for preparing a bloom-stable, flavored confectionery composition which contains reduced calorie fat in the stable beta phase, which process comprises:

(I) forming a temperable, flavored confectionery composition which comprises:

A) a flavor enhancing amount of a flavor component;

B) from about 15% to about 45% of a fat component comprising:

(i) at least about 70% by weight of the fat component of a reduced calorie cocoa butter substitute fat having:

(a) at least about 40% by weight of the reduced calorie fat MLM triglycerides;

(b) at least about 85% by weight of the reduced calorie fat combined MLM and MML triglycerides;

(c) no more than about 5% by weight of the reduced calorie fat combined LLM and LML triglycerides;

(d) no more than about 4% by weight of the reduced calorie fat of MMM triglycerides;

(e) no more than about 2% by weight LLL triglycerides; and

(f) no more than about 6% by weight of other triglycerides;

wherein said triglycerides M is a C₆ to C₁₀ saturated fatty acid residue and L is a C₁₇ to C₂₆ saturated fatty acid residue; and wherein said triglycerides are further characterized by having a fatty acid composition which comprises

(x) from about 35% to about 60% combined C₈ and C₁₀ saturated fatty acids;

(y) a ratio of C₈ to C₁₀ saturated fatty acids of from about 1:5 to about 25:1;

(z) from about 35% to about 60% behenic fatty acid;

(ii) up to about 20% by weight of the fat component of milkfat;

(iii) up to about 20% by weight of the fat component of cocoa butter; and

(iv) no more than about 4% by weight of the fat component of diglycerides; and

C) from about 55% to about 85% other nonfat confectionery ingredients;

(II) dynamically tempering the flavored confectionery composition of Step (I) by cooling said composition from a non-crystalline state to a temperature of less than about 21.1° C. at a rate of from about 0.4° C./min. to about 83° C./min. while simultaneously working said composition to impart shear agitation thereto to the extent of shear rates ranging from about 400 to about 8000 sec⁻¹, and by thereafter conditioning said composition for at least about 2 minutes by agitating and warming said composition to a temperature of from about 21.1° C. to about 29.4° C.; and thereafter


(III) setting the tempered composition by cooling and/or warming the tempered composition from Step (II) in a manner such that the reduced calorie fat transforms into a stable beta crystalline phase.

5,589,217
REDUCED CALORIE FAT COMPONENT
Harry Mazurek, Bala Cynwyd, Pa., assignor to ARCO Chemical Technology, L.P., Greenville, Del.
Filed May 11, 1995, Ser. No. 439,167
Int. Cl.⁶ A23D 9/02

U.S. Cl. 426-611

10 Claims

1. A reduced calorie fat component comprised of
(a) a digestion resistant esterified propoxylated glycerin having a dilatometric solid fat index of at least 50° at 21° C. and at least 10° at 37° C. and structure



wherein x, y, and z are each at least 1, the sum of x+y+z is from 3 to 21, and X, Y, and Z are the same or different and are selected from the group consisting of H and



wherein R is a C₄-C₂₃ aliphatic group and at least two of X, Y, or Z are




and
(b) a triacylglycerol bearing both at least one C₂-C₄ carboxylic acid residue and at least one C₁₆-C₂₄ saturated fatty acid residue and having a dilatometric solid fat index of less than 50° at 21° C. and less than 10° at 37° C.; wherein the triacylglycerol is present in the reduced calorie fat component in an amount effective to provide a dilatometric solid fat index of less 50° at 21° C. and less than 10° at 37° C.

5,589,218
METHOD FOR MAKING ARTIFICIAL EGG YOLKS IN THE FORM OF A CYLINDER
Eustathios Vassiliou, 12 S. Townview La., Newark, Del. 19711
Filed Mar. 14, 1995, Ser. No. 403,653
Int. Cl.⁶ A23L 1/32

U.S. Cl. 426-614

6 Claims



1. A method of making artificial egg-yolk comprising the steps of:

(a) mixing artificial egg-yolk materials including a positive thermoreversible gel former to form a first mixture, the positive thermoreversible gel former providing a gel temperature to the artificial egg-yolk;

(b) heating the first mixture to a first temperature in the range of 150°-190° F.;

(c) mixing a quantity of the first mixture, while said first mixture is still at a temperature in the range of 150°-190° F., with a quantity of a liquid having a second temperature, in the range of 32°-60° F., and comprising egg-white to form a second mixture having a third temperature in the range of 100°-130° F. the quantities of the first mixture and the liquid, and the first and second temperatures being such that the third tem-

perature is higher than the gel temperature but lower than a temperature at which the egg-white coagulates;
(d) cooling the second mixture below the gel temperature to form a gel; and
(e) extruding the second mixture through a die to form a gelled artificial yolk having a shape of a cylinder.

5,589,219

HEAT-RESISTANT, HIGH-VOLTAGE LEAD WIRE FOR DIRECT CURRENT


Hiroshi Hayami, Osaka, Japan, assignor to Sumitomo Electric Industries, Ltd., Osaka, Japan

Division of Ser. No. 281,531, Jul. 28, 1994, Pat. No. 5,470,657, which is a continuation of Ser. No. 930,597, Oct. 2, 1992, abandoned. This application May 3, 1995, Ser. No. 433,061

Claims priority, application Japan, Apr. 26, 1991, 3-125376
Int. Cl.⁶ B05D 5/12; B02J 7/04


U.S. Cl. 427-117

4 Claims



1. A method for producing heat-resistant, high-voltage lead wires for direct current comprising:

forming an insulating layer over a high-voltage lead wire for direct current, wherein said insulating layer comprises a polyolefin based resin composition, said polyolefin resin composition being a resin composition made by adding more than 1 part by weight and less than 10 parts by weight of an organic silane compound during the mixing of more than 100 parts by weight and less than 200 parts by weight of a metal hydroxide and more than 5 parts by weight and less than 50 parts by weight of a halogen containing flame retardant to 100 parts by weight of a polyolefin resin, said organic silane compound having the formula:



where, R stands for an alkyl group containing an acryl or methacryl group, and X¹, X² and X³ represent a member selected from the group consisting of alkoxy, alkyl and halogen.

and irradiating said insulating layer with ionizing radiation.

5,589,220

METHOD OF DEPOSITING CHROMIUM AND SILICON ON A METAL TO FORM A DIFFUSION COATING

Robert A. Rapp; Ge Wang, both of Columbus, Ohio, and Endang Pangestuti, Palembang, Indonesia, assignors to The Ohio State University Research Foundation, Columbus, Ohio


Continuation of Ser. No. 240,350, May 10, 1994, Pat. No. 5,492,727. This application Oct. 30, 1995, Ser. No. 550,108

Int. Cl.⁶ B05D 5/12
U.S. Cl. 427-126.1

9 Claims

1. A method for forming a diffusion coating by depositing chromium and silicon on an iron-based substrate comprising the steps of:

(a) placing a cementation pack in surrounding relationship to a surface of the substrate, the cementation pack including a



mixture of essentially pure chromium powder and essentially pure silicon powder, at least one halide salt activator, and an alumina filler;

(b) heating the substrate and cementation pack in an inert or reducing atmosphere to a first temperature sufficient to cause vaporization of the halide salt and for a time sufficient to cause the preferential deposition of essentially silicon on the surface of the substrate; and then

(c) heating the substrate and cementation pack to a second, higher temperature for a time sufficient to cause the deposition of predominantly chromium on the surface of the substrate.

5,589,221

MAGNETIC THIN FILM, AND METHOD OF MANUFACTURING THE SAME, AND MAGNETIC HEAD

Masayoshi Hiramoto, Ikoma; Osamu Inoue; Koichi Kugimiya, both of Osaka, and Kenji Iijima, Kyoto, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed May 11, 1995, Ser. No. 439,574

Claims priority, application Japan, May 30, 1994, 6-116454; May 16, 1994, 6-100939; Dec. 7, 1994, 6-303614

Int. Cl.⁶ G11B 5/85

U.S. Cl. 427-130

7 Claims



1. A method of manufacturing a magnetic thin film, comprising the steps of:

forming at least one layer of a main magnetic precursor layer containing at least one element having lower oxide or nitride formation free energy than Fe and at least one element selected from the group consisting of Fe, Co, and Ni on at least one layer of an intermediate precursor layer on the surface of a substrate;

conducting a heat treatment thereto at a temperature of from 400° to 700° C.; and

laminating a main magnetic layer comprising magnetic crystal grains substantially having a columnar structure which have an average height dl and an average diameter ds forming a shape ratio of 0.3 ≤ ds/dl ≤ 0.9 on an intermediate layer having saturation magnetic flux density of at least 0.1 tesla less than said main magnetic layer.

5,589,222

HYDROPHOBIC FREE-FLOWING PELLETS, A PROCESS FOR THEIR PRODUCTION AND THEIR USE

Peter Thometzek, Krefeld, Germany, and Heinrich Christ, Spilamberto, Italy, assignors to Ferro (Italia) S.r.l., Bologna, Italy

Continuation of Ser. No. 510,331, Aug. 2, 1995, abandoned, which is a continuation of Ser. No. 72,105, Jun. 7, 1993, abandoned. This application Feb. 1, 1996, Ser. No. 595,514
Claims priority, application Italy, Jun. 18, 1992, MI92A1507
Int. Cl.⁶ B05D 7/00

U.S. Cl. 427—215 7 Claims

1. A process for the production of hydrophobic, free-flowing pellets having an average particle size of 5 to 150 μm comprising the steps of:

- providing a first hydrophilic inorganic powder and a second hydrophilic inorganic powder which is separate and distinct from said first inorganic powder;
- providing an aqueous emulsion comprising one or more hydrophobic polyorganosiloxanes;
- adding together in a granulator said first and said second inorganic powders and said aqueous emulsion to provide a mixture, said mixture comprising from about 0.05 to 15% by weight said hydrophobic polyorganosiloxane and processing said mixture in said granulator; and
- heating said mixture subsequent to said step (iii) for up to 24 hours at a temperature of from 120° to 600° C. to provide said free-flowing pellets.

5,589,223

PROCESS FOR PRODUCING CEMENT CUTTING TOOLS HAVING BOTH LONGITUDINAL AND GRANULAR CRYSTAL STRUCTURESNiro Odani, Hironori Yoshimura, Akira Osada, Tetsuya Tanaka, and Seichiro Nakamura, all of Ibaraki-ken, Japan, assignors to Mitsubishi Material Corp., Tokyo, Japan
Division of Ser. No. 73,328, Jun. 8, 1993, Pat. No. 5,436,071, which is a continuation-in-part of Ser. No. 644,446, Jan. 23, 1991, abandoned. This application Mar. 21, 1995, Ser. No. 408,691Claims priority, application Japan, Jan. 31, 1990, 2-21048; Jan. 31, 1990, 2-21048; Aug. 4, 1992, 4-227874; Aug. 11, 1992, 4-235265; Aug. 11, 1992, 4-235266; Aug. 11, 1992, 4-235267
Int. Cl.⁶ C23C 16/30

U.S. Cl. 427—248.1 4 Claims



1. A process for producing a cermet cutting tool comprising the steps of:

- preparing a substrate, having a surface, from titanium carbo-nitride based cermet;
- forming a coating layer onto the surface of said substrate using a first chemical vapor deposition and a second chemical vapor deposition;
- wherein said first chemical vapor deposition is performed using a reaction gas comprised of 1-5% of TiCl_4 , 0.1-1% of CH_3CN , and 0-25% of N_2 , with the remaining portion being H_2 , at a reaction temperature of 800°-900° C. and a reaction pressure of 30-200 Torr, so as to form at least one titanium carbo-nitride layer having a longitudinal growth crystal struc-

ture in which crystal grains are elongated along a direction perpendicular to the surface of said substrate;

- said second chemical vapor deposition is performed at a reaction temperature of 950°-1050° C. so as to form at least one granular crystal layer having a granular crystal structure, each said granular crystal layer being formed from a compound selected from the group consisting of titanium carbide (TiC), titanium nitride (TiN), titanium carbo-oxy-nitride (TiCNO), and aluminum oxide (Al_2O_3); and
- said coating layer is formed by said first chemical vapor deposition and said second chemical vapor deposition to comprise at least one of the following crystal structures:
 - a crystal structure which changes from said granular crystal structure to said longitudinal growth crystal structure in going from said substrate to the surface of said coating layer;
 - a crystal structure which changes from said granular crystal structure to said longitudinal growth crystal structure and back to said granular crystal structure in going from said substrate to the surface of said coating layer; and
 - a crystal structure which changes from said longitudinal growth crystal structure to said granular crystal structure in going from said substrate to the surface of said coating layer.

5,589,224


APPARATUS FOR FULL WAFER DEPOSITION

Avi Tepman, Cupertino, Calif.; Takeshi Jinbo, Ichihara, Japan; Hiroyuki Takahama, Sawara, Japan, and Akihiko Saito, Chiba, Japan, assignors to Applied Materials, Inc., Santa Clara, Calif.

Continuation-in-part of Ser. No. 954,850, Sep. 30, 1992. This application Sep. 22, 1994, Ser. No. 310,617

Claims priority, application Japan, Sep. 30, 1993, 5-245469
Int. Cl.⁶ C23C 16/00

U.S. Cl. 427—248.1 13 Claims



1. A deposition shield arrangement for limiting the deposition of deposition materials on internal chamber components during the processing of a substrate in the deposition chamber, comprising: a substrate support member disposed in the chamber and selectively positionable in the chamber to receive a substrate thereon;

- a shield member extending circumferentially around the substrate support member and cooperating with said substrate support member to prevent deposition on the deposition chamber interior surfaces shielded by said shield member and said substrate support member during the processing of a substrate in the chamber;
- said support member including a circumferential groove extending inwardly of the substrate receiving portion thereof; and
- said shield member including a circumferential, downwardly extending portion received in said groove when said support member is positioned for the processing of a substrate in the chamber.

10. A method of shielding the interior surfaces of a processing chamber from a deposition environment maintained within the chamber, comprising the steps of:

5,589,226

METHOD AND DEVICE FOR APPLYING LIQUID MATERIAL, IN PARTICULAR A HOT MELT, BY MEANS OF A SEQUENTIALLY OPERATING APPLICATOR TO A SUBSTRATE

Herman R. Geul, Leiden, Netherlands, assignor to Nordson Corporation, Westlake, Ohio

PCT No. PCT/NL93/00113, § 371 Date Nov. 30, 1994, § 102(e)
Date Nov. 30, 1994, PCT Pub. No. WO93/24239, PCT Pub. Date Dec. 9, 1993


PCT Filed Jun. 2, 1993, Ser. No. 347,328

Claims priority, application Netherlands, Jun. 4, 1992, 9200984

Int. Cl.⁶ B05D 5/00; B05C 5/00

U.S. Cl. 427—286

13 Claims



1. Method for applying a material pattern by means of a sequentially operating applicator to a substrate moving in a direction of movement relative to said applicator, by way of a control valve means for liquid hot melt adhesive material, said valve means being controllable for opening and closing, and being connected to a material supply, which material pattern in the direction of movement of the substrate, is sub-divided into pattern parts with spacing between them, characterised in that use is made of at least two alternately operating control valves which are connected to the material supply and are made to open and close sequentially with each valve alternately being in the open position when the other valve is in the closed position and the outflow from each two alternately operating control valves being directed to locations on the substrate in a single row of pattern parts in alignment with the direction of travel of the substrate.

5,589,225

GRANULATING-COATING APPARATUS AND GRANULATING AND COATING METHOD USING THE SAME

Shuri Yamada, Hosoe-cho; Masanori Ogawa, Hamakita, and Kazuomi Unosawa, Hamamatsu, all of Japan, assignors to Freund Industrial Co., Ltd., Tokyo, Japan


Filed Mar. 2, 1995, Ser. No. 397,568

Claims priority, application Japan, Mar. 11, 1994, 6-040860

Int. Cl.⁶ B05D 7/00

U.S. Cl. 427—212

32 Claims



14. A method of granulating and coating, wherein articles to be processed are granulated or coated by use of a granulating coating apparatus comprising a processing container, in which articles to be processed are contained, said processing container comprising a fluidized bed container, in which gas is introduced from under said articles received in said container, to form a fluidized bed;

- a spraying means including a spray gun for spraying a binder liquid or a coating liquid onto said articles;

an adhered article removing means for removing adhered articles adhering to said spray gun; and

- an adhered article receiving means for receiving said adhered articles removed by said adhered article removing means; whereby at least one of said spraying means and said adhered article removing means is reciprocally movable in the horizontal direction relative to the other, said method including the steps of horizontally reciprocating at least one of said spraying means and said adhered article removing means moves whereby adhered articles on said spray gun are removed by said adhered article removing means and said adhered articles that are removed are received into said adhered article receiving means and granulating or coating said articles by introducing gas from under said articles into said container.

5,589,227

METHOD FOR PRESERVING ROLLERS IMMERSED INTO THE MOLTEN ALLOY BATH FOR EXTENDING THE OPERATING LIFE THEREOF

Horacio C. Falia, Remedios de Escalada, and Carlos I. Rojas, Lanús-Buenos Aires, both of Argentina, assignors to Comesi S.A.I.C., Buenos Aires, Argentina


Filed Mar. 30, 1995, Ser. No. 413,310

Claims priority, application Argentina, Aug. 17, 1994, 329118
Int. Cl.⁶ B05D 1/00

U.S. Cl. 427—348

3 Claims

1. A process for extending the life of rollers used in formation of steel sheet bands, comprising the steps of immersing the rollers into an alloy bath through gas feeding, applying at least one mechanical scraper means with hard steel cutting edges against each roller surface of the rollers, and providing a source of inert gas to provide a fluid action by injecting said inert gas through an inner portion of said mechanical scraper.



5,589,228

PROCESS FOR COATING VEHICLE BODIES AND AQUEOUS COATING

Egon Wegner, Drensteinfurt; Ulrich Poth, Münster; Lutz-Werner Gross, Haltern, and Klaus Weidemeier, Münster, all of Germany, assignors to BASF Lacke + Farben, AG, Muenster-Hiltrup, Germany

Continuation of Ser. No. 934,624, Oct. 21, 1992, abandoned. This application Oct. 11, 1994, Ser. No. 321,082

Claims priority, application Germany, Feb. 26, 1990, 40 05 961.8

Int. Cl.⁶ B05D 3/02; 1/36

U.S. Cl. 427—407.1

14 Claims

1. A process for coating vehicle bodies, comprising the steps of:
 - (1) applying to a substrate an electro-dipping primer and baking the primer
 - (2) optionally, applying an intermediate primer, resistant to damage by stone chips and baking separately or together with the filler coat applied in stage (3)
 - (3) applying a filler and baking the filler and
 - (4) applying a single- or multi-layer top coating and baking, in which the intermediate primer and/or filler-coat employed is an aqueous stoving enamel containing as the binder a combination of
 - (A) a water-dilutable polyurethane resin,
 - (B) a water-dilutable polyester resin and
 - (C) an aminoplast resin,
 in which component (A) has an acid number from 10 to 60 and a number-average molecular weight of 4000 to 25,000 and is prepared by reacting
 - (a) a polyester- and/or polyether-polyol having a number-average molecular weight of 400 to 5000, or a mixture of such polyester- and/or polyether-polyols,
 - (b) a polyisocyanate, or a mixture of polyisocyanates,
 - (c) a compound which contains in the molecule at least one group which is reactive towards isocyanate groups and at least one group which is capable of anion formation, or a mixture of each compounds, and optionally
 - (d) an organic compound which contains hydroxyl and/or amino groups and has a molecular weight of 40 to 400, or a mixture of such compounds,
 with one another and at least partly neutralizing the reaction product formed, wherein component (A) is employed in an amount of 40 to 70% by weight, component (B) in an amount of 15 to 40% by weight and component (C) in an amount of 8 to 35% by weight, in which the percentage by weight data are based on (A)+(B)+(C)=100% by weight, and component (B) is a water-dilutable polyester resin which has an acid number of 20 to 100, preferably 25 to 45,

and a hydroxyl number of 40 to 150, preferably 50 to 80, and can be prepared by reacting

- (i) an organic compound containing at least three functional groups, in which at least one of the functional groups is a carboxyl group and the other functional groups are selected from the group consisting of hydroxyl, amino, carboxyl, acid anhydride groups, and mixtures thereof, where an acid anhydride group is counted as two functional groups, and mixtures of such organic compounds,
 - (ii) a cyclic dicarboxylic acid, or a mixture of cyclic dicarboxylic acids,
 - (iii) optionally an aliphatic dicarboxylic acid, or a mixture of aliphatic dicarboxylic acids,
 - (iv) a polyol in which at least one α -C atom is a secondary or tertiary C atom or a member in a carbon-containing ring system, or a mixture of such polyols, and
 - (v) optionally a polyol other than (iv), or a mixture of such polyols,
- with one another, the carboxylic acid components ((i)+(ii)+(iii)) and the polyol components ((iv)+(v)) being employed in a molar ratio of 3:4 to 7:8, the molar ratio between (i)+(ii) and (iii) being 50:50 to 100:0, and the molar ratio between (iv) and (v) being 40:60 to 100:0, and at least partly neutralizing the reaction product formed.

5,589,229

COMPOSITION AND METHOD FOR PREVENTING MOSS GROWTH ON ROOFS


Richard Howard, 30311 Camas Swale Rd., Creswell, Oreg. 97426

Continuation-in-part of Ser. No. 120,949, Sep. 14, 1993, Pat. No. 5,366,767. This application Nov. 21, 1994, Ser. No. 342,757

Int. Cl.⁶ B05D 7/00; C09D 5/14

U.S. Cl. 427—421

2 Claims



2. A method of preventing parasitic growth on a porous weather exposed surface material, the method comprising the steps of:
 - providing an aqueous penetrant solution having a pH of at least 11.0 comprising Na_2O and SiO_2 at a combined concentration between 10-percent and 30-percent (W/V);
 - translating a boom along a path across a roof, wherein the boom is substantially parallel to the roof and perpendicular to the direction of the path;
 - pumping the aqueous penetrant solution through plural nozzles distributed equidistantly across the boom;
 - applying at least approximately 0.75 gallons of the solution per 100 square feet of the surface material; and
 - allowing the solution to dry on and in the surface material at ambient temperatures.

5,589,230

POLYMERIZABLE, CURABLE MOLDING COMPOSITION AND A MOLDING OR COATING PROCESS USING THIS MOLDING COMPOSITION

Yoshitami Yamamura; Nobuhiko Morimoto, and Nobuyuki Tanaka, all of Hyogo-ken, Japan, assignors to Henkel Kommanditgesellschaft auf Aktien, Duesseldorf, Germany


Filed Apr. 7, 1995, Ser. No. 418,977

Claims priority, application Japan, Oct. 9, 1992, 4-271463; Mar. 1, 1993, 5-40066

Int. Cl.⁶ B05D 3/06

U.S. Cl. 427—493

32 Claims



1. A polymerizable curable composition comprising (A) 100 parts by weight of an unsaturated epoxyester resin with an acid value below 3.0, (B) 10 to 40 parts by weight of a polymerizable monomer selected from the group consisting of phenoxyethyl acrylate, 2-acryloxyethyl-2-hydroxypropyl phthalate and mixtures thereof and (C) 1 to 5 parts by weight of a mixture of hydroxyketone oligomer and 2-hydroxy-2-methyl-1-phenylpropan-1-one.

5,589,232

METHOD OF MAKING A WEAR COMPONENT BY PLASMA JET CVD


Matthew Simpson, Arlington, Mass., assignor to Norton Company, Worcester, Mass.

Continuation of Ser. No. 773,465, Oct. 9, 1991, Pat. No. 5,411,758. This application Sep. 19, 1994, Ser. No. 308,374

Int. Cl.⁶ B05D 3/06

U.S. Cl. 427—577

13 Claims



1. A method of making a wear component, comprising the steps of:
 - providing a base surface;
 - producing a synthetic diamond film by plasma jet chemical vapor deposition having a thickness of at least 20 microns and an equivalent strain of at least 0.08 percent; and
 - applying said diamond film to said base surface.

5,589,233

SINGLE CHAMBER CVD PROCESS FOR THIN FILM TRANSISTORS


Kam Law, Union City; Robert Robertson, Palo Alto, and Guofu J. Feng, San Jose, all of Calif., assignors to Applied Materials, Inc., Santa Clara, Calif.

Continuation of Ser. No. 174,103, Dec. 28, 1993, abandoned. This application Jun. 6, 1995, Ser. No. 466,915

Int. Cl.⁶ C23C 16/00; B05D 3/06

U.S. Cl. 427—579

17 Claims

5,589,231
HALOGEN-ACTIVATED CHEMICAL VAPOR DEPOSITION OF DIAMOND


Robert H. Hauge, Houston, Tex., and Chenyu Pan, Tucson, Ariz., assignors to Rice University, Houston, Tex.

Filed Apr. 4, 1995, Ser. No. 417,050

Int. Cl.⁶ B05D 3/06; 3/14; C23C 16/26

U.S. Cl. 427—561

36 Claims



1. A method of depositing diamond on a substrate, said method comprising:
 - providing a first gas stream comprising molecular halogen, said first gas stream being substantially free of hydrogen-containing species;
 - treating said first gas stream so as to dissociate at least a portion of said molecular halogen into atomic halogen;
 - admixing with said first treated gas stream hydrogen gas and a carbon-containing species, which hydrogen gas and carbon-containing species have not been pretreated for activation to a high energy level, to provide a gas stream mixture;
 - flowing said gas stream mixture over the substrate so as to deposit diamond on at least a portion of said substrate.

1. A method of sequentially depositing an intrinsic silicon layer and a doped silicon layer containing a dopant on a substrate positioned in a chemical vapor deposition chamber having interior chamber surfaces without substantially contaminating the intrinsic silicon layer by said dopant, said method comprising the steps of:
 - depositing simultaneously on said substrate and said interior chamber surfaces a layer of at least one insulating material of a thickness sufficient to cover up any residual dopant particles left on said interior chamber surfaces from a previous deposition cycle;
 - depositing a layer of intrinsic silicon having a first thickness on top of said at least one insulating material on said substrate, and
 - depositing a layer of doped silicon having a second thickness on top of said intrinsic silicon on said substrate.

wherein all three depositing steps which comprise a deposition cycle are performed in a single chemical vapor deposition chamber without an in-situ cleaning step between each deposition cycle.


5,589,234

METHOD OF MANUFACTURING ULTRAFINE PARTICLES OF A COMPOUND

Hiroto Mori, Saita, and Hidehiro Yasuda, Toyonaka, both of Japan, assignors to Osaka University, Osaka-Fu, Japan
Filed Dec. 27, 1993, Ser. No. 173,113

Claims priority, application Japan, Jun. 23, 1993, 5-174650
Int. Cl.⁶ B05D 3/06; C23C 16/00
U.S. Cl. 427-597

5 Claims



1. A method of manufacturing ultrafine particles of a compound consisting of at least two elements on the surface of a substrate comprised of at least one material selected from the group consisting of an organic material and an inorganic material, the method comprising:

- depositing a first element onto a surface of the substrate by a method selected from the group consisting of vacuum deposition, sputtering, chemical vapor deposition (CVD), and electron beam deposition, to provide a layer of particles of the first element, each of the particles having a particle size ranging from 2 to 50 nm, which particle size is effective to permit spontaneous alloying;
- depositing successively at least one additional element onto the layer of the first element on the surface of the substrate by a method selected from the group consisting of vacuum deposition, sputtering, chemical vapor deposition (CVD), and electron beam deposition, to provide respective layers of particles of the at least one additional element, each of the particles of the respective at least one additional element having a particle size ranging from 2 to 50 nm, which particle size is effective to permit spontaneous alloying, the successive depositions taking place at respective deposition rate ranges which are effective for forming a compound by spontaneously alloying the first element and the at least one additional element over a time period effective to provide a preselected area density; and
- reacting the layers of particles on the substrate at a reaction temperature ranging from below 32° C. to -173° C., and under a vacuum ranging from 10⁻¹¹ to 10⁻¹ Torr to spontaneously alloy the first element and the at least one additional element.

5,589,235

NONLINEAR OPTICAL MATERIAL AND ITS METHOD OF MANUFACTURE


Kazufumi Ogawa, Osaka, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan
Continuation of Ser. No. 681,994, Apr. 8, 1991, abandoned.

This application Jun. 11, 1993, Ser. No. 76,284
Claims priority, application Japan, Apr. 13, 1990, 2-98499
Int. Cl.⁶ C09K 19/00

U.S. Cl. 428-1

10 Claims

1. A nonlinear optical material having a high Secondary Harmonic Generation effect resulting from:



forming an organic orientation film on a surface of each of two substrates;
positioning the surface of each of said substrates having said organic orientation film in a face to face relationship and establishing a gap therebetween;
introducing into said gap energy-beam sensitive liquid-crystal monomer molecules having a dipole moment of a magnitude so that said monomer molecules become oriented in an aligned direction when exposed to a magnetic field;
aligning said energy beam sensitive monomer molecules in a specified direction by exposure to a magnetic field; and
exposing said substrates containing said monomer to radiation in an amount between 10 and 100M rad. to yield a cross linked polymer.

5,589,236


COEXTRUSION OF LIQUID CRYSTAL POLYMERS AND THERMOPLASTIC POLYMERS

Andrew C. Harvey, Waltham; Richard W. Lusignea, Brighton, and Leslie S. Rubin, Newton, all of Mass., assignors to Superex Polymer Inc., Waltham, Mass.

Continuation-in-part of Ser. No. 125,919, Sep. 23, 1993, abandoned, and Ser. No. 126,043, Sep. 23, 1993, abandoned, said Ser. No. 125,919 and Ser. No. 126,043, each is a division of Ser. No. 778,812, Dec. 12, 1991, Pat. No. 5,288,529, which is a continuation-in-part of Ser. No. 367,433, Jun. 16, 1989, abandoned. This application Mar. 24, 1994, Ser. No. 217,236
Int. Cl.⁶ C09K 19/00

U.S. Cl. 428-1

25 Claims



1. A multilayer film prepared from one or more liquid crystal polymers (LCPs) and one or more thermoplastic polymers (TPs) having at least one LCP layer which has a controlled molecular orientation.

5,589,237

REVERSIBLE DISPLAY MEDIUM

Ryojiro Akashi; Takashi Morikawa; Masanobu Ninomiya, and Takashi Uematsu, all of Minami Ashigara, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan


Filed Jun. 21, 1994, Ser. No. 262,910

Claims priority, application Japan, Jun. 25, 1993, 5-177628; Sep. 7, 1993, 5-246147; Oct. 6, 1993, 5-272969; May 11, 1994, 6-120753

Int. Cl.⁶ C09K 19/52; G02F 1/137

U.S. Cl. 428-1

9 Claims



1. A reversible display medium comprising a substrate having a recording layer containing a side chain polymeric liquid crystal repeatedly switchable between a transparent state and a light-scattered state by the action of at least one of heat, an electrical field, and a magnetic field.

wherein said side chain polymeric liquid crystal is a copolymer comprising at least a repeating unit derived from a liquid crystal monomer and a repeating unit derived from a non-liquid crystal monomer having a hydrogen bond-forming substituent, said side chain polymeric liquid crystal has a multi-domain structure in which the domain diameter at the maximum of the domain number distribution is not greater than 3 μm.

5,589,239

VARIABLE-ANGLE OPTICAL DEVICE WITH OPTICALLY TRANSPARENT SUBSTANCE

Haruo Tomono, Kanagawa-ken; Naoki Kobayashi; Toshiyuki Nakajima, both of Tokyo; Takashi Kai, Kanagawa-ken; Masayoshi Sekine, Tokyo; Masahiro Watabe, and Kazuhiro Ohki, both of Kanagawa-ken, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 429,613, Oct. 31, 1989, abandoned.


This application Sep. 14, 1993, Ser. No. 120,230

Claims priority, application Japan, Nov. 2, 1988, 63-277646; Nov. 2, 1988, 63-277647; Nov. 2, 1988, 63-277648; Apr. 28, 1989, 1-107742

Int. Cl.⁶ G02B 3/14

U.S. Cl. 428-34

22 Claims



1. An optical element in which an optically transparent substance is sandwiched between transparent paired plate-shaped elements by utilizing a connection member capable of deforming, and the angle formed by said paired plate-shaped elements is caused to vary by a force applied thereto from the outside, whereby a predetermined optical characteristic for a passing light ray is obtained, wherein said connection member is constructed from a high-molecular weight polymeric material that is capable of being molded and said optically transparent substance comprises silicone oil or modified silicone oil.

5,589,240

MULTIPLE CELLULAR CONFINEMENT ASSEMBLY FOR PLANT PROPAGATION


Ronald A. Hunter, Finksburg, Md., assignor to Atlantic Construction Fabrics, Inc., Richmond, Va.

Filed Mar. 28, 1995, Ser. No. 412,780

Int. Cl.⁶ B29D 22/00; A01G 9/02

U.S. Cl. 428-34.1

5 Claims



1. A compressible cellular container assembly (100) for plant propagation which is confineable in subsoil of the ground, comprising:

- collapsible linked two-layer, open ended structure containers (110) formed of opposed container walls (112), said containers being of volute horizontal cross-section and bonded by

5,589,238

DECORATIVE GARLAND


Edward Ruff, Boca Raton, Fla., assignor to Santa's Best, Northfield, Ill.

Filed Sep. 28, 1995, Ser. No. 535,946

Int. Cl.⁶ A41G 1/04

U.S. Cl. 428-10

14 Claims



1. A garland comprising an elongated base ribbon and a plurality of annealed metal wires spirally wrapped around said base ribbon member forming a garland without spring back characteristics.

- weldment (114) at opposed contacting wall portions to form multiple cells (116), for retention of a soil mix and an associated plant;
- b) a permeable soil drain board (120), upon which the soil mix structure containers (110) are supported, said drain board defining a fluid permeable mat (124) having pylons (126); said mat resting upon a foraminous screen (122);
- c) an impermeable ground liner (130) resting within a cavity of subsoil of the ground, said liner being interposed between ground and drainage board (120) to confine the container (110) and drainage board (120) on at least three sides thereof;
- d) a drainage means (140) for the liner to drain recyclable water and fertilizer from the drainage means.

5,589,241

FUEL TANK HAVING AN INTEGRALLY MOLDED PERMEATION BARRIER


Ernest D. Stiles, St. Clair Shores, and Dale L. Hartsock, Livonia, both of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Dec. 14, 1992, Ser. No. 990,497

Int. Cl.⁶ B65D 1/26

U.S. Cl. 428—36.9

3 Claims



1. A blow-molded polymeric fuel tank having a permeation retardant laminate on a surface of said tank, said laminate consisting of a polymeric carrier film having first and second surfaces and an uninterrupted permeation retardant coating applied to said first surface of said film, said second surface of said film being welded to said tank surface.

5,589,242

HOUSING LINING

Reinhard Stief, Weinheim; Roger Schork, Mörlenbach; Gerhard Müller-Broll, Rimbach; Thomas Jost, Weinheim; Manfred Mattutat, Ladenburg, and Klaus-Dieter Schmitt, Gornhelmertal, all of Germany, assignors to Firma Carl Freudenberg, Weinheim, Germany


Filed Dec. 9, 1993, Ser. No. 164,182

Claims priority, application Germany, Dec. 10, 1992, 42 41 515.2

Int. Cl.⁶ E04B 1/82

U.S. Cl. 428—45

8 Claims



1. A housing lining comprising a sound-absorbent layer of fibers; wherein the housing lining includes a supporting structure comprising at least a supporting frame located at a peripheral edge of said layer of fibers;

wherein said supporting structure is formed of a first portion of fibers, wherein said first portion of fibers comprises compressed and glued fibers;

wherein said supporting structure substantially bounds at least one intermediate area formed of a second portion of fibers; wherein the fibers in said supporting structure are more compressed than the fibers in said intermediate area; and

wherein said supporting structure comprises at least one cup-shaped convexity forming a Helmholtz resonator with an opening for air to pass through.

5,589,243

REINFORCED FOAM CORES AND METHOD AND APPARATUS OF PRODUCTION


Stephen W. Day, Dayton, Ohio, assignor to Webcore Technologies, Inc., Centerville, Ohio

Continuation-in-part of Ser. No. 102,892, Aug. 6, 1993, Pat. No. 5,462,623, which is a continuation-in-part of Ser. No. 877,985, May 4, 1992, abandoned. This application Jul. 17, 1995, Ser. No. 503,205

Int. Cl.⁶ B32B 3/10; 3/18

U.S. Cl. 428—56

24 Claims



1. A reinforced foam core panel adapted for use between generally parallel skins, comprising a plurality of boards of rigid plastics foam material with each board having opposite faces, a strip of porous and fibrous flexible web material overlying at least one of said faces of each said board, said boards of foam material arranged in a stack with said strips of web material disposed between said boards, means for connecting said boards of rigid foam material and said strips of porous and flexible fibrous web material together while maintaining substantial porosity throughout said strips of web material to form a core panel with said boards having opposite side surfaces and with said strips of web material having edge portions extending to said opposite side surfaces, said side surfaces of said boards being exposed for receiving an adhesive resin for attaching the skins to said side surfaces and to said edge portions of said strips of web material, the porosity of said strips of web material providing for the flow of resin through said strips to form integral tie webs connecting the skins, said boards of foam material defining fillet recesses within said side surfaces adjacent said edge portions of said strips of web material, and said recesses are adapted to receive the resin for increasing the bond of said strips to said skins.

5,589,244

MAGNETO-OPTICAL DISC

Kunio Takada, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Feb. 7, 1994, Ser. No. 192,749


Claims priority, application Japan, Feb. 16, 1993, 5-026932

Int. Cl.⁶ G11B 5/66; B32B 3/02

U.S. Cl. 428—64.3

4 Claims

1. A magneto-optical disc comprising a resin substrate and a magneto-optical film, wherein a birefringence distribution of said substrate in a static state is set so that a disc phase difference during rotation of the disc is eliminated.



5,589,245

TEXTILE SPACER MATERIAL, OF VARIABLE THICKNESS, PRODUCTION PROCESS AND USES FOR IT

Friedrich Roell, Biberach, Germany, assignor to TECNIT-Technische Textilien und Systeme GmbH, Laupheim, Germany


Filed Feb. 22, 1994, Ser. No. 200,185

Claims priority, application Switzerland, Feb. 22, 1993, 00540/93

Int. Cl.⁶ B32B 3/26; 5/26

U.S. Cl. 428—85

12 Claims



1. Textile spacer material having at least an upper and a lower knitted covering layer, which are connected by at least one pile thread, at least one of said covering layers comprising inlaid weft or warp yarns, wherein at least one of the inlaid yarns is introduced into said one covering layer in a direction transverse to the direction of the pile thread.

5,589,246

HEAT-ACTIVATABLE ADHESIVE ARTICLE


Clyde D. Calhoun, Stillwater, and David C. Koskenmaki, St. Paul, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Oct. 17, 1994, Ser. No. 324,333

Int. Cl.⁶ C09J 7/02

U.S. Cl. 428—120

25 Claims



1. A heat-activatable adhesive article comprising:
- (a) a substantially laterally stable heat recoverable carrier film of memory shaped material and having at least one surface comprising a recessed surface portion and a raised surface portion therein; and
- (b) an adhesive layer in the recessed surface portion in an amount such that the adhesive does not extend above the raised surface portion thereby forming an exposed raised surface portion.

5,589,247

MAGNETIC RECORDING MEDIUM HAVING AN EMBOSSED BACKCOAT LAYER


David A. Wallack, Ventura, Calif.; Donald M. Lewis, Hudson Township, St. Croix County, Wis.; John D. Munter, Oakdale; Peter J. Silbernagel, Woodbury, both of Minn.; Robert V. Heiti, Troy Township, St. Croix County, Wis., and Yuko Yoshida, Kanagawa, Japan, assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Continuation of Ser. No. 353,959, Dec. 12, 1994, abandoned, which is a continuation of Ser. No. 994,930, Dec. 22, 1992, abandoned. This application Jan. 26, 1996, Ser. No. 592,770

Int. Cl.⁶ G11B 5/68

U.S. Cl. 428—141

6 Claims



1. A magnetic recording medium comprising a substrate, a magnetizable layer on a front side thereof and a crosslinked polymeric coating on the backside thereof wherein the coating on the backside ranges from about 0.2 to 3 microns thick and has a smooth surface having a surface roughness not greater than 0.05 microns Ra except that said coating includes in the otherwise smooth surface a plurality of depressions having a depth ranging from 1-50% of the average thickness of said coating and wherein the ratio of the greatest width of a depression to the depth of the depression is from 100/1 to 10,000/1.

5,589,248

SHAPED GLASS SHEET AND A PROCESS FOR THE PREPARATION THEREOF

Shotaro Tomozane; Hirokazu Kidou, and Yukikazu Nakabayashi, all of Toyama, Japan, assignors to Suntec Corporation, Toyama, Japan


Filed Sep. 17, 1993, Ser. No. 123,375

Claims priority, application Japan, Sep. 18, 1992, 4-273386; Sep. 21, 1992, 4-274802; Feb. 25, 1993, 5-059342; Mar. 1, 1993, 5-062491

Int. Cl.⁶ B32B 1/00

U.S. Cl. 428—174

8 Claims




1. A shaped glass sheet having at least one linear bend and two straight sections extending from the bend, characterized in that a radius of curvature of an outer circumference of the bend transverse to the bend is at most 4 times a thickness of the glass sheet and the straight sections of the shaped glass sheet are substantially flat, and wherein the thickness of the glass sheet is 3 mm or more.

5,589,249 MEDICAL COMPOSITE WITH DISCONTINUOUS ADHESIVE STRUCTURE

Carl A. Bodford, Charlottesville; Stephen O. Chester, Staunton, and Rahul K. Nayak, Waynesboro, all of Va., assignors to Poly-Bond, Inc., Waynesboro, Va.
Continuation-in-part of Ser. No. 389,029, Feb. 15, 1995, which is a division of Ser. No. 220,671, Mar. 31, 1994, abandoned, which is a division of Ser. No. 2,421, Jan. 8, 1993, Pat. No. 5,342,469. This application Jul. 18, 1995, Ser. No. 504,066
Int. Cl.⁶ B32B 3/00; 7/06; 7/10

U.S. Cl. 428—200 22 Claims




1. A vapor permeable, liquid impermeable protective fabric composite comprising:
 - (A) a vapor permeable, non-woven fabric substrate formed of a material selected from the thermoplastic polyolefin polymers;
 - (B) at least two vapor permeable and liquid impermeable film substrates; and
 - (C) a thermoplastic adhesive bonding said substrates together into a protective fabric/film/film composite; said fabric substrate having a weight of 0.43–3.0 OSY and percentage bond area of 5–45%; said composite being characterized by passing a viral barrier test (modified ASTM E522) at a level of at least 3 psi and having a moisture vapor transmission rate (ASTM F 1249) of at least 2000 gm/m²/24 hours.

5,589,250 RESIN COMPOSITIONS AND PRINTED CIRCUIT BOARDS USING THE SAME

Motoo Asai, and Ritsuko Kato, both of Gifu, Japan, assignors to Ibiden Co., Ltd., Gifu, Japan
Continuation of Ser. No. 225,331, Apr. 8, 1994, abandoned.
This application Aug. 23, 1995, Ser. No. 518,358
Claims priority, application Japan, Apr. 12, 1993, 5-109961
Int. Cl.⁶ B32B 9/00

U.S. Cl. 428—209 9 Claims




1. A multilayer printed circuit board comprising:
 - a substrate;
 - a first conductor circuit formed on the substrate;
 - an adhesive layer formed on the conductor circuit by dispersing 5–350 parts by weight of particles of a cured heat-resistant resin soluble in an acid or an oxidizing agent into 100 parts by weight of a matrix of an uncured photosensitive resin hardly soluble in the acid or oxidizing agent;
 - a second conductor circuit formed on the adhesive layer and electrically connected to the first conductor circuit through a via-hole;
 wherein the particles of the cured heat-resistant resin include 0.10–1.50% by weight of coloring matter selected from the

group consisting of phthalocyanine, phthalocyanine derivatives and cyanine color.

5,589,251 RESONANT TAG AND METHOD OF MANUFACTURING THE SAME

Hideaki Imaichi; Takeshi Matsumoto; Yuji Suzuki; Koichi Himura, and Tadayoshi Haneda, all of Chigasaki, Japan, assignors to Tokai Electronics Co., Ltd., Chigasaki, Japan
Division of Ser. No. 9,855, Jan. 27, 1993, Pat. No. 5,447,779, which is a continuation-in-part of Ser. No. 827,509, Feb. 28, 1992, abandoned, which is a continuation of Ser. No. 634,529, Dec. 27, 1990, Pat. No. 5,108,822. This application Aug. 22, 1995, Ser. No. 517,690
Claims priority, application Japan, Aug. 6, 1990, 2-206791
Int. Cl.⁶ B32B 3/00


U.S. Cl. 428—209 9 Claims



1. A resonant tag comprising:
 - a first electrode plate having a first area;
 - a second electrode plate having a second area, said second area being larger than said first area;
 - a composite dielectric between said first and second electrode plates and having a third area greater than said second area, said composite dielectric having a thinned portion substantially equal in area to said first area and separating said first electrode from an oppositely corresponding and coextensive portion of said second electrode, said thinned portion of said composite dielectric including material of a first dielectric strength and at least one area within said material of a second dielectric strength lower than said first dielectric strength; and
 - an inductor formed on said composite dielectric and electrically connected to said first and second electrode plates to form a resonant circuit, said at least one area of said composite dielectric having said second dielectric strength providing preferred paths for electrical breakdown of said resonant circuit.

5,589,252
GAS BARRIER LAMINATED MATERIAL
Ryukichi Matsuo, and Toshiaki Yoshibara, both of Saltama, Japan, assignors to Toppan Printing Co., Ltd., Tokyo, Japan
Filed Sep. 29, 1994, Ser. No. 314,802
Claims priority, application Japan, Sep. 30, 1993, 5-245443; Mar. 31, 1994, 6-064187
Int. Cl.⁶ B32B 7/02; 27/40

U.S. Cl. 428—216 10 Claims



1. A gas barrier laminated material comprising a polymer sheet of film substrate, and an inorganic compound layer having a thickness of from 50 angstroms to 3,000 angstroms and a protec-


tive layer having a thickness of from 0.01 μ m to 100 μ m which are laminated in this order, wherein said protective layer is formed by coating on said inorganic compound layer a coating composition containing a metal alkoxide or a hydrolyzate thereof and from 5 parts by weight to 400 parts by weight of an isocyanate compound having two or more isocyanate groups based on 100 parts by weight of the metal alkoxide or hydrolyzate thereof, followed by heat drying.

5,589,253

Patent Not Issued For This Number

5,589,254
METHOD FOR IMPROVING THE ENERGY
ABSORPTION OF A HIGH TENACITY FABRIC DURING
A BALLISTIC EVENT
Louis Dischler, Spartanburg, S.C., assignor to Milliken Research Corporation, Spartanburg, S.C.
Division of Ser. No. 880,045, May 7, 1992, Pat. No. 5,466,503.
This application May 15, 1995, Ser. No. 441,470
Int. Cl.⁶ F41H 1/02; 1/04

U.S. Cl. 428—221 2 Claims




1. A method for making ballistic-resistant fabric which comprises of cutting a plurality of strips of fabric each having a length and a width, made from fibers having a tenacity of at least ten grams/denier, at least one said strip of fabric having a ballistic failure ratio less than one for an impact with a projectile having a velocity of about at least five hundred feet per second, and a ratio of said length of said strip of fabric to said width of said strip of fabric greater than a reciprocal squared of said ballistic failure ratio and attaching said strips of fabric together in substantially overlapping relationship.

5,589,255 ADHESIVE FOR ELECTROLESS PLATING, PRINTED CIRCUIT BOARDS AND METHOD OF PRODUCING THE SAME

Ryo Enomoto, and Motoo Asai, both of Ogaki, Japan, assignors to Ibiden Co., Ltd., Gifu, Japan
Continuation of Ser. No. 41,874, Apr. 2, 1993, abandoned, which is a continuation of Ser. No. 692,729, Apr. 29, 1991, abandoned, which is a division of Ser. No. 344,968, Apr. 28, 1989, Pat. No. 5,055,321. This application Jun. 3, 1994, Ser. No. 253,582

Claims priority, application Japan, Apr. 28, 1988, 63-104044; May 30, 1988, 63-130253; May 30, 1988, 63-130254
Int. Cl.⁶ C09J 7/02

U.S. Cl. 428—261 11 Claims




1. An adhesive suitable for use in electroless plating used in connection with printed circuit boards, comprising:
 - (a) a heat-resistant resin which is slightly soluble in the presence of an oxidizing agent;
 - (b) a plurality of heat-resistant particles which are easily soluble in said oxidizing agent when dispersed in said heat-resistant resin, said heat-resistant particles being selected from the group consisting of (1) quasi particles obtained by adhering at least one of heat-resistant resin fine powders having an average particle size of not more than 2 μ m and inorganic fine powders having an average particle size of not more than 2 μ m to surfaces of heat-resistant particles having an average particle size of 2–10 μ m through heating or with a binder, and (2) agglomerated particles obtained by agglomerating heat-resistant resin fine powders having an average particle size of not more than 2 μ m into an average particle size of 2–10 μ m, through heating or with a binder and then sieving them, and mixtures thereof.

5,589,256
PARTICLE BINDERS THAT ENHANCE FIBER
DENSIFICATION
Michael R. Hansen, Seattle, and Richard H. Young, Sr., Renton, both of Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

Filed Aug. 17, 1992, Ser. No. 931,279
Int. Cl.⁶ A01N 25/34; A61F 13/20; 13/46; A61L 15/16; 15/42; 15/44; 15/60; B32B 5/24; 29/04; 31/12; 33/00; D04H 1/58; 1/64; 1/72; D21H 11/16; 11/20

U.S. Cl. 428—283 56 Claims



1. A method of producing fibers with adhered particles comprising:
 - providing fibers that have hydrogen bonding functional sites;
 - adding particles to the fibers, wherein the particles have a hydrogen bonding or coordinate covalent bonding functionality;
 - interposing a binder having a functional group capable of forming a binder-fiber hydrogen bond as well as a functional group

capable of forming a binder-particle hydrogen bond or a binder-particle coordinate covalent bond between fibers having hydrogen bonding functional sites and particles having a hydrogen bonding or coordinate covalent bonding functionality, the binder selected from the group consisting of (a) a polymeric binder with repeating units, wherein each repeating unit has a functional group capable of forming a hydrogen bond or a coordinate covalent bond with the particles, or a hydrogen bond with the fibers, and (b) a nonpolymeric organic binder, whereby a substantial portion of the particles with said functional groups are bound in particulate form to the fibers primarily by a hydrogen bond or coordinate covalent bond; and

thereafter densifying the fibers with their bound particles by applying external pressure to the fibers.

52. A fiber product comprising:

individualized fibers densified by applying pressure, having a density of 0.1 to 0.7 g/cc, and hydrogen bonding functionalities; and

particles that are bound to the fibers by a binder interposed between the particles and the fibers, the particles having a hydrogen bonding or coordinate covalent bonding functionality, and the binder having a functional group capable of forming a binder-particle hydrogen bond or a binder-particle coordinate covalent bond and a functional group capable of forming a binder-fiber hydrogen bond, the binder selected from the group consisting of (a) a polymeric binder with repeating units, wherein each repeating unit has a functional group capable of forming a hydrogen bond or a coordinate covalent bond with the particles, or a hydrogen bond with the fibers; and (b) a nonpolymeric organic binder, wherein the product comprises 0.05-80% of said bound particles, said bound particles bound to the fibers primarily by a hydrogen bond or coordinate covalent bond.

5,589,257


LOW PERMEABILITY GEOSYNTHETIC CLAY LINER AND METHOD OF MANUFACTURE THEREOF
Richard W. Carriker, Woodstock, and John M. Fuller, Dunwoody, both of Ga., assignors to Claymax Corporation, Chicago, Ill.

Filed May 8, 1995, Ser. No. 436,540

Int. Cl.⁶ B32B 19/06

U.S. Cl. 428-284

15 Claims



1. An improved flexible geosynthetic clay liner having a water permeability less than 5×10^{-10} cm/sec comprising:
a primary carrier sheet of fabric;
a first layer of bentonite disposed on top of the primary carrier sheet;
an intermediate polymeric sheet or fabric layer disposed on top of the first layer of bentonite;
a second layer of bentonite disposed on top of the intermediate layer; and
a cover sheet of fabric disposed on top of the second layer of bentonite.

5,589,258
NON-WOVEN FABRIC COMPRISING AT LEAST ONE SPUNBONDED LAYER

Peter Maddern, and Kenneth J. G. Currie, both of Clwyd, Great Britain, assignors to Kimberly-Clark Limited, Kent, England


Continuation of Ser. No. 388,178, Jul. 14, 1989, abandoned, which is a continuation of Ser. No. 130,386, Nov. 20, 1987, abandoned. This application Nov. 26, 1991, Ser. No. 799,927

Claims priority, application United Kingdom, Mar. 27, 1986, 8607803

Int. Cl.⁶ B32B 5/26; 31/20; 31/22

U.S. Cl. 428-286

11 Claims



1. A laminate comprising a layer of spunbonded polymeric nonwoven filaments and a layer of meltblown polymeric fibers, the laminate having been treated with a thermal stabilizing agent forming an exterior fiber casing on at least one of said filaments and fibers, thermally pattern bonded and subsequently to the pattern bonding of the laminate, calendered by passing through a nip between two rolls including a smooth, hot roll resulting in increased surface abrasion resistance of an average weight loss per thousand rubs of 10.5 milligrams or less while retaining an open fiber structure providing an average air permeability of at least 11 dm³/min per 20 cm² measured by DIN Std 53 887.

5,589,259

INK JET RECORDING PAPER

Kiyoshi Hosoi, and Tsukasa Matsuda, both of Ebina, Japan, assignors to Fujii Xerox Co., Ltd., Tokyo, Japan

Filed Jun. 26, 1995, Ser. No. 494,545

Claims priority, application Japan, Jun. 30, 1994, 6-149538

Int. Cl.⁶ B41M 5/00

U.S. Cl. 428-323

6 Claims

1. An ink jet recording paper, which comprises:
(a) a base paper having an apparent density according to JIS-P8118 of from 0.80 to 0.90 g/cm³, an air permeability according to JIS-P8117 of from 5 to 15 seconds and a formation index of not less than 20; and
(b) a coating layer provided on at least one surface of said base paper, said coating layer having a dried coverage of from 4 to 10 g/m² and comprising (1) a white pigment having a BET specific surface area of from not less than 250 m²/g to less than 400 m²/g and (2) an adhesive.

5,589,260

METHOD AND APPARATUS FOR PRODUCING PLASTIC PRODUCTS

Guy Ben Zvi, Kibbutz Ramat Yohanan; Shlomo Nevo, Neot Afeka, and Michael Berman, Kfar Yona, all of Israel, assignors to Palboard Ltd., Givatayim, Israel

Filed Jul. 19, 1994, Ser. No. 277,184


Claims priority, application Israel, Jul. 23, 1993, 106460

Int. Cl.⁶ B29C 35/10; B32B 5/16

U.S. Cl. 428-327

12 Claims

1. A method of producing plastic products, comprising: cutting into pieces a thermoplastic material having a loss factor higher than 0.005 such as to have a high absorbance of radio-frequency radiation, the pieces being cut so that the bulk of the pieces have a size of 2-10 mm in their largest dimension; mixing said pieces of



thermoplastic material with at least one other particulate material which is an organic plastic material having a loss factor lower than 0.005 so as to have a low absorbance of radio-frequency radiation; depositing said mixture on a supporting surface; applying radio-frequency heating radiation to said mixture sufficient to soften only the outer surfaces of said pieces of thermoplastic material by dielectric heating, while applying pressure to said mixture to bond the mixture together by sintering; and removing said sintered mixture from said supporting surface.

9. Apparatus for producing plastic products, comprising: a table extending longitudinally of the apparatus; a first conveyor belt moving longitudinally over said table for receiving pieces of thermoplastic material to be sintered; a second conveyor belt moving with and aligned over said first conveyor belt at an angle which converges therewith from one end to the opposite end of the first conveyor belt for applying gradually increasing pressure to the pieces of thermoplastic materials on said first conveyor belt; a plurality of pairs of radio-frequency electrodes spaced longitudinally along the length of, and straddling, the two conveyor belts and an RF generator connected to said electrodes for applying sufficient heat to soften the outer surfaces of the pieces of thermoplastic material at the same time as the pieces of thermoplastic material are heated by said radio-frequency radiation to sinter them into a layer on said first conveyor belt.

11. A plastic sintered product including pieces of a thermoplastic material having a loss factor higher than 0.005 such as to have a high absorbance of radio-frequency radiation, the bulk of said pieces having a size of 2-10 mm in the largest dimension, said pieces being mixed with pieces of an organic plastic material having a loss factor lower than 0.005 so as to have a low absorbance of radio-frequency radiation, said sintered product being made according to the method of claim 1.

5,589,261

PERPENDICULAR MAGNETIC FILM, PROCESS FOR PRODUCING THE SAME AND MAGNETIC RECORDING MEDIUM HAVING THE SAME

Kousaku Tamari, Hiroshima, Japan, assignor to Toda Kogyo Corporation, Japan

Continuation of Ser. No. 36,209, Mar. 23, 1993, abandoned.


This application Oct. 24, 1994, Ser. No. 328,135

Claims priority, application Japan, Mar. 30, 1992, 4-105460

Int. Cl.⁶ G11B 5/66; B32B 5/16; B05D 5/12; C23C 14/00


U.S. Cl. 428-332

12 Claims



1. A multilayer perpendicular magnetic film having at least four layers formed of at least two (A)/(B) or (B)/(A) units, the units

disposed one atop the other, each unit having a layer (A) having a spinel crystal structure and represented by the following formula:



wherein A represents Co, Ni and Mn, or x is not more than 1, disposed a layer (B) having a spinel crystal structure and represented by the following formula:



wherein B represents Fe, Ni or Mn, and y is not more than 1, the oxide of each of said layer (A) and said layer (B) being respectively composed of spinel crystals having an average crystal grain size of 30 to 100 Å, the number of the (A)/(B) units or (B)/(A) units being 2 to 30, and the thickness of one unit (A)/(B) or (B)/(A) being less than 1000 Å.

5,589,262

PERPENDICULAR MAGNETIC RECORDING MEDIUM HAVING A SOFT MAGNETIC UNDERLAYER WITH A STRIPE MAGNETIC DOMAIN STRUCTURE

Katsumi Kiuchi, Ebina; Hiroaki Wakamatsu, Yokohama; Fumitake Suzuki, Kawasaki, and Takao Koshikawa, Atsugi, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Continuation of Ser. No. 144,613, Nov. 1, 1993, abandoned, and Ser. No. 531,339, May 31, 1990, abandoned. This application Aug. 8, 1994, Ser. No. 286,951

Claims priority, application Japan, May 31, 1989, 1-138273; May 31, 1989, 1-138274; Nov. 20, 1989, 1-302719; Dec. 19, 1989, 1-329240; Dec. 20, 1989, 1-330667

Int. Cl.⁶ G11B 5/66

U.S. Cl. 428-336

15 Claims



1. A perpendicular magnetic recording medium for use in a magnetic recording/reproducing apparatus which has a magnetic head for recording/reproduction, said perpendicular magnetic recording medium comprising:

- a substrate;
- a magnetic recording layer having a perpendicular magnetic anisotropy;
- a soft magnetic under layer interposed between said substrate and said magnetic recording layer and subject to undergoing domain wall motion when the perpendicular magnetic recording medium is used in the magnetic recording/reproducing apparatus as a result of a stray magnetic field inherently existing within the magnetic recording/reproducing apparatus in the vicinity of the magnetic head thereof, the soft magnetic underlayer having a permeability selected to be in a range of from 50 to 800 and a thickness selected to be in a range of from 4 μm to 20 μm; and
- a stripe magnetic domain structure, formed in said soft magnetic under layer, suppressing motion of the domain walls of said soft magnetic under layer at least with respect to an external magnetic field having a field strength which is greater than 0 and less than or equal to 10 Oe, where the stray magnetic field has a maximum field strength of 10 Oe.

5,589,263

MAGNETIC RECORDING MEDIUM HAVING A FERROMAGNETIC METAL THIN FILM, A DRY ETCHED LAYER, A CARBONACEOUS FILM, AND A LUBRICANT FILM

Hideyuki Ueda; Hiroshi Seki, both of Osaka; Kenji Kuwahara, Ikoma; Mikio Mura; Kiyosi Takahashi, both of Osaka; Masaru Odagiri, Kawanishi, and Sadayuki Okazaki, Osaka, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Dec. 28, 1994, Ser. No. 365,216

Claims priority, application Japan, Dec. 28, 1993, 5-337781

Int. Cl.⁶ G11B 5/72

U.S. Cl. 428—336

25 Claims



1. A ferromagnetic metal thin film recording medium comprising a non-magnetic substrate, a ferromagnetic metal thin film comprising aggregates of columnar crystal particles of cobalt formed on said non-magnetic substrate, a dry etched layer which is formed in a surface layer of said ferromagnetic metal thin film and contains oxygen atoms in a higher concentration than the remaining part of said ferromagnetic metal thin film, a carbonaceous film formed on said dry etched layer of said ferromagnetic metal thin film, and in which an atomic ratio of oxygen to carbon measured at an interface between said carbonaceous film and said dry etched layer is at least 0.50:1, and a lubricant layer formed on said carbonaceous film.

5,589,264

UNSPUN ACRYLIC STAPLE FIBERS

Han S. Yoon; Tae W. Son; Byung C. Kim; Chul J. Lee; Byung G. Min, all of Seoul, and Jae W. Cho, Anyang, all of Rep. of Korea, assignors to Korea Institute of Science and Technology, Seoul, Rep. of Korea

Continuation-in-part of Ser. No. 128,657, Sep. 30, 1993, abandoned. This application May 22, 1995, Ser. No. 446,287

Claims priority, application Rep. of Korea, Oct. 1, 1992, 92-18009

Int. Cl.⁶ D02G 3/00

U.S. Cl. 428—359

3 Claims



1. A white acrylic staple fiber which is prepared by a simple extrusion of a gel crystal formed from a PAN/H₂O mixture without spinning, consisting of fibrils which are extended and uniformly gathered in parallel with each other, and said fiber having the following properties: a degree of orientation observed by X-ray diffraction of 80–97%; a length of 5–500 mm; a thickness of 5–500 μm; a length to thickness ratio of 100–100,000 determined by a scanning electron microscope; a tensile strength of 10–70 kg/mm²;

an initial tensile modulus of 300–1,500 kg/mm²; an elongation of 5–20%; and a specific surface area of 1–50 m²/g.

5,589,265

AROMATIC POLYAMIDE STAPLE FIBER BUNDLES OF IMPROVED DISPERSIBILITY IN VISCOUS MATRICES AND PRODUCTION OF FIBER-REINFORCED COMPOSITES

Richard Neuert, Winkelhaid, and Gerhard Stein, Kelheim, both of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Filed Jan. 13, 1995, Ser. No. 372,366

Claims priority, application Germany, Jan. 18, 1994, 44 01 233.0

Int. Cl.⁶ D02G 3/00

U.S. Cl. 428—361

12 Claims

1. A staple fiber bundle comprising aromatic polyamide staple fibers having a staple length of at least 1 mm, wherein the staple fibers have been treated with an effective amount of an agent which enhances the cohesion of the fiber bundle, and wherein the fiber bundle cohesion enhancing agent is a modified cellulose derivative, a water-soluble alkali metal silicate, a water-soluble polymer, a tallow fat derivative, a polyurethane resin, or an organosilane adhesion promoter of the formula



herein n is a number from 1 to 5, X is —COOR¹ or —CN, Y is alkyl, alkoxy, or halogen, and R¹ is alkyl, cycloalkyl, aryl, or aralkyl.

5,589,266

Patent Not Issued For This Number

5,589,267

POLYVINYL ETHER ENCAPSULATED PARTICLES

Francois Delwel, Dordrecht, Netherlands, and David J. Lang, Ossining, N.Y., assignors to Lever Brothers Company, Division of Conopco, Inc., New York, N.Y.

Continuation-in-part of Ser. No. 239,663, May 9, 1994, Pat. No. 5,460,743. This application Jul. 17, 1995, Ser. No. 459,915

Int. Cl.⁶ B32B 5/16; C11D 7/54; A62D 3/00

U.S. Cl. 428—407

15 Claims

1. A encapsulated particle for use in liquid cleaning compositions comprising:

- 20–90% by weight of a continuous coating blend comprised of
 - 70 wt. % to 1 wt. % of a polyvinyl ether material having a formula



(1)

wherein x is an integer from 18–22 and y is an integer from 150–300; and


- 30% to 99% of a paraffin wax having a melting point range of from about 30° C. to about 60° C.

wherein the coating blend has a viscosity of less than about 200 centipoises as measured by a cone and plate rheometer at 80° C., a melting point range of about 40° C. to about 50° C., and a solids content of from about 35 to 100% at 40° C. and from about 0 to about 15% at 50° C.; and

- 10 to 80% by weight of a core particle or an aggregate of core particles which are water soluble or water dispersible, or which dissolve, disperse or melt in a temperature range of from about 40° C. to about 50° C.

wherein the particle is stable in an alkaline environment and exhibits a volume % compressibility of 20 or less at 30° C.

a) a mordant having the following general structure:



**5,589,268
MATRIX FOR A HARD COMPOSITE**


Harold E. Kelley, Fallon, Nev.; William E. Silvis, Austin, Tex., and Charles J. Terry, Fallon, Nev., assignors to Kennametal Inc., Latrobe, Pa.

Filed Feb. 1, 1995, Ser. No. 382,468

Int. Cl.⁶ C22C 1/05; 26/00

U.S. Cl. 428—408

13 Claims



1. A diamond composite member comprising:

a support;

a diamond composite affixed to the support;

the diamond composite including a matrix comprising a mass of particles held together by an infiltrant, the mass of particles is formed by heating a powder mixture in the presence of an infiltrant wherein the powder mixture comprises: about 100 weight percent crushed sintered cemented macrocrystalline tungsten carbide particles having a particle size of —120 +400 mesh; and the composition of the crushed sintered cemented macrocrystalline tungsten carbide comprising between about 6 weight percent and about 13 weight percent cobalt and between about 87 weight percent and about 94 weight percent tungsten carbide.

5,589,269

INK RECEPTIVE SHEET

Mahfuza B. Ali, Mendota Heights; Omar Farooq, Woodbury, both of Minn.; Mohammed Iqbal, and Alan G. Miller, both of Austin, Tex., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Continuation-in-part of Ser. No. 204,354, Mar. 11, 1994,

abandoned, which is a continuation-in-part of Ser. No. 30,811,

Mar. 12, 1993, Pat. No. 5,342,688. This application Apr. 25,

1995, Ser. No. 428,276

Int. Cl.⁶ B41M 5/00


U.S. Cl. 428—411.1

10 Claims

1. An ink-receptive sheet comprising a substrate bearing on at least one major surface thereof, an ink-receptive layer comprising an ink receptive polymer and an effective amount of at least one polymeric mordant comprising a guanidine functionality, said mordant being selected from the group consisting of:

wherein X[−] is an anion, and n represents an integer of 2 or greater; and

b) a mordant having the following general structure:



wherein X[−] is an anion, and n represents an integer of 2 or greater.

5,589,270

PROCESSED SUBSTRATE OBTAINED BY A PROCESS FOR EFFECTING SUPPRESSION OF ELECTRIFICATION

Fumio Murai, Tokyo; Yasunori Suzuki, Hachioji; Hideki Tomozawa, Tokyo; Ryuma Takashi, Tokyo; Yoshihiro Saida, Tokyo, and Yoshiaki Ikenoue, Tokyo, all of Japan, assignors to Hitachi, Ltd., and Showa Denko K.K., both of Tokyo, Japan

Continuation of Ser. No. 51,841, Apr. 26, 1993, Pat. No.

5,437,893, which is a continuation of Ser. No. 707,819, May

30, 1991, Pat. No. 5,256,454. This application Jun. 1, 1995,

Ser. No. 456,313

Claims priority, application Japan, May 30, 1990, 2-138467

Int. Cl.⁶ B32B 9/04

U.S. Cl. 428—411.1

14 Claims



1. A method for suppression of electrification which comprises a step of forming on a substrate a water-soluble electrification-suppressing film having an electron conductivity and comprising a polymer resin and a step of irradiating a charged particle beam onto the substrate.

5,589,271


FLUORINE COMPOUND - CONTAINING COMPOSITE MATERIAL AND METHOD OF PREPARING SAME

Nobuatsu Watanabe, 136, Uguisudai, Nagaokakyo-shi, Kyoto; Yong-Bo Chong, #60, Nishijin Ground Heights, 394-1, Jyuyonken-sho, Demizukudaru, Senbon-dori, Kamigyo-ku, Kyoto-shi, Kyoto, and Sowjun Matsumura, Toyonaka, all of Japan, assignors to Nobuatsu Watanabe; Yong-Bo Chong, both of Kyoto, and C. Uyemura & Co., Osaka, all of Japan. Continuation-in-part of Ser. No. 850,427, Mar. 12, 1992, abandoned. This application Apr. 23, 1993, Ser. No. 51,701. Claims priority, application Japan, Mar. 12, 1991, 3-72444; Mar. 12, 1991, 3-72445.

Int. Cl. B32B 27/00

U.S. Cl. 428-421

18 Claims



1. A fluorine compound-containing composite material having a contact angle of 150° or more at the surface consisting essentially of a metal matrix and particles or fibers of a polytetrafluoroethylene oligomer having a number average molecular weight of 10,000 or less dispersed therein, the proportion of the number of fluorine atoms to the number of the total atoms at the surface portion of the composite material being 40% or more, wherein the surface portion is that portion of the composite material which extends from about 20 to about 40 Å into the composite material from the surface of the composite material.

5,589,272

GLAZING

Rüdiger Braun, Friedrichshafen; Manfred Arnold, Meckenbeuren; Thomas Meisel; Werner Scherber, both of Bermatingen; Günther Abersfelder, Sindelfingen, and Stefan Uhl, Stuttgart, all of Germany, assignors to Dornier GmbH, Friedrichshafen, Germany.

Filed Feb. 27, 1995, Ser. No. 394,350

Claims priority, application Germany, Feb. 25, 1994, 44 06 097.1

Int. Cl. B32B 17/06; 17/10; 27/36

U.S. Cl. 428-425.6

15 Claims

1. A transparent glass/plastic material composite pane, comprising at least one transparent plastic pane, at least one glass pane and an adhesion-promoting intermediate layer between the glass pane and the plastic pane, wherein the glass pane is a glass film of a layer thickness of from 300 to 700 µm, and the adhesion-promoting intermediate layer is elastic to thereby equalize different thermal expansions of the plastic pane and the glass pane.

5,589,273

PROCESS AND AGENT FOR THE PRODUCTION OF PURPLE DECORATION

Bernd Dorbath, Alzenau; Norbert Giesecke, Bruchköbel, and Klaus-Dieter Fritzsche, Colditz, all of Germany, assignors to Cerdec Aktiengesellschaft Keramische Farben, Frankfurt am Main, Germany.

Filed Mar. 29, 1995, Ser. No. 412,888

Claims priority, application Germany, Mar. 30, 1994, 44 11 103.7

Int. Cl. B32B 9/00

U.S. Cl. 428-433

34 Claims

1. A process for the production of purple decoration on a storable substrate which comprises applying an agent containing at least one gold compound and a finely divided glass flux onto a substrate to be decorated and firing the resultant substrate at a temperature of 400° to 1,050° C., wherein

the agent to be applied contains at least one gold compound, with the exception of gold oxide, which is decomposed to colloidal gold on firing, and the weight ratio of gold in the gold compound to the glass flux is between 1:10 and 1:2,000.

5,589,274

THERMAL CONTROL COATING


Lyon E. Long, Manhattan Beach, and Joan L. Lum, Redondo Beach, both of Calif., assignors to Hughes Electronics, Los Angeles, Calif.

Filed May 13, 1994, Ser. No. 242,201

Int. Cl. B32B 7/02; 5/16; 15/08

U.S. Cl. 428-215

18 Claims



1. A coated article, consisting essentially of: a substrate having a surface; and a single-layer coating on the surface of the substrate, the coating being sufficiently electrically conductive to dissipate electrostatic charge and having a white color, the coating comprising a silicone polymeric matrix having doped zinc oxide pigment particles distributed therein, the zinc oxide pigment particles being doped with an element that forms shallow donorlike states in the zinc oxide.

5,589,275

COMPOSITE MATERIAL

Hans P. Breitler, Kreuzlingen, Switzerland; Klaus Sommerer, Allensbach, Germany, and Monique Roulin, Aesch, Switzerland, assignors to Alusuisse-Lonza Services AG, Switzerland. PCT No. PCT/CH94/00035, § 371 Date Oct. 5, 1994, § 102(e) Date Oct. 5, 1994, PCT Pub. No. WO94/19184, PCT Pub. Date Sep. 1, 1994.

PCT Filed Feb. 17, 1994, Ser. No. 318,643

Claims priority, application Switzerland, Feb. 25, 1993, 576/93


Int. Cl. B32B 15/08

U.S. Cl. 428-458

9 Claims

1. A blister pack base part for use in freeze drying applications for foodstuffs and pharmaceuticals, comprising: a composite material forming said base, wherein said composite material includes a metal layer with two sides and a plastic

layer on each of said two sides, said metal layer having a thickness of 8 to 80 µm and said plastic layer on each of said sides having a thickness of 20 to 50 µm and containing polyamide-based thermoplastics; and a plurality of compartments formed in said composite material for receiving at least one of said pharmaceuticals and food-stuffs.



5,589,276

THERMALLY TRANSFERABLE PRINTING RIBBONS AND METHODS OF MAKING SAME

Joseph D. Roth, Springboro; Thomas J. Obringer, Vandalia, and Monica N. Lewis, Fairborn, all of Ohio, assignors to NCR Corporation, Dayton, Ohio.

Filed Dec. 20, 1993, Ser. No. 169,935

Int. Cl. B41M 3/12

U.S. Cl. 428-488.1

12 Claims

1. A method of making thermally transferable printing ribbons, comprising the steps of: mixing at least one wax, at least one resin and pigments together to form a mixture of solids; grinding said mixture of solids to form a resultant mixture; emulsifying said resultant mixture to form an emulsified thermally transferable printing media layer formulation; and coating said emulsified thermally transferable printing media layer formulation onto an elongated backing element in a single layer to form said thermally transferable printing ribbons.

8. A thermally transferable printing ribbon fabricated using the method of making thermally transferable printing ribbons in accordance with claim 1.

wherein said superlattice film has a structure in which a plurality of staircase facets which have <100> direction ridge lines and {100} side surfaces stand side by side; wherein said staircase facets of said superlattice film have <110> direction widths of 5 to 30 nm at a top surface thereof; and wherein a dispersion of said 110 direction widths is within ±50%.

5,589,279

WELDABLE BLACK STEEL SHEET

Naoto Yoshimi; Toyofumi Watanabe, and Masaaki Yamashita, all of Tokyo, Japan, assignors to NKK Corporation, Tokyo, Japan.

Continuation of Ser. No. 856,245, Mar. 25, 1992, abandoned.


This application Aug. 15, 1994, Ser. No. 290,675

Claims priority, application Japan, Mar. 29, 1991, 3-089148

Int. Cl. B32B 15/08

U.S. Cl. 428-623

10 Claims



1. A weldable black steel sheet having a surface plated with zinc or zinc alloy, and carrying a chromate film formed on said plated surface and having a coating weight of 10 to 200 mg/m² in terms of metallic chromium, and a black film formed on said chromate film from a composition comprising 100 parts by weight of a water-soluble or water-dispersible thermosetting resin as a base resin, and 'x' parts by weight of a black metal complex of azo dye having at least one hydroxyl group per molecule as a blackening agent, said black film having a thickness of 'y' microns, and 'x' being a value satisfying formulas 1 and 2, while said 'y' is a value satisfying formulas 1 and 3:

$$(x-1)(y-0.2) \geq 7 \quad (1)$$

$$1 < x \leq 200 \quad (2)$$

$$0.2 < y \leq 3 \quad (3)$$

where 'x' represents the proportion, in parts by weight, of said dye against 100 parts by weight of said resin, and 'y' represents the thickness, in microns, of said black film.

5,589,278

MAGNETORESISTIVE THIN-FILM AND DEVICE

Atsushi Kamiyo, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan.

Filed Jul. 5, 1995, Ser. No. 498,389

Claims priority, application Japan, Jul. 5, 1994, 6-1583188

Int. Cl. G11B 5/66

U.S. Cl. 428-611

8 Claims

1. A magnetoresistive thin-film, comprising: a substrate; an (110) oriented epitaxial buffer layer which is formed on said substrate, said buffer layer being made of a body-centered cubic crystalline metal or alloy in which a (110) face is epitaxially grown; and (110) orientation Fe/Cr superlattice film which is formed on said buffer layer, a Fe (110) face and a Cr (110) face of said superlattice film alternately being epitaxially grown;

5,589,280

METAL ON PLASTIC FILMS WITH ADHESION-PROMOTING LAYER

Kevin P. Gibbons, Sunnyvale; Louis C. Lan, Alameda, and Floyd E. Woodard, Los Altos, all of Calif., assignors to Southwall Technologies Inc., Palo Alto, Calif.
Filed Feb. 5, 1993, Ser. No. 14,447

Int. Cl.⁶ C23C 14/00; G02B 1/10; B32B 15/08; 9/00
U.S. Cl. 428—626 16 Claims



1. A metal-on-plastic material comprising a plastic substrate having a surface, a 3 to 200 Å thick, substantially transparent first layer sputter-deposited upon the surface of the substrate comprising metal selected from the group consisting of hafnium, zirconium, tantalum, titanium, niobium, tungsten, vanadium, molybdenum, chromium, nickel and alloys thereof, the metal in said first layer being deposited in the form of metal or substoichiometric oxide, and a second layer sputter-deposited upon the first layer comprising 100–10,000 Å of metal selected from the group consisting of copper, silver, gold, palladium, rhodium, iridium and alloys thereof.

5,589,281

STABILIZED CARBON CLUSTER CONDUCTING OR SUPERCONDUCTING MATERIAL, PROCESS FOR PRODUCING THE SAME, DEVICE USING CARBON CLUSTER, AND PROCESS FOR PRODUCING THE DEVICE

Nobuyuki Okuda; Takashi Uemura; Yoshinobu Ueba; Koji Tada; Kengo Ohkura, and Hirokazu Kugai, all of Osaka, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan

Continuation of Ser. No. 51,345, Apr. 23, 1993, abandoned.
This application Feb. 23, 1995, Ser. No. 393,043

Claims priority, application Japan, May 20, 1992, 4-127027; Aug. 19, 1992, 4-220407; Mar. 4, 1993, 5-043730
Int. Cl.⁶ B32B 9/00

U.S. Cl. 428—688 3 Claims



1. A device comprising a substrate having thereon, (1) a film of a conducting or superconducting carbon cluster comprising (a) C₆₀ or (b) a C₆₀/C₇₀ mixture, each of (a) and (b) being doped with at least one dopant selected from the group consisting of Group I elements, Group II elements, Group III elements, and Group IV elements, covered with (2) a protective film capable of substantially preventing permeation of oxygen and water from the atmosphere, wherein said protective film (2) comprises an insulator having a thermal expansion coefficient ranging from 1×10⁻⁶/°C. to 5×10⁻⁶/°C., wherein said device further comprises (3) a non-doped carbon cluster film between said film (1) and said protective film (2), wherein said insulator is selected from the group consisting of silicon, silicon dioxide, silicon nitride, diamond, amorphous carbon, and boron nitride, and wherein said protective film (2) has a thickness of from 0.1 μm to 10 μm.

5,589,282


MAGNETO-OPTICAL RECORDING MEDIUM

Masayuki Kubogata, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Jul. 21, 1994, Ser. No. 278,225

Claims priority, application Japan, Jul. 22, 1993, 5-181472
Int. Cl.⁶ G11B 5/66

U.S. Cl. 428—694 ML 14 Claims



1. A magneto-optical recording medium having a film of amorphous rare earth-transition metal alloy as a recording layer, comprising: a substrate; a first dielectric layer; a recording layer; a second dielectric layer; and a reflective layer, laminated in this order, wherein a total film thickness of said recording layer is 40 nm or more and less than 80 nm, wherein a thickness of said second dielectric layer is greater than a thickness of said first dielectric layer, and wherein the thickness of said second dielectric layer and the thickness of said first dielectric layer maximize a product of a Kerr rotation angle and a reflectivity of said medium.

5,589,283

SOFT MAGNETIC THIN FILM


Yoh Iwasaki; Yosuke Murakami, and Masao Itabashi, all of Kanagawa, Japan, assignors to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 22,499, Feb. 25, 1993, abandoned.

This application Nov. 3, 1994, Ser. No. 334,353

Claims priority, application Japan, Feb. 29, 1992, 4-079289; Nov. 30, 1992, 4-320988

Int. Cl.⁶ G11B 5/66 7 Claims



1. A soft magnetic thin film which satisfies the following relationship: where the magnetization energy required to magnetize the soft magnetic thin film in any direction in the plane thereof is referred to as total magnetization energy, K_{tot} is the difference between the maximum and minimum values of the total magnetization energy in every direction in the plane, and IK_{tot} is the difference between the maximum and minimum values of the magnetization energy in every direction in the plane

due to crystalline magnetic anisotropy, wherein the total magnetic anisotropy energy value IK_{tot} and the crystalline magnetic anisotropy energy value IK_c is selected to satisfy the following relationship:

$$IK_{tot} < 50 < IK_c (J/m^2)$$

wherein the soft magnetic thin film is made of an FeRuGaSi alloy, and wherein the total Fe and Ru in the FeRuGaSi alloy is of at least 75 atomic %.

5,589,284


ELECTRODES COMPRISING CONDUCTIVE PEROVSKITE-SEED LAYERS FOR PEROVSKITE DIELECTRICS

Scott R. Summerfelt, and Howard R. Beratan, both of Dallas, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 283,468, Aug. 1, 1994, abandoned. This application Jun. 7, 1995, Ser. No. 474,803

Int. Cl.⁶ B32B 18/00

U.S. Cl. 428—697 13 Claims



1. A microelectronic structure comprising: a conductive oxide layer comprising a first metal; a conductive perovskite-seed layer comprising said first metal overlying said conductive oxide layer; and a perovskite dielectric layer overlying said perovskite-seed layer, whereby the similar crystal structure of the perovskite-seed layer improves the crystal quality of the perovskite dielectric layer and minimizes the formation of non-perovskite crystal structures.


5,589,285

ELECTROCHEMICAL APPARATUS AND PROCESS

Thomas L. Cable, Newbury, and Michael A. Petrik, Highland Hts., both of Ohio, assignors to Technology Management, Inc., Cleveland, Ohio

Continuation-in-part of Ser. No. 118,524, Sep. 9, 1993, Pat. No. 5,445,903. This application May 31, 1995, Ser. No. 455,099

Int. Cl.⁶ H01M 8/00 41 Claims



26. A process for utilizing a sulfur bearing fuel in an electrochemical apparatus including: providing a fuel cell having an electrolyte disposed between a fuel electrode and a second electrode, wherein a fuel electrode material interfacial layer is further disposed between the electrolyte and the fuel electrode, and wherein at least one of the interfacial layer and the fuel electrode comprises at least one sulfur tolerant material; introducing a fuel containing at least about 2 ppm sulfur species, at reaction temperature, into said fuel cell; and reacting said fuel.

5,589,286


SOLID ELECTROLYTE FUEL CELL

Tomoo Iwata, Kawasaki, Japan, assignor to Fuji Electric Co., Ltd., Kanagawa, Japan

Filed Jul. 20, 1994, Ser. No. 278,070

Claims priority, application Japan, Jul. 21, 1993, 5-179486
Int. Cl.⁶ H01M 8/24; 8/12

U.S. Cl. 429—34 37 Claims



1. A planar solid electrolyte fuel cell comprising: a stack casing having a stack reaction chamber therein; a plurality of vertically oriented electrode/solid electrolyte separator assemblies arranged in a parallel orientation in the stack reaction chamber of said stack casing, each of said assemblies comprising: a cell substrate serving as a first electrode, said cell substrate being a flat box with first and second, oppositely located vertical main surfaces during operation of the fuel cell, and including a plurality of reaction gas flow ports located therein, said gas flow ports being parallel to the main surfaces, and feeding a first reactant gas in a uniform direction; a solid electrolyte provided on the first main surface of said cell substrate; a second electrode provided on said solid electrolyte, and a separator provided on the second main surface of said cell substrate; and an electroconductive felt interposed between adjacent ones of said assemblies, said electroconductive felt having a plurality of cavities through which a second gas flows.

5,589,287

MOLTEN CARBONATE FUEL CELL

Kazubito Hatoh, Daitou; Junji Niikura, Hirakata; Eiichi Yasumoto, Katano, and Takaharu Gamou, Fujiidera, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan

Filed Oct. 5, 1994, Ser. No. 318,916

Claims priority, application Japan, Oct. 18, 1993, 5-260125; Feb. 9, 1994, 6-015524

Int. Cl.⁶ H01M 8/14

U.S. Cl. 429—41 6 Claims

1. A molten carbonate fuel cell comprising: an anode and a cathode which are both porous gas-diffusion electrodes, and an electrolyte making contact with both the electrodes, wherein said cathode comprises a metal oxide represented by the formula $Li_xNi_{1-x}O$ ($0.05 \leq x < 0.5$), and at least one of said cathode and electrolyte contains an alkali earth metal carbonate.

5,589,288


CORDLESS POWER TOOL HAVING A PUSH BUTTON BATTERY RELEASE ARRANGEMENT

Richard R. Coulson, Toronto; Eric D'Amario, Woodbridge, and Jerry Moscovitch, Toronto, all of Canada, assignors to Black & Decker, Inc., Newark, Del.

Filed Jul. 31, 1995, Ser. No. 509,076
Int. Cl.⁶ H01M 2/10

U.S. Cl. 429—96

18 Claims



1. A battery pack release arrangement for a power tool having a housing and at least one battery pack releasably mounted within the housing, the release arrangement comprising:

- an actuation member for releasably latching the at least one battery pack in an operative position, said actuation member being moveable between a latching position and a release position, said actuation member integrally formed to include a button portion and a latching portion, said latching portion adapted to be in interfering relation with the at least one battery pack when said actuation member is in said latching position; and
- a camming portion disposed adjacent to said latching portion of said actuation member, said camming portion adapted to resiliently deflect said engaging portion out interfering relation with the at least one battery pack when said actuation member is moved from said latching position to said release position.

5,589,289


CARBON ELECTRODE MATERIALS FOR ELECTROCHEMICAL CELLS AND METHOD OF MAKING SAME

Jinshan Zhang, Duluth, and Anaba A. Anani, Norcross, both of Ga., assignors to Motorola, Inc., Schaumburg, Ill.


Filed Sep. 27, 1995, Ser. No. 534,427
Int. Cl.⁶ H01M 6/00

U.S. Cl. 429—122

4 Claims



1. A rechargeable electrochemical cell comprising:
a lithium intercalation cathode; an electrolyte; and an anode fabricated of an amorphous carbon material resulting from the condensation and reduction of a multi-functional organic monomer having the structure:



wherein R_1 , R_2 , and R_3 are all selected from the group consisting of carboxylic acids of eight carbons or less, carboxylic esters of eight carbons or less, alcohols of eight carbons or less, carboxylic anhydrides of eight carbons or less, amines, and combinations thereof, and wherein at least one of R_1 , R_2 , and R_3 is different than the others.

5,589,290

BATTERY BOX WITH FLUID FLOW CHANNELS TO MAINTAIN PROPER TEMPERATURE

Rainer Klink, Kernen; Johann German, and Wolfgang Warthmann, both of Weinstadt, all of Germany, assignors to Deutsche Automobilgesellschaft mbH, Germany


Filed Mar. 6, 1995, Ser. No. 400,105

Claims priority, application Germany, Mar. 4, 1994, 44 07 156.6

Int. Cl.⁶ H01M 2/10

U.S. Cl. 429—99

11 Claims



1. A battery box having a plurality of orientation independent electrochemical cells, of the type in which said cells are arranged into at least one cell group, with flow channels formed between adjacent cells within said cell groups, through which a fluid can flow, a distributor channel being arranged in a first region of said box and coupled in fluid communication with said fluid flow channels at an inlet end thereof, and a collector channel being arranged in a second region of said box opposite said first region and coupled in fluid communication at an outlet end thereof, wherein:

in an installed orientation of said battery box, said cells are arranged in a horizontal orientation having the smallest dimension thereof in a vertical direction;
cells within a cell group are stacked one above the other;
each cell group has associated therewith inlet and outlet flow channels which extend transversely with respect to said battery box;
the transverse inlet flow channel is connected in fluid communication with the distributor channel and to the flow channels of a cell group associated therewith; and
the transverse outlet flow channel being connected in fluid communication with the collecting channels and the flow channels of an associated cell group.

5,589,291

STABILIZED RECHARGEABLE CELL IN MSE

Richard T. Carlin, Colorado Springs, Colo., and Joan Fuller, Raleigh, N.C., assignors to The United States of America as represented by the Secretary of the Air Force, Washington, D.C.


Division of Ser. No. 494,425, Jun. 26, 1995. This application

Feb. 22, 1996, Ser. No. 613,746

Int. Cl.⁶ H01M 10/36

U.S. Cl. 429—103

5 Claims



1. A stabilized rechargeable cell comprising,
a) an MSE melt of $\text{LiBF}_4/\text{EMIBF}_4$
b) a lithium metal negative electrode and
c) a lithium salt protective film deposited on the lithium metal surface of said electrode, which film is permeable to Li^+ ions.

5,589,292

PORTABLE BOOSTER BATTERY

Luc Rozon, St-Luc, Canada, assignor to Booster Pac International Corporation, St-Jean-sur-Richelieu, Canada


Filed Aug. 9, 1994, Ser. No. 287,840

Claims priority, application Canada, Oct. 25, 1993, 2109166

Int. Cl.⁶ H01M 2/06

U.S. Cl. 429—170

20 Claims



1. A portable automobile booster battery comprising:
a sealed non-spillable battery having a positive terminal and a negative terminal;
a housing surrounding said battery and covering said terminals of said battery;
a first cable with one end permanently connected to said positive terminal of said battery, said first cable extending outside said housing;
a second cable with one end permanently connected to said negative terminal of said battery, said second cable extending outside said housing;
first clamp means connected to another end of said first cable and for electrically connecting said first cable to a positive terminal of an automobile battery;
second clamp means connected to another end of said second cable and for electrically connecting said second cable to one of a negative terminal of said automobile battery and a ground of an automobile;

a first holster means connected to an outside of said housing, and for holding said first clamp means outside of said housing;
a second holster means connected to an outside of said housing, and for holding said second clamp mean outside said housing.

5,589,293

SEALED GALVANIC CELL WITH INJECTION MOLDED TOP

Peter J. Pope, Balcumbe, and Richard B. Willis-Owen, West Sussex, both of Great Britain, assignors to Duracell Inc., Bethel, Conn.

PCT No. PCT/US89/01365, § 371 Date Dec. 14, 1990, § 102(e) Date Dec. 14, 1990, PCT Pub. No. WO89/11164, PCT Pub. Date Nov. 16, 1989


PCT Filed Mar. 31, 1989, Ser. No. 623,701

Claims priority, application United Kingdom, May 5, 1988, 8810651

Int. Cl.⁶ H01M 2/08

U.S. Cl. 429—172

7 Claims



1. A top for sealing and insulating the open end of a cylindrical container subject to internal pressure variations, said top comprising means to support the top and a sealing and insulating member, said sealing and insulating member comprising a central platform having an axially extending boss, with said platform having a plurality of vent membranes integrally formed therein, wherein each vent is designed to vent at approximately the same pressure, said membranes in combination comprising between at least about 30% of the surface area of said platform exclusive of said boss portion, and means to strengthen the top, wherein said platform is disc shaped and said vent membranes comprise up to about 50% of the platform surface area and are equidistantly spaced around the surface of said disc and are separated from each other by thicker, non-venting portions of said platform, wherein said means to strengthen the top comprises vertically extending stiffening ribs which extend radially from the central boss member, and each rib being integral with the upper surface of the platform at the juncture of a vent membrane and an adjacent non-venting portion thereof, and wherein said sealing and insulating member further comprises a downwardly depending frustoconical member attached to the outer circumference of the platform; an annular bottom member attached at its inner circumference to the lower end of the frustoconical member; and an upwardly extending outer wall attached to the outer circumference of the annular bottom member.

5,589,294

SIDE WALL ELECTRICITY BATTERY TERMINAL

Bernard N. Spiegelberg, Germantown, and Mark E. Sauter, Shorewood, both of Wis., assignors to Tulip Corporation, Milwaukee, Wis.


Continuation of Ser. No. 199,100, Feb. 22, 1994, Pat. No. 5,425,170, which is a division of Ser. No. 79,153, Jun. 17, 1993, Pat. No. 5,422,202. This application Jun. 2, 1995, Ser. No. 459,783

Int. Cl.⁶ H01M 2/30

U.S. Cl. 429—178

2 Claims

1. A cold formed side wall battery terminal comprising a cylindrical lead slug having a cavity at one end, a nut positioned in said cavity, a spline ring formed around the other end of the slug and a set of rings formed around the perimeter of said slug to seal the



terminal in the side wall of the battery wherein said nut is encapsulated in said terminal when said slug is cold formed to shape the terminal.

5,589,295

THIN FILM POLYMERIC GEL ELECTROLYTES

Dora K. Derzon, 1554 Rosalba St. NE., Albuquerque, Bernalillo County, N.M. 87112; Charles Arnold, Jr., 3436 Tahoe, NE., Albuquerque, Bernalillo County, N.M. 87111, and Frank M. Delnick, 9700 Fleming Rd., Dexter, Mich. 48130
Filed Dec. 6, 1995, Ser. No. 568,029
Int. Cl.⁶ H01M 10/08

U.S. Cl. 429—190

6 Claims

1. A hybrid thin film electrolyte, comprising: in combination, a polymer capable of forming a gel, said polymer gel having a solution retained therein, said solution comprising ethylene carbonate, at least one organonitrile and at least one lithium salt having a polarizable anion and capable of dissolving in said solution.

5,589,296

FIBROUS SOLID ELECTROLYTE, CELL USING THE ELECTROLYTE AND PROCESS FOR PRODUCING THE ELECTROLYTE

Kazuya Iwamoto, Sakai; Noboru Aotani, Uji; Kazunori Takada, Osaka, and Shigeo Kondo, Hirakata, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Mar. 3, 1994, Ser. No. 205,109

Claims priority, application Japan, Mar. 22, 1993, 5-061640
Int. Cl.⁶ H01M 6/18

U.S. Cl. 429—191

28 Claims

1. A fibrous solid electrolyte for use in solid electro-chemical elements, which comprises a fibrous ion conductive glassy solid electrolyte, whose ion conductive species is selected from the group consisting of copper and proton.

5,589,297

LITHIUM SECONDARY CELL

Keiji Koga; Hltoshi Arai; Tsuneo Kagotani, and Yousuke Miyaki, all of Nagano, Japan, assignors to TDK Corporation, Tokyo, Japan

Filed Dec. 29, 1994, Ser. No. 365,745

Claims priority, application Japan, Dec. 29, 1993, 5-353671; Dec. 29, 1993, 5-353672


Int. Cl.⁶ H01M 4/36

U.S. Cl. 429—212

10 Claims

1. A secondary lithium cell comprising a negative electrode, a positive electrode and an electrolyte of a non-aqueous electrolyte solution containing a lithium salt, wherein

at least one of said negative electrode and said positive electrode includes an electrode layer disposed on a current collector through an underlying layer, and



said underlying layer being formed of a composition comprising from 10 to 200 parts by weight of carbon black having a DBP oil absorption of 100 to 500 cc/100 g, 100 parts by weight of a thermosetting polymer containing a fluorinated polymer and from 1 to 10 parts by weight of a crosslinking agent, said composition being a thermoset.

5,589,298

ELECTROCHEMICAL DEVICES COMPRISING LITHIUM NITRIDE-METAL COMPOUNDS IN AT LEAST ONE OF A PAIR OF ELECTRODES


Kazunori Takada, Osaka; Shigeo Kondo, Hirakata; Osamu Yamamoto, Ichinomiya, and Motoaki Nishijima, Mie-ken, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Sep. 8, 1994, Ser. No. 302,300

Claims priority, application Japan, Sep. 9, 1993, 5-224281
Int. Cl.⁶ H01M 4/02

U.S. Cl. 429—218

66 Claims



1. A lithium secondary cell which comprises a cell unit including a pair of electrodes, a separator provided between said pair of electrodes, and a liquid electrolyte impregnated in said separator and capable of lithium ion concentration, wherein at least one of said pair of electrodes comprises a lithium nitride-metal compound which contains at least one metal selected from the group consisting of Co, Cu, Cr, V, Sr, Ni, W and Nb.

5,589,299

CARBON ELECTRODE FOR NONAQUEOUS SECONDARY BATTERY, FABRICATION METHOD FOR THE SAME AND NONAQUEOUS SECONDARY BATTERY USING THE SAME

Kazuo Yamada, Kitakatsuragi-gun; Takehito Mitate, Yamato-takada; Tetsuya Yoneda, Nabari, and Naoto Nishimura, Kitakatsuragi-gun, all of Japan, assignors to Sharp Kabushiki Kaisha, Japan

Filed Jun. 6, 1995, Ser. No. 469,906


Claims priority, application Japan, Jul. 21, 1994, 6-169333; Mar. 28, 1995, 7-070058

Int. Cl.⁶ H01M 4/66

U.S. Cl. 429—218

10 Claims

1. A carbon electrode for a nonaqueous secondary battery comprising a conductive substrate doubling as a collector, the conductive substrate having a portion with carbon formed directly thereon and a portion where carbon is not formed, wherein the conductive substrate comprises a metal or a compound thereof having a catalytic action with respect to graphitization of a carbon material



at the portions where carbon is formed directly thereon and comprises a metal or a compound thereof having no catalytic action with respect to graphitization of the carbon material at the portions where carbon is not formed.

5,589,300

SMALL PARTICLE ELECTRODES BY AEROSOL PROCESS

Denis G. Fauteux, Acton; Arthur A. Massucco, Natick, and Ronnie D. Wilkins, Melrose, all of Mass., assignors to Arthur D. Little, Inc., Cambridge, Mass.

Continuation of Ser. No. 126,918, Sep. 27, 1993, abandoned.

This application Jun. 6, 1995, Ser. No. 447,137

Int. Cl.⁶ H01M 4/48

U.S. Cl. 429—218

42 Claims



1. A method for preparing an electrode, comprising the steps of: generating droplets of a solution of a precursor material in a carrier liquid, said precursor material capable of being converted into an active material of an electrode; removing at least a portion of said carrier liquid from said droplet to form precursor particles; converting said precursor particles into particles of said active electrode material, wherein parameters for the conversion of the droplet into an active electrode material are controlled to obtain a predetermined particle configuration wherein the step of generating droplets of a solution of a precursor material in a carrier liquid comprises using a carrier liquid comprising a solvent and a diluent liquid.

5,589,301

BATTERY ELECTRODE SUBSTRATES AND METHOD OF MAKING SAME

Robert J. Edgington, Granger; James A. Stepro; Harold J. Wissell, both of Mishawaka, all of Ind., and Scott A. Lundberg, Niles, Mich., assignors to National-Standard Company, Niles, Mich.

Continuation of Ser. No. 979,830, Nov. 20, 1992, abandoned.


This application Oct. 5, 1994, Ser. No. 318,489

Int. Cl.⁶ H01M 4/72

U.S. Cl. 429—234

36 Claims

1. A three-dimensional substrate material for use in constructing battery electrodes comprising: a sintered matrix material selected from the group of elements consisting of reticulated metal foams, conductive fibers and



metal powder compacts, said matrix material having at least one flexible bonded open surface structure, and a flexible open surface matrix retaining means bonded to at least one surface of said sintered matrix material, with said retaining means structurally arranged to permit loading of active chemical material through said retaining means into said sintered matrix material and to retain said sintered matrix material substantially within the formed surface of said at least one surface of said matrix material during subsequent spiral-winding of the sintered matrix material.

5,589,302

BATTERY SEPARATOR AND BATTERY CONTAINING SAME

Peter J. Degen, Huntington, and Joseph Y. Lee, South Setauket, both of N.Y., assignors to Pall Corporation, East Hills, N.Y.

Filed Nov. 4, 1994, Ser. No. 334,756

Int. Cl.⁶ H01M 2/16

U.S. Cl. 429—250

32 Claims

1. A battery separator comprising (a) a nonwoven web of fibers having a mean diameter of about 15 μ m or less and (b) a graft polymerized monomer on the surface of said nonwoven web which renders said nonwoven web spontaneously wettable by an alkaline electrolyte, wherein said nonwoven web comprises at least about 60 wt. % of a first polyolefin having a first melting temperature and no more than about 40 wt. % of a second polyolefin having a second melting temperature which is lower than said first melting temperature, said nonwoven web has been subjected to a temperature between said first and second melting temperatures, said nonwoven web has a thickness of at least about 50 μ m, and said monomer is selected from the group consisting of vinyl sulfonic acid, vinyl phosphonic acid, and acrylic and methacrylic acid monomers and hydroxyl functional derivatives thereof.

5,589,303

SELF-ALIGNED OPAQUE REGIONS FOR ATTENUATING PHASE-SHIFTING MASKS


John J. DeMarco, East Brunswick, N.J.; Taebo Kook, Lower Macungie Township, Lehigh County, Pa., and Robert L. Kostelak, Jr., Bernardsville, N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Dec. 30, 1994, Ser. No. 366,952

Int. Cl.⁶ G03F 9/00

U.S. Cl. 430—5

18 Claims



1. A method of making an optical lithographic mask comprising the steps of:

(a) providing a substrate having a top surface upon which is located a first layer, the first layer being partially transparent to optical radiation of a wavelength λ ;

(b) depositing a second layer chemically different from the first layer on the top surface of the first layer, the second layer

being sufficiently thick so as to be, in combination with the first layer, opaque to the optical radiation of the wavelength λ ;

(c) forming a first patterned resist layer on the top surface of the second layer;

(d) etching the first and second layers, using the first patterned resist layer as a protective layer against etching of the second layer and using the first patterned resist layer or the resulting patterned second material layer as a protective mask against etching the first layer, whereby a first patterned opaque layer is formed having spaced-apart areas each having a top surface bounded by at least one sidewall;

(e) forming a second patterned resist layer that coats the entire top surfaces of, and the entire spaces between, at least some, but not all, of the spaced-apart areas; and

(f) etching only the patterned second layer using the second patterned resist layer as a protective mask against etching the patterned second layer, while using exposed portions of the first patterned opaque layer as a protective mask against etching the patterned first layer, whereby a second patterned opaque layer and a patterned partially transparent layer are formed, the second patterned opaque layer having a first pattern that includes at least an alignment indicator that is self-aligned with a second pattern of the partially transparent layer.


5,589,304

PHOTOMASK COMPRISING A HOLDING FRAME AND REINFORCING MEMBER WITH A CERAMIC OXIDE BOND

Keiko Chiba, Isehara, and Takeshi Miyachi, Zama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Mar. 16, 1995, Ser. No. 404,959
Claims priority, application Japan, Mar. 16, 1994, 6-046219
Int. Cl.⁶ G03F 9/00

U.S. Cl. 430—5

8 Claims



1. A mask, comprising:
a membrane on which a pattern is formed or to be formed;
a holding frame for holding said membrane; and
a reinforcing member for reinforcing said holding frame;
wherein said reinforcing member comprises ceramics and wherein said reinforcing member and said holding frame are bonded to each other through a film oxide of the ceramics.

5,589,305

METHOD OF FABRICATING A RETICLE

Yoko Tomofuji, Makoto Nakase, both of Tokyo, Japan; Takashi Sato, Fishkill, N.Y.; Hiroaki Hazama; Haruki Komano, both of Kanagawa, Japan, and Shinichi Ito, Kanagawa, Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan
Division of Ser. No. 192,091, Feb. 4, 1994, abandoned, and a continuation-in-part of Ser. No. 798,721, Nov. 29, 1991, abandoned. This application May 30, 1995, Ser. No. 453,465
Claims priority, application Japan, Nov. 29, 1990, 2-331308; Jul. 3, 1991, 3-163131; Nov. 11, 1991, 3-294540; Nov. 13, 1991, 3-297461

Int. Cl.⁶ G03F 9/00

U.S. Cl. 430—5

12 Claims

1. A method of fabricating a reticle comprising the step of forming on a light-transmissible substrate a mask pattern of a semi-transparent film which causes length of an optical path for a light beam passing therethrough to be different from length of an optical path for a light beam passing through the light-

transmissible substrate by a predetermined amount, wherein the step of forming a mask pattern comprises the steps of:
determining ranges of refractive index n and extinction coefficient k of the semi-transparent film within which transmissivity ratio T and a phase difference ϕ between the semi-transparent film and air that has the same thickness of the semi-transparent film fall within ranges necessary to obtain desired resolution and depth of focus;
obtaining relationship in the form of a curved line between the refractive index n and the extinction coefficient k by changing conditions for formation of the mask pattern;
selecting values of the refractive index and the extinction coefficient from the range thus determined, and determining the conditions for formation of the mask pattern such that the refractive index and the extinction coefficient become the selected values; and
forming a mask pattern based on the conditions for formation of the mask pattern.

5,589,306


PHOTOSENSITIVE RESIN COMPOSITION FOR PRODUCING A RELIEF PRINTING PLATE

Masahiko Takahashi, and Shusaku Tabata, both of Fuji, Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan
Continuation of Ser. No. 641,762, Jan. 16, 1991, abandoned, which is a division of Ser. No. 326,902, Mar. 21, 1989, abandoned. This application Dec. 2, 1992, Ser. No. 985,233
Claims priority, application Japan, Mar. 26, 1988, 63-072926
Int. Cl.⁶ G03C 3/00; G03F 7/035


U.S. Cl. 430—18

2 Claims

1. A corrugated board printing plate having a thickness of from 3 mm to 10 mm produced by a method comprising the steps of:
(a) providing a photosensitive resin layer, then in either order for exposure;
(b) subjecting one surface of said resin layer to relief exposure through a transparency having a transmitting pattern; and
(c) subjecting the other surface of said resin layer to back exposure;
(d) subjecting the resultant exposed resin layer to development to obtain a corrugated board printing plate;
(e) washing said corrugated board printing plate; and
(f) drying the washed corrugated board printing plate;
wherein said photosensitive resin layer is composed of a photosensitive resin composition comprising:
(A) from 5.0 to 98.0% by weight, based on the total weight of components (A), (B), (C), and (D), of an ethylenically unsaturated polyurethane prepolymer having a number average molecular weight of 5,000 to 100,000;
(B) from 1.0 to 94.0% by weight, based on the total weight of components (A), (B), (C), and (D), of an ethylenically unsaturated monomer having a number average molecular weight of less than 2,000;
(C) from 0.05 to 10.0% by weight, based on the total weight of components (A), (B), (C), and (D), of a hindered amine having a piperidine ring represented by the formula:



(D) from 0.002 to 10.0% by weight, based on the total weight of components (A), (B), (C), and (D), of a photopolymerization initiator,
wherein at least one component selected from the group consisting of component (A) and component (B) contains in its structure a segment containing ether bonds which is represented by the formula:



wherein R^1 represents a hydrocarbon group having from 2 to 20 carbon atoms and n is an integer of 3 or more, said segment being present in an amount of 50% by weight or more, based on the total weight of components (A) and (B), and
wherein the weight ratio of said component (A) to said component (B) is from 80.0/19.0 to 30.0/70.0.

5,589,307

PRINTING PLATE AND PROCESS FOR PREPARING THE SAME

Satoshi Takeuchi, Tokyo-to, Japan, assignor to Dai Nippon Printing Co., Ltd., Japan

Filed May 26, 1995, Ser. No. 452,060

Claims priority, application Japan, May 26, 1994, 6-136345; Aug. 11, 1994, 6-209389; Oct. 6, 1994, 6-268369

Int. Cl.⁶ G03G 13/26

U.S. Cl. 430—49

18 Claims

1. A process for preparing a dry lithographic printing plate, comprising the steps of:
providing an N-type photoconductor layer having an optical memory property on the surface of a substrate having an electrical conductivity at least in its surface to form an N-type photoconductor substrate;
subjecting the N-type photoconductor layer to a desired pattern-wise exposure by at least one of batch exposure and photo-drawing exposure to render exposed areas electrically conductive;
immersing the N-type photoconductor substrate in an aqueous electrodeposit bath containing an ionic organic polymer having oil-repellent properties after electrodeposition to electrodeposit said ionic organic polymer contained in the electrodeposit bath to form an oil-repellent electrodeposit layer which is unresponsive to a printing ink; and
washing and drying the electrodeposit substrate to obtain a dry lithographic printing plate.

5,589,308

METHOD FOR PREPARATION OF PRINTING PLATE BY ELECTROPHOTOGRAPHIC PROCESS

Eiichi Kato; Makoto Momota, and Hiroyuki Ohishi, all of Shizuoka, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed Jun. 20, 1995, Ser. No. 492,701

Claims priority, application Japan, Jun. 21, 1994, 6-160779
Int. Cl.⁶ G03G 13/32

U.S. Cl. 430—49

18 Claims

1. A method for preparation of a printing plate by an electrophotographic process comprising forming a peelable transfer layer capable of being removed upon a chemical reaction treatment on a surface of an electrophotographic light-sensitive element, forming a toner image by an electrophotographic process on the transfer layer, heat-transferring the toner image together with the transfer layer onto a receiving material having a surface capable of providing a hydrophilic surface suitable for lithographic printing at the time of printing, and removing the transfer layer on the receiving material upon the chemical reaction treatment, wherein the transfer layer has a stratified structure composed of a first transfer layer (T_1) which is in contact with the surface of electrophotographic light-sensitive element and is formed by an electrodeposit coating method using thermoplastic resin grains (AL) each containing a resin (A_1) having a glass transition point of from 10° C. to 140° C. or a softening point of from 35° C. to 180° C. and a resin (A_2) having a glass transition point of not more than 45° C. or a softening point of not more than 60° C. wherein the glass transition point or softening point of resin (A_1) is at least 2° C. higher than

that of resin (A_2) and a second transfer layer (T_2) provided thereon mainly containing a resin (A_2).

5,589,309

ELECTROPHOTOGRAPHIC PHOTORECEPTOR CONTAINING PERYLENES

Tomoko Suzuki; Akira Kinoshita; Hirofumi Hayata, and Tomoo Sakimura, all of Hino, Japan, assignors to Konica Corporation, Tokyo, Japan


Filed Jul. 17, 1995, Ser. No. 503,125

Claims priority, application Japan, Jul. 20, 1994, 6-168005
Int. Cl.⁶ G03G 5/06; 5/047

U.S. Cl. 430—59


3 Claims

1. An electrophotographic photoreceptor comprising a conductive support and provided thereon an intermediate layer, a carrier generation layer and a carrier transportation layer containing a carrier transportation material, wherein a first perylene compound represented by Formula A and a second perylene compound represented by Formula B are mixed in said carrier generation layer:



Formula A

wherein Z represents a substituted or unsubstituted divalent aromatic hydrocarbon group or a substituted or unsubstituted divalent heterocyclic group; and R represents an alkyl group, an aralkyl group, a hydroxyalkyl group, an alkoxyalkyl group, an aromatic hydrocarbon group or a heterocyclic group;



Formula B

and wherein a weight ratio of said first perylene compound represented by Formula A to said second perylene compound represented by Formula B is a ratio of 9/1 to 999/1.

5,589,310

METHOD FOR PRODUCING TONER FOR DEVELOPING ELECTROSTATIC IMAGES

Mikio Uno; Takashi Shintaku, and Takatsugu Takehara, all of Kanagawa, Japan, assignors to Mitsubishi Chemical Corporation, Tokyo, Japan



Filed Jul. 6, 1995, Ser. No. 499,005

Claims priority, application Japan, Jul. 29, 1994, 6-178352
Int. Cl.⁶ G03G 9/097

U.S. Cl. 430—106

18 Claims

1. A method for producing a toner for developing electrostatic images, which comprises the steps of kneading a mixture of raw materials comprising at least a resin and a colorant, cooling the kneaded mixture, pulverizing the cooled mixture, classifying the pulverized mixture, and feeding a fine powder separated by the classification step to a melt of the mixture of raw materials in the middle of the kneading step.



wherein l , m , and n are integers, $l=2$ to 10 , $m=0$ to 5 , $n=0$ to 5 , and $l+m+n=2$ to 20 ; n^1 to n^7 are integers from 0 to 10 , $n^1+n^2+n^3+\dots+n^7=2$ to 20 ;

X^- is an anion selected from the group consisting of chloride, bromide, sulfate, hydrogensulfate, phosphate, phosphite, tetrafluoroborate, hexafluorophosphate, chloride-zinc chloride, trifluoroacetate, oxalate, alkylsulfonate having 1 to 8 carbon atoms, trifluoromethane sulfonate, arylsulfonate having 6 to 24 carbon atoms and 2 -hydroxy- 4 -methoxybenzophenone- 5 -sulfonate;

G^1 is selected from the group consisting of chlorine, methoxy, ethoxy, propoxy, butoxy, octyloxy, benzyloxy, phenethyloxy, methylbenzyloxy, carboxymethyloxy, carboxyethyloxy, car-

boxypropyloxy, methoxymethyloxy, 2 -tetrahydropyranyloxy, allyloxy, crotyloxy, sulfoethyloxy, sulfopropyloxy, acetoxy, propionyloxy, butyryloxy, hexanoyloxy, chloroacetyloxy, oxaloxy, carboxyethylcarbonyloxy, carboxypropylcarbonyloxy, and N -phenylcarbamoyloxy;

G^2 is selected from the group consisting of hydroxyl group and the same as G^1 , provided however, that the number of hydroxyl groups represented by G^2 in the diazo compound of Formula (II) is 0 to 10 , and the number of the same groups as G^1 is 2 to 20 ;

Q is a polyvalent group derived from the following compounds from which $(1+m+n)$ hydrogen atoms are removed by reacting with $(1+m+n)$ molecules of epichlorohydrin: compounds selected from the group consisting of ammonia, primary alkylamines having 1 to 20 carbon atoms, polyamines of 4 to 30 carbon atoms having two or more secondary amino groups in the molecule, dihalogenoaniline, trihalogenoaniline, trialkylaniline, $4,4'$ -diaminodiphenylsulfone, aniline-formaldehyde condensate, ethanolamine, diethanolamine, glycine, β -alanine, 6 -aminohexanoic acid, p -aminobenzoic acid, anthranilic acid, sulfanilic acid, taurine, ethylenediamine, xylylenediamine, ethyleneurea, hydantoin, isocyanuric acid; ethylene glycol, propylene glycol, butylene glycol, xylene glycol, glycerin, sorbitol, sorbitan, pentaerythritol, tris(2-hydroxyethyl) isocyanurate; $4,4'$ -dihydroxydiphenylmethane, bisphenol A, tetrabromobisphenol A, bis(4-hydroxyphenyl)acetic acid, $2,2$ -bis(4-hydroxyphenyl)propionic acid, $4,4'$ -dihydroxydiphenyl ether, $4,4'$ -dihydroxydiphenyl sulfone, $1,1,2,2$ -tetra(4-hydroxyphenyl)ethane, phenol-novolac resin, cresol-novolac resin, catechol, resorcinol, hydroquinone, pyrogallol, gallic acid, dihydroxynaphthalene; dimercaptoalkanes having 2 to 18 carbon atoms, dimercaptoaralkanes having 8 to 20 carbon atoms, dimercaptoethers having 4 to 20 carbon atoms, dimercaptobenzene; dialkyl malonate, N,N' -diacetoacetylalkylenediamine, N,N' -diacetoacetylarylenediamine, N,N' -diacetoacetylalkylenediamine, diethylenetriamine, triethylenetetramine; aminophenol, hydroxythiophenol, aminothiophenol, and N -acetoacetylthiophenol;

Q_1 is a monovalent group derived from the following compounds reacting with one molecule of epichlorohydrin: compounds selected from the group consisting of secondary amines of 2 to 30 carbon atoms having the same or two different alkyls, aralkyls, or aryls, N -methyltaurine, N -methylanthranilic acid, and N -ethylsulfanilic acid; alkyl alcohols having 1 to 20 carbon atoms, aralkyl alcohols having 7 to 30 carbon atoms, phenol and alkyl phenols, p -hydroxybenzoic acid, salicylic acid, and hydroxybenzenesulfonic acid; alkyl or aralkyl mercaptans having 1 to 30 carbon atoms, thiophenol and alkyl thiophenol; 2 -mercaptoethanesulfonic acid, mercaptoacetic acid, mercaptopropionic acid, mercaptosuccinic acid, and mercaptobenzoic acid; alkylcyanoacetate, dialkyl esters of alkylmalonic acid, acetoacetylarylamide, hydrogen halides, phosphonic acid, phosphinic acid, and thiosulfate;


Q_2^1 to Q_2^7 and Q_3 are divalent groups derived from the following compounds reacting with two molecules of epichlorohydrin: Compounds selected from the group consisting of primary alkylamines having 1 to 12 carbon atoms, aralkylamines having 7 to 20 carbon atoms, dihalogenoanilines, trihalogenoanilines, trialkylanilines, ethanolamines, glycine, β -alanine, 6 -aminohexanoic acid, p -aminobenzoic acid, anthranilic acid, sulfanilic acid, taurine, ethyleneurea, hydantoin, alkylene glycols, aralkylene glycols, $4,4'$ -dihydroxydiphenylmethane, bis(4-hydroxyphenyl)acetic acid, $2,2$ -bis(4-hydroxyphenyl)propionic acid, bisphenol A, tetrabromobisphenol A, $4,4'$ -dihydroxydiphenyl ether, $4,4'$ -dihydroxydiphenyl sulfone, catechol, resorcinol, hydroquinone, dihydroxynaphthalenes; dimercaptoalkanes having 2 to 12 carbon atoms, dimercaptoaralkanes having 8 to 20 carbon atoms, dimercaptoethers having 7 to 20 carbon atoms, dimercaptobenzene; dialkyl malonates, N,N' -diacetoacetylalkylenediamines, N,N' -diacetoacetylarylenediamines, N,N' -diacetoacetylalkylene-

diamines, N -alkylaminophenols, hydroxythiophenol, N -alkylaminothiophenols, and N -acetoacetylthiophenol;

R^1 and R^2 are each selected from the group consisting of hydrogen, alkyl having 1 to 8 carbon atoms and alkoxy having 1 to 8 carbon atoms;

R^3 is selected from the group consisting of alkyl or substituted alkyl having 1 to 8 carbon atoms, aralkyl or substituted aralkyl having 7 to 14 carbon atoms, and $Q_1-CH_2-CHG^2-CH_2-$;

R^4 is selected from the group consisting of Q_1 and G^2 , or is the following group:



wherein X^- , R^1 , R^2 , and R^3 denote the same groups as above;

(b) an oleophilic resinous binder which comprises a high molecular weight organic compound containing at least one of an aliphatic or aromatic hydroxyl group, carboxyl group, sulfo group, carbamoyl group or a sulfonamide group; and

(c) at least one additive selected from the group consisting of dyes, surface active agents, plasticizers, oleophilic compounds, and stabilizers;

said composition being coated on a base material selected from the group consisting of an aluminum plate, a sheet of paper, a plastic film, a glass plate, and a screen mesh comprising a synthetic resin or stainless steel.

5,589,316

DYES AND DYE-DONOR ELEMENTS FOR THERMAL DYE TRANSFER RECORDING

Luc Vanmaele, Lochristi, Belgium, assignor to Agfa-Gevaert N.V., Mortsel, Belgium

Filed Sep. 11, 1995, Ser. No. 526,848


Claims priority, application European Pat. Off., Sep. 13, 1994, 94202634

Int. Cl. B41M 5/035; 5/38

U.S. Cl. 430-200

12 Claims


1. Dye-donor element for use according to thermal dye sublimation transfer, said dye-donor element comprising a support having thereon a dye layer comprising a polymeric binder and a dye corresponding to the following general formula (I):



wherein:

Z represents hydrogen or a substituent,

X represents $N-R$ or



R represents NR^3R^4 ;

R^1 represents NR^3R^4 or SR^{12} ;

R^2 represents hydrogen cyano COR^{13} , CO^2R^{13} , $CONR^{14}R^{15}$, SO_2R^{16} ;

R^3 and R^4 each independently represent hydrogen, an alkyl group, an alkenyl group, an aryl group, an alkenyl group, a heterocyclic group or R^3 and R^4 together with the atoms to which they are attached represent the atoms necessary to complete a ring or R^3 and/or R^4 and one of the Y -substituents together with the atoms to which they are attached represent the necessary atoms to form a 5 - or 6 -membered, fused-on heterocyclic ring;

Y represents a substituent;

n represents 0 , 1 , 2 , 3 or 4 , the substituents being the same or different when n is greater than 1 or two or more Y substituents can form an annelated ring system;

R^{12} , R^{13} , R^{14} and R^{15} each independently represent hydrogen, an alkyl group, an alkenyl group, an aryl group, an alkenyl group, a heterocyclic ring or R^{14} and R^{15} together with the atoms to which they are attached represent the necessary atoms to form a 5 - or 6 -membered ring or R^{13} or R^{14} or R^{15} or R^{14} and R^{15} together with one of the Y -substituents and the atoms to which they are attached represent the necessary atoms to form a 5 - or 6 -membered fused-on heterocyclic ring;

R^{16} represents hydroxy, an alkoxy group, an aryloxy group, $NR^{17}R^{18}$, an aryl group or an alkyl group, an alkenyl group, an alkenyl group, or R^{16} together with one of the Y -substituents and the atoms to which they are attached represent the necessary atoms to form a 5 - or 6 -membered fused-on heterocyclic ring;

R^{17} and R^{18} each independently represent hydrogen, an alkyl group, an alkenyl group, an alkenyl group, an aryl group, a heterocyclic ring or R^{17} and R^{18} together with the atoms to which they are attached represent the necessary atoms to form a 5 - or 6 -membered ring.

5,589,317

THERMAL TRANSFER IMAGING PROCESS

Geert Defieuw, Kessel-Lo; Wilhelmus Janssens, Aarschot; Herman Uytterhoeven, Bonheiden; Bart Horsten, Rumst; Jean-Marie Dewanckele, Drongen, and Jan Van den Bogaert, Schilde, all of Belgium, assignors to Agfa-Gevaert N.V., Mortsel, Belgium

Filed Mar. 8, 1995, Ser. No. 400,337

Claims priority, application European Pat. Off., Mar. 10, 1994, 94200612

Int. Cl. G03C 8/40; 8/44

U.S. Cl. 430-203

9 Claims

1. A thermal imaging process comprising in order, the steps of:

a) bringing a donor layer of a donor element into face to face relationship with a receiving layer of a receiving element to obtain an assemblage,

b) image-wise heating the assemblage by means of a thermal head, thereby causing image-wise transfer of an amount of a thermotransferable reducing agent to said receiving element in accordance with the amount of heat supplied by said thermal head,

c) separately said donor element from said receiving element, and

d) overall heating said receiving element, wherein

(i) said donor element comprises said donor layer on a support, wherein said donor layer comprises both a binder and a thermotransferable reducing agent which is capable of reducing a silver source to metallic silver upon heating, and

(ii) said receiving element comprises said receiving layer on a support, said receiving layer comprising a silver source which is capable of being reduced by means of a heat in the presence of a reducing agent.

5,589,318

HIGH CONTRAST PHOTOGRAPHIC SILVER HALIDE MATERIAL

Allison Hazel C. Dale, Mill End; Roger H. Piggin, Abbots Langley; Richard A. Hallett, East Finchley, and Paul R. McIntyre, South Oxhey, all of England, assignors to Eastman Kodak Company, Rochester, N.Y.

Continuation of Ser. No. 400,155, Mar. 7, 1995, abandoned.

This application Jan. 4, 1996, Ser. No. 583,198

Claims priority, application United Kingdom, Apr. 16, 1994, 9407599; Dec. 21, 1994, 9425802

Int. Cl.⁶ G03C 1/035; 1/08

U.S. Cl. 430—264

10 Claims

1. A high contrast photographic material comprising a support bearing a silver halide emulsion layer; said photographic material containing, in said emulsion layer or an adjacent hydrophilic colloid layer, a hydrazide nucleating agent and said photographic material being characterized in that said emulsion layer comprises silver halide grains which are spectrally sensitized with a non-desorbing sensitizing dye and silver halide grains which are not spectrally sensitized; both said spectrally sensitized silver halide grains and said non-spectrally-sensitized silver halide grains contributing, as a consequence of the presence of said hydrazide nucleating agent in said photographic material, to the visible silver image that is produced by imagewise exposure and development of said photographic material.

5,589,319

PHOTOSENSITIVE POLYIMIDE RESIN COMPOSITION

Kouichi Katou; Eiji Watanabe, both of Kanagawa, and Kouichi Kunimune, Chiba, all of Japan, assignors to Chisso Corporation, Osaka, Japan

PCT No. PCT/JP93/00853, § 371 Date Feb. 17, 1994, § 102(e) Date Feb. 17, 1994, PCT Pub. No. WO94/00800, PCT Pub. Date Jan. 6, 1994

PCT Filed Jun. 24, 1993, Ser. No. 196,125

Claims priority, application Japan, Jun. 25, 1992, 4-190155

Int. Cl.⁶ G03C 1/73

U.S. Cl. 430—288.1

16 Claims

1. A photosensitive resin composition which comprises (1) 100 parts by weight of a fluorine-containing polyimide, (2) 10–100 parts by weight of an isocyanurate having a (meth)acrylic group, (3) 10–100 parts by weight of a polyalkylene glycol di(meth)acrylate, and (4) 0.5–20 parts by weight of a photopolymerization initiator as essential components.

5,589,320

POLYMERIC FLUORESCENT SUBSTANCE AND ORGANIC ELECTROLUMINESCENCE DEVICES USING THE SAME

Toshihiro Ohnishi; Takanobu Noguchi, and Shuji Doi, all of Tsukuba, Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Jul. 14, 1994, Ser. No. 274,798

Claims priority, application Japan, Jul. 21, 1993, 5-180247; Sep. 24, 1993, 5-237851

Int. Cl.⁶ G03C 5/00

U.S. Cl. 430—321

7 Claims

1. An organic electroluminescence device at least having a light emitting layer between two electrodes consisting of an anode and a cathode forming a counterpart thereto at least one of which electrodes is transparent or semi-transparent, wherein said light emitting layer comprises

a polymeric fluorescent substance which is soluble in organic solvents, has a number-average molecular weight of 10^3 to 10^7 and contains, as main constituents, three different repeating units A, B and C selected from the repeating units presented by the following formula (1), wherein the ratios of the respective repeating units in the polymeric substance are such

that when the repeating unit constituting the polymer having the longest optical absorption edge wavelength is expressed by A, the repeating unit constituting the polymer having the next longest absorption edge wavelength is expressed by B and the repeating unit constituting the polymer having the shortest optical absorption edge wavelength is expressed by C, A is contained in an amount of 2–60 mol %, B in an amount of 5–60 mol % and C in an amount of 20–50 mol % based on the total number of the three different repeating units:



(1)

wherein Ar is an arylene group having 6 to 20 carbon atoms, a heterocyclic compound group having 4 to 20 carbon atoms or a divalent group represented by the following formula (2) and at least one of the repeating units At B and C has at least one substituent group selected from an alkyl group, an alkoxy group and an alkylthio group having 2 to 22 carbon atoms, an aryl group and an aryloxy group having 6 to 60 carbon atoms and a heterocyclic compound group having 4 to 60 carbon atoms:



(2)

wherein Ar₁ and Ar₂ are respectively an arylene group having 6 to 20 carbon atoms or a heterocyclic compound group having 4 to 20 carbon atoms and optionally containing at least one substituent of at least one species of a group selected from an alkyl group, an alkoxy group and an alkylthio group having 2 to 22 carbon atoms, an aryl group and an aryloxy group having 6 to 60 carbon atoms and a heterocyclic compound group having 4 to 60 carbon atoms; R is a hydrocarbon or a heterocyclic compound group having 1 to 22 carbon atoms; and X₁ and X₂ represent independently —O—, —S—, —COO— or —OCO—.

5,589,321

METHOD OF AND APPARATUS FOR CONTROLLING DRYING OF PHOTOGRAPHIC MATERIAL

Shinichi Matsuda, Kanagawa, Japan, assignor to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Jul. 19, 1994, Ser. No. 277,168

Claims priority, application Japan, Jul. 20, 1993, 5-179373

Int. Cl.⁶ G03C 1/725; 1/73; 5/18; 5/26

U.S. Cl. 430—432

6 Claims



1. A method of controlling drying of a photographic material wherein after a photosensitive material is processed by processing solutions, heating the resulting photographic material by a contact-heating device, and blowing warm air onto said photographic material, further comprising the step of:

controlling the temperatures of said contact-heating device and the warm air so that relative contributions of drying of said photographic material by said contact-heating device and the warm air are always constant.

5,589,322

PROCESS FOR MAKING A DIRECT DISPERSION OF A PHOTOGRAPHICALLY USEFUL MATERIAL

Lloyd A. Lobo, Webster, and Aileen M. Sverika, Rochester, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Dec. 12, 1995, Ser. No. 570,995

Int. Cl.⁶ G03C 7/388; 1/025; 1/38; 1/005

U.S. Cl. 430—449

16 Claims

1. A process for making a direct dispersion of a photographically useful material comprising: subjecting a mixture of an aqueous gelatin solution, a liquid organic phase comprising a photographically useful material, and an ionic polymer to conditions of high shear or turbulence to form a fine dispersion of the organic phase having an average particle size of less than 0.5 micron dispersed in the aqueous solution; wherein the ratio of the organic phase viscosity to the aqueous gelatin solution viscosity in the absence of the ionic polymer, measured at the temperature of the dispersion forming step, is greater than a value of 2.0, and the ionic polymer is a water soluble or dispersible substantially non-surface active polyelectrolyte which has a molecular weight of at least 10,000 selected from:

- synthetic polymers derived from at least 5 mole % of monomers which contain —OSO₃M, —SO₃M, —COOM, or —OPO(OM)₂ substituent groups where M represents a hydrogen atom or a cationic counterion, and
- polysaccharide materials bearing at least one suDstituent group as described in i) per saccharide unit.

5,589,323

CHEMICALLY STABLE ASCORBATE-BASED PHOTOGRAPHIC DEVELOPER AND IMAGING PROCESS

John L. Adkins, Smyrna, Ga., and Dinesh P. Patel, Edison, N.J., assignors to Sun Chemical Corporation, Fort Lee, N.J.

Filed Jan. 23, 1996, Ser. No. 589,918

Int. Cl.⁶ G03C 5/29

U.S. Cl. 430—492

12 Claims

1. A process for forming a high contrast photographic image comprising the steps of:

- imagewise exposing a silver halide photographic element containing a hydrazine compound which functions as a nucleating agent, wherein said element is free of incorporated amine boosters; and
- developing said exposed element with a chemically stable aqueous alkaline developing solution that is free of dihydroxybenzene developing agents and has a pH between 9.5 and 11, said developing solution comprising:
 - an ascorbic acid developing agent;
 - an auxiliary developing agent; and
 - a combination of an alkali metal carbonate and an alkali metal borate comprising between 0.125 and 0.5 molar concentration of said carbonate and between 0.04 and 0.35 molar concentration of said borate.

5,589,324

ANTISTATIC LAYER FOR PHOTOGRAPHIC ELEMENTS COMPRISING POLYMERIZED POLYFUNCTIONAL AZIRIDINE MONOMERS

Allan J. Wexler, Vestal, N.Y., assignor to International Paper Company, Purchase, N.Y.

Filed Jul. 13, 1993, Ser. No. 91,335

Int. Cl.⁶ G03C 1/89

U.S. Cl. 430—529

28 Claims

1. A photographic element comprising a support having at least one surface, at least one photosensitive layer on the support, and a permanent antistatic layer coated on at least one surface of the support,

wherein the antistatic layer comprises a distinct layer, said antistatic layer comprising a polymer polymerized on said

support from monomers, in the presence of a water-soluble, electrically conductive polyelectrolyte, wherein the monomers comprise polyfunctional aziridines, wherein said polymer entraps the polyelectrolyte, wherein said polyelectrolyte contains ionizable functional groups selected from the group consisting of salts of sulfonic acid and salts of hydrogen sulfate, and wherein the weight ratio of the monomers to the polyelectrolyte is greater than 0.3 but less than or equal to 1.0.

5,589,325

SILVER HALIDE PHOTOGRAPHIC MATERIAL

Koichi Kuno, and Shuzo Suga, both of Kanagawa, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Continuation of Ser. No. 331,193, Oct. 28, 1994, abandoned.

This application Jan. 22, 1996, Ser. No. 589,210



Claims priority, application Japan, Nov. 1, 1993, 5-293825

Int. Cl.⁶ G03C 1/12



U.S. Cl. 430—576

3 Claims


1. A silver halide photographic material comprising a support having provided thereon at least one light-sensitive silver halide emulsion layer, wherein the emulsion is spectrally sensitized with at least one compound selected from the compounds represented by the following formulae (1) and (2) and contains a compound represented by the following formula (5):



wherein DYE represents a methine dye; G and G⁻ each represents a substituent of the methine dye, wherein G and G⁻ are represented by the following formula (3) and (4) respectively; and n is an integer of from 1 to 3:



wherein T¹ represents a divalent linking group; G¹ represents a carbonyl group, a sulfinyl group or a sulfonyl group; G² represents —CO—T², —SO—T², —SO₂—T² or a cyano group; and T² represents a monovalent group:



wherein R₅₂ represents an unsubstituted an alkylene group having from 1 to 6 carbon atoms; X₁ represents a halogen atom, a nitro group, an alkyl group, a substituted or unsubstituted amino group, —CO—R₅₂ or —SO₃M, in which R₅₂ represents a hydrogen atom, —OM, an alkyl group, an alkoyl group or a substituted or unsubstituted amino group; M represents a hydrogen atom, an alkali metal atom or an atomic group which is a monovalent cation; and m represents 0 or an integer of from 1 to 5;

wherein the compound represented by formula (5) is added in an amount of 0.05 mol or more per mol of the silver halide.

5,589,326


OSMIUM-CONTAINING REDOX MEDIATOR

Zhi D. Deng; Gerald F. Sigler, both of Carmel; Nigel A. Surridge, Indianapolis; Christopher D. Wilsey, Carmel; Robert J. McEnroe, Noblesville; Walter W. Jernigan, and Rebecca W. Muddiman, both of Indianapolis, all of Ind., assignors to Boehringer Mannheim Corporation, Indianapolis, Ind.


Filed Dec. 30, 1993, Ser. No. 180,492
Int. Cl.⁶ C12Q 1/00; 1/37; 1/26

U.S. Cl. 435—4

11 Claims



1. A compound having the formula:



wherein

R and R' are the same or different and are 2,2'-bipyridyl, 4,4'-disubstituted-2,2'-bipyridyl, 5,5'-disubstituted-2,2'-bipyridyl, 1,10-phenanthroline, 4,7-disubstituted-1,10-phenanthroline, or 5,6-disubstituted-1,10-phenanthroline, wherein the disubstitution is a methyl, ethyl, or phenyl group.
R and R' are coordinated to Os at their nitrogen atoms.
R' is hydrogen, methyl or ethyl.
Z is chloro or bromo.
m is +1 or +2.
X is an anion and is chloride, bromide, iodide, fluoride, tetrafluoroborate, perchlorate, nitrate, sulfate, carbonate, or sulfite.
Y is an anion and is chloride, bromide, iodide, fluoride, tetrafluoroborate, perchlorate or nitrate, and
n is 1 or zero,
but when X is sulfate, carbonate, or sulfite, n is zero,
and when m is 1, n is zero and X is not sulfate, carbonate or sulfite,
wherein the aqueous solubility of the compound is greater than about 1 millimolar.

5,589,327

METHOD AND COMPOSITION FOR THE DETERMINATION OF RED BLOOD CELL FLOATE

Kathy Hilyard, Pembroke, Fla.; James Monticello, New City, N.Y., and James Rugg, North Miami, Fla., assignors to Dade International Inc., Deerfield, Ill.


Filed Jul. 18, 1994, Ser. No. 276,293

Int. Cl.⁶ C12Q 1/00; G01N 33/53; 33/48

U.S. Cl. 435—4

22 Claims

1. A composition useful for the determination of folate from a hemolysate of red blood cells in a non-radiolabeled assay comprising:



a) a detergent; and
b) a buffer;
wherein the composition solubilizes membranes of red blood cells in the hemolysate and allows for the determination of folate in said non-radiolabeled assay.

5,589,328

CHEMILUMINESCENCE ASSAYS BASED ON INDOXYL SUBSTRATES, THIOINDOXYL SUBSTRATES AND OTHER SUBSTRATES

Vijay K. Mahant, 5669 Amaya Dr., #367, La Mesa, Calif. 91942
Continuation-in-part of Ser. No. 286,697, Aug. 4, 1994, abandoned. This application Mar. 15, 1995, Ser. No. 404,545

Int. Cl.⁶ C12Q 1/00; 1/34; 1/44

U.S. Cl. 435—4

20 Claims

1. A method for determining enzyme activity in a sample comprising:
combining the sample with a substrate selected from indoxyl ester, thioindoxyl ester and benzofuran ester to produce a hydrolysis product upstream of H₂O₂ production;
reacting the hydrolysis product upstream of H₂O₂ production with a chemiluminescence generating reagent to produce chemiluminescence;
measuring the chemiluminescence produced; and
correlating the chemiluminescence measured with the enzyme activity in the sample.

5,589,329

METHODS AND COMPOSITIONS FOR DETECTING BASE PAIR MISMATCHES


Matthew Winkler, Austin, and Marianna M. Goldrick, Pflugerville, both of Tex., assignors to Ambion, Inc., Austin, Tex.

Filed Nov. 15, 1993, Ser. No. 155,937

Int. Cl.⁶ C12Q 1/68

U.S. Cl. 435—5

44 Claims



1. A method for detecting a base pair mismatch between a nucleic acid sample and a single stranded RNA probe, comprising the steps of:

5,589,331

METHOD FOR DETECTING ABNORMAL SEROTONERGIC FUNCTION

David A. Nielsen, Kensington; David Goldman, Potomac; Markku Linnoila, Bethesda, all of Md., and Matti Virkkunen, Helsinki, Finland, assignors to The United States of America as represented by the Department of Health and Human Services, Washington, D.C.

Continuation-in-part of Ser. No. 873,913, Apr. 24, 1992, abandoned. This application Sep. 22, 1993, Ser. No. 125,628

Int. Cl.⁶ C12Q 1/68; C07H 21/04; C12P 19/34

U.S. Cl. 435—6

13 Claims

- separately contacting a single stranded RNA probe with a control nucleic acid sample and a test nucleic acid sample, thereby forming a control duplex, which is free from mismatches, and a test duplex;
- treating said control duplex and said test duplex with a composition comprising an RNase enzyme at a final concentration of between about 0.1 ng/ml and about 4000 ng/ml in a final salt concentration of between about 3 mM and about 90 mM; and
- detecting a difference in the products of said RNase treated duplexes;

wherein said difference indicates a base pair mismatch.

5,589,330

HIGH-THROUGHPUT SCREENING METHOD FOR SEQUENCE OR GENETIC ALTERATIONS IN NUCLEIC ACIDS USING ELUTION AND SEQUENCING OF COMPLEMENTARY OLIGONUCLEOTIDES


Anthony P. Shuber, Millford, Mass., assignor to Genzyme Corporation, Cambridge, Mass.

Filed Jul. 28, 1994, Ser. No. 281,940

Int. Cl.⁶ C12Q 1/68; 1/70; C12P 19/34

U.S. Cl. 435—5

18 Claims



1. A method for high-throughput screening of mammalian genomic DNA samples to identify one or more genetic alterations in one or more target DNA sequences present in said samples, comprising the steps of:

- immobilizing a plurality of said mammalian genomic DNA samples on a solid-phase support;
 - simultaneously hybridizing said immobilized DNA samples with a multiplicity of synthetic oligonucleotides of equivalent length, each of said oligonucleotides comprising a variant sequence of one of said target DNA sequences;
 - removing oligonucleotides that do not hybridize to said immobilized DNA samples;
 - individually eluting from each of said immobilized DNA samples oligonucleotides that hybridize to said samples; and
 - determining the sequence of said individually eluted oligonucleotides;
- wherein the sequence identifies said one or more genetic alterations.

5,589,332

RIBOZYME AMPLIFIED DIAGNOSTICS

Aody Shih; Jeffrey M. Bockman, and Shaji T. George, all of New York, N.Y., assignors to Innovir Laboratories, Inc., New York, N.Y.


Continuation of Ser. No. 985,308, Dec. 4, 1992, abandoned.

This application May 9, 1994, Ser. No. 240,081

Int. Cl.⁶ C12Q 1/68; C07H 21/02; 21/04

U.S. Cl. 435—6

25 Claims



1. A method for detecting a target nucleic acid molecule in a solution, comprising:
providing in the solution under conditions wherein two complementary nucleotide molecules will hybridize, a ribozyme molecule, a labelled co-target nucleic acid molecule and the target nucleic acid molecule, wherein the co-target and the target

5,589,342

KIT FOR SEPARATING DOUBLE-STRANDED NUCLEIC ACID FROM A SINGLE-STRANDED/DOUBLE-STRANDED MIXTURE OF NUCLEIC ACIDS

Jon R. Gelger, West Hartford, and Samuel I. Trotz, Orange, both of Conn., assignors to Olin Corporation, Cheshire, Conn.

Division of Ser. No. 944,919, Dec. 22, 1986, Pat. No. 5,034,314. This application Nov. 19, 1990, Ser. No. 615,095
Int. Cl.⁶ C12Q 1/68

U.S. Cl. 435—6

2 Claims

1. A kit for effecting separation of labelled probe nucleic acid molecules from hybridized probe/target nucleic acid molecules consisting essentially of:

- a sample of labelled probe nucleic acid molecules and
- a membrane filter having a pore size within a range such that unhybridized labelled probe nucleic acid molecules pass through said membrane filter whereas labelled probe nucleic acid molecules hybridized with complementary target nucleic acid molecules are retained on said membrane filter, said pore size provided a molecular weight cutoff of between 200,000 and about 300,000 Daltons, wherein said labelled probe nucleic acid molecules have an enzyme label, either covalently attached to the probe or indirectly attached to the probe by means of a biotin-avidin-biotin linkage, and wherein said kit additionally contains an enzyme substrate to assist in identification of hybridized probe/target nucleic acid molecules.

5,589,343

ANTIBODIES WHICH BIND TO MOLECULES CONTAINING AT LEAST ONE PEPTIDE SEQUENCE CARRYING ONE OR SEVERAL EPITOPES CHARACTERISTIC OF A LIVER STAGE ANTIGEN PRODUCED BY *P. FALCIPARUM* IN HEPATOCYTES

Claudine Marchand, Paris; Pierre Druilhe, Saint Mande; Odile Puijalon-Mercereau, Issy Les Moulineaux, and Gordon Langsley, Paris, all of France, assignors to Institut Pasteur, France

Division of Ser. No. 275,139, Oct. 6, 1988. This application Jun. 5, 1995, Ser. No. 463,512

Claims priority, application France, Feb. 9, 1987, 87 01543
Int. Cl.⁶ C01N 33/569; C07K 16/20

U.S. Cl. 435—7.22

19 Claims

1. An isolated or antibody which specifically binds to a *P. falciparum* polypeptide, antigen comprising an amino acid sequence selected from the group consisting of:

Leu-Ala-Lys-Glu-Lys-Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg

Ala-Lys-Glu-Lys-Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Gln-Arg-Leu

Lys-Glu-Lys-Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Gln-Arg-Leu-Ala

Glu-Lys-Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys

Lys-Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu

Leu-Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys

Gln-Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Glu

Glu-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln

Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Glu

Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Glu-Gln

Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Glu-Gln-Gln

Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser

Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser-Asp

Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser-Asp-Leu

Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser-Asp-Leu-Glu

Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser-Asp-Leu-Glu-Gln

Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Leu

Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg

Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu

Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala

Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys

Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu

Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys

Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu

Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln

Gln-Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly

Gln-Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln

Ser-Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln

Asp-Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser

Leu-Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp

Glu-Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu

Gln-Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu

Glu-Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln

Arg-Leu-Ala-Lys-Glu-Lys-Leu-Gln-Gly-Gln-Gln-Ser-Asp-Leu-Glu-Gln-Leu

wherein said polypeptide induces antibodies that react with the schizont stage of *Plasmodium falciparum*, and wherein said polypeptide does not react with antibodies to the blood or sporozoite stages of *Plasmodium falciparum*.

5,589,344

TEST KIT AND METHOD FOR COMPETITIVE SPECIFIC BINDING ASSAY

Paul B. Contestable, and Brian A. Snyder, both of Rochester, N.Y., assignors to Johnson & Johnson Clinical Diagnostics, Inc., Rochester, N.Y.

Filed Jun. 15, 1994, Ser. No. 259,942

Int. Cl.⁶ G01N 33/53; 33/543

U.S. Cl. 435—7.9

14 Claims

1. A specific binding method for the detection of a target specific binding ligand comprising the steps of:

A) bringing together, in any order:

- 1) a fluid sample suspected of containing a target specific binding ligand,
- 2) an immobilized first receptor for said target specific binding ligand, and
- 3) a water-soluble conjugate of said target specific binding ligand and a reporter enzyme,

to form a mixture containing a water-insoluble complex between said first receptor and said conjugate,

B) separating said water-insoluble complex of said first receptor from any uncomplexed water soluble conjugate,

C) bringing together a sample of said uncomplexed water-soluble conjugate, and an immobilized second receptor, wherein said second receptor is specific for said reporter enzyme, and further wherein said second receptor inhibits the activity of said reporter enzyme by less than 20%,

to form a water-insoluble reaction product of said immobilized second receptor and any uncomplexed water-soluble conjugate,

D) separating said water insoluble reaction product formed in step C) from any unreacted water-soluble conjugate, and

E) detecting any signal generated from said separated water-insoluble reaction product as a determination of said target specific binding ligand in said fluid sample.

5,589,345

CULTURES OF PERMANENT LINES OF HUMAN PROMYELOCYTIC CELLS AND THEIR USES FOR THE SCREENING OF MOLECULES UTILIZABLE IN PARTICULAR IN THE TREATMENT OF LEUKEMIAS

Michel Lanotte, and Roland Berger, both of Paris, France, assignors to Institut National de la Sante et de la Recherche Medicale, Paris, France

PCT No. PCT/FR92/00173, § 371 Date Dec. 17, 1993, § 102(e) Date Dec. 17, 1993, PCT Pub. No. WO92/14815, PCT Pub. Date Sep. 3, 1992

PCT Filed Feb. 25, 1992, Ser. No. 108,587

Claims priority, application France, Feb. 25, 1991, 91 02229

Int. Cl.⁶ G01N 33/574; C12N 5/08

U.S. Cl. 435—7.23

4 Claims

4. A kit for a method for in vitro screening of acute human promyelocytic leukemia utilizing an NB4 cell line as a positive control, wherein the cell line NB4 was deposited with the Collection Nationale de Culture de Micro-organismes de l'INSTITUT PASTEUR (CNCM) on Feb. 25, 1991 under accession number I-1045, and with the Deutsche Sammlung von Mikro-organismen und Zellkulturen GmbH (DSMZ) on Feb. 14, 1992 under accession number DSM ACC.2030, said kit comprising:

- (a) an NB4 cell line; and
- (b) a reagent suitable for detection of cellular differentiation.

5,589,346

METHOD OF MONITORING MARKERS OF BONE METABOLISM

Paul G. Kanan, Laguna Niguel, Calif.; Richard H. Smith, Ann Arbor, Mich., and Ellen Rudnick, Deerfield, Ill., assignors to BioQuant, Inc., Irvine, Calif.

Filed Jun. 21, 1994, Ser. No. 263,137

Int. Cl.⁶ G01N 33/543

U.S. Cl. 435—7.92

8 Claims

1. A method of monitoring bone metabolism comprising continuously collecting a sweat sample from a subject and assaying the sweat sample to determine the concentration of pyridinoline in the sample.

5,589,347

MULTILAYER ANALYSIS ELEMENTS FOR THE DETERMINATION OF TOTAL CHOLESTEROL

Fuminori Arai, and Takeshi Igarashi, both of Saitama, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan
Continuation of Ser. No. 128,758, Sep. 30, 1993, abandoned, which is a continuation-in-part of Ser. No. 600,289, Oct. 19, 1990, abandoned, which is a continuation-in-part of Ser. No. 133,980, Dec. 17, 1987, abandoned. This application Jun. 5, 1995, Ser. No. 461,766

Claims priority, application Japan, Dec. 18, 1986, 61-302325
Int. Cl.⁶ C12Q 1/60; 1/44; C12N 11/00; G01N 33/92

U.S. Cl. 435—11

26 Claims

1. A multilayer analysis element for determination of total cholesterol comprising a light-transmissive water-impermeable support, at least one hydrophilic polymer layer provided on said support and a spreading layer provided on said hydrophilic polymer layer(s), and containing in one or more of said layers:

- (a) at least one enzyme having cholesterol esterase activity,
- (b) cholesterol oxidase,
- (c) peroxidase,
- (d) a colorimetric reagent composition, which in the presence of hydrogen peroxide and said peroxidase, produces a color change;
- (e) at least one bile acid compound selected from the group consisting of bile acids, bile acid derivatives and salts of said acids and derivatives, and
- (f) an alkyl phenoxy polyethoxy ethanol containing a polyoxyethylene chain composed of 30 to 60 oxyethylene units, wherein the alkyl group in said alkyl phenoxy polyethoxy ethanol is a linear or branched alkyl group having 7 to 10 carbon atoms.

5,589,348

IN SITU NICOTINAMIDE COENZYME GENERATING SYSTEM FOR ENZYME BASED CLINICAL CHEMISTRY ASSAYS

Richard A. Kaufman, Belleville; John M. Konopka, Westfield; Henry J. Rosenfeld, Florham Park, and Janine E. Sabo, Lodi, all of N.J., assignors to Hoffmann-La Roche Inc., Nutley, N.J.

Continuation of Ser. No. 67,415, May 25, 1993, abandoned, which is a continuation of Ser. No. 930,494, Aug. 14, 1992, abandoned, which is a continuation of Ser. No. 800,654, Nov. 27, 1991, abandoned, which is a continuation of Ser. No. 447,337, Dec. 7, 1989, abandoned, which is a continuation-in-part of Ser. No. 399,052, Aug. 28, 1989, abandoned. This application Mar. 22, 1994, Ser. No. 216,231

Int. Cl.⁶ C12Q 1/32; C12P 17/02

U.S. Cl. 435—26

27 Claims


1. In an enzymatic method for determining the concentration of an analyte in a body fluid sample by measuring the change in absorbance of a reaction mixture containing said sample, the change in absorbance due to oxidation of a reduced nicotinamide coenzyme in the reaction mixture, comparing the change in absorbance with the analyte to the change in absorbance with standards

which calibrate for reaction conditions and calculating the concentration of said analyte, the improvement comprising generating a reduced nicotinamide coenzyme in situ by mixing the body fluid sample, an oxidized nicotinamide coenzyme, a substrate is a molar amount equal to or less than the molar amount of the oxidized nicotinamide coenzyme added, and an enzyme specific for said substrate, such that the reduced nicotinamide coenzyme is generated in situ from the oxidized coenzyme by reaction of said substrate with the substrate specific enzyme, the substrate specific enzyme being present in an amount such that the in situ generation of the reduced nicotinamide coenzyme occurs at a rate equal to or greater than reoxidation of the reduced coenzyme by an analyte specific enzyme.

5,589,349

METHOD FOR ENZYMATIC ANALYSIS AND REAGENT THEREFOR

Akihito Shinzaki, Miwa Watanabe, and Tadao Suzuki, all of Kyoto, Japan, assignors to Unilika Ltd., Hyogo, Japan
Continuation of Ser. No. 32,263, Mar. 17, 1993, abandoned.
This application Nov. 3, 1994, Ser. No. 335,975
Claims priority, application Japan, Mar. 17, 1992, 4-060743; Nov. 9, 1992, 4-298924
Int. Cl.⁶ C12Q 1/32; 1/00; G01N 33/53; 33/48
U.S. Cl. 435—26 4 Claims




1. A method of enzymatic analysis of a sample containing NAD or NADH, which comprises conducting enzymatic cycling of NAD-NADH interconversions in the presence of a dehydrogenase, a substrate for the dehydrogenase, a tetrazolium dye and a diaphorase, and detecting an amount of the NAD or NADH with a color-development signal of formazan which is produced by reduction of the tetrazolium dye by the action of the diaphorase and NADH-NAD conversions, wherein the dehydrogenase is alcohol dehydrogenase derived from microorganisms belonging to *Zymomonas*.

5,589,350

TESTING DEVICE FOR LIQUID AND LIQUID SUSPENDED SAMPLES

Barry Bochner, Alameda, Calif., assignor to Biolog, Inc., Hayward, Calif.
Continuation of Ser. No. 462,443, Jun. 5, 1995, abandoned, which is a continuation of Ser. No. 972,625, Nov. 6, 1992, abandoned. This application Jan. 11, 1996, Ser. No. 584,989
Int. Cl.⁶ C12Q 1/02; C12M 1/18
U.S. Cl. 435—29 8 Claims

1. A method for testing samples comprising:
(a) providing a sample in liquid form;
(b) providing a sample delivering means;




- (c) providing a device comprising: i) a housing, ii) a testing region comprising a plurality of test wells contained within said housing, iii) a liquid receiving means at an external surface of said housing, iv) a liquid flow-directing means providing liquid communication between said test wells of said testing region and said liquid receiving means, and v) a single gas-venting, liquid barrier having an inner and outer surface wherein said inner surface is in fluidic communication with said test wells of said testing region;
(d) delivering, internal to said housing, said sample via said sample delivering means to said testing region, such that said liquid enters said device at said liquid receiving means under positive pressure and the air in said device is vented through said gas-venting liquid barrier, wherein said positive pressure is greater than 1 pound per square inch; and
(e) attaching a non-venting material to said outer surface of said gas-venting barrier, such that said device is sealed.

5,589,351

FLUORESCENCE DETECTION APPARATUS

Alec T. Harootunian, Salt Lake City, Utah, assignor to NPS Pharmaceuticals, Inc., Salt Lake City, Utah
Filed Dec. 6, 1994, Ser. No. 350,232
Int. Cl.⁶ C12Q 1/02
U.S. Cl. 435—29 21 Claims




1. An apparatus for detecting light transmitted from a composition disposed in one of a plurality of sample wells, said apparatus comprising:
a single light detector;
a reflector comprising means for selectively receiving light from any one of a plurality of detection emitters positioned about said reflector and of reflecting light toward said light detector; and
a plurality of detection carriers, each of said detection carriers comprising means for carrying light from one of the wells to one of said detection emitters.

5,589,352

DIFFUSION GRADIENT CHAMBER SYSTEM

John A. Breznak, David Emerson, both of East Lansing, and John K. Koh, Ann Arbor, all of Mich., assignors to Board of Trustees operating Michigan State University, East Lansing, and Koh Development, Inc., Ann Arbor, both of Mich.
Continuation of Ser. No. 117,222, Sep. 3, 1993. This application Jun. 6, 1995, Ser. No. 466,758
Int. Cl.⁶ C12Q 1/02; 1/04; C12M 3/00; 1/00
U.S. Cl. 435—34 34 Claims




1. An apparatus which functions for recording observations of microorganisms in an environment by providing a diffusion gradient in the environment which comprises:

- (a) a chamber having a space which supports a semi-solid nutrient medium for microorganism growth, wherein the chamber has spaced apart transparent walls and sidewalls defining a space between the walls;
(b) at least two reservoirs mounted on the chamber for a liquid transport medium to be provided in the chamber each reservoir with an opening into the space in the chamber through an opening into the chamber, wherein the reservoirs are removably mounted on the chamber;
(c) a diffusion membrane mounted between the opening in the reservoir and the opening in the chamber at a height so that the membrane is covered by the semi-solid nutrient medium wherein the diffusion membrane allows a molecule in the transport medium through the opening in the reservoirs, the diffusion membrane and the opening in the chamber into the semi-solid nutrient medium to establish the diffusion gradient of the molecule in the chamber for the microorganism wherein one of the reservoirs can serve as a sink to receive the molecule moving from the semi-solid nutrient medium out of the diffusion gradient;
(d) an inlet into and an outlet from each of the reservoirs for flow of the liquid transport medium;
(e) a supply means for supplying the liquid transport medium to the inlet to each of the reservoirs;
(f) an effluent means for receiving the transport medium from the outlet of each of the reservoirs without destroying the diffusion gradient of the molecule in the semi-solid nutrient medium;
(g) enclosed housing means defining an enclosure and supporting the chamber on an outside portion of the housing means and including a light source inside the housing means for illuminating the chamber through the transparent walls; and
(h) recorder means for providing a picture of an activity of the microorganisms over a time span on the nutrient medium as an analyte in the liquid transport medium is fed into the nutrient medium in the space in the chamber through the membrane from each of the reservoirs.

5,589,353

METHOD AND APPARATUS FOR THE SELECTIVE DETERMINATION OF FERMENTATIVE CULTURED ACTIVITIES

D. Roy Cullimore, 3303 Grant Road, Regina, Saskatchewan, Canada, and George W. Alford, 1954 Old Daytona Rd., Daytona Beach, Fla. 32014
Filed May 25, 1995, Ser. No. 450,420
Int. Cl.⁶ C12Q 1/04; C12M 3/00
U.S. Cl. 435—34 12 Claims



8. A method for testing a sample for the presence of a targeted microorganism, said method comprising the steps of placing said sample into a culture chamber, placing a test chamber within said culture chamber, said test chamber having a culture medium therein, and having a window in the wall thereof, capping said test chamber and said culture chamber, and inverting said test chamber and culture chamber so that at least some of said sample will pass through said window and into said test chamber, and manipulating said test chamber and culture chamber so that said sample flows onto said culture medium.

5,589,354

HALOGENATION OF CEPHALEXIN WITH HALOPEROXIDASE FROM RATHAYIBACTER BIOPURESIS

Bing L. Wong, Durham, N.H.; Yong-Qiang Shen, Revere, Mass., and Yung-Pin Chen, Columbia, S.C., assignors to Biopure Corporation, Cambridge, Mass.
Filed Dec. 20, 1994, Ser. No. 360,149
Int. Cl.⁶ C12P 35/00; C12N 9/02; 1/20
U.S. Cl. 435—47 4 Claims

1. A method for producing a halogenated cephalixin comprising incubating cephalixin in an aqueous environment with hydrogen peroxide and a protein extract from *Rathayibacter biopuresis* having cephalixin haloperoxidase activity under conditions such that said halogenated cephalixin is produced and recovered.

5,589,355

PROCESS FOR PRODUCING RIBOFLAVIN

Satoshi Koizumi, Yoshiyuki Yonetani, and Sadao Teshiba, all of Machida, Japan, assignors to Kyowa Hakko Kogyo Co., Ltd., Japan
Continuation of Ser. No. 161,394, Dec. 6, 1993, abandoned.
This application Jun. 6, 1995, Ser. No. 465,795
Claims priority, application Japan, Dec. 7, 1992, 4-326578
Int. Cl.⁶ C12P 25/00; C12N 1/21; 15/52; 15/63
U.S. Cl. 435—66 6 Claims

1. An isolated DNA fragment which comprises a DNA having the nucleotide sequence set forth in SEQ ID NO:2.

5,589,356

LITIGATION OF SIDECHAIN UNPROTECTED PEPTIDES VIA A MASKED GLYCOLALDEHYDE ESTER AND O,N-ACYL REARRANGEMENT


James P. Tam, Nashville, Tenn., assignor to Vanderbilt University, Nashville, Tenn.

Filed Jun. 21, 1993, Ser. No. 81,412

Int. Cl.⁶ C12P 21/06; C07K 1/00; 1/107

U.S. Cl. 435—68.1

12 Claims



Scheme II
I. DMSF, 60-70°C, 24 h; II. 30% TFA in CH₂Cl₂ (2.5% H₂O);
III. H₂O/CH₂Cl₂, pH 2-5; IV. pH 8-9.

1. A method of chemically ligating a C-terminal carboxylic group or a first peptide and an N-terminal amino group of a second peptide, said method comprising:

- introducing a masked aldehyde ester which is a glycolaldehyde ester into said carboxylic group of said first peptide;
- converting said masked aldehyde ester to its corresponding free aldehyde ester on said carboxylic group of said first peptide;
- reacting said free aldehyde ester with the N-terminal amino group of said second peptide whose amino terminal residue moiety is β -functionalized with —SH, —OH, —CO—NH₂, indole or imidazole to form a ring structure with said aldehyde on said first peptide and the N-terminal amino acid of said second peptide; and
- intramolecular-acyl rearranging said carboxylic group and said amino group such that said carboxylic group and said amino group form an amide bond.

5,589,357

MILK PROTEIN PARTIAL HYDROLYSATE AND PROCESS FOR PREPARATION THEREOF

Sarah B. Martinez, H. Lee Leary, Jr., and Debra J. Nichols, all of Evansville, Ind., assignors to Bristol-Myers Squibb Company, Princeton, N.J.

Division of Ser. No. 85,213, Jun. 30, 1993. This application Nov. 21, 1994, Ser. No. 342,977

Int. Cl.⁶ C12P 21/06

U.S. Cl. 435—68.1

6 Claims

1. A process for preparing a partial hydrolysate of a protein mixture comprising whey protein and casein, said process comprising:

- performing a pretreatment step comprising heating the protein mixture at about 75° C. to about 85° C. for about 10 minutes to about 30 minutes;
- contacting the protein mixture resulting from step (a) with an enzyme mixture comprising at least 1800 USP Trypsin Units/mg and at least 350 USP Chymotrypsin Units/mg in an aqueous suspension wherein the ratio in USP units of Trypsin to Chymotrypsin is about 1.3 to about 18, at a temperature of about 30° C. to about 50° C., a pH of about 6.5 to about 8.0, for about 2 to about 6 hours; and
- inactivating the enzyme mixture.

5,589,358

ILEAL BILE ACID TRANSPORTER COMPOSITIONS AND METHODS

Paul A. Dawson, 2111 Carriage Way, Chapel Hill, N.C. 27514

Filed Dec. 29, 1993, Ser. No. 176,126

Int. Cl.⁶ C12N 15/12

U.S. Cl. 435—69.1

22 Claims

1. An isolated DNA segment wherein said segment encodes a mammalian ileal/renal bile acid cotransporter having an amino acid sequence in accordance with seq id no:2 or seq id no:4.

5,589,359

CHIMERIC PROTEINS

Michael A. Innis, Moraga, and Abba A. Creasey, Piedmont, both of Calif., assignors to Chiron Corporation, Emeryville, Calif.

Filed Aug. 5, 1994, Ser. No. 286,521

Int. Cl.⁶ C12N 15/15; 15/63; A61K 38/00; C07K 14/81; 14/745; C12P 21/02; A61K 38/57; 38/36

U.S. Cl. 435—69.2

38 Claims

1. A chimeric protein comprising:

- a Kunitz-type domain 1 of Tissue Factor Pathway Inhibitor (TFPI)-2, and
- a Kunitz-type domain 2 of Tissue-Factor Pathway Inhibitor (TFPI); or
- a Kunitz-type domain 1 of TFPI, and
- a Kunitz-type domain 2 of TFPI-2.

5,589,360

POLYPEPTIDE, DNA FRAGMENT ENCODING THE SAME, DRUG COMPOSITION CONTAINING THE SAME AND PROCESS FOR PRODUCING THE SAME

Hideoaki Morishita, Toshinori Kanamori, and Masahiro Nobuhara, all of Tokyo, Japan, assignors to Mochida Pharmaceutical Co., Ltd., Tokyo, Japan

Division of Ser. No. 972,387, Nov. 5, 1992, Pat. No. 5,451,659.

This application Apr. 28, 1995, Ser. No. 431,412

Claims priority, application Japan, Nov. 8, 1991, 3-293472; May 12, 1992, 4-119289

Int. Cl.⁶ C12P 21/06; C12N 1/20; C07H 19/00; 21/00

U.S. Cl. 435—69.1

13 Claims

5' 3' 3' 5' AGCTTAAAAA AGGTTATATA ATAAATGAA AC
ATTATT TCCCATATT TATTACTT TGTTCATGA 5'

5' 3' 5' 5' AAAGTACTAT TGCATGGCA CTCTTACCGT TACTGTTT
TA AGGTGACCGT GAGATGGCA ATGACAAA TGCGGA 5'

5' 3' 5' 5' ACCCTGTGA CAAAGCGCA CTCCTAGGT CG
CACT GTTTCGGCT GAGGATCCA GC 5'

1. An isolated DNA molecule which comprises a nucleotide

sequence encoding a polypeptide consisting of a polypeptide having an amino acid sequence as recited in SEQ. I.D. NO. 67, wherein the amino acid sequence as recited in SEQ. I.D. NO. 67 is substituted by at least one substitution selected from the substitutions (i) to (iii):

- substitution of Arg at residue 7, counting from the amino-terminus by an amino acid selected from the group consisting of Ala, Asp, Asn, Gln, Leu, Glu and Ser,
- substitution of Gln at residue 15, counting from the amino-terminus by an amino acid selected from the group consisting of Arg and Lys, and
- substitution of Tyr at residue 42, counting from the amino-terminus by an amino acid selected from the group consisting of Asp, and Glu;

wherein said polypeptide optionally has an amino-terminal peptide having an amino acid sequence selected from the group consisting of:

Asp-Asp-Ala-Ala-, Thr-Val-Ala-Ala-, Val-Ala-Ala-, Ala-Ala-, and Ala-; and

wherein said polypeptide optionally has a carboxy-terminal peptide having an amino acid sequence selected from the group consisting of:

Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-Leu-Leu-Arg-Phe-Ser-Asn,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-Leu-Leu-Arg-Phe-Ser-,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-Leu-Leu-Arg-Phe-,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-Leu-Leu-Leu-,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-Glu-,
Gly-Val-Pro-Gly-Asp-Gly-Asp-Glu-,
Gly-Val-Pro-Gly-Asp-Gly-, Gly-Val-Pro-Gly-Asp-,
Gly-Val-Pro-Gly-, Gly-Val-Pro-, Gly-Val-, and Gly-.

5,589,361

HUMAN TISSUE-TYPE PLASMINOGEN ACTIVATOR VARIANT

Adair J. Hotchkiss, Half Moon Bay; John V. O'Connor, San Carlos, and Michael W. Spellman, San Bruno, all of Calif., assignors to Genentech, Inc., San Bruno, Calif.

Continuation of Ser. No. 118,098, Nov. 6, 1987, abandoned, which is a continuation-in-part of Ser. No. 21,893, Mar. 4, 1987, abandoned, which is a continuation-in-part of Ser. No. 841,075, Mar. 18, 1986, abandoned. This application Sep. 10, 1990, Ser. No. 581,189

Int. Cl.⁶ A61K 38/49; C12N 15/58

U.S. Cl. 435—69.1

2 Claims

1. A method for producing a human tissue-type plasminogen activator comprising transforming with DNA encoding said plasminogen activator variant mammalian host cell lacking N-acetylglucosamine aminotransferase, culturing the transformed cell, and recovering said variant from a culture of the cells.

5,589,362

TETRACYCLINE REGULATED TRANSCRIPTIONAL MODULATORS WITH ALTERED DNA BINDING SPECIFICITIES

Hermann Bujard, Heidelberg; Manfred Gossen, El Cerrito; Wolfgang Hillen, Erlangen; Vera Helbl, Fuerth, and Dirk Schnappinger, Bad Driburg, all of Germany, assignors to BASF Aktiengesellschaft, and Knoll Aktiengesellschaft, both of Ludwigshafen, Germany

Continuation-in-part of Ser. No. 383,754, Feb. 3, 1995, and a continuation-in-part of Ser. No. 275,876, Jul. 15, 1994, and a continuation-in-part of Ser. No. 260,452, Jun. 14, 1994, and a continuation-in-part of Ser. No. 76,726, Jun. 14, 1993, Pat. No. 5,464,758, said Ser. No. 275,876 is a continuation-in-part of Ser. No. 270,637, Jul. 1, 1994, abandoned, said Ser. No. 260,452 is a continuation-in-part of Ser. No. 76,327, Jun. 14, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 485,971

Int. Cl.⁶ C12P 21/00; C12N 15/31; C07H 21/04

U.S. Cl. 435—69.1

20 Claims

1. An isolated nucleic acid molecule encoding a fusion protein which regulates transcription, the fusion protein comprising a Tet repressor having at least one amino acid mutation that confers on the fusion protein an ability to bind a class B tet operator sequence having a nucleotide substitution at position +4 or +6, operatively linked to a polypeptide which regulates transcription in eukaryotic cells.

5,589,363

DNA ENCODING TISSUE FACTOR MUTANTS USEFUL FOR THE TREATMENT OF MYOCARDIAL INFARCTION AND COAGULOPATHIC DISORDERS

Soumitra Roy, San Francisco, and Gordon A. Vehar, San Carlos, both of Calif., assignors to Genentech, Inc., South San Francisco, Calif.

Division of Ser. No. 714,819, Jun. 13, 1991, Pat. No.

5,346,991. This application May 20, 1994, Ser. No. 246,978

Int. Cl.⁶ C07K 14/745; C12N 1/13; 15/12; 15/63

U.S. Cl. 435—69.6

16 Claims

1. An isolated substantially purified nucleic acid molecule encoding a tissue factor protein mutant molecule wherein either or both of the positively charged amino acid residues 165 and 166 are substituted with an α -amino acid other than one bearing a substantially positively charged sidechain at physiological pH.

5,589,364

RECOMBINANT PRODUCTION OF BIOLOGICALLY ACTIVE PEPTIDES AND PROTEINS

Jon I. Williams, Robbinsville, N.J.; James C. Pierce, Wilmington, Del.; G. Mark Anderson, Norristown, and Prasad Kari, Lansdale, both of Pa., assignors to Magainin Pharmaceuticals Inc., Plymouth Meeting, Pa.

Filed Jul. 29, 1994, Ser. No. 282,030

Int. Cl.⁶ C12P 21/00

U.S. Cl. 435—69.7

39 Claims

1. A method for recombinantly producing an antimicrobial amphiphilic, ion channel-forming peptide, comprising:

- providing a protease-deficient microbial host transformed with an expression vector having DNA that encodes the peptide as a fusion protein under the control of a regulatory sequence operable in the microbial host; and

- b. expressing the peptide as a fusion protein in the transformed microbial host, wherein the peptide is expressed in soluble form.

5,589,365

PROCESS FOR PRODUCING GLYCOSYLATED INDOLOPYRROLOCARBAZOLE DERIVATIVES BY CULTURING CERTAIN MICROORGANISMS

Katsuhisa Kojiri; Hisao Kondo; Hiroharu Arakawa; Mitsuru Ohkubo, and Hiroyuki Suda, all of Tsukuba, Japan, assignors to Banyu Pharmaceutical Co., Ltd., Tokyo, Japan
Continuation of Ser. No. 68,097, May 28, 1993, abandoned, which is a continuation-in-part of Ser. No. 981,070, Nov. 24, 1992. This application Jan. 31, 1995, Ser. No. 381,286


Claims priority, application Japan, Nov. 29, 1991, 3-341916; Jan. 9, 1992, 4-257306; Feb. 18, 1992, 4-69269; Dec. 14, 1992, 4-353623; Feb. 18, 1993, 5-053035

Int. Cl.⁶ C12P 19/28


U.S. Cl. 435—85

7 Claims

1. A process for preparation of a compound of the formula (VII)



wherein X¹ and X² are each a hydroxyl group, which comprises culturing a microorganism selected from the group consisting of *Microtetraspora* sp. A34549, *Saccharothrix aerocolonigenes* ATCC 39243, and a mutant thereof, all of which have ability to glycosylate a compound represented by the formula



wherein X¹ and X² have the same meanings as defined above, in a nutrient medium containing the compound of formula (VIII), and recovering the compound represented by formula (VII) from the culture medium.

5,589,366 PROCESS FOR PRODUCING ANTIPARASITIC MACROLIDE ANTIBIOTICS

Mark A. Haxell, Broadstairs; David A. Perry, Sandwich, both of England; Hiroshi Maeda, Chita-Gun, and Junsuke Tone, Chita, both of Japan, assignors to Pfizer Inc., New York, N.Y.
Division of Ser. No. 378,997, Jan. 27, 1995, Pat. No. 5,492,928, which is a continuation of Ser. No. 703,578, May 20, 1991, abandoned, which is a continuation of Ser. No. 314,734, Feb. 23, 1989, abandoned. This application Nov. 9, 1995, Ser. No. 556,245


Claims priority, application United Kingdom, Feb. 25, 1988, 8804440

Int. Cl.⁶ C07D 493/22

U.S. Cl. 435—119

6 Claims

1. A process for producing compounds N787-182-1 to N787-182-12 of the formula (I)



wherein, for the respective compound specified, the substituents R¹, R² and R³ are as follows:

COM- POUND	R	R ¹	R ²	R ³
N787-182-1	CH ₃	OH	OH	H
N787-182-2	H	OH	OH	OCOCH(CH ₃) ₂
N787-182-3	CH ₃	OH	OH	OCOCH(CH ₃) ₂
N787-182-4	H	OCOCH(CH ₃) ₂	OH	H
N787-182-5	CH ₃	OCOCH(CH ₃) ₂	OH	H
N787-182-6	H	OCOCH(CH ₃) ₂	OH	OCOCH(CH ₃) ₂
N787-182-7	CH ₃	OCOCH(CH ₃) ₂	OH	OCOCH(CH ₃) ₂
N787-182-8	H	H	OH	OCOCH(CH ₃) ₂
N787-182-9	H	OCOCH(CH ₃) ₂	H	H
N787-182-10	CH ₃	OCOCH(CH ₃) ₂	OH	OCOCH(CH ₃) ₂
N787-182-11	CH ₃	H	OH	OCOCH(CH ₃) ₂
N787-182-12	CH ₃	OCOCH(CH ₃) ₂	H	H

which comprises cultivating a microorganism having the identifying characteristics of *Streptomyces* sp. ATCC 53718, or a mutant, genetically transformed or recombinant form thereof having the ability to produce one or more of the N787-182 compounds, in submerged aqueous or solid agar culture media containing an assimilable source of carbon, nitrogen and inorganic salts, under submerged aerobic fermentation conditions until a recoverable amount of said N787-182 compounds are obtained; and recovering said compounds.

5,589,367

RECOMBINANT PLANT VIRAL NUCLEIC ACIDS

Jon Danson, Davis, Calif.; William O. Dawson, Winter Haven, Fla.; George L. Grantham, Riverside, Calif.; Thomas H. Turpen, Vacaville, Calif.; Ann M. Turpen, Vacaville, Calif.; Stephen J. Garger, Vacaville, Calif., and Laurence K. Grill, Vacaville, Calif., assignors to Biosource Technologies, Inc., Vacaville, Calif.

Continuation of Ser. No. 923,692, Jul. 31, 1992, Pat. No. 5,316,931, which is a continuation-in-part of Ser. No. 600,244, Oct. 22, 1990, abandoned, Ser. No. 641,617, Jan. 16, 1991, abandoned, Ser. No. 737,899, Jul. 26, 1991, abandoned, and Ser. No. 739,143, Aug. 1, 1991, abandoned, said Ser. No. 600,244 is a continuation of Ser. No. 310,881, Feb. 17, 1989, abandoned, which is a continuation-in-part of Ser. No. 160,766, Feb. 26, 1988, abandoned, and Ser. No. 160,771, Feb. 26, 1988, abandoned, said Ser. No. 641,617 is a continuation of Ser. No. 347,637, May 5, 1989, abandoned, said Ser. No. 737,899 is a continuation of Ser. No. 363,138, Jun. 8, 1989, abandoned, which is a continuation-in-part of Ser. No. 219,279, Jul. 15, 1988, abandoned. This application Jan. 19, 1994, Ser. No. 184,237

Int. Cl.⁶ C12N 15/83; 15/33; 15/68

U.S. Cl. 435—172.3

9 Claims

1. A recombinant plant viral nucleic acid comprising a native plant viral subgenomic promoter, at least one non-native plant viral subgenomic promoter and a plant viral coat protein coding sequence, wherein said native plant viral subgenomic promoter initiates transcription of the plant viral coat protein sequence and said non-native plant viral subgenomic promoter initiates transcription of an operably joined nucleic acid sequence in a host plant and wherein said non-native plant viral subgenomic promoter is incapable of recombination with any other subgenomic promoter of said recombinant plant viral nucleic acid and said recombinant plant viral nucleic acid is expressed systemically in a host plant.

5,589,368

METHOD FOR MAMMALIAN CELL TRANSFECTION

David H. Spear, Playa del Rey, and Peter A. Edwards, Los Angeles, both of Calif., assignors to Regents of the University of California, Oakland, Calif.

Continuation of Ser. No. 899,745, Jun. 17, 1992, Pat. No. 5,330,904. This application Apr. 25, 1994, Ser. No. 232,717

Int. Cl.⁶ C12N 15/00; 1/00; 1/13; C12Q 1/68

U.S. Cl. 435—172.3

23 Claims

12. A process for high-efficiency transfection of a mammalian cell culture comprising:
incubating a cell culture in the presence of a transfection medium comprising a serum and a calcium phosphate-DNA precipitate to produce a transfected cell culture, wherein the serum of the transfection medium is of a different type from the serum used to grow the cell culture.

5,589,369

CELLS HOMOZYGOUS FOR DISRUPTED TARGET LOCI

Jonathan G. Seidman, Milton, Mass., and Aya Jakobovits, Menlo Park, Calif., assignors to Cell Genesys Inc., Foster City, Calif., and The President and Fellows of Harvard College, Cambridge, Mass.

Continuation of Ser. No. 833,992, Feb. 11, 1992, abandoned. This application May 31, 1994, Ser. No. 252,048

Int. Cl.⁶ C12N 15/00; 5/00

U.S. Cl. 435—172.3

11 Claims

1. A method for making diploid mammalian cells homozygous for disrupted target loci, said method comprising:

- introducing into diploid mammalian cells a construct, said construct comprising a selectable marker gene flanked by regions of sequence homology to said loci, wherein said marker gene is a non-amplifiable gene which confers on said cells a preferential ability to grow in a selective medium;
- growing the cells obtained in step (a) in said selective medium at a first level of selective agent and analyzing viable cells to provide a population of cells which have undergone homologous recombination at one or both of the target loci;
- subjecting the population of cells obtained in step (b) to a level of selective agent greater than said first level, whereby cells which have undergone homologous recombination at both loci are selected; and
- isolating said cells obtained in step (c).

5,589,370

PROCESS FOR ENCAPSULATING SENSITIVE MATERIALS

Florencio Ratuiste, Union; Robert Abart, Wayne, both of N.J.; David J. Lang, Ossining, N.Y., and Liang S. Tsaur, Norwood, N.J., assignors to Lever Brothers Company, Division of Conopco, Inc., New York, N.Y.

Filed Aug. 1, 1995, Ser. No. 509,931

Int. Cl.⁶ C12N 9/96; C11D 17/08

U.S. Cl. 264—4.3

7 Claims

1. An improved curing or hardening process for the continuous production of capsules containing an active material which active material is subject to loss of activity upon release in a cleaning product wherein said process comprises:

- mixing
 - said active material subject to loss of activity; and
 - a solution of a cross-linking polymer selected from the group consisting of
 - nonionic water soluble polymers
 - polysaccharides selected from the group consisting of carrageenan, guar gum, pectin, xanthan gum, partially hydrogenated cellulose acetate, hydroxy alkyl cellulose, alkyl cellulose and mixtures thereof;
 - proteins; and
 - mixtures thereof
- into an atomizing device in which the components are atomized into droplets;
- spraying the droplets from said atomizing device onto a film of hardening liquid over a distance of at least 30 centimeters, wherein said liquid is cascading continuously down the wall of a closed vessel containing both said atomizing device and a source of hardening liquid;
- collecting hardened capsules formed when the droplets and hardening liquid are contacted and filtering the capsules from the hardening liquid; and
- recirculating the recovered hardening liquid to the top of said closed vessel where it cascades and contacts the droplets to form additional capsules.

5,589,371

HUMAN MANGANESE SUPEROXIDE DISMUTASE (HMN-SOD)

Konrad Heckl, Heidelberg, Germany; Walter Spevak, Stockerau, Austria; Ellenborg Ostermann, Wien, Austria; Andreas Zöphel, Neulengbach, Austria; Edeltraud Krystek, Wien, Austria; Ingrid Maurer-Fogy, Wien, Austria; Maria J. Wiche-Castanon, Wien, Austria; Christian Stratowa, Wien, Austria, and Rudolf Hauptmann, Ebreichsdorf, Austria, assignors to Boehringer Ingelheim International GmbH, Germany

Continuation of Ser. No. 945,240, Sep. 15, 1992, Pat. No. 5,436,162, which is a continuation of Ser. No. 167,261, Mar. 11, 1988, Pat. No. 5,240,847. This application Mar. 30, 1995, Ser. No. 413,367

Claims priority, application Germany, May 26, 1990, 37 17 695.1; Mar. 14, 1987, 37 08 306.6; Jul. 10, 1987, 37 22 884.6; Dec. 24, 1987, 37 44 038.1

Int. Cl.⁶ C12N 9/02

U.S. Cl. 435—189

2 Claims

1. A method for the preparation of tetrameric human manganese superoxide dismutase (hMn-SOD) consisting of 198 amino acids, comprising

- obtaining a yeast host transformed with a yeast expression vector comprising a cloned gene encoding hMn-SOD consisting of 198 amino acids;
- cultivating said yeast host under conditions which result in the expression of tetrameric hMn-SOD; and
- isolating said tetrameric hMn-SOD.

5,589,372

SQUALENE SYNTHETASE

Gordon W. Robinson, Lawrenceville, N.J., assignor to E. R. Squibb & Sons, Inc., Princeton, N.J.

Continuation of Ser. No. 911,835, Jul. 10, 1992, abandoned, which is a continuation-in-part of Ser. No. 588,235, Sep. 26, 1990, abandoned. This application Dec. 8, 1994, Ser. No. 351,981

Int. Cl.⁶ C12N 1/21; 5/10; 15/54; 15/63

U.S. Cl. 435—193

20 Claims

1. An isolated nucleic acid molecule comprising a sequence coding for the amino acid sequence of FIGS. 2, 8, or 9 (SEQ ID NOS. 2, 4, or 6).

5,589,373

THERMOSTABLE ALKALINE METALLOPROTEASE PRODUCED BY A HYPHOMONAS AND PREPARATION THEREOF

Ronald M. Weiner, Adelphi; Juan Shi, College Park, both of Md., and Vernon E. Coyne, Lakeside, South Africa, assignors to University of Maryland at College Park, College Park, Md.

Continuation of Ser. No. 104,847, Aug. 12, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 478,808

Int. Cl.⁶ C12N 9/52; 15/57; 15/70; 1/22

U.S. Cl. 435—220

28 Claims

1. A native purified thermostable alkaline metalloprotease of *Hyphomomys jannaschiana* having the following properties:
- an optimal activity at a pH of approximately 9.5 at a reaction temperature of about 60° to 65° C.;
 - lack of inhibition by 60 mM phenylmethyl sulfonamide fluoride (PMSF); and
 - a molecular weight of approximately 80,000 daltons.

GATCC GAG ATC TGT GGT ATC GTA ATG GAC GGC CAT TGC GAG AAA
Glu Ile Cys Arg Thr Val Met Asp Gly His Cys Glu Lys

1 5 10

CAG GGC GAT GCT GAG TGC CAC GAC GAC CAG TCC GCT GCT
Gln Gly Asp Ala Cys His Arg Asp Gln Gln Ser Ala Arg

15 20 25

CCG GCG GAT CAG CCG ATA AAT CAG GAT GTA GAA CAG GGT GAT
Pro Ala Asp Gln Arg Ile Asn Gln Asp Val Glu Gln Val Asp

30 35 40

GAC CAG TTC GAA GAA CAG GGT CCA GGC CCG AAC GTT TGC GGC
Asp Gln Phe Glu Glu Gln Gly Pro Gly Arg Asn Val Cys Gly

45 50 55

ATA AAT GTA TTC GAA TTC CG
Ile Asn Val Phe Gly Ser

60

5,589,374

DIABETOGENE RAD: A TYPE II DIABETES SPECIFIC GENE

C. Ronald Kahn, West Newton, and Christine Reynet, Boston, both of Mass., assignors to Joslin Diabetes Center, Inc., Boston, Mass.

Continuation-in-part of Ser. No. 901,710, Jun. 19, 1992, abandoned. This application Jun. 11, 1993, Ser. No. 76,089

Int. Cl.⁶ C12N 15/55; 15/63; 9/16

U.S. Cl. 435—240.1

8 Claims

2. A vector comprising a DNA sequence encoding human rad.

5,589,375

PTP 1D: A NOVEL PROTEIN TYROSINE PHOSPHATASE

Axel Ullrich, Martinsried bei München, and Wolfgang Vogel, Germering, both of Germany, assignors to Max-Planck-Gesellschaft Zur Förderung Der Wissenschaften E. V., Göttingen, Germany

Continuation-in-part of Ser. No. 956,315, Oct. 6, 1992, abandoned. This application Feb. 16, 1993, Ser. No. 18,129

Int. Cl.⁶ C12N 5/06; C07H 21/04

U.S. Cl. 435—240.2

10 Claims

1. An isolated and purified nucleic acid molecule substantially free of nucleotide sequences with which the molecule is natively associated comprising a nucleotide sequence that (a) encodes the protein tyrosine phosphatase 1D amino acid sequence (SEQ ID No. 5); or (b) which hybridizes to the complement of the nucleotide sequence of (a).

5,589,376

MAMMALIAN NEURAL CREST STEM CELLS

David J. Anderson, Altadena, and Derek L. Stemple, Pasadena, both of Calif., assignors to California Institute of Technology, Pasadena, Calif.

Continuation of Ser. No. 920,617, Jul. 27, 1992, abandoned. This application Aug. 15, 1994, Ser. No. 290,228

Int. Cl.⁶ C12N 5/00

U.S. Cl. 435—240.2

10 Claims

1. An isolated population of mammalian neural crest stem cells, wherein said cells are capable of self-renewal in a feeder cell-independent culture medium and capable of differentiation to peripheral nervous system neuronal or glial cells, wherein said neural crest stem cells express low-affinity nerve growth factor receptor (LNGFR) and nestin, but do not express glial fibrillary acidic protein (GFAP), wherein at least one of said isolated population is capable of differentiation to a peripheral nervous system neuronal cell that does not express LNGFR or nestin but does express neurofilament-160, and wherein at least one cell of said

isolated population is capable of differentiation to a peripheral nervous system glial cell that expresses LNGFR, nestin and GFAP.

5,589,377

RECOMBINANT ADENO-ASSOCIATED VIRUS VECTORS

Jane S. Lebkowski, Portola Valley; Maureen A. McNally, and Thomas B. Okarma, both of Palo Alto, all of Calif., assignors to Rhône-Poulenc Rorer Pharmaceuticals, Inc., Collegeville, Pa.

Continuation of Ser. No. 236,642, May 2, 1994, abandoned, which is a division of Ser. No. 993,776, Dec. 21, 1992, Pat. No. 5,354,678, which is a continuation-in-part of Ser. No. 605,775, Oct. 30, 1990, Pat. No. 5,173,414. This application Jun. 6, 1995, Ser. No. 490,095

Int. Cl.⁶ C12N 5/10; 7/01; 15/86

U.S. Cl. 435—240.2

8 Claims

1. A rep/cap vector, wherein said vector is a recombinant adenovirus or herpes virus which comprises adeno-associated virus rep and cap genes, and said adenovirus or herpes virus retains helper functions sufficient to permit adeno-associated virus replication.

5,589,378

Patent Not Issued For This Number

5,589,379

GEMINIVIRUS-BASED GENE EXPRESSION SYSTEM

Jean C. Kridl; George Bruening, both of Davis, and Vic C. Knauf, Winters, all of Calif., assignors to Calgene, Inc., Davis, Calif.

Continuation of Ser. No. 42,103, Apr. 2, 1993, abandoned, which is a continuation of Ser. No. 24,164, Feb. 26, 1993. This application May 23, 1994, Ser. No. 248,859

The portion of the term of this patent subsequent to Feb. 26, 2013, has been disclaimed.

Int. Cl.⁶ C12N 5/04; 15/34; 15/82; 15/83; 15/84

U.S. Cl. 435—240.4

18 Claims

1. A geminivirus transfer vector comprising a plant geminivirus genome wherein the coding sequence for the coat protein gene in said genome is deleted and replaced with a first multiple cloning site and wherein the transcriptional initiation region of the geminivirus transacting factor gene in said genome is replaced with a DNA sequence comprising a transcriptional initiation region of a gene which is expressed other than constitutively in one or more plant cells.

8. A plant cell comprising a geminivirus transfer vector of claim 1.

5,589,380

ISOLATED DNA MOLECULE ENCODING SHET1 OF SHIGELLA FLEXNERI 2A AND MUTANT SHIGELLA FLEXNERI 2A

Alessio Fasano, Ellicott City; Myron M. Levine, Columbia; James P. Nataro, Catonsville, and Fernando Noriega, Columbia, all of Md., assignors to University of Maryland at Baltimore, Baltimore, Md.

Continuation-in-part of Ser. No. 160,317, Dec. 2, 1993, Pat. No. 5,468,639, which is a continuation-in-part of Ser. No. 894,774, Jun. 5, 1992, abandoned. This application Nov. 30, 1994, Ser. No. 351,147

Int. Cl.⁶ C12N 1/20; C12P 21/04; C07K 1/00; C07H 19/00

U.S. Cl. 435—252.3

8 Claims

1. An isolated DNA molecule encoding SHET1 which consists of the amino acid sequence encoded by the DNA of SEQ ID NO: 15.

5,589,381

BACILLUS LICHENIFORMIS PRODUCING ANTIFUNGAL AGENTS AND USES THEREOF FOR CONTROL OF PHYTOPATHOGENIC FUNGI

Carlos A. Neyra, Kendall Park, and Lakshmi Sadasivan, Piscataway, both of N.J., assignors to Rutgers, The State University of New Jersey, Piscataway, N.J.

Filed Jun. 30, 1994, Ser. No. 268,922

Int. Cl.⁶ C12N 1/20; A01N 63/00

U.S. Cl. 435—252.5

12 Claims

1. A method for biologically controlling a plant disease caused by a plant-colonizing fungus, which comprises inoculating a plant requiring disease control with an effective amount of a microbial inoculant comprising a microorganism having all of the identifying characteristics of *Bacillus licheniformis* strain PR1-36a, said inoculation resulting in the control of said plant disease.

5,589,382

BACILLUS THURINGIENSIS GENES ENCODING NEMATODE-ACTIVE TOXINS

Jewel Payne, Davis; Kenneth E. Narva, and Jenny Fu, both of San Diego, all of Calif., assignors to Mycogen Corporation, San Diego, Calif.

Continuation-in-part of Ser. No. 310,197, Sep. 21, 1994, and Ser. No. 357,698, Dec. 16, 1994, which is a division of Ser. No. 176,403, Dec. 30, 1993, abandoned, which is a continuation-in-part of Ser. No. 999,053, Dec. 31, 1992, abandoned, said Ser. No. 310,197 is a division of Ser. No. 92,155, Jul. 15, 1993, Pat. No. 5,350,577, which is a division of Ser. No. 918,345, Jul. 21, 1992, Pat. No. 5,270,448, which is a division of Ser. No. 558,738, Jul. 27, 1990, Pat. No. 5,151,363. This application Jun. 7, 1995, Ser. No. 485,568

Int. Cl.⁶ C12N 1/20; A01N 63/00

U.S. Cl. 435—252.5

8 Claims

1. A polynucleotide sequence from a *Bacillus thuringiensis* isolate selected from the group consisting of PS80J1, PS158D5, PS167P, PS169E, PS177F1, PS177G, PS204G4, and PS204G6, which encodes a toxin active against nematodes.

5,589,383

PROTEASE DELETION

Alan Sloma, Watertown; Gerald A. Rufo, Jr., Burlington; Cathy F. Rudolph, Stoughton; Barbara J. Sullivan, Burlington, and Janice Pero, Lexington, all of Mass., assignors to Omnigene, Inc., Cambridge, Mass.

Division of Ser. No. 579,401, Sep. 7, 1990, which is a continuation-in-part of Ser. No. 396,521, Aug. 21, 1989, abandoned, which is a continuation-in-part of Ser. No. 347,428, May 4, 1989, abandoned, which is a continuation-in-part of Ser. No. 273,423, Nov. 18, 1988, abandoned. This application Aug. 12, 1994, Ser. No. 285,477

Int. Cl.⁶ C12N 1/21; 9/54; 15/57; 15/75

U.S. Cl. 435—252.31

3 Claims

1. An isolated and purified DNA molecule encoding a *Bacillus* residual protease 1 (bpr).

5,589,384

FUSION PROTEINS

Martin J. Lipscombe, Cambridge; Ian G. Charles, and Neil F. Fairweather, both of Beckenham, all of United Kingdom, assignors to Glaxo Wellcome Inc., Research Triangle Park, N.C.

Continuation of Ser. No. 896,003, Jun. 11, 1992, abandoned.

This application May 2, 1994, Ser. No. 237,716

Claims priority, application United Kingdom, Jun. 11, 1991, 9112553.4

Int. Cl.⁶ C12N 15/61; 1/00; 1/21; 15/63; C07K 14/28; 14/24

U.S. Cl. 435—252.33 25 Claims

1. A fusion protein comprising the following elements linked in an N-terminal to C-terminal direction:

- (A) sufficient of the B subunit of cholera toxin or heat-labile enterotoxin of *Escherichia coli* such that the fusion protein forms a pentamer complex and binds to GM₁-ganglioside;
- (B) a hinge of from two to eight directly linked glycineproline repeats; and
- (C) a predetermined antigen or epitope of a human or animal pathogen, which antigen or epitope effects an immune response.

5,589,385

CLONING OF THE BIOSYNTHETIC PATHWAY FOR CHLORTETRACYCLINE AND TETRACYCLINE FORMATION AND COSMIDS USEFUL THEREIN

Michael J. Ryan, West Milford; Jason A. Lotvin, Union, both of N.J.; Nancy Strathy, Monsey, N.Y., and Susan E. Fantini, Ridgewood, N.J., assignors to American Cyanamid Company, Wayne, N.J.

Continuation-in-part of Ser. No. 821,109, Jan. 15, 1992, abandoned, and Ser. No. 821,419, Jan. 15, 1992, abandoned, which is a continuation of Ser. No. 558,039, Jul. 26, 1990, abandoned, said Ser. No. 821,109 is a continuation of Ser. No. 558,040, Jul. 26, 1990, abandoned. This application Sep. 22, 1993, Ser. No. 125,468

Int. Cl.⁶ C12N 1/21; 15/52; 15/76

U.S. Cl. 435—258.35 13 Claims

1. A purified and isolated nucleic acid molecule encoding the proteins of the biosynthetic pathway for tetracycline, chlortetracycline, 6-demethylchlortetracycline, demethyltetracycline, 7-chloro-5a, 11a-dehydrotetracycline or 2-decarboxamido-2-acetyl tetracycline, wherein said nucleic acid molecule is isolated from an antibiotic-producing wild-type or mutant *Streptomyces*.

5,589,386

HYDROLYSIS OF CHOLINESTERASE INHIBITORS USING PARATHION HYDROLASE

Cuneyt M. Serdar, 1844 Rivendell Cir., Newbury Park, Calif. 91320

Continuation-in-part of Ser. No. 237,255, Aug. 26, 1988. This application Feb. 17, 1989, Ser. No. 312,503

Int. Cl.⁶ C12S 13/00; C12N 15/00; 1/20; 1/14

U.S. Cl. 435—262.5 4 Claims

1. A method for the hydrolysis of a cholinesterase inhibitor comprising an organophosphate, said method comprising treating the cholinesterase inhibitor with a purified and isolated biologically active substance selected from the group consisting of mature parathion hydrolase and a methionine (-1) analog thereof, said parathion hydrolase having enhanced specific activity as a result of having been produced in a microorganism cultivated in a culture medium comprising greater than 0.15 mM but not more than 3.0 mM of a metal selected from the group consisting of cobalt, zinc and a mixture of cobalt and zinc.

5,589,387

METHOD FOR PREVENTING THE ACCUMULATION OF INORGANIC DEPOSITS ON CONTACT LENSES

Daniel P. Cafaro, Santa Ana, Calif., assignor to Allergan, Inc., Irvine, Calif.

Division of Ser. No. 132,606, Oct. 6, 1993, Pat. No. 5,447,650.

This application Jun. 6, 1995, Ser. No. 470,910

Int. Cl.⁶ C11D 3/06; 7/16

U.S. Cl. 435—264 15 Claims

1. A method for preventing the accumulation of inorganic deposits on a contact lens comprising the step of treating the lens with a solution comprising

- (A) hydrogen peroxide and
- (B) a composition comprising
 - (i) at least one sequestering agent selected from the group consisting of sodium borogluconate and sodium gluconate and
 - (ii) a neutralizing system capable of reducing the hydrogen peroxide in an exothermic reaction producing heat at a temperature of at least 30° C. without external application of heat, thereby activating said sequestering agent wherein the lens is treated with the solution for a period of time sufficient to prevent the accumulation of inorganic deposits thereon.

5,589,388

HOT-COMPOSTING APPARATUS

Esko Hanhikoski, Leipurintie 9, FIN-00620 Helsinki, Finland


PCT No. PCT/FI93/00028, § 371 Date Jul. 29, 1994, § 102(e) Date Jul. 29, 1994, PCT Pub. No. WO93/15033, PCT Pub. Date Aug. 5, 1993

PCT Filed Jan. 29, 1993, Ser. No. 256,919

Claims priority, application Finland, Jan. 30, 1992, U920086

Int. Cl.⁶ C05F 9/02

U.S. Cl. 435—290.3 9 Claims



1. A hot-composting apparatus for household use comprising a drum having a geometric longitudinal axis, said drum comprising: heat insulated casing wall having a polygonal form; heat insulated gable walls, wherein the heat insulated casing walls and the heat insulated gable walls are constructed and arranged to provide an internal composting space, and the heat insulated gable walls are constructed and arranged to provide support for rotation about the geometric longitudinal axis of the drum; an intermediate wall unit positioned in the composting space and which has a form corresponding substantially to the polygonal form of the drum, and which divides the drum into departments in a plane which is substantially perpendicular in relation to the geometric longitudinal axis of the drum, wherein the intermediate wall unit comprises at least one movable intermediate wall element which can be shifted in a direction along the geometric longitudinal axis of the drum to a location between the gable walls, and which is perforated to provide air dehtles for conveying air from one composting department into another; means for opening and closing the drum comprising a two part cover, which cover substantially forms one section of the casing wall; shiftable plate elements provided under one part of the two part cover;

wherein the casing wall and the gable walls are substantially air-tight and heat insulated so that inner and outer surface layers are air-tight and a layer therebetween is heat insulated; at least one gable wall includes an openable and closable air dehtle for conveying air in a sufficient amount to maintain microbe actions in the internal composting space; and widths of parts of the cover in the direction of the geometric longitudinal axis of the drum are selected such that adjacent edges of the parts of the cover meet the intermediate wall unit when the intermediate wall unit is positioned in the middle of the drum.

5,589,389

APPARATUS FOR CAUSING MEDICINAL PRODUCTS TO PENETRATE INTO RED BLOOD CELLS

Etienne Pages; Claude Ropars, both of Saint-Avertin, and Christophe Bailleul, Montfermeil, all of France, assignors to Fondation Nationale de Transfusion Sanguine, Paris Cedex, France


PCT No. PCT/FR92/00623, § 371 Date Jan. 3, 1994, § 102(e) Date Jan. 3, 1994, PCT Pub. No. WO93/00940, PCT Pub. Date Jan. 21, 1993

PCT Filed Jul. 2, 1992, Ser. No. 170,352

Claims priority, application France, Jul. 3, 1991, 91 08302

Int. Cl.⁶ C12M 1/12; 3/06

U.S. Cl. 435—306.1 20 Claims



1. An apparatus for introducing at least one biologically active substance into erythrocytes, comprising: a settling bowl for removing plasma, leucocytes, platelets of blood, and adjusting hematocrit and controlling osmolarity of blood, and for obtaining erythrocytes suspended in a solution of a product to be internalized; a lysis unit for cooling the erythrocyte suspension obtained from the settling bowl and introducing the active substance into the cooled erythrocyte suspension, the lysis unit having cooling means for maintaining the erythrocyte suspension at a temperature less than 10° C., a dialysis cartridge for receiving the cooled erythrocyte suspension and a first collection pouch for receiving the erythrocyte suspension processed by the dialysis cartridge, and means for introducing the active substance into the first pouch along with the processed erythrocyte suspension; and a resealing unit for heating the erythrocyte suspension treated with the active substance from the first pouch and introducing a resealing product into the heated and treated erythrocyte suspension, the resealing unit having heating means for maintaining the temperature of the treated erythrocyte suspension greater than 20° C., a second collection pouch for receiving and holding the heated and treated erythrocyte suspension, and means for introducing the resealing product into the second pouch along with the heated and treated erythrocyte suspension.

5,589,390

VERMIN EXTERMINATING ELEMENT AND VERMIN EXTERMINATING METHOD


Toshio Higuchi; Yasuhiro Fukushima; Kenji Furumori; Kazuhiro Yamamoto, and Minoru Ouchi, all of Osaka, Japan, assignors to Nitto Denko Corporation, Osaka, Japan

Continuation of Ser. No. 124,435, Sep. 22, 1993, abandoned, which is a continuation of Ser. No. 7,015, Jan. 21, 1993, abandoned, which is a continuation of Ser. No. 700,151, Jul. 11, 1991, abandoned. This application Jun. 7, 1995, Ser. No. 479,840

Claims priority, application Japan, Sep. 11, 1989, 1-234969; Mar. 23, 1990, 2-74598

Int. Cl.⁶ C12N 1/00; C12M 1/00

U.S. Cl. 435—307.1 19 Claims



19. A method for exterminating vermin which comprises applying a vermin exterminating element to a stem or branch of a tree from which vermin are to be exterminated, wherein said vermin exterminating element comprises a culture carrier which comprises nonwoven cloth or woven cloth impregnated with medium components for cultivating a microorganism, wherein a culture solution of a vermin infectious microorganism is impregnated together with the medium components, wherein said vermin exterminating element is dried after cultivating said vermin infectious microorganism, and said nonwoven or woven cloth has a thickness of 1.8 mm or more and has a base weight of at least 100 g/m².

5,589,391


ROTATABLE COMPOSTING DEVICE

Thomas M. Fink, 6 Bassett Pl., Fairfield, Ohio 45014

Filed Dec. 21, 1993, Ser. No. 170,787

Int. Cl.⁶ C12M 1/10

U.S. Cl. 435—290.3 17 Claims



1. A composting device comprising, a support base unit, a hollow enclosed tumbler drum of polygonal shaped cross-section having sidewalls and endwalls, said drum comprising a unitary rigid polygonal shaped end frame surrounding each endwall and directly secured thereto, a plurality of discrete boards extending between and secured to the end frames to form the sidewalls of the drum, an angle corner covering and reinforcing member secured to said boards along the exterior of each corner of said polygonal shaped drum, a door in said drum for loading material into said

drum, said drum being mounted on said base unit for rotation about a horizontal central longitudinal axis through the endwalls of the drum, wherein the support base unit is rectangular in plan and comprises upright corner leg members and wherein the leg members at opposite ends of the base unit are connected at their upper ends by a cross-member which supports a respective end of said drum, said sidewalls being constructed such that cracks are formed between each adjacent board whereby air may enter the drum.

5,589,392

NUCLEIC ACID CONSTRUCT ENCODING A NUCLEAR TRANSPORT PEPTIDE OPERATIVELY LINKED TO AN INDUCIBLE PROMOTER

Jay M. Short, Encinitas, Calif., assignor to Stratagene, La Jolla, Calif.

Continuation of Ser. No. 640,983, Jan. 14, 1991, abandoned.

This application Nov. 29, 1993, Ser. No. 158,718

Int. Cl.⁶ C12N 15/09; 15/63; C07H 21/02; 21/04

U.S. Cl. 435—320.1

2 Claims

1. A nucleic acid construct comprising a DNA sequence encoding a nuclear transport signal peptide operatively linked to a DNA sequence encoding an inducible repressor, where the nuclear transport signal peptide is from an SV40 large T antigen and the inducible repressor is a lac inducible repressor protein, and wherein said DNA sequences are operatively linked to a promoter.

5,589,393

METHOD FOR PREPARING A GLYCATED HEMOGLOBIN SOLUTION

Michael D. Flechtner, Highland Park; John M. Ramp, Gurnee, both of Ill.; Barbara J. England, Milwaukee, Wis., and Mary J. Annino, Arlington Heights, Ill., assignors to Abbott Laboratories, Abbott Park, Ill.

Division of Ser. No. 717,558, Jun. 19, 1991, abandoned. This application Apr. 24, 1995, Ser. No. 427,508

Int. Cl.⁶ G01N 33/96

U.S. Cl. 436—15

8 Claims

1. A method for preparing a stable glycated hemoglobin solution useful as a calibrator or control in an assay for glycated hemoglobin comprising:

- washing erythrocytes;
- releasing hemoglobin from the erythrocytes into a solution;
- removing lipids from the hemoglobin solution;
- oxidizing the hemoglobin to met-hemoglobin;
- converting the met-hemoglobin to azido-met-hemoglobin or cyano-met-hemoglobin; and
- adding glucose to the azido-met-hemoglobin or cyano-met-hemoglobin to form glycated azido-met-hemoglobin or glycated cyano-met-hemoglobin.

5,589,394

CELL SUSPENSION PREPARATION APPARATUS AND METHOD

Young R. Kim, Sunnyvale; Kenneth E. Iles, Los Altos, and Roderick W. Larue, Sebastopol, all of Calif., assignors to Abbott Laboratories, Abbott Park, Ill.

Continuation-in-part of Ser. No. 283,379, Aug. 1, 1994, abandoned. This application Dec. 15, 1994, Ser. No. 356,412


Int. Cl.⁶ H01N 35/10

U.S. Cl. 436—63

24 Claims

1. A method for preparing a solution made from a first predetermined volume of a first fluid and a second predetermined volume of a second fluid, the method comprising the steps of:

- operating a heater attached to a first housing and movable with the first housing for receiving the first fluid and the second fluid to apply thermal energy to the first housing, the first housing being operatively connected with and disposed substantially within a second housing;



(h) introducing the second predetermined volume of the second fluid to the first housing;

(c) vibrating the first housing with a prime mover to move the second predetermined volume of the second fluid in the first housing for a first predetermined time period while second housing remains substantially stationary with respect to the prime mover;

(d) introducing the first predetermined volume of the first fluid to the first housing;

(e) vibrating the first housing with the prime mover to move the first predetermined volume of first fluid and the second predetermined volume of second fluid in the first housing for a second predetermined time period to make the solution while the second housing remains substantially stationary with respect to the prime mover; and

(f) removing the solution made from the first predetermined volume of first fluid and the second predetermined volume of second fluid from the first housing.

5,589,395

METHOD FOR STABILIZING ANNEXINS

Jürgen Römsch; Bernhard Auerbach, and Hermann Pelzer, all of Marburg, Germany, assignors to Behringwerke Aktiengesellschaft, Marburg, Germany

Continuation of Ser. No. 629,718, Dec. 18, 1990, abandoned.

This application Apr. 15, 1993, Ser. No. 46,908

Claims priority, application Germany, Dec. 20, 1989, 39 42 081.7

Int. Cl.⁶ G01N 33/92; 11/00

U.S. Cl. 436—71

7 Claims

1. A method for stabilizing annexins in a biological fluid sample comprising the steps of:

- obtaining the biological fluid sample; and
- bringing said sample into contact with an agent containing an anticoagulant, a chelate-forming agent and at least one aggregation inhibiting substance, said aggregation inhibiting substance selected from the group consisting of chloroquine, hydroxychloroquine, quinacrine, camoquine, dibucaine, lidocaine, procaine, tetracaine, chlorpromazine, trifluoparazine, reserpine, acetylsalicylic acid, indomethacin, poquazone, prenylamine lactate, perhexiline maleate, nifedipine, verapamil and pentoxifylline.

5,589,396

COATINGS WITH CONTROLLED POROSITY AND CHEMICAL PROPERTIES


Gregory C. Frye, Bernalillo County; C. Jeffrey Brinker, Albuquerque; Daniel H. Doughty, Albuquerque; Thomas Bein, Albuquerque, and Karin Moller, Albuquerque, all of N.M., assignors to Sandia Corporation, Albuquerque, N.M.

Continuation of Ser. No. 686,548, Apr. 18, 1991, Pat. No. 5,224,972, which is a continuation-in-part of Ser. No. 580,373, Sep. 11, 1990, Pat. No. 5,151,110. This application Feb. 1, 1993, Ser. No. 11,518

Int. Cl.⁶ B01D 53/04

U.S. Cl. 436—73

23 Claims




5,589,399

SYSTEM AND METHOD FOR PLASMA SEPARATION AND MEASUREMENT

Michael P. Allen, Los Altos; Robert F. Zuk, Burlingame, and Lawrence M. Ensler, Los Altos, all of Calif., assignors to First Medical, Inc., Mountain View, Calif.
Filed Oct. 21, 1994, Ser. No. 326,974
Int. Cl.⁶ G01N 21/01

U.S. Cl. 436-169

19 Claims



1. A system for transferring measured amounts of plasma from unmeasured blood samples to a test substrate, said system comprising:

- an applicator having a blood-receiving reservoir with a predetermined plasma capacity and a single plasma transfer port having a cross-sectional area and shape in fluid communication with the reservoir and including a filter member extending across the plasma transfer port, wherein the filter member permits the passage of plasma and plasma macromolecules but inhibits the passage of blood cells;
- a plasma-receiving test substrate having a surface; and
- at least one reaction zone on the substrate surface; and
- a single absorptive element on the substrate surface having a contact surface with a shape and area substantially identical to those of the port so that the contact surface is configured to engage the plasma transfer port and a plasma capacity which is less than the plasma capacity of the reservoir, wherein plasma transferred from the reservoir will saturate the absorptive element to provide a measured amount of plasma on the substrate; and wherein the at least one reaction zone is spaced from said single absorptive element.

5,589,400

METHOD OF DISTRIBUTING MATERIAL ONTO A MICROSCOPE SLIDE OF A LARGE CYTOLOGY SAMPLE CHAMBER

William J. Hayes, Edgeworth, Pa., assignor to Shandon, Inc., Pittsburgh, Pa.


Division of Ser. No. 355,630, Dec. 14, 1994, Pat. No. 5,470,758. This application Aug. 18, 1995, Ser. No. 516,916
Int. Cl.⁶ G01N 9/30

U.S. Cl. 436-177

8 Claims

1. A method of distributing biological material suspended in a liquid sample onto a microscope slide during centrifugation of said sample comprising the steps of:

- (a) directing said liquid sample into a centrifuge sample chamber fastened to a microscope slide whereby said sample advances downwardly along a tortuous path of vertically spaced surfaces in said chamber prior to centrifugation, each of said vertically spaced surfaces being in communication



- with a discharge opening from said chamber to one surface of said microscope slide;
- (b) directing said sample into said chamber until at least a portion of said biological material is deposited on portions of at least one of said vertically spaced surfaces; followed by
- (c) centrifuging said sample chamber whereby said biological material on each of said surfaces passes through said discharge opening onto said one surface of said slide.

5,589,401

LIGHT SCATTER-BASED IMMUNOASSAY WITHOUT PARTICLE SELF AGGREGATION

W. Peter Hansen, 20 E. 35th St., Apt. 7G, New York, N.Y. 10016, and Michael Cennerazzo, 9 Oak St., Weehauken, N.J. 07087

Continuation of Ser. No. 994,903, Dec. 22, 1992, abandoned.
This application Aug. 5, 1994, Ser. No. 286,778

Int. Cl.⁶ G01N 33/538; 33/544; 33/553

U.S. Cl. 436-525

36 Claims

1. A particle light scatter-based immunoassay for measuring an analyte in a fluid sample, comprising the steps of:

- a) combining with said fluid sample a reagent set including first binding molecule-coated monodisperse microspheres and second binding molecule-coated colloidal metal particles smaller than said microspheres or an immunocomplex comprising said monodisperse microspheres and said colloidal metal particles, to form a mixture and allow a reaction to occur, wherein at least one of said first and second binding molecules binds said analyte, said reaction being formation or decomplexation of said immunocomplex, so that the reacted mixture includes said microspheres in uncomplexed form, in said immunocomplex or both, the degree of binding of said microspheres in said reacted mixture with said colloidal metal particles being dependent upon presence or amount of said analyte in said fluid sample;
- b) measuring light scattered by said microspheres in said reacted mixture by means of an optical flow particle analyzer to thereby provide light scatter signals for said microspheres;
- c) determining a dimension of a statistical distribution of said light scatter signals from said microspheres in said reacted mixture, such that the dimension of said statistical distribution varies with the degree of binding of said microspheres with said colloidal metal particles in said reacted mixture; and
- d) correlating said dimension of said statistical distribution of said light scatter signals for said microspheres in said reacted mixture with the amount of said analyte in said fluid sample.

5,589,402

PROCESS FOR MANUFACTURING A PACKAGE FOR MATING WITH A BARE SEMICONDUCTOR DIE



Kenneth C. Ramsey, Gilbert; William J. Miller, Mesa, and William M. Strom, Chandler, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Continuation of Ser. No. 155,880, Nov. 23, 1993, abandoned.
This application Oct. 30, 1995, Ser. No. 550,416

Int. Cl.⁶ H01L 21/56; 21/60; 21/70

U.S. Cl. 437-2

20 Claims



- 1. A method of manufacturing a package for mating with a bare semiconductor die, comprising the steps of: providing a leadframe having at least one lead wherein the at least one lead has a plurality of ends; encapsulating a portion of the leadframe to form the package, wherein at least two ends of the at least one lead exit the package; and mating the bare semiconductor die externally to the package.

5,589,403

METHOD FOR PRODUCING PHOTOVOLTAIC DEVICE


Noboru Toyama, and Katsumi Nakagawa, both of Nagahama, Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 341,948, Nov. 16, 1994, Pat. No. 5,500,055, which is a continuation of Ser. No. 13,109, Feb. 3, 1993, abandoned. This application Mar. 18, 1996, Ser. No. 573,996

Claims priority, application Japan, Feb. 5, 1992, 4-20052
Int. Cl.⁶ H01K 31/18

U.S. Cl. 437-2

5 Claims



- 1. A method for producing a photovoltaic device provided with a metal layer with a smooth surface, a transparent layer composed of

a plurality of layers on said metal layer, and a photovoltaic layer on said transparent layer, which comprises utilizing the difference in forming temperatures of said plural layers of said transparent layer and forming an irregular surface structure in a first said layer in contact with the smooth surface of said metal layer, and satisfying a relation $T1 > Tn$ between the forming temperature of T1 of said first layer the forming temperature Tn of the second to the nth layers, wherein said layer forming temperatures are numbered as the first layer forming temperature T1, the second layer forming temperature T2 . . . Tn from the metal layer side.

5,589,404


MONOLITHICALLY INTEGRATED VLSI OPTOELECTRONIC CIRCUITS AND A METHOD OF FABRICATING THE SAME

John E. Cunningham, Lincroft; Keith W. Goossen, Aberdeen; William Y. Jan, Scotch Plains; Rajiv N. Pathak, Matawan, and James A. Walker, Howell, all of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Aug. 1, 1994, Ser. No. 284,026
Int. Cl.⁶ H01L 31/18

U.S. Cl. 437-5

15 Claims



- 1. A process for fabricating a smart pixel array on a compound semiconductor surface having a preexisting VLSI electronic circuit on the surface, comprising the steps of: thermally activating the compound semiconductor surface while directing an atomic gas plasma at the compound semiconductor surface for removing substantially all surface contaminants from the compound semiconductor surface to form a substantially impurity free compound semiconductor surface; and growing a plurality of optical devices on said compound semiconductor surface at a temperature below 500° C.

5,589,405

METHOD FOR FABRICATING VDMOS TRANSISTOR WITH IMPROVED BREAKDOWN CHARACTERISTICS

Claudio Contiero, Buccinasco; Paola Galbiati, Monza, and Lucia Zullino, Milan, all of Italy, assignors to SGS-Thomson Microelectronics, S.r.l., Agrate Brianza, Italy

Division of Ser. No. 19,124, Feb. 17, 1993, Pat. No. 5,430,316.
This application Apr. 21, 1995, Ser. No. 403,629


Claims priority, application Italy, Feb. 18, 1992, M192A0344
Int. Cl.⁶ H01L 49/00

U.S. Cl. 437-6

21 Claims

1. A method for fabricating vertical-current-flow field-effect transistors, comprising the steps of:

- (a.) providing a substrate which includes at least one substantially monolithic volume of semiconductor material having a first conductivity type in proximity to a first surface thereof, and having a buried layer of a high concentration of said first conductivity type therebelow;
- (b.) implanting said first surface with dopants having a second conductivity type, to form body regions in locations;
- (c.) forming thick insulator regions to cover substantially all of said surface except for active area locations;
- (d.) implanting said first surface with dopants of said first conductivity type, to form source regions within said body regions;
- (e.) forming insulated gate regions on said first surface which are each capacitively coupled to at least some portion of said body region at said first surface;



- (f.) forming ohmic contacts to said source regions; and
(g.) forming ohmic contacts to said buried layer;
wherein ones of said source, gate, and body regions are formed to define at least one matrix comprising a plurality of cells, each cell comprising at least a portion of one of said source regions and a portion of one of said body regions, said matrix being laterally surrounded by a portion of said thick insulator region which is underlain by a field-isolation diffusion which is electrically connected to said body region of at least some ones of said cells of said matrix, and which is overlain by a field plate which is electrically connected to said gate region.

5,589,406


METHOD OF MAKING TFT DISPLAY

Naoki Kato, and Masaya Kunigita, both of Yokohama, Japan, assignors to AG Technology Co., Ltd., Yokohama, Japan
Filed Jul. 29, 1994, Ser. No. 282,433
Claims priority, application Japan, Jul. 30, 1993, 5-208393
Int. Cl.⁶ H01L 21/84

U.S. Cl. 437—21

11 Claims

1. A method which comprises:




forming an amorphous semiconductor layer on a substrate;
irradiating beam spots on the amorphous semiconductor layer;
scanning linearly the beam spots at scanning speed ≥ 10 m/s;
beam-annealing for polycrystallization the amorphous semiconductor layer to form a polycrystalline semiconductor layer;
forming stripes in the polycrystalline semiconductor layer;
forming semiconductor islands in the stripes; and
forming polycrystalline semiconductor channels for a pixel-drive-TFT, a row-drive-TFT and a column-drive-TFT in the semiconductor islands.

5,589,407
METHOD OF TREATING SILICON TO OBTAIN THIN, BURIED INSULATING LAYER
Narayanan Meyyappan, Camas, and Tatsuo Nakato, Vancouver, both of Wash., assignors to Implanted Material Technology, Inc.

Filed Sep. 6, 1995, Ser. No. 524,039
Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—26

21 Claims



1. A method of forming a buried insulating film in a silicon substrate comprising the following steps:
(a) providing an ion source of a species A;
(b) forming an ion beam from the ion source;
(c) implanting ions into the substrate using the ion beam of step (b) to a depth, d_1 ;
(d) annealing the doped substrate in an atmosphere having an amount of a second species, B, therein;
(e) diffusing species B into the substrate during annealing to the depth of (c);
(f) reacting species B with the substrate and implanted species A, thereby forming a buried layer of insulating material within the substrate.

5,589,408


METHOD OF FORMING AN ALLOYED DRAIN FIELD EFFECT TRANSISTOR AND DEVICE FORMED

Francine Y. Robb; Stephen P. Robb, both of Tempe, and Paul J. Groenig, Chandler, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Jul. 5, 1995, Ser. No. 498,158
Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—29

15 Claims



1. A method of forming an alloyed drain field effect transistor, comprising the steps of:
providing a semiconductor substrate, the semiconductor substrate having a first major surface, a second major surface, and being of N-type conductivity and a first concentration;
forming at least one region of a P-type conductivity, the at least one region of the P-type conductivity extending into the semiconductor substrate;
forming at least one N-type conductivity region in the at least one region of the P-type conductivity, the at least one N-type conductivity region extending into the at least one region of the P-type conductivity;
forming a first layer of dielectric material overlying the first major surface;
patterning the first layer of dielectric material to expose portions of the at least one N-type conductivity region and the at least one region of P-type conductivity;

forming an electrically conductive material overlying the first major surface, wherein the electrically conductive material is patterned and electrically coupled to the exposed portions of the at least one region of the P-type conductivity and the at least one N-type conductivity region; and
forming a P-type region by alloying a metal-semiconductor contact with said semiconductor substrate, wherein the alloyed metal-semiconductor contact is comprised of a metal that dopes the semiconductor substrate to form a P-type region.

than three times the minimum distance t_{BMIN} by which the main intrinsic base portion vertically separates the emitter and a main collector region of the first conductivity type underlying the main intrinsic base portion.


5,589,410

AN INTEGRATED SEMICONDUCTOR DEVICE HAVING A BURIED SEMICONDUCTOR LAYER AND FABRICATION METHOD THEREOF

Noriaki Sato, and Fumitake Mieno, both of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan
Division of Ser. No. 699, Jan. 5, 1993, Pat. No. 5,362,981. This application Jul. 22, 1994, Ser. No. 279,205
Claims priority, application Japan, Jan. 7, 1992, 4-000548
Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—40

5 Claims



1. A method for production of an integrated semiconductor device comprising the steps of:

- (a) forming a surface portion of a first conductivity type in a semiconductor substrate, wherein the surface portion borders a surface of the semiconductor substrate;
(b) forming an insulating layer on the semiconductor substrate, with a window exposing the surface portion;
(c) forming a semiconductor layer of the first conductivity type selectively on the surface portion within the window;
(d) forming an insulating gate film on a surface of the semiconductor layer within the window of the insulating layer;
(e) subsequently to said step (d), forming a buried semiconductor layer of the first conductivity type with an upper surface and a lower surface, wherein the upper surface is in the semiconductor layer;
(f) forming an insulated gate electrode on the insulating gate film across the window; and
(g) forming a first region of the first conductivity type and a pair of second regions of a second conductivity type opposite to the first conductivity type bordering the surface of the semiconductor layer, wherein the first region of the first conductivity type is between the pair of second regions of the second conductivity type.

5,589,411


PROCESS FOR FABRICATING A HIGH-VOLTAGE MOSFET

Sheng-Hsing Yang, Hsinchu, and Shing-Ren Sheu, Taoyuan, both of Taiwan, assignors to United Microelectronics Corporation, Hsinchu, Taiwan
Filed Jul. 28, 1995, Ser. No. 508,515
Int. Cl.⁶ H01L 21/265

U.S. Cl. 437—41

7 Claims

1. A process for fabricating a high-voltage MOSFET device on a semiconductor substrate doped with impurities of a first conductivity type as the drain region for said MOSFET device, said process comprising:



subsequently forming a first doped layer of the first conductivity type on said substrate, a second doped layer of the first conductivity type on said first doped layer, a third doped layer of the first conductivity type on said second doped layer and a shielding layer on said third doped layer, wherein said second doped layer has an impurity concentration smaller than the impurity concentration of said first doped layer and a thickness larger than the thickness of said first doped layer, and larger impurity concentration than the third doped layer and a smaller thickness than said third doped layer, and wherein said impurity concentration of said first doped layer is smaller than the impurity concentration of said substrate;

forming an opening in said shielding layer;

forming the source region of said MOSFET device in said third doped layer in the area exposed by said opening;

performing a thermal oxidation process for forming a field oxide layer over said source region;

etching said third doped layer by using said field oxide layer as a first mask thereby exposing said second doped layer to form a source protruding body;

forming an insulating layer around the sidewalls of said source protruding body; and

utilizing said field oxide layer and said insulating layer as a second mask for implanting impurities of a second conductivity type into said second doped layer, thereby forming the gate region for said MOSFET device.

5,589,412


METHOD OF MAKING INCREASED-DENSITY FLASH EPROM THAT UTILIZES A SERIES OF PLANARIZED, SELF-ALIGNED, INTERMEDIATE STRIPS OF CONDUCTIVE MATERIAL TO CONTACT THE DRAIN REGIONS

Ali Iranmanesh, Sunnyvale; John M. Pierce, Palo Alto, and Albert M. Bergemont, Santa Clara, all of Calif., assignors to National Semiconductor Corporation, Santa Clara, Calif. Continuation of Ser. No. 269,892, Jul. 1, 1994, abandoned, which is a division of Ser. No. 207,858, Mar. 8, 1994, abandoned, which is a continuation-in-part of Ser. No. 168,756, Dec. 16, 1993, Pat. No. 5,416,349. This application Jun. 1, 1995, Ser. No. 456,548

Int. Cl.⁶ H01L 21/8247

U.S. Cl. 437—43

8 Claims



1. A method of fabricating a high-density flash electrically programmable read-only-memory (EEPROM) array, the method comprising the steps of:

providing a semiconductor substrate of P-type conductivity;

forming a plurality of spaced-apart field oxide regions on the semiconductor substrate;

forming a plurality of first implanted channel regions in the semiconductor substrate so that a pair of first implanted channel regions are formed between each pair of horizontally-adjacent field oxide regions, and so that each first implanted channel region adjoins both of the adjacent field oxide regions, each implanted channel region having a first side and a second side;

forming a layer of first gate dielectric material on the semiconductor substrate;

forming a layer of first conductive material over the layer of first gate dielectric material;

forming a layer of intermediate dielectric material over the layer of first conductive material;

etching the layer of intermediate dielectric material and the layer of first conductive material to define a plurality of strips of dielectric/conductive material;

forming a layer of second conductive material over the strips of dielectric/conductive material, the field oxide regions, and the semiconductor substrate;

forming a layer of third conductive material over the layer of second conductive material;

forming a layer of first insulation material over the layer of third conductive material;

etching the layer of first insulation material, the layer of third conductive material, and the layer of second conductive material to form a plurality of word lines;

etching the layer of intermediate dielectric material and the layer of first conductive material to form a plurality of floating gate memory cells;

forming a plurality of N⁺ buried drain regions in the semiconductor substrate so that each drain region adjoins the first side of each pair of implanted channel regions;

forming a plurality of common source bit lines in the semiconductor substrate so that the second side of each implanted channel region formed in one row of implanted channel regions and the second side of each implanted channel region formed in an adjacent row of implanted channel regions are adjoined by one common source bit line;

forming a plurality of strips of second insulation material so that each strip of second insulation material is formed over one common source bit line;

forming a plurality of strips of spacer material so that each strip of spacer material covers a portion of each drain region and each horizontally-adjacent field oxide region in each row of drain regions, and adjoins one word line, the underlying stacked gate structures, and the overlying layer of first insulation material;

forming a plurality of planar, intermediate interconnect strips over the strips of second insulation material, the strips of spacer material, the layers of first insulation, and the drain regions so that each planar, intermediate interconnect strip interconnects each drain region in one column of drain regions, each planar, intermediate interconnect strip having a substantially flat top surface;

forming a layer of third insulation material having a plurality of metal bit line openings formed therethrough over the strips of second insulation material, the strips of spacer material, the layers of first insulation material, the semiconductor substrate, and the plurality of planar, intermediate interconnect strips so that each planar, intermediate interconnect strip is periodically exposed by a metal bit line opening; and

forming a plurality of metal bit lines over the layer of third insulation material and the exposed portion of each planar, intermediate interconnect strip so that each metal bit line interconnects the exposed portions of one intermediate interconnect strip.

5,589,413

METHOD OF MANUFACTURING SELF-ALIGNED BIT-LINE DURING EPROM FABRICATION


Hung-Cheng Sung, Paoshan Hsin-Chu, Taiwan, and Ling Chen, Sunnyvale, Calif., assignors to Taiwan Semiconductor Manufacturing Company, Hsinchu, Taiwan

Filed Nov. 27, 1995, Ser. No. 562,868

Int. Cl.⁶ H01L 21/8247

U.S. Cl. 437—43

20 Claims U.S. Cl. 437—44



1. A method for manufacturing EPROM integrated circuit memory devices which comprises the steps of:

providing a semiconductor substrate having devices therein to which electrical connections are to be made;

forming a tunnel oxide layer on said substrate;

forming a blanket, doped, polysilicon layer over said tunnel oxide layer on said substrate;

forming an interelectrode dielectric layer over said blanket, doped, polysilicon layer;

forming a blanket polycide layer over said interelectrode dielectric layer;

forming a silicon dioxide dielectric layer over said blanket polycide layer;

forming a silicon nitride (Si₃N₄) layer over said silicon dioxide layer;

forming a source/drain mask over said silicon nitride layer with source/drain trench openings therein said source trench openings being substantially more narrow than said drain trench openings;

etching to form EPROM gate electrode stacks with trench spaces between said stacks in an array of said stacks, said stacks being formed by said silicon nitride (Si₃N₄) layer, said silicon dioxide dielectric layer, said polycide layer, said interelectrode dielectric layer, and said polysilicon layer down to said tunnel oxide layer;

said EPROM gate stacks having sidewalls with said trench spaces therebetween, said trench spaces between said sidewalls including source trench spaces over said source regions and drain trench spaces over said drain regions, said source trench spaces being substantially more narrow than said drain trench spaces;

ion implanting of source/drain dopant ions between said stacks forming alternating source regions and drain regions below said spaces between said sidewalls;

forming spacer dielectric structures adjacent to said sidewalls over said drain regions leaving narrow drain spaces therebetween and spacer dielectric plugs completely filling said spaces over said source regions;

forming a blanket dielectric layer over said stacks, said spaces and said sidewalls;

etching bit-line conductor openings across said device and drain trench openings through said blanket dielectric layer down to said drain regions;

forming a bit-line conductive metal blanket layer over said device extending down into contact with said drain regions through said drain trench openings;

etching back said conductive metal blanket layer leaving conductor lines in contact with said drain regions;

whereby said EPROM memory devices include a self-aligned bit-line structure formed simultaneously with electrical contacts to the drain electrodes.

5,589,414


METHOD OF MAKING MASK ROM WITH TWO LAYER GATE ELECTRODE

Yeh-Jye Wann, Taipei, and Hsien-Tsong Liu, Keelung, both of Taiwan, assignors to Taiwan Semiconductor Manufacturing Company Ltd., Hsin-Chu, Taiwan

Filed Jun. 23, 1995, Ser. No. 494,585

Int. Cl.⁶ H01L 21/8246

21 Claims



1. A process of manufacture of a semiconductor device adapted for inclusion in a semiconductor memory system, formed on a semiconductor substrate covered with a gate oxide layer between field oxide regions, comprising:

forming a blanket lower lamina for a gate electrode on the surface of said gate oxide layer and said field oxide regions;

forming a mask contacting said lower lamina with a mask code opening therethrough over a location for the gate electrode;

forming a doped code implant region in said substrate by ion implanting code implant through said Mask code opening into said code implant region;

removing said mask;

forming a blanket upper lamina of said gate electrode on the surface of said lower lamina;

forming a gate mask over said upper lamina and said lower lamina, said gate mask patterned to protect the gate location and leaving the remainder of said upper and lower lamina as exposed surfaces;

etching away all exposed surfaces of said upper and lower lamina unprotected by said gate mask leaving a laminated gate electrode formed by the remainder of said upper lamina and said lower lamina;

forming lightly doped regions in said substrate between said field oxide regions and said gate by ion implanting dopant through portions of said gate oxide layer unprotected by said gate electrode;

forming dielectric spacers adjacent to said gate electrode, and forming heavily doped source and drain regions in said substrate between said field oxide regions and said spacers adjacent to said gate electrode by ion implanting dopant through portions of said gate oxide layer unprotected by said spacers and said gate electrode.

5,589,415

METHOD FOR FORMING A SEMICONDUCTOR STRUCTURE WITH SELF-ALIGNED CONTACTS

Richard A. Blanchard, Los Altos, Calif., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Filed Jun. 7, 1995, Ser. No. 472,336


Int. Cl.⁶ H01L 21/70

U.S. Cl. 437—57

16 Claims

1. An integrated circuit fabrication method, comprising the steps of:

(a.) forming a first patterned thin-film polycrystalline semiconductor layer to provide insulated gates over first and second crystalline semiconductor regions, said second crystalline



semiconductor region having a first conductivity type and said first crystalline semiconductor region having a second conductivity type;

- (b.) forming an interlevel dielectric over said first patterned thin film polycrystalline semiconductor layer;
 - (c.) depositing a second polycrystalline semiconductor layer which at least partly overlies said interlevel dielectric, and patterning said second polycrystalline semiconductor layer to expose first portions, but not second portions, of said first and second crystalline semiconductor regions;
 - (d.) doping a first portion of said second polycrystalline semiconductor layer with first-conductivity-type dopants, and simultaneously doping any exposed portions of said first crystalline semiconductor regions;
 - (e.) doping a second portion of said second polycrystalline semiconductor layer with second-conductivity-type dopants, and simultaneously doping said first portions of said second crystalline semiconductor regions; and
 - (f.) cladding said second polycrystalline semiconductor layer with a cladding layer of metallic conductivity which shunts at least some of the lateral junctions between said first and second portions of said second polycrystalline layer;
- whereby said steps c), d), and e) create an asymmetrical source/drain structure.


5,589,416

PROCESS FOR FORMING INTEGRATED CAPACITORS
Salleh Chittipeddi, Austin, Tex., assignor to Lucent Technologies Inc., Murray Hill, N.J.

Filed Dec. 6, 1995, Ser. No. 568,040
Int. Cl.⁶ H01L 21/70

U.S. Cl. 437—60

5 Claims



1. Process for the manufacture of an integrated circuit including a capacitor, the capacitor comprising a first plate, a capacitor dielectric, and a second plate, the process comprising the steps of:
 - a. growing a field oxide layer on a silicon substrate;
 - b. depositing a layer of polysilicon on the field oxide;
 - c. depositing a capacitor dielectric layer comprising silicon dioxide on the polysilicon layer;
 - d. lithographically forming a pattern in the capacitor dielectric layer to form an oxide hardmask, said pattern defining a mask for the first plate of said capacitor, and said mask also serving as the capacitor dielectric;
 - e. removing the unmasked portions of the polysilicon layer using the oxide hardmask as an etch mask, thereby exposing portions of the field oxide;

- f. forming a blanket insulating layer over the oxide hardmask and the exposed portions of the field oxide;
- g. anisotropically etching said blanket insulating layer to form sidewall spacers on the vertical edges of the etched polysilicon and hardmask of the capacitor;
- h. depositing a blanket layer of titanium-nitride;
- i. masking the titanium layer with a mask corresponding essentially to the mask used to form the hardmask;
- j. patterning the titanium nitride layer to form the second plate of the capacitor;
- k. depositing an insulating layer over the patterned titanium nitride layer;
- l. opening a contact window to said second plate of the capacitor;
- m. depositing a metal layer over the contact window; and
- n. etching said metal layer to form a contact to said second capacitor plate.

5,589,417


TISI/TIN CLAD INTERCONNECT TECHNOLOGY
Shin-Puu Jeng, Plano, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 369,562, Jan. 6, 1995, which is a continuation of Ser. No. 186,828, Jan. 24, 1994, abandoned, which is a continuation of Ser. No. 3,209, Jan. 12, 1993, abandoned.

This application Jun. 7, 1995, Ser. No. 481,665
Int. Cl.⁶ H01L 21/28

U.S. Cl. 437—190

8 Claims



1. A process for forming a local interconnect comprising: depositing a refractory metal layer over a substrate which includes silicon; annealing the structure thus formed by the foregoing process step in a first ambient gas so as to form a first barrier metal material adjacent a first silicide region; depositing a refractory metal on said first barrier metal material; depositing silicon on said refractory metal deposited on said first barrier metal material; annealing the structure thus formed by the foregoing process steps in a second ambient gas so as to form a second barrier metal material adjacent a conductive region; and substantially etching away exposed regions of said first and said second barrier metal materials.

5,589,418

METHOD OF FORMING A POLYSILICON BURIED CONTACT
Alexander Kalnitsky, San Francisco, Calif., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Division of Ser. No. 102,529, Aug. 4, 1993, Pat. No. 5,410,174.
This application Nov. 21, 1994, Ser. No. 342,863
Int. Cl.⁶ H01L 21/44

U.S. Cl. 437—193

18 Claims

1. A method of forming a buried contact of an integrated circuit comprising the steps of:

5,589,420


METHOD FOR A HYBRID LEADFRAME-OVER-CHIP SEMICONDUCTOR PACKAGE

Ernest J. Russell, Richmond, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.


Division of Ser. No. 304,988, Sep. 13, 1994. This application Jun. 7, 1995, Ser. No. 475,446
Int. Cl.⁶ H01L 21/60

U.S. Cl. 437—220

4 Claims



- forming a field oxide region over a portion of a substrate leaving an exposed active region;
- forming an oxide layer over the active region;
- forming a first silicon layer over the oxide layer and the field oxide region;
- forming and patterning a first photoresist layer over the first silicon layer;
- etching the first silicon layer to form an opening therethrough exposing a portion of the oxide layer;
- etching the oxide layer through the opening exposing a portion of the substrate;
- forming a conductive etch stop layer over the exposed portion of the substrate and the first photoresist layer;
- removing the first photoresist layer and the etch stop layer disposed over the first photoresist layer;
- forming a second silicon layer over the first silicon layer and the remaining etch stop layer;
- forming and patterning a second photoresist layer over the second silicon layer; and
- etching the first and second silicon layers to form a conductive structure contacting the exposed portion of the substrate through the etch stop layer.



1. A method for electrically coupling bonding pads of a semiconductor component to a leadframe with a conducting wire, wherein said leadframe is positioned in a leadframe-over-chip with respect to said semiconductor component, wherein said bonding pads form at least one row in a center portion of said semiconductor component generally parallel to an edge of said semiconductor component, said method comprising the steps of:
 - locating a bonding finger of a leadframe conducting lead in an off-chip position;
 - bonding a first end of said conducting wire to said off-chip bonding finger; and
 - bonding a second end of said conducting wire to a selected semiconductor component bonding pad.

5,589,419

PROCESS FOR FABRICATING SEMICONDUCTOR DEVICE HAVING A MULTILEVEL INTERCONNECTION
Akihiko Ochiai, Kanagawa, Japan, assignor to Sony Corporation, Japan


Filed Jul. 21, 1995, Ser. No. 505,786

Claims priority, application Japan, Jul. 26, 1994, 6-194873
Int. Cl.⁶ H01L 21/283

U.S. Cl. 437—795

6 Claims

1. A process for fabricating a semiconductor device having a



- multilevel interconnection, comprising:
 - forming a trench on the surface of a first substrate to provide an element isolating region;
 - forming a first insulating film on the surface of the trench and the first substrate;
 - forming a first interconnection layer on the surface of the first insulating film;
 - forming a second insulating film on the surface of the first substrate in such a manner that the first interconnection layer is covered and the trench is filled;
 - forming a second interconnection layer on the second insulating film;
 - forming sequentially in this order, a third insulating film and an adhesion layer on the surface of said second insulating film covering the second interconnection layer;
 - bonding a second substrate on the surface of the adhesion layer; planarizing the back of the first substrate by removing the first substrate from the back side thereof and the bottom of the trench; and
 - forming a fourth insulating film on the back of the first substrate, and forming a third interconnection layer on the fourth insulating film.

5,589,421

METHOD OF MANUFACTURING ANNEALED FILMS
Naoto Miyashita, Yokohama; Koichi Takahashi, Kawasaki; Mitsutoshi Koyama, Tokyo; Shinji Nunotani, Yokohama; Satoshi Yanagiya, Kawasaki, and Yoshiro Baba, Yokohama, all of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Division of Ser. No. 98,245, Jul. 29, 1993, abandoned, which is a continuation of Ser. No. 732,762, Jul. 19, 1991, abandoned. This application Sep. 1, 1994, Ser. No. 300,067

Claims priority, application Japan, Jul. 20, 1990, 2-192100; Mar. 19, 1991, 3-080688

Int. Cl.⁶ H01L 21/302; 21/463

U.S. Cl. 437—225

6 Claims



1. A method of manufacturing thermally annealed films, comprising the steps of:
 - decreasing internal temperature of a furnace to 150° C. or less;
 - inserting a semiconductor wafer into the furnace;
 - increasing the internal temperature of the furnace to a first temperature;
 - reducing internal pressure of the furnace to a first pressure;
 - decreasing the internal temperature for a second time to a second temperature necessary for forming a reaction film, the second temperature being higher than the first temperature;
 - increasing the internal pressure of the furnace to a second pressure;

forming the reaction film after the internal temperature of the furnace is decreased to the second temperature and the internal pressure of the furnace is increased to the second pressure; then decreasing the internal temperature of the furnace for a third time to 150° C. at a rate of 10° C. or more/min.; and removing the semiconductor wafer from furnace after the internal temperature of the furnace is decreased to 150° C.

5,589,422

CONTROLLED, GAS PHASE PROCESS FOR REMOVAL OF TRACE METAL CONTAMINATION AND FOR REMOVAL OF A SEMICONDUCTOR LAYER


Suresh A. Bhat, Fremont, Calif., assignor to Intel Corporation, Santa Clara, Calif.

Filed Jan. 15, 1993, Ser. No. 5,475

Int. Cl.⁶ H01L 21/311; 21/316

U.S. Cl. 437—228

29 Claims



1. A process for treating a semiconductor layer to remove contaminants and impurities therein, comprising the steps of:
 - a) oxidizing at least a portion of said semiconductor layer in a gaseous first ambient comprising ozone, said first ambient being oxidizing, to form an oxidized layer, wherein a portion of said semiconductor layer is consumed; and
 - b) etching at least a portion of said oxidized layer in a second ambient, said second ambient being gaseous, to expose a surface;
 wherein said semiconductor layer is maintained in an absence of UV radiation and at a temperature within a range of approximately room temperature to 300° C. during and between steps a and b.

5,589,423

PROCESS FOR FABRICATING A NON-SILICIDED REGION IN AN INTEGRATED CIRCUIT

Ted R. White; Ting-Chen Hsu; Bradley M. Somero; Mark A. Chonko, and Jung-Hui Lin, all of Austin, Tex., assignors to Motorola Inc., Schaumburg, Ill.


Filed Oct. 3, 1994, Ser. No. 317,045

Int. Cl.⁶ H01L 21/70; 21/700; 21/465; 21/306

U.S. Cl. 437—228

16 Claims

1. A process for fabricating a non-silicided region in an integrated circuit comprising the steps of:
 - providing a substrate having a silicide blocking layer overlying a dielectric layer;
 - forming a carbonaceous mask on a first portion of the silicide blocking layer and leaving a second portion exposed;



partially etching the second portion of the silicide blocking layer using the carbonaceous mask as an etching mask; removing the carbonaceous mask; etching away the second portion of the silicide blocking layer, after removing the carbonaceous mask, to expose a portion of the dielectric layer; etching away the portion of the dielectric layer; and forming a silicide layer in the portion of the substrate, after etching away the portion of the dielectric layer.

5,589,424

PHOTODEFINABLE DIELECTRIC LAYERS COMPRISING POLY(AROMATIC DIACETYLENES)

Elizabeth W. Kwock, Califon, and Timothy M. Miller, New Providence, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Division of Ser. No. 173,284, Dec. 22, 1993. This application

Oct. 17, 1995, Ser. No. 543,900

Int. Cl.⁶ H01L 21/312

U.S. Cl. 437—229

3 Claims

1. In the method of making a multichip module comprising the steps of providing a substrate, applying conductors and resistors to a surface of the substrate, applying a layer of photodefinable dielectric material to said surface, exposing selected portions of said layer to light and developing the exposed layer to define a pattern of dielectric, the improvement wherein:
 - said photodefinable dielectric material comprises a copolymer of diethynylidiphenyl ether and an aromatic diacetylene.

5,589,425

PROCESS OF SELECTIVE AREA CHEMICAL VAPOR DEPOSITION OF METAL FILMS

Masataka Hoshino, and Nobuhiro Misawa, both of Kawasaki, Japan, assignors to Fujitsu Limited, Kanagawa, Japan

Filed Nov. 29, 1994, Ser. No. 350,036


Claims priority, application Japan, Feb. 9, 1994, 6-035159

Int. Cl.⁶ C23C 16/00

U.S. Cl. 427—250

5 Claims

1. A process of growing a film of a noble metal on a substrate in a selective area thereof by chemical vapor deposition, said process comprising the steps of:
 - preparing a source material having a molecule comprising a noble metal and a hexafluoroacetylacetonate radical (C₆HF₅O₂);
 - providing a substrate having a selective area made of a first substance which is unreactive with said radical and an other area made of copper which is reactive with said radical; and
 - supplying said source material onto said substrate held at a film growing temperature to induce a reaction on said substrate, such that, in said selective area, said molecule of said source material is bonded to said first substance and decomposed to precipitate said noble metal on said first substance while, in said other area, said radical of said molecule is combined with



said copper to cover said other area of said substrate with a coating which is unreactive with said molecule of said source material.

5,589,426

MONOLITHIC REFRACTORIES

Itsutoshi Iwasaki; Tatsuo Yamasaki, and Hideaki Sawada, all of Fukuoka-ken, Japan, assignors to Taikorozei Co., Ltd., Fukuoka-ken, Japan

Filed Jul. 9, 1993, Ser. No. 89,677

Claims priority, application Japan, Jul. 14, 1992, 4-209743

Int. Cl.⁶ C04B 35/66

U.S. Cl. 501—32

1 Claim

1. Monolithic refractories comprising 100% by weight of refractory aggregate powders, and in addition thereto, based on the weight of said powders, 0.05 to 5% by weight of a binder selected from the group consisting of phosphate glass mainly composed of P₂O₅-Al₂O₃-Na₂O-K₂O, and hydroxycarboxylates and combinations of the phosphate glass and hydroxycarboxylates, and 0.01 to 1% by weight of a thickener, characterized in that said monolithic refractories have been kneaded with water or other kneading liquid,
 - wherein the thickener is a cellulose compound or a copolymer of maleic anhydride and isobutylene, wherein hydroxycarboxylates are glycolate, tartrate, lactate and citrate, the metal of which is lithium, sodium, potassium or aluminum.

5,589,427

SUBSTANTIALLY SPHERICAL PARTICLES OF LITHIUM SILICATES WITH IMPROVED MECHANICAL PROPERTIES AND IMPAIRED SURFACE QUALITY

Mario Dalle Donne, Stutensee; Guster Schumacher, Karlsruhe; Volkmar Geller, Mainz; Marc Clement, Mainz, and Burkhard Speit, Mainz, all of Germany, assignors to Schott Glaswerke, Mainz, Germany

PCT No. PCT/EP93/00671, § 371 Date Dec. 29, 1994, § 102(e)

Date Dec. 29, 1994, PCT Pub. No. WO93/19474, PCT Pub.

Date Sep. 30, 1993

PCT Filed Mar. 19, 1993, Ser. No. 307,693


Claims priority, application Germany, Mar. 24, 1992, 42 09 420.8

Int. Cl.⁶ C04B 35/16

U.S. Cl. 501—33

14 Claims

1. A composition comprising particles of lithium orthosilicate, wherein said particles further contain tellurium, a tellurium compound, or combinations thereof.



5,589,428

SILICON CARBIDE WITH CONTROLLED POROSITY

Ramesh Divakar, and Sai-Kwing Lau, both of East Amherst, N.Y., assignors to The Carborundum Company, Worcester, Mass.

Continuation of Ser. No. 295,956, Aug. 25, 1994, abandoned, which is a division of Ser. No. 65,037, May 25, 1993, Pat. No. 5,395,807, which is a continuation-in-part of Ser. No. 23,769, Feb. 26, 1993, abandoned, which is a continuation-in-part of

Ser. No. 910,042, Jul. 8, 1992, abandoned. This application

Jun. 5, 1995, Ser. No. 464,919

Int. Cl.⁶ C04B 35/56; 35/576

U.S. Cl. 501—88

20 Claims

1. A silicon carbide sintered body comprising controlled porosity in the range of about 2 to about 12 volume percent, said pores being distributed uniformly throughout the body, substantially independent, closed, essentially spherical in shape, and having a nominal diameter between about 50 microns and about 500 microns.

5,589,429

ALUMINUM NITRIDE SINTERED BODY AND PROCESS FOR PRODUCING THE SAME

Kenzo Kawaguchi; Tetsuya Takemura; Hideki Matsubara; Sinya Takagi, and Atsushi Kanda, all of Aichi, Japan, assignors to NGK Spark Plug Co., Ltd., Aichi, Japan


Filed Dec. 27, 1994, Ser. No. 364,497

Claims priority, application Japan, Dec. 27, 1993, 5-352132

Int. Cl.⁶ C04B 35/58

U.S. Cl. 501—96

7 Claims



1. An aluminum nitride sintered body comprising aluminum nitride as a main component, a titanium compound, and an yttrium compound, wherein when the content of titanium and the content of yttrium both in terms of percentage by weight based on said

aluminum nitride sintered body are plotted on an x-y coordinate system, with the titanium content as the x axis and the yttrium content as the y axis, the titanium content and the yttrium content each is within a region surrounded by the lines connecting points A and B, B and C, C and D, D and E, and E and A, inclusive of the lines, said points A, B, C, D and E being:

- A (0.2, 2.0)
- B (0.2, 6.5)
- C (1.0, 10.25)
- D (2.2, 10.25)
- E (2.2, 5.0).

5,589,430

DENSELY SINTERED, TABULAR CERAMIC PARTS OF ALUMINUM OXIDE HAVING IMPROVED THERMAL SHOCK RESISTANCE

Wolfgang Krahn; Johannes Ernst, both of Marktredwitz, and Claudia Drabent, Fuchsmühl, all of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Germany
Division of Ser. No. 188,678, Jan. 31, 1994, Pat. No. 5,518,974.
This application Dec. 29, 1995, Ser. No. 580,859


Claims priority, application Germany, Feb. 2, 1993, 43 02 795.4

Int. Cl.⁶ C04B 35/44

U.S. Cl. 501—120

13 Claims

Dependence of Fracture Resistance During Thermal Shocking on Test Piece Size



1. A densely sintered ceramic part, comprising aluminum oxide and magnesium as $MgAl_2O_4$, which is added in the form of non-agglomerated MgO having an average particle size d_{50} of at most 0.8 μm , wherein said part has improved shock thermal resistance and a fine porosity of at most 10% by volume, and wherein said part does not contain any inclusions having a diameter of $\geq 70 \mu m$ within the ceramic microstructure and wherein said ceramic part is not cracked or fractured on immersion in a molten bath having a temperature of at least 350° C.

5,589,431

DOUBLE METAL CYANIDE COMPLEX CATALYSTS

Bi Le-Khac, West Chester, Pa., assignor to ARCO Chemical Technology, L.P., Greenville, Del.

Division of Ser. No. 156,534, Nov. 23, 1993, Pat. No. 5,470,813. This application Jun. 7, 1995, Ser. No. 476,479

Int. Cl.⁶ B01J 27/26

U.S. Cl. 502—175

9 Claims

1. A method of preparing an epoxide polymer, said method comprising polymerizing an epoxide in the presence of a catalyst which comprises at least about 70 wt. % of a substantially amorphous double metal cyanide complex.

5,589,432 EXHAUST GAS CLEANER AND METHOD FOR CLEANING SAME

Kiyohide Yoshida; Gyo Muramatsu; Akira Abe, and Naoko Irite, all of Kumagaya, Japan, assignors to Kabushiki Kaisha Riken, Tokyo, Japan


Division of Ser. No. 171,679, Dec. 22, 1993, abandoned. This application May 4, 1995, Ser. No. 434,915

Claims priority, application Japan, Dec. 28, 1992, 4-360377; Feb. 15, 1993, 5-48613; May 10, 1993, 5-132581; May 12, 1993, 5-133954; May 26, 1993, 5-146917; Jul. 20, 1993, 5-200391

Int. Cl.⁶ B01J 23/72; B01D 51/00

U.S. Cl. 502—325

12 Claims



1. An exhaust gas cleaner having an inlet side and an outlet side for removing nitrogen oxides from an exhaust gas containing nitrogen oxides and oxygen in an amount larger than its stoichiometric amount relative to unburned components in said exhaust gas, which consists essentially of a first catalyst on the inlet side of said exhaust gas cleaner and a second catalyst on the outlet side of said exhaust gas cleaner, said first catalyst consisting essentially of 0.2–15 weight % of silver or silver oxide supported on a porous inorganic oxide, and said second catalyst consisting essentially of 0.2–15 weight % of silver or silver oxide and up to 2 weight % of copper or copper oxide supported on a porous inorganic oxide.

5,589,433

THERMAL TRANSFER SYSTEMS HAVING VANADIUM OXIDE ANTISTATIC LAYERS


Eric D. Morrison, West St. Paul; Jeffrey C. Chang, North Oaks, and Linda K. Williams, St. Paul, all of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Division of Ser. No. 15,419, Feb. 9, 1993, abandoned. This application Jun. 23, 1994, Ser. No. 264,463

Int. Cl.⁶ B41M 5/035; 5/38

U.S. Cl. 503—227

8 Claims



1. A thermal transfer donor sheet comprising a flexible substrate having a frontside and a backside, a colorant layer coated on the frontside, and a vanadium oxide antistatic layer coated on the backside wherein the vanadium oxide antistatic layer comprises needle-shaped vanadium oxide particles in intimate contact with other vanadium oxide particles.

5,589,434

RECEPTOR LAYER TRANSFER SHEET, THERMAL TRANSFER SHEET, THERMAL TRANSFER METHOD AND APPARATUS THEREFOR

Hidetake Takahara; Takeshi Ueno; Katsuyuki Oshima; Mikio Asajima, and Mineo Yamauchi, all of Tokyo-to, Japan, assignors to Dai Nippon Printing Co., Ltd., Tokyo-to, Japan
Division of Ser. No. 103,360, Aug. 6, 1993, Pat. No. 5,424,267.


This application Mar. 7, 1995, Ser. No. 399,845

Claims priority, application Japan, Jul. 27, 1990, 2-197806; Sep. 27, 1990, 2-255165; Sep. 27, 1990, 2-255166; Nov. 29, 1990, 2-325470; Dec. 25, 1990, 2-412857; Jan. 17, 1991, 3-15697; Jan. 17, 1991, 3-15699; Apr. 22, 1991, 3-116609

Int. Cl.⁶ B41M 5/035; 5/38

U.S. Cl. 503—227

8 Claims



1. A receptor layer transfer sheet comprising a substrate sheet and a transferable layer disposed on one side surface of the substrate sheet, the transferable layer being peelable from the substrate sheet and comprising a dye receptor layer, wherein the transferable layer has an adhesive layer disposed thereon by the medium of an intermediate layer, and at least one layer selected from the dye receptor layer, intermediate layer and the adhesive layer contains bubbles.

5,589,435

SHEET CAPABLE OF RELEASING A THERMAL TRANSFER IMAGE-RECEIVING LAYER, A METHOD FOR TRANSFERRING A THERMAL TRANSFER IMAGE-RECEIVING LAYER FROM THE SHEET AND A METHOD FOR FORMING IMAGES

Kengo Ito, Miyagi; Kaori Isaji, Chiba; Yoshio Fujiwara, Tochigi; Mitsuhiko Isogai, and Masanobu Hida, both of Tokyo, all of Japan, assignors to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 242,418, May 13, 1994, Pat. No. 5,446,012. This application Jun. 6, 1995, Ser. No. 471,767

Claims priority, application Japan, May 19, 1993, 5-141585

Int. Cl.⁶ B41M 5/035; 5/38

U.S. Cl. 503—227

10 Claims



5. A method for transferring a thermal transfer image-receiving layer from an image transfer sheet to a substrate comprising the steps of:

providing a transfer sheet of the type including a release base sheet and a thermal transfer image-receiving layer formed on the release base sheet, said image-receiving layer being a dispersion including a resin binder and a dye-fixing amount of a layer compound capable of fixing cationic dyes through ion exchange reaction therewith, said layer compound being selected from the group consisting of: montmorillonite, magnesium montmorillonite, iron montmorillonite, iron magnesium montmorillonite, heidellite, aluminum heidellite, nontroite, aluminum nontroite, saponite, aluminum saponite, hectorite, sauconite, halogen-substituted compounds of any of

the foregoing, sodium silicic mica, sodium taeniolite and lithium taeniolite, cation exchangeable alkali metal cations and alkaline earth metal cations in said layer compound having been replaced by organic cations selected from the group consisting of alkyl-substituted quaternary ammonium ions and alkyl-substituted phosphonium ions, wherein said alkyl group substituents have not less than 8 carbon atoms; superposing the image transfer sheet on a substrate, on which a thermal transfer image is to be formed in such a way that said image-receiving layer is in face-to-face relation with the substrate; and peeling off the release base sheet from the image transfer sheet.

5,589,436

AGENT FOR PRESERVING THE FRESHNESS OF PLANTS

Hideaki Hagiwara, Takarazuka, and Toshiaki Suzuki, Kasai, both of Japan, assignors to Yoshitake Hagiwara, and HIH Biocenter, Inc., both of Takarazuka, Japan

Filed May 30, 1995, Ser. No. 453,467

Claims priority, application Japan, May 30, 1994, 6-137855

Int. Cl.⁶ A01N 3/02

U.S. Cl. 504—114

10 Claims

1. A method for preserving the freshness of cut flowers, cut sprays, cut leaves or a potted plant which comprises applying an effective amount of 2'-O-glucosylisovitexin thereto.

5,589,437

METHOD OF USING 5-HYDROXYBENZIMIDAZOLE COMPOUNDS FOR REDUCING TRANSPIRATION IN PLANTS

Klara D. Vichnevetskaia, Faculty of Forestry, University of Toronto, 33 Wilcocks St.; Terence J. Blake, Faculty of Forestry, University of Toronto, both of Toronto, Ontario, Canada; Eddie Bevilacqua, 3 Rutherford Avenue, Toronto, County of York, Province of Ontario, Canada, and Timothy J. B. Boyle, City of Bogor, Province of West Java, Indonesia


Filed Jun. 13, 1994, Ser. No. 258,806

Int. Cl.⁶ A01N 43/40; 43/52; 43/84; 43/90

U.S. Cl. 504—225

8 Claims

1. A method of using a compound of the structural formula



wherein:

nMa connotes that the hydroxybenzimidazole derivative structurally presented above is a mineral acid salt; n is an integer 1 through 6; MA is a mineral acid selected from the group consisting of HNO_3 , H_2SeO_4 , $HClO_4$, $HBrO_4$, $HMnO_4$, HSO_3F , H_2SO_4 , $H_2S_2O_7$, H_3PO_4 , H_3BO_3 , HF , HCl , HBr , HI , and mixtures thereof; R is hydrogen, dimethylamino, piperidinyl or morpholino; and R^1 is hydrogen or dimethylaminomethyl.

comprising applying a drought resistance enhancing amount of at least one of the above mentioned compounds to plants or seeds in need of having their drought resistance increased.

5,589,438

DRY FLOWABLE POWDERS OF HYGROSCOPIC PLANT GROWTH REGULATORS AND TABLETS FORMED OF THE SAME


Rudolph E. Lisa, Riverview; Terence K. Kilbride, Bloomfield Hills, both of Mich., and Karl-Friedrich Jager, Lumburgerhof, Germany, assignors to BASF Corporation, Mt. Olive, N.J.

Division of Ser. No. 95,122, Jul. 20, 1993, Pat. No. 5,468,720. This application Mar. 30, 1995, Ser. No. 415,124

Int. Cl.⁶ A01N 25/12; 43/40; 43/58

U.S. Cl. 504—236

20 Claims



1. A dry, flowable powder of a plant growth regulator formulation comprising a mixture of (i) a solid particulate consisting essentially of at least 95% by weight of a hygroscopic plant growth regulator, and (ii) an effective amount between 0.2 to 3 parts by weight per 100 parts by weight of the plant growth regulator of an inert flow aid sufficient to inhibit hygroscopicity of said plant growth regulator such that said powder remains free-flowing and non-caking.

5,589,439

TETRAZOLINONE DERIVATIVES

Toshio Goto, Shimotsuga-gun; Koichi Moriya, Oaza; Fritz Maurer, Tochigi; Seishi Ito, Oyama; Katsuaki Wada, Tochigi; Kazuhiro Ukawa, Oyama; Ryo Watanabe, Tochigi; Asami Ito, Tochigi, and Natsuko Minegishi, Tochigi, all of Japan, assignors to Nihon Bayer Agrochem K.K., Tokyo, Japan

Filed Jul. 28, 1995, Ser. No. 508,776


Claims priority, application Japan, Aug. 5, 1994, 6-202919; Mar. 3, 1995, 7-068837

Int. Cl.⁶ A01N 43/82; 43/824; 43/828; 43/832; C07D 409/04; 407/04; 405/04; 403/04; A01N 43/836; 43/713; C07D 417/04; 413/04

U.S. Cl. 504—261

12 Claims

1. A substituted tetrazolinone of the formula



wherein

R¹ is alkyl, haloalkyl, cycloalkyl, alkenyl, haloalkenyl, alkynyl, alkoxy or phenyl which is optionally substituted;

R² is alkyl, haloalkyl, cycloalkyl, alkenyl, haloalkenyl, alkynyl, alkoxy, or phenyl of which is optionally substituted; or

R¹ and R² form, together with the nitrogen atom to which they are bonded, a 5- or 6-membered heterocyclic ring, optionally fused to a carboxylic ring and optionally substituted by C₁₋₄ alkyl,

and

R³ is a 5-membered heterocyclic radical containing at least one hetero atom selected from the group consisting of nitrogen, oxygen and sulfur, optionally substituted by at least one substituent selected from the group consisting of halogen, benzyl, phenyl, halogen-substituted phenyl, C₁₋₄ alkyl, C₁₋₄

alkoxy, C₁₋₄ haloalkyl, C₁₋₄ haloalkoxy, C₁₋₄ alkylthio, C₁₋₄ alkyl-sulfonyl and C₃₋₈ cycloalkyl.

5,589,440

FERROELECTRIC RF LIMITER


Satyendranath Das, P.O. Box 574, Mountain View, Calif. 94042-0574

Continuation-in-part of Ser. No. 70,738, May 27, 1993, Pat. No. 5,329,261. This application Mar. 9, 1994, Ser. No. 207,750

Int. Cl.⁶ H01P 1/22; H01B 12/06

U.S. Cl. 505—210

20 Claims



1. A ferroelectric waveguide limiter having an input, output, flanges and comprising of:
a main waveguide of appropriate length;
a first tapered branch guide being connected in series with the said main waveguide and having a length of one or more half wavelengths at the operating frequency of the limiter;
a first reduced height branch guide at the end of the tapered first branch guide;
a ferroelectric material being connected across the reduced height and in the middle of the reduced height branch guide at the junction of the tapered guide at the point of the maximum electric field, being one or more half wavelengths, at the operating frequency of the limiter, from the main waveguide forming a variable capacitor of a parallel resonant circuit tuned to the operating frequency of the limiter;
an appropriate length of the said reduced height first branch guide, behind the ferroelectric material, forming an inductance of a parallel resonant circuit tuned to the operating frequency of the limiter;
a waveguide short being connected at the end of the reduced height first branch guide;
a large level of input signal, at which the capacitance of the ferroelectric material and the inductance of the shorted reduced height first branch guide form parallel resonance tuned to the operating frequency of the limiter;
said limiter being operated slightly above the Curie temperature of the ferroelectric material; and
voltage means for applying a bias electric field to the ferroelectric material to set the zero signal operating point.

5,589,441

SUPERCONDUCTIVE FIBERFORM CERAMIC COMPOSITE

Anna L. Baker, Seattle, and Michael Strasik, Renton, both of Wash., assignors to The Boeing Company, Seattle, Wash.

Continuation of Ser. No. 833,862, Feb. 11, 1992, abandoned, which is a division of Ser. No. 381,498, Jul. 18, 1989, abandoned, which is a continuation-in-part of Ser. No. 698,496, Feb. 5, 1985, Pat. No. 5,041,321, which is a continuation-in-part of Ser. No. 667,568, Nov. 2, 1984, abandoned. This application Aug. 19, 1994, Ser. No. 293,256


Int. Cl.⁶ H01B 12/02; H01L 39/12; C04B 35/45; 35/624

U.S. Cl. 505—125

6 Claims

1. A ceramic composite comprising a felted mat of ceramic particles and superconductive metal oxide particles bound together with a cured sol-gel precursor binder, wherein:

the ceramic particles include ceramic fibers selected from the group consisting of silica, alumina, mullite, zirconia, aluminosilicate, silicon nitride, and mixture thereof;
the superconductive metal oxide particles include fibers selected from the group consisting of superconductive oxide fibers, superconductive oxide coated ceramic fibers, and mixtures thereof;
the superconductive oxide coated ceramic fibers comprising a superconductive mixed metal oxide coating on a ceramic fiber;
the uncured, sol-gel precursor binder is an aqueous solution of metal salts stabilized in solution with ethylene glycol, and organic acid, or mixtures thereof;
wherein the superconductive metal oxide particles are present in sufficient amount to render the composite superconductive below the superconducting transition temperature of the superconductive metal oxide particles; and
wherein the ceramic fibers are about 0.0625–4.0 inches (0.16–10.2 cm) long and about 1–3 micrometers in diameter.



and has a viscosity greater than 500 centistokes at 120° C., the grease composition comprising:
synthetic polymer lubricant basestocks;
a metal complex soap base thickener; and
a boron nitride extreme pressure agent.

5,589,442

DRILLING FLUIDS COMPRISING MOSTLY LINEAR OLEFINS


Jeffrey C. Gee; Christophe J. Lawrie, and Roger C. Williamson, all of Kingwood, Tex., assignors to Chevron Chemical Company, San Ramon, Calif.

Continuation of Ser. No. 190,405, Feb. 2, 1994. This application Jun. 7, 1995, Ser. No. 480,986

Int. Cl.⁶ C09K 7/02

U.S. Cl. 507—103

18 Claims



1. An invert emulsion drilling fluid comprising:
(a) a continuous phase, comprising a mixture of mostly linear olefins containing 50 to 100% linear olefins and less than 20% alpha olefins, wherein the olefins contain at least 12 carbon atoms;
(b) a weight material; and
(c) water.

5,589,443

ROCK BIT GREASE COMPOSITION

Robert M. Denton, Friendswood, and Zhigang Fang, The Woodlands, both of Tex., assignors to Smith International, Inc., Houston, Tex.

Filed Dec. 21, 1995, Ser. No. 576,617

Int. Cl.⁶ C10M 125/00; 169/00

U.S. Cl. 508—150

35 Claims

1. A rock bit for drilling subterranean formations comprising:
a bit body including a plurality of journal pins, each having a bearing surface;
a cutter cone mounted on each journal pin and including a bearing surface;
a grease reservoir in communication with such bearing surfaces;
a grease composition in the grease reservoir and adjacent the bearing surfaces, wherein the grease composition is silica free

5,589,444

GREASE COMPOSITION FOR CONSTANT VELOCITY JOINTS

Ko Hatakeyama, Fujisawa, Japan, assignor to Kyodo Yushi Co., Ltd., Tokyo, Japan

Filed Jun. 6, 1996, Ser. No. 659,386

Int. Cl.⁶ C10M 141/06; 141/08

U.S. Cl. 508—168

5 Claims

1. A grease composition for constant velocity joints consisting essentially of:
(a) a base oil;
(b) an urea thickener;
(c) molybdenum disulfide;
(d) a calcium salt or an overbasic calcium salt selected from the group consisting of calcium salts of oxidized waxes, calcium salts of petroleum sulfonates, calcium salts of alkyl aryl sulfonates, calcium salts of salicylate, calcium salts of phenates, overbasic calcium salts of oxidized waxes, overbasic calcium salts of petroleum sulfonates, overbasic calcium salts of alkyl aryl sulfonates, overbasic calcium salts of salicylate, and overbasic calcium salts of phenates;
(e) a metal-free sulfur-phosphorus extreme pressure agent; and
(f) molybdenum dithiocarbamate.

5,589,445

OVERBASED METAL SALTS, THEIR PREPARATION AND USE

Richard Leahy, and Stephen J. Cook, both of North Humber-side, United Kingdom, assignors to BP Chemicals (Additives) Limited, London, England

Filed Aug. 21, 1995, Ser. No. 517,235


Claims priority, application United Kingdom, Aug. 19, 1994, 9416838

Int. Cl.⁶ C10M 159/20; 159/22

U.S. Cl. 508—381

21 Claims

1. An overbased metal salt of a hydrocarbyl-substituted sulphurised or non-sulphurised phenol, a calixarene having a substituent hydroxyl group or groups available for reaction with metal base or a linear phenol/formaldehyde resin wherein the metal moiety comprises a first metallic component which is at least one alkaline earth metal and a second metallic component which is at least one of either (i) at least one alkali metal or (ii) at least one metal selected from Groups IIIa, IVa, Va, VIa, VIIa and VIII of either the first or the second transition series of the Periodic Table of the Elements, the weight ratio of the first metal component to the second metal component being in the range from 1000:1 to 2:1.



5,589,446

PROCESS FOR REMOVAL OF IONIC SALT DEPOSITS
Greg R. Unruh, Amarillo, Tex., assignor to Tech Spray, Inc., Amarillo, Tex.

Division of Ser. No. 218,903, Mar. 28, 1994, which is a continuation-in-part of Ser. No. 21,797, Feb. 24, 1993. This application Jun. 7, 1995, Ser. No. 477,116
Int. Cl. C07D 323/00

U.S. Cl. 510—175

30 Claims

1. A method of removing ionic residues from a printed circuit board surface which comprises:
providing a solid surface having an ionic salt residue disposed thereon containing at least one salt of an alkali metal or alkaline earth metal cation;
contacting the surface with a liquid cleaning mixture comprising an organic solvent selected from the group consisting of an alkyl halide, a paraffinic monohydric alcohol, a non-halogenated paraffin, an aromatic compound and a mixture thereof, and a complexing agent comprising a crown ether formed of a monocyclic oligoether ligand exclusively containing oxygen as donor atoms whereby said cleaning mixture solvates said ionic residue and said crown ether enters into a guest/host relationship with at least one alkali metal or alkaline earth metal cation corresponding to an alkali metal or alkaline earth metal salt in said residue;
withdrawing said cleaning mixture from said surface with said crown ether and said alkali metal or alkaline earth metal cation in a guest/host relationship.

5,589,447

LIQUID DISHWASHING-DETERGENT COMPOSITION
Jadwiga Palicka, Lidköping, Sweden, assignor to Berol Nobel AB, Stenungsund, Sweden

PCT No. PCT/EP93/03092, § 371 Date May 10, 1995, § 102(e) Date May 10, 1995, PCT Pub. No. WO94/11476, PCT Pub. Date May 26, 1994

PCT Filed Nov. 3, 1993, Ser. No. 433,436


Claims priority, application Sweden, Nov. 11, 1992, 9203373
Int. Cl. C11D 1/12; 1/72; 1/90; 1/94

U.S. Cl. 510—237

7 Claims



1. An anionic surfactant-based liquid dishwashing-detergent composition, comprising

a) at least one amphoteric surface-active compound of type a) having the general formula (I)



wherein R is a hydrocarbon group having 7–22 carbon atoms, n is 0 or 1, A is a carbonyl group (C(O)), a group (OCH₂CH₂), or a group (OCH₂CH₂CH₂), in which z is an integer from 1 to 5, R₁ is hydrogen or a lower alkyl group, x is 2 or 3, y is an integer from 0 to 4, Q is the group —R₂COOM in which R₂ is an alkylene group having 1–6 carbon atoms and M is hydrogen or an ion from the groups alkali metals, alkaline-earth metals, ammonium and substituted ammonium, and B is hydrogen or a group Q as defined above,

b) at least one amphoteric surface-active compound of type b) having the general formula (III) or (IV)



wherein R is a longer hydrophobic hydrocarbon group having at least 7 carbon atoms, R' is an alkyl or hydroxyalkyl group having 1–4 carbon atoms, n is 1 or 2, and M is hydrogen or a sodium ion, c) at least one non-ionic surface-active compound consisting of an ethoxylated and/or propoxylated adduct of a fatty alcohol, and

d) at least one anionic surfactant, wherein the total amount of amphoteric compounds of type a) and type b) and ethoxylated and/or propoxylated fatty alcohol is 20 to 70% by weight, based on the anionic surfactant, and the weight ratio of ethoxylated and/or propoxylated fatty alcohol to the total amount of amphoteric surface-active compounds is from 1:1–2:1.

5,589,448

HIGH WATER LIQUID ENZYME PREWASH COMPOSITION


Michael Koerner, Pleasanton, and David L. Deleeuw, San Ramon, both of Calif., assignors to The Clorox Company, Oakland, Calif.

Continuation of Ser. No. 18,621, Feb. 17, 1993, abandoned.
This application Jun. 7, 1995, Ser. No. 474,353

Int. Cl. C11D 3/386

U.S. Cl. 510—284

15 Claims



1. A high water liquid enzyme prewash composition without hydrotropes, organic solvents and surfactants, other than nonionic surfactants, said composition consisting essentially of:

- about 0.0001–10% of a hydrolase enzyme stabilized with about 1–10,000 ppm of a soluble alkaline earth salt;
- about 0.1–9.99% of a more hydrophilic, first nonionic surfactant having an HLB of greater than about 11;
- about 0.1–9.99% of a more hydrophobic, second nonionic surfactant having an HLB of less than or equal to about 11;
- about 80–99% water;

wherein the difference in HLB between said first and second nonionic surfactants is at least 2, and said nonionic surfactants interact with said water to form an opalescent, structured liquid, said structured liquid both suspending said hydrolase and protecting said hydrolase against deactivation with said water wherein first and second nonionic surfactants are selected from the groups consisting of C₅–C₂₀ alcohols with 1–20 mole of ethylene oxide, propylene oxide or mixtures of ethylene oxide and propylene oxide and alkoxyalkyl phenols.

5,589,449

PARTICULATE FOAM CONTROL AGENTS

Leonidas Kolaitis, Meise; Bertrand L. J. Lenoble, Bois-de-Lessines, and Mark A. Prince, Overijse, all of Belgium, assignors to Dow Corning S.A., Seneffe, Belgium

Filed Jul. 22, 1994, Ser. No. 279,755

Claims priority, application United Kingdom, Jul. 29, 1993, 9315675; Jan. 14, 1994, 9400599

Int. Cl. B01D 19/04; C11D 3/20

U.S. Cl. 510—466

19 Claims

1. A particulate foam control agent comprising from 1 to 30 parts by weight of a silicone antifoam, from 70 to 99 parts by weight of a zeolite carrier for the antifoam, from 1 to 60% by weight of the silicone antifoam of an organopolysiloxane polyoxy-alkylene copolymer, which has been deposited onto the zeolite carrier not later than the silicone antifoam and from 1 to 40 parts by weight of a polycarboxylate-type binder or encapsulant.

19. A detergent composition in powder form which comprises 100 parts by weight of a detergent component and sufficient of a foam control agent according to claim 1 to give 0.05 to 5 parts by weight of the silicone antifoam comprised in the foam control agent.

HLB value of from about 6 to about 12 and having the formula (IV):



wherein R⁷ is an alkyl radical having from about 8 to about 14 carbon atoms, R⁸ is hydrogen or a methyl group and n is a number of 1 to 10;

wherein the reaction is carried out in the absence of water or any additional organic solvents.

5,589,451

METHODS AND TREATMENTS FOR CORNEAL HEALING WITH HEPATOCYTE AND KERATINOCYTE GROWTH FACTORS

Steven E. Wilson, Plano, Tex., assignor to Board of Regents, The University of Texas System, Austin, Tex.

Filed Sep. 21, 1992, Ser. No. 947,683

Int. Cl. A61K 38/18; C12N 5/06; C07K 14/485; 14/475

U.S. Cl. 512—2

13 Claims

1. A method for promoting corneal cell proliferation or maintaining corneal cell viability in vivo comprising treating the corneal cells with an amount of hepatocyte growth factor to stimulate growth in a pharmaceutically acceptable composition.

5,589,450

PROCESS FOR THE PRODUCTION OF WATER-FREE DETERGENT MIXTURES

Raphael Pi, Granollers; Joaquim Bigorra-Losas, Sabadell; Oriol Ponsati-Obiols, Barcelona, all of Spain, and Karl Schmid, Mettmann, Germany, assignors to Henkel Kommanditgesellschaft auf Aktien, Duesseldorf, Germany

PCT No. PCT/EP94/00392, § 371 Date Sep. 15, 1995, § 102(e) Date Sep. 15, 1995, PCT Pub. No. WO94/19313, PCT Pub. Date Sep. 1, 1994

PCT Filed Feb. 11, 1994, Ser. No. 505,305

Claims priority, application Germany, Feb. 19, 1993, 43 05 083.2


Int. Cl. C11D 3/28; 3/30; 1/72

U.S. Cl. 510—535

16 Claims


1. A process for the production of a water-free detergent mixture comprising reacting at least one secondary or tertiary amine selected from the group consisting of

(i) a compound of the formula (I):




wherein R¹ is an alkyl or alkenyl radical having from about 6 to about 22 carbon atoms, R² is hydrogen or an alkyl radical having from 1 to about 4 carbon atoms and R³ is an alkyl radical having from 1 to about 4 carbon atoms,

(ii) a compound of the formula (II):



wherein R³CO is an aliphatic acyl radical having from about 6 to about 22 carbon atoms and 0 or 1 to 3 double bonds, n is 0 or a number of 1 to 3 and R² and R³ are as defined above, and

(iii) a compound of the formula (III):



wherein each of R³CO and R⁴CO is independently an aliphatic acyl radical having from about 6 to about 22 carbon atoms and 0 or 1 to 3 double bonds with an alkylating agent which is a halocarboxylic acid or an alkali metal salt or ester thereof in the presence of at least one fatty alcohol polyglycol ether having an

5,589,452

ANALOGS OF PARATHYROID HORMONE AND PARATHYROID HORMONE RELATED PEPTIDE: SYNTHESIS AND USE FOR THE TREATMENT OF OSTEOPOROSIS

John L. Krstenansky, Palo Alto; John J. Nestor, Jr., Cupertino; Teresa H. Ho, Los Altos; Brian H. Vickery, Mountain View, and Chinh T. Bach, San Jose, all of Calif., assignors to Syntex (U.S.A.) Inc., Palo Alto, Calif.

Filed Jul. 14, 1992, Ser. No. 915,247

Int. Cl. A61K 38/29; C07K 14/635

U.S. Cl. 514—12

37 Claims

1. A modified parathyroid hormone related polypeptide (PTHrP), of the formula:

Ala Val Ser Glu Xaa⁵ Gln Leu Leu His Asp Xaa¹¹ Gly Xaa¹³ Ser Ile

Gln Asp Leu Xaa¹⁹ Arg Xaa²¹ Xaa²²⁻³¹ Xaa³² Xaa³³ Xaa³⁴

Term, wherein:

Xaa⁵ is His or Ala;

Xaa¹¹ and Xaa¹³ are independently Lys, Arg, or Leu;

Xaa¹⁹ and Xaa²¹ are independently Ala or Arg;

Xaa²²⁻³¹ is selected from the group consisting of (SEQ ID NOS: 26, 27, 28, 29, and 30);

Xaa³² is His or Lys;

Xaa³³ is Thr, Glu, or Ala;

Xaa³⁴ is Ala, hSer, Tyr, or Leu;

Term is OH, NR₂, lactone, or Gly Arg Arg, where R is H or (C₁–C₄) alkyl; and the pharmaceutically acceptable salts thereof.

5,589,453

HUMAN RHINOVIRUS RECEPTOR PROTEIN (ICAM-1) THAT INHIBITS RHINOVIRUS ATTACHMENT AND INFECTIVITY

Jeffrey M. Greve, Branford, Conn., assignor to Molecular Therapeutics, Inc., West Haven, Conn.
Continuation of Ser. No. 139,622, Oct. 19, 1993, abandoned, which is a continuation of Ser. No. 14,087, Feb. 4, 1993, abandoned, which is a continuation of Ser. No. 239,571, Sep. 1, 1988, abandoned. This application Sep. 30, 1994, Ser. No. 316,383

Int. Cl.⁶ A61K 38/17;39/00; C07K 14/705

U.S. Cl. 514—8

6 Claims

1. A method for reducing the infection by human rhinovirus (HRV) of a host cell susceptible to infection by HRV, comprising contacting the virus under conditions favorable for binding with an antiviral agent selected from the group consisting of human rhinovirus major receptor protein (HRR) and fragments thereof in a form that exhibits the ability to bind to HRV capsids and reduce infectivity of the virus.

5,589,454

Patent Not Issued For This Number

5,589,455

CYCLOSPORIN-CONTAINING SOFT CAPSULE COMPOSITIONS

Jong S. Woo, Kyunggi-do, Rep. of Korea, assignor to Hanmi Pharm. Ind. Co., Ltd., Kyunggi-do, Rep. of Korea
Filed Apr. 21, 1995, Ser. No. 427,187

Claims priority, application Rep. of Korea, Dec. 28, 1994, 94-37948

Int. Cl.⁶ A61K 37/00

U.S. Cl. 514—11

14 Claims

1. A cyclosporin-containing soft capsule composition which comprises:

- (1) cyclosporin as an active ingredient,
- (2) polyethylene glycol having a molecular weight of 200 to 600 as a cosurfactant,
- (3) a mixture of an esterified compound of fatty acid and primary alcohol, medium chain fatty acid triglyceride and fatty acid monoglyceride as an oil component, and
- (4) a surfactant having HLB (Hydrophilic-lipophilic balance) value of 10 to 17.

5,589,456

GRANULOCYTE-COLONY STIMULATING FACTOR RECEPTORS

Craig A. Smith; Alf D. Larsen; John E. Sims, and Benson M. Curtis, all of Seattle, Wash., assignors to Immunex Corporation, Seattle, Wash.

Division of Ser. No. 6,183, Jan. 15, 1993, Pat. No. 5,422,248, which is a continuation of Ser. No. 587,329, Sep. 24, 1990, abandoned, which is a continuation-in-part of Ser. No. 522,952, Apr. 3, 1990, abandoned, which is a continuation-in-part of Ser. No. 416,306, Oct. 3, 1989, abandoned, which is a continuation-in-part of Ser. No. 412,816, Sep. 26, 1989, abandoned. This application Feb. 2, 1995, Ser. No. 382,771

Int. Cl.⁶ C12N 15/19; A61K 38/19; C07K 14/715

U.S. Cl. 514—12

2 Claims

1. A purified biologically active Granulocyte Colony Stimulating Factor receptor (G-CSFR), selected from the group consisting of: (a) a G-CSFR having an amino acid sequence comprising amino acids 1 through 759 of FIGS. 2A-2B; (b) a G-CSFR having an amino acid sequence comprising amino acids 1 through 725 of FIGS. 2A-2B followed by amino acids 726-776 of FIG. 3;

(c) a biologically active G-CSFR identical to the G-CSFR molecules of (a) or (b) except for modification(s) to the amino acid sequence selected from the group consisting of: inactivated N-linked glycosylation sites; altered KEX2 protease cleavage sites; and conservative amino acid substitutions; and (d) soluble forms of the G-CSFR according to (a), (b) or (c), consisting of the extracellular domain of G-CSFR,

which G-CSFR molecules exhibit biological activity in an assay selected from the group consisting of a G-CSFR membrane binding assay, a G-CSFR solid phase binding assay, a G-CSFR whole cell binding assay, and a binding assay for soluble G-CSFR.

5,589,457

PROCESS FOR THE SYNCHRONIZATION OF OVULATION

Milo Wiltbank, Madison, and James R. Pursley, Sun Prairie, both of Wis., assignors to AUSA International, Inc., Tyler, Tex.

Filed Jul. 3, 1995, Ser. No. 498,691

Int. Cl.⁶ A61K 38/24;31/19

U.S. Cl. 514—12

40 Claims

1. A method for synchronizing ovulation in cattle, the steps comprising:

- (a) administering a first dose of a hormone selected from the group consisting of a gonadotropin releasing hormone (GnRH), a luteinizing hormone (LH) and a human chorionic gonadotropin (hCG), to an open cow during an estrous cycle in an amount effective to stimulate ovarian follicle development;
- (b) subsequent to step (a) and after a period of time sufficient for development of a dominant follicle, administering a dose of prostaglandin F_{2α} (PGF_{2α}) in an amount effective to initiate corpus luteum regression;
- (c) concomitantly with or within a period of 3 days subsequent to step (b), administering a second dose of a hormone selected from the group consisting of LH, hCG and GnRH to stimulate ovulation of said follicle; and
- (d) concomitantly with or within one day prior to or subsequent to step (c), breeding said cow.

5,589,458

COMPOUNDS THAT INHIBIT T CELL PROLIFERATION AND METHODS FOR USING THE SAME

Bradford A. Jameson; James M. McDonnell, both of Philadelphia, Pa., and Robert Korngold, Cherry Hill, N.J., assignors to Thomas Jefferson University, Philadelphia, Pa.

Continuation-in-part of Ser. No. 977,692, Nov. 13, 1992, abandoned. This application Jun. 11, 1993, Ser. No. 76,092

Int. Cl.⁶ A61K 38/00;38/04; C07K 5/00;7/00

U.S. Cl. 514—13

27 Claims

1. A compound consisting of 20 amino acids or less including Lys-Glu-Glu; wherein said compound inhibits T cell proliferation.

19. A method of treating an individual suffering from or being susceptible to multiple sclerosis, graft rejection or graft versus host disease comprising the step of administering to said individual a pharmaceutical composition comprising:

- a) a therapeutically effective amount of a compound according to claim 1; and
- b) a pharmaceutically acceptable carrier or diluent.

5,589,459

SYNTHETIC PEPTIDES FOR DETOXIFICATION OF BACTERIAL ENDOTOXINS AND FOR THE PREVENTION AND TREATMENT OF SEPTIC SHOCK


Massimo Porro, Siena, Italy, assignor to Biosynth s.r.l., Siena, Italy
Division of Ser. No. 819,893, Jan. 16, 1992, Pat. No. 5,371,186, which is a continuation-in-part of Ser. No. 658,744, Feb. 11, 1991, abandoned. This application Jul. 26, 1994, Ser. No. 280,397

Int. Cl.⁶ A61K 38/00;38/12; C07K 5/00;7/00

U.S. Cl. 514—15

14 Claims

1. A method for the removal of endotoxin from human and animal blood sera which comprises contacting said blood or sera with a peptide of which is a monomeric, linear polymeric, cyclic monomeric or cyclic polymeric peptide of the formula:



wherein R₁ and R are independently H or an amino acid residue or a fatty acid residue; A is an amino acid residue selected from the group consisting of Lys and Arg; B is an amino acid selected from the group consisting of Phe, Tyr and Trp; C is an amino acid selected from the group consisting of Leu, Ile and Val; n is an integer of from 1-100, in an amount which is effective for the removal of endotoxin from said blood or sera.

5,589,460

TRI-, TETRA-, PENTA-, AND POLYPEPTIDES AND THEIR THERAPEUTIC USE AS AN ANTIDEPRESSANT AGENT


Henry B. Abajian, Hillsdale, N.J.; John F. Noble, Pomona, and Joseph J. Hlavka, Tuxedo Park, both of N.Y., assignors to Innapharma, Inc., Suffern, N.Y.

Filed May 4, 1994, Ser. No. 238,089

Int. Cl.⁶ A61K 38/04;38/07; C07K 5/04;7/00

U.S. Cl. 514—17

68 Claims



1. A tripeptide composition or salt thereof, comprising a general formula (1):



where Pro¹ represents an amino acid selected from the group consisting of Pro and dehydro-Pro; AA¹ represents an amino acid selected from the group consisting of Trp, Orn, Lys, Leu, Arg, D-Arg, and Ile; R is selected from the group consisting of a carboxyl group, a hydroxyalkyl group, a carbamyl group and an alkoxycarbonyl group; R¹ is selected from the group consisting of a hydrogen atom, a lower alkyl group having 1 to 3 carbon atoms, a halogen atom, a hydroxyl group, a sulphhydryl group, an alkylamino group, and a dialkylamino group; and, R² is selected from the group consisting of a hydrogen atom and a lower alkyl group having 1 to 3 carbon atoms, with the provisos that: where Pro¹ is Pro and AA¹ is Leu, Ile, Lys, Arg, or Orn, then R¹ and R² cannot both be a

hydrogen atom when R is a carbamyl group; where Pro¹ is dehydro-Pro and AA¹ is Leu, then R¹ and R² cannot both be a hydrogen atom when R is a carbamyl group; where Pro¹ is Pro and AA¹ is Leu, R¹ and R² cannot both be a hydrogen atom when R is either a carboxyl group or a hydroxyalkyl group; and, where Pro¹ is Pro and AA¹ is Trp, R¹ and R² cannot be a hydrogen atom when R is a hydroxyalkyl group.

5,589,461

ACTIVE SUBSTANCE FOR INHIBITING THE PROLIFERATION RATE OF HEPATOCYTES

G. Ruhenstroth-Bauer, Spitzelbergerstrasse 11, 82166 Gräfelfing, Germany

Filed May 17, 1994, Ser. No. 243,873

Int. Cl.⁶ C07K 5/08;5/10;5/06

U.S. Cl. 514—18

3 Claims

1. A method of inhibiting the proliferation rate of hepatocytes in a subject, comprising the step of:

- administering the free tripeptide of the composition SDK (serine-aspartic acid-lysine) or the salt thereof for treating the subject by administering a therapeutically effective amount to a subject in need thereof.

5,589,462

METHOD OF PREPARING A BIOLOGICAL ADHESIVE ENRICHED WITH PLATELET FACTORS, AND APPLICATION

Jean-Louis Patat, Paris; Olivier Delmas, Montbazou, and Roland Schmittauesler, Montigny-le Bretonneux, all of France, assignors to Inotek, Saint-Gonery, France

PCT No. PCT/FR93/00954, § 371 Date Jul. 15, 1994, § 102(e) Date Jul. 15, 1994, PCT Pub. No. WO94/07548, PCT Pub. Date Apr. 14, 1994

PCT Filed Sep. 30, 1993, Ser. No. 244,253

Claims priority, application France, Sep. 30, 1992, 92 11643

Int. Cl.⁶ A61K 38/18;35/16; C07K 14/49;1/30

U.S. Cl. 514—21

16 Claims

1. A method of preparing a platelet factor-enriched biological adhesive, comprising:

- (a) freezing a platelet-enriched plasma; and
- (b) isolating a cryoprecipitate from the frozen platelet-enriched plasma.

5,589,463

ORAL DELIVERY OF BIOLOGICALLY ACTIVE SUBSTANCES BOUND TO VITAMIN B12

Gregory J. Russell-Jones, Willoughby; Peter Howe, West Pennington Hills; Henry J. de Aizpurua, Bexley, and Geoffrey L. Burge, Thornleigh, all of Australia, assignors to Biotechnology Australia Pty., Ltd., Roseville, Australia

Division of Ser. No. 61,343, May 17, 1993, Pat. No. 5,428,023, which is a continuation of Ser. No. 759,697, Sep. 9, 1991, abandoned, which is a continuation of Ser. No. 600,137, Oct. 19, 1990, abandoned, which is a continuation of Ser. No. 84,821, Jun. 9, 1987, abandoned. This application Jun. 7, 1995, Ser. No. 479,635

Claims priority, application Australia, Oct. 10, 1985, PH2838

Int. Cl.⁶ A61K 31/715;39/385; C07H 23/00

U.S. Cl. 514—21

10 Claims

1. An orally administrable complex comprising an antigen or hapten that is covalently linked via a cross-linking agent to a vitamin B12 carrier molecule, wherein

(A) said carrier molecule is capable of binding in vivo to intrinsic factor, thereby enabling uptake and transport of the complex from the intestinal lumen of a vertebrate host via intrinsic factor to the systemic circulation of said host, and

(B) said cross-linking agent links said antigen or hapten to a carboxyl group of an acid-hydrolyzed propionamide side chain adjacent to ring A, ring B or ring C of said carrier molecule, and

said antigen or hapten is an allergen, protein, polysaccharide or secretory product selected from the group consisting of polysaccharides, grass pollen, weed pollen, tree pollen, plant pollen, cat hair, dog hair, pig hair, other epithelia, house dust mite, wheat chaff, kapok, a protein from or immunogens against influenza, measles, Rubella, smallpox, yellow fever, diphtheria, tetanus, cholera, plague, typhus, BCG, tuberculosis causing agents, *Haemophilus influenzae*, *Neisseria catarrhalis*, *Klebsiella pneumoniae*, pneumococci, streptococci, a malarial parasite or the causative agent of coccidiosis in chickens, a secretory product from diphtheria, tetanus, cholera, plague, typhus, tuberculosis causing agents, *Haemophilus influenzae*, *Neisseria catarrhalis*, *Klebsiella pneumoniae*, pneumococci, streptococci, and *Streptococcus mutans*.

5,589,465 GLYCOLIPID DERIVATIVES ACTING AS LIGANDS FOR SELECTINS

Hideharu Ishida, Gifu; Makoto Kiso, Motosu-gun, and Akira Hasegawa, 1735-160 Kano, Gifu-ken, all of Japan, assignors to Akira Hasegawa, and Kanebo Ltd., both of Japan


Filed Mar. 1, 1995, Ser. No. 396,793

Claims priority, application Japan, Sep. 30, 1994, 6-261557

Int. Cl.⁶ A61K 31/70; C07H 3/06; 11/00; 15/04

U.S. Cl. 514—25 9 Claims

1. A glycolipid derivative of Formula (I):



wherein R is 2-(tetradecyl) hexadecyl, in the form of a pharmaceutically acceptable salt.

5,589,466 INDUCTION OF A PROTECTIVE IMMUNE RESPONSE IN A MAMMAL BY INJECTING A DNA SEQUENCE

Philip L. Feigner, Rancho Santa Fe, Calif.; Jon A. Wolff, Madison, Wis.; Gary H. Rhodes, Leucadia, Calif.; Robert W. Malone, Chicago, Ill., and Dennis A. Carson, Del Mar, Calif., assignors to Vical Incorporated, San Diego, Calif., and Wisconsin Alumni Research Foundation, Dane, Wis.

Continuation of Ser. No. 8,197, Jan. 25, 1993, abandoned, which is a continuation of Ser. No. 496,991, Mar. 21, 1990, abandoned, which is a continuation-in-part of Ser. No. 467,881, Jan. 19, 1990, abandoned, which is a continuation-in-part of Ser. No. 326,305, Mar. 21, 1989, abandoned. This application Jan. 26, 1995, Ser. No. 380,131

Int. Cl.⁶ A61K 48/00; C12N 15/00

U.S. Cl. 514—44 11 Claims

1. A process for inducing a protective immune response in a mammal, comprising:

injecting into muscle or skin of said mammal a construct comprising a noninfectious, nonintegrating DNA sequence encoding an immunogen linked to a promoter sequence which can control the expression of said DNA sequence in said mammal, in an amount sufficient that uptake of said construct occurs, and sufficient expression results, to induce said protective immune response,

wherein said construct is free from association with transfection-facilitating viral particles, liposomal formulations or charged lipids.

5,589,467 2,5',N6-TRISUBSTITUTED ADENOSINE DERIVATIVES

Jesper Lau, Farum, and Lars J. S. Knutsen, Vedbæk, both of Denmark, assignors to Novo Nordisk A/S, Bagsvaerd, Denmark

Filed Sep. 14, 1994, Ser. No. 306,232

Claims priority, application Denmark, Sep. 17, 1993, 1043/93; Mar. 16, 1994, 0310/94

Int. Cl.⁶ A61K 31/70; C07H 19/67

U.S. Cl. 514—46 14 Claims

1. A compound of formula (I) or a pharmaceutically acceptable salt thereof

5,589,464

USE OF 2-SUBSTITUTED-THIAZOLIDINE-4-CARBOXYLIC ACIDS FOR TREATMENT OF CATARACT

William H. Garner, Southlake, and Larry A. Wheeler, Irvine, both of Calif., assignors to Allergan, Waco, Tex.


Division of Ser. No. 938,967, Sep. 1, 1992, Pat. No. 5,399,573.

This application Sep. 30, 1994, Ser. No. 316,596

Int. Cl.⁶ A61K 31/70; 31/435; 31/425; 31/38

U.S. Cl. 514—23 4 Claims

1. A method for delaying the onset of cataract in mammals comprising administering to said mammal a composition having a therapeutically effective amount of a compound of the formula:



R is hydrogen, hydroxy, aliphatic(C₁₋₂₀), (CH₂)_n-Q, where n is 0-20 and Q is phenyl, thienyl, furyl, pyridyl, or (CH₂)_n-T where n is 0-20 and T is an aliphatic ring of 3 to 7 carbon atoms, or =O or a ketal of 2-5 carbons, or hydroxy, or 0-aliphatic (C₁₋₁₀), or N(R₁)₂ where R₁ is hydrogen or alkyl of 1 to 5 carbons, or thiazolidine, or a sugar; and Z is -OH or a pharmaceutically acceptable salt thereof, OR₃ where R₃ is an aliphatic group of 1-10 carbons, N(R₁)₂ when R₁ is hydrogen or alkyl of 1-5 carbon atoms.

5,589,469 SUBSTITUTED 1H-3-ARYL-PYRROLIDINE-2,4-DIONE DERIVATIVES

Reiner Fischer, Monheim; Bernd-Wieland Krüger, Bergisch Gladbach; Thomas Bretschneider, Siegburg; Christoph Erdelen, Leichlingen; Ulrike Wachendorf-Neumann, Monheim; Klaus Lürssen, Bergisch Gladbach; Hans-Joachim Santel, Leverkusen, and Robert R. Schmidt, Bergisch Gladbach, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany


Continuation of Ser. No. 166,669, Dec. 14, 1993, abandoned, which is a continuation of Ser. No. 901,051, Jun. 19, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 483,913

Claims priority, application Germany, Jun. 28, 1991, 41 21 365.3


Int. Cl.⁶ A01N 43/36; 57/16; C07D 207/273; C07F 9/52

U.S. Cl. 514—91 8 Claims


1. A substituted 3-aryl-pyrrolidine-2,4-dione derivative of the general formula



in which
X represents C₁₋₆-alkyl,
Y represents C₁₋₆-alkyl,
Z represents C₁₋₆-alkyl,
n represents a number from 0-3,
A and B independently represent hydrogen, or C₁₋₄-alkyl, or in which
A and B together with the carbon atom to which they are bonded represent cyclohexyl,
R represents



in which
R¹ and R² independently of each other represent C₁₋₆-alkyl, C₁₋₆-alkoxy or C₁₋₆-alkylthio, and
the pure enantiomeric forms of compounds of the formula (I).




wherein

X is halogen, amino, perhalomethyl, cyano, C₁₋₆-alkoxy, C₁₋₆-alkylthio or C₁₋₆-alkylamino;

A is methyl, halomethyl, cyanomethyl, aminomethyl, vinyl, methylthiomethyl or methoxymethyl; and


R¹ is selected from the group consisting of

(i) a ring of formula (a)



wherein Q is nitrogen, n is 2 and the ring of formula (a) is unsubstituted or substituted with one or two C₁₋₆-alkyl groups, C₂₋₆-alkenyl, C₂₋₆-alkynyl, phenoxy, phenylsulphonyl, phenylsulphinyl, phenylthio, hydroxy, phenyl, C₁₋₆-alkoxy, C₁₋₆-alkoxy-C₁₋₆-alkyl, or phenylthioalkyl,

(ii) a ring of formula (b)



wherein Y is O, S or NZ, wherein Z is H, C₁₋₆-alkyl or phenyl, and wherein the ring of formula (b) is unsubstituted or substituted with C₁₋₆-alkyl, C₂₋₆-alkenyl, C₂₋₆-alkynyl, phenoxy, phenyl, C₁₋₆-alkoxy or C₁₋₆-alkoxy-C₁₋₆-alkyl, and

(iii) —NR²R³ or —Y²R⁴, wherein Y² is oxygen or sulphur; R² is C₁₋₆-alkyl; R³ is phenyl or C₁₋₆-alkyl which is unsubstituted or substituted by phenyl or phenoxy; and R⁴ is C₁₋₆-alkyl or C₃₋₈-cycloalkyl, each of which is unsubstituted or substituted by phenyl or phenoxy.

5,589,468 METHOD FOR PROVIDING NUTRITION TO ELDERLY PATIENTS

Paul M. Lin, Fullerton, Calif.; Shen-Youn Chang, Wadsworth, and Chris Kruzel, Wheeling, both of Ill., assignors to Clintec Nutrition Co., Deerfield, Ill.

Filed Jan. 13, 1995, Ser. No. 372,558

Int. Cl.⁶ A01N 43/04; 45/00; 43/60; 43/08

U.S. Cl. 514—52 20 Claims

1. A method for providing nutrition to an elderly patient comprising enterally administering to the patient an effective amount of a composition comprising:

a protein source including at least 18% of the calorie distribution of the composition;

a carbohydrate source; and

a lipid source including a mixture of medium and long chain triglycerides.

5,589,470 REDUCING TETRACYCLINE RESISTANCE IN LIVING CELLS

Stuart B. Levy, Boston, Mass., assignor to Trustees of Tufts College, Medford, Mass.

PCT No. PCT/US92/08965, § 371 Date Jun. 14, 1994, § 102(e) Date Jun. 14, 1994, PCT Pub. No. WO93/08806, PCT Pub. Date May 13, 1993

Continuation-in-part of Ser. No. 788,693, Nov. 6, 1991, abandoned, which is a continuation of Ser. No. 672,323, Mar. 20, 1991, Pat. No. 5,258,372, and Ser. No. 484,904, Feb. 26, 1990, Pat. No. 5,064,821. This PCT application Oct. 16, 1992, Ser. No. 232,247

Int. Cl.⁶ A61K 31/65

U.S. Cl. 514—154 27 Claims

1. A pharmaceutical composition for converting tetracycline resistant bacteria into tetracycline sensitive bacteria comprising a

5,589,475

BENZODIAZEPINE TREATMENT

Ernir Snorrason, Stigahlid 80, 105 Reykjavik, Iceland
Continuation of Ser. No. 883,037, May 14, 1992, abandoned.
This application Aug. 22, 1994, Ser. No. 292,230
Claims priority, application Iceland, May 14, 1991, 3706;
Denmark, Feb. 13, 1992, 182/92


Int. Cl.⁶ A01N 43/46

U.S. Cl. 514—215

42 Claims

1. A method for counteracting the sedative, hypnotic or respiratory depressive effects of benzodiazepines, substantially without interfering with the anxiolytic, antipsychotic, anticonvulsant, and muscle relaxant activity of benzodiazepines, comprising the steps of

administering, to a patient subjected to benzodiazepine therapy, an effective amount of galanthamine or a galanthamine derivative of the formula I



wherein R¹ and R² represents a hydrogen atom or an acyl group, and wherein R¹ and R² may be the same or different;

R³ is a straight or branched chain alkyl, alkenyl or alkaryl group which is optionally substituted by a halogen atom or a cycloalkyl, hydroxy, alkoxy, nitro, amino, amino-alkyl, acylamino, heteroaryl, heteroaryl-alkyl, aroyl, aryloalkyl or cyano group; and

R⁴ represents a hydrogen or halogen atom attached to at least one of the ring carbons of the tetracyclic skeleton, with the proviso that when R₄ is in a position neighboring the nitrogen atom, then R₄ is not halogen;

or a pharmaceutically acceptable salt thereof.

5,589,476

IMIDAZOL-4-YLPYRIMIDINE DERIVATIVES, THEIR PREPARATION AND THEIR APPLICATION IN THERAPEUTICS

Samir Jegham, Argenteuil; Gérard Defosse, Paris; Thomas A. Purcell, Montfort L'Amaury, and Luc Even, Paris, all of France, assignors to Synthelabo, Le Plessis Robinson, France
Filed Oct. 3, 1994, Ser. No. 317,661


Claims priority, application France, Oct. 4, 1993, 93 11771

Int. Cl.⁶ C07D 498/12; 498/16; A61K 31/535; 31/435

U.S. Cl. 514—230.2

3 Claims

1. A compound of formula (I):



in which

R₁ represents a hydrogen atom or a straight or branched (C₁—C₄) alkyl group; and

A represents a 4,5-dihydroimidazo[1,5,4-de][1,4]benzoxazin-2-yl group, a 4-methyl-4,5-dihydroimidazo[1,5,4-de][1,4]benzoxazin-2-yl group, a 4-phenyl-4,5-dihydroimidazo[1,5,4-de][1,4]benzoxazin-2-yl group, a 4-phenylmethyl-4,5-dihydroimidazo[1,5,4-de][1,4]benzoxazin-2-yl group, or a 5-methyl-4,5-

dihydroimidazo[1,5,4-de][1,4]benzoxazin-2-yl group, which may be unsubstituted or substituted in the 6-position by a phenylmethyl group;

or an addition salt thereof with a pharmaceutically acceptable acid.

5,589,477

PYRIMIDINE DERIVATIVES AND DRUGS

Shoichi Chokai, Kyoto; Tomiyoshi Aoki, Shiga, and Kiyoshi Kimura, Osaka, all of Japan, assignors to Nippon Shinyaku Company, Limited, Japan

Filed Feb. 26, 1993, Ser. No. 983,515


Claims priority, application Japan, Aug. 31, 1990, 2-231029; May 29, 1991, 3-155628

Int. Cl.⁶ A61K 31/505; C07D 403/04; 403/12

U.S. Cl. 514—256


24 Claims

1. A compound of the formula



or a pharmacologically acceptable salt thereof wherein A and B are as follows:


When A represents




B represents methyl, trifluoromethyl, or tert-butyl; when B represents



A represents methyl, trifluoromethyl, or tert-butyl wherein R¹ and R² are the same or different and each is hydrogen, hydroxy, lower alkoxy, trifluoromethyl or halogen;

R³ represents

wherein Y represent O or NH, or



wherein Y represents O or NH, m is 2 or 3, and R⁶ and R⁷ form a 5 to 6 membered cyclic-amino group with the adjacent nitrogen atom, wherein said cyclic-amino group optionally includes an oxygen or sulfur atom, and said cyclic-amino group being unsubstituted or substituted by aryl with or without substituent(s), aralkyl with or without substituent(s) wherein the alkyl moiety thereof is lower alkyl, or aroyl with or without substituent(s).

5,589,478

BENZENESULFONAMIDE DERIVATIVE AND PROCESS FOR PREPARING THEREOF

Koichiro Yamada; Kōsuke Yasuda, both of Saitama-ken; Kobei Kikkawa, Kawaguchi, and Rikako Kohno, Omiya, all of Japan, assignors to Tanabe Seryaku Co., Ltd., Osaka, Japan
Filed Dec. 16, 1994, Ser. No. 356,958


Claims priority, application Japan, Dec. 17, 1993, 5-318779; Jun. 23, 1994, 6-140628; Aug. 4, 1994, 6-183553

Int. Cl.⁶ C07D 239/32; 239/42; A61K 31/50; 31/505

U.S. Cl. 514—269

15 Claims

1. A benzenesulfonamide derivative of the formula [I]:



wherein Ring A is a benzene ring substituted by a lower alkyl group; one or two lower alkoxy groups; a lower alkoxy-carbonyl-lower alkyl group; a hydroxy-substituted lower alkyl group; or a lower alkoxy-carbonyl-lower alkoxy group.

Ring B is a benzene ring substituted by formyl group; trifluoromethyl group; a lower alkyl group; one or two lower alkoxy groups; a lower alkenedioxy group; a hydroxy-lower alkyl group; or a lower alkoxy-carbonyl group.

Q is a single bond or a group of the formula: —O— or —S—.

Y is a group of the formula: —O—.

Alk is a lower alkylene group.

Z is a group of the formula: —O—.

R is a phenyl group having optionally a substituent selected from amino group, nitro group, a halogen atom and a hydroxy-lower alkyl group; a pyridyl group having optionally a substituent selected from amino group, nitro group, trifluoromethyl group and a lower alkanoylamino group; a pyrimidinyl group having optionally a substituent selected from a halogen atom, formyl group, thienyl group, furyl group, pyridyl group, a lower alkyl group, a lower alkylthio group, a lower alkanoyl group, a lower alkynyl group, a lower alkenyloxy group, a lower alkoxy group, a lower alkylsulfinyl group, a lower alkylsulfonyl group, a cyano-substituted lower alkoxy group, thiazolyl group, a lower alkyl-substituted thienyl group, a lower alkyl-substituted pyrrolyl group, phenyl group and a lower alkoxyphenyl group; or benzothialolyl group, and R¹ is hydrogen atom, a lower alkyl group, pyridyl group, morpholinyl group or pyrimidinyl group or a pharmaceutically acceptable salt thereof.

5,589,479

FUNGICIDAL MIXTURES

Kari Elcken, Wachenheim; Bernd Müller, Frankenthal; Hubert Sauter, Mannheim; Gisela Lorenz, Neustadt; Eberhard Ammermann, Heppenheim; Klaus Schelberger, Gönheim, and Reinhold Saur, Böhl-Iggelheim, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

Division of Ser. No. 305,396, Sep. 13, 1994, Pat. No. 5,508,283.

This application Oct. 30, 1995, Ser. No. 550,405

Claims priority, application Germany, Sep. 13, 1993, 43 30 970.4


Int. Cl.⁶ A01N 37/12; 37/18; 37/44; 43/54

U.S. Cl. 514—275


8 Claims

1. A fungicidal mixture containing in synergistic fungicidally effective amounts of:

a) a compound of the formula IA or IB




1.A



1.B

b) a pyrimidine of the formula II



II

where R is propyn-1-yl.

wherein the weight ratio of the compound IA or IB to the compound II is from 10:1 to 0.1:1.

5,589,480

TOPICAL APPLICATION OF OPIOID ANALGESIC DRUGS SUCH AS MORPHINE

George F. Elkhoury, 1561 Ramillo Ave., Long Beach, Calif. 90815, and Christoph Stein, 310 Warren Ave., #302, Baltimore, Md. 21230

Filed Aug. 17, 1994, Ser. No. 291,614

Int. Cl.⁶ A61K 31/485

U.S. Cl. 514—282

19 Claims

1. A method of inducing analgesia in inflamed skin, comprising topically administering to a patient in need of such treatment a topically effective amount of an opioid analgesic agent, which amount is systemically ineffective for induction of analgesia, admixed with a pharmaceutically acceptable excipient for topical administration, whereby effective analgesia is induced in the substantial absence of transdermal delivery of the opioid analgesic agent to the systemic circulation.

5,589,481

NERVE GROWTH FACTOR PRODUCTION ACCELERATORS AND COMPOSITIONS FOR PREVENTING OR TREATING NEURONAL DEGENERATION

Tomoko Tsuji; Kohji Yamaguchi; Kiyosi Kondo, all of Kanagawa, and Teizi Urakami, Tokyo, all of Japan, assignors to Mitsubishi Gas Chemical Company, and Sagami Chemical Research Center, both of Tokyo, Japan

Continuation of Ser. No. 9,806, Jan. 27, 1993, abandoned.

This application Feb. 22, 1994, Ser. No. 200,912

Claims priority, application Japan, Feb. 7, 1992, 4-056677;


Feb. 20, 1992, 4-069382

Int. Cl.⁶ A61K 31/44

U.S. Cl. 514—287

7 Claims

1. A method for accelerating the production of nerve growth factor in a non-diabetic host in need of such acceleration using a compound which is oxazopyrroloquinoline or an ester thereof represented by the formula:



wherein R represents a hydrogen atom or an alkyl group having 1-4 carbon atoms, which may be substituted with a hydroxyl, carboxyl, mercapto, carbamoyl, hydroxyphenyl, guanidyl, imidazolyl, or methylmercapto group, and R¹, R² and R³ represent a hydrogen atom or an alkyl, alkenyl or benzyl group, which may be the same or different, which method comprises administration to such host of an amount of such compound which is effective for such acceleration.

5,589,482

BENZO-THIOPHENE ESTROGEN AGONISTS TO TREAT PROSTATIC HYPERPLASIA

David D. Thompson, Groton, Conn., assignor to Pfizer Inc., New York, N.Y.


Filed Dec. 14, 1994, Ser. No. 356,011

Int. Cl.⁶ A61K 31/44; 31/445; 31/395; 31/40

U.S. Cl. 514—305



10 Claims

1. A method of treating prostatic hyperplasia in a mammal which comprises administering to a mammal in need of such treatment a compound of the formula




wherein:

R is OR¹ wherein R¹ is hydrogen, C₁-C₆ alkyl or phenyl optionally substituted with up to three substituents independently selected from C₁-C₆ alkyl, C₁-C₆ alkoxy or halogen; Y is phenyl, optionally substituted with 1 to 3 substituents independently selected from halo, hydroxy and C₁-C₃ alkyl; D is —CO— or —CH₂—; E is 1,4 linked phenylene; Z¹ is —OCH₂CH₂—, —CH₂CH₂—, —CH₂—, —OCH₂CHR²—, —C≡C—CH₂—; or Z¹ in combination with G is



wherein n is 0, 1 or 2; m is 1, 2 or 3; or G is azabicyclohept-2-yl; or G in combination with Z¹ is



and geometric and optical isomers pharmaceutically acceptable esters, ethers and salts thereof.

5,589,483

ISOQUINOLINE POLY (ADP-RIBOSE) POLYMERASE INHIBITORS TO TREAT SKIN DISEASES ASSOCIATED WITH CELLULAR SENESCENCE

Michael D. West, Belmont, Calif., assignor to Geron Corporation, Menlo Park, Calif.

Filed Dec. 21, 1994, Ser. No. 361,798

Int. Cl.⁶ A61K 31/47

U.S. Cl. 514—310

3 Claims

1. A method for delaying the onset of cell senescence associated with skin aging in a human comprising administering to fibroblast cells in the human an amount of an isoquinoline PADPRP inhibitor effective to increase the maximum achievable number of cumulative population doublings of the fibroblast cells, whereby the proliferative capacity of the fibroblast cells is increased.

5,589,484

4-QUINOLINYL DERIVATIVES

Marc G. Venet, Le Mesnil Esnard; Jérôme E. G. Guillemont, Oissel; Daniel F. J. Vernier, Rouen, all of France, and Frank C. Odds, Schilde, Belgium, assignors to Janssen Pharmaceutica N.V., Beerse, Belgium

PCT No. PCT/EP93/02884, § 371 Date Apr. 4, 1995, § 102(e) Date Apr. 4, 1995, PCT Pub. No. WO94/10164, PCT Pub. Date May 11, 1994


PCT Filed Oct. 19, 1993, Ser. No. 428,176

Int. Cl.⁶ C07D 403/06; A61K 31/47



U.S. Cl. 514—314

15 Claims

1. A compound having the formula




a pharmaceutically acceptable acid addition salt thereof, a stereochemically isomeric form thereof, a pharmaceutically acceptable quaternized form thereof or an N-oxide thereof, wherein —A— represents a bivalent radical of formula




(e).




(f).



(g).



(h).



(i).

R¹, R², R³, R⁴, R⁵, R⁶ and R⁷ each independently represent hydrogen, halo, hydroxy, C₁₋₄alkyloxy, C₁₋₄alkyl, trifluoromethyl, amino, mono- or di(C₁₋₄alkyl)amino or nitro, provided that when one substituent on an aromatic ring is a nitro then the other substituents on said aromatic ring are other than nitro.

5,589,485

DORRIGOCIN ANTITUMOR AGENTS

Jill E. Hochlowski, Green Oaks; Marianna Jackson, Waukegan, both of Ill.; Sunil K. Kadam, Kenosha, Wis.; James P. Karwowski, Mundelein, and James B. McAlpine, Libertyville, both of Ill., assignors to Abbott Laboratories, Abbott Park, Ill.

Division of Ser. No. 164,234, Dec. 9, 1993, Pat. No. 5,484,799.


This application Apr. 26, 1995, Ser. No. 429,405

Int. Cl.⁶ C07D 211/40; 211/76; A61K 31/44; 31/445


U.S. Cl. 514—315

6 Claims

1. A method of controlling ras-gene dependent tumor development in a patient in need of such treatment, comprising administering to the patient a therapeutically effective amount of a compound having the formula



or a pharmaceutically acceptable salt, ester, amide or pro-drug thereof, wherein R is selected from the group consisting of



and

5,589,486 N-HYDROXYALKYL-SUBSTITUTED 1,2,3,6-TETRAHYDRO-PYRIDINE AND PIPERIDINE DERIVATIVES

Kalman Harsanyi; Tibor Gizur; Eva Agai-Csongor; Anna Kallai-Sohonyai; Marta Kapolnas-Pap; Eva Csizer; Bela Hegedus; Laszlo Szporny; Bela Kiss; Egon Karpati; Eva Palosi; Zsolt Szombathelyi; Adam Sarkadi; Aniko Gere; Mihaly Bodo; Katalin Csomor; Judit Laszy; Zsolt Szentirmai; Erzsebet Lapis; Sandor Szabo, all of Budapest; Peter Bod, Gyomro, and Attila Csehi, Göd, all of Hungary, assignors to Richter Gedeon Vegyeszeti Gyar Rt., Budapest, Hungary

PCT No. PCT/HU92/00050, § 371 Date Jan. 17, 1995, § 102(e) Date Jan. 17, 1995, PCT Pub. No. WO93/11107, PCT Pub. Date Jun. 10, 1993

PCT Filed Dec. 1, 1992, Ser. No. 244,867

Claims priority, application Hungary, Dec. 2, 1991, 3747/91; Jun. 9, 1992, 3747/91

Int. Cl.⁶ A61K 31/445; C07D 211/22

U.S. Cl. 314—317

8 Claims

1. A compound selected from the group consisting of:

- 1-[4-(4-chlorobenzyl)phenyl]-2-(4-phenyl-1,2,3,6-tetrahydro-1-pyridyl)ethanol;
- 1-[4-(4-chlorobenzyl)phenyl]-3-(4-phenyl-1-piperidyl)propanol;
- 1-[4-(4-chlorobenzyl)phenyl]-4-(4-phenyl-1,2,3,6-tetrahydro-1-pyridyl)butanol;
- 3-[4-(4-fluorophenyl)-1-piperidyl]-1-(1,1'-biphenyl-4-yl)propanol; and
- 3-[4-(4-chlorophenyl)-1,2,3,6-tetrahydro-1-pyridyl]-1-(2,4-dichlorophenyl)propanol; or a pharmaceutically acceptable acid addition salt thereof.

5,589,487

PIPERIDINE DERIVATIVES AND PROCESS FOR THEIR PRODUCTION

Thomas E. D'Ambra, Wynantskill, N.Y., assignor to Albany Molecular Research, Inc., Albany, N.Y.


Division of Ser. No. 83,102, Jun. 24, 1993, abandoned. This application Feb. 2, 1995, Ser. No. 382,425

Int. Cl.⁶ A61K 31/445; C07D 211/34

U.S. Cl. 514—317

20 Claims

1. A process of preparing a piperidine derivative compound of the formula:



wherein

R₁ is hydrogen or hydroxy;

X is the NH group;

Y is an ethylene or a C₃-C₆ straight or branched alkylene, or a cyclopentylene, cyclohexylene or cycloheptylene group;

R₁ is the OCOR₃ group, wherein R₃ is methyl, ethyl or C₃-C₅ straight or branched alkyl, or the residue from a 5- or 6-membered monocyclic heterocycle which can be aromatic or partially or totally hydrogenated, containing one or more hetero-atoms selected independently from O, N and S;

R₂ is hydrogen, hydroxy, halogen, C₁₋₄ alkyl, C₁₋₄ alkoxy, trifluoromethyl, sulfo, nitro, amino, or mono- or di- C₁₋₄ alkylamino; or

R₁ and R₂, taken together, are the methylenedioxy group; with the proviso that when Y is ethylene and R₂ is hydrogen, R₁ cannot be the OCOR₃ group at the 2- position in which R₃ is methyl;

and the pharmaceutically acceptable acid salts thereof.

5,589,491

INJECTION AND INJECTION KIT CONTAINING OMEPRAZOLE AND ITS ANALOGS

Shigeo Nakanishi, Neyagawa; Tetsuo Tominaga, Itami; Iwao Yamanaka, Osaka; Takashi Higo, Ikeda, and Toshiyuki Shibata, Nakatsu, all of Japan, assignors to Astra Aktiebolag, Sodertalje, Sweden

PCT No. PCT/JP93/00998, § 371 Date Jan. 18, 1995, § 102(e) Date Jan. 18, 1995, PCT Pub. No. WO94/02141, PCT Pub. Date Feb. 3, 1994

PCT Filed Jul. 15, 1993, Ser. No. 373,245

Claims priority, application Japan, Jul. 28, 1992, 4-201203

Int. Cl.⁶ A61K 31/44; 31/415

U.S. Cl. 514—338

6 Claims

1. An injection solution comprising a 2-[(2-pyridyl)methylsulfinyl]benzimidazole compound or a salt thereof having antilulcer activity and an aqueous solvent devoid of non-aqueous solvent, wherein the pH of the injection solution is not less than 9.5 and not more than 11.5.

5,589,492

HETEROCYCLIC COMPOUNDS AND THEIR USE IN THE TREATMENT OF TYPE-II DIABETES

David Haigh, Horsham, England, assignor to SmithKline Beecham PLC, Brentford, England

PCT No. PCT/GB93/00735, § 371 Date Dec. 12, 1994, § 102(e) Date Dec. 12, 1994, PCT Pub. No. WO93/21166, PCT Pub. Date Oct. 28, 1993

PCT Filed Apr. 7, 1993, Ser. No. 318,615

Claims priority, application United Kingdom, Apr. 10, 1992, 9208016; Apr. 16, 1992, 9208451; Dec. 29, 1992, 9227046

Int. Cl.⁶ C07D 413/12; 213/74; A61K 31/42; 31/44

U.S. Cl. 514—339

12 Claims

1. A compound of formula (1):



or a tautomeric form thereof and/or a pharmaceutically acceptable salt thereof, and/or a pharmaceutically acceptable solvate thereof, wherein:

A¹ represents a substituted or unsubstituted aromatic heterocycl group;

A² represents a benzene ring having three optional substituents;

A³ represents a moiety of formula $-(CH_2)_m-CHR^1-$ wherein R¹ represents a halogen atom or a moiety of formula $S(O)_pA^4$ wherein A⁴ represents hydrogen, substituted or unsubstituted alkyl, aryl, aralkyl, alkylcarbonyl or an aromatic heterocycl group and p represents zero or an integer 1 or 2 and m represents zero or an integer in the range of from 1 to 5, or A³ represents a moiety of formula $-CH=CR^1-$ wherein R¹ is as defined above;

R² represents OR³ wherein R³ represents hydrogen, alkyl, aryl or aralkyl, or R² represents $-NR^4R^5$ wherein R⁴ and R⁵ each independently represent hydrogen or alkyl or R⁴ and R⁵ together with the nitrogen atom to which they are attached form a heterocyclic ring;

X represents O, S or NR wherein R represents a hydrogen atom, an alkyl group, an acyl group, an aralkyl group wherein the aryl moiety may be substituted or unsubstituted, or a substituted or unsubstituted aryl group; and

n represents an integer in the range of from 2 to 6.

5,589,493

ANILIDE DERIVATIVES AND THEIR USE FOR COMBATING BOTRYTIS

Karl Eicken, Wachenheim; Norbert Goetz, Worms; Albrecht Harreus, Ludwigshafen; Eberhard Ammermann, Heppenheim; Gisela Lorenz, Neustadt, and Harald Rang, Ludwigshafen, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

Division of Ser. No. 215,463, Mar. 21, 1994, Pat. No.

5,480,897, which is a division of Ser. No. 973,976, Nov. 9, 1992, Pat. No. 5,330,995. This application Jun. 7, 1995, Ser. No. 478,681


Claims priority, application Germany, Nov. 22, 1991, 41 38 387.7; Feb. 18, 1992, 42 04 764.1; Feb. 18, 1992, 42 04 766.8; Feb. 18, 1992, 42 04 767.6; Feb. 18, 1992, 42 04 768.4

Int. Cl.⁶ A01N 43/40; C07D 213/56

U.S. Cl. 514—355

16 Claims

1. A nicotinic anilide derivative of the formula I



wherein

R¹ is halogen, methyl, trifluoromethyl, methoxy, methylthio, methylsulfinyl, or methylsulfonyl, and

R² is unsubstituted or halogen-substituted C₃-C₁₂-alkyl, unsubstituted or halogen-substituted C₃-C₁₂-alkenyl, C₃-C₆-alkynyl, unsubstituted or halogen-substituted C₂-C₁₂-alkoxy, unsubstituted or halogen-substituted C₃-C₁₂-alkenyloxy, C₃-C₁₂-alkynyloxy, C₃-C₆-cycloalkyl, C₃-C₆-cycloalkenyl, C₅-C₆-cycloalkyloxy, C₃-C₆-cycloalkenyloxy, with the proviso that R² is not isopropyl when R¹ is chlorine and that when R¹ is halogen, R² is not unsubstituted or halogen-substituted ethoxy.

5,589,494

2-[(3-HETEROARYL-1-PYRROLIDINYL)ALKYL]-1,3-DIOXANES AND RELATED COMPOUNDS AND THEIR THERAPEUTIC UTILITY

Joseph T. Strupczewski, Flemington; Grover C. Helsley, Stockton; Edward J. Glamkowski, Warren; Yulin Chiang, Covent Station, all of N.J.; Kenneth J. Bordeau, Kintnersville, Pa.; Peter A. Nemoto, Raritan, N.J., and John J. Tegeler, Bridgewater, N.J., assignors to Hoechst-Roussel Pharmaceuticals, Inc., Summerville, N.J.


Division of Ser. No. 329,000, Oct. 25, 1994, which is a continuation-in-part of Ser. No. 144,265, Oct. 28, 1993, abandoned, which is a continuation-in-part of Ser. No. 969,383, Oct. 30, 1992, Pat. No. 5,364,866, which is a continuation-in-part of Ser. No. 788,269, Nov. 5, 1991, abandoned, which is a continuation-in-part of Ser. No. 944,705, Sep. 5, 1991, abandoned, which is a continuation of Ser. No. 619,825, Nov. 29, 1990, abandoned, which is a continuation of Ser. No. 456,790, Dec. 29, 1989, abandoned, which is a continuation-in-part of Ser. No. 354,411, May 19, 1989, abandoned. This application Jun. 6, 1995, Ser. No. 470,040

Int. Cl.⁶ A61K 31/495; 31/55; 31/505; C07D 401/00

U.S. Cl. 514—37.3

14 Claims

1. A compound of the formula:



wherein,

X is —O—, —S—, —NH—, or —N(R₂);

R₂ is selected from the group consisting of lower alkyl, aryl, lower alkyl, aryl, (C₃-C₁₀) cycloalkyl, aryl, (C₂-C₁₈) alkanoyl, (C₁-C₁₈) alkoxy, carbonyl and phenylsulfonyl groups;

aryl is as defined hereinafter;

p is 1 or 2;

Y is hydrogen, lower alkyl, hydroxy, chlorine, fluorine, bromine, iodine, lower alkoxy, trifluoromethyl, nitro, or amino;

R₁ is —CR₂₄R₂₇—(CR₂₃R₂₂)_n—, where n is 0, 1, 2 or 4; or —CHR₂₄CH=CH—CHR₂₄—,

—CHR₂₄—C≡C—CHR₂₄—,

—CHR₂₄—CH=CH—CR₂₃R₂₄—CHR₂₄—,


—CHR₂₄—CR₂₃R₂₄—CH=CH—CHR₂₄—,

CHR₂₄—C≡C—CR₂₃R₂₄—CHR₂₄—, or

—CHR₂₄—CR₂₃R₂₄—C≡C—CHR₂₄—,

the —CH=CH— bond being cis or trans;


R₂₃ is hydrogen, (C₁-C₁₈) linear alkyl, phenyl, hydroxy, (C₁-C₁₈) alkoxy, aryloxy, aryl (C₁-C₁₈) alkoxy, (C₁-C₁₈) alkanoyloxy, hydroxy (C₁-C₆) alkyl, (C₁-C₁₈) alkoxy (C₁-C₆) alkyl, phenyl (C₁-C₆) alkoxy, aryl (C₁-C₁₈) alkoxy (C₁-C₆) alkyl, (C₁-C₁₈) alkanoyloxy (C₁-C₆) alkyl or



where

Z₁ is lower alkyl, —OH, lower alkoxy, —CF₃, —NO₂, —NH₂, or halogen, and p is as previously defined;

R₂₄ is hydrogen, (C₁-C₁₈) linear alkyl, phenyl, hydroxy (C₁-C₆) alkyl, (C₁-C₁₈) alkoxy (C₁-C₆) alkyl, phenyl (C₁-C₆) alkoxy, aryl (C₁-C₁₈) alkoxy (C₁-C₆) alkyl (C₁-C₁₈) alkanoyloxy (C₁-C₆) alkyl or




where

Z₁ and p are as previously defined;

R₂₇ is hydrogen or R₂₄ and R₂₇ taken together with the carbon to which they are attached form C=O or C=S;

alkyl is (C₁-C₁₈) alkyl;

aryl is phenyl or



where

R₃ is hydrogen, lower alkyl, lower alkoxy, hydroxy, chlorine, fluorine, bromine, iodine, lower monoalkylamino, lower dialkylamino, nitro, cyano, trifluoromethyl, or trifluoromethoxy; and

R₁₀ is hydrogen, lower alkyl, C₁-C₃ acyl, aryl, —C(=O)-aryl or —C(=O)-heteroaryl, where aryl and heteroaryl are as defined above; and

m is 1, 2, or 3;

all geometric, optical, and stereoisomers thereof, or a pharmaceutically acceptable acid addition salt thereof.

5,589,495

2-[(3-HETEROARYL-1-PYRROLIDINYL)ALKYL]-1,3-INDANDIONES AND RELATED COMPOUNDS AND THEIR THERAPEUTIC UTILITY

Edward J. Glamkowski, Warren, and Yulin Chiang, Covent Station, both of N.J., assignors to Hoechst Marion Roussel, Inc., Kansas City, Mo.



Division of Ser. No. 329,000, Oct. 25, 1994, which is a continuation-in-part of Ser. No. 144,265, Oct. 28, 1993, abandoned, which is a continuation-in-part of Ser. No. 969,383, Oct. 30, 1992, Pat. No. 5,364,866, which is a continuation-in-part of Ser. No. 788,269, Nov. 5, 1991, abandoned, which is a continuation-in-part of Ser. No. 944,705, Sep. 5, 1991, abandoned, which is a continuation of Ser. No. 619,825, Nov. 29, 1990, abandoned, which is a continuation of Ser. No. 456,790, Dec. 29, 1989, abandoned, which is a continuation-in-part of Ser. No. 354,411, May 19, 1989, abandoned. This application Jun. 6, 1995, Ser. No. 471,515

Int. Cl.⁶ A61K 31/495; 31/55; 31/505; 31/44; C07D 401/04; 403/04; 407/04; 419/04

U.S. Cl. 514—373

14 Claims

1. A compound of the formula:



wherein

X is —O—, —S—, —NH—, or —N(R₂);

R_2 is selected from the group consisting of lower alkyl, aryl, lower alkyl, aryl, cycloalkyl, aryl, alkanoyl, alkoxy, carbonyl, and phenylsulfonyl groups; aryl is as defined hereinafter; p is 1 or 2;

Y is hydrogen, lower alkyl, hydroxy, chlorine, fluorine, bromine, iodine, lower alkoxy, trifluoromethyl, nitro, or amino;

R_1 is $-\text{CR}_{24}\text{R}_{27}-(\text{CR}_{23}\text{R}_{27})_n-$, where n is 0, 1, 2 or 3; or $-\text{CHR}_{24}\text{CH}=\text{CH}-\text{CHR}_{24}-$,

$-\text{CHR}_{24}-\text{C}\equiv\text{C}-\text{CHR}_{24}-$,

$-\text{CHR}_{24}-\text{CH}=\text{CH}-\text{CR}_{23}\text{R}_{24}-\text{CHR}_{24}-$,


$-\text{CHR}_{24}-\text{CR}_{23}\text{R}_{24}-\text{CH}=\text{CH}-\text{CHR}_{24}-$,

$-\text{CHR}_{24}-\text{C}\equiv\text{C}-\text{CR}_{23}\text{R}_{24}-\text{CHR}_{24}-$, or

$-\text{CHR}_{24}-\text{CR}_{23}\text{R}_{24}-\text{C}\equiv\text{C}-\text{CHR}_{24}-$,


the $-\text{CH}=\text{CH}-$ bond being cis or trans;

R_{23} is hydrogen, $(\text{C}_1-\text{C}_{18})$ linear alkyl, phenyl, hydroxy, $(\text{C}_1-\text{C}_{18})$ alkoxy, aryloxy, aryl $(\text{C}_1-\text{C}_{18})$ alkoxy, $(\text{C}_1-\text{C}_{18})$ alkanoyloxy, hydroxy (C_1-C_6) alkyl, $(\text{C}_1-\text{C}_{18})$ alkoxy (C_1-C_6) alkyl, phenyl (C_1-C_6) alkoxy, aryl $(\text{C}_1-\text{C}_{18})$ alkoxy (C_1-C_6) alkyl, $(\text{C}_1-\text{C}_{18})$ alkanoyloxy (C_1-C_6) alkyl or



where Z_1 is lower alkyl, $-\text{OH}$, lower alkoxy, $-\text{CF}_3$, $-\text{NO}_2$, $-\text{NH}_2$, or halogen, and p is as previously defined;

R_{24} is hydrogen, $(\text{C}_1-\text{C}_{18})$ linear alkyl, phenyl, hydroxy (C_1-C_6) alkyl, $(\text{C}_1-\text{C}_{18})$ alkoxy (C_1-C_6) alkyl, phenyl (C_1-C_6) alkoxy, aryl $(\text{C}_1-\text{C}_{18})$ alkoxy (C_1-C_6) alkyl, $(\text{C}_1-\text{C}_{18})$ alkanoyloxy (C_1-C_6) alkyl or



where Z_1 and p are as previously defined;

R_{27} is hydrogen or R_{24} taken together with the carbon to which they are attached form $\text{C}=\text{O}$ or $\text{C}=\text{S}$;

where R_4 is hydrogen, lower alkyl, lower alkoxy, hydroxy, tri (C_1-C_6) alkylsilyloxy, hydroxy lower alkyl, alkanoyloxy lower alkyl, amino, mono- or dialkylamino, $(\text{C}_1-\text{C}_{18})$ acyl amino, $(\text{C}_1-\text{C}_{18})$ alkanoyl, trifluoromethyl, chlorine, fluorine, bromine, $-\text{O}-\text{C}(=\text{O})-(\text{C}_1-\text{C}_{18})$ straight or branched chain-alkyl or $-\text{C}(=\text{O})$ -aryl;

where R_{28} is hydrogen, (C_1-C_6) alkyl, aryl (C_1-C_6) alkyl, phenyl, or substituted phenyl;

where aryl is phenyl or



where R_5 is hydrogen, lower alkyl, lower alkoxy, hydroxy, chlorine, fluorine, bromine, iodine, lower monoalkylamino, lower dialkylamino, nitro, cyano, trifluoromethyl, or trifluoromethoxy;

m is 1, 2, or 3;

and, any hydroxyl group attached to an aliphatic or aromatic carbon atom, or any primary or secondary nitrogen atom may be acylated with a $(\text{C}_4-\text{C}_{18})$ carboxylic group, in addition, any nitrogen atom may alternatively be acylated with a $(\text{C}_4-\text{C}_{18})$ alkoxy carbonyl group;

all geometric, optical, and stereoisomers thereof, or a pharmaceutically acceptable acid addition salt thereof.

5,589,496 FUSED BENZENE OXYACETIC ACID DERIVATIVES WHICH HAVE PGI₂ RECEPTOR AGONIST ACTIVITY Nobuyuki Hamanaka; Kanji Takahashi, and Hidekado Tokumoto, all of Osaka, Japan, assignors to Ono Pharmaceutical Co., Ltd., Osaka, Japan







Division of Ser. No. 997,492, Dec. 28, 1992, Pat. No. 5,389,666. This application Nov. 3, 1994, Ser. No. 334,395
Claims priority, application Japan, Dec. 27, 1991, 3-360502;
Jul. 14, 1992, 4-209587

Int. Cl.⁶ C07D 261/02; A61K 31/42




U.S. Cl. 514—374

11 Claims

1. A fused benzeneoxyacetic acid derivative of the formula (I):



-continued



R^1 is

(i) a hydroxy group,

(ii) a C_{1-4} alkoxy group, or

(iii) NR^2R^3 ;

R^2 and R^3 each, independently, is

(i) a hydrogen atom or

(ii) a C_{1-4} alkyl group; or

R^2 and R^3 , taken together with a nitrogen atom bond to R^2 and R^3 are the residue of an amino acid;

R^4 each, independently, is

(i) a hydrogen atom,

(ii) a C_{1-4} alkyl group,

(iii) a phenyl group, or

(iv) a C_{1-4} alkyl group substituted by one or two phenyl group;

the said phenyl group may also be substituted by one to three of a C_{1-4} alkyl group, a C_{1-4} alkoxy group, a halogen atom, a nitro group or a trihalomethyl group,

Y is an oxygen atom or a sulfur atom;

e is 3-5;

f is 1-3;

l is 1-3;

m is 1 or 2;

p is 1-4;


q is 0-2;

r is 1-4;

s is 0-3;

with the proviso that

(1) when A is








wherein

R^4 is a hydrogen atom,

q or s is not zero;

(2) when A is



wherein Y, l and m are the same meaning as hereinbefore defined,

and R^4 is a C_{1-4} alkyl group substituted by a hetero ring, a hetero

ring in R^4 should be bonded to the alkyl group via a carbon atom

in the hetero ring;

(3) $-(\text{CH}_2)_e$ or $-\text{CH}(\text{CH}_2)_f-$ should be bonded to the carbon atom at the position a or b in the ring; or non-toxic salts thereof or non-toxic acid addition salts thereof.


5,589,497 PHENYLIMIDAZOLIDINES André Claussner, Villemomble; François Goubet, Paris, and Jean-Georges Teutsch, Pantin, all of France, assignors to Roussel Uclaf, Romainville, France

Division of Ser. No. 68,736, May 28, 1993, Pat. No. 5,434,176.
This application Apr. 8, 1994, Ser. No. 225,230
Claims priority, application France, Jul. 8, 1992, 92 08432
Int. Cl.⁶ C07D 233/74


U.S. Cl. 514—386

17 Claims

1. A compound selected from the group consisting of compounds of the formula



wherein one of R_1 and R_2 is $-\text{CN}$, and the other is $-\text{CF}_3$, -A-B- is selected from the group consisting of



wherein X is $-\text{O}-$ or $-\text{S}-$, R_3 is alkyl of up to 12 carbon atoms optionally substituted with $-\text{OH}$, Y is $-\text{O}-$, $-\text{S}-$, or NH ; R_4 and R_5 are individually selected from the group consisting of hydrogen and alkyl of up to 12 carbon atoms optionally substituted with at least one halogen and their non-toxic pharmaceutically acceptable acid addition salts.

5,589,498 TRANSDERMAL DELIVERY OF THE ACTIVE ENANTIOMER OF KETOROLAC

Judy M. Mohr, Menlo Park; Richard W. Baker, Palo Alto, and Lisa A. Nakajima, San Jose, all of Calif., assignors to Pharmetrix Corporation, Menlo Park, Calif.

Continuation of Ser. No. 8,814, Jan. 22, 1993, abandoned, which is a continuation of Ser. No. 973,801, Nov. 9, 1992, abandoned. This application Jun. 6, 1995, Ser. No. 470,648
Int. Cl.⁶ A61K 31/40; 9/70

U.S. Cl. 514—413

19 Claims

1. A patch for the transdermal administration of ketorolac and through a patient's skin for a period of 12 hours or more, said

patch comprising:

(a) an occlusive backing layer having a skin-facing side, and

(b) a drug depot having a skin-facing side and a skin-distal side in contact with said skin-facing side of said backing layer, said depot comprising,

i. (-) ketorolac,

ii. an enhancer combination comprising a plasticizing-type enhancer and a solvent-type enhancer, said plasticizing-type enhancer being a member selected from the group consisting of isopropyl myristate, caprylic triglyceride, capric triglyceride and glyceryl oleate, and said solvent-type enhancer being a member selected from the group consisting of propylene glycol, glycerin and butanol, and

iii. an adhesive polymer in which said (-) ketorolac and said enhancer are dispersed,

wherein said patch delivers (-) ketorolac through the skin facing side of said patch and through said patient's skin at a flux rate of about 20 $\text{g}/\text{cm}^2\cdot\text{hr}$ or more.


5,589,499
DOPAMINERGIC AGENTS FOR THE TREATMENT OF CEREBRAL AND PERIPHERAL BLOOD FLOW DISORDERS

Gosbert Weth, Coburgerstrasse 6, W-8520, Erlangen, Germany
 Continuation of Ser. No. 981,368, Nov. 25, 1992, abandoned.
 This application Nov. 14, 1994, Ser. No. 339,423
 Int. Cl.⁶ A61K 31/40

U.S. Cl. 514—423

4 Claims

1. A method for increasing the rate of cerebral or peripheral blood flow in a patient who already suffers from cerebral or peripheral blood flow disorders which comprises administering to such a patient an amount of a compound effective to increase the flow of blood in said patient and to cause a significant increase of dopamine in said patient, wherein said compound is of the Formula (I):



wherein R¹ and R² (as shown by the broken line) together are a pyrrolidine ring;

R³ is hydrogen;

R⁴ is hydrogen, alkyl or



where R⁵ is hydrogen or lower alkyl and R⁶ is 2-phenylethyl or n-propyl, and Z is a straight-chain or branched-chain alkylene having from 1 to 3 carbon atoms, or a pharmaceutically acceptable salt thereof, wherein the compound is administered to the patient at a dosage of 2 to 20 mg per day.

5,589,500
SUBSTITUTED 1,1,2-TRIPHENYLBUTENES AND THEIR USE IN THE TREATMENT OF CANCER

Karen J. Edwards, Natal, South Africa; Michael Jarman, Tooting, England; Charles A. Laughton, Sutton, England; Stephen Neldie, Oxhey, England, and Ian R. Hardecastle, Sutton, England, assignors to British Technology Group Limited, London, England

PCT No. PCT/GB93/00889, § 371 Date Jan. 17, 1995, § 102(e) Date Jan. 17, 1995, PCT Pub. No. WO93/22275, PCT Pub. Date Nov. 11, 1993

PCT Filed Apr. 29, 1993, Ser. No. 331,582


Claims priority, application United Kingdom, May 1, 1992, 9209509; Feb. 26, 1993, 9303982

Int. Cl.⁶ C07C 217/18; C07D 295/088; A61K 31/135; 31/40

U.S. Cl. 514—428

13 Claims

1. Compounds of the general formula



wherein n is an integer of from 3 to 8, the iodo substituent is in the 3- or 4-position and R¹ and R², which may be the same or different, represent C₁₋₃ alkyl groups or R¹ represents a hydrogen atom and R² a C₁₋₃ alkyl group or R¹ and R² together with the nitrogen atom to which they are attached represent a saturated heterocyclic group, in the form of their free bases or pharmaceutically acceptable acid addition salts.

5,589,501

PHARMACEUTICAL COMPOUNDS

Jesus E. Carrera; Almudena R. Esteban, both of Madrid, Spain; André Mann, Ostwald; Angèle Schoenfelder, Lampertheim, both of France; Darryle D. Schoepp, Indianapolis, Ind.; Concepcion P. Tercero, Madrid, Spain, and Camille-Georges Wermuth, Strasbourg, France, assignors to Eli Lilly and Company, Indianapolis, Ind.; Université Louis Pasteur, Strasbourg Cedex, France, and Lilly, S.A., Madrid, Spain


Filed Nov. 22, 1994, Ser. No. 343,817

Int. Cl.⁶ C07C 229/36; C07D 257/04; A61K 31/195; 31/41

U.S. Cl. 514—438

7 Claims

1. A compound of the formula



in which m is 1 or 2, n and q are each 0 or 1 to 5, and p is 0 or 1.

X is —CO₂H or tetrazolyl,


Y is —CH=CH—, and

Z is

(i) phenyl, naphthyl or thienyl, said phenyl, naphthyl and thienyl being optionally substituted,

(ii) —CHR¹R² where R¹ and R² are each phenyl, naphthyl or thienyl, said phenyl, naphthyl and thienyl being optionally substituted, or

(iii)



where r is 0 or 1 to 3 and the phenyl rings are optionally substituted; provided that when Z is phenyl and m is 1, p is 1; or a salt or ester thereof.

5,589,502
BACCATIN DERIVATIVES AND PROCESSES FOR PREPARING THE SAME

Kenji Tsujihara, Urawa; Tomiki Hashiyama, Washimiya-machi; Motoaki Ohashi, Koganei, and Noriyuki Nakanishi, Kawaguchi, all of Japan, assignors to Tanabe Seiyaku Co., Ltd., Osaka, Japan

Filed Nov. 15, 1995, Ser. No. 558,772


Claims priority, application Japan, Nov. 17, 1994, 6-283780; Sep. 28, 1995, 7-251185

Int. Cl.⁶ C07D 305/14; A61K 31/335

U.S. Cl. 514—449

12 Claims

1. A compound represented by the formula [I]:



wherein R³ represents a lower alkanoyl group; R⁴ represents a substituted or unsubstituted benzoyl group; ring A represents a substituted or unsubstituted cyclopropane ring; X represents a single bond or a group represented by —O—, —S— or —NH—; R represents a substituted or unsubstituted lower alkyl group (wherein said lower alkyl group may have a cycloalkyl moiety), a substituted or unsubstituted aryl group or a substituted or unsubstituted aromatic heterocyclic group; E represents a hydrogen atom or a group represented by —CO(CH₂)_nZY; Y represents a residue obtained from an amino acid or a dipeptide by removing a hydroxyl group in one carboxyl group (wherein an amino group existing in said residue may be protected, and a carboxyl group existing in said residue may be esterified or amidated); Z represents a group represented by the formula of —O— or —NH—; and n represents 1, 2, 3, 4, 5 or 6, or a pharmaceutically acceptable salt thereof.

5,589,503
ENDOPARASITICIDAL COMPOSITIONS

Norbert Mencke, Leverkusen; Achim Harder, Köln, and Peter Jeschke, Leverkusen, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Filed Jan. 4, 1995, Ser. No. 368,515

Claims priority, application Germany, Jan. 11, 1994, 44 00 464.8

Int. Cl.⁶ A61K 31/335

U.S. Cl. 514—450

5 Claims

1. A composition comprising approximately equal amounts by weight of a compound selected from the group consisting of praziquantel and epsiprantel; and one compound is selected from the group consisting of cyclo(-MeLeu-D-Lac-MeLeu-D-PhLac-MeLeu-D-Lac-MeLeu-D-PhLac-) and cyclo(-MeLeu-D-Lac-MeLeu-D-p-MorPhLac-MeLeu-D-Lac-MeLeu-D-p-MorPhLac-).

5,589,504
TREATMENT OF NEWBORN JAUNDICE

Andrew J. Dannenberg, New York, and Jayanta R. Chowdhury, New Rochelle, both of N.Y., assignors to Cornell Research Foundation, Inc., Ithaca, and Albert Einstein College of Medicine of Yeshiva University, a Division of Yeshiva University, Bronx, both of N.Y.

Filed Jul. 26, 1994, Ser. No. 279,899

Int. Cl.⁶ A61K 31/36; 31/195; 31/185; 31/095

U.S. Cl. 514—456

6 Claims

1. A method of prophylaxis or treatment of newborn jaundice comprising administering to a subject in need of said prophylaxis or treatment a therapeutically effective amount of a compound which is not habit-forming and which does not cause drowsiness and which does not contain heavy metals or arsenic and which at a concentration of less than 50 μM doubles the quinone reductase specific activity of Hepa 1clc7 cells, said compound being selected from the group consisting of Michael reaction acceptors; diphenols, quinones and compounds which are metabolized to these in Hepa 1clc7 cells; isothiocyanates; fumarates; maleates; 1,2-dithiole-3-thione; beta-naphthoflavone; methyl propiolate; and crotonaldehyde.

5,589,505
METHOD OF TREATING WRINKLES USING QUINIC ACID OR QUINOLACTONE

Ruey J. Yu, Ambler, and Eugene J. Van Scott, Abington, both of Pa., assignors to Tristrata Technology, Inc., Wilmington, Del.

Continuation of Ser. No. 179,190, Jan. 10, 1994, Pat. No. 5,470,880, which is a continuation of Ser. No. 89,101, Jul. 12, 1993, Pat. No. 5,389,677, which is a division of Ser. No. 8,223, Jan. 22, 1993, abandoned, which is a continuation of Ser. No. 812,858, Dec. 23, 1991, abandoned, which is a continuation of Ser. No. 469,738, Jan. 19, 1990, abandoned, which is a continuation of Ser. No. 945,680, Dec. 23, 1986, abandoned. This application Jun. 5, 1995, Ser. No. 463,724

Int. Cl.⁶ A61K 7/48; 31/19; 31/365

U.S. Cl. 514—470

10 Claims

1. Method of visibly reducing a human skin wrinkle comprising topically applying to said wrinkle a composition comprising quinic acid or a topically effective salt thereof, or quinolactone in an amount and for a period of time sufficient to visibly reduce said wrinkle, wherein said wrinkle is a facial wrinkle.

5,589,506
STILBENE DERIVATIVE AND STILBENE ANALOG DERIVATIVE, AND USE THEREOF

Koichi Hashimoto, Yokohama; Akio Yamada, Chigasaki; Hirokazu Hamano, Isehara; Shigehiro Mori, Zama, and Hisako Moriuchi, Yokohama, all of Japan, assignors to Morinaga Milk Industry Co., Ltd., Tokyo, Japan

PCT No. PCT/JP94/00390, § 371 Date Dec. 30, 1994, § 102(e) Date Dec. 30, 1994, PCT Pub. No. WO94/20456, PCT Pub. Date Sep. 15, 1994

PCT Filed Mar. 10, 1994, Ser. No. 331,618


Claims priority, application Japan, Mar. 10, 1993, 5-074992; Jun. 28, 1993, 5-182027; Aug. 5, 1993, 5-212097; Aug. 19, 1993, 5-225030

Int. Cl.⁶ A61K 31/275; C07C 255/34

U.S. Cl. 514—520

15 Claims

1. A compound of the formula:



wherein

R¹ is hydrogen or hydroxy;
R² and R³ are different and each is hydrogen or cyano; and
R⁴ is lower alkyl, lower alkoxy, halogen or trifluoromethyl.

5,589,507

METHOD FOR STERILIZING MEDICAL DEVICES UTILIZING A ROOM TEMPERATURE STERILANT

Robert T. Hall, II, Welch, and Bradley K. Onstad, Deephaven, both of Minn., assignors to Minntech Corporation, Minneapolis, Minn.

Filed Nov. 17, 1995, Ser. No. 558,236

Int. Cl.⁶ A01N 37/00; 37/02; 59/00; A61K 33/40

U.S. Cl. 514—557

28 Claims

1. A method of sterilizing a medical device comprising contacting a surface to be sterilized of the medical device with an anti-microbial composition having improved anti-corrosive properties, wherein the anti-microbial composition is made by combining sufficient amount of an ester of formic acid, an oxidizer and water to provide about 0.01 to about 10 wt. % of the ester of formic acid, from about 0.01 to about 10 wt. % of the oxidizer, from about 0.001 to about 5 wt. % of performic acid, and up to about 99.98 wt. % of water.

5,589,508

USE OF AN EMULSION TO PREPARE AN INTRAVENOUSLY ADMINISTERED MEDICAMENT FOR TREATING SKIN DISEASES

Ewald Schlotzer, Oberursel; Peter Mayser, Biebertal; Friedrich Grimminger, Butzbach; Werner Seeger, Lahnau; Burghard Weidner; Klaus Sommermeier, both of Rosbach, and Martin Thomas, Frankfurt am Main, all of Germany, assignors to Fresenius AG, Germany

PCT No. PCT/EP92/02285, § 371 Date Apr. 20, 1994, § 102(e) Date Apr. 20, 1994, PCT Pub. No. WO93/06812, PCT Pub. Date Apr. 15, 1993

PCT Filed Oct. 2, 1992, Ser. No. 211,644

Claims priority, application Germany, Oct. 11, 1991, 41 33 694.1

Int. Cl.⁶ A61K 31/20

U.S. Cl. 514—560

13 Claims

1. A method for treating a skin disease in a patient, comprising administering intravenously to a patient suffering from a skin disease an effective amount of an emulsion comprising at least one polyunsaturated long-chain omega-3 or omega-6 fatty acid, or a pharmaceutically acceptable ester or salt thereof, and a conventional additive.

5,589,509
METHODS OF REDUCING PORPHYRIN TOXICITY USING FATTY ACIDS

David F. Horrobin, Guildford, England, assignor to Efamol Limited, England

Continuation of Ser. No. 372,846, Jan. 13, 1995, abandoned, which is a continuation of Ser. No. 136,606, Oct. 15, 1993, abandoned, which is a continuation of Ser. No. 847,884, Mar. 10, 1992, abandoned, which is a continuation of Ser. No. 611,881, Nov. 13, 1990, abandoned, which is a division of Ser. No. 480,375, Feb. 14, 1990, Pat. No. 4,996,233. This application Mar. 6, 1996, Ser. No. 611,525

Claims priority, application United Kingdom, Sep. 13, 1985, 85/22670


Int. Cl.⁶ A61K 31/20; 31/40

U.S. Cl. 514—560

4 Claims

1. In a method of enhancing the effect of administered tumor cell-locating porphyrins in subsequent light irradiation to destroy tumor cells,

the improvement wherein, in conjunction with treatment of a patient having a tumor susceptible to porphyrin therapy with said porphyrin, there is administered an effect-enhancing amount of an essential fatty acid of the n-6 series or the n-3 series alone or in an acceptable pharmaceutical diluent or carrier, and wherein said porphyrin is HpD or a water-soluble, tumor-locating meso-porphyrin of the formula:



wherein R is hydroxy, amino or sulphhydryl and n is 1 to 3, alone or in a pharmaceutically acceptable diluent or carrier.

5,589,510

METHOD FOR INHIBITING RETROVIRAL INFECTION BY ADMINISTERING A NAPHTHALENESULFONIC ACID COMPOUND

Mitsunori Ono; Yumiko Wada, both of Lexington; Yaming Wu, Cambridge, all of Mass.; Hiroshi Kitaguchi, Kanagawa, Japan; Yumiko Jimbo, Asaka, Japan; Ryoichi Nemori, Kanagawa, Japan; Stephen Gilles, Hingham, and Kin-Ming Lo, Wellsley, both of Mass., assignors to Fuji Immunopharmaceuticals Corp., Lexington, Mass.


Continuation-in-part of Ser. No. 253,156, Jun. 2, 1994, abandoned. This application May 15, 1995, Ser. No. 441,219

Int. Cl.⁶ A61K 31/175; 31/16; 31/10

U.S. Cl. 514—590

14 Claims

1. A method for treating retroviral infection in a subject comprising administering to said subject a therapeutically effective amount of a naphthalenesulfonic acid compound of formula (I) or a pharmaceutically acceptable salt thereof:



wherein R¹¹ to R²⁷ are individually selected from the group consisting of a hydrogen atom, a hydroxyl group, an amino group which is optionally substituted with an alkyl group or an aryl group, a sulfo group, a carboxyl group, an amide group which is optionally substituted with an alkyl group or an aryl group, an acylamino group, a sulfonamide group, a sulfonylamino group, an alkoxy group and a halogen atom;

provided that at least one of R¹¹ to R¹⁷ is a hydroxyl group or an amino group, at least one of R²¹ to R²⁷ is a hydroxyl group or an amino group, at least one of R¹¹ to R¹⁷ is a sulfo group, and at least one of R²¹ to R²⁷ is a sulfo group;

A and B are individually selected from the group consisting of a hydrogen atom, an alkyl (C₁–C₄) group, an alkoxy (C₁–C₄) group, and a halogen atom.

5,589,511

METHOD FOR TREATING MIGRAINE HEADACHES USING OPTICALLY PURE S(+) FLUOXETINE

James W. Young, Palo Alto, Calif., and Timothy J. Barberich, Concord, Mass., assignors to Sepracor Inc., Marlborough, Mass.

Continuation-in-part of Ser. No. 67,380, May 26, 1993, abandoned, and Ser. No. 793,036, Nov. 15, 1991, abandoned, which is a continuation-in-part of Ser. No. 566,655, Aug. 13, 1990, Pat. No. 5,104,899, said Ser. No. 67,380 is a division of Ser. No. 793,036. This application Apr. 15, 1994, Ser. No. 228,240

Int. Cl.⁶ A61K 31/135

U.S. Cl. 514—646

10 Claims

1. A method of treating migraine headaches in a human, comprising administering to said human a therapeutically effective amount of S(+) fluoxetine or a pharmaceutically acceptable salt thereof, substantially free of its R(–) stereoisomer.

5,589,512

METHOD FOR TREATING BORDERLINE PERSONALITY DISORDER WITH SEROTONIN RE-UP TAKE BLOCKERS

Michael J. Norden, 348 NW 113th Pl., Seattle, Wash. 98177

Continuation of Ser. No. 870,360, Apr. 17, 1992, Pat. No. 5,283,263, which is a division of Ser. No. 610,339, Nov. 5, 1990, Pat. No. 5,114,976, which is a continuation of Ser. No. 294,461, Jan. 6, 1989, abandoned. This application Jan. 25, 1994, Ser. No. 186,232

Int. Cl.⁶ A61K 31/135; 31/435; 31/15; 31/445

U.S. Cl. 514—651

4 Claims

1. A method for treating borderline personality disorder in a patient in need thereof comprising administering to said patient a nontoxic dose of a serotonin re-uptake blocker.

5,589,513

(I) PHARMACEUTICAL COMPOSITION AND PROCESS FOR THE PREPARATION THEREOF

Kálmán Magyar; József Gaál; István Sziráki; József Lengyel; Anna Z. Szabó, all of Budapest; Katalin Mármárosi, Biatorbágy; István Hermecz, Budapest; István Szatmári, Budapest; Zoltán Török, Budapest, and Péter Körmöczy, Budapest, all of Hungary, assignors to Chinoin Gyógyszer és Vegyeszeti Termékek Gyára Rt., Budapest, Hungary

PCT No. PCT/HU92/00060, § 371 Date Jun. 17, 1994, § 102(e) Date Jun. 17, 1994, PCT Pub. No. WO93/12775, PCT Pub. Date Jul. 8, 1993

PCT Filed Dec. 18, 1992, Ser. No. 256,128

Claims priority, application Hungary, Dec. 20, 1991, 4060/91

Int. Cl.⁶ A01N 33/02; A61K 31/135

U.S. Cl. 514—654

3 Claims

1. A pharmaceutical composition for treating a neurodegenerative disease by selectively inhibiting MAO-B activity without inhibiting MAO-A activity and by inhibiting uptake of a biogenic amine to the brain, which consists essentially of:

(a) a fast-acting MAO-B inhibitor in an amount effective to inhibit MAO-B selected from the group consisting of deprenyl and p-fluoro-deprenyl or a pharmaceutically acceptable acid addition salt thereof; and

(b) a slow-acting inhibitor of uptake of a biogenic amine in an amount effective to inhibit uptake of a biogenic amine, said slow-acting inhibitor of uptake of a biogenic amine selected from the group consisting of deprenyl and p-fluoro-deprenyl or a pharmaceutically acceptable acid addition salt thereof.

5,589,514

ARYLCYCLOALKYL DERIVATIVES, THEIR PRODUCTION AND THEIR USE

Ramachandra G. Naik; Vilas N. Mumbalkar; Rangarajan Vasumathy; Aftab D. Lakdawala, all of Bombay; Mandakini V. Shirole, Thane; Bansi Lal, Bombay, all of Ind.; Jürgen Blumbach, Niedernhausen, Germany; Klaus U. Weithmann, Hofheim am Taunus, and Robert R. Bartlett, Darmstadt, both of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Germany

Continuation of Ser. No. 2,863, Jan. 14, 1993, abandoned.

This application May 19, 1995, Ser. No. 444,518


Claims priority, application European Pat. Off., Jan. 16, 1992, 92100664

Int. Cl.⁶ A61K 31/165; C07C 59/84

U.S. Cl. 514—681

4 Claims

1. Compounds of the formula III



wherein

R₂ is H or C₁–C₃-alkyl.

R₅ denotes one or two halogens, one or two C₁–C₆-alkyl groups, one or two C₁–C₃-alkoxy groups, hydroxy, CF₃ or —OCH₂—

O—, and a denotes an optional additional single bond.

5,589,515

COSMETIC COMPOSITION AND AN EMULSION COMPOSITION

Masao Suzuki, Nara-ken; Koichi Saito, Amagasaki, and Masahide Nakata, Nishinomiya, all of Japan, assignors to NOF Corporation, Japan

PCT No. PCT/JP92/01229, § 371 Date May 27, 1993, § 102(e) Date May 27, 1993, PCT Pub. No. WO93/05755, PCT Pub. Date Apr. 1, 1993

PCT Filed Sep. 25, 1992, Ser. No. 66,017

Claims priority, application Japan, Sep. 27, 1991, 3-276697; Dec. 11, 1991, 3-351403

Int. Cl.⁶ A61K 7/00; 31/185

U.S. Cl. 514—784

20 Claims

1. A composition as a cosmetic which comprises 0.1 to 99 weight % of a first component and 99.9 to 1 weight % of a second component which is water soluble the first component comprising 85 or more weight % of a cis-Δ⁹-octadecenoic acid or derivatives thereof included within 90 weight % or more of a cis-Δ⁹-alkenoic acid or derivatives thereof, wherein the first component is either insoluble in the second component, dissolved in the second component or emulsified in the second component.

5,589,516

LIQUID PREPARATION OF ANTITHROMBIN-III AND STABILIZING METHOD THEREOF

Katsuhiko Uriyu; Akimasa Ohmizu; Hajime Fukuyama; Kazuo Takechi, and Kazumasa Yokoyama, all of Hirakata, Japan, assignors to The Green Cross Corporation, Osaka, Japan

PCT No. PCT/JP94/00563, § 371 Date Dec. 5, 1994, § 102(e) Date Dec. 5, 1994, PCT Pub. No. WO94/22471, PCT Pub. Date Oct. 13, 1994

PCT Filed Apr. 5, 1994, Ser. No. 351,268

Claims priority, application Japan, Apr. 5, 1993, 5-100117; Dec. 24, 1993, 5-328205; Jan. 21, 1994, 6-005073

Int. Cl.⁶ A61K 35/16; 37/18; 37/64; 39/395

U.S. Cl. 514—2

32 Claims

1. A liquid pharmaceutical preparation of antithrombin-III, comprising an antithrombin-III dissolved in water, an organic acid which is a dibasic acid and/or a tribasic acid or a salt thereof, and a non-ionic surfactant.

5,589,517

MODIFIED ION EXCHANGE RESINS AND USE THEREOF

Takahiro Sugawara; Michi Watanabe; Naoko Sumitani; Miwa Shirasaki, and Toshitaka Suzuki, all of Ami-machi, Japan, assignors to Mitsubishi Chemical Corporation, Tokyo-to, Japan

Filed Apr. 6, 1995, Ser. No. 417,763


Claims priority, application Japan, Apr. 8, 1994, 6-070771; Aug. 11, 1994, 6-189405; Aug. 19, 1994, 6-195627; Sep. 5, 1994, 6-211510; Nov. 9, 1994, 6-275104; Nov. 9, 1994, 6-275105

Int. Cl.⁶ C07C 39/12; 39/06; 39/16

U.S. Cl. 521—33

8 Claims

1. In a process for preparing a bisphenol by the catalytic condensation reaction of a phenol with a ketone, the improvement which comprises the use of a catalyst which is a modified ion exchange resin comprising a strongly acidic ion exchange resin of a sulfonic acid type having an N,N-di-substituted mercaptoalkylamine ionically bound thereto, the N,N-di-substituted mercaptoalkylamine being represented by the formula (I):



wherein R¹ represents hydrogen or an alkyl group having 1-6 carbon atoms, and R⁰'s independently represent an alkyl group having 1-10 carbon atoms or the substituents R⁰ are bonded to each other at their ω-terminals to form an alkylene ring having 4-5 carbon atoms together with the nitrogen atom, a and b independently denote an integer from 0 to 3, and a+b equals 2 or 3.

5,589,518

BIODEGRADABLE FOAMED ARTICLES AND PROCESS FOR THE PREPARATION THEREOF

Catia Bastioli, Novara; Vittorio Bellotti, Fontaneto d'Agogna; Gianfranco Del Tredici, Sesto Calende, and Angelos Rallis, Novara, all of Italy, assignors to Novamont S.p.A., Italy

Continuation-in-part of Ser. No. 384,515, Feb. 6, 1995, abandoned. This application Jun. 6, 1995, Ser. No. 469,566

Claims priority, application Italy, Feb. 9, 1994, M194A0228

Int. Cl.⁶ C08J 9/24; 9/36

U.S. Cl. 521—55

25 Claims

1. Process for preparing biodegradable foamed articles from foamed particles having a density from 0.003 to 0.1 g/cm³ and said particles being of a composition comprising:

30 to 98.5% by weight of thermoplastic starch or a natural thermoplastic polymeric substance, which when converted into the thermoplastic state, is capable of absorbing an amount of water equal to at least 15% of its weight;

0.5 to 70% by weight of a thermoplastic polymer, and 0 to 20% of water based on the weight of the composition;

said process comprising the step of agglomerating the particles, or the particles and a coating agent capable of promoting the bonding between the particles when subjected to compression, by compression under heat conditions until reduction of the volume of the particles is from 20 to 500%.

5,589,519

PROCESS OF EXTRUDING LIGHTLY CROSSLINKED POLYOLEFIN FOAM


Dennis A. Knaus, 12 Marlin Dr., Malvern, Pa. 19355

Filed Sep. 30, 1994, Ser. No. 315,445

Int. Cl.⁶ C08J 9/18

U.S. Cl. 521—60

111 Claims



1. A method for the preparation of a lightly crosslinked polyolefin foam, comprising the steps of:

- providing a composition comprising at least one polyolefin;
- inducing light crosslinking in said composition;
- melting said lightly crosslinked composition into a molten mass;
- mixing said molten mass with a blowing agent at a first pressure to form an admixture;
- cooling said admixture to an appropriate foaming temperature; and
- extruding said cooled admixture at a second pressure into a lightly crosslinked polyolefin foam.

5,589,520

ACRYLONITRILE POLYMER COMPOSITION AND ARTICLES AND METHODS FOR THEIR PREPARATION


Edmund H. Merz, Melbourne Beach, Fla.; Roy A. White, Somers, Conn.; John P. Fouser, San Francisco, and Norman Fishman, Menlo Park, both of Calif., assignors to Solcas Polymer, Limited Partnership, Walpole, Mass.

Continuation of Ser. No. 191,171, Feb. 3, 1994, abandoned, which is a division of Ser. No. 822,288, Jan. 21, 1992, Pat. No. 5,304,590. This application Feb. 3, 1995, Ser. No. 384,448

Int. Cl.⁶ C08J 9/12

U.S. Cl. 521—64

6 Claims



1. A method of making a polymeric foam comprising polyacrylonitrile comprising:

- forming a free-flowing particulate polymer comprising polyacrylonitrile and having from about 5 percent to about 20 percent by weight of an absorption aid therein;
- mixing a liquid fugitive plasticizer with the particulate polymer to produce a free-flowing particulate polymer wherein the plasticizer is uniformly absorbed in the particulate polymer; and
- extruding the particulate polymer at sufficient temperature and with sufficient blowing agent to form a foamed polymer.

5,589,521

Patent Not Issued For This Number

5,589,522

INK COMPOSITION

Bradley L. Beach, Lexington, Ky.; James F. Feeman, Wyomissing, Pa.; Anna M. Pearson, Richmond, and Jing X. Sun, Lexington, both of Ky., assignors to Lexmark International, Inc., Lexington, Ky.

Filed Dec. 21, 1994, Ser. No. 360,200

Int. Cl.⁶ C03C 17/00

U.S. Cl. 523—160

13 Claims

1. An aqueous ink composition for ink jet printers comprising an aqueous carrier, a pigment, and a polymer component selected from a graft polymer comprising:

- a hydrophilic polyacrylic acid backbone of weight average molecular weight between 1000 and 5000; and
- hydrophobic segment side chains, in amount of one to ten side chains attached to one backbone chain.

5,589,523

MICROCAPSULE-TYPE CURING AGENT, METHOD FOR PRODUCING THE SAME, THERMOSETTING RESIN COMPOSITION, PREPREG AND FIBER REINFORCED COMPOSITE MATERIAL

Ryuji Sawaoka, Ehime; Shinji Kouchi, and Toshio Muraki, both of Matsuyama, all of Japan, assignors to Toray Industries, Inc., Japan

Division of Ser. No. 401,195, Mar. 9, 1995. This application Jun. 6, 1995, Ser. No. 468,445

Claims priority, application Japan, Mar. 15, 1994, 6-043679

Int. Cl.⁶ C08K 9/10

U.S. Cl. 523—211

7 Claims

1. A method for producing a microcapsule curing agent comprising the steps of:

- dissolving i) a water-insoluble curing agent for a thermosetting resin and ii) a water-insoluble thermoplastic resin in an organic solvent and forming an organic solution;
- forming an emulsion solution by initially adding water to the organic solution and, thereafter, further adding water to the organic solution and transforming the organic solution into an emulsion solution in which an organic solvent phase is dispersed in said water; and removing said organic solvent from the emulsified solution.

5,589,524

POLYPHENYLENE SULFIDE RESIN COMPOSITION AND LIGHT REFLECTIVE MOLDED ARTICLE

Yasuhisa Ogita, and Toshikazu Kato, both of Mie, Japan, assignors to Tosoh, Corporation, Yamaguchi, Japan

Filed Jul. 25, 1995, Ser. No. 507,015

Claims priority, application Japan, Jul. 27, 1994, 6-175185

Int. Cl.⁶ C08K 9/06

U.S. Cl. 523—212

9 Claims

1. A polyphenylene sulfide resin composition consisting of from 40 to 60% by weight of a polyphenylene sulfide resin having a melt viscosity of from 300 to 4,000 poises determined at a temperature of 300° C. under a load of 10 kg, from 30 to 50% by weight of calcium carbonate having an average particle size of from 1 to 7 μm, from 8 to 25% by weight of mica having an average particle size of from 1 to 10 μm, and one or more mold releasing agents.

5,589,525

PROCESS FOR PREPARING NOVEL HIGH SOLIDS NON-AQUEOUS POLYMER COMPOSITIONS

Wood E. Hunter, Pittsburgh; Kevin W. Frederick, Wexford, and Randy J. Loeffler, Carnegie, all of Pa., assignors to Calgon Corporation, Pittsburgh, Pa.

Continuation of Ser. No. 993,990, Dec. 21, 1992, abandoned. This application Sep. 30, 1994, Ser. No. 315,371

Int. Cl.⁶ C08L 33/04

U.S. Cl. 523—331

16 Claims

1. A method for removing water from a water-in-oil polymer composition which method comprises dehydrating said composition in a falling-film evaporator, wherein said composition comprises: 1) about 25 to about 74.5%, based on total composition weight, of an aqueous phase comprising about 10 to about 60%, based on the weight of 1), of a water soluble polymer and the balance water; 2) about 0.5 to about 20%, based on total composition weight, of at least one emulsifying surfactant; and 3) about 25 to about 74.5%, based on total composition weight, of a hydrophobic liquid; wherein said polymer is a water soluble polymer prepared from one or more ethylenically unsaturated monomers; and wherein the molecular weight of said polymer is not substantially degraded in the dehydration step.

5,589,526
MASTER BATCH COMPOSITIONS CONTAINING ORGANIC PEROXIDES

Günter Sienel, Ebenhausen; Maximilian Dorn, Grünwald, and Heinz Zimmermann, München, all of Germany, assignors to Peroxid-Chemie GmbH, Pullach, Germany

Filed Oct. 13, 1995, Ser. No. 543,005

Claims priority, application Germany, Oct. 19, 1994, 44 37 465.8

Int. Cl.⁶ C08K 5/14; C08L 9/00

U.S. Cl. 523—351

19 Claims

1. A master batch composition comprising:
 an elastomeric carrier;
 an organic peroxide in an amount of from 30 to 50% by weight based on the master batch composition;
 a plasticizer;
 a filling material; and optionally further additives compatible with the organic peroxide, wherein in addition to the elastomeric carrier, the composition contains a polyoctenamer.

5,589,527
PIGMENT GRINDING RESIN FOR ELECTRODEPOSITION PAINT AND PIGMENT PASTE CONTAINING THE SAME

Mitsuo Yamada, Suita, and Hiroyuki Nojiri, Takatsuki, both of Japan, assignors to Nippon Paint Co., Ltd., Osaka-fu, Japan

Filed Jan. 9, 1995, Ser. No. 370,105


Claims priority, application Japan, Jan. 10, 1994, 6-000785

Int. Cl.⁶ C08K 3/20; C08L 63/02

U.S. Cl. 523—414

9 Claims

1. A pigment grinding resin represented by the formula:



wherein, Ep is a residue of a reacted epoxy resin of which the starting unreacted epoxy resin has an epoxy equivalent of 150 to 2000 and a hydroxyl group equivalent of 300 to 4000; R¹ represents a hydrophilic group selected from the group consisting of a 2-hydroxyethyl group and a group of the formula —CH₂CH(OH)CH₂R¹ wherein, R¹ is a hydroxyl group or a hydroxylalkyl group having 1 to 10 carbon atoms; R² represents a hydrophilic group selected from the group consisting of 3-hydroxypropyl, 2-hydroxypropyl and 4-hydroxybutyl; R³ is selected from the group consisting of a hydrogen atom and alkyl, hydroxylalkyl and alkylamide groups having 1 to 5 carbon atoms; m is a numerical value of 0.1 to 2.0; A is a residue of diisocyanate selected from the group consisting of aliphatic, alicyclic and aromatic diisocyanates having 4 to 20 carbon atoms; B is a residue of a compound selected from the group consisting of an alcohol, an amine, a carboxylic acid, an oxime and a caprolactam having 1 to 20 carbon atoms; and n is a numerical value of 10.1 to 2.0

5,589,528
HOT MELT GLUE BASED ON MODIFIED WATERBEARING GELS

Lawrence S. Bogardy, 3243 Decker St., Bartlett, Tenn. 38124

Continuation of Ser. No. 259,024, Jun. 13, 1994, abandoned.

This application Feb. 7, 1996, Ser. No. 598,089

Int. Cl.⁶ C08L 89/00; C09J 44/00

U.S. Cl. 524—17

21 Claims

1. A biodegradable, water soluble, and repulpable hot melt adhesive comprising:
 from 50 to 70% by weight hydrocolloids; and
 from 25 to 50% by weight water;

said hot melt adhesive having a melting point below approximately 43° C.

5,589,529

DIMERIC BENZOTRIAZOLES AS UV ABSORBERS

Dieter Reinehr, Kandern, Germany; Jean-Pierre Bacher, Buschwiller, and André Schmitter, Hegenheim, both of France, assignors to Ciba-Geigy Corporation, Tarrytown, N.Y.

Division of Ser. No. 392,638, Feb. 22, 1995, Pat. No. 5,488,112.

This application Nov. 6, 1995, Ser. No. 554,215


Claims priority, application Switzerland, Feb. 24, 1994, 554/94

Int. Cl.⁶ C08K 5/3475; C09K 15/22

U.S. Cl. 524—91

15 Claims

1. A composition comprising
 A) an organic material which is sensitive to damage by light, oxygen and/or heat, and
 B) an effective stabilizing amount of a compound of the formula I



in which

p is 0 or 1;

A is C₁-C₁₂alkylene;

R₁ and R₂, independently of one another, are hydrogen, halogen, C₁-C₁₂alkyl, C₁-C₁₂alkoxy or —CN;

R₂ and R₂, independently of one another, are hydrogen or C₁-C₁₂alkyl or together are C₂-C₁₂alkylene or C₂-C₁₂hydroxyalkylene; and

R₃ and R₃, independently of one another, are hydrogen, halogen, C₁-C₁₂alkyl or C₁-C₁₂alkoxy.

5,589,530

STABILIZATION OF LOW MOLECULAR WEIGHT POLYBUTYLENE TEREPHTHALATE/POLYESTER BLENDS WITH PHOSPHORUS COMPOUNDS

Eileen B. Walsh, Evansville, Ind., assignor to General Electric Company, Pittsfield, Mass.

Division of Ser. No. 164,642, Dec. 8, 1993, Pat. No. 5,367,011,

which is a continuation of Ser. No. 994,738, Dec. 22, 1992,


abandoned. This application Sep. 19, 1994, Ser. No. 308,722

Int. Cl.⁶ C08K 5/53; 5/524; 5/521; 3/32

U.S. Cl. 524—152

22 Claims

1. A thermoplastic resin blend comprising:
 (a) a relatively low molecular weight polybutylene terephthalate resin having a melt viscosity of less than 600 poise;
 (b) a relatively high molecular weight polyester resin having a melt viscosity greater than 600 poise; and
 (c) an effective melt viscosity stabilizing amount of (i) an acid, alkyl, aryl or mixed phosphite having at least one acidic hydrogen or alkyl group, (ii) a phosphorus oxo acid or (iii) a mixture of any of the foregoing.



5,589,531

PREPARATION AND USE OF PELLETIZED SUBMICRON PIGMENT POWDER/POLYMER COMPOSITIONS

Jameel Menashi; Robert C. Reid; Robert S. Whitehouse, all of Lexington, and David J. Kaul, Acton, all of Mass., assignors to Cabot Corporation, Boston, Mass.

Filed Mar. 7, 1995, Ser. No. 399,475

Int. Cl.⁶ C08K 3/10

U.S. Cl. 524—409

21 Claims

1. A process for preparing co-pelletized submicron pigment powder/polymer products comprising the step of pelletizing a submicron pigment powder in a dry drum in the presence of thermoplastic polymeric seed pellets having a mean size in the range of 0.2 to 2.0 mm, wherein the submicron pigment powder to thermoplastic polymeric seed pellet weight ratio is in the range of 0.4:1 to 9:1.

5,589,532

SOLVENTLESS BUTADIENE-VINYLDENE CHLORIDE ADHESIVES CONTAINING MACROMONOMERS FOR THE BONDING OF RUBBER TO METAL

I. Glen Hargis, Tallmadge; John P. Kovalchin, Akron; Satish C. Sharma, Stow; Raymond J. Wehnert, Macedonia, and John A. Wilson, Akron, all of Ohio, assignors to GenCorp Inc., Fairlawn, Ohio

Filed May 15, 1995, Ser. No. 440,586

Int. Cl.⁶ C08K 3/22; C08L 9/10

U.S. Cl. 524—432

9 Claims

1. An adhesive composition, comprising:
 a latex and a nitrosamine crosslinking agent or a precursor thereto said precursor comprising an oxime with an oxidant or a nitro compound with a reductant, said latex comprising:
 the emulsion polymerization product from at least two unsaturated monomers wherein said unsaturated monomers comprise at least a conjugated diene having from 4 to 12 carbon atoms and at least an ethylene oxide macromonomer, wherein said ethylene oxide macromonomer comprises an unsaturated terminal group and from 2 to 40 ethylene oxide repeat units.

5,589,533
SELF-CROSSLINKING COMPOSITION, FORMING OBTAINED FROM THE COMPOSITION, AND METHOD FOR MANUFACTURING THE FORMING

Satoru Aikawa, Tokyo, Japan, assignor to Tajima Incorporated, Tokyo, Japan

Division of Ser. No. 421,873, Apr. 14, 1995. This application

Dec. 26, 1995, Ser. No. 578,239

Claims priority, application Japan, May 24, 1994, 6-133620

Int. Cl.⁶ C08F 8/00

U.S. Cl. 524—529

1 Claim

1. A method for manufacturing a forming of floor material comprising blending:

- (a) a vegetable oil having at least one unsaturated fatty acid or an ester of an unsaturated fatty acid as one of its components;
 (b) a drier;
 (c) at least one member that is capable of being crosslinked in the absence of a peroxide, wherein said member is selected from the group consisting of styrene-butadiene rubber, styrene-butadiene-acrylonitrile copolymer, styrene-butadiene-styrene block copolymer, styrene-isoprene-styrene block copolymer, styrene-ethylene-butylene block copolymer, ethylene-propylene-diene terpolymer, ethylene-vinyl acetate copolymer, ethylene-ethyl acrylate copolymer, low density polyethylene, very low density polyethylene, polybutadiene, and 1,2-syndiotactic polybutadiene; and
 (d) a filler; to prepare a self-crosslinking composition which is free of a solvent and free of a crosslinking agent, wherein said self-crosslinking occurs at a crosslinking temperature; forming said self-crosslinking composition into a specific shape at a first temperature lower than said crosslinking temperature; and crosslinking said shape at a second temperature higher than said crosslinking temperature.

5,589,534
AQUEOUS COATING COMPOSITIONS INCLUDING A REACTIVE EMULSIFIER

Carl W. Metzger, Denkendorf; Bernhard H. Feith, Markgroningen; Ute Gruber, Remchingen; Angelika A. Zedler, Stuttgart, all of Germany, and Mario M. M. van Wingerde, Roosendaal, Netherlands, assignors to Akzo Nobel N.V., Netherlands

Continuation of Ser. No. 39,383, Apr. 16, 1993, abandoned.

This application Jan. 10, 1994, Ser. No. 179,297

Claims priority, application European Pat. Off., Oct. 16, 1990, 90202769

Int. Cl.⁶ C08L 37/00

U.S. Cl. 524—548

19 Claims

1. An aqueous coating composition comprising (A) a generally lipophilic, crosslinkable binder, (B) optionally, a chemical curing/crosslinking agent for the crosslinkable binder and (C) an emulsifying agent which comprises a reactive amphiphatic emulsifier which has a lipophilic backbone having separately pendant therefrom:


- (a) at least one activated unsaturated group; and
 (b) at least one hydrophilic polyoxyalkylene group selected from the group consisting of

- (1) a polyoxyalkylene monoalkylether group of the formula (I)



and

- (2) a polyoxyalkylene monoamine monoalkylether group of the formula (II)



wherein R is selected from the group consisting of a C₁ to C₄ alkyl group,
 R¹ is selected from the group consisting of an H atom and a C₁ to C₄ alkyl group,
 R² is selected from the group consisting of (i) an alkyl group having 1 to 20 carbon atoms, (ii) the residue of a hydrocarbon having 1 to 20 carbon atoms and having a group reactive with a nitrogen, and (iii) a polyoxyalkylene monoether group of the formula (III)



R³ is selected from the group consisting of a C₁ to C₄ alkyl group,
 n, n2 and n4 are independently 0 to 25,
 n1 is 4 to 40 and
 n3 and n5 are independently 0 to 40,
 with the proviso that $n+n1 \leq 50$, $4 \leq n2+n3+n4+n5 \leq 50$ and $n3+n5 \geq 4$;
 the reactive amphiphatic emulsifier having an HLB value of at least about 6.0.

5,589,535

AIR-DRYING POLYURETHANE RESINS, THEIR PREPARATION AND USE

Michael Schwab, Mainz-Kostheim; Gerd Walz, and Gerhard Merten, both of Wiesbaden, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany
 Continuation of Ser. No. 839,926, Feb. 21, 1992, abandoned, which is a continuation of Ser. No. 650,912, Feb. 5, 1991, abandoned. This application May 30, 1995, Ser. No. 454,019
 Claims priority, application Germany, Feb. 15, 1990, 40 04 651.6

Int. Cl.⁶ C08J 3/00; C08K 3/20; C08L 75/00; B32B 27/00
 U.S. Cl. 524—591 20 Claims

1. A process for the preparation of an aqueous coating composition containing at least one water-dispersible polyurethane resin containing air-drying groups, the polyurethane having no residual NCO content and a degree of branching of up to 30% and optionally further binder resins and paint additives, which polyurethane resin contains structural units derived from

- polyisocyanates,
- polyols containing air-drying groups, made by reacting unsaturated fatty acids with polyepoxides,
- optionally polyols which are free of air-drying groups,
- compounds having at least two groups which are reactive with isocyanate groups and at least one group capable of anion formation,
- optionally monoalcohols containing air-drying groups,
- and optionally compounds which differ from (B), (C), (D) and (E) which act as chain terminators and which are selected from the group consisting of monofunctional compounds which react with NCO groups and compounds having active hydrogen of different reactivity towards NCO groups which are selected from the group consisting of compounds having a primary amino group and a secondary amino group, compounds having a hydroxyl and carboxyl group, compounds having a primary or secondary amino group and a hydroxyl group; wherein the functionality and amounts of the polyfunctional components (A) through (D) are chosen such that there is a degree of branching in the resulting polyurethane of up to 30%, and wherein the amount of component (B) is such that the content of unsaturated fatty acids within the polyurethane is between 25 and 50 percent by weight, and wherein the content of the isocyanate component (A) within the resulting polyurethane is from 10 to 40 percent by weight, the content of component (F) is from 0 to 10 percent by weight of the polyurethane resin, the content of component (B) within the resulting polyurethane resin is from 20 to 60 percent by weight; the content of structural units derived from component (D) within the polyurethane resin is from 2 to 20 percent by weight; and the content of components (C) is from 0 to 10

percent by weight of the total mass of polyol components (B) through (D); and wherein the equivalent ratio of isocyanate groups to the total number of hydroxyl groups in the polyols (B) through (D) is 1.05 to 1.4 which process comprises first preparing a polyurethane prepolymer from the polyisocyanates of (A), the polyols of (B) and optionally the polyols of (C) and the compounds of (D), which prepolymer contains on average at least 1.7 isocyanate groups per molecule, then reacting the prepolymer with the compounds of (E) and/or (F) in a non-aqueous system, and optionally then neutralizing the completely reacted polyurethane resin and transferring it into the aqueous system, it being possible for the further binder resins, if used, and the conventional additives to be added before, during and after the preparation of the polyurethane resin.

5,589,536

GLASS FIBER BINDING COMPOSITIONS, PROCESS OF BINDING GLASS FIBERS, AND GLASS FIBER COMPOSITIONS

Carlo M. Golino, Evergreen; Thomas J. Taylor; William H. Klemmeyer, both of Englewood; Leo K. Thiessen, Littleton, all of Colo., and Carl A. Rude, Lafayette, Ind., assignors to QO Chemicals, Inc., and Schuller International, Inc.
 Continuation of Ser. No. 886,668, May 19, 1992, abandoned.
 This application Mar. 13, 1995, Ser. No. 402,576

Int. Cl.⁶ C08L 61/00

U.S. Cl. 524—593 36 Claims

1. A glass fiber binding composition suitable for preparing a binder-coated glass fiber random mat product having a binder solids content of from 1 weight percent to about 25 weight percent, prepared by spraying freshly formed glass fibers with said binding composition, said weight percent binder solids relative to the weight of said binder-coated glass fiber random mat product, said binder-coated glass fiber random mat product being compressible in thickness by a factor of from about 4 to about 12, the interstitial voids between glass fibers being substantially free of binder, said binding composition comprising:

- an effective binding amount of an aqueous compatible furan resin;
- 15 to 99 percent by weight water, the total being 100% by weight,
- wherein said composition contains about 60 percent or more volatiles.

5,589,537

SINGLE PHASE SOLIDS OF POLYMERIZABLE METAL CLUSTERS

Josh H. Golden, Stamford, Conn.; Francis J. DiSalvo, and Jean M. J. Frechet, both of Ithaca, N.Y., assignors to Cornell Research Foundation, Inc., Ithaca, N.Y.

Continuation-in-part of Ser. No. 245,574, May 18, 1994, abandoned. This application Jun. 7, 1995, Ser. No. 485,685

Int. Cl.⁶ C08K 3/10; C08F 30/04

U.S. Cl. 524—780 16 Claims

1. A mixed organic-inorganic single phase solid comprising a homogeneous molecular mixture of a polymerized organic solvent and a metal cluster, wherein the metal cluster is dissolved in said solvent prior to polymerization thereof and contains chemically bound ligands copolymerizable with said solvent.

5,589,538

POLYURETHANE LOW PROFILE ADDITIVES FOR POLYESTER-BASED MOLDING COMPOSITIONS

Gary C. Rex, Cross Lanes, and Kenneth E. Atkins, South Charleston, both of W. Va., assignors to Union Carbide Chemicals & Plastics Technology Corporation, Danbury, Conn.

Continuation-in-part of Ser. No. 258,658, Jun. 13, 1994, abandoned, which is a continuation of Ser. No. 815,255, Dec. 31, 1991, abandoned. This application Dec. 19, 1994, Ser. No. 358,262

Int. Cl.⁶ C08L 75/04; 67/06

U.S. Cl. 525—28 9 Claims

1. A method of preparing thermoset polyester composition comprising:

- preparing a mixture comprising the below-listed ingredients:
 - an unsaturated polyester;
 - an ethylenically unsaturated monomer which is copolymerizable with said unsaturated polyester;
 - an esterified polyurethane low profile additive which comprises the reaction product of
 - a polyisocyanate;
 - a polyol or polyol blend having an average functionality of 2 to 3 hydroxyl groups per molecule and a number average molecular weight of at least 500; and
 - a diol chain extender having between 2 and 32 carbon atoms per molecule;
 to form a hydroxyl-terminated prepolymer which is further reacted with an anhydride in the presence of a catalyst comprising a diamine having no active hydrogens to esterify the hydroxyl-terminated prepolymer and form said esterified polyurethane low profile additive; and
 - a pigment;
- forming the resulting mixture into a desired shape; and
- curing the formed mixture.

5,589,539

PROCESS FOR PREPARING AN IN SITU POLYETHYLENE BLEND

Burkhard E. Wagner, Highland Park, and Arakalud V. Ramamurthy, East Windsor, both of N.J., assignors to Union Carbide Chemicals & Plastics Technology Corporation, Danbury, Conn.

Filed Nov. 23, 1994, Ser. No. 343,849

Int. Cl.⁶ C08L 23/16; 23/08; C08F 297/08

U.S. Cl. 525—53 9 Claims

1. A process for the production of an in situ particulate polyethylene blend comprising contacting a magnesium/titanium based catalyst system including a particulate precursor with one or more alpha-olefins in each of two or more reactors connected in series, in the gas phase, under polymerization conditions, with the proviso that:

- the particulate precursor has a particle size distribution span of no greater than 1.5 as introduced into the first reactor in the series;
- ethylene is introduced into each reactor;
- optionally, an alpha-olefin having at least 3 carbon atoms is introduced into at least one reactor;
- the mixture of ethylene polymer matrix and active catalyst formed in the first reactor in the series is transferred to the subsequent reactors in the series; and
- the polymerization conditions in each reactor are such that a high molecular weight polymer is formed in at least one reactor and a low molecular weight polymer is formed in at least one other reactor wherein the ratio of molecular weights of high molecular weight polymer to low molecular weight polymer in the final product is at least about 8:1.

5,589,540

SYNTHESES OF NEW TYPES OF CHELATING RESINS AND THEIR ADSORPTION PROPERTIES FOR NOBLE METALS

Dong Shihua, 900 Frances way, #211, Richardson, Tex. 75081
 Filed Jan. 30, 1995, Ser. No. 379,915
 Int. Cl.⁶ C08G 63/91

U.S. Cl. 525—65 6 Claims

1. A method of making a chelating resin adapted to selectively adsorb noble metals, comprising the step of reacting polyethyleneimine with at least one of the monomer selected from the group consisting of 2-chloromethylthiirane and epichlorohydrin.

5,589,541

PROCESS FOR PRODUCING MODIFIED PROPYLENE POLYMER AND MODIFIED PROPYLENE POLYMER COMPOSITION

Masafumi Kinoshita; Toshio Niwa, and O. Shibata, all of Osaka, Japan, assignors to Dainippon Ink and Chemicals Inc., Tokyo, Japan

Filed Mar. 28, 1995, Ser. No. 413,218

Claims priority, application Japan, Mar. 28, 1994, 6-57116; Oct. 12, 1994, 6-246170

Int. Cl.⁶ C08F 255/02; C08L 51/06

U.S. Cl. 525—66 20 Claims

1. A process for producing a modified propylene polymer comprising the steps of
 premixing a particulate propylene polymer having a specific surface area of 0.1 m²/g or more with a vinyl monomer comprising styrene and
 polymerizing the vinyl monomer by heating, melting, and kneading the premix at a temperature of a melting point of the premix or higher of from 150° to 250° C. in an extruder.

17. A resin composition comprising a modified polypropylene polymer according to any one of claims 1 to 5 or 8 and a resin selected from the group consisting of a polyamide resin, a polyester resin and a polyphenylene ether resin.

5,589,542

MULTIBLOCK HYDROGENATED POLYMERS FOR ADHESIVES

Glenn R. Himes, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Continuation-in-part of Ser. No. 147,218, Nov. 3, 1993, abandoned. This application Oct. 7, 1994, Ser. No. 320,033

Int. Cl.⁶ C08L 53/02; C08F 297/04

U.S. Cl. 525—98 1 Claim

1. An adhesive composition comprising
 (a) a nontapered multiblock copolymer of the formula

D-A-B-A

- wherein A is a vinyl aromatic hydrocarbon polymer block having a peak molecular weight as determined by gel permeation chromatography of from 4000 to 35,000,
- B is a hydrogenated butadiene polymer block having a peak molecular weight as determined by gel permeation chromatography of from 20,000 to 200,000, and the vinyl content of the polymer block is from 30 to 65 percent by weight,
- D is a hydrogenated isoprene polymer block having a peak molecular weight as determined by gel permeation chromatography of from 5000 to 50,000,
- the ratio of the molecular weight of D to the molecular weight of B ranges such that the normalized peak molecular weight as determined by gel permeation chromatography factor ranges from greater than 0 to 180×10⁻⁶, and
- the copolymer has a vinyl aromatic hydrocarbon content of from 9 to 35 percent by weight; and
 (b) a tackifying resin.

5,589,543

POLYURETHANE ELASTOMERS PREPARED FROM DIFUNCTIONAL TELECHELIC LINEAR NON-CROSSLINKED POLYOLEFINS

Howard B. Ynkelson; Phillip O. Nubel, both of Naperville, and Raymond T. Behrends, Lombard, all of Ill., assignors to Amoco Corporation, Chicago, Ill.

Continuation-in-part of Ser. No. 3,536, Sep. 11, 1995, and a continuation-in-part of Ser. No. 68,236, May 27, 1993, Pat. No. 5,403,904, and a continuation-in-part of Ser. No. 68,240, May 27, 1993, Pat. No. 5,519,101, and a continuation-in-part of Ser. No. 167,668, Dec. 15, 1993, Pat. No. 5,512,635. This application Nov. 27, 1995, Ser. No. 563,197

Int. Cl.⁶ C08L 75/14; C08G 18/69

U.S. Cl. 525—131

11 Claims

1. A hydrophobic polyurethane elastomer composition containing a linear soft segment without pendant chain branched groups, wherein said polyurethane elastomer has a glass transition temperature (T_g) of less than -70°C . and a moisture uptake of less than 1.0 wt % after 24 hours of immersion in water at 70°C ., and wherein said polyurethane elastomer comprises at least one repeat unit containing said linear soft segment, which soft segment comprises a moiety derived from a polyol of the structure:



wherein X is a hydroxyl-containing moiety selected from the group consisting of $-\text{CH}_2\text{OH}$, $-(\text{CH}_2)_p\text{COO}(\text{CH}_2)_p\text{OH}$ and $-\text{COO}(\text{CH}_2)_p\text{OH}$, wherein the functionality number of the terminal groups is 2.0, p is 2 to 12, n is 1 to 10, m is a number average value of up to 1000, and the weight of said polyol is from about 0.5 wt % to about 99.5 wt % of said polyurethane elastomer, and the said polyurethane comprises the reaction product of:

- the said polyol; and
- an isocyanate having a functionality of at least b 2; and
- a chain extender selected from the group consisting of monomeric diols of from 2 to 20 carbon atoms and amines of from 2 to 20 carbon atoms.

5,589,544

SOFT THERMOPLASTIC ELASTOMERS HAVING IMPROVED RESISTANCE TO OIL SWELL AND COMPRESSION SET

Jacques Horron, Tilff, Belgium, assignor to Advanced Elastomer Systems, L.P., Akron, Ohio

Filed May 15, 1995, Ser. No. 440,615

Claims priority, application European Pat. Off., Jul. 6, 1994, 94110498

Int. Cl.⁶ C08F 8/00

U.S. Cl. 525—176

9 Claims

1. A thermoplastic elastomeric composition comprising a blend of:

- about 10 to about 40 parts by weight of an engineering thermoplastic resin and
- about 90 to about 60 parts by weight of a cured rubber concentrate consisting essentially of cured rubber and a carrier, which has been previously obtained by mixing:
 - about 10 to about 90% by weight, based on the weight of (i) plus (ii), of a curable elastomeric copolymer (rubber);
 - about 90 to about 10% by weight, based on the weight of (i) plus (ii), of a polymeric carrier which is not miscible with the curable elastomeric copolymer as assessed by the presence of two different glass transition temperatures in the blend of (i) and (ii) and which carrier does not react with the curative used to vulcanize (i);
 - about 0.1 to about 5 parts by weight, based on 100 parts by weight of (i) plus (ii) of a curing agent (curative) for the curable elastomeric copolymer; and
 - optionally additives, under conditions of heat and shear in a melt mix at least until the maximum torque has been reached, and

- up to about 10 parts by weight of a compatibilizer.

5,589,545

LUBRICIOUS POLYMER BLENDS COMPRISING POLYETHYLENE OXIDE, POLYETHYLENE AND A POLYLACTONE

Ramesh Ramachandran, North Brunswick, and Sharon A. Dinunzi, Middlesex, both of N.J., assignors to Union Carbide Chemicals & Plastics Technology Corporation, Danbury, Conn.

Filed Jul. 18, 1994, Ser. No. 276,342

Int. Cl.⁶ C08F 8/30; C08L 23/00; 71/02

U.S. Cl. 525—184

12 Claims

- A molded polymer blend comprising:
 - from about 40 to 70 weight percent polyethylene;
 - from about 25 to 50 weight percent poly(ethylene oxide); and
 - from about 5 to 35 weight percent of a polylactone; wherein
 - said poly(ethylene oxide) has a weight average molecular weight of from about 500,000 to 1,000,000 grams per gram mole;
 - said polymer blend exhibits a reduction in the coefficient of friction upon exposure to water; and
 - said polymer blend is substantially homogeneous.

5,589,546

SOLID GOLF BALL

Hidenori Hiraoka, and Yoshimasa Koizumi, both of Kobe, Japan, assignors to Sumitomo Rubber Industries, Ltd., Kobe, Japan

Continuation of Ser. No. 53,235, Apr. 28, 1993, abandoned.

This application Jan. 13, 1995, Ser. No. 372,861

Claims priority, application Japan, Apr. 28, 1992, 4-135772

Int. Cl.⁶ A63B 37/02

U.S. Cl. 525—193

4 Claims

1. A one-piece solid golf ball formed from a rubber composition comprising

- 100 parts by weight of a butadiene rubber having at least 40% of cis-1,4-configuration as base rubber,
- 1 to 35 parts by weight of vulcanized rubber powder,
- 5 to 50 parts by weight of a metal salt of an α,β -ethylenically unsaturated carboxylic acid as a co-crosslinking agent,
- 0.1 to 6 parts by weight of an organic peroxide as a vulcanizing agent, and
- a filler,

wherein said vulcanized rubber powder has a particle size of 0.1 to 1,000 μm and is prepared by pulverizing a vulcanized rubber having a JIS-C hardness of 40 to 95.

5,589,547

POLYOLEFIN COMPOSITION, MOLDED ARTICLE THEREOF AND MULTILAYERED LAMINATE

Kazuyuki Watanabe, and Satoshi Iwamoto, both of Oita, Japan, assignors to Showa Denko K.K., Tokyo, Japan

Filed Oct. 12, 1994, Ser. No. 321,517

Claims priority, application Japan, Oct. 13, 1993, 5-280240

Int. Cl.⁶ C08L 23/10; 23/04

U.S. Cl. 525—240

3 Claims

1. A film molded article obtained by extrusion molding of a polyolefin composition which comprises:

- 1 to 99% by weight of a polyolefin having the following properties of (a) to (c):
 - a ratio (η_1/η_2) of kinematic viscosity η_1 at a frequency of 10^{-1} rad/sec to kinematic viscosity η_2 at a frequency of 10 rad/sec at a temperature of 190°C . according to a kinematic viscoelasticity determination method of 4 to 20,

- a crystallization peak temperature T_{cp} according to a Differential Scanning Calorimetry (DSC) of 110° to 130°C .,

- a ratio (T_{mp}/T_{cp}) of melting peak temperature T_{mp} to crystallization peak temperature T_{cp} according to a Differential Scanning Calorimetry (DSC) of 1.1 to 1.5,

- $T_{mp}/(T_{mp}-T_{cp})=3.0$ to 9.8, and

- a crystal structure exhibiting a-axial orientation in a diffraction pattern according to an X-ray diffraction method, and

- 99 to 1% by weight of a propylene resin having the following properties of (f) and (g) and a ratio (M_w/M_n) of weight average molecular weight M_w to number average molecular weight M_n according to a gel permeation gas chromatography of 4.0 to 5.5;

- a ratio (η_1/η_2) of kinematic viscosity η_1 at a frequency of 10^{-1} rad/sec to kinematic viscosity η_2 at a frequency of 10 rad/sec at a temperature of 190°C . according to a kinematic viscoelasticity determination method of below 4, and
- no crystal structure exhibiting a-axial orientation in a diffraction pattern according to an X-ray diffraction method.

5,589,548

PROCESS FOR PREPARING DIFUNCTIONAL TELECHELIC LINEAR NON-CROSSLINKED POLYOLEFINS

Phillip O. Nubel, and Howard B. Ynkelson, both of Naperville, Ill., assignors to Amoco Corporation, Chicago, Ill.

Continuation-in-part of Ser. No. 68,236, May 27, 1993, Pat. No. 5,403,904, and a continuation-in-part of Ser. No. 68,240, May 27, 1993, Pat. No. 5,519,101, and a continuation-in-part of Ser. No. 167,668, Dec. 15, 1993, Pat. No. 5,512,635. This application Jun. 2, 1995, Ser. No. 459,651

Int. Cl.⁶ C08G 61/12; C08F 4/69

U.S. Cl. 525—247

6 Claims

1. A process for the preparation of a difunctional telechelic linear non-crosslinked polyolefin without pendant chain-branched groups wherein the functional groups consist essentially of ester moieties and are other than vinyl groups, the functionality number of said polyolefin as determined by NMR is 2.0, polydispersity is from 1.3 to 3.0, the polyolefin molecular structure is:



wherein X is selected from the group consisting of $-\text{COOR}$, $-\text{CH}_2\text{OC}(\text{O})\text{R}$, and $-(\text{CH}_2)_m\text{COOR}$, wherein R is an alkyl group of from 1 to 8 carbon atoms, n is 1 to 10, and m is a number average value of up to 1000, which process comprises:

- reaction (A) comprising a metathesis reaction between olefinic compound linear acyclic esters of from 3 to 30 carbon atoms having at least one carbon-to-carbon double bond, selected from the group consisting of an alkyl undecylenate of up to 30 carbon atoms, allyl acetate, allyl propionate, allyl butyrate and vinyl acetate to prepare a linear difunctional olefinic compound product, and
- reaction (B) comprising a ring-opening polymerization of a cyclic olefin in the presence of the product of reaction (A), wherein olefinic compound co-products of lower molecular weight than said reaction products of reactions (A) and (B) are removed from reaction products of reactions (A) and (B) by suitable means comprising evaporation, crystallization, purging with an inert gas, and combinations thereof, and wherein said reactions (A) and (B) are metathesis reactions in the presence of a catalyst composition comprising a metathesis catalyst (a) comprising a transition metal compound selected from the group consisting of transition metal halides, oxyhalides, oxides and organic ammonium salts; an activator (b) selected from the group consisting of organic tin compounds, alkylaluminum halides, alkoxyalkylaluminum halides

and aryloxy-alkylaluminum halides, and an organic Lewis base (c), said metathesis catalyst (a) is present in an amount of from about 0.01 to about 50 millimoles per mole of said reactants, activator (b) is present in a molar ratio to metathesis catalyst (a) of from about 0.001:1 to about 200:1, and organic Lewis base (c) is present in a molar ratio to metathesis catalyst (a) of from about 0.1:1 to about 10,000:1, said reactions (A) and (B) conducted at a temperature of from about 0°C . to about 200°C . and a pressure of from about 1×10^{-6} mm Hg to about 30 atmospheres.

5,589,549

MULTISTAGE PROCESS FOR THE (CO) POLYMERIZATION OF OLEFINS

Gabriele Govoni, Renazzo; Mario Sacchetti, Ferrara, and Stefano Pasquali, Fossanova San Marco, all of Italy, assignors to Montell Technology Company bv, Hoofddorp, Netherlands


Filed Jun. 5, 1995, Ser. No. 461,136

Claims priority, application Italy, Jul. 20, 1994, MI94A1515

Int. Cl.⁶ C08F 295/00; 10/06

U.S. Cl. 525—247

22 Claims



1. Process for the polymerization of one or more olefins $\text{CH}_2=\text{CHR}$, where R is hydrogen or an alkyl, cycloalkyl or aryl radical with 1-10 carbon atoms, characterized in that it comprises:

- a first stage of polymerization, in which one or more of said olefins $\text{CH}_2=\text{CHR}$ are polymerized, in one or more reactors, in the presence of a catalyst comprising the product of the reaction between an Al-alkyl compound and a solid component comprising at least one compound of a transition metal M' selected from Ti and V and not containing $\text{M}'-\pi$ bonds and a Mg halide in active form, said catalyst being capable of producing an olefin polymer having porosity, expressed as percentage of voids, greater than 5%;
- a treatment stage, in which the product obtained in said first stage of polymerization (I) is contacted with a compound of a transition metal M selected from Ti, V, Zr and Hf containing at least one $\text{M}-\pi$ bond and optionally with an alkyl-Al compound;
- a second stage of polymerization, in which one or more of the said olefins $\text{CH}_2=\text{CHR}$ are polymerized, in one or more reactors, in the presence of the product obtained in said stage (II).

5,589,550

PEROXIDE-CURED POLYACRYLATES

Paul E. Manley, Louisville, Ky., and Richard J. Flecksteiner, Crystal Lake, Ill., assignors to Zeon Chemicals Incorporated, Louisville, Ky.


Filed Oct. 25, 1995, Ser. No. 547,925

Int. Cl.⁶ C08F 8/30


U.S. Cl. 525—282

7 Claims


1. A process for curing a polyacrylate consisting essentially of at least 10 mole % of the structural unit



wherein R^1 is C_{4-8} alkyl; 0 to 20 mole % the structural unit



wherein R^2 is hydrogen, methyl, ethyl or cyano; and the balance to a total of 100% of the structural unit



wherein R^4 is C_{1-3} alkyl; which comprises heating the polyacrylate with 1,1-bis(t-butylperoxy)-3,3,5-trimethylcyclohexane and m-phenylenediamine maleimide at a temperature in the range of 150°–220° C.

5,589,551

SWELL REDUCTION OF CHROMIUM CATALYZED HDPE RESINS BY CONTROLLED DEGRADATION USING HIGH TEMPERATURE PEROXIDES

John P. Blatt, Plainfield, and Pradeep P. Shirodkar, Belle Mead, both of N.J., assignors to Mobil Oil Corporation, Fairfax, Va.

Filed Feb. 22, 1995, Ser. No. 391,858

Int. Cl.⁶ C08J 3/24; C08L 23/26

U.S. Cl. 525—333.8

8 Claims

1. A modified high density polyethylene formed from a mixture comprising a chromium catalyzed high density (0.94 to 0.97 g/cc) polymer of ethylene or copolymer of ethylene and an alpha olefin of 4 to 10 carbon atoms, containing 0.1 to 10 ppm Cr (elemental), and 10 to 1000 ppm of a high temperature peroxide with a half life temperature at 0.1 hours which is greater than 130° C.

wherein the modified high density polyethylene exhibits at least 30 percent increase in MFR because of crosslinking, and swell reduction determined by annular die swell in the range of 3 to 50 when compared to a base resin comprising said polymer or copolymer and free of peroxide.

5,589,552

COATINGS BASED ON POLYESTERS FROM PERFLUOROPOLYETHERS

Giovanni Simeone, Solaro; Fabrizio Motta, Caronno Pertusella; Angelo Locaspi, Milan, and Claudio Tonelli, Concorezzo, all of Italy, assignors to Ausimont, S.p.A., Milan, Italy

Division of Ser. No. 234,661, Apr. 28, 1994, Pat. No. 5,476,721.

This application Sep. 21, 1995, Ser. No. 531,925

Claims priority, application Italy, Apr. 28, 1993, MI93A0838

Int. Cl.⁶ C08F 20/00; C08G 73/24

U.S. Cl. 525—440

11 Claims

1. Crosslinkable resins based on fluorinated polyesters having a high functionality and having a fluorine content of about 0.5–40% by weight, the cross-linkable resins being soluble in xylene at 70% based on the weight of xylene, the cross-linkable resins being obtained by reacting (i) a hydroxy-terminated perfluoropolyether having a number average molecular weight from 400 to 3000, (ii) a compound containing from 3 to 20 carbon atoms selected from the group consisting of acid anhydrides, diacids, and mixtures

thereof, (iii) a diol containing from 3 to 20 carbon atoms, and (iv) a polyol containing from 3 to 20 carbon atoms and having a functionality of three or greater.

5,589,553

ESTERIFICATION PRODUCT OF AROMATIC NOVOLAK RESIN WITH QUINONE DIAZIDE SULFONYL GROUP

Anthony Zampini, Westborough, and Peter Trefonas, III, Medway, both of Mass., assignors to Shipley Company, L.L.C., Marlborough, Mass.

Filed Mar. 29, 1995, Ser. No. 413,089

Int. Cl.⁶ C08L 61/06; 61/14

U.S. Cl. 525—504

21 Claims

1. A light sensitive resin that is the esterification product of (1) an alkali-soluble aromatic novolak resin having a molecular weight in excess of 1,200 Daltons and pendant phenolic hydroxyl groups and (2) an o-quinonediazide compound, said reaction product having pendant groups consisting of hydroxyl groups and a maximum of 20 percent hydroxyl groups esterified with said o-quinonediazide compound.

5,589,554

ADHESIVE COMPOSITION AND PROCESS FOR PREPARING IT

Seiichi Hiraoka, Otsuki, Japan, assignor to Three Bond Co., Ltd., Japan

Filed Sep. 16, 1994, Ser. No. 307,235

Claims priority, application Japan, Sep. 17, 1993, 5-253610

Int. Cl.⁶ C08F 283/00

U.S. Cl. 525—530

20 Claims

1. An adhesive composition which comprises a 2-cyanoacrylate and at least one of the following compounds (a) and (b):

- (a) an adduct of an epoxy group and a cyano-containing carboxylic acid, and
- (b) a cyano-containing carboxylic acid.

5,589,555

CONTROL OF A SOLUTION PROCESS FOR POLYMERIZATION OF ETHYLENE

Vaclav G. Zboril, Kingston, and Stephen J. Brown, Elginburg, both of Canada, assignors to Novacor Chemicals (International) S.A., Fribourg, Switzerland

Continuation of Ser. No. 70,369, Jun. 3, 1993, abandoned.

This application Jul. 7, 1995, Ser. No. 499,646

Claims priority, application United Kingdom, Oct. 3, 1991, 9120971

Int. Cl.⁶ C08F 4/654

U.S. Cl. 526—64

1 Claim

1. A process for the solution polymerization of high molecular weight polymers of alpha olefins selected from the group consisting of homopolymers of ethylene and copolymers of ethylene and C_{3-12} alpha olefins at a temperature from 105° to 320° C. and a pressure from 4–20 MPa, said process comprising feeding to a tubular reactor kept under non-isothermal conditions or a series of reactors which operate under different conditions, monomer, selected from the group consisting of ethylene and mixtures of ethylene and at least one C_{3-12} alpha olefin, a hydrocarbon solvent and a catalyst; wherein said catalyst is prepared by in-line mixing at a temperature of less than 30° C.:

- (i) a catalyst precursor prepared by the in-line mixing at a temperature of less than 30° C. of a mixture consisting of:
 - (a) MgR^1_2 and AlR^2_3 , wherein each R^1 and R^2 is the same or different and is a C_{1-10} alkyl radical;
 - (b) a reactive halide; and
 - (c) titanium tetrachloride;
- to provide a molar ratio of halide to magnesium from 2.2 to 2.4; magnesium to titanium of 5; and aluminum to titanium of 0.9; with

- (ii) a catalyst activator prepared by in-line mixing at a temperature of less than 30° C. a composition consisting of:
- (d) a first component which is an aluminum alkyl of the formula AlR_3 wherein R is an alkyl radical of the 2–8 carbon atoms; with
- (e) an alcohol of the formula $R^4 OH$ wherein R^4 is a C_{1-20} alkyl radical in a ratio of alcohol to aluminum from 0.1 to 1.

5,589,556

PROCESS AND CATALYST FOR PRODUCING CRYSTALLINE POLYOLEFINS

Abbas Razavi, Patuxent, Belgium, assignor to Fina Technology, Inc., Dallas, Tex.

Division of Ser. No. 925,950, Aug. 5, 1992, Pat. No. 5,304,523, which is a continuation-in-part of Ser. No. 419,157, Oct. 10, 1989, Pat. No. 5,162,278, which is a continuation-in-part of Ser. No. 220,007, Jul. 15, 1988, Pat. No. 4,892,851. This application Jan. 21, 1994, Ser. No. 184,533

Int. Cl.⁶ C07C 2/08; C08F 4/64

U.S. Cl. 526—170

20 Claims

1. A process for the stereospecific propagation of a polymer chain derived from an ethylenically unsaturated monomer comprising:

- (a) providing a catalyst comprising 1) a stereorigid neutral metallocene characterized by a metallocene ligand having ring structures joined to a coordinated transition metal atom, each of said ring structures being a substituted cyclopentadienyl ring and each of said ring structures being in a stereorigid relationship relative to said coordinating metal atom to prevent rotation of said rings structure, said stereorigid relationship being imparted by substituent groups on said ring structures and characterized by the formula:



wherein Cp is a cyclopentadienyl ring, S is a hydrocarbyl radical having from 1–20 carbon atoms, being the same or different, S' is a hydrocarbyl radical having from 1–20 carbon atoms, being the same or different, Me is a Group IVB, VB or VIB metal from the Periodic Table of Elements, Q is a hydrocarbyl having from 1–20 carbon atoms or is a halogen, x is from 1 to 5, y is from 1 to 5, k is from 0 to 3 and 2) an aluminoxane of the formula $(R-Al-O)_n$ in the cyclic form and $R(R-Al-O)_n ALR_2$ in the linear form wherein R is an alkyl group with one to five carbon atoms and n is an integer from 1 to about 20.

- (b) contacting said catalyst in a polymerization reaction zone with an ethylenically unsaturated monomer which contains 3 or more carbon atoms or which is a substituted vinyl compound and maintaining said reaction zone under polymerization conditions to produce crystalline polymer of said monomer.

5,589,557

FLUORINATED POLYMERS AND COPOLYMERS CONTAINING CYCLIC STRUCTURES

Walter Navarrini; Vito Tortelli, both of Milan, and Alessandro Zedda, La Spezia, all of Italy, assignors to Ausimont, S.p.A., Milan, Italy

Filed May 15, 1995, Ser. No. 441,197


Claims priority, application Italy, May 19, 1994, 94A001011

Int. Cl.⁶ C08F 16/24

U.S. Cl. 526—247


9 Claims

1. Polymers and copolymers of one or more fluorinated dienes of structure $CFX^1=CX^2-O-CX^3X^4-O-CX^5=CX^6F$, wherein X^1 and X^2 , equal to or different from each other, are F, Cl or H, and X^3 and X^4 , equal to or different from each other, are F or CF_3 , said dienes essentially forming cyclic repetitive units having the structures:




a)

and




b)

wherein X^1 , X^2 , X^3 and X^4 have the meaning indicated above, at least one of the comonomers used in preparing said copolymers being a compound with an ethylene unsaturation having the structure:



c)

wherein Y^1 , Y^2 , Y^3 , equal to or different from each other, are F, Cl or H and Z is F, Cl, H, R' or $O-R'$ with R' perfluoroalkyl radical having from one to five carbon atoms, the compound containing at most 2 chlorine atoms; or



d)

wherein W^1 and W^2 , equal to or different from each other, represent F or CF_3 , W^3 represents F or H, and W^4 represents F, H, R' or $O-R'$ with R' perfluoroalkyl radical containing from 1 to 5 carbon atoms.

5,589,558

PROCESS FOR THE PREPARATION OF MODIFIED POLYTETRAFLUOROETHYLENE AND ITS USE

Bernd Felix, Burgkirchen; Klaus Hintzer, Kastl; Gernot Löhr, Burgkirchen, and Thomas Schöttle, Burghausen, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Continuation of Ser. No. 310,633, Sep. 22, 1994, This application Jun. 7, 1995, Ser. No. 473,261

Claims priority, application Germany, Sep. 25, 1993, 43 32 712.5

Int. Cl.⁶ C08F 16/24

U.S. Cl. 526—247

3 Claims

1. A process for the preparation of a polymer of tetrafluoroethylene having a content of 0.01 to 1% by weight of perfluoro(alkyl vinyl) ether units with 1 to 4 carbon atoms in the perfluoroalkyl chain, which comprises the step of reacting the monomers by suspension process in an aqueous medium containing initiators and polymerization auxiliaries, in the essential absence of ammonium salts.

5,589,559

FLUOROELASTOMER AND PROCESS FOR PRODUCING THE SAME

Satoru Saito, Kitaibaraki; Haruyoshi Tatsu, Ibaraki, both of Japan, and Lev S. German, deceased, late of Moscow, Russian Federation, assignors to Nippon Mektron, Limited, Tokyo, Japan

Filed Oct. 4, 1995, Ser. No. 538,936

Claims priority, application Japan, Oct. 4, 1994, 6-266246

Int. Cl.⁶ C08F 16/24

U.S. Cl. 526—247

2 Claims

1. A fluoroelastomer having a copolymer composition comprising 50 to 80% by mole of tetrafluoroethylene, 20 to 45% by mole of perfluoro(lower alkyl vinyl ether) and 0.1 to 2% by mole of

5,589,580 RIBOZYMES

James P. Haseloff, O'Connor; Wayne L. Gerlach, Hughes; Phillip A. Jennings, West Chatswood, and Fiona H. Cameron, Forestville, all of Australia, assignors to Gene Shears Pty. Limited, Neutral Bay, Australia

Continuation of Ser. No. 967,693, Oct. 27, 1992, Pat. No. 5,494,814, which is a continuation of Ser. No. 926,148, Aug. 5, 1992, Pat. No. 5,254,678, which is a continuation of Ser. No. 536,625, Aug. 14, 1990, abandoned. This application Feb. 8, 1994, Ser. No. 195,747

Claims priority, application Australia, Dec. 15, 1987, P15911/87; Aug. 19, 1988, P19950/88; Sep. 9, 1988, P10353/88; Nov. 4, 1988, P11304/88; Nov. 7, 1988, P11333/88

Int. Cl.⁶ C12N 15/11; 15/70; 15/74; 15/79

U.S. Cl. 536—23.2

7 Claims

1. A compound having the formula:



wherein each X represents a nucleotide which may be the same or different;

wherein each of (X)_{n-1} and (X)_n represents an oligonucleotide having a predetermined sequence which is (a) capable of hybridizing with an RNA target sequence to be cleaved and (b) does not naturally occur covalently bound to the sequences C-A-A-A-G-C- and X-C-U-G-A-, respectively, such RNA target sequence not being present within the compound;

wherein each of n-1 and n' represents an integer which defines the number of nucleotides in the oligonucleotide with the proviso that the sum of n+n' is greater than or equal to 14;

wherein each * represents base pairing between the nucleotides located on either side thereof;

wherein each solid line represents a chemical linkage providing covalent bonds between the nucleotides located on either side thereof;

wherein a represents an integer which defines a number of nucleotides with the proviso that a may be 0 or 1 and if 0, the A located 5' of (X)_n is bonded to the G located 3' of (X)_{n-1};

wherein each of m and m' represents an integer which is greater than or equal to 1 and less than or equal to 5;

wherein each of the dashed lines independently represents either a chemical linkage providing covalent bonds between the nucleotides located on either side thereof or the absence of any such chemical linkage; and

wherein (X)_b represents an oligonucleotide which may be present or absent with the proviso that b represents an integer which is greater than or equal to 2 if (X)_a is present.

5,589,581 DNA SEQUENCES USEFUL FOR THE SYNTHESIS OF CAROTENOIDS

Norihiko Misawa; Kazuo Kobayashi, and Katsumi Nakamura, all of Takasaki, Japan, assignors to Kirin Beer Kabushiki Kaisha, Tokyo-To, Japan

Continuation of Ser. No. 519,011, Apr. 19, 1990, abandoned.

This application Mar. 10, 1994, Ser. No. 209,617

Claims priority, application Japan, Apr. 21, 1989, 1-103078; Mar. 5, 1990, 2-53255

Int. Cl.⁶ C07H 21/04; C12N 11/18; 9/02; 9/90

U.S. Cl. 536—23.2

6 Claims

1. An isolated and purified DNA encoding a polypeptide which has an enzymatic activity involved in carotenoid biosynthesis and whose amino acid sequence is from A to B of the amino acid sequence shown in FIGS. 1(a) and (b).

5,589,582 POLYNUCLEOTIDES ENCODING PORCINE CYTOKINES

Robert J. Hawley, Newton; Rodney L. Monroy, Rockport; Margaret D. Rosa, Winchester, all of Mass.; Bernice Z. Schacter, Madison, Conn., and Paul D. Ronath, Boston, Mass., assignors to BioTransplant, Inc., Charlestown, Mass.

Continuation-in-part of Ser. No. 967,188, Oct. 27, 1992, abandoned. This application Oct. 8, 1993, Ser. No. 133,979

Int. Cl.⁶ C12N 15/19; C07K 14/52

U.S. Cl. 536—23.5

31 Claims

1. An isolated polynucleotide comprising a polynucleotide sequence which is at least 90% identical to a polynucleotide selected from the group consisting of:

- a polynucleotide encoding a protein comprising amino acid sequence 1-180 of SEQ ID NO:4; and
- a polynucleotide complementary to (a).

5,589,583 PLANT PROMOTER

Harry J. Klee, Ballwin, and James S. Elmer, Ellisville, both of Mo., assignors to Monsanto Company, St. Louis, Mo.

Filed Jan. 11, 1990, Ser. No. 463,682

Int. Cl.⁶ C12N 15/82; 15/11; 15/67; A01H 5/00

U.S. Cl. 536—24.1

17 Claims

1. An isolated DNA molecule consisting essentially of a plant promoter region from *Arabidopsis thaliana* located upstream to a structural DNA sequence which hybridizes to a cDNA probe derived from the structural DNA sequence shown in FIG. 1, said plant promoter region, when operably linked to a heterologous gene, causes transcription in meristematic tissue or regions of rapidly dividing plant cells.

5,589,584 ANGIOTENSINOGEN GENE VARIANTS AND PREDISPOSITION TO HYPERTENSION

Jean-Marc Lalouel, Salt Lake City, Utah; Xavier Jeunemaitre, Paris, France; Richard P. Lifton, Salt Lake City, Utah; Florent Soubrier, Paris, France; Youri Kotelevtsev, Edinburgh, United Kingdom, and Pierre Corvol, Paris, France, assignors to University of Utah Research Foundation, Salt Lake City, Utah

Division of Ser. No. 952,442, Sep. 30, 1992, Pat. No. 5,374,525

This application Jul. 1, 1994, Ser. No. 269,766

Int. Cl.⁶ C07H 21/04; C12Q 1/68

U.S. Cl. 536—24.31

3 Claims

1. An isolated DNA useful in determining predisposition to human hypertension which comprises the DNA sequence of an angiotensinogen gene which codes for methionine at amino acid residue 174.

5,589,587

PROCESS FOR THE PREPARATION OF RIBONUCLEOTIDE REDUCTASE INHIBITORS

James R. McCarthy; Donald P. Matthews, both of West Chester; Jeffrey S. Sabol, Loveland, all of Ohio; James R. McConnell; Richard E. Donaldson, both of Midland, Mich., and Robert Duquid, Richmond, Va., assignors to Merrell Pharmaceuticals Inc., Cincinnati, Ohio


Division of Ser. No. 178,952, Jan. 7, 1994, abandoned, which is a continuation-in-part of Ser. No. 31,012, Mar. 26, 1993, abandoned, which is a continuation-in-part of Ser. No. 881,978, May 12, 1992, abandoned. This application Apr. 10, 1995, Ser. No. 419,315

Int. Cl.⁶ C07H 1/00

U.S. Cl. 536—28.5


3 Claims

1. A process for stereoselectively preparing a compound of the formula




wherein

V is oxy or methylene;
the exocyclic vinylfluoride is in the (E) configuration; and
A is of the formula




wherein Y is hydrogen, C₁-C₄ alkyl or C₁-C₄ alkoxy, comprising the steps of:

- reacting a compound of the formula




wherein A



and Y are defined as above, with excess 1,3-dichloro-1,1,3,3-tetraalkyldisiloxane and triethylamine followed by treatment with SO₃-pyridine complex to produce a 3',5'-protected-2'-keto derivative;

- reacting the 3',5'-protected-2'-keto derivative with a phosphonate ylid of the formula (X)₂OP=CF(SO₂Ar) wherein the ylid is prepared from potassium tert-butoxide; Ar is an aryl group and X is a phenoxy or C₁-C₄ alkoxy to produce an exocyclic fluorovinyl sulfone in the (Z) configuration;
- reacting the (Z)-exocyclic fluorovinyl sulfone with a stannylating reagent of the formula (R)₃SnH wherein R is aryl or C₁-C₄ alkyl to produce an exocyclic (fluorovinyl)stannane in the (Z)-configuration;



5,589,585 DNA FRAGMENTS, PROBES AND AMPLIFICATION PRIMERS OF THE 65 KD ANTIGEN OF MYCOBACTERIA

Claude Mabilat, Villeurbanne, France, and Jean-Claude Pechere, Geneva, Switzerland, assignors to Bio Merieux, L'Etoile, France

Filed Aug. 12, 1993, Ser. No. 105,168

Claims priority, application France, Aug. 12, 1992, 92 10094

Int. Cl.⁶ C07H 21/04

U.S. Cl. 536—24.32

9 Claims

1. A nucleotide fragment consisting of nucleotides 438 to 751 of a gene coding for a 65-kD mycobacterial antigen or a fully complementary sequence.

5,589,586 NUCLEOSIDES ATTACHED TO A SOLID SUPPORT THROUGH A 3'-SILYL LINKAGE AND THEIR USE IN OLIGONUCLEOTIDE SYNTHESIS

Lars Holmberg, Uppsala, Sweden, assignor to Pharmacia LKB Biotechnology AB, Uppsala, Sweden

PCT No. PCT/SE91/00797, § 371 Date Jul. 24, 1992, § 102(e)

Date Jul. 24, 1992, PCT Pub. No. WO92/09615, PCT Pub.

Date Jun. 11, 1992

PCT Filed Nov. 25, 1991, Ser. No. 915,820

Claims priority, application Sweden, Nov. 26, 1990, 9003743

Int. Cl.⁶ C07H 21/00

U.S. Cl. 536—25.3

9 Claims


1. A support for the synthesis of oligonucleotides consisting of a solid support having a first nucleoside bound thereto, wherein said first nucleoside is bound to said support via a silylether linkage directly to said first nucleoside, said silylether linkage being stable to synthesis and deprotection reagents and selectively cleavable by a silylether cleaving agent.

2. A method for synthesizing oligonucleotides on a solid support, wherein said solid support has a first nucleoside bound thereto via a silylether linkage directly to said first nucleoside, said silylether linkage being stable to synthesis and deprotection reagents and selectively cleavable by a silylether cleaving agent which comprises:

- condensing protected nucleotides onto said first nucleoside thereby forming a desired oligonucleotide in protected form, each condensation of a nucleotide being preceded by an acid catalyzed 5'-deprotection step;
- removing all protecting groups on said protected oligonucleotide except for a 5'-protecting group and cleaving any apurinic sites which may have been formed during acid-catalyzed 5'-deprotection in step (i);
- cleaving said silylether linkage by a silylether cleaving agent to remove said oligonucleotide from said support; and
- purifying said oligonucleotide by reverse phase chromatography, using said 5'-protecting group as an affinity handle.

- (d) reacting the (Z)-exocyclic (fluorovinyl)stannane with a protolysis agent and, either concomitantly or sequentially, reacting the silyl protecting group with a suitable acid or a fluoride ion source.

5,589,588
SULFATED ACID AMIDES HAVING ANTICOAGULANT PROPERTIES
 Joseph A. Toce, Webster Groves, Mo., assignor to Reliable Biopharmaceutical Corporation, St. Louis, Mo.
 Filed Mar. 30, 1993, Ser. No. 40,112
 Int. Cl.⁶ A61K 31/735
 U.S. Cl. 536—53



1. A sulfated acid amide of the formula:



wherein

- R_1 is selected from the group consisting of sulfated maltose, sulfated maltotriose and sulfated maltotetraose acids or mixtures thereof, and
 R is a hydrocarbon chain of 3 carbons, and is substituted with one hydroxyl in the 2-position.


5,589,589
PROCESS FOR SCREENING CELLULOSE ETHERS
 Manfred Sponheimer, Wiesbaden; Guenther Welt, Gau-Bischofsheim, and Manfred Ziegelmayer, Bischofsheim, all of Germany, assignors to Hoechst AG, Germany
 Filed Apr. 11, 1995, Ser. No. 420,070
 Claims priority, application Germany, Apr. 11, 1994, 44 12 391.4
 Int. Cl.⁶ C08B 11/20; 11/08

- U.S. Cl. 536—86 16 Claims
 1. A process for recovering finely divided cellulose ether particles from a particulate cellulose ether containing elongated or fibrous particles thereof cellulose ether having a finely fibrous or wad-like or woolly structure, comprising the following steps:
 a) applying a said particulate cellulose ether to a sieve surface of a sieving system,
 b) agitating the sieve surface and dividing said particulate cellulose ether into a first, finely divided fraction capable of passing through the sieve and a second, oversize fraction which remains on the sieve surface,
 c) during said step b, flushing said agitated sieve surface with an air flow, generally perpendicular to the sieve surface, which air flow is applied from below the sieve surface,
 d) discharging the second, oversize fraction from the sieving system, and
 e) discharging or recovering the first, finely divided fraction.

5,589,590
PROCESS FOR THE PREPARATION OF CYCLODEXTRINS OR OTHER COMPOUNDS CAPABLE OF PRODUCING CLATHRATES WITH A GAS
 Henry Ledon, Versailles; Pierre Larnicol, Chalon-sur-Saone; Marie-Jeanne Desmurs, Saint Gengoux le National, and Michel Dupont, Chagny, all of France, assignors to Chemoxal, Paris, France
 Continuation of Ser. No. 887,046, May 22, 1992, abandoned.
 This application Jan. 25, 1994, Ser. No. 186,238
 Claims priority, application France, May 27, 1991, 91 06325
 Int. Cl.⁶ C08B 37/16; C07B 63/00

- U.S. Cl. 536—127 32 Claims
 1. A process for purification of a first substance, said first substance being a cyclodextrin capable of forming a clathrate with a gas from a mixture comprising said first substance and other components, said process comprising the following steps:
 contacting said mixture with at least one non-toxic and non-flammable gas, in the absence of substantially any substance, other than said at least one gas, that forms a clathrate with said first substance that will precipitate from said mixture, until a precipitate of clathrates is formed comprised of said first substance and the at least one gas;
 separating said precipitate of clathrates from said other components remaining in said mixture;
 and recovering said first substance with no content of said other substance.

5,589,591
ENDOTOXIN-FREE POLYSACCHARIDES
 Jerome M. Lewis, Newton, Mass., assignor to Advanced Magnetics, Inc., Cambridge, Mass.
 Continuation-in-part of Ser. No. 260,551, Jun. 16, 1994, Pat. No. 5,554,386, which is a continuation-in-part of Ser. No. 936,873, Aug. 27, 1992, Pat. No. 5,336,506, which is a continuation-in-part of Ser. No. 900,686, Jun. 17, 1992, Pat. No. 5,478,576, which is a continuation of Ser. No. 630,017, Dec. 19, 1990, abandoned, which is a continuation of Ser. No. 679,526, Apr. 2, 1991, Pat. No. 5,141,739, which is a continuation of Ser. No. 384,991, Jul. 2, 1989, abandoned, which is a continuation-in-part of Ser. No. 228,640, Aug. 4, 1988, abandoned, which is a continuation-in-part of Ser. No. 67,586, Jun. 26, 1987, Pat. No. 4,827,945, which is a continuation-in-part of Ser. No. 882,044, Jul. 3, 1986, Pat. No. 4,770,183. This application Nov. 29, 1994, Ser. No. 346,142
 Int. Cl.⁶ C07H 1/00; C08B 37/00
 U.S. Cl. 536—128 8 Claims




1. A method of making a highly purified, substantially endotoxin-free arabinogalactan composition which comprises the steps of:
 (i) removing from an arabinogalactan-containing preparation by ultrafiltration, materials of a molecular weight that are less than the molecular weight of the arabinogalactan composition, and collecting the arabinogalactan-containing fraction thereof;
 (ii) thereafter removing from the arabinogalactan-containing fraction by ultrafiltration, endotoxin and materials of a

- molecular weight that are greater than the molecular weight of the arabinogalactan; and
 (iii) collecting the resulting arabinogalactan-containing fraction, which has been rendered substantially endotoxin-free.

5,589,592
PROCESS FOR PREPARING β -LACTAM DERIVATIVE AND SYNTHETIC INTERMEDIATE
 Hiroshi Horikawa, Kawanishi, and Kazuhiko Kondo, Osaka, both of Japan, assignors to Tanabe Seiyaku Co., Ltd., Osaka, Japan
 Division of Ser. No. 18,407, Feb. 17, 1993, Pat. No. 5,414,081.
 This application Apr. 7, 1995, Ser. No. 393,395
 Claims priority, application Japan, Jun. 3, 1992, 4-99023
 Int. Cl.⁶ C07D 503/04

- U.S. Cl. 540—204 11 Claims
 1. A 1-aza-3-thia-bicycloalkane compound represented by the formula:




- wherein R^1 represents a hydroxy-substituted lower alkyl group which may be protected or an amino group which may be protected; R^2 represents hydrogen atom or an ester residue; X represents a methylene, a methylene group substituted by a lower alkyl group, sulfur atom or a group represented by the formula: $-A-CH_2-$ where A represents sulfur atom, oxygen atom or methylene group;
 or a salt thereof.

5,589,593
CRYSTALLINE FORM OF A CEPHALOSPORIN ANTIBIOTIC
 Marco Da Col, Bologna; Leone Dall'Asta, Pavia, and Irene Resta, Milan, all of Italy, assignors to Biochimica Opos SpA, Agrate Brianza, Italy
 Division of Ser. No. 455,136, May 31, 1995, which is a continuation of Ser. No. 235,262, Apr. 29, 1994, abandoned, which is a continuation of Ser. No. 973,457, Nov. 9, 1992, abandoned. This application Jun. 7, 1995, Ser. No. 483,888
 Claims priority, application Italy, Nov. 11, 1991, MI91A2995
 Int. Cl.⁶ C07D 501/32


- U.S. Cl. 540—220 3 Claims
 1. A process for the preparation of crystalline cefaclor and for its conversion to cefaclor monohydrate, which comprises
 (i) treating raw cefaclor with a mineral or organic acid in a from about 4/1 (v/v) to about 1/4 (v/v) mixture of water and a substantially water-miscible alcohol until a complete solution is obtained, adjusting the pH of the solution to about 4.5, bringing the temperature of the solution to 0°–5° C. and isolating the crystalline cefaclor thus obtained; then
 (ii) acidifying an aqueous suspension of said crystalline cefaclor until a complete solution is obtained, adjusting the pH to about 4.5 and isolating the cefaclor monohydrate thus obtained.

5,589,594
PROCESS FOR THE PREPARATION OF CEPHEM PRODRUG ESTERS
 Elisabeth Defossa, Idstein; Gerd Fischer, Limburg; Uwe Gerlach, Frankfurt am Main; Rolf Hörlein, Frankfurt am Main; Norbert Krass, Frankfurt am Main; Rudolf Lattrell, Königstein/Taunus; Ulrich Stache, Hofheim am Taunus, and Theodor Wollmann, Hofheim am Taunus, all of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Germany
 Continuation of Ser. No. 16,562, Feb. 11, 1993, abandoned.
 This application Dec. 30, 1993, Ser. No. 176,501
 Claims priority, application Germany, Feb. 14, 1992, 42 04 349.2
 Int. Cl.⁶ C07D 501/02

- U.S. Cl. 540—228 5 Claims
 1. A process for the preparation of a compound of the formula I




- in which R^1 is C_1 – C_5 -alkanoyloxy- C_1 – C_3 -alkyl or C_1 – C_5 -alkoxycarbonyloxy- C_1 – C_3 -alkyl and X is an inorganic or organic anion, and in which the hydroxyimino group is present in the syn-form, which comprises allowing a compound of the formula II




in which

- R^2 is a protective group which can be removed by acid hydrolysis, to react with a bis(benzothiazol-2-yl) disulfide of the formula VI




- in which R^3 is hydrogen, C_1 – C_6 -alkyl, C_2 – C_6 -alkenyl, C_3 – C_6 -alkynyl, C_1 – C_6 -alkyloxy, C_2 – C_6 -alkenyloxy, C_3 – C_6 -alkynyloxy, hydroxyl, acetoxy, halogen, nitro, amino, carboxyl or the sulfo group, and triphenylphosphine in an inert solvent, in the presence of a tertiary amine, to give a compound of the formula V




in which

- R^2 and R^3 have the abovementioned meanings, then reacting the compound of formula V with a 7-aminoceph-3-em-4-carboxylic acid ester of the formula III



- in which R^1 has the abovementioned meaning, in inert organic or dipolar aprotic solvents at temperatures between 0° and +80° C. and treating the resulting oxime-protected compound of the formula IV



in which R^1 and R^2 have the abovementioned meanings and in which the protected oxime group is present in the syn-form, with inorganic acids or with aliphatic or aromatic sulfonic acids in organic solvents at temperatures between $+20^\circ$ and $+110^\circ$ C. whereby the protective group R^2 is removed and a salt is formed in one step to form the compound of the formula I.

5,589,595

PROCESS FOR TETRAAZACYCLOALKANE PREPARATION

Rolf W. Sandnes; Kjell Undheim; Michel Gacek, all of Oslo, Norway, and Janis Vasilevskis, Wayne, Pa., assignors to Nycomed Imaging AS, Oslo, Norway

Filed Jun. 7, 1995, Ser. No. 483,189

Claims priority, application United Kingdom, Mar. 10, 1995, 9504922

Int. Cl.⁶ C07D 257/02; A61K 49/00

U.S. Cl. 540—474

27 Claims

1. A process for the preparation of macrocyclic tetraazacycloalkanes, said process comprising (i) reacting a tetraazaalkane with a bridging agent to couple four amine nitrogens of said tetraazaalkane to a bridging moiety to yield a fused tricyclic intermediate, (ii) reacting said intermediate to introduce an alkylene bridge between the secondary amine nitrogens in the outer rings of the fused tricyclic intermediate, optionally by decoupling an alkanediylidene bridging moiety from the tertiary amine nitrogens at the ring fusion sites of the fused tricyclic intermediate, and (iii) where necessary, decoupling said bridging moiety to yield a macrocyclic tetraazacycloalkane.

5,589,596

PROCESS FOR PRODUCING AMINES

Atsushi Furutani, Nishinomiya; Takuo Hibi, Toyonaka; Michio Yamamoto, Otsu; Kazuyuki Tanaka, Ibaraki; Kazuhiro Tada, Kyoto; Masami Fukao, Kurita-gun, and Gohfu Suzukamo, Suita, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Feb. 8, 1994, Ser. No. 194,328

Claims priority, application Japan, Apr. 27, 1993, 5-101074; Jul. 21, 1993, 5-180248; Jul. 21, 1993, 5-180249; Aug. 6, 1993, 5-196041; Aug. 9, 1993, 5-197339

Int. Cl.⁶ C07C 209/22

U.S. Cl. 564—446

32 Claims

1. A process for producing an amine by carrying out a reductive amination of a cyclic ketone or by carrying out a reduction of an imino derivative of a cyclic ketone to the corresponding amine which comprises carrying out the reductive amination or reduction in the presence of a cobalt catalyst containing a carbonate of an alkaline earth metal and/or lanthanum oxide on which cobalt is supported.

5,589,597

PROCESS OF PRODUCING ETHER COMPOUND

Tatsuya Egawa; Yasuhiro Kawaguchi; Kenji Mogami, and Nobuaki Shimizu, all of Sodegaura, Japan, assignors to Iemitsu Kasei Co., Ltd., Tokyo, Japan

Division of Ser. No. 355,180, Dec. 8, 1994, Pat. No. 5,523,491, which is a division of Ser. No. 66,238, May 25, 1993, Pat. No. 5,399,631. This application Dec. 14, 1995, Ser. No. 572,642


Claims priority, application Japan, Jun. 4, 1992, 4-143922; Sep. 7, 1992, 4-237842

Int. Cl.⁶ C07C 43/03; 43/11; 43/184; 43/205


U.S. Cl. 568—608

3 Claims


1. A method of production of an ether compound expressed by the formula (II):



or by the formula (III):



wherein R^1 and R^2 are a hydrocarbon group or a hydrocarbon group containing ether oxygens in the main chain, in the side chain or in the both of them, respectively, and may be the same or different from each other and R^3 , R^4 and R^5 are a hydrogen atom, a hydrocarbon group or a hydrocarbon group containing ether oxygens in the main chain, in the side chain or in the both of them, respectively, and may be the same or different from each other, which comprises bringing an acetal compound or a ketal compound, expressed by the formula (I):



wherein R^1 , R^2 , R^3 , R^4 and R^5 are the same as those in the formulae (II) and (III), into the reaction at a temperature of 10° – 250° C. with hydrogen at a pressure of 1° – 200 kg/cm² in the presence of a solid acid catalyst having hydrogenating ability.

5,589,598

PROCESS OF PURIFICATION OF 2,6-DIISOPROPYLPHENOL

Maurizio Paoletti, Milan, Italy, assignor to Zambon Group S.p.A., Vicenza, Italy

Filed Jun. 1, 1995, Ser. No. 457,592


Claims priority, application Italy, Sep. 28, 1994, M194A1969

Int. Cl.⁶ C07C 37/68

U.S. Cl. 568—756

10 Claims

1. A process for the purification of Propofol comprising the transformation of the crude Propofol into an ester solid at room temperature of formula



wherein R is a residue of a carboxylic or sulphonic acid, the crystallization of the ester (I) in order to obtain a purity degree equal to or higher than 99.9% and its subsequent hydrolysis.

5,589,599

PYROLYTIC CONVERSION OF ORGANIC FEEDSTOCK AND WASTE


Frederick G. McMullen, P.O. Box 396, Gwynedd Valley, Pa. 19437; Dillon G. McMullen, N6640 County Hwy. H, and Roger B. McMullen, N5238 Hwy. 51, both of Irma, Wis. 54442

Filed Jun. 7, 1994, Ser. No. 255,326

Int. Cl.⁶ C02F 11/10

U.S. Cl. 585—240

5 Claims



1. A process for producing usable gaseous fuel and a carbonaceous solid from a substantially organic feedstream such as municipal wastes comprising:

subjecting the feedstream to flash pyrolysis at a temperature of from about 700° to about 2400° F. to form intermediate solid and gas products;

subjecting the intermediate products to a series of water sprays thereby creating a superheated steam with at least the first of said water sprays and later water sprays cooling and condensing the products, scrubbing and contracting the gases, and forming a slurry with the solid product;

separating the gas from the slurry;

scrubbing and drying the gas to remove selected compounds; draining the water from the solid in the slurry; and drying the solid.

5,589,600

PREPARATION OF CYCLOHEXENE BY PARTIAL HYDROGENATION OF BENZENE

Rolf Fischer, Heidelberg; Roman Dostalek, Roemersberg, and Laszlo Marosi, Ludwigshafen, all of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Germany

Continuation of Ser. No. 233,716, Apr. 26, 1994, abandoned, which is a continuation of Ser. No. 14,409, Feb. 5, 1993, abandoned. This application May 25, 1995, Ser. No. 450,981

Claims priority, application Germany, Feb. 5, 1992, 42 03 220.2

Int. Cl.⁶ C07C 5/10; 5/11

U.S. Cl. 585—266

9 Claims

1. A process for the preparation of cyclohexene by the partial hydrogenation of benzene with hydrogen which comprises: carrying out the partial hydrogenation reaction at elevated temperatures of from about 20° to about 300° C. in an aqueous and liquid phase in the presence of a ruthenium/nickel alloy catalyst having a space lattice constant for the a-axis of from 0.2610 to 0.2705 nm and for the c-axis of from 0.4200 to 0.4280 nm, wherein the aqueous phase contains one or more dissolved cations of Group II to VIII transition metals of the periodic table as promoters.

5,589,601

PROCESS FOR THE DIMERIZATION, CO-DIMERIZATION AND OLIGOMERIZATION OF OLEFINS

Yves Chauvin, Le Pecq, and Hélène Olivier, Rueil Malmaison, both of France, assignors to Institut Français du Pétrole, France

Filed Sep. 15, 1995, Ser. No. 528,519

Claims priority, application France, Sep. 16, 1994, 94 11153

Int. Cl.⁶ C07C 2/02; 2/04; 2/24

U.S. Cl. 585—513

15 Claims

1. A process for the dimerization, co-dimerization or oligomerization of olefins, comprising contacting said olefins under effective conditions with a catalytic composition which results from mixing at least one tungsten oxyhalide, at least one aryl isocyanate and/or diisocyanate, and at least one alkylaluminum halide.

5,589,602

METHOD OF PREPARING ISOMERIZATION CATALYST


Robert S. Smith, 1018 Buoy, Houston, Tex. 77062, and Steven L. McMahon, 848 Amy Lea, Sevierville, Tenn. 37862

Division of Ser. No. 150,950, Nov. 12, 1993, abandoned. This application Jun. 7, 1995, Ser. No. 475,153

Int. Cl.⁶ C07C 5/27; B01J 23/04

U.S. Cl. 585—671

20 Claims



1. A method of isomerizing 5-vinyl-2-norbornene (VNB) to 5-ethylidene-2-norbornene comprising contacting VNB with an isomerization catalyst at a temperature of 0° to 80° C. and a contact time in the range of 1 to 12 hours wherein said isomerization catalyst is prepared by:

(a) introducing alumina particles having a particle diameter in the range of 10 to 500 microns into a vertical fluidization zone,

(b) introducing an upward flow of fluidizing nitrogen gas to said fluidization zone at a rate sufficient to suspend said alumina in a fluidized bed maintained in said fluidization zone,

(c) maintaining the temperature in the fluidization zone at a premixing temperature in the range of 150° to 400° C. to dry said alumina, and thereafter,

(d) introducing an amount of sodium, wherein said amount of sodium is within the range of 1:20 to 1:5 based upon the weight of alumina particles, into said fluidization zone at a rate of 0.01 to 0.45 lb sodium/hr per lb alumina while maintaining the temperature in the fluidization zone within the range of 100° to 200° C.,

(e) maintaining said flow of fluidizing gas for a mixing period of at least 30 minutes after said amount of sodium has been introduced to said fluidization zone to disperse said sodium on said alumina to form an isomerization catalyst, and thereafter,

(f) introducing an amount of oxygen to said fluidization zone at a rate in the range of 0.01 to 1 moles/hr per mole of sodium wherein said amount of oxygen is within the range of 0.001:1 to 0.2:1 based on the moles of oxygen introduced to said fluidization zone to the moles of said amount of sodium to form an isomerization catalyst, and

(g) withdrawing said isomerization catalyst from said fluidization zone.

2. The method of isomerizing an olefin which comprises contacting a stream comprising the olefin with an activated catalyst, wherein the activated catalyst is prepared by a method comprising introducing an amount of alkali metal into a fluidized bed of support particles wherein said fluidized bed of support particles is maintained at a temperature above the melting point of the alkali metal and in a fluidized bed state for a time sufficient to evenly disperse the alkali metal on the support particles without substantial breakdown of the support particles, wherein said fluidized bed of support particles is maintained in a fluidized state utilizing a fluidizing gas flowing at a superficial velocity of from 2 to 20 linear feet per minute, and wherein the diameter of the support particles is in the range from 10 to 500 microns.

5,589,603


METHOD AND APPARATUS FOR THE INJECTION DISPOSAL OF SOLID AND LIQUID WASTE MATERIALS FROM THE DRILLING AND PRODUCTION OF OIL AND GAS WELLS

Albert H. D. Alexander, Laurel, Miss.; W. Thomas Ballatine, Mandeville, La.; Leland D. Lakey, Sandeville, La., and Frank L. Lyon, Mandeville, La., assignors to Newpark Resources, Inc., Metairie, La.

Filed Aug. 22, 1994, Ser. No. 294,250
Int. Cl.⁶ A62D 3/00

U.S. Cl. 588—250

35 Claims



1. A method for disposing solid material in a subterranean injection formation comprising:

- mixing at the surface of the earth said solid material, liquid and viscosifier thereby forming a slurry;
- penetrating a subterranean injection formation with a borehole;
- selecting said subterranean injection formation such that:
 - the porosity and permeability of said subterranean injection formation is such that said slurry can be either flowed through said borehole and into said injection formation by means of the force of gravity or pumped through said borehole and into said injection formation at a low surface injection pressure, and

- said injection formation is below underground sources of drinking water; and
- transferring said slurry from the surface of the earth through said borehole into said injection formation.

5,589,604

EXPRESSION OF HUMAN PROTEIN C IN MAMMARY TISSUE OF TRANSGENIC MAMMALS

William N. Drohan, Springfield; Tracy D. Wilkins, Blacksburg; William H. Velander, Blacksburg, and John L. Johnson, Blacksburg, all of Va., assignors to American Red Cross, Washington, D.C., and Virginia Intellectual Property Division, Blacksburg, Va.

Continuation of Ser. No. 638,995, Jan. 11, 1991, abandoned.
This application May 23, 1994, Ser. No. 247,484
Int. Cl.⁶ C12N 5/00; 15/00; 9/48; C12P 21/04

U.S. Cl. 800—2

20 Claims

- A transgenic non-human mammal that contains and expresses a human protein C DNA construct in the cells of its mammary gland, wherein the DNA construct consists of:
 - a mammary gland promoter;
 - a nucleotide sequence that encodes a signal peptide, wherein said signal peptide is effective in directing the secretion of an associated polypeptide into the milk of said transgenic non-human mammal, and wherein said signal peptide-encoding nucleotide sequence is operatively associated with said mammary gland promoter; and
 - a nucleotide sequence encoding human protein C that is operatively associated with said signal peptide-encoding nucleotide sequence,
 wherein human protein C is secreted into the milk of said transgenic non-human mammal, and when purified, said protein C has a specific activity more than about 80% of the specific activity of human protein C isolated from human plasma, as determined by an assay of protein C serine protease activity or anticoagulant activity, and wherein said non-human mammal is selected from the group consisting of mouse, pig, sheep, goat and cattle.

5,589,605

HYBRID CORN WITH A GENETIC COMPLEMENT PRODUCING INCREASED YIELD, SEEDLING VIGOR, EARLY STAND, STALK STRENGTH AND LOW HARVEST MOISTURE

Marvin E. Lindsey, Boone, Iowa, assignor to DeKalb Genetics Corporation, DeKalb, Ill.

Continuation of Ser. No. 463,848, Jan. 12, 1990, abandoned, which is a continuation of Ser. No. 187,188, Apr. 28, 1988, abandoned. This application Nov. 8, 1990, Ser. No. 610,460
Int. Cl.⁶ A01H 5/00; 1/00

U.S. Cl. 800—200

2 Claims

- F₁ generation hybrid corn plant EXP 748, wherein a sample of seed of EXP 748 has been deposited under ATCC accession No. 40470.

5,589,606

INBRED CORN LINE ZS1679

Michael R. Buendgen, Madison, Wis., and Bernard J. Hable, Ankeny, Iowa, assignors to Zenco (No. 4) Limited, London, England

Filed Mar. 28, 1995, Ser. No. 413,872

Int. Cl.⁶ A01H 1/02; 4/00; 5/00; C12N 5/04

U.S. Cl. 800—200

11 Claims

- Inbred corn seed designated ZS1679 seed of which has been deposited in the ATCC under deposit number X.
- A corn plant produced by the seed of claim 1.

5,589,607

Patent Not Issued For This Number

5,589,608

Patent Not Issued For This Number

5,589,609

Patent Not Issued For This Number

5,589,610

STAMEN-SPECIFIC PROMOTERS FROM CORN

Marc De Beuckeleer; Lydia Herdies; Véronique Gossele, all of Gent, Belgium, and Celestina Mariani, Nijmegen, Netherlands, assignors to Plant Genetic Systems, N.V., Belgium
PCT No. PCT/EP92/00275, § 371 Date Oct. 4, 1993, § 102(e)
Date Oct. 4, 1993, PCT Pub. No. WO92/13957, PCT Pub. Date Aug. 20, 1992

PCT Filed Feb. 5, 1992, Ser. No. 104,073

Claims priority, application European Pat. Off., Feb. 7, 1991, 91400300; Jun. 28, 1991, 91401787

Int. Cl.⁶ A01H 1/00; 5/00; 5/10; C12N 15/10; 15/29

U.S. Cl. 800—205

37 Claims

- A stamen-specific promoter region, wherein said promoter region is contained within the sequence of nucleotides 1 to 1179 of SEQ ID No. 3.

19. A plant cell containing stably integrated in its genome a foreign DNA comprising the promoter region of claim 9 operably linked to a heterologous structural gene.

24. A plant or seed containing stably integrated in the genome of its cells a foreign DNA comprising the promoter region of claim 9 operably linked to a heterologous structural gene.

5,589,611

DISEASE RESISTANCE GENE FROM MAIZE AND ITS USE FOR DISEASE RESISTANCE AS A SELECTABLE MARKER AND AS A GENE IDENTIFICATION PROBE

Steven P. Briggs, Des Moines, and Gurmukh S. Johal, Urbana, both of Iowa, assignors to Pioneer Hi-Bred International, Inc., Des Moines, Iowa

Continuation-in-part of Ser. No. 995,658, Dec. 15, 1992, abandoned. This application Sep. 17, 1993, Ser. No. 123,761

Int. Cl.⁶ A01H 1/04; C12N 5/00; 15/00; C07H 21/04

U.S. Cl. 800—205

11 Claims

- A method of imparting resistance to diseases caused by *C. carborum* to plants of a susceptible taxon, comprising the steps of:
 - culturing cells or tissues from at least one plant from the taxon;
 - introducing into the cells or tissue culture at least one copy of an expression cassette comprising the Hm1 gene operably linked to plant regulatory sequences which cause the expression of the gene in the cells; and
 - regenerating disease-resistant whole plants from the cell or tissue culture.

5,589,612

VIRUS RESISTANT PLANTS TRANSFORMED WITH A PVY PROTEASE GENE

Joseph M. Jilka, Ankeny, Iowa, and Nilgun E. Tumer, Chesterfield, Mo., assignors to Monsanto Company

Continuation of Ser. No. 910,792, Jul. 9, 1992, abandoned.

This application Nov. 4, 1993, Ser. No. 148,022

Int. Cl.⁶ C12N 15/40; 5/14; 15/82; A01H 5/00

U.S. Cl. 800—205

13 Claims

- A virus resistant transformed potato plant which contains a PVY protease gene, wherein said protease gene is derived from a PVY which is capable of infecting said plant and wherein said protease gene is stably incorporated into the genome of said plant and is expressed at a level sufficient to render the plant resistant to PVY.

5,589,613

CARNATION PLANTS AND METHODS FOR THEIR TRANSFORMATION AND PROPAGATION

Ebrahim Firoozabady, Pleasant Hill, Calif.; Christine Lemieux, Boulder, Colo.; Benjamin A. Moll, Berkeley, and Karol Robinson, Moraga, both of Calif., assignors to Florigene Europe B.V., Rijnsburg, Netherlands

Continuation of Ser. No. 678,915, Apr. 1, 1991, abandoned.

This application Nov. 10, 1993, Ser. No. 150,528

Int. Cl.⁶ A01H 4/00

U.S. Cl. 800—205

41 Claims

- A method for genetically transforming carnation plant material, said method comprising:

cocultivating carnation plant material with *Agrobacterium tumefaciens* or *rhizogenes* cells carrying an exogenous DNA sequence;

initiating callus formation in the plant material; and selecting transformed plant cells.

5,589,614

PLANT-DERIVED GLUTATHIONE-S-TRANSFERASE ISOFORM II PROMOTER

Ian G. Bridges, Silchester; Simon W. J. Bright, Marlow; Andrew J. Greenland, Maidenhead; David C. Holt, Wokingham; Ian Jepson, Slough, and Wolfgang W. Schuch, Crowthorne, all of England, assignors to Zeneca Limited, London, England

PCT No. PCT/GB92/01187, § 371 Date May 23, 1994, § 102(e)
Date May 23, 1994, PCT Pub. No. WO93/01294, PCT Pub. Date Jan. 21, 1993

PCT Filed Jul. 1, 1992, Ser. No. 170,294

Claims priority, application United Kingdom, Jul. 2, 1991, 9114259

Int. Cl.⁶ A01H 4/00; C12N 15/82

U.S. Cl. 800—205

7 Claims

- A genomic DNA sequence encoding the gene promoter for the 27 kD subunit of glutathione-S-transferase, isoform II, containing the nucleotide sequence shown in FIG. 8 herewith.

5,589,615

PROCESS FOR THE PRODUCTION OF TRANSGENIC PLANTS WITH INCREASED NUTRITIONAL VALUE VIA THE EXPRESSION OF MODIFIED 2S STORAGE ALBUMINS

Ann De Clercq, Harelbeke, Belgium; Enno Krebbers, Alhambra, Calif.; Joël Vandekerckhove, Loppem, Belgium; Luiz Barreto De Castro; Eugen Gander, both of Brasilia, Brazil, and Marc Van Montagu, Brussels, Belgium, assignors to Plant Genetic Systems N.V., Ghent, Belgium, and Brazilian Agricultural Research Organization-Embrapa/Cenargen, Brasilia, Brazil

Continuation of Ser. No. 47,538, Apr. 19, 1993, abandoned, which is a continuation of Ser. No. 499,386, Aug. 9, 1990, abandoned. This application Apr. 18, 1994, Ser. No. 229,069

Claims priority, application United Kingdom, Oct. 18, 1988, 88402611; Oct. 20, 1988, 88402650

Int. Cl.⁶ A01H 4/00

U.S. Cl. 800—205

19 Claims

1. A seed-forming plant susceptible to Agrobacterium transformation; the genome of said plant comprising a recombinant DNA encoding a precursor of a modified 2S albumin, under the control of a promoter, said recombinant DNA comprising:

a nucleic acid sequence encoding a precursor of a 2S albumin from Brassica species, an Arabidopsis species, *Ricinus communis* or *Bertholletia excelsa*, wherein a second DNA sequence is inserted into or replaces in part a region of said nucleic acid sequence between (i) a third codon downstream of a codon encoding a fourth cysteine residue and (ii) a third codon upstream of a codon encoding a fifth cysteine residue of the large subunit of said 2S albumin and wherein said second DNA sequence encodes a polypeptide containing an amino acid selected from the group consisting of a lysine, a methionine, a tryptophan, a threonine, a phenylalanine, a leucine, a valine, an arginine and an isoleucine; and whereby said precursor of said modified 2S albumin is expressed and said modified 2S albumin or said precursor of said modified 2S albumin is stored in said plant.

5,589,616

MONOCOT SEED STORAGE PROTEINS IN DICOTS

Leslie M. Hoffman, Madison, Wis., assignor to Mycogen Plant Science, Inc., San Diego, Calif.

Continuation of Ser. No. 982,869, Nov. 30, 1992, abandoned, which is a division of Ser. No. 393,834, Aug. 14, 1989, Pat. No. 5,215,912, which is a continuation of Ser. No. 902,224, Aug. 29, 1986, abandoned. This application Jul. 25, 1994, Ser. No. 279,616

Int. Cl.⁶ C12N 5/14; 5/29; A01H 5/00; 5/10

U.S. Cl. 800—205

64 Claims

1. A dicot cell containing a monocot seed storage protein.

7. A plant material descended from the cell of claim 1, in which said monocot seed storage protein is detectably expressed.

5,589,617

ENHANCED REGENERATION SYSTEM

Narender S. Nehra; Kutty K. Kartha, and Ravindra N. Chibbar, all of Saskatoon, Canada, assignors to National Research Council of Canada, Saskatoon, Canada

Continuation of Ser. No. 29,652, Mar. 11, 1993, abandoned. This application Aug. 3, 1994, Ser. No. 284,296

Int. Cl.⁶ A01H 1/00; 4/00; C12N 5/04; 5/10; 15/00; 15/09

U.S. Cl. 800—205

21 Claims

1. In a method of regenerating wheat or barley plants from harvested immature plant embryos, the improvement comprising isolating scutellar tissue from said embryos in such a manner that substantially all of the embryo axis is removed and the scutellum is essentially undamaged by the removal of the embryo axis, and culturing the isolated scutellar tissue in vitro under conditions conducive to the regeneration of a wheat or barley plant by somatic

embryogenesis, wherein said scutellar tissue is capable of producing predominantly embryogenic callus.

16. An isolated scutellum of a wheat or barley plant, from which substantially all of the embryo axis is removed, and which is essentially undamaged by the removal of the embryo axis, at least some of whose cells are transformed with foreign DNA.

5,589,618

MATERIALS AND METHODS FOR INCREASING CORN SEED WEIGHT

L. Curtis Hannah, Gainesville, Fla., and Michael Giroux, Pullman, Wash., assignors to University of Florida, Gainesville, Fla.

Filed Sep. 1, 1994, Ser. No. 299,675

Int. Cl.⁶ A01H 4/00; C12N 15/05

U.S. Cl. 800—205

10 Claims

1. A polynucleotide molecule, comprising a variant of the wild type shrunken-2 (Sh2) gene, wherein said variant codes for the insertion of at least one additional amino acid within the allosteric binding site of the ADP-glucose pyrophosphorylase (AGP) enzyme subunit, whereby a plant expressing said polynucleotide molecule has increased seed weight relative to the seed weight of a plant expressing the wild type Sh2 gene.

8. A plant expressing the polynucleotide molecule of claim 1.

5,589,619

PROCESS AND COMPOSITION FOR INCREASING SQUALENE AND STEROL ACCUMULATION IN HIGHER PLANTS

Joseph Chappell, Lexington, Ky.; Court A. Saunders, Clarendon Hills, and Fred R. Wolf, Naperville, both of Ill., assignors to Amoco Corporation, Chicago, Ill.

Division of Ser. No. 934,374, Aug. 14, 1992, Pat. No. 5,349,126, which is a continuation-in-part of Ser. No. 596,467, Oct. 12, 1990, Pat. No. 5,306,862. This application Dec. 8, 1994, Ser. No. 308,551

Int. Cl.⁶ A01H 5/00; C12N 15/00; 15/82

U.S. Cl. 800—205

7 Claims

1. A process of increasing squalene accumulation in a transgenic plant comprising:

(a) transforming a plant cell with a recombinant DNA molecule comprising a vector operatively linked to a DNA segment that encodes a polypeptide having HMG-CoA reductase activity, and a promoter suitable for driving the expression of said polypeptide in said plant cell to form a transformed plant cell; and

(b) regenerating said transformed plant cell into said transgenic plant.

6. A transgenic plant produced in accordance with the process of claim 1.

5,589,620

BIBENZYL SYNTHASE GENES

Helmut Kindl, Marburg; Rüdiger Hain, Langenfeld, and Hans-Jörg Reif, Köln, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Filed Oct. 11, 1994, Ser. No. 321,358

Claims priority, application Germany, Oct. 13, 1993, 43 34 791.6

Int. Cl.⁶ A01H 5/00; 5/10; C12N 15/29; 15/82

U.S. Cl. 800—205

25 Claims

1. An isolated and purified DNA sequence comprising a nucleotide sequence that encodes a bibenzyl synthase isolatable from an orchid.

11. Transgenic whole plants comprising a DNA sequence according to claim 1 as foreign DNA or additional DNA.

5,589,621

PINOSYLVIN SYNTHASE GENES

Helmut Kindl, Marburg; Rüdiger Hain, Langenfeld; Hans-Jörg Reif, Cologne; Klaus Stenzel, Duesseldorf, and Jürgen Thomzik, Langenfeld, all of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Division of Ser. No. 941,469, Sep. 8, 1992, Pat. No. 5,391,724. This application Nov. 14, 1994, Ser. No. 338,996

Claims priority, application Germany, Sep. 18, 1991, 41 30 986.3

Int. Cl.⁶ A01H 4/00; C12N 5/14

U.S. Cl. 800—205

3 Claims

3. A transformed whole plant containing within its genome a nucleotide sequence selected from the group consisting of (i) the nucleotide sequence of the cDNA contained in plasmid pin 5-49, (ii) the nucleotide sequence of the cDNA sequence of SEQ ID NO: 1 and (iii) the nucleotide sequence of a degenerate variant of (i) or (ii), wherein said nucleotide sequence is expressed when said transformed whole plant is exposed to fungi, said transformed whole plant having increased resistance to said fungi as compared to an untransformed whole plant of the same plant species exposed to the same fungi under the same conditions, and said increased resistance to said fungi being a result of the expression of said nucleotide sequence.

5,589,622

PLANT PARASITIC NEMATODE CONTROL

Sarah J. Gurr, York; Michael J. McPherson, Dewsbury; Howard J. Atkinson, Leeds, and Dianna J. Bowles, North Yorkshire, all of England, assignors to Advanced Technologies (Cambridge) Ltd., Cambridge, England

Continuation of Ser. No. 988,954, Jun. 28, 1993, abandoned. This application Dec. 13, 1994, Ser. No. 356,790

Claims priority, application United Kingdom, Sep. 10, 1990, 9019736; Apr. 19, 1991, 9108471

Int. Cl.⁶ C12N 15/09; 15/63; A01M 1/00; 5/00

U.S. Cl. 800—205

34 Claims

1. A method of controlling nematodes, the method including the steps of:

a) identifying a plant gene induced specifically at or adjacent to a nematode feeding site within a successfully nematode-infected plant;

b) preparing a construct by combining a promoter region of said plant gene with a further region which codes for a product disruptive of nematode attack; and,

c) transforming plants with the construct to obtain plants which are nematode resistant.

25. A nematode resistant transgenic plant incorporating a modified gene derived from a method according to claim 1.

5,589,623

GENETIC CONTROL OF ETHYLENE BIOSYNTHESIS IN PLANTS

Adolph J. Ferro, Lake Oswego; Richard K. Bestwick, Portland, and Lyle R. Brown, Corvallis, all of Oreg., assignors to Agritope, Inc., Beaverton, Oreg.

Continuation of Ser. No. 255,833, Jun. 8, 1994, Pat. No. 5,416,250, which is a continuation of Ser. No. 613,858, Dec. 12, 1990, abandoned, which is a continuation-in-part of Ser. No. 448,095, Dec. 12, 1989, abandoned. This application Dec. 20, 1994, Ser. No. 360,974

Int. Cl.⁶ A01H 4/00; C12N 15/82

U.S. Cl. 800—205

10 Claims

10. A transgenic plant containing a DNA sequence which encodes and expresses a S-adenosylmethionine hydrolase enzyme, where said enzyme can hydrolyze S-adenosylmethionine to homoserine and 5'-methylthioadenosine.

5,589,624

ANTIFUNGAL POLYPEPTIDE AND PROCESS FOR ITS PRODUCTION

Norbert Ulbrich, Berlin; Rolf Hilgenfeld, Friedrichsdorf; Heinz Hänel, Oberursel; Burkhard Sachse, Kelkheim; Peter Braun, Mainz; Joachim Wink, Rödermark; Peter Eckes, Kelkheim; Jürgen Logemann, and Josef Schell, both of Köln, all of Germany, assignors to Hoechst Aktiengesellschaft, Germany

Division of Ser. No. 945,982, Oct. 30, 1992, Pat. No. 5,421,839. This application Jan. 13, 1995, Ser. No. 372,455

Claims priority, application Germany, Jun. 15, 1990, 40 19 105.2; Mar. 6, 1991, 41 07 140.9

Int. Cl.⁶ C12N 5/04; 5/10; 15/09; 15/31; A01H 1/00; 5/00

U.S. Cl. 800—205

19 Claims

1. A plant cell which expresses the polypeptide with the amino acid sequence Ala-Thr-Tyr-Asn-Gly-Lys-Cys-Tyr-Lys-Lys-Asp-Asn-Ile-Cys-Lys-Tyr-Lys-ala-Gln-Ser-Gly-Lys-Thr-Ala-Ile-Cys-Lys-Cys-Tyr-Val-Lys-Lys-Cys-Pro-Arg-Asp-Gly-Ala-Lys-Cys-Glu-Phe-Asp-Ser-Tyr-Lys-Gly-Lys-Tyr-Cys (SEQ ID NO: 1).

5,589,625

TRANSGENIC PLANTS DISPLAYING MULTIPLE VIRUS RESISTANCE AND A PROCESS FOR THEIR PRODUCTION

Mart Saarma, Helsinki, Finland; Merikke Kelve; Erkki Truve, both of Tallin, Estonia, and Teemu Teeri, Espoo, Finland, assignors to Kemira Oy, Biotech, Helsinki, Finland

Continuation-in-part of Ser. No. 965,343, Oct. 23, 1992, abandoned. This application Jan. 18, 1995, Ser. No. 374,229

Claims priority, application European Pat. Off., Mar. 18, 1992, 92104676

Int. Cl.⁶ A01H 5/00; C12N 15/82

U.S. Cl. 800—205

24 Claims

1. A transgenic plant that utilizes the 2,5A oligoadenylate pathway and displays resistance to multiple plant viral taxonomic groups comprising a genetically engineered DNA sequence encoding at least one polypeptide having a 2,5A synthetase activity, wherein said polypeptide activates an endonuclease causing degradation of viral RNA.

5,589,626

USE OF LYSOZYME GENE STRUCTURES IN PLANTS TO INCREASE RESISTANCE

Rüdiger Hain, Langenfeld, and Klaus Stenzel, Duesseldorf, both of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Germany

Continuation of Ser. No. 163,493, Dec. 7, 1993, abandoned, which is a division of Ser. No. 555,557, Jul. 19, 1990, Pat. No. 5,349,122. This application Feb. 14, 1995, Ser. No. 389,085

Claims priority, application Germany, Aug. 10, 1989, 39 26 390.8

Int. Cl.⁶ A01H 5/00; 5/10; C12N 15/56; 15/82

U.S. Cl. 800—205

41 Claims


10. Transformed whole plants, said transformed whole plants being other than solanaceous plants, said transformed whole plants comprising in their genome one or more lysozyme gene structures, said lysozyme gene structures expressing lysozyme, said lysozyme gene structures comprising a chimetic gene fusion of the TR promoter, the signal peptide-encoding sequence of barley alpha-amylase and one or more lysozyme genes, and said transformed plants, as a result of being transformed with said lysozyme gene structures, exhibiting an increased resistance to said fungus as compared to a plant of the same plant species which is not so transformed.

VOL
11 93
ISS
5
DE
31
1996
UMI

ELECTRICAL


5,589,627
SENSOR FAULT DETECTION
David M. Sutton, Camberley, Great Britain, assignor to British Gas plc, London, Great Britain
Filed Jan. 31, 1995, Ser. No. 381,562
Claims priority, application United Kingdom, Feb. 2, 1994, 9402018

Int. Cl.⁶ F23N 5/00
U.S. Cl. 73—1 G 7 Claims



1. Apparatus for compensating for faults in a sensor providing an output signal representative of the aeration of a combustible mixture, the apparatus comprising means for checking whether a current value of a stored reference signal with which the output signal is compared to control the aeration is suitable for causing an intended value of aeration to be maintained, means for estimating a corrected value of the stored reference signal in the event that a current value of the stored reference signal is found on checking not to be suitable for causing an intended value of aeration to be maintained and means for storing the corrected value of the reference signal with which the output signal is then compared.


5,589,628
GOLF BALL STRIKING DEVICE
Joseph M. Braly, Kennett Square, Pa., assignor to PGA Tour, Ponte Vedra, Fla.
Filed Dec. 19, 1995, Ser. No. 575,092
Int. Cl.⁶ G01N 3/30
U.S. Cl. 73—12.02 17 Claims



1. A golf ball striking device comprising a framework, a club and shaft assembly rotatably mounted to the framework for movement along a swing path in a first vertical plane, and a golf ball tee assembly having upper and lower ends with the upper end rotatably mounted to the framework for free movement of the golf ball tee assembly in a second vertical plane into any one of a plurality of positions, means for releasably locking the golf ball tee assembly in place at any one of the plurality of positions, a golf ball tee at the lower end of the golf ball tee assembly for supporting a golf ball in the first vertical plane in the swing path of the club and shaft

assembly, means on the golf ball tee assembly for maintaining the tee vertical at any of the plurality of positions of the golf ball tee assembly, and motivator means connected to drive the club and shaft assembly along its swing path for impacting a golf ball on the tee.

5,589,629
METHOD AND APPARATUS FOR TESTING VEHICLE EXHAUST EMISSIONS
Stephen J. Quinn, 91 Breckonwood Cr., Thornhill, Ontario, Canada
Filed Apr. 25, 1995, Ser. No. 429,237
Int. Cl.⁶ G01N 21/00
U.S. Cl. 73—23.31 19 Claims




1. A method of spectroscopic testing of exhaust emissions of vehicles having internal combustion engines to estimate whether the emissions of any vehicle meet predetermined standards, comprising:

- moving each said vehicle under its own power along a test track under controlled conditions of operation,
- said test track having an upwardly inclined portion, a horizontal portion and a downwardly inclined portion, the method comprising the steps of:
 - (a) moving the vehicle to ascend the upwardly inclined portion at a positive rate of acceleration and within a predetermined first range of velocities, and remotely testing the exhaust emissions of the vehicle by spectroscopic means as the vehicle ascends the upwardly inclined portion at a first test point on the upwardly inclined portion;
 - (b) moving the vehicle across the horizontal portion at a substantially constant velocity and within a predetermined second range of velocities, and remotely testing the exhaust emissions of the vehicle by spectroscopic means as the vehicle crosses the horizontal portion at a second test point on the horizontal portion; and
 - (c) moving the vehicle to descend the downwardly inclined portion at a negative rate of acceleration and within a predetermined third range of velocities, and remotely testing the exhaust emissions of the vehicle by spectroscopic means as the vehicle descends the downwardly inclined portion at a third test point on the downwardly inclined portion;
- comparing the test results from the first, second and third test points of one vehicle with results for vehicles which meet the predetermined standards, said steps (a), (b) and (c) being performed in any order.

5,589,630
FAST GAS CHROMATOGRAPHY METHOD, APPARATUS AND APPLICATIONS
Patrick M. Wiegand, South Charleston; John F. Fisher, St. Albans; John R. Parrish, Cross Lanes; Elizabeth S. Ballard, Charleston; Courtland P. Sears, III, Dunbar; George W. Schwarz, Jr., and Cloyd R. Smith, III, both of Charleston, all of W. Va., assignors to Union Carbide Chemicals & Plastics Technology Corporation, Danbury, Conn.
Division of Ser. No. 88,677, Jul. 7, 1993, Pat. No. 5,437,179.
This application Apr. 26, 1995, Ser. No. 429,185
Int. Cl.⁶ G01N 30/54

U.S. Cl. 73—23.35 3 Claims
1. A fast temperature programming module for heating and cooling a gas chromatographic column, comprising:
a) cylindrical body having two parallel, circular faces, said body comprising an inlet means in the center of one of the circular



faces and an exit means located at the perimeter of the faces for the passage of heat transfer fluid through said body, said body being suitable for the location of a gas chromatographic column therein:

- b) circular heating means located inside said body, said heating means being capable of imparting a temperature change to the heat transfer fluid; and means to provide an electrical current to said heating means in order to impart a temperature change to said heating means.

5,589,631

LEAK DETECTION WITH NON-TOXIC LIQUIDS


G. Everett Spring, Makawao, HI., and Douglas V. Keller, Jr., Lafayette, N.Y., assignors to Spring Patents Corporation, Makawao, HI.

Continuation of Ser. No. 922,622, Jul. 30, 1992, abandoned, which is a continuation-in-part of Ser. No. 530,613, Jul. 9, 1990, Pat. No. 5,184,504, and a continuation-in-part of Ser. No. 673,772, Mar. 21, 1991, abandoned. This application Jul. 26, 1994, Ser. No. 281,854

Int. Cl.⁶ G01M 3/32

U.S. Cl. 73-49.2

4 Claims



1. A method of detecting leaks in a system comprising a primary containment for a substance with a fluid phase and a secondary containment enveloping the primary containment, said method comprising the steps of:

filling the space between the primary containment and the secondary containment with a non-corrosive, nontoxic, leak detection liquid which contains vegetable oil and citric acid in a minor amount effective to reduce the concentration of oxidation catalyzing metal ions in said liquid, said vegetable oil: (a) having a viscosity of not more than 100 centistokes at a temperature of -25° F., (b) being essentially stable over a temperature range of -25° to 140° F., and (c) being essentially chemically inert relative to the materials from which the primary and secondary containments are fabricated; and

said method further comprising the step of monitoring a characteristic of or associatable with said leak detection liquid for a change indicative of a leak in at least one of said components.

5,589,632

METHOD AND DEVICE FOR ESTIMATING THE THRUST OF A RAMJET


Alain Chevalier, and Vincent Protat, both of Bourges, France, assignors to Societe Anonyme dite: Aerospatiale Societe Nationale Industrielle, Paris, France

Filed May 9, 1995, Ser. No. 437,058

Claims priority, application France, May 18, 1994, 94 06058 Int. Cl.⁶ G01M 15/00

U.S. Cl. 73-117.4

12 Claims



1. A method for estimating a thrust of a ramjet, said method comprising:

- (a) mounting a combustion chamber of the ramjet on support means for providing said combustion chamber with partial freedom of longitudinal movement;
- (b) arranging blowing means, comprising a nozzle which is fixed in position relative to said support means, at an intake of said combustion chamber;
- (c) arranging, between said nozzle and the intake of said combustion chamber, at least one flexible bladder which is filled with a fluid;
- (d) blowing air through said nozzle into the combustion chamber so as to create in said combustion chamber feed conditions which are identical to operational feed conditions existing during a defined operation of the ramjet;
- (e) feeding fuel to said combustion chamber so as to generate combustion; and
- (f) measuring the pressure of the fluid contained in said bladder, said pressure resulting from a displacement of said combustion chamber with respect to said nozzle during the combustion.

5,589,633

METHOD AND APPARATUS FOR MEASURING PUMPING ROD POSITION AND OTHER ASPECTS OF A PUMPING SYSTEM BY USE OF AN ACCELEROMETER

James N. McCoy, 2210 Midwestern Pkwy., Wichita Falls, Tex. 76308; Jerry B. West, Dallas, and Augusto L. Podio, Austin, both of Tex., assignors to James N. McCoy, Wichita Falls, Tex.

Division of Ser. No. 808,578, Dec. 17, 1991, Pat. No. 5,406,482. This application Apr. 7, 1995, Ser. No. 418,378


Int. Cl.⁶ G06F 15/00

U.S. Cl. 417-63

3 Claims

1. A method for analyzing the performance of a pumping system for an oil well by use of an accelerometer, wherein said pumping system includes a rod connected to a downhole pump, comprising the steps of:

mounting said accelerometer to said pumping system, wherein said accelerometer produces an output signal, digitizing said output signal to produce a first digital data set, storing said first digital data set in a memory of a computer, and



displaying said first digital data set as a waveform on a display screen of said computer wherein said waveform includes features indicating performance of said pumping system.

5,589,634

SEMICONDUCTOR ACCELERATION SENSOR FOR DETECTING ACCELERATION IN ORTHOGONAL DIRECTIONS


Teruaki Nagahara, and Masahiro Yamamoto, both of Itami, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Aug. 8, 1995, Ser. No. 512,632

Claims priority, application Japan, Mar. 15, 1995, 7-056223 Int. Cl.⁶ G01P 15/12

U.S. Cl. 73-514.33

2 Claims



1. A semiconductor acceleration sensor comprising:
- an acceleration sensor beam having first and second opposing surfaces;
- a diaphragm formed on the first surface of said acceleration sensor beam, said diaphragm having a width less than the width of the acceleration sensor beam as measured in a direction perpendicular to the longitudinal axis of said acceleration sensor beam;
- a pair of groups of gauge resistors arranged on a first side of said diaphragm at end portions of said diaphragm as viewed in the longitudinal direction of said acceleration sensor beam;
- first and second bridge circuits formed by electrically connecting the gauge resistors of the respective groups, said first bridge circuit being formed by connecting the gauge resistors of one of said groups to sense acceleration acting in the direction of thickness of said acceleration sensor beam, the second bridge circuit being formed by connecting the gauge resistors of the other of said groups to sense acceleration acting in the direction which is perpendicular both to the longitudinal and thickness directions of said acceleration sensor beam, wherein each gauge resistor of said second bridge circuit is disposed at a respective corner of the first side of said diaphragm.

5,589,635

AUTOMATED TAPPING PROCESS FOR COMPLEX PARTS USED FOR DETECTING SHALLOW FAULTS


Gilles Baudrillard, Suresnes, and Christophe P. Bouju, Paris, both of France, assignors to Aerospatiale Societe Nationale Industrielle, France

Filed Aug. 8, 1995, Ser. No. 512,531

Claims priority, application France, Aug. 8, 1994, 94 09808 Int. Cl.⁶ G01N 9/24

U.S. Cl. 73-600

12 Claims



1. Process for tapping a complex part, wherein the part is subject to successive shocks based on impacts distributed over a surface to be tested of the part and a diagnosis relative to a presence of shallow faults is deduced from an acoustic response produced by said shocks, in which sound signals produced by each shock are collected and at least two successive sound signals are compared with one another in order to deduce therefrom in automated manner a fault diagnosis when a significant difference is detected between these successive sound signals.

5,589,636

METHOD OF AND APPARATUS FOR THE DETECTION OF AN ULTRASONIC FIELD

Wieslaw Bicz, Wroclaw, Poland, assignor to Sonident Anstalt Liechtensteinischen Rechts, Vaduz, Liechtenstein


Filed Dec. 6, 1994, Ser. No. 349,880

Claims priority, application Germany, Apr. 22, 1994, 44 14 081.9

Int. Cl.⁶ G01B 17/00; G06K 9/00

U.S. Cl. 73-617

11 Claims



1. A method for detecting ultrasonic waves propagated through a medium, comprising the steps of:
- (a) at a given time collecting respective ultrasonic waves at each of a plurality of spaced apart collection locations in said medium;
- (b) passing ultrasonic waves collected at said given time at each of said collection locations from the respective collection location to a common detection site along a respective ultrasonic wave path assigned to the respective collection location

having a sound transit time different from sound transit times of others of said ultrasonic wave paths terminating at said common detection site; and

(c) detecting ultrasonic waves received at said common detection site with a single transducer responsive to ultrasonic waves from a plurality of said paths and received in a time-spaced relationship determined by the respective sound transit times, and converting the detected ultrasonic waves to electrical signals with said transducer.

5,589,637

EXCITER-MOUNTING FOR SHAKER TABLE


Gregg K. Hobbs, Westminster, Colo., assignor to Qualmark Corporation, Denver, Colo.

Division of Ser. No. 950,631, Aug. 27, 1992, Pat. No. 5,365,788, which is a continuation-in-part of Ser. No. 487,757, Mar. 1, 1990. This application Nov. 22, 1994, Ser. No. 344,544

Int. Cl.⁶ G01N 29/12

U.S. Cl. 73—663

29 Claims



1. Screening apparatus for imparting vibrational acceleration forces to a device to be tested, comprising:

a shaker table having a top surface and a bottom surface with device mounting means for securely attaching the device to said top surface; and

an exciter that produces vibrational acceleration forces with exciter mounting means for connecting said exciter to said bottom surface of the table, said exciter mounting means including said table having a table hole extending through said table from said bottom surface to said top surface and including said exciter having an exciter hole that extends through said exciter and aligns axially with said table hole an exciter mounting bolt extending through said exciter hole in said exciter and into said table hole said exciter mounting bolt having a tapped center bore extending axially into said exciter mounting bolt in a manner that is accessible from the top surface of the table for receiving and fastening a threaded device mounting bolt into said exciter mounting bolt.

5,589,638

PRESSURE SENSOR HAVING A HEAT CONDUCTING ELEMENT BETWEEN THE PRESSURE TRANSMITTING ELEMENT AND THE PRESSURE SENSOR HOUSING

Josef Glaser, Graz, and Pierre Fornet, Lebnitz, both of Austria, assignors to AVL Gesellschaft Für Verbrennungskraftmaschinen und Messtechnik m.b.H. Prof.Dr.Dr.h.c. Hans List, Graz, Austria

Filed May 30, 1996, Ser. No. 655,463


Claims priority, application Austria, Jun. 2, 1995, A950/95

Int. Cl.⁶ G01L 7/00

U.S. Cl. 73—706

6 Claims

1. Pressure sensor comprising a housing containing a measuring device which is separated from said housing by a radial gap and comprises a pressure transmitting element and a measuring element, said pressure sensor comprising a sealing membrane tightly and flexibly connecting said housing and said pressure transmitting



element on a side facing a medium to be measured, wherein at least one heat conducting element is provided between said pressure transmitting element and said housing, said heat conducting element being made from a material of good thermal conductivity and having a large cross-section for heat conduction such that most of the heat arising in a region of said pressure transmitting element is carried off to said housing via said heat conducting element, acting as bending or rolling element in the instance of axial shifts between said pressure transmitting element and said housing and being flexible in axial direction as regards force transmission.

5,589,639

SENSOR AND TRANSDUCER APPARATUS


Nicholas F. D'Antonio, 7695 Admiral Dr., Liverpool, N.Y. 13090, and Nicholas J. D'Antonio, 138A Long Rd., Tully, N.Y. 13159

Continuation-in-part of Ser. No. 621,653, Dec. 31, 1990, Pat. No. 5,279,163, which is a continuation-in-part of Ser. No. 834,939, Feb. 28, 1986, Pat. No. 4,823,619, and a continuation-in-part of Ser. No. 151,483, Feb. 2, 1988, Pat. No. 4,987,783. This application Jan. 18, 1994, Ser. No. 182,578

Int. Cl.⁶ G01L 9/00

U.S. Cl. 73—724

2 Claims



1. A force sensing system for generating an intelligible output signal corresponding to a parameter, said system comprising:

sensing means having a stationary first portion and a second portion movable relative to the first portion for generating an electric reactance signal corresponding to the parameter;

first supporting means connected to a housing or conduit for supporting said first portion of said sensing means;

second deflectable supporting means for supporting said movable second portion of said sensing means;

securing means for securing said first and second supporting means in a movable relationship, said first and second supporting means being movable relative to each other in response to the occurrence of said parameter to move said movable second portion with respect to said stationary first portion of said sensing means to generate said electric reactance signal;

processing means including reactance controlled square wave generator means for receiving said reactance signal and for generating a corresponding variable period pulse train transduced signal, voltage converter means for establishing a voltage signal having a magnitude proportional to the frequency

of the variable period pulse train transduced signal, and means for receiving said voltage signal and generating an intelligible output signal reflective of the magnitude and variation in said voltage signal; and

transmitting means for transmitting said electric reactance signal from said sensing means to said processing means.

5,589,640

METHOD FOR DETECTING CHANGES IN PRELOAD ON A TIE ROD INSTALLED AS PART OF A CORE SHROUD REPAIR IN A BOILING WATER REACTOR


Patrick J. Butler, 6909 Duke Dr., Alexandria, Va. 22307

Filed Apr. 3, 1996, Ser. No. 627,154

Int. Cl.⁶ F16B 31/02

U.S. Cl. 73—761

10 Claims



1. In a boiling water reactor having a core shroud disposed within a reactor vessel and a plurality of tie rods installed with an initial preload between vertically spaced sites on the core shroud at a respective plurality of angularly spaced locations about the shroud periphery as part of a core shroud repair, a method of measuring preload on an installed tie rod to determine whether the preload on the tie rod has changed since installation, said method comprising the steps of

- lowering a tool into the reactor vessel from a remote location positioned externally of the reactor vessel;
- attaching the tool to an upper portion of the tie rod;
- using the tool to apply a tensile load along a longitudinal axis of the tie rod;
- measuring the tensile load as it is applied to the tie rod;
- measuring axial displacement of the tie rod as the tensile load is applied;
- plotting the load measured in step (d) versus the axial displacement measured in step (e); and
- identifying a change in slope on the load-displacement plot occurring at a load corresponding to the tie rod preload.

5,589,641

STRAIN AND FABRY-PEROT ETALON MEASUREMENT SYSTEM AND METHOD


Bartley C. Johnson, Clayton, and John H. Belk, St. Louis, both of Mo., assignors to McDonnell Douglas Corporation, St. Louis, Mo.

Filed Jun. 5, 1995, Ser. No. 461,820

Int. Cl.⁶ G01L 1/24

U.S. Cl. 73—800

22 Claims



- transmitting a low-coherence light through an optical strain sensor;
- coupling an output of the optical strain sensor and a high-coherence light source into a coherence detector;
- determining an equal optical path length point;
- measuring a first phase change of the high-coherence light source from the equal optical path length point to a first optical path length of the strain sensor;
- applying a strain to the optical strain sensor;
- measuring a second phase change of the high-coherence light source from the equal optical path length point to a second optical path length of the strain sensor; and
- calculating a difference phase change from the first phase change and the second phase change.

5,589,642

HIGH VOID FRACTION MULTI-PHASE FLUID FLOW METER


Joram Agar, Grand Cayman, Cayman Islands, and David Farchi, Houston, Tex., assignors to Agar Corporation Inc., Houston, Tex.

Filed Sep. 13, 1994, Ser. No. 305,344

Int. Cl.⁶ G01F 1/74

U.S. Cl. 73—861.04

25 Claims



- a first fluid flow path including a first flow measuring device for measuring gas and liquid flow and a restrictor coupled in series with said first flow measuring device thereby to slow the flow of fluid through said first flow measuring device when said fluid includes liquid;
- a second fluid flow path in parallel with said first fluid path and including a second flow measuring device for measuring gas flow;
- means for detecting liquid flow in said flow meter;
- means for diverting flow of gas into said second fluid flow path liquid flow when liquid flow is not detected by said detecting means;
- means for outputting an indication of the amount of liquid flow through said first flow measuring device and combined total amount of gas flow through said first and second flow measuring devices.

5,589,643

ACROSS THE WALL PRESSURE DIFFERENTIAL INDICATOR

Robert D. Pyle, 3286 Balsam Ridge St., White Oak, Ohio 45239


Filed Apr. 25, 1995, Ser. No. 428,503

Int. Cl.⁶ G01F 1/28

U.S. Cl. 73—861.75

10 Claims

- An across the wall pressure differential indicating apparatus comprising:
- a wall duct having first and second open ends, first and second mounting plates respectively attached to said wall duct at said first and second open ends respectively, and a low speed airflow indicator is adapted to indicate a pressure differential and is mounted in full fluid communication with



said wall duct at one of said ends such that all airflow passing through said wall duct also passes through said indicator.

5,589,644

TORQUE-ANGLE WRENCH


Thomas P. Becker; Matthew M. Crass, both of Kenosha; Gordon A. Putney, Lake Geneva; Randy J. Niesen, Kenosha, and Dean J. Iwinski, Muskego, all of Wis., assignors to Snap-on Technologies, Inc., Crystal Lake, Ill.

Filed Dec. 1, 1994, Ser. No. 347,871

Int. Cl.⁶ G01L 5/00

U.S. Cl. 73-862.23

15 Claims



1. A torque-angle wrench comprising:
 - a handle for applying torque through a tightening angle at a rotational angular velocity;
 - a piezoelectric gyroscopic sensor, including a vibrating body responsive to rotation of said handle, for generating an electrical signal representative of the rotational angular velocity; and
 - integrating means for converting said electrical signal into an output signal representing degrees of rotation of said handle, said integrating means including a voltage to frequency converter and a totalizer circuit, said electrical signal being converted to a digital pulse signal by said voltage to frequency converter and said digital pulse signal being fed directly to said totalizer circuit which, on the basis of said digital pulse signal, generates said output signal.

5,589,645

STRUCTURE OF MAGNETOSTRICTIVE SHAFT APPLICABLE TO MAGNETOSTRICTION-TYPE TORQUE SENSOR FOR DETECTING TORQUE APPLIED TO ROTATABLE SHAFT AND METHOD FOR MANUFACTURING THE SAME

Nobuaki Kobayashi; Satoshi Kaise, and Hideki Kano, all of Atsugi, Japan, assignors to Unisia Jecs Corporation, Atsugi, Japan

Filed Nov. 22, 1994, Ser. No. 345,751


Claims priority, application Japan, Nov. 30, 1993, 5-326325; Dec. 3, 1993, 5-339290

Int. Cl.⁶ G01L 3/10; G01R 33/18

U.S. Cl. 73-862.335

6 Claims

1. A structure of a magnetostriction-type torque sensor, comprising:



- a) a cylindrical outer casing;
- b) a magnetostrictive shaft disposed within said outer casing so as to enable a rotation thereof according to a torque applied thereto; and
- c) a pair of self-inductance determining coils, each coil being connected to a torque magnitude and direction detection circuitry and being wound around a radial part of an outer peripheral surface of the magnetostrictive shaft with a gap provided against the outer peripheral surface, wherein said magnetostrictive shaft comprises a shaft parent material made of a non-magnetic austenitic series metallic material and a magnetic thin film formed on the whole outer peripheral surface of said shaft parent material, said magnetic thin film being made of a magnetostriction material.

5,589,646

TENSION LOAD CELL APPARATUS


Jon E. Khachaturian, and William B. Thrift, both of New Orleans, La., assignors to Versabar, Inc., Harvey, La.

Continuation-in-part of Ser. No. 36,184, Mar. 23, 1993, Pat. No. 5,429,007. This application Jul. 3, 1995, Ser. No. 498,022

Int. Cl.⁶ G01L 1/22

U.S. Cl. 73-862.474

20 Claims



11. A method of generating a tension load value with a load cell comprising the steps of:
 - a) providing a structural member of metallic construction having a pair of larger diameter end portions and a smaller diameter center portion, each larger diameter portion having a transverse opening that receives a lifting pin;
 - b) generating a tension load value with a strain gauge mounted at the center portion of the structural member responsive to an elongation of the structural member when loaded;
 - c) covering the center section with a casing;
 - d) attaching one end portion of the casing to one of the larger diameter end portions of the structural member;
 - e) the other larger diameter end portion of the casing from the structural member so that the structural member can elongate independently of the casing when the structural member is loaded; and

- f) wherein in step "b" the flow of the strain field from the transverse openings through the center portion remains smooth, parallel and free of substantial discontinuity.

5,589,647

FLEXIBLE SENSOR TUBE AND METHOD FOR DETERMINING A CONCENTRATION CURVE OF A MEDIUM ALONG A PATH WITH THE FLEXIBLE SENSOR TUBE

Peter Jax, Erlangen, and Klaus Ruthrof, Nürnberg, both of Germany, assignors to Siemens Aktiengesellschaft, Munich, Germany


Filed Jun. 19, 1995, Ser. No. 491,395

Claims priority, application Germany, Dec. 17, 1992, 42 42 806.8

Int. Cl.⁶ G01N 37/00

U.S. Cl. 73-863.23

5 Claims



1. A sensor assembly, comprising:
 - a sensor and
 - a flexible tube communicating with said sensor and extending along a given path for determining a concentration curve of a medium along the given path, said flexible tube being formed of a material having relatively good permeability to the medium and having an inner surface; and
 - a thin coating completely covering said inner surface and being formed of a material having relatively poor permeability to the medium.

5,589,648

TEST KIT GRIPPING APPARATUS


Matthew A. Valbuena, 23235 Sky Dr., Lake Forest, Calif. 92630

Filed Nov. 18, 1994, Ser. No. 342,216

Int. Cl.⁶ G01N 1/12

U.S. Cl. 73-864.51

10 Claims



1. A gripping apparatus for a water test kit, said water test kit comprising a housing having a base portion, an upper portion, and two side edges, said gripping apparatus comprising:
 - a handle element;
 - a retaining bracket having a base portion and two side arm portions, said side arm portions being adapted to grip said two water test kit side edges;
 - a slit disposed on said handle element for receiving a base portion of said test kit; and

clip means disposed on said handle element above said slit for securing an upper portion of said test kit to said handle element; wherein said gripping apparatus may be used to manipulate said water test kit into a predetermined submerged location within a body of water for the purpose of obtaining one or more samples of said water.

5,589,649

DISSOLUTION TESTING APPARATUS

Gerald Brinker, North Brunswick; Peter Hladik, Piscataway, both of N.J., and Alan Gutwillig, Sterling, Va., assignors to Distek, Inc., North Brunswick, N.J.


Continuation of Ser. No. 201,633, Feb. 25, 1994, abandoned.

This application Feb. 14, 1995, Ser. No. 389,063

Int. Cl.⁶ G01N 13/00; B01L 7/00

U.S. Cl. 73-866

63 Claims



1. An apparatus for dissolution testing of a material in a test solution within a test vessel, comprising:
 - (a) a stirring element for stirring the test solution;
 - (b) a non-liquid-bath heating element placed around the outside of the test vessel for heating the test solution; and
 - (c) a controller for controlling the heating element to control the temperature of the test solution, wherein the stirring element comprises:
 - (1) a hollow shaft; and
 - (2) a temperature sensor located within the hollow shaft for generating signals representative of the temperature of the test solution when the hollow shaft is inserted into the test solution, wherein the controller controls the heating element in accordance with the signals from the temperature sensor.

5,589,650

APPARATUS AND METHOD FOR DEFINING MOLDING TECHNOLOGICAL PROPERTIES OF MOLDING SUBSTANCES IN CASTING WORKS

Eckardt Flemming; Werner Tilch, both of Freiberg; Thomas Schuster, Augsburg; Marian Ivanov, Freiberg, and Paul Eirich, Handheim, all of Germany, assignors to Maschinenfabrik Gustav Eirich, Germany

Filed Apr. 21, 1994, Ser. No. 230,892


Claims priority, application Germany, Apr. 21, 1993, 43 12 939.0; Apr. 21, 1993, 43 12 938.2

Int. Cl.⁶ G01N 33/38; 29/18; 29/00; 29/10

U.S. Cl. 73-866

25 Claims

5. A process for defining properties and composition of molding sand which comprises:



- introducing a sample of the molding sand into a test sleeve having a side wall and opposing ends;
- compressing the sample within said sleeve by means of a stamp and pressure plate which move toward each other to compress the sample within the sleeve to form a compressed sample having opposing ends;
- after compressing the sample measuring a length of the sample between the stamp and pressure plate;
- measuring ultrasonic speed through the sample by means of at least one ultrasonic transducer located at one of said ends;
- measuring at least one other property of the sample selected from the group consisting of moisture content, compressibility, ultrasound attenuation and temperature; and
- using all of such measurements to define the properties of the sample.

5,589,651


LOWER LEG FOR CRASH TEST DUMMY

David C. Viano, Bloomfield Hills; Edward A. Jedrzejczak, Brown City, and Joseph G. Smrcka, Northville, all of Mich., assignors to First Technology Safety Systems, Inc., Plymouth, Mich.

Filed Oct. 28, 1994, Ser. No. 331,282
Int. Cl.⁶ G01B 3/10

U.S. Cl. 73—866.4

9 Claims



- A lower leg assembly for a crash test dummy having a thigh bone comprising:
 - a tibia having an upper end, a lower end for connecting to a foot assembly of a crash test dummy and a front surface extending between said upper and lower ends of said tibia;
 - a pivot arm having an upper end adapted for pivotal connection to a lower end of a thigh bone of the crash test dummy and a lower end pivotally connected to said upper end of said tibia;
 - a lower leg skin having an interior space surrounded by an inner wall, said tibia being retained in said interior space; and

a leg laceration indicator being retained in said interior space between said inner wall and said front surface for indicating crash injuries whereby said leg laceration indicator is at least one of lacerated, punctured and inelastically deformed by forces applied to a portion of said lower leg skin abutting said leg laceration indicator during a crash test.

5,589,652


CERAMIC-PARTICLE-DISPERSED METALLIC MEMBER, MANUFACTURING METHOD OF SAME AND USE OF SAME

Toshiaki Arato, Katsuta; Yasuhisa Aono, Hitachi; Shigeo Tsuruoka, Hitachi, and Katsuhiko Komuro, Hitachi, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Feb. 23, 1994, Ser. No. 200,731

Claims priority, application Japan, Mar. 18, 1993, 5-058335
Int. Cl.⁶ C22C 9/00

U.S. Cl. 75—235

18 Claims



- A ceramic-particle-dispersed metallic member in which ceramic super fine particles, and solid lubricant particles or solid lubricant short size fibers are dispersed, wherein said ceramic super fine particles have the content not more than 1 wt % and the mean grain size not more than 200 nm, and a region where said ceramic super fine particles are dispersed in a matrix by not less than 500 in number per section area of one square micrometer at 1 wt % is formed substantially over the entirety region of said metallic member.

5,589,653


TUNING SYSTEMS FOR STRINGED INSTRUMENTS

Floyd D. Rose, 114 Via de la Valle, Del Mar, Calif. 92104
Filed Jun. 7, 1995, Ser. No. 484,121

Int. Cl.⁶ G10D 3/06

U.S. Cl. 84—314 N

6 Claims



- A stringed instrument comprising: a body; a neck attached to said body; a fretboard having first and second ends arranged on said body; a nut assembly mounted on said neck at one end of said

fretboard, said nut assembly comprising a plurality of individually pivotable string holders in combination with a fixed nut having a plurality of corresponding nut critical contact surfaces; a bridge including a plurality of bridge critical contact surfaces mounted on said body spaced from an opposing end of said fretboard, said plurality of bridge critical contact surfaces arranged at a selectively adjustable distance from corresponding ones of said plurality of nut critical contact surfaces; and a plurality of strings each having a first end and a second end and a predetermined length extending between said first and second ends, said plurality of strings extending across and being in contact with said plurality of bridge critical contact surfaces and corresponding ones of said plurality of nut critical contact surfaces and being secured at said first end to said bridge and at said second end to corresponding ones of said plurality of individually pivotable string holders so that said plurality of strings are under tension to permit obtaining of musical notes upon strumming or plucking thereof, said second end of said plurality of strings being selectively moveable with corresponding ones of said plurality of individually pivotable string holders along a path including a vertical component, said bridge including tuning means for obtaining at least harmonic tuning upon adjusting said distance between said plurality of bridge critical contact surfaces and said plurality of nut critical contact surfaces.

5,589,654

ELECTRONIC DANCE FLOOR SYSTEM


Kern T. Kowiser, and Kip M. Kowiser, both of I Catamaran St., Ste. A, Marina Del Rey, Calif. 90292

Filed Mar. 7, 1996, Ser. No. 612,117

Int. Cl.⁶ G01H 1/02; 1/55

U.S. Cl. 84—600

22 Claims



- An electronic dance floor system comprising:

- a composite pad assembly comprising:

- (1) an electrical switch module having a side surface, an upper surface, a lower surface and an output that terminates at a pair of output terminals that project from the side surface, where said switch module closes when pressure is applied to the upper surface,
- (2) an electrical cable assembly having an inward end and an outward end, where the inward end is attached to the output terminals on said electrical switch module and the outward end is attached to an output jack,
- (3) an upper pad section having a lower surface and an upper surface, where to the center of the lower surface is attached, by an attachment means, the upper surface of said electrical switch module,
- (4) a lower base section having a lower surface and an upper surface,
- (5) a center section having an inward edge, a centered module bore extending therethrough and a cable slot that interfaces with the module bore and that extends normal to the inward edge, wherein said module bore is placed over said electrical switch module and the cable slot is placed over said cable such that the outward end of said cable extends outward from the inward edge of said center section, where when the lower surface of said upper pad section is attached, by an attachment means, to the upper surface of said center section, and the lower surface of said center

section is attached, by an attachment means, to the upper surface of said lower base section said composite pad assembly is formed, wherein when pressure is applied to the upper surface of said upper pad section, the pressure closes said switch to produce an analog trigger signal that is applied through the output jack of said cable.

- a musical instrument digital interface (MIDI) converter which receives the trigger signal from said electrical switch module via the output jack and converts the signal to a corresponding digital signal, and
- a MIDI equipped sound source that through an audio cable, receives and converts the digital signal to a specific sound produced by said sound source.

5,589,655

ELECTRICAL INITIATION DEVICE WITH CONTACTOR

André Gaulmier, Charenton Du-Cher, France, assignor to Giat Industries, France


Filed Apr. 11, 1995, Ser. No. 420,839

Claims priority, application France, Apr. 15, 1994, 94 04526

Int. Cl.⁶ F41F 3/04; F41A 19/00

U.S. Cl. 89—1.814

7 Claims



- An electrical initiation device for an ammunition igniter, comprising:

- a contactor located in a launch tube, the contactor being equipped with means to impart translational movement and means to impart rotational movement, both the translational and rotational movement being imparted to the contactor by the weight of the ammunition on said contactor, and the contactor further being equipped with a head including cleaning means for abutting against and cleaning a contact surface of the ammunition igniter.

5,589,656

SPLIT WEDGE/BREECHBLOCK AND SEALING MEANS FOR GUN

Richard W. Tortorici, Jr., Schenectady, N.Y., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Feb. 12, 1996, Ser. No. 613,736


Int. Cl.⁶ F41A 3/74

U.S. Cl. 89—24

8 Claims

- A split stepped wedge/breechblock apparatus for opening and closing a powder chamber of a gun tube of a high pressure gun, said apparatus comprises:

- a wedge member having a first side adapted to fit against the one end of the gun tube to thereby close the powder chamber of the gun tube, said wedge member including a central longitudinal port which passes from the first side of the wedge member through to a second side of the wedge member and is aligned with the bore centerline of the gun tube when the first



side of the wedge member is fitted against the gun tube, said wedge member further including a sealing means associated with the first side of the wedge member for sealing the wedge member against the gun tube and the second side of the wedge member forming a stepped face.

a breechblock having a first side which includes a stepped face adapted to closely fit with the stepped face of said wedge member, said breechblock including a central longitudinal port which passes from said first side through to a second side and which is aligned with the central port of said wedge member when said breechblock is in a first, closed position, said breechblock being capable of a movement along a path substantially perpendicular to the bore centerline of the gun tube from said first, closed position to a second, open position, and

means for coupling said breechblock and said wedge member together so as to cause the sealing means of said wedge member to be drawn out of engagement with the gun tube to a drawback position during a first phase of said movement of said breechblock and causes said wedge member to move out of alignment with said gun tube to thereby open the powder chamber during a second portion of said movement of said breechblock.

5,589,657

DETONATING SYSTEM HAVING A DETONATOR WITHIN AN INSULATING CONTAINER

Uwe Gessel, Troisdorf; Rolf Rospek, Edemissen, and Helmut Zollner, Meerbusch, all of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Germany


Filed Apr. 26, 1995, Ser. No. 429,530

Claims priority, application Germany, Apr. 26, 1994, 44 14 411.3

Int. Cl. C F42C 19/12

U.S. Cl. 102—202.14

7 Claims



2. A detonating system comprising a detonator surrounded by a thermal insulating container, said detonator comprising an elec-

tronic detonator which is operative at temperatures up to 150° C., said insulating container comprising Dewar vessel having an open end positioned within an external protective sheath, a sealing plug for closing the open end of the Dewar vessel and an upper lid for closing an open end of the external protective sheath; said sealing plug and said upper lid each being provided with at least one opening for allowing entry of a detonating cord which is connected to the detonator and said detonating cord extending out of the insulating container.

5,589,658

SABOT WITH CONTROLLED SEPARATION OF THE ELEMENTS FOR SUBCALIBER PROJECTILES

Jean-Claude Sauvestre, 64 rue de la Vallée, 18230 Saint-Doulchard, France

PCT No. PCT/FR94/00984, § 371 Date Apr. 6, 1995, § 102(e) Date Apr. 6, 1995, PCT Pub. No. WO95/04913, PCT Pub. Date Feb. 16, 1995


PCT Filed Aug. 5, 1994, Ser. No. 411,661

Claims priority, application France, Aug. 6, 1993, 93 09708

Int. Cl. F42B 14/06

U.S. Cl. 102—521

13 Claims



1. A sabot for encasing a subprojectile in an ammunition casing holding a propellant charge, and wherein the sabot separates into multi-pieces upon being discharged out of a firearm, comprising:

a main body having a leading end and a trailing end;

an elongated external wall extending from the trailing end, wherein an external channel is formed between the external wall and the trailing end of the main body to enable the external wall to be flexible and wherein the external wall is adapted to contact an inner wall of the casing;

a partition wall extending inwardly from the elongated external wall, substantially perpendicularly to the main body, wherein the elongated wall, the partition wall and an outer surface of the subprojectile form an internal annular chamber, the partition wall separating the internal annular chamber from the propellant charge, and wherein the elongated external wall and the external channel form an external chamber, the elongated wall separating the inner and outer chambers, and

wherein the partition wall is breakable upon igniting the propellant charge to trap gases produced therein, which gases cause separation of the sabot upon being discharged.

5,589,659

CONTROL OVER EXCESS COATING COMPOSITION IN COATING DEVICE FOR TRAVELING PAPER WEB

Martin Kustermann, Heidenheim; Ingo Gottwald, Steinheim, and Manfred Ueberschär, Nattheim, all of Germany, assignors to J.M. Voith GmbH, Germany

Filed Sep. 10, 1993, Ser. No. 119,963

Claims priority, application Germany, Sep. 10, 1992, 42 30 276.5


Int. Cl. B05C 3/02

U.S. Cl. 118—413

22 Claims

1. A device for the predosing of coating composition on a web of material traveling past the device along a path of travel in a predetermined direction of travel, comprising

a doctor element;



a coating material guide member having a first side, an opposite second side and a tip, the guide member being structured and arranged to extend from a location away from the web toward the web such that the first side faces generally toward the web, the opposite second side generally faces away from the web and the tip of the guide member extends generally parallel to the doctor element across the web for defining a slot between the tip of the guide member and the web;

means for supporting the doctor element in engagement with the web at a location along the path of travel of the web; the guide member being spaced from the doctor element with the means supporting the doctor element for defining a feed channel for coating composition between the doctor element and the opposite second side of the guide member;

means for feeding the coating composition along the feed channel and toward the web; the means for feeding coating composition and the distance between the tip of the guide member and the doctor element being coordinated to define a pressure space for the coating composition between the opposite second side of the guide member and the doctor element;

the first side of the guide member being so shaped and oriented as to define a return channel and a discharge channel for excess coating composition which has moved out of the pressure space past the slot at the tip of the guide member and over the first side of the guide member, the discharge channel being defined between the first side of the guide member and a support member, and the first side of the guide member and the discharge channel being so shaped as to define a pressure reduction space for the excess coating composition in which substantially no back pressure is extended on the excess coating composition, the width of the discharge channel being at least 1.7 times the minimum width of the feed channel.

5,589,660

ENHANCED PERFORMANCE BLASTING AGENT

Robert W. Perry, Morgan Hill, and Forrest R. Goodson, San Jose, both of Calif., assignors to United Technologies Corporation, Hartford, Conn.

Filed Aug. 3, 1995, Ser. No. 510,751

Int. Cl. C06B 45/06

U.S. Cl. 149—18

7 Claims

1. A composition for quarry blasting comprising from about 13 to 15 weight percent of wax, from about 15 to 25 weight percent of aluminum powder, from about 10 to 52 weight percent sodium perchlorate and from about 10 to 52 weight percent ammonium nitrate, all weights being based on the total weight of the composition.

6. A blasting system comprising a mixture of two components, the first component being ANFO, and the second component being a composition comprising from about 13 to 15 weight percent of wax, from about 15 to 25 weight percent of aluminum powder, from about 10 to 52 weight percent sodium perchlorate and from about 10 to 52 weight percent ammonium nitrate, all weights being based on the total weight of the composition, wherein the weight ratio of the first component to the second component is from about 70/30 to 30/70.

5,589,661

SOLID PROPELLANT BASED ON PHASE-STABILIZED AMMONIUM NITRATE

Klaus Menke, Bruchsal; Jutta Böhnlein-Maass, Speyer; Helmut Schmid; Klaus M. Bucerius, both of Karlsruhe, and Walther Engel, Wöschbach, all of Germany, assignors to Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V., Munich, Germany


Filed Sep. 29, 1995, Ser. No. 536,640

Claims priority, application Germany, Oct. 5, 1994, 44 35 523.8

Int. Cl. C06B 45/10

U.S. Cl. 149—19.4

23 Claims



1. Solid propellant for rocket propulsion systems or gas generators, comprising 35 to 80 wt. % ammonium nitrate (AN) with an average particle size of 5 to 200 μ m, which is phase-stabilized (PSAN) by chemical reaction with CuO or ZnO, 15 to 50 wt. % of a binder system of a binder polymer and an energy-rich plasticizer, as well as 0.2 to 5.0 wt. % of a burning moderator of vanadium oxide/molybdenum oxide as an oxide mixture or mixed oxide.

5,589,662

PYROTECHNIC MIXTURE AND GAS GENERATOR FOR AN AIRBAG

Ulrich Schleicher, Hersbruck; Martin Klobner, Heideck; Wolfgang Schwarz, Nuremberg, and Eugen Feuerstake, Erlangen, all of Germany, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan


Division of Ser. No. 125,029, Sep. 21, 1993. This application Jun. 7, 1995, Ser. No. 475,673

Claims priority, application Germany, Sep. 21, 1992, 42 31 521.2; Apr. 2, 1993, 43 10 853.9

Int. Cl. C06B 35/00; 21/00

U.S. Cl. 149—35

25 Claims




1. Gas-generator, particularly for an airbag, comprising as a propellant charge a pyrotechnic mixture in the form of granulates comprising a nitrogen-generating substance, an inorganic oxidizing agent and as a binder silicone rubber, wherein said nitrogen-generating substance is an alkaline metal azide, an alkaline earth metal azide or an ammonium azide, characterized in that said mixture contains granulates each comprising a plurality of particles

of the nitrogen-generating substance and the inorganic oxidizing agent having a size of from 1 μ m to 200 μ m, which are bonded together by said binder, which is present in an amount of 13 to 28%, based on the weight of the total mixture.

a cap affixed to one end of the tubular member, said cap being made of a non-ferrous metal; means for mounting said tubular member into a housing wherein said cap is within said housing.


5,589,663
EARTHED CABLE GLAND
Alan C. D. Wales, Newcastle upon Tyne, United Kingdom, assignor to Elkay Electrical Manufacturing Company Limited, Newtown, United Kingdom
Filed Dec. 22, 1993, Ser. No. 171,651
Claims priority, application United Kingdom, Dec. 23, 1992, 9226789

Int. Cl.⁶ H02G 15/04
U.S. Cl. 174—51 9 Claims




1. An earthed cable gland for an armored cable for mounting on an enclosure wall comprising:
an electrically insulating gland nut;
an electrically insulating tubular entry member, threaded at one end for engagement with the gland nut, and with at least one slot extending longitudinally from an other end of the entry member along a part of its length;
means for mounting the entry member on an enclosure wall;
an electrically conducting tubular connection member retained within the entry member and for engagement with an armour covering of a cable extending through said cable gland;
an electrically conducting contact member located within the at least one slot in the entry member, the contact member being moveable inwardly, when said entry member is mounted on the enclosure wall, from a first position wherein said contact member is substantially free of the connection member to a second position wherein said contact member is in abutment with an electrical contact with the connection member; and
an earth tag for electrical contact with the contact member.

5,589,664
APPARATUS FOR CONTAINING ELECTRICAL COMPONENTS FOR SENSING OR MEASURING MAGNETIC FIELDS
John E. Rode, Fonda, N.Y., assignor to Temper Corporation, Fonda, N.Y.
Filed Sep. 21, 1993, Ser. No. 124,818
Int. Cl.⁶ H02G 3/08
U.S. Cl. 174—52.1 18 Claims



1. An apparatus for containing electric components for sensing or measuring magnetic fields comprising:
a tubular member made of a ferrous metal, said tubular member being capable of receiving electrical components for measuring magnetic fields therein;


5,589,665
CHILD-RESISTANT ELECTRICAL OUTLET COVER
Randal Scamacca, 222 Deer Park Ct., Seymour, Ind. 47274
Filed Jun. 7, 1994, Ser. No. 254,953
Int. Cl.⁶ H02G 3/14; H05K 5/03
U.S. Cl. 174—67 13 Claims



1. An electrical outlet shield apparatus comprising:
a face plate having a front and a back and an opening through the back for reception therein of a socket boss of a wall-mounted electrical socket assembly,
the face plate having a recess associated with the opening, the recess having a wall extending outwardly from the opening to the front of the plate;
a pair of anchor pins projecting from the wall of the recess toward the center of the recess;
a covering cup having an open end for reception in the recess, and the cup having a closed end,
the cup having a first slot intercepting the open end and a second slot intercepting the open end and an aperture spaced from a closed end of the second slot,
the spacing of the slots at the open end corresponding to the spacing of the pins so that the cup can be installed on the pins by advancing the open end of the cup straight into the recess with open ends of the slots in registry with the pins,
the cup having a wall portion between the second slot and the aperture and which, by abuttingly engaging one of the pins that is in the second slot, normally prevents turning the cup in the recess,
the wall portion being manually deflectable inwardly to clear that wall portion from the abuttingly engaging relationship with the one pin while the cup is in the recess to enable turning the cup to place the aperture in registry with the one pin,
the wall portion being resiliently restorable to non-deflected condition for reception of the aperture around the one pin to secure the cup in the recess.


5,589,666
ENCLOSURE FOR SEALING A SPLICE OF ELECTRICAL CABLES
David J. DeCarlo, Toms River; Thomas L. Mineur, High Bridge, and Ronald S. Stanwick, Belvidere, all of N.J., assignors to Thomas & Betts Corporation, Memphis, Tenn.
Continuation-in-part of Ser. No. 776,139, Oct. 15, 1991, Pat. No. 5,251,373. This application Apr. 30, 1993, Ser. No. 55,494
Int. Cl.⁶ H02G 15/06
U.S. Cl. 174—87 19 Claims

1. An enclosure for sealing a splice of electrical cables comprising:



a closure defining an interior space for accommodating a splice of cables and defining an opening for receipt of said splice therethrough;
a closure seal for sealably closing said closure opening and having one or more apertures for receipt therethrough of said cables;
means for sealing said closure seal to said closure and for sealing said cables to said closure seal at said one or more apertures;
an inlet fitting extending into and communicating with said interior space, said inlet fitting adapted to receive and pass an encapsulant under pressure therethrough into said interior space; and
an outlet fitting extending into and communicating with said interior space, said outlet fitting adapted to pass said encapsulant therethrough when said encapsulant is exposed to a predetermined pressure in said interior space.


5,589,667
REMOVABLE CORE FOR PRE-STRETCHED TUBE
Tomio Tsukazaki, Machida, and Tsunehisa Nakamura, Tokyo, both of Japan, assignors to Minnesota Mining and Manufacturing Company, Saint Paul, Minn.
PCT No. PCT/US93/03139, § 371 Date Sep. 14, 1994, § 102(e) Date Sep. 14, 1994, PCT Pub. No. WO93/22816, PCT Pub. Date Nov. 11, 1993
PCT Filed Apr. 2, 1993, Ser. No. 302,821
Claims priority, application Japan, Apr. 28, 1992, 4-109374; May 8, 1992, 4-116249
Int. Cl.⁶ H01B 7/00
U.S. Cl. 174—135 8 Claims



1. A removable core for supporting a pre-stretched elastomeric tube in a radially-expanded condition comprising:
a flexible sheet having opposite edges which include means for interlocking said opposite edges to maintain said sheet in a cylinder;
said sheet having a series of substantially parallel lines of localized weakening extending from one of said opposite edges to a point near but short of the other of said opposite edges, with successive lines extending from alternate edges of

said sheet to define a strip beginning at a free end and continuing in a serpentine length between and around consecutive lines;
so that pulling said free end will cause said strip to separate along said lines and permit said core to be removed from said tube without coiling of said strip.


5,589,668
MULTI-METAL LAYER WIRING TAB TAPE CARRIER AND PROCESS FOR FABRICATING THE SAME
Kenji Yamaguchi, Shoji Takagi, Sadahiko Mitsugi, Mamoru Mita, and Tomio Murakami, all of Hitachi, Japan, assignors to Hitachi Cable, Ltd., Tokyo, Japan
Filed Nov. 10, 1993, Ser. No. 149,795
Claims priority, application Japan, May 12, 1993, 5-110476
Int. Cl.⁶ H05K 1/14 23 Claims



1. A multi-metal layer wiring TAB tape carrier, comprising:
a plurality of conductive metal layers forming a wiring pattern of said TAB tape carrier;
at least one dielectric layer interposed between said conductive metal layers for electrically isolating said conductive metal layers from each other, a first conductive metal layer, of the plurality of conductive metal layers, being on a first side of said at least one dielectric layer, and a second conductive metal layer, of the plurality of conductive metal layers, being on an opposed side of the at least one dielectric layer, said at least one dielectric layer having connection holes therethrough; and
a conductive via layer formed in said connection holes, so as to electrically connect said first conductive metal layer to said second conductive metal layer through said at least one dielectric layer, by way of said conductive via layer,
wherein said conductive via layer and one of the first and second conductive metal layers are codeposited layers formed by vapor deposition, and wherein said conductive via layer and said one of the first and second conductive metal layers are a continuous integral layer.

5,589,669
ELECTRICAL CONTACT FOR PRINTED CIRCUIT BOARDS
Stuart D. Downes, Milford, and Leonard A. Merrill, Millis, both of Mass., assignors to EMC Corporation, Hopkinton, Mass.
Filed Dec. 28, 1995, Ser. No. 579,773
Int. Cl.⁶ H05K 1/02
U.S. Cl. 174—266 17 Claims

1. An electrical contact for mounting on a printed circuit board that has a plated-through hole, the contact comprising:
a conductive pin; and



a base attached to one end of the pin, the base having a triangular cross-section with three sides and three vertices, the base constructed and arranged to be mounted in a plated-through hole on a printed circuit board.

5,589,670

WEIGHING APPARATUS AND METHOD USING VARIABLE KEY BAR MEANS

Urs Berli, Bauma, Switzerland, assignor to Mettler-Toledo AG, Greifensee, Switzerland


Filed Jan. 24, 1994, Ser. No. 185,259

Claims priority, application Switzerland, Feb. 26, 1993, 589/93

Int. Cl.⁶ G01G 19/22

U.S. Cl. 177—25.13

5 Claims



1. Weighing apparatus comprising:

- a scale housing (1) including load responsive means (17);
- means (30) for producing a digital weight signal as a function of a load applied to said load-responsive means;
- digital signal processing means (50) for processing the digital weight signal in accordance with selected ones of a plurality of weighing parameters stored in a memory to produce a desired result;
- display means (13,15) controlled by the digital signal processing means for displaying:
 - selected ones of the plurality of weighing parameters, and
 - said desired result; and
- variable keyboard means including:
 - a first tare bar key (7) for taring said digital weight signal producing means and said display means; and
 - a second parameter bar key (11) for selecting weighing parameters and programs indicated in said display, said second bar key including a plurality of variable switching portions of variable length longitudinally of said parameter bar key, respectively.

5,589,671 ROTARY SWITCH WITH SPRING STABILIZED CONTACT CONTROL ROTOR


David G. Hackbarth, New Berlin, Wis.; Kenyon A. Hapke, Libertyville, Ill., and Spencer C. Schantz, Dousman, Wis., assignors to US Controls Corp., New Berlin, Wis.

Filed Aug. 22, 1995, Ser. No. 518,108

Int. Cl.⁶ H01H 19/60; 21/80; G05G 5/06

U.S. Cl. 200—6 R

17 Claims



1. A rotary switch comprising:

- a base member and a housing for enclosing the base member,
- a plurality of electrical switch contacts mounted to said base member,
- a rotor including a shaft journaled for rotation in said housing and means on said shaft for operating said switch contacts in response to rotation of said shaft, and including an index wheel mounted to the shaft coaxially therewith,
- said index wheel having circumferentially spaced apart radially outwardly extending teeth defined by curved radially inwardly depressed recesses between said teeth,
- a plastic spring operatively engaged with said index wheel to control said rotor to turn in discrete angular steps when said shaft is turned,
- said spring is comprised of two longitudinally extending laterally spaced apart deflectable legs having opposite free end portions and struts spanning laterally between said legs and joined with said legs, respectively, near said opposite free end portions, each of said legs having a detent formed therein intermediate of said free end portions, said detents being convex and registered in said recesses of said index wheel when said rotor has turned one step,
- said housing having pairs of laterally spaced apart slots with said pairs of slots longitudinally spaced apart to provide for inserting in said pairs of slots said free end portions of said legs of said spring and,
- said end portions of said legs being constrained in said slots to prevent said legs from moving longitudinally by any amount when said legs are deflected by said detents thereon passing over said tips of said index wheel teeth when said rotor is turned.

5,589,672

CIRCUIT BREAKER WITH ARC QUENCHING DEVICE AND VENT

Naoshi Uchida; Masao Miura; Jun Oyama; Katsunori Kuboyama, and Koji Asakawa, all of Kawasaki, Japan, assignors to Fuji Electric Co., Ltd., Kawasaki, Japan

Filed Jun. 7, 1995, Ser. No. 477,822


Claims priority, application Japan, Jun. 14, 1994, 6-155332; Dec. 20, 1994, 6-334792

Int. Cl.⁶ H01H 9/36; 33/04

U.S. Cl. 218—34

11 Claims

1. A circuit breaker comprising:



- a stationary contact member bent back into a U-shape and having a stationary contact at a bent back portion thereof;
- a U-shaped magnetic driving core disposed at the bent back portion of the stationary contact member and having arms extending upwardly from the bent back portion;
- a moving contact member situated adjacent to the stationary contact member to be able to contact with the stationary contact;
- a plurality of grids laminated vertically with a space therebetween and situated adjacent to the stationary contact member to surround the same; and
- a unitary molded insulator situated around the stationary and moving contact members, said insulator including a pair of side walls facing to each other, each side wall having a hollow part extending upwardly from a lower end thereof, and a plurality of slots arranged in the opposed side walls to vertically space apart from each other so that when the circuit breaker is assembled, the side walls are located to sandwich the stationary and moving contact members while the arms of the magnetic driving core are located in the hollow parts of the side walls, and the grids are inserted into the slots and vertically piled together.

5,589,673

ELECTRIC HIGH-TENSION CIRCUIT BREAKER

Volker Lehmann; Heiner Marin, and Ingolf Reiher, all of Berlin, Germany, assignors to Siemens Aktiengesellschaft, München, Germany

PCT No. PCT/DE93/00129, § 371 Date May 15, 1995, § 102(e) Date May 15, 1995, PCT Pub. No. WO93/20573, PCT Pub. Date Oct. 14, 1993


PCT Filed Feb. 9, 1993, Ser. No. 313,086

Claims priority, application Germany, Mar. 31, 1992, 42 11 159.5

Int. Cl.⁶ H01H 33/86

U.S. Cl. 218—66

10 Claims



- A high-tension circuit breaker with a separating gap and having self-generated quenching gas flow comprising:

- a compression device for blow-out of electric arcs, the compression device including:
 - a compression space delimited by an inner wall of the compression device and by a piston;
 - a pressure chamber heatable by the arc energy, adjacent to the separating gap and connected to said compression space of the compression device;
- a piston for insertion into an open end of the compression device, the piston including:
 - a low-pressure space delimited by an inner wall of the piston; and
 - a valve device located on the piston, between the compression space and the low-pressure space, the valve device comprising first and second concentric washers in contact with one another, the second washer having an outer diameter greater than an outer diameter of the first washer and an inner diameter greater than an inner diameter of the first washer and smaller than an outer diameter of the first washer, wherein the valve device acts as a refill valve by allowing the compression space to be refilled with gas from the low-pressure space and as a relief valve by allowing gas under pressure to pass from the compression space to the low-pressure space.

5,589,674

METAL-ENCAPSULATED, GAS-INSULATED SWITCHING INSTALLATION

Ernst Berger, Mellingen; Franz Heil, Baden-Rütihof; Herbert Schifko, Glattbrugg, and Piero Tecchio, Oberrohrdorf, all of Switzerland, assignors to ABB Management AG, Baden, Switzerland


Filed Mar. 29, 1995, Ser. No. 412,926

Claims priority, application Switzerland, Apr. 19, 1994, 1218/94

Int. Cl.⁶ H02B 13/035; H01H 33/70

U.S. Cl. 218—71

10 Claims



- A single-phase, metal-encapsulated, gas-insulated switching installation, the modular circuit breaker pole comprising:
 - a modular circuit breaker pole, the modular circuit breaker pole including
 - an enclosure lower part having a first end and a second end, and at least one opening for connecting an isolator for a busbar system between the first end and the second end of the enclosure lower part,
 - an enclosure upper part having a first end and a second end, at least one of the first end and the second end of the enclosure upper part being attachable to either of the first end and the second end of the enclosure lower part,
 - an enclosure cover attachable to either of the second end and the first end of the enclosure upper part;
 - the enclosure lower part, the enclosure upper part, and the enclosure cover defining at least part of a circuit breaker pole enclosure having a pole axis, and
 - a quenching chamber disposed inside of the pole enclosure and electrically connectable to the isolator through the opening in the enclosure lower part.

5,589,675

VACUUM SWITCH


Nole L. Walters, Granger, Ind.; Edward A. Raleigh, Madison, Wis., and Peter H. Thiel, Bloomington, Ind., assignors to Trinetics, Inc., Mishawaka, Ind.

Filed Apr. 8, 1994, Ser. No. 224,819

Int. Cl.⁶ H01H 33/02; 33/66

U.S. Cl. 218—140

22 Claims



1. A mechanism for opening and closing the contacts of a vacuum switch, comprising:
 - a drive link coupled to a movable contact of the vacuum bottle;
 - a first toggle link coupled to said drive link;
 - a drop link coupled to said first toggle link and to a lever;
 - a cam rotatably coupled to said lever for imparting motion to said lever;
 - a handle coupled to said cam for rotating said cam;
 - an over-center spring assembly coupled to said cam for resisting movement of the movable contact until a predetermined level of force is stored in said spring assembly;
 - a clevis attached to the movable contact; and
 - a pin extending through the arms of said clevis and said drive link.

5,589,676

ELECTRONIC CASH REGISTER SYSTEM

Kesayoshi Iguchi, Fujisawa, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Mar. 21, 1995, Ser. No. 407,627

Claims priority, application Japan, May 27, 1994, 6-115423

Int. Cl.⁶ G07G 1/00

U.S. Cl. 235—7 R

4 Claims



1. An electronic cash register system comprising:
 - a plurality of order registers each having a register number and for receiving content of orders;

a display unit for displaying the content of orders received by said plurality of order registers;

a display control unit having an internal memory, for controlling display on said display unit and successively storing in said internal memory a plurality of said content of orders received by said plurality of order registers in association with the register number of the one of said plurality of order registers which received one of said plurality of content of orders; and

a plurality of account registers each associated with at least one of said plurality of order registers and having its own register number corresponding to that of said at least one of said plurality of order registers and for reading out the content of orders from the internal memory of said display control unit on the basis of said own register number and then accounting for the read-out content of orders.

5,589,677

PLEDGE LOCK FOR A SHOPPING TROLLEY

Horst Merchel, Bietigheim-Bissingen, Germany, assignor to Vendoret Holding S. A., Luxembourg-Hesperange, Luxembourg

Continuation of Ser. No. 254,293, Jun. 6, 1994, abandoned.


This application Mar. 28, 1996, Ser. No. 623,983

Claims priority, application Germany, Jun. 4, 1993, 43 18 627.0; Dec. 8, 1993, 43 41 791.4

Int. Cl.⁶ G06K 15/00

U.S. Cl. 235—383

12 Claims



1. An information system for a store, comprising:
 - a plurality of interlockable shopping trolleys, each of said trolleys being provided with a respective pledge lock securing a locked position of the trolley;
 - detaching means on each of the trolleys cooperating with the pledge lock for removably enabling release of the respective trolley;
 - means on each of the locks forming a respective opening;
 - an information carrier forming a pledge and carrying shopper information for a customer and removably inserted in the respective opening to unlock the pledge lock, said information carrier being retained in the unlocked pledge lock;
 - central information database means for storing information derived from and applicable to the respective carrier; and
 - means separate from the pledge lock in the store and forming part of the central information database means for scanning the respective carrier while it is retained in the pledge lock for communication of information between the central information database means and the respective information carrier.

5,589,678

SCANNER OF A BAR CODE VERIFIER

Toru Atsumi, Yasuhiro Kamijo, both of Kariya; Yoshiki Furukawa, and Naoki Matsumura, both of Hadano, all of Japan, assignors to Nippon Denso Co. Ltd., and Stanley Electric Co. Ltd., both of Aichi-ken, Japan

Filed Sep. 21, 1995, Ser. No. 531,469

Claims priority, application Japan, Sep. 22, 1994, 6-254630

Int. Cl.⁶ G06K 7/10

U.S. Cl. 235—472

9 Claims

1. A scanner for reading a bar code comprising:
 - a light source for irradiating a bar code with rays of light;
 - a sensor device for receiving rays of light reflected by said bar code;

5,589,680

PORTABLE LASER DIODE SCANNING HEAD


Jerome Swartz, Old Field; Howard M. Shepard, Great River; Mark J. Krichever, Hauppauge; Boris Metlitsky, Stony Brook, and Edward Barkan, Setauket, all of N.Y., assignors to Symbol Technologies, Inc., Holtsville, N.Y.

Continuation of Ser. No. 163,580, Dec. 7, 1993, abandoned, which is a continuation of Ser. No. 784,619, Oct. 30, 1991, abandoned, which is a continuation of Ser. No. 562,037, Aug. 2, 1990, abandoned, which is a continuation-in-part of Ser. No. 454,144, Dec. 21, 1989, Pat. No. 5,021,641, which is a division of Ser. No. 295,151, Jan. 9, 1989, Pat. No. 4,897,532, which is a division of Ser. No. 148,669, Jan. 26, 1988, Pat. No. 4,825,057, which is a division of Ser. No. 706,502, Feb. 28, 1985, abandoned. This application Feb. 22, 1996, Ser. No. 604,858

Int. Cl.⁶ G06K 7/10

U.S. Cl. 235—472

8 Claims



1. A case for housing said light source and said sensor device; characterized in that
- said case is provided with an opening for allowing said reflected rays of light to enter the case arranged at a position to be placed vis-a-vis said bar code;
- a viewing window for allowing the operator of the scanner to confirm the alignment of said bar code and said opening; and
- a blind shutter for closing said viewing window, to block external light from entering the scanner.

5,589,679

PARALLELEPIPED-SHAPED OPTICAL SCANNING MODULE


Paul Dvorkis, Stony Brook, and Howard Shepard, Great River, both of N.Y., assignors to Symbol Technologies, Inc., Holtsville, N.Y.

Continuation of Ser. No. 237,531, May 3, 1994, Pat. No. 5,479,000, which is a continuation-in-part of Ser. No. 789,705, Nov. 8, 1991, Pat. No. 5,412,198, which is a continuation-in-part of Ser. No. 520,464, May 8, 1990, Pat. No. 5,168,149, which is a continuation-in-part of Ser. No. 428,770, Oct. 30, 1989, Pat. No. 5,099,110. This application Dec. 19, 1995, Ser. No. 575,662

Int. Cl.⁶ G06K 7/10

U.S. Cl. 235—472

13 Claims



1. An optical scanning module including a light emitter for emitting a light beam and a detector for receiving light reflected back from indicia with portions of differing light reflectivity and producing an electrical signal corresponding to the differing light reflectivity of the indicia, comprising:
 - a first circuit board carrying a first circuit forming at least a portion of a first side of said module;
 - a second circuit board carrying a second circuit forming at least a portion of at least a portion of a second side of said module;
 - a base forming at least a portion of a third side of said module; said first and second circuits being electrically connected to each other; and
 - said optical scanning module being in the shape of a rectangular parallelepiped.

5,589,681

CARD RECEIVER ENABLING A BROKEN CARD TO BE EJECTED AND CARD READER USING IT

Bruno Merlin, Argenteuil, and Jean Quintana, Cergy, both of France, assignors to Societe d'Applications Generales d'Electricite et de Mecanique Sagem, France

PCT No. PCT/FR93/00533, § 371 Date Jan. 26, 1995, § 102(e) Date Jan. 26, 1995, PCT Pub. No. WO93/25977, PCT Pub. Date Dec. 23, 1993

PCT Filed Jun. 4, 1993, Ser. No. 351,238


Claims priority, application France, Jun. 4, 1992, 92 06781

Int. Cl.⁶ G06K 13/00

U.S. Cl. 235—482

11 Claims

1. Information-bearing-card receiver (1), including an insertion slot (4) made between two lips (5, 5A), with a bearing lip (5) being one of the two lips, means (6, 17P) for bending the card (3) which are arranged, in the direction of insertion of the card (3), beyond this bearing lip (5), means (11) for guiding the front edge (3A) of



the said card (3) in order to bring the card (3) into a read position in which the card is capable of being read when the card is fully inserted, and means (8) for receiving, in the read position, the front edge (3A) of the card (3), which include a limit-stop wall (9) constructed so as to be moved in the direction of insertion of the card (3) under the action of a thrust by the card (3) and against the action of first return means (13), characterized by the fact that the bending means (6, 17P) are arranged for acting in the direction of the bearing lip (5) and against the action of the guiding means (11) and for laterally ejecting the card (3) out of its introduction path when is out of reach of the bearing lip (5).

5,589,682

PHOTOCURRENT DETECTOR CIRCUIT WITH HIGH SENSITIVITY, FAST RESPONSE TIME, AND LARGE DYNAMIC RANGE


Dale M. Brown, Schenectady, and Gerald J. Michon, Waterford, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Jun. 7, 1995, Ser. No. 474,238

Int. Cl.⁶ H01J 40/14; H03F 17/00; G01J 5/28

U.S. Cl. 250—214 A

11 Claims



1. A photocurrent detector circuit comprising:
a photodetector;
an operational amplifier, the photodetector being coupled to an input terminal of the operational amplifier;
a first resistor being coupled between the photodetector and an output terminal of the operational amplifier;
a first diode;
a second resistor, the first diode being coupled between the photodetector and the second resistor;
a low gain bias network being coupled between the second resistor and the output terminal of the operational amplifier;
a second diode being coupled to the photodetector; and
a clamp bias network being coupled between the second diode and the output terminal of the operational amplifier.

5,589,683 OPTICAL RECEIVER APPARATUS FOR QUICKLY DETECTING LOSS OF A COMPOSITE OPTICAL SIGNAL INPUT EMPLOYING A LOSS-OF-CLOCK DETECTOR

Yukako Nakai, Kawasaki, Japan, assignor to Fujitsu Limited, Kanagawa, Japan


Filed Sep. 19, 1994, Ser. No. 308,587

Claims priority, application Japan, Sep. 20, 1993, 5-233102

Int. Cl.⁶ H01J 40/14

U.S. Cl. 250—214 R

6 Claims



1. An optical signal receiver apparatus comprising:
a photoelectric conversion circuit for receiving an optical signal conveying cyclic timing information, and converting the optical signal into an electrical signal conveying the cyclic timing information;
a receiving clock signal extraction circuit for extracting a receiving clock signal indicating the cyclic timing information, from the electrical signal; and
a loss-of-clock digital-detection circuit for detecting absence of a change in a digital level of the receiving clock signal, wherein said loss-of-clock digital-detection circuit comprises a latch circuit for latching a predetermined constant electric level cyclically in synchronization with the digital level change in the receiving clock signal, and being reset by receiving a cyclic reset signal having a frequency less than the frequency of the receiving clock signal, the time required to detect loss of clock being determined by the frequency of said reset signal.

5,589,684

MULTIPLE DIODE LASERS STABILIZED WITH A FIBER GRATING

Brian F. Ventrudo, Victoria, and Peter G. Berrang, Sidney, both of Canada, assignors to SDI, Inc., San Jose, Calif.

Continuation-in-part of Ser. No. 267,785, Jun. 28, 1994, Pat. No. 5,485,481. This application Mar. 30, 1995, Ser. No. 415,129

Int. Cl.⁶ G02F 1/01

U.S. Cl. 250—225

30 Claims



1. Apparatus for generating a stable source of optical radiation comprising:
two mutually incoherent diode lasers that emit linearly polarized light beams substantially in a single spatial mode and that include a diode laser cavity including an output facet having substantially broadband reflectivity capable of generating multiple longitudinal modes within the laser cavity in the absence of external optical feedbacks, said beams comprising mutually incoherent beams of substantially orthogonal polarizations;
a polarizing beam combiner to receive said beams of substantially orthogonal polarizations and combine them into a single, substantially unpolarized beam of light, while adding the optical power of said beams;

first means for directing the orthogonally polarized emission of each diode laser into the polarizing beam combiner while maintaining the polarization state of each diode laser such that the light beams from each laser exiting the beam combiner are substantially overlapped and co-propagating;
an optical fiber which includes a guided-wave region that is capable of sustaining at least one mode of wavelength of the diode laser;
second means for directing the combined light of the diode lasers into the guided-mode region of the optical fiber;
a narrow-bandwidth reflector formed in the guided mode region of the optical fiber.

5,589,685

MATRIX ENHANCED SIMS


Kuang Jen Wu, 2705 Alma St., and Robert W. Odom, 2068 Harvard St., both of Palo Alto, Calif. 94306

Filed May 26, 1995, Ser. No. 451,257

Int. Cl.⁶ H01J 49/90

U.S. Cl. 250—282

25 Claims



1. A method for measuring any one of:
(i) a spatial distribution of a plurality of analyte particulates;
(ii) a difference in masses of each of said plurality of analyte particulates;
(iii) a mass of each of said analyte;
which includes the steps in operable order:
(a) providing a mass spectrometer constructed to project an energetic primary beam on a target surface of said mass spectrometer and to impose an accelerating field between said target surface and an accelerating electrode wherein said primary beam is one of:
(i) an electron beam;
(ii) a negative ion beam;
(iii) a positive ion beam; and
(iv) neutral beam;
(b) mixing a quantity of an analyte component in a quantity of a matrix forming compound such as to form a sample wherein said matrix forming compound is one of an acid and a base selected to enhance ionization efficiency;
(c) depositing said sample on a substrate;
(d) positioning said substrate on said target surface;
(e) projecting said primary beam onto said sample such as to sputter said analyte particulates from said sample;
(f) directing said sputtered analyte particulates toward said accelerating electrode in an extraction field then into a drift region to a detector; and
(g) measuring the mass-to-charge ratio of analyte said particulates by said mass spectrometer.

5,589,686

METHOD OF AN APPARATUS FOR REAL-TIME NANOMETER-SCALE POSITION MEASUREMENT OF THE SENSOR OF A SCANNING TUNNELING MICROSCOPE OR OTHER SENSOR SCANNING ATOMIC OR OTHER UNDULATING SURFACES

Tetsuo Ohara, 12 Lindall Pl., #4, Boston, Mass. 02114


Continuation of Ser. No. 216,057, Mar. 22, 1994, abandoned.

This application Jan. 19, 1996, Ser. No. 588,651

Int. Cl.⁶ G01B 5/28; H01J 37/26

U.S. Cl. 250—306

20 Claims



13. Apparatus for real-time nanometer position measurement of a sensor probe scanning a periodically undulating surface as the surface and the probe are relatively moved, having, in combination with said probe, means for setting up a current between the probe and the surface; means operable during said scanning for oscillating the probe about a reference origin point of the probe by a controlling sinusoidal voltage; means for measuring the output sinusoidal voltage generated by the current during said oscillating and after passing to the surface; means for comparing the phase and/or amplitude of the controlling and output voltages by means for multiplying said output sinusoidal voltage by said controlling sinusoidal voltage; and means for developing from such comparing, positional signals on a continual basis, indicative of the direction and distance of the probe off the apex of the nearest atom or undulation of the surface, and thus the position of the probe along the surface.

5,589,687

INFRARED DETECTION DEVICE COMPRISING A PYROELECTRIC THIN FILM AND METHOD FOR FABRICATING THE SAME

Satoshi Kawata, Masaji Dohi, Yoichi Sakachi, and Hiroshi Daiku, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Filed Mar. 30, 1995, Ser. No. 413,958

Claims priority, application Japan, Apr. 18, 1994, 6-101682

Int. Cl.⁶ G01J 1/02

U.S. Cl. 250—338.3

11 Claims



1. An infrared detection device comprising:
a substrate having a surface which has a plurality of mesas, each of said mesas having a hollow structure, and
a pyroelectric thin film formed on said surface having said mesas.

5,589,688


INFRARED RADIATION SENSOR

Mitsuteru Kimura, 2-56, Shiomidai 3-chome, Shichigahama-cho, Miyagi-gun, Miyagi-ken, and Takeshi Kudo, Kanagawa, both of Japan, assignors to Terumo Kabushiki Kaisha, Tokyo, and Mitsuteru Kimura, Miyagi-ken, both of Japan
Filed Nov. 29, 1995, Ser. No. 564,428

Claims priority, application Japan, Nov. 30, 1994, 6-296565
Int. Cl.⁶ G01J 5/20

U.S. Cl. 250—338.4

6 Claims



1. A heat sensitive infrared radiation sensor comprising an n type single crystal area formed in the shape of a thin film by doping a sensor substrate made of p type semiconductor with an n type impurity through the surface of said sensor substrate, a temperature sensor element formed in said n type single crystal area, a hollow part formed by removing by etching said p type semiconductor from the substantially lower and peripheral parts of said n type single crystal area as to leave said n type single crystal area of the sensor substrate, and a thermally and electrically insulating thin film bridge structure part having said n type single crystal area in the shape of a thin film provided with said temperature sensor element carried thereon, said bridge structure part formed over said hollow part and including a light receiving part.

5,589,689

INFRARED DETECTOR WITH FABRY-PEROT INTERFEROMETER

Yrjö Koskinen, Helsinki, Finland, assignor to Vaisala Oy, Helsinki, Finland


Filed Jul. 7, 1995, Ser. No. 499,188

Claims priority, application Finland, Jul. 7, 1994, 943251

Int. Cl.⁶ G01J 5/10

U.S. Cl. 250—339.01

20 Claims



1. A silicon micromechanically fabricated infrared detector comprising:
an electrically tuneable Fabry-Perot interferometer having mirrors and being manufactured by silicon micromechanical techniques;
an infrared radiation absorbing layer integrally coupled with one of the mirrors;
thermal detector means for detecting the amount of radiation absorbed into said absorbing layer.

5,589,690

APPARATUS AND METHOD FOR MONITORING CASTING PROCESS


Thomas A. Siewert, Boulder; William P. Dubé, Denver, and Dale W. Fitting, Golden, all of Colo., assignors to National Institute of Standards and Technology, Washington, D.C.

Filed Mar. 21, 1995, Ser. No. 407,699

Int. Cl.⁶ G01N 23/20

U.S. Cl. 250—390.06

25 Claims



1. A method for monitoring an interface between a crystalline phase and an amorphous phase of a material within a container, comprising the steps of:

directing source radiation through at least one wall of a container and into an interface between a portion of a crystalline phase of a material and a portion of an amorphous phase of said material contained in said container to provide diffracted radiation having a first diffraction component with a first spatial radiation distribution associated with said crystalline phase and a second diffraction component with a second spatial radiation distribution associated with said amorphous phase, said first and second spatial radiation distributions being spatially distinct;

receiving at least a portion of at least one of said first diffraction component and said second diffraction component of said diffracted radiation on a radiation sensitive detector means located outside of said container to provide an output signal, said output signal including information corresponding to said spatial radiation distribution of the received portion; and using said output signal to monitor said interface between said crystalline phase and said amorphous phase.

5,589,691

PROCESS FOR RECOVERY AND RECYCLE OF METHANESULFONIC ACID AND PHOSPHOROUS ACID

Edamandal S. Venkataramani, Woodbridge; Andrew L. Forman, Scotch Plains; Ralph J. Maglette, Jr., Piscataway; William A. Vaughn, Avenel, all of N.J., and Richard R. Dauer, Longmont, Colo., assignors to Merck & Co., Inc., Rahway, N.J.

Filed Jun. 6, 1994, Ser. No. 254,213

Int. Cl.⁶ C09K 3/00

U.S. Cl. 252—182.11

13 Claims

1. A process comprising the steps of:

- (i) contacting an aqueous medium comprised of the sodium salts of methanesulfonic acid and phosphorous acid with hydrochloric acid to obtain an HCl concentration of about 6N or above to precipitate sodium chloride;
- (ii) separating sodium chloride from the aqueous medium in (i);
- (iii) washing the separated sodium chloride with saturated aqueous sodium salt solution to remove residual methanesulfonic acid;
- (iv) removing hydrochloric acid and water from the resulting medium in Step (iii) by atmospheric distillation;
- (v) separating methanesulfonic acid and phosphorous acid from the resulting medium in Step (iv), which contains small

5,589,693

SUBSTRATES AND METHODS FOR GAS PHASE DEPOSITION OF SEMICONDUCTORS AND OTHER MATERIALS

Tien-Heng Chiu, Spotswood, N.J., assignor to Lucent Technologies Inc., Murray Hill, N.J.


Division of Ser. No. 346,444, Nov. 29, 1994, Pat. No.

5,462,012. This application Jun. 7, 1995, Ser. No. 475,110

Int. Cl.⁶ H01L 23/58

U.S. Cl. 257—48

12 Claims



1. A substrate for semiconductor growth comprising: a wafer having a temperature monitoring zone of a growth preventing material, the temperature monitoring zone having an area of at least about 3 mm².

5,589,692

SUB-NANOSCALE ELECTRONIC SYSTEMS AND DEVICES

Mark A. Reed, New Haven, Conn., assignor to Yale University, New Haven, Conn.


Continuation of Ser. No. 893,092, Jun. 1, 1992, Pat. No.

5,475,341. This application Apr. 11, 1995, Ser. No. 421,357

Int. Cl.⁶ H01L 29/06:35/24

U.S. Cl. 257—23

3 Claims



1. A picoelectronic device comprising:

- a first and second conductor chains, each comprising multiple monomer units having mutually conjugated bonding;
 - a first barrier region, connected to said first conductor chain, said first barrier having a potential energy for electrons which is less favorable than that of said first conductor chain;
 - a second barrier region, connected to said second conductor chain, said second barrier having a potential energy for electrons which is less favorable than that of said second conductor chain;
 - a well region, connected to said first and second barrier regions, said well region having a potential energy for electrons which is more favorable than that of said first and second barrier regions;
 - a third barrier region, connected to said well region, said third barrier having a potential energy for electrons which is less favorable than that of said well;
 - a third conductor chain, comprising multiple monomer units having mutually conjugated bonding, and operatively connected to said well region through said third barrier region;
- whereby changing potentials applied to said third chain can effect modulation of currents between said first and second chains.

5,589,694

SEMICONDUCTOR DEVICE HAVING A THIN FILM TRANSISTOR AND THIN FILM DIODE

Toru Takayama, Kanagawa, and Yasuhiko Takemura, Atsugi, both of Japan, assignors to Semiconductor Energy Laboratory Co., Ltd., Kanagawa-ken, Japan

Division of Ser. No. 216,107, Mar. 21, 1994, Pat. No.

5,501,989. This application Mar. 28, 1995, Ser. No. 411,972

Claims priority, application Japan, Mar. 22, 1993, 5-86744;


Mar. 22, 1993, 5-86745; Mar. 22, 1993, 5-86746; Mar. 22, 1993,

5-86747

Int. Cl.⁶ H01L 29/78

U.S. Cl. 257—67

25 Claims



1. A semiconductor circuit having at least one thin film transistor and at least one thin film diode formed on a substrate, wherein a semiconductor film that forms an active region (channel-forming region) of said thin film transistor comprises the same layer of a semiconductor film as that of an intrinsic region (i-layer) of said thin film diode, and a concentration of a catalyst element for promoting crystallization of semiconductor contained in source and drain regions of said thin film transistor is higher by more than one digit than that in the active region of said thin film transistor.

5,589,695

HIGH-PERFORMANCE HIGH-VOLTAGE DEVICE STRUCTURES

Satwinder Malhi, Garland, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Continuation of Ser. No. 158,675, Nov. 29, 1993, abandoned.


This application Jun. 2, 1995, Ser. No. 459,369

Int. Cl.⁶ H01L 27/01:29/68:29/78

U.S. Cl. 257—77

13 Claims

1. A high-voltage power device structure having a low $R_{ds(on)}$ comprising:



- a source region of a first conductivity type formed in a silicon substrate region;
- a gate electrode located over said silicon substrate region adjacent said source region;
- a high voltage drift region located in a non-silicon-only substrate region, wherein said non-silicon-only substrate region comprises silicon-carbide;
- a drain region of said first conductivity type located in said high voltage drift region;
- a first diffused region of said first conductivity type located in said silicon substrate region adjacent said gate electrode;
- a second diffused region of said first conductivity type located in said high voltage drift region and connected to said first diffused region.

5,589,696

TUNNEL TRANSISTOR COMPRISING A SEMICONDUCTOR FILM BETWEEN GATE AND SOURCE/DRAIN


Toshio Baba, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Oct. 14, 1992, Ser. No. 960,863

Claims priority, application Japan, Oct. 15, 1991, 3-265749
Int. Cl.⁶ H01L 29/06; 29/861; 29/866

U.S. Cl. 257—105

15 Claims



1. A tunnel transistor including a semiconductor substrate having a principal surface and doped with an impurity of a first conductivity type to a first concentration and degenerate first and second semiconductor layers formed contiguous to said principal surface with a spacer region left therebetween and doped with an impurity of said first conductivity type and a second conductivity type, respectively, to a concentration higher than said first concentration, said tunnel transistor comprising:

- a degenerate third semiconductor layer formed on top of said principal surface and doped with an impurity of said second conductivity type to cover said spacer region and first and second parts of said first and said second semiconductor layers, respectively, while leaving third and fourth parts of said first and said second semiconductor layers uncovered;
- a gate isolating film formed on said third semiconductor layer over said first part of the first semiconductor layer and having a wider forbidden bandwidth than said third semiconductor layer;
- a gate electrode on said gate isolating film; and
- a pair of electrodes forming ohmic junctions with said third and said fourth parts of the first and the second semiconductor layers.

5,589,697

CHARGE PUMP CIRCUIT WITH CAPACITORS


Michael C. Smayling, Missouri City, Tex., and Luciano Talamonti, Rieti, Italy, assignors to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 270,090, Jul. 1, 1994, Pat. No. 5,479,040, which is a division of Ser. No. 65,694, May 21, 1993, Pat. No. 5,364,801, which is a continuation of Ser. No. 628,783, Dec. 17, 1990, abandoned. This application Jun. 7, 1995, Ser. No. 473,051

Int. Cl.⁶ H01L 29/788

U.S. Cl. 257—204

25 Claims



1. A charge pump comprising:
- first and second clocks having a predetermined phase differential;
- a plurality of Schottky diodes coupled in series; and
- a plurality of capacitors having first and second plates, said first plates coupled between said Schottky diodes and said second plates alternately coupled to said first and second clocks.

5,589,698

SOLID STATE IMAGING DEVICE HAVING SLIDING POTENTIAL GRADIENT


Yasutaka Nakashiba, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Dec. 7, 1994, Ser. No. 350,897

Claims priority, application Japan, Dec. 10, 1993, 5-310513
Int. Cl.⁶ H01L 27/148; 29/768

U.S. Cl. 257—231

9 Claims



1. A solid state imaging device comprising:
- a) a plurality of photo-electric converter elements;
- b) a vertical charge transfer section receiving signal charges generated by said photo-electric converter elements and transferring said signal charges through a vertical channel section;
- c) a horizontal charge transfer section receiving said signal charges transferred from said vertical channel section and transferring said signal charges through a horizontal channel section having:
- 1) a first region of one conductivity type having a first impurity concentration and serving as a charge storage region, and
- 2) a second region of said one conductivity type having a second impurity concentration and serving as a charge barrier region; and
- d) a coupling region including a portion of said horizontal channel section extended towards said vertical channel section with a width substantially equal to the width of said vertical channel section to provide electrical coupling therebetween, said coupling region having a potential gradient continuously changing from said vertical channel section towards said horizontal channel section generated by varying the

effective channel width associated with said first region in a complementing proportion to the effective channel width associated with said second region, while maintaining said width of said coupling region constant.

5,589,699

ELECTRICALLY ERASABLE PROGRAMMABLE NON-VOLATILE SEMICONDUCTOR MEMORY DEVICE HAVING SELECT GATES AND SMALL NUMBER OF CONTACT HOLES

Hitoshi Araki, Yokohama, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Dec. 20, 1994, Ser. No. 359,660

Claims priority, application Japan, Dec. 27, 1993, 5-348512;
Jun. 30, 1994, 6-150242; Nov. 11, 1994, 6-277470

Int. Cl.⁶ H01L 29/788

U.S. Cl. 257—316

52 Claims



1. A non-volatile semiconductor memory device comprising: memory cell means for storing data, which has a source/drain region formed in a surface portion of a semiconductor substrate, a first control gate electrode formed on the source/drain region, and a first charge-accumulating region formed between the first control gate electrode and the semiconductor substrate, the first charge-accumulating region being charged with electricity in a writing mode as a result of a difference in potential between the first control gate electrode and the semiconductor substrate and between the first control gate electrode and the source/drain region, thereby setting the threshold voltage of the memory cell means to a value higher than a voltage applied to the first control gate electrode in a reading mode, the first charge-accumulating region being discharged of electricity in an erasing mode as a result of a difference in potential reverse to that in the writing mode, thereby setting the threshold voltage of the memory cell means to a value lower than the voltage applied to the first control gate electrode in the reading mode; and select transistor means having a second control gate electrode located at an end portion of the memory cell means, and a second charge-accumulating region similar to the first charge-accumulating region and located between the second control gate electrode and the semiconductor substrate, the select transistor means having a positive threshold voltage at least in the reading mode and the writing mode for the memory cell means.

5,589,700

SEMICONDUCTOR NONVOLATILE MEMORY

Hironobu Nakao, Kyoto, Japan, assignor to Rohm Co., Ltd., Japan

Continuation of Ser. No. 844,803, Mar. 2, 1992, abandoned.

This application Feb. 28, 1994, Ser. No. 203,698


Claims priority, application Japan, Aug. 20, 1991, 3-208058

Int. Cl.⁶ H01L 29/792

U.S. Cl. 257—325

3 Claims

1. A semiconductor device including a nonvolatile memory, comprising:



- a first conductivity type semiconductor region;
- a pair of second conductivity type diffusion regions formed within said first conductivity type semiconductor region;
- an insulating layer formed on said first conductivity type semiconductor region;
- a charge trapping layer comprising a plurality of silicon nitride regions formed within a silicon dioxide layer, said charge trapping layer formed on said insulating layer, and
- a control electrode formed on said charge trapping layer.

5,589,701

PROCESS FOR REALIZING P-CHANNEL MOS TRANSISTORS HAVING A LOW THRESHOLD VOLTAGE IN SEMICONDUCTOR INTEGRATED CIRCUITS FOR ANALOG APPLICATIONS


Livio Baldi, Milan, Italy, assignor to SGS-Thomson Microelectronics S.r.l., Agrate Brianza, Italy

Division of Ser. No. 282,408, Jul. 28, 1994, Pat. No. 5,534,448.
This application Jun. 7, 1995, Ser. No. 486,747

Int. Cl.⁶ H01L 29/76

U.S. Cl. 257—369

9 Claims



1. A CMOS integrated circuit for analog applications comprising:
- a substrate of semiconductor material having a uniform first doping level and a uniform first work function;
- a plurality of N-channel transistors;
- a plurality of first P-channel transistors having a first threshold voltage, said first P-channel transistors having gate electrodes comprised solely of polysilicon, the polysilicon having a second doping level and a second work function, the second doping level being less than the first doping level, the second work function being less than the first work function, such that said first P-channel transistors have a positive flat band voltage; and
- a plurality of second P-channel transistors having gate electrodes comprised solely of polysilicon having a different doping level than the second doping level of the first plurality of P-channel transistors, the second P-channel transistors having a second threshold voltage, the second threshold voltage having an absolute value higher than the first threshold voltage.

5,589,702

HIGH VALUE GATE LEAKAGE RESISTOR

Martin J. Alter, Los Altos, Calif., assignor to Micrel Incorporated, San Jose, Calif.


Division of Ser. No. 180,579, Jan. 12, 1994, Pat. No. 5,439,841.

This application Apr. 10, 1995, Ser. No. 418,748

Int. Cl.⁶ H01L 29/00

U.S. Cl. 257—379

22 Claims



1. A device comprising:

- a semiconductor substrate;
- an MOS transistor having a gate, a source region, and a drain region, said source region and said drain region formed in said semiconductor substrate to a first diffusion depth and having a first dopant concentration; and
- a high value gate leakage resistor for providing a specified resistance between a first node and a second node, said resistor formed proximate to said MOS transistor on said substrate, said resistor having a first end for connection to said gate and a second end for connection to a current sink,

wherein said resistor comprises a diffusion region formed in said substrate by implanting dopants into said substrate through an oxide portion less than a first thickness, said oxide portion less than said first thickness formed by ends of two opposing bird's beaks which have merged together, oxide portions greater than said first thickness blocking said dopants from implanting into said substrate, wherein the resistivity of said resistor is controlled by controlling the extent of merging of said bird's beaks.

5,589,703

EDGE DIE BOND SEMICONDUCTOR PACKAGE


Ira E. Baskett, Tempe, Ariz., assignor to Motorola, Inc., Schaumburg, Ill.

Filed Apr. 28, 1995, Ser. No. 431,217

Int. Cl.⁶ H01L 29/82

U.S. Cl. 257—419

11 Claims



9. An edge die bond semiconductor package comprising:

- a semiconductor die having an active major surface and a mounting edge substantially orthogonal to the active surface, the semiconductor die including a sensor diaphragm positioned in the major surface and a grid surrounding the diaphragm and defining a depression in the semiconductor die;

a constraint die having a cooperating surface formed to mate with the grid of the semiconductor die and a mounting edge substantially orthogonal to the cooperating surface, the semiconductor die and the constraint die being formed of materials having substantially similar temperature coefficients of expansion;

the semiconductor die and the constraint die being chemically bonded together so that a sensor cavity is defined between the diaphragm and the constraint die with the diaphragm defining one wall of the sensor cavity, the semiconductor die and the constraint die being further bonded with the mounting edge of the semiconductor die and the mounting edge of the constraint die forming a single mounting edge substantially orthogonal to the diaphragm;

a base having a mounting surface; and
material affixing the single mounting edge of the semiconductor die and the constraint die to the mounting surface of the base.

5,589,704

ARTICLE COMPRISING A SI-BASED PHOTODETECTOR


Barry F. Levine, Livingston, N.J., assignor to Lucent Technologies Inc., Murray Hill, N.J.

Filed Jan. 27, 1995, Ser. No. 379,422

Int. Cl.⁶ H01L 31/0232

U.S. Cl. 257—436

8 Claims



1. An article comprising a Si-based photodetector comprising
 - a) a crystalline Si layer disposed on a dielectric material, said Si layer having a major surface; and
 - b) spaced apart first and second contacts to the Si layer; and the article also comprises
 - c) a voltage source for providing a bias voltage between said first and second contacts, and a receiver that is responsive to a current between said first and second contacts, said current being responsive to electromagnetic radiation of wavelength λ incident on said major surface;

CHARACTERIZED IN THAT

- d) the thickness t of said crystalline Si layer is less than an absorption length $0.5 \alpha^{-1}$ in crystalline Si of said radiation of wavelength λ , and is in the range 1.5–5 μm ;
- e) said dielectric material has a refractive index that is less than a refractive index of crystalline Si; and
- f) at least a portion of said major surface is textured, such that said radiation of wavelength λ is transmitted through said portion of the surface in substantially random directions, wherein associated with said at least portion of the surface is an average feature size, said average feature size being in the range $0.2(\lambda/2n)$ to $5(\lambda/2n)$, where n is the refractive index of crystalline Si for radiation of wavelength λ .

5,589,705

REAL-TIME SEMICONDUCTOR RADIATION DETECTOR

Yutaka Saito, and Yoshikazu Kojima, both of Tokyo, Japan, assignors to Seiko Instruments Inc., Japan

Continuation of Ser. No. 36,058, Mar. 23, 1993, abandoned.


This application Mar. 17, 1995, Ser. No. 417,141

Claims priority, application Japan, Mar. 24, 1992, 4-066364; Mar. 5, 1993, 5-045439

Int. Cl.⁶ H01L 31/00

U.S. Cl. 257—459

11 Claims



1. A semiconductor radiation detector comprising: a semiconductor substrate; radiation detecting means formed on the semiconductor substrate for detecting incident radiation and producing a corresponding electrical output signal; an output electrode connected to the radiation detecting means; and a capacitor electrically connected to the radiation detecting means and the output electrode; wherein the radiation detecting means comprises a PN junction formed in a first surface of the semiconductor substrate and the output electrode is formed of a material selected from the group consisting of poly-si and a metal silicide; and wherein the capacitor comprises a plurality of electrodes and a plurality of insulating layers.

5,589,706

FUSE LINK STRUCTURES THROUGH THE ADDITION OF DUMMY STRUCTURES

Alexander Miltwsky, Poughkeepsie, N.Y., and James G. Ryan, Newtown, Conn., assignors to International Business Machines Corp., Armonk, N.Y.

Filed May 31, 1995, Ser. No. 455,811

Int. Cl.⁶ H01L 27/10

U.S. Cl. 257—529

8 Claims



1. A fuse bank for an integrated circuit comprising: an array of fuse links; and an interstitial array of dummy structures in close proximity of the fuse links so as to promote forming vertical sidewalls and constant height of the fuse links, whereby the fuse links may be reliably and reproducibly cut by laser.

5,589,707

MULTI-SURFACED CAPACITOR FOR STORING MORE CHARGE PER HORIZONTAL CHIP AREA

John E. Cronin, Milton, Vt., assignor to International Business Machines Corporation, Armonk, N.Y.


Filed Nov. 7, 1994, Ser. No. 335,012

Int. Cl.⁶ H01L 27/108; 29/00

U.S. Cl. 257—532

2 Claims

1. A semiconductor chip comprising: a semiconductor substrate, first and second regions of a first conductivity type deposited therein, said regions being separated by a third region of a second conductivity type; a first elongated dielectric layer disposed on a portion of a surface of said substrate overlying a portion of said third region;



- a first, conductive, elongated capacitor plate, having a selected width and further having a pair of sidewalls of a selected height, located over said first dielectric layer on said substrate and separated from said third region in said substrate by said first dielectric layer;
- a second dielectric layer deposited along substantially the full length of a first one of said pair of sidewalls;
- a third dielectric layer deposited along substantially the full length of the other one of said pair of sidewalls;
- a fourth dielectric layer disposed over substantially the full length of said top surface; and
- a second capacitor conductive plate extending along substantially the full length of one of the dielectric layers on one of said sidewalls and in electrical contact with said first region in said substrate, wherein the first capacitor plate has a top surface that is non-planar.

5,589,708

RADIATION HARD INTEGRATED CIRCUITS WITH IMPLANTED SILICON IN GATE OXIDE LAYER, FIELD OXIDE REGION, AND INTERLEVEL DIELECTRIC LAYER

Alexander Kalnitsky, Dallas, Tex., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.


Division of Ser. No. 905,020, Jun. 26, 1992, Pat. No.

5,418,174. This application Jan. 5, 1995, Ser. No. 368,889

Int. Cl.⁶ H01L 23/552; 23/58

U.S. Cl. 257—646

3 Claims



5,589,709

LEAD FRAME CAPACITOR AND CAPACITIVELY-COUPLED ISOLATOR CIRCUIT USING SAME

Robert C. Dobkin, Monte Sereno, and Robert L. Reay, Mountain View, both of Calif., assignors to Linear Technology Inc., Milpitas, Calif.

Division of Ser. No. 985,881, Dec. 3, 1992, Pat. No. 5,444,600.


This application Mar. 8, 1995, Ser. No. 401,027

Int. Cl.⁶ H01L 23/495

U.S. Cl. 257—666

17 Claims

1. An isolator circuit comprising: a first circuit adapted to be coupled to a first ground potential;



a second circuit adapted to be coupled to a second ground potential; and
one or more capacitors coupled between the first circuit and second circuit for providing capacitively-coupled isolation therebetween, the capacitors having electrodes formed from a lead frame structure.

5,589,710

Patent Not Issued For This Number

5,589,711

SEMICONDUCTOR PACKAGE

Toshifumi Sano, Masahiro Yamada, Yoshiaki Umezawa, Yoshikatsu Okada, and Akira Natori, all of Tokyo, Japan, assignors to NEC Corporation, and Japan Aviation Electronics Industry, Limited, both of Japan


Filed Dec. 28, 1994, Ser. No. 365,502

Claims priority, application Japan, Dec. 29, 1993, 5-351496

Int. Cl.⁶ H01L 23/34; 23/552

U.S. Cl. 257-718

18 Claims



1. A multi-chip package for packaging a semiconductor device comprising a substrate having upper and lower surfaces, a primary integrated circuit chip mounted on the lower surface of said substrate, secondary integrated circuit chips mounted on a predetermined region of the upper surface of said substrate, said multi-chip package comprising:

- a heat sink having a convex section, said convex section being opposed to said primary integrated circuit chip, said heat sink being thermally connected to said primary integrated circuit chip through said convex section, said convex section having a hole at a center thereof;
- a stud member, comprising a rod section and a board section, for fixing said heat sink to said substrate with the rod section inserted in the hole and with the board section inserted between said heat sink and said substrate, the rod section having a threaded end, said stud member being fixed to said substrate by an adhesive; and
- a nut screwed to said threaded end, thereby fixing said heat sink to said substrate.


5,589,712
SEMICONDUCTOR INTEGRATED CIRCUIT DEVICE
AND A METHOD OF MANUFACTURING THE SAME
Ikue-Kawashima, Kohbe, and Katsunari Hanaoka, Ono, both of Japan, assignors to Ricoh Company, Ltd., Tokyo, Japan
Filed Dec. 2, 1994, Ser. No. 349,033

Claims priority, application Japan, Dec. 3, 1993, 5-339563;
Aug. 26, 1994, 6-225763

Int. Cl.⁶ H01L 23/48; 21/44

U.S. Cl. 257-750

14 Claims



1. A semiconductor device comprising:
a substrate formed with semiconductor elements; and
a metal wiring having a laminated structure and provided on said substrate, said metal wiring including:
a first layer A having aluminum as a main component; and
a second layer D formed on said first layer A, said second layer D having as main components titanium and nitrogen in a given ratio such that a reflectance of said second layer D is 30% or less for a given wavelength of exposing light in a range including wavelengths different from that of i-light.

5,589,713

SEMICONDUCTOR DEVICE HAVING AN IMPROVED WIRING LAYER

Sang-in Lee, and Chang-soo Park, both of Kyungki-do, Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Division of Ser. No. 8,775, Jan. 25, 1993. This application
Jun. 1, 1995, Ser. No. 456,732

Claims priority, application Rep. of Korea, Jan. 23, 1992,
92-904

Int. Cl.⁶ H01L 29/54

U.S. Cl. 257-773

22 Claims



1. A semiconductor device comprising:
a semiconductor substrate;
an insulating layer formed over said semiconductor substrate, said insulating layer having an opening formed therein, said opening exposing a portion of a surface of a layer underlying said insulating layer;
a reactive spacer formed on a sidewall of said opening, said spacer comprised of any one selected from the group consisting of Ge, Mg, Sn, In, Pb and Zn; and
a first conductive layer formed over said insulating layer, over said reactive spacer, and over said exposed surface portion of said layer underlying said insulating layer.

5,589,714
EPOXY POLYMER FILLED WITH ALUMINUM
NITRIDE-CONTAINING POLYMER AND
SEMICONDUCTOR DEVICES ENCAPSULATED WITH A
THERMOSETTING RESIN CONTAINING ALUMINUM
NITRIDE PARTICLES

Kevin E. Howard, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Continuation-in-part of Ser. No. 351,450, Dec. 8, 1994, Pat.
No. 5,508,110, which is a continuation-in-part of Ser. No.
895,496, Jun. 8, 1992, Pat. No. 5,234,712. This application
Mar. 24, 1995, Ser. No. 410,264

Int. Cl.⁶ H01L 23/29

U.S. Cl. 257-788

10 Claims

1. An encapsulated semiconductor device, comprising:
(a) a semiconductor device, which is encapsulated in
(b) a cured thermosetting resin filled with from about 1 to about 90 weight %, based on the combined weight of the resin and aluminum nitride particles, of aluminum nitride particles which have an outer layer of Al—O—N into which amorphous Si—O is incorporated, and which additionally have a layer of Si—O or Si—O—Al on the surface of said Al—O—N layer; and
(c) a plurality of conductive leads which are in electrical connection with said semiconductor device and which extend through the cured thermosetting resin.

5,589,715

METER MODULE ASSEMBLY

Keizo Nishitani, Susono, and Hiroshi Suzuki, Haibara-gun, both of Japan, assignors to Yazaki Corporation, Tokyo, Japan


Filed Mar. 27, 1995, Ser. No. 411,304

Claims priority, application Japan, Mar. 28, 1994, 6-057071

Int. Cl.⁶ H02B 1/26; H02G 3/00

U.S. Cl. 307-10.1

6 Claims



1. A meter module assembly having at least one junction box for distributing input/output signals and electric power to on-vehicle electrical components, at least one switch unit having a plurality of switches for controlling said electrical components, and an instrument board, comprising:


- a circuit board by means of which said junction box and said switch unit are electrically connected to form a control board, said junction box and said switch unit being horizontally juxtaposed in a direction perpendicular to a longitudinal axis of a vehicle with which said meter module assembly is used; and
- a panel-mounting case having a first case and a second case, said first case having said instrument board mounted upright thereon in vertical and crosswise arrangement relative to said longitudinal axis of the vehicle, said first case and second case being vertically assembled together in integral construction with said control board sandwiched between said first and second cases, said first case being provided with a hole through which said instrument board is electrically connected

with said control board when said instrument board and said first and second cases are assembled together.

5,589,716
LIGHT-GOVERNED WINDSHIELD WIPER AND
HEADLIGHT CONTROL SYSTEM WITH PROVISION
FOR MAINTAINING THE HEADLIGHTS ON WITH
INSUFFICIENT AMBIENT LIGHT
Gyles B. Dailey, 820 Dogwood Dr., New Ellenton, S.C. 29809
Filed Sep. 20, 1995, Ser. No. 531,321
Int. Cl.⁶ B60L 1/14

U.S. Cl. 307-10.8

2 Claims



1. A new and improved light-governed windshield wiper and headlight control system comprising, in combination:
a relay having a switching coil with a negative terminal thereof connected to ground and further including:
a first switching contact coupled to the headlights of the automobile and having a closed orientation when the switching coil is relaxed,
a second switching contact coupled to an ignition actuator device which supplies direct current from a power supply when closed, the second switching contact having an open orientation when the switching coil is relaxed, and
a third switching contact coupled between the headlights of an automobile and auxiliary power source which supplies direct current from said auxiliary power source, the third switching contact having an open orientation when the switching coil is relaxed;
a light-governed switching means coupled between the second switching contact of the relay and switching coil of the relay, the light-governed switching means having an open orientation when exposed to sufficient light thereby precluding current flow therebetween and further having a closed orientation when exposed to insufficient light thereby allowing continued excitation of the switching coil upon initial excitation thereof;
a single pole single throw headlight switch coupled between the first switching contact of the relay and power supply, the headlight switch having an open orientation for withholding current from the first switching contact of the relay, the headlight switch further having a closed orientation for allowing direct current to flow to the first switching contact of the relay thereby activating the headlights when switching coil is relaxed;
a double pole single throw wiper switch having a first wiper switch contact coupled between a wiper blades circuit and ignition actuator device and further comprising a second wiper switch contact coupled between the switching coil of the relay and the ignition actuator device, the wiper switch having an open orientation for withholding direct current, the wiper switch further having a closed orientation for allowing direct current to flow to the wiper blades circuit, switching coil of the relay, and second switching contact of the relay thereby activating the windshield wipers and headlights coincidentally and further exciting the switching coil hence continu-

ing activation of the headlights when the windshield wipers are deactivated and there is insufficient light.

5,589,717

COMPACT SPECTRUM ANALYZER MODULE

Chiu Chau, Woodbridge, N.J., assignor to Instruments SA, Inc., Edison, N.J.


Continuation of Ser. No. 2,597, Jan. 11, 1993, abandoned.

This application Sep. 12, 1995, Ser. No. 527,290

Int. Cl.⁶ G01J 3/28

U.S. Cl. 356—328

22 Claims



1. A compact spectrum analyzer module, comprising:
 - a) a concave diffraction grating having an optical axis and having grating grooves extending generally perpendicularly to said optical axis;
 - b) an inlet for admitting an input beam of light to be analyzed along an input path in an input direction generally transverse to said optical axis and to said grating grooves;
 - c) an input mirror oriented at an angle to said input path to reflect said input beam toward said diffraction grating, said light beam traveling from said input mirror to said diffraction grating in a plane of incidence to said diffraction grating said plane of incidence passing through said optical axis of the diffraction grating transversely of said grooves;
 - d) output mirror positioned to intercept light dispersed by said diffraction grating and reflect said dispersed light in an output direction; and
 - e) an output aperture for egress of light from said module; wherein said output direction is transverse to said plane of incidence to said diffraction grating and said input direction and said output direction is rotated about said diffraction grating optical axis through an acute angle of at least 28°, or through a right angle, to said input direction.

5,589,718

POWER LINE CONDITIONER

Noel Lee, Daly City, Calif., assignor to Monster Cable International, Ltd., Hamilton, Bermuda


Filed Apr. 14, 1995, Ser. No. 422,442

Int. Cl.⁶ H02J 1/00

U.S. Cl. 307—72

3 Claims

1. A power line conditioner comprising a housing, a plurality of outlets mounted on said housing for receiving AC plugs from a plurality of electrical components, means for connecting said housing to a source of AC power, means for distributing said AC power to each of said outlets, and means associated with said outlets for processing the AC power distributed to said outlets and therefore to the components connected to the outlets to improve the performance of the components, the processing means associated with at least one of said outlets differing from the processing means associated with at least one other outlet so that said outlets can



5,589,719

CARD OUT OF SOCKET DETECTOR FOR IC CARDS


Peter D. Fiset, 5 Upper Loudon Rd., Loudonville, N.Y. 12211

Filed Mar. 10, 1995, Ser. No. 401,778

Int. Cl.⁶ H05K 1/11

U.S. Cl. 307—131

13 Claims



1. An IC card circuit for a portable IC card selectively insertable and extractable from a host terminal unit thereby connecting and disconnecting the IC card circuit from the host terminal unit comprising,
 - a function generating circuit,
 - an internal power supply for applying a voltage to said function generating circuit to maintain the proper sequencing of states of said function generating circuit when the IC card circuit is not connected to the host terminal unit,
 - a first card detect socket for mating with a first card detect pin of the host terminal connector,
 - a second card detect socket for mating with a second card detect pin of the host terminal connector,
 - a card operating properly detector for detecting the ability of the portable IC card to function properly, responsive to the state of said internal power supply and responsive to the state of said function generating circuit;
 - a first transistor for receiving current into the base of said first transistor from the host terminal's first card detect pin,
 - a first impedance means for biasing the collector of said first transistor to said internal power supply,
 - a second transistor for receiving current into the base of said second transistor from the host terminal's second card detect pin,

- a second impedance means for biasing the collector of said second transistor to said internal power supply,
- a logic element for outputting a card insertion and extraction signal responsive to signals from the collectors of said first transistor and said second transistor,
- a power input terminal for supplying power to said internal power supply from said host terminal unit when the IC card is connected to said host terminal unit,
- a power switch connected in series between said power input terminal and said internal power supply, and
- a supply voltage detecting circuit for receiving said card insertion and extraction signal indicative of the connection with and disconnection from said host terminal unit and the voltage of said internal power supply for generating an output signal for the opening and closing of said power switch.

5,589,720

ELECTRIC MOTOR WITH COOLING DEVICE

Josef Berger, Vienna, Austria, assignor to Elin Motoren GmbH, Vienna, Austria

PCT No. PCT/AT93/00140, § 371 Date Apr. 28, 1995, § 102(e)

Date Apr. 28, 1995, PCT Pub. No. WO94/06196, PCT Pub.

Date Mar. 17, 1994


PCT Filed Sep. 9, 1993, Ser. No. 397,231

Claims priority, application Austria, Sep. 10, 1992, 1807/92

Int. Cl.⁶ H02K 9/00; 1/32

U.S. Cl. 310—61

12 Claims



1. An electric motor comprising:
 - a rotatable shaft having therewithin a longitudinally extending bore, said shaft having a first end portion and a second end portion;
 - a longitudinally extending tube positioned within said longitudinally extending bore of said shaft, a space existing between an exterior of said tube and an interior of said bore, said tube having a first end portion at the first end portion of said shaft and a second end portion at the second end portion of said shaft, said first end portion of said tube having at least one lateral bore for communicating an interior of said tube with said space between the exterior of said tube and the interior of said bore;
 - a rotor rigidly secured onto said rotatable shaft;
 - a frame, a stator secured onto said frame, said frame comprising first and second spaced-apart end members, said first end member supporting a drive-side bearing and said second end member supporting an operating-side bearing, said drive-side bearing receiving the first end portion of said shaft and said operating-side bearing receiving the second end portion of said shaft, said second end portion of said shaft having an extension extending beyond said operating-side bearing; and
 - a device, secured onto said second end member of said frame, over said extension of said second end portion of said shaft, having a passageway in communication with the interior of said tube for transferring a cooling fluid through said device into said tube at said second end portion of said shaft, along the interior of said tube, through said lateral bore in said first end portion of said tube, along said space between the exterior of said tube and the interior of said longitudinal bore of said shaft.

5,589,721

DISPLAY APPARATUS UTILIZING MAGNETIC INTERACTION


Quansheng Han, and Bruce Lahn, both of 863 Mass. Ave. #24, Cambridge, Mass. 02139

Filed Dec. 11, 1995, Ser. No. 570,501

Int. Cl.⁶ H02K 7/09; G09F 19/00

U.S. Cl. 310—90.5

18 Claims



1. A display apparatus comprising:
 - a base assembly including an anchoring point, and a first magnet disposed in spaced relation relative to the anchoring point;
 - a suspension member disposed between the anchoring point and the first magnet and including a longitudinal axis, a first end which is adjacent to the first magnet, an opposite second end, a second magnet mounted on the first end thereof, and a third magnet member radially mounted thereon;
 - means for tethering the suspension member to the anchoring point;
 - wherein the first magnet is polarized to attract the second magnet so that the first magnet is operable to magnetically support the suspension member in a suspended state where the suspension member is in spaced relation relative to the first magnet, the anchoring point and the base assembly, respectively; and
 - means for electromagnetically impelling the third magnet member when the suspension member is rotated about its longitudinal axis thereby maintaining the rotation of the suspension member.

5,589,722

SHEET COIL MOTOR AND METHOD OF FABRICATING THE SAME

Takahiro Sakaguchi, Kodaira, and Fumio Sakamoto, Machida, both of Japan, assignors to TEAC Corporation, Tokyo, Japan

Filed Apr. 14, 1994, Ser. No. 227,792

Claims priority, application Japan, Apr. 16, 1993, 5-019623


U; Apr. 16, 1993, 5-090195; Mar. 24, 1994, 6-053774

Int. Cl.⁶ H02K 3/26; 21/12; 19/26

U.S. Cl. 310—180

16 Claims

1. A sheet coil motor comprising:
 - a driving sheet coil formed by a plurality of coil units with each coil unit composed of a plurality of independent coils formed on a substrate and arranged relative to one another such that the plurality of coils in each coil unit has the shape of a sector; and
 - a rotor magnet provided opposite the driving sheet coil at a close distance,



wherein said driving sheet coil is configured such that said plurality of coil units are concentrically arranged and disposed a predetermined distance from each other.

5,589,723

DRIVING APPARATUS USING TRANSDUCER

Ryuichi Yoshida, Sakai; Yasuhiro Okamoto, Tondabayashi, and Minoru Kuwana, Osaka, all of Japan, assignors to Minolta Co., Ltd., Osaka, Japan


Filed Mar. 15, 1995, Ser. No. 404,240

Claims priority, application Japan, Mar. 29, 1994, 6-081127; Mar. 29, 1994, 6-081128; Mar. 29, 1994, 6-081129; Mar. 29, 1994, 6-081130; Apr. 26, 1994, 6-088562; Apr. 27, 1994, 6-089797; Aug. 30, 1994, 6-227396; Oct. 4, 1994, 6-240339; Nov. 21, 1994, 6-309488

Int. Cl.⁶ H01L 41/08; H02N 2/00

U.S. Cl. 310—328

19 Claims



1. A driving apparatus comprising:
 - a transducer for producing repeatable linear displacements in a predetermined direction;
 - a driving member coupled with said transducer for simultaneous displacement therewith and having a guide surface formed in the direction of displacement of said transducer;
 - a moving member having a friction member in surface-to-surface contact with the guide surface of said driving member, said moving member being movable along said guide surface; and
 - a pushing member furnished on said moving member for pushing said friction member against said guide surface.

5,589,724
PIEZOELECTRIC DEVICE AND A PACKAGE

Yuki Satoh, Neyagawa; Toshio Ishizaki, Kobe; Tsuyoshi Sakaue, Neyagawa; Koji Hashimoto, Kobe; Tohru Yamada, Katano, and Tomoki Uwano, Hirakata, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 186,566, Jan. 25, 1994, abandoned.


This application Dec. 7, 1994, Ser. No. 350,717

Claims priority, application Japan, Jan. 25, 1993, 5-010125; Mar. 30, 1993, 5-071440; Apr. 16, 1993, 5-089610; Apr. 16, 1993, 5-089611

Int. Cl.⁶ H01L 41/08

U.S. Cl. 310—348

7 Claims



1. A piezoelectric device comprising:
 - a piezoelectric plate provided with at least one electrode at almost a central portion of each face,
 - a first plate made of an ionic material having a recessed portion to cover said at least one electrode at one face to face said piezoelectric plate, and
 - a second plate made of an ionic material having a recessed portion to cover said at least one electrode at one face to face said piezoelectric plate,
 wherein each of said at least one electrode is packaged by direct bonding said piezoelectric plate with said first plate and said second plate so as to be sandwiched therebetween with no intervening adhesive or structure, and
- said at least one electrode on one face of said piezoelectric plate is led to the other face of said piezoelectric plate via at least one through-hole filled with a conductive material.

5,589,725

MONOLITHIC PRESTRESSED CERAMIC DEVICES AND METHOD FOR MAKING SAME

Gene H. Haertling, Central, S.C., assignor to Research Corporation Tech., Inc., Tucson, Ariz.


Division of Ser. No. 21,367, Feb. 23, 1993, Pat. No. 5,471,721.

This application May 5, 1995, Ser. No. 435,698

Int. Cl.⁶ H01L 41/08

U.S. Cl. 310—358

46 Claims



1. An internally asymmetrically stress biased ceramic element comprising:
 - a concave shaped ceramic element having first and second opposing surfaces;
 - said first surface being a conductive reduced layer of the ceramic material and in tension; and
 - said second surface being in compression.

5,589,726

ARC LAMP WITH EXTERNAL MAGNETIC MEANS

Ronald S. Gold, Fullerton, Calif., assignor to Hughes Aircraft Company, Los Angeles, Calif.


Continuation of Ser. No. 171,289, Dec. 21, 1993, abandoned.

This application Sep. 25, 1995, Ser. No. 533,724

Int. Cl.⁶ H01J 1/50

U.S. Cl. 313—161

14 Claims



1. An arc lamp point light source comprising:
 - a bulb for generating and emitting a light source including a first and a second electrode having a gap therebetween, the electrodes being enclosed and hermetically sealed in bulb envelope filled with an ionizing gas;
 - connector means for applying a voltage potential across the electrodes to generate an arc plasma having an arc volume and an arc centroid in the gap when electric current passes between the first and second electrodes; and
 - magnetic field means located outboard of the bulb envelope for generating at least two magnetic fields, the magnetic fields operable to produce lines of force, for converging the arc plasma toward the arc centroid, wherein said magnetic field means comprises a first magnetic field means for spherically compressing the volume of the arc plasma between the first and second electrodes, and a second magnetic field means for adjusting the magnetic field generated by the first magnetic field means.

5,589,727

ENERGY STORAGE SYSTEM

D. Clint Seward, Acton, Mass., assignor to Electron Power Systems, Acton, Mass.

Continuation-in-part of Ser. No. 841,308, Feb. 24, 1992, Pat. No. 5,175,466, which is a continuation of Ser. No. 529,783,

May 25, 1990, abandoned, which is a continuation of Ser. No. 214,904, Jun. 28, 1988, abandoned, which is a continuation of Ser. No. 914,629, Oct. 2, 1986, abandoned. This application


Dec. 24, 1992, Ser. No. 996,752

The portion of the term of this patent subsequent to Dec. 29, 2009, has been disclaimed.

Int. Cl.⁶ H05H 1/46

U.S. Cl. 313—231.31

19 Claims



1. A charged particle energy storage device comprising:
 - a vacuum tube for housing a plurality of electrons circulating within the vacuum tube;
 - a magnetic field generator for providing a magnetic field having closed magnetic field lines within the vacuum tube; and

an electron source for delivering a plurality of electrons into a predetermined path within the vacuum tube, the electrons having a substantially uniform velocity such that the predetermined path comprises a spiral about an axis that is parallel to a closed magnetic field line of the magnetic field;

a gas source for delivering a plurality of gaseous particles into the vacuum tube such that the gaseous particles interact with the electrons to form energized particles; and

a valve to control an opening in the vacuum tube such that the energized particles can be removed from the vacuum tube through the opening.

5,589,728

FIELD EMISSION DEVICE WITH LATTICE VACANCY POST-SUPPORTED GATE


Jules D. Levine, Dallas; Chi-Cheong Shen, and Robert Taylor, both of Richardson, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed May 30, 1995, Ser. No. 453,043

Int. Cl.⁶ H01J 1/02

U.S. Cl. 313—336

12 Claims



6. An electron emitter plate comprising:
 - a substrate;

a first layer of conductive material deposited on said substrate; said first layer of conductive material being patterned in a mesh structure defining a plurality of mesh spacings;

a layer of insulating material deposited on said substrate over said first layer of conductive material and said mesh spacings;

a second layer of conductive material deposited on said substrate over said layer of insulating material; said second layer of conductive material having a cluster of apertures located within each mesh spacing; the apertures of each cluster being arranged in a regular, periodic array defining a lattice having at least one internal vacancy;

a conductive microtip formed in each aperture in electrical communication with said first layer of conductive material; said insulating layer being formed with a cavity located within each mesh spacing, each cavity connecting the apertures of one of said clusters and commonly containing the microtips associated with that cluster; said insulating layer supporting said second layer of conductive material above said first layer of conductive material peripherally of each cavity; and said insulating layer forming a post under each lattice vacancy, said post supporting said second layer of conductive material above said first layer of conductive material centrally of each cavity.

5,589,729

DEFLECTION YOKE LINER WITH SUPPORT RIDGES
Jean-Philippe Descombes, Premières, and Philippe Marotte, Genlis, both of France, assignors to Thomson Tubes & Displays, S.A., France


Filed Jun. 5, 1995, Ser. No. 464,431

Claims priority, application European Pat. Off., Jul. 1, 1994, 94401503

Int. Cl.⁶ H01J 29/82; 29/76

U.S. Cl. 313—440

9 Claims



1. A deflection yoke for a cathode ray tube, comprising: a deflection coil; and a separator for supporting said deflection coil, said separator having a plurality of support ridges for supporting said deflection coil that bears against said support ridges in a manner to space said deflection coil from a surface of said separator, said supporting ridges extending in a longitudinal direction between a front portion and a rear portion of the separator, a given one of said supporting ridges being placed at an intersection of a surface of said separator with a radial plane.

5,589,730

MOTOR VEHICLE LIGHTING/INDICATING APPARATUS USING LUMINESCENT DISCHARGE

Marc Brassier, Vincennes; Jean-Claude Gasquet, Saint-Clement; Daniel Segaud, Paris, and Bernard Mauroy, Roissy en Brie, all of France, assignors to Valeo Vision, Bohigny Cedex, France

Filed Oct. 12, 1993, Ser. No. 135,693


Claims priority, application France, Oct. 12, 1992, 92 12136

Int. Cl.⁶ H01J 61/30

U.S. Cl. 313—493

23 Claims

1. A lighting or indicating apparatus for a vehicle comprising a light transmitting element and a base element disposed behind said light transmitting element, wherein the light transmitting element constitutes an outer wall having at least one surface which is at least partly curved, the base element constitutes an inner wall, said outer and inner walls together define a thin envelope defining at least one closed cavity being gastight for containing gas under low pressure, and the apparatus further includes at least two electrodes situated in the at least one closed cavity, and means connected with the electrodes for applying a voltage for starting and maintaining a luminescent gas discharge in said cavity, said apparatus defining at



least one zone having at least two superimposed cavities each containing a gas under low pressure.

5,589,731

INTERNAL SUPPORT STRUCTURE FOR FLAT PANEL DEVICE



Theodore S. Fahlen, San Jose; Robert M. Duboc, Jr., Menlo Park, and Paul A. Lovoi, Saratoga, all of Calif., assignors to Silicon Video Corporation, San Jose, Calif.

Continuation-in-part of Ser. No. 867,044, Apr. 10, 1992, Pat. No. 5,424,605. This application Feb. 1, 1993, Ser. No. 12,542

Int. Cl.⁶ H01J 29/04

U.S. Cl. 313—495

74 Claims



1. A flat panel device comprising: a faceplate; a backplate connected to the faceplate to form a sealed enclosure; means for emitting light from the flat panel device; and a spacer situated within the enclosure and supporting the backplate and the faceplate against forces acting in a direction toward the enclosure, wherein the spacer is made of ceramic reinforced glass or metal coated with an electrically insulating layer.

5,589,732

COLOR THIN FILM ELECTROLUMINESCENCE PANEL
Katsushi Okibayashi, Sakurai; Takashi Ogura, Nara, and Masaru Yoshida, Nara-ken, all of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 4,067, Jan. 13, 1993, abandoned.


This application Jan. 24, 1995, Ser. No. 378,869

Claims priority, application Japan, Jan. 18, 1992, 4-006957

Int. Cl.⁶ H01J 1/62

U.S. Cl. 313—506

10 Claims



1. A color film electroluminescence panel, comprising: an electroluminescence device; buffer means, provided on the electroluminescence device, including silicon resin as a main ingredient thereof and having a thickness of at least 2 μ m for reducing the possibility of dielectric breakdown of the color film electroluminescence panel by creating a buffer between the electroluminescence device and a color filter; and the color filter, laminated via the dielectric breakdown reduction means onto the electroluminescence device.

5,589,733

ELECTROLUMINESCENT ELEMENT INCLUDING A DIELECTRIC FILM OF TANTALUM OXIDE AND AN OXIDE OF EITHER INDIUM, TIN, OR ZINC

Koji Noda, Nagoya; Hisayoshi Fujikawa; Katsuji Yamashita, both of Seto, and Yasunori Taga, Nagoya, all of Japan, assignors to Kabushiki Kaisha Toyota Chuo Kenkyusbo, Aichi-ken, Japan


Filed Feb. 17, 1995, Ser. No. 390,567

Claims priority, application Japan, Feb. 17, 1994, 6-020430

Int. Cl.⁶ H01J 1/70

U.S. Cl. 313—509

16 Claims



1. An electroluminescent element comprising a dielectric film, said dielectric film comprising: tantalum oxide; and at least one metal oxide selected from the group consisting of indium oxide and tin oxide, being incorporated in said tantalum oxide, said dielectric film being formed as a thin film, and the content of metal atoms in said at least one metal oxide being 55 atomic % or less with respect to the total content of metal atoms in said tantalum oxide and said at least one metal oxide.

5,589,734

ELECTRIC LAMP HAVING A FLUORESCENCE-SUPPRESSED QUARTZ-GLASS ENVELOPE, AND QUARTZ GLASS THEREFOR

Manfred Deisenhofer, Altenmuenster; Dieter Meiss, Tuebingen, and Ekkehard Messner, Augsburg, all of Germany, assignors to Patent-Treuhand-Gesellschaft F. Elektrische Gluehlampen mbH, Munich, Germany


Filed May 11, 1995, Ser. No. 439,472

Claims priority, application Germany, May 25, 1994, 44 18 198.1

Int. Cl.⁶ H01J 17/16; 61/30

U.S. Cl. 313—636

16 Claims



1. A lamp (12) having a lamp bulb or vessel (10) of quartz glass, and a light source (11) which, in operation, emits radiation in the ultraviolet (UV) spectral range, located in said quartz glass bulb or vessel (10), wherein the quartz glass of the bulb or vessel includes a first doping material comprising cerium, absorbing UV radiation, and being stimulated to fluorescence within the visible spectrum by said UV radiation; and wherein the quartz glass of the bulb or vessel further includes a further doping material comprising praseodymium or a praseodymium compound, suppressing, or at least substantially attenuating said fluorescence of the quartz glass of the bulb or vessel (10).

5,589,735

EMISSION DEVICE WITH A CADMIUM LAMP

Akiyasu Yamaguchi; Yukio Yasuda; Tsuneo Okanuma; Tatsushi Igarashi; Hiromitsu Matsuno, all of Hyogo-ken, and Tatsumi Hiramoto, Tokyo, all of Japan, assignors to Ushiodenki Kabushiki Kaisha, Japan


Filed Jul. 25, 1995, Ser. No. 506,829

Claims priority, application Japan, Jul. 29, 1994, 6-196206

Int. Cl.⁶ H01J 7/08; 61/18

U.S. Cl. 313—638

2 Claims



1. An emission device comprising a cadmium lamp having a fluorescent tube within which a cathode and an anode are spaced apart with respect to one another and a buffer gas for easier initiation of luminous operation and metallic cadmium in an amount per unit volume of the fluorescent tube of 1×10^{-4} g/cm³ to 3×10^{-3} g/cm³ are encapsulated, and a power source device for supplying electrical input between the cathode and the anode in an electrical input range from 0.5 kW to 5.0 kW and in accordance with the relationship:

$$6.03+2.79 W \leq r \leq 40$$

where the electrical input of the power source device into the cadmium lamp in steady-state luminous operation is designated W (kW) and a maximum inside radius of the fluorescent tube of the cadmium lamp is designated r (mm).

5,589,736

FREQUENCY MULTIPLIER INCLUDING GRID HAVING PLURAL SEGMENTS


Erling L. Lien, Los Altos, and Arthur Karp, Palo Alto, both of Calif., assignors to Communications and Power Industries, Inc., Palo Alto, Calif.

Division of Ser. No. 508,442, Apr. 13, 1990, Pat. No. 5,317,233. This application May 4, 1994, Ser. No. 237,731

Int. Cl.⁶ H01J 25/02

U.S. Cl. 315-5.43

14 Claims



1. Apparatus for multiplying the frequency of an AC signal by a factor N , where N is an integer greater than one, comprising an electron tube including a cathode for emitting an electron beam, a grid including N segments in proximity to the cathode and positioned to be responsive to the beam emitted by the cathode, the grid being electrically biased and electrically coupled to the signal for causing the beam to be configured as N groups of electron bunches during each cycle of the signal so that each of the segments accelerates one group of said N groups of electron bunches for a duration of about $1/N$ th of each cycle of the signal, different groups of said N groups of electron bunches associated with the different segments being accelerated at phases displaced from each other during each cycle of the signal, and means responsive to the N groups of bunches for deriving an output signal having a frequency N times that of the signal.

5,589,737

PLASMA PROCESSOR FOR LARGE WORKPIECES

Michael Barnes, San Francisco; Neil Benjamin, E.P.A.; John Holland, Santa Clara; Richard Beer, Sunnyvale, and Robert Veltrop, Saratoga, all of Calif., assignors to LAM Research Corporation, Fremont, Calif.


Filed Dec. 6, 1994, Ser. No. 354,122

Int. Cl.⁶ H01J 7/24

U.S. Cl. 315-111.21

36 Claims

1. A device for treating a workpiece with a plasma comprising a vacuum chamber in which the workpiece is adapted to be mounted, means for introducing into the chamber a gas which can be converted into the plasma for treating the workpiece, means for



converting the gas into the plasma including an electric source for producing an r.f. field originating outside of the chamber, plural individually supported dielectric windows on an exterior surface of the chamber positioned to couple the r.f. field to the gas so the field coupled through the windows excites the plasma, the windows having a thickness substantially less than the thickness of a single window having the same combined area as the plural windows to withstand the differential pressure between the interior and exterior of the chamber.

5,589,738

FIELD EMISSION TYPE DISPLAY DEVICE

Koji Onodaka; Katsuya Hiraga; Yoichi Kobori; Hiroshi Sakurada; Teruo Watanabe, and Shigeo Itoh, all of Mobara, Japan, assignors to Futaba Denshi Kogyo Kabushiki Kaisha, Mobara, Japan


Continuation of Ser. No. 359,827, Dec. 20, 1994. This application Dec. 22, 1994, Ser. No. 361,582

Claims priority, application Japan, Dec. 20, 1993, 5-344482; Dec. 22, 1993, 5-345610; Dec. 22, 1993, 5-345612

Int. Cl.⁶ G09G 3/10

U.S. Cl. 315-169.1

7 Claims



1. A field emission type display device having a plurality of field emission cathode elements each including at least cathode electrodes, control electrodes and focus electrodes incorporated therein, comprising: image cell sections each including a first field emission cathode element which forms one image cell so as to emit electron to an anode electrode; and data holding sections each arranged for each of said image cell sections and formed by a second field emission cathode element so as to permit electrons to be emitted from said cathode electrodes to said focus electrodes by field emission in response to application of a voltage to said control electrodes;

said control electrodes of said field emission cathode element of each of said image cell sections being fed with data held in each of said data holding sections.

5,589,739

HYBRID BALLAST FOR HIGH PRESSURE DISCHARGE LAMP

Hendrikus M. W. Goossens, Oss, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Aug. 18, 1995, Ser. No. 516,806

Claims priority, application European Pat. Off., Aug. 24, 1994, 94202427

Int. Cl.⁶ H05B 37/00

U.S. Cl. 315-176

20 Claims



1. A circuit arrangement for operating a discharge lamp, comprising: input terminals for connection to a supply voltage source, means coupled to the input terminals for generating a low-frequency alternating current from a supply voltage delivered by the supply voltage source, means coupled to the input terminals for generating from the supply voltage a further current which is superimposed on the low-frequency alternating current, and means for supplying said low-frequency alternating current and said superimposed further current to the discharge lamp such that the further current has the same polarity as the alternating current.

5,589,740

SEMICONDUCTOR-CONTROLLED OPERATING CIRCUIT FOR ONE OR MORE LOW-PRESSURE DISCHARGE LAMPS, TYPICALLY FLUORESCENT LAMPS

Bernd Rudolph, and Alwin Vesper, both of Munich, Germany, assignors to Patent-Treuhand-Gesellschaft F. Elektrische Gluehlampen mbH, Munich, Germany


Filed Jun. 27, 1995, Ser. No. 495,803

Claims priority, application Germany, Jul. 21, 1994, 44 25 859.3

Int. Cl.⁶ H05B 37/02

U.S. Cl. 315-291

16 Claims



1. Semiconductor-controlled operating circuit for at least one low-pressure discharge lamp (LP1, LP2; LP; LP*), in which said at

least one lamp has heatable lamp electrodes (E1, E2, E3, E4; E1', E2', E1'', E2''), comprising an inverter (Q1, Q2, A; Q1', Q2', A'; Q1'', Q2'', A'') adapted to be coupled to a source of direct-current energy, and including an inverter control circuit (A, A', A''); a resonance circuit coupled to the inverter (Q1, Q2, A; Q1', Q2', A'; Q1'', Q2'', A'') and including at least one resonance inductance (L, L', L'') and a resonance capacitance (C2, C2', C2''); at least one heater circuit coupled to the heatable electrodes (E1, E2, E3, E4; E1', E2'; E1'', E2'') of the at least one low-pressure lamp for preheating the electrodes thereof; and a semiconductor switch (Q3, Q3', Q3'') having its main switching path (drain-source) connected into the heater circuit and, in dependence on the switched state of said semiconductor switch, switching the heating circuit between a low-resistance and a high-resistance state, said operating circuit further comprising, in accordance with the invention, an impedance element (Z, Z', Z'') connected in at least one of the at least one heater circuit, and in series with the main switching path of the semiconductor switch (Q3, Q3', Q3''); and a control connection between said impedance element (Z, Z', Z'') and a control terminal of the semiconductor switch (Q3, Q3', Q3'') for controlling said semiconductor switch in accordance with the voltage drop across the combination of the impedance element (Z, Z', Z'') and the main switching path of the semiconductor switch, said impedance element (Z, Z', Z'') and main switching path combination providing a voltage drop which, when the semiconductor switch is in low-resistance state, is sensed and coupled to the control terminal of the semiconductor switch to control said semiconductor switch (Q3, Q3', Q3'') into low-resistance state.

5,589,741

SYSTEM FOR CREATING NATURALISTIC ILLUMINATION CYCLES


Michael Terman; Stephen Fairhurst, both of New York, N.Y.; Philip Hughes, Lake Hopatcong, N.J., and Joel Levitt, Brooklyn, N.Y., assignors to Research Foundation For Mental Hygiene, Inc., Albany, N.Y., and Medic-Light Inc., Lake Hopatcong, N.J.

Continuation-in-part of Ser. No. 52,044, Apr. 22, 1993, abandoned. This application Apr. 19, 1994, Ser. No. 229,533

Int. Cl.⁶ H05B 37/02

U.S. Cl. 315-360

18 Claims



1. A naturalistic illumination system for a user at a location comprising: a light source for providing illumination of variable intensity above a non-zero value to said user location; means including a computer having an input device for producing a variable signal to control a cycle of variable intensity illumination level output of said light source to correspond to the progressive variation in light level intensity above a non-zero value over a selected time of day period at a selected geographical location as selected from said input device, said signal producing means operating on a daily basis to produce the variable intensity illumination cycle for the same

period of time and including means for progressively shifting the time of the start of the production of the variable intensity illumination cycle for said period of time each day over a period of successive days relative to the normal time of start of the production of the variable intensity illumination cycle during said period of successive days at said selected geographical location.

5,589,742

DISCHARGING LAMP LIGHTING APPARATUS HAVING OPTIMAL LIGHTING CONTROL

Hiroyuki Ueda, Hyogo, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 47,484, Apr. 19, 1993, abandoned.


This application Apr. 25, 1995, Ser. No. 428,618

Claims priority, application Japan, Apr. 23, 1992, 4-129365; Sep. 22, 1992, 4-276791

Int. Cl.⁶ H05B 37/02

U.S. Cl. 315—307

24 Claims



1. A discharging lamp lighting apparatus for updating a desired voltage value to be applied to a discharging lamp when the discharging lamp is lighted at a rated power, each time the discharge light is lighted, comprising:
power supplying means for supplying power for said discharging lamp;
dielectric breakdown detecting means for detecting dielectric breakdown of said discharging lamp;
voltage detecting means for detecting voltage applied to said discharging lamp;
stable voltage storing means for storing the desired voltage value when said discharging lamp is stabilized; and
control means for providing said power supplying means with an instruction defining said desired voltage value previously stored in said stable voltage storing means as a target value when said dielectric breakdown detecting means detects occurrence of said dielectric breakdown of said discharging lamp, damping current flowing through said discharging lamp such that said voltage of said discharging lamp becomes said target value previously stored in said stable voltage storing means when power consumption of said discharging lamp becomes the rated power, and detecting voltage applied to said discharging lamp by said voltage detecting means, when said discharging lamp is stabilized, to update said desired voltage value stored in said stable voltage storing means.

5,589,743

INTEGRATED CRANKING INVERTER AND BOOST CONVERTER FOR A SERIES HYBRID DRIVE SYSTEM

Robert D. King, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.


Filed Mar. 3, 1995, Ser. No. 398,266

Int. Cl.⁶ B60L 11/08

U.S. Cl. 318—139

17 Claims

1. An electric continuously variable drive system, comprising:
an ac motor;



an alternator for supplying electrical power to the ac motor via a rectifier and a drive inverter;
a heat engine for driving the alternator;
an energy storage device;
a combination cranking inverter and boost converter, the combination coupled in series between the alternator and the energy storage device and coupled substantially in parallel with the rectifier in a series hybrid drive.

5,589,744

SLEW RATE CONTROL CIRCUIT FOR A LOWSIDE DRIVER OF A DC MOTOR


Massimiliano Brambilla, San Jose, Calif., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Filed Jul. 13, 1995, Ser. No. 502,124

Int. Cl.⁶ H02P 6/02

U.S. Cl. 318—254

20 Claims



1. A driver circuit for a polyphase DC motor, comprising:
an error amplifier, for generating at an output drive signal responsive to a command input signal and to a feedback signal;
a plurality of coil drive circuits, each corresponding to a coil of the motor, each coil drive circuit comprising:
a driver transistor having a conduction path connected to the corresponding coil, and having a control electrode;
a buffer amplifier having an input, and having an output coupled to the control electrode of the driver transistor;
a capacitor coupled between the input of the buffer amplifier and the conduction path of the driver transistor;
a first current source connected to the input of the buffer amplifier, for conducting a first current;
a switched current source, having a control electrode for receiving a commutation signal, for conducting a second current;
a switched transistor having a current path between the output of the error amplifier and the input of the buffer amplifier, the switched transistor having a control element,
an operational amplifier having a first input connected to the output of the error amplifier, having a second input connected to the input of the buffer amplifier, and having an output, and
a flip-flop having a first input connected to the output

of the operational amplifier, having a second input for receiving the commutation signal, and having an output connected to the control element of the switched transistor.

5,589,745

DRIVE CIRCUIT FOR A BRUSHLESS DIRECT-CURRENT MOTOR

Helmut Hans, St. Georgen, and Mojtaba Moinl, Königfeld, both of Germany, assignors to Papst Licensing GmbH, Spaichingen, Germany


Division of Ser. No. 292,693, Aug. 18, 1994, which is a continuation of Ser. No. 76,720, Jun. 14, 1993, Pat. No. 5,343,129, which is a continuation of Ser. No. 932,737, Aug. 25, 1992, Pat. No. 5,220,258. This application Jun. 7, 1995, Ser. No. 473,930

Claims priority, application Germany, Jun. 18, 1990, 40 19 338.1

Int. Cl.⁶ H02P 6/20

U.S. Cl. 318—431

8 Claims



1. A restart circuit for a DC motor supplied with trigger pulses of a predetermined minimal rate, the restart circuit having an output signal of one predetermined voltage level in case the trigger pulses have a sufficient rate or frequency and another predetermined voltage level in case the trigger pulses have less than a predetermined frequency, the restart circuit comprising: a timing circuit coupling current to the DC motor; a second circuit comprising a capacitor, means for charging the capacitor, means for discharging the capacitor, including means for starting the discharging of the capacitor, and means for decoupling the charging means from the discharging means; and amplifying means coupled to the second circuit for producing the output signal.

5,589,746

BRUSHLESS MOTOR SPEED CONTROL ARRANGEMENT HAVING DERIVED COMMON MODE SUPPLY SIGNAL COMPONENT


Martyn A. Lewis, Pacific Palisades, Calif., assignor to Seagate Technology, Inc., Scotts Valley, Calif.

Filed Nov. 10, 1994, Ser. No. 336,981

Int. Cl.⁶ H02P 7/00

U.S. Cl. 318—439

9 Claims



1. A method of increasing the efficiency of a multiphase motor having a plurality of phase windings comprising the steps of:

- obtaining the voltage amplitude for each phase of said motor;
- determining the smallest voltage amplitude of the motor phase windings;
- generating a common mode voltage equal to one-half the absolute value of said smallest voltage amplitude;
- summing said common mode voltage with said voltages from each phase of said motor thereby creating a modified control voltage; and
- commutating said motor with said modified control voltage.

5,589,747

LIGHT AND MOTION GOVERNED GARAGE DOOR OPENER LAMP


Michael C. Utke, 3204 - 31st St., Lubbock, Tex. 79410

Filed Jul. 6, 1995, Ser. No. 498,626

Int. Cl.⁶ E05F 15/20

U.S. Cl. 318—468

4 Claims



1. A new and improved sensor actuated garage door opener light for sensing the local presence of a human form and actuating an illumination system when there is insufficient light comprising, in combination:

an electrically powered garage door opening and closing system including a garage door; a housing; a plurality of lamps; a transformer coupled to a conventional power receptacle and adapted to supply an acceptable amount of current to the system; a security switch coupled to the transformer with an open orientation for precluding operation of the system and a closed orientation for allowing normal operation thereof; a receiver switch coupled in series with the security switch and adapted to allow transmission of current upon receipt of a radio signal; a manual switch coupled in series with the receiver switch and adapted to allow transmission of current upon the manual activation thereof; an upper limit switch coupled in series with the manual switch and adapted to allow transmission of current when the garage door is open; a lower limit switch coupled in series with the manual switch and adapted to allow transmission of current when the garage door is closed; an obstruction switch coupled in series with the manual switch and adapted to allow transmission of current when the garage door is obstructed; a first relay that transmits a first electric signal upon the activation thereof; a second relay coupled to an upward motor to effect opening of the garage door upon the activation thereof; a third relay coupled to a downward motor to effect closing of the garage door upon the activation thereof; an integrated circuit coupled between the upper limit switch, lower limit switch, and obstruction switch and the first relay, second relay, and third relay, the integrated circuit adapted to activate the first relay, second relay, and third relays upon the receipt of current via the upper limit switch, lower limit switch, and obstruction switch thereby effecting normal operation of the garage door system; and

a sensor module including:

- a sensor housing having a window that removes light at wavelengths not included in the infrared domain,
- a plurality of passive monostatic infrared sensor elements disposed within the housing at a location near the window, the sensor elements capable of detecting the presence of

one or more humans within a sensing range and producing a second electrical signal whenever one or more humans are detected.

a light sensor switch coupled to the motion sensor element and further coupled to the first relay via a relay control line, the light sensor switch having an open orientation when exposed to sufficient light for precluding the transmission of the first and second electric signals, the light sensor switch further having a closed orientation when exposed to insufficient light for allowing the transmission thereof, temporal delay circuitry coupled to the light sensor switch and comprising an input power control line coupled to the power receptacle, an input neutral control line, and an output power control line coupled to the lamps of the garage door system, the temporal delay circuitry adapted to allow transmission of current between the input power control line and output power control line upon the receipt of the first or second electric signal thereby allowing independent actuation of the lamps upon the detection of humans or activation of the garage door system and precluding said actuation upon exposure to sufficient light, the temporal delay circuitry further adapted to remain activated for a predetermined amount of time despite the absence of motion, and

a rodlike member connected to the garage door system with a pivotal fulcrum wherein pivoting of the sensor housing is substantially in a vertical plane with the sensor element disposed in a first substantially horizontal direction and with the sensor element repositionable at any angle from the first substantially horizontal direction through a nadir passing through a pivotal axis and to a second substantially horizontal direction, and wherein rotation of the rodlike member is substantially within a horizontal plane positioned about a substantially vertical axis passing through the pivotal axis and with such rotation occurring through angles somewhat less than three hundred and sixty degrees, the rodlike member having an axially aligned conduit formed therein for containment of the input and output control lines.

5,589,748

POSITION CONTROL SYSTEM AND POSITION CONTROL METHOD THEREOF


Tsutomu Kazama, and Mitsuyasu Kachi, both of Nagoya, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Mar. 10, 1994, Ser. No. 208,480

Claims priority, application Japan, Mar. 10, 1993, 5-049473
Int. Cl. G06F 15/46

U.S. Cl. 318—560

11 Claims



1. A position control system for feeding back position information detected by position detection means for detecting the position of a movable part, said position control system having first and second control loops coupled together to form a second order system position control loop, a transfer function of said second order system position control loop being defined by the equation:

$$G(s) = \frac{1}{(1 + \frac{1}{2kp} s)^2}$$

where S=a Laplace transform operator; and
kp=a first order loop gain, wherein 4 kp is equal to a second order loop gain.

5,589,749

CLOSED LOOP CONTROL SYSTEM AND METHOD USING BACK EMF ESTIMATOR


Dale D. Davidson, Glendale, and Hamid R. Sadehpour, Phoenix, both of Ariz., assignors to Honeywell Inc., Minneapolis, Minn.

Filed Aug. 31, 1994, Ser. No. 298,726

Int. Cl. G05B 9/03

U.S. Cl. 318—564

25 Claims



1. A feedback control system for controlling an actuator in response to a command signal, said control system comprising:

- a first input for receiving said command signal;
- a second input for receiving a current signal indicative of the current through said actuator;
- a third input for receiving a voltage signal indicative of the voltage across said actuator;
- a fourth input for receiving a position signal indicative of the position of said actuator;
- a back EMF combiner having,

- 1) a first input in communication with said current signal,
- 2) a second input in communication with said voltage signal, and,
- 3) an output communicating a rate signal indicative of the rate of movement of said actuator;

f) a position command combiner having,

- 1) a first input in communication with said command signal,
- 2) a second input in communication with said position signal, and,
- 3) an output communicating a position displacement signal indicative of the difference between the signals received by said first input and said second input;

g) a displacement combiner having,

- 1) a first input in communication with said displacement signal,
- 2) a second input in communication with said rate signal, and,
- 3) an output communicating a rate error signal indicative of the difference between the signals received by said first input and said second input; and,

h) a filter, interposed between said back EMF combiner and said second input of said displacement combiner, said filter conditioning said rate signal so as to minimize the effect of motor impedance variations.

5,589,750

ACCELERATION/DECELERATION CONTROL APPARATUS FOR NUMERICAL CONTROL APPARATUS

Takashi Idei, Sholchi Sagara, both of Minamitsuru-gun, and Kentaro Fujibayashi, Musashino, all of Japan, assignors to Fanuc Ltd., Yamanashi, Japan

PCT No. PCT/JP94/00106, § 371 Date Sep. 28, 1994, § 102(e)
Date Sep. 28, 1994, PCT Pub. No. WO94/19730, PCT Pub. Date Sep. 1, 1994

PCT Filed Jan. 26, 1994, Ser. No. 307,808

Claims priority, application Japan, Feb. 23, 1993, 5-032921

Int. Cl. G05B 19/416

U.S. Cl. 318—573

6 Claims



1. An acceleration/deceleration control apparatus for a numerical control apparatus which controls a tool in a vicinity of a stroke end, comprising:

- stroke end determination means for determining whether said tool moves beyond said stroke end by prereading a machining block before said tool reaches the vicinity of said stroke end;
- tool feed speed control means for controlling a feed speed of said tool in response to said stroke end determination means such that the feed speed of said tool is reduced to a minute speed in the vicinity of said stroke end; and
- interpolation means for determining first, second and third pulses, respectively supplied to first axis control means, second axis control means and third axis control means to thereby execute drive control of said tool.

5,589,751

SENSORLESS SWITCHED RELUCTANCE MOTOR

Jun Y. Lim, Seoul, Rep. of Korea, assignor to Goldstar Co., Ltd., Seoul, Rep. of Korea


Filed Dec. 16, 1993, Ser. No. 167,361

Claims priority, application Rep. of Korea, Dec. 17, 1992, 24724/1992; Dec. 17, 1992, 24725/1992; Jan. 29, 1993, 1155/1993

Int. Cl. H02P 6/02

U.S. Cl. 318—701

3 Claims



1. A switch for a sensorless switched reluctance motor comprising:

motor driving means for driving the motor by exciting phases of the motor with current in a predetermined sequence;

filtering means for filtering the current exciting the phases of the motor;

first amplifying means for amplifying output voltages from said filtering means to respective first proper levels;

first comparing means for comparing output voltages of said first amplifying means with first reference voltages respectively, to generate a high level signal when the output voltage of said first amplifying means is higher than the respective first reference voltage and a low level signal when the output voltage of said first amplifying means is lower than the respective first reference voltage;

delaying means for delaying the output voltages from said filtering means for predetermined times;

second amplifying means for amplifying the output voltages from said delaying means to respective second proper levels;

second comparing means for comparing output voltages from said second amplifying means with second reference voltages respectively, to generate a high level signal when the output voltage of said second amplifying means is higher than the respective second reference voltage and a low level signal when the output voltage of said second amplifying means is lower than the respective second reference voltage; and

OR gating means for ORing the output signals from said first comparing means and the output signals from said second comparing means.

5,589,752

CONTROLLER FOR SWITCHED RELUCTANCE MOTOR


Shinichi Iwasaki, Anjou; Masanori Sugiyama, Nishio; Chiaki Umemura, Toyohashi; Akemi Oookawa, Chita-gun, and Hisayoshi Takahashi, Kariya, all of Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya, Japan

Filed Apr. 25, 1995, Ser. No. 428,367

Claims priority, application Japan, Apr. 25, 1994, 6-086769
Int. Cl. H02P 5/05

U.S. Cl. 318—701

6 Claims



1. A controller for switched reluctance motor including means for detecting a rotational position of a rotor and in which an electrical coil which is used to drive the rotor is turned on or off at a particular rotational position of each pole on the rotor; characterized by

speed detecting means for detecting the rotational speed of the rotor; and

current waveform control means for modifying the current waveform as the current rises or falls to turn on or off the coil by modifying the current rising speed or the current falling speed in accordance with the rotational speed of the rotor which is detected by the speed detecting means.

5,589,753

RATE EFFECT MOTOR START CIRCUIT


Andrew S. Kadah, 6333 Daedulus Dr., Cicero, N.Y. 13039, and Benjamin V. Morrow, Pennellville, N.Y., assignors to Andrew S. Kadah, Cicero, N.Y.

Filed Apr. 11, 1994, Ser. No. 225,581

Int. Cl.⁶ H02P 1/42; 1/44

U.S. Cl. 318—785

18 Claims



1. A motor start circuit for an AC induction motor, said motor including at least one run winding coupled between a pair of AC power conductors, and a start winding, said motor start circuit having first and second connection terminals only and which are connected in series with said start winding, with the first connection terminal being connected to one end of said start winding and the second connection terminal being connected to one of said AC power conductors, for applying AC current to said start winding upon commencement of an application of AC current to said run winding and for removing said AC current from said start winding when said AC induction motor reaches an operating speed; the motor start circuit comprising a triac device having a main current path connected in series with said start winding and said one AC power conductor, and including means to produce a low dv/dt characteristic in the triac device so that the commencement of the application of current causes said AC current to flow through said main current path.

5,589,754

METHOD FOR DETERMINING A STATOR FLUX ESTIMATE FOR AN ASYNCHRONOUS MACHINE

Samuli Heikkilä, Helsinki, Finland, assignor to ABB Industry Oy, Helsinki, Finland


PCT No. PCT/FI94/00071, § 371 Date Aug. 24, 1995, § 102(e) Date Aug. 24, 1995, PCT Pub. No. WO94/22213, PCT Pub. Date Sep. 29, 1994

PCT Filed Feb. 24, 1994, Ser. No. 507,413

Claims priority, application Finland, Mar. 17, 1993, 931186 Int. Cl.⁶ H02P 5/28

U.S. Cl. 318—805

10 Claims



1. A method for determining an estimate for the stator flux of an asynchronous machine when the supply frequency ω_s , stator inductance L_s , at least one of stator resistance R_s and an estimate R_s , therefore, and short-circuit inductance σL_s are known, comprising the steps of:

measuring the stator current I_s and stator voltage U_s , calculating a difference voltage by subtracting at least one of the product of the stator resistance and the estimate thereof and the stator current from the stator voltage, integrating said difference voltage in relation to time to give a stator flux estimate $\Psi_{s,est}$, subtracting, prior to said step of integrating a correction term based on the feedback stator flux estimate $\Psi_{s,est}$ and being proportional to the product of the difference variable ϵ and the direction vector $\vec{C}$ given therefor, from said difference voltage, determining said difference variable from the equation:

$$(\text{height} \Psi_{s,est} - L_s I_s) / (\text{height} \Psi_{s,est} - \sigma L_s I_s) = \epsilon \text{ and}$$

forming the direction vector $\vec{C}$ from the feedback stator flux estimate $\Psi_{s,est}$ by turning it for the angle θ which is dependent on the operational mode of the machine.

5,589,755

METHOD AND APPARATUS FOR CHARGING A SECONDARY BATTERY


Osamu Kaite, Tatsuya Okada, and Toshiharu Kokuga, all of Hyogo, Japan, assignors to Sanyo Electric Co., Ltd., Osaka, Japan

Filed Feb. 23, 1995, Ser. No. 392,658

Claims priority, application Japan, Feb. 24, 1994, 6-026623 Int. Cl.⁶ H01M 10/44; 10/46

U.S. Cl. 320—21

17 Claims



8. A method of charging a secondary battery, comprising the steps of:

charging the secondary battery with a constant voltage to generate a charging current, the charging current decreasing as a function of time to a stable, low level of charging; maintaining charging of the secondary battery until detecting a first occurrence when the charging current becomes smaller than a predetermined current value; substantially reducing charging of the secondary battery on a first occasion in response to detecting the first occurrence when the charging current becomes smaller than the predetermined current value, the predetermined current value being higher than the stable, low level of charging current; sampling an open circuit voltage of the secondary battery while the charging is substantially reduced; and controlling charging according to the sampled open circuit voltage.

16. An apparatus for charging a secondary battery, the apparatus comprising:

charging means for charging the secondary battery with a charging current at a substantially constant voltage; current detecting means responsive to the charging current for generating a signal after detecting a first occurrence when the charging current becomes smaller than a predetermined value;

controlling means responsive to the signal for substantially reducing the charging current, and wherein the controlling means maintains the charging until the first occurrence of when the charging current becomes smaller than the predetermined value; and sampling means for sampling an open circuit voltage of the secondary battery while reducing the charging current; wherein the controlling means is responsive to the sampled open circuit voltage for controlling the charging current.

5,589,756

BATTERY CHARGER HAVING A MULTIPLE FUNCTION SENSE LINE


Nathaniel B. Wilson, 11346-8 Portobello, San Diego, Calif. 92124, and Elbert A. McLaren, II, 11291 Paul Barwick Ct., San Diego, Calif. 92126

Filed Nov. 29, 1994, Ser. No. 346,960

Int. Cl.⁶ H02J 7/00

U.S. Cl. 320—22

7 Claims



1. A battery charging system having at least a first and a second charging mode, the system charging a battery in a battery powered device having at least a first and a second operating mode, the battery charging system comprising:

a battery charger for charging the battery; a clock signal generator coupled to the battery charger by a multiple function conductor, the clock signal generator impressing a first clock signal on said multiple function conductor during the first operating mode and impressing a second clock signal on said multiple function conductor during the second operating mode; a temperature sensing device, coupled to the multiple function conductor, for sensing a temperature of the battery; a clock detection circuit, coupled to the multiple function conductor, for detecting the first clock signal and the second clock signal; a temperature detection circuit, coupled to the multiple function conductor, for detecting the temperature of the battery over said multiple function conductor in response to the temperature sensing device; and a variable current source for generating a first current in the first charging mode when the first clock signal is detected and a second current in the second charging mode when the second clock signal is detected.

5,589,757

APPARATUS AND METHOD FOR STEP-CHARGING BATTERIES TO OPTIMIZE CHARGE ACCEPTANCE


James K. Klang, Rosemount, Minn., assignor to GNB Battery Technologies, Inc., Mendota Heights, Minn.

Continuation-in-part of Ser. No. 188,957, Jan. 26, 1994. This application Jun. 7, 1995, Ser. No. 480,828 Int. Cl.⁶ H02J 7/04; H01M 10/44

U.S. Cl. 320—22

45 Claims

19. An apparatus for charging a battery, comprising: a controllable power source providing an electrical charging output at variable current or voltage levels; means for connecting the power source to charging terminals of the battery; control circuitry for controlling the power source to apply the electrical charging output to the battery at a plurality of levels with respect to a base charging level, including charging



output levels comprising an upper pair and a lower pair of spaced-apart charging levels;

a sensor for measuring charging input to the battery at each charging level comprising one of said pairs and providing charging input values corresponding thereto;

arithmetic means for calculating a lower differential from the difference in the charge inputs at the two charging levels comprising the lower pair of charging levels, and for calculating an upper differential from the difference in the charge inputs at the two charging levels comprising the upper pair of charging levels; and

comparison circuitry for comparing the lower and upper differentials with one another and providing a comparison result, the comparison circuitry being operatively connected to provide the comparison result to the control circuitry, the control circuitry increasing or decreasing the base charging level in dependence on the comparison result.

36. A method of charging a battery, comprising the steps of: outputting a charging voltage to the battery in dependence on a base voltage level;

adjusting the charging voltage in steps of predetermined magnitudes to provide first, second and third voltage levels, wherein the first level is less than the second level and the second level is less than the third level;

measuring first, second and third currents at the first, second and third voltage levels, respectively;

calculating a first differential from the difference in the first current from the second current, and calculating a second differential from the difference in the second current from the third current;

comparing the first differential and the second differential; and increasing the base voltage a selected increment amount if the first differential is greater than the second differential, or decreasing the base voltage a selected decrement amount if the first differential is less than the second differential.

5,589,758

MODULAR, HYBRID POWER SYSTEM

James B. Blackmon, Brownsboro, Ala.; Robert E. Drubka, Huntington Beach, Calif.; Nelson E. Jones, Los Osos, Calif.; R. Andrew Gerrick, Santa Ana, Calif., and Michael L. Hand, Huntington Beach, Calif., assignors to McDonnell Douglas Corporation, Huntington Beach, Calif.

Filed Sep. 7, 1993, Ser. No. 116,852

Int. Cl.⁶ H02P 9/00

U.S. Cl. 322—100

16 Claims

1. A power system, comprising:


a turbogenerator system;

a low voltage amplifier;

an amplifier fuel cell connected to said low voltage amplifier for supplying electrical power thereto;

a medium voltage amplifier connected to said turbogenerator system for receiving high voltage electrical power therefrom; and

a high voltage amplifier connected to said turbogenerator system for receiving high voltage electrical power therefrom, said



high, medium and low voltage amplifiers supplying electrical power at selected radio frequencies to an electrical system.

5,589,759

CIRCUIT FOR DETECTING VOLTAGE VARIATIONS IN RELATION TO A SET VALUE, FOR DEVICES COMPRISING ERROR AMPLIFIERS


Pierandrea Borgato, Lomagna; Claudio Diazzi, Milan, and Albino Fidutti, Udine, all of Italy, assignors to SGS-Thomson Microelectronics S.r.l., Agrate Brianza, Italy
Filed Jul. 30, 1993, Ser. No. 100,482

Claims priority, application European Pat. Off., Jul. 30, 1992, 92830428

Int. Cl.⁶ G05F 1/63

U.S. Cl. 323-222

25 Claims



1. A circuit for detecting voltage variations of an output terminal in relation to a set value, said circuit comprising an error amplifier, having an amplifier input connected to the output terminal and an amplifier output for supplying an error signal, said circuit also comprising a feedback branch connected between said amplifier input and said amplifier output of said error amplifier, said circuit further comprising a current sensor connected to the feedback branch, said current being proportional to the voltage variations of the output terminal and said current sensor generating a signal proportional to the voltage variations at the output terminal.

5,589,760

TRAVELLER'S VOLTAGE CONVERTER FOR AUTOMATICALLY SELECTING LOAD WATTAGE

Anthony Lee, C/O Hung Hsing Service Center P.O. Box 55-1670, Taipei, Taiwan

Filed Sep. 5, 1995, Ser. No. 523,354


Int. Cl.⁶ G05F 1/12

U.S. Cl. 323-247

3 Claims

1. A voltage converter for traveller's uses for automatically selecting load wattage comprising:

- a low-wattage transformer for converting an input voltage of 220 volts AC across a hot input terminal and a neutral terminal to an output voltage of 110 volts AC across a hot output terminal and the neutral terminal for powering a low-wattage load connected across said hot output terminal and said neutral terminal;



- a high-wattage transformer for converting an input voltage of 220 volts AC across said hot input terminal and said neutral terminal to an output voltage of 110 volts AC across said hot output terminal and said neutral terminal to obtain an output power rating of wattage value greater than that of said low-wattage transformer for powering a high-wattage load connected across said hot output terminal and said neutral terminal;

- a sensing control circuit connected between said low-wattage transformer and said neutral terminal, and operatively sensing an induced current signal from a lead of said neutral terminal when led to a high-wattage load; and
- a relay connected to said sensing control circuit and normally connecting a first contactor of said low-wattage transformer with said hot output terminal, and operatively actuated by said induced current signal from said sensing control circuit for switching on a second contactor of said high-wattage transformer to connect the hot output terminal with the high-wattage transformer for powering the high-wattage load when connected between said hot output terminal and said neutral terminal.

5,589,761

DUAL POLARITY VOLTAGE REGULATOR CIRCUITS AND METHODS FOR PROVIDING VOLTAGE REGULATION


Carl T. Nelson, San Jose, and Robert Essaff, Fremont, both of Calif., assignors to Linear Technology Corporation, Milpitas, Calif.

Continuation of Ser. No. 228,478, Apr. 15, 1994. This application Jun. 7, 1995, Ser. No. 472,538

Int. Cl.⁶ G05F 1/575

U.S. Cl. 323-285

13 Claims



1. A dual polarity voltage regulator circuit comprising: negative feedback network means; error amplifier means coupled to the negative feedback network means; positive regulator network means coupled to the error amplifier means and to the negative feedback network means; and negative regulator network means coupled to the error amplifier means and to the negative feedback network means, such that: when positive voltages are being regulated by the voltage regulator, the error amplifier means provides a feedback signal to the voltage regulator and the negative regulator network is deactivated; and

when negative voltages are being regulated by the voltage regulator, the error amplifier means and the negative regulator network operate together to provide a feedback signal to the voltage regulator.

5,589,762

ADAPTIVE VOLTAGE REGULATOR


James M. Iannuzzo, Phoenix, Ariz., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Continuation of Ser. No. 74,132, Jun. 8, 1993, abandoned, which is a continuation of Ser. No. 659,248, Feb. 22, 1991, abandoned. This application Sep. 1, 1994, Ser. No. 299,815

Int. Cl.⁶ G05F 1/64

U.S. Cl. 323-351

18 Claims



15. A controller for providing a continuously variable regulated power supply voltage, comprising:

- a source voltage;
- a reference voltage;
- means for sensing a voltage at an output node;
- means for comparing the reference voltage to the sensed voltage, and for, if the sensed voltage falls below a value determined by the reference voltage, connecting said source voltage to the output node, and for, if the sensed voltage rises above the value determined by said reference voltage, disconnecting said source voltage from the output node; and
- means for automatically adjusting an output voltage on said output node by increasing said reference by a continuously variable amount in response to a continuously varying input signal indicating that a higher voltage is desired on the output node, wherein the increase in said output voltage is functionally related to the increase in said reference voltage.

5,589,763

COHERENT UNDERSAMPLING DIGITIZER FOR USE WITH AUTOMATIC FIELD TEST EQUIPMENT


Mark A. Burns, Garland, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed May 16, 1995, Ser. No. 442,538

Int. Cl.⁶ G01R 13/34

U.S. Cl. 324-76.15

7 Claims



1. An apparatus for measuring a repetitive test waveform in a coherent manner, comprising:

- a signal generating circuit to generate and output said repetitive test waveform in accordance with first clock signals;
- a first clock circuit coupled to said signal generating circuit to output said first clock signals at a first clock frequency;
- a strobed comparator to sample the repetitive test signal in accordance with second clock signals and to output a one-bit comparison result signal;
- a second clock circuit coupled to strobed comparator circuit to output said second clock signals at a second clock frequency;
- a processor coupled to said first clock circuit and said second clock circuit to determine a frequency ratio between said first clock frequency and said second clock frequency, said processor using frequency ratio for producing S sampling point signals evenly spaced across said repetitive test waveform;
- a successive approximation digital to analog converter for providing a comparison level to said strobed comparator and to receive said S sampling point signals;
- said processor to generate and provide successive approximation values to said successive approximation routine digital to analog converter;
- waveform capture memory to store said one bit comparison result signal for subsequent retrieval and refinement by successive approximation routine logic, said waveform capture memory and said successive approximation routine logic collecting one bit at a time from each digitized sample from said S sampling point signals, all most significant bits MSB's first, all least significant bits LSB's last, resulting in a digitized waveform corresponding to said repetitive test waveform.

5,589,764

METER FOR MEASURING ACCUMULATED POWER CONSUMPTION OF AN ELECTRICAL APPLIANCE DURING OPERATION OF THE APPLIANCE


Graham S. Lee, 760 Fairmile Rd., West Vancouver, British Columbia, Canada

Continuation-in-part of Ser. No. 196,556, Feb. 15, 1994, which is a continuation of Ser. No. 664,888, Mar. 5, 1991, Pat. No. 5,315,236. This application Oct. 3, 1994, Ser. No. 320,409

Int. Cl.⁶ G01R 22/00; G07C 1/00

U.S. Cl. 324-157

8 Claims



1. An electric power meter, comprising: a body member; prongs on said body member for insertion into an electric socket; a second socket on said body member for receiving the plug of an electric appliance, said second socket being in electrical communication with said prongs for transferring electric power from said prongs to said second socket; current measuring means in said body member for measuring the total accumulated electric current flow between said prongs and said second socket on said body member during actual operation of said electrical appliance; a timer for measuring the duration of said electric current flow; processing means associated with said body member for receiving data from said current measuring means to calculate electric power consumed from said data; and display means associated with said body member for displaying measurement results of the power meter thereon; said dis-

played measurement results comprising electric power consumed and the time period during which the appliance is in actual operation and said power has been so consumed.

5,589,765

METHOD FOR FINAL TESTING OF SEMICONDUCTOR DEVICES


Dale V. Ohmart, Fuishear; Willie B. Benitez, III, Wylie, both of Tex.; Deogracias D. Marrero, Baguio City, Philippines, and Douglas J. Mirizzi, Rosenberg, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Jan. 4, 1995, Ser. No. 368,683

Int. Cl.⁶ G01R 31/02

U.S. Cl. 324-158.1

18 Claims



1. A method for final testing a lot consisting of a predetermined plurality of semiconductor devices, comprising the steps of: testing operation of a test system relative to a predetermined set of test system performance characteristics; if said test system fails to operate in accordance with said predetermined set of test system performance characteristics, repairing said test system and retesting operation of said test system until said test system operates in accordance with said predetermined set of test system performance characteristics; certifying that said test system is operating in accordance with said predetermined set of test system performance criteria; testing a plurality of semiconductor device performance characteristics of each of said lot of semiconductor devices with said test system, said testing resulting in passing semiconductor devices operating in accordance with said plurality of semiconductor device performance characteristics and failing semiconductor devices not operating in accordance with said plurality of semiconductor device performance characteristics; subsequent to said testing of said lot of semiconductor devices, testing operation of said test system relative to said predetermined set of test system performance characteristics; if said test system fails to operate in accordance with said predetermined set of test system performance criteria subsequent to said testing of said lot of semiconductor devices repairing said test system and retesting operation of said test system until said test system operates in accordance with said predetermined set of test system performance characteristics; following repair of said test system restarting testing each of said lot of semiconductor devices and subsequent to said restart of testing of said lot of semiconductor devices retesting operation of said test system; if said test system operates in accordance with said predetermined set of test system performance criteria subsequent to said testing of said lot of semiconductor devices, recertifying that said test system is operating in accordance with said predetermined set of test system performance criteria; and packing and shipping said passing semiconductor devices.

5,589,766 FIELD-TESTABLE INTEGRATED CIRCUIT AND METHOD OF TESTING


Paul A. Frank, Albany; Donald T. McGrath, and Daniel A. Staver, both of Scotia, all of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Apr. 6, 1995, Ser. No. 417,576

Int. Cl.⁶ G01R 31/02

U.S. Cl. 324-158.1

8 Claims



1. A field-testable integrated circuit comprising: a plurality of analog signal channels for receiving a respective analog signal during a normal mode of operation; signal processing means coupled to said plurality of analog signal channels for utilizing the analog signals received by said plurality of analog signal channels; and circuit means for selecting respective ones of said plurality of channels to receive a predetermined reference instead of said respective analog signal during a test mode of operation while permitting the normal mode of operation to continue uninterrupted in any remaining unselected channels in said integrated circuit.

5,589,767

MECHANISM FOR THE ATTACHMENT OF A SPEED SENSOR TO A TRAIN WHEEL INCLUDING A BEARING AND A CONNECTION LINK WITH A SHOCK ABSORBING BUSHING

Osamu Akamatsu, Akashi, Japan, assignor to NABCO Ltd., Kobe, Japan


Filed Apr. 5, 1994, Ser. No. 223,390

Claims priority, application Japan, Apr. 6, 1993, 5-105055

Int. Cl.⁶ G01P 3/48; G01R 33/02; B61L 11/08

U.S. Cl. 324-173

4 Claims



1. A mechanism for attaching a speed sensor to a railway vehicle comprising: (a) a rotary body for abutting attachment to an end face of a wheel axle and disposed in a nonsurrounding relationship to such wheel axle such that said rotary body rotates with such wheel axle, said rotary body having an outer peripheral surface, said outer peripheral surface having a gear wheel with teeth;

- (b) a sensor mounting body within which said rotary body rotates;
- (c) a speed sensor attached to said sensor mounting body and aligned opposite to said gear wheel with teeth of said rotary body, said teeth providing the change in magnetic field sensed by said speed sensor when said rotary body is rotating with such wheel axle so that said speed sensor generates a signal corresponding to the rotational speed of such wheel axle;
- (d) a bearing disposed between said rotary body and said sensor mounting body such that said bearing maintains a predetermined gap between said speed sensor and said gear wheel with teeth; and
- (e) a connection link through which said sensor mounting body is connected to a frame of such vehicle, said connection link comprising a displacement absorption means for preventing transmission of vibration from both such vehicle frame and such wheel axle to said speed sensor attachment mechanism so as to protect said speed sensor attachment mechanism from damage.

5,589,768

MAGNETORESISTANCE-EFFECT MAGNETIC SENSOR OF THE TEMPERATURE COMPENSATING TYPE

Noritaka Ishiyama, Tokyo, and Koutarou Kobayashi, Yamanashi-ken, both of Japan, assignors to Mitsubishi Steel Mfg. Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 976,984, Jan. 22, 1993, abandoned.


This application Jun. 23, 1994, Ser. No. 264,211

Claims priority, application Japan, Jul. 30, 1990, 2-199123; Dec. 25, 1990, 2-412876

Int. Cl.⁶ G01R 33/09; G01B 7/14; G11B 5/39; H01L 43/08

U.S. Cl. 324-207.21

2 Claims



1. A magnetoresistance-effect magnetic sensor for sensing a magnetic pattern on a magnetic medium comprising: at least first and second devices having respective first and second current paths each with first and second ends, said first and second devices being formed in a magnetoresistance-effect thin film layer; said thin film layer of said first and second devices consisting essentially of a Fe-Ni alloy having a rate of decrease of the magnetoresistance-effect with temperature and a rate of increase of intrinsic resistance with temperature that are substantially equal; said first and second devices being arranged in 180 degree shifted positions with respect to the magnetic pattern to be detected such that said first device senses a first portion of the magnetic pattern and said second device senses a second portion of the magnetic pattern wherein the second portion is 180° out of phase with respect to the first portion as determined by a periodicity of the magnetic pattern; first and second constant current sources, each serially connected to first ends of said first and second devices respectively to supply constant currents therethrough and to generate respective first and second potentials across said first and second devices, said first device and first constant current source and said second device and second current source being arranged in parallel with said second ends of said first and second devices connected to a common potential, wherein

a difference between said first and second potentials is compensated for temperature effects and varies in accordance with said magnetic pattern.

5,589,769

POSITION DETECTION APPARATUS INCLUDING A CIRCUIT FOR RECEIVING A PLURALITY OF OUTPUT SIGNAL VALUES AND FITTING THE OUTPUT SIGNAL VALUES TO A CURVE


Donald R. Krahn, Eagan, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Sep. 30, 1994, Ser. No. 324,182

Int. Cl.⁶ G01B 7/02; G01D 5/16; 5/246

U.S. Cl. 324-207.26

15 Claims



1. Apparatus for determining a position of a member movable along a defined path, comprising: means for producing a magnetic field attached to said member; an array of magnetic field transducers located adjacent said defined path, each transducer comprising magnetoresistive material and providing a bipolar output signal as said means for producing a magnetic field approaches, passes and moves away from said each transducer, with said magnetic field of sufficient strength to saturate said magnetoresistive material; said array of transducers providing a plurality of output signal values for a first position of said means for producing a magnetic field; and electronic means for receiving said plurality of output signal values and fitting said plurality of output signal values to a first curve and using a crossover point of said first curve to determine said first position.

5,589,770

MECHANICAL SENSOR FOR DETECTING STRESS OR DISTORTION WITH HIGH SENSITIVITY

Shinji Saitou, Sulta, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Jun. 23, 1995, Ser. No. 494,221

Claims priority, application Japan, Jun. 27, 1994, 6-144436

Int. Cl.⁶ G01L 1/00

U.S. Cl. 324-209

18 Claims



1. A mechanical sensor, comprising: a first ferromagnetic layer having magnetostriction; a second ferromagnetic layer, separate from the first ferromagnetic layer, and having magneto-resistance effect; a magnetic field generating means for exciting said first and second ferromagnetic layers; and


a substrate which integrally support said first and second ferromagnetic layers and said magnetic field generating means, wherein a change of a magnetic flux density passing through said first and second ferromagnetic layers resulting from a change of magnetic properties due to stress is detected as a change of resistance value arising from the magneto-resistance effect.

5,589,771
MAGNETIC MEDIA HEAD DYNAMIC TESTING
APPARATUS AND METHOD WHICH OPERATE BY
DEFORMING A LOCALIZED PORTION OF MAGNETIC
MEDIA TOWARD THE HEAD ELEMENT
 Sung P. Chur, Palo Alto, Calif., assignor to Swan Instruments, Inc., Santa Clara, Calif.

Filed Oct. 24, 1994, Ser. No. 328,062
 Int. Cl.⁶ G01R 33/12

U.S. Cl. 324—212

17 Claims



1. A method for testing, prior to final assembly of hard disk drives, a magnetic head element of the type used for reading rigid media, comprising:


- placing the magnetic head element in proximity to a flexible magnetic medium disk;
- causing said flexible magnetic medium disk to move in relation to a stationary stabilizer plate;
- deforming a localized portion of the flexible magnetic medium disk toward, but not into actual contact with, the magnetic head element; wherein
- said deforming is accomplished without physical contact of a solid body with said flexible magnetic medium disk; and
- testing the magnetic head element.

5,589,772
NON-DESTRUCTIVE EDDY CURRENT SENSOR HAVING
A SQUID MAGNETIC SENSOR AND SELECTIVELY
POSITIONABLE MAGNETS
 Hirokazu Kugai, Hyogo, Japan, assignor to Sumitomo Electric Industries, Ltd., Osaka, Japan

Filed Jul. 12, 1994, Ser. No. 273,947
 Claims priority, application Japan, Jul. 12, 1993, 5-195125; Dec. 27, 1993, 5-348837
 Int. Cl.⁶ G01N 27/82; G01C 21/08

U.S. Cl. 324—240

14 Claims



1. A non-destructive testing equipment comprising:

- a magnetic shield container defining a magnetically stable inspection zone where an object to be tested is to be positioned for testing and said magnetic shield container having a magnetically transparent opening adjacent said inspection zone;
- a magnetic field generator attached to said magnetic shield container, for generating a stable magnetic field in said inspection zone;
- a magnetic sensor located in said magnetic shield container and including at least one SQUID, for detecting, through said opening, the magnetic field in said inspection zone;
- means provided to said magnetic shield container, for cooling said magnetic sensor,
- means for allowing the testing equipment to move in relation to and along an object to be tested, and means for maintaining a distance between said magnetic sensor and the object to be tested at a constant value;
- wherein said cooling means includes a thermal insulation container accommodating said magnetic sensor therein and filled with a cooling medium for cooling said magnetic sensor to a temperature not higher than a superconducting critical temperature; and
- wherein said magnetic field generator includes at least one pair of permanent magnets which are so constructed and arranged to be selectively positioned in a first orientation in which said at least one pair of permanent magnets are located in parallel to each other but opposed in polarity to each other so that said at least one pair of permanent magnets are magnetically strongly bonded to each other and no substantial magnetic field is generated in the outside of said at least one pair of permanent magnets magnetically bonded to each other, and in a second orientation in which said at least one pair of perma-

nent magnets are located in parallel to each other and in the same polarity direction, so that said at least one pair of permanent magnets are magnetically strongly repelled from each other, and the at least one pair of permanent magnets in said second orientation generate a substantial magnetic field outside of the said at least one pair of permanent magnets.


5,589,773
SYSTEM AND METHOD FOR MAKING
ELECTROMAGNETIC MEASUREMENTS USING A
TILTABLE TRANSVERSE ELECTROMAGNETIC CELL
AND A FIXED TILT SAMPLE HOLDER

H. Stephen Berger, Georgetown; Martha L. Vela de Casillas, Austin, and Harry L. Cochran, Liberty Hill, all of Tex., assignors to Siemens Rolm Communications Inc., Santa Clara, Calif.

Filed Oct. 12, 1994, Ser. No. 321,699
 Int. Cl.⁶ G01R 33/02; B23Q 1/25

U.S. Cl. 324—261

34 Claims



1. A system for obtaining electromagnetic measurements from a test object, comprising:
 - a hollow cell for inserting the test object,
 - said hollow cell comprising an electromagnetically conductive material for conducting electromagnetic radiation generated by the test object, and being tilttable about at least one axis, said at least one axis being perpendicular to the direction of the force of gravity;
 - a table rotatable about its vertical axis within said hollow cell, the test object being positioned upon said table; and
 - a fixed tilt mechanism for maintaining said table in a fixed tilt position relative to said at least one axis as said hollow cell is tilted about said at least one axis perpendicular to the direction of the force of gravity.

5,589,774
Patent Not Issued For This Number

5,589,775
ROTATING MAGNET FOR DISTANCE AND DIRECTION
MEASUREMENTS FROM A FIRST BOREHOLE TO A
SECOND BOREHOLE


Arthur F. Kuckes, Ithaca, N.Y., assignor to Vector Magnetics, Inc., Ithaca, N.Y.
 Continuation-in-part of Ser. No. 155,529, Nov. 22, 1993, abandoned. This application Dec. 5, 1995, Ser. No. 567,578

Int. Cl.⁶ G01V 3/26; 3/20; 3/40; G01R 33/04

U.S. Cl. 324—346

32 Claims

1. A method for determining the direction from a magnetic field source to an observation point, comprising:



- generating, by way of a rotating magnetic field source at a first location, an elliptically polarized magnetic field in the region of an observation point;
- measuring, by first and second sensors at said observation point the amplitude and relative phase of respective first and second perpendicular vector components of said ellipticity polarized rotating magnetic field; and
- determining from said measurements the direction, relative to said sensors, from said observation point to said first location.


5,589,776
NON-INTRUSIVE TESTING OF A TERMINAL RESISTOR
 David G. Morant, Mercer Island, Wash., assignor to The Boeing Company, Seattle, Wash.

Division of Ser. No. 173,328, Dec. 23, 1993. This application Jun. 6, 1995, Ser. No. 469,303

Int. Cl.⁶ G01R 31/11

U.S. Cl. 324—534

3 Claims



1. A method of non-intrusive testing of a terminal resistor on a data bus, comprising:
 - inserting a signal having an amplitude that varies over time onto said data bus adjacent one end thereof by magnetically coupling a signal generator to said data bus and producing a signal of known repetition rate and amplitude in said data bus;
 - electronically observing any reflected signal, having an amplitude that varies over time, produced by a reflection of said signal from the end of said data bus;
 - comparing the amplitude over time of said signal with the amplitude over time of said reflected signal to determine if said signal and said reflected signal are in phase or out of phase; and
 - determining from the amplitude over time of said reflected signal and from whether said signal and said reflected signal are in phase or out of phase, or the absence of said reflected signal, whether said terminal resistor is correctly sized and correctly installed.


5,589,777

CIRCUIT AND METHOD FOR TESTING A DISK DRIVE HEAD ASSEMBLY WITHOUT PROBING

Bradley K. Davis, Meridian, Id.; Johannes O. Voorman, Geldrop; Joao N. V. L. Ramalho, Eindhoven, both of Netherlands, and Patrice Gamand, Douvres-la-delivrande, France, assignors to Hewlett-Packard Company, Palo Alto, Calif., and Philips Electronics N.V., Netherlands
 Filed Jun. 21, 1995, Ser. No. 493,384
 Int. Cl.⁶ G01R 31/02; 31/302

U.S. Cl. 324—537

20 Claims



1. A preamplifier circuit for a data storage system, the data storage system including at least one read head element and at least one write head element, the preamplifier circuit comprising:

- means for forcing a write current generated by preamplifier circuit through the at least one write head element, the write current being responsive to a write data signal received and processed by the preamplifier circuit;
- means for presenting a read data signal at an output means of the preamplifier circuit, the read data signal being responsive to a read current generated by the preamplifier circuit through the at least one read head element;
- input means for receiving a test mode signal indicative of a test mode for identifying and initiating testing of selected circuitry associate with the preamplifier circuit or the data storage system;
- means, electrically connected to the input means, responsive to the test mode signal for initiating a controlled test current in the identified selected circuitry; and,
- means for presenting an output signal at the output means of the preamplifier circuit, the output signal being responsive to the controlled test current and indicative of electrical properties, including resistance, of the identified selected circuitry.

5,589,778

SENSOR DRIVE CIRCUIT


Yukio Ono, and Seichiro Kikuyama, both of Hyogo, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Apr. 11, 1995, Ser. No. 419,697
 Claims priority, application Japan, May 20, 1994, 6-106597
 Int. Cl.⁶ G01R 27/28

U.S. Cl. 324—654

24 Claims

1. A sensor drive circuit comprising:
- a reference sensor having first and second ends and including a first coil of a fixed inductance;
 - a variable sensor including a second coil of a variable inductance, said second coil being connected in series with said first coil;



amplitude control means receiving a first signal from a side of the first end of said reference sensor and a second signal from a side of the second end thereof for controlling an amplitude of a difference signal between said first and second signals so as to be held constant; and
 inductance detection signal output means for outputting an inductance detection signal responsive to the amount of variation in the inductance of said second coil of said variable sensor.

said amplitude control means including:

- peak detecting means receiving said first and second signals for detecting a peak value of said difference signal to output a peak detection signal; and
- signal applying means receiving said peak detection signal for applying a signal to said first and second coils so that amplitudes of said first and second signals are varied in response to said peak detection signal.

5,589,779


POTENTIOMETER CIRCUIT PROVIDING IDENTIFIABLE OPEN WIPER SIGNALS

Eric S. Micko, Rescue, Calif., assignor to Qualimetries, Inc., Sacramento, Calif.

Filed Jan. 24, 1994, Ser. No. 184,980
 Int. Cl.⁶ G01R 27/08

U.S. Cl. 324—714

7 Claims



1. A circuit, comprising:

- a signal source;
- a first conducting element having a first contact coupled to the signal source and having a second contact coupled to the signal source;
- a second conducting element having a first contact coupled to the first conducting element, providing a first signal corresponding to a position of the second conducting element relative to the first conducting element during a decoupling of the second conducting element first contact from the first conducting element;
- means, coupled to the second conducting element, for providing a second signal corresponding to the second conducting element first contact position during the decoupling responsive to the first signal, wherein the means for providing includes:
- means, coupled to the second conducting element, for sensing the first signal; and,
- means, coupled to the sensing means, for driving the first signal to a reference signal level.

5,589,780

IC ANALYSIS SYSTEM AND ELECTRON BEAM PROBE SYSTEM AND FAULT ISOLATION METHOD THEREFOR


Koshi Ueda, Machida; Akira Goishi, Kazo, and Masayuki Kuribara, Gyoda, all of Japan, assignors to Advantest Corporation, Tokyo, Japan

Division of Ser. No. 181,584, Jan. 14, 1994, Pat. No. 5,528,156.
 This application Sep. 30, 1994, Ser. No. 312,953
 Claims priority, application Japan, Jul. 30, 1993, 5-190431;
 Jul. 30, 1993, 5-190449; Sep. 21, 1993, 5-257624

Int. Cl.⁶ G01R 31/305

U.S. Cl. 324—751

8 Claims



1. An integrated circuit analysis system comprising:

an electron beam probe system which scans and irradiates a surface of a device under test with an electron beam, measures a quantity of secondary emission from an irradiated point, and displays a potential distribution on the surface of said device under test; and

an integrated circuit tester which applies a test pattern signal comprising a series of test patterns to said device under test, said IC tester comprising:

a test pattern generator which generates a test pattern signal comprising a series of test patterns and sequentially updates and applies the test patterns of said test pattern signal to said device under test.

stop pattern setting means for setting therein at least a first test pattern and a second test pattern among the test patterns of said test pattern signal as update stopping test patterns for temporarily stopping said test pattern generator from updating one of said first test pattern and said second test pattern generated by said test pattern generator, respectively, and main control means for controlling, when said test pattern generator generates one of said first test pattern and said second test pattern, said test pattern generator to temporarily stop from updating said one test pattern and to hold said test pattern generator in a state of continuing to output said one test pattern being applied to said device under test, and concurrently outputting a first pattern update stop signal representing a pause of the test pattern updating operation of said test pattern generator when said test pattern generator generates said second test pattern; and

said electron beam probe system comprising:

at least two image data processing means each of which acquires an image data from the surface of said device under test on receiving one of said first pattern update stop signal and said second pattern update stop signal from said main control means;

calculating means for calculating a difference between said image data acquired by said at least two image data processing means; and

a monitor displaying image data of said difference calculated by said calculating means.

5,589,781


DIE CARRIER APPARATUS

H. Dan Higgins, 323 E. Redfield Rd., Chandler, Ariz. 85225, and Peter Normington, 516 Country Plz. South, Gilbert, Ariz. 85234

Continuation-in-part of Ser. No. 775,914, Oct. 15, 1991, Pat. No. 5,521,518, which is a continuation-in-part of Ser. No. 585,939, Sep. 20, 1990, abandoned. This application May 12, 1993, Ser. No. 60,757
 Int. Cl.⁶ G01R 1/073

U.S. Cl. 324—755

23 Claims



1. Carrier apparatus for supporting an integrated circuit die for testing the die comprising in combination:

carrier block means comprising a base for receiving and supporting an integrated circuit die to be tested;
 probe card means disposed on the carrier block means for testing the integrated circuit die, including

a substrate,

an aperture extending through the substrate,

a plurality of conductive traces, each comprising two portions, a first portion on the substrate and a second portion extending beyond the substrate and into the aperture and terminating in a tip for contacting the integrated circuit die for testing, the second portion comprising a probe needle extending from the first portion;

an alignment plate disposed on the carrier block means for aligning the probe card means and the integrated circuit die; support plate means for supporting the integrated circuit die relative to the carrier block means and the probe card means; and

means for securing the carrier block means, the probe card means, the alignment block and the support plate means with the integrated circuit die together for testing the integrated circuit die.

5,589,782

MACROCELL AND CLOCK SIGNAL ALLOCATION CIRCUIT FOR A PROGRAMMABLE LOGIC DEVICE (PLD) ENABLING PLD RESOURCES TO PROVIDE MULTIPLE FUNCTIONS


Bradley A. Sharpe-Geisler, San Jose, Calif., assignor to Advanced Micro Devices, Inc., Sunnyvale, Calif.

Filed Jun. 2, 1995, Ser. No. 458,865
 Int. Cl.⁶ H03K 19/173

U.S. Cl. 326—38

36 Claims

1. A macrocell and block clock/control circuit for a programmable logic device, the macrocell receiving a data signal at a data input from a sum of product terms output of an OR gate and block



clock signals from outputs of the block clock/control circuit, wherein the macrocell comprises:

- a storage element having a data input for receiving the data signal, a clock input, and an output, the storage element configured for providing a data signal received at its data input to its output as controlled by a signal received at its clock input; and
- a multiplexer having first inputs connected to the block clock/control circuit outputs to receive the block clock signals, a second input connected to receive a select signal, and an output connected to the clock input of the storage element, the multiplexer configured for providing one of the block clock signals at its output as selected by the select signal, and wherein the block clock/control circuit comprises circuit elements configured for providing the block clock signals to selectively enable operation modes in a group consisting of two or more different ones of the following: a latch mode; a single edge D-type flip-flop mode; a dual edge D-type flip-flop mode, a reset mode; a preset mode; and a mixed clock mode.

5,589,783

VARIABLE INPUT THRESHOLD ADJUSTMENT


David C. McClure, Carrollton, Tex., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Filed Jul. 29, 1994, Ser. No. 282,177

Int. Cl.⁶ H03K 19/0448

U.S. Cl. 326—71

24 Claims



1. An integrated circuit device having a variable trip point adjustment, comprising:

- a programmable input buffer of an integrated circuit device, wherein the integrated circuit device has a supply voltage; and
 - a control input signal to the programmable input buffer, wherein when the control input signal is equal to a first logic level, a first trip point of the integrated circuit device is defined, and when the control input signal is equal to a second logic level, a second trip point of the integrated circuit device is defined, wherein a chip enable signal of the integrated circuit device may determine whether the control input signal is equal to the first logic level or the second logic level,
- wherein the programmable input buffer is comprised of a bond pad, a logic gate, a first transistor having a first source/drain, a second source/drain, and a gate, a second transistor having a first source/drain, a second source/drain, and a gate, a third

transistor having a first source/drain, a second source/drain, and a gate, a fourth transistor having a first source/drain, a second source/drain, and a gate, a fifth transistor having a first source/drain, a second source/drain, and a gate, and a sixth transistor having a first source/drain, a second source/drain, and a gate; and

wherein the chip enable signal controls the gate of the first transistor and the gate of the sixth transistor; wherein a bond pad signal generated by the bond pad controls the gate of the second transistor, the gate of the third transistor, and the gate of the fifth transistor; wherein the chip enable signal is a first input signal to the logic gate, the control input signal is a second input signal to the logic gate, and the logic gate generates a derivative chip enable signal which controls the gate of the fourth transistor; and

wherein the first source/drain of the first transistor and the first source/drain of the fourth transistor are connected to a first supply voltage; the second source/drain of the third transistor and the second source/drain of the sixth transistor are connected to a second supply voltage; the second source/drain of the first transistor is connected to the first source/drain of the second transistor; the second source/drain of the second transistor, the first source/drain of the third transistor, the second source/drain of the fifth transistor, and the first source/drain of the sixth transistor are connected together to form an output signal; and the second source/drain of the fourth transistor is connected to the first source/drain of the fifth transistor.

5,589,784

METHOD AND APPARATUS FOR DETECTING CHANGES IN A CLOCK SIGNAL TO STATIC STATES


Sabrina D. Phillips, Garland, and James R. Hellums, Dallas, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Continuation of Ser. No. 237,949, May 2, 1994, abandoned, which is a continuation of Ser. No. 861,721, Mar. 31, 1992, abandoned. This application Sep. 21, 1994, Ser. No. 310,354

Int. Cl.⁶ H03K 5/153

U.S. Cl. 327—18

4 Claims



1. An integrated circuit for detecting changes in a clock signal from a first static state to at least a second static state comprising: charging circuitry;

- a first capacitor means coupled to said charging circuitry, said charging circuitry operable to linearly charge said first capacitor means in response to the clock signal changing to the first static state;
- a first differential pair having a first reference voltage input, a first input, and a first output, said first capacitor means coupled to said first input, and said first reference voltage input coupled to a first reference voltage signal, such that a first output level is generated at said first output in response to said first capacitor means being charged to a voltage equal to or greater than said first reference voltage signal, said first capacitor means further being discharged responsive to said clock signal changing to the second static state;
- a second capacitor means coupled to said charging circuitry, said charging circuitry operable to linearly charge said second

capacitor means in response to said clock signal changing to the second static state; and

- a second differential pair having a second reference voltage input, a second input, and a second output, said second capacitor means coupled to said second input, said second reference voltage input coupled to a second reference voltage signal, such that a second output level is generated at said second output in response to said second capacitor means being charged to a voltage equal to or greater than said second reference voltage signal, said second capacitor means further being discharged responsive to said clock signal changing to the first static state.

5,589,785

LOW-VOLTAGE CMOS COMPARATOR

Patrick J. Garavan, Limerick, Ireland, assignor to Analog Devices, Inc., Norwood, Mass.


Division of Ser. No. 235,557, Apr. 29, 1994. This application

Jun. 7, 1995, Ser. No. 474,532

Int. Cl.⁶ H03K 5/22

U.S. Cl. 327—63

37 Claims



1. A comparator gain stage, comprising:

- a differential pair input circuit comprising first and second input devices, the first input device being placed in a first electrical path between a supply voltage and a first output node, the second input device being placed in a second electrical path between the supply voltage and a second output node;
- a first cascode device in a third electrical path between the supply voltage and the first output node, the third electrical path being distinct from the first and second electrical paths;
- a second cascode device in a fourth electrical path between the supply voltage and the second output node, the fourth electrical path being distinct from the first and second electrical paths;
- a first diode-connected load device in the third path and a second diode-connected load device in the fourth path, said first and second diode-connected load devices being responsive to the input devices and the cascode devices; and
- fifth and sixth current paths parallel to the diode-connected load devices.

5,589,786

HIGH-SPEED CMOS DRIVER FOR OPTICAL SOURCES

Valter Bella, and Paolo Pellegrino, both of Turin, Italy, assignors to Csele - Centro Studi e Laboratori Telecomunicazioni S.p.A., Turin, Italy

Filed Jun. 1, 1995, Ser. No. 456,712

Claims priority, application Italy, Jun. 6, 1994, TO94A0462


Int. Cl.⁶ H03K 3/42

U.S. Cl. 327—108

6 Claims

1. A CMOS driver for an optical device, comprising:

- a bias current generator formed by a transistor having a source connected to a power supply terminal, a gate connected to a



bias current control terminal, and a drain connected to a terminal of an optical device to be driven whereby a bias current is supplied to said optical device;

- a modulation current generator for supplying a modulation current to said optical device and comprising a pair of series-connected transistors, a first transistor of said pair having a drain connected to said terminal of said optical device to be driven, a gate, and a source connected to a drain of a second transistor of said pair, said second transistor of said pair having a source connected to said power supply terminal, and a gate connected to a modulation current control terminal; and
- a cascade of CMOS inverter stages having an input terminal receiving digital signals and an output connected to said gate of said first transistor of said pair, said bias current and said modulation current having values depending only upon voltages applied to said bias current control terminal and applied to said modulation current control terminal and said input terminal, respectively.

5,589,787

CELL FOR SHIFT REGISTER

Charles Odinet, La Tronche, France, assignor to SGS-Thomson Microelectronics, S.A., Gentilly, France


Filed May 18, 1995, Ser. No. 443,808

Claims priority, application France, May 20, 1994, 94 06491

Int. Cl.⁶ H03K 3/289

U.S. Cl. 327—202


29 Claims



1. A cell for a shift register designed for the injection, into a transmission line, of a binary value or for the sampling of the value of the signal present in said line, this cell comprising:

- a parallel input connected to the line to receive a parallel input signal (Pin);
 - a parallel output connected to the line to give a parallel output signal (Pout);
 - a series input to receive a series input signal (Sin) to be shifted into a following cell or to be injected into the line;
 - a series output to give a series output signal (Sout) to a series input of a following cell;
- wherein the parallel input and the parallel output are connected and wherein the parallel output is separated from the rest of the cell by a tristate buffer circuit.


6 Claims



Filed Oct. 17, 1994, Ser. No. 323,776
Claims priority, application Japan, Oct. 16, 1993, 5-281904;
Oct. 26, 1993, 5-266821; Dec. 29, 1993, 5-352432


U.S. Cl. 327—278 2 Claims

1. A bus driver circuit comprising:
a plurality of first transistors connected between a data input terminal and a data output terminal, and
a plurality of controlling transistors;
wherein sources of said plurality of first transistors are connected to drains of said plurality of controlling transistors; and
wherein gates of said plurality of controlling transistors are connected to receive control signals for selectively turning



**Michael J. Allen, Rescue, Calif., assignor to Intel Corporation,
Santa Clara, Calif.**

Filed Jun. 30, 1995, Ser. No. 496,872
Int. Cl.⁶ H03K 19/0175; G06F 13/00

U.S. Cl. 327—333 3 Claims

3669


- a first node that receives the legacy signal;
- a resistor voltage divider coupled to the first node that divides the legacy signal to the low voltage logic level range at a first center tap;
- a capacitor voltage divider coupled to the first node and having a second center tap coupled to the first center tap;
- a diode that clamps the center taps to approximately a supply voltage, the diode being coupled between the center taps and the supply voltage;
- a transistor coupled in series with the resistor voltage divider, the transistor having a gate that controls a current flow there-through; and

wherein the first and second center taps are coupled to the internal logic of the digital IC such that the legacy signal, at the low voltage logic level range, is transmitted to the internal logic effectively without delay.

5,589,791
**VARIABLE GAIN MIXER HAVING IMPROVED
 LINEARITY AND LOWER SWITCHING NOISE**
 Barrie Gilbert, Portland, Oreg., assignor to Analog Devices,
 Inc., Norwood, Mass.

Filed Jun. 9, 1995, Ser. No. 489,129
Int. Cl.⁶ G06G 7/16

U.S. Cl. 327-359 36 Claims




a second current source connected to the cathode of the second diode.

5,589,792
RESISTOR PROGRAMMABLE TEMPERATURE SWITCH
A. Paul Brokaw, Burlington, Mass., assignor to Analog Devices
Inc., Norwood, Mass.

Int. Cl.⁶ H01L 35/00; G05F 1/10; 3/16

U.S. Cl. 327-512 6 Claims



5,589,793


**VOLTAGE BOOSTER CIRCUIT OF THE CHARGE-PUMP
TYPE WITH BOOTSTRAPPED OSCILLATOR**

Christian G. Kassapien, Marseille, France, assignor to SGS-Thomson Microelectronics S.A., Saint Genis Pouilly, France
Filed Sep. 29, 1993, Ser. No. 128,871

Claims priority, application France, Oct. 1, 1992, 92 11751
Int. Cl.⁶ H03K 3/00

U.S. Cl. 327—536 23 Claims

1. A charge pump comprising:
 - a stage of a voltage-boosting circuit comprising a transistor and a capacitor; and
 - a transistor switching control circuit coupled to the stage and controlling the switching of the transistor, the transistor switching control circuit comprising:




- a ring oscillator generating an oscillator signal at an oscillator frequency;
- a phase splitter stage receiving the oscillator signal and generating a plurality of non-overlapping phase-split signals substantially at the oscillator frequency;
- a non-bootstrapped output stage, receiving the plurality of non-overlapping phase-split signals, and generating a plurality of non-bootstrapped non-overlapping output signals that switch between a zero voltage and a supply voltage substantially at the oscillator frequency; and
- a bootstrapped output stage, receiving the plurality of non-overlapping phase-split signals, and generating a plurality of bootstrapped non-overlapping output signals that switch between the zero voltage and a voltage of greater magnitude than the supply voltage substantially synchronously with the non-bootstrapped non-overlapping output signals.

5,589,794
DYNAMICALLY CONTROLLED VOLTAGE REFERENCE
CIRCUIT

David C. McClure, Denton, Tex., assignor to SGS-Thomson
Microelectronics, Inc., Carrollton, Tex.
Filed Dec. 20, 1994, Ser. No. 360,227
Int. Cl.⁶ G05F 1/10

U.S. Cl. 327—538 19 Claims



1. A voltage reference circuit, comprising:
- a first reference transistor, having a source/drain path connected on a first end to a power supply voltage, and having a gate connected to a drain end of its source/drain path;
 - a second reference transistor having a source/drain path connected between a second end of the first reference transistor and a common node, and having a gate for receiving a bias voltage;


- a first mirror transistor, having a source/drain path connected between the power supply voltage and an output node, and having a gate connected to the gate of the first reference transistor;
- a second mirror transistor, having a source/drain path connected between the output node and the common node, and having a gate coupled to the output node; and
- a switchable bias current source, coupled to the common node, for conducting a current including the sum of the currents in the second reference transistor and the second mirror transistor at a first level responsive to a select signal being at a first logic level, and at a second level lower than the first level responsive to the select signal being at a second logic level, wherein the select signal is a clock signal.

5,589,795
METHOD AND ARRANGEMENT FOR CONTROLLING A
LOOP FILTER

Matti Latva-Aho, Oulu, Finland, assignor to Nokla Mobile Phones Ltd., Salo, Finland

Filed Dec. 19, 1994, Ser. No. 359,049
Claims priority, application Finland, Dec. 23, 1993, 935837
Int. Cl.⁶ H03K 5/00

U.S. Cl. 327—553 6 Claims



4. Apparatus for controlling a loop filter in a digital phase lock circuit, said phase lock circuit having a phase comparator, a loop filter, a clock, a local oscillator and a divider, said loop filter comprising:


- a first integrator in the loop filter, said first integrator having an input coupled to an output of the phase comparator;
- a first threshold detector coupled to an output of said first integrator, said first detector having an output coupled to the clock;
- a second integrator;
- a first means for providing an absolute value, said first means coupling an input of said second integrator to the output of the phase comparator;
- a second threshold detector operatively coupled to an output of said second integrator; and
- an OR gate having a first input connected to the output of said second threshold detector; and
- a second means for providing an absolute value, said second means connecting a second input of said OR gate to the output of said first threshold detector, an output of said OR gate being connected to inputs of said first and second integrators for controlling said first and second integrators to reduce, when in a predetermined logic state, an output signal of said first and second integrators.

5,589,796
METHOD AND APPARATUS FOR INCREASING
AMPLIFIER EFFICIENCY

William P. Alberth, Jr., Crystal Lake; John J. Janssen, Round Lake Beach, and Armin Klomdsdorf, Grayslake, all of Ill., assignors to Motorola, Inc., Schaumburg, Ill.
Filed Nov. 1, 1994, Ser. No. 332,968

Int. Cl.^b H03G 3/30

U.S. Cl. 330—133 **13 Claims**
13. A method of controlling amplifying circuitry of an RF communication device, the amplifying circuitry coupled to a power



source and having a first and a second input, an output, a saturation point, a gate bias responsive to a gate voltage signal, and amplifying an input signal into an amplified output signal having one of a plurality of power levels, the input signal coupled to the first input of the amplifying circuitry, the gate voltage signal coupled to the second input of the amplifying circuitry, the amplified output signal coupled to the output of the amplifying circuitry, the method of controlling the amplifying circuitry comprising the steps of:

- (a) causing the amplifying circuitry to attenuate in a forward isolation mode;
- (b) boosting the amplifying circuitry, when the RF communication device is outside of a range of normal communications, such that the amplified output signal has a power level greater than the plurality of power levels to maintain communication; and
- (c) dynamically varying the gate voltage signal, when the RF communication device is functioning within the range of normal communications, for operating the amplifying circuitry as close to the saturation point as possible without preventing the amplifying circuitry from maintaining the amplified output signal at a preferred one of the plurality of power levels.


5,589,797
LOW DISTORTION AMPLIFIER
Michael J. Gans, Monmouth Beach, and Yu S. Yeh, Freehold,
both of N.J., assignors to Lucent Technologies Inc., Murray
Hill, N.J.

Filed Sep. 26, 1995, Ser. No. 534,371
Int. Cl.⁶ H03F 1/26

U.S. Cl. 330—149

20 Claims

U.S. Cl. 330—149 20 Claims



1. A cuber circuit for converting a time varying input signal into an output signal having at least a third order distortion component, comprising:


- an antiparallel diode arrangement including a first diode having a first cathode and a first anode, said first anode being coupled to a first circuit node, and a second diode having a second anode and a second cathode, said second cathode being coupled to said first circuit node;
- a biasing circuit arrangement coupled to said antiparallel diode arrangement for causing D.C. bias current to flow through

5,589,798
INPUT STAGE IMPROVEMENT FOR CURRENT
FEEDBACK AMPLIFIERS

Barry Harvey, Los Altos, Calif., assignor to Elantec, Milpitas, Calif.

Continuation of Ser. No. 245,683, May 18, 1994, Pat. No. 5,418,495. This application May 19, 1995, Ser. No. 444,932
Int. Cl.⁶ H03F 3/26; 1/14

U.S. Cl. 330-263 3 Claims



1. An input stage for a current feedback amplifier having a positive input terminal (V_{IN+}), a negative input terminal (V_{IN-}) with a parasitic capacitance (C_{IN}) and a gain node (G) connected to an output buffer, the input stage comprising:

- a first pair of emitter follower transistors having bases coupled to the positive input (V_{IN+}), emitters coupled to the negative input (V_{IN-}) and collectors;
- a capacitor (C^*) having a first end connected to a reference potential and a second end;
- a second pair of emitter follower transistors having bases coupled to the positive input (V_{IN+}), emitters coupled to the second end of the capacitor (C^*) and collectors;
- a first pair of current mirrors, each current mirror having an input connected to the collector of one transistor of the first pair of emitter follower transistors and an output connected to the gain node (G); and
- a second pair of current mirrors, each current mirror having an input connected to the collector of one transistor of the second pair of emitter follower transistors and an output connected to the collector of one transistor of the first pair of emitter follower transistors.

5,589,799

LOW NOISE AMPLIFIER FOR MICROPHONE


Peter L. Madaffari, Camden, and James S. Collins, Lincolnville, both of Me., assignors to Tibbetts Industries, Inc., Camden, Me.

Continuation of Ser. No. 314,694, Sep. 29, 1994, abandoned.
This application May 23, 1995, Ser. No. 447,349

Int. Cl.⁶ H03F 3/16

U.S. Cl. 330—277

12 Claims



1. A preamplifier for a high impedance microphone comprising, in combination,

first and second stages each comprising a JFET connected in follower mode, each stage having a gate to ground input impedance, an output impedance connected from its source to ground independently of said input impedance and a drain connected to a power supply terminal, the source of the first stage JFET having a circuit connection to the gate of the second stage JFET, the size of the first stage JFET being less than half, and the size of the second stage JFET being more than twice, the size of a 2N4338 transistor considered as a standard for reference purposes.

5,589,800

DUAL VOLTAGE LEVEL SHIFTED, CASCODED CURRENT MIRROR


Kirk D. Peterson, Plano, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Continuation of Ser. No. 313,526, Sep. 26, 1994, Pat. No. 5,515,010. This application Jun. 7, 1995, Ser. No. 481,907

Int. Cl.⁶ H03F 3/16

U.S. Cl. 330—288

22 Claims



1. A method for biasing a current mirror circuit having an input terminal; an output terminal; a common voltage terminal; first and second transistors having sources commonly connected to said common voltage terminal, gates commonly connected to each other, and drains; third and fourth transistors having sources respectively connected to said drains of said first and second transistors, gates, and drains respectively connected to said input and output terminals; said method comprising:

providing said third and fourth transistors with commonly connected gates;

providing a fifth transistor having a source connected to said commonly connected third and fourth transistor gates, a gate connected to said third transistor drain, and a drain;

flowing a current through said fifth transistor, for applying a forward biasing voltage at said commonly connected third and fourth transistor gates equal to an input voltage applied at said input terminal, shifted by a voltage differential between said fifth transistor gate and source; and

applying a forward biasing voltage at said commonly connected first and second transistor gates.

5,589,801

PHASE COMPARATOR CIRCUIT AND PHASE SYNCHRONIZATION CIRCUIT

Takaya Yamamura, and Kunihiko Esaki, both of Kanagawa, Japan, assignors to Sony Corporation, Tokyo, Japan


Filed Nov. 15, 1995, Ser. No. 558,789

Claims priority, application Japan, Nov. 21, 1994, 6-286278

Int. Cl.⁶ H03L 7/085; 7/093

U.S. Cl. 331—14

9 Claims



1. A phase comparison circuit for use in generating clock pulses comprising:

detection means for detecting phase information present in an input signal;

error detection means for detecting a phase error with respect to the phase of the input signal;

switching means for switching between the phase error detected by the error detection means and a plurality of fixed values of phase error; and

control means for controlling switching of said switching means, wherein said control means includes first storage means for

storing past m portions of the phase information detected by said detection means, second storage means for storing past m

portions of a frequency comparison state of the clock pulses, setting means for setting a current frequency comparison state

from the phase information detected by said detection means, the phase information being stored in said first storage means

and the frequency comparison state being stored in said second storage means, and selection means for selecting the

phase error output by said switching means based upon the frequency comparison state as set by said setting means and a

sign of the phase error detected by said error detection means.

5,589,802

CIRCUIT FOR DETECTING THE ABSENCE OF AN EXTERNAL COMPONENT

Timothy G. O'Shaughnessy, Blackforest, Colo., and David G. Brown, Pocatello, Id., assignors to American Microsystems, Inc., Pocatello, Id.

Filed Jun. 7, 1995, Ser. No. 479,302

Int. Cl.⁶ G01R 27/14; 27/26; H03K 3/0231; H03B 5/20


U.S. Cl. 331—44

30 Claims

10. A resistor detecting circuit comprising:

a biasing circuit coupled to the resistor, the biasing circuit generating a bias current;

a bias current threshold detector coupled to the biasing circuit; and



means coupled to the bias current threshold detector for generating a signal indicative that the bias current is lower than threshold;

wherein the signal generating means comprises:

a NOR gate having a first input terminal coupled to a system clock timing signal generator and a second input terminal coupled to the bias current threshold detector.

5,589,803

Patent Not Issued For This Number

5,589,804

OSCILLATOR WITH IMPEDANCE BUFFER FOR INCREASED PULLABILITY


Stanley Wrzesinski, Arlington Heights, Ill., assignor to Motorola Inc., Schaumburg, Ill.

Filed Jul. 17, 1995, Ser. No. 502,998

Int. Cl.⁶ H03B 5/36; H03C 3/20

U.S. Cl. 331—116 R

10 Claims



1. A pullable overtone oscillator comprising:

an amplifier having an input and an output wherein the output of the amplifier forms an output of the pullable overtone oscillator;

a tuned circuit having an input coupled to the output of the amplifier, and an output; and

an emitter follower having an input coupled to the output of the tuned circuit, and an output coupled to the input of the amplifier.

5,589,805

ENHANCED RESOLUTION PULSE WIDTH MODULATION CONTROL

Jeffery A. Zuraski, Saginaw, and Mark P. Colosky, Vassar, both of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Nov. 6, 1995, Ser. No. 554,173


Int. Cl.⁶ H03K 7/08

U.S. Cl. 332—109

5 Claims

1. A method of increasing the effective resolution of a pulse width modulated output in a pulse width modulated system including a plurality of discrete pulse width modulated output states, said method comprising the steps:

determining a desired output state to be effected during a predetermined control period;



determining a first pulse width modulated output state as one of the two of the plurality of discrete pulse width modulated output states which immediately flank said desired output state;

determining a second pulse width modulated output state as the other of the two of the plurality of discrete pulse width modulated output states which immediately flank said desired output state;

executing said first pulse width modulated state for a first total duration during said predetermined control period;

executing said second pulse width modulated state for a second total duration during said predetermined control period;

said predetermined control period comprising said first and second total durations.

5,589,806

SURFACE ACOUSTIC WAVE FILTER HAVING PARALLEL/SERIAL RESONATOR CONNECTION BASED ON TRANSMITTING AND RECEIVING FREQUENCIES

Yutaka Taguchi, Ibaraki; Kazuo Eda, Nara; Shun-ichi Seki, Osaka, and Keiji Onishi, Settsu, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan


Filed Jan. 5, 1995, Ser. No. 368,981

Claims priority, application Japan, Jan. 12, 1994, 6-001476

Int. Cl.⁶ H03H 9/64

U.S. Cl. 333—193

6 Claims



1. A surface acoustic wave filter to be used in a receiving circuit of a communication apparatus configured for simultaneously transmitting a first signal having a predetermined transmitting frequency and receiving a second signal having a predetermined receiving frequency which is lower than the transmitting frequency, the surface acoustic wave filter comprising:

an input terminal for receiving an input signal;

an output terminal for providing an output signal; and

a plurality of surface acoustic wave resonators,

wherein the plurality of surface acoustic wave resonators include: at least one series surface acoustic wave resonator

connected in series to a signal line connecting the input terminal and the output terminal; and at least two parallel

surface acoustic wave resonators each connected between a ground and respective predetermined positions in the signal line, and

wherein one of the at least two parallel surface acoustic wave resonators is disposed most closely to the input terminal

among the plurality of surface acoustic wave resonators.

5,589,807

MULTI-MODE TEMPERATURE COMPENSATED FILTERS AND A METHOD OF CONSTRUCTING AND COMPENSATING THEREFOR


Wai-Cheung Tang, Ontario, Canada, assignor to COM Dev. Ltd., Cambridge, Canada

Filed Jun. 7, 1995, Ser. No. 475,656

Claims priority, application Canada, Jul. 7, 1994, 2127609
Int. Cl.⁶ H01P 1/208; 7/06

U.S. Cl. 333-212

48 Claims



1. A microwave filter comprising an input and output and a first cavity made of a material having a coefficient of thermal expansion and resonating at an operating frequency in at least two orthogonal modes substantially simultaneously, said cavity having a volume that is changeable with temperature, said cavity containing solid dielectric material having a dielectric constant that varies with temperature, said dielectric material being sized so that it does not resonate at the operating frequency of the cavity, there being at least one amount of said dielectric material having a value of a temperature coefficient of the dielectric constant to compensate for changes in the volume of the cavity with temperature to at least reduce a variation in said operating frequency that would otherwise be caused by a temperature-induced volume change of said cavity.

5,589,808

ENCAPSULATED TRANSFORMER


William A. Clark; Carl C. Strickland, Jr., both of Kinston, and Mark C. Newman, LaGrange, all of N.C., assignors to Cooper Industries, Inc., Houston, Tex.

Division of Ser. No. 104,484, Jul. 28, 1993, abandoned. This application Aug. 12, 1994, Ser. No. 289,534

Int. Cl.⁶ H01F 27/02; 27/30

U.S. Cl. 336-92

10 Claims



1. An encapsulated transformer, comprising:
a transformer coil assembly that includes a core having a hollow interior, primary wire windings and secondary wire windings; at least one primary lead connected to the primary windings; at least one secondary lead connected to the secondary windings;
a rigid core insert having an upstanding portion positioned within the hollow interior of the core and a base portion on which the transformer coil assembly rests, said core insert having a hole which extends through the base portion and into

the upstanding portion wherein the base portion of said core insert has an end face which faces away from said upstanding portion, said end face having at least one groove formed therein that extends from the hole in the core insert to an outer edge of the end face to communicate the hole in the core insert with the outer edge of the end face;
a unitary thermoplastic rubber jacket surrounding the transformer coil assembly and bonded to the base portion of the core insert to provide a completely waterproof encapsulated transformer.


5,589,809

THERMAL OVERLOAD RELAY WITH MIS-READJUSTMENT PREVENTING DEVICE

Kunlyuk Kogawa, and Koetsu Takaya, both of Kawasaki, Japan, assignors to Fuji Electric Co., Ltd., Kawasaki, Japan
Filed Mar. 7, 1995, Ser. No. 399,990Claims priority, application Japan, Mar. 15, 1994, 6-043472
Int. Cl.⁶ H01H 61/00

U.S. Cl. 337-36

9 Claims



1. A thermal overload relay comprising:
a case for retaining a relay, said case having an insertion hole and first coupling means formed around the insertion hole; means for adjusting a working current of the relay situated inside the insertion hole; and
a cover for covering said adjusting means situated in the insertion hole, said cover being formed of a transparent plate and including a side surface, a smooth upper surface, second coupling means formed on the side surface and engageable with the first coupling means, and a handle formed on the upper surface of the cover for handling the cover and being shaped and made of a material cuttable along the upper surface thereof, said cover, when disposed in the insertion hole to engage the first and second coupling means, being positioned such that the upper surface of the cover is located below an upper surface of the case and the handle projects outwardly from the upper surface of the case.

5,589,810

SEMICONDUCTOR PRESSURE SENSOR AND RELATED METHODOLOGY WITH POLYSILICON DIAPHRAGM AND SINGLE-CRYSTAL GAGE ELEMENTS

Clifford D. Fung, Mansfield, Mass., assignor to The Foxboro Company, Foxboro, Mass.


Continuation-in-part of Ser. No. 38,664, Mar. 26, 1993, Pat. No. 5,357,808, which is a division of Ser. No. 676,914, Mar. 28, 1991, Pat. No. 5,220,838. This application Mar. 18, 1994, Ser. No. 210,422

Int. Cl.⁶ G01L 1/22

U.S. Cl. 338-4

9 Claims

1. Semiconductor pressure sensor apparatus comprising
A. a polysilicon diaphragm having opposed first and second surfaces,
B. an etched silicon substrate supporting said diaphragm at said first surface for deflection of said diaphragm in response to a pressure difference between said first and second surfaces,



C. first means forming single-crystal silicon piezoresistive sensing means mounted with said first surface of said diaphragm for sensing deflection of said diaphragm,
D. dielectric isolation means of silicon oxide disposed for dielectrically isolating said sensing means, and
E. first interconnection means in circuit with said sensing means for external electrical connection to said pressure sensor.

5,589,811

POWER DOOR SAFETY SENSING STRIP


Robert Pariot, New Windsor, N.Y., and J. Mortimer Traugott, Riverton, N.J., assignors to Techstrip, Inc., Oaklyn, N.J.

Filed Jun. 22, 1995, Ser. No. 493,624

Int. Cl.⁶ H01C 3/00

U.S. Cl. 338-210

8 Claims



1. A door safety sensing strip for attachment to a power door for sensing an object obstructing closure of the door comprising a flexible insulating elongated tubular member having a bell-like shaped cross section, the tubular member being formed by an arcuate deformable portion connected by flexible sidewalls to a narrow section, a wide inner face on the arcuate portion facing the narrow section, a first flexible conductive surface on the wide inner face, a flat flexible insulating member fastened to and extending from the narrow section of the tubular member into contact with and substantially perpendicular to the conductive inner surface, second flexible conductive surfaces on opposite sides of the flat insulating member located near the first conductive inner surface of the tubular member, whereby deformation of the tubular member will result in electrical contact between the first conductive inner surface of the tubular member and at least one of the second conductive surfaces on the flat insulating member due to bending of the flat insulating member causing said at least one second conductive surface to rotate toward a parallel relationship with and engage the first conductive surface to form an electrical contact.

5,589,812


PERSONAL METER TIMING DEVICE

Rickey A. Jones, 1248 W. 127th St., Los Angeles, Calif. 90044
Filed Jan. 6, 1995, Ser. No. 369,714Int. Cl.⁶ G08B 1/00; G07F 7/00

U.S. Cl. 340-309.15

5 Claims

1. A portable parking meter timing device comprising:



an electrical circuit having a plurality of electrical components including a power source, a timing duration programming means, a timing means, a time set and remaining display means, an audible warning means, and a power switch, the components interconnected to enable programming of a selected timing duration, timing said timing duration, and providing an audible warning signal when said timing duration is completed;

a case providing a front and a rear opposing walls and a plurality of side walls interconnecting the front and rear walls and providing rigidity to the case and fully enclosing an interior space within the walls for holding the electrical circuit, an aperture in the rear wall for accepting coins for storage therein, the rear wall further providing, mounted pivotally thereon, a clip capable of attaching the case to a support element, and a window enabling observation of the display means, and an actuation means enabling the setting of a timing duration into the timing duration programming means, the silencing of the audible alarm means, and the turning of the timing device off and on.

5,589,813

DATA COMMUNICATION SYSTEM OF THE FIELD BUS TYPE WITH A TWIN LEAD FOR POWER SUPPLY TO CONNECT UNITS AND FOR DATA TRANSMISSION BETWEEN THE UNITS

Ole C. Nielsen, Asger Jorns Vej 18, DK-8600 Silkeborg, Denmark


PCT No. PCT/DK92/00302, § 371 Date Apr. 13, 1994, § 102(e) Date Apr. 13, 1994, PCT Pub. No. WO93/08652, PCT Pub. Date Apr. 29, 1993

PCT Filed Oct. 14, 1992, Ser. No. 211,703

Claims priority, application Denmark, Oct. 14, 1991, 1732/91
Int. Cl.⁶ H04M 1/104

U.S. Cl. 340-310.01

6 Claims



1. A field bus data communication system comprising:
a twin lead cable;
a plurality of electronic units connected to the twin lead cable, each electronic unit including a current pulse generator which generates current pulse trains modulating current flow on the twin lead cable to produce current flow between the electronic units on the twin lead cable; and wherein
each electronic unit is contained in a conductive housing having at least one capacitor coupled between the conductive housing

and the electronic unit which equalizes capacitance between the conductive housing and respective terminals of the electronic unit and has a dynamic clamp circuit coupled to the twin lead cable for limiting alternating current voltage variations on the twin lead cable to be below a maximum value to minimize reflections on the twin lead cable and has a pair of diodes coupled in an anti-parallel configuration to each other with the anti-parallel configuration having terminals electrically coupled between the twin lead cable.

5,589,814

ANTI-THEFT VEHICLE SECURITY SYSTEM


John Smith, Jr., 2635 Sawmill Rd., N. Bellmore, N.Y. 11710

Filed Nov. 14, 1994, Ser. No. 369,217

Int. Cl.⁶ B60K 25/10

U.S. Cl. 340-426

9 Claims



1. An anti-theft security system for a motor vehicle, comprising: a double pane front windshield in a motor vehicle, comprising two spaced-apart window panes defining a chamber therebetween, said chamber having a top end and a bottom end; an extensible and retractable opaque curtain positioned within said chamber for movement between a retracted position in which said curtain is retracted to allow an uninhibited driving view through said front windshield and an extended position in which said curtain extends from the top to the bottom of said chamber to block the driving view through said front windshield, said curtain being configured and dimensioned to generally span said chamber from said top end to said bottom end of said chamber and across the width of the same when in said extended position thereof;
- a control switch having an on position and an off position for arming and disarming said system;
- means for automatically moving said curtain from said retracted position to said extended position; and
- a trigger mechanism for activating said means for automatically moving said curtain upon activation of the trigger mechanism when said control switch is in an on position.

5,589,815

SYSTEM FOR DETERMINING PNEUMATIC TIRE PRESSURE FOR MOTOR VEHICLE

Takashi Nishihara; Toru Ikeda; Osamu Yano, and Shuji Shiraishi, all of Wako, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Oct. 26, 1994, Ser. No. 329,941


Claims priority, application Japan, Nov. 2, 1993, 5-274521

Int. Cl.⁶ B60C 23/00

U.S. Cl. 340-444

3 Claims

1. A system for determining a pneumatic tire pressure of road wheels on a motor vehicle, comprising: first differential speed means for detecting a front rotational speed difference between rotational speeds of front left and right road wheels of the motor vehicle;
- second differential speed means for detecting a rear rotational speed difference between rotational speeds of rear left and right road wheels of the motor vehicle;
- running condition detecting means for detecting a running condition of the motor vehicle;
- reference differential speed calculating means for calculating a reference rotational speed difference between rotational



- speeds of the front left and right road wheels based on an output signal from said running condition detecting means;
- first pressure reduction determining means for comparing said front rotational speed difference and said rear rotational speed difference to determine a pneumatic tire pressure reduction of said front left and right road wheels or said rear left and right road wheels;
- second pressure reduction determining means for comparing said front rotational speed difference or said rear rotational speed difference and said reference rotational speed difference to determine a pneumatic tire pressure reduction of one of said front left and right road wheels or said rear left and right road wheels; and
- final pressure reduction determining means for determining a pneumatic tire pressure reduction from output signals from said first pressure reduction determining means and said second pressure reduction determining means based on at least a combination of a first ratio in said first pressure reduction determining means and a second ratio in said second pressure reduction determining means corresponding to one of: (a) at least a steering angle, (b) at least a yaw rate, and (c) at least a lateral acceleration of said motor vehicle.

5,589,816

METHOD AND DEVICE FOR DETECTING A DEFLATED TIRE ON A VEHICLE

David Jones, Lichfield, England, assignor to Sumitomo Rubber Industries, Ltd., Hyogo, Japan

PCT No. PCT/JP94/00501, § 371 Date Nov. 16, 1994, § 102(e) Date Nov. 16, 1994, PCT Pub. No. WO94/22681, PCT Pub. Date Oct. 13, 1994


PCT Filed Mar. 29, 1994, Ser. No. 335,822

Claims priority, application United Kingdom, Apr. 1, 1993, 9306846.8

Int. Cl.⁶ B60C 23/00

U.S. Cl. 340-444

25 Claims



1. A method of detecting a deflated tire on a vehicle comprising the steps of: comparing the rolling radii of the tires by comparing angular velocity signals from wheel speed sensors one at each wheel;

calculating an error value (DEL') where

$$DEL' = \frac{[(C1 + C4)/2 - (C2 + C3)/2] \times 100}{(C1 + C2 + C3 + C4)/4}$$

where C1, C2, C3 and C4 are angular velocity values for left-hand front, right-hand front, left-hand rear and right-hand rear wheels of the vehicle respectively;

determining a correction factor;

calculating a corrected error signal (DEL) where

$$DEL = DEL' - DELCOR$$

wherein

$$DELCOR = (LAT \times A) + (B \times LAT^2)$$

wherein

A and B are vehicle related constants;

outputting a warning signal when a magnitude of the corrected error signal is between 0.05 and 0.5; and

operating a tire warning indicator indicating that at least one tire is deflated when said warning signal is output.

5,589,817

EARLY WARNING BRAKE LIGHT SYSTEM

Geoffrey M. Furness, 14 Fordyce Avenue, Auckland, New Zealand

PCT No. PCT/NZ93/00110, § 371 Date Jul. 12, 1995, § 102(e)

Date Jul. 12, 1995, PCT Pub. No. WO94/11221, PCT Pub.

Date May 26, 1994


PCT Filed Nov. 11, 1993, Ser. No. 428,205

Claims priority, application New Zealand, Nov. 18, 1992, 245165

Int. Cl.⁶ B60Q 1/50

U.S. Cl. 340-467

22 Claims



17. A method of operating a warning signal indicative or reasonably indicative of a vehicle about to be braked or severely decelerated, said method comprising:

- (i) generating with a piezoelectric transducer an electrical signal indicative of a rate of change in the pressure or force (hereafter "foot pressure signal") being applied to the accelerator of the vehicle;
- (ii) optionally generating an electrical signal indicative of the speed of the vehicle (hereafter "speed signal");
- (iii) (a) comparing, in a monitoring circuit receiving said foot pressure signal, negative values (ie. those of a rate of decrease of pressure) of said foot pressure signal against a threshold level to provide a determination of whether or not there is likely to be a panic stop or not;
- (b) optionally comparing in a monitoring circuit receiving said speed signal, values of said speed signal to determine whether said vehicle is travelling in excess of a speed threshold;
- (iv) if the comparison is step (iii) provides a determination of there being a likely panic stop providing at least for a brief period of time an electrical current actuation of said warning signal.

5,589,818

PERSONAL RESPONSE SYSTEM WITH REMOTELY ADJUSTABLE MICROPHONE SENSITIVITY


Andrew Queen, 4744 S. Ocean Blvd., Highland Beach, Fla. 33487

Filed Aug. 27, 1993, Ser. No. 113,274

Int. Cl.⁶ G08B 29/00; 1/00; 23/00; H04M 11/04

U.S. Cl. 340-506

16 Claims



1. A personal response system with emergency audio mode, comprising:

- a response center for monitoring a plurality of help consoles for emergency status conditions, the response center further having means to transmit microphone sensitivity commands; at least one help console for use in a user's premises, further comprising:
- a microphone sensitivity control;
- a communications control to communicate with the response center, the communications control capable of receiving microphone sensitivity commands from the response center which define gradual changes in microphone sensitivity and further having means to control the microphone sensitivity control;
- the microphone sensitivity control is controlled by the communications control and has an output for adjusting microphone sensitivity levels;
- a microphone means to input and transmit audio signals from the help console to the response center, the sensitivity of the microphone means controlled by the microphone sensitivity control such that a single microphone in the microphone means can have its sensitivity adjusted to extend from the immediate area of the microphone to several rooms within the user's premises; and
- a speaker to output audio signals received from the response center;
- whereby the response center can gradually adjust the microphone sensitivity of the help console such that the physical listening range of a single microphone in the help console can be gradually increased from the immediate area of the help console to several rooms within the user's premises.

5,589,819

SELF-SOUNDING TAG ALARM

Harumi Takeda, Osakasayama, Japan, assignor to Takeda Technological Research Co., Ltd., Osaka, Japan

Filed Aug. 18, 1994, Ser. No. 292,750


Claims priority, application Japan, Aug. 23, 1993, 5-230935

Int. Cl.⁶ G08B 13/14

U.S. Cl. 340-571

6 Claims

1. A self-sounding tag alarm apparatus for use on a commodity to prevent shoplifting, said apparatus comprising:
- a main housing;
- coupling means for detachably attaching the main housing to the commodity;
- alarm generating means mounted in said main housing for generating an alarm;



detecting means for detecting at least one of a signal of a particular frequency produced externally of said main housing and removal of said coupling means;

reset signal input means on said main housing for having a reset signal applied thereto, said reset signal being provided externally of said main housing, said reset signal input means including a resonator circuit for detecting an electromagnetic wave of a predetermined frequency, said electromagnetic wave of a predetermined frequency being different from the signal of a particular frequency produced externally of said main housing, and a comparator, said comparator being enabled when an output of said resonator circuit exceeds a predetermined level; and


reset signal generating means for generating the electromagnetic wave of a predetermined frequency, said electromagnetic wave of a predetermined frequency being a reset signal, said reset signal generating means including an oscillator coil disposed in a flat housing.

5,589,820
RETAIL THEFT PREVENTION AND INFORMATION
DEVICE

Donald G. Robinson; Michael W. Geatz, both of Fargo, N. Dak., and Michael J. Corcoran, Bend, Oreg., assignors to PAC/SCAN, Inc., Bismarck, N. Dak.
Continuation of Ser. No. 131,663, Oct. 5, 1993, abandoned.
This application Oct. 11, 1995, Ser. No. 540,901
Int. Cl.⁷ G08B 13/18

U.S. Cl. 340—572

18 Claims



1. A device adapted to be associated with a product for preventing theft of the product and for emitting a code identifying the product, the device comprising:

- frequency activation means for receiving a frequency signal generated by an external source and for generating an activation signal;
- a piezoelectric device for receiving the activation signal;
- power means for supplying power only after the activation signal is received;
- memory means for storing the code, the memory means being coupled to the power means to output the code when power is supplied to the memory means;
- switch means with normally open contacts coupled between the memory means and the power means, the switch means being operable in response to the piezoelectric device to couple the power means to the memory means upon the piezoelectric


device receiving the activation signal initiated by the frequency activation means; and
transmitter means for transmitting the code received from the memory means.

5,589,821
DISTANCE DETERMINATION AND ALARM SYSTEM
Roy Sallen, Wayland; W. James Budzyna, Whitinsville, and
Charles E. Sawabini, Carlisle, all of Mass., assignors to
Secure Technologies, Inc., Boston, Mass.

Filed Dec. 13, 1994, Ser. No. 355,041
Int. Cl.⁶ G08B 21/00

U.S. Cl. 340—573

4 Claims



1. A system, of the type having a plurality of transceiver units for generating an alarm when a child transceiver unit is more than a predetermined distance away from a parent transceiver unit, the system comprising:

- (a) a portable parent unit;
- (b) a first transmitter portion, disposed in the parent unit, the first transmitter portion having:
 - (i) a first rf transmitter, operative at a first carrier frequency, having an output;
 - (ii) a signal generator for generating a first reference signal;
 - (iii) a first FM modulator, coupled to the first rf transmitter, for modulating the first carrier with the first reference signal;
 - (iv) a first digital encoder for digitally encoding the FM-modulated carrier with a digital signature to identify the output of the first transmitter;
- (c) a portable child unit of a size permitting it to be worn by a human subject, the child unit having:
 - (i) a second receiver, tuned to the first carrier frequency, for receiving a signal broadcast from the output of the first transmitter;
 - (ii) a digital decoder for decoding the digital signature from the signal received by the second receiver and providing a decoded output;
 - (iii) an inhibitor arrangement, coupled to the digital decoder, for preventing transmission by the child unit unless the decoded output meets criteria stored in the child unit;
 - (iv) a second rf transmitter, operative at a second carrier frequency, and having an output; and
 - (v) a second FM modulator, coupled to the second rf transmitter and to the second receiver, for modulating the second carrier with a second reference signal having a pre-specified phase relationship to the first reference signal as received by the second receiver;
- (d) a first receiver portion, disposed in the parent unit, the first receiver portion having:
 - (i) a first receiver, tuned to the second carrier frequency, for providing an output of the demodulated second reference signal;
 - (ii) a distance resolver, coupled to the first receiver and the signal generator, for providing an output signal dependent on the phase relationship, between the first reference signal

(iii) an alarm, coupled to the distance resolver, triggered if the output signal from the distance resolver, exceeds a specified maximum distance.

5,589,822


**SYSTEM FOR DETECTING ICE OR SNOW ON
SURFACE WHICH SPECULARLY REFLECTS LIGHT**
Howard Stern, Greenlawn, N.Y., assignor to Robotic Vision
Systems, Inc., Hauppauge, N.Y.

Continuation-in-part of Ser. No. 963,840, Oct. 20, 1992, Pat.
No. 5,475,370. This application Dec. 16, 1994, Ser. No.

U.S. Cl. 340—583

Int. Cl.⁶ G08B 19/02

26 Claims



1. A method for detecting on a surface which specularly reflects light, a presence of a polarization altering substance comprising the steps of:


transmitting light over a transmitting path to said surface;
receiving said transmitted light over a receiving path for said
transmitted light from said surface and from said substance
alternately in optical isolator and optical nonisolator states;
measuring a first intensity of light received in said optical
non-isolator state;
measuring a second intensity of light received in said optical
isolator state; and
comparing said first and second intensities of received light to a
plurality of reference data to detect the presence of said
substance on said surface.

5,589,823
REMOTE STATUS INDICATOR FOR HOLDING TANKS
CONTAINING NO MOVING PARTS

Robert Lange, 18652 Midway, Allen Park, Mich. 48101
 Filed Dec. 29, 1994, Ser. No. 365,702
 Int. Cl.⁶ G08B 21/00

U.S. Cl. 340-622

20 Claims




1. A transistor and integrated circuit-free device for remotely indicating the fill status of a liquid-containing holding tank on a recreational vehicle or pleasure boat having a direct current voltage supply, comprising:

- (a) at least one sensing element comprising a support adapted to be inserted in a holding tank;
- (b) a plurality n of sensor elements fixedly mounted to said sensing element, said sensor elements positioned at different heights relative to said liquid contained in said tank, the height of each of said sensor elements corresponding to a level of liquid whose status is to be monitored, each of said sensor elements comprising a positive temperature coefficient resistor characterized by a resistance/temperature curve exhibiting relatively low resistance below a given temperature, and a steeply rising resistance above said given temperature;
- (c) a parallel electrical circuit having n branches, said parallel electrical circuit biased by said direct current voltage supply, each of said branches comprising at least one of said sensor elements and a current limiting resistor associated therewith;
- (d) a plurality of light emitting diodes having a non-emitting off-state and an emitting on-state, mounted remotely from said sensor elements, each of said light emitting diodes associated with a branch of said parallel circuit such that the on/off-state of said light emitting diode changes in response to said liquid level passing the position of the sensor element which forms a part of the same parallel circuit branch with which said light emitting diode is associated.

5,589,824
MULTI-SENSOR DETECTION SYSTEM
Adam Q. Lynch, 75 N. Lakeside Dr., Madison, Ind. 47250
Filed Nov. 9, 1995, Ser. No. 556,201
Int. Cl.⁶ G08B 17/10

U.S. Cl. 340—628

17 Claims



1. An alarm for sensing a plurality of conditions of an ambient air comprising:

- a housing, said housing having a generally triangular configuration and including:
- first, second and third lobes at corners of said housing;
 - perforations in a lower surface of said housing and at said lobes for passage of the ambient air therethrough;
 - a perforated central portion in said lower surface of said housing for passage of sound therethrough;
- an alarm circuit in said housing comprising:
- a power source for said circuit;
 - an alarm adjacent said central portion of said housing;
 - an air sensor in each respective lobe, each sensor causing a particular current flow to sound said alarm upon sensing a predetermined condition of the ambient air, the alarm sound passing through said central portion.

5,589,825

LOGGING OR MEASUREMENT WHILE TRIPPING
Daniel G. Pomerleau, Calgary, Canada, assignor to LWT Instruments Inc., Alberta, Canada


Filed Sep. 22, 1994, Ser. No. 310,840

Claims priority, application Canada, Jul. 6, 1994, 2127476

Int. Cl. G01V 3/00

U.S. Cl. 340—854.9

34 Claims



1. A drilling sub for receiving a logging tool through a drillstring, the logging tool having sensing and monitoring means for collecting and storing data from within a drillstring, the drilling sub comprising:

- a drilling sub body engageable with the drillstring;
- coupling means within the drilling sub body for engaging the logging tool within the drilling sub body; and
- hydraulically actuated window means on the drilling sub body responsive to the engagement of the logging tool within the drilling sub body, the window means to enable the sensing and monitoring means access to the well bore.

5,589,826

Patent Not Issued For This Number

5,589,827

INTERACTIVE METHOD FOR MONITORING ROAD TRAFFIC, AND ITS ONBOARD APPARATUS, AND SYSTEM FOR IMPLEMENTING THE METHOD

Mario Scurati, Milan, Italy, assignor to SGS-Thomson Microelectronics S.r.l., Agrate Brianza, Italy

Filed Apr. 26, 1994, Ser. No. 233,120

Claims priority, application European Pat. Off., May 11, 1993, 93830197


Int. Cl. G08B 1/00

U.S. Cl. 340—901

22 Claims

1. An interactive method for monitoring road traffic, comprising the steps of:

- detecting, through a receiver and a processor installed on a vehicle, said processor being coupled to said receiver, the presence of vehicles traveling ahead in the same running direction and their dynamic conditions; as transmitted in the form of a coded message from each of said preceding vehicles, at defined transmission time windows that are different for each vehicle, within a transmission period comprising a plurality of time windows;



detecting through said receiver and said processor, said transmission time windows and their position within said transmission period and

transmitting, through a transmitter installed on the vehicle, and capable of recognizing received messages, a coded message indicating at least the presence of said vehicle and dynamic conditions thereof to following vehicles, traveling in the same running direction, at separate time windows from said detected transmission time windows of the preceding vehicles whose presence has been detected.

5,589,828

6 DEGREES OF FREEDOM CONTROLLER WITH CAPABILITY OF TACTILE FEEDBACK


Brad A. Armstrong, 6630 Arabian Cir., Roseville, Calif. 95661

Filed Mar. 5, 1992, Ser. No. 847,619

Int. Cl. G05G 9/00

U.S. Cl. 341—20

18 Claims



14. A hand-operated controller allowing six bi-directional degrees of freedom of hand input force into a single handle, said controller comprising:

- said single handle movably supported by means for converting hand input force applied in any direction to said single handle into movement of said single handle in a direction substantially identical to the hand input force direction and relative to
- a stationary support base of said controller; whereby linear hand input force against said single handle absent rotational force can move said single handle purely linearly, and rotational hand input force against said single handle absent linear force can move said single handle purely rotationally;
- linear sensor means for sensing only linear movement of said single handle and producing electrical output signals indicative of linear hand input force direction against said single handle;

rotational sensor means for sensing only rotational movement of said single handle and producing electrical output signals indicative of rotational hand input force direction against said single handle.

15. An improved hand operated controller of the type allowing six degrees of bi-directional freedom of hand inputs for conversion of the hand inputs into electrical outputs;

wherein the improvement comprises the use of a separate and distinct sensor for each direction of each bi-directional degree of freedom of said six degrees of freedom; whereby twelve separate and distinct sensors are utilized for converting hand inputs into said electrical outputs.

5,589,829

DECODING VARIABLE-LENGTH ENCODED SIGNALS


Brian Astle, Phoenix, Ariz., assignor to Intel Corporation, Santa Clara, Calif.

Filed Oct. 26, 1994, Ser. No. 329,340

Int. Cl. H03M 7/40

U.S. Cl. 341—67

16 Claims



1. A computer-implemented process for transforming a variable-length encoded signal into a decoded signal, wherein the variable-length encoded signal comprises up to M bits, comprising the steps of:

- (a) reading N bits from a bit stream comprising the variable-length encoded signal, wherein N is less than M;
- (b) accessing an N-bit lookup table using the N bits from the bit stream as an index to retrieve a table entry, wherein the table entry comprises:
 - a flag bit indicating whether the variable-length encoded signal is a short code signal or a long code signal;
 - one or more code-length bits; and
 - one or more code-value bits;
- (c) if the flag bit indicates that the variable-length encoded signal is a short code signal, then generating the decoded signal using the code-value bits, wherein the code-length bits indicate the length of the variable-length encoded signal; and
- (d) if the flag bit indicates that the variable-length encoded signal is a long code signal, then generating the decoded signal using the code-value bits and one or more additional bits from the bit stream, wherein the code-length bits indicate the number of additional bits to be read from the bit stream to complete the variable-length encoded signal.

5,589,830

STEREO AUDIO CODEC


Alfredo R. Linz, Carlin D. Cabler, Glen W. Brown, and Martin P. Soques, all of Austin, Tex., assignors to Advanced Micro Devices, Inc., Sunnyvale, Calif.

Filed Nov. 2, 1994, Ser. No. 333,467

Int. Cl. H03M 1/00

U.S. Cl. 341—110

30 Claims



1. A stereo audio coder-decoder (CODEC) circuit, comprising:

- (a) an analog mixer circuit having a plurality of inputs and outputs;
 - (b) a digital-to-analog conversion circuit, having at least one input and one output, and having a multi-stage interpolation filter circuit, a noise shaper circuit and a semi-digital FIR filter circuit, whereby said at least one output is connected to an input of said analog mixer circuit;
 - (c) an analog-to-digital conversion circuit, having at least one input and one output, and having a fourth order sigma-delta modulator circuit, a multi-stage digital decimation filter circuit and a digital compensation circuit, whereby said at least one input is connected to an output of said analog mixer circuit;
 - (d) data format conversion circuitry connected to said at least one input of said digital-to-analog conversion circuit and to said at least one output of said analog-to-digital conversion circuit;
 - (e) on-chip memory, for storing digital audio signals, whereby said data format conversion circuitry is connected to said on-chip memory and provides data compression/decompression operations on data being input or output to or from said on-chip memory; and
- wherein said digital-to-analog and said analog-to-digital conversion circuits are capable of operating at independently programmable sample rates.

5,589,831

FULLY DIFFERENTIAL FLASH ADC BASED ON THE VOLTAGE FOLLOWER AMPLIFIER STRUCTURE

Derek L. Knee, Sunnyvale, Calif., assignor to Samsung Semiconductor, Inc., San Jose, Calif.

Filed Jan. 30, 1995, Ser. No. 380,778


Int. Cl. H03M 1/36

U.S. Cl. 341—159

4 Claims

1. An analog to digital converter comprising:

- an input follower differential input stage, having first and second inputs coupled to receive a differential input signal and having first and second outputs for providing a differential output signal;
- first and second current sources for providing a constant reference current;
- a differential resistive ladder (DRL) having first and second legs with each leg having a series of (N+2) nodes, where N is a predetermined integer, starting with an input node and ending with an output node with the input node of the first and second legs coupled to the first and second outputs, respec-



tively, of the differential input stage and the output nodes of the first and second legs coupled, respectively, to the first and second current sources, said DRL for providing a voltage difference between adjacent nodes determined by the differential output signal and the constant reference current; and a comparator array comprising (N+2) comparators, with the nth comparator, $n=0, 1, \dots, N, N+1$, having a first input coupled to a node of the first leg displaced from the output node of the first leg by n nodes and a second input coupled to a node in the second leg displaced from the input node of the second leg by n nodes.

5,589,832


LOW NOISE NON-SAMPLED SUCCESSIVE APPROXIMATION

Jeffrey P. Grundvig, and David G. Vallancourt, both of Macungie, Pa., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Dec. 2, 1994, Ser. No. 349,153
Int. Cl.⁶ H03M 1/38

U.S. Cl. 341-161

20 Claims



1. A successive approximation circuit for digitally approximating a moving signal forming an analog-digital converter (ADC) receiving a comparison signal to the successive approximation circuit, the successive approximation circuit comprising:
a conversion control circuit including a decoder for generating a plurality of decoder counts as a control signal;
an estimate register for holding a current plurality of output bits; and
a bit control circuit for generating a next plurality of output bits as a next input to the estimate register in response to the control signal to generate the next plurality of output bits and to generate, from the plurality of decoder counts, a control value associated with a current decoder value and a least significant bit (LSB), the bit control circuit responsive to the comparison signal for adjusting the current plurality of output bits using the control value to compensate for an error due to a slow rate and to generate a next plurality of output bits as the digitally approximated moving signal.

5,589,833


RADAR ACQUISITION SYSTEM

Mitchell A. Randall, Longmont, and Eric Loew, Boulder, both of Colo., assignors to University Corporation for Atmospheric Research, Boulder, Colo.

Filed Apr. 21, 1995, Ser. No. 426,030
Int. Cl.⁶ G01S 13/95

U.S. Cl. 342-195

22 Claims



1. A radar acquisition system comprising:
an electronic circuit module operatively connected to a host processor, wherein said electronic circuit module contains a plurality of signal processing components thereon;
means for receiving a radio wave;
means for converting said radio wave into an analog intermediate frequency signal; and
means for producing in-phase and quadrature signal components from said analog intermediate frequency signal by way of at least one of said plurality of signal processing components independent of any radar signal processing component external to said electronic circuit module and said host processor.

5,589,834


COST EFFECTIVE GEOSYNCHRONOUS MOBILE SATELLITE COMMUNICATION SYSTEM

Aaron Weinberg, Potomac, Md., assignor to Stanford Telecommunications, Inc., Reston, Va.

Filed Apr. 22, 1994, Ser. No. 231,711
Int. Cl.⁶ H04B 7/185

U.S. Cl. 342-354

10 Claims



1. A satellite communication system for providing communication links between a plurality of earth-based low power transceivers and external cellular and terrestrial networks comprising:
one or more satellites in geosynchronous orbit and inclined at a predetermined angle greater than 0 relative to earth, each satellite having a multi-element phased array antenna and transmit and receive circuits selectively connected to said multi-element phased array antenna for providing spatially

discriminated spot radiation beams on the earth's surface, and a steerable spaced-to-ground antenna and transmitter-receiver circuitry connected thereto,

at least one gateway ground terminal having means for:

- (1) performing uplink phasing of said phased array antenna for directive satellite transmissions to desired user locations,
 - (2) tracking the moving satellites via combination of range and doppler tracking,
 - (3) steering said space-to-ground antenna in accordance with satellite motion,
 - (4) performing all ground-beamforming associated with user inbound transmissions,
 - (5) performing all user signal modulation and demodulation,
 - (6) providing the necessary ground interfaces with the external cellular and terrestrial networks, and
- a plurality of earth-based low power transceiver means for one and two-way communications via said selected elements of said phased array antenna.

5,589,836

METHOD FOR SELECTING SIGNALS FROM NAVIGATION SATELLITES

Gunter Noetzel, Dickholzen, Germany, assignor to Robert Bosch GmbH, Stuttgart, Germany


Filed Mar. 6, 1995, Ser. No. 398,701

Claims priority, application Germany, Apr. 29, 1994, 44 15 083.0

Int. Cl.⁶ H04B 7/185; G01S 5/02

U.S. Cl. 342-357

10 Claims



1. A method for selecting signals from navigation satellites, comprising the steps of:
arranging an antenna of a vehicle at a location for receiving, directly and indirectly, signals transmitted by the navigation satellites;
determining a momentary direction of travel of the vehicle;
determining a momentary direct receiving range of the antenna relative to the momentary direction of travel of the vehicle;
determining which of the navigation satellites are located within the momentary direct receiving range of the antenna;
selecting received signals, corresponding to those navigation satellites that are determined to be located within the momentary direct receiving range of the antenna, from the directly and indirectly received signals;
evaluating the selected received signals; and
determining a position of the vehicle as a function of the selected signals.

5,589,835


DIFFERENTIAL GPS RECEIVER SYSTEM LINKED BY INFRARED SIGNALS

David R. Gildes, Menlo Park, and Lloyd H. Banta, Palo Alto, both of Calif., assignors to Trimble Navigation Limited, Sunnyvale, Calif.

Filed Dec. 20, 1994, Ser. No. 359,604
Int. Cl.⁶ G01S 5/02

U.S. Cl. 342-357

15 Claims



1. A GPS receiver system to determine and display a geographical differential Global Positioning System (DGPS) location where the system is interconnected by an airwave infrared (IR) link, the system including:

- a DGPS radio receiver to receive an airwave radio frequency DGPS signal from a source external to the system, said airwave DGPS signal including DGPS corrections, and to provide an airwave infrared (IR) DGPS signal having data indicative of said DGPS corrections;
- a GPS Smart Antenna module to receive an airwave GPS signal including GPS location information from a plurality of GPS satellites, to receive said IR DGPS signal, to use said DGPS corrections and said GPS location information to compute said DGPS location, said DGPS location having a better location accuracy better than a location computed from said GPS location information without said DGPS corrections, and to provide data indicative of said DGPS location in an airwave infrared (IR) module signal; and
- a personal computing display to receive said IR module signal and said IR DGPS signal and to display said DGPS location in a form that is visibly or audibly perceptible to a human being.

5,589,837


APPARATUS FOR POSITIONING AN ANTENNA IN A REMOTE GROUND TERMINAL

Mohammad Soleimani, Silver Spring; John E. Corrigan, III, Chevy Chase; Mohammad Bukhari, Germantown, and David A. Roos, Boyds, all of Md., assignors to Hughes Electronics, Los Angeles, Calif.

Filed Feb. 6, 1995, Ser. No. 384,060
Int. Cl.⁶ H01Q 3/00

U.S. Cl. 342-359

20 Claims



1. An apparatus for aiding the orientation of a directional antenna of a remote ground terminal which transmits and receives a signal via said antenna, said apparatus comprising:
a signal generator for producing a frequency variable reference signal having a variable duty cycle of frequency,
a controller coupled to said signal generator, said controller operative to analyze said signal received via said antenna and to vary the duty cycle of said reference signal in accordance with an identification tag forming part of said signal received

via said antenna, said identification tag identifying a designated central hub station which originates said signal to be transmitted to said remote ground terminal, and
 a detector coupled to said signal generator to receive said reference signal, said detector producing an output signal having an average amplitude proportional to the duty cycle of said reference signal,
 wherein said controller commands said signal generator to produce a reference signal having a first duty cycle when a signal having an identification tag not corresponding to the designated central hub station is received by said antenna, and to produce a reference signal having a second duty cycle when a signal having an identification tag corresponding to the designated central hub station is received by said antenna, said first duty cycle causing the average amplitude of said output signal of said detector to equal a first value and said second duty cycle causing the average amplitude of said output signal of said detector to equal a second value.


5,589,838

SHORT RANGE RADIO LOCATOR SYSTEM

Thomas E. McEwan, Livermore, Calif., assignor to The Regents of the University of California, Oakland, Calif.
 Continuation-in-part of Ser. No. 300,909, Sep. 6, 1994. This application Aug. 3, 1995, Ser. No. 510,979
 Int. Cl.⁶ G01S 1/24

U.S. Cl. 342—387

5 Claims



1. A radio location system, comprising:
 a roving transmitter with an unknown position and providing for periodic bursts of wireless radio frequency (RF) carrier transmissions at a first repetition rate;
 a plurality of receivers with known locations and providing for the reception of said bursts of RF carrier transmissions according to a sample gate input for each;
 local oscillator generation means connected to provide a single sample gate signal to each of said sample gate inputs at a second repetition rate that is different than said first repetition rate, wherein said first and second repetition rates are in phase once each "n" cycles of said first repetition rate;
 digital output means connected to each of the receivers for binary signaling TRUE/FALSE of whether the reception of one of said bursts of said RF carrier transmissions arrived simultaneously with one of said sample gate signals; and
 computer means for storing representations which of the plurality of receivers and what particular cycles "0...n" of said first repetition rate provided a TRUE binary signal connected from the digital output means, and for computing a relative difference in the time-of-flight of said RF carrier transmissions to each of the plurality of receivers from said stored representations, and for computing a position estimate of the roving transmitter from said relative difference and said known positions of each of the plurality of receivers.

5,589,839

RADIO ANTENNA ARRANGEMENT LOCATED NEXT TO VEHICLE WINDOW PANELS

Heinz Lindenmeier, Fürstenrieder Strasse 7 b, D-8033 Planegg;
 Jochen Hopf, Salmdorfer Strasse 3 a, D-8013 Haar, and
 Leopold Rlter, Ludwig-Thoma-Strasse 9, D-8031 Gilching,
 all of Germany


Continuation of Ser. No. 185,955, Mar. 7, 1994, abandoned.
 This application Mar. 11, 1996, Ser. No. 613,021

Claims priority, application Germany, May 18, 1992, 42 16 377.3

Int. Cl.⁶ H01Q 1/32

U.S. Cl. 343—713

26 Claims



1. An antenna arrangement for a motor vehicle, said antenna arrangement comprising
 an exterior radio antenna (1) for radiating electromagnetic waves in a radio frequency broadcast range;
 a vehicle window pane (2) closing an opening provided in a metallic body (3) of the motor vehicle, the exterior radio antenna (1) being arranged on one of the metallic body (3) and the vehicle window pane (2) and located outside of an interior of the motor vehicle, and
 means for shielding said interior of the motor vehicle from the electromagnetic waves radiated by the exterior radio antenna (1), said means for shielding comprising a two-dimensional component (4) arranged on at least a portion of the vehicle window pane (2) and made of a conductive material substantially optically transparent but substantially opaque to said electromagnetic waves in the radio broadcast frequency range radiated by the exterior radio antenna (1) and an electrically conductive capacitive connection (11, 12, 13) for said electromagnetic waves in the radio broadcast frequency range between said two-dimensional component (4) and said metallic body (3), wherein said two-dimensional component (4) has a sufficiently low surface resistance in the radio broadcast frequency range and said electrically conductive capacitive connection (11, 12, 13) of the two-dimensional component (4) to the metallic body (3) is of sufficiently low impedance in the radio broadcast frequency range so that electric and magnetic fields radiated by the exterior radio antenna (1) in the radio broadcast frequency range are effectively prevented from penetrating into said interior of said motor vehicle.

5,589,840

WRIST-TYPE WIRELESS INSTRUMENT AND ANTENNA APPARATUS

Teruhiko Fujisawa, Nagano-ken, Japan, assignor to Seiko Epson Corporation, Tokyo, Japan

Continuation-in-part of Ser. No. 81,380, Jun. 29, 1993, Pat. No. 5,465,098. This application May 24, 1995, Ser. No. 449,482


Claims priority, application Japan, Nov. 5, 1991, 3-288763; Jul. 19, 1994, 6-167095

Int. Cl.⁶ H01Q 1/12; 1/31/0

U.S. Cl. 343—718

8 Claims

1. A wrist-type wireless instrument comprising:
 a casing containing a circuit board;



a wrist band connected to said casing, said casing and said wrist band defining a loop when said instrument is in use;
 a conductive plate having a slot and disposed within said casing and said wrist band, said conductive plate configured and disposed so as to function as a slot antenna; and
 a capacitive element electrically connected to opposing portions of said conductive plate, said opposing portions being separated by said slot;
 wherein said circuit board is arranged so as to be disposed on an inner side of said loop and so as to function as an antenna reflector when said instrument is in use, and wherein said capacitive element is disposed near an approximately central portion of said circuit board.

5,589,841


SATELLITE ANTENNA WITH ADJUSTMENT GUIDANCE SYSTEM

Takaaki Ota, Englewood, N.J., assignor to Sony Corporation, Tokyo, Japan, and Sony Electronics, Inc., Park Ridge, N.J.
 Continuation of Ser. No. 181,915, Jan. 18, 1994, Pat. No. 5,493,310. This application Nov. 30, 1995, Ser. No. 565,343

Int. Cl.⁶ H01Q 3/02

U.S. Cl. 343—760

8 Claims



1. A satellite antenna comprising:
 a support;
 an antenna assembly adjustably mounted on said support and exhibiting a changeable orientation with respect to a satellite broadcast signal, said assembly including a housing, a low noise amplifier within said housing for receiving and amplifying said satellite broadcast signal, and a dish antenna arranged with respect to said low noise amplifier so as to convergently reflect said satellite broadcast signal toward said low noise amplifier;
 adjustment guidance means provided within said housing for emitting an adjustment signal that is responsive to a characteristic of said satellite broadcast signal received by said low noise amplifier to provide an indication of the orientation of said antenna assembly; and
 switch means for selectively activating said adjustment guidance means comprising a switch element provided within said housing and switch control means disposed externally of said housing, said switch element having a plurality of states and said switch control means being operable to select the state of

said switch element without a mechanical connection between said switch element and said switch control means.

5,589,842

COMPACT MICROSTRIP ANTENNA WITH MAGNETIC SUBSTRATE


Johnson J. H. Wang, Marietta, and Victor K. Tripp, Tucker, both of Ga., assignors to Georgia Tech Research Corporation, Atlanta, Ga.

Continuation of Ser. No. 335,489, Nov. 7, 1994, abandoned, which is a division of Ser. No. 217,006, Mar. 23, 1994, Pat. No. 5,453,752, which is a continuation of Ser. No. 7,409, Jan. 22, 1993, abandoned, which is a continuation of Ser. No. 798,700, Nov. 26, 1991, abandoned, which is a continuation-in-part of Ser. No. 695,686, May 3, 1991, abandoned. This application Jan. 30, 1996, Ser. No. 594,330

Int. Cl.⁶ H01Q 1/38; 25/04; 1/36

U.S. Cl. 343—787

6 Claims



1. A compact microstrip antenna for mounting to one side of a surface of a structure, comprising:
 one or more antenna elements; and
 a ferromagnetic substrate adapted for positioning the antenna elements a selected distance from the surface, said ferromagnetic substrate having a relative permittivity and a relative permeability, said relative permittivity being roughly equal to said relative permeability.

5,589,843

ANTENNA SYSTEM WITH TAPERED APERTURE ANTENNA AND MICROSTRIP PHASE SHIFTING FEED NETWORK


Sheldon K. Meredith; Pitt W. Arnold, both of Phoenix, Ariz.; Warren F. Hunt, Lakewood; Kevin J. Connolly, Freehold, both of N.J., and Kevin M. Gaukel, Tempe, Ariz., assignors to Radio Frequency Systems, Inc., Marlboro, N.J.

Filed Dec. 28, 1994, Ser. No. 365,590

Int. Cl.⁶ H01Q 9/16

U.S. Cl. 343—820

15 Claims



1. An antenna system (20), comprising:
 A) a space-tapered multi-beam antenna (24) having:
 1) N co-linear arrays (26) with innermost co-linear arrays and outer co-linear arrays, each co-linear array having at least one electromagnetic radiating element (30), where N is an integer greater than 2, and wherein the number of radiating elements monotonically increases from the outer-

most co-linear arrays toward the innermost co-linear arrays to form a monotonically increasing co-linear array.

2) means (43) for connecting each radiating element within a co-linear array to all other radiating elements in the same array, and

3) an electrically conductive backplane onto which the co-linear arrays are positioned with respect thereto;

B) a microstrip fabricated phase array feed network (28) having N radio receiver/transmitter ports (31) for connection to receiver or transmitter equipment, and N antenna ports (29), each antenna port for connection to one of the N co-linear arrays (26), the phase array feed network having means for phase shifting any outgoing signal at one of the receiver/transmitter ports with respect to each of the N antenna ports, and vice versa, so as to electronically steer the radiating pattern of the antenna to any one of the N main lobes; and

C) means (35) for interconnecting the antenna port (29) to the means (43) for connecting the radiating elements in each co-linear array;

whereby the antenna system radiation pattern for each of the N main lobes has one or more sidelobes that each are attenuated with respect to the corresponding main lobe by an amount greater than the sidelobes generated by an N co-linear array antenna with a fixed number of radiating elements per co-linear array.

5,589,844

AUTOMATIC ANTENNA TUNER FOR LOW-COST MOBILE RADIO


Donald K. Belcher, Rogersville, Tenn., and David C. Bailey, Cocoa Beach, Fla., assignors to Flash Comm, Inc., Melbourne, Fla.

Filed Jun. 6, 1995, Ser. No. 470,542

Int. Cl.⁶ H01Q 1/50

U.S. Cl. 343—860

9 Claims



1. An antenna tuner for automatically matching the impedance of an electrically short antenna to the impedance of an output stage of a transmitter amplifier, the antenna tuner operating over a range of frequencies, the automatic antenna tuner comprising:

an impedance matching network consisting of a pair of shunt capacitive circuit elements and at least one inductive circuit element, the capacitance of at least one of the capacitive circuit elements being mechanically adjustable in increments over a range of incremental capacitance values, a first capacitive circuit element of said pair of shunt capacitive circuit elements being disposed between a first node and a ground reference node, a second capacitive circuit element of said pair of shunt capacitive circuit elements being disposed between a second node and the ground reference node, and a series inductive circuit element being disposed between the first and second nodes, the second node for connecting to the antenna;

a resistive bridge network, disposed between the output stage of the transmitter amplifier and the first node, the resistive bridge network providing a bridge output signal indicating a degree of match between an impedance presented by the output stage

of the amplifier and the impedance matching network to the impedance presented by the antenna;

means for electromechanically adjusting the capacitance of at least one of the first or second capacitive elements, by reading a capacitance set signal indicating a capacitance value and by then adjusting the capacitance of said at least one adjustable capacitive circuit element to a selectable capacitance value in the range of incremental capacitance values;

non-volatile storage means, for storing a plurality of optimum capacitance values, with at least one optimum capacitance value being associated with one frequency in the range of frequencies to which the antenna can be tuned; and

control means, for performing an antenna set-up procedure whereby a set of optimum capacitance values is determined for each frequency in the range of frequencies, the set of optimum capacitance values being then stored in the non-volatile storage means, the optimum capacitance value for each frequency being determined by serially selecting each one of the incremental capacitance values in the range of capacitance values, setting said at least one adjustable capacitive circuit element to that incremental capacitance value by operating the means for mechanically adjusting the capacitance, and then reading the output signal from the resistive bridge network, to determine which incremental capacitance value provides a best impedance match to the antenna, and upon receiving an instruction to tune the antenna to a particular frequency in the range of frequencies, reading the optimum capacitance value for the particular frequency, and for providing the capacitance set signal to the means for electromechanically adjusting.

5,589,845

TUNEABLE ELECTRIC ANTENNA APPARATUS INCLUDING FERROELECTRIC MATERIAL

Robert M. Yandrofski, Littleton; John C. Price; Frank Barnes, both of Boulder; Allen M. Hermann, Golden, and James F. Scott, Boulder, all of Colo., assignors to Superconducting Core Technologies, Inc., Golden, Colo.


Division of Ser. No. 983,632, Dec. 1, 1992, Pat. No. 5,472,935.

This application Jun. 7, 1995, Ser. No. 484,012

Int. Cl.⁶ H01Q 15/02

U.S. Cl. 343—909

24 Claims



1. A tuneable electric antenna apparatus for passing radio frequency energy comprising at least a first tuneable electric antenna component that includes an elongated base portion of a thin film ferroelectric material having a dielectric property, the dielectric property of the ferroelectric material being a function of a voltage applied to the thin film ferroelectric material, a plurality of elements extending from the base portion and spaced apart from one

another at a predetermined interval along the length of the base portion, the predetermined interval between each of the plurality of elements providing a predetermined time delay for radio frequency energy, the predetermined time delay between each of the plurality of elements causing the radio frequency energy to be passed at a common predetermined angle with respect to each of the plurality of elements, wherein, when a predetermined voltage is applied to the thin film ferroelectric material, the dielectric property of the thin film ferroelectric material located between each of the plurality of elements changes and the radio frequency energy passes through the thin film ferroelectric material located between each of the plurality of elements to yield said common predetermined angle.

5,589,846

HEAD MOUNTED IMAGE DISPLAY

Hiroyoshi Kobayashi, Hachioji, Japan, assignor to Olympus Optical Co., Ltd., Tokyo, Japan


Filed Mar. 14, 1995, Ser. No. 404,149

Claims priority, application Japan, Mar. 17, 1994, 6-047187

Int. Cl.⁶ G09G 3/02

U.S. Cl. 345—8

23 Claims



1. A head mounted image display comprising:

an image display body for projecting an image on each eye of an observer; and

mount supporting means for removably mounting said image display body on a head of the observer including the observer's face, said mount supporting means having, at least:

a sinciput contact member to be brought into contact with the head of the observer between a forehead and a crown thereof;

a left occiput contact member to be brought into contact, at a contact section thereof, with a lower portion of a left occiput of the observer located near and behind a left ear of the observer; and

a right occiput contact member to be brought into contact, at a contact section thereof, with a lower portion of a right occiput of the observer located near and behind a right ear of the observer,

wherein when said head mounted image display is mounted on the head of the observer so that said sinciput contact member,

said contact section of said left occiput member and said contact section of said right occiput contact member come into contact with corresponding parts of the head, said image display body is supported by a contact force of said sinciput contact member and by resistance forces produced by the force of gravity acting on said image display body, said resistance forces acting against the contact sections of said left occiput contact member and said right occiput contact member at the respective lower portions of the left occiput and the right occiput of the observer, and said left occiput contact member and said right occiput contact member are spaced from each other with respect to a route along a surface of a middle occiput of the observer so that the middle occiput is free from contact with any member of said head mounted image display when mounted on the head of the observer.

5,589,847

SWITCHED CAPACITOR ANALOG CIRCUITS USING POLYSILICON THIN FILM TECHNOLOGY


Alan G. Lewis, Sunnyvale, Calif., assignor to Xerox Corporation, Stamford, Conn.

Filed Sep. 23, 1991, Ser. No. 764,292

Int. Cl.⁶ G09G 3/36

U.S. Cl. 345—98

27 Claims



1. An analog switched capacitor circuit comprising:

at least one polysilicon thin film capacitor means;

at least one polysilicon thin film transistor switch means;

at least one polysilicon thin film amplifier means; and

interconnection means for interconnecting the capacitor means, the transistor switch means, and the amplifier means so that the output of said circuit is set by the accumulation of electrical charge on said capacitor means under the control of said transistor switch means and said amplifier means;

said capacitor means, said transistor switch means, said amplifier means, and said interconnection means all being formed on a common substrate.

5,589,848

ELECTRONIC EQUIPMENT HAVING A DISPLAY DEVICE

Hiroyuki Shimizu, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 241,679, May 12, 1994, abandoned, which is a continuation of Ser. No. 826,688, Jan. 28, 1992, abandoned, which is a continuation of Ser. No. 430,975, Nov. 1, 1989, abandoned, which is a continuation of Ser. No.


81,453, Aug. 4, 1987, abandoned. This application Apr. 21, 1995, Ser. No. 427,715

Claims priority, application Japan, Aug. 7, 1986, 61-184170

Int. Cl.⁶ G09G 3/36

U.S. Cl. 345—102

8 Claims



1. Electronic equipment comprising:

a keyboard for entering a plurality of kinds of data by a same key, comprising a selecting key for selecting one of said plurality of kinds of data to be entered by the same key; display means for displaying data, said display means having a display screen;

illumination means for illuminating said display screen of said display means, having a first illumination state and a second illumination state;

a power supply included within said electronic equipment for supplying power to said electronic equipment;

first manual time setting means for setting an illumination time of said illumination means;

second manual time setting means for setting a power supply time of said power supply for said electronic equipment;

control means for changing an illumination state of said illumination means after completion of the illumination time set by said first manual time setting means to reduce power consumption by said illumination means; and
power supply control means for causing said power supply to stop the power after completion of the power supply time set by said second manual time setting means.


5,589,849 DISPLAY MONITOR POSITION ADJUSTMENT APPARATUS

Richard J. Ditzik, 3143 Carnegie Ct., San Diego, Calif. 92122
Continuation of Ser. No. 771,856, Oct. 7, 1991, abandoned, which is a continuation-in-part of Ser. No. 375,366, Jul. 3, 1989, abandoned. This application Jul. 25, 1994, Ser. No. 280,148

Int. Cl.⁶ G09G 1/06

U.S. Cl. 345—126

4 Claims



1. A display device position adjusting apparatus, which comprises:

- a table support structure defining a horizontal surface member and a plurality of vertical support members fixed to the horizontal surface, the horizontal surface member having an opening sufficiently large that the display device can fit inside the opening and moved in a multiplicity of orientations;
- means for adjusting the display device through a large range of orientations, wherein the adjusting means is attached to the table support structure, such that the display device can be adjusted to position well above and below the table support structure horizontal surface and can be locked into a fixed position, and wherein the adjusting means provides:
 - a front reversible motor connected to a display elevation linkage means and front display hinge, for elevation adjustment, and
 - a rear reversible motor connected to a display inclination linkage means and rear hinge, for inclination rotation adjustment, wherein each linkage means is connected to the display device cradle in which the display device sits;
- said table support structure being suitable for a computer desk, capable of supporting computer related devices; and
- said adjusting means may be comprised of a plurality of electrical and mechanical adjustment means.

5,589,850

APPARATUS FOR CONVERTING TWO DIMENSIONAL PIXEL IMAGE INTO ONE-DIMENSIONAL PIXEL ARRAY
Lie-Der Lin, Taipei Hsien, and Jiunn-Ming Ju, Tainan Hsien, both of Taiwan, assignors to Industrial Technology Research Institute, Hsinchu Hsien, Taiwan
Filed Sep. 26, 1994, Ser. No. 313,524

Int. Cl.⁶ G09G 5/36

U.S. Cl. 345—132

10 Claims

1. A converter apparatus for use with a computer display screen to convert coordinates of two-dimensional pixels of a graphic




image to linear address, each of said pixels being represented by a first coordinate and a second coordinate, said first coordinate having an X-bit address and said second coordinate having a Y-bit address, said X bits consisting of lower X bits and higher X bits, and said Y bits consisting of lower Y bits and higher Y bits, each of said linear addresses having Z bits consisting of lower Z bits, middle Z bits, and higher Z bits, said converter apparatus comprising:

- a first circuit to receive said lower X bits of various resolutions as inputs, and to output said lower Z bits;
- a second circuit to receive said higher X bits and said lower Y bits as inputs, also of various resolutions, and to output said middle Z bits and a first carrier bit;
- a third circuit to receive said upper Y bits and a portion of said lower Y bits, also of various resolutions, and null bits as inputs, and to output precursory higher Z bits;
- a first adder circuit to receive said precursory Z bits, said Y bits and said first carrier bit as inputs, and to output said higher Z bits; and
- a second adder circuit to receive said lower Z bits, said middle Z bits and said higher Z bits as inputs, and to output said Z-bit linear address;
- wherein said first circuit, said second circuit, and said third circuit all being connected to a resolution select to select one of said inputs respectively connected thereto;
- said second circuit comprises a second multiplexer, a third multiplexer, a fourth multiplexer, a third adder circuit, and a logical operation circuit;
- said third adder circuit being adapted to receive outputs from said second, third, and fourth multiplexers as inputs, and to output said middle Z bits minus the highest middle Z bit, a special Z bit corresponding said highest middle Z bit, and a second carrier bit; and
- said logical operation circuit being adapted to receive said special Z bit, said second carrier bit, and a portion of said higher X bits as inputs, and to output said first carrier bit and said highest middle Z bits.

5,589,851

MULTI-LEVEL TO BI-LEVEL RASTER SHAPE CONVERTER

Jacobo Valdés, Palo Alto, and Eduardo Martinez, Los Altos, both of Calif., assignors to Ductus Incorporated, Mountain View, Calif.


Filed Mar. 18, 1994, Ser. No. 210,869

Int. Cl.⁶ G09G 5/36

U.S. Cl. 345—136

14 Claims

1. A method of generating a bi-level raster shape from a shape outline, the method comprising the steps of:
positioning the shape outline relative to a pixel grid;
identifying a bounding region of said pixel grid which totally encloses the positioned shape outline, said bounding region characterized by the set of pixels which are in said bounding region, wherein each pixel in the set of pixels is characterized by a pixel position relative to said bounding region;



generating a multi-level raster shape representative of the shape outline, said multi-level raster shape storable as an array of multi-level coverage values, wherein each multi-level coverage value is associated with a pixel of said set of pixels and each multi-level coverage value is selected from a plurality of more than two possible coverage values;

identifying, using results of said step of positioning, at least one pair of adjacent pixels with a drop-out warning;
flagging at least one pixel of each pair of pixels which were identified in the step of identifying;

calculating, from a variable threshold function, a threshold value for each pixel in said set of pixels, said variable threshold function being variable in that not all pixels in said set of pixels obtain the same threshold value; and

rounding each multi-level coverage value in said array of multi-level coverage values to a bi-level coverage value selected from a covered value and an uncovered value, wherein said multi-level coverage value is rounded to said uncovered value when said multi-level coverage value is between said uncovered value and said threshold value, and said multi-level coverage value is rounded to said covered value when said multi-level coverage value is not between said uncovered value and said threshold value, said rounding step including the step of rounding a multi-level coverage value to said covered value regardless of its value if the pixel associated with said multi-level coverage value being rounded was flagged in the step of flagging.

5,589,852

APPARATUS AND METHOD FOR IMAGE PROJECTION WITH PIXEL INTENSITY CONTROL


E. Earle Thompson, Dallas, and Thomas W. DeMond, Richardson, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 995,570, Dec. 22, 1992, which is a continuation of Ser. No. 711,558, May 30, 1991, which is a continuation of Ser. No. 315,632, Feb. 27, 1989. This application Jun. 7, 1995, Ser. No. 472,377

Int. Cl.⁶ G09G 3/34;5/10

U.S. Cl. 345—147

9 Claims



1. A method for varying intensity of a pixel comprising:

- varying the intensity of light produced from at least one light source such that said light source produces at least two distinct levels of illumination along a first optical path;
- reflecting light from said light source in said first optical path to form said pixel in a second optical path; and
- varying the amount of time said light source is reflected into said second optical path.

5,589,853

ON-SCREEN DISPLAY APPARATUS WITH SEQUENTIALLY DISPLAYED PICTURE ADJUSTMENT MESSAGES

Mikio Fujiki, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 1,278, Jan. 7, 1993, abandoned. This application Aug. 15, 1994, Ser. No. 290,225

Claims priority, application Japan, Jan. 7, 1992, 4-018539

Int. Cl.⁶ G09G 5/02

U.S. Cl. 345—150

4 Claims

■ CHROMA (COLOR)
LEVEL ADJ.
CHROMA PHASE (HUE)
LEVEL ADJ.
BRIGHT LEVEL ADJ.
CONTRAST LEVEL ADJ.
BIAS ADJ.
GAIN ADJ.
EXIT.

1. An on-screen display apparatus that guides an operator step-by-step through a process of picture quality adjustments of a television monitor, the apparatus comprising:

- memory means for storing messages which instruct the operator as to each step of a step-by-step procedure to follow to accurately perform the picture quality adjustments of at least chroma, hue, brightness, contrast, bias, and gain;
- a CPU for controlling the memory means in such a manner as to retrieve the messages from the memory means sequentially according to the step-by-step procedure for performing the picture quality adjustments and to display the retrieved messages on the television monitor;
- a remote controller having a key input unit manipulated by the operator to transmit a desired command to the CPU, wherein the key input unit has pattern selector keys, a message/enter key, and arrow keys, and wherein the messages stored in the memory means are retrieved and displayed in response to manipulation of the key input unit by the operator; and
- a signal generator for generating a predetermined pattern in response to a pattern signal from the key input unit and for providing the predetermined pattern to the television monitor through the CPU, wherein the predetermined pattern generated by the signal generator includes a gray scale pattern having an array of gray scale levels ranging from white to black, the gray scale pattern being used in the picture quality adjustment of the bias, and the picture quality adjustment of the gain is used for setting a white level gain.

5,589,854

TOUCHING FEEDBACK DEVICE

Ming-Chang Tsai, Fl. 12th, No. 138, Sec. 2, King San South Road, Taipei, Taiwan


Filed Jun. 22, 1995, Ser. No. 493,547

Int. Cl.⁶ G09G 5/08

U.S. Cl. 345—161

1 Claim

1. A tactile feedback device, comprising:



- a) a joystick assembly having a joystick handle and a pair of orthogonally disposed yoke components installed adjacent a bottom end of said joystick handle and adapted for corresponding displacement therewith, each of said yoke components having a driving motor connected to one end thereof through reduction gears and a variable resistor coupled to an opposing end of said yoke for generating a position signal, said pair of yokes being displaceable responsive to rotation of said driving motors for corresponding displacement of said joystick handle; and
- a) a force feedback controlling system including (1) a central processing unit connected to a computer, (2) an A/D converter having a pair of inputs respectively coupled to said variable resistors of said pair of yokes and an output coupled to said central processing unit for converting respective position signals to digital signals, (3) a PWM driver circuit having an input coupled to said central processing unit, and (4) a bridge amplifier having an input coupled to said PWM driver and a pair of outputs respectively coupled to said driving motors, each of said driving motors receives a relative average current according to a simulation condition established by the computer for obtaining a relative rotating speed thereof to generate a relative feedback force to said joystick handle.

5,589,855


VISUALLY IMPAIRED CUSTOMER ACTIVATED
TERMINAL METHOD AND SYSTEM

Paul Blumstein, Palos Verdes; Randy Cole, Los Angeles; James Cook, Manhattan Beach; Ashwin Doshi, Cerritos; Michael Grandcolas, Santa Monica; Stephen Gryte, Los Angeles; Frank McCallick, Encino; Marvin Moskowitz, West Hills; Howard Schechtman, Agoura Hills; Michael Sears, Torrance; Steve Shulman, West Hollywood, all of Calif.; Walter Greenberg, Chicago, Ill.; Patricia Millo, Port Washington, N.Y.; Paul Sidlikman, Livingston, N.J.; Alex J. Virnig, Northridge; Paul Witman, Simi Valley, both of Calif., and Valerie Fenster, New York, N.Y., assignors to Transaction Technology, Inc., Santa Monica, Calif.

Filed Aug. 14, 1992, Ser. No. 930,319
Int. Cl.⁶ G09G 5/00

U.S. Cl. 345-173

23 Claims



1. A method of inputting any multidigit number into a processing machine having a touch responsive interface comprising the steps of:

- a) transmitting a signal representing one digit of said number to the processing machine by touching a first location of said touch responsive interface a number of times equal to said digit; and
- b) transmitting a signal to the processing machine indicating the completion of said inputting of said digit by touching a second location on said touch responsive interface one time,
- c) repeating steps a) and b) for each digit of said multidigit number; and
- d) transmitting a signal to the processing machine indicating the completion of said inputting of said multidigit number by touching a third location on said touch responsive interface wherein said first, second and third locations of said touch responsive interface are physically distinct areas of said touch responsive interface and are disposed relative to borders of said touch responsive interface.

5,589,856


SYSTEM & METHOD FOR DYNAMICALLY LABELED
TOUCH SENSITIVE BUTTONS IN A DIGITIZING
DISPLAY

Frank L. Stein, Vienna, Va., and Guy F. Verrier, Boca Raton, Fla., assignors to International Business Machines Corporation, Armonk, N.Y.

Continuation of Ser. No. 55,067, Apr. 29, 1993, abandoned.
This application Dec. 30, 1994, Ser. No. 378,306
Int. Cl.⁶ G09G 5/00

U.S. Cl. 345-173

13 Claims



1. A data processing system, a digitizing display for inputting two simultaneous touch inputs, comprising:
- a) a display coupled to a computer, having a display surface partitioned into a main panel display region and a button panel display region;
- a) a touch overlay coupled to said computer, having a touch input surface partitioned into a main panel touch region juxtaposed with said main panel display region, and partitioned into a button panel to each region juxtaposed with said button panel display region;
- means for electrically isolating the main panel and button regions in the display and touch overlay;
- a) a button panel driver program stored in said computer, for defining a button touch area in said button panel touch region in accordance with a button specification table, for outputting a button value when said button touch area receives a touch input;
- said button panel driver program defining a button display area in said button panel display region, juxtaposed with said button touch area, said button display area for displaying a button indicium representing said button value and identifying the location of said button touch area;

- said computer receiving a first touch input in said main panel touch region and a simultaneous second touch input in said button touch area and in response thereto, outputting a panel value and said button value, the multiple, simultaneous panel and button values being separately identified in a touch circuit;
- said computer storing a default button specification table describing a plurality of button touch areas and corresponding button display areas in the event a button specification table is not available;
- said button panel driver program using said default table to reconfigure said plurality of button touch areas in said touch overlay and said corresponding button display areas in said display;
- an application program stored in said computer, having an alternate button specification table describing a plurality of alternate button touch areas and corresponding alternate button display areas for selection by a user; and
- said button panel driver program using said alternate table to configure said plurality alternate button touch areas in said touch overlay and said corresponding alternate button display areas in said display when selected by the user.

5,589,857

COORDINATE INPUT DEVICE


Makoto Tanahashi, Kanagawa, and Kazuyasu Takenaka, Chiba, both of Japan, assignors to Sony Corporation, Tokyo, Japan

Filed Nov. 29, 1994, Ser. No. 350,047

Claims priority, application Japan, Dec. 7, 1993, 5-339879
Int. Cl.⁶ G09G 5/00

U.S. Cl. 345-174

9 Claims



1. A coordinate input device comprising:
- an input surface in the form of a rectangle formed by overlapping a first input detecting member and a second input detecting member so that they will not contact each other, first and second electrodes being provided on both side portions at the shorter sides of a rectangular resistive surface of said first input detecting member, a voltage being applied between said first and second electrodes, third and fourth electrodes being provided on both side portions at the longer sides of a rectangular resistive surface of said second input detecting member, a fifth electrode being connected to said fourth electrode through a resistive portion, a voltage being applied between said second and fifth electrodes, the resistive surfaces of the first and second input detecting members contacting each other at an area on said input surface which has been pushed, the coordinate of the input in the X-Y coordinate system on said input surface being obtained from the resistance at said first or second electrode of said first input detecting member and the resistance detected at said second or fifth electrode of said second input detecting member at that time; and

- at least one face-plate switch formed by overlapping at least one first face-plate switch conductor portion and at least a second switch conductor portion so that they will not contact each other, said first switch conductor portion being electrically connected to a predetermined position in the area extending from said first electrode of said first input detecting member through the resistive portion up to said second electrode, said second switch conductor portion being electrically connected to a predetermined position in the area extending from said fourth electrode of said second input detecting member through the resistive portion up to said fifth electrode, wherein when a push on said face-plate switch causes said first and second face-plate switch conductor portions to contact each other, the input using said face-plate switch is detected from the resistance detected at said second or fifth electrode of said second input detecting member.

5,589,858

INFORMATION RECORDING APPARATUS

Hidejiro Kadowaki; Hiroshi Sugiyama, both of Yokohama; Yasuhiko Ishida, Tokyo, and Makoto Takamiya, Kawasaki, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 714,378, May 22, 1991, abandoned.


This application Mar. 15, 1994, Ser. No. 213,998

Claims priority, application Japan, May 22, 1990, 2-132887; May 22, 1990, 2-132891

Int. Cl.⁶ B41J 29/38


U.S. Cl. 347-14

17 Claims



1. An information recording apparatus having:
- recording means for recording information on a recording medium having a front surface, on the basis of recording information data, said recording means effecting recording by discharging a liquid for recording onto said recording medium;
- conveying means for conveying said recording medium with the front surface thereof opposed to said recording means so that said recording means records information on the front surface of the recording medium;
- photodetection speed detecting means for photodetecting light from a back side of the front surface of the recording medium to detect a conveyance speed condition of the recording medium, said photodetection speed detecting means including a light source for generating said light and a detector for photodetecting said light, said light source and said detector being arranged in the back side of the front surface of the recording medium, a position where the conveyance speed is detected by said photodetection speed detecting means being located at substantially a back side of a position where said recording means discharges said liquid onto said recording medium; and
- control means for adjusting a recording position on the basis of conveyance speed information detected by said speed detecting means.

wherein solvent from the first pad comes into contact with printhead nozzles while passing the backing sheet through a paper path of the printer; and
 wherein absorbing material of the second pad comes into contact with printhead nozzles to remove ink and solvent from the nozzles while passing the backing sheet through the paper path of the printer; and
 wherein an opening is defined in the backing sheet for encountering less than all nozzles of the page-wide-array printhead during a cleaning operation while the opening is positioned adjacent to a printhead nozzle the opening defining a scanning path along which a cleaning apparatus contacts the printhead as the backing sheet passes through the paper path of the printer.



a voltage corresponding to an image information signal to control the supply of toner and formation of the toner pattern on the toner carrier.

5,589,866

AIR EVACUATION SYSTEM FOR INK-JET PRINTER
 Todd L. Russell, Camas, Wash.; Brent W. Richtsmeler, San Diego, and Kevin L. Glassett, Escondido, both of Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif.
 Continuation of Ser. No. 171,129, Dec. 20, 1993, Pat. No. 5,446,487, which is a continuation of Ser. No. 876,939, May 1, 1992, Pat. No. 5,296,873. This application Jan. 13, 1995, Ser. No. 372,541

Int. Cl.⁶ B41J 2/01; 29/377

U.S. Cl. 347-102

28 Claims



1. An ink-jet printer, comprising:
 a printhead for ink-jet printing on a print medium disposed at a print zone, said printhead being supported by a printhead carriage for movement relative to a printer body;
 means for advancing the print medium to said print zone during print operations; and
 ink vapor removal means for removing ink carrier vapors emanating from said printhead and ink deposited on said print medium away from said print zone, said ink vapor removal means comprising a duct having an elongated inlet opening disposed along an extent of said print zone, said duct and inlet opening fixed in position relative to said printer body, and means for transporting said ink vapors into said duct and away from said print zone.

5,589,867

METHOD AND APPARATUS FOR FORMING AN IMAGE ON A RECORDING MEDIUM

Chiseki Yamaguchi, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Jun. 23, 1994, Ser. No. 264,525

Claims priority, application Japan, Jun. 23, 1993, 5-150958

Int. Cl.⁶ G01D 15/06

U.S. Cl. 347-141

25 Claims

1. A method for forming an image on a recording medium comprising the steps of: supplying toner injected with static charge onto a toner carrier to form a toner pattern transferring the toner pattern from the toner carrier to a conveying member by applying an electric field directing the static charge toward the conveying member; transcribing the toner pattern from the conveying member onto a recording medium; and fixing the toner pattern onto the recording medium, wherein said step of supplying toner onto the toner carrier to form the toner pattern is effected by a toner supply control member having one end disposed in abutment with the toner carrier, said toner supply control member being supplied with

5,589,868


MULTI-HEAD WIDE-FORMAT THERMAL PLOTTER
 Harry Schofield, Narragansett; Paul Caron, Tiverton; Gary Field, Portsmouth, and Paul Follett, Wakefield, all of R.I., assignors to Atlantek Inc., Wakefield, R.I.

Filed Feb. 21, 1995, Ser. No. 391,048

Int. Cl.⁶ B41J 2/32

U.S. Cl. 347-171

11 Claims



4. A thermal printing apparatus comprising:
 a single platen roller;
 a plurality of thermal print heads arranged in upper and lower diametrically opposed rows on said single platen roller, said print heads each including a print line, said print heads being arranged such that said print lines are aligned in a common vertical plane, each of said print heads engaging said single platen roller with a predetermined engagement pressure;
 a continuous web of print media sequentially threaded through said first and second rows of print heads, said print heads being further arranged in alternating relation between said rows such that print lines of thermal print heads in alternate rows abut each other with respect to a width of said print media;
 means for providing a back tension force on said continuous web of print media; and
 drive means for directly driving rotation of said platen roller wherein said first and second rows of print heads cooperate with said single platen roller to form upper and lower drawing nips directly on the surface of said single platen roller and further wherein a combined engagement pressure of said print heads in said first and second rows cooperates with said single platen roller to provide a sufficient drawing force to overcome said media back tension force and draw said print media through said first and second rows of print heads, said engagement pressure of said print heads in said first row providing insufficient drawing force to overcome said back tension force.

5,589,869

SYSTEMS AND METHODS FOR THERMAL TRANSFER PRINTING


Thomas J. Brandt, Canby, and Stephen A. Zimmerman, Wilsonville, both of Oreg., assignors to Tektronix, Inc., Wilsonville, Oreg.

Division of Ser. No. 962,367, Oct. 16, 1992, Pat. No. 5,512,930, which is a continuation-in-part of Ser. No. 930,572, Aug. 17, 1992, Pat. No. 5,546,114, which is a continuation-in-part of Ser. No. 762,537, Sep. 18, 1991, abandoned. This application Mar. 31, 1995, Ser. No. 415,003

Int. Cl.⁶ B41J 2/325

U.S. Cl. 347-212

16 Claims



—SURROUND —SHADOW MASK

1. A method of printing to form a predetermined printed image on a substrate, comprising the steps of:
 (a) determining a first area on said substrate where a colorant is to be deposited to form said predetermined printed image;
 (b) determining a second area which is immediately adjacent to said first area;
 (c) depositing said colorant over said first area to create said predetermined printed image; and
 (d) depositing an aftercoat over said first area and said second area for sealing said deposited colorant.

5,589,870

SPOT PROFILE CONTROL USING FRACTIONAL INTERLACE FACTORS IN A POLYGON ROS


Douglas N. Curry, Menlo Park, and David L. Hecht, Palo Alto, both of Calif., assignors to Xerox Corporation, Stamford, Conn.

Filed Oct. 31, 1994, Ser. No. 332,175

Int. Cl.⁶ B41J 2/45; 2/455; 2/47

U.S. Cl. 347-233

28 Claims



1. A fractional interlace scanning method for scanning a scan line across an image receiving member, the scan line formed by separately scanning a plurality of light beams across the image receiving member, the method comprising the steps of:
 determining a shape of an envelope representative of a profile of the plurality of light beams to be separately scanned to form the scan line;
 adjusting the shape of the envelope by changing a characteristic of one of the plurality of light beams; and
 separately scanning the plurality of light beams corresponding to the adjusted shape of the envelope to form the scan line.

5,589,871

IMAGE FORMING APPARATUS WITH SAFETY SWITCH AND CURRENT DISSIPATING CONTROLLER

Mikiyuki Aoki, and Kunihiko Omura, both of Toyohashi, Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Jan. 25, 1994, Ser. No. 186,802

Claims priority, application Japan, Jan. 26, 1993, 5-011035

Int. Cl.⁶ B41J 2/435

U.S. Cl. 347-237

16 Claims



1. An image forming apparatus comprising:
 a motor;
 a power source for driving said motor, said motor capable of providing a regeneration current when said power source is disconnected;
 a cover provided so as to be capable of opening and closing relative to a body of the apparatus;
 a safety switch for switching an electrical connection and a disconnection between said motor and said power source in conjunction with the opening and closing operation of said cover; and
 an interrupt member for interrupting an outflow of any regeneration current generated by said motor when said motor is disconnected from said power source by said safety switch.

5,589,872

COMPATIBLE INTERACTIVE TV AND MULTIMEDIA DELIVERY SYSTEM TWO-WAY CABLE TV CONVERSION SYSTEM FOR DATA TRANSMISSION OVER A DEDICATED FREQUENCY BAND


Louis Martinez, Perris, Calif., assignor to Radio Telecom & Technology, Inc., Riverside, Calif.

Division of Ser. No. 207,386, Mar. 7, 1994, which is a continuation-in-part of Ser. No. 941,187, Sep. 4, 1992, Pat. No. 5,321,514, which is a division of Ser. No. 202,206, Jun. 3, 1988, Pat. No. 5,177,604, which is a division of Ser. No. 863,101, May 14, 1986, Pat. No. 4,750,036. This application Sep. 11, 1995, Ser. No. 526,787

Int. Cl.⁶ H04N 7/14

U.S. Cl. 348-12

28 Claims



1. In an interactive television system, a method for communicating information to at least one central receiver from at least one remote receiver location, each remote receiver location connected to a cable television system, the cable television system for transmitting at least one video signal in a downlink direction over at

least one cable, the at least one cable having at least one amplifier along the at least one cable, each amplifier serving at least one remote location, the method comprising the steps of:

- (i) at least one remote location:
 - (a) modulating the information to be communicated from the at least one remote location onto a first carrier;
 - (b) transmitting the modulated first carrier of step (i)(a) onto the at least one cable only during at least some of the blanking intervals of a first cable channel;
- (ii) after at least one cable amplifier in the downlink direction from the at least one remote location:
 - (a) detecting the modulated information received on the at least one cable and retransmitting the modulated information over the air on a second carrier in a dedicated frequency band.

5,589,873

MULTIPOINT TELEVISION CONFERENCE SYSTEM WITH A MULTIPOINT CONTROL UNIT FOR REGISTERING INFORMATION ABOUT TV CONFERENCE ROOMS AND ROOM GROUPS AND ALLOWING A SELECTED ROOM TO PARTICIPATE IN THE TV CONFERENCE BASED ON REGISTERED INFORMATION

Hiroaki Natori, Hitoshi Takel, Shoichi Sano, and Shoichi Tamaki, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kanagawa, Japan


Filed Mar. 30, 1995, Ser. No. 413,178

Claims priority, application Japan, Jul. 20, 1994, 6-167615

Int. Cl.⁶ H04M 3/56

U.S. Cl. 348—15

(DURING CONFERENCE)



1. A multipoint television conference system for holding television conferences among television conference rooms (20-1, 20-2, ... 20-n) by using a multipoint control unit (1) connected with the television conference rooms through a communication network (3), said multipoint television conference system comprising:

registration means (14) provided in the multipoint control unit, for registering room names of the television conference rooms and group names of groups into which the television conference rooms are divided;

control means (15) provided in the multipoint control unit, for reading the room names of the television conference rooms not participating in the television conferences, from said registration means and transmitting the read room names to the television conference rooms requiring to hold the television conferences, and for reading the group names from said registration means and transmitting the read group names to the television conference rooms requesting to participate in the television conferences, and

operation means (30) provided in the television conference rooms respectively, for receiving and displaying the room names which are produced at said control means and transmitted from the multipoint control unit and selecting a designated room name from the displayed room names, and for receiving and displaying the group names which are produced at said control means and transmitted from the multipoint control unit and selecting a designated group name from the displayed group names.

VIDEO IMAGING SYSTEM WITH EXTERNAL AREA PROCESSING OPTIMIZED FOR SMALL-DIAMETER ENDOSCOPES

Michael P. Buchin, Palo Alto, Calif., assignor to Origin Med-systems, Inc., Menlo Park, Calif.


Continuation of Ser. No. 74,110, Jun. 9, 1993, abandoned.

This application May 4, 1995, Ser. No. 434,207

Int. Cl.⁶ H04N 7/18

U.S. Cl. 348—72

15 Claims



1. A method of deriving an output video signal by processing an input video signal generated by an image sensor on which an image of a fibre-optic imaging bundle is formed by an image-forming apparatus of which the fibre-optic imaging bundle is a part, the image of the fibre-optic imaging bundle being formed on only a part of the image sensor to mitigate pixelation artifacts resulting from the optical fibres of the fibre-optic imaging bundle, the method comprising steps of:

receiving the input video signal, the input video signal including plural frames, each of the frames having a frame structure, each of the frames including an image portion generated by the part of the image sensor on which the image of the fibre-optic imaging bundle is formed, and an external portion generated by the part of the image sensor on which the image is not formed;

automatically identifying the external portion of the input video signal;

synthesizing, in response to the identifying step, a synthesized external signal portion corresponding to the external portion of the input video signal; and

generating frames of the output video signal by replacing the external portion of each of the frames of the input video signal with the synthesized external signal portion synthesized in the synthesizing step to provide a respective one of the frames of the output video signal with the same frame structure as the frames of the input video signal, wherein, in the step of synthesizing a synthesized external signal portion, the synthesized external signal portion is synthesized to have a predetermined level.

5,589,875

TELEVISION CAMERA HAVING VARIABLE LENS IRIS/SHUTTER BASED ON POSITION/ROTATIONAL SPEED OF CAMERA

Shigeru Fujita, and Toshio Sakai, both of Yokohama, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 891,050, Jun. 1, 1992, abandoned.

This application Nov. 21, 1994, Ser. No. 344,703

Claims priority, application Japan, Jun. 17, 1991, 3-144479; Apr. 10, 1992, 4-090528

Int. Cl.⁶ H04N 7/18; 9/47

U.S. Cl. 348—143

12 Claims

1. A television camera device comprising:

an image pickup camera moveable in at least one direction and including a lens iris and means for (i) adjusting said lens iris automatically in accordance with a quantity of incoming light from a scene, including an object and a background, being imaged to achieve an adjusted lens iris and (ii) correcting the

5,589,877

AUTOMATIC AMPLITUDE CONTROL CIRCUIT FOR A VECTOR SCOPE

Kenzo Ikuzawa, and Yoshimichi Hika, both of Kanagawa-ken, Japan, assignors to Leader Electronics Corporation, Kanagawa-ken, Japan


Filed May 17, 1995, Ser. No. 443,168

Claims priority, application Japan, May 17, 1994, 6-102918

Int. Cl.⁶ H04N 17/02

U.S. Cl. 348—186

16 Claims




adjusted lens iris in accordance with a correction datum to image said object while reducing influences of light from the background;

means for moving said camera to image said object;

detecting means for detecting a position of said camera in said at least one direction and outputting a position signal indicating said position; and

storing means, receiving said position signal, for storing correction data to correct the adjusted lens iris, said correction data being predetermined and including a plurality of data portions corresponding to a plurality of possible positions of said camera, said storing means outputting one of said plurality of data portions to said camera as said correction datum in response to said position signal, thereby enabling production of a clearer image of said object.



5,589,876

INFRARED IMAGING DEVICE READILY REMOVING OPTICAL SYSTEM CONTRIBUTORY COMPONENT

Kazuo Konuma, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan


Filed Sep. 20, 1994, Ser. No. 308,932

Claims priority, application Japan, Sep. 28, 1993, 5-240981

Int. Cl.⁶ H04N 5/217; H01L 25/00

U.S. Cl. 348—164

7 Claims



1. An infrared imaging device, comprising:

an optical system including an infrared lens;

an infrared solid state image sensing device for detecting a light radiated from an object, focused by the optical system, the infrared solid state image sensing device having an image area where first infrared detectors for detecting infrared image signals are arranged in a two-dimensional array form;

infrared detecting means being arranged on the infrared solid state image sensing device outside the image area and comprising infrared detector groups for extracting an optical system contributory component, the infrared detector groups including at least two kinds of second infrared detectors having respectively different sensitivity characteristics to obtain at least two kinds of output signals; and

processing means for carrying out a calculation processing of the infrared image signals output from the first infrared detectors within the image area on the basis of basic data previously prepared as characteristics of said at least two kinds of the output signals obtained by the second infrared detectors of the infrared detecting means, so as to remove the optical system contributory component.

5,589,878

METHOD OF DETERMINING AN ERROR IN A VIDEO CONFERRING SYSTEM CAMERA

Leo M. Cortjens, Norcross; Kenneth A. Franklin, Lawrenceville; Richard C. Mays, Atlanta, and Curtis M. Smith, Lawrenceville, all of Ga., assignors to Videoconferencing Systems, Inc., Norcross, Ga.

Division of Ser. No. 139,645, Oct. 20, 1993, abandoned. This

application Jan. 17, 1995, Ser. No. 373,412

Int. Cl.⁶ H04N 5/232

U.S. Cl. 348—211

27 Claims


1. A videoconferencing system with error detection, comprising: a camera for providing a picture, said camera including a zoom mechanism and a focus mechanism;

a pan and tilt mechanism for pointing said camera to a desired position;

a zoom position indicator tier providing a zoom status signal;

a focus position indicator for providing a focus status signal;

a pan position indicator for providing a pan status signal;



a tilt position indicator for providing a tilt status signal;
a monitor for displaying said picture;
means for providing zoom and focus commands to said camera,
for providing pan and tilt commands to said pan and tilt
mechanism, for monitoring said zoom status signal, said focus
status signal, said pan status signal, and said tilt status signal
to determine whether said commands were properly executed,
for determining that an error has occurred if any of said
commands were not properly executed, for providing an error
detection signal if a said error has occurred and for maintaining
a record of said error and an indication of the command
associated with said error.

5,589,879


PERFORMING WHITE BALANCE CORRECTION ON INTEGRATED DIVIDED AREAS OF WHICH AVERAGE COLOR IS SUBSTANTIALLY WHITE

Kenji Saito, and Yasuhiro Shinkai, both of Asaka, Japan,
assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan
Filed Mar. 24, 1994, Ser. No. 216,850

Claims priority, application Japan, Mar. 26, 1993, 5-067715;
Mar. 30, 1993, 5-071290; Mar. 31, 1993, 5-074257
Int. Cl.⁶ H04N 9/73

U.S. Cl. 348—223

14 Claims



1. An automatic white balance control device comprising:
picture dividing means, receiving a photograph signal corresponding to a photograph condition, for dividing a picture image into a plurality of areas and periodically receiving picture signals with respect to one of the plurality of areas for one field in numerical order;
integrating means for integrating picture signals output from said picture dividing means and outputting integrated values for every one field;
control means for judging whether an average color of said picture signals within each of said areas outputting said picture signals is substantially white, outputting white balance control signals in accordance with said integrated values when said average color is judged as substantially white and outputting to said picture dividing means a command representing a number of divided areas for which said picture image is to be divided and

a white balance circuit for controlling white balance by adjusting levels of elementary color signals in accordance with said white balance control signals,
wherein said control means groups said divided areas into a plurality of groups according to predetermined patterns corresponding to each different group, adjacent divided areas are grouped into different groups from each other, signals are alternatively output from each of said groups in accordance with said command.

5,589,880

TELEVISION CAMERA USING TWO IMAGE PICKUP DEVICES WITH DIFFERENT SENSITIVITY


Akimi Tsukui, Higashikurume, Japan, assignor to Hitachi Den-shi Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 25, 1995, Ser. No. 377,708

Claims priority, application Japan, Jan. 25, 1994, 6-006202
Int. Cl.⁶ H04N 5/235

U.S. Cl. 348—229

17 Claims



1. A television camera comprising:
a lens system having an iris structure for receiving incident light from an object;
a spectrometer for dispersing an optical image of said object from said lens system and producing first and second optical images, said spectrometer splitting light quantity of the optical image of said object from said, lens system and assigning the split light quantities to said first and second optical images in a predetermined ratio;
first and second image pickup devices, on which the first and second optical images from said spectrometer are focused, for converting said first and second optical images into video signals, respectively;
first and second amplifiers for amplifying the video signals from said first and second image pickup devices, respectively;
a high-brightness signal detection circuit for detecting whether or not the video signal supplied from said first amplifier is a high-brightness signal indicating that said video signal from said first amplifier has a level equal to or higher than a predetermined level which is lower than a saturated output signal level of said first image pickup device, and for outputting a detection signal indicating the high-brightness signal during a period where the video signal from said first amplifier is detected to have a level equal to or higher than said predetermined level;
a video signal switcher for selecting and outputting one of said video signals from said first and second amplifiers in accordance with said detection signal;
a signal processing circuit for converting the video signal from said video signal switcher into a composite video signal and outputting said composite video signal as an output composite video signal of said television camera;
an iris control circuit for controlling an opening of said iris structure of said lens system in accordance with the video signal from said first amplifier;
a high-brightness video signal extraction circuit for gating the video signal from said second amplifier in accordance with

said detection signal and extracting the gated video signal of said video signal from said second amplifier corresponding to said high-brightness signal out of the video signal output from said second amplifier; and
an image pickup device control circuit for controlling a charge storage time of said second image pickup device in accordance with a level of the video signal extracted by said high-brightness video signal extraction circuit.

filtering effect with respect to bundles of optical transmission rays to prevent production of pseudo-colors.

5,589,883

CATHODE RAY TUBE DISPLAY


Masanori Ogino; Takeo Yamada; Miyuki Ikeda, all of Yokohama; Tsuneo Fujikura, Chigasaki; Takahiko Fujiwara, Yokohama, and Etsuhiro Nakagiri, Yokosuka, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Division of Ser. No. 813,082, Dec. 24, 1991, abandoned. This application Jun. 8, 1994, Ser. No. 257,441

Claims priority, application Japan, Dec. 26, 1990, 2-417590
Int. Cl.⁶ H04N 5/68

U.S. Cl. 348—379

9 Claims



5,589,881

ENHANCED PERFORMANCE CCD OUTPUT AMPLIFIER


Mark E. Dunham, Los Alamos, and David W. Morley, Santa Fe, both of N.M., assignors to The Regents of the Univ. of California Office of Technology Transfer, Alameda, Calif.

Filed Nov. 9, 1994, Ser. No. 337,692

Int. Cl.⁶ H04N 5/335; H03F 3/16

U.S. Cl. 348—300

3 Claims



1. An output amplifier for amplifying an output charge signal from a CCD comprising:
A FET having a gate connected to said CCD for receiving said output charge signal from said CCD and outputting an intermediate signal from a drain of said FET where said FET has a gate-to-source shunt capacitance at least equal to the sum of CCD shunt capacitance, circuit stray capacitance, and gate-to-drain capacitance, the remaining capacitances seen at the output node of said CCD; and
an intermediate amplifier connected to said drain of said FET for receiving said intermediate signal and outputting a low-noise signal.

5,589,882

INTEGRAL INFRARED ABSORBING OPTICAL LOW-PASS FILTER


Akihiko Shiraishi; Kazuo Fujibayashi, both of Kawasaki, and Tetsun Kuwabara, Urawa, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 539,175, Jun. 18, 1990, abandoned. This application May 31, 1995, Ser. No. 455,250

Claims priority, application Japan, Jun. 20, 1989, 1-157031
Int. Cl.⁶ H04N 5/225


U.S. Cl. 348—340

10 Claims



1. An optical low-pass filter comprising:
a single optical member formed of a material having a property of absorbing infrared light in a predetermined wavelength range, said optical member having a plurality of ridge-like portions formed on at least one surface thereof at a predetermined pitch, said ridge-like portions comprising a phase type diffraction grating, said diffraction grating having a low-pass

1. A display system comprising:
at least one cathode ray tube, said at least one cathode ray tube having three cathode electrodes;
first video amplifiers for amplifying three video signals;
second video amplifiers for outputting three amplified video signals to said three cathode electrodes of said at least one cathode ray tube;
black reference insertion means for inserting a black level reference signal into a part of a vertical blanking period of the three video signals;
cathode current detection means coupling the outputs of said second video amplifiers to said three cathode electrodes, for independently detecting each of three cathode beam currents of said at least one cathode ray tube;
black reference sampling means coupled to said cathode current detection means, for sampling and holding each of three black level cathode beam currents outputted from said cathode current detection means and corresponding to the black level reference signal; and
black level control means responsive to said black reference sampling means for automatically and independently controlling each of three optical black levels of said at least one cathode ray tube by adjusting at least one second-grid voltage of said at least one cathode ray tube, thereby correcting a change in a cut-off voltage of said at least one cathode ray tube and at the same time correcting a change in permeance of said at least one cathode ray tube,
wherein said cathode current detection means comprises a voltage follower having an output connected to one of said three cathode electrodes of said at least one cathode ray tube and an input connected to receive one of the three amplified video output signals from said second video amplifiers, and a capacitor coupling said output and said input of said voltage follower, so that an output current of said voltage follower is detected through a current return path.



at least one anterior lens having an anterior surface and a posterior surface, the surfaces of the posterior lens and the surfaces of the anterior lens having curvatures adapted to focus light rays emanating from the fundus when the posterior lens is in juxtaposition to the cornea in an aerial image anterior to and in close proximity to the anterior surface of the anterior lens, and

means for coupling said posterior lens and said anterior lens together so that the anterior lens and the posterior lens are substantially coincident along their optical axes, and so that the anterior lens and posterior lens can be moved axially relative to each other between a proximal position and a distal position, the surfaces of the posterior lens and the surfaces of the anterior lens cooperating to change the magnification of the aerial image from at least a first predetermined value when the anterior lens is in a proximal position to a second predetermined value when the anterior lens is in the distal position.

5,589,897


METHOD AND APPARATUS FOR CENTRAL VISUAL FIELD MAPPING AND OPTIMIZATION OF IMAGE PRESENTATION BASED UPON MAPPED PARAMETERS
Stephen H. Sinclair, 1208 Henry La., Gladwyne, Pa. 19035; Jonathan Nissanov, Philadelphia, and Amitabha Gupta, Pittsburgh, both of Pa., assignors to Stephen H. Sinclair, Gladwyne, Pa.

Continuation of Ser. No. 432,015, May 1, 1995, abandoned.
This application Dec. 22, 1995, Ser. No. 576,859

Int. Cl.⁶ A61B 3/02

U.S. Cl. 351—223

21 Claims



1. A method for optimizing the presentation of visual information to a person having a sub-optimal central field of vision comprising the steps of:

- Determining the geometry of the person's central visual field with regard to perception of high contrast images;
- Measuring parameters representative of contrast sensitivity of the person at a plurality of locations within the determined central visual field;
- Measuring parameters representative of luminance sensitivity at a plurality of locations in the determined central visual field;
- Measuring parameters representative of perceived spatial distortion of locations within the determined central visual field;

- Modifying and enhancing the visual information in accordance with the measured parameters to create individualized visual information;
- Presenting the individualized visual information to the person's functional areas of the central visual field.

5,589,898

METHOD AND SYSTEM FOR COLOR VISION DEFICIENCY CORRECTION


Holly G. Atkinson, Bridgewater, Conn., assignor to Reuters Limited, London, England

Filed Jun. 7, 1995, Ser. No. 474,257

Int. Cl.⁶ A61B 3/02;3/00

U.S. Cl. 351—237

11 Claims



1. A method for determining color vision defects of a user of a computer system comprising a processing means, display means, input means and memory means, and for altering a color palette displayed on the display means to compensate for any color vision defect comprising the steps of:

- storing in the memory means data comprising a plurality of color vision test images and medical information on color vision deficiencies;
- causing the processing means sequentially to place one or more of the test images on the display means;
- providing the user with certain instructions concerning his perception of the content of each displayed image;
- receiving the user's response to the instruction as entered through the input means;
- storing the response in the memory means;
- comparing in the processing means the user's response with medical information on color vision deficiencies stored in the memory means to determine the nature of the user's color vision deficiency;
- storing in the memory means a plurality of color palettes for the display means, at least one of which palettes compensates for color vision deficiencies;
- determining, in response to the comparing step, which of the plurality of color palettes is optimal in view of the user's color deficiency as determined from his responses; and
- causing the system to set the display means to display the optimal color palette.

5,589,899

OPHTHALMOLOGIC APPARATUS HAVING A SLIDABLE BED

Yasuo Maeda, Kawasaki, and Kyoji Sekiguchi, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 21, 1994, Ser. No. 361,044

Claims priority, application Japan, Dec. 22, 1993, 5-324577


Int. Cl.⁶ A61B 3/00;3/14

U.S. Cl. 351—245

13 Claims

1. An ophthalmologic apparatus comprising:

- a base;
- a slidable bed slidable on said base;
- input means for inputting instruction for sliding said slidable bed relative to said base from a user;



display means for effecting image display of a stored instruction image; and

control means for controlling an image display of the stored instruction image on said display means on the basis of an input effected by said input means by a technique similar to the input of instructions for sliding said slidable bed.

5,589,900

VIRTUAL DRUM IMAGESETTER

Michael Sterflinger, Huntington, N.Y., assignor to Exstra Corporation, Hauppauge, N.Y.

Division of Ser. No. 196,875, Feb. 15, 1994, Pat. No.


5,404,187, which is a continuation of Ser. No. 823,527, Jan. 21, 1992, abandoned. This application Sep. 23, 1994, Ser. No. 311,559

The portion of the term of this patent subsequent to Apr. 4, 2012, has been disclaimed.

Int. Cl.⁶ G03B 41/00

U.S. Cl. 396—548

38 Claims



1. Imagesetter apparatus for producing an image on a flexible section of photosensitive material having a first end, an opposite second end and two substantially parallel side edges extending between said first and second ends and containing between them an available image area, said apparatus comprising:

- (a) means for retaining said section in a cylindrical arcuate configuration, said retaining means including two circular arced supports, each support being in physical contact with the surface of said photosensitive material immediately adjacent one of said edges outside of said image area and delimiting a side of said image area, said cylindrical arcuate configuration having a central axis;
- (b) means for selectively exposing said image area to radiation to produce said image, said exposing means including means for directing a modulated beam of radiation along said axis, means for redirecting said beam at an angle with respect to said axis toward said image area, means for rotating said

redirecting means about said axis so as to scan said beam in the circumferential direction substantially parallel to said two edges, and means for translating said redirecting means in the axial direction so as to scan said beam in a direction substantially perpendicular to said edges, thereby to produce a two dimensional image.

wherein no physical contact is made with said section in the image area thereof during exposing of the two dimensional image.

5,589,901

APPARATUS AND METHOD FOR SYNCHRONIZING SEARCH AND SURVEILLANCE DEVICES


Kevin P. Means, 3126 Goldsmith St., San Diego, Calif. 92106

Filed May 15, 1995, Ser. No. 441,121

Int. Cl.⁶ G03B 39/00

U.S. Cl. 396—12

21 Claims



1. Apparatus for search and surveillance from a moving vehicle by an observer within said vehicle, which comprises:

- a lamp projecting a directable beam of visible light, said lamp being mounted in a movable lamp gimbal attached to the exterior of said vehicle, and said beam being visible to said observer from within said vehicle; lamp positioning means for positioning said lamp gimbal to aim said beam of visible light and of said camera to aim said camera at said object; and a pair of lamp gimbal signal generators generating respectively an azimuth position signal and an altitude position of said lamp within said lamp gimbal;

a camera for detecting an image of any object in light of visible or infrared wavelength, said camera being mounted in a movable camera gimbal attached to the exterior of said vehicle, and said image of said object being visible to said observer from within said vehicle; camera positioning means for positioning said camera gimbal to aim said camera at said object; and a pair of camera gimbal signal generators generating respectively an azimuth position signal and an altitude signal indicating respectively the azimuth position and the altitude position of said camera within said camera gimbal;

control means operable by said observer for controlling said lamp positioning means to position said lamp gimbal;

a comparator for comparing said position signals from said camera and lamp gimbal signal generators with each other, and in response thereto causing said positioning means of said camera gimbal to move said camera into alignment with said lamp;

said comparator also alternatively comparing said position signals of said camera gimbal signal generator with predetermined position signals generated by a manually tunable signal generator;

whereby said comparator permits synchronized positioning of said camera with said lamp or predetermined positioning of said lamp independently of positioning of said camera.

5,589,902

INTEGRATED AUTOMATIC INSTALLATION FOR TAKING PHOTOGRAPHS OR SEQUENCES OF PHOTOGRAPHS

Henri Gruel, Grenoble; Michel Moraine, and Serge Crasnian-ski, both of Meylan, all of France, assignors to KIS Photo Industrie (SARL), France

Continuation of Ser. No. 38,919, Mar. 29, 1993, abandoned.


This application Apr. 4, 1995, Ser. No. 417,264

Claims priority, application France, Mar. 30, 1992, 92 04041

Int. Cl.⁶ G03B 29/00

U.S. Cl. 396—3

22 Claims



1. An installation for taking photographs or sequences of photographs, comprising:

acquisition means for receiving analog signals from an optical image of a subject of which it is desired to take a photograph or a sequence of photographs, said subject being positioned within the installation and in view of said acquisition means and wherein said acquisition means defines an acquisition axis and includes two cameras whose fields of acquisition are, respectively, vertical and horizontal, the optical axis of one of said two cameras being coincident with said acquisition axis by means of a second half-silvered mirror positioned along the bisector of the real optical axes of said two cameras so that the acquisition of images is effected equally by either or both of said cameras as a function of the type of photograph desired;

memory means for storing the optical information received by said acquisition means;

a first screen, connected to said acquisition means, for allowing simultaneous viewing by the subject of the image received by said acquisition means;

photographing means for taking the desired photograph or the sequence of photographs;

a first half-silvered mirror, mounted on the optical axis of said acquisition means and being directed along a bisector of the angle defined by the optical axes of said acquisition means and said first screen respectively, so as to generate a virtual image of said first screen on the optical axis of said acquisition means;

a central processing unit, connected to said acquisition means and photographing means, being fitted with a digitization card intended to digitize the analog signals received by said acquisition means, the digital signals thereby obtained being capable of undergoing processing by said central processing unit to be conveyed to said first screen so as to allow simultaneous viewing by the subject of the image or of the images received by said acquisition means and, optionally, capable of further processing by said central processing unit upon command of the subject; and

an interaction element, interposed between said central processing unit and the subject, capable of being actuated by the subject while positioned within the installation and viewing the image on said first screen, to freeze the image reproduced on said first screen at the instant of the image's actuation in

said memory means and capable of inducing the image's production on a medium by said photographing means upon further actuation by the subject.

5,589,903

PANORAMA HEAD FOR OPTICAL EQUIPMENT PARTICULARLY FOR PHOTOGRAPHIC EQUIPMENT

Paolo Speggorin, Mussolente, Italy, assignor to Lino Manfrotto & Co., S.p.A., Bassano Del Grappa, Italy


Filed May 16, 1995, Ser. No. 442,533

Claims priority, application Italy, Jul. 20, 1994, PD94A0135

Int. Cl.⁶ G03B 17/00

U.S. Cl. 396—428

14 Claims



1. A panorama head for optical equipment, particularly for photographic equipment, for positioning the equipment precisely relative to a system of axes, comprising an articulated joint for each axis, each articulated joint including first and second joint elements which are coupled with one another for rotation about the corresponding axis and can be clamped selectively in a preselected angular position relative to said corresponding axis, characterized in that wherein at least one of the articulated joints comprises a kinematic reduction coupling with first and second coupling elements which are fixed to the first and second joint elements, respectively, during rotation about the corresponding axis and can be moved between a position of mutual coupling for precision adjustments and a position of mutual disengagement for quick positioning.

5,589,904

CAMERA WHICH PERFORMS MOTION COMPENSATION FOR SEQUENTIAL PHOTOGRAPHS BY CONTINUOUSLY DETECTING MOTION UNTIL THE FINAL PHOTOGRAPH IS TAKEN

Keishi Urata, and Toshiyuki Nakamura, both of Tokyo, Japan, assignors to Nikon Corporation, Tokyo, Japan

Filed Dec. 12, 1995, Ser. No. 571,178

Claims priority, application Japan, Dec. 14, 1994, 6-310516


Int. Cl.⁶ G03B 5/00

U.S. Cl. 396—55

11 Claims

1. A camera which takes a first photograph upon initiation of exposure, and then takes a second photograph after the first photograph is taken, the camera comprising:

an exposure control mechanism causing the camera to take the first photograph after a first time period elapses from the initiation of exposure, and to take the second photograph after a second time period elapses from the first photograph being taken; and



a motion detector continuously detecting motion affecting the camera prior to the first photograph being taken until after the second photograph is taken.

5,589,905

CAMERA WITH ILLUMINATION SOURCE


Dale F. McIntyre, Honeoye Falls, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Jan. 24, 1995, Ser. No. 378,129

Int. Cl.⁶ G03B 13/16; 13/18

U.S. Cl. 396—431

9 Claims



1. A camera device for a photographer viewing a scene to be photographed comprising an illumination source for illuminating the scene, and means for linearly scanning the scene with said illumination source to provide a visible linear indication of a scanned region of the scene, is characterized by:

control means for automatically varying the brightness of the illumination in accordance with changes in one or more scene parameters, to ensure constant visibility of the linear indication.

5,589,906

APERTURE DEVICE FOR A CAMERA

Hitoshi Shimizu, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Aug. 18, 1995, Ser. No. 516,556

Claims priority, application Japan, Aug. 25, 1994, 6-222750

Int. Cl.⁶ G03B 9/02


U.S. Cl. 396—505

21 Claims

1. An aperture device for defining an aperture through which light can pass along an optical axis, comprising:

a resilient opaque tube supported coaxially with said optical axis;

means for constricting an intermediate portion of said resilient opaque tube by rotating at least a portion of said tube to form



a circular aperture for controlling an amount of said light passing through said resilient opaque tube.

5,589,907

CAMERA HAVING AN INFORMATION SETTING APPARATUS FOR SETTING PHOTOGRAPHIC DATA

Toshiaki Hozumi, Tokyo, and Hidehiro Ogawa, Funabashi, both of Japan, assignors to Nikon Corporation, Tokyo, Japan


Filed Jun. 30, 1995, Ser. No. 497,710

Claims priority, application Japan, Sep. 7, 1994, 6-213635

Int. Cl.⁶ G03B 17/00

U.S. Cl. 396—287

17 Claims



1. A camera having a setting value for photography, said camera comprising:

an information setting unit to increase and decrease the setting value of the camera through motion in first and second directions; and

a determination unit having a normal mode and an inverse mode, wherein said determination unit causes said information setting unit to increase the setting value through motion in the first direction and decrease the setting value through motion in the second direction in the normal mode, and said determination unit causes said information setting unit to decrease the setting value through motion in the first direction and increase the setting value through motion in the second direction in the inverse mode.

5,589,908

CONTROL FOR VARIABLE MAGNIFICATION IN AN IMAGING APPARATUS

Yoshiaki Irie, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Nov. 10, 1994, Ser. No. 338,780

Claims priority, application Japan, Nov. 29, 1993, 5-298573

Int. Cl.⁶ G03B 3/00


U.S. Cl. 396—51

6 Claims

1. An imaging apparatus having a predetermined image plane, said apparatus comprising:

a variable magnification optical system for magnifying an image in the image plane with a variable magnification;

detecting means for detecting a distance related to each of a plurality of image areas in the image plane



means for designating a plurality of image portions by grouping together adjacent image areas having distance values that differ from each other by less than a predetermined amount; means for manually selecting one of the plurality of image portions designated by said designating means; and means for controlling the magnification of said variable magnification optical system in accordance with a size of the image portion selected by said manual selecting means.

5,589,909

AUTOMATIC FOCUS ADJUSTMENT CAMERA WITH HIGH SPEED SEQUENTIAL PHOTOGRAPHY CAPABILITY, AND METHOD OF AUTOMATIC FOCUS ADJUSTMENT THEREFOR

Yosuke Kusaka, Yokohama, Japan, assignor to Nikon Corporation, Tokyo, Japan


Filed Dec. 21, 1994, Ser. No. 360,443

Claims priority, application Japan, Dec. 24, 1993, 5-328334

Int. Cl.⁶ G03B 13/36

U.S. Cl. 396—96

12 Claims



1. An automatic focus adjustment camera, comprising:
 - a sequential photography device which performs photographic action sequentially;
 - a photographic optical system, which is driven so as to be focused;
 - a charge accumulation type image sensor which outputs target object image data corresponding to a distribution of intensity of illumination in an image of a target object to be photographed;
 - a focus detection optical system which forms said image of said target object on said charge accumulation type image sensor from light from said target object which has passed through said photographic optical system;
 - a time detection device which detects charge accumulation time of said charge accumulation type image sensor;
 - a focus detection device which detects the focus adjustment state of said photographic optical system by:
 - performing a first calculation process upon said target object image data output from said charge accumulation type image sensor when sequential photographic operation is not being performed by said sequential photography device or

accumulation time of said charge accumulation type image sensor detected by said time detection device is shorter than a predetermined value; and, performing a second calculation process, different from said first calculation process, upon said target object image data which is output from said charge accumulation type image sensor when sequential photographic operation is being performed by said sequential photography device and accumulation time of said charge accumulation type image sensor detected by said time detection device is longer than said predetermined value; and, a drive device which drives said photographic optical system so as to focus it, based upon the adjustment state detected by said focus detection device.

5,589,910

APPARATUS FOR MEASURING A DISTANCE

Tatsuo Saito, and Shigenori Goto, both of Omiya, Japan, assignors to Fuji Photo Optical Co., Ltd., Saltama-ken, Japan


Filed Dec. 14, 1994, Ser. No. 357,431

Claims priority, application Japan, Dec. 15, 1993, 5-315431; Dec. 15, 1993, 5-315441; Dec. 15, 1993, 5-315458; Dec. 15, 1993, 5-315461

Int. Cl.⁶ G03B 13/36

U.S. Cl. 396—106

10 Claims



1. An apparatus for measuring a distance to an object, comprising:
 - (a) a first processing unit for calculating the distance to said object, based on an input signal;
 - (b) a second processing unit for calculating the distance to said object, based on an input signal;
 - (c) a first distance measuring unit of an active method for projecting first light toward said object in order to calculate the distance to the object by said first processing unit and detecting said first light reflected by said object to output a signal detected to said first processing unit;
 - (d) a second distance measuring unit of a passive method for detecting two light beams from said object, having passed through mutually different paths, in order to calculate the distance to the object by said second processing unit and outputting a signal detected to said second processing unit;
 - (e) a semiconductor photodetector comprising a first photodetecting region, a second photodetecting region surrounding said first photodetecting region, and an insulator located between said first photodetecting region and said second photodetecting region;
 - (f) an optical system arranged so that light from said object is incident to said first photodetecting region and so that light from the surroundings of said object is incident to said second photodetecting region;
 - (g) a comparator into which an output signal from said first photodetecting region and an output signal from said second photodetecting region are put; and
 - (h) a selecting circuit into which a first output signal from said first processing unit and a second output signal from said second processing unit are put and which outputs said first output signal or said second output signal depending upon an output from said comparator.

5,589,911

AUTOFOCUSING APPARATUS FOR CAMERA HAVING MULTIPLE RANGING DEVICE

Osamu Nonaka, Sagami-hara, Japan, assignor to Olympus Optical Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 162,340, Dec. 3, 1993, abandoned.


This application Dec. 11, 1995, Ser. No. 570,364

Claims priority, application Japan, Dec. 9, 1992, 4-329481; Jan. 8, 1993, 5-1542; Mar. 2, 1993, 5-41510

Int. Cl.⁶ G03B 3/00; 13/18

U.S. Cl. 396—80

32 Claims



1. An autofocus apparatus for a camera, comprising:
 - a photographing lens for forming an object image on a film surface;
 - a first ranging unit for measuring a distance to an object located at a substantially central portion of a photographic frame of said camera, and for outputting a first ranging result;
 - a second ranging unit for measuring a distance to an object located at a peripheral portion of the photographic frame, and for outputting a second ranging result;
 - a control unit for receiving the first and second ranging results obtained by said first and second ranging units and for determining a focusing position of said photographing lens, said control unit determining whether the first ranging result obtained by said first ranging unit is larger than a first predetermined distance which is relatively short, and, when said control unit determines that the first ranging result is larger than the first predetermined distance, said control unit selecting and outputting one of the first and second ranging results which is nearer to a second predetermined distance which is larger than said first predetermined distance, wherein said first and second ranging results indicate distance which are at least one of far from and near to said second predetermined distance; and
 - a focus control unit for receiving the output from said control unit and for controlling said photographing lens on the basis of the output from said control unit.

5,589,912

CAMERA WITH IMAGE STABILIZING DEVICE

Yasuhiko Shiomi, Kawaguchi, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 154,720, Nov. 19, 1993, abandoned, which is a division of Ser. No. 973,955, Nov. 9, 1992, abandoned, which is a continuation of Ser. No. 743,033, Aug. 9, 1991, Pat. No. 5,175,580. This application May 19, 1995, Ser. No. 444,921


Claims priority, application Japan, Aug. 14, 1990, 2-214634

Int. Cl.⁶ G03B 7/00

U.S. Cl. 396—55

15 Claims

1. An apparatus for use with an image blur prevention device including an image blur detection unit and an image blur prevention unit responsive to an output of the image blur detection unit for preventing image blur, the apparatus comprising:
 - a determination device for determining a state of a power supply for supplying power to the image blur prevention device; and



a control device for controlling the image blur prevention unit in a first control mode or a second control mode, said control device switching between the first control mode and the second control mode in accordance with a determination result of said determination device.

5,589,913

Patent Not Issued For This Number

5,589,914

DENSITY DETECTING DEVICE USED FOR IMAGE FORMING APPARATUS

Kenji Katsuhara, Osaka, Japan, assignor to Mita Industrial Co., Ltd., Osaka, Japan


Filed Aug. 21, 1995, Ser. No. 517,232

Claims priority, application Japan, Sep. 20, 1994, 6-225177

Int. Cl.⁶ G03G 15/00

U.S. Cl. 399—60

16 Claims



15. A density detecting device for detecting a density of a toner image formed by an image forming apparatus including a photoreceptor on which an electrostatic latent image is formed and a developing device for developing the electrostatic latent image formed on the photoreceptor into a toner image, the density detecting device comprising:
 - a density sensor for irradiating light onto a photoreceptor to output density data corresponding to an amount of light reflected from the photoreceptor and capable of varying an amount of light to be irradiated onto the photoreceptor;

means for finding a first amount of light to be irradiated onto the photoreceptor to detect a toner image density from the density sensor at a time of initialization;

characteristic curve acquiring means for setting the first amount of light as the amount of light to be irradiated onto the photoreceptor, and further for causing the density sensor to detect a density of a toner image having a known density, at the time of initialization, thereby to acquire an input-output characteristic curve of the density sensor;

means for finding a second amount of light to be irradiated onto the photoreceptor from the density sensor in order to detect a toner image density at a time of density detection; and

density operating means for referring to the density data outputted by the density sensor and the input-output characteristic curve, at the time of density detection, to find the toner image density.

5,589,915

ELECTROPHOTOGRAPHIC IMAGE FORMING APPARATUS WITH TONER BOX EXCHANGE ALARM FEATURE


Kouji Hashimoto, Matsudo, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Mar. 14, 1995, Ser. No. 403,412

Claims priority, application Japan, Mar. 15, 1994, 6-044035; Mar. 7, 1995, 7-047241

Int. Cl.⁶ G03G 21/10

U.S. Cl. 399—120



16. An image forming apparatus for forming an image on a recording medium, comprising:

- a main body of the image forming apparatus;
- a toner container mounting means for removably mounting a toner container for containing toner removed from an image bearing member provided in said main body, said toner container being removably mounted to said main body; and
- a detection means for detecting a condition that the toner in said toner container has not risen to a predetermined amount when said toner container is mounted onto said main body and a condition that said toner container is not mounted onto said main body.

5,589,916

DEVELOPING APPARATUS


Masaki Sutoh, and Shinichi Fukunaga, both of Saitama, Japan, assignors to Fuji Xerox Co., Ltd., Tokyo, Japan

Filed May 27, 1994, Ser. No. 250,486

Claims priority, application Japan, May 28, 1993, 5-126668; Apr. 8, 1994, 6-070590

Int. Cl.⁶ G03G 15/06

U.S. Cl. 399—286



1. A developing apparatus, comprising:
- an electrostatic latent image holder; and
 - a developer support for supplying a charge developer to an electrostatic latent image formed on said electrostatic latent image holder.

said developer support having a nonmagnetic substrate in a shape of a hollow cylinder, wherein said substrate comprises at least one metal and an amorphous film formed on said

nonmagnetic substrate, wherein said amorphous film consists essentially of an element selected from chrome or zinc, said at least one metal, oxygen, and hydrogen.

5,589,917

DONOR ROLLS WITH MAGNETICALLY COUPLED (TRANSFORMER) COMMUTATION


Steven C. Hart, Webster, and Delmer G. Parker, Rochester, both of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Sep. 25, 1995, Ser. No. 533,627

Int. Cl.⁶ G03G 15/08

U.S. Cl. 399—274

19 Claims



1. A donor roll for transporting marking particles to an electrostatic latent image recorded on a surface, comprising:
- electrostatic latent image recorded on a surface, comprising:
 - a rotatably mounted body;
 - an electrode member mounted on said body;
 - a magnetically permeable core external to said body and rotatable therewith;
 - an electrically conductive material positioned on said core, said material electrically connected to said electrode member; and
 - a second magnetically permeable core spaced from said first mentioned magnetically permeable core.

5,589,918

PROCESS CARTRIDGE, ASSEMBLY METHOD THEREFOR AND ELECTROPHOTOGRAPHIC APPARATUS

Haruhisa Oshida, Hatogaya; Keiji Okano, Tokyo; Masahide Kinoshita; Koji Takahashi, both of Yokohama; Yasushi Shmizu, Tokyo, and Akira Domon, Kawasaki, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Jan. 30, 1995, Ser. No. 380,420

Claims priority, application Japan, Jan. 28, 1994, 6-008568

Int. Cl.⁶ G03G 15/06

U.S. Cl. 399—114

41 Claims



1. A process cartridge detachably mountable to an image forming apparatus, wherein said image forming apparatus includes light

5,589,920

IMAGE FORMING APPARATUS IN WHICH PLURAL TRANSFER MEDIA ARE CARRIED CONCURRENTLY

Takahiro Kubo, Tokyo; Masashi Suda, Iruma; Yoshihiro Murasawa, Yokohama; Takashi Hasegawa, Ageo; Satoshi Tamura, Yokohama; Hisashi Fukushima, Kawasaki, and Takeshi Menjo, Tokyo, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 281,627, Jul. 28, 1994, abandoned.


This application Jun. 30, 1995, Ser. No. 497,340

Claims priority, application Japan, Jul. 30, 1993, 5-208314; Aug. 3, 1993, 5-212262; Dec. 24, 1993, 5-347983

Int. Cl.⁶ G03G 15/14

U.S. Cl. 399—145

37 Claims



14. An image forming apparatus comprising:

an image carrier for carrying an image thereon;

a transfer material bearing member for bearing and conveying a transfer material to a transfer position on said image carrier, said transfer material bearing member being capable of bearing multiple transfer materials concurrently; and

transfer means for transferring the image on said image carrier onto one or more transfer materials borne on said transfer material bearing member at said transfer position;

wherein in consecutively transferring the image onto M transfer materials, in which a number M is not divisible by a maximum number N of transfer materials that the transfer material bearing member is capable of bearing concurrently, said transfer material bearing member concurrently bears, at a first time, P transfer materials, where P is a number which is greater than or equal to 1 and which corresponds to a remainder obtained when M is divided by N, and wherein at other times, said transfer material bearing member bears N transfer materials.

5,589,921

INTERMEDIATE TRANSFER MEMBER HAVING A MATERIAL WHICH BREAKS DOWN IMPURITIES

Peter R. Markies, Grubbenvorst, and Mark Miedema, Em Velden, both of Netherlands, assignors to Océ-Nederland, B.V., Venlo, Netherlands

Filed Mar. 10, 1995, Ser. No. 402,051

Claims priority, application Netherlands, Mar. 11, 1994, 9400382

Int. Cl.⁶ G03G 13/16

U.S. Cl. 399—297

30 Claims

1. A device for transferring a toner image from an image-forming medium to a receiving material comprising:

emitting means and light receiving means cooperative with said light emitting means to detect an amount of toner in a part of said process cartridge, said process cartridge comprising:

- an electrophotographic photosensitive member;
 - process means actable on said electrophotographic photosensitive member;
 - a toner container, adapted for being mounted in the part of said process cartridge, for containing the toner to be used for developing a latent image formed in said electrophotographic photosensitive member;
 - a light transmitting member, provided in said toner container, for transmitting light emitted from said light emitting means to the light receiving means to permit detection of the amount of the toner in said toner container when said process cartridge is mounted to a main assembly of said image forming apparatus;
 - a cover member movable between a protecting position for protecting said electrophotographic photosensitive member and a retracted position wherein said cover member is retracted from the protecting position;
- wherein in response to mounting of said process cartridge to the image forming apparatus, said cover member moves from a position where it covers a part of said photosensitive member toward a position beyond where said light transmitting member is disposed.

5,589,919

TONER CARTRIDGE AND COLOR IMAGE FORMING APPARATUS IN USE THEREWITH

Yoshikazu Ikunami; Satoshi Minami, and Yozo Fujii, all of Hachioji, Japan, assignors to Konica Corporation, Japan


Filed Apr. 18, 1995, Ser. No. 423,314

Claims priority, application Japan, Apr. 26, 1994, 6-088807; May 26, 1994, 6-112812

Int. Cl.⁶ G03G 15/08


U.S. Cl. 399—262

16 Claims



1. A toner supplying apparatus for supplying a toner to a developing station of an image forming machine, comprising:

- a toner cartridge;
- a toner receiver means for receiving said toner from said toner cartridge and for conveying said toner to said developing station;
- said toner cartridge including:
- a cylindrical container for accommodating toner therein; wherein said cylindrical container includes an spiral protrusion, provided on an inner circumferential surface of said cylindrical container, for conveying said toner in a direction of an axis in said cylindrical container when said cylindrical container is rotated on said axis;
- wherein said toner cartridge and said toner receiver are arranged on a same horizontal plane; and
- a scoop for scooping said toner conveyed by said spiral protrusion and for discharging said toner to said toner receiver; said scoop operating to scoop said toner during said rotation of said cylindrical container.



- a light source means for emitting optical energy in response to electrical energy;
- a detector for providing an electrical output signal in response to incident optical energy;
- a propagation means defining a path for delivering optical energy from the light source means to the optical fiber under test, whereby optical energy is launched into the fiber under test, and for delivering optical energy from the optical fiber under test to the detector, at least one segment of the path defined by the propagation means being a segment in which the optical energy is propagated in free space as an unconfined beam, and said propagation means comprising at least a first optical fiber segment and a second optical fiber segment, the first and second optical fiber segments being separated across said one segment of the path;
- an optical attenuator element, and
- a positioning means for displacing the optical attenuator element between a first position, in which it is out of said path, and a second position, in which it is interposed in said one segment of the path.

5,589,934

LIGHT MEASURING APPARATUS CAPABLE OF MEASURING AMBIENT LIGHT AND FLASH LIGHT
 Norihisa Hosoi, Toyokawa; Susumu Shirai, Toyohashi; Ken-ichiro Hibi, Toyokawa; Yoshihiro Okui, Daitoh; Takehiro Katoh, Nara, and Yoshihiko Azuma, Kawasaki, all of Japan, assignors to Minolta Co., Ltd., Osaka, Japan


Filed Jan. 5, 1995, Ser. No. 368,876

Claims priority, application Japan, Jan. 17, 1994, 6-002977

Int. Cl. G01J 1/46; G03B 15/05

U.S. Cl. 356-218

7 Claims



1. A light measuring apparatus capable of measuring ambient light and flash light, comprising:
- a photoelectric sensor to convert the light to be measured into an electric signal;
- a manual operating member which is manually operated by the user to start light measurement;
- a generating device to generate a flash light emission signal in response to the operation of said manual operating member and to transmit said flash light emission signal to the flash unit where the flash unit is connected to the apparatus using a cord;

- a detecting device to detect the emission of flash light by monitoring a sudden change in the intensity of the light being measured;
- an integration circuit to perform integration of electric signals output by said photoelectric sensor;
- a control device to regulate said integration circuit such that said integration circuit performs integration twice at prescribed intervals in response to the operation of said manual operating member;
- a first mode in which light measurement is conducted without any flash light emission;
- a second mode in which the flash unit is connected to the apparatus using a cord and light measurement begins at the same time as the transmission of said flash light emission signal to the flash unit through the cord;
- a third mode in which the flash unit is not connected to the apparatus and light measurement begins in response to the detection of flash light emission by said detecting device;
- a determining device to determine the mode in which light measurement took place based on an electric signal output by said photoelectric sensor; and
- a calculator to calculate measurement values for the mode used based on the output from said integration circuit wherein said determining device compares the two outputs generated from said two integrations by said integration circuit and determines that light measurement took place in the first mode when the two outputs generated by said two integrations are almost equal, and wherein said calculator calculates measurement values for the first mode based on either of said two outputs from said integration circuit.

5,589,935


TURBIDITY SENSOR WITH THE CAPABILITY OF REGULATING THE INTENSITY OF A LIGHT SOURCE
 James R. Biard, Richardson, Tex., assignor to Honeywell, Inc., Minneapolis, Minn.

Filed May 25, 1995, Ser. No. 452,607

Int. Cl. G01N 21/00; D06F 33/00; B08B 3/00

U.S. Cl. 356-339

4 Claims



1. A turbidity sensor, comprising:
- a light source;
- a first light sensitive component, said light source and said first light sensitive component being spaced apart to provide a gap therebetween, said gap being shaped to permit a fluid to be disposed between said first light sensitive component and said light source, light from said light source being transmittable through said fluid for receipt by said first light sensitive component, the intensity of said light received by said first light sensitive component being indicative of the level of turbidity of said fluid;
- a second light sensitive component, said second light sensitive component being disposed proximate said light source, said first and second light sensitive components being photo-diodes;
- means for preventing said fluid from interfering with the transmission of light from said light source to said second light sensitive component;

5,589,937

FIBER OPTIC SELF-MULTIPLEXING AMPLIFIED RING TRANSDUCER AND FORCE TRANSFER SENSOR WITH PRESSURE COMPENSATION


Michael R. Brininstool, La Jolla, Calif., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Continuation-in-part of Ser. No. 339,992, Oct. 31, 1994, abandoned. This application May 2, 1995, Ser. No. 434,366

Int. Cl. G01B 9/02; G01L 1/24

U.S. Cl. 356-352

29 Claims



1. A fiber optic sensor system, comprising:
- a first optical power source for generating a light pulse;
- an optical fiber loop system coupled to receive said light pulse, wherein said light pulse circulates in said optical fiber loop system at a circulation frequency, and which includes:
- a transducer which modulates said circulation frequency in response to detecting a changing physical condition;
- an optical fiber gain medium for amplifying said light pulse;
- a second optical power source for providing optical energy to said optical fiber gain medium; and
- a detector system for receiving a portion of said light pulse received from said optical fiber loop system and generating an output signal representing said circulation frequency.

5,589,938

METHOD AND APPARATUS FOR OPTICAL INTERFEROMETRIC MEASUREMENTS WITH REDUCED SENSITIVITY TO VIBRATION


Leslie L. Deck, Middletown, Conn., assignor to Zygo Corporation, Middletown, Conn.

Filed Jul. 10, 1995, Ser. No. 499,969

Int. Cl. G01B 9/02

U.S. Cl. 356-359

26 Claims



1. A method for providing interferometric measurements having reduced sensitivity to vibration comprising the steps of:
- amplitude splitting an interference pattern into a first and a second interferogram;

- means for regulating the intensity of light received by a preselected one of said first and second light sensitive components from said light source to a predetermined magnitude, said regulating means comprising a means for regulating the intensity of light received by said first light sensitive component by controlling the magnitude of current flowing through said light source;
- means for comparing a first signal from said first light sensitive component to a threshold magnitude; and
- means for providing a second signal which is representative of the difference between said first signal and said threshold magnitude; and
- means for controlling an electrical current provided to said light source as a function of said second signal.

5,589,936

OPTICAL MEASURING APPARATUS FOR MEASURING PHYSICHEMICAL PROPERTIES

Kiyoshi Uchikawa, Tokyo; Takayuki Suga, and Akira Furusawa, both of Tsukuba, all of Japan, assignors to Nikon Corporation, Tokyo, Japan


Filed Sep. 10, 1993, Ser. No. 120,874

Claims priority, application Japan, Sep. 14, 1992, 4-244637; Oct. 22, 1992, 4-284701; May 26, 1993, 5-123778; May 26, 1993, 5-123779

Int. Cl. G01B 9/02

U.S. Cl. 356-345

16 Claims




1. An optical measuring apparatus comprising:
- a laser beam source;
- a light splitter for splitting light emitted from said laser beam source into two beams transmitting in different directions;
- an optical delay unit disposed in an optical path of one of said beams outgoing from said light splitter;
- a phase modulator disposed in an optical path of the other of said beams outgoing from said light splitter, for phase-modulating said other beam by a predetermined frequency;
- an optical mixer for mixing two beams respectively outgoing from said optical delay unit and from said phase modulator;
- an illumination optical system for guiding a mixed beam outgoing from said optical mixer onto a specimen to form a light spot thereon;
- a photodetector for detecting light from said specimen; and
- signal processing means for extracting a modulation component with a frequency even times larger than the modulation frequency of said phase modulator from an output signal from said photodetector and detecting an intensity of optical echo depending upon an optical delay time set by said optical delay unit.

imaging said first interferogram onto a first detector having a first data acquisition rate for acquiring a first data set of interferograms;
 imaging said second interferogram onto a second detector having a second data acquisition rate for acquiring a second data set of interferograms, said second data acquisition rate being different than said first data acquisition rate, with said first data acquisition rate comprising a first frame rate for providing a first data set as said first data set and said second data acquisition rate comprising a slow frame rate for providing a slow data set as said second data set;
 providing substantially identical frame integration periods which overlap in time said first and second detectors;
 analyzing said first data set for phase for said interferograms in said fast data set and analyzing said first data set for phase at each image point on each frame of said fast data set;
 determining a phase difference between said interferograms in said slow data set from said phases derived from said fast data set; and
 analyzing said slow data set with said phase differences while accounting for non-equal phase separations between interferograms; wherein the phase separation between acquired interferograms may be dynamically measured while enabling correction of phase errors due to instrument inaccuracies and external vibrations calculating a phase increment between each frame in said slow data set using said fast data set using said fast data set phases and analyzing said low data set for phase at each image point using said calculated phase increments.

5,589,939

LASER SURVEYING SYSTEM

Elchi Kitajima, Yokohama, Japan, assignor to Nikon Corporation, Tokyo, Japan
 Continuation of Ser. No. 363,342, Dec. 23, 1994, abandoned.
 This application Feb. 21, 1996, Ser. No. 604,294
 Claims priority, application Japan, Dec. 28, 1993, 5-348925
 Int. Cl.⁶ G01B 11/00; G01C 5/00
 U.S. Cl. 356—375 14 Claims



1. A laser surveying system comprising:
 a light projector which projects a laser beam in a direction that rotates around a rotational axis and within a plane perpendicular to said rotational axis to sweep an object;
 an angle detector to detect a rotational angle, at which said laser beam is being projected, substantially continuously throughout a sweep range of said laser beam;
 a reflector to be provided on the object and including means for converting said laser beam into a reflected laser beam containing two-dimensional positional data; and
 a light receiving unit which receives the reflected laser beam and generates an output indicating a three-dimensional position of the reflector based on the rotational angle detected by said angle detector and the two-dimensional positional data contained in the reflected laser beam.

5,589,940
 APPARATUS FOR MEASURING THE CURVATURE OF A SURFACE USING MOVEABLE REFLECTING AND FOCUSING ELEMENTS


Joerg W. Hollmann, Midland, Canada, assignor to Hughes Electronics, Los Angeles, Calif.

Filed Dec. 21, 1994, Ser. No. 361,260

Int. Cl.⁶ G01B 11/24; G02B 7/04; 27/40

U.S. Cl. 356—376

22 Claims



1. Apparatus for measuring the curvature of a surface of an object at a first position on the surface comprising:
 a frame;
 means for moving said frame relative to said object to provide a frame position signal;
 light source means for providing incident light;
 means disposed adjacent to said light source means for focussing said incident light said focussing means including means for transmitting light onto said reflecting means and means for receiving return light from said reflecting means and for transmitting return light to said light source means to provide a focus signal;
 means disposed adjacent to said focussing means for reflecting said incident light onto said surface and for reflecting return light from said surface to said focussing means;
 means for rotating said reflecting means to provide an angle position signal for the reflecting means;
 means for moving said focussing means to provide a focus position signal; and
 control means including a processor means for receiving said frame position signal, said angle position signal, said focus position signal, and said focus signal to calculate the curvature of said surface at said first position.

5,589,941

DEVICE FOR THE MEASUREMENT OF A PROFILE ON A PLANE SURFACE

Jacques Sabater, Gif Sur Yvette; Guy E. P. Tourtollet, Tencin, and Gérard Jayet, Oyeu, all of France, assignors to Centre Technique de L'Industrie des Papiers, Cartons et Celluloses, France


Filed Apr. 12, 1995, Ser. No. 421,053

Claims priority, application France, Apr. 12, 1994, 94 04672
 Int. Cl.⁶ G01B 11/02

U.S. Cl. 356—376

11 Claims

1. Apparatus for measuring a relief profile line contained upon a planar surface of a substrate that includes:
 a hand-held measurement head that further includes,
 a light source and a lens means for converting a beam of light emanating from said source into an image in the form of a luminous streak that is perpendicular to a relief profile line being measured wherein the orientation of said beam of light is effected at an angle of incidence (α) having a value about equal to the Brewster angle of the substrate.



means for focussing back-scattered light from the illuminated relief profile line upon a matrix camera which converts received analog light signals into digital output signals, and processing means connected to said camera for processing said digital signals to determine at least one of the geometrical characteristics defining the relief profile line.

5,589,942

REAL TIME THREE DIMENSIONAL SENSING SYSTEM


Steven J. Gordon, Boston, Mass., assignor to Intelligent Automation Systems, Cambridge, Mass.

Filed Apr. 5, 1990, Ser. No. 505,722

Int. Cl.⁶ G01B 11/24

U.S. Cl. 356—376

15 Claims



1. A three dimensional object sensing apparatus comprising:
 an electromagnetic radiation source for illuminating an object to be sensed with a plurality of electromagnetic radiation patterns,
 first and second electromagnetic recording means for recording first and second images, respectively, of the reflection of said patterns off of said object as it is illuminated by said electromagnetic radiation source, wherein said first and second electromagnetic recording means are positioned in any manner relative to each other such that said first electromagnetic recording means records an image containing at least some of the reflected patterns which said second electromagnetic recording means records, and
 data processing means for correlating the reflections of each of said patterns as recorded by said first recording means with the reflection of each of said patterns as recorded by said second recording means and determining the shape or position of said object therefrom,
 wherein said data processing means comprises:
 means for converting each of said images into a series of digital pixel words,
 means for grouping said digital pixel words of each image into stripes, each stripe comprising the digital pixel words corresponding to points illuminated by a single one of said patterns,

means for selecting a single digital pixel word from each stripe from said first image, each of said selected digital pixel words representing a selected point on said object which is illuminated by the associated pattern,
 means for determining an epipolar line in said second image associated with each of said selected digital pixel words,
 means for determining each digital pixel word representing a point in said second image which is both part of a stripe in said second image and part of an epipolar line, said points termed intersection points,
 means for determining the three dimensional coordinate of each of said intersection points,
 means for selecting the single intersection point on each of said epipolar lines which lies closest to one of said patterns as the selected point from said first image associated with each of said epipolar lines, and
 means for determining the shape or position of said object based on the known position of said selected points.

5,589,943

APPARATUS FOR RECORDING DIGITAL STILL IMAGE SIGNALS AND ANALOG STILL IMAGE SIGNALS IN RESPECTIVE RECORDING AREAS

Susumu Kozuki, Tokyo; Isao Harigaya, and Taizou Hori, both of Kanagawa-ken, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 927,213, Aug. 6, 1992, abandoned.


This application Sep. 7, 1994, Ser. No. 303,122

Claims priority, application Japan, Aug. 20, 1991, 3-207829; Sep. 2, 1991, 3-221706; Oct. 21, 1991, 3-272626


Int. Cl.⁶ H04N 5/76; 5/225; 5/78

U.S. Cl. 386—121

14 Claims



10. A video signal recording apparatus, comprising:
 (a) first recording means for recording a moving-image signal in first areas respectively provided in a multiplicity of tracks on a recording medium;
 (b) second recording means for recording a digital still-image signal in second areas which are respectively separated from the first areas in the multiplicity of tracks; and
 (c) controlling means for simultaneously controlling said first recording means and said second recording means;
 said controlling means causing an analog still-image signal for one picture to be automatically recorded a plurality of times instead of the moving-image signal on the first areas correspondingly located the second areas on which the digital still-image signal is recorded once.



distance information which is represented by a value obtained by multiplying the dimension by the magnification.

5,589,950


IMAGE FORMING APPARATUS THAT CORRECTS INPUT GRAY LEVEL-OUTPUT GRAY LEVEL CHARACTERISTIC DATA SUCH THAT OUTPUT GRAY LEVELS GRADUALLY INCREASE WITH HIGHER INPUT GRAY LEVELS NEAR A BOUNDARY

Masaya Fujimoto, and Haruo Yamamoto, both of Osaka, Japan, assignors to Mita Industrial, Co. Ltd., Osaka, Japan
Filed Nov. 30, 1994, Ser. No. 352,088

Claims priority, application Japan, Dec. 3, 1993, 5-339496
Int. Cl.⁶ H04N 1/40; 1/46

U.S. Cl. 358—455

8 Claims



1. An image forming apparatus comprising:
first storing means for storing input gray level-output gray level characteristic data which represent an output gray level relative to an input gray level;
a density processing section which receives input gray level-output gray level characteristic data from said first storing means, said density processing section including second storing means for storing input gray level-output gray level characteristic data transferred from said first storing means, and address generating means for generating addresses corresponding to said second storing means in response to input gray level data, said second storing means and said address generating means cooperating to supply output gray level data from an address in said second storing means when said address is specified by said address generating means;
inputting means for inputting characteristic correcting data, said characteristic correcting data providing input gray level-output gray level corrections corresponding to a plurality of division steps into which input gray levels are divided;

correcting means for correcting input gray level-output gray level characteristic data stored in said first storing means on the basis of characteristic correcting data supplied by said inputting means; and

reversal phenomenon correcting means for correcting, when there occurs at the boundary between adjacent steps such a reversal phenomenon that an output gray level in the step having relatively low input gray levels is higher than an output gray level in the step having relatively high input gray levels in input gray level-output gray level characteristic data obtained by the correction using said correcting means, said input gray level-output gray level characteristic data so that output gray levels gradually increase with higher input gray levels in the vicinity of the boundary.

said reversal phenomenon correcting means including means for finding data of a point A at which a boundary line between the adjacent steps at which the reversal phenomenon occurs and a total output gray level characteristic line corresponding to the step having relatively low input gray levels which is represented by said input gray level-output gray level characteristic data obtained by the correction using the correcting means cross each other.

means for finding data of a point B at which the boundary line between the adjacent steps at which the reversal phenomenon occurs and a total output gray level characteristic line corresponding to the step having relatively high input gray levels which is represented by said input gray level-output gray level characteristic data obtained by the correction using the correcting means cross each other.

finding a point C having an output gray level equal to the output gray level of said point B on the total output gray level characteristic line corresponding to the step having relatively low input gray levels which is represented by said input gray level-output gray level characteristic data obtained by the correction using the correcting means.

finding a point D having an output gray level equal to the output gray level of said point A on the total output gray level characteristic line corresponding to the step having relatively high input gray levels which is represented by said input gray level-output gray level characteristic data obtained by the correction using the correcting means, and

means for finding a found straight line connecting said point C and said point D and changing the input gray level-output gray level characteristic data between the point C and the point D to characteristics represented by the found straight line.

5,589,951

PAD FOR USE IN SCANNING DATA STORED ON A FLAT SURFACE

Horst Woydich, Auf der Haid, 37, D-8190 Wolftratshausen, Germany

PCT No. PCT/EP92/01510, § 371 Date Jan. 4, 1994, § 102(e)
Date Jan. 4, 1994, PCT Pub. No. WO93/01678, PCT Pub. Date Jan. 21, 1993

PCT Filed Jul. 3, 1992, Ser. No. 175,341
Claims priority, application Germany, Jul. 4, 1991, 41 22 205.9; Oct. 29, 1991, 41 35 626.8

Int. Cl.⁶ H04N 1/00; 1/024

U.S. Cl. 358—473

14 Claims

1. A device for scanning patterns from a surface of a pad, the device comprising in combination:

a scanner adapted to be manually moved over said surface to scan data from said patterns thereon;

a plurality of calibration marks, integrated in said pad and provided on said surface thereof and indicating image resolution parameters required for scanned patterns and being detectable by said scanner as said scanner is moved over said surface for immediate calibration of said scanner during a scanning process of said data so that the scanning process

5,589,953

IMAGE INPUT SYSTEM HAVING AN AUTO-FEEDER INCLUDING LOADING MAGAZINE AND DISCHARGE MAGAZINE ARRANGED SIDE BY SIDE AND METHOD

Masashi Tazawa, Nobuhiro Fujinawa, Kumiko Matsui, all of Kanagawa-ken, and Maki Suzuki, Chiba-ken, all of Japan, assignors to Nikon Corporation, Tokyo, Japan


Filed Apr. 24, 1995, Ser. No. 427,230

Claims priority, application Japan, Jun. 24, 1994, 6-143542; Jun. 27, 1994, 6-144894; Jun. 27, 1994, 6-144931; Jun. 28, 1994, 6-146191; Jun. 28, 1994, 6-146202; Aug. 25, 1994, 6-200000

Int. Cl.⁶ H04N 1/04

U.S. Cl. 358—498

40 Claims



may be controlled by a user comparing said calibration marks with image resolution parameters of said scanning process; and
guiding means detachably attached to said pad for guiding said scanner parallel and perpendicular to said calibration marks.

5,589,952

DISC HIGH RESOLUTION SCANNER

Yasushi Sato, Chiba, and Kaname Kamibayashi, Tokyo, both of Japan, assignors to Sony/Tektronix Corporation, Tokyo, Japan



Filed Feb. 27, 1995, Ser. No. 395,121

Claims priority, application Japan, Mar. 18, 1994, 6-073899; Jun. 22, 1994, 6-162895; Oct. 31, 1994, 6-290529


Int. Cl.⁶ H04N 1/08

U.S. Cl. 358—487

18 Claims



1. A scanner apparatus comprising:
rotatable means having a first surface for mounting an original to be scanned and a second surface having a track;
means for rotating the rotatable mounting means;
a structure comprising a first arm disposed for reading the original on the first surface and a second arm disposed for accurately tracing the track on the second surface;
means for moving the structure radially with respect to the rotatable mounting means; and
means for controlling the rotating and moving means so that the first arm reads the original, the controlling means comprising means for regulating the rotating and moving means according to an output from the second arm so that the first arm reads the original at a high resolution.



1. A feeder for use in an image input system adapted to be mounted on an image input device of said image input system, said feeder comprising:

- a loading magazine storing source documents, a source document of said source documents being inserted from said loading magazine into said image input device for reading image data from said source document;
- a discharge magazine storing source documents discharged from said image input device, wherein said loading magazine and said discharge magazine are positioned on one side of said image input device and in parallel and in side-by-side relationship within said feeder; and
- a transport surface extending substantially perpendicular to an edge surface of said loading magazine and an edge surface of said discharge magazine.

5,589,954

γ-CORRECTION CURVE SELECTING APPARATUS AND A γ-CORRECTION CURVE CREATING APPARATUS

Hideyuki Watanabe, Kawasaki, Japan, assignor to Ricoh Company, Ltd., Tokyo, Japan


Filed May 31, 1994, Ser. No. 251,312

Claims priority, application Japan, May 28, 1993, 5-127559
Int. Cl.⁶ H04N 1/56; 1/60

U.S. Cl. 358—518

7 Claims

2. A γ-correction curve creating apparatus for creating a γ-correction curve for each color component in order to convert the density value for each color component obtained by color-dissolving the color image for each pixel by use of a predetermined color dissolving apparatus, comprising:
achromatic color density estimating means for estimating the density value for each color component when said predetermined color image processing apparatus outputs achromatic color;



γ -characteristic estimating means for estimating the γ -characteristic value of said image processing means for each color component in said predetermined color image processing apparatus; and

γ -correction curve creating means for creating the γ -correction curve from the γ -characteristic value emitted from said γ -characteristic estimating means and the density value for each color component of said achromatic color estimating means.

5,589,955

OPTICAL DEVICE AND OPTICAL MACHINING SYSTEM USING THE OPTICAL DEVICE

Jun Amako, Hirotsuna Miura, and Tomio Sonohara, all of Suwa, Japan, assignors to Seiko Epson Corporation, Tokyo, Japan

Continuation of Ser. No. 965,276, Jan. 21, 1993, abandoned.


This application Mar. 18, 1993, Ser. No. 33,217

Claims priority, application Japan, May 21, 1991, 3-116058; May 24, 1991, 3-120383; May 7, 1992, 4-114479; May 14, 1992, 4-122136

Int. Cl.⁶ G03H 1/08

U.S. Cl. 359-9

11 Claims



1. An optical device for reproducing an original image pattern on a subject material, the original image pattern being represented by original image pattern data, the optical device, comprising:

a coherent light source that emits a light having a wavefront;

rewritable spatial light modulation means for controlling the wavefront of the light emitted from said light source to produce a plurality of image patterns on the subject material for reproducing the original image; and

electric processing means for generating a plurality of computer hologram data groups and for sequentially supplying the computer hologram data groups to said rewritable spatial light modulation means, said electric processing means including:

means for receiving and storing the original image pattern data;

means for generating a plurality of random phase distribution data groups;

means for multiplying the original image pattern data by each group of the random phase distribution data to produce, respectively, a plurality of data sets, and

means for converting the plurality of data sets produced from said multiplying means to a plurality of computer hologram data groups, respectively, with each computer hologram data group representing one image frame;

wherein the random phase distribution data groups are statistically uncorrelated one another;

wherein said electric processing means supplies the plurality of computer hologram data groups to said rewritable spatial light modulation means on a group-by-group basis, so that the image frames as represented by the computer hologram data groups are supplied to said rewritable spatial light modulation means on a frame-by-frame basis;

wherein said rewritable spatial light modulation means produces and projects an image pattern on the subject material on a pattern-by-pattern basis for each computer hologram data group received from said electric processing means, so that a plurality of image patterns are projected in a series manner and are superposed and integrated at a substantially same location on the subject material to reproduce the original image pattern.

5,589,956

IMAGE DISPLAY APPARATUS

Hideki Morishima, Tokyo; Susumu Matsumura, Kawaguchi; Naosato Taniguchi; Yoko Yoshinaga, both of Machida; Shin Kobayashi, Atsugi; Toshiyuki Sudo, Kawasaki, and Tadashi Kaneko, Isehara, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 102,995, Jul. 28, 1993, abandoned.


This application Apr. 4, 1996, Ser. No. 626,901

Claims priority, application Japan, Jul. 31, 1992, 4-224869

Int. Cl.⁶ G02B 5/32

U.S. Cl. 359-15

15 Claims



a display control circuit for causing said liquid crystal display device to display at least one of characters and forms;
 a temperature sensor for detecting a temperature of an atmosphere in which said liquid crystal display device and said compensating liquid crystal device are set, to provide an initial optimum value range for one or more drive voltages;
 light detecting means for measuring and calculating a display contrast of said liquid crystal display device;
 at least two drive voltage control circuits for controlling said drive voltages, said drive voltages applied to said liquid crystal display device and said compensating device; and
 a displaying light source,
 wherein said liquid crystal display device and said compensating liquid crystal device are driven with said drive voltages which are adjusted according to the calculation of contrast made with the aid of said light detecting means.

5,589,961

OPTICAL WAVE GUIDE DRIVEN LIQUID CRYSTAL DISPLAY EMPLOYING OPTICAL SWITCHING FOR INPUT

Mitsuhiro Shigeta, Kyoto, and Keisaku Nonomura, Nara, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan


Division of Ser. No. 43,477, Apr. 7, 1993, Pat. No. 5,455,883.
 This application May 24, 1995, Ser. No. 449,664

Claims priority, application Japan, Apr. 7, 1992, 4-85428; Apr. 5, 1993, 5-78377

Int. Cl.⁶ G02F 1/1343

U.S. Cl. 349-41

7 Claims



1. A liquid crystal display apparatus comprising:
 a display medium;
 a plurality of pixel electrodes arranged in row and column directions for driving said display medium;
 a plurality of signal lines arranged in the row or column direction;
 a plurality of photoconductors having photoconductive portions provided for said plurality of pixel electrodes, respectively, said photoconductors functioning to connect or disconnect said signal lines to or from said pixel electrodes in accordance with an optical signal which illuminates said photoconductive portions; and
 an optical input device, a part of said optical input device being disposed in a direction across said plurality of signal lines, said optical input device allowing said optical signal to selectively illuminate said photoconductive portions of said plurality of photoconductors;
 wherein said optical input device includes:
 a transparent substrate;
 a plurality of optical wave guides formed in a surface portion of said transparent substrate;
 an optical input portion provided at one end of said optical wave guide;
 a plurality of optical switch elements provided with said plurality of optical wave guides, respectively; and

a plurality of optical output portions for connecting a side face of said optical wave guide to a surface of said transparent substrate; and
 wherein said plurality of switch elements optically connecting one of said plurality of optical wave guides selectively, said optical signal input from said optical input portion is transmitted through said one of optical wave guide and output from said optical output portions to the outside of said transparent substrate, said optical signal illuminating said photoconductive portions of said plurality of photoconductors, respectively.

5,589,962

ACTIVE MATRIX DISPLAY DEVICE USING ALUMINUM ALLOY IN SCANNING SIGNAL LINE OR VIDEO SIGNAL LINE

Hideaki Yamamoto, Tokorozawa; Haruo Matsumaru, Tokyo; Tetsuaki Suzuki, Mobara; Mitsuo Nakatani, Mobara; Michio Tsukli, Mobara; Akira Sasano, Tokyo; Saburo Oikawa, Hitachi, and Ryoji Oritsuki, Chiba-ken, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of Ser. No. 72,966, Jun. 8, 1993, abandoned.


This application Jun. 6, 1995, Ser. No. 467,967

Claims priority, application Japan, Jun. 8, 1992, 4-147120

Int. Cl.⁶ G02F 1/136

U.S. Cl. 349-46

1 Claim



1. An active matrix display device comprising a plurality of pixels arranged in a matrix, each of said pixels having a pixel electrode and a thin film transistor, said thin film transistor including:
 a gate electrode electrically connected to a scanning signal line;
 a first insulating film formed on said gate electrode;
 a semiconductor layer formed above said first insulating film;
 a source electrode formed on said semiconductor layer and electrically connected to said pixel electrode; and
 a drain electrode formed on said semiconductor layer and electrically connected to a video signal line,
 wherein each of said scanning signal line and said gate electrode is made of an alloy of Al containing Ta and Ti, and a second insulating film formed of an anodized oxide film of said scanning signal line or said gate electrode is formed on the surface of at least one of said scanning signal line and said gate electrode.

5,589,963

PIXELATED COMPENSATORS FOR TWISTED NEMATIC LIQUID CRYSTAL DISPLAYS

William J. Gunning, III, 3924 Calle Valle Vista, Newbury Park, Calif. 91320; Bruce K. Winker, 4438 Sugar Maple Ct., Moorpark, Calif. 93021, and Gene C. Koch, 3090 Deerfield Dr., NE., Swisher, Iowa 52338


Filed Sep. 30, 1994, Ser. No. 313,509

Int. Cl.⁶ G02F 1/1335; 1/1337

U.S. Cl. 349-119

13 Claims

1. A twisted nematic liquid crystal display comprising:
 (a) a polarizer layer;
 (b) an analyzer layer;



- (c) a liquid crystal cell comprising a liquid crystal material disposed between said polarizer layer and said analyzer layer;
 (d) said liquid crystal cell being defined by an optically transparent active matrix substrate and an optically transparent color filter substrate;
 (e) said liquid crystal cell comprising a plurality of pixels;
 (f) each said pixel comprising a pair of oppositely oriented liquid crystal tilt domains;
 (g) each said tilt domain being defined by a liquid crystal alignment region on said active matrix substrate and a liquid crystal alignment region on said color filter substrate;
 (h) a positively birefringent O-plate compensator layer having a plurality of segments, said segments on an interior surface of one of said optically transparent substrates, each said segment corresponding to a respective liquid crystal tilt domain and having an optical configuration that is optimized for that liquid crystal tilt domain;
 (i) a first positively birefringent A-plate compensator layer disposed between said liquid crystal material and said O-plate compensator layer; and
 (j) a second positively birefringent A-plate compensator layer disposed between one of said optically transparent substrates and said polarizer.

5,589,964

FERROELECTRIC LIQUID CRYSTAL DEVICE WITH MINUTE CONVEXITIES BETWEEN ADJACENT ELECTRODES

Yoshio Hotta; Yukio Hanyu, both of Atsugi; Tadashi Mihara, Isehara; Yasuto Kodera, Fujisawa, and Katsutoshi Nakamura, Atsugi, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 8,607, Jan. 22, 1993, Pat. No. 5,467,209.

This application Apr. 27, 1995, Ser. No. 431,564


Claims priority, application Japan, Jan. 24, 1992, 4-011025; Jan. 24, 1992, 4-032861

Int. Cl.⁶ G02F 1/141; 1/1333

U.S. Cl. 349-160

8 Claims

1. A ferroelectric liquid crystal device, comprising: a pair of substrates each having thereon a group of stripe-shaped electrodes, and a ferroelectric liquid crystal disposed between the substrates, wherein a groove having minute convexities is formed between neighboring stripe-shaped electrodes on a substrate, and the neighboring stripe-shaped electrodes on the substrate extend in a direc-



tion which forms an angle of 45-135 degrees with a normal to smectic layers of the liquid crystal.

5,589,965

WIDE VIEWING-ANGLE DYE-DOPED TN LCD WITH RETARDATION FILMS

Birendra Bahadur, Etobicoke, and Kam H. Wan, Mississauga, both of Canada, assignors to Litton Systems (Canada) Limited, Ontario, Canada


Filed Jun. 23, 1994, Ser. No. 264,300

Claims priority, application Canada, Jun. 24, 1993, 2099642
 Int. Cl.⁶ G02F 1/1335; C09K 19/60

U.S. Cl. 349-165

11 Claims

Scanning Direction: 45 deg.



1. A liquid crystal display, comprising:
 a) a cell containing twisted nematic liquid crystal having a predetermined percentage of black dichroic dye mixed therein for maximizing contrast ratio at a 90° scanning direction to said cell;
 b) a first polarizer adjacent one side of said cell and having a first polarization axis;
 c) a second polarizer adjacent an opposite side of said cell and having a second polarization axis approximately parallel to said first polarization axis; and
 d) a pair of retardation films intermediate said cell and said second polarizer, said pair of retardation films having respective slow axes thereof oriented at predetermined angles to said first polarization axis for maximizing contrast ratio at -45° and +45° scanning directions to said cell.

5,589,966

ANTIFERROELECTRIC LIQUID CRYSTAL LIGHT MODULATION DEVICE

Hideo Hama, and Yukari Sakai, both of Sodegaura, Japan, assignors to Mitsui Petrochemical Industries, Ltd., Tokyo, Japan


Filed May 3, 1994, Ser. No. 237,120

Claims priority, application Japan, May 11, 1993, 5-109512
 Int. Cl.⁶ G02F 1/141; 1/1347

U.S. Cl. 349-194

4 Claims

1. A liquid crystal element consisting of at least one liquid crystal cell, each liquid crystal cell comprising



a pair of spaced apart transparent substrates, each of said substrates having laminated thereon in the following order, a transparent electrode and a transparent orientation control film, and an antiferroelectric liquid crystal material layer sandwiched between said orientation control films; and voltage signal input means electrically connected with each of said transparent electrodes; wherein the polarization direction of a linear polarized monochromatic light transmitted by the liquid crystal element changes by approximately 90° when a given voltage signal is input to the liquid crystal element from the voltage signal input means; and wherein the antiferroelectric liquid crystal material layer is formed from liquid crystal molecules having a tilt angle of 21° to 24°; the thickness d (μm) of the antiferroelectric liquid crystal material layer contained in the liquid crystal cell for forming the liquid crystal element satisfies the following formula:

$$d = \lambda / 2(n_e - n_o)$$

wherein n_e is a refractive index of the liquid crystal molecule of the antiferroelectric liquid crystal material layer in the major axis direction in the case where the given voltage signal is input to the liquid crystal element, n_o is a refractive index of the liquid crystal molecule of the antiferroelectric liquid crystal material layer in the minor axis directions in the above case, and λ (μm) is a wavelength of a light incident on the liquid crystal element, said λ is in the range of 0.4 to 0.7 μm , and d is in the range of 1.5 to 4 μm , with the proviso that when the liquid crystal element has more than one antiferroelectric liquid crystal material d is the total thickness of the antiferroelectric liquid crystal material layers;

said device further comprising a linear polarization plate placed at the light incidence side of said liquid crystal element, and optionally, a $\frac{1}{4}$ wave plate placed on the light outgoing side of the liquid crystal element.

5,589,967

METHOD AND DEVICE FOR TRANSMITTING AND SWITCHING PACKETS IN AN OPTICAL NETWORK
René Auffret, Perros Guirec, France, assignor to France Telecom Etablissement Autonome de Droit Public, Paris, France
Filed Dec. 27, 1994, Ser. No. 364,089


Claims priority, application France, Jan. 7, 1994, 94 00114
Int. Cl. H04J 4/00; 14/00

U.S. Cl. 359—123

2 Claims

1. Device for transmitting and switching packets in an optical network, said device including a transposer, said transposer comprising:

N 2 to 1 optical couplers, a first input branch of each coupler receiving a tributary signal at a wavelength λ_A , a second input branch of each coupler receiving a continuous emission of a coloring laser at a wavelength λ_i , an output of each optical coupler being transmitted to one of N first semiconductor optical amplifiers, an output of each of said first



semiconductive optical amplifiers comprising a signal at the wavelength λ_A and a complementary signal at the wavelength λ_i ;

an N to 1 mixer which receives said outputs of said first semiconductive optical amplifiers, said mixer having an output;

an optical fiber connecting said mixer output to a 1 to N coupler, said 1 to N coupler having N outputs, each output of said 1 to N coupler having a rejecting filter which eliminates the wavelength λ_A ; and

synthesizer/transposers which function as a tuneable laser and a transposer amplifier, each of the synthesizer/transposers includes an optical fiber loop comprising a second semiconductive optical amplifier, an optical isolator, and a tuneable Fabry Perot filter, and wherein a residual reflectivity of each of the second optical amplifiers is such that said second optical amplifiers generate a modulation of a spectrum of a spontaneous emission, and each of said optical fiber loops define a laser which emits the wavelength λ_i ($i=1$ to N) each time the filter coincides with a resonance of the spontaneous emission.

5,589,968

MODE-LOCKED DIODE LASER BASED OPTICAL COMMUNICATION SYSTEM

Paul May, Abingdon, United Kingdom, assignor to Sharp Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 947,122, Sep. 17, 1992, abandoned.


This application Jan. 27, 1995, Ser. No. 380,248

Claims priority, application United Kingdom, Sep. 20, 1991, 9120117

Int. Cl. H04J 14/02; H04B 10/04

U.S. Cl. 359—124

6 Claims



1. An optical communication system comprising means for generating a plurality of signal carrying sub-carrier channels on respective carriers, each sub-carrier channel being a different respective frequencies each separated from the frequencies of all other said channels by respective predetermined intervals, means for providing a reference sub-carrier on a respective carrier having an intermediate reference frequency such that intervals between the reference sub-carrier frequency and each of the respective signal carrying sub-carrier channel frequencies are distinguishable from each of the predetermined intervals, and means for mixing said

reference sub-carrier with said signal carrying sub-carrier channels to provide difference signals.

5,589,969

WAVELENGTH DIVISION MULTIPLEXED OPTICAL FIBER TRANSMISSION EQUIPMENT

Hideori Taga, Saitama; Noboru Edagawa, Tokyo; Noriyuki Takeda; Shu Yamamoto, both of Saitama-ken, and Shigeyuki Akiba, Tokyo, all of Japan, assignors to Kokusai Denshin Denwa Kabushiki Kaisha, Tokyo, Japan


Filed Oct. 12, 1995, Ser. No. 542,058

Claims priority, application Japan, Mar. 15, 1995, 7-083429

Int. Cl. H04J 14/02

U.S. Cl. 359—124

5 Claims



1. A wavelength division multiplexed optical fiber transmission equipment for transmitting a plurality of signals having different wavelengths by multiplexing the wavelengths, the equipment comprising a WDM optical transmitting terminal including five or more optical transmitters for outputting signals wherein the spacing between the wavelengths of two first signals is re-used as the spacing between the wavelengths of two other signals separated from said first signals by two or more signal wavelengths and there is no periodicity in channel spacings.

5,589,970

LOCKING APPARATUS FOR OPTICAL FREQUENCY MULTIPLEX SYSTEM

Gap Y. Lyu, and Chang S. Park, both of Daejeon, Rep. of Korea, assignors to Electronics and Telecommunications Research Institute, and Telecommunication Authority, both of Rep. of Korea


Filed Apr. 14, 1995, Ser. No. 422,055

Claims priority, application Rep. of Korea, Dec. 2, 1994, 1994-32595

Int. Cl. H04B 10/00; H04J 14/02

U.S. Cl. 359—133

8 Claims



1. A locking apparatus for an optical frequency multiplex system having a plurality of light sources, comprising: local oscillating means for applying low frequency signals to individual light sources for making center frequencies of the light sources dither;

photocoupler means for grouping dithering optical signals outputted from the light sources into a single signal;

resonating means for respectively aligning the dithering optical signals coupled by the photocoupler means with optical frequency slots, the resonating means producing a reflection optical signal from an input portion of the resonating means, the reflection optical signal being received by the photocoupler means;

photodetecting means for converting the reflection optical signal applied by the photocoupling means into a photodetector signal; and

optical frequency stabilizing control means for controlling the light sources on the basis of the photodetector signal received from the photodetecting means.

5,589,971

Patent Not Issued For This Number

5,589,972

SCANNER DRIVE SYSTEM HAVING MINIMUM ROTATIONAL ERROR CARRIAGE SUSPENSION


Mark E. Tellam, Charlestown, Mass.; Mark G. Brook, Londonderry, N.H.; Kevin J. Haded, Chelmsford, and Joseph A. Wheeler, Gloucester, both of Mass., assignors to AGFA Division, Bayer Corporation, Wilmington, Mass.

Continuation of Ser. No. 496,484, Jun. 29, 1995. This application Feb. 12, 1996, Ser. No. 600,392

Int. Cl. G02B 26/08

U.S. Cl. 359—196

10 Claims



1. A system for scanning an original document to obtain a digitized representation of said original document, said scanning system comprising:

- (A) An object focal plane;
- (B) Scanning means, movably disposed for linear motion along a scanning axis, for illuminating a scan line of an original document located in said object focal plane, and for obtaining a digitized representation of said scan line;
- (C) Means for moving said scanning means along said scanning axis to obtain digitized representations of successive scan lines of said original document, said digitized representations of said successive scan lines together comprising said digital representation of said original document; and
- (D) Means for suspending said scanning means along an axis of rotation substantially parallel to, and coincident with, said scan line.

5,589,973

OPTICAL ENCLOSURE FOR HIGH SPEED ROTATING BEAM DEFLECTOR


Gregg R. King, Londonderry, N.H.; John A. Morrell, Wakefield, Mass.; Lawrence S. Blake, Peabody, Mass.; Philip A. Rombult, Bradford, Mass., and Thomas K. Hebert, Groveland, Mass., assignors to AGFA Division, Bayer Corporation, Wilmington, Mass.

Filed May 16, 1994, Ser. No. 243,677

Int. Cl.⁶ G02B 26/08

U.S. Cl. 359—214

8 Claims



1. An optical scanning device comprising:
 - a. optical means;
 - b. rotation means for rotating said optical means about a spin axis;
 - c. enclosure means surrounding said optical means for reducing imaging artifacts on scanned output from said optical scanning device, comprising a non-rotating hollow shield having entrance aperture means for allowing a light beam to enter said hollow shield and project onto said optical means, and exit aperture means for allowing the light beam to exit said hollow shield, said hollow shield having a substantially cylindrical body with a first end and a second end, and a longitudinal axis parallel to the spin axis of said optical means, said entrance aperture means provided at the first end of the cylindrical body with the longitudinal axis passing therethrough, said exit aperture means comprising a radial slot in a peripheral portion of said cylindrical body, said hollow shield mounted to said rotation means at the second end of said cylindrical body; and
 - d. a hollow fan-like portion extending radially outward from said slot in said peripheral portion of said cylindrical body, comprising two fan-like members attached to opposing sides of said slot and extending outward therefrom in planes substantially parallel to the beam exiting said slot and extending substantially away from said cylindrical body thereby enclosing the beam exiting the slot between the two fan-like members of the hollow fan-like portion as the beam is rotated through an angle by said optical means.

5,589,974

MICROMECHANICAL MODULATOR

Keith W. Goossen, Aberdeen, and James A. Walker, Howell, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.


Continuation-in-part of Ser. No. 187,676, Jan. 27, 1994, Pat. No. 5,500,761. This application Jun. 7, 1995, Ser. No. 479,476

Int. Cl.⁶ G02B 26/00

U.S. Cl. 359—290

20 Claims

1. A modulator for modulating an optical signal, the optical signal being comprised of at least one wavelength, comprising:
 - a substrate characterized by a refractive index;
 - a membrane having an optically transparent portion and comprising at least a first layer of material having a refractive index which is approximately equal to the square root of the refractive index of the substrate and a thickness approxi-



mately equal to one-quarter of a wavelength of the optical signal, as measured within the first layer;

a means for supplying bias to the membrane and substrate; and

a flexible support for positioning the membrane in a spaced and superposed relation to the substrate defining an air gap having a variable size; wherein, in the absence of bias, the membrane has a first position and the air gap has a first size and, under the action of bias, the membrane moves to a second position and the air gap has a second size which is approximately an integer multiple of one-quarter of a wavelength of the optical signal, as measured in air, and wherein the size of the air gap when the membrane is in its first position is such that the difference between the first size and the second size is less than one-third of the first size;

wherein the change from the first to the second position causes a change in the amount of the optical signal that is reflected from the membrane.

5,589,975

OPTICAL AMPLIFICATION SYSTEM

Kazunori Nakamura, Yokohama, Japan, and I. Kou Tei, Ontario, Canada, assignors to The Furukawa Electric Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 885,956, May 20, 1992, abandoned.


This application Nov. 4, 1994, Ser. No. 334,444

Claims priority, application Japan, May 20, 1991, 3-143792

Int. Cl.⁶ G02B 6/00; H01S 3/13; H04B 9/00

U.S. Cl. 359—345

4 Claims



1. An optical amplification system comprising an optical amplifier unit having a silicate-glass type or fluoride-glass type optical waveguide capable of amplifying optical signals transmitted through said optical waveguide by means of the effect of optical amplification produced in the optical waveguide when pumped light is fed to said optical waveguide, said amplifier unit being operative only when in a saturated condition, pumped light being fed being to said optical waveguide only when an optical signal stream having an interval shorter than a relaxation life time of the optical waveguide is transmitted through said optical waveguide, no pumped light being fed to said optical waveguide when no optical signal stream is transmitted through said optical waveguide and when an optical signal stream having an interval longer than a relaxation life time of the optical waveguide is transmitted through said optical waveguide.

5,589,976

TELESCOPE WITH REAR CONVERTER AND REAR CONVERSION LENS AND TELESCOPE

Moriyasu Kanai, and Hirofumi Matsuo, both of Tokyo, Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 23, 1994, Ser. No. 362,888

Claims priority, application Japan, Dec. 28, 1993, 5-70809 U; Dec. 5, 1994, 6-301183

Int. Cl.⁶ G02B 21/36; 23/00; 15/02; 13/00

U.S. Cl. 359—362

9 Claims



1. A telescope with a rear converter, comprising:
 - a master telescope whose aberration has been independently corrected and which has an objective lens and an ocular lens; and
 - a rear conversion lens provided on an image side of said objective lens of said master telescope, said rear conversion lens being made of a single lens having a concave surface facing an object side;
- wherein said rear conversion lens satisfies the following formulae:

$$f_o/f_c > 1,$$

and

$$0.5 < (dx_1/dh_1)/(dx_2/dh_2) > 1.3$$

wherein,

" f_o " designates a focal length of said objective lens of the master telescope;

" f_c " designates a resultant focal length of said objective lens of said master telescope and said rear conversion lens;

" dx_1/dh_1 " designates an inclination of an incident surface of said rear conversion lens at an incident point thereof, upon which light is incident at a height h_1 from an optical axis of the rear conversion lens; and,

" dx_2/dh_2 " designates an inclination of an emission surface of said rear conversion lens at an emission point thereof, at which light is emitted from the rear conversion lens at a height h_2 from the optical axis;

and wherein $h_1 = 0.36(f_o)^2/mf_c'$, $h_2 = 0.36(f_o)/m$, and m = magnification of said master telescope.

5,589,977

BINOCULAR TUBE ASSEMBLY FOR A STEREOMICROSCOPE

Christian Lücke, Oberkochen; Uwe Vry, Aalen, and Ulrich Lemcke, Heidenheim, all of Germany, assignors to Carl-Zeiss-Stiftung, Heidenheim-Brenz, Germany

Filed Mar. 20, 1995, Ser. No. 406,400

Claims priority, application Germany, Mar. 24, 1994, 44 10 147.3

Int. Cl.⁶ G02B 21/20


U.S. Cl. 359—375

15 Claims

1. A binocular tube assembly for a stereomicroscope defining at least two stereoscopic component beam paths along first and second optical axes, respectively, said binocular tube assembly comprising:
 - two sets of ocular optics;

pivot means for pivotally mounting said sets of ocular optics to pivot relative to said stereomicroscope through a pregiven angular range;

a prism component group including a deflecting prism having an entry face for receiving said component beam paths therein and an exit face through which said component beam paths



leave said prism; and, two image-reversing roof prisms having respective roof edges, said roof prisms being mounted on one of said faces so as to cause said roof edges to be offset relative to respective ones of said optical axes; and,

an optical deflecting element common to both of said component beam paths and being mounted on said pivot means for deflecting said component beams toward said sets of ocular optics, respectively, for all positions of said ocular optics within said angular range.

5,589,978

DUAL-PATH OPTICAL SYSTEM

Stephen D. Fantone, Lynnfield, Mass., assignor to Mobi Corporation, Lynnfield, Mass.


Division of Ser. No. 118,881, Sep. 9, 1993, Pat. No. 5,469,293.

This application Jun. 7, 1995, Ser. No. 487,837

Int. Cl.⁶ G02B 23/00; 23/08

U.S. Cl. 359—412

7 Claims



1. A dual-path, pseudoscopic optical system comprising:
 - a pair of objectives including right and left objectives arranged along separate optical axes that are spaced apart from one another by a predetermined distance;
 - a pair of eyepieces including right and left eyepieces arranged, respectively, along a pair of rearwardly extending optical axes that are vertically offset with respect to said optical axes of said objectives;
 - a cross-coupled mirror system configured and arranged with respect to said pairs of objectives and said eyepieces to form pseudoscopic images of an object space which can be viewed via said eyepieces with the image formed by said right objective being viewed through said left eyepiece and the image formed by said left objective being viewed through said right eyepiece; and
 - means for adjusting an interpupillary distance between said eyepieces, said means for adjusting an interpupillary distance between said right and left eyepieces is structured and arranged to move one of said eyepieces and one of said objectives in equal and opposite directions while keeping the other of said eyepieces and said objectives stationary.

5,589,979

SIMULATOR ARRANGEMENT

Donald L. M. Martin, Mosman, Australia, assignor to Trutan Pty Limited, Homebush, Australia
 PCT No. PCT/AU93/00037, § 371 Date Mar. 15, 1994, § 102(e)
 Date Mar. 15, 1994, PCT Pub. No. WO93/17366, PCT Pub.
 Date Sep. 2, 1993


PCT Filed Jan. 27, 1993, Ser. No. 211,100

Claims priority, application Australia, Feb. 20, 1992, 11088/92

Int. Cl.⁶ G03B 21/10; 21/56; G02B 5/08; 27/10

U.S. Cl. 359—449

3 Claims



1. A screen simulator arrangement including spaced apart screen means adapted to allow viewing of imagery and one or more mirror means adapted to cause partial reflection of imagery; said screen means being formed with a plurality of spaced apart transparent portions therein producing a distribution of screen pixels in said screen means; said mirror means including at least one curved mirror and being formed or provided with a plurality of holes or openings therein, producing a plurality of reflective portions in said mirror means; said screen means and said mirror means being fixedly mounted relative to each other; the transparent portions of said screen means and the holes or openings of said mirror means being substantially out of register one with the other; an inner screen surface of said screen means and a reflective surface of said mirror means generally facing inwardly towards each other; said transparent portions of said screen means and said holes or openings of said mirror means being so out of register one with the other, such that said screen pixels of said screen means are in substantial alignment/register with holes or openings in said mirror means; the arrangement being such that a projector spaced apart from an outer surface of said mirror means projects images at said outer surface thereof, and through said holes or openings therein, so that imagery will appear on said screen pixels of said screen means in substantial alignment/register with said holes or openings in said mirror means; said imagery being so reflected by said reflective portions of said mirror means, so as to be viewable through said transparent portions in said screen means, from a position spaced apart from an outer surface of said screen means.

5,589,980

THREE DIMENSIONAL OPTICAL VIEWING SYSTEM

Robert Bass, and John Bass, both of 2832 NE. 35th St., Fort Lauderdale, Fla. 33306

PCT No. PCT/US91/09737, § 371 Date Jun. 23, 1994, § 102(e)
 Date Jun. 23, 1994, PCT Pub. No. WO93/13446, PCT Pub.
 Date Jul. 8, 1993

PCT Filed Dec. 23, 1991, Ser. No. 256,402

Int. Cl.⁶ G02B 27/22


U.S. Cl. 359—478

7 Claims

1. An optical viewing system for producing a simulated three dimensional image, comprising:

first means for displaying an image on a first electronic display device;

at least one second means for displaying an image on at least one second electronic display device, said at least one second electronic display device being a substantially transparent



display device, whereby an observer can view through transparent areas of the second electronic display device; said first and second electronic display devices being located at different, predetermined locations along an optical viewing path such that the image displayed by said first electronic display device is projected through said at least one second electronic display device;

wherein said first electronic display device includes an image projector and said second electronic display device includes a controllable pixel display spaced therefrom, said controllable pixel display comprising a positive pixel display panel having a field of pixel elements which are controllably illuminated, said controllable pixel display being substantially transparent such that the image produced by the controllable pixel display is overlaid upon the image produced by said image projector.

5,589,981

RETROREFLECTOR TARGET FOR LASER RANGING

Michel Kasser, Joinville-Le-Pont, and Glenn Lund, Peillon, both of France, assignors to Aerospatiale Societe Nationale Industrielle, Paris, France


Filed Mar. 9, 1995, Ser. No. 401,188

Claims priority, application France, Mar. 10, 1994, 94 02773

Int. Cl.⁶ G02B 5/122

U.S. Cl. 359—529

13 Claims



1. A retroreflective target for laser ranging, said retroreflective target comprising:

at least one hollow cube corner retroreflector comprising three reflective surfaces which are substantially planar, are perpendicular to each other, and intersect at three edges, said three edges being substantially orthogonal to each other and converging at an apex, each of said at least one hollow cube corner retroreflector defining a geometrical normal lying at the same angle to each of said three edges;

a reference point coexisting on said geometrical normal at a predetermined distance from said apex in a direction away from said three reflective surfaces; and

a parallel-sided plate for each surface of said at least one hollow cube corner retroreflector, each said parallel-sided plate spaced a predetermined distance from each surface of said three reflective surfaces, each parallel-sided plate further being transparent to a light to be retroreflected, made from a material having a known refractive index, and having the same thickness.

5,589,982

POLYCHROMATIC DIFFRACTIVE LENS


Dean Faklis, and G. Michael Morris, both of Fairport, N.Y., assignors to Rochester Photonics Corporation, Rochester, N.Y.

Filed Jun. 3, 1994, Ser. No. 254,018

Int. Cl.⁶ G02B 5/18; 27/44

U.S. Cl. 359—565

21 Claims



1. A diffractive lens for directing a plurality of different wavelengths of radiation to a single focus which comprises a diffractive structure having a plurality of zones which define zone boundaries at which light incident on the structure experiences an optical phase shift, and which diffract light of each of said wavelengths in a different diffractive order, m , such that $m \geq 1$, to said focus, thereby providing a plural order diffractive singlet.

5,589,983

METHOD OF MANUFACTURING A DIFFRACTIVE SURFACE PROFILE


Mark M. Meyers, Hamlin, and Mark E. Schickler, Webster, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Dec. 29, 1993, Ser. No. 174,737

Int. Cl.⁶ G02B 26/08

U.S. Cl. 359—566

20 Claims



1. A method of manufacturing a diffractive surface profile comprising:

- rotating a surface to be cut at a high speed W , where $W > 1,500$ RPM;
- translating a cutting tip at a low speed V , where $V < 1.2$ mm/minute; and
- cutting said surface with said cutting tip.

5,589,984

OVAL ELLIPTICAL MIRROR

William P. Schmidt, Rockwood, and Franklin D. Hutchinson, New Boston, both of Mich., assignors to Mirror Lite of North Carolina, Shallotte, N.C.

Division of Ser. No. 942,294, Sep. 9, 1992. This application
 Nov. 17, 1994, Ser. No. 341,665


Int. Cl.⁶ G02B 5/08; 5/10; 7/182; B60R 1/06

U.S. Cl. 359—603

9 Claims

1. A mirror assembly, comprising:

- a mirror lens having a reflective outer surface and a non-reflective rear surface, the mirror lens comprising a mirror body which terminates in an oval perimetral edge, the edge surrounds the reflective surface and the non-reflective surface



of the mirror lens, the mirror body being a substantially convex ellipsoid having a major axis and a minor axis which intersects with the major axis, the major axis having a varying radius of curvature, which radius decreases from the intersection with the minor axis to the perimetral edge.

5,589,985

COMPUTER MONITOR HOOD


Philip Heller, 216 Coldstream Ave., Toronto, Ontario, Canada, and David Heller, 41 Ezrat Tora, Jerusalem, Israel

Filed Jun. 9, 1995, Ser. No. 488,908

Int. Cl.⁶ G02B 27/00

U.S. Cl. 359—608

13 Claims



1. A computer monitor hood for use in conjunction with a computer monitor having a top surface, left and right side surfaces, and a forwardly facing screen, said computer monitor hood comprising:

a top shading panel having a front edge, a rear edge, and left and right side edges;

left and right side shading panels operatively attached to said top shading panel and disposed in generally vertically oriented relation to said left and right side edges of said top shading panel, respectively, left and right side shading panels each having front, rear, and bottom edges;

a front-to-rear main axis; and

at least one counterweight of weight to balance said computer monitor hood, mounted on a receiving portion of said computer monitor hood in selectively manually movable relation among any one of a plurality of front-to-rear positions so as to permit said counterweight to balance said computer monitor hood at a selected position on the computer monitor;

wherein said counterweight is operatively mounted on said top surface of said computer hood by means of a hook loop fastener system comprising an elongate strip of one component of said hook and loop fastener system disposed on said computer monitor hood and extending generally parallel to said main axis of said computer monitor hood, with the other component of said hook and loop fastener system disposed on said counterweight; and

wherein, when said computer monitor hood is in place on a computer monitor, said top, left and right shading panels each project forwardly from the front of the computer monitor, at the respective of the top, left side, and right side surfaces of the computer monitor, so as to shade the screen of the computer monitor.

5,589,986

ZOOM LENS


Hironori Shibata, Hachioji, Japan, assignor to Olympus Optical Co., Ltd., Tokyo, Japan

Filed May 9, 1995, Ser. No. 437,477

Claims priority, application Japan, May 18, 1994, 6-103851
Int. Cl.⁶ G02B 15/14; 3/02

U.S. Cl. 359—684

24 Claims



1. A zoom lens comprising, in the order from the object side: a front lens group including a variator lens unit having a negative refractive power; an aperture stop; and a rear lens group arranged behind the aperture stop; wherein the rear lens group includes a lens unit having a positive refractive power, a focusing lens unit having a negative refractive power, a compensator lens unit having a positive refractive power for correcting variation of a position of an image due to variation of magnification; and the distance between the lens unit having the positive refractive power and the focusing lens unit is constant during variation of magnification and variable during focusing.

5,589,987

ZOOM LENS BARREL

Hitoshi Tanaka, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 106,574, Aug. 16, 1993, Pat. No.

5,488,513. This application Aug. 9, 1995, Ser. No. 513,029

Claims priority, application Japan, Aug. 17, 1992, 4-217919
Int. Cl.⁶ G02B 15/14

U.S. Cl. 359—701

7 Claims



1. A zoom lens barrel, comprising: a cam ring that is threadably engaged to a female helicoid formed in a stationary barrel; a linear movement guide member that is rotatable relative to said cam ring and movable in an optical axis direction together with said cam ring; at least three movable lens groups, including first, second and third lens groups that are guided in said optical axis direction by said linear movement guide member, said first, second and

third lens groups being located in this order from an object side of said zoom lens barrel; a first lens frame that holds said first lens group and is provided with a helicoid, wherein another helicoid is formed on said cam ring to engage with said helicoid of said first lens frame; a plurality of cam grooves formed on said cam ring to drive said second and third lens groups behind said first lens group; wherein said helicoid on the first lens frame is a male helicoid, and said helicoid on said cam ring is a female helicoid.

5,589,988

RETROFOCUS-TYPE WIDE ANGLE LENS SYSTEM HAVING A FIXED FRONT LENS GROUP AND A MOVABLE REAR LENS GROUP


Yutaka Suenaga, Yokohama, Japan, assignor to Nikon Corporation, Tokyo, Japan

Continuation-in-part of Ser. No. 231,042, Apr. 22, 1994, abandoned. This application Dec. 7, 1995, Ser. No. 568,522

Claims priority, application Japan, Apr. 26, 1993, 5-099602
Int. Cl.⁶ G02B 13/04

U.S. Cl. 359—752

18 Claims



1. A wide angle lens system comprising: a front lens group; and a rear lens group having positive refractive power; said front lens group including, in the order from the object side, a negative meniscus lens component having a convex surface facing the object side, and a cemented lens component having a negative lens element, a positive lens element and a convex cemented surface with positive refractive power facing the object side; said rear lens group including, a cemented lens component having a positive lens element, a negative lens element and a convex surface facing the object side; wherein the distance between said front lens group and said rear lens group decreases during focusing operation from the infinite object distance toward the shortest object distance.

5,589,989

COMPACT OBJECTIVE LENS SYSTEM

Lee R. Estelle, Rochester, and William T. Goosey, Jr., Fairport, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.


Filed Jun. 29, 1993, Ser. No. 84,387

Int. Cl.⁶ G02B 9/14

U.S. Cl. 359—785

34 Claims

1. A lens system comprising from an object side: a first positive power meniscus lens component having a foremost lens surface convex to the object side; a second bi-concave lens component engaging said first lens component and defining with said first lens component an airspace separating said second lens component from said first component;



- a third bi-convex lens component engaging said second lens component and defining with said second lens component an airspace between said third lens component from said second lens component; and a diaphragm arranged behind the rear-most lens element of the lens system, wherein all of the airspaces between said lens components are so arranged that there exists between all of adjacent lens components an edge contact located only at points located within the region from over 0.0 mm at a position to sufficiently eliminate stray light to about 2 mm beyond clear aperture diameter, and wherein the lens system fulfills the following conditions:

$$N_1 - N_2 \leq 0.1$$

$$\frac{N_1}{N_2} \geq 0.9$$

$$0.25f < \Sigma d < 0.35f$$

where:

f is the composite focal length of the lens system;

Σd is the distance from the vertex of the foremost lens surface to the vertex of the last lens surface;

N₁ represents the refractive index of a positive lens element forming the first lens component;

N₂ represents the refractive index of a negative lens element forming the second lens component; and

N₃ represents the refractive index of a positive lens element forming the third lens component.

5,589,990

LIGHT EMITTING ELEMENT MODULE AND MANUFACTURING METHOD THEREFOR


Takashi Kato, and Hiromi Nakanishi, both of Kanagawa, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan

Filed Jun. 7, 1995, Ser. No. 481,100

Claims priority, application Japan, Jun. 14, 1994, 6-155173
Int. Cl.⁶ G02B 27/02

U.S. Cl. 359—799

5 Claims



1. A light emitting element module comprising: a substrate, said substrate including a portion having a through hole; a light emitting element mounted on said substrate; a lens as an optical system for at least one of the focusing and artificially collimating light emitted from said light emitting element;

a lens holder for holding said lens therein, said lens holder having an insertion portion for being inserted in said through hole and a flange portion having an outer diameter larger than an inner diameter of said through hole; and a spacer inserted between said portion of said substrate and said flange portion of said lens holder for defining a distance between said light emitting element and said lens.

5,589,991

OPTICAL ASSEMBLY WITH FOLDING MIRROR ASSEMBLY


Zvi Bleier, Comack, N.Y., assignor to PLX Inc., Deer Park, N.Y.

Filed Nov. 19, 1993, Ser. No. 156,023

Int. Cl.⁶ G02B 5/08; 7/182; G03B 13/08

U.S. Cl. 359—856

33 Claims



1. A folding mirror assembly, comprising: at least first and second reflecting members, each of said reflecting members comprising first and second panels, each of said panels having a reflecting surface, said reflecting surface of said first panel disposed at substantially a right angle to said reflecting surface of said second panel, and a support panel having a receiving surface, wherein each of said panels has a side at substantially a right angle to said surface of said panel, and wherein each of said panels is abutting and joined along said side to said surface of said panel immediately adjacent to said side; and a plate member having a plurality of mounting pads for mounting said first and second reflecting members thereon so that one of said reflecting surfaces of said first reflecting member is in reflecting relation with one of said reflecting surfaces of said second reflecting member.

5,589,992

MAGNETIC RECORDING AND REPRODUCING APPARATUS FOR PERFORMING SLOW-MOTION REPRODUCTION WITH HIGHER QUALITY OF IMAGE

Hideyo Shibata, Neyagawa; Ritsuro Kinoshita, Hirakata; Takayasu Yoshida, Osaka, and Shigeo Eshima, Otokuni-gun, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan

Filed Aug. 3, 1994, Ser. No. 285,282


Claims priority, application Japan, Aug. 4, 1993, 5-193427; Mar. 29, 1994, 6-057916; Mar. 29, 1994, 6-057918

Int. Cl.⁶ H04N 5/78

U.S. Cl. 386—72

24 Claims

1. A magnetic recording and reproducing apparatus for reproducing a video signal recorded on a video track of a magnetic tape by means of a pair of magnetic heads arranged in a rotation drum so as to oppose to each other at an angle of 180 degrees, while rotating a capstan for moving said magnetic tape in the longitudinal direction thereof, comprising: two memories each for storing a video signal of at least one field;



memory control means for controlling the reproduced video signal to be written into and be read out from said two memories;

reproduced video signal supply means for supplying a reproduced video signal reproduced from the magnetic tape by means of said pair of magnetic heads to said two memories;

control signal reproducing means for reproducing a control signal for tracking control recorded on the magnetic tape;

capstan frequency generating signal generating means for generating a capstan frequency generating signal in synchronous with rotation of said capstan; and

optimum field judgment means for judging a time interval including a timing when a scanning trace of each of said pair of magnetic heads coincides with the video track in the vicinity of the center of the video track based on a head pair switching signal for switching over between said pair of magnetic heads, said control signal, and said capstan frequency generating signal, and supplying a judgment signal representing the time interval;

wherein, when the magnetic tape is continuously moved in a forward or reverse direction at a speed slower than a normal reproduction speed, said memory control means controls the reproduced video signal of one field to be written into one of said two memories for the time interval represented by the judgment signal supplied by said optimum field judgment means, whereas said memory control means simultaneously controls the reproduced video signal of another one field to be read out from another one of said two memories.

5,589,993


DIGITAL HIGH DEFINITION TELEVISION VIDEO RECORDER WITH TRICK-PLAY FEATURES

Saiprasad V. Nalmpally, Langhorne, Pa., assignor to Matsushita Electric Corporation of America, Secaucus, N.J.
Continuation of Ser. No. 21,248, Feb. 23, 1993, abandoned.
This application Nov. 14, 1994, Ser. No. 339,647

Int. Cl. H04N 5/78

U.S. Cl. 386-81

8 Claims



1. Apparatus which processes signals representing video image information to produce a signal to be recorded on a tape by a digital video tape recorder (VTR), whereby the image may be displayed from the recorded signal when the VTR is operating in a trick-play mode, said apparatus comprising:

means for providing a first data stream representing a relatively high resolution video image which has been encoded using motion compensated encoding techniques;

data compression means for compressing the first data stream to generate a segmented second data stream representing a relatively low resolution version of said high resolution image,

wherein the first data stream is independent of the second data stream for reproducing the image, the second data stream is independent of the first data stream for reproducing the image, and each segment of the second data stream may be expanded independently of any other segment;

means for segmenting the first data stream to produce a first set of data segments representing the high resolution image;

means for interleaving respective data segments representing the first and second data streams to generate the signal to be recorded by the VTR, whereby image data recorded in the low resolution data segments is displayed in trick-play mode.

5,589,994

IMAGE RECORDING METHOD AND APPARATUS WITH REDUCED ERROR PROPAGATION

Tatsuo Yamasaki, Ikuo Okuma, and Ken Onishi, all of Nagakakyō, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Aug. 19, 1993, Ser. No. 109,723

Claims priority, application Japan, Aug. 21, 1992, 4-222493; Jul. 29, 1993, 5-208494

Int. Cl. G11B 5/86; 5/09

U.S. Cl. 360-15

10 Claims



1. A method of copying compressed digital data from a first medium to a second medium, comprising the steps of:

(a) reading, from said first medium, compressed digital data comprising codewords having check fields and flags, said flags identifying codewords with uncorrected errors;

(b) using said check fields to correct errors in said codewords;

(c) using said check fields to detected uncorrectable errors in said codewords;

(d) updating said flags to identify codewords in which uncorrectable errors were detected in said step (c); and

(e) recording said compressed digital data as read in said step (a) and corrected in said step (b) on said second medium, together with the check fields used in said steps (b) and (c) and said flags as updated in said step (d).

5,589,995

HEADER INFORMATION OF INFORMATION SIGNAL RECORDING AND REPRODUCING METHOD AND APPARATUS THEREFOR

Seichi Saito, Toshifumi Takeuchi, Masafumi Nakamura, Junji Shiokawa, and Osamu Kawamae, all of Yokohama, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Continuation of Ser. No. 218,701, Mar. 28, 1994, abandoned, which is a continuation of Ser. No. 956,597, Oct. 5, 1992, abandoned, which is a continuation of Ser. No. 428,949, Oct. 30, 1989, abandoned. This application Jan. 11, 1996, Ser. No. 583,861

Claims priority, application Japan, Nov. 2, 1988, 63-276243
Int. Cl. G11B 5/09

U.S. Cl. 360-48

32 Claims

1. A method for processing a digital information signal in a system having a recording medium, the method comprising the steps of:



designating discrete areas on the recording medium;

sequentially arranging a preamble area and a data frame area in each of said discrete areas;

sequentially arranging a plurality of data block areas in said data frame area of each of said discrete areas;

sequentially arranging a header area and a data area for recording said digital information signal in each of said data block areas;

providing a block synchronizing area for recording a block synchronizing signal, block synchronizing signals being identical to one another and indicative of a head position of each said data block area, and a block address area for recording a block address signal for discriminating said data block areas in each said header area;

providing one or more clock regenerating areas for recording a clock regenerating signal for executing bit synchronism and a plurality of dummy header areas to each said preamble areas;

providing a dummy block synchronizing area in each said dummy header area for recording a dummy block synchronizing signal identical with a corresponding block synchronizing signal, and a dummy block address area in each said dummy header area for recording a dummy block address signal for discriminating a position of said dummy block synchronizing area; and

arranging each said dummy block synchronizing area included in each said dummy header area in at least two positions among respective positions of which distance between an arbitrary succeeding two of said dummy block synchronizing areas is substantially the same as the distance between the block synchronizing area included in the first one of said header areas and the adjacent dummy block synchronizing area.

5,589,996

METHOD AND APPARATUS FOR CONTROLLING SPINDLE SPEED TO COMPENSATE FOR DRAG IN A DISK DRIVE SYSTEM

Paul R. Patrick, Longmont, and Walter Wong, Boulder, both of Colo., assignors to Seagate Technology, Inc., Scotts Valley, Calif.


Filed Dec. 13, 1993, Ser. No. 167,317

Int. Cl. G11B 19/24

U.S. Cl. 360-73.03

10 Claims

1. A control system for controlling the speed of a spindle motor for rotating disks in a disk drive system at a constant speed where the transducers ride or fly upon a medium between said disks and said transducers thereby exerting a load upon said spindle motor, said load having a non uniform profile across the disks from the inner diameter to the outer diameter of said disks where said load at any location across said disk is a function of the type of medium upon which said transducers ride or fly above said disks, said location itself and the physical environment being experienced by said medium at any given instant of time, said disk drive system comprising disks having a plurality of concentric addressable tracks between said inner and outer diameters of said disks, a positioning and track following system for moving said transducers to an addressed track on said disk and for maintaining said trans-



5,589,997

TRACKING CONTROL METHOD AND APPARATUS FOR VIDEO RECORDER WHICH ADDS A COMBINED FIRST AND SECOND TRACKING ERROR SIGNAL TO THE NEXT TRACKING ERROR SIGNAL

Jeong-tae Kim, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-do, Rep. of Korea


Filed Jun. 16, 1994, Ser. No. 260,825

Claims priority, application Rep. of Korea, Jun. 16, 1993, 1993-10977

Int. Cl. G11B 5/588; 15/467


U.S. Cl. 360-77.14

9 Claims



1. A tracking control apparatus for read out of information recording on a track of a magnetic tape driven by a capstan motor, said tracking control apparatus comprising:

a capstan speed controller receiving a rotation number signal of said capstan and comparing the input rotation number signal and a predetermined rotation number thereof, thereby outputting a first capstan speed control signal;
 tracking error generating means receiving a pilot signal for generating a tracking error signal;
 a memory for storing a renewed second capstan speed control signal as one of second capstan speed control signals generated respectively at corresponding control positions of a track;
 tracking control means receiving said tracking error signal and a respective one of said second capstan speed control signals, stored in said memory and corresponding to said tracking error signal, for renewing and outputting said second capstan speed control signal as the respective renewed second capstan speed control signal;
 first adding means for adding said respective renewed second capstan speed control signal and said first capstan speed control signal applied from said capstan speed controller to thereby generate a real capstan speed control signal; and
 means for rotatingly driving said capstan in response to the real capstan speed control signal output by said first adding means.



tape (2) circulate in front of the recording head and from a recording reel (6) respectively, a reading head (8), means for having the tape circulate in front of the reading head towards and from a playback reel (7) respectively, both the heads being provided with means enabling them to be actuated independently of each other, a storage hopper (33), located operatively between the two heads (8 and 9) for receiving and storing in loose and random folds a tape portion corresponding to the distance between said first and second regions of the tape, means for selectively actuating the reading head and selectively feeding the tape in forward and reverse in front of the reading head independently of actuation of the recording head, whereby during recording of the first region of the tape by the recording head the second region of the tape can be selectively read by the reading head and fed without being read, selectively with and without change of the distance between the first and second regions of the tape, fitting means (28) for a cassette (1) with two reels (6 and 7) each of which is associated with one of the ends of the tape, the recording and reading heads being arranged so that each one cooperates with one of the cassette reels, one of which in operation constitutes the recording reel and the other the playback reel respectively, and means (3, 24 and 25) for bringing the tape into position in relation to the storage hopper (33) after insertion of the cassette into operational relationship with the fitting means.

5,589,998
CYLINDER ADDRESS STORAGE IN MULTIPLE SERVO SECTORS OF A TRACK
 Mantle M. Yu, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.
 Filed Dec. 22, 1994, Ser. No. 361,624
 Int. Cl. G11B 5/596
 U.S. Cl. 360—78.14



1. A disk drive system, comprising:
 - a data recording disk having radially spaced tracks, each track having a plurality of servo sectors; and
 - a cylinder address for identifying each track, said cylinder address divided into a plurality of cylinder address sub-sections where each sub-section comprises a partial cylinder address and wherein a predetermined number of said cylinder address sub-sections, less than the total number of said cylinder address sub-sections, are stored in each servo sector embedded on each track;
 - a head mounted in said disk drive system for reading said cylinder address sub-sections; and
 - a servo system in communication with said head to construct a cylinder address from said cylinder address sub-sections.

5,589,999
TAPE RECORDER AND OFFSET PLAYBACK APPARATUS WITH A VARIABLE TAPE LENGTH BETWEEN THE RECORDING AND READING HEAD
 Marc Hayat, 13 rue de Liège, Paris, France, and Max de Ferran, 4 Grande Rue, Bazainville, France
 PCT No. PCT/FR93/00666, § 371 Date Dec. 28, 1994, § 102(e) Date Dec. 28, 1994, PCT Pub. No. WO94/01863, PCT Pub. Date Jan. 20, 1994


PCT Filed Jul. 1, 1993, Ser. No. 367,182
 Claims priority, application France, Jul. 1, 1992, 92 08085
 Int. Cl. G11B 5/027

1. Apparatus for recording and playback, of a recording tape such as a video-tape recorder or tape recorder tape, with which playback can be selectively carried out in three modes which are an immediate playback mode, a simultaneous offset playback mode in which the apparatus simultaneously records on a first region of the tape and reads a second region of the tape, which is at a distance from the first region, and a playback alone mode, the apparatus comprising a recording head (9), means for having the

5,590,000
PIVOTING DEVICE FOR A SHUTTER ARRANGED IN THE AREA OF THE INSERTION OPENING OF THE LOADING MECHANISM OF A MAGNETIC-TAPE CASSETTE APPARATUS
 Christian Hopf, Hüttenberg-Rechtenbach, and Hans-Georg Hermann, Slinn-Fleischbach, both of Germany, assignors to U.S. Philips Corporation, New York, N.Y.
 Continuation of Ser. No. 293,984, Aug. 22, 1994, abandoned.
 This application Feb. 8, 1996, Ser. No. 598,417
 Claims priority, application Germany, Aug. 24, 1993, 43 28 443.4

Int. Cl. G11B 15/675
 U.S. Cl. 360—96.5


1. A pivoting device for a shutter pivotally arranged at a cassette insertion opening of a magnetic tape cassette apparatus, which cassette apparatus includes (i) a loading mechanism comprising a slide, translatable in an insertion and an ejection direction, between a slide takeover position and a slide play position, which loading mechanism (a) moves a tape cassette into and out of the apparatus through the cassette insertion opening and (b) moves the tape cassette between a takeover position and a play position corresponding to the takeover and play positions of the slide, respectively, and (ii) an electromotive drive for moving said slide, said drive being loaded to its greatest load while the loading mechanism moves the tape cassette from the play to the takeover position, wherein said pivoting device comprises:
 - a coupling lever;



shutter coupling means for disengagingly coupling said coupling lever to the shutter, said coupling lever being pivotable to move the shutter between an open and a closed position;
 an actuating rod engageable with said coupling lever, said slide being coupled to the actuating rod for moving the actuating rod in the insertion and ejection direction during respective movement of said slide in each of said insertion and ejection directions,
 said actuating rod being arranged relative to said coupling lever such that said actuating rod (i) is not coupled to said coupling lever during movement of said slide in the ejection direction from said slide play position to said slide takeover position by said electromotive drive, during which said electromotive drive is loaded to its greatest extent, and (ii) is coupled to said coupling lever when said slide is moved in the ejection direction from the slide takeover position.

5,590,001
BREATHING FILTER UNIT FOR MAGNETIC DISK DRIVE
 Tsuneyori Ino, Tsuyoshi Furukawa, Masaki Jinbo, Hisashi Kaneko, Shinichi Fukuzawa, Masaharu Sugimoto, Yoshiaki Nagasawa, Katsuaki Ishida, Osamu Yamazaki, Yukihiko Komura, all of Kawasaki, and Tomoo Sukagawa, Higashine, all of Japan, assignors to Fujitsu Limited, Japan
 Filed Nov. 29, 1994, Ser. No. 346,370
 Claims priority, application Japan, Mar. 15, 1994, 6-044192; Apr. 19, 1994, 6-080185


Int. Cl. G11B 33/14
 U.S. Cl. 360—97.02



1. A breather filter unit for a magnetic disk drive including a base and a cover fixed to said base, said cover having a vent, said breather filter unit comprising:
 - a casing fixed to an inner surface of said cover, said casing having a vent inlet communicating with said vent of said cover and a vent outlet communicating with an inside of said magnetic disk drive, said vent outlet being opposed to said vent inlet;
 - a first filter contained in said casing at a position adjacent to said vent inlet, said first filter comprising a plurality of fibers extending in a direction substantially parallel to that of an air flow from said vent inlet toward said vent outlet;
 - a second filter bonded to said casing so as to cover said vent outlet; and

an activated carbon layer contained in said casing at a position between said first filter and said second filter.

5,590,002
COMPLIANT ANCHOR FOR SECURING DISK DRIVE ACTUATOR BEARING
 Allen T. Bracken, Layton, and Edward L. Rich, Ogden, both of Utah, assignors to Iomega Corporation, Roy, Utah
 Filed Jan. 23, 1995, Ser. No. 377,033
 Int. Cl. G11B 33/14; 5/54
 U.S. Cl. 360—97.02




1. A magnetic disk drive in which recording media is engaged by read/write heads comprising:
 - a base;
 - an arm carrying said read/write heads into engagement with said media;
 - a body having a side from which said arm projects and another side;
 - a fork having tines which extend from said other side of said body;
 - an actuator bearing assembly around which said arm and said body pivots, said assembly being mounted to said base;
 - an actuator including a coil in said fork for rotating said arm;
 - shelves including a shelf extending across the bottom edge of said other side of said body between said tines of said fork for holding said coil;
 - a projection extending upwardly from said base and being unitary with said base; and
 - a compliant member connecting the top of said bearing assembly solely to said projection, said member being stiff in a direction of actuation forces applied to said bearing assembly when said actuator rotates said arm, the compliance of said member being in a direction transverse to said direction of said actuation forces.

5,590,003
HYDRODYNAMIC SPINDLE MOTOR HAVING DISTRIBUTED WINDINGS
 John C. Dunfield, Santa Cruz, and Gunter K. Heine, Aptos, both of Calif., assignors to Seagate Technology, Inc., Scotts Valley, Calif.
 Filed Mar. 8, 1995, Ser. No. 400,661

Int. Cl. G11B 17/02; H02K 3/00; F16C 32/06
 U.S. Cl. 360—98.07

15. A disc drive data storage system, comprising:
 - a housing;
 - a central axis;
 - a stationary member which is fixed with respect to the housing and coaxial with the central axis;
 - a hub;
 - a hydrodynamic bearing interconnecting the hub with the stationary member such that the hub is rotatable about the central axis;
 - at least one data storage disc attached to and coaxial with the hub;
 - at least one rotor magnet attached to the hub;
 - a stator which is coaxial with the hub, wherein the stator has a circumference and a plurality of slots positioned about the circumference; and



a three phase stator winding, with each phase comprising at least one phase winding formed of a plurality of turns, wherein the plurality of turns of each phase is distributed among adjacent slots and has a pitch of about 120 electrical degrees, and wherein at least one of the slots includes turns of more than one phase.

5,590,004

RESILIENT CLAMP AND COMPLIANT ELEMENT DATA DISK SUPPORT SYSTEM


Zine-Eddine Boutaghoul, Rochester, Minn., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 30, 1994, Ser. No. 366,960

Int. Cl.⁶ G11B 17/02; 17/08; 23/00; 25/00

U.S. Cl. 360-99.12

18 Claims



1. A disk assembly, comprising:
 - (a) a spindle disposed rotatably around a fixed axis, the spindle comprising a rim formed at a lower portion of the spindle, the rim having an upper surface defining a groove, the spindle further comprising an upper portion, the upper portion comprising a flange extending radially outward from the axis and spaced axially above the rim;
 - (b) at least one disk having a recording surface for recording data, the at least one disk having an upper side, the at least one disk further having a lower side facing the rim;
 - (c) a resilient clamping member having a lower end facing the upper side of the at least one disk, the resilient clamping member flexibly engaging the upper portion of the spindle for providing bias against the upper side of the at least one disk, the resilient clamping member further comprising an annulus, the annulus including a first portion at an inner radius of the annulus, the first portion extending radially inward and axially upward toward the flange; and
 - (d) a compliant element disposed in the groove and supported by the rim so that an upper portion of the compliant element is compressed toward the upper surface of the rim by the bias of the resilient clamping member;
 - (e) wherein, during a shock capable of separating the at least one disk a space away from the upper surface of the rim, the resilient clamping member and the compliant element cooperate to allow displacement of the at least one disk in response to the shock and to buffer the displaced at least one disk from

impact with the upper surface of the rim, wherein the resilient clamping member flexes to allow the displacement and the compliant element in response to the flexing of the resilient clamping member, expands to fill at least a portion of the space between the lower side of the at least one disk and the upper surface of the rim.

5,590,005

THIN FILM MAGNETIC HEAD

Hiroaki Tachibana, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Continuation of Ser. No. 162,894, Dec. 8, 1993, abandoned.


This application Jun. 7, 1995, Ser. No. 498,001

Claims priority, application Japan, Dec. 10, 1992, 4-352647

Int. Cl.⁶ G11B 5/31; 5/60

U.S. Cl. 360-103

5 Claims



1. A thin film magnetic head having terminals formed on a slider, comprising:
 - a pair of magnetic elements provided on said slider at spaced locations along a direction of width of said slider; and
 - a pair of first and second terminals connected to one of said magnetic elements by first and second leads, respectively, and a pair of third and fourth terminals connected to the other of said magnetic elements by third and fourth leads, respectively, said first and second terminals being spaced a predetermined distance from each other in a direction of thickness of said slider, which is normal to said direction of width of said slider, and deviated from each other in said direction of width of said slider so that a first end of said first terminal which is closest to said one of said magnetic elements is closer to said one of said magnetic elements in said direction of width of said slider than any end of said second terminal, and a second end of said first terminal opposite to said first end of said first terminal is further from said one of said magnetic elements in said direction of width of said slider than a first end of said second terminal, said first end of said second terminal is closest to said one of said magnetic elements, and is closer to said one of said magnetic elements in said direction of width of said slider than a second end of said second terminal, and said third and fourth terminals being spaced a second predetermined distance from each other in said direction of thickness of said slider and deviated from each other in said direction of width of said slider so that a first end of said third terminal which is closest to said other of said magnetic elements is closer to said other of said magnetic elements in said direction of width of said slider than any end of said fourth terminal, and a second end of said third terminal opposite to said first end of said third terminal is further from said other of said magnetic elements in said direction of width of said slider than a first end of said fourth terminal, said first end of said fourth terminal is closest to said other of said magnetic elements, and is closer to said other of said magnetic elements in said direction of width of said slider than a second end of said fourth terminal opposite to said first end of said fourth terminal

terminal, said first terminal having a corner thereof removed to form a first slant and said second terminal having a corner thereof removed to form a second slant, said first and second slants being substantially parallel to each other, and said third terminal having a corner thereof removed to form a third slant and said fourth terminal having a corner thereof removed to form a fourth slant, said third and fourth slants being substantially parallel to each other.

5,590,006

ONE-SIDED, SINGLE PLATTER HARD DISK WITH CENTER PARKING FEATURES


Mathew K. Shafé, Campbell, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 23, 1994, Ser. No. 363,463

Int. Cl.⁶ G11B 5/54; 21/22

U.S. Cl. 360-105

39 Claims



1. A disk drive assembly, comprising:
 - a disk including an upper data recording surface having a substantially coplanar region at its center with an axis of rotation of said disk passing through said coplanar region, and a lower surface;
 - means disposed below said disk for rotating said disk;
 - an actuator assembly including a suspension supporting a transducer, and means for selectively moving said transducer over said data recording surface and said substantially coplanar region; and
 - means for parking said transducer on said substantially coplanar region.

5,590,007

MAGNETIC HEAD DRIVING APPARATUS HAVING A MAGNETIC HEAD WHICH IS IMMUNE TO THE INFLUENCE OF A MAGNETIC CIRCUIT

Yoshifumi Yanagawa, Kyoto, and Tadashi Kunihiro, Osaka, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka-fu, Japan

Continuation of Ser. No. 62,610, May 18, 1993, abandoned.

This application Jan. 18, 1995, Ser. No. 375,514


Claims priority, application Japan, Jun. 29, 1992, 4-170410

Int. Cl.⁶ G11B 5/588

U.S. Cl. 360-109

7 Claims

1. A magnetic head driving apparatus which comprises:
 - a first yoke having a plurality of apertures therein and composed of a magnetic material;
 - a cylindrical first permanent magnet secured to said first yoke;
 - a second yoke composed of empty cylindrical magnetic material which is opposite to a side face of said first permanent magnet and which is mounted on said first yoke;



- a third yoke composed of a magnetic material mounted on said second yoke;
 - a second permanent magnet secured to said third yoke; a magnetic core composed of a magnetic material disposed between said first permanent magnet and said second permanent magnet; a first gimbal spring mounted on said first yoke or said second yoke; a second gimbal spring mounted on said second yoke or said third yoke; a coil bobbin mounted on said first gimbal spring and said second gimbal spring; a coil wound around said coil bobbin; a plurality of rigid projecting portions of said coil bobbin extending through said plurality of apertures of said first yoke;
 - a head base mounted on and supported by said extended rigid projecting portions of said coil bobbin so as to position a magnetic head mounted on said head base on an external side of said first yoke, each of said plurality of rigid projecting portions being integrally formed with the coil bobbin; and
 - a sensor object for showing the gap position provided on said head base;
- wherein said head base undergoes no deformation angle when said magnetic head is displaced.

5,590,008

MAGNETIC DISC UNIT HAVING A PLURALITY OF MAGNETIC HEADS WHICH INCLUDE MULTILAYER MAGNETIC FILMS

Masanori Tanabe, Odawara; Hiroshi Fukui, Hitachi; Tadayuki Iwakura, Hitachi; Kazuhiro Nakamoto, Hitachi; Moriaki Fuyama, Hitachi; Katsuya Mitsuoka, Hitachi; Masaaki Sano, Hitachi; Makoto Saito, Hiratsuka; Makoto Aihara, Katsuta, and Shuji Sudo, Hitachi, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of Ser. No. 873,219, Apr. 24, 1992, abandoned.


This application Oct. 17, 1994, Ser. No. 324,380

Claims priority, application Japan, Apr. 25, 1991, 3-095145

Int. Cl.⁶ G11B 5/147

U.S. Cl. 360-126

30 Claims



1. A magnetic disc unit comprising:
 - a magnetic recording medium;
 - a thin film magnetic head which confronts said magnetic recording medium, wherein said thin film magnetic head includes at least an upper magnetic core and a lower magnetic core;
 - a head slider for carrying said thin film magnetic head;
 - a spring member for supporting said head slider; a guide arm for connecting said spring member to a positioning mechanism;
 - a disc rotation control system for rotating a disc relative to said recording medium;

a head positioning control system for positioning said magnetic head;
 a recording/reproducing signal control system; and
 wherein at least an upper magnetic core of said thin film magnetic head includes at least two magnetic films, and
 a layer of magnetic material of said upper magnetic core in contact with a magnetic gap between said upper magnetic core and said lower magnetic core, said layer having a saturation magnetic flux density B_{HRI} and a thickness less than that of a layer of said upper magnetic core not in contact with said magnetic gap, one end of said layer extending to an end of said thin film magnetic head which confronts said recording medium, and
 wherein a saturation magnetic flux density B_1 of a magnetic material of said layer of said upper magnetic core not in contact with said magnetic gap, and a saturation magnetic flux density B_2 of a magnetic material of said lower magnetic core are expressed by the following respective relationships:

$$B_{HRI} > B_1, \text{ and } B_{HRI} > B_2$$

5,590,009

MAGNETIC DISK UNIT

Takehisa Ishida, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Continuation of Ser. No. 126,456, Sep. 24, 1993, abandoned.


This application May 19, 1995, Ser. No. 445,123

Claims priority, application Japan, Sep. 30, 1992, 4-285209

Int. Cl.⁶ G11B 5/82

U.S. Cl. 360—135

20 Claims




1. A magnetic disc unit, comprising:
 a magnetic recording medium having a servo region and a data region alternately allocated, the servo region having a servo pattern with a servo pattern width T_s , the data region having a recording track pattern with a track pitch T_p and a recording track width T_w , having a step between a recording area and a non-recording area thereon;
 a magnetic head with a magnetic writing width of W_w and a magnetic readout width of W_r ;
 wherein a relation between said recording track width T_w and said magnetic readout width W_r is $W_r > T_w$, while a relation between said recording track width T_w and said magnetic writing width W_w is $W_w > T_w$;
 wherein a relation between said servo pattern width T_s and said track pitch T_p is set to be $T_p(n-0.1) \leq T_s \leq T_p(n+0.1)$, where n is a positive, non-zero integer; and
 wherein a relation between said magnetic readout width W_r and said track pitch T_p is set to be $0.9 T_p \leq W_r \leq 1.1 T_p$, wherein a dead zone in a tracking error signal produced from said magnetic recording medium is substantially eliminated.

5,590,010
 HEAT RESPONSIVE POWER INTERRUPTING DEVICE
 Giacomo Ceola, Via Pastro 61/G, Villorba, Treviso, Italy;
 James K. McCusker, 12 Post La., Suffern, N.Y. 10901, and
 Giacomo Calzavara, 128 Surrey Ct., Ramsey, N.J. 07446
 Filed Jul. 12, 1994, Ser. No. 274,097
 Int. Cl.⁶ H02H 5/04

U.S. Cl. 361—93

17 Claims



1. A circuit coupled to an electrical socket for interrupting electrical power to an electric appliance, said circuit comprising:
 (a) an input port for receiving electrical power from an electrical socket;
 (b) an output port for delivering electrical power to an electric appliance, said output port accommodating plug blades of said electrical appliance;
 (c) a first resettable switching element coupled to said input and output ports and operative to interrupt electrical power to said electric appliance in response to when either of said electrical socket or said plug blades of said electric appliance attains a first predetermined temperature; and
 (d) a second resettable switching element coupled to said first resettable switching element and operative to interrupt electrical power to said electric appliance in response to when either of said electrical socket or said plug blades of said electric appliance attains a second predetermined temperature, wherein said second predetermined temperature is greater than said first predetermined temperature.

5,590,011

SHORT CIRCUIT PROTECTED SPLICE CONNECTOR

David A. Hein, Sterling Heights, Mich., assignor to Alcoa Fujikura Limited, Brentwood, Tenn.

Continuation of Ser. No. 150,967, Nov. 12, 1993. This application Jul. 27, 1995, Ser. No. 507,920

Int. Cl.⁶ H02H 5/04

U.S. Cl. 361—106

1 Claim

1. An electrical connector for connecting current receiving ends of a plurality of circuit wires together and to means having a positive temperature coefficient characteristic, comprising:
 at least two electrically conductive members each having integral legs for electrical connection respectively to the current receiving ends of a first group of branch circuit wires and to a feed wire supplying electrical current to one of said electrically conductive members;
 at least one member having a positive, temperature coefficient characteristic disposed between the two electrically conductive members and in electrical contact therewith including the integral legs of the electrically conductive members;
 a housing for receiving said positive temperature coefficient and electrically conductive members including the legs of the electrically conductive members;
 one of said electrically conductive members being effective to splice together the current receiving ends of the branch wires and electrically connect said wire ends to the member having a positive temperature coefficient characteristic such that the branch wires are connected to the feed wire through the member having the positive temperature coefficient characteristic when the feed wire is connected to a leg of the other electrically conductive member, and

from the primary frequency and representative of arcing within the electrical circuit.

5,590,013

ELECTRIC-SUPPLY-SWITCH RELAY-CIRCUIT

Shinichiro Harasawa, Kawasaki, Japan, assignor to Fujitsu Limited, Japan

Continuation of Ser. No. 99,188, Jul. 29, 1993, abandoned.


This application Feb. 22, 1996, Ser. No. 605,655

Claims priority, application Japan, Nov. 30, 1992, 4-319825

Int. Cl.⁶ H01H 47/22

U.S. Cl. 361—187

21 Claims



a third electrically conductive member having integral legs, and
 a second member having a positive temperature coefficient characteristic placed between the third electrically conductive member and one of the two electrically conductive members for splicing current receiving ends of a second group of branch circuit wires to the second positive temperature coefficient characteristic member.

5,590,012

ELECTRIC ARC DETECTOR SENSOR CIRCUIT


Charles R. Dollar, II, Norcross, Ga., assignor to Siemens Energy & Automation, Inc., Alpharetta, Ga.

Filed Mar. 30, 1995, Ser. No. 413,304

Int. Cl.⁶ H02H 3/46

U.S. Cl. 361—113

22 Claims



1. An arc detection system for detecting arcing within an alternating current electrical circuit, the electrical circuit conducting a desired alternating current at a primary frequency, the system, comprising:
 a first terminal;
 a second terminal;
 an inductor electrically coupled between the first and second terminals;
 a capacitor electrically coupled to the first terminal;
 a transformer including a primary winding magnetically coupled to a secondary winding, the primary winding being electrically coupled between the capacitor and the second terminal; and
 an arc monitoring circuit electrically coupled to the secondary winding, the capacitor limiting current at the primary frequency from flowing through the primary winding, and the monitoring circuit detecting currents at frequencies different

5,590,014

METHOD AND APPARATUS FOR SUPPLYING ELECTRIC POWER


Boyd B. Bushman, Lewisville, Tex., assignor to Lockheed Martin Corporation, Fort Worth, Tex.

Filed Mar. 16, 1995, Ser. No. 405,342

Int. Cl.⁶ H01G 7/02

U.S. Cl. 361—225

20 Claims



1. An apparatus for supplying electric power, the apparatus comprising in combination:
 a central member of an electret material;
 a pair of voltage input contacts electrically connected to and spaced apart on the central member;
 static voltage means connected to the voltage input contacts for applying a static voltage potential across the voltage input contacts to create a current flow in the central member; and
 a pair of voltage output contacts electrically connected to the central member, spaced apart from the voltage input contacts for receiving the current flow while the static voltage potential is being applied to the central member.

5,590,015

VARIABLE CAPACITOR HAVING SAFETY END SWITCHES DISPOSED ON AN ADJUSTABLE SCREW AT END FACE OF CAPACITOR HOUSING

Andrea V. Planta, Oetwil, and Rolf Gerber, Kehrsatz, both of Switzerland, assignors to Comet Technik AG, Liebefeld, Switzerland


Filed Nov. 21, 1995, Ser. No. 561,005

Claims priority, application Switzerland, Nov. 21, 1994, 3503/94

Int. Cl.⁶ H01G 5/00

U.S. Cl. 361—277

9 Claims



1. A variable capacitor, in particular a vacuum capacitor, in which stationary capacitor disks and capacitor disks which are linearly displaceable with respect to said stationary capacitor disks; and disposed on a motor-driven screw are accommodated in a housing, and safety end switches and a position indicator device are associated to the displaceable capacitor disks, wherein the position indicator and the safety end switches are disposed on an adjusting screw at one of the end faces of the capacitor housing in a portion of said housing itself or in an additional flange-mounted housing.

5,590,016

MULTILAYER THROUGH TYPE CAPACITOR ARRAY

Yoshikazu Fujishiro, Takaya Ishigaki, both of Akita-ken, and Hiraku Harada, Yamagata-ken, all of Japan, assignors to TDK Corporation, Tokyo, Japan


Filed Dec. 14, 1994, Ser. No. 356,834

Claims priority, application Japan, Dec. 16, 1993, 5-316577

Int. Cl.⁶ H01G 4/20; 4/34

U.S. Cl. 361—313

21 Claims



1. A multilayer through type capacitor array having a rectangular parallelepiped shape, comprising a first dielectric sheet, a second dielectric sheet, a third dielectric sheet and a fourth dielectric sheet, each designed in rectangular form and placed in this order, on said first dielectric sheet a single first internal electrode made of conductive material, extended in longitudinal direction of the rectangle and reaching only the two shorter sides of the rectangle being provided, on said second dielectric sheet a plurality of second internal electrodes made of conductive material, extended in lateral direction of the rectangle and reaching the longer sides of the rectangle being provided, and on said third dielectric sheet, a single third internal electrode made of conductive material, extended in longitudinal direction of the rectangle and reaching the two shorter sides of the rectangle being provided, and a plurality of through type capacitors where said second internal electrodes are used as central conductor and said first internal electrode and said third internal electrode are used as external conductor, whereby:

a plurality of first holes are extended along said second internal electrodes between said plurality of second internal electrodes on said second dielectric sheet;
a plurality of second holes are formed on said first dielectric sheet, at positions corresponding to the positions where said first holes are formed;
a plurality of third holes are formed on said third dielectric sheet, at positions corresponding to the positions where said first holes are formed;
first conductive materials are filled in each of said plurality of first holes;
second conductive materials are filled in each of said plurality of second holes;
third conductive materials are filled in each of said plurality of third holes;
said first internal electrode is electrically connected to said first conductive materials;
said third internal electrode is electrically connected to said third conductive materials; and
said first, second and third conductive materials, placed at corresponding positions respectively, are electrically connected to form a plurality of inner shielding electrodes.

5,590,017

ALUMINA MULTILAYER WIRING SUBSTRATE PROVIDED WITH HIGH DIELECTRIC MATERIAL LAYER


John F. Kelso, Apollo, Pa., assignor to Aluminum Company of America, Pittsburgh, Pa.

Filed Apr. 3, 1995, Ser. No. 415,874

Int. Cl.⁶ H01G 4/06; H05K 1/00

U.S. Cl. 361—321.4

13 Claims



1. A wiring substrate comprising:
a first alumina layer;
a first metallized layer on the first alumina layer;
a dielectric material layer on the first metallized layer;
a cermet layer on the dielectric material layer;
a second metallization layer on the cermet layer; and
a second alumina layer on the second metallized layer;
a first conductor electrically connecting to and extending from the second metallized layer through the second alumina layer; and
a second conductor electrically extending from the first metallized layer through the cermet layer and dielectric material layer, through but not electrically connecting the first metallized layer, and through the second alumina layer.

5,590,018

ARRANGEMENT OF ARRESTORS IN A GAS-INSULATED SWITCHGEAR

Satoshi Watahiki, and Shingo Shirakawa, both of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jul. 13, 1995, Ser. No. 501,878


Claims priority, application Japan, Jul. 25, 1994, 6-172271

Int. Cl.⁶ H02B 1/04

U.S. Cl. 361—612

6 Claims

1. A gas insulated switchgear, comprising:



a first set of isolated three-phase main buses disposed on a horizontal plane and running in a first direction;
a second set of isolated three-phase main buses disposed on said horizontal plane and running in parallel with said first set of isolated three-phase main buses;
a first set of gas insulated three-phase switchgear units disposed at a side of said first set of isolated three-phase main buses that is remote from said second set of isolated three-phase main buses;
three first connecting buses extending in a second direction perpendicular to the first direction, each of said first connecting buses connecting a respective one of said first set of isolated three-phase main buses and a respective one of said second set of isolated three-phase main buses with a respective one of said first set of gas insulated three-phase switchgear units of a corresponding phase via a respective disconnecting switch;
a second set of gas insulated three-phase switchgear units disposed at a side of said second set of isolated three-phase main buses that is remote from said first set of isolated three-phase main buses;
three second connecting buses extending in the second direction perpendicular to the first direction, each of said second connecting buses connecting a respective one of said first set of isolated three-phase main buses and a respective one of said second set of isolated three-phase main buses with one of said second set of gas insulated three-phase switchgear units of the corresponding phase via respective disconnecting switches;
a first set of first, second, and third isolated vertical type three-phase cylindrical arrestors disposed adjacent to said first set of gas insulated switchgear units and at the same side thereof with respect to said first set of isolated three-phase main buses, said first set of isolated vertical type three-phase cylindrical arrestors being arranged as three apices of a first triangle occupying said horizontal plane, wherein said second cylindrical arrestor of said first set of isolated vertical type three-phase cylindrical arrestors is located intermediate, along said first direction, of said first and third cylindrical arrestors of said first set of isolated vertical type three-phase cylindrical arrestors, a distance between said first and third cylindrical arrestors of said first set of isolated vertical type three-phase cylindrical arrestors in said first direction as a measurement axis being less than the diameter of said second cylindrical arrestor of said first set of isolated vertical type three-phase cylindrical arrestors;
three first leading-out buses extending in the second direction, each connecting one of said first set of isolated three-phase main buses with one of said first set of isolated vertical type three-phase cylindrical arrestors of a corresponding phase;
a second set of first, second, and third isolated vertical type three-phase cylindrical arrestors disposed adjacent to said second set of gas insulated switchgear units and at the same side thereof with respect to said second set of isolated three-phase main buses, said second set of isolated vertical type three-phase cylindrical arrestors being arranged as three apices of a second triangle occupying said horizontal plane, wherein said second cylindrical arrestor of said second set of

isolated vertical type three-phase cylindrical arrestors is located intermediate, along said first direction, of said first and third cylindrical arrestors of said second set of isolated vertical type three-phase cylindrical arrestors, a distance between said first and third cylindrical arrestors of said second set of isolated vertical type three-phase cylindrical arrestors in said first direction as a measurement axis being less than the diameter of said second cylindrical arrestor of said second set of isolated vertical type three-phase cylindrical arrestors; and
three second leading-out buses extending in the second direction, each connecting one of said second set of isolated three-phase main buses with one of said second set of isolated vertical type three-phase cylindrical arrestors of a corresponding phase.

5,590,019

DEVICE FOR CHANGE-OVER SWITCHING OF INDIVIDUAL ELECTRIC MOTORS OR GROUPS OF ELECTRIC MOTORS

Siegfried Fox, Xanten, and Andreas Keil, Krefeld, all of Germany, assignors to Palltex Project-Company GmbH, Krefeld, Germany


Filed Nov. 17, 1995, Ser. No. 560,319

Claims priority, application Germany, Nov. 19, 1994, 44 41 209.6

Int. Cl.⁶ H02B 1/04

U.S. Cl. 361—643

2 Claims



1. A device for change-over switching of electric motors, said device comprising:
a housing;
two safety disconnecting switch systems positioned adjacently to one another in said housing;
a cover slidably connected to said housing so as to cover one of said safety disconnecting switch systems respectively;
a fuse holder detachably connected to said housing;
fuses connected to said fuse holder;
each one of said safety disconnecting switch systems comprising receiving means for receiving said fuses;
said safety disconnecting switch systems electrically connected to one another such that upon insertion of said fuses into said receiving means of one of said safety disconnecting switch systems the electric motors rotate in one direction of rotation and that upon insertion of said fuses into said receiving means of the other one of said safety disconnecting switch systems the electric motors rotate in the other direction of rotation; and
wherein said fuse holder is detachably connected to said housing adjacent to said cover such that said cover covers one of said safety disconnecting switch systems and that said fuses are inserted into the receiving means of the other one of said safety disconnecting switch systems.
2. A device according to claim 1, wherein:
said housing is U-shaped and comprises a base and two legs;
said safety disconnecting switch systems are connected to said base;

said housing further comprising two rods connected to said legs so as to extend parallel to one another between said legs; and said cover displaceably guided on said rods.


5,590,020

COLLAPSIBLE NOTEBOOK COMPUTER KEYBOARD STRUCTURE WITH RESILIENTLY DEFLECTABLE KEY CAP SKIRTS

Charles A. Sellers, Houston, Tex., assignor to Compaq Computer Corporation, Houston, Tex.

Continuation-in-part of Ser. No. 268,818, Jun. 30, 1994, Pat. No. 5,532,904. This application Jul. 18, 1995, Ser. No. 503,869

Int. Cl.⁶ G06F 1/16; H01H 3/12; B41J 11/56; H05K 7/04
U.S. Cl. 361—680 23 Claims




1. A collapsible keyboard structure for a portable computer, comprising:

- a first support structure having top and bottom side portions;
- a series of key cap members each carried on said top side portion of said first support structure for vertical movement relative thereto, through a vertical key stroke distance, between extended and retracted positions separated by a vertical distance greater than said key stroke vertical distance, each of said key cap members having a relatively rigid top side portion with a horizontal periphery, and a resiliently deflectable skirt portion anchored and extending around said periphery and extending downwardly and horizontally outwardly therefrom;
- a second support structure carried beneath said first support structure and having a top side facing said bottom side of said first support structure; and
- a spaced series of resilient key return members anchored to said second support structure and having top end portions projecting upwardly beyond said top side of said second support structure,

said first and second support structures being horizontally shiftable relative to one another between a first position in which said key return members underlie and resiliently hold said key cap members in said extended positions thereof and permit said key cap members to be resiliently moved downwardly from said extended positions through said key stroke distance, and a second position in which said key return members are horizontally shifted relative to said key cap members in a manner permitting said key cap members to be forcibly moved downwardly from said extended positions thereof to said retracted positions thereof without vertically compressing said resilient key return members.


said resilient skirt portions of said key cap members bearing against and being deflected horizontally outwardly by said bottom side portion of said first support structure when said key cap members are in said retracted positions thereof.

5,590,021
SECONDARY DISPLAY SYSTEM FOR COMPUTER
David S. Register, 4202 Sandy Acre La., Austin, Tex. 78746
Filed Jul. 16, 1993, Ser. No. 92,846
Int. Cl.⁶ G06F 1/16; H05K 7/02
U.S. Cl. 361—681 9 Claims





1. A secondary display system for a computer, the system comprising:
 - a flat panel display;
 - a display controller electrically connected between said computer and said flat panel display for interfacing said flat panel display to said computer;
 - means connected to said flat panel display for positioning said flat panel display relative to said computer, said positioning means defining an axis on which said flat panel display is rotatable; and
 - means connected to said positioning means for mounting said system on said computer;
- wherein said computer comprises a computer chassis and a monitor disposed on a top surface thereof, said mounting means comprising a substantially planar plate interposed between said chassis and said monitor.

5,590,022
SHIELDED MODULAR PORTABLE COMPUTER WORK STATION HAVING CABLE ROUTING MEANS
Stephen Harvey, Las Cruces, N.M., assignor to The I.D.E.A. Corporation, Las Cruces, N.M.
Filed May 19, 1995, Ser. No. 444,704
Int. Cl.⁶ G06F 1/16; H05K 5/02
U.S. Cl. 361—683 20 Claims




16. A modular portable work station including a carrying case and a computer, a printer and at least one computer peripheral transported within the carrying case, said carrying case having a body and a cover movable to opened and closed positions relative to the body, said work station comprising:
 - a source of electric power;
 - electric cable means to connect said source of electric power to each of said computer and said at least one computer peripheral;
 - a computer tray located within said carrying case body to support the computer thereon;
 - a channel attached to said computer tray;

means by which to move said computer tray and said channel attached thereto relative to said carrying case body; at least one first and at least one second electrical connector mounted on said channel means; and means by which to electrically couple said electric cable means to said at least one first and second electrical connectors; said at least one first electrical connector adapted to be attached to said computer and said at least one second electrical connector adapted to be attached to said at least one computer peripheral.




5,590,023
COMPUTER APPARATUS FOR SUSPENSION OF COMPUTER EXPANSION CARDS
Gilberto Hernandez, 16707 Simsbrook Dr., Russell C. Smith, P.O. Box 1156, both of Pflugerville, Tex. 78691, and Daniel Bouvier, 7101 Figvine Cove, Austin, Tex. 78750
Filed Jul. 26, 1995, Ser. No. 507,619
Int. Cl.⁶ G06F 1/16; H05K 7/04; H01R 13/74
U.S. Cl. 361—683 16 Claims



- a case having a bottom surface, an upper surface opposing the bottom surface, and a peripheral surface continuous with the bottom surface and the upper surface, the peripheral surface having a card insertion port formed therein;
- a circuit board housed in said case to be parallel to the bottom surface and the upper surface, said circuit board having upper and lower surfaces; and
- first and second card storage portions which are respectively arranged on the upper and lower surfaces of said circuit board said first and second card storage portions being arranged so as to oppose each other across said circuit board and respectively having an opening portions continuous with said insertion port, said card-like electronic components being removably housed in said first and second card storage portions through said insertion port and said opening portions, and said card-like electronic components being parallel to said circuit board, when said card-like electronic components are housed in said first and second card storage portions.

5,590,025
FAN ATTACHMENT CLIP FOR HEAT SINK
Donald Clemens, The Colony, Tex., assignor to Thermalloy, Inc., Dallas, Tex.
Filed Jun. 7, 1995, Ser. No. 482,011
Int. Cl.⁶ H05K 7/20
U.S. Cl. 361—695 15 Claims



1. A clip for securing a heat sink having upstanding parallel fins to a fan for cooling said heat sink comprising:

1. Computer apparatus comprising:
 - an expansion card for suspension in a computer chassis relative to a planar, said planar having a connector for connecting to said card;
 - a hanger extending from said chassis; and
 - an interface plate secured to said card and having an opening therein such that said hanger extends through said opening when said card is connected to said connector and said hanger engages said interface plate through said opening to support said card away from said planar when said card is disconnected from said connector.

5,590,024
PORTABLE ELECTRONIC APPARATUS HAVING A PLURALITY OF CARD STORAGE PORTIONS FOR REMOVABLY HOUSING A MEMORY CARD
Masami Honda, and Kazuaki Kawabata, both of Tokyo, Japan, assignors to Kabushiki Kaisha Toshiba, Kanagawa-Ken, Japan
Filed May 6, 1994, Ser. No. 239,255
Claims priority, application Japan, Jun. 21, 1993, 5-149544
Int. Cl.⁶ G06F 1/16; H05K 7/16
U.S. Cl. 361—684 4 Claims

1. A portable electronic apparatus wherein a plurality of card-like electronic components are loaded/unloaded therethrough comprising:

a frame having a width adapted to be wedged between said fins of said heat sink;
 means adapted to secure said fan to said frame including upstanding corner posts on said frame adapted to engage said fan to secure it to said frame; and
 a blade extending downwardly from said frame adapted to bear against said fins to secure said frame to said heat sink, said blade having a downwardly facing arcuate cut-out which accommodates a wire clip adapted for securing said heat sink to a socket.

5,590,026

APPARATUS FOR DISSIPATING HEAT FROM AN INTEGRATED CIRCUIT


James D. Warren, Clayton; Carl R. Vogt, and Charles D. Klooz, both of Raleigh, all of N.C., assignors to Borg-Warner Automotive, Inc., Sterling Heights, Mich.

Filed Jul. 31, 1995, Ser. No. 509,597

Int. Cl.⁶ H05K 7/20

U.S. Cl. 361—704

12 Claims



1. An apparatus dissipating heat from an integrated circuit which is connected to a printed circuit board having first and second sides, the apparatus comprising:

- a support member having first and second sides, said first side of said support member being directly connected to the first side of the circuit board for supporting the integrated circuit with respect to the circuit board;
- a plurality of electrical connectors in electrical communication with the integrated circuit and surface-mounted on the first side of the circuit board;
- a metal tab in thermal communication with the integrated circuit and extending from said support member in a plane spaced from and substantially parallel to said circuit board and substantially coplanar with said second side of said support member;
- an electrically insulating thermally conductive compressible pad positioned in contact with said metal tab which receives heat from said tab; and
- a thermally conductive housing positioned adjacent said pad which compresses said pad against said tab and receives heat from said pad, said housing including a plurality of fins extending therefrom for heat dissipation, and wherein said housing is positioned opposing the first side of the circuit board.

5,590,027 TECHNIQUE PROVIDING BRIDGE FOR CONNECTING MODULAR UNITS


Ronald A. Provenzale, Fremont, Calif., assignor to Unisys Corporation, Blue Bell, Pa.
 Division of Ser. No. 223,270, Apr. 4, 1994, Pat. No. 5,421,739, which is a division of Ser. No. 4,031, Jan. 15, 1993, Pat. No. 5,304,077, which is a division of Ser. No. 746,456, Nov. 12, 1991, Pat. No. 5,267,873. This application May 31, 1995, Ser. No. 454,905

The portion of the term of this patent subsequent to Dec. 7, 2010, has been disclaimed.

Int. Cl.⁶ H01R 13/639; F16B 12/00

U.S. Cl. 361—732

11 Claims



1. In a computer array, a connection arrangement for removably connecting a prescribed base machine to a like associated satellite machines, each machine having at least one join-face with electrical plug-in connector means thereon, this arrangement comprising: coupling means comprising a thin, planar structure presenting a pair of opposed like couple-sides, each side having coupling means;

said base machine and said satellite machine, each having at least one join-face characterized by rib-guide means and attachment means thereon; each attachment means being disposed to correspond with a respective one of said coupling means when join-faces of said base and satellite machines are located in closely-opposed registering relation to one another, being coplanar, aligned and separated by a prescribed gap governed by said connector means, said coupling means being adapted to be removably engaged with both confronting join-faces via said respective coupling means engaging said attachment means, after being inserted therebetween, guided by said rib-guide means.

5,590,028 MEMORY CARD ASSEMBLY HAVING IMPROVED MEANS FOR GROUNDING PRINTED WIRING BOARD AND METHOD OF USE

Paul M. Duncan, Durham, N.C., assignor to Berg Technology, Inc., Reno, Nev.

Filed Sep. 30, 1994, Ser. No. 315,439


Int. Cl.⁶ H05K 1/14

U.S. Cl. 361—737

27 Claims

1. A printed wiring board and memory card assembly comprising:

- (a) a pair of opposed cover plates;
- (b) a printed wiring board interposed between said opposed cover plates;
- (c) an electrical power source comprising an electrical battery;
- (d) a positive terminal connecting the printed wiring board with the electrical power source;



(e) a negative terminal connecting the printed wiring board with the power source and with both of the opposed cover plates wherein the opposed cover plates comprise a first cover plate and a second cover plate and the battery has a negative electrode and a positive electrode and the negative terminal has a first section and a second section and is fixed to the printed wiring board at an attachment area interposed between said first and second sections and said first section of said negative terminal extends from said attachment area to contact the first cover plate and said second section of the negative terminal extends from said attachment area to contact the second cover plate and the negative electrode of said battery and the second section of the negative terminal contacts the positive electrode of said battery.

5,590,029

CIRCUIT BOARD SMT DEVICE MOUNTING APPARATUS


H. Scott Estes, Austin, Tex., assignor to Dell USA, L.P., Austin, Tex.

Filed Jan. 12, 1995, Ser. No. 371,720

Int. Cl.⁶ H05K 7/02

U.S. Cl. 361—760

19 Claims



1. Circuit board apparatus comprising:

- a dielectric substrate member having opposite first and second side surfaces;
- spaced apart first and second electrically conductive structures carried by said substrate member;
- a through hole extending through said substrate member and opening outwardly through said first and second side surfaces, said through hole having an interior side surface;
- spaced apart first and second electrically conductive plating segments disposed on said interior side surface of said through hole and respectively coupled to said first and second electrically conductive structures;
- an adapter structure extending along a longitudinal axis, said adapter structure having a first longitudinal portion coaxially

received in said through hole, a second longitudinal portion extending outwardly from said through hole, a depression formed in said second longitudinal portion, and first and second electrically isolated exterior portions respectively and conductively coupled to said first and second plating segments; and

an SMT type electronic component secured within said depression of said adapter structure and having opposite electrically conductive first and second end sections respectively and conductively coupled to said first and second plating segments of said through hole through said first and second electrically isolated exterior portions of said adapter structure.

5,590,030

CIRCUIT BOARD CAPABLE OF EFFICIENTLY CONDUCTING HEAT THROUGH AN INSIDE THEREOF USING THERMAL LANDS SURROUNDING THROUGH-HOLE CONNECTIONS

Masatsugu Kametani, and Kazuhiro Umekita, both of Ibaraki-ken, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of Ser. No. 29,919, Mar. 11, 1993, Pat. No.


5,371,653, which is a continuation of Ser. No. 462,778, Jan. 10, 1990, abandoned. This application Aug. 17, 1994, Ser. No. 291,893

Claims priority, application Japan, Jan. 13, 1989, 1-004923

Int. Cl.⁶ H05K 7/20; 1/11

U.S. Cl. 361—794

5 Claims



1. A circuit board apparatus comprising:


- a mother board including a ground or power supply layer having a ground or power supply potential-defining plane;
- at least one circuit board including at least one ground or power supply layer having a ground or power supply potential-defining plane, the circuit board being mounted on the mother board in such a manner that the at least one ground or power supply layer of the circuit board is contacted respectively to the corresponding ground or power supply layer of the mother board; and
- an electronic circuit unit mounted on the circuit board and having at least one terminal connected to the circuit board, the electronic circuit unit being adapted to generate heat upon operation thereof;
- wherein a thermal resistance of connection of the ground or power supply layer of the circuit board with the terminal of the electronic circuit unit is adjusted to be a low level to conduct therethrough an excess part, other than a part removed from surface of the electronic circuit unit, of heat generated from the electronic circuit unit, and
- wherein the ground or power supply layer in the circuit board is thick enough to conduct therethrough the excess part of heat to be diffused over an area wide enough to be removed, a part of the diffused heat over the ground or power supply layer of the circuit board being removed therefrom by fluid which flows along a surface of the circuit board, an other part of the diffused heat over the ground or power supply layer of the circuit board being further conducted from the ground or power supply layer of the circuit board to the ground or power supply layer of the mother board to be further diffused to be removed therefrom.

5,590,031
SYSTEM FOR CONVERTING ELECTROMAGNETIC RADIATION ENERGY TO ELECTRICAL ENERGY
 Franklin B. Mead, Jr., 44536 Avenida Del Sol, Lancaster, Calif. 93535, and Jack Nachamkin, 12314 Teri Dr., Poway, Calif. 92064

Filed Jul. 27, 1994, Ser. No. 281,271
 Int. Cl.⁶ H02M 1/00

U.S. Cl. 363-8

14 Claims



1. A system for converting incident electromagnetic radiation energy to electrical energy, comprising:

a first means for receiving incident primary electromagnetic radiation, said means for receiving producing emitted secondary electromagnetic radiation at a first frequency, said first means for receiving having a first volumetric size selected to resonate at a frequency within the frequency spectrum of the incident primary electromagnetic radiation in order to produce the secondary electromagnetic radiation at the first frequency at an enhanced energy density;

a second means for receiving the incident primary electromagnetic radiation, said means for receiving producing emitted secondary electromagnetic radiation at a second frequency, the secondary radiation at the first frequency and the secondary radiation at the second frequency interfering to produce secondary radiation at a lower frequency than that of the incident primary radiation, said second means for receiving having a second volumetric size selected to resonate at a frequency within the frequency spectrum of the incident primary electromagnetic radiation in order to produce the emitted secondary electromagnetic radiation at the second frequency at an enhanced energy density;

an antenna for receiving the emitted secondary electromagnetic radiation at the lower frequency, said antenna providing an electrical output responsive to the secondary electromagnetic radiation received;

a converter electrically connected to said antenna for receiving electrical current output from said antenna and converting the electrical current output to electrical current having a desired voltage and waveform.


5,590,032
SELF-SYNCHRONIZED DRIVE CIRCUIT FOR A SYNCHRONOUS RECTIFIER IN A CLAMPED-MODE POWER CONVERTER
 Wayne C. Bowman, Allen, and Van A. Niemela, Dallas, both of Tex., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed May 25, 1995, Ser. No. 452,560
 Int. Cl.⁶ H02J 1/00; H02M 3/00

U.S. Cl. 363-15

28 Claims

3. A DC to DC power converter, comprising:
 a power transformer having a primary winding and a secondary winding;



a primary circuit for connecting an input DC voltage to the primary winding and including, a power switch and a circuit that reverses the polarity of the secondary voltage during a portion of the period of non-conduction of the power switch sufficient to ensure the reset of the transformer magnetic core;
 a secondary circuit for coupling energy transfer from the secondary winding to an output and including, a low pass output filter connected to the output and a synchronous rectifier connecting the secondary winding to the low pass output filter;

the synchronous rectifier including:

first and second synchronous rectifier switches each controlled by a signal applied to an included control electrode, first and second voltage limit switch devices connected to limit a voltage of drive signals applied to the first and second synchronous rectifier switches and a drive winding connected to alternately energize the first and second synchronous rectifier switches.


5,590,033
POWER SOURCE APPARATUS
 Toshihiko Kawano, Hamamatsu, Japan, assignor to Yamaha Corporation, Hamamatsu, Japan

Continuation of Ser. No. 705,102, May 24, 1991, abandoned, which is a continuation-in-part of Ser. No. 397,575, Aug. 23, 1989, abandoned. This application Mar. 16, 1993, Ser. No. 32,728

Claims priority, application Japan, Sep. 2, 1988, 63-115037
 Int. Cl.⁶ H02M 3/335

U.S. Cl. 363-25

10 Claims



1. A power source apparatus for use in a digital audio recording apparatus, the digital audio recording apparatus including a variable speed drive being driven by an external sampling clock signal having a frequency used in digital audio equipment, wherein the speed of the drive varies in accordance with the external sampling clock signal, the power source apparatus comprising:

a DC power source;

a switching arrangement coupled to the DC power source for switching at a variable switching frequency to provide a DC output signal;

clock means for providing a clock signal substantially at the external sampling clock frequency; and
 a controller, responsive to the clock signal having the external sampling clock frequency, for controlling the switching frequency of the switching arrangement to be about an integer multiple of the external sampling clock frequency.


5,590,034
METHOD FOR CONTROLLING THE MOVEMENT OF AN INDUSTRIAL ROBOT AT AND NEAR SINGULARITIES
 John-Erik Snell, Västerås, Sweden, assignor to ASEA Brown Boveri AB, Västerås, Sweden

Filed Feb. 13, 1995, Ser. No. 387,231

Claims priority, application Sweden, Feb. 21, 1994, 9400579
 Int. Cl.⁶ G06F 19/00; G05B 19/18

U.S. Cl. 364-167.01

8 Claims



1. A method for controlling an industrial robot such that a tool supported by the robot can follow a path determined by a number of consecutive points, and wherein the robot while following the path ends up near or at a singularity, said robot having a plurality of movement axes (A1-A6) and the configuration of the robot being determined by the angles of rotation (θ_1 - θ_6) of the movement axes, the ratio of the angular velocities of the axes to the velocity of the tool being given by a Jacobian matrix, the angles of rotation which the robot is to assume in order to obtain the correct position and orientation for the tool at the next point on the path being calculated as follows:

- setting start values of the angles of rotation,
- calculating the errors in the position and orientation of the tool in relation to the desired position and orientation for the start values,
- calculating the total error,
- calculating new start values, based on the errors in the position and orientation of the tool,
- allowing steps b-d to constitute an iteration and repeating it until the total error is lower than a tolerance value for the total error,

characterized in that the iteration comprises the following steps:

- determining with the aid of the Jacobian matrix whether the robot is at or near a singularity,
- if the robot is at or near a singularity, carrying out the steps of:
 - identifying those axes which are singular and setting their joint angle values to their start values,
 - weighting the errors in the position of the tool in relation to the errors in the orientation of the tool by a weighting factor (V),

- increasing the tolerance value for the total error by a tolerance factor (k) such that it exceeds the tolerance for the total error for points outside the singularities,
- based on the weighted errors, calculating new start values for the next iteration.


5,590,035
OUTPUT CONTROL CIRCUIT
 Takehiko Shimomura, and Takashi Miyake, both of Itami, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 8, 1994, Ser. No. 354,168

Claims priority, application Japan, Dec. 24, 1993, 5-327766
 Int. Cl.⁶ G05B 11/01

U.S. Cl. 364-177

8 Claims



1. An output control circuit comprising:
 an output terminal connected with at least two kinds of different signal sources;
 first storing means for storing information specifying one of the signal sources from which a signal is outputted by said output terminal derives;
 a circuit for making a signal output from said output terminal according to the information stored in said first storing means;
 second storing means for storing the information to be stored in said first storing means;
 reload signal generating means for generating a reload signal; and
 reloading means for reloading the information stored in said second storing means to said first storing means, when the reload signal is generated by said reload signal generating means.

5,590,036
FAILURE-RECOVERING SEQUENTIAL PROCEDURE TEACHING SYSTEM AND METHOD THEREOF
 Noboru Maeda, Chiryu, Japan, assignor to Nippondenso Co., Ltd., Kariya, Japan

Filed Jun. 1, 1995, Ser. No. 457,281


Claims priority, application Japan, Jun. 1, 1994, 6-120404
 Int. Cl.⁶ G05B 9/02

U.S. Cl. 364-184

10 Claims

1. A failure-recovering sequential procedure teaching system comprises:

a failure removal data recording section which records as a set of failure removal data an associated-portion state data representing prescribed associated-portion states at the time when the equipment to be controlled is in failure and a recovery



sequence data representing a recovery sequential procedure with which an operator performs his recovering operation;

a failure removal data analysis section which selects one or a plurality of associated-portion state data items corresponding to the same recovery sequence data among a plurality of sets of failure removal data and groups them as data of the same recovery sequence data, analyzes said associated-portion state data in each recovery sequence group to produce failure-characterizing data typically representing the characteristics of the relevant failure state, and records the failure-characterizing data as the data paired with the corresponding recovery sequence data; and

a recovery sequence determination section which compares the corresponding associated-portion state data with each item of the failure-characterizing data as stored to determine the degree of match between an item of said corresponding associated-portion state data when a new piece of failure occurs and outputs the recovery sequence data corresponding to a high match-degree item of the failure-characterizing data.


5,590,037
DIGITAL COMPUTER SYSTEM AND METHODS FOR
COMPUTING A FINANCIAL PROJECTION AND AN
ILLUSTRATION OF A PREFUNDING PROGRAM FOR AN
EMPLOYEE BENEFIT

Raymond B. Ryan, Darien, Conn., and Noah F. Gans, New York, N.Y., assignors to The Evergreen Group Incorporated, Stamford, Conn.

Filed Sep. 17, 1993, Ser. No. 123,312
Int. Cl.⁶ G06F 157/00
U.S. Cl. 395-204

U.S. Cl. 395—204

42 Claims



1. A method implemented on a machine comprising an electrical digital computer having a processor programmed to electrically process input data into output data, the digital computer being

electrically connected to a keyboard and to a printer, the method comprising the steps of:

entering a first forecast of an employee benefit at the keyboard to convert the entered first forecast into a portion of the input data that is electrically conveyed to the digital electrical computer to electrically process;

entering a second forecast of a segregated and restricted investment subject to an indenture agreement at the keyboard to convert the entered second forecast into an other portion of the input data that is electrically conveyed to the digital computer to electrically process;

engaging the digital computer to process the input data add to generate the output data that is electrically conveyed to the printer, the output data representing an illustration of the segregated and restricted investment subject to an indenture agreement providing prefunding for the employee benefit; and printing said illustration at the printer from the electrically conveyed output data.

5,590,038

UNIVERSAL ELECTRONIC TRANSACTION CARD
INCLUDING RECEIPT STORAGE AND SYSTEM AND
METHODS OF CONDUCTING ELECTRONIC
TRANSACTIONS

Satyan G. Pitroda, 1480 Golden Bell Ct., Downers Grove, Ill.
60515

Filed Jun. 20, 1994, Ser. No. 262,307

Int. Cl.⁶ G06F 17/60

U.S. Cl. 395—241

24 Claims

CREDIT	BANK	SHOPS
MEDICAL	INSURANCE	I.D.
TRAVEL/TEL.	ADD/TEL.	MISC.

1 A universal electronic transaction card for storing, transmitting, and receiving information, including personal information for a user of the universal electronic transaction card, account information for accounts with service institutions in which the user has an account, and transactional information for accounts with service institutions in which the user has an account, for a plurality of service institutions comprising

- a. housing means for housing inputting means, memory means, communications means, display means, and processing means, the housing means adapted to fit in a pocket or purse;
- b. inputting means for inputting information, including personal information for the user, account information for a plurality of service institutions in which the user has an account, and transactional information for each service institution for which account information exists, into the memory means;
- c. memory means for storing information, including personal information for the user, account information for a plurality of service institutions in which the user has an account, and transactional information for each service institution for which account information exists;
- d. communications means for electronically communicating information, including personal information, account information, and transactional information, with service institutions;
- e. display means for displaying a replica of a card corresponding to a selected service institution and for displaying information for a plurality of service institution accounts, including personal information, account information, and transactional information;

DECEMBER 31, 1996

ELECTRICAL

3753

- f. processing means for processing information, including personal information, account information, and transactional information; and
- g. means for providing and storing electric power.

5,590,039

**NATURAL LANGUAGE PROCESSING APPARATUS AND
METHOD FOR PERFORMING PROCESSING TO
ANALYZE THE MEANING OF AN INPUT SENTENCE
ENTERED IN THE FORM OF A NATURAL LANGUAGE**

Yuji Ikeda, and Minoru Fujita, both of Yokohama, Japan,
assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 982,070, Nov. 25, 1992, abandoned,
which is a continuation of Ser. No. 594,954, Oct. 10, 1990,
abandoned. This application Aug. 29, 1994, Ser. No. 296,159

Claims priority, application Japan, Oct. 14, 1989, 1-267515

Int. Cl.⁶ G06F 17/28

U.S. Cl. 395—759

6 Claims




1. A natural language processing apparatus for performing processing to analyze the meaning of an input sentence entered in the form of a natural language, comprising:

memory means for storing subjects of analysis;
input means for applying the input sentence, which is an initial one of the subjects of analysis, to said memory means;
a plurality of meaning analyzing means for analyzing the meaning of the input sentence, each of said plurality of meaning analyzing means performing different meaning analyzing operations, and being capable of outputting a result of its analysis to said memory means to update a subject of a subsequent analysis; and
control means for sending a subject of analysis stored in said memory means to each of said plurality of meaning analyzing means when the subject of analysis is updated in said memory means.

wherein each of said plurality of meaning analyzing means determines whether respective meaning analysis is executable with regard to the subject of analysis sent by said control means and sends a result of the determination to said control means, and

wherein if at least one of the plurality of meaning analyzing means sends a determination that an analysis of the subject of analysis is executable, said control means selects one from among said at least one of the plurality of meaning analyzing means on the basis of the results of the determination sent by said plurality of meaning analyzing means and causes the selected one of said plurality of meaning analyzing means to perform a meaning analysis on the subject of analysis is sent by said control means and output a result of its meaning analysis to said memory means to update the subjects of analysis.

5,590,040
SELF-DIAGNOSIS APPARATUS FOR VEHICLE
Takahide Abe, Kariya, and Katsumi Takaba, Obu, both of
Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan
Filed Aug. 17, 1993, Ser. No. 107,154
Claims priority, application Japan, Aug. 19, 1992, 4-242804
Int. Cl.⁶ G06F 17/00; G01M 15/00
U.S. Cl. 364—424.04 **12 Claims**



1. A self-diagnosis apparatus for a vehicle for detecting and storing data of vehicle conditions, detecting a possible abnormality of equipment mounted on the vehicle, and for outputting stored data for diagnosis of the possible abnormality, said apparatus comprising:

plurality of sensors each for detecting and outputting, during operation of equipment mounted on the vehicle, a value of a respective ones of predetermined parameters representative of vehicle operating conditions;

means for dividing a predetermined region of output values of each of said sensors into a plurality of subregions;

means for determining into which of said subregions values of each of the parameters output by the sensors fall;

memory means for storing data and for updating the stored data, said memory means including a plurality of storage regions corresponding in number to said subregions, each of said storage regions storing therein a period of time during which values of the parameters are in the subregion corresponding to the storage region, as determined by said determining means;

abnormality detecting means for detecting an abnormality of equipment; and

fixing means for causing said memory means to fixedly store data of said memory means when an abnormality is detected by said abnormality detecting means.

5,590,041
TRACK TRENCHER STEERING SYSTEM AND PROCESS
Mark R. Cooper, Pella, Iowa, assignor to Vermeer Manufacturing Company, Pella, Iowa

Filed Jul. 29, 1994, Ser. No. 282,878

Int. Cl.

22 Claims

1. A system for steering a track trencher including an engine coupled to left and right track drives, the system comprising:
left and right track pumps for powering the left and right track drives respectively;
means for producing a travel mode signal indicative of one of a plurality of track trencher travel modes;

a central control unit,

a multiplicity of similar first control modules spaced along the row, each of said first control modules being connected to a plurality of said sensor elements and including means for evaluating said sensor signals and means for communicating data between said first modules and between one of said first modules and said central unit, and a multiplicity of similar second control modules spaced along the row, each of said second control modules being connected to a plurality of said effector elements and including means for generating said effector signals and means for communicating data between said second modules and between one of said second modules and said central unit, and means for connecting said first modules of the row serially in at least one chain and for connecting said second module serially in at least one other chain, and means for connecting said chains independently to said central unit for data transfer from each chain to said central unit from one module through another module in succession along each chain and, conversely, for data transfer from said central unit to each chain being effected from one module through another module in succession along the respective chain, whereby interruption of each chain automatically reconfigures flow of data from the interrupted chain to said central unit and from said central unit through the respective chain.

5,590,046


AUTOMATED FLOOR PANEL WORKCELL

Thomas Q. Anderson, Seattle; Garth W. Broadrick, Spokane; Merrill A. Christianson, Puyallup; Daniel A. Hippe; Arthur T. Hughes, both of Auburn; Jagdish C. Kalyan, Bothell; Daniel L. Nydegger, Auburn; Robert C. Platt, Seattle, and Karapurath Ramachandran, Maple Valley, all of Wash., assignors to The Boeing Company, Seattle, Wash.

Continuation-in-part of Ser. No. 609,180, Oct. 31, 1990, Pat. No. 5,247,477. This application Apr. 1, 1993, Ser. No. 42,347 Int. Cl.⁶ G05B 19/18

U.S. Cl. 364-474.13

20 Claims



1. A method of making parts from rigid, self-supporting sheet material, comprising:
creating a virtual nest of parts on a space equal to a standard sheet of said rigid sheet material;
loading a working sheet of said rigid sheet material having said standard size, on edge, into a CNC machine;
in said CNC machine, cutting at least one reference cut into said working sheet for future indexing;
moving said working sheet, on edge, to a second CNC machine and indexing said working sheet, on edge, to a known position on said second CNC machine using said reference cut;
positioning a tool of a second CNC machine precisely at a predetermined position on said working sheet using said reference cut as a reference, and performing additional operations on said working sheet in said second CNC machine; and
cutting the periphery of each nested part on said working sheet to separate said parts from said working sheet.

5,590,047

INFORMATION PROCESSING APPARATUS

Nagatoshi Uehara, Tokyo, Japan, assignor to Clarion Co., Ltd., Saitama-ken, Japan


Filed Aug. 2, 1994, Ser. No. 284,358

Claims priority, application Japan, Aug. 5, 1993, 5-212160; Aug. 5, 1993, 5-212161

Int. Cl.⁶ G06F 17/00; G11B 15/68; 17/22

U.S. Cl. 364-478.02

21 Claims



1. An information processing apparatus for performing a predetermined processing to the information recorded in a recording medium inserted into said apparatus, said apparatus including a plurality of storing positions capable of storing the recording medium and a holding member (3) movable between a processing position at which said predetermined processing is performed and positions opposed to each of said storing positions for holding the recording medium, said information processing apparatus comprising:

first designating means for initially designating one of said plurality of storing positions to which the recording medium is to be stored;

second designating means for independently designating one of said plurality of storage positions at which the inserted recording medium is to be located; and

determining means for determining the position designated by said second designating means as a position at which the recording medium is to be located when such a position is available and said second designating means has designated a position other than the initial position of the first designating means.

5,590,048

BLOCK EXPOSURE PATTERN DATA EXTRACTING SYSTEM AND METHOD FOR CHARGED PARTICLE BEAM EXPOSURE

Tomohiko Abe; Hiroshi Yasuda; Kichiro Sakamoto, and Yoshihisa Oae, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Filed Jun. 4, 1993, Ser. No. 71,262

Claims priority, application Japan, Jun. 5, 1992, 4-145833; Jun. 8, 1992, 4-147655; Sep. 21, 1992, 4-251224

Int. Cl.⁶ G06F 17/50; G06K 9/00

U.S. Cl. 364-489

42 Claims



1. A pattern extracting apparatus which is applied to a charge-particle beam exposure system for extracting an input exposure pattern corresponding to a unit block exposure pattern, the input exposure pattern including a plurality of apexes, a selected apex of the input exposure pattern having first vectors connecting the selected apex to other apexes of the input exposure pattern, the unit block exposure pattern including a plurality of apexes, one of the plurality of apexes of the unit block exposure pattern being a reference point having second vectors connecting the reference point to other apexes of the unit block exposure pattern, said pattern extracting apparatus comprising:

comparator means for comparing the first vectors of the selected apex of the input exposure pattern with the second vectors of the reference point of the unit block exposure pattern;

determining means, coupled to said comparator means, for determining whether or not the first vectors coincide with the second vectors; and

extracting means, coupled to the determining means, for extracting the input exposure pattern as the unit block exposure pattern when the determining means determines that the first vectors coincide with the second vectors.

5,590,049

METHOD AND SYSTEM FOR USER PROGRAMMABLE DESIGN VERIFICATION FOR PRINTED CIRCUIT BOARDS AND MULTICHIP MODULES


Sandeep Arora, Boston, Mass., assignor to Cadence Design Systems, Inc., San Jose, Calif.

Filed Sep. 7, 1994, Ser. No. 302,329

Int. Cl.⁶ G06F 17/50

U.S. Cl. 364-489

9 Claims



1. In an computer aided design system for the design of an electronic circuit, a method of verifying design constraints in the electronic circuit, the electronic circuit including a selected plurality of interconnected components, the method comprising the steps of:

defining a design constraint for a component of the electronic circuit;

providing a verification engine for executing a verification procedure verifying the design constraint of the component;

providing a programming interface for defining the verification procedure verifying the design constraint;

defining the verification procedure in the programming interface, the verification procedure remaining independent of the verification engine until execution of the verification procedure; and

executing the verification procedure with the verification engine to verify the design constraint.

5,590,050

DEVICE FOR AID IN INTEGRATED CIRCUIT DESIGN THAT REDUCES THE NUMBER OF CELLS IN A CIRCUIT REPRESENTATION


Ryosuke Okuda, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Feb. 15, 1994, Ser. No. 196,365

Claims priority, application Japan, Feb. 24, 1993, 5-058086 Int. Cl.⁶ H01L 21/70

U.S. Cl. 364-490

26 Claims



1. A device for automatically designing a semiconductor integrated circuit, said device including a placement and routing unit for determining the arrangement of cells and lines on an integrated circuit chip on the basis of data of cells stored in a cell library storage and data of a circuit stored in a circuit storage, said device comprising:

a circuit converter for generating data of an equivalent circuit having cells smaller in total number than those of said circuit by the use of a new cell which is not stored in said cell library storage on the basis of said circuit formed by connecting only the cells stored in said cell library storage to apply said data of said equivalent circuit to said placement and routing unit, said circuit converter producing a specification of said new cell; and

a cell generator for producing data required to register said new cell in said cell library storage on the basis of said new cell specification.

5,590,051

PROCESS SIMULATION METHOD, PROCESS SIMULATOR AND CHEMICAL VAPOR DEPOSITION SYSTEM EMPLOYING THE SAME

Ayumi Yokozawa, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Nov. 29, 1994, Ser. No. 350,982


Claims priority, application Japan, Dec. 1, 1993, 5-301383 Int. Cl.⁶ G06F 17/00

U.S. Cl. 364-496

7 Claims

1. A process simulation method wherein a plurality of parameters required to determine optimum process conditions which provide the best step coverage of a dielectric film for a capacitor to be formed on a semiconductor substrate by a chemical vapor deposition method by supplying a plurality of raw material gases to the semiconductor substrate are inputted as values defining given variation ranges and the thus inputted parameters are individually varied to select optimum process conditions, comprising the steps of:

setting a plurality of process condition sets of different combinations from the plurality of inputted parameters;



associating means that stores in said memory means an association between the product names stored in said memory means and each of said module names stored in said memory means; monitoring means that monitors invocations of said modules on said computer and stores in said memory means invocation data relating to said invocations of said modules; correlating means that correlates said invocation data stored in said memory means and said association between the product names and each of said module names stored in said memory means; and reporting means that outputs the data correlated by said correlating means.


5,590,057 TRAINING AND CERTIFICATION SYSTEM AND METHOD

Robert L. Fletcher, Dallas, and Gregory V. Ruuska, Garland, both of Tex., assignors to Atlantic Richfield Company, Los Angeles, Calif.

Filed Dec. 20, 1993, Ser. No. 169,264
Int. Cl.⁶ G06F 15/20; 15/42; G07B 7/00

U.S. Cl. 364—551.01

4 Claims



1. A computer-implemented system for training and certifying a trainee to perform a task, the system comprising:
a data storage for storing preset limit data to determine certifiability of the trainee and for storing log data of the trainee;
a controller for receiving input data of the trainee from an input device, sending control data to an output device and sending said log data of the trainee to said data storage;
a supervisor for interpreting said input data, determining said control data to be sent by said controller to said output device and determining said input data to be stored as said log data in said data storage, said supervisor further monitoring trainee's interaction with simulations of a portion of said task to determine control data sent to said output device to review instructions and information pertaining to said portion of said task if it is determined that said trainee's interaction with simulations of said portion of said task is not acceptable or to provide a test pertaining to said portion of said task if it is determined that said trainee's interaction with simulations of said portion of said task is acceptable, such that said interaction with said simulations and said review or test pertaining to said portion of said task is thereafter repeated for other portions of said task, and is followed by a post testing of the trainee's overall knowledge of said task for comprising said log data; and
a comparator that is accessible to said data storage to compare said log data with said preset limit data to determine certifiability of the trainee.

5,590,058 BATTERY MONITOR FOR UNOBSTRUSIVE INSTALLATION WITH A BATTERY CONNECTOR

Kevin G. Foreman, Sandia Park; Paul J. Miller, and Steven M. Siska, both of Albuquerque, all of N.M., assignors to TRW Inc., Redondo Beach, Calif.


Continuation of Ser. No. 998,354, Dec. 30, 1992, abandoned, which is a continuation-in-part of Ser. No. 938,111, Aug. 31, 1992, Pat. No. 5,290,191, which is a continuation-in-part of Ser. No. 895,148, Jun. 5, 1992, Pat. No. 5,181,859, which is a continuation of Ser. No. 694,262, Apr. 29, 1991, abandoned.

This application Feb. 24, 1995, Ser. No. 394,924

Int. Cl.⁶ G01R 15/00; 19/155

U.S. Cl. 364—551.01

21 Claims



1. A wafer-like device for sensing characteristics of a battery having a positive post and a negative post extending from a surface thereof, said device comprising:
a generally flat substrate having first and second openings therein for receiving the positive and negative posts of the battery;
sensor means carried by the substrate for detecting characteristics of the battery;
port means carried by the substrate for providing a connection to external equipment for transmitting information detected by the sensor means;
conductive means for making electrical connection between the posts and at least the sensor means; and
said device being constructed so that it is insertable over the posts of the battery such that it lies essentially parallel to the battery surface with the posts extending through the openings in the substrate and making contact with the conductive means.


5,590,059 POSITION ENCODER SYSTEM WHICH UTILITES THE FUNDAMENTAL FREQUENCY OF A RULED SCALE ON AN OBJECT

J. Alan Schier, 7105 Owens St., Tujunga, Calif. 91042-1425
Filed Mar. 14, 1995, Ser. No. 403,409

Int. Cl.⁶ G05B 19/18

U.S. Cl. 364—559

33 Claims



1. A method for determining position of an object comprising the

obtaining a continuous representation of a continuous section of the object, the section having indicia thereon;
determining, from the continuous representation, frequency of changes on the indicia; and
determining phase between the determined frequency and a reference to obtain actual position of the object.


5,590,060 APPARATUS AND METHOD FOR AN OBJECT MEASUREMENT SYSTEM

Gregg Grauville, New Boston, and J. Peter Glasson, Durham, both of N.H., assignors to Metronics, Inc., Bedford, N.H.
Continuation of Ser. No. 258,123, Jun. 10, 1994, abandoned, which is a continuation of Ser. No. 854,247, Mar. 20, 1992, abandoned. This application Nov. 15, 1995, Ser. No. 558,767

Int. Cl.⁶ G06K 9/00

U.S. Cl. 364—560

30 Claims



1. An object inspection system comprising:
an inspection station for holding an object to be measured;
a display monitor for viewing the object to be measured;
means for inputting at least one point location datum indicative of a point on the object;
processing means, responsive to the inputted point location data, for automatically determining if the inputted point location data represent a particular geometric feature type including a single point, two single points, a line, a circle, an arc, and an angle; and
means for displaying an indication of the geometric feature type determined to be represented by said inputted data.

5,590,061 METHOD AND APPARATUS FOR THERMAL MANAGEMENT IN A COMPUTER SYSTEM


J. Rhoads Hollowell, II, Sunnyvale; James R. Benninghaus, Cupertino, both of Calif., and Daniel J. Hansen, Jr., Georgetown, Tex., assignors to Apple Computer, Inc., Cupertino, Calif.

Filed May 12, 1994, Ser. No. 241,962
Int. Cl.⁶ G06F 15/00

U.S. Cl. 364—571.03

26 Claims

1. A method for regulating the internal temperature of a computer system, said method comprising the steps of:
monitoring the internal temperature of the computer system;
placing at least one integrated circuit within the computer system into a first powered state for a first period of time and then a second powered state for a second period of time repeatedly when the internal temperature is at least at a threshold temperature, wherein the step of placing comprises the step of selecting durations of the first period of time and



the second period of time based on an amount the internal temperature exceeds the threshold temperature.

5,590,062 SIMULATOR FOR PRODUCING VARIOUS LIVING ENVIRONMENTS MAINLY FOR VISUAL PERCEPTION


Sachio Nagamitsu, Kyoto; Hisashi Kodama, Ikoma; Mayumi Sakai, Katano; Yoshihiro Hattori, Osaka, and Tunekio Okada, Moriguchi, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Jun. 21, 1994, Ser. No. 263,187
Claims priority, application Japan, Jul. 2, 1993, 5-164863; Jul. 8, 1993, 5-169325; Sep. 13, 1993, 5-226992; Jun. 21, 1994, 6-138502


Int. Cl.⁶ G06F 17/00

U.S. Cl. 364—578

58 Claims



1. A simulator system for providing a virtual environment for a user, comprising:
viewing means to provide images of a virtual environmental for the user's eyes;
input means for inputting data to create images for the user's eyes through the viewing means including physical conditions of the virtual environment at predetermined locations in the virtual environment; and
control means to enable the user to interact with the virtual environment images including:
means for creating a variable symbol in the virtual environment, controlling movement of the symbol through the virtual environment and cause the symbol to visually change in appear-



the following spaced-apart, parallel strips of polysilicon and underlying gate oxide formed on the silicon substrate, all of which run perpendicular to the N+ buried bit lines;

- (i) one segment select line strip formed at the top and one segment select line strip formed at the bottom of each segment to provide gate electrodes of segment select switching transistors;
- (ii) one outer select line strip formed at the top and one outer select line strip formed at the bottom of each segment to provide gate electrodes of outer select transistors;
- (iii) one inner select line strip formed at the top and one inner select line strip formed at the bottom of each segment to provide gate electrodes of inner select transistors; and
- (iv) one word line strip for each row of ROM data storage cells in a segment to provide gate electrodes for the ROM data storage cells

such that the outer select line strips, the inner select line strips and the word line strips overlie the N+ buried bit lines and are separated therefrom by gate oxide and such that the segment select line strips overlie p-type silicon substrate and are separated therefrom by gate oxide;

N-type dopant introduced into the silicon substrate to define N+ source and N+ drain regions of the segment select transistors and to connect the segment select transistors to corresponding N+ buried bit lines; and

a plurality of conductive contact lines formed such that each alternating N+ buried bit line is contacted by a corresponding conductive contact line at first and second contact locations in each segment to thereby define contacted drain bit lines of the array, each non-contacted N+ buried bit line being segmented into a length sufficient to form a segmented source bit line for a preselected plurality of ROM data storage cells, thereby defining a column of ROM data storage cells in the array segment;

such that, for each contacted drain bit line, one of a pair of segment select switching transistors is connected between the contacted drain bit line and one of the two contact locations of that contacted drain bit line, and

such that, for each segmented source bit line, one of a pair of inner select switching transistors is connected between one of the ends of the segmented source bit line and a first adjacent contacted drain bit line associated with the segmented source bit line, and

such that, for each segmented source bit line, one of a pair of outer select switching transistors is connected between one of the ends of the segmented source bit line and a second adjacent contacted drain bit line associated with the segmented source bit line.

5,590,069 METHOD AND APPARATUS FOR PROVIDING ROM IN AN INTEGRATED CIRCUIT HAVING UPDATE THROUGH SINGLE SUBSTANCE LAYER MODIFICATION CAPABILITY


Jeffrey A. Levin, San Diego, Calif., assignor to Qualcomm Incorporated, San Diego, Calif.

Filed Oct. 17, 1994, Ser. No. 324,433

Int. Cl.⁶ G11C 17/00

U.S. Cl. 365—96

23 Claims



23. A circuit placed within an integrated circuit for storing data within the integrated circuit comprising:

- a plurality of circuits that can be permanently placed in a first state or second state via modification of a single substance layer that is difference for each circuit;
- means for generating first signal in said first logic state when a first circuit in said plurality of circuits is in said first state and in second logic state when said first circuit is in second state;
- means for generating an alternative first signal in said second logic state when said first signal from said plurality of circuits is in said first state, and in said first logic state when said first circuit is in said second state; and
- means for generating a second signal that is logically equivalent to said first signal when a second circuit from said plurality of circuits is in said first state, and which is logically equivalent to said alternative first signal when said second circuit is in said second state.

5,590,070 DYNAMIC MEMORY


Michel Harrand, Saint Egreve, and Michel Runtz, Grenoble, both of France, assignors to SGS-Thomson Microelectronics S.A., Saint Genis Pouilly, France

Division of Ser. No. 240,144, May 10, 1994. This application Jun. 6, 1995, Ser. No. 465,810

Claims priority, application France, May 24, 1993, 93 06533 Int. Cl.⁶ G11C 11/24

U.S. Cl. 365—149

20 Claims



1. A dynamic memory device, comprising:
memory means for storing a memory voltage having one of a first value and a second value, the memory means having a first capacitance;

reference means for storing a reference voltage, the reference means having a second capacitance substantially equal to the first capacitance of the memory means, the reference voltage being determined by the second capacitance;

comparing means for comparing the memory voltage with the reference voltage, the comparing means including first input means for receiving voltage, second input means for receiving voltage, and output means for outputting voltage, wherein the memory means and the reference means are coupled to the first input means and the second input means, respectively, and the output means outputs an output voltage according to the memory voltage and the reference voltage;

first connecting means interconnected between the memory means and the first input means;

second connecting means interconnected between the reference means and the second input means, wherein the first connecting means has a third capacitance, and the second connecting means has a fourth capacitance substantially equal to the third capacitance of the first connecting means, wherein the reference means is constructed and arranged to provide a first reference voltage, and wherein the second connecting means is constructed and arranged to provide a second reference voltage; and

means for enabling the second connecting means such that the first reference voltage is increased to a third reference voltage when the second connecting means is enabled.

5,590,071

METHOD AND APPARATUS FOR EMULATING A HIGH CAPACITY DRAM


Daniel J. Kolor, Wappingers Falls; Nitin B. Gupte, and Siddharth R. Shah, both of Hopewell Junction, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Nov. 16, 1995, Ser. No. 559,321

Int. Cl.⁶ G11C 11/24

U.S. Cl. 365—149

32 Claims



1. An apparatus for emulating a first DRAM component having a first storage capacity, said first DRAM component being accessed by receiving an address signal from a controller, together with DRAM control signals, said address signal including a first number of address bits, said apparatus comprising:

- an integrated circuit component including a plurality of second DRAMs, each of said plurality of second DRAMs having a second storage capacity, lower than the first storage capacity, wherein the cumulative total of said second storage capacities for said plurality of second DRAMs is at least equal to said first storage capacity, and wherein each of said plurality of second DRAMs may be accessed by receiving a second number of address bits from said address signal from said controller together with said DRAM control signals, said second number of address bits being less than said first number of address bits, each of said plurality of second

DRAMs including a plurality of inputs for receiving said second number of address bits from said address signal and for receiving said DRAM control signals; and

a decoder having at least one first input for receiving a number of decode bits from said address signal, said number of decode bits being equal to the difference between the first number of address bits and the second number of address bits, said decoder further having at least one second input for receiving at least one of said DRAM control signals, said decoder decoding said number of decode bits to direct the output of said at least one DRAM control signal, and selecting one of said plurality of second DRAMs by providing at least one directed DRAM control signal to at least one of said plurality of second DRAMs to permit access to one of said plurality of second DRAMs, each of said plurality of second DRAMs further having at least one input for receiving said at least one directed DRAM control signal.

5,590,072

NONVOLATILE SEMICONDUCTOR MEMORY DEVICE Jeong-Hyuk Choi, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Filed May 4, 1995, Ser. No. 434,803

Claims priority, application Rep. of Korea, May 7, 1994, 9986/1994

Int. Cl.⁶ G11C 13/00

U.S. Cl. 365—185.01

5 Claims



1. A connecting device within an electrically erasable and programmable read only memory device having a NAND cell string and first select means, said NAND cell string including a plurality of memory transistors, each of said memory transistors having a floating gate separated by a tunnel oxide layer from a channel region formed on a semiconductor substrate, and each of said memory transistors having a control gate separated by an interlayer insulation layer from said floating gate, respective channels of said memory transistors being serially connected to each other by source-drain regions, said control gate of each of said memory transistors being respectively connected to a corresponding word line, said first select means connected to one terminal of said NAND cell string, said device comprising:

- a resistor connected between said first select means and a bit line, said resistor having a preset resistance value; and
- an amplifying device connected between said first select means and said bit line which amplifies a reading current flowing through said NAND cell string and which supplies the amplified current to said bit line.


5,590,073

RANDOM ACCESS MEMORY HAVING FLASH MEMORY

Hideki Arakawa, and Takashi Narikiyo, both of Kanagawa, Japan, assignors to Sony Corporation, Japan
 Filed Nov. 21, 1994, Ser. No. 345,695
 Claims priority, application Japan, Nov. 30, 1993, 5-300678
 Int. Cl.⁶ G11C 11/34

U.S. Cl. 365—185.08

24 Claims



1. A semiconductor nonvolatile memory device comprising:
 - a first bit line;
 - a second bit line;
 - a buffer memory connected to said first and second bit lines;
 - an electrically erasable programmable nonvolatile memory connected to said first and second bit lines;
 - a writing latch circuit to which said first and second bit lines are connected in parallel and having a differential sensor type sense amplifier;
 - a switching circuit for switching said nonvolatile memory and said writing latch circuit to a nonconnected state when said buffer memory is in operation, and switching said buffer memory and said writing latch circuit to a nonconnected state when said nonvolatile memory is in a writing or erasure operation;
- wherein said nonvolatile memory comprises:
 - a first memory cell connected to a word line and said first bit line;
 - a second memory cell connected to a word line common with said first memory cell and connected to said second bit line, and
 - a means for holding the potential of either of said first and second bit lines at a first potential at a predetermined operation time and for setting the potential of the other bit line of said first and second bit lines to a second potential given a difference with the first potential for a predetermined time.

5,590,074


NONVOLATILE SEMICONDUCTOR MEMORY

Takao Akaogi, Masanobu Yoshida, both of Kawasaki; Yasushige Ogawa, Kasugai; Yasushi Kasa, and Shouichi Kawamura, both of Kawasaki, all of Japan, assignors to Fujitsu Limited, Kanagawa, Japan
 Division of Ser. No. 996,942, Dec. 28, 1992, Pat. No. 5,490,107. This application Jun. 6, 1995, Ser. No. 466,732
 Claims priority, application Japan, Dec. 27, 1991, 3-346663; May 28, 1992, 4-137080; Jul. 20, 1992, 4-191793; Sep. 17, 1992, 4-248023; Oct. 9, 1992, 4-271869; Oct. 13, 1992, 4-274355; Dec. 3, 1992, 4-324302; Dec. 4, 1992, 4-325544
 Int. Cl.⁶ G11C 11/34

U.S. Cl. 365—185.22

7 Claims

1. A nonvolatile writable and erasable semiconductor memory having a matrix (1) of nonvolatile writable and erasable memory



cell transistors (Mij) formed at intersections of word lines (WL1 to WLn) and bit lines (BL1 to BLn), a row decoder (3), a column decoder (5), and sense amplifiers (71 to 7n) connected to the bit lines (BL1 to BLn, . . . , BLn1 to BLn), respectively, the nonvolatile writable and erasable semiconductor memory comprising:

- write means connected to said matrix;
- verify means having at least one function selected from a) a write verify function which determines whether or not data are written in a memory as to accurately read out said data even when variation in a power source voltage occurs during a reading operation, and b) an erase verify function which determines whether or not data are erased in said memory as to accurately read out said data even when variation in the power source voltage occurs in the reading operation;
- the verify means including means for detecting an output voltage of the sense amplifiers, comparison means for comparing the output voltage with a reference voltage, and storage means for storing a result of the comparison; and
- means for repeating a write operation and/or erase operation to memory cell transistors, if a result of comparison provided by the storage means after a verify operation for the write operation and/or erase operation indicates that the write operation and/or erase operation is not successful.

5,590,075


METHOD FOR TESTING AN ELECTRICALLY ERASABLE AND PROGRAMMABLE MEMORY DEVICE

Stefano Mazzali, Carnate, Italy, assignor to SGS-Thomson Microelectronics S.r.l., Agrate Brianza, Italy
 Filed Jun. 7, 1995, Ser. No. 479,081

Claims priority, application European Pat. Off., Jun. 7, 1994, 94830276
 Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—185.22

12 Claims



5,590,077


SEMICONDUCTOR MEMORY DEVICE

Dong M. Lee, Kyungki-Do, Rep. of Korea, assignor to Hyundai Electronics Industries Co., Ltd., Kyungki-Do, Rep. of Korea
 Filed Feb. 3, 1995, Ser. No. 383,003

Claims priority, application Rep. of Korea, Feb. 7, 1994, 94-2245
 Int. Cl.⁶ G11C 13/00

U.S. Cl. 365—189.05

3 Claims



1. A semiconductor memory device comprising:
 - a row address buffer;
 - a row predecoder connected to said row address buffer;
 - a plurality of row decoder groups and a plurality of memory blocks connected to said row decoder groups, respectively;
 - and
 - a plurality of repeaters connected between said row predecoder and said row decoder groups in a way such that any one of said row decoder groups is selected by an output signal of said row predecoder and each block select address signal which is inputted to said repeaters, respectively.

5,590,076

CHANNEL HOT-CARRIER PAGE WRITE


Sameer S. Haddad, San Jose; Chi Chang, Redwood City, and David K. Y. Liu, Cupertino, all of Calif., assignors to Advanced Micro Devices, Inc., Sunnyvale, Calif.

Filed Jun. 21, 1995, Ser. No. 493,138

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—185.25

31 Claims



1. A low-energy write mode flash EEPROM, comprising:
 - an array of floating gate flash EEPROM memory cells formed on a substrate in rows and columns, each cell having a source, a drain, a channel between the source and the drain, a floating gate extending between the source and the drain above the channel, and a control gate extending between the source and the drain above the floating gate, the control gates of respective rows being connected to respective word select lines, the memory cell sources for at least one row of memory cells being coupled to a common source line, and the memory cell drains of respective columns being connected to respective bit select lines;
 - the memory cells having a high core doping to optimize cell programming by hot carrier injection into the floating gates of selected memory cells;
 - a circuit for limiting a programming drain current to less than 10 μ A per memory cell, the limited cell drain current resulting in a high programming efficiency; and
 - a selected row of memory cells being programmable within a shortened row programming interval having a predetermined value less than 100 μ S,
- whereby the limited drain current and the shortened row programming interval define a low-energy write mode of operation for the flash EEPROM.

5,590,078

METHOD OF AND APPARATUS FOR IMPROVED DYNAMIC RANDOM ACCESS MEMORY (DRAM) PROVIDING INCREASED DATA BANDWIDTH AND ADDRESSING RANGE FOR CURRENT DRAM DEVICES AND/OR EQUIVALENT BANDWIDTH AND ADDRESSING RANGE FOR SMALLER DRAM DEVICES


Mukesh Chatter, 53 Godfrey La., Milford, Mass. 01757

Filed Oct. 7, 1994, Ser. No. 320,058

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—189.01

17 Claims



1. A method of improving the data bandwidth and addressing range capabilities of a dynamic random access memory device of the type conventionally having row and column address, data input, data output, and enable pins, and operating with addressing, data write and read cycle control lines connected with corresponding of said pins, the method comprising, on each of write and read cycles, respectively initially addressing row address on a predetermined set of the pins; then addressing on each of the write and read

cycles, column address along the row on the same predetermined set of pins; then, on each of said write and read cycles, and following their respective column addressing, applying and retrieving data on the same predetermined set of pins during the respective write and read cycles, thereby reducing the number of pins required for addressing, writing and reading, and thus increasing data bandwidth and addressing range capabilities of the device.

5,590,079

WAFER BURN-IN TEST CIRCUIT OF A SEMICONDUCTOR MEMORY DEVICE

Jae-Hyeong Lee, Seoul, and Yong-sik Seok, Suwon, both of Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Filed Jun. 7, 1995, Ser. No. 474,158

Claims priority, application Rep. of Korea, Jun. 8, 1994, 12847/1994

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—201

20 Claims



1. A burn-in test circuit for sensing a defective cell of a semiconductor memory device having a plurality of memory cells connected to a word line and a row decoder for selecting the word line, said burn-in test circuit comprising:

a word line driver circuit having an input coupled to receive a row decoding signal generated by the row decoder, and an output node coupled to the word line, said row decoding signal having a first state during a normal mode of operation and a second state different than said first state during a burn-in test mode of operation, said word line driver circuit including:

a word line boosting voltage transferring circuit coupled to receive an enable voltage and to said output node and being controlled by said row decoding signal, said word line boosting voltage transferring circuit being responsive to said row decoding signal in said normal mode of operation to raise said word line to a voltage level of said enable voltage,

and a current pass circuit coupled between said output node and a discharge node and being controlled by said row decoding signal, said current pass circuit being responsive to said row decoding signal in said burn-in test mode of operation to connect said word line to said discharge node;

a control circuit having a first input coupled to receive a burn-in voltage, and a second input coupled to receive a control signal; and an electrical line connected between said discharge node of said word line driver circuit and said control circuit said control circuit being responsive to said control signal in said burn-in test mode of operation to apply said burn-in voltage to the word line via said electrical line and said current pass circuit of said word line driver circuit.

5,590,080 DYNAMIC RANDOM ACCESS MEMORY WITH VARIABLE SENSE-AMPLIFIER DRIVE CAPACITY

Takehiro Hasagawa, and Yukihito Oowaki, both of Kanagawa-ken, Japan, assignors to Kabushiki Kaisha Toshiba, Kanagawa-ken, Japan


Filed Sep. 12, 1995, Ser. No. 527,264

Claims priority, application Japan, Sep. 17, 1994, 6-248435

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—201

31 Claims



1. A semiconductor memory device comprising:
a memory cell array comprising a plurality of memory-cell units arranged in a matrix, each memory-cell unit comprising a plurality of connected memory cells;
a plurality of sense-amplifier circuits, each corresponding to at least one memory-cell unit, for comparing and amplifying a potential difference of data lines of respective corresponding memory-cell units;
a plurality of sense-amplifier drivers for charging or discharging the data lines; and
means for changing drive capacity of the plurality of sense-amplifier circuit drivers during reading-out, restoring, and writing.

5,590,081

SEMICONDUCTOR MEMORY DEVICE

Tamio Shimizu, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan


Filed Oct. 23, 1995, Ser. No. 546,982

Claims priority, application Japan, Oct. 24, 1994, 6-257813

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—203

2 Claims



1. A semiconductor memory device comprising:
a memory cell array in which memory cells to store information therein are arranged along rows and columns and in which an input/output operation of the information is conducted by specifying a row address and a column address;
a sense amplifiers for keeping therein information of one-row memory cells of a row corresponding to a beforehand specified row address, the information being kept as cache data; and
precharge control means;
the memory device achieving, when an external row address externally specified matches the selection row address, a read or write operation of the cache data in the sense amplifier and accomplishing a periodic refresh operation;

the precharge control means completing, during a period of the refresh operation cycle, a predetermined precharge operation for the sense amplifier and bit lines corresponding thereto for the subsequent memory access.

5,590,082

CIRCUIT AND METHOD FOR RETAINING DRAM CONTENT

Seiichi Abe, Odawara, Japan, assignor to Hitachi, Ltd., Tokyo, Japan


Filed Jun. 6, 1995, Ser. No. 467,277

Claims priority, application Japan, Jun. 7, 1994, 6-125377

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—222

19 Claims



1. A memory control circuit comprising a DRAM, a drive circuit for driving said DRAM, a DRAM control circuit for controlling operation of said DRAM through said drive circuit, a power supply connected to said DRAM, said DRAM control circuit and said drive circuit, a first detection circuit for generating a first detection signal that is output to said DRAM control circuit when the power supply voltage is lowered to a first predetermined voltage, and a second detection circuit for generating a second detection signal that is output to said drive circuit when the power supply voltage is lowered to a second predetermined voltage lower than said first predetermined voltage, wherein said DRAM control circuit, when said first detection signal is received, starts self-refreshing and, when said second detection signal is received, said drive circuit establishes a self-refresh mode for said DRAM.

5,590,083

PROCESS OF WRITING DATA FROM A DATA PROCESSOR TO A MEMORY DEVICE REGISTER THAT IS SEPARATE FROM THE ARRAY

Raymond Pinkham, Missouri City, and Anthony M. Balistreri, Houston, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.


Division of Ser. No. 734,028, Jul. 22, 1991, Pat. No. 5,195,056, which is a continuation of Ser. No. 388,783, Aug. 2, 1989, abandoned, which is a continuation of Ser. No. 81,926, Aug. 5, 1987, Pat. No. 4,961,171, which is a continuation-in-part of Ser. No. 53,200, May 21, 1987, Pat. No. 4,817,058. This application Jan. 15, 1993, Ser. No. 4,818

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—230.01

19 Claims

1. A system for writing data to a random access memory array device, said memory array including a plurality of memory cells



arranged in rows and columns, said device having a register separate from said array containing data to be written to said array and having a data port receiving data to be written to said array, comprising:

processor unit circuits for producing a special function signal of one and another value and a column address signal to said device; and

special function circuits in said device and responsive to said special function signal and said column address signal, said special function circuits for writing the contents of said register to said array responsive to said processor unit circuits producing said one state of said special function signal to said device and while producing said column address signal to said device, and said special function circuits for writing the data received at said data port to said array responsive to said processor unit circuits producing said another state of said special function signal to said device and while producing said column address signal to said device.

5,590,084

SEMICONDUCTOR MEMORY DEVICE HAVING A COLUMN SELECTOR

Shinji Miyano; Katsuhiko Sato, both of Yokohama, and Tomoaki Yabe, Kawasaki, all of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Apr. 11, 1995, Ser. No. 419,688

Claims priority, application Japan, Apr. 13, 1994, 6-074549

Int. Cl.⁶ G11C 7/00

U.S. Cl. 365—230.01

30 Claims



1. A semiconductor memory device comprising:
a memory cell array in which a plurality of memory cells are arranged in a matrix, the memory cell array including a plurality of groups of columns;
a plurality of column gates respectively connected to the plurality of columns of the memory cell array;

a plurality of data lines provided for the plurality of groups of columns and connected in common to first ends of column gates of a corresponding group of columns;

a column decoder row including column decoders, of the number greater than the number of column addresses of the memory cell array, for decoding a column address signal which designates a column of the memory cell array; and

a plurality of logical circuits, provided for columns of different column addresses in the memory cell array, for controlling the column gates of the respective columns by means of a logical OR between outputs from a predetermined plurality of column decoders for decoding different column addresses of the column decoder row.

5,590,085

COLUMN REDUNDANCY DEVICE FOR SEMICONDUCTOR MEMORY

Jong H. Yuh, and Jong G. Nam, both of Kyongki-do, Rep. of Korea, assignors to Hyundai Electronics Industries Co., Ltd., Rep. of Korea


Filed Jun. 7, 1995, Ser. No. 475,863

Claims priority, application Rep. of Korea, Jun. 8, 1994, 94-12824

Int. Cl.⁶ G11C 7/00; 8/00

U.S. Cl. 365—230.03

3 Claims



1. In a semiconductor memory having at least two memory blocks, each of said at least two memory blocks including a plurality of cell array blocks and a redundancy cell array, and input/output means for performing bidirectional data transmission with said at least two memory blocks, a column redundancy device comprising:

address input means for inputting a first row address signal used to select said cell array blocks regardless of a refresh speed of said semiconductor memory, a second row address signal selectively used to select said cell array blocks according to the refresh speed of said semiconductor memory, a first column address signal used to select one of said at least two memory blocks to be connected to said input/output means, and a second column address signal used to select bit lines included in said cell array blocks;

block programming means for determining in response to said first row address signal whether a desired number of said plurality of cell array blocks are selected;

auxiliary block programming means for determining in response to one of said second row address signal and said first column address signal and an output signal from said block programming means whether any one of said desired number of cell array blocks is selected; and

column programming means for determining in response to said second column address signal and an output signal from said auxiliary block programming means whether any one of said bit lines in said cell array block selected by said one of said second row address signal and said first column address signal

and said first row address signal is addressed and selectively driving any one of memory cells included in said redundancy cell array in accordance with the determined result.

5,590,086

SEMICONDUCTOR MEMORY HAVING A PLURALITY OF I/O BUSES

Churoo Park, Suwon; Hyun-Soon Jang, Seoul; Chul-Soo Kim, Suwon; Myung-Ho Kim, Suwon; Seung-Hun Lee, Suwon; Si-Yeol Lee, Yongin-gun; Ho-Cheol Lee; Tae-Jin Kim, both of Seoul, and Yun-Ho Choi, Suwon, all of Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea


Division of Ser. No. 130,138, Oct. 4, 1993. This application Dec. 29, 1995, Ser. No. 580,481

Claims priority, application Rep. of Korea, Oct. 2, 1992, 18130; Oct. 2, 1992, 18131; Apr. 27, 1993, 7127

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—230.03

1 Claim



1. A semiconductor memory comprising:

a memory cell array having a plurality of memory cells arranged in rows and columns;

a plurality of sub-arrays provided by partitioning the memory cell array in a row direction, each of the sub-arrays having a plurality of word lines respectively connected to associated columns of the memory cells and a plurality of bit lines respectively connected to associated rows of the memory cells, the bit lines of each sub-array divided into first groups of bit lines and second groups of bit lines, the respective ones of which are divided into first sub-groups of bit lines and second sub-groups of bit lines, the first groups of each sub-array alternately arranged with the second groups thereof, the first sub-groups of each sub-array alternately arranged with the second sub-groups thereof; and

I/O buses respectively disposed in parallel to the word lines between the sub-arrays and on outer sides of the sub-arrays, and divided into first I/O buses and second I/O buses respectively arranged at odd and even positions, each I/O bus divided into first I/O lines and second I/O lines, the first and the second I/O lines of the respective first I/O buses respectively connected via column selection switches with the bit lines of the first and the second sub-groups of the first groups of sub-arrays adjacent thereto, the first and the second I/O lines of the respective second I/O buses respectively connected via column selection switches with the bit lines of the first and the second sub-groups of the second groups of sub-arrays adjacent thereto.

5,590,087


MULTI-PORTED DATA STORAGE DEVICE WITH IMPROVED CELL STABILITY

Shine Chung, and Paul G. Emerson, both of San Jose, Calif., assignors to Hewlett-Packard Company, Palo Alto, Calif. Continuation of Ser. No. 317,986, Oct. 4, 1994, abandoned, which is a continuation of Ser. No. 58,118, May 5, 1993, abandoned. This application Sep. 25, 1995, Ser. No. 533,133

Int. Cl.⁶ G11C 11/34; 7/00; 8/00

U.S. Cl. 365—230.05

7 Claims



1. A multi-ported register file, comprising:

a plurality of memory cells, each of said memory cells having first and second nodes;

a first plurality of write-side switching devices associated with each of said memory cells, each of said first plurality of write-side switching devices, when activated, connecting a different write bit line to the first node of said memory cell associated therewith;

a second plurality of write-side switching devices associated with each of said memory cells, each of said second plurality of write-side switching devices, when activated, connecting a different write-side read bit line to the first node of said memory cell associated therewith;

a plurality of read-side switching devices associated with each of said memory cells, each of said read-side switching devices, when activated, respectively connecting a different read-side read bit line to one of a plurality of read-side intermediate nodes;

a plurality of unidirectional read-side isolation devices, each of said unidirectional read-side isolation devices operatively connecting the second node of one of said memory cells to one of said read-side intermediate nodes, and each of said unidirectional read-side isolation devices comprising a field-effect transistor having a gate terminal connected to the second node of one of said memory cells, a source terminal connected to said one of said read-side intermediate nodes, whereby each of said unidirectional read-side isolation devices substantially prevents one of the read-side read bit lines from influencing a signal stored at one of said memory cells while enabling the signal stored at said one of said memory cells to influence said one of said read-side intermediate nodes;

a plurality of unidirectional write-side isolation devices, each of said unidirectional write-side isolation devices operatively connecting the first node of one of said memory cells to one of write-side intermediate nodes, and each of said unidirectional write-side isolation devices comprising a field-effect transistor having a gate terminal connected to the first node of one of said memory cells, a source terminal connected to the fixed voltage source and a drain terminal connected to said

one of said write-side intermediate nodes, whereby each of said unidirectional write-side isolation devices substantially prevents one of the write-side read bit lines from influencing a signal stored at one of said memory cells while enabling the signal stored at said one of said memory cells to influence said one of said write-side intermediate nodes; and

a differential sense amplifier connected between said read-side read bit lines and said write-side read bit lines.

5,590,088

SEMICONDUCTOR MEMORY DEVICE WITH ENABLE SIGNAL CONVERSION CIRCUIT OPERATIVE FOR REDUCING CURRENT CONSUMPTION

Noriaki Sakurada, Suwa, Japan, assignor to Seiko Epson Corporation, Tokyo, Japan

PCT No. PCT/JP94/01119, § 371 Date Mar. 13, 1995, § 102(e) Date Mar. 13, 1995, PCT Pub. No. WO95/02885, PCT Pub. Date Jan. 26, 1995


PCT Filed Jul. 7, 1994, Ser. No. 403,691

Claims priority, application Japan, Jul. 13, 1993, 5-173229

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—233

12 Claims



1. In a semiconductor memory device having a semiconductor memory area containing memory cells, and an enable signal conversion circuit that converts an external enable signal delivered from outside said device into an internal enable timing signal for controlling internal enable signals to be applied to the semiconductor memory area, the enable signal conversion circuit causing the internal enable timing signal to be in an active state at all times when the external enable signal is in an active state, the improvement wherein said enable signal conversion circuit comprises an active state maintenance unit that maintains the internal enable signal in the active state for a specified period of time independently of a change in state of the external enable signal.

5,590,089

ADDRESS TRANSITION DETECTION (ATD) CIRCUIT

Frankie F. Roohparvar, Cupertino, Calif., assignor to Micron Quantum Devices Inc., Santa Clara, Calif.

Filed Jul. 25, 1995, Ser. No. 506,168

Int. Cl.⁶ G11C 8/00

U.S. Cl. 365—233.5

4 Claims

26. A method of detecting address line transitions in a memory, comprising the steps of:

limiting means and said resilient member when said magnetic head is in the recording position.

5,590,096

REWITABLE STORAGE APPARATUS USING FIRST AND SECOND BIAS MAGNETIC FIELDS

Masaoki Ohtsuka, Kawasaki; Teruji Yamakawa, Yokohama, and Tetsuo Maruyama, Hyogo, all of Japan, assignors to Fujitsu Limited, Japan


Filed Nov. 18, 1994, Ser. No. 341,743

Claims priority, application Japan, Jan. 31, 1994, 6-009423

Int. Cl.⁶ G11B 11/00

U.S. Cl. 369—13

14 Claims



1. A rewritable storage apparatus which, when new data is recorded in an area on a medium, performs an erase operation to erase data recorded in said area by applying a second bias magnetic field for data erasing to said area then performs a record operation to record said new data by applying a first bias magnetic field for data recording to said area, comprising:

- a bias application unit for applying said bias magnetic field to said medium, said bias magnetic field being switchable between said first bias magnetic field and said second bias magnetic field; and
- a bias control means for controlling said bias application unit so that said second bias magnetic field for data erasing is applied to said medium directly after said record operation is finished and said second bias magnetic field for data erasing is maintained.

5,590,097

MAGNETOOPTIC RECORDING MEDIUM

Akira Kashiwakura, Yuuki-gun; Katsusuke Shimazaki, Kitasouma-gun; Masafumi Yoshihiro, Yuuki-gun; Shin-Itsu Kinoshita, Toride; Norio Oota, Kitasouma-gun, and Hisanori Sugiyama, Tsukuba, all of Japan, assignors to Hitachi Maxell, Ltd., Ibaraki-ken, Japan

Filed Dec. 15, 1994, Ser. No. 356,547


Claims priority, application Japan, Dec. 15, 1993, 5-343732

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—13

11 Claims

1. A magneto-optic recording medium comprising a substrate and a magneto-optic recording film thereon, said medium having, on said substrate, a plurality of tracks on which magneto-optic recording signals are recorded, a part of said tracks selected from the plurality of tracks including clusters of pre-pits having pre-pit densities of at least 2×10^5 pre-pits/mm², wherein $(\Delta A/A) \leq 20\%$ is satisfied, provided that (a) is a difference in magnitude between a variation in light amount detected in a track region within 10 tracks from the tracks including the cluster of pre-pits and a variation in light amount (A) detected in a track region other than the track region, when signals from the tracks with recorded magneto-optic



recording signals are measured by changes in light amount on the basis of Kerr rotational angles of reflected light from the medium.

5,590,098

MAGNETOOPTICAL RECORDING AND REPRODUCING APPARATUS HAVING AN AUTOMATIC HEAD LIFTING DEVICE


Jae-Yong Eom, Seoul, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-Do, Rep. of Korea
Division of Ser. No. 131,540, Oct. 5, 1993, Pat. No. 5,450,377.
This application Jun. 6, 1995, Ser. No. 470,041

Claims priority, application Rep. of Korea, Oct. 5, 1992, 92-18175; Jun. 1, 1993, 93-9795; Jun. 1, 1993, 93-9798; Jun. 1, 1993, 93-9800

Int. Cl.⁶ G11B 13/04; 21/12

U.S. Cl. 369—13

3 Claims



1. A magneto-optical recording/reproducing apparatus for recording/reproducing information, using a disk cartridge which houses a magneto-optical disk in a rotatable state, said apparatus having a deck on which the disk cartridge is loaded, an optical pickup assembly movably seated on the deck to project a focused light beam onto one surface of the magneto-optical disk, and a magnetic head for applying a magnetic field onto the other surface of the magneto-optical disk, said apparatus comprising:

- a cartridge holding member which receives the disk cartridge when the disk cartridge is inserted into the apparatus, said cartridge holding member being pivotally mounted with respect to the deck, so that the disk cartridge can be moved between a closing position, in which the disk cartridge is

loaded on the top of the deck, and an opening position in which the received disk cartridge is detached from the top of the deck, when the disk cartridge is received in the apparatus; ejecting means for ejecting the disk cartridge from the cartridge holding member in response to movement of the cartridge holding member from the closing position to the opening position, said ejecting means comprising an ejecting member for pushing the disk cartridge received in the cartridge holding member in the ejecting direction, a locking means for locking the ejecting member, and a locking releasing means interlocked with the cartridge holding member to move the locking means, said locking releasing means being movable and having a one-direction elastic operation means which operates the locking member when moved in one direction and does not operate the locking member when moved in the opposite direction;

- a connecting member pivotally connecting the magnetic head and the optical pickup assembly so that the magnetic head moves together with the optical pickup assembly in the radial direction of the magneto-optical disk and the magnetic head is pivotal in a movement direction of the cartridge holding member with respect to the optical pickup assembly; and magnetic head lifting means interlocked with a recordable disk cartridge which is inserted into and extracted from the cartridge holding member, so as to lower the magnetic head toward the magneto-optical disk of the recordable disk cartridge.

5,590,099

MAGNETO-OPTICAL RECORDING METHOD AND METHOD FOR MAKING INFORMATION-CARRYING MAGNETO-OPTICAL RECORDING MEDIUM

Giichi Shibuya, Chiba; Masanori Shibahara, Nagano; Suguru Takayama, Chiba, and Hajime Utsunomiya, Nagano, all of Japan, assignors to TDK Corporation, Tokyo, Japan


Filed Dec. 11, 1995, Ser. No. 570,471

Claims priority, application Japan, Dec. 19, 1994, 6-334523

Int. Cl.⁶ G11B 11/00; 13/00

U.S. Cl. 369—13

6 Claims



1. A method for recording information in a magneto-optical recording medium including a groove having a wobble, which is operated in a recording/reading apparatus adapted to carry out recording and reading operation in a magnetic field modulation mode, comprising the steps of

- recording information while controlling a recording linear velocity in accordance with the wobble, and
- recording address-related information at the end of recording, wherein the recording of information for a first time being carried out in an optical modulation mode at a linear velocity which is higher than a reading linear velocity.

5,590,100

INFORMATION RECORDING/REPRODUCING TECHNIQUE TO RECORD PLURAL-CHANNEL INFORMATION FOR SUBSEQUENT SIMULTANEOUS REPRODUCTION

Mikio Ogusu, and Kazunobu Fujiwara, both of Hamamatsu, Japan, assignors to Yamaha Corporation, Hamamatsu, Japan


Filed May 17, 1995, Ser. No. 444,844

Claims priority, application Japan, Jun. 3, 1994, 6-145548

Int. Cl.⁶ G11B 7/00

U.S. Cl. 369—32

23 Claims



1. A recording device comprising:

- recording means for recording program information of plural channels onto a recording medium in such a manner that said program information of the plural channels can be simultaneously reproduced from said recording medium; and reproduction information generation means for, with respect to said program information recorded on said recording medium, generating reproduction information, wherein the reproduction information comprises either information that indicates each position of the program information to be reproduced, or information that indicates each position of the program information to be silenced, or both.

5,590,101

TRACK JUMP CONTROLLER FOR OPTICAL DISK RECORDING

Satoshi Ito, Tokyo, Japan, assignor to NEC Corporation, Japan


Filed May 31, 1995, Ser. No. 455,980

Claims priority, application Japan, May 31, 1994, 6-117779; Jul. 27, 1994, 6-175613; Oct. 24, 1994, 6-257816

Int. Cl.⁶ G11B 17/22

U.S. Cl. 369—32

41 Claims



1. An optical disk apparatus comprising:

- an optical disk has a recording area constituted by a plurality of equal clock blocks obtained by dividing a track area in a radial direction, the optical disk rotates at a constant rotational speed in synchronism with one of a frame frequency and a field frequency of recording data;
- an optical head for optically recording data on said optical disk;

a readout part that sequentially reads out the data stored in the storage device at the predetermined reproduction speed; and a control part that, when an amount of data in the storage means which has not yet been read out by the readout part reaches a predetermined value, returns the data pickup part to any of the tracks from which the data has already been read out by the data pickup part.

5,590,113

DISC CLAMPING DEVICE FOR SELECTIVELY CLAMPING A COMPACT DISC IN A UNITED DEVICE
Youngsuk Choi, Seoul, Rep. of Korea, assignor to Daewoo Electronics Co., Ltd., Seoul, Rep. of Korea


Filed Dec. 23, 1994, Ser. No. 363,344

Claims priority, application Rep. of Korea, Dec. 28, 1993, 93-30146

Int. Cl. G11B 17/035; 17/04; 33/02

U.S. Cl. 369—270

5 Claims



1. A disc clamping device comprising:

a tray holder having first guide bars outwardly projecting from side walls thereof, said tray holder receiving a disc tray for loading a first naked disc thereon, and a cartridge tray for loading a second disc encased in a cartridge thereon and having a size smaller than that of said first naked disc;

a moving plate having side portions for guiding a horizontal and inclined movement of said first guide bars and a guide plate for guiding a linear movement of said moving plate, said side portions each provided with a first stepped cut portion into which said first guide bars are inserted, an arcuate portion defined in a lower corner of a rear end of said moving plate, a rack gear formed in a lower edge of said moving plate, and said guide plate formed incorporated with an upper part of said moving plate;

a base plate including two side walls, each of said side walls having a first reversed "L" shaped cut-out portion into which said first guide bars are inserted;

a loading means fixed to said base plate for driving said rack gear; and

a clamping means having a supporter mounted to a rear end of said base plate, a clamping arm folded so as to pivot about a hinged shaft of said supporter, a rotating body integrally formed with said clamping arm and positioned between said clamping arm and said supporter, an actuating rod projected on a lower side surface of said rotating body, and a clamping member mounted on a forward portion of said clamping arm folded at an angle to the rest of said clamping arm, said actuating rod being forced to pivot by said arcuate portion of said moving plate, so that said clamping means selectively clamps said first naked disc when said disc tray is loaded.

5,590,114

COMPACT DISC PLAYBACK ENHANCER


John P. Murphy, 37508 Grove Ave., Willoughby, Ohio 44094, assignor to John P. Murphy, Willoughby, Ohio

Continuation of Ser. No. 884,283, May 13, 1992, abandoned, which is a continuation of Ser. No. 283,127, Dec. 12, 1988, abandoned. This application May 26, 1995, Ser. No. 453,072

Int. Cl. G11B 7/24; 33/14

U.S. Cl. 369—290

10 Claims



1. In combination with a player having a spinning mechanism, a data storage disc for being read in the player, the data storage disc comprising:

a pulse code modulated optical disc having a first side and a second side, the data storage disc having a data retrieval portion on the first side from which data is retrieved by the player and having a drive portion on the first side;

an annular dampening and friction component ring on the first side of the optical disc for engagement by the spinning mechanism, the ring substantially covering the drive portion and leaving the data retrieval portion completely uncovered, the ring made from a soft flexible material and having a friction coefficient greater than that of the optical disc for simultaneously

absorbing and dampening vibration of the optical disc and reducing the transmission of vibrations between the optical disc and the spinning mechanism and improving the frictional engagement of the optical disc with the spinning mechanism,

the soft and flexible material having a Shore A hardness of between 0 and 100; and

a flexible dampening adhesive layer for adhering the ring to the drive portion of the optical disc, the adhesive layer covering the drive portion and leaving the data retrieval portion completely uncovered, the adhesive layer being non-rigid and pliable and made from a soft flexible material for absorbing and dampening and reducing the transmission of vibrations between the optical disc and the spinning mechanism, the adhesive layer interposed between the drive portion of the disc and the spinning mechanism.

5,590,115

OPTICAL DISK AND APPARATUS FOR MANUFACTURING THE SAME

Toyohide Kubo, Tokushima, Japan, assignor to Awa Engineering Co., Ltd., Tokushima, Japan

Continuation of Ser. No. 78,051, Jun. 18, 1993, abandoned.

This application Aug. 29, 1995, Ser. No. 521,023

Claims priority, application Japan, Jun. 22, 1992, 4-188663

Int. Cl. G11B 7/24


U.S. Cl. 369—290

20 Claims

1. An optical disk comprising:

a plastic disk having a central plate-receiving part;

a clamping plate mounted in said central plate-receiving part of said plastic disk and retained in said central plate-receiving



part of said plastic disk by a heat pressed and deformed portion of said plastic disk at a periphery of said central plate-receiving part of said plastic disk;

wherein said heat pressed and deformed portion of said plastic disk has been discontinuously heat pressed so as to form heat pressed segments with circumferentially spaced apart gaps therebetween and so as to connect said clamping plate to said plastic disk;

wherein said clamping plate includes a circular central part and an annular outer part surrounding said central part;

wherein a radial gap is formed between an inner peripheral edge of said discontinuously heat pressed and deformed portion of said plastic disk and a radially outwardly facing edge of said central part of said clamping plate;

wherein an annular gap is formed between said periphery of said central plate-receiving part of said plastic disk and a periphery of said annular part of said clamping plate, such that said clamping plate is radially movably disposed in said central plate-receiving part;

wherein said circumferentially spaced apart gaps between said projection segments constitute means for viewing, along an axial direction, segments of said annular gap at circumferentially spaced apart locations thereof; and

wherein, when said clamping plate is concentric with said plate-receiving part, said heat pressed and deformed portion of said plastic disk does not contact said circular central part of said clamping plate.

5,590,116


MULTI-PORT ANALYZING, TIME STAMP SYNCHRONIZING AND PARALLEL COMMUNICATING
Jing Zhang, Durham, N.C., assignor to Wandel & Goltermann Technologies, Inc., Research Triangle Park, N.C.

Filed Feb. 9, 1995, Ser. No. 385,288

Int. Cl. H04J 1/16

U.S. Cl. 370—253

11 Claims



1. An analyzer for digital transmission networks with multiple ports, said analyzer having data packet analyzing capability, a

facility for participating in an analysis with at least one other analyzer with which said analyzer is synchronized and in intercommunication outside of the digital transmission networks under the analysis, for said analysis at least two ports of a digital transmission network, said analyzer including:

a clock having an output and constituting a part of said analyzer; a counter, the output of which is used to time stamp data packets received by said analyzer, the input of the counter being interconnectable with the output of the clock of said other analyzer;

the output of said clock being interconnectable with the input of the counter of said analyzer and to the input of the counter of said other analyzer;

a clock control circuit for selectively interconnecting the clock of said analyzer to the counter of said analyzer and to the counter of said other analyzer, and for disconnecting the clock of said analyzer from the counter of said analyzer in response to a clock-disable signal received by said analyzer from a source external to said analyzer, thereby allowing the clock output of said other analyzer to substitute for the output of the disconnected clock of said analyzer;

at least one receive-transmit circuit, having a receive mode and a transmit mode, for intercommunicating, separately from said digital transmission network, in either direction with said other analyzer; and

a receive-transmit control circuit for controlling the transmission and reception capability of the receive-transmit circuit in response to a command from a source external to said analyzer.

5,590,117

NODE INFORMATION COLLECTING METHOD IN A RING SYSTEM

Suichi Iida, Tokyo, and Masayuki Oyama, Miyagi, both of Japan, assignors to NEC Corporation, Tokyo, Japan


Filed Mar. 29, 1995, Ser. No. 413,102

Claims priority, application Japan, Mar. 29, 1994, 6-059524

Int. Cl. H04J 3/14

U.S. Cl. 370—248

12 Claims



1. A method for collecting node information in a ring network comprising a plurality of nodes, the method comprising the steps of:

retaining self-node information in each of the nodes at predetermined time intervals; and

accessing two adjacent nodes clockwise and counterclockwise adjacent to each of the nodes to collect node information retained in the two adjacent nodes at the predetermined time intervals so that each of the nodes stores node information of all the nodes.

5,590,118

METHOD FOR REROUTING A DATA STREAM

Leo Nederlof, Antwerp, Belgium, assignor to Alcatel N.V., Rijswijk, Netherlands


Filed Aug. 23, 1995, Ser. No. 518,268


Claims priority, application European Pat. Off., Aug. 23, 1994, 94202415; Aug. 3, 1995, 95202121

Int. Cl.⁶ H04L 12/24; G06F 11/20


U.S. Cl. 370—218

33 Claims





5,590,129
SINGLE STAGE TELECOMMUNICATIONS SWITCH WITH PARTITIONED PROCESSORS
 Menachem T. Ardon, Naperville, Ill., assignor to Lucent Technologies Inc., Murray Hill, N.J.
 Filed Dec. 22, 1994, Ser. No. 361,414
 Int. Cl.⁶ H04Q 11/04
 U.S. Cl. 370—376 16 Claims




1. A single stage time slot interchange TSI unit for interconnecting a plurality of telecommunications transceiver comprising: a plurality of TSI slices each for transmitting and receiving signals of a group of time slots, said plurality of TSI slices interconnected to form a single stage TSI switch for interconnecting all time slots of said plurality of TSI slices; and a plurality of module processors, each for controlling a separate subset of said TSI slices;

Wherein a connection between a first telecommunications transceiver connected to a first TSI slice controlled by a first of said module processors and a second telecommunications transceiver connected to a second TSI slice controlled by a second of said module processors is established through cooperative actions by said first and said second module processors;


Wherein said first module processor transmits a message to said second module processor identifying a first time slot and said second module processor transmits a message to said first module processor identifying a second time slot and wherein a connection is established by having said first module processor control said first TSI slice to establish a connection between said first time slot and said second time slot and said second module processor controls said second TSI slice to establish a connection between said second time slot and said first time slot whereby a connection is established between time slots connectable to said first and said second telecommunications transceiver.

5,590,130
BUS PROTOCOL USING SEPARATE CLOCKS FOR ARBITRATION AND DATA TRANSFER
 William T. Krein, San Jose; Charles M. Flaig, Cupertino, and James D. Kelly, Aptos, all of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.
 Continuation of Ser. No. 186,380, Jan. 25, 1994, abandoned.
 This application Aug. 2, 1995, Ser. No. 510,557
 Int. Cl.⁶ H04L 12/417
 U.S. Cl. 370—462 13 Claims



1. In a bus system comprising a central arbiter and a plurality of nodes coupled to a bus, a data communication process comprising the steps of: arbitrating among the plurality of nodes by the central arbiter synchronously with an arbitration clock signal to provide bus access to a first node of the plurality of nodes coupled to the bus; transferring by the first node a data packet through the bus to a second node of the plurality of nodes coupled to the bus according to a data clock signal generated by the first node independently from the arbitration clock signal; and transferring by the first node to the second node a done signal according to the data clock signal.

5,590,131
EFFICIENT DISTRIBUTED QUEUEING RANDOM ACCESS METHOD FOR THE MEDIUM ACCESS CONTROL LAYER IN NETWORKS WITH BROADCAST CHANNELS
 Mete Kabatepe, Norwood, Mass., assignor to Motorola, Inc., Schaumburg, Ill.
 Filed May 30, 1995, Ser. No. 453,854
 Int. Cl.⁶ H04T 3/02
 U.S. Cl. 370—461 18 Claims



10. A network system for providing efficient distributed queueing random access for the medium access control layer in networks with broadcast channels, for conserving reservation bandwidth and concomitantly providing immediate transmission access, wherein, prior to receiving a first time slot, a plurality of reservation slot parameters are initialized by a user of a plurality of users, comprising:


- A) a headend controller, responsive to a plurality of users, for controlling transmissions between the headend controller and the plurality of users; and
- B) the plurality of users, responsive to the headend controller, for receiving and transmitting on predetermined broadcast

channels, wherein each user includes a reservation counter scheduler, wherein each reservation counter scheduler operates to conserve reservation bandwidth and concomitantly provide immediate transmission access by:

- C) receiving a time slot;
- D) determining whether any reservation in a previous time slot was successful, and, where a reservation has been successful, executing a predetermined reservation updating procedure to provide a user reservation position, and where a reservation has been unsuccessful, updating reservation temporary value (RCtemp);
- E) determining whether at least one of the feedbacks indicates failure of reservation, and where feedbacks fail to indicate failure of reservation, proceeding to step G;
- F) performing, where at least one of the feedbacks indicates failure of reservation, predetermined reserved pointer adjustments;
- G) determining transmission probability for the user;
- H) determining whether the user is eligible to transmit, and where eligible, whether the user has a data segment for transmission; and where one of:
 - the user is ineligible to transmit, and
 - the user is eligible to transmit and the user fails to have data segments for transmission,
 proceeding to step I;
- I) executing, where user's reservation position is in the current time slot, a reservation-transmission procedure, and where the user's reservation position fails to be in the current time slot, proceeding to step J; and
- J) executing a predetermined distributed global queue temporary value (DQtemp) procedure for reserving, where needed, a minislot in an upcoming frame.

5,590,132
CONGESTION RELIEVING SYSTEM IN A COMMUNICATION SYSTEM


Ryoichi Ishibashi, and Katsumi Sekine, both of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan.
 Continuation of Ser. No. 831,794, Feb. 5, 1992, Pat. No. 5,341,373. This application Mar. 22, 1994, Ser. No. 216,049
 Claims priority, application Japan, Feb. 5, 1991, 3-035519; Feb. 5, 1991, 3-035520
 Int. Cl.⁶ H04J 3/02; H04L 12/40
 U.S. Cl. 370—236 10 Claims



9. A method for transmitting a first cell having a request bit from a local switch to a customer station by way of a down-signal bus and for receiving a second cell from the customer station by way of an up-signal bus, comprising the steps of: generating a cell restriction signal when the customer station is to be restricted from sending the second cell; inserting the cell restriction signal as the request bit in the first cell; transmitting the first cell to the customer station; monitoring the request bit to control sending the second cell onto the up-signal bus; and


inserting the request bit into the first cell to indicate that the customer station possesses data to be sent on the second cell.

5,590,133
APPARATUSES AND MOBILE STATIONS FOR PROVIDING PACKET DATA COMMUNICATION IN DIGITAL TDMA CELLULAR SYSTEMS
 Lars Billström, Sonja; Lars Wetterborg; Steinar Dahlin, both of Järfälla, and Bengt Persson, Djursboholm, all of Sweden, assignors to Telefonaktiebolaget LM Ericsson, Stockholm, Sweden
 Filed Dec. 9, 1994, Ser. No. 354,874
 Claims priority, application Sweden, Dec. 10, 1993, 9304119
 Int. Cl.⁶ H04T 3/26; H04Q 7/38
 U.S. Cl. 370—349 57 Claims



1. An apparatus for providing packet data communication to and from mobile stations in a digital TDMA cellular system having a plurality of base stations providing regular cellular control channels and regular cellular dedicated traffic channels; one or more mobile services switching centers, each being associated with a visitor location register and being coupled to a subordinated plurality of the base stations; and home location register means for storing information on mobile station subscribers, the apparatus comprising:

- channel providing means for providing, in at least some of the base stations, on a per cell basis, one or more shared packet data channels for packet transfer to and from the mobile stations, and packet transfer controlling means for controlling the packet transfer;
- channel defining means for defining, on a per cell basis, the packet data channel to be used for packet transfer;
- first packet data mode establishing means for establishing packet data mode for a mobile station to enable the mobile station to send and receive packets over the packet data channels;
- first packet transferring means for transferring packets between the mobile stations and base stations;
- second packet transferring means for transferring packets between the base stations and their respective superior mobile services switching centers;
- packet routing means for routing packets to and from a service area of a mobile services switching center;
- first means for performing cell selection for a mobile station in packet data mode;
- first means for performing location updating for the mobile station in packet data mode;
- first packet data mode maintaining means for maintaining the packet data mode for a roaming mobile station; and



operation of said light-emitting means based on detection signal so that said light emitting means selectively changes the direction of the polarization plane of output light to one of the two orthogonal directions.


5,590,146 GAS LASER

Michael von Borstel, Stuttgart, Germany, assignor to Trumpf Lasertechnik GmbH, Ditzingen, Germany
Filed May 19, 1995, Ser. No. 444,782
Claims priority, application Germany, May 19, 1994, 44 17 468.3

Int. Cl.⁶ H01S 3/22; 3/223

U.S. Cl. 372—58

25 Claims



1. A gas laser assembly having
 - (a) a laser-gas circulation path (5) including a fan (4) which moves the laser gas (6) through the laser discharge space (2) and a cooling system (3a, 3b);
 - (b) a bypass (8) connected to said path on opposite sides of said fan through which a part (15) of the laser gas (6) is moved by the fan (4) to bypass the laser discharge space (2); and
 - (c) means for opening and for blocking said bypass (8) so that it can be turned off and on.


5,590,147 SIDE-PUMPED LASERS

John W. Hobbs, Somerset, and Laurence E. Cramer, Flemingston, both of N.J., assignors to The Morgan Curcible Company plc, Windsor, United Kingdom
Filed Dec. 19, 1994, Ser. No. 359,074
Int. Cl.⁶ H01S 3/091; 3/094

U.S. Cl. 372—75

16 Claims

1. A solid-state laser comprising:
 - a. a material having opposed first and second sides and first and second ends and adapted to emit lasing radiation, wherein the first and second sides of the material are convex, the material having an oblong shape;
 - b. first and second means spaced along the first and second sides of the material, respectively, for pumping the material by emitting pumping radiation, wherein each of the pumping means spaced along the first and second sides of the material comprises a 1×N array of diodes, where N is an integer greater than one;



- c. a lens having a cylindrical shape interposed optically between the first pumping means and the first side of the material, for at least partially collimating the emitted pump radiation; and
- d. means for redirecting the emitted lasing radiation through the material along at least four paths extending from the first end of the material to the second end, wherein the redirecting means comprises a prism having adjoining first and second faces, at least one of the four paths extending to the first face and another of the four paths extending to the second face, and a truncated prism having a plurality of reflective faces, each of the four paths extending to at least one of which reflective faces.

5,590,148

BIREFRINGENT BEAMSPLITTER FOR HIGH POWER LASERS AND LASER APPLICATIONS


Eric B. Szarmes, Durham, N.C., assignor to Duke University, Durham, N.C.

Filed Aug. 24, 1994, Ser. No. 295,169

Int. Cl.⁶ H01S 3/08

U.S. Cl. 372—105

27 Claims




1. In a high intensity laser of the type having three reflective surfaces and beam splitting means for producing a plurality of optical paths using a lasing medium having opposite ends and located between two of said reflective surfaces with the beam splitting means being located between one of the reflective surfaces and one of said ends of the lasing medium, said beam splitting means comprising a birefringent crystal having at least two substantially parallel surfaces, a first one of said optical paths passing between said two reflective surfaces and through said lasing medium, said two parallel surfaces of said crystal intercepting said first one of said optical paths at an angle of interception sufficiently close to Brewster's angle such that another of said optical paths is created from a first one of said two parallel surfaces with a beam having a polarization of one type and a further one of said optical paths is created from the second one of said two parallel surfaces with a beam having a polarization that is different from that of said one type, said further one of said optical paths including said third of said reflective surfaces.

5,590,149 MIRROR MOUNT

Dennis Reeder, South Jordan, Utah, assignor to Spectra-Physics Lasers, Inc., Mountain View, Calif.
Filed Sep. 13, 1995, Ser. No. 527,564
Int. Cl.⁶ H01S 3/08

U.S. Cl. 372—107

16 Claims



1. A mirror mount assembly, comprising:
 - a base plate positioned at one end of a laser resonator;
 - a movable plate spaced from and positioned substantially parallel to the base plate; and
 - one or more elastic springs connected between the base plate and the movable plate to provide tip and tilt of the movable plate away from or towards the base plate, each elastic spring including a bushing made of an elastic material capable of elastic expansion and contraction, the bushing including a threaded interior side, a longitudinal axis and at least three elastic dimples formed in the bushing circumferentially in a plane across the bushing longitudinal axis and extend into the bushing threaded interior side to flexibly contact one or more threads of a screw received in the bushing threaded interior side, wherein the dimples are dimensioned to be smaller than a screw thread and configured to permit rotation of the bushing and screw relative to each other to advance and retract the screw along the longitudinal axis and provide a selected adjustment of the screw along the bushing's longitudinal axis with reduced mechanical hysteresis of the screw.

5,590,150

ELECTRIC ARC MELTING FURNACE

Masaki Ogushi, Yokohama; Osamu Takeuchi, Mitaka; Ikuro Yamamura, Tokyo; Toru Iura, Fujisawa, and Hironobu Yoshida, Urayasu, all of Japan, assignors to Ishikawajima-Harima Jukogyo Kabushiki Kaisha, Tokyo, Japan

PCT No. PCT/JP94/00619, § 371 Date Dec. 9, 1994, § 102(e) Date Dec. 9, 1994, PCT Pub. No. WO95/09336, PCT Pub. Date Apr. 6, 1994

PCT Filed Apr. 14, 1994, Ser. No. 338,545


Claims priority, application Japan, Sep. 30, 1993, 5-244839; Dec. 22, 1993, 5-324158

Int. Cl.⁶ F27D 17/00

U.S. Cl. 373—9

4 Claims

1. An electric arc melting furnace comprising:
 - a furnace shell with an electrode for melting scrap by heat of arc;
 - an air blasting port for blasting air oxygen or oxygen-enriched air to an upper space in said furnace shell through an air control valve;
 - a carbon blasted quantity indicator for measuring quantity of carbon to be charged into said furnace shell;
 - a scrap charged quantity indicator for measuring quantity of the scrap charged into said furnace shell;



an oxygen blasted quantity indicator for measuring quantity of oxygen blasted into said furnace shell; and
arithmetic processor for computing quantity of air required for complete combustion of carbon monoxide quantity of which is determined by calculation on chemical reaction from the quantity of carbon in the scrap measured by said scrap charged quantity indicator, from the quantity of carbon measured by said carbon blasted quantity indicator and from the quantity of oxygen measured by said oxygen blasted quantity indicator to control a degree of opening of said air control valve.

5,590,151

PROCESS FOR MELTING SCRAP IRON IN AN ELECTRIC FURNACE AND INSTALLATION FOR IMPLEMENTING THE PROCESS

Guy Forestier, Saint-Just-Saint-Rambert, France, assignor to Clecim, Cergy-Pontoise, France


PCT No. PCT/FR94/00523, § 371 Date Jun. 12, 1995, § 102(e) Date Jun. 12, 1995, PCT Pub. No. WO94/26938, PCT Pub. Date Nov. 24, 1994

PCT Filed May 5, 1994, Ser. No. 374,514

Claims priority, application France, May 13, 1993, 93 05785
Int. Cl.⁶ F27D 1/00

U.S. Cl. 373—72

7 Claims



2. Direct current electric furnace for melting a ferrous raw material and producing a predetermined quantity of molten metal at each casting, said furnace comprising:
 - (a) a vessel having an axis and comprising a bottom constituting a hearth lined with refractory material and having a form of a basin with a raised upper edge, and a cooled substantially cylindrical lateral wall having a bottom connecting to said upper edge of said basin and an upper part which is closed by a detachable cover for introducing a charge of raw material to be melted;
 - (b) at least one consumable electrode which is mounted to slide substantially along said axis of said vessel so as to descend vertically into an interior of said vessel by passing through at least one opening provided in said cover and provided with a removable shutter;

- (c) at least one stationary electrode positioned in said hearth;
- (d) at least one source of direct current having two poles connected, respectively, to said at least one consumable and stationary electrodes, said at least one consumable electrode gradually descending in said vessel for melting said raw material and forming a bath of molten metal which collects in said basin up to a level, said bath being covered by a layer of dross;
- (e) said basin having a first opening for pouring said molten metal and a second opening for removing said dross, said basin having a height and a maximum cross-section defining a capacity corresponding to said predetermined quantity of molten metal;
- (f) wherein said lateral wall has a cross-section which is substantially equal to said maximum cross-section of said basin and a height which is so selected that a volume defined by said lateral wall is between six and twelve times said capacity of said basin for allowing said vessel to contain a charge of raw material sufficient to produce, in a single melting operation, said predetermined quantity of molten metal;
- (g) said vessel being associated with additional heating means for introducing hot gases at said bottom of said lateral wall, said hot gases rising at least through an annular region of a charge of said raw material along said lateral wall and escaping through an outlet opening in said cover.

5,590,152

DC ARC FURNACE

Shinobu Nakajima, Matsudo, and Kunji Maebou, Kasukabe, both of Japan, assignors to Ishikawajima-Harima Jukogyo Kabushiki Kaisha, Tokyo, Japan

PCT No. PCT/JP94/00616, § 371 Date Nov. 15, 1994, § 102(e) Date Nov. 15, 1994, PCT Pub. No. WO94/24504, PCT Pub. Date Oct. 27, 1994


PCT Filed Apr. 14, 1994, Ser. No. 331,555

Claims priority, application Japan, Apr. 15, 1993, 5-088802

Int. Cl.⁶ H05B 7/11

U.S. Cl. 373—103

2 Claims



1. A DC arc furnace characterized by comprising a furnace shell with a lower electrode at a bottom thereof, a furnace roof adapted to close an upper portion of said furnace shell, two upper electrodes horizontally spaced apart from each other with a predetermined distance and vertically extending through said furnace roof, lifting devices for vertically moving the upper electrodes independently from each other, upper conductors each connected to the corresponding upper electrode and extending in the direction away from the remainder of the upper electrodes, two lower conductors connected to said lower electrode and each extending in a direction along which the corresponding upper conductor extends and power source circuits each arranged between extension ends of the corresponding upper and lower conductors.

5,590,153

DIGITAL MODEM FOR REDUCING INTERFERENCE IN THE SAME CHANNEL OF ANOTHER SYSTEM

Yutaka Tanaka, and Minoru Honda, both of Tokyo, Japan, assignors to Nippon Hoso Kyokai, Tokyo, Japan

Continuation of Ser. No. 913,449, Jul. 15, 1992, abandoned.


This application Jul. 18, 1994, Ser. No. 277,413

Claims priority, application Japan, Jul. 17, 1991, 3-201172

Int. Cl.⁶ H04B 1/38; H04L 5/16

U.S. Cl. 375—222

2 Claims



1. A digital modem comprising:
- digital thin-out means for dividing an input binary code string, every period of m digits, into at least a first series of 1 digit binary code string and a second series of (m-1) digits binary code string and for converting said first series binary code at 1/m clock rate and said second series binary code at (m-1)/m clock rate to form first and second continuous binary code strings, 1 being unequal to (m-1);
- means for generating first and second intermediate carriers; first and second digital modulators, each modulating, respectively, said first and second intermediate carriers with said first and second continuous binary code strings respectively, said first digital modulator generating a first modulated carrier which is transmitted in a higher frequency band between video and voice carriers in one channel of a conventional television broadcasting system, and said second digital modulator generating a second modulated carrier which is transmitted in a lower frequency band below said video carrier in said one channel of the conventional television broadcasting system to use an idle channel of the conventional system in one area, said channel being the same as one channel of the conventional system used in another area adjacent to said one area, to reduce radio interference therebetween;
- first and second demodulators, each demodulating, respectively, said first and second modulated carriers to reproduce said first and second continuous binary code strings;
- first and second clock rate conversion means, each converting, respectively, a clock rate of said reproduced first and second continuous binary code strings into said first series of 1 digit binary code string and said second series of (m-1) digits binary code string respectively; and
- digital synthesis means for synthesizing said first series of 1 digit binary code string and said second series of (m-1) digits binary code string to produce said input binary code string.

5,590,154

EQUALIZER CIRCUIT AND A METHOD FOR EQUALIZING A CONTINUOUS SIGNAL


William R. Forni, Chandler, and Scott A. Kaylor, Gilbert, both of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Jun. 26, 1995, Ser. No. 494,424

Int. Cl.⁶ H03D 3/22

U.S. Cl. 375—229

19 Claims



1. An equalizer circuit having a continuous time output signal, comprising:
- a finite impulse response filter having a plurality of successive delay nodes coupled for providing a set of delayed signal data and a set of delayed signs of the corresponding set of delayed signal data from a continuous time input signal and having a plurality of multiplier circuits coupled for multiplying the set of delayed signal data with a corresponding set of tap weights, wherein the plurality of successive delay nodes includes a filter circuit having an input terminal and an output terminal and a signum generating circuit having a plurality of input terminals and an output terminal, and each multiplier circuit of the plurality of multiplier circuits has a plurality of input terminals and an output terminal, the input terminal of the filter circuit coupled to a first input terminal of the signum generating circuit and to a first input terminal of a first multiplier circuit of the plurality of multiplier circuits, a second input terminal of the signum generating circuit coupled to receive a reference signal, and the output terminal of the signum generating circuit coupled to the tap weight generation circuit; and
- a tap weight generation circuit coupled for providing the set of tap weights.

5,590,155

EQUIPMENT FOR GENERATING A TRANSMIT SIGNAL FROM FIRST AND SECOND DIGITAL SIGNALS

Akira Yasuda, Tokyo, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Continuation-in-part of Ser. No. 143,064, Oct. 29, 1993. This application Jun. 5, 1995, Ser. No. 461,972


Claims priority, application Japan, Oct. 30, 1992, 4-292306; Jun. 9, 1994, 6-127770

Int. Cl.⁶ H04L 5/12; 23/02

U.S. Cl. 375—261

16 Claims

1. A transmitting equipment comprising:
- signal conversion means for converting a time-series input signal into first and second time-series digital signals;
- signal holding means for dividing the first and second time-series digital signals from said signal conversion means into a plurality of first and second digital signals each consisting of a plurality of bits, holding the plurality of first and second digital signals, and outputting the plurality of first and second digital signals in parallel;
- waveform forming means for outputting a plurality of first and second waveform data items respectively corresponding to the plurality of first and second digital signals output from said signal holding means;



5,590,156

MULTICHANNEL WIDEBAND DIGITAL RECEIVER MAKING USE OF MULTIPLE WIDEBAND TUNERS HAVING INDIVIDUALLY SELECTABLE GAINS TO EXTEND OVERALL SYSTEM DYNAMIC RANGE


Ronald Carney, 916 Flower St., NW., Palm Bay, Fla. 32907

Filed Apr. 22, 1994, Ser. No. 231,262

Int. Cl.⁶ H03K 9/00; H04B 1/06; H04Q 1/00

U.S. Cl. 375—316

25 Claims



1. A basestation for processing signals in a multiple subscriber unit wireless communication system comprising:
- an antenna for receiving signals from a plurality of the subscriber units;
- a power splitter, connected to the antenna, to provide a plurality of power splitter output signals;
- a plurality of gain control means, each one of the gain control means being connected to receive a respective one of the power splitter output signals, and each gain control means

stream, and wherein the encoder outputs a first pulse for each sequential bits of the digital bit stream encoded;

a frequency generator for supplying a stable frequency to the A/D converter and the encoder;

a synchronization circuit receiving the stable frequency from the frequency generator and the first pulse from the encoder and creating a second pulse at a time corresponding to a common multiple of $2n$ and m ;

an error generator, connected to the encoder and the synchronization circuit, for generating an error in a bit in the $(m+r)$ bit encoded bit stream for every occurrence of the second pulse and outputting an error-containing bit stream;

a modulator, connected to the error generator, for modulating an rf carrier with the error-containing bit stream according to a predetermined modulation technique to provide a modulated signal and to allow for low probability of detection of the modulated rf carrier; and

an output port for outputting the modulated signal.

5,590,162

STAND-ALONE POWER SUPPLY ENERGIZED BY DECAY OF RADIOACTIVE ISOTOPE


James H. Terhune, San Jose, and Barry M. Gordon, Monte Sereno, both of Calif., assignors to General Electric Company, San Jose, Calif.

Continuation-in-part of Ser. No. 384,997, Feb. 7, 1995, which is a continuation-in-part of Ser. No. 239,773, May 9, 1994, Pat. No. 5,444,747. This application Jul. 21, 1995, Ser. No. 505,727

Int. Cl.⁶ G21D 7/00

U.S. Cl. 376—320

6 Claims



1. A method for powering an electrical circuit inside a nuclear reactor, comprising the steps of:

installing an electrical circuit inside a nuclear reactor;

selecting an isotopic material which has the property, when placed at a predetermined location within a neutron flux inside the nuclear reactor, or capturing neutrons from the neutron flux and being activated by neutron capture to a radioactive state having a subsequent decay chain during which at least one β -particle is emitted;

constructing a β -battery by placing a metallic collector in relationship to a mass of said selected isotopic material so that β -particles emitted by said selected isotopic material are collected;

placing said β -battery in an unactivated state at said predetermined location within the neutron-flux; and

connecting said β -battery to said electrical circuit.

5,590,163 FREQUENCY DIVIDER CIRCUIT, FREQUENCY SYNTHESIZER COMPRISING SUCH A DIVIDER AND RADIO TELEPHONE COMPRISING SUCH A SYNTHESIZER


Yves Dufour, Sunnyvale, Calif., assignor to U.S. Philips Corporation, New York, N.Y.

Filed May 2, 1995, Ser. No. 432,746

Claims priority, application France, May 4, 1994, 94 05483
Int. Cl.⁶ H03K 23/66

U.S. Cl. 377—110

9 Claims



1. A programmable frequency divider circuit comprising p cascade-connected frequency-dividing cells, where p is an integer greater than one, each of said p cascade-connected frequency-dividing cells representing a division of rank i , all of said p cascade-connected frequency-dividing cells being switchable between a normal divide-by-two mode, and a programmed divide-by-three mode, each of said p cascade-connected frequency-dividing cells comprising:

a first input for receiving an input frequency signal;

a first output for supplying an output frequency signal to be applied to the first input of an immediately following cascade-connected frequency-dividing cell;

a second input for receiving an enable signal for the programmed mode;

a third input for receiving a programming signal; and

a second output for supplying a signal generated in response to the enable signal applied to the second input, wherein said signal at the second output of one of said p cascade-connected frequency-dividing cells is applied to the second input of immediately preceding cascade-connected frequency-dividing cell as an enable signal, characterized in that at least one of said p cascade-connected frequency-dividing cells further comprises an additional input for receiving a signal to disable said at least one cascade-connected frequency-dividing cell.

5,590,164

METHOD AND APPARATUS FOR X-RAY COMPUTED TOMOGRAPHY

Hiroaki Kawai, Tokyo; Kensuke Sekihara, Musashimurayama, and Shinichi Migita, Ryugasaki, all of Japan, assignors to Hitachi Medical Corporation, Tokyo, Japan

Filed Jun. 1, 1995, Ser. No. 456,382

Claims priority, application Japan, Jun. 28, 1994, 6-146332
Int. Cl.⁶ A61B 6/00


U.S. Cl. 378—4

21 Claims

1. An X-ray computed tomography apparatus for reconstructing a distribution of X-ray attenuation coefficient within an object on the basis of projection data derived from a plurality of directions, said X-ray computed tomography apparatus comprising:

an X-ray source for continuously generating X-rays to expose said object thereto;

an arrangement of a plurality of X-ray detector elements disposed on an opposite side of said X-ray source from said object, said X-ray detector elements being arranged with a predetermined arrangement pitch angle to measure X-rays transmitted through said object as projection data;



means for rotating positions of said X-ray source and said arrangement of X-ray detector elements by minute angles;

control means for shifting an X-ray focal spot position of said X-ray source;

a plurality of first temporary holding means respectively connected to said X-ray detector elements, a measured value of X-ray intensity transmitted through said object to be incident on one of said X-ray detector elements being temporarily held in one of said first temporary holding means;

switch means for switching over connection between said X-ray detector elements and said first temporary holding means;

switchover control means for controlling switchover of said switch means;

transfer means for transferring said measured value from said first temporary holding means to interpolation calculating means;

interpolation calculating means for performing interpolation calculations on said projection data including said measured value to generate projection data equivalent to projection data measured by using a measuring system virtually having twice as many X-ray detector elements as said arranged X-ray detector elements;

image reconstruction means for reconstructing the distribution of X-ray attenuation coefficient within the object on the basis of the projection data generated by said interpolation calculating means; and

a memory for holding parameters used for calculations in said interpolation calculating means.

5,590,165

METHOD FOR GENERATING FAT DISTRIBUTION IMAGE BY CT SYSTEM

Makoto Gohno, and Tetsuya Horiuchi, both of Tokyo, Japan, assignors to GE Yokogawa Medical Systems, Limited, Tokyo, Japan

PCT No. PCT/JP93/00696, § 371 Date Nov. 9, 1994, § 102(e) Date Nov. 9, 1994, PCT Pub. No. WO93/24054, PCT Pub. Date Dec. 9, 1993


PCT Filed May 25, 1993, Ser. No. 335,772

Claims priority, application Japan, May 26, 1992, 4-133204
Int. Cl.⁶ A61B 6/03

U.S. Cl. 378—18

2 Claims

1. A method for generating a fat distribution image by a CT system wherein an image of fat distribution is generated from a cross sectional image data via X ray, comprising the steps of a scanning step wherein scanning is effected at least at two different levels of X-ray tube voltage using a phantom containing a sample rod of a fat standard material in addition to plural sample rods with different densities of a bone mineral equivalent material to generate at least two cross sectional image data, a CT number detecting step wherein the CT number of each pixel in the whole region or an objective region of the cross sectional image data is detected as the "CT number of a tissue including fat", ie. α_{wf} , a linear



regression calculating step wherein the CT number of the bone mineral equivalent material is detected in the cross sectional image data following the principle of quantitative measurement of bone mineral mass to calculate a linear regression between the CT number and the density of the bone mineral equivalent material and to define the CT number as the "CT number of a tissue excluding fat", ie. α_{nf} , a fat standard material CT number detecting step wherein the "CT number of the fat standard material", ie. α_{ff} is detected in the cross sectional image data, a soft tissue standard material CT number detecting step wherein the CT number of blood in the cross sectional image data is detected as the "CT number of a soft tissue standard material", ie. α_{st} , a CT number application step wherein "α" in the equation $\alpha = \alpha_{wf} - \alpha_{nf}$ is defined as the variation of the CT number due to fat while "β" in the equation $\alpha = \{\alpha_{ff} - \alpha_{st}\}$ is defined as a fat ratio parameter and the "CT number of a tissue including fat" ie. α_{wf} , etc., is applied to the equation

$$\alpha_{wf} = \alpha_{nf} + \beta \cdot \{\alpha_{ff} - \alpha_{st}\} \quad \text{Equation (A)}$$

a fat ratio parameter calculating step wherein the density of the bone mineral equivalent material and the "CT number of a tissue excluding fat", ie. α_{nf} is deleted in at least two linear regressions calculated at the linear regression calculating step and in at least two equations (A) to be applied at the CT number application step, to calculate the fat ratio parameter β on the basis of the detected CT number of each pixel at the CT number detecting step, and a fat ratio parameter image generation step wherein an image is generated on the basis of the calculated fat ratio parameter β .

5,590,166

MAMMOGRAPHY UNIT

Jarmo Suni, Espoo, and Petri Rantanen, Tuusula, both of Finland, assignors to Instrumentarium Corporation, Finland


Filed Dec. 28, 1995, Ser. No. 579,220

Int. Cl.⁶ A61B 6/04

U.S. Cl. 378—37

6 Claims

1. A mammography unit, comprising a C-arm which is mounted on a turning axle (2) adapted to be vertically (arrow C) movable on an upright column (1) and which is pivotable about the turning axle (2) (arrow D), one leg (3) of said C-arm being provided with an X-ray tube (4) and the opposite leg (5) with an image receptor, and said unit further comprising a compression element (6) for compressing the breast to be imaged against the image receptor, said C-arm being further adapted to move linearly (arrow A) in substantially radial directions in the direction transverse to the turning axle (2), in which unit the compression element (6) is mounted on the C-arm and travels essentially linearly relative to the C-arm lengthwise of the C-arm and simultaneously with the



C-arm radially relative to the turning axle, said unit comprising elements for controlling the linear motorized movement of the C-arm (arrow A) and the relative compressive movement of the compression element (6) (arrow B) to occur simultaneously at a substantially equal but oppositely directed speed for compressing the breast between the compression element and the image receptor.

5,590,167


DIGITAL PANORAMIC X-RAY IMAGING APPARATUS
Yoshinori Arai, Tokyo, Japan, assignor to J. Morita Manufacturing Corporation, Kyoto, Japan

Filed Mar. 7, 1996, Ser. No. 613,383

Claims priority, application Japan, Mar. 10, 1995, 7-051106; Feb. 29, 1996, 8-042952

Int. Cl.⁶ A61B 6/14

U.S. Cl. 378—38



1. A digital panoramic X-ray imaging apparatus for performing tomographic imaging along a predetermined tomographic plane of a subject, said apparatus comprising:
an X-ray generator for irradiating a subject with X-rays;
an X-ray imaging device for detecting an image of X-rays having passed through the subject; and
a swivel member for supporting the X-ray generator and the X-ray imaging device and for rotating the X-ray generator around the subject;
wherein the X-ray imaging device comprises a rotation drum disposed in parallel with a rotation shaft of the swivel member, a storage fluorescent sheet disposed on the circumferential surface of the rotation drum, an excitation light source for irradiating the storage fluorescent sheet with excitation light, a light receiving portion for receiving accelerated-phosphorescence emission generated from storage fluorescent sheet by excitation light irradiation, a rotation drive portion for performing primary scanning by rotating the rotation drum, and a linear drive portion for performing secondary scanning by moving the excitation light source and the light-receiving portion in the axial direction of the rotation drum.

5,590,168

X-RAY MICROSCOPE

Yoshinori Iketaki, Oume, Japan, assignor to Olympus Optical Co., Ltd., Tokyo, Japan


Division of Ser. No. 171,719, Dec. 22, 1993, Pat. No. 5,450,463. This application Jun. 6, 1995, Ser. No. 466,973

Claims priority, application Japan, Dec. 25, 1992, 4-347051; Dec. 25, 1992, 4-347083; Mar. 1, 1993, 5-040012; Mar. 2, 1993, 5-041219; Mar. 11, 1993, 5-050873; Mar. 12, 1993, 5-052269; Mar. 12, 1993, 5-052410

Int. Cl.⁶ G21K 7/00

U.S. Cl. 378—43

1 Claim



1. In an X-ray microscope in which a specimen is irradiated with X-rays having a wave length region of 65 to 43.7 Å and ultraviolet rays and X-rays transmitted through the specimen are received by an X-ray detector to form a transmitted X-ray microscopic image of the specimen, the improvement being characterized in that a ultraviolet transmissive window is provided in a wall of a vacuum chamber in which an X-ray optical system of the X-ray microscope is arranged and the ultraviolet rays are made incident upon the specimen through said window as a converged or parallel ultraviolet beam.

5,590,169

RADIATION IMAGING SYSTEM


Sergio L. P. Monteiro, 15166F Campus Park Dr., Moorpark, Calif. 93021

Filed Jan. 9, 1995, Ser. No. 369,802

Int. Cl.⁶ G01N 23/01

U.S. Cl. 378—87

6 Claims



1. A radiation imaging system for producing images of a scanned object comprising:
a radiation source for applying, to at least one point of the object, a collimated radiation beam extending in an incident direction;
detector means for producing a first electrical signal having a first value representing the energy of the portion of said beam that transmits through the object along the incident direction and a second electrical signal representing the energy of the scattered portion of said beam scattered from the incident direction by the object;

information processing means for receiving said first and second electrical signals and displaying a visual representation of the point of the object by using a combination of the information content of said first and second electrical signals;

a scanner assembly for moving said beam in a scanning pattern throughout a surface zone of the object and said source applying said beam intermittently throughout the surface zone and said detector means producing first and second electrical signals for each point representing respectively the energy level of the incident beam transmitted portion and energy level of the scattered beam portion;

wherein said detection means comprises a detector array of individual detectors arranged generally in a plane oriented generally perpendicular to the incident direction of said beam and a positioning means for maintaining the more centrally located detectors at a position to intercept the beam incident direction as the scanner moves the incident beam in a scanning pattern;

wherein said first electrical signal has a value representative of the outputs of the more centrally located detectors and said second signal has a value representative of the combined outputs of the other than centrally located detectors; and wherein said more centrally located detectors have a smaller detection area than that of said other than centrally located detectors.

5,590,170

X-RAY INSPECTION SYSTEM


Gilbert Zweig, Morris Plains, N.J., assignor to Glenbrook Technologies, Morris Plains, N.J.

Continuation-in-part of Ser. No. 46,604, Apr. 12, 1993, abandoned. This application Oct. 25, 1994, Ser. No. 328,465

Int. Cl.⁶ G01N 23/04

U.S. Cl. 378—63

3 Claims



1. An X-ray inspection system for electronic components including printed circuit boards comprising:
X-ray means for generating an X-ray beam for producing an X-ray image of an object, said object being said electronic component;

fluoroscopic imaging means for converting said X-ray image of said object to a fluoroscopic image, said fluoroscopic imaging means includes a thin luminescent phosphor means optically coupled to a microchannel plate image intensifier for providing a substantially high resolution fluoroscopic X-ray image of said object;

a first mirror positioned between said object and said X-ray means at an angle A_1 , said mirror creating an optical image of said predetermined location of said object, said mirror being formed of a composition having at least one element with an atomic number of less than 14, said X-ray beam passes through said first mirror to said object and onto said fluoroscopic imaging means, said mirror being relatively transparent to said X-ray beam.

5,590,171

METHOD AND APPARATUS FOR COMMUNICATIONS MONITORING

Wayne Howe, Alpharetta, and Dale Malik, Dunwoody, both of Ga., assignors to BellSouth Corporation, Atlanta, Ga.


Continuation of Ser. No. 271,191, Jul. 7, 1994, abandoned.

This application Aug. 21, 1995, Ser. No. 517,648

Int. Cl.⁶ H04M 1/24; 3/08; 3/22

U.S. Cl. 379—33

22 Claims




1. In an intelligent switched telephone network, a method for allowing a communication in said intelligent switched telephone network from a calling party to a called party to be monitored by a monitoring party through said intelligent switched telephone network, regardless of the respective locations of said calling party, said called party or said monitoring party, comprising the steps of:
receiving said communication in said intelligent switched telephone network;
reading identification information associated with said communication for a calling line or called party number;
searching for a matching entry to said calling line or called party number in a monitoring list maintained by said intelligent switched telephone network, said searching being conducted to determine whether communications to or from said calling line or called party number are to be monitored;
routing said communication through said intelligent switched telephone network from said calling party to said called party; and
only in response to finding said matching entry, establishing a bridge from said communication to said monitoring party, said bridge allowing said monitoring party to monitor said communication through said intelligent switched telephone network regardless of the respective locations of said calling party, said called party or said monitoring party.

5,590,172
METHOD AND SYSTEM FOR TRANSFERRING A
RADIOTELEPHONE CALL FROM ONE COVERAGE
AREA TO ANOTHER

John P. Ludwig, Naperville; Kenneth A. Felix, Crystal Lake, both of Ill., and Charles L. Whittington, Colleyville, Tex., assignors to Motorola, Inc., Schaumburg, Ill.

U.S. Cl. 379—58

9 Claims



1. A method of transferring a user message-conveying radiotelephone call by a subscriber unit from a first radio coverage area, served by a first fixed control unit which is coupled to a wireline telephone switch, to a second radio coverage area served by a second fixed control unit, the method comprising the steps of:

- transmitting a directory number, associated with the first fixed control unit and the wireline telephone switch, the directory number identifying a wireline telephone number of the first fixed control unit, from the first fixed control unit to the subscriber unit;
- storing the transmitted directory number at the subscriber unit;
- transmitting the stored directory number from the subscriber unit to the second fixed control unit when a need for transfer of the radiotelephone call to the second fixed control unit from the first fixed control unit is determined;
- dialing the transmitted directory number from the second fixed control unit;
- in response to the dialing of the directory number, connecting the second fixed control unit to the first fixed control unit via the wireline telephone switch; and
- transferring control of the radiotelephone call from the first fixed control unit to the second fixed control unit by dialing the transmitted directory number from the second fixed control unit.

5,590,173
**DELAY INSENSITIVE BASE STATION-TO-HANDSET
 INTERFACE FOR RADIO TELEPHONE SYSTEMS**


Andrew S. Beasley, Box 38, Lake Errock, B.C., Canada
Continuation of Ser. No. 357,065, Dec. 14, 1994, abandoned,
which is a continuation of Ser. No. 924,904, Aug. 5, 1992,
abandoned. This application Aug. 22, 1995, Ser. No. 517,608
Int. Cl.⁶ H04Q 7/20

U.S. Cl. 379—58

7 Claims

1. A method of exchanging telephone signals between a basestation and a mobile cordless time division duplex (TDD) handset, comprising the steps of:

- passing transmit signals as frequency division duplex (FDD) signals from said basestation to a remote antenna driver;
- converting said transmit signals to time division duplex (TDD) signals at said remote antenna driver;
- broadcasting said time division duplex signals to said handset;
- receiving at said remote antenna driver TDD receive signals broadcast by said handset, said TDD receive signals including bit clock timing;



converting said TDD receive signals to FDD receive signals at said remote antenna driver;
passing said FDD receive signals to said base station; and
deriving bit clock timing from said FDD receive signals at said base station and employing said bit clock timing to process said FDD receive signals.

5,590,174

APPARATUS AND METHOD FOR MOBILE
COMMUNICATION NETWORK WHICH ENSURES THAT
A USER WHO IS OUT OF A SERVICE AREA CAN
RECEIVE AN INCOMING CALL FROM ANOTHER
SERVICE AREA


Toshiya Tsuji, and Masahiko Yahagi, both of Tokyo, Japan,
assignors to NEC Corporation, Tokyo, Japan

Filed Nov. 14, 1994, Ser. No. 340,374

Claims priority, application Japan, Dec. 17, 1993, 5-318336
Int. Cl.⁶ H04Q 7/38

U.S. Cl. 379—58

11 Claims



1. An apparatus for providing mobile communication in association with a public fixed communication network and a subscriber communication system by a fixed terminal device connected in said public fixed communication network, said apparatus comprising:

a plurality of base stations for providing a first service area for radio communication with a mobile terminal device and a first portable device operating within said first service area;

a terminal device switching means operating in association with said public fixed communication network for controlling call processing of calls of said mobile terminal device, and having a database on which location information of said mobile terminal device are registered; and

a network terminal fixed device operating in association with said public fixed communication network for providing a second service area for radio communication with a second portable device within said second service area;

wherein said first portable device is integrally provided with:

a call circuit, providing an equivalent function to said second portable device for radio communication with said network terminal fixed device, said call circuit including:

5,590,175
METHOD AND SYSTEM FOR ENHANCED CALL
COMPLETION IN TELECOMMUNICATIONS MOBILITY
APPLICATIONS


John K. Gallant, and Steven R. Donovan, both of Plano, Tex., assignors to MCI Communications Corporation, Washington, D.C.

Filed May 17, 1995, Ser. No. 443,185

Int. Cl.⁶ H04O 7/22

U.S. Cl. 379—58

4 Claims



1 A method of directing calls from a public switch telephone network to a mobile station within a mobile telephone network, the mobile telephone network including a plurality of mobile telephone stations, a plurality of base stations for communicating with the mobile telephone stations, a plurality of mobile services switching centers for routing calls between base stations and between base stations and the public switch telephone network, a plurality of visitor location registers for storing data relating to visiting mobile telephone stations, and at least one home location register for storing all management data relating to all mobile telephone stations in the mobile telephone network, the method comprising the steps of:

- receiving a call directed to a mobile telephone station from a public switch telephone network in a mobile services switching center;
- attempting to locate a profile of the mobile telephone station in a visitor location register, the profile having an HLR query flag for indicating whether the home location register should be queried;
- checking a status of the HLR query flag, if the profile of the mobile telephone station is located in the visitor location register;
- sending a query message to a home location register requesting routing information for the call, if the HLR query flag is set to yes;
- completing the call to the mobile telephone station using the profile in the visitor location register, if the HLR query flag is set to no;
- sending a query message to the home location register requesting routing information for the call, if the mobile telephone profile is not found in the visitor location register; and


5,590,176
ARRANGEMENT FOR LOCAL TRUNK HUNTING IN A
DISTRIBUTED SWITCHING SYSTEM

Anjana Agarwal, Wheaton, and Chinmei C. Lee, Woodridge, both of Ill., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Continuation of Ser. No. 114,020, Aug. 30, 1993, abandoned.
This application Jun. 22, 1995, Ser. No. 493,779

U.S. Cl. 379—59


12 Claims



1. A switching system having a distributed architecture including a centralized processor, a communication module and a plurality of switching modules with each of the switching modules having a local processor and a subgroup of trunks connecting to another switching system, comprising:

- means for receiving a trunk request for a destination at one local processor of one of the plurality of switching modules;
- means for interrogating a trunk subgroup availability bitmap in said local processor to determine if a trunk of the trunk subgroup can fulfill the trunk request and if such a trunk of the trunk subgroup is available;
- means for assigning the available trunk to the requesting station if a trunk of the subgroup that fulfills the trunk request is available;
- means for requesting an alternate one of the plurality of switching modules to assign an alternate trunk on an alternate local processor from the centralized processor if a trunk of the subgroup that fulfills the trunk request is not available;
- means for fulfilling the trunk request by a trunk from the trunk subgroup of the alternate switching module;
- means for storing a plurality of at least three trunk loading statuses in each trunk subgroup availability bitmap for each switching module in the centralized processor; and
- wherein said centralized processor has an trunk subgroup availability bitmap that is updated by each switching module if a threshold of one of a plurality of trunk loading statuses of its respective switching module is exceeded.

5,590,177
METHOD FOR PREVENTING A DROPPED CALL DURING A HANDOFF IN A RADIOTELEPHONE SYSTEM
 Richard J. Vilmur, Palatine, and Eugene J. Bruckert, Arlington Heights, both of Ill., assignors to Motorola, Inc., Schaumburg, Ill.
 Filed Sep. 30, 1994, Ser. No. 316,697
 Int. Cl.⁶ H04Q 7/22; H04J 13/02
 U.S. Cl. 379—60 22 Claims




1. In a cellular radiotelephone communication system including at least one switch controller, a plurality of base stations including first and second base stations, and at least one mobile station, wherein a switch controller is coupled to the first and second base stations to provide radiotelephone communication throughout first and second coverage areas, respectively, wherein a mobile station is in an active call in the first coverage area with the first base station on a first traffic channel and substantially shadowed from transmissions from the second base station in the second coverage area, a method, performed by the mobile station, for preventing the active call from being dropped when the mobile station suddenly transitions from the first coverage area to the second coverage area, the method comprising the steps of:

- determining that the active call is in danger of being dropped responsive to the mobile station suddenly transitioning from the first coverage area to the second coverage area;
- notifying the first base station that the active call is in danger of being dropped responsive to the step of determining that the active call is in danger of being dropped;
- determining that the active call with the first base station is in the process of being dropped responsive to the step of notifying the first base station that the active call is in danger of being dropped; and
- establishing the active call with the second base station in the second coverage area before the active call with the first base station is dropped responsive to the step of determining that the active call with the first base station is in the process of being dropped.

5,590,178
ELECTRONIC MAIL SYSTEM LINKED WITH TELEPHONE
 Masahiko Murakami, Masahiro Matsuda, and Noriyuki Fukuyama, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kanagawa, Japan
 Filed Jun. 27, 1994, Ser. No. 266,225
 Claims priority, application Japan, Sep. 28, 1993, 5-241556
 Int. Cl.⁶ H04M 11/00; H04N 7/14
 U.S. Cl. 379—96 54 Claims

1. An electronic mail system linked with a telephone system, comprising:



an electronic mail system composed of a plurality of terminals connected through a network, and an electronic mail center via which electronic mail is exchanged among users of said terminals; and

a telephone system composed of a plurality of telephones and a telephone exchange for connecting said telephones, wherein

said telephones are associated in advance with individual users of said electronic mail system,

said electronic mail center comprises:

- correspondence table storing means for storing a table of correspondence between user IDs and telephone numbers as well as electronic mail for individual users;
- a terminal interface for identifying the users using said terminals; and
- status variable managing means for managing status variables by which to recognize the mail each individual user is currently reading,


said telephone exchange, upon reception of a call request, notifies the calling telephone number to said electronic mail center, and

said electronic mail center identifies the user ID of the calling user corresponding to the notified telephone number by referencing said correspondence table, and transmits, upon connection of the call, electronic mail messages or lists of electronic mail messages associated with the calling user to the login terminal of the calling user, the electronic mail messages or the lists of electronic mail messages thus transmitted being displayed on said login terminal of the calling user.

5,590,179
REMOTE AUTOMATIC METER READING APPARATUS
 John T. Shincovich, North Canton; Jan K. Michalek; Norman C. Baldwin, both of Newark; Ebrahim Shahrodi, Delaware, all of Ohio; Darrell Robinson, Highland, Mich.; Allen V. Pruehs, Howell, Mich., and Robert O. Learmont, Walled Lake, Mich., assignors to Ekstrom Industries, Inc., Farmington Hills, Mich.
 Continuation of Ser. No. 17,650, Feb. 12, 1993, abandoned.
 This application Mar. 8, 1995, Ser. No. 400,495
 Int. Cl.⁶ H04M 11/00 12 Claims

1. A remote metering system, including a central computer and a plurality of digital meters installed at locations remote from said central computer, said central computer including communicating means for remotely communicating with each of said plurality of digital meters, each of said plurality of digital meters including:

- a current sensing circuit and voltage sensing circuit for sensing current and voltage, respectively, of electricity passing through said meter and producing current and voltage signals indicative of a magnitude sensed current and voltage;




an analog-to-digital converter, responsive to said current and voltage signals, for producing a plurality of digital signals at predetermined time intervals indicative of said sensed current and voltage;

processing means, responsive to said plurality of digital signals, for calculating an amount of electrical power passing through said meter and producing consumption signals indicative of consumed power for each predetermined time interval;

memory means, responsive to said processing means, for storing data indicative of said consumed power; and

power outage detection means, responsive to said voltage sensing circuit, for detecting a power outage condition and storing outage data indicative of said power outage condition in said memory means, wherein said power outage detection means includes outage type determination means for determining if said power outage condition is one of a first type power outage condition and a second type power outage condition, wherein said power outage detection means includes means for disabling operation of said meter responsive to a determination that said power outage condition is a first type power outage condition.

5,590,180
COMMUNICATION METHOD OF SUPPLYING INFORMATION IN INTELLIGENT NETWORK AND APPARATUS THEREFOR
 Yukiko Tonomura; Yoshito Sakurai, both of Yokohama, and Yumiko Nishi, Tokyo, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
 Filed Sep. 28, 1994, Ser. No. 314,373
 Claims priority, application Japan, Sep. 30, 1993, 5-244252
 Int. Cl.⁶ H04M 15/00 11 Claims



1. A communication method for providing information in an intelligent network including a transmission layer having a user terminal and a switching system connected through a first network and an intelligent layer connected to said transmission layer through a second network for issuing a connection command of a line to said transmission layer, comprising the steps of:

- entering by a user a connection number of the user terminal, a connection number of an information provider terminal and a

time to receive an information providing service into a user database provided in said transmission layer;

reading data registered in said user database into a service control database provided in said intelligent layer;


collating a current time with the time to receive the information providing service read in said service control database by a timer circuit provided in said intelligent layer;

automatically connecting said user terminal to said information provider terminal when a service start time is reached as a result of the collation;

collating a current time with a service end time by said timer circuit; and

automatically disconnecting the connection between said user terminal and said information provider terminal when the service end time is reached as a result of the collation.

5,590,181
CALL-PROCESSING SYSTEM AND METHOD
 Steven J. Hogan; Kristi T. Feltz; Douglas R. Murdock; Todd A. Goodman; David J. Vercande; Michael R. Tangeman; Eric M. Busch; Raghavan Kripakaran; Madhigubba G. Jayasimha; Keith E. Smith; Mark A. Austin, and Dana B. Berry, all of Cedar Rapids, Iowa, assignors to Link USA Corporation, Cedar Rapids, Iowa
 Filed Oct. 15, 1993, Ser. No. 136,211
 Int. Cl.⁶ H04M 15/00; 7/00 23 Claims



1. A call-processing system for processing a telephone call comprising call audio and call data, wherein the call audio of the telephone call is routed to a destination by a matrix switch that includes a matrix switch processor, the call-processing system comprising:

- a network control processor that provides an interface between the matrix switch and a common channel signaling network, said network control processor comprising:
- means for receiving the call data for the telephone call, that is intended for the matrix switch, from said common channel signaling network,
- means for determining a routing for the call audio of the telephone call,
- means for sending switch control data to the matrix switch processor of the matrix switch to effect said routing of the call audio of the telephone call, and
- means for sending operator control data to an operator console connected to the matrix switch via a connection between said network control processor and said operator console to support a telephone call that requires operator assistance.

5,590,182

SYSTEM FOR INTERCEPTION AND TRANSMISSION OF COMMUNICATION SIGNALS ON TELEPHONE AND DATA LINES


Jessica L. Stevens, and Bonnie Crystal, both of Foster City, Calif., assignors to Telegen Corporation, Foster City, Calif.

Filed Jun. 22, 1994, Ser. No. 264,041

Int. Cl.⁶ H04M 1/50

U.S. Cl. 379—130

60 Claims



1. An apparatus for intercepting a signal carried on a telephone line that links a signal transmitter to a signal receiver, the signal receiver having signal detection filters with predetermined passbands and having valid signal decoder ranges, the apparatus comprising:

a waveform generating means for producing an interfering signal having a component frequency that is inside the passbands of the signal detection filters but outside the valid signal decoder ranges, so that a substantial portion of the interfering signal passes through at least one of the filters and has an amplitude above a predetermined noise threshold; and
a coupling means for introducing the interfering signal into the telephone line while the signal is carried on the line;
whereby the portion of the interfering signal which passes through one of the filters is interpreted by the signal receiver as noise, and causes the signal to be not recognized by the signal receiver.

5,590,183

KEEP CALL BACK DEVICE

Norihito Yoneda; Toshimitsu Obba; Reiko Furuya, and Kiyotaka Shikata, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kanagawa, Japan

Filed Nov. 18, 1994, Ser. No. 342,245

Claims priority, application Japan, Mar. 18, 1994, 6-087120


Int. Cl.⁶ H04M 1/56; 1/50; 3/42

U.S. Cl. 379—142

9 Claims

1. A keep call back device for use in telephone communication between subscribers, the keep call back device comprising:

a first call establishing means for establishing a first call by establishing a call received from a calling terminal to a called terminal, wherein the calling terminal can respond to a call from one terminal without ending communication with another terminal during communication with said another terminal;
a second call establishing means for establishing a second call by placing a call to said calling terminal after said first call has been established and for connecting said second call between said calling terminal and said called terminal if said calling terminal responds to the call from the one terminal; and
a call releasing means for releasing said first call by disconnecting said first terminal when said second call is established.



5,590,184

COMMUNICATIONS PRIVACY PROTECTION SYSTEM BY REPLACING CALLING PARTY NUMBER WITH NON-ASSIGNED NUMBER


Thomas B. London, Tinton Falls, N.J., assignor to Lucent Technologies Inc., Murray Hill, N.J.

Filed Mar. 3, 1995, Ser. No. 398,251

Int. Cl.⁶ H04M 1/56; 1/50; 3/42; 3/00

U.S. Cl. 379—142

22 Claims



15. A system for providing a communications service to a caller, said system comprising:
means for receiving source information which includes a calling party number associated with said call; and
means for replacing said calling party number with a selected non-assigned telephone number.

5,590,185

MULTIPLE PHONE LINE ADAPTOR

Harold Sandler, 18607 Acetuno St., San Diego, Calif. 92128, and Kendy Ip, Rm D, G/F, BLK 6, The Eldorado, Tong Yan San Tsuen, Yuen Long, Hong Kong


Filed Mar. 25, 1995, Ser. No. 409,225

Int. Cl.⁶ H04M 1/00

U.S. Cl. 379—163

14 Claims

1. A multiple line phone adaptor for connection of at least two separate phone lines to a single line phone comprising:
first and second ring detector means for connection respectively to first and second phone lines,
micro controller means connected to said first and second ring detector means,
first and second hold means connected respectively to said first and second phone lines and each hold means connected to said micro controller means;



electronic line selector means for connection to said first and second phone lines, said selector means being connected to said micro controller means and said micro controller means controlling the selection of said first and second phone lines; off hook detector means for detecting when said single line phone is taken off the hook, and
DTMF decoder means connected to said micro controller means and for connection to said single line phone for decoding DTMF command signals from said single line phone.

5,590,186

SYSTEM AND METHOD FOR REDIRECTING A TELEPHONE CALL WITH CALL MERGING


Frank Y. Liao, Howell; Antoinette Rule, Trenton; Rise J. Frankel, Somerset; Thomas W. Blickle, Keyport, all of N.J., and Sandra L. Bish, Thornton, Colo., assignors to AT & T, Holmdel, N.J.

Filed Dec. 22, 1993, Ser. No. 172,374

Int. Cl.⁶ H04M 3/42; 11/04

U.S. Cl. 379—210

39 Claims



11. A system for completing telephone calls comprising means including a switch having an associated adjunct processor for routing a call from a calling party at a customer location to a redirecting party at a primary location,
a voice response unit (VRU) positioned at said primary location and including means for receiving and processing dual tone multifrequency (DTMF) instruction signals,
means in said adjunct processor for monitoring the call after it has been completed to said primary location for a redirection signal indicative to forward said call to an alternate destination,
means in said adjunct processor for routing said call from said calling party to said primary location, and including means in said adjunct processor for transmitting to said voice response unit a series of dual tone multifrequency signals indicating the results of the attempted transfer to an alternate destination, so as to enable further, predetermined processing of said call such as transfer to a second alternate location, and including

means for releasing said call legs to and from said adjunct processor while merging said call legs within said switch so as to conserve adjunct processor resources for further incoming calls.

5,590,187

CALL TRANSFER WITH AUTOMATIC RETURN

Steven L. Greenspan, Oak Park, Ill., assignor to Lucent Technologies Inc., Murray Hill, N.J.


Continuation of Ser. No. 994,566, Dec. 21, 1992, abandoned.

This application Apr. 21, 1995, Ser. No. 427,636

Int. Cl.⁶ H04M 3/58

U.S. Cl. 379—212

22 Claims



2. A call processing method comprising:
establishing a connection from a first station to a second station, said connection includes a two way voice communication path between said first station and said second station,
establishing a connection from one of said first and second stations to a third station, said connection includes a two way voice communication path between said one station and said third station, where said one station is for a subscriber to a transfer-with-return feature,
invoking said feature at said one station which establishes a connection between the other of said first and second stations and said third station, said connection includes a two way voice communication path between said other of said first and second stations and said third station,
disconnecting said one station from said connections thereby effecting a call transfer from said one station to said third station, and
automatically establishing a return call connection to said one station in response to a prespecified event occurring at said other station or said third station and without receiving a dialed number for said one station.

5,590,188

RULES-BASED CALL ROUTING

Gary B. Crockett, Plano, Tex., assignor to IEX Corporation, Richardson, Tex.

Continuation of Ser. No. 973,034, Nov. 9, 1992, abandoned.

This application Feb. 17, 1995, Ser. No. 390,934


Int. Cl.⁶ H04M 7/00

U.S. Cl. 379—225

7 Claims

1. A method, using a call processor, for selecting which call center among a plurality of call centers in a telephone network is to receive an incoming telephone call, comprising the steps of:
generating a routing plan comprising a set of rules, one or more rules in the set of rules having a conditions portion and an

using a first selector controlled by said key signal to select between said first and second color components;
 using a second selector controlled by said key signal to select between said first and second color components, wherein said first selector and said second selector select opposite signals from said first and second color component signals;
 coupling said luminance component signal, an output of said first selector and an output of said second selector respectively to a luminance input, a first color input and a second color input of an encoder, thus producing a scrambled color output; and
 coupling said key signal to said encoder to combine said key signal said signal with said key signal.



5,590,195


INFORMATION DISSEMINATION USING VARIOUS TRANSMISSION MODES

John O. Ryan, Cupertino, Calif., assignor to Command Audio Corporation, Sunnyvale, Calif.

Continuation-in-part of Ser. No. 31,763, Mar. 15, 1993, Pat. No. 5,406,626. This application Jan. 12, 1994, Ser. No. 181,394
 Int. Cl.⁶ H04L 9/00; H04B 1/06

U.S. Cl. 380—9

43 Claims



36. A system for information dissemination to transmit audio data comprising:
 a data producing sub-system for converting analog audio information to digital data and a database with menus;
 a data compressor for compressing the encrypted audio data; and
 an encryptor for encrypting the digital audio data;
 a means for inserting the compressed encrypted digital audio data into a transmission channel;
 a tuner means for receiving the transmitted compressed encrypted digital audio data;
 a memory means for storing the selected data in the database;
 a means for providing a set of menus to a user describing the database, and a means for updating the data in the database;
 a controller means for selecting data from the database in response to the accepted selections and providing the selected data in the encrypted compressed digital form; and
 a decrypting means for decrypting the encrypted compressed digital audio data;
 a decompressing means for decompressing the compressed digital audio data; and
 a means for converting the digital audio data to analog audio data representing the audio originally transmitted.

5,590,196

SECURE PAYMENT METHOD USING FACSIMILE

Thierry Moreau, Montreal, Canada, assignor to Connotech Experts Conseils Inc., Montreal, Canada

Filed Oct. 6, 1994, Ser. No. 319,041

Int. Cl.⁶ H04L 9/00; 9/32

U.S. Cl. 380—18

23 Claims

1. A method for transferring economic value from a payer to a payee comprising the steps of:

- preparing a value transfer form including information for identifying a specific value to be transferred, a financial institution of the payee and an account number of the payee;
- receiving and verifying a security code at an encryption unit to authorize a transmission including a cryptographic processing result;
- preparing a facsimile transmission device to send an image of the value transfer form;
- connecting the facsimile device through the encryption unit over a communication channel to a value transfer service provider;
- sending said image of the value transfer form in said transmission;
- receiving at the value transfer service provider said transmission including said cryptographic processing result;
- sending a confirmation message to said facsimile device that said transmission has been correctly received;
- decrypting the cryptographic processing result at the value transfer service provider;
- determining whether the cryptographic processing result was authentically generated by the payer;
- extracting said identifying information from the facsimile transmission; and
- generating an electronic value transfer transaction based on said identifying information provided that the cryptographic processing result is determined to be authentic in step (i).

5,590,197

ELECTRONIC PAYMENT SYSTEM AND METHOD


James F. Chen, and Jieh-Shan Wang, both of Potomac, Md., assignors to V-ONE Corporation, Rockville, Md.

Filed Apr. 4, 1995, Ser. No. 416,045

Int. Cl.⁶ H04L 9/00


U.S. Cl. 380—24

12 Claims



1. An electronic payment system, comprising:
 storage means for storing sensitive account information, at least one browser program, and a public key file, said at least one browser program constituting a means for enabling communications with at least one merchant over an open computer network, and said public key file including means for selecting the public key of a private-public key cryptosystem and for encrypting the sensitive information using the public key to generate an authorization ticket;

means possessed by a merchant in communication with the storage means for receiving said authorization ticket from the storage means and forwarding it to a secured account processor;
 means in the account processor including a private key for decrypting the authorization ticket and informing the merchant whether a transaction is authorized.



at least one workstation in communication with a network; and a removable, personally protectable coprocessor adapted to communicate with the workstation,
 the coprocessor adapted to receive user-provided initialization information from the workstation,
 the coprocessor adapted to receive signals including first encrypted authentication information from the workstation, the coprocessor including a preselected first key to decrypt the first encrypted authentication information, the coprocessor further programmed to assemble second authentication information using at least one of (i) a key contained within the first encrypted authentication information and (ii) a preselected second key and to send the second encrypted authentication information to the network via the workstation,
 whereby the user is authenticated to access the networked computer or service.

5,590,200

APPARATUS AND METHOD FOR SECURING COMMUNICATION SYSTEMS

Jacob B. Nachman, Ramat Modiim, and Yossef Tsuria, Jerusalem, both of Israel, assignors to News Datacom Ltd., London, England


Filed Sep. 21, 1994, Ser. No. 309,807

Claims priority, application Israel, Dec. 9, 1993, 107967

Int. Cl.⁶ H04L 9/14; 9/26

U.S. Cl. 380—46

29 Claims



5. A hacking prevention method for use with a network including a transmitter which transmits information to a multiplicity of subscriber units, wherein each of the multiplicity of subscriber units is independently enabled by a descrambling secret number, and when enabled is responsive to data received from the transmitter for descrambling scrambled information, the method comprising the steps of:
 receiving a data stream including a series of authorization packets, and a series of offset values, wherein each offset value in

5,590,198

OPEN METERING SYSTEM WITH SUPER PASSWORD VAULT ACCESS


David K. Lee, Monroe, and David W. Riley, Easton, both of Conn., assignors to Pitney Bowes Inc., Stamford, Conn.

Filed Dec. 19, 1995, Ser. No. 574,749

Int. Cl.⁶ H04L 9/00

U.S. Cl. 380—21

10 Claims



1. A method of reinitializing a user password system in a transaction evidencing device, the method comprising the steps of:
 sharing secret data in the transaction evidencing device and in a database at a data center for performing secure communications therebetween, the secret data including at least two counters and an encryption key;
 requesting for the transaction evidencing device a super password from the data center;
 authenticating at the data center the transaction evidencing device requesting the super password;
 issuing a super password from the data center for the authenticated transaction evidencing device;
 entering the super password into the transaction evidencing device;
 authenticating in the transaction evidencing device the super password entered in the transaction evidencing device; and
 resetting the user password in the transaction evidencing device upon verification of the authenticity of the super password.

5,590,199

ELECTRONIC INFORMATION NETWORK USER AUTHENTICATION AND AUTHORIZATION SYSTEM

Marjan Krajewski, Jr., Acton; John C. Chipchak, Dracut; David A. Chodorow, Groton; Jonathan T. Trustle, Lexington, and Peter T. Baldwin, Rowley, all of Mass., assignors to The Mitre Corporation, Bedford, Mass.

Filed Oct. 12, 1993, Ser. No. 134,399

Int. Cl.⁶ H04L 9/32; 9/08

U.S. Cl. 380—25

4 Claims


1. A system for authenticating a user to any service or computer on a heterogenous computer network comprising:

said series of offset values is paired with a corresponding authorization packet in said series of authorization packets; generating a random number integer in the range between one and the total number of packets in said series of authorization packets; providing a selected packet, wherein said selected packet is a packet having a serial number in the series of authorization packets which is equal to said random number integer; producing a key which uniquely corresponds to said selected packet; and generating a descrambling secret number which is the same for all of said multiplicity of subscriber units by utilizing the key with the offset value which is paired with said selected packet, whereby said key and said selected packet intercepted at a first subscriber unit cannot be effective to enable a second subscriber unit.

5,590,201
PROGRAMMABLE SOURCE ADDRESS LOCKING MECHANISM FOR SECURE NETWORKS
William Lo, Santa Clara, Calif., assignor to Advanced Micro Devices Inc., Sunnyvale, Calif.
Filed Nov. 10, 1994, Ser. No. 337,634
Int. Cl.⁶ H04L 9/00

U.S. Cl. 380—49

5 Claims



1. In a managed repeater having an address learn capability wherein receipt at a particular port of a data packet having a received source address different from a stored source address associated with the particular port replaces the stored source address with the received source address, a source address locking circuit, comprising:


- a learn mode circuit for the particular port, for replacing the stored source address with the received source address when the stored source address does not match the received source address; and
- an address lock register for the particular port, coupled to said learn mode circuit, for storing a bit value to prevent said learn mode circuit from replacing the stored source address with the received source address.

5,590,202
COUNTDOWN SYSTEM FOR CONDITIONAL ACCESS MODULE
Caitlin B. Bestler, Chicago; Harry A. Hartley, III, Palatine, and Khosro M. Rabii, Arlington Heights, all of Ill., assignors to Zenith Electronics Corporation, Glenview, Ill.
Filed Jan. 18, 1995, Ser. No. 375,319
Int. Cl.⁶ H04L 9/00

U.S. Cl. 380—49

13 Claims

1. A conditional access system for a subscriber terminal comprising:
means operable for decrypting a received product packet identified by a PID;
means including a PID register and an associated countdown register for enabling said decrypting means in response to the




value of said received PID matching the value stored in said PID register and said associated countdown register having a value other than a first selected value;
means for decrementing said countdown register each time one of said product packets is decrypted; and
means for setting the countdown register to a second selected value in response to a received CA packet.

5,590,203
PILOT SIGNAL DETECTION CIRCUIT
Toshiya Matsui, Tokyo, Japan, assignor to Nec Corporation, Tokyo, Japan
Filed Sep. 14, 1994, Ser. No. 306,387
Claims priority, application Japan, Sep. 16, 1993, 5-255163
Int. Cl.⁶ H04H 5/00

U.S. Cl. 381—4

10 Claims




1. A pilot signal detection circuit, comprising: extracting means for extracting a carrier of a pilot signal from a received broadcast waves;
reference signal generating means for generating a reference signal having the same frequency as and phase-synchronized with the carrier extracted by the extracting means;
sync-detecting means for sync-detecting the carrier extracted by the extracting means by using the reference signal;
frequency signal generating means for generating a pair of first signals having a frequency assigned for sound multiplex broadcasting and whose phases are different by 90 degrees each other, and a second pair of signals having a frequency assigned for stereophonic broadcasting and whose phases are different by 90 degrees each other;
multiplying means for multiplying a detection signal output from the sync-detecting means by any one of the first pair of signals and the second pair of signals;
squaring means for squaring the output signals from the multiplying means; and
detecting means for detecting the pilot signal in accordance with a sum signal of signals output from the squaring means.

5,590,204
DEVICE FOR REPRODUCING 2-CHANNEL SOUND FIELD AND METHOD THEREFOR
Hee-Soo Lee, Suwon, Rep. of Korea, assignor to Samsung Electronics Co., Ltd., Kyungki-do, Rep. of Korea
Filed Dec. 7, 1992, Ser. No. 987,449
Claims priority, application Rep. of Korea, Dec. 7, 1991, 1991-22376

U.S. Cl. 381—24

6 Claims



2. A sound field reproducing method for a stereo system including a first digital signal processor generating four sound signals, including a first front left sound field signal, a first front right sound field signal, a first rear left sound field signal and a first rear right sound field signal, from two input sound signals, a second digital signal processor combining the four sound signals received from said first digital signal processor into a first channel signal and a second channel signal provided via a stereo amplifier to speakers, said method comprising the steps of:

- adding said first rear left sound field signal to said first rear right sound field signal to generate a second rear right sound field signal, and subtracting said first rear left sound field signal from said first rear right sound field signal to generate a second rear left sound field signal;
- filtering said second rear left sound field signal and said second rear right sound field signal into a third rear left sound field signal and a third rear right sound field signal, respectively, said third rear left sound field signal and said third rear right sound field signal having transfer characteristics;
- adding said third rear left sound field signal to said third rear right sound field signal to generate a fourth rear left sound field signal, and subtracting said third rear left sound field signal from said third rear right sound field signal to generate a fourth rear right sound field signal; and
- adding a level-controlled said first front left sound field signal to said fourth rear left sound field signal to generate said first channel signal, and adding a level-controlled said first front right sound field signal to said fourth rear right sound field signal to generate said second channel signal.


5,590,205
ADAPTIVE CONTROL SYSTEM WITH A CORRECTED-PHASE FILTERED ERROR UPDATE
Steven R. Popovich, Stoughton, Wis., assignor to Digisonix, Inc., Middleton, Wis.
Filed Aug. 25, 1994, Ser. No. 297,241
Int. Cl.⁶ G06F 15/00

U.S. Cl. 381—71

47 Claims

1. An adaptive control system having a system input and a system output, the system comprising:
an adaptive filter that inputs one or more reference signals and one or more error input signals, and outputs one or more correction signals;

174-405 O.G.-96-23: QL3




one or more output transducers, each output transducer inputting one of the correction signals and outputting a control signal that combines with a system input;
one or more error sensors that senses a system output and outputs an error signal;
an error signal filter that inputs each error signal and outputs one or more filtered error signals, wherein the error signal filter includes a delayed Hermitian transpose of a model of an auxiliary path between the output of the adaptive filter and the input of the error signal filter; and
an error signal correlator that inputs each reference signal and each filtered error signal and outputs the one or more error input signals.

5,590,206
NOISE CANCELER
Hyeon-keon An; Young-ho Shin, and Suk-ki Kim, all of Kyungki-do, Rep. of Korea, assignors to Samsung Electronics Co., Ltd., Suwon, Rep. of Korea
Division of Ser. No. 45,011, Apr. 9, 1993, Pat. No. 5,406,149.
This application Oct. 21, 1994, Ser. No. 326,954
Claims priority, application Rep. of Korea, Apr. 9, 1992, 92-5927

U.S. Cl. 381—71

4 Claims




1. A noise canceler, comprising:
a noise detector;
an address sequencer connected to the noise detector;
a memory connected to the address sequencer, said memory storing predetermined inverted digitized noise patterns and regenerating the predetermined inverted digitized noise patterns in response to the address sequencer;
a D/A converter receiving said predetermined inverted digitized noise patterns from the memory and converting said predetermined inverted digitized noise patterns into analog form;
a speaker connected to the D/A converter and generating inverse noise signals.

5,590,207

SOUND REPRODUCING ARRAY PROCESSOR SYSTEM
 Stephen F. Taylor, Pacific Palisades, Calif., assignor to Taylor Group of Companies, Inc., Santa Monica, Calif.
 Continuation-in-part of Ser. No. 166,463, Dec. 14, 1993. This application May 17, 1994, Ser. No. 245,160
 Int. Cl.⁶ H04R 1/02

U.S. Cl. 381—90

21 Claims



1. An acoustical modeling and playback system, comprising:
- (a) a computer comprising: (1) means for modeling acoustical properties of a three dimensional space, (2) means for placing and moving a propagating acoustical energy source in the three dimensional space, (3) means for modeling acoustical characteristics of the propagating acoustical energy source as it is placed and moved in the three dimensional space, (4) means for modeling an intersection of the propagating acoustical energy source with a surface in the three dimensional space, (5) means for translating the modeled acoustical properties, the modeled acoustical characteristics, and the modeled intersection into a plurality of data streams, and (6) means for storing the data streams on a data storage device; and
- (b) a playback system, coupled to the data storage device, the playback system comprising: (1) a plurality of sound pixels, each comprising addressable transducers for generating acoustical energy, (2) means for retrieving at least one data stream from the data storage device, (3) means for transmitting each of the data streams to specific sound pixels, and (4) means for operating the sound pixels as directed by the data streams to recreate the modeled acoustical properties, the modeled acoustical characteristics, and the modeled intersection.

5,590,208
SPEAKER SYSTEM


Shinji Koyano; Koushirou Kogure; Takashi Ohya; Makoto Sakakibara, and Katsutoki Hanayama, all of Saltama-ken, Japan, assignors to Pioneer Electronic Corporation, Tokyo, Japan

Filed Apr. 11, 1995, Ser. No. 419,902
 Claims priority, application Japan, Apr. 18, 1994, 6-079057
 Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—154

6 Claims

1. A speaker system comprising:
 a cabinet,
 a first speaker unit provided within the cabinet; and
 a duct for radiating sound pressure emitted from the first speaker unit,



wherein a drive signal to be applied to the speaker unit is passed through a network circuit means, said network circuit means for eliminating a high frequency component contained in the drive signal;
 wherein the duct extends in a direction perpendicular to a radiating direction of the sound pressure radiated from a front side of the first speaker unit, with one end of the duct being communicated with a space of the cabinet, and another end of the duct forming an opening of the speaker system;
 wherein the first speaker unit is disposed with the front side thereof positioned at a portion of a wall of the duct;
 wherein the duct has a cross section which is perpendicular to a sound propagating direction and has a consistent cross sectional area along an entire length thereof; and
 wherein sound pressure radiated from a rear side of the first speaker unit is propagated in the duct and applied to the sound pressure from the front side of the first speaker unit, and combined sound pressure is discharged outwardly from the duct.


5,590,209
MOUNT FOR SUPPORTING A MICROPHONE ON A HELMET

David S. Pratt, San Jose; Phillip Bourgeois, Woodside; Edward J. Cornelius, III, San Francisco; Chin H. Lee, Palo Alto, and Blaise G. Stollenberg, Oakland, all of Calif., assignors to Setcom Corporation, Mountain View, Calif.

Filed Jul. 22, 1994, Ser. No. 279,282
 Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—168

21 Claims




1. A microphone mount assembly for use with a motorcycle helmet having a hardened outer shell and with a transmission cable carrying electrical conductors, comprising a mount having a front and rear and a front profile which includes opposite inner and outer surfaces, the inner surface having a contour which conforms to the outer shell of the helmet prior to being mounted on said helmet and the outer surface being generally smooth and free of projections, a cylindrical boom member having first and second end portions, a microphone mounted on the first end portion of the boom member, a sleeve-like member extending from the front of the mount in a forward direction within the front profile for receiving the second end portion of the boom member and directing the boom member forwardly so that the microphone is disposed in front of the helmet, receiving means extending from the rear of the mount adapted for receiving the transmission cable and means adapted to secure the mount to the helmet consisting of a layer of an adhesive material

5,590,211
MICROPHONE

Ching-Lu Chang, No. 39, Lane 29, Shih-Chia Rd., Tung Dist., Taichung City, Taiwan
 Filed Jul. 14, 1995, Ser. No. 502,070
 Int. Cl.⁶ H04R 25/00; H05K 5/00
 U.S. Cl. 381—193

4 Claims



1. A microphone comprising:
 a housing having an opening on an upper end thereof;
 a magnet mounted inside said opening and having two opposite poles, said magnet generating a magnetic field between said opposite poles;
 a voice coil disposed movably in said magnetic field;
 a diaphragm spread over said opening and attached to said upper end of said housing at a peripheral portion thereof, said diaphragm having a central convex portion dimensionally matching perimeter of said voice coil, said central convex portion having a concentric cutout portion, said diaphragm further having an annular convex portion encircling said central convex portion and forming an annular juncture with said central convex portion, said annular juncture being attached to said voice coil so that said voice coil will move in said magnetic field by virtue of movement of said diaphragm in response to compression and rarefaction of sound waves; and
 a membrane made of a material more rigid than said diaphragm, said membrane covering said cutout portion and extending to said annular juncture, said membrane being connected to said central convex portion only at said annular juncture.


5,590,212
DIAPHRAGM FOR A CAPACITANCE TYPE LOUDSPEAKER

Masaru Uryu, Chiba; Kunihiko Tokura, Saitama; Ikuo Chatani, Kanagawa; Ikuo Mizoguchi, and Mamoru Ito, both of Tochigi, all of Japan, assignors to Sony Corporation, Tokyo, Japan

Filed Jul. 28, 1994, Ser. No. 281,633
 Claims priority, application Japan, Jul. 30, 1993, 5-190147
 Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—191

8 Claims



1. A diaphragm for a capacitance type loudspeaker comprising:
 a base film having a thickness of 25 μm or less, and a conductive polymer layer disposed on said base film, the conductive polymer layer having a thickness of from about 0.04 μm to 0.08 μm

carried by the inner surface for fastening the mount to the outer shell of the helmet whereby the layer of adhesive material permits the fastening of the mount to the helmet without impairing the structural integrity of the helmet and whereby the generally smooth outer surface, the sleeve-like member extending from the front of the mount within the front profile and the receiving means extending from the rear of the mount minimize undesirable wind noise during use of the microphone mount assembly on a helmet.

5,590,210

LOUDSPEAKER STRUCTURE AND METHOD OF ASSEMBLING LOUDSPEAKER

Shinta Matsuo, Kokubunji, and Yoshio Sakamoto, Hachioji, both of Japan, assignors to Kabushiki Kaisha Kenwood, Tokyo, Japan

Continuation of Ser. No. 223,968, Apr. 6, 1994, abandoned.


This application Aug. 21, 1995, Ser. No. 517,352

Claims priority, application Japan, Apr. 9, 1993, 5-107367

Int. Cl.⁶ H04R 25/00; 31/00

U.S. Cl. 381—199

1 Claim



1. A method of assembling a loudspeaker comprising:
 preparing first and second disc-like magnets which have been magnetized in their axial directions and a disc-like plate of magnetic material which is not magnetized, each of the first and second magnets and the plate being provided with an aperture in its center;
 preparing a holder for holding magnetic circuit components of said first and second magnets and said plate;
 standing up a jig shaft on a said holder, the diameter of the jig shaft being slightly smaller than that of the aperture in said first and second magnets and said plate and the length of the jig shaft being sufficiently long so that the magnetic field at the upper end of the standing jig shaft produced by the first magnet mounted on the holder is sufficiently weak so as not to disturb manipulation of the second magnet;
 sequentially disposing said first magnet and said plate in a semi-stack on said holder so that said jig shaft passes through the apertures of said first magnet and said plate;
 after setting the semi-stack of said first magnet and said plate on said holder, further disposing said second magnet in a stack on said holder so that said jig shaft passes through the apertures of said first magnet, said plate and said second magnet; and
 removing said jig shaft from said holder and then fixing the magnetic circuit components in the stack by screw means,
 wherein said holder or said screw means has an axial shaft which extends through the apertures of said first and second magnets and said plate and the same magnetic polarity ends of said first and second magnets are disposed to face each other to generate a repulsive magnetic field.

about 5% of the base film thickness and having a surface resistivity of from about 1×10^4 to about 1×10^{10} ohms per square, and being formed by soaking the base film in an aqueous solution comprising a conductive high molecular monomer, a chemical oxidizer and a dopant in the absence of a resin binder.

5,590,213

HEADSET WITH ADJUSTABLE HEADPAD


Richard M. Urella, Charlton, and Glen A. Davis, Leominster, both of Mass., assignors to David Clark Company Inc., Worcester, Mass.

Filed Feb. 15, 1995, Ser. No. 388,740

Int. Cl.⁶ H04R 25/00

U.S. Cl. 381—183

7 Claims



5. For use in a headset of the type having a resilient headband with a bridge portion configured to overlie a user's head and leg portions extending from said bridge portion to stirrups carrying earcups configured and dimensioned to enclose a user's ears, an adjustable headpad assembly comprising:
slide members carried on and moveable along said leg portions;
a cushioning element extending between said slide members and connected at opposite ends to said slide members;
securing means associated with said slide members and said leg portions, said securing means being operative to accommodate movement of said slide members along said leg portions to selected positions of adjustment, and to secure said slide members at said positions; and
headpad biasing means for resiliently urging said slide members towards the bridge portion of said headband, said headpad biasing means including an elastomeric sheath enclosing said cushioning element and said bridge portion.

5,590,214

VERTICAL ARRAY TYPE SPEAKER SYSTEM

Hisatsugu Nakamura, 13-3-1001 Roppongi 5-Chome, Minato-ku Tokyo, Japan

Filed Oct. 21, 1994, Ser. No. 326,878


Claims priority, application Japan, Nov. 12, 1993, 5-307445

Int. Cl.⁶ H04R 25/00; H05K 5/00

U.S. Cl. 381—182

20 Claims

1. A vertical array type speaker system comprising:
a pair of adjustable symmetrically opposed baffle boards having front and rear edges;
an array of small diameter speakers mounted on each of said pair of adjustable symmetrically opposed baffle boards so as to be positioned face to face;
the rear edges of said pair of adjustable symmetrically opposed baffle boards being sealingly held together, whereas the front edges of said pair of adjustable symmetrically opposed baffle boards are held apart by top and bottom boards to form a V-shaped chamber having a narrow slot-like opening with a predetermined width.



5,590,215

METHOD FOR PROVIDING MEDICAL IMAGES

George S. Allen, 628 Westview Ave., Nashville, Tenn. 37205


Continuation of Ser. No. 136,183, Oct. 15, 1993, abandoned.

This application Apr. 21, 1995, Ser. No. 427,634

Int. Cl.⁶ G06K 9/00

U.S. Cl. 382—128

25 Claims



1. A method for determining a measurement of a physical property of interest associated with the discrete spatial locations of a three dimensional object, wherein each spatial location of the three dimensional object has a unique address, and wherein the three dimensional object is composed of a plurality of types of matter, each type of matter having at least two properties, comprising the steps of:
generating a first set of data reflective of at least a first physical property accessible by a first imaging technique and scanner for each spatial location of the area of interest;
generating a second set of data reflective of at least a second physical property accessible by a second, different imaging technique and scanner for each spatial location of the area of interest;
storing the data generated by the first and second imaging techniques in a memory storage device along with the address of each spatial location; and
assigning to each unique address a first value, said first value representing the measurement of said property of interest for each unique address, said first value based on a correlation between said property of interest with the measure of the first physical property obtained in the first imaging scan taken and the correlation between said property of interest with the measure of the second physical property obtained in the second imaging scan taken, such that said property of interest is different from said first and second physical properties.

5,590,216

Patent Not Issued For This Number

5,590,217

VEHICLE ACTIVITY MEASURING APPARATUS

Masakazu Toyama, Tokyo, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 862,426, Apr. 2, 1992, abandoned.


This application Jul. 6, 1994, Ser. No. 272,377

Claims priority, application Japan, Apr. 8, 1991, 3-075024; Apr. 8, 1991, 3-075026; Apr. 12, 1991, 3-079587; Apr. 16, 1991, 3-083892

Int. Cl.⁶ G06K 9/00

U.S. Cl. 382—104

13 Claims



1. A vehicle activity measuring apparatus comprising:
a video camera for picking up an image of a road, on which a vehicle is traveling, and a background image of the road on which no vehicle is traveling, and for outputting the image of the road every frame and the background image of the road;
a first storage means for storing the images to the road for a predetermined number of frames and the background image of the road;
image processing means for extracting the vehicle which is traveling on the road based on the image of the road and the background image of the road, both of which are stored in the first storage means, to produce vehicle information on the extracted vehicle, every frame, and for assigning an identification number to the vehicle information when the vehicle is extracted for the first time, the vehicle information containing position information of the extracted vehicle;
a second storage means for storing the vehicle information in a storage area identified by the identification number; and
a computer for calculating an instantaneous vehicle speed of the extracted vehicle based on the position information contained in the vehicle information stored in the second storage means and then weighing the instantaneous vehicle speed, every frame, and for calculating a vehicle speed of the extracted vehicle based on an average of the weighted instantaneous vehicle speeds over the predetermined number of frames.

5,590,218

UNSUPERVISED NEURAL NETWORK CLASSIFICATION WITH BACK PROPAGATION

Leonard Ornstein, White Plains, N.Y., assignor to Bayer Corporation, Tarrytown, N.Y.


Continuation of Ser. No. 139,396, Oct. 18, 1993, Pat. No. 5,444,796. This application Jun. 7, 1995, Ser. No. 481,108

Int. Cl.⁶ G06K 9/62

U.S. Cl. 382—157

23 Claims

1. A method for training a neural network model running on a computer system to generate classifications from a training sample set, said neural network model representing a neural network



having an input layer an output layer and at least one hidden layer between the input layer and the output layer wherein each layer includes at least one node and wherein each connection between two nodes of successive layers is characterized by an internal weight, said method comprising the steps of:

- arbitrarily assigning a numeric label to each training sample signal of a training sample signal set as a target vector signal for an output vector signal for classification, said numeric label selected from a set comprising a plurality of values;
- executing a back propagation-like training run by cycling through said training sample set, presenting each said training sample signal to an input of said model, the input representing said input layer, thereby generating said output vector signal for each said training sample signal, and modifying internal weight signals representing said internal weights based on the differences between said output vector signals and their corresponding target vector signals;
- estimating the convergence of components of said output vector signal towards respective components of said target vector signal;
- permuting said components of each said target vector signal according to said convergence, thereby updating said target vector signals;
- repeating steps (b), (c), and (d) until a predetermined condition is satisfied, thereby generating a final set of said internal weight signals to be used with said neural network model or said neural network for future classifications.

5,590,219

METHOD AND APPARATUS FOR RECOGNIZING GESTURES ON A COMPUTER SYSTEM

Arnaud P. J. Gourdol, Cupertino, Calif., assignor to Apple Computer, Inc., Cupertino, Calif.


Continuation of Ser. No. 130,074, Sep. 30, 1993. This application Mar. 16, 1995, Ser. No. 405,542

Int. Cl.⁶ G06K 9/46

U.S. Cl. 382—202

27 Claims

1. A method for recognizing a gesture input on a display screen for a computer system, the method comprising the steps of:
receiving a stroke input by a user onto a computer screen, the stroke being represented as a string of points;
smoothing said stroke by reducing the number of points that represent the stroke such that the points of the smoothed stroke are located at least a threshold distance apart from one another;
calculating angles between adjacent segments of said smoothed stroke and calculating derivatives of said angles; and
determining whether said stroke substantially represents an ellipse, the ellipse determining step utilizing said angles and said derivatives of said angles to determine whether said




stroke substantially curves in one direction or curves in more than one direction, wherein said stroke is not considered to substantially represent an ellipse when said stroke does not curve in one direction, and summing said derivatives of said angles and checking whether said sum is within a predetermined range of values, wherein said stroke is not considered to substantially represent an ellipse when said sum is outside said range of values.

5,590,220
BENDING POINT EXTRACTION METHOD FOR
OPTICAL CHARACTER RECOGNITION SYSTEM
Hiroyasu Takahashi, San Jose, Calif., assignor to International
Business Machines Corporation, Armonk, N.Y.
Filed Aug. 12, 1992, Ser. No. 928,818
Int. Cl.⁶ G06K 9/46

U.S. Cl. 382—203

23 Claims



1. A computer-implemented bending point extraction method for selectively identifying bending points in a character image and generating a corresponding data set for use as input to an optical character recognition procedure that identifies the character image, the bending point extraction method comprising the steps of:

- inputting a picture element (PEL) array pattern of black and white picture elements representing a character image to be recognized, the PEL array pattern including a plurality of array positions representing continuous contours of the character image;
- scanning the PEL array pattern to trace one or more continuous contours of the character image and generating a list of contour points for each traced contour;

determining for each contour point an acuteness value representing an angle of contour curvature and generating a list of acuteness values for each traced contour;

separating each acuteness list into contour groups, each contour group having a series of a consecutive points that are either all convex or all concave in curvature;

selecting one or more heuristically determined parameters for use in identifying bending points to be extracted;

identifying contour groups having potential bending points therein using at least one of said heuristically determined parameters and

extracting selected bending points from one or more of said identified contour groups using at least one of said heuristically determined parameters in one or more iterations, said parameters defining one or more contour group properties and having different values in successive iterations to identify bending points that meet or exceed the threshold values imposed by the heuristically determined parameters and which are of different significance relative to the optical character recognition procedure.


5,590,221

IMAGING METHOD AND SYSTEM CONCATENATING
IMAGE DATA VALUES TO FORM AN INTEGER, AND
PARTITIONING THE INTEGER

Dale C. Newton, 986 Cobblestone Dr., Orange Park, Fla. 32073
Filed Mar. 30, 1994, Ser. Nn. 219,827

Int. Cl.⁶ G06T 9/00

22 Claims



1. An imaging system, comprising the combination of

- scanning means adapted to scan an image field as an array of image pixels in a preselected order, the image pixels having a characteristic adapted to be evaluated numerically;
- evaluative means adapted to evaluate the given characteristic of each of the pixels, in the scanned order, to produce at least one set of successive numerical image data values;
- linking means adapted to concatenate each set of numerical image data values into a single corresponding linked image data integral number;
- partition means adapted to partition each linked image data integral number into at least one image partition set of numerical terms summing to that number, any numerical partition term being present only once within any single resulting partition set; and
- storage means adapted to store foregoing numerical data representing said at least one image partition set of numerical terms, pending subsequent retrieval thereof and consequent image replication.

5,590,222

IMAGE SIGNAL PROCESSING APPARATUS UTILIZING
A 2D HAAR TRANSFORM AND ADAPTIVE SELECTION
OF IMAGES BASED ON A PARAMETER SUCH AS A
RATIO OF COEFFICIENTS FOR REDUCING BLOCK
DISTORTION AND METHOD THEREOF

**Yulchi Kojima, Kanagawa, Japan, assignor to Sony Corpora-
tion, Tokyo, Japan**


Filed Nov. 14, 1994, Ser. No. 339,002

Claims priority, application Japan, Nov. 15, 1993, 5-308730


Int. Cl.⁶ G06K 9/40

U.S. Cl. 382-268

8 Claims



1. A method for processing a restored image signal having distortions obtained by decoding coded data by utilizing a two-dimensional inverse orthogonal transformation, said coded data obtained by coding an image signal by utilizing a two-dimensional orthogonal transformation, said method comprising the steps of:
 - constructing a correction block having pixels of four coded blocks which are adjacent to one another and having a distortion;
 - performing two-dimensional orthogonal transformation in units of said correction block by utilizing a Haar function so as to form a plurality of coefficients including higher-order side coefficients, three lower-order side coefficients and a dc coefficient;
 - calculating a ratio of one of a power sum and absolute value sum of said three lower-order side coefficients to a corresponding one of a power sum and absolute value sum of the coefficients other than said dc coefficient and said three lower-order side coefficients;
 - adding a correction value to said higher-order side coefficients in accordance with said three lower-order side coefficients after the coefficients other than said dc coefficient and said three lower-order side coefficients have been made zero so as to form a correction coefficient signal;
 - performing two-dimensional inverse orthogonal transformation on said correction coefficient signal in units of said correction block by utilizing the Haar function so as to generate a smoothed image signal in which step-shaped distortions on the boundaries of said coded blocks have been smoothed; and
 - combining together said restored image signal and said smoothed image signal in accordance with said ratio so as to obtain an image signal in which the distortions on the boundaries of the coded blocks have been substantially eliminated.



- (2) based upon whether a function of the values of the pixels within a predetermined area of the dot profile is different from a predetermined desired value, adjusting the value assigned to a particular pixel within the predetermined area such that in some instances, the adjusted value is interpretable as the other of the two colors; and
- (3) repeating step (2) for additional predetermined areas of the dot profile until the entire dot profile has been covered;
- (4) repeating steps (1) through (3) for each of the dot profiles in the threshold array, whereby the resulting dot profiles are substantially free of artifacts;
- (5) assembling the filtered dot profiles into a threshold array made up of a set of reference gray values;
- (6) sampling the image to be reproduced at each pixel of the display device to obtain an image gray value;
- (7) selecting a reference gray value for that pixel from the threshold array corresponding to the sampled image gray value for that pixel;
- (8) comparing the image gray value for that pixel against the reference gray value for that pixel to obtain the color of the pixel to be displayed;
- (9) displaying an image on the digital display device, including each of the pixels with the color determined by the comparison of step (8).

5,590,224

OCR IMAGE PREPROCESSING METHOD FOR IMAGE
ENHANCEMENT OF SCANNED DOCUMENTS BY
CORRECTION OF REGISTRATION

**Bruce B. Fast, 2600 Prindle Rd., Belmont, Calif. 94402, and
Dana R. Allen, 1745 Hunt Dr., Burlingame, Calif. 94010
Division of Ser. No. 963,051, Oct. 19, 1992, abandoned. This
application May 22, 1995, Ser. No. 447,191
Int. Cl.⁶ G06K 9/36**

Int. Cl.⁶ G06K 9/36

U.S. Cl. 382—291

3 Claims

5,590,223

METHOD OF GENERATING A THRESHOLD ARRAY

Stephen N. Schiller, Hayward, Calif., assignor to Adobe Systems Incorporated, Mountain View, Calif.

Filed Apr. 29, 1994, Ser. No. 236,493

Int. C
U.S. Cl. 382—270

6 Claims

1. A method of displaying on a digital display device an image made up of a plurality of pixels, each having a particular color, using a threshold array made up of a plurality of dot profiles, the dot profiles being made up of a plurality of black or white pixels, certain of the pixels in certain of the dot profiles being constrained to be either black or white, comprising the following steps:

- (1) assigning a value to each unconstrained pixel of one of the dot profiles, each such value being interpretable as one of the two colors black or white;

1. A scanned document image enhancement process for determining a horizontal scan line as a top registration reference scan line and a vertical pixel column as a left margin registration reference pixel column of said image, said image having scan lines including a top most scan line and pixel columns including a leftmost pixel column, said process including the steps of
starting at said topmost scan line totaling scan line wise black horizontal run length values, and
starting at said left most pixel column totaling pixel column wise black vertical run length values,
determining a lowest accumulated vertical run length value and a lowest accumulated horizontal black run-length value,
detecting on successive ones of said scan lines an increase in

- c) each of said members including at least one spring-loaded assembly including a spring coaxial with an internal channel of a body element for exerting a compressive force between the ends of aligned ferrule-mounted optical fibers;
- d) a fastener for engaging said members to one another; and
- e) an asymmetrical keying member associated with each of said fibers for rotationally aligning the terminal end thereof.

5,590,230

OPTICAL FIBER CONNECTOR INCLUDING HOUSING WITH A PLURALITY OF SLOTS HAVING SECURING PLATES


Yu-feng Cheng, No. 7, Fu Hsing St., Tu Cheng Hsiang, Taipei Hsien, Taiwan

Filed Nov. 13, 1995, Ser. No. 585,439

Int. Cl.⁶ G02B 6/36

U.S. Cl. 385—77

3 Claims



1. An optical fiber connector comprising:
- a tubular housing which defines a lumen, including:
 - a distal portion having a first inside diameter and adapted to receive a head portion of an optical fiber;
 - an intermediate portion having a second inside diameter larger than the first inside diameter, wherein the intermediate portion is substantially adjacent to the distal portion and adapted to receive a middle portion of the optical fiber; and
 - a proximal portion having a third inside diameter larger than the second inside diameter, wherein the proximal portion is substantially adjacent to the intermediate portion and adapted to receive a tail portion of the optical fiber;
 - a plurality of parallel slots each defined through a corresponding upper periphery and lower periphery of said housing; and
 - a plurality of securing plates each being positioned inside said slot with two distal ends thereof substantially protruding slightly out of said slot, the securing plate defining a hole at the center of said plate and further defining a recess at both sides of said securing plate for firmly securing a fiber there-through.

5,590,231

FERRULE

Shigeto Kawamura, and Takehiko Yamamura, both of Yokkai-chi, Japan, assignors to Sumitomo Wiring Systems, Ltd., Japan

Filed Nov. 29, 1994, Ser. No. 346,021


Claims priority, application Japan, Jan. 24, 1994, 6-023283

Int. Cl.⁶ G02B 6/36

U.S. Cl. 385—78

4 Claims

1. A ferrule comprising:
- a tubular core wire holding portion for receiving and holding a core wire portion of a plastic optical fiber; and
 - a tubular sheath holding portion for receiving and holding a sheath portion of said plastic fiber,
- said core wire holding portion including a large-diameter portion at a front end thereof having a tapered inner surface such that an inner diameter thereof increases toward the front end.



wherein an angle at which said tapered inner surface is flared is not more than 3 degrees.

5,590,232

OPTICAL PACKAGE AND METHOD OF MAKING


Robert M. Wentworth, Phoenix; David Galloway; Garland D. Cotney, both of Tempe, and Brian A. Webb, Chandler, all of Ariz., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Feb. 16, 1995, Ser. No. 390,209

Int. Cl.⁶ G02B 6/00; 6/36

U.S. Cl. 385—92

21 Claims



1. An optical package comprising:
- a housing defining a mounting area with a plurality of leads formed in the housing, each lead having a first end extending into the mounting area and a second end extending externally from the housing;
 - a semiconductor die including at least one photonic device with a plurality of electrical terminals, the semiconductor die being mounted on the housing in the mounting area with the plurality of electrical terminals electrically connected to the plurality of leads, and the photonic device further having an active light area positioned to be optically accessible through the mounting area in the housing; and
 - optical fiber alignment means mounted on the housing in the mounting area for receiving at least one optical fiber and aligning the received optical fiber with the active light area of the photonic device.

5,590,233

OPTICAL FIBER CABLE AND AN ASSOCIATED METHOD OF MANUFACTURE

Michel Carratt, Houilles, and Michel de Vecchis, Vaureal, both of France, assignors to Alcatel Cable, Clichy Cedex, France

Filed Aug. 3, 1994, Ser. No. 285,287

Claims priority, application France, Aug. 4, 1993, 93 09615

Int. Cl.⁶ G02B 6/44

U.S. Cl. 385—100

13 Claims

1. An optical fiber-cable comprising:

5,590,235

DC MOTOR CONTROL WITH PERIODIC RESET

Hermann Rappenecker, Vöbrenbach, and Frank Jeske, Tennenbron, both of Germany, assignors to Papst-Motoren GmbH & Co. KG, Georgen, Germany


Filed Nov. 22, 1994, Ser. No. 343,723

Claims priority, application Germany, Dec. 3, 1993, 43 41 203.3

Int. Cl.⁶ H02P 7/28

U.S. Cl. 388—803

16 Claims



a plurality of optical fibers, each fiber having an optical core surrounded by optical cladding, each of said optical fibers being provided over said optical cladding with a substantially hermetic coating and including over said hermetic coating a coating of plastics material;

said cable further including an outer protective sheath of plastics material surrounding said optical fibers;

wherein each of said optical fibers has a mode field diameter lying in the range 7 μ m to 9 μ m at around 1550 nm, and a cutoff wavelength that is less than or equal to 1.35 μ m, and wherein said optical fibers are assembled together in said cable by being twisted around one another.

5,590,234

FIBER OPTIC SPLICE ORGANIZERS


Jacqueline J. Pulido, Cedar Park, Tex., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Mar. 31, 1995, Ser. No. 414,612

Int. Cl.⁶ G02B 6/00

U.S. Cl. 385—135

19 Claims



1. An article for releasably securing a plurality of elongate, fiber optic components such as splice elements, the article comprising:
- a pad member; and
 - a plurality of flexible arm members attached and extending generally perpendicular to said pad member, said arm members positioned to form first and second adjacent, parallel grooves for receiving individual fiber optic components, said arm members being staggered along a given one of said grooves to provide a multi-point load on any component inserted therein wherein said first groove has at least two of said arm members located along a first side of said first groove at opposite ends of said first groove, and an additional arm member located along a second side of said first groove, intermediate said ends thereof, such that a fiber optic component may be placed in said first groove without interfering with said second groove.

5,590,236

SPEED CONTROLLER OR AN INSTRUMENT HAVING A SPEED CONTROLLER INCLUDING DETECTION MEANS FOR LINEARLY DETECTING THE AMOUNT OF ROTATION LESS THAN ONE FULL ROTATION OF A ROTATING MEMBER

Osamu Sato, Saitama-ken, and Fumio Mochida, Maebashi, both of Japan, assignors to Canon Denshi Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 767,841, Sep. 30, 1991, abandoned, which is a division of Ser. No. 493,294, Mar. 14, 1990, Pat. No. 5,072,162. This application Jan. 10, 1994, Ser. No. 180,771

Claims priority, application Japan, Mar. 14, 1989, 1-59589

Int. Cl.⁶ H02P 5/168

U.S. Cl. 388—821

20 Claims



1. A speed controller comprising:
- a drive source as a rotating member;
 - input means for inputting driving speed information on the driving speed of said rotating member;

driving means for rotatably driving said rotating member less than one full rotation thereof on the basis of said driving speed information;
 detection means for directly detecting a movement amount of said rotating member and outputting a detection signal which varies linearly with the position of said rotating member representing movement amount information;
 means for forming rotating speed information of said rotating member from said detection signal; and
 means for correcting said driving speed information by the use of said rotating speed information, said correcting means providing corrected driving speed information.


5,590,237

APPARATUS AND METHOD FOR CONTROLLING THE ROTATION SPEED OF ELECTRIC MOTORS

Gilles Audemard, Mirandola, Italy, assignor to Hospal AG, Basel, Switzerland
 Filed Jun. 12, 1991, Ser. No. 713,367
 Claims priority, application Italy, Jun. 22, 1990, 67457/90
 Int. Cl. H02P 7/285

U.S. Cl. 388-832

14 Claims



1. An apparatus for controlling the rotation speed of an electric motor, the apparatus comprising:
 means for generating a first signal (S1) with pulses having a variable frequency corresponding to a desired rotation speed of the motor;
 means for transforming the first signal (S1) into a second signal (S2) with pulses having the frequency of the first signal (S1) and a predetermined constant duration; and
 means for supplying the motor with a pulsating voltage having a frequency and a pulse duration substantially equal to the frequency and the pulse duration of the second signal (S2).

5,590,238

HORIZONTALLY AND VERTICALLY MOVABLE RADIANT HEATER FOR REMOVING PAINT FROM A SURFACE

Birger Ericson, Alingsås, Sweden, assignor to Birger Ericson Fasad AB, Sweden


Continuation of Ser. No. 923,940, Sep. 3, 1992, abandoned.
 This application Sep. 12, 1995, Ser. No. 526,544

Claims priority, application Sweden, Mar. 5, 1990, 9000763
 Int. Cl. B44D 3/16; E04G 23/00

U.S. Cl. 392-412

33 Claims

1. An apparatus for facilitating the removal of paint from a vertical wall surface, comprising:
 heating means including at least one heat source for heating a painted vertical wall surface;
 carrier means for retaining said heating means in operative position with respect to a painted vertical wall surface, said carrier means being selectively movable with respect to a painted vertical wall surface;
 guide means for obtaining horizontal and vertical guided travel along distinct horizontal and vertical paths of said carrier means with respect to the painted vertical wall surface and for



retaining said carrier means in the vicinity of a painted vertical wall surface so that said heating means can be selectively moved and exposed to various areas on a painted vertical wall surface; and
 fastening means for securing a portion of said guide means to a surface sufficient to permit secured placement of said heating means in an operative position with respect to a painted vertical wall surface.

5,590,239



PLANAR UNIFORM HEATING SURFACE WITH ADDITIONAL CIRCUMSCRIBING RING

Douglas J. Resnick, Phoenix; William A. Johnson, Paradise Valley; Kevin D. Cummings, Phoenix, all of Ariz., and Hector T. H. Chen, Madison, Wis., assignors to Motorola, Schaumburg, Ill.

Filed Jun. 6, 1994, Ser. No. 254,845
 Int. Cl. H05B 1/00; G21K 5/00

U.S. Cl. 392-418

13 Claims



1. A uniform heating fixture in combination with an X-ray mask including a supporting ring structure defining a central opening with a membrane across an end thereof, the fixture comprising:
 a heat conductive member having a first plane surface, a second surface, and a third plane surface, the first plane surface and the third plane surface being parallel and connected by the second surface, the third plane surface circumscribing and extending away from the first plane surface; and
 the heat conductive member extending into the central opening of the supporting ring structure and thereby positioning the first plane surface adjacent the membrane, at least one of the second surface and the third plane surface of the heat conductive member being formed and positioned to engage the

supporting ring structure of the X-ray mask and position the membrane parallel with and spaced from the first plane surface.

5,590,240

ULTRA PURE WATER HEATER WITH COAXIAL HELICAL FLOW PATHS


Dennis J. Rezabek, Thompson, Ohio, assignor to Process Technology Inc., Mentor, Ohio

Filed May 30, 1995, Ser. No. 453,480

Int. Cl. F24H 1/16

U.S. Cl. 392-483

32 Claims



1. A high efficiency, non-contaminating fluid heater for heating ultra pure water with a minimum amount of contamination as the ultra pure water passes through the fluid heater, comprising an inner and an outer helical passageway, both of which are tubular and formed from an electrically nonconductive material which is substantially inert in the presence of ultra pure water, each of said inner and outer helical passageways having a helical outer surface and defining a helical tubular passageway therein through which said ultra pure water passes as it is heated, said inner helical tubular passageway being in fluid communication with said outer helical tubular passageway and providing for sequential fluid flow between said inner and outer helical passageways, a coiled resistance heater disposed about and being in intimate contact with said helical outer surface of said inner helical passageway, said coiled resistance heater when energized having a temperature of at least 1200° F. to maximize the production of infrared energy having a wavelength of between 2 and 4.3 micron to heat by radiation, conduction and convection the ultra pure water which flows through said inner tubular helical passageway, said outer helical passageway substantially surrounding said inner helical passageway, said inner helical passageway having a longitudinal axis and said outer helical passageway having a longitudinal axis which is substantially coaxial with said longitudinal axis of said inner helical passageway, said longitudinal axes of said inner and outer helical passageways being substantially horizontally disposed, said inner helical passageway at least in part supporting said outer helical passageway, said outer helical passageway being disposed to enable the ultra pure water flowing therethrough to absorb radiated and convective heat from said coiled resistance heater which surrounds said inner helical passageway to increase the efficiency of the fluid heater, and housing means formed from an infrared reflective material substantially enclosing said inner and outer helical passageways to reduce radiated heat flow from said coiled resistance heater to the ambient environment.

5,590,241

SPEECH PROCESSING SYSTEM AND METHOD FOR ENHANCING A SPEECH SIGNAL IN A NOISY ENVIRONMENT

Sangil Park; Ed F. Martinez, both of Austin, Tex., and Dae-Hee Yoon, Seoul, Rep. of Korea, assignors to Motorola Inc., Schaumburg, Ill.


Filed Apr. 30, 1993, Ser. No. 54,494

Int. Cl. G10L 3/02; 9/00

U.S. Cl. 395-236

9 Claims

6. An adaptive finite impulse response filter, comprising:
 a signal input for receiving an input signal;



a feedback input for receiving an error signal;
 an output for providing a filtered output signal;
 a plurality of filter taps coupled in series with said input signal;
 a plurality of variable multipliers for multiplying said input signal and outputs of said plurality of filter taps by corresponding ones of a plurality of coefficients;
 a summing device for providing said filtered output signal as a sum of outputs of each of said plurality of variable multipliers; and
 prediction means for receiving said error signal, and for recursively updating each coefficient according to a maximum one of first and second predicted values of said filtered output signal, in response to said error signal;
 said first predicted value of said filtered output signal having a first smoothing parameter associated therewith;
 said second predicted value of said filtered output signal having a second smoothing parameter associated therewith;
 said first smoothing parameter providing a faster prediction response after a change in said input signal than said second smoothing parameter.

5,590,242

SIGNAL BIAS REMOVAL FOR ROBUST TELEPHONE SPEECH RECOGNITION

Bing-Hwang Juang, Warren, and Mazin G. Rahim, Manalapan, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.


Filed Mar. 24, 1994, Ser. No. 217,035

Int. Cl. G10L 3/02; 9/00; 5/00

U.S. Cl. 395-254

13 Claims

1. A method for reducing the effect of an unknown signal bias in



an input speech signal for use by a speech recognition system, comprising:

- (1) training the speech recognition system by using the following steps:
 - (a) generating a set of centroids based on a training speech signal;
 - (b) computing an estimate of the bias for the training speech signal based on maximizing a likelihood function;
 - (c) subtracting the estimate of the bias from the training speech signal to obtain a tentative training speech value;
 - (d) repeating steps (b) and (c), wherein each subsequent computed estimate of the bias is based on the previous


- tentative training speech value to arrive at a reduced bias training speech signal value;
- (e) recomputing the centroids based on the reduced bias training speech signal to generate a new set of centroids;
- (f) repeating steps (b) to (e) to compute a processed reduced bias speech signal and to form an enhanced set of centroids;
- (g) utilizing the enhanced set of centroids and the processed reduced bias speech signal as training input for a speech recognizer;
- (2) testing an input speech signal to minimize the unknown bias by using the following steps:
- (h) utilizing the enhanced set of centroids to compute an estimate of the bias for each utterance of the speech signal based on maximizing a likelihood function;
- (i) subtracting the estimate of the bias from the speech signal to obtain a tentative speech value;
- (j) repeating steps (h) and (i), wherein each subsequent computed estimate of the bias is based on the previous tentative speech value, resulting in a reduced bias speech signal value; and
- (3) utilizing the reduced bias speech signal as input to a speech recognizer.

5,590,243

NEURAL NETWORK SYSTEM WITH SAMPLING DATA
Yoshiaki Akimoto, Kanagawa-ken; Hideo Tanaka; Hiromi Ogi, both of Tokyo; Yoshio Izul, Hyogo-ken; Hisao Tanka, Hyogo-ken, and Toshiaki Sakaguchi, Hyogo-ken, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
Continuation of Ser. No. 728,540, Jul. 11, 1991, abandoned.
This application Oct. 3, 1994, Ser. No. 317,215
Claims priority, application Japan, Jul. 12, 1990, 2-186496; Jul. 12, 1990, 2-186499

Int. Cl.⁶ G06F 15/18
U.S. Cl. 395—23

35 Claims



1. A neural network system comprising:
an input layer, an intermediate layer and an output layer each layer containing at least one neural element, each having an input and an output, for simulating a neuron; and a plurality of inter-layer connections between neural elements wherein each neural element input layer has a connection from the output to the input of at least one neural element in the intermediate layer, each neural element in the intermediate layer has a connection from the output to the input of at least one neural element in the output layer, and each inter-layer connection has a connecting weight;
sampling data having a plurality pairs of sampling data values, each pair of sampling data values including a sampling data input value and a corresponding sampling data output value wherein the sampling data input values have regular intervals, and learning data having at least three pairs of learning data values, each pair of learning data values including a learning


data input value and a corresponding desired output value wherein the learning data input values have irregular intervals;
wherein each neural element of said intermediate layer is assigned a unique pair of sampling data values and has a unique sampling function derived by translating an original sampling function by the sampling data input value assigned to the neural element, wherein the sampling function defines a relationship between the input and output of the neural element;
wherein said connecting weight for each connection between a neural element in said intermediate layer and a neural element in said output layer is set to the sampling data output value assigned to the neural element in the intermediate layer; and means for training the neural network including means for adjusting the connecting weights so as to minimize an error between a learning data output value and an actual output value obtained by applying a learning data input value to the neural network.

5,590,244

PROFILE CONTROL SYSTEM FOR ROBOTS

Yasuyuki Nakata, Sagami-hara; Akihiko Yabuki, Isehara; Yutaka Yoshida, and Katsushi Nishimoto, both of Kawasaki, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan
Continuation of Ser. No. 943,158, Sep. 10, 1992, abandoned, which is a continuation of Ser. No. 524,487, May 17, 1990, abandoned. This application Jan. 18, 1995, Ser. No. 374,997
Claims priority, application Japan, May 17, 1989, 1-123275; Jul. 14, 1989, 1-182071; Sep. 20, 1989, 1-241897; Dec. 14, 1989, 1-322652; Dec. 14, 1989, 1-322654
Int. Cl.⁶ G06F 15/50; 15/46; G05B 19/42
U.S. Cl. 395—95

14 Claims



1. A profile control system for a force control robot system including a robot, a force detecting section for detecting a force acting between an end of the robot and a work object, and a position detecting section detecting the position of the end of the robot and permitting the robot to perform a profiling operation on a surface of the work object from a known start point to a known target point, said profile control system comprising:
calculating means for calculating a unit vector L in a target direction at a contact point between the end of the robot and the work object, by equation

$$L = \frac{P_E - P_i}{|P_E - P_i|}$$

wherein a unit vector L_i at a contact point P_i in a profiling operation is calculated using a position vector P_i and P_t at the contact point P_i and the target point P_t , respectively;
normal vector calculating means for calculating a unit vector n at a point of contact between the end of the robot and the work object based on the force detected by the force detecting section;
movement calculating means for calculating a unit vector o in a direction of movement of the end of the robot, comprising:
first means for finding a unit vector a as an outer product of the unit vector n and the unit vector L in a direction of an outer product of the unit vector n and the unit vector L , and
second means for finding the unit vector o as an outer product of the unit vector a and the unit vector n in a direction of the outer product of the unit vector a and the unit vector n ;
control command generating means for generating control commands to said robot based on the unit vector o in the direction of movement of the end of the robot and the unit vector n ; and
force and position control means for controlling the force of the robot and the position of the end of the robot based on at least the control commands, permitting the robot to perform a profile on a surface of the work object having the known start point, the known target point, and an unknown contour.


5,590,245

METHOD FOR TRANSMITTING IMAGE PROCESSING JOBS FROM A CLIENT SYSTEM, AND ROUTING AND PERFORMING THE JOBS IN AN IMAGE PROCESSING SYSTEM

Patrick Leamy, Alan Leamy, and John Gillin, all of Dublin, Ireland, assignors to Offset Studios Limited, Dublin, Ireland
Filed Aug. 24, 1994, Ser. No. 294,030
Claims priority, application Ireland, Apr. 6, 1994, 940297
Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—118

10 Claims



1. An image processing method carried out by a client system comprising an image processor having a communications device and by an image processing system comprising a network connected to a plurality of image processing workstations, to scanner/printer devices, to printers, and to a control image processor which is in turn connected to a communications device, the method comprising the steps of:

- the image processor of the client system generating a transmission file by:
interactively logging client data for instructing image processing operations,
automatically retrieving image data from storage devices to which the image processor is connected using said client data, and

combining the logged client data and the retrieved image data and compressing said logged client data and said retrieved image data to generate the transmission file,
the communications device of the client system automatically transmitting said transmission file to the communications device connected to the control image processor of the image processing system;
the control image processor: automatically decompressing the transmission file received via the communications device, reading a client identifier from the client data and generating an output notification display on a video screen of the control image processor,
generating a parameter display for interactive inputting of job parameters by a supervisor according to data received in said transmission file, the parameters including a job category command classifying the job as direct output, page make-up, re-touching, or imposition, and
generating a job file of image processing commands according to inputted parameters and the client data, and automatically routing the job file to a workstation of the image processing system;
the workstation which receives the job file automatically determining if the job is for direct output to a printer according to the job category command and if so automatically routing the image processing commands to a printer of the network, and if the job is not for direct output the workstation reading the image processing commands within the job file and automatically configuring image processing settings via the workstation operating system for carrying out image processing operations required by said image processing commands, the settings being selected from a look-up table retrieved from the control image processor; and
the workstation carrying out the image processing operations and generating processed image data and, when completed, automatically transmitting a supervisor signal to the control image processor and subsequently routing the processed image data to a printer for printing of color separation films.

5,590,246

FUZZY LOGIC CONTROLLED VIDEO PRINTER


Ali Asgharzadeh, and Mohammad Jamshidi, both of Albuquerque, N.M., assignors to University of New Mexico, Albuquerque, N.M.

Filed Aug. 15, 1994, Ser. No. 290,232

Int. Cl.⁶ G06K 15/00

U.S. Cl. 395—109

12 Claims



5. A video printer control method comprising the steps of:
a) sensing at least four attributes of images output from a video source to a video printer;
b) non-iteratively determining video printer output attribute settings based upon attributes sensed by said sensing means via fuzzy logic control comprising a plurality of IF-THEN rules; and
setting output attribute settings of the video printer to the determined settings.

5,590,247
CHARACTER STRING OUTPUTTING METHOD AND APPARATUS CAPABLE OF VARYING SIZES OF CHARACTERS

Shio Mikuni, Hamura, Japan, assignor to Casio Computer Co., Ltd., Tokyo, Japan


Filed Aug. 25, 1994, Ser. No. 296,357

Claims priority, application Japan, Aug. 31, 1993, 5-237136; Aug. 31, 1993, 5-237137

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—110

14 Claims



1. A character string outputting apparatus for arranging a character string within a designated region, comprising:
 region designating means for designating a character string configuration region so as to arrange the character string within said character string configuration region;
 numeral sequence calculating means for expressing said character string configuration region in the form of a numeral sequence; configuration function and for producing a configuration position of each of characters in the form of a numeral sequence;
 character frame producing means for substituting the numeral sequence calculated by said numeral sequence calculating means for the character string configuration function to produce a coordinate value of a character frame in which said character string is allocated into said character string configuration region;
 coordinate transforming means for moving a coordinate value of an origin about a font of each character contained in the character string to a predetermined position, and for parallel-moving coordinate data for constituting the fonts of the respective characters in correspondence with moving amounts of the origins; and
 output means for arranging the respective fonts of the characters constituting said character string within said character frame produced by said character frame producing means, and for outputting said character string proportionally spaced within said character string configuration region.

5,590,248
METHOD FOR REDUCING THE COMPLEXITY OF A POLYGONAL MESH

Jonathan A. Zarge, Woburn, Mass., and William J. Schroeder, Schenectady, N.Y., assignors to General Electric Company, Schenectady, N.Y.

Continuation of Ser. No. 815,772, Jan. 2, 1992, abandoned.


This application Feb. 24, 1995, Ser. No. 394,044

Int. Cl.⁶ G06T 17/00

U.S. Cl. 395—121

19 Claims

8. A method for reducing complexity of a polygonal mesh while preserving shape and topology, the method comprising the steps of:
 analyzing each vertex in said mesh to determine if regions around the vertex are substantially co-planar;
 removing said vertex from said mesh if regions around the vertex are substantially co-planar; and
 triangulating an opening left by removing said vertex from said mesh, wherein said triangulating comprises calculating an



angle value for each remaining vertex defining said opening; removing a vertex with a smallest of said angle values from said opening; connecting vertices adjacent to said removed vertex forming a triangle; determining whether a ratio of the triangle height to base length is less than a first predetermined threshold; and replacing said vertex removed if said ratio is less than said first predetermined threshold.

5,590,249
THREE DIMENSIONAL SPRITE RENDERING APPARATUS AND METHOD

Toshiharu Hanaoka, Chiba, Japan, assignor to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Mar. 31, 1995, Ser. No. 414,234

Claims priority, application Japan, Apr. 1, 1994, 6-064279

Int. Cl.⁶ G06T 15/40

U.S. Cl. 395—122

24 Claims



1. A three dimensional sprite rendering apparatus for producing three dimensional graphic images, comprising:
 a three dimensional graphic circuit for producing backgrounds of three dimensional graphic and outputting pixel data for each pixel of said backgrounds;
 a first buffer for storing depth data for each pixel of said backgrounds;
 a voxel character control register for storing control data for voxel characters serving as sprites;
 a voxel character memory for storing geometric data for voxel characters;
 a volume rendering circuit connected to said voxel character control register and said voxel character memory for producing graphics of voxel characters and outputting pixel data for each pixel of said voxel characters;
 a second buffer for storing depth data for each pixel of said voxel characters;
 a depth comparator connected to said first and second buffers for comparing the depth of a three dimensional background

graphic with the depth of a voxel character graphic and generating a control signal according to a result of comparison; and

an image synthesis circuit connected to receive said pixel data of backgrounds and said pixel data of voxel characters as well as said control signal for synthesizing two pixel data inputs according to said control signal.

5,590,250
LAYOUT OF NODE-LINK STRUCTURES IN SPACE WITH NEGATIVE CURVATURE


John O. Lamping, Los Altos, and Ramana B. Rao, San Francisco, both of Calif., assignors to Xerox Corporation, Stamford, Conn.

Filed Sep. 14, 1994, Ser. No. 306,043

Int. Cl.⁶ G06T 1/40

U.S. Cl. 395—127

40 Claims



1. A method comprising:
 obtaining layout data; the layout data indicating positions in a layout space for parts of a node-link structure; the layout space being a space with negative curvature; the node-link structure including nodes and links, each link relating at least two of the nodes; the layout data indicating positions in the layout space for a set of the nodes; the set of nodes forming a branch that includes two or more levels of nodes including a top level and at least one lower level, the top level including a top level node and the lower levels including lower level nodes, each node at each lower level having a parent node at a next higher level to which the node is related through one link; for each of a set of two or more parent nodes, the layout data indicating:
 a parent position in the layout space for the parent node; and
 child positions that lie approximately along a circle in the layout space for a number of lower level nodes that share the parent node, the parent position being approximately at the center of the circle; the number of lower level nodes being two or more; adjacent child positions along the circle being separated by approximately a base spacing;
 the circles having radii that, together, approximate a function that increases slowly with number of lower level nodes such that the radii and spacings between adjacent child positions along circles are all approximately uniform within the branch;
 using the layout data to present a first representation of the node-link structure on a display;
 receiving a signal from a user; the signal indicating a change from a first display position to a second display position; the first representation including a first feature near the first display position, the first feature representing a first part of the node-link structure; and
 in response to the signal, presenting a second representation of the node-link structure on the display; the second representation including a second feature representing the first part of the node-link structure, the second feature being presented

near the second display position; the second representation being perceptible as a changed continuation of the first representation.

5,590,251
COLOR REPRODUCING DEVICE FOR REPRODUCING MATCHED COLORS AND AN OUTPUTTING DEVICE FOR OUTPUTTING INFORMATION FOR REPRODUCING A COLOR OF A COATED SURFACE

Atsushi Takagi, Toyota, Japan, assignor to Toyota Jidosha Kabushiki Kaisha, Toyota, Japan


Filed Aug. 5, 1994, Ser. No. 286,350

Claims priority, application Japan, Aug. 6, 1993, 5-196082; Nov. 30, 1993, 5-300386

Int. Cl.⁶ G06T 15/50

U.S. Cl. 395—131

16 Claims



1. A color reproducing device to which first data expressing a color expressed in a first colorimetric system is inputted, and which reproduces a color corresponding to the inputted first data and to be expressed in a second colorimetric system different than the first colorimetric system, comprising:
 a measuring device measuring each of a predetermined number of colors reproduced by inputting a predetermined number of first data to said color reproducing device, and outputting a predetermined number of second data expressing a color expressed in the second colorimetric system;
 estimating means for estimating relationships of interpolated correspondence expressing relationships between second data other than the measured second data and first data corresponding to the second data other than the measured second data, on the basis of a plurality of relationships of correspondence between the first data inputted to said color reproducing device and the measured second data; and
 selecting means for, after second data which is the same as or closest to data of a color to be reproduced is selected on the basis of the relationships of correspondence and the relationships of interpolated correspondence, selecting first data corresponding to the selected second data on the basis of the relationships of correspondence and the relationships of interpolated correspondence, wherein the selected first data is inputted to said color reproducing device, and said color reproducing device reproduces the color to be reproduced.

5,590,252
VIDEO PROCESSOR SYSTEM AND AUDIO PROCESSOR SYSTEM

Kia Silverbrook, Woollahra, Australia, assignor to Canon Kabushiki Kaisha, Japan, and Canon Information Systems Research Australia Pty Ltd., Australia

Filed Apr. 28, 1993, Ser. No. 53,569


Claims priority, application Australia, Apr. 29, 1992, PL2141

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—133

27 Claims

1. A video processor comprising:



a real-time object (RTO) processor for processing object-based graphic image data describing an object-based graphic image to form pixel-based image data representing the object-based graphic image, said RTO processor incorporating memory means for intermediate storage of only said object-based graphic image data and forming pixel-based image data directly from said object-based graphic image data in real-time without using a pixel-based image data storage means, thereby permitting real-time colour mixing and generation of the pixel-based image data with a first video signal so as to form a second video signal;

a video input means for receiving said first video signal;
at least one colour mixing and generation device arranged to combine said first video signal with said pixel-based image data formed by said RTO processor to provide said second video signal; and
a video output means for outputting said second video signal.


5,590,253

SEQUENCE PROGRAM EDIT SYSTEM FOR INSERTING
ADDITIONAL GRAPHIC ELEMENTS AND FOR
AUTOMATICALLY INSERTING VERTICAL
CONNECTOR LINES

Yasushi Onishi, and Yoshiharu Saiki, both of Minamitsurugun, Japan, assignors to Fanuc Ltd., Japan
Filed Jul. 3, 1995, Ser. No. 497,981

Claims priority, application Japan, Jul. 14, 1994, 6-161740
Int. Cl.⁶ G06T 11/00

U.S. Cl. 395—133 3 Claims



1. A sequence program edit system expressed by a sequential function chart (SFC) system, comprising:


- graphic input means for inputting graphic elements of a flow-chart to respective blocks formed by partitioning a display screen into rows and columns;
- input graphic display means for displaying the inputted graphic elements on the display screen;
- insertion command means for issuing an insertion command to an arbitrary block on the display screen; and
- insertion and display means for automatically inserting and displaying graphic elements of vertical connector lines to blocks in the same row as that of the arbitrary block to which the insertion command has been issued.

5,590,254
**DISPLAYING MULTIPLE VIDEO STREAMS USING A BIT
MAP AND A SINGLE FRAME BUFFER**

Louis A. Lippincott, Roebbing, N.J., and Thomas R. Craver,
Chandler, Ark., assignors to Intel Corporation, Santa Clara,
Calif.

Filed Sep. 30, 1994, Ser. No. 316,605
Int. Cl.⁶ G06T 11/00

U.S. Cl. 395—135 48 Claims



1. A computer-implemented process for processing signals for display using a single frame buffer, comprising the steps of:

- (a) receiving a plurality of pixels, wherein one or more of the plurality of pixels corresponds to a first display and one or more of the plurality of pixels corresponds to a second display;
- (b) generating a display bit map in accordance with the plurality of pixels; and
- (c) generating a display mask in accordance with the plurality of pixels, wherein:
 - if a pixel of the plurality of pixels corresponds to the first display and if a corresponding mask field of the display mask has a first-display value, then the pixel is stored in the display bit map, wherein the mask field comprises at least one mask bit;
 - else if the pixel corresponds to a key color, then the mask field corresponding to the pixel is set to the first-display value;
 - else the pixel is stored in the display bit map and the mask field corresponding to the pixel is set to a second-display value.

5,590,255
GRAPHIC DRAWING APPARATUS FOR GENERATING
GRAPHS OF IMPLICIT FUNCTIONS

Taku Takeshima; Masayuki Noro, both of Kawasaki, and Tomokatsu Saito, Tokyo, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Filed Mar. 14, 1995, Ser. No. 404,107

Claims priority, application Japan, Mar. 18, 1994, 6-048717
Int. Cl.⁶ G06T 11/00

U.S. Cl. 395—141 23 Claims

1. A graphic drawing apparatus for use in an information processing apparatus for displaying a graphic defined by zeros of a polynomial $f(x, y)$ in variables x and y in a logical region on an xy coordinate plane, in a two-dimensional display region corresponding to the logical region, comprising:

zero point calculating means for calculating a zero point interval of the variable y in which zeros of a first univariate polynomial are present within a y -direction display unit width, the first univariate polynomial being obtained by substituting each of a plurality of fixed values of the variable x into the



polynomial $f(x, y)$ and for calculating a zero point interval of the variable x in which zeros of a second univariate polynomial are present within an x -direction display unit width, the second univariate polynomial being obtained by substituting each of a plurality of fixed values of the variable y into the polynomial $f(x, y)$; and


pixel determining means for obtaining a pixel in the two-dimensional display region corresponding to the zero point interval of the variable y for each of the fixed values of the variable x , obtaining a pixel in the two-dimensional display region corresponding to the zero point interval of the variable x for each of the fixed values of the variable y , and determining obtained pixels as pixels representing the graphic.

5,590,256
METHOD FOR MANIPULATING NOTES ON A
COMPUTER DISPLAY

Michael C. Tchao, Palo Alto, and Stephen P. Capps, San Carlos, both of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Continuation of Ser. No. 868,013, Apr. 13, 1992, Pat. No. 5,398,310. This application Dec. 14, 1994, Ser. No. 357,707
Int. Cl.⁶ G09G 5/34

U.S. Cl. 395-787 12 Claims



6. A method for moving divider indicia in the form of a header bar displayed on a computer display as a linear region which separates two adjacent note areas on a screen of the computer display, the header bar containing information corresponding to at least one of the adjacent areas, said method comprising:

- detecting the selection of the header bar by a pointer;
- detecting a sizing gesture made with said pointer on said header bar;
- moving said header bar as indicated by said sizing gesture; and
- scrolling in a scroll direction through said adjacent note areas in response to one or more scrolling commands such that when

an end of a note area is reached, the header bar of the next successive note area is displayed at the top of the computer screen in response to a scrolling command, said scrolling including

scrolling, in response to said scrolling command, in the scroll direction to display a remaining undisplayed area of a displayed one of the note areas as well as at least a portion of an adjacent note area when the remaining undisplayed area of the displayed one of the note areas in the scroll direction has an undisplayed length that is greater than zero but less than the height of the computer screen.

scrolling, in response to said scrolling command, in the scroll direction to display a next successive portion of a remaining undisplayed area of a displayed one of the note areas as well as to not display any portion of an adjacent note area when the remaining undisplayed area of the displayed one of the note areas in the scroll direction has an undisplayed length that is greater than the height of the computer screen, and

scrolling, in response to said scrolling command, in the scroll direction to display a least a portion of an adjacent note area with the header bar associated therewith displayed at the top of the computer screen when the end of the displayed one of the note areas and a portion of the adjacent note area are displayed.


5,590,257

SCRIPT CHARACTER PROCESSING METHOD AND
SYSTEM WITH BIT-MAPPED DOCUMENT EDITING

Continuation-in-part of Ser. No. 693,316, Apr. 29, 1991, Pat. No. 5,220,649, which is a continuation-in-part of Ser. No. 673,292, Mar. 20, 1991, Pat. No. 5,231,698. This application Jun. 14, 1993, Ser. No. 77,293

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—792 40 Claims.



1. A pen-based computer method for a user interactively to edit a series of glyphs which include one or more of handwritten script, text or bitmapped images using a pen-type input device on a document display having a series of lines defining machine editable line spaces for writing script, the method comprising:
 - inputting and displaying a bit-mapped image containing a series of glyphs arranged in a generally linear format but initially unconstrained to the line spaces;
 - decomposing the image into image lines; and
 - mapping each glyph in the image lines to one of the machine editable line spaces;
 - the step of decomposing the image including:
 - establishing a baseline for a current image line;
 - determining a height of the current image line; and
 - determining beginning and end points of the current image line relative to the image;
 - the step of mapping including defining the machine editable line space according to the baseline, height, and beginning and end points, and
 - the step of establishing a baseline comprising:
 - detecting all non-zero bits in a row which represent visible dots on the image;
 - counting the detected bits; and
 - establishing a baseline on the row where the count is less than or equal to a predetermined number of bits.

5,590,258

TEXT GENERATION APPARATUS


Shoichi Aoyama, Katano, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Oct. 3, 1994, Ser. No. 316,942

Claims priority, application Japan, Oct. 1, 1993, 5-247146
Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—793

16 Claims



1. A text generation apparatus for generating a text including character rows separated by blank characters and displaying the text using display means, comprising:

text storage means for storing information for character rows composed of at least one (1) character which are displayed as being interposed with blank characters;

display means for displaying the information stored in the text storage means;


first input operation means for receiving an input of character rows and symbols in the text storage means;

conversion position specifying means for receiving a specification of a conversion position, the specification converting the information stored in the text storage means;

second input operation means for receiving an input of a changing character row;

conversion mode determination means for determining an appropriate conversion mode using an appropriate process for the conversion position received by the conversion position specifying means; and

text content conversion means for writing the changing character row received by the second input operation means into the stored information in the text storage means in accordance with the conversion mode determined by the conversion mode determination means.



- dividing said three-dimensional matrix of information cells into a plurality of two-dimensional matrices, each of said two-dimensional matrices being represented on a display device as a page array of information cells, wherein cell references between cells on one page array are formed by specifying horizontal and vertical coordinates, and cell references between cells on different page arrays are formed by specifying horizontal, vertical, and page coordinates;
- displaying with each said page array of information cells a tab identifier, so that each tab identifier of a particular page array displays the page coordinate for that particular page array;
- receiving as input from a user a descriptive name for naming a page array;
- in response to step (c), assigning said descriptive name to the page coordinate for the named page array; and
- creating a formula having at least one cell reference to a cell on said named page array from a cell on a different page array, so that said at least one cell reference includes said descriptive name as the page coordinate for said named page array.

5,590,260

METHOD AND APPARATUS FOR OPTIMIZING THE DISPLAY OF FONTS IN A DATA PROCESSING SYSTEM


Gary J. Morse, Boca Raton, and Stephen P. Thompson, Delray Beach, both of Fla., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 30, 1993, Ser. No. 176,155

Int. Cl.⁶ G06T 11/00

U.S. Cl. 395—167

35 Claims



1. A method in a data processing system for increasing efficiency in the display of characters on a display within said data processing system, wherein said data processing system includes a system

5,590,259

SYSTEM AND METHODS FOR IMPROVED SPREADSHEET INTERFACE WITH USER-FAMILIAR OBJECTS

Charles R. Anderson, Santa Cruz; Robert W. Warfield, Aptos; Istvan Cseri, Scotts Valley; Murray K. Low; Welkuo Liaw, both of Santa Cruz, and Alan M. Bush, Menlo Park, all of Calif., assignors to Borland International, Inc., Scotts Valley, Calif.

Continuation of Ser. No. 866,658, Apr. 8, 1992, Pat. No. 5,416,895. This application May 12, 1995, Ser. No. 440,184
Int. Cl.⁶ G06F 17/40

U.S. Cl. 395—764

56 Claims

1. In a computer system having a three-dimensional spreadsheet, said three-dimensional spreadsheet comprising a plurality of information cells arranged in a three-dimensional matrix, said information cells storing user-supplied data and formulas operative on said user-supplied data, each said information cell being uniquely identified by a three-dimensional cell address comprising three-dimensional coordinates, wherein at least one cell stores a formula having a cell address for referencing information stored by another cell, an improved method for creating a formula with cell references to information cells in said three-dimensional spreadsheet, the method comprising:

memory and a graphics adapter, said system memory having a page mode, said method comprising:

- storing a plurality of characters in said system memory as a plurality of glyph bitmaps, wherein each character has a width and wherein each glyph bitmap for a character is arranged as a column of scanlines such that each scanline within said column of scanlines includes said width of said character; and
- transmitting selected ones of said plurality of glyph bitmaps from said system memory to said graphics adapter, wherein an occurrence of breaks in said page mode are minimized when said glyph bitmap is moved from said system memory to said graphics adapter, increasing efficiency in displaying characters on a display.

G) based on the correspondence, processing at least one of the source and target images or generating at least one intermediate image therebetween.

5,590,262

INTERACTIVE VIDEO INTERFACE AND METHOD OF CREATION THEREOF


Anthony J. Isadore-Barreca, Oakland, Calif., assignor to Magic Circle Media, Inc., San Jose, Calif.

Filed Nov. 2, 1993, Ser. No. 146,964

Int. Cl.⁶ G06T 1/00

U.S. Cl. 395—806

10 Claims



FINITE-ELEMENT METHOD FOR IMAGE ALIGNMENT AND MORPHING


Stanley E. Sclaroff, Boston, and Alex Pentland, Cambridge, both of Mass., assignors to Massachusetts Institute of Technology, Cambridge, Mass.

Filed May 7, 1993, Ser. No. 59,449

Int. Cl.⁶ G06T 7/00

U.S. Cl. 395—173

18 Claims



1. A method of processing images by determining a point in a target image comprising electronically encoded target points that corresponds to a given point in a source image comprising electronically encoded source points, the method comprising the steps of:

- defining first and second simulated elastic bodies associated with the source and target images, respectively, each body comprising body points which include nodal points;
- identifying source and target feature points among the source and target points, respectively;
- for each of the images, computing the mode shapes of the modes of collective motion of nodal points of the body associated with that image and whose positions with respect to each other are the same as those of the feature points in the associated image, each of said mode shapes being an eigenvector comprising eigenvector components, each eigenvector component being associated with a different nodal point and representing the relative participation of that nodal point in the mode to which the eigenvector corresponds, and thereby associating with each feature point a generalized feature vector whose components represent the participations as embodied in the eigenvector components, of that feature point's associated nodal point in respective modes;
- assigning to each of a plurality of the source feature points a target feature point associated with a generalized feature vector whose difference from that associated with that source feature point is sufficiently small according to a predetermined criterion;
- determining a mapping function of source points to target points in accordance with the relationships between the target feature points to which source feature points are assigned and the points to which the mapping function maps those same feature points;
- identify the point in the target image that corresponds to the given source point by applying the mapping function to the given source point; and

6. In a computer having a video display, an interactive video computer/user interface, comprising:

a live action video presentation having a plurality of frames, the plurality of frames being divided into a plurality of sequences;

a resource database layer having therein a plurality of resource items, each of the resource items being an item of information available to the user; and

a library program portion for causing the computer to display a specific one of a plurality of key frames of said video presentation when said video presentation is stopped by the user at any of the frames, and further for defining a plurality of hot spots within the key frames, the hot spots designating those portions of the key frames about which additional information is available, and further for linking each of said hot spots with a specific one of the resource items such that, when the user selects one specific hot spot, then the specific resource item designated as being associated with that hot spot is presented to the user on the video display.

5,590,263

Patent Not Issued For This Number

5,590,264

METHOD AND APPARATUS FOR GRAPHIC ASSOCIATION OF USER DIALOG DISPLAYS WITH PRIMARY APPLICATIONS IN A DATA PROCESSING SYSTEM

Patrick J. Keane, Grapevine, Tex., and Justin J. C. Richards, Warwick, United Kingdom, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 10, 1991, Ser. No. 683,381

Int. Cl.⁶ G06F 3/00


U.S. Cl. 395—340

5 Claims

1. A method of managing a computer display system having a graphic pointing device, a plurality of simultaneously active software applications displayed therein and one or more common user dialogs which are displayable within separate windows within said computer display system and wherein each common user dialog may be displayed in association with multiple ones of said plurality of simultaneously active software applications, said method comprising the steps of:

creating a unique miniature graphic representation for each of said plurality of software applications;

displaying said unique miniature graphic representation for a selected software application within a window display of a common user dialog displayed in association with said



selected software application in response to a displaying of said common user dialog wherein a user may readily determine which selected software application is associated with said displayed common user dialog upon reference to said unique miniature graphic representation; and displaying a graphic identification of said selected software application in response to a selection of said unique miniature graphic representation utilizing said graphic pointing device.

5,590,265

SYSTEM WHICH CAN DISPLAY MULTIWINDOWS AND ITS WINDOW DISPLAY METHOD

Toshiyuki Nakazawa, Kawasaki, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Jul. 23, 1993, Ser. No. 95,218

Claims priority, application Japan, Jul. 27, 1992, 4-219750

Int. Cl.⁶ G06F 3/14

U.S. Cl. 395—340

4 Claims



1. A system which can display multiwindows, comprising: window information memory means for storing a content and a display position of each of a plurality of windows and a higher/lower hierarchy among the windows; first display control means for allowing the plurality of windows to be displayed on a same screen in a manner such that the content of a window with a higher hierarchy is displayed to overlap two or more windows of a lower hierarchy based on information stored in said window information memory means; instructing means for providing instructions to display the windows in a transparent state in which the plurality of windows are displayed on the same screen by said first display control means; and second display control means, which operates in response to the instructions of said instructing means, for allowing each window, except for contents within frames of the windows, to be displayed based on the hierarchy information stored in said window information memory means in a manner such that frames of lower hierarchy windows are overlapped by frames of higher hierarchy windows and are displayed with a title bar

including a window name on the basis of a higher/lower hierarchy among the windows stored in said window information memory means.

5,590,266

INTEGRITY MECHANISM FOR DATA TRANSFER IN A WINDOWING SYSTEM


Mark E. Carson; Mudumbai Ranganathan, both of Montgomery County, and Janet A. Cugini, Walkersville, all of Md., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Oct. 11, 1994, Ser. No. 321,644

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—340

8 Claims



1. A regrading selection mechanism for a secure windowing system comprising: a plurality of client programs running in separate window on said windowing system, each of said programs displaying data within its window; a client called a Selection Manager for cutting and pasting operations to transfer data from one client program window to another client program window, the Selection Manager meeting Compartmented Mode Workstations (CMW) requirements and sending events to applications to notify the application of any changes in state, said Selection Manager manipulating ownership and other security properties of data being transferred to allow a controlled verifiable data transfer to take place; wherein the windowing system uses dummy window identifications (IDs) in communicating to a lower level process during a Mandatory Access Control (MAC) upgrade operation.

5,590,267

METHOD AND SYSTEM FOR SCALABLE BORDERS THAT PROVIDE AN APPEARANCE OF DEPTH

Laura J. Butler, Bellevue, and Joyce A. Grauman, Seattle, both of Wash., assignors to Microsoft Corporation, Redmond, Wash.

Division of Ser. No. 62,845, May 14, 1993, Pat. No. 5,452,406.

This application Jun. 5, 1995, Ser. No. 462,523


Int. Cl.⁶ G09G 3/00

U.S. Cl. 395—340

7 Claims

1. In a data processing system having memory means holding system metrics, a processor that produces a user interface and an output device with a resolution of a number of horizontal dots per inch and a number of vertical dots per inch, a method comprising the steps of:

- determining with the processor a minimum border width for each border in the user interface for the border to be sufficiently visible, based on the resolution of the output device, each border having vertical edges and horizontal edges;
- determining with the processor a minimum border height for each border in the user interface for the border to be sufficiently visible, based on the resolution of the output device;



- drawing the vertical edges of the borders in the user interface to have the minimum border width and drawing the horizontal edges of the borders to have the minimum border height;
- storing the minimum border height and the minimum border width in the memory means as system metrics;
- scaling other system metrics to have scaled values that are proportional to the minimum border height or the minimum border width; and
- storing the other system metrics in the memory means.

5,590,268

SYSTEM AND METHOD FOR EVALUATING A WORKSPACE REPRESENTED BY A THREE-DIMENSIONAL MODEL

Miwako Doi; Mika Fukui; Ikiko Nishida, and Nobuko Kato, all of Kanagawa-ken, Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Mar. 30, 1994, Ser. No. 220,180

Claims priority, application Japan, Mar. 31, 1993, 5-074716

Int. Cl.⁶ G06F 3/00; G06T 17/00

U.S. Cl. 395—326

39 Claims



1. A system for evaluating a virtually produced workspace wherein various objects are arranged, by causing a predetermined operator model to conduct a motion in said workspace, said system comprising:

- first setting means for setting a sequence in which said operator model conducts a motion in said workspace, and for setting objects at which said operator model is to gaze when said operator model conducts a motion in accordance with said sequence; and
- display means for visibly displaying on a screen a visual field area of each of said objects which is set by said first setting means, a visual field area being defined when said operator model gazes at an object which is set.

5,590,269

RESOURCE ASSIGNMENT SYSTEM PROVIDING MIXED-INITIATIVE USER INTERFACE UPDATES


John M. Kruse, Minneapolis, Minn.; John E. Collins, Hudson, Wis., and Elizabeth M. Sisley, Woodbury, Minn., assignors to Minnesota Mining & Manufacturing Company, St. Paul, Minn.

Filed Apr. 22, 1994, Ser. No. 231,031

Int. Cl.⁶ G06F 15/00; 7/00

U.S. Cl. 395—209

31 Claims



29. A computer-implemented system for assigning a plurality of resource requests among a plurality of resource providers, said system comprising:

- an assignment database for storing an assignment set, said assignment set defining assignment of one or more of said resource requests among said resource providers;
- a user interface for displaying a representation of at least part of said assignment set, and for receiving input from a system user; and
- an update module for receiving changes to said assignment set, and for updating said user interface to display a representation of each of said changes to said assignment set, said update module including means for selecting one of a plurality of update modes, said plurality of update modes including: an assertive mode wherein said update module updates said user interface in response to receipt of each of said changes to said assignment set, and an update-on-delay mode wherein said update module updates said user interface in response to a combination of said receipt of each of said changes and an elapse of a time delay from a time of said receipt of each of said changes.

5,590,270

METHOD AND APPARATUS FOR DETECTING A LOWER LEVEL SOFTWARE REUSABLE PRODUCT IN GENERATING AN UPPER LEVEL SOFTWARE PRODUCT FROM A LOWER LEVEL SOFTWARE PRODUCT AND CHANGING THE UPPER LEVEL SOFTWARE PRODUCT

Gunji Tsukuda, Kawasaki; Ichiro Naito, Tokyo; Hirofumi Danno, Yokohama; Kazutoshi Tamura, Yokohama; Hiroshi Tsukino, Yokohama; Hideo Kamiko, Yokohama; Hirokazu Mimura, Yokohama; Akiko Fukuya, Dazaifu, and Hiroyuki Maezawa, Tama, all of Japan, assignors to Hitachi, Ltd.; Hitachi System Engineering, Ltd., both of Tokyo, and Hitachi Software Engineering Co. Ltd., Yokohama, all of Japan

Continuation of Ser. No. 791,484, Nov. 12, 1991, abandoned.

This application Feb. 21, 1995, Ser. No. 392,025

Claims priority, application Japan, Nov. 14, 1990, 2-308297


Int. Cl.⁶ G06F 17/50; 17/30

U.S. Cl. 395—701

9 Claims

1. A reverse engineering method of supporting software reuse in generating an upper level software product from a lower level software product by reusing some software product among multi-level software products ranging from an upper level data flow to a lower level job flow, comprising the steps of:

- inputting a plurality of lower level software products each having a job name, at least one program name, at least one file



name, and at least one arrow connecting said at least one program name with said at least one file name; generating an upper level software product having program names, file names, and arrows connecting said program names and file names of a plurality of lower level software products, said lower level software products connected to one another at a place where there is a common file name in any of the plurality of lower level software products, said upper level software product having a sheet name; generating relational information including the same sheet name and job names included in any of said connected plurality of lower level software products; displaying said upper level software product on an input/output interface; inputting a request for changing a part of said upper level software product via said input/output interface; changing said part of said upper level software product displayed on said input/output interface in response to said change request; detecting information of a sheet name and a job name representing a reusable field of said lower level software product included in said upper level software product not changed in said changing step and detecting information of a sheet name and a job name corresponding to a content which was changed in said changing step, in response to a change of said upper level software product; and providing a user with the detected information with the sheet names and the job names by outputting the detected information to a printer or screen.


5,590,271

INTERACTIVE VISUALIZATION ENVIRONMENT WITH IMPROVED VISUAL PROGRAMMING INTERFACE
 Gudrun J. Klinker, Westborough, Mass., assignor to Digital Equipment Corporation, Maynard, Mass.
 Continuation of Ser. No. 66,187, May 21, 1993, abandoned.
 This application Jan. 16, 1996, Ser. No. 585,810

Int. Cl.⁶ G06F 3/00

U.S. Cl. 395—326

17 Claims



1. A method for enhancing user interaction with an output image displayed on a computer screen, said output image having been

derived by means of at least one transformation of a source image, said method comprising the steps of:

constructing a dataflow network comprising a plurality of interconnected icons on the screen, said icons representing executable software modules including a first module for acquiring said source image, a second module for applying a transformation to said source image and a third module for displaying said output image;

executing said modules to display said output image on the screen;

providing user parameters to said third module through cursor positioning events to relative to said displayed output image;

transferring said user parameters from said third module directly to said second module; and

modifying said source image by said second module in response to said transferred user parameters so as to provide a corresponding modification to said displayed output image, thereby enhancing user interaction with said output image.

5,590,272

METHOD AND SYSTEM FOR A HIGH-RELIABLE DISK SYSTEM

Tomohiro Murata, Yokohama; Kenzo Kurihara, Tokyo; Kazuhiro Kawashima, Yokohama, and Mitsuaki Niida, Kanagawa-ken, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Dec. 21, 1992, Ser. No. 993,394

Claims priority, application Japan, Dec. 26, 1991, 3-357579

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—181

4 Claims



1. A defect recovery method comprising:

providing a disk system having a disk controller for controlling and maintaining tracks on a recording medium and copying data among the tracks, the disk controller including an internal storing means, a track dividing means, a track selecting means, a defect identifying means, a defect counting means, a comparing means, a data writing means, a data reading means and a drive;

with said disk controller track divider means, dividing tracks on said recording medium into: (i) a current track group directly available to an external computer and (ii) a spare track group available to said disk controller;

storing an identification of the tracks in the current track group and the spare track group in the disk controller internal storing means;

with said disk controller track selecting means, automatically selecting a track in said spare track group as an alternative track;

selecting a current track from the current track group with the disk controller track selecting means;

if said selected current track has data recorded thereon, identifying defects in data recorded on the selected current track with the disk controller defect identifying means;

with said disk controller defect counting means, counting a number of identified defects on the selected current track;

comparing the counted number with a threshold value with said disk controller comparing means;

in response to the counted number being greater than the threshold value, with said disk controller data writing means, copying the data recorded on said selected current track to said alternative track;

after copying the recorded data from the selected current track to the alternative track, with said disk controller data writing means writing prepared diagnostic data onto said selected current track;

with said disk controller data reading means, reading the prepared diagnostic data written on said selected current track; with the defect identifying means identifying any defect positions on said selected current track;

storing each identified defect position in the internal storage means; and

with said disk controller data writing means, copying the data from said alternative track back to said selected current track, without recording in the identified defect positions.

2. A defect recovery system comprising:

a disk system having a disk controller for controlling and maintaining tracks on a recording medium and copying data among the tracks, the disk controller including:

a track divider means for dividing tracks on said recording medium into: (i) a current track group directly available to an external computer and (ii) a spare track group available to said disk controller;

a track selecting means for automatically selecting one of (i) a track in said spare track group as an alternative track and (ii) a current track from the current track group;

a defect identifying means for identifying any defects in data recorded on the selected current track and a position of each identified defect on the selected current track;

an internal storage means for storing (i) an identification of the tracks in the current track group and the spare track group and (ii) storing each identified defect position;

a defect counting means for counting a number of identified defects on the selected current track;

a comparing means for comparing the counted number of identified defects with a threshold value;

a data writing means for (i) copying the data recorded on said selected current track to said alternative track in response to the counted number of identified defects being greater than the threshold value, (ii) writing prepared diagnostic data onto said selected current track, after copying the data from the selected current track to the alternative track, and (iii) copying the data from said alternative track back to said selected current track, without recording in the identified defect positions; and

a data reading means for reading the prepared diagnostic data written on said selected current track.

5,590,273

MICROCONTROLLER INTEGRATED CIRCUIT WITH READ ONLY MEMORY CONTAINING A GENERIC PROGRAM

Jean-Pierre Balbinot, Le Kremlin-Bicetre, France, assignor to Alcatel Mobile Communication France, Paris, France
 Continuation of Ser. No. 272,073, Jul. 8, 1994, abandoned.

This application Jan. 30, 1996, Ser. No. 593,283

Claims priority, application France, Jul. 13, 1993, 93 08626

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—182.01

20 Claims

17. A microcontroller-based system comprising:


a microcontroller having a processor core and a read only memory; and

a storage device;

said processor core being adapted to exchange data with said storage device;

said read only memory containing a generic program which is executable by said processor core;

said generic program including a writing function for writing a downloading program into said storage device;



said downloading program including a function for downloading an application program into said microcontroller-based system; said storage device containing said downloading program stored under control of said generic program; and said microcontroller-based system containing said application program stored under control of said downloading program.

5,590,274

MULTI-VOLUME AUDIT TRAILS FOR FAULT TOLERANT COMPUTERS


Michael J. Skarpelos, San Jose; Robbert van der Linden, Scotts Valley; William J. Carley; James M. Lyon, both of San Jose, all of Calif., and Matthew C. McCline, Bellevue, Wash., assignors to Tandem Computers Incorporated, Cupertino, Calif.

Filed Jan. 23, 1995, Ser. No. 377,075

Int. Cl.⁶ G06F 11/34

U.S. Cl. 395—182.05

3 Claims



3. In a fault tolerant computing system having an audit generator, and a plurality of audit trail storage processes, wherein said audit trail storage processes are for storing audit records generated by said audit generator in audit files accessible to said audit storage processes, wherein as successive audit files become full, current responsibility for storing audit records generated by said audit generator is transferred by sending a message from a previously responsible audit trail storage process to a newly responsible audit trail storage process, wherein successively used audit files are assigned unique sequence numbers in order, and wherein each audit trail storage process stores a sequence number identifying a last known audit file employed by one of said audit trail storage processes for storing audit records, a fault tolerant method for processing messages received at a first audit trail storage process, wherein said first audit trail storage process operates as if it were already the responsible audit trail storage process, said method comprising the steps of:

a) receiving, at said first audit trail storage process, a message from a second audit trail storage process, said message including an audit file sequence number of a next audit file for receiving audit records;

b) extracting, at said first audit trail storage process, said audit file sequence number from said message;

c) comparing said received audit file sequence number to the last known audit file sequence number stored in said first audit trail storage process; and

d) upon a determination in said c) step that said received audit file sequence number is greater than the stored last known audit file sequence number, 1) closing the audit file identified

by the audit file sequence number stored by the audit file sequence number stored within said first audit storage process and 2) opening a new audit file identified by said sequence number included within said message for receiving audit records from said first audit trail storage process.

5,590,275

METHOD FOR TESTING AN INTEGRATED CIRCUITRY AND AN INTEGRATED CIRCUIT HAVING A PLURALITY OF FUNCTIONAL COMPONENTS AND HAVING JUNCTION/SWITCH TEST COMPONENTS IN INTERCONNECTING CHANNELS BETWEEN FUNCTIONAL COMPONENTS

Cornelis H. Van Berkel; Maria E. Roncken, and Ronald W. J. J. Saeljs, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Continuation of Ser. No. 16,409, Feb. 11, 1993, abandoned.


This application Feb. 14, 1995, Ser. No. 389,083

Claims priority, application European Pat. Off., Feb. 18, 1992, 92200455


Int. Cl. G06F 11/34

U.S. Cl. 395—183.06

31 Claims



wherein, when one of said address data demultiplexing circuits detects that one of said address data multiplexing circuits has written into said FIFO memory, said one of said address data demultiplexing circuits performs read accessing of the FIFO memory and reads the address information, the data and the identification bit written in said FIFO memory; and when the identification bit represents address information, the address data demultiplexing circuit stores the address information in an address register in the address data demultiplexing circuit; and when the identification bit represents data, the address data demultiplexing circuit interrupts the read accessing of the FIFO memory while the address data demultiplexing circuit stores the data into a data register in the address data demultiplexing circuit, and then the address data demultiplexing circuit transfers the stored data and address information from the respective registers into the main storage apparatus of the other one of said first and second systems.



5,590,280

METHOD AND AN APPARATUS FOR RESETTING AN INFORMATION RECORDING APPARATUS Hiroshi Watanabe, Kawasaki, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Sep. 16, 1994, Ser. No. 306,950

Claims priority, application Japan, Sep. 24, 1993, 5-237731

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—185.08

16 Claims



1. A reset apparatus comprising:
 - detecting means for generating a detection result corresponding to a predetermined signal received from an external device;
 - determining means, including counting means, for counting a period of time during which the predetermined signal is continuous based on the detection result, and for generating a reset enable signal when the period of time counted is longer than a predetermined period of time;
 - checking means for checking whether the predetermined signal is output from the external device, said check being performed in response to the enable signal generated by the determining means; and
 - controlling means for executing a signal process corresponding to the predetermined signal when the checking means checks that the predetermined signal is output from the external device after the predetermined period of time has elapsed.

5,590,281

ASYNCHRONOUS BIDIRECTIONAL APPLICATION PROGRAM PROCESSES INTERFACE FOR A DISTRIBUTED HETEROGENEOUS MULTIPROCESSOR SYSTEM

Bruce W. Stevens, North Kingstown, R.I., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Oct. 28, 1991, Ser. No. 783,661

Int. Cl.⁶ G06F 15/16

U.S. Cl. 395—200.01

14 Claims

1. For use in a multiprocessing system in which plural and heterogeneous processors perform distributed processing, a sub-

system for interfacing component processes of application programs resident in different ones of the plural heterogeneous processors, which subsystem for interfacing asynchronously and bidirectionally enables processing in one and another of at least two heterogeneous processors of the plurality as though the distributed processing was performed under run control of a unitary, undistributed application program, said heterogeneous one and another processors differing by having at least one difference characteristic from among (A) plural, predetermined data representation format characteristics of the plural processors and (B) plural, predetermined different processor architecture characteristics dependent ways of using component processes of an application program, said plural processors being interconnected for multiprocessing by an interprocessor communication subsystem in which signals are borne by a hardware interconnection means, said subsystem for interfacing application program processes comprising:

cross-processor-tasking-of-application-program-components-layer-means residing in the application program level of software hierarchy coupled to a selected processor, which cross-processor-tasking-layer-means is operative to enable one task asynchronous to one component process run by one processor of one heterogeneous kind to use another component task asynchronous to another process run by another processor of another heterogeneous kind in such a way that the fact that the another task is being run by the another processor is transparent to the using processor as if the distributed processing is being performed under run control of a unitary, undistributed application program;

presentation-layer-means residing in the application program level of software hierarchy which is cooperative with the cross-process-tasking-of-application-program-components-layer-means for converting data from the data representation format characteristic of the one processor whose component process is to use the another component process to another data representation format characteristic corresponding to the another processor whose component process is being run thereby and for determining which of plural, predetermined ways the used component process is to be used;

connections-and-task-transport-layer-means in part residing in the application program level of software hierarchy and in part facilitated by the hardware interconnection means of the interprocessor communications subsystem, which connections-and-task-transport-layer-means is cooperative with both the cross-processor-tasking-of-application-program-components-layer-means and the presentation-layer-means for providing a network virtual circuit between sockets defined between the processes borne by the distributed processors and for providing sending and receiving tasks along the network

virtual circuit between the sockets of the several processes thereof thereby facilitating execution of the component processor application programs resident in different and heterogeneous processors as though a unitary, undistributed application program were being executed, the hardware interconnection means providing the communication path facilitating unification of execution of the component processes in the separately resident application programs; and data-and-usage-determined-information-transport-layer-means resident in the application program level of software hierarchy cooperative with the connections-and-task-transport-layer-means for providing data reads and data writes of data representation-format-converted and usage-determined information along the network virtual circuit by the sending and receiving tasks between the sockets of the network virtual circuit.

5,590,282

REMOTE ACCESS SERVER USING FILES CONTAINING GENERIC AND SPECIFIC MUSIC DATA FOR GENERATING CUSTOMIZED MUSIC ON DEMAND


Manfred Clynes, 19181 Mesquite Ct., Sonoma, Calif. 95476

Filed Jul. 11, 1994, Ser. No. 272,849

Int. Cl.⁶ G06F 13/00; G10F 1/00

U.S. Cl. 395—200.02

13 Claims



1. A music information highway comprising:

A. a central computer station having a first memory file in which is stored a library of different music scores, each score being defined by the nominal notation of a particular music composition including the pitch and duration of each tone, the station including a stored source of sounds and means coupled to the source to play and reproduce the tones of a score selected from the first file;

B. a second memory file which is a matrix having stored therein microstructures related to the relative loudness and duration values of a series of notes, said stored different microstructures each adapted to modify the nominal notation of a selected score including the duration and amplitude of the notes to impart expressivity to the reproduced score; and

C. a plurality of subscriber posts coupled by an interactive network to said station, each post having means to select from the first file for reproduction by the station a particular means to select from the first file for reproduction by the station a particular score and to select from the second file a microscore modifying the nominal notation of the selected score so that the selected music composition, played expressively, can be heard at the post.

5,590,283

PARALLEL COMPUTER SYSTEM WITH PHYSICALLY SEPARATE TREE NETWORKS FOR DATA AND CONTROL MESSAGES


W. Daniel Hillis, Cambridge; David C. Douglas, Concord; Charles E. Leiserson, Winchester; Bradley C. Kuszmaul, Waltham, all of Mass.; Mahesh N. Ganmukhi, Wexford, Pa.; Jeffrey V. Hill, San Jose, Calif., and Monica C. Wong-Chan, Cambridge, Mass., assignors to Thinking Machines Corporation, Bedford, Mass.

Division of Ser. No. 183,219, Jan. 14, 1994, Pat. No. 5,388,214, which is a continuation of Ser. No. 592,029, Oct. 3, 1990, abandoned. This application Jan. 27, 1995, Ser. No. 380,854

Int. Cl.⁶ G06F 15/163; 15/173

U.S. Cl. 395—200.02

5 Claims



1. A digital computer comprising

A. a plurality of processing elements each performing data processing operations in connection with commands, at least some of the processing elements performing said data processing operations in connection with said commands which they receive in control network messages, each processing element also (i) generating and receiving data transfer messages, each including an address portion containing an address, for transfer to another processing element as identified by the address and (ii) at least one of said processing elements further generating said control network messages and (iii) said at least some processing elements receiving said control network messages;

B. a communications router comprising a plurality of router node groups interconnected in a tree pattern in a series of levels from a lower leaf level to an upper root level, and each node group in levels above the leaf level including a plurality of router nodes, with router nodes in levels below the root level being connected to a plurality of router nodes in the next higher level thereby forming a fat-tree structure, each node receiving data transfer messages and coupling them to another node or to a processing element connected thereto as determined by the address in the respective address portion; and


C. a control network comprising a like plurality of control network node groups interconnected in a like tree pattern in a series of levels from a lower leaf level to an upper physical root level, each control network node group below the upper root level receiving control network messages from a processing element or a lower-level control network node group and generating a control network message in response thereto for transmission to a higher-level control network node group, and receiving control network messages from a higher level control network node group and generating control messages in response thereto for transmission to lower-level control network node groups, the control network node group at the root level generating control network messages for transmission to the lower level control network node groups in response to control network messages received therefrom.

5,590,284 PARALLEL PROCESSING DATA NETWORK OF MASTER AND SLAVE TRANSPUTERS CONTROLLED BY A SERIAL CONTROL NETWORK

Dario B. Crosetto, DeSoto, Tex., assignor to Universities
Research Association, Inc., Washington, D.C.
Continuation of Ser. No. 856,622, Mar. 24, 1992, abandoned.
This application Sep. 26, 1994, Ser. No. 312,435
Int. Cl. G06F 15/16

U.S. Cl. 395—200.05

14 Claims



1. A parallel data transfer network for the transfer of data controlled by a serial communication network to effect direct point to point communication between processing nodes arranged in an n-dimensional array, independent of physical or logical location of the processing nodes within the array, said parallel data transfer network comprising:

- a plurality of processing nodes, each adapted for processing, sending and receiving data and commands; one of said nodes acting as a master node and at least one of said nodes acting as a slave node; each processing node further comprising a transputer connected to (i) at least one serial link for serial transmission of commands to and from the processing node, (ii) at least one memory for retaining data being transferred to and from the processing node, and (iii) a switch connecting the at least one memory, through at least one parallel data bus, to a hardware parallel channel for transmission of data to and from the processing node;
- a plurality of serial links connecting at least two of said processing nodes for the serial transmission of commands between said at least two processing nodes;
- a parallel hardware channel connected to said processing nodes by a plurality of parallel data buses for the transmission of data between said processing nodes in response to the commands serially transmitted over the serial links; and
- a plurality of parallel data buses, each parallel data bus connecting one of said processing nodes to the parallel hardware channel.

5,590,285 NETWORK STATION WITH MULTIPLE NETWORK ADDRESSES


Jeffrey Krause, Los Altos; Niles E. Strohl, Tracy; Michael J. Seaman, San Jose; Steven P. Russell, Menlo Park, and John H. Hart, Saratoga, all of Calif., assignors to 3Com Corporation, Santa Clara, Calif.
Continuation of Ser. No. 98,616, Jul. 28, 1993, abandoned.
This application Aug. 9, 1995, Ser. No. 513,167
Int. Cl. G06F 13/00

U.S. Cl. 395—200.20

11 Claims

1. A network interface control apparatus for connection of a data processing system including a plurality of processing modules to a network transmission medium in a network, the network having a physical layer and a data link layer comprising:

- a connector to transport data to and from the network transmission medium; and
- a medium access control device in the data link layer, coupled to the connector, to receive and transmit frames of data through the connector, the medium access control device including:



a plurality of data channels to communicate between the network transmission medium through the connector and respective processing modules in the data processing system, each channel in the plurality of data channels having an assigned data link layer address;

memory to store the assigned data link layer addresses for the plurality of data channels; and

address filtering logic, coupled to the plurality of data channels and the memory, which passes and blocks frames received through the connector in response to the assigned data link layer addresses on the corresponding data channels in the plurality of data channels;


a media arbitration circuit coupled between the connector and the medium access control device, which supplies to the address filtering logic frames of data which are received through the connector from the network transmission medium, and receives from the plurality of data channels, frames of data which are to be transmitted to the network transmission medium from the plurality of data channels.

5,590,286 METHOD AND APPARATUS FOR THE PIPELINING OF DATA DURING DIRECT MEMORY ACCESSES

Peter A. Mehrling, Sunnyvale, and Cau L. Nguyen, Milpitas, both of Calif., assignors to Sun Microsystems, Inc., Mountain View, Calif.
Filed Oct. 7, 1993, Ser. No. 131,970
Int. Cl. G06F 13/38

U.S. Cl. 395—250

17 Claims



1. In a system comprising a processor component coupled to an external bus, and an external device coupled to the external bus, an apparatus for transferring data from the external device across the external bus to main memory coupled to the processor component

by a high speed memory bus, said external bus operating at a first clock speed and said memory bus operating at a second clock speed faster than the first clock speed, said apparatus comprising:

an external bus controller coupled to the memory bus and the external bus for communicating data between the processor component and the external device coupled to the external bus, said bus controller communicating data across the external bus at the speed of the first clock and communicating data across the memory bus at the speed of the second clock, said external controller comprising:

a buffer for temporarily storing data communicated from/to the external device pursuant to a write/read operation to be performed, said data stored in the buffer in accordance with the speed of the second clock;

a first communication path for communicating data between the external bus controller and the external bus at the rate of the first clock;

a second communication path for causing the communication of data between the buffer and the memory bus at the rate of the second clock;

a transfer controller which detects a determined number of words stored in the buffer and causes the completion of the operation with respect to the buffered data while the remaining data to be transferred pursuant to the operation is transferred to the buffer;


wherein said external bus controller continues to buffer remaining data of the operation and complete the operation with respect to the buffered data such that delay incurred by waiting for the data to be communicated to the external bus controller prior to transferring the data to complete the operation is minimized.

5,590,287 CONFIGURABLE INTERFACE FOR ROUTING DATA BETWEEN MISMATCHED DEVICES

Charles P. Zeller, Austin; Terry J. Parks, Round Rock, and Michael D. Durkin, Austin, all of Tex., assignors to Dell USA, L.P., Austin, Tex.
Continuation of Ser. No. 559,872, Jul. 27, 1990, abandoned.
This application Mar. 7, 1994, Ser. No. 207,810
Int. Cl. G06F 9/315; 13/40

U.S. Cl. 395—250

37 Claims



1. A digital computer system having a data interface for transferring fixed word length data units output by an 8, 16 or 32 bit wide I/O device to a 32 bit wide data bus by accumulating said 8, 16 or 32 bit wide fixed word-length data units output by said I/O device into a 32 bit data word, comprising:

configurable first, second, third and fourth latches, each of said latches having an input and an output;

configurable means for separately routing a first, second, third and fourth data byte output from said I/O device to the input of said first, second third and fourth latches, respectively

wherein said means further comprises means for selectively routing said first, second, third and fourth data byte outputs;

configurable means for accumulating said 32 bit data word from each of said latch output;

means for generating a code representing a fixed word-length data routing command said codes selectively configuring said latches routing means and accumulating means to route fixed word-length data as a function of data bus width, said code embodied as a set of bused signals generated by a bus controller to thereby permit devices communicating by buses of different width to communicate with each other without requiring circuitry other than said bus controller; and


means for transmitting said accumulated 32 bit data word to said data bus.

5,590,288 DISTRIBUTED DATA PROCESSING SYSTEM AND METHOD UTILIZING PERIPHERAL DEVICE POLLING AND LAYERED COMMUNICATION SOFTWARE

Patrick F. Castor, Naperville; Yung-Chun Tsau, Oak Brook, both of Ill.; Inge B. Kristiansen, Pasadena, Calif., and John W. Nelson, Chicago, Ill., assignors to Restaurant Technology, Inc., Oak Brook, Ill.
Continuation of Ser. No. 738,084, Jul. 30, 1991, abandoned.
This application Mar. 13, 1995, Ser. No. 402,810
Int. Cl. G06F 13/37; 13/372

U.S. Cl. 395—200.03

13 Claims



1. A distributed data processing system, comprising:

- network means for enabling electronic communication;
- a plurality of computers, each of which comprises a processor, a memory and a plurality of peripheral devices;
- layered software means for enabling each of said plurality of computers to send and receive data, procedure calls and function calls through said network means, said layered software means residing in the memory of each of said plurality of computers and including remote procedure calling software means for creating a request block to service a request from one of said peripheral devices;

(d) a plurality of predetermined computer procedures located in said memories of said computers for processing data inputted from said plurality of peripheral devices and means for enabling each of said procedures to call said layered software means;

(e) polling software means residing in the memory means of each of said plurality of computers for successively polling said plurality of peripheral devices attached to said computer to determine whether a request is pending from said peripheral device and said computer including means for servicing said request, prior to said computer polling its next peripheral device, by calling a procedure located in said memory of said computer or, when said computer does not have the procedure in its memory by calling said remote procedure calling software means to request another of said computers to call a procedure located in the memory of that computer to service said request prior to polling the next peripheral device; and

(f) processing means, comprising the processor of each of said computers, for processing input data from said peripheral devices, said processing means being controlled by said layered software means and said polling software means;

wherein each said plurality of peripheral devices includes at least one interface adapter as one of said peripheral devices for electronically connecting said processing means to said network means.

5,590,289

METHOD AND APPARATUS FOR INITIALIZING A COMPUTER SYSTEM HAVING CENTRAL AND DISTRIBUTED ADDRESS DECODE MEMORY BUS RESOURCES

Joseph M. Nardone; Michael J. McTague, both of Portland, and Howard S. David, Beaverton, Oreg., assignors to Intel Corporation, Santa Clara, Calif.


Continuation of Ser. No. 151,535, Nov. 12, 1993, abandoned.

This application Jan. 31, 1995, Ser. No. 384,472

Int. Cl.⁶ G06F 13/14

U.S. Cl. 395—289

18 Claims



1. In a computer system having a memory bus, a processing unit coupled to said memory bus, wherein said memory bus supports a first plurality of memory bus resources that require centralized address decoding and to a second plurality of memory bus resources which are capable of distributed address decoding, a method of initializing said computer system comprising the steps of:

- providing said computer system with decoding logic coupled to said memory bus, said decoding logic being compatible with said memory bus having both centrally decoded memory bus resources and distributed decode memory bus resources, said memory bus providing select lines between said decoding logic and said memory bus resources;
- polling each of said memory bus resources coupled to said memory bus to determine whether each is a centrally decoded resource or a distributed decode resource;
- dynamically orienting the memory bus select lines such that select lines are driven to said centrally decoded resources by said decoding logic and are driven to said decoding logic by said distributed decode resources; and
- maintaining information in said decoding logic identifying which addresses propagated by said processing unit over said memory bus are directed to said centrally decoded resources.

5,590,290

METHOD FOR CONTROLLING A BUS TO PROGRESS TRANSFER CYCLES WITHOUT INSERTING A CYCLE FOR ACKNOWLEDGEMENT

Nobukazu Kondo, Ebina; Seiji Kaneko, Yokohama; Hideaki Gemma, Hadano; Tetsuhiko Okada, Hachioji; Kazuhiko Komori, Ebina, and Koichi Okazawa, Tokyo, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Division of Ser. No. 60,055, May 13, 1993, Pat. No. 5,428,753.

This application Jun. 7, 1995, Ser. No. 487,401


Claims priority, application Japan, May 15, 1992, 4-123569

Int. Cl.⁶ G06F 3/04

U.S. Cl. 395—298

21 Claims

1. An information processing system comprising:
- a bus for transmitting an address and/or data;
 - a plurality of modules connected to the bus; and
 - an acknowledge bus line, separate from said bus, to be used for transmitting an acknowledge report, said acknowledge bus line being connected to said plurality of modules;
- a master module which acquires a mastership of the bus, controls the bus and transfers an address and/or data to a slave module being a transfer destination, and releases the master-



ship of the bus after transmitting of an address and/or data to said slave module via said bus; wherein said slave module which had received the transferred address and/or data as said slave, transmit an acknowledge report on said acknowledge bus line after receipt of the transferred address and/or data; and said master module which had transferred address or data as said master, confirms whether or not an executed transferring of address or data was successful upon receipt of said acknowledge report after releasing said mastership of the bus.

5,590,291

DIGITAL SIGNAL PROCESSING SYSTEM FOR LIMITING A RESULT TO BE PREDETERMINED BIT COUNT


Tokumichi Murakami, and Hideo Ohira, both of Kanagawa, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 807,510, Dec. 16, 1991, abandoned, which is a continuation of Ser. No. 483,840, Feb. 23, 1990, Pat. No. 5,130,797. This application Jan. 4, 1993, Ser. No. 562 Claims priority, application Japan, Feb. 27, 1989, 1-45632; Mar. 31, 1989, 1-81851; May 29, 1989, 1-132646; Oct. 16, 1989, 1-268406

Int. Cl.⁶ G06F 3/14

U.S. Cl. 395—566

1 Claim



1. A digital signal processing system, comprising:
- an instruction memory for storing microinstructions;
 - an instruction execution control circuit for fetching and decoding said microinstructions from said instruction memory, each of said microinstructions including a data operation instruction and a bit limiting instruction designating a significant bit count;
 - a data memory for storing data;
 - a data operation circuit for performing an operation on data from said data memory, said operation being designated by a decoded microinstruction from said instruction execution control circuit; and
 - a limiting circuit for inputting a result of said operation performed by said data operation circuit, inputting a bit limiting instruction from said instruction execution control unit, physically limiting the number of bits of said result to any integer m designated by the bit limiting instruction of said decoded microinstruction, and outputting the limited result to an output bus with a width of n bits, where $m < n$.

5,590,292

SCALABLE TREE STRUCTURED HIGH SPEED INPUT/OUTPUT SUBSYSTEM ARCHITECTURE


David R. Wooten, Spring; Craig A. Miller, Cedar Park; Kevin B. Leigh, Houston; Robert B. Costley, Spring, and Christopher E. Simonich, Tomball, all of Tex., assignors to Compaq Computer Corporation, Houston, Tex.

Continuation-in-part of Ser. No. 986,918, Dec. 8, 1992. This application Jan. 21, 1993, Ser. No. 7,333

Int. Cl.⁶ G06F 13/36; 15/17

U.S. Cl. 395—825

27 Claims



1. An input/output subsystem for a computer system, the computer system having a means for providing and receiving addresses and data to perform operations, the input/output subsystem comprising:

- a plurality of addressable input/output devices receiving and providing packets, each of said input/output devices having an address range unique to that input/output device, each of said packets having a plurality of fields according to a predetermined protocol, said packets including a command portion and being formed of a plurality of elements; and

means connected to said means for providing and receiving addresses and data and each of said plurality of input/output devices for transferring data between said means for providing and receiving addresses and data and each of said plurality of input/output devices, each of said plurality of input/output devices separately connected to said means for transferring, wherein said means for transferring includes:

- means for determining if an address and data operation is or a plurality of address and data operations are directed to one of said plurality of input/output devices by analyzing said address portion of said operation or operations to determine if the address provided in said address portion of said operation or operations corresponds to an address within one of said unique address ranges of said plurality of input/output devices;
- means for converting said address and data operation or said plurality of address and data operations to a packet;
- means for transmitting said packet developed by said means for converting to a packet to said one of said plurality of input/output devices as a series of said plurality of elements forming said packet;
- means for receiving a packet from one of said plurality of input/output devices as a series of said plurality of elements forming said packet;
- means for converting said packet received from said one of said plurality of input/output devices to an address and data operation or a plurality of address and data operations; and

means for providing the output of said means for converting said packet to said means for providing and receiving addresses and data.

5,590,293

DYNAMIC MICROBRANCHING WITH PROGRAMMABLE HOLD ON CONDITION, TO PROGRAMMABLE DYNAMIC MICROBRANCHING DELAY MINIMIZATION


George M. Uhler, and George G. Mills, both of Marlborough, Mass., assignors to Digital Equipment Corporation, Maynard, Mass.

Continuation of Ser. No. 68,835, May 28, 1993, abandoned, which is a continuation of Ser. No. 222,097, Jul. 20, 1988, abandoned. This application Apr. 18, 1995, Ser. No. 425,683

Int. Cl.⁶ G06F 9/302; 9/26; 9/38

U.S. Cl. 395—581

24 Claims




1. A processor comprising:

- a) a control store for producing microinstructions in response to microaddresses applied to an input of the control store, the processor operating in machine cycles and the control store producing one of said microinstructions each machine cycle; each microinstruction executing during a plurality of successive machine cycles;
- b) a plurality of execution stages, each execution stage using each one of said microinstructions in said successive machine cycles whereby execution of each of said microinstructions overlaps execution of other of said microinstructions, with latch means in each of said execution stages receiving said microinstructions to store and shift each microinstruction for said successive machine cycles;
- c) means for generating condition information in response to a condition at an output of one of said execution stages in each of said successive machine cycles;
- d) means for generating a next microaddress using said condition information, and for applying said next microaddress to said input of the control store;
- e) and means for selecting said condition information generated in a selected machine cycle, for use by said means for generating a next micro-address after a designated number of said successive machine cycles, said designated number of said successive machine cycles being dependent upon a decoded field of one of said microinstructions.

5,590,294
METHOD AND APPARATUS FOR RETARTING PIPELINE PROCESSING
 Sunil Mirapuri, Mountain View, and Thomas J. Riordan, Los Altos, both of Calif., assignors to Silicon Graphics, Inc., Mountain View, Calif.
 Continuation of Ser. No. 229,076, Apr. 18, 1994, abandoned, which is a continuation of Ser. No. 671,560, Mar. 19, 1991, abandoned. This application May 24, 1995, Ser. No. 449,588
 Int. Cl.⁶ G06F 9/38

U.S. Cl. 395—591

8 Claims



8. A method of processing instructions by a processor, said method comprising the steps:


- operating said processor by cycling a plurality of instructions through a single pipeline, said single pipeline having a plurality of sequential stages including stages for instruction processing and execution;
- stalling all of said stages of the pipeline in response to a detected processing fault without stalling as a result solely of a predicted fault;
- serving the detected fault while the pipeline is stalled; preloading all of said stages of the pipeline invalidated by said processing fault, while maintaining those stages which are not invalid, so as to fill the pipeline while the pipeline is stalled, said step of preloading comprising backing up invalidated stages of the pipeline and re-executing said stages with corrected information; and
- running the pipeline upon completion of preloading, wherein the pipeline includes a stage for executing an instruction, in which for an execution type processing fault the execution stage is invalidated and in which said preloading comprises preloading the execution stage.

5,590,295
SYSTEM AND METHOD FOR REGISTER RENAMING
 Trevor A. Deosaran, Sunnyvale; Sanjiv Garg, Fremont, and Kevin R. Iadonato, San Jose, all of Calif., assignors to Seiko Epson Corporation, Japan
 Continuation of Ser. No. 997,948, Dec. 31, 1992, abandoned.
 This application Jun. 7, 1995, Ser. No. 478,531
 Int. Cl.⁶ G06F 9/30

U.S. Cl. 395—393

17 Claims

1. A system for renaming source registers of at least one instruction in an instruction window, comprising: control logic that assigns a tag to each new instruction that enters the instruction window, wherein said tag comprises a unique address in a temporary buffer where instruction execution results are stored;
- a recycling queue comprising a plurality of slots equal in number to a predetermined size of the instruction window, each of said plurality of slots containing one of said tags, wherein an order defined by a position of said assigned tags in said recycling queue corresponds to an order of instructions in the instruction window;
- selecting means for selecting a tag assigned to a first instruction as a register address of a source register of a second instruction if said source register of said second instruction is dependant on said first instruction, wherein said selected tag is a




renamed register address for said source register of said second instruction; and
 a register file that stores renamed register addresses at address locations indicated by said tags, wherein a tag assigned to said second instruction, when applied to a read address port of said register file, outputs said renamed register address for said source register of said second instruction at a read data port of said register file.

5,590,296
DATA PROCESSOR PROCESSING A JUMP INSTRUCTION
 Masahito Matsuo, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
 Division of Ser. No. 10,085, Jan. 27, 1993, Pat. No. 5,485,587.
 This application Sep. 29, 1995, Ser. No. 537,046
 Claims priority, application Japan, Feb. 7, 1992, 4-22695
 Int. Cl.⁶ G06F 9/38; 9/30; 9/32

U.S. Cl. 395—570

1 Claim




1. A data processor comprising: a memory for storing instructions; an instruction fetch unit for fetching the instructions from said memory; an instruction decoding unit for decoding the instructions fetched by said instruction fetch unit; an instruction execution unit for executing the instructions on the basis of the instruction decoding result by the instruction decoding unit; and pre-jump means including, a jump target address generating unit having means for generating the jump target address relating to processing the jump instruction, and transferring means for transferring said jump target address to said instruction fetch unit, and means for, at jump instruction processing, instructing to fetch an instruction of the jump target by transferring the jump target address generated in said jump target address generating unit to said instruction fetch unit via the transferring means; and a mode register for, which can be set by the instruction or hardware, specifying operation modes; wherein at processing the unconditional jump instruction, said pre-jump means generates said jump target address in said jump target address generating unit, and transfers said jump

target address to said instruction fetch unit via said transferring means, and said instruction fetch unit fetches an instruction of said jump target, when said mode register shows a first mode, said unconditional jump instruction is processed in said instruction execution unit, and when said mode register shows a second mode, said unconditional jump instruction is not processed in said instruction execution unit.

5,590,297
ADDRESS GENERATION UNIT WITH SEGMENTED ADDRESSES IN A MICROPROCESSOR
 Kamla P. Huck, Portland; Scott D. Rodgers, and Andrew F. Glew, both of Hillsboro, all of Oreg., assignors to Intel Corporation, Santa Clara, Calif.
 Filed Jan. 4, 1994, Ser. No. 176,066
 Int. Cl.⁶ G06F 12/00

U.S. Cl. 395—401

4 Claims




1. A processor comprising: a bus; a memory; an execution unit coupled to said bus for performing arithmetic functions; a fetch unit coupled to said bus for determining an entry is to be accessed; an issue unit coupled to said bus for accessing said entry from storage in said memory; an address generation unit (AGU) coupled to said bus for generating an address corresponding to said entry, said AGU including a segment register file for storing address segments, and a circuit for rearranging noncontiguous base and limit bit positions of a first address segment when said first address segment is loaded from said memory into said segment register file, thereby producing a second address segment having all base bits and all limit bits contiguous; and said segment register file includes a resettable null bit which indicates a null segment.

5,590,298
METHOD OF RESTORING AND UPDATING RECORDS IN A DISK CACHE SYSTEM DURING DISK DRIVE IDLE TIME USING START AND END ADDRESSES
 Masakazu Kawamoto, Komae, Japan, assignor to Fujitsu Limited, Kawasaki, Japan
 Continuation of Ser. No. 210,774, Mar. 21, 1995, abandoned, which is a continuation of Ser. No. 647,623, Jan. 29, 1991, abandoned. This application Nov. 6, 1995, Ser. No. 553,822
 Claims priority, application Japan, Jan. 30, 1990, 2-18075
 Int. Cl.⁶ G06F 12/16; 12/00; 12/06

U.S. Cl. 395—403

6 Claims

1. A method of restoring write data in a disk cache system comprising the steps of: providing a host, a disk drive having a plurality of tracks including a plurality of records, a cache memory, a nonvolatile memory storing a directory which controls storing of



tracks in said nonvolatile memory, and a disk controller, wherein said disk controller writes tracks of data from said disk drive, including records addressed by a read command sent from said host, into said cache memory, and said disk controller also writes tracks of data, including records updated by said host, into said nonvolatile memory in response to a write command sent from said host and restores the records updated by said host to said disk drive during an idle time of said disk drive; updating, in said nonvolatile memory, one of said records in response to said write command sent from said host; updating, in said directory, a start address and an end address of said one of said records to be restored to said disk drive from said nonvolatile memory in response to an address of said one of said records updated by said host; and restoring said one of said records updated by said host to said disk drive from said nonvolatile memory during said idle time of said disk drive in response to a write command sent from said host containing said start address and said end address of said one of said records to be restored to said disk drive from said nonvolatile memory.

5,590,299
MULTIPROCESSOR SYSTEM BUS PROTOCOL FOR OPTIMIZED ACCESSING OF INTERLEAVED STORAGE MODULES

Brian R. Bennett, Laguna Niguel, Calif., assignor to AST Research, Inc., Irvine, Calif.


Filed Oct. 28, 1994, Ser. No. 331,290

Int. Cl.⁶ G06F 12/00

U.S. Cl. 395—405

7 Claims

6. An information processing system including multiple bus mastering modules, said system comprising: a system bus; a plurality of memory modules in communication with said system bus; and a plurality of bus mastering modules, wherein each of said bus mastering modules includes a subcircuit which, before an address directed to one of said memory modules is placed on said system bus, monitors said address requested by said bus mastering modules, and wherein said subcircuit grants the local bus mastering circuit control of the system bus for a next data transfer cycle if a current memory address is to a different memory module than a previous address request.



5,590,300

CACHE MEMORY UTILIZING ADDRESS TRANSLATION TABLE


Marvin Lautzenheiser, Springfield, Va., assignor to Zitel Corporation, Fremont, Calif.

Division of Ser. No. 255,251, Jun. 7, 1994, which is a continuation-in-part of Ser. No. 139,559, Oct. 20, 1993, Pat. No. 5,353,430, which is a continuation of Ser. No. 860,731, Feb. 21, 1992, which is a continuation of Ser. No. 665,021, Mar. 5, 1991. This application Feb. 22, 1995, Ser. No. 392,209

Int. Cl.⁶ G06F 12/08

U.S. Cl. 395-412

26 Claims



1. A cache memory system comprising:
 - a mass storage device organized into logical blocks, each logical block including the same fixed number of sectors;
 - a cache memory for temporarily storing selected data associated with said mass storage device, said cache memory organized by logical blocks each including the same number of sectors as said logical blocks of said mass storage device, said cache memory containing a lesser number of logical blocks than said mass storage device;
 - a cache memory logical block address reference table indexed by cache memory logical block number and which maintains information related to each logical block of said cache memory and including the identity of the mass storage logical block to which a given cache memory logical block is currently associated, if any; and
 - a mass storage logical block address reference table indexed by mass storage logical block number and which is used for

storing information indicating which logical blocks of data currently stored in said cache memory correspond to data stored in, or intended to be stored in, said mass storage device, said mass storage logical block address reference table including for each logical block of said mass storage device: a flag indicating whether data associated with said logical block is currently stored within said cache memory; and a cache memory logical block number, wherein:

if said flag indicates data associated with said mass storage logical block is currently stored within said cache memory, the cache memory logical block number is then the index into said cache memory logical block address reference table, and data stored in, or intended to be stored in, the corresponding block of said mass storage device is currently stored in the associated block of said cache memory.

5,590,301

ADDRESS TRANSFORMATION IN A CLUSTER COMPUTER SYSTEM


Russell W. Guenther, Glendale, and Leonard Rabins, Scottsdale, both of Ariz., assignors to Bull HN Information Systems Inc., Billerica, Mass.

Filed Oct. 6, 1995, Ser. No. 540,106

Int. Cl.⁶ G06F 9/26; 9/34; 12/00

U.S. Cl. 395-412

12 Claims



5. A cluster computer system comprising:

A) a plurality of clusters, each said cluster including:

- 1) a plurality of processors, each said processor having inherent limitations on the range of memory which is directly addressable by a processor address field, said processor address field being divided into higher order and lower order segments, each said processor including:
 - a) a primary cache; and
 - b) an address translator; and

2) a secondary cache;

- B) a memory having a capacity which exceeds the range each said processor is inherently capable of directly addressing, said memory being addressable by a memory address field, said memory address field exceeding said processor address field, said memory address field being divided into higher order and lower order segments;

C) means establishing a cluster number for each said cluster;

D) means coupling said plurality of clusters, via said secondary caches, to said memory; and

- E) each said address translator in each said processor in each said cluster being coupled between said primary cache in its said processor and said secondary cache in its said cluster, said address translator including second address translation logic responsive to memory address field information, said second translation logic comprising means responsive to the digital states of predetermined indicator bits in said memory address field, which predetermined indicator bits are of a lower order than the most significant bit thereof, by effecting one of two address transformations:
 - 1) if said predetermined indicator bits are both a first digital value:
 - a) forcing a predetermined bit of said higher order segment of said processor address field to a first logic level;

- b) copying two higher order bits of said higher order segment of said memory address field to the two lowest order bits of said higher order segment of said processor address field; and
- c) copying the contents of the lower order segment of said memory address field to said lower order segment of said processor address field;

thereby specifying a memory region containing information accessible by all said clusters; and

- 2) if either of said predetermined indicator bits are a second digital value:

- a) comparing higher order bits, representing a target cluster, in said higher order segment of said memory address field to a cluster number;

- b) if said higher order bits in said higher order segment of said memory address field match said cluster number:

- i) copying the two lowest order bits of said higher order segment of said memory address field to the two lowest order bits of said higher order segment of said processor address field in at least one of said processors in said cluster identified by said cluster number; and

- ii) copying the contents of said lower order segment of said memory address field to said lower order segment of said processor address field in at least one of said processors in said cluster identified by said cluster number; and

- c) if said higher order bits in said higher order segment of said memory address field do not match said cluster number, inhibiting transfer of the contents of said memory address field to said processor address fields in all said processors in said cluster identified by said cluster number;

thereby specifying a memory region containing information accessible only by the cluster specified by said cluster number.

5,590,302

DEVICE FOR GENERATING STRUCTURED ADDRESSES

Koichi Tanaka, Kawasaki, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan

Continuation of Ser. No. 935,095, Aug. 26, 1992, abandoned.


This application Jun. 7, 1995, Ser. No. 487,700

Claims priority, application Japan, Aug. 26, 1991, 3-213676

Int. Cl.⁶ G06F 12/10

U.S. Cl. 395-416

7 Claims



1. A device for generating structured addresses indicating an address position in one of a memory and an Input/Output (I/O) unit to be accessed, said device receiving address data comprising a first address of i bits (i is a positive integer, high order k bits, low order i-k bits, k is a positive integer), a second address of n bits (n is a positive integer), and a control bit indicating which of said first address and said second address is valid, comprising:
 - (a) page address storage means for storing a page address of m bits (m is a positive integer, high order m-k bits, low order k bits) of each of a plurality of pages dividing said memory;
 - (b) first structured address generation means for receiving said first address and a page address from said page address storage means, for adding only said high order k bits of said first address to only said low order k bits of said page address, and for generating a first structured address of n-bits comprising the high order m-k bits of said page address, intermediate order k bits made from a result of said addition, and said low-order i-k bits made from the low order i-k bits of said first address; and
 - (c) second structured address generation means for selecting one of said first structured address and said second address based on said control bit to generate a second structured address, and for transmitting said second structured address to one of said memory and said I/O unit, wherein when said first address is valid, said second structured address generation means transmits said first structured address, and when said second address is valid, said second structured address generation means transmits said second address.

5,590,303

MEMORY DESIGNATION CONTROL DEVICE

Kouichi Shibata, Sakai, and Shigenori Motooka, Nishinomiya, both of Japan, assignors to Mita Industrial Co., Ltd., Japan


Filed Nov. 10, 1992, Ser. No. 974,103

Claims priority, application Japan, Nov. 13, 1991, 3-326328

Int. Cl.⁶ G06F 12/00; 12/02; G11C 16/06

U.S. Cl. 395-427

5 Claims



1. A memory designation control device comprising:

- a first rewritable memory device for storing a basic program;
- a second memory device, different from said first memory device, for storing a rewriting program for rewriting the contents of said first memory device;

- a mode selecting switch for switching between a normal processing mode in which normal processing based on the basic program is performed, and a rewrite processing mode in which rewrite processing based on the rewriting program is performed;

- means for bringing only said first memory device, out of said first memory device and said second memory device, into a selectable state when a system power supply is turned on while the mode selecting switch is in a state where the normal processing mode is selected;

- means for bringing only said second memory device, out of said first memory device and said second memory device, into a selectable state at the time of a read instruction, while bringing only said first memory device, out of said first memory device and said second memory device, into a selectable state at the time of a write instruction, when a system power supply is turned on while said mode selecting switch is in a state where the rewrite processing mode is selected; and

- means for inhibiting, when a system power supply is turned on while said mode selecting switch is in the state where the normal processing mode is selected, said second memory device from being brought into a selectable state if said mode selecting switch is switched to the state where the rewrite processing mode is selected after a system power supply is turned on.

5,590,304 CIRCUITS, SYSTEMS AND METHODS FOR PREVENTING QUEUE OVERFLOW IN DATA PROCESSING SYSTEMS


Richard W. Adkisson, Dallas, Tex., assignor to Covex Computer Corporation, Richardson, Tex.

Filed Jun. 13, 1994, Ser. No. 258,761

Int. Cl.⁶ G06F 13/16

U.S. Cl. 395-427

30 Claims



19. A processing system comprising:
circuitry for generating memory requests at a first clock rate;
input queuing circuitry comprising:

- a first queue for receiving said memory requests from said circuitry for generating at said first clock rate; and
- a second queue coupled in series with said first queue for holding said memory requests when contention for access to a particular memory unit occurs and for outputting said memory requests at a second clock rate;

a memory system containing said particular memory unit for storing and retrieving data in response to said memory requests, said memory system outputting data at said second clock rate in response to read requests from said input queuing circuitry;

an output queue for receiving data from said memory at said second clock rate and outputting said data at said first clock rate; and

queuing control circuitry associated with said input queuing circuitry for preventing overflows of said output queue by controlling a number of said memory requests sent in bursts from said input queuing system to said memory system and by controlling wait time between ones of said bursts.

5,590,305 PROGRAMMING CIRCUITS AND TECHNIQUES FOR PROGRAMMING LOGIC

Richard S. Terrill, Sunnyvale, and Robert R. N. Bielby, Fremont, both of Calif., assignors to Altera Corporation, San Jose, Calif.

Continuation of Ser. No. 219,688, Mar. 28, 1994, abandoned.

This application Dec. 15, 1995, Ser. No. 572,806

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395-430

21 Claims

18. A method for configuring a plurality of programmable logic devices, comprising the steps of:

providing a source of configuration data, wherein said source is a microprocessor;

generating a first clock signal from said microprocessor;

generating a second clock signal from said microprocessor;

retrieving a first set of configuration data into said microprocessor;


transferring in parallel, responsive to said first clock signal generated by said microprocessor, via a first direct data path a first portion of said first set of configuration data, in the form of a stream of parallel data bits, from a data port of said microprocessor to a first programmable logic device;

configuring at least a portion of said first programmable logic device with said first portion of said first set of configuration data;

transferring in parallel, responsive to said second clock signal generated by said microprocessor, via a second direct data path a second portion of said first set of configuration data, in the form of a stream of parallel data bits, from said data port of said microprocessor to a second programmable logic device;

configuring at least a portion of said second programmable logic device with said second portion of said first set of configuration data; and

repeating the steps of generating a first clock signal, generating a second clock signal, retrieving a first set of configuration data, transferring in parallel, responsive to said first clock signal, configuring at least a portion of said first programmable logic device, and transferring in parallel, responsive to said second clock signal, configuring at least a portion of said second programmable logic device, until all of said plurality of programmable logic devices are configured.



transferring in parallel, responsive to said second clock signal generated by said microprocessor, via a second direct data path a second portion of said first set of configuration data, in the form of a stream of parallel data bits, from said data port of said microprocessor to a second programmable logic device;

configuring at least a portion of said second programmable logic device with said second portion of said first set of configuration data; and

wherein said step of configuring at least a portion of said first programmable logic device is interleaved with said step of configuring at least a portion of said second programmable logic device, wherein said first programmable logic device may be partially configured when said second programmable logic device is partially configured.

5,590,306 MEMORY CARD MANAGEMENT SYSTEM FOR WRITING DATA WITH USAGE AND RECORDING CODES MADE SIGNIFICANT

Mikio Watanabe, Akira Aoki, and Osamu Saito, all of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan


Filed Jul. 20, 1993, Ser. No. 93,640

Claims priority, application Japan, Sep. 8, 1992, 4-239269; Sep. 14, 1992, 4-244766

Int. Cl.⁶ G06F 12/08

U.S. Cl. 395-442

15 Claims



3. An IC memory card control system comprising:

an IC memory card, which is provided with a plurality of data areas in which data is stored and management areas in which management information is stored for managing recording of the data into the data areas;

said IC memory card being provided with an identification area into which written are an occupation code indicative of recording of the data in a data area and a recording code indicative of an abnormal recording of the data in a data area; and

IC memory card control means, to which said IC memory card is detachably coupled, for storing the management information data;

and the data in said IC memory card, said IC memory card control means comprising
management information read means for reading out the management information stored in the management areas of said IC memory card,
management information updating means for updating the management information read out by said management information read means, and
data recording means for writing the data into said IC memory card.

said management information updating means providing such a control that when writing the data into a data area, prior to the data writing, the occupation code and the recording code are written into the identification area in a first significant condition, and after having completed the data writing the recording code is cleared/reset from the first significant condition.

5,590,307 DUAL-PORT DATA CACHE MEMORY


David C. McClure, Carrollton, Tex., assignor to SGS-Thomson Microelectronics, Inc., Carrollton, Tex.

Filed Jan. 5, 1993, Ser. No. 711

Int. Cl.⁶ G06F 12/08

U.S. Cl. 395-458

4 Claims



1. A dual-port data cache memory, comprising:

a dual-port memory array having a plurality of entries, wherein each of said plurality of entries has a corresponding address, said memory array laid out as a plurality of rows and columns, wherein a plurality of memory cells in a row are selected for reading or writing by activating a single word line, and wherein the plurality of selected cells place data onto a corresponding plurality of bit lines;

a first memory port capable of reading and writing entries to the dual-port memory array, wherein the first memory port is utilized by a processor;

a second memory port capable of reading and writing entries to the dual-port memory array, wherein the second memory port is utilized by a system;

an address latch connected to the second memory port for storing an address generated by the system on an address bus; a row decoder for decoding a plurality of most significant bits from the address latch, and activating a word line;

a column decoder connected to the plurality of bit lines for selecting a subset thereof, wherein at least one less significant bit than the most significant bits from the address latch are connected to the column decoder, and wherein the subset of bit lines is selected in response to such less significant bits;

a counter for generating a sequence of consecutive binary signals representing numbers; and

means for connecting the binary signals generated by the counter to the column decoder in response to a control signal; wherein, in response to the control signal, a plurality of entries selected by the column decoder in response to the signals generated by the counter are read from the memory array for a single address stored in the address latch.

5,590,308 METHOD AND APPARATUS FOR REDUCING FALSE INVALIDATIONS IN DISTRIBUTED SYSTEMS


Yifeng Shih, Cupertino, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 1, 1993, Ser. No. 115,501

Int. Cl.⁶ G06F 12/12

U.S. Cl. 395-463

20 Claims



1. A method of reducing false invalidations in a distributed file, multiple processor system having a plurality of processors coupled to a global cache memory, each processor being connected to a central processor unit, local cache memory, and mass storage unit, the global cache memory and each local cache memory maintaining a least recently used (LRU) stack that contains identification indicia for each data record contained in the corresponding cache memory for selectively determining which data records shall be deleted, each read miss and each write operation by a processor resulting in an update to operating system statistical metrics, including a cache memory data input/output rate and miss ratio, and to the global cache LRU stack and the local cache memory LRU stack of the processor, the method comprising the steps of:

responding to each read hit by a processor by updating the local cache memory LRU stack associated with that processor;
defining an update interval of the global cache memory LRU stack as a function of a predetermined statistical metric of data residency time for the local cache memory; and
updating the global cache memory LRU stack no more frequently than at the expiration of the update interval in response to the read hit.

5,590,309 STORAGE PROTECTION CACHE AND BACKING STORAGE HAVING SYSTEM CONTROL ELEMENT DATA CACHE PIPELINE AND STORAGE PROTECTION BITS IN A STACK ARRAY WITH A STACK DIRECTORY FOR THE STACK ARRAY

Edward W. Chencinski, Poughkeepsie; Jeffrey C. Bixler, Highland, and Neal T. Christensen, Wappingers Falls, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 1, 1994, Ser. No. 222,191

Int. Cl.⁶ G06F 12/08

U.S. Cl. 395-472

10 Claims

1. A data processing system having a hierarchical memory comprising:


a plurality of processing elements;

said hierarchical memory including a main memory and a primary cache for each of said plurality of processing elements;

an input output element;

a system control apparatus coupling said plurality of processing elements and said input output element to said memory;

said system control apparatus providing:



- (a) a system control element data cache pipeline for receiving requests from said plurality of processing elements or from said input output element;
- (b) a shared cache portion of said hierarchical memory; and
- (c) a storage protection cache, a storage protection backing storage coupled to said storage protection cache, and a storage protection store stack for controlling access to said storage protection store, and a set of latches forming a storage protection store stack directory for a request stack of requests that require access to said storage protection store, said stack directory having stack positions and containing for each stack position pointer fields including a stack address field, a fetch request field, a castout request field, a putaway request field, a Key Op request field, a fetch pending field, a castout pending field and a putaway pending field, and a storage protection cache pipeline which is coupled for receiving said requests either from said system control element data cache pipeline or from said storage protection store.

5,590,310

METHOD AND STRUCTURE FOR DATA INTEGRITY IN A MULTIPLE LEVEL CACHE SYSTEM

Avigdor Willenz, Saratoga, and Yiftach Tzori, Sunnyvale, both of Calif., assignors to Integrated Device Technology, Inc., Santa Clara, Calif.

Continuation of Ser. No. 4,332, Jan. 14, 1993, abandoned.

This application Apr. 21, 1995, Ser. No. 426,440


Int. Cl.⁶ G06F 12/00

U.S. Cl. 395—473

6 Claims

1. A computer system having a processor bus including data and address portions, and a memory bus coupled to a main memory, said main memory including a plurality of cacheable and non-cacheable memory locations, said computer system comprising:

- a primary cache memory coupled to said processor bus, said primary cache memory receiving (i) a datum placed on said data portion of said processor bus and (ii) a cache write enable signal which is asserted when said datum on said processor bus is to be written into said primary cache memory;
- a buffer memory, coupled to said processor bus and said memory bus, said buffer memory including a plurality of read registers and a plurality of write registers, said buffer memory receiving (i) said datum placed on said processor bus and (ii) a buffer write enable signal which is asserted when a datum is to be written into one of said write registers;
- a central processing unit coupled to said processor bus, said central processing unit, during a store operation to a cacheable memory location, asserts said cache write enable signal and



- said buffer write enable signal, and during a store operation to a non-cacheable memory location asserts said buffer write enable signal and deasserts said cache write enable signal;
- a circuit receiving said cache write enable signal and said buffer write enable signal for generating a control signal for indicating whether a store operation is performed on a cacheable memory location or a noncacheable memory location, in accordance with whether or not said cache write enable signal is enabled and whether or not said buffer write enable signal is enabled; and
- a secondary cache memory receiving said control signal, said secondary cache memory performs a store operation when control signal indicates that said store operation is directed to a cacheable memory location.

5,590,311

SYSTEM AND METHOD FOR EMULATING DISK TRACKS TO MAINTAIN DATA FORMAT COMPATIBILITY

Hitoshi Matsushima, Kawasaki, Japan, assignor to Fujitsu Limited, Japan

Continuation of Ser. No. 800,969, Dec. 2, 1991, abandoned.


This application Jun. 14, 1994, Ser. No. 259,558

Claims priority, application Japan, Nov. 30, 1990, 2-334167

Int. Cl.⁶ G06F 13/00; 5/00

U.S. Cl. 395—500

20 Claims



1. A disk track emulation system for making a first variable track length data format used by a host device compatible with a second variable track length data format used by a disk device;
- said first data format including cells each consisting of n bytes, N number or cells being on a circumferential track of the first data format;

said second data format including cells each consisting of m bytes, M number of cells being on one circumferential track of the second data format;

wherein N is unequal to M and n is unequal to m;

said system comprising:

- said host device, said disk device, and a disk control device connected between said host device and said disk device;
- said disk device including at least one disk track having a plurality of cells, each of said cells having a certain number of bytes;
- said host device handling data in accordance with said first data format, and said disk control device and said disk device handling data in accordance with said second data format;

said disk control device comprising:

- physical cell position data generating means for generating physical cell position data representing a track position and a record position of a cell to be accessed in accordance with said second data format using said M cells and said m bytes, in response to accessing operations by said host device, said disk control device, and said disk device;
- logical cell position data generating means for generating logical cell position data representing a track position and a record position of the cell to be accessed in accordance with said first data format using said N cells and said n bytes; and
- said disk control device storing said physical cell position data and said logical cell position data on said disk track in accordance with said second data format.

5,590,312

METHOD AND APPARATUS FOR EMULATING CIRCUITRY IN A COMPUTER SYSTEM USING A SYSTEM MANAGEMENT INTERRUPT

Suresh K. Marisetty, San Jose, Calif., assignor to Intel Corporation, Santa Clara, Calif.


Continuation of Ser. No. 987,199, Dec. 7, 1992, abandoned.

This application Jun. 24, 1994, Ser. No. 265,502

Int. Cl.⁶ G06F 9/46

U.S. Cl. 395—500

8 Claims



1. A computer system comprising:

- a bus;
- at least one memory coupled to the bus, wherein the memory stores data and instructions;
- a processor having a plurality of pins coupled to the bus, wherein the processor executes a plurality of instructions that comprise an operating system and at least one application program designed to perform accesses to a first circuitry not present in the computer system, and further wherein the processor asserts a signal on a first of the plurality of pins when an access to the first circuitry occurs;
- a second circuitry for performing a function; and
- a controller coupled to the processor, said controller generating a system management interrupt in response to said signal.

wherein the system management interrupt is transparent to said at least one application program and the operating system;

wherein the processor receives the system management interrupt on a second of the plurality of pins, said processor further comprising

- a first trapping mechanism to trap accesses generated by said at least one application program in response to the system management interrupt, and
- a system management handler that handles the system management interrupt in an operating environment that underlies the operating system and said at least one application, such that the system management interrupt is handled transparently to the operating system and said at least one application, wherein said system management handler translates accesses generated by said at least one application program that are designated for said first circuitry to be compatible with said second circuitry in response to the system management interrupt, and the system management handler sends converted accesses to the second circuitry for completion and returns to said at least one application while said at least one application program and said operating system are unaware of the first circuitry being emulated by the processor.

5,590,313

MULTIPLE PROTOCOL DEVICE INTERFACE SUBSYSTEM AND METHOD


Robert A. Reynolds, Pflugerville, and David W. Sheffield, Austin, both of Tex., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 30, 1994, Ser. No. 269,338

Int. Cl.⁶ G06F 13/14; 13/42

U.S. Cl. 395—500

10 Claims



1. A method for interfacing to adapter hardware in a multiprotocol computer system environment having a plurality of different interfaces comprising:

- passing from a plurality of different protocol stacks at least two different structures to corresponding different protocol heads, each of said at least two different structures being comprised of a structure for a different interface of said plurality of different interfaces;
- generating a common interface structure with said different protocol heads containing pointers to said two different structures so as to accept with said common structure said at least two different structures, said at least two different structures each including a pointer to a buffer address, a pointer to a buffer length, and a cross-memory descriptor; and
- passing said common structure to said adapter hardware through said plurality of different interfaces.

5,590,314


APPARATUS FOR SENDING MESSAGE VIA CABLE
BETWEEN PROGRAMS AND PERFORMING
AUTOMATIC OPERATION IN RESPONSE TO SENT
MESSAGE

Hitoshi Ueno, Zama; Junichi Kazama, Yokohama; Hirofumi Kinoshita, Yokohama, and Masaki Sato, Yokohama, all of Japan, assignors to Hitachi, Ltd., Tokyo, and Hitachi Software Engineering Co., Ltd., Yokohama, both of Japan

Claims priority, application Japan, Oct. 18, 1993, 5-259588
Int. Cl.⁶ G06F 19/00

U.S. Cl. 395-681

17 Claims



1. An automated operation machine that can be continued to run by sending back a response to a message given from a program, comprising:


- a application program area having an application program;
- a first device driver for transmitting via a first interface a console display message addressed from said application program area for automatic operation in a first preselected format for said first interface;
- a first adaptor connected to the first device driver, for outputting via a console interface of said first adaptor said console display message in said first preselected format adapted for said console interface;
- an operator program memory region having an operator program;
- a second device driver for transmitting via a second interface a predetermined operator command from said operator program in correspondence to said console display message;
- a second adaptor connected to said second device driver, for outputting via said console interface said operator command in said first preselected format;
- a connection cable for mutually connecting said first adaptor with said second adaptor and for transmitting said console display message and said operator command between said first and second device drivers in order to continue said automatic operation in said application program by use of said console display message and said predetermined operator command; and,
- a configuration information area for storing addresses of said first and second device drivers, for indicating to which device driver said application program and said operator program should send said console display message and said predetermined operator command.

5,590,315
METHOD AND APPARATUS FOR SIMULATING USER
INPUT DEVICE PRESENCE IN A COMPUTER SYSTEM
Randall L. Hess, Cypress, and Drew S. Johnson, Houston, both
of Tex., assignors to Compaq Computer Corporation, Hous-
ton, Tex.

Continuation of Ser. No. 119,430, Sep. 10, 1993, abandoned.
This application Dec. 19, 1994, Ser. No. 359,014
Int. Cl.⁶ G06F 3/00

U.S. Cl. 395—500

13 Claims



1. A method of simulating user input device presence in a computer system including a processor, a first device port for coupling with a first external physical user input device, and controller circuitry for communicating device command and data characters between the processor and the first device port, the first external physical user input device being capable of assuming a configuration, the method comprising the steps of:

- (a) determining whether the first external physical user input device is or is not coupled to the first device port;
- (b) if at step (a) it was determined that the first external physical user input device is coupled to the first device port, performing the steps of
 - (1) sending a device command or data character from the processor to the first device port, and
 - (2) sending any device command or data character subsequently received from the first device port to the processor; and
- (c) if at step (a) it was determined that the first external physical user input device is not coupled to the first device port, performing the steps of
 - (1) determining whether a device command or data character from the processor requires a response,
 - (2) if a response was determined to be needed at step (c)(1), sending a device command or data character response from the controller circuitry to the processor,
 - (3) determining whether the device command or data character from the processor is one of a predetermined number of commands intended to alter the configuration of the first external physical user input device, and
 - (4) if it was determined at step (c)(3) that the device command or data character is intended to alter the configuration, saving the new configuration of the first external physical user input device.


5,590,316
CLOCK DOUBLER AND SMOOTH TRANSFER CIRCUIT
Brian S. Hausauer, 16914 Timberwork Rd., Spring, Tex. 77379
Filed May 19, 1995, Ser. No. 445,184

Int. Cl.⁶ G06F 1/04; 1/12

U.S. CL. 395-556

14 Claims

1. A computer system having a burst transfer cycle for transferring data, comprising:
an expansion bus having a basic clock and control signals, said basic clock having a frequency and rising and falling edges, said control signals indicating the start and the end of the burst transfer cycle;



- a fixed frequency multiplier coupled to said basic clock, said fixed frequency multiplier providing a clock having a frequency which is a multiple of the basic clock frequency, said fixed frequency multiplier clock having rising edges aligned with the rising and falling edges of said basic clock;
- a decoder, said decoder coupled to said fixed frequency multiplier and to control signals of said expansion bus to detect the start and the end of the burst transfer cycle, said decoder providing a speed-up signal during the burst transfer cycle on the rising edges of said fixed frequency multiplier clock; and
- a variable frequency multiplier coupled to said basic clock and said speed-up signal, said variable frequency multiplier multiplying the frequency of said basic clock when said speed-up signal is provided and reproducing the frequency of the basic clock when said speed-up signal is deasserted, said variable frequency multiplier output having rising edges aligned with the rising and falling edges of said basic clock when multiplying the frequency and having rising edges aligned with the rising edges of said basic clock when reproducing the frequency.

5,590,317

DOCUMENT INFORMATION COMPRESSION AND
RETRIEVAL SYSTEM AND DOCUMENT INFORMATION
REGISTRATION AND RETRIEVAL METHOD

Hiroaki Iguchi, Yokohama; Yasuo Kuros, Yokosuka; Masaaki Fujinawa, Kanagawa-ken; Yoshihiro Yokoyama, Yokohama, and Hidefumi Masuzaki, Hadano, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed May 27, 1993, Ser. No. 68,658

Claims priority, application Japan, May 27, 1992, 4-135340;
May 27, 1992, 4-135341

Int. Cl.⁶ G06F 17/30

U.S. Cl. 395-602

16 Claims



1. A document information compression and retrieval system comprising:
an input section for inputting document information;

a text analysis section which separates the document information consisting of a large number of characters input at said input section into words consisting of one or more characters;

a code conversion dictionary in which pairs of said words and compressed codes corresponding to said words are stored;

a text compression section which makes reference to said code conversion dictionary for converting said words into the compressed codes corresponding thereto;

compressed text storage means for storing the compressed codes of words of said document information compressed by said text compression section as a compressed text;

retrieval information input means for entering key information used to retrieve document information registered in said compressed text storage means;

- a text retrieval section which makes reference to said code conversion dictionary for converting said key information into compressed key data corresponding thereto, and retrieves compressed texts including a compressed code identical to said compressed key data stored in said compressed text storage means;
- an expansion section which expands the compressed text retrieved by said text retrieval section into document information;
- an output section for outputting the document information restored by said expansion section; and
- character string registration means for detecting words not registered in said code conversion dictionary from said words into which said document information is separated by said text analysis section, and assigning fixed-length compressed codes to said detected words not registered in said code conversion dictionary in sequence for registering the words in said code conversion dictionary;
- wherein said text compression section makes reference to the code conversion dictionary in which words are registered by said character string registration means for converting said words into the compressed codes corresponding thereto;
- wherein when a compressed code registration area of said code conversion dictionary is finite, said character string registration means assigns the compressed codes to said detecting words in sequence, and terminates assignment of the compressed codes upon detection of said compressed code registration area becoming full; and
- wherein said text compression section, after the termination of assignment of the compressed codes, converts the words already registered in said code conversion dictionary into their corresponding compressed codes, and stores words not registered in said code conversion dictionary in said compressed text storage means without conversion into compressed codes.

5,590,318
METHOD AND SYSTEM FOR TRACKING FILES
PENDING PROCESSING

Mark Zbikowski, Woodinville; Brian T. Berkowitz, Bellevue, and Robert I. Ferguson, Seattle, all of Wash., assignors to Microsoft Corporation, Redmond, Wash.

Filed Nov. 18, 1993, Ser. No. 154,582

Int. Cl.⁶ G06F 17/30

U.S. Cl. 395-618

17 Claims

1. A computer implemented method of restoring data lost from a volatile storage, the computer including a second storage for storing a plurality of files, each file including associated file identifying information which identifies the file, the computer including a processor for processing the files, the method comprising the steps of:
- providing update sequence values for files, each update sequence value indicating an order in which the file is to be processed relative to the other files;
 - storing identifying information for files to be processed by the computer in a portion of the volatile storage;
 - selecting a next file to be processed by examining the identifying information and update sequence value of files to be processed that are stored in the portion of the volatile storage;

the edit window, conceptual schema diagram, drag-and-drop means, parsing means, list means, compiler, drawing means, and database mapping means forming in operative combination a drag-and-drop fact compiler for specifying the information system represented in the conceptual schema; and query means for specifying a query to the information system.

- (a) selecting an initial number of microprocessors for executing the application in real-time, said selecting step including:
 - placing in a first column of a matrix all real-time constrained tasks specific to said application; and
 - associating a row of dependent tasks with each task placed in the first column of the matrix to define a plurality of task subsets, each task subset comprising a maximum number of intradependent tasks and a minimum number of interdependent tasks, and said plurality of task subsets corresponding to the initial number of microprocessors;
- (b) listing dependencies between rows in a second column of the matrix;
- (c) assigning a priority P_i to each task, where p_i is between 0 and 1;
- (d) subdividing at least one of the tasks into discrete activities, each of said activities having a corresponding execution time t_{ij} ;
- (e) estimating the execution time for each activity;

- (f) reducing the number of rows in the matrix by grouping together tasks having activities which can be executed within a predetermined time window T; and
 (g) providing a final number of microprocessors corresponding to the number of rows obtained from said reducing step.

5,590,324


OPTIMIZATION OF SQL QUERIES USING UNIVERSAL QUANTIFIERS, SET INTERSECTION, AND MAX/MIN AGGREGATION IN THE PRESENCE OF NULLABLE COLUMNS

Ting Y. Leung; Mir H. Pirahesh; Michelle M. Jou, and David E. Simmen, all of San Jose, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Feb. 7, 1995, Ser. No. 384,925
 Int. Cl.⁶ G06F 17/30

U.S. Cl. 395—605

38 Claims



1. A method of optimizing an SQL query in a computer having a memory, the SQL query being performed by the computer to retrieve data from a relational database stored in an electronic storage device coupled to the computer, the method comprising the steps of:

- propagating column nullability values in the memory of the computer through various SQL operations of the query, wherein the column nullability values are selected from a group comprising null, non-null, and nullable; and
- optimizing the SQL operations of the query in the memory of the computer based on the propagated column nullability values.

5,590,325

SYSTEM FOR FORMING QUERIES TO A COMMODITIES TRADING DATABASE USING ANALOG INDICATORS

Anthony D. Kolton, Chicago, Ill.; Ruben A. Gamboa, and Danette S. Chiment, both of Austin, Tex., assignors to Logical Information Machines, Inc., Chicago, Ill.

Continuation of Ser. No. 713,359, Jun. 11, 1991, abandoned.
 This application Feb. 22, 1995, Ser. No. 392,612


Int. Cl.⁶ G06F 17/30

U.S. Cl. 395—615

18 Claims

1. A system for generating queries suitable for retrieving data from a database including a sequential history of commodity attributes, comprising:

- a display;
- a pointer device having a corresponding rendition on said display for choosing selections presented on said display;
- an event definition window sequence presented on said monitor having selections responsive to said pointer, for defining an event as one or more analog indicators from market attributes comprising: market indicators, commodities, equities, transac-



tion price, transaction volume, date, time, and the like for defining time correlated analog characteristics indicative of correlated analog characteristics indicative of a point in the sequential history when a temporal relation imposed upon selected market attributes is satisfied, and

a report definition window sequence presented on said display having selections responsive to said pointer, for defining a set of analog markets, for each point in history corresponding to the satisfaction of said one or more analog indicators as one or more time-series defining the current market being temporally related to said event to be retrieved from said database allowing comparison of report presentations for identifying recurring trends as defined by patterns relating to historical antecedents to find periods with similar characteristics.

5,590,326

SHARED DATA MANAGEMENT SCHEME USING SHARED DATA LOCKS FOR MULTI-THREADING

Toshihiko Manabe, Kanagawa-ken, Japan, assignor to Kabushiki Kaisha Toshiba, Kawasaki, Japan


Filed Sep. 13, 1994, Ser. No. 305,354

Claims priority, application Japan, Sep. 13, 1993, 5-226816

Int. Cl.⁶ G06F 12/00

U.S. Cl. 395—477

15 Claims



1. A method for managing shared data to be accessed by multiple threads, comprising the steps of:

- assigning different shared data identifiers, for identical shared data, to different threads, said different shared data identifiers to be used in identifying the shared data at a time of making accesses to the shared data;
- setting up different locks for said different shared data identifiers assigned at the assigning step; and
- detecting an access to the shared data in violation of at least one of the locks set up at the setting step among the accesses to the shared data made from the threads, said detecting being in accordance with the shared data identifiers assigned at the assigning step.

5,590,327

METHOD FOR MAKING DATA OBJECTS HAVING HIDDEN POINTERS PERSISTENT

Alexandros Biliris, Arlington, Mass.; Shaul Dar, Madison, Wis., and Narain H. Gehani, Summit, N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.


Continuation of Ser. No. 40,327, Mar. 30, 1993, abandoned.

This application Nov. 22, 1994, Ser. No. 343,735

Int. Cl.⁶ G06F 9/00

U.S. Cl. 395—670

22 Claims



1. An automated method performed by a data processing system for processing a preexisting data object, the data object having a pointer for use in providing memory access to information associated with the data object, the pointer having become invalid, said method comprising the steps of

- determining a location of said associated information in a memory; and
- changing said invalid pointer to refer to the determined location in the memory.

wherein said changing step comprises applying a modified object creation process to said preexisting data object to perform said changing of said invalid pointer, wherein an object creation process has been modified to form said modified object creation process, said object creation process comprising the steps of allocating memory space in a memory for a data object being created, initializing data within said data object being created, and initializing pointers within said data object being created, and wherein said modification comprises selectively inhibiting said step of allocating memory space and said step of initializing data.

5,590,328

PROTOCOL PARALLEL PROCESSING APPARATUS HAVING A PLURALITY OF CPUS ALLOCATED TO PROCESS HIERARCHICAL PROTOCOLS

Shoichiro Seno, and Tetsuo Ideguchi, both of Kanagawa-ken, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 907,833, Jul. 2, 1992, abandoned.


This application Mar. 6, 1995, Ser. No. 399,331

Claims priority, application Japan, Jul. 25, 1991, 3-208558

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—675

20 Claims



1. A protocol parallel processing apparatus, comprising:

a plurality of CPUs for processing a plurality of protocol data units;

a shared memory accessible by each of the plurality of CPUs for storing a CPU state table, that associates each of the plurality of CPUs with an idle flag indicative of whether a CPU is currently processing a protocol data unit, a remote address indicative of a remote node identified by a protocol data unit, and a process start time indicative of a time at which each CPU begins processing a protocol data unit; and

at least one line interface, coupled to the shared memory, including means for writing a remote address into the CPU state table when a protocol data unit is processed, and means for requesting one of the plurality of CPUs whose idle flag indicates that the CPU is idle to process the protocol data unit, and, means operative when no CPU is idle, for requesting a CPU with an oldest process start time to process the protocol data unit if none of the plurality of CPUs is idle.

5,590,329

METHOD AND APPARATUS FOR DETECTING MEMORY ACCESS ERRORS


James E. Goodnow, II, Grass Valley, Calif.; Thaddeus J. Kowalski, Summit, and James R. Rowland, Short Hills, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Feb. 4, 1994, Ser. No. 192,239

Int. Cl.⁶ G06F 11/08

U.S. Cl. 395—708

12 Claims



1. A method of generating executable code for a program from source code for the program, the executable code including pointer checking code which checks memory references made by dereferencing pointers, the method comprising the steps of:

- performing an analysis based on the source code to identify certain memory references which are made by dereferencing pointers and which need not be checked; and
- responding to the analysis by generating the executable code without pointer checking code that checks the certain memory references.


5,590,330

METHOD AND SYSTEM FOR PROVIDING A TESTING FACILITY IN A PROGRAM DEVELOPMENT TOOL
Nurcan Coskun, and Bruce A. Tate, both of Austin, Tex., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 13, 1994, Ser. No. 354,695
Int. Cl.⁶ G06F 9/45; 3/14

U.S. Cl. 395—704

12 Claims



1. A method for providing a testing facility in a program development tool within a data processing system, said method comprising:

- associating a dictionary object with each static object constructed by a user within said program development tool for a program being developed, wherein said dictionary object includes an event list and a method list;
- adding a method entry to said method list within said dictionary object in response to each action object constructed by a user within said program development tool for said program being developed; and
- in response to an association of a static object with an action object utilizing an event key selected by a user within said program development tool, associating an event key in said event list which corresponds to said selected event key with a method entry in said method list which corresponds to said action object, such that the effect of said action object on said static object can be tested via a triggering of said action object by a user within said program development tool independent of the status of all other static objects within said program being developed.

5,590,331

METHOD AND APPARATUS FOR GENERATING PLATFORM-STANDARD OBJECT FILES CONTAINING MACHINE-INDEPENDENT CODE

Brian T. Lewis, and Theodore C. Goldstein, both of Palo Alto, Calif., assignors to Sun Microsystems, Inc., Mountain View, Calif.


Filed Dec. 23, 1994, Ser. No. 363,743
Int. Cl.⁶ G06F 9/45

U.S. Cl. 395—708

21 Claims

1. A method for generating a platform-standard object file, the method comprising the steps of:

- a) providing a machine-independent software module, wherein the machine-independent software module contains abstract code defining at least one procedure;
- b) analyzing said abstract code to determine whether any global variables are defined in said machine-independent software module;
- c) if any global variables are defined in said machine-independent software module, then
 - c1) generating a list of definitions of said any global variables;
 - c2) storing said list of definitions in said platform-standard object file;



- d) analyzing said abstract code to determine whether said at least one procedure references any external variables or external procedures;
- e) if said at least one procedure references any external variables or external procedures, then
 - e1) generating a list of symbol references indicative of said any external variables or external procedures;
 - e2) storing said list of symbol references in said platform-standard object file;
- f) generating a sequence of machine instructions for calling an execution routine when a client calls said at least one procedure;
- g) storing said sequence of machine instructions in said platform-standard object file; and
- h) storing said abstract code in said platform-standard object file.

5,590,332

GARBAGE COLLECTION, TAIL RECURSION AND FIRST-CLASS CONTINUATIONS IN STACK-ORIENTED LANGUAGES

Henry G. Baker, 16231 Meadow Ridge Way, Encino, Calif. 91436

Filed Jan. 13, 1995, Ser. No. 372,514
Int. Cl.⁶ G06F 9/45

U.S. Cl. 395—705

18 Claims

1. A method for executing an advanced application, said application comprising a number of related subprograms implemented in a stack-oriented language which includes both a stack and a heap, comprising the steps of:

- converting one or more of said application subprograms into continuation-passing style (CPS) in the stack-oriented language;
- determining the extent and limit points of a stack buffer on the execution stack of the stack-oriented language, which buffer is capable of holding a plurality of invocation stack frames;
- commencing the execution of the application such that the initial invocation stack frame is within the limits of the stack buffer;
- interrupting any of said CPS-converted subprograms when the execution stack pointer is beyond a limit point of the stack buffer;
- initiating an evacuation process to transport out of the stack buffer into the heap any live data objects found in the stack buffer;
- contracting the execution stack of the stack-oriented language back to the beginning of the stack buffer; and
- resuming the execution of the interrupted CPS-converted subprogram.

5,590,333

Patent Not Issued For This Number

5,590,334


OBJECT ORIENTED MESSAGE PASSING SYSTEM AND METHOD

Thomas E. Saulpaugh, San Jose; Bill M. Bruffey, Cupertino, and Russell T. Williams, San Jose, all of Calif., assignors to Apple Computer, Inc., Cupertino, Calif.

Continuation of Ser. No. 220,043, Mar. 30, 1994, abandoned.
This application Mar. 19, 1996, Ser. No. 618,404
Int. Cl.⁶ G06F 13/14

U.S. Cl. 395—683

15 Claims



1. A computer-implemented message passing method for a computer system having a processing unit and a memory wherein a plurality of client tasks, a plurality of server tasks and a message passing unit reside, each client task comprising a sequence of program instructions that require a service, each server task comprising a sequence of program instructions capable of providing a service, the message passing unit comprising a sequence of program instructions that manages the transfer of messages between client tasks and server tasks, each client task, each server task, and the message passing unit executable by the processing unit, the message passing method comprising the steps of:

- creating a plurality of message object data structures with the message passing unit, each message object data structure corresponding to a type of service provided by at least one server task within the plurality of server tasks, each message object data structure serving as a message destination from the perspective of a client task within the plurality of client tasks and to which a client task within the plurality of client tasks issues a send message request for the purpose of requesting a particular type of service be performed upon a message;
- creating a port object data structure with the message passing unit, the port object data structure associated with the plurality of message data structures, the port object data structure corresponding to a receptacle for messages directed to each message object data structure within the plurality of message object data structures and to which each server task within the plurality of server tasks issues a receive message request for the purpose of polling for a message;
- issuing a send message request with a first client task within the plurality of client tasks, the send message request including a reference to a first message and a reference to a message object data structure within the plurality of message object data structures;
- receiving the send message request with the message passing unit;
- transferring the first message to the port object data structure with the message passing unit;
- polling the port object data structure with a first server task within the plurality of server tasks; and
- transferring the first message to the first server task with the message passing unit.

5,590,335

PROCESS FOR ANALYSIS OF DEADLOCKS IN AN OPERATING SYSTEM


Jean-Paul Dubourreau, Biviers, and Thierry Jacquin, Echirrolles, both of France, assignors to Bull S.A., Puteaux, France

Continuation of Ser. No. 263,082, Jun. 21, 1994. This application Apr. 2, 1996, Ser. No. 626,597

Claims priority, application France, Aug. 3, 1993, 93 09533
Int. Cl.⁶ G06F 15/16

U.S. Cl. 393—704

8 Claims



1. A process for analyzing deadlocks in an operating system of a machine comprising a symmetrical multiprocessor operating in a UNIX environment, said process implemented by iteratively executing a specific function for tracing a thread from any one of plural processors in said symmetrical multiprocessor to any type of lock, said process comprising:

- searching all processors of said symmetrical multiprocessor for and identifying a waiting thread stopped on a lock or waiting for a holding signal from an element of said machine;
- searching for and identifying a holding thread that holds said lock or said holding signal from said element of said machine; and
- when said holding thread is itself waiting for another lock, repeating the previous process steps through chains of inter-related threads and locks until a cycle is identified, wherein said function makes it possible to reconstruct a deadlock, and hence a cycle, element by element.

5,590,336

METHOD AND APPARATUS FOR PERFORMING OVERLAPPING SERVICE OF MULTIPLE IDE PERIPHERAL DEVICES

William G. Parry, Bellevue, Wash., assignor to Microsoft Corporation, Redmond, Wash.


Filed Oct. 25, 1994, Ser. No. 328,481
Int. Cl.⁶ G06F 9/46; 13/22

U.S. Cl. 395—727

31 Claims

1. A method for performing overlapping service of requests from a computer to multiple peripheral devices connected to the computer, wherein each request includes a seek and a data transfer operation and wherein the time required for a first peripheral device to complete a seek operation is longer than the time required for a second peripheral device to complete a seek operation, said method comprising the steps of:

- initiating a seek operation for the first peripheral device in response to a request from the computer to the first peripheral device;
- starting a timer;



initiating execution of a request from the computer to the second peripheral device;
determining whether the first peripheral device has completed its seek operation when the timer times out;
executing a data transfer operation for the first peripheral device if the first peripheral device has completed its seek operation; resetting the timer and returning to said step of starting the timer if the first peripheral device has not completed its seek operation.

5,590,337

PROCESSOR INTERFACE CHIP FOR DUAL-MICROPROCESSOR PROCESSOR SYSTEM

Mizanur M. Rahman, Cupertino; Fred C. Sabernick, Sunnyvale; Jeff A. Sprouse, Mountain View; Martin J. Grosz, Santa Clara; Peter Fu, Sunnyvale, and Russell M. Rector, Oakland, all of Calif., assignors to Tandem Computers Incorporated, Cupertino, Calif.


Division of Ser. No. 88,562, Jul. 6, 1993, Pat. No. 5,435,001.

This application Apr. 21, 1995, Ser. No. 426,365

Int. Cl.⁶ G06F 9/46; 13/14

U.S. Cl. 395—735

2 Claims



1. An interrupt processing apparatus, wherein a microprocessor receives interrupt signals from a plurality of interrupt sources over a processor bus, wherein the interrupt signals set or reset interrupt flags in an interrupt register of the microprocessor and the microprocessor acts on the state of the interrupt flags, the interrupt processing apparatus comprising:

an interrupt image register, wherein said interrupt image register stores data indicative of states of the interrupt flags in the interrupt image register; and

interrupt filtering means, coupled between the processor bus and the plurality of interrupt sources and coupled to the interrupt

image register, for receiving interrupt signals and preventing the transfer of interrupt signals over the processor bus which do not change the state of the interrupt register, said interrupt filtering means comparing said received interrupt signals and contents of said interrupt image register to determine if said signal is a signal which would change the state of the interrupt register.

5,590,338

COMBINED MULTIPROCESSOR INTERRUPT CONTROLLER AND INTERPROCESSOR COMMUNICATION MECHANISM

Terry J. Parks, Round Rock, and Darius D. Gaskins, Austin, both of Tex., assignors to Dell USA, L.P., Austin, Tex.


Continuation of Ser. No. 96,588, Jul. 23, 1993, abandoned.

This application Aug. 8, 1995, Ser. No. 512,867

Int. Cl.⁶ G06F 13/24

U.S. Cl. 395—742

10 Claims



1. In a computer system including a first processor and a second processor, said computer system having a programmable interrupt controller for receiving a processor-associated vector and for correspondingly generating an interrupt request, a combined multiprocessor interrupt controller and interprocessor communication system comprising:

a system bus;

an input/output bridge element coupled to said system bus, said input/output bridge element comprising interrupt circuitry for receiving said interrupt request and for obtaining said processor-associated vector from said programmable interrupt controller, and

circuitry for packaging said processor-associated vector into an interprocessor communication message and for providing said interprocessor communication message onto said system bus; and

a system controller coupled to said system bus, said system controller comprising bus interface circuitry for receiving said interprocessor communication message from said input/output bridge element through said system bus, and

decode circuitry for decoding said interprocessor communication message and retrieving said processor-associated vector,

wherein said bus interface circuitry further provides said processor-associated vector to one of said first and second processors.

5,590,339

INPUT DEVICE INTERFACE WITH POWER CONNECT STATE AND SERIAL DATA CHANNEL ENABLING POWER TO THE DEVICE FROM TIME TO TIME


Hershow Chang, Hsin-Chu, Taiwan, assignor to Macronix International Co., Ltd., Hsinchu, Taiwan

Filed Aug. 23, 1993, Ser. No. 110,533

Int. Cl.⁶ G06F 1/32

U.S. Cl. 395—750

18 Claims



1. An interface between a host and an input device, comprising: a plurality of signal lines for connecting the input device to the host, including a power supply line, a data transmission line, a control signal transmitting line and a control signal receiving line;
power supply in communication with said power supply line for supplying power over said power supply line to the input device;
a data transmission channel coupled to said data transmission line for receiving data from the input device and for transferring the received data to the host; and
control logic coupled to the host and said power supply for enabling the supply of power over said power supply line to the input device from time to time, and monitoring said control signal receiving line to maintain the supply of power until a time out occurs, or until a data transfer on said data transmission channel ends.

5,590,340

APPARATUS AND METHOD FOR SUSPENDING AND RESUMING SOFTWARE APPLICATION ON A COMPUTER

Mitsuaki Morita, Hirakata; Masaya Miyazaki, Ikeda; Nobuyuki Enoki, Kadoma, and Akira Takuma, Kyoto, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 895,812, Jun. 9, 1992, abandoned.

This application Apr. 1, 1994, Ser. No. 221,993

Claims priority, application Japan, Jun. 10, 1991, 3-137484

Int. Cl.⁶ G06F 1/32

U.S. Cl. 395—750

10 Claims


1. A control unit of a computer system comprising: power supply means for supplying power to the computer system;

first storing means serving as a CPU's register, and input/output controlling device's register, and a volatile memory for holding written data while power is being supplied, said volatile memory's data includes graphic display data for generating a graphic display signal, and original graphic display data for generating the graphic display data;

second storing means for holding the data with no use of power; a power switch for selectively outputting one of an ON signal and an OFF signal in accordance with the selection of an operator;

power-off preserving means for selectively transferring data related to the original graphic display data from the first storing means to the second storing means while leaving the graphic display data in the first storing means, data read out from the first storing means being stored in the second storing means by said transferring operation;

power-off preserving controlling means for detecting the OFF signal from the power switch to instruct the power-off preserving means to initiate said transferring operation;



power supply stopping means for instructing the power supply means to stop the power supply when detecting the completion of said transferring operation;
window system processing means for refreshing the graphic display by generating the graphic display data based on the original graphic display data held in the second storing means and by storing it in the first storing means;
refresh requesting means for requesting the window system processing means to refresh the graphic display;
power supply restarting means for instructing the power supply means to restart the supply of the power by detecting the ON signal from the power switch;
power-on resuming means for reading out the data stored in the second storing means to return them to the first storing means; resuming means for the graphic display data for resuming the graphic display data based on the original graphic display data returned to the first storing means as well as storing the resumed graphic display data in the first storing means; and
power-on controlling means for instructing the power-on resuming means to execute said transferring by detecting the ON signal from the power switch, and for instructing the refresh requesting means to request the refresh operation.

5,590,341

METHOD AND APPARATUS FOR REDUCING POWER CONSUMPTION IN A COMPUTER SYSTEM USING READY DELAY

Eugene P. Matter, Folsom, Calif., assignor to Intel Corporation, Santa Clara, Calif.


Filed Sep. 30, 1994, Ser. No. 316,547

Int. Cl.⁶ G06F 1/04

U.S. Cl. 395—750

21 Claims

1. A computer system comprising:



a bus;

a memory coupled to the bus to store data and instructions;

a processor coupled to the bus for executing said instructions, wherein the processor performs bus cycles on the bus in

response to executing said instructions, and further wherein the processor enters a reduced power consumption state while at least one bus cycle is being performed and exits the reduced power consumption state upon completion of said at least one bus cycle; and

a controller coupled to the bus to monitor bus cycles from the processor, wherein the controller indicates completion of bus cycles to the processor using a completion indication coupled to the processor, wherein the controller withholds the completion indication for a period of time after completion of said at least one bus cycle to control power consumption by the processor, such that power consumption in the processor is reduced within an instruction boundary.

5,590,342

METHOD AND APPARATUS FOR REDUCING POWER CONSUMPTION IN A COMPUTER SYSTEM USING VIRTUAL DEVICE DRIVERS


Suresh K. Marisetty, San Jose, Calif., assignor to Intel Corporation, Santa Clara, Calif.

Filed Nov. 29, 1994, Ser. No. 346,040

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—750

35 Claims



11. A computer system comprising:

a bus;

a central processing unit (CPU) coupled to the bus running an operating system and at least one power-unaware application, wherein the operating system has a virtual device driver performing device idle detection using one or more events timers indicating the activity level of at least one local device, and further wherein the virtual device driver places idle local devices in a reduced power consumption state when associated events timers indicate that no activity has occurred for a predetermined period of time transparent to said at least one power-unaware application.

5,590,343

TOUCH-SENSITIVE SWITCHING CIRCUITRY FOR POWER-UP

Michael L. Bolan, Dallas, and Wendell L. Little, Denton, both of Tex., assignors to Dallas Semiconductor Corporation, Dallas, Tex.

Continuation of Ser. No. 87,239, Aug. 20, 1993, abandoned, which is a division of Ser. No. 998,897, Dec. 28, 1992, Pat. No. 5,249,298, which is a continuation-in-part of Ser. No. 283,268, Dec. 9, 1988, abandoned, and a continuation-in-part of Ser. No. 282,793, Dec. 9, 1988, abandoned, and a continuation-in-part of Ser. No. 283,267, Dec. 9, 1988, abandoned. This application Jul. 19, 1995, Ser. No. 504,228

Int. Cl.⁶ G06F 13/00; 1/32


U.S. Cl. 395—750

21 Claims

1. A circuit, for connection to an external contact pad, comprising:

a battery;

a power supply connected to receive current from an AC line;



a switch separate from said battery, said switch connected to disconnect said power supply from said AC line;

logic connected to detect a voltage transition on said external contact pad, such as may be caused when a user touches said external contact pad, and to selectively operate said switch when said voltage transition is detected, said logic being connected to be operated from said battery when said power supply is inoperative; and

at least one microprocessor connected to be powered by said power supply, wherein said external contact pad is electrically isolated from said power supply.

5,590,344

Patent Not Issued For This Number

5,590,345

ADVANCED PARALLEL ARRAY PROCESSOR (APAP)


Thomas N. Barker, Vestal; Clive A. Collins, Poughkeepsie; Michael C. Dapp, Endwell; James W. Dieffenderfer, Owego; Donald G. Grice, Kingston; Peter M. Kogge, Endicott; David C. Kuchinski, Owego; Billy J. Knowles, Kingston; Donald M. Lesmeister, Vestal; Richard E. Miles; Richard E. Nier, both of Apalachin, all of N.Y.; Eric E. Reiter, Warren Center, Pa.; Robert R. Richardson, Vestal, N.Y.; David B. Rolfe, West Hurley, N.Y.; Nicholas J. Schoonover, Tioga Center, N.Y.; Vincent J. Smoral; James R. Stupp, both of Endwell, N.Y., and Paul A. Wilkinson, Apalachin, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Continuation-in-part of Ser. No. 611,594, Nov. 13, 1990, abandoned, and Ser. No. 798,788, Nov. 27, 1991, abandoned, and Ser. No. 698,866, May 31, 1991, Pat. No. 5,313,645. This application May 22, 1992, Ser. No. 887,630

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—800

2 Claims



1. A computer system, comprising: a control unit, an interconnection system and a processing array for parallel processing

having nodes which are interconnected with the distribution system to other processing nodes, wherein: the control unit is programmable and has means for enabling the processing array having an array of processing elements to operate in coordination and which also enables a system control program to operate subsets of the parallel array with each subset dedicated to different applications or different phases of a single application program's processing, wherein

the interconnection system provides physical connections between the control unit and the elements of the parallel array of processing elements enabling data and control transfers which are completely independent of the transfer of data between elements of the processing array,

the interconnection system distributes functions associated with data transfer between elements of the processing array and distributed functions embedded in processing node software, and

the processing array provides non-shared memory and compute services and which are partitioned and the processing array is scalable

wherein the control unit and interconnection system provide means, including a broadcast bus path, for broadcasting data and instructions to the parallel array, for accumulating data and status information from the elements of the array, for generating and accepting status information which represents the union of the status derived from the elements of the array, and for controlling how elements of the parallel array interact with the broadcast bus path,

means for continuously and unobtrusively accumulating status from individual processing elements to facilitate programmer testing and tuning,

means for partitioning the elements of the array into subgroups that are controlled by interleaved commands and data transfers where:

subgroup size is specified by the application and/or system operating program and ranges from a single processing unit to the assembly of all processing units, subgroups may be assembled from any particular set of elements of the parallel array regardless of the particular address information associated with the specific elements,

means for generating program specified cross sections of the parallel array for assembly into partitions,

means for associating with each command or data, tag information to control which partition should receive the data,

means for writing to registers within the processor elements of the parallel array data specifying which partition code will be used to address the individual element,

means for writing commands and data to the elements of the parallel array which are passed to the units irrespective of the current status of the partition data within any particular element of the parallel array,

means for providing to elements of the parallel array a broadcast facility to all or subsets of the parallel array data specified by the application and/or system operating program, and such operations comprise sequential action of:

means for permitting all or a subset of the elements in the parallel array to signal the need for the broadcast,

means for accumulating and prioritizing broadcast requests,

means for causing the performance of a broadcast operation sequence,

means for initializing parallel processor system operations and for providing additional program loads when directed by an application and/or system operating program.

5,590,346

ANTENNA CAP FOR COMPUTER DEVICE UTILIZING A RADIO CARD

Guy J. West, and Ronald L. Mahany, both of Cedar Rapids, Iowa, assignors to Norand Corporation, Cedar Rapids, Iowa

Filed Jul. 26, 1993, Ser. No. 97,462

Int. Cl.⁶ G06F 1/16

U.S. Cl. 395—800

24 Claims

1. A computer device comprising:



a radio card having a radio card electrical interface and radio card antenna contacts disposed thereon;

a housing having an external surface, wherein said external surface includes an opening having a periphery;

a second electrical interface disposed within the opening of said housing;

said radio card electrical interface communicatively coupling with said second electrical interface upon insertion of said radio card through the opening of said housing;

a cap sized to engage said opening of said housing;

cap antenna contacts disposed on said cap to communicatively couple with said radio card antenna contacts upon engaging said cap with said opening of said housing; and

a first antenna connected to said cap antenna contacts.

5,590,347

METHOD AND SYSTEM FOR SPECIFYING ALTERNATE BEHAVIOR OF A SOFTWARE SYSTEM USING ALTERNATE BEHAVIOR INDICIA

David J. D'Souza, Kirkland; Neil Konzen, Bellevue, and David N. Weise, Kirkland, all of Wash., assignors to Microsoft Corporation, Redmond, Wash.


Filed Dec. 7, 1992, Ser. No. 987,363

Int. Cl.⁶ G06F 9/445

U.S. Cl. 395—800

31 Claims

17. A method in a computer system of operating a server with a



client, the server designed to provide a service to the client, the service having common steps and a plurality of behavior groups, each of the behavior groups including one or more alternative behaviors, each alternative behavior having a series of steps, the method comprising the steps of:

associating a plurality of indications with the client, each of the indications associated with one of the behavior groups and indicating the alternative behavior in that behavior group with which the client is compatible; under control of the client, requesting the service provided by the server; and under control of the server, executing the common steps; and for each of the behavior groups, determining the alternative behavior of that behavior group with which the client is compatible using the indication associated with that behavior group; and executing the steps of the determined alternative behavior.

5,590,348


STATUS PREDICTOR FOR COMBINED SHIFTER-ROTATE/MERGE UNIT

James E. Phillips, Binghamton; Bartholomew Blanner, Newark Valley, and Stamatis Vassiliadis, Vestal, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jul. 28, 1992, Ser. No. 920,962
Int. Cl. G06F 9/00; 5/00

U.S. Cl. 395—564

25 Claims



1. A computer system comprising in combination: a combination shift-rotate/merge functional unit having input operands comprised of a left half and right half parts, an instruction decode and issue means for decoding and issuing instructions to the functional unit, said functional unit comprising means responsive to said instructions to carry out a shift function to shift the bits of one or more of said operands to more or less significant bit positions, and to carry out a merge function to merge said operands, a status mask generator responsive to said instructions to generate a status mask, and a status generator responsive to said status mask and said operands to predict the status of the result to be produced by said functional unit in response to said instructions, said status including a status condition which depends upon said shift function and a status condition which depends upon said merge function.

5,590,349

REAL TIME PROGRAMMABLE SIGNAL PROCESSOR ARCHITECTURE


Jeffrey I. Robinson, New Fairfield; Keith Rouse, Oxford, both of Conn., and Bruce R. Musicus, Arlington, Mass., assignors to Logic Devices, Inc., Sunnyvale, Calif.
Continuation of Ser. No. 525,977, May 18, 1990, abandoned, which is a continuation-in-part of Ser. No. 217,616, Jul. 11, 1988, Pat. No. 5,068,823. This application Jun. 18, 1992, Ser. No. 900,536

Int. Cl. G06F 15/173

U.S. Cl. 395—800

87 Claims

1. A programmable, real time, signal processor apparatus designed for semiconductor integration, which receives regularly



clocked data signals from means external said signal processor apparatus, and processes said data signals in a real time fashion, thereby generating processed data signals which are available external to said processor apparatus as regularly clocked output signals, comprising:

- at least one data signal receiving means for receiving said regularly clocked data signals from said means external said signal processor apparatus;
- a multiported central memory unit coupled to said data signal receiving means for storing said received data signals, said data signal receiving means including means for regularly forwarding said received data signals to desired locations in said multiported central memory unit;
- a plurality of digital processor means coupled to said multiported central memory unit, for obtaining said data signals from said multiported central memory unit, for processing said data signals thereby generating processed data signals, and for sending said processed data signals for storage in said multiported central memory unit;
- a program memory means coupled to said plurality of digital processors for storing microinstructions for said plurality of digital processors, wherein said digital processors process said data signals according to said microinstructions stored in said program memory means;
- at least one output port coupled to said multiported central memory unit for obtaining said processed data signals from said multiported central memory unit and providing said processed data signals as regularly clocked output signals to means external to said processor apparatus; and
- at least one data bus coupling said plurality of digital processor means, said at least one output port, and said at least one data signal receiving means to said multiported central memory unit, wherein substantially all data received by said data receiving means is forwarded via said at least one data bus to said multiported central memory unit, obtained from said multiported central memory unit via said at least one data bus and processed by at least one of said plurality of digital processor means to generate said processed data signals, and said processed data signals are forwarded via said at least one data bus to said multiported central memory unit for either obtaining via said at least one data bus by at least one of said plurality of digital processor means for additional processing or for obtaining via said at least one data bus and output by said at least one output port as a regularly clocked output signal at a rate related to the rate of said received regularly clocked data signals.

5,590,350

THREE INPUT ARITHMETIC LOGIC UNIT WITH MASK GENERATOR


Karl M. Guttig, Missouri City, Tex.; Keith Balmer, Bedford, England; Robert J. Gove, Plano, Tex.; Christopher J. Read, Houston, Tex.; Jeremiah E. Golston, Sugar Land, Tex.; Sydney W. Poland, Katy, Tex.; Nicholas Ing-Simmons, Alconbury Weston, and Philip Moyse, Bromham, both of England, assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Nov. 30, 1993, Ser. No. 159,282

Int. Cl. G06F 9/00; H03K 19/00

U.S. Cl. 395—800

75 Claims



1. A data processing apparatus comprising:

- an arithmetic logic unit having first, second and third data inputs for multibit digital signals representing corresponding first, second and third input signals, and a function control input signal for receiving a function signal, said arithmetic logic unit generating at an output a multibit digital signal representing a mixed arithmetic and Boolean combination of said first, second and third inputs corresponding to said function signal, said mixed arithmetic and Boolean combination including at least one combination performing a Boolean function prior to an arithmetic function;
- a first data source supplying a first multibit digital signal to said first data input of said arithmetic logic unit;
- a second data source supplying a second multibit digital signal to said second data input of said arithmetic logic unit;
- a third data source supplying a third multibit digital signal;
- a mask generator having a data input connected to said third data source and a data output connected to said third data input of said arithmetic logic unit, said mask generator generating a multibit digital mask signal corresponding to said third multibit digital signal.

5,590,351

SUPERSCALAR EXECUTION UNIT FOR SEQUENTIAL INSTRUCTION POINTER UPDATES AND SEGMENT LIMIT CHECKS

Elliot A. Sowadsky, Santa Clara; Larry Wldigen, Salinas; David L. Puziol, Sunnyvale, and Korbin S. Van Dyke, Fremont, all of Calif., assignors to Advanced Micro Devices, Inc., Sunnyvale, Calif.


Filed Jan. 21, 1994, Ser. No. 185,488

Int. Cl. G06F 9/38

U.S. Cl. 395—800

20 Claims

17. A sequential instruction pointer execution unit for a processor that executes instructions, said instructions including branch instructions, said branch instructions having respectively associated not-taken-direction and taken-direction control flow paths, said taken-direction control flow paths also being referred to as instruction streams, said processor tracking a plurality of said instruction streams, said sequential instruction pointer execution unit being one type of a plurality of types of execution units within said processor, said sequential instruction pointer execution unit performing superscalar instruction pointer updates for a plurality of sequential operations, said operations being associated with said instructions, said sequential instruction pointer execution unit



executing at least some of said plurality of sequential operations speculatively, said sequential instruction pointer execution unit comprising:

- first storage for a first and a second of said plurality of operations, said second operation being sequential to said first operation, said first and second operations having respective first and second instruction length values;
- instruction pointer selection logic, said selection logic providing a current instruction pointer value, said instruction pointer selection logic including storage for a plurality of next instruction pointer values respectively associated with said plurality of instruction streams;
- an adder having
 - a first input, said first input being coupled to said current instruction pointer value;
 - a second input, said second input being coupled to said first instruction length value;
 - a third input, said third input being coupled to said second instruction length value;
 - a first sum output providing a first instruction pointer update equal to the addition of said current instruction pointer value and said first instruction length value, said first instruction pointer update corresponding to the execution of said first operation, said first sum output being coupled to said instruction pointer selection logic;
 - a second sum output, said second sum output providing a second instruction pointer update equal to the addition of said current instruction pointer value to said first and second instruction length values, said second instruction pointer update corresponding to the simultaneous execution of said first and second operations, said second sum output being coupled to said instruction pointer selection logic;
 - a first wrap-carry output bit, associated with said first instruction pointer update by said first instruction length value; and
 - a second wrap-carry output bit, associated with said second instruction pointer update by said first and said second instruction length values; and
- an instruction pointer storage array storing a plurality of speculative instruction pointer values corresponding to at least some of said plurality of sequential operations, said instruction pointer storage array being coupled to said instruction pointer selection logic.

5,590,352

DEPENDENCY CHECKING AND FORWARDING OF VARIABLE WIDTH OPERANDS

Gerald D. Zuraski, Jr.; Scott A. White; Murali S. Chinna-konda, and David S. Christie, all of Austin, Tex., assignors to Advanced Micro Devices, Inc., Sunnyvale, Calif.


Filed Apr. 26, 1994, Ser. No. 233,567

Int. Cl. G06F 9/38

U.S. Cl. 395—800

31 Claims

24. A processor which executes operations operating on variable-sized operands, comprising: an instruction decoder including:



an operand field selector which defines a variable-sized operand and by partitioning a full-sized operand bit-wise into a plurality of operand fields and identifying operand fields utilized by the operation, and

a dispatcher coupled to the operand field selector to dispatch operation codes, operand identifiers and utilized operand field identifiers;

a reorder buffer coupled to the instruction decoder and including:

- a speculative result memory coupled to the dispatcher to receive operand identifiers and utilized field identifiers;
- a reorder buffer controller responsive to the dispatching means to allocate entries in the speculative result memory;
- a data dependency detector coupled to the reorder buffer controller which detects data dependencies of a utilized operand field independently of other fields; and
- a tagging circuit coupled to the dependency detector and responsive to a data dependency to tag a data dependent operand field independently of other fields;

an operand bus coupled to the reorder buffer for communicating operand fields and operand field tags;

a functional unit coupled to the operand bus to receive the operand fields and the operand field tags and execute operations defined by the dispatched operation code utilizing the operand fields to generate result data; and

a result bus connected from the functional unit output to the inputs of the reorder buffer and the functional unit to forward operation result data thereto.

5,590,353

VECTOR PROCESSOR ADOPTING A MEMORY SKEWING SCHEME FOR PREVENTING DEGRADATION OF ACCESS PERFORMANCE

Tadayuki Sakakibara, Kunitachi; Teruo Tanaka, Hachioji; Yoshiko Tamaki, Kodaira, all of Japan; Katsuyoshi Kitai, Palo Alto, Calif., and Yasuhiro Inagami, Kodaira, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jul. 15, 1994, Ser. No. 275,388


Claims priority, application Japan, Jul. 15, 1993, 5-175115
Int. Cl.⁶ G06F 15/16

U.S. Cl. 395—800

17 Claims

1. A vector processor, comprising:

a storage unit including a number (N) of memory modules, which number is given by a power of two and in which an interleave method of successively assigning continuous addresses to memory modules which differ from one to another is adopted;



a number (N) of access request circuits for issuing a number (N) of access requests in parallel for vector data stored in said storage unit; and

a storage control apparatus for transferring the access requests issued by said access request circuits to desired memory modules;

wherein said storage control apparatus includes access request buffer units provided in one-to-one correspondence to said access request circuits holding the access requests, respectively, and an access request priority determining circuit for arbitrating access conflict taking place upon transferring of the access requests from said plurality of access request circuit to said plurality of memory modules;

said storage control apparatus further including address decoder means for determining identification numbers of the transfer destination memory modules from addresses accompanying said access requests issued from said access request circuits, said address decoder means determining identification numbers of said memory modules which differ sequentially in accordance with a predetermined relation formula so long as said addresses vary with a predetermined skew periodicity (m), and which are shifted by a given number every time said address varies by said predetermined skew periodicity (m), said storage control apparatus further including means for making said predetermined skew periodicity (m) equal to skew periodicities of other vector processors which belong to a same system series (same machine or product series) of vector processors and which differ from one another mutually in respect to said number N.

5,590,354

MICROCONTROLLER PROVIDED WITH HARDWARE FOR SUPPORTING DEBUGGING AS BASED ON BOUNDARY SCAN STANDARD-TYPE EXTENSIONS

Peter Klapproth; Frederik Zandveld; Jacobus M. Bakker, and Gerardus C. Van Loo, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Jul. 28, 1994, Ser. No. 281,964


Claims priority, application European Pat. Off., Jul. 28, 1993, 93202228

Int. Cl.⁶ G06F 11/00

U.S. Cl. 395—800

10 Claims

1. A microprocessor comprising a processor element, a memory interface element, an IO interface element, a debug support element and an internal bus directly connected to all above elements, said microprocessor further comprising a registered boundary scan standard (JTAG) interface element directly connected to said internal bus, said JTAG interface element accessing one or more scan chains inside said microprocessor, and said JTAG interface element furthermore controlling DMA-type exchanges via said internal bus with other elements connected to said internal bus for debugging software running on said microprocessor.



5,590,355

DATA DRIVEN PROCESSOR, A DATA DRIVEN INFORMATION PROCESSING DEVICE, AND A METHOD OF VERIFYING PATH CONNECTIONS OF A PLURALITY OF DATA DRIVEN PROCESSORS IN SUCH A DATA DRIVEN INFORMATION PROCESSING DEVICE

Ricardo T. Shichiku, Tenri; Shinichi Yoshida, Kashihara; Tsuyoshi Muramatsu, Tenri; Manabu Onozaki, Nara, and Yasuhiro Matsuura, Kitakatsuragi-gun, all of Japan, assignors to Sharp Kabushiki Kaisha, Osaka-fu, Japan


Filed Aug. 9, 1994, Ser. No. 287,919

Claims priority, application Japan, Aug. 11, 1993, 5-199766;
Mar. 25, 1994, 6-055641

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—800

12 Claims



9. A data driven information processing device comprising:

a plurality of data driven processors, and

connection means for connecting said plurality of data driven processors to each other such that any two processors can be connected at least indirectly,

wherein each of said plurality of data driven processors comprises

an input port and at least two output ports,

output destination information memory means for storing output destination information specifying an output port from which a data packet is to be output in path verification testing,

disable means for selectively disabling instruction execution, by the data driven processor such that only a state of a path verification flag in the data packet is changed, of an instruction held in an instruction field of the data packet, as a function of the state of the verification flag in the data packet, regardless of the nature of the instruction held by the instruction field; and

selective output means, connected to said input port, for selectively providing an input data packet to one of said output ports according to the path verification flag and destination information included in said data packet and according to said output destination information, when instruction execution is disabled,

wherein said connection means comprises a plurality of data transmission paths for connecting said input port of said plurality of data driven processors to an output port of another of said data driven processors.

5,590,356

MESH PARALLEL COMPUTER ARCHITECTURE APPARATUS AND ASSOCIATED METHODS


Ira H. Gilbert, Carlisle, Mass., assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Filed Aug. 23, 1994, Ser. No. 294,757

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—800

40 Claims



1. Digital data processing apparatus for synchronously processing data from a host computer, comprising:

program memory means for storing data, and bus means connecting said program memory means to the host computer;

a master processor element and an array of slave processor elements, said master processor element having means to access said data within said program memory and for broadcasting instructions to said array; and

input/output module means connected to communicate with said bus means and having a plurality of data links connected to said array, each of said data links providing serial communication with selected slave processor elements;

wherein each of said slave processor elements comprises

(i) an input/output processor section having interprocessor communication links for communicating data through link ports to and from selected other processor elements within said array, and further having means for communicating data to and from said input/output module means, the input/output processor section being programmable to through-route data by defining transfer leg specifications including link port selection and leg durations,

(ii) internal memory means having a storage capacity of at least 128 kilobytes for storing executable code and data, and

(iii) a core processor section for processing said executable code and said instructions, each of said processor sections being operable independently from the other of said processor sections;

said slave processor elements synchronously executing at least one of said instructions and said executable code.

5,590,357

INTEGRATED CPU CORE AND PARALLEL, INDEPENDENTLY OPERATING DSP MODULE AND TIME-CRITICAL CORE PRIORITY SCHEME


Amos Intrater, Natanya, Israel; Andy Birenbaum, Lyons, France; Gideon Intrater, Tel-Aviv, Israel; Iddo Carmon, Kfar Saba, Israel; Ilan Shimony, Ramat-Gan, Israel; Itai Fraenkel, Petah Tikva, Israel; Lev Epstein, Holon, Israel; Lior Katzri, Ramat-Aviv, Israel; Omri Viner, Hod Hasharon, Israel; Raya Levitan, Givataim, Israel; Ronny Cohen, Ramat-Hasharon, Israel; Sidi Yomtov, Nex-Ziona, Israel; Yehezkel Tzadik, Hedera, Israel; Zvi Greenfeld, Kfar Saba, Israel; Israel Greiss, Raanana, Israel; Oved Oz, Yachin Afek, both of Kfar Saba, Israel; Meir Tsadik, Hod Hasharon, Israel; Moshe Doron, Givataim, Israel, and Alberto Sandbank, Natanya, Israel, assignors to National Semiconductor Corporation, Del.

Continuation of Ser. No. 63,403, May 17, 1993, abandoned, which is a division of Ser. No. 806,082, Dec. 6, 1991, abandoned. This application Sep. 6, 1994, Ser. No. 301,739

Int. Cl.⁶ G06F 13/12; 13/24

U.S. Cl. 395—800

2 Claims



1. An integrated circuit data processing system comprising:
 - a shared internal bus for transferring both data and instructions;
 - a shared bus interface unit connected to the shared internal bus and connectable via a shared external bus to a shared external memory array such that instructions and data stored in the shared external memory may be transferred to the shared internal bus via the shared bus interface unit;
 - a general purpose (GP) central processing unit (CPU) connected to the shared internal bus for retrieving GP instructions, the GP CPU including means for executing GP instructions to process data retrieved by the GP CPU from the shared internal bus;
 - a digital signal processor (DSP) module connected to the shared internal bus, the DSP module including means for executing DSP command-list code instructions to process an externally-provided signal received by the DSP module and to access the external system memory, execution of the DSP command-list code instructions by the DSP module being independent of and in parallel with execution of GP instructions by the GP CPU, wherein the GP CPU includes arbitration means for arbitrating access to the shared external memory such that access to the shared external memory responsive to execution of command-list code instructions by the DSP module is at a higher priority than access to the shared external memory responsive to execution of instructions by the GP CPU;
 - means associated with the GP CPU for indicating that the GP CPU is performing time-critical operations; and
 - means associated with the DSP module and responsive to the indication that the GP CPU is performing time-critical operations, for preventing the DSP module from executing command-list code instructions which cause access to the shared external memory, whereby the DSP module is temporarily prevented from interfering with the time-critical operations being performed by the GP CPU.

5,590,358

PROCESSOR WITH WORD-ALIGNED BRANCH TARGET IN A BYTE-ORIENTED INSTRUCTION SET


Ori K. Mizrahi-Shalom, San Jose, and Kung-Ling Ko, Union City, both of Calif., assignors to Philips Electronics North America Corporation, New York, N.Y.

Filed Sep. 16, 1994, Ser. No. 308,337

Int. Cl.⁶ G06F 9/00

U.S. Cl. 395—800

11 Claims



10. A system, comprising:
 - a code generator performing instruction expansion and code manipulations to align transfer target addresses on word boundaries; and
 - a processor, comprising:
 - an instruction queue receiving byte aligned instructions;
 - an alignment multiplexer coupled to said queue and aligning the instructions for execution;
 - a program counter register designating addresses of instructions fetched;
 - an instruction address modification unit coupled to said program counter register and modifying a program counter using a word-aligned address when loading a schedule program flow change address and using a byte-aligned address otherwise;
 - transfer means for returning from unplanned program flow changes using byte aligned addresses; and
 - execution means for executing the fetched instructions.

5,590,359

METHOD AND APPARATUS FOR GENERATING A STATUS WORD IN A PIPELINED PROCESSOR

Harshvardhan P. Sharaogpani, Santa Clara, Calif., assignor to Intel Corporation, Santa Clara, Calif.


Continuation of Ser. No. 925,984, Aug. 5, 1992, abandoned.

This application Sep. 27, 1994, Ser. No. 313,728

Int. Cl.⁶ G06F 9/00

U.S. Cl. 395—800

20 Claims



8. In a microprocessor capable of executing an x87 instruction set and having a pipelined floating point unit with a plurality of stages including a first stage and a last stage, a method of generating an x87 Status Word for an instruction as it completes the last stage of the execution pipeline, said method comprising the steps of:
 - decoding an instruction into a stream of microvectors or into a single microvector, wherein each of said microvectors comprises a plurality of control fields, wherein a first control field provides control directives for updating a TOS component of the Status Word, a second control field provides boundary

information specifying first and last microvectors of said stream of microvectors representing said instruction, wherein if said instruction is decoded into a single microvector said second control field specifies both a first and last microvector, a third control field controls an updating of a plurality of condition code bits P, C1, C0, C2 and C3 of said Status Word and a fourth control field controls the updating of a plurality of components SF, U, 0, Z, D and I of said Status Word;

providing in the last stage of the pipeline storage means SW for storing the x87 Status Word representing overall status of the floating point unit due to a plurality of executed instructions, said SW storage means having storage means for each bit of the x87 Status Word, a SW.B storage means for storing a busy bit of the Status Word, storage means SW.C3, SW.C2, SW.C1, SW.CO, for storing the condition code bits C3, C2, C1 and CO, of the Status Word, respectively, a SW.ES storage means for storing an error summary bit of the Status Word, a SW.SF storage means for storing a stack flag bit of the Status Word, a SW.P storage means for storing a status precision bit of the Status Word, a SW.U storage means for storing an underflow exception bit of the Status Word, a SW.O storage means for storing an overflow exception bit of the Status Word, a SW.Z storage means for storing a zero divide bit of the Status Word, a SW.D storage means for storing a denormalized operand bit of the Status Word, a SW.I storage means for storing an invalid operation bit of the Status Word, a SW.TOS storage means for storing a top of stack pointer of said Status Word;

providing storage means (TSW) in a stage prior to said last stage of said pipelined floating point unit said storage means for storing and accumulating status data of said individual microvectors of said instruction, wherein when said last microvector of said instruction is in the second to last stage of the pipeline said accumulated status data representing the status of the floating point unit due to said instruction alone, said TSW storage means having storage means TSW.C3, TSW.C2, TSW.C1, TSW.CO, for storing the condition code bits C3, C2, C1 and CO, respectively, representing the status of the floating point unit due to said instruction alone, a TSW.SF storage means for storing the stack flag bit representing the status of the floating point unit due to said instruction alone, a TSW.P storage means for storing the precision bit representing the status of the floating point unit due to said instruction alone, a TSW.U storage means for storing the underflow exception bit representing the status of the floating point unit due to said instruction alone, a TSW.Z storage means for storing the zero divide bit representing the status of the floating point unit due to said instruction alone, a TSW.D storage means for storing the denormalized operand bit representing the status of the floating point unit due to said instruction alone, a TSW.I storage means for storing the invalid operation bit representing the status of the floating point unit due to said instruction; associating a valid bit VP with said TSW.P storage means, associating a valid bit VC1 with said TSW.C1 storage means and associating a valid bit Vcc with the group of TSW.CO, TSW.C2 and TSW.C3 storage means wherein said valid bits indicate when said associative storage means contains valid data;

generating with each microvector of said instruction a TOS value, wherein said TOS value is generated from said first control field of said microvector, and staging down said TOS value, along with said microvector which generated said TOS value, to said TSW.TOS storage means; clearing said TSW.B, TSW.C3, TSW.C2, TSW.C1, TSW.CO, TSW.ES, TSW.SF, TSW.P, TSW.U, TSW.O, TSW.Z, TSW.D and TSW.I storage means each time a first microvector enters the second to last stage of the pipeline; updating with each microvector of said instruction a prespecified group of said TSW.CO, TSW.C1, TSW.C2, TSW.C3 and TSW.P storage means and setting said associated valid bits of

those storage means which have been updated, said updated group specified by said third control field of said microvector; updating with each microvector of said instruction said TSW.SF, TSW.U, TSW.O, TSW.Z, TSW.D and TSW.I storage means according to said fourth control field of said microvectors; and generating when said last microvector is in the last stage of the pipeline a new Status Word from said accumulated status stored in said TSW storage means and from the current Status Word presently stored in said SW storage means said new Status Word providing the overall status of the processor after execution of said instruction.

5,590,360

APPARATUS AND METHOD FOR GATHERING AND ENTERING DATA REQUIREMENTS FROM MULTIPLE USERS IN THE BUILDING OF PROCESS MODELS AND DATA MODELS

Geraldine E. Edwards, Redding, Conn., assignor to International Business Machines Corporation, Armonk, N.Y.


Continuation of Ser. No. 962,764, Oct. 19, 1992, abandoned.

This application Dec. 20, 1994, Ser. No. 360,195

Int. Cl.⁶ G06F 15/00

U.S. Cl. 395—800

10 Claims



7. Apparatus for gathering information for modeling a preselected Process or a dataflow, said apparatus comprising:
 - a local area network having a plurality of user terminals and an analyst terminal on the network, each terminal having a respective display and means for entering data;
 - computer server means, connected to the network and having a centralized database, for receiving from the terminals and storing in the database information related to the preselected Process or dataflow;
 - means for displaying at least one data item on each user display to prompt each user to selectively respond with input;
 - means for providing the same data items to each user display for display at the same time;
 - means for enabling the user at each user terminal to enter natural language information for the preselected Process or dataflow into the centralized database;
 - means for storing data received from the plurality of user terminals in common tables in the centralized database;
 - information engineering tool means for constructing decomposition models or dataflow models or Entity relationship diagrams or a combination thereof based on data files having a prescribed format;
 - bridge means for converting the stored data in the database into data files in the prescribed format; and
 - means for connecting the bridge means and information engineering tool means and for exporting the data files converted by the bridge means to the information engineering tool means;
- wherein the bridge means includes:
- token identifier means for assigning and storing, in files corresponding to the files recognized by the information engineering tool means, token identifiers for (i) Parent Processes and subsidiary Processes that compose each Par-


ent Process, (ii) Data Flows, (iii) External Agents, (iv) Associations, (v) Entities associated with Data Flows, and (vi) Attributes associated with Entities; means for selecting and associating all offspring Processes which compose a Parent Process and storing an association therebetween; and means for assigning, to Information assigned a token by the token identifier means, type codes that are prescribed by the information engineering tool means.

5,590,361

MICROPROCESSOR HAVING AN EFFECTIVE BICMOS EXTRA MULTIPLE INPUT COMPLEX LOGIC CIRCUIT
Masahiro Iwamura; Tatsumi Yamauchi; Shigeya Tanaka, all of Hitachi, and Kazutaka Mori, Higashiyamato, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Continuation of Ser. No. 748,511, Aug. 22, 1991, abandoned.
This application Dec. 23, 1994, Ser. No. 364,406
Claims priority, application Japan, Aug. 31, 1990, 2-228136
Int. Cl. G06F 15/00

U.S. Cl. 395-800

21 Claims



5. A complex logic circuit comprising:

N ($N \geq 2$) number of unit logic circuits, each of said unit logic circuits including:
a CMOS logic circuit for outputting one signal in response to M ($M \geq 1$) input signals, and
a bipolar transistor, of which the collector is connected to a power source, the base is connected to an output of said CMOS circuit, and the emitter being connected to a common output line;
a connection node coupled to said common output line for connecting outputs of said unit logic circuits; and
common output line pull-down means provided between said connection node and a reference voltage for pulling down the common output line to a same level as said reference voltage when said common output line is not energized, wherein one logic output is output in response to $M \times N$ input signals from said connection node.


5,590,362

DATABASE ENGINE PREDICATE EVALUATOR

Richard I. Baum, Poughkeepsie; Glen A. Brent, Fishkill; Donald H. Gibson, Salt Point, and David B. Lindquist, Poughkeepsie, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Continuation of Ser. No. 243,729, May 17, 1994, which is a continuation of Ser. No. 993,170, Dec. 18, 1992, abandoned, which is a division of Ser. No. 499,849, Mar. 27, 1990, Pat. No. 5,082,740. This application Jan. 24, 1995, Ser. No. 378,905
Int. Cl. G06F 15/00

U.S. Cl. 395-800

4 Claims



1. An apparatus for performing predicate evaluation, said apparatus comprising

instruction table means for storing a predicate evaluation program, the instruction table means comprising means for receiving the predicate evaluation program from an external processor;

instruction register means, coupled with the instruction table means, for receiving an instruction to be executed from the instruction table means, said instruction register means including a field for storing a branching condition and a field for storing a branching address;

internal processor means coupled with the instruction table means, coupled with the instruction register means, for controlling a sequence of operations within the predicate evaluation apparatus in accordance with the predicate evaluation program, said internal processor being programmable by said predicate evaluation program;


next field branching means, coupled with the instruction register means and responsive to a branch condition stored in said field for storing a branch condition, for determining when a processing operation of a predicate evaluation query causing processing of records in operations on sequential portions produces a result matching said branch condition, without processing the entire record, and for causing the internal processor means to branch to said branch address and around unnecessary instructions for processing the rest of the record in the predicate evaluation program for processing the query;
a stack for temporarily holding data during the processing of the predicate evaluation program, said data being other than said predicate evaluation program; and
comparator means, coupled with the internal processor means, for comparing a first value from the top of the stack with a second value obtained from the working storage.

5,590,363

CIRCUIT FOR DETECTION OF CO-PROCESSOR UNIT PRESENCE AND FOR CORRECTION OF ITS ABSENCE
David R. Lunsford, and Michael D. Durkin, both of Austin, Tex., assignors to Dell USA, L.P., Austin, Tex.
Continuation of Ser. No. 750,442, Aug. 20, 1991, abandoned, which is a continuation of Ser. No. 339,690, Apr. 18, 1989, abandoned. This application May 14, 1993, Ser. No. 387,658
Int. Cl. C06F 15/16

U.S. Cl. 395-800

5 Claims



5. A personal computer system having a local bus, a central processor unit (CPU) for producing a first signal, and an optional co-processor unit that is addressable by the CPU and that is capable of producing a second signal, the system comprising:

- a socket, having pins, for receiving the co-processor unit, the pins being connected to communicate with the CPU through the local bus;
- a presence-detect circuit receiving a signal indicative of whether the co-processor unit is mounted in the socket, and providing an output signal at a first voltage level when the co-processor unit is mounted in the socket, and at a second voltage level when the co-processor unit is not mounted in the socket; and
- a logic circuit capable of receiving the output signal from the presence-detect circuit, the first signal from the CPU, and the second signal from the optional co-processor unit and providing a third signal that is responsive to the second signal if the co-processor unit is installed into the socket and responsive to the first signal if the co-processor unit is not installed into the socket.

5,590,364


SIGNAL PROCESSING APPARATUS

Kohtaro Hanzawa, Iruma; Goro Sakata, Mitaka, and Kikuji Tanaka, Fussa, all of Japan, assignors to Casio Computer Co., Ltd., Tokyo, Japan
Continuation of Ser. No. 150,542, Nov. 10, 1993, which is a continuation of Ser. No. 770,646, Oct. 3, 1991, abandoned.
This application Mar. 17, 1995, Ser. No. 407,498
Claims priority, application Japan, Oct. 31, 1990, 2-294569
Int. Cl. G06F 9/45

U.S. Cl. 395-800

12 Claims

1. A signal processing apparatus comprising:



storing means for storing contents including a first program;

processing means for processing an input signal based on the first program received from said storing means within a period of a cycle of a sync signal and for outputting a processed signal;

instructing means for generating an instruction signal for instructing rewriting of said contents stored in said storing means;

instruction signal outputting means for outputting the instruction signal generated by said instructing means, in synchronism with the sync signal which is generated immediately after the instruction signal is generated by said instruction means;

control means for preventing the first program from being sent from said storing means to said processing means, in response to the instruction signal output from said instruction signal outputting means, and for enabling the first program stored in said storing means to be rewritten; and

writing means for writing a second program onto the first program stored in said storing means, the second program being different from the first program stored in said storing means, when said control means has enabled said contents of said storing means to be rewritten, and for sending the second program to be written in said storing means to said processing means, so as to enable said processing means to process the input signal based on said second program while said second program is being written onto the first program in said storing means, such that an operation by said writing means for writing the second program onto the first program in said storing means and an operation by said processing means for processing the input signal based on the second program are performed simultaneously, wherein the input signal is continuously processed based on the first and second programs without an interruption.


5,590,365

PIPELINE INFORMATION PROCESSING CIRCUIT FOR FLOATING POINT OPERATIONS

Nobuhiro Ide, Tokyo-to; Takeshi Yoshida, Kanagawa-ken; Yoshihisa Kondo, Kanagawa-ken; Masato Nagamatsu, Kanagawa-ken; Junji Mori, Kanagawa-ken, and Itaru Yamazaki, Kanagawa-ken, all of Japan, assignors to Kabushiki Kaisha Toshiba, Kawasaki, Japan
Continuation of Ser. No. 678,711, Apr. 1, 1991, abandoned.
This application Mar. 21, 1995, Ser. No. 408,125
Claims priority, application Japan, Mar. 30, 1990, 2-084721; Jun. 7, 1990, 2-147499
Int. Cl. G06F 7/38

U.S. Cl. 395-394

22 Claims



7. An operation unit for floating point arithmetic operations, comprising:

first operation means which has a bit width sufficient for carrying out a first operation, and can be operated in a first operation mode for carrying out the first operation and a second operation mode for carrying out a second operation, second operation means having a bit width sufficient at least for carrying out the second operation,

third operation means which has a bit width sufficient for carrying out the first operation, and can be operated in the first operation mode and the second operation mode;
 fourth operation means having a bit width sufficient at least for carrying out the second operation, and
 fifth operation means which has a bit width sufficient for carrying out the first operation, and is operated in the first operation mode, the second operation mode and a third operation mode for carrying out two different sets of second operations are carried out at a same time.

5,590,366

PACKET FORWARDING SYSTEM FOR MEASURING THE AGE OF DATA PACKETS FLOWING THROUGH A COMPUTER NETWORK

Stewart F. Bryant, Redhill, England; Michael J. Seaman, San Jose, Calif., and Christopher R. Schmidt, Reading, England, assignors to Digital Equipment Corporation, Maynard, Mass.


Continuation of Ser. No. 889,551, May 27, 1992, abandoned.

This application Apr. 13, 1995, Ser. No. 421,141

Int. Cl. G06F 13/00

U.S. Cl. 395-800

2 Claims



1. A packet forwarding station for a computer network, comprising:

- a receiving module for receiving a plurality of packets, each packet having an age held; and
- an output module, said output module including:
 - a timing means for defining successive time intervals;
 - means for grouping each packet into one of a plurality of groups in dependence on said successive time interval in which each packet arrives at said station;
 - age measuring means, including a group counter, for maintaining an age for each of said groups, said group counter maintaining a running count of said groups;
 - a shift register having a plurality of stages, said stages including:
 - a top stage and a bottom stage, each stage for containing a packet count of how many of said packets were grouped into one of said groups;
 - wherein when said timing means defines a new time interval, a packet count contained in said top stage is shifted out of said shift register, a packet count contained in each of the other stages is shifted into an emptied stage of said shift register, and a packet count contained in said bottom stage is set to zero, said packet count contained in said bottom stage then incrementing whenever a new packet is received by said receiving module during said new time interval; and
 - an overflow accumulator for receiving a packet count shifted out of said top stage of said shift register;
 - said output module for using said group counter to alter the age field of a first packet before transmitting said first packet, and for discarding a second packet when said second packet is included in a packet count that is shifted out of said top stage.

5,590,367 PROCESSING MODULE FOR PROGRAMMABLE PROCESSING USING COMPUTER GENERATED HOLOGRAMS


Tsen-Hwang Lin, Dallas, and Falvey Malarcher, Plano, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Continuation of Ser. No. 275,463, Jul. 14, 1994, abandoned, which is a continuation of Ser. No. 809,595, Dec. 18, 1991, abandoned. This application Jun. 6, 1995, Ser. No. 466,028

Int. Cl. G06F 3/00

U.S. Cl. 395-800

4 Claims



1. A processing module comprising:

- a. at least one processing board comprising a plurality of processing elements each processing element comprising:
 - i. at least one signal receiver for receiving an incoming signal to said processing element;
 - ii. at least one signal transmitter for transmitting an outgoing signal from said processing element;
 - iii. at least one digital micromirror device to provide intra-board and interboard communication with other processing elements;
- b. at least one computer generated hologram board which, in conjunction with said digital micromirror device, directs said outgoing signal and said incoming signal to and from other processing elements;
- c. at least one extension board which, in conjunction with said digital micromirror device and said computer generated hologram board, provides interboard communication between said processing element on said processing board and other processing elements on other processing boards; and
- d. at least one clear spot on said computer generated hologram board which allows said incoming signal and said outgoing signal from said processing element to reach said extension board.

5,590,368

METHOD AND APPARATUS FOR DYNAMICALLY EXPANDING THE PIPELINE OF A MICROPROCESSOR

Jay Heeb, Gilbert, Ariz.; Sunil Shenoy, and Jimmy Wong, both of Portland, Oreg., assignors to Intel Corporation, Santa Clara, Calif.


Continuation of Ser. No. 40,675, Mar. 31, 1993, abandoned.

This application Jul. 27, 1995, Ser. No. 508,318

Int. Cl. G06F 9/38

U.S. Cl. 395-800

9 Claims



3. A microprocessor, comprising:

a core unit for issuing instructions and processing data, said core unit being coupled to a local bus;

a bus controller logic for loading instructions and data from an external store to said microprocessor to be processed by said core unit, said bus controller logic being coupled to the local bus and to a system bus, the system bus for transferring data between said microprocessor and the external store;

a data cache unit for storing copies of data loaded by said bus controller logic and retrieving the copies of data for use by said core unit, said data cache unit being coupled to the local bus;

a pipeline, coupled to the local bus, for causing a first pipe to at least issue a first instruction on the local bus during a cycle and a second pipe to at least execute a second instruction during the cycle, said pipeline repeatedly executing the cycle, the first instruction issued by the first pipe in the cycle being available for execution by the second pipe in a next cycle, the first pipe causing said core unit to issue the first instruction, the second pipe selectively causing said bus controller logic or said data cache unit to execute the second instruction;

said data cache unit determining if a copy of a first external data is stored in said data cache unit when the first instruction issued by the core unit during the cycle is a load instruction to load the first external data from external to said microprocessor, the determining beginning during the cycle but not finishing before the cycle ends, the cycle being immediately followed by a second cycle, the second cycle being immediately followed by a third cycle;


said bus controller logic indicating to said data cache unit whether the first external data is cacheable, said bus controller logic being coupled to said data cache unit, said data cache unit determining if a copy of the first external data is stored only if the first external data is cacheable;

said bus controller logic delaying execution of the second instruction in the second cycle until the third cycle when the first external data is cacheable;

a scoreboarding unit for scoreboarding the first pipe when the copy of the first external data is not stored in said data cache unit and the first instruction issued by the first pipe in the second cycle is an instruction that requires execution by said bus controller logic, said scoreboarding maintaining the state of the first pipe for one additional cycle such that the first instruction issued by the first pipe in the second cycle is reissued by the first pipe in the third cycle, said scoreboarding unit being coupled to the local bus;

an instruction latch coupled to the local bus, said instruction latch latching a copy of the first instruction issued by the first pipe during the cycle; and

a mux having a first input coupled to the local bus, a second input coupled to the instruction latch, a select input coupled to said data cache unit, and a mux output coupled to said bus controller logic, said mux selecting either the first input or the second input to be driven at the mux output, said mux selecting the first input when the copy of the first external data is stored in said data cache unit, said mux selecting the second input when the copy of the first external data is not stored in said data cache unit.



high speed synchronous component and one of a synchronous component and an asynchronous component and wherein all data transfers from each of said plurality of components are sent to said master component;

a bus including connection means connecting said master component and said plurality of components for transferring data between said master component and said plurality of components, said connection means including a predetermined plurality of data transmission lines such that substantially every data transfer on said bus uses said plurality of data transmission lines and said connection means has a number of control lines that provide the following:

- (a) a request signal supplied by said master component to said first high speed synchronous component in which said request signal has a logic state that changes to indicate that said master component has data for transfer;
- (b) an available signal supplied by said first high speed synchronous component that has a logic state that changes after said logic state of said request signal changes to indicate that said first high speed synchronous component is available to commence transfer of data; and
- (c) a ready signal supplied by said master component that changes its logic state after the logic state of said available signal is changed and before all data is transferred;

wherein said changes of said logic states of said request, available and ready signals occur in connection with a first high speed synchronous data transfer operation;

a plurality of protocol performing means, each protocol performing means used in a data transfer on said bus using a predetermined protocol, said plurality of protocol performing means including: a high speed synchronous protocol performing means related to a high speed synchronous protocol in which a varying amount of data can be transferred between said master component and said first high speed synchronous component during an predetermined period of time and at least one of: a synchronous protocol performing means related to a synchronous protocol in which data is transferred involving said master components for a predetermined time interval and an asynchronous protocol performing means related to an asynchronous protocol in which data is transferred until an acknowledged signal is received by said master component;

wherein said master component controls operations of said bus, with said master component selecting which one of said plurality of components is to be involved with a data transfer including said master component selecting said first high speed synchronous component to receive data from said master component, and wherein said first high speed synchronous data transfer operation involves a data transfer from said master component to said first high speed synchronous component in which a first amount of data is transferred for a first

5,590,369

BUS SUPPORTING A PLURALITY OF DATA TRANSFER SIZES AND PROTOCOLS

Dana J. Burgess, Estes Park, and Robert E. Stubbs, Longmont, both of Colo., assignors to Fujitsu Limited, Kawasaki, Japan

Continuation of Ser. No. 275,119, Jul. 14, 1994, abandoned.

This application Aug. 3, 1995, Ser. No. 511,048

Int. Cl. G06F 13/00

U.S. Cl. 395-800

17 Claims

11. An apparatus for transferring data between components communicating with a bus, comprising:

- a single master component;
- a plurality of components communicating with said master component, said plurality of components including at least a first

unpredetermined period of time and said master component is also involved with a second high speed synchronous data transfer operation from said master component to said first high speed synchronous component in which a second amount of data is transferred for a second predetermined period of time, with said second predetermined period of time and said second amount of data being different from said first predetermined period of time and said first amount of data, respectively, with all of said data being transferred in connection with said first high speed synchronous data transfer operation after said first changing of the logic state by said ready signal and before any subsequent changing of the logic state of said ready signal, and wherein all of said request signal, said available signal and said ready signal change their logic states and in the same predetermined time sequence for said second high speed synchronous data transfer operation as was done for said first high speed synchronous data transfer operation.

5,590,370

INTELLIGENT MEMORY SYSTEM FOR PROCESSING VARIABLE LENGTH I/O INSTRUCTIONS

Abhaya Asthana; Mark R. Cravatts, both of Berkeley Heights, and Paul Krzyzanowski, Fanwood, all of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.


Continuation of Ser. No. 231,528, Apr. 22, 1994, abandoned.

This application Nov. 16, 1995, Ser. No. 558,208

Int. Cl.⁶ G06F 12/00

U.S. Cl. 395—800

8 Claims



7. A computer system comprising:

- a host processor;
- memory comprised of two or more active storage elements which are arranged in an array, each active storage element comprising a memory element and a processing element associated with the memory element, said memory element being capable of receiving and storing variable length instructions which are used to implement one or more functions, said host processor compiling and downloading said variable length instructions to said memory at run time;
- at least one peripheral;
- a first port for connecting said processing element to said host processor;
- a second port for connecting said processing element to at least one of the peripherals, said processing element receiving data from said peripheral via a bus that is independent of the connection of the host processor to the first port; and
- means for transmitting a packet to said processing element for invoking said variable length instructions, said invoked variable length instructions being capable of performing low level operations.

5,590,371

SERIAL COMMUNICATION CIRCUIT ON AN LSI CHIP AND COMMUNICATING WITH ANOTHER MICROCOMPUTER ON THE CHIP

Tetsu Tashiro, Itami, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 19, 1994, Ser. No. 305,937

Claims priority, application Japan, Oct. 29, 1993, 5-271954

Int. Cl.⁶ G06F 13/00

U.S. Cl. 395—821

4 Claims



1. A serial communication circuit for a communication protocol, which represents a predetermined meaning according to a signal of one unit composed of a plurality of sections obtained by combining high level sections and low level sections respectively having different time widths with each other and represents data of a first value or a second value by a signal of one unit having a data section in which high level or low level can be set optionally, comprising:

- a control circuit;
 - a transmit terminal;
 - a receiving terminal;
 - a transmit data register which is given data of a plurality of bits to be transmitted from said transmit terminal and holds it therein;
 - a transmit pointer which designates successively bits of data held in said transmit data register;
 - a first register which makes said transmit pointer designate bit of said transmit data register, as well as generates a transmit trigger signal which makes data of bits designated by said transmit pointer outputted from said data register when a first value is written from said control circuit;
 - a second register to which a first value or a second value can be written from said control circuit, corresponding to a signal level to be transmitted from said transmit terminal;
 - a third register to which a first value or a second value to be transmitted from said transmit terminal can be written from said control circuit after selecting a content of said second register or said transmit data register;
 - a receiving data register which holds data of a plurality of bits to be received from said receiving terminal so as to make said control circuit to read it;
 - a receiving pointer which designates successively bits of data to be held in said receiving data register;
 - a fourth register which makes said receiving pointer designate bit of said receiving data register, as well as generates a receiving trigger signal which makes bit of said receiving data register designated by said receiving pointer take in a value of a signal inputted from said receiving terminal when the first value is written from said control circuit; and
 - a fifth register which makes said control circuit read a signal received from said receiving terminal directly;
- wherein said control circuit at the time of transmitting according to a predetermined program, writes a first or a second value to said second register every time a time determined in said program is passed, writes the first value to said first register at a time corresponding to said data section so as to give said transmit trigger signal to said transmit pointer and said transmit data register as well as writes the first value or the second value to said third register, thereby transmits each signal of one unit from said transmit terminal, and at the time of receiving according to a predetermined program, reads out

from said fifth register a signal received from said receiving terminal so as to recognize a meaning of each signal of one unit, writes the first value to said fourth register at a time corresponding to said data section and gives said receiving trigger signal to said receiving pointer and to said receiving data register, thereby data is taken to said receiving data register.

5,590,372

VME BUS TRANSFERRING SYSTEM BROADCASTING MODIFIERS TO MULTIPLE DEVICES AND THE MULTIPLE DEVICES SIMULTANEOUSLY RECEIVING DATA SYNCHRONOUSLY TO THE MODIFIERS WITHOUT ACKNOWLEDGING THE MODIFIERS


James N. Dieffenderfer, Endicott, N.Y., and Bruce J. Morehead, Santa Clara, Calif., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jul. 14, 1992, Ser. No. 913,270

Int. Cl.⁶ G06F 12/02

U.S. Cl. 395—823

16 Claims



1. A system for digital communications comprising:

- a VME bus including at least a first bus portion and a second bus portion;
- a first device attached to at least the first bus portion and the second bus portion and comprising means for requesting control of the bus, means for sending clock pulses via said bus; means for sending via the second bus portion an identifier for a broadcast, means for sequentially sending data words via the first bus portion synchronously with said clock pulses without receiving an acknowledgment from any recipient from a time of said first device requesting said control until completion of said broadcast; and
- second and third devices attached to said bus, each of said second and third devices comprising means for receiving the broadcast identifier via the second bus portion, and receiving means, responsive to the broadcast identifier, for receiving said data words via the first bus portion synchronously with said clock pulses without replying with an acknowledgment from a time of said first device requesting said control until completion of said broadcast, said second and third devices simultaneously receiving said data words.

5,590,373

FIELD PROGRAMMING APPARATUS AND METHOD FOR UPDATING PROGRAMS IN A PERSONAL COMMUNICATIONS DEVICE


Wayne P. Whitley; Randall S. Springfield, both of Boca Raton; Harold D. Hudson, Lake Worth; Byron K. Tiller, Boca Raton; David J. Allard, Boynton Beach; Daniel Ming-Te Hsieh, Coral Springs; Julie F. Goodwin, Boca Raton; Thomas T. Murakami, Deerfield Beach, and Francis J. Canova, Jr., Boynton Beach, all of Fla., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jul. 25, 1994, Ser. No. 279,638

Int. Cl.⁶ G06F 13/00


U.S. Cl. 395—828

14 Claims



1. A field programming subsystem for a portable communications device that includes an electrically programmable data storage, comprising:

- a decoding means coupled to a programming voltage source and the programmable data storage, for selectively applying a programming voltage to the programmable data storage;
-



sintering said first and said second compressed materials to form a sintered body made of third oxide crystal; pulverizing said sintered body made of said third oxide crystal to form a third oxide powder; mixing said third oxide powder and titanium powder and compressing the mixed powder to form a third compressed material; and sintering said third compressed material in a vacuum condition to form an oxide target.

5,590,386

METHOD OF MAKING AN ALLOY OF TUNGSTEN AND LANTHANA

Thomas J. Patrician, Monroeton, and Harry D. Martin, III, Troy, both of Pa., assignors to Osram Sylvania Inc., Danvers, Mass.

Filed Jul. 26, 1995, Ser. No. 507,183
Int. Cl.⁶ C22C 1/10

U.S. Cl. 419—20

8 Claims

1. A method of making an alloy of tungsten and lanthana comprising the steps of:
heating lanthanum oxide in a water saturated atmosphere until at least 95% of the lanthanum oxide is converted to lanthanum hydroxide;
forming a mixture of a tungsten metal powder and the lanthanum hydroxide powder, pressing the mixture to form a pressed ingot, and sintering the ingot at a temperature sufficient to form the alloy of tungsten and lanthana.

5,590,387

METHOD FOR PRODUCING METAL AND CERAMIC SINTERED BODIES AND COATINGS

Helmut Schmidt, Saarbrücken; Rüdiger Nass, Riegelsberg; Mesut Aslan, Pirmasens; Sener Alhayrak; Ertugrul Arpac, both of Saarbrücken; Theo König, Laufenburg-Rotzel, and Dietmar Fister, Murg, all of Germany, assignors to H. C. Starck, GmbH & Co. KG, Goslar, Germany

Filed Oct. 11, 1994, Ser. No. 321,416

Claims priority, application Germany, Oct. 27, 1993, 43 36 694.5

Int. Cl.⁶ B22F 7/02

U.S. Cl. 419—36

35 Claims

1. Method for producing metal and ceramic sintered bodies or coatings comprising:
(a) nanoscale ceramic or metal powder particles wherein less than 1% of the individual particles have a deviation of more than 40%, and essentially no individual particles have a deviation of more than 60%, from the average grain size, and
(b) at least one low molecular-weight organic compound having at least one functional group that reacts and/or interacts with groups present on the surface of the powder particles, the materials (a) and (b) being dispersed in water and/or a polar organic solvent as dispersion medium;

the method comprising the further steps of removing the dispersion medium, forming the surface-modified ceramic or metal powder, before or after the removal of the dispersion medium, to a green body or coating and sintering such green body or coating.

5,590,388

MOLDED CERAMIC ARTICLES AND PRODUCTION METHOD THEREOF


Mitsuo Kuwabara; Kiyoshi Ikegami; Teruaki Yoshida; Koji Takahashi; Tamotsu Harada; Takeshi Komiyama; Fumio Hirai, and Masamichi Hayashi, all of Sayama, Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan
Division of Ser. No. 76,500, Jun. 9, 1993, Pat. No. 5,374,391, which is a division of Ser. No. 965,085, Oct. 22, 1992, Pat. No. 5,443,615, which is a continuation of Ser. No. 652,884, Feb. 8, 1991, abandoned. This application Sep. 1, 1994, Ser. No. 299,306

Claims priority, application Japan, Feb. 13, 1990, 2-33023; Feb. 22, 1990, 2-41976; Mar. 22, 1990, 2-72854; Mar. 26, 1990, 2-76131

Int. Cl.⁶ B22F 3/12

U.S. Cl. 419—39

10 Claims



1. A method of producing a molded article, which comprises:
providing a powder mix as raw materials comprising electrolytic copper powder as a main component, and chromium powder within a composition range of from at least 0.4 wt. % to at most 3.0 wt. % based on the whole weight of the powder mix and a carbonaceous material in which the carbon residue falls within a composition range of at most 0.1 wt. %, or chromium powder in a proportion of from at least 4 mg to at most 30 mg per gram of the powder mix and a carbonaceous material in which the carbon residue is in a proportion of at most 1 mg per gram of the powder mix to diffuse the chromium powder into the electrolytic copper powder;

the first step wet-mixing the powder mix with a liquid additive thereby obtaining a mixed raw material;

the second step press-molding the mixed raw material obtained in the first step in a hydrostatically applied condition of pressure, thereby removing an excess of the liquid additive to obtain a preform; and

the third step subjecting the preform obtained in the second step to a heat treatment within a temperature range of at most 700° C. under an inert gas atmosphere and then sintering the preform in a temperature range of from at least 950° C. to at most 1065° C. under an inert gas atmosphere whose pressure is lower than 10 kg/cm², thereby depositing a reinforcement on a part of the surface of the chromium powder.

5,590,389


SPUTTERING TARGET WITH ULTRA-FINE, ORIENTED GRAINS AND METHOD OF MAKING SAME

John A. Dunlop, Veradale, Wash.; Jun Yuan, Santa Clara, Calif.; Janine K. Kardokus, Otis Orchards, Wash., and Roger A. Emigh, Post Falls, Id., assignors to Johnson Matthey Electronics, Inc., Spokane, Wash.

Filed Dec. 23, 1994, Ser. No. 363,397
Int. Cl.⁶ B22F 3/20

U.S. Cl. 419—67

18 Claims



1. A method of making a sputtering target comprising:
extruding a metal workpiece comprising a metal from the group consisting of aluminum, copper, and titanium, alone or alloyed with a dissimilar metal selected from the group consisting of copper, silicon, zirconium, titanium, tungsten, platinum, gold, niobium, rhenium, scandium, cobalt, molybdenum, hafnium, and alloys thereof, through a die having contiguous, transverse inlet and outlet channels of substantially identical cross section, whereby the workpiece enters the inlet channel and exits the outlet channel, to produce an extrusion in which the grains of the major constituent measure less than about 20 microns for an aluminum body, less than 30 microns for a copper body, and less than 10 microns for a titanium body; and
fabricating the extrusion into a sputtering target.

5,590,390

FLUID TREATMENT SYSTEM AND PROCESS

Jan M. Maarschalkwerd, Mount Brydges, Canada, assignor to Trojan Technologies Inc., London, Canada

PCT No. PCT/CA94/00125, § 371 Date Oct. 17, 1994, § 102(e) Date Oct. 17, 1994, PCT Pub. No. WO94/20208, PCT Pub. Date Sep. 15, 1994


Continuation-in-part of Ser. No. 26,572, Mar. 5, 1993, Pat. No. 5,418,370. This PCT application Mar. 4, 1994, Ser. No. 318,858

Int. Cl.⁶ B01J 19/12

U.S. Cl. 422—186.3

46 Claims

1. A gravity fed fluid treatment system comprising a fluid inlet, a



fluid outlet, an irradiation zone disposed between the fluid inlet and fluid outlet, and at least one radiation source assembly comprising at least one radiation source and a support therefor, the at least one radiation source being elongate and having a longitudinal axis substantially parallel to the direction of fluid flow through the

irradiation zone and being fully submersed in fluid flow through the irradiation zone, the support being disposed upstream or downstream of the irradiation zone, the irradiation zone having a closed cross-section to confine fluid to be treated within a predefined maximum distance from the at least one radiation source, said closed cross-section being less than a cross-section of said fluid inlet.

5,590,391


DOWN-BLENDING OF FISSIONABLE MATERIAL

Norman E. Brandon, Erwin; David R. Hopson, Jonesborough, both of Tenn.; Ronald J. Green, Hamilton, Ohio; James H. G. Grimaud, III; Timothy J. Heagle, both of Johnson City, Tenn., and Kerry D. Schutt, Gray, Tenn., assignors to Nuclear Fuel Services, Inc., Erwin, Tenn.

Filed Jan. 20, 1995, Ser. No. 375,631
Int. Cl.⁶ C01G 43/00

U.S. Cl. 423—253

6 Claims



1. A process for reducing the concentration of fissionable uranium containing components of a feed material to a target concentration level, comprising providing said feed material in first vessel means as an aqueous system of high-enriched uranyl nitrate hydrate (HE-UNH) wherein at least about 18% of the uranium therein is the ²³⁵U isotope, providing in second vessel means an aqueous dilution medium containing natural uranyl nitrate hydrate (NUNH) wherein at least about 90% of the uranium therein is the ²³⁸U isotope, forcing a diluent stream of said dilution medium from said second vessel means through jet pump means to provide a suction region within said jet pump means coextensive with said diluent stream, providing a feed fluid connection of said HE-UNH within said first vessel means with said suction region through first conduit means to cause a HE-UNH stream to flow into said suction region and intermix therein with said diluent stream to form a product stream of markedly reduced ²³⁵U concentration, and providing a product fluid connection of said product stream with said second vessel means, said forcing, when carried out in an uninterrupted, recycle manner, can continually withdraw said HE-UNH from said first vessel means, mix it with NUNH in said pump means, and exit said product stream from said jet pump means and into said second vessel means until all of said HE-UNH has been diluted.

5,590,392

CORROSION-RESISTANT MATERIAL FOR CONTACT WITH HIGH TEMPERATURE MOLTEN METAL AND METHOD FOR PRODUCTION THEREOF

Yutaka Ishiwata, Zushi, and Yoshiyasu Itoh, Yokohama, both of Japan, assignors to Kabushiki Kaisha Toshiba, Kanagawa-ken, Japan


Filed Feb. 22, 1995, Ser. No. 393,309

Claims priority, application Japan, Feb. 24, 1994, 6-026769
Int. Cl.⁶ B22F 1/00

U.S. Cl. 428—546

9 Claims

1. A corrosion resistant material comprising:



a refractory metal matrix having grains separated by grain boundaries; and
molten metal wetting prevention means for preventing the infiltration of a molten, preselected metal into the grain boundaries by presenting a non-wetting surface to the molten metal; the molten metal wetting prevention means being oxides of metal elements selected from the group consisting of the preselected metal and metals having lower free energies for the formation of the oxide than the preselected metal.

5,590,393

NEUTRON-ABSORBING MATERIAL AND ITS PRODUCTION PROCESS


Guy M. Decroix, Chevilly-Larue; Dominique Gosset, Bourg-la-Reine, and Bernard Kryger, Paris, all of France, assignors to Commissariat à l'Energie Atomique, Paris, France

PCT No. PCT/FR94/00614, § 371 Date Feb. 7, 1995, § 102(e) Date Feb. 7, 1995, PCT Pub. No. WO94/28556, PCT Pub. Date Dec. 8, 1994

PCT Filed May 25, 1994, Ser. No. 373,262

Claims priority, application France, May 26, 1993, 93 06304 Int. Cl. B22F 3/12

U.S. Cl. 428—552



1. A composite, neutron-absorbing material comprising a homogeneous, boron carbide matrix, in which are homogeneously dispersed calibrated clusters of at least one boron chosen from among HFB₂, TiB₂ and ZrB₂, wherein the calibrated clusters have dimensions of 100 to 500 μm.

5,590,394 DATA TRANSMISSION SYSTEM FOR CATV SYSTEMS WITH CAPABILITY TO INTERRUPT THE REPEATED TRANSMISSION OF CHARACTER INFORMATION BLOCKS TO SEND PRIORITY UPDATES


Masaaki Ishimoto, and Takehito Toyota, both of Kanagawa-ken, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 70,015, Jun. 1, 1993, abandoned, which is a continuation of Ser. No. 610,401, Nov. 7, 1990, abandoned. This application Apr. 3, 1995, Ser. No. 417,432 Claims priority, application Japan, Nov. 15, 1989, 1-296673 Int. Cl. H04N 7/10; 7/087

U.S. Cl. 455—6.1

19 Claims

1. A data transmission system for a cable access television



(CATV) system, said data transmission system comprising:
a buffer, having an input to receive character information blocks and an output that provides a plurality of character information blocks in a predetermined order, that stores the plurality of character information blocks in the predetermined order;
a transmitter, coupled to the buffer, that transmits character information blocks over CATV transmission lines; and
a control means for controlling the buffer and the transmitter so that the transmitter transmits the character information blocks, stored in the buffer, in the predetermined order, and upon detection of an updated transmission block, for interrupting the transmission of the character information blocks in the predetermined order to send the updated character information block with priority.

5,590,395

SATELLITE CELLULAR NETWORK RESOURCE MANAGEMENT METHOD AND APPARATUS


Dennis P. Diekelman, Tempe, Ariz., assignor to Motorola, Inc., Schaumburg, Ill.

Filed Nov. 10, 1993, Ser. No. 150,702

Int. Cl. H04B 7/185

U.S. Cl. 455—13.1

73 Claims



1. A method for operating a satellite cellular communication system having multiple satellites, at least some of which are moving with respect to a surface of a celestial body, each of the satellites containing communication resources including transmitters and receivers communicating with multiple ground terminals and at least one controlling station, comprising:

- forecasting by a first computer, communication traffic expected to pass between the ground terminals and the satellites and operating capabilities of the satellites, during a future predetermined period;
- determining from the communication traffic and the operating capabilities, an individual operational plan for each of the satellites for managing resources on the satellites to accommodate the forecasted communication traffic during the future predetermined period;
- transmitting to and storing within each of the satellites the individual operational plan for each of the satellites; and
- energizing the transmitters and the receivers of each of the satellites according to the individual operational plan stored within each of the satellites in response to actual communication traffic demands during the future predetermined period.

5,590,396

METHOD AND APPARATUS FOR A DEEP-SLEEP MODE IN A DIGITAL CELLULAR COMMUNICATION SYSTEM

Raymond C. Henry, Durham, N.C., assignor to Ericsson Inc., Research Triangle Park, N.C.

Filed Apr. 20, 1994, Ser. No. 231,000

Int. Cl. H04Q 7/22

U.S. Cl. 455—33.1

7 Claims

1. In a cellular radio communication system including a base station with a base station control signal, said control signal having a plurality of paging classes numbered 1 through N, said paging classes corresponding to lengths of time between paging time slots during which paging information is broadcast, and at least one mobile station conditioned to receive paging information broadcast by the base station during said paging time slots corresponding to a particular paging class assigned to the mobile station by the base station, said mobile station further having a regular sleep mode wherein a first set of selected circuits are deactivated and a deep sleep mode wherein a second set of selected circuits are deactivated, a method for saving battery power in the mobile station, comprising the steps of:

- placing the mobile station into a page only mode;
- transmitting a first signal from the mobile station to the base station indicating that the mobile station is unable to receive messages;
- entering said deep-sleep mode by deactivating said first set and said second set of selected circuits within the mobile station for a predetermined period of time;
- automatically entering said regular sleep mode by reactivating said second set of selected circuits within the mobile station after said predetermined time period;
- reactivating said first set of selected circuits and receiving by the mobile station the base station control signal and transmitting from the mobile station a second signal indicating that the mobile station is able to receive said messages;
- transmitting from the base station said messages on a set of said plurality of time slots of the base station control signal;
- monitoring by the mobile station said messages on said set of said plurality of time slots of the base station control signal; and
- repeating steps (b) through (g) until said mobile station is reset from said page only mode.

5,590,397

SELECTING AND PRIORITIZING RADIO TELEPHONE SYSTEMS AT RADIO TERMINAL

Susumu Kojima, Tokyo, Japan, assignor to NEC Corporation, Tokyo, Japan

Filed Dec. 6, 1994, Ser. No. 354,107

Claims priority, application Japan, Dec. 17, 1993, 5-317585 Int. Cl. H04Q 7/00

U.S. Cl. 455—33.1

3 Claims

SYSTEM NUMBER	SYSTEM IDENTIFICATION CODE	SELECTION INFORMATION	PRIORITY	SYSTEM NAME
1	102345	1	1	HOME
2	106789	1	2	HEAD OFFICE
3	106789	0	4	BRANCH OFFICE
4	500010	1	3	THREE
5	500020	0	5	OSAKA

1. A radio telephone system, comprising:

a radio terminal, and
a plurality of radio systems, each of which transmits a respective system identification code, particular radio systems of said plurality of radio systems providing service for said radio terminal, each said respective system identification code of said particular radio systems being stored in said radio terminal and defining a set of registered system identification codes, each of said registered system identification codes having stored in said radio terminal a corresponding user selectable selection priority and a corresponding user selectable selection information, said selection information indicating radio system enablement or non-enablement; wherein when said radio terminal receives different ones of said registered system identification codes, said radio terminal selects a selected radio system of said particular radio systems which has said respective system identification code corresponding to one of said registered system identification codes which has a highest said selection priority, and which has said selection information indicating enablement.

5,590,398

VIRTUAL MOBILE LOCATION AREA

Adrian S. Matthews, Middlesex, N.J., assignor to Lucent Technologies Inc., Murray Hill, N.J.


Continuation of Ser. No. 191,565, Feb. 3, 1994, abandoned.

This application Mar. 27, 1995, Ser. No. 410,420

Int. Cl. H04Q 7/22

U.S. Cl. 455—33.1

5 Claims



1. In a cellular telephone network comprising a plurality of local areas, each local area comprising a plurality of base stations and having associated therewith a home location register to indicate which mobile stations in the network are registered in that particular local area, a method for locating mobile stations comprising:

determining the call habits of a mobile station;

determining the base stations that the habits of the mobile station indicate the mobile station will most likely use to initiate and receive calls;

arranging the cells that contain the base stations that the habits of the mobile station indicate the mobile station will most likely use to initiate and receive calls into a group, called a Virtual Mobile Location Area (VMLA), and assigning said VMLA to said mobile station, wherein said VMLA is only modified when the call habits of said mobile station indicate that said mobile station has entered a new cell, having a new base station contained therein, more than once; and

registering the mobile station with each home location register in the local area associated with every base station that the habits of the mobile station indicate will most likely be used by the mobile station.


5,590,399
UP-LINK CHANNEL ASSIGNMENT SCHEME FOR CELLULAR MOBILE COMMUNICATIONS SYSTEMS EMPLOYING MULTI-BEAM ANTENNAS WITH BEAM SELECTION

Tadashi Matsumoto, Walnut Creek, and Seiji Nishioka, San Ramon, both of Calif., assignors to Nextel Communications, Lafayette, Calif., and NTT Mobile Communications Network Inc., Tokyo, Japan

Filed Feb. 23, 1995, Ser. No. 393,210
 Int. Cl.⁶ H04Q 7/30

U.S. Cl. 455—33.3

10 Claims



1. A channel assignment method for a cellular mobile communications system having a multibeam antenna system with beam selection, the method comprising the steps of:

- estimating with said antenna a signal-to-interference power ratio ("SIR") for each channel in said cellular communications system by measuring Euclidean distance between a desired signal and a received signal and by averaging said measured distance over several samples;
- using said averaged Euclidean distance as a signal quality measure; and
- assigning by said antenna a communications channel to each antenna beam of said multibeam system at a cell within said cellular system independently of other cells within said cellular system based upon an SIR derived value by initiating a hand-off process if said quality measure expressed by the averaged Euclidean distance becomes worse than a selected threshold level, selecting a hand-off destination channel from among all available channels in frequency band, and measuring a received composite signal power of the other channels at a base station receiver to determine said hand-off destination.


5,590,400
METHOD OF SEARCHING FOR A SIGNALLING CHANNEL IN A RADIO SYSTEM

Jussi Löppönen, Helsinki, Finland, assignor to Nokia Telecommunications OY, Espoo, Finland
 PCT No. PCT/FI94/00118, § 371 Date Nov. 30, 1994, § 102(e)
 Date Nov. 30, 1994, PCT Pub. No. WO94/23544, PCT Pub. Date Oct. 13, 1994

PCT Filed Mar. 29, 1994, Ser. No. 347,311
 Claims priority, application Finland, Mar. 30, 1993, 931434
 Int. Cl.⁶ H04Q 7/00

U.S. Cl. 455—34.2

2 Claims



2. A method of searching for a signalling channel in a radio system comprising a mobile exchange, base stations connected therewith, subscriber stations that are connected with the base stations and communicate with the radio system via the channels of the base station via traffic channels and non-dedicated control channels; the method comprising the following steps:

- a first subscriber station registered in a first base station listens to a signalling channel of the base station;
- the first subscriber station sends a call set-up request that contains signalling data to the radio system, and the radio system stores the signalling data transmitted by the first subscriber station;
- the radio system allocates said signalling channel to a second subscriber station for use as a traffic channel since the other channels of the first base station are busy;
- the first subscriber station receives a message indicating that the signalling channel used by the first subscriber station is assigned as a traffic channel for communication between the second subscriber station and the first base station;
- the first subscriber station stays to listen for a predetermined time to the inband signalling on said signalling channel that has been converted to a traffic channel;
- if said signalling channel is released within a predetermined time, the radio system establishes a telecommunication link in accordance with said signalling data, continuing the connection establishment between the first subscriber station and the radio system from where it ended when the signalling channel was allocated to another subscriber station as a traffic channel.

5,590,401
SELECTIVE-CALLING RECEIVER WITH BATTERY SWITCHING UPON CPU STOP DETECTION

Motoki Ide, Tokyo, and Hiroaki Shibayama, Shizuoka, both of Japan, assignors to NEC Corporation, Japan

Filed Apr. 18, 1994, Ser. No. 228,962
 Claims priority, application Japan, Apr. 16, 1993, 5-113925
 Int. Cl.⁶ H04Q 7/18

U.S. Cl. 455—38.3

15 Claims

1. A selective-calling radio receiver comprising:
- an exchangeable first battery as a first power supply source;
- a second battery as a second power supply source, said second battery being capable of being charged by said first battery;

5,590,403
METHOD AND SYSTEM FOR EFFICIENTLY PROVIDING TWO WAY COMMUNICATION BETWEEN A CENTRAL NETWORK AND MOBILE UNIT


Dennis W. Cameron, Jackson, Miss.; Walter C. Roehr, Jr., Reston, Va.; Rade Petrovic, Oxford; Jai P. Bhagat, Jackson, both of Miss.; Masood Garahi, Madison; William D. Hays, Jackson, both of Miss., and David W. Ackerman, Washington, D.C., assignors to Destineer Corporation, Jackson, Miss.

Filed Nov. 12, 1992, Ser. No. 973,918


Int. Cl.⁶ H04B 7/06

U.S. Cl. 455—51.2

12 Claims



- a CPU which stops operating when a supply voltage of said first battery lowers to a stop voltage, said CPU being unable to operate normally when said supply voltage is equal to or lower than said stop voltage;
 - a stop detector for detecting operational stop of said CPU due to drop of said supply voltage of said first battery, a minimum operable voltage of said stop detector being lower than said stop voltage; and
 - a power supply switcher for switching a power supply source for said CPU and said stop detector between said first battery and said second battery;
- wherein said first battery is used as said power supply source until said supply voltage of said first battery lowers to said stop voltage;
- and wherein said power supply source is switched from said first battery to said second battery when said operational stop of said CPU is detected by said stop detector.



1. A method for information transmission by a plurality of transmitters to provide broad communication capability over a region of space, the information transmission occurring during at least both a first time period and a second time period and the plurality of transmitters being divided into at least a first and second set of transmitters, the method comprising the steps of:

- (a) generating a system information signal which includes a plurality of blocks of information;
- (b) transmitting the system information signal to the plurality of transmitters;
- (c) transmitting by the first and second sets of transmitters a first block of information in simulcast during the first time period;
- (d) transmitting by the first set of transmitters a second block of information during the second time period; and
- (e) transmitting by the second set of transmitters a third block of information during the second time period.

5,590,402
MULTI-MODE TRANSMITTER FOR TRANSMITTER FOR SIGNALS HAVING VARYING DEVIATION LEVELS

Randall J. Samson, Ft. Worth; Allan Budlong, and Dan Hustig, both of Bedford, all of Tex., assignors to Motorola, Inc., Schaumburg, Ill.


Continuation of Ser. No. 896,707, Jun. 10, 1992, abandoned.

This application Apr. 13, 1995, Ser. No. 421,148

Int. Cl.⁶ H04B 7/005; 7/26

U.S. Cl. 455—44

5 Claims



1. A dual-mode transmitter for automatically adjusting a frequency deviation level of a signal to be transmitted, the transmitter comprising:

- means for providing a signal indicating when the transmitter changes from a first mode to a second mode, wherein said first mode is a wideband mode and said second mode is a narrowband mode;
- means for attenuating the frequency deviation level of the signal to be transmitted based on a change from said wideband mode to said narrowband mode; and
- means, coupled to said means for attenuating, for amplifying the frequency deviation level based on a change from said wideband mode to said narrowband mode.

5,590,404
BASE STATION TRANSMISSION-RECEPTION APPARATUS FOR CELLULAR SYSTEM

Toshifumi Sato, and Yukitsuna Furuya, both of Tokyo, Japan, assignors to NEC Corporation, Tokyo, Japan

Filed Nov. 8, 1994, Ser. No. 337,471


Claims priority, application Japan, Nov. 8, 1993, 5-278208

Int. Cl.⁶ H04B 7/04

U.S. Cl. 455—53.1

4 Claims

1. A base station transmission-reception apparatus for a cellular system, comprising:
 - M sector antennae provided in a number equal to the number of sectors;
 - M collective modulation-demodulation sections connected to said M sector antennae; and
 - N baseband signal processing sections provided in a number equal to the number of communication channels and connected to said M collective modulation-demodulation sections;
- each of said baseband signal processing sections including:
- a control section for controlling a selection signal for controlling a transmission condition;



a transmission signal processing section for producing a transmission signal in the form of a digital signal in accordance with a modulation method from transmission data;
a transmission signal selection circuit for outputting the transmission signal from said transmission signal processing section to only one of said sector antennae which is indicated by the selection signal;
a reception signal selection circuit for selecting and outputting one of M reception signals received by said sector antennae which is indicated by the selection signal; and
a reception signal processing section for detecting reception data corresponding to its own communication channel from the reception signal from said reception signal selection circuit;

each of said collective modulation-demodulation sections including:

transmission processing means for converting transmission signals from the transmission signal selection circuits into a transmission radio signal in the form of an analog signal and supplying the resulting signal to said sector antennae;
frequency conversion means for converting reception radio signals of a bandwidth corresponding to the N communication channels received by said sector antennae collectively into a baseband signal by frequency conversion; and
an analog-to-digital converter for converting the base band signal (analog) from said frequency conversion means into a digital signal and supplying the digital signal to the reception signal processing section.

5,590,405

COMMUNICATION TECHNIQUE EMPLOYING VARIABLE INFORMATION TRANSMISSION

John J. Daly, Neshanic Station; Herman F. Haisch, Holmdel; Peter Kapsales, Middletown; Bala Krishnamurthy, Morganville; Richard A. Miska, Belle Mead; Joseph K. Nordgaard, Fair Haven, and Carl E. Walker, Red Bank, all of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.


Filed Oct. 29, 1993, Ser. No. 146,372

Int. Cl.⁶ H04Q 7/20

U.S. Cl. 455-54.1

12 Claims

1. A method for transmitting information within a communication system comprising an application node, a base transceiver node and a field transceiver node; said method comprising the steps of:



tion system comprising an application node, a base transceiver node and a field transceiver node; said method comprising the steps of:

transmitting information between said field transceiver node and said base transceiver node at a variable data rate via a first fixed bandwidth information channel, wherein said variable data rate is a function of the transmission quality afforded by said first fixed bandwidth information channel, and wherein, prior to the transmission of said information between said field transceiver node and said base transceiver node, the effective rate of said variable data rate information is elevated via bitstuffing or reduced via buffering to match the transmission rate supported by said first fixed bandwidth information channel;

transmitting, from said base transceiver node to said application node, a signal indicative of the present variable data rate at which information is being transmitted between said field transceiver node and said base transceiver node via said first fixed bandwidth information channel; and

varying the data rate at which information is transmitted between said application node and said base transceiver node via a second fixed bandwidth information channel as a function of said received signal indicative of said variable data rate of transmission between said field transceiver node and said base transceiver node, wherein, prior to the transmission of said information between said application node and said base transceiver node, the effective rate of said variable data rate information is elevated via bitstuffing or reduced via buffering to match the transmission rate supported by said second fixed bandwidth information channel.

5,590,406

METHOD OF INVOKING AND CANCELING VOICE OR DATA SERVICE FROM A MOBILE UNIT


Gwain Bayley; Matthew S. Grob, both of San Diego; Gadi Karmi, Del Mar; Robert H. Kimball, and David S. Propach, both of San Diego, all of Calif., assignors to Qualcomm Incorporated, San Diego, Calif.

Continuation of Ser. No. 152,162, Nov. 15, 1993, Pat. No. 5,487,175. This application Apr. 21, 1995, Ser. No. 426,763

Int. Cl.⁶ H04B 1/00

U.S. Cl. 455-54.2

11 Claims



1. A method of invoking and canceling voice service and data service in a communication system comprising a mobile unit supporting simultaneous voice and data communication having a keypad for receiving and providing user data and a speaker, microphone, and vocoder unit for receiving and providing encoded voice signals, and a terminal equipment unit input for receiving and providing digital data, said communication system further comprising a base station having a vocoder portion for receiving and providing said encoded voice signals and said user data and a modem portion for receiving and providing said digital data and said user data wherein a wireless link couples said encoded voice signal, said user data, and said digital data between said mobile unit and said base station, comprising the steps of:

receiving at said mobile unit from said terminal equipment unit a first modem command within said digital data wherein said first modem command designates a directory number and a request to establish a first voice communication between said mobile unit and said base station; and

receiving said first modem command at said modem portion of said base station and establishing said first voice communication in response to said first modem command such that said encoded voice signals are passed from said speaker, microphone, and vocoder unit over said wireless link to said vocoder portion of said base station and from said vocoder portion of said base station over said wireless link to said speaker, microphone, and vocoder unit.

5,590,407

DRIVE THROUGH WIRELESS ORDER TAKING SYSTEM

Hideaki Ishikawa, Yokohama, and Atsunao Shinoda, Fujisawa, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Sep. 25, 1995, Ser. No. 533,194

Claims priority, application Japan, Oct. 11, 1994, 6-245573; Oct. 11, 1994, 6-245574

Int. Cl.⁶ H04B 7/00

U.S. Cl. 455-66

5 Claims



1. A drive through wireless order taking system comprising: a base station; and

a slave station being connectable with the base station by radio and being manually movable into and out of a talk lock state at the discretion of an order taker;

wherein the base station comprises means for transmitting a talk lock release signal to the slave station, and the slave station comprises means for automatically moving the slave station out of the talk lock state in response to the talk lock release signal transmitted from the base station.

5,590,408

REVERSE LINK, TRANSMIT POWER CORRECTION AND LIMITATION IN A RADIOTELEPHONE SYSTEM


Ana L. Weiland, Encinitas; Richard K. Kornfeld, and John E. Maloney, both of San Diego, all of Calif., assignors to QUALCOMM Incorporated, San Diego, Calif.

Division of Ser. No. 203,151, Feb. 28, 1994, Pat. No. 5,452,473. This application Mar. 20, 1995, Ser. No. 407,543

Int. Cl.⁶ H04B 1/04

U.S. Cl. 455-69

7 Claims



1. A method for limiting transmit power of a radio operating in a radio communications system, the radio communications system comprising at least one base station that transmits signals including power control commands to the radio, the radio comprising a variable gain amplifier and a maximum gain setting, the method comprising the steps of:

determining an open loop power control value in response to a signal received from the at least one base station;

determining a gain adjust signal in response to the transmitted power control commands;

combining the open loop power control value and the gain adjust signal to produce a summation signal;

comparing the summation signal to the maximum gain setting; if the summation signal is greater than or equal to the maximum gain setting, adjusting the variable gain amplifier in response to the maximum gain setting; and

if the summation signal is less than the maximum gain setting, adjusting the variable gain amplifier in response to the summation signal.

5,590,409

TRANSMISSION POWER CONTROL METHOD AND A TRANSMISSION POWER CONTROL APPARATUS

Mamoru Sawahashi, Yokosuka, and Fumiaki Adachi, Yokohama, both of Japan, assignors to NTT Mobile Communications Network Inc., Tokyo, Japan


Filed May 11, 1995, Ser. No. 439,463

Claims priority, application Japan, May 12, 1994, 6-098815; Apr. 3, 1995, 7-077936

Int. Cl.⁶ H04B 1/00

U.S. Cl. 455-69

4 Claims



1. A transmission power control method for a CDMA (Code Division Multiple Access) system which controls transmission power of a mobile station on the basis of a transmission power control bit sent from a base station to the mobile station, said method comprising the steps of:

measuring, at the mobile station, average received power per transmission power control period of a signal sent from the base station;

detecting, at the mobile station, a power difference between the average received power of a current transmission power control period and that of one of previous transmission power control periods;

deciding, at the mobile station, whether said power difference exceeds a predetermined reference power difference;

setting, at the mobile station, transmission power of the mobile station in accordance with said power difference when said power difference exceeds said predetermined reference power difference, and in accordance with the transmission power control bit when said power difference is lower than the predetermined reference power difference.

5,590,410


SYSTEM AND METHOD FOR FREQUENCY BASED
ACQUISITION ACKNOWLEDGMENT BETWEEN
TRANSMITTER AND RECEIVERBrian M. Deutsch, Maple Valley, and Robert B. Foster, Jr.,
Bellevue, both of Wash., assignors to American Wireless
Corporation, Bellevue, Wash.

Filed Oct. 26, 1994, Ser. No. 329,435

Int. Cl. H04Q 7/20

U.S. Cl. 455—76

2 Claims



1. A communications system comprising:
at least two communications units, each communications unit further comprising a transmitter and a receiver, said transmitter capable of transmitting on a plurality of different frequencies and said receiver capable of receiving on a plurality of different frequencies, and wherein frequency locking is required to insure that each communication unit is operating on a same frequency during a given time frame;
means for predetermining a plurality of n frequencies to be used as set-up channels;
means for establishing a plurality of time frames for transmission and reception of signals on said set-up channels between said units;
means for dividing each said time frame into a transmit period and a receive period;
means for first transmitting, during said transmit period of a first time frame, by an originating unit of said units, a signal on a first one of said plurality of n frequencies;
means for second transmitting, during a transmit period of a next time frame, by said originating unit of said units, a signal on a next one of said plurality of n frequencies;
means for repeating said second transmitting step for each additional frequency in said predetermined plurality of n frequencies;
means for third transmitting, during a transmit period of an $n+1$ time frame, by said originating unit, a signal on said first one of said plurality of n frequencies, such that in $n+1$ time frames, a signal has been transmitted on each of said n frequencies and also on said first frequency a second time in said $n+1$ time frame to complete a cycle of acquisition attempts by said originating unit;
means for first receiving on one of said plurality of n frequencies by a receiver in a second unit in said communications system for $n+1$ time frames;
means for second receiving on a next one of said plurality of n frequencies by said receiver and said second unit for $n+1$ time frames;
means for repeating the enabling of said second receiving means for each additional frequency in said n frequencies;
means for repeating the enabling of said first receiving means for $n+1$ time frames;

means for enabling a transmitter in said second unit as a result of the enabling of said first or second receiving means in said second unit receiving a signal on one of said n frequencies;
means for maintaining said frequency of said receiver in said second unit on one of said n frequencies;
means for fourth transmitting by a transmitter in said second unit, in a transmit period for said second unit of a time frame during which said one of said n frequencies is next received by said receiver in said second unit, a signal on said one of said n frequencies; and
means for repeating the enabling of said last mentioned maintaining means and said fourth transmitting means for an additional time frame to acknowledge acquisition of frequency lock.

5,590,411


METHOD AND APPARATUS FOR SUPPRESSING
SPURIOUS THIRD-ORDER RESPONSES IN
TRANSCIEVERSPeter Sroka, West End, and Peter D. Harrison, Ascot, both of
England, assignors to Nokia Mobile Phones Ltd., Finland

Filed Jan. 10, 1995, Ser. No. 371,027

Int. Cl. H04B 1/10

U.S. Cl. 455—78

13 Claims



1. Apparatus for inhibiting spurious responses in a receiver section of a transceiver, said receiver section having a non-linear device, said apparatus comprising:
detection means for detecting transmission of a RF signal from the transceiver and outputting a control signal indicative of said transmission; and
linearity control means connected to said detection means and to the non-linear device so as to vary the linearity of said non-linear device in accordance with said control signal.

5,590,412

COMMUNICATION APPARATUS USING COMMON
AMPLIFIER FOR TRANSMISSION AND RECEPTIONTetsuro Sawai, Ashiya; Hisanori Uda, Hirakata; Toshikazu
Hirai, Hirakata; Toshikazu Imaoka, Hirakata; Yasuo
Harada, Hirakata; Keiichi Honda, Hirakata, and Masao
Nishida, Sakai, all of Japan, assignors to Sanyo Electric Co.,
Ltd., Moriguchi, Japan

Filed Nov. 18, 1994, Ser. No. 342,220


Claims priority, application Japan, Nov. 19, 1993, 5-290992

Int. Cl. H04B 1/44; H03F 3/193; 3/62

U.S. Cl. 455—82

19 Claims

1. A communication apparatus, comprising:
a transmit-receive common amplifier for amplifying a transmitted signal or a received signal;
a transmit-receive common mixer for frequency-mixing the transmitted signal or the received signal with a local oscillator output signal;
a first switch, connected to an input side of said transmit-receive common amplifier, to said mixer and to an input side of a



- receiving system circuit, for switching path connection between a transmission path and a reception path;
a second switch, connected to an output side of said transmit-receive common amplifier, to said mixer and to an output side of a transmitting system circuit, for switching path connection between the transmission path and the reception path;
a buffer amplifier disposed on a local oscillation input side of said mixer; and
said transmit-receive common amplifier, said mixer and said buffer amplifier each respectively including an FET as an active element, and a common gate bias being applied to said respective FETs.

5,590,413


RADIO TRANSCIEVER HAVING SHARED
MODULATION AND DEMODULATION MIXER
CIRCUITSVictor K. Kondratiev; Valery P. Kouplitchenko, both of Mos-
cow; Alexander V. Galitsky, Moscow-Zelenograd, all of Rus-
sian Federation, and Geoffrey G. Baehr, Palo Alto, Calif.,
assignors to Sun Microsystems, Inc., Mountain View, Calif.

Filed Jan. 14, 1994, Ser. No. 181,329

Int. Cl. H04B 1/44

U.S. Cl. 455—86

18 Claims



1. A radio having an antenna, comprising:
a reception element configured to receive a reception carrier signal at the antenna;
a transmission element configured to transmit from the antenna a transmission carrier signal with a transmission baseband signal modulated thereon; and
a mixer stage, coupled between the reception element and the transmission element, the mixer stage including a first mixer circuit configured to modulate the transmission baseband signal onto the transmission carrier signal and a second mixer circuit to modulate the reception carrier signal during transmission of the radio, the first mixer circuit further configured to perform a first down-conversion of the reception

carrier signal and to perform a second down-conversion on the reception carrier signal received during reception of the radio.

5,590,414

ADAPTER UNIT FOR A PORTABLE RADIO TELEPHONE
ENABLING EITHER ONE OF DATA TRANSMISSION
AND HAND-FREE OPERATIONKuniyoshi Marui, Saitama-ken, and Goichi Sato, Tokyo, both
of Japan, assignors to Kabushiki Kaisha Toshiba, Japan


Filed Jan. 9, 1992, Ser. No. 818,567

Claims priority, application Japan, Jan. 11, 1991, 3-002291

Int. Cl. H04B 1/40

U.S. Cl. 455—89

6 Claims



1. A radio telephone apparatus comprising:
a portable unit comprising:

- (a) a radio telephone comprising an operation mode control responsive to a user-supplied for generating an operation mode control signal, and a transmitter for converting information signals to radio frequency signals and for transmitting the radio frequency signals over a radio communication link;
(b) a first contact-type connector coupled to said radio telephone for receiving information signals external of said portable unit, supplying the information signals to said transmitter, and for outputting the operational mode control signal; and
(c) a power supply control which supplies a POWER-ON signal to said first contact-type connector, said first contact-type connector supplying the POWER-ON signal to a second contact-type connector when said first contact-type connector is attached to said second contact-type connector;

an adapter unit comprising:

- (a) said second contact-type connector detachably coupled to said first contact-type connector for outputting information signals to said portable unit and for receiving the operational mode control signal;
(b) a microphone terminal for receiving information signals from a microphone;
(c) a data terminal for receiving information signals from a data transmission device; and
(d) switching means coupled to said second contact-type connector for supplying, in response to the operational mode control signal, the information signals to said second contact-type connector from one of said microphone terminal and said data terminal, whereby the information signals are output from said second contact-type connector to said first contact-type connector, supplied from said first contact-type connector to said transmitter, and are converted to radio frequency signals, which are transmitted by said transmitter over said radio communication link; and

- (e) a power supply control which receives the POWER-ON signal from said second contact-type connector and powers a power supply switch ON in response thereto.

5,590,415

METHOD AND DEVICE FOR SUPERVISING THE CONDITION OF AN ANTENNA


Jukka Peltola, and Pekka Koponen, both of Oulu, Finland, assignors to Nokia Telecommunications OY, Espoo, Finland
PCT No. PCT/FI94/00138, § 371 Date Dec. 14, 1994, § 102(e)
Date Dec. 14, 1994, PCT Pub. No. WO94/24576, PCT Pub. Date Oct. 27, 1994

PCT Filed Apr. 13, 1994, Ser. No. 356,214

Claims priority, application Finland, Apr. 14, 1993, 931672
Int. Cl.⁶ H04B 17/00

U.S. Cl. 455—115

3 Claims



1. A transmitter antenna diagnostic method, comprising the steps of:

- providing a first fixed alarm limit;
- transmitting a signal from a transmitter device to an antenna line to an antenna, whereby a portion is reflected from the antenna through the antenna line;
- measuring the magnitude of said signal;
- measuring the magnitude of said reflected portion of said signal;
- providing a measuring signal related to the measured magnitudes of said reflected signal and said transmitted signal, a level of said measuring signal representing a condition of the antenna;
- determining said level of said measuring signal by:
 - providing a second alarm limit having an adjustable level;
 - setting said adjustable level of said second alarm limit at a preset level;
 - adjusting said level of the second alarm limit from said present level until said adjustable level reaches said level of said measuring signal;
 - indicating the level of said second alarm limit reaching said level of said measuring signal;
 - determining said level of said measuring signal to be equal to said indicated level of said second alarm limit; and
 - determining a condition of said antenna on the basis of said determined level of said measuring signal; and
- switching-off said transmitter device when said level of said measuring signal exceeds said first fixed alarm limit.

5,590,416

CANTED ANTENNA FOR A CELLULAR RADIOTELEPHONE

Nils R. Rydbeck, Cary, N.C., assignor to Ericsson Inc., Research Triangle Park, N.C.


Filed Jun. 8, 1995, Ser. No. 401,024

Int. Cl.⁶ H04B 1/38; H01Q 1/12

U.S. Cl. 455—90

26 Claims

1. A cellular radiotelephone comprising:
a radiotelephone body having a front face, said front face defining a first imaginary plane extending therefrom;
an antenna extending from said radiotelephone body and defining an axis, said antenna having a first end surface adjacent



- said radiotelephone body, said first end surface defining a second imaginary plane intersecting said axis at a non-orthogonal angle;
a boss on said radiotelephone body for receiving said first end surface of said antenna, said boss having an angled surface defining a third imaginary plane extending therefrom said third imaginary plane being parallel to said second imaginary plane, and intersecting said first imaginary plane at a non-orthogonal angle; and
a pin rotatably connecting said first end surface to said angled surface, and forming an orthogonal angle with said first end surface and said angled surface.

5,590,417

RADIOTELEPHONE APPARATUS INCLUDING A WIRELESS HEADSET

Nils Rydbeck, Cary, N.C., assignor to Ericsson Inc., Research Triangle Park, N.C.


Continuation of Ser. No. 70,813, Jun. 3, 1993, abandoned.

This application Feb. 28, 1995, Ser. No. 396,327

Int. Cl.⁶ H04B 1/40

U.S. Cl. 455—89

13 Claims



1. A radiotelephone apparatus comprising:
a body, including first means for communicating with a radio-telephone network; and
a headset, selectively attachable to the body and including second means for communicating with the body, wherein the second means includes:
means for receiving a modulated carrier signal from a third communications means; and
means for recovering an audio signal from the modulated carrier signal; and the headset further includes:
means for amplifying the audio signal recovered by the recovering means; and
means for converting the audio signal to a sound signal;
wherein the body includes the third means for communicating with the headset in one of two modes and, when the headset is attached to the body, the headset and the body are able to exchange information by wired electrical communication

- and, when the headset is detached from the body, the headset and the body exchange information by wireless communication; and
the body further includes means for adjusting a gain of the amplifying means.

5,590,418

METHOD AND APPARATUS FOR STABILIZING THE GAIN OF A CONTROL LOOP IN A COMMUNICATION DEVICE


Kevin J. Holoubek, Buffalo Grove; Richard J. Keniuk, Cary, and Paul R. Bontrager, Woodstock, all of Ill., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Sep. 30, 1993, Ser. No. 129,276

Int. Cl.⁶ H04B 1/04

U.S. Cl. 455—126

7 Claims



1. A method of stabilizing a control loop in a power amplifier, the control loop including a forward gain path and a reverse gain path, the power amplifier being compatible with a time division multiple access (TDMA) communication system and transmitting information via bursts, the method comprising the steps of:

- monitoring a control signal input to the forward gain path and a signal produced in the reverse gain path during a first time period of a burst when a power output of the power amplifier is at a steady-state amplitude;
- determining the gain of the control loop based on a ratio of the control signal and the signal produced in the reverse gain path, the signal produced in the reverse gain path based on a level of a signal detected at an output of the forward gain path;
- producing a correction signal based on the determined gain of the control loop during a second time period when the power output of the power amplifier is at a steady-state amplitude; and
- adjusting the gain of the control loop during a time period between signal bursts utilizing the correction signal to maintain the desired loop bandwidth.

5,590,419

VARIABLE POWER CIRCUIT AND APPARATUS USING THE POWER CIRCUIT

Norio Shimo, Kanagawa, Japan, assignor to Sony Corporation, Tokyo, Japan


Filed Feb. 23, 1994, Ser. No. 200,665

Claims priority, application Japan, Feb. 26, 1993, 5-039032

Int. Cl.⁶ H04B 1/04

U.S. Cl. 455—127

9 Claims



1. A radiocommunication apparatus on a time division multiplex communication system comprising:

- a power amplifier circuit for amplifying a transmitted signal intermittently transmitted at predetermined periods to a radio transmission power level;
- a signal processing circuit operating at a voltage lower than the operating voltage of said power amplifier circuit;
- a battery having a full-charged voltage lower than the operating voltage of said power amplifier circuit and an ultimate voltage higher than the operating voltage of said signal processing circuit, with a large voltage difference between the full-charged voltage and the ultimate voltage;
- a stepping up circuit with a small output current capacity for stepping up the output voltage of said battery, changing within the range between the full-charged voltage and the ultimate voltage, at least to the operating voltage of said power amplifier circuit;
- a storing circuit for storing power of which the voltage is stepped up by said stepping up circuit; and
- switch means provided between said storing circuit and said power amplifier circuit for supplying power stored in said storing circuit to said power amplifier circuit only while said power amplifier circuit is amplifying said transmitted signal.

VOL
11 93

ISS
5

DE
31

1996

UMI

DESIGNS

DECEMBER 31, 1996

376,893


TORTILLA SHELL

Timothy J. Gornet, 625 Newport Ave., Webster Groves, Mo. 63119

Filed Feb. 8, 1995, Ser. No. 34,610

Term of patent 14 years

U.S. Cl. D1—122



376,895

SANDAL

Gordon Cook, 780 Laird Blvd., Montreal, Que. H3B 1Y6, Canada

Continuation-in-part of Ser. No. 19,097, Feb. 23, 1994, abandoned. This application Feb. 3, 1995, Ser. No. 34,393

Claims priority, application Canada, Nov. 8, 1993, 08-11-93-1

Term of patent 14 years

U.S. Cl. D2—916



376,894

SKATE BOOT

Todd J. Olson, Chanhassen, Minn., assignor to Rollerblade, Inc., Minneapolis, Minn.

Filed Jun. 7, 1995, Ser. No. 39,917

Term of patent 14 years

U.S. Cl. D2—904



376,896


REPEAT PATTERN OF A SHOE SOLE

Nicholas O'Rourke, N. Quincy, Mass., assignor to Reebok International Ltd., Stoughton, Mass.

Filed Dec. 22, 1995, Ser. No. 48,244

Term of patent 14 years

U.S. Cl. D2—953



376,897


BLADDER FOR A SHOE SOLE

Joel L. Passke, Portland, and James C. Sell, Jr., Beaverton, both of Oreg., assignors to Nike, Inc., Beaverton, Oreg.

Filed Jun. 6, 1996, Ser. No. 55,478

Term of patent 14 years

U.S. Cl. D2—961



376,899


BLADDER FOR A SHOE SOLE

Joel L. Passke, Portland, and James C. Sell, Jr., Beaverton, both of Oreg., assignors to Nike, Inc., Beaverton, Oreg.

Filed Jun. 6, 1996, Ser. No. 55,481

Term of patent 14 years

U.S. Cl. D2—961



376,900

OUTSOLE CUSHION

Roland Seydel; Juan A. Diaz, both of Lake Oswego, Oreg.; Bruno Kächele, Weilheim/Teck, Germany, and Ian Burgess, Beaverton, Oreg., assignors to Adidas AG, Germany

Filed Jul. 3, 1995, Ser. No. 41,035

Term of patent 14 years

U.S. Cl. D2—968



376,898


BLADDER FOR A SHOE SOLE

Joel L. Passke, Portland, and James C. Sell, Jr., Beaverton, both of Oreg., assignors to Nike, Inc., Beaverton, Oreg.

Filed Jun. 6, 1996, Ser. No. 55,480

Term of patent 14 years

U.S. Cl. D2—961



376,901


PORTION OF A SHOE UPPER

Eric P. Avar, Aloha, and Aaron A. C. Cooper, Portland, both of Oreg., assignors to Nike, Inc., Beaverton, Oreg.

Filed Feb. 20, 1996, Ser. No. 50,465

Term of patent 14 years

U.S. Cl. D2—972



376,903

PORTABLE SHADE

Johnel Harris, 215 Timber Oaks Dr., N. Aurora, Ill. 60542

Filed Apr. 17, 1995, Ser. No. 37,534

Term of patent 14 years

U.S. Cl. D3—5



376,904

COMBINED HOLDER, KEY PICTURE DISPLAY AND CONTAINER

Anthony DiRocco, 48 Mississippi Ave., West Orange, N.J. 07052

Filed Oct. 23, 1995, Ser. No. 46,686

Term of patent 14 years

U.S. Cl. D3—208



376,902


ELEMENT OF A SHOE MIDSOLE

Eric P. Avar, Aloha, Oreg., assignor to Nike, Inc., Beaverton, Oreg.

Filed Nov. 20, 1995, Ser. No. 46,544

Term of patent 14 years

U.S. Cl. D2—977



376,905


FISHING GEAR CARRYING POUCH

Jason R. Volmer, 12150 Race St. #G204, Northglenn, Colo. 80241

Filed Sep. 13, 1995, Ser. No. 43,887

Term of patent 14 years

U.S. Cl. D3—221



376,907


CASE FOR A PORTABLE SHOWER

Jeffrey M. Simpson, Wichita, Kans., assignor to The Coleman Company, Inc., Wichita, Kans.

Filed Mar. 17, 1995, Ser. No. 36,120

Term of patent 14 years

U.S. Cl. D3—274



376,906

GOLF BAG

Masahiro Mori, and Masahiko Nagahama, both of Tokyo, Japan, assignors to The Yokohama Rubber Co., Ltd., Tokyo, Japan

Filed Sep. 5, 1995, Ser. No. 48,839

Claims priority, application Japan, Mar. 8, 1995, 7-6097

Term of patent 14 years

U.S. Cl. D3—255



376,908


TOOL BOX

Hung-Chi Hsu, No. 30-12, Chue Tzu Tou, Hsi Kang Village, Tainan Hsien, Taiwan

Filed Dec. 7, 1995, Ser. No. 47,578

Term of patent 14 years

U.S. Cl. D3—274



376,909


TOOL BOX

Thomas Dickinson, and Bradley D. Gale, both of St. Louis, Mo., assignors to Contico International, Inc., St. Louis, Mo.

Filed Dec. 27, 1995, Ser. No. 48,808

Term of patent 14 years

U.S. Cl. D3—281



376,911


PAINT ROLLER FRAME

Ilan Zigelboim, and Virginia B. Hagan, both of 4955 NW. 82nd Ter., Lauderhill, Fla. 33351

Continuation-in-part of Ser. No. 37,008, Apr. 3, 1995, Pat. No. Des. 369,027. This application Feb. 1, 1996, Ser. No. 49,835

Term of patent 14 years

U.S. Cl. D4—122



376,912

BATHING BRUSH

Arnold J. Stein, 14225 N. Alyssum, Tucson, Ariz. 85737

Filed Jul. 31, 1995, Ser. No. 42,092

Term of patent 14 years

U.S. Cl. D4—127



376,910


COMBINED COSMETIC BRUSH AND PERFUME ATOMIZER

Stephan A. Tuchman, 530 Eagle Ave., West Hempstead, N.Y. 11552

Filed Jul. 21, 1994, Ser. No. 26,165

Term of patent 14 years

U.S. Cl. D4—114



376,913


TWO-DIMENSIONAL PICTURE FRAME

Mary Borden, 48 W. Center St., Akron, Ohio 44308

Filed Jan. 5, 1995, Ser. No. 33,085

Term of patent 14 years

U.S. Cl. D6—300



376,915

CORNER UNIT FOR A PICTURE FRAME


John H. van Quach, 1911 SW. Brandon St., Seattle, Wash.

98106

Filed Apr. 5, 1996, Ser. No. 52,552

Term of patent 14 years

U.S. Cl. D6—300



376,914


MIRRORED PICTURE FRAME

John C. Waszkiewicz, III, 11 White Pine Rd., New Hartford, N.Y. 13413

Filed Dec. 14, 1995, Ser. No. 47,917

Term of patent 14 years

U.S. Cl. D6—300



376,916


GARMENT HANGER

Philip R. McDowell, Lake Forest; Robert W. McDowell, Gridley, and Matthew F. McDowell, Santa Monica, all of Calif., assignors to McDowell Bros, Laguna Hills, Calif.

Filed Jul. 14, 1995, Ser. No. 41,451

Term of patent 14 years

U.S. Cl. D6—317



376,917


BOOSTER SEAT

James M. Kain, Tipp City, Ohio, assignor to Cosco, Inc., Columbus, Ind.

Filed Sep. 26, 1995, Ser. No. 44,524

Term of patent 14 years

U.S. Cl. D6—333



376,919


CAR SEAT BASE

Mark A. Sedlack, Cuyahoga Falls, Ohio, assignor to Century Products Company, Macedonia, Ohio

Filed Nov. 13, 1995, Ser. No. 46,351

Term of patent 14 years

U.S. Cl. D6—333



376,918


BATH RING

Keith L. Poulson, Westminster; Robert M. Parker, Aurora, both of Colo.; Jon R. Rossman, Chelmsford, and Bryan R. Hotelling, Arlington, both of Mass., assignors to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 7, 1995, Ser. No. 46,091

Term of patent 14 years

U.S. Cl. D6—333



376,920


BOOSTER SEAT

Gary M. Wood, Charlotte, N.C., assignor to Smart Products, Inc., Charlotte, N.C.

Filed Jan. 16, 1996, Ser. No. 48,938


Term of patent 14 years

U.S. Cl. D6—333




376,921
CHAIR


David P. Chandler, Jamestown, N.C., assignor to Henredon Furniture Industries, Inc., Morganton, N.C.
Filed Jan. 22, 1996, Ser. No. 49,291
Term of patent 14 years
U.S. Cl. D6—334

376,923
POTTY STEP


Thomas J. Jones, 3007 Crone Rd., Borden, Ind. 47106
Division of Ser. No. 25,179, Jul. 5, 1994, Pat. No. Des. 365,693. This application Dec. 26, 1995, Ser. No. 49,025
Term of patent 14 years
U.S. Cl. D6—349

376,924
CHAIR


Jocelyn Beaulieu, Newmarket, Canada, assignor to Global Upholstery Company, Downsview, Canada
Filed Jun. 27, 1995, Ser. No. 40,786
Claims priority, application Canada, Apr. 18, 1995, 1995-0825
Term of patent 14 years
U.S. Cl. D6—347




Marilyn M. Hieber, 7445 Steadman, Dearborn, Mich. 48126
Filed Sep. 18, 1995, Ser. No. 44,124
Term of patent 14 years
U.S. Cl. D6—347

376,925
SEAT


Michael J. Paus, High Point, N.C., assignor to Universal Furniture Industries, Inc., High Point, N.C.
Filed Feb. 23, 1995, Ser. No. 35,278
Term of patent 14 years
U.S. Cl. D6—381

376,927
COMBINED MINIATURE GUN COLLECTION AND
DISPLAY CASE


Ernest R. Pinder, and Ronna J. Pinder, both of Clifton, Colo.
Filed Jan. 18, 1996, Ser. No. 49,115
Term of patent 14 years
U.S. Cl. D6—397

376,926
SOFA

David P. Chandler, Jamestown, N.C., assignor to Henredon Furniture Industries, Inc., Morganton, N.C.
Filed Jan. 22, 1996, Ser. No. 49,292
Term of patent 14 years
U.S. Cl. D6—381

376,928
LAP TRAY

Moises B. Lorenzana, 601 Lake Hinsdale Dr., Willowbrook, Ill. 60514, and Vance A. Lorenzana, 73 Chippewa Dr., Oswego, Ill. 60543
Filed Apr. 22, 1995, Ser. No. 53,446
Term of patent 14 years
U.S. Cl. D6—406



376,929


GARMENT DISPLAY RACK WITH MOVABLE FRAMES

Eugenio Tranquilli, Ponzano Veneto, Italy, assignor to Benetton Group S.p.A., Ponzano-Veneto, Italy

Filed Aug. 1, 1994, Ser. No. 26,581

Claims priority, application Italy, Feb. 4, 1994, MI9400060
Term of patent 14 years

U.S. Cl. D6—411



376,931

DESK

Michael A. Fewchuk, Eastwood, Australia, assignor to Sebel Furniture Limited, New South Wales, Australia

Filed Jul. 18, 1995, Ser. No. 41,628

Claims priority, application Australia, Jan. 20, 1995, 165/95
Term of patent 14 years

U.S. Cl. D6—425



376,930


DESKTOP PODIUM

Stan Kotkosky, 16422 Gentry La., Huntington Beach, Calif. 92647

Continuation-in-part of Ser. No. 23,076, May 17, 1994, abandoned. This application Oct. 2, 1995, Ser. No. 44,878

Term of patent 14 years

U.S. Cl. D6—419



376,932


COMPUTER DESK

Chao-Chuan Hsu; Sun-Yu Wang, and Yee-Chang Liao, all of P.O. Box 453, Taichung, Taiwan

Filed Sep. 21, 1995, Ser. No. 44,402

Term of patent 14 years

U.S. Cl. D6—425



376,933


PORTABLE KITCHEN CABINET

Russell E. Barnhill, 219 Duerr Dr., Bellville, Tex. 77418

Continuation-in-part of Ser. No. 57,494, May 6, 1993, abandoned. This application May 18, 1995, Ser. No. 39,007

Term of patent 14 years

U.S. Cl. D6—445



376,935


OCCASIONAL TABLE

Aagje M. T. Nourse, Fort Worth, Tex., assignor to BBA Holdings, Inc., Wilmington, Del.

Filed Mar. 11, 1996, Ser. No. 51,442

Term of patent 14 years

U.S. Cl. D6—486



376,936

TABLE


Gabriel Batki-Braun, Purley, and Bernard Heppenstall, Middle Woodford, both of England, assignors to Faversham Furniture Limited, Faversham, United Kingdom

Filed Feb. 22, 1995, Ser. No. 35,241

Claims priority, application United Kingdom, Aug. 26, 1994, 2041307

Term of patent 14 years

U.S. Cl. D6—488



376,934

OVAL TABLE


Gabriel Batki-Braun, Purley, and Bernard Heppenstall, Middle Woodford, both of England, assignors to Faversham Furniture Limited, Faversham, United Kingdom

Filed Feb. 22, 1995, Ser. No. 35,238

Claims priority, application United Kingdom, Aug. 26, 1994, 2041306

Term of patent 14 years

U.S. Cl. D6—480

VOL
11 93ISS
5DE
31

1996

UMI

376,937


END FRAME FOR A BENCH

Gerald P. Skalka, Potomac, Md., assignor to Victor Stanley, Michael T. Credle, Sr., 1205 Wilson Rd., Smithfield, Va. 23430 Inc., Dunkirk, Md.

Filed Dec. 8, 1995, Ser. No. 47,597

Term of patent 14 years

U.S. Cl. D6—492



376,939


CLAMSHELL TABLE TOP

Michael T. Credle, Sr., 1205 Wilson Rd., Smithfield, Va. 23430

Filed Dec. 7, 1994, Ser. No. 31,861

Term of patent 14 years

U.S. Cl. D6—511



376,938

CHAIR FRAME ARMREST

John Caldwell, San Marino, Calif., assignor to Crown Leisure Products, Inc., Owosso, Mich.

Filed Apr. 28, 1994, Ser. No. 21,986

Term of patent 14 years

U.S. Cl. D6—501



376,940


STANDING FRAME FOR GIFT WRAPPING PAPER

Haskell R. Logan, 1108 Martin Rd., Starr, S.C. 29684

Filed Oct. 6, 1995, Ser. No. 45,044

Term of patent 14 years

U.S. Cl. D6—520



376,941


SHOWER CADDY

Raul Munoz, Chicago, Ill.; Patrick R. Welsh, Wilmington, Del., and Robert W. Matthes, Mechanicsville, Pa., assignors to Selfix, Inc., Chicago, Ill.

Filed Aug. 11, 1995, Ser. No. 42,524

Term of patent 14 years

U.S. Cl. D6—525



376,943


EXTENDER FOR ATTACHMENT TO A HOSPITAL OPERATING ROOM MAYO STAND

Sharon Czynon, 95631 Lorraine Dr., Hinsdale, Ill. 60521

Filed Oct. 26, 1995, Ser. No. 46,711

Term of patent 14 years

U.S. Cl. D6—567



376,942


SHOWER CADDY

Raul Munoz, Chicago, Ill., assignor to Selfix, Inc., Chicago, Ill.

Filed Dec. 26, 1995, Ser. No. 48,344

Term of patent 14 years

U.S. Cl. D6—525



376,944


GARAGE MAT WITH ADJUSTABLE TIRE INDICATOR

Michael T. Dunn, 19841 Martinsville Rd., Belleville, Mich. 48111

Filed Feb. 6, 1996, Ser. No. 50,014

Term of patent 14 years

U.S. Cl. D6—582



376,945


FOLDABLE MATTRESS

Vincenzo A. Bonaddio, Boothwyn, Pa., and Jose De Jesus Munoz Contreras, Apple Valley, Calif., assignors to Foamex L.P., Linwood, Pa.

Filed Jan. 23, 1995, Ser. No. 33,864

Term of patent 14 years

U.S. Cl. D6—596



376,947

INFANT PLAY PILLOW

Tiffany A. Hill, 4666 Pontchartrain Blvd., New Orleans, La. 70118

Filed Sep. 5, 1995, Ser. No. 43,467

Term of patent 14 years

U.S. Cl. D6—599



376,946


PORTABLE SEAT TOTE

Michael Maxim, 147 Knipp, Houston, Tex. 77024

Filed Mar. 5, 1996, Ser. No. 51,190

Term of patent 14 years

U.S. Cl. D6—596



376,948

COMBINED LAP PILLOW AND BOOK SUPPORT
Patrick H. Sullins, and Don M. Jennings, both of Arlington, Tex., assignors to Creative Manufacturing, Inc., Arlington, Tex.

Filed May 11, 1995, Ser. No. 38,660

Term of patent 14 years

U.S. Cl. D6—601



376,949


WINE DISPENSER

Ronald F. Barriault, Lewiston, and Ronald Boucher, Lisbon, both of Me., assignors to Central Distributors, Inc., Lewiston, Me.

Filed Sep. 5, 1995, Ser. No. 43,505

Term of patent 14 years

U.S. Cl. D7—306



376,951

BLENDER

Anthony B. Rorke, Guilford, Conn., assignor to Black & Decker Inc., Newark, Del.

Filed Jan. 11, 1996, Ser. No. 48,681

Term of patent 14 years

U.S. Cl. D7—386



376,950

ELECTRIC COFFEEMAKER


Philippe Saltet, Chateaufort, France, assignor to Moulinex S.A., Paris, France

Filed Jan. 5, 1996, Ser. No. 48,616

Claims priority, application France, Jul. 7, 1995, 95 3745

Term of patent 14 years

U.S. Cl. D7—309



376,952

FOOD STORAGE CONTAINER LID

Kevin Rausch, Cross Junction, Va., assignor to Rubbermaid Commercial Products Inc., Winchester, Va.

Filed Apr. 17, 1995, Ser. No. 37,561

Term of patent 14 years

U.S. Cl. D7—392.1




376,953
DISH

John W. Dunn, Durham, Conn., assignor to Design Specialties, Inc., Wallingford, Conn.

Filed Sep. 1, 1995, Ser. No. 43,724

Term of patent 14 years

U.S. Cl. D7—349


376,955
COMBINED BOTTLES AND STAND

Gagik Petrosyan, 615 S. Adams #1, and Arshak Akopyan, 513 Griswold St. Apt. #9, both of Glendale, Calif. 91205

Filed Feb. 21, 1995, Ser. No. 35,155

Term of patent 14 years

U.S. Cl. D7—598


376,954
BOWL

Richard H. Burns, Troy, Ohio, and Allen J. Hutton, Greenfield, Ind., assignors to Seco Products Corporation, Washington, Mo.

Filed Feb. 26, 1996, Ser. No. 50,950

Term of patent 14 years

U.S. Cl. D7—560


376,956
INSULATED JACKET FOR BEVERAGE CONTAINER

Darren Sharp, 3331 N. Blythe, Fresno, Calif. 93722

Filed Jan. 22, 1996, Ser. No. 50,561

Term of patent 14 years

U.S. Cl. D7—607




376,957

INSULATED JACKET FOR BEVERAGE CONTAINER
Darren Sharp, 3331 N. Blythe, Fresno, Calif. 93722

Filed Jan. 22, 1996, Ser. No. 50,562

Term of patent 14 years

U.S. Cl. D7—607




376,959

CARRIER FOR SUPPORTING A BEVERAGE
CONTAINER IN AN AUTOMOTIVE CUP HOLDER
Daniel A. Norris, 608 Old Towne La., Alabaster, Ala. 35077

Filed Nov. 2, 1995, Ser. No. 47,052

Term of patent 14 years

U.S. Cl. D7—619



376,960


SALAD BOWL

Ian Ferris, Finchampstead, England, assignor to Dart Industries Inc., Orlando, Fla.

Filed Sep. 28, 1995, Ser. No. 43,923

Term of patent 14 years

U.S. Cl. D7—629

376,958
CANISTER


Jean P. Blanc, Gattieres, France, assignor to Compagnie Mediterraneenne de Cafes, Carros, France

Filed Jan. 21, 1993, Ser. No. 3,889

Claims priority, application France, Jul. 20, 1992, 92 4539


Term of patent 14 years

U.S. Cl. D7—612



376,961
KNIFE


Signe Persson-Melin, Malmö, Sweden, assignor to Boda Nova International AB, Höganas, Sweden
Division of Ser. No. 11,706, Aug. 12, 1993, abandoned. This application Apr. 4, 1995, Ser. No. 37,442
Claims priority, application Sweden, Feb. 12, 1993, 93-0372
Term of patent 14 years
U.S. Cl. D7—649




376,963

SHRIMP CLEANING DEVICE


William C. Davis, 2221 Silk Tree Dr., Tustin, Calif. 92680
Filed Mar. 11, 1996, Ser. No. 51,436
Term of patent 14 years
U.S. Cl. D7—693

376,962
OVEN-TONGS

Harry Ludvigsson, Lantbruksgatan 12, Mölndal, Sweden, and Eleonore Larsson, Nergårdsvägen 41, Askim, Sweden
Filed Jan. 6, 1995, Ser. No. 33,195
Claims priority, application Sweden, Jul. 7, 1994, 94-1494; Oct. 19, 1994, 94-2075
Term of patent 14 years
U.S. Cl. D7—686

376,964
SIFTER


Joann Lewy, 225 S. Circle Dr., San Gabriel, Calif. 91776
Filed Jan. 29, 1996, Ser. No. 49,542
Term of patent 14 years
U.S. Cl. D8—1



376,965

FOLDING HANDLE FOR A SLEIGH SHOVEL

Kenneth J. Spear, Vienna, W. Va., and Steven F. Brooker, Marietta, Ohio, assignors to O. Ames Co., Parkersburg, W. Va.
Filed Nov. 7, 1995, Ser. No. 46,095
Term of patent 14 years
U.S. Cl. D8—10



376,967

COMBINED FLEXIBLE PICKUP TOOL COMPONENTS


Kevin S. Fuller, 3675 Gershwin, Oakdale, Minn. 55128
Filed Mar. 29, 1994, Ser. No. 20,596
Term of patent 14 years
U.S. Cl. D8—14




376,966

HAND-HELD DIGGING IMPLEMENT

Jerrold Bartlett, and Glenda Bartlett, both of P.O. Box 348, Clarkston, Wash. 99403-0348
Filed Sep. 18, 1995, Ser. No. 44,131
Term of patent 14 years
U.S. Cl. D8—11

376,968
GRINDER

Kyung T. Kim, Incheon, Rep. of Korea, assignor to LG Industrial Systems Co., Ltd., Seoul, Rep. of Korea
Filed Aug. 28, 1995, Ser. No. 43,377
Claims priority, application Rep. of Korea, Feb. 28, 1995, 95-3416
Term of patent 14 years
U.S. Cl. D8—62




376,969

PISTOL HANDLE PULSE TOOL

Yutaka Kazamaki, New Hartford; Joseph Groshans, Clinton; Jeffrey Spooner, West Winfield; Seth Jones, Camden, and Mark Tinklepaugh, Canastota, all of N.Y., assignors to Chicago Pneumatic Tool Company, Utica, N.Y.

Filed May 11, 1995, Ser. No. 38,654
Term of patent 14 years

U.S. Cl. D8—68




376,971

NO-PIN HINGE

Joseph J. Schutz, 61 Colchester Commons, Colchester, Conn. 06415

Filed Jan. 3, 1996, Ser. No. 48,533
Term of patent 14 years

U.S. Cl. D8—327



376,972

HOLDER FOR BABY WIPES CONTAINER

Diane M. Zissu, Watchung, N.J., assignor to BabySmart, Watchung, N.J.

Division of Ser. No. 89,836, Jul. 12, 1993. This application
Mar. 8, 1995, Ser. No. 35,894
Term of patent 14 years

U.S. Cl. D8—354

376,970

CLAMPING GUN



Johannes Drake, Am Richterbusch 18, 33106 Paderborn, Germany

Filed Oct. 19, 1994, Ser. No. 29,928

Claims priority, application Germany, Apr. 21, 1994,
M9403408.7

Term of patent 14 years

U.S. Cl. D8—72




376,973

GUTTER CLIP

Peter A. Brown, Lubbock, Tex., assignor to Industrial Molding Corporation, Lubbock, Tex.

Filed Mar. 7, 1995, Ser. No. 35,783
Term of patent 14 years

U.S. Cl. D8—395



376,975


COSMETIC TUBE

Tetsuo Hiro; Tetsuo Togasawa, both of Tokyo, and Yotsuda Chieko, Yokohama, all of Japan, assignors to Shiseido Company, Ltd., Tokyo, Japan

Filed May 19, 1995, Ser. No. 39,392

Claims priority, application Japan, Nov. 21, 1994, 6-35102
Term of patent 14 years

U.S. Cl. D9—302



376,976

COLLAPSIBLE BOX FOR A DOLL


Erika B. Eicke, and Eberhard Eicke, both of Steineggweg 18, D-79736 Rickenbach, Germany

Filed Nov. 8, 1995, Ser. No. 46,155

Claims priority, application Germany, May 18, 1995, M 95
04 590.2

Term of patent 14 years

U.S. Cl. D9—418




376,974

TUBE CLAMP

Waterson Chen, No. 477, Kuo-Kuang Rd., Nan Dist., Taichung City, Taiwan

Filed Nov. 21, 1995, Ser. No. 47,082
Term of patent 14 years

U.S. Cl. D8—396



376,977


SAFETY CONTAINMENT HOUSING FOR THE STORAGE
OF HAZARDOUS WASTE MATERIAL

John O. Milliken, Gates Mills, Ohio, assignor to Enpac Corporation, Chardon, Ohio

Filed Jun. 5, 1995, Ser. No. 39,816

Term of patent 14 years

U.S. Cl. D9—431



376,979


COMBINED CONTAINER AND LIDS

Thomas A. Davidson, III, 13 Glen Ave., Castle Hills, New Castle, Del. 19720

Filed Oct. 23, 1995, Ser. No. 46,687

Term of patent 14 years

U.S. Cl. D9—504



376,978


PAIR OF OUTWARDLY RIBBED HANDGRIPS FOR A
CONTAINER

Kerry W. Silvers, Chelsea, and Richard P. Entrup, Tecumseh, both of Mich., assignors to Hoover Universal, Inc., Plymouth, Mich.

Filed Mar. 3, 1995, Ser. No. 35,627

Term of patent 14 years

U.S. Cl. D9—434



376,980


COMBINED CONTAINER AND CAP

Vincent LoPreto, New York, N.Y., assignor to Cosmair, Inc., New York, N.Y.

Filed Mar. 14, 1995, Ser. No. 36,161

Term of patent 14 years

U.S. Cl. D9—542



376,981


CLOCK

Frederick N. Levinger, Providence, R.I., and Brian LaBrecque, New York, N.Y., assignors to Colibri Corporation, Linden Division, Providence, R.I.

Filed Sep. 1, 1995, Ser. No. 43,407

Term of patent 14 years

U.S. Cl. D10—1



376,983


CLOCK

Randy Dieu, 2450 E. 23rd St., Los Angeles, Calif. 90058, assignor to Randy Dieu, Los Angeles, Calif.

Filed Mar. 25, 1996, Ser. No. 52,136

Term of patent 14 years

U.S. Cl. D10—22



376,982


CAMERA SLATE CLOCK

Michael Otto, 33241 Chamizo Calle, Aqua Dulce, Calif. 91350

Filed Dec. 5, 1995, Ser. No. 47,470

Term of patent 14 years

U.S. Cl. D10—6



376,984


WALL CLOCK

Shan-Ker Moore, Taichung Hsien, Taiwan, assignor to Centre Clock Industry Co., Ltd., Taichung Hsien, Taiwan

Filed Dec. 19, 1995, Ser. No. 48,073

Term of patent 14 years

U.S. Cl. D10—24



376,985

WRIST WATCH WITH BRACELET

Marie Ikeuchi, Tokyo, Japan, assignor to Citizen Watch Co., Ltd., Tokyo, Japan

Filed Aug. 14, 1995, Ser. No. 42,687

Term of patent 14 years

U.S. Cl. D10—32



376,987


MEASURING INSTRUMENT

Robert C. Geschwender, 3855 Orchard St., Lincoln, Nebr. 68503

Filed Dec. 15, 1995, Ser. No. 47,944

Term of patent 14 years

U.S. Cl. D10—52



376,986

WRIST WATCH

Yoshito Uzawa, and Naoki Yasukawa, both of Suwa, Japan, assignors to Seiko Epson Corporation, Tokyo, Japan

Filed Aug. 16, 1995, Ser. No. 42,752

Claims priority, application Japan, Apr. 10, 1995, 7-9950

Term of patent 14 years

U.S. Cl. D10—38



376,988


COMBINATION CUTTING GAUGE AND GUIDE

Anthony T. Bruno, 69 Hawthorne Ave., Neptune City, N.J. 07753

Filed Mar. 15, 1996, Ser. No. 51,709

Term of patent 14 years

U.S. Cl. D10—65



376,989


GRAPHICAL TEST INSTRUMENT

George L. McCain, Almelo, Netherlands, assignor to Fluke Corporation, Everett, Wash.

Filed Sep. 27, 1995, Ser. No. 44,629

Term of patent 14 years

U.S. Cl. D10—78



376,991


BABY MONITOR RECEIVER

Theodore B. Freese, Westminster, Colo.; Gregory S. Hinzmann, Hillsboro, and Angelika I. Schubert, Portland, both of Oreg., assignors to Gerry Baby Products Company, Thornton, Colo.

Filed Nov. 3, 1995, Ser. No. 46,754

Term of patent 14 years

U.S. Cl. D10—104



376,990

KITCHEN SCALE


Ennio Pasini, Cesena, and Maurizio Mattei, Macerata, both of Italy, assignors to Fratelli Guzzini S.p.A., Recanati, Italy

Filed Nov. 7, 1995, Ser. No. 46,140

Claims priority, application Italy, May 12, 1995, M19500262

Term of patent 14 years

U.S. Cl. D10—91



376,992


INFRARED BEACON

Gary L. Palmer, Vinton, Va., assignor to ITT Corporation, New York, N.Y.

Filed Nov. 29, 1995, Ser. No. 47,225


Term of patent 14 years

U.S. Cl. D10—106




376,993

SMOKE GENERATING AUTOMOBILE ALARM UNIT
 Joe Epiceno, III, 333 Kirby St., Los Angeles, Calif. 90042
 Filed Jan. 16, 1996, Ser. No. 49,093
 Term of patent 14 years
 U.S. Cl. D10—106



376,995



STIRRUP BUCKLE
 Ben G. Veach, P.O. Box 322, Greencastle, Ind. 46135, and
 Robert L. Shields, P.O. Box 623, Newburgh, Ind. 47629
 Continuation-in-part of Ser. No. 126,871, Sep. 27, 1993, Pat.
 No. 5,452,498. This application Jul. 17, 1995, Ser. No. 41,487
 Term of patent 14 years
 U.S. Cl. D11—216



376,996


TRACK FOR A VEHICLE
 Gilles Soucy, Jean Watelle, and Claude Faucher, all of Drummondville, Canada, assignors to Kimpex, Inc., and Quimpex
 Limitee, both of Drummondville, Canada
 Filed Dec. 12, 1994, Ser. No. 31,979
 Claims priority, application Canada, Jun. 22, 1994, 1994-
 1209
 Term of patent 14 years
 U.S. Cl. D12—7

GARMENT STRAPS RETAINER
 J. Bernice Norris, 5102 Walnut Grove rd., Memphis, Tenn. 38117
 Continuation-in-part of Ser. No. 16,863, Dec. 27, 1993, Pat.
 No. Des. 358,117, and a continuation of Ser. No. 221,522, Apr.
 1, 1994. This application May 3, 1995, Ser. No. 38,322
 Term of patent 14 years
 U.S. Cl. D11—218




376,997

CHOPPER BICYCLE
 David K. Camfield, Olney, Ill., assignor to Roadmaster Corporation, Olney, Ill.
 Filed Sep. 1, 1995, Ser. No. 43,412
 Term of patent 14 years
 U.S. Cl. D12—111




376,999

AUTOMOBILE TIRE
 Yoshimasa Hashimoto; Sadakazu Takel; Toshihiko Suzuki, all
 of Hiratsuka; Izumi Kuramochi, and Hiroshi Tokizaki, both
 of Tokyo, all of Japan, assignors to The Yokohama Rubber
 Co., Ltd., Tokyo, Japan
 Filed Feb. 14, 1995, Ser. No. 34,869
 Claims priority, application Japan, Aug. 16, 1994, 6-24641
 Term of patent 14 years
 U.S. Cl. D12—147



377,000

AUTOMOBILE TIRE
 Takashi Kukimoto, Tokyo, Japan, assignor to Bridgestone Corporation, Tokyo, Japan
 Filed Aug. 21, 1995, Ser. No. 42,905
 Claims priority, application Japan, Feb. 22, 1995, 7-4338
 Term of patent 14 years
 U.S. Cl. D12—147



376,998

REAR DROPOUT FOR BICYCLE
 Michael Stotsky, 1440 W. North Shore Apt. 1W, Chicago, Ill. 60626
 Filed Feb. 13, 1996, Ser. No. 50,287
 Term of patent 14 years
 U.S. Cl. D12—117



377,001


SLIDING FIFTH WHEEL UNIT

Ronald G. Martin, and Patricia A. Martin, both of 2272 Bolyston Rd., Ellensburg, Wash. 98926

Filed Dec. 18, 1995, Ser. No. 48,042

Term of patent 14 years

U.S. Cl. D12-161



377,003

WINDOW HOLDER FOR A VEHICLE


Toshihito Shimazu, Toyota, and Norihiko Murata, Kasugai, both of Japan, assignors to Nifco Inc., Yokohama, Japan

Filed Dec. 5, 1995, Ser. No. 47,483

Claims priority, application Japan, Jun. 19, 1995, 7-17163

Term of patent 14 years

U.S. Cl. D12-223



377,004


CONTAINER FOR ARTICLE STORAGE

Fred W. Timms, 3095 Tig Knight Rd., Loganville, Ga. 30249

Filed Dec. 8, 1995, Ser. No. 47,652

Term of patent 14 years

U.S. Cl. D12-423



377,002


COMBINED SPOILER AND VEHICLE SPARE TIRE COVER

Nga V. Tran, 18771 Pinto La., Santa Ana, Calif. 92705-2263

Filed May 24, 1995, Ser. No. 39,226

Term of patent 14 years

U.S. Cl. D12-202



377,005


LAMP SOCKET

Ching-fang Lin, Taipei Hsien, Taiwan, assignor to Golo Chang Company Ltd., Taipei Hsien, Taiwan

Filed Aug. 18, 1995, Ser. No. 42,828

Term of patent 14 years

U.S. Cl. D13-134



377,007


SHIELDED CONNECTOR

Haw-Chan Tan, Diamond Bar, and Tim S. L. Chang, Chino Hills, both of Calif., assignors to Hon Hai Precision Ind. Co., Ltd., Taiwan

Filed Dec. 8, 1995, Ser. No. 47,635

Term of patent 14 years

U.S. Cl. D13-147



377,006


NETWORK ADAPTOR

Trent L. England, Costa Mesa; Walter D. Kuver, Laguna Hills, both of Calif.; Teddy R. Bryant, Greenville, Tenn., and Shawn G. Hanna, Cupertino, Calif., assignors to Canon Information Systems, Inc., Costa Mesa, Calif.

Filed Jun. 9, 1995, Ser. No. 40,085

Term of patent 14 years

U.S. Cl. D13-147



377,008


COMPUTER DATA STORAGE DEVICE

Carl F. Nicklos, Ogden, Utah, and Nicholas Brawne, Columbus, Ohio, assignors to Iomega Corporation, Roy, Utah

Filed Aug. 25, 1995, Ser. No. 48,746

Term of patent 14 years

U.S. Cl. D14-100




377,009

COMPUTER CABINET WITH EXTENDING SPEAKERS
Stanford W. Crane, Jr., Boca Raton; Bruce Smith, Jupiter, both of Fla.; Aaron Lown, New York, N.Y.; Jon P. Otis, New York, N.Y.; Richard J. Schneebeli, Jr., New York, N.Y., and Stephen G. Burks, Brooklyn, N.Y., assignors to The Panda Project, Boca Raton, Fla.

Filed Nov. 16, 1995, Ser. No. 46,826

Term of patent 14 years

U.S. Cl. D14—106



377,011

TELEVISION RECEIVER


Takashi Inoue, Nara, and Toru Higashibata, Osaka, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Sep. 6, 1995, Ser. No. 43,513

Claims priority, application Japan, Mar. 8, 1995, 7-6263

Term of patent 14 years

U.S. Cl. D14—126



377,010

TELEVISION RECEIVER


Shigeo Usui, and Mitsunari Fujii, both of Osaka, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Aug. 24, 1995, Ser. No. 43,054

Claims priority, application Japan, Apr. 14, 1995, 7-10448

Term of patent 14 years

U.S. Cl. D14—126



377,012


REAR PROJECTION SCREEN

Carl J. Oslund, Eugene, Oreg., assignor to Oslund Design Incorporated, Eugene, Oreg.

Filed Sep. 25, 1995, Ser. No. 44,486

Term of patent 14 years

U.S. Cl. D14—128



377,013

TELEVISION RECEIVER WITH COMPUTER


Masakazu Mori, and Tamotsu Senda, both of Ehime, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Sep. 18, 1995, Ser. No. 44,118

Claims priority, application Japan, Mar. 17, 1995, 7-7381

Term of patent 14 years

U.S. Cl. D14—129



377,015


SHOWER SPEAKER TELEPHONE HANDSET

Joseph E. Ford, Cary; Donald N. Jursich, Chicago, both of Ill., and Raymond Chan, Vancouver, Canada, assignors to Jing Mei Industrial Holdings, Ltd.

Filed Oct. 18, 1995, Ser. No. 46,634

Term of patent 14 years

U.S. Cl. D14—149



377,014

PORTABLE TELEPHONE HANDSET


Daniel R. Biskup, Somerset; Pratod V. Kasbekar, Manalapan, both of N.J.; Michael J. Nuttall, Portola valley, Calif.; Heidi A. Rajan, Morganville, N.J.; Christopher A. Robinette, Woodside, Calif.; John H. Schaffeld, New Vernon, and Chaoong Yoh, Matawan, both of N.J., assignors to Lucent Technologies Inc., Murray Hill, N.J.

Filed Jan. 4, 1995, Ser. No. 33,030

The portion of the term of this patent subsequent to Dec. 3, 2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D14—138



377,016

TELEPHONE SET

Josh Zeitman, Brooklyn, N.Y., assignor to Lenox Electronics Corp., Brooklyn, N.Y.

Filed Jun. 27, 1995, Ser. No. 40,817

Claims priority, application United Kingdom, May 5, 1995, 2047264

The portion of the term of this patent subsequent to Jun. 4, 2010, has been disclaimed.

Term of patent 14 years

U.S. Cl. D14—151



377,017


RELIGIOUS STATUE CASSETTE PLAYER

John Giumarra, #1 Bryant Crescent - Apt. 1-1, White Plains, N.Y. 10607

Filed Mar. 19, 1996, Ser. No. 51,827

Term of patent 14 years

U.S. Cl. D14—164



377,019

PAGER


Katsumi Nagano, and Yuko Komamiya, both of Kanagawa, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Dec. 18, 1995, Ser. No. 47,978

Claims priority, application Japan, Aug. 2, 1995, 7-22823

Term of patent 14 years

U.S. Cl. D14—191



377,020

COMMUNICATIONS HEADSET

Gabriele Bungardt, Aptos, Calif.; Luis Pedraza, West Roxbury, Mass., and Tim Dearborn, Rochester Hills, Mich., assignors to Plantronics, Inc., Santa Cruz, Calif.

Filed Apr. 19, 1995, Ser. No. 37,706

Term of patent 14 years

U.S. Cl. D14—205

377,018

PAGER



Masataka Suzuki, and Shuji Yamaguchi, both of Tokyo, Japan, assignors to NEC Corporation, Tokyo, Japan

Filed Sep. 29, 1995, Ser. No. 44,699

Claims priority, application Japan, Mar. 31, 1995, 7-8923

Term of patent 14 years

U.S. Cl. D14—191



377,021


HEADPHONE

Rie Isono, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Filed Aug. 29, 1995, Ser. No. 43,195

Term of patent 14 years

U.S. Cl. D14—205



377,023

UNTETHERED COMMUNICATIONS/MEDIA HANDSET

Douglas Andrea, New York, N.Y., assignor to Andrea Electronics Corporation, Long Island City, N.Y.

Filed Jun. 5, 1995, Ser. No. 39,769

Term of patent 14 years

U.S. Cl. D14—218



377,024

TETHERED MEDIA/COMMUNICATION HANDSET

Douglas Andrea, New York, N.Y., assignor to Andrea Electronics Corporation, Long Island City, N.Y.

Continuation-in-part of Ser. No. 39,769, Jun. 5, 1995. This

application Feb. 14, 1996, Ser. No. 50,326

Term of patent 14 years

U.S. Cl. D14—218

377,022



SPEAKER BOX

Hitoshi Takahashi, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Filed Aug. 3, 1995, Ser. No. 42,182

Term of patent 14 years

U.S. Cl. D14—214



377,025

IMITATION EAGLE ANTENNA

Carl W. Leu, Miami, Fla., assignor to Poli-Auto, Inc., Miami, Fla.

Division of Ser. No. 17,935, Jan. 26, 1994, Pat. No. Des. 363,071, which is a continuation-in-part of Ser. No. 5,923, Mar. 12, 1993, Pat. No. Des. 347,226. This application Jun. 30, 1995, Ser. No. 40,981

Term of patent 14 years

U.S. Cl. D14—230



377,027


TROLLING MOTOR FOOT PEDAL CONTROL

Calvin Tyler, Gadsden, Ala.; Prentice Moore, Starkville, Miss., and Jack Robbins, Derby, Kans., assignors to Brunswick Corporation, Lake Forest, Ill.

Filed Apr. 21, 1995, Ser. No. 37,865

Term of patent 14 years

U.S. Cl. D15—4



377,028


ICE HOLDING AND DRAINING BASKET

Ronald Monday, 812 Berkshire La., Carol Stream, Ill. 60188

Filed May 8, 1995, Ser. No. 38,541

Term of patent 14 years

U.S. Cl. D15—90



377,026


DISPLAY PANEL FOR A SELECTIVE CALL RECEIVER

Anthony W. Cuteri, Lantana; Barry S. Boes, Boynton Beach, and Arturo Heinsen, Delray Beach, all of Fla., assignors to Motorola, Inc., Schaumburg, Ill.

Filed Sep. 18, 1995, Ser. No. 44,127

Term of patent 14 years

U.S. Cl. D14—257



377,029

DRILL BIT FINGER

Gavin T. McLeod, 21B Hertford Close, Bullcreek, Western Australia 6154, and Matthew V. Egan, 21 San Miguel Drive, Leeming, Western Australia 6155, both of Australia

Filed Jun. 7, 1995, Ser. No. 40,007

Claims priority, application Australia, Dec. 15, 1994, 4179/94

Term of patent 14 years

U.S. Cl. D15—139



377,031


THREADED FUNNEL

Emmanuel R. Didier, 111 Marquez Pl., Pacific Palisades, Calif. 90272

Filed Nov. 14, 1995, Ser. No. 46,424

Term of patent 14 years

U.S. Cl. D15—150



377,032

VIDEO CAMERA

Takashi Morooka, Tokyo, Japan, assignor to Sony Corporation, Tokyo, Japan

Filed Jul. 19, 1995, Ser. No. 41,604

Term of patent 14 years

U.S. Cl. D16—202



377,030


SAND BAG FILLING DEVICE

James J. Spear, 1321 N. 76th East Ave., Tulsa, Okla. 74115

Filed Dec. 15, 1995, Ser. No. 47,883

Term of patent 14 years

U.S. Cl. D15—145




377,033
TV CAMERA

Mineo Kubota, Kofu, and Masayoshi Satou, Yamanashi-ken, both of Japan, assignors to Nisca Corporation, Yamanashi-ken, Japan

Filed Dec. 19, 1995, Ser. No. 48,044
Term of patent 14 years

U.S. Cl. D16—202




377,035
35 MM CAMERA

Tatsuyuki Hayashi, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 18, 1996, Ser. No. 49,137
Claims priority, application Japan, Jul. 18, 1995, 7-20686
Term of patent 14 years

U.S. Cl. D16—209




377,034

DIGITAL CAMERA

Takeshi Matsushita, Tokyo, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 18, 1996, Ser. No. 49,136
Claims priority, application Japan, Jul. 18, 1995, 7-20687
Term of patent 14 years

U.S. Cl. D16—202




377,036

SPORTS EYEWEAR

Peter F. Leonardi, Gloversville, N.Y., assignor to Halo Sports and Safety, Inc., Gloversville, N.Y.

Filed Jan. 26, 1996, Ser. No. 49,504
Term of patent 14 years

U.S. Cl. D16—304



377,037
COMBINED EYE WEAR AND FLEXIBLE STRAP
TEMPLES

Jill L. Stolt, 31 Edmonds St., Rochester, N.Y. 14607

Filed Feb. 21, 1995, Ser. No. 35,433
Term of patent 14 years

U.S. Cl. D16—306




377,039
SWIMMING GOGGLES

Kimiko Minamidani, Higashi-Osaka, Japan, assignor to Yamamoto Kogaku Co., Ltd., Higashi-Osaka, Japan

Filed Jan. 30, 1996, Ser. No. 49,752
Claims priority, application Japan, Aug. 3, 1995, 7-22985
Term of patent 14 years

U.S. Cl. D16—311




377,038

SWIMMING GOGGLES

Tomoyuki Yashiro, Osaka, Japan, assignor to Yamamoto Kogaku Co., Ltd., Higashi-Osaka, Japan

Filed Jan. 30, 1996, Ser. No. 49,722
Claims priority, application Japan, Aug. 21, 1995, 7-24227
Term of patent 14 years

U.S. Cl. D16—311



377,040

EYEGLASSES

Carlos A. Khantzis, Woodland Hills, and Ruta Z. Empakeris, Santa Monica, both of Calif., assignors to California Design Studio Inc., Westlake Village, Calif.

Filed Dec. 18, 1995, Ser. No. 48,017
Term of patent 14 years

U.S. Cl. D16—317



377,049

DOCUMENT CASE

James T. M. Guyer, 3115 Kensington St., Tampa, Fla. 33629,
and Michael L. Cone, 6735 S. Lois Ave., Tampa, Fla. 33616
Filed Sep. 15, 1994, Ser. No. 28,434
Term of patent 14 years

U.S. Cl. D19—27



377,051

WRITING PEN

Shun Takemura, Torrance, Calif., assignor to Itoya of America,
Ltd., Torrance, Calif.

Filed Apr. 23, 1996, Ser. No. 53,489

Term of patent 14 years

U.S. Cl. D19—51




377,050

MECHANICAL PENCIL WITH ATTACHED MOLDED PENCIL GRIP

Fayez Azeez, 40 Hollis Rd., East Brunswick, N.J. 08816-2754
Filed May 6, 1996, Ser. No. 54,075

Term of patent 14 years

U.S. Cl. D19—49



377,052


VENDING MACHINE

Robert H. Woodard, Ventura, Calif., assignor to Accurate
Engineering Precision Sheet Metal Fabrication and Machin-
ing, Inc., Newbury Park, Calif.

Filed Oct. 13, 1995, Ser. No. 46,616

Term of patent 14 years

U.S. Cl. D20—2



377,053

DISPLAY GARMENT FOR THE HAND

Douglas A. Williams, 926 Victoria Landing Dr., Woodstock,
Ga. 30188

Filed Feb. 23, 1995, Ser. No. 35,252

Term of patent 14 years

U.S. Cl. D20—33



377,055


GAME BOARD

Danna D. Thompson, 375 Merton St. Apt. 108, Toronto,
Ontario, Canada

Filed Sep. 29, 1995, Ser. No. 44,769

Term of patent 14 years

U.S. Cl. D21—31



377,054

VERTICAL HOLDER FOR PAPER INSERTS

Robert A. Noreika, Rocky Hill, Conn., assignor to Gastro-
Gnomes, Inc., West Hartford, Conn.

Filed Aug. 31, 1994, Ser. No. 27,878

Term of patent 14 years

U.S. Cl. D20—40



377,056

JOYSTICK

Ricardo Salinas, Palo Alto, Calif., assignor to Logitech S.A.,
Romanel/Morges, Switzerland

Filed Sep. 27, 1995, Ser. No. 44,594

Term of patent 14 years

U.S. Cl. D21—48



377,057


ELECTRONIC GAME HOUSING

Lan-Yan Lee, Fanling, N.T., Hong Kong, assignor to Esel International Company Limited, Hong Kong

Filed Feb. 15, 1996, Ser. No. 50,349

Term of patent 14 years

U.S. Cl. D21—48



377,059

CONSTRUCTION GAME


Peter Larws, Schlappmuhlerpfad 13, 61250 Usingen, Germany

Filed Aug. 24, 1994, Ser. No. 27,575

Claims priority, application Benelux TM/Des. Off., Feb. 28, 1994, 69524/01-06

Term of patent 14 years

U.S. Cl. D21—108



377,058


FLYING TOY

Michael E. Henley, Santa Barbara, Calif., assignor to Lanard Toys Limited, Hong Kong

Filed Oct. 13, 1995, Ser. No. 45,252

Term of patent 14 years

U.S. Cl. D21—83



377,060


TUMBLER

Jesper B. Frederiksen, Nykøbing F., Denmark, assignor to INTERLEGO AG, Baar, Switzerland

Filed Sep. 29, 1994, Ser. No. 29,186

Term of patent 14 years

U.S. Cl. D21—108



377,061


DOME FOR BALL AND ROD TOY CONSTRUCTION SET

Richard Gabriel, Portland, Oreg., assignor to Matrix Toys, Ltd., Portland, Oreg.

Filed Jan. 11, 1996, Ser. No. 48,710

Term of patent 14 years

U.S. Cl. D21—108



377,063


TOY

Constance R. Sisler, 50 Sutton Place South, New York, N.Y. 10022

Filed Nov. 28, 1995, Ser. No. 47,198

Term of patent 14 years

U.S. Cl. D21—161




377,064

DOLL

Carl Gurbisz, 3 Belaire Dr., Matawan, N.J. 07747

Filed Jun. 28, 1994, Ser. No. 25,266

Term of patent 14 years



377,062


CAVITY FOR BALL AND ROD TOY CONSTRUCTION SET

Richard Gabriel, Portland, Oreg., assignor to Matrix Toys, Ltd., Portland, Oreg.

Filed Jan. 11, 1996, Ser. No. 48,711

Term of patent 14 years

U.S. Cl. D21—108



377,065


ATHLETIC BALL

Khurshid A. Soofi, Saga House, Daska Road, Toor Abad, Mubarikpura, Sialkot, Pakistan

Filed Jan. 17, 1995, Ser. No. 33,637

Term of patent 14 years

U.S. Cl. D21—204



377,067

GOLF CLUB

Terry Wiens, 1814 - 196th Street, Langley, B.C., Canada, and Greg Howard, 3553 West 25th Street, Vancouver, B.C., Canada

Filed Jul. 7, 1995, Ser. No. 41,170

Term of patent 14 years

U.S. Cl. D21—219



377,066

COMBINED GOLF CLUB AND LEVEL

Charles L. Goosman, and Cheryl L. Goosman, both of Box 695, Gauley Bridge, W. Va. 25085

Filed Jul. 12, 1995, Ser. No. 41,362

Term of patent 14 years

U.S. Cl. D21—214



377,068


GOLF CLUB HEAD

John T. Stites, III, Fortworth, Tex., assignor to Ray Cook Golf Company, Vista, Calif.

Filed Aug. 11, 1995, Ser. No. 42,561

Term of patent 14 years

U.S. Cl. D21—220



377,069

GOLF HEAD COVER

Randal W. High, 4456 W. 76th St., #103, Edina, Minn. 55435

Continuation of Ser. No. 669,214, Mar. 13, 1991, abandoned.

This application Nov. 24, 1993, Ser. No. 15,713

Term of patent 14 years

U.S. Cl. D21—221



377,071

SKATE BOOT

Ting-Hsing Chen, Tainan, Taiwan, assignor to Far Great Plastics Industrial Co., Ltd., Tainan, Taiwan

Filed Apr. 29, 1996, Ser. No. 53,721

Term of patent 14 years

U.S. Cl. D21—226



377,070

GOLF PUTTER GRIP

Paul Gurrola, 949 S. Hope St., #3130, Los Angeles, Calif. 90015

Filed May 25, 1995, Ser. No. 40,197

Term of patent 14 years

U.S. Cl. D21—222



377,072


SURFBOARD WITH TRANSPARENT WINDOW

Patrick L. Ilejay, North Hollywood, Calif., assignor to Leon Opseth, North Hollywood, Calif.

Filed Dec. 22, 1995, Ser. No. 48,233

Term of patent 14 years

U.S. Cl. D21—236



377,073


SWIMMING FIN

Barney Chang, No. 2, Lane 380, Chin-Hua N. Rd., Taichung, Taiwan

Filed Jan. 30, 1996, Ser. No. 49,735

Term of patent 14 years

U.S. Cl. D21—239



377,075


PLAYGROUND APPARATUS

Kenneth D. Temple, Twinshurg, and Christopher G. Walter, Suffield, both of Ohio, assignors to The Little Tikes Company, Hudson, Ohio

Filed Jul. 10, 1995, Ser. No. 41,216

Term of patent 14 years

U.S. Cl. D21—244



377,074


PLAYGROUND ACTIVITY APPARATUS

William K. Ford, Hudson, and Matthew R. Fullini, Twinshurg, both of Ohio, assignors to The Little Tikes Company, Hudson, Ohio

Filed Jul. 7, 1995, Ser. No. 41,126

Term of patent 14 years

U.S. Cl. D21—243



377,076

TENT STAKE

William E. Adams, Portersville, Pa., assignor to Adams Mfg. Corp., Portersville, Pa.

Filed Nov. 28, 1995, Ser. No. 47,196

Term of patent 14 years

U.S. Cl. D21—255



377,077

PISTOL


René Predazzer, Flemalle, Belgium, assignor to Fabrique Nationale Nouvelle Herstal, Herstal, Belgium

Filed Feb. 15, 1995, Ser. No. 34,907

Claims priority, application Belgium, Jan. 24, 1995, 5718

Term of patent 14 years

U.S. Cl. D22—104



377,079


ICE FISHING REEL

Paul Robinson, Box 81, Dwight, ON, Canada

Filed Sep. 29, 1995, Ser. No. 44,787

Term of patent 14 years

U.S. Cl. D22—137



377,080

FISH HOOK REMOVER

Ed E. Johnston, P.O. Box 648, Opalika, Ala. 36803-0648

Filed Dec. 18, 1995, Ser. No. 47,973

Term of patent 14 years

U.S. Cl. D22—149



377,078

ARROW REST SUPPORT GUIDE

B. Howard Coffey, LaGrange, Ky., assignor to Coffey Marketing Corporation, Crestwood, Ky.

Filed Jan. 30, 1996, Ser. No. 49,731

Term of patent 14 years

U.S. Cl. D22—107



377,081


WATER TREATMENT CABINET

Alfred J. Lipshultz, 4090 Lake Dr., Coconut Creek, Fla. 33066, and Mitchell Lipshultz, Fort Lauderdale, Fla., assignors to Alfred J. Lipshultz, Coconut Creek, Fla.

Filed Oct. 10, 1995, Ser. No. 45,080

Term of patent 14 years

U.S. Cl. D23—207



377,083


FLOOR REGISTER GRILLE

Morris Smolarski, Victoria, Australia, assignor to Ripponlea Austria Pty. Ltd., Victoria, Australia

Filed Mar. 24, 1995, Ser. No. 36,782

Term of patent 14 years

U.S. Cl. D23—393



377,084


COMBINED CEILING FAN MOUNTING CANOPY, MOTOR AND SWITCH HOUSING AND BLADE IRONS UNIT

Charles J. DiPasquale, Carrollton, Tex., assignor to Smartel, Inc., Carrollton, Tex.

Filed Jan. 27, 1995, Ser. No. 34,112

Term of patent 14 years

U.S. Cl. D23—411



377,082


WHIRLPOOL TUB

Christopher A. Lacy, New Brighton, Minn., assignor to Pearl Baths, Inc., Minneapolis, Minn.

Filed Sep. 5, 1995, Ser. No. 43,506

Term of patent 14 years

U.S. Cl. D23—277



377,085


TABLET

George E. Tortarolo, Bridgewater, N.J., assignor to Warner-Lambert Company, Morris Plains, N.J.

Filed Jul. 28, 1995, Ser. No. 41,966

Term of patent 14 years

U.S. Cl. D24—101



377,087


SOFTGEL CAPSULE

Gregory A. Schurig, Clearwater, and David G. Williams, Palm Harbor, both of Fla., assignors to R. P. Scherer Corporation, Troy, Mich.

Filed Dec. 4, 1995, Ser. No. 47,413

Term of patent 14 years

U.S. Cl. D24—104



377,088

Patent Not Issued For This Number

377,089


RESPIRATORY MASK FACIAL SEAL

Eric W. Starr, Gibsonia; John R. Starr, Leechburg, and Mary T. Walthour, Pitcairn, all of Pa., assignors to Respironics, Inc., Murrysville, Pa.

Filed Jun. 6, 1995, Ser. No. 39,856

Term of patent 14 years

U.S. Cl. D24—110.1



377,086


TABLET

George E. Tortarolo, Bridgewater, N.J., assignor to Warner-Lambert Company, Morris Plains, N.J.

Filed Jul. 28, 1995, Ser. No. 41,968

Term of patent 14 years

U.S. Cl. D24—101



377,090


AID FOR ARTIFICIAL RESPIRATION

Gary C. J. Lee, No. 12, Alley 16, Chung-San St., Hsi-Chih, Taiwan

Filed Dec. 27, 1995, Ser. No. 48,353

Term of patent 14 years

U.S. Cl. D24—110.4



377,092


IV STAND HANDLE

Fred Ebert, 1250 Doblon St., Apt. C, Green Bay, Wis. 54302

Filed Jul. 3, 1995, Ser. No. 41,052

Term of patent 14 years

U.S. Cl. D24—128



377,093


SPINAL DISTRATOR

Gary K. Michelson, 438 Sherman Canal, Venice, Calif. 90291

Filed May 27, 1994, Ser. No. 23,623

Term of patent 14 years

U.S. Cl. D24—135



377,091

INSTRUMENT FOR ADMINISTERING MEDICATION TO THE NOSE


Jack J. Scott, Sr., P.O. Box 248, Bethany, Ill. 61914

Division of Ser. No. 167,241, Dec. 15, 1993, Pat. No.

5,417,652. This application May 12, 1995, Ser. No. 38,963

Term of patent 14 years

U.S. Cl. D24—121



377,094


CLIP APPLICATOR HANDLE

David L. Foshee, Apex; Stephen J. Dawes, Raleigh; Bahram B. Rahimizadeh, Durham, and Jason R. Durkin, Raleigh, all of N.C., assignors to Pilling Week Incorporated, Research Triangle Park, N.C.

Filed Jun. 2, 1995, Ser. No. 39,814

Term of patent 14 years

U.S. Cl. D24—143



377,096


INTERBODY SPINAL IMPLANT

Gary K. Michelson, Venice, Calif., assignor to Sofamor Danek Properties, Inc., Memphis, Tenn.

Filed Jun. 3, 1994, Ser. No. 23,926

Term of patent 14 years

U.S. Cl. D24—155



377,095

INTERBODY SPINAL IMPLANT

Gary K. Michelson, Venice, Calif., assignor to Sofamor Danek Properties, Inc., Memphis, Tenn.

Filed Jun. 3, 1994, Ser. No. 23,923

Term of patent 14 years

U.S. Cl. D24—155



377,097


DEFIBRILLATOR IN SOFT-SIDED CARRYING BAG

Kenneth F. Olson, Minneapolis; Byron L. Gilman, Plymouth; Thomas M. Reiter, Woodbury, all of Minn., and James W. Luther, Boston, Mass., assignors to Survivalink Corporation, Minneapolis, Minn.

Filed Jun. 1, 1995, Ser. No. 39,811

Term of patent 14 years

U.S. Cl. D24—168




377,098

DEVICE FOR USE AS A LEARNING AID FOR
CONVEYING A USER'S VOICE TO THE USER'S EAR
Kenichi Morimoto, Kitasouma-gun, Japan, assignor to Yugen-
kaisha Keiei Vision Center, Japan
Filed Oct. 18, 1994, Ser. No. 29,853
Term of patent 14 years
U.S. Cl. D24—175



377,100

MASSAGE DEVICE
Bernard L. Gladieux, Jr., 128 Oberholtzer Rd., Gilbertsville,
Pa. 19525
Filed Oct. 18, 1995, Ser. No. 45,395
Term of patent 14 years
U.S. Cl. D24—211




377,099

COLOR GUIDE FOR ARTIFICIAL TEETH
Devon O. Howe, York, Pa., assignor to Dentsply Research &
Development Corp., Milford, Del.
Filed Nov. 14, 1995, Ser. No. 49,021
Term of patent 14 years
U.S. Cl. D24—181




377,101

WINDOW COMPONENT EXTRUSION
Lorane C. Goss, Jr., Slippery Rock, Pa., assignor to Mikron
Industries, Kent, Wash.
Filed May 31, 1995, Ser. No. 39,613
The portion of the term of this patent subsequent to Aug. 6,
2010, has been disclaimed.
Term of patent 14 years
U.S. Cl. D25—124




377,102

WINDOW COMPONENT EXTRUSION
Teresa A. Oliver, Kent, Wash., assignor to Mikron Industries,
Inc., Kent, Wash.
Filed Dec. 1, 1995, Ser. No. 47,344
Term of patent 14 years
U.S. Cl. D25—124



377,104

LAMP WITH HEAT SINK
Roy D. Roberts, Newark, Calif., assignor to ILC Technology,
Inc., Sunnyvale, Calif.
Filed Apr. 13, 1995, Ser. No. 37,451
Term of patent 14 years
U.S. Cl. D26—24




377,103

CANDLE TOPPER
Peggie (Margaret) C. Hibner, and Harry P. Hibner, Jr., both of
7015 Erdrick St., Philadelphia, Pa. 19135
Filed Feb. 22, 1996, Ser. No. 50,678
Term of patent 14 years
U.S. Cl. D26—23



377,105

RECHARGEABLE FLASHLIGHT
Se K. Yuen, Kowloon, Hong Kong, assignor to John Manufac-
turing Limited, Kowloon, Hong Kong
Filed Dec. 5, 1995, Ser. No. 47,490
Claims priority, application United Kingdom, Jul. 24, 1995,
2049028
Term of patent 14 years
U.S. Cl. D26—38



377,106
LAMP

Alex Chan, Hong Kong, Hong Kong, assignor to Alpan, Inc.,
Camarillo, Calif.

Filed Aug. 11, 1995, Ser. No. 42,497

Term of patent 14 years

U.S. Cl. D26—62



LIST OF PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 31st DAY OF DECEMBER, 1996

NOTE— Arranged in accordance with the first significant character or word of the name
(in accordance with city and telephone directory practice).

- A.C.E. Corporation: *See—*
Atsumi, Haruo, 5,588,966, Cl. 604-110,000.
- A.W.T. World Trade, Inc.: *See—*
Bart, Mark, 5,588,770, Cl. 403-325,000.
- Abajian, Henry B.; Noble, John F.; and Hlavka, Joseph J., to Innapharma, Inc., Tri-, tetra-, penta-, and polypeptides and their therapeutic use as an antidepressant agent, 5,589,460, Cl. 514-17,000.
- Abatement Technologies, Inc.: *See—*
Shagott, David M.; Kruse, Gary E.; Harber, Blair L., Jr.; Sutherland, Daniel N.; and Travis, Terrell F., 5,588,985, Cl. 95-25,000.
- Abaxis, Inc.: *See—*
Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498,000.
- ABB Industry Oy: *See—*
Heikkilä, Samuli, 5,589,754, Cl. 318-805,000.
- ABB Management AG: *See—*
Berger, Ernst; Heil, Franz; Schifko, Herbert; and Tecchio, Piero, 5,589,674, Cl. 218-71,000.
- Döbbling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelmayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431-354,000.
- Kreitmeyer, Franz, 5,588,799, Cl. 415-211,200.
- McMillan, Robin T. D., 5,588,824, Cl. 431-285,000.
- ABB Paint Finishing, Inc.: *See—*
Josefsson, Leif E. B.; and Monte, Robert F., 5,588,830, Cl. 432-147,000.
- Abbas, Fazal: *See—*
Shariff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, 5,590,374, Cl. 395-829,000.
- Abbott Laboratories: *See—*
Fiechtner, Michael D.; Ramp, John M.; England, Barbara J.; and Annino, Mary J., 5,589,393, Cl. 436-15,000.
- Hochlowski, Jill E.; Jackson, Marianna; Kadam, Sunil K.; Karwowski, James P.; and McAlpine, James B., 5,589,485, Cl. 514-315,000.
- Kim, Young R.; Iles, Kenneth E.; and Larue, Roderick W., 5,589,394, Cl. 436-63,000.
- Abbott, Martyn; and Thompson, Thomas C., to Quest Medical, Inc. Disposable cassette for cardioplegia delivery system, 5,588,816, Cl. 417-479,000.
- Abe, Akira: *See—*
Yoshida, Kiyohide; Muramatsu, Gyo; Abe, Akira; and Irite, Naoko, 5,589,432, Cl. 502-325,000.
- Abe, Kimhiro: *See—*
Tsuji, Masanori; Abe, Kimhiro; Sugiyama, Osamu; and Yamamoto, Hiroshi, 5,588,868, Cl. 439-397,000.
- Abe, Seiichi, to Hitachi, Ltd. Circuit and method for retaining DRAM content, 5,590,082, Cl. 365-222,000.
- Abe, Takahide; and Takaba, Katsumi, to Nippondenso Co., Ltd. Self-diagnosis apparatus for vehicle, 5,590,040, Cl. 364-424,040.
- Abe, Tomohiko; Yasuda, Hiroshi; Sakamoto, Kiichi; and Oae, Yoshihisa, to Fujitsu Limited. Block exposure pattern data extracting system and method for charged particle beam exposure, 5,590,048, Cl. 364-489,000.
- Abecassis, Max. Computer-themed playing system, 5,589,945, Cl. 386-83,000.
- Abersfelder, Günther: *See—*
Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425,600.
- Abramovici, Miron; Agrawal, Vishwani D.; Cheng, Kwang-Ting; and Rajan, Krishna B., to Lucent Technologies Inc. Testing a sequential circuit, 5,590,135, Cl. 371-22,100.
- Abtex Corporation: *See—*
Biocca, Peter M., 5,588,172, Cl. 15-179,000.
- AC Directional Control, Inc.: *See—*
Gomez, Reynaldo, 5,588,911, Cl. 454-290,000.
- Acampora, Anthony S.; and Naghshineh, Mahmoud, to Trustees of Columbia University in the City of New York, The. Method and apparatus for supporting mobile communications in asynchronous transfer mode based networks, 5,590,125, Cl. 370-397,000.
- Acerinox, S.A.: *See—*
Nagata, Masato, and Comejo, José, 5,588,828, Cl. 432-59,000.
- Achelpohl, Fritz; and Sandmeier, Hermann, to Windmüller & Holscher. Apparatus for welding the tubular sections of sacks, bags or the like, 5,588,944, Cl. 493-205,000.
- Ackerman, David W.: *See—*
Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51,200.
- Acme Electric Corporation: *See—*
Wood, Daniel P., 5,588,880, Cl. 439-709,000.
- Acra Products, LLC: *See—*
Embree, Gary L.; and Williams, Robert A., 5,588,382, Cl. 111-139,000.
- Adachi, Fumiyuki: *See—*
Sawashashi, Mamoru; and Adachi, Fumiyuki, 5,590,409, Cl. 455-69,000.
- Adachi, Rensuke: *See—*
Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikiyo; and Koeda, Takashi, 5,588,950, Cl. 600-178,000.
- Adachi, Takashi; Ishii, Takafumi; and Hidaka, Hidemasa, to Meiji Seika Kaisha, Ltd. Plant cultivation method, 5,588,254, Cl. 47-57,600.
- Adamezyk, John W., to Walt Disney Company. The. Method and system for guiding a user in a virtual reality presentation, 5,588,914, Cl. 463-32,000.
- Adams Rite Manufacturing Company: *See—*
Riley, Rory M.; Uveda, Alan K.; and Winardi, Michael, 5,588,686, Cl. 292-92,000.
- Adamson, Robert E., Jr.: *See—*
Bolsworth, James; and Adamson, Robert E., Jr., 5,588,707, Cl. 297-378,120.
- Adkins, John L.; and Patel, Dinesh P., to Sun Chemical Corporation. Chemically stable ascorbate-based photographic developer and imaging process, 5,589,323, Cl. 430-492,000.
- Adkisson, Richard W., to Covex Computer Corporation. Circuits, systems and methods for preventing queue overflow in data processing systems, 5,590,304, Cl. 395-427,000.
- Adobe Systems Incorporated: *See—*
Schiller, Stephen N., 5,590,223, Cl. 382-270,000.
- Advance Biofactures of Curacao: *See—*
Wegman, Thomas L., 5,589,171, Cl. 424-94,670.
- Advanced Accessory Systems LLC: *See—*
Cronce, Gary M.; and Stapleton, Craig A., 5,588,572, Cl. 224-321,000.
- Advanced Elastomer Systems, L.P.: *See—*
Horion, Jacques, 5,589,544, Cl. 525-176,000.
- Advanced Fuel Research, Inc.: *See—*
Solomon, Peter R., 5,588,632, Cl. 248-560,000.
- Advanced Logic Research: *See—*
Sangveraphunsiri, Vic; Pina, Felix; Shu, Thomas; and Spears, Cameron, 5,590,375, Cl. 395-841,000.
- Advanced Magnetics, Inc.: *See—*
Lewis, Jerome M., 5,589,591, Cl. 536-128,000.
- Advanced Micro Devices, Inc.: *See—*
Haddad, Sameer S.; Chang, Chi; and Liu, David K. Y., 5,590,076, Cl. 365-185,250.
- Linz, Alfredo R.; Cabler, Carlin D.; Brown, Glen W.; and Soques, Martin P., 5,589,830, Cl. 341-110,000.
- Lo, William, 5,590,201, Cl. 380-49,000.
- Sharpe-Geisler, Bradley A., 5,589,782, Cl. 326-38,000.
- Sowadsky, Elliot A.; Widigen, Larry; Puziol, David L.; and Van Dyke, Korbin S., 5,590,351, Cl. 395-800,000.
- Zuraski, Gerald D., Jr.; White, Scott A.; Chinnakonda, Murali S.; and Christie, David S., 5,590,352, Cl. 395-800,000.
- Advanced Technologies (Cambridge) Ltd.: *See—*
Gurr, Sarah J.; McPherson, Michael J.; Atkinson, Howard J.; and Bowles, Dianna J., 5,589,622, Cl. 800-205,000.
- Advantek, Inc.: *See—*
Smith, Nathan R., 5,588,797, Cl. 414-797,500.
- Advantest Corporation: *See—*
Ueda, Koshi; Goishi, Akira; and Kuribara, Masayuki, 5,589,780, Cl. 324-751,000.
- Yamaguchi, Takahiro; Tajiri, Shinsuke; and Nakada, Juichi, 5,590,158, Cl. 375-331,000.
- Yamashita, Kazuhiro, 5,590,137, Cl. 371-27,000.
- Aerospaiale Societe Nationale Industrielle: *See—*
Baudrillard, Gilles; and Bouja, Christophe P., 5,589,635, Cl. 73-600,000.
- Kasser, Michel; and Lund, Glenn, 5,589,981, Cl. 359-529,000.
- Afek, Yachin: *See—*
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Affaticati, Artemio; Cerutti, Claudio; and Ceglia, Teodoro, to Rapistan Demag Corp. Crossbelt sortation system, 5,588,520, Cl. 198-370,060.
- AG Technology Co., Ltd.: *See—*
Kato, Naoki; and Kunigita, Masaya, 5,589,406, Cl. 437-21,000.
- Agai-Csongor, Eva: *See—*

- Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpomy, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
- Agar Corporation Inc.: See—
Agar, Joram; and Farchi, David, 5,589,642, Cl. 73-861,040.
- Agar, Joram; and Farchi, David, to Agar Corporation Inc. High void fraction multi-phase fluid flow meter, 5,589,642, Cl. 73-861,040.
- Agarwal, Anjana, and Lee, Chinmei C., to Lucent Technologies Inc. Arrangement for local trunk hunting in a distributed switching system, 5,590,176, Cl. 379-59,000.
- AGF Manufacturing, Inc.: See—
McHugh, George J., 5,588,462, Cl. 137-557,000.
- AGFA Division, Bayer Corporation: See—
King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Romhult, Philip A.; and Hebert, Thomas K., 5,589,973, Cl. 359-214,000.
- Tellam, Mark E.; Brook, Mark G.; Haded, Kevin J.; and Wheeler, Joseph A., 5,589,972, Cl. 359-196,000.
- AGFA-Gevaert, N.V.: See—
De Jaeger, Nikolaas; Damen, Guy; Winter, Gerhard; and Van Havenbergh, Jan, 5,589,048, Cl. 204-489,000.
- Defieuw, Geert; Janssens, Wilhelmus; Uytterhoeven, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, 5,589,317, Cl. 430-203,000.
- Vanmaele, Luc, 5,589,316, Cl. 430-200,000.
- Agrawal, Vishwani D.: See—
Abramovici, Miron; Agrawal, Vishwani D.; Cheng, Kwang-Ting; and Rajan, Krishna B., 5,590,135, Cl. 371-22,100.
- Agrotepe, Inc.: See—
Ferro, Adolph J.; Bestwick, Richard K.; and Brown, Lyle R., 5,589,623, Cl. 800-205,000.
- Ahart, Robert: See—
Ratuste, Florencio; Ahart, Robert; Lang, David J.; and Tsaui, Liang S., 5,589,370, Cl. 264-430,000.
- Ahern, Steven R., to Orbital Engine Company Pty. Limited. Engine management system, 5,588,415, Cl. 123-676,000.
- Ahghar, Massoud: See—
Rendall, John S.; and Ahghar, Massoud, 5,589,023, Cl. 156-245,000.
- Ahlgren, Dexter D.; and Ahlgren, Valerie E. Cork puller for pulling corks from a range of bottle top sizes, 5,588,342, Cl. 81-347,000.
- Ahlgren, Valerie E.: See—
Ahlgren, Dexter D.; and Ahlgren, Valerie E., 5,588,342, Cl. 81-347,000.
- Ahmad, Suhail; Cole, James J.; and Ahmed, Mahboob, to University of Washington. Hemodialysis recirculation measuring method, 5,588,959, Cl. 604-6,000.
- Ahmed, Mahboob: See—
Ahmad, Suhail; Cole, James J.; and Ahmed, Mahboob, 5,588,959, Cl. 604-6,000.
- Ahn, Kun-Young; Park, Kyung-Ho; Nam, Kee-Soo; and Kang, Sang-Won, to Electronics and Telecommunications Research Institute. Method of manufacturing microstructure by the anisotropic etching and bonding of substrates, 5,589,083, Cl. 216-24,000.
- Aihara, Makoto: See—
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Mioriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126,000.
- Aikawa, Satoru, to Tajima Incorporated. Self-crosslinking composition, forming obtained from the composition, and method for manufacturing the forming, 5,589,533, Cl. 524-529,000.
- Air Packaging Technologies, Inc.: See—
Pharo, Daniel A., 5,588,532, Cl. 206-522,000.
- Air Products And Chemicals, Inc.: See—
Daugherty, Tamara L.; and Harris, Christopher F., 5,588,308, Cl. 62-622,000.
- Varghese, Alexander P., 5,589,020, Cl. 156-185,000.
- Aircast, Inc.: See—
Johnson, Glenn W., Jr.; McVicker, Henry J.; and Hargrave, David C., 5,588,955, Cl. 601-152,000.
- Aisin AW Co., Ltd.: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kargawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128,000.
- Aisin Seiki Kabushiki Kaisha: See—
Iwasaki, Shinichiro; Sugiyama, Masanori; Umemura, Chiaki; Oikawa, Akemi; and Takahashi, Hisayoshi, 5,589,752, Cl. 318-701,000.
- Akagawa, Minoru, to Intelmate Corporation. Apparatus for sequentially delivering articles contained in cassettes, 5,588,791, Cl. 414-331,000.
- Akagiri, Kenzo: See—
Mitsuno, Makoto; Akagiri, Kenzo; Suzuki, Hiroshi; and Shimoyoshi, Osamu, 5,590,108, Cl. 369-59,000.
- Akai, Toshio: See—
Yoshida, Toshio; and Akai, Toshio, 5,588,531, Cl. 206-454,000.
- Akanatsu, Osamu, to NABCO Ltd. Mechanism for the attachment of a speed sensor to a train wheel including a bearing and a connection link with a shock absorbing bushing, 5,589,767, Cl. 324-173,000.
- Akaogi, Takao; Yoshida, Masanobu; Ogawa, Yasushige; Kasa, Yasushi; and Kawamura, Shouichi, to Fujitsu Limited. Nonvolatile semiconductor memory, 5,590,074, Cl. 365-185,220.
- Akashi, Ryojiro; Morikawa, Takashi; Ninomiya, Masanobu; and Uematsu, Takashi, to Fuji Xerox Co., Ltd. Reversible display medium, 5,589,237, Cl. 428-1,000.
- Akiba, Masaru; and Tsurufuji, Tomoyoshi, to Daiwa Seiko, Inc. Fishing rod with a pre-inserted fishing line guide member, 5,588,244, Cl. 43-24,000.
- Akiba, Shigeyuki: See—
Taga, Hidenori; Edagawa, Noboru; Takeda, Noriyuki; Yamamoto, Shu; and Akiba, Shigeyuki, 5,589,969, Cl. 359-124,000.
- Akimoto, Yoshiaki; Tanaka, Hideo; Ogi, Hiromi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, to Mitsubishi Denki Kabushiki Kaisha. Neural network system with sampling data, 5,590,243, Cl. 395-23,000.
- Akita, Mamoru: See—
Shintizume, Kazutoshi; and Akita, Mamoru, 5,590,106, Cl. 369-50,000.
- Akui, Nobuaki: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
- Akzo Nobel N.V.: See—
Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., 5,589,534, Cl. 524-548,000.
- Alabama Power Company: See—
Hendrix, Charles F., 5,588,982, Cl. 75-10,500.
- Albany Molecular Research, Inc.: See—
D'Ambr, Thomas E., 5,589,487, Cl. 514-317,000.
- Albayrak, Sener: See—
Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Ertugrul; König, Theo; and Fister, Dietmar, 5,590,387, Cl. 419-36,000.
- Alber, Friedrich; Dedelmahr, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, to Siemens Aktiengesellschaft. Process for producing a cast resin coil, 5,588,201, Cl. 29-605,000.
- Albert Einstein College of Medicine of Yeshiva University, a Division of Yeshiva University: See—
Dannenberg, Andrew J.; and Chowdhury, Jayanta R., 5,589,504, Cl. 514-456,000.
- Alberth, William P., Jr.; Janssen, John J.; and Klomdsdorf, Armin, to Motorola, Inc. Method and apparatus for increasing amplifier efficiency, 5,589,796, Cl. 330-133,000.
- Alcan International Limited: See—
Jin, Ilhoon; Lloyd, David J.; Timsit, Roland S.; and Lees, Eric R., 5,588,478, Cl. 164-480,000.
- Alcan-Tech Co., Inc.: See—
Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, 5,589,001, Cl. 118-722,000.
- Alcatel Cable: See—
Carratt, Michel; and de Vecchis, Michel, 5,590,233, Cl. 385-100,000.
- Alcatel Cable Interface: See—
Maurice, Denis, 5,588,859, Cl. 439-290,000.
- Alcatel Mobile Communication France: See—
Balbinot, Jean-Pierre, 5,590,273, Cl. 395-182,010.
- Alcatel N.V.: See—
Nederlof, Leo, 5,590,118, Cl. 370-218,000.
- Alco Industries, Inc.: See—
Goetz, Charles R., 5,588,541, Cl. 211-188,000.
- Alcoa Fujikura Limited: See—
Hein, David A., 5,590,011, Cl. 361-106,000.
- Alcon Laboratories, Inc.: See—
Robertson, Stella M.; and Kunkle, Herman M., Jr., 5,589,184, Cl. 424-427,000.
- Robertson, Stella M.; and Kunkle, Herman M., Jr., 5,589,185, Cl. 424-427,000.
- Zaleski, Richard L., II, 5,588,815, Cl. 417-477,200.
- Aldrich, William L., III: See—
Downs, Robert C.; Mainquist, James K.; Nitz, Larry T.; and Aldrich, William L., III, 5,588,327, Cl. 74-335,000.
- Aleshire, Rex A.: See—
Collins, Donald A., Jr.; and Aleshire, Rex A., 5,588,621, Cl. 248-27,100.
- Alexander, Albert H. D.; Ballantine, W. Thomas; Lakey, Leland D.; and Lyon, Frank L., to Newpark Resources, Inc. Method and apparatus for the injection disposal of solid and liquid waste materials from the drilling and production of oil and gas wells, 5,589,603, Cl. 588-250,000.
- Alexandres, Richard B.: See—
Hughett, Elmer; and Alexandres, Richard B., 5,588,970, Cl. 29-623,200.
- Alfa-Laval Food Engineering AB: See—
Palm, Bengt, 5,589,214, Cl. 426-506,000.
- Alford, George W.: See—
Cullimore, D. Roy; and Alford, George W., 5,589,353, Cl. 435-34,000.
- Ali, Mahfaza B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G., to Minnesota Mining and Manufacturing Company. Ink receptive sheet, 5,589,269, Cl. 428-411,100.
- Alko Group Ltd.: See—
Peltonen, Soili; and Harju, Kai, 5,589,577, Cl. 536-221,000.
- All Rite Products, Inc.: See—
Hancock, Dennis H., 5,588,340, Cl. 76-82,000.
- All Seas Group S.A.: See—

- Wolbers, Dick R.; and Koerse, Ronkers, 5,588,780, Cl. 405-170,000.
- Allard, David J.: See—
Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie E.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828,000.
- Allegheny Ludlum Corporation: See—
Snyder, Ralph E.; Sorace, Dominic A.; and Benford, James G., 5,588,321, Cl. 72-366,200.
- Allen, Bruce S.: See—
Blumberg, Barry B.; Pecka, James M.; and Allen, Bruce S., 5,588,649, Cl. 463-18,000.
- Allen, Dana R.: See—
Fast, Bruce B.; and Allen, Dana R., 5,590,224, Cl. 382-291,000.
- Allen, George S. Method for providing medical images, 5,590,215, Cl. 382-128,000.
- Allen, Harvey S., II; Berke, E. William; and Erwin, Gary B., to Allen, II, Harvey S.; Berke, E. William; Newgard, Ken; and Vertucci, Nicholas. Remotely controlled dog muzzle, 5,588,398, Cl. 119-822,000.
- Allen, John J., Jr.; and Root, Kevin B., to New York Air Brake Corporation. Independent brake control, 5,590,042, Cl. 364-426,010.
- Allen, Michael J., to Intel Corporation. Input structure for receiving high voltage signals on a low voltage integrated circuit device, 5,589,790, Cl. 327-333,000.
- Allen, Michael P.; Zuk, Robert F.; and Enslar, Lawrence M., to First Medical, Inc. System and method for plasma separation and measurement, 5,589,399, Cl. 436-169,000.
- Allen, William D.; Linggood, Margaret A.; and Porter, Philip, to Unilever Patent Holdings B.V. Probiotic, 5,589,168, Cl. 424-93,400.
- Allergan: See—
Garner, William H.; and Wheeler, Larry A., 5,589,464, Cl. 514-23,000.
- Allergan, Inc.: See—
Cafaro, Daniel P., 5,589,387, Cl. 435-264,000.
- AlliedSignal Europe Services Technique: See—
Kervagoret, Gilbert, 5,588,463, Cl. 137-596,150.
- Le Dent, Gerard, 5,588,508, Cl. 188-73,310.
- AlliedSignal Europe Services Techniques: See—
Gautier, Jean Pierre; Verbo, Ulysse; and Perez Revilla, Miguel, 5,588,346, Cl. 91-369,002.
- Gautier, Jean Pierre; Verbo, Ulysse; and Gebauer, Maurice, 5,588,349, Cl. 92-169,300.
- AlliedSignal, Inc.: See—
Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zaremka, Michael J., 5,588,507, Cl. 188-71,500.
- Minh, Nguyen Q., 5,589,017, Cl. 156-87,000.
- Rapoport, William R.; and Hou, Janpu, 5,589,931, Cl. 356-33,000.
- Allport, Anthony. Finishing tool, 5,588,904, Cl. 451-512,000.
- Alter, Martin J., to Micrel Incorporated. High value gate leakage resistor, 5,589,702, Cl. 257-379,000.
- Altera Corporation: See—
Terrill, Richard S.; and Brelby, Robert R. N., 5,590,305, Cl. 395-430,000.
- Aluminum Company of America: See—
Kelso, John E., 5,590,017, Cl. 361-321,400.
- Alusuisse-Lonza Services AG: See—
Breitler, Hans P.; Sommerer, Klaus; and Roulin, Monique, 5,589,275, Cl. 428-458,000.
- Amako, Jun; Miura, Hirotsuna; and Sonehara, Tomo, to Seiko Epson Corporation. Optical device and optical machining system using the optical device, 5,589,955, Cl. 359-9,000.
- Amano, Akira: See—
Kitamura, Shoji; Shindo, Yoichi; and Amano, Akira, 5,590,144, Cl. 372-36,000.
- Ambion, Inc.: See—
Winkler, Matthew; and Goldrick, Marianna M., 5,589,329, Cl. 435-5,000.
- Ambu International A/S: See—
Martin, Bill, Sr., 5,588,957, Cl. 602-18,000.
- Amedure, Michael E.: See—
Cassel, Scott T.; and Amedure, Michael E., 5,588,680, Cl. 285-3,000.
- Amemiya, Koji; and Inoue, Masahiro, to Canon Kabushiki Kaisha. Image forming apparatus, 5,589,922, Cl. 399-315,000.
- Amerchol Corporation: See—
Hathfield, James C., 5,589,157, Cl. 424-47,000.
- American Cyanamid Company: See—
Ryan, Michael J.; Lotvin, Jason A.; Strathy, Nancy; and Fantini, Susan E., 5,589,385, Cl. 435-258,350.
- American Medical Systems, Inc.: See—
Burton, John H.; and Staehle, Bradford G., 5,588,965, Cl. 604-101,000.
- American Microsystems, Inc.: See—
O'Shaughnessy, Timothy G.; and Brown, David G., 5,589,802, Cl. 331-44,000.
- American Red Cross: See—
Drohan, William N.; Wilkins, Tracy D.; Velander, William H.; and Johnson, John L., 5,589,604, Cl. 800-2,000.
- American Rug Craftsmen, Inc.: See—
Thornton, John; Poxl, Stanton J.; and Doll, Dennis R., 5,589,027, Cl. 156-304,400.
- American Standard Inc.: See—
Hathfield, Jon P.; and Sanborn, Duane F., 5,588,596, Cl. 239-542,000.
- American Wireless Corporation: See—
Deutsch, Brian M.; and Foster, Robert B., Jr., 5,590,410, Cl. 455-76,000.
- Ameron International Corporation: See—
Folkers, Joie L., 5,588,685, Cl. 285-94,000.
- Amersham International plc: See—
Archer, Colin M.; Dilworth, Jonathan R.; Jobanputra, Panna; Latham, Ian A.; and Thompson, Russell M., 5,589,576, Cl. 534-14,000.
- Hampson, Ian N.; Pope, Lynne; and Butler, John, 5,589,339, Cl. 435-6,000.
- Ametek, Specialty Metal Products Division: See—
Reinschagen, John H., 5,590,384, Cl. 419-6,000.
- Amick, Alan: See—
Laidig, Jon; Updike, Dale; and Amick, Alan, 5,588,521, Cl. 198-532,000.
- Amini, Bijan: See—
Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76,000.
- Ammermann, Eberhard: See—
Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275,000.
- Eicken, Karl; Goetz, Norbert; Harreus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela; and Rang, Harald, 5,589,493, Cl. 514-355,000.
- Amoco Corporation: See—
Chappell, Joseph; Saunders, Cour A.; and Wolf, Fred R., 5,589,619, Cl. 800-205,000.
- Kearney, Kevin R.; Collins, Mark L.; Eldredge, John K.; and Morrissey, David V., 5,589,335, Cl. 435-6,000.
- Nubel, Philip O.; and Yokelson, Howard B., 5,589,548, Cl. 525-247,000.
- Yokelson, Howard B.; Nubel, Philip O.; and Behrends, Raymond T., 5,589,543, Cl. 525-131,000.
- An, Hyeon-keon; Shin, Young-ho; and Kim, Suk-ki, to Samsung Electronics Co., Ltd. Noise canceler, 5,590,206, Cl. 381-71,000.
- Analog Devices, Inc.: See—
Brokaw, A. Paul, 5,589,792, Cl. 327-512,000.
- Garavan, Patrick J., 5,589,785, Cl. 327-63,000.
- Gilbert, Barrie, 5,589,791, Cl. 327-359,000.
- Anani, Anaba A.: See—
Zhang, Jinshan; and Anani, Anaba A., 5,589,289, Cl. 429-122,000.
- Anderson, Bradley T., to Wandel & Goltermann Technologies, Inc. Digital data sequence pattern filtering, 5,590,159, Cl. 375-340,000.
- Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., to Borland International, Inc. System and methods for improved spreadsheet interface with user-familiar objects, 5,590,259, Cl. 395-764,000.
- Anderson, David J.; and Stemple, Derek L., to California Institute of Technology. Mammalian neural crest stem cells, 5,589,376, Cl. 435-240,200.
- Anderson, G. Mark: See—
Williams, Jon I.; Pierce, James C.; Anderson, G. Mark; and Kan, Prasad, 5,589,364, Cl. 435-69,700.
- Anderson, Iver E.; Lograsso, Barbara K.; and Terpstra, Robert L., to Iowa State University Research Foundation, Inc. Apparatus for making environmentally stable reactive alloy powders, 5,589,199, Cl. 425-10,000.
- Anderson, Robert J., to CCL Label, Inc. Expanded content label adapted for application to curved surfaces, 5,588,239, Cl. 40-630,000.
- Anderson, Stephen, to Rutgers, The State University of New Jersey. Methods for the prevention or treatment of vascular hemorrhaging and Alzheimer's disease, 5,589,154, Cl. 424-1,410.
- Anderson, Thomas O.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karaparth, to Boeing Company. The Automated floor panel workcell, 5,590,046, Cl. 364-474,130.
- Ando, Hiroshi: See—
Kurahashi, Akira; Ando, Hiroshi; Kanetwa, Toshiyuki; and Hoashi, Yoshiaki, 5,589,930, Cl. 356-5,010.
- Ando, Masahiko: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kargawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128,000.
- Ando, Takayuki: See—
Imai, Keisuke; Kato, Kenichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, 5,588,608, Cl. 242-374,000.
- Andrews, Anthony D., to EMC Corporation. Method for synchronizing reserved areas in a redundant storage array, 5,590,276, Cl. 395-182,040.
- Andrieu, Veronique; Montel, Jean; and Wick, Alexander, to Synthelabo. Sustained-release compositions of alfuzosin hydrochloride, 5,589,190, Cl. 424-462,000.
- Andruik, Donald R.: See—
Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704,000.
- Angus, James S.: See—
Inchymenko, Victor Y.; Howard, J. Richard; Luczynski, Andrew J.; and Angus, James S., 5,588,235, Cl. 40-547,000.
- Anino, Mary J.: See—
Fiechtner, Michael D.; Ramp, John M.; England, Barbara J.; and Anino, Mary J., 5,589,393, Cl. 436-15,000.

- Anshits, Alexandr G.: See—
Pavlov, Vyacheslav F.; Shabanov, Vasily F.; Anshits, Alexandr G., and Bayakin, Sergei G., 5,588,977, Cl. 65-17,400.
- Anthony, John C., to Hubbell Incorporated. Closure cap with gasket for electrical connector housing, 5,588,853, Cl. 439-136,000.
- Aoki, Akio: See—
Shimokoriyama, Makoto; Aoki, Akio; and Kato, Masato, 5,589,946, Cl. 386-47,000.
- Aoki, Akira: See—
Watanabe, Mikio; Aoki, Akira; and Saito, Osamu, 5,590,306, Cl. 395-442,000.
- Aoki, Mikiyuki; and Omura, Kunitiko, to Minolta Camera Kabushiki Kaisha. Image forming apparatus with safety switch and current dissipating controller, 5,589,871, Cl. 347-237,000.
- Aoki, Tomiyoshi: See—
Chokai, Shoichi; Aoki, Tomiyoshi; and Kimura, Kiyoshi, 5,589,477, Cl. 514-256,000.
- Aono, Yasuhisa: See—
Arato, Toshiaki; Aono, Yasuhisa; Tsuruoka, Shigeo; and Komuro, Katsuhiko, 5,589,652, Cl. 75-235,000.
- Aota, Kensaku: See—
Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki, 5,588,555, Cl. 221-197,000.
- Aotani, Noboru: See—
Iwamoto, Kazuya; Aotani, Noboru; Takada, Kazunori; and Kondo, Shigeo, 5,589,296, Cl. 429-191,000.
- Aotsuka, Yasuyuki: See—
Hagiwara, Hideaki; and Aotsuka, Yasuyuki, 5,589,573, Cl. 530-387,200.
- Aoyama, Shouchi, to Matsushita Electric Industrial Co., Ltd. Text generation apparatus, 5,590,258, Cl. 395-793,000.
- Aparici, Antonio N., to Colorobbia Espana, S.A. Fusion heat recovery and combustion gases filtering system with electric power production, 5,588,296, Cl. 60-671,000.
- Apple Computer, Inc.: See—
Saulpaugh, Thomas E.; Bruffey, Bill M.; and Williams, Russell T., 5,590,334, Cl. 395-683,000.
- Apple Computer, Inc.: See—
Gourdol, Arnaud P. J., 5,590,219, Cl. 382-202,000.
- Hollowell, J. Rhoads, II; Benninghaus, James R.; and Hansen, Daniel J., Jr., 5,590,061, Cl. 364-571,030.
- Krein, William T.; Flaig, Charles M.; and Kelly, James D., 5,590,130, Cl. 370-462,000.
- Robins, Nicholas, 5,590,124, Cl. 370-258,000.
- Tchao, Michael C.; and Capps, Stephen P., 5,590,256, Cl. 395-787,000.
- Appliance Development Corp.: See—
Glucksman, Dov Z.; and Weidemann, Karl H., 5,588,353, Cl. 99-348,000.
- Applied Materials, Inc.: See—
Law, Kam; Robertson, Robert; and Feng, Guofu J., 5,589,233, Cl. 427-579,000.
- Su, Yuh-Jia, 5,589,002, Cl. 118-723,000.
- Tepman, Avi; Jinbo, Takeshi; Takahama, Hiroyuki; and Saito, Akihiko, 5,589,224, Cl. 427-248,100.
- Zhao, Jun; Chang, Frank P.; and Dornfest, Charles N., 5,589,003, Cl. 118-728,000.
- Applied Specialties, Inc.: See—
Scheurman, Clarence, III, 5,589,107, Cl. 252-392,000.
- Aquam Company Limited: See—
Medvedev, Igor N.; and Schogenov, Klim A., 5,589,050, Cl. 204-630,000.
- Arab-Sadeghabadi, Akbar: See—
Goldman, Robert P.; Arab-Sadeghabadi, Akbar; and Varni, Anselm E., 5,590,229, Cl. 385-59,000.
- Arai, Fuminori; and Igarashi, Takeshi, to Fuji Photo Film Co., Ltd. Multilayer analysis elements for the determination of total cholesterol, 5,589,347, Cl. 435-11,000.
- Arai, Hitoshi: See—
Koga, Keiji; Arai, Hitoshi; Kagotani, Tsuneo; and Miyaki, Yousuke, 5,589,297, Cl. 429-212,000.
- Arai, Yoshinori, to J. Morita Manufacturing Corporation. Digital panoramic X-ray imaging apparatus, 5,590,167, Cl. 378-38,000.
- Arakawa, Hideki; and Nankiyo, Takashi, to Sony Corporation. Random access memory having flash memory, 5,590,073, Cl. 365-185,080.
- Arakawa, Hiroharu: See—
Kojiri, Katsuhisa; Kondo, Hisao; Arakawa, Hiroharu; Ohkubo, Mitsuru; and Suda, Hiroyuki, 5,589,365, Cl. 435-85,000.
- Arakawa, Satoshi: See—
Otsuka, Kenji; Fukuda, Hideki; and Arakawa, Satoshi, 5,589,148, Cl. 423-240,005.
- Araki, Hitoshi, to Kabushiki Kaisha Toshiba. Electrically erasable programmable non-volatile semiconductor memory device having select gates and small number of contact holes, 5,589,699, Cl. 257-316,000.
- Aramaki, Teruo; and Hamamoto, Magozo, to Nippon Seiko Kabushiki Kaisha. Plastic holder for bearing, 5,590,225, Cl. 384-527,000.
- Arato, Toshiaki; Aono, Yasuhisa; Tsuruoka, Shigeo; and Komuro, Katsuhiko, to Hitachi, Ltd. Ceramic-particle-dispersed metallic member, manufacturing method of same and use of same, 5,589,652, Cl. 75-235,000.
- Arbeiter, Markus; and Weichaupt, Christian, to Fichtel & Sachs AG. Shifter for transmissions on bicycles, 5,588,925, Cl. 474-81,000.
- Archer, Colin M.; Dilworth, Jonathan R.; Johantputra, Panna; Latham, Ian A.; and Thompson, Russell M., to Amersham International plc. Cores for technetium radiopharmaceuticals, 5,589,576, Cl. 534-14,000.
- ARCO Chemical Technology, L.P.: See—
Le-Khac, Bi, 5,589,431, Cl. 502-175,000.
- Mazurek, Harry, 5,589,217, Cl. 426-611,000.
- Ardon, Menachem T., to Lucent Technologies Inc. Single stage telecommunications switch with partitioned processors, 5,590,129, Cl. 370-376,000.
- Argent, Ronald D.; and Bolin, James A., to IMTEC. Process and apparatus for coloring glass, 5,588,978, Cl. 65-29,100.
- Argus International: See—
Costello, Bernard J., 5,588,996, Cl. 118-668,000.
- Arimoto, Kazuhiko: See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53,000.
- Aritake, Hirokazu; Kato, Masayuki; and Nakashima, Masato, to Fujitsu Limited. Stereoscopic display apparatus using cylindrical screen, 5,589,957, Cl. 359-23,000.
- Armano, Frank, Sr. Automobile heat transfer apparatus, 5,588,480, Cl. 165-300,000.
- Armstrong, Brad A. 6 Degrees of freedom controller with capability of tactile feedback, 5,589,828, Cl. 341-20,000.
- Armstrong, William R.: See—
Farison, Brian K.; and Armstrong, William R., 5,588,533, Cl. 206-522,000.
- Arnaud, Gilles L.: See—
Marze, Henri-James R.; Routhieu, Vincent Jean-Luc; Arnaud, Gilles L.; and Arnaud, Rémy E., 5,588,618, Cl. 244-17,190.
- Arnaud, Rémy E.: See—
Marze, Henri-James R.; Routhieu, Vincent Jean-Luc; Arnaud, Gilles L.; and Arnaud, Rémy E., 5,588,618, Cl. 244-17,190.
- Arnold, Charles, Jr.: See—
Derzon, Dora K.; Arnold, Charles, Jr.; and Delnick, Frank M., 5,589,295, Cl. 429-190,000.
- Arnold, Manfred: See—
Braun, Rudiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Aherfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425,600.
- Arnold, Pitt W.: See—
Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., 5,589,843, Cl. 343-820,000.
- Arora, Sandeep, to Cadence Design Systems, Inc. Method and system for user programmable design verification for printed circuit boards and multichip modules, 5,590,049, Cl. 364-489,000.
- Arpac, Erugrul: See—
Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Erugrul; König, Theo; and Fister, Dietmar, 5,590,387, Cl. 419-36,000.
- Arterair Wire Works, Inc.: See—
Finger, Gary E., 5,588,543, Cl. 211-90,000.
- Arthur D. Little, Inc.: See—
Fauteux, Denis G.; Massucco, Arthur A.; Wilkins, Ronnie D.; and Shi, Jie, 5,588,971, Cl. 29-623,500.
- Fauteux, Denis G.; Massucco, Arthur A.; and Wilkins, Ronnie D., 5,589,300, Cl. 429-218,000.
- Asahi Kasei Kogyo Kabushiki Kaisha: See—
Komiya, Kyosuke; Kawakami, Yoshifumi; and Okamoto, Hiroshige, 5,589,564, Cl. 528-196,000.
- Takahashi, Masahiko; and Tabata, Shusaku, 5,589,306, Cl. 430-18,000.
- Asahi Kogyo Kogyo Kabushiki Kaisha: See—
Kanae, Moriyasu; and Matsuo, Hirofumi, 5,589,976, Cl. 359-362,000.
- Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikyo; and Koeda, Takashi, 5,588,950, Cl. 600-178,000.
- Shimizu, Hitoshi, 5,589,906, Cl. 396-505,000.
- Tanaka, Hitoshi, 5,589,987, Cl. 359-701,000.
- Asahi Research Corp.: See—
Sasaki, Yuu; Iwasawa, Junichi; and Yamada, Masahiro, 5,588,732, Cl. 362-10,000.
- Asai, Koichi; Matsumoto, Koso; and Muto, Yasuo, to Fuji Machine Mfg. Co., Ltd. Electronic-component mounting apparatus, 5,588,195, Cl. 29-33,000M.
- Asai, Koichi: See—
Takada, Yukinori; Kuno, Tokiyuki; Muto, Yasuo; and Asai, Koichi, 5,588,614, Cl. 242-538,200.
- Asai, Motoo; and Kato, Ritsuko, to Ilden Co., Ltd. Resin compositions and printed circuit boards using the same, 5,589,250, Cl. 428-209,000.
- Asai, Motoo: See—
Enomoto, Ryo; and Asai, Motoo, 5,589,255, Cl. 428-261,000.
- Asai, Yoshikazu: See—
Toyama, Makoto; and Asai, Yoshikazu, 5,588,515, Cl. 192-4,000.
- Asajima, Mikio: See—
Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo, 5,589,434, Cl. 503-227,000.
- Asakawa, Koji: See—
Uchida, Naoshi; Miura, Masao; Oyama, Jun; Kuboyama, Katsunori; and Asakawa, Koji, 5,589,672, Cl. 218-34,000.
- Asano, Katsuhiko; Sugai, Masaru; Yamaguchi, Hiroyuki; and Umeno, Takaji, to Kabushiki Kaisha Toyota Chuo Kenkyusho. Vibration analysis of the rotating wheel for controlling anti-lock braking operation, 5,588,721, Cl. 303-163,000.
- Asano, Yasuo: See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53,000.

- ASEA Brown Boveri AB: See—
Snell, John-Erik, 5,590,034, Cl. 364-167,010.
- Asea Brown Boveri Inc.: See—
Marshall, Hugh G., 5,588,223, Cl. 34-414,000.
- Asgharzadeh, Ali; and Jamshidi, Mohammad, to University of New Mexico. Fuzzy logic controlled video printer, 5,590,246, Cl. 395-109,000.
- Ashcroft, Robert G.: See—
Coster, Hans G. L.; Ashcroft, Robert G.; and Mahaworasilpa, Tohsak, 5,589,047, Cl. 204-450,000.
- Aslan, Mesut: See—
Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Erugrul; König, Theo; and Fister, Dietmar, 5,590,387, Cl. 419-36,000.
- AST Research, Inc.: See—
Bennett, Brian R., 5,590,299, Cl. 395-405,000.
- Smith, Michael F., 5,590,377, Cl. 395-842,000.
- Asthana, Abhaya; Cravatts, Mark R.; and Krzyzanowski, Paul, to Lucent Technologies Inc. Intelligent memory system for processing variable length I/O instructions, 5,590,370, Cl. 395-800,000.
- Astle, Brian, to Intel Corporation. Decoding variable-length encoded signals, 5,589,829, Cl. 341-67,000.
- Astle, Brian, to Intel Corporation. Post-filtering for decoded video signals, 5,590,064, Cl. 364-715,020.
- Astra Aktiebolag: See—
Hansson, Stig G. V.; and Holmén, Anders, 5,588,838, Cl. 433-173,000.
- Nakanishi, Shigeo; Tomimaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki, 5,589,491, Cl. 514-338,000.
- Asymmetry Corporation: See—
Harding, James A.; and McCormack, Jonathan I., 5,590,322, Cl. 395-604,000.
- AT & T: See—
Liao, Frank Y.; Rule, Antoinette; Frankel, Rise J.; Blicke, Thomas W.; and Bish, Sandra L., 5,590,186, Cl. 379-210,000.
- AT&T Global Information Solutions Company: See—
Collins, Donald A., Jr.; and Aleshire, Rex A., 5,588,621, Cl. 248-27,100.
- Ata, Masafumi; Machida, Masataka; and Watanabe, Haruo, to Sony Corporation. Magnetic substance, 5,589,038, Cl. 204-157,420.
- ATG Cygnat Inc.: See—
Ricco, Gary C.; Shannon, Michael D.; and Wilkins, Tyler R., 5,588,796, Cl. 414-741,000.
- Atkins, Kenneth E.: See—
Rex, Gary C.; and Atkins, Kenneth E., 5,589,538, Cl. 525-28,000.
- Atkinson, Holly G., to Reuters Limited. Method and system for color vision deficiency correction, 5,589,898, Cl. 351-237,000.
- Atkinson, Howard J.: See—
Gurr, Sarah J.; McPherson, Michael J.; Atkinson, Howard J.; and Bowles, Dianna J., 5,589,622, Cl. 800-205,000.
- Atlantek Inc.: See—
Schofield, Harry; Caron, Paul; Field, Gary; and Follett, Paul, 5,589,868, Cl. 347-171,000.
- Atlantic Construction Fabrics, Inc.: See—
Hunter, Ronald A., 5,589,240, Cl. 428-34,100.
- Atlantic Research Corporation: See—
Sides, James R.; Martin, James D.; and Scheffee, Robert S., 5,589,141, Cl. 422-164,000.
- Atlantic Richfield Company: See—
Fletcher, Robert L.; and Ruuska, Gregory V., 5,590,057, Cl. 364-551,010.
- Atlas Copco Aktiebolag: See—
Rinaldo, John M., 5,588,503, Cl. 184-6,400.
- Atsumi, Haruo, to A.C.E. Corporation. Device for removing a needle from a syringe, 5,588,966, Cl. 604-110,000.
- Atsumi, Toru; Kajiyo, Yasuhiro; Furukawa, Yoshiaki; and Matsumura, Naoki, to Nippon Denso Co. Ltd.; and Stanley Electric Co. Ltd. Scanner of a bar code verifier, 5,589,678, Cl. 235-472,000.
- Aubert, Lucien; and Gagnebin Cabanne, Francoise, to L'Oreal. Cosmetic and/or dermatological composition for the treatment of aging, containing ceramides, and the use thereof, 5,589,178, Cl. 424-401,000.
- Audemard, Gilles, to Hospal AG. Apparatus and method for controlling the rotation speed of electric motors, 5,590,237, Cl. 388-832,000.
- Auerbach, Bernhard: See—
Römsch, Jürgen; Auerbach, Bernhard; and Pelzer, Hermann, 5,589,395, Cl. 436-71,000.
- Auffret, René, to France Telecom Etablissement Autonome de Droit Public. Method and device for transmitting and switching packets in an optical network, 5,589,967, Cl. 359-123,000.
- Aura Systems, Inc.: See—
Ji, Jeong B.; and Um, Gregory, 5,589,084, Cl. 216-24,000.
- Ausa International, Inc.: See—
Wiltbank, Milo; and Pursley, James R., 5,589,457, Cl. 514-12,000.
- Ausimont, S.p.A.: See—
Navarrini, Walter; Tortelli, Vito; and Zedda, Alessandro, 5,589,557, Cl. 526-247,000.
- Simeone, Giovanni; Muma, Fabrizio; Locaspi, Angelo; and Tonelli, Claudio, 5,589,552, Cl. 525-440,000.
- Austin, Mark A.: See—
Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114,000.
- Autogenics, Inc.: See—
Lemp, Steven K.; Hudak, Philip J.; and Love, Charles S., 5,588,967, Cl. 606-167,000.
- Autoliv Development AB: See—
Laun, Ulrich, 5,588,612, Cl. 242-383,100.
- Automobiles Citroen: See—
Baillieux, Francois, 5,588,719, Cl. 303-122,040.
- Automobiles Peugeot: See—
Baillieux, Francois, 5,588,719, Cl. 303-122,040.
- Avdel Systems Limited: See—
Dear, Aiden R.; and Higgs, John E., 5,588,495, Cl. 173-170,000.
- Avery Dennison Corporation: See—
Davignon, Paul A., 5,588,575, Cl. 227-67,000.
- AVL Gesellschaft Für Verbrennungskraftmaschinen und Messtechnik m.b.H. Prof.Dr.Dr.h.c. Hans List: See—
Glaser, Josef; and Fomet, Pierre, 5,589,638, Cl. 73-706,000.
- Awa Engineering Co., Ltd.: See—
Kubo, Toyohide, 5,590,115, Cl. 369-290,000.
- Azuma, Yoshihiko: See—
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218,000.
- B&B Partnership: See—
Byrd, Harold N., 5,588,588, Cl. 232-35,000.
- B&S Research, Inc.: See—
Lashmett, Brent J.; Lashmett, Doug C.; Lashmett, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Merideth L., 5,589,004, Cl. 134-10,000.
- Baba, Toshio, to NEC Corporation. Tunnel transistor comprising a semiconductor film between gate and source/drain, 5,589,696, Cl. 257-105,000.
- Baba, Yoshiro: See—
Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagiya, Satoshi; and Baba, Yoshiro, 5,589,421, Cl. 437-225,000.
- Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjolholm, Paul E., to Boeing Company, The. Method and apparatus for measuring distance to a target, 5,589,928, Cl. 356-4,100.
- Babcock & Wilcox Company, The: See—
LaRose, Jeffrey A., 5,588,380, Cl. 110-263,000.
- Bach, Chinh T.: See—
Krstensky, John L.; Nestor, John J., Jr.; Ho, Teresa H.; Vickery, Brian H.; and Bach, Chinh T., 5,589,452, Cl. 514-12,000.
- Bacher, Jean-Pierre: See—
Reinehr, Dieter; Bacher, Jean-Pierre; and Schmitter, André, 5,589,529, Cl. 524-91,000.
- Bachinski, Thomas J.: See—
Scovil, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772,000.
- Backs, Stephen A., to Chem-tainer Industries, Inc. Liquid containment pallet, 5,588,373, Cl. 108-55,300.
- Baehr, Geoffrey G.: See—
Kondratiev, Victor K.; Kouplitchenko, Valery P.; Galitsky, Alexander V.; and Baehr, Geoffrey G., 5,590,413, Cl. 455-86,000.
- Bagasra, Omar; and Pomerantz, Roger J., to Thomas Jefferson University. In situ polymerase chain reaction, 5,589,333, Cl. 435-6,000.
- Bahadur, Brendra; and Wan, Kam H., to Litton Systems (Canada) Limited. Wide viewing-angle dye-doped TN LCD with retardation films, 5,589,965, Cl. 349-165,000.
- Bailey, David C.: See—
Belcher, Donald K.; and Bailey, David C., 5,589,844, Cl. 343-860,000.
- Bailey, Francis V., to Outboard Marine Corporation. Resin transfer molding process, 5,588,392, Cl. 114-357,000.
- Baillargeon, James N.; and Cho, Alfred Y., to Lucent Technologies Inc. Method for supplying phosphorous vapor, 5,588,969, Cl. 23-294,000.
- Baillieu, Christophe: See—
Pages, Etienne; Ropars, Claude; and Baillieu, Christophe, 5,589,389, Cl. 435-306,100.
- Baillieux, Francois, to Automobiles Peugeot; and Automobiles Citroen. Anti-wheel-lock braking system for a motor vehicle, 5,588,719, Cl. 303-122,040.
- Baird, Brian; DeFreez, Richard; and Sun, Yunlong, to Electro Scientific Industries, Inc. Method and apparatus for generating and employing a high density of excited ions in a laser, 5,590,141, Cl. 372-10,000.
- Bakalik, Dennis P.: See—
Shim, Sang-Hea; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo, and Lu, Frank F., 5,589,106, Cl. 252-387,000.
- Baker, Anna L.; and Stralik, Michael, to Boeing Company, The. Superconductive fiberform ceramic composite, 5,589,441, Cl. 505-125,000.
- Baker, Gerald N.; and Maes, Gregory R., to Emerson Electric Co. Refrigeration fan system, 5,588,484, Cl. 165-122,000.
- Baker, Henry G. Garbage collection, tail recursion and first-class continuations in stack-oriented languages, 5,590,332, Cl. 395-705,000.
- Baker Hughes Incorporated: See—
Park, David B.; and Crawley, Michael F., 5,589,079, Cl. 210-784,000.
- Baker, Jerry W.; and Reader, Timothy W., to Kimberly-Clark Corporation. Liquid impervious surgical gown cuff and method for making the same, 5,588,155, Cl. 2-123,000.
- Baker, Richard W.: See—
Mohr, Judy M.; Baker, Richard W.; and Nakaji, Lisa A., 5,589,498, Cl. 514-413,000.
- Bakker, Jacobus M.: See—

Klaproth, Peter; Zandveld, Frederik; Bakker, Jacobus M.; and Van Lee, Gerardus C., 5,590,354, Cl. 395-800.000.

Balbinot, Jean-Pierre, to Alcatel Mobile Communication France. Microcontroller integrated circuit with read only memory containing a generic program. 5,590,273, Cl. 395-182.010.

Balch, Joseph W.: See—

Northrup, M. Allen; Mariella, Raymond P., Jr.; Carrano, Anthony V.; and Balch, Joseph W., 5,589,136, Cl. 422-102.000.

Baldi, Livio, to SGS-Thomson Microelectronics S.r.l. Process for realizing P-channel MOS transistors having a low threshold voltage in semiconductor integrated circuits for analog applications. 5,589,701, Cl. 257-369.000.

Baldwin-Gegenheimer GmbH: See—

Kurz, Hans-Joachim, 5,588,360, Cl. 101-212.000.

Baldwin, Norman C.: See—

Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.

Baldwin, Peter T.: See—

Krajewski, Marjan, Jr.; Chipchak, John C.; Chodorow, David A.; Trostle, Jonathan T.; and Baldwin, Peter T., 5,590,199, Cl. 380-25.000.

Bales, Bruce M.; and Thiel, Stephen M., to Lucent Technologies Inc. Multimedia conference call providing adjustable bandwidth for individual communication terminals. 5,590,127, Cl. 370-260.000.

Balistreri, Anthony M.: See—

Pinkham, Raymond; and Balistreri, Anthony M., 5,590,083, Cl. 365-230.010.

Balistreri, Thomas R. Automatic animal feeder. 5,588,394, Cl. 119-51.110.

Ballard, Elizabeth S.: See—

Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clod R., III, 5,589,630, Cl. 73-23.350.

Ballatine, W. Thomas: See—

Alexander, Albert H. D.; Ballatine, W. Thomas; Lakey, Leland D.; and Lyon, Frank L., 5,589,603, Cl. 588-250.000.

Balmer, Keith: See—

Guttig, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golsion, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moyse, Philip, 5,590,350, Cl. 395-800.000.

Bambeck, Gregory S. Electrophoresis separation gel and a method for preparing an electrophoresis separation gel. 5,589,104, Cl. 252-315.100.

Banfi, Aldo: See—

Sala, Alberto; Banfi, Aldo; Benedini, Francesca; and Cereda, Roberta, 5,589,490, Cl. 514-330.000.

Banta, Lloyd H.: See—

Gildea, David R.; and Banta, Lloyd H., 5,589,835, Cl. 342-357.000.

Banyu Pharmaceutical Co., Ltd.: See—

Kojiri, Katsuhisa; Kondo, Hisao; Arakawa, Hiroharu; Ohkubo, Mitsuru; and Suda, Hiroyuki, 5,589,365, Cl. 435-85.000.

Barber, James J.: See—

Tennent, Howard G.; Barber, James J.; and Hoch, Robert, 5,589,152, Cl. 423-447.300.

Barberich, Timothy J.: See—

Young, James W.; and Barberich, Timothy J., 5,589,511, Cl. 514-646.000.

Bardot, James P. Swim training device. 5,588,891, Cl. 441-115.000.

Bargiel, Douglas A.; Burgoon, Jack L.; and Combs, Michael D., to Clarke Industries, Inc. Dust box emptying device. 5,588,179, Cl. 15-349.000.

Barkan, Edward: See—

Swartz, Jerome; Shepard, Howard M.; Krichever, Mark J.; Metlitsky, Boris; and Barkan, Edward, 5,589,680, Cl. 235-472.000.

Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., to International Business Machines Corporation. Advanced parallel array processor (APAP). 5,590,345, Cl. 395-800.000.

Barmag AG: See—

Korber, Ralf, 5,588,601, Cl. 242-18.0EW.

Barnes, Frank: See—

Yandrofski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., 5,589,845, Cl. 343-909.000.

Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrop, Robert, to LAM Research Corporation. Plasma processor for large workpieces. 5,589,737, Cl. 315-111.210.

Barnes, Renny H. Wall article hanging device. 5,588,629, Cl. 248-475.100.

Barradas, George. Foot bath. 5,588,161, Cl. 4-662.000.

Barreto De Castro, Luiz: See—

De Clercq, Ann; Krebbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205.000.

Barritz, Robert, to Isogon Corporation. Method and apparatus for computer program usage monitoring. 5,590,056, Cl. 364-550.000.

Barry, Camilla: See—

Barry, David; and Barry, Camilla, 5,588,218, Cl. 33-471.000.

Barry, David; and Barry, Camilla. Teaching protractor. 5,588,218, Cl. 33-471.000.

Barry, James J.: See—

Nicholas, Peter M.; Sahatjian, Ronald A.; and Barry, James J., 5,588,962, Cl. 604-52.000.

Barry, Russell P.; and Pellereau, Bernard, to Dow Chemical Company, The. Bioriented blown film. 5,589,561, Cl. 526-348.100.

Bart, Mark, to A W T World Trade, Inc. Quick release and adjustable pallet assembly for textile screen printing machine. 5,588,770, Cl. 403-325.000.

Bartels, Frank: See—

Reinecke, Holger; Unal, Nezir; Peters, Ralf-Peter; Bartels, Frank; and Noker, Fredolin F., 5,588,597, Cl. 239-553.500.

Barthel, Herbert; Daar, Horst; and Schuetz, Hartmut, to Siemens Aktiengesellschaft. Method for detecting addressing errors in an electrical unit. 5,590,278, Cl. 395-185.060.

Bartlett, Robert R.: See—

Nark, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Banshi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.

Bartmann, Ekkehard; and Tarumi, Kazuaki, to Merck Patent Gesellschaft mit beschränkter Haftung. Benzene derivatives, and liquid-crystalline medium. 5,589,102, Cl. 252-299.010.

BASF Aktiengesellschaft: See—

Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera; and Schnappinger, Dirk, 5,589,362, Cl. 435-69.100.

Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275.000.

Eicken, Karl; Goetz, Norbert; Harreus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela; and Rang, Harald, 5,589,493, Cl. 514-355.000.

Fischer, Rolf; Dostalek, Roman; and Marost, Laszlo, 5,589,600, Cl. 585-266.000.

BASF Corporation: See—

Lisa, Rudolph E.; Kilbride, Terence K.; and Jager, Karl-Friedrich, 5,589,438, Cl. 504-236.000.

BASF Lacke + Farben, AG: See—

Ott, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heimann, Ulrich; and Gilbert, John, 5,589,049, Cl. 204-504.000.

Wegner, Egon; Poth, Ulrich; Gross, Lutz-Werner; and Weidemeier, Klaus, 5,589,228, Cl. 427-407.100.

Baskett, Ira E., to Motorola, Inc. Edge die bond semiconductor package. 5,589,703, Cl. 257-419.000.

Bass, John: See—

Bass, Robert; and Bass, John, 5,589,980, Cl. 359-478.000.

Bass, Robert; and Bass, John. Three dimensional optical viewing system. 5,589,980, Cl. 359-478.000.

Bassett, Carol T.: See—

Cousins, Michael; Patrick, Douglas; and Bassett, Carol T., 5,588,220, Cl. 33-768.000.

Bastoli, Catia; Bellotti, Vittorio; Del Tredici, Gianfranco; and Rallis, Angelos, to Novamont S.p.A. Biodegradable foamed articles and process for the preparation thereof. 5,589,518, Cl. 521-55.000.

Bates, Warren A.: See—

Irlbeck, Robert D.; Bates, Warren A.; Dumas, Robert; and Volz, Keith L., 5,588,846, Cl. 439-66.000.

Bath, William R.; and Yemington, Charles R., to Sensus, Inc. Apparatus for excavating soil using a plurality of independently pivotable brushes. 5,588,230, Cl. 37-190.000.

Battistella, Mirco: See—

Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergamin, Mirco; and Canil, Gilberto, 5,588,228, Cl. 36-118.200.

Battlogg, Stefan. Windshield wiper system with electric motor. 5,588,173, Cl. 15-350.300.

Batts, Curtis L. Rotatable paper roll holder. 5,588,615, Cl. 242-598.300.

Baudrillard, Gilles; and Bouju, Christophe P., to Aérospatiale Societe Nationale Industrielle. Automated tapping process for complex parts used for detecting shallow faults. 5,589,635, Cl. 73-600.000.

Bauer, Matthew J., to M. J. Bauer Company, Inc. Apparatus for treatment of water. 5,589,058, Cl. 210-98.000.

Baughman, Robert W.: See—

Wright, Kevin; Rogers, Lloyd W., Jr.; Baughman, Robert W.; and Chapman, David J., 5,588,258, Cl. 49-340.000.

Baum, Burton M., to Ecolab Inc. Low foaming rinse agents comprising ethylene oxide/propylene oxide block copolymer. 5,589,099, Cl. 510-514.000.

Baum, Richard I.; Brent, Glen A.; Gibson, Donald H.; and Lindquist, David B., to International Business Machines Corporation. Database engine predicate evaluator. 5,590,362, Cl. 395-800.000.

Baum, Thomas M.: See—

Jensen, Michael L.; Summers, George D., Jr.; and Baum, Thomas M., 5,588,869, Cl. 439-417.000.

Baxter International, Inc.: See—

Shockley, Ty R.; Martis, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, 5,589,197, Cl. 424-663.000.

Bayakin, Sergei G.: See—

Pavlov, Vyacheslav F.; Shabanov, Vasily F.; Anshits, Alexandr G.; and Bayakin, Sergei G., 5,588,977, Cl. 65-17.400.

Bayer Aktiengesellschaft: See—

Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91.000.

Hain, Rüdiger; and Stenzel, Klaus, 5,589,626, Cl. 800-205.000.

Kindl, Helmut; Hain, Rüdiger; and Reif, Hans-Jörg, 5,589,620, Cl. 800-205.000.

Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jörg; Stenzel, Klaus; and Thomzik, Jürgen, 5,589,621, Cl. 800-205.000.

Mencke, Norbert; Harder, Achim; and Jeschke, Peter, 5,589,503, Cl. 514-450.000.

Bayer Corporation: See—

Ornstein, Leonard, 5,590,218, Cl. 382-157.000.

Bayer, Georg: See—

Lucas, John M.; Schonbek, Arnold; and Bayer, Georg, 5,588,744, Cl. 362-405.000.

Bayley, Gwain; Grob, Matthew S.; Karmi, Gadi; Kimball, Robert H.; and Propach, David S., to Qualcomm Incorporated. Method of invoking and canceling voice or data service from a mobile unit. 5,590,406, Cl. 455-54.200.

Bayona, Manuel: See—

Garcia-Rubio, Luis H.; Bayona, Manuel; Potter, Robert; and Leparo, German, 5,589,932, Cl. 356-39.000.

Beach, Bradley L.; Feeman, James F.; Pearson, Anna M.; and Sun, Jing X., to Lexmark International, Inc. Ink composition. 5,589,522, Cl. 523-160.000.

Beak, Soon-ki, to Samsung Electronics Co., Ltd. Monitor stand assembly. 5,588,625, Cl. 348-371.000.

Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zaremka, Michael J., to AlliedSignal, Inc. Aircraft brake assembly providing additional wearable friction material. 5,588,507, Cl. 188-71.500.

Beasley, Andrew S. Delay insensitive base station-to-handset interface for radio telephone systems. 5,590,173, Cl. 379-58.000.

Becker, Achim; and Zlotos, Michael, to Filterwerk Mann & Hummel GmbH. Method of drying an injection molding tool. 5,588,225, Cl. 34-474.000.

Becker, John C.; Cameron, John D., Jr.; Cameron, William L.; and Sinram, Bryan W. Commingled recyclables recovery and recycling process and related apparatuses. 5,588,598, Cl. 241-19.000.

Becker, Thomas J.: See—

Mott, Philip J.; White, David C.; and Becker, Thomas J., 5,588,926, Cl. 474-212.000.

Becker, Thomas P.; Crass, Matthew M.; Putney, Gordon A.; Niesen, Randy J.; and Iwinski, Dean J., to Snap-on Technologies, Inc. Torque-angle wrench. 5,589,644, Cl. 73-862.230.

Becker, Willi, to Heidelberger Druckmaschinen AG. Method and device for performing operating steps in an adjustment of a printing press. 5,588,363, Cl. 101-230.000.

Beckmann, Ronald L.: See—

Lu, Jian G.; and Beckmann, Ronald L., 5,588,334, Cl. 74-502.600.

Becton Dickinson and Company: See—

Khan, Azhar J.; Hopkins, David P.; and Khan, Mohammad A., 5,589,120, Cl. 264-130.000.

Bedi, Ram D.; and van der Griendt, Adrianus J., to K. J. Manufacturing Co. Quick connect nipple having a cylindrical magnet. 5,588,502, Cl. 184-1.500.

Beer, Richard: See—

Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrop, Robert, 5,589,737, Cl. 315-111.210.

Beeson and Sons Limited: See—

King, Roger M., 5,588,545, Cl. 215-216.000.

Beeson, Robert R., to Hewlett-Packard Company. Inkjet page-wide-array printhead cleaning method and apparatus. 5,589,865, Cl. 347-28.000.

Behan, Kevin, to CatsClaw Limited. Apparatus for arresting the progress of vehicles. 5,588,774, Cl. 404-6.000.

Behrends, Raymond T.: See—

Yokelson, Howard B.; Nubel, Philip O.; and Behrends, Raymond T., 5,589,543, Cl. 525-131.000.

Behringwerke Aktiengesellschaft: See—

Römis, Jürgen; Auerbach, Bernhard; and Pelzer, Hermann, 5,589,395, Cl. 436-71.000.

Beiersdorf-Jobst, Inc.: See—

Ribando, Philip P.; Bolam, Kenneth M.; Peeler, Donald H.; and Sandman, Terry L., 5,588,954, Cl. 601-149.000.

Bein, Thomas: See—

Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Möller, Karin, 5,589,396, Cl. 436-73.000.

Beinert, Zohar: See—

Spector, Yechiel; Jacobson, Esther; Naishut, Vida; Vittenberg, Michael; and Beinert, Zohar, 5,588,493, Cl. 169-46.000.

Belcher, Donald K.; and Bailey, David C., to Flash Comm, Inc. Automatic antenna tuner for low-cost mobile radio. 5,589,844, Cl. 343-860.000.

Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., to Rubbermaid Incorporated. Plastic dish drainer having integral cup area. 5,588,539, Cl. 211-41.000.

Belk, John H.: See—

Johnson, Bartley C.; and Belk, John H., 5,589,641, Cl. 73-800.000.

Bell, Alan G.: See—

Lyles, Joseph B.; and Bell, Alan G., 5,590,123, Cl. 370-397.000.

Bell, John A.: See—

Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sijthoff, Paul F., 5,589,928, Cl. 356-4.100.

Bell, Stephen E.: See—

Stillman, Bruce W.; Bell, Stephen E.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; L. Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.

Bella, Valter; and Pellegrino, Paolo, to Csel: Centro Studi e Laboratori Telecomunicazioni S.p.A. High-speed CMOS driver for optical sources. 5,589,786, Cl. 327-108.000.

Bellotti, Vittorio: See—

Bastoli, Catia; Bellotti, Vittorio; Del Tredici, Gianfranco; and Rallis, Angelos, 5,589,518, Cl. 521-55.000.

BellSouth Corporation: See—

Lucas, John M.; and Malik, Dale, 5,590,171, Cl. 379-33.000.

Beloit Technologies, Inc.: See—

Thompson, Stanley P., 5,588,222, Cl. 34-379.000.

Bemis, Jon L.: See—

Goldston, Mark R.; Bemis, Jon L.; Wickemeyer, Daniel M.; and Potter, David, 5,588,227, Cl. 36-93.000.

Bencsis, Franz; to Bencsis, Franz; and Perycut-Chemie AG. Insect repellent. 5,589,181, Cl. 424-405.000.

Bending Tooling S.R.L.: See—

Passone, Carlo, 5,588,322, Cl. 72-383.000.

Benedict, Dale G.; Wilgus, Frank R.; Fulk, Henry J.; and Gagliardi, William T., to Dow Corning Corporation. Ergonomic dispenser for viscous materials. 5,588,560, Cl. 222-106.000.

Benedini, Francesca: See—

Sala, Alberto; Banfi, Aldo; Benedini, Francesca; and Cereda, Roberta, 5,589,490, Cl. 514-330.000.

Benford, Howard L., to Chrysler Corporation. Four-speed automatic transmission. 5,588,929, Cl. 475-276.000.

Benford, James G.: See—

Snyder, Ralph E.; Sorace, Dominic A.; and Benford, James G., 5,588,321, Cl. 72-366.200.

Beninghaus, James R.: See—

Hollowell, J. Rhoads, II; Beninghaus, James R.; and Hansen, Daniel J., Jr., 5,590,061, Cl. 364-571.030.

Benitez, Willie B., III: See—

Ohmart, Dale V.; Benitez, Willie B., III; Marrero, Deogracias D.; and Mirizzi, Douglas J., 5,589,765, Cl. 324-158.100.

Benjamin, Neil: See—

Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrop, Robert, 5,589,737, Cl. 315-111.210.

Bennett, Brian R., to AST Research, Inc. Multiprocessor system bus protocol for optimized accessing of interleaved storage modules. 5,590,299, Cl. 395-405.000.

Benninger AG: See—

Ulrich, Horst; and Fuhr, Martin, 5,588,194, Cl. 28-194.000.

Ben, Gerhard; Flik, Gottfried; Treutler, Christoph; and Friedrich, Heinz, to Robert Bosch GmbH. Magnetostriuctive transducer. 5,588,466, Cl. 137-831.000.

Ben Zvi, Guy; Nevo, Shlomo; and Berman, Michael, to Palboard Ltd. Method and apparatus for producing plastic products. 5,589,260, Cl. 428-327.000.

Beratan, Howard R.: See—

Summerfelt, Scott R.; and Beratan, Howard R., 5,589,284, Cl. 428-697.000.

Berg Technology, Inc.: See—

Duncan, Paul M., 5,590,028, Cl. 361-737.000.

Townsend, Peter K., 5,588,861, Cl. 439-342.000.

Berg, Todd A.: See—

Scovil, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772.000.

Bergamin, Mirco: See—

Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergamin, Mirco; and Canil, Gilberto, 5,588,228, Cl. 36-118.200.

Bergemont, Albert, to National Semiconductor Corporation. Ultra-high density alternate metal virtual ground ROM. 5,590,068, Cl. 365-63.000.

Bergemont, Albert M.: See—

Iranmanesh, Ali; Pierce, John M.; and Bergemont, Albert M., 5,589,412, Cl. 437-43.000.

Berger, Ernst; Heil, Franz; Schifko, Herbert; and Tecchio, Piero, to ABB Management AG. Metal-encapsulated, gas-insulated switching installation. 5,589,674, Cl. 218-71.000.

Berger, Horst, to MEPLA-Werke Lautenschläger GmbH & Co. KG. Hardware device for the vertical adjustment of drawers. 5,588,729, Cl. 312-334.400.

Berger, H. Stephen; Vela de Casillas, Martha L.; and Cochran, Harry L., to Siemens Rolm Communications Inc. System and method for making electromagnetic measurements using a tiltable transverse electromagnetic cell and a fixed tilt sample holder. 5,589,773, Cl. 324-261.000.

Berger, Josef, to Elin Motoren GmbH. Electric motor with cooling device. 5,589,720, Cl. 310-61.000.

Berger, Roland: See—

Lanotte, Michel; and Berger, Roland, 5,589,345, Cl. 435-7.230.

Bergmann, Ernest E., to Lucent Technologies Inc. Clock recovery extrapolation. 5,590,140, Cl. 371-61.000.

Bergquist Company, The: See—

Green, Mark; and Hartline, Robert B., 5,588,673, Cl. 280-731.000.

Berk, Brian K.: See—

Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zaremka, Michael J., 5,588,507, Cl. 188-71.500.

Berke, E. William: See—

Allen, Harvey S., II; Berke, E. William; and Erwin, Gary B., 5,588,398, Cl. 119-822.000.

- Berke-Jorgensen, Jorgen. Fluid motor driven pump arrangement having motive fluid exhaust into the pump chamber. 5,588,813, Cl. 417-391.000.
- Berkowitz, Brian T. *See*—
Zbikowski, Mark; Berkowitz, Brian T.; and Ferguson, Robert I., 5,590,318, Cl. 395-618.000.
- Berli, Urs, to Mettler-Toledo AG. Weighing apparatus and method using variable key bar means. 5,589,670, Cl. 177-25.130.
- Berman, Michael. *See*—
Ben Zvi, Guy; Nevo, Shlomo; and Berman, Michael, 5,589,260, Cl. 428-327.000.
- Bernstein, Daniel. *See*—
Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498.000.
- Berol Nobel AB. *See*—
Palicka, Jadwiga, 5,589,447, Cl. 510-237.000.
- Berrang, Peter G. *See*—
Ventrado, Brian E.; and Berrang, Peter G., 5,589,684, Cl. 250-225.000.
- Berry, Dana B. *See*—
Hogan, Steven J.; Feltz, Kristi T.; Murdoch, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.
- Bertoldo, Franco; and Dalla Vecchia, Gino, to Sperimento Rimar S.p.A. Profiled cylinder for tusseling and/or drilling machines. 5,588,192, Cl. 26-37.000.
- BERU Ruprecht GmbH & Co. KG. *See*—
Müller, Helmut, 5,589,091, Cl. 219-270.000.
- Bestler, Caitlin B.; Hartley, Harry A., III; and Rabii, Khosro M., to Zenith Electronics Corporation. Countdown system for conditional access module. 5,590,202, Cl. 380-49.000.
- Bestwick, Richard K. *See*—
Ferro, Adolph J.; Bestwick, Richard K.; and Brown, Lyle R., 5,589,623, Cl. 800-205.000.
- Bevilacqua, Eddie. *See*—
Vichnevetskaia, Klara D.; Blake, Terence J.; Bevilacqua, Eddie; and Boyle, Timothy J. B., 5,589,437, Cl. 504-225.000.
- Bhagat, Jai P. *See*—
Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51.200.
- Bhagavan, Nachiparam V.; Petersen, Charles E.; and Mandel, Morton, to University of Hawaii. Nucleic acids encoding a mutant form of human serum albumin involved in familial dysalbuminemic hyperthyroxinemia. 5,589,338, Cl. 435-6.000.
- Bhat, Shailesh. *See*—
Smith, Daniel J.; and Bhat, Shailesh, 5,588,428, Cl. 128-653.100.
- Bhat, Suresh A., to Intel Corporation. Controlled, gas phase process for removal of trace metal contamination and for removal of a semiconductor layer. 5,589,422, Cl. 437-228.000.
- BIIP Steel (JLA) Pty Ltd. *See*—
Leadbeater, Darren J.; Kato, Heiji; and Fukase, Hisahiko, 5,588,479, Cl. 164-480.000.
- Bianchi, Sabatino A.; and Stoyanoff, Richard P., to Livernois Research & Development Company. Method and apparatus for making heat exchanger fins. 5,588,319, Cl. 72-186.000.
- Bianco, James S. Method and apparatus for sequentially unlocking compartments. 5,588,317, Cl. 70-265.000.
- Biard, James R., to Honeywell, Inc. Turbidity sensor with the capability of regulating the intensity of a light source. 5,589,935, Cl. 356-339.000.
- Bick, Werner. *See*—
von Essen, Mathias; Bollig, Christoph; and Bick, Werner, 5,588,407, Cl. 123-192.200.
- Bicz, Wieslaw, to Sonident Anstalt Luechtensteinschen Rechts. Method of and apparatus for the detection of an ultrasonic field. 5,589,636, Cl. 73-617.000.
- Bidefeld, Branko, to Matsushita Communication Industrial Corporation of America. Nozzle for a vacuum mounting head. 5,588,203, Cl. 29-743.000.
- Bielhy, Robert R. N. *See*—
Terrill, Richard S.; and Bielhy, Robert R. N., 5,590,305, Cl. 395-430.000.
- Bier, Helmar. *See*—
Kosy, Adi; Bier, Helmar; and Mehns, Norbert, 5,588,517, Cl. 192-70.250.
- Bigorra-Losas, Joaquim. *See*—
Pi, Raphael; Bigorra-Losas, Joaquim; Ponsati-Obiols, Onofre; and Schmid, Karl, 5,589,450, Cl. 510-535.000.
- Biliris, Alexandros; Dar, Shaul; and Gelani, Naraiah H., to Lucent Technologies Inc. Method for making data objects having hidden pointers persistent. 5,590,327, Cl. 395-670.000.
- Billotti, Joseph D. Method for supporting body joints and brace therefor. 5,588,956, Cl. 602-13.000.
- Bjllstrom, Lars; Wetterberg, Lars; Dahlin, Steinar; and Persson, Bengt, to Telefontekniska AB. Apparatus and mobile stations for providing packet data communication in digital TDMA cellular systems. 5,590,133, Cl. 370-349.000.
- Bio Merieux. *See*—
Mahilat, Claude; and Pecheur, Jean-Claude, 5,589,585, Cl. 536-24.320.
- Bioceca, Peter M., to Abtech Corporation. Radial brush. 5,588,172, Cl. 15-179.000.
- Biochimica Opos SpA. *See*—
Da Col, Marco; Dall'Asta, Leone; and Resta, Irene, 5,589,593, Cl. 540-220.000.
- Biolog, Inc. *See*—
Bochner, Barry, 5,589,350, Cl. 435-29.000.
- Biopure Corporation. *See*—
Wong, Bing L.; Shen, Yong-Qiang; and Chen, Yung-Pin, 5,589,354, Cl. 435-47.000.
- BioQuant, Inc. *See*—
Kanan, Paul G.; Smith, Richard H.; and Rudnick, Ellen, 5,589,346, Cl. 435-7.920.
- Biosource Technologies, Inc. *See*—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Ganger, Stephen J.; and Grill, Laurence K., 5,589,367, Cl. 435-172.300.
- Biosynth s.r.l. *See*—
Porro, Massimo, 5,589,459, Cl. 514-15.000.
- Biotechnology Australia Pty., Ltd. *See*—
Russell-Jones, Gregory J.; Howe, Peter; de Aizpurua, Henry J.; and Burge, Geoffrey L., 5,589,463, Cl. 514-21.000.
- BioTransplant, Inc. *See*—
Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Ronath, Paul D., 5,589,582, Cl. 536-23.500.
- Birck, Freddie C. *See*—
House, Randall H.; Hofmann, Johann H.; and Birck, Freddie C., 5,588,786, Cl. 405-285.000.
- Birenbaum, Andy. *See*—
Intrater, Anios; Birenbaum, Andy; Intrater, Gideon; Carnon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfield, Zvi; Greiss, Israel; Oz, Oved; Atek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.
- Birger Ericson Fasad AB. *See*—
Ericson, Birger, 5,590,238, Cl. 392-412.000.
- Birkhan, Joao A. *See*—
Jennebach, Markus; and Birkhan, Joao A., 5,588,381, Cl. 110-345.000.
- Bish, Sandra L. *See*—
Liao, Frank Y.; Rule, Antoinette; Frankel, Rise J.; Bickle, Thomas W.; and Bish, Sandra L., 5,590,186, Cl. 379-210.000.
- Bishop, Gregory D. *See*—
Conlon, Sean P.; Oureshi, Saleem U.; Hihner, John A.; Okorocho, Livyn O.; and Bishop, Gregory D., 5,588,581, Cl. 227-176.100.
- Bitron S.P.A. *See*—
De Filippis, Pietro; Quarero, Ernesto; and Petrone, Alberto, 5,588,814, Cl. 417-423.700.
- Bivens, Donald B. *See*—
Shillett, Mark B.; and Bivens, Donald B., 5,589,098, Cl. 252-67.000.
- Bixler, Jeffrey C. *See*—
Chencinski, Edward W.; Bixler, Jeffrey C.; and Christensen, Neal T., 5,590,309, Cl. 395-472.000.
- BKS Company. *See*—
Cassel, Scott T.; and Amedure, Michael E., 5,588,680, Cl. 285-3.000.
- Black & Decker, Inc. *See*—
Coulson, Richard R.; D'Amario, Eric; and Moscovitch, Jerry, 5,589,288, Cl. 429-96.000.
- Black, Michael J. *See*—
Davis, David L.; Black, Michael J.; Doll, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112-80.160.
- Blackborow, John R.; and Clarke, Michael J., to BP Chemicals Limited. Fuel compositions containing a polyisobutene succinimide detergent. 5,588,973, Cl. 44-347.000.
- Blackmon, James B.; Drubka, Robert E.; Jones, Nelson E.; Gerrick, R. Andrew; and Hand, Michael L., to McDonnell Douglas Corporation. Modular, hybrid power system. 5,589,758, Cl. 322-100.000.
- Bladt, John P., and Shirodkar, Pradeep P., to Mobil Oil Corporation. Swell reduction of chromium catalyzed HDPE resins by controlled degradation using high temperature peroxides. 5,589,551, Cl. 525-333.800.
- Blake, Larry W., to Pharmacia Iovision, Inc. Fabrication of an intraocular lens. 5,589,024, Cl. 156-245.000.
- Blake, Lawrence S. *See*—
King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Rombult, Philip A.; and Hebert, Thomas K., 5,589,973, Cl. 359-214.000.
- Blake, Terence J. *See*—
Vichnevetskaia, Klara D.; Blake, Terence J.; Bevilacqua, Eddie; and Boyle, Timothy J. B., 5,589,437, Cl. 504-225.000.
- Blanchard, Richard A., to SGS-Thomson Microelectronics, Inc. Method for forming a semiconductor structure with self-aligned contacts. 5,589,415, Cl. 437-57.000.
- Blaner, Bartholomew. *See*—
Phillips, James E.; Blaner, Bartholomew; and Vassiliadis, Stamatis, 5,590,348, Cl. 395-564.000.
- Blauer Manufacturing Co. Inc. *See*—
Blauer, Stephen; and Mordechai, Mark, 5,588,154, Cl. 2-69.000.
- Blauer, Stephen; and Mordechai, Mark, to Blauer Manufacturing Co. Inc. Uniform with optionally concealed/deployed visual panels for display about a 360 degree periphery. 5,588,154, Cl. 2-69.000.
- Bleier, Zvi, to PLX Inc. Optical assembly with folding mirror assembly. 5,589,991, Cl. 359-856.000.
- Blevins, Terry D. Measuring cup with externally-mounted liquid crystal thermometer. 5,588,747, Cl. 374-157.000.
- Blickle, Thomas W. *See*—

- Liao, Frank Y.; Rule, Antoinette; Frankel, Rise J.; Bickle, Thomas W.; and Bish, Sandra L., 5,590,186, Cl. 379-210.000.
- Bliss, Daniel L.; Marshall, Steven E.; and Ruby, Michael L., to Boeing Company. The Motor operated restrictor valve. 5,588,617, Cl. 244-1.00N.
- Block Drug Company Inc. *See*—
Markowitz, Kenneth; and Gelfer, Mikhail Y., 5,589,159, Cl. 424-49.000.
- Block Systems, Inc. *See*—
Woodford, Michael E.; and Sievert, Dick J., 5,589,124, Cl. 264-157.000.
- Bloom, Hanley D., to Colorprinting Specialists, Inc. Method of producing a sign. 5,589,021, Cl. 156-219.000.
- Blumhach, Jürgen. *See*—
Naik, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansi; Blumhach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.
- Blumberg, Barry B.; Pecka, James M.; and Allen, Bruce S., to CompuScan Technologies, Inc. Multi token gaming method. 5,588,649, Cl. 463-18.000.
- Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Siddiman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, to Transaction Technology, Inc. Visually impaired customer activated terminal method and system. 5,589,855, Cl. 345-173.000.
- Board of Regents, The University of Texas. *See*—
Higashijima, Tsutomu; and Ross, Elliott M., 5,589,568, Cl. 530-324.000.
- Board of Regents, The University of Texas System. *See*—
Wilson, Steven E., 5,589,451, Cl. 512-2.000.
- Board of Supervisors of Louisiana State University and Agricultural and Mechanical College. *See*—
Rice, Richard G., 5,589,062, Cl. 210-198.200.
- Board of Trustees operating Michigan State University. *See*—
Breznak, John A.; Emerson, David; and Koh, John K., 5,589,352, Cl. 435-34.000.
- Boart Longyear Company. *See*—
Holmes, William K.; Jonekis, Albert E.; and Wong, Kwok W., 5,588,418, Cl. 125-13.010.
- Bochner, Barry, to Biolog, Inc. Testing device for liquid and liquid suspended samples. 5,589,350, Cl. 435-29.000.
- Bockman, Jeffrey M. *See*—
Shih, Andy; Bockman, Jeffrey M.; and George, Shaji T., 5,589,332, Cl. 435-6.000.
- Bod, Peter. *See*—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szpomy, Laszlo; Kiss, Bela; Karpatti, Egon; Palosi, Eva; Szombathelyi, Zolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Bodford, Carl A.; Chester, Stephen O.; and Nayak, Rahul K., to Poly-Bond, Inc. Medical composite with discontinuous adhesive structure. 5,589,249, Cl. 428-200.000.
- Bodo, Mihaly. *See*—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szpomy, Laszlo; Kiss, Bela; Karpatti, Egon; Palosi, Eva; Szombathelyi, Zolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Boehringer Ingelheim International GmbH. *See*—
Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogys, Ingrid; Wiehe-Castanon, Maria J.; Stratowa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189.000.
- Boehringer Mannheim Corporation. *See*—
Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wiley, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.
- Boehringer Mannheim GmbH. *See*—
Krause, Manfred; Kaufmann, Norbert; and Neumann, Mathias, 5,589,398, Cl. 436-164.000.
- Boeing Company, The. *See*—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474.130.
- Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4.100.
- Baker, Anna L.; and Stravik, Michael, 5,589,441, Cl. 505-125.000.
- Bliss, Daniel L.; Marshall, Steven E.; and Ruby, Michael L., 5,588,617, Cl. 244-1.00N.
- Hoopingarner, Neil L.; and Matin, Barry D., 5,589,016, Cl. 156-87.000.
- Jones, Darrell D., 5,588,554, Cl. 221-88.000.
- Morant, David G., 5,589,776, Cl. 324-534.000.
- Boes, Chad W. *See*—
Boes, James A.; Boes, Chad W.; and Boes, Douglas W., 5,588,659, Cl. 280-47.190.
- Boes, Douglas W. *See*—
Boes, James A.; Boes, Chad W.; and Boes, Douglas W., 5,588,659, Cl. 280-47.190.
- Boes, James A.; Boes, Chad W.; and Boes, Douglas W., to Triple B Trenching, Inc. Tool cart. 5,588,659, Cl. 280-47.190.
- Bogardy, Lawrence S. Hot melt glue based on modified waterbearing gels. 5,589,528, Cl. 524-17.000.
- Bogatin, Jacob G.; and Podosyma, Vladimir, to YBM Magnetics, Inc. Magnetohydrodynamic device. 5,589,065, Cl. 210-222.000.
- Böhnlein-Maass, Jutta. *See*—
Menke, Klaus; Böhnlein-Maass, Jutta; Schmid, Helmut; Bucerius, Klaus M.; and Engel, Walther, 5,589,661, Cl. 149-19.400.
- Boilard, Reno C., to Medar, Inc. Method of regulating DC current in resistance welders. 5,589,088, Cl. 219-110.000.
- Boisture, Thomas B., to C.H. Heist Corp. Safety apparatus for high pressure liquid jet system. 5,588,593, Cl. 239-67.000.
- Bolam, Kenneth M. *See*—
Ribando, Philip P.; Bolam, Kenneth M.; Peeler, Donald H.; and Sandman, Terry L., 5,588,954, Cl. 601-149.000.
- Bolan, Michael L.; and Little, Wendell L., to Dallas Semiconductor Corporation. Touch-sensitive switching circuitry for power-up. 5,590,343, Cl. 395-750.000.
- Bolin, James A. *See*—
Argent, Ronald D.; and Bolin, James A., 5,588,978, Cl. 65-29.100.
- Bollig, Christoph. *See*—
von Essen, Mathias; Bollig, Christoph; and Bick, Werner, 5,588,407, Cl. 123-192.200.
- Bollon, Arthur P. *See*—
Torczynski, Richard M.; and Bollon, Arthur P., 5,589,579, Cl. 536-23.100.
- Bolsworth, James; and Adamson, Robert E., Jr., to General Motors Corporation. Folding seat. 5,588,707, Cl. 297-378.120.
- Bolza-Schünemann, Claus A., to Koenig & Bauer Aktiengesellschaft. Print unit damage prevention assembly. 5,588,364, Cl. 101-247.000.
- Bonebrake, Randall A. *See*—
Rank, David B.; Bonebrake, Randall A.; and Stoner, Spurgeon C., 5,588,216, Cl. 33-286.000.
- Bontrager, Paul R. *See*—
Holubek, Kevin J.; Keniuk, Richard J.; and Bontrager, Paul R., 5,590,418, Cl. 455-126.000.
- Boodley, James W.; Noe, James P.; and Hann, Daniel, to Smithers-Oasis Company. Method and apparatus for displaying floral arrangements. 5,588,253, Cl. 47-41.120.
- Boon-Falleur, Thierry. *See*—
Coulie, Pierre; and Boon-Falleur, Thierry, 5,589,334, Cl. 435-6.000.
- Booster Pac International Corporation. *See*—
Ruzon, Luc, 5,589,292, Cl. 429-170.000.
- Bordeau, Kenneth J. *See*—
Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37.300.
- Borell, Michael. *See*—
Rundle, Christopher; and Borell, Michael, 5,588,538, Cl. 211-23.000.
- Rundle, Christopher; and Borell, Michael, 5,588,663, Cl. 280-304.100.
- Rundle, Christopher; and Borell, Michael, 5,588,699, Cl. 297-216.110.
- Borg-Warner Automotive, Inc. *See*—
Mott, Philip J.; White, David C.; and Becker, Thomas J., 5,588,926, Cl. 474-212.000.
- Warren, James D.; Vogt, Carl R.; and Klooz, Charles D., 5,590,026, Cl. 361-704.000.
- Borgato, Pierandrea; Diazzi, Claudio; and Pidutti, Albino, to SGS-Thomson Microelectronics S.r.l. Circuit for detecting voltage variations in relation to a set value, for devices comprising error amplifiers. 5,589,759, Cl. 323-222.000.
- Boriani, Silvano; and Gamberini, Antonio, to G.D. Societa' Per Azioni. Method of producing cartons of cigarettes with a rigid hinged-lid wrapping. 5,588,281, Cl. 53-443.000.
- Borland International, Inc. *See*—
Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., 5,590,259, Cl. 395-764.000.
- Born, Ray W. Aircraft maintenance elevator system. 5,588,506, Cl. 187-209.000.
- Bosch-Siemens Hausgerate GmbH. *See*—
Hildebrand, Gerald, 5,588,313, Cl. 68-17.000.
- Bossart, Erwin, to Buchi Laboratoriums - Technik AG. Height adjustable stand for laboratory equipment. 5,589,135, Cl. 422-99.000.
- Boston Scientific Corporation. *See*—
Crowley, Robert J., 5,588,432, Cl. 128-660.030.
- Nicholas, Peter M.; Sahatjian, Ronald A.; and Barry, James J., 5,588,962, Cl. 604-52.000.
- Boteler, William C.; and Klein, Lawrence J., to Hubbell Incorporated. Electrical cord clamp. 5,588,870, Cl. 439-467.000.
- Boucherie, Leonel P., to Firma G. B. Boucherie, naamloze vennootschap. Method for manufacturing brushes. 5,588,714, Cl. 300-21.000.
- Bouju, Christophe P. *See*—
Baudrillard, Gilles; and Bouju, Christophe P., 5,589,635, Cl. 73-600.000.
- Boumarafi, Mohamed; Hurford, Jonathan P.; Collier, William V.; and Lichlyter, Ralph, to Takata, Inc. Resealable tear seam for seat deployed side impact air bag. 5,588,671, Cl. 280-730.200.
- Boumarafi, Mohamed. *See*—
Karlou, James P.; Boumarafi, Mohamed; and Hurford, Jonathan P., 5,588,672, Cl. 280-730.200.
- Bour, Daniel L. *See*—

- Vijn, Jan P.; Nenakis, Zacharias; Bour, Daniel L.; and Childs, Jerry D., 5,588,488, Cl. 166-293,000.
- Bourgeois, Philip: See—
Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stollenberg, Blaise G., 5,590,209, Cl. 381-168,000.
- Boussouira, Boudiaf; and Nguyen, Quang L., to L'oreal. Composition containing a non-photocatalytic metal oxide and tocopherol, its use in the cosmetics and/or dermatological field and processes employing it, 5,589,179, Cl. 424-401,000.
- Boutaghou, Zine Eddine, to International Business Machines Corporation. Resilient clamp and compliant element data disk support system, 5,590,004, Cl. 360-99,120.
- Bouvier, Daniel: See—
Hernandez, Gilberto; Smith, Russell C.; and Bouvier, Daniel, 5,590,023, Cl. 361-683,000.
- Bova, Frank J.; and Friedman, William A., to University of Florida Research Foundation, Inc. Repeat fixation for frameless stereotactic procedure, 5,588,430, Cl. 128-653,100.
- Bowell, Richard A., Sr., to Freudenberg-NOK General Partnership. Manufacture of banded pistons, 5,588,994, Cl. 92-192,000.
- Bowles, Dianna J.: See—
Gurr, Sarah J.; McPherson, Michael J.; Atkinson, Howard J., and Bowles, Dianna J., 5,589,622, Cl. 800-205,000.
- Bowman, Wayne C.; and Niemela, Van A., to Lucent Technologies Inc. Self-synchronized drive circuit for a synchronous rectifier in a clamped-mode power converter, 5,590,032, Cl. 363-15,000.
- Boyle, Timothy J. B.: See—
Vichnevetskaia, Klara D.; Blake, Terence J.; Bevilacqua, Eddie; and Boyle, Timothy J. B., 5,589,437, Cl. 504-225,000.
- Bozler, Carl O.; Fan, John C. C.; and McClelland, Robert W., to Massachusetts Institute of Technology. Method of producing sheets of crystalline material and devices made therefrom, 5,588,994, Cl. 117-89,000.
- BP Chemicals Limited: See—
Blackborow, John R.; and Clarke, Michael J., 5,588,973, Cl. 44-347,000.
- Leahy, Richard; and Cook, Stephen J., 5,589,445, Cl. 508-381,000.
- Braibon, William N.; and Malone, Philip G., to United States of America, Army. Soil reinforcement with adhesive-coated fibers, 5,588,783, Cl. 405-258,000.
- Bracken, Allen T.; and Rich, Edward L., to Iomega Corporation. Compliant actuator for securing disk drive actuator bearing, 5,590,002, Cl. 360-97,020.
- Braly, Joseph M., to PGA Tour. Golf ball striking device, 5,589,628, Cl. 73-12,020.
- Brambilla, Massimiliano, to SGS-Thomson Microelectronics, Inc. Slew rate control circuit for a lowside driver of a DC motor, 5,589,744, Cl. 318-254,000.
- Brandt, Ernest D.; and Weatherby, David E., to Schnabel Foundation Company. Soil or rock nail wall with outer face and method of constructing the same, 5,588,784, Cl. 405-262,000.
- Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Keny D., to Nuclear Fuel Services, Inc. Down-blending of fissionable material, 5,590,391, Cl. 423-253,000.
- Brandt, Lorelei: See—
Neill, Paul; Brandt, Lorelei; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, 5,589,163, Cl. 424-70,510.
- Brandt, Thomas J.; and Zimmerman, Stephen A., to Tektronix, Inc. Systems and methods for thermal transfer printing, 5,589,869, Cl. 347-212,000.
- Brankley, Jacob R. Adjustable baby bottle neck, 5,588,548, Cl. 215-388,000.
- Brassier, Marc; Gasquet, Jean-Claude; Segaud, Daniel; and Mauray, Bernard, to Valeo Vision. Motor vehicle lighting/indicating apparatus using luminescent discharge, 5,589,730, Cl. 313-493,000.
- Braun, Eugene R.; and Olson, Otis J., to Eaton Corporation. Synchronizer with self-energizing, 5,588,516, Cl. 192-48,910.
- Braun, Peter: See—
Ulbrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205,000.
- Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, to Donier GmbH. Glazing, 5,589,272, Cl. 428-425,000.
- Brazilian Agricultural Research Organization-Embrapa/Cenargen: See—
De Clercq, Ann; Krehbers, Enno; Vandekerckhove, Joël; Baneto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205,000.
- Breeze, Dean E., to Schwler Manufacturing Company Inc. Electrically insulating gas line system, 5,588,682, Cl. 285-52,000.
- Bretler, Hans P.; Sommerer, Klaus; and Roulin, Monique, to Alusuisse-Lonza Services AG. Composite material, 5,589,275, Cl. 428-458,000.
- Bremer, Ralf: See—
Gerstel, Eberhard; and Bremer, Ralf, 5,588,988, Cl. 96-101,000.
- Brenco, Incorporated: See—
Fetty, Mark W. K., 5,588,752, Cl. 384-477,000.
- Brent, Glen A.: See—
Baum, Richard L.; Brent, Glen A.; Gibson, Donald H.; and Lindquist, David B., 5,590,362, Cl. 395-800,000.
- Bretschneider, Thomas: See—
Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wabendorff-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91,000.
- Brenthauer, Hans-Jürgen: See—
Focke, Heinz; and Brenthauer, Hans-Jürgen, 5,588,286, Cl. 53-575,000.
- Bretting, Claus Aage S.: See—
Hansen, Kai; and Bretting, Claus Aage S., 5,589,471, Cl. 514-167,000.
- Breznak, John A.; Emerson, David; and Koh, John K., to Board of Trustees operating Michigan State University; and Koh Development, Inc. Diffusion gradient chamber system, 5,589,352, Cl. 435-34,000.
- Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., to Zeneca Limited. Plant-derived glutathione-S-transferase isoform II promoter, 5,589,614, Cl. 800-205,000.
- Bridgestone/Firestone, Inc.: See—
Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Niaux, William S.; and McKinley, Gareth H., 5,588,509, Cl. 188-267,000.
- Briggs, Steven P.; and Johal, Gurmukh S., to Pioneer Hi-Bred International, Inc. Disease resistance gene from maize and its use for disease resistance as a selectable marker and as a gene identification probe, 5,589,611, Cl. 800-205,000.
- Bright, Simon W. J.: See—
Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., 5,589,614, Cl. 800-205,000.
- Brightbill, Keith E.: See—
Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., 5,588,539, Cl. 211-41,000.
- Brininstool, Michael R., to United States of America, Navy. Fiber optic self-multiplexing amplified ring transducer and force transfer sensor with pressure compensation, 5,589,937, Cl. 356-352,000.
- Brinker, C. Jeffrey: See—
Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Moller, Karin, 5,589,396, Cl. 436-73,000.
- Brinker, Gerald; Hladik, Peter; and Gutwillig, Alan, to Distek, Inc. Dissolution testing apparatus, 5,589,649, Cl. 73-866,000.
- Brisebois, Michel J.: See—
Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J., 5,590,189, Cl. 379-356,000.
- Bristol Compressors, Inc.: See—
DiFlora, Michael A.; Pandeya, Prakash N.; Robinson, Christopher S.; and Wagner, Philip C., 5,588,810, Cl. 417-312,000.
- Hill, Joe T.; Fields, Gene M.; and Williams, John R., 5,588,820, Cl. 418-55,400.
- Bristol-Myers Squibb Company: See—
Martinez, Sarah B.; Leary, H. Lee, Jr.; and Nichols, Debra J., 5,589,357, Cl. 435-68,100.
- British Gas plc: See—
Sutton, David M., 5,589,627, Cl. 73-1,000.
- British Technology Group Limited: See—
Byrne, Phillip O.; and Essex, Timothy J. H., 5,588,437, Cl. 128-691,000.
- Edwards, Karen J.; Jarman, Michael; Loughton, Charles A.; Neidle, Stephen; and Harcastle, Ian R., 5,589,500, Cl. 514-428,000.
- British Telecommunications public limited company: See—
Shan, Xuekang, 5,590,142, Cl. 372-18,000.
- Britt, Wayne A.: See—
Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498,000.
- Britton, Charles L., to Martin Marietta Energy Systems, Inc. Method of pedestal and common mode noise correction for switched-capacitor analog memories, 5,590,104, Cl. 365-45,000.
- Broadrick, Garth W.: See—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramchandran, Karapurath, 5,590,146, Cl. 364-474,130.
- Broden, Reiner: See—
Lysson, Hans-Jürgen; Broden, Reiner; and Leppert, Hans-Dietlef, 5,588,997, Cl. 118-405,000.
- Brokaw, A. Paul, to Analog Devices, Inc. Resistor programmable temperature switch, 5,589,792, Cl. 327-512,000.
- Brook, Mark G.: See—
Tellam, Mark E.; Brook, Mark G.; Haded, Kevin J.; and Wheeler, Joseph A., 5,589,972, Cl. 359-196,000.
- Brooks Automation: See—
Muka, Richard S.; and Hofmeister, Christopher A., 5,588,789, Cl. 414-217,000.
- Brooks Automation Inc.: See—
Muka, Richard S., 5,588,827, Cl. 432-5,000.
- Brooks, Louie J. Device and method for lowering a dump truck bed according to the transmission state of the vehicle, 5,588,712, Cl. 298-22,000.
- Brother Kogyo Kabushiki Kaisha: See—
Nishimura, Osamu; and Nishikawa, Hiroshi, 5,588,842, Cl. 434-307,000.
- Brotz, Gregory R. Tri-strip memory metal actuator, 5,588,295, Cl. 60-528,000.
- Brown, Dale M.; and Michon, Gerald J., to General Electric Company. Photocurrent detector circuit with high sensitivity, fast response time, and large dynamic range, 5,589,682, Cl. 250-214,000.
- Brown, David G.: See—
O'Shaughnessy, Timothy G.; and Brown, David G., 5,589,802, Cl. 331-44,000.
- Brown, David L.: See—
Eldridge, Robert A.; Unrein, Ed J.; Brown, David L.; and Noble, Scott L., 5,588,728, Cl. 312-332,100.

- Brown, Glen W.: See—
Linz, Alfredo R.; Cabler, Carlin D.; Brown, Glen W.; and Soques, Martin P., 5,589,830, Cl. 341-110,000.
- Brown, Lyle R.: See—
Ferro, Adolph J.; Bestwick, Richard K.; and Brown, Lyle R., 5,589,623, Cl. 800-205,000.
- Brown, Stephen J.: See—
Zboril, Vaclav G.; and Brown, Stephen J., 5,589,555, Cl. 526-64,000.
- Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., to Whitaker Corporation, The. Arrangement for securing a door to an enclosure, 5,588,182, Cl. 16-268,000.
- Brück, Rolf: See—
Maus, Wolfgang; Brück, Rolf; and Swars, Helmut, 5,588,291, Cl. 60-274,000.
- Bruckert, Eugene J.: See—
Vilmur, Richard J.; and Bruckert, Eugene J., 5,590,177, Cl. 379-60,000.
- Brucks, Richard M.: See—
Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401,000.
- Bruening, George: See—
Kridl, Jean C.; Bruening, George; and Knauf, Vic C., 5,589,379, Cl. 435-240,400.
- Bruffey, Bill M.: See—
Saulpaugh, Thomas E.; Bruffey, Bill M.; and Williams, Russell T., 5,590,334, Cl. 395-683,000.
- Brugman, James D.; and Tasson, Paul L., to Varco Shaffer, Inc. Rotating blowout preventer and method, 5,588,491, Cl. 166-383,000.
- Bruss, Elke: See—
Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruss, Elke; Guntert, Dietmar; and Müller, Hubert, 5,589,060, Cl. 210-130,000.
- Bryant, David W., to Mobil Oil Corporation. Tool for blocking axial flow in gravel-packed well annulus, 5,588,487, Cl. 166-51,000.
- Bryant, Stewart F.; Seaman, Michael J.; and Schmidt, Christopher R., to Digital Equipment Corporation. Packet forwarding system for measuring the age of data packets flowing through a computer network, 5,590,366, Cl. 395-800,000.
- Bu, Jong U., to Goldstar Co., Ltd. Microwave oven employing thermopile type sensor, 5,589,094, Cl. 219-711,000.
- Bucurius, Klaus M.: See—
Menke, Klaus; Böhmlein-Maass, Jutta; Schmid, Helmut; Bucurius, Klaus M.; and Engel, Walther, 5,589,661, Cl. 149-19,400.
- Buchanan, Charles M.: See—
White, Alan W.; Pearce, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., 5,589,566, Cl. 528-286,000.
- Buchi Laboratories, Technik AG: See—
Bossart, Erwin, 5,589,135, Cl. 422-99,000.
- Buchin, Michael P., to Origin Medsystems, Inc. Video imaging system with external area processing optimized for small-diameter endoscopes, 5,589,874, Cl. 348-72,000.
- Buckreub, Stefan, to Deutsche Forschungsanstalt für Luft- und Raumfahrt e.V. Method and apparatus for finding aircraft position by integrating accelerations less time averages, 5,590,044, Cl. 364-453,000.
- Budlong, Allan: See—
Samson, Randall J.; Budlong, Allan; and Huslig, Dan, 5,590,402, Cl. 455-44,000.
- Budzyna, W. James: See—
Sallen, Roy; Budzyna, W. James; and Sawahini, Charles E., 5,589,821, Cl. 340-573,000.
- Buendgen, Michael R.; and Hable, Bernard J., to Zenco (No. 4) Limited. Inbred corn line ZS1679, 5,589,606, Cl. 800-200,000.
- Buhl, Steven N.: See—
Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498,000.
- Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera; and Schnappinger, Dirk, to BASF Aktiengesellschaft; and Knoll Aktiengesellschaft. Tetracycline regulated transcriptional modulators with altered DNA binding specificities, 5,589,362, Cl. 435-69,100.
- Bukhari, Mohammad: See—
Soleimani, Mohammad; Corrigan, John E., III; Bukhari, Mohammad; and Rooks, David A., 5,589,837, Cl. 342-359,000.
- Bull HN Information Systems Inc.: See—
Guenther, Russell W.; and Rabins, Leonard, 5,590,301, Cl. 395-412,000.
- Bull S.A.: See—
Dubourcau, Jean-Paul; and Jacquin, Thierry, 5,590,335, Cl. 393-704,000.
- Buluca, Constantine; and Grubisich, Michael J., to National Semiconductor Corporation. Fabrication of bipolar transistors with improved output current-voltage characteristics, 5,589,409, Cl. 437-31,000.
- Bunting, Bryce T.; and Cook, Lalan W. Ball valve, 5,588,638, Cl. 251-315,050.
- Burge, Geoffrey L.: See—
Russell-Jones, Gregory J.; Howe, Peter; de Aizpurua, Henry J.; and Burge, Geoffrey L., 5,589,463, Cl. 514-21,000.
- Burger, Guenter, to Rampf Formen GmbH. Process for producing a steel mold for concrete paving blocks with spacers, 5,589,087, Cl. 219-93,000.
- Burgess, Dana J.; and Stubbs, Robert E., to Fujitsu Limited. Bus supporting a plurality of data transfer sizes and protocols, 5,590,369, Cl. 395-800,000.
- Burgoon, Jack L.: See—
Bargiel, Douglas A.; Burgoon, Jack L.; and Combs, Michael D., 5,588,179, Cl. 15-349,000.
- Burnet, John. Medical attachment device, 5,588,166, Cl. 5-503,100.
- Burns, Clay A.: See—
Jay, John C.; and Burns, Clay A., 5,588,696, Cl. 297-129,000.
- Burns, David: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickey; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242,400.
- Burns, Mark A., to Texas Instruments Incorporated. Coherent undersampling digitizer for use with automatic field test equipment, 5,589,763, Cl. 324-76,150.
- Burr Oak Tool & Gauge Company: See—
Franks, Lawrence A.; Harman, Galen B.; and Flint, Herman, 5,588,345, Cl. 83-95,000.
- Burton, John H.; and Staehle, Bradford G., to American Medical Systems, Inc. Device for slowly dilating the prostatic urethra, 5,588,965, Cl. 604-101,000.
- Busch, Dietrich; and Leroux, Roland, to Schott Glaswerke. Heat-insulating viewing window or viewing door for an apparatus having an interior temperature deviating from the ambient temperature thereof, 5,588,421, Cl. 126-200,000.
- Busch, Eric M.: See—
Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114,000.
- Bush, Alan M.: See—
Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., 5,590,259, Cl. 395-764,000.
- Bush Buake Allen Inc.: See—
Mankoo, Amrit S., 5,589,158, Cl. 424-49,000.
- Bushman, Boyd B., to Lockheed Martin Corporation. Method and apparatus for supplying electric power, 5,590,014, Cl. 361-225,000.
- Busse, Bernd: See—
Scannell, Robert; Busse, Bernd; and Vormwald, Helmut, 5,589,044, Cl. 204-286,000.
- Butler, John: See—
Hampson, Ian N.; Pope, Lynne; and Butler, John, 5,589,339, Cl. 435-6,000.
- Butler, Kenneth C.: See—
Taylor, Lynn P.; le Blanc, Pieter W. J. C.; Butler, Kenneth C.; and Maher, Timothy R., 5,588,812, Cl. 417-356,000.
- Butler, Laura J.; and Grauman, Joyce A., to Microsoft Corporation. Method and system for scalable borders that provide an appearance of depth, 5,590,267, Cl. 395-340,000.
- Butler, Patrick J. Method for detecting changes in preload on a tie rod installed as part of a core shroud repair in a boiling water reactor, 5,589,640, Cl. 73-761,000.
- Butters, Brian E.; and Powell, Anthony L. Advanced filtration technique for fluid purification, 5,589,078, Cl. 210-748,000.
- Buzon, Claude. Method and apparatus for supporting a building surface, 5,588,264, Cl. 52-126,600.
- Byrd, Harold N., to B&B Partnership. Signal device for use with a mailbox, 5,588,588, Cl. 232-35,000.
- Byrne, Phillip O.; and Essex, Timothy J. H., to British Technology Group Limited. Blood flow determination, 5,588,437, Cl. 128-691,000.
- Byrne, Thomas; and O'Connor, John. Contoured symmetrical differential-elasticity neck pillow, 5,588,168, Cl. 5-636,000.
- C.H. Heist Corp.: See—
Boisture, Thomas B., 5,588,593, Cl. 239-67,000.
- C. R. Bard, Inc.: See—
Cunningham, Robert W.; Koch, Durmus; Mura, Janine R.; Felix, Augustus; and Halick, Gary V., 5,588,958, Cl. 604-4,000.
- C. Uyemura & Co.: See—
Watanabe, Nobuatsu; Chong, Yong-Bo; and Matsumura, Sowjun, 5,589,271, Cl. 428-421,000.
- Cable, Thomas L.; and Petrik, Michael A., to Technology Management, Inc. Electrochemical apparatus and process, 5,589,285, Cl. 429-13,000.
- Cabler, Carlin D.: See—
Linz, Alfredo R.; Cabler, Carlin D.; Brown, Glen W.; and Soques, Martin P., 5,589,830, Cl. 341-110,000.
- Cabletron Systems, Inc.: See—
Vaishnavi, Vick; Matthews, Wallace; and Kenny, Patrick, 5,590,120, Cl. 370-254,000.
- Cabot Corporation: See—
Menashi, Jameel; Reid, Robert C.; Whitehouse, Robert S.; and Kaul, David J., 5,589,531, Cl. 524-409,000.
- Cadence Design Systems, Inc.: See—
Arora, Sandeep, 5,590,049, Cl. 364-489,000.
- Cafaro, Daniel P., to Allergan, Inc. Method for preventing the accumulation of inorganic deposits on contact lenses, 5,589,387, Cl. 435-264,000.
- Cahill, David E., to Eastman Kodak Company. Anti-gouging skive mechanism with replaceable fingers, 5,589,925, Cl. 399-323,000.
- Caldwell, Gregory. Fishing line device, 5,588,243, Cl. 43-4,000.
- Calgene, Inc.: See—
Kridl, Jean C.; Bruening, George; and Knauf, Vic C., 5,589,379, Cl. 435-240,400.
- Calgon Corporation: See—
Hunter, Wood E.; Frederick, Kevin W.; and Loeffler, Randy J., 5,589,525, Cl. 523-331,000.

Calhoun, Clyde D., and Koskenmaki, David C., to Minnesota Mining and Manufacturing Company. Heat-activatable adhesive article. 5,589,246, Cl. 428-120,000.

California Institute of Technology. *See—*

Anderson, David J., and Stemple, Derek L., 5,589,376, Cl. 435-240,200.

Callaghan, David T., Phipps, Alan M., and Provencal, Stephen J., to Gillette Company. The Antiperspirant composition. 5,589,196, Cl. 424-617,000.

Callaway Golf Company. *See—*

Schmidt, Glenn H., and Helmstetter, Richard C., 5,588,922, Cl. 473-324,000.

Schmidt, Glenn H., and Helmstetter, Richard C., 5,588,923, Cl. 473-340,000.

Calsonic North America, Inc. *See—*

Heath, Phillip T., 5,588,505, Cl. 184-18,000.

Calzavara, Giacomo. *See—*

Ceola, Giacomo; McCusker, James K., and Calzavara, Giacomo, 5,590,010, Cl. 361-93,000.

Camarota, Richard J., to ITC, Incorporated. Ventilation hose mounting assembly. 5,588,908, Cl. 454-78,000.

Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masoud; Hays, William D.; and Ackerman, David W., to Destineer Corporation. Method and system for efficiently providing two way communication between a central network and mobile unit. 5,590,403, Cl. 455-51,200.

Cameron, Fiona H. *See—*

Haseloff, James P.; Gerlach, Wayne L.; Jennings, Philip A.; and Cameron, Fiona H., 5,589,580, Cl. 536-23,200.

Cameron, John D., Jr. *See—*

Becker, John C.; Cameron, John D., Jr.; Cameron, William L.; and Sinram, Bryan W., 5,588,598, Cl. 241-19,000.

Cameron, William L. *See—*

Becker, John C.; Cameron, John D., Jr.; Cameron, William L.; and Sinram, Bryan W., 5,588,598, Cl. 241-19,000.

Camp, Floyd E. *See—*

Kim, Andrew S., and Camp, Floyd E., 5,589,009, Cl. 148-302,000.

Campbell, Robert K., to Signa Scan, Inc. Apparatus for analyzing signatures. 5,588,765, Cl. 401-216,000.

Campfield, Richard A. Glass repair kit and method of use. 5,589,018, Cl. 156-94,000.

Canada, Her Majesty the Queen in right of, as represented by the Minister of Agriculture. *See—*

Cohen, Hugue; and Williams, Ross E., 5,589,575, Cl. 530-413,000.

Canil, Gilberto. *See—*

Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergantini, Mirco; and Canil, Gilberto, 5,588,228, Cl. 36-118,200.

Canon Denshi Kabushiki Kaisha. *See—*

Sato, Osamu; and Mochida, Fumio, 5,590,236, Cl. 388-821,000.

Canon Information Systems Research Australia Pty Ltd. *See—*

Silverbrook, Kia, 5,590,252, Cl. 395-133,000.

Canon Kabushiki Kaisha. *See—*

Amemiya, Koji; and Inoue, Masahiro, 5,589,922, Cl. 399-315,000.

Chaya, Masahiko, 5,590,095, Cl. 369-13,000.

Chiba, Keiko; and Miyachi, Takeshi, 5,589,304, Cl. 430-5,000.

Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249,000.

Hashimoto, Kouji, 5,589,915, Cl. 399-120,000.

Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuto; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160,000.

Ikeda, Yui; and Fujita, Minoru, 5,590,039, Cl. 395-759,000.

Irie, Yoshiaki, 5,589,908, Cl. 396-51,000.

Itezo, Toshiyuki, 5,589,948, Cl. 358-449,000.

Itoyama, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yui; Toyomura, Fumitaka; and Ohtsuka, Takashi, 5,589,006, Cl. 136-248,000.

Iwamura, Keiichi, 5,590,138, Cl. 371-37,100.

Kadowaki, Hidejiro; Sugiyama, Hiroshi; Ishida, Yasuhiko; and Takamiya, Makoto, 5,589,858, Cl. 347-14,000.

Kageyama, Mitsuhiro, 5,590,190, Cl. 379-356,000.

Kozuki, Susumu; Harigaya, Isao; and Hori, Taizou, 5,589,943, Cl. 386-121,000.

Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145,000.

Maeda, Yasuo; and Sekiguchi, Kyoji, 5,589,899, Cl. 351-245,000.

Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15,000.

Murasawa, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi; and Hasegawa, Takashi, 5,589,926, Cl. 399-302,000.

Nakazawa, Toshiyuki, 5,590,265, Cl. 395-340,000.

Nishimura, Naoki, 5,589,040, Cl. 204-192,260.

Nitta, Jun, 5,590,145, Cl. 372-50,000.

Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114,000.

Shimizu, Hirokimi, 5,589,848, Cl. 345-102,000.

Shimoda, Isamu, 5,588,839, Cl. 434-114,000.

Shimokoriyama, Makoto; Aoki, Akio; and Kato, Masato, 5,589,946, Cl. 386-47,000.

Shiomi, Yasuhiko, 5,589,912, Cl. 396-55,000.

Shiraishi, Akihiko; Fujibayashi, Kazuo; and Kuwahara, Tetsuo, 5,589,882, Cl. 348-340,000.

Silverbrook, Kia, 5,590,252, Cl. 395-133,000.

Takada, Kuno, 5,589,244, Cl. 428-64,300.

Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34,000.

Toyama, Noboru; and Nakagawa, Katsumi, 5,589,403, Cl. 437-2,000.

Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadaaki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87,000.

Unokawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279,000.

Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuo, 5,589,103, Cl. 252-299,610.

Yamamoto, Shinji, 5,588,758, Cl. 400-322,000.

Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399-350,000.

Canon Sales Co., Inc. *See—*

Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, 5,589,001, Cl. 118-722,000.

Canova, Francis J., Jr. *See—*

Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie E.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828,000.

Capps, Stephen P. *See—*

Tchao, Michael C.; and Capps, Stephen P., 5,590,256, Cl. 395-787,000.

Capron, Barbara A. *See—*

Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4,100.

Carbonium Company, The. *See—*

Divakar, Ramesh; and Lau, Sai-Kwing, 5,589,428, Cl. 501-88,000.

Cardiac Pathways Corporation. *See—*

Imran, Mir A.; Pomeranz, Mark L.; and Glynn, Brian A., 5,588,964, Cl. 604-95,000.

Cargile, John W., Jr., to Klirklok Corporation. Paperboard container having flexible product dividing keel. 5,588,583, Cl. 229-120,170.

Carl-Zeiss-Stiftung. *See—*

Lücke, Christian; Vry, Uwe; and Lemcke, Ulrich, 5,589,977, Cl. 359-375,000.

Carley, William J. *See—*

Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., 5,590,274, Cl. 395-182,050.

Carlin, Richard T.; and Fuller, Joan, to United States of America, Air Force. Stabilized rechargeable cell in MSE. 5,589,291, Cl. 429-103,000.

Carmon, Iddo. *See—*

Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.

Carney, Glenn R. *See—*

Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.

Carney, Ronald. Multichannel wideband digital receiver making use of multiple wideband tuners having individually selectable gains to extend overall system dynamic range. 5,590,156, Cl. 375-316,000.

Caroli, Rodolfo. *See—*

Tagliaferri, Roberto; and Caroli, Rodolfo, 5,588,643, Cl. 271-35,000.

Caron, Paul. *See—*

Schofield, Harry; Caron, Paul; Field, Gary; and Follent, Paul, 5,589,868, Cl. 347-171,000.

Caron, Paul R. *See—*

Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.

Carr, James E.; and Lindsey, Mark A., to General Motors Corporation. Snap-in pedal with end caps. 5,588,338, Cl. 74-560,000.

Carrano, Anthony V. *See—*

Northrup, M. Allen; Mariella, Raymond P., Jr.; Carrano, Anthony V.; and Balch, Joseph W., 5,589,136, Cl. 422-102,000.

Carratt, Michel; and de Vecchis, Michel, to Alcatel Cable. Optical fiber cable and an associated method of manufacture. 5,590,233, Cl. 385-100,000.

Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angele; Schoepf, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, to Eli Lilly and Company; Universite Louis Pasteur; and Lilly, S.A. Pharmaceutical compounds. 5,589,501, Cl. 514-438,000.

Carriere, Steven N. Tree stand. 5,588,499, Cl. 182-135,000.

Carriker, Richard W.; and Fuller, John M., to Claymax Corporation. Low permeability geosynthetic clay liner and method of manufacture thereof. 5,589,257, Cl. 428-284,000.

Carson, Dennis A. *See—*

Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44,000.

Carson, Mark E.; Ranganathan, Mudumbai; and Cugini, Janet A., to International Business Machines Corporation. Integrity mechanism for data transfer in a windowing system. 5,590,266, Cl. 395-340,000.

Carsten, Robert L.; and Wilherger, Bernard E., to Carsten, Robert L. Auxiliary automatic valve shut-off system. 5,588,637, Cl. 251-129,030.

Carter, Jay, Jr. Dual lift boat hull. 5,588,389, Cl. 114-271,000.

Casio Computer Co., Ltd. *See—*

Hanzawa, Kohitaro; Sakata, Goro; and Tanaka, Kikuji, 5,590,364, Cl. 395-800,000.

Mikuni, Shin, 5,590,247, Cl. 395-110,000.

Nimura, Wataru, 5,588,755, Cl. 400-234,000.

Cassel, Scott T.; and Amedure, Michael E., to BKS Company. Pipe lap joint with improved collapsible sealing zone. 5,588,680, Cl. 285-3,000.

Casteel, Stephen P. *See—*

Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., 5,588,539, Cl. 211-41,000.

Castor, Patrick F.; Tsau, Yung-Chun; Kristiansen, Inge B.; and Nelson, John W., to Restaurant Technology, Inc. Distributed data processing system and method utilizing peripheral device polling and layered communication software. 5,590,288, Cl. 395-200,030.

Caterpillar Inc. *See—*

Stone, Dwight V.; Long, Douglas A.; and Salazar-Vior, Jose M., 5,588,413, Cl. 123-508,000.

CatsClaw Limited. *See—*

Behan, Kevin, 5,588,774, Cl. 404-6,000.

CCL Label, Inc. *See—*

Anderson, Robert J., 5,588,239, Cl. 40-630,000.

Ceglia, Teodoro. *See—*

Affaticati, Artemio; Cerutti, Claudio; and Ceglia, Teodoro, 5,588,520, Cl. 198-370,060.

Cell Genesys, Inc. *See—*

Seidman, Jonathan G.; and Jakobovits, Aya, 5,589,369, Cl. 435-172,300.

Cennerazzo, Michael. *See—*

Hansen, W. Peter; and Cennerazzo, Michael, 5,589,401, Cl. 436-525,000.

Centek Industries, Inc. *See—*

Magharious, Walaa, 5,588,888, Cl. 440-89,000.

Centre Technique de L'Industrie des Papiers, Cartons et Celluloses. *See—*

Sahater, Jacques; Tountollet, Guy E. P.; and Jayet, Gérard, 5,589,941, Cl. 356-376,000.

Centro de Investigacion Y de Estudios-Avanzados del IPN. *See—*

De La Luz, Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa, C. Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243,000.

Ceola, Giacomo; McCusker, James K.; and Calzavara, Giacomo. Heat responsive power interrupting device. 5,590,010, Cl. 361-93,000.

Cerdec Aktiengesellschaft Keramische Farben. *See—*

Dorbath, Bernd; Giesecke, Norbert; and Fritsche, Klaus-Dieter, 5,589,273, Cl. 428-433,000.

Cereda, Roberta. *See—*

Sala, Alberto; Banfi, Aldo; Benedini, Francesca; and Cereda, Roberta, 5,589,490, Cl. 514-330,000.

Cerutti, Claudio. *See—*

Affaticati, Artemio; Cerutti, Claudio; and Ceglia, Teodoro, 5,588,520, Cl. 198-370,060.

Ceshkovsky, Ludwig, to Discovision Associates. Recording information on an optical disc without using pre-manufactured tracks. 5,590,102, Cl. 369-44,110.

Cesnik, Friedrich. *See—*

Stefan, Ion; and Cesnik, Friedrich, 5,588,400, Cl. 122-406,100.

CFR Corporation. *See—*

Cho, Sung K.; and Schiebe, Lowell H., 5,589,080, Cl. 210-791,000.

Chalmers, James. *See—*

Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, 5,590,055, Cl. 364-550,000.

Champion International Corporation. *See—*

Fleck, John A., 5,589,036, Cl. 162-246,000.

Chan, Chin-Feng. *See—*

Duhamel, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, 5,588,257, Cl. 49-199,000.

Chang, Chi. *See—*

Haddad, Sameer S.; Chang, Chi; and Liu, David K. Y., 5,590,076, Cl. 365-185,250.

Chang, Chien-Chung. Roller assembly for massaging device. 5,588,953, Cl. 601-124,000.

Chang, Ching-Lu. Microphone. 5,590,211, Cl. 381-193,000.

Chang, Chung L. Seatback recliner mechanism. 5,588,705, Cl. 297-367,000.

Chang, Frank P. *See—*

Zhao, Jun; Chang, Frank P.; and Dornfest, Charles N., 5,589,003, Cl. 118-728,000.

Chang, Gwo-Jer. *See—*

Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, 5,590,055, Cl. 364-550,000.

Chang, Hershow, to Macronix International Co., Ltd. Input device interface with power connect state and serial data channel enabling power to the device from time to time. 5,590,339, Cl. 395-750,000.

Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., to North Carolina State University; and Du Pont de Nemours, E. I., and Company. Process for preparing a bleaching liquor containing percarboxylic acid and caro's acid. 5,589,032, Cl. 162-76,000.

Chang, Hueng-San. Elevator mechanism for vehicle. 5,588,793, Cl. 414-557,000.

Chang, Jeffrey C. *See—*

Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,589,433, Cl. 503-227,000.

Chang, Jeng C. *See—*

Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jeng C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498,000.

Chang, Kwei-Tang. Control circuit for controlling the operation of a multipurpose electronic cooker. 5,589,092, Cl. 219-506,000.

Chang, Shen-Youn. *See—*

Lin, Paul M.; Chang, Shen-Youn; and Kruzel, Chris, 5,589,468, Cl. 514-52,000.

Chang, Wen-Feng. *See—*

Shariff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, 5,590,374, Cl. 395-829,000.

Chapman, David J. *See—*

Wright, Kevin; Rogers, Lloyd W., Jr.; Baughman, Robert W.; and Chapman, David J., 5,588,258, Cl. 49-340,000.

Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., to Gas Research Institute. System and method for removing asbestos and other solid particles from a slurry. 5,589,073, Cl. 210-704,000.

Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, to Motorola, Inc. Method for describing measured results. 5,590,055, Cl. 364-550,000.

Chappell, Joseph; Saunders, Court A.; and Wolf, Fred R., to Amoco Corporation. Process and composition for increasing squalene and sterol accumulation in higher plants. 5,589,619, Cl. 800-205,000.

Charles, Bruce D.; Hassan, Ahmed A.; Tadghighi, Hormoz; JanakiRam, Ram D.; and Sankar, Lakshmi N., to McDonnell Douglas Helicopter Co. Blade vortex interaction noise reduction techniques for a rotorcraft. 5,588,800, Cl. 416-24,000.

Charles, Ian G. *See—*

Lipscombe, Martin J.; Charles, Ian G.; and Fairweather, Neil F., 5,589,384, Cl. 435-252,330.

Chase, Jeffrey A.; and Chase, Joseph L. System for mounting billboards. 5,588,237, Cl. 40-597,000.

Chase, Joseph L. *See—*

Chase, Jeffrey A.; and Chase, Joseph L., 5,588,237, Cl. 40-597,000.

Chatani, Ikuo. *See—*

Uryu, Masaru; Tokura, Kunihiko; Chatani, Ikuo; Mizoguchi, Ikuo; and Ito, Mamoru, 5,590,212, Cl. 381-191,000.

Chatani, Masayuki, to Sony Corporation. Information processing apparatus for adding handwritten data to a magneto-optical disc database. 5,590,107, Cl. 369-54,000.

Chatter, Mukesh. Method of and apparatus for improved dynamic random access memory (DRAM) providing increased data bandwidth and addressing range for current DRAM devices and/or equivalent bandwidth and addressing range for smaller DRAM devices. 5,590,078, Cl. 365-189,010.

Chatterji, Jiten; Griffith, James E.; Totten, Patty L.; and King, Bobby J., to Halliburton Company. Lightweight well cement compositions and methods. 5,588,489, Cl. 166-293,000.

Chau, Chiu, to Instruments SA, Inc. Compact spectrum analyzer module. 5,589,717, Cl. 356-328,000.

Chauvin, Yves; and Olivier, Hélène, to Institut Français du Pétrole. Process for the dimerization, co-dimerization and oligomerization of olefins. 5,589,601, Cl. 585-513,000.

Chaya, Masahiko, to Canon Kabushiki Kaisha. Magneto-optical disk apparatus with floating type magnetic head and a device for limiting an amount of deflection of a resilient member supporting the magnetic head. 5,590,095, Cl. 369-13,000.

Chem-tainer Industries, Inc. *See—*

Backs, Stephen A., 5,588,373, Cl. 108-55,300.

Chemoxal. *See—*

Ledon, Henry; Larnicol, Pierre; Desmurs, Marie-Jeanne; and Dupont, Michel, 5,589,590, Cl. 536-127,000.

Chen, Chu-Mei. *See—*

Pan, H. T.; and Chen, Chu-Mei, 5,588,850, Cl. 439-92,000.

Chen, Hector T. H. *See—*

Resnick, Douglas J.; Johnson, William A.; Cummings, Kevin D.; and Chen, Hector T. H., 5,590,239, Cl. 392-418,000.

Chen, Jack J. *See—*

Shariff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, 5,590,374, Cl. 395-829,000.

Chen, Jacob, to Testo Industry Corp. Magazine assembly for pneumatic staple guns. 5,588,577, Cl. 227-120,000.

Chen, James F.; and Wang, Jieh-Shan, to V-ONE Corporation. Electronic payment system and method. 5,590,197, Cl. 380-24,000.

Chen, Jey-Cheng, to Electronics Research & Service Organization. Microwave heating chamber for vending machines. 5,589,093, Cl. 219-679,000.

Chen, Kuo-Jen. Belt buckle. 5,588,184, Cl. 24-170,000.
 Chen, Liang B. See—
 Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401,000.
 Chen, Ling. See—
 Sung, Hung-Cheng; and Chen, Ling, 5,589,413, Cl. 437-43,000.
 Chen, Li-Yu, to Industrial Technology Research Institute. Two-speed gearbox. 5,588,930, Cl. 475-300,000.
 Chen, Yung-Pin. See—
 Wong, Bing L.; Shen, Yong-Qiang; and Chen, Yung-Pin, 5,589,354, Cl. 435-47,000.
 Chen-Chao, Huang. Adjustable base to hold flag banners. 5,588,630, Cl. 248-514,000.
 Chencinski, Edward W.; Bixler, Jeffrey C.; and Christensen, Neal T., to International Business Machines Corporation. Storage protection cache and backing storage having system control element data cache pipeline and storage protection bits in a stack array with a stack directory for the stack array. 5,590,309, Cl. 395-472,000.
 Cheney, Margaret. See—
 Isaacson, David; and Cheney, Margaret, 5,588,429, Cl. 128-734,000.
 Cheng, Kwang-Ting. See—
 Abramovici, Miron; Agrawal, Vishwani D.; Cheng, Kwang-Ting; and Rajan, Krishna B., 5,590,135, Cl. 371-22,100.
 Cheng, Yu-feng. Optical fiber connector including housing with a plurality of slots having securing plates. 5,590,230, Cl. 385-77,000.
 Chester, Brian, to Trychrest Proprietary Limited. Hinge. 5,588,180, Cl. 16-225,000.
 Chester, Stephen O. See—
 Bodford, Carl A.; Chester, Stephen O.; and Nayak, Rahul K., 5,589,249, Cl. 428-200,000.
 Chevalier, Alain; and Protat, Vincent, to Societe Anonyme dite: Aerospatiale Societe Nationale Industrielle. Method and device for estimating the thrust of a ramjet. 5,589,632, Cl. 73-117,400.
 Chevron Chemical Company. See—
 Gee, Jeffrey C.; Lawrie, Christophe J.; and Williamson, Roger C., 5,589,442, Cl. 507-103,000.
 Chevron U.S.A. Inc. See—
 Trimble, Harold J.; and Darsow, Brian A., 5,589,057, Cl. 208-148,000.
 Chiang, Chung-Ping. See—
 Huang, Jack; Chiang, Chung-Ping; and Feng, Chan-Hua, 5,588,331, Cl. 74-489,000.
 Chiang, Yulin. See—
 Glamkowski, Edward J.; and Chiang, Yulin, 5,589,495, Cl. 514-373,000.
 Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37,300.
 Chiba, Hiroshi; and Furumori, Kenji, to Nitto Denko Corporation; and Oct Co. Ltd. Adhesive insect trapping housing. 5,588,250, Cl. 43-114,000.
 Chiba, Keiko; and Miyachi, Takeshi, to Canon Kabushiki Kaisha. Photomask comprising a holding frame and reinforcing member with a ceramic oxide bond. 5,589,304, Cl. 430-5,000.
 Chiba, Masao; and Ishii, Mikio, to Kansai Corporation. Liquid crystal display system. 5,589,960, Cl. 349-76,000.
 Chiba, Takahiro. See—
 Takashima, Takayoshi; Chiba, Takahiro; and Tanaka, Takashi, 5,588,514, Cl. 215-42,000.
 Chibbar, Ravindra N. See—
 Nelra, Narendra S.; Kartha, Kuttu K.; and Chibbar, Ravindra N., 5,589,617, Cl. 800-205,000.
 Childs, Jerry D. See—
 Vijn, Jan P.; Venakis, Zacharias; Bour, Daniel L.; and Childs, Jerry D., 5,588,488, Cl. 166-293,000.
 Chimenti, Danette S. See—
 Kolton, Anthony D.; Gamboa, Ruben A.; and Chimenti, Danette S., 5,590,325, Cl. 395-615,000.
 Chinese Academy of Sciences, Chang Chun Institute of Applied Chemistry of the. See—
 Li, Wentan; and Liu, Xuying, 5,589,046, Cl. 204-424,000.
 Chinnakonda, Murali S. See—
 Zuraski, Gerald D., Jr.; White, Scott A.; Chinnakonda, Murali S.; and Christie, David S., 5,590,352, Cl. 395-800,000.
 Chino, Hiroshi. See—
 Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, 5,589,001, Cl. 118-722,000.
 Chinnon Gyogysezer es Vegyeszeti Termekek Gyara Rt. See—
 Mayar, Kálmán; Gáál, József; Sziráki, István; Lengyel, József; Szabo, Anna Z.; Mármárosi, Katalin; Hermecz, István; Szatmari, István; Torok, Zoltán; and Kormoczy, Péter, 5,589,513, Cl. 514-654,000.
 Chioffe, Joseph J. Earning back adapter. 5,588,309, Cl. 63-12,000.
 Chipchak, John C. See—
 Krajewski, Marjan, Jr.; Chipchak, John C.; Chodorow, David A.; Trostle, Jonathan T.; and Baldwin, Peter T., 5,590,199, Cl. 380-25,000.
 Chiron Corporation. See—
 Innis, Michael A.; and Creasey, Abia A., 5,589,359, Cl. 435-69,200.
 Chisso Corporation. See—
 Haruta, Hiroshi; and Takahashi, Takehiko, 5,589,111, Cl. 264-8,000.
 Kato, Kouichi; Watanabe, Eiji; and Kunimune, Kouichi, 5,589,319, Cl. 430-288,100.
 Chittipoddi, Satish, to Lucent Technologies Inc. Process for forming integrated capacitors. 5,589,416, Cl. 437-60,000.

Chiu, Tien-Heng, to Lucent Technologies Inc. Substrates and methods for gas phase deposition of semiconductors and other materials. 5,589,693, Cl. 257-48,000.
 Cho, Alfred Y. See—
 Baillargeon, James N.; and Cho, Alfred Y., 5,588,969, Cl. 23-294,000.
 Cho, Jae W. See—
 Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., 5,589,264, Cl. 428-359,000.
 Cho, Sung K.; and Schiebe, Lowell H., to CFR Corporation. Liquid recycling system with moving concentrated counterflow for filter clearance. 5,589,080, Cl. 210-791,000.
 Choate, Glenda L. See—
 Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britt, Wayne A., 5,590,052, Cl. 364-498,000.
 Chochinov, Allan B. See—
 Tanaka, Kazuna; Kapek, Jeffrey; and Chochinov, Allan B., 5,588,745, Cl. 366-130,000.
 Chodorow, David A. See—
 Krajewski, Marjan, Jr.; Chipchak, John C.; Chodorow, David A.; Trostle, Jonathan T.; and Baldwin, Peter T., 5,590,199, Cl. 380-25,000.
 Choi, Jeong-Hyuk, to Samsung Electronics Co., Ltd. Nonvolatile semiconductor memory device. 5,590,072, Cl. 365-185,010.
 Choi, Youngsuk, to Daewoo Electronics Co., Ltd. Disc clamping device for selectively clamping a compact disc in a unit device. 5,590,113, Cl. 369-270,000.
 Choi, Yun-Ho. See—
 Park, Churoo; Jang, Hyun-Seon; Kim, Chull-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230,030.
 Chokas, Shoichi; Aoki, Tomiyoshi; and Kimura, Kiyoshi, to Nippon Shinyaku Company, Limited. Pyrimidine derivatives and drugs. 5,589,477, Cl. 514-256,000.
 Chong, Yong-Bo. See—
 Watanabe, Nobuatsu; Chong, Yong-Bo; and Matsumura, Sowjun, 5,589,271, Cl. 428-421,000.
 Chonko, Mark A. See—
 White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hun, 5,589,423, Cl. 437-228,000.
 Chou, Chen-chang. Handlebar stem coupling module for a bicycle. 5,588,336, Cl. 74-551,100.
 Chow, Cheung K. See—
 Voigt, Carl E., IV; and Chow, Cheung K., 5,588,654, Cl. 273-284,000.
 Chowdhury, Jayanta R. See—
 Dannenberg, Andrew J.; and Chowdhury, Jayanta R., 5,589,504, Cl. 514-456,000.
 Christ, Heinrich. See—
 Thometzek, Peter; and Christ, Heinrich, 5,589,222, Cl. 427-215,000.
 Christensen, Jay D. See—
 Pickett, J. Paul; Jones, Dee L.; and Christensen, Jay D., 5,588,494, Cl. 171-124,000.
 Christensen, Neal T. See—
 Chencinski, Edward W.; Bixler, Jeffrey C.; and Christensen, Neal T., 5,590,309, Cl. 395-472,000.
 Christianson, Merrill A. See—
 Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474,130.
 Christie, David S. See—
 Zuraski, Gerald D., Jr.; White, Scott A.; Chinnakonda, Murali S.; and Christie, David S., 5,590,352, Cl. 395-800,000.
 Chrysler Corporation. See—
 Benford, Howard L., 5,588,929, Cl. 475-276,000.
 Lawrence, Thomas G., 5,588,402, Cl. 123-65,01P.
 Snell, William M., 5,588,514, Cl. 192-4,00A.
 Chuang, Louis. Tool assembly for bicycle. 5,588,169, Cl. 7-138,000.
 Chuang, Shi W. Device for mounting baby chair to bicycle. 5,588,701, Cl. 297-256,160.
 Chugai Ro Co., Ltd. See—
 Nagata, Masato; and Cornejo, José, 5,588,828, Cl. 432-59,000.
 Chum, Pak-Wing S. See—
 Ian, Shih-Yaw; Hazlett, Lomnie G.; and Chum, Pak-Wing S., 5,589,128, Cl. 264-328,100.
 Chun, Victor L., to Murata Machinery, Ltd. Electric servo motor punch press ram drive. 5,588,344, Cl. 83-13,000.
 Chung, Judy B. See—
 Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401,000.
 Chung, Shime, and Emerson, Paul G., to Hewlett-Packard Company. Multiported data storage device with improved cell stability. 5,590,087, Cl. 365-230,050.
 Chur, Sung P., to Swan Instruments, Inc. Magnetic media head dynamic testing apparatus and method which operate by deforming a localized portion of magnetic media toward the head element. 5,589,771, Cl. 324-212,000.
 Cialone, Anthony M. See—
 Pertido, Kenneth F.; and Cialone, Anthony M., 5,588,600, Cl. 241-23,000.
 Ciba-Giegy Corporation. See—

Reinehr, Dieter; Bacher, Jean-Pierre; and Schmitter, André, 5,589,529, Cl. 524-91,000.
 Clarion Co., Ltd. See—
 Uehara, Nagatoshi, 5,590,047, Cl. 364-478,020.
 Clark, Randall J.; Smith, Bradley W.; Rasmussen, Kirk H.; and Kort, Leland B., to Morion International, Inc. Stamped metal toroidal hybrid gas generator. 5,588,676, Cl. 280-741,000.
 Clark, William A.; Strickland, Carl C., Jr.; and Newman, Mark C., to Cooper Industries, Inc. Encapsulated transformer. 5,589,808, Cl. 336-92,000.
 Clarke Industries, Inc. See—
 Bargiel, Douglas A.; Burgoon, Jack L.; and Combs, Michael D., 5,588,179, Cl. 15-349,000.
 Clarke, Michael J. See—
 Blackborow, John R.; and Clarke, Michael J., 5,588,973, Cl. 44-347,000.
 Claussner, André; Goubet, François; and Teutsch, Jean-Georges, to Uclaf, Roussel. Phenylimidazolidines. 5,589,497, Cl. 514-386,000.
 Claymax Corporation. See—
 Carriker, Richard W.; and Fuller, John M., 5,589,257, Cl. 428-284,000.
 Clearman, Jack F., to R. J. Reynolds Tobacco Company. Cigarette with improved cellulosic substrate. 5,588,446, Cl. 131-194,000.
 Clecim. See—
 Forestier, Guy, 5,590,151, Cl. 373-72,000.
 Cleland, Jeffrey L.; and Jones, Andrew J. S., to Genentech, Inc. Excipient stabilization of polypeptides treated with organic solvents. 5,589,167, Cl. 424-85,700.
 Clemens, Donald, to Thermalloy, Inc. Fan attachment clip for heat sink. 5,590,025, Cl. 361-695,000.
 Clement, Marc. See—
 Donne, Mario Dalle; Schumacher, Guster; Geiler, Volkmar; Clement, Marc; and Speit, Burkhard, 5,589,427, Cl. 501-33,000.
 Cleveland Clinic Foundation, The. See—
 Insler, Steven R.; and Kraenzler, Erik J., 5,588,424, Cl. 128-207,159.
 Clintec Nutrition Co. See—
 Lin, Paul M.; Chang, Shen-Youn; and Kruzel, Chris, 5,589,468, Cl. 514-52,000.
 Clorox Company, The. See—
 Koerner, Michael; and Deleuw, David L., 5,589,448, Cl. 510-284,000.
 Cloud, Gene, to Micron Technology, Inc. Wrist support for expandable keyboards. 5,588,759, Cl. 400-472,000.
 Clynes, Manfred. Remote access server using files containing generic and specific music data for generating customized music on demand. 5,590,282, Cl. 395-200,020.
 CMI Corporation. See—
 Swisher, Robert W., Jr.; and Phillips, John F., 5,588,776, Cl. 404-72,000.
 Cobb, George E. Reel-to-reel pipe wrap machine. 5,588,290, Cl. 57-3,000.
 COBE Laboratories, Inc. See—
 Maltais, Jo-Ann B.; Wood, Archie T.; and Hovland, Roy S., 5,589,070, Cl. 210-636,000.
 Cochran, Harry L. See—
 Berger, H. Stephen; Vela de Casillas, Martha L.; and Cochran, Harry L., 5,589,773, Cl. 324-261,000.
 Coel, Joseph B. See—
 Lindner, Thomas A.; and Coel, Joseph B., 5,588,217, Cl. 33-379,000.
 Cohen, Gerald D.; Stout, Ralph L.; and Edson, Jay H., to Information Builders, Inc. Query processor for parallel processing in homogenous and heterogeneous databases. 5,590,319, Cl. 395-604,000.
 Cohen, Huguette; and Williams, Ross E., to Canada, Her Majesty the Queen in right of, as represented by the Minister of Agriculture. Purification of hapten-carrier generated antibodies. 5,589,575, Cl. 530-413,000.
 Cohen, Ronny. See—
 Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itiel; Epstein, Lev; Katziy, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehzekel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
 Cold Spring Harbor Laboratory. See—
 Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6,000.
 Cole, James J. See—
 Ahmad, Suhail; Cole, James J.; and Ahmed, Mahboob, 5,588,959, Cl. 604-6,000.
 Cole, Randy. See—
 Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173,000.
 Collier, William V. See—
 Boumarah, Mohamed; Hurford, Jonathan P.; Collier, William V.; and Lichlyter, Ralph, 5,588,671, Cl. 280-730,200.
 Collins, Clive A. See—
 Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800,000.
 Collins, Donald A., Jr.; and Aleshire, Rex A., to AT&T Global Information Solutions Company. Universal mounting apparatus and method for bar code scanners. 5,588,621, Cl. 248-27,100.
 Collins, James S. See—
 Madaffari, Peter L.; and Collins, James S., 5,589,799, Cl. 330-277,000.
 Collins, John E. See—
 Kruse, John M.; Collins, John E.; and Sisley, Elizabeth M., 5,590,269, Cl. 395-209,000.
 Collins, John H. See—
 Sivakumar, Ananthasubramanian; Collins, John H.; and Ramesh, Manian, 5,589,075, Cl. 210-727,000.
 Collins, Mark L. See—
 Kearney, Kevin R.; Collins, Mark L.; Eldredge, John K.; and Morrissey, David V., 5,589,335, Cl. 435-6,000.
 Collins, Mary A.; Perkins, David G.; and White, Harry E., to Raychem Corporation. Sealing member and methods of sealing. 5,588,856, Cl. 439-204,000.
 Colorobbia Espana, S.A. See—
 Aparici, Antonio N., 5,588,296, Cl. 60-671,000.
 Colorprinting Specialists, Inc. See—
 Bloom, Hanley D., 5,589,021, Cl. 156-219,000.
 Colosky, Mark P. See—
 Zuraski, Jeffrey A.; and Colosky, Mark P., 5,589,805, Cl. 332-109,000.
 COM Dev. Ltd. See—
 Tang, Wai-Cheung, 5,589,807, Cl. 333-212,000.
 Combes, James R. See—
 DeSimone, Joseph M.; Maury, Elise E.; Combes, James R.; and Mence-loglu, Yusuf Z., 5,589,105, Cl. 252-351,000.
 Combs, Michael D. See—
 Bargiel, Douglas A.; Burgoon, Jack L.; and Combs, Michael D., 5,588,179, Cl. 15-349,000.
 Comesi S.A.I.C. See—
 Falia, Horacio C.; and Rojas, Carlos I., 5,589,227, Cl. 427-348,000.
 Comet Technik AG. See—
 Planta, Andrea V.; and Gerber, Rolf, 5,590,015, Cl. 361-277,000.
 Command Audio Corporation. See—
 Ryan, John O., 5,590,195, Cl. 380-9,000.
 Commelin, Sylvie J.; and Mondet, Jean J., to Eurocopter France. Flap stops device with retractable upper stops ring, and rotor head including it. 5,588,801, Cl. 416-46,000.
 Commercial Concepts, Inc. See—
 Schwan, Fred W.; and Francis, William C., 5,588,645, Cl. 473-456,000.
 Commissariat à l'Energie Atomique. See—
 Decroix, Guy M.; Gosset, Dominique; and Kryger, Bernard, 5,590,393, Cl. 428-552,000.
 Communications and Power Industries, Inc. See—
 Lien, Erling L.; and Karp, Arthur, 5,589,736, Cl. 315-5,430.
 Compaq Computer Corporation. See—
 Hess, Randall L.; and Johnson, Drew S., 5,590,315, Cl. 395-500,000.
 Sellers, Charles A., 5,590,020, Cl. 361-680,000.
 Thayer, John S.; and Ferguson, Patrick L., 5,590,378, Cl. 395-850,000.
 Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,590,292, Cl. 395-825,000.
 CompuScan Technologies, Inc. See—
 Blumberg, Barry B.; Pecka, James M.; and Allen, Bruce S., 5,588,649, Cl. 463-18,000.
 Conlon, Sean P.; Oureshi, Saleem U.; Hibner, John A.; Okorocho, Livyn O.; and Bishop, Gregory D., to Ethicon Endo-Surgery, Inc. Surgical instrument. 5,588,581, Cl. 227-176,100.
 Connolly, Kevin J. See—
 Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., 5,589,843, Cl. 343-820,000.
 Connotech Experts Conseils Inc. See—
 Moreau, Thierry, 5,590,196, Cl. 380-18,000.
 Connolly, Steven M. See—
 Mani, Sanjay; Nishimura, Dwight G.; Connolly, Steven M.; and Pauly, John M., 5,588,431, Cl. 128-653,300.
 Consorzio per la Ricerca sulla Microelettronica nel Mezzogiorno. See—
 Mancuso, Massimo; Poluzzi, Rinaldo; and Rizzotto, Gianguido, 5,589,890, Cl. 348-678,000.
 Contestable, Paul B.; and Snyder, Brian A., to Johnson & Johnson Clinical Diagnostics, Inc. Test kit and method for competitive specific binding assay. 5,589,344, Cl. 435-7,900.
 Contiero, Claudio; Galbiati, Paola; and Zullino, Lucia, to SGS-Thomson Microelectronics, S.r.l. Method for fabricating VDMOS transistor with improved breakdown characteristics. 5,589,405, Cl. 437-6,000.
 Converting, Inc. See—
 Hicks, Dennis G., 5,589,014, Cl. 156-73,100.
 Cook, James. See—
 Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173,000.
 Cook, Lalan W. See—
 Bunting, Bryce T.; and Cook, Lalan W., 5,588,638, Cl. 251-315,050.
 Cook Pacemaker Corporation. See—
 Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Goode, Louis; and Fearnot, Neal E., 5,588,436, Cl. 128-662,030.
 Cook, Stephen J. See—
 Leahy, Richard; and Cook, Stephen J., 5,589,445, Cl. 508-381,000.

- Cooper Industries, Inc. *See*—
Clark, William A.; Strickland, Carl C., Jr.; and Newman, Mark C., 5,589,808, Cl. 336-92.000.
- Cooper, Mark R., to Vermeer Manufacturing Company. Track trencher steering system and process. 5,590,041, Cl. 364-424.051.
- Cooper, Neal. *See*—
McCracken, William P., and Cooper, Neal, 5,589,891, Cl. 348-730.000.
- Copeland Corporation. *See*—
Wallis, Frank S., 5,588,819, Cl. 418-39.000.
- Coppes, Bryan A. *See*—
Nichols, James M., and Coppes, Bryan A., 5,588,778, Cl. 405-48.000.
- COR Therapeutics, Inc. *See*—
King, Robert, 5,589,571, Cl. 530-381.000.
King, Robert, 5,589,572, Cl. 530-381.000.
- Corcoran, Michael J. *See*—
Robinson, Donald G.; Geatz, Michael W.; and Corcoran, Michael J., 5,589,820, Cl. 340-572.000.
- Cordis Corporation. *See*—
Leone, James E., and Rowland, Stephen M., 5,588,961, Cl. 604-21.000.
- Corghi, Remo, to Corghi, S.p.A. System for measuring the wheel base of an automobile frame and the transverse and longitudinal offsets of its steered wheels. 5,589,927, Cl. 356-3.120.
- Corghi, S.p.A. *See*—
Corghi, Remo, 5,589,927, Cl. 356-3.120.
- Cornejo, José. *See*—
Nagata, Masao, and Cornejo, José, 5,588,828, Cl. 432-59.000.
- Cornelius, Edward J., III. *See*—
Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stollenberg, Blaise G., 5,590,209, Cl. 381-168.000.
- Cornell Research Foundation, Inc. *See*—
Dannenberg, Andrew J., and Chowdhury, Jayanta R., 5,589,504, Cl. 514-456.000.
Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,589,537, Cl. 524-780.000.
- Cornell, Thomas W., Jr., and Reinbold, John L. Fishing weight. 5,588,248, Cl. 43-44.900.
- Corning Incorporated. *See*—
Sherwood, Diana L., 5,589,115, Cl. 264-60.000.
- Corporation, Yelapa. *See*—
Rubey, Arthur C., III; Taylor, Andrew M.; and Spears, William E., Jr., 5,588,901, Cl. 451-99.000.
- Corring, John E., III. *See*—
Soleimani, Mohammad; Corrigan, John E., III; Bukhari, Mohammad; and Roos, David A., 5,589,837, Cl. 342-359.000.
- Corrugated Gear & Services, Inc. *See*—
Lauderbaugh, David M., 5,588,945, Cl. 493-480.000.
- Cortjens, Leo M.; Franklin, Kenneth A.; Mays, Richard C.; and Smith, Curtis M., to Videoconferencing Systems, Inc. Method of determining an error in a video conferencing system camera. 5,589,878, Cl. 348-211.000.
- Corvol, Pierre. *See*—
Lalouel, Jean-Marie; Jeunemaitre, Xavier; Liffon, Richard P.; Soubrier, Florent; Kotelevtsev, Youri; and Corvol, Pierre, 5,589,584, Cl. 536-24.310.
- Coskun, Nurecan, and Tate, Bruce A., to International Business Machines Corporation. Method and system for providing a testing facility in a program development tool. 5,590,330, Cl. 395-704.000.
- Costello, Bernard J., to Argus International. Apparatus for spray coating flat surfaces. 5,588,996, Cl. 118-668.000.
- Coster, Hans G. L.; Ashcroft, Robert G.; and Mahaworastipa, Tohsak, to Fucell Pty Limited. Methods for the selection, separation and fusion of cells. 5,589,047, Cl. 204-450.000.
- Costley, Robert B. *See*—
Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,590,292, Cl. 395-825.000.
- Cotney, Garland D. *See*—
Wentworth, Robert M.; Galloway, David; Cotney, Garland D.; and Webb, Brian A., 5,590,232, Cl. 385-92.000.
- Cotterill, Michael J. Mounting track. 5,588,375, Cl. 108-102.000.
- Coulie, Pierre, and Boon-Falleur, Thierry, to Ludwig Institute for Cancer Research. Isolated nucleic acid molecule which codes for a tumor rejection antigen precursor which is processed to an antigen presented by HLA-B44, and uses thereof. 5,589,334, Cl. 435-6.000.
- Coulson, Richard R.; D'Amario, Eric; and Moscovitch, Jerry, to Black & Decker, Inc. Cordless power tool having a push button battery release arrangement. 5,589,288, Cl. 429-96.000.
- Cousins, Michael; Patrick, Douglas; and Bassett, Carol T., to U.S. Tape Company, Inc. Measuring tape device including external cleaning member. 5,588,220, Cl. 33-768.000.
- Covex Computer Corporation. *See*—
Adkisson, Richard W., 5,590,304, Cl. 395-427.000.
- Covi, Christian, and Steinlechner, Werner, to D. Swarovski & Co. Zipper closure. 5,588,185, Cl. 24-381.000.
- Covol Technologies, Inc. *See*—
Ford, George W., Jr.; Lambert, Richard C.; and Madsen, Russell G., 5,589,118, Cl. 264-122.000.
- Cowie, Jocelyn W. Method and apparatus for locating and assessing soft tissue lesions. 5,588,440, Cl. 128-734.000.
- Cox, Anthony C. *See*—
Gianforte, John S., and Cox, Anthony C., 5,588,224, Cl. 34-447.000.
- Cox, Barbara. *See*—
Cox, Vance; and Cox, Barbara, 5,588,558, Cl. 222-64.000.
- Cox, James P., and Duffy Cox, Robert W. Stabilization of biowastes. 5,589,164, Cl. 424-76.500.
- Cox, James P.; Cox, R. W. Duffy; and Cox, Jeanne M. Methods for processing poultry shell eggs. 5,589,211, Cl. 426-298.000.
- Cox, Jeanne M. *See*—
Cox, James P.; Cox, R. W. Duffy; and Cox, Jeanne M., 5,589,211, Cl. 426-298.000.
- Cox, R. W. Duffy. *See*—
Cox, James P.; Cox, R. W. Duffy; and Cox, Jeanne M., 5,589,211, Cl. 426-298.000.
- Cox, Vance; and Cox, Barbara, to Van-Bar Enterprises, Inc. Liquid beverage dispenser. 5,588,558, Cl. 222-64.000.
- Coyne, Vernon E. *See*—
Weiner, Ronald M.; Shi, Juan; and Coyne, Vernon E., 5,589,373, Cl. 435-220.000.
- Craft, Charles W. *See*—
Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., 5,588,539, Cl. 211-41.000.
- Craig, Franklin J. *See*—
Weder, Donald E.; and Craig, Franklin J., 5,588,530, Cl. 206-451.000.
- Cramer, Laurence E. *See*—
Hobbs, John W.; and Cramer, Laurence E., 5,590,147, Cl. 372-75.000.
- Crane, Dreu E., to Crane Manufacturing, Inc. Office fitting. 5,588,467, Cl. 138-43.000.
- Crane Manufacturing, Inc. *See*—
Crane, Dreu E., 5,588,467, Cl. 138-44.000.
- Crasnianski, Serge. *See*—
Gruel, Henri; Moraine, Michel; and Crasnianski, Serge, 5,589,902, Cl. 396-3.000.
- Crass, Matthew M. *See*—
Becker, Thomas P.; Crass, Matthew M.; Putney, Gordon A.; Niesen, Randy J.; and Dwinski, Dean J., 5,589,644, Cl. 73-862.230.
- Cravatts, Mark R. *See*—
Ashana, Abhaya; Cravatts, Mark R.; and Krzyzanowski, Paul, 5,590,370, Cl. 395-800.000.
- Craver, Thomas R. *See*—
Lippincott, Louis A.; and Craver, Thomas R., 5,590,254, Cl. 395-135.000.
- Crawley, Michael E. *See*—
Park, David B.; and Crawley, Michael E., 5,589,079, Cl. 210-784.000.
- Creasey, Abba A. *See*—
Imms, Michael A.; and Creasey, Abba A., 5,589,359, Cl. 435-69.200.
- Crockett, Gary B., to IEX Corporation. Rules-based call routing. 5,590,188, Cl. 379-225.000.
- Cronce, Gary M.; and Stapleton, Craig A., to Advanced Accessory Systems LLC. Article carrier. 5,588,572, Cl. 224-321.000.
- Cronin, John E., to International Business Machines Corporation. Multi-surfaced capacitor for storing more charge per horizontal chip area. 5,589,707, Cl. 257-532.000.
- Crossetto, Dario B., to Universines Research Association, Inc. Parallel processing data network of master and slave transputers controlled by a serial control network. 5,590,284, Cl. 395-200.050.
- Crossman, Janet L. *See*—
Mainster, Martin A.; Crossman, Janet L.; and Johnson, Robert D., 5,589,896, Cl. 351-219.000.
- Crowley, Robert J., to Boston Scientific Corporation. Catheters for imaging, sensing electrical potentials, and ablating tissue. 5,588,432, Cl. 128-660.030.
- Crucible Materials Corporation. *See*—
Kim, Andrew S.; and Camp, Floyd E., 5,589,009, Cl. 148-302.000.
- Crum, David P. *See*—
Terjung, Herman F.; and Crum, David P., 5,588,276, Cl. 53-399.000.
- Cruz, Lourdes J. *See*—
Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurino D., 5,589,340, Cl. 435-6.000.
- Cryogenic Technical Services, Inc. *See*—
McIntosh, Glen E., 5,590,054, Cl. 364-505.000.
- Crystal, Bonnie. *See*—
Stevens, Jessica L.; and Crystal, Bonnie, 5,590,182, Cl. 379-130.000.
- Crystal Semiconductor Corporation. *See*—
Lin, Kun, 5,590,065, Cl. 364-724.100.
- Csagoly, Paul F. Structural beam. 5,588,273, Cl. 52-634.000.
- Csehi, Attila. *See*—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Ersebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Cselt, Centro Studi e Laboratori Telecomunicazioni S.p.A. *See*—
Bella, Valter; and Pellegrino, Paolo, 5,589,786, Cl. 327-108.000.
- Csen, Istvan. *See*—
Anderson, Charles R.; Warfield, Robert W.; Csen, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., 5,590,259, Cl. 395-764.000.
- Csizer, Eva. *See*—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Ersebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.

- Csonor, Katalin. *See*—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Ersebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Cuatt, Daniel R. *See*—
Lichti, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydelis, Ronald A.; and Fox, Michael J., 5,588,404, Cl. 123-90.170.
- Cugini, Janet A. *See*—
Carson, Mark E.; Ranganathan, Mudumbai; and Cugini, Janet A., 5,590,266, Cl. 395-340.000.
- Cullimore, D. Roy; and Alford, George W. Method and apparatus for the selective determination of fermentative cultured activities. 5,589,353, Cl. 435-34.000.
- Cummings, Kevin D. *See*—
Resnick, Douglas J.; Johnson, William A.; Cummings, Kevin D.; and Chen, Hector T. H., 5,590,239, Cl. 392-418.000.
- Cunningham, John E.; Goossen, Keith W.; Jan, William Y.; Pathak, Rajiv N.; and Walker, James A., to Lucent Technologies Inc. Monolithically integrated VLSI optoelectronic circuits and a method of fabricating the same. 5,589,404, Cl. 437-5.000.
- Cunningham, Robert W.; Koch, Durmus, Mura, Janine R.; Felix, Augustus; and Halick, Gary V., to C. R. Bard, Inc. Closed wound ontopedic drainage and autotransfusion system. 5,588,958, Cl. 604-4.000.
- Currie, Kenneth J. G. *See*—
Maddern, Peter; and Currie, Kenneth J. G., 5,589,258, Cl. 428-286.000.
- Curry, Douglas N.; and Hecht, David L., to Xerox Corporation. Spot profile control using fractional interface factors in a polygon ROS. 5,589,870, Cl. 347-233.000.
- Curtis, Benson M. *See*—
Smith, Craig A.; Larsen, Alf D.; Sims, John E.; and Curtis, Benson M., 5,589,456, Cl. 514-12.000.
- Cushing, Richard. *See*—
Suthersan, Suthan S.; Dynkin, Boris; and Cushing, Richard, 5,588,490, Cl. 166-370.000.
- Cytoclonal Pharmaceuticals, Inc. *See*—
Torczynski, Richard M.; and Bollon, Arthur P., 5,589,579, Cl. 536-23.100.
- D. Swarovski & Co. *See*—
Covi, Christian; and Steinlechner, Werner, 5,588,185, Cl. 24-381.000.
- Daar, Horst. *See*—
Barthel, Herbert; Daar, Horst; and Schuetz, Hartmut, 5,590,278, Cl. 395-185.000.
- Da Col, Marco; Dall'Asta, Leone; and Resta, Irene, to Biochimica Opos SpA. Crystalline form of a cephalosporin antibiotic. 5,589,593, Cl. 540-220.000.
- Dade International Inc. *See*—
Hilyard, Kathy; Monticello, James; and Rugg, James, 5,589,327, Cl. 435-4.000.
- Daewoo Electronic Co., Ltd. *See*—
Kim, Sang K.; Oh, PahngRoc; and Lee, Hong J., 5,588,717, Cl. 303-84.200.
- Daewoo Electronics Co., Ltd. *See*—
Choi, Youngsuk, 5,590,113, Cl. 369-270.000.
Ji, Jeong B.; and Um, Gregory, 5,589,084, Cl. 216-24.000.
- D'Agaro, Amos; Manno, Adriano; and Venturini, Andrea, to Exponent Italia S.r.l. Desktop organizer for an office workstation. 5,588,727, Cl. 312-283.000.
- Dahlin, Steinar. *See*—
Billstrom, Lars; Wetterborg, Lars; Dahlin, Steinar; and Persson, Bengt, 5,590,133, Cl. 370-349.000.
- Dai Nippon Printing Co., Ltd. *See*—
Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo, 5,589,434, Cl. 503-227.000.
- Takeuchi, Satoshi, 5,589,307, Cl. 430-49.000.
- Daiku, Hiroshi. *See*—
Kawata, Satoshi; Dohi, Masaji; Sakachi, Yoichiro; and Daiku, Hiroshi, 5,589,687, Cl. 250-338.300.
- Dailey, Gyles B. Light-governed windshield wiper and headlight control system with provision for maintaining the headlights on with insufficient ambient light. 5,589,716, Cl. 307-10.800.
- Dainippon Ink and Chemicals Inc. *See*—
Kinoshita, Masafumi; Niwa, Toshio; and Shihata, O., 5,589,541, Cl. 525-66.000.
- Daiwa Seiko, Inc. *See*—
Akiba, Masaru; and Tsurufuji, Tomoyoshi, 5,588,244, Cl. 43-24.000.
Yamaguchi, Nobuyuki, 5,588,605, Cl. 242-268.000.
- Dale, Allison Hazel C.; Piggitt, Roger H.; Hallett, Richard A.; and McIntyre, Paul R., to Eastman Kodak Company. High contrast photographic silver halide material. 5,589,318, Cl. 430-264.000.
- Dallas Semiconductor Corporation. *See*—
Bolan, Michael L.; and Little, Wendell L., 5,590,343, Cl. 395-750.000.
- Dall'Asta, Leone. *See*—
Da Col, Marco; Dall'Asta, Leone; and Resta, Irene, 5,589,593, Cl. 540-220.000.
- Dalla Vecchia, Gino. *See*—
Bentoldo, Franco; and Dalla Vecchia, Gino, 5,588,192, Cl. 26-37.000.
- Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., to Lucent Technologies Inc. Communication technique employing variable information transmission. 5,590,405, Cl. 455-54.100.
- D'Amario, Eric. *See*—
Coulson, Richard R.; D'Amario, Eric; and Moscovitch, Jerry, 5,589,288, Cl. 429-96.000.
- D'Ambra, Thomas E., to Albany Molecular Research, Inc. Piperidine derivatives and process for their production. 5,589,487, Cl. 514-317.000.
- Damen, Guy. *See*—
De Jaeger, Nikolaas; Damen, Guy; Winter, Gerhard; and Van Havenbergh, Jan, 5,589,048, Cl. 204-489.000.
- Dana Corporation. *See*—
Smith, Johnny N., 5,588,915, Cl. 464-14.000.
- Dandolu, Bhaktavatsala R. Intracardiac illuminator with suction. 5,588,952, Cl. 600-249.000.
- Danfoss A/S. *See*—
Jepsen, Hardy P., 5,588,347, Cl. 92-12.200.
- Dangson, Henry T. *See*—
Plantan, Ronald S.; and Dangson, Henry T., 5,588,348, Cl. 92-63.000.
- Dannenberg, Andrew J.; and Chowdhury, Jayanta R., to Cornell Research Foundation, Inc.; and Albert Einstein College of Medicine of Yeshiva University, a Division of Yeshiva University. Treatment of newborn jaundice. 5,589,504, Cl. 514-456.000.
- Danno, Hirofumi. *See*—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.
- D'Antonio, Nicholas F.; and D'Antonio, Nicholas J. Sensor and transducer apparatus. 5,589,639, Cl. 73-724.000.
- D'Antonio, Nicholas J. *See*—
D'Antonio, Nicholas F.; and D'Antonio, Nicholas J., 5,589,639, Cl. 73-724.000.
- Dapp, Michael C. *See*—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Dar, Shaul. *See*—
Biliris, Alexandros; Dar, Shaul; and Gehani, Narain H., 5,590,327, Cl. 395-670.000.
- Darsow, Brian A. *See*—
Trimble, Harold J.; and Darsow, Brian A., 5,589,057, Cl. 208-148.000.
- Das, Satyendranath. Ferroelectric RF limiter. 5,589,440, Cl. 505-210.000.
- Datacard Corporation. *See*—
Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700.000.
- Dauer, Richard R. *See*—
Venkataramani, Edamanal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182.110.
- Daugherty, Tamara L.; and Harris, Christopher E., to Air Products And Chemicals, Inc. Recompression cycle for recovery of natural gas liquids. 5,588,308, Cl. 62-622.000.
- David Clark Company Inc. *See*—
Urella, Richard M.; and Davis, Glen A., 5,590,213, Cl. 381-183.000.
- David, Howard S. *See*—
Nardone, Joseph M.; McTague, Michael J.; and David, Howard S., 5,590,289, Cl. 395-289.000.
- Davidson, Dale D.; and Sadeghpour, Hamid R., to Honeywell Inc. Closed loop control system and method using back EMF estimator. 5,589,749, Cl. 318-564.000.
- Davidson, James A., to Smith & Nephew Richards, Inc. Zirconium oxide and zirconium nitride coated guide wires. 5,588,443, Cl. 128-772.000.
- Davignon, Paul A., to Avery Dennison Corporation. Needle for use in the rodless dispensing of plastic fasteners. 5,588,575, Cl. 227-67.000.
- Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L.; and Gamand, Patrice, to Hewlett-Packard Company; and Philips Electronics N.V. Circuit and method for testing a disk drive head assembly without probing. 5,589,777, Cl. 324-537.000.
- Davis, Bruce. *See*—
Knee, Robert A.; Favia, Anthony R.; Davis, Bruce; and Miller, Larry, 5,589,892, Cl. 348-731.000.
- Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., to Tapistron International, Inc. Apparatus and method for producing patterned tufted goods. 5,588,383, Cl. 112-80.180.
- Davis, Glen A. *See*—
Urella, Richard M.; and Davis, Glen A., 5,590,213, Cl. 381-183.000.
- Davis, Grover W. Air encircling marine propulsion apparatus. 5,588,886, Cl. 440-67.000.
- Davis, Howard P.; and Ruff, Wolfram, to Euro-Matic Ltd.; and VAW Aluminium AG. Mass or energy transfer process using fluidized bed. 5,588,986, Cl. 95-211.000.

- Davis, James F. Offset, poultry deboning system. 5,588,906, Cl. 452-179,000.
- Davis, Wayne S.; Shirk, Michael E.; and Whiteman, Robert N., Jr., to Whitaker Corporation. The electrical connector with multiple blade contacts. 5,588,877, Cl. 439-660,000.
- Dawson, Paul A. Ireal hile acid transporter compositions and methods. 5,589,358, Cl. 435-69,100.
- Dawson, William B., to Keystone Retaining Wall Systems, Inc. Landscaping block system. 5,588,262, Cl. 52-102,000.
- Dawson, William O. See—
- Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K., 5,589,367, Cl. 435-172,300.
- Day, Stephen W., to Webcore Technologies, Inc. Reinforced foam cores and method and apparatus of production. 5,589,243, Cl. 428-56,000.
- de Aizpurua, Henry J. See—
- Russell-Jones, Gregory J.; Howe, Peter; de Aizpurua, Henry J.; and Burge, Geoffrey L., 5,589,463, Cl. 514-21,000.
- Deal, Gregory K. See—
- Hassler, Joseph A.; Deal, Gregory K.; Koss, Timothy A.; and Heil, Stephen F., 5,590,379, Cl. 395-851,000.
- de Almeida, Amilton F. See—
- Schmidt, Christopher G.; Fisher, Michael H.; de Almeida, Amilton F.; and Tani, Edson T., 5,588,731, Cl. 312-405,000.
- Dear, Aiden R.; and Higgs, John E., to Avdel Systems Limited. Adaptor for hand-held power tool. 5,588,495, Cl. 173-170,000.
- De Beuckeleer, Marc; Herdies, Lydia; Gossele, Veronique; and Mariani, Celestina, to Plant Genetic Systems, N.V. Stamen-specific promoters from corn. 5,589,610, Cl. 800-205,000.
- DeBleeker, Luc. See—
- Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Mueller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.
- DeCarlo, David J.; Mineur, Thomas L.; and Stanwick, Ronald S., to Thomas & Betts Corporation. Enclosure for sealing a splice of electrical cables. 5,589,666, Cl. 174-87,000.
- Deck, Leslie L., to Zygo Corporation. Method and apparatus for optical interferometric measurements with reduced sensitivity to vibration. 5,589,938, Cl. 356-359,000.
- De Clercq, Ann; Krehbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, to Plant Genetic Systems N.V.; and Brazilian Agricultural Research Organization-Embrapa/Cenargen. Process for the production of transgenic plants with increased nutritional value via the expression of modified 2S storage albumins. 5,589,615, Cl. 800-205,000.
- Detroit, Guy M.; Gosset, Dominique; and Kryger, Bernard, to Commissariat à l'Energie Atomique. Neutron-absorbing material and its production process. 5,590,393, Cl. 428-552,000.
- Delelmah, Rudolf. See—
- Alber, Friedrich; Delelmah, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605,000.
- De Dios Figueroa C., Juan. See—
- De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C., Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243,000.
- de Ferran, Max. See—
- Havay, Marc; and de Ferran, Max, 5,589,999, Cl. 360-85,000.
- Dehieuw, Geert; Janssens, Wilhelmus; Uytendaele, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, to Agfa-Gevaert N.V. Thermal transfer imaging process. 5,589,317, Cl. 430-203,000.
- De Filippis, Pietro; Quatterio, Ernesto; and Petrone, Alberto, to Bitron S.P.A. Electronic switching fan assembly for a vehicle. 5,588,814, Cl. 417-423,700.
- Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Horlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, to Hoechst Aktiengesellschaft. Process for the preparation of cepheine produgs. 5,589,594, Cl. 540-228,000.
- Defosse, Gérard. See—
- Jegham, Samir; Defosse, Gérard; Purcell, Thomas A.; and Even, Luc, 5,589,476, Cl. 514-230,200.
- DeFreez, Richard. See—
- Baird, Brian; DeFreez, Richard; and Sun, Yunlong, 5,590,141, Cl. 372-10,000.
- DeFreitas, Dennis M., to Simmonds Precision Engine Systems, Inc. Electrostatic fuel injector body with igniter electrodes formed in the housing. 5,588,299, Cl. 60-740,000.
- Degen, Peter J.; and Lee, Joseph Y., to Pall Corporation. Battery separator and battery containing same. 5,589,302, Cl. 429-250,000.
- deGroot, Peter. See—
- Wynn, Ed; Diaz-Infante, Javier; and deGroot, Peter, 5,588,278, Cl. 53-399,000.
- deGroot, Peter J. See—
- Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4,100.
- Dersenhofer, Manfred; Meiss, Dieter; and Messner, Ekkehard, to Patent-Treuhand-Gesellschaft F. Elektrische Glühlampen mbH. Electric lamp having a fluorescence-suppressed quartz-glass envelope, and quartz glass therefor. 5,589,734, Cl. 313-636,000.
- De Jaeger, Nikolaas; Damen, Guy; Winter, Gerhard; and Van Havenbergh, Jan, to AGFA-Gevaert, N.V. Method for the production of a radiographic screen. 5,589,048, Cl. 204-489,000.
- de Jong, Hendrik J.; and Postma, Ebele M., to N.V. Nederlandsche Apparatenfabriek Nedap. Fraud-resistant electronic identification device. 5,588,234, Cl. 40-301,000.
- DeKalb Genetics Corporation. See—
- Landsey, Marvin F., 5,589,605, Cl. 800-200,000.
- de Laforcade, Vincent; and Lacout, Franck, to L'Oréal. Device for actuating a dispensing mechanism such as a valve fitted to a pressurized aerosol container. 5,588,566, Cl. 222-402,110.
- De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C., Juan; and Martinez-Bustos, Fernando, to Centro de Investigacion Y de Estudios- Avanzados del I.P.N. Method for cooking wheat flour products by using infrared radiation. 5,589,210, Cl. 426-243,000.
- Delaune, Lawrence J. See—
- Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127,900.
- Deleuw, David L. See—
- Koerner, Michael; and Deleuw, David L., 5,589,448, Cl. 510-284,000.
- Dell USA, L.P. See—
- Estes, H. Scott, 5,590,029, Cl. 361-760,000.
- Lunsford, David R.; and Durkin, Michael D., 5,590,363, Cl. 395-800,000.
- Parks, Terry J.; and Gaskins, Darius D., 5,590,338, Cl. 395-742,000.
- Zeller, Charles P.; Parks, Terry J.; and Durkin, Michael D., 5,590,287, Cl. 395-250,000.
- Dellanoce, Paulo T. See—
- Lippai, Andre; Tanigami, Jorge K.; and Dellanoce, Paulo T., 5,588,351, Cl. 92-208,000.
- Delmas, Olivier. See—
- Patat, Jean-Louis; Delmas, Olivier; and Schmittauesler, Roland, 5,589,462, Cl. 514-21,000.
- Delnick, Frank M. See—
- Derzon, Dora K.; Arnold, Charles, Jr.; and Delnick, Frank M., 5,589,295, Cl. 429-190,000.
- Delta Electronics, Inc. See—
- Yang, Dah-Rong, 5,588,626, Cl. 242-378,100.
- Del Tredici, Gianfranco. See—
- Bastiohi, Catia; Bellotti, Vittorio; Del Tredici, Gianfranco; and Rallis, Angelos, 5,589,518, Cl. 521-55,000.
- Delwel, Francois; and Lang, David J., to Lever Brothers Company, Division of Conopco, Inc. Polyvinyl ether encapsulated particles. 5,589,267, Cl. 428-407,000.
- Demachi, Takashi. See—
- Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki, 5,588,555, Cl. 221-197,000.
- Demangus, Robert. See—
- Hutson, Clifford L.; and Demangus, Robert, 5,588,564, Cl. 222-383,100.
- DeMarco, John J.; Kook, Taehoo; and Kostelak, Robert L., Jr., to Lucent Technologies, Inc. Self-aligned opaque regions for attenuating phase-shifting masks. 5,589,303, Cl. 430-5,000.
- DeMay, Karl F., to Fold-Pak Corporation. Lipless folding cartons and blanks. 5,588,584, Cl. 229-132,000.
- DeMond, Thomas W. See—
- Thompson, E. Earle; and DeMond, Thomas W., 5,589,852, Cl. 345-147,000.
- Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wilsey, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., to Boehringer Mannheim Corporation. Osmium-containing redox mediator. 5,589,326, Cl. 435-4,000.
- De Nier, Theodorius H. M. See—
- Van Es, Arthur R.; Van Engelen, Gerard; De Nier, Theodorius H. M.; and Hoefnagels, Johannes F., 5,588,607, Cl. 242-356,300.
- Denton, Robert M.; and Fang, Zhigang, to Smith International, Inc. Rock bit grease composition. 5,589,443, Cl. 508-150,000.
- Deosaran, Trevor A.; Garg, Sanjiv; and Jadonato, Kevin R., to Seiko Epson Corporation. System and method for register renaming. 5,590,295, Cl. 395-393,000.
- DePietro, Richard P.; and Wilkinson, Brian J. Portable game hoist. 5,588,907, Cl. 452-187,000.
- D'Ercole, Steve, to KOP-Flex, Inc. Coupling with dual torque transmission paths. 5,588,917, Cl. 464-79,000.
- Derksen, Klaus, to Freudenberg, Carl. Covering developed for infusion bottle. 5,588,547, Cl. 215-247,000.
- Deroche, Gerald J., Sr. Air scoop and method of use with roof mounted vehicle air conditioner. 5,588,301, Cl. 62-61,000.
- Derzon, Dora K.; Arnold, Charles, Jr.; and Delnick, Frank M. Thin film polymeric gel electrolytes. 5,589,295, Cl. 429-190,000.
- Desai, Pravin M.; Pfeiffer, Michael L.; Pohlmeier, Mary M.; and Raymond, Jennifer B., to Recot, Inc. Dual-stage process for manufacturing potato chips. 5,589,213, Cl. 426-438,000.
- De Santis, Gerard J., to Hytech Pumps International, Inc. Pump pressure multiplier. 5,588,808, Cl. 417-225,000.
- Descombes, Jean-Philippe; and Marotte, Philippe, to Thomson Tubes & Displays, S.A. Deflection yoke liner with support ridges. 5,589,729, Cl. 313-440,000.

- DeSimone, Joseph M.; Maury, Elise E.; Combes, James R.; and Menceglou, Yusuf Z., to University of North Carolina at Chapel Hill. The Heterogeneous polymerization in carbon dioxide. 5,589,105, Cl. 252-351,000.
- Desmurs, Marie-Jeanne. See—
- Ledon, Henry; Larnicol, Pierre; Desmurs, Marie-Jeanne, and Dupont, Michel, 5,589,590, Cl. 536-127,000.
- Destineer Corporation. See—
- Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51,200.
- Deutsch, Brian M.; and Foster, Robert B., Jr., to American Wireless Corporation. System and method for frequency based acquisition acknowledgment between transmitter and receiver. 5,590,410, Cl. 455-76,000.
- Deutsche Automobilgesellschaft mbH. See—
- Klink, Rainer; German, Johann; and Warthmann, Wolfgang, 5,589,290, Cl. 429-99,000.
- Deutsche Forschungsanstalt für Luft- und Raumfahrt e.V. See—
- Buckreuth, Stefan, 5,590,044, Cl. 364-453,000.
- de Vecchis, Michel. See—
- Carratt, Michel; and de Vecchis, Michel, 5,590,233, Cl. 385-100,000.
- Dewanckele, Jean-Marie. See—
- Dehieuw, Geert; Janssens, Wilhelmus; Uytendaele, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, 5,589,317, Cl. 430-203,000.
- Dewar, Kevin D. See—
- Jones, Anthony M.; Dewar, Kevin D.; and Sotharan, Martin W., 5,590,067, Cl. 364-725,000.
- DewEze Manufacturing, Inc. See—
- Green, Norman E.; and Sowers, Kenneth V., 5,588,325, Cl. 74-15,630.
- Diamond Electric Mfg. Co., Ltd. See—
- Ishida, Yoshio, 5,588,483, Cl. 165-86,000.
- Diamond Safety Gear, Inc. See—
- Panton, George S., Jr., 5,588,156, Cl. 2-243,100.
- Diaz-Infante, Javier. See—
- Wynn, Ed; Diaz-Infante, Javier; and deGroot, Peter, 5,588,278, Cl. 53-399,000.
- Diazzi, Claudio. See—
- Borgato, Pierandrea; Diazzi, Claudio; and Pidutti, Alhino, 5,589,759, Cl. 323-222,000.
- Dickson, Curtis M. Charcoal-burning outdoor heater. 5,588,420, Cl. 126-25,000.
- Dickson, John W. Tethered ball batting practice device. 5,588,646, Cl. 473-426,000.
- Dieffenderfer, James N.; and Morehead, Bruce J., to International Business Machines Corporation. VME bus transferring system broadcasting modifiers to multiple devices and the multiple devices simultaneously receiving data synchronously to the modifiers without acknowledging the modifiers. 5,590,372, Cl. 395-823,000.
- Dieffenderfer, James W. See—
- Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800,000.
- Diekelman, Dennis P., to Motorola, Inc. Satellite cellular network resource management method and apparatus. 5,590,395, Cl. 455-13,100.
- Dietrich, Bernard. See—
- Jager, Helmut F.; Peschina, Jürgen; and Dietrich, Bernard, 5,588,795, Cl. 414-733,000.
- DiFlora, Michael A.; Pandey, Prakash N.; Robinson, Christopher S.; and Wagner, Philip C., to Bristol Compressors, Inc. Low noise refrigerant compressor. 5,588,810, Cl. 417-312,000.
- Digisonix, Inc. See—
- Popovich, Steven R., 5,590,205, Cl. 381-71,000.
- Digital Equipment Corporation. See—
- Bryant, Stewart F.; Seaman, Michael J.; and Szmidt, Christopher R., 5,590,366, Cl. 395-800,000.
- Klinker, Gudrun J., 5,590,271, Cl. 395-326,000.
- Uhler, George M.; and Mills, George G., 5,590,293, Cl. 395-581,000.
- Dillard, Keith A. Adjustable exercise device. 5,588,942, Cl. 482-139,000.
- Dilworth, Jonathan R. See—
- Archer, Colin M.; Dilworth, Jonathan R.; Jobanputra, Panna; Latham, Ian A.; and Thompson, Russell M., 5,589,576, Cl. 534-14,000.
- Dinunzi, Sharon A. See—
- Ramachandran, Ramesh; and Dinunzi, Sharon A., 5,589,545, Cl. 525-184,000.
- DiSalvo, Francis J. See—
- Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,589,537, Cl. 524-780,000.
- Dischler, Louis, to Milliken Research Corporation. Method for improving the energy absorption of a high tenacity fabric during a ballistic event. 5,589,254, Cl. 428-221,000.
- Discovision Associates. See—
- Ceshkovsky, Ludwig, 5,590,102, Cl. 369-44,110.
- Jones, Anthony M.; Dewar, Kevin D.; and Sotharan, Martin W., 5,590,067, Cl. 364-725,000.
- Distek, Inc. See—
- Brinker, Gerald; Hladik, Peter; and Gutwillig, Alan, 5,589,649, Cl. 73-866,000.
- Dittmann, Guenter. See—
- Stahl, Hans-Juergen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, 5,588,829, Cl. 432-77,000.
- Ditzik, Richard J. Display monitor position adjustment apparatus. 5,589,849, Cl. 345-126,000.
- Divakar, Ramesh; and Lau, Sai-Kwing, to Carborundum Company, The. Silicon carbide with controlled porosity. 5,589,428, Cl. 501-88,000.
- Döbbling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelamayer, Thomas; and Steinbach, Christian, to ABB Management AG. Burner. 5,588,826, Cl. 431-354,000.
- Dobkin, Robert C.; and Reay, Robert L., to Linear Technology Inc. Lead frame capacitor and capacitively-coupled isolator circuit using same. 5,589,709, Cl. 257-666,000.
- Doege, Reimer. See—
- Stahl, Hans-Juergen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, 5,588,829, Cl. 432-77,000.
- Doering, Jeffrey A. See—
- Kotwicki, Allan J.; Doering, Jeffrey A.; and Falandino, Michael P., 5,588,417, Cl. 123-697,000.
- Dohi, Masaji. See—
- Kawata, Satoshi; Dohi, Masaji; Sakachi, Yoichiro; and Daiku, Hiroshi, 5,589,687, Cl. 250-338,300.
- Doi, Miwako; Fukui, Mika; Nishida, Ikiko; and Kato, Nobuko, to Kabushiki Kaisha Toshiba. System and method for evaluating a workspace represented by a three-dimensional model. 5,590,268, Cl. 395-326,000.
- Doi, Shuji. See—
- Ohnishi, Toshihiro; Noguchi, Takanobu; and Doi, Shuji, 5,589,320, Cl. 430-321,000.
- Dole Fresh Vegetables Co. See—
- Wynn, Ed; Diaz-Infante, Javier; and deGroot, Peter, 5,588,278, Cl. 53-399,000.
- Dolf, Richard A. See—
- Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112-80,160.
- Doll, Dennis R. See—
- Thornton, John; Pool, Stanton J.; and Doll, Dennis R., 5,589,027, Cl. 156-304,400.
- Dollar, Charles R., II, to Siemens Energy & Automation, Inc. Electric arc detector sensor circuit. 5,590,012, Cl. 361-113,000.
- Dominguez, Armando. Double headed fastener. 5,588,788, Cl. 411-482,000.
- Domon, Akira. See—
- Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114,000.
- Donaldson, Richard E. See—
- McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28,500.
- Dongell, Jonathan E., to Universal Cement & Concrete Products, Inc. Pozzolan cement compositions and admixtures therefor. 5,588,990, Cl. 106-716,000.
- Donlon, Brian S. See—
- Taylor, Charles S.; Donlon, Brian S.; and Machold, Timothy R., 5,588,949, Cl. 600-166,000.
- Donna McMahon, Inc. See—
- McMahon, Donna, 5,588,892, Cl. 441-116,000.
- Donne, Mario Dalle; Schumacher, Gustav; Geiler, Volkmar; Clement, Marc; and Speit, Burkhard, to Schott Glaswerke. Substantially spherical particles of lithium silicates with improved mechanical properties and impaired surface quality. 5,589,427, Cl. 501-33,000.
- Donovan, Steven R. See—
- Gallant, John K.; and Donovan, Steven R., 5,590,175, Cl. 379-58,000.
- Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K., to Biosource Technologies, Inc. Recombinant plant viral nucleic acids. 5,589,367, Cl. 435-172,300.
- Dorbath, Bernd; Giesecke, Norbert; and Fritsche, Klaus-Dieter, to Cerdec Aktiengesellschaft Keramische Farben. Process and agent for the production of purple decoration. 5,589,273, Cl. 428-433,000.
- Dorn, Maximilian. See—
- Siemel, Günter; Dorn, Maximilian; and Zimmermann, Heinz, 5,589,526, Cl. 523-351,000.
- Dornfest, Charles N. See—
- Zhao, Jun; Chang, Frank P.; and Dornfest, Charles N., 5,589,003, Cl. 118-728,000.
- Dornier GmbH. See—
- Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425,600.
- Dornier, Pascal. See—
- Kikinis, Dan; Dornier, Pascal; and Seiler, William J., 5,590,382, Cl. 395-893,000.
- Doron, Moshe. See—
- Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmion, Iddo; Shlomo, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Ori; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yezbekel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Doryokuro Kakunenyō Kaihatsu Jigyodan. See—
- Takahashi, Yoshiharu, 5,589,140, Cl. 422-159,000.
- Doshi, Ashwin. See—

- Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virmig, Alex J.; Witman, Paul, and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Dostalek, Roman: See—
Fischer, Rolf; Dostalek, Roman; and Marosi, Laszlo, 5,589,600, Cl. 585-266.000.
- Doughty, Daniel H.: See—
Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Moller, Karin, 5,589,396, Cl. 436-73.000.
- Douglas & Lomason Company: See—
Homier, Robert L., 5,588,700, Cl. 297-238.000.
- Douglas, David C.: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmaul, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200.020.
- Dow Chemical Company, The: See—
Barry, Russell P.; and Pellereau, Bernard, 5,589,561, Cl. 526-348.100.
Garcés, Juan M.; Millar, Dean M.; and Howard, Kevin E., 5,589,153, Cl. 423-705.000.
Howard, Kevin E., 5,589,714, Cl. 257-788.000.
Lai, Shih-Yaw; Hazlett, Lonnie G.; and Chum, Pak-Wing S., 5,589,128, Cl. 264-328.100.
Russell, John W., 5,589,061, Cl. 210-198.200.
- Dow Corning Corporation: See—
Benedict, Dale G.; Wilgus, Frank R.; Fulk, Henry J.; and Gagliardi, William T., 5,588,560, Cl. 222-106.000.
- Dow Corning S.A.: See—
Kolaitis, Leonidas; Lenoble, Bertrand L. J.; and Prince, Mark A., 5,589,449, Cl. 510-466.000.
- Downes, Stuart D.; and Merrill, Leonard A., to EMC Corporation: Electrical contact for printed circuit boards, 5,589,669, Cl. 174-266.000.
- Downs, Robert C.; Mainquist, James K.; Nitz, Larry T.; and Aldrich, William L., III, to Saturn Corporation: Multiplexed hydraulic clutch control, 5,588,327, Cl. 74-335.000.
- Doyle, James J.: Nail flattening apparatus, 5,588,578, Cl. 227-155.000.
- Doyle, Mark C.: See—
Sancoff, Gregory E.; Doyle, Mark C.; and Field, Frederic P., 5,588,556, Cl. 222-1.000.
- Dr. Ing. h.c.F. Porsche AG: See—
Koehr, Robert, 5,588,694, Cl. 296-188.000.
- Drabent, Claudia: See—
Krahn, Wolfgang; Ernst, Johannes; and Drabent, Claudia, 5,589,430, Cl. 501-120.000.
- Drechsler, Peter H., to Torrington Company, The: Apparatus for and methods of stabilizing and regenerating metalworking fluids, 5,589,138, Cl. 422-108.000.
- Drohan, William N.; Wilkins, Tracy D.; Velandier, William H.; and Johnson, John L., to American Red Cross; and Virginia Intellectual Property Division: Expression of human protein C in mammary tissue of transgenic mammals, 5,589,604, Cl. 800-2.000.
- Drufka, Robert E.: See—
Blackmon, James B.; Drufka, Robert E.; Jones, Nelson E.; Gernick, R. Andrew; and Hand, Michael L., 5,589,758, Cl. 322-100.000.
- Druihe, Pierre: See—
Marchand, Claudine; Druihe, Pierre; Pujolant-Mercereau, Odile; and Langley, Gordon, 5,589,343, Cl. 435-7.220.
- D'Souza, David J.; Konzen, Neil; and Weise, David N., to Microsoft Corporation: Method and system for specifying alternate behavior of a software system using alternate behavior indicia, 5,590,347, Cl. 395-800.000.
- Du Pont de Nemours, E. I., and Company: See—
Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76.000.
Shiffert, Mark B.; and Rovens, Donald B., 5,589,098, Cl. 252-67.000.
- Dubé, William P.: See—
Siewert, Thomas A.; Dubé, William P.; and Fitting, Dale W., 5,589,690, Cl. 250-390.000.
- Duboc, Robert M., Jr.: See—
Fahlen, Theodore S.; Duboc, Robert M., Jr.; and Lovoi, Paul A., 5,589,731, Cl. 313-495.000.
- Dubourreau, Jean-Paul; and Jacquin, Thierry, to Bull S.A.: Process for analysis of deadlocks in an operating system, 5,590,335, Cl. 393-704.000.
- Ductus Incorporated: See—
Valdés, Jacobo; and Martínez, Eduardo, 5,589,851, Cl. 345-136.000.
- Duffy Cox, Robert W.: See—
Cox, James P.; and Duffy Cox, Robert W., 5,589,164, Cl. 424-76.500.
- Dufour, Yves, to U.S. Philips Corporation: Frequency divider circuit, frequency synthesizer comprising such a divider and radio telephone comprising such a synthesizer, 5,590,163, Cl. 377-110.000.
- Duggal, Anil R.; and Yakymyshyn, Christopher P., to General Electric Company: Ultrasonic detector using vertical cavity surface emitting lasers, 5,590,090, Cl. 367-7.000.
- Duhamel, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, to Stanley Works, The: Garage door operator, 5,588,257, Cl. 49-199.000.
- Duke University: See—
Szarnes, Eric B., 5,590,148, Cl. 372-105.000.
- Dulger, Viktor, to ProMinent Dosiertechnik GmbH: Adjustable stroke drive for a displacement piston pump, 5,588,339, Cl. 74-836.000.
- Dumas, Robert: See—
Irlbeck, Robert D.; Bates, Warren A.; Dumas, Robert; and Volz, Keith L., 5,588,846, Cl. 439-66.000.
- Duncan, Paul M., to Berg Technology, Inc.: Memory card assembly having improved means for grounding printed wiring board and method of use, 5,590,028, Cl. 361-737.000.
- Dunfield, John C.; and Heine, Gunter K., to Seagate Technology, Inc.: Hydrodynamic spindle motor having distributed windings, 5,590,003, Cl. 360-98.070.
- Dunham, Mark E.; and Morley, David W., to Univ. of California Office of Technology Transfer, The Regents of the: Enhanced performance CCD output amplifier, 5,589,881, Cl. 348-300.000.
- Dunlop, John A.; Yuan, Jun; Kardokus, Janine K.; and Emigh, Roger A., to Johnson Matthey Electronics, Inc.: Sputtering target with ultra-fine, oriented grains and method of making same, 5,590,389, Cl. 419-67.000.
- Dupont, Michel: See—
Ledon, Henry; Larnicol, Pierre; Desmuts, Marie-Jeanne; and Dupont, Michel, 5,589,590, Cl. 536-127.000.
- Duquid, Robert: See—
McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500.
- Duracell Inc.: See—
Pope, Peter J.; and Willis-Owen, Richard B., 5,589,293, Cl. 429-172.000.
- Duramax, Inc.: See—
Moore, Richard E., 5,588,916, Cl. 464-20.000.
- Durkin, Michael D.: See—
Lunsford, David R.; and Durkin, Michael D., 5,590,363, Cl. 395-800.000.
Zeller, Charles P.; Parks, Terry J.; and Durkin, Michael D., 5,590,287, Cl. 395-250.000.
- Dvorkis, Paul; and Shepard, Howard, to Symbol Technologies, Inc.: Parallelepiped-shaped optical scanning module, 5,589,679, Cl. 235-472.000.
- Dynamit Nobel Aktiengesellschaft: See—
Gessell, Uwe; Rospek, Rolf; and Zollner, Helmut, 5,589,657, Cl. 102-202.140.
- Dynatex International: See—
Elsbree, Charles N., 5,588,419, Cl. 125-15.000.
- Dynkin, Boris: See—
Suthersan, Suthan S.; Dynkin, Boris; and Cushing, Richard, 5,588,490, Cl. 166-370.000.
- Dziania, Krzysztof E.; and Tipping, John, to Rover Group Limited: System for providing heating, air conditioning and ventilation for a vehicle, 5,588,481, Cl. 165-42.000.
- E. R. Squibb & Sons, Inc.: See—
Robinson, Gordon W., 5,589,372, Cl. 435-193.000.
- East West Trade Group, Inc.: See—
Pavlov, Vyacheslav E.; Shabanov, Vasily F.; Anshits, Alexandr G.; and Bayakin, Sergei G., 5,588,977, Cl. 65-17.400.
- Easter, Scott D.: Timing buoy with remote timing capability, 5,588,889, Cl. 441-1.000.
- Eastman Chemical Company: See—
Shih, Wayne K.; and Light, Ronald R., 5,589,126, Cl. 264-211.000.
White, Alan W.; Pearce, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., 5,589,566, Cl. 528-286.000.
- Eastman Kodak Company: See—
Cabill, David F., 5,589,925, Cl. 399-323.000.
Dale, Allison Hazel C.; Piggitt, Roger H.; Hallett, Richard A.; and McIntyre, Paul R., 5,589,318, Cl. 430-264.000.
Estelle, Lee R.; and Goosey, William T., Jr., 5,589,989, Cl. 359-785.000.
Lobo, Lloyd A.; and Svereika, Aileen M., 5,589,322, Cl. 430-449.000.
McIntyre, Dale F., 5,589,905, Cl. 396-431.000.
Meyers, Mark M.; and Schickler, Mark E., 5,589,983, Cl. 359-566.000.
- Eaton Corporation: See—
Braun, Eugene R.; and Olson, Otis J., 5,588,516, Cl. 192-48.910.
Osinski, Mark A.; and Teadt, Donald D., 5,588,935, Cl. 477-107.000.
- Ebara Corporation: See—
Ushitora, Akihiro; and Shimizu, Osamu, 5,588,458, Cl. 137-205.000.
- Eberspächer, J.: See—
Wilson, Robert F., 5,588,592, Cl. 239-4.000.
- Ecker, Friedrich: See—
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruff, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Eckes, Peter: See—
Ulbrich, Norbert; Hilgenfeld, Rolf; Hanel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205.000.
- Eckman, Michael G.; and Smallwood, Paul A., to Taylor Nathan Co., Inc.: Golf putting cup, 5,588,918, Cl. 473-187.000.
- Ecolab Inc.: See—
Baum, Burton M., 5,589,099, Cl. 510-514.000.
- Eda, Kazuo: See—
Taguchi, Yutaka; Eda, Kazuo; Seki, Shun-ichi; and Onishi, Keiji, 5,589,806, Cl. 333-193.000.
- Edagawa, Noboru: See—

- Taga, Hidenori; Edagawa, Noboru; Takeda, Noriyuki; Yamamoto, Shu; and Akiha, Shigeyuki, 5,589,969, Cl. 359-124.000.
- Edgington, Robert J.; Stepro, James A.; Wissell, Harold J.; and Lundberg, Scott A., to National-Standard Company: Battery electrode substrates and method of making same, 5,589,301, Cl. 429-234.000.
- Edson, Jay H.: See—
Cohen, Gerald D.; Stout, Ralph L.; and Edson, Jay H., 5,590,319, Cl. 395-604.000.
- Edwards, Geraldine E., to International Business Machines Corporation: Apparatus and method for gathering and entering data requirements from multiple users in the building of process models and data models, 5,590,360, Cl. 395-800.000.
- Edwards, James P.: Mask for plating metals and method of construction thereof, 5,589,043, Cl. 204-281.000.
- Edwards, Karen J.; Jarman, Michael; Laughton, Charles A.; Neidle, Stephen; and Hardcastle, Ian R., to British Technology Group Limited: Substituted 1,1,2-triphenylbutenes and their use in the treatment of cancer, 5,589,500, Cl. 514-428.000.
- Edwards, Peter A.: See—
Spear, David H.; and Edwards, Peter A., 5,589,368, Cl. 435-172.300.
- Edwards, Stuart D.; Lax, Ronald G.; and Sharkey, Hugh R., to Vidamed, Inc.: Transurethral needle delivery device with cystoscope and method for treatment of urinary incontinence, 5,588,960, Cl. 604-20.000.
- Emalox Limited: See—
Horrobin, David F., 5,589,509, Cl. 514-560.000.
- Egawa, Tatsuya; Kawaguchi, Yasuhiro; Mogami, Kenji; and Shimizu, Nobuaki, to Idemitsu Kosan Co., Ltd.: Process of producing ether compound, 5,589,597, Cl. 568-608.000.
- Eger, Norman J.: See—
Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; DeLaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127.900.
- Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, to Weidmueller Interface GmbH & Co.: Connector terminal block with electronic module, 5,588,881, Cl. 439-709.000.
- Egging, Philip J., to Vermeer Manufacturing Company: Feed rate control system for stump cutters, 5,588,474, Cl. 144-24.120.
- EGS Americas, Inc.: See—
Gianforte, John S.; and Cox, Anthony C., 5,588,224, Cl. 34-447.000.
- Ehlers, Wayne L.; Eichholz, Kenneth L., Jr.; and Johnston, Mark F., to Honeywell Inc.: Method for manufacturing an overmolded sensor, 5,588,202, Cl. 29-606.000.
- Eichholz, Heinz-Dieter; and Rudrich, Hans-Peter, to Friedrich Grohe Aktiengesellschaft: Water fixture control system, 5,588,636, Cl. 251-129.040.
- Eichholz, Kenneth L., Jr.: See—
Ehlers, Wayne L.; Eichholz, Kenneth L., Jr.; and Johnston, Mark F., 5,588,202, Cl. 29-606.000.
- Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, to BASF Aktiengesellschaft: Fungicidal mixtures, 5,589,479, Cl. 514-275.000.
- Eicken, Karl; Gnetz, Norbert; Harreus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela; and Rang, Harald, to BASF Aktiengesellschaft: Anilide derivatives and their use for combating botrytis, 5,589,493, Cl. 514-355.000.
- Eiko Engineering Co., Ltd.: See—
Takahashi, Hiroshi, 5,588,999, Cl. 118-715.000.
- Eilers, Wayne E., to Owens-Brockway Glass Container Inc.: Apparatus for forming wide mouth glassware, 5,588,981, Cl. 65-241.000.
- Eirich, Paul: See—
Flemming, Eckardt; Tilch, Werner; Schusztz, Thomas; Ivanov, Marian; and Eirich, Paul, 5,589,650, Cl. 73-866.000.
- Ekstrom Industries, Inc.: See—
Pruhs, Allen V.; Robinson, Darrell; and Learmont, Robert O., 5,588,874, Cl. 439-517.000.
- Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruhs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.
- Elan Energy Inc.: See—
Heinrichs, Bernard, 5,588,486, Cl. 166-50.000.
- Elantec: See—
Harvey, Barry, 5,589,798, Cl. 330-263.000.
- Eldredge, John K.: See—
Kearney, Kevin R.; Collins, Mark L.; Eldredge, John K.; and Morrissey, David V., 5,589,335, Cl. 435-6.000.
- Eldridge, Robert A.; Unrein, Ed J.; Brown, David L.; and Noble, Scott L., to Intel Corporation: Portable disk drive carrier and chassis, 5,588,728, Cl. 312-332.100.
- Electro Scientific Industries, Inc.: See—
Baird, Brian; DeFreez, Richard; and Sun, Yunlong, 5,590,141, Cl. 372-10.000.
- Electron Power Systems: See—
Seward, D. Clint, 5,589,727, Cl. 313-231.310.
- Electronics and Telecommunications Research Institute: See—
Ahn, Kun-Young; Park, Kyung-Ho; Nam, Kee-Soo; and Kang, Sang-Won, 5,589,083, Cl. 216-24.000.
- Lyu, Gap Y.; and Park, Chang S., 5,589,970, Cl. 359-133.000.
- Electronics Research & Service Organization: See—
Chen, Jey-Cheng, 5,589,093, Cl. 219-679.000.
- Elf Atochem North America, Inc.: See—
- Robinson, Donald N.; and Peltz, John H., 5,589,028, Cl. 156-306.600.
- Elger, William A., to Milwaukee Electric Tool Corporation: Slip clutch arrangement for power tool, 5,588,496, Cl. 173-178.000.
- Eli Lilly and Company: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoepp, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Elin Mobren GmbH: See—
Berger, Josef, 5,589,720, Cl. 310-61.000.
- Elkay Electrical Manufacturing Company Limited: See—
Wales, Alan C. D., 5,589,663, Cl. 174-51.000.
- Elkhoury, George F.; and Stein, Christoph: Topical application of opioid analgesic drugs such as morphine, 5,589,480, Cl. 514-282.000.
- Ellis, Mark E.: Device for facilitating removal of wastewater and sewage from a recreational vehicle, 5,588,459, Cl. 137-239.000.
- Elmaleh, Samuel: Apparatus for liquid solid separation of liquid effluents or wastewater, 5,589,064, Cl. 210-206.000.
- Elmer, James S.: See—
Klee, Harry J.; and Elmer, James S., 5,589,583, Cl. 536-24.100.
- Elms, Timothy J.: See—
Studer, Michael K.; Zodrow, Thomas J.; and Elms, Timothy J., 5,588,947, Cl. 588-252.000.
- Elonex IP Holdings Ltd.: See—
Kikinis, Dan; Dornier, Pascal; and Seiler, William J., 5,590,382, Cl. 395-893.000.
- Elsbree, Charles N., to Dynatex International: Semiconductor wafer hubbed saw blade, 5,588,419, Cl. 125-15.000.
- Elul, Rafael: Razor with angled blades and guides, 5,588,211, Cl. 30-48.000.
- Emambakhsh, Ali S.; Pionk, Michael P.; Saberan, Ali A.; and Wallner, John P., to TRW Vehicle Safety Systems Inc.: Vehicle occupant restraint apparatus and method of assembly, 5,588,667, Cl. 280-728.200.
- Emambakhsh, Ali S.; and Stein, Russell E., to TRW Vehicle Safety Systems Inc.: Air bag module, 5,588,668, Cl. 280-728.200.
- Eman, Richard G.; and Mansur, Luis E.: Automated interactive roulette with progressive jackpot, 5,588,650, Cl. 273-142.000.
- Embre, Gary L.; and Williams, Robert A., to Acra Products, LLC: Zone tiller attachment for planters, 5,588,382, Cl. 111-139.000.
- EMC Corporation: See—
Andrews, Anthony D., 5,590,276, Cl. 395-182.040.
Downes, Stuart D.; and Merrill, Leonard A., 5,589,669, Cl. 174-266.000.
Sandorfi, Miklos A.; and Shriki, Moshe M., 5,590,122, Cl. 370-394.000.
- Emerson, David: See—
Brenzak, John A.; Emerson, David; and Koh, John K., 5,589,352, Cl. 435-34.000.
- Emerson Electric Co.: See—
Baker, Gerald N.; and Maes, Gregory R., 5,588,484, Cl. 165-122.000.
- Emerson, Paul G.: See—
Chung, Shine; and Emerson, Paul G., 5,590,087, Cl. 365-230.050.
- Emery, David: Camp kitchen cabinet, 5,588,724, Cl. 312-236.000.
- Emhart Inc.: See—
Knetsch, Harold, 5,588,576, Cl. 227-119.000.
Schliesser, Lothar, 5,588,683, Cl. 285-62.000.
- Emigh, Roger A.: See—
Dunlop, John A.; Yuan, Jun; Kardokus, Janine K.; and Emigh, Roger A., 5,590,389, Cl. 419-67.000.
- Emitec Gesellschaft fuer Emissionstechnologie mbH: See—
Maus, Wolfgang; Brück, Rolf; and Swars, Helmut, 5,588,291, Cl. 60-274.000.
- Empire Level Mfg. Co.: See—
Lindner, Thomas A.; and Coel, Joseph B., 5,588,217, Cl. 33-379.000.
- EMS-Inventa AG: See—
Pfleger, Wolfgang, 5,588,468, Cl. 138-121.000.
- Enami, Katsuya; and Miura, Tohru, to TEAC Corporation: Disk apparatus using constant linear velocity method and having head function stopped in standby mode, 5,590,105, Cl. 369-50.000.
- Endo, Sadahisa: See—
Suzuki, Shigemichi; and Endo, Sadahisa, 5,588,260, Cl. 49-502.000.
- Endo, Takashi: See—
Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zana, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161.000.
- Endoh, Hirotaka: See—
Ukigaya, Tadashi; and Endoh, Hirotaka, 5,589,191, Cl. 424-480.000.
- Engel, Walther: See—
Menke, Klaus; Böhlein-Maass, Jutta; Schmid, Helmut; Bucerius, Klaus M.; and Engel, Walther, 5,589,661, Cl. 149-19.400.
- England, Barbara J.: See—
Fiechtner, Michael D.; Ramp, John M.; England, Barbara J.; and Annino, Mary J., 5,589,393, Cl. 436-15.000.
- Enoki, Nobuyuki: See—
Morita, Mitsuaki; Miyazaki, Masaya; Enoki, Nobuyuki; and Takuma, Akira, 5,590,340, Cl. 395-750.000.
- Enomoto, Ryo; and Asai, Motoo, to Ibsiden Co., Ltd.: Adhesive for electroless plating, printed circuit boards and method of producing the same, 5,589,255, Cl. 428-261.000.
- Ensler, Lawrence M.: See—
Allen, Michael P.; Zuk, Robert F.; and Ensler, Lawrence M., 5,589,399, Cl. 436-169.000.
- Entact Corporation: See—
Studer, Michael K.; Zodrow, Thomas J.; and Elms, Timothy J., 5,588,947, Cl. 588-252.000.

Fom, Jae-Yong, to Samsung Electronics Co., Ltd. Magneto-optical recording and reproducing apparatus having an automatic head lifting device. 5,590,098, Cl. 369-13.000.

Fpps, Rickey: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Fpps, Rickey; Burns, David, and Hlozek, Robert J., 5,589,149, Cl. 423-242.000.

Epstein, Lev: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Iael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.

Erdelen, Christoph: See—
Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürsen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91.000.

Ereson, Birger, to Birger Ereson Fasad AB. Horizontally and vertically movable radiant heater for removing paint from a surface. 5,590,238, Cl. 392-412.000.

Ereson Inc.: See—
Fehnel, Michael D., 5,590,092, Cl. 368-10.000.
Henry, Raymond C., 5,590,396, Cl. 455-33.100.
Rydbeck, Nils, 5,590,417, Cl. 455-89.000.
Rydbeck, Nils R., 5,590,416, Cl. 455-90.000.

Erk Schmidt Autotilbehör Aps: See—
Schmidt, Erk, 5,588,574, Cl. 224-520.000.

Eriksen, Steen M. Backpack vacuum cleaner. 5,588,177, Cl. 15-327.500.

Ernst, Johannes: See—
Krahn, Wolfgang; Ernst, Johannes; and Drabent, Claudia, 5,589,430, Cl. 501-120.000.

Erwin, Gary B.: See—
Allen, Harvey S., II; Berke, E. William; and Erwin, Gary B., 5,588,398, Cl. 119-822.000.

Esaki, Kunihito: See—
Yamamura, Takaya; and Esaki, Kunihito, 5,589,801, Cl. 331-14.000.

Eshima, Shigeo: See—
Shibata, Hideyo; Kinoshita, Ritsuro; Yoshida, Takayasu; and Eshima, Shigeo, 5,589,992, Cl. 386-72.000.

Eskin, Bernard A., and Ghent, R. Alison, to 943038 Ontario, Inc., and Eskin, Bernard A. Treatment of iodine deficiency diseases. 5,589,198, Cl. 424-667.000.

Essaff, Robert: See—
Nelson, Carl T., and Essaff, Robert, 5,589,761, Cl. 323-285.000.

Essex, Timothy J. II: See—
Byrne, Phillip O., and Essex, Timothy J. H., 5,588,437, Cl. 128-691.000.

Esteban, Almudena R.: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoepf, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.

Estelle, Lee R., and Goosey, William T., Jr., to Eastman Kodak Company. Compact objective lens system. 5,589,989, Cl. 359-785.000.

Estes, H. Scott, to Dell USA, L.P. Circuit board SMT device mounting apparatus. 5,590,029, Cl. 361-760.000.

Ethicon Endo-Surgery, Inc.: See—
Conlon, Sean P.; Oueshi, Saleem U.; Hibner, John A.; Okorocho, Livyn O., and Bishop, Gregory D., 5,588,581, Cl. 227-176.100.
Paul, Michel A., and Gutierrez, Jorge, 5,588,580, Cl. 227-176.100.

Etoh, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirotsugu; Sakumura, Tomoo; Suzuki, Tomoko; and Kinoshita, Akira, to Konica Corporation. Image forming method using an imidazole-*perylene* electro-photographic photoreceptor. 5,589,314, Cl. 430-126.000.

Euro-Matic Ltd.: See—
Davis, Howard P., and Ruff, Wolfram, 5,588,986, Cl. 95-211.000.

Eurocopter France: See—
Commielin, Sylvie J., and Mondet, Jean J., 5,588,801, Cl. 416-46.000.
Marze, Henri-James R.; Routhieu, Vincent Jean-Luc; Arnaud, Gilles L., and Arnaud, Remy E., 5,588,618, Cl. 241-17.190.

Evans, Bruce A.: See—
Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amin, Bijan; Webster, John R., and Evans, Bruce A., 5,589,032, Cl. 162-76.000.

Evans, Everett: See—
Visocky, Joseph E., and Evans, Everett, 5,588,238, Cl. 40-618.000.

Evans, Joseph D.: See—
Hammond, Mark S., and Evans, Joseph D., 5,588,975, Cl. 51-293.000.

Evans, Rowland F. Temperature regulating system, method and apparatus. 5,589,114, Cl. 264-40.600.

Even, Luc: See—
Jegham, Samir; Defosse, Gérard; Purcell, Thomas A., and Even, Luc, 5,589,476, Cl. 514-230.200.

Everbrite, Inc.: See—
Visocky, Joseph E., and Evans, Everett, 5,588,238, Cl. 40-618.000.

Evergreen Group Incorporated, The: See—
Ryan, Raymond B., and Gans, Noah F., 5,590,037, Cl. 395-204.000.

Every, Inc.: See—
Kalina, Alexander I., and Mroli, Mark D., 5,588,298, Cl. 60-676.000.

Exponent Italia S.r.l.: See—
D'Agaro, Amos; Marino, Adriano; and Venturini, Andrea, 5,588,727, Cl. 312-283.000.

Exxon Chemical Patents Inc.: See—
Patil, Abhimanyu O.; and Femino, Frank, 5,588,972, Cl. 44-312.000.

Exxon Research and Engineering Company: See—
Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eiger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127.900.

Extra Corporation: See—
Sierfinger, Michael, 5,589,900, Cl. 396-548.000.

Ezaki, Tadashi, to Sony Corporation. Multistandard decoder for data stored in the vertical blanking interval of a video signal. 5,589,886, Cl. 348-461.000.

Fabricius, Norbert: See—
Wolf, Barbara; and Fabricius, Norbert, 5,590,226, Cl. 385-45.000.

Fabrik Produktionsaktieselskaf Leo Pharmaceutical Products Ltd.: See—
Hansen, Kai; and Bretting, Claus Aage S., 5,589,471, Cl. 514-167.000.

Fahlen, Theodore S.; Duboc, Robert M., Jr.; and Lovoi, Paul A., to Silicon Video Corporation. Internal support structure for flat panel device. 5,589,731, Cl. 313-495.000.

Fahman, Hal, to Fleetwood Enterprises, Inc. Convertible table configurable between expanded and compressed positions. 5,588,377, Cl. 108-145.000.

Fain, John: See—
Lerner, Ruth, and Fain, John, 5,588,287, Cl. 53-588.000.

Fairhurst, Stephen: See—
Terman, Michael; Fairhurst, Stephen; Hughes, Philip, and Levin, Joel, 5,589,741, Cl. 315-360.000.

Fairweather, Neil F.: See—
Lipscombe, Martin J.; Charles, Ian G.; and Fairweather, Neil F., 5,589,384, Cl. 435-252.330.

Faklis, Dean, and Morris, G. Michael, to Rochester Photonics Corporation. Polychromatic diffractive lens. 5,589,982, Cl. 359-565.000.

Falandino, Michael P.: See—
Korwicki, Allan J.; Doering, Jeffrey A., and Falandino, Michael P., 5,588,417, Cl. 123-697.000.

Falcon, William C. Hair roller apparatus and method for highlighting hair. 5,588,449, Cl. 132-208.000.

Falia, Horacio C., and Rojas, Carlos I., to Comesi S.A.I.C. Method for preserving rollers immersed into the molten alloy bath for extending the operating life thereof. 5,589,227, Cl. 427-348.000.

Fan, John C. C.: See—
Bozler, Carl O.; Fan, John C. C., and McClelland, Robert W., 5,588,994, Cl. 117-89.000.

Fang, Zhigang: See—
Denton, Robert M.; and Fang, Zhigang, 5,589,443, Cl. 508-150.000.

Fantini, Susan E.: See—
Ryan, Michael J.; Lotvin, Jason A.; Strathy, Nancy; and Fantini, Susan E., 5,589,385, Cl. 435-258.350.

Fantone, Stephen D.; Gelardi, Anthony L., and Gelardi, John A., to Insight, Inc. Flat box system with multiple view optics. 5,588,526, Cl. 206-308.100.

Fantone, Stephen D., to Moli Corporation. Dual-path optical system. 5,589,978, Cl. 359-412.000.

Fanuc Ltd.: See—
Idei, Takashi; Sagara, Shochi; and Fujibayashi, Kentaro, 5,589,750, Cl. 318-573.000.

Fanuc, Ryo, Terada, Akihiro; and Kurebayashi, Hidenori, 5,588,328, Cl. 74-409.000.

Onishi, Yasushi; and Saiki, Yoshihito, 5,590,253, Cl. 395-133.000.

Sawada, Kiyoshi; and Odaka, Shun'ichi, 5,589,086, Cl. 219-69.160.

Farchi, David: See—
Agar, Joram; and Farchi, David, 5,589,642, Cl. 73-861.040.

Farison, Brian K., and Armstrong, William R., to Sealed Air Corporation. Inflatable packaging cushion. 5,588,533, Cl. 206-522.000.

Farmont, Hans, to Farmont Technik GmbH & Co. KG. Issuing device for disc-shaped parking tickets. 5,588,553, Cl. 221-76.000.

Farmont Technik GmbH & Co. KG: See—
Farmont, Hans, 5,588,553, Cl. 221-76.000.

Farnos, Maria D.; McWilliams, John P.; Sharma, Sanjay B., and Shihabi, David S., to Mobil Oil Corporation. Catalytic system for the reduction of nitrogen oxides. 5,589,147, Cl. 423-239.200.

Farnstrand, Per-Åke; Sjodin, Lars T.; Lindström, Lars-Åke; and Norden, K. Solberg E., to Sundy Defibrator Industries Aktiebolag. Chlorine dioxide bleaching of chemical pulp. 5,589,031, Cl. 162-65.000.

Farooq, Omar: See—
Ali, Mahfuz B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G., 5,589,269, Cl. 428-411.100.

Farr, Spencer B., to President and Fellows of Harvard College. The Methods and diagnostic kits for determining toxicity utilizing bacterial stress promoters fused to reporter genes. 5,589,337, Cl. 435-6.000.

Farside, Nicholas, to Kerr Group, Inc. Closure with stay-open lid. 5,588,546, Cl. 215-237.000.

Farzin-Nia, Farrokh, to Ormco Corporation. Method of fabricating metal instruments from raw material and orthodontic pliers made thereby. 5,588,832, Cl. 433-4.000.

Fasano, Alessio; Levine, Myron M.; Nataro, James P., and Noriega, Fernando, to University of Maryland at Baltimore. Isolated DNA molecule encoding SHET1 of *Shigella flexneri* 2a and mutant *Shigella flexneri* 2a. 5,589,380, Cl. 435-252.300.

East, Bruce B., and Allen, Dana R. OCR image preprocessing method for image enhancement of scanned documents by correction of registration. 5,590,224, Cl. 382-291.000.

Fauteux, Denis G.; Massucco, Arthur A.; Wilkins, Ronnie D., and Shi, Jie, to Arthur D. Little, Inc. Current collector device and method of manufacturing same. 5,588,971, Cl. 29-623.500.

Fauteux, Denis G.; Massucco, Arthur A.; and Wilkins, Ronnie D., to Arthur D. Little, Inc. Small particle electrodes by aerosol process. 5,589,300, Cl. 429-218.000.

Favia, Anthony R.: See—
Knee, Robert A.; Favia, Anthony R.; Davis, Bruce; and Miller, Larry, 5,589,892, Cl. 348-731.000.

Fearnot, Neal E.: See—
Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Goode, Louis; and Fearnot, Neal E., 5,588,436, Cl. 128-662.030.

Feeman, James F.: See—
Beach, Bradley L.; Feeman, James F.; Pearson, Anna M.; and Sun, Jing X., 5,589,522, Cl. 523-160.000.

Feher, Frank J.: See—
Lichtenhan, Joseph D.; Vu, Ngo Quang; Gilman, Jeffrey W.; and Feher, Frank J., 5,589,562, Cl. 528-9.000.

Fehnel, Michael D., to Ericsson Inc. Systems and methods for generating a current time of day in a cellular radiotelephone. 5,590,092, Cl. 368-10.000.

Feith, Bernhard H.: See—
Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., 5,589,534, Cl. 524-548.000.

Feldhaus, Reinhard, to Fichtel & Sachs AG. Clutch disc with a reinforced hub. 5,588,518, Cl. 192-204.000.

Feldmeier, Günter, and Schrettinger, Christian, to Whitaker Corporation. The Centering spring support for panel mount connectors. 5,588,857, Cl. 439-248.000.

Feldmeier, Günter: See—
Götz, Klaus P.; Schaarschmidt, Manfred; and Feldmeier, Günter, 5,588,885, Cl. 439-876.000.

Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., to Vical Incorporated; and Wisconsin Alumni Research Foundation. Induction of a protective immune response in a mammal by injecting a DNA sequence. 5,589,466, Cl. 514-44.000.

Felix, Augustus: See—
Cunningham, Robert W.; Koch, Durmus; Mura, Janine R.; Felix, Augustus; and Halick, Gary V., 5,588,958, Cl. 604-4.000.

Felix, Bernd; Hintzer, Klaus; Löhr, Gernot; and Schöttle, Thomas, to Hoechst Aktiengesellschaft. Process for the preparation of modified polytetrafluoroethylene and its use. 5,589,558, Cl. 526-247.000.

Felix, Kenneth A.: See—
Lodwig, John P.; Felix, Kenneth A.; and Whittington, Charles L., 5,590,172, Cl. 379-58.000.

Felsomat GmbH & Co KG: See—
Jäger, Helmut F.; Peschina, Jürgen; and Dietrich, Bernard, 5,588,795, Cl. 414-733.000.

Feltz, Kristi T.: See—
Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.

Femino, Frank: See—
Patil, Abhimanyu O.; and Femino, Frank, 5,588,972, Cl. 44-312.000.

Feng, Chan-Hua: See—
Huang, Jack; Chiang, Chung-Ping; and Feng, Chan-Hua, 5,588,331, Cl. 74-489.000.

Feng, Guofu J.: See—
Law, Kam; Robertson, Robert; and Feng, Guofu J., 5,589,233, Cl. 427-579.000.

Fenster, Valerie: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.

Ferdani, Philip: See—
Fisher, Ian A.; and Ferdani, Philip, 5,588,209, Cl. 29-897.200.

Ferguson, Patrick L.: See—
Thayer, John S., and Ferguson, Patrick L., 5,590,378, Cl. 395-850.000.

Ferguson, Robert I.: See—
Zbikowski, Mark; Berkowitz, Brian T.; and Ferguson, Robert I., 5,590,318, Cl. 395-618.000.

Feng, Shing-Lai. Solar power-operated cooling system for motor vehicles. 5,588,909, Cl. 454-141.000.

Ferro, Adolph J.; Bestwick, Richard K.; and Brown, Lyle R., to Agritope, Inc. Genetic control of ethylene biosynthesis in plants. 5,589,623, Cl. 800-205.000.

Ferro (Italia) S.r.l.: See—
Thometzek, Peter; and Christ, Heinrich, 5,589,222, Cl. 427-215.000.

Fetty, Mark W. K., to Brenco, Incorporated. Bearing and journal assembly. 5,588,752, Cl. 384-477.000.

Feuerstake, Eugen: See—
Schleicher, Ulrich; Klobner, Martin; Schwarz, Wolfgang; and Feuerstake, Eugen, 5,589,662, Cl. 149-35.000.

FEV Motorentechnik GmbH & Co.: See—
Fetty, Mark W. K., to Brenco, Incorporated. Bearing and journal assembly. 5,588,752, Cl. 384-477.000.

FEV Motorentechnik GmbH & Co. KG: See—
von Essen, Mathias; Bollig, Christoph; and Bick, Werner, 5,588,407, Cl. 123-192.200.

Fichtel & Sachs AG: See—
Arbeiter, Markus; and Weishaupt, Christian, 5,588,925, Cl. 474-81.000.

Feldhaus, Reinhard, 5,588,518, Cl. 192-204.000.

Fiechtner, Michael D.; Ramp, John M.; England, Barbara J.; and Annino, Mary J., to Abbott Laboratories. Method for preparing a glycated hemoglobin solution. 5,589,393, Cl. 436-15.000.

Field, Frederic P.: See—
Sancoff, Gregory E.; Doyle, Mark C.; and Field, Frederic P., 5,588,556, Cl. 222-1.000.

Field, Gary: See—
Schofield, Harry; Caron, Paul; Field, Gary; and Follett, Paul, 5,589,868, Cl. 347-171.000.

Fields, Gene M.: See—
Hill, Joe T.; Fields, Gene M.; and Williams, John R., 5,588,820, Cl. 418-55.400.

Fiene, Uwe: See—
Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709.000.

Fijitsu Limited: See—
Hoshino, Masataka; and Misawa, Nobuhiro, 5,589,425, Cl. 427-250.000.

Filges, Ralf: See—
Stahl, Hans-Juergen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, 5,588,829, Cl. 432-77.000.

Filippi, John E.; and Golen, John A. Thermal barrier for an exhaust system. 5,589,144, Cl. 422-179.000.

Filterwerk Mann & Hummel GmbH: See—
Becker, Achim; and Zlotos, Michael, 5,588,225, Cl. 34-474.000.

Fina Technology, Inc.: See—
Razavi, Abbas, 5,589,556, Cl. 526-170.000.

Finger, Gary E., to Artercraft Wire Works, Inc. Adjustable shelving system. 5,588,543, Cl. 211-90.000.

Fink, Thomas M. Rotatable composting device. 5,589,391, Cl. 435-290.300.

FireKing International, Inc.: See—
Osborne, Shelby M., 5,588,318, Cl. 70-469.000.

Firma Carl Freudenberg: See—
Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000.

Firma G. B. Boucherie, naamloze vennootschap: See—
Boucherie, Leonel P., 5,588,714, Cl. 300-21.000.

Firooz, Kamran, to Hewlett-Packard CO. Method for creating an in-circuit test for an electronic device. 5,590,136, Cl. 371-25.100.

Firoozabady, Ebrahim; Lemieux, Christine; Moll, Benjamin A.; and Robinson, Karol, to Florigene Europe B.V. Carnation plants and methods for their transformation and propagation. 5,589,613, Cl. 800-205.000.

First Medical, Inc.: See—
Allen, Michael P.; Zuk, Robert F.; and Ensler, Lawrence M., 5,589,399, Cl. 436-169.000.

First Technology Safety Systems, Inc.: See—
Viano, David C.; Jedrzejczak, Edward A.; and Smrcka, Joseph G., 5,589,651, Cl. 73-866.400.

Fischer, Gerd: See—
Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228.000.

Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürsen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., to Bayer Aktiengesellschaft. Substituted 1H-3-aryl-pyrrolidine-2,4-dione derivatives. 5,589,469, Cl. 514-91.000.

Fischer, Roger: See—
Hoeltke, Larry; and Fischer, Roger, 5,588,221, Cl. 34-58.000.

Fischer, Rolf; Dostalek, Roman; and Marosi, Laszlo, to BASF Aktiengesellschaft. Preparation of cyclohexene by partial hydrogenation of benzene. 5,589,600, Cl. 585-266.000.

Fiset, Peter D. Card out of socket detector for IC cards. 5,589,719, Cl. 307-131.000.

Fisher & Paykel Limited: See—
Smith, Malcolm D., 5,588,423, Cl. 128-203.260.

Fisher, Ian A.; and Ferdani, Philip, to Tempered Spring Company Limited. The Method and apparatus to manufacture stabilizer bars. 5,588,209, Cl. 29-897.200.

Fisher, John F.: See—
Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clold R., III, 5,589,630, Cl. 73-23.350.

Fisher, Michael H.: See—
Schmidt, Christopher G.; Fisher, Michael H.; de Almeida, Amilton F.; and Tani, Edson T., 5,588,731, Cl. 312-405.000.

Fishman, Henry. Allergy testing apparatus with variably spaced test using sites. 5,588,441, Cl. 128-743.000.

Fishman, Norman: See—
Merz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, 5,589,520, Cl. 521-64.000.

Fister, Dietmar: See—
Spiegel, Leo; and Pischinger, Franz, 5,588,504, Cl. 184-6.800.

Fitting, Dale W.: See—
Siewert, Thomas A.; Dubé, William P.; and Fitting, Dale W., 5,589,690, Cl. 250-390.060.

Flag, Charles M.: See—

- Krein, William T.; Flaig, Charles M.; and Kelly, James D., 5,590,130, Cl. 370-462,000.
- Flash Comm, Inc.: *See—*
- Belcher, Donald K.; and Bailey, David C., 5,589,844, Cl. 343-860,000.
- Flavin, James M., and Flavin, Myra E.: Eyelet threader, 5,588,568, Cl. 223-99,000.
- Flavin, Myra E.: *See—*
- Flavin, James M.; and Flavin, Myra E., 5,588,568, Cl. 223-99,000.
- Fleck, John A., to Champion International Corporation: Controlling pulp flow in an upflow pulp treatment tower, 5,589,036, Cl. 162-246,000.
- Flecksteiner, Richard J.: *See—*
- Manley, Paul E.; and Flecksteiner, Richard J., 5,589,550, Cl. 525-282,000.
- Fleetwood Enterprises, Inc.: *See—*
- Fahman, Hal, 5,588,377, Cl. 108-145,000.
- Hemming, Eckardt; Tilch, Werner; Schusztel, Thomas; Ivanov, Marian; and Eirich, Paul, to Maschinenfabrik Gustav Eirich: Apparatus and method for defining molding technological properties of molding substances in casting works, 5,589,650, Cl. 73-866,000.
- Fletcher, Robert L.; and Ruuska, Gregory V., to Atlantic Richfield Company: Training and certification system and method, 5,590,057, Cl. 364-551,010.
- FLEXcon Company, Inc.: *See—*
- Skov, Richard T.; and Pennace, John R., 5,588,679, Cl. 283-67,000.
- Flik, Gottfried: *See—*
- Benz, Gerhard; Flik, Gottfried; Treutler, Christoph; and Friedrich, Heinz, 5,588,466, Cl. 137-831,000.
- Flinchbaugh, Bernadette M.; Gabany, Andrew J.; Melnyk, Adrian L.; and Schmid, Christopher J., to Whitaker Corporation: The Electrical receptacle assembly and spring contact therefor, 5,588,878, Cl. 439-682,000.
- Flinner, John: Humane rodent trap, 5,588,249, Cl. 43-61,000.
- Flint, Herman: *See—*
- Frank, Lawrence A.; Harman, Galen B.; and Flint, Herman, 5,588,345, Cl. 83-95,000.
- Florigne Europe B.V.: *See—*
- Firoozabady, Ebrahim; Lemieux, Christine; Moll, Benjamin A.; and Robinson, Karol, 5,589,613, Cl. 800-205,000.
- FMC Corporation: *See—*
- Lotto, Ronald L.; Teske, Ernest H.; and Hatchell, Peter, 5,588,644, Cl. 271-183,000.
- Focke & Co. (GmbH & Co.): *See—*
- Focke, Heinz; and Brethauer, Hans-Jürgen, 5,588,286, Cl. 53-575,000.
- Focke, Heinz; and Brethauer, Hans-Jürgen, to Focke & Co. (GmbH & Co.): Folding device, especially folding turret, with folding mandrel, 5,588,286, Cl. 53-575,000.
- Fold-Pak Corporation: *See—*
- DeMay, Karl F., 5,588,584, Cl. 229-132,000.
- Folkers, Joie L., to Ametron International Corporation: Push-pull pipe joint, 5,588,685, Cl. 285-94,000.
- Follett, Paul: *See—*
- Schofield, Harry; Caron, Paul; Field, Gary; and Follett, Paul, 5,589,868, Cl. 347-171,000.
- Fondation Nationale de Transfusion Sanguine: *See—*
- Pages, Itienne; Ropars, Claude; and Bailleul, Christophe, 5,589,389, Cl. 435-306,100.
- Forcier, Mitchell D.: Script character processing method and system with bit mapped document editing, 5,590,257, Cl. 395-792,000.
- Ford, George W., Jr.; Lambert, Richard C.; and Madsen, Russell G., to Covol Technologies, Inc.: Process for recovering iron from iron-containing material, 5,589,118, Cl. 264-122,000.
- Ford Motor Company: *See—*
- Heckler, Gregory T., 5,588,332, Cl. 74-493,000.
- Holka, Thomas C., 5,588,482, Cl. 165-44,000.
- Hutter, Robert J.; Martin, Christopher J.; and Roesner, Thomas W., 5,588,910, Cl. 454-154,000.
- Kowicki, Allan J.; Doering, Jeffrey A.; and Falandino, Michael P., 5,588,417, Cl. 123-697,000.
- Panyard, James R., 5,588,794, Cl. 414-729,000.
- Stiles, Ernest D.; and Hanscock, Dale L., 5,589,241, Cl. 428-36,900.
- Foreman, Kevin G.; Miller, Paul J.; and Siska, Steven M., to TRW Inc.: Battery monitor for unobtrusive installation with a battery connector, 5,590,058, Cl. 364-551,010.
- Forestier, Guy, to Clecim: Process for melting scrap iron in an electric furnace and installation for implementing the process, 5,590,151, Cl. 373-72,000.
- Fork, Werner, to J.M. Voith GmbH: Rotating machine part, in particular a rotor of a cycloid ship's propeller, 5,588,798, Cl. 415-111,000.
- Forman, Andrew L.: *See—*
- Venkataramani, Edamanal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182,110.
- Fornet, Pierre: *See—*
- Glaser, Josef; and Fornet, Pierre, 5,589,638, Cl. 73-706,000.
- Forni, William R., and Kaylor, Scott A., to Motorola, Inc.: Equalizer circuit and a method for equalizing a continuous signal, 5,590,154, Cl. 375-229,000.
- Forster, Franz, to Linde Aktiengesellschaft: Planetary reducer and wheel bearing unit, 5,588,931, Cl. 475-338,000.
- Fortier, Robert L.: Adjustable bicycle rear axle support assembly, 5,588,662, Cl. 280-288,000.
- Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergamin, Mirco; and Canil, Gilberto, to Nordica S.p.A.: Sports shoe with a reinforcing shell-frame, 5,588,228, Cl. 36-118,200.
- Foss, Margit: *See—*
- Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6,000.
- Foss, Richard J.: *See—*
- Harms, Michael R.; Foss, Richard J.; Trice, Jennifer L.; and Neavin, Terence D., 5,589,000, Cl. 118-715,000.
- Foster, George: *See—*
- Rudell, Elliot; and Foster, George, 5,588,647, Cl. 473-470,000.
- Foster-Miller, Inc.: *See—*
- Fusco, Thomas M.; Magee, Constance; and Freitas, Glenn, 5,589,015, Cl. 156-73,100.
- Foster, Randall M.: *See—*
- Foster, Raymond K.; and Foster, Randall M., 5,588,522, Cl. 198-775,000.
- Foster, Raymond K.; and Foster, Randall M., to Raymond Keith Foster: Reciprocating floor conveyor for conveying palletized loads or the like, 5,588,522, Cl. 198-775,000.
- Foster, Robert B., Jr.: *See—*
- Deutsch, Brian M.; and Foster, Robert B., Jr., 5,590,410, Cl. 455-76,000.
- Fouser, John P.: *See—*
- Mertz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, 5,589,520, Cl. 521-64,000.
- Fowler, David N.: *See—*
- Schnut, Robert H.; Robertson, John C.; Gallagher, Richard J.; and Fowler, David N., 5,588,579, Cl. 227-175,100.
- Fox, Michael J.: *See—*
- Licht, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydeis, Ronald A.; and Fox, Michael J., 5,588,404, Cl. 123-90,170.
- Fox, Siegfried; and Keil, Andreas, to Palitex Project Company GmbH: Device for change-over switching of individual electric motors or groups of electric motors, 5,590,019, Cl. 361-643,000.
- Foxboro Company, The: *See—*
- Fung, Clifford D., 5,589,810, Cl. 338-4,000.
- Fraenkel, Itael: *See—*
- Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Atef, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Framatome Connectors International: *See—*
- Morlion, Danny; Jonckheere, Luc; and van Koetssem, Jan P. K., 5,588,851, Cl. 439-108,000.
- France Telecom Etablissement Autonome de Droit Public: *See—*
- Auffret, René, 5,589,967, Cl. 359-123,000.
- Francies, Sidney E., III: *See—*
- Kelly, David L.; and Francies, Sidney E., III, 5,588,263, Cl. 52-125,400.
- Francis, William C.: *See—*
- Schwan, Fred W.; and Francis, William C., 5,588,645, Cl. 473-456,000.
- Frank, Carmella L.: Decorative multi-purpose emergency cabinet, 5,588,725, Cl. 312-245,000.
- Frank, Patrick M.: *See—*
- Sanford, James R. M.; Frank, Patrick M.; Golias, Joseph H.; and Jennings, William C., 5,589,063, Cl. 210-198,200.
- Frank, Paul A.; McGrath, Donald T.; and Staver, Daniel A., to General Electric Company: Field-testable integrated circuit and method of testing, 5,589,766, Cl. 324-158,100.
- Frankel, Rose J.: *See—*
- Liao, Frank Y.; Rule, Antoinette; Frankel, Rose J.; Bickle, Thomas W.; and Bish, Sandra L., 5,590,186, Cl. 379-210,000.
- Franklin Brass Manufacturing Company: *See—*
- Sharpe, Norton, 5,588,627, Cl. 242-599,000.
- Franklin, Kenneth A.: *See—*
- Cortjens, Leo M.; Franklin, Kenneth A.; Mays, Richard C.; and Smith, Curtis M., 5,589,878, Cl. 348-211,000.
- Franks, Lawrence A.; Harman, Galen B.; and Flint, Herman, to Burr Oak Tool & Gauge Company: Fin sheet control apparatus for press, 5,588,345, Cl. 83-95,000.
- Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V.: *See—*
- Menke, Klaus; Böhlein-Maass, Jutta; Schmid, Helmut; Bucerius, Klaus M.; and Engel, Walther, 5,589,661, Cl. 149-19,400.
- Fraysher, Mary A.: Manicure device, 5,588,453, Cl. 132-76,400.
- Frechet, Jean M. J.: *See—*
- Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J., 5,589,537, Cl. 524-780,000.
- Frederick, Kevin W.: *See—*
- Hunter, Wood E.; Frederick, Kevin W.; and Loeffler, Randy J., 5,589,525, Cl. 523-331,000.
- Freitas, Glenn: *See—*
- Fusco, Thomas M.; Magee, Constance; and Freitas, Glenn, 5,589,015, Cl. 156-73,100.
- French, Leon D.: Universal cavitation plate system, 5,588,390, Cl. 114-274,000.
- Fresenius AG: *See—*
- Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeyer, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560,000.
- Freudenberg, Carl: *See—*
- Derksen, Klaus, 5,588,547, Cl. 215-247,000.

- Freudenberg-NOK General Partnership: *See—*
- Bowell, Richard A., Sr., 5,588,350, Cl. 92-192,000.
- Freund Industrial Co., Ltd.: *See—*
- Yamada, Shun; Ogawa, Masanori; and Unosawa, Kazuomi, 5,589,225, Cl. 427-212,000.
- Friedman, William A.: *See—*
- Bova, Frank J.; and Friedman, William A., 5,588,430, Cl. 128-653,100.
- Friedrich Grohe Aktiengesellschaft: *See—*
- Eichholz, Heinz-Dieter; and Rudrich, Hans-Peter, 5,588,636, Cl. 251-129,040.
- Friedrich, Heinz: *See—*
- Benz, Gerhard; Flik, Gottfried; Treutler, Christoph; and Friedrich, Heinz, 5,588,466, Cl. 137-831,000.
- Friedrichs, Jens; and Helmstädter, Karl-Heinz, to Heidelberger Druckmaschinen AG: Device for connecting a machine element to a structural member movable about its longitudinal axis so that the machine element and the structural member are secured against relative rotation, 5,588,773, Cl. 403-373,000.
- Fritsche, Klaus-Dieter: *See—*
- Dorbath, Bernd; Giesecke, Norbert; and Fritsche, Klaus-Dieter, 5,589,273, Cl. 428-433,000.
- Fritz Gegauf AG Bernina Nähmaschinenfabrik: *See—*
- Schneider, Werner; Lerch, Hansuel; and Hausmann, Erich, 5,588,938, Cl. 482-4,000.
- Fromme, Heinrich, to Senne Lizen/ & Produkte GmbH: Cushioning assembly having plastic springs for supporting a pad, 5,588,165, Cl. 5-247,000.
- Frost, John H.: Hand accessory for swinging an implement handle, 5,588,651, Cl. 473-206,000.
- Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Moller, Karin, to Sandia Corporation: Coatings with controlled porosity and chemical properties, 5,589,396, Cl. 436-73,000.
- Frye, Ricky J.; Motts, Jon T.; and Rufenner, Ron, to MIM Industries, Inc.: Process of inverting an article or air bag, 5,589,113, Cl. 264-40,500.
- Fu, Jenny: *See—*
- Payne, Jewel; Narva, Kenneth E.; and Fu, Jenny, 5,589,382, Cl. 435-252,500.
- Fu, Peter: *See—*
- Rohman, Mizanur M.; Sabermick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735,000.
- Fucell Pty Limited: *See—*
- Coster, Hans G. L.; Ashcroft, Robert G.; and Mahaworasitpa, Tohsak, 5,589,047, Cl. 204-450,000.
- Fuchs, Wesley K.; Huang, Yennun; and Wang, Yi-Min, to Lucent Technologies Inc.: Progressive retry method and apparatus for software failure recovery in multi-process message-passing applications, 5,590,277, Cl. 395-183,140.
- Fudo, Takashi: *See—*
- Ishihara, Manabu; Rakuma, Tsuyoshi; Kanai, Hiroshi; Fudo, Takashi; and Watanabe, Masato, 5,588,589, Cl. 236-46,000.
- Fuhr, Martin: *See—*
- Ubrich, Horst; and Fuhr, Martin, 5,588,194, Cl. 28-194,000.
- Fuji-Danisco Chemical Ltd.: *See—*
- Kano, Jiro; Omi, Ryuji; Borinouchi, Yuzo; and Ito, Mutsuhiro, 5,589,150, Cl. 423-338,000.
- Fuji Electric Co., Ltd.: *See—*
- Iwata, Tomo; 5,589,286, Cl. 429-34,000.
- Kitamura, Shoji; Shindo, Yoichi; and Amano, Akira, 5,590,144, Cl. 372-36,000.
- Kogawa, Kunyuki; and Takaya, Koetsu, 5,589,809, Cl. 337-36,000.
- Sugata, Yoshinobu; Yamazaki, Mikio; and Umegaki, Takashi, 5,589,860, Cl. 347-20,000.
- Uchida, Naoshi; Miura, Masao; Osama, Jun; Kuboyama, Katsunori; and Asakawa, Koji, 5,589,672, Cl. 218-34,000.
- Fuji Immunopharmaceuticals Corp.: *See—*
- Ono, Mitsunori; Wada, Yumiko; Wu, Yanung; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kon-Ming, 5,589,510, Cl. 514-590,000.
- Fuji Machine Mfg. Co., Ltd.: *See—*
- Asai, Koichi; Matsumoto, Koso; and Muto, Yasuo, 5,588,195, Cl. 29-33,000.
- Takada, Yukinori; Kuno, Tokiyuki; Muto, Yasuo; and Asai, Koichi, 5,588,614, Cl. 242-538,200.
- Fuji Photo Film Co., Ltd.: *See—*
- Arai, Fumimori; and Igarashi, Takeshi, 5,589,347, Cl. 435-11,000.
- Horie, Seiji; Sano, Kenji; Suzuki, Nobuo; and Watarai, Shu, 5,589,312, Cl. 430-115,000.
- Kato, Eiichi; Momota, Makoto; and Ohishi, Hiroyuki, 5,589,308, Cl. 430-49,000.
- Kawaoka, Yoshiki, 5,589,889, Cl. 348-674,000.
- Kuno, Koichi; and Suga, Shuzo, 5,589,325, Cl. 430-576,000.
- Matsuda, Shimichi, 5,589,321, Cl. 430-432,000.
- Saito, Kenji; and Shinkai, Yasuhiro, 5,589,879, Cl. 348-223,000.
- Watanabe, Mikio; Aoki, Akira; and Saito, Osamu, 5,590,306, Cl. 395-442,000.
- Fuji Photo Optical Co., Ltd.: *See—*
- Saito, Tatsuo; and Goto, Shigenori, 5,589,910, Cl. 396-106,000.
- Fuji Xerox Co., Ltd.: *See—*
- Akashi, Ryojiro; Morikawa, Takashi; Nnoniya, Masanobu; and Uematsu, Takashi, 5,589,237, Cl. 428-1,000.
- Hongo, Kazuya; and Takimoto, Hitoshi, 5,588,991, Cl. 117-2,000.
- Hosoi, Kiyoshi; and Matsuda, Tsukasa, 5,589,259, Cl. 428-323,000.
- Sutoh, Masaki; and Fukunaga, Shinichiro, 5,589,916, Cl. 399-286,000.
- Fujibayashi, Kazuo: *See—*
- Shirashi, Akihiko; Fujibayashi, Kazuo; and Kuwabara, Tetsuo, 5,589,882, Cl. 348-340,000.
- Fujibayashi, Kentaro: *See—*
- Idet, Takashi; Sagara, Shoichi; and Fujibayashi, Kentaro, 5,589,750, Cl. 318-573,000.
- Fujii, Yozo: *See—*
- Ikunami, Yoshikazu; Minami, Satoshi; and Fujii, Yozo, 5,589,919, Cl. 399-262,000.
- Fujikawa, Hisayoshi: *See—*
- Noda, Koji; Fujikawa, Hisayoshi; Yamashita, Katsuji; and Taga, Yasunori, 5,589,733, Cl. 313-509,000.
- Fujiki, Masaru, to Glory Kiki Co., Ltd.: Hand injector gas fire extinguisher, 5,588,492, Cl. 169-11,000.
- Fujiki, Mikio, to Sony Corporation: On-screen display apparatus with sequentially displayed picture adjustment messages, 5,589,853, Cl. 345-150,000.
- Fujikiko Kabushiki Kaisha: *See—*
- Kataumi, Yoshimasa; and Takikawa, Yoshitiro, 5,588,330, Cl. 74-483,000.
- Fujikura, Tsuneo: *See—*
- Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, 5,589,883, Cl. 348-379,000.
- Fujimoto, Hiroshi, to Olympus Optical Co., Ltd.: Ultrasonic diagnostic apparatus presenting closely correlated ultrasonic image, 5,588,434, Cl. 128-660,070.
- Fujimoto, Masaya; and Yamamoto, Haruo, to Mira Industrial Co., Ltd.: Image forming apparatus that corrects input gray level-output gray level characteristic data such that output gray levels gradually increase with higher input gray levels near a boundary, 5,589,950, Cl. 358-455,000.
- Fujimoto, Shuzo: *See—*
- Sato, Yutaka; Morita, Koichi; Fujimoto, Shuzo; Ichihashi, Satoru; and Ohsawa, Koji, 5,588,208, Cl. 29-888,044.
- Fujinawa, Masaaki: *See—*
- Iguchi, Hiroaki; Kurosu, Yasuo; Fujinawa, Masaaki; Yokoyama, Yoshitiro; and Masuzaki, Hidetami, 5,590,317, Cl. 395-602,000.
- Fujinawa, Nobuhiro: *See—*
- Tazawa, Masashi; Fujinawa, Nobuhiro; Matsui, Kumiko; and Suzuki, Maki, 5,589,952, Cl. 358-498,000.
- Fujioaka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, to Canon Kabushiki Kaisha: Photovoltaic elements and process and apparatus for their formation, 5,589,007, Cl. 136-249,000.
- Fujisawa, Katsuhide; Tahara, Eiichi; and Hida, Tetsuya, to Nippon Rein Co., Ltd.: Laminated metal gasket with diverse bead height, 5,588,657, Cl. 277-180,000.
- Fujisawa, Masayuki: *See—*
- Kosuo, Yasuhiko; Matsumoto, Yoshiki; Fujisawa, Masayuki; and Nagatsu, Isao, 5,588,304, Cl. 62-340,000.
- Fujisawa, Teruhiko, to Seiko Epson Corporation: Wrist-type wireless instrument and antenna apparatus, 5,589,840, Cl. 343-718,000.
- Fujishiro, Yoshikazu; Ishigaki, Takaya; and Harada, Hiraoki, to TDK Corporation: Multilayer through type capacitor array, 5,590,016, Cl. 361-313,000.
- Fujita, Minoru: *See—*
- Ikeda, Yumi; and Fujita, Minoru, 5,590,039, Cl. 395-759,000.
- Fujita, Shigeru; and Sakai, Toshio, to Matsushita Electric Industrial Co., Ltd.: Television camera having variable lens iris/shutter based on position/rotational speed of camera, 5,589,875, Cl. 348-143,000.
- Fujitsu Limited: *See—*
- Abe, Tomohiko; Yasuda, Hiroshi; Sakamoto, Kiuchi; and Oae, Yoshitaka, 5,590,048, Cl. 364-489,000.
- Akagi, Takao; Yoshida, Masanobu; Ogawa, Yasuhide; Kasa, Yasushi; and Kawamura, Shomichi, 5,590,074, Cl. 365-185,220.
- Antake, Hirokazu; Kato, Masayuki; and Nakashima, Masato, 5,589,957, Cl. 359-23,000.
- Burgess, Dana J.; and Stubbs, Robert E., 5,590,369, Cl. 395-800,000.
- Harasawa, Shinichiro, 5,590,013, Cl. 361-187,000.
- Ito, Tsuneyori; Furukawa, Tsuyoshi; Jimbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiko; and Sugagawa, Tomoo, 5,590,001, Cl. 360-97,020.
- Ishibashi, Ryoichi; and Sekine, Katsumi, 5,590,132, Cl. 370-236,000.
- Ito, Tatsuya; Kawai, Masahito; and Yasukawa, Yoshitomo, 5,590,053, Cl. 364-499,000.
- Kawanoto, Masakazu, 5,590,298, Cl. 395-403,000.
- Kawata, Satoshi; Dohi, Masaji; Salachi, Yoichiro; and Daiku, Hiroshi, 5,589,687, Cl. 250-338,300.
- Kiuchi, Katsumi; Wakamatsu, Hiroaki; Suzuki, Fumitake; and Koshikawa, Takao, 5,589,262, Cl. 428-336,000.
- Matsushima, Hitoshi, 5,590,311, Cl. 395-500,000.
- Murakami, Masahiko; Matsuda, Masahiro; and Fukuyama, Noriyuki, 5,590,178, Cl. 379-96,000.
- Nakai, Yutaka, 5,589,683, Cl. 250-214,000.
- Nakata, Yasuyuki; Yabuki, Akihiko; Yoshida, Yutaka; and Nishimoto, Katsushi, 5,590,244, Cl. 395-95,000.
- Natori, Hiroaki; Takei, Hitoshi; Sano, Shoichi; and Tamuki, Shota, 5,589,873, Cl. 348-15,000.

- Ohtsuka, Masaoki; Yamakawa, Teruji; and Maruyama, Tetsuo, 5,590,096, Cl. 369-13.000.
- Sato, Noriaki; and Mieno, Fumitake, 5,589,410, Cl. 437-40.000.
- Shaniff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, 5,590,374, Cl. 395-829.000.
- Shirai, Takeshi; and Yagi, Wataru, 5,588,433, Cl. 128-660.050.
- Suzuki, Hiroaki, 5,589,133, Cl. 422-79.000.
- Takeshima, Taku; Noro, Masayuki; and Saito, Tomokatsu, 5,590,255, Cl. 395-141.000.
- Takezawa, Satoshi; Katagiri, Yoshimichi; Nakamura, Yasushige; and Sawatari, Norio, 5,589,313, Cl. 430-122.000.
- Yoneda, Norihiro; Ohba, Toshimitsu; Furuya, Reiko; and Shikata, Kiyotaka, 5,590,183, Cl. 379-142.000.
- Fujiwara, Kazuhito: See—
Tomikawa, Hideo; Matsuo, Hideo; and Fujiwara, Kazuhito, 5,588,357, Cl. 99-451.000.
- Fujiwara, Kazunobu: See—
Ogusu, Mikio; and Fujiwara, Kazunobu, 5,590,100, Cl. 369-32.000.
- Fujiwara, Takahiko: See—
Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, 5,589,883, Cl. 348-379.000.
- Fujiwara, Yoshio: See—
Ito, Kengo; Isaji, Kaori; Fujiwara, Yoshio; Isogai, Mitsuhiro; and Hida, Masanobu, 5,589,435, Cl. 503-227.000.
- Fukae, Kimitoshi: See—
Itoyama, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yuji; Toyomura, Fumitaka; and Ohtsuka, Takashi, 5,589,006, Cl. 136-248.000.
- Fukao, Masami: See—
Furutani, Atsushi; Hibi, Taku; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446.000.
- Fukase, Hisahiko: See—
Leadbeater, Darren J.; Kato, Heiji; and Fukase, Hisahiko, 5,588,479, Cl. 164-480.000.
- Fukatsu, Akira: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tahata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Fukaya, Takashi: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Fukuda, Hideki: See—
Osuka, Kenji; Fukuda, Hideki; and Arakawa, Satoshi, 5,589,148, Cl. 423-240.000.
- Fukuda, Masaru: to Yazaki Corporation. Connector with engagement checking structure, 5,588,872, Cl. 439-489.000.
- Fukui, Hiroshi: See—
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126.000.
- Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, 5,589,165, Cl. 424-78.030.
- Fukui, Mika: See—
Doi, Miwako; Fukui, Mika; Nishida, Ikiko; and Kato, Nobuko, 5,590,268, Cl. 395-326.000.
- Fukumura, Kagenori: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tahata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Fukunaga, Shinichiro: See—
Sutoh, Masaki; and Fukunaga, Shinichiro, 5,589,916, Cl. 399-286.000.
- Fukushima, Hisashi: See—
Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145.000.
- Murasawa, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi; and Hasegawa, Takashi, 5,589,926, Cl. 399-302.000.
- Fukushima, Yasuhiro: See—
Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru, 5,589,390, Cl. 435-307.100.
- Fukuya, Akiko: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.
- Fukuyama, Hajime: See—
Uryu, Katsuhiko; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, 5,589,516, Cl. 514-2.000.
- Fukuyama, Noriyuki: See—
Murakami, Masahiko; Matsuda, Masahiro; and Fukuyama, Noriyuki, 5,590,178, Cl. 379-96.000.
- Fukuyama, Sharon M.: See—
Guggenheim, Thomas L.; Fukuyama, Sharon M.; and Warner, Gregory L., 5,589,037, Cl. 203-35.000.
- Fukuzawa, Shinichi: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiro; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Fulks, Henry J.: See—
Benedict, Dale G.; Wilgus, Frank R.; Fulks, Henry J.; and Gagliardi, William T., 5,588,560, Cl. 222-106.000.
- Fuller, Bryan B.: to University Oklahoma, The Board of Regents of the. Pigmentation enhancer and method, 5,589,161, Cl. 424-59.000.
- Fuller, Joan: See—
Carlin, Richard T.; and Fuller, Joan, 5,589,291, Cl. 429-103.000.
- Fuller, John M.: See—
Carrier, Richard W.; and Fuller, John M., 5,589,257, Cl. 428-284.000.
- Fung, Clifford D.: to Foxboro Company, The. Semiconductor pressure sensor and related methodology with polysilicon diaphragm and single-crystal gage elements, 5,589,810, Cl. 338-4.000.
- Funk, David R.: See—
Seidl, Lon D.; and Funk, David R., 5,588,376, Cl. 108-106.000.
- Furness, Geoffrey M.: Early warning brake light system, 5,589,817, Cl. 340-467.000.
- Furtner, Josef: to Steiner Freizeitmöbel Gesellschaft m.b.H. & Co. KG. Container with swivelling sidewalls, 5,588,549, Cl. 220-7.000.
- Furukawa Electric Co., Ltd.: The: See—
Nakamura, Kazunori; and Tei, I. Kou, 5,589,975, Cl. 359-345.000.
- Furukawa, Tsuyoshi: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiro; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Furukawa, Yoshiki: See—
Atsumi, Toru; Kamijo, Yasuhiro; Furukawa, Yoshiki; and Matsumura, Naoki, 5,589,678, Cl. 235-472.000.
- Furumori, Kenji: See—
Chiba, Hiromi; and Furumori, Kenji, 5,588,250, Cl. 43-114.000.
- Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru, 5,589,390, Cl. 435-307.100.
- Furusawa, Akira: See—
Uchikawa, Kiyoshi; Suga, Takayuki; and Furusawa, Akira, 5,589,936, Cl. 356-345.000.
- Furutani, Atsushi; Hibi, Taku; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, to Sumitomo Chemical Company, Limited. Process for producing amines, 5,589,596, Cl. 564-446.000.
- Furuya, Okitsugu: See—
Naitoh, Takaki; and Furuya, Okitsugu, 5,588,845, Cl. 439-66.000.
- Furuya, Reiko: See—
Yoneda, Norihiro; Ohba, Toshimitsu; Furuya, Reiko; and Shikata, Kiyotaka, 5,590,183, Cl. 379-142.000.
- Furuya, Yukitsuna: See—
Sato, Toshifumi; and Furuya, Yukitsuna, 5,590,404, Cl. 455-53.100.
- Fusco, Thomas M.; Magee, Constance; and Freitas, Glenn, to Foster-Miller, Inc. Method and system for inserting reinforcing elements in a composite structure, 5,589,015, Cl. 156-73.100.
- Futaba Denshi Kogyo Kabushiki Kaisha: See—
Onodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Teruo; and Itoh, Shigeo, 5,589,738, Cl. 315-169.100.
- Fuyama, Moriaki: See—
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126.000.
- G.D. Societa' Per Azioni: See—
Boriani, Silvano; and Gamberini, Antonio, 5,588,281, Cl. 53-443.000.
- Gaál, József: See—
Magyar, Kálmán; Gaál, József; Sziráki, István; Lengyel, József; Szabó, Anna Z.; Mármarosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Kórmóczy, Péter, 5,589,513, Cl. 514-654.000.
- Gabany, Andrew J.: See—
Flinchbaugh, Bernadette M.; Gabany, Andrew J.; Melnyk, Adrian L.; and Schmid, Christopher J., 5,588,878, Cl. 439-682.000.
- Gacek, Michel: See—
Sandnes, Rolf W.; Undheim, Kjell; Gacek, Michel; and Vasilevskis, Janis, 5,589,595, Cl. 540-474.000.
- Gagliardi, William T.: See—
Benedict, Dale G.; Wilgus, Frank R.; Fulks, Henry J.; and Gagliardi, William T., 5,588,560, Cl. 222-106.000.
- Gagnebien-Cabanne, Françoise: See—
Aubert, Lucien; and Gagnebien-Cabanne, Françoise, 5,589,178, Cl. 424-401.000.
- Gaillard, Alain: See—
Winner, Hermann; and Gaillard, Alain, 5,588,718, Cl. 303-113.100.
- Galbiati, Paola: See—
Contiero, Claudio; Galbiati, Paola; and Zullino, Lucia, 5,589,405, Cl. 437-6.000.
- Galili, Naftali: See—
Mizrach, Amos; Galili, Naftali; and Rosenhouse, Giora, 5,589,209, Cl. 426-231.000.

- Galison Drilling (Proprietary) Limited: See—
Thorburn, Peter R., 5,588,497, Cl. 175-420.100.
- Galitsky, Alexander V.: See—
Kondratiev, Victor K.; Koupitchenko, Valery P.; Galitsky, Alexander V.; and Baehr, Geoffrey G., 5,590,413, Cl. 455-86.000.
- Gallagher, Richard J.: See—
Schnut, Robert H.; Robertson, John C.; Gallagher, Richard J.; and Fowler, David N., 5,588,579, Cl. 227-175.100.
- Gallant, John K.; and Donovan, Steven R., to MCI Communications Corporation. Method and system for enhanced call completion in telecommunications mobility applications, 5,590,175, Cl. 379-58.000.
- Gallivan, Timothy J.: See—
Moran, Stephen W.; Jackson, John R.; Gallivan, Timothy J.; and Loftfield, Richard E., 5,589,053, Cl. 205-698.000.
- Galloway, David: See—
Wentworth, Robert M.; Galloway, David; Cotney, Garland D.; and Webb, Brian A., 5,590,232, Cl. 385-92.000.
- Gamand, Patrice: See—
Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L.; and Gamand, Patrice, 5,589,777, Cl. 324-537.000.
- Gamberini, Antonio: See—
Boriani, Silvano; and Gamberini, Antonio, 5,588,281, Cl. 53-443.000.
- Gambo, Ruben A.: See—
Koltun, Anthony D.; Gamboa, Ruben A.; and Chimenti, Danette S., 5,590,325, Cl. 395-615.000.
- Gamou, Takaharu: See—
Hato, Kazuhito; Nikiura, Junji; Yasumoto, Eiichi; and Gamou, Takaharu, 5,589,287, Cl. 429-41.000.
- Gander, Eugen: See—
De Clercq, Ann; Krebbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205.000.
- Gandhi, Umesh N.; and Osmak, Douglas J., to General Motors Corporation. Push-out vehicle side door, 5,588,692, Cl. 296-146.700.
- Gannukhi, Mahesh N.: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kusmaul, Bradley C.; Gannukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200.020.
- Gans, Michael J.; and Yeh, Yu S., to Lucent Technologies Inc. Low distortion amplifier, 5,589,797, Cl. 330-149.000.
- Gans, Noah F.: See—
Ryan, Raymond B.; and Gans, Noah F., 5,590,037, Cl. 395-204.000.
- Garahi, Masood: See—
Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51.200.
- Garavan, Patrick J.: to Analog Devices, Inc. Low-voltage CMOS comparator, 5,589,785, Cl. 327-63.000.
- Garces, Juan M.; Miller, Dean M.; and Howard, Kevin E., to Dow Chemical Company. The. Synthesis of crystalline porous solids in ammonia, 5,589,153, Cl. 423-705.000.
- Garcia-Rameau, Eduardo: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickie; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242.400.
- García-Rubio, Luis H.; Bayona, Manuel; Potter, Robert; and Leparc, German, to University of South Florida. Spectrophotometric method and apparatus for the characterization of blood and blood types, 5,589,932, Cl. 356-39.000.
- Gardner, Robert M.: See—
White, Alan W.; Percy, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., 5,589,566, Cl. 528-286.000.
- Garg, Sanjiv: See—
Deosaran, Trevor A.; Garg, Sanjiv; and Iadonato, Kevin R., 5,590,295, Cl. 395-393.000.
- Garger, Stephen J.: See—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K., 5,589,367, Cl. 435-172.300.
- Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickie; Burns, David; and Hlozek, Robert J., to Union Carbide Chemicals & Plastics Technology Corporation. Process for absorption of mercaptans, 5,589,149, Cl. 423-242.400.
- Garner, William H.; and Wheeler, Larry A., to Allergan. Use of 2-substituted-thiazolidine-4-carboxylic acids for treatment of cataract, 5,589,464, Cl. 514-23.000.
- Garofalo, Giovanni, to HTM Sport S.p.A. Swimming fin, 5,588,890, Cl. 441-64.000.
- Garrison, Ronald R., to Wallace Computer Services, Inc. I D card intermediate and method, 5,589,025, Cl. 156-268.000.
- Garvin, Hugh L.: See—
Robinson, Klaus; and Garvin, Hugh L., 5,589,042, Cl. 204-192.340.
- Gary, Daniel, to L'Air Liquide Société Anonyme Pour l'Etude et l'Exploitation des Procédés Georges Claude. Process for the preparation of high-purity liquid nitrogen, 5,589,151, Cl. 423-351.000.
- Gas Research Institute: See—
Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704.000.
- Gaskins, Darius D.: See—
Parks, Terry J.; and Gaskins, Darius D., 5,590,338, Cl. 395-742.000.
- Gasquet, Jean-Claude: See—
Brassier, Marc; Gasquet, Jean-Claude; Segaud, Daniel; and Mauroy, Bernard, 5,589,730, Cl. 313-493.000.
- Gaughan, Kevin J.; and Zato, Thomas J., to Zenith Electronics Corporation. On-screen remote control of a television receiver, 5,589,893, Cl. 348-734.000.
- Gaukel, Kevin M.: See—
Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., 5,589,843, Cl. 343-820.000.
- Gaulmier, André, to Giat Industries. Electrical initiation device with contactor, 5,589,655, Cl. 89-1.814.
- Gautier, Jean Pierre; Verbo, Ulysse; and Perez Revilla, Miguel, to AlliedSignal Europe Services Techniques. Pneumatic booster, 5,588,346, Cl. 91-369.002.
- Gautier, Jean-Pierre; Verbo, Ulysse; and Gebauer, Maurice, to AlliedSignal Europe Services Techniques. Servo with enhanced safety, 5,588,349, Cl. 92-169.300.
- Gavin, Kimberly: See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryujii; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.
- Gay, David E., to General Motors Corporation. Annealed polymer-bonded soft magnetic body, 5,589,010, Cl. 148-306.000.
- GE Yokogawa Medical Systems, Limited: See—
Gohno, Makoto; and Honuchi, Tetsuya, 5,590,165, Cl. 378-18.000.
- Geatz, Michael W.: See—
Robinson, Donald G.; Geatz, Michael W.; and Corcoran, Michael J., 5,589,820, Cl. 340-572.000.
- Gebauer, Maurice: See—
Gautier, Jean-Pierre; Verbo, Ulysse; and Gebauer, Maurice, 5,588,349, Cl. 92-169.300.
- Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruns, Elke; Guntert, Dietwart; and Müller, Hubert, to Knecht Filterwerke GmbH. Filter for liquids, in particular internal-combustion engine lubricant oils, 5,589,060, Cl. 210-130.000.
- Gebhard, Angelika: See—
Neumueller, Maria; and Gebhard, Angelika, 5,588,706, Cl. 297-374.000.
- Gee, Jeffrey C.; Lawrie, Christophe J.; and Williamson, Roger C., to Chevron Chemical Company. Drilling fluids comprising mostly linear olefins, 5,589,442, Cl. 507-103.000.
- Gehani, Narain H.: See—
Biliris, Alexandros; Dar, Shaul; and Gehani, Narain H., 5,590,327, Cl. 395-670.000.
- Geigel, Alfred A.; and Keasler, William E., to Lucent Technologies Inc. Method and apparatus for adaptive filtering, 5,590,121, Cl. 370-290.000.
- Geiger, Jon R.; and Trotz, Samuel I., to Olin Corporation. Kit for separating double-stranded nucleic acid from a single-stranded/double-stranded mixture of nucleic acids, 5,589,342, Cl. 435-6.000.
- Geiler, Volkmar: See—
Donne, Mario Dalle; Schumacher, Guster; Geiler, Volkmar; Clement, Marc; and Speit, Burkhard, 5,589,427, Cl. 501-33.000.
- Geiwitz, Jürgen; Götschi, Erwin; Hebeisen, Paul; Link, Helmut; and Lübbers, Thomas, to Hoffmann-La Roche Inc. Mono- and bicyclic DNA gyrase inhibitors, 5,589,473, Cl. 514-183.000.
- Gelardi, Anthony L.: See—
Fantone, Stephen D.; Gelardi, Anthony L.; and Gelardi, John A., 5,588,526, Cl. 206-308.100.
- Gelardi, John A.: See—
Fantone, Stephen D.; Gelardi, Anthony L.; and Gelardi, John A., 5,588,526, Cl. 206-308.100.
- Gelfer, Mikhail Y.: See—
Markowitz, Kenneth; and Gelfer, Mikhail Y., 5,589,159, Cl. 424-49.000.
- Gemma, Hideaki: See—
Kondo, Nobukazu; Kaneko, Seiji; Gemma, Hideaki; Okada, Tetsuhiko; Komori, Kazuhiko; and Okazawa, Koichi, 5,590,290, Cl. 395-298.000.
- Gemplus Card International: See—
Le Roux, Jean-Yves, 5,590,193, Cl. 380-4.000.
- GenCorp Inc.: See—
Hargis, I. Glen; Kovalchin, John P.; Sharma, Satish C.; Weimer, Raymond J.; and Wilson, John A., 5,589,532, Cl. 524-432.000.
- Gene Shears Pty. Limited: See—
Haseloff, James P.; Gerlach, Wayne L.; Jennings, Philip A.; and Cameron, Fiona H., 5,589,580, Cl. 536-23.200.
- Genentech, Inc.: See—
Cleland, Jeffrey L.; and Jones, Andrew J. S., 5,589,167, Cl. 424-85.700.
- Hotchkiss, Adair J.; O'Connor, John V.; and Spellman, Michael W., 5,589,361, Cl. 435-69.100.
- Mohler, Marjorie A.; and Nguyen, Tue H., 5,589,169, Cl. 424-94.200.
- O'Brien, Donogh P.; Vehar, Gordon A.; and Wilcox, Josiah N., 5,589,173, Cl. 424-145.100.
- Roy, Scumitra; and Vehar, Gordon A., 5,589,363, Cl. 435-69.600.
- General Electric Company: See—
Brown, Dale M.; and Michon, Gerald J., 5,589,682, Cl. 250-214.00A.
- Duggal, Anil R.; and Yakymyshyn, Christopher P., 5,590,090, Cl. 367-7.000.
- Frank, Paul A.; McGrath, Donald T.; and Staver, Daniel A., 5,589,766, Cl. 324-158.100.
- Guggenheim, Thomas L.; Fukuyama, Sharon M.; and Warner, Gregory L., 5,589,037, Cl. 203-35.000.

- King, Robert D., 5,589,743, Cl. 318-139,000.
 Scott, Curtis E.; Kaliszewski, Mary Sue, and Levinson, Lionel M., 5,588,992, Cl. 117-2,000.
 Terhune, James H.; and Gordon, Barry M., 5,590,162, Cl. 376-320,000.
 Walsh, Eileen B., 5,589,530, Cl. 524-152,000.
 Zarge, Jonathan A.; and Schroeder, William J., 5,590,248, Cl. 395-121,000.
 General Motors Corporation: See—
 Bolsworth, James; and Adamson, Robert E., Jr., 5,588,707, Cl. 297-378,120.
 Carr, James E.; and Lindsey, Mark A., 5,588,338, Cl. 74-560,000.
 Gandhi, Umesh N.; and Osmak, Douglas J., 5,588,692, Cl. 296-146,700.
 Gay, David E., 5,589,010, Cl. 148-306,000.
 Lederman, Frederick E., 5,588,210, Cl. 29-898,000.
 Lieht, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydelis, Ronald A.; and Fox, Michael J., 5,588,404, Cl. 123-90,170.
 Lotsph, John A., 5,588,675, Cl. 280-738,000.
 Lu, Jian G.; and Beckmann, Ronald L., 5,588,334, Cl. 74-502,600.
 Milton, Thomas J., 5,588,337, Cl. 74-552,000.
 Paddison, Richard L., 5,588,660, Cl. 280-95,100.
 Sokol, Gerald E.; Lee, Howard H.; and Kibbel, Bradley W., 5,588,477, Cl. 164-34,000.
 Vetter, Stephan M.; and Parisi, Mark J., 5,588,803, Cl. 416-186,000.
 Wright, Kevin; Rogers, Lloyd W., Jr.; Baughman, Robert W.; and Chapman, David J., 5,588,258, Cl. 49-340,000.
 Zuraski, Jeffery A.; and Colosky, Mark P., 5,589,805, Cl. 332-109,000.
 Genetics Institute, Inc.: See—
 Jones, Simon; and Tang, Jin, 5,589,170, Cl. 424-94,600.
 Genzyme Corporation: See—
 Shuber, Anthony P., 5,589,330, Cl. 435-5,000.
 George, Shaji T.: See—
 Shih, Andy; Bockman, Jeffrey M.; and George, Shaji T., 5,589,332, Cl. 435-6,000.
 Georgia Tech Research Corporation: See—
 Wang, Johnson J. H.; and Tripp, Victor K., 5,589,842, Cl. 343-787,000.
 Geraghty & Miller, Inc.: See—
 Suthersan, Suthan S.; Dynkin, Boris; and Cushing, Richard, 5,588,490, Cl. 166-370,000.
 Gerber, Rolf: See—
 Planta, Andrea V.; and Gerber, Rolf, 5,590,015, Cl. 361-277,000.
 Gere, Aniko: See—
 Harsanyi, Kálmán; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sobonyai, Anna; Kápolnás-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szporny, Laszlo; Kiss, Bela; Karpáti, Egon; Palosi, Eva; Szomathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihály; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sándor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
 Geringer, Kerry G.; to Sauer Inc. Vibration and pressure attenuator for hydraulic units, 5,588,805, Cl. 417-53,000.
 Gerlach, Uwe: See—
 Deffosa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lantrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228,000.
 Gerlach, Wayne L.: See—
 Haseloff, James P.; Gerlach, Wayne L.; Jennings, Philip A.; and Cameron, Fiona H., 5,589,880, Cl. 536-23,200.
 German, Elena N., legal representative: See—
 Saito, Satoru; Tatsui, Haruyoshi; German, Lev S., deceased, 5,589,559, Cl. 526-247,000.
 German, Johann: See—
 Klunk, Rainer; German, Johann; and Warthmann, Wolfgang, 5,589,290, Cl. 429-99,000.
 German, Lev S., deceased (by Elena N. German, legal representative): See—
 Saito, Satoru; Tatsui, Haruyoshi; German, Lev S., deceased, 5,589,559, Cl. 526-247,000.
 Geron Corporation: See—
 West, Michael D., 5,589,483, Cl. 514-310,000.
 Gerrick, R. Andrew: See—
 Blackmon, James B.; Drubka, Robert E.; Jones, Nelson E.; Gerrick, R. Andrew; and Hand, Michael L., 5,589,758, Cl. 322-100,000.
 Gerry Baby Products Company: See—
 Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 5,588,158, Cl. 4-572,100.
 Poulson, Keith L.; Parker, Robert M.; Samson, Jeffrey T.; and Taylor, Harry B., 5,588,159, Cl. 4-572,100.
 Gerstel, Eberhard; and Bremer, Ralf: Thermal desorption device for a gas chromatograph, 5,588,988, Cl. 96-101,000.
 Gessel, Uwe; Rospek, Rolf; and Zollner, Helmut; to Dynamit Nobel Aktiengesellschaft: Detonating system having a detonator within an insulating container, 5,589,657, Cl. 102-202,140.
 Geul, Herman R.; to Nordson Corporation: Method and device for applying liquid material, in particular a hot melt, by means of a sequentially operating applicator to a substrate, 5,589,226, Cl. 427-286,000.
 Ghara, Mehrad: See—
 Gibola, Norbert; and Ghara, Mehrad, 5,590,228, Cl. 385-56,000.
 Ghent, R. Alison: See—
 Eskin, Bernard A.; and Ghent, R. Alison, 5,589,198, Cl. 424-667,000.
 Gianforte, John S.; and Cox, Anthony C., to EGS Americas, Inc.: Chill roll assembly, 5,588,224, Cl. 34-447,000.
 Giat Industries: See—
 Gaulmier, André, 5,589,655, Cl. 89-1,814.
 Gibbons, Kevin P.; Lau, Louis C.; and Woodard, Floyd E.; to Southwall Technologies Inc.: Metal on plastic films with adhesion-promoting layer, 5,589,280, Cl. 428-626,000.
 Gibola, Norbert; and Ghara, Mehrad; to Packard Hughes Interconnect Company: Ratchet lock connector interlocking mechanism, 5,590,228, Cl. 385-56,000.
 Gibson, Donald H.: See—
 Baum, Richard L.; Brent, Glen A.; Gibson, Donald H.; and Lindquist, David B., 5,590,362, Cl. 395-800,000.
 Giesecke, Norbert: See—
 Dorbath, Bernd; Giesecke, Norbert; and Fritsche, Klaus-Dieter, 5,589,273, Cl. 428-433,000.
 Gilbert, Barrie; to Analog Devices, Inc.: Variable gain mixer having improved linearity and lower switching noise, 5,589,791, Cl. 327-359,000.
 Gilbert, Ira H.; to Massachusetts Institute of Technology: Mesh parallel computer architecture apparatus and associated methods, 5,590,356, Cl. 395-800,000.
 Gilbert, John: See—
 Ott, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heilmann, Ulrich; and Gilbert, John, 5,589,049, Cl. 204-504,000.
 Gilbert, Raymond D.: Radial-force spoiler system, 5,588,620, Cl. 244-90,00A.
 Gildea, David R.; and Banra, Lloyd H.; to Trimble Navigation Limited: Differential GPS receiver system linked by infrared signals, 5,589,835, Cl. 342-357,000.
 Gill, Danny A.: Earthquake protective structure, 5,588,265, Cl. 52-167,100.
 Gillette Company, The: See—
 Callaghan, David T.; Phipps, Alan M.; and Provencal, Stephen J., 5,589,196, Cl. 424-617,000.
 Gillies, Stephen: See—
 Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,589,510, Cl. 514-590,000.
 Gillin, John: See—
 Leamy, Patrick; Leamy, Alan; and Gillin, John, 5,590,245, Cl. 395-118,000.
 Gilman, Jeffrey W.: See—
 Lichtenhan, Joseph D.; Vu, Ngo Quang; Gilman, Jeffrey W.; and Feher, Frank J., 5,589,562, Cl. 528-9,000.
 Gimenez Guasch, Francesc X.: See—
 Vallet Mas, Alberto; and Gimenez Guasch, Francesc X., 5,588,559, Cl. 222-92,000.
 Gire, Hélène; to VALÉO Thermique Moteur: Plate-type heat exchanger, for use especially as an oil cooler, 5,588,485, Cl. 165-157,000.
 Giroux, Michael: See—
 Hannah, L. Curtis; and Giroux, Michael, 5,589,618, Cl. 800-205,000.
 Gizur, Tibor: See—
 Harsanyi, Kálmán; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sobonyai, Anna; Kápolnás-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szporny, Laszlo; Kiss, Bela; Karpáti, Egon; Palosi, Eva; Szomathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihály; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sándor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
 Glachet, Charles; to SNE LA CALBENE: Interface device for the transfer of fluid products between two containers, 5,588,473, Cl. 141-387,000.
 Glankowski, Edward J.; and Chiang, Yulin; to Hoechst Marion Roussel, Inc.: 2-[(3-heteroaryl-1-pyrrolidinyl)alkyl]-1,3-indandiones and related compounds and their therapeutic utility, 5,589,495, Cl. 514-373,000.
 Glankowski, Edward J.: See—
 Strupczewski, Joseph T.; and Glankowski, Edward J., 5,589,488, Cl. 514-321,000.
 Strupczewski, Joseph T.; Helsley, Grover C.; Glankowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-373,000.
 Glaser, Josef; and Fomet, Pierre; to AVL Gesellschaft für Verbrennungskraftmaschinen und Messtechnik m.H. Prof. Dr. h.c. Hans List: Pressure sensor having a heat conducting element between the pressure transmitting element and the pressure sensor housing, 5,589,638, Cl. 73-706,000.
 Glassett, Kevin L.: See—
 Russell, Todd L.; Richtsmeier, Brent W.; and Glassett, Kevin L., 5,589,866, Cl. 347-102,000.
 Glasson, J. Peter: See—
 Granville, Gregg; and Glasson, J. Peter, 5,590,060, Cl. 364-560,000.
 Glaxo Wellcome Inc.: See—
 Lipscombe, Martin J.; Charles, Ian G.; and Fairweather, Neil F., 5,589,384, Cl. 435-252,330.
 Nicol, Robin H.; Slater, Martin J.; and Hodgson, Simon T., 5,589,474, Cl. 514-211,000.
 Glenbrook Technologies: See—
 Zweig, Gilbert, 5,590,170, Cl. 378-63,000.
 Glew, Andrew P.: See—
 Huck, Kamla P.; Rodgers, Scott D.; and Glew, Andrew P., 5,590,297, Cl. 395-401,000.
 Gloden, Michael L.; and Sprecher, Arnold F., Jr.; to MTS Systems Corporation: Waveguide suspension device and modular construction for some waveguides, 5,590,091, Cl. 367-140,000.
 Glory Kiki Co., Ltd.: See—
 Fujiki, Masaru, 5,588,492, Cl. 169-11,000.
 Glucksmann, Dov Z.; and Weidemann, Karl H.; to Appliance Development Corp.: Automatic bread-making apparatus, 5,588,353, Cl. 99-348,000.
 Glynn, Brian A.: See—

- Imran, Mir A.; Pomeranz, Mark L.; and Glynn, Brian A., 5,588,964, Cl. 604-95,000.
 GNB Battery Technologies, Inc.: See—
 Klang, James K., 5,589,757, Cl. 320-22,000.
 Godfrey, Geoffrey L.: Disposable hazardous medical waste collection system, 5,588,174, Cl. 15-257,200.
 Goetz, Charles R.; to Alco Industries, Inc.: Heavy-duty decorative shelving, 5,588,541, Cl. 211-188,000.
 Goetz, Norbert: See—
 Eicken, Karl; Goetz, Norbert; Harreus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela; and Rang, Harald, 5,589,493, Cl. 514-355,000.
 Gohn, Makoto; and Horiuchi, Tetsuya; to GE Yokogawa Medical Systems, Limited: Method for generating fat distribution image by CT system, 5,590,165, Cl. 378-18,000.
 Goshii, Akira: See—
 Ueda, Koshi; Goshii, Akira; and Kunbara, Masayuki, 5,589,780, Cl. 324-751,000.
 Gold, Barbara S.: See—
 Lurie, Keith G.; and Gold, Barbara S., 5,588,422, Cl. 128-200,240.
 Gold, Ronald S.; to Hughes Aircraft Company: Arc lamp with external magnetic means, 5,589,726, Cl. 313-161,000.
 Golden, Josh H.; DiSalvo, Francis J.; and Frechet, Jean M. J.; to Cornell Research Foundation, Inc.: Single phase solids of polymerizable metal clusters, 5,589,537, Cl. 524-780,000.
 Goldhaber, David M.: See—
 Zhang, Weiguo; Kramer, David M.; and Goldhaber, David M., 5,589,774, Cl. 324-309,000.
 Goldman, David: See—
 Nielsen, David A.; Goldman, David; Linnoila, Markku; and Virkkunen, Matti, 5,589,331, Cl. 435-6,000.
 Goldman, Robert P.; Arab-Sadeghahadi, Akbar; and Varni, Anselm F.; to Litton Systems, Inc.: Multichannel fiber optic connector, 5,590,229, Cl. 385-59,000.
 Goldrick, Marianna M.: See—
 Winkler, Matthew; and Goldrick, Marianna M., 5,589,329, Cl. 435-5,000.
 Goldstar Co., Ltd.: See—
 Bu, Jong U., 5,589,094, Cl. 219-711,000.
 Lim, Jun Y., 5,589,751, Cl. 318-701,000.
 Goldstein, Theodore C.: See—
 Lewis, Brian T.; and Goldstein, Theodore C., 5,590,331, Cl. 395-708,000.
 Goldston, Mark R.; Bemis, Jon L.; Wickemeyer, Daniel M.; and Potter, David; to L.A. Gear, Inc.: Athletic shoe having air bladder pressure indicating means, 5,588,227, Cl. 36-93,000.
 Golen, John A.: See—
 Filippi, John E.; and Golen, John A., 5,589,144, Cl. 422-179,000.
 Golia, Joseph H.: See—
 Sanford, James R. M.; Frank, Patrick M.; Golia, Joseph H.; and Jennings, William C., 5,589,063, Cl. 210-198,200.
 Golino, Carlo M.; Taylor, Thomas J.; Kielmeier, William H.; Thiessen, Leo K.; and Rude, Carl A.; to QO Chemicals, Inc.; and Schuller International, Inc.: Glass fiber binding compositions, process of binding glass fibers, and glass fiber composites, 5,589,536, Cl. 524-593,000.
 Golio, John M.; Turner, Robert C.; Miller, Monte G.; and Halchin, David J.; to Motorola, Inc.: Optimization method using parallel processors, 5,590,063, Cl. 364-580,000.
 Golston, Jeremiah E.: See—
 Guttag, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moysse, Philip, 5,590,350, Cl. 395-800,000.
 Gomes, Daniel; Foldable beach chair, 5,588,695, Cl. 297-56,000.
 Gomez, Reynaldo; to AC Directional Control, Inc.: Mechanical control for central air conditioners' outlets, 5,588,911, Cl. 454-290,000.
 Gomi, Takeshi: See—
 Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hiroto; and Yamamoto, Yoshio, 5,588,414, Cl. 123-571,000.
 Gonsalves, Kenneth E.; to University of Connecticut, The: Nanostructured steel alloy, 5,589,011, Cl. 148-334,000.
 Gonzalez-Hernandez, Jesus: See—
 De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C., Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243,000.
 Goode, Louis: See—
 Narayanan, Krishna; Padmanabhan, Vasanti; Shipko, Fredrick J.; Goode, Louis; and Fearnot, Neal E., 5,588,436, Cl. 128-662,030.
 Goodman, Gregory L.: Toy balloon inflation and ejection device, 5,588,896, Cl. 446-187,000.
 Goodman, Todd A.: See—
 Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Knapkaran, Raghavan; Jayasinha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114,000.
 Goodnow, James E.; Kowalski, Thaddeus J.; and Rowland, James R.; to Lucent Technologies Inc.: Method and apparatus for detecting memory access errors, 5,590,329, Cl. 395-708,000.
 Goodson, Forrest R.: See—
 Perry, Robert W.; and Goodson, Forrest R., 5,589,660, Cl. 149-18,000.
 Goodwin, Julie E.: See—
 Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie E.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828,000.
 Goosey, William T., Jr.: See—
 Estelle, Lee R.; and Goosey, William T., Jr., 5,589,989, Cl. 359-785,000.
 Goossens, Keith W.; and Walker, James A.; to Lucent Technologies Inc.: Micromechanical modulator, 5,589,974, Cl. 359-290,000.
 Goossen, Keith W.: See—
 Cunningham, John E.; Goossen, Keith W.; Jan, William Y.; Pathak, Rajiv N.; and Walker, James A., 5,589,404, Cl. 437-5,000.
 Goossens, Hendrikus M. W.; to U.S. Philips Corporation: Hybrid ballast for high pressure discharge lamp, 5,589,739, Cl. 315-176,000.
 Gordon, Barry M.: See—
 Terhune, James H.; and Gordon, Barry M., 5,590,162, Cl. 376-320,000.
 Gordon, M. Brian, Sr.: Bag holder, 5,588,622, Cl. 248-101,000.
 Gordon, Steven J.; to Intelligent Automation Systems: Real time three dimensional sensing system, 5,589,942, Cl. 356-376,000.
 Gorman, Patrick J.; Yee, Phillip D.; and Gray, Mark F.; to TRW Vehicle Safety Systems Inc.: Buckle for vehicle seat belt system, 5,588,189, Cl. 24-632,000.
 Gorman, Sean E.: See—
 Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112-80,160.
 Gossele, Véronique: See—
 De Beuckeleer, Marc; Herdies, Lydia; Gossele, Véronique; and Mariani, Celestina, 5,589,610, Cl. 800-205,000.
 Gossen, Manfred: See—
 Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera; and Schnappinger, Dirk, 5,589,362, Cl. 435-69,100.
 Gosset, Dominique: See—
 Decroix, Guy M.; Gosset, Dominique; and Kryger, Bernard, 5,590,393, Cl. 428-552,000.
 Goszczynski, Piotr T.: See—
 Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J., 5,590,189, Cl. 379-356,000.
 Goto, Masaharu; to Hewlett-Packard Company: Timing adjustment circuit, 5,589,788, Cl. 327-276,000.
 Goto, Masahito: See—
 Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Aki; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
 Goto, Shigenori: See—
 Saito, Tatsuo; and Goto, Shigenori, 5,589,910, Cl. 396-106,000.
 Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Katsuaki; Uka, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko; to Nihon Bayer Agrochem K.K.: Tetrazolinone derivatives, 5,589,439, Cl. 504-261,000.
 Gotou, Shinichirou; to Honda Giken Kogyo Kabushiki Kaisha: Head lamp device for vehicle, 5,588,733, Cl. 362-37,000.
 Götschi, Erwin: See—
 Geiwiz, Jürgen; Götschi, Erwin; Hebeisen, Paul; Link, Helmut; and Lübbers, Thomas, 5,589,473, Cl. 514-183,000.
 Gottschald, Lutz; to Wernicke & Co. GmbH: Apparatus for grinding spectacle lenses, 5,588,899, Cl. 451-5,000.
 Gottwald, Ingo: See—
 Kustermann, Martin; Gottwald, Ingo; and Uebberschär, Manfred, 5,589,659, Cl. 118-413,000.
 Götz, Klaus P.; Schaarschmidt, Manfred; and Feldmeier, Günter; to Whitaker Corporation: The Connector with terminals having anti-wicking gel, 5,588,885, Cl. 439-876,000.
 Goubet, François: See—
 Claussner, André; Goubet, François; and Teutsch, Jean-Georges, 5,589,497, Cl. 514-386,000.
 Gourdel, Arnaud P. J.; to Apple Computer, Inc.: Method and apparatus for recognizing gestures on a computer system, 5,590,219, Cl. 382-202,000.
 Gove, Robert J.: See—
 Guttag, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moysse, Philip, 5,590,350, Cl. 395-800,000.
 Govoni, Gabriele; Sacchetti, Mario; and Pasquali, Stefano; to Montell Technology Company bv: Multistage process for the (CO) polymerization of olefins, 5,589,549, Cl. 525-247,000.
 Graefenhain, Paul; to Leica AG: Connectible locking mechanism, 5,588,769, Cl. 403-322,000.
 Graham, Gary A.; Jacobs, Merrit N.; Marvin, Russel H.; Shaw, James D.; and VanBrunt, Nicholas; to Johnson & Johnson Clinical Diagnostics, Inc.: Centrifuge and phase separation, 5,588,946, Cl. 494-11,000.
 Granerby Enterprises (U.S.A.) Corp.: See—
 Lai, Danny S., 5,588,310, Cl. 63-15,000.
 Grand Haven Stamped Products: See—
 Osborn, Charles; Medema, Robert M.; and Ruiter, Andrew K., 5,588,934, Cl. 477-96,000.
 Grandcolas, Michael: See—

- Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Grantham, George L., *See*—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K., 5,589,367, Cl. 435-172.300.
- Granville, Gregg; and Glasson, J. Peter, to Metronics, Inc. Apparatus and method for an object measurement system, 5,590,060, Cl. 364-560.000.
- Grasso, Robert P.; O'Brien, Michael K.; and Shannon, Paul J., to Hercules Incorporated, Dichroic azo dyes, 5,589,100, Cl. 252-299.010.
- Grauman, Joyce A., *See*—
Butler, Laura J.; and Grauman, Joyce A., 5,590,267, Cl. 395-340.000.
- Gray, Buddy D., to Teledyne Industries, Inc. Portable water purification system, 5,589,066, Cl. 210-258.000.
- Gray, Mark F., *See*—
Gorman, Patrick J.; Yee, Phillip D.; and Gray, Mark F., 5,588,189, Cl. 24-632.000.
- Great Western Press, Inc., *See*—
Young, Steven R., 5,588,678, Cl. 283-67.000.
- Green Cross Corporation, *See*—
Uryu, Katsuhito; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, 5,589,516, Cl. 514-2.000.
- Green, Mark; and Hartline, Robert B., to Bergquist Company, The, Membrane switch for use over a steering wheel airbag assembly, 5,588,673, Cl. 280-731.000.
- Green, Norman E.; and Sowers, Kenneth V., to DewEze Manufacturing, Inc. Auxiliary power take off assembly and method, 5,588,325, Cl. 74-15.630.
- Green, Ronald J., *See*—
Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Kerry D., 5,590,391, Cl. 423-253.000.
- Greenberg, Leonard H., *See*—
Young, Phillip L.; and Greenberg, Leonard H., 5,589,944, Cl. 386-84.000.
- Greenberg, Walter, *See*—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Greene, Jeffrey A., *See*—
Volk, Donald R.; and Greene, Jeffrey A., 5,588,989, Cl. 106-14.120.
- Greenfield, Zvi, *See*—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Vinc, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.
- Greenland, Andrew J., *See*—
Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., 5,589,614, Cl. 800-205.000.
- Greenspan, Steven L., to Lucent Technologies Inc. Call transfer with automatic return, 5,590,187, Cl. 379-212.000.
- Gregory, Richard A., *See*—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickey; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242.400.
- Greiss, Israel, *See*—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Vinc, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.
- Greve, Jeffrey M., to Molecular Therapeutics, Inc. Human rhinovirus receptor protein (ICAM-1) that inhibits rhinovirus attachment and infectivity, 5,589,453, Cl. 514-8.000.
- Gribbon, Sean T., to Safem Englehard. Integrated regenerative catalytic oxidation/selective catalytic reduction abatement system, 5,589,142, Cl. 422-171.000.
- Grice, Donald G., *See*—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Griffith, James E., *See*—
Chatterji, Jiten; Griffith, James E.; Totten, Patty L.; and King, Bobby J., 5,588,489, Cl. 166-293.000.
- Griffith Laboratories Worldwide, Inc., *See*—
Tang, Pamela S., 5,589,215, Cl. 426-549.000.
- Grill, Laurence K., *See*—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K., 5,589,367, Cl. 435-172.300.
- Grimaud, James H. G., III, *See*—
Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Kerry D., 5,590,391, Cl. 423-253.000.
- Grimminger, Friedrich, *See*—
Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeier, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560.000.
- Grob, Matthew S., *See*—
Bayley, Gwain; Grob, Matthew S.; Karim, Gadi; Kimball, Robert H.; and Propach, David S., 5,590,406, Cl. 455-54.200.
- Groemig, Paul J., *See*—
Robb, Francine Y.; Robb, Stephen P.; and Groemig, Paul J., 5,589,408, Cl. 437-29.000.
- Gross, Lutz-Werner, *See*—
Wegner, Egon; Poth, Ulrich; Gross, Lutz-Werner; and Weidemeier, Klaus, 5,589,228, Cl. 427-407.100.
- Grosz, Martin J., *See*—
Rahman, Mizanur M.; Sabernick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735.000.
- Gruber, Ute, *See*—
Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., 5,589,534, Cl. 524-548.000.
- Grubisich, Michael J., *See*—
Bulucea, Constantin; and Grubisich, Michael J., 5,589,409, Cl. 437-31.000.
- Gruel, Henri; Moraine, Michel; and Crasnianski, Serge, to KIS Photo Industrie (SARL). Integrated automatic installation for taking photographs or sequences of photographs, 5,589,902, Cl. 396-3.000.
- Grundvig, Jeffrey P., and Vallancourt, David G., to Lucent Technologies Inc. Low noise non-sampled successive approximation, 5,589,832, Cl. 341-161.000.
- Gruntel Ltda., *See*—
Jennebach, Markus; and Birkhan, Joan A., 5,588,381, Cl. 110-345.000.
- Gryte, Stephen, *See*—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Gueck, Wayne, *See*—
Weng, Lee; and Gueck, Wayne, 5,588,435, Cl. 128-660.070.
- Guenther, Russell W., and Rabins, Leonard, to Bull HN Information Systems Inc. Address transformation in a cluster computer system, 5,590,301, Cl. 395-412.000.
- Gueret, Jean-Louis H., to L'Oreal. Brush for applying nail varnish and method, 5,588,447, Cl. 132-200.000.
- Gueret, Jean-Louis H., to L'Oreal. Brush for applying a make-up product, particularly mascara, 5,588,450, Cl. 132-218.000.
- Guevara, Nelson V., to Independent Enclosures, Inc. Reinforced public telephone having dual key pads, 5,590,191, Cl. 379-451.000.
- Guggenheim, Thomas L.; Fukuyama, Sharon M.; and Warner, Gregory L., to General Electric Company. Method for removing tetranitromethane from nitric acid, 5,589,037, Cl. 203-35.000.
- Guillemonet, Jérôme E. G., *See*—
Venet, Marc G.; Guillemonet, Jérôme E. G.; Verrier, Daniel F. J.; and Odds, Frank C., 5,589,484, Cl. 514-314.000.
- Gunning, William J., III; Winker, Bruce K.; and Koch, Gene C. Pixelated compensators for twisted nematic liquid crystal displays, 5,589,963, Cl. 349-119.000.
- Günter Rubeling, *See*—
Rubeling, Günter; and Otten, Burghard, 5,588,837, Cl. 433-172.000.
- Guntert, Dietwart, *See*—
Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruns, Elke; Guntert, Dietwart; and Müller, Hubert, 5,589,060, Cl. 210-130.000.
- Gupta, Amitabha, *See*—
Sinclair, Stephen H.; Nissanov, Jonathan; and Gupta, Amitabha, 5,589,897, Cl. 351-223.000.
- Gupte, Nitin B., *See*—
Kolar, Daniel J.; Gupte, Nitin B.; and Shah, Siddharth R., 5,590,071, Cl. 365-149.000.
- Gurr, Sarah J.; McPherson, Michael J.; Atkinson, Howard J.; and Bowles, Dianna J., to Advanced Technologies (Cambridge) Ltd. Plant parasitic nematode control, 5,589,622, Cl. 800-205.000.
- Guskey, Gerald J.; Hellyer, James A.; Kluesener, Bernard W.; and Stipp, Gordon K., to Procter and Gamble Company, The. Reduced calorie confectionery compositions which contain reduced calorie fats which exhibit rapid transformation to beta phase, 5,589,216, Cl. 426-607.000.
- Gutierrez, Jorge, *See*—
Paul, Michel A.; and Gutierrez, Jorge, 5,588,580, Cl. 227-176.100.
- Guttig, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moysse, Philip, to Texas Instruments Incorporated. Three input arithmetic logic unit with mask generator, 5,590,350, Cl. 395-800.000.
- Gutwillig, Alan, *See*—
Brinker, Gerald; Hladik, Peter; and Gutwillig, Alan, 5,589,649, Cl. 73-866.000.
- H. C. Starck GmbH & Co. KG, *See*—
Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Erugrul; König, Theo; and Fister, Dietmar, 5,590,387, Cl. 419-36.000.

- Hable, Bernard J., *See*—
Buendgen, Michael R.; and Hable, Bernard J., 5,589,606, Cl. 800-200.000.
- Hackbarth, David G.; Hapke, Kenyon A.; and Schantz, Spencer C., to US Controls Corp. Rotary switch with spring stabilized contact control rotor, 5,589,671, Cl. 200-6.000.
- Haddad, Sameer S.; Chang, Chi; and Liu, David K. Y., to Advanced Micro Devices, Inc. Channel hot-carrier page write, 5,590,076, Cl. 365-185.250.
- Haded, Kevin J., *See*—
Tellam, Mark E.; Brook, Mark G.; Haded, Kevin J.; and Wheeler, Joseph A., 5,589,972, Cl. 359-196.000.
- Hadintoglou, Babur B., to Xerox Corporation. Integrated varactor switches for acoustic ink printing, 5,589,864, Cl. 347-46.000.
- Haerthling, Gene H., to Research Corporation Tech., Inc. Monolithic prestressed ceramic devices and method for making same, 5,589,725, Cl. 310-358.000.
- Hage, Günther, *See*—
Kopetzky, Robert; and Hage, Günther, 5,588,677, Cl. 280-806.000.
- Hagenah, Gerhard, to SF-Kooperation GmbH Beton-Konzepte. Paving stone set and process and device for the manufacture thereof, 5,588,775, Cl. 404-45.000.
- Hagiwara, Hideaki; and Suzuki, Toshiaki, to Hagiwara, Yoshihide; and HH Biocenter, Inc. Agent for preserving the freshness of plants, 5,589,436, Cl. 504-114.000.
- Hagiwara, Yoshihide; *See*—
Hagiwara, Hideaki; and Suzuki, Toshiaki, 5,589,436, Cl. 504-114.000.
- Hagman, Ronald L., *See*—
Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4.100.
- Hagopian, Gerald M., to KCS Industries, Inc. Merchandise display system, 5,588,537, Cl. 211-4.000.
- Haigh, David, to SmithKline Beecham PLC. Heterocyclic compounds and their use in the treatment of Type-II diabetes, 5,589,492, Cl. 514-339.000.
- Hain, Rüdiger; and Stenzel, Klaus, to Bayer Aktiengesellschaft. Use of Jysozyme gene structures in plants to increase resistance, 5,589,626, Cl. 800-205.000.
- Hain, Rüdiger, *See*—
Kindl, Helmut; Hain, Rüdiger; and Reif, Hans-Jörg, 5,589,620, Cl. 800-205.000.
- Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jörg; Stenzel, Klaus; and Thonizik, Jürgen, 5,589,621, Cl. 800-205.000.
- Haisch, Herman F., *See*—
Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54.100.
- Halchin, David J., *See*—
Golio, John M.; Turner, Robert C.; Miller, Monte G.; and Halchin, David J., 5,590,063, Cl. 364-580.000.
- Halick, Gary V., *See*—
Cunningham, Robert W.; Koch, Durmus; Mura, Janine R.; Felix, Augustus; and Halick, Gary V., 5,588,958, Cl. 604-4.000.
- Hall, Daniel J., to John Daniel Containers (Proprietary) Limited. Side dumping container, 5,588,711, Cl. 298-18.000.
- Hall, Robert T., II; and Onstad, Bradley K., to Minntech Corporation. Method for sterilizing medical devices utilizing a room temperature sterilant, 5,589,507, Cl. 514-557.000.
- Hallett, Richard A., *See*—
Dale, Allison Hazel C.; Piggitt, Roger H.; Hallett, Richard A.; and McIntyre, Paul R., 5,589,318, Cl. 430-264.000.
- Halliburton Company, *See*—
Chatterji, Jiten; Griffith, James E.; Totten, Patty L.; and King, Bobby J., 5,588,489, Cl. 166-293.000.
- Vijn, Jan P.; Xenakis, Zacharias; Bour, Daniel L.; and Childs, Jerry D., 5,588,488, Cl. 166-293.000.
- Hama, Hideo; and Sakai, Yukari, to Mitsui Petrochemical Industries, Ltd. Antiferroelectric liquid crystal light modulation device, 5,589,966, Cl. 349-194.000.
- Hamabuchi, Teruyoshi, *See*—
Sugiyama, Hiroyuki; Hirose, Norio; Hamabuchi, Teruyoshi; and Muto, Hikoji, 5,588,362, Cl. 101-218.000.
- Hamai, Tsuyoshi; and Yashima, Norimichi, to Yazaki Corporation. Connector adapted for fit detection, 5,588,873, Cl. 439-489.000.
- Hamajima, Tetsuo, *See*—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukutsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Hamamoto, Magozo, *See*—
Aramaki, Teruo; and Hamamoto, Magozo, 5,590,225, Cl. 384-527.000.
- Hamanaka, Nobuyuki; Takahashi, Kanji; and Tokumoto, Hidekado, to Ono Pharmaceutical Co., Ltd. Fused benzoxoyacetic acid derivatives which have PGI₂ receptor agonist activity, 5,589,496, Cl. 514-374.000.
- Hamann, James L., to Penibone Corporation. Drain line cleaning apparatus, 5,588,171, Cl. 15-104.120.
- Hamano, Hirokazu, *See*—
Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigehiro; and Moriuchi, Hisako, 5,589,506, Cl. 514-520.000.
- Hamisch, Paul H., Jr.; and Mistyunk, John D., to Monarch Marking Systems, Inc. Ink ribbon cartridge and method of installing same, 5,588,756, Cl. 400-234.000.
- Hammond, Douglas S., *See*—
Subisak, Gregory J.; and Hammond, Douglas S., 5,588,742, Cl. 362-291.000.
- Hammond, Mark S.; and Evans, Joseph D., to SI Diamond Technology, Inc. Coated grinding tool, 5,588,975, Cl. 51-293.000.
- Hampshire Paper Corp., *See*—
Stepanek, Michael J., 5,589,013, Cl. 156-71.000.
- Hampson, Ian N.; Pope, Lynne; and Butler, John, to Amersham International PLC. Subtraction hybridization, 5,589,339, Cl. 435-6.000.
- Hamrick Manufacturing & Service, Inc., *See*—
Klover, John M.; and Hamrick, Philip F., 5,588,284, Cl. 53-534.000.
- Hamrick, Philip F., *See*—
Klover, John M.; and Hamrick, Philip F., 5,588,284, Cl. 53-534.000.
- HAMS Corporation, *See*—
Miyachi, Nobuji; and Miyachi, Kouji, 5,588,384, Cl. 112-475.060.
- Han, Quansheng; and Lahn, Bruce. Display apparatus utilizing magnetic interaction, 5,589,721, Cl. 310-90.500.
- Hanaoka, Katsunari, *See*—
Kawashima, Ikue; and Hanaoka, Katsunari, 5,589,712, Cl. 257-750.000.
- Hanaoka, Toshiharu, to Sharp Kabushiki Kaisha. Three dimensional sprite rendering apparatus and method, 5,590,249, Cl. 395-122.000.
- Hanayama, Katsutoshi, *See*—
Koyano, Shinji; Kogure, Koushiro; Ohya, Takashi; Sakakibara, Makoto; and Hanayama, Katsutoshi, 5,590,208, Cl. 381-154.000.
- Hancock, Dennis H., to All Rite Products, Inc. Hand held implement sharpening device, 5,588,340, Cl. 76-82.000.
- Hand, Michael L., *See*—
Blackmon, James B.; Drukka, Robert E.; Jones, Nelson E.; Gerrick, R. Andrew; and Hand, Michael L., 5,589,758, Cl. 322-100.000.
- Haneda, Tadayoshi, *See*—
Imachi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Himura, Koichi; and Haneda, Tadayoshi, 5,589,251, Cl. 428-209.000.
- Hänel, Heinz, *See*—
Ulbrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Jozef, 5,589,624, Cl. 800-205.000.
- Hanikowski, Esko. Hot-composting apparatus, 5,589,388, Cl. 435-290.300.
- Hanmi Pharm. Ind. Co., Ltd., *See*—
Woo, Jong S., 5,589,455, Cl. 514-11.000.
- Hann, Daniel, *See*—
Boddley, James W.; Noe, James P.; and Hann, Daniel, 5,588,253, Cl. 47-41.120.
- Hannah, L. Curtis; and Giroux, Michael, to University of Florida. Materials and methods for increasing corn seed weight, 5,589,618, Cl. 800-205.000.
- Hanning, Walter, *See*—
Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709.000.
- Hans, Helmut; and Moini, Mojtaba, to Papst Licensing GmbH. Drive circuit for a brushless direct-current motor, 5,589,745, Cl. 318-431.000.
- Hansen, Daniel J., Jr., *See*—
Hollowell, J. Rhoads, II; Benninghaus, James R.; and Hansen, Daniel J., Jr., 5,590,061, Cl. 364-571.030.
- Hansen, Kai; and Bretting, Claus Aage S., to Fabrik Produktionsaktieselskab Leo Pharmaceutical Products Ltd. Vitamin D analogues containing a hydroxy or alkylated hydroxy group in the 20-position, 5,589,471, Cl. 514-167.000.
- Hansen, Michael R.; and Young, Richard H., Sr., to Weyerhaeuser Company. Particle binders that enhance fiber densification, 5,589,256, Cl. 428-283.000.
- Hansen, W. Peter; and Cennerazzo, Michael. Light scatter-based immunoassay without particle self aggregation, 5,589,401, Cl. 436-525.000.
- Hansson, Stig G. V.; and Holmén, Anders, to Astra Aktiebolag. Fixture for use in a dental implant system, 5,588,838, Cl. 433-173.000.
- Hanyu, Yukio, *See*—
Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuto; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160.000.
- Hanzawa, Kohtaro; Sakata, Goro; and Tanaka, Kikui, to Casio Computer Co., Ltd. Signal processing apparatus, 5,590,364, Cl. 395-800.000.
- Hanzawa, Toyoharu, *See*—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiko; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Hapke, Kenyon A., *See*—
Hackbarth, David G.; Hapke, Kenyon A.; and Schantz, Spencer C., 5,589,671, Cl. 200-6.000.
- Haponski, Edward L. Reinforced monolithic concrete wall structure for spanning spaced-apart footings and the like, 5,588,272, Cl. 52-309.120.
- Hara, Shoji; Yanai, Takenori; and Ishikawa, Kazuhiro, to Murata Kikai Kabushiki Kaisha. Roller driving device, 5,588,523, Cl. 198-781.080.
- Harada, Hiraku, *See*—
Fujishiro, Yoshikazu; Ishigaki, Takaya; and Harada, Hiraku, 5,590,016, Cl. 361-313.000.

Harada, Noboru. *See* 5,588,735, Cl. 362.102.000.
 Harada, Tamotsu. *See*—
 Kuwahara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Tetsuaki; Takahashi, Koji; Harada, Tamotsu; Komiya, Takeshi; Hirai, Fumio, and Hayashi, Masamichi, 5,590,388, Cl. 419.39.000.
 Harada, Yasuo. *See*—
 Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Inaoka, Toshikazu; Harada, Yasuo; Honda, Kenichi, and Nishida, Masao, 5,590,412, Cl. 455.82.000.
 Haraoka, Mutsumi. *See*—
 Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshitomi, and Haraoka, Mutsumi, 5,588,611, Cl. 242.381.100.
 Harasawa, Shinichi, to Fujitsu Limited. Electric supply-switch relay circuit, 5,590,013, Cl. 361.187.000.
 Harber, Blair L., Jr. *See*—
 Shagott, David M.; Kruse, Gary E.; Harber, Blair L., Jr.; Sutherland, Daniel N., and Travis, Terrell F., 5,588,985, Cl. 95.25.000.
 Harcastle, Ian R. *See*—
 Edwards, Karen J.; Jarman, Michael; Laughton, Charles A.; Neidle, Stephen; and Harcastle, Ian R., 5,589,500, Cl. 514.428.000.
 Harder, Achim. *See*—
 Mencke, Norbert; Harder, Achim, and Jeschke, Peter, 5,589,503, Cl. 514.450.000.
 Harding, James A.; and McCormack, Jonathan I., to Asymetrix Corporation. Method and apparatus for the modeling and query of database structures using natural language-like constructs, 5,590,322, Cl. 395.604.000.
 Harel, Denis. Garbage separator system, 5,588,534, Cl. 209.3.100.
 Hargis, I. Glen; Kovalchik, John P.; Sharma, Satish C.; Weiner, Raymond J., and Wilson, John A., to GenCorp Inc. Solventless butadiene-vinylidene chloride adhesives containing macromonomers for the bonding of rubber to metal, 5,589,532, Cl. 524.432.000.
 Hargrave, David C. *See*—
 Johnson, Glenn W., Jr.; McVicker, Henry J., and Hargrave, David C., 5,588,955, Cl. 601.152.000.
 Har, Atsushi. *See*—
 Inagaki, Jiro; Shimoki, Takashi, and Har, Atsushi, 5,589,121, Cl. 264.132.000.
 Harigaya, Isao. *See*—
 Kozuki, Susumu; Harigaya, Isao, and Hori, Tazou, 5,589,943, Cl. 386.121.000.
 Haring, William F. Portable boat dock, 5,588,782, Cl. 405.218.000.
 Harju, Kai. *See*—
 Peltonen, Sulo; and Harju, Kai, 5,589,577, Cl. 536.221.000.
 Harlen, Charles D. Non-rotating wheel cover assembly, 5,588,715, Cl. 301.37.250.
 Harley-Davidson Motor Company. *See*—
 Rank, David B.; Bonebrake, Randall A.; and Stoner, Spurgeon C., 5,588,216, Cl. 33.286.000.
 Harman, Galen B. *See*—
 Franks, Lawrence A.; Harman, Galen B.; and Flint, Herman, 5,588,345, Cl. 83.95.000.
 Harms, Michael R.; Foss, Richard J.; Trice, Jennifer L.; and Neavin, Terence D., to Minnesota Mining and Manufacturing Company. Fixture for deposition, 5,589,000, Cl. 118.715.000.
 Hansotum, Alec T., to NPS Pharmaceuticals, Inc. Fluorescence detection apparatus, 5,589,351, Cl. 435.29.000.
 Hamard, Michel, and Runtz, Michel, to SGS-Thomson Microelectronics S.A. Dynamic memory, 5,590,070, Cl. 365.149.000.
 Harneus, Albrecht. *See*—
 Eicken, Karl; Goetz, Norbert; Harneus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela, and Rang, Harald, 5,589,493, Cl. 514.355.000.
 Harris, Christopher F. *See*—
 Daugherty, Tamara L., and Harris, Christopher F., 5,588,308, Cl. 62.622.000.
 Harris, Ronald B. Divided phase separator for liquid/solid separation in sludge, 5,589,081, Cl. 210.804.000.
 Harrison, Peter D. *See*—
 Sroka, Peter, and Harrison, Peter D., 5,590,411, Cl. 455.78.000.
 Harrison, Robert G., to PMI International Corporation. Appliance for making yeast doughs and cooking bagels, 5,588,352, Cl. 99.339.000.
 Harsanyi, Kálmán; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kápolnás-Pap, Márta; Csizer, Éva; Hegedus, Béla; Szporny, László; Kiss, Béla; Kárpáti, Égon; Palosi, Éva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Anikó; Bod, Péter; Cséhi, Attila; Zolt, László; Erdélyi, Zsolt; Szabo, Sándor; Bod, Péter, and Cséhi, Attila, to Richter Gedeon Vegyeszet Gyár Rt. N-hydroxyalkyl-substituted 1,2,3,6-tetrahydropyridine and piperidine derivatives, 5,589,486, Cl. 314.317.000.
 Hart, David, to Ontario Crippled Children's Centre. Orthotic walker, 5,588,456, Cl. 135.67.000.
 Hart, John H. *See*—
 Krause, Jeffrey; Strobl, Niles E.; Seaman, Michael J.; Russell, Steven P., and Hart, John H., 5,590,285, Cl. 395.200.000.
 Hart, Penny F. Transportable measurement device for children's clothes, 5,588,215, Cl. 33.2.000.
 Hart, Steven C., and Parker, Delmer G., to Xerox Corporation. Donor rolls with magnetically coupled (Transformer) commutation, 5,589,917, Cl. 399.274.000.
 Hartfield, Jon P., and Sanborn, Duane F., to Amecan Standard Inc. Falling film evaporator with refrigerant distribution system, 5,588,596, Cl. 239.542.000.

Hartley, Harry A., III. *See*—
 Bestler, Cathlin B.; Hartley, Harry A., III; and Rabin, Khosro M., 5,590,202, Cl. 380.49.000.
 Hartline, Robert B. *See*—
 Green, Mark, and Hartline, Robert B., 5,588,673, Cl. 280.731.000.
 Hartman, Delbert L. Infinite ratios cant wheel transmission, 5,588,933, Cl. 476.51.000.
 Hartman, Thomas A. Liquid flow velocity diffuser, 5,588,635, Cl. 251.127.000.
 Hartness International, Inc. *See*—
 Hartness, Thomas P., 5,588,282, Cl. 53.473.000.
 Hartness, Thomas P., to Hartness International, Inc. Continuous motion case packing apparatus and method, 5,588,282, Cl. 53.473.000.
 Hartsock, Dale L. *See*—
 Stiles, Ernest D.; and Hartsock, Dale L., 5,589,241, Cl. 428.36.900.
 Hartung, Georg. *See*—
 Herold, Manfred; Hartung, Georg; Schütz, Hans Willy; and Jung, Ulrich, 5,588,365, Cl. 101.350.000.
 Haruta, Hiroshi, and Takahashi, Takehiko, to Chisso Corporation. Polyimide precursor composition for extrusion molding of polyimide, process for preparing it, and process for preparing molded articles of polyimide, 5,589,111, Cl. 264.8.000.
 Harvey, Andrew C.; Lusignea, Richard W.; and Rubin, Leslie S., to Supertex Polymer Inc. Coextrusion of liquid crystal polymers and thermoplastic polymers, 5,589,236, Cl. 428.1.000.
 Harvey, Barry, to Elantec. Input stage improvement for current feedback amplifiers, 5,589,798, Cl. 330.263.000.
 Harvey, Stephen, to I.D.E.A. Corporation. The shielded modular portable computer work station having cable routing means, 5,590,022, Cl. 361.683.000.
 Harwood, H. James. *See*—
 Valpey, Richard S., III; Yokoyama, Thomas W.; Kraan, John D.; and Harwood, H. James, 5,589,560, Cl. 526.271.000.
 Harza, Richard D. Ergonomic antifatigue seating device and method, 5,588,704, Cl. 297.314.000.
 Hasagawa, Takehiro, and Okawa, Yukihito, to Kabushiki Kaisha Toshiba. Dynamic random access memory with variable sense-amplifier drive capacity, 5,590,080, Cl. 365.201.000.
 Hasegawa, Akira. *See*—
 Ishida, Hideharu; Kiso, Mikoto, and Hasegawa, Akira, 5,589,465, Cl. 514.25.000.
 Hasegawa, Hiroshi. *See*—
 Maejima, Takamichi; Inoue, Toshihiro; Hasegawa, Hiroshi, and Nakano, Atsushi, 5,588,206, Cl. 29.845.000.
 Hasegawa, Hiroto. *See*—
 Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399.350.000.
 Hasegawa, Ryosuke. *See*—
 Ishikawa, Hajime; Ogawa, Masaaki; Hasegawa, Ryosuke; and Yamamoto, Hideo, 5,589,205, Cl. 425.526.000.
 Hasegawa, Takashi. *See*—
 Kubo, Takahiro; Suda, Masashi; Muraoka, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi, and Menjo, Takeshi, 5,589,920, Cl. 399.145.000.
 Muraoka, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi, and Hasegawa, Takashi, 5,589,926, Cl. 399.302.000.
 Haseloff, James P.; Gerlach, Wayne L.; Jennings, Philip A., and Cameron, Fiona H., to Gene Shears Pty. Limited. Ribozymes, 5,589,580, Cl. 536.23.200.
 Hashiguchi, Toshihiko. *See*—
 Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamon, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiko; Akai, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600.111.000.
 Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigehiro, and Moriuchi, Hisako, to Morinaga Milk Industry Co., Ltd. Stilbene derivative and stilbene analog derivative, and use thereof, 5,589,506, Cl. 514.520.000.
 Hashimoto, Koji. *See*—
 Sato, Yuki; Ishizaki, Toshio; Sakaue, Tsuyoshi; Hashimoto, Koji; Yamada, Tohru, and Uwano, Tomoki, 5,589,724, Cl. 310.348.000.
 Hashimoto, Kouji, to Canon Kabushiki Kaisha. Electrophotographic image forming apparatus with toner box exchange alarm feature, 5,589,915, Cl. 399.120.000.
 Hashimoto, Seishiro, to Tsudakoma Kogyo Kabushiki Kaisha, and Kyowa Denki Kogyo Kabushiki Kaisha. Driving apparatus for needles of knitting machine, 5,588,312, Cl. 66.75.200.
 Hashiyama, Tomiki. *See*—
 Tsuyama, Kenji; Hashiyama, Tomiki; Ohashi, Motonori; and Nakatani, Noriyuki, 5,589,502, Cl. 514.449.000.
 Hassan, Ahmed A. *See*—
 Charles, Bruce D.; Hassan, Ahmed A.; Tadghighi, Hormoz; JanakRam, Ram D.; and Sankar, Lakshmi N., 5,588,800, Cl. 446.24.000.
 Hassler, Joseph A.; Deal, Gregory K.; Koss, Timothy A., and Heil, Stephen E., to Unisys Corporation. Method and apparatus for cache memory access with separate fetch and store queues, 5,590,379, Cl. 395.851.000.
 Hastings, Roger. *See*—

Scovil, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128.772.000.
 Hatakeyama, Akihito. *See*—
 Kawakita, Kouji; Fukumoto, Masahide; Horio, Yasuhiro; Nakatani, Seichi, and Hatakeyama, Akihito, 5,588,207, Cl. 29.852.000.
 Hatakeyama, Ko, to Kyodo Yushi Co., Ltd. Grease composition for constant velocity joints, 5,589,444, Cl. 508.168.000.
 Hatchell, Peter. *See*—
 Lotto, Ronald L.; Teske, Ernest H., and Hatchell, Peter, 5,588,644, Cl. 271.183.000.
 Hatfield, James C., to Amerchol Corporation. Hairsprays and acrylic polymer compositions for use therein, 5,589,157, Cl. 424.47.000.
 Hatoh, Kazuhito; Niikura, Junji; Yasumoto, Eiichi; and Gamou, Takaharu, to Matsushita Electric Industrial Co., Ltd. Molten carbonate fuel cell, 5,589,287, Cl. 429.41.000.
 Hattori, Kazuhiko, to Sumitomo Wiring Systems, Ltd. Connector, 5,588,883, Cl. 439.761.000.
 Hattori, Yoshihiro. *See*—
 Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tetsuo, 5,590,062, Cl. 364.578.000.
 Hauge, Robert H., and Pan, Chensu, to Rice University. Halogen-activated chemical vapor deposition of diamond, 5,589,231, Cl. 427.561.000.
 Haumann, Jürgen. *See*—
 Döbeling, Klaus; Haumann, Jürgen; Knöfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelmayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431.354.000.
 Hauptmann, Rudolf. *See*—
 Heckl, Konrad; Spevak, Walter; Ostermann, Elnborg; Zophel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratawa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435.189.000.
 Hausamann, Erich. *See*—
 Schneider, Werner; Letch, Hansueli; and Hausamann, Erich, 5,588,938, Cl. 482.4.000.
 Hausauer, Brian S. Clock doubler and smooth transfer circuit, 5,590,316, Cl. 395.586.000.
 Havard, John M. *See*—
 Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112.80.160.
 Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Romath, Paul D., to BioTransplant, Inc. Polynucleotides encoding porcine cytokines, 5,589,582, Cl. 536.23.500.
 Havell, Mark A.; Perry, David A.; Maeda, Hiroshi, and Ione, Junzuke, to Pfizer Inc. Process for producing antiparasitic macrolide antibiotics, 5,589,366, Cl. 435.119.000.
 Hayabuchi, Masahito. *See*—
 Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahito; Fukatsu, Akira; Mae, Toshiyuki; Kangawa, Masato; Fukumura, Kagenori; Oba, Hidehiko; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475.128.000.
 Hayakawa, Tsuneyasu, and Kimura, Makoto, to Paloma Kogyo Kabushiki Kaisha. Flame trap for use in a pulse combustor, 5,588,822, Cl. 431.1.000.
 Hayama, Hiroshi, to Sumitomo Electric Industries, Ltd. Heat-resistant, high-voltage lead wire for direct current, 5,589,219, Cl. 427.117.000.
 Hayashi, Masamichi. *See*—
 Kuwahara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Tetsuaki; Takahashi, Koji; Harada, Tamotsu; Komiya, Takeshi; Hirai, Fumio, and Hayashi, Masamichi, 5,590,388, Cl. 419.39.000.
 Hayat, Marc, and de Ferrari, Max. Tape recorder and offset playback apparatus with a variable tape length between the recording and reading head, 5,589,999, Cl. 360.85.000.
 Hayata, Hirofumi. *See*—
 Ftoh, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirofumi; Sakimura, Tomoo; Suzuki, Tomoko, and Kinoshita, Akira, 5,589,314, Cl. 430.126.000.
 Suzuki, Tomoko; Kinoshita, Akira; Hayata, Hirofumi; and Sakimura, Tomoo, 5,589,309, Cl. 430.59.000.
 Hayes, Brian B., and Hayes, Colin J., to Multico International Pty. Ltd. Fused electrical connectors, 5,588,876, Cl. 439.622.000.
 Hayes, Colin J. *See*—
 Hayes, Brian B., and Hayes, Colin J., 5,588,876, Cl. 439.622.000.
 Hayes, William J., to Shandon, Inc. Method of distributing material onto a microscope slide of a large cytology sample chamber, 5,589,400, Cl. 436.177.000.
 Hays, William D. *See*—
 Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455.51.200.
 Hazama, Hiroaki. *See*—
 Tomotaji, Yoko; Nakase, Makoto; Sato, Takashi; Hazama, Hiroaki; Komano, Haruki; and Ito, Shimechi, 5,589,305, Cl. 430.5.000.
 Hazlett, Lonnie G. *See*—
 Lai, Shih-Yaw; Hazlett, Lonnie G.; and Chunt, Pak-Wing S., 5,589,128, Cl. 264.328.100.
 Headrick, J. Charles. Continuous daylight sill with adaptable threshold caps and removable paint shield, 5,588,266, Cl. 52.204.100.
 Heagle, Timothy J. *See*—

Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J., and Schutt, Kerry D., 5,590,391, Cl. 423.253.000.
 Heartport, Inc. *See*—
 Taylor, Charles S.; Donlon, Brian S.; and Machold, Timothy R., 5,588,949, Cl. 600.166.000.
 Heath, Philip T., to Calsonic North America, Inc. Cleaning attachment for internal tube mandrel, 5,588,505, Cl. 184.18.000.
 Hebeisen, Paul. *See*—
 Gerwig, Jürgen; Gotschi, Erwin; Hebeisen, Paul; Link, Helmut; and Lübberts, Thomas, 5,589,473, Cl. 514.183.000.
 Hebert, Thomas K. *See*—
 King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Rombult, Philip A.; and Hebert, Thomas K., 5,589,973, Cl. 359.214.000.
 Hecht, Allen R. Gaming system and process for generating card faces, 5,588,913, Cl. 463.19.000.
 Hecht, David L. *See*—
 Curry, Douglas N.; and Hecht, David L., 5,589,870, Cl. 347.233.000.
 Heckl, Konrad; Spevak, Walter; Ostermann, Elnborg; Zophel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratawa, Christian; and Hauptmann, Rudolf, to Boehringer Ingelheim International GmbH. Human manganese superoxide dismutase (hMn-SOD), 5,589,371, Cl. 435.189.000.
 Hedderly, Gregory T., to Ford Motor Company. Collapsible steering column assembly, 5,588,332, Cl. 294.000.
 Hedley, Robert L., to Hedwell Engineering Pty. Ltd. Locking arrangement, 5,588,768, Cl. 403.294.000.
 Hedwell Engineering Pty. Ltd. *See*—
 Hedley, Robert L., 5,588,768, Cl. 403.294.000.
 Heeb, Jay; Shenoy, Sunil; and Wong, Jimmy, to Intel Corporation. Method and apparatus for dynamically expanding the pipeline of a microprocessor, 5,590,368, Cl. 395.800.000.
 Heeger, Alan. *See*—
 Wudl, Fred, and Heeger, Alan, 5,589,565, Cl. 528.205.000.
 Hegedus, Béla. *See*—
 Harsanyi, Kálmán; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kápolnás-Pap, Márta; Csizer, Éva; Hegedus, Béla; Szporny, László; Kiss, Béla; Kárpáti, Égon; Palosi, Éva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Anikó; Bod, Péter; Cséhi, Attila; Zolt, László; Erdélyi, Zsolt; Szabo, Sándor; Bod, Péter, and Cséhi, Attila, to Richter Gedeon Vegyeszet Gyár Rt. N-hydroxyalkyl-substituted 1,2,3,6-tetrahydropyridine and piperidine derivatives, 5,589,486, Cl. 314.317.000.
 Heidenberger Druckmaschinen AG. *See*—
 Becker, Willi, 5,588,365, Cl. 101.240.000.
 Friedrichs, Jens, and Helmstader, Karl Heinz, 5,588,773, Cl. 403.373.000.
 Löffler, Gerhard, 5,588,366, Cl. 101.484.000.
 Heikkilä, Samuli, to ABB Industry Oy. Method for determining a stator flux estimate for an asynchronous machine, 5,589,754, Cl. 318.805.000.
 Heil, Franz. *See*—
 Berger, Ernst; Heil, Franz; Schiffa, Herbert, and Tecchio, Piero, 5,589,674, Cl. 218.71.000.
 Heil, Stephen F. *See*—
 Hassler, Joseph A.; Deal, Gregory K.; Koss, Timothy A.; and Heil, Stephen F., 5,590,379, Cl. 395.851.000.
 Heilborn, Eric W. Collapsible pet bed, 5,588,393, Cl. 119.285.000.
 Heilmann, Ulrich. *See*—
 Ott, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heilmann, Ulrich, and Gilbert, John, 5,589,049, Cl. 204.504.000.
 Hein, David A., to Alcoa Fupkura Limited. Short circuit protected splice connector, 5,590,011, Cl. 361.106.000.
 Heine, Günter K. *See*—
 Dunfield, John C.; and Heine, Günter K., 5,590,003, Cl. 360.98.070.
 Heinrichs, Bernard, to Elan Energy Inc. Down-hole gas separator for pump, 5,588,486, Cl. 166.50.000.
 Heint, Robert V. *See*—
 Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heint, Robert V.; and Yoshida, Yoko, 5,589,247, Cl. 428.141.000.
 Helbl, Vera. *See*—
 Bujagl, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera, and Schnappinger, Dirk, 5,589,362, Cl. 435.69.100.
 Helena Laboratories Corporation. *See*—
 Sanford, James R. M.; Frank, Patrick M.; Gohas, Joseph H., and Jennings, William C., 5,589,063, Cl. 210.198.200.
 Helene Curtis, Inc. *See*—
 Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly, and Brucks, Richard M., 5,589,177, Cl. 424.401.000.
 Neill, Paul; Brandt, Loralen; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, 5,589,163, Cl. 424.70.510.
 Heller, David. *See*—
 Heller, Philip, and Heller, David, 5,589,985, Cl. 359.608.000.
 Heller, Philip, and Heller, David. Computer monitor hood, 5,589,985, Cl. 359.608.000.
 Hellums, James R. *See*—
 Phillips, Sabrina D., and Hellums, James R., 5,589,784, Cl. 327.18.000.
 Hellyer, James A. *See*—
 Guskey, Gerald J.; Hellyer, James A.; Kluesener, Bernard W.; and Stupp, Gordon K., 5,589,216, Cl. 426.607.000.
 Helms-Man Industrial Co., Ltd. *See*—
 Hung, Ng Y., 5,588,882, Cl. 439.741.000.

- Helmstädter, Karl-Heinz: See—
Friedrichs, Jens; and Helmstädter, Karl-Heinz, 5,588,773, Cl. 403-373,000.
- Helmstetter, Richard C.: See—
Schmidt, Glenn H.; and Helmstetter, Richard C., 5,588,922, Cl. 473-324,000.
- Schmidt, Glenn H., and Helmstetter, Richard C., 5,588,923, Cl. 473-340,000.
- Helsley, Grover C.: See—
Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37,300.
- HEM Trading: See—
Kelly, David L.; and Francies, Sidney E., III, 5,588,263, Cl. 52-125,400.
- Henderson, Lee W.: See—
Shockley, Ty R.; Martis, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, 5,589,197, Cl. 424-663,000.
- Hendrix, Charles E., to Alabama Power Company, Process for producing foamy iron, 5,588,982, Cl. 75-10,500.
- Henington, Paul, to Process Automation International Limited, Clamp for use with electroplating apparatus and method of using the same, 5,589,051, Cl. 205-80,000.
- Henkel Kommanditgesellschaft auf Aktien: See—
Pi, Raphael; Bigorra-Losas, Joaquin; Ponsati-Obiols, Oriol; and Schmid, Karl, 5,589,450, Cl. 510-535,000.
- Yamamura, Yoshitami; Morimoto, Nobuhiko; and Tanaka, Nobuyuki, 5,589,230, Cl. 427-493,000.
- Henry, Raymond C., to Ericsson Inc., Method and apparatus for a deep-sleep mode in a digital cellular communication system, 5,590,396, Cl. 455-33,100.
- Henry, Richard A., to Pricolair and hydrofluorocarbon aerosol preparations, 5,589,156, Cl. 424-45,000.
- Hepler, Douglas C., to Polysht Corporation, Compact disc injection molding apparatus, 5,589,206, Cl. 425-549,000.
- Heraeus Electrochemie GmbH: See—
Scannell, Robert; Busse, Bernd; and Vormwald, Helmut, 5,589,044, Cl. 204-286,000.
- Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., to Helene Curtis, Inc., Rinse-off water-in-oil-in-water compositions, 5,589,177, Cl. 424-401,000.
- Hercules Incorporated: See—
Grasso, Robert P.; O'Brien, Michael K.; and Shannon, Paul J., 5,589,100, Cl. 252-299,010.
- Herdies, Lydia: See—
De Beuckeleer, Marc; Herdies, Lydia; Gossele, Véronique; and Mariani, Celestina, 5,589,610, Cl. 800-205,000.
- Heribacka, Edward W.: See—
Hultman, David P.; Watson, Donald D.; and Heribacka, Edward W., 5,589,034, Cl. 162-111,000.
- Hermann, Allen M.: See—
Yandruski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., 5,589,845, Cl. 343-909,000.
- Hermann, Hans-Georg: See—
Hopf, Christian; and Hermann, Hans-Georg, 5,590,000, Cl. 360-96,500.
- Hermecz, István: See—
Magyar, Kálmán; Gaál, József; Székely, István; Lengyel, József; Szabó, Anna Z.; Mármárosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Kőröczky, Peter, 5,589,513, Cl. 514-654,000.
- Hernandez, Gilberto; Smith, Russell C.; and Bouvier, Daniel, Computer apparatus for suspension of computer expansion cards, 5,590,023, Cl. 361-683,000.
- Herold, Manfred; Hartung, Georg; Schutz, Hans-Willy; and Jung, Ulrich, to MAN Roland Druckmaschinen AG, Apparatus for metering liquid media in offset printing machines, 5,588,365, Cl. 101-350,000.
- Herskowitz, Ira: See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Rymji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6,000.
- Herzog, Larry R.: See—
Lashmett, Brent J.; Lashmett, Doug C.; Lashmett, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Merideth L., 5,589,004, Cl. 134-10,000.
- Hess, Randall L.; and Johnson, Drew S., to Compaq Computer Corporation, Method and apparatus for simulating user input device presence in a computer system, 5,590,315, Cl. 395-500,000.
- Hetherington, Ray C., to New Southland, Inc., Silicone elastomer seals for molded plastic parts, 5,589,119, Cl. 264-129,000.
- Heuser, Peter: See—
Kreuter, Peter; and Heuser, Peter, 5,588,411, Cl. 123-418,000.
- Hewlett-Packard CO: See—
Firooz, Kamran, 5,590,136, Cl. 371-25,100.
- Hewlett-Packard Company: See—
Beeson, Robert R., 5,589,865, Cl. 347-28,000.
- Chung, Shine; and Emerson, Paul G., 5,590,087, Cl. 365-230,050.
- Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L.; and Gamand, Patrice, 5,589,777, Cl. 324-537,000.
- Goto, Masaharu, 5,589,788, Cl. 327-276,000.
- Russell, Dale D., 5,589,311, Cl. 430-114,000.
- Russell, Todd L.; Richtsmeier, Brent W.; and Glassett, Kevin L., 5,589,866, Cl. 347-102,000.
- Shibata, Alan, 5,589,861, Cl. 347-22,000.
- Hibi, Kenichiro: See—
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okur, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218,000.
- Hibi, Takuo: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohlu, 5,589,596, Cl. 564-446,000.
- Hibner, John A.: See—
Conlon, Sean P.; Oureshi, Saleem U.; Hibner, John A.; Okoricha, Lavin O.; and Bishop, Gregory D., 5,588,581, Cl. 227-176,100.
- Hicks, Dennis G., to Converting, Inc., Method for forming pleats in a sheet-like material, 5,589,014, Cl. 156-73,100.
- Hida, Masanobu: See—
Ito, Kengo; Isaji, Kaori; Fujiwara, Yoshio; Isogai, Mitsuhiro; and Hida, Masanobu, 5,589,435, Cl. 503-227,000.
- Hida, Tetsuya: See—
Fujiwara, Katsuhide; Tahara, Eiichi; and Hida, Tetsuya, 5,588,657, Cl. 277-180,000.
- Hidaka, Hidemasa: See—
Adachi, Takashi; Ishii, Takafumi; and Hidaka, Hidemasa, 5,588,254, Cl. 47-57,600.
- Hidaka, Masumi: See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Rymji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6,000.
- Higashijima, Tsutomu, and Ross, Elliott M., to Board of Regents, The University of Texas, Methods and compositions for modulating G protein action, 5,589,568, Cl. 530-324,000.
- Higgins, H. Dan, and Normington, Peter, Die carrier apparatus, 5,589,781, Cl. 324-755,000.
- Higginson, Roy C., and Whiteman, Paul L., Modular truck cargo area body, 5,588,693, Cl. 246-183,000.
- Higgs, John E.: See—
Dear, Aiden R.; and Higgs, John E., 5,588,495, Cl. 173-170,000.
- Higo, Takashi: See—
Nakanishi, Shigeo; Tominaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki, 5,589,491, Cl. 514-338,000.
- Higuchi, Eiji, to Sumitomo Wiring Systems, Ltd., Fuse extraction tool, 5,588,341, Cl. 81-3,800.
- Higuchi, Shintaro: See—
Kikuchi, Shuichi; and Higuchi, Shintaro, 5,588,606, Cl. 242-347,000.
- Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru, to Nitto Denko Corporation, Vermen exterminating element and vermen exterminating method, 5,589,390, Cl. 435-307,100.
- HIH Biocenter, Inc.: See—
Hagiwara, Hideaki; and Suzuki, Toshiaki, 5,589,436, Cl. 504-114,000.
- Hika, Yoshimichi: See—
Ikuzawa, Kenzo; and Hika, Yoshimichi, 5,589,877, Cl. 348-186,000.
- Hikmet, Rifat A. M., to U.S. Philips Corporation, Optical modulation device having a polymer network containing free molecules of a chiral liquid crystalline material, 5,589,959, Cl. 349-88,000.
- Hildebrand, Gerald, to Bosch-Siemens Hausgerate GmbH, Automatic washing machine fitted for drying, 5,588,313, Cl. 68-17,000.
- Hilgenfeld, Rolf: See—
Ulrich, Norbert; Hilgenfeld, Rolf; Hanel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205,000.
- Hill, Craig S.: See—
Wolfert, Robert L.; and Hill, Craig S., 5,589,574, Cl. 530-388,260.
- Hill, Curtis J., Interchangeable eyes for fishing lures, 5,588,246, Cl. 43-42,060.
- Hill, Jeffrey V.: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmaul, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200,020.
- Hill, Joe T.; Fields, Gene M.; and Williams, John R., to Bristol Compressors, Inc., Scroll compressor having an axial compliance pressure chamber, 5,588,820, Cl. 418-55,400.
- Hillen, Wolfgang: See—
Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera; and Schnappinger, Dirk, 5,589,362, Cl. 435-69,100.
- Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmaul, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., to Thinking Machines Corporation, Parallel computer system with physically separate tree networks for data and control messages, 5,590,283, Cl. 395-200,020.
- Hillyard, David R.: See—
Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurino D., 5,589,340, Cl. 435-6,000.
- Hilyard, Kathy; Monticello, James; and Rugg, James, to Dade International Inc., Method and composition for the determination of red blood cell floate, 5,589,327, Cl. 435-4,000.
- Himes, Glenn R., to Shell Oil Company, Multiblock hydrogenated polymers for adhesives, 5,589,542, Cl. 525-98,000.
- Himura, Koichi: See—

- Imaichi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Himura, Koichi; and Haneda, Tadayoshi, 5,589,251, Cl. 428-209,000.
- Hind, Harry, to Hind Health Care, Inc., Method for treating nerve injury pain associated with shingles (herpes-zoster and post-herpetic neuralgia) by topical application of lidocaine, 5,589,180, Cl. 424-402,000.
- Hind Health Care, Inc.: See—
Hind, Harry, 5,589,180, Cl. 424-402,000.
- Hintzer, Klaus: See—
Felix, Bernd; Hintzer, Klaus; Löhr, Gernot; and Schöttle, Thomas, 5,589,558, Cl. 526-247,000.
- Hippe, Daniel A.: See—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474,130.
- Hiraga, Katsuya: See—
Onodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Tetsuo; and Itoh, Shigeo, 5,589,738, Cl. 315-169,100.
- Hirai, Fumio: See—
Kuwabara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Tetsuaki; Takahashi, Koji; Harada, Tamotsu; Komiyama, Takeshi; Hirai, Fumio; and Hayashi, Masamichi, 5,590,388, Cl. 419-39,000.
- Hirai, Toshikazu: See—
Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao, 5,590,412, Cl. 455-82,000.
- Hirai, Yoichi: See—
Yada, Yukihiko; and Hirai, Yoichi, 5,588,691, Cl. 296-93,000.
- Hiraishi, Masahiro; and Kuroda, Shin-ichi, to Shimadzu Corporation, Exhaust gas purifier, 5,588,292, Cl. 60-300,000.
- Hiramatsu, Osamu: See—
Kimura, Kazuya; Kayukawa, Hiroaki; Takeichi, Toru; and Hiramatsu, Osamu, 5,588,807, Cl. 417-222,200.
- Hiramoto, Masayoshi; Inoue, Osamu; Kugimiya, Koichi; and Iijima, Kenji, to Matsushita Electric Industrial Co., Ltd., Magnetic thin film, and method of manufacturing the same, and magnetic head, 5,589,221, Cl. 427-130,000.
- Hiramoto, Tatsumi: See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, 5,589,735, Cl. 313-638,000.
- Hiraoka, Hidenori; and Koizumi, Yoshimasa, to Sumitomo Rubber Industries, Ltd., Solid golf ball, 5,589,546, Cl. 525-193,000.
- Hiraoka, Soichiro, to Three Bond Co., Ltd., Adhesive composition and process for preparing it, 5,589,554, Cl. 525-530,000.
- Hirose, Norio: See—
Sugiyama, Hiroyuki; Hirose, Norio; Hamahuchi, Teruyoshi; and Muto, Hikoji, 5,588,362, Cl. 101-218,000.
- Hitachi Automotive Engineering Co., Ltd.: See—
Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155,000.
- Hitachi Cable, Ltd.: See—
Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, 5,589,668, Cl. 174-266,000.
- Hitachi Denshi Kabushiki Kaisha: See—
Tsukui, Akimi, 5,589,880, Cl. 348-229,000.
- Hitachi, Ltd.: See—
Abe, Seiichi, 5,590,082, Cl. 365-222,000.
- Arato, Toshiaki; Aono, Yasuhisa; Tsuruoka, Shigeo; and Komuro, Katsumi, 5,589,652, Cl. 75-235,000.
- Iguchi, Hiroaki; Kurosu, Yasuo; Fujinawa, Masaaki; Yokoyama, Yoshihiro; and Masuzaki, Hidefumi, 5,590,317, Cl. 395-602,000.
- Iwamura, Masahiro; Yamauchi, Tatsumi; Tanaka, Shigeyu; and Mori, Kazutaka, 5,590,361, Cl. 395-800,000.
- Kametani, Masatsugu; and Umekita, Kazuhiro, 5,590,030, Cl. 361-794,000.
- Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116,000.
- Kondo, Nobukazu; Kaneko, Seiji; Gemma, Hideaki; Okada, Tetsuhiko; Komori, Kazuhiko; and Okazawa, Koichi, 5,590,290, Cl. 395-298,000.
- Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, 5,589,270, Cl. 428-411,100.
- Murata, Tomohiro; Kunihara, Kenzo; Kawashima, Kazuhiro; and Niida, Mitsuaki, 5,590,272, Cl. 395-181,000.
- Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, 5,589,883, Cl. 348-379,000.
- Saito, Seiichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shikawa, Junji; and Kawamae, Osamu, 5,589,995, Cl. 360-48,000.
- Sakakihara, Tadayuki; Tanaka, Tetsuo; Tamaki, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuhiro, 5,590,353, Cl. 395-800,000.
- Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126,000.
- Tomomura, Yukiko; Sakurai, Yoshito; and Nishi, Yumiko, 5,590,180, Cl. 379-112,000.
- Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701,000.
- Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155,000.
- Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, 5,590,314, Cl. 395-681,000.
- Watahiki, Satoshi; and Shirakawa, Shingo, 5,590,018, Cl. 361-612,000.
- Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, 5,589,962, Cl. 349-46,000.
- Hitachi Maxell, Ltd.: See—
Kashiwakura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Itsuo; Oota, Norio; and Sugiyama, Hisanori, 5,590,097, Cl. 369-13,000.
- Hitachi Medical Corporation: See—
Kawai, Hiroyuki; Sekihara, Kensuke; and Migita, Shinichi, 5,590,164, Cl. 378-4,000.
- Hitachi Software Engineering Co., Ltd.: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701,000.
- Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, 5,590,314, Cl. 395-681,000.
- Hitachi System Engineering, Ltd.: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701,000.
- Hladik, Peter: See—
Brinker, Gerald; Hladik, Peter; and Gutwillig, Alan, 5,589,649, Cl. 73-866,000.
- Hlavka, Joseph J.: See—
Abajian, Henry B.; Noble, John F.; and Hlavka, Joseph J., 5,589,460, Cl. 514-17,000.
- Hlozek, Robert J.: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickney; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242,400.
- Ho, Teresa H.: See—
Kristenansky, John L.; Nestor, John J., Jr.; Ho, Teresa H.; Vickery, Brian H.; and Bach, Chinh T., 5,589,452, Cl. 514-12,000.
- Hoashi, Yoshiaki: See—
Kurashiki, Akira; Ando, Hiroshi; Kaneiwa, Toshiyuki; and Hoashi, Yoshiaki, 5,589,930, Cl. 356-5,010.
- Hobbs, Gregg K., to Qualmark Corporation, Exciter-mounting for shaker table, 5,589,637, Cl. 73-663,000.
- Hobbs, John W.; and Cramer, Laurence E., to Morgan Crucible Company plc, The, Side-pumped lasers, 5,590,147, Cl. 372-75,000.
- Hobby, Gray P.; and Riggs, Bernard A., to Systems Integration and Research, Inc., Bearing systems, 5,589,012, Cl. 148-561,000.
- Hoch, Robert: See—
Tennent, Howard G.; Barber, James J.; and Hoch, Robert, 5,589,152, Cl. 423-447,300.
- Hochlowski, Jill E.; Jackson, Marianna; Kadam, Sunil K.; Karawowski, James P.; and McAlpine, James B., to Abbott Laboratories, Dornigocin antitumor agents, 5,589,485, Cl. 514-315,000.
- Hodgson, Simon T.: See—
Nicol, Robin H.; Slater, Martin J.; and Hodgson, Simon T., 5,589,474, Cl. 514-211,000.
- Hoechst AG: See—
Sponheimer, Manfred; Welt, Guenther; and Ziegelmayer, Manfred, 5,589,589, Cl. 536-86,000.
- Hoechst Aktiengesellschaft: See—
Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228,000.
- Felix, Bernd; Hintzer, Klaus; Löhr, Gernot; and Schöttle, Thomas, 5,589,558, Cl. 526-247,000.
- Krahn, Wolfgang; Ernst, Johannes; and Drabent, Claudia, 5,589,430, Cl. 501-120,000.
- Naik, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansi; Blumberg, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681,000.
- Neuert, Richard; and Stein, Gerhard, 5,589,265, Cl. 428-361,000.
- Schwab, Michael; Walz, Gerd; and Merten, Gerhard, 5,589,535, Cl. 524-591,000.
- Ulrich, Norbert; Hilgenfeld, Rolf; Hanel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205,000.
- Hoechst Marion Roussel, Inc.: See—
Glamkowski, Edward J.; and Chiang, Yulin, 5,589,495, Cl. 514-373,000.
- Hoechst-Roussel Pharmaceuticals, Inc.: See—
Strupczewski, Joseph T.; and Glamkowski, Edward J., 5,589,488, Cl. 514-321,000.
- Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37,300.
- Hoefnagels, Johannes F.: See—

- Van Es, Arthur R.; Van Engelen, Gerard; De Nier, Theodor H. M.; and Hoefnagels, Johannes F., 5,588,607, Cl. 242-356.300.
- Hoeltke, Larry; and Fischer, Roger, to Shur-Line, Inc. Drive drive shaft for a paint brush and roller cover cleaning machine. 5,588,221, Cl. 34-58.000.
- Hoffman, Leslie M., to Mycogen Plant Science, Inc. Monocot seed storage proteins in dicots. 5,589,616, Cl. 800-205.000.
- Hoffmann-La Roche Inc. See—
- Geiwiz, Jürgen; Götschi, Erwin; Hebeisen, Paul; Link, Helmut; and Lübbers, Thomas, 5,589,473, Cl. 514-183.000.
- Kaufman, Richard A.; Konopka, John M.; Rosenfeld, Henry J.; and Sabo, Janine E., 5,589,348, Cl. 435-26.000.
- Hofmann, Jim; and Stansbury, Darryl, to Micron Display Technology, Inc. Method for forming a screen for screen printing a pattern of small closely spaced features onto a substrate. 5,588,359, Cl. 101-128.210.
- Hofmann, Johann H. See—
- Houze, Randall H.; Hofmann, Johann H.; and Birck, Freddie C., 5,588,786, Cl. 405-285.000.
- Hofmeister, Christopher A. See—
- Muka, Richard S.; and Hofmeister, Christopher A., 5,588,789, Cl. 414-217.000.
- Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vergande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripukaran, Raghavan; Jayasimha; Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., to Link USA Corporation. Call-processing system and method. 5,590,181, Cl. 379-114.000.
- Hojo, Yasuo. See—
- Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukasui, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Holder, John D., to MEMC Electronic Materials, Inc. Method for preparing molten silicon melt from polycrystalline silicon charge. 5,588,993, Cl. 117-13.000.
- Holka, Thomas C., to Ford Motor Company. Ducted cooling system for an automotive vehicle. 5,588,482, Cl. 165-44.000.
- Holland, Herbert W. Liquid hydrocarbon sorbing and solidifying pillow. 5,588,785, Cl. 405-270.000.
- Holland, John. See—
- Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrop, Robert, 5,589,737, Cl. 315-111.210.
- Hollmann, Joerg W., to Hughes Electronics. Apparatus for measuring the curvature of a surface using moveable reflecting and focusing elements. 5,589,940, Cl. 356-376.000.
- Hollowell, J.; Rhoads, H.; Benninghaus, James R.; and Hansen, Daniel J., Jr., to Apple Computer, Inc. Method and apparatus for thermal management in a computer system. 5,590,061, Cl. 364-571.030.
- Hollub, Seth D., to Nellcor Incorporated. Acoustic impulse respirometer and method. 5,588,439, Cl. 128-721.000.
- Holman, John A. One man lift for motorcycles. 5,588,639, Cl. 254-133.000.
- Holmberg, Lars, to Pharmacia LKB Biotechnology AB. Nucleosides attached to a solid support through a 3'-silyl linkage and their use in oligonucleotide synthesis. 5,589,586, Cl. 536-25.300.
- Holmén, Anders. See—
- Hansson, Stig G. V., and Holmén, Anders, 5,588,838, Cl. 433-173.000.
- Holmes, William K.; Jonekis, Albert E.; and Wong, Kwok W., to Boart Longyear Company. Saw assembly with handle-actuated guide mechanism. 5,588,418, Cl. 125-13.010.
- Holmgren, Bertil, to M W Trading APS. Safety device for a box. 5,588,315, Cl. 70-57.100.
- Holophone Corporation. See—
- Subisak, Gregory J.; and Hammond, Douglas S., 5,588,742, Cl. 362-291.000.
- Holoubek, Kevin J.; Keniuk, Richard J.; and Bontrager, Paul R., to Motorola, Inc. Method and apparatus for stabilizing the gain of a control loop in a communication device. 5,590,418, Cl. 455-126.000.
- Holt, David C. See—
- Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., 5,589,614, Cl. 800-205.000.
- Holt, James. See—
- Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, 5,590,055, Cl. 364-550.000.
- Hornier, Robert J., to Douglas & Lomason Company. Child safety seat with side bolsters. 5,588,700, Cl. 297-238.000.
- Honda, Atsushi. See—
- Kono, Katsumi; Nakamura, Shinya; and Honda, Atsushi, 5,588,937, Cl. 477-169.000.
- Honda Giken Kogyo Kabushiki Kaisha. See—
- Gotou, Shinichiro, 5,588,733, Cl. 362-37.000.
- Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hiroto, and Yamamoto, Yoshio, 5,588,414, Cl. 123-571.000.
- Ito, Katsuhiko; Kobayashi, Hideo; Ishiuchi, Yukio; and Shimada, Toshio, 5,588,406, Cl. 123-90.340.
- Kuwahara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Teruaki; Takahashi, Koji; Harada, Tamotsu; Komiyama, Takeshi; Hirai, Fumio; and Hayashi, Masamichi, 5,590,388, Cl. 419-39.000.
- Matsumoto, Yukihiro; and Yokotaki, Hisashi, 5,588,401, Cl. 123-41.310.
- Nishihara, Takashi; Ikeda, Toru; Yano, Osamu; and Shiraishi, Shuji, 5,589,815, Cl. 340-444.000.
- Sato, Yutaka; Morita, Koichi; Fujimoto, Shiro; Ichihashi, Satoru; and Ohsawa, Kohji, 5,588,208, Cl. 29-888.044.
- Sawa, Atsushi; and Kawakubo, Hiroyuki, 5,588,405, Cl. 123-90.330.
- Schleicher, Ulrich; Klobner, Martin; Schwarz, Wolfgang; and Feuerstake, Eugen, 5,589,662, Cl. 149-35.000.
- Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161.000.
- Urakami, Fukashi, 5,588,900, Cl. 451-92.000.
- Yoshida, Masami; and Okazaki, Hidetsugu, 5,588,697, Cl. 297-173.000.
- Honda, Keiichi. See—
- Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao, 5,590,412, Cl. 455-82.000.
- Honda, Masami; and Kawahata, Kazuaki, to Kabushiki Kaisha Toshiba. Portable electronic apparatus having a plurality of card storage portions for removably housing a memory card. 5,590,024, Cl. 361-684.000.
- Honda, Minoru. See—
- Tanaka, Yutaka; and Honda, Minoru, 5,590,153, Cl. 375-222.000.
- Honeywell, Inc. See—
- Biard, James R., 5,589,935, Cl. 356-339.000.
- Davidson, Dale D.; and Sadeghpour, Hamid R., 5,589,749, Cl. 318-564.000.
- Ehlers, Wayne L.; Eichholz, Kenneth L., Jr.; and Johnston, Mark E., 5,588,202, Cl. 29-606.000.
- Krahn, Donald R., 5,589,769, Cl. 324-207.260.
- Hongo, Kazuya; and Takimoto, Hitoshi, to Fuji Xerox Co., Ltd. Process for producing chloroaluminum phthalocyanine crystal. 5,588,991, Cl. 117-2.000.
- Hoopingarner, Neil L.; and Matin, Barry D., to Boeing Company, The. Prescored foam for panel fabrication. 5,589,016, Cl. 156-87.000.
- Hopf, Christian; and Hermanni, Hans-Georg, to U.S. Philips Corporation. Pivoting device for a shutter arranged in the area of the insertion opening of the loading mechanism of a magnetic-tape cassette apparatus. 5,590,000, Cl. 360-96.500.
- Hopf, Jochen. See—
- Lindenmeier, Heinz; Hopf, Jochen; and Ritter, Leopold, 5,589,839, Cl. 343-713.000.
- Hopkins, David P. See—
- Khan, Azhar J.; Hopkins, David P.; and Khan, Mohammad A., 5,589,120, Cl. 264-130.000.
- Hopson, David R. See—
- Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Kerry D., 5,590,391, Cl. 423-253.000.
- Horal, Peter. See—
- Vahne, Anders; Svennerholm, Bo; Rynio, Lars; Jeansson, Stig; and Horal, Peter, 5,589,175, Cl. 424-208.100.
- Hori, Tadashi. See—
- Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tanura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249.000.
- Hori, Tazou. See—
- Kozuki, Susumu; Horigaya, Isao; and Hori, Tazou, 5,589,943, Cl. 386-121.000.
- Horiba, Ltd. See—
- Nomura, Toshiyuki; Tsujioka, Yuji; and Osuga, Naohiro, 5,588,748, Cl. 374-158.000.
- Horie, Seiji; Sano, Kenji; Suzuki, Nobuo; and Watarai, Shu, to Fuji Photo Film Co., Ltd. Liquid developer for electrostatic photography. 5,589,312, Cl. 430-115.000.
- Horioka, Hiroshi; and Kondo, Kazuhiro, to Tanabe Seiyaku Co., Ltd. Process for preparing β -lactam derivative and synthetic intermediate. 5,589,592, Cl. 540-204.000.
- Horiuchi, Yuzo. See—
- Kano, Jiro; Orii, Ryuji; Horiuchi, Yuzo; and Ito, Mutsuhiro, 5,589,150, Cl. 423-338.000.
- Horio, Yasukiho. See—
- Kawakita, Kouji; Tsukamoto, Masahide; Horio, Yasukiho; Nakatani, Seiichi; and Hatakeyama, Akihito, 5,588,207, Cl. 29-852.000.
- Horiuchi, Tetsuya. See—
- Gohno, Makoto; and Horiuchi, Tetsuya, 5,590,165, Cl. 378-18.000.
- Horizon Directional Systems, Inc. See—
- Houmand, Mitchell J.; and Kraus, James E., 5,588,818, Cl. 418-5.000.
- Hörlein, Rolf. See—
- DeLossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228.000.
- Horron, Jacques, to Advanced Elastomer Systems, L.P. Soft thermoplastic elastomers having improved resistance to oil swell and compression set. 5,589,544, Cl. 525-176.000.
- Horrobin, David E., to Elamol Limited. Methods of reducing porphyrin toxicity using fatty acids. 5,589,509, Cl. 514-560.000.
- Horsten, Bart. See—
- Deheuw, Geert; Janssens, Wilhelms; Uytterhoeven, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, 5,589,317, Cl. 430-203.000.
- Hoshino, Masataka; and Misawa, Nobuhiro, to Fujitsu Limited. Process of selective area chemical vapor deposition of metal films. 5,589,425, Cl. 427-250.000.
- Hoshino, Ryo. See—
- Mitomi, Masako; and Hoshino, Ryo, 5,588,569, Cl. 224-153.000.

- Hosoi, Kiyoshi; and Matsuda, Tsukasa, to Fuji Xerox Co., Ltd. Ink jet recording paper. 5,589,259, Cl. 428-323.000.
- Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, to Minolta Co., Ltd. Light measuring apparatus capable of measuring ambient light and flash light. 5,589,934, Cl. 356-218.000.
- Hospal AG. See—
- Audemard, Gilles, 5,590,237, Cl. 388-832.000.
- Hotaling, Bryan R. See—
- Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 5,588,158, Cl. 4-572.100.
- Hotchkiss, Adair J.; O'Connor, John V.; and Spellman, Michael W., to Genentech, Inc. Human tissue-type plasminogen activator variant. 5,589,361, Cl. 435-69.100.
- Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kadera, Yasuto; and Nakamura, Katsutoshi, to Canon Kabushiki Kaisha. Ferroelectric liquid crystal device with minute convexities between adjacent electrodes. 5,589,964, Cl. 349-160.000.
- Hou, Janpu. See—
- Rapport, William R.; and Hou, Janpu, 5,589,931, Cl. 356-33.000.
- Houmand, Mitchell J.; and Kraus, James E., to Horizon Directional Systems, Inc. Rotor-to-rotor coupling. 5,588,818, Cl. 418-5.000.
- House, Randall H.; Hofmann, Johann H.; and Birck, Freddie C., to Marilyn House. Combination retaining wall and method of construction. 5,588,786, Cl. 405-285.000.
- Hovland, Roy S. See—
- Maltais, Jo-Ann B.; Wood, Archie T.; and Hovland, Roy S., 5,589,070, Cl. 210-636.000.
- Howard, J. Richard. See—
- Juchymenko, Victor Y.; Howard, J. Richard; Laczynski, Andrew J.; and Angus, James S., 5,588,235, Cl. 40-547.000.
- Howard, Kevin E., to Dow Chemical Company, The. Epoxy polymer filled with aluminum nitride-containing polymer and semiconductor devices encapsulated with a thermosetting resin containing aluminum nitride particles. 5,589,714, Cl. 257-788.000.
- Howard, Kevin E. See—
- Gares, Juan M.; Millar, Dean M.; and Howard, Kevin E., 5,589,153, Cl. 423-705.000.
- Howard, Richard. Composition and method for preventing moss growth on roofs. 5,589,229, Cl. 427-421.000.
- Howe, Peter. See—
- Russell-Jones, Gregory J.; Howe, Peter; de Aizputua, Henry J.; and Burge, Geoffrey L., 5,589,463, Cl. 514-21.000.
- Howe, Roger T. See—
- Lin, Liwei; Nguyen, Clark T.; Howe, Roger T.; and Pisano, Albert P., 5,589,082, Cl. 216-2.000.
- Howe, Wayne; and Malik, Dale, to BellSouth Corporation. Method and apparatus for communications monitoring. 5,590,171, Cl. 379-33.000.
- Hoves, Ronald B. See—
- Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700.000.
- Howington, Lee. See—
- Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, 5,590,055, Cl. 364-550.000.
- Howmedica. See—
- Tanaka, Kazuna; Kapeck, Jeffrey; and Chochinov, Allan B., 5,588,745, Cl. 366-130.000.
- Hoy, Angela C. See—
- Talamo, John A.; and Hoy, Angela C., 5,588,734, Cl. 362-61.000.
- Hozumi, Ichiro. See—
- Iida, Hirotada; Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, 5,589,315, Cl. 430-163.000.
- Hozumi, Toshiaki; and Ogawa, Hidehiro, to Nikon Corporation. Camera having an information setting apparatus for setting photographic data. 5,589,907, Cl. 396-287.000.
- Hreha, Kenneth W. See—
- Rust, Howell B.; and Hreha, Kenneth W., 5,588,343, Cl. 81-489.000.
- Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hiroto, and Yamamoto, Yoshio, to Siemens Electric Limited; and Honda Giken Kogyo Kabushiki Kaisha. Construction for maintaining assembled axial integrity of an electrically actuated valve. 5,588,414, Cl. 123-571.000.
- Hsieh, Daniel Ming-Te. See—
- Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828.000.
- Hsu, Jon S., to Sony Corporation; and Materials Research Corporation. In-plane parallel bias magnetic field generator for sputter coating magnetic materials onto substrates. 5,589,039, Cl. 204-192.120.
- Hsu, Ting-Chen. See—
- White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hui, 5,589,423, Cl. 437-228.000.
- Hsueh, Tien-Chu. Reclinable motorcycle backrest with saddle cushion cover having sun ray blocking function. 5,588,698, Cl. 297-184.110.
- HTM Sport S.p.A. See—
- Garofalo, Giovanni, 5,588,890, Cl. 441-64.000.
- Huang, Angus. Lamp holder assembly. 5,588,741, Cl. 362-267.000.
- Huang, Jack; Chiang, Chung-Ping; and Feng, Chan-Hua, to Industrial Technology Research Institute. Rotary shifter for bicycle. 5,588,331, Cl. 74-489.000.
- Huang, Yennun. See—
- Fuchs, Wesley K.; Huang, Yennun; and Wang, Yi-Min, 5,590,277, Cl. 395-183.140.
- Hubbell Incorporated. See—
- Anthony, John C., 5,588,853, Cl. 439-136.000.
- Boteler, William C.; and Klein, Lawrence J., 5,588,870, Cl. 439-467.000.
- Huber, Edgar. See—
- Röck, Erich; and Huber, Edgar, 5,588,730, Cl. 312-348.200.
- Hueck, Kamla P.; Rodgers, Scott D.; and Glew, Andrew F., to Intel Corporation. Address generation unit with segmented addresses in a microprocessor. 5,590,297, Cl. 395-401.000.
- Hudak, Philip J. See—
- Lemp, Steven K.; Hudak, Philip J.; and Love, Charles S., 5,588,967, Cl. 606-167.000.
- Hudson, Harold D. See—
- Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828.000.
- Huete, David A. See—
- Smolinski, Susan L.; Morrison, Denby G.; Marshall, Peter W.; and Huete, David A., 5,588,781, Cl. 405-195.100.
- Hughes Aircraft Company. See—
- Gold, Ronald S., 5,589,726, Cl. 313-161.000.
- Robinson, Klaus; and Garvin, Hugh L., 5,589,042, Cl. 204-192.340.
- Sobhani, Mohi, 5,588,843, Cl. 439-22.000.
- Yuan, Lin-Sen; and Yuan, Lu, 5,589,095, Cl. 508-168.000.
- Hughes, Arthur T. See—
- Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramchandran, Karapurath, 5,590,046, Cl. 364-474.130.
- Hughes Electronics. See—
- Hollmann, Joerg W., 5,589,940, Cl. 356-376.000.
- Long, Lynn E.; and Lum, Joan L., 5,589,274, Cl. 428-215.000.
- Soleimani, Mohammad; Corrigan, John E., III; Bukhari, Mohammad; and Roos, David A., 5,589,837, Cl. 342-359.000.
- Hughes, Jeffrey T., to Hughes Products Company, Inc. Gun barrel cleaning rod and method. 5,588,242, Cl. 42-95.000.
- Hughes, Philip. See—
- Terman, Michael; Fairhurst, Stephen; Hughes, Philip; and Levitt, Joel, 5,589,741, Cl. 315-360.000.
- Hughes Products Company, Inc. See—
- Hughes, Jeffrey T., 5,588,242, Cl. 42-95.000.
- Hughes, Tim P. See—
- Mills, Vincent; and Hughes, Tim P., 5,588,943, Cl. 493-58.000.
- Hughett, Elmer; and Alexandres, Richard B. Method for vacuum filling and sealing of a battery cell. 5,588,970, Cl. 29-623.200.
- Hultman, David P.; Watson, Donald D.; and Herbacka, Edward W., to Kimberly-Clark Corporation. Polymer-reinforced paper having improved cross-direction tear. 5,589,034, Cl. 162-111.000.
- Humphrey, John W. See—
- Scovil, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772.000.
- Hung, Ng Y., to Helms-Man Industrial Co., Ltd. Wall socket with twist lock prongs. 5,588,882, Cl. 439-741.000.
- Hunklinger, Herbert. See—
- Klein, Joachim; and Hunklinger, Herbert, 5,588,809, Cl. 417-283.000.
- Hunt, Warren F. See—
- Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., 5,589,843, Cl. 343-820.000.
- Hunter, Ronald A., to Atlantic Construction Fabrics, Inc. Multiple cellular confinement assembly for plant propagation. 5,589,240, Cl. 428-34.100.
- Hunter, Wood E.; Frederick, Kevin W.; and Loeffler, Randy J., to Calgon Corporation. Process for preparing novel high solids non-aqueous polymer compositions. 5,589,525, Cl. 523-331.000.
- Hurford, Jonathan P. See—
- Boumarah, Mohamed; Hurford, Jonathan P.; Collier, William V.; and Lichlyter, Ralph, 5,588,671, Cl. 280-730.200.
- Karlows, James P.; Boumarah, Mohamed; and Hurford, Jonathan P., 5,588,672, Cl. 280-730.200.
- Hurley, William W. High capacity conversion magazine. 5,588,241, Cl. 42-50.000.
- Huron Tech Incorporated. See—
- Moran, Stephen W.; Jackson, John R.; Gallivan, Timothy J.; and Loftfield, Richard E., 5,589,053, Cl. 205-698.000.
- HUSCO International, Inc. See—
- Wilke, Raud A., 5,588,510, Cl. 188-299.000.
- Huslig, Dan. See—
- Samson, Randall J.; Budlong, Allan; and Huslig, Dan, 5,590,402, Cl. 455-44.000.
- Huston, Paul O. Discharge stream conditioner and method. 5,588,987, Cl. 95-260.000.
- Hutchinson, Franklin D. See—
- Schmidt, William P.; and Hutchinson, Franklin D., 5,589,984, Cl. 359-603.000.

Hutson, Clifford L., and Demangus, Robert. Eye spray mist dispenser. 5,588,564, Cl. 222-383.100.

Hutter, Robert J.; Martin, Christopher J., and Roesner, Thomas W., to Ford Motor Company. Air outlet register for an opening in a vehicle. 5,588,910, Cl. 454-154.000.

Hwang, Emerald. See—
Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James. 5,590,055, Cl. 364-550.000.

Hybritech, Incorporated. See—
Wolfe, Robert L., and Hill, Craig S. 5,589,574, Cl. 530-388.260.

Hyodo, Hiroshi, to Kyoto Daiichi Kagaku Co., Ltd. Data managing method in portable blood sugar value-measuring and portable blood sugar value-measuring apparatus using same. 5,589,045, Cl. 204-406.000.

Hyperion Catalysis International, Inc. See—
Tennent, Howard G.; Barber, James J., and Hoch, Robert. 5,589,152, Cl. 423-447.300.

Hytech Pumps International, Inc. See—
De Santis, Gerard J. 5,588,808, Cl. 417-225.000.

Hyundai Electronics Industries Co., Ltd. See—
Lee, Dong M. 5,590,077, Cl. 365-189.050.
Yuh, Jong H., and Nam, Jong G. 5,590,085, Cl. 365-230.030.

Hyundai Motor Company, Ltd. See—
Moon, Tae J. 5,588,664, Cl. 280-689.000.
Sim, Hwan-Oh. 5,588,305, Cl. 62-419.000.

I.D.E.A. Corporation, The. See—
Harvey, Stephen. 5,590,022, Cl. 361-683.000.

I. Krüger Systems A/S. See—
Nielsen, Martinus K. 5,589,068, Cl. 210-614.000.

I.M.A. Industria Macchine Automatiche S.p.A. See—
Tagliaferri, Roberto, and Caroli, Rodolfo. 5,588,643, Cl. 271-35.000.

Iadonato, Kevin R. See—
Deosaran, Trevor A.; Garg, Sanjay; and Iadonato, Kevin R. 5,590,295, Cl. 395-393.000.

Iannuzzi, James M., to SGS-Thomson Microelectronics, Inc. Adaptive voltage regulator. 5,589,762, Cl. 323-351.000.

Ibamoto, Masahiko. See—
Uchida, Makoto; Ibamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi. 5,588,936, Cl. 477-155.000.

Ibiden Co., Ltd. See—
Asai, Motoo; and Kato, Ritsuko. 5,589,250, Cl. 428-209.000.
Enomoto, Ryo, and Asai, Motoo. 5,589,255, Cl. 428-261.000.

Ichihashi, Satoru. See—
Sato, Yutaka; Monta, Koichi; Fujimoto, Shuzo; Ichihashi, Satoru; and Ohnawa, Kohji. 5,588,208, Cl. 29-888.044.

Ide, Hiroshi. See—
Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seirichi; Shigenatsu, Kazuo; and Toda, Tsuyoshi. 5,590,111, Cl. 369-116.000.

Ide, Mitsuru. See—
Kinoshita, Shinji; and Ide, Mitsuru. 5,588,753, Cl. 384-488.000.

Ide, Motoki; and Shibayama, Hiroaki, to NEC Corporation. Selective-calling receiver with battery switching upon CPU stop detection. 5,590,401, Cl. 455-38.300.

Ide, Nobuhiko; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, to Kabushiki Kaisha Toshiba. Pipeline information processing circuit for floating point operations. 5,590,365, Cl. 395-394.000.

Ideguchi, Tetsuo. See—
Seno, Shoichiro; and Ideguchi, Tetsuo. 5,590,328, Cl. 395-675.000.

Idei, Takashi; Sagara, Shoichi; and Fujiyoshi, Kentaro, to Fanuc Ltd. Acceleration/deceleration control apparatus for numerical control apparatus. 5,589,750, Cl. 318-573.000.

Idemitsu Kosan Co., Ltd. See—
Egawa, Tatsuya; Kawaguchi, Yasuhiro; Mogami, Kenji, and Shimizu, Nobuaki. 5,589,597, Cl. 568-608.000.

IEC Corporation. See—
Crockett, Gary B. 5,590,188, Cl. 379-225.000.

Igarashi, Takeshi. See—
Arai, Fuminori; and Igarashi, Takeshi. 5,589,347, Cl. 435-11.000.

Igarashi, Tatsushi. See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi. 5,589,735, Cl. 313-638.000.

Ignon, Roger G.; and Thomas, Ronald E. Jr., to Stackhouse, Inc. Surgical gown. 5,588,153, Cl. 2-457.000.

Iguchi, Hiroaki; Kurosu, Yasuo; Fujinawa, Masaaki; Yokoyama, Yoshihiro; and Masuzaki, Hidenori, to Hitachi, Ltd. Document information compression and retrieval system and document information registration and retrieval method. 5,590,317, Cl. 395-602.000.

Iguchi, Kesayoshi, to Matsushita Electric Industrial Co., Ltd. Electronic cash register system. 5,589,676, Cl. 235-7.000.

Iida, Hirotsada; Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, to Toyo Gosei Kogyo Co., Ltd. Photosensitive compositions comprising photosensitive polyfunctional aromatic diazo compounds, and presensitized lithographic plates formed with the same. 5,589,315, Cl. 430-163.000.

Iida, Kouzo. See—
Mori, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo. 5,589,146, Cl. 423-237.000.

Iida, Shuichi; and Oyama, Masayuki, to NEC Corporation. Nide information collecting method in a ring system. 5,590,117, Cl. 370-248.000.

Iida, Yoshikatsu. See—
Suzuki, Toshio, and Iida, Yoshikatsu. 5,588,416, Cl. 123-684.000.

Iijima, Kenji. See—
Hiramoto, Masayoshi; Inoue, Osamu; Kugimiya, Koichi; and Iijima, Kenji. 5,589,221, Cl. 427-130.000.

Iinuma, Shoji. See—
Yoshimura, Toshifumi; Kikuchi, Ryo; and Iinuma, Shoji. 5,588,674, Cl. 280-732.000.

Ikeda, Keijiroh, to Yanaha Hatsudoki Kabushiki Kaisha. Watercraft. 5,588,887, Cl. 440-88.000.

Ikeda, Kunitoshi. See—
Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikiyo; and Koeda, Takashi. 5,588,950, Cl. 600-178.000.

Ikeda, Miyuki. See—
Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagin, Etsuhiro. 5,589,883, Cl. 348-379.000.

Ikeda, Tadaaki. See—
Sakakibara, Hisayoshi; Okada, Tomoo; and Ikeda, Tadaaki. 5,588,590, Cl. 236-92.000.

Ikeda, Toru. See—
Nishihara, Takashi; Ikeda, Toru; Yano, Osamu; and Shiraishi, Shuji. 5,589,815, Cl. 340-444.000.

Ikeda, Yuji; and Fujita, Minoru, to Canon Kabushiki Kaisha. Natural language processing apparatus and method for performing processing to analyze the meaning of an input sentence entered in the form of a natural language. 5,590,039, Cl. 395-759.000.

Ikegami, Kiyoshi. See—
Kuwahara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Teruaki; Takahashi, Koji; Harada, Tamotsu; Koriyama, Takeshi; Hirai, Fumio; and Hayashi, Masamichi. 5,590,388, Cl. 419-39.000.

Ikegami, Yasuyuki. See—
Uehara, Haruo; and Ikegami, Yasuyuki. 5,588,297, Cl. 60-673.000.

Ikenoue, Yoshiaki. See—
Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saïda, Yoshihiro; and Ikenoue, Yoshiaki. 5,589,270, Cl. 428-411.100.

Iketaki, Yoshinori, to Olympus Optical Co., Ltd. X-ray microscope. 5,590,168, Cl. 378-43.000.

Ikumi, Tohru; Suzuki, Nobuhiko; and Ishikawa, Satoshi, to Yazaki Corporation. Electrical connection device between handle and steering column. 5,588,854, Cl. 439-164.000.

Ikunami, Yoshikazu; Minami, Satoshi; and Fujii, Yozo, to Konica Corporation. Toner cartridge and color image forming apparatus in use therewith. 5,589,919, Cl. 399-262.000.

Ikuzawa, Kenzo; and Hika, Yoshimichi, to Leader Electronics Corporation. Automatic amplitude control circuit for a vector scope. 5,589,877, Cl. 348-186.000.

Iles, Kenneth E. See—
Kim, Young R.; Iles, Kenneth E.; and Larue, Roderick W. 5,589,394, Cl. 436-63.000.

Illinois Tool Works Inc. See—
Swain, Henry L. 5,588,187, Cl. 24-587.000.

Imai, Keisuke; Kato, Keiichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, to Kabushiki Kaisha Tokai-Rika-Denki Seisakusho. Pretensioner. 5,588,608, Cl. 242-374.000.

Imachi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Himura, Koichi; and Haneda, Tadayoshi, to Tokai Electronics Co., Ltd. Resonant tag and method of manufacturing the same. 5,589,251, Cl. 428-209.000.

Imaoka, Toshikazu. See—
Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao. 5,590,412, Cl. 455-82.000.

Immunex Corporation. See—
Smith, Craig A.; Larsen, Alf D.; Sims, John E., and Curtis, Benson M. 5,589,456, Cl. 514-12.000.

Implanted Material Technology, Inc. See—
Meyyappan, Narayanan; and Nakato, Tatsuo. 5,589,407, Cl. 437-26.000.

Imran, Mir A.; Pomeranz, Mark L.; and Glynn, Brian A., to Cardiac Pathways Corporation. Steerable catheter with adjustable bend location and/or radius and method. 5,588,964, Cl. 604-95.000.

INTEC. See—
Argent, Ronald D., and Bolin, James A. 5,588,978, Cl. 65-29.100.

Inaba, Naoto. See—
Sato, Masahiro; and Inaba, Naoto. 5,589,947, Cl. 386-96.000.

Inagaki, Jiro; Shinoki, Takashi; and Iiani, Atsushi, to Teikoku Tsushin Kogyo Co., Ltd. Method of enlarging design provided on a synthetic resin film. 5,589,121, Cl. 264-132.000.

Inagami, Yasuhiro. See—
Sakakibara, Tadayuki; Tanaka, Teruo; Tamaki, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuhiro. 5,590,353, Cl. 395-800.000.

Inanaga, Kiyofumi; and Yamada, Yuji, to Sony Corporation. System and method for reproducing sound. 5,590,094, Cl. 369-4.000.

Independent Enclosures, Inc. See—
Guevara, Nelson V. 5,590,191, Cl. 379-451.000.

Indian Head Industries, Inc. See—
Plantan, Ronald S., and Dangson, Henry T. 5,588,348, Cl. 92-63.000.

Indresco Inc. See—
Pennison, Robert A. 5,588,903, Cl. 451-344.000.

Industrial Technology Research Institute. See—

Chen, Li-Yu. 5,588,930, Cl. 475-300.000.

Huang, Jack; Chiang, Chung-Ping; and Feng, Chan-Hua. 5,588,331, Cl. 74-489.000.

Lin, Lie-Der; and Ju, Jiunn-Ming. 5,589,850, Cl. 345-132.000.

Infiltrator Systems Inc. See—
Nichols, James M.; and Coppes, Bryan A. 5,588,778, Cl. 405-48.000.

Information Builders, Inc. See—
Cohen, Gerald D.; Stout, Ralph L.; and Edson, Jay H. 5,590,319, Cl. 395-604.000.

Ing-Simmons, Nicholas. See—
Guttig, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moyse, Philip. 5,590,350, Cl. 395-800.000.

Inland Container Corporation. See—
McClure, Jack A. 5,588,585, Cl. 229-191.000.

Inman, Dana M. See—
Sackner, Marvin A.; and Inman, Dana M. 5,588,425, Cl. 128-632.000.

Innapharma, Inc. See—
Abajian, Henry B.; Noble, John F.; and Hlavka, Joseph J. 5,589,460, Cl. 514-17.000.

Innis, Michael A.; and Creasey, Abba A., to Chiron Corporation. Chimeric proteins. 5,589,359, Cl. 435-69.200.

Innovir Laboratories, Inc. See—
Shih, Andy; Bockman, Jeffrey M.; and George, Shaji T. 5,589,332, Cl. 435-6.000.

Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Yoshiaki, Ishida, Katsuki; Yamazaki, Osamu; Komura, Yukihiko; and Sukagawa, Tomoo, to Fujitsu Limited. Breather filter unit for magnetic disk drive. 5,590,001, Cl. 360-97.020.

Inotech. See—
Patat, Jean-Louis; Delmas, Olivier; and Schmitthausier, Roland. 5,589,462, Cl. 514-21.000.

Inoue, Masahiro. See—
Amemiya, Koji; and Inoue, Masahiro. 5,589,922, Cl. 399-315.000.

Inoue, Osamu. See—
Hiramoto, Masayoshi; Inoue, Osamu; Kugimiya, Koichi; and Iijima, Kenji. 5,589,221, Cl. 427-130.000.

Inoue, Soichi. See—
Wenzhi, Hu. 5,589,069, Cl. 210-635.000.

Inoue, Takahiro. See—
Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki. 5,588,555, Cl. 221-197.000.

Inoue, Toshihiro. See—
Maejima, Takamichi; Inoue, Toshihiro; Hasegawa, Hiroshi; and Nakano, Atsushi. 5,588,206, Cl. 29-845.000.

Inoue, Yuji. See—
Itoya, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yuji; Toyomura, Fumitaka; and Ohtsuka, Takashi. 5,589,006, Cl. 136-248.000.

Insight, Inc. See—
Fantone, Stephen D.; Gelardi, Anthony L.; and Gelardi, John A. 5,588,526, Cl. 206-308.100.

Insler, Steven R.; and Kraenzler, Erik J., to Cleveland Clinic Foundation, The. Bronchial blocker endotracheal apparatus. 5,588,424, Cl. 128-207.150.

Institut Francais du Pétrole. See—
Chauvin, Yves; and Olivier, Hélène. 5,589,601, Cl. 585-513.000.

Institut National de la Santé et de la Recherche Médicale. See—
Lanotte, Michel; and Berger, Roland. 5,589,345, Cl. 435-7.230.

Institut Pasteur. See—
Marchand, Claudine; Druilhe, Pierre; Pujalon-Mercereau, Odile; and Langley, Gordon. 5,589,343, Cl. 435-7.220.

Instrumentarium Corporation. See—
Sun, Jarmo; and Rantanen, Petri. 5,590,166, Cl. 378-37.000.

Instruments SA, Inc. See—
Chau, Chiu. 5,589,717, Cl. 356-328.000.

Integrated Device Technology, Inc. See—
Willenz, Avigdor; and Tzori, Yiftach. 5,590,310, Cl. 395-473.000.

Intel Corporation. See—
Allen, Michael J. 5,589,790, Cl. 327-333.000.
Astle, Brian. 5,589,829, Cl. 341-67.000.
Astle, Brian. 5,590,064, Cl. 364-715.020.
Bhat, Suresh A. 5,589,422, Cl. 437-228.000.
Eldridge, Robert A.; Unrein, Ed J.; Brown, David L.; and Noble, Scott L. 5,588,728, Cl. 312-332.100.
Heeb, Jay; Shenoy, Sunil; and Wong, Jimmy. 5,590,368, Cl. 395-800.000.
Huck, Kamla P.; Rodgers, Scott D.; and Glew, Andrew F. 5,590,297, Cl. 395-401.000.
Lippincott, Louis A.; and Craver, Thomas R. 5,590,254, Cl. 395-135.000.
Maloney, Michael; and Schlesinger, Robert. 5,590,128, Cl. 370-260.000.
Marisette, Suresh K. 5,590,312, Cl. 395-500.000.
Marisette, Suresh K. 5,590,342, Cl. 395-750.000.
Matter, Eugene P. 5,590,341, Cl. 395-750.000.
Mardone, Joseph M.; McTague, Michael J.; and David, Howard S. 5,590,289, Cl. 395-289.000.
Sharangpani, Harshvardhan P. 5,590,359, Cl. 395-800.000.

Intelligent Automation Systems. See—
Gordon, Steven J. 5,589,942, Cl. 356-376.000.

Intelmat Corporation. See—

Akagawa, Minoru. 5,588,791, Cl. 414-331.000.

Interflo Medical, Inc. See—
McKown, Russell C.; Quinn, Michael D.; and Yelderman, Mark L. 5,588,438, Cl. 128-692.000.

International Business Machines Corporation. See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Renter, Eric E.; Richardson, Robert R.; Roffe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A. 5,590,345, Cl. 395-800.000.

Baum, Richard I.; Brent, Glen A.; Gibson, Donald H.; and Lindquist, David B. 5,590,362, Cl. 395-800.000.

Boutaghou, Zine-Eddine. 5,590,004, Cl. 360-99.120.

Carson, Mark E.; Ranganathan, Mudumbai; and Cugini, Janet A. 5,590,266, Cl. 395-340.000.

Chencinski, Edward W.; Bixler, Jeffrey C.; and Christensen, Neal T. 5,590,309, Cl. 395-472.000.

Coskun, Nurcan; and Tate, Bruce A. 5,590,330, Cl. 395-704.000.

Cronin, John E. 5,589,707, Cl. 257-532.000.

Dieffenderfer, James N.; and Morehead, Bruce J. 5,590,372, Cl. 395-823.000.

Edwards, Geraldine E. 5,590,360, Cl. 395-800.000.

Keane, Patrick J.; and Richards, Justin J. C. 5,590,264, Cl. 395-340.000.

Kolor, Daniel J.; Gupte, Nitin B.; and Shah, Siddharth R. 5,590,071, Cl. 365-149.000.

Krounbi, Mohamad T.; Lee, Hin P. E.; and Seagle, David J. 5,588,199, Cl. 29-603.100.

Leung, Ting Y.; Pirahesh, Mir H.; Jou, Michelle M.; and Simmen, David E. 5,590,324, Cl. 395-605.000.

Lin, Eileen T.; and Wang, Yun. 5,590,321, Cl. 395-610.000.

Mitwalsky, Alexander; and Ryan, James G. 5,589,706, Cl. 257-529.000.

Morse, Gary J.; and Thompson, Stephen P. 5,590,260, Cl. 395-167.000.

Phillips, James E.; Blauer, Bartholomew; and Vassiliadis, Stamatios. 5,590,348, Cl. 395-564.000.

Reynolds, Robert A.; and Sheffield, David W. 5,590,313, Cl. 395-500.000.

Shaff, Mathew K. 5,590,006, Cl. 360-105.000.

Shih, Yifong. 5,590,308, Cl. 395-463.000.

Stein, Frank L.; and Verrier, Guy F. 5,589,856, Cl. 345-173.000.

Takahashi, Hiroyasu. 5,590,220, Cl. 382-203.000.

Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr. 5,590,373, Cl. 395-828.000.

Yu, Mantle M. 5,589,998, Cl. 360-78.140.

International Paper. See—
Sner, David E.; and Liquori, Katherine S. 5,588,587, Cl. 229-232.000.

International Paper Company. See—
Mills, Vincent; and Hughes, Tim P. 5,588,943, Cl. 493-58.000.

Wexler, Allan J. 5,589,324, Cl. 430-529.000.

Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehzekel; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, to National Semiconductor Corporation. Integrated CPU core and parallel, independently operating DSP module and time-critical core priority scheme. 5,590,357, Cl. 395-800.000.

Intrater, Gideon. See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehzekel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto. 5,590,357, Cl. 395-800.000.

Iomega Corporation. See—
Bracken, Allen T.; and Rich, Edward L. 5,590,002, Cl. 360-97.020.

IOT Integrierte Optik GmbH. See—
Wolf, Barbara; and Fabricius, Norbert. 5,590,226, Cl. 385-45.000.

Iowa State University Research Foundation, Inc. See—
Anderson, Iver E.; Lograsso, Barbara K.; and Terpstra, Robert L. 5,589,199, Cl. 425-10.000.

Ip, Kendy. See—
Sandler, Harold; and Ip, Kendy. 5,590,185, Cl. 379-163.000.

Iqbal, Mohammed. See—
Ali, Mahfuza B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G. 5,589,269, Cl. 428-411.100.

Iranmanesh, Ali; Pierce, John M.; and Bergemont, Albert M., to National Semiconductor Corporation. Method of making increased-density flash EPROM that utilizes a series of planarized, self-aligned, intermediate strips of conductive material to contact the drain regions. 5,589,412, Cl. 437-43.000.

Irie, Nobuhiko, to Mitsubishi Jukogyo Kabushiki Kaisha. Split mold apparatus for a tire vulcanizer. 5,589,200, Cl. 425-46.000.

Irie, Yoshiaki, to Canon Kabushiki Kaisha. Control for variable magnification in an imaging apparatus. 5,589,908, Cl. 396-51.000.

Irite, Naoko. See—
Yoshida, Kiyohide; Muramatsu, Gyo; Abe, Akira; and Irite, Naoko. 5,589,432, Cl. 502-325.000.

Irlbeck, Robert D.; Bates, Warren A.; Dumas, Robert; and Volz, Keith L., to Whitaker Corporation. The Right angle electrical connector. 5,588,846, Cl. 439-66.000.

Isaacson, David, and Cheney, Margaret, to Rensselaer Polytechnic Institute. Process for producing optimal current patterns for electrical impedance tomography. 5,588,429, Cl. 128-734.000.

Isadore-Barreca, Anthony J., to Magic Circle Media, Inc. Interactive video interface and method of creation thereof. 5,590,262, Cl. 395-806.000.

Isaji, Kaori. See—

Ito, Kengo, Isaji, Kaori, Fujiwara, Yoshio, Isogai, Mitsuhiro, and Hida, Masanobu. 5,589,435, Cl. 503-227.000.

Isegawa, Yuji. See—

Okuno, Yoshinobu, Isegawa, Yuji, Sasao, Fuyoko, and Ueda, Shigeharu. 5,589,174, Cl. 424-147.100.

Ishibashi, Ryoichi, and Sekine, Katsumi, to Fujitsu Limited. Congestion relieving system in a communication system. 5,590,132, Cl. 370-236.000.

Ishida, Hideharu, Kiso, Makoto, and Hasegawa, Akira, to Hasegawa, Akira, and Kanebo Ltd. Glycolipid derivatives acting as ligands for selectins. 5,589,465, Cl. 514-250.000.

Ishida, Katsuki. See—

Ito, Tsuneyori, Furukawa, Tsuyoshi, Jinbo, Masaki, Kaneko, Hisashi, Fukuzawa, Shimichi, Sugimoto, Masaharu, Nagasawa, Yoshiaki, Ishida, Katsuki, Yamazaki, Osamu, Komura, Yukihiko, and Saka-gawa, Tomoo. 5,590,001, Cl. 360-97.020.

Ishida, Takehisa, to Sony Corporation. Magnetic disk unit. 5,590,009, Cl. 360-135.000.

Ishida, Yasuhiko. See—

Kadowaki, Hidepro, Sugiyama, Hiroshi, Ishida, Yasuhiko, and Takamiya, Makoto. 5,589,858, Cl. 347-14.000.

Ishida, Yoshio, to Diamond Electric Mfg. Co., Ltd. Heat radiating apparatus. 5,588,483, Cl. 165-86.000.

Ishigaki, Takaya. See—

Fujishiro, Yoshikazu, Ishigaki, Takaya, and Harada, Hiraku. 5,590,016, Cl. 361-313.000.

Ishihara, Manabu, Rakuma, Tsuyoshi, Kanai, Hiroshi, Fudo, Takashi, and Watanabe, Masato, to Sanyo Electric Co., Ltd. Air conditioner. 5,588,589, Cl. 236-46.000.

Ishii, Mikio. See—

Chiba, Masao, and Ishii, Mikio. 5,589,960, Cl. 349-76.000.

Ishii, Takafumi. See—

Adachi, Takashi, Ishii, Takafumi, and Hidaka, Hidemasa. 5,588,254, Cl. 47-57.000.

Ishikawa, Hajime, Ogiwara, Masaki, Hasegawa, Ryosuke, and Yamamoto, Hideo, to Tigers Polymer Corporation. Apparatus for manufacturing boll-w resin products. 5,589,205, Cl. 425-526.000.

Ishikawa, Hideaki, and Shimoda, Atsunao, to Matsushita Electric Industrial Co., Ltd. Drive through wireless order taking system. 5,590,407, Cl. 455-66.000.

Ishikawa, Hiromi, to Office Ishikawa Co., Ltd. Multifunctional bag. 5,588,749, Cl. 383-4.000.

Ishikawa, Kazuhiro. See—

Hara, Shoji, Yanai, Takenori, and Ishikawa, Kazuhiro. 5,588,523, Cl. 198-781.000.

Ishikawa, Satoshi. See—

Kumi, Tohru, Suzuki, Nobuhiko, and Ishikawa, Satoshi. 5,588,854, Cl. 439-164.000.

Ishikawajima-Harima Heavy Industries Company Limited. See—

Leadbeater, Darren J., Kato, Heiji, and Fukase, Hisahiko. 5,588,479, Cl. 164-480.000.

Ishikawajima-Harima Jukogyo Kabushiki Kaisha. See—

Nakajima, Shinobu, and Maebou, Kunji. 5,590,152, Cl. 373-103.000.

Ogushi, Masaki, Takeuchi, Osamu, Yamamura, Ikuro, Iura, Toru, and Yoshida, Hironobu. 5,590,150, Cl. 373-9.000.

Ishimoto, Masaaki, and Toyota, Takehito, to Mitsubishi Denki Kabushiki Kaisha. Data transmission system for CATV systems with capability to interrupt the repeated transmission of character information blocks to send priority updates. 5,590,394, Cl. 455-6.100.

Ishuchi, Yukio. See—

Ito, Katsuhiko, Kobayashi, Hideo, Ishuchi, Yukio, and Shimada, Toshio. 5,588,406, Cl. 123-90.340.

Ishiwata, Yutaka, and Itoh, Yoshiyasu, to Kabushiki Kaisha Toshiba. Corrosion-resistant material for contact with high temperature molten metal and method for production thereof. 5,590,392, Cl. 428-546.000.

Ishiyama, Noritaka, and Kobayashi, Koutaro, to Mitsubishi Steel Mfg. Co., Ltd. Magneto-resistance-effect magnetic sensor of the temperature compensating type. 5,589,768, Cl. 324-207.210.

Ishizaki, Toshio. See—

Sato, Yuki, Ishizaki, Toshio, Sakaue, Tsuyoshi, Hashimoto, Koji, Yamada, Tohru, and Umano, Tomoki. 5,589,724, Cl. 310-348.000.

Isoke, Yoshio, Ito, Toshio, and Shibata, Fumio, to Takeda Chemical Industries, Ltd. Feed composition for ruminant animals and method of feeding ruminant animals with the same. 5,589,186, Cl. 424-438.000.

Isogai, Mitsuhiro. See—

Ito, Kengo, Isaji, Kaori, Fujiwara, Yoshio, Isogai, Mitsuhiro, and Hida, Masanobu. 5,589,435, Cl. 503-227.000.

Isogon Corporation. See—

Hartitz, Robert. 5,590,056, Cl. 364-550.000.

Issuu Motors Limited. See—

Yoshimura, Toshitumi, Kikuchi, Ryo, and Inuma, Shoji. 5,588,674, Cl. 280-732.000.

Itabashi, Masao. See—

Iwasaki, Yoh, Murakami, Yosuke, and Itabashi, Masao. 5,589,283, Cl. 428-694.000.

Italfarmaco S.p.A. See—

Sala, Alberto, Banfi, Aldo, Benedini, Francesca, and Cereda, Roberta. 5,589,490, Cl. 514-330.000.

ITC, Incorporated. See—

Camarota, Richard J. 5,588,908, Cl. 454-78.000.

Itezo, Toshiyuki, to Canon Kabushiki Kaisha. Facsimile apparatus. 5,589,948, Cl. 358-449.000.

Ito, Asami. See—

Goto, Toshio, Moriya, Koichi, Maurer, Fritz, Ito, Seishi, Wada, Katsuki, Ukawa, Kazuhiro, Watanabe, Ryo, Ito, Asami, and Minegishi, Natsuko. 5,589,439, Cl. 504-261.000.

Ito, Hiroshi, to Olympus Optical Co., Ltd. Apparatus for molding a glass optical element with a transporting supporting member. 5,588,980, Cl. 65-223.000.

Ito, Katsuhiko, Kobayashi, Hideo, Ishuchi, Yukio, and Shimada, Toshio, to Honda Giken Kogyo Kabushiki Kaisha. Structure for lubricating cam sliding surface in an internal combustion engine. 5,588,406, Cl. 123-90.340.

Ito, Kengo, Isaji, Kaori, Fujiwara, Yoshio, Isogai, Mitsuhiro, and Hida, Masanobu, to Sony Corporation. Sheet capable of releasing a thermal transfer image-receiving layer, a method for transferring a thermal transfer image-receiving layer from the sheet and a method for forming images. 5,589,435, Cl. 503-227.000.

Ito, Mamoru. See—

Uryu, Masaru, Tokura, Kunihiko, Chatani, Ikuro, Mizoguchi, Ikuro, and Ito, Mamoru. 5,590,212, Cl. 381-191.000.

Ito, Mitsuhiro. See—

Kano, Jiro, Omi, Ryuji, Horimouchi, Yuzo, and Ito, Mitsuhiro. 5,589,150, Cl. 423-338.000.

Ito, Seishi. See—

Goto, Toshio, Moriya, Koichi, Maurer, Fritz, Ito, Seishi, Wada, Katsuki, Ukawa, Kazuhiro, Watanabe, Ryo, Ito, Asami, and Minegishi, Natsuko. 5,589,439, Cl. 504-261.000.

Ito, Shinichi. See—

Tomofuji, Yoko, Nakase, Makoto, Sato, Takashi, Hazama, Hiroaki, Komano, Haruki, and Ito, Shinichi. 5,589,305, Cl. 430-5.000.

Ito, Tatsuya, Kawai, Masahito, and Yasukawa, Yoshinori, to Fujitsu Limited. Method of determining a space group. 5,590,053, Cl. 364-499.000.

Ito, Toshiro. See—

Isoke, Yoshio, Ito, Toshio, and Shibata, Fumio. 5,589,186, Cl. 424-438.000.

Itoh, Motoo. See—

Kobayashi, Masamichi, Itoh, Motoo, Matsubara, Yoji, and Shimizu, Kazuhiro. 5,589,055, Cl. 205-768.000.

Itoh, Seichi. See—

Satomi, Yasuhiko, Itoh, Seichi, Otsuka, Eiji, Yamaki, Jun, and Kato, Takashi. 5,588,197, Cl. 29-455.100.

Itoh, Shigeo. See—

Onokaka, Koji, Hiraga, Katsuya, Kobori, Yoichi, Sakurada, Hiroshi, Watanabe, Tetsu, and Itoh, Shigeo. 5,589,738, Cl. 315-169.100.

Itoh, Yoshiyasu. See—

Ishiwata, Yutaka, and Itoh, Yoshiyasu. 5,590,392, Cl. 428-546.000.

Ito, Satoshi, to NEC Corporation. Track jump controller for optical disk recording. 5,590,101, Cl. 364-32.000.

Ito, Kenichi, to Tachi S Co., Ltd. Lumbar support device for vehicle seat. 5,588,703, Cl. 297-284.400.

Itoyama, Shigenori, Fukae, Kimotsu, Mori, Masahiro, Inoue, Yuji, Toyomura, Tsumitaka, and Ohtsuka, Takashi, to Canon Kabushiki Kaisha. Solar battery module and passive solar system using same. 5,589,006, Cl. 136-248.000.

ITT Automotive Electrical Systems, Inc. See—

Neely, Michael J., and Savage, John R. 5,588,804, Cl. 416-223.000.

ITT Corporation. See—

Lester, Lester J., and Van Trump, Gary N. 5,588,858, Cl. 439-275.000.

Iura, Toru. See—

Ogushi, Masaki, Takeuchi, Osamu, Yamamura, Ikuro, Iura, Toru, and Yoshida, Hironobu. 5,590,150, Cl. 373-9.000.

Ivanov, Marian. See—

Flemming, Eckardt, Tilch, Werner, Schuster, Thomas, Ivanov, Marian, and Eirich, Paul. 5,589,650, Cl. 73-866.000.

Iwaki, Takashi. See—

Yamada, Yoko, Takiguchi, Takao, Iwaki, Takashi, Togano, Takeshi, Nakamura, Shinichi, and Nakazawa, Ikuro. 5,589,103, Cl. 252-299.610.

Iwakura, Tadayuki. See—

Tanabe, Masanori, Fukui, Hiroshi, Iwakura, Tadayuki, Nakamoto, Kazuhiro, Fuyama, Moriaki, Mitsuoka, Katsuya, Sano, Masaaki, Saito, Makoto, Aihara, Makoto, and Sudo, Shuji. 5,590,008, Cl. 360-126.000.

Iwamoto, Kazuya, Aotani, Noboru, Takada, Kazunori, and Kondo, Shigeo, to Matsushita Electric Industrial Co., Ltd. Fibrous solid electrolyte cell using the electrolyte and process for producing the electrolyte. 5,589,296, Cl. 429-191.000.

Iwamoto, Satoshi. See—

Watanabe, Kazuyuki, and Iwamoto, Satoshi. 5,589,547, Cl. 525-240.000.

Iwamura, Kenichi, to Canon Kabushiki Kaisha. Error correction apparatus. 5,590,138, Cl. 371-37.100.

Iwamura, Masahiro, Yamauchi, Tatsumi, Tanaka, Shigeya, and Mori, Kazutaka, to Hitachi, Ltd. Microprocessor having an effective BiCMOS extra multiple input complex logic circuit. 5,590,361, Cl. 395-800.000.

Iwasaki, Itsutoshi, Yamasaki, Tatsuo, and Sawada, Hideaki, to Taikorizan Co., Ltd. Monolithic refractories. 5,589,426, Cl. 501-32.000.

Iwasaki, Kiyoshi, to NEC Corporation. YC separation and still picture reproducing circuit. 5,589,888, Cl. 348-669.000.

Iwasaki, Shinichi, Sugiyama, Masanori, Umemura, Chiaki, Oikawa, Akemi, and Takahashi, Hisayoshi, to Aisin Seiki Kabushiki Kaisha. Controller for switched reluctance motor. 5,589,752, Cl. 318-701.000.

Iwasaki, Yoh, Murakami, Yosuke, and Itabashi, Masao, to Sony Corporation. Soft magnetic thin film. 5,589,283, Cl. 428-694.000.

Iwasawa, Junichi. See—

Sasaki, Yu, Iwasawa, Junichi, and Yamada, Masahiro. 5,588,732, Cl. 362-10.000.

Iwata, Tomoo, to Fuji Electric Co., Ltd. Solid electrolyte fuel cell. 5,589,286, Cl. 429-34.000.

Iwinski, Dean J. See—

Becker, Thomas P., Crass, Matthew M., Putney, Gordon A., Niesen, Randy J., and Iwinski, Dean J. 5,589,644, Cl. 73-862.230.

Izui, Yohji. See—

Akimoto, Yoshiaki, Tanaka, Hideo, Ogi, Hiromi, Izui, Yoshio, Taoka, Hisao, and Sakaguchi, Toshiaki. 5,590,243, Cl. 395-23.000.

Izumi Corporation. See—

Numata, Shigeo. 5,588,666, Cl. 280-728.200.

J.M. Voith GmbH. See—

Fork, Werner. 5,588,798, Cl. 415-111.000.

Kustermann, Martin, Gottwald, Ingo, and Ueberschar, Manfred. 5,589,659, Cl. 118-413.000.

J. Morita Manufacturing Corporation. See—

Arai, Yoshinori. 5,590,167, Cl. 378-38.000.

Jackson, John R. See—

Moran, Stephen W., Jackson, John R., Gallivan, Timothy J., and Loftfield, Richard E. 5,589,053, Cl. 205-698.000.

Jackson, Marianna. See—

Hochlewska, Jill E., Jackson, Marianna, Kadani, Sunil K., Karwowski, James P., and McAlpine, James B. 5,589,485, Cl. 514-315.000.

Jacobs, Merrit N. See—

Graham, Gary A., Jacobs, Merrit N., Marvin, Russell H., Shaw, James D., and VanBrunt, Nicholas. 5,588,946, Cl. 494-11.000.

Jacobs, Robert L. See—

Shenai, Ashokkumar B., Jacobs, Robert L., Miller, Scott C., Ohnmacht, Cyrus J., Jr., and Veale, Chris A. 5,589,489, Cl. 514-323.000.

Jacobson, Stephen C., Potter, Dwight, and Smith, Fraser, to Sarcos, Inc. Robotic grasping apparatus. 5,588,688, Cl. 294-106.000.

Jacobson, Esther. See—

Spector, Yechiel, Jacobson, Esther, Naishit, Vida, Vittenberg, Michael, and Beinert, Zohar. 5,588,493, Cl. 169-46.000.

Jacquin, Thierry. See—

Duboureaux, Jean-Paul, and Jacquin, Thierry. 5,590,335, Cl. 393-704.000.

Jäger, Helmut F., Peschina, Jürgen, and Dietrich, Bernard, to Felsomat GmbH & Co KG. Handling apparatus. 5,588,795, Cl. 414-733.000.

Jager, Karl-Friedrich. See—

Lisa, Rudolph E., Kilbride, Terence K., and Jager, Karl-Friedrich. 5,589,438, Cl. 504-236.000.

Jakobovits, Aya. See—

Seidman, Jonathan G., and Jakobovits, Aya. 5,589,369, Cl. 435-172.300.

Jameel, Hasan. See—

Chang, Hou-Min, Jameel, Hasan, Song, Junfu, Pan, Dingru, Amin, Bijan, Webster, John R., and Evans, Bruce A. 5,589,032, Cl. 162-76.000.

Jamson, Bradford A., McDonnell, James M., and Korngold, Robert, to Thomas Jefferson University. Compounds that inhibit T cell proliferation and methods for using the same. 5,589,458, Cl. 514-13.000.

Jamshidi, Mohammad. See—

Asgharzadeh, Ali, and Jamshidi, Mohammad. 5,590,246, Cl. 395-109.000.

Jan, William Y. See—

Cunningham, John E., Goossen, Keith W., Jan, William Y., Pathak, Rajiv N., and Walker, James A. 5,589,404, Cl. 437-5.000.

JanakiRam, Ram D. See—

Charles, Bruce D., Hassan, Ahmed A., Tadghighli, Hormoz, JanakiRam, Ram D., and Sankar, Lakshmi N. 5,588,800, Cl. 416-24.000.

Jang, Hyun-Soon. See—

Park, Churso, Jang, Hyun-Soon, Kim, Chul-Soo, Kim, Myung-Ho, Lee, Seung-Hun, Lee, Si-Yeol, Lee, Ho-Cheol, Kim, Tae-Jin, and Choi, Yun-Ho. 5,590,086, Cl. 365-230.030.

Jannetta, Peter J. Method and apparatus for treatment of neurogenic diabetes mellitus, and other conditions. 5,589,183, Cl. 424-423.000.

Janse Van Rensburg, Richard W., and Keep, Peter R., to Videojet Systems International, Inc. Ink jet droplet generator. 5,589,863, Cl. 347-75.000.

Janssen, John J. See—

Alberth, William P., Jr., Janssen, John J., and Klomdsdorf, Armin. 5,589,796, Cl. 330-133.000.

Janssen Pharmaceutica N.V. See—

Venet, Marc G., Guillemont, Jérôme E. G., Vernier, Daniel F. J., and Odds, Frank C. 5,589,484, Cl. 514-314.000.

Janssens, Wilhelmus. See—

Delieuw, Geert, Janssens, Wilhelmus, Uytendhoeven, Herman, Horsten, Bart, Dewaenkele, Jean-Marie, and Van den Bogaert, Jan. 5,589,317, Cl. 430-203.000.

Japan Aviation Electronics Industry, Limited. See—

Sano, Toshifumi, Yamada, Masahiro, Umezawa, Yoshiaki, Okada, Yoshikatsu, and Natori, Akira. 5,589,711, Cl. 257-718.000.

Japan Fronties Co., Ltd. See—

Koiso, Yasuhiko, Matsumoto, Yoshiaki, Fujisawa, Masayuki, and Nagatsu, Isao. 5,588,304, Cl. 62-340.000.

Otsuka, Kenji, Fukuda, Hideki, and Arakawa, Satoshi. 5,589,148, Cl. 423-240.000.

Japan Steels International Inc. See—

Yonahara, Yoshihiro. 5,588,500, Cl. 182-141.000.

Jarman, Michael. See—

Edwards, Karen J., Jarman, Michael, Laughton, Charles A., Neidle, Stephen, and Hardcastle, Ian R. 5,589,500, Cl. 514-428.000.

Järvenkylä, Jyrk, Scharwächter, Dieter, Johansson, Åke, and Kristensson, Ronny, to Uponor Innovation AB. Method and apparatus for forming ribs with sidewall projections in a plastic pipe, and a plastic pipe. 5,589,127, Cl. 264-280.000.

Jason, Inc. See—

Rice, Patrick E. 5,589,067, Cl. 210-493.500.

Jax, Peter, and Ruthrof, Klaus, to Siemens Aktiengesellschaft. Flexible sensor tube and method for determining a concentration curve of a medium along a path with the flexible sensor tube. 5,589,647, Cl. 73-863.230.

Jay, John C., and Burns, Clay A. Convertible chair with armrests which converts to a backpack. 5,588,696, Cl. 297-129.000.

Jayasinha, Madhigubba G. See—

Hogan, Steven J., Feltz, Kristi T., Murdock, Douglas R., Goodman, Todd A., Vercande, David J., Tangeman, Michael R., Busch, Eric M., Kripakaran, Raghavan, Jayasinha, Madhigubba G., Smith, Keith E., Austin, Mark A., and Berry, Dana B. 5,590,181, Cl. 379-114.000.

Jayet, Gérard. See—

Sabater, Jacques, Tourtollot, Guy E. P., and Jayet, Gérard. 5,589,941, Cl. 356-376.000.

Jeansson, Stig. See—

Vahlne, Anders, Svennerholm, Bo, Rymo, Lars, Jeansson, Stig, and Horal, Peter. 5,589,175, Cl. 424-208.100.

Jedrzeczak, Edward A. See—

Viano, David C., Jedrzeczak, Edward A., and Smrcka, Joseph G. 5,589,651, Cl. 73-866.400.

Jegham, Samir, Defosse, Gérard, Purcell, Thomas A., and Even, Luc, to Synthelabo. Imidazol-4-ylpiperidine derivatives, their preparation and their application in therapeutics. 5,589,476, Cl. 514-230.200.

Jeng, Shin-Puu, to Texas Instruments, Incorporated. TiSi₂/TiN clad interconnect technology. 5,589,417, Cl. 437-190.000.

Jennebach, Markus, and Birkhan, Joao A., to Leslie Technologies, Inc., and Gruntec Ltd. Method and system for burning waste materials. 5,588,381, Cl. 110-345.000.

Jennings, Philip A. See—

Hascloft, James P., Gerlach, Wayne L., Jennings, Philip A., and Cameron, Fiona H. 5,589,580, Cl. 536-23.200.

Jennings, William C. See—

Sanford, James R. M., Frank, Patrick M., Golias, Joseph H., and Jennings, William C. 5,589,063, Cl. 210-198.200.

Jensen, Michael L., Summers, George D., Jr., and Baum, Thomas M., to Ratschem Corporation. Telecommunications terminal block. 5,588,869, Cl. 439-417.000.

Jen Wu, Kuang, and Odum, Robert W. Matrix enhanced SIMS. 5,589,685, Cl. 250-282.000.

Jepsen, Hardy P., to Danfoss A/S. Hydraulic axial piston machine with an inclined plate. 5,588,347, Cl. 92-12.200.

Jepson, Ian. See—

Bridges, Ian G., Bright, Simon W. J., Greenland, Andrew J., Holt, David C., Jepson, Ian, and Schuch, Wolfgang W. 5,589,614, Cl. 800-205.000.

Jermyn, Richard A., Jr., to United States of America, Navy. Swaged cable swivel hook assembly and swivel hook therefor. 5,588,188, Cl. 24-598.700.

Jernigan, Walter W. See—

Deng, Zhi D., Sigler, Gerald F., Surridge, Nigel A., Wilsey, Christopher D., McEnroe, Robert J., Jernigan, Walter W., and Muddiman, Rebecca W. 5,589,326, Cl. 435-4.000.

Jeschke, Peter. See—

Menneke, Norbert, Harder, Achim, and Jeschke, Peter. 5,589,503, Cl. 514-450.000.

Jeske, Frank. See—

Rappenecker, Hermann, and Jeske, Frank. 5,590,235, Cl. 388-803.000.

Jeunemaitre, Xavier. See—

Lalouel, Jean-Marc, Jeunemaitre, Xavier, Lifton, Richard P., Soubrier, Florent, Kotelevtsev, Youri, and Corvol, Pierre. 5,589,684, Cl. 536-24.310.

Ji, Jeong B., and Um, Gregory, to Daewoo Electronics Co. Ltd., and Aura Systems, Inc. Thin film actuated mirror array. 5,589,084, Cl. 216-24.000.

Jilka, Joseph M., and Turner, Nilgun E., to Monsanto Company. Virus resistant plants transformed with a PVY protease gene. 5,589,612, Cl. 800-205.000.

Jimbo, Yumiko. See—

Ono, Mitsunori, Wada, Yumiko, Wu, Yaming, Kitaguchi, Hiroshi, Jinbo, Yumiko, Nemori, Ryoichi, Gillies, Stephen, and Lu, Kin-Ming. 5,589,510, Cl. 514-590.000.

Jin, Ilwon, Lloyd, David J., Timsit, Roland S., and Lees, Eric R., to Alcan International Limited. Control of sticking in twin roll casting. 5,588,478, Cl. 164-480.000.

- Jin, Sungho; Kochanski, Gregory P.; and Zhu, Wei, to Lucent Technologies Inc. Field emission device and method for making same. 5,588,894, Cl. 445-24.000.
- Jinbo, Masaki: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiko; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Jinbo, Takeshi: See—
Tepman, Avi; Jinbo, Takeshi; Takahama, Hiroyuki, and Saito, Akihiko, 5,589,224, Cl. 427-248.100.
- Johanputra, Panna: See—
Archer, Colin M.; Dilworth, Jonathan R.; Johanputra, Panna; Latham, Ian A.; and Thompson, Russell M., 5,589,576, Cl. 534-14.000.
- Johal, Gurmukh S.: See—
Briggs, Steven P.; and Johal, Gurmukh S., 5,589,611, Cl. 800-205.000.
- Johansson, Åke: See—
Järvenkylä, Jyri; Scharwächter, Dieter; Johansson, Åke; and Kristens-son, Ronny, 5,589,127, Cl. 264-280.000.
- John Daniel Containers (Proprietary) Limited: See—
Hall, Daniel J., 5,588,711, Cl. 298-18.000.
- John, Robin C.: See—
Van Beersel, Jozef; and John, Robin C., 5,589,019, Cl. 156-184.000.
- Johnakin, E. Kimble, III, to Just Selling, Inc. Bird perch apparatus. 5,588,397, Cl. 119-468.000.
- Johnson & Johnson Clinical Diagnostics, Inc.: See—
Contestabile, Paul B.; and Snyder, Brian A., 5,589,344, Cl. 435-7.900.
- Graham, Gary A.; Jacobs, Merrit N.; Marvin, Russell H.; Shaw, James D.; and VanBrunt, Nicholas, 5,588,946, Cl. 494-11.000.
- Johnson, Bartley C.; and Belk, John H., to McDonnell Douglas Corporation. Strain and fabry-perot etalon measurement system and method. 5,589,641, Cl. 73-800.000.
- Johnson, Christopher S. Capillary wick hydroponic process. 5,588,255, Cl. 47-58.000.
- Johnson, Donald A.: See—
Shim, Sang-Hea; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo; and Lu, Frank F., 5,589,106, Cl. 252-387.000.
- Johnson, Drew S.: See—
Hess, Randall L.; and Johnson, Drew S., 5,590,315, Cl. 395-500.000.
- Johnson, George P., Jr., to North Houston Machine, Inc. High strength, quick connect/disconnect coupling. 5,588,772, Cl. 403-355.000.
- Johnson, Glenn W., Jr.; McVicker, Henry J.; and Hargrave, David C., to Aircast, Inc. Method and apparatus for providing therapeutic compression for reducing risk of DVT. 5,588,955, Cl. 601-152.000.
- Johnson, John L.: See—
Drohan, William N.; Wilkins, Tracy D.; Velander, William H.; and Johnson, John L., 5,589,604, Cl. 800-2.000.
- Johnson, Kelly B., to Morton International, Inc. Method for combined gas fill and proof test of pressure vessels. 5,588,472, Cl. 141-83.000.
- Johnson, Matthew R.: See—
Kostiuk, Larry W.; and Johnson, Matthew R., 5,588,825, Cl. 431-349.000.
- Johnson, Matthew Electronics, Inc.: See—
Dunlop, John A.; Yuan, Jun; Kardokus, Janine K.; and Emigh, Roger A., 5,590,389, Cl. 419-67.000.
- Johnson, Robert D.: See—
Mainster, Martin A.; Crossman, Janet L.; and Johnson, Robert D., 5,589,896, Cl. 351-219.000.
- Johnson, Timothy C. Disposable rolled rim cup and lid closure. 5,588,552, Cl. 220-712.000.
- Johnson, William A.: See—
Resnick, Douglas J.; Johnson, William A.; Cummings, Kevin D.; and Chen, Hector T. H., 5,590,239, Cl. 392-418.000.
- Johnston, Mark F.: See—
Ehlers, Wayne L.; Eichholz, Kenneth L., Jr.; and Johnston, Mark F., 5,588,202, Cl. 29-606.000.
- Jonekheere, Luc: See—
Morlion, Danny; Jonekheere, Luc; and van Koetsem, Jan P. K., 5,588,851, Cl. 439-108.000.
- Joneikis, Albert E.: See—
Holmes, William K.; Joneikis, Albert E.; and Wong, Kwok W., 5,588,418, Cl. 125-13.010.
- Jones, Allan S.: See—
White, Alan W.; Percy, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., 5,589,566, Cl. 528-286.000.
- Jones, Andrew J. S.: See—
Cleland, Jeffrey L.; and Jones, Andrew J. S., 5,589,167, Cl. 424-85.700.
- Jones, Anthony M.; Dewar, Kevin D.; and Sotharan, Martin W., to Discovision Associates. Method and arrangement for transformation of signals from a frequency to a time domain. 5,590,067, Cl. 364-725.000.
- Jones, Darrell D., to Boeing Company, The. Feeding fasteners to a workpiece. 5,588,554, Cl. 221-88.000.
- Jones, David, to Sumitomo Rubber Industries, Ltd. Method and device for detecting a deflated tire on a vehicle. 5,589,816, Cl. 340-444.000.
- Jones, Dee L.: See—
Pickett, J. Paul; Jones, Dee L.; and Christensen, Jay D., 5,588,494, Cl. 171-124.000.
- Jones, Jerry L. Mole gassing device. 5,588,252, Cl. 43-124.000.
- Jones, Nelson E.: See—
Blackmon, James B.; Druhka, Robert E.; Jones, Nelson E.; Gerneck, R. Andrew; and Hand, Michael L., 5,589,758, Cl. 322-100.000.
- Jones, Philip J., to Raychem Corporation. Flexible electrode-bearing article. 5,589,253, Cl. 428-220.000.
- Jones, Rickey A. Personal meter timing device. 5,589,812, Cl. 340-309.150.
- Jones, Simon; and Tang, Jin, to Genetics Institute, Inc. Calcium independent cytosolic phospholipase A₂/B enzymes. 5,589,170, Cl. 424-94.600.
- Jones, Steven. Locking device for selectively preventing access to the valve handles of a domestic water tap. 5,588,316, Cl. 70-178.000.
- Josefsson, Leif E. B.; and Monte, Robert F., to ABB Paint Finishing, Inc. Combined radiant and convection heating oven. 5,588,830, Cl. 432-147.000.
- Jos. L. Meyer Werft GmbH & Co.: See—
Sterflinger, Fritz; and Möhlenkamp, Hans, 5,588,268, Cl. 52-236.700.
- Joslin Diabetes Center, Inc.: See—
Kahn, C. Ronald; and Reynet, Christine, 5,589,374, Cl. 435-240.100.
- Jost, Thomas: See—
Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000.
- Jou, Michelle M.: See—
Leung, Ting Y.; Pirabesh, Mir H.; Jou, Michelle M.; and Simmen, David E., 5,590,324, Cl. 395-605.000.
- Jouck, Walter: See—
Ott, Günther; Reuter, Hardy; Jouck, Walter; Pontek, Susanne; Heimann, Ulrich; and Gilbert, John, 5,589,049, Cl. 204-504.000.
- Ju, Junn-Ming: See—
Lin, Lie-Der; and Ju, Junn-Ming, 5,589,850, Cl. 345-132.000.
- Juang, Bing-Hwang; and Rahim, Mazin G., to Lucent Technologies Inc. Signal bias removal for robust telephone speech recognition. 5,590,242, Cl. 395-2.540.
- Juchymenko, Victor Y.; Howard, J. Richard; Laczynski, Andrew J.; and Angus, James S., to Roberts Systems, Inc. Light processing apparatus for creating visual effects. 5,588,235, Cl. 40-547.000.
- Julius Blum Gesellschaft m.b.H.: See—
Röck, Erich; and Huber, Edgar, 5,588,730, Cl. 312-348.200.
- Jung, Ulrich: See—
Herold, Manfred; Hartung, Georg; Schutz, Hans-Willy; and Jung, Ulrich, 5,588,365, Cl. 101-350.000.
- Jungnitz, Winfried: See—
Alber, Friedrich; Dedelmahr, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605.000.
- Juratovac, Diana W.: See—
Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., 5,588,539, Cl. 211-41.000.
- Jurkovic, Raimund: See—
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruff, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Just Selling, Inc.: See—
Johnakin, E. Kimble, III, 5,588,397, Cl. 119-468.000.
- K. J. Manufacturing Co.: See—
Bedi, Ram D.; and van der Griendt, Adrianus J., 5,588,502, Cl. 184-1.500.
- K. R. Precision Public Company Limited: See—
Schudel, Dale F., 5,588,200, Cl. 29-603.010.
- Kaak, Hartmut; and Neuendorf, Andreas; to Zinser Textilmaschinen GmbH. Control system for a production machine, especially a ring-spinning machine. 5,590,045, Cl. 364-470.100.
- Kahatepe, Mete, to Motorola, Inc. Efficient distributed queueing random access method for the medium access control layer in networks with broadcast channels. 5,590,131, Cl. 370-461.000.
- Kabel Rheydt AG: See—
Lysson, Hans-Jürgen; Broden, Reiner; and Leppert, Hans-Detlef, 5,588,997, Cl. 118-405.000.
- Kabeshita, Akira: See—
Matsui, Hisako; and Kabeshita, Akira, 5,589,029, Cl. 156-344.000.
- Kabushiki Kaisha Cosmo Area: See—
Mitomi, Masako; and Hoshino, Ryo, 5,588,569, Cl. 224-153.000.
- Kabushiki Kaisha Kenwood: See—
Matsuo, Shinta; and Sakamoto, Yoshio, 5,590,210, Cl. 381-199.000.
- Kabushiki Kaisha Komatsu Seisakusho: See—
Toyama, Makoto; and Akai, Yoshikazu, 5,588,515, Cl. 192-4.00C.
- Kabushiki Kaisha Kosmek: See—
Yonezawa, Keitaro, 5,588,642, Cl. 209-244.000.
- Kabushiki Kaisha Plex: See—
Ooba, Hideki, 5,588,898, Cl. 446-321.000.
- Kabushiki Kaisha Riken: See—
Yoshida, Kiyohide; Muramatsu, Gyo; Abe, Akira; and Irie, Naoko, 5,589,432, Cl. 502-325.000.
- Kabushiki Kaisha Saginomiya Seisakusho: See—
Sakakibara, Hisayoshi; Okada, Tomoo; and Ikeda, Tadaaki, 5,588,590, Cl. 236-92.00B.
- Kabushiki Kaisha Sankyo Seiki Seisakusho: See—
Kinoshita, Shinji; and Ide, Mitsuru, 5,588,753, Cl. 384-488.000.
- Kabushiki Kaisha Tokai-Rika-Denki Seisakusho: See—
Imai, Keisuke; Kato, Keiichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, 5,588,608, Cl. 242-374.000.
- Kabushiki Kaisha Toshiba: See—
Araki, Hitoshi, 5,589,699, Cl. 257-316.000.
- Doi, Miwako; Fukui, Mika; Nishida, Ikiko; and Kato, Nobuko, 5,590,268, Cl. 395-326.000.

- Hasagawa, Takehiro; and Oowaki, Yukihito, 5,590,080, Cl. 365-201.000.
- Honda, Masami; and Kawabata, Kazuaki, 5,590,024, Cl. 361-684.000.
- Ide, Nobuhiro; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, 5,590,365, Cl. 395-394.000.
- Ishiwata, Yutaka; and Itoh, Yoshiyasu, 5,590,392, Cl. 428-546.000.
- Kato, Tsuguo; and Thai, Cao M., 5,589,129, Cl. 264-437.000.
- Manabe, Toshihiko, 5,590,326, Cl. 395-477.000.
- Marui, Kuniyoshi; and Sato, Goichi, 5,590,414, Cl. 455-89.000.
- Miyano, Shinji; Sato, Katsuhiko; and Yabe, Tomoaki, 5,590,084, Cl. 365-230.010.
- Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagiya, Satoshi; and Baba, Yoshiro, 5,589,421, Cl. 437-225.000.
- Tanaka, Koichi, 5,590,302, Cl. 395-416.000.
- Tomofuji, Yoko; Nakase, Makoto; Sato, Takashi; Hazama, Hiroaki; Komano, Haruki; and Ito, Shinichi, 5,589,305, Cl. 430-5.000.
- Watanabe, Hiroshi, 5,590,282, Cl. 395-185.080.
- Yamada, Kunio; and Sawada, Michio, 5,590,380, Cl. 395-868.000.
- Yasuda, Akira, 5,590,155, Cl. 375-261.000.
- Kabushiki Kaisha Toyota Jidoshokki Seisakusho: See—
Kimura, Kazuya; Kayukawa, Hiroaki; Takeichi, Toru; and Hiramatsu, Osamu, 5,588,807, Cl. 417-222.200.
- Shiraki, Masao; Suzuki, Fujio; and Yoshida, Kazunori, 5,588,470, Cl. 139-435.500.
- Kabushiki Kaisha Toyota Chuo Kenkyusho: See—
Asano, Katsuhiko; Sugai, Masaru; Yamaguchi, Hiroyuki; and Umeno, Takaji, 5,588,721, Cl. 303-163.000.
- Noda, Koji; Fujikawa, Hisayoshi; Yamashita, Katsuji; and Taga, Yasunori, 5,589,733, Cl. 313-509.000.
- Shiraki, Masao; Suzuki, Fujio; and Yoshida, Kazunori, 5,588,470, Cl. 139-435.500.
- Kabushiki Kaisha Ohara: See—
Miyazaki, Mutsumi; and Yoshida, Toshiaki, 5,588,979, Cl. 65-164.000.
- Kachi, Mitsuyasu: See—
Kazama, Tsutomu; and Kachi, Mitsuyasu, 5,589,748, Cl. 318-560.000.
- Kadah, Andrew S.; and Morrow, Benjamin V., to Kadah, Andrew S. Rate effect motor start circuit. 5,589,753, Cl. 318-785.000.
- Kadam, Sunil K.: See—
Hochlowski, Jill E.; Jackson, Marianna; Kadam, Sunil K.; Karowski, James P.; and McAlpine, James B., 5,589,485, Cl. 514-315.000.
- Kadowaki, Hidejiro; Sugiyama, Hiroshi; Ishida, Yasuhiko; and Takamiya, Makoto, to Canon Kabushiki Kaisha. Information recording apparatus. 5,589,858, Cl. 347-14.000.
- Kaftanov, V. S.; Suvorov, A. L.; and Sheshin, E. P., to Kentucky Research and Investment Company Limited. Field emission cathode and methods in the production thereof. 5,588,893, Cl. 445-6.000.
- Kageyama, Mitsuhiro; to Canon Kabushiki Kaisha. Data communication apparatus including volatile and non-volatile storage. 5,590,190, Cl. 379-356.000.
- Kageyama, Shigeki: See—
Motoda, Takashi; Karakida, Shoichi; Kaneno, Nobuaki; and Kageyama, Shigeki, 5,589,110, Cl. 261-61.000.
- Kagotani, Tsuneo: See—
Koga, Keiji; Arai, Hitoshi; Kagotani, Tsuneo; and Miyaki, Yousuke, 5,589,297, Cl. 429-212.000.
- Kah, Carl L. C., Jr. Adjustable arc spray nozzle. 5,588,594, Cl. 239-107.000.
- Kahn, C. Ronald; and Reynet, Christine, to Joslin Diabetes Center, Inc. Diabetogene rad. a type II diabetes specific gene. 5,589,374, Cl. 435-240.100.
- Kai, Takashi: See—
Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34.000.
- Kaigawa, Masato: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Kaise, Satoshi: See—
Kobayashi, Nobuaki; Kaise, Satoshi; and Kano, Hideki, 5,589,645, Cl. 73-862.335.
- Kaite, Osamu; Okada, Tatsuya; and Kokuga, Toshiharu, to Sanyo Electric Co., Ltd. Method and apparatus for charging a secondary battery. 5,589,755, Cl. 320-21.000.
- Kakiuchi, Daisuke; Ogawa, Yasumichi; Yasumatsu, Hifumi; and Shiraga, Kazutaka, to Marugo Rubber Industries, Ltd. Hose for automotive fuel piping. 5,588,469, Cl. 138-137.000.
- Kaku, Toshimitsu: See—
Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116.000.
- Kalina, Alexander I.; and Mirolli, Mark D., to Exergy, Inc. Supplying heat to an externally fired power system. 5,588,298, Cl. 60-676.000.
- Kaliszewski, Mary Sue: See—
Scott, Curtis E.; Kaliszewski, Mary Sue; and Levinson, Lionel M., 5,588,992, Cl. 117-2.000.
- Kallai-Sohonyai, Anna: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizser, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Kallenbach, Ralph M., to Sargent & Lundy. Seismic pipe restraint and method for using the same. 5,588,511, Cl. 188-374.000.
- Kalnitsky, Alexander, to SGS-Thomson Microelectronics, Inc. Method of forming a polysilicon buried contact. 5,589,418, Cl. 437-193.000.
- Kalnitsky, Alexander, to SGS-Thomson Microelectronics, Inc. Radiation hard integrated circuits with implanted silicon in gate oxide layer, field oxide region, and interlevel dielectric layer. 5,589,708, Cl. 257-646.000.
- Kalyan, Jagdish C.: See—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474.130.
- Kametani, Masatsugu; and Umekita, Kazuhiro, to Hitachi, Ltd. Circuit board capable of efficiently conducting heat through an inside thereof using thermal lands surrounding through-hole connections. 5,590,030, Cl. 361-794.000.
- Kamihayashi, Kaname: See—
Sato, Yasushi; and Kamibayashi, Kaname, 5,589,952, Cl. 358-487.000.
- Kamijo, Atsushi, to NEC Corporation. Magnetoresistive thin-film and device. 5,589,278, Cl. 428-611.000.
- Kamijo, Yasuhiro: See—
Atsumi, Toru; Kamijo, Yasuhiro; Furukawa, Yoshiki; and Matumura, Naoki, 5,589,678, Cl. 235-472.000.
- Kamiko, Hideo: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hiroyuki; Fukaya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.
- Kamis, Kimberly: See—
Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401.000.
- Kamiya, Hiroshi, to NEC Corporation. Bus driver circuit for high-speed data transmission. 5,589,789, Cl. 327-278.000.
- Kamps, Rolf: See—
Ströter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegemund, Rainer, 5,588,326, Cl. 74-50.000.
- Kamura, Hitoshi: See—
Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416.000.
- Kanai, Hiroshi: See—
Ishihara, Manabu; Rakuma, Tsuyoshi; Kanai, Hiroshi; Fudo, Takashi; and Watanabe, Masato, 5,588,589, Cl. 236-46.00R.
- Kanai, Masahiro: See—
Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249.000.
- Kanai, Moriyasu; and Matsuo, Hirofumi, to Asahi Kogaku Kogyo Kabushiki Kaisha. Telescope with rear converter and rear conversion lens and telescope. 5,589,976, Cl. 359-362.000.
- Kanamori, Iwao: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki, to TOA Medical Electronics Co., Ltd. Synthetic apparatus for inspection of blood. 5,588,555, Cl. 221-197.000.
- Kanamori, Toshinori: See—
Morishita, Hideaki; Kanamori, Toshinori; and Nobuhara, Masahiro, 5,589,360, Cl. 435-69.100.
- Kanan, Paul G.; Smith, Richard H.; and Rudnick, Ellen, to BioQuant, Inc. Method of monitoring markers of bone metabolism. 5,589,346, Cl. 435-7.920.
- Kanda, Atsushi: See—
Kawaguchi, Kenzo; Takemura, Tetsuya; Matsubara, Hideki; Takagi, Sinya; and Kanda, Atsushi, 5,589,429, Cl. 501-96.000.
- Kanebo Ltd.: See—
Ishida, Hideharu; Kiso, Makoto; and Hasegawa, Akira, 5,589,465, Cl. 514-25.000.
- Kanejiwa, Toshiyuki: See—
Kurahashi, Akira; Ando, Hiroshi; Kanejiwa, Toshiyuki; and Hoashi, Yoshiaki, 5,589,930, Cl. 356-5.010.
- Kaneko, Hisashi: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiko; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Kaneko, Kunikiyo: See—
Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikiyo; and Koeda, Takashi, 5,588,950, Cl. 600-178.000.
- Kaneko, Seiji: See—

- Kondo, Nobukazu; Kaneko, Seiji; Gemma, Hideaki; Okada, Tetsuhiko; Komori, Kazuhiko; and Okazawa, Koichi, 5,590,290, Cl. 395-298,000.
- Kaneko, Tadashi: See—
Moriyama, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15,000.
- Kanemitsu, Shinji: See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279,000.
- Kaneno, Nobuaki: See—
Motoda, Takashi; Karakida, Shoichi; Kaneno, Nobuaki; and Kageyama, Shigeki, 5,589,110, Cl. 261-61,000.
- Kang, Sang-Won: See—
Ahn, Kun-Young; Park, Kyung-Ho; Nam, Kee-Soo; and Kang, Sang-Won, 5,589,083, Cl. 216-24,000.
- Kano, Haruyuki: See—
Kojima, Shoichi; Minagawa, Kazuhiro; Kano, Haruyuki; Miyazaki, Tadaaki; and Wada, Hiroaki, 5,589,116, Cl. 264-65,000.
- Kano, Hideki: See—
Kobayashi, Nobuaki; Kaise, Satoshi; and Kano, Hideki, 5,589,645, Cl. 73-862,335.
- Kano, Jiro; Orii, Ryuji; Horinouchi, Yuzo; and Ito, Mutsuhiro, to Fuji-Davison Chemical Ltd. Method for preparing spherical silica gel particles, 5,589,150, Cl. 423-338,000.
- Kano, Masami, to Mitsuba Electric Manufacturing Co., Ltd. Direct coupler device, 5,588,879, Cl. 439-686,000.
- Kansei Corporation: See—
Chiba, Masao; and Ishii, Mikio, 5,589,960, Cl. 349-76,000.
Suzuki, Shigemichi; and Endo, Sadahisa, 5,588,260, Cl. 49-502,000.
- Kanzaki Kokyukoki Mfg. Co. Ltd.: See—
Sakakura, Shinya; Ohashi, Ryota; and Sakikawa, Shigenori, 5,588,294, Cl. 60-464,000.
- Kao Corporation: See—
Muraoka, Tsutomu, 5,589,162, Cl. 424-70,120.
- Kapec, Jeffrey: See—
Tanaka, Kazuma; Kapec, Jeffrey; and Chochinov, Allan B., 5,588,745, Cl. 366-130,000.
- Kaplan-Pap, Marta: See—
Harsanyi, Kalman; Gizer, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kaplan-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
- Kapsales, Peter: See—
Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54,100.
- Karakida, Shoichi: See—
Motoda, Takashi; Karakida, Shoichi; Kaneno, Nobuaki; and Kageyama, Shigeki, 5,589,110, Cl. 261-61,000.
- Karasawa, Hitoshi: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
- Kardokus, Janine K.: See—
Dunlop, John A.; Yuan, Jun; Kardokus, Janine K.; and Emigh, Roger A., 5,590,389, Cl. 419-67,000.
- Kari, Prasad: See—
Williams, Jon L.; Pierce, James C.; Anderson, G. Mark; and Kari, Prasad, 5,589,364, Cl. 435-69,700.
- Karlow, James P.; Boumarah, Mohamed; and Hurford, Jonathan P., to Takata, Inc. Side impact head restraint with inflatable deployment, 5,588,672, Cl. 280-730,200.
- Karini, Gadi: See—
Bayley, Gwain; Grob, Matthew S.; Karmi, Gadi; Kimball, Robert H.; and Propach, David S., 5,590,406, Cl. 455-54,200.
- Karp, Arthur: See—
Lien, Erling L.; and Karp, Arthur, 5,589,736, Cl. 315-5,430.
- Karpati, Egon: See—
Harsanyi, Kalman; Gizer, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kaplan-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
- Karpik, Meredith L.: See—
Lashmet, Brent J.; Lashmet, Doug C.; Lashmet, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Meredith L., 5,589,004, Cl. 134-10,000.
- Kartalopoulos, Stamatios V., to Lucent Technologies Inc. Optimal parallel processor architecture for real time multitasking, 5,590,323, Cl. 395-676,000.
- Kartha, Kutty K.: See—
Nehra, Narendra S.; Kartha, Kutty K.; and Chibbar, Ravindra N., 5,589,617, Cl. 800-205,000.
- Kartman, Albert E.: See—
Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zaremka, Michael J., 5,588,507, Cl. 188-71,500.
- Karwowski, James P.: See—
Hochlowski, Jill E.; Jackson, Marianna; Kadam, Sunil K.; Karwowski, James P.; and McAlpine, James B., 5,589,485, Cl. 514-315,000.
- Kasa, Yasushi: See—
Akaogi, Takao; Yoshida, Masanobu; Ogawa, Yasushige; Kasa, Yasushi; and Kawamura, Shouichi, 5,590,074, Cl. 365-185,220.
- Kashimura, Makoto: See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279,000.
- Kashiwaka, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Itsu; Oota, Norio; and Sugiyama, Hisanori, to Hitachi Maxell, Ltd. Magneto-optic recording medium, 5,590,097, Cl. 369-13,000.
- Kassapian, Christian G., to SGS-Thomson Microelectronics S.A. Voltage booster circuit of the charge-pump type with bootstrapped oscillator, 5,589,793, Cl. 327-536,000.
- Kasser, Michel; and Lund, Glenn, to Aerospatiale Societe Nationale Industrielle. Retroreflector target for laser ranging, 5,589,981, Cl. 359-529,000.
- Kasuga, Koji, to NEC Corporation. Backlight device for a liquid crystal display facilitating the replacement of a lamp thereof, 5,588,740, Cl. 362-221,000.
- Katagiri, Yoshimichi: See—
Takezawa, Satoshi; Katagiri, Yoshimichi; Nakamura, Yasushige; and Sawatari, Norio, 5,589,313, Cl. 430-122,000.
- Katahira, Masayuki: See—
Osawa, Nobuyuki; and Katahira, Masayuki, 5,588,750, Cl. 384-15,000.
- Kataumi, Yoshimasa; and Takikawa, Yoshihiro, to Fujikiko Kabushiki Kaisha. Gear shifting device with locking disengageable mechanism manually operated by a tool, 5,588,330, Cl. 74-483,000.
- Kato, Eiichi; Momota, Makoto; and Ohishi, Hiroyuki, to Fuji Photo Film Co., Ltd. Method for preparation of printing plate by electrophotographic process, 5,589,308, Cl. 430-49,000.
- Kato, Heiji: See—
Leadbeater, Darren J.; Kato, Heiji; and Fukase, Hisahiko, 5,588,479, Cl. 164-480,000.
- Kato, Hiroyasu, to Katoh Kinzoku Kogyo Kabushiki Kaisha. Lock for deflectable writing utensil, 5,588,764, Cl. 401-99,000.
- Kato, Kenichi: See—
Imai, Keisuke; Kato, Kenichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, 5,588,608, Cl. 242-374,000.
- Kato, Masato: See—
Shimokoriyama, Makoto; Aoki, Akio; and Kato, Masato, 5,589,946, Cl. 386-47,000.
- Kato, Masayuki: See—
Aritake, Hirokazu; Kato, Masayuki; and Nakashima, Masato, 5,589,957, Cl. 359-23,000.
- Kato, Naoki; and Kunigita, Masaya, to AG Technology Co., Ltd. Method of making TFT display, 5,589,406, Cl. 437-21,000.
- Kato, Nobuko: See—
Doi, Miwako; Fukui, Mika; Nishida, Ikko; and Kato, Nobuko, 5,590,268, Cl. 395-326,000.
- Kato, Ritsuko: See—
Asai, Motoo; and Kato, Ritsuko, 5,589,250, Cl. 428-209,000.
- Kato, Shingo: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
- Kato, Takashi; and Nakanishi, Hiromi, to Sumitomo Electric Industries, Ltd. Light emitting element module and manufacturing method thereof, 5,589,990, Cl. 359-799,000.
- Kato, Takashi: See—
Satomi, Yasuhiko; Itoh, Seiji; Otsuka, Eiji; Yamaki, Jun; and Kato, Takashi, 5,588,197, Cl. 29-455,100.
- Kato, Toshiyuki: See—
Ogita, Yasuhisa; and Kato, Toshiyuki, 5,589,524, Cl. 523-212,000.
- Kato, Tsuguo; and Thai, Cao M., to Kabushiki Kaisha Toshiba. Method of manufacturing a molding using a filler or an additive concentrated on an arbitrary portion or distributed at a gradient concentration, 5,589,129, Cl. 264-437,000.
- Katoh Kinzoku Kogyo Kabushiki Kaisha: See—
Kato, Hiroyasu, 5,588,764, Cl. 401-99,000.
- Katoh, Takehiro: See—
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218,000.
- Katou, Kouichi; Watanabe, Eiji; and Kunitune, Kouichi, to Chisso Corporation. Photosensitive polyimide resin composition, 5,589,319, Cl. 430-288,100.
- Katsuhara, Kenji, to Mita Industrial Co., Ltd. Density detecting device used for image forming apparatus, 5,589,914, Cl. 399-60,000.
- Katz, Lior: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Levi; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehzekel; Greenfield, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Kaufman, Jack W. Waste treatment material dispensing canister, 5,589,145, Cl. 422-292,000.
- Kaufman, Richard A.; Konopka, John M.; Rosenfeld, Henry J.; and Sabo, Janine E., to Hoffmann-La Roche Inc. In situ nicotinamide coenzyme generating system for enzyme based clinical chemistry assays, 5,589,348, Cl. 435-26,000.
- Kaufmann, Norbert: See—
Krause, Manfred; Kaufmann, Norbert; and Neumann, Mathias, 5,589,398, Cl. 436-164,000.
- Kaul, David J.: See—
Menashi, Jameel; Reid, Robert C.; Whitehouse, Robert S.; and Kaul, David J., 5,589,531, Cl. 524-400,000.
- Kawabata, Hiromi; and Takeda, Yutaka, to NEC Corporation. Memory data copying apparatus, 5,590,279, Cl. 395-185,000.
- Kawahata, Kazuaki: See—
Honda, Masami; and Kawabata, Kazuaki, 5,590,024, Cl. 361-684,000.
- Kawaguchi, Kenzo; Takemura, Tetsuya; Matsuhara, Hideki; Takagi, Sinya; and Kanda, Atsushi, to NGK Spark Plug Co., Ltd. Aluminum nitride sintered body and process for producing the same, 5,589,429, Cl. 501-96,000.
- Kawaguchi, Yasuhiro: See—
Egawa, Tatsuya; Kawaguchi, Yasuhiro; Mogami, Kenji; and Shimizu, Nobuaki, 5,589,597, Cl. 568-608,000.
- Kawahata, Kazunari; and Kushihi, Yuichi, to Murata Manufacturing Co., Ltd. Method of regulating resonance frequency of surface-mountable antenna, 5,588,198, Cl. 29-600,000.
- Kawai, Hiroyuki; Sekihara, Kensuke; and Migita, Shinichi, to Hitachi Medical Corporation. Method and apparatus for x-ray computed tomography, 5,590,164, Cl. 378-4,000.
- Kawai, Masahito: See—
Ito, Tatsuya; Kawai, Masahito; and Yasukawa, Yoshihiro, 5,590,053, Cl. 364-499,000.
- Kawakami, Yoshifumi: See—
Koniya, Kyosuke; Kawakami, Yoshifumi; and Okamoto, Hiroshige, 5,589,564, Cl. 528-196,000.
- Kawakita, Kouji; Tsukamoto, Masahide; Horio, Yasuhiro; Nakatani, Seichi; and Hatakeyama, Akihiro, to Matsushita Electric Industrial Co., Ltd. Method of manufacturing two-sided and multi-layered printed circuit boards, 5,588,207, Cl. 29-852,000.
- Kawakubo, Hiroyuki: See—
Sawa, Atsushi; and Kawakubo, Hiroyuki, 5,588,405, Cl. 123-90,330.
- Kawamae, Osamu: See—
Saito, Seichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shiokawa, Junji; and Kawamae, Osamu, 5,589,995, Cl. 360-48,000.
- Kawamoto, Masakazu, to Fujitsu Limited. Method of restoring and updating records in a disk cache system during disk drive idle time using start and end addresses, 5,590,298, Cl. 395-403,000.
- Kawamura, Shigetoshi; and Yamamura, Takehiko, to Sumitomo Wiring Systems, Ltd. Ferrule, 5,590,231, Cl. 385-78,000.
- Kawamura, Shouichi: See—
Akaogi, Takao; Yoshida, Masanobu; Ogawa, Yasushige; Kasa, Yasushi; and Kawamura, Shouichi, 5,590,074, Cl. 365-185,220.
- Kawanishi, Satoki: See—
Takara, Hidehiko; Kawanishi, Satoki; and Saruwatari, Masatoshi, 5,590,143, Cl. 372-28,000.
- Kawano, Toshihiko, to Yamaha Corporation. Power source apparatus, 5,590,033, Cl. 363-25,000.
- Kawaoka, Yoshiki, to Fuji Photo Film Co., Ltd. Image memory device and method of operating same, 5,589,889, Cl. 348-674,000.
- Kawasaki Jukogyo Kabushiki Kaisha: See—
Maruyama, Haruyoshi; Ogata, Shin; and Tsumiyama, Yoshinori, 5,588,388, Cl. 114-271,000.
- Kawashima, Ikue; and Hanaoka, Katsunori, to Ricoh Company, Ltd. Semiconductor integrated circuit device and a method of manufacturing the same, 5,589,712, Cl. 257-750,000.
- Kawashima, Kazuhiro: See—
Murata, Tomohiro; Kurihara, Kenzo; Kawashima, Kazuhiro; and Niida, Mitsuaki, 5,590,272, Cl. 395-181,000.
- Kawata, Satoshi; Doh, Masaji; Sakachi, Yoichiro; and Daiku, Hiroshi, to Fujitsu Limited. Infrared detection device comprising a pyroelectric thin film and method for fabricating the same, 5,589,687, Cl. 250-338,300.
- Kaylor, Scott A.: See—
Forn, William R.; and Kaylor, Scott A., 5,590,154, Cl. 375-229,000.
- Kayukawa, Hiroaki: See—
Kimura, Kazuya; Kayukawa, Hiroaki; Takeichi, Toru; and Hiramatsu, Osamu, 5,588,807, Cl. 417-222,200.
- Kazama, Junichi: See—
Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, 5,590,314, Cl. 395-681,000.
- Kazama, Tsutomu; and Kachi, Mitsuyasu, to Mitsubishi Denki Kabushiki Kaisha. Position control system and position control method thereof, 5,589,748, Cl. 318-560,000.
- KCS Industries, Inc.: See—
Hagopian, Gerald M., 5,588,537, Cl. 211-4,000.

- Keane, Patrick J.; and Richards, Justin J. C., to International Business Machines Corporation. Method and apparatus for graphic association of user dialog displays with primary applications in a data processing system, 5,590,264, Cl. 395-340,000.
- Kearney, Kevin R.; Collins, Mark L.; Eldredge, John K.; and Morrissey, David V., to Amoco Corporation. Hybridization promotion reagents, 5,589,335, Cl. 435-6,000.
- Keasler, William E.: See—
Geigel, Alfred A.; and Keasler, William E., 5,590,121, Cl. 370-290,000.
- Keating, Carey E. Garage door brace, 5,588,270, Cl. 52-291,000.
- Keep, Peter R.: See—
Janse Van Rensburg, Richard W.; and Keep, Peter R., 5,589,863, Cl. 347-75,000.
- Keil, Andreas: See—
Fox, Siegfried; and Keil, Andreas, 5,590,019, Cl. 361-643,000.
- Kejr Engineering, Inc.: See—
Scon, Gregory H.; and Kejr, Melvin P., 5,588,771, Cl. 403-353,000.
- Kejr, Melvin P.: See—
Scott, Gregory H.; and Kejr, Melvin P., 5,588,771, Cl. 403-353,000.
- Keller, Douglas V., Jr.: See—
Spring, G. Everett; and Keller, Douglas V., Jr., 5,589,631, Cl. 73-49,200.
- Kelley, Harold E.; Silvis, William E.; and Terry, Charles J., to Kennametal Inc. Matrix for a hard composite, 5,589,268, Cl. 428-408,000.
- Kelly, David L.; and Francis, Sidney E., III, to HEM Trading. Double adaptor bar for single inserts used in casting concrete, 5,588,263, Cl. 52-125,400.
- Kelly, James D.: See—
Krein, William T.; Flaig, Charles M.; and Kelly, James D., 5,590,130, Cl. 370-462,000.
- Kelly, Patrick J., to National-Standard Company. Stackable dispensing apparatus for wire reels, 5,588,372, Cl. 108-55,100.
- Kelso, John F., to Aluminum Company of America. Alumina multilayer wiring substrate provided with high dielectric material layer, 5,590,017, Cl. 361-321,400.
- Kelve, Merikke: See—
Saarna, Mart; Kelve, Merikke; Truve, Erkki; and Teeri, Teemu, 5,589,625, Cl. 800-205,000.
- Kemira Oy. Biotech: See—
Saarna, Mart; Kelve, Merikke; Truve, Erkki; and Teeri, Teemu, 5,589,625, Cl. 800-205,000.
- Kenik, Richard J.: See—
Holoubek, Kevin J.; Kenik, Richard J.; and Bontrager, Paul R., 5,590,418, Cl. 455-126,000.
- Kennametal Inc.: See—
Kelley, Harold E.; Silvis, William E.; and Terry, Charles J., 5,589,268, Cl. 428-408,000.
- Kenny, Patrick: See—
Vaishnavi, Vick; Matthews, Wallace; and Kenny, Patrick, 5,590,120, Cl. 370-254,000.
- Kentucky Research and Investment Company Limited: See—
Kaftanov, V. S.; Suvorov, A. L.; and Sheshin, E. P., 5,588,893, Cl. 445-6,000.
- Keppner, Herbert, to Universite De Neuchatel. Photovoltaic cell and method for fabrication of said cell, 5,589,008, Cl. 136-259,000.
- Kerr Group, Inc.: See—
Farside, Nicholas, 5,588,546, Cl. 215-237,000.
- Kert, Jimmie. Endodontic obturator, 5,588,835, Cl. 433-81,000.
- Kervagoret, Gilbert, to AlliedSignal Europe Services Technique. Module for controlling pressure in a hydraulic circuit, 5,588,463, Cl. 137-596,150.
- Keystone Retaining Wall Systems, Inc.: See—
Dawson, William B., 5,588,262, Cl. 52-102,000.
- Khachaturian, Jon E.; and Thrift, William B., to Versabar, Inc. Tension load cell apparatus, 5,589,646, Cl. 73-862,474.
- Khan, Azhar J.; Hopkins, David P.; and Khan, Mohammad A., to Beeton Dickinson and Company. Process of making a shaped tip on a catheter, 5,589,120, Cl. 264-130,000.
- Khan, Mohammad A.: See—
Khan, Azhar J.; Hopkins, David P.; and Khan, Mohammad A., 5,589,120, Cl. 264-130,000.
- Khoo, Iam-Choon, to Penn State Research Foundation. The. Liquid crystal fiber array for optical limiting of laser pulses and for eye/sensor protection, 5,589,101, Cl. 252-299,010.
- Kibbel, Bradley W.: See—
Sokol, Gerald E.; Lee, Howard H.; and Kibbel, Bradley W., 5,588,477, Cl. 164-34,000.
- Kidawara, Atsushi: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
- Kidou, Hirokazu: See—
Tomozane, Shotaro; Kidou, Hirokazu; and Nakabayashi, Yukikazu, 5,589,248, Cl. 428-174,000.
- Kiefer, James, to RAN Enterprises, Inc. Non-rotatable mechanical attachment and method thereof, 5,588,684, Cl. 285-62,000.
- Kielmeyer, William H.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kielmeyer, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593,000.

Kikinis, Dan; Doerner, Pascal; and Seiler, William J., to Elonex IP Holdings Ltd. Personal digital assistant module having a multi-portion keyboard with inductive coupling. 5,590,382, Cl. 395-893,000.

Kikkawa, Kohei. See—
Yamada, Koichiro; Yasuda, Kōsuke; Kikkawa, Kohei; and Kohno, Rikako, 5,589,478, Cl. 514-269,000.

Kikuchi, Ryo. See—
Yoshimura, Toshifumi; Kikuchi, Ryo; and Inuma, Shoji, 5,588,674, Cl. 280-732,000.

Kikuchi, Shoji. See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nima, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279,000.

Kikuchi, Shuichi, and Higuchi, Shintaro, to Sony Corporation. Cover of tape cartridge and assembly method of same cartridge. 5,588,606, Cl. 242-347,000.

Kikuyama, Seiichiro. See—
Ono, Yukio; and Kikuyama, Seiichiro, 5,589,778, Cl. 324-654,000.

Kilbride, Terence K. See—
Lisa, Rudolph E.; Kilbride, Terence K.; and Jager, Karl-Friedrich, 5,589,438, Cl. 504-236,000.

Kile, Richard A., to Whitaker Corporation. The Connector with pin terminals adapted for surface mounting. 5,588,849, Cl. 439-83,000.

Kim, Andrew S.; and Camp, Floyd E., to Crucible Materials Corporation. RE-Fe-B magnets and manufacturing method for the same. 5,589,009, Cl. 148-302,000.

Kim, Byung C. See—
Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., 5,589,264, Cl. 428-359,000.

Kim, Chul-Soo. See—
Park, Churoo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230,030.

Kim, Jeong-tae, to Samsung Electronics Co., Ltd. Tracking control method and apparatus for video recorder which adds a combined first and second tracking error signal to the next tracking error signal. 5,589,997, Cl. 360-77,140.

Kim, Myung-Ho. See—
Park, Churoo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230,030.

Kim, Sang K.; Oh, Pahng-Roo; and Lee, Hong J., to Daewoo Electronic Co., Ltd. Valve utilizing shape memory alloys and an anti-lock brake system with the valve. 5,588,717, Cl. 303-84,200.

Kim, Seong-Woo. See—
Lee, Don-Seon; and Kim, Seong-Woo, 5,589,923, Cl. 399-28,000.

Kim, Suk-ki. See—
An, Hyeon-keon; Shin, Young-ho; and Kim, Suk-ki, 5,590,206, Cl. 381-71,000.

Kim, Tae-Jin. See—
Park, Churoo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230,030.

Kim, Thomas K. Flue for water heater. 5,588,399, Cl. 122-17,000.

Kim, Young R.; Iles, Kenneth E.; and Larue, Roderick W., to Abbott Laboratories. Cell suspension preparation apparatus and method. 5,589,394, Cl. 436-63,000.

Kimball, Robert H. See—
Bayley, Gwain; Grob, Matthew S.; Karmi, Gad; Kimball, Robert H.; and Propach, David S., 5,590,406, Cl. 455-54,200.

Kimberly-Clark Corporation. See—
Baker, Jerry W.; and Reader, Timothy W., 5,588,155, Cl. 2-123,000.

Hultman, David P.; Watson, Donald D.; and Heribacka, Edward W., 5,589,034, Cl. 162-111,000.

Kimberly-Clark Limited. See—
Madden, Peter; and Currie, Kenneth J. G., 5,589,258, Cl. 428-286,000.

Kimura, Hiromichi. See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128,000.

Kimura, Kazuya, Kayukawa, Hiroaki; Takechi, Toru; and Hiramatsu, Osamu, to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho. Swash plate type variable displacement compressor. 5,588,807, Cl. 417-222,200.

Kimura, Kiyoshi. See—
Chokai, Shouchi; Aoki, Tomiyoshi; and Kimura, Kiyoshi, 5,589,477, Cl. 514-256,000.

Kimura, Makoto. See—
Hayakawa, Tsuneyasu; and Kimura, Makoto, 5,588,822, Cl. 431-1,000.

Kimura, Mitsuteru, and Kudo, Takeshi, to Terumo Kabushiki Kaisha; and Kimura, Mitsuteru. Infrared radiation sensor. 5,589,688, Cl. 250-338,400.

Kindl, Helmut; Hain, Rüdiger; and Reif, Hans-Jörg, to Bayer Aktiengesellschaft. Bifenyl synthase genes. 5,589,620, Cl. 800-205,000.

Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jörg; Stenzel, Klaus; and Thomzik, Jürgen, to Bayer Aktiengesellschaft. Pinosylvine synthase genes. 5,589,621, Cl. 800-205,000.

King, Bobby J. See—
Chatterji, Jiten; Griffith, James E.; Totten, Patty L.; and King, Bobby J., 5,588,489, Cl. 166-293,000.

King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Rombult, Philip A.; and Hebert, Thomas K., to AGFA Division, Bayer Corporation. Optical enclosure for high speed rotating beam deflector. 5,589,973, Cl. 359-214,000.

King, Robert, to COR Therapeutics, Inc. Process for production of inhibited forms of activated blood factors. 5,589,571, Cl. 530-381,000.

King, Robert, to COR Therapeutics, Inc. Process for production of inhibited forms of activated blood factors. 5,589,572, Cl. 530-381,000.

King, Robert D., to General Electric Company. Integrated cranking inverter and boost converter for a series hybrid drive system. 5,589,743, Cl. 318-139,000.

King, Roger M., to Beeson and Sons Limited. Child-resistant and elderly friendly closure for containers. 5,588,545, Cl. 215-216,000.

Kinoshita, Akira. See—
Etoh, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirofumi; Sakimura, Tomoo; Suzuki, Tomoko; and Kinoshita, Akira, 5,589,314, Cl. 430-126,000.

Suzuki, Tomoko; Kinoshita, Akira; Hayata, Hirofumi; and Sakimura, Tomoo, 5,589,309, Cl. 430-59,000.

Kinoshita, Hirofumi. See—
Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, 5,590,314, Cl. 395-681,000.

Kinoshita, Masafumi; Niwa, Toshio; and Shibata, O., to Dainippon Ink and Chemicals Inc. Process for producing modified propylene polymer and modified propylene polymer composition. 5,589,541, Cl. 525-66,000.

Kinoshita, Masahide. See—
Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114,000.

Kinoshita, Ritsuro. See—
Shibata, Hideyo; Kinoshita, Ritsuro; Yoshida, Takayasu; and Eshima, Shigeo, 5,589,992, Cl. 386-72,000.

Kinoshita, Shin-Issu. See—
Kashiwakura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Issu; Oota, Norio; and Sugiyama, Hisanori, 5,590,097, Cl. 369-13,000.

Kinoshita, Shinji, and Ide, Mitsuru, to Kabushiki Kaisha Sankyo Seiki Seisakusho. Disk drive motor with labyrinth seal. 5,588,753, Cl. 384-488,000.

Kinoshita, Takashi, to Mitsubishi Denki Kabushiki Kaisha. Vacuum pump with planetary gear accelerator. 5,588,821, Cl. 418-259,000.

Kiribuchi, Takeshi, to Shima Seiki Manufacturing Ltd. Control method for a carrier of a knitting machine and its apparatus. 5,588,311, Cl. 66-60,000.

Kirin Beer Kabushiki Kaisha. See—
Misawa, Norihiko; Kobayashi, Kazuo; and Nakamura, Katsumi, 5,589,581, Cl. 536-23,200.

Kirino, Fumiyoshi; Maeda, Takeshi, Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigenatsu, Kazuo; and Toda, Tsuyoshi, to Hitachi, Ltd. Method of controlling recording of optical records. 5,590,111, Cl. 369-116,000.

Kirsch, Wolff M. See—
Zhu, Yong H.; and Kirsch, Wolff M., 5,588,951, Cl. 600-207,000.

KIS Photo Industrie (SARL). See—
Gruel, Henri; Moraine, Michel; and Crasntanski, Serge, 5,589,902, Cl. 396-3,000.

Kiso, Makoto. See—
Ishida, Hideharu; Kiso, Makoto; and Hasegawa, Akira, 5,589,465, Cl. 514-25,000.

Kiss, Bela. See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csongor, Katalin; Lakzy, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, János; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.

Kitada, Shinichiro, to Nissan Motor Co., Ltd. Electric hybrid vehicle. 5,588,498, Cl. 180-65,400.

Kitaguchi, Hiroshi. See—
Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,589,510, Cl. 514-590,000.

Kitai, Katsuyoshi. See—
Sakakibara, Tadayuki; Tanaka, Teruo; Tanaka, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuharu, 5,590,353, Cl. 395-800,000.

Kitajima, Eiichi, to Nikon Corporation. Laser surveying system. 5,589,939, Cl. 356-375,000.

Kitamura, Shoji; Shindo, Yoichi; and Amano, Akira, to Fuji Electric Co., Ltd. Semiconductor laser device. 5,590,144, Cl. 372-36,000.

Kitamura, Yoshiharu, to NHK Spring Co. Ltd.; and Uniflex, Inc. Length-adjusting device for control cable. 5,588,333, Cl. 74-502,400.

Kiuchi, Katsumi; Wakamatsu, Hiroaki; Suzuki, Fumitake; and Koshikawa, Takao, to Fujitsu Limited. Perpendicular magnetic recording medium having a soft magnetic underlayer with a stripe magnetic domain structure. 5,589,262, Cl. 428-336,000.

Klang, James K., to GNB Battery Technologies, Inc. Apparatus and method for step-charging batteries to optimize charge acceptance. 5,589,757, Cl. 320-22,000.

Klapproth, Peter; Zandveld, Frederik; Bakker, Jacobus M.; and Van Lee, Gerardus C., to U.S. Philips Corporation. Microcontroller provided with hardware for supporting debugging as based on boundary scan standard-type extensions. 5,590,354, Cl. 395-800,000.

Klee, Harry J.; and Elmer, James S., to Monsanto Company. Plant promoter. 5,589,583, Cl. 536-24,100.

Klein, Joachim; and Hunklinger, Herbert, to Lang Apparatebau GmbH. Metering pump with a vent valve. 5,588,809, Cl. 417-283,000.

Klein, Lawrence J. See—
Boteler, William C.; and Klein, Lawrence J., 5,588,870, Cl. 439-467,000.

Klepacki, David G. See—
Klepacki, Frank H.; and Klepacki, David G., 5,588,358, Cl. 100-53,000.

Klepacki, Frank H.; and Klepacki, David G. Trash handling device. 5,588,358, Cl. 100-53,000.

Kliklok Corporation. See—
Cargile, John W., Jr., 5,588,583, Cl. 229-120,170.

Klink, Rainer; German, Johann; and Warthmann, Wolfgang, to Deutsche Automobilgesellschaft mbH. Battery box with fluid flow channels to maintain proper temperature. 5,589,290, Cl. 429-99,000.

Klinker, Gudrun J., to Digital Equipment Corporation. Interactive visualization environment with improved visual programming interface. 5,590,271, Cl. 395-326,000.

Klitz, Kevin. See—
Scovill, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772,000.

Klober, Martin. See—
Schleicher, Ulrich; Klober, Martin; Schwarz, Wolfgang; and Feuerstake, Eugen, 5,589,662, Cl. 149-35,000.

Kloekner-Humboldt-Deutz AG. See—
Stahl, Hans-Jürgen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, 5,588,829, Cl. 432-77,000.

Klomsdorf, Armin. See—
Alberth, William P., Jr.; Janssen, John J.; and Klomsdorf, Armin, 5,589,796, Cl. 330-133,000.

Klooz, Charles D. See—
Warren, James D.; Vogt, Carl R.; and Klooz, Charles D., 5,590,026, Cl. 361-704,000.

Klover, John M.; and Hamrick, Philip F., to Hamrick Manufacturing & Service, Inc. Method and apparatus for packing a plurality of articles in cartons. 5,588,284, Cl. 53-534,000.

Kluesener, Bernard W. See—
Guskey, Gerald J.; Hellyer, James A.; Kluesener, Bernard W.; and Stipp, Gordon K., 5,589,216, Cl. 426-607,000.

Knauf, Vic C. See—
Kndl, Jean C.; Bruening, George; and Knauf, Vic C., 5,589,379, Cl. 435-240,400.

Knaus, Dennis A. Process of extruding lightly crosslinked polyolefin foam. 5,589,519, Cl. 521-60,000.

Knecht Filterwerke GmbH. See—
Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruns, Elke; Guntert, Dietmar; and Müller, Hubert, 5,589,060, Cl. 210-130,000.

Knee, Derek L., to Samsung Semiconductor, Inc. Fully differential flash ADC based on the voltage follower amplifier structure. 5,589,831, Cl. 341-159,000.

Knee, Robert A.; Favia, Anthony R.; Davis, Bruce; and Miller, Larry. Electronic television program guide schedule system and method with data feed access. 5,589,892, Cl. 348-731,000.

Knetsch, Harold, to Emhart Inc. Feeder for components, in particular components designed with a head. 5,588,576, Cl. 227-119,000.

Knezovich, Anthony D. Security gate lock assembly. 5,588,314, Cl. 70-56,000.

Knoll Aktiengesellschaft. See—
Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Hehl, Vera; and Schnappinger, Dirk, 5,589,362, Cl. 435-69,100.

Knöpfel, Hans P. See—
Döbbling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelamayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431-354,000.

Knowles, Billy J. See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800,000.

Knutsen, Lars J. S. See—
Lau, Jesper; and Knutsen, Lars J. S., 5,589,467, Cl. 514-46,000.

Ko, Kung-Ling. See—
Mizrahi-Shalom, Ori K.; and Ko, Kung-Ling, 5,590,358, Cl. 395-800,000.

Ko, Soon-Myung. Belt with ratchet type buckling means. 5,588,186, Cl. 24-585,000.

Kobayashi, Hideo. See—
Ito, Katsuhiko; Kobayashi, Hideo; Ishiuchi, Yukio; and Shimada, Toshio, 5,588,406, Cl. 123-90,340.

Kobayashi, Hiroyoshi, to Olympus Optical Co., Ltd. Head mounted image display. 5,589,846, Cl. 345-8,000.

Kobayashi, Kazuo. See—
Misawa, Norihiko; Kobayashi, Kazuo; and Nakamura, Katsumi, 5,589,581, Cl. 536-23,200.

Kobayashi, Koutarou. See—
Ishiyama, Nontaka; and Kobayashi, Koutarou, 5,589,768, Cl. 324-207,210.

Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, to Toray Industries, Inc. Method for preparing carbon fibers. 5,589,055, Cl. 205-768,000.

Kobayashi, Naoki. See—
Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34,000.

Kobayashi, Nobuaki; Kaise, Satoshi; and Kano, Hideki, to Unisia Jecs Corporation. Structure of magnetostrictive shaft applicable to magnetostriction-type torque sensor for detecting torque applied to rotatable shaft and method for manufacturing the same. 5,589,645, Cl. 73-862,335.

Kobayashi, Ryuji. See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6,000.

Kobayashi, Shin. See—
Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15,000.

Koberger, Hermann. See—
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Rief, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187,000.

Kobori, Yoichi. See—
Onodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Teruo; and Itoh, Shigeo, 5,589,738, Cl. 315-169,100.

Koch, Durmus. See—
Cunningham, Robert W.; Koch, Durmus; Mura, Janine R.; Felix, Augustus; and Halick, Gary V., 5,588,958, Cl. 604-4,000.

Koch, Gene C. See—
Gunning, William J., III; Winker, Bruce K.; and Koch, Gene C., 5,589,963, Cl. 349-119,000.

Kochanski, Gregory P. See—
Jin, Sungho; Kochanski, Gregory P.; and Zhu, Wei, 5,588,894, Cl. 445-24,000.

Kodama, Hisashi. See—
Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tunekio, 5,590,062, Cl. 364-578,000.

Kodera, Yasuto. See—
Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuto; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160,000.

Koeda, Takashi. See—
Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikiyo; and Koeda, Takashi, 5,588,950, Cl. 600-178,000.

Koehr, Robert, to Dr. Ing. h.c.f. Porsche AG. Arrangement for increasing the buckling strength of windshield pillars of a vehicle. 5,588,694, Cl. 296-188,000.

Koenig & Bauer Aktiengesellschaft. See—
Bolza-Schünemann, Claus A., 5,588,364, Cl. 101-247,000.

Koerner, Michael; and Deleuw, David L., to Clorox Company. The High water liquid enzyme prewash composition. 5,589,448, Cl. 510-284,000.

Koerse, Ronkers. See—
Wolbers, Dick R.; and Koerse, Ronkers, 5,588,780, Cl. 405-170,000.

Kofflach Sport Gesellschaft m.b.H. & Co. KG. See—
Perner, Johann; and Trinkaus, Gerhard, 5,588,658, Cl. 280-11,220.

Koga, Keiji; Arai, Hitoshi; Kagotani, Tsuneo; and Miyaki, Yousuke, to TDK Corporation. Lithium secondary cell. 5,589,297, Cl. 429-212,000.

Kogawa, Kuniyuki; and Takaya, Koetsu, to Fuji Electric Co., Ltd. Thermal overload relay with mis-readjustment preventing device. 5,589,809, Cl. 337-36,000.

Kogge, Peter M. See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800,000.

Kogl, Lorenz, III. See—
Tsuei, Alexander C.; Kogl, Lorenz, III; and Pendergrass, Daniel B., Jr., 5,589,194, Cl. 424-497,000.

Kogure, Koushirou. See—
Koyano, Shinji; Kogure, Koushirou; Ohya, Takashi; Sakakibara, Makoto; and Hanayama, Katsutoki, 5,590,208, Cl. 381-154,000.

Kogure, Masao. See—
Okabe, Hideaki; Suzuki, Eiji; Kogure, Masao; and Saito, Takanori, 5,589,192, Cl. 424-486,000.

Koh Development, Inc. See—
Breznak, John A.; Emerson, David; and Koh, John K., 5,589,352, Cl. 435-34,000.

Koh, John K. See—
Breznak, John A.; Emerson, David; and Koh, John K., 5,589,352, Cl. 435-34,000.

Kohno, Rikako. See—
Yamada, Koichiro; Yasuda, Kōsuke; Kikkawa, Kohei; and Kohno, Rikako, 5,589,478, Cl. 514-269,000.

Koiso, Yasuhiko; Matsumoto, Yoshiki; Fujisawa, Masayuki; and Nagatsu, Isao, to Japan Pionics Co., Ltd. Trigger for regenerative substances and regenerative body with the trigger. 5,588,304, Cl. 62-340,000.

- Korvonen, Erkki A. Self-synchronizing brake band actuating system for automatic change speed transmissions. 5,588,928, Cl. 475-126.000.
- Kozumi, Satoshi, Yonetani, Yoshiyuki, and Teshiba, Sadao, to Kyowa Hakko Kogyo Co., Ltd. Process for producing riboflavin. 5,589,355, Cl. 435-66.000.
- Kozumi, Yoshimasa, Hiraoaka, Hidenori, and Kozumi, Yoshimasa, 5,589,546, Cl. 525-193.000.
- Kojima, Shoichi, Minagawa, Kazuhiro, Kano, Haruyuki, Miyazaki, Tadaaki, and Wada, Hiroaki, to Sumitomo Metal Industries, Ltd. Process for preparing a silicon carbide sintered body for use in semiconductor equipment. 5,589,116, Cl. 264-65.000.
- Kojima, Susumu, to NEC Corporation. Selecting and prioritizing radio telephone systems at radio terminal. 5,590,397, Cl. 455-33.100.
- Kojima, Yoshikazu, Ser. Saito, Yutaka, and Kojima, Yoshikazu, 5,589,705, Cl. 257-459.000.
- Kojima, Yuchi, to Sony Corporation. Image signal processing apparatus utilizing a 2D Haar transform and adaptive selection of images based on a parameter such as a ratio of coefficients for reducing block distortion and method thereof. 5,590,222, Cl. 382-268.000.
- Kojima, Katsuhiko, Kondo, Hisao, Arakawa, Hiroharu, Ohkubo, Mitsuru, and Suda, Hiroyuki, to Banyu Pharmaceutical Co., Ltd. Process for producing glycosylated indolopyridocarbazole derivatives by culturing certain microorganisms. 5,589,365, Cl. 435-85.000.
- Kokuga, Toshiharu, Ser. Kane, Osamu, Okada, Tatsuya, and Kokuga, Toshiharu, 5,589,755, Cl. 320-21.000.
- Kokusai Denshin Denwa Kabushiki Kaisha, Ser. Taga, Hidenori, Edagawa, Noboru, Takeida, Noriyuki, Yamamoto, Shu, and Akiba, Shigeyuki, 5,589,969, Cl. 359-124.000.
- Kolatis, Leonidas, Lenoble, Bertrand L. J., and Prince, Mark A., to Dow Corning S.A. Particulate foam control agents. 5,589,449, Cl. 510-466.000.
- Kolefas, Chris, Supporting arm with locking means for a hinged panel. 5,588,250, Cl. 49-304.000.
- Kolor, Daniel J., Gupte, Nalin B., and Shah, Siddharth R., to International Business Machines Corporation. Method and apparatus for emulating a high capacity DRAM. 5,590,071, Cl. 365-149.000.
- Kolon, Anthony D., Gamboa, Ruben A., and Chiment, Danette S., to Logical Information Machines, Inc. System for forming queries to a commodities trading database using analog indicators. 5,590,325, Cl. 395-615.000.
- Komano, Haruki, Ser. Tomotani, Yoko, Nakase, Makoto, Sato, Takashi, Hazama, Hiroaki, Komano, Haruki, and Ito, Shunichi, 5,589,305, Cl. 430-5.000.
- Komiyama, Hiroshi, Ser. Nakata, Ryuji, and Komiyama, Hiroshi, 5,588,751, Cl. 384-463.000.
- Komiyama, Kyosuke, Kawakami, Yoshitami, and Okamoto, Hiroshige, to Asahi Kasei Kogyo Kabushiki Kaisha. Wire-wrapping fall polymerization process for the production of polycarbonates. 5,589,564, Cl. 528-196.000.
- Komiyama, Takeo, Ser. Osaka, Kenji, Komiyama, Takeo, Asano, Yasuo, Sano, Tomomi, Takasugi, Hidetoshi, and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53.000.
- Komiyama, Takeshi, Ser. Kuwabara, Mitsuo, Ikegami, Kiyoshi, Yoshida, Teruaki, Takahashi, Koji, Harada, Tamiyoshi, Komiyama, Takeshi, Hirai, Fumio, and Hayashi, Masamichi, 5,590,388, Cl. 419-39.000.
- Komori Corporation, Ser. Sugiyama, Hiroyuki, Hirose, Norio, Hamabuchi, Teruyoshi, and Muto, Hikop, 5,588,362, Cl. 101-218.000.
- Komori, Kazuhiko, Ser. Kondo, Nobukazu, Kaneko, Seiji, Gemma, Hideaki, Okada, Tetsuhiko, Komori, Kazuhiko, and Okazawa, Koichi, 5,590,290, Cl. 395-298.000.
- Komura, Yukihito, Ser. Ino, Tsuneyori, Furukawa, Sugiyoshi, Jinbo, Masaki, Kaneko, Hisashi, Fukuzawa, Shinichi, Sugimoto, Masaharu, Nagasawa, Yoshiaki, Ishida, Katsuaki, Yamazaki, Osamu, Komura, Yukihito, and Saka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Komuro, Katsuhiko, Ser. Arato, Toshiaki, Aono, Yasuhisa, Tsumoka, Shigeo, and Komuro, Katsuhiko, 5,589,652, Cl. 75-235.000.
- Kondo, Hisao, Ser. Kojiri, Katsuhisa, Kondo, Hisao, Arakawa, Hiroharu, Ohkubo, Mitsuru, and Suda, Hiroyuki, 5,589,365, Cl. 435-85.000.
- Kondo, Kazuhiko, Ser. Horikawa, Hiroshi, and Kondo, Kazuhiko, 5,589,592, Cl. 540-204.000.
- Kondo, Kiyosi, Ser. Fujii, Tomoko, Yamiaguchi, Kojiro, Kondo, Kiyosi, and Urakami, Teizi, 5,589,481, Cl. 514-287.000.
- Kondo, Masako, Ser. Suzuki, Yoshitaka, Kondo, Masako, Iino, Takashi, Zama, Toshihiro, Shimoda, Yuji, and Takata, Hiroshi, 5,588,302, Cl. 62-161.000.
- Kondo, Nobukazu, Kaneko, Seiji, Gemma, Hideaki, Okada, Tetsuhiko, Komori, Kazuhiko, and Okazawa, Koichi, to Hitachi, Ltd. Method for controlling a bus to progress transfer cycles without inserting a cycle for acknowledgement. 5,590,290, Cl. 395-298.000.
- Kondo, Shigeo, Ser. Iwamoto, Kazuya, Aotani, Noboru, Takada, Kazunori, and Kondo, Shigeo, 5,589,296, Cl. 429-191.000.
- Takada, Kazunori, Kondo, Shigeo, Yamamoto, Osamu, and Nishijima, Motoaki, 5,589,298, Cl. 429-218.000.
- Kondo, Yoshihisa, Ser. Ide, Nobuhito, Yoshida, Takeshi, Kondo, Yoshihisa, Nagamatsu, Masato, Mori, Junji, and Yamazaki, Itaru, 5,590,365, Cl. 395-394.000.
- Kondratiev, Victor K., Kouplitchenko, Valery P., Galitsky, Alexander V., and Baehr, Geoffrey G., to Sun Microsystems, Inc. Radio transceiver having shared modulation and demodulation mixer circuits. 5,590,413, Cl. 455-86.000.
- Konica Corporation, Ser. Itoh, Yoshihiko, Oshiba, Takeo, Matsushima, Asao, Hayata, Hirofumi, Sakimura, Tomoo, Suzuki, Tomoko, and Kimoshita, Akira, 5,589,314, Cl. 430-126.000.
- Ikonami, Yoshikazu, Minami, Satoshi, and Fujii, Yozo, 5,589,919, Cl. 399-262.000.
- Suzuki, Tomoko, Kimoshita, Akira, Hayata, Hirofumi, and Sakimura, Tomoo, 5,589,309, Cl. 430-59.000.
- Konig, Theo, Ser. Schmidt, Helmut, Nass, Ridiger, Aslan, Mesut, Ahayrak, Sener, Arpac, Erugrul, Konig, Theo, and Fister, Dietmar, 5,590,387, Cl. 419-36.000.
- Kono, Katsumi, Nakamura, Shinya, and Honda, Atsushi, to Toyota Jidosha Kabushiki Kaisha. Slip control apparatus for motor vehicle lock-up/clutch. 5,588,937, Cl. 477-169.000.
- Konoike, Takehiro, Marasawa, Hiroshi, Takagi, Hiroshi, and Tomono, Kunis-aburo, to Murata Manufacturing Co., Ltd. Magnetic material for high frequencies. 5,589,096, Cl. 252-62.570.
- Konopka, John M., Ser. Kaufman, Richard A., Konopka, John M., Rosenfeld, Henry J., and Sabo, Janine E., 5,589,348, Cl. 435-26.000.
- Konuma, Kazuo, to NEC Corporation. Infrared imaging device readily removing optical system contributory component. 5,589,876, Cl. 348-164.000.
- Konwiser, Kern T., and Konwiser, Kip M. Electronic dance floor system. 5,589,651, Cl. 84-600.000.
- Konwiser, Kip M., Ser. Konwiser, Kern T., and Konwiser, Kip M., 5,589,654, Cl. 84-600.000.
- Konzen, Neil, Ser. D'Souza, David J., Konzen, Neil, and Weise, David N., 5,590,347, Cl. 395-800.000.
- Kook, Taeho, Ser. DeMarco, John J., Kook, Taeho, and Kostelak, Robert L., Jr., 5,589,303, Cl. 430-5.000.
- Kooy, Ad, Bier, Helmar, and Mebus, Norbert, to LuK Lamellen und Kupplungsbau GmbH. Clutch operating apparatus. 5,588,517, Cl. 192-70.250.
- KOP Flex, Inc., Ser. D'Ercole, Steve, 5,588,917, Cl. 464-79.000.
- Kopetzky, Robert, and Hage, Günther, to Takata (Europe) Vehicle Safety Technology GmbH. Safety belt tensioner for motor vehicles. 5,588,677, Cl. 280-806.000.
- Kopt, Sill, Anne R., Buhl, Steven N., Choate, Glenda L., Schick, Lloyd A., Nagle, Robert E., Chang, Jenq C., Bernstein, Daniel, and Britt, Wayne A., to Abaxis, Inc. Error checking in blood analyzer. 5,590,052, Cl. 364-498.000.
- Koponen, Pekka, Ser. Peltola, Jukka, and Koponen, Pekka, 5,590,415, Cl. 455-115.000.
- Korber, Rolf, to Harmag AG. Yarn winding method and apparatus for carrying out same. 5,588,601, Cl. 242-18.03W.
- Korea Advanced Institute of Science and Technology, Ser. Lee, Kun-Jai, and Park, Jong-Kil, 5,589,071, Cl. 210-638.000.
- Korea Institute of Science and Technology, Ser. Yoon, Han S., Son, Lee W., Kim, Byung C., Lee, Chul I., Min, Byung G., and Cho, Jae W., 5,589,264, Cl. 428-359.000.
- Kormoczy, Peter, Ser. Magyar, Kalman, Gaál, József, Sziráki, István, Lengyel, József, Szabo, Anna Z., Marmatosi, Katalin, Hermezy, István, Szatmari, István, Tarók, Zoltán, and Kormoczy, Péter, 5,589,513, Cl. 514-654.000.
- Kornfeld, Richard K., Ser. Weiland, Ana L., Kornfeld, Richard K., and Maloney, John E., 5,590,408, Cl. 455-69.000.
- Korngold, Robert, Ser. Jameson, Bradford A., McDonnell, James M., and Korngold, Robert, 5,589,458, Cl. 514-13.000.
- Kori, Leland B., Ser. Clark, Randall J., Smith, Bradley W., Rasmussen, Kirk H., and Kori, Leland B., 5,588,676, Cl. 280-741.000.
- Koshikawa, Takao, Ser. Kiuchi, Katsumi, Wakamatsu, Hiroaki, Suzuki, Fumitake, and Koshikawa, Takao, 5,589,262, Cl. 428-336.000.
- Koskenmaki, David C., Ser. Calhoun, Clyde D., and Koskenmaki, David C., 5,589,246, Cl. 428-120.000.
- Koskinen, Jukka, to Valmet Corporation. Jet coating apparatus. 5,588,998, Cl. 118-410.000.
- Koskinen, Yrjö, to Vaisala Oy. Infrared detector with Fabry-Perot interferometer. 5,589,689, Cl. 250-339.010.
- Koss, Timothy A., Ser. Hassler, Joseph A., Deal, Gregory K., Koss, Timothy A., and Heil, Stephen E., 5,590,379, Cl. 395-851.000.
- Kostelak, Robert L., Jr., Ser. DeMarco, John J., Kook, Taeho, and Kostelak, Robert L., Jr., 5,589,303, Cl. 430-5.000.
- Kostiuk, Larry W., and Johnson, Matthew R., to University of Alberta. Governors of the lean premixed fuel burner. 5,588,825, Cl. 431-349.000.

- Kotaki, Yasuo, Ser. Ujita, Toshihiko, Yamakawa, Koji, Takenouchi, Masanori, Sugama, Sadaaki, Watanabe, Kenjiro, Osada, Torachika, Nakajima, Kazuhiro, Tsurumi, Takayoshi, Kubota, Hidemi, Kotaki, Yasuo, Tsukuda, Kei-ichiro, and Sato, Yohei, 5,589,862, Cl. 347-87.000.
- Kotelevtsev, Yuri, Ser. Lalouel, Jean-Marc, Jeunemaitre, Xavier, Lifton, Richard P., Soubrier, Florent, Kotelevtsev, Yuri, and Corvol, Pierre, 5,589,584, Cl. 536-24.310.
- Kotsiopoulos, Thomas G., to Witt, Carol Joyce. Coupon inserting apparatus and method. 5,588,280, Cl. 53-435.000.
- Kotke, Kurt E., Ser. Leonard, Timothy J., and Kotke, Kurt E., 5,588,669, Cl. 280-728.300.
- Korwicki, Allan J., Doering, Jeffrey A., and Falandino, Michael P., to Ford Motor Company. Engine air/fuel control with exhaust gas oxygen sensor heater control. 5,588,417, Cl. 123-697.000.
- Kou, Chin S. Dual locking mechanism for use in umbrella handles. 5,588,454, Cl. 135-24.000.
- Kou, James L. T., to Toshiba America Information Systems, Inc. Apparatus and method for detecting and updating status of removable storage system using shared interrupt and software flag. 5,590,376, Cl. 395-839.000.
- Kouchi, Shinji, Ser. Sawaoka, Ryuji, Kouchi, Shinji, and Muraki, Toshio, 5,589,523, Cl. 523-211.000.
- Kouplitchenko, Valery P., Ser. Kondratiev, Victor K., Kouplitchenko, Valery P., Galitsky, Alexander V., and Baehr, Geoffrey G., 5,590,413, Cl. 455-86.000.
- Kovalchin, John P., Ser. Hargis, I. Glen, Kovalchin, John P., Sharma, Satish C., Weinert, Raymond J., and Wilson, John A., 5,589,532, Cl. 524-432.000.
- Kovasin, Kari, Ser. Tikka, Panu, and Kovasin, Kari, 5,589,033, Cl. 162-84.000.
- Koves, William J., Ser. Zinke, Randy J., and Koves, William J., 5,589,139, Cl. 422-144.000.
- Kowalski, Thaddeus J., Ser. Goodnow, James E., II, Kowalski, Thaddeus J., and Rowland, James R., 5,590,329, Cl. 395-708.000.
- Koyama, Mitsutoshi, Ser. Miyashita, Naoto, Takahashi, Koichi, Koyama, Mitsutoshi, Nunotani, Shunji, Yamagata, Satoshi, and Baba, Yoshiro, 5,589,421, Cl. 437-225.000.
- Koyanagi, Hideki, Ser. Takahashi, Susumu, Uehara, Masao, Kato, Shingo, Kidawara, Atsushi, Saito, Katsuyuki, Goto, Masahito, Ohno, Wataru, Kanamori, Iwao, Hamazawa, Toyoharu, Yoshino, Kenji, Nakada, Akio, Taguchi, Akihiro, Akai, Nobuaki, Karasawa, Hiroshi, Hashiguchi, Toshihiko, Mochida, Akihiko, Fukaya, Takashi, Yamashita, Shinji, Murata, Akira, Koyanagi, Hideki, and Saito, Ken-uke, 5,588,948, Cl. 600-111.000.
- Koyano, Shinji, Kogure, Koushiro, Ohya, Takashi, Sakakibara, Makoto, and Hanayama, Katsutoshi, to Pioneer Electronic Corporation. Speaker system. 5,590,208, Cl. 381-154.000.
- Koyo Seiko Co., Ltd., Ser. Nakata, Ryuji, and Komiyama, Hiroshi, 5,588,751, Cl. 384-463.000.
- Kozuki, Susumu, Harigaya, Isao, and Hori, Taizou, to Canon Kabushiki Kaisha. Apparatus for recording digital still image signals and analog still image signals in respective recording areas. 5,589,943, Cl. 386-121.000.
- Kraan, John D., Ser. Valpey, Richard S., III, Yokoyama, Thomas W., Kraan, John D., and Harwood, H. James, 5,589,560, Cl. 526-271.000.
- Kraenzler, Erik J., Ser. Insler, Steven R., and Kraenzler, Erik J., 5,588,424, Cl. 128-207.150.
- Krahn, Donald R., to Honeywell Inc. Position detection apparatus including a circuit for receiving a plurality of output signal values and fitting the output signal values to a curve. 5,589,769, Cl. 324-207.260.
- Krahn, Wolfgang, Ernst, Johannes, and Drabant, Claudia, to Hoechst Aktiengesellschaft. Densely sintered, tubular ceramic parts of aluminum oxide having improved thermal shock resistance. 5,589,430, Cl. 501-120.000.
- Krajewski, Marjan, Jr., Chipchak, John C., Chodorow, David A., Trostle, Jonathan T., and Baldwin, Peter T., to Mitre Corporation. The Electronic information network user authentication and authorization system. 5,590,199, Cl. 380-25.000.
- Kramer, David M., Ser. Zhang, Weiguo, Kramer, David M., and Goldhaber, David M., 5,589,774, Cl. 324-309.000.
- Krass, Norbert, Ser. DeJossia, Elisabeth, Fischer, Gerd, Gerlach, Uwe, Hörlein, Rolf, Krass, Norbert, Lattrell, Rudolf, Stache, Ulrich, and Wollmann, Theodor, 5,589,594, Cl. 540-228.000.
- Kraus, James E., Ser. Houmand, Mitchell J., and Kraus, James E., 5,588,818, Cl. 418-5.000.
- Krause, Jeffrey, Strohl, Niles E., Scaman, Michael J., Russell, Steven P., and Hart, John H., to 3Com Corporation. Network station with multiple network addresses. 5,590,285, Cl. 395-200.200.
- Krause, Manfred, Kaufmann, Norbert, and Neumann, Mathias, to Boehringer Mannheim GmbH. Use of test strips to determine the UV intensity or to pre-determine the duration of stay in the sun without sunburn. 5,589,398, Cl. 436-164.000.
- Kreibbers, Enno, Ser. De Clercq, Ann, Kreibbers, Enno, Vandekerckhove, Joël, Barreto De Castro, Luiz, Gander, Eugen, and Van Montagu, Marc, 5,589,615, Cl. 800-205.000.
- Krein, William T., Flaig, Charles M., and Kelly, James D., to Apple Computer, Inc. Bus protocol using separate clocks for arbitration and data transfer. 5,590,130, Cl. 370-462.000.
- Kreitmeier, Franz, to ABB Management AG. Diffuser for a turbo-machine with outwardly curved guided plate. 5,588,799, Cl. 415-211.200.
- Kreuter, Peter, and Heuser, Peter, to Meta Motoren- und Energie-Technik GmbH. Method for controlling an internal combustion engine with external ignition system and with a fuel injection system. 5,588,411, Cl. 123-418.000.
- Krichever, Mark J., Ser. Swartz, Jerome, Shepard, Howard M., Krichever, Mark J., Metlitsky, Boris, and Barkan, Edward, 5,589,680, Cl. 235-472.000.
- Kridl, Jean C., Bruening, George, and Knauf, Vic C., to Calgene, Inc. Geminivirus-based gene expression system. 5,589,379, Cl. 435-240.400.
- Kripakaran, Raghavan, Ser. Hogan, Steven J., Feltz, Kristi T., Murdock, Douglas R., Goodman, Todd A., Vercande, David J., Tangeman, Michael R., Busch, Eric M., Kripakaran, Raghavan, Jayasimha, Madhigubba G., Smith, Keith E., Austin, Mark A., and Berry, Dana B., 5,590,181, Cl. 379-114.000.
- Krishnamurthy, Bala, Ser. Daly, John J., Haisch, Herman E., Kapsales, Peter, Krishnamurthy, Bala, Miska, Richard A., Nordgaard, Joseph K., and Walker, Carl E., 5,590,405, Cl. 455-54.100.
- Kristensson, Ronny, Ser. Järvenkylä, Jyri, Scharwächter, Dieter, Johansson, Åke, and Kristensson, Ronny, 5,589,127, Cl. 264-280.000.
- Kristensen, Inge B., Ser. Castor, Patrick F., Tsau, Yung-Chun, Kristensen, Inge B., and Nelson, John W., 5,590,288, Cl. 395-200.030.
- Krotz-Vogel, Werner, Ser. Scharstein, Hans, Krotz-Vogel, Werner, and Scharstein, Daniel, 5,590,093, Cl. 368-15.000.
- Krounhi, Mohamad T., Lee, Hin P. E., and Seagle, David J., to International Business Machines Corporation. Lapping process for a single element magnetoresistive head. 5,588,199, Cl. 29-603.100.
- Krstenansky, John L., Nestor, John J., Jr., Ho, Teresa H., Vickery, Brian H., and Bach, Chinh T., to Syntex (U.S.A.) Inc. Analogs of parathyroid hormone and parathyroid hormone related peptide: synthesis and use for the treatment of osteoporosis. 5,589,452, Cl. 514-12.000.
- Krueger International, Ser. Seidl, Lon D., and Funk, David R., 5,588,376, Cl. 108-106.000.
- Krüger, Bernd-Wieland, Ser. Fischer, Reiner, Krüger, Bernd-Wieland, Bretschneider, Thomas, Erdelen, Christoph, Wachendorff-Neumann, Ulrike, Lürssen, Klaus, Santel, Hans-Joachim, and Schmidt, Robert R., 5,589,469, Cl. 514-91.000.
- Kruse, Gary E., Ser. Shagott, David M., Kruse, Gary E., Harber, Blair L., Jr., Sutherland, Daniel N., and Travis, Terrell F., 5,588,985, Cl. 95-25.000.
- Kruse, John M., Collins, John E., and Sisley, Elizabeth M., to Minnesota Mining & Manufacturing Company. Resource assignment system providing mixed-initiative user interface updates. 5,590,269, Cl. 395-209.000.
- Kruzel, Chris, Ser. Lin, Paul M., Chang, Shen-Youn, and Kruzel, Chris, 5,589,468, Cl. 514-52.000.
- Kryger, Bernard, Ser. Decoux, Guy M., Gosset, Dominique, and Kryger, Bernard, 5,590,393, Cl. 428-552.000.
- Krystek, Edeltraud, Ser. Heckl, Konrad, Spevak, Walter, Ostermann, Elinborg, Zipfel, Andreas, Krystek, Edeltraud, Maurer-Fog, Ingrid, Wiche-Castanon, Maria J., Stratowa, Christian, and Hauptmann, Rudolf, 5,589,371, Cl. 435-189.000.
- Krzyzanowski, Paul, Ser. Asthana, Abhaya, Cravatts, Mark R., and Krzyzanowski, Paul, 5,590,370, Cl. 395-800.000.
- Kubo, Suehiro, Ser. Mizuno, Hiroyuki, Okamoto, Akio, and Kubo, Suehiro, 5,588,409, Cl. 123-339.110.
- Kubo, Takahiro, Suda, Masashi, Murasawa, Yoshihiro, Hasegawa, Takashi, Tamura, Satoshi, Fukushima, Hisashi, and Menjo, Takeshi, to Canon Kabushiki Kaisha. Image forming apparatus in which plural transfer media are carried concurrently. 5,589,920, Cl. 399-145.000.
- Kubo, Toyohide, to Awa Engineering Co., Ltd. Optical disk and apparatus for manufacturing the same. 5,590,115, Cl. 369-290.000.
- Kubogata, Masayuki, to NEC Corporation. Magneto-optical recording medium. 5,589,282, Cl. 428-694.0ML.
- Kubota, Hidemi, Ser. Ujita, Toshihiko, Yamakawa, Koji, Takenouchi, Masanori, Sugama, Sadaaki, Watanabe, Kenjiro, Osada, Torachika, Nakajima, Kazuhiro, Tsurumi, Takayoshi, Kubota, Hidemi, Kotaki, Yasuo, Tsukuda, Kei-ichiro, and Sato, Yohei, 5,589,862, Cl. 347-87.000.
- Kubota, Yasuhiko, Ser. Uno, Toshiyuki, and Kubota, Yasuhiko, 5,588,602, Cl. 242-35.50A.
- Kuboyama, Katsunori, Ser. Uchida, Naoshi, Miura, Masao, Oyama, Jun, Kuboyama, Katsunori, and Asakawa, Koji, 5,589,672, Cl. 218-34.000.
- Kuchinski, David C., Ser.

- Barker, Thomas N.; Collins, Chive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R., and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Kuckes, Arthur F., to Vector Magnetics, Inc. Rotating magnet for distance and direction measurements from a first borehole to a second borehole. 5,589,775, Cl. 324-346.000.
- Kudo, Takeshi: See—
- Kimura, Mitsuteru, and Kudo, Takeshi, 5,589,688, Cl. 250-338.400.
- Kugai, Hirokazu, to Sumitomo Electric Industries, Ltd. Non-destructive eddy current sensor having a squid magnetic sensor and selectively positionable magnets. 5,589,772, Cl. 324-240.000.
- Kugai, Hirokazu: See—
- Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu, 5,589,281, Cl. 428-688.000.
- Kugimiya, Koichi: See—
- Hiramoto, Masayoshi; Inoue, Osamu; Kugimiya, Koichi; and Iijima, Kenji, 5,589,221, Cl. 427-130.000.
- Kunigita, Masaya: See—
- Kato, Naoki; and Kunigita, Masaya, 5,589,406, Cl. 437-21.000.
- Kunihira, Tadashi: See—
- Yanagawa, Yoshifumi; and Kunihira, Tadashi, 5,590,007, Cl. 360-109.000.
- Kunimune, Kouichi: See—
- Katou, Kouichi; Watanabe, Eiji; and Kunimune, Kouichi, 5,589,319, Cl. 430-288.100.
- Kuniyoshi, Yasuo: See—
- Iida, Hirotsada; Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, 5,589,315, Cl. 430-163.000.
- Kunkle, Herman M., Jr.: See—
- Robertson, Stella M.; and Kunkle, Herman M., Jr., 5,589,184, Cl. 424-427.000.
- Robertson, Stella M.; and Kunkle, Herman M., Jr., 5,589,185, Cl. 424-427.000.
- Kuno, Koichi; and Suga, Shuzo, to Fuji Photo Film Co., Ltd. Silver halide photographic material. 5,589,325, Cl. 430-576.000.
- Kuno, Tokiyuki: See—
- Takada, Yukinori; Kuno, Tokiyuki; Muto, Yasuo; and Asai, Koichi, 5,588,614, Cl. 242-538.200.
- Kuo, Cheng M. L. Securing runner of an umbrella. 5,588,455, Cl. 135-28.000.
- Kurahashi, Akira; Ando, Hiroshi; Kaneiwa, Toshiyuki; and Hoashi, Yoshiaki, to Nippondenso Co., Ltd. Optical radar apparatus. 5,589,930, Cl. 356-5.010.
- Kurebayashi, Hidenori: See—
- Nihei, Ryo; Terada, Akihiro; and Kurebayashi, Hidenori, 5,588,328, Cl. 74-409.000.
- Kurihara, Masayuki: See—
- Ueda, Koshi; Goishi, Akira; and Kurihara, Masayuki, 5,589,780, Cl. 324-751.000.
- Kurihara, Katsumi, to Ryobi Limited. Engine unit. 5,588,408, Cl. 123-196.00W.
- Kurihara, Kenzo: See—
- Murata, Tomohiro; Kurihara, Kenzo; Kawashima, Kazuhiro, and Niida, Mitsuaki, 5,590,272, Cl. 395-181.000.
- Kuroda, Shin-ichi: See—
- Hiraishi, Masahiro; and Kuroda, Shin-ichi, 5,588,292, Cl. 60-300.000.
- Kuroiwa, Hiroshi: See—
- Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155.000.
- Kurosu, Yasuo: See—
- Iguchi, Hiroaki; Kurosu, Yasuo; Fujinawa, Masaaki; Yokoyama, Yoshihiro; and Masuzaki, Hidefumi, 5,590,317, Cl. 395-602.000.
- Kurz, Hans-Joachim, to Baldwin Gegenheimer GmbH. Temperature-control device for rotating bodies in printing mechanisms. 5,588,360, Cl. 101-212.000.
- Kusaka, Yosuke, to Nikon Corporation. Automatic focus adjustment camera with high speed sequential photography capability, and method of automatic focus adjustment therefor. 5,589,909, Cl. 396-96.000.
- Kushihi, Yuichi: See—
- Kawahata, Kazunari; and Kushihi, Yuichi, 5,588,198, Cl. 29-600.000.
- Kusmer, Raymond J., to Thomas Industries, Inc. Modular recessed lighting system. 5,588,737, Cl. 362-148.000.
- Kustermann, Martin; Gottwald, Ingo; and Ueberschar, Manfred, to J.M. Voith GmbH. Control over excess coating composition in coating device for traveling paper web. 5,589,659, Cl. 118-413.000.
- Kuszmaul, Bradley C.: See—
- Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmaul, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200.020.
- Kuwahara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Teruaki; Takahashi, Koji; Harada, Tamotsu; Komiyama, Takeshi; Hirai, Fumio; and Hayashi, Masamichi, to Honda Giken Kogyo Kabushiki Kaisha. Molded ceramic articles and production method thereof. 5,590,388, Cl. 419-39.000.
- Kuwahara, Tetsuo: See—
- Shiraishi, Akihiko; Fujibayashi, Kazuo; and Kuwahara, Tetsuo, 5,589,882, Cl. 348-340.000.
- Kuwahara, Eiji. Method of manufacturing emblem of thermoplastic synthetic resin sheet. 5,589,022, Cl. 156-231.000.
- Kuwahara, Kenji: See—
- Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.
- Kuwana, Minoru: See—
- Yoshida, Ryuichi; Okamoto, Yasuhiro; and Kuwana, Minoru, 5,589,723, Cl. 310-328.000.
- Kval Marketing Inc.: See—
- Larsen, Peter, deceased; and Pedersen, Henrik S., executor, 5,589,207, Cl. 426-20.000.
- Kwock, Elizabeth W.; and Miller, Timothy M., to Lucent Technologies Inc. Photodegradable dielectric layers comprising poly(aromatic diacetylenes). 5,589,424, Cl. 437-229.000.
- Kyodo Yushi Co., Ltd.: See—
- Hatakeyama, Ko, 5,589,444, Cl. 508-168.000.
- Kyoto Daiichi Kagaku Co., Ltd.: See—
- Hyodo, Hiroshi, 5,589,045, Cl. 204-406.000.
- Kyowa Denki Kogyo Kabushiki Kaisha: See—
- Hashimoto, Seishiro, 5,588,312, Cl. 66-75.200.
- Kyowa Hakko Kogyo Co., Ltd.: See—
- Koizumi, Satoshi; Yonetani, Yoshiyuki; and Teshiba, Sadao, 5,589,355, Cl. 435-66.000.
- Kyoyu Corporation: See—
- Nakao, Masashi, 5,588,739, Cl. 362-205.000.
- L.A. Gear, Inc.: See—
- Goldston, Mark R.; Bemis, Jon L.; Wickemeyer, Daniel M.; and Potter, David, 5,588,227, Cl. 36-93.000.
- L. & C. Steinmüller GmbH: See—
- Stefan, Ion; and Cesnik, Friedrich, 5,588,400, Cl. 122-406.100.
- L&P Property Management Company: See—
- Wiecek, Glenn N., 5,588,710, Cl. 297-463.100.
- Laak, Rein. Wastewater treatment system. 5,588,777, Cl. 405-40.000.
- Lab-Interlink, Inc.: See—
- Markin, Rodney S.; and Newcomb, Michael R., 5,589,137, Cl. 422-104.000.
- Laboratorios Cusi, S.A.: See—
- Vallet Mas, Alberto; and Gimenez Guasch, Francesc X., 5,588,559, Cl. 222-92.000.
- Lacout, Franck: See—
- de Laforade, Vincent; and Lacout, Franck, 5,588,566, Cl. 222-402.110.
- Laczynski, Andrew J.: See—
- Juchymenko, Victor Y.; Howard, J. Richard; Laczynski, Andrew J.; and Angus, James S., 5,588,235, Cl. 40-547.000.
- Lahn, Bruce: See—
- Han, Quansheng; and Lahn, Bruce, 5,589,721, Cl. 310-90.500.
- Lai, Danny S., to Gramercy Enterprises (U.S.A.) Corp. Jewelry with changeable ornamentation. 5,588,310, Cl. 63-15.000.
- Lai, Shih-Yaw; Hazlitt, Lonnie G.; and Chum, Pak-Wing S., to Dow Chemical Company, The. Performance super high flow ethylene polymer compositions. 5,589,128, Cl. 264-328.100.
- Lai, Yu-Shan. Ascending/descending structure. 5,588,766, Cl. 403-105.000.
- Laidig, Inc.: See—
- Laidig, Jon; Updike, Dale; and Amick, Alan, 5,588,521, Cl. 198-532.000.
- Laidig, Jon; Updike, Dale; and Amick, Alan, to Laidig, Inc. Method and apparatus for material handling. 5,588,521, Cl. 198-532.000.
- L'Air Liquide Societe Anonyme Pour L'Etude et L'Exploitation des Procédes Georges Claude: See—
- Gary, Daniel, 5,589,151, Cl. 423-351.000.
- Lakdawala, Aftab D.: See—
- Naik, Ramachandra G.; Mumhaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansil; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.
- Lakey, Leland D.: See—
- Alexander, Albert H. D.; Ballatine, W. Thomas; Lakey, Leland D.; and Lyon, Frank L., 5,589,603, Cl. 588-250.000.
- Lal, Bansil: See—
- Naik, Ramachandra G.; Mumhaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansil; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.
- Lallier, Guy. Cornerbead crimping tool. 5,588,320, Cl. 72-325.000.
- Lalouel, Jean-Marc; Jeunemaitre, Xavier; Lifton, Richard P.; Soubner, Florent; Kotelevtsev, Youri; and Corvol, Pierre, to University of Utah Research Foundation. Angiotensinogen gene variants and predisposition to hypertension. 5,589,584, Cl. 536-24.310.
- LAM Research Corporation: See—
- Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrap, Robert, 5,589,737, Cl. 315-111.210.
- Lambert, Richard C.: See—
- Ford, George W., Jr.; Lambert, Richard C.; and Madsen, Russell G., 5,589,118, Cl. 264-122.000.
- Lamping, John O.; and Rao, Ramana B., to Xerox Corporation. Layout of node-link structures in space with negative curvature. 5,590,250, Cl. 395-127.000.
- Landis, Timothy J.; and Perry, Scott M., to OP-D-OP, Inc. Mouth prop and tongue deflector apparatus. 5,588,836, Cl. 433-93.000.
- Lang Apparatebau GmbH: See—

- Klein, Joachim; and Hunklinger, Herbert, 5,588,809, Cl. 417-283.000.
- Lang, David J.: See—
- Delwel, Francois; and Lang, David J., 5,589,267, Cl. 428-407.000.
- Ratuiste, Florencio; Ahart, Robert; Lang, David J.; and Tsaui, Liang S., 5,589,370, Cl. 264-4.300.
- Lang, John. Golf range game. 5,588,652, Cl. 473-168.000.
- Lange, Fredric. Modular structural framing system. 5,588,274, Cl. 52-653.100.
- Lange International S.A.: See—
- Marmonier, Gilles, 5,588,229, Cl. 36-118.900.
- Lange, Robert. Remote status indicator for holding tanks containing no moving parts. 5,589,823, Cl. 340-622.000.
- Lansley, Gordon: See—
- Marchand, Claudine; Drulhe, Pierre; Pujalon-Mercereau, Odile; and Langsley, Gordon, 5,589,343, Cl. 435-7.220.
- Lanotte, Michel; and Berger, Roland, to Institut National de la Sante et de la Recherche Medicale. Cultures of permanent lines of human promyelocytic cells and their uses for the screening of molecules utilizable in particular in the treatment of leukemias. 5,589,345, Cl. 435-7.230.
- Lantech, Inc.: See—
- Lerner, Ruth; and Fain, John, 5,588,287, Cl. 53-588.000.
- Lantsman, Alexander D., to Sony Corporation; and Materials Research Corp. Plasma sputter etching system with reduced particle contamination. 5,589,041, Cl. 204-192.330.
- Lapis, Erzsebet: See—
- Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpomy, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Larnicol, Pierre: See—
- Ledon, Henry; Larnicol, Pierre; Desmurs, Marie-Jeanne; and Dupont, Michel, 5,589,590, Cl. 536-127.000.
- LaRose, Jeffrey A., to Babcock & Wilcox Company, The. Diffuser for coal nozzle burner. 5,588,380, Cl. 110-263.000.
- Larsen, Alf D.: See—
- Smith, Craig A.; Larsen, Alf D.; Sims, John E.; and Curtis, Benson M., 5,589,456, Cl. 514-12.000.
- Larsen, Peter, deceased; and Pedersen, Henrik S., executor, to Kval Marketing Inc. Method of producing a frozen yeast dough product. 5,589,207, Cl. 426-20.000.
- Larson, Diana A. Angel action figure doll. 5,588,895, Cl. 446-98.000.
- Larsson, Stefan; and Tennstedt, Christer. Thermoelectric refrigeration system with flexible heatconducting element. 5,588,300, Cl. 62-3.610.
- Larue, Roderick W.: See—
- Kim, Young R.; Iles, Kenneth E.; and Larue, Roderick W., 5,589,394, Cl. 436-63.000.
- Lashmet, Brent J.; Lashmet, Doug C.; Lashmet, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Meredith L., to B&S Research, Inc. Method for remediating contaminated material. 5,589,004, Cl. 134-10.000.
- Lashmet, Doug C.: See—
- Lashmet, Brent J.; Lashmet, Doug C.; Lashmet, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Meredith L., 5,589,004, Cl. 134-10.000.
- Lashmet, H. W.: See—
- Lashmet, Brent J.; Lashmet, Doug C.; Lashmet, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Meredith L., 5,589,004, Cl. 134-10.000.
- Laszy, Judit: See—
- Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpomy, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Latham, Ian A.: See—
- Archer, Colin M.; Dilworth, Jonathan R.; Johanputra, Panna; Latham, Ian A.; and Thompson, Russell M., 5,589,576, Cl. 534-14.000.
- Lattrell, Rudolf: See—
- Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228.000.
- Latva-Aho, Matti, to Nokia Mobile Phones Ltd. Method and arrangement for controlling a loop filter. 5,589,795, Cl. 327-553.000.
- Lau, Jesper; and Knutsen, Lars J. S., to Novo Nordisk A/S. 2,5'-N6-trisubstituted adenosine derivatives. 5,589,467, Cl. 514-46.000.
- Lau, Louis C.: See—
- Gibbons, Kevin P.; Lau, Louis C.; and Woodard, Floyd E., 5,589,280, Cl. 428-626.000.
- Lau, Sai-Kwing: See—
- Divakar, Ramesh; and Lau, Sai-Kwing, 5,589,428, Cl. 501-88.000.
- Lauderbaugh, David M., to Corrugated Gear & Services, Inc. Method and device for spacing a corrugating finger relative to a corrugating roll. 5,588,945, Cl. 493-480.000.
- Laughton, Charles A.: See—
- Edwards, Karen J.; Jarman, Michael; Laughton, Charles A.; Neidle, Stephen; and Hardcastle, Ian R., 5,589,500, Cl. 514-428.000.
- Laun, Ulrich, to Autoliv Development AB. Safety belt blocking device with self-blocking prevention. 5,588,612, Cl. 242-383.100.
- Laurenson, Patricia: See—
- Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurenson, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.
- Lautzenheiser, Marvin, to Zitel Corporation. Cache memory utilizing address translation table. 5,590,300, Cl. 395-412.000.
- Law, Kam; Robertson, Robert; and Feng, Guofu J., to Applied Materials, Inc. Single chamber CVD process for thin film transistors. 5,589,233, Cl. 427-579.000.
- Law, Ronald L.; Roy, Apurba; and Shewmake, Steven A., to Lucent Technologies Inc. Low inductance surface-mount connectors for interconnecting circuit devices and method for using same. 5,588,848, Cl. 439-83.000.
- Lawrence, Thomas G., to Chrysler Corporation. Control device for exhaust timing of a two cycle engine using intake system pressure. 5,588,402, Cl. 123-65.0PE.
- Lawrie, Christophe J.: See—
- Gee, Jeffrey C.; Lawrie, Christophe J.; and Williamson, Roger C., 5,589,442, Cl. 507-103.000.
- Lax, Ronald G.: See—
- Edwards, Stuart D.; Lax, Ronald G.; and Sharkey, Hugh R., 5,588,960, Cl. 604-20.000.
- Leadbeater, Darren J.; Kato, Heiji; and Fukase, Hisahiko, to Ishikawajima-Harima Heavy Industries Company Limited; and BHP Steel (JLA) Pty Ltd. Strip casting. 5,588,479, Cl. 164-480.000.
- Leader Electronics Corporation: See—
- Ikezawa, Kenzo; and Hika, Yoshimichi, 5,589,877, Cl. 348-186.000.
- Leahy, Richard; and Cook, Stephen J., to BP Chemicals (Additives) Limited. Overbased metal salts, their preparation and use. 5,589,445, Cl. 508-381.000.
- Leamy, Alan: See—
- Leamy, Patrick; Leamy, Alan; and Gillin, John, 5,590,245, Cl. 395-118.000.
- Leamy, Patrick; Leamy, Alan; and Gillin, John, to Offset Studios Limited. Method for transmitting image processing jobs from a client system, and routing and performing the jobs in an image processing system. 5,590,245, Cl. 395-118.000.
- Learnmont, Robert O.: See—
- Pruhs, Allen V.; Robinson, Darrell; and Learnmont, Robert O., 5,588,874, Cl. 439-517.000.
- Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruhs, Allen V.; and Learnmont, Robert O., 5,590,179, Cl. 379-107.000.
- Leary, H. Lee, Jr.: See—
- Martinez, Sarah B.; Leary, H. Lee, Jr.; and Nichols, Debra J., 5,589,357, Cl. 435-68.100.
- Lebkowski, Jane S.; McNally, Maureen A.; and Okarma, Thomas B., to Rhône-Poulenc Rorer Pharmaceuticals, Inc. Recombinant adeno-associated virus vectors. 5,589,377, Cl. 435-240.200.
- le Blanc, Pieter W. J. C.: See—
- Taylor, Lynn P.; le Blanc, Pieter W. J. C.; Butler, Kenneth C.; and Maher, Timothy R., 5,588,812, Cl. 417-356.000.
- Le Deit, Gerard, to AlliedSignal Europe Services Technique. Disk brake using a pulled pad with permanent bearing. 5,588,508, Cl. 188-73.310.
- Lederman, Frederick E., to General Motors Corporation. Method of manufacturing a unitized seal. 5,588,210, Cl. 29-898.000.
- Ledon, Henry; Larnicol, Pierre; Desmurs, Marie-Jeanne; and Dupont, Michel, to Chemoxal. Process for the preparation of cyclodextrins or other compounds capable of producing clathrates with a gas. 5,589,590, Cl. 536-127.000.
- Leduc, Steven. Sterilization system. 5,588,623, Cl. 248-164.000.
- Lee, Anthony. Traveller's voltage converter for automatically selecting load wattage. 5,589,760, Cl. 323-247.000.
- Lee, Chin H.: See—
- Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stollenberg, Blaise G., 5,590,209, Cl. 381-168.000.
- Lee, Chinmei C.: See—
- Agarwal, Anjana; and Lee, Chinmei C., 5,590,176, Cl. 379-59.000.
- Lee, Chul J.: See—
- Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., 5,589,264, Cl. 428-359.000.
- Lee, David K.; and Riley, David W., to Pitney Bowes Inc. Open metering system with super password vault access. 5,590,198, Cl. 380-21.000.
- Lee, Dong M., to Hyundai Electronics Industries Co., Ltd. Semiconductor memory device. 5,590,077, Cl. 365-189.050.
- Lee, Don-Seon; and Kim, Seong-Woo, to SamSung Electronics Co., Ltd. Power saving method of an image forming apparatus. 5,589,923, Cl. 399-28.000.
- Lee, Eng-Hong. Drinking tray for small animals shipped in containers. 5,588,395, Cl. 119-72.000.
- Lee, Graham S. Meter for measuring accumulated power consumption of an electrical appliance during operation of the appliance. 5,589,764, Cl. 324-157.000.
- Lee, Hee-Soo, to Samsung Electronics Co., Ltd. Device for reproducing 2-channel sound field and method therefor. 5,590,204, Cl. 381-24.000.
- Lee, Hin P. E.: See—
- Krounbi, Mohamad T.; Lee, Hin P. E.; and Seagle, David J., 5,588,199, Cl. 29-603.100.
- Lee, Ho-Cheol: See—
- Park, Churoo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230.030.

- Lee, Hong J.: See—
Kim, Sang K.; Oh, PahngRoc; and Lee, Hong J., 5,588,717, Cl. 303-84.200.
- Lee, Howard H.: See—
Sokol, Gerald E.; Lee, Howard H.; and Kibbel, Bradley W., 5,588,477, Cl. 164-34.000.
- Lee, Jae-Hyeong; and Seok, Yong-sik, to Samsung Electronics Co., Ltd. Wafer burn in test circuit of a semiconductor memory device, 5,590,079, Cl. 365-201.000.
- Lee, Joseph Y.: See—
Degen, Peter J.; and Lee, Joseph Y., 5,589,302, Cl. 429-250.000.
- Lee, Kun-Jai; and Park, Jong-Kil, to Korea Advanced Institute of Science and Technology. Anion-exchange membrane extractor for boric acid separation, 5,589,071, Cl. 210-638.000.
- Lee, Noel, to Monster Cable International, Ltd. Power line conditioner, 5,589,718, Cl. 307-72.000.
- Lee, Sang-in; and Park, Chang-soo, to Samsung Electronics Co., Ltd. Semiconductor device having an improved wiring layer, 5,589,713, Cl. 257-773.000.
- Lee, Seung-Hun: See—
Park, Churoo; Jang, Hyun-Soon; Kim, Chull-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230.030.
- Lee, Shang-Ming. Cabinet wall board assembly, 5,588,726, Cl. 312-263.000.
- Lee, Si-Yeol: See—
Park, Churoo; Jang, Hyun-Soon; Kim, Chull-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230.030.
- Lee, Sooshee; and Redman, Colvin, to New York Blood Center. Diagnostic method and kit for determining Kell blood group genotype, 5,589,336, Cl. 435-6.000.
- Lees, Eric R.: See—
Jin, Iljeon; Lloyd, David J.; Timsit, Roland S.; and Lees, Eric R., 5,588,478, Cl. 164-480.000.
- Lehnmann, Volker; Mann, Heiner; and Reiber, Ingolf, to Siemens Aktiengesellschaft. Electric high-tension circuit breaker, 5,589,673, Cl. 218-66.000.
- Leica AG: See—
Graefenhain, Paul, 5,588,769, Cl. 403-322.000.
- Leigh, Kevin B.: See—
Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,590,292, Cl. 395-825.000.
- Leiserson, Charles E.: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmil, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong, Chan, Monica C., 5,590,283, Cl. 395-200.020.
- Le-Khac, Bi, to ARCO Chemical Technology, L.P. Double metal cyanide complex catalysts, 5,589,431, Cl. 502-175.000.
- Leland Stanford Junior University. The Board of Trustees of the: See—
Mami, Sanjay; Nishimura, Dwight G.; Conolly, Steven M.; and Pauly, John M., 5,588,431, Cl. 128-653.300.
- Lemcke, Ulrich: See—
Lücke, Christian; Vry, Uwe; and Lemcke, Ulrich, 5,589,977, Cl. 359-375.000.
- Lemieux, Christine: See—
Firoozabady, Ebrahim; Lemieux, Christine; Moll, Benjamin A.; and Robinson, Karol, 5,589,613, Cl. 800-205.000.
- Lemp, Steven K.; Hudak, Philip J.; and Love, Charles S., to Autogenics, Inc. Tissue cutting die, 5,588,967, Cl. 606-167.000.
- Lengyel, József: See—
Magyar, Kálmán; Gaál, József; Sziráki, István; Lengyel, József; Szabó, Anna Z.; Mármárosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter, 5,589,513, Cl. 514-654.000.
- Lenoble, Bertrand L. J.: See—
Kolaitis, Leonidas; Lenoble, Bertrand L. J.; and Prince, Mark A., 5,589,449, Cl. 510-466.000.
- Lenzing Aktiengesellschaft: See—
Zakeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruff, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Leonard, Timothy J.; and Kottke, Kurt E., to Morton International, Inc. Cover attachment for an air bag module, 5,588,669, Cl. 280-728.300.
- Leonard, William K.; Mody, Kirit C.; and Rolando, Richard J., to Minnesota Mining And Manufacturing Company. Method of making double-sided pressure-sensitive adhesive tape, 5,589,122, Cl. 264-146.000.
- Leone, James E.; and Rowland, Stephen M., to Cordis Corporation. Electro-osmotic infusion catheter, 5,588,961, Cl. 604-21.000.
- Leparc, German: See—
García Rubio, Luis H.; Bayona, Manuel; Potter, Robert; and Leparc, German, 5,589,932, Cl. 356-39.000.
- Leppert, Hans-Detlef: See—
Lysson, Hans-Jürgen; Broden, Reiner; and Leppert, Hans-Detlef, 5,588,997, Cl. 118-405.000.
- Lerch, Hansueli: See—
Schneider, Werner; Lerch, Hansueli; and Hausmann, Erich, 5,588,938, Cl. 482-4.000.
- Lerner, Ruth; and Fan, John, to Lantech, Inc. Wrapping apparatus with barrier, 5,588,287, Cl. 53-588.000.
- Le Roux, Jean-Yves, to Gemplus Card International. Method to secure the operations for accessing detachable cards for computers, 5,590,193, Cl. 380-4.000.
- Leroux, Roland: See—
Busch, Dietrich; and Leroux, Roland, 5,588,421, Cl. 126-200.000.
- Leslie Technologies, Inc.: See—
Jennebach, Markus; and Birkhan, Joao A., 5,588,381, Cl. 110-345.000.
- Lesmeister, Donald M.: See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Reiter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Lester, Lester J.; and Van Trump, Gary N., to ITT Corporation. Connector system with wedge and grommet retainer, 5,588,858, Cl. 439-275.000.
- Leung, Ting Y.; Pirahesh, Mir H.; Jou, Michelle M.; and Simmen, David E., to International Business Machines Corporation. Optimization of SQL queries using universal quantifiers, set intersection, and max/min aggregation in the presence of nullable columns, 5,590,324, Cl. 395-605.000.
- Lever Brothers Company, Division of: See—
Delwel, Francois; and Lang, David J., 5,589,267, Cl. 428-407.000.
- Ratuiste, Florencio; Ahart, Robert; Lang, David J.; and Tsaui, Liang S., 5,589,370, Cl. 264-4.300.
- Levin, Jeffrey A., to Qualcomm Incorporated. Method and apparatus for providing ROM in an integrated circuit having update through single substance layer modification capability, 5,590,069, Cl. 365-96.000.
- Levine, Barry E., to Lucent Technologies Inc. Article comprising a Si-based photodetector, 5,589,704, Cl. 257-436.000.
- Levine, Jules D.; Shen, Chi-Cheng; and Taylor, Robert, to Texas Instruments Incorporated. Field emission device with lattice vacancy post-supported gate, 5,589,728, Cl. 313-336.000.
- Levine, Myron M.: See—
Pasano, Alessio; Levine, Myron M.; Nataro, James P.; and Noriega, Fernando, 5,589,380, Cl. 435-252.300.
- Levinson, Lionel M.: See—
Scott, Curtis E.; Kaliszewski, Mary Sue; and Levinson, Lionel M., 5,588,992, Cl. 117-2.000.
- Levitan, Raya: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Idolo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehzekel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afeq, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.
- Levitt, Joel: See—
Terman, Michael; Fairhurst, Stephen; Hughes, Philip; and Levitt, Joel, 5,589,741, Cl. 315-360.000.
- Levy, Stuart B., to Trustees of Tufts College. Reducing tetracycline resistance in living cells, 5,589,470, Cl. 514-154.000.
- Lewallen, William J., Sr. Knockdown seat, 5,588,709, Cl. 297-440.190.
- Lewis, Alan G., to Xerox Corporation. Switched capacitor analog circuits using polysilicon thin film technology, 5,589,847, Cl. 345-98.000.
- Lewis, Brian T.; and Goldstein, Theodore C., to Sun Microsystems, Inc. Method and apparatus for generating platform-standard object files containing machine-independent code, 5,590,331, Cl. 395-708.000.
- Lewis, Donald M.: See—
Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heint, Robert V.; and Yoshida, Yuko, 5,589,247, Cl. 428-141.000.
- Lewis, Jerome M., to Advanced Magnetics, Inc. Endotoxin-free polysaccharides, 5,589,591, Cl. 536-128.000.
- Lewis, Martyn A., to Seagate Technology, Inc. Brushless motor speed control arrangement having derived common mode supply signal component, 5,589,746, Cl. 318-439.000.
- Lewis, Monica N.: See—
Roth, Joseph D.; Obringer, Thomas J.; and Lewis, Monica N., 5,589,276, Cl. 428-488.100.
- Lexmark International, Inc.: See—
Beach, Bradley L.; Feeman, James F.; Pearson, Anna M.; and Sun, Jing X., 5,589,522, Cl. 523-160.000.
- Li, Joachim: See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.
- Li, Ming-Chiang. RF signal train generator and interconnectors, 5,589,929, Cl. 356-5.010.
- Li, Wenfan; and Liu, Xiuying, to Chinese Academy of Sciences, Chang Chun Institute of Applied Chemistry of the. Room temperature carbon monoxide gas sensor and the process for preparing the same, 5,589,046, Cl. 204-424.000.
- Liao, Frank Y.; Rule, Antoinette; Frankel, Rise J.; Blickle, Thomas W.; and Bish, Sandra L., to AT & T. System and method for redirecting a telephone call with call merging, 5,590,186, Cl. 379-210.000.
- Liaw, Weikuo: See—
Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Hush, Alan M., 5,590,259, Cl. 395-764.000.
- Lichtlyer, Ralph: See—
Huford, Huford; Jonathan P.; Collier, William V.; and Boumarah, Mohamed, 5,588,671, Cl. 280-730.200.
- Lichtlyer, Ralph; Vu, Ngo Quang; Gilman, Jeffrey W.; and Feher, Frank J., to University of Dayton, The. Polymers containing alternating silsesquioxane and bridging group segments and process for their preparation, 5,589,562, Cl. 528-9.000.

- Lichti, Robert D. High speed storage system, 5,588,790, Cl. 414-331.000.
- Lichti, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydelis, Ronald A.; and Fox, Michael J., to General Motors Corporation. Variable cam phaser and method of assembly, 5,588,404, Cl. 123-90.170.
- Lieh, Joseph A. Kitchen ensemble having windows with controllable opacity, 5,589,958, Cl. 349-16.000.
- Lien, Erling L.; and Karp, Arthur, to Communications and Power Industries, Inc. Frequency multiplier including grid having plural segments, 5,589,736, Cl. 315-5.430.
- Lifton, Richard P.: See—
Lalouel, Jean-Marc; Jeunemaitre, Xavier; Lifton, Richard P.; Souhrier, Florent; Kotelevtsev, Youri; and Corvol, Pierre, 5,589,584, Cl. 536-24.310.
- Light, Ronald R.: See—
Shih, Wayne K.; and Light, Ronald R., 5,589,126, Cl. 264-211.000.
- Lilly, S.A.: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoepf, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Lim, Jun Y., to Goldstar Co., Ltd. Sensorless switched reluctance motor, 5,589,751, Cl. 318-701.000.
- Lin, Chao-Tsung. Connection device of a computer connector, 5,588,864, Cl. 439-357.000.
- Lin, Eileen T.; and Wang, Yun, to International Business Machines Corporation. Push down optimization in a distributed, multi-database system, 5,590,321, Cl. 395-610.000.
- Lin, Jerhng. Internal frame for a wheeled suitcase, 5,588,512, Cl. 190-115.000.
- Lin, Jerhng. Tilt-locking pull handle for a wheeled suitcase, 5,588,513, Cl. 190-115.000.
- Lin, Jung-Hui: See—
White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hui, 5,589,423, Cl. 437-228.000.
- Lin, Kun, to Crystal Semiconductor Corporation. Digital decimation filter for delta sigma analog-to-digital conversion with reduced hardware complexity, 5,590,065, Cl. 364-724.100.
- Lin, Lie-Der; and Ju, Juann-Ming, to Industrial Technology Research Institute. Apparatus for converting two dimensional pixel image into one-dimensional pixel array, 5,589,850, Cl. 345-132.000.
- Lin, Liwei; Nguyen, Clark T.; Howe, Roger T.; and Pisano, Albert P., to University of California, The Regents of the. Microelectromechanical signal processor fabrication, 5,589,082, Cl. 216-2.000.
- Lin, Paul M.; Chang, Shen-Youn; and Kruezel, Chris, to Clintec Nutrition Co. Method for providing nutrition to elderly patients, 5,589,468, Cl. 514-52.000.
- Lin, Tsen-Hwang; and Malcher, Falvey, to Texas Instruments Incorporated. Processing module for programmable processing using computer generated holograms, 5,590,367, Cl. 395-800.000.
- Lindblad, Lennart, to Linvent AB. Device for the setting of the mutual positions of pivotable elements, 5,588,932, Cl. 475-341.000.
- Linde Aktiengesellschaft: See—
Forster, Franz, 5,588,931, Cl. 475-338.000.
- Schmidt, Hans, 5,588,306, Cl. 62-614.000.
- Schmidt, Hans, 5,588,307, Cl. 62-614.000.
- Lindenmeier, Heinz; Hopf, Jochen; and Ritter, Leopold. Radio antenna arrangement located next to vehicle window panels, 5,589,839, Cl. 343-713.000.
- Lindner, Thomas A.; and Coel, Joseph B., to Empire Level Mfg. Co. Level vial assembly with encapsulated vial, 5,588,217, Cl. 33-379.000.
- Lindquist, David B.: See—
Baum, Richard I.; Brent, Glen A.; Gibson, Donald H.; and Lindquist, David B., 5,590,362, Cl. 395-800.000.
- Lindsey, Mark A.: See—
Carr, James E.; and Lindsey, Mark A., 5,588,338, Cl. 74-560.000.
- Lindsey, Marvin E., to DeKalb Genetics Corporation. Hybrid corn with a genetic complement producing increased yield, seedling vigor, early stand, stalk strength and low harvest moisture, 5,589,605, Cl. 800-200.000.
- Lindström, Lars-Åke: See—
Färnstrand, Per-Åke; Sjödin, Lars T.; Lindström, Lars-Åke; and Nordén, K. Solveig E., 5,589,031, Cl. 162-65.000.
- Linear Technology Corporation: See—
Nelson, Carl T.; and Essaff, Robert, 5,589,761, Cl. 323-285.000.
- Linear Technology Inc.: See—
Dohkin, Robert C.; and Reay, Robert L., 5,589,709, Cl. 257-666.000.
- Linggood, Margaret A.: See—
Allen, William D.; Linggood, Margaret A.; and Porter, Philip, 5,589,168, Cl. 424-93.400.
- Link, Helmut: See—
Gerwitz, Jürgen; Götschi, Erwin; Hebeisen, Paul; Link, Helmut; and Lübbers, Thomas, 5,589,473, Cl. 514-183.000.
- Link USA Corporation: See—
Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vereande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.
- Linnoila, Markku: See—
Nielsen, David A.; Goldman, David; Linnoila, Markku; and Virkkunen, Matti, 5,589,331, Cl. 435-6.000.
- Lino Manfredi & Co., S.p.A.: See—
Spegiorin, Paolo, 5,589,903, Cl. 396-428.000.
- Lintec Corporation: See—
Okabe, Hideaki; Suzuki, Eiji; Kogure, Masao; and Saito, Takanori, 5,589,192, Cl. 424-486.000.
- Linvent AB: See—
Lindblad, Lennart, 5,588,932, Cl. 475-341.000.
- Linz, Alfredo R.; Cabler, Carlin D.; Brown, Glen W.; and Soques, Martin P., to Advanced Micro Devices, Inc. Stereo audio codec, 5,589,830, Cl. 341-110.000.
- Lippai, Andre; Tanigami, Jorge K.; and Dellanocce, Paulo T., to Metal Leve S/A Industria E Comercio. Head for two piece articulated piston, 5,588,351, Cl. 92-208.000.
- Lippincott, Louis A.; and Craver, Thomas R., to Intel Corporation. Displaying multiple video streams using a bit map and a single frame buffer, 5,590,254, Cl. 395-135.000.
- Lipscombe, Martin J.; Charles, Ian G.; and Fairweather, Neil F., to Glaxo Wellcome Inc. Fusion proteins, 5,589,384, Cl. 435-252.330.
- Liquori, Katherine S.: See—
Stier, David E.; and Liquori, Katherine S., 5,588,587, Cl. 229-232.000.
- Lisa, Rudolph E.; Kilbride, Terence K.; and Jager, Karl-Friedrich, to BASF Corporation. Dry flowable powders of hygroscopic plant growth regulators and tablets formed of the same, 5,589,438, Cl. 504-236.000.
- Lisco, Inc.: See—
Sullivan, Michael J.; Nealon, John L.; and Nesbitt, R. Dennis, 5,588,924, Cl. 473-377.000.
- Little, Wendell L.: See—
Bolan, Michael L.; and Little, Wendell L., 5,590,343, Cl. 395-750.000.
- Liton Systems, Inc.: See—
Goldman, Robert P.; Arab-Sadeghabadi, Akbar; and Varni, Anselm F., 5,590,229, Cl. 385-59.000.
- Liton Systems (Canada) Limited: See—
Bahadur, Birendra; and Wan, Kam H., 5,589,965, Cl. 349-165.000.
- Litwin, Stanislaw. Garden rocking-chair, 5,588,702, Cl. 297-277.000.
- Liu, Chin-Ching. Quantitative dispenser, 5,588,563, Cl. 222-158.000.
- Liu, David K. Y.: See—
Haddad, Sameer S.; Chang, Chi; and Liu, David K. Y., 5,590,076, Cl. 365-185.250.
- Liu, Hsien-Tsong: See—
Wann, Yeh-Jye; and Liu, Hsien-Tsong, 5,589,414, Cl. 437-44.000.
- Liu, James J.: See—
Sekhar, Jainagesh A.; Liu, James J.; and Zhu, Naiping, 5,590,383, Cl. 419-2.000.
- Liu, Li-Hsiung, to McCulloch Corporation. Impeller for blower/vacuum, 5,588,178, Cl. 15-330.000.
- Liu, Xiuying: See—
Li, Wenfan; and Liu, Xiuying, 5,589,046, Cl. 204-424.000.
- Livernois Research & Development Company: See—
Bianchi, Sabatino A.; and Stoyoff, Richard P., 5,588,319, Cl. 72-186.000.
- Ljungström, Tommy B. G.: See—
Runnberg, Bo; and Ljungström, Tommy B. G., 5,588,279, Cl. 53-426.000.
- Lloyd, David J.: See—
Jin, Iljeon; Lloyd, David J.; Timsit, Roland S.; and Lees, Eric R., 5,588,478, Cl. 164-480.000.
- Lo, Kin-Ming: See—
Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,589,510, Cl. 514-590.000.
- Lo, William, to Advanced Micro Devices Inc. Programmable source address locking mechanism for secure networks, 5,590,201, Cl. 380-49.000.
- Lobo, Lloyd A.; and Sverika, Aileen M., to Eastman Kodak Company. Process for making a direct dispersion of a photographically useful material, 5,589,322, Cl. 430-449.000.
- Locaspi, Angelo: See—
Simeone, Giovanni; Mutta, Fabrizio; Locaspi, Angelo; and Tonelli, Claudio, 5,589,552, Cl. 525-440.000.
- Lockheed Martin Corporation: See—
Bushman, Boyd B., 5,590,014, Cl. 361-225.000.
- Lodwig, John P.; Felix, Kenneth A.; and Whittington, Charles L., to Motorola, Inc. Method and system for transferring a radiotelephone call from one coverage area to another, 5,590,172, Cl. 379-58.000.
- Loeffler, Randy J.: See—
Hunter, Wood E.; Frederick, Kevin W.; and Loeffler, Randy J., 5,589,525, Cl. 523-331.000.
- Loew, Eric: See—
Randall, Mitchell A.; and Loew, Eric, 5,589,833, Cl. 342-195.000.
- Löffler, Gerhard, to Heidelberger Druckmaschinen AG. Method of monitoring the wear on printing forms in a printing machine, 5,588,366, Cl. 101-484.000.
- Loffield, Richard E.: See—
Moran, Stephen W.; Jackson, John R.; Gallivan, Timothy J.; and Loftfield, Richard E., 5,589,053, Cl. 205-698.000.
- Logan, Robert J.: See—
Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704.000.
- Logemann, Jürgen: See—
Ulrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205.000.
- Logic Devices, Inc.: See—

- Robinson, Jeffrey L.; Rouse, Keith, and Musicus, Bruce R., 5,590,349, Cl. 395-800.000.
- Logical Information Machines, Inc.: See—
- Kolton, Anthony D.; Gamboa, Ruben A., and Chimentu, Danette S., 5,590,325, Cl. 395-615.000.
- Lograsso, Barbara K.: See—
- Anderson, Iver E.; Lograsso, Barbara K., and Terpstra, Robert L., 5,589,199, Cl. 425-10.000.
- Löhr, Gernot: See—
- Felix, Bernd; Hintzer, Klaus; Löhr, Gernot, and Schötle, Thomas, 5,589,558, Cl. 526-247.000.
- Loma Linda University Medical Center: See—
- Zhu, Yong H.; and Kirsch, Wolff M., 5,588,951, Cl. 600-207.000.
- London, Thomas B., to Lucent Technologies Inc.: Communications privacy protection system by replacing calling party number with non-assigned number, 5,590,184, Cl. 379-142.000.
- Long, Douglas A.: See—
- Stone, Dwight V.; Long, Douglas A.; and Salazar-Vior, Jose M., 5,588,413, Cl. 123-508.000.
- Long, Lynn E.; and Lum, Joan L., to Hughes Electronics: Thermal control coating, 5,589,274, Cl. 428-215.000.
- Long, Michelle A.: See—
- Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401.000.
- Longley, Jonathan T.: Rigid shelf structure, 5,588,370, Cl. 108-42.000.
- Looker, Robert, to Satco, Inc.: Skid for heavy payloads, 5,588,371, Cl. 108-51.100.
- Löppönen, Jussi, to Nokia Telecommunications OY: Method of searching for a signalling channel in a radio system, 5,590,400, Cl. 455-34.200.
- LoPresti, Jim: See—
- LoPresti, Leroy; and LoPresti, Jim, 5,588,619, Cl. 244-53.00R.
- LoPresti, Leroy; and LoPresti, Jim: Propeller synchro-pulsing, 5,588,619, Cl. 244-53.00R.
- L'Oreal: See—
- Aubert, Lucien; and Gagnebin Cahanne, Francoise, 5,589,178, Cl. 424-401.000.
- Boussouira, Boudiaf, and Nguyen, Quang L., 5,589,179, Cl. 424-401.000.
- Gueret, Jean-Louis H., 5,588,447, Cl. 132-200.000.
- Gueret, Jean-Louis H., 5,588,450, Cl. 132-218.000.
- de Laforcade, Vincent; and Lacout, Franck, 5,588,566, Cl. 222-402.110.
- Lorenz, Gisela: See—
- Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Scheibberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275.000.
- Eicken, Karl; Goetz, Norbert; Harreus, Albrecht; Ammermann, Eberhard; Lorenz, Gisela; and Rang, Harald, 5,589,493, Cl. 514-355.000.
- Lotsch, John A., to General Motors Corporation: Air bag module with gas augmentation, 5,588,675, Cl. 280-738.000.
- Lotto, Ronald L.; Teske, Ernest H.; and Hatchell, Peter, to FMC Corporation: Interleaving apparatus for rolled up segments, 5,588,644, Cl. 271-183.000.
- Lotvin, Jason A.: See—
- Ryan, Michael J.; Lotvin, Jason A.; Strathy, Nancy; and Fantini, Susan E., 5,589,385, Cl. 435-258.350.
- Love, Charles S.: See—
- Lemp, Steven K.; Hudak, Philip J., and Love, Charles S., 5,588,967, Cl. 606-167.000.
- Lovett, Donna M.; and Lovett, Robert R.: Smart disk software protection system, 5,590,192, Cl. 380-4.000.
- Lovett, Robert R.: See—
- Lovett, Donna M.; and Lovett, Robert R., 5,590,192, Cl. 380-4.000.
- Lavoi, Paul A.: See—
- Fahlen, Theodore S.; Duboc, Robert M., Jr., and Lovoi, Paul A., 5,589,731, Cl. 313-495.000.
- Low, Murray K.: See—
- Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., 5,590,259, Cl. 395-764.000.
- Lowe, Terry B.: Container filling apparatus, 5,588,471, Cl. 141-83.000.
- Lowell, Dana: See—
- Duhane, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, 5,588,257, Cl. 49-199.000.
- Lu, Frank E.: See—
- Shim, Sang-Hea; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo; and Lu, Frank E., 5,589,106, Cl. 252-387.000.
- Lu, Jian G.; and Beckmann, Ronald L., to General Motors Corporation: Cable core adjuster with lock members, 5,588,334, Cl. 74-502.600.
- Lubbers, Thomas: See—
- Gerwitz, Jürgen; Gotsch, Erwin; Hebeisen, Paul; Link, Helmut; and Lubbers, Thomas, 5,589,473, Cl. 514-183.000.
- Lucas, John M.; Schombek, Arnold; and Bayer, Georg, to Schoenbek Worldwide Lighting, Inc.: Gallery ring assemblies for chandeliers, 5,588,744, Cl. 362-405.000.
- Lucent Technologies Inc.: See—
- Abramovici, Miron; Agrawal, Vishwani D.; Cheng, Kwang-Ting; and Rajan, Krishna B., 5,590,135, Cl. 371-22.100.
- Agarwal, Anjana; and Lee, Chinmei C., 5,590,176, Cl. 379-59.000.
- Anlon, Menachem T., 5,590,129, Cl. 370-376.000.
- Asthana, Abhaya; Cravatts, Mark R.; and Krzyzanowski, Paul, 5,590,370, Cl. 395-800.000.
- Baillargeon, James N.; and Cho, Alfred Y., 5,588,969, Cl. 23-294.00R.
- Bales, Bruce M.; and Thiel, Stephen M., 5,590,127, Cl. 370-260.000.
- Bergmann, Ernest E., 5,590,140, Cl. 371-61.000.
- Bifinis, Alexandros; Dar, Shaal; and Gehani, Narain H., 5,590,327, Cl. 395-670.000.
- Bowman, Wayne C.; and Niemela, Van A., 5,590,032, Cl. 363-15.000.
- Chittipeddi, Sailesh, 5,589,416, Cl. 437-60.000.
- Chiu, Tien-Heng, 5,589,693, Cl. 257-48.000.
- Cunningham, John E.; Goossen, Keith W.; Jan, William Y.; Pathak, Rajiv N.; and Walker, James A., 5,589,404, Cl. 437-5.000.
- Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54.100.
- DeMarco, John J.; Kook, Taeho; and Kostelak, Robert L., Jr., 5,589,303, Cl. 430-5.000.
- Fuchs, Wesley K.; Huang, Yennun; and Wang, Yi-Min, 5,590,277, Cl. 395-183.140.
- Gans, Michael J.; and Yeh, Yu S., 5,589,797, Cl. 330-149.000.
- Geigel, Alfred A.; and Keasler, William E., 5,590,121, Cl. 370-290.000.
- Goodnow, James E., II; Kowalski, Thaddeus J.; and Rowland, James R., 5,590,329, Cl. 395-708.000.
- Goossen, Keith W.; and Walker, James A., 5,589,974, Cl. 359-290.000.
- Greenspan, Steven L., 5,590,187, Cl. 379-212.000.
- Grundvig, Jeffrey P.; and Vallancourt, David G., 5,589,832, Cl. 341-161.000.
- Jin, Sungho; Kochanski, Gregory P.; and Zhu, Wei, 5,588,894, Cl. 445-24.000.
- Juang, Bing-Hwang; and Rahim, Mazin G., 5,590,242, Cl. 395-2.540.
- Kartalopoulos, Stamatios V., 5,590,323, Cl. 395-676.000.
- Kwock, Elizabeth W.; and Miller, Timothy M., 5,589,424, Cl. 437-229.000.
- Law, Ronald L.; Roy, Apurba; and Shewmake, Steven A., 5,588,848, Cl. 439-83.000.
- Levine, Barry F., 5,589,704, Cl. 257-436.000.
- London, Thomas B., 5,590,184, Cl. 379-142.000.
- Matthews, Adrian S., 5,590,398, Cl. 455-33.100.
- Mishra, Partho P.; and Srivastava, Mani B., 5,590,126, Cl. 370-329.000.
- Moutad, Antoine N., 5,590,381, Cl. 395-872.000.
- Lücke, Christian; Vry, Uwe; and Lemcke, Ulrich, to Carl Zeiss-Stiftung: Binocular tube assembly for a stereomicroscope, 5,589,977, Cl. 359-375.000.
- Ludwig Institute for Cancer Research: See—
- Coulie, Pierre; and Boon-Falleur, Thierry, 5,589,334, Cl. 435-6.000.
- LuK Lamellen und Kupplungsbau GmbH: See—
- Kooy, Ad; Bier, Helmar; and Mebus, Norbert, 5,588,517, Cl. 192-70.250.
- Lum, Joan L.: See—
- Long, Lynn E.; and Lum, Joan L., 5,589,274, Cl. 428-215.000.
- Lund, Glenn: See—
- Kasser, Michel; and Lund, Glenn, 5,589,981, Cl. 359-529.000.
- Lundberg, Scott A.: See—
- Edgington, Robert J.; Stepro, James A.; Wissell, Harold J.; and Lundberg, Scott A., 5,589,301, Cl. 429-234.000.
- Lunford, David R.; and Durkin, Michael D., to Dell USA, L.P.: Circuit for detection of co-processor unit presence and for correction of its absence, 5,590,363, Cl. 395-800.000.
- Lurie, Keith G.; and Gold, Barbara S., to University of Minnesota, Regents of the: Methods and pharmaceutical compositions for enhanced cardiopulmonary resuscitation, 5,588,422, Cl. 128-200.240.
- Lürssen, Klaus: See—
- Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91.000.
- Lusignea, Richard W.: See—
- Harvey, Andrew C.; Lusignea, Richard W.; and Rubin, Leslie S., 5,589,236, Cl. 428-1.000.
- LWT Instruments Inc.: See—
- Pomerleau, Daniel G., 5,589,825, Cl. 340-854.000.
- Lyles, Joseph B.; and Bell, Alan G., to Xerox Corporation: Device and method for use of a reservation ring to compute crossbar set-up parameters in an ATM switch, 5,590,123, Cl. 370-397.000.
- Lynch, Adam Q.: Multi-sensor detection system, 5,589,824, Cl. 340-628.000.
- Lyon, Frank L.: See—
- Alexander, Albert H. D.; Ballantine, W. Thomas; Lakey, Leland D.; and Lyon, Frank L., 5,589,603, Cl. 588-250.000.
- Lyon, James M.: See—
- Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., 5,590,274, Cl. 395-182.050.
- Lysson, Hans-Jürgen; Broden, Reiner; and Leppert, Hans-Detlef, to Kabel Rheydt AG: Device for coating an optical fiber, 5,588,997, Cl. 118-405.000.
- Lyn, Gap Y.; and Park, Chang S., to Electronics and Telecommunications Research Institute, and Telecommunication Authority: Locking apparatus for optical frequency multiplex system, 5,589,970, Cl. 359-133.000.
- M. J. Bauer Company, Inc.: See—
- Bauer, Matthew J., 5,589,058, Cl. 210-98.000.
- M. W. Trading APS: See—
- Holmgren, Bertil, 5,588,315, Cl. 70-57.100.

- Maarschalkerweerd, Jan M., to Trojan Technologies Inc.: Fluid treatment system and process, 5,590,390, Cl. 422-186.300.
- Mabilat, Claude; and Pechere, Jean-Claude, to Bio Merieux: DNA fragments, probes and amplification primers of the 65 kD antigen of mycobacteria, 5,589,585, Cl. 536-24.320.
- Mabuchi, Mamoru: See—
- Mori, Hiroshi; Tanaka, Masakazu; Mabuchi, Mamoru; and Saito, Makoto, 5,589,143, Cl. 422-171.000.
- MacConochie, Ian O.: Discriminator rain gutter system, 5,588,261, Cl. 52-11.000.
- Machida, Masataka: See—
- Ata, Masafumi; Machida, Masataka; and Watanabe, Haruo, 5,589,038, Cl. 204-157.420.
- Machold, Timothy R.: See—
- Taylor, Charles S.; Donlon, Brian S.; and Machold, Timothy R., 5,588,949, Cl. 600-166.000.
- Macro Engineering & Technology Inc.: See—
- Tkach, Peter V.; and Opl, Frank G., 5,589,201, Cl. 425-66.000.
- Macronix International Co., Ltd.: See—
- Chang, Hershaw, 5,590,339, Cl. 395-750.000.
- Macrovision Corporation: See—
- Ryan, John O., 5,590,194, Cl. 380-5.000.
- Madaffari, Peter L.; and Collins, James S., to Tibbetts Industries, Inc.: Low noise amplifier for microphone, 5,589,799, Cl. 330-277.000.
- Maddern, Peter; and Currie, Kenneth J. G., to Kimberly-Clark Limited: Non-woven fabric comprising at least one spunbonded layer, 5,589,258, Cl. 428-286.000.
- Madsen, Russell G.: See—
- Ford, George W., Jr.; Lambert, Richard C.; and Madsen, Russell G., 5,589,118, Cl. 264-122.000.
- Mac, Toshiyuki: See—
- Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mac, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Maebou, Kunji: See—
- Nakajima, Shinobu; and Maebou, Kunji, 5,590,152, Cl. 373-103.000.
- Maeda, Hiroshi: See—
- Hazell, Mark A.; Perry, David A.; Maeda, Hiroshi; and Tone, Junsuke, 5,589,366, Cl. 435-119.000.
- Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, to Canon Sales Co., Inc.; Alcan-Tech Co., Inc.; and Semiconductor Process Laboratory Co., Ltd.: Apparatus for forming a film on a water, 5,589,001, Cl. 118-722.000.
- Maeda, Noboru, to Nipponendo Co., Ltd.: Failure-recovering sequential procedure teaching system and method thereof, 5,590,036, Cl. 364-184.000.
- Maeda, Takeshi: See—
- Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116.000.
- Maeda, Tetsuo: See—
- Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416.000.
- Maeda, Yasuo; and Sekiguchi, Kyoji, to Canon Kabushiki Kaisha: Ophthalmologic apparatus having a shiftable bed, 5,589,899, Cl. 351-245.000.
- Maehjima, Takamichi; Inoue, Toshihiro; Hasegawa, Hiroshi; and Nakano, Atsushi, to Yazaki Corporation: Method for inserting wire-equipped terminal in connector housing, 5,588,206, Cl. 29-845.000.
- Maes, Gregory R.: See—
- Baker, Gerald N.; and Maes, Gregory R., 5,588,484, Cl. 165-122.000.
- Maezawa, Hiroyuki: See—
- Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.
- Magainin Pharmaceuticals Inc.: See—
- Williams, Jon I.; Pierce, James C.; Anderson, G. Mark; and Kari, Prasad, 5,589,364, Cl. 435-69.700.
- Magee, Constance: See—
- Fusco, Thomas M.; Magee, Constance; and Freitas, Glenn, 5,589,015, Cl. 156-73.100.
- Magharious, Walaa, to Centek Industries, Inc.: Wet marine exhaust muffler, 5,588,888, Cl. 440-89.000.
- Magic Circle Media, Inc.: See—
- Isadore-Barreca, Anthony J., 5,590,262, Cl. 395-806.000.
- Maglietta, Ralph J., Jr.: See—
- Venkataramani, Edamanal S.; Forman, Andrew L.; Maglietta, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182.110.
- Magyar, Kálmán; Gaál, József; Szirák, István; Lengyel, József; Szabó, Anna Z.; Mármárosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter, to Chinoin Gyógyszer és Vegyszeri Termékek Gyára Rt.: Pharmaceutical composition and process for the preparation thereof, 5,589,513, Cl. 514-654.000.
- Mahant, Vijay K.: Chemiluminescence assays based on indoxyl substrates, thioindoxyl substrates and other substrates, 5,589,328, Cl. 435-4.000.
- Mahany, Ronald L.: See—
- West, Guy J.; and Mahany, Ronald L., 5,590,346, Cl. 395-800.000.
- Mahaworasilpa, Tohsak: See—
- Coster, Hans G. L.; Ashcroft, Robert G.; and Mahaworasilpa, Tohsak, 5,589,047, Cl. 204-450.000.
- Maher, Timothy R.: See—
- Taylor, Lynn P.; le Blanc, Pieter W. J. C.; Butler, Kenneth C.; and Maher, Timothy R., 5,588,812, Cl. 417-356.000.
- Mainquist, James K.: See—
- Downs, Robert C.; Mainquist, James K.; Nitz, Larry T.; and Aldrich, William L., III, 5,588,327, Cl. 74-335.000.
- Mainster, Martin A.; Crossman, Janet L.; and Johnson, Robert D., to Ocular Instruments, Inc.: Adjustable indirect ophthalmoscopy lens, 5,589,896, Cl. 351-219.000.
- Malarcher, Falvey: See—
- Lin, Tsen-Hwang; and Malarcher, Falvey, 5,590,367, Cl. 395-800.000.
- Malhi, Satwinder, to Texas Instruments Incorporated: High-performance high-voltage device structures, 5,589,695, Cl. 257-77.000.
- Malhotra, Shadi L., to Xerox Corporation: Recording sheets containing amino acids, hydroxy acids, and polycarboxylic compounds, 5,589,277, Cl. 428-500.000.
- Malik, Dale: See—
- Howe, Wayne; and Malik, Dale, 5,590,171, Cl. 379-33.000.
- Malone, Philip G.: See—
- Brabston, William N.; and Malone, Philip G., 5,588,783, Cl. 405-258.000.
- Malone, Robert W.: See—
- Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44.000.
- Maloney, John E.: See—
- Weiland, Ana L.; Kornfeld, Richard K.; and Maloney, John E., 5,590,408, Cl. 455-69.000.
- Maloney, Michael; and Schlesinger, Robert, to Intel Corporation: Dial lists for computer-based conferencing systems, 5,590,128, Cl. 370-260.000.
- Maltais, Jo-Ann B.; Wood, Archie T.; and Hovland, Roy S., to COBE Laboratories, Inc.: Method and apparatus for cleaning a dialysis circuit downstream of a dialyzer, 5,589,070, Cl. 210-636.000.
- MAN GH Schienenverkehrstechnik GmbH: See—
- Richter, Wolfgang-Dieter; Uebel, Lutz; and Weeger, Engelbert, 5,588,368, Cl. 105-199.100.
- MAN Roland Druckmaschinen AG: See—
- Herold, Manfred; Hartung, Georg; Schutz, Hans-Willy; and Jung, Ulrich, 5,588,365, Cl. 101-350.000.
- Manabe, Toshihiko, to Kabushiki Kaisha Toshiba: Shared data management scheme using shared data locks for multi-threading, 5,590,326, Cl. 395-477.000.
- Mancini, Rick A., to New York State Electric & Gas Corporation: Combustion enhancement system with in-bed foils, 5,588,378, Cl. 110-101.00A.
- Mancuso, Massimo; Poluzzi, Rinaldo; and Rizzotto, Gianguido, to SGS-Thomson Microelectronics S.r.l.; and Consorzio per la Ricerca sulla Microelettronica nel Mezzogiorno: Filter architecture, particularly for video applications, 5,589,890, Cl. 348-678.000.
- Mandel, Morton: See—
- Bhagavan, Nadhipuram V.; Petersen, Charles E.; and Mandel, Morton, 5,589,338, Cl. 435-6.000.
- Mani, Sanjay; Nishimura, Dwight G.; Conolly, Steven M.; and Pauly, John M., to Leland Stanford Junior University, The Board of Trustees of the: Inversion recovery MRI, 5,588,431, Cl. 128-653.300.
- Manjunath, Konanur; Paulsen, Knut A.; and Ognedal, Leiv B., to Norsk Hydro a.s.: Pulse-operated point feeder, 5,588,787, Cl. 406-85.000.
- Mankoo, Amrit S., to Bush Boake Allen Inc.: Flavor enhancer, 5,589,158, Cl. 424-49.000.
- Manley, Paul E.; and Flecksteiner, Richard J., to Zeon Chemicals Incorporated: Peroxide-cured polyacrylates, 5,589,550, Cl. 525-282.000.
- Mann, André: See—
- Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoeppe, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Mann, Gerhard, to Mont Blanc Industri AB: Load-carrier for vehicles, 5,588,573, Cl. 224-329.000.
- Mansur, Luis E.: See—
- Eman, Richard G.; and Mansur, Luis E., 5,588,650, Cl. 273-142.00B.
- Marchand, Claudine; Druihe, Pierre; Pujalon-Mercereau, Odile; and Langsley, Gordon, to Institut Pasteur: Antibodies which bind to molecules containing at least one peptide sequence carrying one or several epitopes characteristic of a liver stage antigen produced by *P. falciparum* in hepatocytes, 5,589,343, Cl. 435-7.220.
- Mariani, Celestina: See—
- De Beuckeleer, Marc; Herdies, Lydia; Gossele, Véronique; and Mariani, Celestina, 5,589,610, Cl. 800-205.000.
- Mariella, Raymond P., Jr.: See—
- Northrup, M. Allen; Mariella, Raymond P., Jr.; Carrano, Anthony V.; and Balch, Joseph W., 5,589,136, Cl. 422-102.000.
- Marin, Heiner: See—
- Lehmann, Volker; Marin, Heiner; and Reiher, Ingolf, 5,589,673, Cl. 218-66.000.
- Marino, Adriano: See—
- D'Agaro, Amos; Marino, Adriano; and Venturini, Andrea, 5,588,727, Cl. 312-283.000.
- Marisetty, Suresh K., to Intel Corporation: Method and apparatus for emulating circuitry in a computer system using a system management interrupt, 5,590,312, Cl. 395-500.000.
- Marisetty, Suresh K., to Intel Corporation: Method and apparatus for reducing power consumption in a computer system using virtual device drivers, 5,590,342, Cl. 395-750.000.
- Markert, Eberhard: See—

- Vetter, Gerhard; and Markert, Eberhard, 5,588,604, Cl. 242-47.050
- Markies, Peter R., and Miedema, Mark, to Océ Nederland, B.V. Intermediate transfer member having a material which breaks down impurities, 5,589,921, Cl. 399-297.000
- Markin, Rodney S., and Newcomb, Michael R., to Lab Interlink, Inc. Specimen carrier, 5,589,137, Cl. 422-104.000
- Markowitz, Kenneth, and Gelfer, Mikhail Y., to Block Drug Company Inc. Dispersible particulate system for desensitizing teeth, 5,589,159, Cl. 424-49.000
- Marmarosi, Katalin, See—
Magyar, Kalman, Gábor, József; Szirák, István; Lengyel, József; Szabó, Anna Z.; Marmarosi, Katalin; Hennezy, István; Szatmari, István; Török, Zoltán; and Kormóczy, Péter, 5,589,513, Cl. 514-654.000
- Marmoner, Gilles, to Lange International S.A. Ski boot, 5,588,229, Cl. 36-118.900
- Marosi, Laszlo, See—
Fischer, Rolf; Dostalek, Roman; and Marosi, Laszlo, 5,589,600, Cl. 585-266.000
- Marotte, Philippe, See—
Descombes, Jean-Philippe; and Marotte, Philippe, 5,589,729, Cl. 313-440.000
- Marrero, Deogracias D., See—
Ohmart, Dale V.; Benitez, Willie B., III; Marrero, Deogracias D.; and Mirizzi, Douglas J., 5,589,765, Cl. 324-158.100
- Marshall Air Systems, Inc., See—
Stuck, Robert M., and Rapner, James, III, 5,588,354, Cl. 99-386.000
- Marshall, Hugh G., to Asea Brown Boveri Inc. Restrained paper driver, 5,588,223, Cl. 34-414.000
- Marshall, Peter W., See—
Sinolinski, Susan L.; Morrison, Denby G.; Marshall, Peter W.; and Huete, David A., 5,588,781, Cl. 405-195.100
- Marshall, Steven E., See—
Bliss, Daniel L.; Marshall, Steven E.; and Ruby, Michael I., 5,588,617, Cl. 244-1.000
- Martin, Bill, Sr., to Ambu International A/S. Cervical collar, 5,588,957, Cl. 602-18.000
- Martin, Christopher J., See—
Hutter, Robert J.; Martin, Christopher J.; and Roesner, Thomas W., 5,588,910, Cl. 454-154.000
- Martin, David O., to Martin Door Manufacturing Inc. Water diversion channel for the joint between door sections of a sectional door, 5,588,475, Cl. 160-44.000
- Martin, Donald L. M., to Tritan Pty Limited. Simulator arrangement, 5,589,979, Cl. 359-449.000
- Martin Door Manufacturing, Inc., See—
Martin, David O., 5,588,475, Cl. 160-44.000
- Martin, Harry D., III, See—
Patrician, Thomas I.; and Martin, Harry D., III, 5,590,386, Cl. 419-20.000
- Martin, Herman W., to Ropak Canada Inc. Lidding machine, 5,588,283, Cl. 53-486.000
- Martin, James D., See—
Sides, James R.; Martin, James D.; and Schiefel, Robert S., 5,589,141, Cl. 422-164.000
- Martin Marietta Energy Systems, Inc., See—
Britton, Charles L., 5,590,104, Cl. 365-45.000
- Martinez, Ed E., See—
Park, Sangil; Martinez, Ed E.; and Yoon, Dae Hee, 5,590,241, Cl. 395-2.360
- Martinez, Eduardo, See—
Valdés, Jacobo; and Martinez, Eduardo, 5,589,851, Cl. 345-136.000
- Martinez, Louis, to Radio Telecom & Technology, Inc. Compatible interactive TV and multimedia delivery system two way cable TV conversion system for data transmission over a dedicated frequency band, 5,589,872, Cl. 348-12.000
- Martinez, Sarah B.; Leary, H. Lee, Jr.; and Nichols, Debra J., to Bristol Myers Squibb Company. Milk protein partial hydrolysate and process for preparation thereof, 5,589,357, Cl. 435-68.100
- Martinez-Bustos, Fernando, See—
De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C. Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243.000
- Martins, Leo, See—
Shockley, Ty R.; Martins, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, 5,589,197, Cl. 424-663.000
- Marugo Rubber Industries, Ltd., See—
Kakuchi, Daisuke; Ogawa, Yasumichi; Yasumatsu, Hiromi; and Shiraga, Kazutaka, 5,588,469, Cl. 138-137.000
- Marui, Kuniyoshi, and Sato, Goichi, to Kabushiki Kaisha Toshiba. Adapter unit for a portable radio telephone enabling either one of data transmission and hand-free operation, 5,590,414, Cl. 455-89.000
- Marusawa, Hiroshi, See—
Konoike, Takehiro; Marusawa, Hiroshi; Takagi, Hiroshi; and Tomono, Kunitaburo, 5,589,096, Cl. 252-62.570
- Maruyama, Haruyoshi; Ogata, Shin; and Tsunoyama, Yoshinori, to Kawasaki Jukogyo Kabushiki Kaisha. Hull shape of small watercraft, 5,588,388, Cl. 114-271.000
- Maruyama, Tetsuo, See—
Ohtsuka, Masaaki; Yamakawa, Teruji; and Maruyama, Tetsuo, 5,590,096, Cl. 369-13.000
- Marvin, Russel H., See—
Graham, Gary A.; Jacobs, Merrit N.; Marvin, Russel H.; Shaw, James D.; and VanBrunt, Nicholas, 5,588,946, Cl. 494-11.000
- Marilyn House, See—
House, Randall H.; Hofmann, Johann H.; and Birck, Freddie C., 5,588,786, Cl. 405-285.000
- Matze, Henri-James R.; Routhieu, Vincent Jean Luc; Arnaud, Gilles L.; and Arnaud, Remy E., to Eurocopter France. Counter-torque device with rotor and flow straightening stator, both of which are ducted, and phase modulation of the blades of the rotor, for helicopter, 5,588,618, Cl. 244-17.190
- Maschinenfabrik Gustav Ehrlich, See—
Flemming, Fekardt, Tilch, Werner; Schusztel, Thomas; Ivanov, Marian; and Ehrlich, Paul, 5,589,650, Cl. 73-866.000
- Massachusetts Institute of Technology, See—
Bozler, Carl O.; Fan, John C. C.; and McClelland, Robert W., 5,588,994, Cl. 117-89.000
- Gilbert, Ira H., 5,590,356, Cl. 395-800.000
- Scharoff, Stanley E.; and Pentland, Alex, 5,590,261, Cl. 395-173.000
- Massucco, Arthur A., See—
Fauteux, Denis G.; Massucco, Arthur A.; Wilkins, Ronnie D.; and Shi, Jie, 5,588,971, Cl. 29-623.500
- Fauteux, Denis G.; Massucco, Arthur A.; and Wilkins, Ronnie D., 5,589,300, Cl. 429-218.000
- Masuzaki, Hidefumi, See—
Iguchi, Hiroaki; Kurosu, Yasuo; Fujimawa, Masaaki; Yokoyama, Yoshihiro; and Masuzaki, Hidefumi, 5,590,317, Cl. 395-602.000
- Materdomini, Daniel, See—
Resk, Richard E.; Shapiro, Jeffrey R.; and Materdomini, Daniel, 5,588,834, Cl. 433-26.000
- Materials Research Corporation, See—
Hsu, Jon S., 5,589,039, Cl. 204-192.120
- Lantsman, Alexander D., 5,589,041, Cl. 204-192.330
- Matin, Barry D., See—
Hoopingarner, Neil L.; and Matin, Barry D., 5,589,016, Cl. 156-87.000
- Matsubara, Hideki, See—
Kawaguchi, Kenzo; Takemura, Tetsuya; Matsubara, Hideki; Takagi, Sinya; and Kanda, Atsushi, 5,589,429, Cl. 501-96.000
- Matsuda, Masahiro, See—
Murakami, Masahiko; Matsuda, Masahiro; and Enkyama, Noriyuki, 5,590,178, Cl. 379-96.000
- Matsuda, Shimichi, to Fuji Photo Film Co., Ltd. Method of and apparatus for controlling drying of photographic material, 5,589,321, Cl. 430-432.000
- Matsuda, Tsukasa, See—
Hosoi, Kiyoshi; and Matsuda, Tsukasa, 5,589,259, Cl. 428-323.000
- Matsuda, Yoji, Morikawa, Masao, and Toma, Masaki, to Sumitomo Chemical Company, Limited. Liquid filtering and supply system controlling recirculation responsive to pressure difference across filter, 5,589,077, Cl. 210-741.000
- Matsuhisa, Yoji, See—
Kobayashi, Masanobu; Itoh, Motor; Matsuhisa, Yoji; and Shimizu, Kazuharu, 5,589,055, Cl. 205-768.000
- Matsui, Hisako, and Kabeshita, Akira, to Matsushita Electric Industrial Co., Ltd. Semiconductor chip-supply method and apparatus, 5,589,029, Cl. 156-344.000
- Matsui, Kenji, See—
Inai, Keisuke; Kato, Kenichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, 5,588,608, Cl. 242-374.000
- Matsui, Kuniko, See—
Tazawa, Masashi; Fujimawa, Nobuhito; Matsui, Kuniko; and Suzuki, Maki, 5,589,953, Cl. 358-498.000
- Matsui, Shinya, See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhito; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279.000
- Matsui, Toshiya, to Nec Corporation. Pilot signal detection circuit, 5,590,203, Cl. 381-4.000
- Matsumaru, Haruo, See—
Yamanoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsuki, Michio; Sasano, Akira; Okawa, Saburo; and Onitsuki, Ryoji, 5,589,962, Cl. 349-46.000
- Matsumoto, Kenji, See—
Miyaza, Masao; and Matsumoto, Kenji, 5,589,949, Cl. 358-451.000
- Matsumoto, Koso, See—
Asai, Koichi; Matsumoto, Koso; and Muto, Yasuo, 5,588,195, Cl. 29-33.000
- Matsumoto, Tadashi, and Nishioka, Seiji, to Nextel Communications, and NTL Mobile Communications Network Inc. Up-link channel assignment scheme for cellular mobile communications systems employing multi-beam antennas with beam selection, 5,590,399, Cl. 455-33.300
- Matsumoto, Takahiro, See—
Sasaki, Kunimasa; Wakiyama, Youchi; Matsumoto, Takahiro; Tanaka, Kiyaburo; and Yamanoto, Kenichi, 5,588,582, Cl. 228-127.000
- Matsumoto, Takeshi, See—
Imachi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Homura, Koichi; and Haneda, Tadayoshi, 5,589,251, Cl. 428-209.000
- Matsumoto, Yukihiro; and Yokotaki, Hisashi, to Honda Giken Kogyo Kabushiki Kaisha. Spark ignition internal-combustion engine, 5,588,401, Cl. 123-41.310
- Matsumoto, Yoshiki, See—
Kono, Yasuhiko; Matsumoto, Yoshiki; Fujisawa, Masayuki; and Nagatsu, Isao, 5,588,304, Cl. 62-340.000

- Matsumura, Sowjun, See—
Watanabe, Nobuatsu; Chong, Yong-Bo; and Matsumura, Sowjun, 5,589,271, Cl. 428-421.000
- Matsumura, Susumu, See—
Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15.000
- Matsuno, Hiromitsu, See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, 5,589,735, Cl. 313-638.000
- Matsuo, Hideo, See—
Tonikawa, Hisao; Matsuo, Hideo; and Fujiwara, Kazuhito, 5,588,357, Cl. 99-451.000
- Matsuo, Hiromitsu, See—
Kanai, Moriyasu; and Matsuo, Hiromitsu, 5,589,976, Cl. 359-362.000
- Matsuo, Masahito, to Mitsubishi Denki Kabushiki Kaisha. Data processor processing a jump instruction, 5,590,296, Cl. 395-570.000
- Matsuo, Ryukichi; and Yoshihara, Toshiaki, to Toppan Printing Co., Ltd. Gas barrier laminated material, 5,589,252, Cl. 428-216.000
- Matsuo, Shinta; and Sakamoto, Yoshio, to Kabushiki Kaisha Kenwood. Loudspeaker structure and method of assembling loudspeaker, 5,590,210, Cl. 381-199.000
- Matsushima, Asao, See—
Etoh, Yoshitake; Oshita, Takeo; Matsushima, Asao; Hayata, Hiromitsu; Sakimura, Tomoo; Suzuki, Toshiaki; and Kinoshita, Akira, 5,589,314, Cl. 430-126.000
- Matsushima, Hitoshi, to Fujitsu Limited. System and method for emulating disk tracks to maintain data format compatibility, 5,590,311, Cl. 395-500.000
- Matsushima, Noboru, to NOK Corporation. Crankshaft seal having resilient portion embedded in rigid retainer, 5,588,656, Cl. 277-35.000
- Matsushita Communication Industrial Corporation of America, See—
Bidefeld, Branko, 5,588,203, Cl. 29-743.000
- Matsushita Electric Corporation of America, See—
Naipally, Saiprasad V., 5,589,993, Cl. 386-81.000
- Matsushita Electric Industrial Co., See—
Okawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, 5,590,109, Cl. 369-77.200
- Matsushita Electric Industrial Co., Ltd., See—
Aoyama, Shoichi, 5,590,258, Cl. 395-793.000
- Fujita, Shigeru; and Sakai, Toshio, 5,589,875, Cl. 348-143.000
- Hatoh, Kazuhito; Niihara, Junji; Yasumoto, Eiichi; and Gamou, Takaharu, 5,589,287, Cl. 429-41.000
- Hiramoto, Masayoshi; Inoue, Osamu; Kugimiyu, Koichi; and Iijima, Kenji, 5,589,221, Cl. 427-130.000
- Iguchi, Keisaku; and Shinoda, Atsunao, 5,590,407, Cl. 455-66.000
- Ishikawa, Hideaki; and Aotani, Noboru; Takada, Kazunori; and Kondo, Iwamoto, 5,589,296, Cl. 429-191.000
- Shigeo, 5,589,676, Cl. 235-7.000
- Kawakita, Kouji; Tsukamoto, Masahide; Horio, Yasuhiro; Nakatani, Seiichi; and Hatakeyama, Akihito, 5,588,207, Cl. 29-852.000
- Matsui, Hisako; and Kabeshita, Akira, 5,589,029, Cl. 156-344.000
- Morita, Mitsunori; Miyazaki, Masaya; Enoki, Nobuyuki; and Takuma, Akira, 5,590,340, Cl. 395-750.000
- Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tetsuo, 5,590,062, Cl. 364-578.000
- Ogawa, Kazufumi, 5,589,235, Cl. 428-1.000
- Saitou, Shinji, 5,589,770, Cl. 324-209.000
- Sato, Yuki; Ishizaki, Toshio; Sakaue, Tsuyoshi; Hashimoto, Koji; Yamada, Tohru; and Uwano, Tomoki, 5,589,724, Cl. 310-348.000
- Shibata, Hideyo; Kinoshita, Ritsuro; Yoshida, Takayasu; and Eshima, Shigeo, 5,589,992, Cl. 386-72.000
- Taguchi, Yutaka; Eda, Kazuo; Seki, Shun-ichi; and Onishi, Keiji, 5,589,806, Cl. 333-193.000
- Takada, Kazunori; Kondo, Shigeo; Yamamoto, Osamu; and Nishijima, Motoaki, 5,589,298, Cl. 429-218.000
- Toyama, Masakazu, 5,590,217, Cl. 382-104.000
- Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000
- Yanagawa, Yoshifumi; and Kunthira, Tadashi, 5,590,007, Cl. 360-109.000
- Matsura, Yasuhiro, See—
Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsura, Yasuhiro, 5,590,355, Cl. 395-800.000
- Matter, Eugene P., to Intel Corporation. Method and apparatus for reducing power consumption in a computer system using ready delay, 5,590,341, Cl. 395-750.000
- Mattern, Klaus-Peter, to Robert Bosch GmbH. Circuit arrangement for a brake system with anti-lock system and/or traction control, 5,588,720, Cl. 303-122.080
- Matthews, Adrian S., to Lucent Technologies Inc. Virtual mobile location area, 5,590,398, Cl. 455-33.100
- Matthews, Donald P., See—
McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500
- Matthews, Wallace, See—
Vaishnavi, Vick; Matthews, Wallace; and Kenny, Patrick, 5,590,120, Cl. 370-254.000
- Mattutat, Manfred, See—
Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000
- Matumura, Naoki, See—
Atsumi, Toru; Kamijo, Yasuhiro; Furukawa, Yoshiki; and Matumura, Naoki, 5,589,678, Cl. 235-472.000
- Maurer, Fritz, See—
Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Kazuaki; Uka, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000
- Maurer-Fogy, Ingrid, See—
Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Ströwa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189.000
- Maurice, Denis, to Alcatel Cable Interface. Hermaphrodite contact and a connection defined by a pair of such contacts, 5,588,859, Cl. 439-290.000
- Mauroy, Bernard, See—
Brassier, Marc; Gasquet, Jean-Claude; Segaud, Daniel; and Mauroy, Bernard, 5,589,730, Cl. 313-493.000
- Maury, Elise E., See—
DeSimone, Joseph M.; Maury, Elise E.; Combes, James R.; and Mence-loglu, Yusuf Z., 5,589,105, Cl. 252-351.000
- Maus, Wolfgang; Brück, Rolf; and Swars, Helmut, to Emitec Gesellschaft fuer Emissionstechnologie mbH. Method for controlling the heating of an electrically heatable catalytic converter, 5,588,291, Cl. 60-274.000
- Mavrianos, Kostas, Self contained snow-removal apparatus and method of use therefore, 5,588,231, Cl. 37-227.000
- Max-Planck-Gesellschaft Zur Förderung Der Wissenschaften E. V., See—
Ullrich, Axel; and Vogel, Wolfgang, 5,589,375, Cl. 435-240.200
- Maxey, David, to Smart Storage, Inc. Computer file directory system, 5,590,320, Cl. 395-619.000
- May, Paul, to Sharp Kabushiki Kaisha. Mode-locked diode laser based optical communication system, 5,589,968, Cl. 359-124.000
- May, Stanley W., See—
Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zaremka, Michael J., 5,588,507, Cl. 188-71.500
- Mayer, Guenter, See—
Witowski, Edgar; and Mayer, Guenter, 5,588,465, Cl. 137-625.640
- Mayfield, Ralph L. Toilet valve seat actuator assembly, 5,588,157, Cl. 4-397.000
- Mayo, Kevin; and Wiltshire, Mark, to Menvier (Electronic Engineers) Ltd. Luminaires, 5,588,743, Cl. 362-299.000
- Mays, Richard C., See—
Cortjens, Leo M.; Franklin, Kenneth A.; Mays, Richard C.; and Smith, Curtis M., 5,589,878, Cl. 348-211.000
- Mayser, Peter, See—
Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeier, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560.000
- Mazurek, Harry, to ARCO Chemical Technology, L.P. Reduced calorie fat component, 5,589,217, Cl. 426-611.000
- Mazzali, Stefano, to SGS-Thomson Microelectronics S.r.l. Method for testing an electrically erasable and programmable memory device, 5,590,075, Cl. 365-185.220
- Mazzo, Charles. Wrist wallet and carrying pouch, 5,588,571, Cl. 224-222.000
- McAlpine, James B., See—
Hochlowski, Jill E.; Jackson, Marianna; Kadam, Sunil K.; Karowski, James P.; and McAlpine, James B., 5,589,485, Cl. 514-315.000
- McBurney, Paul W., to Trimble Navigation Limited. Satellite positioning system filter, 5,590,043, Cl. 364-449.100
- McCallick, Frank, See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000
- McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, to Merrell Pharmaceuticals Inc. Process for the preparation of ribonucleotide reductase inhibitors, 5,589,587, Cl. 536-28.500
- McClelland, Robert W., See—
Bozler, Carl O.; Fan, John C. C.; and McClelland, Robert W., 5,588,994, Cl. 117-89.000
- McCline, Matthew C., See—
Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., 5,590,274, Cl. 395-182.050
- McClure, David C., to SGS-Thomson Microelectronics, Inc. Variable input threshold adjustment, 5,589,783, Cl. 326-71.000
- McClure, David C., to SGS-Thomson Microelectronics, Inc. Dynamically controlled voltage reference circuit, 5,589,794, Cl. 327-538.000
- McClure, David C., to SGS-Thomson Microelectronics, Inc. Dual-port data cache memory, 5,590,307, Cl. 395-458.000
- McClure, Jack A., to Inland Container Corporation. Automatic set-up carton with corner posts, 5,588,585, Cl. 229-191.000
- McConnell, James R., See—

- McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500.
- McCormack, Jonathan I.: See—
Harding, James A.; and McCormack, Jonathan I., 5,590,322, Cl. 395-604.000.
- McCoy, James N.; West, Jerry B.; and Podio, Augusto L., to McCoy, James N. Method and apparatus for measuring pumping rod position and other aspects of a pumping system by use of an accelerometer, 5,589,633, Cl. 417-63.000.
- McCracken, William P.; and Cooper, Neal, to Texas Instruments Incorporated. Video synchronized power module, 5,589,891, Cl. 348-730.000.
- McCreer, Alan L., to Winch & Engineering Limited. Mounting bracket, 5,588,633, Cl. 248-647.000.
- McCrory, Edwin D.: See—
Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704.000.
- McCulloch Corporation: See—
Liu, Li-Hsiung, 5,588,178, Cl. 15-330.000.
- McCusker, James K.: See—
Ceola, Giacomo; McCusker, James K.; and Calzavara, Giacomo, 5,590,010, Cl. 361-93.000.
- McDonnell Douglas Corporation: See—
Blackmon, James B.; Drubka, Robert E.; Jones, Nelson E.; Gerrick, R. Andrew; and Hand, Michael L., 5,589,758, Cl. 322-100.000.
- Johnson, Bartley C.; and Belk, John H., 5,589,641, Cl. 73-800.000.
- McDonnell Douglas Helicopter Co.: See—
Charles, Bruce D.; Hassan, Ahmed A.; Tadghighi, Hormoz; Janaki Ram, Ram D.; and Sankar, Lakshmi N., 5,588,800, Cl. 416-24.000.
- McDonnell, James M.: See—
Jameson, Bradford A.; McDonnell, James M.; and Korngold, Robert, 5,589,458, Cl. 514-13.000.
- McEnroe, Robert J.: See—
Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wiley, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.
- McEwan, Thomas E., to University of California, The Regents of the. Short range radio locator system, 5,589,838, Cl. 342-387.000.
- McGarry, Susan J.: See—
Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J., 5,590,189, Cl. 379-356.000.
- McGarvey, John A.: See—
Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagnan, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjolund, Paul F., 5,589,928, Cl. 356-4.100.
- McGee, Daniel. Power string and chalk line, 5,588,610, Cl. 242-379.000.
- McGrath, Donald T.: See—
Frank, Paul A.; McGrath, Donald T.; and Staver, Daniel A., 5,589,766, Cl. 324-158.100.
- McHugh, George J., to AGF Manufacturing, Inc. Valve and sensor arrangement, 5,588,462, Cl. 137-557.000.
- MCI Communications Corporation: See—
Gallant, John K.; and Donovan, Steven R., 5,590,175, Cl. 379-58.000.
- Moran, Carlos W.; and Thibodeaux, Louis S., 5,590,119, Cl. 370-225.000.
- McIntosh, Glen E., to Cryogenic Technical Services, Inc. Variable-density method for multi-layer insulation, 5,590,054, Cl. 364-505.000.
- McIntosh, J. Michael: See—
Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurhno D., 5,589,340, Cl. 435-6.000.
- McIntyre, Dale F., to Eastman Kodak Company. Camera with illumination source, 5,589,905, Cl. 396-431.000.
- McIntyre, Paul R.: See—
Dale, Allison Hazel C.; Piggitt, Roger H.; Hallett, Richard A.; and McIntyre, Paul R., 5,589,318, Cl. 430-264.000.
- McKinley, Gareth H.: See—
Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Naura, William S.; and McKinley, Gareth H., 5,588,509, Cl. 188-267.000.
- McKown, Russell C.; Quinn, Michael D.; and Yelderman, Mark L., to Interflo Medical, Inc. System and method for controlling the temperature of a catheter-mounted heater, 5,588,438, Cl. 128-692.000.
- McLaren, Elbert A., II: See—
Wilson, Nathaniel B.; and McLaren, Elbert A., II, 5,589,756, Cl. 320-22.000.
- McMahon, Donna, to Donna McMahon, Inc. Combination flotation device and swimming aid, 5,588,892, Cl. 441-116.000.
- McMahon, Steven L.: See—
Smith, Robert S.; and McMahon, Steven L., 5,589,602, Cl. 585-671.000.
- McMillan, Robin T. D., to ABB Management AG. Injection nozzle, 5,588,824, Cl. 431-285.000.
- McMullen, Dillon G.: See—
McMullen, Frederick G.; McMullen, Dillon G.; and McMullen, Roger B., 5,589,599, Cl. 585-240.000.
- McMullen, Frederick G.; McMullen, Dillon G.; and McMullen, Roger B. Pyrolytic conversion of organic feedstock and waste, 5,589,599, Cl. 585-240.000.
- McMullen, Roger B.: See—
McMullen, Frederick G.; McMullen, Dillon G.; and McMullen, Roger B., 5,589,599, Cl. 585-240.000.
- McNally, Francis J.: See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryujii; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.
- McNally, Maureen A.: See—
Lebkowski, Jane S.; McNally, Maureen A.; and Okarma, Thomas B., 5,589,377, Cl. 435-240.000.
- McNeil-PPC, Inc.: See—
Yang, Chung-Yun M., 5,589,117, Cl. 264-113.000.
- McPherson, Michael J.: See—
Gurr, Sarah J.; McPherson, Michael J.; Atkinson, Howard J.; and Bowles, Dianna J., 5,589,622, Cl. 800-205.000.
- McTaggart, Fergus; Pemberton, Denis; and Smith, Graham J., to Zeneca Limited. Cross-linked quaternary ammonium derivatives of poly(N,N-dialkylallyl) ammonium polymers, 5,589,166, Cl. 424-78.350.
- McTague, Michael J.: See—
Nardone, Joseph M.; McTague, Michael J.; and David, Howard S., 5,590,289, Cl. 395-289.000.
- McVicker, Henry J.: See—
Johnson, Glenn W., Jr.; McVicker, Henry J.; and Hargrave, David C., 5,588,955, Cl. 601-152.000.
- McWilliams, John P.: See—
Farnos, Maria D.; McWilliams, John P.; Sharma, Sanjay B.; and Shihabi, David S., 5,589,147, Cl. 423-239.200.
- Mead, Franklin B., Jr.; and Nachamkin, Jack. System for converting electromagnetic radiation energy to electrical energy, 5,590,031, Cl. 363-8.000.
- Mead, James B.: See—
Mead, Julian E.; and Mead, James B., 5,588,355, Cl. 99-449.000.
- Mead, Julian E., and Mead, James B. Knockdown compactable food smoker and method of use thereof, 5,588,355, Cl. 99-449.000.
- Means, Kevin P. Apparatus and method for synchronizing search and surveillance devices, 5,589,901, Cl. 396-12.000.
- Mebus, Norbert: See—
Kooy, Ad. Bier, Helmar; and Mebus, Norbert, 5,588,517, Cl. 192-70.250.
- Mechling, Richard W. Apparatus and method for the teaching of standing balance, 5,588,841, Cl. 434-255.000.
- MED Institute: See—
Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Goode, Louis; and Fearnot, Neal E., 5,588,436, Cl. 128-662.030.
- Medar, Inc.: See—
Boillard, Reno C., 5,589,088, Cl. 219-110.000.
- Medema, Robert M.: See—
Osborn, Charles; Medema, Robert M.; and Ruiter, Andrew K., 5,588,934, Cl. 477-96.000.
- Medic-Light Inc.: See—
Terman, Michael; Fairhurst, Stephen; Hughes, Philip; and Levitt, Joel, 5,589,741, Cl. 315-360.000.
- Medvedev, Igor N.; and Schogenov, Klim A., to Aquamin Company Limited. Electrolyzer for desalination, 5,589,050, Cl. 204-630.000.
- Meeco, Incorporated: See—
Mettes, Jacob, 5,589,085, Cl. 216-65.000.
- MegalDyne Medical Products, Inc.: See—
Neutekoven, William S., 5,588,634, Cl. 251-9.000.
- Megahed, El-Sayed A.: See—
Passaniti, Joseph L.; Megahed, El-Sayed A.; and Zreiba, Nuri A., 5,589,109, Cl. 252-518.000.
- Mehring, Peter A., and Nguyen, Cau L., to Sun Microsystems, Inc. Method and apparatus for the pipelining of data during direct memory accesses, 5,590,286, Cl. 395-250.000.
- Meiji Seika Kaisha, Ltd.: See—
Adachi, Takashi; Ishii, Takafumi; and Hidaka, Hidemasa, 5,588,254, Cl. 47-57.600.
- Meinert, Søren: See—
Rykket, Arne O.; and Meinert, Søren, 5,588,708, Cl. 297-423.200.
- Meisel, Thomas: See—
Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425.600.
- Meiss, Dieter: See—
Deisenhofer, Manfred; Meiss, Dieter; and Messner, Ekkehard, 5,589,734, Cl. 313-636.000.
- Melnik, Adrian L.: See—
Flinchbaugh, Bernadette M.; Gabany, Andrew J.; Melnik, Adrian L.; and Schmid, Christopher J., 5,588,878, Cl. 439-682.000.
- Meltzer, Norman: See—
Neill, Paul; Brandt, Loralei; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, 5,589,163, Cl. 424-70.510.
- MEMC Electronic Materials, Inc.: See—
Holder, John D., 5,588,993, Cl. 117-13.000.
- Menashi, Jameel; Reid, Robert C.; Whitehouse, Robert S.; and Kaul, David J., to Cabot Corporation. Preparation and use of pelletized submicron pigment powder/polymer compositions, 5,589,531, Cl. 524-409.000.
- Menceloglu, Yusuf Z.: See—
DeSimone, Joseph M.; Maury, Elise E.; Combes, James R.; and Mence-loglu, Yusuf Z., 5,589,105, Cl. 252-351.000.
- Mencke, Norbert; Harder, Achim; and Jeschke, Peter, to Bayer Aktiengesellschaft. Endoparasiticide compositions, 5,589,503, Cl. 514-450.000.
- Meneses, Aaron B. Fire hydrant valve guide with locking sleeve and wrench therefor, 5,588,460, Cl. 137-296.000.
- Menjo, Takeshi: See—
Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145.000.
- Murasawa, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi; and Hasegawa, Takashi, 5,589,926, Cl. 399-302.000.
- Menke, Klaus; Böhlein-Maass, Jutta; Schmidt, Helmut; Bucerius, Klaus M.; and Engel, Walther, to Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V. Solid propellant based on phase-stabilized ammonium nitrate, 5,589,661, Cl. 149-19.400.
- Menvier (Electronic Engineers) Ltd.: See—
Mayo, Kevin; and Wiltshire, Mark, 5,588,743, Cl. 362-299.000.
- Meoli, Rudy B.; Lantern, 5,588,738, Cl. 362-184.000.
- MEPLA-Werke Lautenschläger GmbH & Co. KG: See—
Berger, Horst, 5,588,729, Cl. 312-334.400.
- Mercedes-Benz AG: See—
Römer, Matthias, 5,588,640, Cl. 267-64.110.
- Merchel, Horst, to Vendoret Holding S.A. Pledge lock for a shopping trolley, 5,589,677, Cl. 235-383.000.
- Merck & Co., Inc.: See—
Venkataramani, Edamandal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182.110.
- Merck Patent Gesellschaft mit beschränkter Haftung: See—
Bartmann, Ekkehard; and Tarumi, Kazuaki, 5,589,102, Cl. 252-299.010.
- Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., to Radio Frequency Systems, Inc. Antenna system with tapered aperture antenna and microstrip phase shifting feed network, 5,589,843, Cl. 343-820.000.
- Merlin, Bruno; and Quintana, Jean, to Societe d'Applications Generales d'Electricite et de Mecanique Sagem. Card receiver enabling a broken card to be ejected and card reader using it, 5,589,681, Cl. 235-482.000.
- Merlo, Werner O. Locking joint mechanism, 5,588,767, Cl. 403-128.000.
- Merrell Pharmaceuticals Inc.: See—
McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500.
- Merrett, Stanley L., to Schlumberger Industries, Inc. Sight, vent, and drain assembly for an underground tank, 5,588,779, Cl. 405-54.000.
- Merrill, Leonard A.: See—
Downes, Stuart D.; and Merrill, Leonard A., 5,589,669, Cl. 174-266.000.
- Merten, Gerhard: See—
Schwab, Michael; Walz, Gerd; and Merten, Gerhard, 5,589,535, Cl. 524-591.000.
- Mertz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, to Solcas Polymer, Limited Partnership. Acrylonitrile polymer composition and articles and methods for their preparation, 5,589,520, Cl. 521-64.000.
- Messner, Ekkehard: See—
Deisenhofer, Manfred; Meiss, Dieter; and Messner, Ekkehard, 5,589,734, Cl. 313-636.000.
- Meta Motoren- und Energie-Technik GmbH: See—
Kreuter, Peter; and Heuser, Peter, 5,588,411, Cl. 123-418.000.
- Metal Leve SA/Industria E Comercio: See—
Lippai, Andre; Tanigami, Jorge K.; and Dellanocce, Paulo T., 5,588,351, Cl. 92-208.000.
- Mettlitsky, Boris: See—
Swartz, Jerome; Shepard, Howard M.; Knechever, Mark J.; Metlitsky, Boris; and Barkan, Edward, 5,589,680, Cl. 235-472.000.
- Metromics, Inc.: See—
Granville, Gregg; and Glasson, J. Peter, 5,590,060, Cl. 364-560.000.
- Mettes, Jacob, to Meeco, Incorporated. Process of manufacturing a detecting unit for an electrolytic cell with thin film electrodes, 5,589,085, Cl. 216-65.000.
- Mettler-Toledo AG: See—
Berli, Urs, 5,589,670, Cl. 177-25.130.
- Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., to Akzo Nobel N.V. Aqueous coating compositions including a reactive emulsifier, 5,589,534, Cl. 524-548.000.
- Meyer, Larry P.: See—
Sweet, Frederick J.; and Meyer, Larry P., 5,588,595, Cl. 239-222.170.
- Meyer, Robert C., to PepsiCo, Inc. Compartmented container including closure with access to individual compartments, 5,588,550, Cl. 220-525.000.
- Meyer, Uwe F.: See—
Sander, Dieter; and Meyer, Uwe F., 5,588,562, Cl. 222-153.060.
- Meyers, Mark M.; and Schickler, Mark E., to Eastman Kodak Company. Method of manufacturing a diffractive surface profile, 5,589,983, Cl. 359-566.000.
- Meyn, William C.; and Schneider, Stanley, to Tektron Micro Electronics, Inc. Apparatus for synchronizing digital data without using overhead frame bits by using deliberately introduced errors for indicating superframe synchronization of audio signals, 5,590,161, Cl. 375-368.000.
- Meyyappan, Narayanan; and Nakato, Tatsuo, to Implanted Material Technology, Inc. Method of treating silicon to obtain thin, buried insulating layer, 5,589,407, Cl. 437-26.000.
- Michael Horauf Maschinenfabrik GmbH & Co. KG: See—
Vener, Gerhard; and Markert, Eberhard, 5,588,604, Cl. 242-47.050.
- Michalek, Jan K.: See—
Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.
- Michon, Gerald J.: See—
Brown, Dale M.; and Michon, Gerald J., 5,589,682, Cl. 250-214.00A.
- Micko, Eric S., to Qualimetrics, Inc. Potentiometer circuit providing identifiable open wiper signals, 5,589,779, Cl. 324-714.000.
- Micrel Incorporated: See—
Alter, Martin J., 5,589,702, Cl. 257-379.000.
- Micron Display Technology, Inc.: See—
Hofmann, Jim; and Stansbury, Darryl, 5,588,359, Cl. 101-128.210.
- Micron Quantum Devices Inc.: See—
Roshparvar, Frankie F., 5,590,089, Cl. 365-233.500.
- Micron Technology, Inc.: See—
Cloud, Gene, 5,588,759, Cl. 400-472.000.
- MicroParts GmbH: See—
Reinecke, Holger; Unal, Nezi; Peters, Ralf-Peter; Bartels, Frank; and Noker, Friedolin F., 5,588,597, Cl. 239-553.500.
- Micropytres Heaters International, Inc.: See—
Sekhar, Jainagesh A.; Liu, James J.; and Zhu, Naiping, 5,590,383, Cl. 419-2.000.
- Microsoft Corporation: See—
Butler, Laura J.; and Grauman, Joyce A., 5,590,267, Cl. 395-340.000.
- D'Souza, David J.; Konzen, Neil; and Weise, David N., 5,590,347, Cl. 395-800.000.
- Parry, William G., 5,590,336, Cl. 395-727.000.
- Zbikowski, Mark; Berkowitz, Brian T.; and Ferguson, Robert L., 5,590,318, Cl. 395-618.000.
- Middleton, David T., Jr.: See—
Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., 5,588,182, Cl. 16-265.000.
- Midwest Research Institute: See—
Sheldon, Peter, 5,588,995, Cl. 117-201.000.
- Miedema, Mark: See—
Markies, Peter R.; and Miedema, Mark, 5,589,921, Cl. 399-297.000.
- Mieno, Fumitake: See—
Sato, Noriaki; and Mieno, Fumitake, 5,589,410, Cl. 437-40.000.
- Migita, Shinichi: See—
Kawai, Hiroyuki; Sekihara, Kensuke; and Migita, Shinichi, 5,590,164, Cl. 378-4.000.
- Mihara, Tadashi: See—
Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuto; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160.000.
- Mikuni, Shin, to Casio Computer Co., Ltd. Character string outputting method and apparatus capable of varying sizes of characters, 5,590,247, Cl. 395-110.000.
- Miles, Richard E.: See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Miller, Dean M.: See—
Garces, Juan M.; Miller, Dean M.; and Howard, Kevin E., 5,589,153, Cl. 423-705.000.
- Miller, Alan G.: See—
Ali, Mahfuza B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G., 5,589,269, Cl. 428-411.100.
- Miller, Craig A.: See—
Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,590,292, Cl. 395-825.000.
- Miller, Donald L., to Schuller International, Inc. Air filtration media, 5,588,976, Cl. 55-514.000.
- Miller, John E. Support deck for mattress or seat, 5,588,163, Cl. 5-13.000.
- Miller, Larry: See—
Knee, Robert A.; Favia, Anthony R.; Davis, Bruce; and Miller, Larry, 5,589,892, Cl. 348-731.000.
- Miller, Monte G.: See—
Golio, John M.; Turner, Robert C.; Miller, Monte G.; and Halchin, David J., 5,590,063, Cl. 364-580.000.
- Miller, Paul J.: See—
Foreman, Kevin G.; Miller, Paul J.; and Siska, Steven M., 5,590,058, Cl. 364-551.010.
- Miller, Robin M., to United Technologies Automotive, Inc. Backup bearings for extreme speed touch down applications, 5,588,754, Cl. 384-609.000.
- Miller, Scott C.: See—
Shenvi, Ashokkumar B.; Jacobs, Robert T.; Miller, Scott C.; Ohnmacht, Cyrus J., Jr.; and Veale, Chris A., 5,589,489, Cl. 514-323.000.
- Miller, Sidney H. Valve for dispensing pressurized fluid through a flexible tube, 5,588,565, Cl. 222-394.000.
- Miller, Timothy M.: See—
Kwock, Elizabeth W.; and Miller, Timothy M., 5,589,424, Cl. 437-229.000.
- Miller, William J.: See—
Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., 5,589,402, Cl. 437-2.000.
- Milliken Research Corporation: See—
Dischler, Louis, 5,589,254, Cl. 428-221.000.
- Millo, Patricia: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.

- Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145.000.
- Murasawa, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi; and Hasegawa, Takashi, 5,589,926, Cl. 399-302.000.
- Menke, Klaus; Böhlein-Maass, Jutta; Schmidt, Helmut; Bucerius, Klaus M.; and Engel, Walther, to Fraunhofer-Gesellschaft zur Förderung der angewandten Forschung e.V. Solid propellant based on phase-stabilized ammonium nitrate, 5,589,661, Cl. 149-19.400.
- Menvier (Electronic Engineers) Ltd.: See—
Mayo, Kevin; and Wiltshire, Mark, 5,588,743, Cl. 362-299.000.
- Meoli, Rudy B.; Lantern, 5,588,738, Cl. 362-184.000.
- MEPLA-Werke Lautenschläger GmbH & Co. KG: See—
Berger, Horst, 5,588,729, Cl. 312-334.400.
- Mercedes-Benz AG: See—
Römer, Matthias, 5,588,640, Cl. 267-64.110.
- Merchel, Horst, to Vendoret Holding S.A. Pledge lock for a shopping trolley, 5,589,677, Cl. 235-383.000.
- Merck & Co., Inc.: See—
Venkataramani, Edamandal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182.110.
- Merck Patent Gesellschaft mit beschränkter Haftung: See—
Bartmann, Ekkehard; and Tarumi, Kazuaki, 5,589,102, Cl. 252-299.010.
- Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., to Radio Frequency Systems, Inc. Antenna system with tapered aperture antenna and microstrip phase shifting feed network, 5,589,843, Cl. 343-820.000.
- Merlin, Bruno; and Quintana, Jean, to Societe d'Applications Generales d'Electricite et de Mecanique Sagem. Card receiver enabling a broken card to be ejected and card reader using it, 5,589,681, Cl. 235-482.000.
- Merlo, Werner O. Locking joint mechanism, 5,588,767, Cl. 403-128.000.
- Merrell Pharmaceuticals Inc.: See—
McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500.
- Merrett, Stanley L., to Schlumberger Industries, Inc. Sight, vent, and drain assembly for an underground tank, 5,588,779, Cl. 405-54.000.
- Merrill, Leonard A.: See—
Downes, Stuart D.; and Merrill, Leonard A., 5,589,669, Cl. 174-266.000.
- Merten, Gerhard: See—
Schwab, Michael; Walz, Gerd; and Merten, Gerhard, 5,589,535, Cl. 524-591.000.
- Mertz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, to Solcas Polymer, Limited Partnership. Acrylonitrile polymer composition and articles and methods for their preparation, 5,589,520, Cl. 521-64.000.
- Messner, Ekkehard: See—
Deisenhofer, Manfred; Meiss, Dieter; and Messner, Ekkehard, 5,589,734, Cl. 313-636.000.
- Meta Motoren- und Energie-Technik GmbH: See—
Kreuter, Peter; and Heuser, Peter, 5,588,411, Cl. 123-418.000.
- Metal Leve SA/Industria E Comercio: See—
Lippai, Andre; Tanigami, Jorge K.; and Dellanocce, Paulo T., 5,588,351, Cl. 92-208.000.
- Mettlitsky, Boris: See—
Swartz, Jerome; Shepard, Howard M.; Knechever, Mark J.; Metlitsky, Boris; and Barkan, Edward, 5,589,680, Cl. 235-472.000.
- Metromics, Inc.: See—
Granville, Gregg; and Glasson, J. Peter, 5,590,060, Cl. 364-560.000.
- Mettes, Jacob, to Meeco, Incorporated. Process of manufacturing a detecting unit for an electrolytic cell with thin film electrodes, 5,589,085, Cl. 216-65.000.
- Mettler-Toledo AG: See—
Berli, Urs, 5,589,670, Cl. 177-25.130.
- Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., to Akzo Nobel N.V. Aqueous coating compositions including a reactive emulsifier, 5,589,534, Cl. 524-548.000.
- Meyer, Larry P.: See—
Sweet, Frederick J.; and Meyer, Larry P., 5,588,595, Cl. 239-222.170.
- Meyer, Robert C., to PepsiCo, Inc. Compartmented container including closure with access to individual compartments, 5,588,550, Cl. 220-525.000.
- Meyer, Uwe F.: See—
Sander, Dieter; and Meyer, Uwe F., 5,588,562, Cl. 222-153.060.
- Meyers, Mark M.; and Schickler, Mark E., to Eastman Kodak Company. Method of manufacturing a diffractive surface profile, 5,589,983, Cl. 359-566.000.
- Meyn, William C.; and Schneider, Stanley, to Tektron Micro Electronics, Inc. Apparatus for synchronizing digital data without using overhead frame bits by using deliberately introduced errors for indicating superframe synchronization of audio signals, 5,590,161, Cl. 375-368.000.
- Meyyappan, Narayanan; and Nakato, Tatsuo, to Implanted Material Technology, Inc. Method of treating silicon to obtain thin, buried insulating layer, 5,589,407, Cl. 437-26.000.
- Michael Horauf Maschinenfabrik GmbH & Co. KG: See—
Vener, Gerhard; and Markert, Eberhard, 5,588,604, Cl. 242-47.050.
- Michalek, Jan K.: See—
Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.
- Michon, Gerald J.: See—
Brown, Dale M.; and Michon, Gerald J., 5,589,682, Cl. 250-214.00A.
- Micko, Eric S., to Qualimetrics, Inc. Potentiometer circuit providing identifiable open wiper signals, 5,589,779, Cl. 324-714.000.
- Micrel Incorporated: See—
Alter, Martin J., 5,589,702, Cl. 257-379.000.
- Micron Display Technology, Inc.: See—
Hofmann, Jim; and Stansbury, Darryl, 5,588,359, Cl. 101-128.210.
- Micron Quantum Devices Inc.: See—
Roshparvar, Frankie F., 5,590,089, Cl. 365-233.500.
- Micron Technology, Inc.: See—
Cloud, Gene, 5,588,759, Cl. 400-472.000.
- MicroParts GmbH: See—
Reinecke, Holger; Unal, Nezi; Peters, Ralf-Peter; Bartels, Frank; and Noker, Friedolin F., 5,588,597, Cl. 239-553.500.
- Micropytres Heaters International, Inc.: See—
Sekhar, Jainagesh A.; Liu, James J.; and Zhu, Naiping, 5,590,383, Cl. 419-2.000.
- Microsoft Corporation: See—
Butler, Laura J.; and Grauman, Joyce A., 5,590,267, Cl. 395-340.000.
- D'Souza, David J.; Konzen, Neil; and Weise, David N., 5,590,347, Cl. 395-800.000.
- Parry, William G., 5,590,336, Cl. 395-727.000.
- Zbikowski, Mark; Berkowitz, Brian T.; and Ferguson, Robert L., 5,590,318, Cl. 395-618.000.
- Middleton, David T., Jr.: See—
Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., 5,588,182, Cl. 16-265.000.
- Midwest Research Institute: See—
Sheldon, Peter, 5,588,995, Cl. 117-201.000.
- Miedema, Mark: See—
Markies, Peter R.; and Miedema, Mark, 5,589,921, Cl. 399-297.000.
- Mieno, Fumitake: See—
Sato, Noriaki; and Mieno, Fumitake, 5,589,410, Cl. 437-40.000.
- Migita, Shinichi: See—
Kawai, Hiroyuki; Sekihara, Kensuke; and Migita, Shinichi, 5,590,164, Cl. 378-4.000.
- Mihara, Tadashi: See—
Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuto; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160.000.
- Mikuni, Shin, to Casio Computer Co., Ltd. Character string outputting method and apparatus capable of varying sizes of characters, 5,590,247, Cl. 395-110.000.
- Miles, Richard E.: See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Miller, Dean M.: See—
Garces, Juan M.; Miller, Dean M.; and Howard, Kevin E., 5,589,153, Cl. 423-705.000.
- Miller, Alan G.: See—
Ali, Mahfuza B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G., 5,589,269, Cl. 428-411.100.
- Miller, Craig A.: See—
Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,5

- Mills, George G.: *See—*
Uhler, George M.; and Mills, George G., 5,590,293, Cl. 395-581.000.
- Mills, Vincent; and Hughes, Tim P., to International Paper Company. Carton bottom sealing dies. 5,588,943, Cl. 493-58.000.
- Milton, Thomas J., to General Motors Corporation. Motor vehicle steering column. 5,588,337, Cl. 74-552.000.
- Milwaukee Electric Tool Corporation: *See—*
Elger, William A., 5,588,496, Cl. 173-178.000.
- MIM Industries, Inc.: *See—*
Frye, Ricky J.; Mims, Jon T.; and Rufener, Ron, 5,589,113, Cl. 264-40.500.
- Mimura, Hirokazu: *See—*
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.
- Min, Byung G.: *See—*
Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., 5,589,264, Cl. 428-359.000.
- Minagawa, Kazuhiro: *See—*
Kojima, Shioichi; Minagawa, Kazuhiro; Kano, Haruyuki; Miyazaki, Tadaaki; and Wada, Hiroaki, 5,589,116, Cl. 264-65.000.
- Minami, Satoshi: *See—*
Ikunami, Yoshikazu; Minami, Satoshi; and Fujii, Yozo, 5,589,919, Cl. 399-262.000.
- Minegishi, Natsuko: *See—*
Goto, Toshio; Moriya, Kouichi; Maurer, Fritz; Ito, Seishi; Wada, Kazuaki; Ukiwa, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000.
- Miner, Thomas L.: *See—*
DeCarlo, David J.; Miner, Thomas L.; and Stanwick, Ronald S., 5,589,666, Cl. 174-87.000.
- Minh, Nguyen Q., to AlliedSignal Inc. Preparation of a solid oxide fuel cell having thin electrolyte and interconnect layers. 5,589,017, Cl. 156-87.000.
- Minnesota Mining and Manufacturing Company: *See—*
Ali, Mahfaza B.; Farooq, Omar; Iqbal, Mohammed; and Miller, Alan G., 5,589,269, Cl. 428-411.100.
- Calhoun, Clyde D.; and Koskenmaki, David C., 5,589,246, Cl. 428-120.000.
- Harnis, Michael R.; Foss, Richard J.; Trice, Jennifer L.; and Neavin, Terence D., 5,589,000, Cl. 118-715.000.
- Kruse, John M.; Collins, John E.; and Sisley, Elizabeth M., 5,590,269, Cl. 395-291.000.
- Leonard, William K.; Mody, Kirit C.; and Rolando, Richard J., 5,589,122, Cl. 264-146.000.
- Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,589,433, Cl. 503-227.000.
- Perceman, Jack L., 5,589,026, Cl. 156-286.000.
- Pulido, Jacqueline J., 5,590,234, Cl. 385-135.000.
- Tsuei, Alexander C.; Kogel, Lorenz, III; and Pendergrass, Daniel B., Jr., 5,589,194, Cl. 424-497.000.
- Tsukazaki, Tomio; and Nakamura, Tsunehisa, 5,589,667, Cl. 174-135.000.
- Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbermagel, Peter J.; Heit, Robert V.; and Yoshida, Yuko, 5,589,247, Cl. 428-141.000.
- Mintech Corporation: *See—*
Hall, Robert T., II; and Onstad, Bradley K., 5,589,507, Cl. 514-557.000.
- Minohe, Masao; Shiraga, Noboru; and Nakamura, Nobutaka, to Sunimoto Chemical Company, Limited; and Seiko Instruments, Inc. Apparatus for thermal analysis. 5,588,746, Cl. 374-10.000.
- Minolta Camera Kabushiki Kaisha: *See—*
Aoki, Mikiyuki; and Omura, Kunihiko, 5,589,871, Cl. 347-237.000.
- Minolta Co., Ltd.: *See—*
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218.000.
- Yoshida, Ryuichi; Okamoto, Yasuhiro; and Kuwana, Minoru, 5,589,723, Cl. 310-328.000.
- Minowa, Toshimichi: *See—*
Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155.000.
- Mirapuri, Sunil; and Riordan, Thomas J., to Silicon Graphics, Inc. Method and apparatus for retarding pipeline processing. 5,590,294, Cl. 395-591.000.
- Mirizzi, Douglas J.: *See—*
Ohmart, Dale V.; Benitez, Willie B., III; Martero, Deogracias D.; and Mirizzi, Douglas J., 5,589,765, Cl. 324-158.100.
- Mirovli, Mark D.: *See—*
Kalina, Alexander I.; and Mirovli, Mark D., 5,588,298, Cl. 60-676.000.
- Mirror Lite of North Carolina: *See—*
Schmidt, William P., and Hutchinson, Franklin D., 5,589,984, Cl. 359-603.000.
- Misawa, Nobuhiro: *See—*
Hoshino, Masataka; and Misawa, Nobuhiro, 5,589,425, Cl. 427-250.000.
- Misawa, Norihiko; Kobayashi, Kazuo; and Nakamura, Katsumi, to Kirin Beer Kabushiki Kaisha. DNA sequences useful for the synthesis of carotenoids. 5,589,581, Cl. 536-23.200.
- Mishra, Partho P.; and Srivastava, Mani B., to Lucent Technologies Inc. Method for call establishment and rerouting in mobile computing networks. 5,590,126, Cl. 370-329.000.
- Miska, Richard A.: *See—*
Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54.100.
- Mistyurik, John D.: *See—*
Hamisch, Paul H., Jr.; and Mistyurik, John D., 5,588,756, Cl. 400-234.000.
- Mita Industrial, Co. Ltd.: *See—*
Fujimoto, Masaya; and Yamamoto, Haruo, 5,589,950, Cl. 358-455.000.
- Katsuhara, Kenji, 5,589,914, Cl. 399-60.000.
- Shibata, Kouichi; and Motooka, Shigenori, 5,590,303, Cl. 395-427.000.
- Mita, Mamoru: *See—*
Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, 5,589,668, Cl. 174-266.000.
- Mita, Seiichi: *See—*
Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116.000.
- Mitate, Takehito: *See—*
Yamada, Kazuo; Mitate, Takehito; Yoneda, Tetsuya; and Nishimura, Naoto, 5,589,299, Cl. 429-218.000.
- Mitomi, Masako; and Hoshino, Ryo, to Niteco, Inc.; and Kabushiki Kaisha Cosmo Area. Carrier bag. 5,588,569, Cl. 224-153.000.
- Mitre Corporation, The: *See—*
Krajewski, Marjan, Jr.; Chipchak, John C.; Chodorow, David A.; Trostle, Jonathan T.; and Baldwin, Peter T., 5,590,199, Cl. 380-25.000.
- Mitsuba Electric Manufacturing Co., Ltd.: *See—*
Kano, Masami, 5,588,879, Cl. 439-686.000.
- Mitsubishi Chemical Corporation: *See—*
Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshitaka, 5,589,517, Cl. 521-33.000.
- Uno, Mikio; Shintaku, Takashi; and Takehara, Takatsugu, 5,589,310, Cl. 430-106.000.
- Mitsubishi Denki Kabushiki Kaisha: *See—*
Akimoto, Yoshiaki; Tanaka, Hideo; Ogi, Hiroshi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, 5,590,243, Cl. 395-23.000.
- Ishimoto, Masaaki; and Toyota, Takehito, 5,590,394, Cl. 455-6.100.
- Kazama, Tsutomu; and Kachi, Mitsuyasu, 5,589,748, Cl. 318-560.000.
- Kinoshita, Takashi, 5,588,821, Cl. 418-259.000.
- Matsuo, Masahito, 5,590,296, Cl. 395-570.000.
- Murakami, Tokumichi; and Ohira, Hideo, 5,590,291, Cl. 395-566.000.
- Nagahara, Tetsuki; and Yamamoto, Masahiro, 5,589,634, Cl. 73-514.330.
- Okuda, Ryosuke, 5,590,050, Cl. 364-490.000.
- Ono, Yukio; and Kikuyama, Seiichi, 5,589,778, Cl. 324-654.000.
- Seno, Shiohito; and Ideguchi, Tetsuo, 5,590,328, Cl. 395-675.000.
- Shinomura, Takehiko; and Miyake, Takashi, 5,590,035, Cl. 364-177.000.
- Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416.000.
- Tashiro, Tetsuo, 5,590,371, Cl. 395-821.000.
- Ueda, Hiroyuki, 5,589,742, Cl. 315-307.000.
- Yamasaki, Tatsuo; Okuma, Ikuro; and Onishi, Ken, 5,589,994, Cl. 360-15.000.
- Mitsubishi Gas Chemical Company: *See—*
Tsuiji, Tomoko; Yamaguchi, Kohji; Kondo, Kiyosi; and Urakami, Teizi, 5,589,481, Cl. 514-287.000.
- Mitsubishi Jidosha Kogyo Kabushiki Kaisha: *See—*
Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416.000.
- Mitsubishi Jukogyo Kabushiki Kaisha: *See—*
Irie, Nobuhiko, 5,589,200, Cl. 425-46.000.
- Sasaki, Kunimasa; Wakiyama, Yuichi; Matsumoto, Takahiro; Tanaka, Kisaburo; and Yamamoto, Kenichi, 5,588,582, Cl. 228-127.000.
- Mitsubishi Jukogyo Kaisha: *See—*
Morii, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo, 5,589,146, Cl. 423-237.000.
- Mitsubishi Material Corp.: *See—*
Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seiichiro, 5,589,223, Cl. 427-248.100.
- Mitsubishi Steel Mfg. Co., Ltd.: *See—*
Ishiyama, Noritaka; and Kobayashi, Koutarou, 5,589,768, Cl. 324-207.210.
- Mitsugi, Sadahiko: *See—*
Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, 5,589,668, Cl. 174-266.000.
- Mitsui Petrochemical Industries, Ltd.: *See—*
Hama, Hideo; and Sakai, Yukari, 5,589,966, Cl. 349-194.000.
- Mitsuno, Makoto; Akagiri, Kenzo; Suzuki, Hiroshi; and Shimoyoshi, Osamu, to Sony Corporation. Encoding method and apparatus for bit compressing digital audio signals and recording medium having encoded audio signals recorded thereon by the encoding method. 5,590,108, Cl. 369-59.000.
- Mitsuoka, Katsuya: *See—*
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126.000.
- Mits, Jon T.: *See—*
Frye, Ricky J.; Mims, Jon T.; and Rufener, Ron, 5,589,113, Cl. 264-40.500.

- Mitwalsky, Alexander; and Ryan, James G., to International Business Machines Corp. Fuse link structures through the addition of dummy structures. 5,589,706, Cl. 257-529.000.
- Miura, Hirotosuna: *See—*
Amako, Jun; Miura, Hirotosuna; and Sonehara, Tomio, 5,589,955, Cl. 359-9.000.
- Miura, Masao: *See—*
Uchida, Naoshi; Miura, Masao; Oyama, Jun; Kuboyama, Katsunori; and Asakawa, Keji, 5,589,672, Cl. 218-34.000.
- Miura, Tohru: *See—*
Enami, Katsuya; and Miura, Tohru, 5,590,105, Cl. 369-50.000.
- Miyachi, Kouji: *See—*
Miyachi, Nobuji; and Miyachi, Kouji, 5,588,384, Cl. 112-475.060.
- Miyachi, Nobuji; and Miyachi, Kouji, to HAMS Corporation. Method and apparatus of folding opposite ends of a piece of tape. 5,588,384, Cl. 112-475.060.
- Miyachi, Takeshi: *See—*
Chiba, Keiko; and Miyachi, Takeshi, 5,589,304, Cl. 430-5.000.
- Miyachi Technos Corporation: *See—*
Uesugi, Akira, 5,589,089, Cl. 219-121.600.
- Miyake, Takashi: *See—*
Shinomura, Takehiko; and Miyake, Takashi, 5,590,035, Cl. 364-177.000.
- Miyaki, Yousuke: *See—*
Koga, Kenji; Arai, Hitoshi; Kagotani, Tsuneyo; and Miyaki, Yousuke, 5,589,297, Cl. 429-212.000.
- Miyano, Shinji; Sato, Katsuhiko; and Yabe, Tomoaki, to Kabushiki Kaisha Toshiba. Semiconductor memory device having a column selector. 5,590,084, Cl. 365-230.010.
- Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagita, Satoshi; and Baba, Yoshio, to Kabushiki Kaisha Toshiba. Method of manufacturing annealed films. 5,589,421, Cl. 437-225.000.
- Miyazaki, Masao; and Matsumoto, Kenji, to Sharp Kabushiki Kaisha. Image processing apparatus. 5,589,949, Cl. 358-451.000.
- Miyazaki, Masaya: *See—*
Morita, Mitsuki; Miyazaki, Masaya; Enoki, Nobuyuki; and Takuma, Akira, 5,590,340, Cl. 395-750.000.
- Miyazaki, Mitsumi; and Yoshida, Toshiaki, to Kabushiki Kaisha Ohara. Apparatus for continuously forming and processing a glass-ceramic. 5,588,979, Cl. 65-164.000.
- Miyazaki, Tadaaki: *See—*
Kojima, Shioichi; Minagawa, Kazuhiro; Kano, Haruyuki; Miyazaki, Tadaaki; and Wada, Hiroaki, 5,589,116, Cl. 264-65.000.
- Mizoguchi, Ikuro: *See—*
Uru, Masaru; Tokura, Kunihiko; Chatani, Ikuro; Mizoguchi, Ikuro; and Ito, Mamoru, 5,590,212, Cl. 381-191.000.
- Mizrahi, Amos; Galili, Naftali; and Rosenhouse, Giora, to State of Israel, Ministry of Agriculture. Method for a non-destructive determination of quality parameters in fresh produce. 5,589,209, Cl. 426-231.000.
- Mizrahi-Shalom, Ori K.; and Ko, Kung-Ling, to Philips Electronics North America Corporation. Processor with word-aligned branch target in a byte-oriented instruction set. 5,590,358, Cl. 395-800.000.
- Mizuno, Hiroyuki; Okamoto, Akiro; and Kubo, Suehiro, to Toyota Jidosha Kabushiki Kaisha. Ignition timing control device for an engine. 5,588,409, Cl. 123-339.110.
- Mizuno, Koji. Hinge structure of a spectacle frame. 5,589,895, Cl. 351-153.000.
- Mobi Corporation: *See—*
Fantone, Stephen D., 5,589,978, Cl. 359-412.000.
- Mobil Oil Corporation: *See—*
Bladt, John P.; and Shirodkar, Pradeep P., 5,589,551, Cl. 525-333.800.
- Bryant, David W., 5,588,487, Cl. 166-51.000.
- Farnos, Maria D.; McWilliams, John P.; Sharma, Sanjay B.; and Shihabi, David S., 5,589,147, Cl. 423-239.200.
- Mochida, Akihiko: *See—*
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akiro; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideo; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Mochida, Fumio: *See—*
Sato, Osamu; and Mochida, Fumio, 5,590,236, Cl. 388-821.000.
- Mochida Pharmaceutical Co., Ltd.: *See—*
Morishita, Hideaki; Kanamori, Toshinori; and Nobuhara, Masahiro, 5,589,360, Cl. 435-69.100.
- Mody, Kirit C.: *See—*
Leonard, William K.; Mody, Kirit C.; and Rolando, Richard J., 5,589,122, Cl. 264-146.000.
- Moeller, Gretchen J.: *See—*
Nelson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700.000.
- Mogami, Kenji: *See—*
Egawa, Tatsuya; Kawaguchi, Yasuhiro; Mogami, Kenji; and Shimizu, Nobuaki, 5,589,597, Cl. 568-608.000.
- Möhle, Rolf: *See—*
Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruns, Elke; Guntert, Dietwart; and Müller, Hubert, 5,589,060, Cl. 210-130.000.
- Möhlenkamp, Hans: *See—*
Sterfänger, Fritz; and Möhlenkamp, Hans, 5,588,268, Cl. 52-236.700.
- Mohler, Marjorie A.; and Nguyen, Tue H., to Genentech, Inc. Method and therapeutic compositions for the prevention of fibrin deposition or adhesions. 5,589,169, Cl. 424-94.200.
- Mohr, Judy M.; Baker, Richard W.; and Nakaji, Lisa A., to Pharmetrix Corporation. Transdermal delivery of the active enantiomer of ketorolac. 5,589,498, Cl. 514-413.000.
- Moini, Mojtaba: *See—*
Hans, Helmut; and Moini, Mojtaba, 5,589,745, Cl. 318-431.000.
- Molecular Therapeutics, Inc.: *See—*
Greve, Jeffrey M., 5,589,453, Cl. 514-8.000.
- Moll, Benjamin A.: *See—*
Firozabadi, Ebrahim; Lemieux, Christine; Moll, Benjamin A.; and Robinson, Karol, 5,589,613, Cl. 800-205.000.
- Moller, Karin: *See—*
Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Moller, Karin, 5,589,396, Cl. 436-73.000.
- Momota, Makoto: *See—*
Kato, Eiichi; Momota, Makoto; and Ohishi, Hiroyuki, 5,589,308, Cl. 430-49.000.
- Monarch Marking Systems, Inc.: *See—*
Hamisch, Paul H., Jr.; and Mistyurik, John D., 5,588,756, Cl. 400-234.000.
- Mondet, Jean J.: *See—*
Commel, Sylvie J.; and Mondet, Jean J., 5,588,801, Cl. 416-46.000.
- Monroy, Rodney L.: *See—*
Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Ronath, Paul D., 5,589,582, Cl. 536-23.500.
- Monsanto Company: *See—*
Jilka, Joseph M.; and Turner, Nilgun E., 5,589,612, Cl. 800-205.000.
- Klee, Harry J.; and Elmer, James S., 5,589,583, Cl. 536-24.100.
- Monster Cable International, Ltd.: *See—*
Lee, Noel, 5,589,718, Cl. 307-72.000.
- Mont Blanc Industri AB: *See—*
Mann, Gerhard; 5,588,573, Cl. 224-329.000.
- Monte, Robert F.: *See—*
Josefsson, Leif E. B.; and Monte, Robert F., 5,588,830, Cl. 432-147.000.
- Monteiro, Sergio L. P. Radiation imaging system. 5,590,169, Cl. 378-87.000.
- Montel, Jean: *See—*
Andrieu, Véronique; Montel, Jean; and Wick, Alexander, 5,589,190, Cl. 424-462.000.
- Montell Technology Company bv: *See—*
Govoni, Gabriele; Sacchetti, Mario; and Pasquali, Stefano, 5,589,549, Cl. 525-247.000.
- Monticello, James: *See—*
Hilyard, Kathy; Monticello, James; and Rugg, James, 5,589,327, Cl. 435-4.000.
- Moon, Tae J., to Hyundai Motor Company, Ltd. Link device of a lateral rod for a vehicle. 5,588,664, Cl. 280-689.000.
- Moore, Richard E., to Duramax, Inc. Torque control device for rotary mine drilling machine. 5,588,916, Cl. 464-20.000.
- Moraine, Michel: *See—*
Gruel, Henri; Moraine, Michel; and Crasnianski, Serge, 5,589,902, Cl. 396-3.000.
- Moran, Carlos W.; and Thibodeaux, Louis S., to MCI Communications Corporation. Deterministic selection of an optimal restoration route in a telecommunications network. 5,590,119, Cl. 370-225.000.
- Moran, John: *See—*
Shockley, Ty R.; Martis, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, 5,589,197, Cl. 424-663.000.
- Moran, Stephen W.; Jackson, John R.; Gallivan, Timothy J.; and Loftfield, Richard E., to Huron Tech Incorporated. Electrolysis process for removal of caustic in hemicellulose caustic. 5,589,053, Cl. 205-698.000.
- Morant, David G., to Boeing Company, The. Non-intrusive testing of a terminal resistor. 5,589,776, Cl. 324-534.000.
- Mordechai, Mark: *See—*
Blauer, Stephen; and Mordechai, Mark, 5,588,154, Cl. 2-69.000.
- Moreau, Thierry, to Connotech Experts Conseils Inc. Secure payment method using facsimile. 5,590,196, Cl. 380-18.000.
- Morehead, Bruce J.: *See—*
Dieffenderfer, James N.; and Morehead, Bruce J., 5,590,372, Cl. 395-823.000.
- Morgan Curcible Company plc. The: *See—*
Hobbs, John W.; and Cramer, Laurence E., 5,590,147, Cl. 372-75.000.
- Mori, Hiroshi; Tanaka, Masakazu; Mabuchi, Mamoru; and Saito, Makoto, to Nippondenso Co., Ltd. Exhaust gas purification apparatus for internal combustion engine. 5,589,143, Cl. 422-171.000.
- Mori, Hirotaro; and Yasuda, Hidehiro, to Osaka University. Method of manufacturing ultrathin particles of a compound. 5,589,234, Cl. 427-597.000.
- Mori, Junji: *See—*
Ide, Nobuhiro; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, 5,590,365, Cl. 395-394.000.
- Mori, Kazutaka: *See—*
Iwamura, Masahiro; Yamauchi, Tatsumi; Tanaka, Shigeya; and Mori, Kazutaka, 5,590,361, Cl. 395-800.000.
- Mori, Masahiro: *See—*
Itoyama, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yuji; Toyomura, Fumitaka; and Ohtsuka, Takashi, 5,589,006, Cl. 136-248.000.
- Mori, Shigehiro: *See—*

Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigehiro; and Moriuchi, Hisako, 5,589,506, Cl. 514-520.000.

Morii, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo, to Mitsubishi Jukogyo Kaisha. Method for treating ammonia, 5,589,146, Cl. 423-237.000.

Morikawa, Masao. *See*—

Matsuda, Yoji; Morikawa, Masao; and Toma, Masaaki, 5,589,077, Cl. 210-741.000.

Morikawa, Takashi. *See*—

Akashi, Ryoji; Morikawa, Takashi; Ninomura, Masanobu, and Uematsu, Takashi, 5,589,237, Cl. 428-1.000.

Morimoto, Nobuhiko. *See*—

Yamamura, Yoshitami; Morimoto, Nobuhiko; and Tanaka, Nobuyuki, 5,589,230, Cl. 427-493.000.

Morinaga Milk Industry Co., Ltd. *See*—

Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigehiro; and Moriuchi, Hisako, 5,589,506, Cl. 514-520.000.

Moroka, Hisashi. *See*—

Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiko; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279.000.

Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kohayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, to Canon Kabushiki Kaisha. Image display apparatus, 5,589,956, Cl. 359-15.000.

Morishima, Morito, to Yamaha Corporation. Track jump controller for correcting information read errors, 5,590,112, Cl. 369-124.000.

Morishita, Hideaki; Kanamori, Toshiro; and Nobuhara, Masahiro, to Mochida Pharmaceutical Co., Ltd. Polypeptide, DNA fragment encoding the same, drug composition containing the same and process for producing the same, 5,589,360, Cl. 435-69.100.

Morita, Koichi. *See*—

Sato, Yutaka; Morita, Koichi; Fujimoto, Shuzo; Ichihashi, Satoru, and Ohsawa, Kohji, 5,588,208, Cl. 29-888.044.

Morita, Mitsuaki; Miyazaki, Masaya; Enoki, Nobuyuki, and Takuma, Akira, to Matsushita Electric Industrial Co., Ltd. Apparatus and method for suspending and resuming software application on a computer, 5,590,340, Cl. 395-750.000.

Moriuchi, Hisako. *See*—

Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigehiro; and Moriuchi, Hisako, 5,589,506, Cl. 514-520.000.

Moriya, Koichi. *See*—

Goto, Toshiro; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Katsuki; Ukawa, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000.

Morley, David W. *See*—

Dunham, Mark E.; and Morley, David W., 5,589,881, Cl. 348-300.000.

Morlion, Danny; Jonckheere, Luc; and van Koetssem, Jan P. K., to Framatome Connectors International. Connector for a cable for high frequency signals, 5,588,851, Cl. 439-108.000.

Morrell, John A. *See*—

King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Rombult, Philip A.; and Hebert, Thomas K., 5,589,973, Cl. 359-214.000.

Morris, G. Michael. *See*—

Faklis, Dean; and Morris, G. Michael, 5,589,982, Cl. 359-565.000.

Morrison, Denby G. *See*—

Smolinski, Susan L.; Morrison, Denby G.; Marshall, Peter W.; and Huete, David A., 5,588,781, Cl. 405-195.100.

Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., to Minnesota Mining and Manufacturing Company. Thermal transfer systems having vanadium oxide antistatic layers, 5,589,433, Cl. 503-227.000.

Morrissey, David V. *See*—

Kearney, Kevin R.; Collins, Mark L.; Eldredge, John K.; and Morrissey, David V., 5,589,335, Cl. 435-6.000.

Morrow, Benjamin V. *See*—

Kadish, Andrew S.; and Morrow, Benjamin V., 5,589,753, Cl. 318-785.000.

Morrow, Dennis. *See*—

Morrow, Megan J.; and Morrow, Dennis, 5,588,551, Cl. 220-574.100.

Morrow, Megan J., and Morrow, Dennis; Eating aid, 5,588,551, Cl. 220-574.100.

Morse, Gary J.; and Thompson, Stephen P., to International Business Machines Corporation. Method and apparatus for optimizing the display of fonts in a data processing system, 5,590,260, Cl. 395-167.000.

Morton International, Inc. *See*—

Clark, Randall J.; Smith, Bradley W.; Rasmussen, Kirk H.; and Kort, Leland B., 5,588,676, Cl. 280-741.000.

Johnson, Kelly B., 5,588,472, Cl. 141-83.000.

Leonard, Timothy J.; and Kotke, Kurt J., 5,588,669, Cl. 280-728.300.

Storey, J. Kirk; and Olson, Brent K., 5,588,670, Cl. 280-730.200.

Moscovitch, Jerry. *See*—

Coulson, Richard R.; D'Amario, Eric; and Moscovitch, Jerry, 5,589,288, Cl. 429-96.000.

Moseley, Gerald. *See*—

Shariff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, 5,590,374, Cl. 395-829.000.

Moskowitz, Marvin. *See*—

Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Siddikman, Paul; Vimig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.

Motoda, Takashi; Karakida, Shoichi; Kaneno, Nobuaki; and Kageyama, Shigeki. Container for liquid metal organic compound, 5,589,110, Cl. 261-61.000.

Motosoka, Shigenori. *See*—

Shibata, Kouichi; and Motosoka, Shigenori, 5,590,303, Cl. 395-427.000.

Motorola. *See*—

Resnick, Douglas J.; Johnson, William A.; Cummings, Kevin D.; and Chen, Hector T. H., 5,590,239, Cl. 392-418.000.

Motorola, Inc. *See*—

Alberth, William P., Jr.; Janssen, John J.; and Klomdsdorf, Armin, 5,589,796, Cl. 330-133.000.

Motorola, Inc. *See*—

Baskett, Ira E., 5,589,703, Cl. 257-419.000.

Chapman, William; Chang, Gwo-Jer; Hwang, Emerald; Holt, James; Howington, Lee; and Chalmers, James, 5,590,055, Cl. 364-550.000.

Diekelman, Dennis P., 5,590,395, Cl. 455-13.100.

Form, William R.; and Kaylor, Scott A., 5,590,154, Cl. 375-229.000.

Golio, John M.; Turner, Robert C.; Miller, Monte G.; and Halchin, David J., 5,590,063, Cl. 364-580.000.

Holoubek, Kevin J.; Kenuk, Richard J., and Bontrager, Paul R., 5,590,418, Cl. 455-126.000.

Kahatepe, Mete, 5,590,131, Cl. 370-461.000.

Lodwig, John P.; Felix, Kenneth A.; and Whittington, Charles L., 5,590,172, Cl. 379-58.000.

Park, Sangil; Martinez, Ed E.; and Yoon, Dae-Hee, 5,590,241, Cl. 395-2.360.

Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., 5,589,402, Cl. 437-2.000.

Robb, Francine Y.; Robb, Stephen P.; and Grosenig, Paul J., 5,589,408, Cl. 437-29.000.

Samson, Randall J.; Budlong, Allan; and Huslig, Dan, 5,590,402, Cl. 455-44.000.

Vilmur, Richard J.; and Bruckert, Eugene J., 5,590,177, Cl. 379-60.000.

Wentworth, Robert M.; Galloway, David; Conney, Garland D.; and Webb, Brian A., 5,590,232, Cl. 385-92.000.

White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hui, 5,589,423, Cl. 437-228.000.

Wrzesinski, Stanley, 5,589,804, Cl. 331-116.000.

Zhang, Jinshan; and Anani, Anaba A., 5,589,289, Cl. 429-122.000.

Moti, Philip J.; White, David C.; and Becker, Thomas J., to Borg-Warner Automotive, Inc. Self-guided chain assemblies, 5,588,926, Cl. 474-212.000.

Mourad, Antoine N., to Lucent Technologies, Inc. Method and apparatus for buffered video playback of video content distributed on a plurality of disks, 5,590,381, Cl. 395-872.000.

Moynihan, Karen L., to NeXstar Pharmaceuticals, Inc. Liposome dispersion, 5,589,189, Cl. 424-450.000.

Moyse, Philip. *See*—

Guttig, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moyse, Philip, 5,590,350, Cl. 395-800.000.

MTS Systems Corporation. *See*—

Gloden, Michael L.; and Sprecher, Arnold E., Jr., 5,590,091, Cl. 367-140.000.

Muddiman, Rebecca W. *See*—

Deng, Zhi D.; Sigler, Gerald E.; Surridge, Nigel A.; Wiley, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.

Mugele, Kurt-Willy. *See*—

Trimborn, Peter; and Mugele, Kurt-Willy, 5,588,806, Cl. 417-68.000.

Muka, Richard S.; and Hofmeister, Christopher A., to Brooks Automation. Load arm for load lock, 5,588,789, Cl. 414-217.000.

Muka, Richard S., to Brooks Automation Inc. Passive gas substrate thermal conditioning apparatus and method, 5,588,827, Cl. 432-5.000.

Muller, Bernd. *See*—

Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275.000.

Müller, Helmut, to BFRU Ruprecht GmbH & Co. KG. Glow plug with prestressed contact surfaces, 5,589,091, Cl. 219-270.000.

Müller, Hubert. *See*—

Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruns, Elke; Guntert, Dietmar; and Müller, Hubert, 5,589,060, Cl. 210-130.000.

Müller-Broll, Gerhard. *See*—

Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000.

Multrico International Pty. Ltd. *See*—

Hayes, Brian B.; and Hayes, Colin J., 5,588,876, Cl. 439-622.000.

Mumbaikar, Vilas N. *See*—

Naik, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.

Munter, John D. *See*—

Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heiti, Robert V.; and Yoshida, Yuko, 5,589,247, Cl. 428-141.000.

Mura, Janine R. *See*—

Cunningham, Robert W.; Koch, Durmus; Mura, Janine R.; Felix, August; and Halick, Gary V., 5,588,958, Cl. 604-4.000.

Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, to Hitachi, Ltd.; and Showa Denko K.K. Processed substrate obtained by a process for effecting suppression of electrification, 5,589,270, Cl. 428-411.100.

Murai, Mikio. *See*—

Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.

Murakami, Masahiko; Matsuda, Masahiro; and Fukuyama, Noriyuki, to Fujitsu Limited. Electronic mail system linked with telephone, 5,590,178, Cl. 379-96.000.

Murakami, Thomas T. *See*—

Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828.000.

Murakami, Tokumichi; and Ohira, Hideo, to Mitsubishi Denki Kabushiki Kaisha. Digital signal processing system for limiting a result to be predetermined bit count, 5,590,291, Cl. 395-566.000.

Murakami, Tomio. *See*—

Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, 5,589,668, Cl. 174-266.000.

Murakami, Yosuke. *See*—

Iwasaki, Yoh; Murakami, Yosuke; and Itahashi, Masao, 5,589,283, Cl. 428-694.000.

Muraki, Toshio. *See*—

Sawaoka, Ryuji; Kouchi, Shinji; and Muraki, Toshio, 5,589,523, Cl. 523-211.000.

Muramatsu, Gyo. *See*—

Yoshida, Kiyohide; Muramatsu, Gyo; Abe, Akira; and Irite, Naoko, 5,589,432, Cl. 502-325.000.

Muramatsu, Tsuyoshi. *See*—

Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsuura, Yasuhiro, 5,590,355, Cl. 395-800.000.

Muraoka, Co., Ltd. *See*—

Sato, Takashi, 5,588,190, Cl. 24-682.100.

Muraoka, Tsutomu, to Kao Corporation. Hair setting agent composition, 5,589,162, Cl. 424-70.120.

Murasawa, Yoshihiro; Fukushima, Hisashi; Menjo, Takeshi; and Hasegawa, Takashi, to Canon Kabushiki Kaisha. Color image forming apparatus for forming a color image by transferring color toner to transfer member, 5,589,926, Cl. 399-302.000.

Murasawa, Yoshihiro. *See*—

Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145.000.

Murata, Akira. *See*—

Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.

Murata Kikai Kabushiki Kaisha. *See*—

Hara, Shoji; Yanai, Takenori; and Ishikawa, Kazuhiro, 5,588,523, Cl. 198-781.000.

Nakaji, Fumiaki, 5,588,603, Cl. 242-35.50A.

Uno, Toshiyuki; and Kubota, Yasuhiko, 5,588,602, Cl. 242-35.50A.

Murata Machinery, Ltd. *See*—

Chun, Victor L., 5,588,344, Cl. 83-13.000.

Murata Manufacturing Co., Ltd. *See*—

Kawahata, Kazunari; and Kushihi, Yuichi, 5,588,198, Cl. 29-600.000.

Konoike, Takehiro; Marusawa, Hiroshi; Takagi, Hiroshi; and Tomono, Kunisaburo, 5,589,096, Cl. 252-62.570.

Tani, Hiroji; and Oshita, Kazuhito, 5,588,983, Cl. 75-354.000.

Murata, Tomohiro; Kurihara, Kenzo; Kawashima, Kazuhiro; and Niida, Mitsuaki, to Hitachi, Ltd. Method and system for a high-reliable disk system, 5,590,272, Cl. 395-181.000.

Murdock, Douglas R. *See*—

Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubha G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.

Murphy, John P.; to Murphy, John P. Compact disc playback enhancer, 5,590,114, Cl. 369-290.000.

Musicus, Bruce R. *See*—

Robinson, Jeffrey J.; Rouse, Keith; and Musicus, Bruce R., 5,590,349, Cl. 395-800.000.

Muto, Hikoji. *See*—

Sugiyama, Hiroyuki; Hirose, Norio; Hamabuchi, Teruyoshi; and Muto, Hikoji, 5,588,362, Cl. 101-218.000.

Muto, Yasuo. *See*—

Asai, Koichi; Matsumoto, Koso; and Muto, Yasuo, 5,588,195, Cl. 29-33.000.

Takada, Yukinori; Kuno, Tokiyuki; Muto, Yasuo; and Asai, Koichi, 5,588,614, Cl. 242-538.200.

Mutta, Fabrizio. *See*—

Simeone, Giovanni; Mutta, Fabrizio; Locaspi, Angelo; and Tonelli, Claudio, 5,589,552, Cl. 525-440.000.

Mycogen Corporation. *See*—

Payne, Jewel; Narva, Kenneth E.; and Fu, Jenny, 5,589,382, Cl. 435-252.500.

Mycogen Plant Science, Inc. *See*—

Hoffman, Leslie M., 5,589,616, Cl. 800-205.000.

N.V. Nederlandsche Apparatenfabriek Nedap. *See*—

de Jong, Hendrik J.; and Postma, Ebele M., 5,588,234, Cl. 40-301.000.

NABCO Ltd. *See*—

Akamatsu, Osamu, 5,589,767, Cl. 324-173.000.

Nachamkin, Jack. *See*—

Mead, Franklin B., Jr.; and Nachamkin, Jack, 5,590,031, Cl. 363-8.000.

Nachman, Jacob B.; and Tsuria, Yossef, to News Datacom Ltd. Apparatus and method for securing communication systems, 5,590,200, Cl. 380-46.000.

Nagahara, Teruaki; and Yamamoto, Masahiro, to Mitsubishi Denki Kabushiki Kaisha. Semiconductor acceleration sensor for detecting acceleration in orthogonal directions, 5,589,634, Cl. 73-514.330.

Nagamatsu, Masato. *See*—

Ide, Nobuhiro; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, 5,590,365, Cl. 395-394.000.

Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tunek, to Matsushita Electric Industrial Co., Ltd. Simulator for producing various living environments mainly for visual perception, 5,590,062, Cl. 364-578.000.

Nagasawa, Yoshiaki. *See*—

Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuki; Yamazaki, Osamu; Komura, Yukihiro; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97.020.

Nagata, Masato; and Cornejo, José, to Chugai Ro Co., Ltd.; and Acerinox, S.A. Vertical bright annealing furnace for continuous heat treatment of metal strips, 5,588,828, Cl. 432-59.000.

Nagatsu, Isao. *See*—

Koiso, Yasuhiko; Matsumoto, Yoshiki; Fujisawa, Masayuki; and Nagatsu, Isao, 5,588,304, Cl. 62-340.000.

Naghsheh, Mahmoud. *See*—

Acampora, Anthony S.; and Naghsheh, Mahmoud, 5,590,125, Cl. 370-397.000.

Nagle, Robert E. *See*—

Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Brit, Wayne A., 5,590,052, Cl. 364-498.000.

Nagy, Peter. Fish tape reel attachment apparatus used in combination with a fish tape reel, 5,588,613, Cl. 242-395.000.

Nai Neway, Inc. *See*—

Pierce, William C.; and Richardson, Gregory A., 5,588,665, Cl. 280-704.000.

Naik, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Bansi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., to Hoechst Aktiengesellschaft. Arylcycloalkyl derivatives, their production and their use, 5,589,514, Cl. 514-681.000.

Naipally, Saiprasad V., to Matsushita Electric Corporation of America. Digital high definition television video recorder with trick-play features, 5,589,993, Cl. 386-81.000.

Naishtut, Vida. *See*—

Spector, Yechiel; Jacobson, Esther; Naishtut, Vida; Vittenberg, Michael; and Beinert, Zohar, 5,588,493, Cl. 169-46.000.

Naito, Ichiro. *See*—

Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.

Naito, Osamu. *See*—

Morii, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo, 5,589,146, Cl. 423-237.000.

Naitoh, Takaki; and Funaya, Okitsugu, to Whitaker Corporation. The Connectors for base boards and methods of connector of base boards, 5,588,845, Cl. 439-66.000.

Nakabayashi, Yukikazu. *See*—

Tomozane, Shotaro; Kidou, Hirokazu; and Nakabayashi, Yukikazu, 5,589,248, Cl. 428-174.000.

Nakada, Akio. *See*—

Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.

Nakada, Juichi. *See*—

Yamaguchi, Takahiro; Tajiri, Shinsuke; and Nakada, Juichi, 5,590,158, Cl. 375-331.000.

Nakagawa, Katsumi. *See*—

Toyama, Noboru; and Nakagawa, Katsumi, 5,589,403, Cl. 437-2.000.

Nakagiri, Etsuhiro. *See*—

Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, 5,589,883, Cl. 348-379.000.

- Nakai, Yukako, to Fujitsu Limited. Optical receiver apparatus for quickly detecting loss of a composite optical signal input employing a loss-of-clock detector. 5,589,683, Cl. 250-214.00R.
- Nakaji, Fumaki, to Murata Kikai Kabushiki Kaisha. Yarn take-up tube supplying apparatus for a winder. 5,588,603, Cl. 242-35.50A.
- Nakaji, Lisa A.: See—
Mohr, Judy M.; Baker, Richard W.; and Nakaji, Lisa A., 5,589,498, Cl. 514-413.000.
- Nakajima, Kazuhito: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadaaki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhito; Tsutsumi, Takayoshi; Kubota, Hidemichi; Kotaki, Yasuo; Tsukuda, Ken-ichi; and Sato, Yohei, 5,589,862, Cl. 347-87.000.
- Nakajima, Shinobu, and Maebou, Kunji, to Ishikawajima-Harima Jukogyo Kabushiki Kaisha. DC arc furnace. 5,590,152, Cl. 373-103.000.
- Nakajima, Toshiyuki: See—
Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34.000.
- Nakamatsu, Shuji: See—
Shimamune, Takayuki; Nakamatsu, Shoji; Sawamoto, Isao; and Nishiki, Yoshinori, 5,589,052, Cl. 205-349.000.
- Nakamoto, Kazuhiko: See—
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiko; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126.000.
- Nakamura, Hisatsugu. Vertical array type speaker system. 5,590,214, Cl. 381-182.000.
- Nakamura, Hitoshi: See—
Mori, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo, 5,589,146, Cl. 423-237.000.
- Nakamura, Katsumi: See—
Mitsawa, Norihiko; Kobayashi, Kazuo; and Nakamura, Katsumi, 5,589,581, Cl. 536-23.200.
- Nakamura, Katsutoshi: See—
Hotta, Yoshio; Hanyu, Yukio; Mihara, Tadashi; Kodera, Yasuo; and Nakamura, Katsutoshi, 5,589,964, Cl. 349-160.000.
- Nakamura, Kazunori, and Tei, I. Kou, to Furukawa Electric Co., Ltd. The Optical amplification system. 5,589,975, Cl. 359-345.000.
- Nakamura, Masafumi: See—
Saito, Seichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shiokawa, Junji; and Kawamae, Osamu, 5,589,995, Cl. 360-48.000.
- Nakamura, Nobutaka: See—
Minobe, Masao; Shiraga, Noboru; and Nakamura, Nobutaka, 5,588,746, Cl. 374-10.000.
- Nakamura, Seichiro: See—
Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seichiro, 5,589,223, Cl. 427-248.100.
- Nakamura, Shinichi: See—
Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuo, 5,589,103, Cl. 252-299.610.
- Nakamura, Shinya: See—
Kono, Katsumi; Nakamura, Shinya; and Honda, Atsushi, 5,588,937, Cl. 477-169.000.
- Nakamura, Toshiyuki: See—
Urata, Keishi; and Nakamura, Toshiyuki, 5,589,904, Cl. 396-55.000.
- Nakamura, Tsunehisa: See—
Tsukazaki, Tomio; and Nakamura, Tsunehisa, 5,589,667, Cl. 174-135.000.
- Nakamura, Yasushige: See—
Takezawa, Satoshi; Katagiri, Yoshimichi; Nakamura, Yasushige; and Sawatari, Norio, 5,589,313, Cl. 430-122.000.
- Nakamura, Yoshikazu. Golf swing training device. 5,588,919, Cl. 473-212.000.
- Nakanishi, Hiromi: See—
Kato, Takashi; and Nakanishi, Hiromi, 5,589,990, Cl. 359-799.000.
- Nakanishi, Noriyuki: See—
Tsujiyama, Kenji; Hashiyama, Tomiki; Ohashi, Motoaki; and Nakanishi, Noriyuki, 5,589,502, Cl. 514-449.000.
- Nakanishi, Shigeo; Tomimaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki, to Astra Aktiebolag. Injection and injection kit containing omeprazole and its analogs. 5,589,491, Cl. 514-338.000.
- Nakano, Atsushi: See—
Maejima, Takamichi; Inoue, Toshihiro; Hasegawa, Hiroshi; and Nakano, Atsushi, 5,588,206, Cl. 29-845.000.
- Nakao, Hiromobu, to Rohm Co., Ltd. Semiconductor nonvolatile memory. 5,589,700, Cl. 257-325.000.
- Nakao, Masashi, to Kyoyu Corporation. Flashlight with signaling lamp. 5,588,739, Cl. 362-205.000.
- Nakase, Makoto: See—
Tomofuji, Yoko; Nakase, Makoto; Sato, Takashi; Hazama, Hiroaki; Komano, Haruki; and Ito, Shinichi, 5,589,305, Cl. 430-5.000.
- Nakashiba, Yasutaka, to NEC Corporation. Solid state imaging device having sliding potential gradient. 5,589,698, Cl. 257-231.000.
- Nakashima, Masato: See—
Aritake, Hirokazu; Kato, Masayuki; and Nakashima, Masato, 5,589,957, Cl. 359-23.000.
- Nakata, Masahide: See—
Suzuki, Masao; Saito, Koichi; and Nakata, Masahide, 5,589,515, Cl. 514-784.000.
- Nakata, Ryuji, and Komiya, Hiroshi, to Koyo Seiko Co., Ltd. Rolling bearing and method of fabricating the same. 5,588,751, Cl. 384-463.000.
- Nakana, Yasuyuki, Yabuki, Akihiko; Yoshida, Yutaka; and Nishimoto, Katsushi, to Fujitsu Limited. Profile control system for robots. 5,590,244, Cl. 395-95.000.
- Nakatani, Mitsuo: See—
Yanamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, 5,589,962, Cl. 349-46.000.
- Nakatani, Seichi: See—
Kawakita, Kouji; Tsukamoto, Masahide; Horio, Yasuhiro; Nakatani, Seichi; and Hatakeyama, Akihito, 5,588,207, Cl. 29-852.000.
- Nakato, Tatsuo: See—
Meyyappan, Narayanan; and Nakato, Tatsuo, 5,589,407, Cl. 437-26.000.
- Nakayama, Masaaki: See—
Shockley, Ty R.; Martis, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, 5,589,197, Cl. 424-663.000.
- Nakazawa, Ikuo: See—
Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuo, 5,589,103, Cl. 252-299.610.
- Nakazawa, Toshiyuki, to Canon Kabushiki Kaisha. System which can display multiwindows and its window display method. 5,590,265, Cl. 395-340.000.
- Nalco Chemical Company: See—
Shim, Sang-Hwa; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo; and Lu, Frank F., 5,589,106, Cl. 252-387.000.
- Sivakumar, Ananthasubramanian; Collins, John H.; and Ramesh, Manian, 5,589,075, Cl. 210-727.000.
- Nam, Jong G.: See—
Yuh, Jong H.; and Nam, Jong G., 5,590,085, Cl. 365-230.030.
- Nam, Kee-Soo: See—
Ahn, Kun-Young; Park, Kyung-Ho; Nam, Kee-Soo; and Kang, Sang-Won, 5,589,083, Cl. 216-24.000.
- Nanami, Hideo: See—
Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanami, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399-350.000.
- Nanba, Tomiyuki: See—
Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, 5,589,165, Cl. 424-78.030.
- Nandagiri, Arun: See—
Neill, Paul; Brandt, Lorelei; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, 5,589,163, Cl. 424-70.510.
- Nankoh, Yuichi, to Sumitomo Wiring Systems, Ltd. Connector. 5,588,855, Cl. 474-188.000.
- Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Guede, Louis; and Fearnot, Neal E., to Cook Pacemaker Corporation; and MED Institute. Pulsed doppler probe. 5,588,436, Cl. 128-662.030.
- Nardone, Joseph M.; McTague, Michael J.; and David, Howard S., to Intel Corporation. Method and apparatus for initializing a computer system having central and distributed address decode memory bus resources. 5,590,289, Cl. 395-289.000.
- Narikiyo, Takashi: See—
Arakawa, Hideki; and Narikiyo, Takashi, 5,590,073, Cl. 365-185.080.
- Narva, Kenneth E.: See—
Payne, Jewel; Narva, Kenneth E.; and Fu, Jenny, 5,589,382, Cl. 435-252.500.
- Nass, Rüdiger: See—
Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Ertugrul; König, Theo; and Fister, Dietmar, 5,590,387, Cl. 419-36.000.
- Nataro, James P.: See—
Fasano, Alessio; Levine, Myron M.; Nataro, James P.; and Noriega, Fernando, 5,589,380, Cl. 435-252.300.
- National Institute of Standards and Technology: See—
Siewert, Thomas A.; Dubé, William P.; and Fitting, Dale W., 5,589,690, Cl. 250-390.060.
- National Research Council of Canada: See—
Nehra, Narendra S.; Kartha, Kuty K.; and Chibbar, Ravindra N., 5,589,617, Cl. 800-205.000.
- National Semiconductor Corporation: See—
Bergemont, Albert, 5,590,068, Cl. 365-63.000.
- Bulucea, Constantin; and Grubisich, Michael J., 5,589,409, Cl. 437-31.000.
- Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzit, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800.000.
- Iranmanesh, Ali; Pierce, John M.; and Bergemont, Albert M., 5,589,412, Cl. 437-43.000.
- National Standard Company: See—
Edgington, Robert J.; Stepro, James A.; Wissell, Harold J.; and Lundberg, Scott A., 5,589,301, Cl. 429-234.000.
- Kelly, Patrick J., 5,588,372, Cl. 108-55.100.
- Natori, Akira: See—
Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, 5,589,711, Cl. 257-718.000.

- Natori, Hiroaki; Takei, Hitoshi; Sano, Shoichi; and Tamuki, Shoichi, to Fujitsu Limited. Multipoint television conference system with a multipoint control unit for registering information about TV conference rooms and room groups and allowing a selected room to participate in the TV conference based on registered information. 5,589,873, Cl. 348-15.000.
- Navarrini, Walter; Tortelli, Vito; and Zedda, Alessandro, to Ausimont, S.p.A. Fluorinated polymers and copolymers containing cyclic structures. 5,589,557, Cl. 526-247.000.
- Nayak, Rahul K.: See—
Bodford, Carl A.; Chester, Stephen O.; and Nayak, Rahul K., 5,589,249, Cl. 428-200.000.
- NCR Corporation: See—
Roth, Joseph D.; Obringer, Thomas J.; and Lewis, Monica N., 5,589,276, Cl. 428-488.100.
- Nealon, John L.: See—
Sullivan, Michael J.; Nealon, John L.; and Nesbitt, R. Dennis, 5,588,924, Cl. 473-377.000.
- Neavin, Terence D.: See—
Harms, Michael R.; Foss, Richard J.; Trice, Jennifer L.; and Neavin, Terence D., 5,589,000, Cl. 118-715.000.
- NEC Corporation: See—
Baba, Toshio, 5,589,696, Cl. 257-105.000.
- Ide, Motoki; and Shibayama, Hiroaki, 5,590,401, Cl. 455-38.300.
- Iida, Shuichi; and Oyama, Masayuki, 5,590,117, Cl. 370-248.000.
- Ito, Satoshi, 5,590,101, Cl. 369-32.000.
- Iwasaki, Kiyoshi, 5,589,888, Cl. 348-669.000.
- Kamijo, Atsushi, 5,589,278, Cl. 428-611.000.
- Kamiya, Hiroshi, 5,589,789, Cl. 327-278.000.
- Kasuga, Koji, 5,588,740, Cl. 362-221.000.
- Kawabata, Hiromi; and Takeda, Yutaka, 5,590,279, Cl. 395-185.060.
- Kojima, Susumu, 5,590,397, Cl. 455-33.100.
- Konuma, Kazuo, 5,589,876, Cl. 348-164.000.
- Kubogata, Masayuki, 5,589,282, Cl. 428-694.0ML.
- Matsui, Toshiya, 5,590,203, Cl. 381-4.000.
- Nakashiba, Yasutaka, 5,589,698, Cl. 257-231.000.
- Nakashiba, Satoru, 5,588,831, Cl. 432-159.000.
- Ooi, Yasushi, 5,589,885, Cl. 348-416.000.
- Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, 5,589,711, Cl. 257-718.000.
- Sato, Toshifumi; and Furuya, Yukitsuna, 5,590,404, Cl. 455-53.100.
- Shimizu, Tamio, 5,590,081, Cl. 365-203.000.
- Tachibana, Hiroaki, 5,590,005, Cl. 360-103.000.
- Tsuji, Toshiya; and Yahagi, Masahiko, 5,590,174, Cl. 379-58.000.
- Yamaguchi, Chiseki, 5,589,867, Cl. 347-141.000.
- Yokozawa, Ayumi, 5,590,051, Cl. 364-496.000.
- Necchi Compressori S.r.l.: See—
Salvaneschi, Marco, 5,588,871, Cl. 439-469.000.
- Nedachi, Mitsuyuki. Snap together shift knob construction. 5,588,329, Cl. 74-470.00R.
- Nederlof, Leo, to Alcatel N.V. Method for rerouting a data stream. 5,590,118, Cl. 370-218.000.
- Neely, Michael J.; and Savage, John R., to ITT Automotive Electrical Systems, Inc. High-lift airfoil with bulbous leading edge. 5,588,804, Cl. 416-223.00R.
- Negelen, Emanuel, to Riverwood International Ltd. Interlocking arrangement. 5,588,586, Cl. 229-198.200.
- Nehra, Narendra S.; Kartha, Kuty K.; and Chibbar, Ravindra N., to National Research Council of Canada. Enhanced regeneration system. 5,589,617, Cl. 800-205.000.
- Neidle, Stephen: See—
Edwards, Karen J.; Jarman, Michael; Laughton, Charles A.; Neidle, Stephen; and Harcastle, Ian R., 5,589,500, Cl. 514-428.000.
- Neill, Paul; Brandt, Lorelei; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, to Helene Curtis, Inc. Permanent wave composition and method. 5,589,163, Cl. 424-70.510.
- Nelleor Incorporated: See—
Hollub, Seth D., 5,588,439, Cl. 128-721.000.
- Nelson, Carl T.; and Essaff, Robert, to Linear Technology Corporation. Dual polarity voltage regulator circuits and methods for providing voltage regulation. 5,589,761, Cl. 323-285.000.
- Nelson Irrigation Corporation: See—
Sweet, Frederick J.; and Meyer, Larry P., 5,588,595, Cl. 239-222.170.
- Nelson, Joe B. Self defense ring. 5,588,214, Cl. 30-368.000.
- Nelson, John W.: See—
Castor, Patrick F.; Tsau, Yung-Chun; Kristiansen, Inge B.; and Nelson, John W., 5,590,288, Cl. 395-200.030.
- Nemori, Ryoichi: See—
Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,589,510, Cl. 514-590.000.
- Nemoto, Hirotomi: See—
Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hirotomi; and Yamamoto, Yoshio, 5,588,414, Cl. 123-571.000.
- Nemoto, Peter A.: See—
Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeaux, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37.300.
- Nesbitt, R. Dennis: See—
Sullivan, Michael J.; Nealon, John L.; and Nesbitt, R. Dennis, 5,588,924, Cl. 473-377.000.
- Ness, Richard B. Portable food container and method for storing and consuming dry and liquid food. 5,588,561, Cl. 222-129.000.
- Nestor, John J., Jr.: See—
Krstensky, John L.; Nestor, John J., Jr.; Ho, Teresa H.; Vickery, Brian H.; and Bach, Chinh T., 5,589,452, Cl. 514-12.000.
- Netekoven, William S., to MegaDyne Medical Products, Inc. Fluid flow control device pinch mechanism. 5,588,634, Cl. 251-9.000.
- Neuendorf, Andreas: See—
Kaak, Hartmut; and Neuendorf, Andreas, 5,590,045, Cl. 364-470.100.
- Neuer, Richard; and Stein, Gerhard, to Hoechst Aktiengesellschaft. Aromatic polyamide staple fiber bundles of improved dispersibility in viscous matrices and production of fiber-reinforced composites. 5,589,265, Cl. 428-361.000.
- Neumann, Mathias: See—
Krause, Manfred; Kaufmann, Norbert; and Neumann, Mathias, 5,589,398, Cl. 436-164.000.
- Neumüller, Maria; and Gebhard, Angelika, to Sifa Sitzfabrik GmbH. Control mechanism for the seat carriers of chairs, especially swivel chairs. 5,588,706, Cl. 297-374.000.
- Nevo, Shlomo: See—
Ben Zvi, Guy; Nevo, Shlomo; and Berman, Michael, 5,589,260, Cl. 428-327.000.
- New Southland, Inc.: See—
Hetherington, Ray C., 5,589,119, Cl. 264-129.000.
- New York Air Brake Corporation: See—
Allen, John J., Jr.; and Root, Kevin B., 5,590,042, Cl. 364-426.010.
- New York Blood Center: See—
Lee, Soohye; and Redman, Colvin, 5,589,336, Cl. 435-6.000.
- New York State Electric & Gas Corporation: See—
Mancini, Rick A., 5,588,378, Cl. 110-101.00A.
- Newbury, David: See—
Rizkalla, Emad; and Newbury, David, 5,588,369, Cl. 108-2.000.
- Newcomb, Michael R.: See—
Markin, Rodney S.; and Newcomb, Michael R., 5,589,137, Cl. 422-104.000.
- Newell, Gerald P.: See—
Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401.000.
- Newgard, Ken: See—
Allen, Harvey S., II; Berke, E. William; and Erwin, Gary B., 5,588,398, Cl. 119-822.000.
- Newman, Mark C.: See—
Clark, William A.; Strickland, Carl C., Jr.; and Newman, Mark C., 5,589,808, Cl. 336-92.000.
- Newpark Resources, Inc.: See—
Alexander, Albert H. D.; Ballatine, W. Thomas; Lakey, Leland D.; and Lyon, Frank L., 5,589,603, Cl. 588-250.000.
- News Datacom Ltd.: See—
Nachman, Jacob B.; and Tsuria, Yossef, 5,590,200, Cl. 380-46.000.
- Newton, Dale C. Imaging method and system concatenating image data values to form an integer, and partitioning the integer. 5,590,221, Cl. 382-232.000.
- NeXstar Pharmaceuticals, Inc.: See—
Moynihan, Karen L., 5,589,189, Cl. 424-450.000.
- NexTel Communications: See—
Matsumoto, Tadashi; and Nishioka, Seiji, 5,590,399, Cl. 455-33.300.
- Neyra, Carlos A.; and Sadasivan, Lakshmi, to Rutgers, The State University of New Jersey. *Bacillus licheniformis* producing antifungal agents and uses thereof for control of phytopathogenic fungi. 5,589,381, Cl. 435-252.500.
- NGK Spark Plug Co., Ltd.: See—
Kawaguchi, Kenzo; Takemura, Tetsuya; Matsubara, Hideki; Takagi, Sinya; and Kanda, Atsushi, 5,589,429, Cl. 501-96.000.
- Nguyen, Cau L.: See—
Mehring, Peter A.; and Nguyen, Cau L., 5,590,286, Cl. 395-250.000.
- Nguyen, Clark T.: See—
Lin, Liwei; Nguyen, Clark T.; Howe, Roger T.; and Pisano, Albert P., 5,589,082, Cl. 216-2.000.
- Nguyen, Quang L.: See—
Boussouira, Boudiaf; and Nguyen, Quang L., 5,589,179, Cl. 424-401.000.
- Nguyen, Tue H.: See—
Mohler, Marjorie A.; and Nguyen, Tue H., 5,589,169, Cl. 424-94.200.
- NHK Spring Co. Ltd.: See—
Kitamura, Yoshiharu, 5,588,333, Cl. 74-502.400.
- Niaura, William S.: See—
Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Niaura, William S.; and McKinley, Gareth H., 5,588,509, Cl. 188-267.000.
- Nicholas, Peter M.; Sahatjian, Ronald A.; and Barry, James J., to Boston Scientific Corporation. Drug treatment of diseased sites deep within the body. 5,588,962, Cl. 604-52.000.
- Nichols, Debra J.: See—
Martinez, Sarah B.; Leary, H. Lee, Jr.; and Nichols, Debra J., 5,589,357, Cl. 435-68.100.
- Nichols, James M.; and Coppes, Bryan A., to Infiltrator Systems Inc. Leaching chamber with angled end. 5,588,778, Cl. 405-48.000.
- Nichols, Timothy G. Total body brush shower. 5,588,160, Cl. 4-606.000.
- Nicol, Robin H.; Slater, Martin J.; and Hodgson, Simon T., to Glaxo Wellcome Inc. Dibenzothiazepinone as antiviral agents. 5,589,474, Cl. 514-211.000.

- Nielsen, David A.; Goldman, David; Linnoila, Markku; and Virkkunen, Matti, to United States of America, Health and Human Services, Method for detecting abnormal serotonergic function, 5,589,331, Cl. 435-6.000.
- Nielsen, Marinius K., to I. Krüger Systems A/S, Method of controlling waste water purification plants using multiple control functions, 5,589,068, Cl. 210-614.000.
- Nielsen, Ole C., Data communication system of the field bus type with a twin lead for power supply to connect units and for data transmission between the units, 5,589,813, Cl. 340-310.010.
- Niemela, Van A.; See—
Bowman, Wayne C., and Niemela, Van A., 5,590,032, Cl. 363-15.000.
- Nier, Richard E.; See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Renner, Eric E.; Richardson, Robert R.; Roffe, David B.; Schoonover, Nicholas J.; Snoral, Vincent J.; Stupp, James R., and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Niesen, Randy J.; See—
Becker, Thomas P.; Crass, Matthew M.; Putney, Gordon A.; Niesen, Randy J., and Iwinski, Dean J., 5,589,644, Cl. 73-862.230.
- Nifco, Inc.; See—
Mitomi, Masako; and Hoshino, Ryo, 5,588,569, Cl. 224-153.000.
- Nightingale, William T., to Pacer Technology, Topical patch to reduce fecal contamination during slaughter, 5,588,905, Cl. 452-176.000.
- Nihei, Ryo; Terada, Akihiko; and Kurebayashi, Hidenori, to Fanie Ltd., Gear mechanism improved to remove backlash, 5,588,328, Cl. 74-409.000.
- Nihira, Yoshito; Zhuang, Haoren; and Nomura, Takeshi, to TDK Corporation, Method for preparing magnetite magnetic powder, 5,589,097, Cl. 252-62.590.
- Nihon Bayer Agrochem K.K.; See—
Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seisshi; Wada, Katsuki; Ukiwa, Kazuhiro; Watanabe, Ryo; Ito, Asami, and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000.
- Nihon Densetsu Yakuhin Kabushikigaisha; See—
Yoshida, Nobuyuki, 5,588,396, Cl. 119-252.000.
- Niida, Mitsuki; See—
Murata, Tomohiro; Kunihara, Kenzo; Kawashima, Kazuhiro; and Niida, Mitsuki, 5,590,272, Cl. 395-181.000.
- Niikura, Junji; See—
Hatoh, Kazuhiro; Niikura, Junji, Yasumoto, Eiichi, and Gamou, Takaharu, 5,589,287, Cl. 429-41.000.
- Nikken Chemicals Co., Ltd.; See—
Ukiyaya, Tadashi; and Endoh, Hirotsuka, 5,589,191, Cl. 424-480.000.
- Nikon Corporation; See—
Hozumi, Toshiaki; and Ogawa, Hidehiro, 5,589,907, Cl. 396-287.000.
- Kitajima, Eiichi, 5,589,939, Cl. 356-375.000.
- Kusaka, Yosuke, 5,589,909, Cl. 396-96.000.
- Suenaga, Yutaka, 5,589,988, Cl. 359-752.000.
- Tazawa, Masashi; Fujinawa, Nobuhiro; Matsui, Kumiko; and Suzuki, Maki, 5,589,953, Cl. 358-498.000.
- Uchikawa, Kiyoshi; Suga, Takayuki; and Furusawa, Akira, 5,589,936, Cl. 356-345.000.
- Urata, Keishi; and Nakamura, Toshiyuki, 5,589,904, Cl. 396-55.000.
- Nimbus, Inc.; See—
Taylor, Lynn P.; Le Blanc, Peter W. J. C.; Butler, Kenneth C.; and Maher, Timothy R., 5,588,812, Cl. 417-356.000.
- Nims, Incorporated; See—
Sackner, Marvin A.; and Inman, Dana M., 5,588,425, Cl. 128-632.000.
- Nimura, Wataru, to Casio Computer Co., Ltd., Unwinding apparatus for unwinding tape-like sheet member, 5,588,755, Cl. 400-234.000.
- Ninontuya, Masanobu; See—
Akashi, Ryojiro; Morikawa, Takashi; Ninomiya, Masanobu; and Uematsu, Takashi, 5,589,237, Cl. 428-1.000.
- Nippon Denso Co., Ltd.; See—
Atsumi, Toru; Kamijo, Yasuhiro; Furukawa, Yoshiki; and Matsumura, Naoki, 5,589,678, Cl. 235-472.000.
- Nippon Hoso Kyokai; See—
Tanaka, Yutaka; and Honda, Minoru, 5,590,153, Cl. 375-222.000.
- Nippon Mektron, Limited; See—
Saito, Satoru; Tatsu, Haruyoshi; German, Lev S., deceased, 5,589,559, Cl. 526-247.000.
- Nippon Paint Co., Ltd.; See—
Yamada, Mitsuo; and Nojiri, Hiroyuki, 5,589,527, Cl. 523-414.000.
- Nippon Reinz Co., Ltd.; See—
Fujisawa, Katsuhide; Tahara, Eiichi; and Hida, Tetsuya, 5,588,657, Cl. 277-180.000.
- Nippon Sanso Corporation; See—
Satomi, Yasuhiko; Itoh, Seichi; Otsuka, Eiji; Yamaki, Jun; and Kato, Takashi, 5,588,197, Cl. 29-455.100.
- Nippon Seiko Kabushiki Kaisha; See—
Aramaki, Teruo; and Hamamoto, Magozo, 5,590,225, Cl. 384-527.000.
- Nippon Shinyaku Company, Limited; See—
Chokai, Shoichi; Aoki, Tomiyoshi; and Kimura, Kiyoshi, 5,589,477, Cl. 514-256.000.
- Nippon Telegraph and Telephone Corporation; See—
Takara, Hidehiko; Kawanishi, Sotoki; and Saruwatari, Masatoshi, 5,590,143, Cl. 372-28.000.
- Nippon Telegraph Telephone Corp.; See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53.000.
- Nippondenso Co., Ltd.; See—
Abe, Takahide; and Takaba, Katsumi, 5,590,040, Cl. 364-424.040.
- Kurahashi, Akira; Ando, Hiroshi; Kaneiwa, Toshiyuki; and Hoashi, Yoshiaki, 5,589,930, Cl. 356-5.010.
- Maeda, Noboru, 5,590,036, Cl. 364-184.000.
- Mori, Hiroshi; Tanaka, Masakazu; Mabuchi, Mamoru; and Saito, Makoto, 5,589,143, Cl. 422-171.000.
- Sakakibara, Hisayoshi; Okada, Tomoo; and Ikeda, Tadaaki, 5,588,590, Cl. 236-92.008.
- Nishi, Yumiko; See—
Tomomura, Yukiko; Sakurai, Yoshito; and Nishi, Yumiko, 5,590,180, Cl. 379-112.000.
- Nishida, Hiroto; See—
Ookawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, 5,590,109, Cl. 369-77.200.
- Nishida, Ikiko; See—
Doi, Miwako; Fukui, Mika; Nishida, Ikiko; and Kato, Nobuko, 5,590,268, Cl. 395-326.000.
- Nishida, Masao; See—
Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao, 5,590,412, Cl. 455-82.000.
- Nishihara, Takashi; Ikeda, Toru; Yano, Osamu; and Shirashi, Shuji, to Honda Giken Kogyo Kabushiki Kaisha, System for determining pneumatic tire pressure for motor vehicle, 5,589,815, Cl. 340-444.000.
- Nishijima, Motoaki; See—
Takada, Kazunori; Kondo, Shigeo; Yamamoto, Osamu, and Nishijima, Motoaki, 5,589,298, Cl. 429-218.000.
- Nishikawa, Hiroshi; See—
Nishimura, Osamu; and Nishikawa, Hiroshi, 5,588,842, Cl. 434-307.00A.
- Nishiki, Yoshinori; See—
Shimamura, Takayuki; Nakamatsu, Shuji; Sawamoto, Isao; and Nishiki, Yoshinori, 5,589,052, Cl. 205-349.000.
- Nishimoto, Katsushi; See—
Nakata, Yasuyuki; Yabuki, Akihiko; Yoshida, Yutaka; and Nishimoto, Katsushi, 5,590,244, Cl. 395-95.000.
- Nishimura, Dwight G.; See—
Mani, Sanjay; Nishimura, Dwight G.; Conolly, Steven M., and Pauly, John M., 5,588,431, Cl. 128-653.300.
- Nishimura, Naoki, to Canon Kabushiki Kaisha, Process for producing optical recording medium sputtering method and sputtering target, 5,589,040, Cl. 204-192.260.
- Nishimura, Naoto; See—
Yamada, Kazuo; Mitate, Takehito; Yoneda, Tetsuya; and Nishimura, Naoto, 5,589,299, Cl. 429-218.000.
- Nishimura, Osamu; and Nishikawa, Hiroshi, to Brother Kogyo Kabushiki Kaisha; and Xing Inc., Karaoke control system for a plurality of karaoke devices, 5,588,842, Cl. 434-307.00A.
- Nishioka, Seiji; See—
Matsumoto, Tadashi; and Nishioka, Seiji, 5,590,399, Cl. 455-33.300.
- Nishitani, Keizo; and Suzuki, Hiroshi, to Yazaki Corporation, Meter module assembly, 5,589,715, Cl. 307-10.100.
- Nissan Motor Co., Ltd.; See—
Kitada, Shinichiro, 5,588,498, Cl. 180-65.400.
- Nissanov, Jonathan; See—
Sinclair, Stephen H.; Nissanov, Jonathan; and Gupta, Amitabha, 5,589,897, Cl. 351-223.000.
- Nissei ASB Machine Co., Ltd.; See—
Takada, Minoru; Sato, Koichi; and Yokobayashi, Kazuyuki, 5,589,130, Cl. 264-537.000.
- Nitta, Jun, to Canon Kabushiki Kaisha, Light-emitting apparatus capable of selecting polarization direction, optical communication system, and polarization modulation control method, 5,590,145, Cl. 372-50.000.
- Nitta, Tetsuhito; See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhito; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279.000.
- Nitto Chemical Industry Co., Ltd.; See—
Shimizu, Shigeru; Saitoh, Takashi; Uzawa, Masashi; and Takayanagi, Yasuyuki, 5,589,108, Cl. 252-500.000.
- Nitto Denko Corporation; See—
Chiba, Hiroshi; and Furumori, Kenji, 5,588,250, Cl. 43-114.000.
- Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru, 5,589,390, Cl. 435-307.100.
- Nitz, Larry T.; See—
Downs, Robert C.; Mainquist, James K.; Nitz, Larry T.; and Aldrich, William L., III, 5,588,327, Cl. 74-335.000.
- Niwa, Toshio; See—
Kinoshita, Masafumi; Niwa, Toshio; and Shibata, O., 5,589,541, Cl. 525-66.000.
- NKK Corporation; See—
Yoshimori, Naoto; Watanabe, Toyofumi; and Yamashita, Masaaki, 5,589,279, Cl. 428-623.000.
- Noble, John F.; See—
Abajian, Henry B.; Noble, John F.; and Ilavka, Joseph J., 5,589,460, Cl. 514-17.000.
- Noble, Scott L.; See—
Eldridge, Robert A.; Unrein, Ed J.; Brown, David L.; and Noble, Scott L., 5,588,728, Cl. 312-332.100.

- Nobuhara, Masahiro; See—
Morishita, Hideaki; Kanamori, Toshinori; and Nobuhara, Masahiro, 5,589,360, Cl. 435-69.100.
- Noda, Hidenobu, to Sony Corporation, Tracking servo circuit for an optical disc player, 5,590,103, Cl. 369-44.290.
- Noda, Koji; Fujikawa, Hisayoshi; Yamashita, Katsuji; and Taga, Yasunori, to Kabushiki Kaisha Toyota Chuo Kenkyusho, Electroluminescent element including a dielectric film of tantalum oxide and an oxide of either indium, tin, or zinc, 5,589,733, Cl. 313-509.000.
- Noe, James P.; See—
Bodley, James W.; Noe, James P.; and Hann, Daniel, 5,588,253, Cl. 47-41.120.
- Noetzel, Guenter, to Robert Bosch GmbH, Method for selecting signals from navigation satellites, 5,589,836, Cl. 342-357.000.
- NOF Corporation; See—
Suzuki, Masao; Saito, Koichi; and Nakata, Masahide, 5,589,515, Cl. 514-784.000.
- Noguchi, Noboru, to Toyota Jidosha Kabushiki Kaisha, Braking system having mechanism for controlling resistance of fluid flow from pump into low-pressure brake cylinder depending upon pressure difference between low-pressure and high-pressure brake cylinders, 5,588,722, Cl. 303-186.000.
- Noguchi, Takanobu; See—
Ohnishi, Toshihiro; Noguchi, Takanobu; and Doi, Shuji, 5,589,320, Cl. 430-321.000.
- Nojiri, Hiroyuki; See—
Yamada, Mitsuo; and Nojiri, Hiroyuki, 5,589,527, Cl. 523-414.000.
- NOK Corporation; See—
Matsushima, Noboru, 5,588,656, Cl. 277-35.000.
- Noker, Friedolin F.; See—
Reinecke, Holger; Unal, Nezi; Peters, Ralf-Peter; Bartels, Frank; and Noker, Friedolin F., 5,588,597, Cl. 239-553.500.
- Nokia Mobile Phones Ltd.; See—
Latva-Aho, Matti, 5,589,795, Cl. 327-553.000.
- Ostman, Kjell, 5,590,160, Cl. 375-367.000.
- Sroka, Peter; and Harrison, Peter D., 5,590,411, Cl. 455-78.000.
- Nokia Telecommunications OY; See—
Loppönen, Jussi, 5,590,400, Cl. 455-34.200.
- Peltola, Jukka; and Koponen, Pekka, 5,590,415, Cl. 455-115.000.
- Nomura, Takeshi; See—
Nihira, Yoshito; Zhuang, Haoren; and Nomura, Takeshi, 5,589,097, Cl. 252-62.590.
- Nomura, Toshiyuki; Tsujioka, Yuji; and Osuga, Naohiro, to Horiba, Ltd., Probe cover for use in tympanic thermometer, 5,588,748, Cl. 374-158.000.
- Nonaka, Osamu, to Olympus Optical Co., Ltd., Autofocusing apparatus for camera having multiple ranging device, 5,589,911, Cl. 396-80.000.
- Nonomura, Keisaku; See—
Shigeta, Mitsuhiko; and Nonomura, Keisaku, 5,589,961, Cl. 349-41.000.
- Nordard Corporation; See—
West, Guy J.; and Mahany, Ronald L., 5,590,346, Cl. 395-800.000.
- Norden, K. Solveig E.; See—
Färnstrand, Per-Åke; Sjödin, Lars T.; Lindström, Lars-Åke; and Norden, K. Solveig E., 5,589,031, Cl. 162-65.000.
- Norden, Michael J., Method for treating borderline personality disorder with serotonin re-uptake blockers, 5,589,512, Cl. 514-651.000.
- Nordgaard, Joseph K.; See—
Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54.100.
- Nordica S.p.A.; See—
Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergamin, Mirco; and Canil, Gilberto, 5,588,228, Cl. 36-118.200.
- Nordson Corporation; See—
Geul, Herman R., 5,589,226, Cl. 427-286.000.
- Noriega, Fernando; See—
Fasano, Alessio; Levine, Myron M.; Nataro, James P.; and Noriega, Fernando, 5,589,380, Cl. 435-252.300.
- Normington, Peter; See—
Higgins, H. Dan; and Normington, Peter, 5,589,781, Cl. 324-755.000.
- Noro, Masayuki; See—
Takeshima, Taku; Noro, Masayuki; and Saito, Tomokatsu, 5,590,255, Cl. 395-141.000.
- Norsk Hydro a.s.; See—
Manjunath, Konanur; Paulsen, Knut A.; and Ognedal, Leiv B., 5,588,787, Cl. 406-85.000.
- North Carolina State University; See—
Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76.000.
- North Houston Machine, Inc.; See—
Johnson, George P., Jr., 5,588,772, Cl. 403-355.000.
- Northern Telecom Ltd.; See—
Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J., 5,590,189, Cl. 379-356.000.
- Northrup, M. Allen; Mariella, Raymond P., Jr.; Carrano, Anthony V.; and Balch, Joseph W., to University of California, Regents of the Silicon-based sleeve devices for chemical reactions, 5,589,136, Cl. 422-102.000.
- Norton Company; See—
Simpson, Matthew, 5,589,232, Cl. 427-577.000.
- Novacor Chemicals (International) S.A.; See—
Zboril, Vaclav G.; and Brown, Stephen J., 5,589,555, Cl. 526-64.000.
- Novak, James P., Method of manufacture of polyester-chip products for casting artificial-stone articles, 5,588,599, Cl. 241-23.000.
- Novamont S.p.A.; See—
Bastoli, Catia; Bellotti, Vittorio; Del Tredici, Gianfranco; and Rallis, Angelos, 5,589,518, Cl. 521-55.000.
- Novo Nordisk A/S; See—
Lau, Jesper; and Knutsen, Lars J. S., 5,589,467, Cl. 514-46.000.
- Nozaki, Shinya, to Zexel Corporation, Variable injection hole type fuel injection nozzle, 5,588,412, Cl. 123-496.000.
- Nozu, Rikuro, Fluid energy conversion apparatus, 5,588,293, Cl. 60-398.000.
- NPS Pharmaceuticals, Inc.; See—
Harcourtman, Alec T., 5,589,351, Cl. 435-29.000.
- NSK Ltd.; See—
Ohsumi, Sadanori, 5,588,609, Cl. 242-376.000.
- Osawa, Nobuyuki; and Katahira, Masayuki, 5,588,750, Cl. 384-15.000.
- Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshifumi; and Harakata, Mutsumu, 5,588,611, Cl. 242-381.100.
- NTT Mobile Communications Network Inc.; See—
Matsumoto, Tadashi; and Nishioka, Seiji, 5,590,399, Cl. 455-33.300.
- Sawashita, Mamoru; and Adachi, Fumiaki, 5,590,409, Cl. 455-69.000.
- Nubel, Philip O.; and Yokelson, Howard B., to Amoco Corporation, Process for preparing difunctional telechelic linear non-crosslinked polyolefins, 5,589,548, Cl. 525-247.000.
- Nubel, Philip O.; See—
Yokelson, Howard B.; Nubel, Philip O.; and Behrends, Raymond T., 5,589,543, Cl. 525-131.000.
- Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., to Datacard Corporation, System and method for cleaning and producing data bearing cards, 5,588,763, Cl. 400-700.000.
- Nuclear Fuel Services, Inc.; See—
Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Kerry D., 5,590,391, Cl. 423-253.000.
- Numata, Shigeo, to Izumi Corporation, Driver side air bag cover mounting assembly, 5,588,666, Cl. 280-728.200.
- Nunotani, Shinji; See—
Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagiya, Satoshi; and Baba, Yoshiro, 5,589,421, Cl. 437-225.000.
- NuPipe, Inc.; See—
Stekette, Campbell H., Jr., 5,589,131, Cl. 264-568.000.
- Nurture, Inc.; See—
Potter, Richard C., 5,589,195, Cl. 424-499.000.
- NV Raychem SA; See—
Van Beersel, Jozef; and John, Robin C., 5,589,019, Cl. 156-184.000.
- Nycomed Imaging AS; See—
Sandnes, Rolf W.; Undheim, Kjell; Gacek, Michel; and Vasilevskis, Janis, 5,589,595, Cl. 540-474.000.
- Nydegger, Daniel L.; See—
Anderson, Thomas O.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474.130.
- Oae, Yoshihisa; See—
Abe, Tomohiko; Yasuda, Hiroshi; Sakamoto, Kiichi; and Oae, Yoshihisa, 5,590,048, Cl. 364-489.000.
- Oatey Co.; See—
Rodriguez, Roberto; and Shroka, Edward T., 5,588,267, Cl. 52-219.000.
- Oba, Hidehiro; See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Obaidi, Hemayatullah S., Head and neck protector for children, 5,588,445, Cl. 128-846.000.
- O'Brien, Donogh P.; Vehar, Gordon A.; and Wilcox, Josiah N., to Genentech, Inc., Method and therapeutic compositions for the treatment of myocardial infarction, 5,589,173, Cl. 424-145.100.
- O'Brien, Michael K.; See—
Grasso, Robert P.; O'Brien, Michael K.; and Shannon, Paul J., 5,589,100, Cl. 252-299.010.
- Obringer, Thomas J.; See—
Roth, Joseph D.; Obringer, Thomas J.; and Lewis, Monica N., 5,589,276, Cl. 428-488.100.
- Obst, Frank; See—
Ströter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegmund, Rainer, 5,588,326, Cl. 74-50.000.
- Oce-Nederland, B.V.; See—
Markies, Peter R.; and Miedema, Mark, 5,589,921, Cl. 399-297.000.
- Ochiai, Akihiko, to Sony Corporation, Process for fabricating semiconductor device having a multilevel interconnection, 5,589,419, Cl. 437-795.000.
- Ochs, Eric W., Dental instrument holder, 5,588,689, Cl. 294-118.000.
- O'Connor, John; See—
Byrne, Thomas; and O'Connor, John, 5,588,168, Cl. 5-636.000.
- O'Connor, John V.; See—
Hotchkiss, Adair J.; O'Connor, John V.; and Spellman, Michael W., 5,589,361, Cl. 435-69.100.

- Oct Co. Ltd.: See—
Chiba, Hiromi; and Furumori, Kenji, 5,588,250, Cl. 43-114.000.
- Ocular Instruments, Inc.: See—
Mainster, Martin A.; Crossman, Janet L.; and Johnson, Robert D., 5,589,896, Cl. 351-219.000.
- Odagiri, Masaru: See—
Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.
- Odaka, Shun'ichi: See—
Sawada, Kiyoshi; and Odaka, Shun'ichi, 5,589,086, Cl. 219-69.160.
- Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seiichirou, to Mitsubishi Material Corp. Process for producing cement cutting tools having both longitudinal and granular crystal structures, 5,589,223, Cl. 427-248.100.
- Odds, Frank C.: See—
Venet, Marc G.; Guillemont, Jérôme E. G.; Vernier, Daniel F. J.; and Odds, Frank C., 5,589,484, Cl. 514-314.000.
- Odenthal, Heinz F., to Ostma Maschinenbau GmbH: See—
Urban, Dieter, 5,588,285, Cl. 53-534.000.
- Odonot, Charles, to SGS-Thomson Microelectronics, S.A. Cell for shift register, 5,589,787, Cl. 327-202.000.
- Odum, Robert W.: See—
Jen Wu, Kuang; and Odum, Robert W., 5,589,685, Cl. 250-282.000.
- Oeco-Team Unternehmens- und Umweltberatung GmbH: See—
Urban, Dieter, 5,588,374, Cl. 108-56.300.
- Office Ishikawa Co., Ltd.: See—
Ishikawa, Hiromi, 5,588,749, Cl. 383-4.000.
- Offset Studios Limited: See—
Leamy, Patrick; Leamy, Alan; and Gillin, John, 5,590,245, Cl. 395-118.000.
- Ogata, Shin: See—
Maruyama, Haruyoshi; Ogata, Shin; and Tsumiyama, Yoshinori, 5,588,388, Cl. 114-271.000.
- Ogawa, Hidehiro: See—
Hozumi, Toshiaki; and Ogawa, Hidehiro, 5,589,907, Cl. 396-287.000.
- Ogawa, Kazufumi, to Matsushita Electric Industrial Co., Ltd. Nonlinear optical material and its method of manufacture, 5,589,235, Cl. 428-1.000.
- Ogawa, Kiyoshi: See—
Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshifumi; and Haraoka, Mutsumu, 5,588,611, Cl. 242-381.100.
- Ogawa, Masaaki: See—
Ishikawa, Hajime; Ogawa, Masaaki; Hasegawa, Ryosuke; and Yamamoto, Hideo, 5,589,205, Cl. 425-526.000.
- Ogawa, Masanori: See—
Yamada, Shun; Ogawa, Masanori; and Unosawa, Kazuomi, 5,589,225, Cl. 427-212.000.
- Ogawa, Yasumichi: See—
Kakiuchi, Daisuke; Ogawa, Yasumichi; Yasumatsu, Hifumi; and Shiraga, Kazutaka, 5,588,469, Cl. 138-137.000.
- Ogawa, Yasushige: See—
Akaogi, Takao; Yoshida, Masanobu; Ogawa, Yasushige; Kasa, Yasushi; and Kawamura, Shouichi, 5,590,074, Cl. 365-185.220.
- Ogi, Hiromi: See—
Akimoto, Yoshiaki; Tanaka, Hideo; Ogi, Hiromi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, 5,590,243, Cl. 395-23.000.
- Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, to Hitachi, Ltd. Cathode ray tube display, 5,589,883, Cl. 348-379.000.
- Ogita, Yasuhisa; and Kato, Toshikazu, to Tosoh, Corporation. Polyphenylene sulfide resin composition and light reflective molded article, 5,589,524, Cl. 523-212.000.
- Ognedal, Leiv B.: See—
Manjunath, Konanur; Paulsen, Knut A.; and Ognedal, Leiv B., 5,588,787, Cl. 406-85.000.
- Ogura, Takashi: See—
Okabayashi, Katsushiro; Ogura, Takashi; and Yoshida, Masaru, 5,589,732, Cl. 313-506.000.
- Ogushi, Masaki; Takeuchi, Osamu; Yamamura, Ikuo; Iura, Toru; and Yoshida, Hironobu, to Ishikawajima-Harima Iukogyo Kabushiki Kaisha. Electric arc melting furnace, 5,590,150, Cl. 373-9.000.
- Ogusu, Mikio; and Fujiwara, Kazunobu, to Yamaha Corporation. Information recording/reproducing technique to record plural-channel information for subsequent simultaneous reproduction, 5,590,100, Cl. 369-32.000.
- Oh, PahngRoc: See—
Kim, Sang K.; Oh, PahngRoc; and Lee, Hong J., 5,588,717, Cl. 303-84.200.
- Ohara, Tetsuo. Method of an apparatus for real-time nanometer-scale position measurement of the sensor of a scanning tunneling microscope or other sensor scanning atomic or other undulating surfaces, 5,589,686, Cl. 250-306.000.
- Ohashi, Motoaki: See—
Tsujihara, Kenji; Hashiyama, Tomiki; Ohashi, Motoaki; and Nakanishi, Noriyuki, 5,589,502, Cl. 514-449.000.
- Ohashi, Ryota: See—
Sakakura, Shinya; Ohashi, Ryota; and Sakikawa, Shigenori, 5,588,294, Cl. 60-464.000.
- Ohba, Toshimitsu: See—
Yoneda, Norihiro; Ohba, Toshimitsu; Furuya, Reiko; and Shikata, Kiyotaka, 5,590,183, Cl. 379-142.000.
- Ohguchi, Yuji, to Toko Kabushiki Kaisha. Adaptive quantization controlled by scene change detection, 5,589,884, Cl. 348-405.000.
- Ohio State University Research Foundation, The: See—
Rapp, Robert A.; Wang, Ge; and Pangestuti, Endang, 5,589,220, Cl. 427-126.100.
- Ohira, Hideo: See—
Murakami, Tokumichi; and Ohira, Hideo, 5,590,291, Cl. 395-566.000.
- Ohira, Kouichi: See—
Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, 5,589,001, Cl. 118-722.000.
- Ohishi, Hiroyuki: See—
Kato, Eiichi; Momota, Makoto; and Ohishi, Hiroyuki, 5,589,308, Cl. 430-49.000.
- Ohki, Kazuhiro: See—
Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34.000.
- Ohki, Mitsuhiro, to Sony Corporation. Two-dimensional discrete cosine transformation system, two-dimensional inverse discrete cosine transformation system, and digital signal processing apparatus using same, 5,590,066, Cl. 364-725.000.
- Ohkubo, Mitsuru: See—
Kojiri, Katsuhisa; Kondo, Hisao; Arakawa, Hiroharu; Ohkubo, Mitsuru; and Suda, Hiroyuki, 5,589,365, Cl. 435-85.000.
- Ohkura, Kengo: See—
Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu, 5,589,281, Cl. 428-688.000.
- Ohmart, Dale V.; Benitez, Willie B., III; Marrero, Deogracias D.; and Mirizzi, Douglas J., to Texas Instruments Incorporated. Method for final testing of semiconductor devices, 5,589,765, Cl. 324-158.100.
- Ohmi, Tadashi. System for supplying ultrapure water and method of washing substrate, and system for producing ultrapure water and method of producing ultrapure water, 5,589,005, Cl. 134-30.000.
- Ohmizu, Akimasa: See—
Uriyu, Katsuhiko; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, 5,589,516, Cl. 514-2.000.
- Ohnishi, Hiroshi: See—
Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155.000.
- Ohnishi, Toshihiro; Noguchi, Takanobu; and Doi, Shuji, to Sumitomo Chemical Company, Limited. Polymeric fluorescent substance and organic electroluminescence devices using the same, 5,589,320, Cl. 430-321.000.
- Ohnmacht, Cyrus J., Jr.: See—
Shenoi, Ashokkumar B.; Jacobs, Robert T.; Miller, Scott C.; Ohnmacht, Cyrus J., Jr.; and Veale, Chris A., 5,589,489, Cl. 514-323.000.
- Ohno, Wataru: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Ohsawa, Koji: See—
Sato, Yutaka; Morita, Koichi; Fujimoto, Shuzo; Ichihashi, Satoru; and Ohsawa, Koji, 5,588,208, Cl. 29-888.044.
- Ohsumi, Sadanori, to NSK Ltd. Seat belt winding device, 5,588,609, Cl. 242-376.000.
- Ohtsuka, Masao; Yamakawa, Teruji; and Maruyama, Tetsuo, to Fujitsu Limited. Rewritable storage apparatus using first and second bias magnetic fields, 5,590,096, Cl. 369-13.000.
- Ohtsuka, Takashi: See—
Itoyama, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yuji; Toyomura, Fumitaka; and Ohtsuka, Takashi, 5,589,006, Cl. 136-248.000.
- Ohyaba, Takashi: See—
Koyano, Shinji; Kogure, Koushiro; Ohyaba, Takashi; Sakakibara, Makoto; and Hanayama, Katsutoshi, 5,590,208, Cl. 381-154.000.
- Oikawa, Saburo: See—
Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, 5,589,962, Cl. 349-46.000.
- Okabe, Hideaki; Suzuki, Eiji; Kogure, Masao; and Saito, Takanori, to Lintec Corporation. Gel pharmaceutical formulation for local anesthesia, 5,589,192, Cl. 424-486.000.
- Okabe, Shotaro: See—
Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249.000.
- Okada, Tatsuya: See—
Kaite, Osamu; Okada, Tatsuya; and Kokuga, Toshiharu, 5,589,755, Cl. 320-21.000.
- Okada, Tetsuhiko: See—
Kondo, Nobukazu; Kaneko, Seiji; Gemma, Hideaki; Okada, Tetsuhiko; Komori, Kazuhiko; and Okazawa, Koichi, 5,590,290, Cl. 395-298.000.
- Okada, Tomoo: See—
Sakakibara, Hisayoshi; Okada, Tomoo; and Ikeda, Tadaaki, 5,588,590, Cl. 236-92.00B.
- Okada, Tuneko: See—

- Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tuneko, 5,590,062, Cl. 364-578.000.
- Okada, Yoshikatsu: See—
Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, 5,589,711, Cl. 257-718.000.
- Okamoto, Akio: See—
Mizuno, Hiroyuki; Okamoto, Akio; and Kubo, Suehiro, 5,588,409, Cl. 123-339.110.
- Okamoto, Hiroshige: See—
Komiya, Kyosuke; Kawakami, Yoshifumi; and Okamoto, Hiroshige, 5,589,564, Cl. 528-196.000.
- Okamoto, Yasuhiro: See—
Yoshida, Ryuichi; Okamoto, Yasuhiro; and Kuwana, Minoru, 5,589,723, Cl. 310-328.000.
- Okano, Hidenobu; and Watanabe, Katsunori, to Toyota Gosei Co., Ltd. Apparatus for molding polyurethane foam, 5,589,202, Cl. 425-73.000.
- Okano, Keiji: See—
Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114.000.
- Okamura, Tsuneo: See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, 5,589,735, Cl. 313-638.000.
- Okarma, Thomas B.: See—
Lebkowski, Jane S.; McNally, Maureen A.; and Okarma, Thomas B., 5,589,377, Cl. 435-240.200.
- Okazaki, Hidetsugu: See—
Yoshida, Masami; and Okazaki, Hidetsugu, 5,588,697, Cl. 297-173.000.
- Okazaki, Sadayuki: See—
Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.
- Okazaki, Toru: See—
Suzuki, Teruhiko; Yagasaki, Yoichi; Sudo, Tatsuya; and Okazaki, Toru, 5,590,139, Cl. 371-49.100.
- Okazawa, Koichi: See—
Kondo, Nobukazu; Kaneko, Seiji; Gemma, Hideaki; Okada, Tetsuhiko; Komori, Kazuhiko; and Okazawa, Koichi, 5,590,290, Cl. 395-298.000.
- Okibayashi, Katsushiro; Ogura, Takashi; and Yoshida, Masaru, to Sharp Kabushiki Kaisha. Color thin film electroluminescence panel, 5,589,732, Cl. 313-506.000.
- Okorocho, Livyn O.: See—
Conlon, Sean P.; Oureshi, Saleem U.; Hibner, John A.; Okorocho, Livyn O.; and Bishop, Gregory D., 5,588,581, Cl. 227-176.100.
- Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu, to Sumitomo Electric Industries, Ltd. Stabilized carbon cluster conducting or superconducting material, process for producing the same, device using carbon cluster, and process for producing the device, 5,589,281, Cl. 428-688.000.
- Okuda, Ryosuke, to Mitsubishi Denki Kabushiki Kaisha. Device for aid in integrated circuit design that reduces the number of cells in a circuit representation, 5,590,050, Cl. 364-490.000.
- Okui, Yoshihiro: See—
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218.000.
- Okuma, Ikuo: See—
Yamasaki, Tatsuo; Okuma, Ikuo; and Onishi, Ken, 5,589,994, Cl. 360-15.000.
- Okuno, Yoshinobu; Isegawa, Yuji; Sasao, Fuyoko; and Ueda, Shigeharu, to Takara Shuzo Co., Ltd. Anti-human influenza virus antibody, 5,589,174, Cl. 424-147.100.
- Okuyama, Satoru, to NEC Corporation. Furnace system equipped with protected combustion nozzle used in fabrication of semiconductor device, 5,588,831, Cl. 432-159.000.
- Olin Corporation: See—
Geiger, Jon R.; and Trotz, Samuel L., 5,589,342, Cl. 435-6.000.
- Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurino D., to University of Utah Research Foundation. Process and primers for identifying nucleic acids encoding A-lineage conotoxin peptides, 5,589,340, Cl. 435-6.000.
- Olivier, Hélène: See—
Chauvin, Yves; and Olivier, Hélène, 5,589,601, Cl. 585-513.000.
- Olson, Brent K.: See—
Storey, J. Kirk; and Olson, Brent K., 5,588,670, Cl. 280-730.200.
- Olson, Otis J.: See—
Braun, Eugene R.; and Olson, Otis J., 5,588,516, Cl. 192-48.910.
- Olumpus Optical Co., Ltd.: See—
Kobayashi, Hiroyoshi, 5,589,846, Cl. 345-8.000.
- Olympus Optical Co., Ltd.: See—
Fujimoto, Hiroshi, 5,588,434, Cl. 128-660.070.
- Iketaki, Yoshinori, 5,590,168, Cl. 378-43.000.
- Ito, Hiroshi, 5,588,980, Cl. 65-223.000.
- Nonaka, Osamu, 5,589,911, Cl. 396-80.000.
- Shibata, Hironori, 5,589,986, Cl. 359-684.000.
- Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Omnigene, Inc.: See—
Sloma, Alan; Rufo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice, 5,589,383, Cl. 435-252.310.
- Omura, Kunihiko: See—
Aoki, Mikiyuki; and Omura, Kunihiko, 5,589,871, Cl. 347-237.000.
- Onishi, Keiji: See—
Taguchi, Yutaka; Eda, Kazuo; Seki, Shun-ichi; and Onishi, Keiji, 5,589,806, Cl. 333-193.000.
- Onishi, Ken: See—
Yamasaki, Tatsuo; Okuma, Ikuo; and Onishi, Ken, 5,589,994, Cl. 360-15.000.
- Onishi, Toshiyuki: See—
Mori, Atsushi; Naito, Osamu; Onishi, Toshiyuki; Nakamura, Hitoshi; and Iida, Kouzo, 5,589,146, Cl. 423-237.000.
- Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279.000.
- Onishi, Yasushi; and Saiki, Yoshiharu, to Fanuc Ltd. Sequence program edit system for inserting additional graphic elements and for automatically inserting vertical connector lines, 5,590,253, Cl. 395-133.000.
- Oono, Kazuaki: See—
Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Oono, Kazuaki, 5,589,924, Cl. 399-350.000.
- Oono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, to Fuji Immunopharmaceuticals Corp. Method for inhibiting retroviral infection by administering a naphthalenesulfonic acid compound, 5,589,510, Cl. 514-590.000.
- Oono Pharmaceutical Co., Ltd.: See—
Hamana, Nobuyuki; Takahashi, Kanji; and Tokumoto, Hidekado, 5,589,496, Cl. 514-374.000.
- Oono, Yukio; and Kikuyama, Seiichiro, to Mitsubishi Denki Kabushiki Kaisha. Sensor drive circuit, 5,589,778, Cl. 324-654.000.
- Onodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Tetsuo; and Itoh, Shigeo, to Futaba Denshi Kogyo Kabushiki Kaisha. Field emission type display device, 5,589,738, Cl. 315-169.100.
- Onozaki, Manabu: See—
Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsura, Yasuhiro, 5,590,355, Cl. 395-800.000.
- Onstad, Bradley K.: See—
Hall, Robert T., II; and Onstad, Bradley K., 5,589,507, Cl. 514-557.000.
- Ontario Crippled Children's Centre: See—
Hart, David, 5,588,456, Cl. 135-67.000.
- Ooba, Hideki, to Kabushiki Kaisha Plex. Doll toy head rotation device, 5,588,898, Cl. 446-321.000.
- Ooi, Yasushi, to NEC Corporation. Moving picture coding and decoding circuit, 5,589,885, Cl. 348-416.000.
- Ookawa, Akemi: See—
Iwasaki, Shinichiro; Sugiyama, Masanori; Umemura, Chiaki; Ookawa, Akemi; and Takahashi, Hisayoshi, 5,589,752, Cl. 318-701.000.
- Ookawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, to Matsushita Electric Industrial Co. Disc apparatus, 5,590,109, Cl. 369-77.200.
- Oota, Norio: See—
Kashiwakura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Itsu; Oota, Norio; and Sugiyama, Hisanori, 5,590,097, Cl. 369-13.000.
- Oowaki, Yukihito: See—
Hasagawa, Takehiro; and Oowaki, Yukihito, 5,590,080, Cl. 365-201.000.
- OP-D-OP, Inc.: See—
Landis, Timothy J.; and Perry, Scott M., 5,588,836, Cl. 433-93.000.
- Opl, Frank G.: See—
Tkach, Peter V.; and Opl, Frank G., 5,589,201, Cl. 425-66.000.
- Orbital Engine Company Pty. Limited: See—
Ahern, Steven R., 5,588,415, Cl. 123-676.000.
- Origi, Ambrogio; and Pécis, Silver. Boot for shod animal's hooves, 5,588,288, Cl. 54-82.000.
- Origin Medsystems, Inc.: See—
Buchin, Michael P., 5,589,874, Cl. 348-72.000.
- Orii, Ryuji: See—
Kano, Jiro; Orii, Ryuji; Horinouchi, Yuzo; and Ito, Mutsuhiro, 5,589,150, Cl. 423-338.000.
- Oritsuki, Ryoji: See—
Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, 5,589,962, Cl. 349-46.000.
- Ormco Corporation: See—
Farzin-Nia, Farokh, 5,588,832, Cl. 433-4.000.
- Orinstein, Leonard, to Bayer Corporation. Unsupervised neural network classification with back propagation, 5,590,218, Cl. 382-157.000.
- Osada, Akira: See—
Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seiichirou, 5,589,223, Cl. 427-248.100.
- Osada, Torachika: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87.000.

Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, to Sumitomo Electric Industries, Ltd.; Nippon Telegraph Telephone Corp.; and Sumiden Opcom Ltd. Optical connector apparatus. 5,590,227, Cl. 385-53.000.

Osa University: See—

Mori, Hiroto; and Yasuda, Hidehiro. 5,589,234, Cl. 427-597.000.

Osawa, Nobuyuki; and Katahira, Masayuki, to NSK Ltd. Ball retainer with inner seal for linear guide apparatus. 5,588,750, Cl. 384-15.000.

Osborn, Charles; Medema, Robert M.; and Ruter, Andrew K., to Grand Haven Stamped Products. Shifter with means for actuating cable to key mechanism. 5,588,934, Cl. 477-96.000.

Osborne, Shelby M., to FireKing International, Inc. Door lock. 5,588,318, Cl. 70-469.000.

Osgood, Edwin B.; and Shaar, Casey S., to Photon Kinetics, Inc. Optical fiber test instrument with mechanically positioned attenuator. 5,589,933, Cl. 356-73.100.

O'Shaughnessy, Timothy G.; and Brown, David G., to American Microsystems, Inc. Circuit for detecting the absence of an external component. 5,589,802, Cl. 331-44.000.

Oshiba, Takeo: See—

Etoh, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirofumi; Sakimura, Tomoo; Suzuki, Tomoko; and Kinoshita, Akira. 5,589,314, Cl. 430-126.000.

Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, to Canon Kabushiki Kaisha. Process cartridge, assembling method therefor and electrophotographic apparatus. 5,589,918, Cl. 399-114.000.

Oshima, Katsuyuki: See—

Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo. 5,589,434, Cl. 503-227.000.

Oshita, Kazuhito: See—

Tani, Hiroji; and Oshita, Kazuhito. 5,588,983, Cl. 75-354.000.

Osinski, Mark A.; and Teadt, Donald D., to Eaton Corporation. Throttle control for automated mechanical transmission. 5,588,935, Cl. 477-107.000.

Osmak, Douglas J.: See—

Gandhi, Umesh N.; and Osmak, Douglas J., 5,588,692, Cl. 296-146.700.

Osram Sylvania Inc.: See—

Patrician, Thomas J., and Martin, Harry D., III. 5,590,386, Cl. 419-20.000.

Ostermann, Elinborg: See—

Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castano, Maria J.; Stratawa, Christian; and Hauptmann, Rudolf. 5,589,371, Cl. 435-189.000.

Ostma Maschinenbau GmbH: See—

Odenhal, Heinz F., 5,588,285, Cl. 53-534.000.

Ostman, Kjell, to Nokia Mobile Phones Ltd. Symbol and frame synchronization in both a TDMA system and a CDMA. 5,590,160, Cl. 375-367.000.

Osuga, Naohiro: See—

Nomura, Toshiyuki; Tsujioka, Yuji; and Osuga, Naohiro. 5,588,748, Cl. 374-158.000.

Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshifumi; and Haraoka, Mutsu, to NSK Ltd.; and Toyota Jidosha Kabushiki Kaisha. Retractor with a clamping mechanism. 5,588,611, Cl. 242-381.100.

Ota, Takaaki, to Sony Corporation; and Sony Electronics, Inc. Satellite antenna with adjustment guidance system. 5,589,841, Cl. 343-760.000.

Otsuka, Eiji: See—

Satomi, Yasuhiko; Itoh, Seiichi; Otsuka, Eiji; Yamaki, Jun; and Kato, Takashi. 5,588,197, Cl. 29-455.100.

Otsuka, Kenji; Fukuda, Hideki; and Arakawa, Satoshi, to Japan Pionics Co., Ltd. Process for purifying halogen-containing gas. 5,589,148, Cl. 423-240.005.

Otsuka, Yasumasa: See—

Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki. 5,589,924, Cl. 399-350.000.

Ott, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heilmann, Ulrich; and Gilbert, John, to BASF Lacke + Farben, AG. Method of coating electrically conductive substrates, aqueous electrodrop paints, process for the preparation of an aqueous dispersion of crosslinked polymer micro-particles and dispersions prepared by this process. 5,589,049, Cl. 204-504.000.

Oten, Burghard: See—

Rubeling, Gunter; and Oten, Burghard. 5,588,837, Cl. 433-172.000.

Ouchi, Minoru: See—

Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru. 5,589,390, Cl. 435-307.100.

Oureshi, Saleem U.: See—

Conlon, Sean P.; Oureshi, Saleem U.; Hibner, John A.; Okorocho, Livyn O.; and Bishop, Gregory D., 5,588,581, Cl. 227-176.100.

Outboard Marine Corporation: See—

Bailey, Francis V., 5,588,392, Cl. 114-357.000.

Owens-Illinois Glass Container Inc.: See—

Eilers, Wayne E., 5,588,981, Cl. 65-241.000.

Oyama, Jun: See—

Uchida, Naohiro; Miura, Masao; Oyama, Jun; Kuboyama, Katsunori; and Asakawa, Koji. 5,589,672, Cl. 218-34.000.

Oyama, Masayuki: See—

Iida, Shuichi; and Oyama, Masayuki. 5,590,117, Cl. 370-248.000.

Oz, Oved: See—

Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzri, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto. 5,590,357, Cl. 395-800.000.

Ozeki, Jiro, to Shide Corporation. Optical recording disc storing device. 5,588,528, Cl. 206-308.100.

PAC/SCAN, Inc.: See—

Robinson, Donald G.; Geatz, Michael W.; and Corcoran, Michael J., 5,589,820, Cl. 340-572.000.

Pacer Technology: See—

Nightingale, William T., 5,588,905, Cl. 452-176.000.

Packard Hughes Interconnect Company: See—

Gibola, Norbert; and Ghara, Mehrad. 5,590,228, Cl. 385-56.000.

Rudoy, Edward; and Szalay, John S., 5,588,884, Cl. 439-845.000.

Paddison, Richard L., to General Motors Corporation. Steering axle. 5,588,660, Cl. 280-95.100.

Padmanabhan, Vasant: See—

Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Goode, Louis; and Fearnor, Neal E., 5,588,436, Cl. 128-662.030.

Pages, Etienne; Ropars, Claude; and Baillieu, Christophe, to Fondation Nationale de Transfusion Sanguine. Apparatus for causing medicinal products to penetrate into red blood cells. 5,589,389, Cl. 435-306.100.

Pahno, Demetrios A.; Stolpmann, James R.; and Thomas, James M. C., to SSI Medical Services, Inc. Apparatus and method for managing waste from patient care maintenance and treatment. 5,588,167, Cl. 5-606.000.

Paik, Choong-ryul, to Samsung Electronics Co., Ltd. Manufacturing method of target for sputtering. 5,590,385, Cl. 419-10.000.

Paikert, Bettina: See—

Dobbeling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelmayer, Thomas; and Steinbach, Christian. 5,588,826, Cl. 431-354.000.

Paiocchi, Maurizio, to Zambon Group S.p.A. Process of purification of 2,6-diisopropylphenol. 5,589,598, Cl. 568-756.000.

Palboard Ltd.: See—

Ben Zvi, Guy; Nevo, Shlomo; and Berman, Michael. 5,589,260, Cl. 428-327.000.

Palicka, Jadwiga, to Berol Nobel AB. Liquid dishwashing-detergent composition. 5,589,447, Cl. 510-237.000.

Palitex Project-Company GmbH: See—

Fox, Siegfried; and Keil, Andreas. 5,590,019, Cl. 361-643.000.

Pall Corporation: See—

Degen, Peter J.; and Lee, Joseph Y., 5,589,302, Cl. 429-250.000.

Palm, Bengt, to Alfa-Laval Food Engineering AB. Process for heat treatment of particulate materials such as food. 5,589,214, Cl. 426-506.000.

Paloma Kogyo Kabushiki Kaisha: See—

Hayakawa, Tsuneyasu; and Kimura, Makoto. 5,588,822, Cl. 431-1.000.

Palosi, Eva: See—

Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila. 5,589,486, Cl. 314-317.000.

Pan, Chényu: See—

Hauge, Robert H.; and Pan, Chényu. 5,589,231, Cl. 427-561.000.

Pan, Dingru: See—

Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76.000.

Pan, H. T.; and Chen, Chu-Mei, to Tongrand Limited. Grounding means for memory card connector. 5,588,850, Cl. 439-92.000.

Pandeva, Prakash N.: See—

DiFlora, Michael A.; Pandeva, Prakash N.; Robinson, Christopher S.; and Wagner, Philip C., 5,588,810, Cl. 417-312.000.

Pangestuti, Endang: See—

Rapp, Robert A.; Wang, Ge; and Pangestuti, Endang. 5,589,220, Cl. 427-126.100.

Panton, George S., Jr., to Diamond Safety Gear, Inc. Article of clothing having high visibility. 5,588,156, Cl. 2-243.100.

Panyard, James R., to Ford Motor Company. Robotic gripper. 5,588,794, Cl. 414-729.000.

Papst Licensing GmbH: See—

Hans, Helmut; and Moim, Mojtaba. 5,589,745, Cl. 318-431.000.

Papst-Motoren GmbH & Co. KG: See—

Rappenecker, Hermann; and Jeske, Frank. 5,590,235, Cl. 388-803.000.

Pariot, Robert; and Traugott, J. Mortimer, to Techstrip, Inc. Power door safety sensing strip. 5,589,811, Cl. 338-210.000.

Parisi, Mark J.: See—

Vetter, Stephan M.; and Parisi, Mark J., 5,588,803, Cl. 416-186.000.

Park, Chang S.: See—

Lyu, Gap Y.; and Park, Chang S., 5,589,970, Cl. 359-133.000.

Park, Chang-soo: See—

Lee, Sang-in; and Park, Chang-soo. 5,589,713, Cl. 257-773.000.

Park, Churoo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, to Samsung Electronics Co., Ltd. Semiconductor memory having a plurality of I/O buses. 5,590,086, Cl. 365-230.030.

Park, David B.; and Crawley, Michael E., to Baker Hughes Incorporated. Crystal recovery method employing a rotary vacuum filtration drum with valved hopper cake treatment means. 5,589,079, Cl. 210-784.000.

Park, Jong-Kil: See—

Lee, Kun-Jai; and Park, Jong-Kil. 5,589,071, Cl. 210-638.000.

Park, Kyung-Ho: See—

Ahn, Kun-Young; Park, Kyung-Ho; Nam, Kee-Soo; and Kang, Sang-Won. 5,589,083, Cl. 216-24.000.

Park, Sangil; Martinez, Ed F.; and Youn, Dae-Hee, to Motorola Inc. Speech processing system and method for enhancing a speech signal in a noisy environment. 5,590,241, Cl. 395-2.360.

Parker, Delmer G.: See—

Hart, Steven C.; and Parker, Delmer G., 5,589,917, Cl. 399-274.000.

Parker, Robert M.: See—

Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 5,588,158, Cl. 4-572.100.

Poulson, Keith L.; Parker, Robert M.; Samson, Jeffrey T.; and Taylor, Harry B., 5,588,159, Cl. 4-572.100.

Parks, Alan D. Valve mounting device useful with flexible pipe. 5,588,681, Cl. 285-46.000.

Parks, Jeffery S. Armored vehicle surface cooling system. 5,588,303, Cl. 62-171.000.

Parks, Terry J.; and Gaskins, Darius D., to Dell USA, L.P. Combined multiprocessor interrupt controller and interprocessor communication mechanism. 5,590,338, Cl. 395-742.000.

Parks, Terry J.: See—

Zeller, Charles P.; Parks, Terry J.; and Durkin, Michael D., 5,590,287, Cl. 395-250.000.

Parnele, David C.; and Sechi, Salvatore, to United States of America, Health and Human Services. Method for monitoring the performance of an amino acid sequencer. 5,589,397, Cl. 436-89.000.

Parrish, John R.: See—

Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clold R., III. 5,589,630, Cl. 73-23.500.

Parry, William G., to Microsoft Corporation. Method and apparatus for performing overlapping service of multiple IDE peripheral devices. 5,590,336, Cl. 395-727.000.

Parsick, Keith. Golf club. 5,588,921, Cl. 473-299.000.

Pasquali, Stefano: See—

Giovoni, Gabriele; Sacchetti, Mario; and Pasquali, Stefano. 5,589,549, Cl. 525-247.000.

Passaniti, Joseph L.; Megahed, El-Sayed A.; and Zreiba, Nuri A., to Rayovac Corporation. Method for producing a cathode material containing silver and bismuth. 5,589,109, Cl. 252-518.000.

Passone, Carlo, to Bending Tooling S.R.L. Universal support and positioning structure for tools used by an elongate element bending machine. 5,588,322, Cl. 72-383.000.

Patat, Jean-Louis; Delmas, Olivier; and Schmitthaesler, Roland, to Innotech. Method of preparing a biological adhesive enriched with platelet factors, and application. 5,589,462, Cl. 514-21.000.

Patel, Dinesh P.: See—

Adkins, John L.; and Patel, Dinesh P., 5,589,323, Cl. 430-492.000.

Patent-Treuhand-Gesellschaft F. Elektrische Glühlampen mbH: See—

Deisenhofer, Manfred; Meiss, Dieter; and Messner, Ekkehard. 5,589,734, Cl. 313-636.000.

Rudolph, Bernd; and Vesper, Alwin. 5,589,740, Cl. 315-291.000.

Pater, Ruth H.: See—

Tashiro, Renki; and Pater, Ruth H., 5,589,182, Cl. 424-423.000.

Pathak, Rajiv N.: See—

Cunningham, John E.; Goossen, Keith W.; Jan, William Y.; Pathak, Rajiv N.; and Walker, James A., 5,589,404, Cl. 437-5.000.

Paul, Abhimanyu O.; and Femino, Frank, to Exxon Chemical Patents Inc. Adducts of quinone compounds and amine-containing polymers for use in lubricating oils and in fuels. 5,588,972, Cl. 44-312.000.

Patrician, Thomas J.; and Martin, Harry D., III, to Osram Sylvania Inc. Method of making an alloy of tungsten and lanthana. 5,590,386, Cl. 419-20.000.

Patrick, Douglas: See—

Cousins, Michael; Patrick, Douglas; and Bassett, Carol T., 5,588,220, Cl. 373-768.000.

Patrick, Paul R.; and Wong, Walter, to Seagate Technology, Inc. Method and apparatus for controlling spindle speed to compensate for drag in a disk drive system. 5,589,996, Cl. 360-73.030.

Paul, Michel A.; and Gutierrez, Jorge, to Ethicon Endo-Surgery, Inc. Surgical instrument. 5,588,580, Cl. 227-176.100.

Paulsen, Knut A.: See—

Manjunath, Konanur; Paulsen, Knut A.; and Ognedal, Leiv B., 5,588,787, Cl. 406-85.000.

Pauly, John M.: See—

Mani, Sanjay; Nishimura, Dwight G.; Conolly, Steven M.; and Pauly, John M., 5,588,431, Cl. 128-653.300.

Pavlov, Vyacheslav F.; Shabanov, Vasily F.; Anshits, Alexandr G.; and Bayakin, Sergei G., to East West Trade Group, Inc. Method of producing glass materials from ash-slag waste. 5,588,977, Cl. 65-17.400.

Payne, Jewel; Narva, Kenneth E.; and Fu, Jenny, to Mycogen Corporation. *Bacillus thuringiensis* genes encoding nematode-active toxins. 5,589,382, Cl. 435-252.500.

Pearcy, Barry G.: See—

White, Alan W.; Pearcy, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., 5,589,566, Cl. 528-286.000.

Pearson, Anna M.: See—

Beach, Bradley L.; Feeman, James F.; Pearson, Anna M.; and Sun, Jing X., 5,589,522, Cl. 523-160.000.

Pearson Engineering Limited: See—

Renwick, Peter J., 5,588,232, Cl. 37-232.000.

Pechere, Jean-Claude: See—

Mabilat, Claude; and Pechere, Jean-Claude. 5,589,585, Cl. 536-24.320.

Pecis, Silver: See—

Origi, Ambrogio; and Pecis, Silver. 5,588,288, Cl. 54-82.000.

Peck, Granger. Tooth cleansing and flossing implement and method. 5,588,452, Cl. 132-321.000.

Pecka, James M.: See—

Blumberg, Barry B.; Pecka, James M.; and Allen, Bruce S., 5,588,649, Cl. 463-18.000.

Pedersen, Henrik S., executor: See—

Larsen, Peter, deceased; and Pedersen, Henrik S., executor. 5,589,207, Cl. 426-20.000.

Peeler, Donald H.: See—

Ribando, Philip P.; Bolam, Kenneth M.; Peeler, Donald H.; and Sandman, Terry L., 5,588,954, Cl. 601-149.000.

Pellegrino, Paolo: See—

Bella, Valter; and Pellegrino, Paolo. 5,589,786, Cl. 327-108.000.

Pellereau, Bernard: See—

Barry, Russell P.; and Pellereau, Bernard. 5,589,561, Cl. 526-348.100.

Peltola, Jukka; and Koponen, Pekka, to Nokia Telecommunications OY. Method and device for supervising the condition of an antenna. 5,590,415, Cl. 455-115.000.

Peltonen, Soili; and Harju, Kai, to Alko Group Ltd. Applications and methods for the preparation of fatty acid esters of polysaccharides. 5,589,577, Cl. 536-221.000.

Peltz, John H.: See—

Robinson, Donald N.; and Peltz, John H., 5,589,028, Cl. 156-306.600.

Pelzer, Hermann: See—

Römsch, Jürgen; Auerbach, Bernhard; and Pelzer, Hermann. 5,589,395, Cl. 436-71.000.

Pemberton, Denis: See—

McTaggart, Fergus; Pemberton, Denis; and Smith, Graham J., 5,589,166, Cl. 424-78.350.

Pendergrass, Daniel B., Jr.: See—

Tsuei, Alexander C.; Kogl, Lorenz, III; and Pendergrass, Daniel B., Jr., 5,589,194, Cl. 424-497.000.

Penn State Research Foundation, The: See—

Khoo, Jam-Choon. 5,589,101, Cl. 252-299.010.

Pennace, John R.: See—

Skov, Richard T.; and Pennace, John R., 5,588,679, Cl. 283-67.000.

Pennison, Robert A., to Indresco Inc. Ergonomic power tool. 5,588,903, Cl. 451-344.000.

Pentland, Alex: See—

Sclaroff, Stanley E.; and Pentland, Alex. 5,590,261, Cl. 395-173.000.

Pepsico, Inc.: See—

Meyer, Robert C., 5,588,550, Cl. 220-525.000.

Perecman, Jack L., to Minnesota Mining and Manufacturing Company. Method and apparatus for adhering object to a glass surface. 5,589,026, Cl. 156-286.000.

Perez Revilla, Miguel: See—

Gautier, Jean Pierre; Verbo, Ulysse; and Perez Revilla, Miguel. 5,588,346, Cl. 91-369.002.

Perfido, Kenneth F.; and Cialone, Anthony M. Process and apparatus for making crumb rubber from vehicle tires. 5,588,600, Cl. 241-23.000.

Perkins, David G.: See—

Collins, Mary A.; Perkins, David G.; and White, Harry E., 5,588,856, Cl. 439-204.000.

Perkins, Richard W.; and Read, Bradley L. Locking mechanism. 5,588,862, Cl. 439-347.000.

Perkins, Terrence L., to Westland Helicopters Limited. Static vent units. 5,588,616, Cl. 244-1.00R.

Permelec Electrode Ltd.: See—

Shimamura, Takayuki; Nakamatsu, Shuji; Sawamoto, Isao; and Nishiki, Yoshinori. 5,589,052, Cl. 205-349.000.

Perner, Johann; and Trinkaus, Gerhard, to Koflach Sport Gesellschaft m.b.H. & Co. KG. Apparatus for mounting skate rollers in inline roller skates. 5,588,658, Cl. 280-11.220.

Pero, Janice: See—

Sloma, Alan; Rufo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice. 5,589,383, Cl. 435-252.310.

Peroxid-Chemie GmbH: See—

Sienel, Günter; Dorn, Maximilian; and Zimmermann, Heinz. 5,589,526, Cl. 523-351.000.

Perry, David A.: See—

Haxell, Mark A.; Perry, David A.; Maeda, Hiroshi; and Tone, Junsuke. 5,589,366, Cl. 435-119.000.

Perry, Robert W.; and Goodson, Forrest R., to United Technologies Corporation. Enhanced performance blasting agent. 5,589,660, Cl. 149-18.000.

Perry, Scott M.: See—

Landis, Timothy J.; and Perry, Scott M., 5,588,836, Cl. 433-93.000.

Persson, Bengt: See—

Billström, Lars; Wetterborg, Lars; Dahlin, Steinar; and Persson, Bengt. 5,590,133, Cl. 370-349.000.

Perycut-Chemie AG: See—

Benecis, Franz. 5,589,181, Cl. 424-405.000.

Peschina, Jürgen: See—

Jäger, Helmut F.; Peschina, Jürgen; and Dietrich, Bernard. 5,588,795, Cl. 414-733.000.

Peters, Helen A. Hair retainer. 5,588,451, Cl. 132-273.000.

- Peters, Ralf-Peter: See—
Reinecke, Holger; Unal, Nezh; Peters, Ralf-Peter; Bartels, Frank; and Noker, Friedolin F., 5,588,597, Cl. 239-553.000.
- Petersen, Charles E.: See—
Bhagavan, Nadhipuram V.; Petersen, Charles E.; and Mandel, Morton, 5,589,338, Cl. 435-6.000.
- Peterson, Craig, to U.S. Industrial Tool and Supply. Hand-held rivet bucking tool using energy dissipative polymer, 5,588,323, Cl. 72-465.000.
- Peterson, Kirk D., to Texas Instruments Incorporated. Dual voltage level shifted, cascaded current mirror, 5,589,800, Cl. 330-288.000.
- Petragallo, Michael R. Human range of motion measurement system, 5,588,444, Cl. 128-782.000.
- Petrik, Michael A.: See—
Cable, Thomas L.; and Petrik, Michael A., 5,589,285, Cl. 429-13.000.
- Petrone, Alberto: See—
De Filippis, Pietro; Quarero, Ernesto; and Petrone, Alberto, 5,588,814, Cl. 417-423.700.
- Petrovic, Rade: See—
Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51.200.
- Perricone Corporation: See—
Hamann, James L., 5,588,171, Cl. 15-104.120.
- Pfeiffer, Michael L.: See—
Desai, Pravin M.; Pfeiffer, Michael L.; Pohlmeier, Mary M.; and Raymond, Jennifer B., 5,589,213, Cl. 426-438.000.
- Pfizer Inc.: See—
Haxell, Mark A.; Perry, David A.; Maeda, Hiroshi; and Tone, Junsuke, 5,589,366, Cl. 435-119.000.
- Thompson, David D., 5,589,482, Cl. 514-305.000.
- Pflegger, Wolfgang, to EMS-Inventa AG. Blow-molded coolant conduit, 5,588,468, Cl. 138-121.000.
- PGA Tour: See—
Brady, Joseph M., 5,589,628, Cl. 73-12.020.
- Pharmacia Lovisoin, Inc.: See—
Blake, Larry W., 5,589,024, Cl. 156-245.000.
- Pharmacia LKB Biotechnology AB: See—
Holmberg, Lars, 5,589,586, Cl. 536-25.300.
- Pharmatrix Corporation: See—
Mohr, Judy M.; Baker, Richard W.; and Nakaji, Lisa A., 5,589,498, Cl. 514-413.000.
- Pharo, Daniel A., to Air Packaging Technologies, Inc. Self-sealing inflatable bag and method for packaging an article therein, 5,588,532, Cl. 206-522.000.
- Philipp Brothers Chemicals, Inc.: See—
Plecnik, Joseph M., 5,588,461, Cl. 137-312.000.
- Philips Electronics N.V.: See—
Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L.; and Gamand, Patrice, 5,589,777, Cl. 324-537.000.
- Philips Electronics North America Corporation: See—
Mizrahi-Shalom, Ori K.; and Ko, Kung-Ling, 5,590,358, Cl. 395-800.000.
- Phillips, James E.; Blauer, Bartholomew; and Vassiliadis, Stamatios, to International Business Machines Corporation. Status predictor for combined shifter-rotate/merge unit, 5,590,348, Cl. 395-564.000.
- Phillips, John F.: See—
Swisher, George W., Jr.; and Phillips, John F., 5,588,776, Cl. 404-72.000.
- Phillips, Sabrina D.; and Hellums, James R., to Texas Instruments Incorporated. Method and apparatus for detecting changes in a clock signal to static states, 5,589,784, Cl. 327-18.000.
- Phipps, Alan M.: See—
Callaghan, David T.; Phipps, Alan M.; and Provencal, Stephen J., 5,589,196, Cl. 424-617.000.
- Photakis, John G. Smoking article holder, 5,588,448, Cl. 131-259.000.
- Photon Kinetics, Inc.: See—
Osgood, Edwin B.; and Shaar, Casey S., 5,589,933, Cl. 356-73.100.
- Pi, Raphael; Bigorra-Losas, Joaquim; Ponsati-Obiols, Oriol; and Schmid, Karl, to Henkel Kommanditgesellschaft auf Aktien. Process for the production of water-free detergent mixtures, 5,589,450, Cl. 510-535.000.
- Pickett Equipment: See—
Pickett, J. Paul; Jones, Dee L.; and Christensen, Jay D., 5,588,494, Cl. 171-124.000.
- Pickett, J. Paul; Jones, Dee L.; and Christensen, Jay D., to Pickett Equipment. Crop inverter and method of using same, 5,588,494, Cl. 171-124.000.
- Pidutti, Albino: See—
Borgato, Pierandrea; Diazzi, Claudio; and Pidutti, Albino, 5,589,759, Cl. 323-222.000.
- Pierce, James C.: See—
Williams, Jon I.; Pierce, James C.; Anderson, G. Mark; and Kari, Prasad, 5,589,364, Cl. 435-69.700.
- Pierce, John M.: See—
Iranmanesh, Ali; Pierce, John M.; and Bergemont, Albert M., 5,589,412, Cl. 437-43.000.
- Pierce, William C.; and Richardson, Gregory A., to Nai Neway, Inc. Trailing arm suspension with lever arm, 5,588,665, Cl. 280-704.000.
- Piggin, Roger H.: See—
Dale, Allison Hazel C.; Piggin, Roger H.; Hallett, Richard A.; and McIntyre, Paul R., 5,589,318, Cl. 430-264.000.
- Pinai, Felix: See—
Sangveraphunsiri, Vic; Pinai, Felix; Shu, Thomas; and Spears, Cameron, 5,590,375, Cl. 395-841.000.
- Pinkerton, William R. Child proof refrigerator door latch, 5,588,687, Cl. 292-259.000.
- Pinkham, Raymond; and Balistreni, Anthony M., to Texas Instruments Incorporated. Process of writing data from a data processor to a memory device register that is separate from the array, 5,590,083, Cl. 365-230.010.
- Pioneer Electronic Corporation: See—
Koyano, Shinji; Kogure, Koushirou; Ohya, Takashi; Sakakibara, Makoto; and Hanayama, Katsutoki, 5,590,208, Cl. 381-154.000.
- Sato, Masuhiro; and Inaba, Naoto, 5,589,947, Cl. 386-96.000.
- Pioneer Hi-Bred International, Inc.: See—
Briggs, Steven P.; and Johal, Gurmukh S., 5,589,611, Cl. 800-205.000.
- Pionk, Michael P.: See—
Emambakhsh, Al S.; Pionk, Michael P.; Saberan, Al A.; and Wallner, John P., 5,588,667, Cl. 280-728.200.
- Piontek, Susanne: See—
Ott, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heimann, Ulrich; and Gilbert, John, 5,589,049, Cl. 204-504.000.
- Pirahesh, Mir H.: See—
Leung, Ting Y.; Pirahesh, Mir H.; Jou, Michelle M.; and Simmen, David E., 5,590,324, Cl. 395-605.000.
- Pirelli Cavi S.p.A.: See—
Portas, Francesco, 5,589,123, Cl. 264-154.000.
- Pisano, Albert P.: See—
Lin, Liwei; Nguyen, Clark T.; Howe, Roger T.; and Pisano, Albert P., 5,589,082, Cl. 216-2.000.
- Pischinger, Franz: See—
Spiegel, Leo; and Pischinger, Franz, 5,588,504, Cl. 184-6.800.
- Pitchford, Peter R. Interlocking building block, 5,588,271, Cl. 52-306.000.
- Pitney Bowes Inc.: See—
Lee, David K.; and Riley, David W., 5,590,198, Cl. 380-21.000.
- Pitroda, Satyan G. Universal electronic transaction card including receipt storage and system and methods of conducting electronic transactions, 5,590,038, Cl. 395-241.000.
- Plant Genetic Systems, N.V.: See—
De Beuckeleer, Marc; Herdies, Lydia; Gossele, Veronique; and Mariani, Celestina, 5,589,610, Cl. 800-205.000.
- De Clercq, Ann; Krebbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205.000.
- Planta, Andrea V.; and Gerber, Rolf, to Comet Technik AG. Variable capacitor having safety end switches disposed on an adjustable screw at end face of capacitor housing, 5,590,015, Cl. 361-277.000.
- Plantan, Ronald S.; and Dangson, Henry T., to Indian Head Industries, Inc. Brake actuator with centering dome in service chamber, 5,588,348, Cl. 92-63.000.
- Platt, Robert C.: See—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474.130.
- Plecnik, Joseph M., to Philipp Brothers Chemicals, Inc. Hazardous material containment system, 5,588,461, Cl. 137-312.000.
- PLX Inc.: See—
Bleier, Zvi, 5,589,991, Cl. 359-856.000.
- PMI International Corporation: See—
Harrison, Robert G., 5,588,352, Cl. 99-339.000.
- Podio, Augusto L.: See—
McCoy, James N.; West, Jerry B.; and Podio, Augusto L., 5,589,633, Cl. 417-63.000.
- Podoyma, Vladimir: See—
Bogatin, Jacob G.; and Podoyma, Vladimir, 5,589,065, Cl. 210-222.000.
- Pohlmeier, Mary M.: See—
Desai, Pravin M.; Pfeiffer, Michael L.; Pohlmeier, Mary M.; and Raymond, Jennifer B., 5,589,213, Cl. 426-438.000.
- Poland, Sydney W.: See—
Guttig, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moysie, Philip, 5,590,350, Cl. 395-800.000.
- Poluzzi, Rinaldo: See—
Mancuso, Massimo; Poluzzi, Rinaldo; and Rizzotto, Gianguido, 5,589,890, Cl. 348-678.000.
- Poly-Bond, Inc.: See—
Bodford, Carl A.; Chester, Stephen O.; and Nayak, Rahul K., 5,589,249, Cl. 428-200.000.
- Polymer Technology Group, The: See—
Ward, Robert S.; and White, Kathleen A., 5,589,563, Cl. 528-44.000.
- Polysheet A/S: See—
Selbeck, Peter, 5,588,191, Cl. 24-713.600.
- Polysht Corporation: See—
Hepler, Douglas C., 5,589,206, Cl. 425-549.000.
- Pomerantz, Roger J.: See—
Bagasra, Omar; and Pomerantz, Roger J., 5,589,333, Cl. 435-6.000.
- Pomeranz, Mark L.: See—
Imran, Mir A.; Pomeranz, Mark L.; and Glynn, Brian A., 5,588,964, Cl. 604-95.000.
- Pomerleau, Daniel G., to LWT Instruments Inc. Logging or measurement while tripping, 5,589,825, Cl. 340-854.900.
- Ponsati-Obiols, Oriol: See—
Pi, Raphael; Bigorra-Losas, Joaquim; Ponsati-Obiols, Oriol; and Schmid, Karl, 5,589,450, Cl. 510-535.000.
- Pool, Stanton J.: See—

- Thornton, John; Pool, Stanton J.; and Doll, Dennis R., 5,589,027, Cl. 156-304.400.
- Pool, Wieberen. Process for electroclamation of soil material, 5,589,056, Cl. 205-766.000.
- Pope, Lynne: See—
Hampson, Ian N.; Pope, Lynne; and Butler, John, 5,589,339, Cl. 435-6.000.
- Pope, Peter J.; and Willis-Owen, Richard B., to Duracell Inc. Sealed galvanic cell with injection molded top, 5,589,293, Cl. 429-172.000.
- Popovich, Steven R., to Digisonix, Inc. Adaptive control system with a corrected-phase filtered error update, 5,590,205, Cl. 381-71.000.
- Porro, Massimo, to BioYnth s.r.l. Synthetic peptides for detoxification of bacterial endotoxins and for the prevention and treatment of septic shock, 5,589,459, Cl. 514-15.000.
- Portas, Francesco, to Pirelli Cavi S.p.A. Process of making a tubular supporting element, 5,589,123, Cl. 264-154.000.
- Potter, Philip: See—
Allen, William D.; Linggood, Margaret A.; and Porter, Philip, 5,589,168, Cl. 424-93.400.
- Postma, Ebele M.: See—
de Jong, Hendrik J.; and Postma, Ebele M., 5,588,234, Cl. 40-301.000.
- Poth, Ulrich: See—
Wegner, Egon; Poth, Ulrich; Gross, Lutz-Werner; and Weidemeier, Klaus, 5,589,228, Cl. 427-407.100.
- Potter, David: See—
Goldston, Mark R.; Bemis, Jon L.; Wickemeyer, Daniel M.; and Potter, David, 5,588,227, Cl. 36-93.000.
- Potter, Dwight: See—
Jacobsen, Stephen C.; Potter, Dwight; and Smith, Fraser, 5,588,688, Cl. 294-106.000.
- Potter, Richard C., to Nurture, Inc. Film-forming proteinaceous emulsion, 5,589,195, Cl. 424-499.000.
- Potter, Robert: See—
Garcia-Rubio, Luis H.; Bayona, Manuel; Potter, Robert; and Leparc, German, 5,589,932, Cl. 356-39.000.
- Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hoteling, Bryan R., to Gerry Baby Products Company. Bath ring, 5,588,158, Cl. 4-572.100.
- Poulson, Keith L.; Parker, Robert M.; Samson, Jeffrey T.; and Taylor, Harry B., to Gerry Baby Products Company. Infant bathtub with multiple-position infant support, 5,588,159, Cl. 4-572.100.
- Powell, Anthony L.: See—
Butters, Brian E.; and Powell, Anthony L., 5,589,078, Cl. 210-748.000.
- PPG Industries, Inc.: See—
Vonk, Donald R.; and Greene, Jeffrey A., 5,588,989, Cl. 106-14.120.
- Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stollenberg, Blaise G., to Setcom Corporation. Mount for supporting a microphone on a helmet, 5,590,209, Cl. 381-168.000.
- President and Fellows of Harvard College, The: See—
Farr, Spencer B., 5,589,337, Cl. 435-6.000.
- Seidman, Jonathan G.; and Jakobovits, Aya, 5,589,369, Cl. 435-172.300.
- Price, Aaron R.: See—
Price, Eric M.; and Price, Aaron R., 5,588,940, Cl. 482-105.000.
- Price, Eric M.; and Price, Aaron R. Weight supporting body harness, 5,588,940, Cl. 482-105.000.
- Price, Gerald H., to Price Manufacturing, Inc. Air bed diaphragm pump, 5,588,811, Cl. 417-350.000.
- Price, John C.: See—
Yandroski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., 5,589,845, Cl. 343-909.000.
- Price Manufacturing, Inc.: See—
Price, Gerald H., 5,588,811, Cl. 417-350.000.
- Prince, Mark A.: See—
Kolaitis, Leonidas; Lenoble, Bertrand L. J.; and Prince, Mark A., 5,589,449, Cl. 510-466.000.
- Process Automation International Limited: See—
Henington, Paul, 5,589,051, Cl. 205-80.000.
- Process Technology Inc.: See—
Rezabek, Dennis J., 5,590,240, Cl. 392-483.000.
- Procter and Gamble Company, The: See—
Guskey, Gerald J.; Hellyer, James A.; Kluesener, Bernard W.; and Stipp, Gordon K., 5,589,216, Cl. 426-607.000.
- Rice, David E., 5,589,160, Cl. 424-49.000.
- ProMinent Dosiertechnik GmbH: See—
Dulger, Viktor, 5,588,339, Cl. 74-836.000.
- Propach, David S.: See—
Bayley, Gwain; Grob, Matthew S.; Karmi, Gadi; Kimball, Robert H.; and Propach, David S., 5,590,406, Cl. 455-54.200.
- Protat, Vincent: See—
Chevalier, Alain; and Protat, Vincent, 5,589,632, Cl. 73-117.400.
- Proulx, Genevieve C. Infant seat rocker and amusement unit, 5,588,164, Cl. 5-109.000.
- Provencal, Stephen J.: See—
Callaghan, David T.; Phipps, Alan M.; and Provencal, Stephen J., 5,589,196, Cl. 424-617.000.
- Provenza, Ronald A., to Unisys Corporation. Technique providing bridge for connecting modular units, 5,590,027, Cl. 361-732.000.
- Pruehs, Allen V.; Robinson, Darrell; and Learmont, Robert O., to Ekstrom Industries, Inc. Wathour meter socket adapter for replacing an OB wathour meter, 5,588,874, Cl. 439-517.000.
- Pruehs, Allen V.: See—
- Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.
- Puerner, Dean A., to Whitaker Corporation. The. Electrical connector having socket contacts with safety shields, 5,588,852, Cl. 439-135.000.
- Pujalon-Mercereau, Odile: See—
Marchand, Claudine; Druilhe, Pierre; Pujalon-Mercereau, Odile; and Langsley, Gordon, 5,589,343, Cl. 435-7.220.
- Pulido, Jacqueline J., to Minnesota Mining and Manufacturing Company. Fiber optic splice organizers, 5,590,234, Cl. 385-135.000.
- Purcell, Thomas A.: See—
Jegham, Samir; Defosse, Gérard; Purcell, Thomas A.; and Even, Luc, 5,589,476, Cl. 514-230.200.
- Pursley, James R.: See—
Wilbank, Milo; and Pursley, James R., 5,589,457, Cl. 514-12.000.
- Putney, Gordon A.: See—
Becker, Thomas P.; Crass, Matthew M.; Putney, Gordon A.; Niesen, Randy J.; and Iwinski, Dean J., 5,589,644, Cl. 73-862.230.
- Puziol, David L.: See—
Sowadsky, Elliot A.; Widigen, Larry; Puziol, David L.; and Van Dyke, Korbin S., 5,590,351, Cl. 395-800.000.
- Pyle, Robert D. Across the wall pressure differential indicator, 5,589,643, Cl. 73-861.750.
- QO Chemicals, Inc.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kielemeyer, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593.000.
- Qualcomm Incorporated: See—
Bayley, Gwain; Grob, Matthew S.; Karmi, Gadi; Kimball, Robert H.; and Propach, David S., 5,590,406, Cl. 455-54.200.
- Levin, Jeffrey A., 5,590,069, Cl. 365-96.000.
- Weiland, Ana L.; Kornfeld, Richard K.; and Maloney, John E., 5,590,408, Cl. 455-69.000.
- Qualimetrics, Inc.: See—
Micko, Eric S., 5,589,779, Cl. 324-714.000.
- Qualmark Corporation: See—
Hobbs, Gregg K., 5,589,637, Cl. 73-663.000.
- Quaranta, Vito: See—
Tamura, Richard N.; and Quaranta, Vito, 5,589,570, Cl. 530-350.000.
- Quarero, Ernesto: See—
De Filippis, Pietro; Quarero, Ernesto; and Petrone, Alberto, 5,588,814, Cl. 417-423.700.
- Queen, Andrew. Personal response system with remotely adjustable microphone sensitivity, 5,589,818, Cl. 340-506.000.
- Quest Medical, Inc.: See—
Abbott, Marty; and Thompson, Thomas C., 5,588,816, Cl. 417-479.000.
- Quinn, Michael D.: See—
McKown, Russell C.; Quinn, Michael D.; and Yelderman, Mark L., 5,588,438, Cl. 128-692.000.
- Quinn, Stephen J. Method and apparatus for testing vehicle exhaust emissions, 5,589,629, Cl. 73-23.310.
- Quintana, Jean: See—
Merlin, Bruno; and Quintana, Jean, 5,589,681, Cl. 235-482.000.
- R. J. Reynolds Tobacco Company: See—
Clearman, Jack F., 5,588,446, Cl. 131-194.000.
- Rabii, Khosro M.: See—
Bestler, Caitlin B.; Hartley, Harry A., III; and Rabii, Khosro M., 5,590,202, Cl. 380-49.000.
- Rabins, Leonard: See—
Guenther, Russell W.; and Rabins, Leonard, 5,590,301, Cl. 395-412.000.
- Radio Frequency Systems, Inc.: See—
Meredith, Sheldon K.; Arnold, Pitt W.; Hunt, Warren F.; Connolly, Kevin J.; and Gaukel, Kevin M., 5,589,843, Cl. 343-820.000.
- Radio Telecom & Technology, Inc.: See—
Martinez, Louis, 5,589,872, Cl. 348-12.000.
- Rahim, Mazin G.: See—
Juang, Bing-Hwang; and Rahim, Mazin G., 5,590,242, Cl. 395-2.540.
- Rahman, Mizanur M.; Sabernick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., to Tandem Computers Incorporated. Processor interface chip for dual-microprocessor processor system, 5,590,337, Cl. 395-735.000.
- Rajan, Krishna B.: See—
Abramovici, Miron; Agrawal, Vishwani D.; Cheng, Kwang-Ting; and Rajan, Krishna B., 5,590,135, Cl. 371-22.100.
- Rakuma, Tsuyoshi: See—
Ishihara, Manabu; Rakuma, Tsuyoshi; Kanai, Hiroshi; Fudo, Takashi; and Watanabe, Masato, 5,588,589, Cl. 236-46.000.
- Raleigh, Edward A.: See—
Walters, Nole L.; Raleigh, Edward A.; and Thiel, Peter H., 5,589,675, Cl. 218-140.000.
- Rallis, Angelos: See—
Bastoli, Calka; Bellotti, Vittorio; Del Tredici, Gianfranco; and Rallis, Angelos, 5,589,518, Cl. 521-55.000.
- Ramachandran, Karapurath: See—
Anderson, Thomas Q.; Broadrick, Garth W.; Christianson, Merrill A.; Hippe, Daniel A.; Hughes, Arthur T.; Kalyan, Jagdish C.; Nydegger, Daniel L.; Platt, Robert C.; and Ramachandran, Karapurath, 5,590,046, Cl. 364-474.130.

- Ramachandran, Ramesh, and Dinunzi, Sharon A., to Union Carbide Chemicals & Plastics Technology Corporation. Lubricious polymer blends comprising polyethylene oxide, polyethylene and a polylactone. 5,589,545, Cl. 525-184.000.
- Ramalho, Joao N. V. L., See—
Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L., and Gamand, Patrice, 5,589,777, Cl. 324-537.000.
- Ramamurthy, Arakalud V., See—
Wagner, Burkhard E.; and Ramamurthy, Arakalud V., 5,589,539, Cl. 525-53.000.
- Ramesh, Manian, See—
Sivakumar, Ananthasubramanian; Collins, John H.; and Ramesh, Manian, 5,589,075, Cl. 210-727.000.
- Ramp, John M., See—
Fiechter, Michael D.; Ramp, John M.; England, Barbara J.; and Annino, Mary J., 5,589,393, Cl. 436-15.000.
- Rampf Formen GmbH, See—
Burger, Guenter, 5,589,087, Cl. 219-93.000.
- Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., to Motorola, Inc. Process for manufacturing a package for mating with a bare semiconductor die. 5,589,402, Cl. 437-2.000.
- RAN Enterprises, Inc., See—
Kiefer, James, 5,588,684, Cl. 285-62.000.
- Randall, Mitchell A., and Loew, Eric, to University Corporation for Atmospheric Research. Radar acquisition system. 5,589,833, Cl. 342-195.000.
- Rang, Harald, See—
Eicken, Karl; Goetz, Norbert; Harreus, Albrecht; Anniermann, Eberhard; Lorenz, Gisela; and Rang, Harald, 5,589,493, Cl. 514-355.000.
- Ranganathan, Mudumbai, See—
Carson, Mark E.; Ranganathan, Mudumbai; and Cugini, Janet A., 5,590,266, Cl. 395-340.000.
- Rank, David B.; Bonebrake, Randall A.; and Stoner, Spurgeon C., to Harley-Davidson Motor Company. Gas tank graphic positioning fixture. 5,588,216, Cl. 33-286.000.
- Rantanen, Petri, See—
Suni, Jarmo; and Rantanen, Petri, 5,590,166, Cl. 378-37.000.
- Rao, Ramana B., See—
Lamping, John O.; and Rao, Ramana B., 5,590,250, Cl. 395-127.000.
- Rapier, James, III, See—
Stuck, Robert M.; and Rapier, James, III, 5,588,354, Cl. 99-386.000.
- Rapistan Demag Corp., See—
Affaticati, Artemio; Cerutti, Claudio; and Ceglia, Teodoro, 5,588,520, Cl. 198-370.000.
- Rapoport, William R.; and Hou, Janpu, to AlliedSignal Inc. System to determine environmental pressure and birefringent-biased cladded optical sensor for use therein. 5,589,931, Cl. 356-33.000.
- Rapp, Robert A.; Wang, Ge; and Pangestuti, Endang, to Ohio State University Research Foundation. The Method of depositing chromium and silicon on a metal to form a diffusion coating. 5,589,220, Cl. 427-126.100.
- Rappenecker, Hermann; and Jeske, Frank, to Papst-Motoren GmbH & Co. KG. DC motor control with periodic reset. 5,590,235, Cl. 388-803.000.
- Rasmussen, Kirk H., See—
Clark, Randall J.; Smith, Bradley W.; Rasmussen, Kirk H.; and Kort, Leland B., 5,588,676, Cl. 280-741.000.
- Ratuitze, Florencio; Ahart, Robert; Lang, David J.; and Tsaur, Liang S., to Lever Brothers Company, Division of Conopco, Inc. Process for encapsulating sensitive materials. 5,589,370, Cl. 264-4.300.
- Rauch, Ernst, See—
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruf, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Raychem Corporation, See—
Collins, Mary A.; Perkins, David G.; and White, Harry E., 5,588,856, Cl. 439-204.000.
- Jensen, Michael L.; Summers, George D., Jr.; and Baum, Thomas M., 5,588,869, Cl. 439-417.000.
- Jones, Philip J., 5,589,253, Cl. 428-220.000.
- Raymond, Jennifer B., See—
Desai, Pravin M.; Pfeiffer, Michael L.; Pohlmeier, Mary M.; and Raymond, Jennifer B., 5,589,213, Cl. 426-438.000.
- Raymond Keith Foster, See—
Foster, Raymond K.; and Foster, Randall M., 5,588,522, Cl. 198-775.000.
- Rayovac Corporation, See—
Passaniti, Joseph L.; Megahed, El-Sayed A.; and Zretha, Nuri A., 5,589,109, Cl. 252-518.000.
- Razavi, Abbas, to Fina Technology, Inc. Process and catalyst for producing crystalline polyolefins. 5,589,556, Cl. 526-170.000.
- Read, Bradley L., See—
Perkins, Richard W.; and Read, Bradley L., 5,588,862, Cl. 439-347.000.
- Read, Christopher J., See—
Guttag, Karl M.; Halmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moyse, Philip, 5,590,350, Cl. 395-800.000.
- Reader, Timothy W., See—
Baker, Jerry W.; and Reader, Timothy W., 5,588,155, Cl. 2-123.000.
- Reay, Robert L., See—
Dohkin, Robert C.; and Reay, Robert L., 5,589,709, Cl. 257-666.000.
- Recot, Inc., See—
Desai, Pravin M.; Pfeiffer, Michael L.; Pohlmeier, Mary M.; and Raymond, Jennifer B., 5,589,213, Cl. 426-438.000.
- Rector, Russell M., See—
Rahman, Mizanur M.; Sabernick, Fred C.; Sprouse, Jeff A.; Grusz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735.000.
- Redman, Colvin, See—
Lee, Soohye, and Redman, Colvin, 5,589,336, Cl. 435-6.000.
- Reed, Mark A., to Yale University. Sub-nanoscale electronic systems and devices. 5,589,692, Cl. 257-23.000.
- Reeder, Dennis, to Spectra-Physics Lasers, Inc. Mirror mount. 5,590,149, Cl. 372-107.000.
- Register, David S. Secondary display system for computer. 5,590,021, Cl. 361-681.000.
- Reich, Holger, See—
Stroter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegemund, Rainer, 5,588,326, Cl. 74-50.000.
- Reid, Robert C., See—
Menashi, Jameel; Reid, Robert C.; Whitehouse, Robert S.; and Kaul, David J., 5,589,531, Cl. 524-409.000.
- Reif, Hans-Jorg, See—
Kindl, Helmut; Hain, Rüdiger; and Reif, Hans-Jorg, 5,589,620, Cl. 800-205.000.
- Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jorg; Stenzel, Klaus; and Thomzik, Jürgen, 5,589,621, Cl. 800-205.000.
- Reiher, Ingolf, See—
Lehmann, Volker; Marin, Heiner; and Reiher, Ingolf, 5,589,673, Cl. 218-66.000.
- Reinbold, John L., See—
Cornell, Thomas W., Jr.; and Reinbold, John L., 5,588,248, Cl. 43-44.900.
- Reinecke, Holger; Unal, Nezhir; Peters, Ralf-Peter; Bartels, Frank; and Nöker, Friedolin F., to MicroParts GmbH. Nozzle plate for a liquid jet print head. 5,588,597, Cl. 239-553.500.
- Reinehr, Dieter; Bacher, Jean-Pierre; and Schmitter, André, to Ciba-Geigy Corporation. Dimeric benzotriazoles as UV absorbers. 5,589,529, Cl. 524-91.000.
- Reinshagen, John H., to Ametek, Specialty Metal Products Division. Process for improving the corrosion resistance of stainless steel powder composition. 5,590,384, Cl. 419-6.000.
- Reliable Biopharmaceutical Corporation, See—
Tove, Joseph A., 5,589,588, Cl. 536-53.000.
- Rendall, John S., and Aghar, Massoud, to Solv-Ex Corporation. Method for making and shaping objects of rigid insulation. 5,589,023, Cl. 156-245.000.
- Rensselaer Polytechnic Institute, See—
Isaacson, David; and Cheney, Margaret, 5,588,429, Cl. 128-734.000.
- Renwick, Peter J., to Pearson Engineering Limited. Vehicle linkage. 5,588,232, Cl. 37-232.000.
- Research Corporation Tech., Inc., See—
Haefling, Gene H., 5,589,725, Cl. 310-358.000.
- Research Foundation For Mental Hygiene, Inc., See—
Terman, Michael; Fairhurst, Stephen; Hughes, Philip; and Levitt, Joel, 5,589,741, Cl. 315-360.000.
- Resk, Richard E.; Shapiro, Jeffrey R.; and Materdomini, Daniel. System for color matching a dental prosthesis. 5,588,834, Cl. 433-26.000.
- Resnick, Douglas J.; Johnson, William A.; Cummings, Kevin D.; and Chen, Hector T. H., to Motorola. Planar uniform heating surface with additional circumscribing ring. 5,590,239, Cl. 392-418.000.
- Resta, Irene, See—
Da Col, Marco; Dall'Asta, Leone; and Resta, Irene, 5,589,593, Cl. 540-220.000.
- Restaurant Technology, Inc., See—
Castor, Patrick E.; Tsau, Yung-Chun; Kristiansen, Inge B.; and Nelson, John W., 5,590,288, Cl. 395-200.030.
- Retter, Eric E., See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Reuter, Hardy, See—
On, Günther; Reuter, Hardy; Jock, Walter; Piontek, Susanne; Heilmann, Ulrich; and Gilbert, John, 5,589,049, Cl. 204-504.000.
- Reuters Limited, See—
Atkinson, Holly G., 5,589,898, Cl. 351-237.000.
- Rex, Gary C.; and Atkins, Kenneth E., to Union Carbide Chemicals & Plastics Technology Corporation. Polyurethane low profile additives for polyester-based molding compositions. 5,589,538, Cl. 525-28.000.
- Reynet, Christine, See—
Kahn, C. Ronald; and Reynet, Christine, 5,589,374, Cl. 435-240.100.
- Reynolds, Robert A.; and Sheffield, David W., to International Business Machines Corporation. Multiple protocol device interface subsystem and method. 5,590,313, Cl. 395-500.000.
- Rezabek, Dennis J., to Process Technology Inc. Ultra pure water heater with coaxial helical flow paths. 5,590,240, Cl. 392-483.000.
- Rhodes, Gary H., See—
Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44.000.
- Rhone-Poulenc Inc., See—
Sande, Walter E.; and Sears, Karl D., 5,589,030, Cl. 162-7.000.
- Rhône-Poulenc Rorer Pharmaceuticals, Inc., See—

- Lebkowski, Jane S.; McNally, Maureen A.; and Okarma, Thomas B., 5,589,377, Cl. 435-240.200.
- Ribando, Philip P.; Bolam, Kenneth M.; Peeler, Donald H.; and Sandman, Terry L., to Beiersdorf-Jobst, Inc. Connector for a gradient sequential compression system. 5,588,954, Cl. 601-149.000.
- Ricco, Gary C.; Shannon, Michael D.; and Wilkins, Tyler R., to ATG Cygnel Inc. Apparatus and method for handling information storage media. 5,588,796, Cl. 414-741.000.
- Rice, David E., to Procter & Gamble Company. The. Dentifrice compositions. 5,589,160, Cl. 424-49.000.
- Rice, Patrick E., to Jason, Inc. Expanded metal filter support structure. 5,589,067, Cl. 210-493.500.
- Rice, Richard G., to Board of Supervisors of Louisiana State University and Agricultural and Mechanical College. Radial flow chromatography. 5,589,062, Cl. 210-198.200.
- Rice University, See—
Hauge, Robert H.; and Pan, Chenyu, 5,589,231, Cl. 427-561.000.
- Rich, Edward L., See—
Bracken, Allen T.; and Rich, Edward L., 5,590,002, Cl. 360-97.020.
- Richards, Justin J. C., See—
Keane, Patrick J.; and Richards, Justin J. C., 5,590,264, Cl. 395-340.000.
- Richardson, Gregory A., See—
Perce, William C.; and Richardson, Gregory A., 5,588,665, Cl. 280-704.000.
- Richardson, Robert R., See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Richmond, Robert M., See—
Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704.000.
- Richter Gedeon Vegyeszeti Gyar Rt., See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kopolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathey, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsébet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Richter, Wolfgang-Dieter; Uebel, Lutz; and Weeger, Engelbert, to MAN GHH Schienenverkehrstechnik GmbH. Secondary suspension for rail vehicles. 5,588,368, Cl. 105-199.100.
- Richmsmeier, Brent W., See—
Russell, Todd L.; Richmsmeier, Brent W.; and Glassett, Kevin L., 5,589,866, Cl. 347-102.000.
- Ricoch Company, Ltd., See—
Kawashima, Ikuo; and Hanaoka, Katsunari, 5,589,712, Cl. 257-750.000.
- Watanabe, Hideyuki, 5,589,954, Cl. 358-518.000.
- Riggs, Bernard A., See—
Hobby, Gray D.; and Riggs, Bernard A., 5,589,012, Cl. 148-561.000.
- Riihimäki, Antero. Safety-belt cutter. 5,588,212, Cl. 30-123.000.
- Riis, Einar K., to Werner Kammann Maschinenfabrik GmbH. Device and method for inserting or removing operating parts into or from a printing machine. 5,588,361, Cl. 101-216.000.
- Riley, David W., See—
Lee, David K.; and Riley, David W., 5,590,198, Cl. 380-21.000.
- Riley, Rory M.; Uyeda, Alan K.; and Winardi, Michael, to Adams Rite Manufacturing Company. Temperature responsive mechanism for controllably deadlocking a door to a door frame. 5,588,686, Cl. 292-92.000.
- Rinaldo, John M., to Atlas Copco Aktiebolag. Flow controller. 5,588,503, Cl. 184-6.400.
- Rine, Jasper, See—
Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.
- Riordan, Thomas J., See—
Mirapuri, Sunit; and Riordan, Thomas J., 5,590,294, Cl. 395-591.000.
- Risse, Georg. System of treatment for use in functional orthodontics. 5,588,833, Cl. 433-24.000.
- Ritter, Leopold, See—
Lindenmeier, Heinz; Hopf, Jochen; and Ritter, Leopold, 5,589,839, Cl. 343-713.000.
- River Medical, Inc., See—
Sancoff, Gregory E.; Doyle, Mark C.; and Field, Frederic P., 5,588,556, Cl. 222-1.000.
- Riverwood International Ltd., See—
Negelein, Emanuel, 5,588,586, Cl. 229-198.200.
- Rizkalla, Emad; and Newbury, David, to Zedd Technologies Inc. Passive stabilization platform. 5,588,369, Cl. 108-2.000.
- Rizzi, Mario, See—
Rizzi, Roberto; and Rizzi, Mario, 5,588,356, Cl. 99-450.600.
- Rizzi, Roberto; and Rizzi, Mario. Chain mold for preparing solid food products, or filled food products, of different three dimensional shapes. 5,588,356, Cl. 99-450.600.
- Rizzotto, Gianguido, See—
Mancuso, Massimo; Poluzzi, Rinaldo; and Rizzotto, Gianguido, 5,589,890, Cl. 348-678.000.
- Roane, Jerry M., to Staktek Corporation. Method of manufacturing a high density integrated circuit module having complex electrical interconnect rails. 5,588,205, Cl. 29-830.000.
- Robb, Francine Y.; Robb, Stephen P.; and Groenig, Paul J., to Motorola, Inc. Method of forming an alloyed drain field effect transistor and device formed. 5,589,408, Cl. 437-29.000.
- Robb, Stephen P., See—
Robb, Francine Y.; Robb, Stephen P.; and Groenig, Paul J., 5,589,408, Cl. 437-29.000.
- Robert Bosch GmbH, See—
Benz, Gerhard; Flik, Gottfried; Treutler, Christoph; and Friedrich, Heinz, 5,588,466, Cl. 137-831.000.
- Mattern, Klaus-Peter, 5,588,720, Cl. 303-122.080.
- Noetzel, Guenter, 5,589,836, Cl. 342-357.000.
- Stumpe, Werner, 5,588,716, Cl. 303-7.000.
- Winner, Hermann; and Gaillard, Alain, 5,588,718, Cl. 303-113.100.
- Witowski, Edgar; and Mayer, Guenter, 5,588,465, Cl. 137-625.640.
- Zirps, Wilhelm; Schuller, Wolfgang; and Urban, Martin, 5,588,817, Cl. 417-549.000.
- Roberts Systems, Inc., See—
Juchymenko, Victor Y.; Howard, J. Richard; Laczynski, Andrew J.; and Angus, James S., 5,588,235, Cl. 40-547.000.
- Robertson, James W., See—
Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., 5,588,182, Cl. 16-268.000.
- Robertson, John C., See—
Schmut, Robert H.; Robertson, John C.; Gallagher, Richard J.; and Fowler, David N., 5,588,579, Cl. 227-175.100.
- Robertson, Robert, See—
Law, Kam; Robertson, Robert; and Feng, Guofu J., 5,589,233, Cl. 427-579.000.
- Robertson, Stella M.; and Kunkle, Herman M., Jr., to Alcon Laboratories, Inc. Pharmaceutical compositions and methods of treatment of the cornea following laser treatment. 5,589,184, Cl. 424-427.000.
- Robertson, Stella M.; and Kunkle, Herman M., Jr., to Alcon Laboratories, Inc. Pharmaceutical compositions and methods of treatment of the cornea following laser irradiation. 5,589,185, Cl. 424-427.000.
- Robins, Nicholas, to Apple Computer, Inc. Link and discovery protocol for a ring interconnect architecture. 5,590,124, Cl. 370-258.000.
- Robinson, Christopher S., See—
DiFlora, Michael A.; Pandeva, Prakash N.; Robinson, Christopher S.; and Wagner, Philip C., 5,588,810, Cl. 417-312.000.
- Robinson, Darrell, See—
Pruhs, Allen V.; Robinson, Darrell; and Learmont, Robert O., 5,588,874, Cl. 439-517.000.
- Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahroodi, Ebrahim; Robinson, Darrell; Pruhs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107.000.
- Robinson, Donald G.; Geatz, Michael W.; and Corcoran, Michael J., to PAC/SCAN, Inc. Retail theft prevention and information device. 5,589,820, Cl. 340-572.000.
- Robinson, Donald N.; and Peltz, John H., to Elf Atochem North America, Inc. Bonding method employing tie layers for adhering polyethylene to fluoropolymers. 5,589,028, Cl. 156-306.600.
- Robinson, Gary C. Power actuated toilet seat. 5,588,162, Cl. 4-667.000.
- Robinson, Gary G. Golf swing practice device. 5,588,653, Cl. 473-218.000.
- Robinson, Gordon W., to E. R. Squibb & Sons, Inc. Squalene synthetase. 5,589,372, Cl. 425-193.000.
- Robinson, Jeffrey L.; Rouse, Keith; and Musicus, Bruce R., to Logic Devices, Inc. Real time programmable signal processor architecture. 5,590,349, Cl. 395-800.000.
- Robinson, Karol, See—
Firoozabady, Ebrahim; Lemieux, Christine; Moll, Benjamin A.; and Robinson, Karol, 5,589,613, Cl. 800-205.000.
- Robinson, Klaus; and Garvin, Hugh L., to Hughes Aircraft Company. System and method for fabrication of precision optical ramp filters. 5,589,042, Cl. 204-192.340.
- Robotic Vision Systems, Inc., See—
Stern, Howard, 5,589,822, Cl. 340-583.000.
- Rochester Photonics Corporation, See—
Faklis, Dean; and Morris, G. Michael, 5,589,982, Cl. 359-565.000.
- Röck, Erich; and Huber, Edgar, to Julius Blum Gesellschaft m.b.H. Fitting. 5,588,730, Cl. 312-348.200.
- Rode, John E., to Temper Corporation. Apparatus for containing electrical components for sensing or measuring magnetic fields. 5,589,664, Cl. 174-52.100.
- Rodgers, Scott D., See—
Huck, Kamla P.; Rodgers, Scott D.; and Glew, Andrew F., 5,590,297, Cl. 395-401.000.
- Rodriguez, Roberto; and Shroka, Edward T., to Oatey Co. Multi-size roof flashings. 5,588,267, Cl. 52-219.000.
- Roehr, Walter C., Jr., See—
Cameron, Dennis W.; Roehr, Walter C., Jr.; Petrovic, Rade; Bhagat, Jai P.; Garahi, Masood; Hays, William D.; and Ackerman, David W., 5,590,403, Cl. 455-51.200.
- Roell, Friedrich, to TECNIT-Technische Textilien und Systeme GmbH. Textile spacer material, of variable thickness, production process and uses for it. 5,589,245, Cl. 428-85.000.
- Roelofs, Bernardus J. G. M. Method for liquid flow measuring and apparatus to practice this method. 5,588,963, Cl. 604-65.000.
- Roesner, Thomas W., See—

- Hutter, Robert J.; Martin, Christopher J.; and Roesner, Thomas W., 5,588,910, Cl. 454-154.000.
- Rogers, Lloyd W., Jr.: See—
Wright, Kevin; Rogers, Lloyd W., Jr.; Baughman, Robert W.; and Chapman, David J., 5,588,258, Cl. 49-340.000.
- Rohm Co., Ltd.: See—
Nakao, Hironobu, 5,589,700, Cl. 257-325.000.
- Rohr, Jochen. Dredge with bi-directional grizzly, 5,588,536, Cl. 209-385.000.
- Rojas, Carlos I.: See—
Falia, Horacio C.; and Rojas, Carlos I., 5,589,227, Cl. 427-348.000.
- Rolando, Richard J.: See—
Leonard, William K.; Mody, Kirt C.; and Rolando, Richard J., 5,589,122, Cl. 264-146.000.
- Rolf, David B.: See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Rombult, Philip A.: See—
King, Gregg R.; Morrell, John A.; Blake, Lawrence S.; Rombult, Philip A.; and Hebert, Thomas K., 5,589,973, Cl. 359-214.000.
- Römer, Matthias, to Mercedes-Benz AG. Air-spring leg with a pressure chamber for motor vehicles, 5,588,640, Cl. 267-64.110.
- Rörmisch, Jürgen; Auerbach, Bernhard; and Pelzer, Hermann, to Behringwerke Aktiengesellschaft. Method for stabilizing annexins, 5,589,395, Cl. 436-71.000.
- Ronath, Paul D.: See—
Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Ronath, Paul D., 5,589,582, Cl. 536-23.500.
- Roncken, Maria E.: See—
Van Berkel, Cornelis H.; Roncken, Maria E.; and Saeijs, Ronald W. J., 5,590,275, Cl. 395-183.060.
- Roochparvar, Frankie F., to Micron Quantum Devices Inc. Address transition detection (ATD) circuit, 5,590,089, Cl. 365-233.500.
- Roos, David A.: See—
Soleimani, Mohammad; Corrigan, John E., III; Bukhari, Mohammad; and Roos, David A., 5,589,837, Cl. 342-359.000.
- Root, Kevin B.: See—
Allen, John J., Jr.; and Root, Kevin B., 5,590,042, Cl. 364-426.010.
- Ropak Canada Inc.: See—
Martin, Herman W., 5,588,283, Cl. 53-486.000.
- Ropars, Claude: See—
Pages, Etienne; Ropars, Claude; and Bailleul, Christophe, 5,589,389, Cl. 435-306.100.
- Rosa, Margaret D.: See—
Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Ronath, Paul D., 5,589,582, Cl. 536-23.500.
- Rose, Floyd D. Tuning systems for stringed instruments, 5,589,653, Cl. 84-314.00N.
- Rose-Plastic GmbH: See—
Rösler, Peter, 5,588,525, Cl. 206-303.000.
- Rosenfeld, Henry J.: See—
Kaufman, Richard A.; Konopka, John M.; Rosenfeld, Henry J.; and Sabo, Janine E., 5,589,348, Cl. 435-26.000.
- Rosenhouse, Giora: See—
Mizrach, Amos; Galili, Naftali; and Rosenhouse, Giora, 5,589,209, Cl. 426-231.000.
- Rösler, Peter, to Rose-Plastic GmbH. Container for annular workpiece, 5,588,525, Cl. 206-303.000.
- Rospek, Rolf: See—
Gessel, Uwe; Rospek, Rolf; and Zollner, Helmut, 5,589,657, Cl. 102-202.140.
- Ross, Elliott M.: See—
Higashijima, Tsutomu; and Ross, Elliott M., 5,589,568, Cl. 530-324.000.
- Rossman, Jon R.: See—
Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 5,588,158, Cl. 4-572.100.
- Rossman, Kenneth J., to Rotor Clip Company, Inc. Apparatus for installing spring retaining rings, 5,588,204, Cl. 29-809.000.
- Roth, Joseph D.; Obringer, Thomas J.; and Lewis, Monica N., to NCR Corporation. Thermally transferable printing ribbons and methods of making same, 5,589,276, Cl. 428-488.100.
- Rothberger, Richard E., to Whitaker Corporation, The. Connector system with a roller latching mechanism, 5,588,866, Cl. 439-372.000.
- Rotor Clip Company, Inc.: See—
Rossman, Kenneth J., 5,588,204, Cl. 29-809.000.
- Roulin, Monique: See—
Breitler, Hans P.; Sommerer, Klaus; and Roulin, Monique, 5,589,275, Cl. 428-458.000.
- Rouse, Keith: See—
Robinson, Jeffrey I.; Rouse, Keith; and Musicus, Bruce R., 5,590,349, Cl. 395-800.000.
- Routhieu, Vincent Jean-Luc: See—
Marze, Henri-James R.; Routhieu, Vincent Jean-Luc; Arnaud, Gilles L.; and Arnaud, Rémy E., 5,588,618, Cl. 244-17.190.
- Rover Group Limited: See—
Dziama, Krzysztof E.; and Tipping, John, 5,588,481, Cl. 165-42.000.
- Rowland, James R.: See—
Goodnow, James E., II; Kowalski, Thaddeus J.; and Rowland, James R., 5,590,329, Cl. 395-708.000.
- Rowland, Stephen M.: See—
Leone, James E.; and Rowland, Stephen M., 5,588,961, Cl. 604-21.000.
- Roy, Apurba: See—
Law, Ronald L.; Roy, Apurba; and Shewmake, Steven A., 5,588,848, Cl. 439-83.000.
- Roy, Soumitra; and Vehar, Gordon A., to Genentech, Inc. DNA encoding tissue factor mutants useful for the treatment of myocardial infarction and coagulopathic disorders, 5,589,363, Cl. 435-69.600.
- Rozon, Luc, to Booster Pac International Corporation. Portable booster battery, 5,589,292, Cl. 429-170.000.
- Rubbermaid Incorporated: See—
Belden, Dennis D., Jr.; Brightbill, Keith E.; Casteel, Stephen P.; Craft, Charles W.; and Juratovac, Diana W., 5,588,539, Cl. 211-41.000.
- Rubeling, Gunter; and Otten, Burghard, to Günter Rubeling. Method and equipment for the formation of prosthetic tooth structures for fastening to implants, 5,588,837, Cl. 433-172.000.
- Ruby, Arthur C., III; Taylor, Andrew M.; and Spears, William E., Jr., to Corporation, Yelapa. Cleaning method and apparatus utilizing sodium bicarbonate particles, 5,588,901, Cl. 451-99.000.
- Rubin, Leslie S.: See—
Harvey, Andrew C.; Lusignea, Richard W.; and Rubin, Leslie S., 5,589,236, Cl. 428-1.000.
- Ruby, Michael I.: See—
Bliss, Daniel L.; Marshall, Steven E.; and Ruby, Michael I., 5,588,617, Cl. 244-1.00N.
- Ruck, Thomas: See—
Döbeling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelmayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431-354.000.
- Rude, Carl A.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kiehlmeier, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593.000.
- Rudell, Elliot; and Foster, George, to Rudell, Elliot. Method of playing a football game, 5,588,647, Cl. 473-470.000.
- Rudnick, Ellen: See—
Kanan, Paul G.; Smith, Richard H.; and Rudnick, Ellen, 5,589,346, Cl. 435-7.920.
- Rudolph, Bernd; and Vesper, Alwin, to Patent-Treuhand-Gesellschaft F. Elektrische Glühlampen mbH. Semiconductor-controlled operating circuit for one or more low-pressure discharge lamps, typically fluorescent lamps, 5,589,740, Cl. 315-291.000.
- Rudolph, Cathy F.: See—
Sloma, Alan; Rufo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice, 5,589,383, Cl. 435-252.310.
- Rudoy, Edward; and Szalay, John S., to Packard Hughes Interconnect Company. Stamped and formed contacts for a power connector, 5,588,884, Cl. 439-845.000.
- Rudrich, Hans-Peter: See—
Eichholz, Heinz-Dieter; and Rudrich, Hans-Peter, 5,588,636, Cl. 251-129.040.
- Ruf, Hartmut: See—
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruf, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Rufener, Ron: See—
Frye, Ricky J.; Mitts, Jon T.; and Rufener, Ron, 5,589,113, Cl. 264-40.500.
- Ruff, Edward, to Santa's Best. Decorative garland, 5,589,238, Cl. 428-10.000.
- Ruff, Wolfram: See—
Davis, Howard P.; and Ruff, Wolfram, 5,588,986, Cl. 95-211.000.
- Rufo, Gerald A., Jr.: See—
Sloma, Alan; Rufo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice, 5,589,383, Cl. 435-252.310.
- Rugg, James: See—
Hilyard, Kathy; Monticello, James; and Rugg, James, 5,589,327, Cl. 435-4.000.
- Ruhenstroth-Bauer, G. Active substance for inhibiting the proliferation rate of hepatocytes, 5,589,461, Cl. 514-18.000.
- Ruiter, Andrew K.: See—
Osborn, Charles; Medema, Robert M.; and Ruiter, Andrew K., 5,588,934, Cl. 477-96.000.
- Ruiz-Torres, Maximiano: See—
De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C., Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243.000.
- Rule, Antoinette: See—
Liao, Frank Y.; Rule, Antoinette; Frankel, Rise J.; Blicke, Thomas W.; and Bish, Sandra L., 5,590,186, Cl. 379-210.000.
- Rundle, Christopher; and Borell, Michael. Tire stacking method and apparatus, 5,588,538, Cl. 211-23.000.
- Rundle, Christopher; and Borell, Michael. Wheelchair tray accessory, 5,588,663, Cl. 280-304.100.
- Rundle, Christopher; and Borell, Michael. Inflatable safety cushion, 5,588,699, Cl. 297-216.110.
- Runnberg, Bo; and Ljungström, Tommy B. G., to Tetra Laval Holdings & Finance S.A. Apparatus and method for transporting a container between processing stations of a packaging machine, 5,588,279, Cl. 53-426.000.
- Runtz, Michel: See—
Harrand, Michel; and Runtz, Michel, 5,590,070, Cl. 365-149.000.

- Russell, Dale D., to Hewlett-Packard Company. Cage complexes for charge direction in liquid toners, 5,589,311, Cl. 430-114.000.
- Russell, Ernest J., to Texas Instruments Incorporated. Method for a hybrid leadframe-over-chip semiconductor package, 5,589,420, Cl. 437-220.000.
- Russell, John W., to Dow Chemical Company. The. Process for the preparation of cellulose based chiral separation liquid chromatography stationary phase, 5,589,061, Cl. 210-198.200.
- Russell, Steven P.: See—
Krause, Jeffrey; Strohl, Niles E.; Seaman, Michael J.; Russell, Steven P.; and Hart, John H., 5,590,285, Cl. 395-200.200.
- Russell, Todd L.; Richtsmeier, Brent W.; and Glassett, Kevin L., to Hewlett-Packard Company. Air evacuation system for ink-jet printer, 5,589,866, Cl. 347-102.000.
- Russell-Jones, Gregory J.; Howe, Peter; de Aizpurua, Henry J.; and Burge, Geoffrey L., to Biotechnology Australia Pty., Ltd. Oral delivery of biologically active substances bound to vitamin B12, 5,589,463, Cl. 514-21.000.
- Rust, Howell B.; and Hreha, Kenneth W., to Stanley Works, The. Handle with improved grip assembly for hammers and the like and method of making same, 5,588,343, Cl. 81-489.000.
- Rutgers, The State University of New Jersey: See—
Anderson, Stephen, 5,589,154, Cl. 424-1.410.
- Neyra, Carlos A.; and Sadasivan, Lakshmi, 5,589,381, Cl. 435-252.500.
- Ruthrof, Klaus: See—
Jax, Peter; and Ruthrof, Klaus, 5,589,647, Cl. 73-863.230.
- Ruuska, Gregory V.: See—
Fletcher, Robert L.; and Ruuska, Gregory V., 5,590,057, Cl. 364-551.010.
- Ryan, James G.: See—
Mitwalsky, Alexander; and Ryan, James G., 5,589,706, Cl. 257-529.000.
- Ryan, John O., to Macrovision Corporation. Method of and apparatus for scrambling a video signal with full network transmission and recording capability, 5,590,194, Cl. 380-5.000.
- Ryan, John O., to Command Audio Corporation. Information dissemination using various transmission modes, 5,590,195, Cl. 380-9.000.
- Ryan, Michael J.; Lovrin, Jason A.; Strathy, Nancy; and Fantini, Susan E., to American Cyanamid Company. Cloning of the biosynthetic pathway for chlortetracycline and tetracycline formation and cosmid useful therein, 5,589,385, Cl. 435-258.350.
- Ryan, Raymond B.; and Gans, Noah F., to Evergreen Group Incorporated. The. Digital computer system and methods for computing a financial projection and an illustration of a prefunding program for an employee benefit, 5,590,037, Cl. 395-204.000.
- Rydbek, Nils, to Ericsson Inc. Radiotelephone apparatus including a wireless headset, 5,590,417, Cl. 455-89.000.
- Rydbek, Nils R., to Ericsson Inc. Cantenna for a cellular radiotelephone, 5,590,416, Cl. 455-90.000.
- Rykkén, Arne O.; and Meiner, Søren. Arrangement in a furniture member, especially a leg supporting member for a chair, 5,588,708, Cl. 297-423.200.
- Rymo, Lars: See—
Vahlne, Anders; Svennerholm, Bo; Rymo, Lars; Jeansson, Stig; and Horal, Peter, 5,589,175, Cl. 424-208.100.
- Ryohi Limited: See—
Kurihara, Katsumi, 5,588,408, Cl. 123-196.00W.
- Saarna, Mart; Kelve, Merik; Truve, Erkki; and Teemu, to Kemira Oy, Biotech. Transgenic plants displaying multiple virus resistance and a process for their production, 5,589,625, Cl. 800-205.000.
- Sabater, Jacques; Tourlet, Guy E. P.; and Jayet, Gérard, to Centre Technique de l'Industrie des Papiers, Cartons et Celluloses. Device for the measurement of a profile on a plane surface, 5,589,941, Cl. 356-376.000.
- Sabaran, Al A.: See—
Emambakhsh, Al S.; Pionk, Michael P.; Sabaran, Al A.; and Wallner, John P., 5,588,667, Cl. 280-728.200.
- Sabermick, Fred C.: See—
Rahman, Mizanur M.; Sabermick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735.000.
- Sabo, Janine E.: See—
Kaufman, Richard A.; Konopka, John M.; Rosenfeld, Henry J.; and Sabo, Janine E., 5,589,348, Cl. 435-26.000.
- Sabol, Jeffrey S.: See—
McCarthy, James R.; Matthews, Donald P.; Sabol, Jeffrey S.; McConnell, James R.; Donaldson, Richard E.; and Duquid, Robert, 5,589,587, Cl. 536-28.500.
- Sacchetti, Mario: See—
Govoni, Gabriele; Sacchetti, Mario; and Pasquali, Stefano, 5,589,549, Cl. 525-247.000.
- Sachleben, Harold K. Collapsible reel, 5,588,628, Cl. 242-607.100.
- Sachse, Burkhard: See—
Ulbrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205.000.
- Sackner, Marvin A.; and Inman, Dana M., to Nims Incorporated. Method and apparatus for discriminating between valid and artifactual pulse waveforms in pulse oximetry, 5,588,425, Cl. 128-632.000.
- Sadasivan, Lakshmi: See—
Neyra, Carlos A.; and Sadasivan, Lakshmi, 5,589,381, Cl. 435-252.500.
- Sadehpour, Hamid R.: See—
Davidson, Dale D.; and Sadehpour, Hamid R., 5,589,749, Cl. 318-564.000.
- Saeijs, Ronald W. J. J.: See—
Van Berkel, Cornelis H.; Roncken, Maria E.; and Saeijs, Ronald W. J. J., 5,590,275, Cl. 395-183.060.
- Saga University: See—
Uehara, Haruo; and Ikegami, Yasuyuki, 5,588,297, Cl. 60-673.000.
- Sagami Chemical Research Center: See—
Tsuiji, Tomoko; Yamaguchi, Kohji; Kondo, Kiyosi; and Urakami, Teizi, 5,589,481, Cl. 514-287.000.
- Sagara, Shoichi: See—
Idei, Takashi; Sagara, Shoichi; and Fujibayashi, Kentaro, 5,589,750, Cl. 318-573.000.
- Sahatjian, Ronald A.: See—
Nicholas, Peter M.; Sahatjian, Ronald A.; and Barry, James J., 5,588,962, Cl. 604-52.000.
- Saida, Yoshihiro: See—
Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, 5,589,270, Cl. 428-411.100.
- Saiki, Yoshiharu: See—
Onishi, Yasushi; and Saiki, Yoshiharu, 5,590,253, Cl. 395-133.000.
- Saito, Akihiko: See—
Tepman, Avi; Jinbo, Takeshi; Takahama, Hiroyuki; and Saito, Akihiko, 5,589,224, Cl. 427-248.100.
- Saito, Katsuyuki: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Saito, Keisuke: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.
- Saito, Kenji; and Shinkai, Yasuhiro, to Fuji Photo Film Co., Ltd. Performing white balance correction on integrated divided areas of which average color is substantially white, 5,589,879, Cl. 348-223.000.
- Saito, Koichi: See—
Suzuki, Masao; Saito, Koichi; and Nakata, Masahide, 5,589,515, Cl. 514-784.000.
- Saito, Makoto: See—
Mori, Hiroshi; Tanaka, Masakazu; Mabuchi, Mamoru; and Saito, Makoto, 5,589,143, Cl. 422-171.000.
- Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126.000.
- Saito, Osamu: See—
Watanabe, Mikio; Aoki, Akira; and Saito, Osamu, 5,590,306, Cl. 395-442.000.
- Saito, Satoru; Tatsu, Haruyoshi; German, Lev S., deceased (by Elena N. German, legal representative), to Nippon Mektron, Limited. Fluoroelastomer and process for producing the same, 5,589,559, Cl. 526-247.000.
- Saito, Seiichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shiohara, Junji; and Kawamae, Osamu, to Hitachi, Ltd. Header information of information signal recording and reproducing method and apparatus therefor, 5,589,995, Cl. 360-48.000.
- Saito, Takanori: See—
Okabe, Hideaki; Suzuki, Eiji; Kogure, Masao; and Saito, Takanori, 5,589,192, Cl. 424-486.000.
- Saito, Tatsu; and Goto, Shigenori, to Fuji Photo Optical Co., Ltd. Apparatus for measuring a distance, 5,589,910, Cl. 396-106.000.
- Saito, Tomokatsu: See—
Takeshima, Taku; Noro, Masayuki; and Saito, Tomokatsu, 5,590,255, Cl. 395-141.000.
- Saito, Yutaka; and Kojima, Yoshikazu, to Seiko Instruments Inc. Real-time semiconductor radiation detector, 5,589,705, Cl. 257-459.000.
- Saitoh, Takashi: See—
Shimizu, Shigeru; Saitoh, Takashi; Uzawa, Masashi; and Takayanagi, Yasuyuki, 5,589,108, Cl. 252-500.000.
- Saitou, Shinji, to Matsushita Electric Industrial Co., Ltd. Mechanical sensor for detecting stress or distortion with high sensitivity, 5,589,770, Cl. 324-209.000.
- Sakachi, Yoichiro: See—
Kawata, Satoshi; Dohi, Masaji; Sakachi, Yoichiro; and Daiku, Hiroshi, 5,589,687, Cl. 250-338.300.
- Sakaguchi, Takahiro; and Sakamoto, Fumio, to TEAC Corporation. Sheet coil motor and method of fabricating the same, 5,589,722, Cl. 310-180.000.
- Sakaguchi, Toshiaki: See—
Akimoto, Yoshiaki; Tanaka, Hideo; Ogi, Hiromi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, 5,590,243, Cl. 395-23.000.
- Sakai, Akira: See—
Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249.000.
- Sakai, Mayumi: See—
Nagamitsu, Sachio; Kodama, Hisashi; Sakai, Mayumi; Hattori, Yoshihiro; and Okada, Tunekio, 5,590,062, Cl. 364-578.000.
- Sakai, Toshio: See—
Fujita, Shigeru; and Sakai, Toshio, 5,589,875, Cl. 348-143.000.

- Sakai, Yukari: See—
Hama, Hideo; and Sakai, Yukari, 5,589,966, Cl. 349-194,000.
- Sakakibara, Hisayoshi; Okada, Tomoo; and Ikeda, Tadaaki, to Kabushiki Kaisha Saginomiya Seisakusho; and Nippondenso Co., Ltd. Expansion valve combined with a solenoid valve, 5,588,590, Cl. 236-92,00B.
- Sakakibara, Makoto: See—
Koyano, Shinji; Kogure, Koushirou; Ohya, Takashi; Sakakibara, Makoto; and Hanayama, Katsutoki, 5,590,208, Cl. 381-154,000.
- Sakakibara, Tadayuki; Tanaka, Teruo; Tamaki, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuhiro, to Hitachi, Ltd. Vector processor adopting a memory skewing scheme for preventing degradation of access performance, 5,590,353, Cl. 395-800,000.
- Sakakura, Shinya; Ohashi, Ryota; and Sakikawa, Shigenori, to Kanzaki Kokyukoki Mfg. Co. Ltd. Hydrostatic transmission, 5,588,294, Cl. 60-464,000.
- Sakamoto, Fumio: See—
Sakaguchi, Takahiro; and Sakamoto, Fumio, 5,589,722, Cl. 310-180,000.
- Sakamoto, Kiichi: See—
Abe, Tomohiko; Yasuda, Hiroshi; Sakamoto, Kiichi; and Oae, Yoshihisa, 5,590,048, Cl. 364-489,000.
- Sakamoto, Yoshio: See—
Matsuo, Shinta; and Sakamoto, Yoshio, 5,590,210, Cl. 381-199,000.
- Sakata, Goro: See—
Hanzawa, Koharo; Sakata, Goro; and Tanaka, Kikui, 5,590,364, Cl. 395-800,000.
- Sakaue, Tsuyoshi: See—
Sato, Yuki; Ishizaki, Toshio; Sakaue, Tsuyoshi; Hashimoto, Koji; Yamada, Tohru; and Uwano, Tomoki, 5,589,724, Cl. 310-348,000.
- Sakikawa, Shigenori: See—
Sakakura, Shinya; Ohashi, Ryota; and Sakikawa, Shigenori, 5,588,294, Cl. 60-464,000.
- Sakimura, Tomoo: See—
Etch, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirofumi; Sakimura, Tomoo; Suzuki, Tomoko; and Kinoshita, Akira, 5,589,314, Cl. 430-126,000.
- Sakimura, Tomoko; Kinoshita, Akira; Hayata, Hirofumi; and Sakimura, Tomoo, 5,589,309, Cl. 430-59,000.
- Sakurada, Hiroshi: See—
Onodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Teruo; and Itoh, Shigeo, 5,589,738, Cl. 315-169,100.
- Sakurada, Noriaki, to Seiko Epson Corporation. Semiconductor memory device with enable signal conversion circuit operative for reducing current consumption, 5,590,088, Cl. 365-233,000.
- Sakurai, Osamu: See—
Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, 5,589,165, Cl. 424-78,030.
- Sakurai, Yoshito: See—
Tomomura, Yukiko; Sakurai, Yoshito; and Nishi, Yumiko, 5,590,180, Cl. 379-112,000.
- Sala, Alberto; Banfi, Aldo; Benedini, Francesca; and Cereda, Roberta, to Italfarmaco S.p.A. Benzocic acid substituted derivatives having cardiovascular activity, 5,589,490, Cl. 514-330,000.
- Salazar-Vior, Jose M.: See—
Stone, Dwight V.; Long, Douglas A.; and Salazar-Vior, Jose M., 5,588,413, Cl. 123-508,000.
- Salem Englehard: See—
Gribbon, Sean T., 5,589,142, Cl. 422-171,000.
- Sallen, Roy; Budzyna, W. James; and Sawabini, Charles E., to Secure Technologies, Inc. Distance determination and alarm system, 5,589,821, Cl. 340-573,000.
- Salvaneschi, Marco, to Necchi Compressori S.r.l. Terminal box for hermetic compressors, 5,588,871, Cl. 439-469,000.
- Samelson, Judy A. Method for making a container from recycled product, 5,588,196, Cl. 29-401,100.
- Samson, Jeffrey T.: See—
Poulson, Keith L.; Parker, Robert M.; Samson, Jeffrey T.; and Taylor, Harry B., 5,588,159, Cl. 4-572,100.
- Samson, Randall J.; Budlong, Allan; and Huslig, Dan, to Motorola, Inc. Multi-mode transmitter for transmitter for signals having varying deviation levels, 5,590,402, Cl. 455-44,000.
- Samsung Electronics Co., Ltd.: See—
An, Hyeon-keon; Shin, Young-ho; and Kim, Suk-ki, 5,590,206, Cl. 381-71,000.
- Beak, Soon-ki, 5,588,625, Cl. 248-371,000.
- Choi, Jeong-Hyuk, 5,590,072, Cl. 365-185,010.
- Eom, Jae-Yong, 5,590,098, Cl. 369-13,000.
- Kim, Jeong-tae, 5,589,997, Cl. 360-77,140.
- Lee, Don-Seon; and Kim, Seong-Woo, 5,589,923, Cl. 399-28,000.
- Lee, Hee-Soo, 5,590,204, Cl. 381-24,000.
- Lee, Jae-Hyeon; and Seok, Yong-sik, 5,590,079, Cl. 365-201,000.
- Lee, Sang-in; and Park, Chang-soo, 5,589,713, Cl. 257-773,000.
- Paik, Chong-ryul, 5,590,385, Cl. 419-10,000.
- Park, Churo; Jang, Hyun-Soon; Kim, Chul-Soo; Kim, Myung-Ho; Lee, Seung-Hun; Lee, Si-Yeol; Lee, Ho-Cheol; Kim, Tae-Jin; and Choi, Yun-Ho, 5,590,086, Cl. 365-230,030.
- Samsung Semiconductor, Inc.: See—
Knee, Derek L., 5,589,831, Cl. 341-159,000.
- Sanborn, Duane F.: See—
Hartfield, Jon P.; and Sanborn, Duane F., 5,588,596, Cl. 239-542,000.
- Sanchez-Sinencio, Feliciano: See—
De La Luz Martinez, Jose; Gonzalez-Hernandez, Jesus; Sanchez-Sinencio, Feliciano; Ruiz-Torres, Maximiano; De Dios Figueroa C., Juan; and Martinez-Bustos, Fernando, 5,589,210, Cl. 426-243,000.
- Sancoff, Gregory E.; Doyle, Mark C.; and Field, Frederic P., to River Medical, Inc. Method for generating gas to deliver liquid from a container, 5,588,556, Cl. 222-1,000.
- Sand, Edward A., to Western Textile Products Company. Method for manufacturing improved back pocket blank for pants, 5,588,385, Cl. 112-475,090.
- Sand, Gunnar, to Stromsholmens Mekaniska Verkstad AB. Gas spring which after compression has a time delayed return to its original length, 5,588,641, Cl. 267-119,000.
- Sandbank, Alberto: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Sande, Walter E.; and Sears, Karl D., to Rhone-Poulenc Inc. Method for preparing vanillin from old newspaper, 5,589,030, Cl. 162-7,000.
- Sander, Dieter; and Meyer, Uwe F. Tamper evident resealable plastic closure, 5,588,562, Cl. 222-153,060.
- Sandia Corporation: See—
Frye, Gregory C.; Brinker, C. Jeffrey; Doughty, Daniel H.; Bein, Thomas; and Moller, Karin, 5,589,396, Cl. 436-73,000.
- Sandler, Harold; and Ip, Kendy. Multiple phone line adaptor, 5,590,185, Cl. 379-163,000.
- Sandman, Terry L.: See—
Ribando, Philip P.; Bolam, Kenneth M.; Peeler, Donald H.; and Sandman, Terry L., 5,588,954, Cl. 601-149,000.
- Sandmeier, Hermann: See—
Achelpohl, Fritz; and Sandmeier, Hermann, 5,588,944, Cl. 493-205,000.
- Sandnes, Rolf W.; Undheim, Kjell; Gacek, Michel; and Vasilevskis, Janis, to Nycomed Imaging AS. Process for tetraazacycloalkane preparation, 5,589,595, Cl. 540-474,000.
- Sandorfi, Miklos A.; and Shriki, Moshe M., to EMC Corporation. Method and apparatus for reordering frames, 5,590,122, Cl. 370-394,000.
- Sanford, James R. M.; Frank, Patrick M.; Golias, Joseph H.; and Jennings, William C., to Helena Laboratories Corporation. Column analyzer system and improved chromatograph column for use in the system, 5,589,063, Cl. 210-198,200.
- Sangveraphunsiri, Vic; Pinai, Felix; Shu, Thomas; and Spears, Cameron, to Advanced Logic Research. Apparatus for performing concurrent seeks on plural integrated drive electronics (IDE) disk drives without additional devices, 5,590,375, Cl. 395-841,000.
- Sankar, Lakshmi N.: See—
Charles, Bruce D.; Hassan, Ahmed A.; Tadghighi, Hormoz; JanakiRam, Ram D.; and Sankar, Lakshmi N., 5,588,800, Cl. 416-24,000.
- Sannel, Benjamin H.: See—
Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.
- Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikiyo; and Koeda, Takashi, to Asahi Kogyo Kogyo Kaishiki Kaisha. Portable endoscope system, 5,588,950, Cl. 600-178,000.
- Sano, Kenji: See—
Horie, Seiji; Sano, Kenji; Suzuki, Nobuo; and Watarai, Shu, 5,589,312, Cl. 430-115,000.
- Sano, Masaaki: See—
Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126,000.
- Sano, Shoichi: See—
Natori, Hiroaki; Takei, Hitoshi; Sano, Shoichi; and Tamaki, Shoichi, 5,589,873, Cl. 348-15,000.
- Sano, Tomomi: See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53,000.
- Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, to NEC Corporation; and Japan Aviation Electronics Industry, Limited. Semiconductor package, 5,589,711, Cl. 257-718,000.
- Santa Maria, Carmen S.: See—
Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Naura, William S.; and McKinley, Gareth H., 5,588,509, Cl. 188-267,000.
- Santa's Best: See—
Ruff, Edward, 5,589,238, Cl. 428-10,000.
- Santel, Hans-Joachim: See—
Fischer, Reiner; Kruger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91,000.
- Santos, Ameurino D.: See—
Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurino D., 5,589,340, Cl. 435-6,000.
- Sanyo Electric Co., Ltd.: See—
Ishihara, Manabu; Rakuma, Tsuyoshi; Kanai, Hiroshi; Fudo, Takashi; and Watanabe, Masato, 5,588,589, Cl. 236-46,000.

- Kaite, Osamu; Okada, Tatsuya; and Kokuga, Toshiharu, 5,589,755, Cl. 320-21,000.
- Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao, 5,590,412, Cl. 455-82,000.
- Sarcos, Inc.: See—
Jacobsen, Stephen C.; Potter, Dwight; and Smith, Fraser, 5,588,688, Cl. 294-106,000.
- Sargent & Lundy: See—
Kallenbach, Ralph M., 5,588,511, Cl. 188-374,000.
- Sarkadi, Adam: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedus, Bela; Szpony, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszy, Judit; Szentirmai, Zsolt; Lapis, Erzsebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317,000.
- Saruwatari, Masatoshi: See—
Takara, Hidehiko; Kawanishi, Satoki; and Saruwatari, Masatoshi, 5,590,143, Cl. 372-28,000.
- Sasaki, Kunimasa; Wakiyama, Yoichi; Matsumoto, Takahiro; Tanaka, Kiyaburo; and Yamamoto, Keiichi, to Mitsubishi Jukogyo Kabushiki Kaisha. Cooling drum for a continuous casting system and method for manufacturing the same, 5,588,582, Cl. 228-127,000.
- Sasaki, Toshiaki: See—
Ookawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, 5,590,109, Cl. 369-77,200.
- Sasaki, Yuu; Iwasawa, Junichi; and Yamada, Masahiro, to Sony Corporation; and Asahi Research Corp. Video lighting apparatus and electrode apparatus therefor, 5,588,732, Cl. 362-10,000.
- Sasame, Hiroshi: See—
Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399-350,000.
- Sasano, Akira: See—
Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, 5,589,962, Cl. 349-46,000.
- Sasao, Fuyuko: See—
Okano, Yoshinobu; Isegawa, Yuji; Sasao, Fuyuko; and Ueda, Shigeharu, 5,589,174, Cl. 424-147,100.
- Sato, Inc.: See—
Locker, Robert, 5,588,371, Cl. 108-51,100.
- Sato, Goichi: See—
Marui, Kuniyoshi; and Sato, Goichi, 5,590,414, Cl. 455-89,000.
- Sato Iron Works Co., Ltd.: See—
Sato, Takuya, 5,589,203, Cl. 425-147,000.
- Sato, Katsuhiko: See—
Miyano, Shinji; Sato, Katsuhiko; and Yabe, Tomoaki, 5,590,084, Cl. 365-230,010.
- Sato, Kazuhiko: See—
Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, 5,588,936, Cl. 477-155,000.
- Sato, Koichi: See—
Takada, Minoru; Sato, Koichi; and Yokobayashi, Kazuyuki, 5,589,130, Cl. 264-537,000.
- Sato, Masahiko, to NEC Corporation. Super-resolution optical head using optical separator, 5,590,110, Cl. 369-100,000.
- Sato, Masaki: See—
Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, 5,590,314, Cl. 395-681,000.
- Sato, Masaru: See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279,000.
- Sato, Masuhiro; and Inaba, Naoto, to Pioneer Electronic Corporation. Karaoke system having a plurality of terminal and a center system, 5,589,947, Cl. 386-96,000.
- Sato, Noriaki; and Mieno, Fumitake, to Fujitsu Limited. An integrated semiconductor device having a buried semiconductor layer and fabrication method thereof, 5,589,410, Cl. 437-40,000.
- Sato, Osamu; and Mochida, Fumio, to Canon Denshi Kabushiki Kaisha. Speed controller or an instrument having a speed controller including detection means for linearly detecting the amount of rotation less than one full rotation of a rotating member, 5,590,236, Cl. 388-821,000.
- Sato, Takashi, to Murao Co., Ltd. Accessories, 5,588,190, Cl. 24-682,100.
- Sato, Takashi: See—
Tomofuji, Yoko; Nakase, Makoto; Sato, Takashi; Hazama, Hiroaki; Komano, Haruki; and Ito, Shinichi, 5,589,305, Cl. 430-5,000.
- Sato, Takuya, to Sato Iron Works Co., Ltd. Vacuum kneading and extruding apparatus, 5,589,203, Cl. 425-147,000.
- Sato, Toshifumi; and Furuya, Yukitsuna, to NEC Corporation. Base station transmission-reception apparatus for cellular system, 5,590,404, Cl. 455-53,100.
- Sato, Yasushi; and Kamibayashi, Kaname, to Sony/Tektronix Corporation. Disc high resolution scanner, 5,589,952, Cl. 358-487,000.
- Sato, Yohei: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadaaki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87,000.
- Sato, Yutaka; Morita, Koichi; Fujimoto, Shuzo; Ichihashi, Satoru; and Ohsawa, Kohji, to Honda Giken Kogyo Kabushiki Kaisha. Method of assembling set oil ring on piston, 5,588,208, Cl. 29-888,044.
- Sato, Yuki; Ishizaki, Toshio; Sakaue, Tsuyoshi; Hashimoto, Koji; Yamada, Tohru; and Uwano, Tomoki, to Matsushita Electric Industrial Co., Ltd. Piezoelectric device and a package, 5,589,724, Cl. 310-348,000.
- Satomi, Yasuhiko; Itoh, Seichi; Otsuka, Eiji; Yamaki, Jun; and Kato, Takashi, to Nippon Sanso Corporation. Method of manufacturing metallic vacuum double-walled container, 5,588,197, Cl. 29-455,100.
- Sattelmayer, Thomas: See—
Döbbling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelmayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431-354,000.
- Saturn Corporation: See—
Downs, Robert C.; Mainquist, James K.; Nitz, Larry T.; and Aldrich, William L., III, 5,588,327, Cl. 74-335,000.
- Sauer Inc.: See—
Geringer, Kerry G., 5,588,805, Cl. 417-53,000.
- Saulpaugh, Thomas E.; Bruffey, Bill M.; and Williams, Russell T., to Apple Computer, Inc. Object oriented message passing system and method, 5,590,334, Cl. 395-683,000.
- Saunders, Court A.: See—
Chappell, Joseph; Saunders, Court A.; and Wolf, Fred R., 5,589,619, Cl. 800-205,000.
- Saur, Reinhold: See—
Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275,000.
- Sauter, Hubert: See—
Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schelberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275,000.
- Sauter, Mark E.: See—
Spiegelberg, Bernard N.; and Sauter, Mark E., 5,589,294, Cl. 429-178,000.
- Sauvestre, Jean-Claude. Sabot with controlled separation of the elements for subcaliber projectiles, 5,589,658, Cl. 102-521,000.
- Savage, John R.: See—
Neely, Michael J.; and Savage, John R., 5,588,804, Cl. 416-223,000.
- Sawa, Atsushi; and Kawakubo, Hiroyuki, to Honda Giken Kogyo Kabushiki Kaisha. Arrangement of oil passage to valve system, 5,588,405, Cl. 123-90,330.
- Sawabini, Charles E.: See—
Sallen, Roy; Budzyna, W. James; and Sawabini, Charles E., 5,589,821, Cl. 340-573,000.
- Sawada, Hideaki: See—
Iwasaki, Itsutoshi; Yamasaki, Tatsuo; and Sawada, Hideaki, 5,589,426, Cl. 501-32,000.
- Sawada, Kiyoshi; and Odaka, Shun'ichi, to Fanuc Ltd. Method and apparatus for electrical discharge machining with control of a servomechanism by a position loop and a speed loop, 5,589,086, Cl. 219-69,160.
- Sawada, Michio: See—
Yamada, Kunio; and Sawada, Michio, 5,590,380, Cl. 395-868,000.
- Sawada, Yoshitsugu, to Yazaki Corporation. Connector, 5,588,875, Cl. 439-595,000.
- Sawahashi, Mamoru; and Adachi, Fumiyuki, to NTT Mobile Communications Network Inc. Transmission power control method and a transmission power control apparatus, 5,590,409, Cl. 455-69,000.
- Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao, to Sanyo Electric Co., Ltd. Communication apparatus using common amplifier for transmission and reception, 5,590,412, Cl. 455-82,000.
- Sawamoto, Isao: See—
Shimamune, Takayuki; Nakamatsu, Shuji; Sawamoto, Isao; and Nishiki, Yoshinori, 5,589,052, Cl. 205-349,000.
- Sawaoka, Ryuji; Kouchi, Shinji; and Muraki, Toshio, to Toray Industries, Inc. Microcapsule-type curing agent, method for producing the same, thermosetting resin composition, prepreg and fiber reinforced composite material, 5,589,523, Cl. 523-211,000.
- Sawatari, Norio: See—
Takezawa, Satoshi; Katagiri, Yoshimichi; Nakamura, Yasushige; and Sawatari, Norio, 5,589,313, Cl. 430-122,000.
- Say, Geoffrey R.: See—
Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127,900.
- Scamacca, Randal. Child-resistant electrical outlet cover, 5,589,665, Cl. 174-67,000.
- Scannell, Robert; Busse, Bernd; and Vormwald, Helmut, to Heraeus Electrochemie GmbH. Electrode for electrolysis cells, 5,589,044, Cl. 204-286,000.
- Schaarschmidt, Manfred: See—
Götz, Klaus P.; Schaarschmidt, Manfred; and Feldmeier, Günter, 5,588,885, Cl. 439-876,000.
- Schacter, Bernice Z.: See—
Hawley, Robert J.; Monroy, Rodney L.; Rosa, Margaret D.; Schacter, Bernice Z.; and Ronath, Paul D., 5,589,582, Cl. 536-23,500.

- Schantz, Christopher A. Inkjet printhead electrical connections. 5,589,859. Cl. 347-19.000.
- Schantz, Spencer C.: See—
Hackbarth, David G.; Hapke, Kenyon A.; and Schantz, Spencer C., 5,589,671, Cl. 200-6.00R.
- Scharstein, Daniel: See—
Scharstein, Hans; Krotz-Vogel, Werner; and Scharstein, Daniel, 5,590,093, Cl. 368-15.000.
- Scharstein, Hans; Krotz-Vogel, Werner; and Scharstein, Daniel. Digital sundial. 5,590,093, Cl. 368-15.000.
- Scharwächter, Dieter: See—
Järvenkylä, Jyri; Scharwächter, Dieter; Johansson, Åke; and Kristensson, Ronny, 5,589,127, Cl. 264-280.000.
- Schechtman, Howard: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Scheffee, Robert S.: See—
Sides, James R.; Martin, James D.; and Scheffee, Robert S., 5,589,141, Cl. 422-164.000.
- Scheffel, Herbert. Railway vehicle suspensions. 5,588,367, Cl. 105-168.000.
- Schellberger, Klaus: See—
Eicken, Karl; Müller, Bernd; Sauter, Hubert; Lorenz, Gisela; Ammermann, Eberhard; Schellberger, Klaus; and Saur, Reinhold, 5,589,479, Cl. 514-275.000.
- Schell, Josef: See—
Ulrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205.000.
- Schenkel, Décio L. Unidirectional air transfer system for shoes. 5,588,226, Cl. 36-3.00B.
- Scherber, Werner: See—
Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425.600.
- Scheurman, Clarence, III, to Applied Specialties, Inc. Method and composition for inhibiting corrosion. 5,589,107, Cl. 252-392.000.
- Schick, Lloyd A.: See—
Kopf-Sill, Anne R.; Buhl, Steven N.; Choate, Glenda L.; Schick, Lloyd A.; Nagle, Robert E.; Chang, Jenq C.; Bernstein, Daniel; and Britz, Wayne A., 5,590,052, Cl. 364-498.000.
- Schickler, Mark E.: See—
Meyers, Mark M.; and Schickler, Mark E., 5,589,983, Cl. 359-566.000.
- Schiebe, Lowell H.: See—
Cho, Sung K.; and Schiebe, Lowell H., 5,589,080, Cl. 210-791.000.
- Schier, J. Alan. Position encoder system which utilizes the fundamental frequency of a ruled scale on an object. 5,590,059, Cl. 364-559.000.
- Schifko, Herbert: See—
Berger, Ernst; Heil, Franz; Schifko, Herbert; and Tecchio, Piero, 5,589,674, Cl. 218-71.000.
- Schiller, Stephen N. to Adobe Systems Incorporated. Method of generating a threshold array. 5,590,223, Cl. 382-270.000.
- Schilt, John A. Portable collapsible ventilator. 5,588,386, Cl. 114-211.000.
- Schleicher, Ulrich; Klobner, Martin; Schwarz, Wolfgang; and Feuerstake, Eugen, to Honda Giken Kogyo Kaisha, Pyrotechnic mixture and gas generator for an airbag. 5,589,662, Cl. 149-35.000.
- Schlesinger, Robert: See—
Maloney, Michael; and Schlesinger, Robert, 5,590,128, Cl. 370-260.000.
- Schliesser, Lothar, to Emhart, Inc. Anti-resonance pipe clip. 5,588,683, Cl. 285-62.000.
- Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeier, Klaus; and Thomas, Martin, to Fresenius AG. Use of an emulsion to prepare an intravenously administered medicament for treating skin diseases. 5,589,508, Cl. 514-560.000.
- Schlumberger Industries, Inc.: See—
Merrett, Stanley L., 5,588,779, Cl. 405-54.000.
- Schmid, Christopher J.: See—
Flinchbaugh, Bernadette M.; Gabany, Andrew J.; Melnyk, Adrian L.; and Schmid, Christopher J., 5,588,878, Cl. 439-682.000.
- Schmid, Helmut: See—
Menke, Klaus; Böhnlein-Mauss, Jutta; Schmid, Helmut; Bucarius, Klaus M.; and Engel, Walther, 5,589,661, Cl. 149-19.400.
- Schmid, Karl: See—
Pi, Raphael; Bigorra-Losas, Joaquim; Ponsati-Obiols, Oriol; and Schmid, Karl, 5,589,450, Cl. 510-535.000.
- Schmidt, Christopher G.; Fisher, Michael H.; de Almeida, Amilton F.; and Tani, Edson T., to Whirlpool Corporation. Refrigerator door construction. 5,588,731, Cl. 312-405.000.
- Schmidt, Erik, to Erik Schmidt Autotilbehör Aps. Cycle rack. 5,588,574, Cl. 224-520.000.
- Schmidt, Glenn H.; and Helmstetter, Richard C., to Callaway Golf Company. Iron golf club head with forwardly divergent interior recess. 5,588,922, Cl. 473-324.000.
- Schmidt, Glenn H.; and Helmstetter, Richard C., to Callaway Golf Company. Golf club head with attached selected swing weight composite. 5,588,923, Cl. 473-340.000.
- Schmidt, Hans, to Linde Aktiengesellschaft. Process for obtaining an ethane-rich fraction for refilling an ethane-containing refrigerant circuit of a process for liquefaction of a hydrocarbon-rich fraction. 5,588,306, Cl. 62-614.000.
- Schmidt, Hans, to Linde Aktiengesellschaft. Process for liquefaction of a pressurized hydrocarbon-rich fraction. 5,588,307, Cl. 62-614.000.
- Schmidt, Helmut; Nass, Rüdiger; Aslan, Mesut; Albayrak, Sener; Arpac, Ertugrul; König, Theo; and Fister, Dietmar, to H. C. Starck, GmbH & Co. KG. Method for producing metal and ceramic sintered bodies and coatings. 5,590,387, Cl. 419-36.000.
- Schmidt, Robert R.: See—
Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorf-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91.000.
- Schmidt, William P.; and Hutchinson, Franklin D., to Mirror Lite of North Carolina. Oval elliptical mirror. 5,589,984, Cl. 359-603.000.
- Schmitt, Joel A. Modular storage unit kit. 5,588,540, Cl. 211-90.000.
- Schmitt, Klaus-Dieter: See—
Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000.
- Schmitter, André: See—
Reinehr, Dieter; Bacher, Jean-Pierre; and Schmitter, André, 5,589,529, Cl. 524-91.000.
- Schmittauesler, Roland: See—
Patai, Jean-Louis; Delmas, Olivier; and Schmittauesler, Roland, 5,589,462, Cl. 514-21.000.
- Schnabel Foundation Company: See—
Brandl, Ernest D.; and Weatherby, David E., 5,588,784, Cl. 405-262.000.
- Schnappinger, Dirk: See—
Bujard, Hermann; Gossen, Manfred; Hillen, Wolfgang; Helbl, Vera; and Schnappinger, Dirk, 5,589,362, Cl. 435-69.100.
- Schnatwinkel, Michael: See—
Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709.000.
- Schneider, Richard: See—
Stahl, Hans-Jürgen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, 5,588,829, Cl. 432-77.000.
- Schneider, Stanley: See—
Meyn, William C.; and Schneider, Stanley, 5,590,161, Cl. 375-368.000.
- Schneider, Werner; Lerch, Hansueli; and Hausmann, Erich, to Fritz Gegauf AG Bernina Nähmaschinenfabrik. Strength of a muscle training apparatus. 5,588,938, Cl. 482-4.000.
- Schnut, Robert H.; Robertson, John C.; Gallagher, Richard J.; and Fowler, David N., to United States Surgical Corporation. Anvil for circular stapler. 5,588,579, Cl. 227-175.100.
- Schoenbek Worldwide Lighting, Inc.: See—
Lucas, John M.; Schonbek, Arnold; and Bayer, Georg, 5,588,744, Cl. 362-405.000.
- Schoenfelder, Angèle: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoep, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Schoep, Darryle D.: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoep, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Schofield, Harold D.: See—
Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700.000.
- Schofield, Harry; Caron, Paul; Field, Gary; and Follent, Paul, to Atlantek Inc. Multi-head wide-format thermal plotter. 5,589,868, Cl. 347-171.000.
- Schogenov, Klim A.: See—
Medvedev, Igor N.; and Schogenov, Klim A., 5,589,050, Cl. 204-630.000.
- Schonbek, Arnold: See—
Lucas, John M.; Schonbek, Arnold; and Bayer, Georg, 5,588,744, Cl. 362-405.000.
- Schoonover, Nicholas J.: See—
Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Schork, Roger: See—
Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Mattutat, Manfred; and Schmitt, Klaus-Dieter, 5,589,242, Cl. 428-45.000.
- Schott Glaswerke: See—
Busch, Dietrich; and Leroux, Roland, 5,588,421, Cl. 126-200.000.
- Donne, Mario Dalle; Schumacher, Gustav; Geiler, Volkmar; Clement, Marc; and Speit, Burkhard, 5,589,427, Cl. 501-33.000.
- Schott, Hans: See—
Alber, Friedrich; Dedelmahr, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605.000.
- Schöttle, Thomas: See—
Felix, Bernd; Hintzer, Klaus; Löhr, Gernot; and Schöttle, Thomas, 5,589,558, Cl. 526-247.000.
- Schrettinger, Christian: See—

- Feldmeier, Günter; and Schrettinger, Christian, 5,588,857, Cl. 439-248.000.
- Schroeder, William J.: See—
Zarge, Jonathan A.; and Schroeder, William J., 5,590,248, Cl. 395-121.000.
- Schubert, Craig N.: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickey; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242.400.
- Schuch, Wolfgang W.: See—
Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., 5,589,614, Cl. 800-205.000.
- Schudel, Dale F., to K. R. Precision Public Company Limited. Tightened distribution of magnetic-head suspension-assembly static roll by infrared stress relief. 5,588,200, Cl. 29-603.010.
- Schuetz, Hartmut: See—
Barthel, Herbert; Daar, Horst; and Schuetz, Hartmut, 5,590,278, Cl. 395-185.060.
- Schuller International, Inc.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kiemeyer, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593.000.
- Miller, Donald L., 5,588,976, Cl. 55-514.000.
- Schuller, Wolfgang: See—
Zirps, Wilhelm; Schuller, Wolfgang; and Urban, Martin, 5,588,817, Cl. 417-549.000.
- Schumacher, Friedrich W.: See—
Schumacher, Gustav, II; and Schumacher, Friedrich W., 5,588,912, Cl. 460-101.000.
- Schumacher, Gustav, II; and Schumacher, Friedrich W. Sieve for harvesting machines. 5,588,912, Cl. 460-101.000.
- Schumacher, Gustav: See—
Donne, Mario Dalle; Schumacher, Gustav; Geiler, Volkmar; Clement, Marc; and Speit, Burkhard, 5,589,427, Cl. 501-33.000.
- Schuszt, Thomas: See—
Flemming, Eckardt; Tilch, Werner; Schuszt, Thomas; Ivanov, Marian; and Einrich, Paul, 5,589,650, Cl. 73-866.000.
- Schutt, Kerry D.: See—
Brandon, Norman E.; Hopson, David R.; Green, Ronald J.; Grimaud, James H. G., III; Heagle, Timothy J.; and Schutt, Kerry D., 5,590,391, Cl. 423-253.000.
- Schutz, Hans-Willy: See—
Herold, Manfred; Hartung, Georg; Schutz, Hans-Willy; and Jung, Ulrich, 5,588,365, Cl. 101-350.000.
- Schuur, Cornelis C. M., to U.S. Philips Corporation. Data terminal comprising a demodulator for a FSK phase-coherent modulated signal. 5,590,157, Cl. 375-327.000.
- Schwab, Michael; Walz, Gerd; and Merten, Gerhard, to Hoechst Aktiengesellschaft. Air-drying polyurethane resins, their preparation and use. 5,589,535, Cl. 524-591.000.
- Schwan, Fred W.; and Francis, William C., to Commercial Concepts, Inc. Baseball pitching apparatus. 5,588,645, Cl. 473-456.000.
- Schwarz, George W., Jr.: See—
Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clold R., III, 5,589,630, Cl. 73-23.350.
- Schwarz, Wolfgang: See—
Schleicher, Ulrich; Klobner, Martin; Schwarz, Wolfgang; and Feuerstake, Eugen, 5,589,662, Cl. 149-35.000.
- Schwenninger, Franz: See—
Zikeli, Stefan; Rauch, Ernst; Kobberger, Hermann; Ecker, Friedrich; Ruff, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, 5,589,125, Cl. 264-187.000.
- Schwler Manufacturing Company Inc.: See—
Breese, Dean E., 5,588,682, Cl. 285-52.000.
- SciMed Life Systems, Inc.: See—
Scovill, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772.000.
- Sciaroff, Stanley E.; and Pentland, Alex, to Massachusetts Institute of Technology. Finite element method for image alignment and morphing. 5,590,261, Cl. 395-173.000.
- Scott, Curtis E.; Kaliszewski, Mary Sue; and Levinson, Lionel M., to General Electric Company. Conversion of doped polycrystalline material to single crystal material. 5,588,992, Cl. 117-2.000.
- Scott, Gary L. Spine therapy and exercise device. 5,588,941, Cl. 482-131.000.
- Scott, Gregory H.; and Kejr, Melvin P., to Kejr Engineering, Inc. Connector for coupling a pair of rods. 5,588,771, Cl. 403-353.000.
- Scott, James F.: See—
Yandroski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., 5,589,845, Cl. 343-909.000.
- Scovill, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, to SciMed Life Systems, Inc. Shaft movement control apparatus and method. 5,588,442, Cl. 128-772.000.
- Scripps Research Institute, The: See—
Tamura, Richard N.; and Quaranta, Vito, 5,589,570, Cl. 530-350.000.
- SCS Promotion Company Limited: See—
Suzuki, Teruo, 5,588,236, Cl. 40-558.000.
- Scurati, Mario, to SGS-Thomson Microelectronics S.r.l. Interactive method for monitoring road traffic, and its onboard apparatus, and system for implementing the method. 5,589,827, Cl. 340-901.000.
- SDL, Inc.: See—
Venturo, Brian F.; and Berrang, Peter G., 5,589,684, Cl. 250-225.000.
- Seabrooks, Jeffrey A. Rolled sheet material having releasable anti-tack guide strip. 5,588,219, Cl. 33-733.000.
- Seagate Technology, Inc.: See—
Dunfield, John C.; and Heine, Gunter K., 5,590,003, Cl. 360-98.070.
- Lewis, Martyn A., 5,589,746, Cl. 318-439.000.
- Patrick, Paul R.; and Wong, Walter, 5,589,996, Cl. 360-73.030.
- Seagle, David J.: See—
Krounbi, Mohamed T.; Lee, Hin P. E.; and Seagle, David J., 5,588,199, Cl. 29-603.100.
- Sealed Air Corporation: See—
Farison, Brian K.; and Armstrong, William R., 5,588,533, Cl. 206-522.000.
- Seaman, Michael J.: See—
Bryant, Stewart F.; Seaman, Michael J.; and Szmidt, Christopher R., 5,590,366, Cl. 395-800.000.
- Krause, Jeffrey; Strohl, Niles E.; Seaman, Michael J.; Russell, Steven P.; and Hart, John H., 5,590,285, Cl. 395-200.200.
- Sears, William J., Jr. Methods of making doubly porous device. 5,589,176, Cl. 424-400.000.
- Sears, Courtland P., III: See—
Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clold R., III, 5,589,630, Cl. 73-23.350.
- Sears, Karl D.: See—
Sande, Walter E.; and Sears, Karl D., 5,589,030, Cl. 162-7.000.
- Sears, Michael: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
- Sechi, Salvatore: See—
Parmelee, David C.; and Sechi, Salvatore, 5,589,397, Cl. 436-89.000.
- Secure Technologies, Inc.: See—
Sallen, Roy; Budzyna, W. James; and Sawabini, Charles E., 5,589,821, Cl. 340-573.000.
- Seeger, Werner: See—
Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeier, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560.000.
- Segaud, Daniel: See—
Brassier, Marc; Gasquet, Jean-Claude; Segaud, Daniel; and Mauroy, Bernard, 5,589,730, Cl. 313-493.000.
- Seib, Ken L. Document printer having skew detection. 5,588,761, Cl. 400-579.000.
- Seidl, Lon D.; and Funk, David R., to Krueger International. System for mounting one or more items to the leg structure of a worktable. 5,588,376, Cl. 108-106.000.
- Seidman, Jonathan G.; and Jakobovits, Aya, to Cell Genesys Inc.; and President and Fellows of Harvard College. The Cells homozygous for disrupted target loci. 5,589,369, Cl. 435-172.300.
- Seiko Epson Corporation: See—
Amako, Jun; Miura, Hirotosuna; and Sonehara, Tomio, 5,589,955, Cl. 359-9.000.
- Deosaran, Trevor A.; Garg, Sanjiv; and Iadonato, Kevin R., 5,590,295, Cl. 395-393.000.
- Fujisawa, Teruhiko, 5,589,840, Cl. 343-718.000.
- Sakurada, Noriaki, 5,590,088, Cl. 365-233.000.
- Seiko Instruments, Inc.: See—
Minobe, Masao; Shiraga, Noboru; and Nakamura, Nobutaka, 5,588,746, Cl. 374-10.000.
- Saito, Yutaka; and Kojima, Yoshikazu, 5,589,705, Cl. 257-459.000.
- Seiler, William J.: See—
Kikinis, Dan; Dornier, Pascal; and Seiler, William J., 5,590,382, Cl. 395-893.000.
- Sekhar, Jainagesh A.; Liu, James J.; and Zhu, Naiping, to Microporetics Heaters International, Inc. Porous membranes and methods for making. 5,590,383, Cl. 419-2.000.
- Seki, Hiroshi: See—
Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.
- Seki, Shun-ichi: See—
Taguchi, Yutaka; Eda, Kazuo; Seki, Shun-ichi; and Onishi, Keiji, 5,589,806, Cl. 333-193.000.
- Sekiguchi, Kyoji: See—
Maeda, Yasuo; and Sekiguchi, Kyoji, 5,589,899, Cl. 351-245.000.
- Sekihara, Kensuke: See—
Kawai, Hiroyuki; Sekihara, Kensuke; and Migita, Shinichi, 5,590,164, Cl. 378-4.000.
- Sekine, Katsumi: See—
Ishibashi, Ryoichi; and Sekine, Katsumi, 5,590,132, Cl. 370-236.000.
- Sekine, Masayoshi: See—
Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34.000.

- Sellers, Charles A., to Compaq Computer Corporation. Collapsible notebook computer keyboard structure with resiliently deflectable key cap skirts. 5,590,020, Cl. 361-680,000.
- Semar, James E. Oil filter adapter system incorporating an accessible filter element. 5,589,059, Cl. 210-109,000.
- Semiconductor Energy Laboratory Co., Ltd.: See—
Takayama, Toru; and Takemura, Yasuhiko, 5,589,694, Cl. 257-67,000.
- Semiconductor Process Laboratory Co., Ltd.: See—
Maeda, Kazuo; Ohira, Kouichi; and Chino, Hiroshi, 5,589,001, Cl. 118-722,000.
- Senne Lizenz & Produkte GmbH: See—
Fromme, Heinrich, 5,588,165, Cl. 5-247,000.
- Seno, Shoichiro; and Ideguchi, Tetsuo, to Mitsubishi Denki Kabushiki Kaisha. Protocol parallel processing apparatus having a plurality of CPUs allocated to process hierarchical protocols. 5,590,328, Cl. 395-675,000.
- Seok, Yong-sik: See—
Lee, Jae-Hyeon; and Seok, Yong-sik, 5,590,079, Cl. 365-201,000.
- Sepracor Inc.: See—
Young, James W.; and Barberich, Timothy J., 5,589,511, Cl. 514-646,000.
- Serdar, Cuneyt M. Hydrolysis of cholinesterase inhibitors using parathion hydrolase. 5,589,386, Cl. 435-262,500.
- Sesterheim, Heinz: See—
Alber, Friedrich; Dedelmaier, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605,000.
- Setcom Corporation: See—
Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stoltenberg, Blaise G., 5,590,209, Cl. 381-168,000.
- Seward, D. Clint, to Electron Power Systems. Energy storage system. 5,589,727, Cl. 313-231,310.
- SF-Kooperation GmbH Beton-Konzepte: See—
Hagenah, Gerhard, 5,588,775, Cl. 404-45,000.
- SGS-Thomson Microelectronics, Inc.: See—
Blanchard, Richard A., 5,589,415, Cl. 437-57,000.
Brambilla, Massimiliano, 5,589,744, Cl. 318-254,000.
Iannuzzi, James M., 5,589,762, Cl. 323-351,000.
Kalnitsky, Alexander, 5,589,418, Cl. 437-193,000.
Kalnitsky, Alexander, 5,589,708, Cl. 257-646,000.
McClure, David C., 5,589,783, Cl. 326-71,000.
McClure, David C., 5,589,794, Cl. 327-538,000.
McClure, David C., 5,590,307, Cl. 395-458,000.
- SGS-Thomson Microelectronics S.A.: See—
Harrand, Michel; and Runtz, Michel, 5,590,070, Cl. 365-149,000.
Kassapien, Christian G., 5,589,793, Cl. 327-536,000.
Odinot, Charles, 5,589,787, Cl. 327-202,000.
- SGS-Thomson Microelectronics S.I.: See—
Baldi, Livio, 5,589,701, Cl. 257-369,000.
- SGS-Thomson Microelectronics S.I.: See—
Borgato, Pierandrea; Diazzi, Claudio; and Pidutti, Albino, 5,589,759, Cl. 323-222,000.
Contiero, Claudio; Galbiati, Paola; and Zullino, Lucia, 5,589,405, Cl. 437-6,000.
Mancuso, Massimo; Poluzzi, Rinaldo; and Rizzotto, Gianguido, 5,589,890, Cl. 348-678,000.
Mazzali, Stefano, 5,590,075, Cl. 365-185,220.
Scurati, Mario, 5,589,827, Cl. 340-901,000.
- Shaar, Casey S.: See—
Osgood, Edwin B.; and Shaar, Casey S., 5,589,933, Cl. 356-73,100.
- Shabanov, Vasily F.: See—
Pavlov, Vyacheslav F.; Shabanov, Vasily F.; Anshits, Alexandr G.; and Bayakin, Sergei G., 5,588,977, Cl. 65-17,400.
- Shafé, Mathew K., to International Business Machines Corporation. One-sided, single platter hard disk with center parking features. 5,590,006, Cl. 360-105,000.
- Shagott, David M.; Kruse, Gary E.; Harber, Blair L., Jr.; Sutherland, Daniel N.; and Travis, Terrell F., to Abatement Technologies, Inc. Methods of using a portable filtration unit. 5,588,985, Cl. 95-25,000.
- Shah, Siddharth R.: See—
Kolor, Daniel J.; Gupta, Nitin B.; and Shah, Siddharth R., 5,590,071, Cl. 365-149,000.
- Shahrodi, Ebrahim: See—
Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., 5,590,179, Cl. 379-107,000.
- Shan, Xuekang, to British Telecommunications public limited company. Mode-locked fibre ring laser stabilization. 5,590,142, Cl. 372-18,000.
- Shanbrom, Edward. Trace capture in biological fluids. 5,589,072, Cl. 210-638,000.
- Shandon, Inc.: See—
Hayes, William J., 5,589,400, Cl. 436-177,000.
- Shannon, Michael D.: See—
Ricco, Gary C.; Shannon, Michael D.; and Wilkins, Tyler R., 5,588,796, Cl. 414-741,000.
- Shannon, Paul J.: See—
Grasso, Robert P.; O'Brien, Michael K.; and Shannon, Paul J., 5,589,100, Cl. 252-299,010.
- Shapiro, Jeffrey R.: See—
Resk, Richard E.; Shapiro, Jeffrey R.; and Materdomini, Daniel, 5,588,834, Cl. 433-26,000.
- Sharangpani, Harshvardhan P., to Intel Corporation. Method and apparatus for generating a status word in a pipelined processor. 5,590,359, Cl. 395-800,000.
- Shariff, Ryan E.; Moseley, Gerald; Chen, Jack J.; Chang, Wen-Feng; and Abbas, Fazal, to Fujitsu Limited. Method and apparatus for employing a dummy read command to automatically assign a unique memory address to an interface card. 5,590,374, Cl. 395-829,000.
- Sharkey, Hugh R.: See—
Edwards, Stuart D.; Las, Ronald G.; and Sharkey, Hugh R., 5,588,960, Cl. 604-20,000.
- Sharma, Sanjay B.: See—
Famos, Maria D.; McWilliams, John P.; Sharma, Sanjay B.; and Shihabi, David S., 5,589,147, Cl. 423-239,200.
- Sharma, Satish C.: See—
Hargis, I. Glen; Kovalchin, John P.; Sharma, Satish C.; Weinert, Raymond J.; and Wilson, John A., 5,589,532, Cl. 524-432,000.
- Sharp Kabushiki Kaisha: See—
Hanaoka, Toshiharu, 5,590,249, Cl. 395-122,000.
May, Paul, 5,589,968, Cl. 359-124,000.
Miyata, Masao; and Matsumoto, Kenji, 5,589,949, Cl. 358-451,000.
Okabayashi, Katsushi; Ogura, Takashi; and Yoshida, Masaru, 5,589,732, Cl. 313-506,000.
Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsuura, Yasuhiro, 5,590,355, Cl. 395-800,000.
Shigeta, Mitsuhiro; and Nonomura, Keisaku, 5,589,961, Cl. 349-41,000.
Yamada, Kazuo; Mitate, Takehito; Yoneda, Tetsuya; and Nishimura, Naoto, 5,589,299, Cl. 429-218,000.
Yoshida, Toshio; and Akai, Toshio, 5,588,531, Cl. 206-454,000.
- Sharpe, Norton, to Franklin Brass Manufacturing Company. Paper roller. 5,588,627, Cl. 242-599,000.
- Sharpe-Geisler, Bradley A., to Advanced Micro Devices, Inc. Macrocell and clock signal allocation circuit for a programmable logic device (PLD) enabling PLD resources to provide multiple functions. 5,589,782, Cl. 326-38,000.
- Shaw, James D.: See—
Graham, Gary A.; Jacobs, Merrit N.; Marvin, Russel H.; Shaw, James D.; and VanBrunt, Nicholas, 5,588,946, Cl. 494-11,000.
- Shay, Francis J.: See—
Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., 5,588,182, Cl. 16-268,000.
- Shea, Raymond E., Sr. Self-lighted safety helmet. 5,588,736, Cl. 362-106,000.
- Sheffield, David W.: See—
Reynolds, Robert A.; and Sheffield, David W., 5,590,313, Cl. 395-500,000.
- Sheldon, Peter, to Midwest Research Institute. System for monitoring the growth of crystalline films on stationary substrates. 5,588,995, Cl. 117-201,000.
- Shell Oil Company: See—
Himes, Glenn R., 5,589,542, Cl. 525-98,000.
Smolinski, Susan L.; Morrison, Denby G.; Marshall, Peter W.; and Huete, David A., 5,588,781, Cl. 405-195,100.
- Shen, Chi-Cheong: See—
Levine, Jules D.; Shen, Chi-Cheong; and Taylor, Robert, 5,589,728, Cl. 313-336,000.
- Shen, Yong-Qiang: See—
Wong, Bing L.; Shen, Yong-Qiang; and Chen, Yung-Pin, 5,589,354, Cl. 435-47,000.
- Shenoy, Sunil: See—
Heeh, Jay; Shenoy, Sunil; and Wong, Jimmy, 5,590,368, Cl. 395-800,000.
- Shenvi, Ashokkumar B.; Jacobs, Robert T.; Miller, Scott C.; Ohnmacht, Cyrus J., Jr.; and Veale, Chris A., to Zeneca Limited. Cyclic amide derivatives for treating asthma. 5,589,489, Cl. 514-323,000.
- Shepard, Howard: See—
Dvorkis, Paul; and Shepard, Howard, 5,589,679, Cl. 235-472,000.
- Shepard, Howard M.: See—
Swartz, Jerome; Shepard, Howard M.; Krichever, Mark J.; Metlitsky, Boris; and Barkan, Edward, 5,589,680, Cl. 235-472,000.
- Sherfield, Charles O. Hydroponic cultivation apparatus and method. 5,588,256, Cl. 47-62,000.
- Sherman, William D.: See—
Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sherman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4,100.
- Sherwin-Williams Company, The: See—
Valpey, Richard S., III; Yokoyama, Thomas W.; Kraan, John D.; and Harwood, H. James, 5,589,560, Cl. 526-271,000.
- Sherwood, Diana L., to Corning Incorporated. Method for making fiber-reinforced ceramic matrix composite. 5,589,115, Cl. 264-60,000.
- Sheshin, E. P.: See—
Kaftanov, V. S.; Suvorov, A. L.; and Sheshin, E. P., 5,588,893, Cl. 445-6,000.
- Sheu, Shing-Ren: See—
Yang, Sheng-Hsing; and Sheu, Shing-Ren, 5,589,411, Cl. 437-41,000.
- Shewmake, Steven A.: See—
Law, Ronald L.; Roy, Apurba; and Shewmake, Steven A., 5,588,848, Cl. 439-83,000.
- Shi, Jie: See—
Fauteux, Denis G.; Massucco, Arthur A.; Wilkins, Ronnie D.; and Shi, Jie, 5,588,971, Cl. 29-623,500.

- Shi, Juan: See—
Weiner, Ronald M.; Shi, Juan; and Coyne, Vernon E., 5,589,373, Cl. 435-220,000.
- Shibahara, Masanori: See—
Shibuya, Giichi; Shibahara, Masanori; Takayama, Suguru; and Utsunomiya, Hajime, 5,590,099, Cl. 369-13,000.
- Shibata, Alan, to Hewlett-Packard Company. Cleaner cartridge for an inkjet printing mechanism. 5,589,861, Cl. 347-22,000.
- Shibata, Fumio: See—
Isobe, Yoshio; Ito, Toshio; and Shibata, Fumio, 5,589,186, Cl. 424-438,000.
- Shibata, Hideyo; Kinoshita, Ritsuro; Yoshida, Takayasu; and Eshima, Shigeo, to Matsushita Electric Industrial Co., Ltd. Magnetic recording and reproducing apparatus for performing slow-motion reproduction with higher quality of image. 5,589,992, Cl. 386-72,000.
- Shihata, Hironori, to Olympus Optical Co., Ltd. Zoom lens. 5,589,986, Cl. 359-684,000.
- Shibata, Kouichi; and Motooka, Shigenori, to Mita Industrial Co., Ltd. Memory designation control device. 5,590,303, Cl. 395-427,000.
- Shibata, O.: See—
Kinoshita, Masafumi; Niwa, Toshio; and Shibata, O., 5,589,541, Cl. 525-66,000.
- Shibata, Toshiyuki: See—
Nakanishi, Shigeo; Tominaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki, 5,589,491, Cl. 514-338,000.
- Shibayama, Hiroaki: See—
Ide, Motoki; and Shibayama, Hiroaki, 5,590,401, Cl. 455-38,300.
- Shibuya, Giichi; Shibahara, Masanori; Takayama, Suguru; and Utsunomiya, Hajime, to TDK Corporation. Magneto-optical recording method and method for making information-carrying magneto-optical recording medium. 5,590,099, Cl. 369-13,000.
- Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsuura, Yasuhiro, to Sharp Kabushiki Kaisha. Data driven processor, a data driven information processing device, and a method of verifying path connections of a plurality of data driven processors in such a data driven information processing device. 5,590,355, Cl. 395-800,000.
- Shiffert, Mark B.; and Bivens, Donald B., to Du Pont de Nemours, E. I., and Company. Compositions of difluoromethane and tetrafluoroethane. 5,589,098, Cl. 252-67,000.
- Shigematsu, Kazuo: See—
Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116,000.
- Shigeta, Mitsuhiro; and Nonomura, Keisaku, to Sharp Kabushiki Kaisha. Optical wave guide driven liquid crystal display employing optical switching for input. 5,589,961, Cl. 349-41,000.
- Shih, Andy; Bockman, Jeffrey M.; and George, Shaji T., to Innovir Laboratories, Inc. Ribozyme amplified diagnostics. 5,589,332, Cl. 435-6,000.
- Shih, Wayne K.; and Light, Ronald R., to Eastman Chemical Company. Plasticized polyester for shrink film applications. 5,589,126, Cl. 264-211,000.
- Shih, Yifong, to International Business Machines Corporation. Method and apparatus for reducing false invalidations in distributed systems. 5,590,308, Cl. 395-463,000.
- Shihabi, David S.: See—
Famos, Maria D.; McWilliams, John P.; Sharma, Sanjay B.; and Shihabi, David S., 5,589,147, Cl. 423-239,200.
- Shihua, Dong. Syntheses of new types of chelating resins and their adsorption properties for noble metals. 5,589,540, Cl. 525-65,000.
- Shikata, Kiyotaka: See—
Yoneda, Norihiro; Ohba, Toshimitsu; Furuya, Reiko; and Shikata, Kiyotaka, 5,590,183, Cl. 379-142,000.
- Shim, Sang-Hea; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo; and Lu, Frank F., to Nalco Chemical Company. Carbon steel corrosion inhibitors. 5,589,106, Cl. 252-387,000.
- Shima Seiki Manufacturing Ltd.: See—
Kiribuchi, Takeshi, 5,588,311, Cl. 66-60,000.
- Shimada, Toshio: See—
Ito, Katsuhiko; Kobayashi, Hideo; Ishiuchi, Yukio; and Shimada, Toshio, 5,588,406, Cl. 123-90,340.
- Shimadzu Corporation: See—
Hiraishi, Masahiro; and Kuroda, Shin-ichi, 5,588,292, Cl. 60-300,000.
- Shimamune, Takayuki; Nakamatsu, Shuji; Sawamoto, Isao; and Nishiki, Yoshinori, to Permelec Electrode Ltd. Method for electrolyzing water. 5,589,052, Cl. 205-349,000.
- Shimazaki, Katsusuke: See—
Kashiwakura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Isu; Oota, Norio; and Sugiyama, Hisenori, 5,590,097, Cl. 369-13,000.
- Shimizu, Hirokimi, to Canon Kabushiki Kaisha. Electronic equipment having a display device. 5,589,848, Cl. 345-102,000.
- Shimizu, Hitoshi, to Asahi Kogyo Kabushiki Kaisha. Aperture device for a camera. 5,589,906, Cl. 396-505,000.
- Shimizu, Kazuharu: See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu, 5,589,055, Cl. 205-768,000.
- Shimizu, Nobuaki: See—
Egawa, Tatsuya; Kawaguchi, Yasuhiro; Mogami, Kenji; and Shimizu, Nobuaki, 5,589,597, Cl. 568-608,000.
- Shimizu, Osamu: See—
Ushitora, Akihiro; and Shimizu, Osamu, 5,588,458, Cl. 137-205,000.
- Shimizu, Shigeru; Saitoh, Takashi; Uzawa, Masashi; and Takayanagi, Yasuyuki, to Nito Chemical Industry Co., Ltd. Soluble alkoxy-group substituted aminobenzenesulfonic acid aniline conducting polymers. 5,589,108, Cl. 252-500,000.
- Shimizu, Tamio, to NEC Corporation. Semiconductor memory device. 5,590,081, Cl. 365-203,000.
- Shimizu, Yasushi: See—
Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114,000.
- Shimizume, Kazutoshi; and Akita, Mamoru, to Sony Corporation. Disc player having a plurality of reading means for reading information on a disc. 5,590,106, Cl. 369-50,000.
- Shimo, Norio, to Sony Corporation. Variable power circuit and apparatus using the power circuit. 5,590,419, Cl. 455-127,000.
- Shimoda, Isamu, to Canon Kabushiki Kaisha. Information processing apparatus. 5,588,839, Cl. 434-114,000.
- Shimoda, Yuji: See—
Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161,000.
- Shimokoriyama, Makoto; Aoki, Akio; and Kato, Masato, to Canon Kabushiki Kaisha. Video signal reproduction apparatus replacing drop-cut signal portions. 5,589,946, Cl. 386-47,000.
- Shimomura, Takehiko; and Miyake, Takashi, to Mitsubishi Denki Kabushiki Kaisha. Output control circuit. 5,590,035, Cl. 364-177,000.
- Shimony, Ilan: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Shimoyoshi, Osamu: See—
Mitsuno, Makoto; Akagiri, Kenzo; Suzuki, Hiroshi; and Shimoyoshi, Osamu, 5,590,108, Cl. 369-59,000.
- Shin-Etsu Handotai Co., Ltd.: See—
Tominaga, Hiroyoshi; and Suzuki, Yoshinori, 5,588,902, Cl. 451-288,000.
- Shin, Young-ho: See—
An, Hyeon-keon; Shin, Young-ho; and Kim, Suk-ki, 5,590,206, Cl. 381-71,000.
- Shincovich, John T.; Michalek, Jan K.; Baldwin, Norman C.; Shahrodi, Ebrahim; Robinson, Darrell; Pruehs, Allen V.; and Learmont, Robert O., to Ekstrom Industries, Inc. Remote automatic meter reading apparatus. 5,590,179, Cl. 379-107,000.
- Shindo, Yoichi: See—
Kitamura, Shoji; Shindo, Yoichi; and Amano, Akira, 5,590,144, Cl. 372-36,000.
- Shinkai, Yasuhiro: See—
Saito, Kenji; and Shinkai, Yasuhiro, 5,589,879, Cl. 348-223,000.
- Shinoda, Atsunao: See—
Ishikawa, Hideo; and Shinoda, Atsunao, 5,590,407, Cl. 455-66,000.
- Shinoki, Takashi: See—
Inagaki, Jiro; Shinoki, Takashi; and Hara, Atsushi, 5,589,121, Cl. 264-132,000.
- Shintaku, Takashi: See—
Uno, Mikio; Shintaku, Takashi; and Takehara, Takatsugu, 5,589,310, Cl. 430-106,000.
- Shinzaki, Akihiro; Watanabe, Miwa; and Suzuki, Tadao, to Unitika Ltd. Method for enzymatic analysis and reagent therefor. 5,589,349, Cl. 435-26,000.
- Shiokawa, Junji: See—
Saito, Seiichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shiokawa, Junji; and Kawamae, Osamu, 5,589,995, Cl. 360-48,000.
- Shiomi, Yasuhiko, to Canon Kabushiki Kaisha. Camera with image stabilizing device. 5,589,912, Cl. 396-55,000.
- Shipko, Fredrick J.: See—
Narayanan, Krishna; Padmanabhan, Vasant; Shipko, Fredrick J.; Goode, Louis; and Feamot, Neal E., 5,588,436, Cl. 128-662,030.
- Shiple Company, L.L.C.: See—
Zampini, Anthony; and Trefonas, Peter, III, 5,589,553, Cl. 525-504,000.
- Shiraga, Kazutaka: See—
Kakiuchi, Daisuke; Ogawa, Yasumichi; Yasumatsu, Hifumi; and Shiraga, Kazutaka, 5,588,469, Cl. 138-137,000.
- Shiraga, Noboru: See—
Minobe, Masao; Shiraga, Noboru; and Nakamura, Nobutaka, 5,588,746, Cl. 374-10,000.
- Shirai, Susumu: See—
Hosoi, Norihisa; Shirai, Susumu; Hibi, Kenichiro; Okui, Yoshihiro; Katoh, Takehiro; and Azuma, Yoshihiko, 5,589,934, Cl. 356-218,000.
- Shirai, Takeshi; and Yagi, Wataru, to Fujitsu Limited. Ultrasonic diagnostic apparatus. 5,588,433, Cl. 128-660,050.
- Shiraishi, Akihiko; Fujibayashi, Kazuo; and Kuwabara, Tetsuo, to Canon Kabushiki Kaisha. Integral infrared absorbing optical low-pass filter. 5,589,882, Cl. 348-340,000.
- Shiraishi, Shuji: See—
Nishihara, Takashi; Ikeda, Toru; Yano, Osamu; and Shiraishi, Shuji, 5,589,815, Cl. 340-444,000.
- Shirakawa, Shingo: See—

Watahiki, Satoshi; and Shirakawa, Shingo, 5,590,018, Cl. 361-612.000.
 Shiraki, Masao; Suzuki, Fujio; and Yoshida, Kazunori, to Kabushiki Kaisha Toyota Jidoshokki Seisakusho; and Kabushiki Kaisha Toyota Chuo Kenkyusho. Weft inserting device for an air jet loom having reed pieces with recessed weft guide openings. 5,588,470, Cl. 139-435.500.
 Shirasaki, Miwa: See—
 Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshitaka, 5,589,517, Cl. 521-33.000.
 Shirk, Michael E.: See—
 Davis, Wayne S.; Shirk, Michael E.; and Whiteman, Robert N., Jr., 5,588,877, Cl. 439-660.000.
 Shirodkar, Pradeep P.: See—
 Bladt, John P.; and Shirodkar, Pradeep P., 5,589,551, Cl. 525-333.800.
 Shirole, Mandakini V.: See—
 Naik, Ramachandra G.; Mumhaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shirole, Mandakini V.; Lal, Banshi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.
 Shiseido Co., Ltd.: See—
 Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, 5,589,165, Cl. 424-78.030.
 Shockley, Ty R.; Maris, Leo; Henderson, Lee W.; Moran, John; and Nakayama, Masaaki, to Baxter International, Inc. Low sodium peritoneal dialysis solution. 5,589,197, Cl. 424-663.000.
 Short, Jay M., to Stratagene. Nucleic acid construct encoding a nuclear transport peptide operatively linked to an inducible promoter. 5,589,392, Cl. 435-320.100.
 Short, Jay M.: See—
 Sorce, Joseph A.; and Short, Jay M., 5,589,155, Cl. 424-9.200.
 Shost, Mark A.: See—
 Licht, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydelis, Ronald A.; and Fox, Michael J., 5,588,404, Cl. 123-90.170.
 Shou, Ming-Hwa: See—
 Duhamel, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, 5,588,257, Cl. 49-199.000.
 Showa Denko K.K.: See—
 Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, 5,589,270, Cl. 428-411.100.
 Watanabe, Kazuyuki; and Iwamoto, Satoshi, 5,589,547, Cl. 525-240.000.
 Showalter, Jerry M., to Tampa G Manufacturing Co. Double back golf cart enclosure. 5,588,690, Cl. 296-77.100.
 Shriki, Moshe M.: See—
 Sandorfi, Miklos A.; and Shriki, Moshe M., 5,590,122, Cl. 370-394.000.
 Shroka, Edward T.: See—
 Rodriguez, Roberto; and Shroka, Edward T., 5,588,267, Cl. 52-219.000.
 Shu, Thomas: See—
 Sangveraphunsiri, Vic; Pinai, Felix; Shu, Thomas; and Spears, Cameron, 5,590,375, Cl. 395-841.000.
 Shuber, Anthony P., to Genzyme Corporation. High-throughput screening method for sequence or genetic alterations in nucleic acids using elution and sequencing of complementary oligonucleotides. 5,589,330, Cl. 435-5.000.
 Shulman, Steve: See—
 Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
 Shur-Line, Inc.: See—
 Hoeltke, Larry; and Fischer, Roger, 5,588,221, Cl. 34-58.000.
 SI Diamond Technology, Inc.: See—
 Hammond, Mark S.; and Evans, Joseph D., 5,588,975, Cl. 51-293.000.
 Sides, James R.; Martin, James D.; and Scheffee, Robert S., to Atlantic Research Corporation. Use of mixed gases in hybrid air bag inflators. 5,589,141, Cl. 422-164.000.
 Sidikman, Paul: See—
 Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173.000.
 Siegmund, Rainer: See—
 Striter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegmund, Rainer, 5,588,326, Cl. 74-50.000.
 Siemens Aktiengesellschaft: See—
 Alber, Friedrich; Dedelmahr, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605.000.
 Barthel, Herbert; Daar, Horst; and Schuetz, Hartmut, 5,590,278, Cl. 395-185.060.
 Jax, Peter; and Ruthhof, Klaus, 5,589,647, Cl. 73-863.230.
 Lehmann, Volker; Marin, Heiner; and Reiber, Ingolf, 5,589,673, Cl. 218-66.000.
 Trimborn, Peter; and Muegle, Kurt-Willy, 5,588,806, Cl. 417-68.000.
 Siemens Electric Limited: See—
 Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hirotomi; and Yamamoto, Yoshio, 5,588,414, Cl. 123-571.000.
 Siemens Energy & Automation, Inc.: See—
 Dollar, Charles R., II, 5,590,012, Cl. 361-113.000.
 Siemens Medical Systems, Inc.: See—
 Weng, Lee; and Gueck, Wayne, 5,588,435, Cl. 128-660.070.

Siemens Rolm Communications Inc.: See—
 Berger, H. Stephen; Vela de Casillas, Martha L.; and Cochrane, Harry L., 5,589,773, Cl. 324-261.000.
 Sienel, Günter; Dorn, Maximilian; and Zimmermann, Heinz, to Peroxid-Chemie GmbH. Master batch compositions containing organic peroxides. 5,589,526, Cl. 523-351.000.
 Sievert, Dick J.: See—
 Woolford, Michael E.; and Sievert, Dick J., 5,589,124, Cl. 264-157.000.
 Siewert, Thomas A.; Dubé, William P.; and Fitting, Dale W., to National Institute of Standards and Technology. Apparatus and method for monitoring casting process. 5,589,690, Cl. 250-390.060.
 Sifa Sitzfabrik GmbH: See—
 Neumueller, Maria; and Gebhard, Angelika, 5,588,706, Cl. 297-374.000.
 Sigelmann, Milton R.: See—
 Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112-80.160.
 Sigler, Gerald F.: See—
 Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wilsey, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.
 Signa Scan, Inc.: See—
 Campbell, Robert K., 5,588,765, Cl. 401-216.000.
 Silbernagel, Peter J.: See—
 Wallace, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heiti, Robert V.; and Yoshida, Yuko, 5,589,247, Cl. 428-141.000.
 Silicon Graphics, Inc.: See—
 Mirapuri, Sunil; and Riordan, Thomas J., 5,590,294, Cl. 395-591.000.
 Silicon Video Corporation: See—
 Fahlen, Theodore S.; Duboc, Robert M., Jr.; and Lovoi, Paul A., 5,589,731, Cl. 313-495.000.
 Silverbrook, Kia, to Canon Kabushiki Kaisha; and Canon Information Systems Research Australia Pty Ltd. Video processor system and audio processor system. 5,590,252, Cl. 395-133.000.
 Silvis, William E.: See—
 Kelley, Harold E.; Silvis, William E.; and Terry, Charles J., 5,589,268, Cl. 428-408.000.
 Sim, Hwan-Oh, to Hyundai Motor Company, Ltd. Air conditioning system for a vehicle. 5,588,305, Cl. 62-419.000.
 Simeone, Giovanni; Mutta, Fabrizio; Locaspi, Angelo; and Tonelli, Claudio, to Ausimont, S.p.A. Coatings based on polyesters from perfluoropolyethers. 5,589,552, Cl. 525-440.000.
 Simmen, David E.: See—
 Leung, Ting Y.; Pirahesh, Mir H.; Jou, Michelle M.; and Simmen, David E., 5,590,324, Cl. 395-605.000.
 Simmonds Precision Engine Systems, Inc.: See—
 DeFreitas, Dennis M., 5,588,299, Cl. 60-740.000.
 Simonich, Christopher E.: See—
 Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., 5,590,292, Cl. 395-825.000.
 Simpson, Matthew, to Norton Company. Method of making a wear component by plasma jet CVD. 5,589,242, Cl. 427-577.000.
 Sims, John E.: See—
 Smith, Craig A.; Larsen, Alf D.; Sims, John E.; and Curtis, Benson M., 5,589,456, Cl. 514-12.000.
 Sinclair, Stephen H.; Nissanov, Jonathan; and Gupta, Anitabha, to Sinclair, Stephen H. Method and apparatus for central visual field mapping and optimization of image presentation based upon mapped parameters. 5,589,897, Cl. 351-223.000.
 Singleton, Michael W.: See—
 Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704.000.
 Sinram, Bryan W.: See—
 Becker, John C.; Cameron, John D., Jr.; Cameron, William L.; and Sinram, Bryan W., 5,588,598, Cl. 241-19.000.
 Sipe, Lynn R., to Whitaker Corporation. The. Variable orientation, surface mounted connector. 5,588,844, Cl. 439-65.000.
 Siska, Steven M.: See—
 Foreman, Kevin G.; Miller, Paul J.; and Siska, Steven M., 5,590,058, Cl. 364-551.010.
 Sisley, Elizabeth M.: See—
 Kruse, John M.; Collins, John E.; and Sisley, Elizabeth M., 5,590,269, Cl. 395-209.000.
 Sivakumar, Ananthasubramanian; Collins, John H.; and Ramesh, Manian, to Nalco Chemical Company. Use of silicon containing polyelectrolytes in wastewater treatment. 5,589,075, Cl. 210-727.000.
 Sivin, B. Jerry. Adjustable kitchen appliance garage. 5,588,723, Cl. 312-205.000.
 Sixsmith, Thomas G., to Sixsmith, Thomas G. Water recovery wash brush. 5,588,176, Cl. 15-322.000.
 Sjödin, Lars T.: See—
 Färnstrand, Per-Åke; Sjödin, Lars T.; Lindström, Lars-Åke; and Nordén, K. Solveig E., 5,589,031, Cl. 162-65.000.
 Sjöholm, Paul F.: See—
 Babbitt, W. Randall; Bell, John A.; Capron, Barbara A.; deGroot, Peter J.; Hagman, Ronald L.; McGarvey, John A.; Sberman, William D.; and Sjöholm, Paul F., 5,589,928, Cl. 356-4.100.

Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., to Tandem Computers Incorporated. Multi-volume audit trails for fault tolerant computers. 5,590,274, Cl. 395-182.050.
 Skov, Richard T.; and Pennace, John R., to FLEXcon Company, Inc. Tamper resistant labeling. 5,588,679, Cl. 283-67.000.
 Slater, Martin J.: See—
 Nicol, Robin H.; Slater, Martin J.; and Hodgson, Simon T., 5,589,474, Cl. 514-211.000.
 Slides Corporation: See—
 Ozeki, Jiro, 5,588,528, Cl. 206-308.100.
 Sloma, Alan; Rufo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice, to OmniGene, Inc. Protease deletion. 5,589,383, Cl. 435-252.310.
 Slupskiy, Leontiy. Volleyball training device. 5,588,655, Cl. 473-429.000.
 Smallwood, Paul A.: See—
 Eckman, Michael G.; and Smallwood, Paul A., 5,588,918, Cl. 473-187.000.
 Smart Storage, Inc.: See—
 Masey, David, 5,590,320, Cl. 395-619.000.
 Smayling, Michael C.; and Talamonti, Luciano, to Texas Instruments Incorporated. Charge pump circuit with capacitors. 5,589,697, Cl. 257-204.000.
 Smith & Nephew Richards, Inc.: See—
 Davidson, James A., 5,588,443, Cl. 128-772.000.
 Smith, Bradley W.: See—
 Clark, Randall J.; Smith, Bradley W.; Rasmussen, Kirk H.; and Kort, Leland B., 5,588,676, Cl. 280-741.000.
 Smith, Clold R., III: See—
 Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clold R., III, 5,589,630, Cl. 73-23.350.
 Smith, Craig A.; Larsen, Alf D.; Sims, John E.; and Curtis, Benson M., to Immunex Corporation. Granulocyte-colony stimulating factor receptors. 5,589,456, Cl. 514-12.000.
 Smith, Curtis M.: See—
 Cortjens, Leo M.; Franklin, Kenneth A.; Mays, Richard C.; and Smith, Curtis M., 5,589,878, Cl. 348-211.000.
 Smith, Daniel J.; and Bhat, Shailesh, to University of Akron. The. Method and apparatus for non-invasive volume and texture analysis. 5,588,428, Cl. 128-653.100.
 Smith, Fraser: See—
 Jacobsen, Stephen C.; Potter, Dwight; and Smith, Fraser, 5,588,688, Cl. 294-106.000.
 Smith, Graham J.: See—
 McTaggart, Fergus; Pemberton, Denis; and Smith, Graham J., 5,589,166, Cl. 424-78.350.
 Smith International, Inc.: See—
 Denton, Robert M.; and Fang, Zhigang, 5,589,443, Cl. 508-150.000.
 Smith, John, Jr. Anti-theft vehicle security system. 5,589,814, Cl. 340-426.000.
 Smith, Johnny N., to Dana Corporation. Seal and seal guard assembly for universal joint. 5,588,915, Cl. 464-14.000.
 Smith, Keith E.: See—
 Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.
 Smith, Malcolm D., to Fisher & Paykel Limited. Humidifier chamber. 5,588,423, Cl. 128-203.260.
 Smith, Michael G., to AST Research, Inc. Automatic control of distributed DMAs in a PCI bus system supporting dual ISA buses. 5,590,377, Cl. 395-842.000.
 Smith, Nathan R., to Advantek, Inc. IC tray handling apparatus and method. 5,588,797, Cl. 414-797.500.
 Smith, Richard H.: See—
 Kanan, Paul G.; Smith, Richard H.; and Rudnick, Ellen, 5,589,346, Cl. 435-7.920.
 Smith, Robert S.; and McMahon, Steven L. Method of preparing isomerization catalyst. 5,589,602, Cl. 585-671.000.
 Smith, Russell C.: See—
 Hernandez, Gilberto; Smith, Russell C.; and Bouvier, Daniel, 5,590,023, Cl. 361-683.000.
 Smithers-Oasis Company: See—
 Boodley, James W.; Noe, James P.; and Hann, Daniel, 5,588,253, Cl. 47-41.120.
 SmithKline Beecham PLC: See—
 Haigh, David, 5,589,492, Cl. 514-339.000.
 Smolinski, Susan L.; Morrison, Denby G.; Marshall, Peter W.; and Huete, David A., to Shell Oil Company. Lightweight, wide-bodied compliant tower. 5,588,781, Cl. 405-195.100.
 Smoral, Vincent J.: See—
 Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
 Smrcka, Joseph G.: See—
 Viano, David C.; Jedrzeczak, Edward A.; and Smrcka, Joseph G., 5,589,651, Cl. 73-866.400.
 Snap-on Technologies, Inc.: See—

Becker, Thomas P.; Crass, Matthew M.; Putney, Gordon A.; Niesen, Randy J.; and Iwinski, Dean J., 5,589,644, Cl. 73-862.230.
 Sne La Calhene: See—
 Glachet, Charles, 5,588,473, Cl. 141-387.000.
 Snell, John-Erik, to ASEA Brown Boveri AB. Method for controlling the movement of an industrial robot at and near singularities. 5,590,034, Cl. 364-167.010.
 Snell, William M., to Chrysler Corporation. Steering column mechanical brake interlock system. 5,588,514, Cl. 192-4.00A.
 Snorrason, Emir. Benzodiazepine treatment. 5,589,475, Cl. 514-215.000.
 Snyder, Brian A.: See—
 Contestable, Paul B.; and Snyder, Brian A., 5,589,344, Cl. 435-7.900.
 Snyder, Ralph E.; Sorace, Dominic A.; and Benford, James G., to Allegheny Ludlum Corporation. Segmented scribing roller for refining the domain structure of electrical steels by local mechanical deformation. 5,588,321, Cl. 72-366.200.
 So, Henry. Key switch unit for computer keyboards. 5,588,760, Cl. 400-495.000.
 Sobhani, Mohi, to Hughes Aircraft Company. Rotary electrical connector. 5,588,843, Cl. 439-22.000.
 Societe Anonyme dite: Aerospaciale Societe Nationale Industrielle: See—
 Chevalier, Alain; and Protat, Vincent, 5,589,632, Cl. 73-117.400.
 Societe d'Applications Generales d'Electricite et de Mecanique Sagem: See—
 Merlin, Bruno; and Quintana, Jean, 5,589,681, Cl. 235-482.000.
 Societe Nouvelle des Ateliers et Chantiers du Harve: See—
 Tessandier, Alain, 5,588,391, Cl. 114-284.000.
 Sokol, Gerald E.; Lee, Howard H.; and Kibbel, Bradley W., to General Motors Corporation. Method of making metal matrix composite. 5,588,477, Cl. 164-34.000.
 Solbeck, Peter, to Polysheet A/S. Anchoring eyelet for tarpaulins and similar coverings. 5,588,191, Cl. 24-713.600.
 Solcas Polymer, Limited Partnership: See—
 Merz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, 5,589,520, Cl. 521-64.000.
 Soleimani, Mohammad; Corrigan, John E., III; Bukhari, Mohammad; and Roos, David A., to Hughes Electronics. Apparatus for positioning an antenna in a remote ground terminal. 5,589,837, Cl. 342-359.000.
 Solipat AG: See—
 Strahm, Christian, 5,588,170, Cl. 8-149.100.
 Solomon, Peter R., to Advanced Fuel Research, Inc. Dynamic support structure. 5,588,632, Cl. 248-560.000.
 Solv-Ex Corporation: See—
 Rendall, John S.; and Ahghar, Massoud, 5,589,023, Cl. 156-245.000.
 Somero, Bradley M.: See—
 White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hui, 5,589,423, Cl. 437-228.000.
 Sommerer, Klaus: See—
 Breitler, Hans P.; Sommerer, Klaus; and Roulin, Monique, 5,589,275, Cl. 428-458.000.
 Sommermeyer, Klaus: See—
 Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeyer, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560.000.
 Son, Tae W.: See—
 Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., 5,589,264, Cl. 428-359.000.
 Sonehara, Tomio: See—
 Amako, Jun; Miura, Hirotosuna; and Sonehara, Tomio, 5,589,955, Cl. 359-9.000.
 Song, Byung-Jun. Laser cutting apparatus with means for measuring cutting groove width. 5,589,090, Cl. 219-121.620.
 Song, Junfu: See—
 Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76.000.
 Sonident Anstalt Liechtensteinischen Rechts: See—
 Bicz, Wieslaw, 5,589,636, Cl. 73-617.000.
 Sonntag, Dietmar: See—
 Gebert, Hans; Möhle, Rolf; Sonntag, Dietmar; Bruss, Elke; Guntert, Dietwart; and Müller, Hubert, 5,589,060, Cl. 210-130.000.
 Sonsub, Inc.: See—
 Bath, William R.; and Yemington, Charles R., 5,588,230, Cl. 37-190.000.
 Sony Corporation: See—
 Arakawa, Hideki; and Nariyuki, Takashi, 5,590,073, Cl. 365-185.080.
 Ata, Masafumi; Machida, Masataka; and Watanabe, Haruo, 5,589,038, Cl. 204-157.420.
 Chatani, Masayuki, 5,590,107, Cl. 369-54.000.
 Ezaki, Tadashi, 5,589,886, Cl. 348-461.000.
 Fujiki, Mikio, 5,589,853, Cl. 345-150.000.
 Hsu, Jon S., 5,589,039, Cl. 204-192.120.
 Inanaga, Kiyofumi; and Yamada, Yuji, 5,590,094, Cl. 369-4.000.
 Ishida, Takehisa, 5,590,009, Cl. 360-135.000.
 Ito, Kengo; Isaji, Kaori; Fujiwara, Yoshio; Isogai, Mitsuhiro; and Hida, Masanobu, 5,589,435, Cl. 503-227.000.
 Iwasaki, Yoh; Murakami, Yosuke; and Itabashi, Masao, 5,589,283, Cl. 428-694.00R.
 Kikuchi, Shuichi; and Higuchi, Shintaro, 5,588,606, Cl. 242-347.000.
 Kojima, Yuichi, 5,590,222, Cl. 382-268.000.
 Lantsman, Alexander D., 5,589,041, Cl. 204-192.330.

- Mitsuno, Makoto; Akagiri, Kenzo; Suzuki, Hiroshi; and Shimoyoshi, Osamu, 5,590,108, Cl. 369-59,000.
- Noda, Hidenobu, 5,590,103, Cl. 369-44,290.
- Ochiai, Akihiko, 5,589,419, Cl. 437-795,000.
- Ohki, Mitsuhiro, 5,590,066, Cl. 364-725,000.
- Ota, Takaaki, 5,589,841, Cl. 343-760,000.
- Sasaki, Yuu; Iwasawa, Junichi; and Yamada, Masahiro, 5,588,732, Cl. 362-10,000.
- Shimizu, Kazutoshi; and Akita, Mamoru, 5,590,106, Cl. 369-50,000.
- Shimo, Norio, 5,590,419, Cl. 455-127,000.
- Suzuki, Teruhiko; Yagasaki, Yoichi; Sudo, Tatsuya; and Okazaki, Toru, 5,590,139, Cl. 371-49,100.
- Tanahashi, Makoto; and Takenaka, Kazuyasu, 5,589,857, Cl. 345-174,000.
- Uryu, Masaru; Tokura, Kunihiko; Chatani, Ikuo; Mizoguchi, Ikuo; and Ito, Mamoru, 5,590,212, Cl. 381-191,000.
- Yamamura, Takaya; and Esaki, Kunihiro, 5,589,801, Cl. 331-14,000.
- Sony Electronics, Inc.: See—
- Ota, Takaaki, 5,589,841, Cl. 343-760,000.
- Sony/Tektronix Corporation: See—
- Sato, Yasushi; and Kamibayashi, Kaname, 5,589,952, Cl. 358-487,000.
- Soong, Tsai C. Handle of golf club with improved control, 5,588,920, Cl. 473-231,000.
- Soques, Martin P.: See—
- Linz, Alfredo R.; Cabler, Carlin D.; Brown, Glen W.; and Soques, Martin P., 5,589,830, Cl. 341-110,000.
- Sorace, Dominic A.: See—
- Snyder, Ralph E.; Sorace, Dominic A.; and Benford, James G., 5,588,321, Cl. 72-366,200.
- Sorge, Joseph A.; and Short, Jay M., to Union Bank of California, N.A. Mutagenesis testing using transgenic non-human animals carrying test DNA sequences, 5,589,155, Cl. 424-9,200.
- Sotheran, Martin W.: See—
- Jones, Anthony M.; Dewar, Kevin D.; and Sotheran, Martin W., 5,590,067, Cl. 364-725,000.
- Souhner, Florent: See—
- Lalouel, Jean-Marc; Jeunenmaître, Xavier; Lifton, Richard P.; Soubrier, Florent; Kotelevtsev, Youri; and Corvol, Pierre, 5,589,584, Cl. 536-24,310.
- Southpac Trust International, Inc.: See—
- Weder, Donald E.; Straeter, William F.; and Straeter, Joseph G., 5,588,277, Cl. 53-399,000.
- Weder, Donald E.; and Craig, Franklin J., 5,588,530, Cl. 206-451,000.
- Southwall Technologies, Inc.: See—
- Gibbons, Kevin P.; Lau, Louis C.; and Woodard, Floyd E., 5,589,280, Cl. 428-626,000.
- Sowadsky, Elliot A.; Widigen, Larry; Puziol, David L.; and Van Dyke, Korbin S., to Advanced Micro Devices, Inc. Superscalar execution unit for sequential instruction pointer updates and segment limit checks, 5,590,351, Cl. 395-800,000.
- Sowers, Kenneth W.: See—
- Green, Norman E.; and Sowers, Kenneth V., 5,588,325, Cl. 74-15,630.
- SpaceLabs Medical, Inc.: See—
- Tien, Jonathan, 5,588,427, Cl. 128-633,000.
- Spaulding, Glenn F., to United States of America, National Aeronautics and Space Administration. Constructing a high density cell culture system, 5,589,112, Cl. 264-413,000.
- Spear, David H.; and Edwards, Peter A., to University of California, Regents of the. Method for mammalian cell transfection, 5,589,368, Cl. 435-172,300.
- Spears, Cameron: See—
- Sangveraphunsiri, Vic; Pina, Felix; Shu, Thomas; and Spears, Cameron, 5,590,375, Cl. 395-841,000.
- Spears, William E., Jr.: See—
- Rubey, Arthur C., III; Taylor, Andrew M.; and Spears, William E., Jr., 5,588,901, Cl. 451-99,000.
- Speck, Michael W. Baseball/softball equipment bag, 5,588,529, Cl. 206-315,100.
- Spector, Yechiel; Jacobson, Esther; Naishtut, Vida; Vitenberg, Michael; and Beinert, Zohar, to Spectronix Ltd. Fire extinguishing methods and systems, 5,588,493, Cl. 169-46,000.
- Spectra-Physics Lasers, Inc.: See—
- Reeder, Dennis, 5,590,149, Cl. 372-107,000.
- Spectronix Ltd.: See—
- Spector, Yechiel; Jacobson, Esther; Naishtut, Vida; Vitenberg, Michael; and Beinert, Zohar, 5,588,493, Cl. 169-46,000.
- Speggin, Paolo, to Lino Manfroto & Co., S.p.A. Panorama head for optical equipment particularly for photographic equipment, 5,589,903, Cl. 396-428,000.
- Speit, Burkhardt: See—
- Donne, Mario Dalle; Schumacher, Guster; Geiler, Volkmar; Clement, Marc; and Speit, Burkhardt, 5,589,427, Cl. 501-33,000.
- Spellman, Michael W.: See—
- Hotchkiss, Adair J.; O'Connor, John V.; and Spellman, Michael W., 5,589,361, Cl. 435-69,100.
- Spens, Richard P.: See—
- Duham, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, 5,588,257, Cl. 49-199,000.
- Speranza, Bernard E. Method for determining the level of a submerged layer of liquid material, 5,588,324, Cl. 73-290,000.
- Sperotto Rimar S.p.A.: See—
- Bertoldo, Franco; and Dalla Vecchia, Gino, 5,588,192, Cl. 26-37,000.
- Spevak, Walter: See—
- Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratowa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189,000.
- Spiegel, Leo; and Pischinger, Franz, to FEV Motorentechnik GmbH & Co. Process and arrangement for supplying lubricant to a reciprocating piston engine, 5,588,504, Cl. 184-6,800.
- Spiegelberg, Bernard N.; and Sauter, Mark E., to Tulip Corporation. Side wall electricity battery terminal, 5,589,294, Cl. 429-178,000.
- Sponheimer, Manfred; Welt, Guenther; and Ziegelmayer, Manfred, to Hoechst AG. Process for screening cellulose ethers, 5,589,589, Cl. 536-86,000.
- Sprecher, Arnold F., Jr.: See—
- Gloden, Michael L.; and Sprecher, Arnold F., Jr., 5,590,091, Cl. 367-140,000.
- Spring, G. Everett; and Keller, Douglas V., Jr., to Spring Patents Corporation. Leak detection with non-toxic liquids, 5,589,631, Cl. 73-49,200.
- Spring Patents Corporation: See—
- Spring, G. Everett; and Keller, Douglas V., Jr., 5,589,631, Cl. 73-49,200.
- Springfield, Randall S.: See—
- Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828,000.
- Sprouse, Jeff A.: See—
- Rahman, Mizanur M.; Sabernick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735,000.
- Squires, Milo B.: See—
- Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.
- Srivastava, Mani B.: See—
- Mishra, Partho P.; and Srivastava, Mani B., 5,590,126, Cl. 370-329,000.
- Sroka, Peter; and Harrison, Peter D., to Nokia Mobile Phones Ltd. Method and apparatus for suppressing spurious third-order responses in transceivers, 5,590,411, Cl. 455-78,000.
- SSI Medical Services, Inc.: See—
- Pahno, Demetrios A.; Stolpmann, James R.; and Thomas, James M. C., 5,588,167, Cl. 5-606,000.
- Stache, Ulrich: See—
- Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228,000.
- Stackhouse, Inc.: See—
- Ignon, Roger G.; and Thomas, Ronald E., Jr., 5,588,153, Cl. 2-457,000.
- Staehele, Bradford G.: See—
- Burton, John H.; and Staehele, Bradford G., 5,588,965, Cl. 604-101,000.
- Stahl, Hans-Juergen; Dittmann, Guenter; Doege, Reimer; Schneider, Richard; and Filges, Ralf, to Kloeckner-Humboldt-Deutz AG. Thrust grating cooler and method for cooling hot material, 5,588,829, Cl. 432-77,000.
- Staktek Corporation: See—
- Roane, Jerry M., 5,588,205, Cl. 29-830,000.
- Stanford Telecommunications, Inc.: See—
- Weinberg, Aaron, 5,589,834, Cl. 342-354,000.
- Stanley Electric Co. Ltd.: See—
- Atsumi, Toru; Kamijo, Yasuhiro; Furukawa, Yoshiki; and Matsumura, Naoki, 5,589,678, Cl. 235-472,000.
- Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161,000.
- Stanley Works, The: See—
- Duham, Dean C.; Spens, Richard P.; Lowell, Dana; Chan, Chin-Feng; and Shou, Ming-Hwa, 5,588,257, Cl. 49-199,000.
- Rust, Howell B.; and Hreha, Kenneth W., 5,588,343, Cl. 81-489,000.
- Stansbury, Darryl: See—
- Hofmann, Jim; and Stansbury, Darryl, 5,588,359, Cl. 101-128,210.
- Stanwick, Ronald S.: See—
- DeCarlo, David J.; Mineur, Thomas L.; and Stanwick, Ronald S., 5,589,666, Cl. 174-87,000.
- Stapleton, Craig A.: See—
- Cronce, Gary M.; and Stapleton, Craig A., 5,588,572, Cl. 224-321,000.
- Star Micronics Co., Ltd.: See—
- Suzuki, Kanji, 5,588,762, Cl. 400-582,000.
- State of Israel, Ministry of Agriculture: See—
- Mizrach, Amos; Galili, Naftali; and Rosenhouse, Giora, 5,589,209, Cl. 426-231,000.
- Staver, Daniel A.: See—
- Frank, Paul A.; McGrath, Donald T.; and Staver, Daniel A., 5,589,766, Cl. 324-158,100.
- Stebbins, Scott. Training ball for baseball and softball batting practice, 5,588,648, Cl. 473-451,000.
- Stefan, Ion; and Cesnik, Friedrich, to L. & C. Steinmüller GmbH. Method of generating steam in a forced-through-flow boiler, 5,588,400, Cl. 122-406,100.
- Stein, Christoph: See—
- Elkhoury, George F.; and Stein, Christoph, 5,589,480, Cl. 514-282,000.
- Stein, Frank L.; and Verrier, Guy F., to International Touch Machines Corporation. System & method for dynamically labeled touch sensitive buttons in a digitizing display, 5,589,856, Cl. 345-173,000.
- Stein, Gerhard: See—
- Neuert, Richard; and Stein, Gerhard, 5,589,265, Cl. 428-361,000.
- Stein, Russell E.: See—
- Emambakhsh, Ali S.; and Stein, Russell E., 5,588,668, Cl. 280-728,200.
- Steinbach, Christian: See—
- Döbbling, Klaus; Haumann, Jürgen; Knöpfel, Hans P.; Paikert, Bettina; Ruck, Thomas; Sattelamayer, Thomas; and Steinbach, Christian, 5,588,826, Cl. 431-354,000.
- Steiner Freizeitmöbel Gesellschaft m.b.H. & Co. KG: See—
- Furtner, Josef, 5,588,549, Cl. 220-7,000.
- Steinlechner, Werner: See—
- Covi, Christian; and Steinlechner, Werner, 5,588,185, Cl. 24-381,000.
- Steinmeier, Rudolf: See—
- Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709,000.
- Stekette, Campbell H., Jr., to NuPipe, Inc. Method for manufacturing a replacement pipe for installation in an existing conduit, 5,589,131, Cl. 264-568,000.
- Stemple, Derek L.: See—
- Anderson, David J.; and Stemple, Derek L., 5,589,376, Cl. 435-240,200.
- Stenzel, Andre: See—
- Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704,000.
- Stenzel, Klaus: See—
- Hain, Rüdiger; and Stenzel, Klaus, 5,589,626, Cl. 800-205,000.
- Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jörg; Stenzel, Klaus; and Thomzik, Jürgen, 5,589,621, Cl. 800-205,000.
- Stepanek, Michael J., to Hampshire Paper Corp. Adhering ceremonial roll, 5,589,013, Cl. 156-71,000.
- Stepro, James A.: See—
- Edgington, Robert J.; Stepro, James A.; Wissell, Harold J.; and Lundberg, Scott A., 5,589,301, Cl. 429-234,000.
- Sterflinger, Fritz; and Möhlenkamp, Hans, to Jos. L. Meyer Werft GmbH & Co. Plate element for a building panel assembly, 5,588,268, Cl. 52-236,700.
- Sterflinger, Michael, to Exstra Corporation. Virtual drum imagesetter, 5,589,900, Cl. 396-548,000.
- Stern, Howard, to Robotic Vision Systems, Inc. System for detecting ice or snow on surface which specularly reflects light, 5,589,822, Cl. 340-583,000.
- Sternlicht, Andrew L. Method for controlling the body temperature of a patient, 5,588,968, Cl. 607-107,000.
- Stevens, Bruce W., to United States of America, Navy. Asynchronous bidirectional application program processes interface for a distributed heterogeneous multiprocessor system, 5,590,281, Cl. 395-200,010.
- Stevens, Jessica L.; and Crystal, Bonnie, to Telegen Corporation. System for interception and transmission of communication signals on telephone and data lines, 5,590,182, Cl. 379-130,000.
- Stevenson, Tom D. Process for making sodium bicarbonate from NaHCO₃ rich solutions, 5,588,713, Cl. 299-5,000.
- Stief, Reinhard; Schork, Roger; Müller-Broll, Gerhard; Jost, Thomas; Matuttat, Manfred; and Schmitt, Klaus-Dieter, to Firma Carl Freudenberg. Housing Lining, 5,589,242, Cl. 428-45,000.
- Stier, David E.; and Liquori, Katherine S., to International Paper. Dual ovenable food package, 5,588,587, Cl. 229-232,000.
- Stiles, Ernest D.; and Hartsock, Dale L., to Ford Motor Company. Fuel tank having an integrally molded permeation barrier, 5,589,241, Cl. 428-36,900.
- Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryuji; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, to Cold Spring Harbor Laboratory; and University of California, The Regents of the. Origin of replication complex genes and methods of using the same, 5,589,341, Cl. 435-6,000.
- Stipp, Gordon K.: See—
- Guskey, Gerald J.; Hellyer, James A.; Kluesener, Bernard W.; and Stipp, Gordon K., 5,589,216, Cl. 426-607,000.
- Stocho Fasteners GmbH: See—
- Ströter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegemund, Rainer, 5,588,326, Cl. 74-50,000.
- Stolpmann, James R.: See—
- Pahno, Demetrios A.; Stolpmann, James R.; and Thomas, James M. C., 5,588,167, Cl. 5-606,000.
- Stoltenberg, Blaise G.: See—
- Pratt, David S.; Bourgeois, Philip; Cornelius, Edward J., III; Lee, Chin H.; and Stoltenberg, Blaise G., 5,590,209, Cl. 381-168,000.
- Stone, Dwight V.; Long, Douglas A.; and Salazar-Vior, Jose M., to Caterpillar Inc. Engine assembly with leaf spring cam follower, 5,588,413, Cl. 123-508,000.
- Stoner, Spurgeon C.: See—
- Rank, David B.; Bonebrake, Randall A.; and Stoner, Spurgeon C., 5,588,216, Cl. 33-286,000.
- Storey, J. Kirk; and Olson, Brent K., to Morton International, Inc. Seat structure pressure vessel for airbag installation, 5,588,670, Cl. 280-730,200.

- Stout, Ralph L.: See—
- Cohen, Gerald D.; Stout, Ralph L.; and Edson, Jay H., 5,590,319, Cl. 395-604,000.
- Stoynoff, Richard P.: See—
- Bianchi, Sabatino A.; and Stoynoff, Richard P., 5,588,319, Cl. 72-186,000.
- Straeter, Joseph G.: See—
- Weder, Donald E.; Straeter, William F.; and Straeter, Joseph G., 5,588,277, Cl. 53-399,000.
- Straeter, William F.: See—
- Weder, Donald E.; Straeter, William F.; and Straeter, Joseph G., 5,588,277, Cl. 53-399,000.
- Strahm, Christian, to Solipat AG. Method and device for treating an in particular tension-sensitive textile web, 5,588,170, Cl. 8-149,100.
- Strait, Daniel L. Torsion lock parking brake actuator with push down release, 5,588,335, Cl. 74-512,000.
- Strasik, Michael: See—
- Baker, Anna L.; and Strasik, Michael, 5,589,441, Cl. 505-125,000.
- Stratagene: See—
- Short, Jay M., 5,589,392, Cl. 435-320,100.
- Strathy, Nancy: See—
- Ryan, Michael J.; Lotvin, Jason A.; Strathy, Nancy; and Fantini, Susan E., 5,589,385, Cl. 435-258,350.
- Stratowa, Christian: See—
- Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratowa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189,000.
- Strickland, Carl C., Jr.: See—
- Clark, William A.; Strickland, Carl C., Jr.; and Newman, Mark C., 5,589,808, Cl. 336-92,000.
- Strohl, Niles E.: See—
- Krause, Jeffrey; Strohl, Niles E.; Seaman, Michael J.; Russell, Steven P.; and Hart, John H., 5,590,285, Cl. 395-200,200.
- Strom, William M.: See—
- Ramsey, Kenneth C.; Miller, William J.; and Strom, William M., 5,589,402, Cl. 437-2,000.
- Stromsholmens Mekaniska Verkstad AB: See—
- Sand, Gunnar, 5,588,641, Cl. 267-119,000.
- Ströter, Hermann; Obst, Frank; Kamps, Rolf; Reich, Holger; and Siegemund, Rainer, to Stocho Fasteners GmbH. Feeding device for parts to be mounted, 5,588,326, Cl. 74-50,000.
- Strupczewski, Joseph T.; and Glamkowski, Edward J., to Hoechst-Roussel Pharmaceuticals, Inc. N-[(4-heteroaryl-1-piperidinyl)alkyl]-2-benzoxazolinones and related compounds and their therapeutic utility, 5,589,488, Cl. 514-321,000.
- Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeau, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., to Hoechst-Roussel Pharmaceuticals, Inc. 2-[(3-heteroaryl-1-pyrrolidinyl)alkyl]-1,3-dioxanes and related compounds and their therapeutic utility, 5,589,494, Cl. 514-37,300.
- Stubbs, Robert E.: See—
- Burgess, Dana J.; and Stubbs, Robert E., 5,590,369, Cl. 395-800,000.
- Stuck, Robert M.; and Rapier, James, III, to Marshall Air Systems, Inc. Apparatus for conveyORIZED gndle-like cooking of food products, 5,588,354, Cl. 99-386,000.
- Studer, Michael K.; and Zdrorow, Thomas J.; and Elms, Timothy J., to Entact Corporation. Apparatus and method for treating hazardous waste material, 5,588,947, Cl. 588-252,000.
- Stumper, Werner, to Robert Bosch GmbH. Method and device for electronically controlling the brake system of a vehicle, 5,588,716, Cl. 303-7,000.
- Stupp, James R.: See—
- Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800,000.
- Su, Yuh-Jia, to Applied Materials, Inc. Gas distribution plate for semiconductor wafer processing apparatus with means for inhibiting arcing, 5,589,002, Cl. 118-723,000.
- Subisak, Gregory J.; and Hammond, Douglas S., to Holophone Corporation. Internally illuminated sign, 5,588,742, Cl. 362-291,000.
- Suda, Hiroyuki: See—
- Kojiri, Katsuhisa; Kondo, Hisao; Arakawa, Hiroharu; Ohkubo, Mitsuru; and Suda, Hiroyuki, 5,589,365, Cl. 435-85,000.
- Suda, Masashi: See—
- Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145,000.
- Sudo, Shuji: See—
- Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, 5,590,008, Cl. 360-126,000.
- Sudo, Tatsuya: See—
- Suzuki, Teruhiko; Yagasaki, Yoichi; Sudo, Tatsuya; and Okazaki, Toru, 5,590,139, Cl. 371-49,100.
- Sudo, Toshiyuki: See—

- Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi. 5,589,956, Cl. 359-15.000.
- Suenaga, Yutaka, to Nikon Corporation. Retrofocus-type wide angle lens system having a fixed front lens group and a movable rear lens group. 5,589,988, Cl. 359-752.000.
- Suga, Shuzo: See—
Kuno, Koichi; and Suga, Shuzo, 5,589,325, Cl. 430-576.000.
- Suga, Takayuki: See—
Uchikawa, Kiyoshi; Suga, Takayuki; and Furusawa, Akira, 5,589,936, Cl. 356-345.000.
- Sugai, Masaru: See—
Asano, Katsuhiko; Sugai, Masaru; Yamaguchi, Hiroyuki; and Umeno, Takaji, 5,588,721, Cl. 303-163.000.
- Sugama, Sadaaki: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadaaki; Watanabe, Kenji; Osada, Torachika; Nakajima, Kazuhiro; Tsumumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohsei, 5,589,862, Cl. 347-87.000.
- Sugata, Yoshinobu; Yamazaki, Mikio; and Umegaki, Takashi, to Fuji Electric Co., Ltd. Ink jet recording head and method of producing the same. 5,589,860, Cl. 347-20.000.
- Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshitaka, to Mitsubishi Chemical Corporation. Modified ion exchange resins and use thereof. 5,589,517, Cl. 521-33.000.
- Sugimoto, Masaharu: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuaki; Yamazaki, Osamu; Komura, Yukihiko; and Suga-gawa, Tomoo, 5,590,001, Cl. 360-97.020.
- Sugiyama, Hiroshi: See—
Kadowaki, Hidejiro; Sugiyama, Hiroshi; Ishida, Yasuhiko; and Takamiya, Makoto, 5,589,858, Cl. 347-14.000.
- Sugiyama, Hiroyuki; Hirose, Norio; Hamabuchi, Teruyoshi; and Muto, Hikoji, to Komori Corporation. Cylinder throw-on and throw-off mechanism for printing press. 5,588,362, Cl. 101-218.000.
- Sugiyama, Hisanori: See—
Kashiwaura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Itsu; Oota, Norio; and Sugiyama, Hisanori, 5,590,097, Cl. 369-13.000.
- Sugiyama, Masanori: See—
Iwasaki, Shinichi; Sugiyama, Masanori; Umemura, Chiaki; Oikawa, Akemi; and Takahashi, Hisayoshi, 5,589,752, Cl. 318-701.000.
- Sugiyama, Osamu: See—
Tsuiji, Masanori; Abe, Kimihiko; Sugiyama, Osamu; and Yamamoto, Hiroshi, 5,588,868, Cl. 439-397.000.
- Sukagawa, Tomoo: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Sloma, Alan; Ruffo, Gerald A., Jr.; Rudolph, Cathy F.; Sullivan, Barbara J.; and Pero, Janice, 5,589,383, Cl. 435-252.310.
- Sullivan, Michael J.; Nealon, John L.; and Nesbitt, R. Dennis, to Lisco, Inc. Golf ball. 5,588,924, Cl. 473-377.000.
- Sumiden Opcom Ltd.: See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53.000.
- Sumitani, Naoko: See—
Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshitaka, 5,589,517, Cl. 521-33.000.
- Sumitomo Chemical Company, Limited: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446.000.
- Matsuda, Yoji; Morikawa, Masao; and Toma, Masaaki, 5,589,077, Cl. 210-741.000.
- Minobe, Masao; Shiraga, Noboru; and Nakamura, Nobutaka, 5,588,746, Cl. 374-10.000.
- Ohnishi, Toshihiro; Noguchi, Takanobu; and Doi, Shuji, 5,589,320, Cl. 430-321.000.
- Sumitomo Electric Industries, Ltd.: See—
Hayami, Hiroshi, 5,589,219, Cl. 427-117.000.
- Kato, Takashi; and Nakanishi, Hiromi, 5,589,990, Cl. 359-799.000.
- Kugai, Hirokazu, 5,589,772, Cl. 324-240.000.
- Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu, 5,589,281, Cl. 428-688.000.
- Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53.000.
- Sumitomo Metal Industries, Ltd.: See—
Kojima, Shoichi; Minagawa, Kazuhiro; Kano, Haruyuki; Miyazaki, Tadaki; and Wada, Hiroaki, 5,589,116, Cl. 264-65.000.
- Sumitomo Rubber Industries, Ltd.: See—
Hiraoka, Hidenori; and Koizumi, Yoshimasa, 5,589,546, Cl. 525-193.000.
- Jones, David, 5,589,816, Cl. 340-444.000.
- Sumitomo Wiring Systems, Ltd.: See—
Hattori, Kazuhiko, 5,588,883, Cl. 439-761.000.
- Higuchi, Fijii, 5,588,341, Cl. 81-3.800.
- Kawamura, Shigeto; and Yamamura, Takehiko, 5,590,231, Cl. 385-78.000.
- Nankoh, Yuichi, 5,588,855, Cl. 439-188.000.
- Uchiyama, Takahiro, 5,588,860, Cl. 439-336.000.
- Summerfelt, Scott R.; and Beratan, Howard R., to Texas Instruments Incorporated. Electrodes comprising conductive perovskite-seed layers for perovskite dielectrics. 5,589,284, Cl. 428-697.000.
- Summers, George D., Jr.: See—
Jensen, Michael L.; Summers, George D., Jr.; and Baum, Thomas M., 5,588,869, Cl. 439-417.000.
- Sun Chemical Corporation: See—
Adkins, John L.; and Patel, Dinesh P., 5,589,323, Cl. 430-492.000.
- Sun, Jing X.: See—
Beach, Bradley L.; Feeman, James F.; Pearson, Anna M.; and Sun, Jing X., 5,589,522, Cl. 523-160.000.
- Sun Microsystems, Inc.: See—
Kondratiev, Victor K.; Kouplitchenko, Valery P.; Galitsky, Alexander V.; and Baehr, Geoffrey G., 5,590,413, Cl. 455-86.000.
- Lewis, Brian T.; and Goldstein, Theodore C., 5,590,331, Cl. 395-708.000.
- Mehring, Peter A.; and Nguyen, Cau L., 5,590,286, Cl. 395-250.000.
- Sun, Wei M.: See—
Herb, Craig A.; Chen, Liang B.; Chung, Judy B.; Long, Michelle A.; Sun, Wei M.; Newell, Gerald P.; Kamis, Kimberly; and Brucks, Richard M., 5,589,177, Cl. 424-401.000.
- Sun, Yunlong: See—
Baird, Brian; DeFreez, Richard; and Sun, Yunlong, 5,590,141, Cl. 372-10.000.
- Sundqvist, Ingemar, to Sunds Defibrator Industries AB. Liquid treatment device. 5,589,035, Cl. 162-232.000.
- Sunds Defibrator Industries AB: See—
Sundqvist, Ingemar, 5,589,035, Cl. 162-232.000.
- Sunds Defibrator Industries Aktiebolag: See—
Färnstrand, Per-Åke; Sjodin, Lars T.; Lindström, Lars-Åke; and Nordén, K. Solveig E., 5,589,031, Cl. 162-65.000.
- Sunds Defibrator Pori OY: See—
Tikka, Panu; and Kovasin, Kari, 5,589,033, Cl. 162-84.000.
- Sung, Hung-Cheng; and Chen, Ling, to Taiwan Semiconductor Manufacturing Company. Method of manufacturing self-aligned bit-line during EPROM fabrication. 5,589,413, Cl. 437-43.000.
- Suni, Jarmo; and Rantanen, Petri, to Instrumentarium Corporation. Mam-mography unit. 5,590,166, Cl. 378-37.000.
- Suntec Corporation: See—
Tomozane, Shotaro; Kidou, Hirokazu; and Nakahayashi, Yukikazu, 5,589,248, Cl. 428-174.000.
- Superconducting Core Technologies, Inc.: See—
Yandroski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., 5,589,845, Cl. 343-909.000.
- Supere Polymer Inc.: See—
Harvey, Andrew C.; Lusigne, Richard W.; and Rubin, Leslie S., 5,589,236, Cl. 428-1.000.
- Surridge, Nigel A.: See—
Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wilsey, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.
- Sutherland, Daniel N.: See—
Shagott, David M.; Kruse, Gary E.; Harber, Blair L., Jr.; Sutherland, Daniel N.; and Travis, Terrell F., 5,588,985, Cl. 95-25.000.
- Suthersan, Suthan S.; Dynkin, Boris; and Cushing, Richard, to Geraghty & Miller, Inc. Method and system to achieve two dimensional air sparging. 5,588,490, Cl. 166-370.000.
- Sutoh, Masaki; and Fukunaga, Shinichi, to Fuji Xerox Co., Ltd. Developing apparatus. 5,589,916, Cl. 399-286.000.
- Suton, David M., to British Gas plc. Sensor fault detection. 5,589,627, Cl. 73-1.000.
- Sutton, Michael R. Hinge for a glass shower door. 5,588,181, Cl. 16-252.000.
- Suvorov, A. L.: See—
Kafanov, V. S.; Suvorov, A. L.; and Sheshin, E. P., 5,588,893, Cl. 445-6.000.
- Suzukamo, Gohfu: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446.000.
- Suzuki, Eiji: See—
Okabe, Hideaki; Suzuki, Eiji; Kogure, Masao; and Saito, Takanori, 5,589,192, Cl. 424-486.000.
- Suzuki, Fujio: See—
Shiraki, Masao; Suzuki, Fujio; and Yoshida, Kazunori, 5,588,470, Cl. 139-435.500.
- Suzuki, Fumitake: See—
Kiuchi, Katsumi; Wakamatsu, Hiroaki; Suzuki, Fumitake, and Koshikawa, Takao, 5,589,262, Cl. 428-336.000.
- Suzuki, Hiroaki, to Fujitsu Limited. Oxygen electrode, biosensor and processes for manufacturing same. 5,589,133, Cl. 422-79.000.
- Suzuki, Hiroshi: See—
Mitsuno, Makoto; Akagiri, Kenzo; Suzuki, Hiroshi; and Shimoyoshi, Osamu, 5,590,108, Cl. 369-59.000.
- Nishitani, Keizo; and Suzuki, Hiroshi, 5,589,715, Cl. 307-10.100.
- Suzuki, Kanji, to Star Micronics Co., Ltd. Paper discharge apparatus. 5,588,762, Cl. 400-582.000.
- Suzuki, Maki: See—

- Tazawa, Masashi; Fujinawa, Nobuhiro; Matsui, Kumiko; and Suzuki, Maki, 5,589,953, Cl. 358-498.000.
- Suzuki, Masao; Saito, Koichi; and Nakata, Masahide, to NOF Corporation. Cosmetic composition and an emulsion composition. 5,589,515, Cl. 514-784.000.
- Suzuki, Nobuhiko: See—
Ikumi, Tooru; Suzuki, Nobuhiko; and Ishikawa, Satoshi, 5,588,854, Cl. 439-164.000.
- Suzuki, Nobuo: See—
Horie, Seiji; Sano, Kenji; Suzuki, Nobuo; and Watarai, Shu, 5,589,312, Cl. 430-115.000.
- Suzuki, Shigemichi; and Endo, Sadahisa, to Kansei Corporation. Construction of a vehicle door provided with a wiring harness and a waterproof grommet used in the construction. 5,588,260, Cl. 49-502.000.
- Suzuki, Tadao: See—
Shinzaki, Akihiro; Watanabe, Miwa; and Suzuki, Tadao, 5,589,349, Cl. 435-26.000.
- Suzuki, Takashi: See—
Ookawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, 5,590,109, Cl. 369-77.200.
- Suzuki, Teruhiko; Yagasaki, Yoichi; Sudo, Tatsuya; and Okazaki, Toru, to Sony Corporation. Method of recording a compressed motion picture signal in which effects of rounding errors resulting from inversely transforming transaction coefficients representing are mitigated. 5,590,139, Cl. 371-49.100.
- Suzuki, Tetsuo, to SCS Promotion Company Limited. Visual panel. 5,588,236, Cl. 40-558.000.
- Suzuki, Tetsuaki: See—
Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryooji, 5,589,962, Cl. 349-46.000.
- Suzuki, Tomoko; Kinoshita, Akira; Hayata, Hirofumi; and Sakimura, Tomoo, to Konica Corporation. Electrophotographic photoreceptor containing perylenes. 5,589,309, Cl. 430-59.000.
- Suzuki, Tomoko: See—
Etou, Yoshihiko; Oshiba, Takeo; Matsushima, Asao; Hayata, Hirofumi; Sakimura, Tomoo; Suzuki, Tomoko; and Kinoshita, Akira, 5,589,314, Cl. 430-126.000.
- Suzuki, Toshiaki: See—
Hagiwara, Hideaki; and Suzuki, Toshiaki, 5,589,436, Cl. 504-114.000.
- Suzuki, Toshio; and Iida, Yoshikatsu, to Yamaha Hatsudoki Kabushiki Kaisha. Fuel control system for gaseous fueled engine. 5,588,416, Cl. 123-684.000.
- Suzuki, Toshitaka: See—
Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshitaka, 5,589,517, Cl. 521-33.000.
- Suzuki, Yasunori: See—
Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, 5,589,270, Cl. 428-411.100.
- Suzuki, Yoshinori: See—
Tomingaga, Hiroyoshi; and Suzuki, Yoshinori, 5,588,902, Cl. 451-288.000.
- Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, to Honda Giken Kogyo Kabushiki Kaisha; and Stanley Electric Co., Ltd. Car air conditioner. 5,588,302, Cl. 62-161.000.
- Suzuki, Yuji: See—
Imaichi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Himura, Koichi; and Haneda, Tadayoshi, 5,589,251, Cl. 428-209.000.
- Svennerholm, Bo: See—
Vahlne, Anders; Svennerholm, Bo; Rymo, Lars; Jeansson, Stig; and Horal, Peter, 5,589,175, Cl. 424-208.100.
- Svereika, Aileen M.: See—
Lobo, Lloyd A.; and Svereika, Aileen M., 5,589,322, Cl. 430-449.000.
- Swain, Henry L., to Illinois Tool Works Inc. Extruded zippers for upholstery applications. 5,588,187, Cl. 24-587.000.
- Swan Instruments, Inc.: See—
Chur, Sung P., 5,589,771, Cl. 324-212.000.
- Swanberg, Alan M. Circular saw with dust trapper. 5,588,213, Cl. 30-124.000.
- Swars, Helmut: See—
Maus, Wolfgang; Brück, Rolf; and Swars, Helmut, 5,588,291, Cl. 60-274.000.
- Swartz, Jerome; Shepard, Howard M.; Krichever, Mark J.; Metlitsky, Boris; and Barkan, Edward, to Symbol Technologies. Portable laser diode scanning head. 5,589,680, Cl. 235-472.000.
- Sweet, Frederick J.; and Meyer, Larry P., to Nelson Irrigation Corporation. Nutating sprinkler. 5,588,595, Cl. 239-222.170.
- Sweitzer, Bruce K., Jr. Heat dissipation unit. 5,588,591, Cl. 237-8.000.
- Swisher, George W., Jr.; and Phillips, John F., to CMI Corporation. Paving machine having automatic metering screed control. 5,588,776, Cl. 404-72.000.
- Symbol Technologies: See—
Swartz, Jerome; Shepard, Howard M.; Krichever, Mark J.; Metlitsky, Boris; and Barkan, Edward, 5,589,680, Cl. 235-472.000.
- Symbol Technologies, Inc.: See—
Dvorkis, Paul; and Shepard, Howard, 5,589,679, Cl. 235-472.000.
- Synectic Technology, Inc.: See—
Thornton, Michael G.; and Thornton, Janine M., 5,588,535, Cl. 209-38.000.
- Syntello Vaccine Development KB: See—
- Vahlne, Anders; Svennerholm, Bo; Rymo, Lars; Jeansson, Stig; and Horal, Peter, 5,589,175, Cl. 424-208.100.
- Syntex (U.S.A.) Inc.: See—
Krstensky, John L.; Nestor, John J., Jr.; Ho, Teresa H.; Vickery, Brian H.; and Bach, Chinh T., 5,589,452, Cl. 514-12.000.
- Synthelabo: See—
Andrieu, Veronique; Montel, Jean; and Wick, Alexander, 5,589,190, Cl. 424-462.000.
- Jegham, Samir; Defosse, Gérard; Purcell, Thomas A.; and Even, Luc, 5,589,476, Cl. 514-230.200.
- Systems Integration and Research, Inc.: See—
Hobby, Gray D.; and Riggs, Bernard A., 5,589,012, Cl. 148-561.000.
- Szabó, Anna Z.: See—
Magyar, Kálmán; Gaál, József; Sziráki, István; Lengyel, József; Szabó, Anna Z.; Mármarosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter, 5,589,513, Cl. 514-654.000.
- Szabo, Sandor: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Szalai, John S.: See—
Rudoy, Edward; and Szalai, John S., 5,588,884, Cl. 439-845.000.
- Szarmes, Eric B., to Duke University. Birefringent beamsplitter for high power lasers and laser applications. 5,590,148, Cl. 372-105.000.
- Szatmári, István: See—
Magyar, Kálmán; Gaál, József; Sziráki, István; Lengyel, József; Szabó, Anna Z.; Mármarosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter, 5,589,513, Cl. 514-654.000.
- Szentirmai, Zsolt: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Sziráki, István: See—
Magyar, Kálmán; Gaál, József; Sziráki, István; Lengyel, József; Szabó, Anna Z.; Mármarosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter, 5,589,513, Cl. 514-654.000.
- Szmidt, Christopher R.: See—
Bryant, Stewart F.; Seaman, Michael J.; and Szmidt, Christopher R., 5,590,366, Cl. 395-800.000.
- Szombathelyi, Zsolt: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Szporny, Laszlo: See—
Harsanyi, Kalman; Gizur, Tibor; Agai-Csongor, Eva; Kallai-Sohonyai, Anna; Kapolnas-Pap, Marta; Csizer, Eva; Hegedüs, Bela; Szporny, Laszlo; Kiss, Bela; Karpati, Egon; Palosi, Eva; Szombathelyi, Zsolt; Sarkadi, Adam; Gere, Aniko; Bodo, Mihaly; Csomor, Katalin; Laszly, Judit; Szentirmai, Zsolt; Lapis, Erzebet; Szabo, Sandor; Bod, Peter; and Csehi, Attila, 5,589,486, Cl. 314-317.000.
- Tabata, Atsushi: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.
- Tabata, Shusaku: See—
Takahashi, Masahiko; and Tabata, Shusaku, 5,589,306, Cl. 430-18.000.
- Tachi-S Co., Ltd.: See—
Itou, Kenichi, 5,588,703, Cl. 297-284.400.
- Tachibana, Hiroaki, to NEC Corporation. Thin film magnetic head. 5,590,005, Cl. 360-103.000.
- Tada, Kazuhiro: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446.000.
- Tada, Koji: See—
Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu, 5,589,281, Cl. 428-688.000.
- Tadghighi, Hormoz: See—
Charles, Bruce D.; Hassan, Ahmed A.; Tadghighi, Hormoz; JanakiRam, Ram D.; and Sankar, Lakshmi N., 5,588,800, Cl. 416-24.000.
- Taga, Hidenori; Edagawa, Noboru; Takeda, Noriyuki; Yamamoto, Shu; and Akiba, Shigeyuki, to Kokusai Denshin Denwa Kabushiki Kaisha. Wave-length division multiplexed optical fiber transmission equipment. 5,589,969, Cl. 359-124.000.
- Taga, Yasunori: See—
Noda, Koji; Fujikawa, Hisayoshi; Yamashita, Katsuji; and Taga, Yasunori, 5,589,733, Cl. 313-509.000.

Tagliaferri, Roberto; and Canoli, Rodolfo, to I.M.A. Industria Macchine Automatiche S.p.A. Method and device for withdrawing flat folded carton blanks from a magazine and for feeding them to a carton set up line. 5,588,643, Cl. 271-35.000.

Taguchi, Akihito: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111.000.

Taguchi, Toshifumi: See—
Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshifumi; and Haraoka, Mutsumu, 5,588,611, Cl. 242-381.100.

Taguchi, Yutaka; Eda, Kazuo; Seki, Shun-ichi; and Onishi, Keiji, to Matsushita Electric Industrial Co., Ltd. Surface acoustic wave filter having parallel/serial resonator connection based on transmitting and receiving frequencies. 5,589,806, Cl. 333-193.000.

Tahara, Eiichi: See—
Fujisawa, Katsuhide; Tahara, Eiichi; and Hida, Tetsuya, 5,588,657, Cl. 277-180.000.

Taikoroza Co., Ltd.: See—
Iwasaki, Itsutoshi; Yamasaki, Tatsuo; and Sawada, Hideaki, 5,589,426, Cl. 501-32.000.

Taiwan Semiconductor Manufacturing Company: See—
Sung, Hung-Cheng; and Chen, Ling, 5,589,413, Cl. 437-43.000.

Taiwan Semiconductor Manufacturing Company Ltd.: See—
Wann, Yeh-Jye; and Liu, Hsien-Tsong, 5,589,414, Cl. 437-44.000.

Tajima Incorporated: See—
Aikawa, Satoru, 5,589,533, Cl. 524-529.000.

Tajiri, Shinsuke: See—
Yamaguchi, Takahiro; Tajiri, Shinsuke; and Nakada, Juichi, 5,590,158, Cl. 375-331.000.

Takaba, Katsumi: See—
Abe, Takahide; and Takaba, Katsumi, 5,590,040, Cl. 364-424.040.

Takada, Kazunori; Kondo, Shigeo; Yamamoto, Osamu; and Nishijima, Motoaki, to Matsushita Electric Industrial Co., Ltd. Electrochemical devices comprising lithium nitride-metal compounds in at least one of a pair of electrodes. 5,589,298, Cl. 429-218.000.

Takada, Kazunori: See—
Iwamoto, Kazuya; Aotani, Noboru; Takada, Kazunori; and Kondo, Shigeo, 5,589,296, Cl. 429-191.000.

Takada, Kunio, to Canon Kabushiki Kaisha. Magneto-optical disc. 5,589,244, Cl. 428-64.300.

Takada, Minoru; Sato, Koichi; and Yokobayashi, Kazuyuki, to Nissei ASB Machine Co., Ltd. Method of injection molding a preform and apparatus for the same. 5,589,130, Cl. 264-537.000.

Takada, Yukinori; Kuno, Tokiyuki; Muto, Yasuo; and Asai, Koichi, to Fuji Machine Mfg. Co., Ltd. Electronic-component supplying cartridge. 5,588,614, Cl. 242-538.200.

Takagi, Atsushi, to Toyota Jidosha Kabushiki Kaisha. Color reproducing device for reproducing matched colors and an outputting device for outputting information for reproducing a color of a coated surface. 5,590,251, Cl. 395-131.000.

Takagi, Hiroshi: See—
Konoke, Takehiro; Marusawa, Hiroshi; Takagi, Hiroshi; and Tomono, Kunsaburo, 5,589,096, Cl. 252-62.570.

Takagi, Shoji: See—
Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, 5,589,668, Cl. 174-266.000.

Takagi, Sinya: See—
Kawaguchi, Kenzo; Takemura, Tetsuya; Matsubara, Hideki; Takagi, Sinya; and Kanda, Atsushi, 5,589,429, Cl. 501-96.000.

Takahama, Hiroyuki: See—
Tepman, Avi; Jinbo, Takeshi; Takahama, Hiroyuki; and Saito, Akihiko, 5,589,224, Cl. 427-248.100.

Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo, to Dai Nippon Printing Co., Ltd. Receptor layer transfer sheet, thermal transfer sheet, thermal transfer method and apparatus therefor. 5,589,434, Cl. 503-227.000.

Takahashi, Hideki: See—
Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, 5,589,165, Cl. 424-78.030.

Takahashi, Hiroshi, to Eiko Engineering Co., Ltd. Thin film forming device. 5,588,999, Cl. 118-715.000.

Takahashi, Hiroyasu, to International Business Machines Corporation. Bending point extraction method for optical character recognition system. 5,590,220, Cl. 382-203.000.

Takahashi, Hisayoshi: See—
Iwasaki, Shinichiro; Sugiyama, Masanori; Umemura, Chiaki; Oikawa, Akemi; and Takahashi, Hisayoshi, 5,589,752, Cl. 318-701.000.

Takahashi, Kanji: See—
Hamanaka, Nobuyuki; Takahashi, Kanji; and Tokumoto, Hidekado, 5,589,496, Cl. 514-374.000.

Takahashi, Koichi: See—
Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagita, Satoshi; and Baba, Yoshiro, 5,589,421, Cl. 437-225.000.

Takahashi, Koji: See—

Kuwahara, Mitsuo; Isegami, Kiyoshi; Yoshida, Teruaki; Takahashi, Koji; Harada, Tamotsu; Komiya, Takeshi; Hirai, Fumio; and Hayashi, Masamichi, 5,590,388, Cl. 419-39.000.

Oshida, Haruhisa; Okano, Keiji; Kinoshita, Masahide; Takahashi, Koji; Shimizu, Yasushi; and Domon, Akira, 5,589,918, Cl. 399-114.000.

Takahashi, Masahiko; and Tabata, Shusaku, to Asahi Kasei Kogyo Kabushiki Kaisha. Photosensitive resin composition for producing a relief printing plate. 5,589,306, Cl. 430-18.000.

Takahashi, Nobuaki: See—
Tsukamoto, Kazumasa; Ando, Masahiko; Hayahuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, 5,588,927, Cl. 475-128.000.

Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, to Olympus Optical Co., Ltd. Stereoscopic endoscope. 5,588,948, Cl. 600-111.000.

Takahashi, Takehiko: See—
Haruta, Hiroshi; and Takahashi, Takehiko, 5,589,111, Cl. 264-8.000.

Takahashi, Yoshiharu, to Doryokuro Kakunenyō Kaihatsu Jigyodan. Continuous denitrification apparatus. 5,589,140, Cl. 422-159.000.

Takahasi, Kiyosi: See—
Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahasi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, 5,589,263, Cl. 428-336.000.

Takamiya, Makoto: See—
Kadowaki, Hidejiri; Sugiyama, Hiroshi; Ishida, Yasuhiko; and Takamiya, Makoto, 5,589,858, Cl. 347-14.000.

Takara, Hidehiko; Kawanishi, Satoki; and Sawawari, Masatoshi, to Nippon Telegraph and Telephone Corporation. Multiple-frequency-modulation type mode-locked laser device. 5,590,143, Cl. 372-28.000.

Takara Shuzo Co., Ltd.: See—
Okuno, Yoshinobu; Isegawa, Yuji; Sasao, Fuyoko; and Ueda, Shigeharu, 5,589,174, Cl. 424-147.100.

Takashi, Ryuma: See—
Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki, 5,589,270, Cl. 428-411.100.

Takashima, Tadayoshi; Chiba, Takahiro; and Tanaka, Takashi, to Yamamura Glass Co., Ltd. Bottle neck structure and a manufacturing method therefor. 5,588,544, Cl. 215-42.000.

Takasugi, Hidetoshi: See—
Osaka, Keiji; Komiya, Takeo; Asano, Yasuo; Sano, Tomomi; Takasugi, Hidetoshi; and Arimoto, Kazuhiko, 5,590,227, Cl. 385-53.000.

Takata, Hiroshi: See—
Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161.000.

Takata, Inc.: See—
Boumarah, Mohamed; Hurford, Jonathan P.; Collier, William V.; and Lichlyter, Ralph, 5,588,671, Cl. 280-730.200.

Karlow, James P.; Boumarah, Mohamed; and Hurford, Jonathan P., 5,588,672, Cl. 280-730.200.

Takata (Europe) Vehicle Safety Technology GmbH: See—
Kopetzky, Robert; and Häge, Günther, 5,588,677, Cl. 280-806.000.

Takaya, Koetsu: See—
Kogawa, Kuniyuki; and Takaya, Koetsu, 5,589,809, Cl. 337-36.000.

Takayama, Suguru: See—
Shibuya, Giichi; Shibahara, Masanori; Takayama, Suguru; and Usunomiya, Hajime, 5,590,099, Cl. 369-13.000.

Takayama, Toru; and Takemura, Yasuhiko, to Semiconductor Energy Laboratory Co., Ltd. Semiconductor device having a thin film transistor and thin film diode. 5,589,694, Cl. 257-67.000.

Takayanagi, Yasuyuki: See—
Shimizu, Shigeru; Saitoh, Takashi; Uzawa, Masashi; and Takayanagi, Yasuyuki, 5,589,108, Cl. 252-500.000.

Takechi, Kazuo: See—
Uriyu, Katsuhiko; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, 5,589,516, Cl. 514-2.000.

Takeda Chemical Industries, Ltd.: See—
Isobe, Yoshio; Ito, Toshio; and Shibata, Fumio, 5,589,186, Cl. 424-438.000.

Takeda, Harumi, to Takeda Technological Research Co., Ltd. Self-sounding tag alarm. 5,589,819, Cl. 340-571.000.

Takeda, Noriyuki: See—
Taga, Hidenori; Edagawa, Noboru; Takeda, Noriyuki; Yamamoto, Shu; and Akiba, Shigeyuki, 5,589,969, Cl. 359-124.000.

Takeda Technological Research Co., Ltd.: See—
Takeda, Harumi, 5,589,819, Cl. 340-571.000.

Takeda, Yutaka: See—
Kawabata, Hiromi; and Takeda, Yutaka, 5,590,279, Cl. 395-185.060.

Takehara, Takatsugu: See—
Uno, Mikio; Shintaku, Takashi; and Takehara, Takatsugu, 5,589,310, Cl. 430-106.000.

Takei, Hitoshi: See—
Natori, Hiroaki; Takei, Hitoshi; Sano, Shoichi; and Tamuki, Shoichi, 5,589,873, Cl. 348-15.000.

Takeichi, Toru: See—

Kimura, Kazuya; Kayukawa, Hiroaki; Takeichi, Toru; and Hiramatsu, Osamu, 5,588,807, Cl. 417-222.200.

Takemura, Makoto: See—
Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiko; Sato, Masaru; and Morioka, Hisashi, 5,588,757, Cl. 400-279.000.

Takemura, Tetsuya: See—
Kawaguchi, Kenzo; Takemura, Tetsuya; Matsubara, Hideki; Takagi, Sinya; and Kanda, Atsushi, 5,589,429, Cl. 501-96.000.

Takemura, Yasuhiko: See—
Takayama, Toru; and Takemura, Yasuhiko, 5,589,694, Cl. 257-67.000.

Takenaka, Kazuyasu: See—
Tanahashi, Makoto; and Takenaka, Kazuyasu, 5,589,857, Cl. 345-174.000.

Takenouchi, Masanori: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukada, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87.000.

Takeshima, Taku; Noro, Masayuki; and Saito, Tomokatsu, to Fujitsu Limited. Graphic drawing apparatus for generating graphs of implicit functions. 5,590,255, Cl. 395-141.000.

Takeuchi, Akihiko: See—
Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399-350.000.

Takeuchi, Osamu: See—
Ogushi, Masaki; Takeuchi, Osamu; Yamamura, Ikuo; Iura, Toru; and Yoshida, Hironobu, 5,590,150, Cl. 373-9.000.

Takeuchi, Satoshi, to Dai Nippon Printing Co., Ltd. Printing plate and process for preparing the same. 5,589,307, Cl. 430-49.000.

Takeuchi, Toshifumi: See—
Saito, Seiichi; Takeuchi, Toshifumi; Nakamura, Masafumi; Shiokawa, Junji; and Kawamae, Osamu, 5,589,995, Cl. 360-48.000.

Takeyama, Akihiro: See—
Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416.000.

Takezawa, Satoshi; Katagiri, Yoshimichi; Nakamura, Yasushige; and Sawatari, Norio, to Fujitsu, Ltd. Method for nonmagnetic monocomponent development. 5,589,313, Cl. 430-122.000.

Takiguchi, Takao: See—
Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuo, 5,589,103, Cl. 252-299.610.

Takikawa, Yoshihiro: See—
Kataumi, Yoshimasa; and Takikawa, Yoshihiro, 5,588,330, Cl. 74-483.00R.

Takimoto, Hitoshi: See—
Hongo, Kazuya; and Takimoto, Hitoshi, 5,588,991, Cl. 117-2.000.

Takuma, Akira: See—
Morita, Mitsuaki; Miyazaki, Masaya; Enoki, Nobuyuki; and Takuma, Akira, 5,590,340, Cl. 395-750.000.

Talano, John A.; and Hoy, Angela C. Side light for in-line roller skate. 5,588,734, Cl. 362-61.000.

Talamonti, Luciano: See—
Smayling, Michael C.; and Talamonti, Luciano, 5,589,697, Cl. 257-204.000.

Tam, James P., to Vanderbilt University. Litigation of sidechain unprotected peptides via a masked glycolaldehyde ester and O,N-acyl rearrangement. 5,589,356, Cl. 435-68.100.

Tamaki, Yoshiko: See—
Sakakibara, Tadayuki; Tanaka, Teruo; Tamaki, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuhiro, 5,590,353, Cl. 395-800.000.

Tamari, Kousaku, to Toda Kogyo Corporation. Perpendicular magnetic film, process for producing the same and magnetic recording medium having the same. 5,589,261, Cl. 428-332.000.

Tampa G Manufacturing Co.: See—
Showalter, Jerry M., 5,588,690, Cl. 296-77.100.

Tamuki, Shoichi: See—
Natori, Hiroaki; Takei, Hitoshi; Sano, Shoichi; and Tamuki, Shoichi, 5,589,873, Cl. 348-15.000.

Tamura, Hideo: See—
Fujioka, Yasushi; Okabe, Shotaro; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249.000.

Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, to Mitsubishi Jidosha Kogyo Kabushiki Kaisha; and Mitsubishi Denki Kabushiki Kaisha. Air-fuel ratio control method. 5,588,410, Cl. 123-416.000.

Tamura, Kazutoshi: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiko; and Maezawa, Hiroyuki, 5,590,270, Cl. 395-701.000.

Tamura, Richard N.; and Quaranta, Vito, to Scripps Research Institute, The. Integrin alpha subunit cytoplasmic domain polypeptides and methods. 5,589,570, Cl. 530-350.000.

Tamura, Satoshi: See—
Kubo, Takahiro; Suda, Masashi; Murasawa, Yoshihiro; Hasegawa, Takashi; Tamura, Satoshi; Fukushima, Hisashi; and Menjo, Takeshi, 5,589,920, Cl. 399-145.000.

Tanabe, Masanori; Fukui, Hiroshi; Iwakura, Tadayuki; Nakamoto, Kazuhiro; Fuyama, Moriaki; Mitsuoka, Katsuya; Sano, Masaaki; Saito, Makoto; Aihara, Makoto; and Sudo, Shuji, to Hitachi, Ltd. Magnetic disc unit having a plurality of magnetic heads which include multilayer magnetic films. 5,590,008, Cl. 360-126.000.

Tanabe Seiyaku Co., Ltd.: See—
Horikawa, Hiroshi; and Kondo, Kazuhiko, 5,589,592, Cl. 540-204.000.

Tsujihara, Kenji; Hashiyama, Tomiki; Ohashi, Motoaki; and Nakanishi, Noriyuki, 5,589,502, Cl. 514-449.000.

Yamada, Koichiro; Yasuda, Kōsuke; Kikkawa, Kohei; and Kohno, Rikako, 5,589,478, Cl. 514-269.000.

Tanahashi, Makoto; and Takenaka, Kazuyasu, to Sony Corporation. Coordinate input device. 5,589,857, Cl. 345-174.000.

Tanaka, Hideo: See—
Akimoto, Yoshiakira; Tanaka, Hideo; Ogi, Hiromi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, 5,590,243, Cl. 395-23.000.

Tanaka, Hitoshi, to Asahi Kogaku Kogyo Kabushiki Kaisha. Zoom lens barrel. 5,589,987, Cl. 359-701.000.

Tanaka, Kazuna; Kapec, Jeffrey; and Chochinov, Allan B., to Howmedica. Methods and apparatus for mixing bone cement components using an evacuated mixing chamber. 5,588,745, Cl. 366-130.000.

Tanaka, Kazuyuki: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiro; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446.000.

Tanaka, Kikuji: See—
Hanzawa, Kohtaro; Sakata, Goro; and Tanaka, Kikuji, 5,590,364, Cl. 395-800.000.

Tanaka, Kisaburo: See—
Sasaki, Kunimasa; Wakiyama, Youichi; Matsumoto, Takahiro; Tanaka, Kisaburo; and Yamamoto, Keiichi, 5,588,582, Cl. 228-127.000.

Tanaka, Kiyoyuki: See—
Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki, 5,588,555, Cl. 221-197.000.

Tanaka, Koichi, to Kabushiki Kaisha Toshiba. Device for generating structured addresses. 5,590,302, Cl. 395-416.000.

Tanaka, Masakazu: See—
Mori, Hiroshi; Tanaka, Masakazu; Mabuchi, Mamoru; and Saito, Makoto, 5,589,143, Cl. 422-171.000.

Tanaka, Nobuyuki: See—
Yamamura, Yoshitami; Morimoto, Nobuhiko; and Tanaka, Nobuyuki, 5,589,230, Cl. 427-493.000.

Tanaka, Shigeya: See—
Iwamura, Masahiro; Yamauchi, Tatsumi; Tanaka, Shigeya; and Mori, Kazutaka, 5,590,361, Cl. 395-800.000.

Tanaka, Takashi: See—
Takashima, Tadayoshi; Chiba, Takahiro; and Tanaka, Takashi, 5,588,544, Cl. 215-42.000.

Tanaka, Teruo: See—
Sakakibara, Tadayuki; Tanaka, Teruo; Tamaki, Yoshiko; Kitai, Katsuyoshi; and Inagami, Yasuhiro, 5,590,353, Cl. 395-800.000.

Tanaka, Tetsuya: See—
Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seichiro, 5,589,223, Cl. 427-248.100.

Tanaka, Yutaka; and Honda, Minoru, to Nippon Hoso Kyokai. Digital modem for reducing interference in the same channel of another system. 5,590,153, Cl. 375-222.000.

Tandem Computers Incorporated: See—
Rahman, Mizanur M.; Sabernick, Fred C.; Sprouse, Jeff A.; Grosz, Martin J.; Fu, Peter; and Rector, Russell M., 5,590,337, Cl. 395-735.000.

Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., 5,590,274, Cl. 395-182.050.

Tang, Jin: See—
Jones, Simon; and Tang, Jin, 5,589,170, Cl. 424-94.600.

Tang, Pamela S., to Griffith Laboratories Worldwide, Inc. Method of making and using a fat mimetic in reduced fat/cholesterol foodstuffs. 5,589,215, Cl. 426-549.000.

Tang, Wai-Cheung, to COM Dev. Ltd. Multi-mode temperature compensated filters and a method of constructing and compensating therefor. 5,589,807, Cl. 333-212.000.

Tangeman, Michael R.: See—
Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubha G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114.000.

Tani, Edson T.: See—
Schmidt, Christopher G.; Fisher, Michael H.; de Almeida, Amilton F.; and Tani, Edson T., 5,588,731, Cl. 312-405.000.

Tani, Hiroji; and Oshita, Kazuhito, to Murata Manufacturing Co., Ltd. Production of copper powder. 5,588,983, Cl. 75-354.000.

Tanigami, Jorge K.: See—
Lippai, Andre; Tanigami, Jorge K.; and Dellanocce, Paulo T., 5,588,351, Cl. 92-208.000.

Tanigawa, Koichi: See—
Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, 5,589,924, Cl. 399-350.000.

Taniguchi, Naosato: See—

- Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15,000.
- Taoka, Hisao: See—
Akimoto, Yoshiakira; Tanaka, Hideo; Ogi, Hiromi; Izui, Yoshio; Taoka, Hisao; and Sakaguchi, Toshiaki, 5,590,243, Cl. 395-23,000.
- Tapistron International, Inc.: See—
Davis, David L.; Black, Michael J.; Dolf, Richard A.; Gorman, Sean E.; Havard, John M.; and Sigelmann, Milton R., 5,588,383, Cl. 112-80,160.
- Tartaglia, John A. Roller cane to aid the handicapped person in walking and in maneuvering, 5,588,457, Cl. 135-85,000.
- Tarumi, Kazuaki: See—
Bartmann, Ekkehard; and Tarumi, Kazuaki, 5,589,102, Cl. 252-299,010.
- Tashiro, Renki; and Pater, Ruth H. Compositions and method of treating cardio-, cerebro-vascular and alzheimer's diseases and depression, 5,589,182, Cl. 424-423,000.
- Tashiro, Tetsu, to Mitsubishi Denki Kabushiki Kaisha. Serial communication circuit on an LSI chip and communicating with another microcomputer on the chip, 5,590,371, Cl. 395-821,000.
- Tasson, Paul L.: See—
Brugman, James D.; and Tasson, Paul L., 5,588,491, Cl. 166-383,000.
- Tate, Bruce A.: See—
Coskun, Nurcan; and Tate, Bruce A., 5,590,330, Cl. 395-704,000.
- Tate, John O. Chip carrier mounting system, 5,588,847, Cl. 439-71,000.
- Tatsu, Haruyoshi: See—
Saito, Satoru; Tatsu, Haruyoshi; German, Lev S., deceased, 5,589,559, Cl. 526-247,000.
- Taylor, Andrew M.: See—
Rubey, Arthur C., III; Taylor, Andrew M.; and Spears, William E., Jr., 5,588,901, Cl. 451-99,000.
- Taylor, Charles S.; Donlon, Brian S.; and Machold, Timothy R., to Heartport, Inc. Stereoscopic percutaneous visualization system, 5,588,949, Cl. 600-166,000.
- Taylor Group of Companies, Inc.: See—
Taylor, Stephen F., 5,590,207, Cl. 381-90,000.
- Taylor, Harry B.: See—
Poulson, Keith L.; Parker, Robert M.; Samson, Jeffrey T.; and Taylor, Harry B., 5,588,159, Cl. 4-572,100.
- Taylor, James H.: See—
Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127,900.
- Taylor, Lynn P.; le Blanc, Pieter W. J. C.; Butler, Kenneth C.; and Maher, Timothy R., to Nimbus, Inc. Implantable electric axial-flow blood pump, 5,588,812, Cl. 417-356,000.
- Taylor Nathan Co., Inc.: See—
Eckman, Michael G.; and Smallwood, Paul A., 5,588,918, Cl. 473-187,000.
- Taylor, Robert: See—
Levine, Jules D.; Shen, Chi-Cheong; and Taylor, Robert, 5,589,728, Cl. 313-336,000.
- Taylor, Stephen F., to Taylor Group of Companies, Inc. Sound reproducing array processor system, 5,590,207, Cl. 381-90,000.
- Taylor, Thomas J.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kilmeyer, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593,000.
- Tazawa, Masashi; Fujinawa, Nobuhiro; Matsui, Kumiko; and Suzuki, Maki, to Nikon Corporation. Image input system having an auto-feeder including loading magazine and discharge magazine arranged side by side and method, 5,589,953, Cl. 358-498,000.
- Tehao, Michael C.; and Capps, Stephen P., to Apple Computer, Inc. Method for manipulating notes on a computer display, 5,590,256, Cl. 395-787,000.
- TDK Corporation: See—
Fujishiro, Yoshikazu; Ishigaki, Takaya; and Harada, Hiraku, 5,590,016, Cl. 361-313,000.
- Koga, Kenji; Arai, Hitoshi; Kagotani, Tsuneo; and Miyaki, Yousuke, 5,589,297, Cl. 429-212,000.
- Nihira, Yoshito; Zhuang, Haoren; and Nomura, Takeshi, 5,589,097, Cl. 252-62,590.
- Shibuya, Giichi; Shibahara, Masanori; Takayama, Suguru; and Utsunomiya, Hajime, 5,590,099, Cl. 369-13,000.
- TEAC Corporation: See—
Enami, Katsuya; and Miura, Tohru, 5,590,105, Cl. 369-50,000.
- Sakaguchi, Takahiro, and Sakamoto, Fumio, 5,589,722, Cl. 310-180,000.
- Teadt, Donald D.: See—
Osinski, Mark A.; and Teadt, Donald D., 5,588,935, Cl. 477-107,000.
- Tecchio, Piero: See—
Berger, Ernst; Heil, Franz; Schifko, Herbert; and Tecchio, Piero, 5,589,674, Cl. 218-71,000.
- Tech Spray, Inc.: See—
Unruh, Greg R., 5,589,446, Cl. 510-175,000.
- Technology Management, Inc.: See—
Cable, Thomas L.; and Petrik, Michael A., 5,589,285, Cl. 429-13,000.
- Techstrip, Inc.: See—
Pano, Robert; and Traugott, J. Mortimer, 5,589,811, Cl. 338-210,000.
- TECNI-Technische Textilien und Systeme GmbH: See—
Rell, Friedrich, 5,589,245, Cl. 428-85,000.
- Teeri, Teemu: See—
Saarna, Mart; Kelve, Merikke; Truve, Erkki; and Teeri, Teemu, 5,589,625, Cl. 800-205,000.
- Tegeler, John J.: See—
Strupczewski, Joseph T.; Helsley, Grover C.; Glamkowski, Edward J.; Chiang, Yulin; Bordeau, Kenneth J.; Nemoto, Peter A.; and Tegeler, John J., 5,589,494, Cl. 514-37,300.
- Tei, I. Kou: See—
Nakamura, Kazunori; and Tei, I. Kou, 5,589,975, Cl. 359-345,000.
- Teikoku Tsushin Kogyo Co., Ltd.: See—
Inagaki, Jiro; Shinoki, Takashi; and Hari, Atsushi, 5,589,121, Cl. 264-132,000.
- Tektron Micro Electronics, Inc.: See—
Meyn, William C.; and Schneider, Stanley, 5,590,161, Cl. 375-368,000.
- Tektronix, Inc.: See—
Brandt, Thomas J.; and Zimmerman, Stephen A., 5,589,869, Cl. 347-212,000.
- Telecommunication Authority: See—
Lyu, Gap Y.; and Park, Chang S., 5,589,970, Cl. 359-133,000.
- Teledyne Industries, Inc.: See—
Gray, Buddy D., 5,589,066, Cl. 210-258,000.
- Telefonaktiebolaget LM Ericsson: See—
Billström, Lars; Wetterborg, Lars; Dahlin, Steinar; and Persson, Bengt, 5,590,133, Cl. 370-349,000.
- Telegen Corporation: See—
Stevens, Jessica L.; and Crystal, Bonnie, 5,590,182, Cl. 379-130,000.
- Tellam, Mark E.; Brook, Mark G.; Haded, Kevin J.; and Wheeler, Joseph A., to AGFA Division, Bayer Corporation. Scanner drive system having minimum rotational error carriage suspension, 5,589,972, Cl. 359-196,000.
- Tellington, Wentworth J. Floating platform, 5,588,387, Cl. 114-261,000.
- Temper Corporation: See—
Rode, John E., 5,589,664, Cl. 174-52,100.
- Tempered Spring Company Limited, The: See—
Fisher, Ian A.; and Ferdani, Philip, 5,588,209, Cl. 29-897,200.
- Tennent, Howard G.; Barber, James J.; and Hoch, Robert, to Hyperion Catalysis International, Inc. Carbon fibrils, method for producing same and adhesive compositions containing same, 5,589,152, Cl. 423-447,300.
- Tennstedt, Christer: See—
Larsson, Stefan; and Tennstedt, Christer, 5,588,300, Cl. 62-3,610.
- Tepman, Avi; Jinbo, Takeshi; Takahama, Hiroyuki; and Saito, Akihiko, to Applied Materials, Inc. Apparatus for full wafer deposition, 5,589,224, Cl. 427-248,100.
- Terada, Akihiro: See—
Nihel, Ryo; Terada, Akihiro; and Kurebayashi, Hidenori, 5,588,328, Cl. 74-409,000.
- Teraoka, Fuminori: See—
Imai, Keisuke; Kato, Keiichi; Ando, Takayuki; Teraoka, Fuminori; and Matsui, Kenji, 5,588,608, Cl. 242-374,000.
- Tercero, Concepcion P.: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angele; Schoepf, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438,000.
- Terhune, James H., and Gordon, Barry M., to General Electric Company. Stand-alone power supply energized by decay of radioactive isotope, 5,590,162, Cl. 376-320,000.
- Terjung, Herman F.; and Crum, David P. Sleeving machine, 5,588,276, Cl. 53-399,000.
- Terman, Michael; Fairhurst, Stephen; Hughes, Philip; and Levitt, Joel, to Research Foundation For Mental Hygiene, Inc.; and Meda-Light Inc. System for creating naturalistic illumination cycles, 5,589,941, Cl. 315-360,000.
- Terpstra, Robert L.: See—
Anderson, Iver E.; Lograsso, Barbara K.; and Terpstra, Robert L., 5,589,199, Cl. 425-10,000.
- Terrill, Richard S.; and Bielby, Robert R. N., to Altera Corporation. Programming circuits and techniques for programming logic, 5,590,305, Cl. 395-430,000.
- Terry, Charles J.: See—
Kelley, Harold E.; Silvis, William E.; and Terry, Charles J., 5,589,268, Cl. 428-408,000.
- Terumo Kabushiki Kaisha: See—
Kimura, Mitsuteru; and Kudo, Takeshi, 5,589,688, Cl. 250-338,400.
- Teshiba, Sadao: See—
Koizumi, Satoshi; Yonetani, Yoshiyuki; and Teshiba, Sadao, 5,589,355, Cl. 435-66,000.
- Teske, Ernest H.: See—
Lotto, Ronald L.; Teske, Ernest H.; and Hatchell, Peter, 5,588,644, Cl. 271-183,000.
- Tessandier, Alain, to Societe Nouvelle des Ateliers et Chantiers du Harve. Fin with trailing edge fixed flaps for ships, 5,588,391, Cl. 114-284,000.
- Tesser, Mirco: See—
Foscaro, Giancarlo; Tesser, Mirco; Battistella, Mirco; Bergamin, Mirco; and Canil, Gilberto, 5,588,228, Cl. 36-118,200.
- Testo Industry Corp.: See—
Chen, Jacob, 5,588,577, Cl. 227-120,000.
- Tetra Laval Holdings & Finance S.A.: See—
Runnberg, Bo; and Ljungström, Tommy B. G., 5,588,279, Cl. 53-426,000.
- Teutsch, Jean-Georges: See—
Clausner, André; Goubet, François; and Teutsch, Jean-Georges, 5,589,497, Cl. 514-386,000.
- Texas Instruments Incorporated: See—

- Burns, Mark A., 5,589,763, Cl. 324-76,150.
- Gutttag, Karl M.; Balmer, Keith; Gove, Robert J.; Read, Christopher J.; Golston, Jeremiah E.; Poland, Sydney W.; Ing-Simmons, Nicholas; and Moyle, Philip, 5,590,350, Cl. 395-800,000.
- Jeng, Shin-Puu, 5,589,417, Cl. 437-190,000.
- Levine, Jules D.; Shen, Chi-Cheong; and Taylor, Robert, 5,589,728, Cl. 313-336,000.
- Lin, Tsen-Hwang; and Malarcher, Falvey, 5,590,367, Cl. 395-800,000.
- Malhi, Satwinder, 5,589,695, Cl. 257-77,000.
- McCracken, William P.; and Cooper, Neal, 5,589,891, Cl. 348-730,000.
- Ohmart, Dale V.; Benitez, Willie B., III; Marrero, Deogracias D.; and Mirizzi, Douglas J., 5,589,765, Cl. 324-158,100.
- Peterson, Kirk D., 5,589,800, Cl. 330-288,000.
- Phillips, Sabrina D.; and Hellums, James R., 5,589,784, Cl. 327-18,000.
- Pinkham, Raymond; and Balistrieri, Anthony M., 5,590,083, Cl. 365-230,010.
- Russell, Ernest J., 5,589,420, Cl. 437-220,000.
- Smailling, Michael C.; and Talamonti, Luciano, 5,589,697, Cl. 257-204,000.
- Summerfelt, Scott R.; and Beratan, Howard R., 5,589,284, Cl. 428-697,000.
- Thompson, E. Earle; and DeMond, Thomas W., 5,589,852, Cl. 345-147,000.
- Yin, Chenwei J., 5,590,134, Cl. 371-21,500.
- Thai, Cao M.: See—
Kato, Tsuguo; and Thai, Cao M., 5,589,129, Cl. 264-437,000.
- Thayer, John S.; and Ferguson, Patrick L., to Compaq Computer Corporation. Apparatus for aligning and padding data on transfers between devices of different data widths and organizations, 5,590,378, Cl. 395-850,000.
- Thermalloy, Inc.: See—
Clemens, Donald, 5,590,025, Cl. 361-695,000.
- Thévenaz, Armand P., to Whitaker Corporation. The. Curved socket contact, 5,588,867, Cl. 439-381,000.
- Thibodeaux, Louis S.: See—
Moran, Carlos W.; and Thibodeaux, Louis S., 5,590,119, Cl. 370-225,000.
- Thiel, Peter H.: See—
Walters, Nole L.; Raleigh, Edward A.; and Thiel, Peter H., 5,589,675, Cl. 218-140,000.
- Thieler, Stephen M.: See—
Bales, Bruce M.; and Thieler, Stephen M., 5,590,127, Cl. 370-260,000.
- Thiessen, Leo K.: See—
Golino, Carlo M.; Taylor, Thomas J.; Kilmeyer, William H.; Thiessen, Leo K.; and Rude, Carl A., 5,589,536, Cl. 524-593,000.
- Thinking Machines Corporation: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmaul, Bradley C.; Ganmukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200,020.
- Third Quarter Corporation: See—
Voigt, Carl E., IV; and Chow, Cheung K., 5,588,654, Cl. 273-284,000.
- Thomas & Betts Corporation: See—
DeCarlo, David J.; Mineur, Thomas L.; and Stanwick, Ronald S., 5,589,666, Cl. 174-87,000.
- Thomas Industries, Inc.: See—
Kusmer, Raymond J., 5,588,737, Cl. 362-148,000.
- Thomas, James M. C.: See—
Pahno, Demetrios A.; Stolpmann, James R.; and Thomas, James M. C., 5,588,167, Cl. 5-606,000.
- Thomas Jefferson University: See—
Bagasra, Omar; and Pomerantz, Roger J., 5,589,333, Cl. 435-6,000.
- Jameson, Bradford A.; McDonnell, James M.; and Korngold, Robert, 5,589,458, Cl. 514-13,000.
- Thomas, Martin: See—
Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidner, Burghard; Sommermeyer, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560,000.
- Thomas, Ronald E., Jr.: See—
Ignon, Roger G.; and Thomas, Ronald E., Jr., 5,588,153, Cl. 2-457,000.
- Thome, Scott: See—
Seovil, Brian; Berg, Todd A.; Klitz, Kevin; Bachinski, Thomas J.; Humphrey, John W.; Thome, Scott; and Hastings, Roger, 5,588,442, Cl. 128-772,000.
- Thometzek, Peter; and Christ, Heinrich, to Ferro (Italia) S.r.l. Hydrophobic free-flowing pellets, a process for their production and their use, 5,589,222, Cl. 427-215,000.
- Thompson, David D., to Pfizer Inc. Benzo-thiophene estrogen agonists to treat prostatic hyperplasia, 5,589,482, Cl. 514-305,000.
- Thompson, E. Earle; and DeMond, Thomas W., to Texas Instruments Incorporated. Apparatus and method for image projection with pixel intensity control, 5,589,852, Cl. 345-147,000.
- Thompson, Russell M.: See—
Archer, Colin M.; Dilworth, Jonathan R.; Johantputra, Panna; Latham, Ian A.; and Thompson, Russell M., 5,589,576, Cl. 534-14,000.
- Thompson, Stanley P., to Beloit Technologies, Inc. Process for recycling combustion gases in a drying system, 5,588,222, Cl. 34-379,000.
- Thompson, Stephen P.: See—
Morse, Gary J.; and Thompson, Stephen P., 5,590,260, Cl. 395-167,000.
- Thompson, Thomas C.: See—
Abbott, Martyn; and Thompson, Thomas C., 5,588,816, Cl. 417-479,000.
- Thomson Tubes & Displays, S.A.: See—
- Descornbes, Jean-Philippe; and Marotte, Philippe, 5,589,729, Cl. 313-440,000.
- Thomzik, Jürgen: See—
Kindl, Helmut; Hain, Rüdiger; Reif, Hans-Jörg; Stenzel, Klaus; and Thomzik, Jürgen, 5,589,621, Cl. 800-205,000.
- Thorburn, Peter R., to Galison Drilling (Proprietary) Limited. Mounting drill buttons, 5,588,497, Cl. 175-420,100.
- Thornton, Janine M.: See—
Thornton, Michael G.; and Thornton, Janine M., 5,588,535, Cl. 209-38,000.
- Thornton, John; Pool, Stanton J.; and Doll, Dennis R., to American Rug Craftsmen, Inc. Custom fabricated and bordered rug and method and apparatus for forming it, 5,589,027, Cl. 156-304,400.
- Thornton, Michael G.; and Thornton, Janine M., to Synectic Technology, Inc. Sample preparation system for separating wear particles by size and magnetic characteristics, 5,588,535, Cl. 209-38,000.
- Three Bond Co., Ltd.: See—
Hiraoka, Soichiro, 5,589,554, Cl. 525-530,000.
- Thrift, William B.: See—
Khachaturian, Jon E.; and Thrift, William B., 5,589,646, Cl. 73-862,474.
- Tibbets Industries, Inc.: See—
Madaffari, Peter L.; and Collins, James S., 5,589,799, Cl. 330-277,000.
- Tien, Jonathan, to SpaceLabs Medical, Inc. Enhancement of physiological signals using fractal analysis, 5,588,427, Cl. 128-633,000.
- Tigers Polymer Corporation: See—
Ishikawa, Hajime; Ogawa, Masaaki; Hasegawa, Ryosuke; and Yamamoto, Hideo, 5,589,205, Cl. 425-526,000.
- Tikka, Panu; and Kovasin, Kari, to Sunds Defibrator Pori OY. Production of prehydrolyzed pulp, 5,589,033, Cl. 162-84,000.
- Tilch, Werner: See—
Flemming, Eckardt; Tilch, Werner; Schuster, Thomas; Ivanov, Marian; and Eirich, Paul, 5,589,650, Cl. 73-866,000.
- Tiller, Byron K.: See—
Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., 5,590,373, Cl. 395-828,000.
- Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., to Exxon Research and Engineering Company. Process, and apparatus, for the injection of pre-heated oxygen into a high temperature reactor, 5,588,974, Cl. 48-127,900.
- Timsit, Roland S.: See—
Jin, Iljoon; Lloyd, David J.; Timsit, Roland S.; and Lees, Eric R., 5,588,478, Cl. 164-480,000.
- Tipping, John: See—
Dziana, Krzysztof E.; and Tipping, John, 5,588,481, Cl. 165-42,000.
- Tiso, Allan. Pipette tip rack loader, 5,588,792, Cl. 414-404,000.
- Tkach, Peter V.; and Opl, Frank G., to Macro Engineering & Technology Inc. Apparatus for gauge distribution in a tubular plastic film, 5,589,201, Cl. 425-66,000.
- TOA Medical Electronics Co., Ltd.: See—
Kanamori, Shigeo; Aota, Kensaku; Demachi, Takashi; Inoue, Takahiro; and Tanaka, Kiyoyuki, 5,588,555, Cl. 221-197,000.
- Toce, Joseph A., to Reliable Biopharmaceutical Corporation. Sulfated acid amides having anticoagulant properties, 5,589,588, Cl. 536-53,000.
- Tochizawa, Noriaki: See—
Hirotsada, Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, 5,589,315, Cl. 430-163,000.
- Toda Kogyo Corporation: See—
Tamari, Kousaku, 5,589,261, Cl. 428-332,000.
- Toda, Tsuyoshi: See—
Kirino, Fumiyoshi; Maeda, Takeshi; Ide, Hiroshi; Kaku, Toshimitsu; Mita, Seiichi; Shigematsu, Kazuo; and Toda, Tsuyoshi, 5,590,111, Cl. 369-116,000.
- Togano, Takeshi: See—
Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuro, 5,589,103, Cl. 252-299,610.
- Tokai Electronics Co., Ltd.: See—
Imaichi, Hideaki; Matsumoto, Takeshi; Suzuki, Yuji; Himura, Koichi; and Haneda, Tadayoshi, 5,589,251, Cl. 428-209,000.
- Tokai Kogyo Kabushiki Kaisha: See—
Yada, Yukihiko; and Hirai, Yoichi, 5,588,691, Cl. 296-93,000.
- Toko Kabushiki Kaisha: See—
Ohguchi, Yuji, 5,589,884, Cl. 348-405,000.
- Tokuda, Katsuyo: See—
Hirotsada, Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, 5,589,315, Cl. 430-163,000.
- Tokumoto, Hidekado: See—
Hamanaka, Nobuyuki; Takahashi, Kanji; and Tokumoto, Hidekado, 5,589,496, Cl. 514-374,000.
- Tokura, Kunihiko: See—
Uryu, Masaru; Tokura, Kunihiko; Chatani, Ikuro; Mizoguchi, Ikuro; and Ito, Mamoru, 5,590,212, Cl. 381-191,000.
- Tokyo Seat Corporation: See—
Yoshida, Masami; and Okazaki, Hidetsugu, 5,588,697, Cl. 297-173,000.
- Toma, Masaaki: See—
Matsuda, Yoji; Morikawa, Masao; and Toma, Masaaki, 5,589,077, Cl. 210-741,000.

- Tomikawa, Hisao; Matsuo, Hideo; and Fujiwara, Kazuhito, to Tsubakimoto Chain Co. Shock wave sterilizer. 5,588,357, Cl. 99-451,000.
- Tominaga, Hiroyoshi; and Suzuki, Yoshinori, to Shin-Etsu Handotai Co., Ltd. Apparatus for polishing wafers. 5,588,902, Cl. 451-288,000.
- Tominaga, Tetsuo: See—
Nakanishi, Shigeo; Tominaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki. 5,589,491, Cl. 514-338,000.
- Tomofuji, Yoko; Nakase, Makoto; Sato, Takashi; Hazama, Hiroaki; Komano, Haruki; and Ito, Shinichi, to Kabushiki Kaisha Toshiba. Method of fabricating a reticle. 5,589,305, Cl. 430-5,000.
- Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watahe, Masahiro; and Ohki, Kazuhiro, to Canon Kabushiki Kaisha. Variable-angle optical device with optically transparent substance. 5,589,239, Cl. 428-34,000.
- Tomono, Kunisaburo: See—
Konoike, Takehiro; Marusawa, Hiroshi; Takagi, Hiroshi; and Tomono, Kunisaburo. 5,589,096, Cl. 252-62,570.
- Tomozane, Shotaro; Kidou, Hirokazu; and Nakabayashi, Yukikazu, to Suntec Corporation. Shaped glass sheet and a process for the preparation thereof. 5,589,248, Cl. 428-174,000.
- Tomozawa, Hideki: See—
Murai, Fumio; Suzuki, Yasunori; Tomozawa, Hideki; Takashi, Ryuma; Saida, Yoshihiro; and Ikenoue, Yoshiaki. 5,589,270, Cl. 428-411,100.
- Tone, Junsuke: See—
Haxell, Mark A.; Perry, David A.; Maeda, Hiroshi; and Tone, Junsuke. 5,589,366, Cl. 435-119,000.
- Tonelli, Claudio: See—
Simeone, Giovanni; Muna, Fabrizio; Locaspi, Angelo; and Tonelli, Claudio. 5,589,552, Cl. 525-440,000.
- Tongrand Limited: See—
Pan, H. T.; and Chen, Chu-Mei. 5,588,850, Cl. 439-92,000.
- Tomomura, Yukiko; Sakurai, Yoshito; and Nishi, Yumiko, to Hitachi, Ltd. Communication method of supplying information in intelligent network and apparatus therefor. 5,590,180, Cl. 379-112,000.
- Topar, William M. Beverage dispenser. 5,588,557, Cl. 222-54,000.
- Toppan Printing Co., Ltd.: See—
Matsuo, Ryukichi; and Yoshihara, Toshiaki. 5,589,252, Cl. 428-216,000.
- Toray Industries, Inc.: See—
Kobayashi, Masanobu; Itoh, Motoi; Matsuhisa, Yoji; and Shimizu, Kazuharu. 5,589,055, Cl. 205-768,000.
- Sawaoka, Ryuji; Kouchi, Shinji; and Muraki, Toshio. 5,589,523, Cl. 523-211,000.
- Torczynski, Richard M.; and Bollon, Arthur P., to Cytoclonal Pharmaceuticals, Inc. Gene sequence and probe for a marker of non-small cell lung carcinoma. 5,589,579, Cl. 536-23,100.
- Török, Zoltán: See—
Magyar, Kálmán; Gaál, József; Szirák, István; Lengyel, József; Szabó, Anna Z.; Mármárosi, Katalin; Hermecz, István; Szatmári, István; Török, Zoltán; and Körmöczy, Péter. 5,589,513, Cl. 514-654,000.
- Torrington Company, The: See—
Drechsler, Peter H.; and Nishida, Masao. 5,589,138, Cl. 422-108,000.
- Tortelli, Vito: See—
Navarini, Walter; Tortelli, Vito; and Zedda, Alessandro. 5,589,557, Cl. 526-247,000.
- Tortorici, Richard W., Jr., to United States of America, Army. Split wedge/breechblock and sealing means for gun. 5,589,656, Cl. 89-24,000.
- Toshiha America Information Systems, Inc.: See—
Kou, James L. T.; 5,590,376, Cl. 395-839,000.
- Toshiba America MRI, Inc.: See—
Zhang, Weiguo; Kramet, David M.; and Goldhaber, David M.; 5,589,774, Cl. 324-309,000.
- Tosoh, Corporation: See—
Ogata, Yasuhisa; and Kato, Toshikazu. 5,589,524, Cl. 523-212,000.
- Totten, Patty L.: See—
Chatterji, Jiten; Griffith, James E.; Totten, Patty L.; and King, Bobby J.; 5,588,489, Cl. 166-293,000.
- Toutoulet, Guy E. P.: See—
Sabater, Jacques; Toutoulet, Guy E. P.; and Jayet, Gérard. 5,589,941, Cl. 356-376,000.
- Townsend, Peter K., to Berg Technology, Inc. ZIF chip socket. 5,588,861, Cl. 439-342,000.
- Toyama, Makoto; and Asai, Yoshikazu, to Kabushiki Kaisha Komatsu Seisakusho. Method of and apparatus for speed change control. 5,588,515, Cl. 192-4,000.
- Toyama, Masakazu, to Matsushita Electric Industrial Co., Ltd. Vehicle activity measuring apparatus. 5,590,217, Cl. 382-104,000.
- Toyama, Noboru; and Nakagawa, Katsumi, to Canon Kabushiki Kaisha. Method for producing photovoltaic device. 5,589,403, Cl. 437-2,000.
- Toyo Gosei Kogyo Co., Ltd.: See—
Iida, Hirotsada; Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro. 5,589,315, Cl. 430-163,000.
- Toyoda Gosei Co., Ltd.: See—
Okano, Hidenobu; and Watanabe, Katsunori. 5,589,202, Cl. 425-73,000.
- Toyomura, Fumitaka: See—
Itoyama, Shigenori; Fukae, Kimitoshi; Mori, Masahiro; Inoue, Yuji; Toyomura, Fumitaka; and Ohtsuka, Takashi. 5,589,006, Cl. 136-248,000.
- Toyota Jidosha Kabushiki Kaisha: See—
Kono, Katsumi; Nakamura, Shinya; and Honda, Atsushi. 5,588,937, Cl. 477-169,000.
- Mizuno, Hiroyuki; Okamoto, Akio; and Kubo, Suehiro. 5,588,409, Cl. 123-339,110.
- Noguchi, Noboru. 5,588,722, Cl. 303-186,000.
- Osumi, Sadanori; Ogawa, Kiyoshi; Taguchi, Toshifumi; and Haraoka, Mutsumu. 5,588,611, Cl. 242-381,100.
- Takagi, Atsushi. 5,590,251, Cl. 395-131,000.
- Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki. 5,588,927, Cl. 475-128,000.
- Toyota, Takehito: See—
Ishimoto, Masaaki; and Toyota, Takehito. 5,590,394, Cl. 455-6,100.
- Transaction Technology, Inc.: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Siddikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie. 5,589,855, Cl. 345-173,000.
- Traugott, J. Mortimer: See—
Panot, Robert; and Traugott, J. Mortimer. 5,589,811, Cl. 338-210,000.
- Travis, Kristin J.: See—
Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J.; 5,589,189, Cl. 379-356,000.
- Travis, Terrell F.: See—
Shagott, David M.; Kruse, Gary E.; Harber, Blair L., Jr.; Sutherland, Daniel N.; and Travis, Terrell F.; 5,588,985, Cl. 95-25,000.
- Trefonas, Peter, III: See—
Zampini, Anthony; and Trefonas, Peter, III. 5,589,553, Cl. 525-504,000.
- Trethewey, Brig E. A. Removable window shade. 5,588,476, Cl. 160-370,210.
- Treutler, Christoph: See—
Benz, Gerhard; Flik, Gottfried; Treutler, Christoph; and Friedrich, Heinz. 5,588,466, Cl. 137-831,000.
- Tri, Thomas P.: See—
Lashmett, Brent J.; Lashmett, Doug C.; Lashmett, H. W.; Herzog, Larry R.; Tri, Thomas P.; and Karpik, Meredith L.; 5,589,004, Cl. 134-10,000.
- Trice, Jennifer L.: See—
Harms, Michael R.; Foss, Richard J.; Trice, Jennifer L.; and Neavin, Terence D.; 5,589,000, Cl. 118-715,000.
- Trimble, Harold J.; and Darsow, Brian A., to Chevron U.S.A. Inc. Method for extending the life of hydroprocessing catalyst. 5,589,057, Cl. 208-148,000.
- Trimble Navigation Limited: See—
Gildea, David R.; and Banta, Lloyd H.; 5,589,835, Cl. 342-357,000.
- McBurney, Paul W.; 5,590,043, Cl. 364-449,100.
- Trimborn, Peter; and Mugele, Kurt-Willy, to Siemens Aktiengesellschaft. Liquid ring machine and process for operating it. 5,588,806, Cl. 417-68,000.
- Trinetics, Inc.: See—
Walters, Nole L.; Raleigh, Edward A.; and Thiel, Peter H.; 5,589,675, Cl. 218-140,000.
- Trinka, Gerhard: See—
Perner, Johann; and Trinka, Gerhard. 5,588,658, Cl. 280-11,220.
- Triple B Trenching, Inc.: See—
Boes, James A.; Boes, Chad W.; and Boes, Douglas W.; 5,588,659, Cl. 280-47,190.
- Tripp, Victor K.: See—
Wang, Johnson J. H.; and Tripp, Victor K.; 5,589,842, Cl. 343-787,000.
- Tristrata Technology, Inc.: See—
Yu, Rucy J.; and Van Scott, Eugene J.; 5,589,505, Cl. 514-470,000.
- Trojan Technologies Inc.: See—
Maarschalkerweerd, Jan M.; 5,590,390, Cl. 422-186,300.
- Trustle, Jonathan T.: See—
Krajewski, Marjan, Jr.; Chipchak, John C.; Chodornow, David A.; Trustle, Jonathan T.; and Baldwin, Peter T.; 5,590,199, Cl. 380-25,000.
- Trotz, Samuel I.: See—
Geiger, Jon R.; and Trotz, Samuel I.; 5,589,342, Cl. 435-6,000.
- Trumpf Lasertechnik GmbH: See—
von Borstel, Michael. 5,590,146, Cl. 372-58,000.
- Trustees of Columbia University in the City of New York, The: See—
Acampora, Anthony S.; and Naghsineh, Mahmoud. 5,590,125, Cl. 370-397,000.
- Trustees of Tufts College: See—
Levy, Stuart B.; 5,589,470, Cl. 514-154,000.
- Trutan Pty Limited: See—
Martin, Donald L. M.; 5,589,979, Cl. 359-449,000.
- Truve, Erkki: See—
Saarna, Mart; Kelve, Merikke; Truve, Erkki; and Teeri, Teemu. 5,589,625, Cl. 800-205,000.
- TRW Inc.: See—
Foreman, Kevin G.; Miller, Paul J.; and Siska, Steven M.; 5,590,058, Cl. 364-551,010.
- TRW Vehicle Safety Systems Inc.: See—
Emambakhsh, Ali S.; Plonk, Michael P.; Saberan, Ali A.; and Wallner, John P.; 5,588,667, Cl. 280-728,200.
- Emambakhsh, Ali S.; and Stein, Russell E.; 5,588,668, Cl. 280-728,200.
- Gorman, Patrick J.; Yee, Phillip D.; and Gray, Mark F.; 5,588,189, Cl. 24-632,000.
- Trybest Proprietary Limited: See—
Chester, Brian. 5,588,180, Cl. 16-225,000.

- Tsadik, Meir: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tsadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto. 5,590,357, Cl. 395-800,000.
- Tsai, Ming-Chang. Touching feedback device. 5,589,854, Cl. 345-161,000.
- Tsau, Yung-Chun: See—
Castor, Patrick F.; Tsau, Yung-Chun; Kristiansen, Inge B.; and Nelson, John W.; 5,590,288, Cl. 395-200,030.
- Tsaur, Liang S.: See—
Raturise, Florencio; Ahart, Robert; Lang, David J.; and Tsaur, Liang S.; 5,589,370, Cl. 264-4,300.
- Tsubakimoto Chain Co.: See—
Tomikawa, Hisao; Matsuo, Hideo; and Fujiwara, Kazuhito. 5,588,357, Cl. 99-451,000.
- Tsudakoma Kogyo Kabushiki Kaisha: See—
Hashimoto, Seishiro. 5,588,312, Cl. 66-75,200.
- Tsuei, Alexander C.; Kogel, Lorenz, III; and Pendergrass, Daniel B., Jr., to Minnesota Mining and Manufacturing Company. Method of encapsulation and microcapsules produced thereby. 5,589,194, Cl. 424-497,000.
- Tsuji, Masanori; Abe, Kimihito; Sugiyama, Osamu; and Yamamoto, Hiroshi, to Yazaki Corporation. Strand cable press-contacting terminal. 5,588,868, Cl. 439-397,000.
- Tsuji, Tomoko; Yamaguchi, Kohji; Kondo, Kiyosi; and Urakami, Teizi, to Mitsubishi Gas Chemical Company; and Sagami Chemical Research Center. Nerve growth factor production accelerators and compositions for preventing or treating neuronal degeneration. 5,589,481, Cl. 514-287,000.
- Tsuji, Toshiya; and Yahagi, Masahiko, to NEC Corporation. Apparatus and method for mobile communication network which ensures that a user who is out of a service area can receive an incoming call from another service area. 5,590,174, Cl. 379-58,000.
- Tsujihara, Kenji; Hashiyama, Tomiki; Ohashi, Motoaki; and Nakanishi, Noriyuki, to Tanabe Seiyaku Co., Ltd. Baccatin derivatives and processes for preparing the same. 5,589,502, Cl. 514-449,000.
- Tsujioaka, Yuji: See—
Nomura, Toshiyuki; Tsujioaka, Yuji; and Osuga, Naohiro. 5,588,748, Cl. 374-158,000.
- Tsukamoto, Kazumasa; Ando, Masahiko; Hayabuchi, Masahiro; Fukatsu, Akira; Mae, Toshiyuki; Kaigawa, Masato; Fukumura, Kagenori; Oba, Hidehiro; Hojo, Yasuo; Kimura, Hiromichi; Tabata, Atsushi; Hamajima, Tetsuo; and Takahashi, Nobuaki, to Aisin AW Co., Ltd.; and Toyota Jidosha Kabushiki Kaisha. Control system for automatic transmission. 5,588,927, Cl. 475-128,000.
- Tsukamoto, Masahide: See—
Kawakita, Kouji; Tsukamoto, Masahide; Horio, Yasukiho; Nakatani, Seichi; and Hatakeyama, Akihito. 5,588,207, Cl. 29-852,000.
- Tsukazaki, Tomio; and Nakamura, Tsunehisa, to Minnesota Mining and Manufacturing Company. Removable core for pre-stretched tube. 5,589,667, Cl. 174-135,000.
- Tsukii, Michio: See—
Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji. 5,589,962, Cl. 349-46,000.
- Tsukino, Hiroshi: See—
Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiho; and Maezawa, Hiroyuki. 5,590,270, Cl. 395-701,000.
- Tsukuda, Gunji; Naito, Ichiro; Danno, Hirofumi; Tamura, Kazutoshi; Tsukino, Hiroshi; Kamiko, Hideo; Mimura, Hirokazu; Fukuya, Akiho; and Maezawa, Hiroyuki, to Hitachi, Ltd.; Hitachi System Engineering, Ltd.; and Hitachi Software Engineering Co., Ltd. Method and apparatus for detecting a lower level software reusable product in generating an upper level software product from a lower level software product and changing the upper level software product. 5,590,270, Cl. 395-701,000.
- Tsukuda, Keiichi: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenji; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Keiichi; and Sato, Yohei. 5,589,862, Cl. 347-87,000.
- Tsukui, Akimi, to Hitachi Denshi Kabushiki Kaisha. Television camera using two image pickup devices with different sensitivity. 5,589,880, Cl. 348-229,000.
- Tsumiyama, Yoshinori: See—
Maruyama, Haruyoshi; Ogata, Shin; and Tsumiyama, Yoshinori. 5,588,388, Cl. 114-271,000.
- Tsuria, Yossef: See—
Nachman, Jacob B.; and Tsuria, Yossef. 5,590,200, Cl. 380-46,000.
- Tsurufuji, Tomoyoshi: See—
Akiba, Masaru; and Tsurufuji, Tomoyoshi. 5,588,244, Cl. 43-24,000.
- Tsuruoka, Shigeo: See—
Arato, Toshiaki; Aono, Yasuhisa; Tsuruoka, Shigeo; and Komuro, Katsuhiko. 5,589,652, Cl. 75-235,000.
- Tsutsumi, Takayoshi: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenji; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Keiichi; and Sato, Yohei. 5,589,862, Cl. 347-87,000.
- Tulip Corporation: See—
Spiegelberg, Bernard N.; and Sauter, Mark E.; 5,589,294, Cl. 429-178,000.
- Tumer, Nilgun E.: See—
Jilka, Joseph M.; and Tumer, Nilgun E.; 5,589,612, Cl. 800-205,000.
- Turnbull, Robert B.; Travis, Kristin J.; Goszczynski, Piotr T.; McGarry, Susan J.; and Brisebois, Michel J., to Northern Telecom Ltd. Method of operating a microprocessor controlled telephone set. 5,590,189, Cl. 379-356,000.
- Turner, Robert C.: See—
Golio, John M.; Turner, Robert C.; Miller, Monte G.; and Halchin, David J.; 5,590,063, Cl. 364-580,000.
- Turpen, Ann M.: See—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K.; 5,589,367, Cl. 435-172,300.
- Turpen, Thomas H.: See—
Donson, Jon; Dawson, William O.; Grantham, George L.; Turpen, Thomas H.; Turpen, Ann M.; Garger, Stephen J.; and Grill, Laurence K.; 5,589,367, Cl. 435-172,300.
- Tylosky, Gordon. Gas shut-off valve. 5,588,464, Cl. 137-613,000.
- Tzadik, Yehezkel: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itael; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tsadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto. 5,590,357, Cl. 395-800,000.
- Tzori, Yiftach: See—
Willenz, Avigdor; and Tzori, Yiftach. 5,590,310, Cl. 395-473,000.
- Uchida, Makoto; Ihamoto, Masahiko; Sato, Kazuhiko; Kuroiwa, Hiroshi; Ohnishi, Hiroshi; and Minowa, Toshimichi, to Hitachi, Ltd.; and Hitachi Automotive Engineering Co., Ltd. Control apparatus for automatic transmission and control method therefor. 5,588,936, Cl. 477-155,000.
- Uchida, Naoshi; Miura, Masao; Oyama, Jun; Kuboyama, Katsunori; and Asakawa, Koji, to Fuji Electric Co., Ltd. Circuit breaker with arc quenching device and vent. 5,589,672, Cl. 218-34,000.
- Uchikawa, Kiyoshi; Suga, Takayuki; and Furusawa, Akira, to Nikon Corporation. Optical measuring apparatus for measuring physicochemical properties. 5,589,936, Cl. 356-345,000.
- Uchiyama, Takahiro, to Sumitomo Wiring Systems, Ltd. Bulb socket. 5,588,860, Cl. 439-336,000.
- Uclaf, Roussel: See—
Clausner, André; Goubet, François; and Teutsch, Jean-Georges. 5,589,497, Cl. 514-386,000.
- Uda, Hisanori: See—
Sawai, Tetsuro; Uda, Hisanori; Hirai, Toshikazu; Imaoka, Toshikazu; Harada, Yasuo; Honda, Keiichi; and Nishida, Masao. 5,590,412, Cl. 455-82,000.
- Ueba, Yoshinobu: See—
Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu. 5,589,281, Cl. 428-688,000.
- Uebel, Lutz: See—
Richter, Wolfgang-Dieter; Uebel, Lutz; and Weeger, Engelbert. 5,588,368, Cl. 105-199,100.
- Ueberschär, Manfred: See—
Kustermann, Martin; Gonwald, Ingo; and Ueberschär, Manfred. 5,589,659, Cl. 118-413,000.
- Ueda, Hideyuki; Seki, Hiroshi; Kuwahara, Kenji; Murai, Mikio; Takahashi, Kiyosi; Odagiri, Masaru; and Okazaki, Sadayuki, to Matsushita Electric Industrial Co., Ltd. Magnetic recording medium having a ferromagnetic metal thin film, a dry etched layer, a carbonaceous film, and a lubricant film. 5,589,263, Cl. 428-336,000.
- Ueda, Hirohisa: See—
Sano, Hiroshi; Ueda, Hirohisa; Adachi, Rensuke; Ikeda, Kunitoshi; Kaneko, Kunikyo; and Koeda, Takashi. 5,588,950, Cl. 600-178,000.
- Ueda, Hiroyuki, to Mitsubishi Denki Kabushiki Kaisha. Discharging lamp lighting apparatus having optimal lighting control. 5,589,742, Cl. 315-307,000.
- Ueda, Koshi; Goishi, Akira; and Kumbara, Masayuki, to Advantest Corporation. IC Analysis system and electron beam probe system and fault isolation method therefor. 5,589,780, Cl. 324-751,000.
- Ueda, Shigeharu: See—
Okuno, Yoshinobu; Isegawa, Yuji; Sasao, Fuyoko; and Ueda, Shigeharu. 5,589,174, Cl. 424-147,100.
- Uehara, Haruo; and Ikegami, Yasuyuki, to Saga University. Thermal power generator. 5,588,297, Cl. 60-673,000.
- Uehara, Keiichi: See—
Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keiichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi. 5,589,165, Cl. 424-78,030.
- Uehara, Masao: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke. 5,588,948, Cl. 600-111,000.
- Uehara, Nagatoshi, to Clarion Co., Ltd. Information processing apparatus. 5,590,047, Cl. 364-478,020.
- Uematsu, Takashi: See—
Akashi, Ryoji; Morikawa, Takashi; Ninomiya, Masanobu; and Uematsu, Takashi. 5,589,237, Cl. 428-1,000.
- Uemura, Takashi: See—
Okuda, Nobuyuki; Uemura, Takashi; Ueba, Yoshinobu; Tada, Koji; Ohkura, Kengo; and Kugai, Hirokazu. 5,589,281, Cl. 428-688,000.

Ueno, Hitoshi; Kazama, Junichi; Kinoshita, Hirofumi; and Sato, Masaki, to Hitachi, Ltd.; and Hitachi Software Engineering Co., Ltd. Apparatus for sending message via cable between programs and performing automatic operation in response to sent message. 5,590,314, Cl. 395-681.000.

Ueno, Takeshi: See—
Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo, 5,589,434, Cl. 503-227.000.

Uesugi, Akira, to Miyachi Technos Corporation. YAG laser machine with safety system for beam path adjustment. 5,589,089, Cl. 219-121.600.

Uhl, Stefan: See—
Braun, Rüdiger; Arnold, Manfred; Meisel, Thomas; Scherber, Werner; Abersfelder, Günther; and Uhl, Stefan, 5,589,272, Cl. 428-425.600.

Uhlir, George M.; and Mills, George G., to Digital Equipment Corporation. Dynamic microbranching with programmable hold on condition, to programmable dynamic microbranching delay minimization. 5,590,293, Cl. 395-581.000.

Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Keiichiro; and Sato, Yohei, to Canon Kabushiki Kaisha. Liquid storing container for recording apparatus. 5,589,862, Cl. 347-87.000.

Ukawa, Kazuhiro: See—
Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Katsuki; Ukawa, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000.

Ukigaya, Tadashi; and Endoh, Hirotsuka, to Nikken Chemicals Co., Ltd. Slow-release sodium valproate tablets. 5,589,191, Cl. 424-480.000.

Ulbrich, Horst; and Fuhr, Martin, to Benninger AG. Method and device for the accumulation of a yarn overlength between a bobbin creel and the beam on a beaming machine. 5,588,194, Cl. 28-194.000.

Ulbrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Jozef, to Hoechst Aktiengesellschaft. Antifungal polypeptide and process for its production. 5,589,624, Cl. 800-205.000.

Ullrich, Axel; and Vogel, Wolfgang, to Max-Planck-Gesellschaft Zur Förderung Der Wissenschaften E. V. PTP 1D: a novel protein tyrosine phosphatase. 5,589,375, Cl. 435-240.200.

Um, Gregory: See—
Ji, Jeong B.; and Um, Gregory, 5,589,084, Cl. 216-24.000.

Umegaki, Takashi: See—
Sugata, Yoshinobu; Yamazaki, Mikio; and Umegaki, Takashi, 5,589,860, Cl. 347-20.000.

Umekita, Kazuhiro: See—
Kametani, Masatsugu; and Umekita, Kazuhiro, 5,590,030, Cl. 361-794.000.

Umemura, Chiaki: See—
Iwasaki, Shinichiro; Sugiyama, Masanori; Umemura, Chiaki; Oikawa, Akemi; and Takahashi, Hisayoshi, 5,589,752, Cl. 318-701.000.

Umeno, Takaji: See—
Asano, Katsuhiko; Sugai, Masaru; Yamaguchi, Hiroyuki; and Umeno, Takaji, 5,588,721, Cl. 303-163.000.

Umezawa, Yoshiaki: See—
Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, 5,589,711, Cl. 257-718.000.

Unal, Nezih: See—
Reinecke, Holger; Unal, Nezih; Peters, Ralf; Peter, Bartels, Frank; and Noker, Friedolin F., 5,588,597, Cl. 239-553.500.

Undheim, Kjell: See—
Sandnes, Rolf W.; Undheim, Kjell; Gacek, Michel; and Vasilevskis, Janis, 5,589,595, Cl. 540-474.000.

Uniflex, Inc.: See—
Kitamura, Yoshiharu, 5,588,333, Cl. 74-502.400.

Unilever Patent Holdings B.V.: See—
Allen, William D.; Linggood, Margaret A.; and Porter, Philip, 5,589,168, Cl. 424-93.400.

Union Bank of California, N.A.: See—
Sorge, Joseph A.; and Short, Jay M., 5,589,155, Cl. 424-9.200.

Union Carbide Chemicals & Plastics Technology Corporation: See—
Garland, Paul; Schubert, Craig N.; Gregory, Richard A.; Garcia-Rameau, Eduardo; Epps, Rickey; Burns, David; and Hlozek, Robert J., 5,589,149, Cl. 423-242.400.

Ramachandran, Ramesh; and Dinunzi, Sharon A., 5,589,545, Cl. 525-184.000.

Rex, Gary C.; and Atkins, Kenneth E., 5,589,538, Cl. 525-28.000.

Wagner, Burkhard E.; and Ramamurthy, Arakalgud V., 5,589,539, Cl. 525-53.000.

Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P. III; Schwarz, George W. Jr.; and Smith, Cloyd R. III, 5,589,630, Cl. 73-23.350.

Unista Jecs Corporation: See—
Kohayashi, Nobuaki; Kaise, Satoshi; and Kano, Hideki, 5,589,645, Cl. 73-862.335.

Unisys Corporation: See—
Hassler, Joseph A.; Deal, Gregory K.; Koss, Timothy A.; and Heil, Stephen F., 5,590,379, Cl. 395-851.000.

Provenzale, Ronald A., 5,590,027, Cl. 361-732.000.

United Microelectronics Corporation: See—
Yang, Sheng-Hsing; and Sheu, Shing-Ren, 5,589,411, Cl. 437-41.000.

U.S. Industrial Tool and Supply: See—
Peterson, Craig, 5,588,323, Cl. 72-465.000.

United States of America

Air Force: See—
Carlin, Richard T.; and Fuller, Joan, 5,589,291, Cl. 429-103.000.

Army: See—
Brabston, William N.; and Malone, Philip G., 5,588,783, Cl. 405-258.000.

Tortorici, Richard W. Jr., 5,589,656, Cl. 89-24.000.

Health and Human Services: See—
Nielsen, David A.; Goldman, David; Linnoila, Markku; and Virkkunen, Matti, 5,589,331, Cl. 435-6.000.

Parmelee, David C.; and Sechi, Salvatore, 5,589,397, Cl. 436-89.000.

National Aeronautics and Space Administration: See—
Spaulding, Glenn F., 5,589,112, Cl. 264-413.000.

Navy: See—
Brininstool, Michael R., 5,589,937, Cl. 356-352.000.

Jermyn, Richard A., Jr., 5,588,188, Cl. 24-598.700.

Stevens, Bruce W., 5,590,281, Cl. 395-200.010.

U.S. Philips Corporation: See—
Dufour, Yves, 5,590,163, Cl. 377-110.000.

Goossens, Hendrikus M. W., 5,589,739, Cl. 315-176.000.

Hikmet, Rifat A. M., 5,589,959, Cl. 349-88.000.

Hopf, Christian; and Hermann, Hans-Georg, 5,590,000, Cl. 360-96.500.

Klapproth, Peter; Zandveld, Frederik; Bakker, Jacobus M.; and Van Loo, Gerardus C., 5,590,354, Cl. 395-800.000.

Schuur, Cornelis C. M., 5,590,157, Cl. 375-327.000.

Van Berkel, Cornelis H.; Roncken, Maria E.; and Saeijs, Ronald W. J. J., 5,590,275, Cl. 395-183.060.

Van Es, Arthur R.; Van Engelen, Gerard; De Nier, Theodorus H. M.; and Hoefnagels, Johannes F., 5,588,607, Cl. 242-356.300.

Wischermann, Gerhard, 5,589,887, Cl. 348-616.000.

United States Surgical Corporation: See—
Schnut, Robert H.; Robertson, John C.; Gallagher, Richard J.; and Fowler, David N., 5,588,579, Cl. 227-175.100.

U.S. Tape Company, Inc.: See—
Cousins, Michael; Patrick, Douglas; and Bassett, Carol T., 5,588,220, Cl. 33-768.000.

United Technologies Automotive, Inc.: See—
Miller, Robin M., 5,588,754, Cl. 384-609.000.

United Technologies Corporation: See—
Perry, Robert W.; and Goodson, Forrest R., 5,589,660, Cl. 149-18.000.

Unitika Ltd.: See—
Shinzaki, Akihiro; Watanabe, Miwa; and Suzuki, Tadao, 5,589,349, Cl. 435-26.000.

Univ. of California Office of Technology Transfer, The Regents of the: See—
Dunham, Mark E.; and Morley, David W., 5,589,881, Cl. 348-300.000.

Univenture, Inc.: See—
Youngs, Ross O., 5,588,527, Cl. 206-308.100.

Universal Cement & Concrete Products, Inc.: See—
Dongell, Jonathan E., 5,588,990, Cl. 106-716.000.

Université De Neuchâtel: See—
Keppner, Herbert, 5,589,008, Cl. 136-259.000.

Université Louis Pasteur: See—
Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoepf, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.

Universities Research Association, Inc.: See—
Crosetto, Dario B., 5,590,284, Cl. 395-200.050.

University Corporation for Atmospheric Research: See—
Randall, Mitchell A.; and Loew, Eric, 5,589,833, Cl. 342-195.000.

University of Akron, The: See—
Smith, Daniel J.; and Bhat, Shailesh, 5,588,428, Cl. 128-653.100.

University of Alberta, Governors of the: See—
Kostiuk, Larry W.; and Johnson, Matthew R., 5,588,825, Cl. 431-349.000.

University of California, The Regents of the: See—
Lin, Liwei; Nguyen, Clark T.; Howe, Roger T.; and Pisano, Albert P., 5,589,082, Cl. 216-2.000.

McEwan, Thomas E., 5,589,838, Cl. 342-387.000.

Northrup, M. Allen; Mariella, Raymond P. Jr.; Carrano, Anthony V.; and Balch, Joseph W., 5,589,136, Cl. 422-102.000.

Spear, David H.; and Edwards, Peter A., 5,589,368, Cl. 435-172.300.

Stillman, Bruce W.; Bell, Stephen P.; Kobayashi, Ryujii; Rine, Jasper; Foss, Margit; McNally, Francis J.; Laurensen, Patricia; Herskowitz, Ira; Li, Joachim; Gavin, Kimberly; and Hidaka, Masumi, 5,589,341, Cl. 435-6.000.

Wudl, Fred; and Heeger, Alan, 5,589,565, Cl. 528-205.000.

University of Connecticut, The: See—
Gonsalves, Kenneth E., 5,589,011, Cl. 148-334.000.

University of Dayton, The: See—
Lichtenhan, Joseph D.; Vu, Ngo Quang; Gilman, Jeffrey W.; and Feher, Frank J., 5,589,562, Cl. 528-9.000.

University of Florida: See—
Hannah, L. Curtis; and Gironx, Michael, 5,589,618, Cl. 800-205.000.

University of Florida Research Foundation, Inc.: See—
Bova, Frank J.; and Friedman, William A., 5,588,430, Cl. 128-653.100.

University of Hawaii: See—
Bhagavan, Nadhipuram V.; Petersen, Charles E.; and Mandel, Morton, 5,589,338, Cl. 435-6.000.

University of Maryland at Baltimore: See—
Fasano, Alessio; Levine, Myron M.; Nataro, James P.; and Noriega, Fernando, 5,589,380, Cl. 435-252.300.

University of Maryland at College Park: See—

Weiner, Ronald M.; Shi, Juan; and Coyne, Vernon E., 5,589,373, Cl. 435-220.000.

University of Minnesota, Regents of the: See—
Lurie, Keith G.; and Gold, Barbara S., 5,588,422, Cl. 128-200.240.

University of New Mexico: See—
Asgharzadeh, Ali; and Jamshidi, Mohammad, 5,590,246, Cl. 395-109.000.

University of North Carolina at Chapel Hill, The: See—
DeSimone, Joseph M.; Maury, Elise E.; Combes, James R.; and Mence-Ioglu, Yusuf Z., 5,589,105, Cl. 252-351.000.

University of South Florida: See—
Garcia-Rubio, Luis H.; Bayona, Manuel; Potter, Robert; and Leparo, German, 5,589,932, Cl. 356-39.000.

University of Utah Research Foundation: See—
Lalouel, Jean-Marie; Jeunemaitre, Xavier; Lifton, Richard P.; Soubrier, Florent; Kotelevtsev, Yuri; and Corvol, Pierre, 5,589,584, Cl. 536-24.310.

Olivera, Baldomero M.; Cruz, Lourdes J.; Hillyard, David R.; McIntosh, J. Michael; and Santos, Ameurino D., 5,589,340, Cl. 435-6.000.

University of Washington: See—
Ahmad, Suhail; Cole, James J.; and Ahmed, Mahboob, 5,588,959, Cl. 604-6.000.

University Oklahoma, The Board of Regents of the: See—
Fuller, Bryan B., 5,589,161, Cl. 424-59.000.

Uno, Mikio; Shimizu, Takashi; and Takehara, Takatsugu, to Mitsubishi Chemical Corporation. Method for producing toner for developing electrostatic images. 5,589,310, Cl. 430-106.000.

Uno, Toshiyuki; and Kubota, Yasuhiko, to Murata Kikai Kabushiki Kaisha. Package changing system for supplying and discharging loaded and empty packages to and from a machine frame. 5,588,602, Cl. 242-35.50A.

Unosawa, Kazuomi: See—
Yamada, Shuri; Ogawa, Masanori; and Unosawa, Kazuomi, 5,589,225, Cl. 427-212.000.

Unosawa, Yasuhiro; Kanemitsu, Shinji; Kashimura, Makoto; Takemura, Makoto; Kikuchi, Shoji; Matsui, Shinya; Onishi, Toshiyuki; Nitta, Tetsuhiro; Sato, Masaru; and Morioka, Hisashi, to Canon Kabushiki Kaisha. Recording apparatus with detachable magnetic sensor. 5,588,757, Cl. 400-279.000.

Unrein, Ed J.: See—
Eldridge, Robert A.; Unrein, Ed J.; Brown, David L.; and Noble, Scott L., 5,588,728, Cl. 312-332.100.

Unruh, Greg R., to Tech Spray, Inc. Process for removal of ionic salt deposits. 5,589,446, Cl. 510-175.000.

UOP: See—
Zinke, Randy J.; and Koves, William J., 5,589,139, Cl. 422-144.000.

Updike, Dale: See—
Laidig, Jon; Updike, Dale; and Amick, Alan, 5,588,521, Cl. 198-532.000.

Uponor Innovation AB: See—
Järvenkylä, Jyri; Scharwächter, Dieter; Johansson, Åke; and Kristensson, Ronny, 5,589,127, Cl. 264-280.000.

Urakami, Fukashi, to Urakami Research & Development; and Honda Giken Kogyo Kabushiki Kaisha. Surface treating device. 5,588,900, Cl. 451-92.000.

Urakami Research & Development: See—
Urakami, Fukashi, 5,588,900, Cl. 451-92.000.

Urakami, Teizi: See—
Tsuiji, Tomoko; Yamaguchi, Kohji; Kondo, Kiyosi; and Urakami, Teizi, 5,589,481, Cl. 514-287.000.

Urat, Keishi; and Nakamura, Toshiyuki, to Nikon Corporation. Camera which performs motion compensation for sequential photographs by continuously detecting motion until the final photograph is taken. 5,589,904, Cl. 396-55.000.

Urbach, Dieter, to Oeco-Team Unternehmens-und Umweltberatung GmbH. Transport and storage system and applicable support and mounting equipment. 5,588,374, Cl. 108-56.300.

Urban, Martin: See—
Zirps, Wilhelm; Schuller, Wolfgang; and Urban, Martin, 5,588,817, Cl. 417-549.000.

Urella, Richard M.; and Davis, Glen A., to David Clark Company Inc. Headset with adjustable headpad. 5,590,213, Cl. 381-183.000.

Uryu, Katsuhiko; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, to Green Cross Corporation, The. Liquid preparation of antithrombin-III and stabilizing method therefor. 5,589,516, Cl. 514-2.000.

Uryu, Masaru; Tokura, Kunihiko; Chatani, Ikuo; Mizoguchi, Ikuo; and Ito, Mamoru, to Sony Corporation. Diaphragm for a capacitance type loudspeaker. 5,590,212, Cl. 381-191.000.

US Controls Corp.: See—
Hackbart, David G.; Hapke, Kenyon A.; and Schantz, Spencer C., 5,589,671, Cl. 200-6.00R.

Ushiodenka Kabushiki Kaisha: See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, 5,589,735, Cl. 313-638.000.

Ushitora, Akihiro; and Shimizu, Osamu, to Ebara Corporation. Vacuum valve controller for vacuum sewer system. 5,588,458, Cl. 137-205.000.

Utke, Michael C. Light and motion governed garage door opener lamp. 5,589,747, Cl. 318-468.000.

Utsunomiya, Hajime: See—

Shibuya, Giichi; Shibahara, Masanori; Takayama, Suguru; and Utsunomiya, Hajime, 5,590,099, Cl. 369-13.000.

Uwano, Tomoki: See—
Sato, Yukio; Ishizaki, Toshio; Sakaue, Tsuyoshi; Hashimoto, Koji; Yamada, Tohru; and Uwano, Tomoki, 5,589,724, Cl. 310-348.000.

Uyeda, Alan K.: See—
Riley, Rory M.; Uyeda, Alan K.; and Winardi, Michael, 5,588,686, Cl. 292-92.000.

Uytterhoeven, Herman: See—
Defieuw, Geert; Janssens, Wilhelmus; Uytterhoeven, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, 5,589,317, Cl. 430-203.000.

Uzawa, Masashi: See—
Shimizu, Shigeru; Saitoh, Takashi; Uzawa, Masashi; and Takayanagi, Yasuyuki, 5,589,108, Cl. 252-500.000.

V-ONE Corporation: See—
Chen, James F.; and Wang, Jieh-Shan, 5,590,197, Cl. 380-24.000.

Vahne, Anders; Svennerholm, Bo; Rymo, Lars; Jeansson, Stig; and Horal, Peter, to Syntello Vaccine Development KB. Peptides for induction of neutralizing antibodies against human immunodeficiency virus. 5,589,175, Cl. 424-208.100.

Vaisala Oy: See—
Koskinen, Yrjö, 5,589,689, Cl. 250-339.010.

Vaishnavi, Vick; Matthews, Wallace; and Kenny, Patrick, to Cabletron Systems, Inc. Port-link configuration tracking method and apparatus. 5,590,120, Cl. 370-254.000.

Valbuena, Matthew A. Test kit gripping apparatus. 5,589,648, Cl. 73-864.510.

Valdés, Jacobo; and Martínez, Eduardo, to Ductus Incorporated. Multi-level to bi-level raster shape converter. 5,589,851, Cl. 345-136.000.

Valentino, George. Balloon with connected pinwheel. 5,588,897, Cl. 446-217.000.

VALEO Thermique Moteur: See—
Gire, Hélène, 5,588,485, Cl. 165-157.000.

Valeo Vision: See—
Brassier, Marc; Gasquet, Jean-Claude; Segaud, Daniel; and Mauroy, Bernard, 5,589,730, Cl. 313-493.000.

Vallancourt, David G.: See—
Grundvig, Jeffrey P.; and Vallancourt, David G., 5,589,832, Cl. 341-161.000.

Vallet Mas, Alberto; and Gimenez Guasch, Francesc X., to Laboratorios Cusi, S.A. Use of polymeric membranes in the dispensing of pharmaceutical solutions that contain quaternary ammonium compounds as preservatives and corresponding dose dispenser. 5,588,559, Cl. 222-92.000.

Valmet Corporation: See—
Koskinen, Jukka, 5,588,998, Cl. 118-410.000.

Valpey, Richard S., III; Yokoyama, Thomas W.; Kraan, John D.; and Harwood, H. James, to Sherwin-Williams Company, The. Curable compositions incorporating anhydride-functional polymers derived from alkenyl succinic anhydride. 5,589,560, Cl. 526-271.000.

Van-Bar Enterprises, Inc.: See—
Cox, Vance; and Cox, Barbara, 5,588,558, Cl. 222-64.000.

Van Beersel, Jozef; and John, Robin C., to NV Raychem SA. Method for applying covering material to an elongate substrate. 5,589,019, Cl. 156-184.000.

Van Berkel, Cornelis H.; Roncken, Maria E.; and Saeijs, Ronald W. J. J., to U.S. Philips Corporation. Method for testing an integrated circuitry and an integrated circuit having a plurality of functional components and having junction/switch test components in interconnecting channels between functional components. 5,590,275, Cl. 395-183.060.

VanBrunt, Nicholas: See—
Graham, Gary A.; Jacobs, Merrit N.; Marvin, Russel H.; Shaw, James D.; and VanBrunt, Nicholas, 5,588,946, Cl. 494-11.000.

Vance, Joseph E. Fishing lure protective container. 5,588,245, Cl. 43-25.200.

Vandekerckhove, Joël: See—
De Clercq, Ann; Krebbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205.000.

Van den Bogaert, Jan: See—
Defieuw, Geert; Janssens, Wilhelmus; Uytterhoeven, Herman; Horsten, Bart; Dewanckele, Jean-Marie; and Van den Bogaert, Jan, 5,589,317, Cl. 430-203.000.

Vanderbilt University: See—
Tam, James P., 5,589,356, Cl. 435-68.100.

van der Griendt, Adrianus J.: See—
Bedi, Ram D.; and van der Griendt, Adrianus J., 5,588,502, Cl. 184-1.500.

van der Linden, Robbert: See—
Skarpelos, Michael J.; van der Linden, Robbert; Carley, William J.; Lyon, James M.; and McCline, Matthew C., 5,590,274, Cl. 395-182.050.

Van Dyke, Korbin S.: See—
Sowadsky, Elliot A.; Widigen, Larry; Puziol, David L.; and Van Dyke, Korbin S., 5,590,351, Cl. 395-800.000.

Van Engelen, Gerard: See—
Van Es, Arthur R.; Van Engelen, Gerard; De Nier, Theodorus H. M.; and Hoefnagels, Johannes F., 5,588,607, Cl. 242-356.300.

Van Es, Arthur R.; Van Engelen, Gerard; De Nier, Theodorus H. M.; and Hoefnagels, Johannes F., to U.S. Philips Corporation. Apparatus with a drive arrangement of information carriers in the form of tapes. 5,588,607, Cl. 242-356.300.

Van Havenbergh, Jan: See—

- De Jaeger, Nikolaas; Damen, Guy; Winter, Gerhard; and Van Havenbergh, Jan, 5,589,048, Cl. 204-489,000.
- van Koetsem, Jan P. K.: See—
- Morlion, Danny; Jonckheere, Luc; and van Koetsem, Jan P. K., 5,588,851, Cl. 439-108,000.
- Van Loo, Gerardus C.: See—
- Klapproth, Peter; Zandveld, Frederik; Bakker, Jacobus M.; and Van Loo, Gerardus C., 5,590,354, Cl. 395-800,000.
- Vanmaele, Luc, to Agfa-Gevaert N.V. Dyes and dye-donor elements for thermal dye transfer recording, 5,589,316, Cl. 430-200,000.
- Van Matre, James V.: See—
- Chapman, Gordon R.; Andruik, Donald R.; Van Matre, James V.; Stenzel, Andre; Logan, Robert J.; McCrory, Edwin D.; Singleton, Michael W.; and Richmond, Robert M., 5,589,073, Cl. 210-704,000.
- Van Montagu, Marc: See—
- De Clercq, Ann; Krebbers, Enno; Vandekerckhove, Joël; Barreto De Castro, Luiz; Gander, Eugen; and Van Montagu, Marc, 5,589,615, Cl. 800-205,000.
- Van Scott, Eugene J.: See—
- Yu, Ruey J.; and Van Scott, Eugene J., 5,589,505, Cl. 514-470,000.
- Van Trump, Gary N.: See—
- Lester, Lester J.; and Van Trump, Gary N., 5,588,858, Cl. 439-275,000.
- van Wingerde, Mario M. M.: See—
- Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., 5,589,534, Cl. 524-548,000.
- Varco Shaffer, Inc.: See—
- Brugman, James D.; and Tasson, Paul L., 5,588,491, Cl. 166-383,000.
- Varghese, Alexander P., to Air Products and Chemicals, Inc. Apparatus for insulating cryogenic devices, 5,589,020, Cl. 156-185,000.
- Varni, Anselm F.: See—
- Goldman, Robert P.; Arah-Sadeghabadi, Akhar; and Varni, Anselm F., 5,590,229, Cl. 385-59,000.
- Vasilevskis, Janis: See—
- Sandnes, Rolf W.; Undheim, Kjell; Gacek, Michel; and Vasilevskis, Janis, 5,589,595, Cl. 540-474,000.
- Vassiliadis, Stamatis: See—
- Phillips, James E.; Blauer, Bartholomew; and Vassiliadis, Stamatis, 5,590,348, Cl. 395-564,000.
- Vassiliou, Eustathios. Methods for coating egg yolks and other articles, 5,589,208, Cl. 426-89,000.
- Vassiliou, Eustathios. Method for making artificial egg yolks in the form of a cylinder, 5,589,218, Cl. 426-614,000.
- Vasumathy, Rangarajan: See—
- Naik, Ramachandra G.; Mumbaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Aftab D.; Shrole, Mandakini V.; Lal, Bansi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681,000.
- Vaughn, William A.: See—
- Venkataramani, Edamanal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., 5,589,691, Cl. 252-182,110.
- VAW Aluminum AG: See—
- Davis, Howard P.; and Ruff, Wolfram, 5,588,986, Cl. 95-211,000.
- Veale, Chris A.: See—
- Shenvi, Ashokkumar B.; Jacobs, Robert T.; Miller, Scott C.; Ohnmacht, Cyrus J., Jr.; and Veale, Chris A., 5,589,489, Cl. 514-323,000.
- Vector Magnetics, Inc.: See—
- Kueckes, Arthur F., 5,589,775, Cl. 324-346,000.
- Vehar, Gordon A.: See—
- O'Brien, Donogh P.; Vehar, Gordon A.; and Wilcox, Josiah N., 5,589,173, Cl. 424-145,100.
- Roy, Soumitra; and Vehar, Gordon A., 5,589,363, Cl. 435-69,600.
- Vela de Casillas, Martha L.: See—
- Berger, H. Stephen; Vela de Casillas, Martha L.; and Cochrane, Harry L., 5,589,773, Cl. 324-261,000.
- Velander, William H.: See—
- Drohan, William N.; Wilkins, Tracy D.; Velander, William H.; and Johnson, John L., 5,589,604, Cl. 800-2,000.
- Veltrop, Robert: See—
- Barnes, Michael; Benjamin, Neil; Holland, John; Beer, Richard; and Veltrop, Robert, 5,589,737, Cl. 315-111,210.
- Vendoret Holding S. A.: See—
- Merchel, Horst, 5,589,677, Cl. 235-383,000.
- Venet, Marc G.; Guillemont, Jérôme E. G.; Vernier, Daniel F. J.; and Odds, Frank C., to Janssen Pharmaceutica N.V. 4-quinoliny derivatives, 5,589,484, Cl. 514-314,000.
- Venkataramani, Edamanal S.; Forman, Andrew L.; Magliette, Ralph J., Jr.; Vaughn, William A.; and Dauer, Richard R., to Merck & Co., Inc. Process for recovery and recycle of methanesulfonic acid and phosphorous acid, 5,589,691, Cl. 252-182,110.
- Ventrudo, Brian F.; and Berrang, Peter G., to SDI, Inc. Multiple diode lasers stabilized with a fiber grating, 5,589,684, Cl. 250-225,000.
- Venturini, Andrea: See—
- D'Agaro, Amos; Marino, Adriano; and Venturini, Andrea, 5,588,727, Cl. 312-283,000.
- Verbo, Ulysse: See—
- Gautier, Jean Pierre; Verbo, Ulysse; and Perez Revilla, Miguel, 5,588,346, Cl. 91-369,002.
- Gautier, Jean-Pierre; Verbo, Ulysse; and Gebauer, Maurice, 5,588,349, Cl. 92-169,300.
- Vercande, David J.: See—
- Hogan, Steven J.; Feltz, Kristi T.; Murdock, Douglas R.; Goodman, Todd A.; Vercande, David J.; Tangeman, Michael R.; Busch, Eric M.; Kripakaran, Raghavan; Jayasimha, Madhigubba G.; Smith, Keith E.; Austin, Mark A.; and Berry, Dana B., 5,590,181, Cl. 379-114,000.
- Verini, Nicholas A. Apparatus and method to intermittently manufacture and dispense nitrogen, 5,588,984, Cl. 95-15,000.
- Vermeer Manufacturing Company: See—
- Cooper, Mark R., 5,590,041, Cl. 364-424,051.
- Egging, Philip J., 5,588,474, Cl. 144-24,120.
- Vernier, Daniel F. J.: See—
- Venet, Marc G.; Guillemont, Jérôme E. G.; Vernier, Daniel F. J.; and Odds, Frank C., 5,589,484, Cl. 514-314,000.
- Verrier, Guy E.: See—
- Stein, Frank L.; and Verrier, Guy E., 5,589,856, Cl. 345-173,000.
- Versabar, Inc.: See—
- Khachaturian, Jon E.; and Thrift, William B., 5,589,646, Cl. 73-862,474.
- Verrucci, Nicholas: See—
- Allen, Harvey S., II; Berke, E. William; and Erwin, Gary B., 5,588,398, Cl. 119-822,000.
- Veser, Alwin: See—
- Rudolph, Bernd; and Veser, Alwin, 5,589,740, Cl. 315-291,000.
- Vetter, Gerhard; and Markert, Eberhard, to Michael Horat Maschinenfabrik GmbH & Co. KG. Device for transporting yarn with a central mast, 5,588,604, Cl. 242-47,050.
- Vetter, Stephan M.; and Parisi, Mark J., to General Motors Corporation. Centrifugal impeller with simplified manufacture, 5,588,803, Cl. 416-186,000.
- Viano, David C.; Jedrzeczek, Edward A.; and Smrcka, Joseph G., to First Technology Safety Systems, Inc. Lower leg for crash test dummy, 5,589,651, Cl. 73-866,400.
- Vical Incorporated: See—
- Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44,000.
- Vice, Susan F. Diindole compounds and pharmaceutical compositions containing them, 5,589,472, Cl. 514-183,000.
- Vichnevskaya, Klara D.; Blake, Terence J.; Bevilacqua, Eddie; and Boyle, Timothy J. B. Method of using 5-hydroxybenzimidazole compounds for reducing transpiration in plants, 5,589,437, Cl. 504-225,000.
- Vickery, Brian H.: See—
- Kristenansky, John L.; Nestor, John J., Jr.; Ho, Teresa H.; Vickery, Brian H.; and Bach, Chinh T., 5,589,452, Cl. 514-12,000.
- Vidamed, Inc.: See—
- Edwards, Stuart D.; Lax, Ronald G.; and Sharkey, Hugh R., 5,588,960, Cl. 604-20,000.
- Videoconferencing Systems, Inc.: See—
- Cortjens, Leo M.; Franklin, Kenneth A.; Mays, Richard C.; and Smith, Curtis M., 5,589,878, Cl. 348-211,000.
- Videojet Systems International, Inc.: See—
- Janse Van Rensburg, Richard W.; and Keep, Peter R., 5,589,863, Cl. 347-75,000.
- Vijn, Jan P.; Xenakis, Zacharias; Bour, Daniel L.; and Childs, Jerry D., to Halliburton Company. Cementing multi-lateral wells, 5,588,488, Cl. 166-293,000.
- Vilimur, Richard J.; and Bruckert, Eugene J., to Motorola, Inc. Method for preventing a dropped call during a handoff in a radiotelephone system, 5,590,177, Cl. 379-60,000.
- Viner, Omri: See—
- Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Han; Fraenkel, Itiel; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachim; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
- Virginia Intellectual Property Division: See—
- Drohan, William N.; Wilkins, Tracy D.; Velander, William H.; and Johnson, John L., 5,589,604, Cl. 800-2,000.
- Virkkunen, Matti: See—
- Nielsen, David A.; Goldman, David; Linnoila, Markku; and Virkkunen, Matti, 5,589,331, Cl. 435-6,000.
- Virmig, Alex J.: See—
- Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sulikman, Paul; Virmig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173,000.
- Visocky, Joseph E.; and Evans, Everett; to Everbrite, Inc. Sign comprised of a carrier frame and manually arrangeable modular information grids and pictorials, 5,588,238, Cl. 40-618,000.
- Vittenberg, Michael: See—
- Spector, Yechiel; Jacobson, Esther; Naishut, Vida; Vittenberg, Michael; and Beinert, Zohar, 5,588,493, Cl. 169-46,000.
- Vogel, Wolfgang: See—
- Ullrich, Axel; and Vogel, Wolfgang, 5,589,375, Cl. 435-240,200.
- Vogt, Carl R.: See—
- Warren, James D.; Vogt, Carl R.; and Kloss, Charles D., 5,590,026, Cl. 361-704,000.
- Voigt, Carl E., IV; and Chow, Cheung K., to Third Quarter Corporation. Game playing apparatus, 5,588,654, Cl. 273-284,000.
- Volkert, Andrew M.: See—
- Volkert, Carolyn K.; and Volkert, Andrew M., 5,588,233, Cl. 40-124,100.

- Volkert, Carolyn K.; and Volkert, Andrew M., to Volkert, Inc. Paper product and method of making, 5,588,233, Cl. 40-124,100.
- Volkert, Inc.: See—
- Volkert, Carolyn K.; and Volkert, Andrew M., 5,588,233, Cl. 40-124,100.
- Volz, Keith L.: See—
- Irlbeck, Robert D.; Bates, Warren A.; Dumas, Robert; and Volz, Keith L., 5,588,846, Cl. 439-66,000.
- von Borstel, Michael, to Trumpf Lasertechnik GmbH. Gas laser, 5,590,146, Cl. 372-58,000.
- von Essen, Mathias; Bollig, Christoph; and Bick, Werner, to FEV Motoren-technik GmbH & Co. KG. Reciprocating piston engine with weight compensation, 5,588,407, Cl. 123-192,200.
- Vonk, Donald R.; and Greene, Jeffrey A., to PPG Industries, Inc. Zinc phosphate coating compositions containing oxime accelerators, 5,588,989, Cl. 106-14,120.
- Voorman, Johannes O.: See—
- Davis, Bradley K.; Voorman, Johannes O.; Ramalho, Joao N. V. L.; and Gamand, Patrice, 5,589,777, Cl. 324-537,000.
- Vormwald, Helmut: See—
- Scannell, Robert; Busse, Bernd; and Vormwald, Helmut, 5,589,044, Cl. 204-286,000.
- Vry, Uwe: See—
- Lücke, Christian; Vry, Uwe; and Lemcke, Ulrich, 5,589,977, Cl. 359-375,000.
- Vu, Ngo Quang: See—
- Lichtenhan, Joseph D.; Vu, Ngo Quang; Gilman, Jeffrey W.; and Fehér, Frank J., 5,589,562, Cl. 528-9,000.
- Wachendorff-Neumann, Ulrike: See—
- Fischer, Reiner; Krüger, Bernd-Wieland; Bretschneider, Thomas; Erdelen, Christoph; Wachendorff-Neumann, Ulrike; Lürssen, Klaus; Santel, Hans-Joachim; and Schmidt, Robert R., 5,589,469, Cl. 514-91,000.
- Wada, Hiroaki: See—
- Kojima, Shoichi; Minagawa, Kazuhiro; Kano, Haruyuki; Miyazaki, Tadaaki; and Wada, Hiroaki, 5,589,116, Cl. 264-65,000.
- Wada, Katsuaki: See—
- Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Katsuaki; Ukawa, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261,000.
- Wada, Yumiko: See—
- Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,590,510, Cl. 514-590,000.
- Wagner, Burkhard E.; and Ramamurthy, Arakalgud V., to Union Carbide Chemicals & Plastics Technology Corporation. Process for preparing an in situ polyethylene blend, 5,589,539, Cl. 525-53,000.
- Wagner, Edmund, to Zorbedo GmbH. Prefabricated construction system for a timber house, 5,588,269, Cl. 52-270,000.
- Wagner, Philip C.: See—
- DiFlora, Michael A.; Pandeva, Prakash N.; Robinson, Christopher S.; and Wagner, Philip C., 5,588,810, Cl. 417-312,000.
- Wakamatsu, Hiroaki: See—
- Kiuchi, Katsumi; Wakamatsu, Hiroaki; Suzuki, Fumitake; and Koshikawa, Takao, 5,589,262, Cl. 428-336,000.
- Wakiyama, Youichi: See—
- Sasaki, Kunimasa; Wakiyama, Youichi; Matsumoto, Takahiro; Tanaka, Kisaburo; and Yamamoto, Keiichi, 5,588,582, Cl. 228-127,000.
- Wales, Alan C. D., to Eljay Electrical Manufacturing Company Limited. Earthed cable gland, 5,589,663, Cl. 174-51,000.
- Walker, Carl E.: See—
- Daly, John J.; Haisch, Herman F.; Kapsales, Peter; Krishnamurthy, Bala; Miska, Richard A.; Nordgaard, Joseph K.; and Walker, Carl E., 5,590,405, Cl. 455-54,100.
- Walker, James A.: See—
- Cunningham, John E.; Goossen, Keith W.; Jan, William Y.; Pathak, Rajiv N.; and Walker, James A., 5,589,404, Cl. 437-5,000.
- Goossen, Keith W.; and Walker, James A., 5,589,974, Cl. 359-290,000.
- Wallace Computer Services, Inc.: See—
- Garrison, Ronald R., 5,589,025, Cl. 156-268,000.
- Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heiti, Robert V.; and Yoshida, Yuko, to Minnesota Mining and Manufacturing Company. Magnetic recording medium having an embossed back-coat layer, 5,589,247, Cl. 428-141,000.
- Walling, Priscilla: See—
- Neill, Paul; Brandt, Lorelei; Walling, Priscilla; Nandagiri, Arun; and Meltzer, Norman, 5,589,163, Cl. 424-70,510.
- Wallis, Frank S., to Copeland Corporation. Compliant drive for scroll machine, 5,588,819, Cl. 418-39,000.
- Wallner, John P.: See—
- Emambakhsh, Al S.; Pionk, Michael P.; Saberan, Al A.; and Wallner, John P., 5,588,667, Cl. 280-728,200.
- Walsh, Eileen B., to General Electric Company. Stabilization of low molecular weight polybutylene terephthalate/polyester blends with phosphorus compounds, 5,589,530, Cl. 524-152,000.
- Walt Disney Company, The: See—
- Adamczyk, John W., 5,588,914, Cl. 463-32,000.
- Walters, Nole L.; Raleigh, Edward A.; and Thiel, Peter H., to Trinetics, Inc. Vacuum switch, 5,589,675, Cl. 218-140,000.
- Walz, Gerd: See—
- Schwab, Michael; Walz, Gerd; and Merten, Gerhard, 5,589,535, Cl. 524-591,000.
- Wan, Kam H.: See—
- Bahadur, Birendra; and Wan, Kam H., 5,589,965, Cl. 349-165,000.
- Wandel & Goltermann Technologies, Inc.: See—
- Anderson, Bradley T., 5,590,159, Cl. 375-340,000.
- Zhang, Jing, 5,590,116, Cl. 370-253,000.
- Wang, Ge: See—
- Rapp, Robert A.; Wang, Ge; and Pangestuti, Endang, 5,589,220, Cl. 427-126,100.
- Wang, Jieh-Shan: See—
- Chen, James F.; and Wang, Jieh-Shan, 5,590,197, Cl. 380-24,000.
- Wang, Johnson J. H.; and Tripp, Victor K., to Georgia Tech Research Corporation. Compact microstrip antenna with magnetic substrate, 5,589,842, Cl. 343-787,000.
- Wang, Yi-Min: See—
- Fuchs, Wesley K.; Huang, Yennun; and Wang, Yi-Min, 5,590,277, Cl. 395-183,140.
- Wang, Yun: See—
- Lin, Eileen T.; and Wang, Yun, 5,590,321, Cl. 395-610,000.
- Wann, Yeh-Jye; and Liu, Hsien-Tsong, to Taiwan Semiconductor Manufacturing Company Ltd. Method of making mask ROM with two layer gate electrode, 5,589,414, Cl. 437-44,000.
- Ward, Robert S.; and White, Kathleen A., to Polymer Technology Group, The. Surface-modifying endgroups for biomedical polymers, 5,589,563, Cl. 528-44,000.
- Warfield, Robert W.: See—
- Anderson, Charles R.; Warfield, Robert W.; Cseri, Istvan; Low, Murray K.; Liaw, Weikuo; and Bush, Alan M., 5,590,259, Cl. 395-764,000.
- Warner, Gregory L.: See—
- Guggenheim, Thomas L.; Fukuyama, Sharon M.; and Warner, Gregory L., 5,589,037, Cl. 203-35,000.
- Warren, James D.; Vogt, Carl R.; and Klooz, Charles D., to Borg-Warner Automotive, Inc. Apparatus for dissipating heat from an integrated circuit, 5,590,026, Cl. 361-704,000.
- Warthmann, Wolfgang: See—
- Klink, Rainer; German, Johann; and Warthmann, Wolfgang, 5,589,290, Cl. 429-99,000.
- Warwick, Dennis J.: See—
- Nubson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700,000.
- Watabe, Masahiro: See—
- Tomono, Haruo; Kobayashi, Naoki; Nakajima, Toshiyuki; Kai, Takashi; Sekine, Masayoshi; Watabe, Masahiro; and Ohki, Kazuhiro, 5,589,239, Cl. 428-34,000.
- Watahiki, Satoshi; and Shirakawa, Shingo, to Hitachi, Ltd. Arrangement of arrestors in a gas-insulated switchgear, 5,590,018, Cl. 361-612,000.
- Watanabe, Eiji: See—
- Katou, Kouichi; Watanabe, Eiji; and Kunimune, Kouichi, 5,589,319, Cl. 430-288,100.
- Watanabe, Haruo: See—
- Ata, Masafumi; Machida, Masataka; and Watanabe, Haruo, 5,589,038, Cl. 204-157,420.
- Watanabe, Hideyuki, to Ricoh Company, Ltd. γ -correction curve selecting apparatus and a γ -correction curve creating apparatus, 5,589,954, Cl. 358-518,000.
- Watanabe, Hiroshi, to Kabushiki Kaisha Toshiba. Method and an apparatus for resetting an information recording apparatus, 5,590,280, Cl. 395-185,080.
- Watanabe, Hitoshi: See—
- Ookawa, Eiichi; Nishida, Hiroto; Suzuki, Takashi; Watanabe, Hitoshi; and Sasaki, Toshiaki, 5,590,109, Cl. 369-77,200.
- Watanabe, Isao: See—
- Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Naura, William S.; and McKinley, Gareth H., 5,588,509, Cl. 188-267,000.
- Watanabe, Katsunori: See—
- Okano, Hidenobu; and Watanabe, Katsunori, 5,589,202, Cl. 425-73,000.
- Watanabe, Kazuyuki; and Iwamoto, Satoshi, to Showa Denko K.K. Polyolefin composition, molded article thereof and multilayered laminate, 5,589,547, Cl. 525-240,000.
- Watanabe, Kenjiro: See—
- Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87,000.
- Watanabe, Masaharu: See—
- Iida, Hirotada; Tochizawa, Noriaki; Kuniyoshi, Yasuo; Watanabe, Masaharu; Tokuda, Katsuyo; and Hozumi, Ichiro, 5,589,315, Cl. 430-163,000.
- Watanabe, Masato: See—
- Ishihara, Manabu; Rakuma, Tsuyoshi; Kanai, Hiroshi; Fudo, Takashi; and Watanabe, Masato, 5,588,589, Cl. 236-46,000.
- Watanabe, Michi: See—
- Sugawara, Takahiro; Watanabe, Michi; Sumitani, Naoko; Shirasaki, Miwa; and Suzuki, Toshiaki, 5,589,517, Cl. 521-33,000.
- Watanabe, Mikio; Aoki, Akira; and Saito, Osamu, to Fuji Photo Film Co., Ltd. Memory card management system for writing data with usage and recording codes made significant, 5,590,306, Cl. 395-442,000.
- Watanabe, Miwa: See—

- Shinzaki, Akihiro; Watanabe, Miwa; and Suzuki, Tadao, 5,589,349, Cl. 435-26.000.
- Watanabe, Nobuatsu; Chong, Yong-Bo; and Matsumura, Sowjun, to Watanabe, Nobuatsu; Chong, Yong-Bo; and C. Uyemura & Co. Fluorine compound - containing composite material and method of preparing same. 5,589,271, Cl. 428-421.000.
- Watanabe, Ryo: See—
- Goto, Toshio; Moriya, Koichi; Maurer, Fritz; Ito, Seishi; Wada, Katsuki; Ukawa, Kazuhiro; Watanabe, Ryo; Ito, Asami; and Minegishi, Natsuko, 5,589,439, Cl. 504-261.000.
- Watanabe, Teruo: See—
- Omodaka, Koji; Hiraga, Katsuya; Kobori, Yoichi; Sakurada, Hiroshi; Watanabe, Teruo; and Itoh, Shigeo, 5,589,738, Cl. 315-169.100.
- Watanabe, Toyofumi: See—
- Yoshimi, Naoto; Watanabe, Toyofumi; and Yamashita, Masaaki, 5,589,279, Cl. 428-623.000.
- Watarai, Shu: See—
- Horie, Seiji; Sano, Kenji; Suzuki, Nobuo; and Watarai, Shu, 5,589,312, Cl. 430-115.000.
- Watson, Donald D.: See—
- Hultman, David P.; Watson, Donald D.; and Heribacka, Edward W., 5,589,034, Cl. 162-111.000.
- Waydelis, Ronald A.: See—
- Licht, Thomas H.; Cuatt, Daniel R.; Shost, Mark A.; Waydelis, Ronald A.; and Fox, Michael J., 5,588,404, Cl. 123-90.170.
- Weatherby, David E.: See—
- Brandl, Ernest D.; and Weatherby, David E., 5,588,784, Cl. 405-262.000.
- Webb, Brian A.: See—
- Wentworth, Robert M.; Galloway, David; Cotney, Garland D.; and Webb, Brian A., 5,590,232, Cl. 385-92.000.
- Webcore Technologies, Inc.: See—
- Day, Stephen W., 5,589,243, Cl. 428-56.000.
- Webster, John R.: See—
- Chang, Hou-Min; Jameel, Hasan; Song, Junfu; Pan, Dingru; Amini, Bijan; Webster, John R.; and Evans, Bruce A., 5,589,032, Cl. 162-76.000.
- Weder, Donald E.; Straeter, William F.; and Straeter, Joseph G., to Southpac Trust International, Inc. Band applicator for applying a band about a sheet of material and a pot. 5,588,277, Cl. 53-399.000.
- Weder, Donald E.; and Craig, Franklin J., to Southpac Trust International, Inc. Wrapping material for wrapping a floral grouping having staggered strips of adhesive material applied thereto and method. 5,588,530, Cl. 206-451.000.
- Weeger, Engelbert: See—
- Richter, Wolfgang-Dieter; Uebel, Lutz; and Weeger, Engelbert, 5,588,368, Cl. 105-199.100.
- Wegman, Thomas L., to Advance Biofactures of Curacao. Treatment of Dupuytren's disease with collagenase. 5,589,171, Cl. 424-94.670.
- Wegner, Egon; Poth, Ulrich; Gross, Lutz-Werner; and Weidemeier, Klaus, to BASF Lacke + Farben, AG. Process for coating vehicle bodies and aqueous coating. 5,589,228, Cl. 427-407.100.
- Weidemann, Karl H.: See—
- Glucksmann, Dov Z.; and Weidemann, Karl H., 5,588,353, Cl. 99-348.000.
- Weidemeier, Klaus: See—
- Wegner, Egon; Poth, Ulrich; Gross, Lutz-Werner; and Weidemeier, Klaus, 5,589,228, Cl. 427-407.100.
- Weidler, Burghard: See—
- Schlotzer, Ewald; Mayser, Peter; Grimminger, Friedrich; Seeger, Werner; Weidler, Burghard; Sommermeier, Klaus; and Thomas, Martin, 5,589,508, Cl. 514-560.000.
- Weidmueller Interface GmbH & Co.: See—
- Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709.000.
- Weiland, Ana L.; Kornfeld, Richard K.; and Maloney, John E., to QUALCOMM Incorporated. Reverse link, transmit power correction and limitation in a radiotelephone system. 5,590,408, Cl. 455-69.000.
- Weinberg, Aaron, to Stanford Telecommunications, Inc. Cost effective geosynchronous mobile satellite communication system. 5,589,834, Cl. 342-354.000.
- Weiner, Ronald M.; Shi, Juan; and Coyne, Vernon E., to University of Maryland at College Park. Thermostable alkaline metalloprotease produced by a hyphomycetes and preparation thereof. 5,589,373, Cl. 435-220.000.
- Weinert, Raymond J.: See—
- Hargis, I. Glen; Kovalchin, John P.; Sharma, Satish C.; Weinert, Raymond J.; and Wilson, John A., 5,589,532, Cl. 524-432.000.
- Weise, David N.: See—
- D'Souza, David L.; Konzen, Neil; and Weise, David N., 5,590,347, Cl. 395-800.000.
- Weishaupt, Christian: See—
- Arbeiter, Markus; and Weishaupt, Christian, 5,588,925, Cl. 474-81.000.
- Weiss, Siegfried: See—
- Alber, Friedrich; Dedelmaier, Rudolf; Jungnitz, Winfried; Schott, Hans; Sesterheim, Heinz; and Weiss, Siegfried, 5,588,201, Cl. 29-605.000.
- Weithmann, Klaus U.: See—
- Naik, Ramachandra G.; Mumhaikar, Vilas N.; Vasumathy, Rangarajan; Lakdawala, Afrah D.; Shirole, Mandakini V.; Lal, Bansi; Blumbach, Jürgen; Weithmann, Klaus U.; and Bartlett, Robert R., 5,589,514, Cl. 514-681.000.
- Weitzenhof, David A.; Watanabe, Isao; Santa Maria, Carmen S.; Niaux, William S.; and McKinley, Gareth H., to Bridgestone/Firestone, Inc. Splined vibration damping device using ER fluids. 5,588,509, Cl. 188-267.000.
- Welt, Guenther: See—
- Sponheimer, Manfred; Welt, Guenther; and Ziegelmayr, Manfred, 5,589,589, Cl. 536-86.000.
- Weng, Lee; and Gueck, Wayne, to Siemens Medical Systems, Inc. System and method for automatic measurement of body structures. 5,588,435, Cl. 128-660.070.
- Wentworth, Alice L.; and Wentworth, Bernard C., to Wisconsin Alumni Research Foundation. Protective encapsulation of micronutrients for ingestion by avian species. 5,589,187, Cl. 424-439.000.
- Wentworth, Bernard C.: See—
- Wentworth, Alice L.; and Wentworth, Bernard C., 5,589,187, Cl. 424-439.000.
- Wentworth, Robert M.; Galloway, David; Cotney, Garland D.; and Webb, Brian A., to Motorola, Inc. Optical package and method of making. 5,590,232, Cl. 385-92.000.
- Wenzhi, Hu, to Inoue, Soichi. Method for separating and analyzing ions by electrostatic ion chromatography and a zwitterionic stationary phase for ion chromatography and method for separating and analyzing analytes by multifunctional liquid chromatography. 5,589,069, Cl. 210-635.000.
- Wermuth, Camille-Georges: See—
- Carrera, Jesus E.; Esteban, Almudena R.; Mann, André; Schoenfelder, Angèle; Schoepp, Darryle D.; Tercero, Concepcion P.; and Wermuth, Camille-Georges, 5,589,501, Cl. 514-438.000.
- Werner Kammann Maschinenfabrik GmbH: See—
- Riss, Einar K., 5,588,361, Cl. 101-216.000.
- Wernicke & Co. GmbH: See—
- Gotschald, Lutz, 5,588,899, Cl. 451-5.000.
- West, Guy J.; and Mahany, Ronald L., to Norand Corporation. Antenna cap for computer device utilizing a radio card. 5,590,346, Cl. 395-800.000.
- West, Jerry B.: See—
- McCoy, James N.; West, Jerry B.; and Podio, Augusto L., 5,589,633, Cl. 417-63.000.
- West, Michael D., to Geron Corporation. Isoquinoline poly (ADP-ribose) polymerase inhibitors to treat skin diseases associated with cellular senescence. 5,589,483, Cl. 514-310.000.
- Western Textile Products Company: See—
- Sand, Edward A., 5,588,385, Cl. 112-475.090.
- Westland Helicopters Limited: See—
- Perkins, Terrence L., 5,588,616, Cl. 244-1.00R.
- Weth, Goshert. Dopaminergic agents for the treatment of cerebral and peripheral blood flow disorders. 5,589,499, Cl. 514-423.000.
- Wetterborg, Lars: See—
- Billström, Lars; Wetterborg, Lars; Dahlin, Steinar; and Persson, Bengt, 5,590,133, Cl. 370-349.000.
- Wetler, Allan J., to International Paper Company. Antistatic layer for photographic elements comprising polymerized polyfunctional aziridine monomers. 5,589,324, Cl. 430-529.000.
- Weyerhaeuser Company: See—
- Hansen, Michael R.; and Young, Richard H., Sr., 5,589,256, Cl. 428-283.000.
- Wheeler, Joseph A.: See—
- Tellam, Mark E.; Brook, Mark G.; Haded, Kevin J.; and Wheeler, Joseph A., 5,589,972, Cl. 359-196.000.
- Wheeler, Larry A.: See—
- Garner, William H.; and Wheeler, Larry A., 5,589,464, Cl. 514-23.000.
- Whirlpool Corporation: See—
- Schmidt, Christopher G.; Fisher, Michael H.; de Almeida, Amilton F.; and Tani, Edison T., 5,588,731, Cl. 312-405.000.
- Whitaker Corporation, The: See—
- Brownlie, Alan W.; Middleton, David T., Jr.; Robertson, James W.; and Shay, Francis J., 5,588,182, Cl. 16-268.000.
- Davis, Wayne S.; Shirk, Michael E.; and Whiteman, Robert N., Jr., 5,588,877, Cl. 439-660.000.
- Feldmeier, Günter; and Schrettinger, Christian, 5,588,857, Cl. 439-248.000.
- Flinchbaugh, Bernadette M.; Gabany, Andrew J.; Melnyk, Adrian L.; and Schmid, Christopher J., 5,588,878, Cl. 439-682.000.
- Götz, Klaus P.; Schaarschmidt, Manfred; and Feldmeier, Günter, 5,588,885, Cl. 439-876.000.
- Irlbeck, Robert D.; Bates, Warren A.; Dumas, Robert; and Volz, Keith L., 5,588,846, Cl. 439-66.000.
- Kile, Richard A., 5,588,849, Cl. 439-83.000.
- Naitoh, Takaki; and Furuya, Okitsugu, 5,588,845, Cl. 439-66.000.
- Puerner, Dean A., 5,588,852, Cl. 439-135.000.
- Rothenberger, Richard E., 5,588,866, Cl. 439-372.000.
- Sipe, Lynn R., 5,588,844, Cl. 439-65.000.
- Thévenaz, Armand P., 5,588,867, Cl. 439-381.000.
- White, Alan W.; Percy, Barry G.; Jones, Allan S.; Buchanan, Charles M.; and Gardner, Robert M., to Eastman Chemical Company. Copolyesters having repeat units derived from succinic acid. 5,589,566, Cl. 528-286.000.
- White, David C.: See—
- Mott, Philip J.; White, David C.; and Becker, Thomas J., 5,588,926, Cl. 474-212.000.
- White, Harry E.: See—
- Collins, Mary A.; Perkins, David G.; and White, Harry E., 5,588,856, Cl. 439-204.000.
- White, Kathleen A.: See—

- Ward, Robert S.; and White, Kathleen A., 5,589,563, Cl. 528-44.000.
- White, Roy A.: See—
- Merz, Edmund H.; White, Roy A.; Fouser, John P.; and Fishman, Norman, 5,589,520, Cl. 521-64.000.
- White, Scott A.: See—
- Zuraski, Gerald D., Jr.; White, Scott A.; Chinnakonda, Murali S.; and Christie, David S., 5,590,352, Cl. 395-800.000.
- White, Ted R.; Hsu, Ting-Chen; Somero, Bradley M.; Chonko, Mark A.; and Lin, Jung-Hui, to Motorola Inc. Process for fabricating a non-silicided region in an integrated circuit. 5,589,423, Cl. 437-228.000.
- Whitehouse, Robert S.: See—
- Menashi, Jaime; Reid, Robert C.; Whitehouse, Robert S.; and Kaul, David J., 5,589,531, Cl. 524-409.000.
- Whiteman, Paul L.: See—
- Higginson, Roy C.; and Whiteman, Paul L., 5,588,693, Cl. 246-183.000.
- Whiteman, Robert N., Jr.: See—
- Davis, Wayne S.; Shirk, Michael E.; and Whiteman, Robert N., Jr., 5,588,877, Cl. 439-660.000.
- Whitley, Wayne P.; Springfield, Randall S.; Hudson, Harold D.; Tiller, Byron K.; Allard, David J.; Hsieh, Daniel Ming-Te; Goodwin, Julie F.; Murakami, Thomas T.; and Canova, Francis J., Jr., to International Business Machines Corporation. Field programming apparatus and method for updating programs in a personal communications device. 5,590,373, Cl. 395-828.000.
- Whittington, Charles L.: See—
- Lodwig, John P.; Felix, Kenneth A.; and Whittington, Charles L., 5,590,172, Cl. 379-58.000.
- Wiche-Castanon, Maria J.: See—
- Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratiowa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189.000.
- Wicht, John E. Rattle jig. 5,588,247, Cl. 43-42.310.
- Wick, Alexander: See—
- Andrieu, Véronique; Montel, Jean; and Wick, Alexander, 5,589,190, Cl. 424-462.000.
- Wickemeyer, Daniel M.: See—
- Goldston, Mark R.; Bemis, Jon L.; Wickemeyer, Daniel M.; and Potter, David, 5,588,227, Cl. 36-93.000.
- Wickstrom, David E.: See—
- Nobson, Richard C.; Carney, Glenn R.; DeBleeker, Luc; Howes, Ronald B.; Squires, Milo B.; Wickstrom, David E.; Warwick, Dennis J.; Sannel, Benjamin H.; Moeller, Gretchen J.; Caron, Paul R.; and Schofield, Harold D., 5,588,763, Cl. 400-700.000.
- Widigen, Larry: See—
- Sowadsky, Elliot A.; Widigen, Larry; Puziol, David L.; and Van Dyke, Korbin S., 5,590,351, Cl. 395-800.000.
- Wiecek, Glenn N., to L&P Property Management Company. Wall avoiding reclining furniture mechanism. 5,588,710, Cl. 297-463.100.
- Wiegand, Patrick M.; Fisher, John F.; Parrish, John R.; Ballard, Elizabeth S.; Sears, Courtland P., III; Schwarz, George W., Jr.; and Smith, Clod R., III, to Union Carbide Chemicals & Plastics Technology Corporation. Fast gas chromatography method, apparatus and applications. 5,589,630, Cl. 73-23.50.
- Wilberger, Bernard E.: See—
- Carsten, Robert L.; and Wilberger, Bernard E., 5,588,637, Cl. 251-129.030.
- Wilcox, Gerald A.: See—
- Tiller, Mark L.; Taylor, James H.; Say, Geoffrey R.; Eger, Norman J.; Delaune, Lawrence J.; and Wilcox, Gerald A., 5,588,974, Cl. 48-127.900.
- Wilcox, Josiah N.: See—
- O'Brien, Donogh P.; Vehar, Gordon A.; and Wilcox, Josiah N., 5,589,173, Cl. 424-145.100.
- Wilgus, Frank R.: See—
- Benedict, Dale G.; Wilgus, Frank R.; Fulks, Henry J.; and Gagliardi, William T., 5,588,560, Cl. 222-106.000.
- Wilke, Raud A., to HUSCO International, Inc. Variable damping force shock absorber. 5,588,510, Cl. 188-299.000.
- Wilkins, Ronnie D.: See—
- Fauteux, Denis G.; Massucco, Arthur A.; Wilkins, Ronnie D.; and Shi, Jie, 5,588,971, Cl. 29-623.500.
- Fauteux, Denis G.; Massucco, Arthur A.; and Wilkins, Ronnie D., 5,589,300, Cl. 429-218.000.
- Wilkins, Tracy D.: See—
- Drohan, William N.; Wilkins, Tracy D.; Velander, William H.; and Johnson, John L., 5,589,604, Cl. 800-2.000.
- Wilkins, Tyler R.: See—
- Ricco, Gary C.; Shannon, Michael D.; and Wilkins, Tyler R., 5,588,796, Cl. 414-741.000.
- Wilkinson, Brian J.: See—
- DePietro, Richard P.; and Wilkinson, Brian J., 5,588,907, Cl. 452-187.000.
- Wilkinson, Paul A.: See—
- Barker, Thomas N.; Collins, Clive A.; Dapp, Michael C.; Dieffenderfer, James W.; Grice, Donald G.; Kogge, Peter M.; Kuchinski, David C.; Knowles, Billy J.; Lesmeister, Donald M.; Miles, Richard E.; Nier, Richard E.; Retter, Eric E.; Richardson, Robert R.; Rolfe, David B.; Schoonover, Nicholas J.; Smoral, Vincent J.; Stupp, James R.; and Wilkinson, Paul A., 5,590,345, Cl. 395-800.000.
- Willenz, Avigdor; and Tzori, Yiftach, to Integrated Device Technology, Inc. Method and structure for data integrity in a multiple level cache system. 5,590,310, Cl. 395-473.000.
- Williams, Douglas J. Rack and pinion valve operating system. 5,588,403, Cl. 123-90.110.
- Williams, John R.: See—
- Hill, Joe T.; Fields, Gene M.; and Williams, John R., 5,588,820, Cl. 418-55.400.
- Williams, Jon I.; Pierce, James C.; Anderson, G. Mark; and Kari, Prasad, to Magainin Pharmaceuticals Inc. Recombinant production of biologically active peptides and proteins. 5,589,364, Cl. 435-69.700.
- Williams, Linda K.: See—
- Morrison, Eric D.; Chang, Jeffrey C.; and Williams, Linda K., 5,589,433, Cl. 503-227.000.
- Williams, Robert A.: See—
- Embrece, Gary L.; and Williams, Robert A., 5,588,382, Cl. 111-139.000.
- Williams, Ross E.: See—
- Cohen, Huguette; and Williams, Ross E., 5,589,575, Cl. 530-413.000.
- Williams, Russell T.: See—
- Saulpaugh, Thomas E.; Bruffey, Bill M.; and Williams, Russell T., 5,590,534, Cl. 395-683.000.
- Williamson, Roger C.: See—
- Gee, Jeffrey C.; Lawrie, Christophe J.; and Williamson, Roger C., 5,589,442, Cl. 507-103.000.
- Willis-Owen, Richard B.: See—
- Pope, Peter J.; and Willis-Owen, Richard B., 5,589,293, Cl. 429-172.000.
- Wilmes, Manfred: See—
- Eggert, Gerhard; Hanning, Walter; Fiene, Uwe; Schnatwinkel, Michael; Steinmeier, Rudolf; and Wilmes, Manfred, 5,588,881, Cl. 439-709.000.
- Wilesey, Christopher D.: See—
- Deng, Zhi D.; Sigler, Gerald F.; Surridge, Nigel A.; Wilesey, Christopher D.; McEnroe, Robert J.; Jernigan, Walter W.; and Muddiman, Rebecca W., 5,589,326, Cl. 435-4.000.
- Wilson, Graham J. Garden cutting tools. 5,588,289, Cl. 56-13.100.
- Wilson, John A.: See—
- Hargis, I. Glen; Kovalchin, John P.; Sharma, Satish C.; Weinert, Raymond J.; and Wilson, John A., 5,589,532, Cl. 524-432.000.
- Wilson, Nathaniel B.; and McLaren, Elbert A., II. Battery charger having a multiple function sense line. 5,589,756, Cl. 320-22.000.
- Wilson, Robert F., to Eberspächer, J. Method and apparatus for detecting the onset of flooding of an ultrasonic atomizer. 5,588,592, Cl. 239-4.000.
- Wilson, Steven E., to Board of Regents, The University of Texas System. Methods and treatments for corneal healing with hepatocyte and keratinocyte growth factors. 5,589,451, Cl. 512-2.000.
- Wiltbank, Milo; and Pursley, James R., to Ausa International, Inc. Process for the synchronization of ovulation. 5,589,457, Cl. 514-12.000.
- Wiltshire, Mark: See—
- Mayo, Kevin; and Wiltshire, Mark, 5,588,743, Cl. 362-299.000.
- Winardi, Michael: See—
- Riley, Rory M.; Uyeda, Alan K.; and Winardi, Michael, 5,588,686, Cl. 292-92.000.
- Winch & Engineering Limited: See—
- McCrene, Alan I., 5,588,633, Cl. 248-647.000.
- Windmüller & Hölcher: See—
- Achelpohl, Fritz; and Sandmeier, Hermann, 5,588,944, Cl. 493-205.000.
- Wink, Joachim: See—
- Ulbrich, Norbert; Hilgenfeld, Rolf; Hänel, Heinz; Sachse, Burkhard; Braun, Peter; Wink, Joachim; Eckes, Peter; Logemann, Jürgen; and Schell, Josef, 5,589,624, Cl. 800-205.000.
- Winker, Bruce K.: See—
- Gunning, William J., III; Winker, Bruce K.; and Koch, Gene C., 5,589,963, Cl. 349-119.000.
- Winkler, Louis J., Jr.; and Winkler, Louis J., Sr. Fishing rod rack. 5,588,542, Cl. 211-70.800.
- Winkler, Louis J., Sr.: See—
- Winkler, Louis J., Jr.; and Winkler, Louis J., Sr., 5,588,542, Cl. 211-70.800.
- Winkler, Matthew; and Goldrick, Marianna M., to Ambion, Inc. Methods and compositions for detecting base pair mismatches. 5,589,329, Cl. 435-5.000.
- Winner, Hermann; and Gaillard, Alain, to Robert Bosch GmbH. Vehicle hydraulic brake system operating with power assistance. 5,588,718, Cl. 303-113.100.
- Winter, Gerhard: See—
- De Jaeger, Nikolaas; Damen, Guy; Winter, Gerhard; and Van Havenbergh, Jan, 5,589,048, Cl. 204-489.000.
- Wischermann, Gerhard, to U.S. Philips Corporation. Method and circuit for detecting and concealing video signal errors. 5,589,887, Cl. 348-616.000.
- Wisconsin Alumni Research Foundation: See—
- Felgner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44.000.
- Wentworth, Alice L.; and Wentworth, Bernard C., 5,589,187, Cl. 424-439.000.
- Wise, Douglas J.: See—
- Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zarembka, Michael J., 5,588,507, Cl. 188-71.500.
- Wissell, Harold J.: See—
- Edgington, Robert J.; Stepro, James A.; Wissell, Harold J.; and Lundberg, Scott A., 5,589,301, Cl. 429-234.000.

- Witman, Paul: See—
Blumstein, Paul; Cole, Randy; Cook, James; Doshi, Ashwin; Grandcolas, Michael; Gryte, Stephen; McCallick, Frank; Moskowitz, Marvin; Schechtman, Howard; Sears, Michael; Shulman, Steve; Greenberg, Walter; Millo, Patricia; Sidikman, Paul; Virnig, Alex J.; Witman, Paul; and Fenster, Valerie, 5,589,855, Cl. 345-173,000.
- Witowski, Edgar; and Mayer, Guenter, to Robert Bosch GmbH. Valve block. 5,588,465, Cl. 137-625,640.
- Witt, Carol Joyce: See—
Kotsopoulos, Thomas G., 5,588,280, Cl. 53-435,000.
- Witteveen, Gustaaf J. Mixing device and method for gaseous liquid of pulverised substances. 5,588,379, Cl. 110-262,000.
- Wohlgemuth, Emanuel E. Bottle mold with adjustable neck block. 5,589,204, Cl. 425-182,000.
- Wolbers, Dick R.; and Koerse, Ronkers, to All Seas Group S.A. Method and installation for laying a pipe-line. 5,588,780, Cl. 405-170,000.
- Wolf, Barbara; and Fabricius, Norbert, to IOT Integrierte Optik GmbH. Integrated optical branching arrangement and method using same. 5,590,226, Cl. 385-45,000.
- Wolf, Fred R.: See—
Chappell, Joseph; Saunders, Court A.; and Wolf, Fred R., 5,589,619, Cl. 800-205,000.
- Wolfe, Robert M. Wheel mounting bracket and spacer. 5,588,661, Cl. 280-202,000.
- Wolffert, Robert L.; and Hill, Craig S., to Hybritech, Incorporated. Assay for bone alkaline phosphatase. 5,589,574, Cl. 530-388,260.
- Wolff, Jon A.: See—
Feigner, Philip L.; Wolff, Jon A.; Rhodes, Gary H.; Malone, Robert W.; and Carson, Dennis A., 5,589,466, Cl. 514-44,000.
- Wollmann, Theodor: See—
Defossa, Elisabeth; Fischer, Gerd; Gerlach, Uwe; Hörlein, Rolf; Krass, Norbert; Lattrell, Rudolf; Stache, Ulrich; and Wollmann, Theodor, 5,589,594, Cl. 540-228,000.
- Womack International, Inc.: See—
Womack, Thomas H., 5,589,076, Cl. 210-739,000.
- Womack, Thomas H., to Womack International, Inc. Method and apparatus for optimizing operation of a filter system. 5,589,076, Cl. 210-739,000.
- Wong, Bing L.; Shen, Yong-Qiang; and Chen, Yung-Pin, to Biopure Corporation. Halogenation of cephalixin with haloperoxidase from *Rathayibacter biopurens*. 5,589,354, Cl. 435-47,000.
- Wong, Jimmy: See—
Heeb, Jay; Shenoy, Sunil; and Wong, Jimmy, 5,590,368, Cl. 395-800,000.
- Wong, Kwok W.: See—
Holmes, William K.; Jones, Albert E.; and Wong, Kwok W., 5,588,418, Cl. 125-13,010.
- Wong, Walter: See—
Patrick, Paul R.; and Wong, Walter, 5,589,996, Cl. 360-73,030.
- Wong-Chan, Monica C.: See—
Hillis, W. Daniel; Douglas, David C.; Leiserson, Charles E.; Kuszmil, Bradley C.; Gannukhi, Mahesh N.; Hill, Jeffrey V.; and Wong-Chan, Monica C., 5,590,283, Cl. 395-200,020.
- Woo, Jong S., to Hanmi Pharm. Ind. Co., Ltd. Cyclosporin-containing soft capsule compositions. 5,589,455, Cl. 395-455,000.
- Wood, Archie T.: See—
Maltais, Jo-Ann B.; Wood, Archie T.; and Hovland, Roy S., 5,589,070, Cl. 210-636,000.
- Wood, Daniel P., to Acme Electric Corporation. Terminal block. 5,588,880, Cl. 439-709,000.
- Woodard, Floyd E.: See—
Gibbons, Kevin P.; Lau, Louis C.; and Woodard, Floyd E., 5,589,280, Cl. 428-626,000.
- Woodham, Annie R. Table leg extension. 5,588,624, Cl. 248-188,400.
- Woolford, Michael E.; and Sievert, Dick J., to Block Systems, Inc. Method of forming composite masonry blocks. 5,589,124, Cl. 264-157,000.
- Wooten, David R.; Miller, Craig A.; Leigh, Kevin B.; Costley, Robert B.; and Simonich, Christopher E., to Compaq Computer Corporation. Scalable tree structured high speed input/output subsystem architecture. 5,590,292, Cl. 395-825,000.
- Woydich, Horst. Pad for use in scanning data stored on a flat surface. 5,589,951, Cl. 358-473,000.
- Wright, Kevin; Rogers, Lloyd W., Jr.; Baughman, Robert W.; and Chapman, David J., to General Motors Corporation. Power operator for pivotable vehicle closure element. 5,588,258, Cl. 49-340,000.
- Wrzesinski, Stanley, to Motorola Inc. Oscillator with impedance buffer for increased pullability. 5,589,804, Cl. 331-116,000.
- Wu, Ching-Lung. Push wheel switch. 5,588,524, Cl. 200-552,000.
- Wu, Hsin-Wei. Light bulb socket structure having a bulb housing with engaging means. 5,588,863, Cl. 439-356,000.
- Wu, Jung-Wuan. Alcohol lamp. 5,588,823, Cl. 431-241,000.
- Wu, Yaming: See—
Ono, Mitsunori; Wada, Yumiko; Wu, Yaming; Kitaguchi, Hiroshi; Jimbo, Yumiko; Nemori, Ryoichi; Gillies, Stephen; and Lo, Kin-Ming, 5,589,510, Cl. 514-590,000.
- Wudd, Fred; and Heeger, Alan, to University of California, The Regents of. Water-soluble conducting polyphenylene vinylene polymers. 5,589,565, Cl. 528-205,000.
- Wynn, Ed; Diaz-Infante, Javier; and deGroot, Peter, to Dole Fresh Vegetables Co. Broccoli banding machine. 5,588,278, Cl. 53-399,000.
- Xenakis, Zacharias: See—
Vijn, Jan P.; Xenakis, Zacharias; Bour, Daniel L.; and Childs, Jerry D., 5,588,488, Cl. 166-293,000.
- Xerox Corporation: See—
Curry, Douglas N.; and Hecht, David L., 5,589,870, Cl. 347-233,000.
- Hadimioglu, Babur B., 5,589,864, Cl. 347-46,000.
- Hart, Steven C.; and Parker, Delmer G., 5,589,917, Cl. 399-274,000.
- Lamping, John O.; and Rao, Ramana B., 5,590,250, Cl. 395-127,000.
- Lewis, Alan G., 5,589,847, Cl. 345-98,000.
- Lyles, Joseph B.; and Bell, Alan G., 5,590,123, Cl. 370-397,000.
- Malhotra, Shadi L., 5,589,277, Cl. 428-500,000.
- Xing Inc.: See—
Nishimura, Osamu; and Nishikawa, Hiroshi, 5,588,842, Cl. 434-307,000.
- Yabe, Tomoaki: See—
Miyano, Shinji; Sato, Katsuhiko; and Yabe, Tomoaki, 5,590,084, Cl. 365-230,010.
- Yabuki, Akihiko: See—
Nakata, Yasuyuki; Yabuki, Akihiko; Yoshida, Yutaka; and Nishimoto, Katsushi, 5,590,244, Cl. 395-95,000.
- Yada, Yukihiko; and Hirai, Yoichi, to Tokai Kogyo Kabushiki Kaisha. Windshield molding for vehicles and the production method thereof. 5,588,691, Cl. 296-93,000.
- Yagasaki, Yoichi: See—
Suzuki, Teruhiko; Yagasaki, Yoichi; Sudo, Tatsuya; and Okazaki, Toru, 5,590,139, Cl. 371-49,100.
- Yagi, Wataru: See—
Shirai, Takeshi; and Yagi, Wataru, 5,588,433, Cl. 128-660,050.
- Yahagi, Masahiko: See—
Tsuiji, Toshiya; and Yahagi, Masahiko, 5,590,174, Cl. 379-58,000.
- Yakymyshyn, Christopher P.: See—
Duggal, Anil R.; and Yakymyshyn, Christopher P., 5,590,090, Cl. 367-7,000.
- Yale University: See—
Reed, Mark A., 5,589,692, Cl. 257-23,000.
- Yamada, Akio: See—
Hashimoto, Koichi; Yamada, Akio; Hamano, Hirokazu; Mori, Shigeiro; and Moruchi, Hisako, 5,589,506, Cl. 514-520,000.
- Yamada, Kazuo; Mitate, Takehito; Yoneda, Tetsuya; and Nishimura, Naoto, to Sharp Kabushiki Kaisha. Carbon electrode for nonaqueous secondary battery, fabrication method for the same and nonaqueous secondary battery using the same. 5,589,299, Cl. 429-218,000.
- Yamada, Koichiro; Yasuda, Kōsuke; Kikkawa, Kohei; and Kohno, Rikako, to Tanabe Seiyaku Co., Ltd. Benzenesulfonamide derivative and process for preparing thereof. 5,589,478, Cl. 514-269,000.
- Yamada, Kunio; and Sawada, Michio, to Kabushiki Kaisha Toshiba. Multiprocessor system with processor arbitration and priority level setting by the selected processor. 5,590,380, Cl. 395-868,000.
- Yamada, Masahiro: See—
Sano, Toshifumi; Yamada, Masahiro; Umezawa, Yoshiaki; Okada, Yoshikatsu; and Natori, Akira, 5,589,711, Cl. 257-718,000.
- Sasaki, Yu; Iwasawa, Junichi; and Yamada, Masahiro, 5,588,732, Cl. 362-10,000.
- Yamada, Mitsuo; and Nojiri, Hiroyuki, to Nippon Paint Co., Ltd. Pigment grinding resin for electrodeposition paint and pigment paste containing the same. 5,589,527, Cl. 523-414,000.
- Yamada, Shuri; Ogawa, Masanori; and Unosawa, Kazuomi, to Freund Industrial Co., Ltd. Granulating-coating apparatus and granulating and coating method using the same. 5,589,225, Cl. 427-212,000.
- Yamada, Takeo: See—
Ogino, Masanori; Yamada, Takeo; Ikeda, Miyuki; Fujikura, Tsuneo; Fujiwara, Takahiko; and Nakagiri, Etsuhiro, 5,589,883, Cl. 348-379,000.
- Yamada, Tohru: See—
Sato, Yuki; Ishizaki, Toshio; Sakae, Tsuyoshi; Hashimoto, Koichi; Yamada, Tohru; and Uwano, Tomoki, 5,589,724, Cl. 310-348,000.
- Yamada, Yoko; Takiguchi, Takao; Iwaki, Takashi; Togano, Takeshi; Nakamura, Shinichi; and Nakazawa, Ikuo, to Canon Kabushiki Kaisha. Mesomorphic compound, liquid crystal composition containing same, and liquid crystal device using same. 5,589,103, Cl. 252-299,610.
- Yamada, Yuji: See—
Inanaga, Kiyofumi; and Yamada, Yuji, 5,590,094, Cl. 369-4,000.
- Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, to Ushiodenki Kabushiki Kaisha. Emission device with a cadmium lamp. 5,589,735, Cl. 313-638,000.
- Yamaguchi, Chiseki, to NEC Corporation. Method and apparatus for forming an image on a recording medium. 5,589,867, Cl. 347-141,000.
- Yamaguchi, Hiroyuki: See—
Asano, Katsuhiko; Sugai, Masaru; Yamaguchi, Hiroyuki; and Umeno, Takaji, 5,588,721, Cl. 303-163,000.
- Yamaguchi, Kenji; Takagi, Shoji; Mitsugi, Sadahiko; Mita, Mamoru; and Murakami, Tomio, to Hitachi Cable, Ltd. Multi-metal layer wiring tape carrier and process for fabricating the same. 5,589,668, Cl. 174-266,000.
- Yamaguchi, Kohji: See—
Tsuiji, Tomoko; Yamaguchi, Kohji; Kondo, Kiyosi; and Urakami, Teizi, 5,589,481, Cl. 514-287,000.
- Yamaguchi, Nobuyuki, to Daiwa Seiko, Inc. Braking force adjusting device in a fishing reel. 5,588,605, Cl. 242-268,000.
- Yamaguchi, Takahiro; Tajiri, Shinsuke; and Nakada, Juichi, to Advantest Corporation. Method and apparatus for estimating PSK modulated signals. 5,590,158, Cl. 375-331,000.

- Yamaha Corporation: See—
Kawano, Toshihiko, 5,590,033, Cl. 363-25,000.
- Morishima, Morito, 5,590,112, Cl. 369-124,000.
- Ogusu, Mikio; and Fujiwara, Kazunobu, 5,590,100, Cl. 369-32,000.
- Yamaha Hatsudoki Kabushiki Kaisha: See—
Ikeda, Keijiroh, 5,588,887, Cl. 440-88,000.
- Suzuki, Toshio; and Iida, Yoshikatsu, 5,588,416, Cl. 123-684,000.
- Yamakawa, Koji: See—
Ujita, Toshihiko; Yamakawa, Koji; Takenouchi, Masanori; Sugama, Sadayuki; Watanabe, Kenjiro; Osada, Torachika; Nakajima, Kazuhiro; Tsutsumi, Takayoshi; Kubota, Hidemi; Kotaki, Yasuo; Tsukuda, Kei-ichiro; and Sato, Yohei, 5,589,862, Cl. 347-87,000.
- Yamakawa, Teruji: See—
Ohtsuka, Masaaki; Yamakawa, Teruji; and Maruyama, Tetsuo, 5,590,096, Cl. 369-13,000.
- Yamaki, Jun: See—
Satomi, Yasuhiko; Itoh, Seiichi; Otsuka, Eiji; Yamaki, Jun; and Kato, Takashi, 5,588,197, Cl. 29-455,100.
- Yamamoto, Haruo: See—
Fujimoto, Masaya; and Yamamoto, Haruo, 5,589,950, Cl. 358-455,000.
- Yamamoto, Hideaki; Matsumaru, Haruo; Suzuki, Tetsuaki; Nakatani, Mitsuo; Tsukii, Michio; Sasano, Akira; Oikawa, Saburo; and Oritsuki, Ryoji, to Hitachi, Ltd. Active matrix display device using aluminum alloy in scanning signal line or video signal line. 5,589,962, Cl. 349-46,000.
- Yamamoto, Hideo: See—
Ishikawa, Hajime; Ogawa, Masaaki; Hasegawa, Ryosuke; and Yamamoto, Hideo, 5,589,205, Cl. 425-526,000.
- Yamamoto, Hiroshi: See—
Tsuiji, Masanori; Abe, Kimihiro; Sugiyama, Osamu; and Yamamoto, Hiroshi, 5,588,868, Cl. 439-397,000.
- Yamamoto, Kazuhiro: See—
Higuchi, Toshio; Fukushima, Yasuhiro; Furumori, Kenji; Yamamoto, Kazuhiro; and Ouchi, Minoru, 5,589,390, Cl. 435-307,100.
- Yamamoto, Keiichi: See—
Sasaki, Kunimasa; Wakiyama, Youichi; Matsumoto, Takahiro; Tanaka, Kisaburo; and Yamamoto, Keiichi, 5,588,582, Cl. 228-127,000.
- Yamamoto, Masahiro: See—
Nagahara, Teruaki; and Yamamoto, Masahiro, 5,589,634, Cl. 73-514,330.
- Yamamoto, Masayuki, to Yazaki Corporation. Connector fastening mechanism. 5,588,865, Cl. 439-364,000.
- Yamamoto, Michio: See—
Furutani, Atsushi; Hibi, Takuo; Yamamoto, Michio; Tanaka, Kazuyuki; Tada, Kazuhiko; Fukao, Masami; and Suzukamo, Gohfu, 5,589,596, Cl. 564-446,000.
- Yamamoto, Osamu: See—
Takada, Kazunori; Kondo, Shigeo; Yamamoto, Osamu; and Nishijima, Motoaki, 5,589,298, Cl. 429-218,000.
- Yamamoto, Shinji, to Canon Kabushiki Kaisha. Sheet feeding apparatus. 5,588,758, Cl. 400-322,000.
- Yamamoto, Shu: See—
Taga, Hidenori; Edagawa, Noboru; Takeda, Noriyuki; Yamamoto, Shu; and Akiba, Shigeyuki, 5,589,969, Cl. 359-124,000.
- Yamamoto, Yoshio: See—
Hrytzak, Bernard J.; Gomi, Takeshi; Nemoto, Hirotomi; and Yamamoto, Yoshio, 5,588,414, Cl. 123-571,000.
- Yamamura Glass Co., Ltd.: See—
Takashima, Tadayoshi; Chiha, Takahiro; and Tanaka, Takashi, 5,588,544, Cl. 215-42,000.
- Yamamura, Ikuo: See—
Ogushi, Masaki; Takeuchi, Osamu; Yamamura, Ikuo; Iura, Toru; and Yoshida, Hironobu, 5,590,150, Cl. 373-9,000.
- Yamamura, Takaya; and Esaki, Kunihiro, to Sony Corporation. Phase comparator circuit and phase synchronization circuit. 5,589,801, Cl. 331-14,000.
- Yamamura, Takehiko: See—
Kawamura, Shigetoshi; and Yamamura, Takehiko, 5,590,231, Cl. 385-78,000.
- Yamamura, Yoshitami; Morimoto, Nobuhiko; and Tanaka, Nobuyuki, to Henkel Kommanditgesellschaft auf Aktien. Polymerizable, curable molding composition and a molding or coating process using this molding composition. 5,589,230, Cl. 427-493,000.
- Yamanaka, Iwao: See—
Nakanishi, Shigeo; Tominaga, Tetsuo; Yamanaka, Iwao; Higo, Takashi; and Shibata, Toshiyuki, 5,589,491, Cl. 514-338,000.
- Yamasaki, Tatsuo; Okuma, Ikuo; and Onishi, Ken, to Mitsubishi Denki Kabushiki Kaisha. Image recording method and apparatus with reduced error propagation. 5,589,994, Cl. 360-15,000.
- Yamasaki, Tatsuo: See—
Iwasaki, Itsutoshi; Yamasaki, Tatsuo; and Sawada, Hideaki, 5,589,426, Cl. 501-32,000.
- Yamashita, Katsuji: See—
Noda, Koji; Fujikawa, Hisayoshi; Yamashita, Katsuji; and Taga, Yasunori, 5,589,733, Cl. 313-509,000.
- Yamashita, Kazuhiro, to Advantest Corporation. Semiconductor IC tester. 5,590,137, Cl. 371-27,000.
- Yamashita, Masaaki: See—
Yoshimi, Naoto; Watanabe, Toyofumi; and Yamashita, Masaaki, 5,589,279, Cl. 428-623,000.
- Yamashita, Shinji: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
- Yamauchi, Mineo: See—
Takahara, Hidetake; Ueno, Takeshi; Oshima, Katsuyuki; Asajima, Mikio; and Yamauchi, Mineo, 5,589,434, Cl. 503-227,000.
- Yamauchi, Tatsumi: See—
Iwamura, Masahiro; Yamauchi, Tatsumi; Tanaka, Shigeya; and Mori, Kazutaka, 5,590,361, Cl. 395-800,000.
- Yamazaki, Itaru: See—
Ide, Nobuhiko; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, 5,590,365, Cl. 395-394,000.
- Yamazaki, Mikio: See—
Sugata, Yoshinobu; Yamazaki, Mikio; and Umegaki, Takashi, 5,589,860, Cl. 347-20,000.
- Yamazaki, Naoki: See—
Tamura, Hiroki; Yamazaki, Naoki; Takeyama, Akihiro; Kamura, Hitoshi; and Maeda, Tetsuo, 5,588,410, Cl. 123-416,000.
- Yamazaki, Osamu: See—
Ino, Tsuneyori; Furukawa, Tsuyoshi; Jinbo, Masaki; Kaneko, Hisashi; Fukuzawa, Shinichi; Sugimoto, Masaharu; Nagasawa, Yoshiaki; Ishida, Katsuki; Yamazaki, Osamu; Komura, Yukihiko; and Suka-gawa, Tomoo, 5,590,001, Cl. 360-97,020.
- Yanagawa, Yoshifumi; and Kunihiro, Tadashi, to Matsushita Electric Industrial Co., Ltd. Magnetic head driving apparatus having a magnetic head which is immune to the influence of a magnetic circuit. 5,590,007, Cl. 360-109,000.
- Yanagiya, Satoshi: See—
Miyashita, Naoto; Takahashi, Koichi; Koyama, Mitsutoshi; Nunotani, Shinji; Yanagiya, Satoshi; and Baba, Yoshiro, 5,589,421, Cl. 437-225,000.
- Yanai, Takenori: See—
Hara, Shoji; Yanai, Takenori; and Ishikawa, Kazuhiro, 5,588,523, Cl. 198-781,080.
- Yandroski, Robert M.; Price, John C.; Barnes, Frank; Hermann, Allen M.; and Scott, James F., to Superconducting Core Technologies, Inc. Tuneable electric antenna apparatus including ferroelectric material. 5,589,845, Cl. 343-909,000.
- Yang, Bo: See—
Shim, Sang-Hea; Bakalik, Dennis P.; Johnson, Donald A.; Yang, Bo; and Lu, Frank F., 5,589,106, Cl. 252-387,000.
- Yang, Ching-Yun M., to McNeil-PPC, Inc. Integrated absorbent structures with density and liquid affinity gradients and methods for making the same. 5,589,117, Cl. 264-113,000.
- Yang, Dah-Rong, to Delta Electronics, Inc. Flexibly adaptable and removable cable winding and collecting apparatus. 5,588,626, Cl. 242-378,100.
- Yang, Sheng-Hsing; and Sheu, Shing-Ren, to United Microelectronics Corporation. Process for fabricating a high-voltage MOSFET. 5,589,411, Cl. 437-41,000.
- Yano, Hideyuki; Tanigawa, Koichi; Takeuchi, Akihiko; Sasame, Hiroshi; Otsuka, Yasumasa; Hasegawa, Hiroto; Nanatani, Hideo; and Ono, Kazuaki, to Canon Kabushiki Kaisha. Electrophotographic image forming system. 5,589,924, Cl. 399-350,000.
- Yano, Osamu: See—
Nishihara, Takashi; Ikeda, Toru; Yano, Osamu; and Shiraishi, Shuji, 5,589,815, Cl. 340-444,000.
- Yashima, Norimichi: See—
Hamai, Tsuyoshi; and Yashima, Norimichi, 5,588,873, Cl. 439-489,000.
- Yasuda, Akira, to Kabushiki Kaisha Toshiba. Equipment for generating a transmit signal from first and second digital signals. 5,590,155, Cl. 375-261,000.
- Yasuda, Hidehiro: See—
Mori, Hiroto; and Yasuda, Hidehiro, 5,589,234, Cl. 427-597,000.
- Yasuda, Hiroshi: See—
Abe, Tomohiko; Yasuda, Hiroshi; Sakamoto, Kiichi; and Oae, Yoshihisa, 5,590,048, Cl. 364-489,000.
- Yasuda, Kōsuke: See—
Yamada, Koichiro; Yasuda, Kōsuke; Kikkawa, Kohei; and Kohno, Rikako, 5,589,478, Cl. 514-269,000.
- Yasuda, Yukio: See—
Yamaguchi, Akiyasu; Yasuda, Yukio; Okanuma, Tsuneo; Igarashi, Tatsushi; Matsuno, Hiromitsu; and Hiramoto, Tatsumi, 5,589,735, Cl. 313-638,000.
- Yasukawa, Yoshihito: See—
Ito, Tatsuya; Kawai, Masahito; and Yasukawa, Yoshihito, 5,590,053, Cl. 364-499,000.
- Yasumatsu, Hifumi: See—
Kakiuchi, Daisuke; Ogawa, Yasumichi; Yasumatsu, Hifumi; and Shiraga, Kazutaka, 5,588,469, Cl. 138-137,000.
- Yasumoto, Eiichi: See—
Hatoh, Kazuhito; Niikura, Junji; Yasumoto, Eiichi; and Gamou, Takaharu, 5,589,287, Cl. 429-41,000.
- Yasuno, Atsushi: See—
Fujioka, Yasushi; Okabe, Shōtarō; Kanai, Masahiro; Tamura, Hideo; Yasuno, Atsushi; Sakai, Akira; and Hori, Tadashi, 5,589,007, Cl. 136-249,000.
- Yazaki Corporation: See—
Fukuda, Masaru, 5,588,872, Cl. 439-489,000.

- Hamai, Tsuyoshi; and Yashima, Norimichi, 5,588,873, Cl. 439-489,000.
Ikumi, Tohru; Suzuki, Nobuhiko; and Ishikawa, Satoshi, 5,588,854, Cl. 439-164,000.
Maejima, Takamichi; Inoue, Toshihiro; Hasegawa, Hiroshi; and Nakano, Atsushi, 5,588,206, Cl. 29-845,000.
Nishitani, Keizo; and Suzuki, Hiroshi, 5,589,715, Cl. 307-10,100.
Sawada, Yoshitsugu, 5,588,875, Cl. 439-595,000.
Tsuiji, Masanori; Abe, Kimihiro; Sugiyama, Osamu; and Yamamoto, Hiroshi, 5,588,868, Cl. 439-397,000.
Yamamoto, Masayuki, 5,588,865, Cl. 439-364,000.
YBM Magnetics, Inc.: See—
Bogatin, Jacob G.; and Podoyma, Vladimir, 5,589,065, Cl. 210-222,000.
Yee, Phillip D.: See—
Gorman, Patrick J.; Yee, Phillip D.; and Gray, Mark F., 5,588,189, Cl. 24-632,000.
Yee, William J.: Locking article anchoring assembly for truck beds, 5,588,631, Cl. 248-553,000.
Yeh, Kuo-Strai: Handle arrangement for tea kettles, 5,588,567, Cl. 222-475,100.
Yeh, Yu S.: See—
Gans, Michael J.; and Yeh, Yu S., 5,589,797, Cl. 330-149,000.
Yelderman, Mark L.: See—
McKown, Russell C.; Quinn, Michael D.; and Yelderman, Mark L., 5,588,438, Cl. 128-692,000.
Yemington, Charles R.: See—
Bath, William R.; and Yemington, Charles R., 5,588,230, Cl. 37-190,000.
Yin, Chenwei J.: To Texas Instruments Incorporated. Test circuits and method for integrated circuit having memory and non-memory circuits by accumulating bits of a particular logic state, 5,590,134, Cl. 371-21,500.
Yodogawa Kasei Kabushiki Kaisha: See—
Yoshida, Toshio; and Akai, Toshio, 5,588,531, Cl. 206-454,000.
Yokelson, Howard B.; Nubel, Philip O.; and Behrends, Raymond T., to Amoco Corporation. Polyurethane elastomers prepared from difunctional telechelic linear non-crosslinked polyolefins, 5,589,543, Cl. 525-131,000.
Yokelson, Howard B.: See—
Nubel, Philip O.; and Yokelson, Howard B., 5,589,548, Cl. 525-247,000.
Yokobayashi, Kazuyuki: See—
Takada, Minoru; Sato, Koichi; and Yokobayashi, Kazuyuki, 5,589,130, Cl. 264-537,000.
Yokotaki, Hisashi: See—
Matsumoto, Yakihiro; and Yokotaki, Hisashi, 5,588,401, Cl. 123-41,310.
Yokoyama, Kazumasa: See—
Uryu, Katsuhiko; Ohmizu, Akimasa; Fukuyama, Hajime; Takechi, Kazuo; and Yokoyama, Kazumasa, 5,589,516, Cl. 514-2,000.
Yokoyama, Thomas W.: See—
Valpey, Richard S., III; Yokoyama, Thomas W.; Kraan, John D.; and Harwood, H. James, 5,589,560, Cl. 526-271,000.
Yokoyama, Yoshihiro: See—
Iguchi, Hiroaki; Kurosu, Yasuo; Fujinawa, Masaaki; Yokoyama, Yoshihiro; and Masuzaki, Hidefumi, 5,590,317, Cl. 395-602,000.
Yokozawa, Ayumi, to NEC Corporation. Process simulation method, process simulator and chemical vapor deposition system employing the same, 5,590,051, Cl. 364-496,000.
Yomtov, Sidi: See—
Intrater, Amos; Birenbaum, Andy; Intrater, Gideon; Carmon, Iddo; Shimony, Ilan; Fraenkel, Itai; Epstein, Lev; Katzi, Lior; Viner, Omri; Levitan, Raya; Cohen, Ronny; Yomtov, Sidi; Tzadik, Yehezkel; Greenfeld, Zvi; Greiss, Israel; Oz, Oved; Afek, Yachin; Tsadik, Meir; Doron, Moshe; and Sandbank, Alberto, 5,590,357, Cl. 395-800,000.
Yonahara, Yoshihiro, to Japan Steels International Inc. Elevatable work facility, 5,588,500, Cl. 182-141,000.
Yoneda, Norihiro; Ohba, Toshimitsu; Furuya, Reiko; and Shikata, Kiyotaka, to Fujitsu Limited. Keep call back device, 5,590,183, Cl. 379-142,000.
Yoneda, Tetsuya: See—
Yamada, Kazuo; Mitate, Takehito; Yoneda, Tetsuya; and Nishimura, Naoto, 5,589,299, Cl. 429-218,000.
Yonetani, Yoshiyuki: See—
Koizumi, Satoshi; Yonetani, Yoshiyuki; and Teshiba, Sadao, 5,589,355, Cl. 435-66,000.
Yonezawa, Keitaro, to Kabushiki Kaisha Kosmek. Clamping apparatus, 5,588,642, Cl. 209-244,000.
Yoon, Han S.; Son, Tae W.; Kim, Byung C.; Lee, Chul J.; Min, Byung G.; and Cho, Jae W., to Korea Institute of Science and Technology. Unspun acrylic staple fibers, 5,589,264, Cl. 428-359,000.
Yoshida, Hironobu: See—
Ogushi, Masaki; Takeuchi, Osamu; Yamamura, Ikuro; Iura, Toru; and Yoshida, Hironobu, 5,590,150, Cl. 373-9,000.
Yoshida, Kazunori: See—
Shiraki, Masao; Suzuki, Fujio; and Yoshida, Kazunori, 5,588,470, Cl. 139-435,000.
Yoshida, Kiyohide; Muramatsu, Gyo; Abe, Akira; and Irite, Naoko, to Kabushiki Kaisha Riken. Exhaust gas cleaner and method for cleaning same, 5,589,432, Cl. 502-325,000.
Yoshida, Masami; and Okazaki, Hidetsugu, to Tokyo Seat Corporation; and Honda Giken Kogyo Kabushiki Kaisha. Table means for vehicle, 5,588,697, Cl. 297-173,000.
Yoshida, Masanobu: See—
Akagii, Takao; Yoshida, Masanobu; Ogawa, Yasushige; Kasa, Yasushi; and Kawamura, Shouichi, 5,590,074, Cl. 365-185,220.
Yoshida, Masaru: See—
Okibayashi, Katsushi; Ogura, Takashi; and Yoshida, Masaru, 5,589,732, Cl. 313-506,000.
Yoshida, Masashi; Nanba, Tomiyuki; Uehara, Keichi; Sakurai, Osamu; Takahashi, Hideki; and Fukui, Hiroshi, to Shiseido Co., Ltd. Cosmetic, 5,589,165, Cl. 424-78,030.
Yoshida, Nobuyuki, to Nihon Doubutsu Yakuhin Kabushikigaisya. Spawning case for use in an aquarium, 5,588,396, Cl. 119-252,000.
Yoshida, Ryuichi; Okamoto, Yasuhiro; and Kuwana, Minoru, to Minolta Co., Ltd. Driving apparatus using transducer, 5,589,723, Cl. 310-328,000.
Yoshida, Shinichi: See—
Shichiku, Ricardo T.; Yoshida, Shinichi; Muramatsu, Tsuyoshi; Onozaki, Manabu; and Matsuura, Yasuhiro, 5,590,355, Cl. 395-800,000.
Yoshida, Takayasu: See—
Shibata, Hideyo; Kinoshita, Ritsuro; Yoshida, Takayasu; and Eshima, Shigeo, 5,589,992, Cl. 386-72,000.
Yoshida, Takeshi: See—
Ide, Nobuhiro; Yoshida, Takeshi; Kondo, Yoshihisa; Nagamatsu, Masato; Mori, Junji; and Yamazaki, Itaru, 5,590,365, Cl. 395-394,000.
Yoshida, Teruaki: See—
Kuwabara, Mitsuo; Ikegami, Kiyoshi; Yoshida, Teruaki; Takahashi, Koji; Harada, Tamotsu; Komiyama, Takeshi; Hirai, Fumio; and Hayashi, Masamichi, 5,590,388, Cl. 419-39,000.
Yoshida, Toshiaki: See—
Miyazaki, Mutsumi; and Yoshida, Toshiaki, 5,588,979, Cl. 65-164,000.
Yoshida, Toshio; and Akai, Toshio, to Yodogawa Kasei Kabushiki Kaisha; and Sharp Kabushiki Kaisha. Glass substrate transport box, 5,588,531, Cl. 206-454,000.
Yoshida, Yuko: See—
Wallack, David A.; Lewis, Donald M.; Munter, John D.; Silbernagel, Peter J.; Heiti, Robert V.; and Yoshida, Yuko, 5,589,247, Cl. 428-141,000.
Yoshida, Yutaka: See—
Nakata, Yasuyuki; Yabuki, Akihiko; Yoshida, Yutaka; and Nishimoto, Katsushi, 5,590,244, Cl. 395-95,000.
Yoshihara, Toshiaki: See—
Matsuo, Ryukichi; and Yoshihara, Toshiaki, 5,589,252, Cl. 428-216,000.
Yoshihide Hagiwara: See—
Hagiwara, Hideaki; and Aotsuka, Yasuyuki, 5,589,573, Cl. 530-387,200.
Yoshihiro, Masafumi: See—
Kashiwakura, Akira; Shimazaki, Katsusuke; Yoshihiro, Masafumi; Kinoshita, Shin-Isu; Oota, Norio; and Sugiyama, Hisanori, 5,590,097, Cl. 369-13,000.
Yoshimi, Naoto; Watanabe, Toyofumi; and Yamashita, Masaaki, to NKK Corporation. Weldable black steel sheet, 5,589,279, Cl. 428-623,000.
Yoshimura, Hironori: See—
Odani, Niro; Yoshimura, Hironori; Osada, Akira; Tanaka, Tetsuya; and Nakamura, Seichiro, 5,589,223, Cl. 427-248,100.
Yoshimura, Toshifumi; Kikuchi, Ryo; and Inuma, Shoji, to Isuzu Motors Limited. Intervening cloth on an air bag, 5,588,674, Cl. 280-732,000.
Yoshinaga, Yoko: See—
Morishima, Hideki; Matsumura, Susumu; Taniguchi, Naosato; Yoshinaga, Yoko; Kobayashi, Shin; Sudo, Toshiyuki; and Kaneko, Tadashi, 5,589,956, Cl. 359-15,000.
Yoshino, Kenji: See—
Takahashi, Susumu; Uehara, Masao; Kato, Shingo; Kidawara, Atsushi; Saito, Katsuyuki; Goto, Masahito; Ohno, Wataru; Kanamori, Iwao; Hanzawa, Toyoharu; Yoshino, Kenji; Nakada, Akio; Taguchi, Akihiro; Akui, Nobuaki; Karasawa, Hitoshi; Hashiguchi, Toshihiko; Mochida, Akihiko; Fukaya, Takashi; Yamashita, Shinji; Murata, Akira; Koyanagi, Hideki; and Saito, Keisuke, 5,588,948, Cl. 600-111,000.
Youn, Dae-Hee: See—
Park, Sangil; Martinez, Ed F.; and Youn, Dae-Hee, 5,590,241, Cl. 395-2,360.
Young, James W.; and Barberich, Timothy J., to Sepracor Inc. Method for treating migraine headaches using optically pure S(+) fluoxetine, 5,589,511, Cl. 514-646,000.
Young, Philip L.; and Greenberg, Leonard H. Method and apparatus for generating a video signal producing an unviewable display from a videotape recording thereof, 5,589,944, Cl. 386-84,000.
Young, Richard H., Sr.: See—
Hansen, Michael R.; and Young, Richard H., Sr., 5,589,256, Cl. 428-283,000.
Young, Sam W. Device for the prevention of collisions of birds with transparent barriers, 5,588,251, Cl. 43-119,000.
Young, Steven R., to Great Western Press, Inc. Talking trading card, 5,588,678, Cl. 283-67,000.
Youngs, Ross O., to Univenture, Inc. Storage container with integral flap, 5,588,527, Cl. 206-308,100.
Yu, Mantle M., to International Business Machines Corporation. Cylinder address storage in multiple servo sectors of a track, 5,589,998, Cl. 360-78,140.
Yu, Ruey J.; and Van Scott, Eugene J., to Tristrata Technology, Inc. Method of treating wrinkles using quinic acid or quinolactone, 5,589,505, Cl. 514-470,000.
Yuan, Jun: See—
Dunlop, John A.; Yuan, Jun; Kardokus, Janine K.; and Emigh, Roger A., 5,590,389, Cl. 419-67,000.
Yuan, Lin-Sen; and Yuan, Lu, to Hughes Aircraft Company. Coolant/lubricant for machining operations, 5,589,095, Cl. 508-168,000.
Yuan, Lu: See—
Yuan, Lin-Sen; and Yuan, Lu, 5,589,095, Cl. 508-168,000.

- Yuh, Jong H.; and Nam, Jong G., to Hyundai Electronics Industries Co., Ltd. Column redundancy device for semiconductor memory, 5,590,085, Cl. 365-230,030.
Zahner, John. Foot vacuum, 5,588,175, Cl. 15-310,000.
Zaleski, Richard L., II, to Alcon Laboratories, Inc. Surgical cassette loading and unloading system, 5,588,815, Cl. 417-477,200.
Zama, Toshihiro: See—
Suzuki, Yoshitaka; Kondo, Masako; Endo, Takashi; Zama, Toshihiro; Shimoda, Yuji; and Takata, Hiroshi, 5,588,302, Cl. 62-161,000.
Zambon Group S.p.A.: See—
Paiochi, Maurizio, 5,589,598, Cl. 568-756,000.
Zampini, Anthony; and Trefonas, Peter, III, to Shipley Company, L.L.C. Esterification product of aromatic novolak resin with quinone diazide sulfonyl group, 5,589,553, Cl. 525-504,000.
Zandveld, Frederik: See—
Klapproth, Peter; Zandveld, Frederik; Bakker, Jacobus M.; and Van Loo, Gerardus C., 5,590,354, Cl. 395-800,000.
Zarembka, Michael J.: See—
Beardsley, George C.; Berk, Brian K.; Kartman, Albert E.; May, Stanley W.; Wise, Douglas J.; and Zarembka, Michael J., 5,588,507, Cl. 188-71,500.
Zarge, Jonathan A.; and Schroeder, William J., to General Electric Company. Method for reducing the complexity of a polygonal mesh, 5,590,248, Cl. 395-121,000.
Zato, Thomas J.: See—
Gaughan, Kevin J.; and Zato, Thomas J., 5,589,893, Cl. 348-734,000.
Zbikowski, Mark; Berkowitz, Brian T.; and Ferguson, Robert I., to Microsoft Corporation. Method and system for tracking files pending processing, 5,590,318, Cl. 395-618,000.
Zboril, Zdenek; and Brown, Stephen J., to Novacor Chemicals (International) S.A. Control of a solution process for polymerization of ethylene, 5,589,555, Cl. 526-64,000.
Zedd Technologies Inc.: See—
Rizkalla, Emad; and Newbury, David, 5,588,369, Cl. 108-2,000.
Zedda, Alessandro: See—
Navarini, Walter; Tortelli, Vito; and Zedda, Alessandro, 5,589,557, Cl. 526-247,000.
Zedler, Angelika A.: See—
Metzger, Carl W.; Feith, Bernhard H.; Gruber, Ute; Zedler, Angelika A.; and van Wingerde, Mario M. M., 5,589,534, Cl. 524-548,000.
Zeller, Charles P.; Parks, Terry J.; and Durkin, Michael D., to Dell USA, L.P. Configurable interface for routing data between mismatched devices, 5,590,287, Cl. 395-250,000.
Zenco (No. 4) Limited: See—
Buendgen, Michael R.; and Hable, Bernard J., 5,589,606, Cl. 800-200,000.
Zeneca Limited: See—
Bridges, Ian G.; Bright, Simon W. J.; Greenland, Andrew J.; Holt, David C.; Jepson, Ian; and Schuch, Wolfgang W., 5,589,614, Cl. 800-205,000.
McTaggart, Fergus; Pemberton, Denis; and Smith, Graham J., 5,589,166, Cl. 424-78,350.
Shenvi, Ashokkumar B.; Jacobs, Robert T.; Miller, Scott C.; Ohnmacht, Cyrus J., Jr.; and Veale, Chris A., 5,589,489, Cl. 514-323,000.
Zenith Electronics Corporation: See—
Bestler, Caitlin B.; Hartley, Harry A., III; and Rabii, Khosro M., 5,590,202, Cl. 380-49,000.
Gaughan, Kevin J.; and Zato, Thomas J., 5,589,893, Cl. 348-734,000.
Zeon Chemicals Incorporated: See—
Manley, Paul E.; and Flecksteiner, Richard J., 5,589,550, Cl. 525-282,000.
Zexel Corporation: See—
Nozaki, Shinya, 5,588,412, Cl. 123-496,000.
Zhang, Jing, to Wandel & Goltermann Technologies, Inc. Multiport analyzing, time stamp synchronizing and parallel communicating, 5,590,116, Cl. 370-253,000.
Zhang, Jinshan; and Anani, Anaba A., to Motorola, Inc. Carbon electrode materials for electrochemical cells and method of making same, 5,589,289, Cl. 429-122,000.
Zhang, Weiguo; Kramer, David M.; and Goldhaber, David M., to Toshiba America MRI, Inc. Method and apparatus for providing separate fat and water MRI images in a single acquisition scan, 5,589,774, Cl. 324-309,000.
Zhao, Jun; Chang, Frank P.; and Dorfmeister, Charles N., to Applied Materials, Inc. Shielded substrate support for processing chamber, 5,589,003, Cl. 118-728,000.
Zheng, Yu. Exercise bike with amusement features, 5,588,939, Cl. 482-57,000.
Zhu, Naiping: See—
Sekhar, Jainagesh A.; Liu, James J.; and Zhu, Naiping, 5,590,383, Cl. 419-2,000.
Zhu, Wei: See—
Jin, Sungho; Kochanski, Gregory P.; and Zhu, Wei, 5,588,894, Cl. 445-24,000.
Zhu, Yong H.; and Kirsch, Wolff M., to Loma Linda University Medical Center. Inflatable endoscopic retractor with multiple rib-reinforced projections, 5,588,951, Cl. 600-207,000.
Zhuang, Haoren: See—
Nihira, Yoshito; Zhuang, Haoren; and Nomura, Takeshi, 5,589,097, Cl. 252-62,590.
Ziegelmayer, Manfred: See—
Sponheimer, Manfred; Welt, Guenther; and Ziegelmayer, Manfred, 5,589,589, Cl. 536-86,000.
Zikeli, Stefan; Rauch, Ernst; Koberger, Hermann; Ecker, Friedrich; Ruff, Hartmut; Jurkovic, Raimund; and Schwenninger, Franz, to Lenzing Aktiengesellschaft. Process of and apparatus for making cellulose mouldings, 5,589,125, Cl. 264-187,000.
Zilliox, Kent. Interlocking picture frame, 5,588,240, Cl. 40-729,000.
Zimmerman, Stephen A.: See—
Brandt, Thomas J.; and Zimmerman, Stephen A., 5,589,869, Cl. 347-212,000.
Zimmermann, Heinz: See—
Sienel, Günter; Dorn, Maximilian; and Zimmermann, Heinz, 5,589,526, Cl. 523-351,000.
Zinke, Randy J.; and Koves, William J., to UOP. Downflow FCC reaction arrangement with upflow regeneration, 5,589,139, Cl. 422-144,000.
Zinser Textilmaschinen GmbH: See—
Kaak, Hartmut; and Neuendorf, Andreas, 5,590,045, Cl. 364-470,100.
Zippel, Gunther. Method and device for purifying and moistening air, 5,589,132, Cl. 422-24,000.
Zirbel, Kurt D. Combination backpack and seat device, 5,588,570, Cl. 224-155,000.
Zips, Wilhelm; Schuller, Wolfgang; and Urban, Martin, to Robert Bosch GmbH. Pressure-medium-traversed piston of a reciprocating piston pump, 5,588,817, Cl. 417-549,000.
Zitel Corporation: See—
Lautzenheiser, Marvin, 5,590,300, Cl. 395-412,000.
Zlotos, Michael: See—
Becker, Achim; and Zlotos, Michael, 5,588,225, Cl. 34-474,000.
Zodrow, Thomas J.: See—
Studer, Michael K.; Zodrow, Thomas J.; and Elms, Timothy J., 5,588,947, Cl. 588-252,000.
Zollner, Helmut: See—
Gessel, Uwe; Rospek, Rolf; and Zollner, Helmut, 5,589,657, Cl. 102-202,140.
Zöphel, Andreas: See—
Heckl, Konrad; Spevak, Walter; Ostermann, Elinborg; Zöphel, Andreas; Krystek, Edeltraud; Maurer-Fogy, Ingrid; Wiche-Castanon, Maria J.; Stratowa, Christian; and Hauptmann, Rudolf, 5,589,371, Cl. 435-189,000.
Zorbedo GmbH: See—
Wagner, Edmund, 5,588,269, Cl. 52-270,000.
Zreiba, Nuri A.: See—
Passaniti, Joseph L.; Megahed, El-Sayed A.; and Zreiba, Nuri A., 5,589,109, Cl. 252-518,000.
Zuk, Robert F.: See—
Allen, Michael P.; Zuk, Robert F.; and Ensler, Lawrence M., 5,589,399, Cl. 436-169,000.
Zullino, Lucia: See—
Contiero, Claudio; Galbiati, Paola; and Zullino, Lucia, 5,589,405, Cl. 437-6,000.
Zuraski, Gerald D., Jr.; White, Scott A.; Chinnakonda, Murali S.; and Christie, David S., to Advanced Micro Devices, Inc. Dependency checking and forwarding of variable width operands, 5,590,352, Cl. 395-800,000.
Zuraski, Jeffery A.; and Colosky, Mark P., to General Motors Corporation. Enhanced resolution pulse width modulation control, 5,589,805, Cl. 332-109,000.
Zweig, Gilbert, to Glenbrook Technologies. X-ray inspection system, 5,590,170, Cl. 378-63,000.
Zygo Corporation: See—
Deck, Leslie L., 5,589,938, Cl. 356-359,000.
3Com Corporation: See—
Krause, Jeffrey; Strohl, Niles E.; Seaman, Michael J.; Russell, Steven P.; and Hart, John H., 5,590,285, Cl. 395-200,200.
943038 Ontario, Inc.: See—
Eskin, Bernard A.; and Ghent, R. Alison, 5,589,198, Cl. 424-667,000.

LIST OF REISSUE PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 31st DAY OF DECEMBER, 1996

NOTE—Arranged in accordance with the first significant character or word of the name
(in accordance with city and telephone directory practice)

Adcock, Carson D.; and Lauter, Robert, to W. W. Adcock, Inc. Spa with recessed filter chamber. Re. 35,410, Cl. 4-541.300.
Asahi Kogaku Kogyo Kabushiki Kaisha: See—
Takami, Satoshi, Re. 35,415, Cl. 396-165.000.
Asai, Kohtaro: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Ashok, Sankaranarayanan; and Cheskis, Harvey P., to Olin Corporation. Belt casting of molten metal. Re. 35,411, Cl. 164-46.000.
Cheskis, Harvey P.: See—
Ashok, Sankaranarayanan; and Cheskis, Harvey P., Re. 35,411, Cl. 164-46.000.
D'Andrade, Bruce M.: See—
Johnson, Lonnie G.; and D'Andrade, Bruce M., Re. 35,412, Cl. 222-79.000.
Dwek, Raymond A.: See—
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., Re. 35,417, Cl. 435-18.000.
Edge, Christopher J.: See—
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., Re. 35,417, Cl. 435-18.000.
Finnigan Corporation: See—
Mylchreest, Iain C.; and Hail, Mark E., Re. 35,413, Cl. 250-282.000.
Hail, Mark E.: See—
Mylchreest, Iain C.; and Hail, Mark E., Re. 35,413, Cl. 250-282.000.
Itoh, Atsushi: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Johnson, Lonnie G.; and D'Andrade, Bruce M., to Larami Limited. Double tank pinch trigger pump water gun. Re. 35,412, Cl. 222-79.000.
Kamizawa, Koh: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Kinjoh, Naoto: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Larami Limited: See—
Johnson, Lonnie G.; and D'Andrade, Bruce M., Re. 35,412, Cl. 222-79.000.
Lauter, Robert: See—
Adcock, Carson D.; and Lauter, Robert, Re. 35,410, Cl. 4-541.300.
Mitsubishi Denki Kabushiki Kaisha: See—

Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, to Mitsubishi Denki Kabushiki Kaisha. Picture coding and decoding apparatus using vector quantization. Re. 35,414, Cl. 348-416.000.
Mylchreest, Iain C.; and Hail, Mark E., to Finnigan Corporation. Electrospray ion source with reduced neutral noise and method. Re. 35,413, Cl. 250-282.000.
Nishida, Masami: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.
Nishikawa, Mitsutaka: See—
Suzuki, Katsumi; and Nishikawa, Mitsutaka, Re. 35,416, Cl. 349-41.000.
Olin Corporation: See—
Ashok, Sankaranarayanan; and Cheskis, Harvey P., Re. 35,411, Cl. 164-46.000.
Oxford GlycoSystems Ltd.: See—
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., Re. 35,417, Cl. 435-18.000.
Parekh, Raj. B.: See—
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., Re. 35,417, Cl. 435-18.000.
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., to Oxford GlycoSystems Ltd. Oligosaccharide sequencing. Re. 35,417, Cl. 435-18.000.
Seiko Epson Corporation: See—
Suzuki, Katsumi; and Nishikawa, Mitsutaka, Re. 35,416, Cl. 349-41.000.
Suzuki, Katsumi; and Nishikawa, Mitsutaka, to Seiko Epson Corporation. Active matrix liquid crystal display device and method for production thereof. Re. 35,416, Cl. 349-41.000.
Takami, Satoshi, to Asahi Kogaku Kogyo Kabushiki Kaisha. Camera having an automatically operated built-in strobe. Re. 35,415, Cl. 396-165.000.
W. W. Adcock, Inc.: See—
Adcock, Carson D.; and Lauter, Robert, Re. 35,410, Cl. 4-541.300.
Wormald, Mark R.: See—
Rademacher, Thomas W.; Wormald, Mark R.; Parekh, Raj. B.; Edge, Christopher J.; and Dwek, Raymond A., Re. 35,417, Cl. 435-18.000.
Yamazaki, Eizo: See—
Murakami, Tokumichi; Asai, Kohtaro; Kamizawa, Koh; Nishida, Masami; Yamazaki, Eizo; Itoh, Atsushi; and Kinjoh, Naoto, Re. 35,414, Cl. 348-416.000.

LIST OF REEXAMINATION PATENTEES

TO WHOM

CERTIFICATES WERE ISSUED

Bonnichsen, Frits F.; and Jørgensen, Peter N., to Novo Nordisk A/S. Syringe system. B1 5,462,535, Cl. 604-272.000.
Buchholz, Richard D., to Sofamor Danek Group, Inc. System for indicating the position of a surgical probe within a head on an image of the head. B1 5,383,454, Cl. 128-653.100.
Francant, Armand, Jr. Leak proof, preloaded, high-biasing force float-operated over-center valve actuating mechanism. B1 1,034,957, Cl. 417-133.000.
Jenkins, Thomas C.: See—
Palmquist, Donald L.; and Jenkins, Thomas C., B1 4,642,317, Cl. 514-558.000.
Jørgensen, Peter N.: See—
Bonnichsen, Frits F.; and Jørgensen, Peter N., B1 5,462,535, Cl. 604-272.000.
Kelly, John G.: See—
Lorenc, Walter F.; Kelly, John G.; and Mandel, Frederick S., B1 4,457,847, Cl. 210-698.000.
Loeb, Marvin P.: See—
Saadatmanesh, Vahid; and Loeb, Marvin P., B1 5,387,211, Cl. 606-10.000.
Lorenc, Walter F.; Kelly, John G.; and Mandel, Frederick S., to Nalco Chemical Company. Carboxylate polymers for internal scale control agents in boiler systems. B1 4,457,847, Cl. 210-698.000.
Mandel, Frederick S.: See—
Lorenc, Walter F.; Kelly, John G.; and Mandel, Frederick S., B1 4,457,847, Cl. 210-698.000.
Marsala, Joseph: See—
Phillips, Benjamin A.; Zawacki, Thomas S.; and Marsala, Joseph, B1 5,367,884, Cl. 62-101.000.
Nalco Chemical Company: See—
Lorenc, Walter F.; Kelly, John G.; and Mandel, Frederick S., B1 4,457,847, Cl. 210-698.000.
Novo Nordisk A/S: See—
Bonnichsen, Frits F.; and Jørgensen, Peter N., B1 5,462,535, Cl. 604-272.000.
Ohio Agricultural Research and Development Center: See—
Palmquist, Donald L.; and Jenkins, Thomas C., B1 4,642,317, Cl. 514-558.000.
Palmquist, Donald L.; and Jenkins, Thomas C., to Ohio Agricultural Research and Development Center. Process for feeding ruminant animals and composition for use therein. B1 4,642,317, Cl. 514-558.000.
Phillips, Benjamin A.; Zawacki, Thomas S.; and Marsala, Joseph, to Phillips Engineering Co. Generator-absorber-heat exchange heat transfer apparatus and method and use thereof in a heat pump. B1 5,367,884, Cl. 62-101.000.
Phillips Engineering Co.: See—
Phillips, Benjamin A.; Zawacki, Thomas S.; and Marsala, Joseph, B1 5,367,884, Cl. 62-101.000.

DECEMBER 31, 1996

LIST OF DESIGN PATENTEES

PI 107

Rutherford, Jerry, to Rutherford, Lora E. Acoustical imaging system. B1 4,625,557, Cl. 73-635.000.
Rutherford, Lora E.: See—
Rutherford, Jerry, B1 4,625,557, Cl. 73-635.000.
Saadatmanesh, Vahid; and Loeb, Marvin P., to Trimedyn, Inc. Multi-head laser assembly. B1 5,387,211, Cl. 606-10.000.
Saarinen, Esko, to Valmet Paper Machinery Inc. Extended nip press with displaceable centre of gravity for the supporting force. B1 4,713,147, Cl. 162-358.300.
Silicon Systems, Inc.: See—
Yamasaki, Richard G., B1 4,803,445, Cl. 331-177.00R.
Sofamor Danek Group, Inc.: See—
Buchholz, Richard D., B1 5,383,454, Cl. 128-653.100.
Trimedyn, Inc.: See—
Saadatmanesh, Vahid; and Loeb, Marvin P., B1 5,387,211, Cl. 606-10.000.

Ultralite International Pty. Limited: See—
Wong, Siew E.; and Yang, Thien S., B1 5,426,344, Cl. 315-200.00R.
Valmet Paper Machinery Inc.: See—
Saarinen, Esko, B1 4,713,147, Cl. 162-358.300.
Wong, Siew E.; and Yang, Thien S., to Ultralite International Pty. Limited. Electronic ballasts. B1 5,426,344, Cl. 315-200.00R.
Yamasaki, Richard G., to Silicon Systems, Inc. Variable frequency oscillator. B1 4,803,445, Cl. 331-177.00R.
Yang, Thien S.: See—
Wong, Siew E.; and Yang, Thien S., B1 5,426,344, Cl. 315-200.00R.
Zawacki, Thomas S.: See—
Phillips, Benjamin A.; Zawacki, Thomas S.; and Marsala, Joseph, B1 5,367,884, Cl. 62-101.000.

LIST OF DESIGN PATENTEES

Accurate Engineering Precision Sheet Metal Fabrication and Machining, Inc.: See—
Woodard, Robert H., 377,052, Cl. D20-2.000.
Adams Mfg. Corp.: See—
Adams, William E., 377,076, Cl. D21-255.000.
Adams, William E., to Adams Mfg. Corp. Tent stake. 377,076, Cl. D21-255.000.
adidas AG: See—
Seydel, Roland; Diaz, Juan A.; Kächele, Bruno; and Burgess, Ian, 376,900, Cl. D2-968.000.
Akopyan, Arshak: See—
Petrosyan, Gagik; and Akopyan, Arshak, 376,955, Cl. D7-598.000.
Alpan, Inc.: See—
Chan, Alex, 377,106, Cl. D26-62.000.
Andrea, Douglas, to Andrea Electronics Corporation. Untethered communications/media handset. 377,023, Cl. D14-218.000.
Andrea, Douglas, to Andrea Electronics Corporation. Tethered media/communication handset. 377,024, Cl. D14-218.000.
Andrea Electronics Corporation: See—
Andrea, Douglas, 377,023, Cl. D14-218.000.
Andrea, Douglas, 377,024, Cl. D14-218.000.
Arashima, Teruo: See—
Tashiro, Naoki; Ujita, Toshihiko; Arashima, Teruo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru, 377,046, Cl. D18-56.000.
Asahi Kogaku Kogyo Kabushiki Kaisha: See—
Hayashi, Tatsuyuki, 377,035, Cl. D16-209.000.
Matsushita, Takeshi, 377,034, Cl. D16-202.000.
Avar, Eric P.; and Cooper, Aaron A. C., to Nike, Inc. Portion of a shoe upper. 376,901, Cl. D2-972.000.
Avar, Eric P., to Nike, Inc. Element of a shoe midsole. 376,902, Cl. D2-977.000.
Azeez, Faye, Mechanical pencil with attached molded pencil grip. 377,050, Cl. D19-49.000.
BabySmart: See—
Zissu, Diane M., 376,972, Cl. D8-354.000.
Barnhill, Russell E. Portable kitchen cabinet. 376,933, Cl. D6-445.000.
Barriault, Ronald F.; and Boucher, Ronald, to Central Distributors, Inc. Wine dispenser. 376,949, Cl. D7-306.000.
Bartlett, Glenda: See—
Bartlett, Jerrold; and Bartlett, Glenda, 376,966, Cl. D8-11.000.
Bartlett, Jerrold; and Bartlett, Glenda. Hand-held digging implement. 376,966, Cl. D8-11.000.
Batki-Braun, Gabriel; and Heppenstall, Bernard, to Faversham Furniture Limited. Oval table. 376,934, Cl. D6-480.000.
Batki-Braun, Gabriel; and Heppenstall, Bernard, to Faversham Furniture Limited. Table. 376,936, Cl. D6-488.000.
BBA Holdings, Inc.: See—
Nourse, Aagie M. T., 376,935, Cl. D6-486.000.
Beaulieu, Jocelyn, to Global Upholstery Company. Chair. 376,924, Cl. D6-366.000.
Benetton Group S.p.A.: See—
Tranquilli, Eugenio, 376,929, Cl. D6-411.000.
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chaonong, to Lucent Technologies Inc. Portable telephone handset. 377,014, Cl. D14-138.000.
Black & Decker Inc.: See—
Rorke, Anthony B., 376,951, Cl. D7-386.000.
Blanc, Jean P., to Compagnie Méditerranéenne de Cafés. Canister. 376,958, Cl. D7-612.000.
Boda Nova International AB: See—
Persson-Melin, Signe, 376,961, Cl. D7-649.000.
Boes, Barry S.: See—
Cuteri, Anthony W.; Boes, Barry S.; and Heinsen, Arturo, 377,026, Cl. D14-257.000.
Bonaddio, Vincenzo A.; and De Jesus Munoz Contreras, Jose, to Foamex L.P. Foldable mattress. 376,945, Cl. D6-596.000.

Borden, Mary. Two-dimensional picture frame. 376,913, Cl. D6-300.000.
Boucher, Ronald: See—
Barriault, Ronald F.; and Boucher, Ronald, 376,949, Cl. D7-306.000.
Brawne, Nicholas: See—
Nicklos, Carl F.; and Brawne, Nicholas, 377,008, Cl. D14-100.000.
Bridgestone Corporation: See—
Kukimoto, Takashi, 377,000, Cl. D12-147.000.
Brooker, Steven F.: See—
Spear, Kenneth J.; and Brooker, Steven F., 376,965, Cl. D8-10.000.
Brown, Peter A., to Industrial Molding Corporation. Gutter clip. 376,973, Cl. D8-395.000.
Bruno, Anthony T. Combination cutting gauge and guide. 376,988, Cl. D10-65.000.
Brunswick Corporation: See—
Tyler, Calvin; Moore, Prentice; and Robbins, Jack, 377,027, Cl. D15-4.000.
Bryant, Teddy R.: See—
England, Trent L.; Kuver, Walter D.; Bryant, Teddy R.; and Hanna, Shawn G., 377,006, Cl. D13-147.000.
Bungardt, Gabriele; Pedraza, Luis; and Dearborn, Tim, to Plantronics, Inc. Communications headset. 377,020, Cl. D14-205.000.
Burgess, Ian: See—
Seydel, Roland; Diaz, Juan A.; Kächele, Bruno; and Burgess, Ian, 376,900, Cl. D2-968.000.
Burks, Stephen G.: See—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106.000.
Burns, Richard H.; and Hutton, Allen J., to Seco Products Corporation. Bowl. 376,954, Cl. D7-560.000.
Caldwell, John, to Crown Leisure Products, Inc. Chair frame armrest. 376,938, Cl. D6-501.000.
California Design Studio Inc.: See—
Khanziz, Carlos A.; and Empakeris, Ruta Z., 377,040, Cl. D16-317.000.
Camfield, David K., to Roadmaster Corporation. Chopper bicycle. 376,997, Cl. D12-111.000.
Canon Information Systems, Inc.: See—
England, Trent L.; Kuver, Walter D.; Bryant, Teddy R.; and Hanna, Shawn G., 377,006, Cl. D13-147.000.
Casio Computer Co., Ltd.: See—
Komatsu, Tomoshige; and Ono, Junichi, 377,042, Cl. D18-2.000.
Takahata, Kenji, 377,043, Cl. D18-7.000.
Yamabe, Hideaki, 377,044, Cl. D18-12.000.
Central Distributors, Inc.: See—
Barriault, Ronald F.; and Boucher, Ronald, 376,949, Cl. D7-306.000.
Centre Clock Industry Co., Ltd.: See—
Moore, Shan-Ker, 376,984, Cl. D10-24.000.
Century Products Company: See—
Sedlack, Mark A., 376,919, Cl. D6-333.000.
Chan, Alex, to Alpan, Inc. Lamp. 377,106, Cl. D26-62.000.
Chan, Raymond: See—
Ford, Joseph E.; Jursich, Donald N.; and Chan, Raymond, 377,015, Cl. D14-149.000.
Chandler, David P., to Henredon Furniture Industries, Inc. Chair. 376,921, Cl. D6-334.000.
Chandler, David P., to Henredon Furniture Industries, Inc. Sofa. 376,926, Cl. D6-381.000.
Chang, Barney. Swimming fin. 377,073, Cl. D21-239.000.
Chang, Tim S. L.: See—
Tan, Haw-Chan; and Chang, Tim S. L., 377,007, Cl. D13-147.000.
Chen, Ting-Hsing, to Far Great Plastics Industrial Co., Ltd. Skate boot. 377,071, Cl. D21-226.000.
Chen, Waterson. Tube clamp. 376,974, Cl. D8-396.000.
Chicago Pneumatic Tool Company: See—
Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, 376,969, Cl. D8-68.000.
Chida, Hiromi, to Seiko Instruments Inc. Printer. 377,045, Cl. D18-50.000.

- Chieko, Yotsuda: *See*—
Hiro, Tetsuo; Togasawa, Tetsuo; and Chieko, Yotsuda, 376,975, Cl. D9-302,000.
- Citizen Watch Co., Ltd.: *See*—
Ikeuchi, Marie, 376,985, Cl. D10-32,000.
- Coffey, B. Howard, to Coffey Marketing Corporation, Arrow rest support guide, 377,078, Cl. D22-107,000.
- Coffey Marketing Corporation: *See*—
Coffey, B. Howard, 377,078, Cl. D22-107,000.
- Coleman Company, Inc.: *See*—
Simpson, Jeffrey M., 376,907, Cl. D3-274,000.
- Colibri Corporation, Linden Division: *See*—
Levinger, Frederick N.; and LaBrecque, Brian, 376,981, Cl. D10-1,000.
- Compagnie Méditerranéenne de Cafés: *See*—
Blanc, Jean P., 376,958, Cl. D7-612,000.
- Cone, Michael L.: *See*—
Guyer, James T. M.; and Cone, Michael L., 377,049, Cl. D19-27,000.
- Contico International, Inc.: *See*—
Dickinson, Thomas; and Gale, Bradley D., 376,909, Cl. D3-281,000.
- Cook, Gordon, Sandal, 376,895, Cl. D2-916,000.
- Cooper, Aaron A. C.: *See*—
Avar, Eric P.; and Cooper, Aaron A. C., 376,901, Cl. D2-972,000.
- Cusco, Inc.: *See*—
Kain, James M., 376,917, Cl. D6-333,000.
- Cosmair, Inc.: *See*—
LoPreto, Vincent, 376,980, Cl. D9-542,000.
- Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., to Panda Project, The, Computer cabinet with extending speakers, 377,009, Cl. D14-106,000.
- Creative Manufacturing, Inc.: *See*—
Sullins, Patrick H.; and Jennings, Don M., 376,948, Cl. D6-601,000.
- Credle, Michael T., Sr. Clamshell table top, 376,939, Cl. D6-511,000.
- Crown Leisure Products, Inc.: *See*—
Caldwell, John, 376,938, Cl. D6-501,000.
- Cuteri, Anthony W.; Boes, Barry S.; and Heinsen, Arturo, to Motorola, Inc., Display panel for a selective call receiver, 377,026, Cl. D14-257,000.
- Czyzson, Sharon, Extender for attachment to a hospital operating room mayo stand, 376,943, Cl. D6-567,000.
- Dart Industries Inc.: *See*—
Ferris, Ian, 376,960, Cl. D7-629,000.
- Davidson, Thomas A., III, Combined container and lids, 376,979, Cl. D9-504,000.
- Davis, William C. Shrimp cleaning device, 376,963, Cl. D7-693,000.
- Dawes, Stephen J.: *See*—
Foshee, David L.; Dawes, Stephen J.; Rahimzadeh, Bahram B.; and Durkin, Jason R., 377,094, Cl. D24-143,000.
- Dearborn, Tim: *See*—
Bungardt, Gabriele; Pedraza, Luis; and Dearborn, Tim, 377,020, Cl. D14-205,000.
- De Jesus Munoz Contreras, Jose: *See*—
Bonaddio, Vincenzo A.; and De Jesus Munoz Contreras, Jose, 376,945, Cl. D6-596,000.
- Dentsply Research & Development Corp.: *See*—
Howe, Devon O., 377,099, Cl. D24-181,000.
- Design Specialties, Inc.: *See*—
Dunn, John W., 376,953, Cl. D7-349,000.
- Diaz, Juan A.: *See*—
Seydel, Roland; Diaz, Juan A.; Kächele, Bruno; and Burgess, Ian, 376,900, Cl. D2-968,000.
- Dickinson, Thomas; and Gale, Bradley D., to Contico International, Inc., Tool box, 376,909, Cl. D3-281,000.
- Didier, Emmanuel R. Threaded funnel, 377,031, Cl. D15-150,000.
- Dieu, Randy, to Dieu, Randy, Clock, 376,983, Cl. D10-22,000.
- DiPasquale, Charles J., to Smartel, Inc., Combined ceiling fan mounting canopy, motor and switch housing and blade irons unit, 377,084, Cl. D23-411,000.
- DiRocco, Anthony, Combined key holder, picture display and container, 376,904, Cl. D3-208,000.
- Drake, Johannes, Clamping gun, 376,970, Cl. D8-72,000.
- Dunn, John W., to Design Specialties, Inc., Dish, 376,953, Cl. D7-349,000.
- Dunn, Michael T. Garage mat with adjustable tire indicator, 376,944, Cl. D6-582,000.
- Durkin, Jason R.: *See*—
Foshee, David L.; Dawes, Stephen J.; Rahimzadeh, Bahram B.; and Durkin, Jason R., 377,094, Cl. D24-143,000.
- Ebert, Fred, IV stand handle, 377,092, Cl. D24-128,000.
- Egan, Matthew V.: *See*—
McLeod, Gavin T.; and Egan, Matthew V., 377,029, Cl. D15-139,000.
- Eicke, Eberhard: *See*—
Eicke, Erika B.; and Eicke, Eberhard, 376,976, Cl. D9-418,000.
- Eicke, Erika B.; and Eicke, Eberhard, Collapsible box for a doll, 376,976, Cl. D9-418,000.
- Empakeris, Ruta Z.: *See*—
Khantzis, Carlos A.; and Empakeris, Ruta Z., 377,040, Cl. D16-317,000.
- England, Trent L.; Kuver, Walter D.; Bryant, Teddy R.; and Hanna, Shawn G., to Canon Information Systems, Inc., Network adaptor, 377,006, Cl. D13-147,000.
- Enpac Corporation: *See*—
Milliken, John O., 376,977, Cl. D9-431,000.
- Entrup, Richard P.: *See*—
Silvers, Kerry W.; and Entrup, Richard P., 376,978, Cl. D9-434,000.
- Episceno, Joe, III, Smoke generating automobile alarm unit, 376,993, Cl. D10-106,000.
- Esel International Company Limited: *See*—
Lee, Lan-Yan, 377,057, Cl. D21-48,000.
- Fabrique Nationale Nouvelle Herstal: *See*—
Predazzer, René, 377,077, Cl. D22-104,000.
- Far Great Plastics Industrial Co., Ltd.: *See*—
Chen, Ting-Hsing, 377,071, Cl. D21-226,000.
- Faucher, Claude: *See*—
Soucy, Gilles; Watelle, Jean; and Faucher, Claude, 376,996, Cl. D12-7,000.
- Faversham Furniture Limited: *See*—
Batki-Braun, Gabriel; and Heppenstall, Bernard, 376,934, Cl. D6-480,000.
- Batki-Braun, Gabriel; and Heppenstall, Bernard, 376,936, Cl. D6-488,000.
- Ferris, Ian, to Dart Industries Inc., Salad bowl, 376,960, Cl. D7-629,000.
- Fewchuk, Michael A., to Sebel Furniture Limited, Desk, 376,931, Cl. D6-425,000.
- Fluke Corporation: *See*—
McCain, George L., 376,989, Cl. D10-78,000.
- Foamex L.P.: *See*—
Bonaddio, Vincenzo A.; and De Jesus Munoz Contreras, Jose, 376,945, Cl. D6-596,000.
- Ford, Joseph E.; Jursich, Donald N.; and Chan, Raymond, to Jing Mei Industrial Holdings, Ltd., Shower speaker telephone handset, 377,015, Cl. D14-149,000.
- Ford, William K., and Fuligni, Matthew R., to Little Tikes Company, The, Playground activity apparatus, 377,074, Cl. D21-243,000.
- Foshee, David L.; Dawes, Stephen J.; Rahimzadeh, Bahram B.; and Durkin, Jason R., to Pilling Weck Incorporated, Clip applicator handle, 377,094, Cl. D24-143,000.
- Fratelli Guzzini S.p.A.: *See*—
Pasini, Ennio; and Mattei, Maurizio, 376,990, Cl. D10-91,000.
- Frederiksen, Jesper B., to INTERLEGO AG, Tumbler, 377,060, Cl. D21-108,000.
- Freese, Theodore B.; Hinzmann, Gregory S.; and Schubert, Angelika I., to Gerry Baby Products Company, Baby monitor receiver, 376,991, Cl. D10-104,000.
- Fuji, Mitsunari: *See*—
Usui, Shigeo; and Fujii, Mitsunari, 377,010, Cl. D14-126,000.
- Fuligni, Matthew R.: *See*—
Ford, William K.; and Fuligni, Matthew R., 377,074, Cl. D21-243,000.
- Fuller, Kevin S. Combined flexible pickup tool components, 376,967, Cl. D8-14,000.
- Gabriel, Richard, to Matrix Toys, Ltd., Dome for ball and rod toy construction set, 377,061, Cl. D21-108,000.
- Gabriel, Richard, to Matrix Toys, Ltd., Cavity for ball and rod toy construction set, 377,062, Cl. D21-108,000.
- Gale, Bradley D.: *See*—
Dickinson, Thomas; and Gale, Bradley D., 376,909, Cl. D3-281,000.
- Gameau, Louis, to Louis Gameau Sports Inc., Hinge end of eyeglass temple, 377,041, Cl. D16-335,000.
- Gastro-Gnomes, Inc.: *See*—
Noreika, Robert A., 377,054, Cl. D20-40,000.
- Gerry Baby Products Company: *See*—
Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 376,918, Cl. D6-333,000.
- Gerry Baby Products Company: *See*—
Freese, Theodore B.; Hinzmann, Gregory S.; and Schubert, Angelika I., 376,991, Cl. D10-104,000.
- Geschwender, Robert C. Measuring instrument, 376,987, Cl. D10-52,000.
- Gilman, Byron L.: *See*—
Olson, Kenneth E.; Gilman, Byron L.; Reiter, Thomas M.; and Luther, James W., 377,097, Cl. D24-168,000.
- Giumarra, John, Religious statue cassette player, 377,017, Cl. D14-164,000.
- Gladieux, Bernard L., Jr. Massage device, 377,100, Cl. D24-211,000.
- Global Upholstery Company: *See*—
Beaulieu, Jocelyn, 376,924, Cl. D6-366,000.
- Golo Chang Company Ltd.: *See*—
Lin, Ching-fang, 377,005, Cl. D13-134,000.
- Goosman, Charles L.; and Goosman, Cheryl L., Combined golf club and level, 377,066, Cl. D21-214,000.
- Goosman, Cheryl L.: *See*—
Goosman, Charles L.; and Goosman, Cheryl L., 377,066, Cl. D21-214,000.
- Gornet, Timothy J. Tortilla shell, 376,893, Cl. D11-122,000.
- Goss, Lorane C., Jr., to Mikron Industries, Window component extrusion, 377,101, Cl. D25-124,000.
- Groshans, Joseph: *See*—
Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, 376,969, Cl. D8-68,000.
- Gurbsiz, Carl, Doll, 377,064, Cl. D21-166,000.
- Gurrola, Paul, Golf putter grip, 377,070, Cl. D21-222,000.
- Guyer, James T. M.; and Cone, Michael L., Document case, 377,049, Cl. D19-27,000.
- Hagan, Virginia B.: *See*—
Zigelboim, Ilan; and Hagan, Virginia B., 376,911, Cl. D4-122,000.
- Halo Sports and Safety, Inc.: *See*—
Leonardi, Peter F., 377,036, Cl. D16-304,000.
- Hamasaki, Yuji: *See*—
Tashiro, Naoki; Ujita, Toshihiko; Arashima, Tetsuo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru, 377,046, Cl. D18-56,000.

- Hanna, Shawn G.: *See*—
England, Trent L.; Kuver, Walter D.; Bryant, Teddy R.; and Hanna, Shawn G., 377,006, Cl. D13-147,000.
- Harris, Johnel, Portable shade, 376,903, Cl. D3-5,000.
- Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, to Yokohama Rubber Co., Ltd., The, Automobile tire, 376,999, Cl. D12-147,000.
- Hayashi, Tatsuyuki, to Asahi Kogaku Kogyo Kabushiki Kaisha, 35 mm camera, 377,035, Cl. D16-209,000.
- Heinsen, Arturo: *See*—
Cuteri, Anthony W.; Boes, Barry S.; and Heinsen, Arturo, 377,026, Cl. D14-257,000.
- Henley, Michael E., to Lanard Toys Limited, Flying toy, 377,058, Cl. D21-83,000.
- Henredon Furniture Industries, Inc.: *See*—
Chandler, David P., 376,921, Cl. D6-334,000.
- Chandler, David P., 376,926, Cl. D6-381,000.
- Heppenstall, Bernard: *See*—
Batki-Braun, Gabriel; and Heppenstall, Bernard, 376,934, Cl. D6-480,000.
- Batki-Braun, Gabriel; and Heppenstall, Bernard, 376,936, Cl. D6-488,000.
- Hibner, Harry P., Jr.: *See*—
Hibner, Peggie (Margaret) C.; and Hibner, Harry P., Jr., 377,103, Cl. D26-23,000.
- Hibner, Peggie (Margaret) C.; and Hibner, Harry P., Jr., Candle topper, 377,103, Cl. D26-23,000.
- Hieber, Marilyn M. Porch swing, 376,922, Cl. D6-347,000.
- Higashibata, Toru: *See*—
Inoue, Takashi; and Higashibata, Toru, 377,011, Cl. D14-126,000.
- High, Randal W. Golf head cover, 377,069, Cl. D21-221,000.
- Hill, Tiffany A. Infant play pillow, 376,947, Cl. D6-599,000.
- Hinzmann, Gregory S.: *See*—
Freese, Theodore B.; Hinzmann, Gregory S.; and Schubert, Angelika I., 376,991, Cl. D10-104,000.
- Hiro, Tetsuo; Togasawa, Tetsuo; and Chieko, Yotsuda, to Shiseido Company, Ltd., Cosmetic tube, 376,975, Cl. D9-302,000.
- Hon Hai Precision Ind. Co., Ltd.: *See*—
Tan, Haw-Chan; and Chang, Tim S. L., 377,007, Cl. D13-147,000.
- Hoover Universal, Inc.: *See*—
Silvers, Kerry W.; and Entrup, Richard P., 376,978, Cl. D9-434,000.
- Hotaling, Bryan R.: *See*—
Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 376,918, Cl. D6-333,000.
- Howard, Greg: *See*—
Wiens, Terry; and Howard, Greg, 377,067, Cl. D21-219,000.
- Howe, Devon O., to Dentsply Research & Development Corp., Color guide for artificial teeth, 377,099, Cl. D24-181,000.
- Hsu, Chao-Chuan; Wang, Sun-Yu; and Liao, Yee-Chang, Computer desk, 376,932, Cl. D6-425,000.
- Hsu, Hung-Chi, Tool box, 376,908, Cl. D3-274,000.
- Hutton, Allen J.: *See*—
Burns, Richard H.; and Hutton, Allen J., 376,954, Cl. D7-560,000.
- Ikeuchi, Marie, to Citizen Watch Co., Ltd., Wrist watch with bracelet, 376,985, Cl. D10-32,000.
- ILC Technology, Inc.: *See*—
Roberts, Roy D., 377,104, Cl. D26-24,000.
- Ilejay, Patrick L., to Leon Opseth, Surfboard with transparent window, 377,072, Cl. D21-236,000.
- Industrial Molding Corporation: *See*—
Brown, Peter A., 376,973, Cl. D8-395,000.
- Inoue, Takashi; and Higashibata, Toru, to Matsushita Electric Industrial Co., Ltd., Television receiver, 377,011, Cl. D14-126,000.
- INTERLEGO AG: *See*—
Frederiksen, Jesper B., 377,060, Cl. D21-108,000.
- Iomega Corporation: *See*—
Nicklos, Carl F.; and Brawne, Nicholas, 377,008, Cl. D14-100,000.
- Ishizawa, Shoichi; and Nishioka, Atsushi, to Seiko Epson Corporation, Printing head for printer, 377,047, Cl. D18-56,000.
- Isono, Ric, to Sony Corporation, Headphone, 377,021, Cl. D14-205,000.
- Itoya of America, Ltd.: *See*—
Takemura, Shun, 377,051, Cl. D19-51,000.
- ITT Corporation: *See*—
Palmer, Gary L., 376,992, Cl. D10-106,000.
- Jennings, Don M.: *See*—
Sullins, Patrick H.; and Jennings, Don M., 376,948, Cl. D6-601,000.
- Jing Mei Industrial Holdings, Ltd.: *See*—
Ford, Joseph E.; Jursich, Donald N.; and Chan, Raymond, 377,015, Cl. D14-149,000.
- John Manufacturing Limited: *See*—
Yuen, Se K., 377,105, Cl. D26-38,000.
- Johnston, Ed E. Fish hook remover, 377,080, Cl. D22-149,000.
- Jones, Seth: *See*—
Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, 376,969, Cl. D8-68,000.
- Jones, Thomas J. Potty step, 376,923, Cl. D6-349,000.
- Jursich, Donald N.: *See*—
Ford, Joseph E.; Jursich, Donald N.; and Chan, Raymond, 377,015, Cl. D14-149,000.
- Kächele, Bruno: *See*—
Seydel, Roland; Diaz, Juan A.; Kächele, Bruno; and Burgess, Ian, 376,900, Cl. D2-968,000.
- Kain, James M., to Cosco, Inc., Booster seat, 376,917, Cl. D6-333,000.
- Kasbekar, Pratod V.: *See*—
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Cha-onong, 377,014, Cl. D14-138,000.
- Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, to Chicago Pneumatic Tool Company, Pistol handle pulse tool, 376,969, Cl. D8-68,000.
- Khantzis, Carlos A.; and Empakeris, Ruta Z., to California Design Studio Inc., Eyeglasses, 377,040, Cl. D16-317,000.
- Kim, Kyung T., to LG Industrial Systems Co., Ltd., Grinder, 376,968, Cl. D8-62,000.
- Kimpex, Inc.: *See*—
Soucy, Gilles; Watelle, Jean; and Faucher, Claude, 376,996, Cl. D12-7,000.
- Komamiya, Yoko: *See*—
Nagano, Katsumi; and Komamiya, Yoko, 377,019, Cl. D14-191,000.
- Komatsu, Tomoshige; and Ono, Junichi, to Casio Computer Co., Ltd., Electronic calculator having the functions of telephone book, address book, calendar, schedule book and memo book, 377,042, Cl. D18-2,000.
- Kotkosky, Stan, Desktop podium, 376,930, Cl. D6-419,000.
- Kubota, Mineo; and Satou, Masayoshi, to Nisca Corporation, TV camera, 377,033, Cl. D16-202,000.
- Kukimoto, Takashi, to Bridgestone Corporation, Automobile tire, 377,000, Cl. D12-147,000.
- Kuramochi, Izumi: *See*—
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,999, Cl. D12-147,000.
- Kuver, Walter D.: *See*—
England, Trent L.; Kuver, Walter D.; Bryant, Teddy R.; and Hanna, Shawn G., 377,006, Cl. D13-147,000.
- LaBrecque, Brian: *See*—
Levinger, Frederick N.; and LaBrecque, Brian, 376,981, Cl. D10-1,000.
- Lacy, Christopher A., to Pearl Baths, Inc., Whirlpool tub, 377,082, Cl. D23-277,000.
- Lanard Toys Limited: *See*—
Henley, Michael E., 377,058, Cl. D21-83,000.
- Larsson, Eleonore: *See*—
Ludvigsson, Harry; and Larsson, Eleonore, 376,962, Cl. D7-686,000.
- Larws, Peter, Construction game, 377,059, Cl. D21-108,000.
- Lee, Gary C. J. Aid for artificial respiration, 377,090, Cl. D24-110,400.
- Lee, Lan-Yan, to Esel International Company Limited, Electronic game housing, 377,057, Cl. D21-48,000.
- Lenox Electronics Corp.: *See*—
Zeitman, Josh, 377,016, Cl. D14-151,000.
- Leon Opseth: *See*—
Ilejay, Patrick L., 377,072, Cl. D21-236,000.
- Leonardi, Peter F., to Halo Sports and Safety, Inc., Sports eyewear, 377,036, Cl. D16-304,000.
- Leu, Carl W., to Poli-Auto, Inc., Imitation eagle antenna, 377,025, Cl. D14-230,000.
- Levinger, Frederick N.; and LaBrecque, Brian, to Colibri Corporation, Linden Division, Clock, 376,981, Cl. D10-1,000.
- Lewy, Joann, Sifter, 376,964, Cl. D8-1,000.
- LG Industrial Systems Co., Ltd.: *See*—
Kim, Kyung T., 376,968, Cl. D8-62,000.
- Liao, Yee-Chang: *See*—
Hsu, Chao-Chuan; Wang, Sun-Yu; and Liao, Yee-Chang, 376,932, Cl. D6-425,000.
- Lin, Ching-fang, to Golo Chang Company Ltd., Lamp socket, 377,005, Cl. D13-134,000.
- Lipshultz, Alfred J.; and Lipshultz, Mitchell, to Lipshultz, Alfred J. Water treatment cabinet, 377,081, Cl. D23-207,000.
- Lipshultz, Mitchell: *See*—
Lipshultz, Alfred J.; and Lipshultz, Mitchell, 377,081, Cl. D23-207,000.
- Little Tikes Company, The: *See*—
Ford, William K.; and Fuligni, Matthew R., 377,074, Cl. D21-243,000.
- Temple, Kenneth D.; and Walter, Christopher G., 377,075, Cl. D21-244,000.
- Logan, Haskell R. Standing frame for gift wrapping paper, 376,940, Cl. D6-520,000.
- Logitech S.A.: *See*—
Salinas, Ricardo, 377,056, Cl. D21-48,000.
- LoPreto, Vincent, to Cosmair, Inc., Combined container and cap, 376,980, Cl. D9-542,000.
- Lorenzana, Moises B.; and Lorenzana, Vance A., Lap tray, 376,928, Cl. D6-406,000.
- Lorenzana, Vance A.: *See*—
Lorenzana, Moises B.; and Lorenzana, Vance A., 376,928, Cl. D6-406,000.
- Louis Gameau Sports Inc.: *See*—
Gameau, Louis, 377,041, Cl. D16-335,000.
- Lown, Aaron: *See*—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106,000.
- Lucent Technologies Inc.: *See*—

- Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chao-nong, 377,014, Cl. D14-138.000.
- Ludvigsson, Harry; and Larsson, Eleonore. Oven-tongs. 376,962, Cl. D7-686.000.
- Luther, James W.: See—
Olson, Kenneth F.; Gilman, Byron L.; Reiter, Thomas M.; and Luther, James W., 377,097, Cl. D24-168.000.
- Martin, Patricia A.: See—
Martin, Ronald G.; and Martin, Patricia A., 377,001, Cl. D12-161.000.
- Martin, Ronald G.; and Martin, Patricia A. Sliding fifth wheel unit. 377,001, Cl. D12-161.000.
- Matrix Toys, Ltd.: See—
Gabriel, Richard, 377,061, Cl. D21-108.000.
- Gabriel, Richard, 377,062, Cl. D21-108.000.
- Matsushita Electric Industrial Co., Ltd.: See—
Inoue, Takashi; and Higashibata, Toru, 377,011, Cl. D14-126.000.
- Mori, Masakazu; and Senda, Tamotsu, 377,013, Cl. D14-129.000.
- Nagano, Katsumi; and Komamiya, Yuko, 377,019, Cl. D14-191.000.
- Usui, Shigeo; and Fujii, Mitsunari, 377,010, Cl. D14-126.000.
- Matsushita, Takeshi; to Asahi Kogaku Kogyo Kabushiki Kaisha. Digital camera. 377,034, Cl. D16-202.000.
- Mattei, Maurizio: See—
Pasini, Ennio; and Mattei, Maurizio, 376,990, Cl. D10-91.000.
- Matthes, Robert W.: See—
Munoz, Raul; Welsh, Patrick R.; and Matthes, Robert W., 376,941, Cl. D6-525.000.
- Maxim, Michael. Portable seat tote. 376,946, Cl. D6-596.000.
- McCain, George L., to Fluke Corporation. Graphical test instrument. 376,989, Cl. D10-78.000.
- McDowell Bros.: See—
McDowell, Philip R.; McDowell, Robert W.; and McDowell, Matthew F., 376,916, Cl. D6-317.000.
- McDowell, Matthew F.: See—
McDowell, Philip R.; McDowell, Robert W.; and McDowell, Matthew F., 376,916, Cl. D6-317.000.
- McDowell, Philip R.; McDowell, Robert W.; and McDowell, Matthew F., to McDowell Bros. Garment hanger. 376,916, Cl. D6-317.000.
- McDowell, Robert W.: See—
McDowell, Philip R.; McDowell, Robert W.; and McDowell, Matthew F., 376,916, Cl. D6-317.000.
- McLeod, Gavin T.; and Egan, Matthew V. Drill bit finger. 377,029, Cl. D15-139.000.
- Michelson, Gary K. Spinal distractor. 377,093, Cl. D24-135.000.
- Michelson, Gary K., to Sofamor Danek Properties, Inc. Interbody spinal implant. 377,095, Cl. D24-155.000.
- Michelson, Gary K., to Sofamor Danek Properties, Inc. Interbody spinal implant. 377,096, Cl. D24-155.000.
- Mikron Industries: See—
Goss, Lorane C., Jr., 377,101, Cl. D25-124.000.
- Mikron Industries, Inc.: See—
Oliver, Teresa A., 377,102, Cl. D25-124.000.
- Milliken, John O., to Enpac Corporation. Safety containment housing for the storage of hazardous waste material. 376,977, Cl. D9-431.000.
- Minamidani, Kimiko, to Yamamoto Kogaku Co., Ltd. Swimming goggles. 377,039, Cl. D16-311.000.
- Monday, Ronald. Ice holding and draining basket. 377,028, Cl. D15-90.000.
- Moore, Prentice: See—
Tyler, Calvin; Moore, Prentice; and Robbins, Jack, 377,027, Cl. D15-4.000.
- Monroe, Shan-Ker, to Centre Clock Industry Co., Ltd. Wall clock. 376,984, Cl. D10-24.000.
- Mori, Masahiro; and Nagahama, Masahiko, to Yokohama Rubber Co., Ltd., The. Golf bag. 376,906, Cl. D3-255.000.
- Mori, Masakazu; and Senda, Tamotsu, to Matsushita Electric Industrial Co., Ltd. Television receiver with computer. 377,013, Cl. D14-129.000.
- Morimoto, Kenichi, to Yugenkaisha Keiei Vision Center. Device for use as a learning aid for conveying a user's voice to the user's ear. 377,098, Cl. D24-175.000.
- Morooka, Takashi, to Sony Corporation. Video camera. 377,032, Cl. D16-202.000.
- Motorola, Inc.: See—
Cuteri, Anthony W.; Boes, Barry S.; and Heinsen, Arturo, 377,026, Cl. D14-257.000.
- Moulinex S.A.: See—
Saltet, Philippe, 376,950, Cl. D7-309.000.
- Munoz, Raul; Welsh, Patrick R.; and Matthes, Robert W., to Selfix, Inc. Shower caddy. 376,941, Cl. D6-525.000.
- Munoz, Raul, to Selfix, Inc. Shower caddy. 376,942, Cl. D6-525.000.
- Murata, Norihiko: See—
Shimazu, Toshihiko; and Murata, Norihiko, 377,003, Cl. D12-223.000.
- Nagahama, Masahiko: See—
Mori, Masahiro; and Nagahama, Masahiko, 376,906, Cl. D3-255.000.
- Nagano, Katsumi; and Komamiya, Yuko, to Matsushita Electric Industrial Co., Ltd. Pager. 377,019, Cl. D14-191.000.
- NEC Corporation: See—
Suzuki, Masataka; and Yamaguchi, Shuji, 377,018, Cl. D14-191.000.
- Nicklos, Carl F.; and Brawne, Nicholas, to Iomega Corporation. Computer data storage device. 377,008, Cl. D14-100.000.
- Nifco Inc.: See—
Shimazu, Toshihiko; and Murata, Norihiko, 377,003, Cl. D12-223.000.
- Nike, Inc.: See—
Avar, Eric P.; and Cooper, Aaron A. C., 376,901, Cl. D2-972.000.
- Avar, Eric P., 376,902, Cl. D2-977.000.
- Paske, Joel L.; and Sell, James C., Jr., 376,897, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., 376,898, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., 376,899, Cl. D2-961.000.
- Nisca Corporation: See—
Kubota, Mineo; and Satou, Masayoshi, 377,033, Cl. D16-202.000.
- Nishioka, Atsushi: See—
Ishizawa, Shoichi; and Nishioka, Atsushi, 377,047, Cl. D18-56.000.
- Noreika, Robert A., to Gastro-Gnomes, Inc. Vertical holder for paper inserts. 377,054, Cl. D20-40.000.
- Norris, Daniel A. Carrier for supporting a beverage container in an automotive cup holder. 376,959, Cl. D7-619.000.
- Norris, J. Bernice. Garment straps retainer. 376,994, Cl. D11-218.000.
- Nourse, Aagie M. T., to BBA Holdings, Inc. Occasional table. 376,935, Cl. D6-486.000.
- Nuttall, Michael J.: See—
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chao-nong, 377,014, Cl. D14-138.000.
- O. Ames Co.: See—
Spear, Kenneth J.; and Brooker, Steven F., 376,965, Cl. D8-10.000.
- Oliver, Teresa A., to Mikron Industries, Inc. Window component extrusion. 377,102, Cl. D25-124.000.
- Olson, Kenneth F.; Gilman, Byron L.; Reiter, Thomas M.; and Luther, James W., to Survivalink Corporation. Defibrillator in soft-sided carrying bag. 377,097, Cl. D24-168.000.
- Olson, Todd J., to Rollerblade, Inc., Skate boot. 376,894, Cl. D2-904.000.
- Ono, Junichi: See—
Komatsu, Tomoshige; and Ono, Junichi, 377,042, Cl. D18-2.000.
- O'Rourke, Nicholas, to Reebok International Ltd. Repeat pattern of a shoe sole. 376,896, Cl. D2-953.000.
- Oslund, Carl J., to Oslund Design Incorporated. Rear projection screen. 377,012, Cl. D14-128.000.
- Oslund Design Incorporated: See—
Oslund, Carl J., 377,012, Cl. D14-128.000.
- Otis, Jon P.: See—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106.000.
- Otto, Michael. Camera slate clock. 376,982, Cl. D10-6.000.
- Pacheco De Carvalho, John M. Form to monitor rations of dairy cows. 377,048, Cl. D19-1.000.
- Palmer, Gary L., to ITT Corporation. Infrared beacon. 376,992, Cl. D10-106.000.
- Panda Project, The: See—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106.000.
- Parker, Robert M.: See—
Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 376,918, Cl. D6-333.000.
- Pasini, Ennio; and Mattei, Maurizio, to Fratelli Guzzini S.p.A. Kitchen scale. 376,990, Cl. D10-91.000.
- Paske, Joel L.; and Sell, James C., Jr., to Nike, Inc. Bladder for a shoe sole. 376,897, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., to Nike, Inc. Bladder for a shoe sole. 376,898, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., to Nike, Inc. Bladder for a shoe sole. 376,899, Cl. D2-961.000.
- Paus, Michael J., to Universal Furniture Industries, Inc. Seat. 376,925, Cl. D6-381.000.
- Pearl Baths, Inc.: See—
Lacy, Christopher A., 377,082, Cl. D23-277.000.
- Pedraza, Luis: See—
Bungardt, Gabriele; Pedraza, Luis; and Dearborn, Tim, 377,020, Cl. D14-205.000.
- Persson-Melin, Signe, to Boda Nova International AB. Knife. 376,961, Cl. D7-649.000.
- Petrosyan, Gagik; and Akopyan, Arshak. Combined bottles and stand. 376,955, Cl. D7-598.000.
- Pilling Weck Incorporated: See—
Foshee, David L.; Dawes, Stephen J.; Rahimzadeh, Bahram B.; and Durkin, Jason R., 377,094, Cl. D24-143.000.
- Pinder, Ernest R.; and Pinder, Ronna J. Combined miniature gun collection and display case. 376,927, Cl. D6-397.000.
- Pinder, Ronna J.: See—
Pinder, Ernest R.; and Pinder, Ronna J., 376,927, Cl. D6-397.000.
- Plantronics, Inc.: See—
Bungardt, Gabriele; Pedraza, Luis; and Dearborn, Tim, 377,020, Cl. D14-205.000.
- Poli-Auto, Inc.: See—
Lew, Carl W., 377,025, Cl. D14-230.000.
- Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., to Gerry Baby Products Company. Bath ring. 376,918, Cl. D6-333.000.
- Predazzer, René, to Fabrique Nationale Nouvelle Herstal. Pistol. 377,077, Cl. D22-104.000.
- Quimpex Limitee: See—
Soucy, Gilles; Watelle, Jean; and Faucher, Claude, 376,996, Cl. D12-7.000.

- R. P. Scherer Corporation: See—
Schurig, Gregory A.; and Williams, David G., 377,087, Cl. D24-104.000.
- Rahimzadeh, Bahram B.: See—
Foshee, David L.; Dawes, Stephen J.; Rahimzadeh, Bahram B.; and Durkin, Jason R., 377,094, Cl. D24-143.000.
- Rajan, Heidi A.: See—
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chao-nong, 377,014, Cl. D14-138.000.
- Rausch, Kevin, to Rubbermaid Commercial Products Inc. Food storage container lid. 376,952, Cl. D7-392.100.
- Ray Cook Golf Company: See—
Sutes, John T., III, 377,068, Cl. D21-220.000.
- Reebok International Ltd.: See—
O'Rourke, Nicholas, 376,896, Cl. D2-953.000.
- Reiter, Thomas M.: See—
Olson, Kenneth F.; Gilman, Byron L.; Reiter, Thomas M.; and Luther, James W., 377,097, Cl. D24-168.000.
- Respironics, Inc.: See—
Starr, Eric W.; Starr, John R.; and Walthour, Mary T., 377,089, Cl. D24-110.100.
- Ripponlea Australia Pty. Ltd.: See—
Smolarski, Morris, 377,083, Cl. D23-393.000.
- Roadmaster Corporation: See—
Camfield, David K., 376,997, Cl. D12-111.000.
- Robbins, Jack: See—
Tyler, Calvin; Moore, Prentice; and Robbins, Jack, 377,027, Cl. D15-4.000.
- Roberts, Roy D., to ILC Technology, Inc. Lamp with heat sink. 377,104, Cl. D26-24.000.
- Robinette, Christopher A.: See—
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chao-nong, 377,014, Cl. D14-138.000.
- Robinson, Paul. Ice fishing reel. 377,079, Cl. D22-137.000.
- Rollerblade, Inc.: See—
Olson, Todd J., 376,894, Cl. D2-904.000.
- Rorke, Anthony B., to Black & Decker Inc. Blender. 376,951, Cl. D7-386.000.
- Rossman, Jon R.: See—
Poulson, Keith L.; Parker, Robert M.; Rossman, Jon R.; and Hotaling, Bryan R., 376,918, Cl. D6-333.000.
- Rubbermaid Commercial Products Inc.: See—
Rausch, Kevin, 376,952, Cl. D7-392.100.
- Salinas, Ricardo, to Logitech S.A. Joystick. 377,056, Cl. D21-48.000.
- Saltet, Philippe, to Moulinex S.A. Electric coffeemaker. 376,950, Cl. D7-399.000.
- Satou, Masayoshi: See—
Kubota, Mineo; and Satou, Masayoshi, 377,033, Cl. D16-202.000.
- Schaffeld, John H.: See—
Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chao-nong, 377,014, Cl. D14-138.000.
- Schneebeli, Richard J., Jr.: See—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106.000.
- Schubert, Angelika I.: See—
Freese, Theodore B.; Hinzmann, Gregory S.; and Schubert, Angelika I., 376,991, Cl. D10-104.000.
- Schurig, Gregory A.; and Williams, David G., to R. P. Scherer Corporation. Softgel capsule. 377,087, Cl. D24-104.000.
- Schutz, Joseph J. No-pin hinge. 376,971, Cl. D8-327.000.
- Scott, Jack J., Sr. Instrument for administering medication to the nose. 377,091, Cl. D24-121.000.
- Sebel Furniture Limited: See—
Fechuk, Michael A., 376,931, Cl. D6-425.000.
- Seco Products Corporation: See—
Burns, Richard H.; and Hutton, Allen J., 376,954, Cl. D7-560.000.
- Sedlack, Mark A., to Century Products Company. Car seat base. 376,919, Cl. D6-333.000.
- Seiko Epson Corporation: See—
Ishizawa, Shoichi; and Nishioka, Atsushi, 377,047, Cl. D18-56.000.
- Uzawa, Yoshito; and Yasukawa, Naoki, 376,986, Cl. D10-38.000.
- Seiko Instruments Inc.: See—
Chida, Hiromi, 377,045, Cl. D18-50.000.
- Selfix, Inc.: See—
Munoz, Raul; Welsh, Patrick R.; and Matthes, Robert W., 376,941, Cl. D6-525.000.
- Sell, James C., Jr.: See—
Paske, Joel L.; and Sell, James C., Jr., 376,897, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., 376,898, Cl. D2-961.000.
- Paske, Joel L.; and Sell, James C., Jr., 376,899, Cl. D2-961.000.
- Senda, Tamotsu: See—
Mori, Masakazu; and Senda, Tamotsu, 377,013, Cl. D14-129.000.
- Seydel, Roland; Diaz, Juan A.; Kächele, Bruno; and Burgess, Ian, to adidas AG. Outsole cushion. 376,900, Cl. D2-968.000.
- Sharp, Darren. Insulated jacket for beverage container. 376,956, Cl. D7-607.000.
- Sharp, Darren. Insulated jacket for beverage container. 376,957, Cl. D7-607.000.
- Shields, Robert L.: See—
Veach, Ben G.; and Shields, Robert L., 376,995, Cl. D11-216.000.
- Shimazu, Toshihiko; and Murata, Norihiko, to Nifco Inc. Window holder for a vehicle. 377,003, Cl. D12-223.000.
- Shiseido Company, Ltd.: See—
Hiro, Tetsuo; Togasawa, Tetsuo; and Chieko, Yotsuda, 376,975, Cl. D9-302.000.
- Silvers, Kerry W.; and Entrup, Richard P., to Hoover Universal, Inc. Pair of outwardly ribbed handgrips for a container. 376,978, Cl. D9-434.000.
- Simpson, Jeffrey M., to Coleman Company, Inc., The. Case for a portable shower. 376,907, Cl. D3-274.000.
- Sisler, Constance R. Toy. 377,063, Cl. D21-161.000.
- Skalka, Gerald P., to Victor Stanley, Inc. End frame for a bench. 376,937, Cl. D6-492.000.
- Smart Products, Inc.: See—
Wood, Gary M., 376,920, Cl. D6-333.000.
- Smartel, Inc.: See—
DiPasquale, Charles J., 377,084, Cl. D23-411.000.
- Smith, Bruce: See—
Crane, Stanford W., Jr.; Smith, Bruce; Lown, Aaron; Otis, Jon P.; Schneebeli, Richard J., Jr.; and Burks, Stephen G., 377,009, Cl. D14-106.000.
- Smolarski, Morris, to Ripponlea Australia Pty. Ltd. Floor register grille. 377,083, Cl. D23-393.000.
- Sofamor Danek Properties, Inc.: See—
Michelson, Gary K., 377,095, Cl. D24-155.000.
- Michelson, Gary K., 377,096, Cl. D24-155.000.
- Sony Corporation: See—
Isono, Rie, 377,021, Cl. D14-205.000.
- Morooka, Takashi, 377,032, Cl. D16-202.000.
- Takahashi, Hitoshi, 377,022, Cl. D14-214.000.
- Soofi, Khurshid A. Athletic ball. 377,065, Cl. D21-204.000.
- Soucy, Gilles; Watelle, Jean; and Faucher, Claude, to Kimpex, Inc.; and Quimpex Limitee. Track for a vehicle. 376,996, Cl. D12-7.000.
- Spear, James J. Sand bag filling device. 377,030, Cl. D15-145.000.
- Spear, Kenneth J.; and Brooker, Steven F., to O. Ames Co. Folding handle for a sleigh shovel. 376,965, Cl. D8-10.000.
- Spooner, Jeffrey: See—
Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, 376,969, Cl. D8-68.000.
- Starr, Eric W.; Starr, John R.; and Walthour, Mary T., to Respironics, Inc. Respiratory mask facial seal. 377,089, Cl. D24-110.100.
- Starr, John R.: See—
Starr, Eric W.; Starr, John R.; and Walthour, Mary T., 377,089, Cl. D24-110.100.
- Stein, Arnold J. Bathing brush. 376,912, Cl. D4-127.000.
- Sutes, John T., III, to Ray Cook Golf Company. Golf club head. 377,068, Cl. D21-220.000.
- Stolt, Jill L. Combined eye wear and flexible strap temples. 377,037, Cl. D16-306.000.
- Stotsky, Michael. Rear dropout for bicycle. 376,998, Cl. D12-117.000.
- Sullins, Patrick H.; and Jennings, Don M., to Creative Manufacturing, Inc. Combined lap pillow and book support. 376,948, Cl. D6-601.000.
- Survivalink Corporation: See—
Olson, Kenneth F.; Gilman, Byron L.; Reiter, Thomas M.; and Luther, James W., 377,097, Cl. D24-168.000.
- Suzuki, Masataka; and Yamaguchi, Shuji, to NEC Corporation. Pager. 377,018, Cl. D14-191.000.
- Suzuki, Toshihiko: See—
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,999, Cl. D12-147.000.
- Takahashi, Hitoshi, to Sony Corporation. Speaker box. 377,022, Cl. D14-214.000.
- Takahashi, Wataru: See—
Tashiro, Naoki; Ujita, Toshihiko; Arashima, Teruo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru, 377,046, Cl. D18-56.000.
- Takahata, Kenji, to Casio Computer Co., Ltd. Electronic calculator. 377,043, Cl. D18-7.000.
- Takei, Sadakazu: See—
Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramochi, Izumi; and Tokizaki, Hiroshi, 376,999, Cl. D12-147.000.
- Takemura, Shun, to Itoya of America, Ltd. Writing pen. 377,051, Cl. D19-51.000.
- Tan, Haw-Chan; and Chang, Tim S. L., to Hon Hai Precision Ind. Co., Ltd. Shielded connector. 377,007, Cl. D13-147.000.
- Tashiro, Naoki; Ujita, Toshihiko; Arashima, Teruo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru. Ink cartridge for printer. 377,046, Cl. D18-56.000.
- Temple, Kenneth D.; and Walter, Christopher G., to Little Tikes Company, The. Playground apparatus. 377,075, Cl. D21-244.000.
- Thompson, Danna D. Game board. 377,055, Cl. D21-31.000.
- Timms, Fred W. Container for article storage. 377,004, Cl. D12-423.000.
- Tinklepaugh, Mark: See—
Kazamaki, Yutaka; Groshans, Joseph; Spooner, Jeffrey; Jones, Seth; and Tinklepaugh, Mark, 376,969, Cl. D8-68.000.
- Togasawa, Tetsuo: See—
Hiro, Tetsuo; Togasawa, Tetsuo; and Chieko, Yotsuda, 376,975, Cl. D9-302.000.
- Tokizaki, Hiroshi: See—

- Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramoto, Izumi; and Tokizaki, Hiroshi, 376,999, Cl. D12-147.000.
 Tortarolo, George E., to Warner-Lambert Company, Tablet, 377,085, Cl. D24-101.000.
 Tortarolo, George E., to Warner-Lambert Company, Tablet, 377,086, Cl. D24-101.000.
 Tran, Nga V. Combined spoiler and vehicle spare tire cover, 377,002, Cl. D12-202.000.
 Tranquilli, Eugenio, to Benetton Group S.p.A. Garment display rack with movable frames, 376,929, Cl. D6-411.000.
 Tuchman, Stephan A. Combined cosmetic brush and perfume atomizer, 376,910, Cl. D4-114.000.
 Tyler, Calvin; Moore, Prentice; and Robbins, Jack, to Brunswick Corporation, Trolling motor foot pedal control, 377,027, Cl. D15-4.000.
 Ujita, Toshihiko: See—
 Tashiro, Naoki; Ujita, Toshihiko; Arashima, Teruo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru, 377,046, Cl. D18-56.000.
 Universal Furniture Industries, Inc.: See—
 Paus, Michael J., 376,925, Cl. D6-381.000.
 Usui, Shigeo; and Fujii, Mitsunari, to Matsushita Electric Industrial Co., Ltd. Television receiver, 377,010, Cl. D14-126.000.
 Uzawa, Yoshito, and Yasukawa, Naoki, to Seiko Epson Corporation, Wrist watch, 376,986, Cl. D10-38.000.
 van Quach, John H. Corner unit for a picture frame, 376,915, Cl. D6-300.000.
 Veach, Ben G.; and Shields, Robert L. Stirrup buckle, 376,995, Cl. D11-216.000.
 Victor Stanley, Inc.: See—
 Skalka, Gerald P., 376,937, Cl. D6-492.000.
 Volmer, Jason R. Fishing gear carrying pouch, 376,905, Cl. D3-221.000.
 Walter, Christopher G.: See—
 Temple, Kenneth D.; and Walter, Christopher G., 377,075, Cl. D21-244.000.
 Walthour, Mary T.: See—
 Starr, Eric W.; Starr, John R.; and Walthour, Mary T., 377,089, Cl. D24-110.100.
 Wang, Sun-Yu: See—
 Hsu, Chao-Chuan; Wang, Sun-Yu; and Liao, Yee-Chang, 376,932, Cl. D6-425.000.
 Warner-Lambert Company: See—
 Tortarolo, George E., 377,085, Cl. D24-101.000.
 Tortarolo, George E., 377,086, Cl. D24-101.000.
 Waszkiewicz, John C., III. Mirrored picture frame, 376,914, Cl. D6-300.000.
 Watelle, Jean: See—
 Soucy, Gilles; Watelle, Jean; and Faucher, Claude, 376,996, Cl. D12-7.000.
 Welsh, Patrick R.: See—
 Munoz, Raul; Welsh, Patrick R.; and Matthes, Robert W., 376,941, Cl. D6-525.000.
 Wiens, Terry; and Howard, Greg. Golf club, 377,067, Cl. D21-219.000.
 Williams, David G.: See—
 Schurig, Gregory A.; and Williams, David G., 377,087, Cl. D24-104.000.
 Williams, Douglas A. Display garment for the hand, 377,053, Cl. D20-33.000.
 Wood, Gary M., to Smart Products, Inc. Booster seat, 376,920, Cl. D6-333.000.
 Woodard, Robert H., to Accurate Engineering Precision Sheet Metal Fabrication and Machining, Inc. Vending machine, 377,052, Cl. D20-2.000.
 Yamabe, Hideaki, to Casio Computer Co., Ltd. Projection unit for an electronic calculator, 377,044, Cl. D18-12.000.
 Yamaguchi, Shuji: See—
 Suzuki, Masataka; and Yamaguchi, Shuji, 377,018, Cl. D14-191.000.
 Yamamoto, Hisashi: See—
 Tashiro, Naoki; Ujita, Toshihiko; Arashima, Teruo; Hamasaki, Yuji; Yamamoto, Hisashi; and Takahashi, Wataru, 377,046, Cl. D18-56.000.
 Yamamoto Kogaku Co., Ltd.: See—
 Minamidani, Kimiko, 377,039, Cl. D16-311.000.
 Yashiro, Tomoyuki, 377,038, Cl. D16-311.000.
 Yashiro, Tomoyuki, to Yamamoto Kogaku Co., Ltd. Swimming goggles, 377,038, Cl. D16-311.000.
 Yasukawa, Naoki: See—
 Uzawa, Yoshito; and Yasukawa, Naoki, 376,986, Cl. D10-38.000.
 Yoh, Chaonong: See—
 Biskup, Daniel R.; Kasbekar, Pratod V.; Nuttall, Michael J.; Rajan, Heidi A.; Robinette, Christopher A.; Schaffeld, John H.; and Yoh, Chaonong, 377,014, Cl. D14-138.000.
 Yokohama Rubber Co., Ltd., The: See—
 Hashimoto, Yoshimasa; Takei, Sadakazu; Suzuki, Toshihiko; Kuramoto, Izumi; and Tokizaki, Hiroshi, 376,999, Cl. D12-147.000.
 Mori, Masahiro; and Nagahama, Masahiko, 376,906, Cl. D3-255.000.
 Yuen, Se K., to John Manufacturing Limited. Rechargeable flashlight, 377,105, Cl. D26-38.000.
 Yugenkaisha Keiei Vision Center: See—
 Morimoto, Kenichi, 377,098, Cl. D24-175.000.
 Zeitman, Josh, to Lenox Electronics Corp. Telephone set, 377,016, Cl. D14-151.000.
 Zigelboim, Ilan; and Hagan, Virginia B. Paint roller frame, 376,911, Cl. D4-122.000.
 Zissu, Diane M., to BabySmart. Holder for baby wipes container, 376,972, Cl. D8-354.000.

LIST OF PLANT PATENTEES

- Barnes, J. Glenn; and Lambert, Marcus S., to Sunshine Foliage World. Aglaonema plant named Deborah, 9,775, Cl. P1t-88.100.
 Cunningham, Peter, to Peter Cunningham Family Trust, Trustees of the; and Sharyn Cunningham Family Trust, Trustees of the. Robinia plant named 'Lace Lady', 9,771, Cl. P1t-51.100.
 Floris AG: See—
 Utecht, Angelika, 9,773, Cl. P1t-87.120.
 Utecht, Angelika, 9,774, Cl. P1t-87.120.
 Glicenstein, Leon, to Yoder Brothers, Inc. Chrysanthemum plant named 'Dreamy Tracy', 9,772, Cl. P1t-82.200.
 Lambert, Marcus S.: See—
 Barnes, J. Glenn; and Lambert, Marcus S., 9,775, Cl. P1t-88.100.
 Lopez, Jose M. A., to Plantas de Navarra, S.A. Strawberry plant named 'Arena', 9,770, Cl. P1t-48.000.
 Maltagliati, Mark G. Hybrid Tea rose plant named 'Maljoanna', 9,769, Cl. P1t-18.000.
 Peter Cunningham Family Trust, Trustees of the: See—
 Cunningham, Peter, 9,771, Cl. P1t-51.100.
 Plantas de Navarra, S.A.: See—
 Lopez, Jose M. A., 9,770, Cl. P1t-48.000.
 Sharyn Cunningham Family Trust, Trustees of the: See—
 Cunningham, Peter, 9,771, Cl. P1t-51.100.
 Sunshine Foliage World: See—
 Barnes, J. Glenn; and Lambert, Marcus S., 9,775, Cl. P1t-88.100.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fismega', 9,773, Cl. P1t-87.120.
 Utecht, Angelika, to Floris AG. Geranium plant named 'Fisboogy', 9,774, Cl. P1t-87.120.
 Yoder Brothers, Inc.: See—
 Glicenstein, Leon, 9,772, Cl. P1t-82.200.

UMI

ISSUED DECEMBER 31, 1996

NOTE.—First number, class; second number, subclass; third number, patent number.

PI 115

334	5,589,011	CLASS 187	209	5,588,506	4	5,588,537	482	5,589,680	CLASS 257	259 R	5,588,687
561	5,589,012	CLASS 188	209	5,588,507	4	5,588,538	482	5,589,681	CLASS 258	259 R	5,588,687
18	5,589,060	CLASS 189	71.5	5,588,508	70.8	5,588,539	482	5,589,682	CLASS 259	259 R	5,588,687
19.4	5,589,061	CLASS 190	73.31	5,588,509	90	5,588,540	482	5,589,683	CLASS 260	259 R	5,588,687
35	5,589,062	CLASS 191	267	5,588,510	188	5,588,541	482	5,589,684	CLASS 261	259 R	5,588,687
71	5,589,013	CLASS 192	374	5,588,511	388	5,588,542	482	5,589,685	CLASS 262	259 R	5,588,687
73.1	5,589,014	CLASS 193	4	5,588,512	42	5,588,543	482	5,589,686	CLASS 263	259 R	5,588,687
87	5,589,015	CLASS 194	115	5,588,513	216	5,588,544	482	5,589,687	CLASS 264	259 R	5,588,687
94	5,589,016	CLASS 195	237	5,588,514	237	5,588,545	482	5,589,688	CLASS 265	259 R	5,588,687
184	5,589,017	CLASS 196	247	5,588,515	247	5,588,546	482	5,589,689	CLASS 266	259 R	5,588,687
185	5,589,018	CLASS 197	388	5,588,516	388	5,588,547	482	5,589,690	CLASS 267	259 R	5,588,687
219	5,589,019	CLASS 198	4 A	5,588,517	2	5,588,548	482	5,589,691	CLASS 268	259 R	5,588,687
231	5,589,020	CLASS 199	4 C	5,588,518	2	5,588,549	482	5,589,692	CLASS 269	259 R	5,588,687
231	5,589,021	CLASS 200	48.91	5,588,519	24	5,588,550	482	5,589,693	CLASS 270	259 R	5,588,687
245	5,589,022	CLASS 201	70.25	5,588,520	65	5,588,551	482	5,589,694	CLASS 271	259 R	5,588,687
268	5,589,023	CLASS 202	204	5,588,521	140	5,588,552	482	5,589,695	CLASS 272	259 R	5,588,687
286	5,589,024	CLASS 203	370.06	5,588,522	34	5,588,553	482	5,589,696	CLASS 273	259 R	5,588,687
304.4	5,589,025	CLASS 204	5,589,026	5,588,523	66	5,588,554	482	5,589,697	CLASS 274	259 R	5,588,687
306.6	5,589,027	CLASS 205	5,589,027	5,588,524	71	5,588,555	482	5,589,698	CLASS 275	259 R	5,588,687
344	5,589,028	CLASS 206	5,589,028	5,588,525	140	5,588,556	482	5,589,699	CLASS 276	259 R	5,588,687
44	5,589,029	CLASS 207	781.08	5,588,526	69.16	5,588,557	482	5,589,700	CLASS 277	259 R	5,588,687
370.21	5,589,030	CLASS 208	6 R	5,588,527	93	5,588,558	482	5,589,701	CLASS 278	259 R	5,588,687
7	5,589,031	CLASS 209	552	5,588,528	110	5,588,559	482	5,589,702	CLASS 279	259 R	5,588,687
65	5,589,032	CLASS 210	35	5,588,529	121.6	5,588,560	482	5,589,703	CLASS 280	259 R	5,588,687
76	5,589,033	CLASS 211	157.42	5,588,530	121.62	5,588,561	482	5,589,704	CLASS 281	259 R	5,588,687
84	5,589,034	CLASS 212	192.12	5,588,531	270	5,588,562	482	5,589,705	CLASS 282	259 R	5,588,687
111	5,589,035	CLASS 213	192.26	5,588,532	506	5,588,563	482	5,589,706	CLASS 283	259 R	5,588,687
232	5,589,036	CLASS 214	192.33	5,588,533	679	5,588,564	482	5,589,707	CLASS 284	259 R	5,588,687
245	5,589,037	CLASS 215	192.34	5,588,534	711	5,588,565	482	5,589,708	CLASS 285	259 R	5,588,687
358.3	5,589,038	CLASS 216	192.34	5,588,535	7	5,588,566	482	5,589,709	CLASS 286	259 R	5,588,687
34	5,589,039	CLASS 217	281	5,588,536	525	5,588,567	482	5,589,710	CLASS 287	259 R	5,588,687
46	5,589,040	CLASS 218	286	5,588,537	574.1	5,588,568	482	5,589,711	CLASS 288	259 R	5,588,687
480	5,589,041	CLASS 219	406	5,588,538	712	5,588,569	482	5,589,712	CLASS 289	259 R	5,588,687
42	5,589,042	CLASS 220	489	5,588,539	76	5,588,570	482	5,589,713	CLASS 290	259 R	5,588,687
44	5,589,043	CLASS 221	504	5,588,540	88	5,588,571	482	5,589,714	CLASS 291	259 R	5,588,687
86	5,589,044	CLASS 222	504	5,588,541	197	5,588,572	482	5,589,715	CLASS 292	259 R	5,588,687
122	5,589,045	CLASS 223	504	5,588,542	1	5,588,573	482	5,589,716	CLASS 293	259 R	5,588,687
157	5,589,046	CLASS 224	504	5,588,543	5	5,588,574	482	5,589,717	CLASS 294	259 R	5,588,687
300	5,589,047	CLASS 225	504	5,588,544	14	5,588,575	482	5,589,718	CLASS 295	259 R	5,588,687
50	5,589,048	CLASS 226	504	5,588,545	64	5,588,576	482	5,589,719	CLASS 296	259 R	5,588,687
51	5,589,049	CLASS 227	504	5,588,546	79	5,588,577	482	5,589,720	CLASS 297	259 R	5,588,687
293	5,589,050	CLASS 228	504	5,588,547	92	5,588,578	482	5,589,721	CLASS 298	259 R	5,588,687
370	5,589,051	CLASS 229	504	5,588,548	106	5,588,579	482	5,589,722	CLASS 299	259 R	5,588,687
383	5,589,052	CLASS 230	504	5,588,549	129	5,588,580	482	5,589,723	CLASS 300	259 R	5,588,687
11	5,589,053	CLASS 231	504	5,588,550	158	5,588,581	482	5,589,724	CLASS 301	259 R	5,588,687
46	5,589,054	CLASS 232	504	5,588,551	183	5,588,582	482	5,589,725	CLASS 302	259 R	5,588,687
124	5,589,055	CLASS 233	504	5,588,552	271	5,588,583	482	5,589,726	CLASS 303	259 R	5,588,687
170	5,589,056	CLASS 234	504	5,588,553	306	5,588,584	482	5,589,727	CLASS 304	259 R	5,588,687
178	5,589,057	CLASS 235	504	5,588,554	338.3	5,588,585	482	5,589,728	CLASS 305	259 R	5,588,687
51	5,589,058	CLASS 236	504	5,588,555	383.1	5,588,586	482	5,589,729	CLASS 306	259 R	5,588,687
52.1	5,589,059	CLASS 237	504	5,588,556	394	5,588,587	482	5,589,730	CLASS 307	259 R	5,588,687
67	5,589,060	CLASS 238	504	5,588,557	402.11	5,588,588	482	5,589,731	CLASS 308	259 R	5,588,687
87	5,589,061	CLASS 239	504	5,588,558	475.1	5,588,589	482	5,589,732	CLASS 309	259 R	5,588,687
135	5,589,062	CLASS 240	504	5,588,559	500	5,588,590	482	5,589,733	CLASS 310	259 R	5,588,687
266	5,589,063	CLASS 241	504	5,588,560	647	5,588,591	482	5,589,734	CLASS 311	259 R	5,588,687
420.1	5,589,064	CLASS 242	504	5,588,561	214 A	5,588,592	482	5,589,735	CLASS 312	259 R	5,588,687
25.13	5,589,065	CLASS 243	504	5,588,562	214 R	5,588,593	482	5,589,736	CLASS 313	259 R	5,588,687
65.4	5,589,066	CLASS 244	504	5,588,563	225	5,588,594	482	5,589,737	CLASS 314	259 R	5,588,687
135	5,589,067	CLASS 245	504	5,588,564	282	5,588,595	482	5,589,738	CLASS 315	259 R	5,588,687
141	5,589,068	CLASS 246	504	5,588,565	306	5,588,596	482	5,589,739	CLASS 316	259 R	5,588,687
1.5	5,589,069	CLASS 247	504	5,588,566	338.3	5,588,597	482	5,589,740	CLASS 317	259 R	5,588,687
6.4	5,589,070	CLASS 248	504	5,588,567	383.1	5,588,598	482	5,589,741	CLASS 318	259 R	5,588,687
6.8	5,589,071	CLASS 249	504	5,588,568	402.11	5,588,599	482	5,589,742	CLASS 319	259 R	5,588,687
18	5,589,072	CLASS 250	504	5,588,569	500	5,588,600	482	5,589,743	CLASS 320	259 R	5,588,687

CLASS 318			467	5,589,817	153.2	5,589,817	794	5,590,030	210	5,590,186	
139	5,589,743	506	5,589,818	153.2	5,589,818	794	5,590,030	210	5,590,186		
164	5,589,744	571	5,589,819	219	5,589,896	10	5,588,732	54	5,590,108		
254	5,589,745	572	5,589,820	223	5,589,897	10	5,588,733	77.2	5,590,109		
439	5,589,746	573	5,589,821	227	5,589,898	37	5,588,734	100	5,590,110		
468	5,589,747	583	5,589,822	245	5,589,899	61	5,588,735	116	5,590,111		
560	5,589,748	622	5,589,823			102	5,588,736	124	5,590,112		
564	5,589,749	628	5,589,824			106	5,588,737	270	5,590,113		
573	5,589,750	854.9	5,589,825	312	5,589,927	148	5,588,738	290	5,590,114		
701	5,589,751	901	5,589,827	5.01	5,589,928	184	5,588,739		5,590,115		
	5,589,752				5,589,929	205	5,588,740				
	5,589,753				5,589,930	221	5,588,741				
	5,589,754	20	5,589,828	33	5,589,931	267	5,588,742	218	5,590,118		
		67	5,589,829	39	5,589,932	291	5,588,743	225	5,590,119		
CLASS 320			110	5,589,830	73.1	5,589,933	298	5,588,744	236	5,590,120	
	5,589,755	159	5,589,831	218	5,589,934	405	5,588,745	248	5,590,121		
	5,589,756	161	5,589,832	328	5,589,935			253	5,590,122		
	5,589,757			339	5,589,936			254	5,590,123		
CLASS 322			195	5,589,833	345	5,589,937		258	5,590,124		
	5,589,758	354	5,589,834	352	5,589,938	15	5,590,032	260	5,590,125		
CLASS 323			357	5,589,835	375	5,589,939		290	5,590,126		
	5,589,759	359	5,589,836		5,589,940			329	5,590,127		
	5,589,760	387	5,589,837		5,589,941			349	5,590,128		
	5,589,761		5,589,838		5,589,942			376	5,590,129		
	5,589,762							394	5,590,130		
CLASS 324			713	5,589,839	449	5,589,948		397	5,590,131		
	5,589,763	718	5,589,840	451	5,589,949			461	5,590,132		
	5,589,764	760	5,589,841	455	5,589,950			462	5,590,133		
	5,589,765	820	5,589,842	473	5,589,951						
	5,589,766	860	5,589,843	483	5,589,952						
	5,589,768	909	5,589,844	498	5,589,953						
	5,589,769		5,589,845	518	5,589,954						
	5,589,770										
	5,589,771	8	5,589,846	9	5,589,955						
	5,589,772	98	5,589,847	15	5,589,956						
	5,589,773	102	5,589,848	13	5,589,957						
	5,589,774	126	5,589,849	124	5,589,960						
	5,589,775	132	5,589,850		5,589,961						
	5,589,776	136	5,589,851	133	5,589,970						
	5,589,777	147	5,589,852	196	5,589,971						
	5,589,778	150	5,589,853	214	5,589,972						
	5,589,779	161	5,589,854	290	5,589,973						
	5,589,780	173	5,589,855	345	5,589,975						
	5,589,781		5,589,856	362	5,589,976						
CLASS 326			174	5,589,857	375	5,589,977					
	5,589,782				5,589,978						
	5,589,783				5,589,979						
CLASS 327			14	5,589,858	478	5,589,980					
	5,589,784	19	5,589,859	529	5,589,981						
	5,589,785	22	5,589,860	565	5,589,982						
	5,589,786	28	5,589,861	566	5,589,983						
	5,589,787	26	5,589,862	603	5,589,984						
	5,589,788	46	5,589,863	608	5,589,985						
	5,589,789	75	5,589,864	684	5,589,986						
	5,589,790	87	5,589,865	701	5,589,987						
	5,589,791	102	5,589,866	752	5,589,988						
	5,589,792	111	5,589,867	785	5,589,989						
	5,589,793	171	5,589,868	799	5,589,990						
	5,589,794	213	5,589,869	856	5,589,991						
	5,589,795	237	5,589,870								
CLASS 330			133	5,589,871	45	5,589,994					
	5,589,796	12	5,589,872	18	5,589,995						
	5,589,797	15	5,589,873	73.03	5,589,996						
	5,589,798	72	5,589,874	77.14	5,589,997						
	5,589,799	143	5,589,875	85	5,589,999						
	5,589,800	164	5,589,876	96.5	5,590,000						
CLASS 331			186	5,589,877	97.02	5,590,001					
	5,589,801	223	5,589,878	98.07	5,590,002						
	5,589,802	229	5,589,879	99.12	5,590,003						
	5,589,803	300	5,589,880	103	5,590,004						
	4,803.445	340	5,589,881	105	5,590,005						
		379	5,589,882	109	5,590,007						
CLASS 332			405	5,589,883	126	5,590,008					
	5,589,805	416	5,589,884	135	5,590,009						
			Re 35.414								
CLASS 333			461	5,589,885							
	5,589,806	616	5,589,886	93	5,590,010						
	5,589,807	649	5,589,887	106	5,590,011						
		674	5,589,888	113	5,590,012						
		678	5,589,889	117	5,590,013						
		730	5,589,890	225	5,590,014						
		731	5,589,891	277	5,590,015						
CLASS 336			92	5,589,892	313	5,590,016					
	5,589,808	734	5,589,893	321.4	5,590,017						
CLASS 337					612	5,590,018					
	5,589,809			643	5,590,019						
CLASS 338			16	5,589,894	680	5,590,020					
	5,589,810	41	Re 35.416	681	5,590,021						
	5,589,811	46	5,589,896	683	5,590,022						
		76	5,589,962		5,590,023						
		46	5,589,960	684	5,590,024						
		88	5,589,959	695	5,590,025						
		119	5,589,963	704	5,590,026						
		140	5,589,964	732	5,590,027						
		165	5,589,965	737	5,590,028						
		194	5,589,966	760	5,590,029						
CLASS 340			309.15	5,589,812							
	5,589,813	118	5,589,813								
	5,589,814	140	5,589,814								
	5,589,815	165	5,589,815								
	5,589,816	194	5,589,816								
CLASS 362			54	5,588,732	54	5,588,732	54	5,588,732	54	5,588,732	
	5,588,732	77.2	5,588,733	100	5,588,734	116	5,588,735	124	5,588,736	270	5,588,737
	5,588,733	100	5,588,734	116	5,588,735	124	5,588,736	270	5,588,737	290	5,588,738
	5,588,734	116	5,588,735	124	5,588,736	270	5,588,737	290	5,588,738		5,588,739
	5,588,735	124	5,588,736	270	5,588,737	290	5,588,738		5,588,739		5,588,740
	5,588,736	270	5,588,737	290	5,588,738		5,588,739		5,588,740		5,588,741
	5,588,737	290	5,588,738		5,588,739		5,588,740		5,588,741		5,588,742
	5,588,738		5,588,739		5,588,740		5,588,741		5,588,742		5,588,743
	5,588,739		5,588,740		5,588,741		5,588,742		5,588,743		5,588,744
	5,588,740		5,588,741		5,588,742		5,588,743		5,588,744		5,588,745
	5,588,741		5,588,742		5,588,743		5,588,744		5,588,745		5,588,746
	5,588,742		5,588,743		5,588,744		5,588,745		5,588,746		5,588,747
	5,588,743		5,588,744		5,588,745		5,588,746		5,588,747		5,588,748
	5,588,744		5,588,745		5,588,746		5,588,747		5,588,748		5,588,749
	5,588,745		5,588,746		5,588,747		5,588,748		5,588,749		5,588,750
	5,588,746		5,588,747		5,588,748		5,588,749		5,588,750		5,588,751
	5,588,747		5,588,748		5,588,749		5,588,750		5,588,751		5,588,752
	5,588,748		5,588,749		5,588,750		5,588,751		5,588,752		5,588,753
	5,588,749		5,588,750		5,588,751		5,588,752		5,588,753		5,588,754
	5,588,750		5,588,751		5,588,752		5,588,753		5,588,754		5,588,755
	5,588,751		5,588,752		5,588,753		5,588,754		5,588,755		5,588,756
	5,588,752		5,588,753		5,588,754		5,588,755		5,588,756		5,588,757
	5,588,753		5,588,754		5,588,755		5,588,756		5,588,757		5,588,758
	5,588,754		5,588,755		5,588,756		5,588,757		5,588,758		5,588,759
	5,588,755		5,588,756		5,588,757		5,588,758		5,588,759		5,588,760
	5,588,756		5,588,757		5,588,758		5,588,759		5,588,760		5,588,761
	5,588,757		5,588,758		5,588,759		5,588,760		5,588,761		5,588,762
			5,588,759		5,588,760		5,588,761		5,588,762		5,588,763
			5,588,760		5,588,761		5,588,762		5,588,763		5,588,764
			5,588,761		5,588,762		5,588,763		5,588,764		5,588,765
			5,588,762		5,588,763		5,588,764		5,588,765		5,588,766
			5,588,763		5,588,764		5,588,765		5,588,766		5,588,767
			5,588,764		5,588,765		5,588,766		5,588,767		5,588,768
			5,588,765		5,588,766		5,588,767		5,588,768		5,588,769
			5,588,766		5,588,767		5,588,768		5,588,769		5,588,770
			5,588,767		5,588,768		5,588,769		5,588,770		5,588,771
			5,588,768		5,588,769		5,588,770		5,588,771		

CLASSIFICATION OF PATENTS

135	5,590,254	5,590,359	CLASS 411	147.1	5,589,174	421	5,589,271	5,589,339
141	5,590,255	5,590,360	482	5,588,788	208.1	5,589,175	425.6	5,589,340
167	5,590,260	5,590,361	CLASS 414	401	5,589,176	433	5,589,272	5,589,341
173	5,590,261	5,590,362	217	5,588,789	5,589,177	458	5,589,273	5,589,342
181	5,590,272	5,590,363	331	5,588,790	5,589,178	488.1	5,589,274	5,589,343
182.01	5,590,273	5,590,364	404	5,588,791	5,589,179	500	5,589,275	5,589,344
182.04	5,590,274	5,590,365	557	5,588,792	5,589,180	546	5,589,276	5,589,345
182.05	5,590,275	5,590,366	729	5,588,793	5,589,181	552	5,589,277	5,589,346
183.06	5,590,276	5,590,367	733	5,588,794	5,589,182	611	5,589,278	5,589,347
183.14	5,590,277	5,590,368	741	5,588,795	5,589,183	623	5,589,279	5,589,348
185.06	5,590,278	5,590,369	797.5	5,588,796	5,589,184	626	5,589,280	5,589,349
185.08	5,590,279	5,590,370	806	5,588,797	5,589,185	688	5,589,281	5,589,350
200.01	5,590,280	5,590,371	111	5,588,798	5,589,186	694 ML	5,589,282	5,589,351
200.02	5,590,281	5,590,372	211.2	5,588,799	5,589,187	694 R	5,589,283	5,589,352
200.03	5,590,282	5,590,373	CLASS 415	462	5,589,188	697	5,589,284	5,589,353
200.04	5,590,283	5,590,374	111	5,588,799	5,589,189	697	5,589,285	5,589,354
200.05	5,590,284	5,590,375	211.2	5,588,800	5,589,190	13	5,589,286	5,589,355
200.20	5,590,285	5,590,376	CLASS 416	497	5,589,191	34	5,589,287	5,589,356
204	5,590,286	5,590,377	24	5,588,801	5,589,192	13	5,589,288	5,589,357
209	5,590,287	5,590,378	46	5,588,802	5,589,193	34	5,589,289	5,589,358
241	5,590,288	5,590,379	186 R	5,588,803	5,589,194	96	5,589,290	5,589,359
250	5,590,289	5,590,380	223 R	5,588,804	5,589,195	99	5,589,291	5,589,360
289	5,590,290	5,590,381	CLASS 417	667	5,589,196	103	5,589,292	5,589,361
298	5,590,291	5,590,382	53	5,588,805	5,589,197	122	5,589,293	5,589,362
326	5,590,292	5,590,383	63	5,588,806	5,589,198	170	5,589,294	5,589,363
340	5,590,293	5,590,384	68	5,588,807	5,589,199	172	5,589,295	5,589,364
393	5,590,294	5,590,385	133	5,588,808	5,589,200	178	5,589,296	5,589,365
394	5,590,295	5,590,386	222.2	5,588,809	5,589,201	191	5,589,297	5,589,366
401	5,590,296	5,590,387	225	5,588,810	5,589,202	191	5,589,298	5,589,367
403	5,590,297	5,590,388	283	5,588,811	5,589,203	212	5,589,299	5,589,368
405	5,590,298	5,590,389	312	5,588,812	5,589,204	218	5,589,300	5,589,369
412	5,590,299	5,590,390	350	5,588,813	5,589,205	218	5,589,301	5,589,370
416	5,590,300	5,590,391	356	5,588,814	5,589,206	234	5,589,302	5,589,371
427	5,590,301	5,590,392	391	5,588,815	5,589,207	250	5,589,303	5,589,372
430	5,590,302	5,590,393	423.7	5,588,816	5,589,208	250	5,589,304	5,589,373
442	5,590,303	5,590,394	477.2	5,588,817	5,589,209	250	5,589,305	5,589,374
458	5,590,304	5,590,395	549	5,588,818	5,589,210	250	5,589,306	5,589,375
463	5,590,305	5,590,396	549	5,588,819	5,589,211	18	5,589,307	5,589,376
472	5,590,306	5,590,397	549	5,588,820	5,589,212	49	5,589,308	5,589,377
473	5,590,307	5,590,398	549	5,588,821	5,589,213	59	5,589,309	5,589,378
477	5,590,308	5,590,399	549	5,588,822	5,589,214	106	5,589,310	5,589,379
500	5,590,309	5,590,400	549	5,588,823	5,589,215	114	5,589,311	5,589,380
556	5,590,310	5,590,401	549	5,588,824	5,589,216	115	5,589,312	5,589,381
564	5,590,311	5,590,402	549	5,588,825	5,589,217	122	5,589,313	5,589,382
566	5,590,312	5,590,403	549	5,588,826	5,589,218	126	5,589,314	5,589,383
570	5,590,313	5,590,404	549	5,588,827	5,589,219	163	5,589,315	5,589,384
581	5,590,314	5,590,405	549	5,588,828	5,589,220	203	5,589,316	5,589,385
591	5,590,315	5,590,406	549	5,588,829	5,589,221	203	5,589,317	5,589,386
602	5,590,316	5,590,407	549	5,588,830	5,589,222	264	5,589,318	5,589,387
604	5,590,317	5,590,408	549	5,588,831	5,589,223	288.1	5,589,319	5,589,388
605	5,590,318	5,590,409	549	5,588,832	5,589,224	321	5,589,320	5,589,389
610	5,590,319	5,590,410	549	5,588,833	5,589,225	321	5,589,321	5,589,390
615	5,590,320	5,590,411	549	5,588,834	5,589,226	432	5,589,322	5,589,391
618	5,590,321	5,590,412	549	5,588,835	5,589,227	449	5,589,323	5,589,392
619	5,590,322	5,590,413	549	5,588,836	5,589,228	492	5,589,324	5,589,393
670	5,590,323	5,590,414	549	5,588,837	5,589,229	576	5,589,325	5,589,394
675	5,590,324	5,590,415	549	5,588,838	5,589,230	576	5,589,326	5,589,395
681	5,590,325	5,590,416	549	5,588,839	5,589,231	576	5,589,327	5,589,396
683	5,590,326	5,590,417	549	5,588,840	5,589,232	576	5,589,328	5,589,397
701	5,590,327	5,590,418	549	5,588,841	5,589,233	576	5,589,329	5,589,398
704	5,590,328	5,590,419	549	5,588,842	5,589,234	576	5,589,330	5,589,399
705	5,590,329	5,590,420	549	5,588,843	5,589,235	576	5,589,331	5,589,400
708	5,590,330	5,590,421	549	5,588,844	5,589,236	576	5,589,332	5,589,401
727	5,590,331	5,590,422	549	5,588,845	5,589,237	576	5,589,333	5,589,402
735	5,590,332	5,590,423	549	5,588,846	5,589,238	576	5,589,334	5,589,403
742	5,590,333	5,590,424	549	5,588,847	5,589,239	576	5,589,335	5,589,404
750	5,590,334	5,590,425	549	5,588,848	5,589,240	576	5,589,336	5,589,405
759	5,590,335	5,590,426	549	5,588,849	5,589,241	576	5,589,337	5,589,406
764	5,590,336	5,590,427	549	5,588,850	5,589,242	576	5,589,338	5,589,407
787	5,590,337	5,590,428	549	5,588,851	5,589,243	576	5,589,339	5,589,408
792	5,590,338	5,590,429	549	5,588,852	5,589,244	576	5,589,340	5,589,409
793	5,590,339	5,590,430	549	5,588,853	5,589,245	576	5,589,341	5,589,410
800	5,590,340	5,590,431	549	5,588,854	5,589,246	576	5,589,342	5,589,411
	5,590,341	5,590,432	549	5,588,855	5,589,247	576	5,589,343	5,589,412
	5,590,342	5,590,433	549	5,588,856	5,589,248	576	5,589,344	5,589,413
	5,590,343	5,590,434	549	5,588,857	5,589,249	576	5,589,345	5,589,414
	5,590,344	5,590,435	549	5,588,858	5,589,250	576	5,589,346	5,589,415
	5,590,345	5,590,436	549	5,588,859	5,589,251	576	5,589,347	5,589,416
	5,590,346	5,590,437	549	5,588,860	5,589,252	576	5,589,348	5,589,417
	5,590,347	5,590,438	549	5,588,861	5,589,253	576	5,589,349	5,589,418
	5,590,348	5,590,439	549	5,588,862	5,589,254	576	5,589,350	5,589,419
	5,590,349	5,590,440	549	5,588,863	5,589,255	576	5,589,351	5,589,420
	5,590,350	5,590,441	549	5,588,864	5,589,256	576	5,589,352	5,589,421
	5,590,351	5,590,442	549	5,588,865	5,589,257	576	5,589,353	5,589,422
	5,590,352	5,590,443	549	5,588,866	5,589,258	576	5,589,354	5,589,423
	5,590,353	5,590,444	549	5,588,867	5,589,259	576	5,589,355	5,589,424
	5,590,354	5,590,445	549	5,588,868	5,589,260	576	5,589,356	5,589,425
	5,590,355	5,590,446	549	5,588,869	5,589,261	576	5,589,357	5,589,426
	5,590,356	5,590,447	549	5,588,870	5,589,262	576	5,589,358	5,589,427
	5,590,357	5,590,448	549	5,588,871	5,589,263	576	5,589,359	5,589,428
	5,590,358	5,590,449	549	5,588,872	5,589,264	576	5,589,360	5,589,429
	5,590,359	5,590,450	549	5,588,873	5,589,265	576	5,589,361	5,589,430
	5,590,360	5,590,451	549	5,588,874	5,589,266	576	5,589,362	5,589,431
	5,590,361	5,590,452	549	5,588,875	5,589,267	576	5,589,363	5,589,432
	5,590,362	5,590,453	549	5,588,876	5,589,268	576	5,589,364	5,589,433
	5,590,363	5,590,454	549	5,588,877	5,589,269	576	5,589,365	5,589,434
	5,590,364	5,590,455	549	5,588,878	5,589,270	576	5,589,366	5,589,435
	5,590,365	5,590,456	549	5,588,879	5,589,271	576	5,589,367	5,589,436
	5,590,366	5,590,457	549	5,588,880	5,589,272	576	5,589,368	5,589,437
	5,590,367	5,590,458	549	5,588,881	5,589,273	576	5,589,369	5,589,438
	5,590,368	5,590,459	549	5,588,882	5,589,274	576	5,589,370	5,589,439
	5,590,369	5,590,460	549	5,588,883	5,589,275	576	5,589,371	5,589,440
	5,590,370	5,590,461	549	5,588,884	5,589,276	576	5,589,372	5,589,441
	5,590,371	5,590,462	549	5,588,885	5,589,277	576	5,589,373	5,589,442
	5,590,372	5,590,463	549	5,588,886	5,589,278	576	5,589,374	5,589,443
	5,590,373	5,590,464	549	5,588,887	5,589,279	576	5,589,375	5,589,444
	5,590,374	5,590,465	549	5,588,888	5,589,280	576	5,589,376	5,589,445
	5,590,375	5,590,466	549	5,588,889	5,589,281	576	5,589,377	5,589,446
	5,590,376	5,590,467	549	5,588,890	5,589,282	576	5,58	

CLASSIFICATION OF PATENTS

161 377,001	377,019	306 377,037	D21— 31 377,055	239 377,073	128 377,092
202 377,002	205 377,020	311 377,038	48 377,056	243 377,074	135 377,093
223 377,003	377,021	317 377,039	377,057	244 377,075	143 377,094
423 377,004	214 377,022	317 377,040	83 377,058	255 377,076	155 377,095
134 377,005	218 377,023	335 377,041	108 377,059	104 377,077	377,096
147 377,006	377,024	377,042	377,060	107 377,078	168 377,097
377,007	230 377,025	7 377,043	377,061	137 377,079	175 377,098
D14— 100 377,008	257 377,026	12 377,044	377,062	149 377,080	181 377,099
106 377,009	4 377,027	50 377,045	161 377,063	207 377,081	211 377,100
126 377,010	90 377,028	56 377,046	166 377,064	277 377,082	124 377,101
377,011	139 377,029	377,047	204 377,065	393 377,083	377,102
128 377,012	145 377,030	1 377,048	214 377,066	411 377,084	23 377,103
129 377,013	150 377,031	27 377,049	219 377,067	101 377,085	24 377,104
138 377,014	202 377,032	49 377,050	220 377,068	377,086	38 377,105
149 377,015	377,033	51 377,051	221 377,069	104 377,087	62 377,106
151 377,016	377,034	2 377,052	222 377,070	110 377,089	
164 377,017	209 377,035	33 377,053	226 377,071	110 377,090	
191 377,018	304 377,036	40 377,054	236 377,072	121 377,091	

CLASSIFICATION OF PLANTS

P— 18 9,769	51.1 9,771	87.12 9,773	88.1 9,775
48 9,770	82.2 9,772	9,774	

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama.....	1	Kentucky.....	21	Oregon.....	41
Alaska.....	2	Louisiana.....	22	Pennsylvania.....	42
American Samoa.....	3	Maine.....	23	Puerto Rico.....	43
Arizona.....	4	Maryland.....	24	Rhode Island.....	44
Arkansas.....	5	Massachusetts.....	25	South Carolina.....	45
California.....	6	Michigan.....	26	South Dakota.....	46
Canal Zone.....	7	Minnesota.....	27	Tennessee.....	47
Colorado.....	8	Mississippi.....	28	Texas.....	48
Connecticut.....	9	Missouri.....	29	Utah.....	49
Delaware.....	10	Montana.....	30	Vermont.....	50
District of Columbia.....	11	Nebraska.....	31	Virginia.....	51
Florida.....	12	Nevada.....	32	Virgin Islands.....	52
Georgia.....	13	New Hampshire.....	33	Washington.....	53
Guam.....	14	New Jersey.....	34	West Virginia.....	54
Hawaii.....	15	New Mexico.....	35	Wisconsin.....	55
Idaho.....	16	New York.....	36	Wyoming.....	56
Illinois.....	17	North Carolina.....	37	U.S. Air Force.....	57
Indiana.....	18	North Dakota.....	38	U.S. Army.....	58
Iowa.....	19	Ohio.....	39	U.S. Navy.....	59
Kansas.....	20	Oklahoma.....	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

01 :	5,588,251	5,588,263	5,588,891	5,589,382	5,589,779	5,590,219
	5,588,622	5,588,265	5,588,905	5,589,386	5,589,782	5,590,220
	5,588,715	5,588,278	5,588,913	5,589,387	5,589,789	5,590,223
	5,588,779	5,588,298	5,588,914	5,589,392	5,589,798	5,590,224
	5,588,942	5,588,342	5,588,922	5,589,394	5,589,812	5,590,228
	5,588,982	5,588,371	5,588,923	5,589,399	5,589,828	5,590,229
	5,588,987	5,588,377	5,588,939	5,589,409	5,589,831	5,590,250
	5,589,758	5,588,394	5,588,949	5,589,412	5,589,835	5,590,256
	5,588,231	5,588,398	5,588,951	5,589,413	5,589,838	5,590,257
02 :	5,588,355	5,588,403	5,588,960	5,589,415	5,589,847	5,590,259
	5,589,043	5,588,418	5,588,964	5,589,418	5,589,849	5,590,262
	5,588,174	5,588,419	5,588,967	5,589,422	5,589,851	5,590,274
04 :	5,588,431	5,588,440	5,589,002	5,589,440	5,589,855	5,590,282
	5,588,178	5,588,461	5,589,003	5,589,448	5,589,859	5,590,285
	5,588,256	5,588,471	5,589,017	5,589,452	5,589,864	5,590,286
	5,588,387	5,588,476	5,589,018	5,589,464	5,589,870	5,590,294
	5,588,557	5,588,506	5,589,021	5,589,466	5,589,874	5,590,299
	5,588,599	5,588,513	5,589,024	5,589,468	5,589,901	5,590,305
	5,588,800	5,588,532	5,589,042	5,589,480	5,589,937	5,590,308
	5,588,852	5,588,556	5,589,057	5,589,483	5,589,963	5,590,310
	5,588,990	5,588,564	5,589,072	5,589,498	5,589,998	5,590,312
	5,589,402	5,588,613	5,589,076	5,589,511	5,590,003	5,590,321
	5,589,408	5,588,627	5,589,082	5,589,562	5,590,006	5,590,324
	5,589,703	5,588,631	5,589,084	5,589,563	5,590,006	5,590,329
	5,589,749	5,588,637	5,589,095	5,589,565	5,590,027	5,590,331
	5,589,762	5,588,646	5,589,136	5,589,570	5,590,031	5,590,332
	5,589,781	5,588,647	5,589,155	5,589,572	5,590,052	5,590,334
	5,589,829	5,588,651	5,589,167	5,589,574	5,590,059	5,590,337
	5,589,843	5,588,661	5,589,169	5,589,613	5,590,061	5,590,341
	5,590,055	5,588,686	5,589,173	5,589,615	5,590,068	5,590,342
	5,590,063	5,588,705	5,589,180	5,589,653	5,590,069	5,590,351
	5,590,154	5,588,734	5,589,189	5,589,654	5,590,076	5,590,353
	5,590,232	5,588,737	5,589,224	5,589,660	5,590,087	5,590,358
	5,590,239	5,588,738	5,589,233	5,589,666	5,590,089	5,590,359
	5,590,301	5,588,765	5,589,247	5,589,685	5,590,102	5,590,366
	5,590,368	5,588,782	5,589,253	5,589,702	5,590,123	5,590,374
	5,590,395	5,588,790	5,589,274	5,589,709	5,590,124	5,590,375
	Re 35,413	5,588,791	5,589,280	5,589,718	5,590,130	5,590,376
06 :	5,588,153	5,588,792	5,589,328	5,589,726	5,590,162	5,590,377
	5,588,176	5,588,796	5,589,346	5,589,731	5,590,163	5,590,382
	5,588,181	5,588,812	5,589,350	5,589,736	5,590,169	5,590,399
	5,588,199	5,588,815	5,589,359	5,589,737	5,590,182	5,590,406
	5,588,211	5,588,832	5,589,361	5,589,744	5,590,185	5,590,408
	5,588,213	5,588,836	5,589,363	5,589,746	5,590,194	5,590,413
	5,588,214	5,588,843	5,589,367	5,589,756	5,590,195	4,625,557
	5,588,218	5,588,856	5,589,368	5,589,761	5,590,201	4,803,445
	5,588,227	5,588,858	5,589,376	5,589,771	5,590,207	5,587,211
	5,588,237	5,588,862	5,589,377	5,589,774	5,590,209	5,588,158
	5,588,240	5,588,884	5,589,379			

5,588,159	5,588,841	21	5,588,287	5,588,337	5,588,204	5,589,115
5,588,535	5,588,888		5,588,318	5,588,338	5,588,259	5,589,145
5,588,623	5,588,906		5,588,345	5,588,345	5,588,543	5,589,158
5,588,984	5,588,945		5,588,457	5,588,402	5,588,628	5,589,171
5,588,995	5,588,985		5,588,522	5,588,417	5,588,655	5,589,204
5,589,291	5,589,257		5,589,550	5,588,477	5,588,724	5,589,206
5,589,070	5,589,289		5,589,619	5,588,482	5,588,894	5,589,267
5,589,337	5,589,323	22	5,588,249	5,588,502	5,588,921	5,589,302
5,589,536	5,589,842		5,588,301	5,588,514	5,588,940	5,589,305
5,589,878	5,588,487		5,588,516	5,588,516	5,588,955	5,589,322
5,589,600	5,590,012		5,588,974	5,588,572	5,588,969	5,589,332
5,589,802	5,590,171		5,589,059	5,588,640	5,588,972	5,589,341
5,589,833	5,589,338	15	5,589,062	5,588,665	5,588,996	5,589,344
5,589,854	5,589,631		5,589,081	5,588,667	5,589,001	5,589,401
5,589,906	5,588,359	16	5,589,046	5,588,668	5,589,017	5,589,428
5,590,054	5,588,494		5,589,799	5,588,671	5,589,149	5,589,487
5,590,127	5,588,759	23	5,588,276	5,588,672	5,589,154	5,589,504
5,590,136	5,589,311	24	5,588,591	5,588,680	5,589,159	5,589,539
5,590,276	5,589,777		5,588,917	5,588,684	5,589,303	5,589,587
5,590,369	5,588,168	17	5,589,240	5,588,689	5,589,333	5,589,639
Re 35,411	5,588,202		5,589,331	5,588,692	5,589,336	5,589,664
5,588,161	5,588,233		5,589,370	5,588,700	5,589,348	5,589,679
5,588,117	5,588,277		5,589,380	5,588,707	5,589,364	5,589,680
5,588,457	5,588,279		5,589,387	5,588,794	5,589,370	5,589,682
5,588,531	5,588,280		5,589,834	5,588,808	5,589,372	5,589,706
5,588,550	5,588,358		5,589,837	5,588,820	5,589,381	5,589,719
5,588,632	5,588,413		5,589,929	5,588,830	5,589,385	5,589,741
5,588,745	5,588,511		5,590,161	5,588,874	5,589,385	5,589,743
5,588,754	5,588,530		5,590,197	5,588,908	5,589,404	5,589,753
5,588,777	5,588,590		5,590,266	5,588,928	5,589,424	5,589,766
5,588,778	5,588,639	25	5,588,154	5,588,929	5,589,472	5,589,775
5,588,853	5,588,645		5,588,196	5,588,934	5,589,488	5,589,811
5,588,870	5,588,704		5,588,353	5,588,935	5,589,494	5,589,814
5,589,011	5,588,770		5,588,370	5,588,940	5,589,495	5,589,822
5,589,138	5,589,025		5,588,432	5,589,034	5,589,539	5,589,900
5,589,142	5,589,067		5,588,448	5,589,049	5,589,545	5,589,905
5,589,453	5,589,075		5,588,526	5,589,058	5,589,551	5,589,917
5,589,482	5,589,106		5,588,552	5,589,061	5,589,649	5,589,925
5,589,537	5,589,139		5,588,575	5,589,142	5,589,666	5,589,961
5,589,692	5,589,163		5,588,679	5,589,144	5,589,691	5,589,983
5,589,898	5,589,177		5,588,696	5,589,153	5,589,693	5,589,989
5,589,938	5,589,197		5,588,736	5,589,241	5,589,704	5,589,991
5,590,037	5,589,215		5,588,789	5,589,352	5,589,717	5,589,993
5,590,198	5,589,293		5,588,827	5,589,438	5,589,797	5,590,010
5,590,349	5,589,485		5,588,847	5,589,651	5,589,841	5,590,042
5,590,360	5,589,543		5,588,924	5,589,714	5,589,931	5,590,056
5,589,098	5,589,548	10	5,588,958	5,589,805	5,589,974	5,590,071
5,589,100	5,589,560		5,588,962	5,589,823	5,590,084	5,590,090
5,589,147	5,589,796		5,588,968	5,589,884	5,590,121	5,590,118
5,589,208	5,589,804		5,588,971	5,589,904	5,590,125	5,590,141
5,589,218	5,589,893		5,588,994	5,589,915	5,590,126	5,590,147
5,589,489	5,590,038		5,589,015	5,589,979	5,590,147	5,590,170
5,589,166	5,590,129	11	5,588,441	5,590,135	5,588,247	5,590,184
5,588,441	5,590,172	12	5,588,156	5,590,176	5,588,252	5,590,186
5,588,188	5,590,176		5,588,188	5,590,176	5,588,262	5,590,191
5,588,273	5,590,177		5,588,273	5,590,177	5,588,274	5,590,242
5,588,309	5,590,187		5,588,309	5,590,187	5,588,274	5,590,242
5,588,320	5,590,202		5,588,320	5,590,202	5,588,274	5,590,242
5,588,425	5,590,277		5,588,425	5,590,277	5,588,274	5,590,242
5,588,430	5,590,288		5,588,430	5,590,288	5,588,274	5,590,242
5,588,449	5,590,325		5,588,449	5,590,325	5,588,274	5,590,242
5,588,480	5,590,418		5,588,480	5,590,418	5,588,274	5,590,242
5,588,538	4,457,847		5,588,538	4,457,847	5,588,274	5,590,242
5,588,568	5,588,324	18	5,588,568	5,588,324	5,588,274	5,590,242
5,588,594	5,588,507		5,588,594	5,588,507	5,588,274	5,590,242
5,588,610	5,588,521		5,588,610	5,588,521	5,588,274	5,590,242
5,588,663	5,588,654		5,588,663	5,588,654	5,588,274	5,590,242
5,588,681	5,588,659		5,588,681	5,588,659	5,588,274	5,590,242
5,588,690	5,588,731		5,588,690	5,588,731	5,588,274	5,590,242
5,588,699	5,589,010		5,588,699	5,589,010	5,588,274	5,590,242
5,588,761	5,589,037		5,588,761	5,589,037	5,588,274	5,590,242
5,588,788	5,589,301		5,588,788	5,589,301	5,588,274	5,590,242
5,588,886	5,589,326		5,588,886	5,589,326	5,588,274	5,590,242
5,588,892	5,589,357		5,588,892	5,589,357	5,588,274	5,590,242
5,588,911	5,589,501		5,588,911	5,589,501	5,588,274	5,590,242
5,588,961	5,589,530		5,588,961	5,589,530	5,588,274	5,590,242
5,589,238	5,589,665		5,589,238	5,589,665	5,588,274	5,590,242
5,589,327	5,589,675		5,589,327	5,589,675	5,588,274	5,590,242
5,589,353	5,589,824		5,589,353	5,589,824	5,588,274	5,590,242
5,589,520	5,588,171	19	5,589,520	5,588,171	5,588,274	5,590,242
5,589,618	5,588,474		5,589,618	5,588,474	5,588,274	5,590,242
5,589,818	5,588,570		5,589,818	5,588,570	5,588,274	5,590,242
5,589,932	5,588,805		5,589,932	5,588,805	5,588,274	5,590,242
5,589,945	5,588,895		5,589,945	5,588,895	5,588,274	5,590,242
5,590,156	5,588,943		5,590,156	5,588,943	5,588,274	5,590,242
5,590,221	5,589,199		5,590,221	5,589,199	5,588,274	5,590,242
5,590,260	5,589,605		5,590,260	5,589,605	5,588,274	5,590,242
5,590,373	5,589,611		5,590,373	5,589,611	5,588,274	5,590,242
Re 35,412	5,589,612		Re 35,412	5,589,612	5,588,274	5,590,242
5,588,155	5,590,041	13	5,588,155	5,590,041	5,588,274	5,590,242
5,588,203	5,590,181		5,588,203	5,590,181	5,588,274	5,590,242
5,588,266	5,590,346		5,588,266	5,590,346	5,588,274	5,590,242
5,588,397	5,588,157	20	5,588,397	5,588,157	5,588,274	5,590,242
5,588,399	5,588,222		5,588,399	5,588,222	5,588,274	5,590,242
5,588,446	5,588,325		5,588,446	5,588,325	5,588,274	5,590,242
5,588,583	5,588,382		5,588,583	5,588,382	5,588,274	5,590,242
5,588,621	5,588,439		5,588,621	5,588,439	5,588,274	5,590,242
5,588,624	5,588,585		5,588,624	5,588,585	5,588,274	5,590,242
5,588,638	5,588,617		5,588,638	5,588,617	5,588,274	5,590,242
5,588,712	5,588,771		5,588,712	5,588,771	5,588,274	5,590,242
5,588,896	5,588,334		5,588,896	5,588,334	5,588,274	5,590,242
5,588,747	5,590,192		5,588,747	5,590,192	5,588,274	5,590,242

	5,588,981	5,588,649	5,588,889	5,589,417	5,590,338	5,588,610
	5,588,992	5,588,693	5,588,941	5,589,420	5,590,343	5,588,648
	5,589,036	5,588,844	5,588,970	5,589,423	5,590,350	5,588,959
	5,589,097	5,588,849	5,589,027	5,589,442	5,590,352	5,589,016
	5,589,104	5,588,861	5,589,066	5,589,443	5,590,363	5,589,030
	5,589,107	5,588,866	5,589,126	5,589,446	5,590,367	5,589,164
	5,589,113	5,588,877	5,589,356	5,589,451	5,590,378	5,589,211
	5,589,160	5,588,878	5,589,528	5,589,540	5,590,402	5,589,256
	5,589,216	5,588,907	5,589,566	5,589,542	5,588,340	5,589,407
	5,589,230	5,588,952	5,589,844	5,589,568	5,588,452	5,589,444
	5,589,243	5,588,978	5,590,104	5,589,579	5,588,472	5,589,456
	5,589,276	5,589,009	5,590,215	5,589,602	5,588,475	5,589,512
	5,589,285	5,589,020	5,590,391	5,589,633	5,588,634	5,589,776
	5,589,301	5,589,028	5,588,205	5,589,642	5,588,669	5,589,861
	5,589,332	5,589,065	5,588,224	5,589,695	5,588,670	5,589,866
	5,589,341	5,589,085	5,588,230	5,589,697	5,588,676	5,589,928
	5,589,401	5,589,101	5,588,241	5,589,708	5,588,688	5,590,046
	5,589,428	5,589,152	5,588,389	5,589,728	5,589,118	5,590,267
	5,589,487	5,589,183	5,588,390	5,589,747	5,589,120	5,590,318
	5,589,504	5,589,198	5,588,438	5,589,763	5,589,176	5,590,322
	5,590,240	5,589,217	5,588,445	5,589,765	5,589,340	5,590,336
	5,590,383	5,589,240	5,588,453	5,589,773	5,589,351	5,590,347
	4,642,317	5,589,431	5,588,491	5,589,783	5,589,584	5,590,389
	5,588,290	5,589,458	5,588,529	5,589,784	5,590,002	5,590,410
	5,588,386	5,589,505	5,588,558	5,589,794	5,590,149	5,589,157
	5,588,459	5,589,519	5,588,593	5,589,800	5,588,551	5,589,538
	5,588,467	5,589,525	5,588,615	5,589,830	5,589,707	5,589,630
	5,588,488	5,589,595	5,588,662	5,589,852	5,590,093	5,588,216
	5,588,489	5,589,599	5,588,678	5,589,891	5,588,160	5,588,217
	5,588,776	5,589,628	5,588,685	5,589,935	5,588,261	5,588,238
	5,589,161	5,589,832	5,588,687	5,590,014	5,588,542	5,588,295
	5,588,522	5,589,892	5,588,713	5,590,020	5,588,548	5,588,376
	5,588,723	5,589,897	5,588,772	5,590,021	5,588,620	5,588,392
	5,588,728	5,589,958	5,588,781	5,590,023	5,588,629	5,588,451
	5,588,904	5,589,993	5,588,784	5,590,025	5,588,752	5,588,496
	5,589,131	5,590,017	5,588,785	5,590,029	5,588,820	5,588,510
	5,589,150	5,590,140	5,588,786	5,590,032	5,588,833	5,588,537
	5,589,229	5,590,379	5,588,816	5,590,057	5,589,012	5,588,596
	5,589,623	5,590,384	5,588,818	5,590,065	5,589,119	5,588,644
	5,589,791	5,590,386	5,588,848	5,590,083	5,589,141	5,589,014
	5,589,865	Re 34,957	5,588,901	5,590,119	5,589,182	5,589,109
	5,589,869	5,589,868	5,588,903	5,590,134	5,589,249	5,589,122
	5,589,933	5,590,281	5,588,916	5,590,175	5,589,604	5,589,187
	5,590,128	5,588,167	5,588,947	5,590,188	5,589,640	5,589,294
	5,590,141	5,588,282	5,588,975	5,590,234	5,589,856	5,589,457
	5,590,289	5,588,354	5,589,063	5,590,241	5,590,300	5,589,606
	5,590,297	5,588,420	5,589,073	5,590,264	5,588,352	5,589,616
	Re 35,410	5,589,254	5,589,112	5,590,284	5,588,383	5,589,644
	5,588,308	5,589,716	5,589,128	5,590,287	5,588,393	5,589,671
	5,588,321	5,589,725	5,589,184	5,590,292	5,588,427	5,590,205
	5,588,436	5,588,239	5,589,185	5,590,304	5,588,433	5,588,314
	5,588,462	5,588,343	5,589,231	5,590,307	5,588,444	
	5,588,490	5,588,443	5,589,284	5,590,313	5,588,464	
	5,588,541	5,588,505	5,589,329	5,590,315	5,588,540	
	5,588,546	5,588,578	5,589,416	5,590,316	5,588,554	
	5,588,565	5,588,810	5,589,416	5,590,330	5,588,595	
40 :						
41 :						
42 :						
44 :						
45 :						
46 :						
47 :						
50 :						
51 :						
53 :						
54 :						
55 :						
56 :						

VOL
11 93

ISS
5

DE
31

19 96

UMI

CHANGE OF ADDRESS FORM

NAME- FIRST, LAST																							
COMPANY NAME OR ADDITIONAL ADDRESS LINE																							
STREET ADDRESS																							
CITY												STATE						ZIP CODE					
PLEASE PRINT OR TYPE																							
(or) COUNTRY																							

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

Attach last subscription
label here.

UMI

Important: Please be sure to include this completed order form with your remittance.

**Thank you for
your order!**

VOL
11 93

ISS
5

DE
31

1996

UMI

VOL
11 93


ISS
5

DE
31

1996

UMI

U.S. DEPARTMENT OF COMMERCE
Michael Kantor, *Secretary*
PATENT AND TRADEMARK OFFICE
Bruce Lehman, *Commissioner*



END